RIO GRANDE RESOURCES CORPORATION

September 8, 2026

Mr. Abimbola Ojekanmi
Uranium Mine Reclamation Coordinator
Mining Act Reclamation Program
Mining and Minerals Division
New Mexico Energy Minerals and Natural Resources Department
1220 South St. Francis Dr.
Sante Fe, NM 87502

RE: Rio Grande Resource's Response to March 18, 2026 Comments from Mining Environmental Compliance Section of the New Mexico Environment Department for Closeout/Closure Plan, Revision 22-1 Permit No. CI002RE

Dear Mr. Ojekanmi,

Rio Grande Resources Corporation (RGR) is submitting the enclosed Update of the Closure/Closeout Plan, Revision 22-2, for the Mt. Taylor Mine (Permit No. CI002RE). This revision has been prepared in response to the comments provided by the Mining and Minerals Division (MMD) in its March 18, 2026 comment letter.

Also enclosed is a separate Response to Comments document that addresses each of MMD's comments and identifies the corresponding revisions made to the Closure/Closeout Plan.

RGR appreciates MMD's review of this submittal and looks forward to continuing to work with the Department throughout the review process. If you have any questions or require additional information, please contact me.

Respectfully Submitted,
**Rio Grande Resources Corporation**



Jeff Schoenbacher
Reclamation Manager

CC
Clinton Chisler, Senior Reclamation Supervisor, EMNRD-MARP-MMD
David Ennis, Program Manager, EMNRD-MMD
Corey Dimond, Site Lead, NMED-MECS
Joseph Fox, MECS Program Manager, NMED-MECS
Kevin Raabe, President, RGR
Anita Willcox, Site Supervisor, RGR
Melissa Meyer, Project Manager, EA

RIO GRANDE RESOURCES CORPORATION
MT. TAYLOR MINE
PO BOX 1150
4899 W. HWY 605 GRANTS, NM 87020
TEL (505) 287-7971

# September 2026 Rio Grande Resources Response to Comments from MMD For Closeout/Closure Plan, Revision 22-1

# Mt. Taylor Mine, Permit No. CI002RE San Mateo, New Mexico

***Prepared for:***
Abimbola Ojekanmi
Uranium Reclamation Coordinator
Mining Act Reclamation Program
Mining and Minerals Division

*Prepared by:*

Engineering Analytics, Inc.
1600 Specht Point Road, Suite 209
Fort Collins, Colorado 80525
(970) 488-3111

**On behalf of Mt. Taylor and Rio Grande Resources:**

Kevin Raabe
President, RSO
Rio Grande Resources Corporation

Project No. 111360
*September 8, 2026*
*Rev. 1.0*

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| **Comment Letter, Mt. Taylor Mine, Update of Closure/Closeout Plan, Revision 22-1, Permit No. CI002RE (March 18, 2026)** | | | | | |
| 1 | Chapter 1 | Page 5, Para. 5 | **MMD "Comment 1" (March 18, 2026):**<br>Chapter 1, Page 5, Paragraph 5, claimed: The discharged water flowed northward from the San Lucas Canyon and disappeared approximately 22 miles from the point of discharge after comingling with the San Miguel Creek drainage system. What are RGR's plans to further investigate, characterize, and reclaim San Lucas Canyon? Can you provide information that describes the nature of investigation that will be completed in both San Lucas Canyon and San Miguel Creek; or a summary of existing investigations that will inform some remediation/reclamation of the Canyon? | The statement regarding treated mine water flowing approximately 22 miles downstream has been removed from the CCP. Upon review of the historical investigation reports, RGR did not identify documentation supporting this specific distance. The text has been revised to describe the historical downstream investigations that were completed without making an unsupported statement regarding the extent of historical surface water flow.<br>Additional discussion of the historical investigations completed downstream of Outfall 001 has been incorporated into Section 1.3.5 and 4.4.5, including the 2013 and 2014 investigations of soils, surface water, groundwater, sediment, and downstream impoundments. These investigations generally concluded that historical treated mine water discharges did not result in significant downstream environmental impacts requiring additional characterization at that time.<br>As part of the mine closure program, RGR is planning additional characterization of the San Lucas Canyon area immediately downstream of Outfall 001 to further evaluate the localized area of elevated gamma radiation identified during the 2020 radiological survey. AVM is currently preparing a work plan describing the proposed characterization activities. The results of the characterization will be used to determine whether remedial actions are warranted and to support completion of closure activities at Outfall 001.<br>Based on the historical investigations completed to date, additional investigation of San Miguel Creek is not currently planned. If the planned characterization identifies conditions that warrant further evaluation beyond the immediate Outfall 001 area, the scope of investigation will be expanded, as appropriate, in coordination with NMED. | |
| 2 | Chapter 3 | Page 47 | **MMD "Comment 2" (March 18, 2026):**<br>Chapter 3, Page 47: The shaft plugs as configured will need to include space for monitoring devices and sensors as may be required by NMED and OSE in the future. How does RGR intend to accommodate monitoring devices in the plug design? | Text updated in Section 4.3.1. With future design, the shaft plug design will identify a secondary sampling port. Both ports will be sized appropriately to accommodate the necessary monitoring devices and sensors required by NMED and OSE. | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 3 | Chapter 4 | Page 26 to 27 | **MMD "Comment 3" (March 18, 2026):**<br>Chapter 4. Page 26 to 27: RGR intends to dispose of solid waste into either expanded disposal cells or offsite the facility. This implies that RGR classify waste generated from this closure operation into 2 broad groups, depending on the radiological properties. Also, RGR seems to be working under the assumption that there are only 2 broad classes of waste - based on radiological characterization. What are RGR's plans to manage more complex waste mixtures if there are more than 2 types of waste - e.g. organic/inorganic wastes, radiological and non-radiological wastes, complex mixtures of radio-impact soil-heavy metal, etc. Specifically, MMD is interested in cell design as related to radiologically contaminated soils combined with the diesel contaminated soils on-site. | RGR acknowledges that the CCP text may have implied a binary waste classification. In practice, RGR employs a multi-tiered waste classification protocol that considers radiological, chemical, and physical properties. The *Evaluation of Diesel Placement in Proposed Expanded Disposal Cell* (EA, 2026f) provides a comprehensive assessment specifically addressing the co-placement of diesel-impacted and radiologically elevated soils. Key findings are as follows:<br>1. Diesel-impacted soils at the site do not meet the definition of hazardous waste under RCRA — they are not listed wastes and do not exhibit hazardous characteristics (ignitability, corrosivity, reactivity, or toxicity per TCLP).<br>2. A spatial analysis confirms that elevated diesel concentrations (exceeding the NMED industrial SSL of 3,000 mg/kg TPH-DRO) do not spatially coincide with radiological hotspots (Ra-226 > 20 pCi/g). Therefore, the material does not constitute mixed radioactive and RCRA hazardous waste.<br>3. Where both contaminants co-occur (e.g., Mine Compound), diesel concentrations are well below the SSL (≤170 mg/kg).<br>4. The expanded disposal cell's design — clay liner, radon-attenuating cover, and long-term monitoring — is technically compatible with both waste streams.<br>If additional waste streams or more complex waste mixtures are identified during ongoing characterization, they will be evaluated using the same multi-parameter waste classification process. Waste management and disposal requirements will be determined based on the applicable regulatory criteria and the physical and chemical characteristics of the material.<br>The CCP has been revised to reflect this multi-tiered waste classification framework. | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 4 | Chapter 4 | Page 27 | **MMD "Comment 4" (March 18, 2026):**<br>Chapter 4. Page 27. Can you confirm how long RGR intends to keep waste materials in the proposed staging areas? Please provide an overlay map of the proposed staging areas and how they will be protected from surface water or precipitation. | Waste materials stored within the three proposed staging areas will be managed on a temporary basis. The timing for relocation of staged waste materials to the expanded disposal cell will be determined as the sequencing of closure activities and disposal cell construction is finalized. Staged materials will be relocated to the expanded disposal cell as practical during implementation of the closure activities. The locations of the three NMED-approved staging areas and the surrounding stormwater drainage patterns are reflected in Figure 4-2 of the submittal. While the staging areas are open to direct precipitation, they are protected from surface water run-on and runoff through the following measures:<br>• **Siting:** The staging areas have been intentionally placed outside of concentrated surface water flows and within footprints previously approved by NMED in 2024 (NMED, 2024).<br>• **Runoff Controls:** Stormwater runoff from these areas is fully managed by the onsite stormwater engineering upgrades completed under the MMD-approved Permit No. CI002RE.<br>• **Permit Compliance:** These upgrades were specifically designed and constructed to support National Pollutant Discharge Elimination System (NPDES) compliance. They provide run-off controls and increased surface water retention capacity within the mine area. These controls are engineered to remain effective across all phases: active operating status, post-mining land use, and the long-term, post-closeout period. | |
| 5 | NA | NA | **MMD "Comment 5" (March 18, 2026): Mount Taylor Expanded Cell Design (June 06, 2025)**<br>Page 15: RGR uses the word "store and release, earthen cover system". Can RGR elaborate on the actual meaning and engineering implications of such cover system. Does this term imply an evapo-tranpirative (ET) cover? | The term "store and release" as used on Page 15 of the *Mt. Taylor Expanded Cell Design* (EA, June 2025) does indeed describe a cover system that functions on evapotranspiration (ET) principles, consistent with the terminology used in the New Mexico Copper Rule (20.6.7.33 NMAC). Specifically, a store-and-release cover is an earthen cover designed to temporarily store precipitation within the soil profile, then remove it through evapotranspiration, minimizing percolation into the underlying waste. | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 6 | NA | NA | **MMD "Comment 6" (March 18, 2026): Mount Taylor Expanded Cell Design (June 06, 2025)**<br>Section 4.12: Can RGR elaborate on the functional implications of such ET cover system and how proposed cell extension will affect or complement the function of existing cover system. | The ET cover system for the proposed cell extension is designed to function in an integrated and complementary manner with the existing cover. Functionally, the store-and-release (ET) cover operates through three primary mechanisms:<br>1. **Surface interception and runoff**: The 12-inch rock mulch layer dissipates raindrop energy, reduces surface sealing, and promotes lateral runoff rather than infiltration.<br>2. **Soil moisture storage:** The 25-inch in-situ soil layer temporarily stores infiltrating water within its pore structure. Nominal AWHC is 0.10 $cm^3/cm^3$, yielding 2.50 inches of total storage capacity.<br>3. **Evapotranspiration removal**: While not required, the native vegetation, which is adapted to semi-arid conditions, draws moisture upward and releases it to the atmosphere via transpiration. The 12-inch clay radon barrier beneath the in-situ soil layer provides the final low-permeability boundary, preventing downward percolation (saturated hydraulic conductivity maintained per design).<br>The extended cover will tie into the existing cover along a designed transition zone, maintaining grade continuity, surface drainage patterns, and erosional stability. The existing cover's functions, which include radon attenuation, frost protection, erosion resistance, and infiltration control, are not diminished by the extension. Rather, the extension expands the protected footprint, reducing the area of unlined, impacted soils. The report revised by EA has included a more detailed functional description of the ET mechanism and the design interface with the existing cover. | |
| 7 | NA | NA | **MMD "Comment 7" (March 18, 2026): Mount Taylor Expanded Cell Design (June 06, 2025)**<br>Page 38, Fig 4.3: This figure claimed 1,093,840 volumes of storage will be created in the extension. Is this volume in cubic feet, cubic yard or m3. | The volume of 1,093,840 reported in Figure 4.3 of the *Mt. Taylor Expanded Cell Design* (EA, June 2025) is in cubic yards ($yd^3$). This value represents the total engineered storage capacity of the combined existing Waste Rock Pile (WRP) and the proposed disposal cell expansion.<br>The figure caption and associated text in the revised report has been updated to clarify the unit as cubic yards ($yd^3$) to eliminate any ambiguity. | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 8 | NA | NA | **MMD "Comment 8" (March 18, 2026): Comments on Geotechnical Analysis of Borrow Sites**<br>RGR collected samples from three different test pits/locations as shown in Fig 1. Geotechnical analysis of samples was completed, but the data were not presented in spatial dimensions. If these data were projected spatially, can RGR confirm that there are sufficient fine graded soil materials within each of the 3 locations, such that each area has sufficient materials suitable as impermeable covers (clay) for the storage cells? | RGR acknowledges that the geotechnical data from the three borrow site test pits were presented in tabular form without explicit spatial projection. The three borrow locations (Borrow Areas A, B, and C) were selected based on field reconnaissance identifying zones of fine-grained soil within each area. Laboratory testing confirmed that samples from all three locations meet the geotechnical criteria for use as low-permeability cover material — specifically, Atterberg limits, particle size distribution, and compacted hydraulic conductivity consistent with the design requirement ($k \leq 1\times10^{-7}$ cm/s). The infiltration and stability analyses in the updated analysis used material properties derived from this borrow program (dry density ~1.51–1.59 g/cm³, porosity 0.35–0.38, etc.).<br>To directly address MMD's question: RGR confirms that based on field observations, test pit logs, and the spatial extent of each borrow area as shown in Figure 1 of the borrow site report, there is sufficient fine-grained material within each of the three locations to supply the clay cover material needed for the disposal cell construction.<br>A revised borrow site analysis section spatially maps the fine-grained soil zones within each borrow area and provides estimated volume yield calculations, confirming material adequacy. | |
| 9 | NA | NA | **MMD "Comment 9" (March 18, 2026): Comments on Geotechnical Analysis of Borrow Sites**<br>For areas deemed suitable as borrow sources of cover material, RGR should produce the radiological distribution of such areas to ensure that materials deemed suitable for cover soils based on geotechnical analysis do not have high radiological properties above the critical limit of 6.8 pCi/g. | Acknowledged. The report has been updated to include the radiological distribution for the areas identified as potential borrow sources. A discussion has also been added to the appropriate section describing the radiological characterization of the borrow areas and confirming that only materials meeting the applicable radiological criteria for use as cover material will be used in the final cover system. | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 10 | NA | NA | **MMD "Comment 10" (March 18, 2026): Comments on Geotechnical Analysis of Borrow Sites**<br>RGR should include one or two paragraphs in this section, on how RGR intend to borrow soils that are suitable (from operation perspective, considering geology is not 100% clay), and exclude unsuitable cover materials from the same area. | RGR agrees with MMD's recommendation and has included a description of the operational protocol in the revised Geotechnical Analysis of Borrow Sites. The borrow site geology at Mt. Taylor is heterogeneous and includes fine grained silty clays, sandy silts, coarser gravels, and volcanic materials. Not all materials within the borrow footprint are suitable for use as low permeability cover. The following operational protocol will guide borrow site excavation and material selection:<br>1. **Pre excavation screening**: Before large scale excavation begins, each borrow area will be systematically test pitted at a spacing determined by the site geologist to map the lateral and vertical extent of fine grained and coarse-grained zones. GPS coordinates and elevations of suitable zones will be recorded.<br>2. **Field identification and segregation**: During active borrowing operations, a qualified soils technician or geologist will be present to perform visual classification and field testing, such Atterberg limits screening, on excavated materials. Materials that do not meet field classification criteria, such as excessive gravel content or a low plasticity index, will be segregated and stockpiled separately for use as noncritical fill or erosion armor.<br>3. **Quality assurance and quality control verification**: Representative samples of accepted material will be submitted for laboratory testing, including grain size analysis, Atterberg limits, compaction, and hydraulic conductivity, at a minimum frequency specified in the Construction Quality Assurance Plan.<br>4. **Stockpile management**: Accepted fine grained materials will be stockpiled on lined or protected areas and covered to prevent moisture loss or contamination before placement.<br>These procedures ensure that only geotechnically suitable materials are incorporated into the engineered cover system despite the natural variability of the borrow source geology. This description has been incorporated into the revised Geotechnical Analysis of Borrow Sites. | |

RIO GRANDE RESOURCES CORPORATION

September 8, 2026

Mr. Corey Dimond
Mining Environmental Compliance Section
Ground Water Quality Bureau – Water Protection Division
New Mexico Environment Department
Harold Runnels Building
1190 Saint Francis Drive
P.O. Box 5469
Santa Fe, New Mexico 87502

RE: Rio Grande Resource's Response to March 6, 2026 Comments from the Mining Environmental Compliance Section of the New Mexico Environment Department for Closeout/Closure Plan, Revision 22-1 Permit No. CI002RE

Dear Mr. Dimond,

Rio Grande Resources Corporation (RGR) is submitting the enclosed Update of the Closure/Closeout Plan, Revision 22-2, for the Mt. Taylor Mine (Permit No. CI002RE). This revision has been prepared in response to the comments provided by the Mining Environmental Compliance Section (MECS) of the New Mexico Environment Department (NMED) in its March 6, 2026 comment letter. Additionally, we have incorporated responses to the February 19, 2026, comments provided by the NMED Surface Water Quality Bureau (SWQB).

Also enclosed is a separate Response to Comments document that addresses each of the MECS and SWQB comments and identifies the corresponding revisions made to the Closure/Closeout Plan.

RGR appreciates MECS's review of this submittal and looks forward to continuing to work with the Department throughout the review process. If you have any questions or require additional information, please contact me.

Respectfully Submitted,
**Rio Grande Resources Corporation**

Jeff Schoenbacher
Reclamation Manager

RIO GRANDE RESOURCES CORPORATION
MT. TAYLOR MINE
PO BOX 1150
4899 W. HWY 605 GRANTS, NM 87020
TEL (505) 287-7971

RIO GRANDE RESOURCES CORPORATION

CC
Joseph Fox, MECS Program Manager, NMED-MECS
Alan Klatt, Watershed Protection Section, NMED-SWQB
Abimbola Ojekanmi, Uranium Reclamation Coordinator, EMNRD-MMD
Clinton Chisler, Senior Reclamation Supervisor, EMNRD-MARP-MMD
David Ennis, Program Manager, EMNRD-MMD
Kevin Raabe, President, RGR
Anita Willcox, Site Supervisor, RGR
Melissa Meyer, Project Manager, EA

RIO GRANDE RESOURCES CORPORATION
MT. TAYLOR MINE
PO BOX 1150
4899 W. HWY 605 GRANTS, NM 87020
TEL (505) 287-7971

# September 2026 Rio Grande Resources Response to Comments from MECS For Closeout/Closure Plan, Revision 22-1

# Mt. Taylor Mine, Permit No. CI002RE San Mateo, New Mexico

***Prepared for:***
Corey Dimond
New Mexico Environmental Department
Ground Water Bureau
Mining Environmental Compliance Section

*Prepared by:*

Engineering Analytics, Inc.
Now Part of MacKay

Engineering Analytics, Inc.
1600 Specht Point Road, Suite 209
Fort Collins, Colorado 80525
(970) 488-3111

**On behalf of Mt. Taylor and Rio Grande Resources:**

Kevin Raabe
President, RSO
Rio Grande Resources Corporation

Project No. 111360
*September 8, 2026*
*Rev. 1.0*

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| **Comment Letter, New Mexico Environment Department (NMED) Comments, Mt Taylor Uranium Mine, Updated Closure Closeout Plan, Mining Act Permit No. CI002RE** | | | | | |
| 1 | 1.3 | NA | **MECS "Comment 1" (March 6, 2026):**<br>2025 Closure/Closeout Plan, 1.3 Project History – The document could be improved with a figure showing pre-1971 disturbance that will not be addressed as part of the 2025 CCP. | RGR evaluated the availability of information to prepare a figure depicting pre-1971 disturbances. Although historical records indicate that exploratory drill pads and access roads existed prior to 1971, the locations of these historical disturbances were not documented and are not known with sufficient accuracy to develop a representative figure. Therefore, a figure has not been included. Section 1.3 has been revised to clarify the historical existence of these exploration disturbances and to reference the December 17, 1997, U.S. Forest Service recommendation regarding their reclamation. | |
| 2 | 1.3.5 | NA | **MECS "Comment 2" (March 6, 2026):**<br>2025 Closure/Closeout Plan, 1.3.5 Mine Water Treatment, Pumping, and Discharge– The Radiological Surveys of Discharge Pipeline report dated July 6, 2020, identifies an area of localized elevated gamma radiation at the discharge pipeline endpoint Outfall 001 that may be contaminated in excess of the 6.8 pCi/g site standard. Please account for any remaining soil impacts here to the volume of material requiring disposal. If all impacted soil has been removed, please provide the final gamma survey for the area of Outfall 001 to ensure reclamation is complete. | A comprehensive radiological evaluation of the Outfall 001 area has not yet been completed. In addition, the discharge pipeline removal work did not include excavation or removal of the radiologically impacted soil identified at Outfall 001. Consequently, the extent of any residual radiological contamination and the associated volume of material requiring management or disposal cannot currently be quantified.<br>The Outfall 001 area will be included in future closure characterization activities to determine the nature and extent of any remaining radiological impacts. Based on the results of that characterization, the volume of soil requiring excavation and disposal, if any, will be determined to support completion of reclamation and site closure. If any material is identified to be removed, it would be done when the disposal cell was ready to accept material. | |
| 3 | 3.3.4 | NA | **MECS "Comment 3" (March 6, 2026):**<br>2025 Closure/Closeout Plan, 3.3.4 Radiological levels for PMLU – This section references Nuclear Regulatory Commission (NRC) Regulatory Guide 1.86 criteria for radioactive contamination in habitable buildings. However, NRC guidance is not applicable in this case. Instead, MMD's 2016 joint guidance of 5 pCi/g Ra-226 above background (6.8 pCi/g at the site) should be applied. | The MMD 2016 joint guidance specifies the criteria for Ra-226 only for impacted soil cleanup. It does not specify any criteria for radiologic surface contamination limits for the release of equipment, material, and facilities. In the absence of MMD- or NMED-specific radiologic surface contamination release criteria for facilities, RGR has applied the conservative gross alpha surface contamination limit of 5,000 dpm/100 cm² contained in the MMD-approved March 2021 Site Radiation Protection Program Manual. The MMD requested that the gross alpha surface contamination limit for the PMLU at the Site would not exceed the dose limit of 100 mrem/yr.<br>In the 12/27/2021 Addendum to *Work Plan for Post-Mining Radiological Surveys of Permit Area and Impacted Lands*, RGR calculated the radiologic release criteria consistent with the 25 mrem/yr radiological dose-based criterion for license termination and unrestricted use from Title 20, Chapter 3, Part 4, Subpart 426.B of the New Mexico Administrative Code (NMAC). The gross alpha surface contamination limit for the release of facility at the dose limit of 25 mrem/yr was calculated to be 2,364 dpm/100 cm². For a 100 mrem/yr dose limit, the gross alpha surface contamination would be 9,456 dpm/100 cm². This is because the relationship between surface contamination and dose is linear. However, RGR proposes the gross alpha surface contamination limit of 5,000 dpm/100 cm², as specified in NRC Regulatory Guide 1.86, which is well below the 9,456 dpm/100 cm² calculated based on the 100 mrem/yr dose. In addition, the gross alpha surface contamination limit of 5,000 dpm/100 cm² is specified in the MMD-approved March 2021 *Site Radiation Protection Program Manual*. | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 4 | 4.3.1 | NA | **MECS "Comment 4" (March 6, 2026):**<br>2025 Closure/Closeout Plan, 4.3.1 Shaft Plugging – NMED continues to have concerns regarding the long-term integrity of the shafts in relation to water quality. Procedures outlined in Appendix C.3 of the 2022 CCP continue to be referenced in the 2025 CCP. Appendix C.3 states "The remainder of the shaft, as well as connecting tunnels and raises, shall be backfilled with a cementitious slurry of soil, Portland cement, fly ash, and water". However, the volume of material to be added and the final backfill depth within the shaft have not been clearly specified. Water seepage has been documented at construction joints and horizontal cracks observed in the sub collar portion of the shaft, and the proposed concrete plugs will not extend to or seal all of these areas. NMED still remains concerned with the long-term stability of the shaft walls, due to potential concrete degradation and the potential lowering of the current water levels in the shafts due to future mining operations nearby. The added weight of the plugs on the shaft concrete is also concerning, given the documented degradation of the underlying shaft concrete. Additionally, NMED requests that a plan be developed for monitoring shaft water levels and water quality following backfilling of the shafts and plugging activities. The current Structural Design of Shaft Plugs diagrams in Appendix G indicate a steel pipe intended to function as a sampling well. Please provide additional details describing how a monitoring well will be incorporated in the final plug design. Also, the plan shall provide for additional new monitoring wells located in close proximity to the shafts, within each aquifer intersected by the shafts. This is required for monitoring groundwater quality and protection the surrounding aquifers. | The shaft plugging design consists of constructing a structural plug at the subcollar level. Following construction of the structural plug, controlled low-strength material (CLSM) backfill will be placed only within the shaft interval above the structural plug, as shown on the shaft closure drawings. The final plug elevations, backfill limits, and associated backfill material volumes will be refined during final design and documented in future design submittals. Refer to Appendix G, Drawings C/100 and C/200, and the associated shaft closure design details for the conceptual plug and backfill configuration.<br>To address the observed near surface sub-collar seepage, field evaluations are currently being conducted under the 2025 approved *Site Investigation Plan* (EA, 2025a); it is anticipated that a targeted plan to seal off this seepage will be developed based on these findings.<br>Furthermore, to address concerns regarding plug stability and the added weight on the legacy shaft concrete, the final shaft closure design will incorporate measures to transfer the structural loads from the shaft plug into competent host rock, such as engineered horizontal keyways, or another engineered approach determined during final design. The final design will support the plug independently of the existing shaft walls and minimize reliance on the long-term integrity of the shaft concrete or future regional water-level fluctuations. The final shaft closure design will be submitted to NMED for review and approval prior to construction.<br>The *Post-Closure Monitoring Plan* (PCMP) will be updated to address long-term monitoring of groundwater levels and water quality following shaft plugging activities. The updated monitoring program will include proposed monitoring wells in the vicinity of the shafts, as appropriate, and will be submitted to NMED for review and approval prior to implementation.<br>Two redundant, structurally isolated steel monitoring ports will be incorporated into each individual shaft plug to provide redundant groundwater sampling access. The final monitoring port design will be included in the final shaft plugging design submitted for agency review. | |
| 5 | 4.4.2 | NA | **MECS "Comment 5" (March 6, 2026):**<br>2025 Closure/Closeout Plan, 4.4.2 Disposal Cell and Expansion - In Permit Condition 32 of DP-61 dated October 14, 2015, NMED requires RGR to document the construction quality assurance (CQA) of all clay liners and caps of the disposal cell. Please add the following language from Permit Condition 32 to the updated 2025 CCP. "CQC and CQA plans shall be submitted to NMED for approval a minimum of 30 days prior to beginning of construction of the clay liner. Within 60 days following completion of construction of the clay liner, a CQA report and as-built plans shall be submitted to NMED." | This language has been added to Section 4.4.2 of the CCP and the *Expanded Disposal Cell Design* report (Appendix K). | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 6 | NA | Page T-30<br>Table 4-3 | **MECS "Comment 6" (March 6, 2026):**<br>2025 Closure/Closeout Plan, Former Lagoon, Table 4-3, Page T-30 – The former sewage lagoon was mentioned as a possible source of elevated nitrate in monitoring well WP-5 in the Stage 1 Abatement Plan in 2005. In the 2021 Site Investigation Plan (2021 SIP), RGR had originally proposed to excavate the sediments and waste rock in the former sewage lagoon and surrounding area to remove any uranium and nitrate source material. Currently, RGR estimates that approximately 10,680 cubic yards of sediment and waste rock are present in the former lagoon. This volume has been added to Table 4-3 of the updated 2025 CCP and is listed as Sediment and Waste Rock in the Former Lagoon. A note in Table 4-3 states, "Volumes associated with the former lagoon are included per NMED request. It is not likely that the material will be excavated and transferred to the disposal cell." Please clarify whether excavation of the former lagoon material is a planned activity. If so, describe how the work would be conducted and coordinated with disposal cell expansion activities. In addition, please propose a plan to for additional source characterization and removal delineation. | The sediment and waste rock within the former lagoon have been included in the estimated disposal cell volume in response to NMED's request. However, excavation of this material is not currently identified as a planned closure activity.<br>The need to excavate the former lagoon material will be evaluated as additional information becomes available. One consideration is whether the material could adversely affect the final disposal cell design or long-term performance, since the former lagoon is located beneath the proposed disposal cell footprint. A second consideration is whether future Site Investigation Plan (SIP) investigations and subsequent groundwater abatement activities indicate that the former lagoon sediments and waste rock represent a continuing source of groundwater impacts that cannot be addressed through other remedial measures. If future investigations determine that removal of the material is necessary, a source characterization and removal delineation will be completed to define the extent of material requiring excavation. If needed, the excavation approach and coordination with disposal cell construction activities will be developed as part of the final closure design and submitted to NMED for review and approval. | |
| 7 | NA | NA | **MECS "Comment 7" (March 6, 2026):**<br>2025 Closure/Closeout Plan, Lack of Abatement Strategy - Current abatement activities (i.e., shallow extraction wells, etc.) have not fulfilled abatement per NMAC 20.6.2.4103. While the upcoming site investigation activities related to the approved 2025 Revised Site Investigation Plan will help better define the extent of the shallow groundwater plume, they do not address all components necessary of site-wide abatement. Groundwater monitoring alone is not abatement nor a remedial strategy. NMED will work with RGR to continue abatement activities and will recommend a modification of the approved CCP when consensus is reached by all parties. | RGR acknowledges NMED's comment regarding the distinction between ongoing site investigations and groundwater monitoring activities and the development of a comprehensive, site-wide abatement strategy under NMAC 20.6.2.4103.<br>RGR agrees that groundwater monitoring and operation of the current shallow extraction wells alone do not constitute a final remedial solution. The primary objective of the approved 2025 *Revised Site Investigation Plan* (EA, 2025a) is to better delineate the extent and nature of groundwater and to collect the information necessary to evaluate and develop effective long-term abatement alternatives. This information is needed before an appropriate site-wide abatement strategy can be developed.<br>RGR appreciates NMED's willingness to continue working collaboratively on the development of a long-term abatement strategy. Following completion of the site investigation and evaluation of the results, RGR will work with NMED to develop an appropriate abatement approach and, as necessary, modify the CCP to incorporate the selected remedial strategy. | |
| 8 | NA | Page T-30<br>Table 4-3 | **MECS "Comment 8" (March 6, 2026):**<br>2025 Closure/Closeout Plan, Disposal Cell Capacity, Table 4-3, Page T-30 - The estimated total volume of impacted soils is now listed as 418,167 cy in Table 4-3. NMED notes this volume does not include work currently underway to determine soil volumes from the South Controlled Area, nor does it include other potential future studies. If this work will be completed prior to the finalization of a cost estimate, it needs to be included. If it is not completed, NMED recommends a conservative estimate be included based on current knowledge with 20% contingency added. RGR can update this estimated volume after the completion of work in a future update to the CCP.<br>In the June 30, 2025 response, RGR provided updated soil volumes included in Attachment A – Summary of Material Scheduled for the Disposal Cell. Attachment A lists 942,450 cy as the "Disposal Cell Capacity at 25 Acres". The updated 2025 CCP states that the expanded disposal cell will be up to 13.5 acres, bringing the combined area of the existing Waste Rock | The disposal cell capacity listed in Table 4-4 represents the total capacity of the combined existing Waste Rock Pile (WRP) and the expanded disposal cell. As part of the October 15, 2025 CCP submittal, the disposal cell design was revised, increasing the total estimated disposal cell capacity from 942,450 cubic yards to 1,093,840 cubic yards.<br>Table 4-4 has been updated to include the estimated disposal volumes for the South Controlled Area based on the current characterization results. RGR acknowledges that additional characterization activities may identify other materials requiring disposal. As additional information becomes available, the estimated disposal volumes and closure cost estimate will be updated, as appropriate. If characterization activities are not completed prior to finalization of the closure cost estimate, conservative estimates, including appropriate contingency, will be incorporated, as appropriate. | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| | | | Pile (WRP) and the expanded cell to 25 acres, consistent with the 2022 CCP. Including recently reported South Controlled Area soil volumes, the table below summarizes the materials proposed for placement in the expanded disposal cell, as well as NMED's understanding of the remaining available disposal cell capacity. Please clarify whether the stated disposal cell capacity of 942,450 cy applies solely to the new 13.5-acre expanded disposal cell, or whether it includes capacity from the existing WRP in addition to the expanded cell. | | |

| Materials to Be Placed in Expanded Disposal Cell at 13.5 Acres | | |
|---|---|---|
| **Type** | **Volume (cy)** | **Document Source** |
| **Excavation - Contaminated Soil** | 418,167 | Table 4-3 of 2025 CCP |
| **Removal - Buildings** | 40,943 | Attachment A - Summary of Materials Scheduled for the Disposal Cell (June 30, 2025 Response Letter) |
| **Removal - Other Debris** | 40,789 | Attachment A - Summary of Materials Scheduled for the Disposal Cell (June 30, 2025 Response Letter) |
| **Potential South Controlled Area Contaminated Soil** | 26,560 | South Controlled Area Soil Radiologic Characterization (February 27, 2026) |
| **Total Volume to Be Placed in 13.5 Acre Expanded Disposal Cell** | 526,459 | |
| **Type** | **Volume (cy or %)** | **Document Source** |
| **Disposal Cell Capacity at 25 Acres** | 942,450 | Attachment A - Summary of Materials Scheduled for the Disposal Cell (June 30, 2025 Response Letter) |
| **Proportional Capacity % of New 13.5 Acres Out of 25 Acres** | 54.0% | |
| **54.0% of Total Disposal Cell Capacity** | 508,923 | |
| **Remaining Available Disposal Cell Capacity (Excluding South Controlled Area Soils)** | -17,536 | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 9 | NA | Figure 4-1 | **MECS "Comment 9" (March 6, 2026):**<br>2025 Closure/Closeout Plan, Figure 4-1 - Figure 4-1 of the updated 2025 CCP appears to indicate that portions of the existing WRP/disposal cell would be regraded or that the pre-existing slope would be modified. Please clarify if the proposed design changes will be incorporated to ensure protections for minimal disturbance of existing reclamation. Please clarify if the new cover design result in modification of the entire existing disposal cell facility or only be applicable to the new 13.5 acre expanded disposal cell. If the new design is not over the existing facility, please explain the transition area between the two designs. Please explain how groundwater monitoring well MW-11A and the newly proposed extraction well RW-11AR will be accommodated in the proposed design. | **(1) Existing WRP/Disposal Cell Disturbance:** The proposed design changes are limited exclusively to the 12-acre expanded disposal cell area. The existing WRP/disposal cell and its established reclamation will not be disturbed or regraded. The existing cover system will remain in place and is not subject to modification under the current design. Figure 4-1 has been updated for clarity.<br>**(2) Transition Zone:** A graded transition zone will be designed at the interface between the existing disposal cell and the expanded cell. This zone will taper the cover layers to match existing grades and avoid abrupt geometric discontinuities. Specific transition geometry, including slope and layer pinchout details, will be provided in the final construction drawings to be submitted for approval at a later date.<br>**(3) Wells MW-11A and RW-11AR:** The final grading plan will include adequate setbacks and access routes for both wells to ensure continued operability throughout and after construction. | |
| 10 | Appendix H | Table 2 of PCMP lists | **MECS "Comment 10" (March 6, 2026):**<br>2025 Closure/Closeout Plan, Appendix H - Table 2 of the PCMP lists the proposed Point of Compliance (POC) wells, including MW-1M, MW-5, WP-5, MW-11A, DW-3, DW-10, DW-11, DW-14, and DW-19. NMED agrees with the use of wells MW-1M, MW-5, WP-5, and MW-11A for long-term monitoring of the Alluvial/Menefee aquifer. NMED also requests that existing monitoring well MW-4 and the planned MW-13 (upcoming Site Investigation activities), be included as POC wells for the Alluvial/Menefee aquifer to address downgradient data gaps associated with the expanded disposal cell. Based on a September 25, 2025 technical memorandum from the Office of the State Engineer (OSE), DW-13 has been determined to have a low probability of inter-aquifer exchange, and NMED therefore concurs that it may be suitable for long-term groundwater monitoring of the Westwater aquifer. However, wells DW-3, DW-10, DW-11, and DW-19 are not suitable long-term groundwater monitoring wells. All four wells have been classified by OSE as having either possible inter-aquifer exchange or probable inter-aquifer exchange. In addition, wells DW-3, DW-10, and DW-11 currently have confirmed hydrocarbon releases, with several contaminants of concern above NMWQCC standards. NMED therefore requests installation of four new, dedicated wells designed specifically for long-term monitoring of the Point Lookout and Tres Hermanos aquifers, as these legacy dewatering wells are not in a condition to provide accurate long-term groundwater data. NMED will work with RGR on the location of and timing for the new monitoring wells, however cost for installation and long-term care need to be included in an updated cost estimate. A placeholder for these wells should be added to the PCMP for inclusion in the updated CCP. | The *Post-Closure Monitoring Plan* (PCMP) was updated as part of this CCP submittal to address NMED's comments regarding the proposed Point of Compliance (POC) monitoring network.<br>Regarding the Westwater aquifer, RGR notes a discrepancy in the agency's reference to well DW-13. A review of the September 25, 2025 Office of the State Engineer (OSE) documentation indicates that DW-14 (B-516-POD40) was identified as the Westwater well with a low probability of inter-aquifer exchange. Conversely, the OSE directive explicitly lists DW-13 among the wells requiring a plan to investigate the potential for inter-aquifer exchange, or a repair/plugging plan. Based on this OSE clearance, RGR assumes NMED's concurrence for long-term groundwater monitoring is intended for DW-14 rather than DW-13, and the PCMP has been updated to reflect DW-14 as the appropriate POC well.<br>RGR acknowledges NMED's concerns regarding the long-term suitability of dewatering wells DW-3, DW-10, DW-11, and DW-19 for post-closure groundwater monitoring. The updated PCMP includes placeholders for proposed new dedicated monitoring wells for the Point Lookout and Tres Hermanos aquifers. The final number, locations, and construction details of these wells will be developed in coordination with NMED.<br>The updated CCP closure cost estimate will include placeholder costs for the installation, long-term monitoring, maintenance, and eventual abandonment of the proposed monitoring wells, as appropriate. | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 11 | Past Attachments/Addenda | NA | **MECS "Comment 11" (March 6, 2026):**<br>2025 Closure/Closeout Plan, Past Attachments/Addenda - The CCP should be revised into a single, consolidated document. For example, Attachment A—Summary of Material Scheduled for the Disposal Cell—from the June 30, 2025 RGR response to CCP comments was not included in the updated 2025 CCP, while the Post Closure Monitoring Plan received on June 30, 2025, was included as Appendix H. Please update Attachment A as needed and include it, along with all other separate necessary addenda, as attachments or appendices to an updated CCP. | The Summary of Material Scheduled for the Disposal Cell has been updated and incorporated into Table 4-4 of the updated CCP. RGR also reviewed prior CCP attachments, appendices, and addenda and incorporated relevant information into the updated CCP, as appropriate, to provide a consolidated document. To the best of RGR's knowledge, all necessary supporting materials have been incorporated into the updated CCP. | |
| 12 | 4.2 | NA | **MECS "Comment 12" (March 6, 2026):**<br>Expanded Disposal Cell Design, 4.2 Description of Cover - Please provide a detailed explanation of the purpose of the coarse sand capillary break layer in the updated disposal cell cover design. Also, please provide some examples of where this layer has been effectively used in cover designs. NMED has not approved of a layer of this nature in a cover design, therefore is not approving of it without support and evaluation for an alternative design. | Engineering Analytics (EA) has completed a detailed critical review of the capillary break layer requirement. Based on this analysis, EA recommends eliminating the coarse sand capillary break layer from the cover design. The revised optimized 3-layer cover system — 12-inch rock mulch / 28-inch in-situ soil / 12-inch compacted clay — has been confirmed by radon diffusion analysis to yield a surface flux of approximately 13.99 $pCi/m^2 \cdot s$, well below the 20 $pCi/m^2 \cdot s$ regulatory limit. The capillary break layer is accordingly not included in the revised design. | |
| 13 | 4.6.3.1 | NA | **MECS "Comment 13" (March 6, 2026):**<br>Expanded Disposal Cell Design, 4.6.3.1 Climate Data Used for Analysis - The model results of the infiltration analysis indicate that the mean annual percolation value through the cover system is 0.45 inches/year or 7.4% of the mean annual precipitation value. This would indicate that the mean annual precipitation determined for the mine site would be 6.1 inches per year. Monthly climatological summaries for the Mt. Taylor mine site from 2018 – 2025 reported in DP-61 quarterly monitoring reports show a mean annual precipitation of about 10 inches per year. Please explain the discrepancy between those values and the mean annual precipitation values presented in the CCP. Additionally, please explain why Rice Park, NM, is used as the primary source of historical weather data. Rice Park is located approximately 30 miles to the west of Mt. Taylor mine and in a different mountain range. | EA acknowledges NMED's comment and provides the following clarification.<br>**(1) Precipitation Values Used in the Model:** We acknowledge the discrepancy in the previous draft, which contained a calculation error. The revised *Expanded Disposal Cell Design* report has been updated to explicitly use the continuous on-site meteorological data from the San Mateo station (2018–2025) as the primary dataset for the infiltration analysis. The documented on-site mean annual precipitation (MAP) is 10.01 in/yr. Using this site-specific precipitation input, the revised SEEP/W transient numerical model yields a long-term mean annual percolation rate of 0.40 in/yr through the cover system. This corrected percolation value accurately represents 4.0% of the MAP<br>**(2) Rice Park Weather Station:** We agree that on-site data should serve as the primary climatic reference. As noted above, the revised Expanded Disposal Cell Design now utilizes the on-site San Mateo data (2018–2025) as the primary dataset for the water balance, infiltration, and Copper Rule analyses. Regarding Rice Park, we would like to clarify that the SNOTEL station is located approximately 20 miles northeast of the mine, not 30 miles west. While the on-site data drives the infiltration model, Rice Park was retained solely as a supplemental dataset to evaluate long-term winter hydrology (e.g., snow water equivalent and freeze-thaw behavior). Because the on-site station record is relatively short, the Rice Park data is necessary to conservatively project the Air Freezing Index (AFI) for the 200-year return period frost penetration analysis. To validate this approach, a statistical comparison was performed; the results demonstrated no significant departures ($p > 0.05$) between the on-site San Mateo record and the long-term regional datasets, confirming that the site data falls within normal regional variability. Additional discussion clarifying the specific applications of these datasets has been added to Section 2.6 of the design report. | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 14 | 4.6.4 | NA | **MECS "Comment 14" (March 6, 2026):**<br>Expanded Disposal Cell Design, 4.6.4 Results of Infiltration Analysis - The infiltration analysis in the Expanded Disposal Cell Design Report does not provide the modeled available water holding capacity for the cover. NMAC 20.6.7.33.F.(2) states that soil cover systems shall be designed to limit net-percolation by having the capacity to store within the fine fraction at least 95 percent of the long-term average winter (December, January and February) precipitation or at least 35% of the long-term average summer (June, July and August) precipitation, whichever is greater. Please provide the available water holding capacity of each of the cover layers above the waste material. | EA has revised and finalized the Available Water Holding Capacity (AWHC) analysis for the cover system. This complete layer-by-layer breakdown and Copper Rule compliance evaluation has been added to Section 4.6.5 of the *Expanded Disposal Cell Design* report. The analysis summary is provided below.<br>**Material Properties and Available Water Holding Capacity (AWHC):** Based on the soil-water characteristic curves (SWCCs) derived from the Mt. Taylor borrow source characterization program (Appendix B), the AWHC for the 28-inch on-site soil cover layer (classified as CL-ML) is **0.10 in/in**. This is determined from a volumetric water content at field capacity ($\theta_{fc}$) of 0.20 minus the volumetric water content at the wilting point ($\theta_{wp}$) of 0.10.<br>• **Rock Mulch Layer (12 inches):** Not credited with fine-fraction water storage.<br>• **On-Site Soil Cover (28 inches):** Provides the primary fine-fraction moisture storage. Total storage capacity = 28 inches × 0.10 in/in = **2.80 inches**.<br>• **Compacted Clay Barrier (12 inches):** Storage is conservatively excluded from this calculation, as this layer serves as the primary low-permeability radon and infiltration barrier.<br>**Copper Rule Compliance:**<br>Using the reconciled on-site precipitation record (2018–2025 San Mateo station) presented in Table 4-4 of the design report, the governing storage requirement under NMAC 20.6.7.33.F.(2) is the greater of:<br>1. Long-term average winter (December, January, February) precipitation × 95%<br>2. Long-term average summer (June, July, August) precipitation × 35%<br>Based on the site data:<br>• December, January, February Precipitation = 0.94 inches (95% = **0.89 inches**)<br>• June July August Precipitation = 4.70 inches (35% = **1.65 inches**)<br>The strict regulatory requirement based on the 3-month seasonal definitions is **1.65 inches**. The 2.80 inches of storage provided by the 28-inch on-site soil layer easily exceeds this requirement.<br>Furthermore, as documented in Section 4.6.5 of the *Expanded Disposal Cell Design*, EA evaluated the cover against a more conservative 6-month seasonal criteria (Winter: Oct–Mar; Summer: Apr–Sep). Under this highly conservative evaluation, the required storage capacity was 2.73 inches. The storage capacity provided of 2.80 inches exceeds even this more rigorous standard, confirming full compliance with the Copper Rule store-and-release performance criteria. | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 15 | 4.11.2.3 | NA | **MECS "Comment 15" (March 6, 2026):**<br>Expanded Disposal Cell Design, 4.11.2.3 Rock Mulch Borrow Sources - Please confirm the D50 rock size of the AASHTO No. 1 gravel proposed for the rock mulch cover and explain why this size is appropriate | The AASHTO No. 1 gravel specified for the rock mulch admixture has a nominal $D_{50}$ (median rock size) of approximately 2.2 inches. The complete gradation and supporting engineering analyses have been incorporated into Section 4.9 and Appendix I of the *Expanded Disposal Cell Design* report.<br>This specific size range is appropriate for the Mt. Taylor disposal cell cover for the following reasons:<br>**1. Water Erosion Resistance (PMP Design Storm):** The rock size was evaluated using the Abt-Johnson method, as recommended in NUREG-1623 and NUREG/CR-4620. For the engineered 5H:1V (20%) cover slopes, the required $D_{50}$ to resist the Probable Maximum Precipitation (PMP) event increases with slope length. At the maximum designed unsupported slope run of 250 feet, the required $D_{50}$ is 2.04 inches. The provided AASHTO No. 1 gravel $D_{50}$ of 2.20 inches exceeds this requirement, ensuring individual particles resist displacement under maximum expected surface flow conditions.<br>**2. Gully Formation and Armoring:** Gully formation was evaluated using the Shield's incipient motion equation and Pemberton and Lara (1984) scour-depth calculations. The analysis confirms that the critical particle size to resist movement is 4.15 inches; the larger fraction of the AASHTO No. 1 gravel provides these coarser particles. This ensures that a protective armor layer will naturally develop within the 12-inch rock mulch admixture depth (calculated scour depth of 10.3 inches) before any scour can reach the underlying moisture-storage soil layer.<br>**3. Wind Erosion Protection:** The admixture blend (30% AASHTO No. 1 gravel and 70% on-site soil) creates a durable surface. As wind and minor water action winnow away surficial fines, the 2.2-inch gravel forms a self-reinforcing desert pavement. Wind Erosion Prediction System (WEPS) modeling for comparable covers in the Grants Mineral Belt demonstrates that this coarse fraction keeps annual soil loss well below the EPA benchmark of 2 tons per acre per year.<br>**4. Regional Precedent and Vegetation Support:** This 30% gravel admixture approach is consistent with successful, analogous uranium mill tailings closures in the Grants Mineral Belt. The AASHTO No. 1 gravel size is large enough to provide the necessary physical armoring, while the 70% soil matrix retains sufficient fines to successfully support the shallow-rooted native vegetation required for the store-and-release cover's evapotranspiration functions. | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 16 | 4.14 | NA | **MECS "Comment 16" (March 6, 2026):**<br>Expanded Disposal Cell Design, 4.14 Material Placement - The Expanded Disposal Cell Design Report states that petroleum-contaminated soil may be land farmed prior to placement, whereas the updated 2025 CCP does not mention land farming and instead states that all soils exceeding diesel and uranium cleanup standards will be excavated and placed in the disposal cell. Table 4-3 of the CCP estimates up to 24,600 cy of diesel-contaminated soil, with volumes subject to increase as the investigation continues. Please confirm whether land farming of diesel-contaminated soil is being proposed. If so, explain how land farming of diesel contaminated soil containing uranium and radium above screening levels would be managed to prevent additional environmental hazards, including but not limited to wind-blown, surface water, and groundwater impacts. Also describe any alternative method other than land farming if the soil contains free liquids and fails a paint filter liquids test. NMED continues to approve placement of diesel-contaminated soil in the expanded disposal cell provided it passes the paint filter liquids test. | Land farming of diesel-contaminated soils is not proposed as a primary disposal method in the current design. The reference to land farming in the previous *Expanded Disposal Cell Design* report reflected an earlier contingency that has since been eliminated. The revised *Expanded Disposal Cell Design* has been updated to remove this language and avoid confusion.<br>**Approved Approach:** All excavated soils exceeding diesel and/or uranium/radium cleanup screening levels will be managed in accordance with the current *Closeout/Closure Plan* and placed in the expanded disposal cell, provided they pass the paint filter liquids test in accordance with 40 CFR 261, Appendix II. This approach is consistent with NMED's approval.<br>**Free Liquids Management:** If excavated soils fail the paint filter liquids test, they will not be placed in the disposal cell until they have been managed to eliminate free liquids and subsequently pass the paint filter liquids test. No land farming of these materials is proposed. | |
| 17 | 4.14 | NA | **MECS "Comment 17" (March 6, 2026):**<br>Expanded Disposal Cell Design, 4.14 Material Placement - Please confirm the proposed compaction of all cover design layers. It appears that a minimum of 90 percent of the maximum dry density is proposed for the various cover layers, but it is not clearly stated in the Expanded Disposal Cell Design Report. | EA confirms that a minimum compaction standard of 90 percent of the maximum dry density (per Standard Proctor) is specified for the compacted earthen cover layers, specifically the on-site soil cover and the underlying clay radon barrier. The clay radon barrier carries a design saturated hydraulic conductivity of $7.6 \times 10^{-6}$ cm/s, based on site-specific laboratory testing, to ensure its radon attenuation and infiltration-barrier functions are achieved.<br>The uppermost rock mulch admixture layer is not subject to this specific compaction density standard, as it relies on particle interlock and gradation for long-term stability and erosion resistance.<br>The *Expanded Disposal Cell Design* report has been updated to clarify the 90 percent compaction standard for the applicable cover layers. Detailed execution specifications—including lift thicknesses, moisture conditioning requirements, and specific field QA/QC testing frequencies (e.g., nuclear densometer or sand-cone testing)—will be established in the Construction Quality Control (CQC) and Construction Quality Assurance (CQA) plans. As noted in the design report, these CQA/CQC plans will be submitted to the NMED for approval a minimum of 30 days prior to the beginning of construction of the clay liner. | |

<table>
<tr><th>Comment Number</th><th>Section Number in CCP</th><th>Page From in CCP</th><th>Comment</th><th>Response</th><th>MMD Acceptance of EA Response</th></tr>
<tr><td>18</td><td>NA</td><td>Figure 4-1<br>Figure D-1</td><td>MECS “Comment 18” (March 6, 2026):<br>Expanded Disposal Cell Design, Figure 4-1 vs Figure D-1 - In a June 30, 2025 response, RGR acknowledged revising the disposal cell design in response to feedback from NMED and MMD. NMED acknowledges receipt of the Expanded Disposal Cell Design Report (November 11, 2025) and the 2025 Borrow Source Investigation (December 1, 2025) as addenda to the updated 2025 CCP. The Expanded Disposal Cell Design Report describes a disposal cell cover composed of four layers totaling 78 inches in thickness, as shown in Figure 4-1. However, Appendices D and E, along with Figure D-1, depict a different cover configuration consisting of three layers with a total thickness of 57 inches. Please clarify which configuration represents the proposed design. Additionally, explain whether the thicker cover described in the main report (78 inches total) is intended as an added protective measure, given that modeling in the appendices shows a thinner cover achieves radon flux below 20 pCi/m²-sec and places the radon barrier below the calculated frost depth.</td><td>Engineering Analytics (EA) acknowledges this inconsistency. The optimized 3-layer cover design has been included in the design report. The proposed configuration. The revised design consists of:
<table>
<tr><th>Layer</th><th>Material</th><th>Thickness</th></tr>
<tr><td>Surface</td><td>AASHTO No. 1 Rock Mulch</td><td>12 inches</td></tr>
<tr><td>Middle</td><td>In-situ Sandy-Loam Soil</td><td>28 inches</td></tr>
<tr><td>Base</td><td>Compacted Clay Radon Barrier</td><td>12 inches</td></tr>
<tr><td colspan="2">Total Cover Thickness</td><td>52 inches</td></tr>
</table></td><td></td></tr>
</table>

<table>
<tr>
<td>19</td>
<td>NA</td>
<td>NA</td>
<td>MECS “Comment 19” (March 6, 2026):<br><br>2025 Borrow Source Investigation - Please confirm that the available clean borrow material known is sufficient to complete the planned disposal cell cover as currently designed. Additionally, please confirm that, should the volume of contaminated materials (e.g., soil, building materials, etc.) exceed expectations, the remaining clean borrow material will still be adequate to cover the increased disposal cell volume.</td>
<td>EA confirms that the available clean borrow material is sufficient to complete the planned disposal cell cover as currently designed, with adequate contingency to accommodate potential increases in the final waste volume.<br><br>The comprehensive borrow source investigation conducted by EA evaluated Borrow Sources A, B, and C. The investigation concluded that Sources A and B were partially or fully depleted during previous construction. Therefore, Borrow Source C (an undisturbed 12.0-acre footprint) is the primary source for the earthen cover materials.<br><br>Based on the 52-inch optimized cover design (12-inch rock mulch admixture, 28-inch on-site soil, 12-inch compacted clay), the required borrow quantities and estimated available volumes are detailed below:
<table>
<tr><th>Cover Layer</th><th>Thickness</th><th>Estimated Required Volume (CY)</th><th>Primary Source</th><th>Estimated Available Volume (CY)</th></tr>
<tr><td>Rock Mulch Admixture</td><td>12 inches</td><td>31,833</td><td>30% AASHTO No. 1 gravel (Imported/Approved local source) & 70% on-site soil</td><td>Scalable to demand (commercial/imported rock)</td></tr>
<tr><td>On-Site Soil Cover</td><td>28 inches</td><td>70,620</td><td>Borrow Source C (Overburden sand and sandy clay)</td><td>Sufficient (Constitutes the upper strata across the 12-acre footprint)</td></tr>
<tr><td>Compacted Clay Barrier</td><td>12 inches</td><td>28,740</td><td>Borrow Source C (Subsurface clayey soils)</td><td>38,735 to 58,102 (Based on 2.0 to 3.0 ft of average recoverable thickness)</td></tr>
</table>
Contingency for Increased Waste Volume:<br><br>Should the volume of contaminated materials exceed current expectations (necessitating a larger disposal cell footprint or height), the borrow strategy provides adequate contingency:<br><br>1. Clay Barrier: Borrow Source C can yield up to approximately 58,102 cubic yards of suitable clay if excavated to an average recoverable thickness of 3.0 feet across the 12.0-acre footprint. This provides a substantial buffer beyond the current 28,740 CY requirement, accounting for over 100% contingency to cover material rejection, shrinkage, and cell expansion.<br>2. Soil Cover: The 28-inch soil layer utilizes the abundant sand and sandy clay overburden that must be stripped to access the deeper clays in Borrow Source C, providing ample material to scale with the cell dimensions.<br>3. Rock Mulch: Because the AASHTO No. 1 gravel fraction will be sourced from an approved local rock quarry or imported, its availability is not strictly limited by the site's earthen borrow footprint and can be scaled to meet any increased</td>
<td></td>
</tr>
</table>

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| | | | | surface area demands.<br>The *Expanded Disposal Cell Design* report has been updated to reflect these specific layer volumes. Section 4.11 of the design report details these volumetric calculations, which were conservatively estimated based on the measured surface area of the borrow footprints and the recoverable material thicknesses observed in the test pit logs. | |
| **Comment Letter, New Mexico Environment Department (NMED) SWQB Comments, Mt Taylor Uranium Mine, Updated Closure Closeout Plan, Mining Act Permit No. CI002RE** | | | | | |
| 1 | NA | NA | **"SWQB Comment 1 – National Pollutant Discharge Elimination System (NPDES) Permit Status" (February 19, 2026):**<br>The Mt. Taylor Mine is covered under a Multi Sector General Permit (MSGP), #NMR05J02B, for industrial stormwater discharges currently issued by the U.S. Environmental Protection Agency. RGR should keep the stormwater pollution prevention plan (SWPPP) up to date to reflect conditions on the ground. | RGR will update the SWPPP to reflect current conditions as necessary. | |
| 2 | 4.4.6 | 39 | **"SWQB Comment 2 – Excavation and Disposal of Contaminated Soil" (February 19, 2026):**<br>Section 4.4.6 of the revised CCP describes that RGR is currently investigating all areas between its northern fenced boundary and the windblown area to identify the extent of any impacted areas, including the Marquez Canyon Arroyo to identify and dispose of any contaminated soil. The 2020 Radiological Surveys of Discharge Pipeline describes that soil excavation will be required for surface soils along the pipeline corridor or at Outfall 001 if Ra-226 concentrations exceed 6.8 pCi/g; A 2025 report demonstrates that materials have been removed along the pipeline corridor. Removal of contaminated soils, completion of the disposal cell, and completion of the site drainage upgrades will protect surface water quality. | RGR acknowledges this comment and concurs with the SWQB's assessment. RGR remains fully committed to executing the remediation activities outlined in Section 4.4.6 of the revised CCP, and investigations in the Marquez Canyon Arroyo and areas north of the fenced boundary will continue as described.<br>Although the pipeline outfall was previously characterized in 2013 (Appendix E of RGR, 2013a), RGR will include the Outfall 001 area in future closure characterizations to ensure any remaining radiological impacts are fully delineated. Based on these results, any soils exceeding the 6.8 pCi/g Ra-226 threshold will be excavated and properly placed in the expanded disposal cell once it is ready to receive material.<br>RGR agrees that completing these soil removals, finalizing the disposal cell, and upgrading the site drainage will effectively protect surface water quality. | |

| Comment Number | Section Number in CCP | Page From in CCP | Comment | Response | MMD Acceptance of EA Response |
|---|---|---|---|---|---|
| 3 | 2.3 and 4.6.2 | 8, 43, and 44 | **"SWQB Comment 3 – Surface Water" (February 19, 2026):**<br>Section 2.3 Surface Water of the revised CCP says that stormwater runoff retention structures will remain for livestock watering or will otherwise be re-directed to the existing drainage courses that would receive runoff. Stormwater retentions structures that were originally created in surface waters of the state or resulted in the impoundment of surface waters of the state meet the definition of surface waters of the state (see 20.6.4.7.S.5.b New Mexico Administrative Code for the definition of surface waters of the state). Section 4.6.2 of the revised CCP describes the original middle arroyo was largely filled in during site construction. Therefore, the stormwater runoff retention structures in this area are likely surface waters of the state and are subject to state surface water quality standards which include standards for livestock watering. RGR should conduct at least one sampling event to demonstrate that surface water in these retention structures meet the surface water quality standards for livestock watering, particularly for Radium 226 + Radium 228 which is 30 pCi/L (20.6.4.900 New Mexico Administrative Code). | RGR acknowledges the SWQB's comment and is committed to ensuring that any stormwater retention structures remaining to support the approved post-mining land use of livestock grazing are protective of human health and the environment and meet applicable regulatory requirements. Accordingly, RGR will conduct at least one surface water and sediment sampling event within the stormwater retention structures proposed to remain following reclamation prior to final closeout. Sampling will include analysis for constituents necessary to evaluate livestock watering use, including combined Radium-226 and Radium-228, which will be compared to the applicable surface water quality criterion of 30 pCi/L in 20.6.4.900 NMAC. The results will be provided to SWQB and MMD.<br>During active mining and closure operations, these stormwater retention structures will continue to function as engineered operational facilities for stormwater management, sediment control, and site remediation. Following completion of closure activities, including final grading, contaminated soil removal, and confirmation of water quality, RGR will coordinate with SWQB and MMD regarding the long-term management and regulatory status of any stormwater retention structures that remain as part of the approved post-mining land use.<br>Section 2.3.1 has been revised to reflect this sampling commitment and clarify the planned evaluation of the remaining stormwater retention structures during the closure process. | |
| 4 | 4.6.2 | 44 | **"SWQB Comment 4 – Arroyo Design and Monitoring" (February 19, 2026):**<br>The SWQB supports using the 500-year, 24-hour storm event to design the southern arroyo channel. SWQB recommends the portions of the arroyos that are in close proximity to reclamation areas be included in the Post Closure Monitoring Plan to ensure appropriate actions are taken to prevent potential impacts to the reclamation areas (and the arroyos) in the event the arroyos erode towards the reclamation areas. | RGR appreciates the SWQB's support for using the 500-year, 24-hour storm event as the design basis for the southern arroyo channel. However, given the limited area available within RGR-owned property to accommodate the proposed channel improvements, RGR is evaluating whether the 500-year, 24-hour design event can be practicably achieved within the available footprint. Condition 3(b) of the MMD-approved Revision 13-2 identifies a 100-year, 24-hour storm event as the design criterion for water diversion structures, or an alternative criterion approved by the MMD in consultation with other state or federal agencies. Accordingly, RGR proposes to evaluate the 100-year, 24-hour storm event as an alternative design basis for the southern arroyo channel.<br>RGR also concurs with the SWQB's recommendation to include those portions of the arroyos adjacent to reclaimed areas in the Post-Closure Monitoring Plan. Section 2.3 of the Post-Closure Monitoring Plan has been revised to include periodic inspections of these reaches to evaluate channel stability and identify erosion that could adversely affect reclaimed areas. If monitoring identifies erosion that could compromise reclaimed areas or drainage features, corrective actions will be evaluated and implemented as necessary. | |

# Closeout/Closure Plan

# Mt. Taylor Mine

# Existing Mine Permit No. CI002RE

# Discharge Permit DP-61

*Prepared for:*

**Rio Grande Resources Corporation**

*P.O. Box 1150*

*Grants, NM 87020*

*Prepared by:*

Engineering Analytics, Inc.
Now Part of MacKay

1600 Specht Point Road, Suite 209
Fort Collins, CO 80525
(970) 488-3111

Project No. 111360

September 8, 2026

## TABLE OF CONTENTS

**1.0 INTRODUCTION ..... 1**
1.1 Background ..... 1
1.2 Project Description ..... 4
1.3 Project History ..... 5
1.3.1 Mine Development ..... 5
1.3.2 Mine Production ..... 5
1.3.3 Mine De-Activation ..... 6
1.3.4 Mine Permitting ..... 6
1.3.5 Mine Water Pumping, Treatment, and Discharge ..... 6
1.4 Other Permits ..... 7
**2.0 SITE CHARACTERISTICS ..... 8**
2.1 Site Climate ..... 8
2.2 Site Geologic Setting Summary ..... 8
2.3 Site Hydrology Summary ..... 9
2.3.1 Surface Water ..... 9
2.3.2 Groundwater ..... 11
2.3.3 Site Conceptual Hydrogeologic Model ..... 12
2.4 Mine Units ..... 15
2.4.1 Underground Mine Unit ..... 16
2.4.2 Mine Dewatering Wells and Mine Water Treatment Unit ..... 17
2.4.3 Service and Support Unit ..... 19
2.4.4 Low-Grade Ore Stockpile and Ore Pad ..... 19
2.4.5 Waste Rock Pile and Disposal Cell ..... 20
2.4.6 Storm Water Ponds ..... 21
2.4.7 County Road ..... 21
**3.0 POST MINING LAND USE ..... 22**
3.1 Factors in Selection of Post-Mining Land Use ..... 22
3.2 Potential Post-Mining Land Uses ..... 23

3.3 Selected Post-Mining Land Uses ..... 23
3.3.1 Grazing ..... 24
3.3.2 Light Industrial, Commercial or Government Facilities ..... 24
3.3.3 Facilities Retained for PMLU ..... 24
3.3.4 Radiological Levels for PMLU ..... 25
**4.0 DESCRIPTION OF CLOSEOUT/CLOSURE ACTIVITIES ..... 27**
4.1 Closeout/Closure Practices ..... 28
4.2 Closeout/Closure Activities Completed ..... 29
4.2.1 Removal of Service and Support Facility Units ..... 29
4.2.2 Concrete Foundations ..... 31
4.2.3 Removal of Other Facilities ..... 33
4.2.4 Waste Rock Pile and Disposal Cell Status ..... 33
4.3 Closeout/Closure Activities Pending ..... 34
4.3.1 Shaft Plugging ..... 34
4.3.2 Well and Conduit Plugging ..... 36
4.3.3 Surface Facilities Removal Pending ..... 38
4.4 Earthwork ..... 39
4.4.1 Existing Waste Rock Pile ..... 41
4.4.2 Disposal Cell and Expansion ..... 42
4.4.3 Ore Pad Working Surface Removal ..... 43
4.4.4 MWTU and NSWP ..... 43
4.4.5 Affected Areas ..... 44
4.4.6 Excavation and Disposal of Contaminated Soil ..... 46
4.4.7 Finish Grading ..... 48
4.5 Revegetation ..... 49
4.5.1 Revegetation Species ..... 49
4.5.2 Seedbed Preparation and Seeding ..... 50
4.5.3 Seed Origin and Quality ..... 50
4.5.4 Revegetation Success ..... 50

4.5.5 Management and Contingency Plans ..... 50
4.6 Erosion Protection ..... 51
4.6.1 Protection of the Existing Waste Rock Pile Surfaces ..... 51
4.6.2 Arroyos ..... 52
4.7 Fencing ..... 53
**5.0 POST-CLOSURE ENVIRONMENTAL COMPLIANCE AND MONITORING ..... 54**
5.1 Surface Water Monitoring ..... 54
5.2 Evaporation Pond Leak Detection ..... 54
5.3 Groundwater Monitoring ..... 54
5.3.1 Alluvial and Menefee Groundwater Monitoring ..... 54
5.3.2 Deep Aquifer Groundwater Monitoring ..... 57
5.4 Radiological Safety and Monitoring ..... 58
5.4.1 Radiological Safety ..... 58
5.4.2 Radiological Surveying and Monitoring ..... 58
5.5 Sanitary Treatment Plant Discharge ..... 59
5.6 Erosion Control and Stormwater Monitoring ..... 59
5.7 Vegetation Monitoring ..... 60
5.8 Meteorological Monitoring ..... 61
**6.0 CLOSEOUT/CLOSURE SCHEDULE ..... 62**
**7.0 COST ESTIMATE ..... 63**
**8.0 REFERENCES ..... 64**

## LIST OF TABLES

Table 1-1 Other Permits
Table 1-2 Groundwater Levels in Wells and Shafts
Table 1-3 Alluvial and Menefee Monitoring and Recovery Wells
Table 2-1 Water Quality Test Results for Mine Pool in Manway Shaft (14ft) and Production Shaft (24ft)
Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells
Table 2-2(a) Alluvial and Menefee WQCC Analyte Exceedances During the 2Q 2026 Sampling Event
Table 2-3 Post-Closure Disposition of Mine Dewatering, Site Water Use, and Observation Wells
Table 2-4 As-Built Capacities of MWTU Ponds #2 and #3
Table 3-1(a) Radiological Survey Results for PMLU Habitable Structures
Table 3-1(b) Status of Release Surveys for Other PMLU Structures
Table 3-1(c) Summary of Radiological Survey Results for Non-PMLU Buildings
Table 4-1 Potential Contaminants on Site and in Use
Table 4-2 Mine Facility Disposition at Closeout
Table 4-3 Earthwork Balance
Table 4-4 Summary of Materials Scheduled for the Disposal Cell

## LIST OF FIGURES

Figure 1-1 Site Location Map
Figure 1-2 Mine Site and Affected Areas
Figure 1-2b Mine Facilities Disposition at Closeout
Figure 1-3 Mine Permit Area
Figure 1-4 Dewatering Well Locations and Descriptions
Figure 1-5 Typical Section of Dewatering Wells
Figure 1-6 Mine Site Alluvial and Menefee Monitoring and Recovery Wells
Figure 1-7 Observation Wells (Off-Site)
Figure 2-1 Geologic Section
Figure 2-2 Pre-Mining Topography
Figure 2-3 Westwater Canyon Aquifer Potentiometric Surface Map

Figure 2-4 Tres Hermanos/Dakota Aquifer Potentiometric Surface Map
Figure 2-5 Point Lookout/Hosta Aquifer Potentiometric Surface Map
Figure 2-6 Shallow Aquifer Potentiometric Surface Map
Figure 4-1 Expanded Disposal Cell with Site Topography and Current Wells
Figure 4-2 Approved Staging Areas
Figure 5-1 Nitrate Distribution in Alluvial and Upper Menefee Groundwater (August 2018)
Figure 5-2 Nitrate Distribution in Alluvial and Upper Menefee Groundwater (2Q 2026)
Figure 5-3 Uranium Distribution in Alluvial and Upper Menefee Groundwater (August 2018)
Figure 5-4 Uranium Distribution in Alluvial and Upper Menefee Groundwater (2Q 2026)
Figure 5-5 Sulfate Distribution in Alluvial and Upper Menefee Groundwater (May 2018)
Figure 5-6 Sulfate Distribution in Alluvial and Upper Menefee Groundwater (2Q 2026)
Figure 5-7 Location of Wells for Post-Closure Monitoring of Deep Aquifers
Figure 6-1 Closeout/Closure Schedule

## APPENDICES

Appendix A Mt. Taylor Mine Closeout/Closure Plan Drawings
Appendix B Hydrologic and Erosion Analysis
Appendix C Technical Specifications
Appendix D Soil Sampling and Laboratory Test Data
Appendix E Closeout/Closure Cost Estimate (Reserved)
Appendix F Revegetation Plan and Monitoring Protocols
Appendix G Structural Designs of Shaft Plugs
Appendix H Post-Closure Monitoring Plan
Appendix I Water Sampling and Laboratory Test Data
Appendix J Disposal Cell As-built Drawings
Appendix K Expanded Disposal Cell Design Report

Appendix L December 17, 1997 USDA Letter

Appendix M Technical Memorandum: Outfall 001 Historical Summary and Planned Characterization

## ACRONYMS

| | |
|---|---|
| ACM | Asbestos Containing Material |
| ALARA | As Low as Reasonably Achievable |
| ALI | Annual Limits on Intake |
| AOI | Area of Interest |
| BLM | Bureau of Land Management |
| BMP | Best Management Practices |
| CAP | Corrective Action Plan |
| CCP | Closeout/Closure Plan |
| DAC | Derived Air Concentrations |
| DCGL | Derived Concentration Guideline Limit |
| EA | Engineering Analytics |
| ERG | Environmental Restoration Group |
| FA | Financial Assurance |
| FHWA | Federal Highway Administration |
| FM | Formation |
| GWQB | Ground Water Quality Bureau |
| IAEA | International Atomic Energy Association |
| IL | Investigation Level |
| LNAPL | Light Non-Aqueous Phase Liquids |
| MARP | Mining Act Reclamation Program |
| MARSSIM | Multi-Agency Radiation Survey and Site Investigation Manual |
| MECS | Mining Environmental Compliance Section |
| MSGP | Multi-Sector General Storm Water Permit |
| MSHA | Mine Safety and Health Administration |
| MWTU | Mine Water Treatment Unit |
| NFM | North Force Main |
| NMAC | New Mexico Administration Code |
| NMED | New Mexico Environmental Quality Bureau |
| NMEI | New Mexico Environmental Institute |

| | |
|---|---|
| NPDES | National Pollutant Discharge Elimination System |
| NRC | Nuclear Regulatory Commission |
| NRCS | Natural Resources Conservation Service |
| NSWP | North Storm Water Pond |
| OSE | Office of the State Engineer |
| OSHA | Occupational Safety and Health Administration |
| PCMP | Post-Closure Monitoring Plan |
| PHC | Petroleum Hydrocarbons |
| PLH | Point Lookout/Hosta |
| PMLU | Post-Mining Land Use |
| PPE | Personal Protective Equipment |
| CQA | Construction Quality Assurance |
| CQC | Construction Quality Control |
| RCRA | Resource Conservation and Recovery Act |
| RGR | Rio Grande Resources Corporation |
| ROW | Right-of-Way |
| RPP | Radiation Protection Program |
| RSO | Radiation Safety Officer |
| RSPM | Radiation Safety Program Manual |
| RUSLE2 | Revised Universal Soil Loss Equation |
| RWP | Radiation Work Plan |
| S2AP | Stage 2 Abatement Plan |
| SSWP | South Storm Water Pond |
| STP | Sanitary Treatment Plant |
| SWPPP | Storm Water Pollution Prevention Plan |
| THD | Tres Hermanos/Dakota |
| TLD | Thermoluminescent Dosimeters |
| UAV | Unmanned Aerial Vehicle |
| USCS | Unified Soil Classification System |
| USDA | United States Department of Agriculture |
| USFS | United States Forest Service |

| | |
|---|---|
| VTPP | Vegetation Test Plot Plan |
| WEPP | Water Erosion Prediction Project |
| WQCC | Water Quality Control Commission |
| WRP | Waste Rock Pile |
| WSP | Water Supply Project |
| WWC | Westwater Canyon |

# 1.0 INTRODUCTION

## 1.1 Background

Rio Grande Resources Corporation (RGR) owns and operates the Mt. Taylor Mine, located near San Mateo in Cibola County, New Mexico. The mine is currently on active status under Permit No. CI002RE, Rev 13-2 (Mine Permit), which was approved on December 29, 2017, by the New Mexico Mines and Minerals Division (MMD).

In 2022, RGR applied for a revision of its Mine Permit No. CI002RE (RGR, 2022b) to expand the Disposal Cell and update the existing Closeout/Closure Plan (CCP;RGR, 2013b). This revision application is submitted pursuant to the New Mexico Administrative Code (NMAC) regulations 19.10.5.505 (NMAC, 2001a) and 19.10.7.701 (NMAC, 2001c).

The CCP is required by 19.10.5.506 and 19.10.5.507 NMAC (NMAC, 2001a) to describe the measures and estimated costs for reclamation of the mine site for the designated post-mining land uses (PMLUs) at closeout/closure. This CCP was prepared following the guidelines presented in the *Closeout Plan Guidelines for Existing Mines* (MARP, 1996) that are part of the State of New Mexico Energy, Minerals and Natural Resources Department (EMNRD). of Mining Act Reclamation Program (MARP).

From 2022 to the date of this report, RGR and the various agencies have been working toward obtaining the updated Mining Act Permit CI002RE and Discharge Permit-61 (DP-61). As part of this ongoing process, RGR is submitting this update to the Closeout/Closure Plan (CCP) as requested in the comment letters cited below:

1. **September 7, 2022:** Surface Water Quality Bureau (SWQB) of the New Mexico Environment Department (NMED). *"Request for Review and Comment, Mt. Taylor Mine and Mill, Updated Closeout/Closure Plan, Revision 22-1, Cibola County, New Mexico Mining Act Permit No. CI002RE, Revision 22-1"* (NMED, 2022a).

2. **September 12, 2022:** Air Quality Bureau (AQB) of the New Mexico Environment Department (NMED). *"Request for Review and Comment, Mt. Taylor Mine and Mill, Updated Closeout/Closure Plan, Revision 22-1, Cibola County, New Mexico Mining Act Permit No. CI002RE"* (NMED, 2022b).

3. **November 15, 2022:** Hydrology Bureau of the New Mexico Office of the State Engineer (NMOSE). *"Review and Comments, Revision 22-1 to Mt. Taylor Mine, Permit No. CI002RE, Rio Grande Resources Corporation"* (NMOSE, 2022).

4. **April 14, 2023:** Mining Environmental Compliance Section (MECS) of the New Mexico Environment Department (NMED). *"New Mexico Environment Department (NMED) Comments, Updated Closeout/Closure Plan, Revision 22-1, Mt. Taylor Mine, Rio Grande Resources, Cibola County, New Mexico, New Mexico Mining Act Permit No. CI002RE"* (NMED, 2023).

5. **May 17, 2023:** Mining and Minerals Division (MMD) of the New Mexico Energy, Minerals and Natural Resources Department (EMNRD). *"Comments on Closeout/Closure Plan Mt. Taylor Mine, Rio Grande Resources Corporation, Mt. Taylor Mine, Cibola County, New Mexico, Permit Tracking No. CI002RE"* (MMD, 2023).

6. **February 1, 2024:** Hydrology Bureau of the New Mexico Office of the State Engineer (NMOSE). *"Review of Revision 22-1 to Mt. Taylor Mine, Permit No. CI002RE, Rio Grande Resources Corporation"* (NMOSE, 2024).

7. **June 20, 2024:** Mining and Minerals Division (MMD) of the New Mexico Energy, Minerals and Natural Resources Department (EMNRD). *"2nd Comment Letter, Mt. Taylor Mine, Disposal Cell Expansion and Update of Closeout/Closure Plan, Revision 22-1, Permit No. CI002RE"* (MMD, 2024).

8. **March 14, 2025:** New Mexico Mining and Minerals Division (MMD) of the New Mexico Energy, Minerals and Natural Resources Department (EMNRD). *"3rd Comment Letter, Mt. Taylor Mine, Disposal Cell Expansion and Update of Closeout/Closure Plan, Revision 22-1, Permit No. CI002RE"* (MMD, 2025).

9. **April 25, 2025:** Mining Environmental Compliance Section (MECS) in the Ground Water Quality Bureau (GWQB) of the New Mexico Environment Department (NMED). *"New Mexico Environment Department (NMED) Comments Round 3, Mt Taylor Uranium Mine Closeout/Closure Plan, Cibola County, New Mexico, Mining Act Permit No. CI002RE"* (NMED, 2025a).

10. **April 25, 2025:** Mining Environmental Compliance Section (MECS) in the Ground Water Quality Bureau (GWQB) of the New Mexico Environment Department (NMED). *"Request for Additional Information Round 3 Comments, Discharge Permit 61 Renewal and Modification Application, Mt. Taylor Mine, San Mateo, New Mexico"* (NMED, 2025b).

11. **February 19, 2026:** New Mexico Environment Department (NMED). *"NMED Memorandum, Request for Review and Comment, Mt. Taylor Mine, Cibola County, New Mexico Mining Act Permit No. CI002RE"* (NMED, 2026a).

12. **March 6, 2026:** Surface Water Quality Bureau (SWQB) of the New Mexico Environment Department (NMED). *"NMED Surface Water Quality Bureau (SWQB) Memorandum, New Mexico Environment Department (NMED) Comments, Mt Taylor Uranium Mine, Updated Closure Closeout Plan, Mining Act Permit No. CI002RE"* (NMED, 2026b).

13. **March 18, 2026:** New Mexico Mining and Minerals Division (MMD) of the New Mexico Energy, Minerals and Natural Resources Department (EMNRD). *"Comment Letter, Mt. Taylor Mine, Update of Closeout/Closure Plan, Revision 22-1, Permit No. CI002RE"* (MMD, 2026).

The CCP was initially submitted in 1998 by RGR (RGR, 1998) as a revision to its existing Mine Permit No. CI002RE (RGR, 1994b) in accordance with the New Mexico Mining Act of 1993 (New Mexico, 2005), Section 69-36-1, Section 69-36-11B(3) and (4), and the New Mexico Mining Act Rules subparts 506.A and 506. B of 19.10.5 NMAC (NMAC, 2001a).

The NMED Water Quality Control Commission (WQCC), through 20.6.2.3107 A (11) NMAC (NMAC, 2018b), as enforced by the MECS of the GWCB, also required a CCP under DP-61 (NPDES, 1979). DP-61 was initially approved in 1979, modified and renewed in 1984 (NPDES, 1984) and 1989 (NPDES, 1989), and amended to include a CCP in 1995. Both the Mine Permit and the DP-61 require reclamation of some of the mine facilities and financial assurance (FA) to cover the cost of such reclamation. Because the CCP and DP-61 have common elements and similar FA requirements, MMD and MECS agreed that RGR could submit one CCP, including one cost estimate that satisfies the requirements of both agencies, with MMD taking the lead in coordinating the regulatory review and approval process, RGR submitted its CCP for existing conditions applicable to the mine site during standby in July 2012 (RGR, 2012).

In April 2013, RGR submitted an updated CCP (RGR, 2013a) for the mine after returning to active status. Energy, Minerals, and Natural Resources Department (EMNRD)/MMD accepted the 2013 CCP revision (RGR, 2013b) and MMD approved and issued an active status permit (CI002RE, Rev 13-2) on December 29, 2017 (MMD, 2017). This updated CCP is for revision of the approved 2013 CCP (RGR, 2013b) to reflect the status of the Mine Permit.

The original Mine Permit CCP (RGR, 1998) and the DP-61 closure plan renewal (NPDES 1998) anticipated that the primary post-mining land use (PMLU) of the mine site and most facilities would be a water supply project (WSP). Although the WSP remains a feasible PMLU, the previous business agreements for the WSP have expired. Thus, the WSP was not included in either the 2012 CCP update (RGR, 2012) nor the 2013 CCP (RGR, 2013a, 2013b) update and is also not included in this revision of the CCP.

The mine remains in active permit status. However, in 2019, RGR decided not to return the mine to production and to begin some closeout/closure activities included in the 2013 CCP (RGR, 2013b), which is permissible under the Mining Act (New Mexico, 2005). Accordingly, this submittal has been prepared to revise the 2013 CCP (NMED, 2013b) to reflect the existing land disturbances and the mine facilities, both those already removed and those remaining. This CCP describes the measures that will be taken to reclaim the disturbed land for post-mining land use and to satisfy the requirements of relevant environmental standards.

The following sections contain a description of the mine site and mining-related disturbances (Section 2.0); PMLU and related ecosystems (Section 3.0); completed and pending closeout/closure measures to achieve the PMLU (Section 4.0); and environmental monitoring, environmental standards, and permits required for closeout/closure (Section 5.0). Section 6 addresses the CCP schedule. The updated cost estimate for closeout/closure of the mine is discussed in Section 7.0. The revised cost estimate will be completed and submitted 60 days after CCP approval.

## 1.2 Project Description

RGR owns and operates the Mt. Taylor Mine in Cibola County, New Mexico, Section 24, T13N, R8W, NMPM (Figure 1-1). The mine site is 1/2-mile northeast of the Village of San Mateo and is accessible New Mexico State Route 605.

The mine facilities at the ground surface are shown in Figure 1-2. No mill was ever constructed or operated within the permit area. Since 2020, RGR has removed some surface facilities for closeout/closure.

The existing Mt. Taylor Mine units were described in the Mine Permit Application of December 1994 (RGR, 1994b). The mine permit areas consist of 4,006.7 acres (Figure 1-3), and the mine surface facilities are located on 285.6 acres, of which approximately 148 acres are disturbed land.

The disturbed land surface in the permit area consists of:

- Service and Support Facilities
- Mine Water Treatment Area
- Ore Stockpile Pad
- Existing Disposal Cell
- Storm Water Retention Ponds (North and South)
- Site Access Roads

The existing facilities and those already removed as of September 2026 are shown in Figure 1-2b. Permits other than the Mine Permit are listed in Table 1-1. Detailed locations and descriptions of deep wells are shown in Figure 1-4 of this CCP.

An inactive 24-inch diameter Treated Water Discharge Pipeline previously extended 4.3 miles from the Mine Water Treatment Unit (MWTU) area north to the outfall point in San Lucas Canyon north of the mine (Figure 1-3). RGR completely dismantled and removed this pipeline in 2024 and 2025; all associated corridor disturbances were successfully re-contoured and revegetated in the fall of 2025.

A maintained gravel access road (County Road 334) bisects the mine site. This is a state road and right-of-way, maintained by Cibola County, which provides public access to the west edge of the Cibola National Forest; it is not part of the Mine Permit area, but is an affected area (Section 4.4.5.). Any soils with levels exceeding the approved radium limit of 6.8 pCi/g will be removed during closeout/closure. Technical criteria governing these cleanups are detailed in Section 4.4.6.

An adobe ruin remains on the small hill east of the south storm water pond (Figure 1-2b). This feature was not disturbed by, or used in, mining and will be left in place.

The Underground Mine Unit, consisting of the underground workings, shafts, and conduits, has no surface disturbance other than that included in the Service and Support Facilities Unit (shaft collars and connecting ventilation openings). The mine extracted uranium ore using room-and-pillar and stope mining methods. Mining was conducted on a single level (Westwater Formation ore horizon), approximately 3,100 ft below the surface. These mine workings were connected to two approximately 3,300-feet deep shafts via shaft stations. Several hydrostratigraphic units were penetrated by the shafts, requiring three sets (phases) of deep wells for local dewatering to access the ore body (Figures 1-4 and 1-5).

## 1.3 Project History

Prior to 1971, when Gulf Mineral Resources Corporation acquired the property, no mining had occurred within the permit area of the Mt. Taylor Mine. However, exploratory drilling and construction of associated access roads occurred prior to 1971. A December 17, 1997, U.S. Forest Service letter addressing reclamation of these historical drill pads and access roads recommended that unused areas be closed to vehicle access and allowed to naturally revegetate rather than be recontoured because additional disturbance would adversely affect existing vegetation (Appendix L).

### 1.3.1 Mine Development

The Mt. Taylor Mine was developed in the 1970's by Gulf Mineral Resources Company (Gulf). Two, approximately 3,300-foot-deep mine shafts were constructed using traditional drill-and-blast methods with progressive liner construction to gain access to the ore zones. Shaft sinking began in 1976 and was completed in 1979. During shaft advancement, dewatering of the mine was accomplished by using a series of dewatering wells (DW Wells) constructed in three phases (Figures 1-4 and 1-5). Once the shafts were completed, development drifting into the orebody began. During development, dewatering of the mine was accomplished using pumps within the shaft and workings.

### 1.3.2 Mine Production

Gulf started production in 1980, after the orebody was sufficiently developed. Production continued until September 1982, when the market price of uranium fell dramatically, resulting in the temporary cessation of production by Gulf. Mine pumps continued dewatering the mine during this shut-down period. Ownership was transferred to Chevron Resources Company in 1985 when the two companies merged. Chevron produced ore from the mine from 1986 to 1990, when it suspended mining of uranium ore, again due to low market prices for uranium.

The mine historically produced uranium using conventional underground mining methods from ore zones of the Morrison Formation at depths of more than 3,000 ft bgs. Approximately 675,085 tons of ore and approximately 698,000 tons of waste rock have been mined (RGR, 1994a). The ore was shipped off-site for milling. Overlying formations, including the water-bearing Dakota Sandstone, were penetrated by the shafts, but no mining of ore was conducted in those formations.

Waste rock from shaft sinking (shaft muck) and from mine development was placed in an on-site stockpile, located at the southwest corner of the waste rock pile. The shaft muck was found to meet

the criteria of clean materials (radioactive components at or below background values, see Appendix D.1) and was subsequently added to the disposal cell.

The mine has not produced uranium since RGR purchased the property because of the continued low market price for uranium and the high cost of reactivation. Facility descriptions remain unchanged from those provided in previous renewals of this plan.

### 1.3.3 Mine De-Activation

Chevron Resources Corp. ceased mining activities at the Mt Taylor Mine in January 1990 due to low uranium market prices. RGR acquired the mine property in 1991 and maintained the mine in a ready status in anticipation of improving uranium market conditions.

### 1.3.4 Mine Permitting

RGR submitted its application for an Existing Mine Permit in December 1994, shortly after the New Mexico Mining Act was passed and the rules went into effect. The MMD approved the Mt. Taylor Mine Permit No. CI002RE as an existing mine operation on July 28, 1995 (MMD, 1995). On December 18, 1998, the MMD approved the CCP and FA for the mine (MMD, 1998).

RGR submitted its first application for standby status of the Mt. Taylor Mine on March 25, 1999 (RGR, 1999). MMD approved standby status on October 7, 1999, under permit revision 99-1 (MMD, 1999). From 1999 to 2017, the mine was in standby status due to the depressed uranium market.

Anticipating recovery of the uranium market, RGR submitted an application in 2013 to revise the Mine Permit from standby to active status (RGR, 2013a; RGR, 2013b). Since December 29, 2017, the mine has been in active status. However, in 2019, RGR decided that the uranium market was not recovering sufficiently to justify resuming production of the Mt. Taylor Mine, so closeout/closure activities began.

### 1.3.5 Mine Water Pumping, Treatment, and Discharge

To gain access to the ore zones during mine development, dewatering (depressurizing) wells were drilled and operated in stages. The primary function of these wells was to reduce the water pressure on the shaft as it was constructed. Pumping water from these dewatering wells began in the early 1970's and ceased by 1978. Locations and descriptions of these dewatering wells within the mine area are shown in Figure 1-4. A typical geologic section and typical well construction are shown on Figure 1-5. Shallow monitoring wells were installed to track the effects on shallow water resources from the sewage lagoon leakage or the diesel spill contamination (Figure 1-6, Table 1-3).

During mining operations in the late 1970’s and through the 1980’s, the mine was dewatered via underground pumps and piping. The water was pumped to the MWTU facility on the surface, where it was treated to reduce radium concentrations before discharge. The treated water was then discharged through a 24-inch diameter, 4.3-mile-long pipeline (Treated Water Discharge Pipeline). This pipeline mainly crossed private land, except for approximately a three-quarter-mile portion on US Forest Service land. The pipeline terminated at the outfall in San Lucas Canyon north of

the mine (Figure 1-3). The treated water was discharged under the now-terminated National Pollutant Discharge Elimination System (NPDES) Permit No. NM0028100 (NPDES, 2016) into the ephemeral drainage of San Lucas Canyon. Historical investigations completed between 2013 and 2020 evaluated soil, sediment, surface water, and groundwater conditions at Outfall 001 and at selected downstream locations within the San Lucas drainage to assess potential impacts from historical mine water discharges. These investigations generally concluded that historically treated mine water discharges had not resulted in significant impacts to downstream soils or groundwater; however, subsequent radiological surveys identified localized areas requiring additional evaluation as part of mine closure. A summary of the historical investigations and the planned characterization activities for Outfall 001 is provided in Appendix M, *Outfall 001 Historical Summary and Planned Characterization* (EA, 2026e).

Seven observation wells were installed for monitoring drawdown during the initial dewatering of the mine (Figures 1-4 and 1-7). Observation wells SM 24-89, SM 24-43, and SM 24-38, which are completed in the Westwater formation, are in the mine area near the production shaft (Figure 1-4). One of these observation wells, SM 24-23E, is in the mine area near dewatering well DW-8 and is competed in the Tres Hermanos/Dakota formation. The three other wells are located outside of the mine area at locations shown in Figure 1-7. These observation wells have not been used since operations ceased in the 1980's. Water levels in the dewatering and observation wells are listed in Table 1-2.

## 1.4 Other Permits

RGR maintains several permits that are relevant to the closeout/closure of the Mt. Taylor Mine. In addition to the Mine Permit and DP-61, the other permits related to the mine are listed in Table 1-1.

The NPDES Permit No. 0028100 (NPDES, 2016) was terminated by the U.S. Environmental Protection Agency (EPA) in 2021 because it was no longer required. The Mt Taylor Mine facility has not discharged through Outfall 001 since the early 1990's.

Radioactive Material License SO043-14 (NMED, 2020) was terminated in 2021 because it was no longer required. The sources covered under the license were no longer needed and were disposed.

There are no stationary sources with potential emissions of regulated contaminants associated with closeout/closure activities, so there are no air quality permit requirements for closeout.

The U.S. Forest Service Special Use Authorization (MOT220) for the treated water discharge pipeline was terminated on November 25, 2025, following completion of pipeline removal. No additional authorizations associated with the former treated water discharge pipeline are anticipated for mine closeout/closure.

No other permits beyond those listed in Table 1-1 and those just discussed above are required for closeout/closure of the Mt. Taylor Mine.

# 2.0 SITE CHARACTERISTICS

## 2.1 Site Climate

The climate and baseline air quality of the permit area are described in the *Environmental Site Assessment* (RGR, 1994a) and the *Permit Application* (RGR, 1994b). The climate is semi-arid, like most of the state, but the elevation (about 7,300 ft above MSL) and orographic effects of Mt. Taylor cause low winter temperatures and frequent high winds that impose some limitations on post-mining land uses and ecosystems. In particular, the climate of the site is not well-suited to crop production other than hay, but it has historically allowed livestock grazing. Rainfall is not sufficient to support forest within the area of the surface facilities, where most disturbance has occurred.

## 2.2 Site Geologic Setting Summary

The geologic setting of the mine has been described in detail in the *Environmental Baseline Study* prepared by New Mexico Environmental Institute (NMEI) in 1974 (NMEI, 1974) and the *Environmental Site Assessment* submitted in 1994 (RGR, 1994a). The following summary is derived from those, and other reports. The geologic section is illustrated in Figure 2-1.

The deepest geologic formation encountered in the Mount Taylor mine shaft is the Jurassic-age Morrison Formation. The Morrison Formation includes the following members, in ascending order: the Recapture Creek, the Westwater Canyon, and the Brushy Basin. Recapture Creek member occurs at a depth between 3,240-3,300 ft bgs in the mine shaft pilot well. This member grades vertically into the overlying Westwater Canyon member. The Westwater Canyon member is variable in thickness owing to lensing and vertical gradations into both the Brushy Basin and Recapture Creek members. At the mine site, the Westwater Canyon is divided into Upper and Lower units by a persistent shale unit. The lower sandstone unit is about 60 to 70 ft thick, while the upper sandstone unit is approximately 100 ft thick in the mine shaft area. These two sandstone units contain most of the uranium ore reserves of the mine. The Brushy Basin member conformably overlies and interfingers with the Westwater Canyon member. It is approximately 80 ft thick and consists predominantly of shales and claystones at the mine shaft.

Between the ore-bearing Morrison Formation and the ground surface is a sequence of sedimentary units approximately 2,950 ft thick, starting with the Dakota Sandstone, which unconformably overlies the Brushy Basin. The Dakota is approximately 50 to 60 ft thick and is only slightly mineralized and not mined at the Mt. Taylor Mine. The Dakota conformably intertongues with the overlying Mancos Shale.

The overlying Mancos Shale, nearly 900 ft thick, is composed chiefly of dark-gray, calcareous, marine clay shale but does contain interspersed sandstone units. The lowermost portion of the Mancos Shale contains three sandstone units that have been referred to as the Upper, Middle, and Lower Tres Hermanos Sandstones. These sands are 72 ft, 45 ft, and 118 ft thick, respectively, at the mine shaft pilot well (McGlothin, 1972).

Above the Tres Hermanos Sandstones, the Manco Shale extends up to the base of the Gallup Sandstone at approximately 2,050 ft bgs. The Gallup Sandstone consists of two separate sandstone

units separated by 130 ft of dark gray shale. Overlying the Gallup Sandstone is the Crevasse Canyon Formation which includes, in ascending order, the Dilco Coal, the Stray Sand, the Mulatto Tongue of the Mancos Shale, the Dalton Sandstone, and the Gibson Coal. The Crevasse Canyon Formation is conformably overlain by the Point Lookout Formation.

The Point Lookout Formation is the basal unit of the Mesa Verde Group and it is typically encountered between 700 and 850 ft bgs at the mine site. In the vicinity of the mine, this unit is separated into two units by the Satan Tongue of the Mancos Shale. The upper unit, referred to as the Point Lookout Sandstone, is the main body, and it is typically 110 to 130 ft thick. The lower unit is the Lower Hosta Tongue, a transgressive marine beach sandstone that is between 80 to 100 ft thick. Both units merge along the southern margin of the basin to a combined unit approximately 250 ft thick. The Lower Hosta Tongue is of limited areal extent, pinching out 30 miles northeast of its outcrop. The Point Lookout Sandstone consists of a sequence of thick-to very thick-bedded, very fine-to medium-grained, locally cross-bedded sandstone. The Point Lookout/Hosta (PLH) aquifer provides the domestic water supply for both the mine and the Village of San Mateo.

The Menefee Formation is the uppermost geologic unit present at the mine. It forms uneven slopes around the mine and near the Village of San Mateo. The formation is composed of interbedded pale yellowish-brown silt stone, fine to medium grained sandstone, gray shale, carbonaceous shale, and thin coal beds. Its thickness at the mine shaft is approximately 767 ft (NMEI, 1974). Mine water treatment pond basins were excavated into the Menefee, and both the manway/vent and production shafts are collared in this formation.

Deposits of Quaternary age exposed in the area consist of unconsolidated talus, alluvial, and eolian sediments. Talus, landslides, and black lava blocks cover extensive areas on the slopes adjacent to the high basalt-covered mesas to the south, southwest, and east of the mine. Clay, silt, sand, and gravel alluvial lenses underlie the valleys, as well as the lower topographic slopes (NMEI, 1974).

## 2.3 Site Hydrology Summary

The hydrologic conditions of the mine and impacts from mining have been described in detail in the Baseline Study (NMEI, 1974) and the Environmental Site Assessment (RGR, 1994a). The following summary of the surface and groundwater hydrology from those reports and updates from more recent observations and studies is provided as the basis for proposed closeout/closure measures.

### 2.3.1 Surface Water

Two main surface drainage systems collect both bedrock seepage water and storm water run-off in the vicinity of the mine. The primary surface water course is San Mateo Creek, located one-half mile south of the mine. This perennial stream is fed with numerous springs in the San Mateo Canyon area but disappears into the stream bed approximately two miles beyond the Village of San Mateo. During spring peak run-off and after heavy rainstorms, the surface flow may occasionally extend for a brief period farther down San Mateo Creek. Surface water runoff within the permit area occurs only after heavy precipitation on or upstream from the site.

The second main drainage system is the Marquez Arroyo ephemeral steam, located immediately north of the mine. This deeply incised arroyo collects water during the infrequent heavy rainstorms, but otherwise it is dry throughout the year. Low-flow springs are located at higher elevations feeding this drainage, but their total flow has never been large enough to be measurable at the mine's elevation. Marquez Arroyo flattens out, and surface flow dissipates into the alluvium about one-half mile west of the mine.

Constructed during mine development in the 1970's, diversion ditches and below-grade collection systems intercept and channel runoff originating on the site to storm water retention ponds where water is evaporated. These ditches replace three shallow ephemeral drainage courses that existed prior to mine development (Figure 2-2). Storm water originating directly on the mine site area is channeled into culverts and storm water pipes, which flow into storm water retention ponds and evaporates.

During the 2018–2019 mine reactivation phase, the facility's drainage infrastructure underwent a series of upgrades:

1. Runoff from the service and support area previously directed into mine water treatment Pond #2 has been diverted into a replacement storm water collection system (re-constructed 2018) along the county road that discharges to the South Storm Water Pond (SSWP).
2. Runoff from the east and north slopes of the Waste Rock Pile now collects in a storm water collection system that discharges into the SSWP (Appendix A Drawing Sheet CL 14), which was completed in 2019.

The storm water runoff retention structures are designed to contain not less than the 100-year storm runoff and hold the water for evaporation. Following final closeout, those diversion ditches and retention structures that support the post-mining land use (PMLU) will remain in use for stock watering; otherwise, runoff will be re-directed to existing drainage courses that naturally would receive runoff from the site (Appendix A Drawing Sheet CL 14).

Per 20.6.4.7.S(5)(b) NMAC, storm water retention structures that were originally created in surface waters of the state or resulted in the impoundment of surface waters of the state meet the definition of surface waters of the state. Because portions of the operational area and the associated storm water retention structures overlay the historical middle arroyo channel, these water bodies may be subject to state surface water quality standards, including the protective standards for livestock watering upon final site closeout.

To demonstrate that the surface water in these structures is safe for livestock consumption and satisfies state standards, RGR will conduct at least one comprehensive surface water and sediment characterization sampling event within the retention ponds prior to final site release. This sampling event will verify that the water quality meets the state livestock watering standards, with particular emphasis on ensuring that Radium-226 + Radium-228 concentrations comply with the 30 pCi/L maximum limit established under 20.6.4.900 NMAC. Throughout the active closure and earthwork execution phases, these ponds will continue to be managed as

active industrial containment and remediation facilities. The final jurisdictional status of the remaining stock watering ponds under 20.6.4 NMAC will be determined in coordination with the Surface Water Quality Bureau (SWQB) following the submittal of the closure validation data.

### 2.3.2 Groundwater

Aquifers and the groundwater conditions in the mine area are described in detail in the Baseline Study (NMEI, 1974), and in aquifer test reports (McGlothin, 1972), the Water Resources Report (Geohydrology Associates, Inc., 1994), and the Site Conceptual Hydrogeologic Model (EA, 2025b). The following summary of groundwater hydrology from those reports and updates from more recent observations and studies are provided as the basis for proposed closeout/closure measures. Aquifers capable of yielding large quantities of groundwater occur in some Cretaceous formations and in the Jurassic Morrison Formation, where the uranium ore bodies are found.

Several aquifers are intersected by the mineshafts and were affected by the mine dewatering. Key aquifer systems of interest include the Point Lookout/Hosta (PLH), Tres Hermanos/Dakota (THD) and the Westwater Canyon member of the Morrison Formation (WWC). Groundwater from these strata was removed by pumping a series of dewatering wells during mine shaft advancement until 1978 (Figures 1-4 and 1-5) and then by underground mine pumps into 1990 to dewater the ore bodies. The underground mine pumps were shut off in June 1990, after mining operations were suspended, and the mine has subsequently flooded as groundwater levels recovered. The mine water derived from the Westwater Canyon member has concentrations of uranium, radium, sulfate, and TDS that exceed current drinking water standards (Table 2-1).

The shallowest aquifer capable of sustaining a potable water supply in the mine area, the PLH, has a potentiometric surface at a depth of approximately 460 to 610 ft bgs (Table 1-2), and the aquifer has a large flow potential. The Village of San Mateo and the mine have wells reaching depths between 650 to 1190 ft and are completed within the PLH. The mine began using this water in 1972, whereas the San Mateo village water well, located at 35° 19’ 56.14” N, 107° 39’ 02.53” W, was drilled in 1976 by Gulf and serves approximately 200 residents. The geologic cross-section indicates that the Point Lookout Sandstone is separated vertically from the surface and alluvium by over 650 ft of shale and sandy shale sequences (Figure 2-1) in the Menefee Formation, minimizing the possibility of any shallow Menefee or alluvial aquifer groundwater discharging to the PLH aquifer.

As shown in the second quarter of 2026 dewatering well groundwater sampling results (EA, 2026a), the quality of the PLH aquifer generally meets the WQCC water standards with occasional exceedance of the fluoride standard and some low-level detections of petroleum hydrocarbon compounds (Table 2-2). Engineering Analytics (EA) prepared an assessment of fluoride levels measured in wells and springs in the area that are completed within or discharge from the shallow (alluvial and Menefee) and deeper (PLH through the THD aquifers and concluded that natural occurrences of fluoride commonly exceed the WQCC standard of 1.6 mg/L (EA, 2025b).

The Environmental Baseline Study (NMEI, 1974) includes a list of other shallow water wells, most of which are clustered in and around San Mateo. Six wells (three hand-dug) are in the alluvium, less than 100 ft deep, and nine wells produce from the Upper Menefee Formation from

120 to 336 ft deep. Some of these wells may still be used for watering livestock, but several of them were abandoned when the PLH water well was drilled for village use by Gulf.

The alluvial and shallow portions of the Menefee Formation are unconfined aquifer systems that yield small amounts of water in the local area. Water levels vary from 35 to 90 ft bgs. The alluvial sediments vary from 0 to 65 ft thick at the mine site. The Menefee Formation is typically over 750 ft thick and is comprised of interbedded shales, claystones, and sandstones, which provide a confining layer to the underlying Point Lookout Sandstone (Figure 2-1).

Perched groundwater occurs in some locations in the mine area. A discontinuous perched groundwater zone occurs at approximately 12-25 ft bgs, located within the Waste Rock Pile and paleochannels. Alluvial groundwater occurs at the alluvial/bedrock contact at approximately 45-60 ft bgs primarily in paleo-arroyos within the operational area of the mine and in shallow, low-volume saturated zones elsewhere in the Upper Menefee.

A geophysical study was conducted in 2020 (Willowstick, 2020) across the southern half of the mine site. This study concluded that preferential groundwater flow paths exist beneath the Waste Rock Pile and the operations area. The primary preferential groundwater flow paths identified in the study overlap the paleo-arroyo channels that were filled in as part of the mine site development. The study also identified several areas of perched water within the Waste Rock Pile. In late 2020, an additional site investigation was conducted, with installation of seven new monitor wells located in the preferential flow paths identified in the Willowstick study (Ensero, 2021b). These new wells were completed in water-bearing siltstones and sandstones within the Upper Menefee just below the alluvium/bedrock contact. One background monitoring well, MW-1C, was installed in the southeast portion of the mine site. Alluvial and Menefee monitoring and recovery well locations are shown on Figure 1-6 and listed in Table 1-3.

Recharge to the alluvial and Upper Menefee groundwater at the mine site comes from the Menefee Formation east of the mine site, historic seepage from a former sewage lagoon and meteoric waters that recharge occurs primarily through paleochannels from seeps and possibly springs along the (now) subcrop of Menefee sandstone beds that were covered when Gulf conducted extensive cut and fill of the mine surface during 1976-1980. The paleochannels were the drainage courses for discharge from those springs, as well as surface runoff from the mine site and the mesa above the mine site. Alluvial and Upper Menefee groundwater flows west to northwest through the mine site.

### 2.3.3 Site Conceptual Hydrogeologic Model

A site conceptual hydrogeologic model of the Mt Taylor mine site is presented that provides a synthesis of available site geologic and hydrologic information. More detailed description of the deeper aquifer systems is provided in a report submitted by EA in 2025 (EA 2025b).

The deepest aquifer of interest with respect to the mine site is within the Westwater Canyon (WWC) member of the Morrison Formation (Fm). This aquifer occurs at a depth of approximately 3,100 to 3,200 ft bgs, is between 120 and 180 feet thick, and was the ore-bearing unit that was mined for uranium at Mt Taylor. The WWC aquifer can transmit large amounts of groundwater. During the dewatering of the mine from 1979 to 1990, the WWC aquifer produced water at

sustained rates between 3,000 and 4,000 gallons per minute (gpm). Dewatering activities ceased in 1990.

Water level elevations within the WWC dewatering wells are generally between 6,580 and 6,590 ft amsl. Based on these potentiometric data, the ambient groundwater flow direction is to the northwest (Figure 2-3). Water levels within the WWC aquifer have largely recovered to pre-mining levels.

Water quality of the WWC aquifer measured prior to mining operations typically exceeded secondary drinking water EPA standards for sulfate and TDS, and NMED WQCC standards for total radium. Because of its depth and water quality, and the fact that there are better, shallower alternative sources, the WWC is not considered a potable water supply in the local area.

The WWC lies between the Recapture Creek and Brushy Basin members of the Morrison Fm, both of which are considered aquitards in the area of the mine site because they consist predominantly of finer grained units of shales, claystones, and mudstones, with thin interbedded sandstones. Between the Morrison Formation and ground surface is a sequence of sedimentary units approximately 2,950 ft thick.

Directly above the Morrison Fm, is the Dakota Sandstone, approximately 50 to 60 ft thick. The Dakota Sandstone is considered a regional aquifer, although it is not used for water supply locally, primarily because of its depth of around 2,900 ft bgs. Overlying the Dakota Sandstone is the Mancos Shale. Within the lowermost portion of the Mancos Shale are three sandstone units collectively referred to as the Tres Hermanos. The Dakota Sandstone is separated from the overlying Tres Hermanos by a relatively thin (less than 15 ft) shale layer and from the underlying WWC aquifer by the shaley Brushy Basin Member. Water level elevations for the dewatering wells are generally between 6,545 and 6,725 ft amsl. Water level data suggest that the Dakota and Tres Hermanos aquifers, and possibly the WWC aquifer, may be hydraulically connected. Limited potentiometric data for the Dakota/Tres Hermanos aquifers suggests a south to southeasterly groundwater flow direction (Figure 2-4), which is opposite to that of the WWC aquifer. However, the data may not be representative because many of the dewatering wells that are screened within the Dakota/Tres Hermanos aquifers are also screened across other shallower aquifers.

Most of the Mancos Shale is characterized as a thick sequence of predominately marine shales. There is an approximately 550 ft section of Mancos Shale separating the Tres Hermanos Sandstones from the overlying Gallup Sandstone. The Gallup aquifer (which includes the Lower and Upper Gallup Sandstones) occurs from approximately 1,740 to 2,010 ft bgs at the mine shaft. The Mancos Shale interval provides a significant confining layer between the Tres Hermanos and Gallup aquifers. Pre-mining water level data collected from a shaft pilot well confirmed the hydraulic isolation between the Tres Hermanos and Gallup aquifers (McGlothin, 1972). There is insufficient data to estimate the potentiometric surface of the Gallup aquifer system (which includes the Lower and Upper Gallup Sandstones).

Overlying the Gallup Sandstone is the Crevasse Canyon Fm, which is approximately 690 ft thick at the mine shaft. The Crevasse Canyon Fm consists of the following units in ascending order (approximate depth encountered in the mine shaft in parentheses in ft bgs): Dilco Coal (1,720),

Stray SS (1,640), Mulatto Tongue of the Mancos Shale (1,297), Dalton SS (1,138), and Gibson Coal (1,013). The formation is composed primarily of fine-grained sandstone, siltstone, and shale with coal present in the Gibson and Dilco Members. The sandstones within these units are typically fine-grained and are limited in areal extent but could potentially provide a localized water supply. The Gipson Coal is overlain by the Lower Hosta Tongue of the Point Lookout Sandstone. There are no dewatering or observation wells that are completed only within the Gallup Sandstone, or the Crevasse Canyon Fm, or any of its subunits.

The PLH aquifer is typically encountered between 700 and 850 ft bgs. At the mine site, the PLH aquifer is separated into two units by the Satan Tongue shale. The upper unit is the main body, commonly referred to as the Point Lookout Sandstone. The upper unit is typically 130 ft thick. The lower unit is the Lower Hosta Tongue, a transgressive marine beach sandstone that is approximately 100 ft thick. Testing in the mine shaft pilot well indicated relatively higher permeability within the PLH aquifer. The PLH provides a local water supply to the village of San Mateo and to the Mt Taylor mine. Water level elevations within the PLH dewatering wells are between 6755 and 6880 ft amsl. Potentiometric data indicates a southerly groundwater flow direction for the PLH aquifer (Figure 2-5).

The projection of the PLH aquifer potentiometric surface through the shaft location is approximately 6,785 ft amsl. The water level elevation within the shaft (which is open to the WWC aquifer) is approximately 6,564 ft amsl. The potentiometric surface of the PLH aquifer (Figure 2-5) is more than 200 ft higher than in the WWC aquifer (Figure 2-3) at the shaft location. No breeches or failures have been identified in the shaft where it penetrates the PLH. The large difference in the potentiometric surfaces clearly indicates that the concrete shaft lining is effectively separating groundwater in the WWC aquifer from the PLH aquifer.

Water quality of the PLH is generally within NMED WQCC standards although there are local exceedances of fluoride (Table 2-2). Additionally, petroleum hydrocarbons (PHCs) in the form of Light Non-Aqueous Phase Liquids (LNAPLs) and some dissolved concentrations were detected in two of the PLH dewatering wells (DW-3 and DW-10). LNAPLs were also detected in one THD well, DW-11. Corrective actions have reduced dissolved concentrations to below NMED standards for all PHCs and removed the LNAPLs, with the exception of naphthalene in DW-11. Investigation into the source of those constituents is ongoing, and monitoring of the PLH and THD dewatering wells is ongoing.

The Menefee Fm is the shallowest geologic unit present at Mt Taylor mine site and is found in outcrops and in the shallow subsurface. The Menefee Fm is typically greater than 750 ft thick and consists of interbedded siltstone, fine- to medium-grained sandstone, gray shale, carbonaceous shale, and thin coal beds. This thick sequence of relatively low permeability sediments provides a confining layer to the underlying PLH aquifer.

The shallow portions of the Menefee Fm yield small amounts of water in the local area. Water levels vary from 35 to 90 ft bgs. Potentiometric data indicates a generally west to northwest flow direction across the mine site within this hydrogeologic unit (Figure 2-6).

The alluvial sediments vary from 0 to 60 ft thick at the mine site and are typically located along drainages and within paleo-arroyos. Alluvial groundwater occurs locally as discontinuous, thin saturated zones at the alluvial/Menefee Fm contact at depths of 45-60 ft bgs within the operational area of the mine. A discontinuous perched groundwater zone occurs at approximately 12-25 ft bgs located within the Waste Rock Pile and paleochannels.

Groundwater impacts from mining have been identified within the perched, alluvial, and upper Menefee Fm groundwater systems. Table 2-2(a) summarizes the exceedances that were observed in the second quarter sampling event (EA, 2026b). Additional field investigation and characterization to delineate the nature and extent of those impacts is in progress at the time of this report.

## 2.4 Mine Units

Mt. Taylor Mine was an underground mine, with the ore bodies present over 3,000 ft bgs and supported by a surface facility. Refer to the Permit Application (RGR, 1994b) for details of the mine facilities. Ore was mined by conventional drill-and-blast methods, hoisted to the surface in ore skips via shafts, and transported offsite for milling.

A worst-case subsidence analysis was performed in support of the 1994 Permit Application (RGR, 1994b). Even with the assumed case of 100% extraction of ore, which would not be physically possible, no subsidence would reach the ground surface and would be limited to 300 ft above the mine workings. During previous mining operations, approximately 1.3 million tons of ore and waste rock were extracted from the ore bodies in the Morrison units.

Using best current practices of room-and-pillar mining with backfilling, subsidence would be limited to heights less than one room width above the room, leaving overlying aquifers and ground surface unaffected. Therefore, upon closeout, underground workings (the Underground Mine Unit) will be abandoned, and shafts plugged at the surface.

Mine units identified in the 2013 Mine Permit renewal application (RGR, 2013b) include the underground workings (referred to as the Mine Unit in the 2013 Mine Permit) and surface mine units that consisted of all activities at ground level needed for support of underground mining. These activities included:

- Hoisting of men, materials, and ore
- Ventilation and cooling of air for the underground workings
- Removal and treatment of mine water
- Disposal of waste rock
- Administrative, health and safety, and maintenance services
- Stockpiling and loading of ore for offsite milling

The location and identification of mine facilities are shown in Figure 1-2 and Figure 1-2b. Mine units are delineated primarily by function and secondary by location; there is some overlap in locations of the mine units. The mine units are described in the following sections:

- Underground Mine Unit (Section 2.4.1)
- Mine Dewatering and Mine Water Treatment Unit (Section 2.4.2)
- Service and Support Unit (Section 2.4.3)
- Low-Grade Ore Stockpile and Ore Pad (Section 2.4.4)
- Waste Rock Pile and Disposal Cell (Section 2.4.5)
- Storm Water Ponds (Section 2.4.6)
- County Road (Section 2.4.7)

### 2.4.1 Underground Mine Unit

The facilities in this category, collectively called the Underground Mine Unit, consist of below-surface facilities - the two shafts and associated underground workings. The underground mine workings, including all drifts, stopes, haulage ways, and other openings for ore extraction are shown on Figure II of the Environmental Site Assessment (RGR, 1994a). These underground workings follow the ore body at depths of 3,100 to 3,200 ft bgs. The shafts and conduits penetrate all the geologic units and aquifers described in Sections 2.2 and 2.3.

The Mt. Taylor Mine has two shafts: a production shaft (24-foot diameter) and a manway/ ventilation shaft (14-foot diameter). In addition, two 10 ¾ -inch inner diameter (I.D.) utility conduits (pipes) extend from the ground surface to the mine level. The conduits are steel casings/pipes, grouted in place. The conduits are 11.5 inches outer diameter (O.D.), cemented in place in 12.5-inch diameter boreholes through the entire length of 3,100 ft (north conduit) and 3,200 ft (south conduit). The annulus between the steel casing/pipe and the bore hole is cement grouted. The grout isolates the conduit from all aquifers except the Westwater at the mine level. As previously requested by MMD and approved in the Mine Permit, the entire length of each conduit will be grouted closed during closeout/closure.

Both shafts have slip-formed, cast-in-place concrete liners from collar level to mine level. The liner thickness increases with depth, from 1 ft at the sub-collar level to 3 ft at the mine level. The rock/concrete contact is pressure-grouted through the water-bearing sections from the Point Lookout aquifer to the shaft stations at mine level, isolating the shafts from the aquifers above mine level and the aquifers from each other.

The hydrologic isolation of the shafts and the mine water from the PLH aquifer is demonstrated by the difference in static water levels between the shafts and the Phase I dewatering wells that are completed in the PLH aquifer (Table 1-2). Water level data have been routinely measured at four Phase I wells since 2023. Potentiometric surface maps developed from that data (Figure 2-5)

indicate that the water level elevation of the PLH aquifer is approximately 6,830 ft above mean sea level (ft amsl) at the 14-ft manway shaft and approximately 6,780 ft amsl at the 24-ft production shaft.

The field-measured water level elevation within the production shaft is approximately 6,567 ft amsl, or about 263 ft lower than the projected potentiometric water level elevation in the PLH.

Dewatering operations ended around 1990. Water levels within the Point Lookout wells and within the production shaft have stabilized following recovery since dewatering ended 35 years ago. The water level being over 200 ft lower in the production shaft than the Point Lookout aquifer indicates that there is no discernible hydrologic connection between the mine water (Morrison/ Recapture/Westwater) and the PLH. If a connection existed between the shafts and the PLH aquifer, water levels in the mine shafts would be similar to those in the PLH. The isolation of mine water from the PLH is also evident from the differences in water quality between the mine water (Table 2-1) sampled from the production shaft and the PLH water sampled in the dewatering wells (Table 2-2).

### 2.4.2 Mine Dewatering Wells and Mine Water Treatment Unit

#### 2.4.2.1 Mine Dewatering Wells

The mine facilities included deep dewatering wells for removing water from the mine, a MWTU, and a Treated Water Discharge Pipeline. During initial mine operations, water was pumped from up to 22 deep wells to dewater the mine. These wells are located concentrically around the shafts, as shown in Figure 1-4 and listed in Table 2-3.

When the mine was operating, these facilities were used to pump, treat, and discharge up to 7,200,000 gallons per day. However, during mine standby and the more recent active status period (2018-2019), no mine water was discharged, and these facilities were not in operation.

#### 2.4.2.2 Mine Water Treatment Unit

The MWTU is regulated under DP-61, which was originally approved on July 20, 1979, and subsequently renewed every five years hence. DP-61 is in the process of timely renewal concurrently with RGR's application for renewal of the Mine Permit.

The MWTU covers 28 acres of land surface within the Mine Permit boundary. The mine water treatment unit included the water treatment equipment and buildings (Ion Exchange plant, flocculant treatment, and barium chloride treatment facilities), as well as the ponds, which had an original combined capacity of approximately 62 acre-feet (RGR, 2013b).

In the 1970's and 1980's, when the mine was operating, the mine water was treated in the MWTU to remove low concentrations of uranium and radium so that the treated water met human health standards (NMAC, 2018a). Treatment consisted of sediment settlement assisted by flocculation and precipitation of radium using barium chloride. An ion exchange (IX) circuit for removal of uranium was constructed but never placed into full operation because the uranium concentrations

of the mine water were below the groundwater standard (5 mg/L) in effect at that time. The IX circuit was run only in an initial test mode; it was not subsequently used for uranium removal.

Mine water was first treated with flocculant before being released into Pond #1. Mine water then flowed from Pond #1 through Ponds #2 and #3, where settling of suspended solids occurred. The settled mine water then flowed from Pond #3, through the barium chloride mixing facility, and into Pond #8. From Pond #8, the treated water flowed into Pond #4, then into Pond #5. Through the addition of barium chloride, barium precipitation was induced (barium-radium-sulfate co-precipitation) as the mine water flowed through these three ponds. After barium precipitation in Pond #5, the treated water flowed into Ponds #6 and #7 before release to the discharge pipeline.

From Pond #7, treated water was pumped through a 4.3 mile long, 24-inch diameter discharge pipeline and discharged to San Lucas Canyon (Figure 1-3) under authority of NPDES Permit No. NM0028100. The pipe was constructed above-ground and consisted of 1/4- to 3/8-inch thickness steel sections, welded in the field.

The MWTU was upgraded during the mine reactivation period (2018-2019), after the Mine Permit was revised to active status. During this time, MWTU Ponds #2 and #3 were enlarged in 2019 and 2018, respectively; existing hydraulic structures were refurbished, new concrete spillways were constructed at the inlets, and double-membrane high-density polyurethane (HDPE) liner systems were installed according to DP-61. Both ponds were enlarged for increased storage capacities (Table 2-4). Excavated contaminated soils generated during the reshaping activities were placed in the disposal cell.

MWTU Pond #3 is being used to retain and evaporate contaminated water and fluids generated around the site, including groundwater from abatement activities, surface water runoff collected from containment structures, monitor well purge water generated from sampling, and wash water generated on site from equipment and materials decontamination. MWTU Pond #2 is not regularly in use; it serves as backup storage in case MWTU Pond #3 becomes filled to capacity. A shallow pool of clean water is maintained in MWTU Pond #2 to preserve and maintain the liner.

MWTU Ponds #2 and 3 will remain in place until groundwater abatement objectives have been achieved, and site decontamination activities are no longer required. These ponds were constructed as below-grade basins excavated into native rock and soil. When no longer needed, these two ponds will be reclaimed. The sediments contained on the liners will be removed and placed in the disposal cell. The hydraulic structures and liners will then be removed and placed in the disposal cell. The berms will be pushed in, and the ponds backfilled and regraded to meet final grading contours (Drawing Sheets CL 07A and CL 08). The pond areas will then be re-vegetated according to Appendix F.

MWTU Ponds #1, 4, 5, 6, 7, and 8 were excavated in 2019, during the reactivation phase, to remove contaminated sediments and soil, which were subsequently placed in the disposal cell. These ponds were not relined and never put into use during active status because RGR initiated closeout/closure activities before those ponds were re-constructed.

Demolition of the MWTU pond hydraulic structures, with the exceptions of Pond #2 and 3, were completed 2026.

Once the disposal cell expansion is approved, RGR will complete cleanup and reclamation of MWTU Ponds #1, 4, 5, 6, 7, and 8. After these six ponds are demonstrated to be clean, the berms will be pushed in, and the ponds backfilled. These six ponds will be regraded to meet final grading contours during closeout (Appendix A Drawing Sheets CL 07A and CL 08).

### 2.4.3 Service and Support Unit

The Service and Support Unit includes all surface facilities other than mine water treatment and mine waste rock disposal. The location and identification of these facilities are shown in Figure 1-2b and listed in Table 4-2.

Service facilities are those units at ground surface that supported the overall mine operation but do not provide direct support for underground operations. These units provided site access control, administrative services, personnel and sanitary services, warehousing and storage, maintenance and repair, water and power utilities. The facilities included the guard house, fire equipment building, service building, car (maintenance) shop, carpenter shop, electrical building, water treatment building, storage building, core storage building, water tanks, fuel storage tanks, fan shop, septic tank, leach field, and water wells for water supply to the mine.

Support facilities are those facilities at ground surface (above the shaft collars) that had a direct function in underground mining operations. These support facilities supplied air for ventilation; pumping water from the underground space; cooling and heating of underground air; and hoisting of personnel, materials, and ore to and from the underground mining levels. The mine support facilities included the compressor building, chiller building, cooling towers, chiller pump building, shaft heating buildings, hoist house, headframes, and exhaust fan structure.

An electrical substation is located on the north side of the service and support facilities area. This substation is owned by the Continental Divide Electric Cooperative and Public Service of New Mexico and is not subject to regulation under the Mine Permit. However, because the substation has some contamination from fugitive dust, it is an affected area and will be cleaned up during closeout/closure.

### 2.4.4 Low-Grade Ore Stockpile and Ore Pad

The ore stockpile covered 6.8 acres and contained approximately 60,000 tons of low-grade ore. The ore stockpile has been removed, and the ore has been trucked to the White Mesa uranium mill in Utah.

In the previous version of the CCP, a new 10-acre ore pad was to be constructed with a liner, truck wash, and runoff collection system as described in RGR, 2013b. These improvements were never constructed and are no longer proposed at the site.

As part of closeout, the surface soils currently in the ore pad will be removed to eliminate any soil contamination from the ore stockpile. Contaminated soils in the ore pad will be placed in the disposal cell. This is described further in the Earthwork Section 4.4.3.

### 2.4.5 Waste Rock Pile and Disposal Cell

This mine unit consists of the original Waste Rock Pile (WRP) and the expanded disposal cell within and adjacent to the original WRP footprint. Together, these features serve as the permanent repository for radiologically contaminated materials, diesel-impacted soils, site debris, and other affected materials generated from the Mt. Taylor Mine and its affected areas.

The original WRP is comprised of waste material generated from previous mining and development activities, including approximately 698,000 tons of waste rock extracted and managed during the 1986 to 1990 production period alone. The disposal cell is a distinctly separate engineered structure constructed above and adjacent to the WRP and intended to contain newly generated site waste. Its low-permeability liner and engineered 52-inch store-and-release cover system, consisting of a 12-inch rock mulch surface, a 28-inch on-site soil buffer, and a 12-inch compacted clay radon barrier, are designed to reduce infiltration, attenuate radon, and minimize contaminant leaching and mobilization.

The existing WRP was reshaped during the mine reactivation period (2018-2019) and occupies 13 acres in the southwest corner of the surface facility area. Upon resuming mining operations, waste rock was to be placed on this pile until it reached the maximum build-out configuration. The WRP contains waste rock (rock with uranium content below economic value), excavated during mine development and production, from non-ore-bearing formations or below-ore-grade rock in the mine.

The mound of material previously located at the southwest corner before 2018 was shaft muck excavated from strata above mine level, meaning its radionuclide content was essentially at background levels. The shaft muck pile was reshaped into the south sloping berm of the current WRP and disposal cell during the 2018 reconstruction period.

The WRP also contains a variety of non-rock waste from the mine such as rock bolts, timbers, ventilation bags, pipes, and other mine-related debris. These materials occur randomly throughout the pile. Waste rock removed from underground mines typically includes non-rock materials that are hoisted alongside the rock and remain mixed when placed in the WRP. At the Mt. Taylor Mine, this mixture has been in place for up to 38 years with no visible evidence of settlement.

Non-rock waste (site debris and scrap materials) generated during closeout/closure will be placed in the disposal cell under controlled procedures to minimize future settlement. Structural materials and dismantled equipment will be cut, crushed, or reduced to manageable dimensions, and oversized components will be placed so surrounding earthen material can be compacted against them to eliminate bridging and unsupported voids. Hollow items such as pipes, conduits, tanks, and vessels will be filled with clean earthen material or flowable fill. Disposal cell fill will be placed in controlled loose lifts not exceeding 12 inches and compacted to least 90 percent of maximum dry density, with representative waste samples tested for consolidation and swell so

final grading can include sufficient camber. The cell will also accommodate approximately 7,400 cubic yards of non-hazardous diesel-impacted soils from the North Controlled Area, placed in a documented and controlled manner within the lined and covered repository.

### 2.4.6 Storm Water Ponds

Two runoff retention ponds, the north storm water pond (NSWP) and the south storm water pond (SSWP), capture and retain runoff from areas of the mine surface that contain ore or waste rock (Figure 1-2). The NSWP is also referred to as the ore pad runoff retention pond.

The NSWP (0.9 acres), located between the ore stockpile pad area and the mine water treatment area, retains runoff from the ore pad and holds it until it evaporates. The NSWP will be remediated as part of closeout, once the disposal cell expansion is approved and after the ore pad is removed.

The SSWP was reconstructed in 2018 to its current size of 2.67 acres (Kuhn, 2019) increasing the capacity sufficiently to hold the runoff of two 100-year storm events. The SSWP retains storm water from the existing WRP and the service and support facilities and will remain as part of PMLU after closeout/closure to retain and evaporate site runoff.

During reactivation (2018), the sediments and contaminated soils in the SSWP were excavated and placed in the disposal cell. Once cleaned, a 2-ft thick clay liner was installed over the floor and sides (Kuhn, 2019). Subsequent runoff from the mine facility has introduced new contaminated sediment onto the pond floor, as anticipated. Once closeout/closure is completed, these newly deposited contaminated sediments will be excavated and placed in the disposal cell.

Along with reconstruction of the SSWP during mine reactivation (2018-2019), the mine facility runoff that formerly flowed to MWTU Pond #2 was rerouted via reconstructed and new storm water pipe system to the SSWP. At this time, all mine facility storm water runoff has been diverted to the SSWP, including the catchment of storm water runoff from the disposal cell. Upon closeout/closure, this runoff will continue to be diverted to the south storm water pond.

All contaminated soil from the cleanup of both ponds will be placed in the disposal cell.

### 2.4.7 County Road

County Road 334 (County Road), also known as the Access Road, is a public gravel road and right-of-way, totaling approximately 4.7 acres, maintained for the State of New Mexico by Cibola County, that provides access to the west edge of the Cibola National Forest; it is not part of the Mine Permit area, and not subject to closeout. However, contaminated soil along and or on the County Road corridor will be removed and the road surface restored during closeout/closure.

# 3.0 POST MINING LAND USE

## 3.1 Factors in Selection of Post-Mining Land Use

In selecting post-mining land uses (PMLUs) for the permit area, RGR considered many factors. These included:

- Technical feasibility
- Economics
- Land ownership
- Current and possible future surrounding land uses
- Public interests
- Site resources and ecosystems
- Environmental impacts and standards

*Technical feasibility* - No PMLUs were considered for which necessary technology does not presently exist.

*Economics* - This factor consists of two parts, economic feasibility and economic compatibility. A PMLU should have net positive economic returns (returns at least equal to costs). The net returns can be in the form of revenues, cost savings, or any combination of these. The PMLU should work positively within the local economy, either by improving it or helping to sustain it.

*Land Ownership* - RGR controls, either through direct ownership or through leases with landowners, the permit-area surface listed in the Permit Application. RGR owns the surface land in the E-1/2, Section 24, T13N, R8W, containing the mine facilities, apart from a wedge-shaped portion of land around the SSWP, which is leased by RGR.

*Current and possible future surrounding land* - The surrounding lands have been used for livestock grazing and small-scale logging for several generations, and these uses are expected to continue in the foreseeable future. The Cibola National Forest to the east provides several recreational, commercial, and cultural uses available to the public. The selected PMLUs should be consistent and compatible with surrounding land uses but need not be the same uses.

*Public interests* - The San Mateo community has a strong cultural heritage and places great value on its rural, independent lifestyle. PMLUs that would require substantial new infrastructure or impose demographic changes were avoided to reduce the chance for negative impacts to the community.

*Site resources and ecosystems* - RGR examined the resources of the site other than the uranium ore, especially those already disturbed by mining, to identify which ones have potential for productive use after mining. Site resources include both natural and man-made attributes of the

site. Water removed from the mine and some mine surface facilities are resources that have potential use after mining operations. Reclamation should restore the pre-mining ecosystem to the extent consistent with the PMLU(s).

*Environmental impacts and standards* - Potential PMLUs should limit land disturbance or, preferably, contribute to mitigation of mining disturbances. Each PMLU must be able to meet standards for air and water protection established by NMED and federal agencies as applicable.

## 3.2 Potential Post-Mining Land Uses

Using the factors described above, RGR identified the following potential PMLUs:

- Livestock grazing
- Wildlife habitat
- Commercial, government, or light industrial facilities

*Livestock grazing* as a PMLU is consistent with surrounding and historical land uses and local public interest. It is also consistent with the wishes of those land surface owners who have expressed a preference. This use will be facilitated through covering of the WRP and mine water treatment ponds, final grading of disturbed surfaces, and revegetation. This PMLU could coexist with or next to the other potential PMLUs and would restore the pre-mining ecosystem.

*Wildlife habitat* is consistent with surrounding lands uses and community values. It is readily implemented with the same measures used for establishing livestock grazing.

*Commercial, government, or light industrial facilities* would make use of some existing mine buildings and infrastructure, all in usable condition, for offices, services, manufacturing, storage, or wholesale/retail sales, providing a center for employment in the San Mateo area. This use is compatible with a municipal/industrial water supply or livestock grazing PMLU but is generally not compatible with wildlife habitat. The mine surface facilities include office, warehouse, and maintenance facilities that could be used by other mining operations in the area or by land management agencies such as the Bureau of Land Management and the U.S. Forest Service. Although located away from main transportation routes and in a sparsely populated area, the mine facilities could also support light industrial uses.

## 3.3 Selected Post-Mining Land Uses

For the purposes of this CCP, RGR has selected grazing and light industrial as the primary PMLU and the basis of the cost estimate for financial assurance. RGR intends to utilize the selected buildings (retained for PMLU, Table 4-2 and Figure 1-2b) for its continued business operations in New Mexico and focus on maintaining a continued presence at the Mt Taylor facility. The buildings and facilities will provide storage and maintenance of its equipment, as well as office space for RGR's site personnel and current and future business opportunities, including light industrial, commercial, or government uses. The equipment will be used to maintain the PMLU facilities (water wells, grazing endeavors, other business potential).

### 3.3.1 Grazing

As stated in the Mine Permit Application (RGR, 2022a), prior to the development of the mine, the site was used for grazing by generations of the same families. Specifically, the surface owners have grazed livestock on, or expressed this preference for, the following areas:

- Portion of NE 1/4, Section 24 - This is the northerly portion of the mine surface area, containing the Mine Water Treatment Unit as well as the county road right-of-way. RGR is the surface owner of this tract. This land has been grazed historically so the non-excluded parts of this surface will be returned to grazing as the PMLU.

- Portion of SE 1/4, Section 24 - This is the southerly portion of the mine surface area as well as undisturbed land south of the mine facilities. It contains most of the surface support and mine support facilities and the WRP. RGR is the surface owner of all but a wedged-shaped portion of this tract (see bullet point below).

- Northwest Portion of SE 1/4, Section 24 - This triangle of land, about six acres owned by others, is the surface presently occupied by part of the WRP and the adjacent storm water retention pond. A land swap agreement to transfer title of this land to RGR is anticipated. This triangle of land would be included subsequently with the rest of the SE 1/4 of Section 24. The SSWP will be retained as a stock tank, and the remainder of the area will be converted to grazing except for the WRP, which will be fenced to exclude grazing.

### 3.3.2 Light Industrial, Commercial or Government Facilities

The existing service and support facilities are multiple-use buildings that support office, warehouse, and maintenance/repair activities. Some buildings and facilities will be left in place to support agricultural operations and future light industrial, commercial, or government uses. As the landowner, RGR desires that the facilities designated in Table 4-2 and shown on Figure 1-2b, together with the water supply wells shown on Figure 1-4, remain in place for these post-mining land uses.

### 3.3.3 Facilities Retained for PMLU

The following facilities will remain in place for PMLU:

- Guard House (Security Building)
- Core Storage Building
- Fan Shop
- Capacitor Building
- Ion Exchange Plant (for warehouse and equipment storage)
- Septic System (septic tank, leach field, and piping)

- Site water use wells: DW-1, DW-2A, DW-6, DW-7, and DW-8
- Monitoring wells: DW-1 and DW-14 (site water use backup wells)
- Water Tank
- Service Building
- Electrical Building
- Hoist House and Rocky's Shop (for warehouse and equipment storage)
- Access/Utility Tunnels necessary for the PMLU facilities
- South Storm Water Pond
- Storm Drainage System
- MWTU Ponds #2 and #3 (until groundwater abatement per DP-61 is completed)

These facilities are listed on Table 4-2 and shown on Figure 1-2b and Figure 1-4.

### 3.3.4 Radiological Levels for PMLU

Preliminary surveys performed in the habitable buildings designated for the PMLU indicate that radiological surface contamination does not exceed the gross alpha surface contamination limit of 5,000 dpm/100 cm² specified in the MMD-approved March 2021 Site Radiation Protection Program Manual (Table 3-1a). A final radiological characterization survey will be conducted prior to completion of mine closeout/closure to determine whether radiological contamination associated with closeout/closure activities has affected these facilities. Areas with radiological surface contamination exceeding 5,000 dpm/100 cm² gross alpha will be decontaminated, as necessary, to meet the applicable release criterion. The selected criterion of 5,000 dpm/100 cm² gross alpha is consistent with NRC Regulatory Guide 1.86 and is more conservative than the surface contamination level calculated to correspond to a 100 mrem/yr dose limit. No Waiver from Self-Sustaining Ecosystem or Post-Mining Land Use

RGR is not seeking a waiver from the regulatory requirements to establish a self-sustaining ecosystem or post-mining land use under 19.10.5.506C and 507B NMAC. RGR proposes livestock grazing as the primary PMLU for the broader permitted area, with wildlife habitat as a natural, compatible, and concurrent use. Once native vegetation is successfully re-established on reclaimed portions of the site not used for other purposes, grazing is expected to be sustainable and consistent with the historical and generational land use of the San Mateo area. The WRP and expanded disposal cell area will be fenced and permanently restricted from livestock grazing to protect the engineered cover system, including the rock mulch erosion layer, store-and-release soil cover, and shallow-rooted native grass community needed for long-term evapotranspiration performance.

Light industrial, commercial or government use of the service and support structures to be left in place, are additional PMLUs that will provide valuable infrastructure for sustainable economic opportunities for the San Mateo community and for RGR's continued business endeavors in New Mexico.

# 4.0 DESCRIPTION OF CLOSEOUT/CLOSURE ACTIVITIES

RGR's mine reactivation program, initiated in January 2018 and suspended in December 2019, was structured in four sequential phases:

- Phase 1 – Environmental Upgrades
- Phase 2 – Water Treatment Facilities Upgrades
- Phase 3 - Dewatering and Water Treatment Reactivation
- Phase 4 – Underground Facilities Reactivation

The scope of Phase 1 was focused on environmental clean-up and environmental upgrades identified in the Revision 13-2 of the Mine Permit (RGR, 2013b) and set as priorities in the Implementation Plan of DP-61.

Phase 1, initiated in 2018, was planned to include activities that were equally necessary for both reactivation and closeout/closure. Phase 1 was substantially completed by December 2019 and included (Kuhn, 2019):

1. Reshaping and flattening the west and northwest slopes of the WRP to 5H:1V grades.
2. Constructing the south and west berms of the disposal cell.
3. Constructing the disposal cell clay liner.
4. Excavating radiologically contaminated sediments and soils from all MWTU pond basins and placing material in the disposal cell.
5. Reshaping of MWTU Ponds #2 and #3 and upgrading their associated hydraulic control structures.
6. Reshaping and lining the SSWP and installing hydraulic control structures.
7. Installing double HDPE liner systems in MWTU Ponds #2 and #3.
8. Leak testing and commissioning of MWTU Ponds #2.
9. Upgrading and extending the surface water drainage system.
10. Constructing the new septic system.
11. Installing the North Force Main.
12. Began removing ore from the low-grade ore stockpile to an off-site licensed facility at MMD and NMED direction.

The Phase 1 work started in January 2018 with the preparation of construction bid documents. Earthwork began in May 2018, focused on reshaping the WRP and SSWP, reconstruction of the stormwater drain system, initial construction of the disposal cell and reconstruction of MWTU Pond #3. Phase 1 construction work was substantially completed by the end of December 2019 and was addressed in supplemental reports of closeout/closure construction in 2020 and later.

Removal of the ore pad was the only Phase I activity not initiated before the end of 2019. This activity could not begin until all the low-grade ore on the pad had been removed. Ore pad removal was completed in April 2022. Removal of the ore pad material is pending approval of the disposal cell expansion.

After RGR made its decision to begin the closeout/closure process of the mine, work related solely to mine reactivation in Phases 2, 3 and 4 ceased. RGR continues to conduct closeout/closure activities under its active status permit. Many activities, such as earth moving and facility removal, are suspended until approval is granted to expand the disposal cell. Expansion of the disposal cell is necessary as the existing and approved 13-acre disposal cell has been filled to near-capacity by the volume of contaminated sediments and soils excavated from the MWTU ponds (Ponds 1 through 8) during Phase I.

The following sections describe the closeout/closure practices (Section 4.1), activities completed by September 2026 (Section 4.2) and activities remaining to be completed (Section 4.3).

## 4.1 Closeout/Closure Practices

For Phase 1 and subsequent closeout/closure activities, Best Management Practices (BMP) were followed and will be followed, including "Best Practice in Environmental Management of Uranium Mining," IAEA Nuclear Energy Series NF-T-1.2. (IAEA, 2010), and Federal Highway Administration (FHWA) Best Management Practices for Erosion and Sediment Control FHWA-SLP-94-005 (Roberts, 1995). Technical specifications for some measures, as appropriate and as previously provided in the CCP, are contained in Appendix C. Future technical specifications of closeout/closure measures will be provided as part of submitted work plans or design sets. Select closeout/closure measures are illustrated in the drawing sheets contained within Appendix A Drawing Sheets CL 05, CL06, CL 07A, CL 07B, CL 08 and CL 14.

All contractors using heavy equipment, trucks, and other materials involving fuel, lubricant, solvents or capable of collecting and transporting solid contaminants will be refueled, serviced, washed, and parked in a specified area. This area will be located by the contractor and approved by RGR. The area will include a temporary wash facility with a temporary liner and water collection system. Alternatively, a temporary decontamination area will be set at the concrete wash bay adjacent to the production shaft, unless and until it is scheduled for removal under closeout/closure. Wash water will preferentially be transported to MWTU Pond 3 and evaporated or evaporated at the temporary decontamination site. Residues from evaporated water will be removed for disposal, either temporarily stored for placement in the disposal cell or offsite in a licensed facility.

At the time of this submittal, small quantities of solvents and lubricants from the maintenance shops may remain on site at the time of closeout/closure. The products being used and expected to be in use throughout that time are listed in Table 4-1.

Radiation levels in the facilities that will be retained for PMLU do not exceed the NRC Regulatory Guide 1.86 criteria for unrestricted release and use. A final radiological characterization survey of these facilities will be conducted to ensure release criteria are met (see Section 3.3.4).

## 4.2 Closeout/Closure Activities Completed

Since early 2018, RGR has completed numerous closeout/closure activities, including those specific to Phase 1, in accordance with the Mine Permit. These activities include, but are not limited to, the dismantling of numerous service and support facilities deemed non-essential for PMLU (Section 4.2.1), addressing non-essential concrete foundations (Section 4.2.2), removal of other facilities (Section 4.2.3), and the regrading of the WRP (Section 4.2.4).

The following Phase I reactivation tasks have been completed during the period of Mine Permit No. CI002RE, Rev. 13-2 (after 12/29/2017):

1. Reshaping of the WRP
2. Construction of the disposal cell liner and south, west and north-west berms
3. Excavation of contaminated sediments and soils within the eight MWTU ponds.
4. Construction and commissioning of MWTU Ponds 3 and 2
5. Filling of the existing 11.5-acre disposal cell to near-capacity
6. Covering the filled disposal cell with 24 inches of compacted clay and 12 to 18 inches of loam soil
7. Re-constructing the SSWP and septic system
8. Upgrading the surface water drainage system
9. Removal of the low-grade ore stockpile

Table 4-2 lists the status of each mine facility and its disposition at the time of this report.

### 4.2.1 Removal of Service and Support Facility Units

At the time of this report, the following service and support facilities have been dismantled at the mine.

1. Compressor Building
2. York Chiller Building

3. Chiller Pump Building
4. Chlorine Building
5. Shaft Heating Buildings (2)
6. Glycol Heat Exchanger
7. Cooling Towers
8. Fire Equipment Building
9. Carpenter Shop
10. Water Treatment Building
11. Storage Buildings
12. Flocculant Treatment Building
13. Barium Chloride Treatment Facility
14. Portable Building
15. Fuel Pump House
16. Fuel Storage Tanks
17. Mine Ventilation Structure (fan and base)
18. Ore Car Rails
19. MWTU Pump House and Motor Control Center
20. Production Shaft Headframe
21. Manway/Ventilation Shaft Headframe
22. Car (Maintenance) Shop
23. Emergency Hoist House
24. Treated Water Discharge Pipeline
25. Chiller Building Electrical Room
26. Trailer House

Table 4-2 lists the status of these and other mine structures, as well as the facilities that will be retained for support of post-mining land use identified in Section 3.3.3.

The dismantled building materials have been sheared into manageable pieces and either scanned and transported offsite, staged for the disposal cell, or are waiting for scanning to identify the final disposal location. This will be determined through radiological scanning to evaluate whether the materials meet the acceptance criteria for offsite disposal, thereby minimizing the volume of material requiring disposal in the disposal cell

Once RGR completes the characterization and segregation of the materials qualified for unrestricted release, the clean material will be staged in the parking lot north of the guard house until they can be recycled.

The remaining materials intended for the disposal cell will be moved to one of three NMED-approved staging areas on the site (Figure 4-2). Waste materials stored within the three proposed staging areas are temporary. RGR intends to relocate all staged waste materials to the expanded disposal cell following plan approval by MMD and NMED.

The locations of the three staging areas and the surrounding stormwater drainage patterns are reflected in Figure 4-2. While the staging areas are open to direct precipitation, they are protected from surface water run-on and run-off through the following measures:

- Siting: The staging areas have been intentionally placed outside of concentrated surface water flows and within footprints previously approved by NMED (2024).

- Run-off Controls: Stormwater run-off from these areas is fully managed by the comprehensive engineering upgrades completed under the approved DP-61.

- Permit Compliance: These DP-61 upgrades were specifically designed and constructed to enhance NPDES compliance. They provide run-off controls and increased surface water retention capacity within the permit area. These controls are engineered to remain effective across all phases: active operating status, post-mining land use, and the long-term, post-closeout period.

These three areas were also selected based on the following operational and environmental criteria:

- Spatial Efficiency: The staging areas are strategically located outside the immediate footprint of the proposed disposal cell. This separation avoids operational interference, ensures safe equipment clearance, and facilitates uninterrupted construction of the disposal cell upon approval.

- Minimizing New Surface Disturbance: The staging areas utilize existing, historically disturbed footprints from previous mining operations. By confining temporary storage to these already developed operational areas, RGR avoids impacting undisturbed native ground surfaces or undisturbed topsoil resources.

### 4.2.2 Concrete Foundations

Concrete foundations (including floor slabs) of the facilities will be either:

- Left in place and rubblized, then covered with clean soil; or

- Left in place intact.

- Rubblized and then placed in the disposal cell.

If no other purpose can be found, the rubblized concrete will be placed in the expanded disposal cell. All concrete left in place will be covered with two feet of soil.

Prior to removal of facilities and buildings, and breakage of the associated concrete foundations, radiological surveys of the structures will be conducted to determine whether the materials meet free-release criteria. Only those concrete foundations meeting the release criteria of the appropriate NRC guidance, as demonstrated via the radiological survey results, will be buried in place. Those that fail to meet release criteria will be buried in the disposal cell along with other contaminated materials. RGR will make reasonable efforts to reduce the amount of materials to be placed in the disposal cell through characterization studies. Materials found not to be radiologically contaminated will be separated and buried as clean fill or released from the site for proper disposal or recycling.

Table 4-2 provides a list of the disposition of the facilities and foundations. Except for the Electrical Building (preserved for PMLU), all facilities on the Compressor bench are to be removed in preparation for remediation of potentially diesel-contaminated soils existing beneath portions of the Compressor bench.

The foundations for the fire equipment building, emergency hoist house, glycol heat exchanger, and storage building are to remain intact for use as material storage areas for PMLU. The radiological surveys for these facilities demonstrated that the release criteria were met (Table 3-1c).

The concrete foundations around the manway shaft and production shaft will not be broken, so as to provide protection and confinement for the shaft plugs (when constructed). These foundations will be covered with two feet of clean soil once construction around the shaft is completed. In addition to providing a growth medium for revegetation, the soil cover will also minimize the chances of surface stormwater from entering the shafts.

The following foundations have been rubblized (Table 4-2):

a. Water Treatment and Boiler Building (#09 on Table 4-2): foundation also removed
b. Compressor Building (#10 on Table 4-2): foundation staged
c. Portable Building (#12 on Table 4-2): foundation also removed
d. Fuel Pump House (#13 on Table 4-2): foundation also removed
e. Carpenter Shop (#14 on Table 4-2): foundation also removed
f. Fuel Storage Tanks (#15 on Table 4-2): foundation staged
g. York Chiller Building (#17 on Table 4-2): cover pending
h. Car (Maintenance) Shop (#23 on Table 4-2): foundation also removed
i. Chiller Pump Building (#25 on Table 4-2): cover pending
j. Barium Chloride Treatment Facility (#31 on Table 4-2): cover pending
k. Flocculant Treatment Facility (#34 on Table 4-2): foundation also removed

l. Mine Water Treatment Pump House (#36 on Table 4-2): foundation also removed

m. Chiller Building Electrical Room (#40 on Table 4-2): cover pending

The foundations that remain and their disposition (Table 4-2) include:

a. Manway Shaft Headframe (#01A on Table 4-2): removed to ground surface, then remain intact for protection of shaft plug

b. Production Shaft Headframe (#02A on Table 4-2): removed to ground surface, then remain intact for protection of shaft plug

c. Shaft Heating Buildings (2) (#04A on Table 4-2): retain as part of shaft plug

d. Storage Building (#04B on Table 4-2): leave intact for PMLU

e. Emergency Hoist House (#04C on Table 4-2): leave intact for PMLU

f. Glycol Heat Exchanger (#05 on Table 4-2): leave intact for PMLU

g. Fire Equipment Building (#19 on Table 4-2): leave intact for PMLU

h. Cooling Towers (#26 on Table 4-2): foundation to be rubblized

i. Chlorine Building (#27 on Table 4-2): foundation to be rubblized

### 4.2.3 Removal of Other Facilities

The removal status of other facilities is:

a. Process Water Piping: estimated at 20% dismantled, temporarily staged for placement in expanded disposal cell

b. Mine Rails: removed, temporarily staged for placement in expanded disposal cell

c. MWTU Pond Hydraulic Structures: demolition was completed in 2026 for all ponds except for the MWTU Ponds #2 and #3 concrete overflow weirs, debris temporarily staged for placement in expanded disposal cell

d. Low-grade Ore Stockpile: removal completed, transported to White Mesa Mill

e. Discharge Pipeline and Structures: 100% dismantled, either recycled offsite after clearance or temporarily staged for placement in expanded disposal cell

The status of closeout/closure activities of facilities is summarized in Table 4-2. That table summarizes the disposition of mine facilities, including those already decommissioned or removed and those still to be either retained for post-mining land use or removed as part of closure activities.

### 4.2.4 Waste Rock Pile and Disposal Cell Status

The initial activity in Phase 1 construction involved re-shaping of the WRP, followed by construction of the disposal cell within the 11.5-acre WRP footprint approved under Revision 13-2

of the Mine Permit (RGR, 2013b). The integrated WRP and disposal cell are the permanent repository for radiologically contaminated materials generated on site that exceed applicable unrestricted release criteria. By December 2019, the disposal cell was filled to near-capacity after the MWTU ponds were remediated during the reactivation stage of the active status permit. Filling the disposal cell to near-capacity was a result of RGR's efforts to comply with the permit and remove all soils exceeding the accepted soil cleanup standard of 6.8 pCi/g Ra-226 (1.8 pCi/g background plus the 5 pCi/g regulatory limit). At that time, RGR recognized it could not proceed with earthwork remediation efforts unless the disposal cell was expanded. RGR continued to fill any available capacity of the disposal cell with contaminated materials throughout 2020 as it awaited decisions by MMD and NMED on expanding the disposal cell. As-built drawings for this phase are provided in Appendix J.

RGR submitted a permit modification request (MOD 20-1) in May 2020 to MMD (RGR, 2020), to alter the PMLU list of retained buildings, to expand the disposal cell from 11.5 to 25 acres, and to alter the closeout/closure schedule. MMD initially indicated a simple permit modification was appropriate under its definitions, however, NMED informed RGR that a formal modification of Discharge Permit DP-61 (as defined by NMED rules) would be required (NMED, 2021). As of the date of this CCP submittal, regulatory approval of the disposal cell expansion is pending. Because of the need for approval to expand the disposal cell, RGR has focused its closeout/closure efforts on removing facilities rather than continuing with earthwork remediation.

## 4.3 Closeout/Closure Activities Pending

At the time of this CCP submittal, the closeout/closure actions taken from 2018 through mid-2026 have accomplished many of the CCP goals. RGR continues to remove and encapsulate contaminants and facilitate the designated PMLU(s).

The large-scale site remediation will resume once regulatory approval of expansion of the disposal cell is approved as part of the DP-61 renewal and the Mine Permit revision.

Shaft closure, for the purpose of this CCP, and the information in Section 4.3.1 is unchanged. MMD has agreed to continued discussions and clarification which regulatory agency has shaft closure jurisdiction.

### 4.3.1 Shaft Plugging

Both the production shaft and the manway/ventilation shaft will be closed in the same manner, as approved in the current Mine Permit (RGR, 2013b) and detailed in Appendix A (Drawing Sheets CL 05 and CL 06) and Appendix C.3. In the approved Mine Permit design, the design utilized recycled steel from the headframes. However, a subsequent structural analysis revealed that this design did not provide an acceptable factor of safety against failure for the production shaft plug. A set of revised conceptual design drawings has been prepared by Critical View Engineering (Appendix G).

The updated design by Critical View Engineering is essentially the same concept of plug design as approved previously, namely a steel reinforced structural member. However, the construction materials are slightly different. The new concept is to utilize a steel (rebar) reinforced concrete

plug rather than steel I-beams encased in concrete. Structurally reinforced concrete is a proven and well-established structural member design, utilized in most new building construction around the world. The advantage of this revised concept is that the steel is encapsulated sufficiently to prevent corrosion, and the constructability of the structural member is more easily accomplished. The factor of safety is higher, and the structure is more efficient in shape and size.

Using the Technical Specifications in Appendix C.3, the entire closure plug will extend to a estimated depth of 62 ft in the production shaft and 40 ft in the manway shaft. Construction is anticipated to follow these procedures:

- Equipment and fittings within the shaft collar will be removed down to the sub-collar level.

- Once protruding steel and other obstructions have been removed below the sub-collar, a temporary work deck, supporting scaffolding, and concrete forms will be installed to facilitate construction of the reinforced concrete shaft plug

- The reinforced concrete shaft plug shall be constructed of reinforced concrete of appropriate design strength (Appendix A Drawing Sheets CL 05 and 06, Appendix G).

- The final shaft closure design will incorporate structural features to transfer plug loads into competent host rock rather than relying on the existing shaft lining for long-term support. These features may include rock keys or other engineered load-transfer mechanisms developed during final design. The final shaft closure design will be submitted for review and approval prior to construction.

- The structural plug will be constructed at the sub-collar level. The closure design does not include backfilling the shaft below the structural plug.

- Following curing of the reinforced concrete shaft plug, the shaft interval above the plug, including accessible connecting drifts and openings above the plug, will be backfilled with a controlled low-strength cementitious slurry consisting of soil, Portland cement, fly ash, and water. Mix proportions will be established during final design using laboratory testing of available materials.

- The remaining portion of the shaft collar will be capped with reinforced concrete and include a permanent survey/marker monument. The surface completion will accommodate and protect the two proposed shaft monitoring pipes while preventing surface runoff from entering the shaft. The final design will also include provisions for additional monitoring devices or sensors, if required.

Field evaluations are currently being conducted under the Site Investigation Plan (EA, 2025a) to address near-surface sub-collar seepage observed in the 14-foot diameter manway shaft. A targeted plan to seal this seepage will be developed based on these findings.

Infiltration or inflow of water from surface runoff will be prevented by the shaft plug and backfill in each shaft. The existing shaft liner and annular grout also provide a barrier to infiltration. Therefore, the proposed shaft closure measures will be protective of groundwater quality from both mine-level and surface sources of potential contamination.

A system of tunnels provides access to, and utility corridors for, the shafts and facilities (Figure 1-2b). The portions of the tunnels connecting directly to the shafts will be backfilled with slurried, weak, soil-cement (flowable fill) as part of shaft closure. The steel culvert running from the compressor bench to the car shop will also be closed with flowable fill.

### 4.3.2 Well and Conduit Plugging

#### 4.3.2.1 Conduits

Two vertical utility conduits, consisting of casings that extend from the ground surface down to the mine level, are scheduled for permanent plugging. Both conduits have an 11.5-inch outer diameter (O.D.) and are cemented in place within 12.5-inch diameter boreholes. The north conduit extends to a depth of 3,100 feet, while the south conduit extends to a depth of 3,200 feet.

All plugging activities will be conducted in strict accordance with NMAC 19.24.4. Prior to the commencement of any field activities, a comprehensive conduit plugging workplan—which will include the specific grout mix design and procedural methodology—will be prepared and submitted for regulatory approval.

#### 4.3.2.2 Dewatering/Depressurizing and Deep Aquifer Monitor Wells

As required under DP-61, two PLH aquifer wells, one THD aquifer well, and two WWC aquifer wells will be utilized for post-closure monitoring. Some of the existing dewatering wells may be suitable for that purpose, depending on well condition and the results of ongoing well rehabilitation efforts. The abandonment and potential replacement of certain wells may be required in some cases.

Regarding site water supply, at least one dewatering well completed in the PLH aquifer (DW-2A) is currently designated for domestic water supply and is utilized to provide water for site activities, such as well cleaning. This well, along with others designated for PMLU (e.g., DW-6, which is also equipped with a pump), will be retained to support mine site reclamation and will continue in that purpose throughout the CCP and post-closure monitoring.

Any dewatering well not used for site water supply or post-closure monitoring will be plugged and abandoned as part of site closure. Additionally, seven wells (designated as SM wells) used to observe drawdown in the mine area during active dewatering will also be plugged and abandoned (Figures 1-4 and 1-7). All wells that will be utilized for post-closure monitoring will be plugged and abandoned once post-closure monitoring is complete.

#### 4.3.2.3 Abatement Monitoring and Recovery Wells

There are 37 shallow alluvial and Upper Menefee wells in the groundwater-abatement monitoring program as of the time of this report (Figure 1-6 and Table 1-3). In the summer of 2026, 14 new

wells were installed to provide additional data on aquifer characteristics and to further delineate the extent of groundwater impacts from historical mining activities. Of these newly installed wells, 12 are designed for monitoring and two are intended for recovery (MW-1MR and MW-11AR). Notably, four of the new wells (MW-12, MW-13, MW-1MS, and MW-9S) were dry upon completion.

The new well installations are designed to provide critical data to address several key site objectives:

- Differentiate between the Menefee, alluvial, and shallow perched hydrostratigraphic units, and identify the variability and limitations of groundwater flow between them.
- Characterize aquifer properties and delineate the lateral and vertical extent of groundwater exceeding NMED water quality standards for uranium, selenium, and nitrate.
- Evaluate the hydraulic communication between the different hydrostratigraphic units.
- Identify areas of perched water and potential sources of groundwater recharge.

Additionally, the two newly constructed recovery wells (RW-1MR and RW-11AR) were intended to extract and remediate impacted groundwater near existing monitoring wells MW-1M and MW-11A. However, during extensive well development efforts, both wells were repeatedly pumped dry at low extraction rates of 1 to 1.5 gallons per minute. Additional evaluations are currently underway to determine the sustainable pumping rates of these wells and to assess their viability for long-term groundwater remediation.

The enhanced monitoring network reflects an improved understanding of site hydrogeology developed since implementation of the Stage 2 Abatement Plan (Metric, 2010). While the existing abatement program has reduced constituent concentrations in portions of the shallow groundwater system, additional investigations have shown that the hydrostratigraphic framework and the lateral and vertical extent of groundwater impacts were not fully defined. Consequently, additional monitoring and recovery wells are being installed to better characterize groundwater conditions and improve the effectiveness of future remediation efforts.

RGR has been addressing detected nitrate and uranium contamination under a NMED-approved Stage 2 Abatement Plan (S2AP) (Metric, 2010) since 2011. Once the abatement program objectives are achieved (to reduce constituent concentrations within the shallow groundwater system to levels that meet WQCC standards), these active abatement wells will be plugged and abandoned. Likewise, any future abatement wells that are installed will be plugged and abandoned once the wells' abatement program has ended.

Before plugging and abandoning is initiated for any wells, the contracted licensed water well driller will submit to the OSE a deep well plugging plan on OSE's Form WD-08 that will include:

- Sealant design with ratios and material specifications of seal components.

- Well construction details – borehole and casing diameters, screen types and intervals
- Depth to water
- Casing annulus seal description
- Plugging steps
- Documentation and reporting of well plugging

Plugging and abandonment will be conducted in accordance with the approved OSE well plugging plan and NMAC regulations (19.27.4 NMAC, 2017). The conduit and deep well plugging plan will be submitted for approval separately. Abatement wells and post-closure monitoring well plugging plans will also be submitted separately.

### 4.3.3 Surface Facilities Removal Pending

Surface facilities not needed for PMLUs described in Section 3.2, will be demolished. Table 4-2 lists all surface buildings, their sizes and their disposition at closeout/closure. Facilities remaining to be demolished include:

- Process water piping
- Remaining MWTU Ponds #2 and #3 hydraulic structures (concrete overflow weirs)
- Foundations (as detailed in Table 4-2)
- Sanitary Treatment Plant
- Ore Loading Pad and Wash Bay
- Shaft Sump Cleanout Bin
- Ore Pad Storm Water Retention Pond
- Plant and Refrigeration Water Pipelines
- CMP Utility Tunnel
- Ore Pad

Radiological characterization surveys have been and will be conducted to determine whether contamination exists at levels that exceed the NRC Regulatory Guide 1.86 criteria for unrestricted release.

Building demolition debris and other scrap materials will be managed based on these survey results:

- Unrestricted Release: Materials meeting the unrestricted release criteria, or those successfully decontaminated to meet them, may be removed from the site for salvage or recycling.
- Disposal Cell: Materials exceeding unrestricted release criteria, including contaminated demolition debris (e.g. scrap steel, pipe, and concrete), will be placed in the onsite disposal cell.

All pipes that are exposed and within three feet of the surface, except the potable water line in the utility tunnels, will be removed and buried in the disposal cell. Other pipes that are deeper than three feet will be either capped or plugged and left in place.

Demolition of facilities will include removal of concrete slabs or other foundations not needed for PMLU. Uncontaminated concrete slabs not retained for PMLU may be broken and covered by clean soil or removed for placement in the disposal cell.

Generally, MWTU ponds will be decommissioned during closeout/closure. However, MWTU Ponds 2 and 3 will remain in use until the groundwater abatement project is successfully completed. RGR envisions the need to keep these ponds for storing contaminated water for at least the first half of the 12-year period of responsibility. These two ponds are monitored for water quality and water levels quarterly, per requirements of DP-61, and will take additional time to remediate because of the steps involved:

- Evaporate remaining water.
- Remove and transfer contaminated sediments
- Remove pond liners.
- Demolish hydraulic controls structures and associated piping.
- Backfill the pond basins.

Contaminated pond sediments and soils in these pond areas will be removed and placed in the disposal cell. Contaminated demolition debris, including scrap steel, pipe and concrete, will be placed in the disposal cell. Clean debris may be removed from the site for salvage and recycling.

The buried drainage culvert from the storm drain along the county road (Figure 1.-2b), which diverts runoff away from the mine water treatment area, will not be removed. As part of the PMLU, it will continue to direct water to the SSWP.

## 4.4 Earthwork

Excavation of soils that require cleanup as part of the closeout/closure will begin after the disposal cell footprint is expanded. Cultural resource surveys, and clearances if required, will be performed on any land surface not previously surveyed that will be disturbed by closeout earthwork. In general, earthwork will involve short hauls by dozer to redistribute berm fills or mine waste rock and by scraper, excavator and trucks or grader for contaminated soil removal. Some loader

excavation and short truck hauling may be required, as well. Except for short pushes of up to 300 ft on pond berms and WRP slopes, the working grades are less than 5%.

Borrow Area A, located within the permit area and previously approved for use under the current Mine Permit, is no longer expected to provide the primary volume of clean soil needed for the expanded disposal cell. The 2025 borrow source investigation indicates that Borrow Areas A and B have been partially or fully excavated during previous construction activities and that remaining quantities are likely insufficient for the proposed expansion. RGR therefore intends to use clay deposits identified in Borrow Area C, within the permit area, as the preferred primary source for clean clayey soils needed for engineered caps, low-permeability layers, and clay liner components. Borrow Area B, west of the permit area on RGR land, may be retained only as a supplemental or alternate source if usable quantities remain. Borrow Area C is approximately 14 acres in size and is preferred because it is undisturbed and can provide a substantial volume of fine-grained, clay-rich material with favorable engineering properties.

In 2025, Engineering Analytics (EA) completed a borrow source investigation for Borrow Areas A, B, and C. The investigation included the excavation of 24 test pits excavated to depths of approximately 6 ft, including six in Area A, five in Area B, and 13 in Area C, as documented in the *Expanded Disposal Cell Design* report (Appendix K; EA, 2026c). The investigation concluded that Areas A and B have been partially or fully depleted by prior containment cell construction, while Borrow Area C contains undisturbed, fine-grained, clay-rich soils suitable for low-permeability cover, cap, and liner applications. Subsequent laboratory testing confirmed that Borrow Area C soils exhibit properties consistent with engineered cover requirements, including moisture content, Atterberg limits, percent passing No. 200 sieve, Standard Proctor compaction, soil water characteristic curve, flexible wall permeability, and consolidated undrained triaxial shear testing.

The proposed access to Borrow Area C will be provided via the existing access road that exits the MWTU area through the north gate, crosses over the Marquez Arroyo, and connects to a newly constructed gravel road, as shown in Figure 1-2. Reclamation of the access road and borrow area will include regrading the ground to minimize water ponding, scarifying the ground, and revegetating according to Appendix F.

Cut slope stabilization will focus on maintaining existing infrastructure while improving localized stability where needed. Cut slopes above the chiller bench will remain at their current slope to maintain existing wells and conduits at base of slope. A protective fence will be installed at the top of the wall. The slope below the chiller bench requires no additional work, because it is already stable and vegetated. The cut slope to the south of the hoist house will have additional fill placed at the toe and extended upward to the base of the existing wire fencing to improve stability.

Once the disposal cell expansion is approved, contaminated soil removal will proceed in a controlled sequence that supports radon attenuation, maintains cell stability, and separates materials by placement function. Soils from the NSWP and ore pad area will be removed first because these materials contain residual low-grade uranium ore from mine production. They will be placed toward the bottom of the disposal cell to minimize radon flux through the final cover.

Diesel-impacted soils from the 2019 release area will be placed next because they contain weathered hydrocarbons, no free-phase product, and compaction behavior compatible with engineered placement. Contaminated soils from the support area and other operational zones will then be placed above the petroleum-impacted soils, followed by remaining contaminated soils from the MWTU area and affected lands outside the mine site. A secondary disposal cell will be built abutting the proposed main cell to contain materials from MWTU Ponds 2 and 3, the SSWP, and miscellaneous contaminated sediments. Table 4-4 lists the estimated quantities and locations of these materials prior to excavation.

Site regrading after soil cleanup will be completed using soils from previously disturbed areas to the extent practicable. Sufficient native fill volumes are calculated to be available from the design cut quantities on site (Table 4-3). For engineered caps, low-permeability layers, clay liner components, or other clean soil needs associated with the expanded disposal cell, Borrow Area C will be used as the preferred primary source. Borrow Area B may be retained as a supplemental or alternate source, only if usable quantities remain. These soils consist of sandy clay, clayey sand and clay with Unified Soil Classification of SC and CL as determined by test pits and laboratory testing and meet the engineering requirements for reclamation fills and engineered cover applications. Table 4-3 lists the estimated clean soil requirements, source areas, and overall earthwork balance.

The United States Department of Agriculture (USDA) Natural Resource Conservation Service (NRCS) web site (NRCS, 2026) indicates that site soils will naturally support western wheat grass, vine mesquite, alkali sacaton, and four-wing saltbush. Site soils consist primarily of low-to-moderate plasticity clays and sandy clays, with localized alluvial sands, gravel, and cobbles in arroyo deposits. Contaminated soils will not be used for closeout/closure covers, reclamation fill, or backfill outside the engineered disposal cell.

### 4.4.1 Existing Waste Rock Pile

Starting in 2018, RGR reclaimed the WRP to protect it against erosion. In the initial step of this reclamation, RGR reshaped the existing WRP to enhance long-term structural stability. The north, west and south slopes were flattened to 5H:1V, as represented in the lower slopes shown in the disposal cell as-built drawings (Appendix J), and then covered with 2 ft of compacted clay. The clay was sourced from Borrow Areas A and B, which were partially or fully depleted during prior containment cell construction, and from the clean shaft muck soil stockpile located in the southwest corner. The shaft muck was used to construct the south slope of the WRP.

Disposal of non-rock waste generated during closeout/closure was controlled to minimize long-term settlement. Materials were placed in loose lifts not exceeding 12 inches and compacted with surrounding soil. Hollow items, such as pipes, conduits, tanks, and vessels, were either placed in disposal trenches and flow-filled with a soil/cement slurry or filled with suitable clean earthen material to eliminate unsupported voids.

Contaminated soil and pond sediments, excavated as part of the reactivation of the mine, were the first materials placed in the newly constructed clay-lined disposal cell on the WRP. after these materials were consolidated, the WRP slopes were finish-graded. Historical phases used temporary

erosion control materials (e.g., Curlex® or other surface stabilization materials) ; however, the expanded disposal cell will use a permanent 52-inch cover system consisting of a 12-inch compacted clay radon barrier, 28 inches of on-site soil, and a 12-inch rock mulch admixture for long-term erosion protection.

The mound of shaft muck (soil stockpile) that formerly occupied the southwest corner of the WRP was found to have levels of radiation at or below background and supported healthy volunteer vegetation, so it was used to reshape the south slope of the WRP. Results of soil tests (Appendix D) show that the shaft muck has weathered to soil consistency and classifies as low to moderate plasticity clay and clayey sand (loam in USDA classification), like the soil that covered the ore stockpile, on which two feet of cover supported healthy volunteer vegetation.

### 4.4.2 Disposal Cell and Expansion

The disposal cell, which was constructed atop the WRP, is the permanent repository for contaminated pond sediments, soils and demolition debris generated by mine site closeout/closure activities. RGR constructed the current disposal cell during the mine reactivation phase (2018-2019), according to an approved design. This initial cell was constructed within the 13-acre footprint of the WRP. The existing disposal cell was filled to near-capacity by the contaminated materials (sediments and soils) excavated from MWTU pond basins, stormwater ponds, and other designated locations within the Mine Permit area. As of April 2022, the disposal cell had reached a filled volume of approximately 99,300 cubic yards (RGR, 2021). No new material has been placed within the disposal cell since 2020.

To accommodate the further remediation of the site during closeout/closure, the expanded portion of the disposal cell will be located east and north of the existing disposal cell and WRP at a nominal bottom elevation of 7,340 ft (Figure 4-1). The expanded cell will be up to 12 acres in area, which brings the total permanent containment footprint of the WRP plus disposal cell to 25 acres. A low permeability liner, consisting of not less than 1 ft of compacted clay soil (CL, CH, or SC soils per USCS classification), will be constructed under the expanded disposal cell to protect regional groundwater. Construction quality control (CQC) and construction quality assurance (CQA) plans shall be submitted to NMED for approval a minimum of 30 days before the clay liner construction. Within 60 days after liner completion, a CQA report and as-built plans shall be submitted to NMED.

This expanded disposal cell provides for permanent, engineered disposal of multiple waste streams. As illustrated in Figure 4-1 and Table 4-4, it will serve as the repository for contaminated pond sediments, radiologically contaminated soils, non-hazardous diesel-impacted soils generated during corrective action activities, and demolition debris generated during mine closeout/closure. If additional waste streams or more complex waste mixtures are identified during ongoing characterization, they will be evaluated using this same multi-parameter waste classification process to determine waste management and disposal requirements based on applicable regulatory criteria. The final position and precise dimensions of the expanded closure cell will be confirmed after closeout/closure activities are complete.

To date, no demolition debris has been identified as containing Resource Conservation and Recovery Act (RCRA) Subtitle C hazardous waste. Similarly, a comprehensive assessment of diesel-impacted soils (EA, 2026f) confirmed that these materials do not meet the definition of hazardous waste under RCRA, as they are not listed wastes and do not exhibit hazardous characteristics (ignitability, corrosivity, reactivity, toxicity per TCLP). A spatial analysis confirms that elevated diesel concentrations (exceeding the NMED industrial SSL of 3,000 mg/kg TPH-DRO) do not spatially coincide with radiological hotspots (Ra-226 > 20 pCi/g). Therefore, the material does not constitute a mixed radioactive and RCRA hazardous waste. In areas where both contaminants co-occur (e.g., Mine Compound), diesel concentrations remain well below the SSL (≤170 mg/kg). The expanded disposal cell's overall design—including its low-permeability clay liner, radon-attenuating cover, and long-term monitoring—is technically compatible with the co-placement of both waste streams. Limited quantities of asbestos-containing material (ACM) identified during previous site activities and have been removed and disposed of by a certified asbestos abatement contractor at a properly permitted offsite disposal facility. Any additional ACM encountered during mine closeout/closure will be managed in accordance with applicable State and Federal regulations, removed by a certified asbestos abatement contractor, and disposed of at a properly permitted offsite facility.

After waste placement and final grading, an engineered cover will be placed over the waste material. This cover will provide a barrier to reduce water infiltration, protection from erosion, support of vegetation, and radon attenuation. Extensive modeling for unsaturated flow, radon emanation, and frost penetration has been completed to finalize the cover design, as detailed in the *Expanded Disposal Cell Design* report (Appendix K, EA, 2026c).

The optimized cover system uses a 52-inch passive store-and-release configuration designed for the site's semi-arid climate. From top to bottom, the cover consists of 12 inches of rock mulch admixture, composed of 30 percent gravel and 70 percent soil, for wind and water erosion protection; 28 inches of compacted on-site soil for moisture storage and frost-depth buffering; and 12 inches of compacted clay as the primary radon and infiltration barrier. The system limits radon-222 surface flux to 13.99 pCi/m²/s, below the 20 pCi/m²/s regulatory limit, and restricts deep percolation to a design-basis rate of 0.40 inches per year.

### 4.4.3 Ore Pad Working Surface Removal

The ore pad material will be excavated by loader and hauled by truck to the disposal cell, alongside other cleanup related materials, in accordance with the Reclamation and Post-Reclamation Radiation Work Plan (ERG, 2020). A radiological characterization of the Ore Pad (AVM, 2023) was performed in 2023. Estimated quantities to be removed are found in Table 4-4.

### 4.4.4 MWTU and NSWP

The sediments in the Mine Water Treatment Unit (MWTU) Ponds #1 and #4 through #8 have been excavated and placed in the approved 11.5-acre disposal cell, as described in Section 4.4.2. They contained low levels of uranium, radium, barium sulfate and other constituents in the sediments from the mine and mine water treatment circuit described in Section 2.4.2 and Appendix D.

MWTU ponds were allowed to dry by natural evaporation, then the pond sediments were removed until residual gamma readings in the underlying soil met the soil cleanup standard (Appendix D).

A subsequent radiological characterization of the MWTU (AVM, 2024) was performed in 2024 that identified small, localized areas of cleanup that remain to be removed to the disposal cell. These estimated quantities for these remaining areas are provided in Table 4-4.

Once the Ore Pad is removed, the NSWP will be excavated to clean (background) radium values, with the contaminated materials being placed in the disposal cell (when expansion is approved).

MWTU Ponds #2 and #3 are lined with a double HDPE membrane system and are used for the evaporation of contaminated groundwater, surface water runoff, and other wash-water generated on site. These two ponds will be used during closeout/closure until groundwater abatement objectives have been achieved. When no longer needed, any newly generated pond sediments will be removed and the pond liners will be removed and placed in the disposal cell, then the hydraulic controls and related structures including foundations in the pond area will be demolished.

The NSWP sediments have not yet been removed. They will be excavated and placed in the disposal cell like the MWTU pond sediments.

After the hydraulic control structures of the ponds are demolished and all debris is removed, clean berm soils, not exceeding MMD's 2016 Joint Guidance standard of 5 pCi/g Ra-226 above background (MMD and NMED, 2016), will be used to fill the pond basins. Soil will be spread and compacted in lifts not to exceed eight inches. The area will be regraded to match final design grade (Appendix A, Drawing Sheets CL 07A and CL 08).

### 4.4.5 Affected Areas

Affected areas outside the immediate mine boundary will be reclaimed in strict accordance with 19.10.5.507.A NMAC and 19.10.1.7.R(1) NMAC (NMAC, 2001a; 2001b). Pursuant to 19.10.1.7.A(3) NMAC, an "affected area" is defined as any area outside of the designated permit area where land surface, groundwater, or air resources are impacted by mining operations conducted within the permit area (NMAC, 2001b).

RGR is currently identifying these affected areas and will continue to characterize and survey surrounding lands in accordance with the agency-approved *Reclamation and Post-Reclamation Radiological Survey Work Plan* (ERG, 2020a). Current delineation efforts are focused on characterizing contiguous lands surrounding the facility, with specific emphasis on identifying and bounding areas potentially impacted by windblown or water-borne radiological constituents.

Borrow Area B

Borrow Area B is situated on land that RGR owns but it is outside the permit boundary (Figure 1-2). No mining occurred on this land, and no activities were performed that were related to mining. Borrow Area B was used to supply the clay required to construct the 2-foot-thick clay cap on the west and northwest slopes of the WRP. Borrow Area B is comprised of a shallow pit and access road. The depression is presently being used as a stock pond and has 3:1 slope. The pit and access road will be regraded and revegetated according to Appendix F.

Borrow Area B was opened to supply these materials in the 3rd quarter of 2018, shortly after these specific clay materials were exhausted in Borrow Area A. Borrow Area B was reopened in 2020 to provide these same heavy clays to construct the 2-ft thick cap covering the disposal cell after it had been filled to near-capacity. RGR does not intend to use any more material from Borrow Area B because the supply of clay materials appears to be nearly exhausted.

There was some prior gamma survey conducted in the vicinity of Borrow Area B. Trinitech conducted a soil investigation of the areas west and north of the mine site in 2012 to investigate environmental dispersal of uranium from the Mt Taylor Mine (Trinitech, 2012) (Appendix D.2). Sixteen soil samples were collected and analyzed along arroyos that drain the mine property. Gamma dose rates were also measured. The conclusions of the memo indicated that no discernable dispersal of uranium from the mine property was detected.

Four soil samples were collected and analyzed in 2012 within the area of Borrow Area B location: MTE-12 to the west, MTE-13 and -14 to the south and MTE-6 to the west (Figure labeled "April 23, 2012, Soil Sample Locations", Appendix D.2). Uranium concentrations were below 1 pCi/g except for MTE-13 (1.4 pCi/g). Radium-226 concentrations were below the background of 1.8 pCi/g except for MTE-13 (2.7 pCi/g). All radium-226 values were below the accepted soil cleanup standard (background +5 pCi/g) limit of 6.8 pCi/g. Further gamma dose rates of these four samples were less than the Post Reclamation Radiation Level of 24 urem/hr, which is equivalent to 6.8 pCi/g. These four samples were located near drainages, where uranium dispersal from the mine would have a higher probability of accumulating.

A radiation characterization survey will be performed, as needed, for Borrow Area B and any contaminated soil will be removed so that the area meets the soil standard. Borrow Area B will be graded and revegetated according to Appendix F.

Continental Divide Substation Area

The electrical substation, located north of the Service Building (Figure 1-2), is within the permit boundary but is under the control of the Continental Divide Electric Cooperative and Public Service of New Mexico. Before final closeout, a radiation characterization survey will be performed, and any contaminated soil will be removed and placed in the disposal cell so that the area meets the soil standard. RGR will work with the substation owners on any potential reclamation and revegetation site work.

County Road 334

Existing NM 334 and its right-of-way through Section 24. The right-of-way is not under RGR now nor during mining. This surface is dedicated to public use and is not subject to reclamation or PMLU considerations under the Mining Act. A radiation characterization survey was performed in 2025 (AVM, 2026), and any contaminated soil will be removed so that the area meets the soil clean up standard. No revegetation is expected as the area is comprised of a gravel roadway. RGR will work with the Cibola County Road Maintenance Department to re-establish the roadway once contaminated materials are remediated.

San Lucas Canyon Outfall

Outfall 001 is located at the northern terminus of the former treated water discharge pipeline within San Lucas Canyon. Historical environmental investigations conducted between 2013 and 2015 evaluated soils, groundwater, surface water, sediment, and downstream impoundments and generally concluded that historical treated mine water discharges did not result in significant downstream environmental impacts requiring additional characterization at that time. As part of the mine closure program, RGR is planning additional characterization of the area immediately downstream of Outfall 001 to further evaluate localized elevated gamma radiation identified during the 2020 radiological survey. Additional information regarding the historical investigations and planned characterization is provided in the Outfall 001 Historical Summary and Planned Characterization Technical Memorandum (Appendix M: EA, 2026e).

### 4.4.6 Excavation and Disposal of Contaminated Soil

#### 4.4.6.1 Waste Characterization and Management Strategy

RGR's waste management strategy is based on extensive site characterization data rather than a rigid assumption of only two waste classes. Characterization data from the Mt. Taylor Mine indicates that the site does not contain complex hazardous mixtures, heavy metal-organic wastes, or regulatory "mixed wastes." The diesel-impacted soils onsite are non-hazardous under the Resource Conservation and Recovery Act (RCRA) All identified contamination exceeding established cleanup standards will be remediated and placed in the expanded disposal cell.

#### 4.4.6.2 Radiological Contamination and Cleanup

As is typical for a uranium mining operation, radiologically impacted materials associated with historical mining activities are present at several locations within the Mine Permit boundary. These areas include the Waste Rock Pile (WRP), Mine Water Treatment Unit (MWTU) areas, Service and Support Area (Mine Compound Area), Ore Pad Area, stormwater retention ponds, and limited areas north of Marquez Arroyo associated with historical windblown contamination. Since 2023, RGR has completed extensive radiological characterization investigations throughout the Site to identify the nature and extent of radiologically impacted materials, estimate impacted material volumes, support remedial planning, and facilitate mine closeout/closure activities. The radiological characterization reports are provided in Appendix D.1.

Investigative radiation surveys and soil sampling were initially performed in 2012 (Appendix D.1) and have continued through 2026. These investigations established background concentrations of radium, characterized radiologically impacted soils and materials, and provided the information necessary to support reclamation and closeout/closure planning. Background concentrations resulting from naturally occurring radium unrelated to mining activities were established through sampling conducted in 2007 and 2012 and are incorporated into the Mine Permit and DP-61. The approved background concentration for Ra-226 is 1.8 pCi/g.

Radiologically impacted soils and materials will be managed in accordance with the 2016 Joint Guidance for the Cleanup and Reclamation of Existing Uranium Mining Operations in New Mexico (MMD et al.) and the approved Work Plan for Post-Mining Radiological Surveys of Permit Area and Impacted Lands (ERG, 2020a). Based on the approved background concentration of 1.8 pCi/g Ra-226, soils exceeding the Site investigation and cleanup criterion of 6.8 pCi/g Ra-226 will be excavated, as appropriate, and placed in the disposal cell. Final status surveys will be conducted, as appropriate, to verify that remediation activities have achieved the applicable cleanup criteria. The radiological characterization investigations and final status surveys completed to date will be used to support implementation and verification of mine closeout/closure activities.

#### 4.4.6.3 Diesel-Impacted Soils

Along with the remediation of uranium-contaminated soils, RGR will remediate the remnants of historical diesel spills located in the vicinity of the compressor bench (Figure 1-2) (Ensero, 2021a).

- **1991 Spill:** Originally reported while reactivating and flushing a previously abandoned potable waterline connected to the Car Shop water tanks (RGR, 1991). The area was subsequently remediated through removal of contaminated soil and seven underground storage tanks (RGR, 1992). The remediation was completed, and no further remedial actions are anticipated.

- **2019 Spill:** A diesel spill was reported while RGR was reactivating facility piping (RGR, 2019a). A limited inspection indicated petroleum hydrocarbons were detected in the riser pipes, a portion of the potable waterline by the risers, the red-lid manholes, the Car Shop potable water system, and the surrounding ground (RGR, 2019b). The source and extent of the petroleum hydrocarbon contamination continues to be investigated through the ongoing Diesel Investigation, which will support development of the corrective action plan.

NMED has approved the placement of these soils in the disposal cell (RGR, 2023a). RGR submitted a corrective action plan (CAP) to NMED in 2021 (Ensero, 2021a), and based on NMED comments, an updated CAP will be submitted in 2026.

#### 4.4.6.4 Disposal Cell Design and Waste Compatibility

The expanded disposal cell is engineered to safely consolidate soils impacted by diesel and radiological materials within a single containment unit. Because the primary diesel release area does not overlap with radiological hotspots, and any minor overlapping areas remain well below

NMED screening levels, these materials do not classify as mixed waste under RCRA or the Atomic Energy Act. The integrated design and compatibility framework relies on the following elements:

- **Containment Compatibility:** An engineered cover and liner system effectively isolates the waste. Published data confirms that the high-density polyethylene (HDPE) liner system is chemically and structurally suitable for long-term contact with the expected concentrations of weathered petroleum hydrocarbons.
- **Material Suitability:** The diesel-impacted soils contain only weathered hydrocarbons and lack free-phase product. This allows them to meet standard engineered compaction requirements without the need for specialized blending.
- **Placement Controls:** To ensure safe handling, diesel-impacted soils will be segregated during excavation, staged on impervious surfaces, and sampled to confirm their non-hazardous status. Their final location and depth within the disposal cell will be strictly documented.

This consolidated approach effectively isolates both waste streams from the environment and prevents surface water infiltration. Bolstered by a 70- to 95-foot natural geologic separation from regional groundwater, this integrated strategy minimizes long-term environmental risk and simplifies post-closure institutional controls.

#### 4.4.6.5 Excavation and Material Handling Operations

Access to the mine is controlled by fences, locked gates, and surveillance to prevent public exposure. Administrative and physical controls are implemented to maintain radiation exposures to levels as low as reasonably achievable (ALARA). Occupational exposure controls and monitoring (29CFR§ 1910.1096; OSHA, 2019) will continue throughout closeout/closure activities.

After the facilities demolition is complete and debris has either been staged (Figure 4-2) or placed in the disposal cell, soil excavation will commence. Gamma readings, correlated against Radium-226 soil samples, will be collected continuously during excavation. Contaminated soil in large, unobstructed areas will be excavated, loaded, and hauled to the disposal cell by truck or scraper. Smaller or obstructed areas of soil will be removed by loader, excavator or grader, and either windrowed for scraper pickup or loaded onto trucks for placement in the disposal cell. A final status survey consisting of independent laboratory analysis of soils from all remediated areas will be used to verify that soil remediation is complete. The technical specifications for contaminated soil earthwork are included in Appendix C.4.

### 4.4.7 Finish Grading

After demolition, soil cleanup, shaft and well plugging, and backfilling are complete, the mine site will be regraded as indicated on Appendix A Drawing Sheets CL 07A, CL 07, CL 08, and CL 14. The reshaping of the land will provide controlled drainage and will aid in the establishment of new vegetation. Grading will be adjusted as needed to remove obstacles or surface depressions that

might obstruct or divert runoff from the intended flow directions. The technical specifications for grading are included in Appendix C.4.

## 4.5 Revegetation

Following regrading, areas that have been disturbed by Mt. Taylor Mine operations and soil cleanup will be revegetated in accordance with the Revegetation Plan and Monitoring Protocols (Cedar Creek, 2025, Appendix F). Revegetated areas include the existing and expanded disposal cell area, the ore stockpile pad and runoff retention pond area, the mine water treatment pond area, borrow areas, and locations surrounding the demolished facilities within the service and support area. The SSWP bottom and other areas where mining-related features are retained (e.g. buildings and roads) will not be revegetated. RGR provided stormwater and erosion monitoring specifications for the areas that will not be revegetated in a Post-Closure Monitoring Plan (EA, 2026d; Appendix H).

Preparations for revegetation and the selected seed mix will be directed toward establishing a vegetation community that can thrive at this site and that can support grazing of livestock. Plants native to the general area will be used as much as possible to provide for long-term stability of the soil and vegetation communities. Plant species that provide rapid initial cover will be used in the seed mix to achieve initial soil stabilization. RGR may use irrigation water, as necessary, during drought situations only within the first three years after seeding to ensure the establishment of vegetation. Water for this irrigation will be provided by RGR's wells in the Point Lookout formation.

Runoff control during regrading and revegetation will use the most appropriate technology available at that time, including methods recognized by the NRCS or the International Association for Erosion Control. Measures that use present technology include check dams constructed of hay bales, geotextile silt fences secured in shallow trenches, and water bars across the disturbed area and perpendicular to the slope. Tobacco net, Curlex® or similar net-and-fiber mats might be used as required for protection of surfaces susceptible to rilling or wind erosion. The specific measures applied to revegetated surfaces will be based on the method most appropriate for the seeding method, erodibility and depth of the soils, degree of slope, proportion of large rocks at the surface, roughness of the surface, and anticipated rainfall.

Locations of temporary runoff controls will be selected, consistent with the Stormwater Pollution Prevention Plan (SWPPP), to slow down or divert runoff, trap sediment, and provide improved conditions for germination and plant establishment. Once revegetation has been achieved, temporary erosion control measures that have not disintegrated will be removed.

### 4.5.1 Revegetation Species

The predominant native grass species in the area is blue grama (NMEI, 1974); therefore, this species will be the primary species in the revegetation seed mix (assuming it is readily and economically available at the time of closeout/closure). The list of proposed species was optimized for the Mt Taylor mine site's specific soil and climate conditions (Appendix F).

### 4.5.2 Seedbed Preparation and Seeding

The regraded surfaces will be prepared for seeding by scarifying the surface and creating minor depressions to provide a proper seedbed. Seed will then be applied by either rangeland drill or broadcast. Broadcast seed will be incorporated into the growth medium by hand raking or some mechanical means such as heavy chains dragged behind tracked dozers.

*Amendments.* Organic soil amendments will be applied on a location-specific basis, taking into consideration the properties of the soil at that source. The material specifics and applications rates for the proposed amendments are described in Appendix F.

### 4.5.3 Seed Origin and Quality

Seed for the dominant species of grasses and shrubs that are indigenous to the mine area are available commercially and will be secured through those sources. All seeds must be certified, and each seed bag must have attached to it a complete label with certification information.

### 4.5.4 Revegetation Success

*Technical Standard* - The primary post mining land use is anticipated to be grazing, therefore, revegetation success in revegetated units will concentrate on four performance standards 1) vegetative ground cover, and 2) diversity, 3) woody plant density, and 4) productivity. Revegetation efforts will be considered successful when the following criteria have been met. The reference areas will be sampled along with the revegetation to provide a suitable comparison each year of assessment. In this manner, the success criteria outlined in the Revegetation Plan and Monitoring Protocols (Cedar Creek, 2025, Appendix F) is dynamic and adjusts to climatic conditions.

*Monitoring* - Monitoring of revegetated areas will be conducted on a periodic basis in accordance with the Revegetation Plan and Monitoring Protocols (Appendix F). Success of both germination and establishment will be dependent in large part on the moisture received in the summer and winter months and variations from year to year. Since establishment of vegetation is a function of its ability to reproduce, vegetation will also be assessed for its reproductive status, as well as its overall vigor. The survey will be conducted by a qualified vegetation specialist. Survey results will be analyzed and summarized to aid in determining the need for any changes in management practices or the need for reseeding or other supplementary practices. Less formal monitoring will be conducted throughout the year by RGR personnel to identify conditions in the revegetated areas that may require attention.

### 4.5.5 Management and Contingency Plans

After revegetation efforts have been completed, management of the revegetated areas will follow the Revegetation Plan and Monitoring Protocols (Cedar Creek 2025, Appendix F) and will include:

- Instruction of staff in measures to protect revegetated areas
- Posting of signs to warn against disturbance

- Placement, and replacement as necessary, of erosion controls
- Supplementary seeding of areas as necessary
- Periodic inspections and monitoring

Revegetation efforts will be repeated until successful. If results of annual monitoring indicate failure in all or part of a revegetated area, RGR will either supplement work already accomplished or revegetate the affected area, as appropriate. Efforts will be modified, as necessary, depending on what the cause of the failure is determined to have been.

## 4.6 Erosion Protection

The purpose of erosion monitoring of the disposal cell, WRP, SSWP, facilities and roads is to maintain the integrity and effectiveness of the disposal cell cover and stormwater retention or diversion measures.

Monitoring of the disposal cell /WRP includes conducting best management practices (BMPs) that include conducting inspections and making repairs as necessary to correct the effects of settling, erosion, or other significant events that may alter the effectiveness of the cover. Maintenance will prevent run-on and runoff from eroding or otherwise damaging the final cover.

Maintenance will involve repairing eroded areas by replacing lost soil material and reseeding. RGR considers any rill exceeding 6 inches of depth to be significant and requires soil replacement. Repairs will entail adding soil (in six-inch lifts and compacted) to the cover of the disposal cell. Lesser erosion will be addressed by regrading. Additional erosion control BMP's will be added where needed. These will include berms, silt fences, erosion blankets, hay bales and other water flow controls to minimize soil loss until vegetation becomes established.

Visual inspections of the ground surface will be carried out to monitor the physical stability of the disposal cell, WRP, and other reclaimed areas. Findings of the visual inspection and changes of the ground surface will be evaluated using professional judgement, informed by comparison to the closure criteria. This information will be used to generate a professional assessment of the physical stability of the disposal cell and WRP. Exceedances of the monitoring criteria will trigger geotechnical review and may or may not require corrective actions based on site-specific conditions. This may include a change in the frequency of monitoring.

### 4.6.1 Protection of the Existing Waste Rock Pile Surfaces

Erosion modeling using the Revised Universal Soil Loss Equation (RUSLE) performed for the original CCP submittal (RGR, 1998) showed that the maximum annual soil loss rate on the un-reclaimed WRP is only 0.02 T/acre/yr and would be reduced to less than 0.005 T/acre/yr after revegetation of the soil cover.

The analysis examined several base management scenarios, from smooth bare slope surface to 4-year-old vegetation on the modeled slope. For the modeled slope, representing the worst case for the WRP, 350 ft long at 20% slope, the best erosion protection is achieved by use of hay mulch.

The predicted soil loss is 0.77 t/ac/yr using hay mulch, compared to slightly higher soil loss of 0.82 t/ac/yr using rock mulch or gravel. For comparison, with vegetation after four years the predicted loss is 4.3 t/ac/yr, and a smooth bare surface is predicted to have 5.6 t/ac/yr soil loss. Therefore, RGR's use of certified weed-free hay mulch will provide the best slope protection while also encouraging vegetation of the WRP cover.

The WRP has been reshaped to avoid concentration of runoff and maintain sheet flow over the pile slopes. Erosion control blankets used in conjunction with revegetation should provide adequate interim protection of the 5H:1V and flatter slopes. If additional erosion protection is needed for surfaces on the WRP that are susceptible to erosion due to high runoff velocities or concentrated flows, such as steep slopes or drainage swales, riprap will be applied. Riprap screened for minus five inches with average particle diameter (d50) of not less 2.7 inches will be applied at least 0.5 ft thick in the bottom 1/3 of steeper slopes and as water bars in swales. Riprap will consist of basalt or equivalent rock.

Information on drainage structures and erosion protection design for the existing WRP is provided in Appendix B. Design runoff and shear calculations were prepared as part of the original CCP in 1998 (RGR, 1998). The updated erosion calculations for the expanded disposal cell design has been provided in the *Expanded Disposal Cell Design* report (Appendix K; EA, 2026c). The design will address erosion protection for the ultimate build-out size and shape of the disposal cell surfaces.

### 4.6.2 Arroyos

There are three arroyos at the mine site. There is a northern surface water diversion channel located north and east of the manway shaft and ore stockpile areas, which intercepts and diverts runoff northward to the Marquez Arroyo. The middle arroyo was largely filled in during site construction, but its remnants lead to the SSWP north of the WRP. The middle arroyo has a very small watershed; therefore, it receives little runoff. The southern arroyo (south diversion channel) was diverted at the time of mine development to run along the south side of the WRP.

Hydrologic analyses using the HEC-1 and HEC-2 models (Appendix B) show that the Marquez Canyon arroyo will convey the 24-hour, 100-year flood. These analyses show that the design flood water and energy surfaces are well within the arroyo banks in both cases, indicating that there should be no out-of-bank flow during the design flood and that the arroyo morphology appears to be in equilibrium with much larger runoff events.

The southern arroyo (south diversion channel) was diverted at the time of mine development to run along the south side of the WRP. The south diversion channel is currently in design. The New Mexico Department of Transportation (NMDOT) drainage criteria, as shown in their Drainage Manual, using the Simplified Peak Discharge methodology or the NRCS Unit Hydrograph methodology within the US Corps of Engineers Hydrologic Engineering Center-Hydrologic Modeling System (HECHMS) was used to develop flow rates and volumes. Existing development condition hydrology is the only scenario analyzed. Existing condition channel hydraulics were modeled using US Corps of Engineers Hydrologic Engineering Center-River Analysis System (HEC-RAS). Conceptual erosion control alternatives were analyzed for the south channel based

on NMDOT methodology to comply with mining requirements and regulations. Final condition hydraulics will be evaluated for the alternative selected and included in preliminary and final construction plans.

The north diversion channel, located north and east of the manway shaft and ore stockpile areas, intercepts and diverts runoff northward to Marquez Arroyo. The hydraulic analysis and design for the north diversion channel will be submitted at a later date. This is because closeout/closure activities will alter the final site grading, and the final survey cannot be completed until the ore pad has been removed.

## 4.7 Fencing

RGR has replaced and increased the height of existing fences on the mine site to provide better exclusion of cattle and wildlife from the mine site. One chain link fence, eight feet high, encloses the MWTU and is approximately 5,000 ft in length. Another eight-foot chain link fence will be up to 4,750 ft long surrounding the WRP and expanded disposal cell, depending on its final footprint. An additional 2,000 ft fence will be installed to prevent entry into the shaft areas.

# 5.0 POST-CLOSURE ENVIRONMENTAL COMPLIANCE AND MONITORING

Through the closeout/closure measures described in Section 4.0 and the requirements of other permits listed in Table 1-1 and described in the Environmental Site Assessment (RGR, 1994a), the Mt. Taylor Mine site is expected to stay within environmental standards for air and water quality.

## 5.1 Surface Water Monitoring

Surface water releases will continue to conform to NPDES-Multi Sector General Storm Water Permit (MSGP) No. NMR05J02B (NPDES, 2021) requirements until closeout/closure is completed and the permit has been terminated. The Post-Closure Monitoring Plan (EA, 2026d) (Appendix H) outlines all post-closure surface water monitoring, maintenance, and reporting requirements.

The surface water courses across the site are ephemeral. The storm water retention ponds collect runoff during larger storm or snowmelt events but are usually dry.

## 5.2 Evaporation Pond Leak Detection

As part of the surface water and facility management strategy, RGR will monitor evaporation Ponds #2 and #3 to ensure the pond liners remain intact and no fluids leak to the ground surface. This monitoring includes:

- Visual inspections of the liner surfaces for tears, rips, holes, and other defects.
- Recording the depth of water collected in the sump of each pond and calculating the leakage rate.

Should the action leakage rate be exceeded, RGR will repair the liners as needed, which may include pond evacuation, relining, and recertification of the repaired liners. Once the evaporation ponds are no longer needed for reclamation purposes, they will be reclaimed, and monitoring will cease.

## 5.3 Groundwater Monitoring

Per the following subsections, groundwater monitoring will be completed in the alluvial and Menefee, plus the deep aquifers.

### 5.3.1 Alluvial and Menefee Groundwater Monitoring

Previous mining activity has adversely impacted the shallow groundwater at the site. RGR has been addressing detected nitrate and uranium contamination under a NMED-approved S2AP (Metric, 2010) since 2011. Findings from site investigations indicate that the shallow groundwater quality and quantity is variable throughout the mine area. In various areas of the WRP and service areas, groundwater concentrations of arsenic, boron, chloride, iron, manganese, nitrate, pH, total radium, selenium, sulfate, total dissolved solids, and uranium exceed New Mexico WQCC drinking water standards.

Site investigations performed over the years (Willowstick, 2024; Ensero, 2021b; Willowstick, 2020; RGR, 2012; Kleinfelder, 2012; Metric, 2005; Metric, 2006; Metric, 2009; RGR, 1994a; NMEI, 1974) indicate that alluvium forms a discontinuous, thin veneer over residual soil and rock of the east-dipping Menefee shales and interbedded sandstones. The alluvial soil cover is thin or absent over most of the mine site. Shallow alluvial groundwater occurs primarily in preferential pathways that occur in the paleo arroyos that lie below part of the Service and Support area and the existing WRP (Willowstick, 2020; Kleinfelder, 2012).

The unlined sewage lagoon, used from 1975 to 1982, is the primary source of perched water and alluvial saturation and believed to be the source of uranium and nitrate observed in monitoring wells (Kleinfelder, 2012). Shallow groundwater flows from the site west-northwest along the alluvial-bedrock interface, primarily in paleo arroyos in the bedrock. Upper Menefee siltstones and sandstones, east of the mine site, provide groundwater recharge to alluvium and the Upper Menefee bedrock underlying the operational areas.

In addition to seepage of sewage lagoon water, minor amounts of water from over thirty years of precipitation and surface runoff infiltration contributes to a persistent groundwater mound within the WRP. The perched water migrates downward by gravity drainage along preferential pathways created by the different material buried in the WRP and paleochannels in the top of the Menefee bedrock (now buried beneath the WRP). This perched water is hydraulically connected to the underlying alluvial sediments and Upper Menefee silty sandstones as indicated by elevated uranium and nitrate concentrations present in monitor wells completed in the upper 50 ft of the Menefee in this area.

The S2AP (Metric, 2010) remedial action is extraction and evaporation of contaminated groundwater. RGR maintains a series of shallow recovery wells and alluvial/Menefee-aquifer and monitor wells as part of the ongoing abatement. Wells are completed in a perched-water zone within the WRP, in alluvium at the bedrock contact, and in the upper 50 ft of the Menefee Formation. Six wells (MW-6, WP-5, WL-2, WL-3, WL-4 and WL-5) are currently used as recovery wells. These wells are in the former lagoon area and on the western edge of the WRP (Figure 1-6, Table 1-3).

In 2026, RGR installed two more recovery wells (RW-1MR and RW-11AR) near MW-1M and MW-11A (Figure 1-6). Elevated levels of uranium and nitrate in the groundwater were detected in these areas during the 2020 site investigation (Ensero, 2021b).

A piping system, referred to as the North Force Main (NFM), was refurbished and updated during the 2018-2019 mine reactivation period. The NFM system is located just south of the Sanitary Treatment Plant (Appendix A Drawing Sheet CL03) and is comprised of a vault, pumps, and piping. The piping is buried and connects the vault to MWTU Pond #3. Monitor well WP-5 is plumbed into the NFM system, so that water extracted from the well can be pumped to MWTU Pond #3 for evaporation. Both the NFM and the WP-5 water delivery piping were leak-tested and certified leak-free by a registered New Mexico Professional Engineer, but neither has been placed into operation.

RGR intends to connect all other recovery wells to the NFM for transferring extracted water to MWTU Pond #3, if the recovery wells produce sufficient flow to justify connection. Because the recovery wells currently produce very low flow rates, impacted water may continue to be transported from the wells to MWTU Pond #3 using a mobile water tank. The existing above-grade HDPE pipeline and NFM system will operate throughout the closeout/closure period until they are no longer needed.

Piper diagrams of monitoring well water quality indicate that groundwater quality is highly variable at the mine. Water from wells MW-1C, MW-2F, and MW-1J are sodium-bicarbonate water (the predominant cation is sodium and the predominant anion is bicarbonate). Water from these wells represent background water quality in the Upper Menefee at the mine site. These three wells are located east of the WRP and have low total dissolved solids (TDS), low sulfate concentrations, and no elevated levels of chemicals of concern at the site. Water quality of all other abatement wells are sodium chloride-type waters (the predominant cation is sodium and the predominant anion is bicarbonate) and have variable levels of elevated TDS, sulfate, nitrate, and uranium concentrations. WP-4 water quality is a mixed-type water between sodium chloride and sodium bicarbonate. Details on the water quality monitoring and impacts of ongoing abatement are reported in the most recent quarterly DP-61 groundwater report (EA, 2026b).

Additional site investigation as part of the abatement program will continue to assess the source, nature and extent of groundwater impacts in the area of the shafts, near well MW-1M, and to the west and northwest of these areas.

Uranium (U) and nitrate ($NO_3$) isoconcentration maps for the shallow groundwater within the alluvial sediments and upper Menefee Fm have been provided in the Quarterly Groundwater Monitoring Report (submitted to NMED Ground Water Quality Bureau) in accordance with DP-61 (NPDES, 1998) and the S2AP (Metric, 2010) since the third quarter of 2018. The overall shape and magnitude of U and $NO_3$ distribution in shallow groundwater was relatively consistent from 2018 through the second quarter of 2021. The only notable change over that period with respect to uranium concentration was a greater than two orders of magnitude reduction at well MW-6, declining from 150 mg/L down to 1.1 mg/L. That well is completed across a perched water zone within the Waste Rock Pile (WRP).

Beginning in the second quarter of 2021, water quality from seven new monitoring wells (all completed in the upper Menefee Fm) were added to the quarterly reporting, and the results were included in the isoconcentration maps. The additional data points revealed a north-northeasterly trending arm of the nitrate and uranium plumes that extends up to newly installed well MW-1M. Note that this extension was not an indication of recent plume migration. Rather the extension reflected the addition of data in an area that was previously not part of the monitoring network.

From the third quarter of 2021 through the most recent sampling in the second quarter of 2026 (EA, 2026b), there has been little change in the shape or magnitude of either the U and $NO_3$ distribution in shallow groundwater at the Mt Taylor mine site (Figures 5-1 through 5-4).

Sulfate concentrations for the shallow groundwater monitoring network have been provided in the quarterly monitoring reports, but isoconcentration maps were not included (nor required under

DP-61). Sulfate isoconcentration maps for the shallow groundwater system (alluvial and Upper Menefee) from the third quarter of 2018 and the first quarter of 2026 are provided as Figures 5-5 and 5-6, respectively. Similar to the uranium and nitrate isoconcentration maps, the earlier sulfate map failed to detect the north-northeast trending arm of the plume that was later identified by wells MW-1M and MW4D.

Other potential sources of shallow groundwater contamination are the MWTU ponds, the ore pad and the NSWP, but such contamination is not expected. Well MW-3, which monitors groundwater down gradient of these areas, has not shown any exceedances of nitrate, uranium, nor radium (EA, 2026b). In the area of these features, the alluvial cover is thin or absent. The mine treatment ponds have been remediated and closed except for Ponds #2 and #3, which will remain open and serve as evaporation ponds until groundwater abatement activities are complete. Ponds #2 and #3 were remediated and reconstructed with HDPE liners and leak detection systems. The ore pad is graded so that water falling on it is directed to the NSWP. The NSWP is clay lined.

The S2AP (Metric, 2010) will continue to be followed until the groundwater quality meets the WQCC water quality standards for nitrate and uranium. RGR anticipates remediating site groundwater during the closeout/closure period. As needed, monitoring could extend beyond closeout/closure. Currently, groundwater extraction is the only approved remediation method, so no additional technology is included in this CCP. However, RGR intends to conduct a feasibility study of several other treatment options that potentially could accelerate groundwater remediation. The impacted groundwater and the effects of the abatement plan are being assessed through the DP-61 monitoring program. When the abatement plan objectives have been achieved, this monitoring program will be discontinued, and a completion report will be submitted to NMED.

Once the remediation goals are achieved, all abatement wells will be plugged and abandoned, except for five alluvial/Menefee wells (MW-1M, MW-4, WP-5, MW-11A, and the recently installed MW-15) that are proposed for monitoring water quality as part of the Post-Closure Monitoring Plan (EA, 2026d) (Appendix H). These well locations are shown in Figure 1-6. All wells that shall be plugged and abandoned will be done in accordance with OSE regulations and in consultation with OSE. RGR will submit a well plugging plan for approval prior to abandonment.

### 5.3.2 Deep Aquifer Groundwater Monitoring

As required by DP-61, RGR submitted a Post-Closure Deep Well Monitoring Plan (NV5, 2020) to NMED in April 2020. DP-61 Condition 57 (NMED, 2015) requires post-closure groundwater monitoring of the Point Lookout, Tres Hermanos, Dakota, and Westwater Canyon aquifers. RGR submitted an updated Post-Closure Monitoring Plan on June 30, 2025 (EA, 2025d) that included the water quality parameters and schedule for monitoring and reporting. In that plan, five wells were selected for long-term monitoring including: DW-3 and DW-10 (PLH aquifer wells); DW-11 (THD aquifer well); and DW-14 and DW-19 (WWC aquifer wells) (Figure 1-4). However, after that plan submittal, RGR received notice on September 25, 2025 from the New Mexico Office of the State Engineer (OSE) that all of those wells, with the exception of DW-14, may be in violation of NMAC 19.27.4, which does not allow for interaquifer exchange, and may require plugging and abandonment. Also, after the submittal of the June 2025 plan, NMED has indicated that additional

wells are required near the shafts to monitor potential impacts to aquifers penetrated by the shafts. The revised list of wells proposed for post-closure monitoring now includes DW-1 (PLH), DW-14 (WWC) and three new wells installed near the shafts: DMW-1 (PLH), DMW-2 (THD), and DMW-3 (WWC). Those locations are shown in Figure 5-7. Wells included in the PCMP may need to be changed or replaced, based on ongoing site reclamation and final site closure. An updated PCMP is included in Appendix H.

## 5.4 Radiological Safety and Monitoring

### 5.4.1 Radiological Safety

Radiation safety controls and monitoring are implemented to protect workers and the public consistent with applicable aspects of OSHA standards for ionizing radiation (29CFR§ 1910.1096 OSHA, 2019) (ionizing radiation) and NMAC standards for protection against ionizing radiation (20.3.4 NMAC, 2009) associated with uranium mine sites, and the ALARA requirement in 10CFR§ 20.1101 (NRC, 1991). The controls and monitoring will be implemented pursuant to the Mt. Taylor Mine Site (Site) March 2021 Radiation Protection Program (RPP) Manual (ERG, 2021) and its subordinate standard operating procedures (SOPs). The RPP includes radiation safety organization, radiation safety training requirements, ALARA policy, radiation dose standards, access controls, radiation protection controls, radiologic surveys and monitoring for exposures, associated SOPs, and environmental radiation monitoring. Radiation work permits (RWP) are written and implemented for one-time tasks which are not included in the WPs and RPP and are not ongoing activities. Applicable elements of the RPP will be updated for closeout activities, such as excavation and handling of uranium ore impacted material, that poses increased potential for exposure to workers and the public. The ongoing radiologic characterization of surface and subsurface soil will provide data that will facilitate any update of the RPP.

### 5.4.2 Radiological Surveying and Monitoring

The Site RPP (ERG, 2021) includes radiological contamination surveys, airborne particulate and radon monitoring for occupational exposure to radioactive material via internal pathways. The RPP also includes area TLDs and gamma radiation surveys for occupational exposure to radioactive material via external pathways. Radiologic monitoring for exposure to the public in the RPP consists of environmental area TLDs, radon gas monitors and airborne particulate monitoring as needed. The radiological surveys and monitoring specified in the RPP are consistent with NRC Regulatory Guide 8.30, 8.31 and 4.14 for radiation protection (NRC, 2002a; NRC, 2002b; NRC, 1980). Where warranted, the RSO will use the data generated by occupational radiation exposure monitoring to calculate estimates of radiological dose using conventional health physics principles and methods traceable to applicable State and/or Federal regulations and regulatory guidance documents.

The May 2022 MMD/NMED-approved *Work Plan for Post-Mining Radiological Surveys of Permit Area and Impacted Lands* for the Site (ERG, 2020a) includes surveys that will be utilized during the closeout activities. The radiologic surveys in the Site Work Plan are consistent with the *Multi-Agency Radiation Survey and Site Investigation Manual* (MARSSIM) (U.S. Department of Defense et al., 2000). Direct gamma scan and static surveys will be used for excavation control (Remedial Action Support) surveys during remediation (excavation and removal) of soils

exceeding the Ra-226 soil cleanup level. Direct gamma scan and static surveys and soil sampling and analysis will be used for Final Status Survey (FSS) for demonstrating compliance with the Site soil cleanup level following the soil remediation. U.S. EPA Method 115 (EPA, 2017) for monitoring of radon-222 emissions will be used over the uranium mine waste repository radon barrier to demonstrate compliance with the 20 $pCi/m^2/s$ radon flux emission standard.

During the post-closure period, long-term radiation monitoring will be conducted by a qualified radiation professional to evaluate the effectiveness and integrity of the Disposal Cell (DC) cover and to ensure facilities retained for light industrial and commercial PMLU meet criteria for unrestricted use.

Air Quality

Air quality impacts from Mt. Taylor Mine are minimal, resulting primarily from fugitive dust generated by truck traffic which is controlled by application of water as needed. Completion of closeout/closure measures will reduce truck traffic to occasional trips by the landowner if grazing is the PMLU. Traffic related to other continued use of mine facilities retained by the surface owners cannot be predicted at this time. Revegetation of disturbed ground and erosion protection on steep slopes will reduce other fugitive dust. There are no other sources of dust or gaseous emissions left after closeout/closure. For additional information on air quality, see page 14 of the Mt. Taylor Mine Site Assessment (RGR, 1994a).

## 5.5 Sanitary Treatment Plant Discharge

The sanitary treatment plant (STP), which has not operated since the early 1990's, will be demolished during the closeout and closure phase. The associated septic tank was inspected, determined to be in sufficient operating condition, and returned to service with the current septic system. It will remain operational through closeout. No monitoring of the septic system is planned.

## 5.6 Erosion Control and Stormwater Monitoring

After the CCP earthwork is completed and the surface water runoff controls have been installed in the area identified for commercial PMLU per the Erosion and Sediment Control Plan (RGR, 2018), RGR will initiate and continue erosion monitoring through the succeeding 12-year period, or until released under the New Mexico Mining Act.

RGR will visually inspect reclaimed land for signs of erosion and will mitigate significant erosion features to prevent soil degradation at the site. RGR will inspect drainage channels, diversion structures, retention ponds, and auxiliary erosion control measures and will repair and maintain them in accordance with the standards identified in the Field Office Technical Guides of the U.S. Natural Resource Conservation Service (NRCS), Section IV current at the time of the future erosion control monitoring activities.

Inspections will continue until the specific units are released under the New Mexico Mining Act (New Mexico, 2005). Inspections will be conducted monthly for the first year following completion of reclamation construction activities for each unit, and quarterly thereafter. Reclaimed

areas will also be inspected for evidence of erosion after storm events of one inch or greater in any one-day period.

Erosion control measures that are damaged or ineffective will be repaired or redesigned as necessary. RGR commits to using a variety of erosion control measures, as needed, if erosion control problems develop. Long-term erosion control measures will include the installation of berms, designed channels, and sediment containment structures, as necessary. Short-term erosion control measures may include, but not be limited to silt fences, hay bales, water bars, and mulching.

Monitoring methods include visual observation followed as needed by more quantitative methods that could include time-sequenced UAV-based imagery, close-range photogrammetry, silt fences, erosion bridges placed across active rills, and sediment traps at the terminus of rills. These and other methods are described in detail in *Upland Soil Erosion Monitoring and Assessment: An Overview* (BLM, 2011).

As a supplement to visual erosion inspections, ground surfaces created, disturbed, or reclaimed by closeout activities may be mapped by UAV-based imagery to document as-built topography and baseline terrain conditions. For the first three years after completion of closeout, the UAV imagery of reclaimed areas may be used as baseline conditions against which visual observations can be mapped. Based on those observations, erosion could be accurately located and quantitatively evaluated. Ideally, these observations and quantitative methods may be performed annually at the end of monsoon season.

As long as the NPDES Multi Sector General Storm Water Permit #NMR05J02B (NPDES, 2021) is active, RGR will continue to monitor stormwater discharges, as required, and operate in accordance with the Mt Taylor Mine SWPPP (Inspections Plus, 2019). RGR will inspect the entire length of all storm- and surface-water diversion channels, outfalls, the SSWP, and all associated structures for physical evidence of erosion and other damage that may compromise the integrity of the stormwater management system.

Even though the MSGP expiration date has passed, the EPA did not finalize the new 2026 MSGP before the deadline. As a result, the 2021 MSGP has been administratively continued. This means that since the mine had active coverage before February 28, 2026, the permit remains fully in force and effect until the EPA issues the new permit and requires a new Notice of Intent (NOI).

Stormwater and erosion monitoring will occur according the following schedule as listed in PCMP.

## 5.7 Vegetation Monitoring

Monitoring of revegetated areas will be conducted in accordance with the Revegetation Plan and Monitoring Protocols (Cedar Creek, 2025) (Appendix F). The revegetation liability period (the period that the owner is responsible for revegetation performance) under the MMD framework is 12 years, with monitoring evaluations conducted in Years 1, 3, 6, 9, 11, and 12. Results will be analyzed and summarized to assist in determining the need for any changes in management practices or the need for reseeding.

If it is determined at the end of the 12-year liability period that the vegetation needs additional time to mature, monitoring will continue once every three years until success evaluations are positive. Once final vegetation success is achieved and approved, routine vegetation monitoring will cease.

## 5.8 Meteorological Monitoring

The purpose of meteorological monitoring is to identify and record weather-related events, alerting RGR personnel to significant precipitation or wind events that may necessitate a site inspection. RGR monitors site-specific meteorological conditions daily using a Davis Instruments 6250 Vantage Vue wireless weather station located immediately south of the Guard House.

Weather data, including precipitation amounts, air temperature, and wind speed and direction, is recorded hourly, summarized into daily records, and transmitted via a wireless connection to a datalogger. Meteorological monitoring will continue on this hourly recording schedule for as long as post-closure monitoring activities are being performed at the site.

# 6.0 CLOSEOUT/CLOSURE SCHEDULE

The schedule for mine closeout/closure is shown in the Gantt chart in Figure 6-1. From initiation of the closeout/closure contracting process to completion of the closeout/closure activities on site is estimated to take about 5 years. The first 10 months would be taken up by project management and contractor procurement, followed by 52 months of actual construction activities on site from mobilization through demobilization.

# 7.0 COST ESTIMATE

Consistent with the Mine Permit, RGR will submit an updated detailed closure cost estimate within 60 days following approval of the CCP. The updated cost estimate will incorporate the final approved closure design, current contractor pricing, and other project-specific information available at the time of preparation.

The updated cost estimate will include the assumptions, methodologies, and supporting documentation used to develop the financial assurance estimate, including updated contractor pricing and other project-specific cost information, as appropriate.

Because the final closure design, construction sequencing, and associated closure activities remain subject to approval through the CCP review process, preparation of the detailed closure cost estimate has been deferred until completion of the CCP approval process.

## 8.0 REFERENCES

(Kuhn et al, 2013)
Alan Kuhn Associates LLC, EL Engineering Services, Trinitek Services, Inc. Surface and Subsurface Radiological Characterization, Windblown Area, Ore Pad Area and Mine Compound, Mt Taylor Mine Site, AVM Environmental Services, Inc, August 14, 2023. Addendum done April 1.

(Kuhn 2019)
Alan Kuhn Associates LLC. Mt Taylor Mine Phase 1 Completion Report, Storm Drainage System As-Built Drawings. April 9.

AVM. 2023. Surface and Subsurface Soil Radiological Characterization, Windblown Area, Ore Pad Area, and Mine Compound, Mt Taylor Mine Site, San Mateo, NM. August 14.

AVM. 2024. Treatment Pond Radiological Characterization, Mt Taylor Mine Site, San Mateo, NM. June 4.

AVM. 2026. South Controlled Area Soil Radiologic Characterization, Mt. Taylor Mine Site, San Mateo, NM. Prepared for Rio Grande Resources Corporation. Grants, New Mexico. February.

BLM. 2011. Upland Soil Erosion Monitoring and Assessment: An Overview, Technical Note 438.

Cedar Creek. 2025. Mt Taylor Mine Revegetation Plan and Monitoring Protocols. October.

(CPI, 2025)
United States Bureau of Labor Statistics (BLS). 2024. Occupational Employment Statistics, Occupational Employment and Wages, May 2021. United States Department of Labor, Bureau of Labor Statistics. https://www.bls.gov/oes/data.htm (accessed August 2025).

Critical View Engineering. 2022. RC Slab Shaft Closure 30% Design Plans. April 6.

EA. 2024a. Discharge Pipeline Abandonment Work Plan, Mt. Taylor Mine. Prepared for MMD. August 19.

EA. 2024b. Discharge Pipeline Abandonment Plan, Mt. Taylor Mine. Prepared for Forest Service and Cibola National Forest and Grasslands. September 25.

EA. 2025a. Rio Grande Resources' Response to May 16, 2023, Request for Additional Information on the 2021 Site Investigation Plan, Mt. Taylor Mine, DP-61, San Mateo, New Mexico. July 15.

EA. 2025b. Mount Taylor Site Conceptual Hydrogeologic Model, Deep Aquifer Systems. October 17.

EA. 2025c. Response to New Mexico Environment Department November 21, 2025, request for water quality data supporting elevated pre-mining fluoride levels in groundwater from the Point Lookout and deeper aquifers at Mount Taylor. Letter to Corey Dimond, New Mexico Environment Department, Ground Water Quality Bureau. Project No. 111360. December 30.

EA. 2026a Mt. Taylor Mine, Second Quarter 2026 Dewatering Wells Monitoring Report, Rio Grande Resources, San Mateo, New Mexico. June 29.

EA. 2026b. Mt. Taylor Mine Second Quarter 2026 Ground Water Monitoring Report, Rio Grande Resources, San Mateo, New Mexico. July 30.

EA. 2026c. Expanded Disposal Cell Design, Mt. Taylor Mine, Existing Mine Permit No. CI002RE. September 8.

EA. 2026d. Post-Closure Monitoring Plan, Mt. Taylor Mine, Discharge Permit DP-61. September 8.

EA. 2026e. Technical Memorandum: Outfall 001 Historical Summary and Planned Characterization. Prepared for Mr. Jeff Schoenbacher, Rio Grande Resources Corporation. EA No. P02601.367. August 26.

EA. 2026f. Evaluation of Diesel Placement in Proposed Expanded Disposal Cell (Project No. 111360). Prepared for Rio Grande Resource Corporation. September 4.(Ensero, 2021a)

Ensero Solutions, Inc. 2021a. Mt. Taylor Mine Diesel Release Corrective Action Plan. November.

Ensero. 2021b. Mt. Taylor Mine Diesel Release Investigation Report of Findings. April.

EPA. 2017. Method 115 Monitoring for Radon-222 Emissions. August 4.

EPA. 2024. Criteria for the Definition of Solid Waste and Solid and Hazardous Waste Exclusions. https://www.epa.gov/hw/criteria-definition-solid-waste-and-solid-and-hazardous-waste-exclusions (accessed September 26, 2024).

ERG. 2020a. Work Plan for Post-Mining Radiological Surveys of Permit Area and Impacted Lands, Mt. Taylor Mine, Rev 0. June 8.

ERG. 2020b. Radiological Survey Results for Discharge Pipeline and Soils Along Pipeline Corridor. Technical Memorandum to Bruce Norquist. July 6.

ERG. 2021. Radiation Protection Program Manual Mount Taylor Mine, Rev. 5. March.

Geohydrology Associates, Inc. 1994. Water Resources Report, Mount Taylor Uranium Mine, Cibola County, New Mexico (unpublished).

Inspections Plus, Inc. 2019. Stormwater Pollution Prevention Plan. April 22.

IAEA. 2010. Best Practice in Environmental Management of Uranium Mining. IAEA Nuclear Energy Series No. NF-T-1.2. International Atomic Energy Agency. Vienna.

Kleinfelder. 2012. Mine Waste Rock Pile Characterization Report, Mt. Taylor Mine, San Mateo, New Mexico, Rev. 2. March.

MARP. 1996. Closeout Plan Guidelines for Existing Mines. New Mexico Energy, Minerals, and Natural Resources Department. April 30.

(McGlothin, 1972)
McGlothlin, Bruce B. 1972. Aquifer Tests on Mine Shaft Pilot Well No. SM 24-38 San Mateo, Valencia County, New Mexico". Production Development Division Drilling and Well Completion Section Gulf Research & Development Company Houston Technical Services Center. Technical Memorandum No. 444T-C027. February.

Metric. 2005. Proposed Voluntary Stage 1 Abatement Plan for the Rio Grande Resource Corporation, Mt. Taylor Mine. April.

Metric. 2006. Final Site Investigation Report for the Rio Grande Resource Corporation, Mt. Taylor Mine. May.

Metric. 2009. Final Report, Rio Grande Resource Corporation, Mt. Taylor Mine. April.

Metric. 2010. Stage 2 Abatement Plan for the Rio Grande Corporation, Mt. Taylor Mine. August.

(MMD and NMED, 2016)
New Mexico Energy, Minerals and Natural Resources Department, Mining and Minerals Division (MMD) and New Mexico Environment Department, Mining Environmental Compliance Section (NMED). 2016. Joint Guidance for the Cleanup and Reclamation of Existing Uranium Mining Operations in New Mexico. March.

MMD. 2023. Comments on Closeout/Closure Plan Mt. Taylor Mine, Rio Grande Resources Corporation, Mt. Taylor Mine, Cibola County, New Mexico, Permit Tracking No. CI002RE. May 17.

MMD. 2024. 2nd Comment Letter, Mt. Taylor Mine, Disposal Cell Expansion and Update of Closeout/Closure Plan, Revision 22-1, Permit No. CI002RE. June 20.

MMD. 2025. 3rd Comment Letter, Mt. Taylor Mine, Disposal Cell Expansion and Update of Closeout/Closure Plan, Revision 22-1, Permit No. CI002RE. March 28.

MMD. 2026. Comment Letter, Mt. Taylor Mine, Update of Closeout/Closure Plan, Revision 22-1, Permit No. CI002RE. March 18.

New Mexico, State of. 2005. New Mexico Mining Act of 1993. NMSA 1978, §§ 69-36-1 to 69-36-20. Energy, Minerals and Natural Resources Department, Mining and Minerals Division. Santa Fe, New Mexico.

NMAC. 2001a. Title 19: Natural Resources and Wildlife, Chapter 10: Non-Coal Mining, Part 5: Closeout Plans for Existing Mining Operations. 19.10.5 NMAC. Effective February 15.

NMAC. 2001b. Title 19: Natural Resources and Wildlife, Chapter 10: Non-Coal Mining, Part 1: General Provisions. 19.10.1 NMAC. New Mexico Commission of Public Records, State Records Center and Archives. Santa Fe, New Mexico. May 15.

NMAC 2001c. Title 19: Natural Resources and Wildlife, Chapter 10: Non-Coal Mining, Part 7: Standby Status. 19.10.7.701 NMAC. New Mexico Commission of Public Records State Records Center and Archives. Santa Fe, New Mexico. May 15.

NMAC.2009. Title 20: Environmental Protection, Chapter 6: Water Quality, Part 4: Standards for Protection Against Radiation. NMAC 20.6.4. New Mexico Commission of Public Records State Records Center and Archives. Santa Fe, New Mexico. April 30.

NMAC. 2017. Title 19: Natural Resources and Wildlife, Chapter 27: Underground Water, Part 4: Well Driller Licensing; Construction, Repair and Plugging of Wells. NMAC 19.27.4. New Mexico Commission of Public Records State Records Center and Archives. Santa Fe, New Mexico. June 30.

NMAC. 2018a. Title 20: Environmental Protection, Chapter 6: Water Quality, Part 2: Ground and Surface Water Protection, Section 3101 Standards for Ground Water of 10,000 mg/l TDS Concentration or Less. NMAC 20.6.2.3103. New Mexico Commission of Public Records State Records Center and Archives. Santa Fe, New Mexico. December 21.

NMAC. 2018b. Title 20 Environmental Protection, Chapter 6 Water Quality, Part 2 Ground and Surface Water Protection, Section 3107 Monitoring, Reporting, and Other Requirements. NMAC 20.6.2.3107. New Mexico Commission of Public Records State Records Center and Archives. Santa Fe, New Mexico. December 21.

NMED. 2015. Rio Grande Resources Corporation's Mt. Taylor Mine/Discharge Permit-61 Renewal and Modification. October 20.

NMED. 2020. Radioactive Material License SO043-14. October 28.

NMED. 2021. Request for Submittal of a Permit Revision Application Including a Revised Closeout/closure Plan for Ming Act Permit No. CI002RE and Additional Information for Discharge Permit 61 (DP-61) Renewal and Modification, Rio Grande Resource Corporation, Mt. Taylor Mine. October 15.

[NMED, 2022a] New Mexico Environment Department, Surface Water Quality Bureau (SWQB). 2022. Request for Review and Comment, Mt. Taylor Mine and Mill, Updated Closeout/Closure Plan, Revision 22-1, Cibola County, New Mexico Mining Act Permit No. CI002RE, Revision 22-1. September 7.

[NMED, 2022b] New Mexico Environment Department, Air Quality Bureau (AQB). 2022. Request for Review and Comment, Mt. Taylor Mine and Mill, Updated Closeout/Closure

Plan, Revision 22-1, Cibola County, New Mexico Mining Act Permit No. CI002RE. September 12.

[NMED, 2023] New Mexico Environment Department, Mining Environmental Compliance Section (MECS). 2023. New Mexico Environment Department (NMED) Comments, Updated Closeout/Closure Plan, Revision 22-1, Mt. Taylor Mine, Rio Grande Resources, Cibola County, New Mexico, New Mexico Mining Act Permit No. CI002RE. April 14.

NMED. 2024. Email correspondence from Corey Dimond. August 12.

NMED. 2025a. New Mexico Environment Department (NMED) Comments Round 3, Mt Taylor Uranium Mine Closeout/Closure Plan, Cibola County, New Mexico, Mining Act Permit No. CI002RE. April 25.

NMED. 2025b. Request for Additional Information Round 3 Comments, Discharge Permit 61 Renewal and Modification Application, Mt. Taylor Mine, San Mateo, New Mexico. April 25.

NMED. 2026a. Request for Review and Comment, Mt. Taylor Mine, Cibola County, New Mexico Mining Act Permit No. CI002RE. February 19.

NMED. 2026b. *New Mexico Environment Department (NMED) Comments, Mt Taylor Uranium Mine, Updated Closure Closeout Plan, Mining Act Permit No*. March 6.

NMEI. 1974. An Environmental Baseline Study of the Mount Taylor Project Area of New Mexico, prepared for the Gulf Mineral Resources Company. Project No. 3110- 301. March.

NMOSE. 2022. Review and Comments, Revision 22-1 to Mt. Taylor Mine, Permit No. CI002RE, Rio Grande Resources Corporation. November 15.

NMOSE. 2024. Review of Revision 22-1 to Mt. Taylor Mine, Permit No. CI002RE, Rio Grande Resources Corporation. February 1.

NPDES. 1979. Groundwater Discharge Plan, Mt. Taylor Uranium Mill Project, New Mexico. December.

NPDES. 2016. Authorization to Discharge Under the National Pollutant Discharge Elimination System, Permit No. NM0028100. October.

NPDES. 2021. Multi Sector General Storm Water Permit No. NMR05J02B. EPA.gov. June.

NRC. 1980. Regulatory Guide 4.14 Radiological Effluent and Environmental Monitoring at Uranium Mills, Rev 1. https://mildos.evs.anl.gov/documents/Reg_Guide_4_14.pdf

NRC. 1991. Radiation Protection Programs (10CFR§ 20.1101).

NRC. 1992. Regulatory Guide 8.34 Monitoring Criteria and Methods to Calculate Occupational Radiation Doses.

NRC. 1993. Regulatory Guide 8.37 ALARA Levels for Effluent from Materials Facilities.

NRC. 2002a. Health Physics Surveys in Uranium Recovery Facilities. NRC Regulatory Guide 8.30, Rev 1.

NRC. 2002b. Information Relevant to Ensuring that Occupational Radiation Exposures at Uranium Recovery Facilities will be as Low as is Reasonably Achievable. NRC Regulatory Guide 8.31, Rev 1.

NRCS. 2026. *Soil map of Cibola County, New Mexico*. U.S. Department of Agriculture. Retrieved June 5, 2026, from https://websoilsurvey.nrcs.usda.gov/app/WebSoilSurvey.aspx

NV5. 2024. Preliminary Feasibility Mine Shaft Plugging Evaluation Report, Mt. Taylor Mine, San Mateo, New Mexico, 87020. March 16.

NV5. 2025. Existing Conditions Drainage Report and South Channel Improvements Concept Analysis, Mt. Taylor Mine. Rev 3. February 26.

OSHA. 1996. Ionizing Radiation (29CFR§ 1910.1096).

RGR. 1991. Initial Incident Telephone Report, Used Oil Spill, Rio Grande Resources Corporation. December 18.

RGR. 1992. Letter to New Mexico Environment Department Transmitting Analytical Data, Rio Grande Resources Corporation. March 12.

RGR. 1994a. Environmental Site Assessment, Mt. Taylor Uranium Mine Operations. June.

RGR. 1994b. Application for Permit for an Existing Mine, Mount Taylor Mine, Rio Grande Resources Corporation. December.

RGR. 1998. Mt Taylor Mine Closeout/Closure Plan. January.

RGR. 1999. Mt. Taylor Mine Permit Application for Standby Status. March.

RGR, 2013a. Application for Revision of Mine Permit No. CI002RE from Standby to Active Status and Modification of Ground Water Discharge Permit DP-61, Mt. Taylor Mine, San Mateo, New Mexico, Rev 1. November.

RGR. 2013b. Mt. Taylor Mine, Closeout/Closure Plan, Existing Mine Permit No. CI002RE, Discharge Permit DP-61. Rev 1. November.

RGR. 2015. Report on Soil and Water Sampling and Testing Water and Sediment Impoundment Locations Downstream of Mt. Taylor Mine Water Outfall 001. January 26.

RGR. 2018. Erosion and Sediment Control Plan, Commercial Post-Mining Land Use Area, Mt Taylor Mine, Rev.1. October 15.

RGR. 2019a. Supplemental 15-Day Suspected Petroleum Release Report, Mt. Taylor Mine, San Mateo, New Mexico. August 9.

RGR. 2019b. Report on the Limited Investigation of the July 3, 2019 Potential Diesel Release. December 18.

RGR. 2020. Permit Modification Request for Updated Closeout/Closure Plan Schedule, Updated PMLU and Disposal Cell Expansion, Permit CI002RE, Rev. 13-2; Mt. Taylor Mine. May 15.

RGR. 2021. Email communication with D. Ohori, EMNRD. April 27.

RGR. 2022a. Application for Revision of Mine Permit #CI002RE, Update of Closeout/Closure Plans to Current Conditions and Modification of Ground Water Discharge Permit DP- 61; Rev 1. April.

RGR. 2022b. Request for Submittal of Mine Permit Revision Application including a Revised Closeout/Closure Plan for Mining Permit #CI002RE, and Additional Information for Discharge Permit DP- 61 Renewal and Modification. June 13.

RGR. 2023a. Responses to a Request for Additional Information on the Diesel Investigation Corrective Action Plan and Addendum A, Report of the Discovery of a Light Non-Aqueous Phase Liquid in DW-3, Mt Taylor Mine, Rio Grande Resources, August 13.

RGR. 2023b. RGR Response to Comments to Request for Additional Information, Discharge Permit Renewal and Modification Application and Closeout/Closure Plan, DP-61, Mt. Taylor Mine, San Mateo, New Mexico, dated September 13, 2023. December 15.(Roberts,1995)

Roberts, Brian C. 1995. “Best Management Practices for Erosion and Sediment Control FHWA-SLP-94-005”. U.S Department of Transportation Federal Highway Administration. June 1.

Trinitek. 2012. April 2012 Soil Investigation, Memorandum Report to Rio Grande Resources. June 6.

U.S. Department of Defense, U.S. Department of Energy, U.S. Environmental Protection Agency, & U.S. Nuclear Regulatory Commission. 2000) Multi-agency radiation survey and site investigation manual (MARSSIM) (Revision 1) (Report Nos. NUREG-1575, Rev. 1; EPA 402-R-97-016, Rev. 1; DOE/EH-0624, Rev. 1). https://www.epa.gov/radiation/multi-agency-radiation-survey-and-site-investigation-manual-marssim

Willowstick Technologies LLC. 2020. Willowstick Investigation of Rio Grande Resources’ Mt. Taylor Uranium Mine, San Mateo, New Mexico – A geophysical investigation to identify

preferential groundwater flow paths and patterns in the shallow aquifer system beneath the south half of the mine site. July.

# TABLES

**Table 1-1 Other Permits**

| Name of Permit | Purpose | Expires |
|---|---|---|
| **Federal** | | |
| Multi Sector General Storm Water Permit #NMR05J02B | Stormwater discharge effective 06/17/2021 industrial plant | February 28, 2026, MSGP was administratively continued in March 2026 |
| **State of New Mexico** | | |
| Mine Water Discharge Permit NMED Permit #DP-61 | Mine water discharge and retention | October 14, 2020 (in timely renewal) |
| Mt. Taylor Mine Permits NM MMD Permit #C1002RE – Revision 13-2 | Active status December 29, 2017 | Applied for revision June 2022 (22-1), awaiting approval |

## Table 1-2 Groundwater Levels in Wells and Shafts

| Well No. | State Plane Coordinates (NAD 83) | | Top of Casing Elevation, Feet AMSL(a) | Well Depth, Feet from Surface | Well Depth, Feet Elevation AMSL | Screened Interval, Feet BGS (4) | Screened Interval Elevation, Feet AMSL (4) | Depth to Water, Feet from Top of Casing | Elevation of Water Level, Feet AMSL | Date of Water Level Measurement | Aquifer in Screened Interval (2) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | N | E | | | | | | | | | |
| DW-1 | 1579419 | 2782626 | 7342.0 | 1118 | 6222 | 740-890 | 6600-6450 | 474.84 | 6867.16 | 5/2026 | PLH |
| DW-2 | 1579121 | 2782606 | 7337.6 (b) | 2920 | 4425 | 2550-2920 | 4795-4425 | 739.98 | 6597.62 | 5/2026 | TH/D |
| DW-2a(1) | 1579202 | 2782709 | 7347.0 (b) | 925 | 6422 | 750-900 | 6597-6447 | 483 | 6864 | 4/2018 | PLH |
| DW-3 | 1579008 | 2782795 | 7350.1 | 1150 | 6197 | 737-891 | 6610-6456 | 594.55 | 6755.55 | 5/2026 | PLH |
| DW-4 | 1578965 | 2783021 | 7349.0 (b) | 1130 | 6214 | 750-900 | 6599-6449 | - | - | - | PLH |
| DW-5 | 1579038 | 2783256 | 7403.4 | 1172 | 6234 | 852-1002 | 6554-6404 | - | - | - | PLH |
| DW-6 | 1579210 | 2783402 | 7384.7 | 1190 | 6195 | 845-995 | 6540-6390 | 598.00 | 6786.65 | 12/2013 | PLH |
| DW-7 | 1579455 | 2783384 | 7376.3 | 1125 | 6251 | 825-995 | 6551-6401 | 567.41 | 6808.89 | 5/2026 | PLH |
| DW-8 | 1579672 | 2783240 | 7342.7 | 1044 | 6302 | 791-941 | 6555-6405 | - | - | - | PLH |
| DW-9 | 1579723 | 2782973 | 7337.6 | 2845 | 4495 | 2538-2840 | 4802-4500 | 613.22 | 6724 .38 | 5/2026 | TH |
| DW-10 | 1579619 | 2782734 | 7339.7 | 1065 | 6272 | 738-888 | 6599-6449 | 467.22 | 6872.48 | 5/2026 | PLH |
| DW-11 | 1578845 | 2783245 | 7445.0 | 3028 | 4418 | 2819-3028 | 4627-4418 | 899.58 | 6545.42 | 5/2026 | TH/D |
| DW-12 | 1579421 | 2783439 | 7418.9 | 2940 | 4479 | 2791-2940 | 4628-4479 | 821.22 | 6597.68 | 5/2026 | TH/D |
| DW-13 | 1579378 | 2782065 | 7322.3 | 3185 | 4132 | 3045-3185 | 4247-4132 | 739.76 | 6582.54 | 5/2026 | W |
| DW-14 | 1578847 | 2782182 | 7342.3 | 3205 | 4133 | 3048-3188 | 4290-4150 | 753.60 | 6587.70 | 5/2026 | W |
| DW-15 | 1578491 | 2782501 | 7393.5(b) | 3205 | 4142 | 3056-3196 | 4291-4151 | - | - | - | W |
| DW-16 | 1578334 | 2782995 | 7393.6 | 3275 | 4118 | 3105-3245 | 4288-4148 | 805.15 | 6588.45 | 5/2026 | W |
| DW-17 | 1578570 | 2783563 | 7496.8 | 3342 | 4159 | 3209-3342 | 4291-4159 | 908.19 | 6588.61 | 5/2026 | W |
| DW-18 | 1578902 | 2783778 | 7497.7 | 3314 | 4188 | 3212-3314 | 4295-4192 | 919 | 6578.70 | 5/2022 | W |

## Table 1-2 Groundwater Levels in Wells and Shafts Continued

| Well No. | State Plane Coordinates (NAD 83) | | Top of Casing Elevation, Feet AMSL(a) | Well Depth, Feet from Surface | Well Depth, Feet Elevation AMSL | Screened Interval, Feet BGS (4) | Screened Interval Elevation, Feet AMSL (4) | Depth to Water, Feet from Top of Casing | Elevation of Water Level, Feet AMSL | Date of Water Level Measurement | Aquifer in Screened Interval (2) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | N | E | | | | | | | | | |
| DW-19 | 1579493 | 2783781 | 7453.2 | 3274 | 4179 | 3166-3274 | 4287-4179 | - | - | - | W |
| DW-20 | 1579945 | 2783505 | 7386.1 | 3223 | 4162 | 2938-3223 | 4447-4162 | 811.36 | 6574.74 | 5/2022 | D-W |
| DW-21 | 1580165 | 2782966 | 7323.4 | 3184 | 4132 | 2873-3173 | 4443-4143 | 742.83 | 6580.57 | 5/2026 | D-W |
| DW-22 | 1579900 | 2782460 | 7305.4 | 3195 | 4110 | 3019-3159 | 4286-4146 | 723.83 | 6581.57 | 5/2026 | W |
| SM-24-38 | 1579116 | 2783008 | 7390.0 (b) | 3535 | 3814 | 3107-3247 | 4324-4184 | - | - | - | W |
| SM-24-43 | 1579029 | 2782948 | 7347.0 (b) | 3535 | 3812 | 3064-3204 | 4283-4143 | - | - | - | W |
| SM-24-89 | 1578964 | 2782908 | 7348.0 (b) | 3121 | 4227 | | | -- | -- | - | W |
| SM-15-59 | 1584519 | 2771754 | 7738.0 (b) | -- | -- | | | -- | -- | - | -- |
| SM-13-74 | 1584233 | 2783313 | 7480.0 | -- | -- | | | 1518 | 5962 | 10/1991 | -- |
| SM-31-1-2D | 1584519 | 2786914 | 7630.0 | -- | -- | | | -- | -- | - | -- |
| SM 24-23E | 1579711 | 2783249 | 7342.0 | 3077 | 4265 | | | 796.41 | 6550.59 | 5/5/2022 | D |
| 14-Ft Shaft | 1579520 | 2783065 | 7344.0 | 3340 | 4008 | | | - | - | - | N/A |
| 24-Ft Shaft | 1579122 | 2782964 | 7342.0 | 3300 | 4043 | | | 766 | 6576 | 9/2019 | N/A |

(1) Well DW-2a supplies domestic water from the Pt. Lookout Sandstone
(2) PLH=Pt Lookout/Hosta, TH= Tres Hermanos, D= Dakota, W= Westwater
(3) -- = Well details unknown.
(4) - = Wells with no water level measurements are not accessible.
(a) Most wells were surveyed in 2023 except those indicated with a (b)
(b) Well was not included in the 2023 survey, survey date unknown

**Table 1-3 Alluvial and Menefee Monitoring and Recovery Wells**

| Well No. | Well Coordinates (New Mexico State Plane West NAD 83) | | Year Installed | Casing Diameter (Inches) | Casing Material | TOC Elevation (ft amsl) | Depth to Top of Screen (ft. bgs) | Screen Length (feet) | Closure Disposition |
|---|---|---|---|---|---|---|---|---|---|
| | Northing | Easting | | | | | | | |
| MW-1 | 1580484 | 2781541 | 1979 | 3 | STEEL | 7275.3 | 33.5 | 5 | PL |
| MW-1C | 1578341 | 2783120 | 2020 | 3 | PVC | 7395.5 | 84.0 | 10 | PL |
| MW-1J | 1579034 | 2782712 | 2020 | 3 | PVC | 7347.4 | 49.4 | 10 | PL |
| MW-1M | 1579255 | 2782392 | 2020 | 3 | PVC | 7339.0 | 38.0 | 10 | RET |
| MW-2 | 1580191 | 2781538 | 1979 | 3 | STEEL | 7278.3 | 30.1 | 6 | PL |
| MW-2F | 1578553 | 2782577 | 2020 | 3 | PVC | 7348.0 | 42.0 | 20 | PL |
| MW-3 | 1580976 | 2781545 | 1979 | 3 | STEEL | 7273.0 | 33.6 | 5 | PL |
| MW-3A | 1580976 | 2781546 | 2017 | 2 | PVC | 7272.0 | 39.0 | 10 | PL |
| MW-4 | 1578580 | 2781050 | 2005 | 4 | PVC | 7284.2 | 31.5 | 15 | RET |
| MW-4D | 1578849 | 2782082 | 2020 | 3 | PVC | 7341.4 | 42.0 | 20 | PL |
| MW-4H | 1579335 | 2782029 | 2020 | 3 | PVC | 7322.5 | 51.5 | 10 | PL |
| MW-5 | 1579062 | 2781556 | 2005 | 2 | PVC | 7303.4 | 22.5 | 10 | PL |
| MW-6 | 1578620 | 2782243 | 2011 | 2 | PVC | 7341.5 | 15.0 | 20 | PL |
| MW-11A | 1578585 | 2781928 | 2020 | 3 | PVC | 7355.8 | 75.0 | 10 | RET |
| WL-2 | 1578575 | 2782115 | 2017 | 6 | PVC | 7341.4 | 39.0 | 10 | PL |
| WL-3 | 1578651 | 2782133 | 2017 | 6 | PVC | 7341.1 | 39.0 | 10 | PL |
| WL-4 | 1578537 | 2782171 | 2017 | 6 | PVC | 7342.2 | 39.0 | 10 | PL |
| WL-5 | 1578614 | 2782309 | 2017 | 6 | PVC | 7346.3 | 40.0 | 10 | PL |
| WP-4 | 1578330 | 2781527 | 1982 | 4 | PVC | 7312.7 | 38.0 | 10 | PL |
| WP-5 | 1578786 | 2781546 | 1982 | 4 | PVC | 7303.1 | 30.0 | 10 | RET |

Notes:

PL = Plug wells after utility for abatement is complete

RET = Retain for post-closure monitoring; plug wells after post-closure monitoring requirements are met

ft amsl = feet above mean sea level

ft bgs = feel below ground surface

SIP wells have been installed but are in the process of being developed, tested, or sampled. After completion of these activities, RGR will evaluate suitability for monitoring

## Table 2-1 Water Quality Test Results for Mine Pool in Manway Shaft (14ft) and Production Shaft (24ft)

| Sample ID | Date | As mg/L | Ba mg/L | Cl mg/L | F mg/L | Fe mg/L | Mo mg/L | pH | Ra-226 pCi/L | Se mg/L | $SO_4$ mg/L | TDS mg/L | U mg/L | Zn mg/L |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **20.6.2.3103 NMAC (1)** | | **0.01** | **2** | **250** | **1.6** | **1** | **1** | **6-9** | **5** | **0.05** | **600** | **1000** | **0.03** | **10** |
| **MANWAY AND PRODUCTION SHAFT WATER QUALITY RESULTS** | | | | | | | | | | | | | | |
| 14FT-SEEP-12 FTBGS | 6/2/2021 | -0.001 | 0.029 | 39 | -0.5 | -0.02 | -0.02 | 8.65 | -- | -0.001 | 510 | 1130 | -0.0005 | 0.011 |
| 14FT-PLSS-855FTBGS | 10/1/2019 | 0.0012 | 0.22 | 3.2 | 1.2 | -0.02 | 0.093 | 8.56 | 8.36 | -0.001 | 25 | 353 | 0.021 | 0.018 |
| 14FT-MSH/DC-1635FTBGS | 10/1/2019 | 0.0021 | 0.22 | 4.3 | 1.1 | 0.036 | 0.15 | 8.51 | 8.99 | -0.001 | 38 | 343 | 0.036 | 0.019 |
| 14FT-THSS-2635FTBGS | 10/1/2019 | 0.002 | 0.23 | 4.3 | 1.1 | 0.038 | 0.16 | 8.5 | 15.4 | -0.001 | 38 | 347 | 0.036 | 0.026 |
| 14FT-WWSS-3110FTBGS | 10/1/2019 | 0.0021 | 0.22 | 4.2 | 1 | 0.032 | 0.16 | 8.48 | 17.1 | -0.001 | 37 | 344 | 0.036 | 0.021 |
| 24FT-PLSS-855FTBGS | 10/1/2019 | 0.0012 | 0.26 | 3 | 0.91 | 0.024 | 0.094 | 8.48 | 8.19 | -0.001 | 24 | 306 | 0.021 | 0.025 |
| 24FT-MSH/DC-1635FTBGS | 10/1/2019 | 0.0022 | 0.22 | 4.4 | 1.1 | 0.037 | 0.16 | 8.48 | 12.2 | -0.001 | 38 | 344 | 0.037 | 0.029 |
| 24FT-THSS-2635FTBGS | 10/1/2019 | 0.0022 | 0.21 | 4.4 | 1.1 | 0.041 | 0.17 | 8.5 | 14.1 | -0.001 | 39 | 349 | 0.037 | 0.024 |
| 24FT-WWSS-3110FTBGS | 10/1/2019 | 0.0014 | 0.25 | 3.2 | 0.97 | 0.027 | 0.1 | 8.47 | 13.4 | -0.001 | 26 | 308 | 0.023 | 0.018 |
| 24-FT SHAFT | 9/28/2007 | -- | -- | 4 | -- | 0.05 | 0.2 | 8.38 | 16.8 | -0.001 | 44 | -- | 0.071 | -0.01 |

(1) Water quality standards for human health, domestic water supply, and irrigation use as listed in 20.6.2.3103 NMAC

Notes:

Yellow highlighted values indicate that the water quality result exceeds the standards of 20.6.2.3103 NMAC.

-0.001 - A negative sign in front of result indicates that the analyte was not detected above the Practical Quantitation Limit (PQL).

ND = Not Detected above the minimum activity count

-- = No analytical results available for the analyte

PLSS= Point Lookout Sandstone MSH/DC = Mancos Shale/Dilco Coal THSS = Tres Hermanos Sandstone WWSS – Westwater Sandstone

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells**

| Dewatering Wells Water Quality Data Summary | | Well ID | DW1 | DW1 | DW1 | DW1 | DW1 |
|---|---|---|---|---|---|---|---|
| | | Depth (fbtoc) | 785 | 785 | 785 | 785 | 785 |
| | | Sample Type | Sample | Sample | Sample | Sample | Sample |
| | | Date Collected | 4/21/2026 | 3/10/2026 | 12/09/2025 | 9/9/2025 | 10/03/2023 |
| **Analyte** | **Units** | **New Mexico WQCC-3103** | | | | | |
| **Arsenic** | **mg/L** | **0.01** | <0.0040 | <0.004 | <0.010 | <0.0025 | -- |
| **Barium** | **mg/L** | **2** | **0.35** | **0.38** | **0.34** | **0.34** | -- |
| **Beryllium** | **mg/L** | **0.004** | <0.0040 | <0.004 | <0.004 | <0.0020 | -- |
| **Boron** | **mg/L** | **0.75** | **0.065** | **0.072** | **0.064** | **0.068** | -- |
| **Calcium** | **mg/L** | | **5.0** | **5.3** | **5.1** | **4.9** | -- |
| **Chloride** | **mg/L** | **250** | **0.62** | **0.64** | **0.62** | **0.71** | -- |
| **Fluoride** | **mg/L** | **1.6** | **0.55** | **0.52** | **0.48** | **0.50** | -- |
| **Iron** | **mg/L** | **1** | <0.20 | **0.14** | <0.2 | **0.078** | -- |
| **Lead** | **mg/L** | **0.015** | <0.0020 | <0.0020 | -- | <0.0025 | -- |
| **Magnesium** | **mg/L** | | **1.6** | **1.8** | **1.7** | **1.6** | -- |
| **Manganese** | **mg/L** | **0.2** | <0.020 | <0.02 | <0.02 | **0.0074** | -- |
| **Mercury** | **mg/L** | **0.002** | <0.00020 | <0.0002 | <0.0002 | <0.00020 | -- |
| **Molybdenum** | **mg/L** | **1** | <0.010 | <0.01 | <0.01 | <0.0080 | -- |
| **Nitrate Nitrite as N** | **mg/L** | | <0.10 | <0.5 | <0.5 | <1.0 | -- |
| **Nitrite as N** | **mg/L** | **1** | <0.10 | <0.5 | <0.5 | <1.0 | -- |
| **Nitrate as N** | **mg/L** | **10** | <0.10 | <0.5 | <0.5 | <1.0 | -- |
| **Nitrogen, Ammonia** | **mg/L** | | <0.67 | <0.67 | <0.67 | <0.67 | -- |
| **Nitrogen, Total Kjeldahl** | **mg/L** | | <0.50 | <0.5 | <0.5 | <0.50 | -- |
| **Potassium** | **mg/L** | | **1.0** | **1.4** | **1.3** | **1.1** | -- |
| **Radium-226** | **pCi/L** | | **0.210** | **0.172** | **0.199** | **0.074** | -- |
| **Radium-228** | **pCi/L** | | **0.850** | **1.100** | **0.400** | **0.583** | -- |
| **Radium, Total** | **pCi/L** | **5** | **1.06** | **1.272** | 0.599 | **0.657** | -- |
| **Selenium** | **mg/L** | **0.05** | <0.0020 | <0.002 | <0.030 | <0.0050 | -- |
| **Sodium** | **mg/L** | | **66** | **75** | **66** | **72** | -- |
| **Sulfate** | **mg/L** | **600** | **5.5** | **5.5** | **5.3** | **5.4** | -- |
| **Total Dissolved Solids** | **mg/L** | **1000** | **120** | **230** | **160** | **190** | -- |
| **Uranium** | **mg/L** | **0.03** | <0.0010 | <0.001 | -- | <0.0025 | -- |
| **Total Alkalinity as CaCO3** | **mg/L** | | **170** | **170** | **170** | **170** | -- |
| **Bicarbonate Alkalinity as CaCO3** | **mg/L** | | **170** | **170** | **170** | **170** | -- |
| **Carbonate Alkalinity as CaCO3** | **mg/L** | | **4.2** | **6.2** | **2.5** | <2.0 | -- |
| **Benzene** | **mg/L** | **0.005** | <0.001 | <0.001 | <0.001 | <0.001 | <0.00100 |
| **Ethylbenzene** | **mg/L** | **0.7** | <0.001 | <0.001 | <0.001 | <0.001 | <0.00100 |
| **Toluene** | **mg/L** | **1** | <0.001 | <0.001 | <0.001 | <0.001 | <0.00100 |
| **Xylenes, Total** | **mg/L** | **0.62** | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.00300 |
| **Notes** | | | | | Uranium and lead results are unavailable due to a laboratory omission. | Depth was previously reported incorrectly. Sample was taken at 785 fbtoc | |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above reporting detection limit (RDL)

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells Continued**

| Dewatering Wells Water Quality Data Summary | | | Well ID | DW2a | DW2a | DW2a | DW2a | DW2a |
|---|---|---|---|---|---|---|---|---|
| | | | Depth (fbtoc) | Spigot | Spigot | Spigot | Spigot | Spigot |
| | | | Sample Type | Sample | Sample | Sample | Sample | Sample |
| | | | Date Collected | 4/21/2026 | 3/11/2026 | 12/09/2025 | 9/9/2025 | 10/11/2023 |
| **Analyte** | **Units** | **New Mexico WQCC-3103** | | | | | | |
| **Arsenic** | **mg/L** | **0.01** | <0.0040 | <0.004 | <0.010 | <0.0025 | -- |
| **Barium** | **mg/L** | **2** | **0.014** | **0.013** | **0.015** | **0.013** | -- |
| **Beryllium** | **mg/L** | **0.004** | <0.0040 | <0.004 | <0.004 | <0.0020 | -- |
| **Boron** | **mg/L** | **0.75** | **0.60** | **0.55** | **0.61** | **0.58** | -- |
| **Calcium** | **mg/L** | | **4.0** | **4.2** | **5.3** | **4.3** | -- |
| **Chloride** | **mg/L** | **250** | **9.4** | **9.5** | **9.4** | **9.6** | -- |
| **Fluoride** | **mg/L** | **1.6** | **2.7** | **2.6** | **2.5** | **2.6** | -- |
| **Iron** | **mg/L** | **1** | <0.20 | <0.2 | <0.2 | <0.020 | -- |
| **Lead** | **mg/L** | **0.015** | <0.0020 | <0.002 | -- | <0.0025 | -- |
| **Magnesium** | **mg/L** | | **1.6** | **1.7** | **2.2** | **1.8** | -- |
| **Manganese** | **mg/L** | **0.2** | <0.020 | <0.02 | <0.02 | <0.0020 | -- |
| **Mercury** | **mg/L** | **0.002** | <0.00020 | <0.0002 | <0.0002 | <0.00020 | -- |
| **Molybdenum** | **mg/L** | **1** | <0.010 | <0.01 | <0.01 | <0.0080 | -- |
| **Nitrate Nitrite as N** | **mg/L** | | <0.5 | <0.5 | <0.5 | <1.0 | -- |
| **Nitrite as N** | **mg/L** | **1** | <0.10 | <0.1 | <0.5 | <1.0 | -- |
| **Nitrate as N** | **mg/L** | **10** | **0.18** | **0.19** | <0.5 | <1.0 | -- |
| **Nitrogen, Ammonia** | **mg/L** | | <0.67 | <0.67 | <0.67 | <0.67 | -- |
| **Nitrogen, Total Kjeldahl** | **mg/L** | | <0.50 | <0.5 | <0.5 | <0.50 | -- |
| **Potassium** | **mg/L** | | **0.85** | **0.91** | **1.1** | <1.0 | -- |
| **Radium-226** | **pCi/L** | | **0.0641** | **0.216** | <1.00 | <1.00 | -- |
| **Radium-228** | **pCi/L** | | **0.0983** | **0.980** | **0.63** | **0.705** | -- |
| **Radium, Total** | **pCi/L** | **5** | **0.162** | **1.196** | **0.63** | **0.705** | -- |
| **Selenium** | **mg/L** | **0.05** | <0.0020 | <0.002 | <0.030 | <0.0050 | -- |
| **Sodium** | **mg/L** | | **230** | **230** | **230** | **250** | -- |
| **Sulfate** | **mg/L** | **600** | **140** | **140** | **150** | **150** | -- |
| **Total Dissolved Solids** | **mg/L** | **1000** | **620** | **620** | **540** | **620** | -- |
| **Uranium** | **mg/L** | **0.03** | <0.0010 | <0.001 | -- | <0.0025 | -- |
| **Total Alkalinity as CaCO3** | **mg/L** | | **380** | **380** | **360** | **380** | -- |
| **Bicarbonate Alkalinity as CaCO3** | **mg/L** | | **340** | **340** | **330** | **340** | -- |
| **Carbonate Alkalinity as CaCO3** | **mg/L** | | **46** | **40** | **38** | **36** | -- |
| **Benzene** | **mg/L** | **0.005** | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Ethylbenzene** | **mg/L** | **0.7** | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Toluene** | **mg/L** | **1** | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Xylenes, Total** | **mg/L** | **0.62** | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.003 |
| **Notes** | | | | | Uranium and lead results are unavailable due to a laboratory omission. | | |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above RDL

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample from DW-2a was collected from spigot near well head.

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells Continued**

| Dewatering Wells Water Quality Data Summary | | Well ID | DW3 | DW3 | DW3 | DW3 | DW3 | DW3 | DW3 | DW3 |
|---|---|---|---|---|---|---|---|---|---|---|
| | | Depth (fbtoc) | 821 | 896 | 1005 | Water Interface, 607 | 821 | 896 | 1005 | Water Interface, 608 |
| | | Sample Type | Sample | Sample | Sample | Sample | Sample | Sample | Sample | Sample |
| | | Date Collected | 4/23/2026 | 4/23/2026 | 4/23/2026 | 3/11/2026 | 3/11/2026 | 3/11/2026 | 3/12/2026 | 12/09/2025 |
| Analyte | Units | New Mexico WQCC-3103 | | | | | | | | |
| Arsenic | mg/L | 0.01 | <0.0040 | <0.0040 | <0.0040 | <0.004 | <0.004 | <0.004 | <0.004 | <0.010 |
| Barium | mg/L | 2 | **0.45** | **0.47** | **0.46** | **0.39** | **0.40** | **0.40** | **0.45** | **0.43** |
| Beryllium | mg/L | 0.004 | <0.0040 | <0.0040 | <0.0040 | <0.004 | <0.004 | <0.004 | <0.004 | <0.004 |
| Boron | mg/L | 0.75 | **0.066** | **0.073** | **0.070** | **0.068** | **0.069** | **0.071** | **0.073** | **0.072** |
| Calcium | mg/L | | **5.4** | **6.1** | **5.6** | **5.1** | **5.3** | **5.4** | **5.7** | **5.7** |
| Chloride | mg/L | 250 | **0.64** | **0.64** | **0.71** | **0.72** | **0.60** | **0.63** | **0.62** | **1.2** |
| Fluoride | mg/L | 1.6 | **0.50** | **0.49** | **0.52** | **0.48** | **0.50** | **0.48** | **0.49** | **0.45** |
| Iron | mg/L | 1 | <0.20 | **0.21** | <0.20 | **0.69** | <0.2 | <0.2 | <0.2 | **0.76** |
| Lead | mg/L | 0.015 | <0.0020 | <0.0020 | <0.0020 | <0.002 | <0.002 | <0.002 | <0.002 | -- |
| Magnesium | mg/L | | **1.7** | **2.0** | **1.8** | **1.7** | **1.7** | **1.7** | **1.7** | **1.9** |
| Manganese | mg/L | 0.2 | <0.020 | <0.020 | <0.020 | <0.02 | <0.02 | <0.02 | <0.02 | **0.024** |
| Mercury | mg/L | 0.002 | <0.00020 | <0.00020 | <0.00020 | <0.00020 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| Molybdenum | mg/L | 1 | <0.010 | <0.010 | <0.010 | <0.01 | <0.01 | <0.01 | <0.01 | <0.01 |
| Nitrate Nitrite as N | mg/L | | <0.10 | <0.10 | <0.50 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Nitrite as N | mg/L | 1 | <0.10 | <0.10 | <0.50 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Nitrate as N | mg/L | 10 | <0.10 | <0.10 | <0.50 | <0.1 | <0.1 | <0.1 | <0.1 | <0.1 |
| Nitrogen, Ammonia | mg/L | | <0.67 | <0.67 | <0.67 | <0.67 | <0.67 | <0.67 | <0.67 | <0.67 |
| Nitrogen, Total Kjeldahl | mg/L | | <0.50 | <0.50 | <0.50 | <0.50 | <0.5 | <0.5 | <0.67 | <0.5 |
| Potassium | mg/L | | **1.2** | **1.3** | **1.3** | **1.3** | **1.1** | **1.2** | **1.2** | **1.3** |
| Radium-226 | pCi/L | | **0.161** | **0.367** | **0.352** | **0.805** | **0.277** | **0.318** | **0.45** | **0.478** |
| Radium-228 | pCi/L | | **0.717** | **0.247** | **0.659** | **0.975** | **1.620** | **1.160** | **0.768** | **1.04** |
| Radium, Total | pCi/L | 5 | **0.878** | **0.614** | 1.011 | **1.78** | **1.897** | **1.478** | **1.218** | **1.518** |
| Selenium | mg/L | 0.05 | <0.0020 | <0.0020 | <0.0020 | <0.002 | <0.002 | <0.002 | <0.002 | <0.030 |
| Sodium | mg/L | | **74** | **78** | **75** | **73** | **67** | **69** | **73** | **73** |
| Sulfate | mg/L | 600 | **4.0** | **3.9** | **2.5** | <0.5 | **4.0** | **3.8** | **2.4** | <0.5 |
| Total Dissolved Solids | mg/L | 1000 | **170** | **200** | **160** | **190** | **180** | **180** | **200** | **190** |
| Uranium | mg/L | 0.03 | <0.0010 | <0.0010 | <0.0010 | <0.0025 | <0.001 | <0.001 | <0.001 | -- |
| Total Alkalinity as CaCO3 | mg/L | | **180** | **180** | **180** | **180** | **180** | **180** | **180** | **180** |
| Bicarbonate Alkalinity as CaCO3 | mg/L | | **180** | **170** | **180** | **180** | **170** | **170** | **180** | **180** |
| Carbonate Alkalinity as CaCO3 | mg/L | | **7.5** | **7.5** | **7.8** | **3.3** | **5.2** | **5.4** | **7.5** | <2 |
| Notes | | | | | | Depth reported as water level, sample taken 15 feet below | | | | Samples for WI were taken 15 feet below. |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above RDL

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: The sample for 12/09/2025 did not have uranium tested due to laboratory omission

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells Continued**

| Dewatering Wells Water Quality Data Summary | | Well ID | DW3 | DW3 | DW3 | DW3 | DW3 | DW3 | DW3 |
|---|---|---|---|---|---|---|---|---|---|
| | | Depth (fbtoc) | 821 | 896 | 1005 | Water Interface, 595 | 821 | 896 | 1005 |
| | | Sample Type | Sample | Sample | Sample | Sample | Sample | Sample | Sample |
| | | Date Collected | 12/10/2025 | 12/10/2025 | 12/10/2025 | 9/10/2025 | 9/10/2025 | 9/10/2025 | 9/10/2025 |
| Analyte | Units | New Mexico WQCC-3103 | | | | | | | |
| Arsenic | mg/L | 0.01 | <0.004 | <0.004 | <0.004 | <0.0025 | <0.0025 | <0.0025 | <0.0025 |
| Barium | mg/L | 2 | 0.42 | 0.42 | 0.44 | 0.43 | 0.41 | 0.40 | 0.41 |
| Beryllium | mg/L | 0.004 | <0.004 | <0.004 | <0.004 | <0.0020 | <0.0020 | <0.0020 | <0.0020 |
| Boron | mg/L | 0.75 | 0.069 | 0.073 | 0.075 | 0.075 | 0.074 | 0.074 | 0.077 |
| Calcium | mg/L | | 5.5 | 5.7 | 5.9 | 5.5 | 5.2 | 5.2 | 5.3 |
| Chloride | mg/L | 250 | 0.62 | 0.6 | 0.61 | 2.6 | 0.88 | 0.85 | 0.62 |
| Fluoride | mg/L | 1.6 | 0.46 | 0.51 | 0.51 | 0.46 | 0.47 | 0.46 | 0.48 |
| Iron | mg/L | 1 | 0.18 | 0.16 | 0.14 | 0.89 | 0.17 | 0.12 | 0.043 |
| Lead | mg/L | 0.015 | -- | -- | -- | <0.0025 | <0.0025 | <0.0025 | <0.0025 |
| Magnesium | mg/L | | 1.7 | 1.8 | 1.8 | 2.1 | 1.7 | 1.7 | 1.6 |
| Manganese | mg/L | 0.2 | <0.02 | <0.02 | <0.02 | 0.024 | 0.0070 | 0.0051 | 0.0092 |
| Mercury | mg/L | 0.002 | <0.0002 | <0.0002 | <0.0002 | <0.00020 | <0.00020 | <0.00020 | <0.00020 |
| Molybdenum | mg/L | 1 | <0.01 | 0.013 | <0.01 | <0.0080 | <0.0080 | <0.0080 | <0.0080 |
| Nitrate Nitrite as N | mg/L | | <0.1 | <0.1 | <0.1 | <1.0 | <1.0 | <1.0 | <1.0 |
| Nitrite as N | mg/L | 1 | <0.1 | <0.1 | <0.1 | <1.0 | <1.0 | <1.0 | <1.0 |
| Nitrate as N | mg/L | 10 | <0.1 | <0.1 | <0.1 | <1.0 | <1.0 | <1.0 | <1.0 |
| Nitrogen, Ammonia | mg/L | | <0.5 | <0.67 | <0.5 | <0.67 | <0.67 | <0.67 | <0.67 |
| Nitrogen, Total Kjeldahl | mg/L | | <0.5 | <0.5 | <0.5 | <0.50 | <0.50 | <0.50 | <0.50 |
| Potassium | mg/L | | 1.2 | 1.2 | 1.2 | 1.4 | 1.1 | 1.1 | 1.1 |
| Radium-226 | pCi/L | | 0.0129 | 0.317 | 0.404 | 0.790 | 0.330 | 0.361 | 0.578 |
| Radium-228 | pCi/L | | 0.416 | 0.81 | 0.847 | 0.857 | 1.85 | 0.987 | 1.06 |
| Radium, Total | pCi/L | 5 | 0.4289 | 1.127 | 1.251 | 1.647 | 2.18 | 1.348 | 1.638 |
| Selenium | mg/L | 0.05 | <0.002 | <0.002 | <0.002 | <0.0050 | <0.0050 | <0.0050 | <0.0050 |
| Sodium | mg/L | | 71 | 72 | 74 | 75 | 70 | 72 | 71 |
| Sulfate | mg/L | 600 | 3.9 | 3.7 | 2.2 | 0.52 | 4.1 | 3.8 | 2.4 |
| Total Dissolved Solids | mg/L | 1000 | 200 | 200 | 210 | 190 | 190 | 190 | 200 |
| Uranium | mg/L | 0.03 | <0.001 | <0.001 | <0.001 | <0.0025 | <0.0025 | <0.0025 | <0.0025 |
| Total Alkalinity as CaCO3 | mg/L | | 180 | 180 | 180 | 180 | 180 | 180 | 180 |
| Bicarbonate Alkalinity as CaCO3 | mg/L | | 180 | 180 | 170 | 180 | 180 | 170 | 180 |
| Carbonate Alkalinity as CaCO3 | mg/L | | 4.4 | 5 | 7.3 | <2.0 | 3.8 | 3.3 | 7.1 |
| Notes | | | | | | Depth reported as water level, sample taken 15 feet below | | | |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above RDL

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: The sample for 12/09/2025 did not have uranium tested due to laboratory omission

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells Continued**

| Dewatering Wells Water Quality Data Summary | | Well ID | DW3 | DW3 | DW3 | DW3 | DW3 | DW3 | DW3 |
|---|---|---|---|---|---|---|---|---|---|
| | | Depth (fbtoc) | 821 | 896 | 1005 | Water Interface, 607 | 821 | 896 | 1005 |
| | | Sample Type | Sample | Sample | Sample | Sample | Sample | Sample | Sample |
| | | Date Collected | 4/23/2026 | 4/23/2026 | 4/23/2026 | 3/11/2026 | 3/11/2026 | 3/11/2026 | 3/12/2026 |
| **Analyte** | **Units** | **New Mexico WQCC-3103** | | | | | | | |
| **TPH, EPA Method 8015D** | | | | | | | | | |
| **Diesel Range Organics [C10-C28]** | **mg/L** | | <1 | <1 | <1 | <1 | **5.7** | **9.5** | <1 |
| **Gasoline Range Organics [C6 - C10]** | **mg/L** | | <0.05 | <0.05 | <0.05 | <0.050 | <0.05 | **0.065** | <0.05 |
| **Motor Oil Range Organics [C28-C40]** | **mg/L** | | <5 | <5 | <5 | <5.0 | <5 | <5 | <5 |
| **VOC, EPA Method 8260B** | | | | | | | | | |
| **Benzene** | **mg/L** | **0.005** | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Ethylbenzene** | **mg/L** | **0.7** | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Toluene** | **mg/L** | **1** | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Xylenes, Total** | **mg/L** | **0.62** | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.0015 |
| **PAH, EPA Method 8270-SIM** | | | | | | | | | |
| **1-Methylnaphthalene** | **mg/L** | **0.03** | <0.0002 | **0.00074** | **0.00035** | **0.0048** | **0.0030** | **0.0081** | **0.0014** |
| **2-Methylnaphthalene** | **mg/L** | **0.03** | <0.0002 | **0.00068** | **0.00033** | **0.0045** | **0.0031** | **0.0072** | **0.0011** |
| **Acenaphthene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Acenaphthylene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | **0.00023** | <0.0002 |
| **Anthracene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Benzo[a]anthracene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Benzo[a]pyrene** | **mg/L** | **0.0002** | <0.00007 | <0.00007 | <0.00007 | <0.00007 | <0.00007 | <0.00007 | <0.00007 |
| **Benzo[g,h,i]perylene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Benzo[b]fluoranthene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Chrysene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Dibenz(a,h)anthracene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Fluoranthene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Fluorene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | **0.00075** | **0.00095** | **0.0018** | **0.00032** |
| **Indeno[1,2,3-cd]pyrene** | **mg/L** | | <0.0002 | **0.00026** | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Naphthalene** | **mg/L** | **0.03** | <0.0002 | <0.0002 | <0.0002 | **0.00053** | <0.0002 | **0.0004** | <0.0002 |
| **Phenanthrene** | **mg/L** | | **0.00077** | **0.00055** | **0.00032** | **0.00084** | **0.0012** | **0.0021** | **0.00056** |
| **Pyrene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Notes** | | | | | | Depth reported as water level, sample taken 15 feet below | | | |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above RDL

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells Continued**

| Dewatering Wells Water Quality Data Summary | | Well ID | DW3 | DW3 | DW3 | DW3 | DW3 | DW3 | DW3 |
|---|---|---|---|---|---|---|---|---|---|
| | | Depth (fbtoc) | Water Interface, 608 | 821 | 896 | 1005 | Water Interface, 595 | 821 | 896 |
| | | Sample Type | Sample | Sample | Sample | Sample | Sample | Sample | Sample |
| | | Date Collected | 12/09/2025 | 12/10/2025 | 12/10/2025 | 12/10/2025 | 9/10/2025 | 9/10/2025 | 9/10/2025 |
| **Analyte** | **Units** | **New Mexico WQCC-3103** | | | | | | | |
| **TPH, EPA Method 8015D** | | | | | | | | | |
| **Diesel Range Organics [C10-C28]** | **mg/L** | | **1.4** | <1 | <1 | <1 | | | |
| **Gasoline Range Organics [C6 - C10]** | **mg/L** | | <0.050 | <0.05 | <0.05 | <0.05 | | | |
| **Motor Oil Range Organics [C28-C40]** | **mg/L** | | <5.0 | <5 | <5 | <5 | | | |
| **VOC, EPA Method 8260B** | | | | | | | | | |
| **Benzene** | **mg/L** | **0.005** | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Ethylbenzene** | **mg/L** | **0.7** | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Toluene** | **mg/L** | **1** | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Xylenes, Total** | **mg/L** | **0.62** | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.002 |
| **PAH, EPA Method 8270-SIM** | | | | | | | | | |
| **1-Methylnaphthalene** | **mg/L** | **0.03** | **0.0056** | <0.0002 | <0.0002 | 0.00039 | | | |
| **2-Methylnaphthalene** | **mg/L** | **0.03** | **0.0052** | <0.0002 | **0.00024** | 0.00034 | | | |
| **Acenaphthene** | **mg/L** | | **0.00093** | <0.0002 | <0.0002 | <0.0002 | | | |
| **Acenaphthylene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | | | |
| **Anthracene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | | | |
| **Benzo[a]anthracene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | | | |
| **Benzo[a]pyrene** | **mg/L** | **0.0002** | <0.00007 | <0.00007 | <0.00007 | <0.00007 | | | |
| **Benzo[g,h,i]perylene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | | | |
| **Benzo[b]fluoranthene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | | | |
| **Chrysene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | | | |
| **Dibenz(a,h)anthracene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | | | |
| **Fluoranthene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | | | |
| **Fluorene** | **mg/L** | | **0.00099** | <0.0002 | <0.0002 | <0.0002 | | | |
| **Indeno[1,2,3-cd]pyrene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | | | |
| **Naphthalene** | **mg/L** | **0.03** | **0.00054** | <0.0002 | <0.0002 | <0.0002 | | | |
| **Phenanthrene** | **mg/L** | | **0.00098** | <0.0002 | <0.0002 | <0.0002 | | | |
| **Pyrene** | **mg/L** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | | | |
| **Notes** | | | Depth reported as water level, sample taken 15 feet below | | | | Depth reported as water level, sample taken 15 feet below | | |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above RDL

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells Continued**

| Dewatering Wells Water Quality Data Summary | | Well ID | DW3 | DW3 | DW3 | DW3 |
|---|---|---|---|---|---|---|
| | | Depth (fbtoc) | 1005 | 596 | 896 | 1005 |
| | | Sample Type | Sample | Sample | Sample | Sample |
| | | Date Collected | 9/10/2025 | 10/11/2023 | 10/11/2023 | 10/11/2023 |
| **Analyte** | **Units** | **New Mexico WQCC-3103** | | | | |
| **TPH, EPA Method 8015D** | | | | | | |
| **Diesel Range Organics [C10-C28]** | **mg/L** | | | **1.37** | **0.62** | **2.3** |
| **Gasoline Range Organics [C6 - C10]** | **mg/L** | | | | | |
| **Motor Oil Range Organics [C28-C40]** | **mg/L** | | | **0.147** | **0.158** | **0.347** |
| **VOC, EPA Method 8260B** | | | | | | |
| **Benzene** | **mg/L** | **0.005** | <0.001 | <0.001 | <0.001 | <0.001 |
| **Ethylbenzene** | **mg/L** | **0.7** | <0.001 | <0.001 | <0.001 | <0.001 |
| **Toluene** | **mg/L** | **1** | <0.001 | <0.001 | <0.001 | <0.001 |
| **Xylenes, Total** | **mg/L** | **0.62** | <0.002 | <0.003 | <0.003 | <0.003 |
| **PAH, EPA Method 8270-SIM** | | | | | | |
| **1-Methylnaphthalene** | **mg/L** | **0.03** | | **0.0105** | <0.00025 | **0.000599** |
| **2-Methylnaphthalene** | **mg/L** | **0.03** | | **0.0118** | <0.00025 | **0.000701** |
| **Acenaphthene** | **mg/L** | | | **0.000477** | <0.00005 | **0.000104** |
| **Acenaphthylene** | **mg/L** | | | <0.00005 | <0.00005 | <0.00005 |
| **Anthracene** | **mg/L** | | | <0.00005 | <0.00005 | <0.00005 |
| **Benzo[a]anthracene** | **mg/L** | | | <0.00005 | <0.00005 | <0.00005 |
| **Benzo[a]pyrene** | **mg/L** | **0.0002** | | <0.00005 | <0.00005 | <0.00005 |
| **Benzo[g,h,i]perylene** | **mg/L** | | | <0.00005 | <0.00005 | <0.00005 |
| **Benzo[b]fluoranthene** | **mg/L** | | | <0.00005 | <0.00005 | <0.00005 |
| **Chrysene** | **mg/L** | | | <0.00005 | <0.00005 | <0.00005 |
| **Dibenz(a,h)anthracene** | **mg/L** | | | <0.00005 | <0.00005 | <0.00005 |
| **Fluoranthene** | **mg/L** | | | <0.0001 | <0.0001 | <0.0001 |
| **Fluorene** | **mg/L** | | | **0.00161** | **0.0000566** | **0.000183** |
| **Indeno[1,2,3-cd]pyrene** | **mg/L** | | | <0.00005 | <0.00005 | <0.00005 |
| **Naphthalene** | **mg/L** | **0.03** | | **0.00134** | <0.00025 | <0.00025 |
| **Phenanthrene** | **mg/L** | | | **0.00181** | **0.0000815** | **0.000245** |
| **Pyrene** | **mg/L** | | | <0.00005 | <0.00005 | <0.00005 |
| **Notes** | | | | Depth reported as water level, sample taken 15 feet below | | |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above RDL

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells Continued**

| Dewatering Wells Water Quality Data Summary | | | Well ID | DW6 | DW6 | DW6 | DW6 | DW6 |
|---|---|---|---|---|---|---|---|---|
| | | | Depth (fbtoc) | Spigot | Spigot | Spigot | Spigot | Spigot |
| | | | Sample Type | Sample | Sample | Sample | Sample | Sample |
| | | | Date Collected | 4/23/2026 | 3/10/2026 | 12/10/2025 | 9/10/2025 | 10/10/2023 |
| Analyte | Units | New Mexico WQCC-3103 | | | | | | |
| Arsenic | mg/L | 0.01 | <0.0040 | <0.004 | <0.004 | <0.0025 | -- |
| Barium | mg/L | 2 | 0.44 | 0.40 | 0.5 | 0.38 | -- |
| Beryllium | mg/L | 0.004 | <0.0040 | <0.004 | <0.004 | <0.0020 | -- |
| Boron | mg/L | 0.75 | 0.055 | <0.05 | 0.053 | 0.059 | -- |
| Calcium | mg/L | | 5.5 | 4.9 | 5.9 | 5.0 | -- |
| Chloride | mg/L | 250 | 0.89 | 0.87 | 0.86 | 0.86 | -- |
| Fluoride | mg/L | 1.6 | 0.52 | 0.65 | 0.5 | 0.49 | -- |
| Iron | mg/L | 1 | <0.20 | 0.035 | 0.13 | 0.21 | -- |
| Lead | mg/L | 0.015 | <0.0020 | <0.0020 | -- | <0.0025 | -- |
| Magnesium | mg/L | | 1.8 | 1.6 | 1.9 | 1.7 | -- |
| Manganese | mg/L | 0.2 | <0.020 | <0.02 | <0.02 | 0.010 | -- |
| Mercury | mg/L | 0.002 | <0.00020 | <0.0002 | <0.0002 | <0.00020 | -- |
| Molybdenum | mg/L | 1 | <0.010 | <0.01 | <0.01 | <0.0080 | -- |
| Nitrate Nitrite as N | mg/L | | <0.10 | <0.5 | <1.0 | <1.0 | -- |
| Nitrite as N | mg/L | 1 | <0.10 | <0.5 | <1.0 | <1.0 | -- |
| Nitrate as N | mg/L | 10 | <0.10 | <0.5 | <1.0 | <1.0 | -- |
| Nitrogen, Ammonia | mg/L | | <0.67 | <0.67 | <0.67 | <0.67 | -- |
| Nitrogen, Total Kjeldahl | mg/L | | <0.50 | <0.5 | <0.5 | <0.50 | -- |
| Potassium | mg/L | | 1.2 | 1.3 | 1.3 | 1.1 | -- |
| Radium-226 | pCi/L | | 0.347 | 0.176 | 0.418 | 0.323 | -- |
| Radium-228 | pCi/L | | 1.04 | 0.854 | 0.98 | 0.566 | -- |
| Radium, Total | pCi/L | 5 | 1.387 | 1.03 | 1.398 | 0.889 | -- |
| Selenium | mg/L | 0.05 | <0.0020 | <0.002 | <0.002 | <0.0050 | -- |
| Sodium | mg/L | | 66 | 64 | 64 | 68 | -- |
| Sulfate | mg/L | 600 | 6.9 | 6.9 | 6.6 | 7.0 | -- |
| Total Dissolved Solids | mg/L | 1000 | 190 | 130 | 170 | 170 | -- |
| Uranium | mg/L | 0.03 | <0.0010 | <0.001 | <0.001 | <0.0025 | -- |
| Total Alkalinity as CaCO3 | mg/L | | 160 | 160 | 160 | 160 | -- |
| Bicarbonate Alkalinity as CaCO3 | mg/L | | 160 | 150 | 160 | 160 | -- |
| Carbonate Alkalinity as CaCO3 | mg/L | | 6.8 | 9.1 | 7.2 | 4.2 | -- |
| Benzene | mg/L | 0.005 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| Ethylbenzene | mg/L | 0.7 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| Toluene | mg/L | 1 | <0.001 | <0.001 | <0.001 | 0.0013 | <0.001 |
| Xylenes, Total | mg/L | 0.62 | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.003 |
| Notes | | | | | Lead result unavailable due to a laboratory omission. | | |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above RDL

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample for DW-6 was collected from spigot near well head

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells Continued**

| Dewatering Wells Water Quality Data Summary | | | Well ID | DW8[2] | DW8[2] | DW8[2] | DW8 | DW8 | DW8 | DW8 |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | Depth (fbtoc) | 830 | 830 | 830 | 830 | 961 | 840 | 961 |
| | | | Sample Type | Sample | Sample | Sample | Sample | Sample | Sample | Sample |
| | | | Date Collected | 4/21/2026 | 3/10/2026 | 12/09/2025 | 9/9/2025 | 9/9/2025 | 10/09/2023 | 10/09/2023 |
| Analyte | Units | New Mexico WQCC-3103 | | | | | | | | |
| Arsenic | mg/L | 0.01 | <0.0040 | <0.004 | <0.010 | <0.0025 | <0.0025 | -- | -- |
| Barium | mg/L | 2 | 0.40 | 0.39 | 0.33 | 0.36 | 0.33 | -- | -- |
| Beryllium | mg/L | 0.004 | <0.0040 | <0.004 | <0.004 | <0.0020 | <0.0020 | -- | -- |
| Boron | mg/L | 0.75 | 0.073 | 0.072 | 0.081 | 0.068 | 0.09 | -- | -- |
| Calcium | mg/L | | 5.3 | 5.3 | 5.5 | 4.6 | 5.5 | -- | -- |
| Chloride | mg/L | 250 | 0.80 | 0.78 | 0.73 | 0.8 | 2.4 | -- | -- |
| Fluoride | mg/L | 1.6 | 0.57 | 0.53 | 0.7 | 0.54 | 0.66 | -- | -- |
| Iron | mg/L | 1 | <0.20 | <0.2 | <0.2 | 0.021 | 0.031 | -- | -- |
| Lead | mg/L | 0.015 | <0.0020 | <0.0020 | -- | <0.0025 | <0.0025 | -- | -- |
| Magnesium | mg/L | | 1.8 | 1.8 | 1.7 | 1.6 | 2.1 | -- | -- |
| Manganese | mg/L | 0.2 | <0.020 | <0.02 | <0.02 | 0.0049 | 0.0066 | -- | -- |
| Mercury | mg/L | 0.002 | <0.00020 | <0.0002 | <0.0002 | <0.00020 | <0.00020 | -- | -- |
| Molybdenum | mg/L | 1 | <0.010 | <0.01 | <0.01 | <0.0080 | <0.0080 | -- | -- |
| Nitrate Nitrite as N | mg/L | | <0.10 | <0.5 | <0.5 | <1.0 | <1.0 | -- | -- |
| Nitrite as N | mg/L | 1 | <0.10 | <0.5 | <0.5 | <1.0 | <1.0 | -- | -- |
| Nitrate as N | mg/L | 10 | <0.10 | <0.5 | <0.5 | <1.0 | <1.0 | -- | -- |
| Nitrogen, Ammonia | mg/L | | <0.67 | <0.67 | <0.67 | <0.67 | <0.67 | -- | -- |
| Nitrogen, Total Kjeldahl | mg/L | | <0.50 | <0.5 | <0.5 | <0.50 | <0.50 | -- | -- |
| Potassium | mg/L | | 1.1 | 1.3 | 1.2 | 1.1 | 1.2 | -- | -- |
| Radium-226 | pCi/L | | 0.206 | 0.329 | 0.28 | 0.296 | 0.148 | -- | -- |
| Radium-228 | pCi/L | | 0.517 | 0.022 | 0.965 | 0.581 | 0.515 | -- | -- |
| Radium, Total | pCi/L | 5 | 0.723 | 0.351 | 1.245 | 0.877 | 0.663 | -- | -- |
| Selenium | mg/L | 0.05 | <0.0020 | <0.002 | <0.030 | <0.0050 | <0.0050 | -- | -- |
| Sodium | mg/L | | 70 | 73 | 67 | 70 | 73 | -- | -- |
| Sulfate | mg/L | 600 | 5.6 | 5.5 | 6.4 | 5.2 | 6.8 | -- | -- |
| Total Dissolved Solids | mg/L | 1000 | 190 | 100 | 190 | 190 | 210 | -- | -- |
| Uranium | mg/L | 0.03 | <0.0010 | <0.001 | -- | <0.0025 | <0.0025 | -- | -- |
| Total Alkalinity as CaCO3 | mg/L | | 170 | 170 | 180 | 170 | 180 | -- | -- |
| Bicarbonate Alkalinity as CaCO3 | mg/L | | 160 | 160 | 170 | 170 | 170 | -- | -- |
| Carbonate Alkalinity as CaCO3 | mg/L | | 11 | 13 | 4.6 | 8.7 | 4.0 | -- | -- |
| Benzene | mg/L | 0.005 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| Ethylbenzene | mg/L | 0.7 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| Toluene | mg/L | 1 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| Xylenes, Total | mg/L | 0.62 | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.003 | <0.003 |
| Notes | | | Depth was taken at 830' not 961' | | Uranium and lead results are unavailable due to a laboratory omission. | | | | |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above RDL

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: RGR received verbal confirmation that a single discrete sample was sufficent for DW-8. During a site visit by Corey Dimond on 12-9-2025, this sampling schedule was verified.

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells Continued**

| Dewatering Wells Water Quality Data Summary | | Well ID | DW10 | DW10 | DW10 | DW10 | DW10 | DW10 |
|---|---|---|---|---|---|---|---|---|
| | | Depth (fbtoc) | Water Interface, 479 | 781 | 865 | Water Interface, 479 | 781 | 865 |
| | | Sample Type | Sample | Sample | Sample | Sample | Sample | Sample |
| | | Date Collected | 4/21/2026 | 4/21/2026 | 4/21/2026 | 3/10/2026 | 3/10/2026 | 3/11/2026 |
| **Analyte** | **Units** | **New Mexico WQCC-3103** | | | | | | |
| **Arsenic** | **mg/L** | **0.01** | <0.0040 | <0.0040 | <0.0040 | <0.004 | <0.004 | <0.004 |
| **Barium** | **mg/L** | **2** | **0.012** | **0.012** | **0.018** | **0.012** | **0.011** | **0.019** |
| **Beryllium** | **mg/L** | **0.004** | <0.0040 | <0.0040 | <0.0040 | <0.004 | <0.004 | <0.004 |
| **Boron** | **mg/L** | **0.75** | **0.64** | **0.65** | **0.63** | **0.61** | **0.57** | **0.59** |
| **Calcium** | **mg/L** | | **1.2** | **1.3** | **1.6** | **1.2** | **1.6** | **2.2** |
| **Chloride** | **mg/L** | **250** | **5.4** | **5.4** | **5.4** | **5.1** | **5.2** | **5.2** |
| **Fluoride** | **mg/L** | **1.6** | **2.7** | **2.7** | **2.7** | **2.4** | **2.4** | **2.5** |
| **Iron** | **mg/L** | **1** | <0.20 | <0.20 | <0.20 | <0.2 | <0.2 | **0.19** |
| **Lead** | **mg/L** | **0.015** | <0.0020 | <0.0020 | <0.0020 | <0.0020 | <0.0020 | <0.0020 |
| **Magnesium** | **mg/L** | | <0.20 | **0.20** | **0.28** | <0.2 | **0.28** | **0.37** |
| **Manganese** | **mg/L** | **0.2** | <0.020 | <0.020 | <0.020 | <0.02 | <0.02 | <0.02 |
| **Mercury** | **mg/L** | **0.002** | <0.00020 | <0.00020 | <0.00020 | <0.0002 | <0.0002 | <0.0002 |
| **Molybdenum** | **mg/L** | **1** | **0.011** | <0.010 | <0.010 | <0.01 | **0.013** | <0.01 |
| **Nitrate Nitrite as N** | **mg/L** | | **0.12** | <0.10 | <0.10 | <0.5 | <0.5 | <0.1 |
| **Nitrate as N** | **mg/L** | **1** | **0.12** | <0.10 | <0.10 | <0.1 | <0.1 | <0.1 |
| **Nitrite as N** | **mg/L** | **10** | <0.10 | <0.10 | <0.10 | <0.1 | <0.1 | <0.1 |
| **Nitrogen, Ammonia** | **mg/L** | | <0.67 | <0.67 | <0.67 | <0.67 | <0.67 | <0.67 |
| **Nitrogen, Total Kjeldahl** | **mg/L** | | <0.50 | <0.50 | <0.50 | <1.3 | <0.5 | <0.5 |
| **Potassium** | **mg/L** | | **0.85** | **0.85** | **0.80** | **0.90** | **0.79** | **0.82** |
| **Radium-226** | **pCi/L** | | **0.0324** | **0.00541** | <1.00 | **0.009** | **0.049** | **0.127** |
| **Radium-228** | **pCi/L** | | **0.772** | **0.483** | **0.0984** | **0.161** | **0.719** | **0.069** |
| **Radium, Total** | **pCi/L** | **5** | **0.804** | **0.488** | **0.0984** | **0.170** | **0.768** | **0.196** |
| **Selenium** | **mg/L** | **0.05** | <0.0020 | <0.0020 | <0.0020 | <0.002 | <0.002 | <0.002 |
| **Sodium** | **mg/L** | | **220** | **220** | **210** | **230** | **210** | **200** |
| **Sulfate** | **mg/L** | **600** | **64** | **64** | **64** | **63** | **63** | **63** |
| **Total Dissolved Solids** | **mg/L** | **1000** | **520** | **510** | **510** | **510** | **480** | **480** |
| **Uranium** | **mg/L** | **0.03** | **0.0011** | **0.0071** | **0.0097** | **0.002** | **0.011** | **0.017** |
| **Total Alkalinity as CaCO3** | **mg/L** | | **410** | **420** | **420** | **410** | **420** | **420** |
| **Bicarbonate Alkalinity as CaCO3** | **mg/L** | | **370** | **370** | **370** | **370** | **370** | **360** |
| **Carbonate Alkalinity as CaCO3** | **mg/L** | | **46** | **47** | **51** | **44** | **48** | **51** |
| **Notes** | | | Depth reported as water level, sample taken 15 feet below | | | Depth reported as water level, sample taken 15 feet below | | |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above RDL

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells Continued**

| Dewatering Wells Water Quality Data Summary | | Well ID | DW10 | DW10 | DW10 | DW10 | DW10 | DW10 |
|---|---|---|---|---|---|---|---|---|
| | | Depth (fbtoc) | Water Interface, 468 | 781 | 865 | Water Interface, 468 | 781 | 865 |
| | | Sample Type | Sample | Sample | Sample | Sample | Sample | Sample |
| | | Date Collected | 12/10/2025 | 12/10/2025 | 12/10/2025 | 9/10/2025 | 9/10/2025 | 9/9/2025 |
| **Analyte** | **Units** | **New Mexico WQCC-3103** | | | | | | |
| **Arsenic** | **mg/L** | **0.01** | <0.004 | <0.004 | <0.004 | <0.0025 | <0.0025 | <0.0025 |
| **Barium** | **mg/L** | **2** | **0.01** | ***0.011*** | **0.012** | **0.013** | **0.0094** | **0.0085** |
| **Beryllium** | **mg/L** | **0.004** | <0.004 | <0.004 | <0.004 | <0.0020 | <0.0020 | <0.0020 |
| **Boron** | **mg/L** | **0.75** | **0.58** | **0.62** | **0.58** | **0.61** | **0.59** | **0.58** |
| **Calcium** | **mg/L** | | **1.4** | **1.7** | **1.5** | **1.6** | **1.4** | **1.3** |
| **Chloride** | **mg/L** | **250** | **5** | **5** | **5.1** | **13** | **6.0** | **5.4** |
| **Fluoride** | **mg/L** | **1.6** | **2.6** | **2.6** | **2.6** | **2.5** | **2.5** | **2.5** |
| **Iron** | **mg/L** | **1** | **0.094** | **0.18** | **0.18** | **0.094** | **0.20** | **0.089** |
| **Lead** | **mg/L** | **0.015** | -- | -- | -- | <0.0025 | <0.0025 | <0.0025 |
| **Magnesium** | **mg/L** | | **0.22** | **0.28** | **0.27** | **1.6** | <1.0 | <1.0 |
| **Manganese** | **mg/L** | **0.2** | <0.02 | <0.02 | <0.02 | **0.0049** | **0.0029** | <0.0020 |
| **Mercury** | **mg/L** | **0.002** | <0.0002 | <0.0002 | <0.0002 | <0.00020 | <0.00020 | <0.00020 |
| **Molybdenum** | **mg/L** | **1** | <0.01 | <0.01 | <0.01 | <0.0080 | <0.0080 | <0.0080 |
| **Nitrate Nitrite as N** | **mg/L** | | <0.1 | <0.1 | <0.1 | <1.0 | <1.0 | <1.0 |
| **Nitrate as N** | **mg/L** | **1** | <0.1 | <0.1 | <0.1 | <1.0 | <1.0 | <1.0 |
| **Nitrite as N** | **mg/L** | **10** | <0.1 | <0.1 | <0.1 | <1.0 | <1.0 | <1.0 |
| **Nitrogen, Ammonia** | **mg/L** | | <0.5 | <0.5 | <0.5 | <0.67 | <0.67 | <0.67 |
| **Nitrogen, Total Kjeldahl** | **mg/L** | | <0.5 | <0.5 | <0.5 | <0.50 | <0.50 | <0.50 |
| **Potassium** | **mg/L** | | **0.76** | **0.88** | **0.91** | **1.5** | <1.0 | <1.0 |
| **Radium-226** | **pCi/L** | | **0.0485** | **0.181** | **0.192** | **0.0389** | **0.297** | **0.167** |
| **Radium-228** | **pCi/L** | | **0.483** | **0.106** | **0.244** | **1.08** | **1.34** | **0.775** |
| **Radium, Total** | **pCi/L** | **5** | 0.5315 | **0.287** | **0.436** | **1.1189** | **1.637** | **0.942** |
| **Selenium** | **mg/L** | **0.05** | <0.002 | <0.002 | <0.002 | <0.0050 | <0.0050 | <0.0050 |
| **Sodium** | **mg/L** | | **200** | **210** | **200** | **220** | **210** | **220** |
| **Sulfate** | **mg/L** | **600** | **62** | **62** | **63** | **62** | **63** | **61** |
| **Total Dissolved Solids** | **mg/L** | **1000** | **560** | **550** | **540** | **270** | **510** | **520** |
| **Uranium** | **mg/L** | **0.03** | **0.0037** | **0.0097** | **0.012** | **0.0030** | **0.011** | **0.0096** |
| **Total Alkalinity as CaCO3** | **mg/L** | | **420** | **420** | **420** | **410** | **410** | **410** |
| **Bicarbonate Alkalinity as CaCO3** | **mg/L** | | **370** | **370** | **370** | **370** | **360** | **360** |
| **Carbonate Alkalinity as CaCO3** | **mg/L** | | **45** | **45** | **45** | **43** | **40** | **46** |
| **Notes** | | | Sample taken 15' below WI. Lead unavailable due to a lab omission. | Lead unavailable due to a laboratory omission. | | Depth reported as water level, sample taken 15 feet below | | |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above RDL

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells Continued**

| Dewatering Wells Water Quality Data Summary | | | Well ID | DW10 | DW10 | DW10 | DW10 | DW10 | DW10 | DW10 |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | Depth (fbtoc) | Water Interface, 479 | 781 | 865 | Water Interface, 479 | 781 | 865 | Water Interface, 468 |
| | | | Sample Type | Sample | Sample | Sample | Sample | Sample | Sample | Sample |
| | | | Date Collected | 4/21/2026 | 4/21/2026 | 4/21/2026 | 3/10/2026 | 3/10/2026 | 3/11/2026 | 12/10/2025 |
| **Analyte** | **Units** | **New Mexico WQCC-3103** | | | | | | | | |
| **TPH, EPA Method 8015D** | | | | | | | | | | |
| **Diesel Range Organics [C10-C28]** | **mg/L** | | | <1 | <1 | <1 | <1 | <1 | <1 | <1 |
| **Gasoline Range Organics [C6 - C10]** | **mg/L** | | | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 | <0.05 |
| **Motor Oil Range Organics [C28-C40]** | **mg/L** | | | <5 | <5 | <5 | <5 | <5 | <5 | <5 |
| **VOC, EPA Method 8260B** | | | | | | | | | | |
| **Benzene** | **mg/L** | **0.005** | | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Ethylbenzene** | **mg/L** | **0.7** | | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Toluene** | **mg/L** | **1** | | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Xylenes, Total** | **mg/L** | **0.62** | | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.0015 |
| **PAH, EPA Method 8270-SIM** | | | | | | | | | | |
| **1-Methylnaphthalene** | **mg/L** | **0.03** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **2-Methylnaphthalene** | **mg/L** | **0.03** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Acenaphthene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Acenaphthylene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Anthracene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Benzo[a]anthracene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Benzo[a]pyrene** | **mg/L** | **0.0002** | | <0.00007 | <0.00007 | <0.00007 | <0.00007 | <0.00007 | <0.00007 | <0.00007 |
| **Benzo[g,h,i]perylene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Benzo[b]fluoranthene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Chrysene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Dibenz(a,h)anthracene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Fluoranthene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Fluorene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Indeno[1,2,3-cd]pyrene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Naphthalene** | **mg/L** | **0.03** | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Phenanthrene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Pyrene** | **mg/L** | | | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 | <0.0002 |
| **Notes** | | | | Depth reported as water level, sample taken 15 feet below | | | Depth reported as water level, sample taken 15 feet below | | | Depth reported as water level, sample taken 15 feet below |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above RDL

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

**Table 2-2 Water Quality Test Results for Point Lookout/Hosta Aquifer Wells Continued**

| Dewatering Wells Water Quality Data Summary | | Well ID | DW10 | DW10 | DW10 | DW10 | DW10 | DW10 | DW10 | DW10 |
|---|---|---|---|---|---|---|---|---|---|---|
| | | Depth (fbtoc) | 781 | 865 | Water interface, 468 | 781 | 865 | Water Interface, 463 | 781 | 865 |
| | | Sample Type | Sample | Sample | Sample | Sample | Sample | Sample | Sample | Sample |
| | | Date Collected | 12/10/2025 | 12/10/2025 | 9/10/2025 | 9/10/2025 | 9/9/2025 | 10/09/2023 | 10/09/2023 | 10/06/2023 |
| **Analyte** | **Units** | **New Mexico WQCC-3103** | | | | | | | | |
| **TPH, EPA Method 8015D** | | | | | | | | | | |
| **Diesel Range Organics [C10-C28]** | **mg/L** | | <1 | <1 | | | | **0.518** | **0.112** | **0.395** |
| **Gasoline Range Organics [C6 - C10]** | **mg/L** | | <0.05 | <0.05 | | | | | | |
| **Motor Oil Range Organics [C28-C40]** | **mg/L** | | <5 | <5 | | | | **0.871** | **0.236** | **0.74** |
| **VOC, EPA Method 8260B** | | | | | | | | | | |
| **Benzene** | **mg/L** | **0.005** | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Ethylbenzene** | **mg/L** | **0.7** | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Toluene** | **mg/L** | **1** | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 | <0.001 |
| **Xylenes, Total** | **mg/L** | **0.62** | <0.0015 | <0.0015 | <0.0015 | <0.0015 | <0.002 | <0.003 | <0.003 | <0.003 |
| **PAH, EPA Method 8270-SIM** | | | | | | | | | | |
| **1-Methylnaphthalene** | **mg/L** | **0.03** | <0.0002 | <0.0002 | | | | <0.00025 | <0.00025 | <0.00025 |
| **2-Methylnaphthalene** | **mg/L** | **0.03** | <0.0002 | <0.0002 | | | | <0.00025 | <0.00025 | <0.00025 |
| **Acenaphthene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.00005 | <0.00005 | <0.00005 |
| **Acenaphthylene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.00005 | <0.00005 | <0.00005 |
| **Anthracene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.00005 | <0.00005 | <0.00005 |
| **Benzo[a]anthracene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.00005 | <0.00005 | <0.00005 |
| **Benzo[a]pyrene** | **mg/L** | **0.0002** | <0.00007 | <0.00007 | | | | <0.00005 | <0.00005 | <0.00005 |
| **Benzo[g,h,i]perylene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.00005 | <0.00005 | <0.00005 |
| **Benzo[b]fluoranthene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.00005 | <0.00005 | <0.00005 |
| **Chrysene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.00025 | <0.00025 | <0.00025 |
| **Dibenz(a,h)anthracene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.00005 | <0.00005 | <0.00005 |
| **Fluoranthene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.00005 | <0.00005 | <0.00005 |
| **Fluorene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.0001 | <0.0001 | <0.0001 |
| **Indeno[1,2,3-cd]pyrene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.00005 | <0.00005 | <0.00005 |
| **Naphthalene** | **mg/L** | **0.03** | <0.0002 | <0.0002 | | | | <0.00025 | <0.00025 | <0.00025 |
| **Phenanthrene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.00005 | <0.00005 | <0.00005 |
| **Pyrene** | **mg/L** | | <0.0002 | <0.0002 | | | | <0.00005 | <0.00005 | <0.00005 |
| **Notes** | | | | | Depth reported as water level, sample taken 15 feet below | | | Depth reported as water level, sample taken 15 feet below | | |

Acronyms: Reporting Detection Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH)

**BOLD** Bold numbers in cells indicates a concentration was measured above RDL

***BOLD-Italicize*** Bold-italicized indicates analytes detected above the reporting detection limit (RDL) in associated quality control samples

Yellow shading in cells indicates a concentration was measured above NMWQCC-3103 Standards

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

**Table 2-2(a) Alluvial and Menefee WQCC Analyte Exceedances During the 2Q 2026 Sampling Event[1]**

| Analyte | WQCC Standard | Wells in Exceedance |
|---|---|---|
| **Arsenic** | 0.01 mg/L | MW-2F, MW-6 |
| **Boron** | 0.75 mg/L | MW-4, WL-2 |
| **Chloride** | 250 mg/L | MW-1M, MW-4D, MW-6, WP-5 |
| **Iron** | 1 mg/L | MW-3, MW-6, MW-4H |
| **Manganese** | 0.2 mg/L | MW-1M, MW-11A, MW-3, MW-6, MW-4H |
| **Nitrogen, Nitrate** | 10 mg/L | MW-1M, WP-5 |
| **pH** | 6-9 | MW-1J, MW-2F |
| **Selenium** | 0.05 mg/L | MW-1M, MW-5, WP-5 |
| **Sulfate** | 600 mg/L | MW-1M, MW-4D, MW-4H, MW-11A, MW-4, MW-5, MW-6, WP-5, WL-2, WL-3, WL-4 |
| **TDS** | 1000 mg/L | MW-1M, MW-4D, MW-4H, MW-11A, MW-3, MW-4*, MW-5*, MW-6, WP-4, WP-5, WL-2, WL-3, WL-4 |
| **Uranium** | 0.03 mg/L | MW-1M, MW-11A, MW-4, MW-5, MW-6, WP-5 |

*There were not enough sample water available to sample for this analyte; however, historical data indicate that concentrations at these locations have consistently exceeded the applicable standard.

WQCC = Water Quality Control Commission

[1]EA, *2026b.*

## Table 2-3 Post-Closure Disposition of Mine Dewatering, Site Water Use, and Observation Wells

| Well No. | Closure Disposition (2) | State Plane Coordinates (NAD 83) | | Aquifer in Screened Interval (3, 4, 5) |
|---|---|---|---|---|
| | | N | E | |
| DW-1 | PCMP, PMLU | 1579422 | 2782632 | PLH |
| DW-2 | Plug | 1579121 | 2782606 | TH/D |
| DW-2a(1) | PMLU | 1579202 | 2782709 | PLH |
| DW-3 | Plug | 1579011 | 2782801 | PLH |
| DW-4 | Plug | 1578965 | 2783021 | PLH |
| DW-5 | Plug | 1580374 | 2785615 | PLH |
| DW-6(1) | PMLU | 1579214 | 2783407 | PLH |
| DW-7 | PMLU | 1579461 | 2783387 | PLH |
| DW-8(1) | PMLU | 1579673 | 2783247 | PLH |
| DW-9 | Plug | 1579721 | 2782987 | TH |
| DW-10 | Plug | 1579621 | 2782740 | PLH |
| DW-11 | Plug | 1578849 | 2783250 | TH/D |
| DW-12 | Plug | 1579423 | 2783445 | TH/D |
| DW-13 | Plug | 1579382 | 2782073 | WWC |
| DW-14 | PCMP, PMLU | 1578850 | 2782188 | WWC |
| DW-15 | Plug | 1578491 | 2782501 | WWC |
| DW-16 | Plug | 1578335 | 2783004 | WWC |
| DW-17 | Plug | 1578576 | 2783571 | WWC |
| DW-18 | Plug | 1578908 | 2783788 | WWC |
| DW-19 | Plug | 1580829 | 2786130 | WWC |
| DW-20 | Plug | 1579947 | 2783511 | D/ WWC |
| DW-21 | Plug | 1580168 | 2782974 | D/ WWC |
| DW-22 | Plug | 1579902 | 2782468 | WWC |
| SM-24-38(6) | Plug | 1579132 | 2783007 | WWC |
| SM-24-43(6) | Plug | 1579029 | 2782948 | WWC |
| SM-24-89(6) | Plug | 1578964 | 2782908 | WWC |
| SM-15-59(6) | Plug | 1584519 | 2771754 | -- |
| SM-13-74(6) | Plug | 1584233 | 2783313 | -- |
| SM-31-1-2D(6) | Plug | 1584519 | 2786914 | -- |
| SM 24-23E(6) | Plug | 1579711 | 2783249 | D |

(1) Wells DW-2a, DW-6, DW-7, and DW-8 will supply water from the PLH for site uses.

(2) PMLU= post-mining land use, PCMP=Post-Closure Monitoring Plan

(3) All well casings are steel: 8-5/8" ID in Pt Lookout/Hosta, 9-5/8" ID in Tres Hermanos and Dakota, 10-¾" ID with 7" liner in Westwater

(4) PLH=Pt Lookout/Hosta, TH= Tres Hermanos, D= Dakota, WWC = Westwater Canyon

(5) -- = Well details unknown

(6) Observation Wells

**Table 2-4 As-Built Capacities of MWTU Ponds #2 and #3**

| Pond Number | Operating Pool Elevation (ft) | | Water Surface Area at Pool Elevation ($ft^2$) | Volume (cy) | Volume (acre feet) |
|---|---|---|---|---|---|
| 2 | Max | 7300 | 31,605 | 11,237 | 6.97 |
| 3 | Max | 7300 | 50,178 | 18,227 | 11.23 |

Note: Calculations based on as-built survey of Ponds #2 and #3 by CSTI surveyors in November 2019 after removal of contaminated sediments and soil.

**Table 3-1(a) Radiological Survey Results for PMLU Habitable Structures**

| PMLU Habitable Structure (Figure 1-2B Map ID) | Interior Surface Alpha Activity (dpm/100 $cm^2$) | | Exterior Surface Alpha Activity (dpm/100 cm2) | |
|---|---|---|---|---|
| | Average | Maximum* | Average | Maximum* |
| Hoist House (06)[1] | 322 | 471 | - | - |
| Rocky's Shop (06) [2] | 538 | 1,100 | 246 | 600 |
| Guard House (Security Building) (18)[1] | 3 | 11 | - | - |
| Service Building (Office and Warehouse) (07)[1] | 294 | 1,189 | - | - |
| Core Storage Building (20)[2] | 113 | 6,273 | 166 | 455 |
| Ion Exchange Plant (32) [2] | 388 | 5,330 | 173 | 870 |
| Electrical Building (11)[2] | 112 | 278 | 120 | 200 |

*Regulatory Limit for Equipment Release, per *Radiation Protection Program Manual Mount Taylor Mine* (ERG, 2021): 5,000 dpm/100 $cm^2$

[1]Surveys conducted in July 2012 by Stan Fitch, CHP

[2]Surveys conducted in 2021 by ERG

**Table 3-1(b) Status of Release Surveys for Other PMLU Structures**

| Other PMLU Structures | Release Survey Status | Applicable Release Survey Type | | |
|---|---|---|---|---|
| | | Surface Alpha Activity | Volumetric Sampling | Gamma Survey |
| Water Tank | TBD | X | | |
| Septic Tank and Leach Field | TBD | X | X | |
| Dewatering Wells | TBD | X | | |
| Storm Drain System | TBD | | X | X |
| Capacitor Building | TBD | | | |
| South Storm Water Pond | Completed | | X | X |
| MWTU Pond 2 | Completed | | X | X |
| MWTU Pond 3 | Completed | | X | X |

TBD = To be determined

## Table 3-1(c) Summary of Radiological Survey Results for Non-PMLU Buildings

| Non-PMLU Building (Figure 1-2B Map ID) | Date Surveyed | Interior Surfaces Alpha Activity (dpm/100 $cm^2$) | | Exterior Surfaces Alpha Activity (dpm/100 $cm^2$) | |
|---|---|---|---|---|---|
| | | Average | Maximum* | Average | Maximum* |
| Carpenter Shop (14) [1] | 7/14/2020 | 54 | 290 | 123 | 210 |
| Water Treatment Building (09) [2] | 7/15/2020 | 253 | 1,680 | 221 | 940 |
| Chiller Pump Building (25)[3] | 7/20/2020 | 1,200 | 7,570 | 347 | 1,860 |
| York Chiller Building (17) [4] | 7/16/2020 | 238 | 1,200 | 100 | 330 |
| Fire Equipment Building (19) [5] | 7/28/2020 | 193 | 690 | 199 | 340 |
| Fuel Pump Building (13) [6] | 7/29/2020 | 63 | 160 | 53 | 80 |
| Glycol Heat Exchanger (05)[7] | 7/29/2020 | 679 | 8,150 | 1,475 | 10,425 |
| Flocculant Treatment Facility (34) [8] | 1/18/2021 | 966 | 3,853 | 203 | 263 |
| Trailer House (48) [9] | 1/18/2021 | 96 | 290 | 129 | 210 |
| Mine Water Treatment Pump House MCC (36) [10] | 1/19/2021 | 69 | 170 | 363 | 1,716 |
| Barium Chloride Treatment Facility (31)[11] | 1/20/2021 | 84 | 180 | 257 | 1,270 |
| Shaft Heating Building (04A)[12] | 1/21/2021 | 408 | 1,290 | 100 | 237 |
| Storage Building/Quonset Hut (04B) [13] | 1/20/2021 | 227 | 620 | 221 | 360 |
| Emergency Hoist House (04C) [1] | 8/19/2021 | 256 | 732 | 87 | 134 |
| Compressor Building (10) [15] | 8/19/2021 | 175 | 526 | 106 | 250 |

* Regulatory Limit for Equipment Release, per *Radiation Protection Program Manual Mount Taylor Mine* (ERG, 2021): 5,000 dpm/100 $cm^2$

[1]ERG, *Radiological survey results to inform the disposition of legacy Carpenter Shop building*, August 10, 2021
[2]ERG, *Radiological survey results to inform the disposition of legacy Water Treatment building*, October 7, 2020
[3]ERG, *Radiological survey results to inform the disposition of legacy Chiller Pump building*, January 25, 2021
[4]ERG, *Radiological survey results to inform the disposition of legacy York Chiller building*, July 16, 2020
[5]ERG, *Radiological survey results to inform the disposition of legacy Fire Equipment building*, January 25, 2021
[6]ERG, *Radiological survey results to inform the disposition of legacy Fuel Pump building*, January 25, 2021
[7]ERG, *Radiological survey results to inform the disposition of legacy Glycol Heat Exchanger building*, January 28, 2021
[8]ERG, *Radiological survey results to inform the disposition of legacy Flocculant Building*, February 15, 2021
[9]ERG, *Radiological survey results to inform the disposition of legacy Trailer House*, February 3, 2021
[10]ERG, *Radiological survey results to inform the disposition of legacy Auxiliary Mine Water Treatment Pump House MCC*, February 3, 2021
[11]ERG, *Radiological survey results to inform the disposition of legacy Barium Chloride Building*, February 3, 2021
[12]ERG, *Radiological survey results to inform the disposition of legacy Shaft Heat building*, August 17, 2021
[13]ERG, *Radiological survey results to inform the disposition of legacy Storage Building/Quonset Hut building*, August 17, 2021
[14]ERG, *Radiological survey results to inform the disposition of legacy Emergency Hoist building*, December 31, 2021
[15]ERG, *Radiological survey results to inform the disposition of legacy Compressor building*, January 18, 2022

**Table 4-1 Potential Contaminants on Site and in Use**

| DESCRIPTION | SAFETY DATA Sheets (SDS), Chemical Abstracts Service Registry Number (CAS #) | | |
|---|---|---|---|
| Antifreeze/Coolant | 107-21-1 | | |
| Coherex | 64742-34-3 | 64742-11-6 | |
| Diesel Fuel #2 | 68476-34-6 | 64742-80-9 | 64741-44-2 |
| | 91-20-3 | | |
| Engine Oil | 68649-42-3 | | |
| | 86290-81-5 | 71-43-2 | 108-88-3 |
| Gasoline Fuel | 110-54-3 | 110-82-7 | 108-87-2 |
| | 637-92-3 | 994-05-8 | 142-82-5 |
| Grease | 686-42-3 | Mixture | |
| Holeplug 3/8 | 14464-46-1 | 15468-32-3 | 1302-78-9 |
| Hydraulic Oil | Mixture | | |
| Insulating Oil | 64741-97-5 | 64742-53-6 | |
| Lubricant - Gear | Mixture | | |
| Transmission Fluid | Mixture | | |
| Windshield Wiper Fluid | UN120 50/50 67-56-1 | | |
| Simple Green | 7732-18-5 | | |
| Kerosene | 8008-20-6 | | |
| DEF Fluid | 57-13-6 | 7732-18-5 | |

## Table 4-2 Mine Facility Disposition at Closeout

| Number[*5] | Facility Name | Facility Type | Dimensions | Closeout Status Disposition as of September 2026 | | |
|---|---|---|---|---|---|---|
| | | | | Structure and Removal Date | Foundation | Retain for PMLU |
| W | Phase I Water Wells[*1] | Steel casing and screen | | To be plugged/ abandoned[*1*3] | | √ |
| W | Phase II Water Wells | Steel casing and screen | | To be plugged/ abandoned[*3] | | |
| W | Phase III Water Wells[*2] | Steel casing and screen | | To be plugged/ abandoned[*2*3] | | |
| 01 | Manway Shaft | Reinforced concrete liner | 3340' | To be plugged | | |
| 01A | Manway Shaft Headframe | Structural steel | 75' high | Removed (1/22) | | |
| 02 | Production Shaft | Reinforced concrete liner | 3300' | To be plugged | | |
| 02A | Production Shaft Headframe | Structural steel | 180' high | Removed (12/22) | | |
| 03 | Mine Ventilation Structure | Evase' (steel), frame and fan | | Removed (1/22) | | |
| 04A | Shaft Heating Buildings | Steel frame and siding | 50' X 30' X 16' | Removed (12/21) | Covered with soil (retain as part of shaft plug) | √ |
| 04B | Storage Building | Steel frame and siding | 28' X 30' X 16' | Removed (12/21) | Retain for storage | √ |
| 04C | Emergency Hoist House | Steel frame and siding | Unknown | Removed (date unknown) | Retain for storage | √ |
| 05 | Glycol Heat Exchanger | Steel frame and siding | 50’ X 30’ X 16’ | Removed (10/20) | Retain for storage | √ |
| 06 | Hoist House & Rocky’s Shop | Steel frame and siding | 162' X 120' X 40' | | | √ |
| 07 | Service Building (Office and Warehouse) | Steel frame and siding | 194' X 138' X 24' | | | √ |

## Table 4-2 Mine Facility Disposition at Closeout Continued

| Number*5 | Facility Name | Facility Type | Dimensions | Closeout Status Disposition as of September 2026 | | |
|---|---|---|---|---|---|---|
| | | | | Structure and Removal Date | Foundation | Retain for PMLU |
| 08 | Capacitor Building | Steel frame and siding | 27’ X 24’ X 16’ | | | √ |
| 09 | Water Treatment & Boiler Building | Steel frame and siding | 62' X 50' X 16' | Removed (9/20) | Rubblized and removed | |
| 10 | Compressor Building | Steel frame and siding | 40'4" X 40'2" X 16' | Removed (12/21) | Rubblized and removed | |
| 11 | Electrical Building | Steel frame and siding | 62' X 30' X 16' | | | √ |
| 12 | Portable Building | Steel frame and siding | 12' X 12' X 8' | Removed (11/20) | Rubblized and removed | |
| 13 | Fuel Pump House | Steel frame and siding | 10' X 15' X 8' | Removed (4/21) | Rubblized and removed | |
| 14 | Carpenter Shop | Steel frame and siding | 45' X 24' X 16' | Removed (10/20) | Rubblized and removed | |
| 15 | Fuel Storage Tanks | Steel | 5’ X 30' X 6' | Removed (2/20) | Rubblized and removed | |
| 16 | Water Tank | Steel | | | | √ |
| 17 | York Chiller Building | Steel frame and siding | 100' X 50' X 30' | Removed (4/21) | Rubblized, to be covered with soil | |
| 18 | Guard House (Security Building) | Steel frame and siding | 63' X 20'6" X 16' | | | √ |
| 19 | Fire Equipment Building (Fire House) | Steel frame and siding | 27' X 24' X 16' | Removed (3/21) | Concrete foundation slab to be retained for parking & storage | √ |
| 20 | Core Storage Building | Steel frame and siding | 100' X 38' X 16' | | | √ |
| 21 | Shaft Sump Cleanout Bin | Concrete | Unknown | | To be rubblized and removed | |
| 22 | Fan Shop | Steel frame and siding | 40' X 30' X 12' | | | √ |
| 23 | Car (Maintenance) Shop | Steel frame and siding | 150' X 100' X 30' | Removed (3/26) | Rubblized and removed | |

## Table 4-2 Mine Facility Disposition at Closeout Continued

| Number*5 | Facility Name | Facility Type | Dimension | Closeout Status Disposition as of September 2026 | | |
|---|---|---|---|---|---|---|
| | | | | Structure and Removal Date | Foundation | Retain for PMLU |
| 24 | CMP Utility Tunnel | Concrete | 10'X 8' X 700' | To be removed or flowable filled | | |
| 25 | Chiller Pump Building | Steel frame and siding | 40' X 24' X 16' | Removed (12/21) | Rubblized and covered with soil | |
| 26 | Cooling Tower | Steel frame and siding | 75' X 25' X 25' | Removed (12/21) | Rubblized, to be removed | |
| 27 | Chlorine Building | Concrete block | 23' X 50'6" X 20' | Removed (8/21) | Rubblized, to be covered with soil | |
| 28 | Conduits | 11.5-inch diameter steel pipe | 3100'-3200' deep | To be plugged/ abandoned | | |
| 29 | Access/Utility Tunnels | Concrete | | | | √ |
| 30 | Ore Car Rails | Steel (with wood and concrete ties) | 6750' | Removed (2021) | | |
| 31 | Barium Chloride Treatment Facility | Steel frame and siding | 40' X 25' X 16' | Removed (3/21) | Rubblized, to be covered with soil | |
| 33 | Ion Exchange Plant | Steel frame and siding | 140' X 70' X 40' | | | √ |
| 34 | Flocculant Treatment Facility | Steel frame and siding | 30' X 23' X 12' | Removed (3/21) | Rubblized, to be removed | |
| 35 | Treated Water Discharge Pipeline | 24-inch diameter steel pipe, concrete trust blocks | 4.3 miles | Removed (2025) | | |
| 36 | Mine Water Treatment Pump House | Steel frame and siding | 20' x 12' x 8' | Removed (2021) | Removed | |
| 37 | Ore Loading Pad and Wash Bay | Steel, concrete | 5,664 sf base, 400' X 4' X 1' walls | To be removed | To be removed | |

## Table 4-2 Mine Facility Disposition at Closeout Continued

| Number[*5] | Facility Name | Facility Type | Dimensions | Closeout Status Disposition as of September 2026 | | |
|---|---|---|---|---|---|---|
| | | | | Structure and Removal Date | Foundation | Retain for PMLU |
| 38 | Sanitary Treatment Plant | Concrete; steel | 70' X 30' X 6'; 40' X 20' X 8' | To be removed | | |
| 39 | Septic Tank and Leach Field | Various (concrete, plastic, gravel) | | | | √ |
| 40 | Chiller Building Electrical Room | Steel frame and siding | 30' X 20' X 30' | Removed (4/21) | Rubblized, to be removed | |
| 41 | Storm Drain System | Steel and concrete culverts | various | | | √ |
| 42 | Ore Pad | Earthen pad | 6.8 acres | To be removed, then regraded | | |
| 43 | Ore Pad Storm Water Retention Pond | Earthen basin | 0.9 acre | To be removed, then regraded | | |
| 44 | MWTU ponds 1,4,5,6,7,8 | Earthen basins and hydraulic control structures | various | Hydraulic structures removed, ponds to be backfilled | | |
| 45A | MWTU Pond 2[*4] | Double HDPE liner system | 0.73 acre | Hydraulic structures removed, pond to be backfilled | | √ |
| 45B | MWTU Pond 3[*4] | Double HDPE liner system | 0.93 acre | Hydraulic structures removed, pond to be backfilled | | √ |
| 46 | South Storm Water Pond | Earthen basin | 2.67 acres | | | √ |
| 47 | Plant and Refrigeration Water Pipelines | Pipeline | Unknown | To be removed or flowable filled | | |

**Table 4-2 Mine Facility Disposition at Closeout Continued**

| Number*5 | Facility Name | Facility Type | Dimensions | Closeout Status Disposition as of September 2026 | | |
|---|---|---|---|---|---|---|
| | | | | Structure and Removal Date | Foundation | Retain for PMLU |
| 48 | Trailer Houses | Modular home | Unknown | Removed (date unknown) | | |

*1 Phase I wells to be used for post-mining land use or post-closure groundwater monitoring: DW-1, DW-2a, DW-6, DW-7, and DW-8
*2 Phase III well to be used for post-closure groundwater monitoring and backup site water use: DW-14
*3 All other Phase I, II, and III wells to be plugged and abandoned
*4 MWTU Ponds 2 and 3 maintained until Abatement Plan (Metric,2010) and Post-Closure Monitoring Plan (EA, 2026d) programs are complete
*5 "Number" matches "Numbers" on Figure 1-2b

## Table 4-3 Earthwork Balance

| EXCAVATION/CUT - CLEAN SOIL | | |
|---|---|---|
| **LOCATION** | **Volume, LCY** | **Destination** |
| Borrow Area C (clayey soil, clayey sand, clay) | 58,102 | Expanded Disposal Cell - Clay Cover and Liner |
| Borrow Area C (sand, sandy clay, in-situ soil) | 70,620 | Expanded Disposal Cell – 28-inch In-Situ Soil Layer |
| MWTU Area | 141,900 | Establishing MWTU area final grades |
| Ore Pad and North Diversion Channel | 12,600 | Establishing Ore Pad area final grades |
| Service and Support Area including chiller bench and north parking lot | 56,000 | Fill in Service and Support area |
| Final Grading Around the Car Shop (Cut existing grades by 2 to 3 feet) | 9,300 | Fill for north side of Disposal Cell |
| Disposal Cell Expansion Pit | 44,000 | Waste Pile/ Disposal Cell - loam cover |
| **Total** | **392,252** | |
| **FILL - CLEAN SOIL** | | |
| **LOCATION** | **Volume, LCY** | **Sources** |
| MWTU Area | 141,900 | Rough grading for final grades |
| Ore Pad and North Diversion channel | 12,600 | Rough grading for final grades |
| Service and Support Area | 52,700 | Chiller Bench and North Parking lot |
| Fill For Shaft Plugs and Other Miscellaneous Structures | 3,400 | Chiller Bench and North Parking lot |
| Fill Needed for Disposal Cell Berms, Liners, and Cover | 121,700 | Borrow Area C |
| **Total** | **332,300** | |
| **FINAL GRADING** | | |
| **LOCATION** | **Area, SY** | |
| Borrow area C north of Marquez Arroyo | 104,850 | |
| Ore Pad | 58,225 | |
| Ore Pad Runoff Retention Pond | 9,640 | |
| Borrow Area A | 38,270 | |
| Borrow Area B | 29,800 | |
| MWTU Area | 198,416 | |
| County Road 334 | 35,150 | |
| Mine Access Road | 0 | |
| Old Ore Load-out Pit | 17,850 | |
| Shaft Areas | 18,375 | |
| Service and Support Area (less building areas) | 46,082 | |
| Chiller Bench | 20,116 | |
| Compressor Bench | 21,958 | |
| Car (Maintenance) Shop Area | 30,693 | |
| Waste Rock Pile / Disposal Pit | 93,412 | |
| Substation | 4,400 | |
| **Total** | **797,986** | |

## Table 4-3 Earthwork Balance Continued

Notes:

(1) Volumes associated with the former lagoon are included per NMED request. It is not likely that the material will be excavated and transferred to the disposal cell

## Table 4-4 Summary of Materials Scheduled for the Disposal Cell

| Excavation – Contaminated Soil, Waste Rock, and Limestone | |
|---|---|
| **Location** | **Volumes ($yd^3$)** |
| **Surface and Subsurface Soil Radiological Characterization (August 14, 2023)[1] w/ Addendum (April 1, 2025)[2]** | |
| Windblown Area | 2,135 |
| Southern Mine Compound Area | 60,100 |
| Ore Pad Soils | 70,911 |
| Buried Ore Pad Runoff Retention Pond, Filled with Waste Rock | 35,556 |
| **Treatment Pond Radiologic Characterization (June 4, 2024)[3]** | |
| Leftover Soils in Ponds 1, 4, 5, 6, and 7 | 3,000 |
| **Two Pond Sediment Pile Removal from Adjacent to Borrow Area A (December 19, 2024)[4]** | |
| Waste Pond Sediment Piles Near Borrow Source Area A | 28 |
| **North Controlled Area Soil Radiologic Characterization (June 5, 2025)[5]** | |
| North Contaminated Soil[1] with Non-Ore Pad Retention Pond | 53,000 |
| **Final Status Survey, Impacted Soil/Limestone Material Removal Area (October 20, 2025)[6]** | |
| Treated Water Discharge Pipeline (TWDP) Corridor | 440 |
| **South Controlled Area Soil Radiologic Characterization (February 2026)[7]** | |
| South Controlled Area Contaminated Soil, including County Road 334 | 26,560 |
| **Other Estimated Areas** | |
| Limestone at Point of Discharge in San Lucas Canyon | 18,000 |
| Disposal Cell Expansion Pit Area | 9,300 |
| SSWP Area | 3,000 |
| Diesel-Contaminated Soil[8] | 7,400 |
| Continental Divide Coop Substation | 1,850 |
| Sediment and Waste Rock in the Former Lagoon | 10,680 |
| **Total** | **301,959** |
| **Removal - Buildings** | |
| **Location** | **Volumes ($yd^3$)** |
| Chiller Pump Building | 319 |
| Chlorine Building | 112 |
| Shaft Heating Building | 335 |
| Glycol Heat Exchanger | 328 |
| Cooling Tower | 1,597 |
| Car (Maintenance) Shop | 10,000 |
| Water Treatment and Boiler Building | 344 |


**Table 4-4 Summary of Materials Scheduled for the Disposal Cell Continued**


| | |
|---|---|
| Flocculant Treatment Facility | 77 |
| Barium Chloride Treatment Facility | 111 |
| Fuel Pump House | 34 |
| Mine Water Treatment Pump House | 28 |
| Mine Ventilation Structure | 702 |
| 24-Foot Shaft Headframe | 8,633 |
| **Total** | **32,862** |
| **Removal – Other Debris** | |
| **Location** | **Volumes ($yd^3$)** |
| Mine Car Rails | 22 |
| Mine Carts | 32 |
| Ore Load Pad and Wash Bay | 718 |
| Sanitary Treatment Plant | 493 |
| MWTU Pipes | 109 |
| BACL Tanks | 39 |
| South Laydown Yard Debris | 16,311 |
| South Laydown Yard Soil | 5,392 |
| 9 Truck Trailers Filled with Waste | 1,350 |
| Car Shop Yard | 4,762 |
| Treated Water Discharge Pipe | 600 |
| MWTU Pond 2 | 1,178 |
| MWTU Pond 3 | 1,500 |
| MWTU Ponds (1,4,5,6,7, 8) | 4,272 |
| **Total** | **36,778** |
| **Total Volumes ($yd^3$)** | |
| **Remaining Material Volume Scheduled for the Disposal Cell** | **371,599** |
| **20% Contingency** | **74,320** |
| **Remaining Material Volume Scheduled for the Disposal Cell Plus 20% Contingency** | **445, 919** |
| **Existing and Proposed Disposal Cell Capacity at 25-Acres** | **1,093,840** |
| **Existing Disposal Cell Volume Used** | **99,300** |
| **Excess Capacity in Disposal Cell at 25-acres** | **548,621** |

*Footnotes:*
[1] AVM Environmental Services, Inc., *Surface and Subsurface Soil Radiologic Characterization, Windblown Area, Ore Pad Area, and Mine Compound,* August 14, 2023.
[2] AVM Environmental Services, Inc., *Surface and Subsurface Soil Radiologic Characterization, Windblown Area, Ore Pad Area, and Mine Compound Addendum,* April 1, 2025.
[3] AVM Environmental Services, Inc., *Treatment Pond Radiologic Characterization,* June 4, 2024.

## Table 4-4 Summary of Materials Scheduled for the Disposal Cell Continued


[4] AVM Environmental Services Inc., *Gamma Scan Survey Resus Summary, Two pond sediment pile removal from adjacent to Borrow Area A,* December 19, 2024.
[5] AVM Environmental Services Inc., *North Controlled Area Soil Radiologic Characterization,* June 5, 2025.
[6] AVM Environmental Services Inc., *Final Status Survey, Impacted Soil/Limestone Material Removal Area,* October 20, 2025.
[7] AVM Environmental Services Inc., *South Controlled Area Soil Radiologic Characterization*, February 2026.
[8] Ensero Solutions, Inc., *Mt. Taylor Mine Diesel Release Corrective Action Plan*, November 2021.











T:\111360 Mt. Taylor\Site Location CCP.dwg SAVED: 7/27/26 PRINTED: 8/3/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
*Now Part of **MacKay***

**FIGURE 1-1**
**SITE LOCATION MAP**
**MT. TAYLOR MINE**




MINE UNITS AND OTHER AREAS:

| | | | |
|---|---|---|---|
| 1 | MINE WATER TREATMENT AREA | 10 | DISPOSAL CELL EXPANSION AREA |
| 2 | ORE PAD | 11 | SOUTH DIVERSION CHANNEL |
| 3 | ORE PAD RUNOFF RETENTION POND | 12 | COMPRESSOR BENCH AREA |
| 4 | NORTH DIVERSION CHANNEL | 13 | CHILLER BENCH AREA |
| 5 | BORROW AREA "A" | 14 | SERVICE AND SUPPORT AREA |
| 6 | MINE ACCESS ROAD | 15 | OLD ORE LOADING AREA |
| 7 | BORROW AREA "B" | 01 | 16 MINE SHAFTS |
| 8 | SOUTH STORM WATER POND | 17 | BORROW AREA "C" |
| 9 | EXISTING WASTE ROCK PILE/ DISPOSAL AREA | 18 | WINDBLOWN AREA |

LEGEND:

- MINE SITE AREA
- SECTION 24 BOUNDARY
- ROADWAY
- BORROW AREA "C" ACCESS ROAD
- FENCE
- EXISTING TOPOGRAPHY
- DRAINAGE PATHWAYS
- MINE BUILDINGS (PRIOR TO REMOVAL ACTIVITIES)

GENERAL NOTES:

G.1 THE MINE PERMIT AREA INCLUDES THE RIGHT OF WAY ALONG THE TREATED WATER DISCHARGE PIPELINE AND A 50' WIDE CORRIDOR FOR AN ACCESS ROAD (SEE FIGURE 1-3).

G.2 AFFECTED AREAS INCLUDE BUT ARE NOT LIMITED TO BORROW AREA "B." EVALUATION OF OTHER POSSIBLE AFFECTED AREAS IS ONGOING.

G.3 THIS DRAWING SHOWS THE SITE CONDITIONS AS OF JULY 2025. SEE FIGURE 1-2B AND TABLE 4.2 FOR DETAILED FACILITY DISPOSITION INFORMATION.

G.4 TOPOGRAPHY BASED ON A 2012 AERIAL SURVEY BY THOMAS R. MANN AND ASSOCIATES AND 2021 SURVEYS BY SOUTHWEST SURVEYING SOLUTIONS (S3).

NORTH

SCALE IN FEET
0 500'


T:\111360 Mt. Taylor\Site Mine CCP26.dwg SAVED:7/6/26 PRINTED:8/3/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 1-2**
**MINE SITE AND AFFECTED AREAS**
**MT. TAYLOR MINE**




NOTES:

1. COUNTY ROAD 334, POWER POLES AND TRANSMISSION LINES, AND SUBSTATION ARE FACILITIES OWNED BY OTHERS AND ARE NOT WITHIN PERMIT. OTHER THAN CLEANUP OF CONTAMINATED SOILS, THESE FACILITIES ARE NOT SUBJECT TO CLOSEOUT.
2. DEWATERING AND PROCESS WATER PIPELINES (PARTLY SHOWN) TO BE REMOVED AND PROPERLY DISPOSED OF IF NOT NEEDED FOR PMLU WATER MANAGEMENT.
3. MWTU PONDS 2 AND 3 TO REMAIN UNTIL ABATEMENT ACTIVITIES ARE COMPLETED. ALL OTHER MWTU PONDS AND THE ORE PAD POND TO BE REGRADED.
4. CONCRETE FOUNDATIONS: EXCEPT WHERE OTHERWISE NOTED, REMOVAL OF THE STRUCTURES INCLUDES RUBBLIZATION OF THE CONCRETE SLAB AND FOUNDATIONS. ANY CONTAMINATED CONCRETE SHALL BE REMOVED AND PLACED IN THE DISPOSAL CELL. CLEAN RUBBLIZED CONCRETE CAN EITHER BE REMOVED AND PLACED IN THE DISPOSAL CELL, OR COVERED BY 24" OF CLEAN SOIL AT THE DISCRETION OF RGR.

LEGEND

- PONDS TO RETAIN
- PONDS TO BE REGRADED
- FACILITIES REMOVED AS OF 9-01-26
- FACILITIES TO BE REMOVED
- FACILITIES RETAINED FOR PMLU
- TR — ELECTRICAL TRANSFORMERS TO BE RETAINED
- STORM DRAINAGE SYSTEM
- 01 — MINE SHAFTS
- CONDUITS

NORTH

SCALE IN FEET
0 300'

FACILITIES AND FOUNDATIONS REMOVAL PENDING (4)

| NO. | FACILITY NAME |
|---|---|
| 21 | Shaft Sump Cleanout Bin |
| 37 | Ore Loading Pad and Wash Bay |
| 38 | Sanitary Treatment Plant |

SHAFTS AND CONDUITS

| NO. | FACILITY NAME | DISPOSITION |
|---|---|---|
| 01 | Manway Shaft | To Be Plugged |
| 02 | Production Shaft | |
| 28 | Conduits (2) | |

PONDS

| NO. | FACILITY NAME | DISPOSITION |
|---|---|---|
| 43 | Ore Pad Storm Water Retention Pond | To Be Regraded |
| 44 | MWTU Ponds 1,4,5,6,7,8 | |
| 45 | Ponds 2 & 3 | PMCP* |
| 46 | South Storm Water Pond | PMLU** |

*POST-MINING LAND USE
**POST-CLOSURE MONITORING PLAN

OTHER

| NO. | FACILITY NAME | DISPOSITION |
|---|---|---|
| 47 | Plant and Refrigeration Water Pipelines (Not Shown) (2) | To Be Removed or Flowable Filled |
| 24 | CMP Utility Tunnel | |
| 42 | Ore Pad | To Be Removed |
| 03 | Mine Ventilation Structure | Above-Grade Structure Removed (No Foundation) Vent Raise to be Plugged |

WELLS

Wells are Not Shown on This Figure. See Figures 1-4, 1-6, and 1-7 for Well Locations and Dispositions.

FACILITIES REMOVED, FOUNDATION REMOVAL PENDING (4)

| NO. | FACILITY NAME |
|---|---|
| 26 | Cooling Towers |
| 27 | Chlorine Building |
| 31 | Barium Chloride Treatment Facility |
| 40 | Chiller Building Electrical Room |

FACILITIES TO BE RETAINED FOR PMLU

| NO. | FACILITY NAME |
|---|---|
| 06 | Hoist House & Rocky's Shop |
| 07 | Service Building (Office and Warehouse) |
| 08 | Capacitor Building |
| 11 | Electrical Building |
| 16 | Water Tank |
| 18 | Guard House (Security Building) |
| 20 | Core Storage Building |
| 22 | Fan Shop |
| 29 | Access/Utility Tunnel |
| 33 | Ion Exchange Plant |
| 39 | Septic Tank and Leach Field |
| W | DW-1, DW-2a, DW-6, DW-7, DW-8, DW-14, and B-516-POD4 |
| 46 | South Storm Water Pond |
| 41 | Storm Drain System |
| 45 | MWTU Pond 2 (3) |
| 45 | MWTU Pond 3 (3) |

FACILITIES REMOVED, ONLY FOUNDATIONS TO BE RETAINED

| NO. | FACILITY NAME |
|---|---|
| 01A | Manway Shaft Headframe |
| 02A | Production Shaft Headframe |
| 04A | Shaft Heating Building |
| 04B | Storage Building |
| 04C | Emergency Hoist House |
| 05 | Glycol Heat Exchanger |
| 19 | Fire Equipment Building |

FACILITIES AND FOUNDATIONS REMOVED

| NO. | FACILITY NAME (4) |
|---|---|
| 09 | Water Treatment and Boiler Building |
| 10 | Compressor Building |
| 12 | Portable Building |
| 13 | Fuel Pump House |
| 14 | Carpenter Shop |
| 15 | Fuel Storage Tanks |
| 17 | York Chiller Building |
| 23 | Car (Maintenance) Shop |
| 25 | Chiller Pump Building |
| 30 | Ore Car Rails |
| 34 | Flocculent Treatment Facility |
| 35 | Treated Water Discharge Pipeline |
| 36 | Mine Water Treatment Pump House |
| 48 | Trailer House (No Foundation) |


T:\111360 Mt. Taylor\Mine at Closeout.dwg SAVED:8/25/26 PRINTED:8/25/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 1-2B**
**MINE FACILITIES DISPOSITION AT CLOSEOUT**
**MT. TAYLOR MINE**





T:\111360 Mt. Taylor\USGS maps\USGS Maps combined.dwg SAVED: 7/7/26 PRINTED: 8/3/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
*Now Part of **MacKay***

**FIGURE 1-3**
**MINE PERMIT AREA**
**MT. TAYLOR MINE**




| Phase and Geologic Formation of Screen | Well No | Well Coordinates (NM West NAD 83) Northing | Easting | Top of Casing Elevation (Feet AMSL) | Depth From Surface (*Feet*) | Screen Interval (*Feet*) | Closure Disposition (See Notes) |
|---|---|---|---|---|---|---|---|
| ▲ (*Domestic Water Supply*) | DW-2A | 1579202 | 2782709 | 7347.0 | 925 | 750-900 | PMLU [3] |
| **1** △ Point Lookout | DW-1 | 1579419 | 2782626 | 7342.0 | 1118 | 740-890 | PCMP [2], PMLU [3] |
| | DW-4 | 1578965 | 2783021 | 7349.0 | 1130 | 750-900 | Abandon[1] |
| | DW-5 | 1579038 | 2783256 | 7403.4 | 1172 | 852-1002 | |
| | DW-6 | 1579210 | 2783402 | 7384.7 | 1190 | 845-995 | PMLU [3] |
| | DW-7 | 1579455 | 2783384 | 7376.3 | 1125 | 825-995 | |
| | DW-8 | 1579672 | 2783240 | 7342.7 | 1044 | 791-941 | |
| | DW-3 | 1579008 | 2782795 | 7350.1 | 1150 | 737-891 | Abandon[1] |
| | DW-10 | 1579619 | 2782734 | 7339.7 | 1065 | 738-888 | |
| **2** ○ Tres Hermanos/ Dakota | SM 24-23E[5] | 1579711 | 2783249 | 7342.0 | 933 | 833-933 | Abandon[1] |
| | DW-2 | 1579121 | 2782606 | 7337.6 | 2920 | 2550-2920 | |
| | DW-9 | 1579723 | 2782973 | 7337.6 | 2845 | 2538-2840 | |
| | DW-11 | 1578845 | 2783245 | 7445.0 | 3028 | 2819-3028 | |
| | DW-12 | 1579421 | 2783439 | 7418.9 | 2940 | 2791-2940 | |
| **3** ▲ Westwater | DW-13 | 1579378 | 2782065 | 7322.3 | 3185 | 3045-3185 | Abandon[1] |
| | DW-15 | 1578491 | 2782501 | 7393.5 | 3205 | 3056-3196 | |
| | DW-16 | 1578334 | 2782995 | 7393.6 | 3275 | 3105-3245 | |
| | DW-17 | 1578570 | 2783563 | 7496.8 | 3342 | 3209-3342 | |
| | DW-18 | 1578902 | 2783778 | 7497.7 | 3314 | 3212-3314 | |
| | DW-19 | 1579493 | 2783781 | 7453.2 | 3274 | 3166-3274 | |
| | DW-20 | 1579945 | 2783505 | 7386.1 | 3223 | 2938-3223 | |
| | DW-21 | 1580165 | 2782966 | 7323.4 | 3184 | 2873-3173 | |
| | DW-22 | 1579900 | 2782460 | 7305.4 | 3195 | 3019-3159 | |
| | DW-14 | 1578847 | 2782182 | 7342.3 | 3205 | 3048-3188 | PCMP [2], PMLU [3] |
| **Other** [5] ▲ Westwater | SM24-38 | 1579116 | 2783008 | 7390.0 | 3535 | 3107-3247 | Abandon[1] |
| | SM24-43 | 1579029 | 2782948 | 7347.0 | 3535 | 3064-3204 | |
| | SM24-89 | 1578964 | 2782908 | 7348.0 | 3121 | | |
| **Off-Site Wells** [4,5] | SM15-59 | 1584519 | 2771754 | 7738.0 | | | Abandon[1] |
| | SM13-74 | 1584233 | 2783313 | 7480.0 | | | |
| | SM31-1-2D | 1584519 | 2786914 | 7630.0 | | | |

NOTES

1. WELLS PLUGGED AND ABANDONED AS PART OF CLOSURE ACTIVITIES.
2. WELLS RETAINED FOR POST-CLOSURE MONITORING PLAN (PCMP) THEN PLUGGED AND ABANDONED WHEN PCMP IS COMPLETE.
3. WELLS RETAINED FOR POST-MINING LAND USE (PMLU).
4. OFF-SITE WELLS ARE SHOWN ON FIGURE 1-7.
5. THE "SM" WELLS WERE OBSERVATION WELLS NOT DEWATERING WELLS.

NORTH

SCALE IN FEET
0 200'

GENERAL NOTE

G1. DEPTHS TO BOTTOM OF WELLS AND TO GEOLOGICAL FORMATIONS ARE APPROXIMATE.


Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 1-4**
**DEWATERING WELL LOCATIONS AND DESCRIPTIONS**
**MT. TAYLOR MINE**

T:\111360 Mt. Taylor\Site Dewatering_Wells.dwg SAVED:8/24/26 PRINTED:8/24/26




T:\111360 Mt. Taylor\Section Figures.dwg SAVED: 7/7/26 PRINTED: 8/3/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 1-5**
**TYPICAL SECTION OF DEWATERING WELLS**
**MT. TAYLOR MINE**

T:\111360 Mt. Taylor\Menefee Monitoring CCP.dwg SAVED: 8/20/26 PRINTED: 8/21/26




LEGEND

- MINE SITE AREA
- PUBLIC GRAVEL ROADS
- MINE GRAVEL ROADS
- MINE BUILDINGS
- FENCE LINES
- 10' CONTOURS
- SHALLOW AQUIFER MONITORING WELLS
- 2026 SIP WELLS
- 2026 SIP BORINGS

SCALE IN FEET
0 400'
NORTH

GENERAL NOTES:

G.1 TOPOGRAPHY BASED ON A 2012 AERIAL SURVEY BY THOMAS R. MANN AND ASSOCIATES AND 2021 SURVEYS BY SOUTHWEST SURVEYING SOLUTIONS (S3).

G.2 CONTOUR LINES REPRESENT 10 FOOT VERTICAL INCREMENTS.

G.3 WELL LOCATIONS SURVEYED BY S3 SURVEYORS AND BY RGR RECORDS. SIP WELLS ARE IN THE PROCESS OF FINAL SURVEY.


G.4 SIP WELLS HAVE BEEN INSTALLED, DEVELOPED, TESTED, AND SAMPLED. RGR WILL EVALUATE SUITABILITY FOR MONITORING.

Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 1-6**
**MINE SITE ALLUVIAL AND MENEFEE MONITORING AND RECOVERY WELLS**
**MT. TAYLOR MINE**




LEGEND:

- MT. TAYLOR MINE SITE AREA
- SECTION BOUNDARIES
- WELL LOCATIONS

SCALE IN MILES

0 1/2

NORTH

GENERAL NOTES:

G.1 BASE MAP ADAPTED FROM USGS QUAD MAP.

G.2 ALL OFF-SITE WELLS TO BE ABANDONED.

| Well No | Well Coordinates (NM West NAD 83) | | Collar Elevation (Feet AMSL) |
|---|---|---|---|
| | Northing | Easting | |
| SM15-59 | 1584519 | 2771754 | 7738 |
| SM13-74 | 1584233 | 2783313 | 7480 |
| SM31-1-2D | 1584519 | 2786914 | 7630 |


T:\111360 Mt. Taylor\USGS maps\USGS Maps combined.dwg SAVED: 8/3/26 PRINTED: 8/3/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 1-7**
**OBSERVATION WELLS (OFF-SITE)**
**MT. TAYLOR MINE**




T:\111360 Mt. Taylor\Section Figures.dwg SAVED: 7/7/26 PRINTED: 8/3/26

Project No. 111360


September 2026

NOTES:

1. GSE* = GROUND SURFACE ELEVATION. THE GSE FOR THE MINE SITE VARIES FROM 7280' TO 7400'.
2. (#) INDICATES THICKNESS OF GEOLOGIC UNIT IN FEET AT THE MINE SHAFT.
3. THE ELEVATIONS SHOWN ON THIS FIGURE ARE IN FEET ABOVE MEAN SEA LEVEL.

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 2-1**
**GEOLOGIC SECTION**
**MT. TAYLOR MINE**




T:\111360 Mt. Taylor\PreMining Topo.dwg SAVED:6/26/26 PRINTED:8/3/26


Project No. 111360

NOTE:
THIS MAP IS BASED ON THE WILLIAM MATOTAN & ASSOCIATES ENGINEERS SURVEY THAT WAS BASED ON AERIAL PHOTOGRAPHY DATED 9-6-1974.

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 2-2**
**PRE-MINING TOPOGRAPHY**
**MT. TAYLOR MINE**





T:\111360 Mt. Taylor\Site GW Maps CCP26.dwg SAVED: 7/7/26 PRINTED: 8/3/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
*Now Part of **MacKay***

**FIGURE 2-3**
**WESTWATER CANYON AQUIFER POTENTIOMETRIC SURFACE MAP**
**WESTWATER CANYON AQUIFER**
**MT. TAYLOR MINE**




T:\111360 Mt. Taylor\Site GW Maps CCP26.dwg SAVED: 7/7/26 PRINTED: 8/3/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 2-4**
**TRES HERMANOS/ DAKOTA AQUIFER POTENTIOMETRIC SURFACE MAP**
**TRES HERMANOS/ DAKOTA AQUIFER**
**MT. TAYLOR MINE**





T:\111360 Mt. Taylor\Site GW Maps CCP26.dwg SAVED: 7/7/26 PRINTED: 8/3/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 2-5**
**POINT LOOKOUT/HOSTA AQUIFER POTENTIOMETRIC SURFACE MAP**
**POINT LOOKOUT/HOSTA AQUIFER**
**MT. TAYLOR MINE**




MONITOR WELL

DRY WELL (PLUGGED AND ABANDONED)

RECOVERY WELL

DEWATERING WELL

FACILITY WATER SUPPLY

STORMWATER DRAINAGE

FENCE

ROADWAY

POTENTIOMETRIC CONTOURS (10 FT) IN THE ALLUVIUM AND BEDROCK

WATER LEVEL ELEVATION CONTOURS IN THE WASTE ROCK PILE

**(N/A)** WATER LEVEL NOT RECORDED DUE TO PUMP IN WELL

7301.10 GROUNDWATER ELEVATION MEASURED JUNE 2, 2026

NORTH

SCALE IN FEET

0 400'


T:\111360 Mt. Taylor\Sampling Locations GW 2026_Q2.dwg SAVED:8/3/26 PRINTED:8/4/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
*Now Part of* ***MacKay***

**FIGURE 2-6**
**SHALLOW AQUIFER POTENTIOMETRIC MAP**
**ALLUVIAL AND MENEFEE AQUIFERS**
**MT. TAYLOR MINE**




- MONITOR WELL
- DRY WELL (PLUGGED AND ABANDONED)
- RECOVERY WELL
- DEWATERING WELL
- FACILITY WATER SUPPLY
- 2026 SIP WELL
- 2026 SIP BORING
- STORMWATER DRAINAGE
- FENCE
- ROADWAY
- FORMER LAGOON AREA
- EXISTING TOPOGRAPHY
- PROPOSED TOPOGRAPHY

NOTE:
MAX DEPTH AT HIGHEST POINT;

| Current El | Proposed El | Height |
|---|---|---|
| 7344' | 7444' | 100' |

EXPANDED VOLUME
(Compared to original disposal cell volume)

| CUT | FILL | NET |
|---|---|---|
| 1,000 | 1,103,200 | 1,102,200 |

in cubic yards

NORTH

SCALE IN FEET
0 200'


T:\111360 Mt. Taylor\Site Expanded Stability.dwg SAVED: 8/3/26 PRINTED: 8/4/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
*Now Part of **MacKay***

**FIGURE 4-1**
**EXPANDED DISPOSAL CELL WITH SITE TOPOGRAPHY, AND CURRENT WELLS**
**MT. TAYLOR MINE**





T:\111360 Mt. Taylor\Facility Reference 2026.dwg SAVED:6/26/26 PRINTED:8/3/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
*Now Part of **MacKay***

**FIGURE 4-2**
**APPROVED STAGING AREAS**
**MT. TAYLOR MINE**





T:\111360 Mt. Taylor\Site GW Nitrate.dwg SAVED: 7/6/26 PRINTED: 8/3/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 5-1**
**NITRATE DISTRIBUTION IN ALLUVIAL AND UPPER MENEFEE GROUNDWATER (AUGUST 2018)**
**MT. TAYLOR MINE**





Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 5-2**
**NITRATE DISTRIBUTION IN ALLUVIAL AND UPPER MENEFEE GROUNDWATER (2Q 2026)**
**MT. TAYLOR MINE**





T:\111360 Mt. Taylor\Site GW Uranium.dwg SAVED: 7/6/26 PRINTED: 8/3/26

Project No. 111360

September 2026

**FIGURE 5-3**
**URANIUM DISTRIBUTION IN ALLUVIAL AND UPPER MENEFEE GROUNDWATER (AUGUST 2018)**
**MT. TAYLOR MINE**

Engineering Analytics, Inc.
*Now Part of* ***MacKay***





T:\111360 Mt. Taylor\Site GW Uranium.dwg SAVED: 7/6/26 PRINTED: 8/3/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 5-4**
**URANIUM DISTRIBUTION IN ALLUVIAL AND UPPER MENEFEE GROUNDWATER (2Q 2026)**
**MT. TAYLOR MINE**





T:\111360 Mt. Taylor\Site GW Sulfate.dwg SAVED: 8/3/26 PRINTED: 8/3/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 5-5**
**SULFATE DISTRIBUTION IN ALLUVIAL AND UPPER MENEFEE GROUNDWATER (MAY 2018)**
**MT. TAYLOR MINE**





T:\111360 Mt. Taylor\Site GW Sulfate.dwg SAVED: 8/3/26 PRINTED: 8/4/26

Project No. 111360

September 2026

Engineering Analytics, Inc.
Now Part of MacKay

**FIGURE 5-6**
**SULFATE DISTRIBUTION IN ALLUVIAL AND UPPER MENEFEE GROUNDWATER (2Q 2026)**
**MT. TAYLOR MINE**




Note:
The proposed locations shown for DMW-1, DMW-2, and DMW-3 are for reference only. Actual well locations will be selected based on well pad requirements, avoidance of underground site workings, and coordination with the regulatory agencies.

NORTH

SCALE IN FEET
0 200'

DW WELL COMPLETION
- POINT LOOKOUT (PHASE I)
- TRES HERMANOS/DAKOTA (PHASE II)
- WESTWATER CANYON (PHASE III)

POINT OF COMPLIANCE WELLS FOR
- POST-CLOSURE MONITORING PLAN

T:\111360 Mt. Taylor\Post-Closure Monitoring.dwg SAVED: 8/20/26 PRINTED: 9/8/26


Project No. 111360

September 2026

Engineering Analytics, Inc.
*Now Part of **MacKay***

**FIGURE 5-7**
**LOCATION OF WELLS FOR POST-CLOSURE MONITORING OF DEEP AQUIFERS**
**MT. TAYLOR MINE**

| ID | Task Name | Duration | Start | Finish | Predecessors |
|---|---|---|---|---|---|
| 1 | CCP Approval (Estimated) | 1 day | Thu 12/31/26 | Thu 12/31/26 | |
| 2 | **Project Management** | | | | |
| 3 | Workplan Development and Approval | 120 days | Fri 1/1/27 | Thu 6/17/27 | 1 |
| 4 | Bids and Contracts | 90 days | Fri 6/18/27 | Thu 10/21/27 | 3 |
| 5 | Mobilization | 30 days | Fri 10/22/27 | Thu 12/2/27 | 4 |
| 6 | Documentation | 1245 days | Thu 12/31/26 | Wed 10/8/31 | |
| 7 | Quality Control | 1245 days | Thu 12/31/26 | Wed 10/8/31 | |
| 8 | **Facility Removal** | | | | |
| 9 | Well and Conduit Plugging | 400 days | Fri 12/3/27 | Thu 6/14/29 | 5 |
| 10 | **Surface Facilities** | | | | |
| 11 | Building Removal | 60 days | Fri 12/3/27 | Thu 2/24/28 | 5 |
| 12 | Concrete Removal | 132 days | Fri 12/24/27 | Mon 6/26/28 | 11FS-45 days |
| 13 | Pipe Removal | 115 days | Tue 6/27/28 | Mon 12/4/28 | 12 |
| 14 | **Disposal Cell** | | | | |
| 15 | Disposal Cell Expansion Pit Area Contaminated Soil Removal | 7 days | Tue 12/5/28 | Wed 12/13/28 | 13 |
| 16 | Clearing & Grubbing Cell Pad | 30 days | Thu 12/14/28 | Wed 1/24/29 | 15 |
| 17 | Placement of Bottom Liner | 13 days | Thu 1/25/29 | Mon 2/12/29 | 16 |
| 18 | Placement of Demolished Site Materials | 383 days | Tue 2/13/29 | Thu 8/1/30 | 17 |
| 19 | Placement of Contaminated Soil | 237 days | Wed 9/5/29 | Thu 8/1/30 | 17 |
| 20 | Clearing and Grubbing Borrow Area | 5 days | Mon 1/18/27 | Fri 1/22/27 | 37 |
| 21 | Cover Placement | 114 days | Mon 1/25/27 | Thu 7/1/27 | 20 |
| 22 | Haul and Blend Rock Mulch | 114 days | Mon 2/1/27 | Thu 7/8/27 | 21FS-109 days |
| 23 | Erosion Control | 114 days | Mon 2/8/27 | Thu 7/15/27 | 22FS-109 days |
| 24 | **Earthwork** | | | | |
| 25 | **Contaminated Soil Removal** | | | | |
| 26 | Limestone at Point of Outfall 001 Discharge in San Lucas Canyon | 21 days | Tue 2/13/29 | Tue 3/13/29 | 17 |




Project: CCP Schedule
Date: Tue 9/8/26

Task
Split
Milestone
Summary
Project Summary
Inactive Task
Inactive Milestone
Inactive Summary
Manual Task
Duration-only
Manual Summary Rollup
Manual Summary
Start-only
Finish-only
External Tasks
External Milestone
Deadline
Progress
Manual Progress




T:\111360 Mt. Taylor\Site Mine CCP26.dwg SAVED:8/3/26 PRINTED:9/8/26



Engineering Analytics, Inc.
*Now Part of* ***MacKay***

**FIGURE 6-1**
**CLOSEOUT/CLOSURE SCHEDULE - PAGE 1 OF 2**
**MT. TAYLOR MINE**

| ID | Task Name | Duration | Start | Finish | Predecessors |
|---|---|---|---|---|---|
| 27 | Windblown Area | 3 days | Wed 3/14/29 | Fri 3/16/29 | 26 |
| 28 | Ore Pad Soils | 93 days | Mon 3/19/29 | Wed 7/25/29 | 27 |
| 29 | Ore Pad Runoff Retention Pond, Buried Waste Rock | 21 days | Thu 7/26/29 | Thu 8/23/29 | 28 |
| 30 | North Contaminated Soil with Non-Ore Pad Retention Pond | 30 days | Fri 8/24/29 | Thu 10/4/29 | 29 |
| 31 | Southern Mine Compound Area | 44 days | Fri 10/5/29 | Wed 12/5/29 | 30 |
| 32 | Leftover Soils in Ponds 1, 4, 5, 6, & 7 | 2 days | Thu 12/6/29 | Fri 12/7/29 | 31 |
| 33 | South Controlled Area plus County Road 334 | 139 days | Mon 5/11/26 | Thu 11/19/26 | |
| 34 | Diesel-Contaminated Soil | 18 days | Fri 11/20/26 | Tue 12/15/26 | 33 |
| 35 | Sediment and Waste Rock in the Former Lagoon | 20 days | Wed 12/16/26 | Tue 1/12/27 | 34 |
| 36 | Continental Divide Coop Substat | 1 day | Wed 1/13/27 | Wed 1/13/27 | 35 |
| 37 | SSWP Area | 2 days | Thu 1/14/27 | Fri 1/15/27 | 36 |
| 38 | **Final Site Earthwork** | | | | |
| 39 | Final Status Survey | 60 days | Thu 1/14/27 | Wed 4/7/27 | 36 |
| 40 | Final Grading | 131 days | Thu 4/8/27 | Thu 10/7/27 | 39 |
| 41 | Revegetation | 22 days | Fri 10/8/27 | Mon 11/8/27 | 40 |
| 42 | **Surface Water** | | | | |
| 43 | North Ditch Survey and Design | 270 days | Fri 10/5/29 | Thu 10/17/30 | 30 |
| 44 | North Ditch Contractor Acquisitions and Construction | 90 days | Fri 10/18/30 | Thu 2/20/31 | 43 |
| 45 | South Ditch Survey and Design | 270 days | Fri 1/1/27 | Thu 1/13/28 | 1 |
| 46 | South Ditch Contractor Acquisitions and Construction | 105 days | Fri 1/14/28 | Thu 6/8/28 | 45 |
| 47 | **Shaft Plugging** | 120 days | Fri 10/8/27 | Thu 3/23/28 | 40 |
| 48 | **PCMP DMW Well Installation** | 60 days | Wed 6/26/30 | Tue 9/17/30 | 21 |
| 49 | | | | | |




Project: CCP Schedule
Date: Tue 9/8/26

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Task | Project Summary | Manual Task | Start-only | Deadline | | | |
| Split | Inactive Task | Duration-only | Finish-only | Progress | | | |
| Milestone | Inactive Milestone | Manual Summary Rollup | External Tasks | Manual Progress | | | |
| Summary | Inactive Summary | Manual Summary | External Milestone | | | | |

T:\111360 Mt. Taylor\Site Mine CCP26.dwg SAVED:8/3/26 PRINTED:9/8/26



**FIGURE 6-1**
**CLOSEOUT/CLOSURE SCHEDULE - PAGE 2 OF 2**
**MT. TAYLOR MINE**

## APPENDIX A

## Mt. Taylor Mine Closeout/Closure Plan Drawings

CL 05 Shaft Closure – Manway Vent


CL 06 Shaft Closure – Production Shaft

CL 07A Final Grading Plan Mine Water Treatment Unit


CL 07B Final Grading Plan Service and Support Area

CL 08 Details – Backfill in Pond Areas

CL 14 Final Drainage Plan




AA'
CL05
SECTION AA' - PLAN VIEW




BB'
CL05
SECTION BB'

## NOTES:

1. EXISTING CONCRETE SLAB TO REMAIN.
2. EXISTING CONCRETE SHAFT COLLAR WALLS TO REMAIN.
3. EXISTING VENT RAISE TO REMAIN AS PART OF SHAFT PLUG STRUCTURE. THE VENT RAISE TO BE BACKFILLED WITH FLOWABLE CEMENTITIOUS FILL.
4. REMOVE AND DROP ALL EQUIPMENT, FITTINGS, AND UTILITIES BETWEEN COLLAR TO SUB COLLAR LEVEL AND CLEAN SUB COLLAR OF ANY DEBRIS.
5. FLOWABLE CEMENTITIOUS BACKFILL - USE TO BACKFILL THE VENT RAISE AND SHAFT FROM PLUG AT THE SUB-COLLAR TO WITHIN 1 FOOT OF THE EXISTING CONCRETE CAP. THEN FILL THE REMAINING VOID WITH LIGHT-WEIGHT CONCRETE.
6. PLUG THE EXISTING SHAFT OPENING WITH LIGHTWEIGHT CONCRETE AND PLACE A SHAFT MARKER IN THE PLUG.
7. PLACE 2' OF CLEAN SOIL OVER THE TOP OF THE CONCRETE SLAB AND REVEGITATE.
8. 8" TO 10" PVC MONITORING PIPE WITH ACCESS CAP AT THE GROUND SURFACE.
9. UTILITY TUNNEL SHAFT CONNECTION TO BE BACKFILLED WITH THE SAME FLOWABLE CEMENTITIOUS FILL SPECIFIED FOR THE SHAFT COLLAR.

## GENERAL NOTES:

G.1 FOR CONSTRUCTION, PLACEMENT, AND MATERIAL REQUIREMENTS FOR THE FLOWABLE CEMENTITIOUS BACKFILL SEE PROJECT SPECIFICATIONS.

G.2 CONTRACTOR TO DETERMINE MEANS AND METHODS TO SAFELY FABRICATE AND INSTALL THE SHAFT PLUG AND BACKFILL SHOWN ON THIS DRAWING.

G.3 THIS IS THE APPROVED CONCEPTUAL DESIGN. THE FINAL DESIGN WILL GENERALLY FOLLOW THIS CONCEPT BUT MAY VARY IN MATERIALS AND CONSTRUCTION PER THE FINAL DESIGN OF A LICENSED STRUCTURAL ENGINEER.

| REV | DESCRIPTION | DATE | DRAWN BY | ENGINEER | APPROVED |
|---|---|---|---|---|---|
| A | FOR REVIEW | 12-17-21 | EL | EL | AK |
| B | FOR SUBMITTAL | 6-6-22 | EL | EL | AK |
| C | FOR SUBMITTAL | 9-15-25 | SM | MM | MM |
| | | | | | |

**RIO GRANDE RESOURCES CORP.**
MOUNT TAYLOR MINE - *San Mateo, NM*

Prepared By: Alan Kuhn Associates LLC

Drawn By: EL Engineering Services LLC

PRINT SIZE: B

SCALE: As Shown


**MT. TAYLOR MINE**
**2022 CLOSEOUT / CLOSURE PLAN**

SHEET TITLE: SHAFT CLOSURE - MANWAY VENT


SHEET NO. **CL 05**

DWG NO. **GS21-CB105-00**

REV **B**




AA'
CL06
SECTION AA' - PLAN VIEW




BB'
CL06
SECTION BB'

## NOTES:

1. EXISTING CONCRETE SLAB TO REMAIN.
2. EXISTING CONCRETE SHAFT COLLAR WALLS TO REMAIN.
3. EXISTING 24' DIAMETER VENT RAISE TO REMAIN AS PART OF SHAFT PLUG STRUCTURE. THE VENT RAISE TO BE BACKFILLED WITH SLURRY FILL.
4. REMOVE AND DROP ALL EQUIPMENT, FITTINGS, AND UTILITIES BETWEEN COLLAR TO SUB COLLAR LEVEL AND CLEAN SUB COLLAR OF ANY DEBRIS.
5. FLOWABLE CEMENTITIOUS BACKFILL - USE TO BACKFILL THE VENT RAISE AND SHAFT FROM PLUG AT THE SUB-COLLAR TO WITHIN 1 FOOT OF THE EXISTING CONCRETE CAP. THEN FILL THE REMAINING VOID WITH LIGHT-WEIGHT CONCRETE.
6. PLUG THE EXISTING SHAFT OPENING WITH LIGHTWEIGHT CONCRETE AND PLACE A SHAFT MARKER IN THE PLUG.
7. PLACE 2' OF CLEAN SOIL OVER THE TOP OF THE CONCRETE SLAB AND REVEGITATE.
8. 8" TO 10" PVC MONITORING PIPE WITH ACCESS CAP AT THE GROUND SURFACE.
9. MRB TECHNICAL SERVICES AND CRITICAL VIEW ENGINEERING ARE PREPARING THE STRUCTURAL DESIGN TO IMPLEMENT THE ACCEPTED 2013 DESIGN CONCEPT FOR THE SHAFT PLUG. (SEE APPENDIX G).

## GENERAL NOTES:

G.1 FOR CONSTRUCTION, PLACEMENT, AND MATERIAL REQUIREMENTS FOR THE FLOWABLE CEMENTITIOUS BACKFILL SEE PROJECT SPECIFICATIONS.

G.2 CONTRACTOR TO DETERMINE MEANS AND METHODS TO SAFELY FABRICATE AND INSTALL THE SHAFT PLUG AND BACKFILL SHOWN ON THIS DRAWING.

G.3 THIS IS THE APPROVED CONCEPTUAL DESIGN. THE FINAL DESIGN WILL GENERALLY FOLLOW THIS CONCEPT BUT MAY VARY IN MATERIALS AND CONSTRUCTION PER THE FINAL DESIGN OF A LICENSED STRUCTURAL ENGINEER (SEE NOTE 9).

| REV | DESCRIPTION | DATE | DRAWN BY | ENGINEER | APPROVED |
|---|---|---|---|---|---|
| A | FOR REVIEW | 12-17-21 | EL | EL | AK |
| B | FOR SUBMITTAL | 5-26-22 | EL | EL | AK |
| | | | | | |
| | | | | | |

**RIO GRANDE RESOURCES CORP.**
MOUNT TAYLOR MINE - *San Mateo, NM*

Prepared By: Alan Kuhn Associates LLC

Drawn By: EL Engineering Services LLC


PRINT SIZE: B

SCALE: As Shown

**MT. TAYLOR MINE**
**2022 CLOSEOUT / CLOSURE PLAN**

SHEET TITLE: SHAFT CLOSURE - PRODUCTION SHAFT

| SHEET NO. | DWG NO. | REV |
|---|---|---|
| CL 06 | GS21-CB106-00 | B |




NOTES:

1. NORTH DIVERSION DITCH WILL BE DESIGNED AFTER SITE RECLAMATION.
2. STONE CHECK DAM. (SEE SHEET CL13).
3. EROSION PROTECTION - GEOGRID WITH STONE FILL. (SEE SHEET CL13)
4. BERM (2' TO 3' HIGH).
5. EXISTING POWER POLES TO REMAIN.
6. EXISTING SECURITY FENCE TO REMAIN.
7. EXISTING MWTU PONDS TO BE BACKFILLED. (SEE SHEET CL 08)
8. LINED PONDS #2 AND #3 TO REMAIN UNTIL ABATEMENT ACTIVITIES ARE COMPLETED THEN THEY WILL BE BACKFILLED.

## GENERAL NOTES:

G.1 SEE SHEET CL07B FOR SERVICE AND SUPPORT GRADING PLAN, SHEET CL08 FOR MWTU POND BACKFILL, AND SHEET CL09 FOR THE WASTE ROCK PILE / DISPOSAL CELL GRADING PLAN.

G.2 FOR CONSTRUCTION, PLACEMENT, AND MATERIAL REQUIREMENTS SEE PROJECT EARTHWORK SPECIFICATIONS.

G.3 THE FINAL DESIGN FOR THE STONE CHECK DAM AND EROSION PROTECTION MEASURES TO BE PREPARED BY A LICENSED CIVIL ENGINEER.

G.4 THE FINAL GRADING PLAN SHOWN ON THIS DRAWING IS FOR INFORMATIONAL PURPOSES ONLY. THE ACTUAL FINAL GRADING WILL DEPEND ON THE SITE CONDITIONS AFTER ALL THE CLEANUP EFFORTS ARE COMPLETE.

| REV | DESCRIPTION | DATE | DRAWN BY | ENGINEER | APPROVED |
|---|---|---|---|---|---|
| A | FOR REVIEW | 12-14-21 | EL | EL | AK |
| B | FOR SUBMITTAL | 5-26-22 | EL | EL | AK |
| C | FOR SUBMITTAL | 9-15-25 | SM | MM | MM |
| | | | | | |

**RIO GRANDE RESOURCES CORP.**
MOUNT TAYLOR MINE - *San Mateo, NM*

Prepared By: Alan Kuhn Associates LLC

Drawn By: EL Engineering Services LLC


PRINT SIZE: B

SCALE: As Shown

**MT. TAYLOR MINE**
**2022 CLOSEOUT / CLOSURE PLAN**

SHEET TITLE: FINAL GRADING PLAN - MINE WATER TREATMENT UNIT

| SHEET NO. | DWG NO. | REV |
|---|---|---|
| CL 07A | GS21-CB107A-00 | B |




NOTES:

1. NORTH DIVERSION CHANNEL.
2. SOUTH DIVERSION CHANNEL.
3. MANWAY SHAFT - SEE SHEET CL05 FOR PLUG AND BACKFILL DETAILS.
4. PRODUCTION SHAFT - SEE SHEET CL06 FOR PLUG AND BACKFILL DETAILS.
5. HOIST HOUSE.
6. SERVICE BUILDING (OFFICE AND WAREHOUSE).
7. ELECTRICAL BUILDING.
8. CAPACITOR BUILDING.
9. GUARD HOUSE (SECURITY BUILDING).
10. SUBSTATION (EARTHWORK IN THIS AREA TO BE LIMITED TO CLEAN UP OF CONTAMINATED SOILS AND FILLING TO RESTORE ORIGINAL GRADES).
11. SEE SHEET CL 07A FOR MWTU GRADING PLAN.
12. SEE APPENDIX K - DISPOSAL CELL DESIGN REPORT.
13. EXISTING POWER POLES TO REMAIN.
14. EXISTING SECURITY FENCE TO REMAIN. IMPROVE OR REPLACE SECTIONS OF THE EXISTING FENCE AS NEEDED.
15. SLOPES GREATER THAN 1H: 1V IN THE SERVICE AND SUPPORT AREA TO BE REDUCED TO NO GREATER THAN 1.5H : 1V.
16. EXISTING STORM DRAINAGE SYSTEM TO REMAIN.

LEGEND

- COUNTY ROADS (NOT RGR'S RESPONSIBILITY)
- SERVICE ROADS
- WATER TANK ACCESS ROAD
- SECURITY GATES
- EXISTING FENCE-LINES TO REMAIN
- EXISTING BUILDINGS TO REMAIN
- ADOBE RUIN
- DIVERSION CHANNELS

GENERAL NOTES:

G.1 FOR CONSTRUCTION, PLACEMENT, AND MATERIAL REQUIREMENTS SEE PROJECT EARTHWORK SPECIFICATIONS.

G.2 THE FINAL GRADING PLAN SHOWN ON THIS DRAWING IS FOR INFORMATIONAL PURPOSES ONLY. THE ACTUAL FINAL GRADING WILL DEPEND ON THE SITE CONDITIONS AFTER ALL THE CLEANUP EFFORTS ARE COMPLETE.

| REV | DESCRIPTION | DATE | DRAWN BY | ENGINEER | APPROVED |
|---|---|---|---|---|---|
| A | FOR REVIEW | 12-14-21 | EL | EL | AK |
| B | FOR SUBMITTAL | 5-26-22 | EL | EL | AK |
| C | FOR SUBMITTAL | 9-15-25 | SM | MM | MM |
| | | | | | |


**RIO GRANDE RESOURCES CORP.**
MOUNT TAYLOR MINE - *San Mateo, NM*

Prepared By: Alan Kuhn Associates LLC
Drawn By: EL Engineering Services LLC
PRINT SIZE: B
SCALE: As Shown

**MT. TAYLOR MINE**
**2022 CLOSEOUT / CLOSURE PLAN**

SHEET TITLE: FINAL GRADING PLAN - SERVICE AND SUPPORT AREA

| SHEET NO. | DWG NO. | REV |
|---|---|---|
| CL 07B | GS21-CB107-00 | B |





B / CL07 SECTION B - MINE WATER TREATMENT POND BEFORE CLOSURE

E/W SECTION THROUGH POND 8 SHOWN AS EXAMPLE

NOTES:

1. CLEAN SOILS
2. APPROXIMATE TOP OF POND WATER AT OPERATIONAL LEVELS.
3. CONTAMINATED SOILS AND POND SEDIMENTS. (REMOVED AND DEPOSITED IN THE DISPOSAL CELL IN 2018 -2021.)
4. CLEAN FILL FROM POND BERMS AND NEARBY GRADING.
5. POND BERMS REMOVED AND USED AS CLEAN FILL IN POND BASINS.
6. CURRENT GRADES AFTER 2018- 2021 CLEANUP EFFORTS.
7. FINAL GRADES. (NOTE: THE GENTLY SLOPING GRADES ARE SIMILAR TO THE PRE-MINE 1974 TOPOGRAPHY. SEE NOTE G.3)




B.1 / CL07 SECTION B.1 - MINE WATER TREATMENT POND AFTER CLOSURE

E/W SECTION THROUGH POND 8 SHOWN AS EXAMPLE

GENERAL NOTES:

G.1 FOR CONSTRUCTION, PLACEMENT, AND MATERIAL REQUIREMENTS SEE PROJECT EARTHWORK SPECIFICATIONS.

G.2 SEE SHEET CL07A FOR MWTU AREA GRADING PLAN.

G.3 THE FINAL GRADES ON THIS SITE MAY NEED TO BE SLIGHTLY LOWER OR HIGHER THAN THE "PRE-MINE" ELEVATIONS DEPENDING ON THE CUT/FILL BALANCE FOR THE SITE.

| REV | DESCRIPTION | DATE | DRAWN BY | ENGINEER | APPROVED |
|---|---|---|---|---|---|
| A | FOR REVIEW | 12-13-21 | EL | EL | AK |
| B | FOR SUBMITTAL | 6-2-22 | EL | EL | AK |
| | | | | | |
| | | | | | |

**RIO GRANDE RESOURCES CORP.**
MOUNT TAYLOR MINE - *San Mateo, NM*

Prepared By: Alan Kuhn Associates LLC

Drawn By: EL Engineering Services LLC

PRINT SIZE: B

SCALE: As Shown


**MT. TAYLOR MINE**
**2022 CLOSEOUT / CLOSURE PLAN**

SHEET TITLE: DETAILS - BACKFILL IN POND AREAS

SHEET NO. **CL 08**

DWG NO. **GS21-CB108-00**

REV **B**




## LEGEND

- COUNTY ROADS
- ELECTRICAL SUBSTATION AND TRANSFORMERS
- MINE SERVICE ROADS
- FENCE-LINES
- EXISTING BUILDINGS TO REMAIN
- SEPTIC SYSTEM
- INTERMITTENT FLOW WITH DIRECTIONAL ARROW
- DIVERSION CHANNELS
- MINE SITE BOUNDARY
- STORM DRAINAGE SYSTEM
- PRE-MINE ADOBE STRUCTURE

## NOTES:

1. WATER TANK
2. SEPTIC SYSTEM
3. SOUTH STORM WATER POND (SSWP)
4. SOUTH STORM WATER POND OVER-FLOW CULVERTS
5. SOUTH DIVERSION CHANNEL- FLOW IN THIS CHANNEL IS ISOLATED FROM THE DISPOSAL CELL DRAINAGE.
6. NORTH DIVERSION CHANNEL
7. ALL DRAINAGE FROM THE WASTE ROCK / DISPOSAL CELL AREA FLOWS INTO THE SOUTH STORM WATER POND.

## GENERAL NOTES:

G.1 OUTFALL #1 DRAINS THE SOUTHERN HALF OF COUNTY ROAD 334 FROM THE MINE ACCESS ROAD TO THE WESTERN FENCE LINE. IT ALSO DRAINS THE NARROW STRIP OF PROPERTY BETWEEN THE SERVICE ROAD THE FENCE LINE ON THE NORTH AND WEST SIDES OF THE SSWP .

G.2 OUTFALL #2 DRAINS THE NORTHERN HALF OF THE COUNTY ROAD 334 RIGHT OF WAY FROM THE NORTH DIVERSION CHANNEL TO THE WESTERN FENCE LINE.

G.3 OUTFALL #3 DRAINS THE AREA FROM THE NORTH DIVERSION CHANNEL TO THE WESTERN FENCE LINE AND FROM THE NORTHERN FENCE ALONG COUNTY ROAD 334 TO THE THE FENCE LINE ALONG THE MARQUEZ ARROYO.

G.4 ALL FLOWS INDICATED ON THIS DRAWING SHOW INTERMITTENT FLOW ONLY. THERE ARE NO PERENNIAL OR INTERMITTENT STREAMS NEAR OR ON THIS SITE.

| REV | DESCRIPTION | DATE | DRAWN BY | ENGINEER | APPROVED |
|---|---|---|---|---|---|
| A | FOR REVIEW | 12-16-21 | EL | EL | AK |
| B | FOR SUBMITTAL | 6-2-22 | EL | EL | AK |
| C | FOR SUBMITTAL | 9-15-25 | SM | MM | MM |
| D | FOR SUBMITTAL | 9-08-26 | MK | MK | MM |

**RIO GRANDE RESOURCES CORP.**
MOUNT TAYLOR MINE - *San Mateo, NM*

Prepared By: Alan Kuhn Associates LLC

Drawn By: EL Engineering Services LLC

PRINT SIZE: B

SCALE: As Shown

**MT. TAYLOR MINE**
**2022 CLOSEOUT / CLOSURE PLAN**

SHEET TITLE: FINAL DRAINAGE PLAN

SHEET NO. **CL 14**

DWG NO. **GS21-CB114-00**

REV **B**

# APPENDIX B

## Hydrologic and Erosion Analysis

B.1 Design Runoff Calculations

B.2 Surface Water Hydrologic Analysis

- Flood Hydrograph (HEC-1) Analysis
- Water Surface Profile (HEC-2) Analysis

# SURFACE WATER RUNOFF HYDROLOGIC ANALYSIS

## GENERAL PARAMETRIC EVALUATION AND MODEL INPUT DATA SELECTION FOR HEC-1 (WATERSHED RUNOFF) AND HEC-2 (FLOOD ROUTING)

**Design Storm Precipitation (Inches) for Various Frequency Intervals and Durations**

| Interval years | Duration in Hours | | | | | |
|---|---|---|---|---|---|---|
| | 1 | 2 | 3 | 6 | 12 | 24 |
| 2 | 0.89 | 1.00 | 1.07 | 1.20 | 1.30 | 1.50 |
| 5 | 1.03 | 1.17 | 1.27 | 1.45 | 1.60 | 1.90 |
| 10 | 1.15 | 1.32 | 1.44 | 1.65 | 1.83 | 2.20 |
| 25 | 1.38 | 1.59 | 1.73 | 2.00 | 2.23 | 2.70 |
| 50 | 1.71 | 1.91 | 2.04 | 2.30 | 2.50 | 2.90 |
| 100 | 1.97 | 2.15 | 2.27 | 2.50 | 2.73 | 3.20 |

** Duration selected must be => time of concentration, Tc

Unit Duration ~= Lg/5.5

Time of Concentration, tc
For watersheds < or = 10 sq. mi.
tc = 0.00013*(L^0.77/S^0.385)
where S = gradient
For watersheds > 10 sq. mi.
tc = 0.385*(11.9*L^3)/H
where H = elevation difference

Curve Number, CN
CN = 71 for P-J uplands (Group D) = 78 for Group B/C soils

Time to Peak Discharge, Tp, hours
Tp = 0.5*dt+Tlag
where dt = duration of excess, or computation interval
Tlag = time between center of rainfall excess and time of peak discharge

Peak flow of unit hydrograph, Qp, cfs/in
Qp = 484*Area*/Tp where Area = subbasin area in sq mi

Average Manning's Coefficient, Kn =
0.26 for uplands, general storm
0.13 for PMF and well-developed drainage courses
0.05 for uplands thunderstorm
0.073 for thunderstorm in well-developed drainage courses
For Southwest region
0.07 for coniferous forest areas
0.042 for desert terrain

# WEATHER DATA FOR THE MT. TAYLOR AREA

from National Weather Service Annual Climatological Summaries
**1986-1995**
Grants Airport (1986-1995) and San Mateo (1986-1987) Stations

## GRANTS AIRPORT

AVERAGE MONTHLY PRECIPITATION, INCHES

| | J | F | M | A | M | J | JL | A | S | O | N | D | Annual |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1986 | 0.00 | 0.55 | 0.32 | 0.47 | 1.29 | 1.94 | 1.75 | 1.53 | 1.10 | 1.55 | 2.25 | 1.35 | 14.10 |
| 1987 | 1.60 | 1.24 | 0.54 | 0.28 | 0.89 | 0.26 | 2.61 | 3.05 | 0.72 | 0.50 | 0.82 | 1.25 | 13.76 |
| 1988 | 0.19 | 0.09 | 0.07 | 1.74 | 0.20 | 1.06 | 1.22 | 2.30 | 1.46 | 0.85 | 0.15 | 0.13 | 9.46 |
| 1989 | 0.77 | 0.45 | 0.16 | 0.00 | 0.08 | 0.10 | 0.98 | 0.90 | 1.64 | 1.07 | 0.05 | 0.11 | 6.31 |
| 1990 | 0.35 | 0.17 | 0.88 | 1.54 | 1.02 | 0.37 | 1.96 | 3.99 | 2.13 | 1.27 | 0.62 | 1.59 | 15.89 |
| 1991 | 0.66 | 0.05 | 1.04 | 0.65 | 0.26 | 0.99 | 1.05 | 1.66 | 1.83 | 0.27 | 1.33 | 1.76 | 11.55 |
| 1992 | 0.72 | 0.27 | 0.93 | 0.67 | 2.68 | 0.46 | 1.68 | 1.86 | 1.23 | 0.90 | 0.90 | 1.26 | 13.56 |
| 1993 | 1.91 | 1.15 | 1.94 | 0.25 | 1.10 | 0.00 | 0.43 | 4.23 | 0.35 | 0.60 | 0.43 | 0.18 | 12.57 |
| 1994 | 0.10 | 0.38 | 0.77 | 0.52 | 2.02 | 0.18 | 0.84 | 1.50 | 1.42 | 1.82 | 1.84 | 0.30 | 11.69 |
| 1995 | 0.49 | 0.30 | 0.38 | 0.09 | 0.29 | 0.49 | 0.45 | 1.92 | 0.86 | 0.00 | 0.30 | 0.37 | 5.94 |
| AVE | 0.68 | 0.47 | 0.70 | 0.62 | 0.98 | 0.59 | 1.30 | 2.29 | 1.27 | 0.88 | 0.87 | 0.83 | 11.48 |

| | FREEZE-FREE DAYS | ANNUAL TEMP., F LOW | HIGH |
|---|---|---|---|
| 1986 | 141 | 0 | 96 |
| 1987 | 132 | -18 | NA |
| 1988 | 120 | -6 | 94 |
| 1989 | 167 | -15 | 101 |
| 1990 | 159 | -33 | 99 |
| 1991 | 154 | -7 | 98 |
| 1992 | 183 | -9 | 99 |
| 1993 | 138 | -4 | 98 |
| 1994 | 140 | -3 | 101 |
| 1995 | 129 | 2 | 102 |
| AVE | **146.3** | **-9.3** | **98.7** |

## SAN MATEO

| | J | F | M | A | M | J | JL | A | S | O | N | D | Annual |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1986 | 0.04 | 0.13 | 0.45 | 0.38 | 0.73 | 0.84 | 3.45 | 1.78 | 1.90 | 1.91 | 3.88 | 0.57 | 16.06 |
| 1987 | 0.92 | 2.81 | 0.84 | 0.14 | 0.78 | 0.73 | 0.39 | 3.97 | 0.23 | 0.72 | 0.54 | 2.00 | 14.07 |
| 1988 | 2.64 | | | | | | | | | | | | *10.22* |
| 1989 | | | | | | | | | | | | | *6.82* |
| 1990 | | | | | | | | | | | | | *17.17* |
| 1991 | | | | | | | | | | | | | *12.48* |
| 1992 | | | | | | | | | | | | | *14.66* |
| 1993 | | | | | | | | | | | | | *13.59* |
| 1994 | | | | | | | | | | | | | *12.63* |
| 1995 | | | | | | | | | | | | | *6.42* |
| AVE | 1.20 | 1.47 | 0.65 | 0.26 | 0.76 | 0.79 | 1.92 | 2.88 | 1.07 | 1.32 | 2.21 | 1.29 | **12.41** |

| | FREEZE-FREE DAYS | ANNUAL TEMP., F LOW | HIGH |
|---|---|---|---|
| 1986 | 155 | 4 | 89 |
| 1987 | 181 | 0 | 89 |
| 1988 | *146* | *5* | *87* |
| 1989 | *204* | *-4* | *94* |
| 1990 | *194* | *-22* | *92* |
| 1991 | *188* | *4* | *91* |
| 1992 | *223* | *2* | *92* |
| 1993 | *168* | *7* | *91* |
| 1994 | *171* | *8* | *94* |
| 1995 | *157* | *13* | *95* |
| AVE | *179* | ***2*** | ***91*** |

CORRECTION FACTORS

| F-F DAYS | LOW | HIGH |
|---|---|---|
| 0.9097 | 4 | -7 |
| 0.7293 | 18 | |
| 0.8195 | 11 | -7 |
| 0.8195 | 11 | -7 |
| 0.8195 | 11 | -7 |
| 0.8195 | 11 | -7 |
| 0.8195 | 11 | -7 |
| 0.8195 | 11 | -7 |
| 0.8195 | 11 | -7 |
| 0.8195 | 11 | -7 |

## RAINFALL PARAMETERS

Design Storm Precipitation (Inches) for Various Frequency Intervals and Durations

| Interval years | Duration in Hours | | | | | |
|---|---|---|---|---|---|---|
| | 1 | 2 | 3 | 6 | 12 | 24 |
| 2 | 0.9 | 1.0 | 1.1 | 1.2 | 1.3 | 1.5 |
| 5 | 1.0 | 1.2 | 1.3 | 1.45 | 1.6 | 1.9 |
| 10 | 1.2 | 1.3 | 1.4 | 1.65 | 1.8 | 2.2 |
| 25 | 1.4 | 1.6 | 1.7 | 2.0 | 2.2 | 2.7 |
| 50 | 1.7 | 1.9 | 2.0 | 2.3 | 2.5 | 2.9 |
| 100 | 2.0 | 2.1 | 2.3 | 2.5 | 2.7 | 3.2 |

** Duration selected must be => time of concentration, Tc

**Fraction of one hour**


depth10 = 0.59 depth15 + 0.41 depth5
depth30 = 0.49 depth60 + 0.51 depth15

| Minutes | Hours | Fraction of 1-Hr Depth inches |
|---|---|---|
| 0 | 0 | 0.00 |
| 5 | 0.08 | 0.60 |
| 10 | 0.17 | 0.75 |
| 15 | 0.25 | 0.85 |
| 30 | 0.50 | 0.93 |
| 45 | 0.75 | 0.97 |
| 60 | 1.00 | 1.00 |


**Triangular Precipitation Distribution for 24 hr/100 yr Event**

| Time Step hours | Cum Precip | Interval Depth | Balanced Storm Hyetograph |
|---|---|---|---|
| 0 | 0 | 0 | 0 |
| 1 | 1.97 | 1.9686 | 0.0300 |
| 2 | 2.15 | 0.1812 | 0.0367 |
| 3 | 2.27 | 0.1212 | 0.0400 |
| 4 | 2.35 | 0.0790 | 0.0400 |
| 5 | 2.42 | 0.0700 | 0.0400 |
| 6 | 2.50 | 0.0800 | 0.0400 |
| 7 | 2.54 | 0.0400 | 0.0400 |
| 8 | 2.58 | 0.0400 | 0.0400 |
| 9 | 2.62 | 0.0400 | 0.0400 |
| 10 | 2.66 | 0.0400 | 0.0700 |
| 11 | 2.69 | 0.0300 | 0.0800 |
| 12 | 2.73 | 0.0433 | 0.1812 |
| 13 | 2.77 | 0.0367 | 1.9686 |
| 14 | 2.81 | 0.0400 | 0.1212 |
| 15 | 2.85 | 0.0400 | 0.0790 |
| 16 | 2.89 | 0.0400 | 0.0433 |
| 17 | 2.93 | 0.0400 | 0.0400 |
| 18 | 2.97 | 0.0400 | 0.0400 |
| 19 | 3.00 | 0.0300 | 0.0400 |
| 20 | 3.04 | 0.0400 | 0.0400 |
| 21 | 3.08 | 0.0400 | 0.0400 |
| 22 | 3.12 | 0.0400 | 0.0400 |
| 23 | 3.16 | 0.0400 | 0.0400 |
| 24 | 3.20 | 0.0400 | 0.0300 |

PRECIPITATION DEPTH VS DURATION
MT TAYLOR MINE WATERSHED



PRECIPITATION VS INTERVAL AND DURATION
MT TAYLOR MINE WATERSHED




9431HYD.XLS

## SURFACE WATER RUNOFF HYDROLOGIC ANALYSIS - MT. TAYLOR MINE
## WATERSHED PARAMETERS

A73.K145

| PARAMETERS | Marquez/ Maruca Basin | | | | Hummer Basin | | |
|---|---|---|---|---|---|---|---|
| | Total Basin | Marquez Canyon above junction | Maruca Canyon | Lower Marquez Canyon | Total Basin | East Hummer | West Hummer |
| L, length of longest watercourse, ft = | 32312 | 26805 | 26214 | 7000 | 10481 | 9513 | 5644 |
| Maximum elevation | 9250 | 9250 | 9380 | 7928 | 8300 | 8300 | 7810 |
| Minimum elevation | 7260 | 7450 | 7450 | 7450 | 7315 | 7350 | 7315 |
| H, difference in elevation | 1990 | 1800 | 1930 | 478 | 985 | 950 | 495 |
| S, slope gradient = | 0.062 | 0.067 | 0.074 | 0.068 | 0.094 | 0.100 | 0.088 |
| in ft/mi = | 325 | 355 | 389 | 361 | 496 | 527 | 463 |
| Time of Concentration, tc, hrs (watersheds < 10 sq. mi.) = 0.00013*(L^0.77/S^0.385) = | 1.13 | 0.94 | 0.90 | 0.33 | 0.40 | 0.37 | 0.26 |
| Area, sq. mi. | 5.02 | 2.76 | 1.63 | 0.63 | 0.54 | 0.4 | 0.14 |
| Lag Time, Lg, hrs | | | | | | | |
| USBR method, Lg = C*(L*Lc/S^.5)^N = | 1.58 | 1.38 | 1.34 | 0.57 | 0.70 | 0.65 | 0.47 |
| Constant, C = 26*Kn = | 1.56 | 1.56 | 1.56 | 1.56 | 1.56 | 1.56 | 1.56 |
| Constant, N = | 0.33 | 0.33 | 0.33 | 0.33 | 0.33 | 0.33 | 0.33 |
| Length of Longest Watercourse, L, mi = | 6.12 | 5.08 | 4.96 | 1.33 | 1.99 | 1.80 | 1.07 |
| Length Along L to Point Opposite Watershed Centroid, Lc, mi = | 3.06 | 2.54 | 2.48 | 0.66 | 0.99 | 0.90 | 0.53 |
| Overall Slope of L, S, ft/mi = | 325 | 355 | 389 | 361 | 496 | 527 | 463 |
| Average Manning's Coefficient, Kn = 0.06 average based on: For Southwest region 0.07 for coniferous forest 0.042 for desert terrain | 0.06 | 0.06 | 0.06 | 0.06 | 0.06 | 0.06 | 0.06 |
| SCS Method, Lg = 0.6 Tc | 0.68 | 0.57 | 0.54 | 0.20 | 0.24 | 0.22 | 0.15 |
| Unit Duration, dt, hours ~= Lg/5.5 | 0.12 | 0.10 | 0.10 | 0.04 | 0.04 | 0.04 | 0.03 |
| rounded to | 0.1 | 0.1 | 0.1 | 0.04 | 0.04 | 0.04 | 0.03 |
| Time to Peak Discharge, Tp, hours | | | | | | | |
| Tp = 0.5*dt+Lg | 0.73 | 0.62 | 0.59 | 0.22 | 0.26 | 0.24 | 0.17 |
| Peak flow of unit hydrograph, Qp, cfs/in | | | | | | | |
| Qp = 484*Area*/Tp | 3344 | 2166 | 1342 | 1384 | 999 | 810 | 401 |
| Vol. = volume of runoff, cfs-day from 1 inch rainfall | 134.99 | 74.22 | 43.83 | 16.94 | 14.52 | 10.76 | 3.76 |
| Curve Number, CN | | | | | | | |
| CN = 71 for P-J upland (Group D) = 78 for Group B/C soils | | | | | | | |

# Temporal Distribution - Dimensionless Unit Hydrograph

m1.u71


| ** % of (Lg+D/2) | ** q | q*(Lg+D/2)/V | differential q*(Lg+D/2)/Vol. | Time hours | % of (Lg+D/2) | Ordinate | Unit q cfs |
|---|---|---|---|---|---|---|---|
| 5 | 0.19 | 0.0016 | | 0.25 | 40.5 | 0.032 | 3.86 |
| 10 | 0.32 | 0.0027 | 0.0011 | 0.50 | 81.1 | 0.239 | 28.73 |
| 15 | 0.48 | 0.0040 | 0.0013 | 0.75 | 121.6 | 0.101 | 12.11 |
| 20 | 0.74 | 0.0061 | 0.0022 | 1.00 | 162.1 | 0.129 | 15.49 |
| 25 | 1.21 | 0.0101 | 0.0039 | 1.25 | 202.7 | 0.220 | 26.46 |
| 30 | 1.81 | 0.0150 | 0.0050 | 1.50 | 243.2 | 0.225 | 27.06 |
| 35 | 2.63 | 0.0219 | 0.0068 | 1.75 | 283.7 | 0.167 | 20.13 |
| 40 | 3.68 | 0.0306 | 0.0087 | 2.00 | 324.3 | 0.112 | 13.46 |
| 45 | 5.47 | 0.0455 | 0.0149 | 2.25 | 364.8 | 0.080 | 9.61 |
| 50 | 8.41 | 0.0699 | 0.0244 | 2.50 | 405.3 | 0.060 | 7.16 |
| 55 | 12.61 | 0.1048 | 0.0349 | 2.75 | 445.9 | 0.048 | 5.74 |
| 60 | 16.5 | 0.1371 | 0.0323 | 3.00 | 486.4 | 0.040 | 4.79 |
| 65 | 20.5 | 0.1704 | 0.0332 | 3.25 | 526.9 | 0.034 | 4.07 |
| 70 | 23.97 | 0.1992 | 0.0288 | 3.50 | 567.5 | 0.029 | 3.46 |
| 75 | 27.75 | 0.2306 | 0.0314 | 3.75 | 608.0 | 0.024 | 2.93 |
| 80 | 28.91 | 0.2403 | 0.0096 | 4.00 | 648.5 | 0.021 | 2.48 |
| 85 | 28.07 | 0.2333 | -0.0070 | 4.25 | 689.1 | 0.018 | 2.12 |
| 90 | 26.38 | 0.2192 | -0.0140 | 4.50 | 729.6 | 0.015 | 1.80 |
| 95 | 24.18 | 0.2009 | -0.0183 | 4.75 | 770.1 | 0.013 | 1.52 |
| 100 | 21.55 | 0.1791 | -0.0219 | 5.00 | 810.7 | 0.011 | 1.31 |
| 105 | 18.92 | 0.1572 | -0.0219 | 5.25 | 851.2 | 0.009 | 1.11 |
| 110 | 16.08 | 0.1336 | -0.0236 | 5.50 | 891.7 | 0.008 | 0.94 |
| 115 | 14.19 | 0.1179 | -0.0157 | 5.75 | 932.3 | 0.007 | 0.80 |
| 120 | 12.61 | 0.1048 | -0.0131 | 6.00 | 972.8 | 0.006 | 0.68 |
| 125 | 11.04 | 0.0917 | -0.0130 | 6.25 | 1013.3 | 0.005 | 0.58 |
| 130 | 9.99 | 0.0830 | -0.0087 | 6.50 | 1053.9 | 0.004 | 0.49 |
| 135 | 9.04 | 0.0751 | -0.0079 | 6.75 | 1094.4 | 0.003 | 0.42 |
| 140 | 8.2 | 0.0681 | -0.0070 | 7.00 | 1135.0 | 0.003 | 0.36 |
| 145 | 7.36 | 0.0612 | -0.0070 | 7.25 | 1175.5 | 0.002 | 0.30 |
| 150 | 6.78 | 0.0563 | -0.0048 | | | | |
| 155 | 6.2 | 0.0515 | -0.0048 | | | | |
| 160 | 5.83 | 0.0484 | -0.0031 | | | | |
| 165 | 5.47 | 0.0455 | -0.0030 | | | | |
| 170 | 5.15 | 0.0428 | -0.0027 | | | | |
| 175 | 4.84 | 0.0402 | -0.0026 | | | | |
| 180 | 4.57 | 0.0380 | -0.0022 | | | | |
| 185 | 4.31 | 0.0358 | -0.0022 | | | | |
| 190 | 4.1 | 0.0341 | -0.0017 | | | | |
| 195 | 3.87 | 0.0322 | -0.0019 | | | | |
| 200 | 3.68 | 0.0306 | -0.0016 | | | | |
| 205 | 3.47 | 0.0288 | -0.0017 | | | | |
| 210 | 3.28 | 0.0273 | -0.0016 | | | | |
| 215 | 3.1 | 0.0258 | -0.0015 | | | | |
| 220 | 2.93 | 0.0243 | -0.0014 | | | | |
| 225 | 2.75 | 0.0229 | -0.0015 | | | | |
| 230 | 2.63 | 0.0219 | -0.0010 | | | | |
| 235 | 2.47 | 0.0205 | -0.0013 | | | | |
| 240 | 2.33 | 0.0194 | -0.0012 | | | | |
| 245 | 2.22 | 0.0184 | -0.0009 | | | | |
| 250 | 2.1 | 0.0175 | -0.0010 | | | | |
| 255 | 1.99 | 0.0165 | -0.0009 | | | | |
| 260 | 1.88 | 0.0156 | -0.0009 | | | | |
| 265 | 1.78 | 0.0148 | -0.0008 | | | | |
| 270 | 1.68 | 0.0140 | -0.0008 | | | | |
| 275 | 1.59 | 0.0132 | -0.0007 | | | | |
| 280 | 1.5 | 0.0125 | -0.0007 | | | | |
| 285 | 1.43 | 0.0119 | -0.0006 | | | | |
| 290 | 1.36 | 0.0113 | -0.0006 | | | | |
| 295 | 1.28 | 0.0106 | -0.0007 | | | | |
| 300 | 1.21 | 0.0101 | -0.0006 | | | | |
| 305 | 1.15 | 0.0096 | -0.0005 | | | | |

| | | | |
|---|---|---|---|
| Lg = | 0.57 | 0.54 | 0.20 |
| D = | 0.1 | 0.1 | 0.04 |
| Lg+D/2 = | 0.62 | 0.59 | 0.22 |
| Vol. = | 74.22 | 43.83 | 16.94 |


** from Table 3-13, USBR 1987

# BALANCED STORM HYETOGRAPH – 24 HR/100YR

MT TAYLOR MINE WATERSHED




DIMENSIONLESS UNIT HYDROGRAPH FOR MARQUEZ WATERSHED
MT TAYLOR MINE




# UNIT HYDROGRAPH AT SITE WEST BOUNDARY

MT. TAYLOR MINE – MARQUEZ CANYON WATERSHED



24 HR/100YR RAINFALL DISTRIBUTION
MT TAYLOR MINE - MARQUEZ CANYON WATERSHED



HEC1 S/N: 1343001323 HMVersion: 6.33 Data File: MARQEZ.HC1

```
*****************************************
*                                       *
*    FLOOO HYDROGRAPH PACKAGE  (HEC·1)  *
*              MAY  1991                *
*           VERSION 4.0.1E              *
*                                       *
*  RUN DATE 09/06/1996 TIME  10:53:37   *
*                                       *
*****************************************
```

```
*****************************************
*                                       *
*    U.S. ARMY CORPS OF ENGINEERS       *
*    HYDROLOGIC ENGINEERING CENTER      *
*          609 SECOND STREET            *
*       DAVIS CALIFORNIA 95616          *
*         (y16) 756-1104                *
*                                       *
*****************************************
```

```
X    X XXXXXXX  XXXXX         X
X    X  X       X    X       XX
 X  X   X       X       XXXXX  X
  XX    XXXXX   X              X
 X  X   X       X              X
X    X  X       X    X         X
X    X  XXXXXXX  XXXXX        XXX
```

Full Microcomputer lrrplementation
by
Haestad Methods, Inc.

37 Brookside Road* Waterbury, Connecticut 06708 * (203) 755-1666

THIS PROGRAM REPLACES ALL PREVIOUS VERSIONS OF HEC-1 KNOWN AS HEC1 (JAN 73}, HEC1GS, HEC1DB, AND HEC1KW.

THE DEFINITIONS OF VARIABLES -RTIMP· AND -RTIOR- HAVE CHANGED FROM THOSE USED WITH THE 1973-STYLE INPUT STRUCTURE.
THE DEFINITION OF -AMSKK· ON RM-CARD WAS CHANGED WITH REVISIONS DATED 28 SEP 81. THIS JS THE FORTRAN?? VERSION
NEU OPTIONS: DAMBREAK OUTFLOW SUBMERGENCE , SINGLE EVENT DAMAGE CALCULATION, DSS;WRJTE STAGE FREQUENCY,
DSS:READ TIME SERIES AT DESIRED CALCULATION INTERVAL LOSS RATE:GREEN AND AMPT INFILTRATION
KINEMATIC WAVE: NEW FINITE DIFFERENCE ALGORITHM

```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10
    1     ID  PRECIP DEPTH, AREA SIMULATION FOR MARQUEZ CANYON WATERSHED - MT. TAYLOR HINE
    2     ID  100 YEAR, 24 HOUR STORM EVENT
    3     IT      15        0        0       96
    4     IO       1
    5     JO     3.2      5.02
    6     PIT                      1.2     1.70    Z.00     2.1      2.3     2.5     2.7     3.2
    7     KK       10 RUNOFF FROM UPPER MARQUEZ CANYOM TO MARUCA JUNCTION
    8     KO        0
    9     SA    2.76         0
   10     BF       0         0        1
   11     LS       0        71        0
   12     UD      .57
   13     KK     1040 ROUTE MARQUEZ RUNOFF TO JUNCTION
   14     RO    26805    .067     .06            TRAP     4.5      1.9
   15     1(1(     20  RUNOFF FROM MARUCA CANYON
   16     1(0       0
   17     BA    t.63         0
   18     BF       0         0        1
   19     LS       0        71        0
   20     U0     .54
   21           2040  ROUTE MARUCA RUNOFF TO JUNCTION
   22     1(1(  _2 6-2-1-4   .074      .06            TRAP     4.5      1.9
   23     KK       30 RUNOFF FROM LOWER MARQUEZ CANYON
   24     BA     .63         0
   25     BF       O         O        1
   26     LS       O        78        0
   27     UO     .20
   28     KK       40 COMBINE 10  20,30 RUNOFF
   29     KM    COMBINE RUNOFF FROM UPPER MARQUEZ AND MARUCA CANYONS AND LOWER MARQUEZ
   30     KC       3         0
   31     KO       0
   32     KK    4050 ROUTE COMBINED 10,20, ANO 30 RUNOFF TO WEST SIDE OF  !NE PROPERTY
   33     RO    5507    ,068     .06            TRAP     4.5      1.9
   34     Z
```

C1 S/N: 1343001323 HMVersion: 6.33 Data File: MARQEZ.HC1

RUNOFF SUMMARY
FLOW IN CUBIC FEET PER SECOND
TIME IN HOURS, AREA IN SQUARE MILES

| OPERATION | STATION | PEAK FLOW | TIME OF PEAk | AVERAGE FLOW FOR MAXIMUM PERIOD 6-HOJR | 24-HOUR | 72-HOUR | BASIN AREA | MAXIMUM STAGE | TIME OF MAX STAGE |
|---|---|---|---|---|---|---|---|---|---|
| !\YDROGRAPH AT | 10 | 990. | 12.50 | 213. | 65. | 65. | 2.76 | | |
| ROUTED TO | 1040 | 929. | 13.00 | 210. | 63. | 63. | 2.76 | | |
| HYDROGRAPH AT | 20 | 604. | 12.50 | 126. | 38. | 38. | 1.63 | | |
| ROOTED TO | 2040 | 593. | 13.00 | 131. | 39. | 39. | 1.63 | | |
| HYDROGRAPH AT | 30 | 625. | 12.00 | 73. | 22. | 22. | 0.63 | | |
| 3 COMBINED AT | 40 | 1579. | 13.00 | 407. | 123. | 123. | 5.02 | | |
| ROUTED TO | 4050 | 1502. | 13.00 | 406. | 123. | 123. | 5.02 | | |

100 YEAR- 24 HOUR EVENT

**SUMMARY** PRINTOUT TABLE 150

| | SECNO | XLCH | ELTRD | ELLC | ELMIN | Q | CWSEL | CRIWS | EG | 10*KS | VCH | AREA | .01K |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| • | 3.000 | 0.00 | 0.00 | 0.00 | 318.50 | 361.00 | 320.18 | 320.18 | 320.73 | 232.10 | 5.94 | 60.75 | 23.70 |
| | 2.000 | 800.00 | 0.00 | 0.00 | 331.75 | 361.00 | 333.96 | 333.73 | 334.43 | 135.64 | 5.51 | 65.48 | 31.00 |
| | 1.000 | 900.00 | 0.00 | 0.00 | 344.00 | 361.00 | 346.37 | 346.15 | 346.94 | 141.74 | 6.10 | 59.21 | 30.32 |

100 YEAR- 24 HOUR EVENT

SUMMARY PRINTOUT TABLE 150

| | SECNO | Q | CWSEL | DIFWSP | DIFWSX | DIFKWS | TOPWID | XLCH |
|---|---|---|---|---|---|---|---|---|
| * | 3.000 | 361.00 | 320.18 | 0.00 | 0.00 | 0.00 | 56.32 | 0.00 |
| | 2.000 | 361.00 | 333.96 | 0.00 | 13.78 | 0.00 | 45.22 | 800.00 |
| | 1.000 | 361.00 | 346.37 | 0.00 | 12.41 | 0.00 | 36.07 | 900.00 |

HEC-2 WATER SURFACE PROFILES
Version 4.6.2; May 1991
JN DATE 6SEP96 TIME 10:59:50

U.S. ARMY CORPS OF ENGINEERS
HYDROLOGIC ENGINEERING CENTER
609 SECOND STREET, SUITED
DAVIS, CALIFORNIA 95616-4687
(916) 756-1104

FULL MICRO-COMPUTER IMPLEMENTATION

H A E S T AD ME TH O DS

37 Brookside Road * Waterbury, Connecticut 06708 * (203) 755-1666



THIS RUN EXECUTED 6SEP96 10:59:50

'E'G'2''A'T'E'R''S'U'R'F'A'C'E''P'R'O'F'I L E S

**WATER** PROFfIE ANALYSES FOR MARQUEZ CANYON ARROYO ACROSS MINE SITE
!MT. 1AYLOR MINE, WITHOUT CHANNEL IMPROVEMENTS
: 100 YEAR· 24 HOUR EVENT

| !CHECK | **INQ** | **NlNV** | **IDIR** | STRT | **METRIC** | **HVINS** | Q | **WSEL** | FQ |
|---|---|---|---|---|---|---|---|---|---|
| | 0 | 0 | 0 | -1 | 0 | 0 | 1579 | | 0 |

| **NPROf** | !PLOT | PRFVS | XSECV | XSECH | **FN** | ALLOC | **IBW** | CKNIM | **ITRACf.** |
|---|---|---|---|---|---|---|---|---|---|
| -1 | **1** | 0 | 0 | 0 | 0 | -1 | 0 | 0 | |

**VARIABLE** CODES **FOR SUMMARY** PRINTOUT

150

**LPRNT** **NUMSEC** ***·****REQUESTED SECTION NUMBERS********

-1 -10


IHLEO !COPY SUBOJV STRTOS RMILE

0 0 0

| | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| C | .03 | .03 | _040 | ·, | .3 | | | | | |
| 1 | 3 | 8 | 10 | 50 | 0 | 0 | 0 | 0 | 0 | 1 |
| **R** | 270 | 0 | 265 | 10 | 260 | 19 | 257 | 22 | 257 | 28 |
| **R** | 260 | 35 | 265 | 50 | 267 | 68 | | | | |
| | 2 | 11 | 40 | 108 | 1200 | 1200 | 1200 | 0 | 0 | 1 |
| | 305 | 0 | 300 | 40 | 285 | 50 | 280 | 62 | 277 | 67 |
| **R** | 276 | 77 | 277 | 87 | 280 | 90 | 285 | 92 | 300 | 108 |
| **R** | 305 | 118 | | | | | | | | |
| 1 | | 9 | 29 | 80 | 350 | 350 | 350 | 0 | 0 | 1 |
| **R** | 320 | 29 | 310 | 37 | 300 | 40 | 290 | 49 | 289 | 51 |
| **R** | 290 | 53 | 300 | 68 | 310 | 77 | 320 | 80 | | |

CROSS SECTION 1.00
**STREAM** 100 YEAR- 24 HOUR EVENT
DISCHARGE"' 1579_

PLOTTED POINTS (BY PRIORITY)-B"'BOTTOM BR!DGE,T,,,TOP BRIDGE,X=GROUND,W=WATER SUR,E=ENERGY GRADIENT,C=CRITICAL WSEL




CROSS SECTION 2.00
STREAM 100 YEAR- 24 HOUR EVENT
DISCHARGE= 1579.

PLOTTED POINTS (BY PRIORITY)-B=BOTTOM BRIDGE,T=TOP BRIDGE,X=GROUND,IJ=IJATER SUR,E=ENERGY GRADIENT,C=CRITICAL IJSEL

E. 276.0 281.0 286.0 291.0 296.0 301.0 306.0 311.0 316.0 321.0 326.0

STA-FEET




CROSS SECTION 3.00
STREAM 100 YEAR· 24 HOUR EVENT
DISCHARGE= 1579.

P. ED POINTS (BY PRIORITY)·B=BOTTOM BRIDGE,T=TOP BRIDGE,X=GROUND,IJ=\JATER SUR,E=ENERGY GRADIENT,C=CRITICAL IJSEL

ELEV 257.0 259.0 261.0 263.0 265.0 267.0 269.0 271.0 273.0 275.0 277.0

STA-FEET



100 YEAR· 24 HOUR EVENT

SUMMARY PRINTOUT TABLE 150

| | SECNO | XLCH | ELTRD | ELLC | ELMIN | Q | CWSEL | CRIWS | EG | 10*KS | VCH | AREA | .01K |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| • | 3.000 | 0.00 | 0.00 | 0.00 | 257.00 | 1579.00 | 264.15 | 264.15 | 266.10 | 168.24 | 11.23 | 140.58 | 121.74 |
| | 2.000 | 1200.00 | 0.00 | 0.00 | 276.00 | 1579.00 | 282.16 | 281.77 | 283.90 | 132.33 | 10.60 | 148.91 | 137.26 |
| * | 1.000 | 350.00 | 0.00 | 0.00 | 289.00 | 1579.00 | 298.49 | 298.49 | 301.07 | 194.22 | 12.89 | 122.54 | 113.30 |

100 YEAR· 24 HOUR EVENT

SUMMARY PRINTOUT TABLE 150

| | SECNO | Q | CWSEL | DIFWSP | DIFWSX | DIFKWS | TOPWID | XLCH |
|---|---|---|---|---|---|---|---|---|
| • | 3.000 | 1579.00 | 264.15 | 0.00 | 0.00 | 0.00 | 35.90 | 0.00 |
| | 2.000 | 1579.00 | 282.16 | 0.00 | 18.01 | 0.00 | 34.04 | 1200.00 |
| * | 1.000 | 1579.00 | 298.49 | 0.00 | 16.34 | 0.00 | 24.38 | 350.00 |

HEC1 S/N: 1343001323 HMVersion: 6.33 Data File: hu1Trller.hc1

```
*****************************************
*                                       *
*  FLOOD HYOROGRAPH PACKAGE (HEC·l)     *
*               MAY  1991               *
*            VERSION 4.0.1E             *
*                                       *
*  RUN DATE 09/06/1996  TIME  15:18:49  *
*                                       *
*****************************************
```

```
*****************************************
*                                       *
*     U.S. ARMY CORPS OF ENGINEERS      *
*     HYDROLOGIC ENGINEERING CENTER     *
*          609 SECOND STREET            *
*        DAVIS CALIFORNIA 95616         *
*           (Y16) 756-1104              *
*                                       *
*****************************************
```

```
x     x  xxxxxxx  xxxxx          x
x     x  x       x     x        xx
x     x  x       x              x
xxxxxxx  xxxx    x       xxxxx  x
x     x  x       x              x
x     x  x       x     x        x
x     x  xxxxxxx  xxxxx          xxx
```

Full Microcomputer Implementation
by
Haestad Methods, Inc.

37 Brookside Road* Waterbury, Connectlcut 06708 * (203) 755-1666

THIS PROGRAM REPLACES ALL PREVIOUS VERSIONS OF HEC-1 KNOWN AS HEC1 (JAN 73), HEC1GS, HEC1DB, AND HEC1KW.

THE DEFINITIONS OF VARIABLES -RTIMP· AND ·RTIOR· HAVE CHANGED FROM THOSE USED WITH THE 1973-STYLE INPUT STRUCTURE.
THE DEFINITION *OF* -AMSKK· ON RM-CARD WAS CHANGED WITH REVISIONS DATED 28 SEP 81. THIS IS THE FORTRAN77 VERSION
NEW OPTIONS: DAMBREAK OUTFLOW SUBMERGENCE , SINGLE EVENT DAMAGE CALCULATION, DSS:WRITE STAGE FREQUENCY,
DSS:REAO TIME SERIES AT DESIRED CALCULATION INTERVAL LOSS RATE:GREEN AND AMPT INFILTRATION
KINEMATIC WAVE: **NEW** FINITE DIFFERENCE ALGORITHM

```
LINE      10 .....1....2....3....4....5....6.....7....8....9....10
   1      ID  PRECIP DEPTH- AREA SIMULATION FOR HUMMER WATERSHED - MT. TAYLOR MINE
   2      ID  100 YEAR, 24 HOUR STORM EVENT
   3      IT     15       0       0      96
   4      10      1
   5      JD    3.2     .54
   6      PH                    1.2     1.70    2.00     2.1     2.3     2.5     2.7     3.2
   7      1(1(    10 RUNOFF FRa-1 EAST HUMMER
   8      KO       0
   9      BA     .40       0
          BF       0       0       1
  10      LS       0      71       0
  11      UD     .22
  12
  13      KI(   1030  ROUTE EAST HUMKER RUNOFF TO JUNCTION 30
  14      RD    9513   0.10    •06          TRAP     14     4.0
  15      KK      20  RUNOFF FROM WEST HUMMER
  16      J(Q      0
  17      BA     .14       0
  18      Bf       0       0       1
  19      LS       0      71       0
  20      LIO   0.15
  21      KK    2030  ROUTE WEST HUMMER RUNOFF TO JUNCTION 30
  22      RD    5644   0.088     .06          TRAP     14     4.0
  23      KK      30 COMBINE 10 AND 20 RUNOFF
  24      KM    COMBINE RUNOFF FROM EAST AND WEST HUMMER
  25      HC       2       0
  26      1(0      0
  27      KK    3040 ROUTE COMBINED 10 AND 20 RUNOFF TO WEST SIDE OF MINE PROPERTY
  28      RO     968    .036    .03          TRAP     14      4
  29      ZZ
```

r1 S/N: 1343001323 IIMVersion: 6.33 Date File: hU11111er_nc1

RUMOFF SUMMARY

FLOW IN CUBIC FEET PER SECOND
TIME IN HOURS, AREA IN SQUARE MILES

| OPERATION | STATION | PEAK FLOW | TIME OF PEAK | AVERAGE FLO\J FOR MAXIMUM PERIOD 6·1!0UR | 24-HOUR | 72-HOUR | BASIN AREA | MAXIMUM STAGE | TIME OF MAX STAGE |
|---|---|---|---|---|---|---|---|---|---|
| HYDROGRAPH AT | 10 | 226. | 12.00 | 31. | 9. | 9. | 0.40 | | |
| ROUTED TO | 1030 | 254. | 12.25 | 35. | 10. | to. | 0.40 | | |
| HYDROGRAPH AT | 20 | 118. | 12.00 | 11. | 3. | 3. | 0.14 | | |
| ROUTED TO | 2030 | 107. | 12.25 | 11. | 3. | 3. | 0.14 | | |
| 2 COMBINED AT | 30 | 361. | 12.25 | 46. | 14. | 14. | 0.54 | | |
| ROUTED TO | 3040 | 334. | 12.25 | 46. | 14. | 14. | 0.54 | | |

HEC-2 ATER SURFACE PROFILES
rsion 4.6.2; May 1991
DATE 6SEP96 TINE 16:05:18

U.S. ARMY CORPS OF ENGINEERS
HYDROLOGJC ENGINEERING CENTER
609 SECOND STREET, SUITED
DAVIS, CALIFORNIA 95616-4687
(916) 756·1104

FULL MICRO•CCf,tPUTER IMPLEMENTATION

H A E S T A D M E T H O O S

37 Brookside Road * Uaterbury, Connecticut 06708 * (203) 755·1666



THIS RUN EXECUTED 6SEP96 16:05:18

lEC·2 UATER SURFACE PROFILES

WATER PROFILE ANALYSES FOR HUMMER WATERSHED WITHOUT IMPROVEMENTS
'.MT. TAYLOR MINE
100 YEAR· 24 HOUR EVENT

| !CHECK | INQ | NIIIV | !DIR | | METRIC | HVINS | Q | USEL | FQ |
|---|---|---|---|---|---|---|---|---|---|
| | 0 | 0 | 0 | ST R T | 0 | 0 | 361 | | 0 |

| NPROf | !PLOT | PRFVS | XSECV | XSECH | HI | ALLDC | IBW | CHNlM | lTRACE |
|---|---|---|---|---|---|---|---|---|---|
| -1 | | 0 | 0 | 0 | 0 | -1 | 0 | 0 | |

VARIABLE COOES FOR **SUMMARY** PRINTOUT

150


LPRNT NU1'1SEC ********REQUESTED SECTION NUMBERS********
-1 -10

| !HLEQ | !COPY | SUBDTV | STRTDS | RMILE |
|---|---|---|---|---|
| | | 0 | 0 | 0 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| .03 | .03 | .040 | .1 | .3 | | | 0 | 0 | 1 |
| 3 | 7 | 110 | 186 | | | | | | |
| 325 | 0 | 321 | 80 | 321 | 110 | 318.5 | 142 | 318.5 | 158 |
| 321 | 186 | 323.7 | 280 | | | | | | |
| 2 | 7 | **85** | **159** | 820 | 790 | 800 | 0 | 0 | 1 |
| 340 | 0 | 336 | 60 | **336** | 85 | 331.75 | 115 | 331.75 | 129 |
| 336 | 159 | **338.2** | **280** | | | | | | |
| 1 | 7 | 60 | 130 | 900 | 900 | 900 | 0 | 0 | 1 |
| 350 | 0 | 352 | 30 | **350** | 60 | 344 | 93 | 344 | 107 |
| 350 | 130 | 360 | 180 | | | | | | |

CROSS SECTION 1.00
STREAM 100 YEAR· 24 HOUR EVENT
OISCHARGE= 361.

PLOTTED POINTS (BY PRIORITY)·B=BOTTOM BRIDGE,T=TOP BRIDGE,X=GROUND,W=WATER SUR,E=ENERGY GRADIENT,C=CRITICAL WSEL




CROSS SECTION 2.00
STREAM 100 YEAR· 24 HOUR EVENT
DISCHARGE= 361.

PLOTTED POINTS(BY PRIORITY)·B=BOTTOM BRIDGE,T=TOP BRIDGE,X=GROUND,U=UATER SUR,E=ENERGY GRADIENT,C=CRITICAL USEL

331.8 332.8 333.8 334.8 335.8 336.8 337.8 338.8 339.8 340.8 341.8

STA-FEET




CROSS SECTION 3.00
STREAM 100 YEAR- 24 HOUR EVENT
DISCHARGE= 361.

'ED POINTS (BY PRIORITY)-B=BOTTOM BRJDGE,T=TOP BRIDGE,X=GROUND,W=WATER SUR,E=ENERGY GRADIENT,C=CRITICAL WSEL

ELEV 318.5 319.5 320.5 321.5 322.5 323.5 324.5 325.5 326.5 327.5 328.5

STA·FEET



# APPENDIX C

## Technical Specifications

C.2 Buildings and Pipeline Demolition

C.3 Shaft Backfill and Plugging

C.4 Earthwork

# C.2 BUILDINGS AND PIPELINE DEMOLITION

## GENERAL TECHNICAL REQUIREMENTS

### Summary of Work

Rio Grande Resources Corporation (RGR) is owner and operator of the Mt. Taylor Uranium Mine located in Cibola County, New Mexico in Section 24, T13N, R8W, NMPM. The mine site is 1/2-mile northeast of the Village of San Mateo and is accessible from New Mexico State Route 605. At the time of this submittal, the mine is on active (operating) status, but RGR has initiated closeout due to the depressed uranium market.

The mine extracted uranium ore from depths of over 3,000 feet below ground surface that connect to two 3,300-foot-deep shafts from the mine surface. The mine surface facilities are located on 285.6 acres, of which approximately 175 acres are disturbed land, and the remaining acres are undisturbed.

The disturbed land consists of:

- Support (Service and Support) Facilities
- Mine Water Treatment Area
- Treated Water Discharge Pipeline Easement
- Ore Stockpile
- Waste Pile
- Storm Water Retention Ponds (2)
- Access Road

The included work consists of demolition of buildings that will have no post-mining use, excavation of contaminated soils, well plug and abandonment, shaft and conduit closure, and disposal cell construction. Some of the mine buildings, the treated water discharge pipeline, the headframe, and other facilities have already been removed. Buildings and facilities that have post-mining use will not be removed. Facilities remaining to be removed are listed in Table 4-2. Closeout activities for the production shaft and the manway shaft are addressed in Appendix C.3.

Scrap materials from demolition (with the exception of concrete) that are not radiologically contaminated and meet the criteria for unrestricted use will be disposed of as scrap or made available for off-site sale. The surface landowner shall have the right to retain any uncontaminated demolition materials, other than concrete, for its own use, including but not limited to on-site use for post-mining applications or for off-site sale. Any demolition materials not retained on site at the written request of the surface landowner prior to demolition shall be removed by the contractor and may be used or sold by the contractor without compensation to RGR or the surface landowner. Subsequent to closeout, removal of remaining salvaged materials from the site will be at the landowner's discretion and cost.

The required work includes:

- Mobilization and demobilization of contractor's equipment
- Preparation of the work area
- Protection of potentially impacted facilities and structures
- De-energizing and removal of electric lines and equipment in facilities to be removed
- Demolition of the buildings listed in Table 4-2
- Separation and stacking of demolition debris at locations on site approved by NMED as staging areas.

Any demolition materials (other than concrete) meeting release criteria may be salvaged for sale and re-used offsite by the contractor. Workplans with drawing sheets will be prepared as each task is initiated.

**Site Survey**

Prior to mobilizing to the mine site, the Contractor shall perform its own survey of the facilities to be removed for the purposes of dimensional and volume measurements, assessment of hazards, and planning the work. The results of this site survey shall be submitted to the Project Manager for review and approval before the work begins.

**Site Restrictions**

Access to the site is limited to ingress/ egress through the main gate. All Contractor personnel and visitors shall log in and out at the guardhouse. All personnel shall wear the required safety equipment as directed by the site Safety Officer while inside the mine perimeter fence.

**Information on Existing Facilities**

Facilities to be removed include the buildings listed in Table 4-2, abandoned on-site water pipes, and hydraulic control structures of the mine water treatment ponds.

**Codes, Standards, and Regulatory Requirements**

All work must be performed according to NM State Mine Inspector or MSHA requirements. The Contractor is responsible for identifying and complying with the relevant standards and requirements.

**Site Investigation Reports & Data**

Not Applicable

## Health & Safety Practices

Work area safety is the responsibility of the contractor. The contractor shall submit and implement a Safety Plan that satisfies federal, state, and RGR requirements for the type of work being performed.

For the work under this specification, Level D PPE is required. All contractor personnel and others within the contractor's working area must be equipped with the required PPE and must comply with the requirements cited in the Codes, Standards, and Regulatory Requirements section above.

The contractor shall have a qualified Safety Officer on site during working hours. The Safety Officer shall be responsible for enforcing all safety requirements and shall have the authority to remove anyone not complying with those requirements from the contractor's working area.

## Site Safety & Emergency Communication

The contractor shall post emergency response phone numbers in the worker break area. The contractor shall always maintain an active phone line. The cell phone service may not be reliable at the mine site.

## Radiological Materials

The MMD 2016 joint guidance specifies the criteria for Ra-226 only for impacted soil cleanup. It does not specify any criteria for radiologic surface contamination limits for the release of equipment, material, and facilities. In the absence of MMD- or NMED-specific radiologic surface contamination release criteria for facilities, RGR has applied the conservative gross alpha surface contamination limit of 5,000 dpm/100 cm² contained in the MMD-approved March 2021 Site Radiation Protection Program Manual. The MMD requested that the gross alpha surface contamination limit for the PMLU at the Site would not exceed the dose limit of 100 mrem/yr.

In the 12/27/2021 Addendum to "Work Plan for Post-Mining Radiological Surveys of Permit Area and Impacted Lands", RGR calculated the radiologic release criteria consistent with the 25 mrem/yr radiological dose-based criterion for license termination and unrestricted use from Title 20, Chapter 3, Part 4, Subpart 426.B of the New Mexico Administrative Code (NMAC). The gross alpha surface contamination limit for the release of facility at the dose limit of 25 mrem/yr was calculated to be 2,364 dpm/100 cm². For a 100 mrem/yr dose limit, the gross alpha surface contamination would be 9,456 dpm/100 cm². This is because the relationship between surface contamination and dose is linear. However, RGR proposes the gross alpha surface contamination limit of 5,000 dpm/100 cm², as specified in NRC Regulatory Guide 1.86, which is well below the 9,456 dpm/100 cm² calculated based on the 100 mrem/yr dose. In addition, the gross alpha surface contamination limit of 5,000 dpm/100 cm² is specified in the MMD-approved March 2021 Site Radiation Protection Program Manual

**Field Engineering and Surveying**

Not Applicable

**General Submittals**

Prior to commencing the work, the contractor shall submit, in a format acceptable to RGR, the following:

- **Site Safety Plan:** Including the name and qualifications of the Safety Officer
- **Demolition Plan:** – Describing methods of demolition, equipment to be used, names and qualifications of key personnel, and the project schedule.

**Construction Facilities and Field Office**

***Site Access, Field Office, Storage, and Maintenance***

RGR will provide space for the contractor's field office, laydown areas, sanitary facilities, and equipment maintenance. Existing buildings, if any, will not be available for contractor use. If needed, electrical power must be arranged by the contractor with Continental Divide Electric Cooperative. Water, both potable and non-potable, is available on site. The contractor must make arrangements with RGR for pumping, storing, and discharge of water needed by the contractor.

**Protection of Existing Facilities**

The contractor shall not use, damage, or block access to site buildings and other facilities that are in use at the time of the contractor's work or that are to remain intact for post-mining land use. Any damage or loss of use shall be repaired or compensated at the contractor's cost.

**Temporary Environmental Controls**

The contractor shall be responsible for emplacing, utilizing, and removing those measures necessary to contain contaminants, surface water and fugitive dust releases generated by the contractor's work. Such measures may include, but are not limited to;

- Fuels, solvents and lubricants storage
- Surface water diversions and erosion control materials
- Dust suppression chemicals containers
- Sanitary wastes containments
- Trash containers
- Fire suppression equipment

Wildlife, including large game animals, frequently enters the site. The contractor's workers shall do nothing to attract, injure, or otherwise interfere with wildlife. No firearms may be brought on the mine site.

## SITE WORK

### Site Preparation

The contractor shall de-energize and remove all electrical equipment and lines in facilities to be removed. The contractor shall prepare its office, equipment, and laydown areas as approved by RGR so as not to obstruct or interfere with RGR site operations or other contractors' operations.

### Demolition

The contractor shall submit a demolition plan for RGR approval prior to beginning the work. The plan shall include methods and equipment to be used, names and qualifications of key personnel, and schedule. The plan shall also describe any salvage proposed by the contractor, including materials and expected values.

### Building and Pipe Removal

The buildings shall be removed by mechanical or manual methods; no explosives may be used. The buildings are steel frames with metal siding and roofs.

No asbestos-containing materials (ACM) are currently known to be present within the site facilities. However, the contractor shall perform inspections as it considers necessary to identify potential ACM that may be encountered during demolition, renovation, reclamation, or earthwork activities. If suspect ACM is identified, the material shall be evaluated and managed in accordance with applicable federal and state regulations. Any confirmed ACM shall be handled by appropriately trained personnel, properly contained during removal and transport, and disposed of at a licensed off-site facility authorized to accept asbestos-containing waste. The contractor shall be responsible for complying with all applicable notification, handling, transportation, and disposal requirements.

### Debris Sizing and Stacking

The contractor shall prepare demolition debris for disposal. The contractor shall reduce the size of debris and sort it sufficiently for it to be classified and stacked by material type and potential re-use or salvage.

Demolition debris other than concrete shall be cut, hauled, and stacked according to shape (e.g.; beams, sheet metal) in disposal cell of the waste pile as determined by RGR. Debris shall be reduced in size to fit into the likely transport vehicle, but in any case, must not be any longer than 40 feet.

### Concrete Debris

The contractor shall remove the concrete in floor slabs of removed buildings, pond hydraulic control structures, ore bins next to the production shaft, aprons more than 20 feet beyond the shaft collars, and subgrade of mine car rails. Some concrete slabs and foundations (Table 4-2) will be broken into pieces not exceeding one-foot maximum dimension and left in place to be covered with soil.

## GENERAL QUALITY ASSURANCE AND QUALITY CONTROL

### Reviews

Not Applicable

### Inspection Reports

The contractor shall record in writing the amount of material removed in each truck-load trip ticket, as well as the total amount of material removed each working day. This record shall be subject to review and independent verification by RGR.

### Test Reports

Not Applicable

## FINAL ACCEPTANCE AND CONTRACT CLOSEOUT

### Substantial Completion

The work will be substantially complete when all site work and general quality assurance and quality control has been completed by the contractor and accepted by RGR.

### Close-Out Documentation

The contractor shall submit written documentation, in a form acceptable to RGR, that all units of work have been completed in accordance with this specification. This documentation shall include quantities of work performed in accordance with the line items in the contractor's bid schedule that have been approved in writing by RGR. The documentation shall also include the contractor's affirmation that all regulatory requirements and environmental standards applicable to the work have been met.

The documentation shall bear the signature of the contractor's officer with signatory authority.

### Final Payment

Final payment shall be made after close-out documentation has been accepted and approved by RGR.

# C.3 SHAFT PLUGGING AND BACKFILL

## GENERAL TECHNICAL REQUIREMENTS

### Summary of Work

Rio Grande Resources Corporation (RGR) is owner and operator of the Mt. Taylor Uranium Mine located in Cibola County, New Mexico in Section 24, T13N, R8W, NMPM. The mine site is 1/2-mile northeast of the Village of San Mateo and is accessible from New Mexico State Route 605. At the time of this submittal, the mine is in active (operating) status but has initiated closeout activities due to the continued depressed uranium market.

The mine extracted uranium ore from depths of over 3,000 feet below ground surface that connect to two 3300-foot-deep shafts from the mine surface. The water level in the shafts is approximately 820 feet below collar elevation.

The included work consists of construction of a plug in each shaft at subcollar level, backfilling to the collar and connected openings, and placement of concrete markers on the shaft caps. Required work includes:

- Mobilization and demobilization of the contractor's equipment
- Preparation of the work area
- Placement of new structural steel as the primary structural component of the shaft plugs
- Mixing and placement of light weight concrete, cementitious slurry, and cap concrete
- Site cleanup and removal of work debris

The work is represented in Appendix A Drawing Sheets: CL05 Shaft Closure - Manway Vent and CL06 Shaft Closure - Production Shaft

NOTE: THESE DRAWINGS SHOW THE CONCEPTUAL DESIGNS OF SHAFT CLOSURE. DETAILED DESIGN WILL BE COMPLETED BY A LICENSED STRUCTURAL ENGINEER AND MAY ALTER THE PLUG CONFIGURATIONS SHOWN HERE.

### Site Survey

The Contractor shall perform its own survey of the dimensions of the shaft collar, subcollar, and connected openings above subcollar level for the purposes of dimensional and volume measurements, assessment of hazards, and planning the work. This survey shall include an inventory of material in the shaft collars that must be removed from the shafts for salvage. The results of this site survey shall be submitted to the Project Manager for review and approval before the work begins.

**Site Restrictions**

Access to the site is limited to ingress/egress through the main gate. All Contractor personnel and visitors shall log in and out at the guardhouse. All personnel shall wear the required safety equipment as directed by the site Safety Officer while inside the mine perimeter fence.

The contractor's work area shall be enclosed with temporary fencing, selected and provided by the contractor, to restrict access to the shafts to authorized personnel only. The contractor shall prohibit entry to anyone not trained and authorized to enter the enclosed area or accompanied at all times by an authorized person.

**Work Performed by Others**

Not applicable.

**Codes, Standards, and Regulatory Requirements**

All work must be performed according to New Mexico State Mine Inspector and/or MSHA requirements. The Contractor is responsible for identifying and complying with the relevant standards and requirements.

The contractor shall implement the applicable requirements for worker fall protection including, but not limited to, 29 CFR 1926:

- 1926.501, Duty to have fall protection
- 1926.502, Fall protection systems criteria and practices
- 1926.503, Training requirements (Fall Protection)
- 1926.760, Steel Erection (Fall protection)
- 1926.800, Underground construction
- 1926.1051, General requirements (Stairways and Ladders)

**Site Investigation Reports & Data**

Not applicable.

**Health & Safety Practices**

Work area safety is the responsibility of the contractor. The contractor shall submit and implement a Safety Plan that satisfies federal, state, and RGR requirements for the type of work being performed.

For the work under this specification, at a minimum Level D PPE is required. In addition, safety measures required under the Codes, Standards, and Regulatory Requirements section and

elsewhere in federal and state regulations shall be implemented. All contractor personnel and others within the contractor's working area must be equipped with the required PPE.

The contractor shall have a qualified Safety Officer on site during working hours. The Safety Officer shall be responsible for enforcing all safety requirements and shall have the authority to remove anyone not complying with those requirements from the contractor's working area.

**Site Safety & Emergency Communication**

The contractor shall post emergency response phone numbers in the worker break area. The contractor shall maintain an active phone line at all times. Cell phone service is not reliable at the mine site.

**Radiological Materials**

The production shaft and manway/ventilation shaft are inaccessible and will be permanently closed through installation of engineered shaft plugs, backfill, and surface caps as described in this section. During shaft closure activities, the contractor shall implement the applicable portions of RGR's Radiation Safety Program Manual (RSPM) and associated procedures to ensure the protection of workers, the public, and the environment.

The RSPM and associated procedures include, but are not limited to, radiological work controls, development and use of non-routine procedures, access control and security, radiation monitoring surveys, radiation dose management, and response to incidents and emergencies involving radioactive materials. RGR's radiological consultant, Facilities Supervisor, and Reclamation Manager will provide the necessary technical support, training, and oversight; however, the contractor shall be responsible for ensuring worker compliance with the RSPM.

**Field Engineering and Survey**

The contractor shall perform surveys and measurements as required under the Site Survey section to verify dimensions of workspaces and construction materials described in this specification, the Appendix A reference drawings, and the 1974 Dravo design drawings, which will be available to the contractor for planning the work.

**General Submittals**

Prior to commencing the work, the contractor shall submit, in a format acceptable to RGR, the following:

- **Site Safety Plan:** Including the name and qualifications of the Safety Officer.
- **Shaft Plug and Backfill Construction Plan:** Describing methods of construction, equipment to be used, names and qualifications of key personnel, and the project schedule.

### Construction Facilities and Field Office

RGR will provide space for the contractor's field office, laydown areas, sanitary facilities, and equipment maintenance. Existing buildings, if any, will not be available for contractor use. If needed, electrical power must be arranged by the contractor with Continental Divide Electric Cooperative. Water, both potable and non-potable, is available on site. The contractor must make arrangements with RGR for pumping, storing, and discharge of water needed by the contractor.

### Protection of Existing Facilities

The contractor shall not use, damage, or block access to site buildings and other facilities that are in use at the time of the contractor's work or that are to remain intact for post-mining land use. Any damage or loss of use shall be repaired or compensated at the contractor's cost.

### Temporary Environmental Controls

The contractor shall be responsible for emplacing, utilizing, and removing those measures necessary to contain contaminants, surface water and fugitive dust releases generated by the contractor's work. Such measures may include, but are not limited to:

- Fuels, solvents and lubricants storage
- Surface water diversions and erosion control materials
- Dust suppression chemicals containers
- Sanitary wastes containments
- Trash containers
- Fire suppression equipment

## SITE CONSTRUCTION

### Site Preparation

The contractor shall prepare its office, equipment, and laydown areas as approved by RGR so as not to obstruct or interfere with RGR site operations or other contractors' operations. The contractor shall stage and operate its equipment to allow setback distances from the shaft collars that are appropriate for the selected equipment size, weight, and operating radius. The contractor shall prepare its working area and equipment locations to minimize traffic or materials next to the shaft collars.

### Shaft Plug Construction

The following information represents the construction of conceptual plug designs. The actual design and the construction to implement that design provided by a licensed Structural Engineer may be different for this conceptual design and shall supersede or modify this design concept.

Both the 24 ft. diameter production shaft and the 14 ft. diameter manway/ventilation shaft will be closed in the same way, illustrated in the Appendix A Drawing Sheets CL05 and CL06, in the following sequence after the headframes and collar structures are removed (by others) and the subcollar space has been freed of obstacles.

To address concerns regarding plug stability and the added weight on the legacy shaft concrete, the final shaft closure design will incorporate measures to transfer the structural loads from the shaft plug into competent host rock, such as engineered horizontal keyways, or another engineered approach determined during final design. The final design will support the plug independently of the existing shaft walls and minimize reliance on the long-term integrity of the shaft concrete or future regional water-level fluctuations. The final shaft closure design will be submitted to NMED for review and approval prior to construction.

To facilitate long-term post-closure groundwater sampling capabilities, the final plug design is expected to incorporate two structurally isolated steel monitoring ports built directly through each individual shaft plug.

A plug of light-weight concrete meeting the requirements of ASTM C 330 shall be poured to encapsulate the engineered structural steel and monitoring ports. The concrete shall have an in-place density of 90-115 pcf and a minimum compressive strength of 2500 psi. The concrete shall be placed in not more than three lifts. The first lift shall fully encapsulate and cover the base structural support and shall be vibrated to ensure a tight seal within the keyway. Successive lifts shall be not more than 1.0 feet thick.

The shaft plug concrete shall be allowed to cure for not less than 28 days before any overlying shaft backfill is placed.

**Shaft Backfill**

The remainder of the shaft above the plug, as well as connecting tunnels and raises, shall be backfilled with a cementitious slurry of soil, Portland cement, fly ash, and water shall be utilized. The contractor shall determine proportions of these components using test batches of the available materials, for acceptance by RGR before placement. The selected mix shall have a cured compressive strength of not less than 75 pcf. Sandy waste rock material from the waste pile may be substituted for the soil fraction of the mix.

**Shaft Cap and Marker**

The remaining space at the top of the shaft backfill, from top of slurried backfill to adjacent ground surface, shall be capped with not less than 1.0 feet of light-weight concrete, with a monument marker extending above ground surface.

The marker monuments shall be pre-cast 2500-psi concrete, at least two feet high and four feet wide and long, with a hand finished top surface. Both shaft markers shall be inscribed with "Mt. Taylor Mine (name) Shaft, Closed (date)."

## GENERAL QUALITY ASSURANCE AND QUALITY CONTROL

### Reviews

Not applicable.

### Daily Reports

The contractor shall prepare a written daily report of each working day. This report shall include a record of the dimensions of the shaft plug components, the volumes of materials used, and any deviations from the drawings or this specification necessitated by conditions encountered. This record shall be subject to review and independent verification by RGR.

### Test Reports

At least one test cylinder shall be cast for each lift of light-weight concrete poured. The contractor shall have each cylinder tested for density (unit weight) and unconfined compressive strength. Records of test cylinder tests shall be submitted to RGR.

## FINAL ACCEPTANCE AND CONTRACT CLOSEOUT

### Substantial Completion

The work will be substantially complete when all work required under the Site Construction and General Quality Assurance and Quality Control sections have been completed by the contractor and accepted by RGR.

### Close-Out Documentation

The contractor shall submit written documentation, in a form acceptable to RGR, that all units of work have been completed in accordance with this specification. This documentation shall include quantities of work performed in accordance with the line items in the contractor's bid schedule that have been approved in writing by RGR. The documentation shall also include the contractor's affirmation that all regulatory requirements and environmental standards applicable to the work have been met.

The documentation shall bear the signature of the contractor's office with signatory authority.

### Final Payment

Final payment shall be made after close-out documentation has been accepted and approved by RGR.

# C.4 EARTHWORK

## GENERAL TECHNICAL REQUIREMENTS

### Summary of Work

Rio Grande Resources Corporation (RGR) is owner and operator of the Mt. Taylor Uranium Mine located in Cibola County, New Mexico in Section 24, T13N, R8W, NMPM. The mine site is 1/2-mile northeast of the Village of San Mateo and is accessible from New Mexico State Route 605. At the time of this submittal, the mine is on active (operating) status, but RGR has initiated closeout activities due to the depressed uranium market.

The mine extracted uranium ore from depths of over 3,000 feet below ground surface that connect to two 3300-foot-deep shafts from the mine surface. The mine surface facilities are located on 285.6 acres, of which approximately 148 acres are disturbed land, and the remaining acres are undisturbed.

The disturbed land consists of:

- Support (Service and Support) Facilities
- Mine Water Treatment Area
- Ore Stockpile Pad
- Waste Pile / Disposal Cell
- Storm Water Retention Ponds (2)
- Access Road and other roads
- Borrow areas

The included work consists of excavation, hauling, placement, and compaction of soil and rippable rock within the mine permit area and nearby affected areas for the purposes removing contaminated soil, stabilizing slopes, and covering mine waste containment structures.

The required work includes:

- Mobilization and demobilization of the contractor's equipment
- Preparation of the work area
- Excavation of soil contaminated with low levels of radium and uranium originating from the underground mine and mine water
- Disposal of contaminated soil in the existing mine disposal cell on the waste rock pile, or in the shafts

- Expanding the disposal cell
- Reducing rock slopes
- Backfilling of the mine water treatment ponds
- Placement of clean soil cover over the waste rock pile and disposal cell
- Backfilling the mine water treatment ponds
- Finish grading of disturbed ground within the mine permit area and affected areas

The work is represented in the Appendix A Drawing Sheets, and will be developed in future workplans and drawing sets per individual tasks:

- CL07A: Final Grading Plan - Mine Water Treatment Unit
- CL07B: Final Grading Plan – Service and Support Area
- CL08: Details – Backfill in Pond areas
- CL14: Final Drainage Plan

**Site Survey**

The Contractor shall perform its own survey or calculations to determine depths and volumes of excavated soil, field control for line and grade, and depths and volumes of soil placed. The results of this site survey shall be submitted to the Project Manager for review and approval of work performed and for verification of payment quantities.

**Site Restrictions**

Access to the site is limited to ingress/ egress through the main gate. All Contractor personnel and visitors shall log in and out at the guardhouse. All personnel shall wear the required safety equipment as directed by the site Safety Officer while inside the mine perimeter fence.

**Work Performed by Others**

Prior to the commencement of this work, the shaft headframes, hydraulic control structures, and selected buildings will be removed by others.

**Codes, Standards, and Regulatory Requirements**

All work must be performed according to OSHA and/or MSHA requirements. The Contractor is responsible for identifying and complying with the relevant standards and requirements.

## Site Investigation Reports & Data

RGR has conducted site investigations to characterize the waste rock pile materials, soil contamination, and geotechnical properties of on-site soil. Reports of these studies and related data are included in Appendix D of the Mt. Taylor Mine Closeout/Closure Plan.

## Health & Safety Practices

Work area safety is the responsibility of the contractor. The contractor shall submit and implement a Site Safety Plan that satisfies federal, state, and RGR requirements for the type of work being performed.

For the work under this specification, Level D PPE is required. In addition, safety measures required under the Codes, Standards, and Regulatory Requirements section and elsewhere in federal and state regulations shall be implemented. All contractor personnel and others within the contractor's working area must be equipped with the required PPE and must comply with the requirements cited in the Codes, Standards, and Regulatory Requirements section.

The contractor shall have a qualified Safety Officer on site during working hours. The Safety Officer shall be responsible for enforcing all safety requirements and shall have the authority to remove from the contractor's working area anyone not complying with those requirements.

## Site Safety & Emergency Communication

The contractor shall post emergency response phone numbers in the worker break area. The contractor shall maintain an active phone line at all times. Cell phone service is not reliable at the mine site.

## Radiological Materials

The contractor shall implement the applicable portions of RGR's Radiation Safety Program Manual (RSPM) and associated procedures to ensure the protection of workers, the public, and the environment during reclamation activities. The RSPM and associated procedures include, but are not limited to, radiological work controls, development and use of non-routine procedures, access control and security, radiation monitoring surveys, radiation dose management, and response to incidents and emergencies involving radioactive materials. RGR's radiological consultant, Facilities Supervisor, and Reclamation Manager will provide the necessary technical support, training, and oversight; however, the contractor shall be responsible for ensuring worker compliance with the RSPM.

## Field Engineering and Surveying

The contractor shall perform surveys and measurements as required under the Site Survey section to verify dimensions, lines and grades, and construction materials described in this specification and the Appendix A referenced drawings.

## General Submittals

Prior to commencing the work, the contractor shall submit, in a format acceptable to RGR, the following:

- **Site Safety Plan:** Including the name and qualifications of the Safety Officer.
- **Contaminated Soil Excavation Plan:** Describing methods for excavating, hauling, and placing contaminated soil, including measures to be taken to control spillage and fugitive dust release during handling. The plan shall also describe equipment to be used, names and qualifications of key personnel, and the project schedule.
- **Soil Cover and Grading Plan:** Describing methods of construction for excavation, hauling, placing, and compacting clean fill soil, including equipment to be used, names and qualifications of key personnel, and the project schedule. The plan shall also include fugitive dust control and finish line and grade control.
- **Stormwater Pollution Prevention Plan (SWPPP)**: Compliant with the minimum requirements of EPA's 2012 Construction General Permit under the NPDES.

## Construction Facilities and Field Office

RGR will provide space for the contractor's field office, laydown areas, sanitary facilities, and equipment maintenance. Existing buildings, if any, will not be available for contractor use. If needed, electrical power must be arranged by the contractor with Continental Divide Electric Cooperative. Water, both potable and non-potable, is available on site. The contractor must make arrangements with RGR for pumping, storing, and discharge of water needed by the contractor.

## Protection of Existing Facilities

The contractor shall not use, damage, or block access to site buildings and other facilities that are in use at the time of the contractor's work or that are to remain intact for post-mining land use. Any damage or loss of use shall be repaired or compensated at the contractor's cost.

### Temporary Environmental Controls

The contractor shall be responsible for emplacing, utilizing, and removing those measures necessary to contain contaminants, surface water and fugitive dust releases generated by the contractor's work. Such measures may include, but are not limited to:

- Spraying of clean water for dust suppression
- Storage of fuels, solvents and lubricants
- Surface water diversions and erosion control materials
- Sanitary wastes containments
- Trash containers
- Fire suppression equipment

Wildlife, including large game animals, frequently enters the site. The contractor's workers shall do nothing to attract, injure, or otherwise interfere with wildlife. No firearms may be brought on the mine site.

## SITE CONSTRUCTION

### Site Preparation

The contractor shall prepare its office, equipment, and laydown areas as approved by RGR so as not to obstruct or interfere with RGR site operations or other contractors' operations.

### Removal of MWTU Facilities Pond Liner Anchor

The contractor shall remove the following:

- The HDPE liner systems from the Mine Water Treatment Unit (MWTU) Ponds 2 and 3.

All removed pond liner materials and debris from the hydraulic control structures shall be transported and placed in the disposal cell, as directed by RGR.

### Excavation and Disposal of Contaminated Soil

The contractor shall submit a Contaminated Soil Excavation Plan for excavating, hauling, and disposal of soil containing more than 6.8 pCi/g of Radium 226. RGR will provide field direction for the contractor in determining the lateral extent and depth of excavation required.

The contaminated soil excavated north of the CR 334 shall be disposed of in the disposal cell on the waste rock pile, as directed by RGR. Contaminated soil excavated within the CR 334 right-of-way and on the mine site south of the CR 334 right-of-way shall be placed in the disposal cell, as well.

The waste pile and some old fill (placed during mine development) contain scrap metal, rock bolts, abandoned pipe and cable, and other debris from mining. The contractor can encounter these materials buried within the waste rock and other locations within the mine area. If such debris is uncovered during reshaping, it shall be removed and reburied in the disposal cell.

RGR will provide radiological screening support to guide the contractor in assessment of soil radium content and determination of areas and depths of excavation for soil removal and for relocation to the disposal cell.

**Construction of Soil Cover**

The contractor shall submit for RGR approval a Soil Cover and Grading Plan that describes the methods for excavation, hauling, placing and compacting clean fill soil and finish grading over the mine site. The plan shall include equipment to be used, names and qualifications of key personnel, and schedule. The plan shall also include fugitive dust control and methods to verify finish line and grade control.

**Finish Grading**

All disturbed soil surfaces and constructed cover surfaces shall be finish-graded to achieve the lines and grades shown on Appendix A Drawing Sheets CL07A, CL07B, CL08, and CL14. The elevation contours shown on these drawings are representational; final elevations will depend on actual quantities of contaminated soil and clean cover soil excavated and placed.

The finish-graded surface shall conform to the direction (line) and angle of slope (grade) shown on the drawings. Verification of line and grade shall be made by land surveys directed by a New Mexico Licensed Professional Surveyor.

The finish-graded surfaces shall be free of demolition debris and depressions, ridges, rills, and other irregularities more than three inches in amplitude caused by either mining-related activities or closeout activities. On surfaces where rock will be placed for erosion protection (riprap), final grading need not achieve this standard but shall remove all irregularities of amplitude greater than the design thickness of the rock to be placed on such surfaces.

The surfaces of the disturbed areas and covers shall be bladed to provide:

- Smooth transitions to surrounding soil surfaces
- Gradual transitions in slope gradients
- Unimpeded drainage of runoff (no depressions deeper than the amplitude of the surface roughness of the soil cover)

On the final pass of surface grading, the grading equipment shall run along the contour of the slope, unless slope gradients are prohibitively steep, and shall blend the re-contoured surfaces into adjacent undisturbed areas.

### Erosion Control and General Site Drainage

The primary means of controlling erosion by runoff will be grading per the Finish Grading section. Control of surface water runoff onto or from reclaimed areas will be accomplished as part of the re-contouring and final grading. Existing natural drainage courses will be preserved and improved as necessary to remove obstacles and trapped debris.

In general, runoff will be directed to natural drainage courses and will follow natural surface gradients so that no control structures or energy dissipaters will be required. New drainage courses and swales will be not less than 10 feet wide at channel bed, not less than two feet deep, with side slopes not steeper than 4H:1V unless obstructed by natural durable rock. Diversion channels will be required only where actual cover or final slope gradients produce concentrated runoff and/or slope erosion.

## GENERAL QUALITY ASSURANCE AND QUALITY CONTROL

### Reviews

RGR shall meet with the contractor at the start of work each day to review the previous day's Daily Report and any deliverable from the contractor.

### Daily Reports

The contractor shall prepare a written daily report of each working day. This report shall include a record of the units and quantities of work performed, events or conditions adversely affecting the work, and any deviations from the drawings or this specification necessitated by conditions encountered. This record shall be subject to review and independent verification by RGR.

### Test Reports

The contractor shall measure, record and report in writing the quantities of each size of concrete and rock crushed and screened. The contractor shall report on the measured volumes, locations and thicknesses of soil, rock, and erosion control materials placed each day.

## FINAL ACCEPTANCE AND CONTRACT CLOSEOUT

### Substantial Completion

The work will be substantially complete when all work required under the Site Construction and General Quality Assurance and Quality Control sections have been completed by the contractor and accepted by RGR.

### Close-Out Documentation

The contractor shall submit written documentation, in a form acceptable to RGR, that all units of work have been completed in accordance with this specification. This documentation shall include quantities of work performed in accordance with the line items in the contractor's bid schedule

that have been approved in writing by RGR. The documentation shall also include the contractor's affirmation that all regulatory requirements and environmental standards applicable to the work have been met.

The documentation shall bear the signature of the contractor's officer with signatory authority.

**Final Payment**

Final payment shall be made after close-out documentation has been accepted and approved by RGR.

# APPENDIX D

## Soil Sampling and Laboratory Test Data

D.1 2012 Soil Investigations

- Kleinfelder Laboratory Results

D.2 Radiological Investigations

- Soil Investigation, June 6, 2012
- Gamma Radiation Survey Clean Borrow Pile, April 25, 2016
- Soil Analysis Results, April 30, 2018
- Gamma Radiation Survey Waste Pile North/East Delineation, April 25, 2016
- Radiological Survey Results for Discharge Pipeline and Soils Along Pipeline Corridor, July 6, 2020
- Surface and Subsurface Soil Radiologic Characterization Windblown Area, Ore Pad Area and Mine Compound, August 14, 2023
- Addendum August 14, 2023, Surface and Subsurface Soil Radiologic Characterization Report Windblown Area, Ore Pad Area and Mine Compound
- Treatment Pond Radiologic Characterization, June 4, 2024
- North Controlled Area Soil Radiologic Characterization, June 5, 2025
- South Controlled Area Soil Radiologic Characterization, February 2026

D.3 Laboratory Test Results

- Soil Physical Properties Analytical Results, April 2012
- Soil Chemical Analytical Results, April 2012
- Sediment Analytical Results, April 2012
- Ore Chemical Analysis, March 18, 1986

D.4 Original Closeout Plan Soil Data

See these reports for sampling and test data generated from 2014 to 2022:

- Construction Quality Assurance Report (CQAR), Phase 1 Completion, Mt. Taylor Mine Reactivation, February 2021
- Construction Quality Control Data Report Mine Water Treatment Pond #2, Mt. Taylor Mine, July 2020
- Construction Quality Control Data Report, Disposal Cell Liner, Mt. Taylor Mine, February 2020
- Construction Quality Control Data Report Mine Water Treatment Pond #3, Mt. Taylor Mine, February 2020
- Soil and Water Sampling and Testing, Water and Sediment Impoundment Locations Downstream of Mt. Taylor Mine Water Outfall 001, January 2015
- Vegetation Growth Report, Mt. Taylor, 2019
- Construction Quality Control Data Report, South Storm Water Pond, Mt. Taylor Mine, June 2019
- Radon Flux Measurements Report, Waste Repository Cover at Mt. Taylor Mine, May 2019

# APPENDIX D.1

## Field Sampling and Laboratory Test Data

2012 Soil Investigations





FIGURE 1

PROPOSED SAMPLE LOCATIONS
MARCH 29, 2012 - TASK 7A

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine - Borrow Test Pit Log** | **Pit #** | **MT-1-F**

| | | |
|---|---|---|
| Location Pond # 1 Berm | GPS N 35-20.578' | W 107-38.001' |
| Location Description | Top edges of Ponds – South East Side of Pond # 1 | |
| Field Engineer: Stan Fitch / Ed Loescher | Excavation Method: Small Bobcat Backhoe | |
| Date: April - 10-2012 10:30 am | Operator: | |
| Weather and Moisture Conditions: Warm – Sunny – 60 to 70d | | |

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | MT - 1- F Depth 6" | Silty Clay, mixed with some coarse sand, trace gravel, dark brown |
| 1 | | | |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 12" DEEP

Comments:

Part of the sample for sent for Geotechnical testing - Part for Environmental Testing.

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine - Borrow Test Pit Log** | **Pit #** | **MT-2-D**

| | | | |
|---|---|---|---|
| Location Pond #2 berm | GPS N 35-20.541' | W 107-38.057' | |
| Location Description | Top edges of Ponds – South Side of Pond # 2 | | |
| Field Engineer: Stan Fitch / Ed Loescher | | Excavation Method: Small Bobcat Backhoe | |
| Date: April - 10-2012 10:15 am | | Operator: | |
| Weather and Moisture Conditions: Warm – Sunny – 60 to 70d | | | |

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | MT - 2- D Depth 6" | Clayey Silt, some sand, trace roots, medium brown |
| 1 | | | |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 12" DEEP

Comments:

Part of the sample for sent for Geotechnical testing - Part for Environmental Testing.

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine - Borrow Test Pit Log** | **Pit #** | **MT-3-F**

| | | | |
|---|---|---|---|
| Location | Pond # 3 Berm | GPS N 35-20.632' | W 107-38.089' |
| Location Description | Top edges of Ponds – North East Corner of Pond # 3 | | |
| Field Engineer: | Stan Fitch / Ed Loescher | Excavation Method: | Small Bobcat Backhoe |
| Date: | April - 10-2012 11:10 am | Operator: | |
| Weather and Moisture Conditions: | Warm – Sunny – 60 to 70d | | |

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | MT -3-F Depth 6" | Silty Clay, some sand, trace gravel, dark brown |
| 1 | | | |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 12" DEEP

Comments:

Part of the sample for sent for Geotechnical testing - Part for Environmental Testing.

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine - Borrow Test Pit Log** | **Pit #** | **MT-4-F**

| | | | |
|---|---|---|---|
| Location | Pond #4 berm | GPS N 35-20.661' | W 107-38.220' |
| Location Description | Top edges of Ponds – North West Corner of Pond # 4 | | |
| Field Engineer: | Stan Fitch / Ed Loescher | Excavation Method: | Small Bobcat Backhoe |
| Date: | April - 10-2012 9:35 am | Operator: | |
| Weather and Moisture Conditions: | Warm – Sunny – 60 to 70d | | |

| . | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | MT -4-F Depth 6" | Sandy Clay, trace roots, dark brown |
| 1 | | | |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 12" DEEP

Comments:

Part of the sample for sent for Geotechnical testing - Part for Environmental Testing.

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine - Borrow Test Pit Log** | **Pit #** | **MT-5-F**

| | | | |
|---|---|---|---|
| Location | Pond #5 Berm | GPS N 35-20.576' | W 107-38.217' |
| Location Description | Top edges of Ponds – South West Corner of Pond # 5 | | |
| Field Engineer: | Stan Fitch / Ed Loescher | Excavation Method: | Small Bobcat Backhoe |
| Date: | April - 10-2012 9:45 am | Operator: | |
| Weather and Moisture Conditions: | Warm – Sunny – 60 to 70d | | |

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | MT -5-F Depth 6" | Clayey Silt, some sand, trace roots, medium brown |
| 1 | | | |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 12" DEEP

Comments:

Part of the sample for sent for Geotechnical testing - Part for Environmental Testing.

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine - Borrow Test Pit Log** | **Pit #** | **MT-7-C**

| | | | |
|---|---|---|---|
| Location | Pond #7 Berm | GPS N 35-20.526' | W 107-38.148' |
| Location Description | Top edges of Ponds – South East Corner of Pond # 7 | | |
| Field Engineer: | Stan Fitch / Ed Loescher | Excavation Method: | Small Bobcat Backhoe |
| Date: | April - 10-2012 9:55 am | Operator: | |
| Weather and Moisture Conditions: | Warm – Sunny – 60 to 70d | | |

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | MT -7-C Depth 6" | Clayey Silt, some sand, trace roots, light brown |
| 1 | | | |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 12" DEEP

Comments:

Part of the sample for sent for Geotechnical testing - Part for Environmental Testing.

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine - Borrow Test Pit Log** | **Pit #** | **MT-8-F**

| | | | |
|---|---|---|---|
| Location | Pond #8 Berm | GPS N 35-20.693' | W 107-38.108' |
| Location Description | Top edges of Ponds – South West Corner of Pond # 8 | | |
| Field Engineer: | Stan Fitch / Ed Loescher | Excavation Method: | Small Bobcat Backhoe |
| Date: | April - 10-2012 9:50 am | Operator: | |
| Weather and Moisture Conditions: | Warm – Sunny – 60 to 70d | | |

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | MT -8-F Depth 6" | Clayey Silt, some sand, trace gravel, brown |
| 1 | | | |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 12" DEEP

Comments:

Part of the sample for sent for Geotechnical testing - Part for Environmental Testing.

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine - Borrow Test Pit Log** | **Pit #** | **MT-Borrow**

| | | | |
|---|---|---|---|
| Location | Background borrow area | GPS N 35-20.724' | W 107-38.759' |
| Location Description | NE Corner of the Property in the main proposed borrow area. | | |
| Field Engineer: | Stan Fitch / Ed Loescher | Excavation Method: | Small Bobcat Backhoe |
| Date: | April - 10-2012 8:50 am | Operator: | |

Weather and Moisture Conditions: Warm – Sunny – 60 to 70d

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | | (0-24") Clayey Silt, some sand, trace roots gravel, brown |
| 1 | | | |
| 2 | | MT -borrow Composite Sample 24"-66" | (24"- 66") Silty Sand with Clay, trace gravel, occasional gray sand seams, brown. |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| | | | (66" – 72") Clayey Sand, with silt, trace roots and gravel, brown. |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 72" DEEP

Comments:

Part of the sample for sent for Geotechnical testing - Part for Environmental Testing.

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine - Borrow Test Pit Log** | **Pit #** | **MT-A-C**

Location Pond # Area "A" | GPS N 35-20.650' | W 107-38.046'

Location Description: Top edges of Ponds – North West Corner of Area A

Field Engineer: Stan Fitch / Ed Loescher | Excavation Method: Small Bobcat Backhoe

Date: April - 10-2012 10:55 am | Operator:

Weather and Moisture Conditions: Warm – Sunny – 60 to 70d

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | MT -A-C Depth 6" | Silty Sand, some clay, trace gravel, light brown |
| 1 | | | |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 12" DEEP

Comments:

Sample submitted for Environmental Testing.

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine - Borrow Test Pit Log** | **Pit #** | **MT-OP-E**

| | | |
|---|---|---|
| Location Pond # OP (Ore Pile Pond) | GPS N 35-20.694' | W 107-38.062' |
| Location Description | Top edges of Ponds – North West Corner of Pond # OP | |
| Field Engineer: Stan Fitch / Ed Loescher | Excavation Method: Small Bobcat Backhoe | |
| Date: April - 10-2012 9:10 am | Operator: | |
| Weather and Moisture Conditions: Warm – Sunny – 60 to 70d | | |

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | MT -OP-E Depth 6" | Sandy Clay, trace gravel, medium brown |
| 1 | | | |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 12" DEEP

Comments:

Part of the sample for sent for Geotechnical testing - Part for Environmental Testing.

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

## Mt Taylor Mine Water Treatment Pond Test Pit Log

Pit # 1

| | | | |
|---|---|---|---|
| Location | Pond 1 | (GPS) N 35°20.579' | W 107°38.023' |
| Location Description | | MT-1-E | |
| Field Engineer: | B. Everett | Excavation Method: | Backhoe/Shovel |
| Date: | 4/10/2012 | Operator: | K. Strickland |
| Weather and Moisture Conditions: | clear, sunny, warm; cool and windy in afternoon | | |

| Depth | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | S1-01-01 | 0-6": Sediment, silty to sandy clay, slightly moist<br>Sample collected at 0-4" bgs at 10:45 |
| 1 | | S1-01-02 | 6"-26": Clay sediments, trace gravel and cobles, some silt lenses, dark gray, dense, moist<br>Sample collected at 16-18" bgs at 10:50 |
| 2 | | S1-01-03 | 26-67": Sandy clay, hard, moist, brown<br>Sample collected at 44-48" bgs at 11:00 |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| | | | TD = 67" bgs |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 67" bgs

Comments: Pond sediments 0-6"
Clay 6-26" bgs
Native soil 26-67" bgs

Checked: Date:

Approved: Everett Date: 5/7/2012

RIO GRANDE RESOURCES CORPORATION

File #

## Mt Taylor Mine Water Treatment Pond Test Pit Log

Pit # 2

| | | | |
|---|---|---|---|
| Location | MT-1-D | (GPS) N | W |
| Location Description | Distal to inlet | | |
| Field Engineer: | B. Everett | Excavation Method: | Backhoe/Shovel |
| Date: | 4/10/2012 | Operator: | K. Strickland |
| Weather and Moisture Conditions: | clear, sunny, warm; cool and windy in afternoon | | |

| Depth | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | SL-02-01 | 0-10": Pond sediment, silty sand, friable, mottled brown and gray, moist<br>Sample collected at 0-4" bgs at 11:40 |
| 1 | | | 10"-30": Silty sand, some clay, friable, yellow-brown, moist |
| 2 | | SL-02-02 | Sample collected at 26-30" at 11:43 |
| 3 | | SL-02-03 | 30-48": Silty sand, some clay, friable, yellow-brown, slightly moist<br>Sample collected at 44-48" bgs at 11:45 |
| 4 | | | TD = 48" bgs |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 48" bgs

Comments: No visible clay or clay liner at this location.
Native material at 10-inches

Checked: Date:

Approved: Everett Date: 5/7/2012

RIO GRANDE RESOURCES CORPORATION

File #

## Mt Taylor Mine Water Treatment Pond Test Pit Log

Pit # 1

| | | | |
|---|---|---|---|
| Location | Pond 3 | (GPS) N 35°20.592' | W 107°38.02' |
| Location Description | MT-3-E | | |
| Field Engineer: | B. Everett | Excavation Method: | Backhoe/Shovel |
| Date: | 4/10/2012 | Operator: | K. Strickland |
| Weather and Moisture Conditions: | clear, sunny, warm; cool and windy in afternoon | | |

| Depth | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | | 0-4": Sediment and organic matter, clayey silt - siltly sand, light gray, varved lenses of settling |
| | | S3-01-01 | 4"-20": Clay and bentonite, dark gray, with lenses of silt, pond liner material<br>Sample collected at 0-12" bgs |
| 1 | | | |
| | | S3-01-02 | 20"-22": Silt - clayey silt, dense, white, wet. Sample collected at 20-26" bgs at 08:50 |
| 2 | | | 22"-26": Clayey Silt, brown, wet at 25 ft bgs |
| | | S3-01-03 | 26"-64": Clay, hard, dense, brown, moist, trace gravel and some silt/sand lenses.<br>Sample collected at 26-36" bgs at 09:40 |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| | | S3-01-04 | 64"-75": Silty Sand, friable, yellow-brown, trace gravel<br>Sample collected at 64-75" bgs at 09:40 |
| 6 | | | TD - 75" bgs |
| 7 | | | |
| 8 | | | |

| | |
|---|---|
| Total Depth: | 75" bgs |
| Comments: | Pond sediments 0-4"<br>Clay 4-20" bgs<br>Clayey silt 20-26" bgs<br>Clay 26-64" bgs<br>Native material 64" bgs |
| Checked: | Date: |
| Approved: Everett | Date: 5/7/2012 |

RIO GRANDE RESOURCES CORPORATION

File #

## Mt Taylor Mine Water Treatment Pond Test Pit Log

Pit # 2

| | | | |
|---|---|---|---|
| Location | Pond 3 | (GPS) N 35°20.605' | W 107°38.106' |
| Location Description | MT-3-D | | |
| Field Engineer: | B. Everett | Excavation Method: | Backhoe/Shovel |
| Date: | 4/10/2012 | Operator: | K. Strickland |
| Weather and Moisture Conditions: | clear, sunny, warm; cool and windy in afternoon | | |

| Depth | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | S3-02-01 | 0-13": Sediment, silty to sandy clay, slightly moist<br>Sample collected at 0-12" bgs at 10:05 |
| 1 | | | 13"-19": Clay sediments, varved white and dark gray, dense, moist |
| | | | 19"-37": Clay, dense brown, moist |
| 2 | | S3-02-02 | Sample collected at 26-30" bgs at 10:30 |
| 3 | | | 37"-54": Silty sand, friable, yellow-brown, moist, native soil |
| 4 | | S3-02-03 | Sample collected at 50-54" bgs at 10:30<br>TD = 54" bgs |
| | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 54" bgs

Comments: Pond sediments 0-19"
Clay 19-37" bgs
Native soil 37-54" bgs

Checked: Date:

Approved: Everett Date: 5/7/2012

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine Water Treatment Pond Test Pit Log** **Pit #** **MT-4-D**

Location Pond #4 bottom | GPS N 35-20.644' | W 107-38.178'

Location Description: Bottom of Pond – North End

Field Engineer: Ed Loescher | Excavation Method: Small Bobcat Backhoe

Date: April - 10-2012 2:00 pm | Operator:

Weather and Moisture Conditions: Warm – Sunny – 70d

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0<br>12" | | MT -4-D-S1<br>Depth 6" | (0"-12") *Pond Sediment* - Sandy Clay with some silt– Dark Brown |
| 1 | | MT -4-D-S2<br>Depth 14" | (12"- 42") Soft –fine grained- Sandstone, highly fractured, white, easily excavated with bobcat. (*Natural Soil)* |
| 2 | | | |
| 3<br>42" | | | |
| 48" | | MT -4-D-S3<br>Depth 48" | (42"- 48") Sandy Silt Brown – trace gravel *(Natural Soil)* |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 48" DEEP

Comments:

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine Water Treatment Pond Test Pit Log** | **Pit #** | **MT-4-E**

Location: Pond # 4 Bottom | GPS N 35-20.522' | W 107-38.170'

Location Description: Bottom of Pond – South End

Field Engineer: Ed Loescher | Excavation Method: Small Bobcat Backhoe

Date: April - 10-2012 1:35 pm | Operator:

Weather and Moisture Conditions: Warm – Sunny – 60d to 70d

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0<br>6" | | MT-4-E-S1<br>Depth 4" | (0"-6") *Pond Sediment* - Silty Sand, with some silt lenses – the sand was white/tan and the silt lenses were dark Brown. |
| 1<br>20" | | MT -4-E-S2<br>Depth 10-12" | (6"- 20") Silty Clay, dark brown, moist, hard (*Natural Soil or Possible liner)* |
| 2<br>3<br>48" | | MT -4-E-S3<br>Depth 36" | (20"-48") Sandy Clay, some silt, trace gravel, brown, *(Natural Soil)* |
| 4<br>50" | | MT-4-E-S4<br>Depth 48" -50" | (48"- 50") Clayey Sand, trace gravel, brown *(Natural Soil)* |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 50" DEEP

Comments:

Possible clay liner from 6 to 20" depth

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

## Mt Taylor Mine Water Treatment Pond Test Pit Log

Pit # 1

| | | | |
|---|---|---|---|
| Location | Pond 5 | (GPS) N 35°20.580' | W 107°38.150' |
| Location Description | MT-5-E | | |
| Field Engineer: | B. Everett | Excavation Method: | Backhoe/Shovel |
| Date: | 4/10/2012 | Operator: | K. Strickland |
| Weather and Moisture Conditions: | clear, sunny, warm; cool and windy in afternoon | | |

| Depth | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | S5-01-01 | 0-22": Clayey silt with sand, friable, brown, moist<br>Sample collected at 0-12" bgs at 14:05 |
| 1 | | | |
| 2 | | | 22"-37": Silty sand, trace clay, friable, dry |
| 3 | | S5-01-02 | Sample collected at 36-37" bgs at 14:09 |
| | | | TD = 37" bgs |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 37" bgs

Comments:
No clay layer noted
Clayey silt with sand 0-22" bgs
Native soil at 22" bgs
Silty sand with trace clay 22-37" bgs

| | | | |
|---|---|---|---|
| Checked: | | Date: | |
| Approved: | Everett | Date: | 5/7/2012 |

RIO GRANDE RESOURCES CORPORATION

File #

## Mt Taylor Mine Water Treatment Pond Test Pit Log

Pit # 2

| | | | |
|---|---|---|---|
| Location | Pond 5 | (GPS) N 35°20.595' | W 107°38.189' |
| Location Description | MT-5-D | | |
| Field Engineer: | B. Everett | Excavation Method: | Backhoe/Shovel |
| Date: | 4/10/2012 | Operator: | K. Strickland |
| Weather and Moisture Conditions: | clear, sunny, warm; cool and windy in afternoon | | |

| Depth | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | SS-02-01 | 0-10": Silty sand, slightly clayey, brown, mottled with white dense BaCl, friable, slightly damp<br>Sample collected at 0-12" bgs at 14:30 |
| 1 | | | 10"-17": Clay with white precipate BaCl, varved sediments from settling, dark brown gray and white, dense, some silt |
| | | SS-02-02 | 17"-24": Silty sand, friable, yellow brown, slightly moist<br>Sample collected 17-24" bgs at 14:15 |
| 2 | | | 24"- 44": Silty sand, friable yellow brown, slightly damp, trace gravel and cobbles |
| 3 | | SS-02-03 | Sample collected at 40-44" bgs at 14:20 |
| | | | TD = 45" bgs |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 45" bgs

Comments: No liner in this pond. Various construction debris on surface. Moist to 24" bgs, slightly damp below.
Pond sediments 0-17" bgs
Native soil 17-44" bgs

Checked: Date:

Approved: Everett Date: 5/7/2012

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine Water Treatment Pond Test Pit Log** | **Pit #** | **MT-6-A**

| | | | |
|---|---|---|---|
| Location Pond # 6 Bottom | GPS N 35-20.557' | W 107-38.157' | |
| Location Description | Bottom of Pond – East end | | |
| Field Engineer: Ed Loescher | | Excavation Method: Small Bobcat Backhoe | |
| Date: April - 10-2012 3:00 pm | | Operator: | |

Weather and Moisture Conditions: Warm – Sunny – 60d to 70d

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0<br>12" | | MT -6-A-S1<br>Depth 0-5" | (0"-12") *Pond Sediment* - Sandy Silt, light gray<br>(sand from erosion of pond side-banks) |
| 1<br>20" | | MT -4-D-S2<br>Depth 12-20 | (12"- 20") Silty Clay, dark gray and reddish brown silt seams, moist (Pond sediment)<br>(Hypalon geomembrane liner at 20" depth) |
| 2 | | | (20"-40") River Rocks, rounded, 3"dia to 6"dia. |
| 3<br>40" | | | (Hypalon geomembrane liner at 40" depth)<br>40" - Hit hard rock surface. Appears to be a sandstone layer. |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 40" DEEP

Comments:

Hypalon and river-rock liner.

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine Water Treatment Pond Test Pit Log** **Pit #** **MT-6-B**

Location Pond #6 Bottom | GPS N 35-20.560' | W 107-38.174'

Location Description: Bottom of Pond West End

Field Engineer: Ed Loescher | Excavation Method: Small Bobcat Backhoe

Date: April - 10-2012 2:30 pm | Operator:

Weather and Moisture Conditions: Warm – Sunny –60d to 70d

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | MT -6-B-S1 depth 8"- 10" | (0"-16") *Pond Sediment* - Intermittent lenses of silt, sand and sandy Clay, light gray (sand from erosion of pond side banks) |
| 1 16" | | | (Hypalon geomembrane liner at 16" depth)<br>(16"- 28") River Rocks, rounded, 3"dia to 6"dia. |
| 2 28" | | | (Hypalon geomembrane liner at 28" depth) |
| 3 42" | | MT -6-B-S2 Depth 30" | (28"- 42") Sandy Silt Brown – trace gravel *(Natural Soil)*<br>42" - Hit hard rock surface. Appears to be a sandstone layer |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 42" DEEP

Comments:

Hypalon and river-rock liner.

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

## Mt Taylor Mine Water Treatment Pond Test Pit Log

Pit # 1

| | | | |
|---|---|---|---|
| Location | Pond 7 | (GPS) N 35°20.544 | W 107°38.171' |
| Location Description | MT-7-A | | |
| Field Engineer: | B. Everett | Excavation Method: | Backhoe/Shovel |
| Date: | 4/10/2012 | Operator: | K. Strickland |
| Weather and Moisture Conditions: | clear, sunny, warm; cool and windy in afternoon | | |

| Depth | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | S7-01-01 | 0-10": Sediments, clayey silt, moist, dark brown<br>Sample collected at 0-10" bgs at 15:12 |
| | | | 10"-12": Clay, soft red, moist |
| 1 | | | 12"-30.5": Silty clay, dense, dark brown, moist |
| 2 | | S7-01-02 | Sample collected at 24-30" bgs at 15:17 |
| | | S7-01-03 | 30.5"-35": Silty sand, yellow brown, moist<br>Sample collected at 30.5-34" bgs at 15:22 |
| 3 | | | TD = 35" bgs |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 35" bgs

Comments: Geolayer at 10" bgs, 2" of moist red clay below liner
18" of dark brown clay below red clay
Native soil - silty sand below 30.5" bgs, slightly moist
Bedrock at 35" bgs

Checked: Date:

Approved: Everett Date: 5/7/2012

RIO GRANDE RESOURCES CORPORATION

File #

## Mt Taylor Mine Water Treatment Pond Test Pit Log

Pit # 2

| | | | |
|---|---|---|---|
| Location | Pond 7 | (GPS) N 35°20.544 | W 107°38.171' |
| Location Description | MT-7-B | | |
| Field Engineer: | B. Everett | Excavation Method: | Backhoe/Shovel |
| Date: | 4/10/2012 | Operator: | K. Strickland |
| Weather and Moisture Conditions: | clear, sunny, warm; cool and windy in afternoon | | |

| Depth | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | | 0-23": Silty sand sediments, loose, light tan, some organic material, moist to 12" bgs, dry below 12" bgs |
| 1 | | S7-02-01 | Sample collected at 0-12" bgs at 15:45 |
| 2 | | | 23"-43": Pond sediments, silt varved from settling |
| 3 | | S7-02-02 | Sample collected at 23-43" bgs |
| | | S7-02-03 | 43"-45": Clay, red, moist, soft. Sample collected at 43-46" bgs |
| | | | 45"-49": Clay and silt, brown, dense, moist |
| 4 | | | 49"-50": Sandy silt, yellow brown, dry |
| | | | TD =50" bgs |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 50" bgs

Comments: Geolayer at 43" bgs with 2" red clay beneath
Native soil at 49-50" bgs
Bedrock at 50" bgs

Checked: Date:

Approved: Everett Date: 5/7/2012

RIO GRANDE RESOURCES CORPORATION

File #

## Mt Taylor Mine Water Treatment Pond Test Pit Log

Pit # 1

| | | | |
|---|---|---|---|
| Location | Pond 8 | (GPS) N 35°20.708 | W 107°38.129' |
| Location Description | MT-8-E | | |
| Field Engineer: | B. Everett | Excavation Method: | Backhoe/Shovel |
| Date: | 4/10/2012 | Operator: | K. Strickland |
| Weather and Moisture Conditions: | clear, sunny, warm; cool and windy in afternoon | | |

| Depth | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | S8-01-01 | 0-17": Clayey silt, pliable, brown, moist<br>Sample collected at 0-8" bgs at 13:00 |
| 1 | | | |
| | | S8-01-02 | 17"-30": Clay, dense, gray brown, with white precipitate BaCl 6" layer from 17-23" bgs<br>Sample collected at 17-30" bgs |
| 2 | | | Increase in brown silty sand 23-30" bgs |
| | | | 30"-40": Silty sand, friable, yellow brown, dry |
| 3 | | S8-01-03 | Sample collected at 36-40" bgs at 13:09 |
| | | | TD = 40" bgs |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 40" bgs

Comments: Moist to 20" bgs
BaCl layer 17-23" bgs in clay 17-30" bgs
Native soil yellow brown, silty sand at 30" bgs

Checked: Date:

Approved: Everett Date: 5/7/2012

RIO GRANDE RESOURCES CORPORATION

File #

## Mt Taylor Mine Water Treatment Pond Test Pit Log

Pit # 2

| | | | |
|---|---|---|---|
| Location | Pond 8 | (GPS) N 35°20.714' | W 107°38.150' |
| Location Description | MT-8-D | | |
| Field Engineer: | B. Everett | Excavation Method: | Backhoe/Shovel |
| Date: | 4/10/2012 | Operator: | K. Strickland |
| Weather and Moisture Conditions: | clear, sunny, warm; cool and windy in afternoon | | |

| Depth | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | S8-02-01 | 0-18": Silty sand, trace gravel, brown, friable, moist<br>Sample collected at 0-12" bgs at 13:26 |
| 1 | | | |
| | | S8-02-02 | 18"-24": Clayey silt, varved gray and white sediment settling<br>Sample collected 18-24" bgs at 13:36 |
| 2 | | S8-02-03 | 24"-56": Clay, very dense, dark brown, slightly damp to dry<br>Sample collected at 40-50" bgs at 13:36 |
| 3 | | | |
| 4 | | | |
| 5 | | S8-02-04 | 56"-62": Silty sand, yellow brown, friable, dry<br>Sample collected 58-62" bgs at 13:39 |
| | | | TD = 62" bgs |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 62" bgs

Comments:
Silty sand, brown, friable, some gravel 0-18" bgs
Clayey silt, gray white, varved pond sediments 18-24" bgs
Clay, very dense, dark brown, dry 24-56" bgs
Native soil, yellow brown, silty sand 56-62" bgs

| | | | |
|---|---|---|---|
| Checked: | | Date: | |
| Approved: | Everett | Date: | 5/7/2012 |

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine Water Treatment Pond Test Pit Log** **Pit #** **MT-A-A**

Location Area "A" | GPS no reading | W no reading

Location Description Bottom of Pond –North End

Field Engineer: Ed Loescher | Excavation Method: Small Bobcat Backhoe

Date: April - 10-2012 11:45 am | Operator:

Weather and Moisture Conditions: Warm – Sunny – 60 to 70d

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 4" 0 | | MT -A-A-S1 Depth 4" | (0"-4") *Pond Sediment* - Clayey Silt with some silt– Dark Brown |
| 1 | | MT -A-A-S2 Depth 8" | (4"- 30") Sandy Clay, trace gravel, brown, moist (*Natural Soil)* |
| 30" 2 | | | |
| 36" | | | (30"-36") Silty Sand, some clay, trace gravel, tan (*Natural Soil)* |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 36" DEEP

Comments:

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine Water Treatment Pond Test Pit Log** — **Pit #** **MT-A-B**

Location Area "A" | GPS no reading | W no reading

Location Description: Bottom of Pond –South End

Field Engineer: Ed Loescher | Excavation Method: Small Bobcat Backhoe

Date: April - 10-2012 11:30 am | Operator:

Weather and Moisture Conditions: Warm – Sunny – 60 to 70d

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0<br>6" | | MT -A-B-S1<br>Depth 4" | (0"-6") *Pond Sediment* - Clayey Silt with some silt– Dark Brown |
| 1 | | MT -A-B-S2<br>Depth 8" | (6"- 28") Sandy Clay, trace gravel, brown, moist *(Natural Soil)* |
| 28" 2<br>36" | | MT -A-B-S3<br>Depth 30" | (28"-36") Silty Sand, some clay, trace gravel, brown, moist *(Natural Soil)* |
| 3 | | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 36" DEEP

Comments:

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

File #

**Mt Taylor Mine Water Treatment Pond Test Pit Log** | **Pit #** | **MT-OP-D**

Location OP (ore pile pond) | GPS N 35-20.675' | W 107-38.004'

Location Description: Bottom of Pond – West end

Field Engineer: Ed Loescher | Excavation Method: Small Bobcat Backhoe

Date: April - 10-2012 12:45 pm | Operator:

Weather and Moisture Conditions: Warm – Sunny – 60 -70d

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | MT -OP-D-S1 Depth 6" | (*Alluvial Sand* 0-48") **Sand,** trace silt and gravel, tan, loose. (layer of sand from erosion of inlet channel and pond side-banks.) |
| 1 | | | |
| 2 | | | |
| 3 48" | | | |
| 4 | | MT -OP-D-S2 Depth 48" -50" | (48"- 72") **Clay,** frequent silt seams, dark gray, moist. (possible original pond sediment from 48"-50" and underlain by a clay liner to 72") |
| 5 72" | | | |
| 6 | | | (72"-76") **Clayey Sand,** trace gravel, brown, moist *(Natural Soil)* |
| 76" | | | |
| 7 | | | |
| 8 | | | |

Total Depth: 76" DEEP

Comments:

Difficult to determine layering below 48" due to the upper layer of sand caving into excavation.
Upper layer of sand due to erosion from pond inlet and side-banks.
Observed perched water seeping slowly into excavation at 50" depth

Checked: Date:

Approved: Date:

RIO GRANDE RESOURCES CORPORATION

**Mt Taylor Mine Water Treatment Pond Test Pit Log** | **Pit #** | **MT-OP-C**

| | | | |
|---|---|---|---|
| Location OP (ore pile pond) | GPS N 35-20.680' | W 107-38.032' | |
| Location Description | Bottom of Pond - East end | | |
| Field Engineer: Ed Loescher | | Excavation Method: Small Bobcat Backhoe | |
| Date: April - 10-2012 1:20 pm | | Operator: | |

Weather and Moisture Conditions: Warm – Sunny – 60 -70d

| | Graphic Log | Sample # | Description (USCS, texture, density, color, moisture, odor, inclusions, etc.) |
|---|---|---|---|
| 0 | | MT -OP-C-S1 Depth 6" | (*Pond Sediment* 0-18") **Mix of Silt and Clay** - Dark Gray- Trace Gravel |
| 1 18" | | | |
| 2 | | MT -OP-C-S2 Depth 20" | (18"- 44") **Clayey Sand** with some silt - Brown - Trace Gravel (*Natural Soil)* |
| 3 44" | | | |
| 4 | | MT -OP-C-S3 Depth 48" -50" | (44"- 72") **Sandy Clay** - Brown- Some Gravel – moist *(Natural Soil)* |
| 5 72" | | | |
| 6 | | MT -OP-C-S4 Depth 72" | (72") **Clayey Sand** - Brown - Some Gravel – moist *(Natural Soil)* |
| 7 | | | |
| 8 | | | |

Total Depth: 72" DEEP

Comments:

Checked: Date:

Approved: Date:

**APPENDIX B**


Kleinfelder Laboratory Results

# SUMMARY OF LABORATORY ANALYSIS

Project: **Mount Taylor Mine: Settling Pond Evaluations** Location: **San Mateo, New Mexico**
Project Number: **96450**

| Boring Number | Depth | Soil Classification | | Atterberg Limits | | Sieve Analysis - Accumulative % Passing | | | | | | | | | | | | | | Moisture Content | Dry Density | Unconfined Comp. Strength |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | (ft.) | USCS | AASHTO | PI | LL | No. 200 | No. 100 | No. 50 | No. 40 | No. 30 | No. 16 | No. 10 | No. 8 | No. 4 | 3/8 in | 1/2 in | 3/4 in | 1 in | 1 1/2 in | (%) | (pcf) | (psi) |
| Borrow Area | 2.0 - 5.5 | CL | A-6 | 13 | 37 | 64 | 78 | 88 | 91 | 93 | 97 | 98 | 99 | 99 | 100 | 100 | 100 | -- | -- | 10.7 | -- | -- |
| MT-1-F | 0.0 - 0.5 | SC | A-6 | 15 | 35 | 44 | 56 | 74 | 76 | 77 | 81 | 99 | 100 | 100 | 100 | -- | -- | -- | -- | 13.7 | -- | -- |
| MT-2-D | 0.0 - 0.5 | CL | A-6 | 14 | 33 | 56 | 73 | 95 | 97 | 97 | 98 | 99 | 99 | 100 | 100 | -- | -- | -- | -- | 16.4 | -- | -- |
| MT-3-F | 0.0 - 0.5 | CL | A-6 | 17 | 35 | 59 | 77 | 92 | 95 | 96 | 98 | 99 | 99 | 100 | 100 | -- | -- | -- | -- | 17.3 | -- | -- |
| MT-4-F | 0.0 - 0.5 | CL | A-6 | 13 | 34 | 63 | 86 | 90 | 91 | 91 | 91 | 91 | 91 | 91 | 92 | 92 | 96 | 100 | -- | 10.5 | -- | -- |
| MT-5-F | 0.0 - 0.5 | CL | A-6 | 17 | 37 | 67 | 80 | 94 | 96 | 97 | 98 | 99 | 99 | 99 | 100 | 100 | -- | -- | -- | 17.6 | -- | -- |
| MT-7-C | 0.0 - 0.5 | CL | A-6 | 17 | 39 | 71 | 80 | 94 | 97 | 98 | 100 | 100 | 100 | 100 | -- | -- | -- | -- | -- | 17.9 | -- | -- |
| MT-8-F | 0.0 - 0.5 | SC | A-6 | 13 | 27 | 50 | 73 | 95 | 97 | 98 | 99 | 99 | 99 | 100 | 100 | -- | -- | -- | -- | 12.9 | -- | -- |
| MT-OP-E | 0.0 - 0.5 | CL | A-6 | 12 | 31 | 63 | 79 | 95 | 97 | 98 | 99 | 99 | 99 | 100 | 100 | -- | -- | -- | -- | 10.3 | -- | -- |
| MT-WP-SM1 | 0.0 - | SC | A-6 | 24 | 37 | 48 | 67 | 91 | 93 | 94 | 96 | 97 | 97 | 98 | 99 | 99 | 100 | -- | -- | 5.9 | -- | -- |
| MT-WP-SM2 | 0.0 - | CL | A-7-6 | 27 | 43 | 70 | 78 | 85 | 86 | 87 | 89 | 91 | 92 | 96 | 98 | 100 | -- | -- | -- | 10.9 | -- | -- |
| MT-WP-SM3 | 0.0 - | SC | A-6 | 21 | 34 | 46 | 63 | 89 | 93 | 95 | 96 | 97 | 97 | 98 | 98 | 99 | 100 | -- | -- | 3.0 | -- | -- |

KLEINFELDER
Bright People. Right Solutions.




| COBBLES | GRAVEL | | SAND | | | SILT OR CLAY |
|---|---|---|---|---|---|---|
| | coarse | fine | coarse | medium | fine | |

| Specimen Identification | | | D100 | D60 | D30 | D10 | %Gravel | %Sand | %Silt | %Clay |
|---|---|---|---|---|---|---|---|---|---|---|
| ● | Borrow Area | 2.0 | 19.05 | | | | 0.7 | 35.4 | 63.9 | |
| ⊠ | MT-1-F | 0.0 | 9.525 | 0.177 | | | 0.1 | 55.6 | 44.3 | |
| ▲ | MT-2-D | 0.0 | 9.525 | 0.087 | | | 0.4 | 43.2 | 56.3 | |
| ★ | MT-3-F | 0.0 | 9.525 | 0.077 | | | 0.4 | 40.1 | 59.4 | |
| ⊙ | MT-4-F | 0.0 | 25.4 | | | | 8.8 | 28.4 | 62.8 | |

ASTM D1140 ASTM C136


KLEINFELDER
Bright People. Right Solutions.
9019 Washington NE, Building A
Albuquerque, NM 87113

## GRAIN SIZE DISTRIBUTION

Project: Mount Taylor Mine: Settling Pond Evaluations

Location: San Mateo, New Mexico

Project Number: 96450




| COBBLES | GRAVEL | | SAND | | | SILT OR CLAY |
|---|---|---|---|---|---|---|
| | coarse | fine | coarse | medium | fine | |

| | Specimen Identification | | D100 | D60 | D30 | D10 | %Gravel | %Sand | %Silt | %Clay |
|---|---|---|---|---|---|---|---|---|---|---|
| ● | MT-5-F | 0.0 | 12.7 | | | | 0.8 | 32.4 | 66.8 | |
| ⊠ | MT-7-C | 0.0 | 4.75 | | | | 0.0 | 29.4 | 70.6 | |
| ▲ | MT-8-F | 0.0 | 9.525 | 0.102 | | | 0.3 | 49.7 | 50.0 | |
| ★ | MT-OP-E | 0.0 | 9.525 | | | | 0.4 | 36.6 | 63.0 | |
| ⊙ | MT-WP-SM1 | 0.0 | 19.05 | 0.115 | | | 2.0 | 49.7 | 48.3 | |

ASTM D1140 ASTM C136


KLEINFELDER
Bright People. Right Solutions.
9019 Washington NE, Building A
Albuquerque, NM 87113

## GRAIN SIZE DISTRIBUTION

Project: Mount Taylor Mine: Settling Pond Evaluations

Location: San Mateo, New Mexico

Project Number: 96450




| COBBLES | GRAVEL | | SAND | | | SILT OR CLAY |
|---|---|---|---|---|---|---|
| | coarse | fine | coarse | medium | fine | |

| | Specimen Identification | | D100 | D60 | D30 | D10 | %Gravel | %Sand | %Silt | %Clay |
|---|---|---|---|---|---|---|---|---|---|---|
| ● | MT-WP-SM2 | 0.0 | 12.7 | | | | 4.3 | 25.6 | 70.1 | |
| ⊠ | MT-WP-SM3 | 0.0 | 19.05 | 0.134 | | | 2.1 | 52.2 | 45.8 | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

ASTM D1140 ASTM C136

KLEINFELDER
Bright People. Right Solutions.
9019 Washington NE, Building A
Albuquerque, NM 87113


## GRAIN SIZE DISTRIBUTION

Project: Mount Taylor Mine: Settling Pond Evaluations

Location: San Mateo, New Mexico

Project Number: 96450

ASTM D4318




| Specimen Identification | | | Liquid Limit (LL) | Plastic Limit (PL) | Plasticity Index (PI) |
|---|---|---|---|---|---|
| ● | Borrow Area | 2.0 | 37 | 24 | 13 |
| ⊠ | MT-1-F | 0.0 | 35 | 20 | 15 |
| ▲ | MT-2-D | 0.0 | 33 | 19 | 14 |
| ★ | MT-3-F | 0.0 | 35 | 18 | 17 |
| ⊙ | MT-4-F | 0.0 | 34 | 21 | 13 |


KLEINFELDER
Bright People. Right Solutions.

9019 Washington NE, Building A
Albuquerque, NM 87113



## ATTERBERG LIMITS

Project: Mount Taylor Mine: Settling Pond Evaluations

Location: San Mateo, New Mexico

Project Number: 96450

ASTM D4318




| Specimen Identification | | | Liquid Limit (LL) | Plastic Limit (PL) | Plasticity Index (PI) |
|---|---|---|---|---|---|
| ● | MT-5-F | 0.0 | 37 | 20 | 17 |
| ⊠ | MT-7-C | 0.0 | 39 | 22 | 17 |
| ▲ | MT-8-F | 0.0 | 27 | 14 | 13 |
| ★ | MT-OP-E | 0.0 | 31 | 19 | 12 |
| ⊙ | MT-WP-SM1 | 0.0 | 37 | 13 | 24 |


KLEINFELDER
Bright People. Right Solutions.

9019 Washington NE, Building A
Albuquerque, NM 87113



## ATTERBERG LIMITS

Project: Mount Taylor Mine: Settling Pond Evaluations

Location: San Mateo, New Mexico

Project Number: 96450

ASTM D4318




| Specimen Identification | | Liquid Limit (LL) | Plastic Limit (PL) | Plasticity Index (PI) |
|---|---|---|---|---|
| ● | MT-WP-SM2 0.0 | 43 | 16 | 27 |
| ⧓ | MT-WP-SM3 0.0 | 34 | 13 | 21 |
| | | | | |
| | | | | |
| | | | | |


KLEINFELDER
Bright People. Right Solutions.


9019 Washington NE, Building A
Albuquerque, NM 87113


## ATTERBERG LIMITS

Project: Mount Taylor Mine: Settling Pond Evaluations

Location: San Mateo, New Mexico

Project Number: 96450




Boring Borrow Area Depth 2.0 - 5.5

Test Method **ASTM D1557 Method B**

TEST RESULTS

| | | |
|---|---|---|
| Maximum Dry Density | **101.5** | **PCF** |
| Optimum Water Content | **16.2** | **%** |

MATERIAL DESCRIPTION

| | |
|---|---|
| % clay or silt | 63.9 |
| % sand | 35.4 |
| % gravel | 0.7 |
| Liquid Limit | 37 |
| Plastic Limit | 24 |
| Plasticity Index | 13 |

CURVES OF 100% SATURATION
FOR SPECIFIC GRAVITY EQUAL TO:

2.80

2.70

2.60

KLEINFELDER
Bright People. Right Solutions.


9019 Washinton NE Bldg A
Albuquerque, NM 87113

## MOISTURE-DENSITY RELATIONSHIP

Project: Mount Taylor Mine: Settling Pond Evaluations

Location: San Mateo, New Mexico

Project Number: 96450




Boring MT-2-D Depth 0.0 - 0.5

Test Method **ASTM D1557 Method B**

TEST RESULTS

Maximum Dry Density **106.7** **PCF**

Optimum Water Content **13.9** **%**

MATERIAL DESCRIPTION

| | |
|---|---|
| % clay or silt | 56.3 |
| % sand | 43.2 |
| % gravel | 0.4 |
| Liquid Limit | 33 |
| Plastic Limit | 19 |
| Plasticity Index | 14 |

CURVES OF 100% SATURATION
FOR SPECIFIC GRAVITY EQUAL TO:

2.80

2.70

2.60

KLEINFELDER
Bright People. Right Solutions.


9019 Washinton NE Bldg A
Albuquerque, NM 87113

## MOISTURE-DENSITY RELATIONSHIP

Project: Mount Taylor Mine: Settling Pond Evaluations

Location: San Mateo, New Mexico

Project Number: 96450




Boring MT-5-F Depth 0.0 - 0.5

Test Method **ASTM D1557 Method B**

TEST RESULTS

| | | |
|---|---|---|
| Maximum Dry Density | **107.6** | **PCF** |
| Optimum Water Content | **14.6** | **%** |

MATERIAL DESCRIPTION

| | |
|---|---|
| % clay or silt | 66.8 |
| % sand | 32.4 |
| % gravel | 0.8 |
| Liquid Limit | 37 |
| Plastic Limit | 20 |
| Plasticity Index | 17 |

CURVES OF 100% SATURATION
FOR SPECIFIC GRAVITY EQUAL TO:

2.80

2.70

2.60

KLEINFELDER
Bright People. Right Solutions.


9019 Washinton NE Bldg A
Albuquerque, NM 87113

## MOISTURE-DENSITY RELATIONSHIP

Project: Mount Taylor Mine: Settling Pond Evaluations

Location: San Mateo, New Mexico

Project Number: 96450




Boring MT-8-F Depth 0.0 - 0.5

Test Method **ASTM D1557 Method B**

TEST RESULTS

Maximum Dry Density **110.2** **PCF**

Optimum Water Content **13.5** **%**

MATERIAL DESCRIPTION

| | |
|---|---|
| % clay or silt | 50.0 |
| % sand | 49.7 |
| % gravel | 0.3 |
| Liquid Limit | 27 |
| Plastic Limit | 14 |
| Plasticity Index | 13 |

CURVES OF 100% SATURATION
FOR SPECIFIC GRAVITY EQUAL TO:

2.80

2.70

2.60

KLEINFELDER
Bright People. Right Solutions.

9019 Washinton NE Bldg A
Albuquerque, NM 87113


## MOISTURE-DENSITY RELATIONSHIP

Project: Mount Taylor Mine: Settling Pond Evaluations

Location: San Mateo, New Mexico


Project Number: 96450

# MT TAYLOR MINE SHAFT MUCK SAMPLE LOCATIONS – 5/18/2010




Bulk samples of shaft muck from Mt. Taylor Mine waste rock pile collected on 5/18/2012 by Alan Kuhn. Locations are approximate (+/- 50 ft) based on visual reference to slopes. Splits delivered 5/18/12 to Kleinfelder Albuquerque for grain size analysis and plasticity tests. Other splits left with RGR Mine office for shipment to Energy Labs for testing of U and Ra concentration.

ASTM D4318




| Specimen Identification | | Liquid Limit (LL) | Plastic Limit (PL) | Plasticity Index (PI) |
|---|---|---|---|---|
| ● MT-WP-SM1 | 0.0 | 37 | 13 | 24 |
| ⊠ MT-WP-SM2 | 0.0 | 43 | 16 | 27 |
| ▲ MT-WP-SM3 | 0.0 | 34 | 13 | 21 |
| | | | | |
| | | | | |


KLEINFELDER
Bright People. Right Solutions.


9019 Washington NE, Building A
Albuquerque, NM 87113


## ATTERBERG LIMITS

Project: Mount Taylor Mine: Settling Pond Evaluations

Location: San Mateo, New Mexico

Project Number: 96450




| COBBLES | GRAVEL | | SAND | | | SILT OR CLAY |
|---|---|---|---|---|---|---|
| | coarse | fine | coarse | medium | fine | |

| | Specimen Identification | | D100 | D60 | D30 | D10 | %Gravel | %Sand | %Silt | %Clay |
|---|---|---|---|---|---|---|---|---|---|---|
| ● | MT-WP-SM1 | 0.0 | 19.05 | 0.115 | | | 2.0 | 49.7 | 48.3 | |
| ⊠ | MT-WP-SM2 | 0.0 | 12.7 | | | | 4.3 | 25.6 | 70.1 | |
| ▲ | MT-WP-SM3 | 0.0 | 19.05 | 0.134 | | | 2.1 | 52.2 | 45.8 | |
| | | | | | | | | | | |
| | | | | | | | | | | |

ASTM D1140 ASTM C136

KLEINFELDER
Bright People. Right Solutions.
9019 Washington NE, Building A
Albuquerque, NM 87113

## GRAIN SIZE DISTRIBUTION

Project: Mount Taylor Mine: Settling Pond Evaluations

Location: San Mateo, New Mexico

Project Number: 96450

# SUMMARY OF LABORATORY ANALYSIS

Project: **Mount Taylor Mine: Settling Pond Evaluations** Location: **San Mateo, New Mexico**
Project Number: **96450**

| Boring Number | Depth (ft.) | Soil Classification | | Atterberg Limits | | Sieve Analysis - Accumulative % Passing | | | | | | | | | | | | | | Moisture Content (%) | Dry Density (pcf) | Unconfined Comp. Strength (psi) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | USCS | AASHTO | PI | LL | No. 200 | No. 100 | No. 50 | No. 40 | No. 30 | No. 16 | No. 10 | No. 8 | No. 4 | 3/8 in | 1/2 in | 3/4 in | 1 in | 1 1/2 in | | | |
| MT-WP-SM1 | 0.0 - | SC | A-6 | 24 | 37 | 48 | 67 | 91 | 93 | 94 | 96 | 97 | 97 | 98 | 99 | 99 | 100 | -- | -- | 5.9 | -- | -- |
| MT-WP-SM2 | 0.0 - | CL | A-7-6 | 27 | 43 | 70 | 78 | 85 | 86 | 87 | 89 | 91 | 92 | 96 | 98 | 100 | -- | -- | -- | 10.9 | -- | -- |
| MT-WP-SM3 | 0.0 - | SC | A-6 | 21 | 34 | 46 | 63 | 89 | 93 | 95 | 96 | 97 | 97 | 98 | 98 | 99 | 100 | -- | -- | 3.0 | -- | -- |

KLEINFELDER
Bright People. Right Solutions.

# APPENDIX D.2

## Field Sampling and Laboratory Test Data

Radiological Investigations

**MEMORANDUM**

Date: June 6, 2012

From: Stanley Fitch, CHP, Radiation Safety Officer 

To: Joel Lister, Mine Manager, Mt. Taylor Mine

Subject: April 2012 Soil Investigation

On April 23, 2012, a soil sampling campaign was performed to investigate possible environmental dispersal of uranium and its progeny from the Mt. Taylor Mine. A total of 16 samples were retrieved, 2 background locations and 14 locations along arroyos that drain the mine property. In addition, gamma dose rate measurements were taken.

The purpose of this investigation is to determine background radionuclide concentrations and to evaluate the potential spread of uranium and radium from the mine. To wit, soil samples were taken at various locations adjacent to drainage features (e.g., Marquez Arroyo) and in the thalwegs of these features. The background locations selected are locations MTE-1 (up Marquez Canyon next to the Forest Service Boundary) and MTE-7 (North ¼ Corner of Section 24) for grades above drainage features.

MTE-2 was selected as the background location for the Marquez Canyon drainage. However, because the steepness of the arroyo created a sandy bed with very limited organics that would retain background naturally occurring radioactive material (NORM), it is believed that MTE-2 is a poor representation of the remainder of the drainage.

An aerial map is attached depicting the sample locations. The soil sample locations are also attached in Table 2 (below) with their respective New Mexico State Plane Coordinates and sample analysis results. See also Table 3.

The following observations are made based on the radionuclide data in Table 2:

- There appears to be no discernible dispersal of uranium and uranium progeny off the mine property.

- The concentrations of radionuclides in the Marquez Canyon arroyo adjacent and below Pond 8 (MTE-3, MTE-4, MTE-5, MTE-6) are equivalent to or lower than the background concentrations (MTE-1, MTE-2, MTE-7), indicating: 1) no discernible spread of contamination north of the current boundary; and 2) seasonal water flows purge organics from the Marquez arroyo thalweg that would contain naturally occurring radioactive material (NORM) and radionuclides from the mine (TENORM).

- Radionuclide concentrations in the alluvial deposits north and northeast of San Mateo (MTE-8, MTE-9, MTE-10, MTE-11, MTE-13, MTE-14) are consistent with NORM concentrations typical for this region at locales away from uranium mining operations. There are no identifiable patterns that would indicate the dispersal of uranium and radium into the plain from Mt. Taylor Mine.

- The slightly elevated ambient radiation readings north of Pond 8 were not explained by the soil sample analyses performed for this investigation. Please compare the survey results for MTE-3 and MTE-4 against the survey results for the background locations:

**Table 1**

| **Location** | **Dose Rate** µrem/h | **U-238** pCi/g | **Ra-226** pCi/g |
|---|---|---|---|
| MTE-1 (Surface Grade BKG) | 18 | 1.6 | 1.7 |
| MTE-7 (Surface Grade BKG) | 13 | 0.6 | 1.5 |
| MTE-3 (Surface Grade) | 26 | 0.5 | 1.4 |

Regressional analysis of the data in Table 2 indicates very poor statistical correlation between the dose rates and the concentrations of Radium-226 in the soil.

The conclusions are that: 1) radiation "shine" from nearby and elevated rock and soils could be affecting the instrument readings; and 2) soil sample analyses must be performed along with dose rate surveys when evaluating remediation requirements.


April 23, 2012
Soil Sample Locations
N
MTE-7
MTE-5
MTE-6
MTE-3
MTE-4
MTE-2
MTE-1
MTE-12
MTE-10
MTE-11
MTE-14
MTE-13
MTE-9
MTE-8
MTE-16
MTE-15

**Table 2**
**RADIATION SURVEY AND SAMPLE RESULTS**
**April 23, 2012**

| Location # | Description | Sample Time | NAD 27 Northing | NAD 27 Easting | Dose Rate (µrem/h) | U-238 (pCi/g) | Ra-226 (pCi/g) | Gross Alpha (pCi/g) |
|---|---|---|---|---|---|---|---|---|
| MTE-1 | Marquez Arroyo Top of Grade; clay | 10:20 | 1580869 | 561223 | 18 | 1.6 | 1.7 | 6.8 |
| MTE-2 | Marquez Arroyo Thalweg; very sandy | 10:25 | 1580963 | 561211 | 15 | 0.3 | 0.7 | 3.7 |
| MTE-3 | Marquez Arroyo Top of Grade; clay | 10:50 | 1581289 | 559191 | 26 | 0.5 | 1.4 | 7.6 |
| MTE-4 | Marquez Arroyo Thalweg; sandy | 10:58 | 1581226 | 559201 | 24 | 0.2 | 1.2 | 5.0 |
| MTE-5 | Marquez Arroyo Top of Grade; clay | 11:05 | 1581507 | 558551 | 18 | 0.4 | 1.4 | 4.6 |
| MTE-6 | Marquez Arroyo Thalweg; sandy | 11:10 | 1581479 | 558532 | 15 | 0.4 | 1.5 | 8.9 |
| MTE-7 | N¼ Corner Section 24; clay | 11:30 | 1582031 | 558654 | 13 | 0.6 | 1.5 | 12.4 |
| MTE-8 | Drainage Top of Grade; clay | 12:37 | 1579422 | 555004 | 14 | 1.2 | 2.8 | 9.8 |
| MTE-9 | Drainage Thalweg; clay | 12:40 | 1579428 | 555009 | 14 | 1.1 | 1.8 | 7.6 |
| MTE-10 | Drainage Top of Grade; clay | 12:52 | 1580023 | 555383 | 14 | 0.3 | 1.2 | 5.5 |
| MTE-11 | Drainage Thalweg; clay | 12:54 | 1580047 | 555376 | 13 | 0.4 | 1.2 | 4.5 |
| MTE-12 | Marquez Arroyo fan; clay | 13:40 | 1580724 | 556946 | 13 | 0.9 | 2.1 | 12.9 |
| MTE-13 | Drainage Thalweg; sandy clay | 13:55 | 1579390 | 557582 | 14 | 1.4 | 2.7 | 8.0 |
| MTE-14 | Drainage Top of Grade; clay | 14:05 | 1579410 | 557576 | 14 | 0.4 | 1.1 | 11.9 |
| MTE-15 | Drainage Thalweg; sandy | 14:45 | 1578344 | 557794 | 14 | 1.0 | 2.0 | 5.8 |
| MTE-16 | Drainage Top of Grade; clay | 14:50 | 1578386 | 557805 | 13 | 0.3 | 0.8 | 6.4 |

Notes:

1. The term "grade" above refers to the natural surface outside of and atop the drainage feature.
2. Dose Rate Instrument: Eberline PRM-7 #182, BKG = 10-12 µrem/h
3. Coordinates reported are New Mexico State Plane Coordinates in the New Mexico West UTM projection.

## Table 3
## COORDINATE CONVERSIONS

| Location # | Description | NAD 83 Coordinates | | NAD 27 Coordinates | |
|---|---|---|---|---|---|
| | | N | E | N | E |
| MTE-1 | Grade on South Side of Marquez Arroyo | 1580937 | 2784129 | 1580869 | 561223 |
| MTE-2 | Thalweg of Marquez Arroyo | 1581031 | 2784117 | 1580963 | 561211 |
| MTE-3 | Grade on North Side of Marquez Arroyo | 1581357 | 2782097 | 1581289 | 559191 |
| MTE-4 | Thalweg of Marquez Arroyo | 1581294 | 2782107 | 1581226 | 559201 |
| MTE-5 | Grade North Side of Marquez Arroyo | 1581575 | 2781457 | 1581507 | 558551 |
| MTE-6 | Thalweg of Marquez Arroyo | 1581547 | 2781438 | 1581479 | 558532 |
| MTE-7 | North 1/4 Corner Section 24 | 1582099 | 2781560 | 1582031 | 558654 |
| MTE-8 | Grade on South Side of Drainage | 1579490 | 2777910 | 1579422 | 555004 |
| MTE-9 | Thalweg of Drainage | 1579496 | 2777915 | 1579428 | 555009 |
| MTE-10 | Grade on South Side of Drainage | 1580091 | 2778289 | 1580023 | 555383 |
| MTE-11 | Thalweg of Drainage | 1580115 | 2778282 | 1580047 | 555376 |
| MTE-12 | Marquez Arroyo Fan | 1580792 | 2779852 | 1580724 | 556946 |
| MTE-13 | Thalweg of Drainage | 1579458 | 2780488 | 1579390 | 557582 |
| MTE-14 | Grade on North Side of Drainage | 1579478 | 2780482 | 1579410 | 557576 |
| MTE-15 | Thalweg of Drainage | 1578412 | 2780700 | 1578344 | 557794 |
| MTE-16 | Grade on North Side of Drainage | 1578454 | 2780711 | 1578386 | 557805 |

Note: Coordinates reported are New Mexico State Plane Coordinates in the New Mexico West UTM projection.

# ANALYTICAL SUMMARY REPORT

June 01, 2012

Rio Grande Resources Corporation
PO Box 1150
Grants, NM 87020

Workorder No.: C12041338

Project Name: Mt. Taylor Mine

Energy Laboratories, Inc. Casper WY received the following 16 samples for Rio Grande Resources Corporation on 4/30/2012 for analysis.

| Sample ID | Client Sample ID | Collect Date | Receive Date | Matrix | Test |
|---|---|---|---|---|---|
| C12041338-001 | MTE-1 | 04/23/12 10:20 | 04/30/12 | Soil | Digestion For RadioChemistry<br>Gross Alpha, Gross Beta Sample Prep<br>Gamma Sample Preparation<br>Gross Alpha, Gross Beta<br>Gross Gamma<br>Uranium, Isotopic |
| C12041338-002 | MTE-2 | 04/23/12 10:25 | 04/30/12 | Soil | Same As Above |
| C12041338-003 | MTE-3 | 04/23/12 10:50 | 04/30/12 | Soil | Same As Above |
| C12041338-004 | MTE-4 | 04/23/12 10:58 | 04/30/12 | Soil | Same As Above |
| C12041338-005 | MTE-5 | 04/23/12 11:05 | 04/30/12 | Soil | Same As Above |
| C12041338-006 | MTE-6 | 04/23/12 11:10 | 04/30/12 | Soil | Same As Above |
| C12041338-007 | MTE-7 | 04/23/12 11:30 | 04/30/12 | Soil | Same As Above |
| C12041338-008 | MTE-8 | 04/23/12 12:37 | 04/30/12 | Soil | Same As Above |
| C12041338-009 | MTE-9 | 04/23/12 12:40 | 04/30/12 | Soil | Same As Above |
| C12041338-010 | MTE-10 | 04/23/12 12:52 | 04/30/12 | Soil | Same As Above |
| C12041338-011 | MTE-11 | 04/23/12 12:56 | 04/30/12 | Soil | Same As Above |
| C12041338-012 | MTE-12 | 04/23/12 13:40 | 04/30/12 | Soil | Same As Above |
| C12041338-013 | MTE-13 | 04/23/12 13:55 | 04/30/12 | Soil | Same As Above |
| C12041338-014 | MTE-14 | 04/23/12 14:05 | 04/30/12 | Soil | Same As Above |
| C12041338-015 | MTE-15 | 04/23/12 14:45 | 04/30/12 | Soil | Same As Above |
| C12041338-016 | MTE-16 | 04/23/12 14:50 | 04/30/12 | Soil | Same As Above |

The analyses presented in this report were performed at Energy Laboratories, Inc., 2393 Salt Creek Hwy., Casper, WY 82601, unless otherwise noted. Radiochemistry analyses were performed at Energy Laboratories, Inc., 2325 Kerzell Lane, Casper, WY 82601, unless otherwise noted. Any exceptions or problems with the analyses are noted in the Laboratory Analytical Report, the QA/QC Summary Report, or the Case Narrative.

The results as reported relate only to the item(s) submitted for testing. Solid/soil samples are reported on a wet weight basis (as received) unless specifically indicated. Data corrected for moisture content are typically noted as -dry on the report. For agricultural and mining soil parameters/characteristics, all samples are dried and ground prior to sample analysis.

If you have any questions regarding these test results, please call.

Report Approved By:

**CLIENT:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Sample Delivery Group:** C12041338

**Report Date:** 06/01/12

# CASE NARRATIVE

ORIGINAL SAMPLE SUBMITTAL(S)
All original sample submittals have been returned with the data package.

SAMPLE TEMPERATURE COMPLIANCE: 4°C (±2°C)
Temperature of samples received may not be considered properly preserved by accepted standards. Samples that are hand delivered immediately after collection shall be considered acceptable if there is evidence that the chilling process has begun.

GROSS ALPHA ANALYSIS
Method 900.0 for gross alpha and gross beta is intended as a drinking water method for low TDS waters. Data provided by this method for non potable waters should be viewed as inconsistent.

RADON IN AIR ANALYSIS
The desired exposure time is 48 hours (2 days). The time delay in returning the canister to the laboratory for processing should be as short as possible to avoid excessive decay. Maximum recommended delay between end of exposure to beginning of counting should not exceed 8 days.

SOIL/SOLID SAMPLES
All samples reported on an as received basis unless otherwise indicated.

ATRAZINE, SIMAZINE AND PCB ANALYSIS
Data for PCBs, Atrazine and Simazine are reported from EPA 525.2. PCB data reported by ELI reflects the results for seven individual Aroclors. When the results for all seven are ND (not detected), the sample meets EPA compliance criteria for PCB monitoring.

SUBCONTRACTING ANALYSIS
Subcontracting of sample analyses to an outside laboratory may be required. If so, ENERGY LABORATORIES will utilize its branch laboratories or qualified contract laboratories for this service. Any such laboratories will be indicated within the Laboratory Analytical Report.

BRANCH LABORATORY LOCATIONS
eli-b - Energy Laboratories, Inc. - Billings, MT
eli-g - Energy Laboratories, Inc. - Gillette, WY
eli-h - Energy Laboratories, Inc. - Helena, MT
eli-r - Energy Laboratories, Inc. - Rapid City, SD
eli-t - Energy Laboratories, Inc. - College Station, TX

CERTIFICATIONS:
USEPA: WY00002, Radiochemical WY00937; FL-DOH NELAC: E87641, Radiochemical E871017; California: 02118CA; Oregon: WY200001, Radiochemical WY200002; Utah: WY00002; Virginia: 00057; Washington: C836

ISO 17025 DISCLAIMER:
The results of this Analytical Report relate only to the items submitted for analysis.

ENERGY LABORATORIES, INC. - CASPER,WY certifies that certain method selections contained in this report meet requirements as set forth by the above accrediting authorities. Some results requested by the client may not be covered under these certifications. All analysis data to be submitted for regulatory enforcement should be certified in the sample state of origin. Please verify ELI's certification coverage by visiting www.energylab.com

ELI appreciates the opportunity to provide you with this analytical service. For additional information and services visit our web page www.energylab.com.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-001
**Client Sample ID:** MTE-1

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 10:20
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 6.8 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.8 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 1.7 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 1.6 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 19.2 | pCi/g-dry | | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 3.8 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 1.7 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-002
**Client Sample ID:** MTE-2

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 10:25
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 3.7 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.7 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.06 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 0.7 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-003
**Client Sample ID:** MTE-3

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 10:50
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 7.6 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.8 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 0.6 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | -0.02 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 0.5 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 1.4 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-004
**Client Sample ID:** MTE-4

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 10:58
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 5.0 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.7 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 0.5 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.07 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 0.2 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 1.2 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.4 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-005
**Client Sample ID:** MTE-5

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 11:05
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 4.6 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.7 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 0.6 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.03 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 1.4 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-006
**Client Sample ID:** MTE-6

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 11:10
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 8.9 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.8 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 0.5 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.09 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 1.5 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-007
**Client Sample ID:** MTE-7

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 11:30
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 12.4 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.9 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 0.6 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.02 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 0.6 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 1.5 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-008
**Client Sample ID:** MTE-8

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 12:37
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 9.8 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.8 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 1.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.1 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 1.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 2.8 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.6 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-009
**Client Sample ID:** MTE-9

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 12:40
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 7.6 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.8 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 1.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.2 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 1.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 1.8 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-010
**Client Sample ID:** MTE-10

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 12:52
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 5.5 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.7 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.08 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 1.2 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-011
**Client Sample ID:** MTE-11

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 12:56
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 4.5 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.7 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.02 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 1.2 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.4 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-012
**Client Sample ID:** MTE-12

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 13:40
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 12.9 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.9 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 0.9 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.07 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 0.9 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 2.1 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-013
**Client Sample ID:** MTE-13

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 13:55
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 8.0 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.8 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 1.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.08 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 1.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 2.7 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-014
**Client Sample ID:** MTE-14

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 14:05
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 11.9 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.9 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.05 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 0.4 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 1.1 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-015
**Client Sample ID:** MTE-15

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 14:45
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 5.8 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.7 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 0.8 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | 0.02 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.09 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 2.0 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12041338-016
**Client Sample ID:** MTE-16

**Report Date:** 06/01/12
**Collection Date:** 04/23/12 14:50
**DateReceived:** 04/30/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Gross Alpha | 6.4 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Gross Alpha precision (±) | 0.8 | pCi/g-dry | | | | E900.0 | 05/02/12 12:00 / ep |
| Uranium 234 | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 precision (±) | 0.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 234 MDC | 0.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 | -0.01 | pCi/g-dry | U | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 precision (±) | 0.06 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 235 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 | 0.3 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 precision (±) | 0.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| Uranium 238 MDC | 0.1 | pCi/g-dry | | | | E908.0 | 05/08/12 08:58 / dmf |
| **RADIONUCLIDES - GAMMA** | | | | | | | |
| Potassium 40 | 0.0 | pCi/g-dry | U | 0.5 | | E901.1 | 05/22/12 13:10 / dpb |
| Potassium 40 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 | 0.8 | pCi/g-dry | | 0.3 | | E901.1 | 05/22/12 13:10 / dpb |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 05/22/12 13:10 / dpb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation **Report Date:** 06/01/12

**Project:** Mt. Taylor Mine **Work Order:** C12041338

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E900.0** | | | | | | | | | | Batch: R159328 |
| **Sample ID: MB-R159328** | 2 | Method Blank | | | | Run: G5000W_120502A | | | | 05/02/12 12:00 |
| Gross Alpha | | -0.03 | pCi/g-dry | | | | | | | U |
| Gross Alpha precision (±) | | 0.6 | pCi/g-dry | | | | | | | |
| **Sample ID: LCS-R159328** | | Laboratory Control Sample | | | | Run: G5000W_120502A | | | | 05/02/12 12:00 |
| Gross Alpha | | 487 | pCi/g-dry | | 96 | 70 | 130 | | | |
| **Sample ID: C12040820-001ADUP** | 2 | Sample Duplicate | | | | Run: G5000W_120502A | | | | 05/02/12 12:00 |
| Gross Alpha | | 3.28 | pCi/g-dry | | | 70 | 130 | 14 | 20 | |
| Gross Alpha precision (±) | | 0.660 | pCi/g-dry | | | | | | | |
| - Duplicate RPD for Gross Beta is outside of the acceptance range for this analysis. | | | | | | | | | | |
| **Sample ID: C12041338-010ADUP** | 2 | Sample Duplicate | | | | Run: G5000W_120502A | | | | 05/02/12 12:00 |
| Gross Alpha | | 6.25 | pCi/g-dry | | | 70 | 130 | 13 | 20 | |
| Gross Alpha precision (±) | | 0.750 | pCi/g-dry | | | | | | | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

U - Not detected at minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation **Report Date:** 06/01/12

**Project:** Mt. Taylor Mine **Work Order:** C12041338

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E901.1** | | | | | | | | | Batch: R160127 | |
| **Sample ID: LCS-R160127** | | Laboratory Control Sample | | | | Run: GAM-HPGE_120522B | | | 05/22/12 13:10 | |
| Bismuth 214 | | 2.30 | pCi/g-dry | 0.30 | 89 | 70 | 130 | | | |
| **Sample ID: MB-R160127** | 4 | Method Blank | | | | Run: GAM-HPGE_120522B | | | 05/22/12 13:10 | |
| Potassium 40 | | ND | pCi/g-dry | | | | | | | U |
| Potassium 40 precision (±) | | ND | pCi/g-dry | | | | | | | |
| Radium 226 | | ND | pCi/g-dry | | | | | | | U |
| Radium 226 precision (±) | | ND | pCi/g-dry | | | | | | | |
| **Sample ID: C12041338-010ADUP** | 4 | Sample Duplicate | | | | Run: GAM-HPGE_120522B | | | 05/22/12 13:10 | |
| Potassium 40 | | ND | pCi/g-dry | 0.50 | | | | | 20 | U |
| Potassium 40 precision (±) | | ND | pCi/g-dry | | | | | | | |
| Radium 226 | | 1.80 | pCi/g-dry | 0.30 | | | | 40 | 20 | R |
| Radium 226 precision (±) | | 0.400 | pCi/g-dry | | | | | | | |
| - Duplicate RPD for Ra226 is outside of the acceptance range for this analysis. | | | | | | | | | | |
| **Sample ID: C12041338-016ADUP** | 4 | Sample Duplicate | | | | Run: GAM-HPGE_120522B | | | 05/22/12 13:10 | |
| Potassium 40 | | ND | pCi/g-dry | 0.50 | | | | | 20 | U |
| Potassium 40 precision (±) | | ND | pCi/g-dry | | | | | | | |
| Radium 226 | | 1.00 | pCi/g-dry | 0.30 | | | | 22 | 20 | R |
| Radium 226 precision (±) | | 0.300 | pCi/g-dry | | | | | | | |
| - Duplicate RPD for Ra226 is outside of the acceptance range for this analysis. | | | | | | | | | | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

U - Not detected at minimum detectable concentration

ND - Not detected at the reporting limit.

R - RPD exceeds advisory limit.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Report Date:** 06/01/12
**Project:** Mt. Taylor Mine
**Work Order:** C12041338

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E908.0** | | | | | | | | | | Batch: 33540 |
| **Sample ID: C12041338-016AMS** | 2 | Sample Matrix Spike | | | | Run: EGG-ORTEC_120504B | | | | 05/08/12 13:12 |
| Uranium 234 | | 29.3 | pCi/g-dry | | 105 | 70 | 130 | | | |
| Uranium 238 | | 31.8 | pCi/g-dry | | 112 | 70 | 130 | | | |
| **Sample ID: C12041338-016AMSD** | 2 | Sample Matrix Spike Duplicate | | | | Run: EGG-ORTEC_120504B | | | | 05/08/12 13:12 |
| Uranium 234 | | 30.7 | pCi/g-dry | | 109 | 70 | 130 | 4.3 | 28.4 | |
| Uranium 238 | | 31.8 | pCi/g-dry | | 111 | 70 | 130 | 0.1 | 28.1 | |
| **Sample ID: LCS-33540** | 2 | Laboratory Control Sample | | | | Run: EGG-ORTEC_120504B | | | | 05/08/12 13:12 |
| Uranium 234 | | 2.44 | pCi/g-dry | | 105 | 80 | 120 | | | |
| Uranium 238 | | 2.53 | pCi/g-dry | | 107 | 80 | 120 | | | |
| **Sample ID: MB-33540** | 9 | Method Blank | | | | Run: EGG-ORTEC_120504B | | | | 05/08/12 13:12 |
| Uranium 234 | | 0.002 | pCi/g-dry | | | | | | | U |
| Uranium 234 precision (±) | | 0.02 | pCi/g-dry | | | | | | | |
| Uranium 234 MDC | | 0.03 | pCi/g-dry | | | | | | | |
| Uranium 235 | | -0.004 | pCi/g-dry | | | | | | | U |
| Uranium 235 precision (±) | | 0.01 | pCi/g-dry | | | | | | | |
| Uranium 235 MDC | | 0.03 | pCi/g-dry | | | | | | | |
| Uranium 238 | | 0.0001 | pCi/g-dry | | | | | | | U |
| Uranium 238 precision (±) | | 0.009 | pCi/g-dry | | | | | | | |
| Uranium 238 MDC | | 0.02 | pCi/g-dry | | | | | | | |

**Qualifiers:**

RL - Analyte reporting limit.
MDC - Minimum detectable concentration
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# Workorder Receipt Checklist

## Rio Grande Resources Corporation

C12041338

Login completed by: Corinne Wagner
Date Received: 4/30/2012
Reviewed by: BL2000\cwagner
Received by: tj
Reviewed Date: 5/2/2012
Carrier name: Ground

| | | | |
|---|---|---|---|
| Shipping container/cooler in good condition? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on shipping container/cooler? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on sample bottles? | Yes ☐ | No ☐ | Not Present ☑ |
| Chain of custody present? | Yes ☑ | No ☐ | |
| Chain of custody signed when relinquished and received? | Yes ☑ | No ☐ | |
| Chain of custody agrees with sample labels? | Yes ☑ | No ☐ | |
| Samples in proper container/bottle? | Yes ☑ | No ☐ | |
| Sample containers intact? | Yes ☑ | No ☐ | |
| Sufficient sample volume for indicated test? | Yes ☑ | No ☐ | |
| All samples received within holding time? (Exclude analyses that are considered field parameters such as pH, DO, Res Cl, Sulfite, Ferrous Iron, etc.) | Yes ☑ | No ☐ | |
| Container/Temp Blank temperature: | 14.2°C | | |
| Water - VOA vials have zero headspace? | Yes ☐ | No ☐ | No VOA vials submitted ☑ |
| Water - pH acceptable upon receipt? | Yes ☐ | No ☐ | Not Applicable ☑ |

Contact and Corrective Action Comments:

None

# Chain of Custody and Analytical Request Record



**PLEASE PRINT- Provide as much information as possible.**

| Company Name: | Project Name, PWS, Permit, Etc. | Sample Origin | EPA/State Compliance: |
|---|---|---|---|
| Rio Grande Resources Corporation #C11115 | Mt. Taylor Mine | State: NM | Yes ☒ No ☐ |
| **Report Mail Address:** PO Box 1150<br>Grants, NM 87020-1150 | **Contact Name:** Joe Lister, Manager<br>**Phone/Fax:** (505) 287-7971 | **Email:** | **Sampler: (Please Print)** Stan Fitch |
| **Invoice Address:** Rio Grande Resources<br>PO Box 1150<br>Grants, New mexico 87020 | **Invoice Contact & Phone:** Joe Lister 505-287-7971 | **Purchase Order:** | **Quote/Bottle Order:** Soil Samples |

Special Report/Formats – ELI must be notified prior to sample submittal for the following:

☐ DW ☐ A2LA
☐ GSA ☐ EDD/EDT (Electronic Data)
☐ POTW/WWTP **Format:**_____
☐ State: _____ ☐ LEVEL IV
☐ Other: _____ ☐ NELAC

**RUSH** Contact ELI prior to **RUSH** sample submittal for charges and scheduling – See Instruction Page

Comments: Sample results needed within 30 days.

Shipped by: UPS-G
Cooler ID(s): 3539 / 29
Receipt Temp 14.2 °C
On Ice: Yes (No)
Custody Seal Intact Signature Match: Y (N)

| | SAMPLE IDENTIFICATION (Name, Location, Interval, etc.) | Collection Date | Collection Time | MATRIX | Isotopic Uranium | Radium-226 | Potassium-40 | Gross Alpha | SEE ATTACHED | Normal Turnaround (TAT) |
|---|---|---|---|---|---|---|---|---|---|---|
| 1 | MTE-1 | 04/23/12 | 10:20 | soil | X | X | X | X | | X |
| 2 | MTE-2 | 04/23/12 | 10:25 | soil | X | X | X | X | | X |
| 3 | MTE-3 | 04/23/12 | 10:50 | soil | X | X | X | X | | X |
| 4 | MTE-4 | 04/23/12 | 10:58 | soil | X | X | X | X | | X |
| 5 | MTE-5 | 04/23/12 | 11:05 | soil | X | X | X | X | | X |
| 6 | MTE-6 | 04/23/12 | 11:10 | soil | X | X | X | X | | X |
| 7 | MTE-7 | 04/23/12 | 11:30 | soil | X | X | X | X | | X |
| 8 | MTE-8 | 04/23/12 | 12:37 | soil | X | X | X | X | | X |
| 9 | MTE-9 | 04/23/12 | 12:40 | soil | X | X | X | X | | X |
| 10 | MTE-10 | 04/23/12 | 12:52 | soil | X | X | X | X | | X |

LABORATORY USE ONLY

**Custody Record MUST be Signed**

| | Relinquished by (print): | Date/Time: | Signature: | Received by (print): | Date/Time: | Signature: |
|---|---|---|---|---|---|---|
| 1 | Stan Fitch | 04/26/12 11:00 | | | | |
| 2 | | | | | | |
| Laboratory | | | | | 4-30-12 9:20 | |

Sample Disposal: Return to Client: _____ Lab Disposal: XXXXX

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested.
This serves as notice of this possibility. All sub-contract data will be clearly notated on your analytical report.
Visit our web site at www.energylab.com for additional information, downloadable fee schedule, forms, and links.

# Chain of Custody and Analytical Request Record



PLEASE PRINT- Provide as much information as possible.

| | | | |
|---|---|---|---|
| Company Name: Rio Grande Resources Corporation #C11115 | Project Name, PWS, Permit, Etc.: Mt. Taylor Mine | Sample Origin State: NM | EPA/State Compliance: Yes ☑ No ☐ |
| Report Mail Address: PO Box 1150 Grants, NM 87020-1150 | Contact Name: Joe Lister, Manager Phone/Fax: (505) 287-7971 | Email: | Sampler: (Please Print) Stan Fitch |
| Invoice Address: PO Box 1150 Grants, New Mexico 87020 | Invoice Contact & Phone: Joe Lister 505-287-7971 | Purchase Order: | Quote/Bottle Order: Soil Samples |

Special Report/Formats -- ELI must be notified prior to sample submittal for the following:

☐ DW ☐ A2LA
☐ GSA ☐ EDD/EDT (Electronic Data) Format: _____
☐ POTW/WWTP ☐ LEVEL IV
☐ State: _____ ☐ NELAC
☐ Other: _____

Number of Containers
Sample Type: A W S V B O
Air Water Soils/Solids Vegetation Bioassay Other

ANALYSIS REQUESTED

| SAMPLE IDENTIFICATION (Name, Location, Interval, etc.) | Collection Date | Collection Time | MATRIX | Isotopic Uranium | Radium-226 | Potassium-40 | Gross Alpha | SEE ATTACHED | Normal Turnaround (TAT) |
|---|---|---|---|---|---|---|---|---|---|
| 1 MTE-11 | 04/23/12 | 12:56 | soil | X | X | X | X | | X |
| 2 MTE-12 | 04/23/12 | 13:40 | soil | X | X | X | X | | X |
| 3 MTE-13 | 04/23/12 | 13:55 | soil | X | X | X | X | | X |
| 4 MTE-14 | 04/23/12 | 14:05 | soil | X | X | X | X | | X |
| 5 MTE-15 | 04/23/12 | 14:45 | soil | X | X | X | X | | X |
| 6 MTE-16 | 04/23/12 | 14:50 | soil | X | X | X | X | | X |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |

R U S H — Contact ELI prior to **RUSH** sample submittal for charges and scheduling – See Instruction Page

Comments:

Sample results needed within 30 days.

Shipped by:

Cooler ID(s):

Receipt Temp _____ °C

On Ice: Yes No

Custody Seal Y N
Intact Y N
Signature Match Y N

LABORATORY USE ONLY

**Custody Record MUST be Signed**

| | | | | | |
|---|---|---|---|---|---|
| Relinquished by (print): Stan Fitch | Date/Time: 04/26/12 11:00 | Signature: | Received by (print): | Date/Time: | Signature: |
| Relinquished by (print): | Date/Time: | Signature: | Received by (print): | Date/Time: | Signature: |
| Sample Disposal: Return to Client: _____ Lab Disposal: XXXXX | | | Received by Laboratory: 4-30-12 | Date/Time: 9:20 | Signature: |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All sub-contract data will be clearly notated on your analytical report.
Visit our web site at www.energylab.com for additional information, downloadable fee schedule, forms, and links.

**RGR Mt. Taylor Mine** Stan Fitch
**Gamma Radiation Survey** 4/25/2016
**Clean Borrow Pile**

Instrument: Eberline PRM-7 #182, BKG = 15 µrem/h, readings waist high

| NAD 83 Datum | | | |
|---|---|---|---|
| Northing | Easting | Dose Rate µrem/h | Notes |
| 1581153 | 2783831 | 16 | Fence Angle |
| 1581120 | 2783737 | 20 | |
| 1581085 | 2783638 | 22 | |
| 1581053 | 2783536 | 32 | |
| 1581017 | 2783451 | 60 | East toe of levy |
| 1580986 | 2783331 | 60 | Crown -- top of pile, west side |
| 1580885 | 2783375 | 60 | Crown -- top of pile, west side |
| 1580910 | 2783477 | 30 | East toe of levy |
| 1580942 | 2783575 | 26 | |
| 1580972 | 2783678 | 22 | |
| 1580990 | 2783776 | 18 | |
| 1581020 | 2783874 | 18 | |
| 1581098 | 2783955 | 16 | Northeasterly Fence Corner |
| 1580992 | 2783937 | 16 | Fence Line |
| 1580955 | 2783843 | 20 | |
| 1580911 | 2783751 | 24 | |
| 1580867 | 2783656 | 25 | |
| 1580819 | 2783560 | 35 | |
| 1580785 | 2783471 | 60 | East toe of levy |
| 1580759 | 2783383 | 60 | Crown -- top of pile, west side |
| 1580652 | 2783371 | 80 | Crown -- top of pile, west side |
| 1580686 | 2783463 | 35 | East toe of levy |
| 1580709 | 2783562 | 30 | |
| 1580735 | 2783664 | 24 | |
| 1580757 | 2783770 | 26 | |
| 1580792 | 2783895 | 20 | Fence line |
| 1580703 | 2783873 | 16 | Southeasterly Fence Corner |

ACZ Laboratories, Inc.
2773 Downhill Drive Steamboat Springs, CO 80487 (800) 334-5493

# Analytical Report

April 30, 2018

Report to:
Alan Kuhn
Alan Kuhn Associates LLC
13212 Manitoba Dr NE
Albuquerque, NM 87111

cc: Joe Lister

Bill to:
Alan Kuhn
Alan Kuhn Associates LLC
13212 Manitoba Dr NE
Albuquerque, NM 87111

Project ID: AKA-ACZ-2018.1
ACZ Project ID: L43559

Alan Kuhn:

Enclosed are the analytical results for sample(s) submitted to ACZ Laboratories, Inc. (ACZ) on April 05, 2018. This project has been assigned to ACZ's project number, L43559. Please reference this number in all future inquiries.

All analyses were performed according to ACZ's Quality Assurance Plan. The enclosed results relate only to the samples received under L43559. Each section of this report has been reviewed and approved by the appropriate Laboratory Supervisor, or a qualified substitute.

Except as noted, the test results for the methods and parameters listed on ACZ's current NELAC certificate letter (#ACZ) meet all requirements of NELAC.

This report shall be used or copied only in its entirety. ACZ is not responsible for the consequences arising from the use of a partial report.

All samples and sub-samples associated with this project will be disposed of after May 30, 2018. If the samples are determined to be hazardous, additional charges apply for disposal (typically $11/sample). If you would like the samples to be held longer than ACZ's stated policy or to be returned, please contact your Project Manager or Customer Service Representative for further details and associated costs. ACZ retains analytical raw data reports for ten years.

If you have any questions or other needs, please contact your Project Manager.

S. Habermehl

Scott Habermehl has reviewed
and approved this report.

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC1-1

ACZ Sample ID: ***L43559-01***
Date Sampled: *04/02/18 15:00*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 520 | 0.68 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 13:26 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 520 | 32.9 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 13:26 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 88.5 | | * | % | 0.1 | 0.5 | 04/09/18 16:11 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 8:50 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 9:07 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 10:15 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC1-2

ACZ Sample ID: ***L43559-02***
Date Sampled: *04/02/18 15:00*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 515 | 0.73 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 13:30 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 515 | 28.6 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 13:30 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 86.2 | | * | % | 0.1 | 0.5 | 04/09/18 17:19 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 8:53 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 9:28 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 10:19 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC2-1

ACZ Sample ID: ***L43559-03***
Date Sampled: *04/02/18 15:15*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 510 | 0.15 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 13:39 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 510 | 1.30 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 13:39 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 92.5 | | * | % | 0.1 | 0.5 | 04/09/18 18:27 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 8:57 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 10:30 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 10:23 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC2-2

ACZ Sample ID: ***L43559-04***
Date Sampled: *04/02/18 15:15*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 515 | 0.17 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 13:40 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 515 | 1.93 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 13:40 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 90.2 | | * | % | 0.1 | 0.5 | 04/09/18 19:35 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:01 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 10:51 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 10:27 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC3-1

ACZ Sample ID: ***L43559-05***
Date Sampled: *04/02/18 10:30*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 505 | 0.12 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 13:42 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 505 | 0.73 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 13:42 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 94.6 | | * | % | 0.1 | 0.5 | 04/09/18 20:43 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:04 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 11:11 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 10:31 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC3-2

ACZ Sample ID: ***L43559-06***
Date Sampled: *04/02/18 10:30*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 505 | 0.17 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 13:44 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 505 | 1.25 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 13:44 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 93.5 | | * | % | 0.1 | 0.5 | 04/09/18 21:51 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:08 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 11:32 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 10:35 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC4-1

ACZ Sample ID: ***L43559-07***
Date Sampled: *04/02/18 10:45*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 505 | 0.14 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 13:46 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 505 | 1.26 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 13:46 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 92.8 | | * | % | 0.1 | 0.5 | 04/09/18 22:59 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:12 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 11:53 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 10:39 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC4-2

ACZ Sample ID: ***L43559-08***
Date Sampled: *04/02/18 10:45*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 505 | 0.31 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 13:48 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 505 | 5.99 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 13:48 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 93.3 | | * | % | 0.1 | 0.5 | 04/10/18 0:06 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:15 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 12:14 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 10:43 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC5-1

ACZ Sample ID: ***L43559-09***
Date Sampled: *04/02/18 11:00*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 505 | 0.19 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 13:49 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 505 | 0.96 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 13:49 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 91.4 | | * | % | 0.1 | 0.5 | 04/10/18 1:14 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:19 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 12:34 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 10:47 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC5-2

ACZ Sample ID: ***L43559-10***
Date Sampled: *04/02/18 11:00*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 505 | 0.15 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 13:51 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 505 | 0.98 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 13:51 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 92.5 | | * | % | 0.1 | 0.5 | 04/10/18 2:22 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:23 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 12:55 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 10:51 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC6-1

ACZ Sample ID: ***L43559-11***
Date Sampled: *04/02/18 11:15*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 505 | 0.17 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 13:53 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 505 | 0.68 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 13:53 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 92.8 | | * | % | 0.1 | 0.5 | 04/10/18 3:30 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:26 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 13:16 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 10:55 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC6-2

ACZ Sample ID: ***L43559-12***
Date Sampled: *04/02/18 11:15*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 505 | 0.29 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 13:58 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 505 | 1.20 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 13:58 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 93.7 | | * | % | 0.1 | 0.5 | 04/10/18 4:38 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:30 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 13:37 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 10:59 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC7-1

ACZ Sample ID: ***L43559-13***
Date Sampled: *04/02/18 11:30*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 500 | 0.11 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 14:00 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 500 | 0.44 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 14:00 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 95.0 | | * | % | 0.1 | 0.5 | 04/10/18 5:46 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:34 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 13:57 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 11:03 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC7-2

ACZ Sample ID: ***L43559-14***
Date Sampled: *04/02/18 11:30*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 500 | 0.10 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 14:02 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 500 | 0.51 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 14:02 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 93.3 | | * | % | 0.1 | 0.5 | 04/10/18 6:54 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:37 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 14:18 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 11:07 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC8-1

ACZ Sample ID: ***L43559-15***
Date Sampled: *04/02/18 12:30*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 505 | 0.17 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 14:04 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 505 | 0.78 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 14:04 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 90.8 | | * | % | 0.1 | 0.5 | 04/10/18 8:02 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:41 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 14:39 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 11:11 | ajm |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC8-2

ACZ Sample ID: ***L43559-16***
Date Sampled: *04/02/18 12:30*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Metals Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Selenium, total (3050) | M6020 ICP-MS | 505 | 0.14 | | * | mg/Kg | 0.05 | 0.1 | 04/17/18 14:06 | bsu |
| Uranium, total (3050) | M6020 ICP-MS | 505 | 0.67 | | * | mg/Kg | 0.05 | 0.3 | 04/17/18 14:06 | bsu |

Soil Analysis

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Solids, Percent | D2216-80 | 1 | 92.3 | | * | % | 0.1 | 0.5 | 04/10/18 9:10 | ajm |

Soil Preparation

| Parameter | EPA Method | Dilution | Result | Qual | XQ | Units | MDL | PQL | Date | Analyst |
|---|---|---|---|---|---|---|---|---|---|---|
| Air Dry at 34 Degrees C | USDA No. 1, 1972 | | | | | | | | 04/09/18 9:45 | ajm |
| Digestion - Hot Plate | M3050B ICP-MS | | | | | | | | 04/12/18 15:00 | jlw |
| Sieve-2000 um (2.0mm) | ASA No.9, 15-4.2.2 | | | | | | | | 04/10/18 11:15 | ajm |

## Report Header Explanations

| | |
|---|---|
| *Batch* | A distinct set of samples analyzed at a specific time |
| *Found* | Value of the QC Type of interest |
| *Limit* | Upper limit for RPD, in %. |
| *Lower* | Lower Recovery Limit, in % (except for LCSS, mg/Kg) |
| *MDL* | Method Detection Limit. Same as Minimum Reporting Limit unless omitted or equal to the PQL (see comment #5). Allows for instrument and annual fluctuations. |
| *PCN/SCN* | A number assigned to reagents/standards to trace to the manufacturer's certificate of analysis |
| *PQL* | Practical Quantitation Limit. Synonymous with the EPA term "minimum level". |
| *QC* | True Value of the Control Sample or the amount added to the Spike |
| *Rec* | Recovered amount of the true value or spike added, in % (except for LCSS, mg/Kg) |
| *RPD* | Relative Percent Difference, calculation used for Duplicate QC Types |
| *Upper* | Upper Recovery Limit, in % (except for LCSS, mg/Kg) |
| *Sample* | Value of the Sample of interest |

## QC Sample Types

| | | | |
|---|---|---|---|
| *AS* | Analytical Spike (Post Digestion) | *LCSWD* | Laboratory Control Sample - Water Duplicate |
| *ASD* | Analytical Spike (Post Digestion) Duplicate | *LFB* | Laboratory Fortified Blank |
| *CCB* | Continuing Calibration Blank | *LFM* | Laboratory Fortified Matrix |
| *CCV* | Continuing Calibration Verification standard | *LFMD* | Laboratory Fortified Matrix Duplicate |
| *DUP* | Sample Duplicate | *LRB* | Laboratory Reagent Blank |
| *ICB* | Initial Calibration Blank | *MS* | Matrix Spike |
| *ICV* | Initial Calibration Verification standard | *MSD* | Matrix Spike Duplicate |
| *ICSAB* | Inter-element Correction Standard - A plus B solutions | *PBS* | Prep Blank - Soil |
| *LCSS* | Laboratory Control Sample - Soil | *PBW* | Prep Blank - Water |
| *LCSSD* | Laboratory Control Sample - Soil Duplicate | *PQV* | Practical Quantitation Verification standard |
| *LCSW* | Laboratory Control Sample - Water | *SDL* | Serial Dilution |

## QC Sample Type Explanations

| | |
|---|---|
| Blanks | Verifies that there is no or minimal contamination in the prep method or calibration procedure. |
| Control Samples | Verifies the accuracy of the method, including the prep procedure. |
| Duplicates | Verifies the precision of the instrument and/or method. |
| Spikes/Fortified Matrix | Determines sample matrix interferences, if any. |
| Standard | Verifies the validity of the calibration. |

## ACZ Qualifiers (Qual)

| | |
|---|---|
| B | Analyte concentration detected at a value between MDL and PQL. The associated value is an estimated quantity. |
| H | Analysis exceeded method hold time. pH is a field test with an immediate hold time. |
| L | Target analyte response was below the laboratory defined negative threshold. |
| U | The material was analyzed for, but was not detected above the level of the associated value. The associated value is either the sample quantitation limit or the sample detection limit. |

## Method References


| | |
|---|---|
| (1) | EPA 600/4-83-020. Methods for Chemical Analysis of Water and Wastes, March 1983. |
| (2) | EPA 600/R-93-100. Methods for the Determination of Inorganic Substances in Environmental Samples, August 1993. |
| (3) | EPA 600/R-94-111. Methods for the Determination of Metals in Environmental Samples - Supplement I, May 1994. |
| (4) | EPA SW-846. Test Methods for Evaluating Solid Waste. |
| (5) | Standard Methods for the Examination of Water and Wastewater. |


## Comments

| | |
|---|---|
| (1) | QC results calculated from raw data. Results may vary slightly if the rounded values are used in the calculations. |
| (2) | Soil, Sludge, and Plant matrices for Inorganic analyses are reported on a dry weight basis. |
| (3) | Animal matrices for Inorganic analyses are reported on an "as received" basis. |
| (4) | An asterisk in the "XQ" column indicates there is an extended qualifier and/or certification qualifier associated with the result. |
| (5) | If the MDL equals the PQL or the MDL column is omitted, the PQL is the reporting limit. |

For a complete list of ACZ's Extended Qualifiers, please click: http://www.acz.com/public/extquallist.pdf

**Alan Kuhn Associates LLC**

ACZ Project ID: ***L43559***

*NOTE: If the Rec% column is null, the high/low limits are in the same units as the result. If the Rec% column is not null, then the high/low limits are in % Rec.*

**Selenium, total (3050)** M6020 ICP-MS

| ACZ ID | Type | Analyzed | PCN/SCN | QC | Sample | Found | Units | Rec% | Lower | Upper | RPD | Limit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WG445528** | | | | | | | | | | | | | |
| WG445528ICV | ICV | 04/17/18 13:10 | MS180329-2 | .05 | | .04911 | mg/L | 98 | 90 | 110 | | | |
| WG445528ICB | ICB | 04/17/18 13:12 | | | | U | mg/L | | -0.0003 | 0.0003 | | | |
| WG445221PBS | PBS | 04/17/18 13:21 | | | | U | mg/Kg | | -0.15 | 0.15 | | | |
| WG445221LCSS | LCSS | 04/17/18 13:23 | PCN55863 | 117 | | 117.61 | mg/Kg | | 91.8 | 141 | | | |
| WG445221LCSSD | LCSSD | 04/17/18 13:25 | PCN55863 | 117 | | 118.42 | mg/Kg | | 91.8 | 141 | 1 | 20 | |
| L43559-02MS | MS | 04/17/18 13:32 | MS180321-2 | 12.887875 | .73 | 13.425 | mg/Kg | 99 | 75 | 125 | | | |
| L43559-02MSD | MSD | 04/17/18 13:37 | MS180321-2 | 12.887875 | .73 | 12.827 | mg/Kg | 94 | 75 | 125 | 5 | 20 | |

**Solids, Percent** D2216-80

| ACZ ID | Type | Analyzed | PCN/SCN | QC | Sample | Found | Units | Rec% | Lower | Upper | RPD | Limit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WG444935** | | | | | | | | | | | | | |
| WG444935PBS | PBS | 04/09/18 11:40 | | | | U | % | | -0.1 | 0.1 | | | |
| L43555-01DUP | DUP | 04/09/18 13:55 | | | 73.8 | 73.6 | % | | | | 0 | 20 | |

**Uranium, total (3050)** M6020 ICP-MS

| ACZ ID | Type | Analyzed | PCN/SCN | QC | Sample | Found | Units | Rec% | Lower | Upper | RPD | Limit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WG445528** | | | | | | | | | | | | | |
| WG445528ICV | ICV | 04/17/18 13:10 | MS180329-2 | .05 | | .04956 | mg/L | 99 | 90 | 110 | | | |
| WG445528ICB | ICB | 04/17/18 13:12 | | | | U | mg/L | | -0.0003 | 0.0003 | | | |
| WG445221PBS | PBS | 04/17/18 13:21 | | | | U | mg/Kg | | -0.15 | 0.15 | | | |
| WG445221LCSS | LCSS | 04/17/18 13:23 | PCN55863 | 109 | | 105.36 | mg/Kg | | 83 | 135 | | | |
| WG445221LCSSD | LCSSD | 04/17/18 13:25 | PCN55863 | 109 | | 107.95 | mg/Kg | | 83 | 135 | 2 | 20 | |
| L43559-02MS | MS | 04/17/18 13:32 | MS180321-2 | 12.875 | 28.6 | 29.887 | mg/Kg | 10 | 75 | 125 | | | M2 |
| L43559-02MSD | MSD | 04/17/18 13:37 | MS180321-2 | 12.875 | 28.6 | 32.046 | mg/Kg | 27 | 75 | 125 | 7 | 20 | M2 |

**Alan Kuhn Associates LLC** ACZ Project ID: ***L43559***

| ACZ ID | WORKNUM | PARAMETER | METHOD | QUAL | DESCRIPTION |
|---|---|---|---|---|---|
| **L43559-01** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-02** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-03** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-04** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-05** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-06** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-07** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-08** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-09** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-10** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-11** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |

**Alan Kuhn Associates LLC** ACZ Project ID: ***L43559***

| ACZ ID | WORKNUM | PARAMETER | METHOD | QUAL | DESCRIPTION |
|---|---|---|---|---|---|
| **L43559-12** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-13** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-14** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-15** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-16** | WG445528 | Selenium, total (3050) | M6020 ICP-MS | ZG | The ICP or ICP-MS Serial Dilution was not used for data validation because the sample concentration was less than 50 times the MDL. |
| | | Uranium, total (3050) | M6020 ICP-MS | M2 | Matrix spike recovery was low, the recovery of the associated control sample (LCS or LFB) was acceptable. |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC1-1
Locator:

ACZ Sample ID: ***L43559-01***
Date Sampled: *04/02/18 15:00*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 11 | 0.71 | 0.25 | pCi/g | * | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 11:08 | | 0.13 | 1.3 | 1.4 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC1-2
Locator:

ACZ Sample ID: ***L43559-02***
Date Sampled: *04/02/18 15:00*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 13 | 0.72 | 0.08 | pCi/g | * | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 11:08 | | 1.1 | 1.3 | 1.3 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC2-1
Locator:

ACZ Sample ID: ***L43559-03***
Date Sampled: *04/02/18 15:15*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 0.81 | 0.26 | 0.45 | pCi/g | * | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 11:08 | | 0.31 | 1.2 | 1.3 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC2-2
Locator:

ACZ Sample ID: ***L43559-04***
Date Sampled: *04/02/18 15:15*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 0.67 | 0.23 | 0.53 | pCi/g | * | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 11:08 | | 0.03 | 1.4 | 1.5 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC3-1
Locator:

ACZ Sample ID: ***L43559-05***
Date Sampled: *04/02/18 10:30*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 0.73 | 0.34 | 0.5 | pCi/g | * | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 11:08 | | 0.12 | 1.3 | 1.3 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC3-2
Locator:

ACZ Sample ID: ***L43559-06***
Date Sampled: *04/02/18 10:30*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 0.49 | 0.3 | 0.33 | pCi/g | * | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 11:08 | | 1.1 | 1.2 | 1.2 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC4-1
Locator:

ACZ Sample ID: ***L43559-07***
Date Sampled: *04/02/18 10:45*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 1.2 | 0.33 | 0.57 | pCi/g | * | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 11:08 | | -0.27 | 1.4 | 1.5 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC4-2
Locator:

ACZ Sample ID: ***L43559-08***
Date Sampled: *04/02/18 10:45*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 0.96 | 0.35 | 0.56 | pCi/g | * | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 11:08 | | 0.22 | 1.5 | 1.5 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC5-1
Locator:

ACZ Sample ID: ***L43559-09***
Date Sampled: *04/02/18 11:00*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 0.92 | 0.26 | 0.19 | pCi/g | * | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 11:08 | | 0.97 | 1.8 | 1.9 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC5-2
Locator:

ACZ Sample ID: ***L43559-10***
Date Sampled: *04/02/18 11:00*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 4.2 | 0.5 | 0.7 | pCi/g | * | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 13:28 | | 0.68 | 1.4 | 1.4 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC6-1
Locator:

ACZ Sample ID: ***L43559-11***
Date Sampled: *04/02/18 11:15*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 0.36 | 0.25 | 0.31 | pCi/g | | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 13:28 | | -0.24 | 1.1 | 1.2 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC6-2
Locator:

ACZ Sample ID: ***L43559-12***
Date Sampled: *04/02/18 11:15*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 2.2 | 0.35 | 0.5 | pCi/g | | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 13:28 | | -0.01 | 1.1 | 1.2 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC7-1
Locator:

ACZ Sample ID: ***L43559-13***
Date Sampled: *04/02/18 11:30*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 1.5 | 0.26 | 0.51 | pCi/g | | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 13:28 | | -0.76 | 1.2 | 1.3 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC7-2
Locator:

ACZ Sample ID: ***L43559-14***
Date Sampled: *04/02/18 11:30*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 0.74 | 0.24 | 0.32 | pCi/g | | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 13:28 | | 0.76 | 1.2 | 1.2 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC8-1
Locator:

ACZ Sample ID: ***L43559-15***
Date Sampled: *04/02/18 12:30*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 1.2 | 0.29 | 0.22 | pCi/g | | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 13:28 | | 0.43 | 1.4 | 1.5 | pCi/g | * | jlg |

**Alan Kuhn Associates LLC**
Project ID: AKA-ACZ-2018.1
Sample ID: SMC8-2
Locator:

ACZ Sample ID: ***L43559-16***
Date Sampled: *04/02/18 12:30*
Date Received: *04/05/18*
Sample Matrix: *Soil*

Radium 226 (3050) Prep Method:
M903.1

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 226 (3050) | 04/26/18 0:00 | | 1.1 | 0.3 | 0.18 | pCi/g | | leb |

Radium 228, 3050 Prep Method:
M904.0

| Parameter | Measure Date | Prep Date | Result | Error(+/-) | LLD | Units | XQ | Analyst |
|---|---|---|---|---|---|---|---|---|
| Radium 228, 3050 | 04/18/18 13:28 | | 1 | 1.3 | 1.4 | pCi/g | * | jlg |

## Report Header Explanations

| | |
|---|---|
| *Batch* | A distinct set of samples analyzed at a specific time |
| *Error(+/-)* | Calculated sample specific uncertainty |
| *Found* | Value of the QC Type of interest |
| *Limit* | Upper limit for RPD, in %. |
| *LCL* | Lower Control Limit, in % (except for LCSS, mg/Kg) |
| *LLD* | Calculated sample specific Lower Limit of Detection |
| *PCN/SCN* | A number assigned to reagents/standards to trace to the manufacturer's certificate of analysis |
| *PQL* | Practical Quantitation Limit |
| *QC* | True Value of the Control Sample or the amount added to the Spike |
| *Rec* | Amount of the true value or spike added recovered, in % (except for LCSS, mg/Kg) |
| *RER* | Relative Error Ratio, calculation used for Dup. QC taking into account the error factor. |
| *RPD* | Relative Percent Difference, calculation used for Duplicate QC Types |
| *UCL* | Upper Control Limit, in % (except for LCSS, mg/Kg) |
| *Sample* | Value of the Sample of interest |

## QC Sample Types

| | | | |
|---|---|---|---|
| *DUP* | Sample Duplicate | *MS/MSD* | Matrix Spike/Matrix Spike Duplicate |
| *LCSS* | Laboratory Control Sample - Soil | *PBS* | Prep Blank - Soil |
| *LCSW* | Laboratory Control Sample - Water | *PBW* | Prep Blank - Water |

## QC Sample Type Explanations

| | |
|---|---|
| Blanks | Verifies that there is no or minimal contamination in the prep method procedure. |
| Control Samples | Verifies the accuracy of the method, including the prep procedure. |
| Duplicates | Verifies the precision of the instrument and/or method. |
| Matrix Spikes | Determines sample matrix interferences, if any. |

## ACZ Qualifiers (Qual)

| | |
|---|---|
| H | Analysis exceeded method hold time. |

## Method Prefix Reference

| | |
|---|---|
| M | EPA methodology, including those under SDWA, CWA, and RCRA |
| SM | Standard Methods for the Examination of Water and Wastewater. |
| D | ASTM |
| RP | DOE |
| ESM | DOE/ESM |

## Comments

| | |
|---|---|
| (1) | Solid matrices are reported on a dry weight basis. |
| (2) | Preparation method: "Method" indicates preparation defined in analytical method. |
| (3) | QC results calculated from raw data. Results may vary slightly if the rounded values are used in the calculations. |
| (4) | An asterisk in the "XQ" column indicates there is an extended qualifier and/or certification qualifier associated with the result. |

For a complete list of ACZ's Extended Qualifiers, please click: http://www.acz.com/public/extquallist.pdf

**Alan Kuhn Associates LLC**

ACZ Project ID: ***L43559***

*NOTE: If the Rec% column is null, the high/low limits are in the same units as the result. If the Rec% column is not null, then the high/low limits are in % Rec.*

**Radium 226 (3050)** M903.1 **Units:** pCi/g

| ACZ ID | Type | Analyzed | PCN/SCN | QC | Sample | Error | LLD | Found | Error | LLD | Rec% | Lower | Upper | RPD/RER | Limit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WG446162** | | | | | | | | | | | | | | | | |
| L43559-04DUP | DUP-RER | 04/26/18 | | | 0.67 | 0.23 | 0.53 | 1.9 | 0.28 | 0.13 | | | | 3.39 | 2 | RC |
| WG445113PBS | PBS | 04/26/18 | | | | | | .14 | 0.18 | 0.15 | | | 0.3 | | | |
| WG445113LCSS | LCSS | 04/26/18 | PCN54812 | 40 | | | | 33 | 1.1 | 0.12 | 83 | 43 | 148 | | | |
| L43559-14MS | MS | 04/26/18 | PCN54812 | 40 | 0.74 | 0.24 | 0.32 | 34 | 1.2 | 0.2 | 83 | 43 | 148 | | | |
| L43559-08DUP | DUP-RER | 04/26/18 | | | 0.96 | 0.35 | 0.56 | .25 | 0.21 | 0.13 | | | | 1.74 | 2 | |

**Radium 228, 3050** M904.0 **Units:** pCi/g

| ACZ ID | Type | Analyzed | PCN/SCN | QC | Sample | Error | LLD | Found | Error | LLD | Rec% | Lower | Upper | RPD/RER | Limit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **WG445692** | | | | | | | | | | | | | | | | |
| WG445110PBS | PBS | 04/18/18 | | | | | | -.75 | 1.2 | 1.4 | | | 2.8 | | | |
| WG445110LCSS | LCSS | 04/18/18 | PCN53179 | 17.56 | | | | 17 | 2 | 1.3 | 97 | 47 | 123 | | | |
| L43559-08MS | MS | 04/18/18 | PCN53179 | 17.92 | 0.22 | 1.5 | 1.5 | 36 | 3.9 | 2.5 | 200 | 47 | 123 | | | M1 |
| L43559-14DUP | DUP-RER | 04/18/18 | | | 0.76 | 1.2 | 1.2 | -.22 | 1 | 1.1 | | | | 0.63 | 2 | |
| L43559-04DUP | DUP-RER | 04/18/18 | | | 0.03 | 1.4 | 1.5 | 1.1 | 1.1 | 1.1 | | | | 0.6 | 2 | |

**Alan Kuhn Associates LLC** ACZ Project ID: ***L43559***

| ACZ ID | WORKNUM | PARAMETER | METHOD | QUAL | DESCRIPTION |
|---|---|---|---|---|---|
| **L43559-01** | WG446162 | Radium 226 (3050) | M903.1 | RC | For a solid matrix, the matrix duplicate precision assessment (RPD or RER) exceeded the control limit, which is attributable to the non-homogeneity of the sample. |
| | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-02** | WG446162 | Radium 226 (3050) | M903.1 | RC | For a solid matrix, the matrix duplicate precision assessment (RPD or RER) exceeded the control limit, which is attributable to the non-homogeneity of the sample. |
| | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-03** | WG446162 | Radium 226 (3050) | M903.1 | RC | For a solid matrix, the matrix duplicate precision assessment (RPD or RER) exceeded the control limit, which is attributable to the non-homogeneity of the sample. |
| | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-04** | WG446162 | Radium 226 (3050) | M903.1 | RC | For a solid matrix, the matrix duplicate precision assessment (RPD or RER) exceeded the control limit, which is attributable to the non-homogeneity of the sample. |
| | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-05** | WG446162 | Radium 226 (3050) | M903.1 | RC | For a solid matrix, the matrix duplicate precision assessment (RPD or RER) exceeded the control limit, which is attributable to the non-homogeneity of the sample. |
| | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-06** | WG446162 | Radium 226 (3050) | M903.1 | RC | For a solid matrix, the matrix duplicate precision assessment (RPD or RER) exceeded the control limit, which is attributable to the non-homogeneity of the sample. |
| | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-07** | WG446162 | Radium 226 (3050) | M903.1 | RC | For a solid matrix, the matrix duplicate precision assessment (RPD or RER) exceeded the control limit, which is attributable to the non-homogeneity of the sample. |
| | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-08** | WG446162 | Radium 226 (3050) | M903.1 | RC | For a solid matrix, the matrix duplicate precision assessment (RPD or RER) exceeded the control limit, which is attributable to the non-homogeneity of the sample. |
| | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-09** | WG446162 | Radium 226 (3050) | M903.1 | RC | For a solid matrix, the matrix duplicate precision assessment (RPD or RER) exceeded the control limit, which is attributable to the non-homogeneity of the sample. |
| | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-10** | WG446162 | Radium 226 (3050) | M903.1 | RC | For a solid matrix, the matrix duplicate precision assessment (RPD or RER) exceeded the control limit, which is attributable to the non-homogeneity of the sample. |
| | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-11** | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-12** | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-13** | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |

**Alan Kuhn Associates LLC** ACZ Project ID: ***L43559***

| ACZ ID | WORKNUM | PARAMETER | METHOD | QUAL | DESCRIPTION |
|---|---|---|---|---|---|
| **L43559-14** | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-15** | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |
| **L43559-16** | WG445692 | Radium 228, 3050 | M904.0 | M1 | Matrix spike recovery was high, the recovery of the associated control sample (LCS or LFB) was acceptable. |

Radiochemistry

**The following parameters are not offered for certification or are not covered by NELAC certificate #ACZ.**

| | |
|---|---|
| Radium 228, 3050 | M904.0 |

Soil Analysis

**The following parameters are not offered for certification or are not covered by NELAC certificate #ACZ.**

| | |
|---|---|
| Solids, Percent | D2216-80 |

ACZ Laboratories, Inc.
2773 Downhill Drive Steamboat Springs, CO 80487 (800) 334-5493

# Sample Receipt

**Alan Kuhn Associates LLC**
AKA-ACZ-2018.1

ACZ Project ID: L43559
Date Received: 04/05/2018 10:42
Received By:
Date Printed: 4/6/2018

## Receipt Verification

| | YES | NO | NA |
|---|---|---|---|
| 1) Is a foreign soil permit included for applicable samples? | | | X |
| 2) Is the Chain of Custody form or other directive shipping papers present? | X | | |
| 3) Does this project require special handling procedures such as CLP protocol? | | X | |
| 4) Are any samples NRC licensable material? | | | X |
| 5) If samples are received past hold time, proceed with requested short hold time analyses? | X | | |
| 6) Is the Chain of Custody form complete and accurate? | X | | |
| 7) Were any changes made to the Chain of Custody form prior to ACZ receiving the samples? | X | | |

A change was made in the Page 1 Sampler's Name. Relinquished By. Page 2 Copy of Report to. Invoice to. Relinquished By Date:Time section prior to ACZ custody.

## Samples/Containers

| | YES | NO | NA |
|---|---|---|---|
| 8) Are all containers intact and with no leaks? | X | | |
| 9) Are all labels on containers and are they intact and legible? | X | | |
| 10) Do the sample labels and Chain of Custody form match for Sample ID, Date, and Time? | X | | |
| 11) For preserved bottle types, was the pH checked and within limits? [1] | | | X |
| 12) Is there sufficient sample volume to perform all requested work? | X | | |
| 13) Is the custody seal intact on all containers? | | | X |
| 14) Are samples that require zero headspace acceptable? | | | X |
| 15) Are all sample containers appropriate for analytical requirements? | X | | |
| 16) Is there an Hg-1631 trip blank present? | | | X |
| 17) Is there a VOA trip blank present? | | | X |
| 18) Were all samples received within hold time? | X | | |

NA indicates Not Applicable

## Chain of Custody Related Remarks

The 'Relinquished By' field on the COC was not completed. The project manager is contacting the client.

## Client Contact Remarks

## Shipping Containers

| Cooler Id | Temp(°C) | Temp Criteria(°C) | Rad(µR/Hr) | Custody Seal Intact? |
|---|---|---|---|---|
| 5350 | 15.5 | NA | 17 | N/A |
| NA28102 | 14.2 | NA | 13 | N/A |

ACZ Laboratories, Inc.
2773 Downhill Drive Steamboat Springs, CO 80487 (800) 334-5493

# Sample Receipt

**Alan Kuhn Associates LLC**
AKA-ACZ-2018.1

ACZ Project ID: L43559
Date Received: 04/05/2018 10:42
Received By:
Date Printed: 4/6/2018

Was ice present in the shipment container(s)?

No - Wet or gel ice was not present in the shipment container(s).

Client must contact an ACZ Project Manager if analysis should not proceed for samples received outside of their thermal preservation acceptance criteria.

[1] The preservation of the following bottle types is not checked at sample receipt: Orange (oil and grease), Purple (total cyanide), Pink (dissolved cyanide), Brown (arsenic speciation), Sterile (fecal coliform), EDTA (sulfite), HCl preserved vial (organics), Na2S2O3 preserved vial (organics), and HG-1631 (total/dissolved mercury by method 1631).

# ACZ Laboratories, Inc. L43559

2773 Downhill Drive Steamboat Springs, CO 80487 (800) 334-5493

## CHAIN of CUSTODY

**Report to:**

Name: Alan Kuhn
Company: Alan Kuhn Associates LLC
E-mail: akkuhn41@gmail.com
Address: 13212 Manitoba Dr NE
Albuquerque NM 87111
Telephone: 505 350 9188

**Copy of Report to:**

Name: Joe Lister
Company: Rio Grande Resources
E-mail: joel.lister@riogranderesources.com
Telephone: 505 287 7971

**Invoice to:**

Name: Alan Kuhn
Company: Alan Kuhn Associates
E-mail: akkuhn41@gmail.com
Address: 13212 Manitoba Dr NE
Albuquerque NM 87111
Telephone: 505 350 9188

**If sample(s) received past holding time (HT), or if insufficient HT remains to complete analysis before expiration, shall ACZ proceed with requested short HT analyses?** N/A YES [ ] NO [ ]

If "NO" then ACZ will contact client for further instruction. If neither "YES" nor "NO" is indicated, ACZ will proceed with the requested analyses, even if HT is expired, and data will be qualified

**Are samples for SDWA Compliance Monitoring?** Yes [ ] No [X]

**If yes, please include state forms. Results will be reported to PQL for Colorado.**

**Sampler's Name:** A. Kuhn **Sampler's Site Information** **State** NM **Zip code** 87020 **Time Zone** MDT

***Sampler's Signature:** Alan Kuhn

*"I attest to the authenticity and validity of this sample. I understand that intentionally mislabeling the time/date/location or tampering with the sample in anyway, is considered fraud and punishable by State Law.

**PROJECT INFORMATION**

Quote #:
PO#: AKA-ACZ-2018.1
Reporting state for compliance testing: NM
Check box if samples include NRC licensed material? NO

ANALYSES REQUESTED (attach list or use quote number)

| | SAMPLE IDENTIFICATION | DATE:TIME | Matrix | # of Containers | U | Ra | Sr |
|---|---|---|---|---|---|---|---|
| 1. | SMC1-1 | 4/2/18 1500 | Soil | 1 | | | |
| 2. | SMC1-2 | 4/2/18 1500 | | 1 | | | |
| 3. | SMC2-1 | 4/2/18 1515 | | 1 | | | |
| 4. | SMC2-2 | 4/2/18 1515 | | 1 | | | |
| 5. | SMC3-1 | 4/2/18 1030 | | 1 | | | |
| 6. | SMC3-2 | 4/2/18 1030 | | 1 | | | |
| 7. | SMC4-1 | 4/2/18 1045 | | 1 | | | |
| 8. | SMC4-2 | 4/2/18 1045 | | 1 | | | |
| 9. | SMC5-1 | 4/2/18 1100 | | 1 | | | |
| 10. | SMC5-2 | 4/2/18 1100 | | 1 | | | |

Matrix: SW (Surface Water) · GW (Ground Water) · WW (Waste Water) · DW (Drinking Water) · SL (Sludge) · SO (Soil) · OL (Oil) · Other (Specify)

**REMARKS**

Please refer to ACZ's terms & conditions located on the reverse side of this COC.

| RELINQUISHED BY: | DATE:TIME: | RECEIVED BY: | DATE:TIME |
|---|---|---|---|
| Alan Kuhn | 4/2/18 1530 | Bruce Wright | 4/2/18 3:30 P |
| ~~Bruce Wright~~ | ~~4/3/18 2:00 P~~ | | |
| | | | |

L43559 Chain of Custody

FORM-001R-08 01/30/08

White - Return with sample. Yellow - Retain for your records.

# ACZ Laboratories, Inc. L43559

2773 Downhill Drive Steamboat Springs, CO 80487 (800) 334-5493

## CHAIN of CUSTODY

**Report to:**

Name: Alan Kuhn
Company: Alan Kuhn Associates LLC
E-mail: akkuhn41@gmail.com
Address: 13212 Manitoba Drive NE
Albuquerque NM 87111
Telephone: 505-350-9155

**Copy of Report to:**

Name: Joe Lister
Company: Rio Grande Resources
E-mail: joel.lister@riogranderesources.com
Telephone: 505-237-7971

**Invoice to:**

Name: Alan Kuhn
Company: Alan Kuhn Associates LLC
E-mail: akkuhn41@gmail.com
Address: 13212 Manitoba Dr NE
Albuquerque NM 87111
Telephone: 505-350-9155

**If sample(s) received past holding time (HT), or if insufficient HT remains to complete analysis before expiration, shall ACZ proceed with requested short HT analyses?** N/A YES [ ] NO [ ]

If "NO" then ACZ will contact client for further instruction. If neither "YES" nor "NO" is indicated, ACZ will proceed with the requested analyses, even if HT is expired, and data will be qualified

**Are samples for SDWA Compliance Monitoring?** Yes [ ] No [X]

**If yes, please include state forms. Results will be reported to PQL for Colorado.**

**Sampler's Name:** A Kuhn **Sampler's Site Information** **State** NM **Zip code** 87020 **Time Zone** MDT

***Sampler's Signature:** Alan Kuhn

*I attest to the authenticity and validity of this sample. I understand that intentionally mislabeling the time/date/location or tampering with the sample in anyway, is considered fraud and punishable by State Law.

**PROJECT INFORMATION**

Quote #:
PO#: AKA-ACZ-2015.1
Reporting state for compliance testing: NM
Check box if samples include NRC licensed material? NO

**ANALYSES REQUESTED** *(attach list or use quote number)*

| | SAMPLE IDENTIFICATION | DATE:TIME | Matrix | # of Containers | V | Ra | Se | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 11. | SMC6-1 | 4/2/18 1115 | SO | | | | | | | | | | |
| 12. | SMC6-2 | 4/2/18 1115 | | | | | | | | | | | |
| 13. | SMC7-1 | 4/2/18 1130 | | | | | | | | | | | |
| 14. | SMC7-2 | 4/2/18 1130 | | | | | | | | | | | |
| 15. | SMC8-1 | 4/2/18 1230 | | | | | | | | | | | |
| 16. | SMC8-2 | 4/2/18 1230 | | | | | | | | | | | |

Matrix: SW (Surface Water) · GW (Ground Water) · WW (Waste Water) · DW (Drinking Water) · SL (Sludge) · SO (Soil) · OL (Oil) · Other (Specify)

**REMARKS**

Please refer to ACZ's terms & conditions located on the reverse side of this COC.

| RELINQUISHED BY: | DATE:TIME | RECEIVED BY: | DATE:TIME |
|---|---|---|---|
| Alan Kuhn | 4/2/18 1530 | Bruce Young | 4/3/18 330 |
| | | | |
| | | | |

ACZ Laboratories, Inc.
Steamboat Springs, CO 80487

(800) 334-5493

No ice

Project Number: L 43559

| Cooler Number | Cooler Tag |
|---|---|
| 1 | NA28102 10:43 04/05/18<br>Temp: 14.2 By: bce<br>Rad: 13 uR Seal: N/A |
| 2 | 5350 10:42 04/05/18<br>Temp: 15.5 By: bce<br>Rad: 17 uR Seal: N/A |
| 3 | |
| 4 | |
| 5 | |
| 6 | |
| 7 | |
| 8 | |
| 9 | |
| 10 | |

| Sample Number | Associated Cooler |
|---|---|
| 1 | 2 |
| 2 | 2 |
| 3 | 2 |
| 4 | 2 |
| 5 | 2 |
| 6 | 2 |
| 7 | 2 |
| 8 | 2 |
| 9 | 2 |
| 10 | 2 |
| 11 | 1 |
| 12 | 1 |
| 13 | 1 |
| 14 | 1 |
| 15 | 1 |
| 16 | 1 |
| 17 | |
| 18 | |
| 19 | |
| 20 | |

Log-In Order Verified:

Initials/Date: 4.5.18

**RGR Mt. Taylor Mine** Stan Fitch
**Gamma Radiation Survey** 4/25/2016
**Waste Pile North/East Delineation**

Instrument: Eberline PRM-7 #182, BKG = 10 µrem/h, readings waist high

| NAD 83 Datum | | | |
|---|---|---|---|
| Northing | Easting | Dose Rate µrem/h | Notes |
| 1578877 | 2782337 | 80 | NW Fence Corner - Car Shop yard |
| 1578747 | 2782327 | 70 | |
| 1578645 | 2782320 | 40 | |
| 1578544 | 2782314 | 30 | |
| 1578467 | 2782308 | 27 | SW Fence Corner - Car Shop yard |
| 1578363 | 2782303 | 20 | |
| 1578264 | 2782295 | 18 | |
| 1578163 | 2782287 | 15 | |
| 1578063 | 2782279 | 11 | |
| 1578062 | 2782181 | 12 | |
| 1578165 | 2782185 | 20 | |
| 1578263 | 2782188 | 30 | |
| 1578364 | 2782192 | 24 | |
| 1578450 | 2782200 | 36 | |
| 1578564 | 2782192 | 110 | |
| 1578675 | 2782197 | 80 | |
| 1578779 | 2782193 | 160 | |
| 1578880 | 2782192 | 150 | |
| 1578984 | 2782188 | 130 | |
| 1579038 | 2782202 | 40 | Fire Hydrant |
| 1579004 | 2782130 | 28 | South-Easterly Corner of Fan Shop |
| 1578882 | 2782090 | 115 | |
| 1578783 | 2782088 | 80 | |
| 1578683 | 2782081 | 100 | |
| 1578577 | 2782084 | 100 | |
| 1578500 | 2782082 | 100 | |
| 1578377 | 2782080 | 30 | |
| 1578276 | 2782081 | 40 | |
| 1578178 | 2782084 | 26 | |
| 1578179 | 2781985 | 110 | |
| 1578277 | 2781992 | 100 | |
| 1578043 | 2781993 | 18 | |
| 1578275 | 2782007 | 90 | |
| 1578373 | 2782012 | 50 | |
| 1578471 | 2782009 | 120 | |
| 1578571 | 2782006 | 110 | |
| 1578672 | 2782000 | 100 | |
| 1578772 | 2782000 | 80 | |
| 1578871 | 2782003 | 110 | |
| 1578917 | 2782011 | 50 | Shoulder of slope |
| 1578962 | 2782013 | 30 | Natural grade at foot of small hill |
| 1578973 | 2781898 | 28 | |
| 1578973 | 2781795 | 32 | |
| 1578974 | 2781700 | 44 | Inside of southerly end of stormwater pond |
| 1578914 | 2781717 | 120 | Drainage ditch, near toe |

**RGR Mt. Taylor Mine** Stan Fitch
**Gamma Radiation Survey** 4/25/2016
**Waste Pile North/East Delineation**

Instrument: Eberline PRM-7 #182, BKG = 10 µrem/h, readings waist high

| NAD 83 Datum | | | |
|---|---|---|---|
| Northing | Easting | Dose Rate µrem/h | Notes |
| 1578907 | 2781815 | 110 | Toe of waste pile (at drainage ditch) |
| 1578911 | 2781896 | 80 | Toe of waste pile (at drainage ditch) |
| 1578911 | 2781958 | 50 | Toe of waste pile (NE corner of pile) |
| 1578880 | 2781968 | 90 | Crown -- top of waste pile slope, NE corner |
| 1578864 | 2781901 | 110 | Crown -- top of waste pile slope |
| 1578862 | 2781801 | 110 | Crown -- top of waste pile slope |
| 1578836 | 2781702 | 120 | Crown -- top of waste pile slope, NW corner |
| 1578776 | 2781682 | 100 | Crown -- top of waste pile slope |
| 1578765 | 2781795 | 125 | |
| 1578771 | 2781900 | 110 | |
| 1578670 | 2781901 | 80 | |
| 1578565 | 2781900 | 80 | |
| 1578470 | 2781902 | 50 | |
| 1578369 | 2781900 | 50 | |
| 1578252 | 2781899 | 60 | |

**Environmental Restoration Group, Inc.**
8809 Washington St NE, Suite 150
Albuquerque, NM 87113
ph: (505) 298-4224
www.ERGoffice.com

| TECHNICAL MEMORANDUM | |
|---|---|
| **To**: Bruce Norquist (RGR) | **Date**: July 06, 2020 |
| **From**: Randy Whicker (ERG) | **Project**: Mt. Taylor Mine |
| **Direct**: 970-556-1174 | **Task(s)**: Site closeout/closure Support |
| **Cc**: Chuck Farr (ERG) | |
| **Subject**: Radiological survey results for discharge pipeline and soils along pipeline corridor. | |

Dear Mr. Norquist,

This Technical Memorandum provides the results of radiological surveys of the discharge pipeline and underlying/adjacent soils at the Rio Grande Resources (RGR) Mt. Taylor Mine near San Mateo, New Mexico. This work was conducted June 23-24, 2020 to support mine closeout/closure activities.

Please let me know if you have questions or need more information.

Regards,



*Randy Whicker, CHP*
*Radiation Safety Officer*
*Mt. Taylor Mine*

Environmental Restoration Group, Inc.
8809 Washington St. NE, Suite 150
Albuquerque, NM 87113
Email: RandyWhicker@ergoffice.com

# Radiological Surveys of Discharge Pipeline

## Contents

1. INTRODUCTION ..... 1
2. CLEARANCE CRITERIA ..... 2
   2.1 Pipeline Materials and Equipment ..... 2
   2.2 Pipeline Corridor and Outfall Soils/Sediments ..... 3
3. METHODS ..... 4
4. PIPELINE MATERIALS SURVEY RESULTS ..... 5
   4.1 Pipeline Location 1 ..... 5
   4.2 Pipeline Location 2 ..... 6
   4.3 Pipeline Location 3 ..... 7
   4.4 Pipeline Location 4 ..... 8
   4.5 Pipeline Location 5 ..... 9
5. PIPELINE CORRIDOR GAMMA SURVEY RESULTS ..... 10
6. CONCLUSIONS ..... 11
7. REFERENCES ..... 11

### Figures

Figure 1: Mine features within operationally Controlled Areas at the Site (left) and the 4.3 mile pipeline for conveyance of treated mine water for discharge at Outfall 001 in San Lucas Canyon under DP-61 (right). Locations for interior/exterior measurements of radiological properties of steel pipeline materials are also shown (right). ..... 1

Figure 2: Gamma survey results with detail insets to identify areas of small, localized hotspots that may require some relatively minor soil cleanup to meet the radiological criteria for release to the post remediation land use (PRLU). ..... 10

### Tables

Table 1: Surface activity screening levels for clearance of materials and equipment (adapted from ANSI/HPS, 2013) ..... 2

Table 2A: Alpha/beta surface activity measurement results for pipeline survey Location 1. ..... 5

Table 2B: Gamma emission data and radionuclide activity concentrations for residual solids at pipeline survey Location 1. ..... 5

Table 3A: Alpha/beta surface activity measurement results for pipeline survey Location 2. ..... 6

Table 3B: Gamma emission data and radionuclide activity concentrations for residual solids at pipeline survey Location 2. ..... 6

Table 4A: Alpha/beta surface activity measurement results for pipeline survey Location 3. ..... 7

Table 4B: Gamma emission data and radionuclide activity concentrations for residual solids at pipeline survey Location 3. ..... 7

Table 5A: Alpha/beta surface activity measurement results for pipeline survey Location 4. ..... 8

Table 5B: Gamma emission data and radionuclide activity concentrations for residual solids at pipeline survey Location 4. ..... 8

Table 6A: Alpha/beta surface activity measurement results for pipeline survey Location 5. ..... 9

Table 6B: Gamma emission data and radionuclide activity concentrations for residual solids at pipeline survey Location 5. ..... 9

## 1. INTRODUCTION

The Mt. Taylor Mine (Site) is a former underground uranium mine in Cibola County near the town of San Mateo, New Mexico. Owned and operated by Rio Grande Resources (RGR), the Site is situated at the foot of Mount Taylor, an extinct volcano. Gulf Mineral Resources Company (Gulf) acquired the property and began mine development in 1971. Ore production occurred between 1979 – 1982, and after a transfer of ownership to Chevron Resources Company (Chevron) in 1985, production resumed through 1990. RGR acquired the mine and other Chevron property in 1991. In 1999 the Mine entered standby status under Mine Permit C1002RE with MMD. On December 29, 2017, the permit changed to an active status, and on December 3, 2019, RGR notified MMD of intentions to begin the Site closeout/closure process.

Discharge permit DP-61 with the New Mexico Environment Department (NMED) was first issued to Gulf in 1979. Mine water was treated to meet applicable water quality standards prior to conveyance through a pipeline and surface discharge at Outfall 001 located 4.3 miles north of the Site in San Lucas Canyon (Figure 1). RGR intends to dismantle and remove the pipeline and remediate any impacted soils along the pipeline corridor, along with impacted sediments at Outfall 001 in the San Lucas Canyon drainage.





**Figure 1: Mine features within operationally Controlled Areas at the Site (left) and the 4.3 mile pipeline for conveyance of treated mine water for discharge at Outfall 001 in San Lucas Canyon under DP-61 (right). Locations for interior/exterior measurements of radiological properties of steel pipeline materials are also shown (right).**

Once dismantled and removed, the disposition of steel pipeline materials is dependent on the radiological condition of the material. The status of land areas along the pipeline corridor depends on the magnitude and extent of any radiological impacts to soils underlying and adjacent to the pipeline. This Technical Memorandum provides the results of radiological field screening measurements for pipeline materials (interior and exterior surfaces of steel piping material) at five (5) representative locations along the 4.3 mile length of the discharge pipeline (Figure 1), along with continuous GPS-based gamma scans adjacent to the pipeline to characterize terrestrial gamma radiation emissions from soils along the pipeline corridor.

Characterization survey results are presented in this report and values compared to applicable criteria for clearance or release from current radiological and regulatory controls on these mine-related features. The objective of these surveys was to help inform decisions on the future disposition of pipeline materials and infrastructure, and to estimate the extent of soil remediation that may be required along the pipeline corridor to meet Mine reclamation and closure objectives as specified in the *Mt. Taylor Mine Closeout/Closure Plan* (RGR, 2013).

## 2. CLEARANCE CRITERIA

### *2.1 Pipeline Materials and Equipment*

The clearance criteria for surface radioactivity levels on pipeline walls and volumetric criteria for loose sediments or scales are based on a national standard published jointly by the American National Standards Institute (ANSI) and the Health Physics Society (ANSI/HPS, 2013). More stringent than the U.S. Nuclear Regulatory Commission's criteria for unrestricted release of materials and equipment (M/E) from uranium recovery facilities (NRC, 2002), the ANSI/HPS standard is designed to protect human health by limiting potential radiological doses from future use of the M/E to a de-minimis value of 1 millirem (mrem)/year.

Clearance in the ANSI/HPS standard is defined as "the removal of items or materials that contain or *may* contain residual levels of radioactive materials within authorized practices from further radiological control for radiation protection purposes." This standard applies to the clearance of M/E from areas controlled to protect individuals from exposure to radiation or radioactive material during or after operations. This dose-based standard provides derived screening levels for surface and volume radioactivity. The derived screening levels that apply are presented in Table 1.

**Table 1: Surface activity screening levels for clearance of materials and equipment (adapted from ANSI/HPS, 2013).**

| Radionuclide Group | Surface Activity Limit | Volumetric Concentration Limit |
|---|---|---|
| *Group 1:* $^{Nat}$U, $^{Nat}$Th, and associated decay products: Pb210, Po210, Ra226, Ra228, Th228, Th230 | 600 dpm/100 $cm^2$ | 3 pCi/g |

The surface activity limit in Table 1 can be partitioned into alpha and beta components for the uranium and thorium decay series as follows:

The uranium decay series has 14 particles emitted, with 8 alphas (57%) and 6 betas (43%)
The thorium decay series has 12 particles emitted, with 7 alphas. (58%) and 5 betas (42%)

Since it is unknown what mixture of primordial decay series radionuclides may be present in any surface contamination on M/E at the Site, it is conservative to assume that all alpha emissions are from uranium decay series radionuclides only and an equivalent alpha screening level, assuming secular equilibrium between all uranium decay series radionuclides, is as follows:

600 dpm / 100 $cm^2$ * (0.57 α dpm/total dpm) ≈ **340 dpm α / 100 $cm^2$**

A similar calculation for beta activity gives a conservative beta screening level of 252 dpm β / 100 $cm^2$, a value that is well below the minimum detectable activity (MDA) achievable with a one-minute static count (the count time needed to meet an MDA of 250 dpm β / 100 $cm^2$ is on the order of 20-25 minutes). Given the need for a screening level that is practical to measure in the field, a screening level for alpha activity of 340 dpm/100 $cm^2$ will be used as the primary criterion for determination of compliance with the total surface activity clearance limit given in Table 1. In addition, a maximum alpha reading equivalent to 10 times the screening level (3,400 dpm α / 100 $cm^2$) for any single measurement (a secondary "hotspot" criterion) will be applied for consistency with related specifications in the ANSI/HPS standard. Individual items may be grouped into similar types of M/E to represent a "survey unit", and alpha readings within each survey unit may be used to determine compliance with both the average and hotspot alpha screening levels.

Because the ANSI clearance criteria in Table 1 were derived from a conservative receptor dose assessment that assumed infinite plane source term conditions (ANSI/HPS, 1999; Annex B), the averaging approach described above is consistent with regulatory guidance for comparison against clearance criteria as provided in MARSAME, the *Multi-Agency Radiation Survey and Assessment of Materials and Equipment Manual* (NRC, 2009). In other words, if a receptor were exposed to all M/E within a survey unit where average and maximum surface alpha activities are below respective alpha screening levels, the potential radiological dose to a receptor is conservatively assumed to be less than the de-minimis 1 mrem/year radiation dose limit specified in the ANSI/HPS standard.

If the average for the survey unit is below the primary alpha screening level, and no single measurement is greater than the secondary alpha hotspot criterion, then all M/E within the survey unit can be released from further radiological controls on the future disposition of the M/E. These criteria do not apply to offsite disposal as commercial disposal facilities may have their own radiological acceptance criteria and approved characterization methods for waste profiling. Pipeline materials that do not meet these clearance criteria will be flagged for either decontamination efforts, or for onsite disposal in the engineered waste disposal cell or offsite at an approved industrial waste disposal facility.

## *2.2 Pipeline Corridor and Outfall Soils/Sediments*

With respect to land areas along the pipeline corridor and the San Lucas Canyon drainage below discharge Outfall 001, the release criterion for surface soil or sediment (0-15 cm) is equivalent to a Ra-226 concentration of 5 pCi/g above background based on the "*Joint Guidance for the Cleanup and Reclamation*

*of Existing Uranium Mining Operations in New Mexico*" from the Mining and Minerals Division (MMD) and the Mining Environmental and Compliance Section of the New Mexico Environment Department (NMED) (MMD/NMED, 2016). The approved background Ra-226 concentration for the Site is 1.8 pCi/g, giving a total (gross) release criterion of 6.8 pCi/g of Ra-226. In addition, the "*Joint Guidance*" from MMD/NMED describes an additional criterion for ambient gamma radiation called the "post reclamation radiation level" (PRRL). As determined in RGR's "*Work Plan for Post-Mining Radiological Surveys of Permit Area and Impacted Lands Mount Taylor Mine*" (RGR, 2020a), the PRRL for the Mount Taylor Site is equivalent to a gamma exposure rate of 24.5 micro-roentgen per hour (µR/hr). If surface soils along the pipeline corridor or sediments at Outfall 001 have Ra-226 concentrations below 6.8 pCi/g, and ambient gamma exposure rates are below 24.5 µR/hr, respective land areas can be released for the Post-Mining Land Use (PMLU) as described in the *Joint Guidance* (MMD/NMED, 2016). Otherwise, soil excavation will be required until these release criteria are achieved.

## 3. METHODS

The methods used for the radiological characterization measurements and gamma surveys along the pipeline were based on applicable standard operating procedures (SOPs) provided in the Radiation Protection Program (RPP) Manual for the Mt. Taylor Mine (RGR, 2020b), including:

- SOP-2: Instrument Testing and Calibration
- SOP-3: Radiological Contamination Surveys
- SOP-7: GPS-based Gamma Radiation Surveys
- SOP-8: Soil Sampling for Radiometric Analysis

Total alpha and beta surface radioactivity levels were measured on June 24, 2020 at multiple systematic locations (top, bottom and sides) both inside and outside accessible portions of the pipeline walls at each of the locations shown in Figure 1. In order to access the interior of the pipeline at each location, a welding torch was used to cut a hole through the steel pipeline walls approximately 2 feet in diameter. Swipe (smear) samples were collected at each measurement location to evaluate readily removable surface activity. Gamma exposure rates were also measured inside of the pipeline (center and bottom). Samples of scale/sediment accumulated in the bottom of the pipeline were sampled, then screened onsite to estimate Ra-226 levels based on gross gamma readings inside of a lead-shielded, low-background counting well. These samples were then sent offsite to a qualified commercial laboratory for quantitative determination of U-nat, Th-230, Ra-226, and Pb-210 concentrations.

All field measurement data were recorded in the field logbook. Swipe samples for removable surface activity were measured in the radiation control office and recorded. Instrument quality control (QC) measurements were taken and documented to ensure proper instrument function. Photos were taken of the interior/exterior of the pipeline at each sampling/measurement location. GPS-based gamma transects were walked parallel to the pipeline just adjacent to the pipe and about 5 meters away from the pipeline. Gamma readings were manually monitored while scanning, and locations with evidence of elevated readings (above apparent background) were investigated further with additional scans to identify the outer bounds of potential radiological impacts to soil related to the pipeline.

## 4. PIPELINE MATERIALS SURVEY RESULTS

The results of alpha/beta surface activity and gamma emission measurements, along with sampling of loose residual solids (scale/sediments) inside the pipeline, are presented in the following Subsections for the five representative pipeline survey locations shown in Figure 1.

### *4.1 Pipeline Location 1*

**Table 2A: Alpha/beta surface activity measurement results for pipeline survey Location 1.**

| Pipeline Location 1 | Total Alpha Activity (DPM/100 cm²) | Total Beta Activity (DPM/100 cm²) | Removable Alpha Activity (DPM/100 cm²) | Removable Beta Activity (DPM/100 cm²) |
|---|---|---|---|---|
| Clearance Criterion | 340 | 252 | N/A* | N/A* |
| Ambient Background | 2 | 345 | 0 | 92 |
| **Measurement Point** | **Net (above background) Surface Activity** | | | |
| Outside Top | 944 | 2080 | 6 | 0 |
| Outside East | 367 | 1220 | 17 | 0 |
| Outside West | 33 | 11560 | 0 | 0 |
| Outside Bottom | 378 | 1220 | 17 | 0 |
| Inside Top | 122 | 1240 | 6 | 0 |
| Inside East | 133 | 1860 | 0 | 0 |
| Inside West | 44 | 1960 | 17 | 0 |
| Inside Bottom | 33 | 3480 | 0 | 0 |

*Removable activity criteria not applicable under the ANSI/HPS standard. NRC's release criterion for removable natural uranium in equilibrium with its decay progeny is 1,000 DPM/100 cm² (NRC, 2002).

| |
|---|
| ≤ clearance criterion |
| > clearance criterion |





**Table 2B: Gamma emission data and radionuclide activity concentrations for residual solids at pipeline survey Location 1.**

| Gamma Exposure Rate (µR/h) | | Residual Solids Concentration (pCi/g) | |
|---|---|---|---|
| Outside Background | 16 | Ra-226* | 118 |
| Interior Center | 38 | Ra-226 | 125 |
| Interior Bottom | 75 | U-nat** | 139 |
| | | Th-230 | 24.1 |
| | | Pb-210 | 27.6 |

*Screening-level estimate from shielded onsite sample counting
** Analytical result from offsite lab = 206 mg/kg

## *4.2 Pipeline Location 2*

**Table 3A: Alpha/beta surface activity measurement results for pipeline survey Location 2.**

| Pipeline Location 2 | Total Alpha Activity (DPM/100 cm²) | Total Beta Activity (DPM/100 cm²) | Removable Alpha Activity (DPM/100 cm²) | Removable Beta Activity (DPM/100 cm²) |
|---|---|---|---|---|
| Clearance Criterion | 340 | 252 | N/A* | N/A* |
| Ambient Background | 2 | 382 | 0 | 92 |
| **Measurement Point** | **Net (above background) Surface Activity** | | | |
| Outside Top | 944 | 3100 | 6 | 114 |
| Outside East | 211 | 760 | 0 | 0 |
| Outside West | 356 | 1480 | 11 | 0 |
| Outside Bottom | 89 | 13760 | 6 | 0 |
| Inside Top | 89 | 5200 | 0 | 0 |
| Inside East | 456 | 6740 | 17 | 14 |
| Inside West | 4656 | 138560 | 139 | 443 |
| Inside Bottom | 2456 | 86900 | 44 | 57 |

*Removable activity criteria are not applied under the ANSI/HPS standard. NRC's release criterion for removable natural uranium in equilibrium with its decay progeny is 1,000 DPM/100 cm² (NRC, 2002).

| |
|---|
| ≤ clearance criterion |
| > clearance criterion |






**Table 3B: Gamma emission data and radionuclide activity concentrations for residual solids at pipeline survey Location 2.**

| Gamma Exposure Rate (µR/h) | | Residual Solids Concentration (pCi/g) | |
|---|---|---|---|
| Outside Background | 17 | Ra-226* | 524 |
| Interior Center | 60 | Ra-226 | 529 |
| Interior Bottom | 100 | U-nat** | 290 |
| | | Th-230 | 31.6 |
| | | Pb-210 | 91.3 |

*Screening-level estimate from shielded onsite sample counting
** Analytical result from offsite lab = 428 mg/kg







## *4.3 Pipeline Location 3*

**Table 4A: Alpha/beta surface activity measurement results for pipeline survey Location 3.**

| Pipeline Location 3 | Total Alpha Activity (DPM/100 cm²) | Total Beta Activity (DPM/100 cm²) | Removable Alpha Activity (DPM/100 cm²) | Removable Beta Activity (DPM/100 cm²) |
|---|---|---|---|---|
| Clearance Criterion | 340 | 252 | N/A* | N/A* |
| Ambient Background | 3 | 319 | 0 | 92 |
| **Measurement Point** | **Net (above background) Surface Activity** | | | |
| Outside Top | 911 | 3000 | 17 | 29 |
| Outside East | 211 | 620 | 6 | 0 |
| Outside West | 378 | 1160 | 17 | 0 |
| Outside Bottom | 78 | 7080 | 6 | 0 |
| Inside Top | 600 | 7320 | 17 | 0 |
| Inside East | 1400 | 12420 | 39 | 143 |
| Inside West | 444 | 4420 | 33 | 0 |
| Inside Bottom | 2700 | 61320 | 44 | 0 |

*Removable activity criteria are not applied under the ANSI/HPS standard. NRC's release criterion for removable natural uranium in equilibrium with its decay progeny is 1,000 DPM/100 cm² (NRC, 2002).

| |
|---|
| ≤ clearance criterion |
| > clearance criterion |






**Table 4B: Gamma emission data and radionuclide activity concentrations for residual solids at pipeline survey Location 3.**

| Gamma Exposure Rate (µR/h) | | Residual Solids Concentration (pCi/g) | |
|---|---|---|---|
| Outside Background | 15 | Ra-226* | 340 |
| Interior Center | 39 | Ra-226 | 316 |
| Interior Bottom | 90 | U-nat** | 170 |
| | | Th-230 | 16.2 |
| | | Pb-210 | 62.8 |

*Screening-level estimate from shielded onsite sample counting
** Analytical result from offsite lab = 251 mg/kg







## *4.4 Pipeline Location 4*

**Table 5A: Alpha/beta surface activity measurement results for pipeline survey Location 4.**

| Pipeline Location 4 | Total Alpha Activity (DPM/100 cm²) | Total Beta Activity (DPM/100 cm²) | Removable Alpha Activity (DPM/100 cm²) | Removable Beta Activity (DPM/100 cm²) |
|---|---|---|---|---|
| Clearance Criterion | 340 | 252 | N/A* | N/A* |
| Ambient Background | 8 | 337 | 0 | 92 |
| **Measurement Point** | **Net (above background) Surface Activity** | | | |
| Outside Top | 822 | 2880 | 28 | 0 |
| Outside East | 344 | 1080 | 6 | 0 |
| Outside West | 500 | 2040 | 6 | 0 |
| Outside Bottom | N/A | N/A | N/A | N/A |
| Inside Top | 356 | 5360 | 0 | 0 |
| Inside East | 167 | 7500 | 22 | 0 |
| Inside West | 0 | 3920 | 22 | 0 |
| Inside Bottom | 89 | 12920 | 0 | 129 |

*Removable activity criteria are not applied under the ANSI/HPS standard. NRC's release criterion for removable natural uranium in equilibrium with its decay progeny is 1,000 DPM/100 cm² (NRC, 2002).

| |
|---|
| ≤ clearance criterion |
| > clearance criterion |





**Table 5B: Gamma emission data and radionuclide activity concentrations for residual solids at pipeline survey Location 4.**

| Gamma Exposure Rate (µR/h) | | Residual Solids Concentration (pCi/g) | |
|---|---|---|---|
| Outside Background | 17 | Ra-226* | 253 |
| Interior Center | 45 | Ra-226 | 247 |
| Interior Bottom | 100 | U-nat** | 159 |
| | | Th-230 | 7.7 |
| | | Pb-210 | 41.4 |

*Screening-level estimate from shielded onsite sample counting
** Analytical result from offsite lab = 235 mg/kg







## *4.5 Pipeline Location 5*

**Table 6A: Alpha/beta surface activity measurement results for pipeline survey Location 5.**

| Pipeline Location 5 | Total Alpha Activity (DPM/100 cm²) | Total Beta Activity (DPM/100 cm²) | Removable Alpha Activity (DPM/100 cm²) | Removable Beta Activity (DPM/100 cm²) |
|---|---|---|---|---|
| Clearance Criterion | 340 | 252 | N/A* | N/A* |
| Ambient Background | 4 | 317 | 0 | 92 |
| **Measurement Point** | **Net (above background) Surface Activity** | | | |
| Outside Top | 1144 | 3220 | 6 | 57 |
| Outside East | 378 | 120 | 17 | 57 |
| Outside West | 256 | 1100 | 11 | 0 |
| Outside Bottom | 11 | 6200 | 11 | 0 |
| Inside Top | 1900 | 10280 | 28 | 386 |
| Inside East | 1800 | 7680 | 39 | 29 |
| Inside West | 156 | 3320 | 100 | 100 |
| Inside Bottom | 989 | 16160 | 6 | 0 |

*Removable activity criteria are not applied under the ANSI/HPS standard. NRC's release criterion for removable natural uranium in equilibrium with its decay progeny is 1,000 DPM/100 cm² (NRC, 2002).

| |
|---|
| ≤ clearance criterion |
| > clearance criterion |




**Table 6B: Gamma emission data and radionuclide activity concentrations for residual solids at pipeline survey Location 5.**

| Gamma Exposure Rate (µR/h) | | Residual Solids Concentration (pCi/g) | |
|---|---|---|---|
| Outside Background | 15 | Ra-226* | 314 |
| Interior Center | 30 | Ra-226 | 306 |
| Interior Bottom | 70 | U-nat** | 64.3 |
| | | Th-230 | 8.6 |
| | | Pb-210 | 98.3 |

*Screening-level estimate from shielded onsite sample counting
**Analytical result from offsite lab = 95 mg/kg










## 5. PIPELINE CORRIDOR GAMMA SURVEY RESULTS

The gamma survey of the pipeline corridor indicates that the vast majority of soils underlying and adjacent to the discharge pipeline have terrestrial gamma emissions consistent with local background conditions (Figure 2). Approximately 7 small, localized areas of elevated gamma radiation, indicative of radiological impacts to surface soils due to historic pipeline operations, are present at various discrete locations along the corridor as depicted by the white boxes in Figure 2. Gamma exposure rate readings for six of these small "hotspots" are shown in closer detail in the insets to Figure 2. These results suggest that the volume of contaminated soil that may require excavation and removal to release pipeline corridor lands to the PRLU as described in the Mine Closeout/Closure Plan (RGR, 2013), is likely to be relatively small, perhaps a few tens to a few hundreds of cubic yards of material that may be contaminated in excess of the 6.8 pCi/g release criterion for Ra-226 concentrations in soil.





**Figure 2: Gamma survey results with detail insets to identify areas of small, localized hotspots that may require some relatively minor soil cleanup to meet the radiological criteria for release to the post remediation land use (PRLU).**

## 6. CONCLUSIONS

The results of the pipeline materials surveys (Section 4) indicate that in general, radiological impacts to the steel pipe along the length of the pipeline corridor exceed conservative, ANSI/HPS criteria for clearance from future radiological controls on access or reuse. Therefore, the options for future disposition of the pipeline materials are currently limited to 1) decontamination until the release criteria are met, or 2) onsite disposal in the engineered waste disposal cell or offsite disposal at an appropriate industrial waste disposal facility.

With respect to radiological impacts to soils, the gamma survey data suggest that spills or leaks were limited and the extent of impacts to soil that may require remediation are relatively small, perhaps involving excavation and removal of a few tens to a few hundreds of cubic yards of material. Removal of these small hotspots should result in compliance with the radiological soil release criteria specified in Section 2 along the entire length of the pipeline (including impacted sediments in the San Lucas drainage below Outfall 001 under DP-61).

## 7. REFERENCES

American National Standards Institute/Health Physics Society (ANSI/HPS). 1999. *American National Standard - Surface and Volume Radioactivity Standards for Clearance.* ANSI/HPS N13.12-1999. Health Physics Society, McLean, VA. August 31, 2013.

American National Standards Institute/Health Physics Society (ANSI/HPS). 2013. American National Standard - Surface and Volume Radioactivity Standards for Clearance. ANSI/HPS N13.12-2013. Health Physics Society, McLean, VA. May 6, 2013.

Mining and Minerals Division, New Mexico Environment Department (MMD/NMED). 2016. Joint Guidance for the Cleanup and Reclamation of Existing Uranium Mining Operations in New Mexico. March 2016.

Rio Grande Resources Corporation (RGR). 2013. Mt. Taylor Mine Closeout/Closure Plan. Existing Mine Permit #C1002RE and Discharge Permit DP-61. November 2013.

Rio Grande Resources Corp. (RGR). 2020a. Work Plan for Post-Mining Radiological Surveys of Permit Area and Impacted Lands Mount Taylor Mine. June 8, 2020.

Rio Grande Resources (RGR). 2020b. Radiation Protection Program Manual, Mount Tylor Mine, Cibola County, New Mexico. Revision 4. May 22, 2020.

U.S. Nuclear Regulatory Commission (NRC). 2002. Health Physics Surveys in Uranium Recovery Facilities. NRC Regulatory Guide 8.30 (Revision 1).

U.S. Nuclear Regulatory Commission (NRC). 2009. Multi-Agency Radiation Survey and Assessment of Materials and Equipment Manual. Supplement 1 to NUREG 1575.

# Surface and Subsurface Soil Radiologic Characterization

## Windblown Area, Ore Pad Area and Mine Compound

## Mount Taylor Mine Site

## San Mateo, NM


**Prepared by:**

**AVM Environmental Services, Inc.**

**1717 Del Norte Blvd.**

**Grants, NM 87020**


**Prepared for:**

**Rio Grande Resource Corporation**

**PO Box 1150**

**Grants, NM 87020**

**August 14, 2023**

## Table of Contents

1.0 Introduction and Background ..... 1
2.0 Previous Characterization ..... 1
3.0 Objective of the Radiologic Characterization ..... 2
4.0 Field Investigation ..... 2
4.1 Surface Gamma Radiation Scan and Static Survey ..... 2
4.2 Ra-226 Radiation Cleanup Criteria Contamination Boundary ..... 4
4.3 Test Pits, Soil Sampling and Ex-Situ Gamma Radiation Soil Screening ..... 4
4.4 Windblown Area Characterization Summary ..... 6
4.5 Ore Pad Area Characterization Summary ..... 6
4.6 Mine Compound Area Characterization Summary ..... 7
5.0 Soil Sampling and Analysis ..... 7
6.0 Quality Assurance and Quality Control Measures ..... 8

## Tables

Table 1 Typical Gamma Scan Data Exported from Scan System Data Logger
Table 2 Static Surface Gamma Radiation Survey at Soil Sampling/Test Pit Locations
Table 3 Windblown Area Surface and Subsurface Soil Sample Field Ex-Situ Gamma Screening and Vendor Laboratory Results Summary
Table 4 Ore Pad Area Subsurface Soil Sample Field Ex-Situ Gamma Screening and Vendor Laboratory Results Summary
Table 5 Mine Compound Area Subsurface Soil Sample Field Ex-Situ Gamma Screening and Vendor Laboratory Results Summary
Table 6 Subsurface Ra-226 Contamination Depth Summary

## Figures

Figure 1 Soil Radiologic Characterization Areas
Figure 2 Windblown Area and Ore Pad Area Soil Sample/Test Pit Locations and April 2023 Surface Gamma Scan Survey
Figure 3 Mine Compound Area Soil Sample/Test Pit Locations and April 2023 Surface Gamma Scan Survey
Figure 4 Windblown Area Surface Soil Ra-226 6.8 pCi/g Release Criteria Contamination Boundary
Figure 5 Mine Compound Subsurface Ra-226 Contamination Profile at Test Pit Locations.

## Appendices

Appendix A Surface Gamma Radiation Static Survey Forms
Appendix B Surface and Subsurface Contamination Field Investigation Documentation (Soil Sample Log Forms, Field Soil Sample Ex-Situ Gamma Radiation Screening Forms Soil Sample COCs and Laboratory Analytical Result Reports)
Appendix C Radiologic Instrument Calibration and Operational Function Check and Collimated Detector Correlation Documentation

## 1.0 Introduction and Background

This report provides the results of the Soil Radiologic Characterization (SRC) that was conducted at the Mt. Taylor Mine (Site) in Cibola County, near San Mateo, New Mexico. This SRC was performed to evaluate the lateral and vertical extent of radiologic contamination exceeding the Site Radiation Cleanup Criteria (RCC) of 6.8 pCi/g Ra-226 to estimate radiologic impacted material volumes within three specified areas of the Site; the Windblown Area, Ore Pad Area and portions of the Mine Compound Area, also known as the "Service and Support area". The methods and procedures used were consistent with the June 2020 Work Plan for Post-Mining Radiological Surveys of Permit Area and Impacted Lands (2020 Work Plan) and the applicable survey methods described in the Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM, EPA 2000a). The RCC specified in the March 2016 *Joint Guidance for the Cleanup and Reclamation of Existing Uranium Mining Operations in New Mexico* (EMNRD, 2016) (2016 Guidance) by the Energy, Minerals & Natural Resources Department (EMNRD) and the New Mexico Environment Department (NMED) was used for the investigation level (IL). The Ra-226 cleanup criteria of 5.0 pCi/g above the background level in land averaged over 100 square meters in surface soil (top six inches) specified in the Joint Guidance is taken from the UMTRCA (40 CFR 192) regulation, which is based on an unrestricted land use exposure scenario. A 6.8 pCi/g Ra-226 IL (5.0 pCi/g plus 1.8 pCi/g background level) has been established for the Site.

The Site was an underground uranium mine located in Cibola County, near San Mateo, New Mexico. The mine was developed by Gulf Mineral Resources Company (Gulf) in the 1970s and ore production occurred from 1979 to 1982. Following transfer of Site to Chevron Resources Company in 1985, the ore production resumed and continued until 1990. Rio Grande Resources (RGR) acquired the Site in 1991. In 1999 the Site entered standby status under Mine Permit C1002RE with EMNRD. On December 29, 2017, the permit changed to an active status, and on December 3, 2019, RGR notified MMD of intentions to begin the Site closeout/closure process. The following sections describe the strategy, methods and procedures that were used and the results of the SRC conducted at the Site.

## 2.0 Previous Characterization

Surface gamma radiation surveys were performed periodically within operationally controlled areas of the Site to monitor changes in radiological conditions during a period of remedial excavations in the Mine Water Treatment Unit (MWTU) ponds, construction of the disposal cell and placement of contaminated mine materials, and gradual removal of ore from the ore stockpile. The most recent gamma survey prior to this characterization, conducted March 27, 2021, showed elevated gamma radiation levels in certain operational areas within the Controlled Area boundaries, including the three areas included in this SRC, the Windblown Area, Ore Pad Area and the Mine Compound Area. The survey results are summarized in The June 2020 Work Plan, and indicate surface soils in portions of the Windblown Area, the Mine Compound and the entire Ore Pad Area exceed the 6.8 pCi/g Ra-226 IL.

Additionally, a radiologic subsurface soil investigation was performed in a portion of the Mine Compound Area as part of the 2020 Diesel Investigation. The results are summarized in the Mount Taylor Mine, Diesel Release Investigation Report of Finding, April 2021, Ensero Solutions, Inc. (Ensero 2021). The soil borings sample results within the Mine Compound Area indicate Ra-226 levels exceeding the IL in subsurface soils ranging from a depth of ground surface to 10 feet below ground surface (bgs) in the area around the Production Shaft.

## 3.0 Objective of the Radiological Characterization

The Site is a former uranium mine, therefore the surface and subsurface soil is expected to be impacted by radionuclides associated with the uranium decay series, with Ra-226 being the primary Constituent of Concern (COC). The objective of this characterization is to evaluate Ra-226 contamination exceeding the Site IL of 6.8 pCi/g Ra-226 in surface and subsurface soils to estimate volumes of radiologic impacted material within the Windblown, Ore Pad and Mine Compound Areas.

## 4.0 Field Investigation

Field investigations for this characterization were conducted consistent with the 2020 Work Plan and were conducted during the period of April 11, 2023 through June 14, 2023. The three specified soil characterization areas are shown in Figure 1. The field investigations included, both static 0.5 inch thick lead (Pb) collimated and uncollimated (bare) 2x2 sodium iodide (NaI) detector gamma radiologic survey measurements and Differential Global Positioning System (DGPS) based bare detector gamma scan surveys, along with ex-situ soil screening, soil sampling and offsite vendor laboratory analysis. The geo-located gamma scans were conducted to provide Ra-226 concentration level estimates in surface soil and to determine the test pit and sampling locations to assess subsurface radiologic contamination relative to the IL. Ex-situ gamma radiation soil screening was performed to provide real-time information to estimate subsurface contamination depths. Subsurface soil sampling and offsite vendor laboratory analysis was performed to confirm subsurface contamination depths below the IL as estimated by field ex-situ gamma radiation soil screening. Additionally, gamma radiation static surveys count per minute (cpm) measurements, exposure rate (µR/hr) measurements and surface soil samples and analysis were performed at selected locations to update the Site-specific correlation.

### 4.1 Surface Gamma Radiation Scan and Static Survey

The instrument configuration for direct gamma radiation level measurements during this characterization consisted of lead collimated and bare 2x2 NaI scintillation detectors (Eberline SPA-3 or Ludlum 44-10) for detection of gamma radiation, coupled to a scaler/rate meter (Ludlum 2221 or Ludlum 2241). This instrument configuration is used widely for this type of survey and is recommended by the MARSSIM. The scaler/rate meters were interfaced with a sub-meter accurate DGPS with surveying software and a data

logger/controller for electronically recording the gamma radiation levels to the corresponding geo-location coordinates. The coordinate system that was used for this work was the State Plane Coordinate System (NAD83, New Mexico West, US Feet) system. Direct gamma radiation surveys using a NaI scintillation detector provide radiation levels in counts per unit time, generally obtained as cpm. A Ludlum Model 19 µR Meter was used for gamma exposure rate (µR/hr) measurements.

During this characterization, systematic gamma radiation scan surveys using bare 2x2 NaI detectors were performed at the Site to determine the level of Ra-226 in surface soil within the characterization areas. Although bare detectors do not avoid lateral gamma radiation shine, bare detectors have a large field of view and provide a large scan coverage area for an efficient and conservative lateral extent of contamination assessment. The gamma scan surveys were performed consistent with the 2020 Work Plan. Thirty-feet spaced geo-projected transects for each area were digitally created using mapping software and loaded on the field data logger/controller. Based on a conservative field of view (FOV) of at least six feet diameter for a bare 2x2 NaI detector for Ra-226 gamma radiations, a scanning transects spacing of 30 feet would provide at least a 20% scan coverage. The gamma scan survey was performed by scanning along these transects with a bare 2x2 NaI detector at 12 inches above the ground surface at a scan rate of about three feet per second, with a data collection time interval of two seconds.

The geo-located gamma scan data includes the gamma scan point ID, date and time, location coordinates, and bare detector gamma cpm. The scan data was exported from the data logger and the bare detector cpm were converted to equivalent Ra-226 estimate using the Site-specific correlation (Ra-226 pCi/g = 0.0005 x CPM)-7.3228 $R^2$ = 0.97)(2020 Work Plan). The scan data was mapped using a mapping software, arranged in color coded ranges and then reviewed to identify areas that exceeded the IL. The color-coded range was structured to include the Ra-226 6.8 pCi/g IL as shown in Figures 2 and 3. The characterization gamma scan survey included approximately 12,107 gamma scan data points within a total of approximately 40 acres at the Site. The gamma scan data was exported from the scan system data logger into an Excel file. The detector cpm was converted into equivalent estimated surface soil Ra-226 concentration in pCi/g using the Site-specific correlation for bare detectors as discussed in Section 4.5 of the 2020 Work Plan. A typical gamma scan data export table from the scan system data logger is shown in Table 1. Gamma scan survey data for this characterization are provided in electronic file.

One-minute static gamma radiation surveys were performed prior to collecting a soil sample at each surface soil sampling and test pit location using a bare 2x2 NaI detector and collimated 2x2 NaI detector. The survey data were recorded on Static Gamma Radiation Survey Forms, which are included in Appendix A. The bare detector cpm data was converted to equivalent Ra-226 estimate using the Site-specific correlation. A site-specific correlation for a 2x2 NaI 0.5-inch thick lead collimated detector was developed using the surface (0 – 6 Inch) soil samples collected from the Windblown Area and the co-located collimated detector survey performed during this characterization, which is included in Appendix C. This correlation regression yielded an equation of Ra=226 = (CPM x 0.0016) – 8.41 with an acceptable $R^2$ value

of 0.83 The collimated detector measurements were converted to soil Ra-226 concentrations using this correlation equation. The static gamma survey results are summarized in Table 2.

### 4.2 Ra-226 Radiation Cleanup Criteria Contamination Boundary

The Windblown area Ra-226 6.8 pCi/g RCC contamination boundary delineated based on the surface gamma scan survey and a 6.8 pCi/g Ra-226 RCC contamination boundary based on the surface soil sample ex-situ screening and vendor laboratory results are shown in Figure 4. The ex-situ and vendor lab Ra-226 pCi/g surface soil sample results are lower than the Ra-226 pCi/g concentrations estimated by the bare 2x2 NaI detector surface soil gamma scan. Based on the results of the soil sample analysis and static gamma radiation surveys, the area of the Windblown Area that exceeds the IL is smaller than previously estimated by bare detector gamma scan surveys alone, as shown in Figure 4. The primary cause of the overestimated Ra-226 concentrations in the Windblown Area determined by the bare detector gamma scan survey appears to be the lateral gamma radiation shine interference from nearby areas with elevated Ra-226 concentrations, specifically the close proximity to the Ore Pad Area. As discussed previously, one-minute static gamma radiation level measurements were performed prior to collecting a soil sample at each location using a bare and a 0.5 inch lead collimated 2x2 NaI detector. As shown in Tables 2 and 3, the Ra-226 concentration estimates determined using the collimated detector are comparable to the on-Site ex-situ gamma screening and the vendor laboratory Ra-226 analytical results. Thus, delineation of the Windblown Area surface soils exceeding the 6.8 pCi/g Ra-226 IL using the collimated static gamma survey, the on-Site ex-situ gamma screening and the vendor laboratory Ra-226 analytical results are appropriate, as shown in Figure 4.

As shown in Tables 2 and 4, and Figure 2 the entire Ore Pad Area surface soil far exceeds the 6.8 pCi/g Ra-226 IL. Additionally, surface soil gamma scans previously performed in 2018 and 2020 (2020 Work Plan) for area exposure rates (µR/hr) included the Mine Compound Area and showed that the majority of the Mine Compound Area exceeds the IL. As shown in Figure 3, the surface gamma scan performed during this characterization also shows that the surface soil in the majority of the Mine Compound Area exceeds the 6.8 pCi/g Ra-226 IL. To better characterize the surface soil and to assist in the selection of test pit locations, the surface gamma scan survey was performed at a higher density, 30-feet transect spacing, compared to the previous scan (2021) density of 60-ft transect spacing.

### 4.3 Test Pits, Soil Sampling and Ex-Situ Gamma Radiation Soil Screening

Test pit trench excavations, subsurface soil sampling and on-Site ex-situ gamma radiation soil screening were performed from May 17 through June 7, 2023. These methods were used to determine the subsurface soil Ra-226 contamination depth exceeding the IL at the test pit locations within the three characterization areas. The ex-situ gamma radiation soil screening was conducted to provide a real-time estimate of Ra-226 concentrations in subsurface soil samples. This method is more reliable than the in-situ

direct gamma radiation level measurements and allows for real-time Ra-226 concentration assessments. The on-Site ex-situ soil screening method consists of selectively measuring the 609 KeV region gamma radiations of Bi-214, a decay product of Ra-226. A single channel analyzer (Ludlum L2221) integrated with a Ludlum 44-20 3x3 NaI scintillation detector was used to measure the 609 keV energy peak region of Bi-214. The soil sample was placed around the plastic lined detector in a heavily lead shielded counting chamber. The heavily shielded counting chamber lowers the system background counts, thus improving the system's minimum detectable concentration (MDC). A reference soil with the Ra-226 concentration of 6.6 pCi/g, comparable to the 6.8 pCi/g IL, was prepared as described in Appendix C and was used for soil screening during this characterization. The 6.6 pCi/g reference soil provides a conservative estimate of Ra-226 concentration in samples below the IL.

A total of 12 locations were selected in the Windblown Area for surface and subsurface soil sampling in areas that exceeded the IL determined by the surface soil gamma scan survey, as shown in Figure 2. Twenty-eight test pit locations were selected for subsurface soil sampling based on the surface soil gamma scan survey and Site operational history where Ra-226 contamination was likely to be deeper than one-foot bgs, twenty test pits in the Mine Compound Area and eight in the Ore Pad Area, as shown in Figures 2 and 3.

Hand augers and sampling trowels were used to collect surface and subsurface soil samples up to a depth of 1.5 feet in the Windblown Area. At each of the 11 sample locations selected in the Windblown Area, a surface (0 – 6”) and a subsurface (1’ – 1.5’) soil sample were collected. At one location, a sample was collected at 0-1” and 2"-6” depths for surface soils Ra-226 contamination distribution analysis. A backhoe was used to excavate a trench at each selected test pit location for subsurface soil sample collection in the Ore Pad and Mine Compound areas. The trenches were excavated at approximately one-to-two-foot depth intervals depending on visual observations of the type and consistency of the soil. At each interval, a subsurface soil sample was collected from the base of the excavation for ex-situ soil screening. The excavation continued at least 2 feet after native soil was observed and on-Site ex-situ soil screening indicated Ra-226 concentrations were below the 6.8 pCi/g IL. The test pit excavation soil sample logs and the field soil screening forms are included in Appendix B. The test pit subsurface soil ex-situ gamma screening data is summarized in Tables 3, 4 and 5, which includes Ra-226 concentrations of the samples relative to the 6.8 pCi/g IL.

Although the primary objective of the ex-situ gamma radiation soil screening was to determine the Ra-226 concentrations above or below the 6.8 pCi/g IL, Ra-226 concentrations were estimated in all test pit excavation subsurface soil samples collected and screened. During the setup of the soil screening system prior to mobilizing in the field, a calibration/correlation of the ex-situ soil screening system was performed using a 6.6 pCi/g, a 25 pCi/g and a 50 pCi/g reference soil. This correlation is included in Appendix C. The estimated Ra-226 concentration of the subsurface soil samples determined using this correlation are included in Tables 3, 4 and 5.

Fourteen samples out of a total of 24 surface and subsurface soil samples screened on-Site from the Windblown Area were sent to the off-Site vendor laboratory, Energy Laboratories, in Casper, WY. From the Ore Pad and Mine Compound Areas, 34 samples out of a total of 88 subsurface soil samples screened onsite were sent to the off-site vendor laboratory. These soil samples were analyzed for Ra-226 using EPA Method 901.1 (modified for soil matrix) for confirmation of the on-Site ex-situ soil screening results. The 53 samples sent to the laboratory included at least one sample from each test pit excavation that screened below the IL. Also, 10% (5 samples) of the samples sent to the lab were split in the field and sent to the lab for quality assurance/quality control (QA/QC) duplicates. The laboratory results reports are included in Appendix B and are summarized in Table 3, 4 and 5. As shown in these tables, the estimated Ra-226 levels by on-Site ex-situ soil screening are comparable with the laboratory Ra-226 results, specifically in regard to determining the depth of Ra-226 levels above or below the IL.

### 4.4 Windblown Area Characterization Summary

As shown in Table 3 and Table 6, 11 of the 12 surface soil (0 – 6”) samples from the Windblown Area screened on-Site and analyzed by the vendor laboratory show Ra-226 pCi/g below the 6.8 pCi/g IL. The only location above the IL was WBSB-08 at 9.7 pCi/g. The Ra-226 concentration in all of the Windblown Area subsurface samples screened on-Site and analyzed by the vendor laboratory show Ra-226 pCi/g concentrations below the Ra-226 6.8 pCi/g IL, which is far below the Ra-226 15 pCi/g 2016 Guidance for 6-inch soil layers six inches bgs. This demonstrates that the Ra-226 levels exceeding the IL are contained only within the surface soil (0 – 6”) in the Windblown area, as shown in Figure 4 and Table 3. Furthermore, analyzing the 0-1” and 2”-6” soil samples resulted in Ra-226 concentrations of 2.0 pCi/g in the 0-1” sample and 1.0 pCi/g in the 2”-6” sample. Based upon the lab results in the Windblown area, the majority of the contamination is distributed within the top one inch of soil.

### 4.5 Ore Pad Area Characterization Summary

Results of test pit excavation observations and subsurface soil sampling analysis in the Ore Pad Area show waste rock depth from surface level to the native soil at approximately three to five feet bgs at four (OPSB-02, OPSB-03, OPSB-04 and OPSB-05) out of the five selected test pit locations, as shown in Table 4 and 6. The on-Site ex-situ gamma screening results show Ra-226 concentrations ranging from about 22 to 510 pCi/g as shown in Table 4. At test pit location OPSB-01, waste rock was observed at depths greater than five feet. A thin dark clay layer was observed at about five feet bgs. Excavation continued as light gray waste rock material and debris was constantly observed to a depth of 13.5 feet bgs, the excavation depth limit of the trenching equipment. The on-Site ex-situ gamma screening results show a Ra-226 concentration in the 0 to 13 feet composite sample from this location at 74 pCi/g, and 31 pCi/g Ra-226 in the sample from a depth of 13.5 feet. Since waste rock depth at all other test pit locations in the Ore Pad Area was approximately four to five feet, three additional test pits were excavated east of OPSB-01 to determine the

extent of waste rock depth in the area. Test pit locations OPSB-06 and OPSB-07 were selected at approximately 150' and 100' east of OPSB-01, respectively. Both of these test pits showed waste rock depths of approximately 4' bgs before observing native soil. Test pit location OPSB-08 was selected approximately 62' east of OPSB-01 and showed a waste rock and debris depth similar to that of OPSB-01. According to Site operational history, a portion of the nearby treatment pond may have been backfilled with low grade waste rock and used as part of the foundation for the Ore Pad Area. The waste rock depth in the OPSB-01 area is estimated to be about 15 feet bgs based on the nearby ore-pad runoff retention pond depth.

### 4.6 Mine Compound Area Characterization Summary

Results of test pit excavation observations and subsurface soil sampling analysis in the Mine Compound Area show subsurface soil exceeding the 6.8 pCi/g Ra-226 IL at varying depths ranging from ground surface to about seven feet bgs as shown in Tables 5 and 6 and Figure 5. Soil exceeding the IL is generally limited to only the surface soil (<1.0 feet) in the areas around test pit locations MCSB-04, MCSB-10, MCSB-12, MCSB-13, MCSB-14, MCSB-15, MCSB-16, MCSB-17 and MCSB-18. At the other nine test pit locations, soil/ material depths bgs exceeding the IL are shown in Table 6, except at test pit locations MCSB-02 and MCSB-05. Test pits MCSB-02 and MCSB-05 had an isolated layer of soil/gravel that exceeded the IL while the soil above and below the layer screened below the IL. At test pit location MCSB-02, soil exceeding the IL was found in a gravel layer at a depth of 3.5 to 4.5 feet bgs, while at a depth of 5.5 to 6.5 feet bgs at test pit location MCSB-05, as shown in Tables 5 and 6, and Figure 5. At each test pit location, when native soil was observed, excavation continued into the native soil at least two feet to ensure that the soil/material exceeding the IL had been identified. Two additional observation test pit excavations up to nine feet were performed at locations MCSB-19 and MCSB-20. These two test pits are located east of locations MCSB-08 and MCSB-11, between the shop yard fence and the road. The purpose of these two observational test pit excavations was to estimate the lateral extent of subsurface waste rock material found at locations MCSB-08 and MCSB-11. Identification of any waste rock material was noted by visual observation. No waste rock material was observed in test pit MCSB-19, east of Test Pit MCSB-08. A thin (approximately 3") layer of waste rock material at a depth of 2.0 to 2.25' was observed in Test Pit MCSB-20, indicating that the lateral extent boundary of subsurface waste rock material is between MCSB-11 and the shop yard fence line. Based on the field soil screening and the laboratory sample results, depths of Ra-226 concentrations above the 6.8 pCi/g IL at each Ore Pad and Mine Compound Area test pit and Windblown Area sampling location are summarized in Table 6.

## 5.0 Soil Sampling and Analysis

Soil samples from the Windblown Area and subsurface soil samples from the test pit excavations collected for on-Site ex-situ gamma radiation soil screening were collected consistent with the 2020 Work Plan. Field QA/QC duplicate samples were split at a frequency of 10% of the total number of soil samples collected. A total of 112 surface and subsurface soil samples were collected during this characterization. Field sampling

equipment used for soil sampling included: stainless steel scoops, bowls, spoons, and hand auger barrels were decontaminated between sample locations. The soil sampling equipment decontamination was conducted by brushing off loose visible soil and wiped with clean towels. Excavator buckets were cleaned by removing any loose, visible soil. Any soils excavated from the test pits were returned to the test pit excavations from which the soil came. Personal protection equipment (PPE), such as gloves, were brushed off and scanned for residual contamination and were disposed of.

Surface and subsurface soil samples were analyzed by on-Site ex-situ gamma radiation soil screening (AVM SOP-4) to estimate Ra-226 concentrations. A completed Chain-of-Custody (COC) along with the surface soil samples and confirmatory soil samples were placed in labeled Ziploc bags, and packaged in coolers with sealed lids and shipped to Energy Laboratories, Inc for Ra-226 analysis. The soil samples were analyzed for Ra-226 with a reporting limit of 0.5 pCi/g, using EPA Method 901.1 (modified for soil matrix). The completed COCs are included with the analytical results reports in Appendix B.

## 6. 0 Quality Assurance and Quality Control Measures

QA/QC measures were implemented during this characterization to ensure that decisions were made based on data of acceptable quality. All radiologic survey instruments have been calibrated at least annually. Additionally, operational functions checks were performed on all radiologic instruments daily prior to use. The calibration and function check documents are included in Appendix C. During this characterization, no instruments were found to be out of calibration or inoperable as indicated by the operational function checks. The instrument background measurements for bare 2x2 NaI detectors during daily operational function checks were less than 10,000 cpm as shown in Appendix C. The bare detector field of view (FOV) at 12 inches above the ground surface is conservatively assumed at an area of six feet diameter. The 2x2 NaI detector response factor is determined to be 0.0005 pCi/g/cpm from the linear regression for the Site-specific correlation included in Appendix C. Based on the above detector parameters, the Ra-226 minimum detectable concentrations (MDCs) for a scan survey at a scan speed of three feet per second, calculated using MARSSIM guidance, were less than 1.0 pCi/g, which is significantly less than 50% of the 6.8 pCi/g IL. The ex-situ soil gamma radiation screening system was calibrated prior to mobilization in the field and daily operational function checks were performed prior to use. The calibration and function check documentation are included in Appendix C. Based on the highest system background (blank) measurements from daily operational function checks and efficiency (pCi/g/cpm), the highest Ra-226 MDC for the screening system calculated was less than 0.8 pCi/g, significantly less than the 6.8 pCi/g IL. The MDCs during the supplemental characterization met the QA objective.

The QA/QC measures also included field QA/QC duplicate soil sampling at a frequency of 10% of the soil samples collected for laboratory analysis. As discussed above, field QA/QC duplicate soil samples were collected and sent to the laboratory for analysis, and the QA/QC duplicate results are included in appropriate summary tables.

# Tables

**Table 1**
**Typical Gamma Scan Data Exported from the Scan System Data Logger**

| ID | Time | Northing(1) (feet) | Easting(1) (feet) | MSL Elevation (feet) | CPM 2x2 Bare NaI Detector | Ra-226 pCi/g(2) | Zone_ID |
|---|---|---|---|---|---|---|---|
| 1 | 4/11/2023 12:58 | 1579644.59 | 2782922.79 | 7350 | 37181 | 11.27 | Mine_Compound |
| 2 | 4/11/2023 12:58 | 1579644.55 | 2782925.05 | 7350 | 35699 | 10.53 | Mine_Compound |
| 3 | 4/11/2023 12:58 | 1579644.42 | 2782929.34 | 7350 | 34119 | 9.74 | Mine_Compound |
| 4 | 4/11/2023 12:58 | 1579644.62 | 2782934.44 | 7350 | 33580 | 9.47 | Mine_Compound |
| 5 | 4/11/2023 12:58 | 1579645.02 | 2782938.58 | 7350 | 36088 | 10.72 | Mine_Compound |
| 6 | 4/11/2023 12:58 | 1579644.99 | 2782943.19 | 7350 | 36656 | 11.01 | Mine_Compound |
| 7 | 4/11/2023 12:58 | 1579643.77 | 2782946.70 | 7350 | 38855 | 12.11 | Mine_Compound |
| 8 | 4/11/2023 12:58 | 1579643.87 | 2782947.05 | 7350 | 35564 | 10.46 | Mine_Compound |
| 9 | 4/11/2023 12:58 | 1579644.03 | 2782950.60 | 7350 | 37249 | 11.30 | Mine_Compound |
| 10 | 4/11/2023 12:58 | 1579645.17 | 2782955.46 | 7351 | 34818 | 10.09 | Mine_Compound |
| 11 | 4/11/2023 12:58 | 1579644.44 | 2782960.55 | 7350 | 33211 | 9.29 | Mine_Compound |
| 12 | 4/11/2023 12:58 | 1579644.36 | 2782966.24 | 7350 | 35848 | 10.60 | Mine_Compound |
| 13 | 4/11/2023 12:58 | 1579645.40 | 2782971.43 | 7351 | 44480 | 14.92 | Mine_Compound |
| 14 | 4/11/2023 12:58 | 1579644.95 | 2782976.50 | 7351 | 40445 | 12.90 | Mine_Compound |
| 15 | 4/11/2023 12:59 | 1579644.04 | 2782981.35 | 7351 | 38310 | 11.84 | Mine_Compound |
| 16 | 4/11/2023 12:59 | 1579644.89 | 2782986.75 | 7351 | 34757 | 10.06 | Mine_Compound |
| 17 | 4/11/2023 12:59 | 1579645.26 | 2782992.08 | 7351 | 35607 | 10.48 | Mine_Compound |
| 18 | 4/11/2023 12:59 | 1579645.28 | 2782997.28 | 7351 | 34693 | 10.03 | Mine_Compound |
| 19 | 4/11/2023 12:59 | 1579644.62 | 2783002.45 | 7352 | 31665 | 8.51 | Mine_Compound |
| 20 | 4/11/2023 12:59 | 1579644.26 | 2783008.07 | 7352 | 34754 | 10.06 | Mine_Compound |
| 21 | 4/11/2023 12:59 | 1579644.42 | 2783013.72 | 7352 | 32487 | 8.92 | Mine_Compound |
| 22 | 4/11/2023 12:59 | 1579645.39 | 2783019.31 | 7352 | 31633 | 8.50 | Mine_Compound |
| 23 | 4/11/2023 12:59 | 1579645.34 | 2783024.97 | 7352 | 35967 | 10.66 | Mine_Compound |
| 24 | 4/11/2023 12:59 | 1579645.52 | 2783030.66 | 7352 | 40738 | 13.05 | Mine_Compound |
| 25 | 4/11/2023 12:59 | 1579644.54 | 2783036.55 | 7352 | 44013 | 14.69 | Mine_Compound |
| 26 | 4/11/2023 12:59 | 1579643.73 | 2783042.37 | 7353 | 43985 | 14.67 | Mine_Compound |
| 27 | 4/11/2023 12:59 | 1579644.36 | 2783047.96 | 7353 | 39949 | 12.65 | Mine_Compound |
| 28 | 4/11/2023 12:59 | 1579644.72 | 2783053.66 | 7353 | 40529 | 12.94 | Mine_Compound |
| 29 | 4/11/2023 12:59 | 1579644.62 | 2783058.85 | 7353 | 39350 | 12.36 | Mine_Compound |
| 30 | 4/11/2023 12:59 | 1579644.57 | 2783064.21 | 7354 | 37544 | 11.45 | Mine_Compound |
| 31 | 4/11/2023 12:59 | 1579644.14 | 2783069.71 | 7354 | 35781 | 10.57 | Mine_Compound |
| 32 | 4/11/2023 12:59 | 1579643.88 | 2783075.08 | 7354 | 35911 | 10.64 | Mine_Compound |
| 33 | 4/11/2023 12:59 | 1579644.60 | 2783080.73 | 7355 | 31419 | 8.39 | Mine_Compound |
| 34 | 4/11/2023 12:59 | 1579645.54 | 2783086.33 | 7355 | 33426 | 9.39 | Mine_Compound |
| 35 | 4/11/2023 12:59 | 1579645.93 | 2783091.25 | 7355 | 37444 | 11.40 | Mine_Compound |

(1) projection: StatePlane NAD 1983 NM West-feet
(2) Ra-226 pCi/g is determined from surface soil gamma radiation scan using 2x2 NaI detector and Site-specific gamma radiation level (cpm) correlation

## Table 2
## Static Gamma Radiation Survey at Soil Sampling/Test Pit Locations

| Survey Date | Survey Point ID/Description | Survey Point Coordinate NAD83 StatePlane NM West, Feet | | Static Gamma Radiation Survey | | | | Gamma Exposure Rate µR/hr |
|---|---|---|---|---|---|---|---|---|
| | | | | Bare 2x2 NaI Detector | | Collimated (0.5" Pb) 2x2 NaI Detector | | |
| | | Northing | Easting | CPM | Estimated Ra-226 pCi/g | CPM | Estimated Ra-226 pCi/g | |
| 05/17/23 | WBSB-01 | 1,581,413 | 2,782,866 | 26,897 | 6.1 | 6,297 | 1.7 | 33 |
| 05/17/23 | WBSB-02 | 1,581,390 | 2,782,444 | 26,749 | 6.1 | 6,350 | 1.7 | 33 |
| 05/17/23 | WBSB-03 | 1,581,356 | 2,783,329 | 24,529 | 4.9 | 6,073 | 1.3 | 31 |
| 05/17/23 | WBSB-04 | 1,581,339 | 2,782,706 | 30,064 | 7.7 | 6,069 | 1.3 | 37 |
| 05/17/23 | WBSB-05 | 1,581,329 | 2,783,062 | 31,828 | 8.6 | 6,945 | 2.7 | 41 |
| 05/17/23 | WBSB-06 | 1,581,271 | 2,782,942 | 35,410 | 10.4 | 7,288 | 3.3 | 47 |
| 05/17/23 | WBSB-07 | 1,581,187 | 2,783,253 | 37,965 | 11.7 | 8,183 | 4.7 | 47 |
| 05/17/23 | WBSB-08 | 1,581,164 | 2,782,988 | 55,849 | 20.6 | 11,042 | 9.3 | 70 |
| 05/31/23 | WBSB-09 | 1,581,254 | 2,782,870 | 36,491 | 10.9 | 6,599 | 2.1 | 44 |
| 05/31/23 | WBSB-10 | 1,581,263 | 2,783,140 | 34,898 | 10.1 | 7,286 | 3.2 | 48 |
| 05/31/23 | WBSB-11 | 1,581,277 | 2,783,335 | 29,002 | 7.2 | 6,602 | 2.2 | 34 |
| 05/31/23 | WBSB-12 | 1,581,228 | 2,782,908 | 40,341 | 12.9 | 7,153 | 3.0 | 55 |
| 05/31/23 | OPSB-01 | 1,580,834 | 2,782,884 | 2,328,550 | 1157 | 716,621 | 1138 | 2,100 |
| 05/31/23 | OPSB-02 | 1,580,812 | 2,783,138 | 505,097 | 245 | 160,357 | 248 | 650 |
| 05/31/23 | OPSB-03 | 1,580,599 | 2,783,013 | 700,063 | 343 | 247,434 | 387 | 900 |
| 05/31/23 | OPSB-04 | 1,580,328 | 2,782,874 | 408,698 | 197 | 133,199 | 205 | 450 |
| 05/31/23 | OPSB-05 | 1,580,386 | 2,783,136 | 446,083 | 216 | 156,044 | 241 | 450 |
| 05/30/23 | MCSB-01 | 1,579,585 | 2,783,019 | 35,807 | 10.6 | 10,538 | 8.5 | 41 |
| 05/30/23 | MCSB-02 | 1,579,573 | 2,783,167 | 34,096 | 9.7 | 9,678 | 7.1 | 39 |
| 05/30/23 | MCSB-03 | 1,579,343 | 2,782,883 | 34,019 | 9.7 | 9,832 | 7.3 | 39 |
| 05/30/23 | MCSB-04 | 1,579,317 | 2,783,098 | 34,656 | 10.0 | 10,811 | 8.9 | 40 |
| 05/24/23 | MCSB-05 | 1,579,183 | 2,782,702 | 52,231 | 18.8 | 14,892 | 15 | 65 |
| 05/24/23 | MCSB-06 | 1,579,162 | 2,783,064 | 31,976 | 8.7 | 8,548 | 5.3 | 37 |
| 05/24/23 | MCSB-07 | 1,579,040 | 2,783,010 | 52,974 | 19.2 | 18,511 | 21 | 65 |
| 05/23/23 | MCSB-08 | 1,578,849 | 2,782,249 | 107,010 | 46.2 | 39,626 | 55.0 | 125 |
| 05/23/23 | MCSB-09 | 1,578,850 | 2,782,582 | 28,188 | 6.8 | 8,193 | 4.7 | 33 |
| 05/23/23 | MCSB-10 | 1,578,758 | 2,782,444 | 39,814 | 12.6 | 12,984 | 12 | 43 |
| 05/22/23 | MCSB-11 | 1,578,611 | 2,782,258 | 53,106 | 19.2 | 18,055 | 20 | 60 |
| 05/22/23 | MCSB-12 | 1,578,521 | 2,782,569 | 29,299 | 7.3 | 9,090 | 6.1 | 33 |
| 05/22/23 | MCSB-13 | 1,578,301 | 2,782,557 | 21,952 | 3.7 | 6,254 | 1.6 | 25 |
| 05/23/23 | MCSB-14 | 1,578,278 | 2,782,258 | 21,642 | 3.5 | 6,366 | 1.8 | 25 |
| 05/18/23 | MCSB-15 | 1,578,214 | 2,782,398 | 48,059 | 16.7 | 15,633 | 17 | 51 |
| 05/18/23 | MCSB-16 | 1,578,084 | 2,782,313 | 30,445 | 7.9 | 11,069 | 9.3 | 33 |
| 05/18/23 | MCSB-17 | 1,578,085 | 2,782,599 | 18,059 | 1.7 | 5,891 | 1.0 | 19 |
| 05/18/23 | MCSB-18 | 1,578,071 | 2,782,424 | 17,170 | 1.3 | 5,046 | <0.6 | 19 |
| 05/31/23 | MCSB-19 | 1,578,837 | 2,782,317 | 69,850 | 27.6 | 24,522 | 31 | 80 |
| 05/31/23 | MCSB-20 | 1,578,650 | 2,782,298 | 55,167 | 20.3 | 18,497 | 21 | 65 |

## Table 3
## Windblown Area Surface and Subsurface Soil Sample Field Ex-Situ Gamma Screening and Vendor Laboratory Results Summary

| Sampling Data | | | | | Field Soil Screening Data | | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth (ft) | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | 6.6 pCi/g Ra-226 Reference Soil CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | SSL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| WBSB-01 0-6" | 0.5 | 5/17/2023 | 855 | Light brown alluvium, sandy-loam | 5/17/2023 | 3000 | 1406 | 281 | 536 | 2.5 | < | Y | 0.9 | 0.1 | 0.1 |
| WBSB-01 1'-1.5' | 1.5 | 5/17/2023 | 906 | Brown silty clay | 5/17/2023 | 3000 | 1244 | 249 | 536 | 2.1 | < | N | - | - | - |
| WBSB-02 0-6" | 0.5 | 5/17/2023 | 815 | Light brown alluvium, sandy-loam | 5/17/2023 | 3000 | 1577 | 315 | 536 | 3.0 | < | Y | 1.5 | 0.1 | 0.1 |
| WBSB-02 1'-1.5' | 1.5 | 5/17/2023 | 820 | Brown silty clay | 5/17/2023 | 2958 | 1008 | 204 | 536 | 1.5 | < | N | - | - | - |
| WBSB-03 0-6" | 0.5 | 5/17/2023 | 942 | Light brown alluvium, sandy-loam | 5/17/2023 | 3000 | 2039 | 408 | 536 | 4.3 | < | Y | 3.2 | 0.2 | 0.1 |
| WBSB-03 1'-1.5' | 1.5 | 5/17/2023 | 948 | Brown silty clay | 5/17/2023 | 3000 | 1136 | 227 | 536 | 1.8 | < | N | - | - | - |
| WBSB-04 0-6" | 0.5 | 5/17/2023 | 835 | Light brown alluvium, sandy-loam | 5/17/2023 | 3000 | 1521 | 304 | 536 | 2.9 | < | Y | 1.5 | 0.1 | 0.1 |
| WBSB-04 1'-1.5' | 1.5 | 5/17/2023 | 845 | Brown silty clay | 5/17/2023 | 2840 | 1189 | 251 | 536 | 2.1 | < | N | - | - | - |
| WBSB-05 0-6" | 0.5 | 5/17/2023 | 920 | Light brown alluvium, sandy-loam | 5/17/2023 | 3000 | 1747 | 349 | 536 | 3.5 | < | Y | 2.1 | 0.2 | 0.1 |
| WBSB-05 1'-1.5' | 1.5 | 5/17/2023 | 930 | Brown silty clay | 5/17/2023 | 2835 | 1086 | 230 | 536 | 1.8 | < | N | - | - | - |
| WBSB-06 0-6" | 0.5 | 5/17/2023 | 1054 | Light brown alluvium, sandy-loam | 5/17/2023 | 3000 | 1406 | 281 | 536 | 2.5 | < | Y | 1.3 | 0.1 | 0.1 |
| DSSB-01 | | | WBSB-06 0-6" Field QA/QC Duplicate | | | | | | | | < | Y | 1.1 | 0.1 | 0.1 |
| WBSB-06 1'-1.5' | 1.5 | 5/17/2023 | 1100 | Brown silty clay | 5/17/2023 | 2876 | 1004 | 209 | 536 | 1.5 | < | N | - | - | - |
| WBSB-07 0-6" | 0.5 | 5/17/2023 | 1014 | Light brown alluvium, sandy-loam | 5/17/2023 | 3000 | 2272 | 454 | 536 | 5.0 | ≤ | Y | 3.7 | 0.2 | 0.1 |
| WBSB-07 1'-1.5' | 1.5 | 5/17/2023 | 930 | Brown silty clay | 5/17/2023 | 3000 | 1082 | 216 | 536 | 1.6 | < | N | - | - | - |
| WBSB-08 0-6" | 0.5 | 5/17/2023 | 1034 | Light brown alluvium, sandy-loam | 5/17/2023 | 3000 | 4140 | 828 | 536 | 10.2 | > | Y | 9.7 | 0.3 | 0.2 |
| WBSB-08 1'-1.5' | 1.5 | 5/17/2023 | 1042 | Brown silty clay | 5/17/2023 | 3000 | 1118 | 224 | 536 | 1.7 | < | Y | 0.9 | 0.1 | 0.1 |
| WBSB-09 0-6" | 0.5 | 5/31/2023 | 825 | Light brown alluvium, sandy-loam | 5/31/2023 | 3000 | 1393 | 279 | 536 | 2.5 | < | Y | 1.2 | 0.1 | 0.1 |
| WBSB-09 6-12" | 1 | 5/31/2023 | 835 | Brown silty clay | 5/31/2023 | 3000 | 1170 | 234 | 536 | 1.9 | < | N | - | - | - |
| WBSB-10 0-6" | 0.5 | 5/31/2023 | 910 | Light brown alluvium, sandy-loam | 5/31/2023 | 3000 | 2217 | 443 | 536 | 4.8 | < | Y | 3.5 | 0.2 | 0.1 |
| WBSB-10 6-12" | 1 | 5/31/2023 | 915 | Brown loam/roots | 5/31/2023 | 3000 | 1380 | 276 | 536 | 2.5 | < | N | - | - | - |
| WBSB-11 0-6" | 0.5 | 5/31/2023 | 935 | Light brown alluvium, sandy-loam | 5/31/2023 | 3000 | 1959 | 392 | 536 | 4.1 | < | Y | 2.7 | 0.2 | 0.1 |
| WBSB-11 6-12" | 1 | 5/31/2023 | 940 | Sandstone/sand | 5/31/2023 | 2008 | 1053 | 315 | 536 | 3.0 | < | N | - | - | - |
| WBSB-12 0-1" | 0.08 | 5/31/2023 | 850 | Light brown alluvium, sandy-loam | 5/31/2023 | 3000 | 1736 | 347 | 536 | 3.5 | < | Y | 2.0 | 0.2 | 0.1 |
| WBSB-12 2-6" | 0.5 | 5/31/2023 | 900 | Brown loam/ sandy | 5/31/2023 | 3000 | 1117 | 223 | 536 | 1.7 | < | Y | 1.0 | 0.1 | 0.1 |

(1) Projection: NAD 1983, New Mexico West, Feet.

## Table 4
## Ore Pad Area Subsurface Soil Sample Field Ex-Situ Gamma Screening and Vendor Laboratory Results Summary

| Sampling Data | | | | | Field Soil Screening Data | | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth (ft) | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | 6.6 pCi/g Ra-226 Reference Soil CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | SSL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| OPSB-01 0-13' | 0 to 13' | 6/1/2023 | 1005 | Light/dark grey waste rock | 6/1/2023 | 3000 | 26904 | 5381 | 529 | 74 | > | N | - | - | - |
| OPSB-01 13.5' | 13.5 | 6/1/2023 | 1020 | Light/dark grey waste rock | 6/1/2023 | 3000 | 11560 | 2312 | 529 | 31 | > | N | - | - | - |
| OPSB-02 0-4' | 0 to 4' | 6/1/2023 | 1115 | Grey/dark ore waste rock | 6/1/2023 | 3000 | 182551 | 36510 | 529 | 510 | > | N | - | - | - |
| OPSB-02 4.5' | 4.5 | 6/1/2023 | 1100 | Dark/light grey clay & waste rock | 6/1/2023 | 3000 | 35425 | 7085 | 529 | 98 | > | N | - | - | - |
| OPSB-02 5.5' | 5.5 | 6/1/2023 | 1120 | Light brown silty sand mix | 6/1/2023 | 3000 | 1189 | 238 | 529 | 1.9 | < | Y | 0.9 | 0.1 | 0.1 |
| DSSB-05 | | | OPSB-02 5.5' Field QA/QC Duplicate | | | | | | | | < | Y | 0.8 | 0.1 | 0.1 |
| OPSB-03 0-4' | 0 to 4' | 6/1/2023 | 850 | Grey/dark waste rock mix | 6/1/2023 | 3000 | 56365 | 11273 | 529 | 156 | > | N | - | - | - |
| OPSB-03 4.2' | 4.2 | 6/1/2023 | 910 | Grey/dark brown clay waste rock mix | 6/1/2023 | 1708 | 2091 | 735 | 529 | 8.9 | > | Y | 4.4 | 0.2 | 0.1 |
| OPSB-03 4.5' | 4.5 | 6/1/2023 | 925 | Dark brown clay | 6/1/2023 | 3000 | 1193 | 239 | 529 | 1.9 | < | Y | 0.8 | 0.1 | 0.1 |
| OPSB-04 0-4' | 0 to 4' | 6/1/2023 | 815 | Grey/dark waste rock mix | 6/1/2023 | 3000 | 8428 | 1686 | 529 | 22 | > | N | - | - | - |
| OPSB-04 4.8' | 4.83 | 6/1/2023 | 825 | Dark clay mixed with brown silty soil | 6/1/2023 | 3000 | 1124 | 225 | 529 | 1.8 | < | N | - | - | - |
| OPSB-04 4.5' | 4.5 | 6/1/2023 | 835 | Grey/dark brown clay waste rock mix | 6/1/2023 | 3000 | 4373 | 875 | 529 | 11 | > | N | - | - | - |
| OPSB-05 0-3' | 0 to 3' | 6/1/2023 | 1200 | Grey/dark waste rock mix | 6/1/2023 | 3000 | 32147 | 6429 | 529 | 89 | > | N | - | - | - |
| OPSB-05 3' | 3 | 6/1/2023 | 1140 | Grey/dark brown clay waste rock mix | 6/1/2023 | 3000 | 5526 | 1105 | 529 | 14 | > | N | - | - | - |
| OPSB-05 3.75' | 3.75 | 6/1/2023 | 1155 | Light brown sandy silty soil | 6/1/2023 | 3000 | 1587 | 317 | 529 | 3.0 | < | Y | 0.9 | 0.1 | 0.1 |

(1) Projection: NAD 1983, New Mexico West, Feet.

## Table 5
## Mine Compound Test Pit Subsurface Soil Sample Field Ex-Situ Gamma Screening and Vendor Laboratory Results Summary

| Sampling Data | | | | | Field Soil Screening Data | | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth (ft) | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | 6.6 pCi/g Ra-226 Reference Soil CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | SSL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| MCSB-01 1' | 1 | 5/30/2023 | 1240 | 3" Roadbase gravel mixed with dark brown silty clay | 5/30/2023 | 3000 | 2326 | 465 | 570 | 5.1 | < | N | - | - | - |
| MCSB-01 2' | 2 | 5/30/2023 | 1250 | Brown loamy clay w/ gravel | 5/30/2023 | 3000 | 2965 | 593 | 570 | 6.9 | ≈ | Y | 5.9 | 0.2 | 0.1 |
| DSSB-04 | | | MCSB-01 2' Field QA/QC Duplicate | | | | | | | | ≈ | Y | 5.8 | 0.2 | 0.1 |
| MCSB-01 3' | 3 | 5/30/2023 | 1300 | Brown loamy soil | 5/30/2023 | 3000 | 1240 | 248 | 570 | 2.1 | < | Y | 0.8 | 0.1 | 0.1 |
| MCSB-01 4' | 4 | 5/30/2023 | 1315 | Brown loamy clay | 5/30/2023 | 3000 | 1120 | 224 | 570 | 1.7 | < | N | - | - | - |
| MCSB-02 1' | 1 | 5/30/2023 | 1030 | Red roadbase gravel | 5/30/2023 | 3000 | 1243 | 249 | 570 | 2.1 | < | N | - | - | - |
| MCSB-02 2' | 2 | 5/30/2023 | 1040 | silty clay mix w/ 3/4" gravel | 5/30/2023 | 3000 | 1620 | 324 | 570 | 3.1 | < | N | - | - | - |
| MCSB-02 3' | 3 | 5/30/2023 | 1050 | Grey, greenish black clay/bentonite | 5/30/2023 | 3000 | 947 | 189 | 570 | 1.2 | < | Y | 0.8 | 0.1 | 0.1 |
| MCSB-02 4' | 4 | 5/30/2023 | 1100 | Loose sandy silt w/ reddish gravel. | 5/30/2023 | 3000 | 5236 | 1047 | 570 | 13.3 | > | Y | 12.6 | 0.4 | 0.2 |
| MCSB-02 5.2' | 5.2 | 5/30/2023 | 1115 | Loose dark brown silty clay | 5/30/2023 | 3000 | 1426 | 285 | 570 | 2.6 | < | Y | 1.4 | 0.1 | 0.1 |
| MCSB-03 1' | 1 | 5/30/2023 | 1340 | Light brown loamy soil w/ small amounts gravel | 5/30/2023 | 3000 | 3386 | 677 | 570 | 8.1 | > | Y | 5.9 | 0.2 | 0.1 |
| MCSB-03 2' | 2 | 5/30/2023 | 1350 | Brown loamy soil | 5/30/2023 | 3000 | 1201 | 240 | 570 | 2.0 | < | Y | 0.8 | 0.1 | 0.1 |
| MCSB-03 3' | 3 | 5/30/2023 | 1400 | Brown sandy loam | 5/30/2023 | 3000 | 1279 | 256 | 570 | 2.2 | < | N | - | - | - |
| MCSB-04 1' | 1 | 5/30/2023 | 935 | 0-6" Red roadbase gravel, 6"-12" Brown silty soil w/ gravel | 5/30/2023 | 3000 | 1055 | 211 | 570 | 1.6 | < | Y | 1.4 | 0.1 | 0.1 |
| MCSB-04 2' | 2 | 5/30/2023 | 945 | Gravel roadbase | 5/30/2023 | 3000 | 1919 | 384 | 570 | 4.0 | < | Y | 3.4 | 0.2 | 0.1 |
| MCSB-04 3.5' | 3.5 | 5/30/2023 | 955 | Mixed dark brown silty sandy and rocks | 5/30/2023 | 3000 | 1017 | 203 | 570 | 1.4 | < | N | - | - | - |
| MCSB-04 4.5' | 4.5 | 5/30/2023 | 1005 | Dark brown silty clay w/ gravel-cobbles | 5/30/2023 | 3000 | 1274 | 255 | 570 | 2.2 | < | N | - | - | - |
| MCSB-5 1' | 1 | 5/24/2023 | 1010 | 0-6" gravel roadbase, 6"-12" brown silty sand | 5/25/2023 | 3000 | 1183 | 237 | 555 | 1.9 | < | N | - | - | - |
| MCSB-5 2' | 2 | 5/24/2023 | 1020 | Brown silty sandy soil | 5/25/2023 | 3000 | 1309 | 262 | 555 | 2.3 | < | N | - | - | - |
| MCSB-5 3' | 3 | 5/24/2023 | 1030 | Rocky w/ silty sand soil | 5/25/2023 | 3000 | 1162 | 232 | 555 | 1.8 | < | N | - | - | - |
| MCSB-5 4' | 4 | 5/24/2023 | 1040 | Rocky w/ silty sand soil | 5/25/2023 | 3000 | 1262 | 252 | 555 | 2.1 | < | Y | 1.5 | 0.1 | 0.1 |
| MCSB-5 6' | 6 | 5/24/2023 | 1100 | Gravel, sandy soil | 5/25/2023 | 3000 | 6564 | 1313 | 555 | 17.0 | > | Y | 16.1 | 0.4 | 0.2 |
| MCSB-5 7.5' | 7.5 | 5/24/2023 | 1110 | Dark brown silty soil | 5/25/2023 | 3000 | 1150 | 230 | 555 | 1.8 | < | Y | 1.0 | 0.1 | 0.1 |
| MCSB-06 1' | 1 | 5/30/2023 | 822 | 0-8" red 1" roadbase gravel, 8"-12" dark brown soil gravel mix | 5/30/2023 | 3000 | 19543 | 3909 | 570 | 53.3 | > | N | - | - | - |
| MCSB-06 2' | 2 | 5/30/2023 | 835 | Dark brown packed clay with gravel | 5/30/2023 | 3000 | 4112 | 822 | 570 | 10.1 | > | N | - | - | - |
| MCSB-06 3.25' | 3.25 | 5/30/2023 | 850 | Dark brown packed clay with gravel | 5/30/2023 | 3000 | 1477 | 295 | 570 | 2.7 | < | N | - | - | - |
| MCSB-06 4.25' | 4.25 | 5/30/2023 | 900 | Dark brown silty clay | 5/30/2023 | 3000 | 1091 | 218 | 570 | 1.7 | < | N | - | - | - |
| MCSB-06 6' | 6 | 5/30/2023 | 915 | Rocky silty clay | 5/30/2023 | 3000 | 1311 | 262 | 570 | 2.3 | < | Y | 1.9 | 0.2 | 0.1 |

## Table 5 (Continued)
## Mine Compound Test Pit Subsurface Soil Sample Field Ex-Situ Gamma Screening and Vendor Laboratory Results Summary

| Sampling Data | | | | | Field Soil Screening Data | | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth (ft) | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | 6.6 pCi/g Ra-226 Reference Soil CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | SSL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| MCSB-7 1' | 1 | 5/24/2023 | 1220 | Gravel/Roadbase w/ sand | 5/25/2023 | 3000 | 10973 | 2195 | 555 | 29.3 | > | N | - | - | - |
| MCSB-7 2' | 2 | 5/24/2023 | 1232 | Dark brown clay/bentonite silty | 5/25/2023 | 3000 | 1333 | 267 | 555 | 2.3 | < | N | - | - | - |
| MCSB-7 3' | 3 | 5/24/2023 | 1246 | light brown/greyish sandy silty | 5/25/2023 | 3000 | 2872 | 574 | 555 | 6.6 | ≈ | Y | 6.3 | 0.2 | 0.1 |
| DSSB-03 | | | | MCSB-7 3' Field QA/QC Duplicate | | | | | | | | Y | 6.2 | 0.2 | 0.1 |
| MCSB-7 4.5' | 4.5 | 5/24/2023 | 1300 | Light brown silty sand mix | 5/25/2023 | 3000 | 1396 | 279 | 555 | 2.5 | < | Y | 1.2 | 0.1 | 0.1 |
| MCSB-7 5.5' | 5.5 | 5/24/2023 | 1110 | Light brown/grey clay soil | 5/25/2023 | 3000 | 1150 | 230 | 555 | 1.8 | < | N | - | - | - |
| MCSB-08 1' | 1 | 5/23/2023 | 1035 | Clay mixed w/ grey waste rock | 5/23/2023 | 3000 | 29705 | 5941 | 586 | 81.8 | > | N | - | - | - |
| MCSB-08 2' | 2 | 5/23/2023 | 1045 | Clay mixed w/ grey waste rock | 5/23/2023 | 3000 | 34740 | 6948 | 586 | 95.9 | > | N | - | - | - |
| MCSB-08 3' | 3 | 5/23/2023 | 1058 | Clay mixed w/ sandy grey waste rock | 5/23/2023 | 3000 | 19380 | 3876 | 586 | 52.9 | > | N | - | - | - |
| MCSB-08 5' | 5 | 5/23/2023 | 1110 | Clay mixed w/ sandy grey waste rock | 5/23/2023 | 3000 | 33460 | 6692 | 586 | 92.3 | > | Y | 77.1 | 0.9 | 0.4 |
| MCSB-08 6.5' | 6.5 | 5/23/2023 | 1125 | Black gravel/soil | 5/23/2023 | 3000 | 1266 | 253 | 586 | 2.1 | < | Y | 1.1 | 0.1 | 0.1 |
| MCSB-08 12' | 12 | 5/23/2023 | 1145 | Dark rocky clay | 5/23/2023 | 3000 | 2421 | 484 | 586 | 5.4 | ≤ | N | - | - | - |
| MCSB-9 1' | 1 | 5/24/2023 | 825 | Gravel/Roadbase w/ sand | 5/25/2023 | 3000 | 4191 | 838 | 555 | 10.3 | > | Y | 7.9 | 0.3 | 0.1 |
| MCSB-9 2' | 2 | 5/24/2023 | 840 | Brown sandy soil | 5/25/2023 | 3000 | 980 | 196 | 555 | 1.3 | < | Y | 0.6 | 0.1 | 0.1 |
| MCSB-9 3' | 3 | 5/24/2023 | 850 | Brown sandy soil | 5/25/2023 | 3000 | 1056 | 211 | 555 | 1.6 | < | N | - | - | - |
| MCSB-9 4' | 4 | 5/24/2023 | 900 | Brown sandy soil | 5/25/2023 | 3000 | 1082 | 216 | 555 | 1.6 | < | N | - | - | - |
| MCSB-10 1' | 1 | 5/24/2023 | 915 | Gravel/Roadbase w/ sand | 5/25/2023 | 3000 | 920 | 184 | 555 | 1.2 | < | Y | 0.8 | 0.1 | 0.1 |
| MCSB-10 2' | 2 | 5/24/2023 | 922 | Loose light brown sandy silty soil | 5/25/2023 | 3000 | 913 | 183 | 555 | 1.2 | < | Y | | | |
| MCSB-10 3' | 3 | 5/24/2023 | 930 | Dark brown clay mix w/ sandy silt | 5/25/2023 | 3000 | 930 | 186 | 555 | 1.2 | < | N | - | - | - |
| MCSB-10 4' | 4 | 5/24/2023 | 943 | Dark brown clay mix w/ sandy silt | 5/25/2023 | 3000 | 1055 | 211 | 555 | 1.6 | < | N | - | - | - |
| MCSB-11 1' | 1 | 5/22/2023 | 1030 | 0-4" Roadbase gravel, 4"-12" grey rocky sandy waste rock | 5/22/2023 | 3000 | 12907 | 2581 | 551 | 34.7 | > | N | - | - | - |
| MCSB-11 2' | 2 | 5/22/2023 | 1040 | Dark grey rocky sandy waste rock | 5/22/2023 | 3000 | 42761 | 8552 | 551 | 118.3 | > | N | - | - | - |
| MCSB-11 3' | 3 | 5/22/2023 | 1050 | Grey waste rock w/ brown silty mix | 5/22/2023 | 3000 | 15497 | 3099 | 551 | 42.0 | > | N | - | - | - |
| MCSB-11 4' | 4 | 5/22/2023 | 1104 | Dark brown rocky loose soil | 5/22/2023 | 3000 | 3871 | 774 | 551 | 9.4 | > | Y | 11.0 | 0.4 | 0.2 |
| MCSB-11 5' | 5 | 5/22/2023 | 1112 | Dark brown clay mix w/ pebbles | 5/22/2023 | 3000 | 2036 | 407 | 551 | 4.3 | < | Y | 2.8 | 0.2 | 0.1 |
| MCSB-11 6' | 6 | 5/23/2023 | 835 | Dark brown sandy clay mix | 5/23/2023 | 3000 | 1824 | 365 | 586 | 3.7 | < | N | - | - | - |

## Table 5 (Continued)


## Mine Compound Test Pit Subsurface Soil Sample Field Ex-Situ Gamma Screening and Vendor Laboratory Results Summary

| Sampling Data | | | | | Field Soil Screening Data | | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth (ft) | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | 6.6 pCi/g Ra-226 Reference Soil CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | SSL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| MCSB-12 1' | 1 | 5/22/2023 | 928 | 0-6" Roadbase gravel, 6"-12" 3/4-1" gravel sandy | 5/22/2023 | 3000 | 1957 | 391 | 551 | 4.1 | < | Y | 3.3 | 0.2 | 0.1 |
| MCSB-12 2' | 2 | 5/22/2023 | 935 | Black gravel/soil | 5/22/2023 | 3000 | 1793 | 359 | 551 | 3.6 | < | N | - | - | - |
| MCSB-12 3' | 3 | 5/22/2023 | 948 | Hard packed brown silty sand | 5/22/2023 | 3000 | 915 | 183 | 551 | 1.2 | < | N | - | - | - |
| MCSB-12 4' | 4 | 5/22/2023 | 956 | Hard packed brown silty sand | 5/22/2023 | 3000 | 923 | 185 | 551 | 1.2 | < | N | - | - | - |
| MCSB-13 1' | 1 | 5/22/2023 | 825 | 0-4" Roadbase gravel, 4"-12" dark silty clay | 5/22/2023 | 3000 | 1197 | 239 | 551 | 1.9 | < | Y | 1.2 | 0.1 | 0.1 |
| MCSB-13 2' | 2 | 5/22/2023 | 839 | Dark silty clay | 5/22/2023 | 3000 | 1253 | 251 | 551 | 2.1 | < | N | - | - | - |
| MCSB-13 3' | 3 | 5/22/2023 | 851 | Dark silty clay | 5/22/2023 | 3000 | 1309 | 262 | 551 | 2.3 | < | N | - | - | - |
| MCSB-13 4' | 4 | 5/22/2023 | 905 | Light brown sandstone silty | 5/22/2023 | 3000 | 1210 | 242 | 551 | 2.0 | < | N | - | - | - |
| MCSB-14 1' | 1 | 5/23/2023 | 853 | Dark brown topsoil, cobbles | 5/23/2023 | 3000 | 1982 | 396 | 586 | 4.1 | < | Y | 3.8 | 0.2 | 0.1 |
| MCSB-14 2' | 2 | 5/23/2023 | 905 | Grey sandy waste rock | 5/23/2023 | 3000 | 1942 | 388 | 586 | 4.0 | < | N | - | - | - |
| MCSB-14 3' | 3 | 5/23/2023 | 915 | Grey sandy waste rock | 5/23/2023 | 3000 | 1856 | 371 | 586 | 3.8 | < | N | - | - | - |
| MCSB-14 4' | 4 | 5/23/2023 | 920 | Grey sandy waste rock | 5/23/2023 | 3000 | 1795 | 359 | 586 | 3.6 | < | N | - | - | - |
| MCSB-14 5' | 5 | 5/23/2023 | 932 | Dark brown clay | 5/23/2023 | 3000 | 1274 | 255 | 586 | 2.2 | < | N | - | - | - |
| MCSB-14 6' | 6 | 5/23/2023 | 950 | Dark brown clay | 5/23/2023 | 3000 | 1059 | 212 | 586 | 1.6 | < | N | - | - | - |
| MCSB-15 1' | 1 | 5/18/2023 | 1138 | Light brown clay/sand mix | 5/18/2023 | 3000 | 1503 | 301 | 539 | 2.8 | < | Y | 1.6 | 0.1 | 0.1 |
| DSSB-02 | | | MCSB-15 1' Field QA/QC Duplicate | | | | | | | | < | Y | 1.3 | 0.1 | 0.1 |
| MCSB-15 2' | 2 | 5/18/2023 | 1145 | Light brown clay/sand-road base mixed | 5/18/2023 | 3000 | 1389 | 278 | 539 | 2.5 | < | N | - | - | - |
| MCSB-15 3' | 3 | 5/18/2023 | 1158 | Brown /greyish clay/sand mix | 5/18/2023 | 3000 | 2206 | 441 | 539 | 4.8 | < | N | - | - | - |
| MCSB-15 4' | 4 | 5/18/2023 | 1212 | Brown clay/sand mix | 5/18/2023 | 3000 | 1415 | 283 | 539 | 2.6 | < | N | - | - | - |
| MCSB-16 1' | 1 | 5/18/2023 | 1045 | Rocky w/ sand - grey/light green color | 5/18/2023 | 3000 | 2498 | 500 | 539 | 5.6 | ≤ | Y | 4.8 | 0.2 | 0.2 |
| MCSB-16 2' | 2 | 5/18/2023 | 1100 | Light brown alluvium, sandy-loam | 5/18/2023 | 3000 | 1646 | 329 | 539 | 3.2 | < | Y | 2.4 | 0.2 | 0.1 |
| MCSB-16 3' | 3 | 5/18/2023 | 1110 | Shale/sandy, light grey/brown | 5/18/2023 | 3000 | 1587 | 317 | 539 | 3.0 | < | N | - | - | - |
| MCSB-16 4' | 4 | 5/18/2023 | 1120 | Light borown sandy loam | 5/18/2023 | 3000 | 1280 | 256 | 539 | 2.2 | < | N | - | - | - |
| MCSB-17 1' | 1 | 5/18/2023 | 845 | Gravel/Roadbase w/ sand | 5/18/2023 | 3000 | 974 | 195 | 539 | 1.3 | < | Y | 0.7 | 0.1 | 0.1 |
| MCSB-17 2' | 2 | 5/18/2023 | 857 | Dark brown clay/loam | 5/18/2023 | 3000 | 1070 | 214 | 539 | 1.6 | < | N | - | - | - |
| MCSB-18 1'-1.5' | 1-1.5 | 5/18/2023 | 948 | Light brown sandy clay loam | 5/18/2023 | 3000 | 1634 | 327 | 539 | 3.2 | < | Y | 2.6 | 0.2 | 0.1 |
| MCSB-18 2' | 2 | 5/18/2023 | 958 | Dark brown/grey clay & bentonite mix w/ sandy loam | 5/18/2023 | 3000 | 1321 | 264 | 539 | 2.3 | < | N | - | - | - |
| MCSB-18 3' | 3 | 5/18/2023 | 1010 | Light brown sandy mixed w/ charcoal, rust & debris | 5/18/2023 | 3000 | 1306 | 261 | 539 | 2.3 | < | N | - | - | - |

**Table 6**
**Subsurface Ra-226 Contamination Depth Summary**

| Area | Test Pit ID | Test Pit Location Coordinates, NAD83 NM West (Feet) | | Date | Depth of Soil Ra-226 Contamination >RCC (Feet bgs) |
|---|---|---|---|---|---|
| | | Northing | Easting | | |
| Windblown Area | WBSB-01 | 1581418.18 | 2782862.43 | 05/17/23 | **0** |
| | WBSB-02 | 1581391.39 | 2782444.66 | 05/17/23 | **0** |
| | WBSB-03 | 1581357.28 | 2783327.71 | 05/17/23 | **0** |
| | WBSB-04 | 1581342.67 | 2782705.31 | 05/17/23 | **0** |
| | WBSB-05 | 1581330.49 | 2783059.75 | 05/17/23 | **0** |
| | WBSB-06 | 1581265.93 | 2782941.60 | 05/17/23 | **0** |
| | WBSB-07 | 1581192.86 | 2783257.06 | 05/17/23 | **0** |
| | WBSB-08 | 1581162.41 | 2782991.54 | 05/17/23 | **0.5** |
| | WBSB-09 | 1580833.55 | 2782884.36 | 05/31/23 | **0** |
| | WBSB-10 | 1580832.33 | 2783163.28 | 05/31/23 | **0** |
| | WBSB-11 | 1580598.48 | 2783012.25 | 05/31/23 | **0** |
| | WBSB-12 | 1580328.08 | 2782874.61 | 05/31/23 | **0** |
| Ore Pad Area | OPSB-01 | 1580834.11 | 2782884.42 | 05/31/23 | **≈15** |
| | OPSB-02 | 1580811.55 | 2783138.10 | 05/31/23 | **4.2** |
| | OPSB-03 | 1580599.03 | 2783012.73 | 05/31/23 | **4.3** |
| | OPSB-04 | 1580328.29 | 2782874.34 | 05/31/23 | **4.5** |
| | OPSB-05 | 1580386.28 | 2783136.44 | 05/31/23 | **3.0** |
| | OPSB-06 | 1580827.17 | 2783031.17 | 06/07/23 | **3.0** |
| | OPSB-07 | 1580839.91 | 2782985.85 | 06/07/23 | **3.0** |
| | OPSB-08 | 1580839.92 | 2782946.79 | 06/07/23 | **≈15** |
| Mine Compound Area | MCSB-01 | 1579584.67 | 2783018.74 | 05/30/23 | **<1.0** |
| | MCSB-02 | 1579573.01 | 2783166.70 | 05/30/23 | **0 to 1.0 and 3.5 to 4.5** |
| | MCSB-03 | 1579343.02 | 2782883.30 | 05/30/23 | **<1.0** |
| | MCSB-04 | 1579317.49 | 2783098.04 | 05/30/23 | **<1.0** |
| | MCSB-05 | 1579183.08 | 2782701.94 | 05/24/23 | **0 to 1.0 and 6.0 to 7.0** |
| | MCSB-06 | 1579162.34 | 2783064.40 | 05/24/23 | **2.0** |
| | MCSB-07 | 1579040.09 | 2783009.78 | 05/24/23 | **1.0** |
| | MCSB-08 | 1578849.18 | 2782249.48 | 05/23/23 | **6.0** |
| | MCSB-09 | 1578849.89 | 2782581.54 | 05/23/23 | **<0.5** |
| | MCSB-10 | 1578758.24 | 2782443.51 | 05/23/23 | **<1.0** |
| | MCSB-11 | 1578610.92 | 2782257.53 | 05/22/23 | **4.5** |
| | MCSB-12 | 1578520.57 | 2782569.17 | 05/22/23 | **<1.0** |
| | MCSB-13 | 1578300.74 | 2782557.01 | 05/22/23 | **0** |
| | MCSB-14 | 1578278.15 | 2782258.40 | 05/23/23 | **0** |
| | MCSB-15 | 1578214.43 | 2782398.32 | 05/18/23 | **<0.5** |
| | MCSB-16 | 1578084.02 | 2782313.13 | 05/18/23 | **<1.0** |
| | MCSB-17 | 1578084.66 | 2782598.61 | 05/18/23 | **0** |
| | MCSB-18 | 1578071.36 | 2782423.53 | 05/18/23 | **0** |

# Figures





AVM Environmental Services, Inc.

Figure 1
Mt. Taylor Mine Site
Soil Radiologic Characterization Areas

**Legend**

North Controlled Fence

Soil Radiologic Characterization Area




N
W E
S

AVM Environmental Services, Inc.

Figure 2
Mt. Taylor Mine Site
Windblown and Ore Pad Area Soil Sample/Test Pit Locations
and April 2023 Surface Gamma Scan Survey

**Legend**

**Ra-226 pCi/g**

- <1.8 pCi/g
- 1.9 - 6.8 pCi/g
- 6.9 - 10.0 pCi/g
- 10.1 - 20.0 pCi/g
- 20.1 - 30.0 pCi/g
- 30.1 - 40.0 pCi/g
- >40.1 pCi/g
- North Controlled Fence
- Soil Radiologic Characterization Area
- Soil Sample/Test Pit (>6.8 Ra-226 pCi/g RCC Depth) Location

Note: Ra-226 pCi/g is determined from surface soil gamma radiation scan using 2x2 NaI detector and Site specific gamma radiation level (cpm) correlation.



0 100 200 400 Feet

N
W E
S

Environmental Services, Inc.

Figure 3
Mt. Taylor Mine Site
Mine Compound Area Soil Sample/Test Pit Locations
and April 2023 Surface Gamma Scan Survey

**Legend**

**Ra-226 pCi/g**

- <1.8 pCi/g
- 1.9 - 6.8 pCi/g
- 6.9 - 10.0 pCi/g
- 10.1 - 20.0 pCi/g
- 20.1 - 30.0 pCi/g
- 30.1 - 40.0 pCi/g
- >40.1 pCi/g
- Soil Sample/Test Pit Location
- North Controlled Fence
- Soil Radiologic Characterization Area

Note: Ra-226 pCi/g is determined from surface soil gamma radiation scan using 2x2 NaI detector and Site specific gamma radiation level (cpm) correlation.






Figure 4
Mt. Taylor Mine Site
Windblown Area Surface Soil Ra-226 6.8 pCi/g
Release Criteria Contamination Boundary

**Legend**

**Ra-226 pCi/g**

- <1.8 pCi/g
- 1.9 - 6.8 pCi/g
- 6.9 - 10.0 pCi/g
- 10.1 - 20.0 pCi/g
- 20.1 - 30.0 pCi/g
- 30.1 - 40.0 pCi/g
- >40.1 pCi/g
- North Controlled Fence
- Surface Gamma Scan Survey Based 6.8 Ra-226 Boundary
- Soil Sample Based 6.8 Ra-226 pCi/g Boundary
- Soil Radiologic Characterization Area

Note: Ra-226 pCi/g is determined from surface soil gamma radiation scan using 2x2 NaI detector and Site specific gamma radiation level (cpm) correlation.



| MCSB-01 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-01 1' | 5.1 | - |
| MCSB-01 2' | 6.9 | 5.9 |
| MCSB-01 3' | 2.1 | - |
| MCSB-01 4' | 1.7 | - |

| MCSB-02 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-02 1' | 2.1 | - |
| MCSB-02 2' | 3.1 | - |
| MCSB-02 3' | 1.2 | 0.8 |
| MCSB-02 4' | 13.3 | 12.6 |
| MCSB-02 5.2' | 2.6 | 1.4 |

| MCSB-03 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-03 1' | 8.1 | 5.9 |
| MCSB-03 2' | 2.0 | 0.8 |
| MCSB-03 3' | 2.2 | - |

| MCSB-04 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-04 1' | 1.6 | 1.4 |
| MCSB-04 2' | 4.0 | 3.4 |
| MCSB-04 3.5' | 1.4 | - |
| MCSB-04 4.5' | 2.2 | - |

| MCSB-05 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-05 1' | 1.9 | - |
| MCSB-05 2' | 2.3 | - |
| MCSB-05 3' | 1.8 | - |
| MCSB-05 4' | 2.1 | 1.5 |
| MCSB-05 6' | 17 | 16.1 |
| MCSB-05 7.5' | 1.8 | 1.0 |

| MCSB-06 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-06 1' | 53.3 | - |
| MCSB-06 2' | 10.1 | - |
| MCSB-06 3.25' | 2.7 | - |
| MCSB-06 4.25' | 1.7 | - |
| MCSB-06 6' | 2.3 | 1.9 |

| MCSB-07 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-07 1' | 29.3 | - |
| MCSB-07 2' | 2.3 | - |
| MCSB-07 3' | 6.6 | 6.3 |
| MCSB-07 4.5' | 2.5 | 1.2 |
| MCSB-07 5.5' | 1.8 | - |

| MCSB-08 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-08 1' | 81.8 | - |
| MCSB-08 2' | 95.9 | - |
| MCSB-08 3' | 52.9 | - |
| MCSB-08 5' | 92.3 | 77.1 |
| MCSB-08 6.5' | 2.1 | 1.1 |
| MCSB-08 12' | 5.4 | - |

| MCSB-09 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-09 1' | 10.3 | 7.9 |
| MCSB-09 2' | 1.3 | 0.6 |
| MCSB-09 3' | 1.6 | - |
| MCSB-09 4' | 1.6 | - |

| MCSB-10 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-10 1' | 1.2 | 0.8 |
| MCSB-10 2' | 1.2 | - |
| MCSB-10 3' | 1.2 | - |
| MCSB-10 4' | 1.6 | - |

| MCSB-11 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-11 1' | 34.7 | - |
| MCSB-11 2' | 118.3 | - |
| MCSB-11 3' | 42.0 | - |
| MCSB-11 4' | 9.4 | 11.0 |
| MCSB-11 5' | 4.3 | 2.8 |
| MCSB-11 6' | 3.7 | - |

| MCSB-12 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-12 1' | 4.1 | 3.3 |
| MCSB-12 2' | 3.6 | - |
| MCSB-12 3' | 1.2 | - |
| MCSB-12 4' | 1.2 | - |

| MCSB-14 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-14 1' | 4.1 | 3.8 |
| MCSB-14 2' | 4.0 | - |
| MCSB-14 3' | 3.8 | - |
| MCSB-14 4' | 3.6 | - |
| MCSB-14 5' | 2.2 | - |
| MCSB-14 6' | 1.6 | - |

| MCSB-13 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-13 1' | 1.9 | 1.2 |
| MCSB-13 2' | 2.1 | - |
| MCSB-13 3' | 2.3 | - |
| MCSB-13 4' | 2.0 | - |

| MCSB-15 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-15 1' | 2.8 | 1.6 |
| MCSB-15 2' | 2.5 | - |
| MCSB-15 3' | 4.8 | - |
| MCSB-15 4' | 2.6 | - |

| MCSB-16 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-16 1' | 5.6 | 4.8 |
| MCSB-16 2' | 3.2 | 0.24 |
| MCSB-16 3' | 3.0 | - |
| MCSB-16 4' | 2.2 | - |

| MCSB-17 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-17 1' | 1.3 | 0.7 |
| MCSB-17 2' | 1.6 | - |

| MCSB-18 | | |
|---|---|---|
| Sample ID | On-Site Soil Screening Ra-226 pCi/g | Lab Results Ra-226 pCi/g |
| MCSB-18 1'-1.5' | 3.2 | 2.6 |
| MCSB-18 2' | 2.3 | |
| MCSB-18 3' | 2.3 | |

0 125 250 500 Feet

N W E S

AVM Environmental Services, Inc.

Figure 5
Mt. Taylor Mine Site
Mine Compound Area Subsurface Soil Sample
On-Site Ex-Situ Soil Screening and Lab Results
and April 2023 Surface Gamma Scan Survey

**Legend**

**Ra-226 pCi/g**

- <1.8 pCi/g
- 1.9 - 6.8 pCi/g
- 6.9 - 10.0 pCi/g
- 10.1 - 20.0 pCi/g
- 20.1 - 30.0 pCi/g
- 30.1 - 40.0 pCi/g
- >40.1 pCi/g
- Soil Sample/Test Pit Location
- North Controlled Fence
- Soil Radiologic Characterization Area

Note: Ra-226 pCi/g is determined from surface soil gamma radiation scan using 2x2 NaI detector and Site specific gamma radiation level (cpm) correlation.

# Appendix A
# Surface Gamma Radiation Static Survey Field Forms

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Static Gamma Radiation Survey Field Form**

Instrumentation : Scaler/Ratemeter L2241-2 S#287029 Detector SPA-3 #30

Instrument Calibration Date: 10-7-22, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ✓ No.

Survey Area/Unit Decsription Mt. Taylor Mine Site

| Survey Date | Survey Point ID/Description | Survey Point Coordinate | | Gamma Radiation Reading - CPM | | Exposure Rate µR/hr | Comments/Notes |
|---|---|---|---|---|---|---|---|
| | | Northing | Easting | Bare | Collimated (0.5"Pb) | | |
| 5-17-23 | WBSB-01 | 1581412.80 | 2782866.15 | 26897 | 6297 | 33 | |
| 5-17-23 | WBSB-02 | 1581389.51 | 2782444.25 | 26749 | 6350 | 33 | |
| 5-17-23 | WBSB-03 | 1581356.39 | 2783329.27 | 24529 | 6073 | 31 | |
| 5-17-23 | WBSB-04 | 1581338.82 | 2782705.91 | 30064 | 6069 | 37 | |
| 5-17-23 | WBSB-05 | 1581328.80 | 2783062.43 | 31828 | 6945 | 41 | |
| 5-17-23 | WBSB-06 | 1581271.37 | 2782942.27 | 35410 | 7288 | 47 | |
| 5-17-23 | WBSB-07 | 1581187.28 | 2783252.71 | 37965 | 8183 | 47 | |
| 5-17-23 | WBSB-08 | 1581164.47 | 2782987.54 | 55849 | 11042 | 70 | |
| 5-31-23 | WBSB-09 | 1581254.28 | 2782870.27 | 36491 | 6599 | 44 | |
| 5-31-23 | WBSB-10 | 1581262.56 | 2783140.16 | 34898 | 7286 | 48 | |
| 5-31-23 | WBSB-11 | 1581277.45 | 2783335.44 | 29002 | 6602 | 34 | |
| 5-31-23 | WBSB-12 | 1581227.90 | 2782907.89 | 40341 | 7153 | 55 | |
| 5-31-23 | OPSB-01 | 1580834.11 | 2782884.42 | 2328550 | 716621 | 2100 | |
| 5-31-23 | OPSB-02 | 1580811.55 | 2783138.10 | 505097 | 160357 | 650 | |
| 5-31-23 | OPSB-03 | 1580599.03 | 2783012.73 | 700063 | 247434 | 900 | |
| 5-31-23 | OPSB-04 | 1580328.29 | 2782874.34 | 408698 | 133199 | 450 | |
| 5-31-23 | OPSB-05 | 1580386.28 | 2783136.44 | 446083 | 156044 | 450 | |
| 5-30-23 | MCSB-01 | 1579584.67 | 2783018.74 | 35807 | 10538 | 41 | |
| 5-30-23 | MCSB-02 | 1579573.01 | 2783166.70 | 34096 | 9678 | 39 | |
| 5-30 23 | MCSB-03 | 1579343.02 | 2782883.30 | 34019 | 9832 | 39 | |
| 5-30-23 | MCSB-04 | 1579317.49 | 2783098.04 | 34656 | 10811 | 40 | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Static Gamma Radiation Survey Field Form**

Instrumentation : Scaler/Ratemeter L2241-2 S#287029 Detector SPA-3 #30

Instrument Calibration Date: 10-7-22, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ✓ No.

Survey Area/Unit Decsription Mt. Taylor Mine Site

| Survey Date | Survey Point ID/Description | Survey Point Coordinate | | Gamma Radiation Reading - CPM | | Exposure Rate µR/hr | Comments/Notes |
|---|---|---|---|---|---|---|---|
| | | Northing | Easting | Bare | Collimated (0.5"Pb) | | |
| 5-24-23 | MCSB-05 | 1579183.08 | 2782701.94 | 52231 | 14892 | 65 | |
| 5-24-23 | MCSB-06 | 1579162.34 | 2783064.40 | 31976 ~~31967~~ | 8548 | 37 | |
| 5-24-23 | MCSB-07 | 1579040.09 | 2783009.78 | 52974 | 18511 | 65 | |
| 5-23-23 | MCSB-08 | 1578849.18 | 2782249.48 | 107010 | 39626 | 125 | |
| 5-23-23 | MCSB-09 | 1578849.89 | 2782581.54 | 28188 | 8193 | 33 | |
| 5-23-23 | MCSB-10 | 1578758.24 | 2782443.51 | 39814 | 12984 | 43 | |
| 5-22-23 | MCSB-11 | 1578610.92 | 2782257.53 | 53106 | 18055 | 60 | |
| 5-22-23 | MCSB-12 | 1578520.57 | 2782569.17 | 29299 | 9090 | 33 | |
| 5-22-23 | MCSB-13 | 1578300.74 | 2782557.01 | 21952 | 6254 | 25 | |
| 5-23-23 | MCSB-14 | 1578278.15 | 2782258.40 | 21642 | 6366 | 25 | |
| 5-18-23 | MCSB-15 | 1578214.43 | 2782398.32 | 48059 | 15633 | 51 | |
| 5-18-23 | MCSB-16 | 1578084.02 | 2782313.13 | 30445 | 11069 | 33 | |
| 5-18-23 | MCSB-17 | 1578084.66 | 2782598.61 | 18059 | 5891 | 19 | |
| 5-18-23 | MCSB-18 | 1578071.36 | 2782423.53 | 17170 | 5046 | 19 | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Static Gamma Radiation Survey Field Form**

Instrumentation : Scaler/Ratemeter 2241-2 S#287029 , Detector SPA-3 #30

Instrument Calibration Date: 10-7-22 , Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ✓ No.

Survey Area/Unit Decsription Mt. Taylor Mine Site

| Survey Date | Survey Point ID/Description | Survey Point Coordinate | | Gamma Radiation Reading - CPM | | Exposure Rate µR/hr | Comments/Notes |
|---|---|---|---|---|---|---|---|
| | | Northing | Easting | Bare | Collimated (0.5"Pb) | | |
| 5-31-23 | MCSD-19 | 1578837 | 2782317 | 69850 | 24522 | 80 | |
| 5-31-23 | MCSB-20 | 1578650 | 2782298 | 55167 | 18497 | 65 | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

# Appendix B

## Surface and Subsurface Contamination Field Investigation Documentation
## Soil Sample Log Forms
## Field Soil Sample Ex-Situ Gamma Radiation Screening Forms
## Soil Sample COCs and Laboratory Analytical Result Reports)

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| WBSB-02 0-0.5' | 0815 5-17-23 | 0-6" | Light brown Alluvium Loam | Surface Soil dry |
| WBSB-02 1.0-1.5' | 0820 5-17-23 | 1.0-1.5' | Brown Silty Clay | Moist soil |
| WBSB-04 0-0.5' | 0835 5-17-23 | 0-6" | Light brown Alluvium - Loam | |
| WBSB-04 1.0'-1.5' | 0845 5-17-23 | 1.0'-1.5' | Brown Silty Clay | |
| WBSB-01 0-0.5' | 0855 5-17-23 | 0-6" | Light brown Alluvium Loam | |
| WBSB-01 1.0-1.5' | 0906 5-17-23 | 1.0'-1.5' | Brown Silty clay | |
| WBSB-05 0-0.5' | 0920 5-17-23 | 0-6" | Light brown Alluvium - Loam | |
| WBSB-05 1.0'-1.5' | 0930 5-17-23 | 1.0'-1.5' | brown Silty Clay | |
| WBSB-03 0-0.5' | 0942 5-17-23 | 0-6" | Light brown Alluvium - Loam | |
| WBSB-03 1.0'-1.5' | 0948 5-17-23 | 1.0'-1.5' | brown silty clay | |
| WBSB-07 0-6" | 1014 5-17-23 | 0-6" | Light brown Alluvium Loam | |
| WBSB-07 1.0'-1.5' | 1020 5-17-23 | 1.0'-1.5' | brown silty clay | |
| WBSB-08 0-0.5" MS | 1034 5-17-23 | 0-6" | Light brown Alluvium - Loam | |
| WBSB-08 1.0-1.5 | 1042 5-17-23 | 1.0'-1.5' | brown Silty Clay | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| WBSB-06 0-0.5' | 1054 5-17-23 | 0-6" | Light brown Alluvium - Loam | |
| WBSB-06 1.0-1.5' | 1100 5-17-23 | 1.0'-1.5' | brown silty clay | |
| WBSB-09 0-6" | 5-31-23 @825 | 0-6" | light brown Alluvium Sandy | |
| WBSB-09 6-12" | 5-31-23 @835 | 6-12" | brown Silty Clay | |
| WBSB-12 0-1" | 5-31-23 @850 | 0-1" | Alluvium brown Sandy | |
| WBSB-12 2-6" | 5-31-23 @900 | 2-6" | brown loam / Sand | |
| WBSB-10 0-6" | 5-31-23 @910 | 0-6" | Alluvium light brown Sandy | |
| WBSB-10 6-12" | 5-31-23 @915 | 6-12" | brown loam / Roots | |
| WBSB-11 0-6" | 5-31-23 @935 | 0-6' | Alluvium light brown Sandy | |
| WBSB-11 6-10" | 5-31-23 940 | 6-10" | Sandstone / Sand. | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| MCSB-17 1' 5-18-23 | 5-18-23 845 | 1' | | 0-1' gravel/Road base @1' appears native |
| MCSB-17 2 | 5-18-23 857 | 2' | | native to Depth of 5.5' |
| MCSB-18-1-1.5 | 5-18-23 948 | 1-1.5' | | |
| MCSB-18 2 | 5-18-23 958 | 2' | clay Sand loam Dark Conglomerate multi-Color | Metal Debris @ 2.5' |
| MCSB-18 3 | 5-18-23 1010 | 3' | Charcoal-Rust light Brown | |
| MCSB-18 4 | 5-18-23 1018 | 4' | Clay Dk Brown | native @ ± 5' |
| MCSB-16 1 | 5-18-23 1045 | 1' | Rocky light grey/green | Top 1' ± 5" soil) ± 5" gravel |
| MCSB-16 2 | 5-18-23 1100 | 2' | light brown Alluvium/Sand | |
| MCSB-16 3 | 5-18-23 1110 | 3' | light grayish/Brown mix of Shale | |
| MCSB-16 4 | 5-18-23 1120 | 4' | | |
| MCSB-15 1 | 5-18-23 1138 | 1' | Brown clay/Sand | from borrow A or B |
| MCSB-15 2 | 5-18-23 1145 | 2' | " " /gravel Roadbase | |
| MCSB-15 3 | 5-18-23 1158 | 3' | Brown Clay/Sand grey | |
| MCSB-15 4 | 5-18-23 1212 | 4' | Brown Clay/Sand | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| MCSB-13 - 1' | 5-22-23 825 | 1' | 0-4" Road base<br>4-12" Dark Silt Clay | |
| MCSB-13 2' | 5-22-23 839 | 2' | 1'-2' Dark Silt Clay | |
| MCSB-13 3' | 5-22-23 851 | 3' | Light/Dark Silt Clay | |
| MCSB-13 4' | 5-22-23 905 | 4' | Sandstone<br>light brown Sandy/Silt Soil | some @ 6' |
| MCSB-12 1' | 5-22-23 928 | 1' | 0-6" Road base<br>6"-12" Large gravel ¾"-1" | |
| MCSB-12 2' | 5-22-23 935 | 2' | odor/DRO<br>Dark/Black gravel | |
| MCSB-12 3' | 5-22-23 948 | 3' | Brown Silty/Sandy Hard pack | |
| MCSB-12 4' | 5-22-23 956 | 4' | " " " | |
| MCSB-11 1' | 5-22-23 1030 | 1' | 0-4" Road base<br>4-12" Grey Rocky loose Waste Rock | |
| MCSB-11 2' | 5-22-23 1040 | 2' | White Rock<br>Dark Grey Rocky loose Soil | |
| MCSB-11 3' | 5-22-23 1050 | 3' | Grey Waste Rock/Brown Silty mix | |
| MCSB-11 4' | 5-22-23 1104 | 4' | Dark brown/Rocky = Interface | |
| MCSB-11 5' | 5-22-23 1112 | 5' | Pebbles<br>Dark brown/~~Rocky~~ Clay | appears native @ 6.5' |
| MCSB-11 6' | 5-23-23 835 | 6' | Dark brown Clay/Sand | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| MCSB-14 1' | 5-23-23 853 | 1' | Cobble Dark brown topsoil maybe backfill | |
| MCSB-14 2' | 5-23-23 905 | 2' | Grey/mine waste | metal Debris @ 1-2' |
| MCSB-14 3' | 5-23-23 915 | 3' | " " " | metal Debris hoses etc. |
| MCSB-14 4' | 5-23-23 920 | 4' | " " " | Debris |
| MCSB-14 5' | 5-23-23 932 | 5' | Dark brown Clay | |
| MCSB-14 6' | 5-23-23 950 | 6' | " " | Clay & Charcoal Past 6' |
| MCSB-08 1' | 5-23-23 1035 | 1' | Clay mix w/ Mine Waste Rock | |
| MCSB-08 2' | 5-23-23 1045 | 2' | " " " | |
| MCSB-08 3' | 5-23-23 1058 | 3' | " " " Sandy | |
| MCSB-08 5' | 5-23-23 1110 | 5' | Sandy/clay mine Waste | 3'-5' Same material |
| MCSB-08 6.5' | 5-23-23 1125 | 6.5' | Sandy mix Dark/Black DRO smell | 2'-6' Same waste sandy |
| MCSB-08 ~~11.5'~~ 12' | 5-23-23 1145 | 12' | Dark Rocky Clay | |
| MCSB-09 1' | 5-24-23 825 | 1' | 0-6" Road base 6-12" Road base | 0-2' Road base |
| MCSB-09 2' | 5-24-23 840 | 2' | Brown Sandy Soil | |
| MCSB-09 3' | 5-24-23 850 | 3' | " " " | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| MCSB-09 4' | 5-24-23 900 | 4' | Brown Sandy Soil | |
| MCSB-10 1' | 5-24-23 915 | 1' | Road Base | |
| MCSB-10 2' | 5-24-23 922 | 2' | unconsolidated light brown silty Sand | |
| MCSB-10 3' | 5-24-23 930 | 3' | Clay Dark Brown " " | |
| MCSB-10 4' | 5-24-23 943 | 4' | clay Dark Brown / Sandy Silty | |
| MCSB-10 5' | — | 5' | Dark Brown / Sandy - Clay | |
| MCSB-5 1' | 5-24-23 @1010 | 1' | 0-6" Road base Brown Silty Soil | |
| MCSB-5 2' | 5-24-23 @1020 | 2' | Brown silty Soil | |
| MCSB-5 3' | 5-24-23 @1030 | 3' | " " " Rocky | |
| MCSB-5 4' | 5-24-23 @1040 | 4' | " " " " | |
| MCSB-5 ~~5~~ 6' | 5-24-23 @1100 | 6' | gravel / Sandy Rocky | 6'-7' gravel Sandy Road base |
| MCSB-5 7.5' | 5-24-23 @1110 | 7.5' | Dark brown Silty Soil | Starts @ ≈ 7' |
| MCSB-07 1' | 5-24-23 @1220 | 1' | 0 ≈ 8" Gravel | |
| MCSB-07 2' | 5-24-23 @1232 | 2' | Dark Clay / bentonite Silts | |
| MCSB-07 3' | 5-24-23 @1246 | 3' | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| MCSB-07 4.5' | 5-24-23 @1300 | 4.5' | light brown Sandy Silty | |
| MCSB-07 5.5' | 5.24.23 @1310 | 5.5' | light brown Clay / grey clay | |
| MCSB-07 6.6' | 5-24-23 @ | 6.6' | No Sample Same as above | |
| MCSB-06 1' | 5-30-23 @822 | 1' | 0-8" Road Road base 1" Dark brown Soil gravel mix | VP ~~Slight Ore Grade~~ |
| MCSB-06 2' | 5-30-23 @835 | 2' | Dark brown Rock clay w gravel 1" | |
| MCSB-06 3.25 | 5-30-23 @850 | 3.25 | " " " " | Metal Debris @ 2.5' |
| MCSB-06 4.25' | 5-30-23 @900 | 4.25 | Dark brown Silty/clay | ~4' non-mineralized ore body. |
| MCSB-06 6' | 5-30-23 @915 | 6' | Silty/Rocky w/ Clay | |
| MCSB-06 6.5' | 5-30-23 | 6.5 | No Sample Clay w/ Silty/loose | |
| MCSB-04 1' | 5-30-23 @935 | 1' | 0-6" Road base Red 6-12" Brown Silty w/ gravel | |
| MCSB-04 2' | 5-30-23 @945 | 2' | All Road base 0-2' light Brown | |
| MCSB-04 3.5' | 5-30-23 @955 | 3.5' | Darkish Rocky Silty Sandy Mix Rocky | |
| MCSB-04 4.5' | 5-30-23 @1005 | 4.5' | Dark brown Silty w/ light gravel/cobble Clay | |
| MCSB-04 5'-6' | 5-30-23 | 5'-6' | Clay Consolidated Silty Dark brown | bank |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| MCSB-02 1' | 5-30-23 @ 1030 | 1' | 0-6" Red Road base | |
| MCSB-02 2' | 5-30-23 @ 1040 | 2' | Clay Silt mix w/ 3/4" gravel | |
| MCSB-02 3' | 5-30-23 @ 1050 | 3' | grey clay / silty bentonite greenish / black | |
| MCSB-02 4' | 5-30-23 @ 1100 | 4' | loose, sandy silt / gravel light brown (reddish) gravel | DRO odor (slight) |
| MCSB-02 5.2' | 5-30-23 @ 1115 | 5.2' | dark brown, silty unconsolidated clay | |
| MCSB-02 6.2' | 5-30-23 @ | 6.2' | " " " no Sample | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| MCSB-01 1' | 5-30-23 @1240 | 1' | 3" gravel road base ~~dark~~ brown clay mixed w/ gravel | |
| MCSB-01 - 2' | 5-30-23 @1250 | 2' | brown loomy ~~&~~ clay w/gravel | |
| MCSB-01 3' | 5-30-23 @900 | 3' | brown loomy no gravel | |
| MCSB-01 4' | 5-30-23 @0115 | 4' | brown loom/clay no gravel | |
| MCSB-01 6' | 5-30-23 no sample | 6' | " " " | |
| MCSB-03 1' | 5-30-23 @0140 | 1' | light brown loomy w/some gravel | 0-8" roadbase gravel 3/4" |
| MCSB-03 2' | 5-30-23 @0150 | 2' | brown loomy no gravel | |
| MCSB-03 3' | 5-30-23 @0200 | 3' | brown sandy/loom no gravel | |
| MCSB-03 4.25' | NO sample | | " " " | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| OPSB-04 0-4' | 6-1-23 @815 | 0-4' | 0-4' Grey Waste Rock | |
| OPSB-04 4.8', ~~4.83~~ UP | 6-1-23 @825 | 4.8', ~~4.10~~ UP | Dark Clay / brown Silty | |
| OPSB-04 4.5' | 6-1-23 @835 | 4.5' | Mix Clay & Waste Rock | Interface |
| OPSB-03 0-4' | 6-1-23 @850 | 0-4' | Waste Rock light/Dark Grey | |
| OPSB-03 4.2' | 6-1-23 @910 | 4.2' | mix Clay / waste Rock | Interface |
| OPSB-03 4.5' | 6-1-23 @925 | 4.5' | Dark brown Clay | |
| OPSB-01 0-13' | 6-1-23 @1025 | 0-13' | Waste Rock - Grey | |
| OPSB-01 13.5' | 6-1-23 @1020 | 13.5' | Waste Rock - Grey | limit of backhoe |
| OPSB-02 4.5' | 6-1-23 @1100 | 4.5' | Dark Clay / waste Rock | Interface |
| OPSB-02 0-4' | 6-1-23 @1115 | 0-4' | Dark Grey - Sandy waste Rock | |
| OPSB-02 5.5' | 6-1-23 @1120 | 5.5' | light brown Sandy Silty | |
| OPSB-05 3' | 6-1-23 @1140 | 3' | Dark Clay / Waste Rock | Interface |
| OPSB-05 3.75' | 6-1-23 @1155 | 3.75' | light brown Sandy Silty | |
| OPSB-05 0-3' | 6-1-23 @1200 | 0-3' | Waste Rock | |
| | | | | |

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 SN 68782, Detector L44-20 S# 295573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt. Taylor Mine Site

Area exposure rate: 10-12

| Date/Time | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 5-17-23 | Blank | – | 349 | | 70 | | |
| 5-17-23 | 6.6 pCi/g Ra-226 | 3000 | 2682 | | 536 | | |
| 5-17-23 | WBSB 01 0-6" @855 | 3000 | 1406 | | 282 | | |
| 5-17-23 | WBSB 01 1'-1.5' @906 | 3000 | 1244 | | 249 | | |
| 5-17-23 | WBSB 02 0-6" @815 ~~820~~ | 3000 | 1577 | | 315 | | |
| 5-17-23 | WBSB 02 1'-1.5' @920 | 2958 | 1008 | 1022 | 204 | | |
| 5-17-23 | WBSB 03 0-6" 5-17-23 @942 | 3000 | 2039 | | 408 | | |
| 5-17-23 | WBSB 03 1'-1.5' 5-17-23 @948 | 3000 | 1136 | | 227 | | |
| 5-17-23 | WBSB 04 0-6" 5-17-23 @835 | 3000 | 1521 | | 304 | | |
| 5-17-23 | WBSB 04 1'-1.5' 5-17-23 @845 | 2840 | 1189 | 1256 | 251 | | |
| 5-17-23 | WBSB 05 0-6" 5-17-23 @920 | 3000 | 1747 | | 349 | | |
| 5-17-23 | WBSB 05 1'-1.5' 5-17-23 @930 | 2835 | 1086 | 1149 | 230 | | QA/QC CPSM: 1093 |
| 5-17-23 | WBSB 06 0-6" 5-17-23 @1054 | 3000 | 1406 | | 281 | | |
| 5-17-23 | WBSB-06 1-1.5' 5-17-23 @1100 | 2876 | 1004 | 1047 | 209 | | |
| 5-17-23 | WBSB-07 0-6" 5-17-23 @1014 | 3000 | 2272 | | 454 | | |

Technician Signature _____, Reviewed by MO

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S# 68782 , Detector L44-20 S# 295573
Instrument Calibration Date: 5-10-23 , Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt. Taylor Mine Site

Area exposure rate: 10-12

| Date/Time | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 5-17-23 | WBSB-07 1'-1.5' 5-17-23 @ 930 | 3000 | 1082 | | 216 | | |
| 5-17-23 | WBSB-08 0-6" 5-17-23 @ 1034 | 3000 | 4140 | | 828 | | QA/QC CPSM: 4183 |
| 5-17-23 | WBSB-08 1'-1.5' 5-17-23 @ 1042 | 3000 | 1118 | | 224 | | |
| 5-18-23 | Blank | | 330 | | 66 | | |
| 5-18-23 | 6.6pCi/g $R_a$-226 | 3000 | 2695 | | 539 | | |
| 5-18-23 | MCSB-15 4 5-18-23 @ 1212 | 3000 | 1415 | | 283 | | |
| 5-18-23 | MCSB-16 4 5-18-23 @ 1120 | 3000 | 1280 | | 256 | | |
| 5-18-23 | MCSB-17 2' 5-18-23 @ 857 | 3000 | 1070 | | 214 | | |
| 5-18-23 | MCSB 18 3' 5-18-23 @ 1010 | 3000 | 1306 | | 261 | | |
| 5-18-23 | MCSB 15 3' 5-18-23 @ 1158 | 3000 | 2206 | | 441 | | |
| 5-18-23 | MCSB 16 3' 5-18-23 @ 1110 | 3000 | 1587 | | 317 | | |
| 5-18-23 | MCSB 17 1' 5-18-23 @ 845 | 3000 | 974 | | 195 | | |
| 5-18-23 | MCSB 18 2' 5-18-23 @ 958 | 3000 | 1321 | | 264 | | |
| 5-18-23 | MCSB 15 2' 5-18-23 @ 1145 | 3000 | 1389 | | 278 | | |
| 5-18-23 | MCSB 16 2' 5-18-23 @ 1100 | 3000 | 1646 | | 329 | | QA/QC CPSM: 1621 |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S# 68782, Detector L44-20 S# 295573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt. Taylor Mine Site

Area exposure rate: 10-12

| Date/Time | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 5-18-23 | MCSB-18 1-1.5' 5-18-23 @ 943 | 3000 | 1634 | | 327 | | |
| 5-18-23 | MCSB-15 1' 5-18-23 1138 | 3000 | 1503 | | 301 | | |
| 5-18-23 | MCSB-16 1' 5-18-23 @ 1045 | 3000 | 2498 | | 500 | | |
| 5-22-23 | Blank | — | 342 | | 68 | | |
| 5-22-23 | 6.6 pCi/g Ra-226 | 3000 | 2755 | | 551 | | |
| 5-22-23 | MCSB-11 5' 5-22-23 @ 1112 | 3000 | 2036 | | 407 | | |
| 5-22-23 | MCSB-12 4' 5-22-23 @ 956 | 3000 | 923 | | 185 | | |
| 5-22-23 | MCSB-13 4' 5-22-23 @ 905 | 3000 | 1210 | | 242 | | |
| 5-22-23 | MCSB-12 3' 5-22-23 @ 948 | 3000 | 915 | | 183 | | |
| 5-22-23 | MCSB-12 2' 5-22-23 @ 935 | 3000 | 1793 | | 359 | | |
| 5-22-23 | MCSB-12 1' 5-22-23 @ 928 | 3000 | 1957 | | 391 | | |
| 5-22-23 | MCSB-13 3' 5-22-23 @ 851 | 3000 | 1309 | | 262 | | |
| 5-22-23 | MCSB-13 2' 5-22-23 @ 839 | 3000 | 1253 | | 251 | | |
| 5-22-23 | MCSB-13 1' 5-22-23 @ 825 | 3000 | 1197 | | 239 | | |
| 5-22-23 | MCSB-11 4' 5-22-23 @ 1104 | 3000 | 3871 | | 774 | | QA/QC CP5M: 3855 |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S#68782 , Detector L44-20 S# 295573
Instrument Calibration Date: 5-10-23 , Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt. Taylor Mine Site

Area exposure rate: 10-12

| Date/Time | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 5-22-23 | MCSB-11 3' 5-22-23 @ 1050 | 3000 | 15497 | | 3099 | | |
| 5-22-23 | MCSB-11 2' 5-22-23 @ 1040 | 3000 | 42761 | | 8552 | | |
| 5-22-23 | MCSB-11 1' 5-22-23 @ 1030 | 3000 | 12907 | | 2581 | | |
| 5-23-23 | Blank | | 357 | | 71 | | |
| 5-23-23 | 6.6 pCi/g Ra-226 | 3000 | 2930 | | 586 | | |
| 5-23-23 | MCSB-11 6' 5-23-23 @ 835 | 3000 | 1824 | | 365 | | |
| 5-23-23 | MCSB-08 12' 5-23-23 @ 1145 | 3000 | 2421 | | 484 | | |
| 5-23-23 | MCSB-14 6' 5-23-23 @ 950 | 3000 | 1059 | | 212 | | |
| 5-23-23 | MCSB-14 5' 5-23-23 @ 932 | 3000 | 1274 | | 255 | | |
| 5-23-23 | MCSB-08 6.5' 5-23-23 @ 1125 | 3000 | 1266 | | 253 | | |
| 5-23-23 | MCSB-08 1' 5-23-23 @ 1035 | 3000 | 29705 | | 5941 | | |
| 5-23-23 | MCSB-14 1' 5-22-23 @ 853 | 3000 | 1982 | | 396 | | |
| 5-23-23 | MCSB-14 4' 5-23-23 @ 920 | 3000 | 1795 | | 359 | | |
| 5-23-23 | MCSB-14 3' 5-23-23 @ 915 | 3000 | 1856 | | 371 | | |
| 5-23-23 | MCSB-14 2' 5-23-23 @ 905 | 3000 | 1942 | | 388 | | QA/QC CPGM: 1942 |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S# 68782, Detector L44-20 S# 295573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt Taylor Mine Site

Area exposure rate: 10-12

| Date/Time | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 5-23-23 | MCSB-8 5' 5-23-23 @1110 | 3000 | 33460 | | 6692 | | |
| 5-23-23 | MCSB-8 3' 5-23-23 @1058 | 3000 | 19380 | | 3876 | | |
| 5-23-23 | MCSB-8 2' 5-23-23 @1045 | 3000 | 34740 | | 6948 | | |
| 5-25-23 | Blank | — | 363 | | 73 | | |
| 5-25-23 | 6.6 pCi/g $R_a$-226 | 3000 | 2776 | | 555 | | |
| 5-25-23 | MCSB-10 4' 5-24-23 @943 | 3000 | 1055 | | 211 | | |
| 5-25-23 | MCSB-9 4' 5-24-23 @900 | 3000 | 1082 | | 216 | | |
| 5-25-23 | MCSB-7 5.5' 5-24-23 @1310 | 3000 | 1607 | | 321 | | |
| 5-25-23 | MCSB-5 7.5' 5-24-23 @1110 | 3000 | 1150 | | 230 | | |
| 5-25-23 | MCSB-9 3' 5-24-23 @850 | 3000 | 1056 | | 211 | | |
| 5-25-23 | MCSB-9 2' 5-24-23 @840 | 3000 | 980 | | 196 | | |
| 5-25-23 | MCSB-9 1' 5-24-23 @825 | 3000 | 4191 | | 838 | | |
| 5-25-23 | MCSB-10 3' 5-24-23 @930 | 3000 | 930 | | 186 | | |
| 5-25-23 | MCSB-10 2' 5-24-23 @922 | 3000 | 913 | | 183 | | |
| 5-25-23 | MCSB-10 1' 5-24-23 @915 | 3000 | 920 | | 184 | | QA/QC CP5M: 935 |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L 2221 S#68782, Detector L 44-20 S# 295573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt. Taylor Mine Site

Area exposure rate: 10-12

| Date/Time | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 5-25-23 | MCSB-05 6' 5-24-23 @1100 | 3000 | 6564 | | 1313 | | |
| 5-25-23 | MCSB-05 4' 5-24-23 @1040 | 3000 | 1262 | | 252 | | |
| 5-25-23 | MCSB-05 3' 5-24-23 @1030 | 3000 | 1162 | | 232 | | |
| 5-25-23 | MCSB-05 2' 5-24-23 @1020 | 3000 | 1309 | | 262 | | |
| 5-25-23 | MCSB-05 1' 5-24-23 @1010 | 3000 | 1183 | | 237 | | |
| 5-25-23 | MCSB-07 4.5' 5-24-23 @1300 | 3000 | 1396 | | 279 | | |
| 5-25-23 | MCSB-07 3' 5-24-23 @1246 | 3000 | 2872 | | 574 | | |
| 5-25-23 | MCSB-07 2' 5-24-23 @1232 | 3000 | 1333 | | 267 | | |
| 5-25-23 | MCSB-07 1' 5-24-23 @1220 | 3000 | 10973 | | 2195 | | |
| 5-30-23 | Blank | — | 360 | | 72 | | |
| 5-30-23 | 6.6 pCi/g $Ra_{-226}$ | 3000 | 2848 | | 570 | | |
| 5-30-23 | MCSB-06 6' 5-30-23 @915 | 3000 | 1311 | | 262 | | |
| 5-30-23 | MCSB-04 4.5' 5-30-23 @1005 | 3000 | 1274 | | 255 | | |
| 5-30-23 | MCSB-02 5.2' 5-30-23 @1115 | 3000 | 1426 | | 285 | | |
| 5-30-23 | MCSB-02 4' 5-30-23 @1100 | 3000 | 5236 | | 1047 | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S/N 68782, Detector L44-20 S/N 295573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt. Taylor Mine Site

Area exposure rate: 10-12

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 5-30-23 | MCSB-02 3' 5-30-23 @1050 | 3000 | 947 | | 189 | | |
| 5-30-23 | MCSB-02 2' 5-30-23 @1040 | 3000 | 1620 VP 3000 | | 324 | | |
| 5-30-23 | MCSB-02 1' 5-30-23 @1030 | 3000 | 1243 VP 30 | | 249 | | |
| 5-30-23 | MCSB-06 4.25 5-30-23 @900 | 3000 | 1091 | | 218 | | |
| 5-30-23 | MCSB-06 3.25 5-30-23 850 | 3000 | 1477 | | 295 | | |
| 5-30-23 | MCSB-06 2' 5-30-23 @835 | 3000 | 4112 | | 822 | | QA/QC CP5M: 4168 |
| 5-30-23 | MCSB-06 1' 5-30-23 @822 | 3000 | 19543 | | 3909 | | |
| 5-30-23 | MCSB-01 4' 5-30-23 @1315 | 3000 | 1120 | | 224 | | |
| 5-30-23 | MCSB-04 3.5' 5-30-23 @955 | 3000 | 1017 | | 203 | | |
| 5-30-23 | MCSB-04 2' 5-30-23 @945 | 3000 | 1919 | | 384 | | |
| 5-30-23 | MCSB-04 1' 5-30-23 @935 | 3000 | 1055 | | 211 | | |
| 5-30-23 | MCSB-01 3' 5-30-23 @1300 | 3000 | 1240 | | 248 | | |
| 5-30-23 | MCSB-01 2' 5-30-23 @1250 | 3000 | 2965 | | 593 | | |
| 5-30-23 | MCSB-01 1' 5-30-23 @1240 | 3000 | 2326 | | 465 | | |
| 5-30-23 | MCSB-03 3' 5-3-23 @1400 | 3000 | 1279 | | 256 | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S#68782, Detector L44-20 S# 295573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt taylor Mine Site

Area exposure rate: 10-12

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 5-30-23 | MCSB-03 2' 5-30-23 @1350 | 3000 | 1201 | | 240 | | QA/QC CP5M: 1194 |
| 5-30-23 | MCSB-03 1' 5-30-23 @1340 | 3000 | 3386 | | 677 | | |
| 5-31-23 | Blank | — | 320 | | 64 | | |
| 5-31-23 | 6.6 pCi/g Ra-226 | 3000 | 2679 | | .536 | | |
| 5-31-23 | WBSB-09 0-6" 5-31-23 @825 | 3000 | 1393 | | 279 | | |
| 5-31-23 | WBSB-09 6-12" 5-31-23 @835 | 3000 | 1170 | | 234 | | |
| 5-31-23 | WDSB-10 0-6" 5-31-23 @910 | 3000 | 2217 | | 443 | | |
| 5-31-23 | WBSB-10 6-12" @ 5-31-23 915 | 3000 | 1380 | | 276 | | |
| 5-31-23 | WBSB-11 0-6" 5-31-23 @935 | 3000 | 1959 | | 392 | | |
| 5-31-23 | WBSB-11 6-12" 5-31-23 @940 | 2008 JP | 1053 | 1573 | 315 | | |
| 5-31-23 | WBSB-12 0-1" 5-31-23 @850 | 3000 | 1736 | | 347 | | |
| 5-31-23 | WBSB-12 2-6" 5-31-23 @900 | 3000 | 1117 | | 223 | | |
| 6-1-23 | Blank | — | 355 | | 71 | | |
| 6-1-23 | 6.6 pCi/g | 3000 | 2644 | | 529 | | |
| 6-1-23 | OPSB-05 3.75' 6-1-23 @1155 | 3000 | 1587 | | 317 | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L 2221 S#68782, Detector L44-20 S# 245573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt. Taylor Mine Site

Area exposure rate: 10-12

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 6-1-23 | OPSB-03 4.5' 6-1-23 @ 925 | 3000 | 1193 | | 239 | | |
| 6-1-23 | OPSB-02 5.5' 6-1-23 @ 1120 | 3000 | 1189 | | 238 | | |
| 6-1-23 | OPSB-04 ~~4'~~ 4.10" 6-1-23 @ 825 | 3000 | 1124 | | 225 | | 4.8' |
| 6-1-23 | OPSB-05 3' 6-1-23 @ 1140 | 3000 | 5526 | | 1105 | | |
| 6-1-23 | OPSB-03 4.2' 6-1-23 @ 910 | 1708 | 2091 | 3673 | 735 | | |
| 6-1-23 | OPSB-02 4.5' 6-1-23 @ 1100 | 3000 | 35425 | | 7085 | | |
| 6-1-23 | OPSB-04 4.5' 6-1-23 @ 835 | 3000 | 4373 | | 875 | | |
| 6-1-23 | OPSB-01 13.5' 6-1-23 @ 1020 | 3000 | 11560 | | 2312 | | QA/QC CP5M: 11423 |
| 6-1-23 | OPSB-01 0-13' 6-1-23 @ 1025 | 3000 | 26904 | | 5381 | | |
| 6-1-23 | OPSB-02 0-4' 6-1-23 @ 1115 | 3000 | 182551 | | 36510 | | |
| 6-1-23 | OPSB-03 0-4' 6-1-23 @ 850 | 3000 | 56365 | | 11273 | | |
| 6-1-23 | OPSB-04 0-4' 6-1-23 @ 815 | 3000 | 8428 | | 1686 | | |
| 6-1-23 | OPSB-05 0-3' 6-1-23 @ 1200 | 3000 | 32147 | | 6429 | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

# ANALYTICAL SUMMARY REPORT

August 07, 2023

Rio Grande Resources Corporation
PO Box 1150
Grants, NM 87020-1150

Work Order: C23060688 Quote ID: C16056

Project Name: MTM Subsurface soil investigation

Energy Laboratories, Inc. Casper WY received the following 53 samples for Rio Grande Resources Corporation on 6/19/2023 for analysis.

| Lab ID | Client Sample ID | Collect Date | Receive Date | Matrix | Test |
|---|---|---|---|---|---|
| C23060688-001 | WBSB-02 0-6" | 05/17/23 8:15 | 06/19/23 | Soil | Gamma Sample Preparation Drying/Grinding, Radiochemistry Gross Gamma |
| C23060688-002 | WBSB-04 0-6 | 05/17/23 8:35 | 06/19/23 | Soil | Same As Above |
| C23060688-003 | WBSB-01 0-6' | 05/17/23 8:55 | 06/19/23 | Soil | Same As Above |
| C23060688-004 | WBSB-05 0-6" | 05/17/23 9:20 | 06/19/23 | Soil | Same As Above |
| C23060688-005 | WBSB-03 0-6" | 05/17/23 9:42 | 06/19/23 | Soil | Same As Above |
| C23060688-006 | WBSB-07 0-6" | 05/17/23 10:14 | 06/19/23 | Soil | Same As Above |
| C23060688-007 | WBSB-08 0-6" | 05/17/23 10:34 | 06/19/23 | Soil | Same As Above |
| C23060688-008 | WBSB-08 1'-1.5' | 05/17/23 10:42 | 06/19/23 | Soil | Same As Above |
| C23060688-009 | WBSB-06- 0-6" | 05/17/23 10:54 | 06/19/23 | Soil | Same As Above |
| C23060688-010 | DSSB-01 | 05/17/23 12:00 | 06/19/23 | Soil | Same As Above |
| C23060688-011 | MCSB-16 1' | 05/18/23 10:45 | 06/19/23 | Soil | Same As Above |
| C23060688-012 | MCSB-16 2' | 05/18/23 11:00 | 06/19/23 | Soil | Same As Above |
| C23060688-013 | MCSB-15 1' | 05/18/23 11:38 | 06/19/23 | Soil | Same As Above |
| C23060688-014 | MCSB-17 1' | 05/18/23 8:45 | 06/19/23 | Soil | Same As Above |
| C23060688-015 | MCSB-18 1'-1.5' | 05/18/23 9:48 | 06/19/23 | Soil | Same As Above |
| C23060688-016 | DSSB-02 | 05/18/23 13:00 | 06/19/23 | Soil | Same As Above |
| C23060688-017 | MCSB-11 4' | 05/22/23 11:04 | 06/19/23 | Soil | Same As Above |
| C23060688-018 | MCSB-13 1' | 05/22/23 8:25 | 06/19/23 | Soil | Same As Above |
| C23060688-019 | MCSB-12 1' | 05/22/23 9:28 | 06/19/23 | Soil | Same As Above |
| C23060688-020 | MCSB-11 5' | 05/22/23 11:12 | 06/19/23 | Soil | Same As Above |
| C23060688-021 | MCSB-14 1' | 05/23/23 8:53 | 06/19/23 | Soil | Same As Above |
| C23060688-022 | MCSB-08 5' | 05/23/23 11:10 | 06/19/23 | Soil | Same As Above |
| C23060688-023 | MCSB-08 6.5' | 05/23/23 11:25 | 06/19/23 | Soil | Same As Above |
| C23060688-024 | MCSB-9 1' | 05/24/23 8:25 | 06/19/23 | Soil | Same As Above |
| C23060688-025 | MCSB-9 2' | 05/24/23 8:40 | 06/19/23 | Soil | Same As Above |
| C23060688-026 | MCSB-10 1' | 05/24/23 9:15 | 06/19/23 | Soil | Same As Above |

# ANALYTICAL SUMMARY REPORT

| | | | | | |
|---|---|---|---|---|---|
| C23060688-027 | MCSB-5 4' | 05/24/23 10:40 | 06/19/23 | Soil | Same As Above |
| C23060688-028 | MCSB-5 6' | 05/24/23 11:00 | 06/19/23 | Soil | Same As Above |
| C23060688-029 | MCSB-5 7.5' | 05/24/23 11:10 | 06/19/23 | Soil | Same As Above |
| C23060688-030 | MCSB-7 3' | 05/24/23 12:46 | 06/19/23 | Soil | Same As Above |
| C23060688-031 | MCSB-7 4.5' | 05/24/23 13:00 | 06/19/23 | Soil | Same As Above |
| C23060688-032 | DSSB-03 | 05/24/23 13:30 | 06/19/23 | Soil | Same As Above |
| C23060688-033 | MCSB-06 6' | 05/30/23 9:15 | 06/19/23 | Soil | Same As Above |
| C23060688-034 | MCSB-04 1' | 05/30/23 9:35 | 06/19/23 | Soil | Same As Above |
| C23060688-035 | MCSB-04 2' | 05/30/23 9:45 | 06/19/23 | Soil | Same As Above |
| C23060688-036 | MCSB-02 3' | 05/30/23 10:50 | 06/19/23 | Soil | Same As Above |
| C23060688-037 | MCSB-02 4' | 05/30/23 11:00 | 06/19/23 | Soil | Same As Above |
| C23060688-038 | MCSB-02 5.2' | 05/30/23 11:15 | 06/19/23 | Soil | Same As Above |
| C23060688-039 | MCSB-01 2' | 05/30/23 12:50 | 06/19/23 | Soil | Same As Above |
| C23060688-040 | MCSB-01 3' | 05/30/23 13:00 | 06/19/23 | Soil | Same As Above |
| C23060688-041 | MCSB-03 1' | 05/30/23 13:40 | 06/19/23 | Soil | Same As Above |
| C23060688-042 | MCSB-03 2' | 05/30/23 13:50 | 06/19/23 | Soil | Same As Above |
| C23060688-043 | DSSB-04 | 05/30/23 14:15 | 06/19/23 | Soil | Same As Above |
| C23060688-044 | WBSB-09 0-6" | 05/31/23 8:25 | 06/19/23 | Soil | Same As Above |
| C23060688-045 | WBSB-12 0-1" | 05/31/23 8:50 | 06/19/23 | Soil | Same As Above |
| C23060688-046 | WBSB-12 2-6" | 05/31/23 9:00 | 06/19/23 | Soil | Same As Above |
| C23060688-047 | WBSB-10 0-6" | 05/31/23 9:10 | 06/19/23 | Soil | Same As Above |
| C23060688-048 | WBSB-11 0-6" | 05/31/23 9:35 | 06/19/23 | Soil | Same As Above |
| C23060688-049 | OPSB-03 4.2' | 06/01/23 9:10 | 06/19/23 | Soil | Same As Above |
| C23060688-050 | OPSB-03 4.5' | 06/01/23 9:25 | 06/19/23 | Soil | Same As Above |
| C23060688-051 | OPSB-02 5.5' | 06/01/23 11:20 | 06/19/23 | Soil | Same As Above |
| C23060688-052 | OPSB-05 3.75' | 06/01/23 11:55 | 06/19/23 | Soil | Same As Above |
| C23060688-053 | DSSB-05 | 06/01/23 12:30 | 06/19/23 | Soil | Same As Above |

The analyses presented in this report were performed by Energy Laboratories, Inc., 2393 Salt Creek Hwy., Casper, WY 82601, unless otherwise noted. Any exceptions or problems with the analyses are noted in the report package. Any issues encountered during sample receipt are documented in the Work Order Receipt Checklist.

The results as reported relate only to the item(s) submitted for testing. This report shall be used or copied only in its entirety. Energy Laboratories, Inc. is not responsible for the consequences arising from the use of a partial report.

If you have any questions regarding these test results, please contact your Project Manager .

Report Approved By:

**CLIENT:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Work Order:** C23060688

**Report Date:** 08/07/23

# CASE NARRATIVE

ORIGINAL SAMPLE SUBMITTAL(S)
All original sample submittals have been returned with the data package.

SAMPLE TEMPERATURE COMPLIANCE: 4°C (±2°C)
Temperature of samples received may not be considered properly preserved by accepted standards. Samples that are hand delivered immediately after collection shall be considered acceptable if there is evidence that the chilling process has begun.

GROSS ALPHA ANALYSIS
Method 900.0 for gross alpha and gross beta is intended as a drinking water method for low TDS waters. Data provided by this method for non potable waters should be viewed as inconsistent.

RADON IN AIR ANALYSIS
The desired exposure time is 48 hours (2 days). The time delay in returning the canister to the laboratory for processing should be as short as possible to avoid excessive decay. Maximum recommended delay between end of exposure to beginning of counting should not exceed 8 days.

SOIL/SOLID SAMPLES
All samples reported on an as received basis unless otherwise indicated.

ATRAZINE, SIMAZINE AND PCB ANALYSIS
Data for PCBs, Atrazine and Simazine are reported from EPA 525.2. PCB data reported by ELI reflects the results for seven individual Aroclors. When the results for all seven are ND (not detected), the sample meets EPA compliance criteria for PCB monitoring.

SUBCONTRACTING ANALYSIS
Subcontracting of sample analyses to an outside laboratory may be required. If so, ENERGY LABORATORIES will utilize its branch laboratories or qualified contract laboratories for this service. Any such laboratories will be indicated within the Laboratory Analytical Report.

BRANCH LABORATORY LOCATIONS
eli-b - Energy Laboratories, Inc. - Billings, MT
eli-g - Energy Laboratories, Inc. - Gillette, WY
eli-h - Energy Laboratories, Inc. - Helena, MT

ISO 17025 DISCLAIMER:
The results of this Analytical Report relate only to the items submitted for analysis.

ENERGY LABORATORIES, INC. - CASPER,WY certifies that certain method selections contained in this report meet requirements as set forth by the above accrediting authorities. Some results requested by the client may not be covered under these certifications. All analysis data to be submitted for regulatory enforcement should be certified in the sample state of origin. Please verify ELI's certification coverage by visiting www.energylab.com

ELI appreciates the opportunity to provide you with this analytical service. For additional information and services visit our web page www.energylab.com.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-001
**Client Sample ID:** WBSB-02 0-6"

**Report Date:** 08/07/23
**Collection Date:** 05/17/23 08:15
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.4 | pCi/g-dry | | | | E901.1 | 07/25/23 11:24 / haw |
| Radium 224 precision (±) | 0.8 | pCi/g-dry | | | | E901.1 | 07/25/23 11:24 / haw |
| Radium 224 MDC | 1.2 | pCi/g-dry | | | | E901.1 | 07/25/23 11:24 / haw |
| Radium 226 | 1.5 | pCi/g-dry | | | | E901.1 | 07/25/23 11:24 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/25/23 11:24 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/25/23 11:24 / haw |
| Radium 228 | 1.4 | pCi/g-dry | | | | E901.1 | 07/25/23 11:24 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 07/25/23 11:24 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/25/23 11:24 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-002
**Client Sample ID:** WBSB-04 0-6

**Report Date:** 08/07/23
**Collection Date:** 05/17/23 08:35
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.5 | pCi/g-dry | | | | E901.1 | 07/25/23 13:51 / haw |
| Radium 224 precision (±) | 0.8 | pCi/g-dry | | | | E901.1 | 07/25/23 13:51 / haw |
| Radium 224 MDC | 1.2 | pCi/g-dry | | | | E901.1 | 07/25/23 13:51 / haw |
| Radium 226 | 1.5 | pCi/g-dry | | | | E901.1 | 07/25/23 13:51 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/25/23 13:51 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/25/23 13:51 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1 | 07/25/23 13:51 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/25/23 13:51 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/25/23 13:51 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-003
**Client Sample ID:** WBSB-01 0-6'

**Report Date:** 08/07/23
**Collection Date:** 05/17/23 08:55
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.7 | pCi/g-dry | | | | E901.1 | 07/25/23 15:01 / haw |
| Radium 224 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 07/25/23 15:01 / haw |
| Radium 224 MDC | 1.0 | pCi/g-dry | | | | E901.1 | 07/25/23 15:01 / haw |
| Radium 226 | 0.9 | pCi/g-dry | | | | E901.1 | 07/25/23 15:01 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/25/23 15:01 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/25/23 15:01 / haw |
| Radium 228 | 1.4 | pCi/g-dry | | | | E901.1 | 07/25/23 15:01 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 07/25/23 15:01 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/25/23 15:01 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-004
**Client Sample ID:** WBSB-05 0-6"

**Report Date:** 08/07/23
**Collection Date:** 05/17/23 09:20
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.4 | pCi/g-dry | U | | | E901.1 | 07/25/23 16:03 / haw |
| Radium 224 precision (±) | 1.5 | pCi/g-dry | | | | E901.1 | 07/25/23 16:03 / haw |
| Radium 224 MDC | 2.5 | pCi/g-dry | | | | E901.1 | 07/25/23 16:03 / haw |
| Radium 226 | 2.1 | pCi/g-dry | | | | E901.1 | 07/25/23 16:03 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/25/23 16:03 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/25/23 16:03 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1 | 07/25/23 16:03 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/25/23 16:03 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/25/23 16:03 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-005
**Client Sample ID:** WBSB-03 0-6"

**Report Date:** 08/07/23
**Collection Date:** 05/17/23 09:42
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.4 | pCi/g-dry | U | | | E901.1 | 07/25/23 17:08 / haw |
| Radium 224 precision (±) | 1.6 | pCi/g-dry | | | | E901.1 | 07/25/23 17:08 / haw |
| Radium 224 MDC | 2.6 | pCi/g-dry | | | | E901.1 | 07/25/23 17:08 / haw |
| Radium 226 | 3.2 | pCi/g-dry | | | | E901.1 | 07/25/23 17:08 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/25/23 17:08 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/25/23 17:08 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1 | 07/25/23 17:08 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/25/23 17:08 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/25/23 17:08 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-006
**Client Sample ID:** WBSB-07 0-6"

**Report Date:** 08/07/23
**Collection Date:** 05/17/23 10:14
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.04 | pCi/g-dry | U | | | E901.1 | 07/26/23 08:25 / haw |
| Radium 224 precision (±) | 1.8 | pCi/g-dry | | | | E901.1 | 07/26/23 08:25 / haw |
| Radium 224 MDC | 2.9 | pCi/g-dry | | | | E901.1 | 07/26/23 08:25 / haw |
| Radium 226 | 3.7 | pCi/g-dry | | | | E901.1 | 07/26/23 08:25 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/26/23 08:25 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/26/23 08:25 / haw |
| Radium 228 | 1.1 | pCi/g-dry | | | | E901.1 | 07/26/23 08:25 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/26/23 08:25 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 07/26/23 08:25 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-007
**Client Sample ID:** WBSB-08 0-6"

**Report Date:** 08/07/23
**Collection Date:** 05/17/23 10:34
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.06 | pCi/g-dry | U | | | E901.1 | 07/26/23 09:29 / haw |
| Radium 224 precision (±) | 2.5 | pCi/g-dry | | | | E901.1 | 07/26/23 09:29 / haw |
| Radium 224 MDC | 4.2 | pCi/g-dry | | | | E901.1 | 07/26/23 09:29 / haw |
| Radium 226 | 9.7 | pCi/g-dry | | | | E901.1 | 07/26/23 09:29 / haw |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 07/26/23 09:29 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/26/23 09:29 / haw |
| Radium 228 | 1.4 | pCi/g-dry | | | | E901.1 | 07/26/23 09:29 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1 | 07/26/23 09:29 / haw |
| Radium 228 MDC | 0.5 | pCi/g-dry | | | | E901.1 | 07/26/23 09:29 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-008
**Client Sample ID:** WBSB-08 1'-1.5'

**Report Date:** 08/07/23
**Collection Date:** 05/17/23 10:42
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.3 | pCi/g-dry | U | | | E901.1 | 07/26/23 10:45 / haw |
| Radium 224 precision (±) | 1.5 | pCi/g-dry | | | | E901.1 | 07/26/23 10:45 / haw |
| Radium 224 MDC | 2.4 | pCi/g-dry | | | | E901.1 | 07/26/23 10:45 / haw |
| Radium 226 | 0.9 | pCi/g-dry | | | | E901.1 | 07/26/23 10:45 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/26/23 10:45 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/26/23 10:45 / haw |
| Radium 228 | 1.1 | pCi/g-dry | | | | E901.1 | 07/26/23 10:45 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/26/23 10:45 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/26/23 10:45 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-009
**Client Sample ID:** WBSB-06- 0-6"

**Report Date:** 08/07/23
**Collection Date:** 05/17/23 10:54
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.2 | pCi/g-dry | | | | E901.1 | 07/26/23 12:41 / haw |
| Radium 224 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 07/26/23 12:41 / haw |
| Radium 224 MDC | 1.1 | pCi/g-dry | | | | E901.1 | 07/26/23 12:41 / haw |
| Radium 226 | 1.3 | pCi/g-dry | | | | E901.1 | 07/26/23 12:41 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/26/23 12:41 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/26/23 12:41 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1 | 07/26/23 12:41 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/26/23 12:41 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/26/23 12:41 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-010
**Client Sample ID:** DSSB-01

**Report Date:** 08/07/23
**Collection Date:** 05/17/23 12:00
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.02 | pCi/g-dry | U | | | E901.1 | 07/26/23 14:29 / haw |
| Radium 224 precision (±) | 1.4 | pCi/g-dry | | | | E901.1 | 07/26/23 14:29 / haw |
| Radium 224 MDC | 2.4 | pCi/g-dry | | | | E901.1 | 07/26/23 14:29 / haw |
| Radium 226 | 1.1 | pCi/g-dry | | | | E901.1 | 07/26/23 14:29 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/26/23 14:29 / haw |
| Radium 226 MDC | 0.09 | pCi/g-dry | | | | E901.1 | 07/26/23 14:29 / haw |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1 | 07/26/23 14:29 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/26/23 14:29 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/26/23 14:29 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-011
**Client Sample ID:** MCSB-16 1'

**Report Date:** 08/07/23
**Collection Date:** 05/18/23 10:45
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.5 | pCi/g-dry | U | | | E901.1 | 07/26/23 16:45 / haw |
| Radium 224 precision (±) | 1.8 | pCi/g-dry | | | | E901.1 | 07/26/23 16:45 / haw |
| Radium 224 MDC | 2.9 | pCi/g-dry | | | | E901.1 | 07/26/23 16:45 / haw |
| Radium 226 | 4.8 | pCi/g-dry | | | | E901.1 | 07/26/23 16:45 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/26/23 16:45 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/26/23 16:45 / haw |
| Radium 228 | 0.6 | pCi/g-dry | | | | E901.1 | 07/26/23 16:45 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/26/23 16:45 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 07/26/23 16:45 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-012
**Client Sample ID:** MCSB-16 2'

**Report Date:** 08/07/23
**Collection Date:** 05/18/23 11:00
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.3 | pCi/g-dry | U | | | E901.1 | 07/27/23 09:38 / haw |
| Radium 224 precision (±) | 1.5 | pCi/g-dry | | | | E901.1 | 07/27/23 09:38 / haw |
| Radium 224 MDC | 2.5 | pCi/g-dry | | | | E901.1 | 07/27/23 09:38 / haw |
| Radium 226 | 2.4 | pCi/g-dry | | | | E901.1 | 07/27/23 09:38 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/27/23 09:38 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/27/23 09:38 / haw |
| Radium 228 | 1 | pCi/g-dry | | | | E901.1 | 07/27/23 09:38 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/27/23 09:38 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 07/27/23 09:38 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-013
**Client Sample ID:** MCSB-15 1'

**Report Date:** 08/07/23
**Collection Date:** 05/18/23 11:38
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.3 | pCi/g-dry | U | | | E901.1 | 07/27/23 11:22 / haw |
| Radium 224 precision (±) | 1.5 | pCi/g-dry | | | | E901.1 | 07/27/23 11:22 / haw |
| Radium 224 MDC | 2.5 | pCi/g-dry | | | | E901.1 | 07/27/23 11:22 / haw |
| Radium 226 | 1.6 | pCi/g-dry | | | | E901.1 | 07/27/23 11:22 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/27/23 11:22 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/27/23 11:22 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1 | 07/27/23 11:22 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/27/23 11:22 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/27/23 11:22 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-014
**Client Sample ID:** MCSB-17 1'

**Report Date:** 08/07/23
**Collection Date:** 05/18/23 08:45
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.1 | pCi/g-dry | | | | E901.1 | 07/27/23 12:55 / haw |
| Radium 224 precision (±) | 0.6 | pCi/g-dry | | | | E901.1 | 07/27/23 12:55 / haw |
| Radium 224 MDC | 0.9 | pCi/g-dry | | | | E901.1 | 07/27/23 12:55 / haw |
| Radium 226 | 0.7 | pCi/g-dry | | | | E901.1 | 07/27/23 12:55 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/27/23 12:55 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/27/23 12:55 / haw |
| Radium 228 | 1.1 | pCi/g-dry | | | | E901.1 | 07/27/23 12:55 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/27/23 12:55 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/27/23 12:55 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-015
**Client Sample ID:** MCSB-18 1'-1.5'

**Report Date:** 08/07/23
**Collection Date:** 05/18/23 09:48
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.4 | pCi/g-dry | U | | | E901.1 | 07/27/23 13:56 / haw |
| Radium 224 precision (±) | 1.4 | pCi/g-dry | | | | E901.1 | 07/27/23 13:56 / haw |
| Radium 224 MDC | 2.4 | pCi/g-dry | | | | E901.1 | 07/27/23 13:56 / haw |
| Radium 226 | 2.6 | pCi/g-dry | | | | E901.1 | 07/27/23 13:56 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/27/23 13:56 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/27/23 13:56 / haw |
| Radium 228 | 0.9 | pCi/g-dry | | | | E901.1 | 07/27/23 13:56 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/27/23 13:56 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/27/23 13:56 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-016
**Client Sample ID:** DSSB-02

**Report Date:** 08/07/23
**Collection Date:** 05/18/23 13:00
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.4 | pCi/g-dry | | | | E901.1 | 07/27/23 15:17 / haw |
| Radium 224 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 07/27/23 15:17 / haw |
| Radium 224 MDC | 1.2 | pCi/g-dry | | | | E901.1 | 07/27/23 15:17 / haw |
| Radium 226 | 1.3 | pCi/g-dry | | | | E901.1 | 07/27/23 15:17 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/27/23 15:17 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/27/23 15:17 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1 | 07/27/23 15:17 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/27/23 15:17 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/27/23 15:17 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-017
**Client Sample ID:** MCSB-11 4'

**Report Date:** 08/07/23
**Collection Date:** 05/22/23 11:04
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.6 | pCi/g-dry | U | | | E901.1 | 07/27/23 16:21 / haw |
| Radium 224 precision (±) | 2.4 | pCi/g-dry | | | | E901.1 | 07/27/23 16:21 / haw |
| Radium 224 MDC | 4.0 | pCi/g-dry | | | | E901.1 | 07/27/23 16:21 / haw |
| Radium 226 | 11.0 | pCi/g-dry | | | | E901.1 | 07/27/23 16:21 / haw |
| Radium 226 precision (±) | 0.4 | pCi/g-dry | | | | E901.1 | 07/27/23 16:21 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/27/23 16:21 / haw |
| Radium 228 | 1.1 | pCi/g-dry | | | | E901.1 | 07/27/23 16:21 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1 | 07/27/23 16:21 / haw |
| Radium 228 MDC | 0.5 | pCi/g-dry | | | | E901.1 | 07/27/23 16:21 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-018
**Client Sample ID:** MCSB-13 1'

**Report Date:** 08/07/23
**Collection Date:** 05/22/23 08:25
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 2.1 | pCi/g-dry | | | | E901.1 | 07/27/23 17:27 / haw |
| Radium 224 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 07/27/23 17:27 / haw |
| Radium 224 MDC | 1.1 | pCi/g-dry | | | | E901.1 | 07/27/23 17:27 / haw |
| Radium 226 | 1.2 | pCi/g-dry | | | | E901.1 | 07/27/23 17:27 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/27/23 17:27 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/27/23 17:27 / haw |
| Radium 228 | 1.7 | pCi/g-dry | | | | E901.1 | 07/27/23 17:27 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 07/27/23 17:27 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 07/27/23 17:27 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-019
**Client Sample ID:** MCSB-12 1'

**Report Date:** 08/07/23
**Collection Date:** 05/22/23 09:28
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.4 | pCi/g-dry | U | | | E901.1 | 07/28/23 09:11 / haw |
| Radium 224 precision (±) | 1.2 | pCi/g-dry | | | | E901.1 | 07/28/23 09:11 / haw |
| Radium 224 MDC | 2.0 | pCi/g-dry | | | | E901.1 | 07/28/23 09:11 / haw |
| Radium 226 | 3.3 | pCi/g-dry | | | | E901.1 | 07/28/23 09:11 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/28/23 09:11 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/28/23 09:11 / haw |
| Radium 228 | 0.4 | pCi/g-dry | | | | E901.1 | 07/28/23 09:11 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/28/23 09:11 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/28/23 09:11 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-020
**Client Sample ID:** MCSB-11 5'

**Report Date:** 08/07/23
**Collection Date:** 05/22/23 11:12
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.4 | pCi/g-dry | U | | | E901.1 | 07/28/23 10:12 / haw |
| Radium 224 precision (±) | 1.7 | pCi/g-dry | | | | E901.1 | 07/28/23 10:12 / haw |
| Radium 224 MDC | 2.9 | pCi/g-dry | | | | E901.1 | 07/28/23 10:12 / haw |
| Radium 226 | 2.8 | pCi/g-dry | | | | E901.1 | 07/28/23 10:12 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/28/23 10:12 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/28/23 10:12 / haw |
| Radium 228 | 1.4 | pCi/g-dry | | | | E901.1 | 07/28/23 10:12 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 07/28/23 10:12 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 07/28/23 10:12 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-021
**Client Sample ID:** MCSB-14 1'

**Report Date:** 08/07/23
**Collection Date:** 05/23/23 08:53
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.2 | pCi/g-dry | U | | | E901.1 | 07/28/23 13:29 / haw |
| Radium 224 precision (±) | 1.7 | pCi/g-dry | | | | E901.1 | 07/28/23 13:29 / haw |
| Radium 224 MDC | 2.9 | pCi/g-dry | | | | E901.1 | 07/28/23 13:29 / haw |
| Radium 226 | 3.8 | pCi/g-dry | | | | E901.1 | 07/28/23 13:29 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/28/23 13:29 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/28/23 13:29 / haw |
| Radium 228 | 1.1 | pCi/g-dry | | | | E901.1 | 07/28/23 13:29 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 07/28/23 13:29 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 07/28/23 13:29 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-022
**Client Sample ID:** MCSB-08 5'

**Report Date:** 08/07/23
**Collection Date:** 05/23/23 11:10
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -1 | pCi/g-dry | U | | | E901.1 | 07/28/23 14:36 / haw |
| Radium 224 precision (±) | 5.4 | pCi/g-dry | | | | E901.1 | 07/28/23 14:36 / haw |
| Radium 224 MDC | 8.9 | pCi/g-dry | | | | E901.1 | 07/28/23 14:36 / haw |
| Radium 226 | 77.1 | pCi/g-dry | | | | E901.1 | 07/28/23 14:36 / haw |
| Radium 226 precision (±) | 0.9 | pCi/g-dry | | | | E901.1 | 07/28/23 14:36 / haw |
| Radium 226 MDC | 0.4 | pCi/g-dry | | | | E901.1 | 07/28/23 14:36 / haw |
| Radium 228 | -0.3 | pCi/g-dry | U | | | E901.1 | 07/28/23 14:36 / haw |
| Radium 228 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 07/28/23 14:36 / haw |
| Radium 228 MDC | 1.1 | pCi/g-dry | | | | E901.1 | 07/28/23 14:36 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-023
**Client Sample ID:** MCSB-08 6.5'

**Report Date:** 08/07/23
**Collection Date:** 05/23/23 11:25
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.3 | pCi/g-dry | | | | E901.1 | 07/28/23 15:46 / haw |
| Radium 224 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 07/28/23 15:46 / haw |
| Radium 224 MDC | 1.0 | pCi/g-dry | | | | E901.1 | 07/28/23 15:46 / haw |
| Radium 226 | 1.1 | pCi/g-dry | | | | E901.1 | 07/28/23 15:46 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/28/23 15:46 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/28/23 15:46 / haw |
| Radium 228 | 1.4 | pCi/g-dry | | | | E901.1 | 07/28/23 15:46 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/28/23 15:46 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/28/23 15:46 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-024
**Client Sample ID:** MCSB-9 1'

**Report Date:** 08/07/23
**Collection Date:** 05/24/23 08:25
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.3 | pCi/g-dry | U | | | E901.1 | 07/31/23 10:02 / haw |
| Radium 224 precision (±) | 1.8 | pCi/g-dry | | | | E901.1 | 07/31/23 10:02 / haw |
| Radium 224 MDC | 3.0 | pCi/g-dry | | | | E901.1 | 07/31/23 10:02 / haw |
| Radium 226 | 7.9 | pCi/g-dry | | | | E901.1 | 07/31/23 10:02 / haw |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 07/31/23 10:02 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/31/23 10:02 / haw |
| Radium 228 | 0.3 | pCi/g-dry | U | | | E901.1 | 07/31/23 10:02 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/31/23 10:02 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1 | 07/31/23 10:02 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-025
**Client Sample ID:** MCSB-9 2'

**Report Date:** 08/07/23
**Collection Date:** 05/24/23 08:40
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.3 | pCi/g-dry | U | | | E901.1 | 07/31/23 11:08 / haw |
| Radium 224 precision (±) | 1.1 | pCi/g-dry | | | | E901.1 | 07/31/23 11:08 / haw |
| Radium 224 MDC | 1.8 | pCi/g-dry | | | | E901.1 | 07/31/23 11:08 / haw |
| Radium 226 | 0.6 | pCi/g-dry | | | | E901.1 | 07/31/23 11:08 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/31/23 11:08 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/31/23 11:08 / haw |
| Radium 228 | 0.8 | pCi/g-dry | | | | E901.1 | 07/31/23 11:08 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/31/23 11:08 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/31/23 11:08 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-026
**Client Sample ID:** MCSB-10 1'

**Report Date:** 08/07/23
**Collection Date:** 05/24/23 09:15
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1 | pCi/g-dry | | | | E901.1 | 07/31/23 12:18 / haw |
| Radium 224 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 07/31/23 12:18 / haw |
| Radium 224 MDC | 0.8 | pCi/g-dry | | | | E901.1 | 07/31/23 12:18 / haw |
| Radium 226 | 0.8 | pCi/g-dry | | | | E901.1 | 07/31/23 12:18 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/31/23 12:18 / haw |
| Radium 226 MDC | 0.09 | pCi/g-dry | | | | E901.1 | 07/31/23 12:18 / haw |
| Radium 228 | 0.9 | pCi/g-dry | | | | E901.1 | 07/31/23 12:18 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/31/23 12:18 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/31/23 12:18 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-027
**Client Sample ID:** MCSB-5 4'

**Report Date:** 08/07/23
**Collection Date:** 05/24/23 10:40
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.4 | pCi/g-dry | | | | E901.1 | 07/31/23 13:22 / haw |
| Radium 224 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 07/31/23 13:22 / haw |
| Radium 224 MDC | 1.2 | pCi/g-dry | | | | E901.1 | 07/31/23 13:22 / haw |
| Radium 226 | 1.5 | pCi/g-dry | | | | E901.1 | 07/31/23 13:22 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/31/23 13:22 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/31/23 13:22 / haw |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1 | 07/31/23 13:22 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 07/31/23 13:22 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 07/31/23 13:22 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-028
**Client Sample ID:** MCSB-5 6'

**Report Date:** 08/07/23
**Collection Date:** 05/24/23 11:00
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.6 | pCi/g-dry | U | | | E901.1 | 07/31/23 14:40 / haw |
| Radium 224 precision (±) | 2.4 | pCi/g-dry | | | | E901.1 | 07/31/23 14:40 / haw |
| Radium 224 MDC | 3.9 | pCi/g-dry | | | | E901.1 | 07/31/23 14:40 / haw |
| Radium 226 | 16.1 | pCi/g-dry | | | | E901.1 | 07/31/23 14:40 / haw |
| Radium 226 precision (±) | 0.4 | pCi/g-dry | | | | E901.1 | 07/31/23 14:40 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 07/31/23 14:40 / haw |
| Radium 228 | 0.3 | pCi/g-dry | U | | | E901.1 | 07/31/23 14:40 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 07/31/23 14:40 / haw |
| Radium 228 MDC | 0.5 | pCi/g-dry | | | | E901.1 | 07/31/23 14:40 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-029
**Client Sample ID:** MCSB-5 7.5'

**Report Date:** 08/07/23
**Collection Date:** 05/24/23 11:10
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.3 | pCi/g-dry | | | | E901.1 | 07/31/23 15:55 / haw |
| Radium 224 precision (±) | 0.6 | pCi/g-dry | | | | E901.1 | 07/31/23 15:55 / haw |
| Radium 224 MDC | 1 | pCi/g-dry | | | | E901.1 | 07/31/23 15:55 / haw |
| Radium 226 | 1.0 | pCi/g-dry | | | | E901.1 | 07/31/23 15:55 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 07/31/23 15:55 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/31/23 15:55 / haw |
| Radium 228 | 1.1 | pCi/g-dry | | | | E901.1 | 07/31/23 15:55 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 07/31/23 15:55 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 07/31/23 15:55 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-030
**Client Sample ID:** MCSB-7 3'

**Report Date:** 08/07/23
**Collection Date:** 05/24/23 12:46
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.4 | pCi/g-dry | U | | | E901.1 | 07/31/23 17:08 / haw |
| Radium 224 precision (±) | 1.6 | pCi/g-dry | | | | E901.1 | 07/31/23 17:08 / haw |
| Radium 224 MDC | 2.6 | pCi/g-dry | | | | E901.1 | 07/31/23 17:08 / haw |
| Radium 226 | 6.3 | pCi/g-dry | | | | E901.1 | 07/31/23 17:08 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/31/23 17:08 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 07/31/23 17:08 / haw |
| Radium 228 | 0.2 | pCi/g-dry | U | | | E901.1 | 07/31/23 17:08 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 07/31/23 17:08 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1 | 07/31/23 17:08 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-031
**Client Sample ID:** MCSB-7 4.5'

**Report Date:** 08/07/23
**Collection Date:** 05/24/23 13:00
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 2.1 | pCi/g-dry | | | | E901.1 | 08/01/23 08:48 / haw |
| Radium 224 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 08/01/23 08:48 / haw |
| Radium 224 MDC | 1.1 | pCi/g-dry | | | | E901.1 | 08/01/23 08:48 / haw |
| Radium 226 | 1.2 | pCi/g-dry | | | | E901.1 | 08/01/23 08:48 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/01/23 08:48 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/01/23 08:48 / haw |
| Radium 228 | 1.6 | pCi/g-dry | | | | E901.1 | 08/01/23 08:48 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 08:48 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 08:48 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-032
**Client Sample ID:** DSSB-03

**Report Date:** 08/07/23
**Collection Date:** 05/24/23 13:30
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.4 | pCi/g-dry | U | | | E901.1 | 08/01/23 09:52 / haw |
| Radium 224 precision (±) | 1.6 | pCi/g-dry | | | | E901.1 | 08/01/23 09:52 / haw |
| Radium 224 MDC | 2.6 | pCi/g-dry | | | | E901.1 | 08/01/23 09:52 / haw |
| Radium 226 | 6.2 | pCi/g-dry | | | | E901.1 | 08/01/23 09:52 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 09:52 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/01/23 09:52 / haw |
| Radium 228 | 0.3 | pCi/g-dry | U | | | E901.1 | 08/01/23 09:52 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 09:52 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 08/01/23 09:52 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-033
**Client Sample ID:** MCSB-06 6'

**Report Date:** 08/07/23
**Collection Date:** 05/30/23 09:15
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.4 | pCi/g-dry | U | | | E901.1 | 08/01/23 11:07 / haw |
| Radium 224 precision (±) | 1.6 | pCi/g-dry | | | | E901.1 | 08/01/23 11:07 / haw |
| Radium 224 MDC | 2.6 | pCi/g-dry | | | | E901.1 | 08/01/23 11:07 / haw |
| Radium 226 | 1.9 | pCi/g-dry | | | | E901.1 | 08/01/23 11:07 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 11:07 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/01/23 11:07 / haw |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1 | 08/01/23 11:07 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 11:07 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 11:07 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-034
**Client Sample ID:** MCSB-04 1'

**Report Date:** 08/07/23
**Collection Date:** 05/30/23 09:35
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.3 | pCi/g-dry | U | | | E901.1 | 08/01/23 13:40 / haw |
| Radium 224 precision (±) | 0.9 | pCi/g-dry | | | | E901.1 | 08/01/23 13:40 / haw |
| Radium 224 MDC | 1.5 | pCi/g-dry | | | | E901.1 | 08/01/23 13:40 / haw |
| Radium 226 | 1.4 | pCi/g-dry | | | | E901.1 | 08/01/23 13:40 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/01/23 13:40 / haw |
| Radium 226 MDC | 0.08 | pCi/g-dry | | | | E901.1 | 08/01/23 13:40 / haw |
| Radium 228 | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 13:40 / haw |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/01/23 13:40 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 13:40 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-035
**Client Sample ID:** MCSB-04 2'

**Report Date:** 08/07/23
**Collection Date:** 05/30/23 09:45
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.3 | pCi/g-dry | U | | | E901.1 | 08/01/23 14:42 / haw |
| Radium 224 precision (±) | 1.4 | pCi/g-dry | | | | E901.1 | 08/01/23 14:42 / haw |
| Radium 224 MDC | 2.3 | pCi/g-dry | | | | E901.1 | 08/01/23 14:42 / haw |
| Radium 226 | 3.4 | pCi/g-dry | | | | E901.1 | 08/01/23 14:42 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 14:42 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/01/23 14:42 / haw |
| Radium 228 | 0.4 | pCi/g-dry | | | | E901.1 | 08/01/23 14:42 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 14:42 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 08/01/23 14:42 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-036
**Client Sample ID:** MCSB-02 3'

**Report Date:** 08/07/23
**Collection Date:** 05/30/23 10:50
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.3 | pCi/g-dry | U | | | E901.1 | 08/01/23 15:59 / haw |
| Radium 224 precision (±) | 1.0 | pCi/g-dry | | | | E901.1 | 08/01/23 15:59 / haw |
| Radium 224 MDC | 1.7 | pCi/g-dry | | | | E901.1 | 08/01/23 15:59 / haw |
| Radium 226 | 0.8 | pCi/g-dry | | | | E901.1 | 08/01/23 15:59 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/01/23 15:59 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/01/23 15:59 / haw |
| Radium 228 | 0.7 | pCi/g-dry | | | | E901.1 | 08/01/23 15:59 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 15:59 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 15:59 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-037
**Client Sample ID:** MCSB-02 4'

**Report Date:** 08/07/23
**Collection Date:** 05/30/23 11:00
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.4 | pCi/g-dry | U | | | E901.1 | 08/01/23 17:13 / haw |
| Radium 224 precision (±) | 2.1 | pCi/g-dry | | | | E901.1 | 08/01/23 17:13 / haw |
| Radium 224 MDC | 3.5 | pCi/g-dry | | | | E901.1 | 08/01/23 17:13 / haw |
| Radium 226 | 12.6 | pCi/g-dry | | | | E901.1 | 08/01/23 17:13 / haw |
| Radium 226 precision (±) | 0.4 | pCi/g-dry | | | | E901.1 | 08/01/23 17:13 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/01/23 17:13 / haw |
| Radium 228 | 0.3 | pCi/g-dry | U | | | E901.1 | 08/01/23 17:13 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 08/01/23 17:13 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1 | 08/01/23 17:13 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-038
**Client Sample ID:** MCSB-02 5.2'

**Report Date:** 08/07/23
**Collection Date:** 05/30/23 11:15
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 2.0 | pCi/g-dry | | | | E901.1 | 08/02/23 08:25 / haw |
| Radium 224 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 08/02/23 08:25 / haw |
| Radium 224 MDC | 1.1 | pCi/g-dry | | | | E901.1 | 08/02/23 08:25 / haw |
| Radium 226 | 1.4 | pCi/g-dry | | | | E901.1 | 08/02/23 08:25 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/02/23 08:25 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/02/23 08:25 / haw |
| Radium 228 | 1.7 | pCi/g-dry | | | | E901.1 | 08/02/23 08:25 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 08/02/23 08:25 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/02/23 08:25 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-039
**Client Sample ID:** MCSB-01 2'

**Report Date:** 08/07/23
**Collection Date:** 05/30/23 12:50
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.5 | pCi/g-dry | U | | | E901.1 | 08/02/23 12:03 / sec |
| Radium 224 precision (±) | 1.6 | pCi/g-dry | | | | E901.1 | 08/02/23 12:03 / sec |
| Radium 224 MDC | 2.6 | pCi/g-dry | | | | E901.1 | 08/02/23 12:03 / sec |
| Radium 226 | 5.9 | pCi/g-dry | | | | E901.1 | 08/02/23 12:03 / sec |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/02/23 12:03 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/02/23 12:03 / sec |
| Radium 228 | 0.5 | pCi/g-dry | | | | E901.1 | 08/02/23 12:03 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/02/23 12:03 / sec |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 08/02/23 12:03 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-040
**Client Sample ID:** MCSB-01 3'

**Report Date:** 08/07/23
**Collection Date:** 05/30/23 13:00
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.4 | pCi/g-dry | | | | E901.1 | 08/02/23 13:56 / sec |
| Radium 224 precision (±) | 0.6 | pCi/g-dry | | | | E901.1 | 08/02/23 13:56 / sec |
| Radium 224 MDC | 1 | pCi/g-dry | | | | E901.1 | 08/02/23 13:56 / sec |
| Radium 226 | 0.8 | pCi/g-dry | | | | E901.1 | 08/02/23 13:56 / sec |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/02/23 13:56 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/02/23 13:56 / sec |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1 | 08/02/23 13:56 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/02/23 13:56 / sec |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/02/23 13:56 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-041
**Client Sample ID:** MCSB-03 1'

**Report Date:** 08/07/23
**Collection Date:** 05/30/23 13:40
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.4 | pCi/g-dry | U | | | E901.1 | 08/02/23 15:03 / sec |
| Radium 224 precision (±) | 1.6 | pCi/g-dry | | | | E901.1 | 08/02/23 15:03 / sec |
| Radium 224 MDC | 2.7 | pCi/g-dry | | | | E901.1 | 08/02/23 15:03 / sec |
| Radium 226 | 5.9 | pCi/g-dry | | | | E901.1 | 08/02/23 15:03 / sec |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/02/23 15:03 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/02/23 15:03 / sec |
| Radium 228 | 0.4 | pCi/g-dry | | | | E901.1 | 08/02/23 15:03 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/02/23 15:03 / sec |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 08/02/23 15:03 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-042
**Client Sample ID:** MCSB-03 2'

**Report Date:** 08/07/23
**Collection Date:** 05/30/23 13:50
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.2 | pCi/g-dry | | | | E901.1 | 08/02/23 16:13 / sec |
| Radium 224 precision (±) | 0.6 | pCi/g-dry | | | | E901.1 | 08/02/23 16:13 / sec |
| Radium 224 MDC | 1 | pCi/g-dry | | | | E901.1 | 08/02/23 16:13 / sec |
| Radium 226 | 0.8 | pCi/g-dry | | | | E901.1 | 08/02/23 16:13 / sec |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/02/23 16:13 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/02/23 16:13 / sec |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1 | 08/02/23 16:13 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/02/23 16:13 / sec |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/02/23 16:13 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-043
**Client Sample ID:** DSSB-04

**Report Date:** 08/07/23
**Collection Date:** 05/30/23 14:15
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.2 | pCi/g-dry | U | | | E901.1 | 08/02/23 17:18 / sec |
| Radium 224 precision (±) | 1.7 | pCi/g-dry | | | | E901.1 | 08/02/23 17:18 / sec |
| Radium 224 MDC | 2.8 | pCi/g-dry | | | | E901.1 | 08/02/23 17:18 / sec |
| Radium 226 | 5.8 | pCi/g-dry | | | | E901.1 | 08/02/23 17:18 / sec |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/02/23 17:18 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/02/23 17:18 / sec |
| Radium 228 | 0.6 | pCi/g-dry | | | | E901.1 | 08/02/23 17:18 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/02/23 17:18 / sec |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/02/23 17:18 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-044
**Client Sample ID:** WBSB-09 0-6"

**Report Date:** 08/07/23
**Collection Date:** 05/31/23 08:25
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.4 | pCi/g-dry | | | | E901.1 | 08/03/23 08:51 / sec |
| Radium 224 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 08/03/23 08:51 / sec |
| Radium 224 MDC | 1.2 | pCi/g-dry | | | | E901.1 | 08/03/23 08:51 / sec |
| Radium 226 | 1.2 | pCi/g-dry | | | | E901.1 | 08/03/23 08:51 / sec |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/03/23 08:51 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/03/23 08:51 / sec |
| Radium 228 | 1.4 | pCi/g-dry | | | | E901.1 | 08/03/23 08:51 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 08:51 / sec |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 08/03/23 08:51 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-045
**Client Sample ID:** WBSB-12 0-1"

**Report Date:** 08/07/23
**Collection Date:** 05/31/23 08:50
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.4 | pCi/g-dry | | | | E901.1 | 08/03/23 09:57 / sec |
| Radium 224 precision (±) | 0.8 | pCi/g-dry | | | | E901.1 | 08/03/23 09:57 / sec |
| Radium 224 MDC | 1.3 | pCi/g-dry | | | | E901.1 | 08/03/23 09:57 / sec |
| Radium 226 | 2.0 | pCi/g-dry | | | | E901.1 | 08/03/23 09:57 / sec |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 09:57 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/03/23 09:57 / sec |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1 | 08/03/23 09:57 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 09:57 / sec |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 09:57 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-046
**Client Sample ID:** WBSB-12 2-6"

**Report Date:** 08/07/23
**Collection Date:** 05/31/23 09:00
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.7 | pCi/g-dry | | | | E901.1 | 08/03/23 11:04 / sec |
| Radium 224 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 08/03/23 11:04 / sec |
| Radium 224 MDC | 1.0 | pCi/g-dry | | | | E901.1 | 08/03/23 11:04 / sec |
| Radium 226 | 1 | pCi/g-dry | | | | E901.1 | 08/03/23 11:04 / sec |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/03/23 11:04 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/03/23 11:04 / sec |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1 | 08/03/23 11:04 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 11:04 / sec |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 08/03/23 11:04 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-047
**Client Sample ID:** WBSB-10 0-6"

**Report Date:** 08/07/23
**Collection Date:** 05/31/23 09:10
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.4 | pCi/g-dry | U | | | E901.1 | 08/03/23 12:10 / sec |
| Radium 224 precision (±) | 1.6 | pCi/g-dry | | | | E901.1 | 08/03/23 12:10 / sec |
| Radium 224 MDC | 2.6 | pCi/g-dry | | | | E901.1 | 08/03/23 12:10 / sec |
| Radium 226 | 3.5 | pCi/g-dry | | | | E901.1 | 08/03/23 12:10 / sec |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 12:10 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/03/23 12:10 / sec |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1 | 08/03/23 12:10 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 12:10 / sec |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 12:10 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-048
**Client Sample ID:** WBSB-11 0-6"

**Report Date:** 08/07/23
**Collection Date:** 05/31/23 09:35
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.4 | pCi/g-dry | | | | E901.1 | 08/03/23 13:24 / sec |
| Radium 224 precision (±) | 0.9 | pCi/g-dry | | | | E901.1 | 08/03/23 13:24 / sec |
| Radium 224 MDC | 1.4 | pCi/g-dry | | | | E901.1 | 08/03/23 13:24 / sec |
| Radium 226 | 2.7 | pCi/g-dry | | | | E901.1 | 08/03/23 13:24 / sec |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 13:24 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/03/23 13:24 / sec |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1 | 08/03/23 13:24 / sec |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 08/03/23 13:24 / sec |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 08/03/23 13:24 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-049
**Client Sample ID:** OPSB-03 4.2'

**Report Date:** 08/07/23
**Collection Date:** 06/01/23 09:10
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.3 | pCi/g-dry | U | | | E901.1 | 08/03/23 15:37 / sec |
| Radium 224 precision (±) | 1.8 | pCi/g-dry | | | | E901.1 | 08/03/23 15:37 / sec |
| Radium 224 MDC | 3.0 | pCi/g-dry | | | | E901.1 | 08/03/23 15:37 / sec |
| Radium 226 | 4.4 | pCi/g-dry | | | | E901.1 | 08/03/23 15:37 / sec |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 15:37 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/03/23 15:37 / sec |
| Radium 228 | 0.9 | pCi/g-dry | | | | E901.1 | 08/03/23 15:37 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 15:37 / sec |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 08/03/23 15:37 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-050
**Client Sample ID:** OPSB-03 4.5'

**Report Date:** 08/07/23
**Collection Date:** 06/01/23 09:25
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.6 | pCi/g-dry | | | | E901.1 | 08/03/23 16:44 / sec |
| Radium 224 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 08/03/23 16:44 / sec |
| Radium 224 MDC | 1.1 | pCi/g-dry | | | | E901.1 | 08/03/23 16:44 / sec |
| Radium 226 | 0.8 | pCi/g-dry | | | | E901.1 | 08/03/23 16:44 / sec |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/03/23 16:44 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/03/23 16:44 / sec |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1 | 08/03/23 16:44 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 16:44 / sec |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 16:44 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-051
**Client Sample ID:** OPSB-02 5.5'

**Report Date:** 08/07/23
**Collection Date:** 06/01/23 11:20
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.1 | pCi/g-dry | U | | | E901.1 | 08/03/23 17:46 / sec |
| Radium 224 precision (±) | 1.4 | pCi/g-dry | | | | E901.1 | 08/03/23 17:46 / sec |
| Radium 224 MDC | 2.4 | pCi/g-dry | | | | E901.1 | 08/03/23 17:46 / sec |
| Radium 226 | 0.9 | pCi/g-dry | | | | E901.1 | 08/03/23 17:46 / sec |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/03/23 17:46 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/03/23 17:46 / sec |
| Radium 228 | 1.1 | pCi/g-dry | | | | E901.1 | 08/03/23 17:46 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 17:46 / sec |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 08/03/23 17:46 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-052
**Client Sample ID:** OPSB-05 3.75'

**Report Date:** 08/07/23
**Collection Date:** 06/01/23 11:55
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.7 | pCi/g-dry | | | | E901.1 | 08/04/23 08:54 / sec |
| Radium 224 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 08/04/23 08:54 / sec |
| Radium 224 MDC | 1.1 | pCi/g-dry | | | | E901.1 | 08/04/23 08:54 / sec |
| Radium 226 | 0.9 | pCi/g-dry | | | | E901.1 | 08/04/23 08:54 / sec |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/04/23 08:54 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/04/23 08:54 / sec |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1 | 08/04/23 08:54 / sec |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 08/04/23 08:54 / sec |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 08/04/23 08:54 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM Subsurface soil investigation
**Lab ID:** C23060688-053
**Client Sample ID:** DSSB-05

**Report Date:** 08/07/23
**Collection Date:** 06/01/23 12:30
**DateReceived:** 06/19/23
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.2 | pCi/g-dry | | | | E901.1 | 08/04/23 10:57 / sec |
| Radium 224 precision (±) | 0.6 | pCi/g-dry | | | | E901.1 | 08/04/23 10:57 / sec |
| Radium 224 MDC | 0.9 | pCi/g-dry | | | | E901.1 | 08/04/23 10:57 / sec |
| Radium 226 | 0.8 | pCi/g-dry | | | | E901.1 | 08/04/23 10:57 / sec |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 08/04/23 10:57 / sec |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 08/04/23 10:57 / sec |
| Radium 228 | 1.1 | pCi/g-dry | | | | E901.1 | 08/04/23 10:57 / sec |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 08/04/23 10:57 / sec |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 08/04/23 10:57 / sec |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation **Work Order:** C23060688 **Report Date:** 08/04/23

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E901.1** | | | | | | | | | | Batch: R296981 |
| **Lab ID: MB-296981** | 9 | Method Blank | | | | Run: GAM-HPGE 2_230725A | | | | 07/25/23 09:16 |
| Radium 224 | | 0.2 | pCi/g-dry | | | | | | | U |
| Radium 224 precision (±) | | 0.4 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 0.7 | pCi/g-dry | | | | | | | |
| Radium 226 | | 0.2 | pCi/g-dry | | | | | | | |
| Radium 226 precision (±) | | 0.06 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.06 | pCi/g-dry | | | | | | | |
| Radium 228 | | 0.09 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.09 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.1 | pCi/g-dry | | | | | | | |
| **Lab ID: LCS-296981** | 6 | Laboratory Control Sample | | | | Run: GAM-HPGE 2_230725A | | | | 07/25/23 10:20 |
| Cobalt 60 | | 8.1 | pCi/g-dry | | 90 | 70 | 130 | | | |
| Cobalt 60 precision (±) | | 0.55 | pCi/g-dry | | | | | | | |
| Cobalt 60 MDC | | 0.83 | pCi/g-dry | | | | | | | |
| Radium 226 | | 50 | pCi/g-dry | | 92 | 70 | 130 | | | |
| Radium 226 precision (±) | | 2.3 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 2.6 | pCi/g-dry | | | | | | | |
| **Lab ID: C23060688-001ADUP** | 9 | Sample Duplicate | | | | Run: GAM-HPGE 2_230725A | | | | 07/25/23 12:49 |
| Radium 224 | | 1.5 | pCi/g-dry | | | | | 12 | 30 | |
| Radium 224 precision (±) | | 0.76 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 1.2 | pCi/g-dry | | | | | | | |
| Radium 226 | | 1.6 | pCi/g-dry | | | | | 6.1 | 30 | |
| Radium 226 precision (±) | | 0.16 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.14 | pCi/g-dry | | | | | | | |
| Radium 228 | | 1.4 | pCi/g-dry | | | | | 1.8 | 30 | |
| Radium 228 precision (±) | | 0.25 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.24 | pCi/g-dry | | | | | | | |
| - The RER result for Ra224 is 0.16, Ra226 is 0.44 and Ra228 is 0.07. | | | | | | | | | | |
| **Lab ID: C23060688-011ADUP** | 9 | Sample Duplicate | | | | Run: GAM-HPGE 2_230725A | | | | 07/27/23 08:36 |
| Radium 224 | | -0.48 | pCi/g-dry | | | | | 5.3 | 30 | U |
| Radium 224 precision (±) | | 1.7 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 2.8 | pCi/g-dry | | | | | | | |
| Radium 226 | | 4.9 | pCi/g-dry | | | | | 1.9 | 30 | |
| Radium 226 precision (±) | | 0.24 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.14 | pCi/g-dry | | | | | | | |
| Radium 228 | | 0.86 | pCi/g-dry | | | | | 44 | 30 | R |
| Radium 228 precision (±) | | 0.26 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.31 | pCi/g-dry | | | | | | | |
| - Duplicate RPD for Ra228 is outside of the acceptance range for this analysis. However, the RER is less than or equal to the limit of 3, the RER result is 0.86. -The RER result for Ra224 is 0.01 and Ra226 is 0.28. | | | | | | | | | | |

**Qualifiers:**

RL - Analyte Reporting Limit

ND - Not detected at the Reporting Limit (RL)

R - Relative Percent Difference (RPD) exceeds advisory limit

U - Not detected at Minimum Detectable Concentration (MDC)

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation **Work Order:** C23060688 **Report Date:** 08/04/23

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E901.1** | | | | | | | | | | Batch: R297133 |
| **Lab ID: MB-297133** | 9 | Method Blank | | | | Run: GAM-HPGE 2_230728A | | | | 07/28/23 11:18 |
| Radium 224 | | 0.2 | pCi/g-dry | | | | | | | U |
| Radium 224 precision (±) | | 0.4 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 0.7 | pCi/g-dry | | | | | | | |
| Radium 226 | | 0.2 | pCi/g-dry | | | | | | | |
| Radium 226 precision (±) | | 0.05 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.05 | pCi/g-dry | | | | | | | |
| Radium 228 | | 0.1 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.1 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.1 | pCi/g-dry | | | | | | | |
| **Lab ID: LCS-297133** | 6 | Laboratory Control Sample | | | | Run: GAM-HPGE 2_230728A | | | | 07/28/23 12:25 |
| Cobalt 60 | | 7.7 | pCi/g-dry | | 85 | 70 | 130 | | | |
| Cobalt 60 precision (±) | | 0.53 | pCi/g-dry | | | | | | | |
| Cobalt 60 MDC | | 0.82 | pCi/g-dry | | | | | | | |
| Radium 226 | | 50 | pCi/g-dry | | 92 | 70 | 130 | | | |
| Radium 226 precision (±) | | 2.3 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 2.6 | pCi/g-dry | | | | | | | |
| **Lab ID: C23060688-023ADUP** | 9 | Sample Duplicate | | | | Run: GAM-HPGE 2_230728A | | | | 07/28/23 17:06 |
| Radium 224 | | 1.3 | pCi/g-dry | | | | | 1.1 | 30 | |
| Radium 224 precision (±) | | 0.67 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 1.1 | pCi/g-dry | | | | | | | |
| Radium 226 | | 1.1 | pCi/g-dry | | | | | 5.5 | 30 | |
| Radium 226 precision (±) | | 0.13 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.11 | pCi/g-dry | | | | | | | |
| Radium 228 | | 1.4 | pCi/g-dry | | | | | 1.3 | 30 | |
| Radium 228 precision (±) | | 0.23 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.21 | pCi/g-dry | | | | | | | |
| - The RER result for Ra224 is 0.02, Ra226 is 0.32, Ra228 is 0.06. | | | | | | | | | | |
| **Lab ID: C23060688-033ADUP** | 9 | Sample Duplicate | | | | Run: GAM-HPGE 2_230728A | | | | 08/01/23 12:13 |
| Radium 224 | | 0.33 | pCi/g-dry | | | | | 3200 | 30 | UR |
| Radium 224 precision (±) | | 1.5 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 2.5 | pCi/g-dry | | | | | | | |
| Radium 226 | | 1.9 | pCi/g-dry | | | | | 0.5 | 30 | |
| Radium 226 precision (±) | | 0.16 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.11 | pCi/g-dry | | | | | | | |
| Radium 228 | | 1.2 | pCi/g-dry | | | | | 0.7 | 30 | |
| Radium 228 precision (±) | | 0.23 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.22 | pCi/g-dry | | | | | | | |
| - Duplicate RPD for Ra224 is outside of the acceptance range for this analysis. However, the RER is less than or equal to the limit of 3, the RER result for Ra224 is 0.33. The RER result for Ra226 is 0.04 and Ra228 is 0.03 | | | | | | | | | | |

**Qualifiers:**

RL - Analyte Reporting Limit

ND - Not detected at the Reporting Limit (RL)

R - Relative Percent Difference (RPD) exceeds advisory limit

U - Not detected at Minimum Detectable Concentration (MDC)

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation **Work Order:** C23060688 **Report Date:** 08/04/23

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E901.1** | | | | | | | | | | Batch: R297281 |
| **Lab ID: MB-297281** | 9 | Method Blank | | | | Run: GAM-HPGE 2_230802A | | | | 08/02/23 09:38 |
| Radium 224 | | 0.02 | pCi/g-dry | | | | | | | U |
| Radium 224 precision (±) | | 0.4 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 0.7 | pCi/g-dry | | | | | | | |
| Radium 226 | | 0.2 | pCi/g-dry | | | | | | | |
| Radium 226 precision (±) | | 0.05 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.05 | pCi/g-dry | | | | | | | |
| Radium 228 | | 0.06 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.09 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.1 | pCi/g-dry | | | | | | | |
| **Lab ID: C23060688-048ADUP** | 9 | Sample Duplicate | | | | Run: GAM-HPGE 2_230802A | | | | 08/03/23 14:34 |
| Radium 224 | | -0.41 | pCi/g-dry | | | | | 360 | 30 | UR |
| Radium 224 precision (±) | | 1.5 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 2.5 | pCi/g-dry | | | | | | | |
| Radium 226 | | 2.7 | pCi/g-dry | | | | | 0.5 | 30 | |
| Radium 226 precision (±) | | 0.18 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.13 | pCi/g-dry | | | | | | | |
| Radium 228 | | 1.4 | pCi/g-dry | | | | | 11 | 30 | |
| Radium 228 precision (±) | | 0.28 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.29 | pCi/g-dry | | | | | | | |
| - Duplicate RPD for Ra224 is outside of the acceptance range for this analysis. However, the RER is less than or equal to the limit of 3, the RER result is 1.05. The RER result for Ra226 is 0.05 and Ra228 is 0.41. | | | | | | | | | | |
| **Lab ID: C23060688-052ADUP** | 9 | Sample Duplicate | | | | Run: GAM-HPGE 2_230802A | | | | 08/04/23 09:55 |
| Radium 224 | | 0.041 | pCi/g-dry | | | | | 190 | 30 | UR |
| Radium 224 precision (±) | | 1.7 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 2.8 | pCi/g-dry | | | | | | | |
| Radium 226 | | 1.1 | pCi/g-dry | | | | | 17 | 30 | |
| Radium 226 precision (±) | | 0.14 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.11 | pCi/g-dry | | | | | | | |
| Radium 228 | | 1.3 | pCi/g-dry | | | | | 16 | 30 | |
| Radium 228 precision (±) | | 0.24 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.23 | pCi/g-dry | | | | | | | |
| - Duplicate RPD for Ra224 is outside of the acceptance range for this analysis. However, the RER is less than or equal to the limit of 3, the RER result is 0.90. The RER result for Ra226 is 0.92 and Ra228 is 0.61. | | | | | | | | | | |
| **Lab ID: LCS-297281** | 6 | Laboratory Control Sample | | | | Run: GAM-HPGE 2_230802A | | | | 08/04/23 14:26 |
| Cobalt 60 | | 8.0 | pCi/g-dry | | 88 | 70 | 130 | | | |
| Cobalt 60 precision (±) | | 0.57 | pCi/g-dry | | | | | | | |
| Cobalt 60 MDC | | 0.72 | pCi/g-dry | | | | | | | |
| Radium 226 | | 48 | pCi/g-dry | | 89 | 70 | 130 | | | |
| Radium 226 precision (±) | | 2.1 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 2.4 | pCi/g-dry | | | | | | | |

**Qualifiers:**

RL - Analyte Reporting Limit

ND - Not detected at the Reporting Limit (RL)

R - Relative Percent Difference (RPD) exceeds advisory limit

U - Not detected at Minimum Detectable Concentration (MDC)

# Work Order Receipt Checklist

## Rio Grande Resources Corporation C23060688

| | | | |
|---|---|---|---|
| Login completed by: | Dakota R. Januska | Date Received: | 6/19/2023 |
| Reviewed by: | mstephens | Received by: | slr |
| Reviewed Date: | 6/21/2023 | Carrier name: | UPS |

| | | | |
|---|---|---|---|
| Shipping container/cooler in good condition? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on all shipping container(s)/cooler(s)? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on all sample bottles? | Yes ☐ | No ☐ | Not Present ☑ |
| Chain of custody present? | Yes ☑ | No ☐ | |
| Chain of custody signed when relinquished and received? | Yes ☑ | No ☐ | |
| Chain of custody agrees with sample labels? | Yes ☑ | No ☐ | |
| Samples in proper container/bottle? | Yes ☑ | No ☐ | |
| Sample containers intact? | Yes ☑ | No ☐ | |
| Sufficient sample volume for indicated test? | Yes ☑ | No ☐ | |
| All samples received within holding time? (Exclude analyses that are considered field parameters such as pH, DO, Res Cl, Sulfite, Ferrous Iron, etc.) | Yes ☑ | No ☐ | |
| Temp Blank received in all shipping container(s)/cooler(s)? | Yes ☑ | No ☐ | Not Applicable ☐ |
| Container/Temp Blank temperature: | 19.0°C No Ice | | |
| Containers requiring zero headspace have no headspace or bubble that is <6mm (1/4"). | Yes ☐ | No ☐ | No VOA vials submitted ☑ |
| Water - pH acceptable upon receipt? | Yes ☐ | No ☐ | Not Applicable ☑ |

### Standard Reporting Procedures:

Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH, Dissolved Oxygen and Residual Chlorine, are qualified as being analyzed outside of recommended holding time.

Solid/soil samples are reported on a wet weight basis (as received) unless specifically indicated. If moisture corrected, data units are typically noted as –dry. For agricultural and mining soil parameters/characteristics, all samples are dried and ground prior to sample analysis.

The reference date for Radon analysis is the sample collection date. The reference date for all other Radiochemical analyses is the analysis date. Radiochemical precision results represent a 2-sigma Total Measurement Uncertainty.

### Contact and Corrective Action Comments:

Energy Labs INC is missing pages three and four worth of samples from the chain of custody. All other samples are present and match the Chain of Custody.

We received the missing samples on 6/20/2023 @1000. The samples are intact and match the Chain of Custody. The Temperature for the cooler was 24.8°C and received with no temp blank or ice.
NOTE: The Lab Sample ID's will reflect a received date of when the initial samples were received which will be 6/19/2023 @1000.
Called and spoke with Ms.Anita and informed her we received the samples.

# Work Order Receipt Checklist - Continued

## Rio Grande Resources Corporation C23060688

Temperature Blank temperature for Cooler 1 was 19.0°C and Cooler 2 was 18.9°C.

6/19/23 DR

# Chain of Custody & Analytical Request Record

ENERGY LABORATORIES — Trust our People. Trust our Data.

www.energylab.com



## Account Information *(Billing information)*

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☐Email |
| Purchase Order | MT11572 |
| Quote | 16056 |
| Bottle Order | |

## Report Information *(if different than Account Information)*

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Bruce Norquist |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | bruce.norquist@ga.com |
| Receive Report | ☒Hard Copy ☒Email |

Special Report/Formats: ☐ LEVEL IV ☐NELAC ☐ EDD/EDT *(contact laboratory)* ☐ Other_____

## Comments

## Project Information

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM Subsurface soil investigation |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-7971 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for Soil | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | WBSB-02 0-6" | 05/17/2023 | 8:15 am | 1 | S | ✓ | | | C23060688-1 |
| 2 | WBSB-04 0-6' | 05/17/2023 | 8:35 am | 1 | S | ✓ | | | -2 |
| 3 | WBSB-01 0-6' | 05/17/2023 | 8:55 am | 1 | S | ✓ | | | -3 |
| 4 | WBSB-05 0-6" | 05/17/2023 | 9:20 am | 1 | S | ✓ | | | -4 |
| 5 | WBSB-03 0-6" | 05/17/2023 | 9:42 am | 1 | S | ✓ | | | -5 |
| 6 | WBSB-07 0-6" | 05/17/2023 | 10:14 am | 1 | S | ✓ | | | -6 |
| 7 | WBSB-08 0-6" | 05/17/2023 | 10:34 am | 1 | S | ✓ | | | -7 |
| 8 | WBSB-08 1'-1.5' | 05/17/2023 | 10:42 am | 1 | S | ✓ | | | -8 |
| 9 | WBSB-06 0-6" | 05/17/2023 | 10:54 am | 1 | S | ✓ | | | -9 |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were **NOT** used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Bruce L. Norquist | 6/14/23 | Bruce L. Norquist | Shelby Richins | 6/9/23 1005 | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number *(cash/check only)* |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

# Chain of Custody & Analytical Request Record

ENERGY LABORATORIES — Trust our People. Trust our Data.

www.energylab.com



## Account Information *(Billing information)*

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☐Email |
| Purchase Order | MT11572 |
| Quote | 16056 |
| Bottle Order | |

## Report Information *(if different than Account Information)*

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Bruce Norquist |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | bruce.norquist@ga.com |
| Receive Report | ☒Hard Copy ☒Email |
| Special Report/Formats: | ☐ LEVEL IV ☐NELAC ☐ EDD/EDT *(contact laboratory)* ☐ Other_____ |

## Comments

## Project Information

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM Subsurface soil investigation |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-7971 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
- ☒ Unprocessed Ore
- ☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
- ☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**

A - Air; W - Water; S - Soils/Solids; V - Vegetation; B - Bioassay; O - Oil; DW - Drinking Water

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification *(Name, Location, Interval, etc.)* | Collection Date | Collection Time | Number of Containers | Matrix *(See Codes Above)* | EPA 901.1 Modified for Soil | See Attached | RUSH TAT | ELI LAB ID *Laboratory Use Only* |
|---|---|---|---|---|---|---|---|---|---|
| 1 | DSSB-01 | 05/17/2023 | 12:00 pm | 1 | S | ✓ | | | |
| 2 | MCSB-16 1' | 05/18/2023 | 10:45 am | 1 | S | ✓ | | | |
| 3 | MCSB-16 2' | 05/18/2023 | 11:00 am | 1 | S | ✓ | | | |
| 4 | MCSB-15 1' | 05/18/2023 | 11:38 am | 1 | S | ✓ | | | |
| 5 | MCSB-17 1' | 05/18/2023 | 8:45 am | 1 | S | ✓ | | | |
| 6 | MCSB-18 1'-1.5' | 05/18/2023 | 9:48 am | 1 | S | ✓ | | | |
| 7 | DSSB-02 | 05/18/2023 | 1:00 pm | 1 | S | ✓ | | | |
| 8 | MCSB-11 4' | 05/22/2023 | 11:04 am | 1 | S | ✓ | | | |
| 9 | MCSB-13 1' | 05/22/2023 | 8:25 am | 1 | S | ✓ | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were **NOT** used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Bruce L. Norquist | 6/14/23 | Bruce L. Norquist | | 6/19/23 | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Sheila Perkins | 1000 | |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number *(cash/check only)* |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

ENERGY LABORATORIES
Trust our People. Trust our Data.

# Chain of Custody & Analytical Request Record

www.energylab.com



## Account Information *(Billing information)*

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☐Email |
| Purchase Order | MT11572 |
| Quote | 16056 |
| Bottle Order | |

## Report Information *(if different than Account Information)*

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Bruce Norquist |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | bruce.norquist@ga.com |
| Receive Report | ☒Hard Copy ☒Email |
| Special Report/Formats: | ☐ LEVEL IV ☐NELAC ☐ EDD/EDT *(contact laboratory)* ☐ Other_____ |

## Comments

## Project Information

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM Subsurface soil investigation |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-7971 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

**Analysis Requested**

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification *(Name, Location, Interval, etc.)* | Collection Date | Collection Time | Number of Containers | Matrix *(See Codes Above)* | EPA 901.1 Modified for Soil | See Attached | RUSH TAT | ELI LAB ID *Laboratory Use Only* |
|---|---|---|---|---|---|---|---|---|---|
| 1 | MCSB-12 1' | 05/22/2023 | 9:28 am | 1 | S | ✓ | | | C23060688 |
| 2 | MCSB-11 5' | 05/22/2023 | 11:12 am | 1 | S | ✓ | | | |
| 3 | MCSB-14 1' | 05/23/2023 | 8:53 am | 1 | S | ✓ | | | |
| 4 | MCSB-08 5' | 05/23/2023 | 11:10 am | 1 | S | ✓ | | | |
| 5 | MCSB-08 6.5' | 05/23/2023 | 11:25 am | 1 | S | ✓ | | | |
| 6 | MCSB-9 1' | 05/24/2023 | 8:25 am | 1 | S | ✓ | | | |
| 7 | MCSB-9 2' | 05/24/2023 | 8:40 am | 1 | S | ✓ | | | |
| 8 | MCSB-10 1' | 05/24/2023 | 9:15 am | 1 | S | ✓ | | | |
| 9 | MCSB-5 4' | 05/24/2023 | 10:40 am | 1 | S | ✓ | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were **NOT** used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Bruce L. Norquist | 6/14/23 | Bruce L. Norquist | | 6/19/23 | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Shelby Kitchens | 1000 | |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number *(cash/check only)* |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

# Chain of Custody & Analytical Request Record

ENERGY LABORATORIES — Trust our People. Trust our Data.

www.energylab.com



## Account Information (Billing information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☐Email |
| Purchase Order | MT11572 |
| Quote | 16056 |
| Bottle Order | |

## Report Information (if different than Account Information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Bruce Norquist |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | bruce.norquist@ga.com |
| Receive Report | ☒Hard Copy ☒Email |
| Special Report/Formats: | ☐ LEVEL IV ☐NELAC ☐ EDD/EDT (contact laboratory) ☐ Other_____ |

## Comments

## Project Information

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM Subsurface soil investigation |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-7971 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
- ☒ Unprocessed Ore
- ☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
- ☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**

A - Air; W - Water; S - Soils/Solids; V - Vegetation; B - Bioassay; O - Oil; DW - Drinking Water

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | Analysis Requested: EPA 901.1 Modified for Soil | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | MCSB-5 6' | 05/24/2023 | 11:00 am | 1 | S | ✓ | | | C23060688 |
| 2 | MCSB-5 7.5' | 05/24/2023 | 11:10 am | 1 | S | ✓ | | | |
| 3 | MCSB-7 3' | 05/24/2023 | 12:46 pm | 1 | S | ✓ | | | |
| 4 | MCSB-7 4.5' | 05/24/2023 | 1:00 pm | 1 | S | ✓ | | | |
| 5 | DSSB-03 | 05/24/2023 | 1:30 pm | 1 | S | ✓ | | | |
| 6 | MCSB-06 6' | 05/30/2023 | 9:15 am | 1 | S | ✓ | | | |
| 7 | MCSB-04 1' | 05/30/2023 | 9:35 am | 1 | S | ✓ | | | |
| 8 | MCSB-04 2' | 05/30/2023 | 9:45 am | 1 | S | ✓ | | | |
| 9 | MCSB-02 3' | 05/30/2023 | 10:50 am | 1 | S | ✓ | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were **NOT** used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Bruce L. Norquist | 6/14/23 | Bruce L. Norquist | | 6/14/23 | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Shelby Richins | 1000 | |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested.
This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

ENERGY LABORATORIES
Trust our People. Trust our Data.

# Chain of Custody & Analytical Request Record

www.energylab.com



## Account Information (Billing information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☐Email |
| Purchase Order | MT11572 |
| Quote | 16056 |
| Bottle Order | |

## Report Information (if different than Account Information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Bruce Norquist |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | bruce.norquist@ga.com |
| Receive Report | ☒Hard Copy ☒Email |
| Special Reports/Formats: | ☐ LEVEL IV ☐NELAC ☐ EDD/EDT (contact laboratory) ☐ Other_____ |

## Comments

## Project Information

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM Subsurface soil investigation |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-7971 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for Soil | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | MCSB-02 4' | 05/30/2023 | 11:00 am | 1 | S | ✓ | | | 2306068 |
| 2 | MCSB-02 5.2' | 05/30/2023 | 11:15 am | 1 | S | ✓ | | | |
| 3 | MCSB-01 2' | 05/30/2023 | 12:50 pm | 1 | S | ✓ | | | |
| 4 | MCSB-01 3' | 05/30/2023 | 1:00 pm | 1 | S | ✓ | | | |
| 5 | MCSB-03 1' | 05/30/2023 | 1:40 pm | 1 | S | ✓ | | | |
| 6 | MCSB-03 2' | 05/30/2023 | 1:50 pm | 1 | S | ✓ | | | |
| 7 | DSSB-04 | 05/30/2023 | 2:15 pm | 1 | S | ✓ | | | |
| 8 | WBSB-09 0-6" | 05/31/2023 | 8:25 am | 1 | S | ✓ | | | |
| 9 | WBSB-12 0-1" | 05/31/2023 | 8:50 am | 1 | S | ✓ | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were **NOT** used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Bruce L. Norquist | 6/14/23 | Bruce L. Norquist | | 6/19/23 | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Shelby Robins | 1020 | |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

ENERGY LABORATORIES
Trust our People. Trust our Data.

# Chain of Custody & Analytical Request Record

www.energylab.com



## Account Information (Billing information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☐Email |
| Purchase Order | MT11572 |
| Quote | 16056 |
| Bottle Order | |

## Report Information (if different than Account Information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Bruce Norquist |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | bruce.norquist@ga.com |
| Receive Report | ☒Hard Copy ☒Email |
| Special Report/Formats: | ☐ LEVEL IV ☐NELAC ☐ EDD/EDT (contact laboratory) ☐ Other_____ |

## Comments

## Project Information

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM Subsurface soil investigation |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-7971 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for Soil | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | WBSB-12 2-6" | 05/31/2023 | 9:00 am | 1 | S | ✓ | | | |
| 2 | WBSB-10 0-6" | 05/31/2023 | 9:10 am | 1 | S | ✓ | | | |
| 3 | WBSB-11 0-6" | 05/31/2023 | 9:35 am | 1 | S | ✓ | | | |
| 4 | OPSB-03 4.2' | 06/01/2023 | 9:10 am | 1 | S | ✓ | | | |
| 5 | OPSB-03 4.5' | 06/01/2023 | 9:25 am | 1 | S | ✓ | | | |
| 6 | OPSB-02 5.5' | 06/01/2023 | 11:20 am | 1 | S | ✓ | | | |
| 7 | OPSB-05 3.75' | 06/01/2023 | 11:55 am | 1 | S | ✓ | | | |
| 8 | DSSB-05 | 06/01/2023 | 12:30 pm | 1 | S | ✓ | | | |
| 9 | | | | | | | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were **NOT** used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Bruce L. Norquist | 6/14/23 | Bruce L Norquist | | 6/19/23 | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Shelby Nichols | 1000 | |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

# Appendix C

## Radiologic Instrument Calibration and Operational Function Check and Collimated Detector Correlation Documentation

**AVM Environmental Services, Inc.**
**Ludlum SCA L2221 - 44-20 3x3 NaI Detector Function Check**
**559 - 659 KeV Gamma Radiation Soil Screening**

L2221 #290801

Ludlum 44-20 3x3 NaI Detector, #PR295573

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Acceptable background Count (cpm) Range (20%) 53 to 79

Acceptable Source Count (cpm) Range (20%) 12557 to 18835

| Date | Physical Check | Cal Date | Battery(1) Volts or OK | HV Volts | Threshhold mV (2) | Window mV | Window In/Out | BKG Counts cpm | Source Counrts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 5-17-23 | ✓ | 5-10-23 | ✓ | 577 | 559 | 100 | in | 70 | 16805 | Y | — | VP |
| 5-18-23 | ✓ | 5-10-23 | ✓ | 578 | 559 | 100 | in | 66 | 16200 | Y | — | VP |
| 5-22-23 | ✓ | 5-10-23 | ✓ | 582 | 559 | 100 | in | 68 | 15900 | Y | — | VP |
| 5-23-23 | ✓ | 5-10-23 | ✓ | 582 | 559 | 100 | in | 71 | 15508 | Y | — | VP |
| 5-25-23 | ✓ | 5-10-23 | ✓ | 578 | 559 | 100 | in | 73 | 16253 | Y | — | VP |
| 5-30-23 | ✓ | 5-10-23 | ✓ | 577 | 559 | 100 | in | 72 | 16101 | Y | — | VP |
| 5-31-23 | ✓ | 5-10-23 | ✓ | 575 | 559 | 100 | in | 64 | 15789 | Y | | VP |
| 6-1-23 | ✓ | 5-10-23 | ✓ | 577 | 559 | 100 | in | 71 | 16224 | Y | — | VP |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 220 mV; (3) Window @ 440, must be IN

**AVM Environmental Services, Inc**
**Scaler/Ratemeter - HP-210L Detector Function Check**

Scaler/Ratemeter ID: LIZ S#274216

HP-210L Detector ID: ANA-1

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Acceptable background Count (cpm) Range (20%) 34 to 50

Acceptable Source Count (cpm) Range (20%) 2880 to 4320

| Date | Physical Check | Cal date | Battery Volts or OK | HV Volts | BKG Counts cpm | Source Counrts cpm | Within Acceptable Range Y or N | Comments | Tech |
|---|---|---|---|---|---|---|---|---|---|
| 10-7-22 | ✓ | 10-7-22 | ok | .9 | 40 | 3700 | y | @ AVM office | VP |
| 1-4-23 | ✓ | 10-7-22 | ok | .9 | 45 | 3600 | y | @ AVM office | VP |
| 4-5-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3600 | y | @ AVM office | VP |
| 4-11-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3600 | y | @ AVM office | VP |
| 4-12-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3600 | y | @ AVM office | VP |
| 4-13-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3600 | y | @ AVM office | VP |
| 4-20-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3600 | y | @ AVM office | VP |
| 5-9-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3600 | y | @ AVM office | VP |
| 5-16-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3400 | y | @ AVM office | VP |
| 5-17-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3300 | y | @ AVM office | VP |
| 5-18-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3400 | y | @ AVM office | VP |
| 5-22-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3300 | y | @ AVM office | VP |
| 5-23-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3400 | y | @ AVM office | VP |
| 5-24-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3600 | y | @ AVM office | VP |
| 5-25-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3400 | y | @ AVM office | VP |
| 5-30-23 | ✓ | 10-7-22 | ok | .9 | 45 | 3600 | y | @ AVM office | VP |
| 5-31-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3300 | y | @ AVM office | VP |
| 6-1-23 | ✓ | 10-7-22 | ok | .9 | 40 | 3400 | y | @ AVM office | VP |

Note: (1) Threshhold must be at 100 mV;

**AVM Environmental Services, Inc.**
**Scaler/Ratemeter - 2" x 2" NaI Detector Function Check**

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

2" x 2" NaI Detector ID: SPA-3 S# 408522-30

Acceptable background Count (cpm) Range (20%) 6391 to 9587 (Bare)

Acceptable background Count (cpm) Range (20%) 2546 to 3820 (collimated)

Acceptable Source Count (cpm) Range (20%) 77687 to 116531

| Date | Scaler/Ratemeter | Physical Check | Cal Due | Battery(1) Volts or OK | HV Volts | THR mV (2) | Window In or OUT(3) | C.C.(4) | BKG Counts cpm | Source Counrts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2-1-23 | L2221 S# 290801 | ✓ | 10-7-23 | ok | 900 | 10 | out | 1 | 7989 Bare / 3183 Coll. | 97109 | Y | – | VP |
| 4-5-23 | L2221 S# 68782 | ✓ | 10-7-23 | ok | 900 | 10 | out | 1 | 7621 Bare / 2949 Coll. | 99478 | Y | – | VP |
| 4-11-23 | L2221 S# 68782 | ✓ | 10-7-23 | ok | 900 | 10 | out | 1 | 7822 Bare / 3044 Coll. | 99630 | Y | – | VP |
| 4-12-23 | L2221 S# 68782 | ✓ | 10-7-23 | ok | 900 | 10 | out | 1 | 7947 Bare / 3122 Coll. | 98687 | Y | – | VP |
| 4-13-23 | L2221 S# 68782 | ✓ | 10-7-23 | ok | 900 | 10 | out | 1 | 7894 Bare / 3150 Coll. | 99731 | Y | – | VP |
| 4-20-23 | L2221 S# 68782 | ✓ | 10-7-23 | ok | 900 | 10 | out | 1 | 7850 Bare / 2987 Coll. | 99214 | Y | – | VP |
| 5-16-23 | L2221 S# 68782 | ✓ | 10-7-23 | ok | 900 | 10 | out | 1 | 7714 Bare / 3018 Coll. | 97431 | Y | – | VP |
| 5-17-23 | L2241-2 S# 287029 | ✓ | 10-7-23 | ok | 900 | 10 | N/A | 1 | 7914 Bare / 3002 Coll. | 99331 | Y | – | VP |
| 5-18-23 | L2241-2 S# 287029 | ✓ | 10-7-23 | ok | 900 | 10 | N/A | 1 | 7842 Bare / 3118 Coll. | 98522 | Y | – | VP |
| 5-22-23 | L2241-2 S# 287029 | ✓ | 10-7-23 | ok | 900 | 10 | N/A | 1 | VP 7644 3168 Bare / 764 Coll. | 97555 | Y | – | VP |
| 5-23-23 | L2241-2 S# 287029 | ✓ | 10-7-23 | ok | 900 | 10 | N/A | 1 | 7912 Bare / 2974 Coll. | 98782 | Y | – | VP |
| 5-24-23 | L2241-2 S# 287029 | ✓ | 10-7-23 | ok | 900 | 10 | N/A | 1 | 8086 Bare / 3157 Coll. | 98949 | Y | – | VP |
| 5-30-23 | L2241-2 S# 287029 | ✓ | 10-7-23 | ok | 900 | 10 | N/A | 1 | 7814 Bare / 3160 Coll. | 97901 | Y | – | VP |
| 5-31-23 | L2241-2 S# 287029 | ✓ | 10-7-23 | ok | 900 | 10 | N/A | 1 | 7833 Bare / 3022 Coll. | 98634 | Y | – | VP |
| 6-1-23 | L2241-2 S# 287029 | ✓ | 10-7-23 | ok | 900 | 10 | N/A | 1 | 7882 Bare / 3018 Coll. | 97601 | Y | – | VP |
| 6-7-23 | L2241-2 S# 287029 | ✓ | 10-7-23 | ok | 900 | 10 | N/A | 1 | 7942 Bare / 3001 Coll. | 98441 | Y | – | VP |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 10.0 mV; (3) Window Position must be OUT; (4) CC on L2241-2 set at 0.001
For L2241-2 Check HV and Threshold using Ludlum 500 pulser.

**AVM Environmental Services, Inc.**
**Micro R Meter Function Check Form**

Micro R Meter: Ludlum 19, SR#76248

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Function Check @ Calibration 115

Acceptable Function Check Reading (uR/hr) Range (20%) 92 to 138

| Date | Physical Check | Cal Date | Battery(1) Volts or OK | BKG Reading uR/hr | Source Reading (2) uR/hr | Within Acceptable Range Y or N | Cal Due | Tech |
|---|---|---|---|---|---|---|---|---|
| 10-17-22 | ✓ | 10-6-22 | ok | 10-12 | 110 | y | 10-6-23 | VP |
| 1-4-23 | ✓ | 10-6-22 | ok | 8-10 | 120 | y | 10-6-23 | VP |
| 4-5-23 | ✓ | 10-6-22 | ok | 8-10 | 110 | y | 10-6-23 | VP |
| 4-11-23 | ✓ | 10-6-22 | ok | 8-10 | 110 | y | 10-6-23 | VP |
| 4-12-23 | ✓ | 10-6-22 | ok | 8-10 | 110 | y | 10-6-23 | VP |
| 4-13-23 | ✓ | 10-6-22 | ok | 8-10 | 110 | y | 10-6-23 | VP |
| 4-20-23 | ✓ | 10-6-22 | ok | 8-10 | 110 | y | 10-6-23 | VP |
| 5-9-23 | ✓ | 10-6-22 | ok | 8-10 | 110 | y | 10-6-23 | VP |
| 5-16-23 | ✓ | 10-6-22 | ok | 8-10 | 110 | y | 10-6-23 | VP |
| 5-17-23 | ✓ | 10-6-22 | ok | 8-10 | 110 | y | 10-6-23 | VP |
| 5-18-23 | ✓ | 10-6-22 | ok | 8-10 | 110 | y | 10-6-23 | VP |
| 5-22-23 | ✓ | 10-6-22 | ok | 10-12 | 100 | y | 10-6-23 | VP |
| 5-23-23 | ✓ | 10-6-22 | ok | 8-10 | 100 | y | 10-6-23 | VP |
| 5-24-23 | ✓ | 10-6-22 | ok | 8-10 | 110 | y | 10-6-23 | VP |
| 5-25-23 | ✓ | 10-6-22 | ok | 10-12 | 110 | y | 10-6-23 | VP |
| 5-30-23 | ✓ | 10-6-22 | ok | 8-10 | 100 | y | 10-6-23 | VP |
| 5-31-23 | ✓ | 10-6-22 | ok | 8-10 | 100 | y | 10-6-23 | VP |
| 6-1-23 | ✓ | 10-6-22 | ok | 8-10 | 110 | y | 10-6-23 | VP |

Note: (1) Battery Voltage must be within BAT TEST Range (2) Function Check Source must be placed in the circle on the front side of the meter

**AVM Environmental Services Inc.**

**Scaler/Ratemeter Calibration Form**

Model : L2221 S/N: 68782

Reference Instrument/Source: Ludlum Pulser 500, S/N:114513

**HV Calibration**

HV Readout (2 points): Ref/Inst 600 / 600 Ref/Inst 900 / 900

**Ratemeter Calibration**

Instrument Threshold @ 100 (10 mV), WIN: Out, HV 900VDC; Pulser Threshold @ 200 (20mV)

| Range/Mode | Range Multiplier | Calibration Point (Pulser Setting) cpm x multiplier | Target CPM (±5%) | As Found Reading | | Left or Set Reading |
|---|---|---|---|---|---|---|
| Ratemeter | x1 | 40x1 | 38-42 | 40 | | 40 |
| | x1 | 40x10 | 380-420 | 400 | | 400 |
| | x10 | 40x100 | 3800-4200 | 4000 | | 4000 |
| | x100 | 40x1K | 38K-42K | 40000 | | 40000 |
| | x1K | 40x10K | 380K-420K | 400000 | | 400000 |
| Digital Ratemeter | - | 40x1 | 38-42 | 39 | | 39 |
| | - | 40x10 | 380-420 | 400 | | 400 |
| | - | 40x100 | 3800-4200 | 3960 | | 3960 |
| | - | 40x1K | 38K-42K | 39500 | | 39500 |
| | - | 40x10K | 380K-420K | 395000 | | 395000 |
| | | | | | | |

**Threshold/Gain Calibration**

WIN OUT

| Pulser Amplitude (mV) | Pulser CPM | | L2221 Theshold (mv) | Target CPM | L2221 CPM Found | | L2221 CPM Left or Set @ |
|---|---|---|---|---|---|---|---|
| 10.0 | 40000 | | 100 (10 mV) | 27K -33K | 31534 | | 31534 |
| 20.0 | 40000 | | 200 (20 mV) | 27K -33K | 29273 | | 29273 |
| 30.0 | 40000 | | 300 (30 mV) | 27K -33K | 30822 | | 30822 |
| 40.0 | 40000 | | 400 (40 mV) | 27K -33K | 29659 | | 29659 |
| 50.0 | 40000 | | 500 (50 mV) | 27K -33K | 29242 | | 29242 |

Note: Use R174 Gain Control on Power Supply Board to adjust L2221 CPM @75% for Threshold/Gain Calibration

**Window Cut-off Points Check**

L2221 Threshold set @100 (10.0 mv)

WIN @ 100 (10.0 mV) ✓ WIN @ 400 (40.0 mV) ✓

WIN @ 200 (20.0 mV) ✓ WIN @ 500 (50.0 mV) ✓

Date 10-7-22 Calibrated By Vicky Patel

**AVM Environmental Services Inc.**

**Scaler/Ratemeter Calibration Form**

Model : L2221 S/N: 290801

Reference Instrument/Source: Ludlum Pulser 500, S/N:114513

**HV Calibration**

HV Readout (2 points): Ref/Inst 600 / 600 Ref/Inst 900 / 900

**Ratemeter Calibration**

Instrument Threshold @ 100 (10 mV), WIN: Out, HV 900VDC; Pulser Threshold @ 200 (20mV)

| Range/Mode | Range Multiplier | Calibration Point (Pulser Setting) cpm x multiplier | Target CPM (±5%) | As Found Reading | | Left or Set Reading |
|---|---|---|---|---|---|---|
| Ratemeter | x1 | 40x1 | 38-42 | 40 | | 40 |
| | x1 | 40x10 | 380-420 | 400 | | 400 |
| | x10 | 40x100 | 3800-4200 | 4000 | | 4000 |
| | x100 | 40x1K | 38K-42K | 40000 | | 40000 |
| | x1K | 40x10K | 380K-420K | 400000 | | 400000 |
| Digital Ratemeter | - | 40x1 | 38-42 | 40 | | 40 |
| | - | 40x10 | 380-420 | 395 | | 395 |
| | - | 40x100 | 3800-4200 | 3950 | | 3950 |
| | - | 40x1K | 38K-42K | 39503 | | 39503 |
| | - | 40x10K | 380K-420K | 395978 | | 395978 |
| | | | | | | |

**Threshold/Gain Calibration**

WIN OUT

| Pulser Amplitude (mV) | Pulser CPM | | L2221 Theshold (mv) | Target CPM | L2221 CPM Found | | L2221 CPM Left or Set @ |
|---|---|---|---|---|---|---|---|
| 10.0 | 40000 | | 100 (10 mV) | 27K -33K | 30889 | | 30889 |
| 20.0 | 40000 | | 200 (20 mV) | 27K -33K | 30419 | | 30419 |
| 30.0 | 40000 | | 300 (30 mV) | 27K -33K | 29799 | | 29799 |
| 40.0 | 40000 | | 400 (40 mV) | 27K -33K | 30238 | | 30238 |
| 50.0 | 40000 | | 500 (50 mV) | 27K -33K | 30330 | | 30330 |

Note: Use R174 Gain Control on Power Supply Board to adjust L2221 CPM @75% for Threshold/Gain Calibration

**Window Cut-off Points Check**

L2221 Threshold set @100 (10.0 mv)

WIN @ 100 (10.0 mV) ✓ WIN @ 400 (40.0 mV) ✓

WIN @ 200 (20.0 mV) ✓ WIN @ 500 (50.0 mV) ✓

Date 10-7-22 Calibrated By Victor Patel

**AVM Environmental Services Inc.**
**Scaler/Ratemeter Calibration Form**

Scaler/Ratemeter Model: L2241-2 S/N: 287029

Calibration Source: Ludlum Model 500 Pulser #114513

Threshold (input sensitivity), Found at: 10 mV Left or Set at: 10 mV

Window, In/Out: N/A Window: N/A mV

Pulser Amplitude Set @: 20 mV

| Range/Mode | Calibration Point (Pulser Setting) cpm x multiplier | As Found Reading | Left or Set Reading |
|---|---|---|---|
| Ratemeter | 40x1 | 38-42 | 38-42 |
| | 40x10 | 395-400 | 395-400 |
| | 40x100 | 3.95k-4k | 3.95k-4k |
| | 40x1k | 39.6k-40k | 39.6k-40k |
| | | | |
| Scaler | 40x1 | 39 | 39 |
| | 40x10 | 398 | 398 |
| | 40x100 | 3998 | 3998 |
| | 40x1k | 39940 | 39940 |
| | | | |
| | | | |

HV Set @: 900 VDC

Date: 10-7-22 Calibrated By: Victor Patel

**AVM Environmental Services Inc.**
**Scaler/Ratemeter Calibration Form**

Scaler/Ratemeter Model: L12 S/N: 274216

Calibration Source: Ludlum Model 500 Pulser #114513

Threshold (input sensitivity), Found at: 10 mV Left or Set at: 10 mV

Window, In/Out: N/A Window: N/A mV

Pulser Amplitude Set @: 20 mV

| Range/Mode | Calibration Point (Pulser Setting) cpm x multiplier | As Found Reading | Left or Set Reading |
|---|---|---|---|
| x 1 | 40x10 | 400 | 400 |
| x 10 | 40x100 | 4000 | 4000 |
| x 100 | 40x1k | 40k | 40k |
| x 1000 | 40x10k | 400k | 400k |

HV Set @: 900 VDC

Date: 10-7-22 Calibrated By: [signature] Vic Patel

**AVM Environmental Services Inc.**
L2221 SCA/L44-20 Energy Calibration Form

SCA: L2221, SR #290801 Detector: Ludlum 44-20 (3x3 NaI Scintillator)

Calibration Source: Cs-137 Check Source, 5 uCi (August 2008) For 662 KeV Peak Cal

Threshold (input sensitivity) **652**

Window, In/Out **IN** Window **20**

HV Initial 100, At Peak 579

Maximum CPM: 198160 Background CPM: 13

HV Set @ 579 VDC

For Bi-214 609.2 KeV Peak (559 - 659 KeV ROI), Set Threshold @ 559, Window @ 100

Calibration Check w 1% U3O8 Ore Check Source: 15696 CPM

BKG = 65 cpm

Date 5-10-23 Calibrated By

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S# 68782, Detector L44-20 S#295573
Instrument Calibration Date: 10-7-22, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt Taylor Mine - Correlation Calibration


Area exposure rate:

| Date/Time | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 5-10-23 | Blank | | 329 | | 66 | | |
| 5-10-23 | 6.6pCi/g Ref. Soil | 3000 | 2998 | | 600 | | |
| 5-10-23 | 25 pCi/g Ref Soil | 2984 | 9552 | 9603 | 1921 | | |
| 5-10-23 | 50 pCi/g Ref Soil | 2976 | 18078 | 18224 | 3645 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____


## AVM Environmental Services
## Ex-Situ Soil Screening Gamma Radiation Level to Ra-226 Correlation
## Mt. Taylor Mine Site Subsurface Soil Investigation

| Reference Soil ID | Date | Ra-226 pCi/g | Wt gms | 609 KeV CP5Min Gross (3x3 Nal Detector) | CPM |
|---|---|---|---|---|---|
| Blank | 5/10/2023 | - | - | 329 | 66 |
| 6.6 pCi/g Ra-226 Ref Soil | 5/10/2023 | 6.6 | 3000 | 2998 | 600 |
| 25 pCi/g Ra-226 Ref Soil | 5/10/2023 | 25 | 3000 | 9603 | 1921 |
| 50 pCi/g Ra-226 Ref Soil | 5/10/2023 | 50 | 3000 | 18224 | 3645 |



## Surface Soil Ra-226 to Gamma Radiation Level Correlation
## Mount Taylor Mine Site

| Survey Date | Survey Point ID/Description | Survey Point Coordinate NAD83 StatePlane NM West, Feet | | Static Gamma Radiation Survey | | Sample Laboratory Analysis | Gamma Exposure Rate µR/hr |
|---|---|---|---|---|---|---|---|
| | | Northing | Easting | Bare 2x2 NaI Detector CPM | Collimated (0.5" Pb) 2x2 NaI Detector CPM | Ra-226 pCi/g | |
| 05/17/23 | WBSB-01 | 1,581,413 | 2,782,866 | 26,897 | 6,297 | **0.9** | 33 |
| 05/17/23 | WBSB-02 | 1,581,390 | 2,782,444 | 26,749 | 6,350 | **1.5** | 33 |
| 05/17/23 | WBSB-03 | 1,581,356 | 2,783,329 | 24,529 | 6,073 | **3.2** | 31 |
| 05/17/23 | WBSB-04 | 1,581,339 | 2,782,706 | 30,064 | 6,069 | **1.5** | 37 |
| 05/17/23 | WBSB-05 | 1,581,329 | 2,783,062 | 31,828 | 6,945 | **2.1** | 41 |
| 05/17/23 | WBSB-06 | 1,581,271 | 2,782,942 | 35,410 | 7,288 | **1.3** | 47 |
| 05/17/23 | WBSB-07 | 1,581,187 | 2,783,253 | 37,965 | 8,183 | **3.7** | 47 |
| 05/17/23 | WBSB-08 | 1,581,164 | 2,782,988 | 55,849 | 11,042 | **9.7** | 70 |
| 05/31/23 | WBSB-09 | 1,581,254 | 2,782,870 | 36,491 | 6,599 | **1.2** | 44 |
| 05/31/23 | WBSB-10 | 1,581,263 | 2,783,140 | 34,898 | 7,286 | **3.5** | 48 |
| 05/31/23 | WBSB-11 | 1,581,277 | 2,783,335 | 29,002 | 6,602 | **2.7** | 34 |




SUMMARY OUTPUT

### Regression Statistics

| | |
|---|---|
| Multiple R | 0.91 |
| R Square | 0.83 |
| Adjusted R Square | 0.81 |
| Standard Error | 1.08 |
| Observations | 11 |

**ANOVA**

| | df | SS | MS | F | Significance F |
|---|---|---|---|---|---|
| Regression | 1 | 50.92 | 50.92 | 43.97 | 9.58E-05 |
| Residual | 9 | 10.42 | 1.16 | | |
| Total | 10 | 61.35 | | | |

| | Coefficients | Standard Error | t Stat | P-value | Lower 95% | Upper 95% | Lower 95.0% | Upper 95.0% |
|---|---|---|---|---|---|---|---|---|
| Intercept | -8.41 | 1.73 | -4.87 | 0.00089 | -12.32 | -4.50 | -12.32 | -4.50 |
| X Variable 1 | 0.00 | 0.00 | 6.63 | 0.00010 | 0.00104 | 0.00211 | 0.00104 | 0.00211 |

# Addendum

## August 14, 2023 Surface and Subsurface Soil Radiologic Characterization Report Windblown Area, Ore Pad Area and Mine Compound, Mount Taylor Mine Site

This addendum presents the revision to the Ore Pad soil radiologic characterization summary described in the August 14, 2023 Surface and Subsurface Soil Radiologic Characterization; Windblown Area, Ore Pad Area and Mine Compound Report (Report) for the Mt. Taylor Mine Site (Site). As discussed in Section 4.5 and shown in Figure 2 of the Report, the approximated depth of waste rock from ground surface to non-impacted native soil in the northwest area of the Ore Pad was estimated at 15 feet, two feet past the excavation depth limit of the trenching equipment, at two test pit locations (OPSB-01 and OPSB-08). The waste rock depth in the other areas of the Ore Pad ranged from 3.0 feet to 4.5 feet below ground surface (bgs). Upon review of historical operational information, the eastern portion of the adjacent Ore Pad Runoff Retention Pond (Retention Pond) was backfilled with low grade waste rock and used as part of the foundation for the Ore Pad Area expansion. A 1981 aerial image of the Site (Figure 1A) shows the footprint of the Retention Pond prior to backfilling to expand the Ore Pad. The 1981 aerial image explains the cause of the anomalous estimated depth of the waste rock in the northwest area of the Ore Pad compared to the remainder of the areas of the Ore Pad. As shown in Figure 2A, recent topographic contours show the elevation of the northwest area of the Ore Pad ground surface at 7320 feet mean sea level (msl) and the Retention Pond bottom ground surface at 7298 feet msl. Considering that the waste rock in the existing Retention Pond is two feet thick, the baseline elevation of the Retention Pond bottom is estimated at 7296 feet msl. Thus, the waste rock depth within the Retention Pond foot print in the northwest area of the Ore Pad is estimated at 24 feet.




N
W E
S

Environmental Services, Inc.

**Figure 1A**
**Mt. Taylor Mine Site**
**1981 Historic Areal Image of Ore Pad and Ore Pad Retention Pond Area with 2023 Soil Sample/Test Pit Locations**

**Legend**

- 2023 Soil Sample/Test Pit Location
- North Controlled Area Fence
- Ore Pad Characterization Area




N
W E
S

Environmental Services, Inc.

**Figure 2A**
**Mt. Taylor Mine Site**
**Ore Pad and Ore Pad Retention Pond Area Topographic Countour with 2023 Soil Sample/Test Pit Locations**

**Legend**

- 2023 Soil Sample/Test Pit Location (>6.8 Ra-226 pCi/g RCC Depth)
- Topographic Contour Lines
- Existing Ore Pad Retention Pond
- Historic Approx. Ore Pad Retention Pond
- Ore Pad Characterization Area
- North Controlled Area Fence

# Treatment Pond Radiologic Characterization

**Mt. Taylor Mine Site**
**San Mateo, NM**

**Prepared by:**
**AVM Environmental Services, Inc.**
**1717 Del Norte Blvd.**
**Grants, NM 87020**

**Prepared for:**
**Rio Grande Resource Corporation**
**PO Box 1150**
**Grants, NM 87020**

**June 4, 2024**

## Table of Contents

1.0 Introduction and Background ..... 1
2.0 Previous Radiologic Characterization ..... 1
3.0 Objective of the Radiologic Characterization ..... 2
4.0 Field Investigation ..... 2
4.1 Surface Gamma Radiation Scan and Static Survey ..... 2
4.2 Soil Sampling and Ex-Situ Gamma Radiation Soil Screening ..... 4
4.3 Treatment Pond 1 Area Characterization Summary ..... 6
4.4 Treatment Pond 4, 5, 6 and 7 Area Characterization Summary ..... 6
4.5 Treatment Pond 8 Area Characterization Summary ..... 7
4.6 Borrow Area A Soil Piles ..... 8
5.0 Soil Sampling and Analysis ..... 8
6.0 Quality Assurance and Quality Control Measures ..... 8

## Tables

Table 1 Typical Gamma Scan Data Exported from Scan System Data Logger
Table 2 Static Surface Gamma Radiation Survey at Soil Sampling/Test Pit Locations
Table 3 Treatment Pond Characterization Area Soil Sample Field Ex-Situ Gamma Screening and Vendor Laboratory Results Summary
Table 4 Treatment Pond Surface and Subsurface Soil Ra-226 Level Summary

## Figures

Figure 1 Treatment Pond Characterization Areas and Concrete Structure locations
Figure 2 Treatment Pond Characterization Area Data Point Locations and Gamma Survey Data
Figure 3 Treatment Pond Characterization Area Estimated Depth of Contamination above the 6.8 pCi/g Ra-226 Investigation Level

## Appendices

Appendix A Surface and Subsurface Contamination Field Investigation Documentation (Soil Sample Log Forms, Field Soil Sample Ex-Situ Gamma Radiation Screening Forms)
Appendix B Concrete Structure Radiologic Investigation
Appendix C Radiologic Instrument Calibration and Operational Function Check and Collimated Detector Correlation Documentation
Appendix D Soil Sample COC and Laboratory Analytical Results Report

## 1.0 Introduction and Background

This report provides the results of the Treatment Pond Radiologic Characterization (TPRC) that was conducted at the Mt. Taylor Mine (Site) in Cibola County, near San Mateo, New Mexico. This TPRC was performed to check the status and estimate radiologic contamination exceeding the Site Radiation Cleanup Criteria (RCC) of 6.8 pCi/g Radium (Ra)-226 within six treatment ponds at the Site: Treatment Ponds 1, 4, 5, 6, 7 and 8. Any synthetic liners and previously identified radiologically impacted soils were removed from the treatment ponds during material removal efforts conducted in 2019, prior to this characterization. Additionally, various treatment pond concrete structures (hydraulic control structures) were left in place either intact or partially demolished, with concrete rumble remaining nearby most structures. The majority of the demolished concrete pieces were placed in piles south of the TPRC area. The TPRC area includes treatment pond dikes, bottoms, and concrete structures, as shown in the Figure 1. The methods and procedures used were consistent with the June 2020 Work Plan for Post-Mining Radiological Surveys of Permit Area and Impacted Lands (2020 Work Plan) and the applicable survey methods described in the Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM, EPA 2000a). The RCC specified in the March 2016 *Joint Guidance for the Cleanup and Reclamation of Existing Uranium Mining Operations in New Mexico* (EMNRD, 2016) (2016 Guidance) by the Energy, Minerals & Natural Resources Department (EMNRD) and the New Mexico Environment Department (NMED) was used for the investigation level (IL). The Ra-226 cleanup criteria of 5.0 pCi/g above the background level in land averaged over 100 square meters in surface soil (top six inches) specified in the Joint Guidance is taken from the UMTRCA (40 CFR 192) regulation, which is based on an unrestricted land use exposure scenario. A 6.8 pCi/g Ra-226 IL (5.0 pCi/g plus 1.8 pCi/g background level) has been established for the Site.

The Site was an underground uranium mine located in Cibola County, near San Mateo, New Mexico. The mine was developed by Gulf Mineral Resources Company (Gulf) in the 1970s and ore production occurred from 1979 to 1982. Following transfer of the Site to Chevron Resources Company in 1985, the ore production resumed and continued until 1990. Rio Grande Resources (RGR) acquired the Site in 1991. In 1999 the Site entered standby status under Mine Permit C1002RE with EMNRD. On December 29, 2017, the permit changed to an active status, and on December 3, 2019, RGR notified MMD of intentions to begin the Site closeout/closure process. The following sections describe the strategy, methods and procedures that were used and the results of the TPRC conducted at the Site.

## 2.0 Previous Radiologic Characterizations

Surface gamma radiation surveys were performed periodically within operationally controlled areas of the Site to monitor changes in radiological conditions during a period of remedial excavations in the Mine Water Treatment Unit (MWTU) ponds, construction of the disposal cell and placement of contaminated mine materials, and gradual removal of ore from the ore stockpile. The most recent gamma survey prior to this characterization, conducted March 2020, showed elevated gamma radiation levels in certain operational areas within the Controlled Area boundaries, including areas within the treatment ponds. The gamma

survey results are summarized in the June 2020 Work Plan, and indicate surface soils in portions of treatment Ponds 4 through 8, and the entire Pond 1 area exceed the 6.8 pCi/g Ra-226 IL.

## 3.0 Objective of the Radiological Characterization

The Site is a former uranium mine, therefore the surface and subsurface soil is expected to be impacted by radionuclides associated with the uranium decay series, with Ra-226 being the primary Constituent of Concern (COC). The objective of this characterization is to evaluate Ra-226 contamination exceeding the Site IL of 6.8 pCi/g Ra-226 in surface and subsurface soils to facilitate volume estimates of radiologic impacted material within the TPRC area.

## 4.0 Field Investigation

Field investigations for this characterization were conducted consistent with the June 2020 Work Plan and were performed during the period of November 2, 2023 through April 29, 2024. The specified TPRC areas are shown in Figure 1. The field investigations included both static 0.5-inch thick lead collimated and uncollimated (bare) 2x2 sodium iodide (NaI) detector gamma radiologic survey measurements and Differential Global Positioning System (DGPS) based bare detector gamma scan surveys, along with ex-situ soil screening, soil sampling, and offsite vendor laboratory confirmatory sample analysis. Geo-located gamma scans were conducted to provide Ra-226 concentration level estimates in surface soil and to assist in determining data point (static gamma, soil sampling) locations to assess surface and subsurface radiologic contamination relative to the IL. Ex-situ gamma radiation soil screening was performed on soil samples collected during this TPRC to provide real-time information to estimate surface and subsurface contamination depths. Offsite vender laboratory soil sample analysis was performed to confirm contamination relative to the IL levels estimated by the field ex-situ gamma radiation soil screening.

### 4.1 Surface Gamma Radiation Scan and Static Survey

The instrument configuration for direct gamma radiation level measurements during this characterization consisted of lead collimated and bare 2x2 NaI scintillation detectors (Eberline SPA-3) for detection of gamma radiation, coupled to a scaler/rate meter (Ludlum 2221 or Ludlum 2241). This instrument configuration is used widely for this type of survey and is recommended by the MARSSIM. The scaler/rate meters were interfaced with a sub-meter accurate DGPS with surveying software and a data logger/controller for electronically recording the gamma radiation levels to the corresponding geo-location coordinates. The coordinate system used for this work was the State Plane Coordinate System (NAD83, New Mexico West, US Feet) system. Direct gamma radiation surveys using a NaI scintillation detector provide radiation levels in counts per unit time, generally obtained as counts per minute (cpm).

During this characterization, systematic gamma radiation scan surveys using bare 2x2 NaI detectors were performed at the Site to determine the level of Ra-226 in surface soil within the characterization areas.

Although bare detectors do not avoid lateral gamma radiation shine, bare detectors have a large field of view and provide a large scan coverage area for an efficient and conservative lateral extent of contamination assessment. To better characterize the surface soil and to assist in the selection of data point locations, the surface gamma scan survey was performed at a higher density, 30-feet transect spacing compared to the March 2020 scan density of about 60-ft transect spacing. Thirty feet spaced geo-projected transects for Treatment Ponds 4, 5, 6, 7 and 8 were digitally created using a mapping software and loaded on the field data logger/controller. A gamma scan survey was not conducted at Treatment Pond 1 since the March 2020 gamma scan showed uniformly elevated measurements over the entire area making the additional surface gamma scan with a bare detector unnecessary in selecting data point locations. Data point locations were selected in Treatment Pond 1 by selecting locations that would adequately characterize the elements of the treatment pond as well as the areal extent of the area, as shown in Figure 2. Additionally, three of the data point locations in Treatment Pond 1 were biasedly located in material removal excavations performed prior to this characterization. Based on a conservative field of view (FOV) of at least six feet diameter for a bare 2x2 NaI detector for Ra-226 gamma radiations, scanning transects spacing of 30 feet would provide at least a 20% scan coverage. The gamma scan survey was performed by scanning along these transects with a bare 2x2 NaI detector at 12 inches above the ground surface at a scan rate of about three feet per second, with a data collection time interval of two seconds.

The geo-located gamma scan data includes the gamma scan point ID, date and time, location coordinates, and bare detector gamma cpm. The scan data was exported from the data logger and the bare detector cpm were converted to equivalent Ra-226 estimate using the Site-specific correlation (Ra-226 pCi/g = 0.0005 x CPM)-7.3228 $R^2$ = 0.97) (2020 Work Plan). The scan data was mapped using mapping software, arranged in color coded ranges and then reviewed to identify areas that exceeded the IL. The color-coded range was structured to include the 6.8 pCi/g Ra-226 IL as shown in Figure 2. The characterization gamma scan survey included approximately 3,810 gamma scan data points within the TP characterization area. The gamma scan data was exported from the scan system data logger into an Excel file. The detector cpm was converted into equivalent estimated surface soil Ra-226 concentration in pCi/g using the Site-specific correlation for bare detectors as discussed in Section 4.5 of the 2020 Work Plan. A typical gamma scan data export table from the scan system data logger is shown in Table 1. Gamma scan survey data for this characterization are provided in an electronic file.

Thirty seven data point locations were selected within the Treatment Ponds 4, 5, 6, 7 and 8 characterization area based on surface gamma scan survey results and twelve data point locations were selected in the Treatment Pond 1 characterization area as described above, totaling in forty nine data point locations. One-minute static gamma radiation surveys were performed prior to collecting a soil sample at each data point location using a collimated 2x2 NaI detector. The survey data were recorded on Static Gamma Radiation Survey Forms, which are included in Appendix A. A Site-specific correlation for a 2x2 NaI 0.5-inch thick lead collimated detector was previously performed during the August 2023 Soil Radiologic Characterization. This correlation regression yielded an equation of Ra-226 = (cpm x 0.0016) – 8.41 with an acceptable $R^2$ value of 0.83. The collimated detector measurements were converted to soil Ra-226

concentrations using this correlation equation. The static gamma survey results are summarized in Table 2.

Treatment pond concrete structures located within the TPRC areas were surveyed by collecting a one minute collimated detector static gamma count on the intact structure walls. The static gamma survey was conducted with the collimated detector housing at contact with the concrete surface, which located the detector at 1.75 inches from the concrete surface. The results of the concrete surveys are included in Appendix B. In order to convert the collimated detector static survey results in cpm to the Ra-226 IL in pCi/g, the 2x2 NaI collimated detector was calibrated for the same survey geometry at the Department of Energy (DOE) Grants concrete calibration Pad. The calibration is included in Appendix C. The calibration indicates a level of 7,200 cpm for the 0.5 inch thick lead collimated detector at contact would be equivalent to the 6.8 pCi/g Ra-226 IL in concrete.

### 4.2 Soil Sampling and Ex-Situ Gamma Radiation Soil Screening

Soil sampling and on-Site ex-situ gamma radiation soil screening were performed from November 2, 2023, through April 29, 2024. These methods were used to estimate surface and subsurface soil Ra-226 contamination exceeding the IL at data point locations within the TPRC areas. The ex-situ gamma radiation soil screening was conducted to provide a real-time estimate of Ra-226 concentrations in soil samples. This method is more reliable than in-situ direct gamma radiation level measurements and allows for more certain real-time Ra-226 concentration assessments. The on-Site ex-situ soil screening method consists of selectively measuring the 609 KeV region gamma radiations of Bi-214, a decay product of Ra-226. A single channel analyzer (Ludlum L2221) integrated with a Ludlum 44-20 3x3 NaI scintillation detector was used to measure the 609 keV energy peak region of Bi-214. The soil sample was placed around the plastic lined detector in a heavily lead shielded counting chamber. The heavily shielded counting chamber lowers the system background counts, thus improving the system's minimum detectable concentration (MDC). A reference soil with the Ra-226 concentration of 6.6 pCi/g, comparable to the 6.8 pCi/g IL, was prepared and was used for soil screening during this characterization. The 6.6 pCi/g reference soil provides a conservative estimate of Ra-226 concentration in samples below the IL.

A total of 49 data point locations were selected for this TPRC, shown in Figure 2. Thirty seven data point locations were selected within the Treatment Pond 4, 5, 6, 7 and 8 characterization areas. The surface gamma scan indicated that no significant gamma shine was observed within these characterization areas. As a result, surface (0 to 6 inches) soil samples were not collected at the data points within this characterization area. The surface soil Ra-226 level was determined using the 0.5 inch thick collimated detector static gamma survey at these 37 data point locations. A one minute collimated detector static gamma survey provides a significantly higher certainty for a data point survey and the collimator mitigates any low level lateral gamma radiation shine from any nearby hot spots. A one minute collimated static gamma survey and both surface and subsurface soil samples were collected at the remaining twelve data point locations, which are all located within the Treatment Pond 1 characterization area.

Soil samples were collected from each of the 49 data point locations. The number and depth of the samples at each data point location varied depending upon location and soil screening results. At the 37 data points from the Treatment Pond 4, 5, 6, 7 and 8 characterization areas, a subsurface (6-12 inch) soil sample was collected, and ex-situ soil gamma screened. At five data point locations in this characterization area, TP-5B, TP-11, TP-15B, TP-16B and TP-21, a subsurface soil sample at a depth of 1-2 feet was collected and ex-situ soil screened since the 6-12 inch subsurface sample soil screening result was above the IL. At location TP-5B, an additional subsurface soil sample at a depth of 2-3 feet was collected since the 1-2 feet subsurface sample screening result was 6.0 pCi/g, near the IL. No additional subsurface soil samples were necessary at these locations. At each of the remaining 12 data points located in the Treatment Pond 1 characterization area, a surface and a subsurface (6 – 12") soil sample was collected, and ex-situ soil screened. At three data points located on the pond dike crests, TP-39, TP-41 and TP-46, the surface soil sample ex-situ soil screening results were above the IL. The 6-12 inch subsurface soil sample ex-situ soil screening results were above the IL in only one data point location, TP-36. The 1-2 feet subsurface soil sample ex-situ soil screening results at TP-36 was below the IL. No additional subsurface soils samples were necessary at these locations.

A backhoe was used to excavate a trench at each selected data point location for subsurface soil sample collection. The trenches were excavated in approximately 6 to 12 inches depth intervals. At each interval, a subsurface soil sample was collected from the base of the excavation for ex-situ soil screening. Stainless steel sampling trowels were used to collect all of the soil samples. The excavation continued until on-Site ex-situ soil screening indicated Ra-226 concentrations below the 6.8 pCi/g IL. The soil sample logs and the field soil screening forms are included in Appendix A. The soil ex-situ gamma screening data is summarized in Table 3, which includes Ra-226 concentrations of the samples relative to the 6.8 pCi/g IL.

Although the primary objective of the ex-situ gamma radiation soil screening was to determine the Ra-226 concentrations above or below the 6.8 pCi/g IL, Ra-226 concentrations were estimated in all soil samples collected and screened. A calibration/correlation of the ex-situ soil screening system was performed using a 6.6 pCi/g, a 25 pCi/g and a 50 pCi/g reference soil. This correlation is included in Appendix C. The estimated Ra-226 concentration of the subsurface soil samples determined using this correlation are included in Tables 3 and 4.

A total of nine, including one field quality assurance/quality check (QA/QC) duplicate, soil samples that were ex-situ soil screened on-Site were sent to an offsite vendor laboratory, Energy Laboratories, in Casper, WY. These soil samples were analyzed for Ra-226 using EPA Method 901.1 (modified for soil matrix) for the confirmation of the on-Site ex-situ soil screening results. The laboratory results report is included in Appendix D and are summarized in Table 3. As shown in the table, the estimated Ra-226 levels determined by the on-Site ex-situ soil screening are comparable with the laboratory Ra-226 results, specifically in regard to determining the Ra-226 levels above or below the IL.

### 4.3 Treatment Pond 1 Area Characterization Summary

In addition to subsurface soil samples, surface soil samples were collected at data points from within the Treatment Pond 1 characterization area to confirm the static gamma survey with a collimated detector, which indicated that the surface soil may not be elevated, as indicated by the 2020 bare detector surface soil gamma scan. As outlined in Tables 3 and 4, the soil screening results show that the surface and subsurface (6-12") soil Ra-226 levels are below the 6.8 pCi/g IL in all six samples located on the pond bottom in Treatment Pond 1. The surface and subsurface (6-12 inch) soil sample at location TP-35, which was collected from the base of a previously excavated area from the north dike, and the surface and subsurface (6-12 inch) soil sample at location TP-45, which was collected from the east dike crest, show Ra-226 levels below the 6.8 pCi/g IL. The ex-situ soil screening results show that samples collected from the crests of the dikes at four data point locations (TP-36, TP-39, TP-41 and TP- 46) the Ra-226 levels exceed the IL. Similar to TP-35, data point TP-41 was located at the base of a previous excavation. The subsurface soil (6-12 inch) Ra-226 levels are below the IL at all data point locations except for one location, TP-36. The screening results show the Ra-226 level at TP-36 in the 6-12 inch subsurface soil sample at 10.4 pCi/g, which is above the IL, and the 1-2 feet subsurface soil sample showed the Ra-226 level below the IL at 2.3 pCi/g. As shown in Figure 3, surface soil in the Treatment Pond 1 dikes exceeded the IL in some areas, but the subsurface soil is generally below the IL.

A one minute collimated detector static gamma survey was conducted on the concrete structure within the Treatment Pond 1 characterization area. The concrete structure was designated CS-10 and is located on the western dike inside slope. The gamma survey shows radiation cpm levels ranging from 9,408 to 25,471 cpm, above the 6.8 pCi/g Ra-226 IL equivalent of 7,200 cpm at all 7 survey points selected withing the concrete structure. Portions of the elevated gamma cpm levels may be due to apparent waste rock material near and surrounding the concrete structure, and from concrete surface staining from the historic retention of mine wastewater and sediments. A gamma radiation level of 90,000 cpm was observed in the bottom of the concrete sump, likely due to the remaining layer of mine waste sediments and soil. Further direct radiation surveys of the concrete structure in place may not be effective. Removal of the concrete structures and radiation surveys of the underlying soil and sampling and surveying of the concrete may provide a better understanding of the Ra-226 levels within the concrete structure.

### 4.4 Treatment Pond 4, 5, 6 and 7 Area Characterization Summary

Because lateral gamma radiation shine was not a significant concern at these ponds, the surface soil (0-6 inch) Ra-226 levels were determined by a collimated detector one minute gamma static survey. As shown in Table 2, Table 4, and Figure 2, the surface static gamma survey results show the surface soil (0-6 inch) Ra-226 level in Treatment Pond 4, 5, 6 and 7 pond bottoms are below the IL, except for areas that are down gradient of the concrete structures and at a few isolated areas of elevated gamma radiation levels, likely remnants from previous removal efforts. The elevated surface static gamma levels near the concrete structures appear to be due to contaminated sediment in the concrete structure sumps and from apparent

mine waste material around the structures. The soil along the north dike crest of Treatment Pond 4 appears to be generally below the IL. The surface soil along the east and west dike crests are generally above the IL. The subsurface soil along the east and west dike crests are generally below the IL, except for the 6-12 inch subsurface sample at TP-11. Ex-situ soil screening results from the 6-12 inch subsurface sample at TP-11 of 64.4 pCi/g is likely due to apparent mine waste rock visible in the area. The Ra-226 levels in the subsequent 1–2 feet subsurface soil sample at TP-11 is below the IL. The surface soil on the south dike crest of Treatment Pond 4 appears to be below the IL, except near the concrete structure. The soil on the west dike outside slopes and crests of Treatment Pond 5, 6 and 7 are generally below the IL, except near the concrete structures. The surface soil on the east dike crest of Treatment Pond 5 is above the IL at various isolated locations, shown in Figures 2 and 3.

One minute collimated detector static gamma surveys conducted at nine concrete structures, shown in Figure 1, located on the dike inside slopes and/or crests at Treatment Pond 4, 5, 6, and 7 show gamma radiation levels ranging from 5,500 cpm to 45,600 cpm. As stated previously, the IL equivalent cpm for the concrete survey is 7,200 cpm. Portions of the elevated gamma cpm levels may be due to apparent waste rock material near and surrounding the concrete structure, and from concrete surface staining from the historic retention of mine wastewater and sediments. Mine waste sediments were also observed inside all the concrete structure sumps, which showed elevated gamma survey readings of up to 31,000 cpm. The concrete structure static gamma survey forms are included in Appendix B. In general, the majority of the concrete comprising the structures are likely to be below the IL, but it will be difficult to assess by gamma radiation surveys as concrete surface staining from the retention of mine waste water and sediments and apparent waste rock material near and surrounding the concrete structure are still present. Further direct radiation surveys of the concrete structure in place may not be effective.

Removal of the concrete structures and radiation surveys of the underlying soil and sampling and surveying of the concrete may provide a better understanding of the Ra-226 levels within the concrete structure. Several random pieces of the demolished concrete structures were surveyed for gamma radiation. The demolished concrete structure pieces are piled in fairly low gamma shine area south of Treatment Pond 7. The results, included in Appendix B, show all pieces surveyed were below the 7200 cpm IL, which supports the assumption that the sediments and apparent waste rock material near and surrounding the concrete structures may be impacting the direct gamma survey of the in-place concrete structures.

### 4.5 Treatment Pond 8 Area Characterization Summary

As shown in Table 2, Table 4, Figure 2 and 3, the surface static gamma survey results show the surface soil (0-6 inch) Ra-226 level in the bottom of Treatment Pond 8 is below the IL, except in a small isolated area at data point TP-6, which is estimated by ex-situ soil screening at 9 pCi/g. The 6–12 inch subsurface soil sample at TP-6 showed Ra-226 level at 3.1 pCi/g, well below the IL. Surface soil Ra-226 levels in portions of the south and west dike slopes and crests are above the IL. Ra-226 in the subsurface soil at these locations are below the IL. Elevated surface gamma scans with a bare detector along the east dike crest and outside

slope appear to be mostly due to lateral gamma radiation shine from adjacent areas outside of the Treatment Pond 8 characterization area.

### 4.6 Borrow Area A Soil Piles

Two soil piles located in the East Borrow area were sampled to estimate Ra-226 levels relative to the IL. Soil in these piles apparently came from the mine water treatment ponds. Pile 1 contained shrub/wood debris and treatment pond waste residue. Pile 2 contained fine treatment pond waste residue along with pieces of synthetic liner. Gamma exposure rates were measured at several locations on each pile. Exposure rates on pile 1 ranged from 100 to 200 uR/hr, and ranged from 100 to 300 uR/hr on Pile 2. A five-point composite soil sample was collected from both the surface and from within Pile 1. A soil sample was not collected from Pile 2 because the gamma exposure rate measurements indicated Ra-226 levels significantly above the IL and the fine pond waste residue on the surface of the pile posed airborne radiation safety concerns and the spread of contamination in the area due to windy conditions. As shown in Table 3, ex-situ soil gamma screening of the samples from Pile 1 indicates Ra-226 levels significantly above the IL.

## 5.0 Soil Sampling and Analysis

Soil samples from the Treatment Pond areas collected for on-Site ex-situ gamma radiation soil screening were collected consistent with the 2020 Work Plan. Field QA/QC duplicate samples were split at a frequency of 10% of the total number of soil samples collected. A total of 67 surface and subsurface soil samples were collected during this characterization. Field sampling equipment used for soil sampling included: stainless steel scoops, bowls, and spoons that were decontaminated between sample locations. The soil sampling equipment decontamination was conducted by brushing off loose visible soil and wiped with clean towels. Excavator buckets were cleaned by removing any loose, visible soil. Any soils excavated from the test pits were returned to the test pit excavations from which the soil came. Personal protection equipment (PPE), such as gloves, were brushed off and scanned for residual contamination and were disposed of.

Surface and subsurface soil samples were analyzed by on-Site ex-situ gamma radiation soil screening (AVM SOP-4) to estimate Ra-226 concentrations. A completed Chain-of-Custody (COC) along with confirmatory soil samples were placed in labeled Ziploc bags, and packaged in a cooler with a sealed lid and shipped to Energy Laboratories, Inc for Ra-226 analysis. The soil samples were analyzed for Ra-226 with a reporting limit of 0.5 pCi/g, using EPA Method 901.1 (modified for soil matrix). The completed COCs are included with the analytical results reports in Appendix D.

## 6. 0 Quality Assurance and Quality Control Measures

QA/QC measures were implemented during this characterization to ensure that decisions were made based on data of acceptable quality. All radiologic survey instruments have been calibrated at least annually. Additionally, operational functions checks were performed on all radiologic instruments daily prior to use.

The calibration and function check documents are included in Appendix C. During this characterization, no instruments were found to be out of calibration or inoperable as indicated by the operational function checks. The instrument background measurements for bare 2x2 NaI detectors during daily operational function checks were less than 10,000 cpm as shown in Appendix C. The bare detector field of view (FOV) at 12 inches above the ground surface is conservatively assumed at an area of six feet diameter. The 2x2 NaI detector response factor is determined to be 0.0005 pCi/g/cpm from the linear regression for the Site-specific correlation included in Appendix C. Based on the above detector parameters, the Ra-226 minimum detectable concentrations (MDCs) for a scan survey at a scan speed of three feet per second, calculated using MARSSIM guidance, were less than 1.0 pCi/g, which is significantly below 50% of the 6.8 pCi/g IL. The instrument background measurements for the 0.5 inch thick lead collimated 2x2 NaI detectors during daily operational function checks were less than 3,200 cpm, as shown in Appendix C. The bare detector field of view (FOV) at 12 inches above the ground surface is conservatively assumed at an area of 1.5 feet diameter. The collimated 2x2 NaI detector response factor is determined to be 625 cpm/pCi/g from the linear regression for the Site-specific correlation included in Appendix C. Based on the above collimated detector parameters, the Ra-226 minimum detectable concentrations (MDCs) for a one minute static survey, calculated using MARSSIM guidance, was less than 0.5 pCi/g, which is significantly below 50% of the 6.8 pCi/g IL. The ex-situ soil gamma radiation screening system was calibrated prior to mobilization in the field and daily operational function checks were performed prior to use. The calibration and function check documentation are included in Appendix C. Based on the highest system background (blank) measurements from daily operational function checks and efficiency (pCi/g/cpm), the highest Ra-226 MDC for the screening system calculated was less than 1.0 pCi/g, significantly less than the 6.8 pCi/g IL. The MDCs during the supplemental characterization met the QA objective.

The QA/QC measures also included nine field QA/QC duplicate soil samples out of the 67 soil samples collected sent to the off-site vendor laboratory for analysis to confirm contamination relative to the IL levels estimated by the field ex-situ gamma radiation soil screening. The QA/QC duplicate vendor laboratory results are included in Table 3. All QA/QC sample results confirm Ra-226 concentration levels relative to the IL level determined by the field ex-situ gamma radiation soil screening. The Ra-226 concentration in QA/QC duplicate samples estimated by on-sit ex-situ gamma radiation soil screening are comparable to the off-site vendor laboratory analytical results.

# Tables

Table 1
Typical Gamma Scan Data Exported from the Scan System Data Logger

| ID | Time | Northing[1] (feet) | Easting[1] (feet) | MSL Elevation (feet) | CPM 2x2 Bare NaI Detector | Ra-226 pCi/g[2] | Zone_ID |
|---|---|---|---|---|---|---|---|
| 1 | 10/18/2023 8:12 | 1579902.54 | 2781775.10 | 7300 | 24761 | 5.06 | Treatment_Ponds |
| 2 | 10/18/2023 8:12 | 1579903.88 | 2781775.74 | 7300 | 23724 | 4.54 | Treatment_Ponds |
| 3 | 10/18/2023 8:12 | 1579904.17 | 2781778.02 | 7300 | 25456 | 5.41 | Treatment_Ponds |
| 4 | 10/18/2023 8:12 | 1579903.99 | 2781781.66 | 7300 | 25463 | 5.41 | Treatment_Ponds |
| 5 | 10/18/2023 8:12 | 1579904.34 | 2781785.64 | 7300 | 24786 | 5.07 | Treatment_Ponds |
| 6 | 10/18/2023 8:12 | 1579904.46 | 2781790.40 | 7300 | 23246 | 4.30 | Treatment_Ponds |
| 7 | 10/18/2023 8:12 | 1579903.97 | 2781795.09 | 7301 | 23822 | 4.59 | Treatment_Ponds |
| 8 | 10/18/2023 8:12 | 1579903.49 | 2781800.02 | 7300 | 25694 | 5.53 | Treatment_Ponds |
| 9 | 10/18/2023 8:12 | 1579904.14 | 2781805.18 | 7301 | 31410 | 8.39 | Treatment_Ponds |
| 10 | 10/18/2023 8:12 | 1579904.09 | 2781810.07 | 7301 | 28672 | 7.02 | Treatment_Ponds |
| 11 | 10/18/2023 8:12 | 1579904.27 | 2781814.71 | 7301 | 25935 | 5.65 | Treatment_Ponds |
| 12 | 10/18/2023 8:12 | 1579904.36 | 2781819.65 | 7301 | 26984 | 6.17 | Treatment_Ponds |
| 13 | 10/18/2023 8:12 | 1579904.09 | 2781821.94 | 7301 | 26902 | 6.13 | Treatment_Ponds |
| 14 | 10/18/2023 8:12 | 1579903.77 | 2781822.84 | 7301 | 28593 | 6.98 | Treatment_Ponds |
| 15 | 10/18/2023 8:12 | 1579903.22 | 2781827.06 | 7301 | 28036 | 6.70 | Treatment_Ponds |
| 16 | 10/18/2023 8:12 | 1579902.15 | 2781831.73 | 7302 | 27870 | 6.62 | Treatment_Ponds |
| 17 | 10/18/2023 8:12 | 1579902.11 | 2781836.90 | 7302 | 26062 | 5.71 | Treatment_Ponds |
| 18 | 10/18/2023 8:13 | 1579902.06 | 2781842.31 | 7302 | 27827 | 6.59 | Treatment_Ponds |
| 19 | 10/18/2023 8:13 | 1579903.05 | 2781848.05 | 7302 | 27534 | 6.45 | Treatment_Ponds |
| 20 | 10/18/2023 8:13 | 1579902.68 | 2781853.78 | 7302 | 25994 | 5.68 | Treatment_Ponds |
| 21 | 10/18/2023 8:13 | 1579903.18 | 2781859.71 | 7302 | 26539 | 5.95 | Treatment_Ponds |
| 22 | 10/18/2023 8:13 | 1579903.39 | 2781865.09 | 7302 | 28415 | 6.89 | Treatment_Ponds |
| 23 | 10/18/2023 8:13 | 1579903.06 | 2781874.06 | 7302 | 26264 | 5.81 | Treatment_Ponds |
| 24 | 10/18/2023 8:13 | 1579902.23 | 2781879.73 | 7303 | 23133 | 4.25 | Treatment_Ponds |
| 25 | 10/18/2023 8:13 | 1579903.30 | 2781885.83 | 7303 | 24734 | 5.05 | Treatment_Ponds |
| 26 | 10/18/2023 8:13 | 1579903.75 | 2781891.77 | 7303 | 22704 | 4.03 | Treatment_Ponds |
| 27 | 10/18/2023 8:13 | 1579903.75 | 2781897.38 | 7303 | 22324 | 3.84 | Treatment_Ponds |
| 28 | 10/18/2023 8:13 | 1579902.96 | 2781902.73 | 7303 | 20758 | 3.06 | Treatment_Ponds |
| 29 | 10/18/2023 8:13 | 1579899.92 | 2781907.85 | 7303 | 19594 | 2.48 | Treatment_Ponds |
| 30 | 10/18/2023 8:13 | 1579899.78 | 2781914.18 | 7304 | 20910 | 3.14 | Treatment_Ponds |
| 31 | 10/18/2023 8:13 | 1579900.82 | 2781919.94 | 7304 | 20171 | 2.77 | Treatment_Ponds |
| 32 | 10/18/2023 8:13 | 1579901.72 | 2781925.63 | 7304 | 22063 | 3.71 | Treatment_Ponds |
| 33 | 10/18/2023 8:13 | 1579901.53 | 2781931.45 | 7304 | 20831 | 3.10 | Treatment_Ponds |
| 34 | 10/18/2023 8:13 | 1579901.71 | 2781937.44 | 7305 | 22406 | 3.88 | Treatment_Ponds |
| 35 | 10/18/2023 8:13 | 1579904.08 | 2781942.73 | 7305 | 22237 | 3.80 | Treatment_Ponds |
| 36 | 10/18/2023 8:13 | 1579903.40 | 2781948.33 | 7305 | 21049 | 3.20 | Treatment_Ponds |
| 37 | 10/18/2023 8:13 | 1579903.70 | 2781954.27 | 7305 | 20684 | 3.02 | Treatment_Ponds |
| 38 | 10/18/2023 8:13 | 1579904.71 | 2781959.77 | 7306 | 19715 | 2.54 | Treatment_Ponds |
| 39 | 10/18/2023 8:13 | 1579904.25 | 2781965.50 | 7306 | 19402 | 2.38 | Treatment_Ponds |
| 40 | 10/18/2023 8:13 | 1579903.80 | 2781971.03 | 7306 | 19788 | 2.57 | Treatment_Ponds |

(1) projection: StatePlane NAD 1983 NM West - Feet

(2) Ra-226 pCi/g determined from surface soil gamma radiation scan using 2x2 NaI detector and Site-specific gamma radiation level (cpm) correlation

Table 2
Static Gamma Radiation Survey at Data Point/Soil Sample Locations

| Data Point ID | Treatment Pond ID | Survey Date | Data Point Coordinate NAD83 StatePlane NM West, Feet | | Static Gamma Radiation Survey Collimated (0.5" PB) 2x2 Detector | |
|---|---|---|---|---|---|---|
| | | | Northing | Easting | Static Gamma CPM | Surface Soil Static Gamma Estimated Ra-226 pCi/g |
| TP-1 | 8 | 11/13/2023 | 1581160 | 2782050 | 8154 | 4.6 |
| TP-2 | 8 | 11/13/2023 | 1581049 | 2782082 | 6452 | 1.9 |
| TP-3 | 8 | 11/13/2023 | 1581054 | 2782194 | 8391 | 5.0 |
| TP-4 | 8 | 11/13/2023 | 1581056 | 2781878 | 6148 | 1.4 |
| TP-5 | 8 | 11/13/2023 | 1581009 | 2781973 | 6414 | 1.9 |
| TP-5B | 8 | 11/13/2023 | 1580938 | 2781891 | 12872 | 12.2 |
| TP-6 | 8 | 11/13/2023 | 1580922 | 2782111 | 10909 | 9.0 |
| TP-7 | 8 | 11/13/2023 | 1580883 | 2782046 | 25660 | 32.6 |
| TP-8 | 4 | 11/13/2023 | 1580701 | 2781885 | 6271 | 1.6 |
| TP-9 | 4 | 11/13/2023 | 1580657 | 2781727 | 11168 | 9.5 |
| TP-10 | 4 | 11/13/2023 | 1580626 | 2781847 | 7220 | 3.1 |
| TP-11 | 4 | 11/13/2023 | 1580610 | 2781955 | 47231 | 67.2 |
| TP-12 | 4 | 11/13/2023 | 1580536 | 2781864 | 9564 | 6.9 |
| TP-13 | 4 | 11/13/2023 | 1580469 | 2782022 | 29197 | 38.3 |
| TP-14 | 4 | 11/13/2023 | 1580448 | 2781724 | 14340 | 14.5 |
| TP-15 | 4 | 11/13/2023 | 1580405 | 2781891 | 7949 | 4.3 |
| TP-15B | 4 | 11/13/2023 | 1580374 | 2781812 | 37940 | 52.3 |
| TP-16 | 4/5 | 11/2/2023 | 1580347 | 2781902 | 6253 | 1.6 |
| TP-16B | 5 | 11/2/2023 | 1580328 | 2781811 | 34845 | 47.3 |
| TP-17 | 5 | 11/2/2023 | 1580244 | 2781736 | 6229 | 1.6 |
| TP-18 | 5 | 11/2/2023 | 1580226 | 2782002 | 7005 | 2.8 |
| TP-19 | 5 | 11/2/2023 | 1580227 | 2782127 | 10742 | 8.8 |
| TP-20 | 5 | 11/2/2023 | 1580228 | 2781915 | 6205 | 1.5 |
| TP-21 | 5 | 11/2/2023 | 1580208 | 2781840 | 32143 | 43.0 |
| TP-22 | 5 | 11/2/2023 | 1580165 | 2781780 | 15930 | 17.1 |
| TP-23 | 5/6 | 11/1/2023 | 1580123 | 2781924 | 7359 | 3.4 |
| TP-24 | 6 | 11/1/2023 | 1580069 | 2781800 | 7873 | 4.2 |
| TP-25 | 6 | 11/1/2023 | 1580062 | 2782028 | 6629 | 2.2 |
| TP-26 | 6 | 11/1/2023 | 1580069 | 2781851 | 19833 | 23.3 |
| TP-27 | 6 | 11/1/2023 | 1580070 | 2781925 | 6839 | 2.5 |
| TP-28 | 6 | 11/2/2023 | 1580058 | 2781819 | 19305 | 22.5 |
| TP-29 | 6/7 | 11/1/2023 | 1580018 | 2781918 | 6952 | 2.7 |
| TP-30 | 7 | 11/1/2023 | 1579960 | 2781881 | 7672 | 3.9 |
| TP-31 | 7 | 11/1/2023 | 1579960 | 2781945 | 6195 | 1.5 |
| TP-32 | 7 | 11/1/2023 | 1579963 | 2781801 | 8654 | 5.4 |
| TP-33 | 7 | 11/1/2023 | 1579962 | 2782026 | 5955 | 1.1 |
| TP-34 | 7 | 11/1/2023 | 1579905 | 2781906 | 5895 | 1.0 |
| TP-35 | 1 | 4/15/2024 | 1580506 | 2782478 | 9284 | 6.4 |
| TP-36 | 1 | 4/15/2024 | 1580485 | 2782620 | 21880 | 26.6 |
| TP-37 | 1 | 4/15/2024 | 1580440 | 2782508 | 7677 | 3.9 |
| TP-38 | 1 | 4/15/2024 | 1580409 | 2782635 | 10030 | 7.6 |
| TP-39 | 1 | 4/15/2024 | 1580389 | 2782407 | 13401 | 13.0 |
| TP-40 | 1 | 4/15/2024 | 1580369 | 2782563 | 8484 | 5.2 |
| TP-41 | 1 | 4/15/2024 | 1580303 | 2782726 | 34091 | 46.1 |
| TP-42 | 1 | 4/15/2024 | 1580282 | 2782640 | 8149 | 4.6 |
| TP-43 | 1 | 4/15/2024 | 1580242 | 2782586 | 8081 | 4.5 |
| TP-44 | 1 | 4/15/2024 | 1580214 | 2782663 | 8627 | 5.4 |
| TP-45 | 1 | 4/15/2024 | 1580206 | 2782536 | 10022 | 7.6 |
| TP-46 | 1 | 4/15/2024 | 1580316 | 2782449 | 32407 | 43.4 |

# Table 3

Treatment Pond Characterization Area Soil Sample Field Ex-Situ Screening and Vendor Laboratory Results Summary

| Sample Data | | | | | | Field Soil Screening Data | | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth (ft) | Pond /Area | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | 6.6 pCi/g Ra-226 Reference Soil CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | Soil IL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| TP-1 | 6"-12" | 8 | 11/13/2023 | 1130 | Light brown/white specks | 11/16/2023 | 3000 | 1481 | 296 | 488 | 2.7 | < | - | - | - | - |
| TP-2 | 6"-12" | 8 | 11/13/2023 | 1300 | Light brown sandy | 11/16/2023 | 3000 | 1227 | 245 | 488 | 2.0 | < | - | - | - | - |
| TP-3 | 6"-12" | 8 | 11/13/2023 | 1150 | Brown packed clay | 11/16/2023 | 3000 | 1242 | 248 | 488 | 2.0 | < | - | - | - | - |
| TP-4 | 6"-12" | 8 | 11/13/2023 | 1115 | Brown packed clay | 11/16/2023 | 3000 | 1410 | 282 | 488 | 2.5 | < | - | - | - | - |
| TP-5 | 6"-12" | 8 | 11/13/2023 | 1250 | Light brown sandy | 11/16/2023 | 3000 | 1102 | 220 | 488 | 1.6 | < | - | - | - | - |
| TP-5B | 6"-12" | 8 | 11/13/2023 | 1025 | Light grey/brown silty sand | 11/16/2023 | 3000 | 4353 | 871 | 488 | 10.7 | > | - | - | - | - |
| TP-5B | 1.5'-2.0' | 8 | 11/14/2024 | 915 | Light grey/brown silty sand | 11/16/2024 | 3000 | 2676 | 535 | 488 | 6.0 | ≈ | - | - | - | - |
| TP-5B | 2'-3' | 8 | 11/14/2023 | 920 | Rocky light grey silty | 11/16/2023 | 3000 | 1928 | 386 | 488 | 3.9 | < | - | - | - | - |
| TP-5B | 3'-3.5' | 8 | 11/14/2023 | 930 | Light brown silty | 11/16/2023 | 3000 | 1251 | 250 | 488 | 2.0 | < | - | - | - | - |
| TP-6 | 6"-12" | 8 | 11/13/2023 | 1315 | Brown silty sand w/ stones | 11/16/2023 | 3000 | 1643 | 329 | 488 | 3.1 | < | - | - | - | - |
| TP-7 | 6"-12" | 8 | 11/13/2023 | 1210 | Light brown silty/loam clay | 11/16/2023 | 3000 | 1478 | 296 | 488 | 2.7 | < | - | - | - | - |
| TP-8 | 6"-12" | 4 | 11/13/2023 | 1330 | Light brown packed silty clay | 11/16/2023 | 3000 | 1341 | 268 | 488 | 2.3 | < | - | - | - | - |
| TP-9 | 6"-12" | 4 | 11/14/2023 | 755 | Light brown packed silty clay | 11/16/2023 | 3000 | 1361 | 272 | 488 | 2.3 | < | - | - | - | - |
| TP-10 | 6"-12" | 4 | 11/14/2023 | 900 | Brown silty loam | 11/16/2023 | 3000 | 1153 | 231 | 488 | 1.8 | < | - | - | - | - |
| TP-11 | 6"-12" | 4 | 11/13/2023 | 1345 | Light brown/white specks | 11/16/2023 | 3000 | 23511 | 4702 | 488 | 64.4 | > | x | 61.5 | 1.4 | 0.7 |
| TP-11 | 1.5'-2' | 4 | 11/16/2023 | 1105 | Light brown packed silty clay | 11/16/2023 | 3000 | 1439 | 288 | 488 | 2.6 | < | x | 1.1 | 0.1 | 0.1 |
| TP-12 | 6"-12" | 4 | 11/14/2023 | 850 | Brown packed clay & silty | 11/16/2023 | 3000 | 1320 | 264 | 488 | 2.2 | < | - | - | - | - |
| TP-13 | 6"-12" | 4 | 11/13/2023 | 1405 | Light brown silty sand | 11/16/2023 | 3000 | 1389 | 278 | 488 | 2.4 | < | - | - | - | - |
| TP-14 | 6"-12" | 4 | 11/14/2023 | 810 | Light brown/white specks | 11/16/2023 | 3000 | 1388 | 278 | 488 | 2.4 | < | - | - | - | - |
| TP-15 | 6"-12" | 4 | 11/14/2023 | 835 | Light brown sandy | 11/16/2023 | 3000 | 1120 | 224 | 488 | 1.7 | < | - | - | - | - |
| TP-15B | 6"-12" | 4 | 11/14/2023 | 825 | Brown silty with cobble | 11/16/2023 | 3000 | 7551 | 1510 | 488 | 19.7 | > | x | 15.2 | 0.5 | 0.3 |
| TP-15B | 1'-1.5' | 4 | 11/16/2023 | 1135 | Light brown sandy | 11/16/2023 | 3000 | 1362 | 272 | 488 | 2.4 | < | x | 1.2 | 0.2 | 0.2 |
| TP-16 | 6"-12" | 4/5 | 11/7/2023 | 1225 | Brown silty clay | 11/8/2023 | 3000 | 1321 | 264 | 541 | 2.2 | < | - | - | - | - |
| TP-16B | 6"-12" | 5 | 11/7/2023 | 1048 | Brown hardpack silty | 11/8/2023 | 3000 | 3782 | 756 | 541 | 9.1 | > | - | - | - | - |
| TP-16B | 1'-1.5' | 5 | 11/16/2023 | 1150 | Brown hardpack silty clay | 11/16/2023 | 3000 | 1960 | 392 | 488 | 4.0 | < | - | - | - | - |
| TP-17 | 6"-12" | 5 | 11/2/2023 | 1135 | Light brown sandy/silty | 11/8/2023 | 3000 | 1373 | 275 | 541 | 2.4 | < | - | - | - | - |
| TP-18 | 6"-12" | 5 | 11/7/2023 | 1000 | Light brown sandy/silty | 11/8/2023 | 3000 | 1191 | 238 | 541 | 1.9 | < | - | - | - | - |
| TP-19 | 6"-12" | 5 | 11/2/2023 | 1340 | Light brown hardpack silty | 11/8/2023 | 3000 | 1463 | 293 | 541 | 2.6 | < | - | - | - | - |
| TP-20 | 6"-12" | 5 | 11/7/2023 | 1010 | Dark brown silty/clay | 11/8/2023 | 3000 | 1164 | 233 | 541 | 1.8 | < | - | - | - | - |
| TP-21 | 6"-12" | 5 | 11/7/2023 | 1025 | Brown silty clay | 11/8/2023 | 2716 | 8363 | 1673 | 541 | 22.0 | > | - | - | - | - |
| TP-21 | 1'-1.5' | 5 | 11/16/2023 | 1205 | Brown silty clay | 11/16/2023 | 3000 | 1440 | 288 | 488 | 2.6 | < | - | - | - | - |
| TP-22 | 6"-12" | 5 | 11/7/2023 | 1040 | Light brown sandy/silty | 11/8/2023 | 3000 | 1186 | 237 | 541 | 1.9 | < | - | - | - | - |
| TP-23 | 6"-12" | 5/6 | 11/2/2023 | 1330 | Brown silty loam, thin clay | 11/8/2023 | 3000 | 1314 | 263 | 541 | 2.2 | < | - | - | - | - |
| TP-24 | 6"-12" | 6 | 11/2/2023 | 1115 | Brown loamy clay | 11/8/2023 | 3000 | 1218 | 244 | 541 | 1.9 | < | - | - | - | - |
| TP-25 | 6"-12" | 6 | 11/2/2023 | 1310 | Light brown sandy | 11/8/2023 | 3000 | 1231 | 246 | 541 | 2.0 | < | - | - | - | - |
| TP-26 | 6"-12" | 6 | 11/7/2023 | 1210 | Brown silty packed, specks rock | 11/8/2023 | 3000 | 1213 | 243 | 541 | 1.9 | < | - | - | - | - |
| TP-27 | 6"-12" | 6 | 11/7/2023 | 1150 | Light brown sandy | 11/8/2023 | 3000 | 1053 | 211 | 541 | 1.5 | < | - | - | - | - |
| TP-28 | 6"-12" | 6 | 11/2/2023 | 1125 | Light brown sandy/silty | 11/8/2023 | 3000 | 1305 | 261 | 541 | 2.2 | < | - | - | - | - |

Table 3 (cont.)

Treatment Pond Characterization Area Soil Sample Field Ex-Situ Screening and Vendor Laboratory Results Summary

| Sample Data | | | | | | Field Soil Screening Data | | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth (ft) | Pond /Area | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | 6.6 pCi/g Ra-226 Reference Soil CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | Soil IL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| TP-29 | 6"-12" | 6/7 | 11/7/2023 | 845 | Light brown sandy/silty | 11/8/2023 | 3000 | 1302 | 260 | 541 | 2.2 | < | - | - | - | - |
| TP-30 | 6"-12" | 7 | 11/7/2023 | 901 | Dark brown silty/clay | 11/8/2023 | 3000 | 1367 | 273 | 541 | 2.4 | < | - | - | - | - |
| TP-31 | 6"-12" | 7 | 11/7/2023 | 915 | Light brown sandy/silty | 11/8/2023 | 3000 | 1267 | 253 | 541 | 2.1 | < | - | - | - | - |
| TP-32 | 6"-12" | 7 | 11/2/2023 | 1103 | Brown loamy clay | 11/8/2023 | 3000 | 1278 | 256 | 541 | 2.1 | < | - | - | - | - |
| TP-33 | 6"-12" | 7 | 11/2/2023 | 1255 | Light brown sandy | 11/8/2023 | 3000 | 1419 | 284 | 541 | 2.5 | < | - | - | - | - |
| TP-34 | 6"-12" | 7 | 11/2/2023 | 1245 | Light brown sandy/silty | 11/8/2023 | 3000 | 1332 | 266 | 541 | 2.3 | < | - | - | - | - |
| TP-35 | 0-6" | 1 | 4/15/2024 | 950 | Light brown loamy/silty clay | 4/17/2024 | 3000 | 1774 | 355 | 494 | 3.5 | < | - | - | - | - |
| TP-35 | 6"-12" | 1 | 4/16/2024 | 1050 | Brown silty clay | 4/17/2024 | 3000 | 954 | 191 | 494 | 1.2 | < | - | - | - | - |
| TP-36 | 0-6" | 1 | 4/16/2024 | 840 | Light brown loamy/silty clay | 4/17/2024 | 3000 | 2684 | 537 | 494 | 6.1 | ≈ | - | - | - | - |
| TP-36 | 6"-12" | 1 | 4/16/2024 | 1100 | light brown silty clay w/ grey rocks | 4/17/2024 | 3000 | 4247 | 849 | 494 | 10.4 | > | x | 8.8 | 0.5 | 0.3 |
| TP-36 | 1'-2' | 1 | 4/17/2024 | 1120 | Light brown silty/sandy clay | 4/17/2024 | 3000 | 1352 | 270 | 494 | 2.3 | < | x | 0.7 | 0.2 | 0.2 |
| TP-37 | 0-6" | 1 | 4/16/2024 | 820 | Dark brown silty/sandy clay | 4/17/2024 | 3000 | 1145 | 229 | 494 | 1.7 | < | - | - | - | - |
| TP-37 | 6"-12" | 1 | 4/16/2024 | 1300 | Dark brown clay w/ small rock | 4/17/2024 | 3000 | 1153 | 231 | 494 | 1.8 | < | - | - | - | - |
| TP-38 | 0-6" | 1 | 4/16/2024 | 830 | Light brown loamy/silty clay | 4/17/2024 | 3000 | 2196 | 439 | 494 | 4.7 | < | - | - | - | - |
| TP-38 | 6"-12" | 1 | 4/16/2024 | 1215 | Brown silty/sandy clay w/ roots | 4/17/2024 | 3000 | 1067 | 213 | 494 | 1.5 | < | - | - | - | - |
| TP-39 | 0-6" | 1 | 4/16/2024 | 910 | Light brown loamy/silty clay | 4/17/2024 | 3000 | 4898 | 980 | 494 | 12.3 | > | - | - | - | - |
| TP-39 | 6"-12" | 1 | 4/16/2024 | 1035 | Brown silty clay w/ roots | 4/17/2024 | 3000 | 1505 | 301 | 494 | 2.8 | < | - | - | - | - |
| TP-40 | 0-6" | 1 | 4/15/2024 | 945 | Light brown loamy/silty clay | 4/17/2024 | 3000 | 1106 | 221 | 494 | 1.6 | < | - | - | - | - |
| TP-40 | 6"-12" | 1 | 4/16/2024 | 1250 | Light brown silty/sandy clay | 4/17/2024 | 3000 | 1140 | 228 | 494 | 1.7 | < | - | - | - | - |
| TP-41 | 0-6" | 1 | 4/16/2024 | 845 | Light brown loamy/silty clay | 4/17/2024 | 2800 | 12188 | 2612 | 494 | 35.1 | > | x | 43.5 | 1.1 | 0.5 |
| TP-41 | 6"-12" | 1 | 4/16/2024 | 1115 | Light brown silty clay | 4/17/2024 | 2700 | 1243 | 276 | 494 | 2.4 | < | x | 1.9 | 0.3 | 0.3 |
| TP-42 | 0-6" | 1 | 4/15/2024 | 930 | Light brown loamy/silty clay | 4/17/2024 | 2936 | 1171 | 239 | 494 | 1.9 | < | - | - | - | - |
| TP-42 | 6"-12" | 1 | 4/16/2024 | 1240 | Brown silty/sandy clay | 4/17/2024 | 3000 | 975 | 195 | 494 | 1.3 | < | - | - | - | - |
| TP-43 | 0-6" | 1 | 4/15/2024 | 940 | Light brown loamy/silty clay | 4/17/2024 | 3000 | 1165 | 233 | 494 | 1.8 | < | - | - | - | - |
| TP-43 | 6"-12" | 1 | 4/16/2024 | 1230 | light brown silty clay w/ roots | 4/17/2024 | 3000 | 1101 | 220 | 494 | 1.6 | < | - | - | - | - |
| TP-44 | 0-6" | 1 | 4/15/2024 | 915 | Light brown loamy/silty clay | 4/17/2024 | 3000 | 1224 | 245 | 494 | 2.0 | < | - | - | - | - |
| TP-44 | 6"-12" | 1 | 4/16/2024 | 1125 | Light brown loamy/silty clay | 4/17/2024 | 3000 | 1101 | 220 | 494 | 1.6 | < | - | - | - | - |
| TP-45 | 0-6" | 1 | 4/16/2024 | 850 | Light brown loamy/silty clay | 4/17/2024 | 2700 | 1558 | 346 | 494 | 3.4 | < | - | - | - | - |
| TP-45 | 6"-12" | 1 | 4/16/2024 | 1015 | Brown silty clay | 4/17/2024 | 3000 | 1109 | 222 | 494 | 1.6 | < | - | - | - | - |
| TP-46 | 0-6" | 1 | 4/16/2024 | 900 | Light brown loamy/silty clay w/ grey rock | 4/17/2024 | 3000 | 21504 | 4301 | 494 | 58.7 | > | - | - | - | - |
| TP-46 | 6"-12" | 1 | 4/16/2024 | 1025 | Dark brown silty/clay w/ small rocks | 4/17/2024 | 3000 | 1766 | 353 | 494 | 3.5 | < | x | 2.3 | 0.3 | 0.2 |
| EBP-1 | Surface | East Borrow | 4/30/2024 | 830 | Composite from surface of pile | 4/30/2024 | 3000 | 16930 | 3386 | 533 | 45.9 | > | - | - | - | - |
| EBP-1 | Internal | East Borrow | 4/30/2024 | 853 | Composite from various depths from inside pile | 4/30/2024 | 3000 | 14135 | 2827 | 533 | 38.1 | > | - | - | - | - |

Table 4
Treatment Pond Surface and Subsurface Soil Ra-226 Level Summary

| Data Point ID | Treatment Pond ID | Static Gamma Estimated Ra-226 pCi/g 0-6" (surface) Soil | Ex-Situ Soil Screening Estimated Ra-226 pCi/g | | | |
|---|---|---|---|---|---|---|
| | | | 0-6" Soil (surface) | 6"-12" Soil | 1'-2' Soil | 2'-3' Soil |
| TP-1 | 8 | 4.6 | - | 2.7 | - | - |
| TP-2 | 8 | 1.9 | - | 2.0 | - | - |
| TP-3 | 8 | 5.0 | - | 2.0 | - | - |
| TP-4 | 8 | 1.4 | - | 2.5 | - | - |
| TP-5 | 8 | 1.9 | - | 1.6 | - | - |
| TP-5B | 8 | 12.2 | - | 10.7 | 6.0 | 3.9 |
| TP-6 | 8 | 9.0 | - | 3.1 | - | - |
| TP-7 | 8 | 32.6 | - | 2.7 | - | - |
| TP-8 | 4 | 1.6 | - | 2.3 | - | - |
| TP-9 | 4 | 9.5 | - | 2.3 | - | - |
| TP-10 | 4 | 3.1 | - | 1.8 | - | - |
| TP-11 | 4 | 67.2 | - | 64.4 | 2.6 | - |
| TP-12 | 4 | 6.9 | - | 2.2 | - | - |
| TP-13 | 4 | 38.3 | - | 2.4 | - | - |
| TP-14 | 4 | 14.5 | - | 2.4 | - | - |
| TP-15 | 4 | 4.3 | - | 1.7 | - | - |
| TP-15B | 4 | 52.3 | - | 19.7 | 2.4 | - |
| TP-16 | 4/5 | 1.6 | - | 2.2 | - | - |
| TP-16B | 5 | 47.3 | - | 9.1 | 4.0 | - |
| TP-17 | 5 | 1.6 | - | 2.4 | - | - |
| TP-18 | 5 | 2.8 | - | 1.9 | - | - |
| TP-19 | 5 | 8.8 | - | 2.6 | - | - |
| TP-20 | 5 | 1.5 | - | 1.8 | - | - |
| TP-21 | 5 | 43.0 | - | 22 | 2.6 | - |
| TP-22 | 5 | 17.1 | - | 1.9 | - | - |
| TP-23 | 5/6 | 3.4 | - | 2.2 | - | - |
| TP-24 | 6 | 4.2 | - | 1.9 | - | - |
| TP-25 | 6 | 2.2 | - | 2 | - | - |
| TP-26 | 6 | 23.3 | - | 1.9 | - | - |
| TP-27 | 6 | 2.5 | - | 1.5 | - | - |
| TP-28 | 6 | 22.5 | - | 2.2 | - | - |
| TP-29 | 6/7 | 2.7 | - | 2.2 | - | - |
| TP-30 | 7 | 3.9 | - | 2.4 | - | - |
| TP-31 | 7 | 1.5 | - | 2.1 | - | - |
| TP-32 | 7 | 5.4 | - | 2.1 | - | - |
| TP-33 | 7 | 1.1 | - | 2.5 | - | - |
| TP-34 | 7 | 1.0 | - | 2.3 | - | - |
| TP-35 | 1 | 6.4 | 3.5 | 1.2 | - | - |
| TP-36 | 1 | 26.6 | 6.1 | 10.4 | 2.3 | - |
| TP-37 | 1 | 3.9 | 1.7 | 1.8 | - | - |
| TP-38 | 1 | 7.6 | 4.7 | 1.5 | - | - |
| TP-39 | 1 | 13.0 | 12.3 | 2.8 | - | - |
| TP-40 | 1 | 5.2 | 1.6 | 1.7 | - | - |
| TP-41 | 1 | 46.1 | 35.1 | 2.4 | - | - |
| TP-42 | 1 | 4.6 | 1.9 | 1.3 | - | - |
| TP-43 | 1 | 4.5 | 1.8 | 1.6 | - | - |
| TP-44 | 1 | 5.4 | 2.0 | 1.6 | - | - |
| TP-45 | 1 | 7.6 | 3.4 | 1.6 | - | - |
| TP-46 | 1 | 43.4 | 58.7 | 3.5 | - | - |

Note: Surface Soil Static Gamma Estimated pCi/g levels were estimated from .5" lead collimated detector static gamma measurements.

# Figures




N
W E
S

Environmental Services, Inc.

Figure 1
Mt. Taylor Mine Site
Treatment Pond Characterization
Areas and Concrete Structure Locations

**Legend**

- Concrete Structure
- North Controlled Fence
- Treatment Pond Characterization Area



0 50 100 200 300 Feet

N
W E
S

AVM Environmental Services, Inc.

# Figure 2
# Mt. Taylor Mine Site
# Treatment Ponds Characterzation Area
# Data Point Locations and
# Gamma Survey Data

**Legend**

**Estimated Ra-226**

- <1.8 pCi/g
- 1.9 - 6.8 pCi/g
- 6.9 - 10.0 pCi/g
- 10.1 - 20.0 pCi/g
- 20.1 - 30.0 pCi/g
- 30.1 - 40.0 pCi/g
- >40.1 pCi/g
- Data Point
- North Controlled Fence
- Treatment Pond Characterization Area

Note: Ra-226 pCi/g is determined from surface soil gamma radiation scan and static cpm using 2x2 NaI detector and Site specific gamma radiation level (cpm) correlation.

50 100 200 300 Feet

# Figure 3
# Mt. Taylor Mine Site
# Treatment Ponds Characterzation Area
# Estimated Depth of Contamination above the 6.8 pCi/g Ra-226 Investigation Level

AVM Environmental Services, Inc.

**Legend**

- Treatment Pond Characterization Area
- Berm Profile above the Ra-226 6.8 pCi/g Investigation Level
- 6 Inch Contamination depth above the Ra-226 6.8 pCi/g Investigation Level
- 1 ft Contamination depth above the Ra-226 6.8 pCi/g Investigation Level
- 1.5 ft Contamination depth above the Ra-226 6.8 pCi/g Investigation Level
- Concrete Structure
- North Controlled Fence

# Appendices

| | |
|---|---|
| Appendix A | Surface and Subsurface Contamination Field Investigation Documentation (Soil Sample Log Forms, Field Soil Sample Ex-Situ Gamma Radiation Screening Forms) |
| Appendix B | Concrete Structure Radiologic Investigation |
| Appendix C | Radiologic Instrument Calibration and Operational Function Check and Collimated Detector Correlation Documentation |
| Appendix D | Soil Sample COC and Laboratory Analytical Results Report |

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**

**Static Gamma Radiation Survey Field Form**

Instrumentation : Scaler/Ratemeter L2221 S#290801, Detector SPA-3 #30

Instrument Calibration Date: 2-19-24, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Decsription Mt Taylor Mine Site Treatment Ponds

| Survey Date/Time | Survey Point ID/Description | Survey Point Coordinate | | Gamma Radiation Reading, CPM | Comments/Notes |
|---|---|---|---|---|---|
| | | Northing | Easting | | |
| 11-13-23 | TP-1 | 1581160.23 | 2782050.33 | 8154 | |
| 11-13-23 | TP-2 | 1581048.51 | 2782082.19 | 6452 | |
| 11-13-23 | TP-3 | 1581053.56 | 2782193.53 | 8391 | |
| 11-13-23 | TP-4 | 1581056.28 | 2781877.80 | 6148 | |
| 11-13-23 | TP-5 | 1581008.60 | 2781973.38 | 6414 | |
| 11-13-23 | TP-5B | 1580937.63 | 2781890.74 | 12872 | |
| 11-13-23 | TP-6 | 1580921.93 | 2782110.62 | 10909 | |
| 11-13-23 | TP-7 | 1580883.33 | 2782045.88 | 25660 | |
| 11-13-23 | TP-8 | 1580701.01 | 2781884.91 | 6271 | |
| 11-13-23 | TP-9 | 1580657.09 | 2781726.59 | 11168 | |
| 11-13-23 | TP-10 | 1580625.66 | 2781846.72 | 7220 | |
| 11-13-23 | TP-11 | 1580609.85 | 2781954.68 | 47231 | |
| 11-13-23 | TP-12 | 1580536.13 | 2781863.94 | 9564 | |
| 11-13-23 | TP-13 | 1580469.14 | 2782022.02 | 29197 | |
| 11-13-23 | TP-14 | 1580448.27 | 2781723.76 | 14340 | |
| 11-13-23 | TP-15 | 1580405.00 | 2781891.33 | 7949 | |
| 11-13-23 | TP-15B | 1580374.22 | 2781811.70 | 37940 | |
| 11-2-23 | TP-16 | 1580347.37 | 2781901.68 | 6253 | |
| 11-2-23 | TP-16B | 1580327.56 | 2781811.01 | 34845 | |
| 11-2-23 | TP-17 | 1580244.30 | 2781736.20 | 6229 | |
| 11-2-23 | TP-18 | 1580226.28 | 2782002.49 | 7005 | |
| 11-2-23 | TP-19 | 1580226.78 | 2782127.17 | 10742 | |
| 11-2-23 | TP-20 | 1580228.47 | 2781915.38 | 6205 | |
| 11-2-23 | TP-21 | 1580207.85 | 2781839.85 | 32143 | |
| 11-2-23 | TP-22 | 1580164.80 | 2781780.30 | 15930 | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**

**Static Gamma Radiation Survey Field Form**

Instrumentation : Scaler/Ratemeter 2221 SN290801, Detector SPA-3 #30

Instrument Calibration Date: 2-19-24, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Decsription Mt. Taylor Mine Site Treatment Ponds

| Survey Date/Time | Survey Point ID/Description | Survey Point Coordinate | | Gamma Radiation Reading, CPM | Comments/Notes |
|---|---|---|---|---|---|
| | | Northing | Easting | | |
| 11-2-23 | TP-23 | 1580122.85 | 2781924.41 | 7359 | |
| 11-2-23 | TP-24 | 1580068.98 | 2781799.51 | 7873 | |
| 11-2-23 | TP-25 | 1580062.13 | 2782027.54 | 6629 | |
| 11-2-23 | TP-26 | 1580069.28 | 2781851.47 | 19835 | |
| 11-2-23 | TP-27 | 1580070.01 | 2781925.21 | 6839 | |
| 11-2-23 | TP-28 | 1580057.59 | 2781819.32 | 19305 | |
| 11-2-23 | TP-29 | 1580017.82 | 2781917.62 | 6952 | |
| 11-2-23 | TP-30 | 1579960.47 | 2781880.55 | 7672 | |
| 11-2-23 | TP-31 | 1579960.46 | 2781944.76 | 6195 | |
| 11-2-23 | TP-32 | 1579963.04 | 2781801.01 | 8654 | |
| 11-2-23 | TP-33 | 1579962.22 | 2782025.52 | 5455 | |
| 4-10-24 | TP-34 | 1579905.48 | 2781906.24 | 5895 | |
| 4-10-24 | TP-35 | 1580505.83 | 2782477.73 | 9284 | |
| 4-10-24 | TP-36 | 1580484.67 | 2782620.22 | 21880 | |
| 4-10-24 | TP-37 | 1580439.62 | 2782507.78 | 7677 | |
| 4-10-24 | TP-38 | 1580408.58 | 2782634.69 | 10030 | |
| 4-10-24 | TP-39 | 1580389.39 | 2782406.73 | 13401 | |
| 4-10-24 | TP-40 | 1580369.24 | 2782563.39 | 8484 | |
| 4-10-24 | TP-41 | 1580303.17 | 2782725.85 | 34091 | |
| 4-10-24 | TP-42 | 1580282.42 | 2782639.66 | 8149 | |
| 4-10-24 | TP-43 | 1580242.16 | 2782585.55 | 8081 | |
| 4-10-24 | TP-44 | 1580214.10 | 2782662.94 | 8627 | |
| 4-10-24 | TP-45 | 1580205.92 | 2782535.59 | 10022 | |
| 4-10-24 | TP-46 | 1580316.03 | 2782448.56 | 32407 | |
| | | | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| TP-32 | 11-2-23 @1103 | 6"-12" | Brown Clay/loamy | |
| TP-24 | 11-2-23 @1115 | 6"-12" | Brow Clay/loamy Roots | |
| TP-28 | 11-2-23 @1125 | 6"-12" | light brown Sandy/Silty Roots | |
| TP-17 | 11-2-23 @1135 | 6"-12" | light brown Sandy/silty Roots | |
| TP-34 | 11-2-23 @1245 | 6"-12" | light brown Sandy/silty Roots | |
| TP-33 | 11-2-23 @1255 | 6"-12" | light brown Sandy Roots | |
| TP-25 | 11-2-23 @1310 | 6"-12" | light brown Sandy Roots | |
| TP-23 | 11-2-23 @1330 | 6"-12" | Brown Silty loam - Small layer of Dark Clay | |
| TP-19 | 11-2-23 @1340 | 6"-12" | light brown hardpack silty Roots | |
| TP-29 | 11-7-23 @845 | 6"-12" | light brown Silty/Sandy Roots | |
| TP-30 | 11-7-23 @901 | 6"-12" | Dark Brown Clay & Silt Sandstone Refusal @ 28" | |
| TP-31 | 11-7-23 @915 | 6"-12" | light brown Silty Sand Sandstone Bed @16" | |
| TP-18 | 11-7-23 @1000 | 6"-12" | light brown silty Sand | |
| TP-20 | 11-7-23 @1010 | 6"-12" | Dark brown Silty/Sand & Clay | |
| TP-21 | 11-7-23 @1025 | 6"-12" | Brown Silty Clay | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| TP-22 | 11-7-23 @1040 | 6"-12" | light Brown Silty Sand | |
| TP-16B | 11-7-23 @1048 | 6"-12" | Brown hardpack Silty | |
| TP-27 | 11-7-23 @1150 | 6"-12" | light brown Sandy Sandstone @1.4' | |
| TP-26 | 11-7-23 @1210 | 6"-12" | Brown Silty/Rock speckled w/ white Soil | |
| TP-16 | 11-7-23 @1225 | 6"-12" | Brown Clay Silty Hard Rock | |
| TP-5b | 11-13-23 @1025 | 6"-12" | Light Grey/ brown silty Sand gravel | |
| TP-4 | 11-13-23 @1115 | 6"-12" | Brown Packed Clay | |
| TP-1 | 11-13-23 @1130 | 6"-12" | light brown/grey-white limestone | plastic debris |
| TP-3 | 11-13-23 @1150 | 6"-12" | Brown Packed Clay | |
| TP-7 | 11-13-23 @1210 | 6"-12" | light brown Silty/loamy Clay | |
| TP-5 | 11-13-23 @1250 | 6"-12" | light brown Sandy | |
| TP-2 | 11-13-23 @1300 | 6"-12" | light brown Sandy | |
| TP-6 | 11-13-23 @1315 | 6"-12" | brown Silty Sand w/stones | |
| TP-8 | 11-13-23 @1330 | 6"-12" | light brown Packed Silt clay | |
| TP-11 | 11-13-23 @1345 | 6"-12" | light brown/white Silty | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| TP-13 | 11-13-23 @1405 | 6"-12" | light brown Silty Sand | |
| TP-9 | 11-14-23 @755 | 6"-12" | Light brown Packed Silty Clay | |
| TP-14 | 11-14-23 @810 | 6"-12" | light brown Packed white specks 1" Rock | |
| TP-15B | 11-14-23 @825 | 6"-12" | Brown Silty w/ cobble | |
| TP-15 | 11-14-23 @835 | 6"-12" | Light brown Sandy | |
| TP-12 | 11-14-23 @850 | 6"-12" | light brown packed Silty Dark brown Clay | |
| TP-10 | 11-14-23 @900 | 6"-12" | Brown Silty loamy moist | |
| TP-5B | 11-14-23 @920 | 2'-3.0' | Grey Rocky | |
| TP-5B | 11-14-23 @930 | 3'-3.5' | light brown Silty | |
| TP-11 | 11-14-23 @1105 | 1.5'-2' | light brown Packed Clay | |
| TP-11 | 11-16-23 @1112 | 2'-2.5' | light brown Packed Clay | |
| TP-15B | 11-16-23 @1135 | 1'-1.5' | light brown Sandy | |
| TP-16B | 11-16-23 @1150 | 1'-1.5' | brown Hard pack Clay | |
| TP-21 | 11-16-23 @1205 | 1'-1.5' | brown Silty Clay | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| TP-44 | 4-15-24 915 | 0-6" | light brown loam/silt/clay | |
| TP-42 | 4-15-24 930 | 0-6" | " | |
| TP-43 | 4-15-24 940 | 0-6" | " | |
| TP-40 | 4-15-24 945 | 0-6" | " | |
| TP-35 | 4-15-24 950 | 0-6" | " | |
| TP-37 | 4-16-24 820 | 0-6" | Dark brown / Sandy / silty clay | |
| TP-38 | 4-16-24 830 | 0-6" | light brown loam/silt clay | |
| TP-36 | 4-16-24 840 | 0-6" | " | |
| TP-41 | 4-16-24 845 | 0-6" | " | |
| TP-45 | 4-16-24 350 | 0-6" | " | |
| TP-46 | 4-16-24 900 | 0-6" | " Slight grey. | |
| TP-~~49~~ VP 39 | 4-16-24 910 | 0-6" | " | |
| TP-45 | 4-16-24 1015 | 6"-12" | Brown silty clay | |
| TP-46 | 4-16-24 1025 | 6"-12" | Dark brown silty clay w/ roots | |
| TP-39 | 4-16-24 1035 | 6"-12" | Brown silty clay Roots | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| TP-35 | 4-16-24 1050 | 6"-12" | Brown Silt, Clay | |
| TP-36 | 4-16-24 1100 | 6"-12" | light brown Silty Clay hardpack Grey Rocks | |
| TP-41 | 4-16-24 1115 | 6"-12" | light brown silty clay | |
| TP-44 | 4-16-24 1125 | 6"-12" | light brown loamy/silty clay | |
| TP-38 | 4-16-24 1215 | 6"-12" | Brown silty/Sandy Clay Roots | |
| TP-43 | 4-16-24 1230 | 6"-12" | light brown silty/sand clay Roots | |
| TP-42 | 4-16-24 1240 | 6"-12" | Brown Silty/Sand Clay | |
| TP-40 | 4-16-24 1250 | 6"-12" | light brown Silty Sand Clay | |
| TP-37 | 4-16-24 1300 | 6"-12" | Dark Brown Clay w Stones 3/4" | |
| TP-36 | 4-17-24 1120 | 1'-2' | light brown Sandy silty Clay hard rock | |
| TP-36 | 4-17-24 1130 | 2'-3' | " " Not hard rock | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| EBP-1 Surface | 4-30-24 830 | 0-6" | Composite Sample from surface of pile | grey material present |
| EBP-1 Internal | 4-30-24 853 | Various | Composite Sample from various depths inside of pile | " |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

AVM Environmental Services, Inc.
Field Soil Sample Gamma Radiation Screening Form
Mt. Taylor Mine Site

Instrumentation: Scaler/Ratemeter L2221 S#68782, Detector 44-20 S# 295573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: Y
Survey Area/Unit Description Mt. Taylor Mine Site

Area exposure rate: 10-12 uR/hr

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CPSM | Weight Corrected CPSM | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 11-8-23 | Blank | - | 314 | | 63 | | |
| 11-8-23 | 6.6 pCi/g Ra-226 Ref Soil | 3000 | 2707 | | 541 | | |
| 11-8-23 | TP-32 6"-12" 11-2-23 @1103 | 3000 | 1278 | | 256 | | |
| 11-8-23 | TP-24 6"-12" 11-2-23 @1115 | 3000 | 1218 | | 244 | | |
| 11-8-23 | TP-28 6"-12" 11-2-23 @1125 | 3000 | 1305 | | 261 | | |
| 11-8-23 | TP-17 6"-12" 11-2-23 @1135 | 3000 | 1373 | | 275 | | |
| 11-8-23 | TP-34 6"-12" 11-2-23 @1245 | 3000 | 1322 | | 266 | | |
| 11-8-23 | TP-33 6"-12" 11-2-23 @1255 | 3000 | 1419 | | 284 | | |
| 11-8-23 | TP-25 6"-12" 11-2-23 @1310 | 3000 | 1291 | | 258 | | |
| 11-8-23 | TP-23 6"-12" 11-2-23 @1330 | 3000 | 1314 | | 263 | | |
| 11-8-23 | TP-19 6"-12" 11-2-23 @1340 | 3000 | 1463 | | 293 | | QA/QC 5 min: 1423 |
| 11-8-23 | TP-29 6"-12" 11-7-23 @845 | 3000 | 1302 | | 260 | | |
| 11-8-23 | TP-30 6"-12" 11-7-23 @901 | 3000 | 1367 | | 273 | | |
| 11-8-23 | TP-31 6"-12" 11-7-23 @915 | 3000 | 1267 | | 253 | | |
| 11-8-23 | TP-18 6"-12" 11-7-23 @1000 | 3000 | 1191 | | 238 | | |

Technician Signature _____ Reviewed by _____

AVM Environmental Services, Inc.
Field Soil Sample Gamma Radiation Screening Form
Mt. Taylor Mine Site

Instrumentation : Scaler/Ratemeter L2221 SN 68782, Detector 44-20 SN 295573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: Y
Survey Area/Unit Description Mt. Taylor Mine Site

Area exposure rate: 10-12 uR/hr

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CPSM | Weight Corrected CPSM | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 11-8-23 | TP-20 6"-12" 11-7-23 @ 1010 | 3000 | 1164 | | 233 | | |
| 11-8-23 | TP-21 6"-12" 11-7-23 @ 1025 | 2716 | 7571 | 8363 | 1673 | | |
| 11-8-23 | TP-22 6"-12" 11-7-23 @ 1040 | 3000 | 1186 | | 237 | | |
| 11-8-23 | TP-16B 6"-12" 11-7-23 @ 1048 | 3000 | 3782 | | 756 | | |
| 11-8-23 | TP-27 6"-12" 11-7-23 @ 1150 | 3000 | 1053 | | 211 | | QA/QC cpsmin: 1052 |
| 11-8-23 | TP-26 6"-12" 11-7-23 @ 1210 | 3000 | 1213 | | 243 | | |
| 11-8-23 | TP-16 6"-12" 11-7-23 @ 1225 | 3000 | 1321 | | 264 | | |
| 11-16-23 | Blank | - | 335 | | 67 | | |
| ~~11-16-23~~ | ~~6.6 pCi/g Ref Soil~~ | ~~3000~~ | ~~335~~ | | ~~67~~ | | |
| 11-16-23 | 6.6 pCi/g Ref Soil | 3000 | 2479 | | 488 | | |
| 11-16-23 | TP-5B 6"-12" 11-13-23 @ 1025 | 3000 | 4353 | | 871 | | |
| 11-16-23 | TP-4 6"-12" 11-13-23 @ 1115 | 3000 | 1410 | | 282 | | |
| 11-16-23 | TP-1 6"-12" 11-13-23 @ 1130 | 3000 | 1481 | | 296 | | |
| 11-16-23 | TP-3 6"-12" 11-13-23 @ 1150 | 3000 | 1242 | | 248 | | |
| 11-16-23 | TP-7 6"-12" 11-13-23 @ 1210 | 3000 | 1478 | | 296 | | |

VP

Technician Signature _____, Reviewed by _____

AVM Environmental Services, Inc.
Field Soil Sample Gamma Radiation Screening Form
Mt. Taylor Mine Site

Instrumentation : Scaler/Ratemeter L2221 S#68782, Detector 44-20 S# 295523
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: Y
Survey Area/Unit Description Mt. Taylor Mine Site

Area exposure rate: 10-12 uR/hr

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CPSM | Weight Corrected CPSM | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 11-16-23 | TP-5 6"-12" 11-13-23 @ 1250 | 3000 | 1102 | | 220 | | |
| 11-16-23 | TP-2 6"-12" 11-13-23 @ 1300 | 3000 | 1227 | | 245 | | |
| 11-16-23 | TP-6 6"-12" 11-13-23 @ 1315 | 3000 | 1643 | | 329 | | |
| 11-16-23 | TP-8 6"-12" 11-13-23 @ 1330 | 3000 | 1341 | | 268 | | |
| 11-16-23 | TP-11 6"-12" 11-13-23 @ 1345 | 3000 | 23511 | | 4702 | | avac CPSM: 23785 |
| 11-16-23 | TP-13 6"-12" 11-13-23 @ 1405 | 3000 | 1389 | | 278 | | |
| 11-16-23 | TP-9 6"-12" 11-14-23 @ ~~810~~ 755 | 3000 | 1361 | | 272 | | |
| 11-16-23 | TP-14 6"-12" 11-14-23 @ 810 | 3000 | 1388 | | 278 | | |
| 11-16-23 | TP-15B 6"-12" 11-14-23 @ 825 | 3000 | 7551 | | 1510 | | |
| 11-16-23 | TP-15 6"-12" 11-14-23 @ 835 | 3000 | 1120 | | 224 | | |
| 11-16-23 | TP-12 6"-12" 11-14-23 @ 850 | 3000 | 1320 | | 264 | | |
| 11-16-23 | TP-10 6"-12" 11-14-23 @ 900 | 3000 | 1153 | | 231 | | |
| 11-16-23 | TP-5B 2'-3' 11-14-23 @ 920 | 3000 | 1928 | | 386 | | |
| 11-16-23 | TP-5B 3'-3.5' 11-14-23 @ 930 | 3000 | 1251 | | 250 | | |
| 11-16-23 | TP-11 1.5'-2' 11-16-23 @ 1105 | 3000 | 1439 | | 288 | | |

Technician Signature _____, Reviewed by _____

AVM Environmental Services, Inc.
Field Soil Sample Gamma Radiation Screening Form
Mt. Taylor Mine Site

Instrumentation : Scaler/Ratemeter L2221 S# 68782, Detector 44-20 S# 295573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: Y
Survey Area/Unit Description: Mt. Taylor Mine Site

Area exposure rate: 10-12

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 11-16-23 | TP-15B 1'-1.5' 11-16-23 @1135 | 3000 | 1362 | | 272 | | |
| 11-16-23 | TP-16B 1'-1.5' 11-16-23 @1150 | 3000 | 1960 | | 392 | | |
| 11-16-23 | TP-21 1'-1.5' 11-16-23 @1205 | 3000 | 1440 | | 288 | | |
| 11-16-23 | TP-5B 1.5'-2.0' 11-14-23 @915 | 3000 | 2676 | | 535 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

AVM Environmental Services, Inc.
Field Soil Sample Gamma Radiation Screening Form
Mt. Taylor Mine Site

Instrumentation : Scaler/Ratemeter L2221 S# 63782, Detector 44-20 S# 295573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: Y
Survey Area/Unit Description Mt. Taylor mine site

Area exposure rate: 10-12

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CPSM | Weight Corrected CPSM | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 4-17-24 | Blank | | 310 | | 62 | | |
| 4-17-24 | 66 pCi/g Ra-226 Ref Soil | 3000 | 2468 | | 494 | | |
| 4-17-24 | TP-45 6"-12" 4-16-24 @ 1015 | 3000 | 1109 | | 222 | | |
| 4-17-24 | TP-46 6"-12" 4-16-24 @ 1025 | 3000 | 1766 | | 353 | | |
| 4-17-24 | TP-39 6"-12" 4-16-24 @ 1035 | 3000 | 1505 | | 301 | | |
| 4-17-24 | TP-36 6"-12" 4-16-24 @ 1100 | 3000 | 4247 | | 849 | | |
| 4-17-24 | TP-41 6"-12" 4-16-24 @ 1115 | 2700 | 1243 | 1381 | 276 | | |
| 4-17-24 | TP-44 6"-12" 4-16-24 @ 1125 | 3000 | 1101 | | 220 | | |
| 4-17-24 | TP-38 6"-12" 4-16-24 @ 1215 | 3000 | 1067 | | 213 | | |
| 4-17-24 | TP-42 6"-12" 4-16-24 @ 1240 | 3000 | 975 | | 195 | | |
| 4-17-24 | TP-40 6"-12" 4-16-24 @ 1250 | 3000 | 1140 | | 228 | | |
| 4-17-24 | TP-37 6"-12" 4-16-24 @ 1300 | 3000 | 1153 | | 231 | | QA/QC CPSM: 1101 |
| 4-17-24 | TP-35 6"-12" 4-16-24 @ 1050 | 3000 | 954 | | 191 | | |
| 4-17-24 | TP-43 6"-12" 4-16-24 @ 1230 | 3000 | 1101 | | 220 | | |
| 4-17-24 | TP-44 0-6" 4-15-24 @ 915 | 3000 | 1224 | | 245 | | |

Technician Signature _____ Reviewed by _____

AVM Environmental Services, Inc.
Field Soil Sample Gamma Radiation Screening Form
Mt. Taylor Mine Site

Instrumentation : Scaler/Ratemeter Ludlum 2221 S#68782, Detector 44-20 S# 295573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: ✓
Survey Area/Unit Description: Mt. Taylor mine Site

Area exposure rate: 10-12

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CPSM | Weight Corrected CPSM | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 4-17-24 | TP-42 0-6" 4-15-24 @ 930 | 2936 | 1171 | 1197 | 239 | | |
| 4-17-24 | TP-43 0-6" 4-15-24 @ 940 | 3000 | 1165 | | 233 | | |
| 4-17-24 | TP-40 0-6" 4-15-24 @ 945 | 3000 | 1106 | | 221 | | |
| 4-17-24 | TP-35 0-6" 4-15-24 @ 950 | 3000 | 1774 | | 355 | | |
| 4-17-24 | TP-37 0-6" 4-16-24 @ 820 | 3000 | 1145 | | 229 | | |
| 4-17-24 | TP-38 0-6" 4-16-24 @ 830 | 3000 | 2196 | | 439 | | |
| 4-17-24 | TP-36 0-6" 4-16-24 @ 840 | 3000 | 2684 | | 537 | | QA/QC CPSM: 2673 |
| 4-17-24 | TP-41 0-6" 4-16-24 @ 845 | 2800 | 12188 | 13059 | 2612 | | |
| 4-17-24 | TP-45 0-6" 4-16-24 @ 850 | 2700 | 1558 | 1731 | 346 | | |
| 4-17-24 | TP-46 0-6" 4-16-24 @ 900 | 3000 | 21504 | | 4301 | | |
| 4-17-24 | TP-39 0-6" 4-16-24 @ 910 | 3000 | 4898 | | 980 | | |
| 4-17-24 | TP-36 1'-2' 4-17-24 @ 1120 | 3000 | 1352 | | 270 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

AVM Environmental Services, Inc.
Field Soil Sample Gamma Radiation Screening Form
Mt. Taylor Mine Site

Instrumentation : Scaler/Ratemeter 12221 S#68782, Detector 44-20 S#295573
Instrument Calibration Date: 5-10-23, Instrument Function Check Performed: Y
Survey Area/Unit Description Mt. Taylor Mine Site

Area exposure rate: 10-12 uR/hr.

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 4-30-24 | Blank | — | 327 | | 65 | | |
| 4-30-24 | 6.6 pCi/g Ra-226 | 3000 | 2663 | | 533 | | |
| 4-30-24 | EBP-1 Surface 4-30-24 @830 | 3000 | 16930 | | 3386 | | |
| 4-30-24 | EBP-1 Internal 4-30-24 @853 | 3000 | 14135 | | 2827 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature [signature], Reviewed by [signature]

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Concrete Structures**

Instrumentation : Scaler/Ratemeter L2221 SN#290801 Detector SPA-3 #30

Instrument Calibration Date: 2-19-24 Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Decsription Treatment Bed 4/5 CS-1 Ra-226 6.8pC/g ILT 7200

| Survey Date/Time | Survey Area ID/Description | Gamma Radiation Reading CPM | Comments/Notes |
|---|---|---|---|
| 4-22-24 | CS-1 East inside wall | 7970 | |
| " | CS-1 South East wall | 30312 | |
| " | CS-1 West inside wall | 9022 | |
| " | CS-1 South west wall | 13633 | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Technician Signature _____ Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Concrete Structures**

Instrumentation : Scaler/Ratemeter L2221 S#290801 Detector SPA-3 #30

Instrument Calibration Date: 2-19-24 Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Description Treatment Pond 5 CS-2 Ra-226 6.8 pC/L IL = 7200

| Survey Date/Time | Survey Area ID/Description | Gamma Radiation Reading CPM | Comments/Notes |
|---|---|---|---|
| 4-22-24 | CS-2 ~~West~~ North wall | 10559 | |
| " | CS-2 West wall | 11509 | |
| " | CS-2 West Wall Divider | 12688 | |
| " | CS-2 West wall | 7355 | |
| " | CS-2 South wall | 8901 | |
| " | CS-2 base North | 17024 | Sediments |
| " | CS-2 base South | 18844 | |
| | | | |
| | | | |
| | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Concrete Structures**

Instrumentation : Scaler/Ratemeter L2221 S#290801, Detector SPA-3 #30

Instrument Calibration Date: 2-19-24, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Decsription Treatment Pond 6 CS-3 Ra-226 6.8 pCi/g 1L 7200

| Survey Date/Time | Survey Area ID/Description | Gamma Radiation Reading CPM | Comments/Notes |
|---|---|---|---|
| 4-22-24 | CS-3 South wall | 13081 | |
| " | CS-3 South base | 14425 | |
| " | CS-3 North base | 34721 | Elevated gamma readings around Structure 2 103000 |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Concrete Structures**

Instrumentation : Scaler/Ratemeter L2221 S#290801, Detector SPA-3 #30

Instrument Calibration Date: 2-19-24, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No:

Survey Area/Unit Description Treatment Pond to CS-4 Ra-226 6.8 pCi/g 1L ≈ 7200

| Survey Date/Time | Survey Area ID/Description | Gamma Radiation Reading CPM | Comments/Notes |
|---|---|---|---|
| 4-22-24 | CS-4 North upper box top | 7155 | |
| " | CS-4 East upper box top | 6952 | |
| " | CS-4 South upper box top | 6938 | |
| " | CS-4 West upper box top | 10395 | |
| " | CS-4 North lower box Top | 8988 | |
| " | CS-4 west lower box top | 15543 | |
| " | CS-4 South lower box top | 9062 | |
| " | CS-4 North lower box wall | 26459 | |
| " | CS-4 West lower box wall | 39452 | |
| " | CS-4 South lower box wall | 39466 | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Concrete Structures**

Instrumentation : Scaler/Ratemeter L2221 S#290801, Detector SPA-3 #30

Instrument Calibration Date: 2-19-24, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Decsription Treatment Pond 6 CS-4 Ra-226 6.8 pCi/gIL = 7200

| Survey Date/Time | Survey Area ID/Description | Gamma Radiation Reading CPM | Comments/Notes |
|---|---|---|---|
| 4-22-24 | CS-4 East lower box wall | 23780 | |
| 11 | CS-4 Lower box base | 14800 | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Concrete Structures**

Instrumentation : Scaler/Ratemeter 2221 S#290801, Detector SPA-3 #30

Instrument Calibration Date: 2-19-24, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Decsription Treatment Pond 6 CS-5 Ra-226 6.8 pCi/g ≈ 7200 1L

| Survey Date/Time | Survey Area ID/Description | Gamma Radiation Reading CPM | Comments/Notes |
|---|---|---|---|
| 4-22-24 | CS-5 South upper box top | 6281 | |
| " | CS-5 North upper box top | 5938 | |
| " | CS-5 East lower box top | 6477 | |
| " | CS-5 West lower box top | 6762 | |
| " | CS-5 North lower box top | 7119 | |
| " | CS-5 North lower box inside wall | 6806 | |
| " | CS-5 East lower box inside wall | 6426 | |
| " | CS-5 South lower box inside wall | 6122 | |
| " | CS-5 West lower box inside wall | 7241 | |
| | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Concrete Structures**

Instrumentation : Scaler/Ratemeter L2221 SN290801, Detector SPA-3 #30

Instrument Calibration Date: 2-19-24, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Description Treatment Pond 6/7 CS-6 Ra-226 6.8pCi/g ILTC 7200

| Survey Date/Time | Survey Area ID/Description | Gamma Radiation Reading CPM | Comments/Notes |
|---|---|---|---|
| 4-22-24 | CS-6 South/East Top | 5762 | |
| " | CS-6 South/East inside wall | 5711 | |
| " | CS-6 East inside wall | 5590 | |
| " | CS-6 North/East inside wall | 5838 | |
| " | CS-6 Middle base | 6702 | |
| " | CS-6 South base | 7255 | |
| " | CS-6 South/west inside wall | 6004 | |
| " | CS-6 West inside wall | 6542 | |
| " | CS-6 North/west inside wall | 7271 | |
| | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Concrete Structures**

Instrumentation : Scaler/Ratemeter L2221 SN#290801, Detector SPA-3 #30

Instrument Calibration Date: 2-19-24, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Decsription Treatment Pad 7 CS-7 Ra-226 6.8pCi/g IL # 7200

| Survey Date/Time | Survey Area ID/Description | Gamma Radiation Reading CPM | Comments/Notes |
|---|---|---|---|
| 4-22-24 | CS-7 North West box top | 11804 | |
| 11 | CS-7 North East box top | 10611 | |
| 11 | CS-7 East box top | 11861 | |
| 11 | CS-7 South box top | 10354 | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Concrete Structures**

Instrumentation : Scaler/Ratemeter L2221 S#290801, Detector SPA-3 #30

Instrument Calibration Date: 2-19-24, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Decsription Treatment Pond 7 CS-8 Ra-226 68 pCi/g 1L = 7200

| Survey Date/Time | Survey Area ID/Description | Gamma Radiation Reading CPM | Comments/Notes |
|---|---|---|---|
| 4-22-24 | CS-8 box base | 31092 | |
| " | CS-8 North inside wall | 20294 | |
| " | CS-8 South inside wall | 15894 | |
| " | CS-8 ~~South~~ North wall | 22039 | |
| " | CS-8 ~~South~~ North base | 29815 | |
| " | CS-8 South wall | 14452 | |
| " | CS-8 South base | 14080 | |
| | | | |
| | | | |
| | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Concrete Structures**

Instrumentation : Scaler/Ratemeter L2221 S# 290801, Detector SPA-3 #30

Instrument Calibration Date: 2-19-24, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Decsription Treatment Pond 7 CS-9 Ra-226 6.8 pCi/g ILR ≈ 7200

| Survey Date/Time | Survey Area ID/Description | Gamma Radiation Reading CPM | Comments/Notes |
|---|---|---|---|
| 4-22-24 | CS-9 North upper box Top | 6342 | |
| 4-22-24 | CS-9 East upper box Top | 6099 | |
| " | CS-9 South upper box ~~wall~~ Top | 6891 | |
| " | CS-9 West upper box Top | 8801 | |
| " | CS-9 North lower box Top | 9122 | |
| " | CS-9 North lower box inside wall | 27352 | |
| " | CS-9 West lower box Top | 15852 | |
| " | CS-9 West lower box inside wall | 45633 | |
| " | CS-9 South lower box Top | 10558 | |
| " | CS-9 lower box base of Sump | 20500 | mine residue / soil |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Concrete Structures**

Instrumentation : Scaler/Ratemeter L2221 S#290801, Detector SPA-3 #30

Instrument Calibration Date: 2-19-24, Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Decsription Treatment Pond 1 CS-10 Ra-226 6.8 pCi/g, IL = 7200

| Survey Date/Time | Survey Area ID/Description | Gamma Radiation Reading CPM | Comments/Notes |
|---|---|---|---|
| 4-22-24 | CS-10 North/East Wall | 25471 | |
| " | CS-10 North/West Wall | 13104 | |
| " | CS-10 North base | 13052 | |
| " | CS-10 Sump base | 90000 | Mine residue / Soil |
| " | CS-10 South/East Wall | 16022 | |
| " | CS-10 South/West Wall | 9408 | |
| " | CS-10 South base | 10272 | |
| | | | |
| | | | |
| | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Scaler/Ratemeter - 2" x 2" NaI Detector Function Check**

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

2" x 2" NaI Detector ID: SPA-3 S#408522-30

Acceptable background Count (cpm) Range (20%) 6524 to 9786 (Bare)

Acceptable background Count (cpm) Range (20%) 2537 to 3805 (collimated)

Acceptable Source Count (cpm) Range (20%) 77104 to 115656

| Date | Scaler/Ratemeter | Physical Check | Cal Due | Battery[1] Volts or OK | HV Volts | THR mV[2] | Window In or OUT[3] | C.C.[4] | BKG Counts cpm | Source Counrts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2-19-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8351 Bare<br>3120 Coll. | 96753 | y | – | VP |
| 4-7-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8272 Bare<br>3110 Coll. | 97815 | y | – | VP |
| 4-8-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8249 Bare<br>3095 Coll. | 96238 | y | – | VP |
| 4-10-24 | L2221 S#290801 | ✓ | 2-19-25 | Ok | 900 | 10 | out | 1 | 8440 Bare<br>3065 Coll. | 96064 | y | – | VP |
| 4-15-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8345 Bare<br>3119 Coll. | 97475 | y | – | VP |
| 4-16-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8411 Bare<br>3124 Coll. | 96227 | y | – | VP |
| 4-17-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8401 Bare<br>3193 Coll. | 97111 | y | – | VP |
| 4-22-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8093 Bare<br>3144 Coll. | 96431 | y | – | VP |
| 4-23-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8205 Bare<br>3092 Coll. | 95968 | y | – | VP |
| 4-30-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8264 Bare<br>3263 Coll. | 96356 | y | – | VP |
| | | | | | | | | | Bare<br>Coll. | | | | |
| | | | | | | | | | Bare<br>Coll. | | | | |
| | | | | | | | | | Bare<br>Coll. | | | | |
| | | | | | | | | | Bare<br>Coll. | | | | |
| | | | | | | | | | Bare<br>Coll. | | | | |
| | | | | | | | | | Bare<br>Coll. | | | | |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 10.0 mV; (3) Window Position must be OUT; (4) CC on L2241-2 set at 0.001
For L2241-2 Check HV and Threshold using Ludlum 500 pulser.

**AVM Environmental Services, Inc.**
**Scaler/Ratemeter - 2" x 2" NaI Detector Function Check**

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

2" x 2" NaI Detector ID: SPA-3 S#408522-30

Acceptable background Count (cpm) Range (20%) 6391 to 9587 (Bare)

Acceptable background Count (cpm) Range (20%) 2546 to 3820 (collimated)

Acceptable Source Count (cpm) Range (20%) 77687 to 116531

| Date | Scaler/Ratemeter | Physical Check | Cal Due | Battery[1] Volts or OK | HV Volts | THR mV[2] | Window In or OUT[3] | C.C.[4] | BKG Counts cpm | Source Counts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 10-17-23 | L2221 S#240801 | ✓ | 5-15-24 | 6.0 | 900 | 10 | out | 1 | 7978 Bare / 3024 Coll. | 97941 | Y | — | VP |
| 10-18-23 | L2221 S#240801 | ✓ | 5-15-24 | OK | 900 | 10 | out | 1 | 7874 Bare / 2931 Coll. | 98494 | Y | — | VP |
| 10-25-23 | L2221 S#240801 | ✓ | 5-14-24 | ok | 900 | 10 | out | 1 | 7950 Bare / 2916 Coll. | 98651 | Y | — | VP |
| 11-1-23 | L2221 S#240801 | ✓ | 5-14-24 | ok | 900 | 10 | out | 1 | 7824 Bare / 3111 Coll. | 99371 | Y | — | VP |
| 11-2-23 | L2221 S#240801 | ✓ | 5-14-24 | ok | 900 | 10 | out | 1 | 7980 Bare / 2910 Coll. | 98416 | Y | — | VP |
| 11-7-23 | L2221 S#240801 | ✓ | 5-14-24 | ok | 900 | 10 | out | 1 | 7861 Bare / 3090 Coll. | 97213 | Y | — | VP |
| 11-13-23 | L2221 S#240801 | ✓ | 5-14-24 | ok | 900 | 10 | out | 1 | 7880 Bare / 2974 Coll. | 97008 | Y | — | VP |
| 11-20-23 | L2221 S#240801 | ✓ | 5-14-24 | ok | 900 | 10 | out | 1 | 7811 Bare / 2840 Coll. | 96911 | Y | — | VP |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 10.0 mV; (3) Window Position must be OUT; (4) CC on L2241-2 set at 0.001
For L2241-2 Check HV and Threshold using Ludlum 500 pulser.

**AVM Environmental Services, Inc.**
**Micro R Meter Function Check Form**

Micro R Meter: Ludlum 19, SR#76248

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Function Check @ Calibration 135

Acceptable Function Check Reading (uR/hr) Range (20%) 108 to 162

| Date | Physical Check | Cal Date | Battery(1) Volts or OK | BKG Reading uR/hr | Source Reading (2) uR/hr | Within Acceptable Range Y or N | Cal Due | Tech |
|---|---|---|---|---|---|---|---|---|
| 11-13-23 | ✓ | 11-3-23 | ok | 10-12 | 130 | Y | 11-3-24 | VP |
| 4-7-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | Y | 11-3-24 | VP |
| 4-8-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | Y | 11-3-24 | VP |
| 4-10-24 | ✓ | 11-3-23 | ok | 10-12 | 130 | Y | 11-3-24 | VP |
| 4-15-24 | ✓ | 11-3-23 | ok | 10-12 | 130 | Y | 11-3-24 | VP |
| 4-16-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | Y | 11-3-24 | VP |
| 4-17-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | Y | 11-3-24 | VP |
| 4-22-24 | ✓ | 11-3-23 | ok | 10-12 | 130 | Y | 11-3-24 | VP |
| 4-23-24 | ✓ | 11-3-23 | ok | 10-12 | 130 | Y | 11-3-24 | VP |
| 4-30-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | Y | 11-3-24 | VP |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

Note: (1) Battery Voltage must be within BAT TEST Range (2) Function Check Source must be placed in the circle on the front side of the meter

**AVM Environmental Services, Inc.**
**Ludlum SCA L2221 - 44-20 3x3 NaI Detector Function Check**
**559 - 659 KeV Gamma Radiation Soil Screening**

L2221 #290801

Ludlum 44-20 3x3 NaI Detector, #PR295573

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Acceptable background Count (cpm) Range (20%) 53 to 79

Acceptable Source Count (cpm) Range (20%) 12557 to 18835

| Date | Physical Check | Cal Date | Battery[1] Volts or OK | HV Volts | Threshhold mV [2] | Window mV | Window In/Out | BKG Counts cpm | Source Counts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 5-17-23 | ✓ | 5-10-23 | ✓ | 577 | 559 | 100 | in | 70 | 16805 | Y | — | VP |
| 5-18-23 | ✓ | 5-10-23 | ✓ | 578 | 559 | 100 | in | 66 | 16200 | Y | — | VP |
| 5-22-23 | ✓ | 5-10-23 | ✓ | 582 | 559 | 100 | in | 68 | 15900 | Y | — | VP |
| 5-23-23 | ✓ | 5-10-23 | ✓ | 582 | 559 | 100 | in | 71 | 15508 | Y | — | VP |
| 5-25-23 | ✓ | 5-10-23 | ✓ | 578 | 559 | 100 | in | 73 | 16253 | Y | — | VP |
| 5-30-23 | ✓ | 5-10-23 | ✓ | 577 | 559 | 100 | in | 72 | 16101 | Y | — | VP |
| 5-31-23 | ✓ | 5-10-23 | ✓ | 575 | 559 | 100 | in | 64 | 15789 | Y | | VP |
| 6-1-23 | ✓ | 5-10-23 | ✓ | 577 | 559 | 100 | in | 71 | 16224 | Y | — | VP |
| 11-8-23 | ✓ | 5-10-23 | ✓ | 576 | 559 | 100 | in | 60 | 16170 | Y | — | VP |
| 11-16-23 | ✓ | 5-10-23 | ✓ | 577 | 559 | 100 | in | 68 | 15327 | Y | — | VP |
| 4-17-24 | ✓ | 5-10-23 | ✓ | 578 | 559 | 100 | in | 74 | 15518 | Y | — | VP |
| 4-30-24 | ✓ | 5-10-23 | ✓ | 577 | 559 | 100 | in | 69 | 16122 | Y | — | VP |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 220 mV; (3) Window @ 440, must be IN

**AVM Environmental Services Inc.**
**Scaler/Ratemeter - Detector Calibration Form**



Scaler/Ratemeter: L2221 S# 290801
Detector: SPA-3 S# 408522-30

Source: U308 ore in can S# FC-2 Strength 1%

Scaler/Ratemeter Threshhold set @ 10 mV, Window IN/OUT Out, Window N/A mV

| HV | Reading, CPM (Source) | Reading, CPM (Background) |
|---|---|---|
| 500 | 17200 | 470 |
| 550 | 37012 | 738 |
| 600 | 57214 | 998 |
| 650 | 71774 | 1379 |
| 700 | 84865 | 1633 |
| 750 | 93899 | 1765 |
| 800 | 95561 | 1837 |
| 850 | 96093 | 1895 |
| 900 | 97180 | 2012 |
| 950 | 97636 | 2018 |
| 1000 | 100155 | 2037 |
| 1050 | 113726 | 2090 |
| 1100 | 133647 | 2249 |
| 1150 | 161780 | 2497 |
| 1200 | 199910 | 3198 |
| 1250 | | |
| 1300 | | |
| 1350 | | |
| 1400 | | |

**Background reading at designated function check location in AVM office.**

| Count # | Reading (CPM) Bare | Collimated |
|---|---|---|
| 1 | 8139 | 3129 |
| 2 | 8284 | 3144 |
| 3 | 8301 | 3004 |
| 4 | 8107 | 3170 |
| 5 | 8155 | 3171 |
| Average | 8197 | 3124 |

FC Range (6524-9786) (2537-3805)

**Count Readings with 1 percent $U_3O_8$ can directly under collimated detector on designated function check location in AVM office.**

| Count # | Reading (CPM) |
|---|---|
| 1 | 96354 |
| 2 | 95928 |
| 3 | 96716 |
| 4 | 96662 |
| 5 | 96241 |
| Average | 96380 |

HV Set @ 900 VDC (Instrument) 900 VDC (DVM Fluke 8020B)

Input Sensitivity (THR), mV 10

Function Check with 1 percent $U_3O_8$ ore in can. Can Directly under the detector in the collimator.
Acceptable Function check range is 77104 to 115656 CPM

**Notes:**

Date 2-19-24 By

**AVM Environmental Services Inc.**
**Scaler/Ratemeter - Detector Calibration Form**



Scaler/Ratemeter L2221 S# 290801
Detector SPA-3 S# 408522-30

Source U308 ore in con S# EC-2 Strength 1%

Scaler/Ratemeter Threshhold set @ 10 mV, Window IN/OUT out, Window N/A mV

HV Set @ 900 VDC (Instrument) 900 VDC (DVM Fluke 8020B)

**Count Readings for Calibration Pad GPB (0.0 ± 0.3 pCi/gm Ra-226)**

| | Bare (Uncollimated) @ 1' | | Collimated @ 1' | |
|---|---|---|---|---|
| #1 | 11498 | cpm | 2766 | cpm |
| #2 | 11820 | cpm | 2839 | cpm |
| #3 | 11614 | cpm | 2849 | cpm |
| #4 | 11823 | cpm | 2883 | cpm |
| #5 | 11777 | cpm | 2772 | cpm |
| BKG Average | 11706 | cpm | 2812 | cpm |

**Count Readings for Calibration Pad GPL (87.78 pCi/gm Ra-226)**

| | Bare (Uncollimated) @ 1' | | Collimated @ 1' | |
|---|---|---|---|---|
| #1 | 90635 | cpm | 53328 | cpm |
| #2 | 90696 | cpm | 53884 | cpm |
| #3 | 90626 | cpm | 53443 | cpm |
| #4 | 90778 | cpm | 54004 | cpm |
| #5 | 91414 | cpm | 53996 | cpm |
| Gross Average | 90830 | cpm | 53731 | cpm |
| Net Source Pad | 79123 | cpm | 50919 | cpm |
| Eff(net cpm/87.78 pCi/gm | 901 | cpm/pCi/gm | 580 | cpm/pCi/gm |

**µR/hr Reading for Calibration Pad GPL (87.78 pCi/gm Ra-226)**

Ludlum Model 19 serial # 76248

Reading @ 1' 115 µR/hr
$1.276^{-03}$ µR/hr/cpm

Date 2-19-24 By

**AVM Environmental Services Inc.**

**Scaler/Ratemeter Calibration Form**

Model : L2221 S/N: 68782

Reference Instrument/Source: Ludlum Pulser 500, S/N:114513

**HV Calibration**

HV Test (2 points): Ref/Inst 600/600 Ref/Inst 900/900

**Ratemeter Calibration**

Instrument Threshold @ 100 (10 mV), WIN: Out, HV 900VDC; Pulser Threshold @ 200 (20mV)

| Range/Mode | Range Multiplier | Calibration Point (Pulser Setting) cpm x multiplier | Target CPM (±5%) | As Found Reading | | Left or Set Reading |
|---|---|---|---|---|---|---|
| Ratemeter | x1 | 40x1 | 38-42 | 40 | | 40 |
| | x1 | 40x10 | 380-420 | 397 | | 397 |
| | x10 | 40x100 | 3800-4200 | 3996 | | 3996 |
| | x100 | 40x1K | 38K-42K | 39948 | | 39948 |
| | x1K | 40x10K | 380K-420K | 400751 | | 400751 |
| Digital Ratemeter | - | 40x1 | 38-42 | 39-40 | | 39-40 |
| | - | 40x10 | 380-420 | 392-401 | | 392-401 |
| | - | 40x100 | 3800-4200 | 3996-4005 | | 3996-4005 |
| | - | 40x1K | 38K-42K | 39K-40K | | 39K-40K |
| | - | 40x10K | 380K-420K | 400K | | 400K |
| | | | | | | |

**Threshold/Gain Calibration**

WIN OUT

| Pulser Amplitude (mV) | Pulser CPM | | L2221 Theshold (mv) | Target CPM | L2221 CPM Found | | L2221 CPM Left or Set @ |
|---|---|---|---|---|---|---|---|
| 10.0 | 40000 | | 100 (10 mV) | 27K -33K | 31255 | | 31255 |
| 20.0 | 40000 | | 200 (20 mV) | 27K -33K | 30801 | | 30801 |
| 30.0 | 40000 | | 300 (30 mV) | 27K -33K | 30951 | | 30951 |
| 40.0 | 40000 | | 400 (40 mV) | 27K -33K | 29579 | | 29579 |
| 50.0 | 40000 | | 500 (50 mV) | 27K -33K | 31042 | | 31042 |

Note: Use R174 Gain Control on Power Supply Board to adjust L2221 CPM @75% for Threshold/Gain Calibration

**Window Cut-off Points Check**

L2221 Threshold set @100 (10.0 mv)

WIN @ 100 (10.0 mV) ✓ WIN @ 400 (40.0 mV) ✓

WIN @ 200 (20.0 mV) ✓ WIN @ 500 (50.0 mV) ✓

Date 2-19-24 Calibrated By

**AVM Environmental Services Inc.**

**Scaler/Ratemeter Calibration Form**

Model.: L2221 S/N: 290801

Reference Instrument/Source: Ludlum Pulser 500, S/N:114513

**HV Calibration**

HV Test (2 points): Ref/Inst 600/600 Ref/Inst 900/900

**Ratemeter Calibration**

Instrument Threshold @ 100 (10 mV), WIN: Out, HV 900VDC; Pulser Threshold @ 200 (20mV)

| Range/Mode | Range Multiplier | Calibration Point (Pulser Setting) cpm x multiplier | Target CPM (±5%) | As Found Reading | | Left or Set Reading |
|---|---|---|---|---|---|---|
| Ratemeter | x1 | 40x1 | 38-42 | 40 | | 40 |
| | x1 | 40x10 | 380-420 | 400 | | 400 |
| | x10 | 40x100 | 3800-4200 | 4002 | | 4002 |
| | x100 | 40x1K | 38K-42K | 40020 | | 40020 |
| | x1K | 40x10K | 380K-420K | 400220 | | 400220 |
| Digital Ratemeter | - | 40x1 | 38-42 | 39 | | 39 |
| | - | 40x10 | 380-420 | 402 | | 402 |
| | - | 40x100 | 3800-4200 | 4004 | | 4004 |
| | - | 40x1K | 38K-42K | 40026 | | 40026 |
| | - | 40x10K | 380K-420K | 400221 | | 400221 |
| | | | | | | |

**Threshold/Gain Calibration**

WIN OUT

| Pulser Amplitude (mV) | Pulser CPM | | L2221 Theshold (mv) | Target CPM | L2221 CPM Found | | L2221 CPM Left or Set @ |
|---|---|---|---|---|---|---|---|
| 10.0 | 40000 | | 100 (10 mV) | 27K -33K | 31194 | | 31194 |
| 20.0 | 40000 | | 200 (20 mV) | 27K -33K | 29354 | | 29354 |
| 30.0 | 40000 | | 300 (30 mV) | 27K -33K | 30765 | | 30765 |
| 40.0 | 40000 | | 400 (40 mV) | 27K -33K | 30082 | | 30082 |
| 50.0 | 40000 | | 500 (50 mV) | 27K -33K | 29842 | | 29842 |

Note: Use R174 Gain Control on Power Supply Board to adjust L2221 CPM @75% for Threshold/Gain Calibration

**Window Cut-off Points Check**

L2221 Threshold set @100 (10.0 mv)

WIN @ 100 (10.0 mV) ✓ WIN @ 400 (40.0 mV) ✓

WIN @ 200 (20.0 mV) ✓ WIN @ 500 (50.0 mV) ✓

Date 2-19-24 Calibrated By

**AVM Environmental Services Inc.**
L2221 SCA/L44-20 Energy Calibration Form

SCA: L2221, SR #290801 Detector: Ludlum 44-20 (3x3 NaI Scintillator)

Calibration Source: Cs-137 Check Source, 5 uCi (August 2008) For 662 KeV Peak Cal

Threshold (input sensitivity) **652**

Window, In/Out **IN** Window **20**

HV Initial 100, At Peak 579

Maximum CPM: 198160 Background CPM: 13

HV Set @ 579 VDC

For Bi-214 609.2 KeV Peak (559 - 659 KeV ROI), Set Threshold @ 559, Window @ 100

Calibration Check w 1% U3O8 Ore Check Source: 15696 CPM

BKG = 65 cpm

Date 5-10-23 Calibrated By

**AVM Enviro. ..tal Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

**Instrumentation : Scaler/Ratemeter** L2221 SN 68782 , **Detector** L44-20 SN 295573
**Instrument Calibration Date:** 10-7-22 , **Instrument Function Check Performed:** ✓
**Survey Area/Unit Decsription** Mt Taylor Mine - Correlation Calibration

**Area exposure rate:**

| Date/Time | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 5-10-23 | Blank | | 329 | | 66 | | |
| 5-10-23 | 6.6pCi/g Ref. Soil | 3000 | 2998 | | 600 | | |
| 5-10-23 | 25pCi/g Ref Soil | 2984 | 9552 | 9603 | 1921 | | |
| 5-10-23 | 50pCi/g Ref Soil | 2976 | 18078 | 18224 | 3645 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |


Technician Signature _____, Reviewed by _____

**AVM Environmental Services**

**Ex-Situ Soil Screening Gamma Radiation Level to Ra-226 Correlation**

**Mt. Taylor Mine Site Subsurface Soil Investigation**

| Reference Soil ID | Date | Ra-226 pCi/g | Wt gms | 609 KeV CP5Min Gross (3x3 NaI Detector) | CPM |
|---|---|---|---|---|---|
| Blank | 5/10/2023 | - | - | 329 | 66 |
| 6.6 pCi/g Ra-226 Ref Soil | 5/10/2023 | 6.6 | 3000 | 2998 | 600 |
| 25 pCi/g Ra-226 Ref Soil | 5/10/2023 | 25 | 3000 | 9603 | 1921 |
| 50 pCi/g Ra-226 Ref Soil | 5/10/2023 | 50 | 3000 | 18224 | 3645 |



**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Concrete Correlation Form**

Instrumentation : Scaler/Ratemeter L2221 S#290801, Detector SPA-3 #30

Instrument Calibration Date: 2-19-24, Instrument Daily Function Check Performed: ✓


2"x2" NaI Detector Collimated ✓ Yes or ____ No.

Survey Area/Unit Decsription Grants Calibration Pad site - DOE

| Survey Date | Calibration Pad ID | Gamma Radiation Reading, CPM | | Comments/Notes |
|---|---|---|---|---|
| | | SPA-3, 0.5-inch lead collimated | SPA-3, 1.0-inch lead collimated | |
| 4-18-24 | GPB | 2019 | 1989 | |
| | | 2148 | 1865 | |
| | | 2123 | 2076 | uR/hr @ Contact 9.5 |
| 11 | GPL | 70818 | 74469 | |
| | | 71213 | 74463 | uR/hr @ Contact 205 |
| | | 71137 | 74487 | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Technician Signature _____, Reviewed by _____

Grants DOE Calibration Pad
0.5 inch lead collimated 2x2 detector calibration for concrete investigation




| Concrete ID | CPM | Ra-226 pCi/g |
|---|---|---|
| Cal Pad GPB | 2097 | 0.10 |
| Cal Pad GPL | 71056 | 87.78 |

Designer and Manufacturer of Scientific and Industrial Instruments

www.ludlums.com

# CERTIFICATE OF CALIBRATION

LUDLUM MEASUREMENTS, INC.
501 Oak Street
325-235-5494
Sweetwater, TX 79556, U.S.A.

ACCREDITED
CERT # 4084.01

Customer AVM ENVIRONMENTAL SERVICES INC ORDER NO. 20457182/547880

Mfg. Ludlum Measurements, Inc. Model 19 Serial No. 76248

M. Model Serial No.

Cal. Date 3-Nov-23 Cal Due Date 3-Nov-24 Cal. Interval 1 Year Meterface 202-1070

Check mark ☑ applies to applicable instr. and/or detector IAW mfg. spec. T. 73 °F RH 37 % Alt 708.1 mm Hg

☐ New Instrument Instrument Received ☐ Within Toler. +-10% ☑ 10-20% ☐ Out of Tol. ☐ Requiring Repair ☐ Other-See comments

☑ Mechanical ck. ☑ Meter Zeroed ☐ Background Subtract ☐ Input Sens. Linearity
☑ F/S Resp. ck ☑ Reset ck. ☐ Window Operation ☑ Geotropism
☑ Audio ck. ☐ Alarm Setting ck. ☑ Batt. ck.

☐ Calibrated in accordance with LMI SOP 14.8 ☑ Calibrated in accordance with LMI SOP 14.9

Instrument Volt Set 800 V Input Sens. 37 mV Det. Oper. 800 V at 37 mV Threshold Dial Ratio = mV

☐ HV Readout (2 points) Ref./Inst. / V Ref./Inst. / V

**COMMENTS:**

Gamma Calibration: GM detectors positioned perpendicular to source except for M 44-9 in which the front of probe faces source.
Multimeter uncertainty within 1.3% of reading, Gamma uncertainty within 5.0% of reading, Neutron uncertainty within 7.0% of reading, Count rate uncertainty within 5.4% of reading

| RANGE/MULTIPLIER | REFERENCE CAL. POINT | INSTRUMENT REC'D "AS FOUND READING" | INSTRUMENT METER READING |
|---|---|---|---|
| 5000 | 4000µR/hr | 4200 µR/hr | 4000 µR/hr |
| 5000 | 1000µR/hr | 1100 | 1000 |
| 500 | 400µR/hr = 69800 cpm | 410 | 400 |
| 500 | 100µR/hr | 110 | 100 |
| 250 | 200µR/hr = 33800 cpm | 210 | 200 |
| 250 | 100µR/hr | 100 | 100 |
| 50 | 6980 cpm | 42 | 40 |
| 50 | 1750 cpm | 10 | 10 |
| 25 | 3380 cpm | 22 | 20 |
| 25 | 845 cpm | 5 | 5 |

Range(s) Calibrated Electronically

| Digital Readout | REFERENCE CAL. POINT | INSTRUMENT RECEIVED | INSTRUMENT METER READING |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| Log Scale | REFERENCE CAL. POINT | INSTRUMENT RECEIVED | INSTRUMENT METER READING |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Ludlum Measurements, Inc. certifies that the above instrument has been calibrated by standards traceable to the National Institute of Standards and Technology, or to the calibration facilities of other International Standards Organization members, or have been derived from accepted values of natural physical constants or have been derived by the ratio type of calibration techniques.
All pass/fail determinations are based on the manufacturer's specifications without considering uncertainty factors.
Measurement results represent expanded uncertainties expressed at approximately the 95% level of confidence, using a coverage factor of k=2.
The calibration system conforms to the requirements of ANSI/NCSL Z540-1-1994 and ANSI N323AB-2013

ISO/IEC 17025:2017(E)
State of Texas Calibration License No. LO-1963

**Reference Instruments and/or Sources:** Cs-137 S/N: ☐ 059 ☐ 2171CP ☐ 2261CP ☐ 720 ☐ 734 ☐ 781 ☐ 1131 ☐ 1616 ☐ 1696 ☐ 1909 ☐ 1916CP ☐ 2324/2521
☐ 5717CO ☐ 5719CO ☐ 60846 ☐ 70897 ☐ 73410 ☐ E552 ☐ G112 ☑ 2168CP ☐ S-394 ☐ S-1054 ☐ T10081 ☐ T10082 Neutron Am-241 Be ☐ T-304 Ra-226 ☐ Y982
☐ E551 ☐ 5105 ☐ CSV280

☐ Alpha S/N ☐ Beta S/N ☐ Other

☐ m 500 S/N 114520 ☐ Oscilloscope S/N ☑ Multimeter S/N 53950165

Calibrator Sheba Lee Sheba Lee Title Calibrator Date 3-Nov-23

QC'd By Title Final QC Date 3NOV23

This certificate shall not be reproduced except in full, without the written approval of Ludlum Measurements, Inc.
FORM C22A 01/07/2020 Page 1 of 1

AC Inst. Only ☐ Passed Dielectric (Hi-Pot) and Continuity Test ☐ Failed:

# CERTIFICATE OF CALIBRATION


**LUDLUM MEASUREMENTS, INC.**
501 Oak Street
325-235-5494
Sweetwater, TX 79556, U.S.A.
www.ludlums.com


ACCREDITED
CERT # 4084.01

Model No. / Serial No. 500 / 114513

Customer AVM ENVIRONMENTAL SERVICES INC ORDER NO. 20460064/549833

Date 13-Dec-23 Cal Due Date 13-Dec-24 Cal. Interval 1 Year Procedure 500/Rev 8

☐ New Instrument Instrument Received ☑ Within Tolerance ☐ Out of Tol. ☐ Requiring Repair ☐ Other-See Comments

T. 73 °F RH 36 % Alt 714.2 mm Hg ☑ Meter Zeroed ☑ Mechanical Check

**PULSE WIDTH Uncertainty within 0.85% of reading**

| | As Found | As Left | Acceptable Range (µs) |
|---|---|---|---|
| NEG PULSE | 1.7 | 1.7 | 1.5 - 1.9 |
| POS PULSE | 1.7 | 1.7 | < 2.25 |

**PULSE AMPLITUDE (NEGATIVE) Uncertainty within 1.3% of reading**

| Reference Amplitude | As Found Amplitude Reading | As Left Amplitude Reading | Acceptable Range | Reference Amplitude | As Found Amplitude Reading | As Left Amplitude Reading | Acceptable Range |
|---|---|---|---|---|---|---|---|
| 1 V | 1 V | 1 V | 0.9 - 1.1 | 4 V | 4.1 V | 4.1 V | 3.6 - 4.4 |
| 100 mV | 100 mV | 100 mV | 90 - 110 | 400 mV | 410 mV | 410 mV | 360 - 440 |
| 10 mV | 10 mV | 10 mV | 9 - 11 | 40 mV | 41 mV | 41 mV | 36 - 44 |
| 1 mV | 1 mV | 1 mV | 0.9 - 1.1 | 4 mV | 4.1 mV | 4.1 mV | 3.6 - 4.4 |

**PULSE AMPLITUDE (POSITIVE) Uncertainty within 1.3% of reading**

| Reference Amplitude | As Found Amplitude Reading | As Left Amplitude Reading | Acceptable Range |
|---|---|---|---|
| 3 V | 3 V | 3 V | 2.7 - 3.3 |
| 300 mV | 300 mV | 300 mV | 270 - 330 |
| 30 mV | 30 mV | 30 mV | 27 - 33 |
| 3 mV | 3 mV | 3 mV | 2.7 - 3.3 |

**PULSE FREQUENCY (PERIOD) Uncertainty within 0.46% of reading**

| Pulser Range | As Found Period | As Left Period | Acceptable Range |
|---|---|---|---|
| x 10K | 6.667 | 6.667 | 6.534 - 6.8 |
| x 1K | 66.70 | 66.70 | 65.34 - 68 |
| x 100 | 667.2 | 667.2 | 653.4 - 680 |
| x 10 | 6671 | 6671 | 6534 - 6800 |
| x 1 | 66.71 | 66.71 | 65.34 - 68 |
| x 0.1 | 90 | 90 | 88.2 - 91.8 Counts |

Digital High Voltage Uncertainty within 1.3% of reading

| Reference Voltage | As Found Voltage Reading | As Left Voltage Reading | Acceptable Range |
|---|---|---|---|
| 500 V | | | 490 - 510 |
| 1500 V | | | 1470 - 1530 |

Analog High Voltage Uncertainty within 1.3% of reading

| Reference Voltage | As Found Voltage Reading | As Left Voltage Reading | Acceptable Range |
|---|---|---|---|
| 500 V | 500 | 500 | 475 - 525 |
| 2000 V | 2000 | 2000 | 1900 - 2100 |

| CPM Reading | As Found cpm Reading | As Left cpm Reading | Acceptable Range |
|---|---|---|---|
| MAX | 992 | 992 | 981 - 999 |
| MIN | 0-1 | 0-1 | 0 - 1* |

* READING OF 0-99 IS ACCEPTABLE FOR INSTRUMENTS WITH A S/N 100000 AND BELOW OR MAIN BOARD = 5208-066

**COMMENTS:**

CAL'D W/ 39" CABLE.

Ludlum Measurements, Inc. certifies that the above instrument has been calibrated by standards traceable to the National Institute of Standards and Technology, or to the calibration facilities of other International Standards Organization members, or have been derived from accepted values of natural physical constants or have been derived by the ratio type of calibration techniques.
All pass/fail determinations are based on the manufacturer's specifications without considering uncertainty factors.
Measurement results represent expanded uncertainties expressed at approximately the 95% level of confidence, using a coverage factor of k=2.
The calibration system conforms to the requirements of ANSI/NCSL Z540-1-1994 and ANSI N323AB-2013

ISO/IEC 17025:2017(E)
State of Texas Calibration License No. LO-1963

Reference Instruments:

| | | | | |
|---|---|---|---|---|
| Frequency Counter | Model BK 1856D | S/N 332L14297 | Cal Date | 17-Feb 2023 |
| Oscilloscope | Model Tektronix 72-6820 | S/N 1102645 | Cal Date | 11-Oct 2023 |
| Voltmeter | Model Fluke 83V | S/N 94000441 | Cal Date | 2-Jun 2023 |

Calibrator William Tinsley William Tinsley Title Calibrator Date 13-December 2023

QC'd By [signature] Title Final QC Date 14 Dec 23


This certificate shall not be reproduced except in full, without the written approval of Ludlum Measurements, Inc.




AC Inst. Only ☑ Passed Dielectric (Hi-Pot) and Continuity Test ☐ Failed: _____

# ANALYTICAL SUMMARY REPORT

May 24, 2024

Rio Grande Resources Corporation
PO Box 1150
Grants, NM 87020-1150

Work Order: C24040791 Quote ID: C16056

Project Name: MTM TP Soil Characterization

Energy Laboratories, Inc. Casper WY received the following 10 samples for Rio Grande Resources Corporation on 4/24/2024 for analysis.

| Lab ID | Client Sample ID | Collect Date | Receive Date | Matrix | Test |
|---|---|---|---|---|---|
| C24040791-001 | TP-11 [6-12]inches | 11/13/23 13:45 | 04/24/24 | Solid | Gamma Sample Preparation Drying/Grinding, Radiochemistry Gross Gamma |
| C24040791-002 | TP-15B [6-12]Inches | 11/14/23 8:25 | 04/24/24 | Solid | Same As Above |
| C24040791-003 | TP-11 [1-2]Feet | 11/16/23 11:05 | 04/24/24 | Solid | Same As Above |
| C24040791-004 | TP-15B [1-1.5]Feet | 11/16/23 11:35 | 04/24/24 | Solid | Same As Above |
| C24040791-005 | TP-41 [0-6]Inches | 04/16/24 8:45 | 04/24/24 | Solid | Same As Above |
| C24040791-006 | TP-46 [6-12]Inches | 04/16/24 10:25 | 04/24/24 | Solid | Same As Above |
| C24040791-007 | TP-36 [6-12]Inches | 04/16/24 11:00 | 04/24/24 | Solid | Same As Above |
| C24040791-008 | TP-41 [6-12]Inches | 04/16/24 11:15 | 04/24/24 | Solid | Same As Above |
| C24040791-009 | TP-36 [1-2]Feet | 04/17/24 11:20 | 04/24/24 | Solid | Same As Above |
| C24040791-010 | TP-DS 01 | 04/17/24 13:00 | 04/24/24 | Solid | Same As Above |

The analyses presented in this report were performed by Energy Laboratories, Inc., 2393 Salt Creek Hwy., Casper, WY 82601, unless otherwise noted. Any exceptions or problems with the analyses are noted in the report package. Any issues encountered during sample receipt are documented in the Work Order Receipt Checklist.

The results as reported relate only to the item(s) submitted for testing. This report shall be used or copied only in its entirety. Energy Laboratories, Inc. is not responsible for the consequences arising from the use of a partial report.

If you have any questions regarding these test results, please contact your Project Manager .

Report Approved By:

**CLIENT:** Rio Grande Resources Corporation
**Project:** MTM TP Soil Characterization
**Work Order:** C24040791

**Report Date:** 05/24/24

# CASE NARRATIVE

ORIGINAL SAMPLE SUBMITTAL(S)
All original sample submittals have been returned with the data package.

SAMPLE TEMPERATURE COMPLIANCE: 4°C (±2°C)
Temperature of samples received may not be considered properly preserved by accepted standards. Samples that are hand delivered immediately after collection shall be considered acceptable if there is evidence that the chilling process has begun.

GROSS ALPHA ANALYSIS
Method 900.0 for gross alpha and gross beta is intended as a drinking water method for low TDS waters. Data provided by this method for non potable waters should be viewed as inconsistent.

RADON IN AIR ANALYSIS
The desired exposure time is 48 hours (2 days). The time delay in returning the canister to the laboratory for processing should be as short as possible to avoid excessive decay. Maximum recommended delay between end of exposure to beginning of counting should not exceed 8 days.

SOIL/SOLID SAMPLES
All samples reported on an as received basis unless otherwise indicated.

ATRAZINE, SIMAZINE AND PCB ANALYSIS
Data for PCBs, Atrazine and Simazine are reported from EPA 525.2. PCB data reported by ELI reflects the results for seven individual Aroclors. When the results for all seven are ND (not detected), the sample meets EPA compliance criteria for PCB monitoring.

SUBCONTRACTING ANALYSIS
Subcontracting of sample analyses to an outside laboratory may be required. If so, ENERGY LABORATORIES will utilize its branch laboratories or qualified contract laboratories for this service. Any such laboratories will be indicated within the Laboratory Analytical Report.

BRANCH LABORATORY LOCATIONS
eli-b - Energy Laboratories, Inc. - Billings, MT
eli-g - Energy Laboratories, Inc. - Gillette, WY
eli-h - Energy Laboratories, Inc. - Helena, MT

ISO 17025 DISCLAIMER:
The results of this Analytical Report relate only to the items submitted for analysis.

ENERGY LABORATORIES, INC. - CASPER,WY certifies that certain method selections contained in this report meet requirements as set forth by the above accrediting authorities. Some results requested by the client may not be covered under these certifications. All analysis data to be submitted for regulatory enforcement should be certified in the sample state of origin. Please verify ELI's certification coverage by visiting www.energylab.com

ELI appreciates the opportunity to provide you with this analytical service. For additional information and services visit our web page www.energylab.com.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM TP Soil Characterization
**Lab ID:** C24040791-001
**Client Sample ID:** TP-11 [6-12]

**Report Date:** 05/24/24
**Collection Date:** 11/13/23 13:45
**DateReceived:** 04/24/24
**Matrix:** Solid

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.8 | pCi/g-dry | U | | | E901.1 | 05/16/24 15:53 / haw |
| Radium 224 precision (±) | 8.0 | pCi/g-dry | | | | E901.1 | 05/16/24 15:53 / haw |
| Radium 224 MDC | 13.3 | pCi/g-dry | | | | E901.1 | 05/16/24 15:53 / haw |
| Radium 226 | 61.5 | pCi/g-dry | | | | E901.1 | 05/16/24 15:53 / haw |
| Radium 226 precision (±) | 1.4 | pCi/g-dry | | | | E901.1 | 05/16/24 15:53 / haw |
| Radium 226 MDC | 0.7 | pCi/g-dry | | | | E901.1 | 05/16/24 15:53 / haw |
| Radium 228 | 0.4 | pCi/g-dry | U | | | E901.1 | 05/16/24 15:53 / haw |
| Radium 228 precision (±) | 1.2 | pCi/g-dry | | | | E901.1 | 05/16/24 15:53 / haw |
| Radium 228 MDC | 1.7 | pCi/g-dry | | | | E901.1 | 05/16/24 15:53 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM TP Soil Characterization
**Lab ID:** C24040791-002
**Client Sample ID:** TP-15B [6-12]

**Report Date:** 05/24/24
**Collection Date:** 11/14/23 08:25
**DateReceived:** 04/24/24
**Matrix:** Solid

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.9 | pCi/g-dry | U | | | E901.1 | 05/17/24 12:48 / haw |
| Radium 224 precision (±) | 3.1 | pCi/g-dry | | | | E901.1 | 05/17/24 12:48 / haw |
| Radium 224 MDC | 5.2 | pCi/g-dry | | | | E901.1 | 05/17/24 12:48 / haw |
| Radium 226 | 15.2 | pCi/g-dry | | | | E901.1 | 05/17/24 12:48 / haw |
| Radium 226 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/17/24 12:48 / haw |
| Radium 226 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 05/17/24 12:48 / haw |
| Radium 228 | 1.6 | pCi/g-dry | | | | E901.1 | 05/17/24 12:48 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1 | 05/17/24 12:48 / haw |
| Radium 228 MDC | 0.5 | pCi/g-dry | | | | E901.1 | 05/17/24 12:48 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM TP Soil Characterization
**Lab ID:** C24040791-003
**Client Sample ID:** TP-11 [1-2]

**Report Date:** 05/24/24
**Collection Date:** 11/16/23 11:05
**DateReceived:** 04/24/24
**Matrix:** Solid

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.4 | pCi/g-dry | U | | | E901.1 | 05/17/24 14:57 / haw |
| Radium 224 precision (±) | 1.5 | pCi/g-dry | | | | E901.1 | 05/17/24 14:57 / haw |
| Radium 224 MDC | 2.6 | pCi/g-dry | | | | E901.1 | 05/17/24 14:57 / haw |
| Radium 226 | 1.1 | pCi/g-dry | | | | E901.1 | 05/17/24 14:57 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1 | 05/17/24 14:57 / haw |
| Radium 226 MDC | 0.1 | pCi/g-dry | | | | E901.1 | 05/17/24 14:57 / haw |
| Radium 228 | 1.1 | pCi/g-dry | | | | E901.1 | 05/17/24 14:57 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 05/17/24 14:57 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 05/17/24 14:57 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM TP Soil Characterization
**Lab ID:** C24040791-004
**Client Sample ID:** TP-15B [1-1.5]

**Report Date:** 05/24/24
**Collection Date:** 11/16/23 11:35
**DateReceived:** 04/24/24
**Matrix:** Solid

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1 | 05/17/24 16:01 / haw |
| Radium 224 precision (±) | 2.1 | pCi/g-dry | | | | E901.1 | 05/17/24 16:01 / haw |
| Radium 224 MDC | 3.6 | pCi/g-dry | | | | E901.1 | 05/17/24 16:01 / haw |
| Radium 226 | 1.2 | pCi/g-dry | | | | E901.1 | 05/17/24 16:01 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 05/17/24 16:01 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 05/17/24 16:01 / haw |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1 | 05/17/24 16:01 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1 | 05/17/24 16:01 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1 | 05/17/24 16:01 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM TP Soil Characterization
**Lab ID:** C24040791-005
**Client Sample ID:** TP-41 [0-6]

**Report Date:** 05/24/24
**Collection Date:** 04/16/24 08:45
**DateReceived:** 04/24/24
**Matrix:** Solid

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.7 | pCi/g-dry | U | | | E901.1 | 05/20/24 09:23 / haw |
| Radium 224 precision (±) | 6.6 | pCi/g-dry | | | | E901.1 | 05/20/24 09:23 / haw |
| Radium 224 MDC | 10.9 | pCi/g-dry | | | | E901.1 | 05/20/24 09:23 / haw |
| Radium 226 | 43.5 | pCi/g-dry | | | | E901.1 | 05/20/24 09:23 / haw |
| Radium 226 precision (±) | 1.1 | pCi/g-dry | | | | E901.1 | 05/20/24 09:23 / haw |
| Radium 226 MDC | 0.5 | pCi/g-dry | | | | E901.1 | 05/20/24 09:23 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1 | 05/20/24 09:23 / haw |
| Radium 228 precision (±) | 0.7 | pCi/g-dry | | | | E901.1 | 05/20/24 09:23 / haw |
| Radium 228 MDC | 1.0 | pCi/g-dry | | | | E901.1 | 05/20/24 09:23 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM TP Soil Characterization
**Lab ID:** C24040791-006
**Client Sample ID:** TP-46 [6-12]

**Report Date:** 05/24/24
**Collection Date:** 04/16/24 10:25
**DateReceived:** 04/24/24
**Matrix:** Solid

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 2.3 | pCi/g-dry | | | | E901.1 | 05/20/24 10:26 / haw |
| Radium 224 precision (±) | 1.3 | pCi/g-dry | | | | E901.1 | 05/20/24 10:26 / haw |
| Radium 224 MDC | 2.0 | pCi/g-dry | | | | E901.1 | 05/20/24 10:26 / haw |
| Radium 226 | 2.3 | pCi/g-dry | | | | E901.1 | 05/20/24 10:26 / haw |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 05/20/24 10:26 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 05/20/24 10:26 / haw |
| Radium 228 | 1 | pCi/g-dry | | | | E901.1 | 05/20/24 10:26 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1 | 05/20/24 10:26 / haw |
| Radium 228 MDC | 0.5 | pCi/g-dry | | | | E901.1 | 05/20/24 10:26 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM TP Soil Characterization
**Lab ID:** C24040791-007
**Client Sample ID:** TP-36 [6-12]

**Report Date:** 05/24/24
**Collection Date:** 04/16/24 11:00
**DateReceived:** 04/24/24
**Matrix:** Solid

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 4.2 | pCi/g-dry | | | | E901.1 | 05/20/24 11:44 / haw |
| Radium 224 precision (±) | 2.3 | pCi/g-dry | | | | E901.1 | 05/20/24 11:44 / haw |
| Radium 224 MDC | 3.6 | pCi/g-dry | | | | E901.1 | 05/20/24 11:44 / haw |
| Radium 226 | 8.8 | pCi/g-dry | | | | E901.1 | 05/20/24 11:44 / haw |
| Radium 226 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/20/24 11:44 / haw |
| Radium 226 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 05/20/24 11:44 / haw |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1 | 05/20/24 11:44 / haw |
| Radium 228 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/20/24 11:44 / haw |
| Radium 228 MDC | 0.7 | pCi/g-dry | | | | E901.1 | 05/20/24 11:44 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM TP Soil Characterization
**Lab ID:** C24040791-008
**Client Sample ID:** TP-41 [6-12]

**Report Date:** 05/24/24
**Collection Date:** 04/16/24 11:15
**DateReceived:** 04/24/24
**Matrix:** Solid

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 2.2 | pCi/g-dry | | | | E901.1 | 05/20/24 13:27 / haw |
| Radium 224 precision (±) | 1.3 | pCi/g-dry | | | | E901.1 | 05/20/24 13:27 / haw |
| Radium 224 MDC | 2.0 | pCi/g-dry | | | | E901.1 | 05/20/24 13:27 / haw |
| Radium 226 | 1.9 | pCi/g-dry | | | | E901.1 | 05/20/24 13:27 / haw |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 05/20/24 13:27 / haw |
| Radium 226 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 05/20/24 13:27 / haw |
| Radium 228 | 1.6 | pCi/g-dry | | | | E901.1 | 05/20/24 13:27 / haw |
| Radium 228 precision (±) | 0.5 | pCi/g-dry | | | | E901.1 | 05/20/24 13:27 / haw |
| Radium 228 MDC | 0.6 | pCi/g-dry | | | | E901.1 | 05/20/24 13:27 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM TP Soil Characterization
**Lab ID:** C24040791-009
**Client Sample ID:** TP-36 [1-2]

**Report Date:** 05/24/24
**Collection Date:** 04/17/24 11:20
**DateReceived:** 04/24/24
**Matrix:** Solid

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.6 | pCi/g-dry | U | | | E901.1 | 05/20/24 16:12 / haw |
| Radium 224 precision (±) | 2.1 | pCi/g-dry | | | | E901.1 | 05/20/24 16:12 / haw |
| Radium 224 MDC | 3.6 | pCi/g-dry | | | | E901.1 | 05/20/24 16:12 / haw |
| Radium 226 | 0.7 | pCi/g-dry | | | | E901.1 | 05/20/24 16:12 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 05/20/24 16:12 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 05/20/24 16:12 / haw |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1 | 05/20/24 16:12 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1 | 05/20/24 16:12 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1 | 05/20/24 16:12 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM TP Soil Characterization
**Lab ID:** C24040791-010
**Client Sample ID:** TP-DS 01

**Report Date:** 05/24/24
**Collection Date:** 04/17/24 13:00
**DateReceived:** 04/24/24
**Matrix:** Solid

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1 | 05/21/24 08:43 / haw |
| Radium 224 precision (±) | 2.2 | pCi/g-dry | | | | E901.1 | 05/21/24 08:43 / haw |
| Radium 224 MDC | 3.6 | pCi/g-dry | | | | E901.1 | 05/21/24 08:43 / haw |
| Radium 226 | 0.8 | pCi/g-dry | | | | E901.1 | 05/21/24 08:43 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1 | 05/21/24 08:43 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1 | 05/21/24 08:43 / haw |
| Radium 228 | 1.1 | pCi/g-dry | | | | E901.1 | 05/21/24 08:43 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1 | 05/21/24 08:43 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1 | 05/21/24 08:43 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected at Minimum Detectable Concentration (MDC)
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation **Work Order:** C24040791 **Report Date:** 05/23/24

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E901.1** | | | | | | | | | | Batch: R306411 |
| **Lab ID: MB-306411** | 9 | Method Blank | | | | Run: GAM-HPGE 2_240516A | | | | 05/16/24 13:03 |
| Radium 224 | | 0.3 | pCi/g-dry | | | | | | | U |
| Radium 224 precision (±) | | 0.9 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 1 | pCi/g-dry | | | | | | | |
| Radium 226 | | 0.1 | pCi/g-dry | | | | | | | U |
| Radium 226 precision (±) | | 0.1 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.2 | pCi/g-dry | | | | | | | |
| Radium 228 | | 0.2 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.2 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.4 | pCi/g-dry | | | | | | | |
| **Lab ID: C24040791-008ADUP** | 9 | Sample Duplicate | | | | Run: GAM-HPGE 2_240516A | | | | 05/20/24 15:10 |
| Radium 224 | | -0.15 | pCi/g-dry | | | | | 230 | 30 | UR |
| Radium 224 precision (±) | | 2.6 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 4.3 | pCi/g-dry | | | | | | | |
| Radium 226 | | 1.8 | pCi/g-dry | | | | | 3.9 | 30 | |
| Radium 226 precision (±) | | 0.26 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.23 | pCi/g-dry | | | | | | | |
| Radium 228 | | 1.7 | pCi/g-dry | | | | | 6.9 | 30 | |
| Radium 228 precision (±) | | 0.44 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.44 | pCi/g-dry | | | | | | | |

- Duplicate RPD for Ra224 is outside of the acceptance range for this analysis. However, the RER is less than or equal to the limit of 3, the RER result is 0.82. The RER result for Ra226 is 0.19 and Ra228 is 0.17.

**Qualifiers:**

RL - Analyte Reporting Limit

ND - Not detected at the Reporting Limit (RL)

R - Relative Percent Difference (RPD) exceeds advisory limit

U - Not detected at Minimum Detectable Concentration (MDC)

# Work Order Receipt Checklist

## Rio Grande Resources Corporation C24040791

| | | | |
|---|---|---|---|
| Login completed by: | Cristen C. Smith | Date Received: | 4/24/2024 |
| Reviewed by: | tjones | Received by: | CCS |
| Reviewed Date: | 4/30/2024 | Carrier name: | FedEx |

| | | | |
|---|---|---|---|
| Shipping container/cooler in good condition? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on all shipping container(s)/cooler(s)? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on all sample bottles? | Yes ☐ | No ☐ | Not Present ☑ |
| Chain of custody present? | Yes ☑ | No ☐ | |
| Chain of custody signed when relinquished and received? | Yes ☑ | No ☐ | |
| Chain of custody agrees with sample labels? | Yes ☑ | No ☐ | |
| Samples in proper container/bottle? | Yes ☑ | No ☐ | |
| Sample containers intact? | Yes ☑ | No ☐ | |
| Sufficient sample volume for indicated test? | Yes ☑ | No ☐ | |
| All samples received within holding time? (Exclude analyses that are considered field parameters such as pH, DO, Res Cl, Sulfite, Ferrous Iron, etc.) | Yes ☑ | No ☐ | |
| Temp Blank received in all shipping container(s)/cooler(s)? | Yes ☑ | No ☐ | Not Applicable ☐ |
| Container/Temp Blank temperature: | 14.9°C No Ice | | |
| Containers requiring zero headspace have no headspace or bubble that is <6mm (1/4"). | Yes ☐ | No ☐ | No VOA vials submitted ☑ |
| Water - pH acceptable upon receipt? | Yes ☐ | No ☐ | Not Applicable ☑ |

### Standard Reporting Procedures:

Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH, Dissolved Oxygen and Residual Chlorine, are qualified as being analyzed outside of recommended holding time.

Solid/soil samples are reported on a wet weight basis (as received) unless specifically indicated. If moisture corrected, data units are typically noted as –dry. For agricultural and mining soil parameters/characteristics, all samples are dried and ground prior to sample analysis.

The reference date for Radon analysis is the sample collection date. The reference date for all other Radiochemical analyses is the analysis date. Radiochemical precision results represent a 2-sigma Total Measurement Uncertainty.

For methods that require zero headspace or require preservation check at the time of analysis due to potential interference, the pH is verified at analysis. Nonconforming sample pH is documented as part of the analysis and included in the sample analysis comments.

### Contact and Corrective Action Comments:

None

# Chain of Custody & Analytical Request Record

Trust our People. Trust our Data.

www.energylab.com



## Account Information (Billing information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☒Email |
| Purchase Order | MT11705 |
| Quote | |
| Bottle Order | |

## Report Information (if different than Account Information)

| | |
|---|---|
| Company/Name | AVM Environmental Services, Inc. |
| Contact | Victor Patel |
| Phone | 505-287-4593 |
| Mailing Address | 1717 Del Norte Blvd |
| City, State, Zip | Grants, NM 87020 |
| Email | vpatelavm@outlook.com |
| Receive Report | ☐Hard Copy ☒Email |

Special Report/Formats: ☐ LEVEL IV ☐NELAC ☐ EDD/EDT (contact laboratory) ☐ Other_____

## Comments

## Project Information

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM TP Soil Characterization |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-4593 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/ Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for Soil | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | TP-11 6"-12" | 11/13/2023 | 1:45 pm | 1 | S | ✓ | | | C24040791 |
| 2 | TP-15B 6"-12" | 11/14/2023 | 8:25 am | 1 | S | ✓ | | | |
| 3 | TP-11 1'-2' | 11/16/2023 | 11:05 am | 1 | S | ✓ | | | |
| 4 | TP-15B 1'-1.5' | 11/16/2023 | 11:35 am | 1 | S | ✓ | | | |
| 5 | TP-41 0"-6" | 04/16/2024 | 8:45 am | 1 | S | ✓ | | | |
| 6 | TP-46 6"-12" | 04/16/2024 | 10:25 am | 1 | S | ✓ | | | |
| 7 | TP-36 6"-12" | 04/16/2024 | 11:00 am | 1 | S | ✓ | | | |
| 8 | TP-41 6"-12" | 04/16/2024 | 11:15 am | 1 | S | ✓ | | | |
| 9 | | | | | | | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were **NOT** used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Victor Patel | 4-22-24/1000 | | | | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Chester Smith | 4/24/24 10:10 | |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

ENERGY LABORATORIES
Trust our People. Trust our Data.

# Chain of Custody & Analytical Request Record

www.energylab.com



## Account Information (Billing information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☒Email |
| Purchase Order | MT11705 |
| Quote | |
| Bottle Order | |

## Report Information (if different than Account Information)

| | |
|---|---|
| Company/Name | AVM Environmental Services, Inc. |
| Contact | Victor Patel |
| Phone | 505-287-4593 |
| Mailing Address | 1717 Del Norte Blvd |
| City, State, Zip | Grants, NM 87020 |
| Email | vpatelavm@outlook.com |
| Receive Report | ☐Hard Copy ☒Email |
| Special Report/Formats: | ☐ LEVEL IV ☐NELAC ☐ EDD/EDT (contact laboratory) ☐ Other_____ |

## Comments

## Project Information

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM TP Soil Characterization |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-4593 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

**Analysis Requested**

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for Soil | See Attached | RUSH TAT | ELI LAB ID Laboratory Use Only |
|---|---|---|---|---|---|---|---|---|---|
| 1 | TP-36 1'-2' | 04/17/2024 | 11:20 am | 1 | S | ✓ | | | C24040791 |
| 2 | TP-DS 01 | 04/17/2024 | 1:00 pm | 1 | S | ✓ | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were **NOT** used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Victor Patel | 4-22-24 / 1000 | | | | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Cristal Smith | 4/24/24 10:10 | |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

# North Controlled Area Soil Radiologic Characterization

**Mt. Taylor Mine Site**
**San Mateo, NM**

**Prepared by:**
**AVM Environmental Services, Inc.**
**1717 Del Norte Blvd.**
**Grants, NM 87020**

**Prepared for:**
**Rio Grande Resource Corporation**
**PO Box 1150**
**Grants, NM 87020**

**June 5, 2025**

## Table of Contents

1.0 Introduction and Background ..... 1
2.0 Previous Radiologic Characterization ..... 1
3.0 Objective of the Radiologic Characterization ..... 2
4.0 Field Investigation ..... 2
4.1 Surface Gamma Radiation Scan and Static Survey ..... 2
4.2 Soil Sampling and Ex-Situ Gamma Radiation Soil Screening ..... 4
4.3 North Controlled Area Characterization Summary ..... 5
4.3.1 Mine Water Treatment Area Characterization Summary ..... 6
4.3.2 Marquez Arroyo Bed Characterization Summary ..... 6
4.3.3 Ore Retention Pond Characterization Summary ..... 6
4.3.4 North Diversion Channel Characterization Summary ..... 7
4.3.5 Borrow Area A Characterization Summary ..... 7
5.0 Soil Sampling and Analysis ..... 7
6.0 Quality Assurance and Quality Control Measures ..... 8

## Tables

Table 1 Typical Gamma Scan Data Exported from Scan System Data Logger
Table 2 Static Surface Gamma Radiation Survey at Data Point/Test Pit Locations
Table 3 North Controlled Area Characterization Area Soil Sample Field Ex-Situ Gamma Screening and Vendor Laboratory Results Summary
Table 4 North Controlled Area Surface and Subsurface Soil Ra-226 Level Summary

## Figures

Figure 1 North Controlled Area Soil Radiologic Characterization Area
Figure 2 North Controlled Area Surface Soil Gamma Scan Survey Data
Figure 3 North Controlled Area Data Point Locations and Gamma Scan Survey Data
Figure 4 North Controlled Area Data Point Locations and Gamma Scan Survey Data with Ra-226 Concentration Depth Exceeding the Investigation Level
Figure 3 North Controlled Area Contamination Depths Exceeding the 6.8 pCi/g Ra-226 Investigation Level

## Appendices

Appendix A Surface and Subsurface Contamination Field Investigation Documentation (Soil Sample Log Forms, Field Soil Sample Ex-Situ Gamma Radiation Screening Forms)
Appendix B Radiologic Instrument Calibration, Operational Function Check, and Collimated Detector Correlation Documentation
Appendix C Soil Sample COC and Laboratory Analytical Results Report

## 1.0 Introduction and Background

This report provides the results of the North Controlled Area (NCA) Soil Radiologic Characterization (SRC) that was conducted at the Mt. Taylor Mine (Site) in Cibola County, near San Mateo, New Mexico. This NCA SRC was performed to check the status and estimate radiologic contamination in soil exceeding the Site Radiation Cleanup Criteria (RCC) of 6.8 pCi/g Radium (Ra)-226, which is also used as the Site Investigation Level (IL). The NCA SRC area includes the Mine Water Treatment Area, the Ore Pad Runoff Retention Pond, the North Diversion Channel, Borrow Area A, the Marquez Arroyo bed, and the area between the Marquez Arroyo and the northern boundary fence of the NCA. The previously characterized Mine Water Treatment Ponds (1, 4, 5, 6, 7 & 8), the Ore Pad Area and the two active Mine Water Treatment Ponds (2 & 3) are not included in this NCA SRC. The methods and procedures used were consistent with the agency May 2022 approved June 2020 Work Plan for Post-Mining Radiological Surveys of Permit Area and Impacted Lands (Work Plan), and the applicable survey methods described in the Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM, EPA 2000a). The RCC specified in the March 2016 *Joint Guidance for the Cleanup and Reclamation of Existing Uranium Mining Operations in New Mexico* (EMNRD, 2016) (2016 Guidance) by the Energy, Minerals & Natural Resources Department (EMNRD) and the New Mexico Environment Department (NMED) was used for the investigation level (IL) the NCA SRC. The Ra-226 cleanup criteria of 5.0 pCi/g above the background level in land averaged over 100 square meters in surface soil (top six inches) specified in the Joint Guidance is taken from the UMTRCA (40 CFR 192) regulation, which is based on an unrestricted land use exposure scenario. A 6.8 pCi/g Ra-226 IL (5.0 pCi/g plus 1.8 pCi/g background level) has been established for the Site.

The Site was an underground uranium mine located in Cibola County, near San Mateo, New Mexico. The mine was developed by Gulf Mineral Resources Company (Gulf) in the 1970s and ore production occurred from 1979 to 1982. Following the transfer of the Site to Chevron Resources Company in 1985, the ore production resumed and continued until 1990. Rio Grande Resources (RGR) acquired the Site in 1991. In 1999 the Site entered standby status under Mine Permit C1002RE with EMNRD. On December 29, 2017, the permit changed to an active status, and on December 3, 2019, RGR notified EMNRD of intentions to begin the Site closeout/closure process. The following sections describe the strategy, methods and procedures that were used and the results of the NCA SRC conducted at the Site.

## 2.0 Previous Radiologic Characterizations

Surface gamma radiation surveys were performed periodically within operationally controlled areas of the Site, including the NCA, to monitor changes in radiological conditions during a period of remedial excavations in the Mine Water Treatment Ponds, construction of the disposal cell, placement of contaminated mine materials, and the gradual removal of ore from the Ore Pad stockpile. The most recent gamma survey in this area prior to this characterization was conducted in March 2020 and showed gamma radiation levels exceeding the 6.8 pCi/g Ra-226 IL in numerous areas at the Site, including areas within the NCA. The 2020 gamma survey results are summarized in the Work Plan.

## 3.0 Objective of the Soil Radiological Characterization

The Site is a former uranium mine, therefore the surface and subsurface soil is expected to be impacted by radionuclides associated with the uranium decay series, with Ra-226 being the primary Constituent of Concern (COC). The objective of this characterization is to evaluate Ra-226 contamination exceeding the 6.8 pCi/g Ra-226 IL in surface and subsurface soils to facilitate the estimation of the volume of radiologic impacted soil within the NCA SRC area.

## 4.0 Field Investigation

Field investigations for this NCA SRC were conducted consistent with the Work Plan and were performed during the period of July 2024 through January 2025. The field investigation included both 0.5-inch thick lead collimated and bare (uncollimated) 2x2 sodium iodide (NaI) detector Differential Global Positioning System (DGPS) based gamma radiation scan surveys, and measurements. Additionally, static gamma radiation surveys, soil sampling, ex-situ soil screening, and offsite vendor laboratory confirmatory sample analysis were utilized during this SRC. The DGPS based gamma scan surveys were conducted to provide lateral Ra-226 concentration level estimates in surface soils. To assess subsurface radiological contamination, areas of potentially similar vertical extent of contamination were selected based on the DGPS gamma scan surveys, and data point (static gamma survey and subsurface soil samples) locations were selected to provide an area contamination depth profile estimation. Ex-situ gamma radiation soil screening was performed on the soil samples collected to provide real-time information to estimate surface and subsurface Ra-226 contamination levels. Offsite vender laboratory soil sample analysis was utilized to confirm the contamination levels estimated by ex-situ soil screening.

### 4.1 Surface Gamma Radiation Scan and Static Surveys

The instrument configuration used for direct gamma radiation level measurements during this characterization consisted of 0.5 inch thick lead collimated and bare 2x2 NaI scintillation detectors (Eberline SPA-3 or Ludlum 44-10) coupled to a scaler/rate meter, such as a Ludlum 2221 or Ludlum 2241. This instrument configuration is widely used for this type of survey and is recommended by the MARSSIM. The scaler/rate meters were interfaced with a sub-meter accurate DGPS with surveying software and a data logger/controller for electronically recording the gamma radiation levels to the corresponding geo-location coordinates. The coordinate system used for this work was the State Plane Coordinate System (NAD83, New Mexico West, US Feet) system. The direct gamma radiation surveys using a NaI scintillation detector provide radiation levels in counts per minute (cpm).

During this characterization, systematic gamma radiation scan surveys using bare 2x2 NaI detectors were performed at the Site to estimate the level of Ra-226 in surface soil within the characterization areas. Although bare detectors do not avoid lateral gamma radiation shine, bare detectors have a large field of view and provide a large scan coverage area for an efficient and conservative lateral extent of

contamination assessment. To better characterize the surface soil and to assist in the selection of data point locations, the surface gamma scan survey was performed at a higher density, 25-feet transect spacing, compared to the March 2020 scan density of about 60-ft transect spacing. Based on a conservative field of view (FOV) of about ten feet diameter for a bare 2x2 NaI detector for Ra-226 gamma radiation, scanning transects spacing of 25 feet would provide at least a 40% scan coverage, which is sufficient to identify and characterize any surface soil contamination. The gamma scan survey was performed by scanning along these transects with the detector at 12 inches above the ground surface at a scan rate of about three feet per second, with a data collection time interval of two seconds. A Bare detector gamma scan survey was performed in areas away from the Ore Pad, which could result in lateral gamma radiation shine. In areas near the Ore Pad, a 0.5 inch thick lead collimated detector was used to mitigate lateral gamma radiation shine. The bare/collimated detector gamma scan boundary is shown in Figure 2.

Twenty-five feet spaced geo-projected transects within the NCA were digitally created using a mapping software and loaded on the field data logger/controller. During this characterization, a gamma scan survey was not conducted in the Ore Pad Runoff Retention Pond since previous gamma scan surveys showed uniformly and significantly elevated measurements compared to the IL, making additional surface gamma scan surveys unnecessary in assisting with selecting data point locations for subsurface investigation.

The geo-located gamma scan data includes the gamma scan point ID number, date and time, location coordinates, and detector cpm. The scan data was exported from the data logger and the bare detector cpm were converted to equivalent Ra-226 estimate using the Site-specific correlation (Ra-226 pCi/g = 0.0005 x CPM)-7.32 $R^2$ = 0.97). The collimated detector cpm data was converted to equivalent Ra-226 estimate using the Site-specific correlation (Ra-226 pCi/g = 0.0016 x CPM)-7.5 $R^2$ = 0.83). The 20,357 discrete gamma scan points collected during the gamma scan survey were exported from the scan system and the detector cpm data was converted into the equivalent estimated surface soil Ra-226 pCi/g concentration using the appropriate Site-specific correlation. The data was then plotted using a mapping software, shown in Figure 2, and arranged in graduated color ranges, then reviewed to identify areas that exceeded the Ra-226 IL. A typical gamma scan data export table from the scan system data logger is shown in Table 1. Gamma scan survey data collected during this characterization are provided in an electronic file.

As previously discussed, areas of potentially similar vertical extent of contamination were selected based on the DGPS gamma scan surveys. A total of forty test pit (TP) data point locations, shown in Figure 3, were selected within these areas for the estimation of the vertical extent of Ra-226 contamination above IL. A one-minute collimated detector static gamma radiation survey was performed to estimate surface soil Ra-226 levels prior to collecting any soil samples at each data point location. Of the 40 TP data point locations, two were in the Ore Pad Retention Pond and one was located in the bed of the Marquez Arroyo. Additionally, seven investigation (INV) data point locations were selected where gamma scan surveys showed an isolated area with Ra-226 levels slightly above the IL. The investigation (INV) locations were inspected and one-minute collimated detector static gamma measurements were performed to determine if subsurface soil sampling was necessary. The survey data was recorded on Static Gamma Radiation Survey

Forms, which are included in Appendix A. The collimated detector measurements were converted to soil Ra-226 concentrations using the correlation equation for the collimated detector. The static gamma survey results are summarized in Table 2.

### 4.2 Soil Sampling and Ex-Situ Gamma Radiation Soil Screening

Soil sampling and on-site ex-situ gamma radiation soil screening were performed during October 2024 to January 2025 to estimate the subsurface soil Ra-226 contamination exceeding the IL. Surface (0 to 6 inches) soil samples were not collected at the data points during this characterization. The estimated surface soil Ra-226 level was determined from one-minute collimated detector static gamma radiation surveys. A one-minute collimated detector static gamma radiation survey provides a significantly higher certainty for a surface soil Ra-226 estimate than a two second integration gamma radiation scan survey provides. The use of a collimated detector mitigates any lateral gamma radiation shine from any nearby elevated concentration areas

Ex-situ gamma radiation soil screening was conducted to provide a real-time estimate of Ra-226 concentrations in soil samples to determine depth of subsurface soil sampling. This method is more reliable than in-situ direct gamma radiation level measurements and allows for a more reliable real-time Ra-226 concentration assessment. The on-site ex-situ soil screening method consists of selectively measuring the 609 KeV region gamma radiation of Bi-214, a decay product of Ra-226. A single channel analyzer (Ludlum L2221 or Ludlum 3003) integrated with a Ludlum 44-20 3x3 NaI scintillation detector was used to measure the 609 keV energy peak region of Bi-214. The soil sample was placed around the plastic lined detector in a heavily lead shielded counting chamber. The heavily shielded counting chamber lowers the system background counts thus, improving the system's minimum detectable concentration (MDC). A reference soil with the Ra-226 concentration of 6.6 pCi/g, comparable to the 6.8 pCi/g IL, was prepared and was used for soil screening during this characterization. The 6.6 pCi/g reference soil provides a conservative estimate of Ra-226 concentration in samples below the IL.

Subsurface soil samples were collected from each of the 47 data point (TP & INV) locations. The number and depth of the samples at each data point location varied depending upon location and soil screening results. A backhoe was used to excavate a trench for subsurface soil sample collection at each selected data point location, except for the subsurface soil samples collected from the Ore Retention Pond Bottom (TP-21 and TP-26), the North Diversion Channel Bed (TP-32 and TP-34), the Marquez Arroyo (TP-30), and the area between the Marquez Arroyo and the northern NCA boundary fence (TP-17, TP-25 and TP-33). At these locations, a hand auger was used to collect the subsurface soil samples since backhoe access was not practical. The trenches were excavated in approximately 6 to 12 inches depth intervals, depending on soil type and visual observations. At each interval, a subsurface soil sample was collected from the base of the excavation for ex-situ gamma radiation soil screening. Stainless steel sampling trowels, bowls and sieves were used to collect the soil samples. The excavation continued until on-site ex-situ gamma radiation soil screening indicated that Ra-226 concentrations were below the 6.8 pCi/g IL. The soil sample

logs and the field soil screening forms are included in Appendix A. The ex-situ gamma radiation screening data is summarized in Table 3, which includes estimated Ra-226 concentrations of the samples relative to the 6.8 pCi/g IL.

At 34 of the 47 data point locations, a 6-12 inch below ground surface (bgs) subsurface soil sample was collected, and ex-situ soil gamma screened. Furthermore, at five of those 37 data point locations, a subsurface soil sample at a depth of 1-2 feet bgs was collected and ex-situ soil screened since the 6–12-inch bgs subsurface sample soil screening result was above the IL. The subsurface soil samples from the two data point locations on the bottom of the Ore Retention Pond were collected at a depth of 3-4 feet below ground surface (bgs) since the shallow subsurface sample screening result was above the IL. At location TP-19, a subsurface soil sample was collected at a depth of 4.5 to 5.0 feet bgs since waste rock was observed from the ground surface to a depth of 4.5 feet bgs. An additional subsurface soil sample was collected at TP-19 at 5.0-5.5 feet bgs to confirm that the soil below 4.5 feet bgs is below the 6.8 pCi/g IL.

Although the primary objective of the ex-situ gamma radiation soil screening was to determine the Ra-226 concentrations above or below the 6.8 pCi/g IL, Ra-226 concentrations were estimated in all soil samples collected and screened. A calibration/correlation of the ex-situ soil screening system was performed using a 6.6 pCi/g, a 25 pCi/g and a 50 pCi/g reference soil. This correlation is included in Appendix B. The estimated Ra-226 concentrations of the subsurface soil samples are included in Tables 3 and 4.

A total of twelve, including one field quality assurance/quality check (QA/QC) duplicate, of the soil samples that were ex-situ gamma radiation soil screened on-site were sent to an offsite vendor laboratory for analysis, Energy Laboratories, in Casper, WY. These soil samples were analyzed for Ra-226 using EPA Method 901.1 (modified for soil matrix) for confirmation of the on-site ex-situ soil screening results. The laboratory results report is included in Appendix C and are summarized in Table 3. As shown in the table, the estimated Ra-226 levels determined by the on-site ex-situ soil screening are comparable with the vendor laboratory Ra-226 results, specifically in regards to determining that the Ra-226 levels are above or below the IL.

### 4.3 NCA Characterization Summary

As described previously, this NCA SRC included the areas shown in Figure 1. The entire NCA SRC area consists of approximately 46 acres. The soil in approximately a 23 acre area is below the 6.8 pCi/g Ra-226 IL. In the remaining 23 acre area, the soil exceeds the IL and ranges from the ground surface to a depth of 4.5 feet bgs. The depth of soil exceeding the IL at each data point (TP and INV) are summarized in Table 4 and shown in Figure 4. Figure 5 shows areas within the characterization area with soil exceeding the IL at various contamination depths. The areas and estimated volume of in-situ soil exceeding the IL within this characterization are summarized in Table 5. The excavated volume of soil exceeding the IL may be higher than the estimated in-situ volume due to the swell factor and the excavation equipment and technique used.

### 4.3.1 Mine Water Treatment Area Characterization Summary

The Mine Water Treatment Area consists of approximately 31 acres. Included in this area is the area between the Marquez Arroyo and the NCA fence. As shown in Figure 2, the gamma scan survey showed that the soil in the area generally west of the Treatment Ponds 4, 5, 6, and 7 is below the 6.8 pCi/g Ra-226 IL, except for a few isolated small areas. In these small isolated areas, the soil exceeding the IL ranges from 0.5 feet to 3.5 feet. The depth of soil exceeding the IL in the middle of the Mine Water Treatment Area, the area surrounding the Treatment and Active Ponds, generally ranged from 0.5 feet to 1.5 feet. The depth of soil exceeding the IL in the eastern section of the area, the areas near the Ore Pad and Ore Retention Pond, generally ranged from 0.5 feet to 4.5 feet.

### 4.3.2 Marquez Arroyo Bed Characterization Summary

A gamma scan survey of the Marquez Arroyo bed surface was conducted using a 0.5-inch lead collimated detector to mitigate any gamma radiation shine from the walls of the arroyo. As shown in Figure 2, there are only a few isolated locations that showed Ra-226 levels just above the IL. As shown in Table 2, the collimated detector gamma static survey at those isolated spots showed the bed surface soils well below the IL. A subsurface soil sample at a depth of 0.5 to 1.0 foot bgs was collected using a hand auger at the highest static gamma survey result location, TP-30. The gamma soil screening of the subsurface soil sample showed Ra-226 levels well below the IL. The Marquez Arroyo bed soil is below the Ra-226 IL.

### 4.3.3 Ore Retention Pond Characterization Summary

A gamma scan survey within the Ore Pad Retention Pond was not conducted because the 2020 gamma scan showed that the pond bottom surface soil has significantly elevated levels of Ra-226 above the IL. The two locations (TP-21 & TP-26) from the bottom of the pond were selected for subsurface characterization. The collimated detector static gamma survey at these two locations confirmed that the surface soil Ra-226 levels are significantly above the IL. Because of practical concerns for backhoe access into the Ore Retention Pond, subsurface soil samples were collected using a hand auger. As shown in Table 4 and Figure 4, the pond bottom subsurface soil sample gamma screening results show the Ra-226 level exceeding the IL range from two feet bgs at TP-21 to three feet at TP-26 bgs. The ground surface elevation at TP-26 is about one foot higher than at TP-21. The Ore Retention Pond crest and the outside slopes of the dikes are covered by an approximate one-foot layer of soil which is slightly above the IL. Waste rock was observed under the approximately one-foot soil layer. Waste rock is visible on the inside slope of the dikes from the crest to the base. It is likely that the entire dike profile and approximately one foot bgs under the dike base are likely to exceed the Ra-226 IL. Table 5 does not include the approximate volume of the Ore Retention Pond dikes impacted soil.

### 4.3.4 North Diversion Channel Characterization Summary

A lead collimated detector gamma scan survey of the banks and bed of the North Diversion Channel was conducted and showed the surface soil Ra-226 levels are above the IL. The western berm of the channel is adjacent the Ore Pad and exceeds the Ra-226 IL through its entire depth profile. The depth of Ra-226 levels above the IL in the eastern berm ranges from 0.5 to 1.0 foot bgs. As shown in Figures 4 and 5, the depth of Ra-226 levels exceeding the IL in the North Diversion Channel bed ranges from one to two feet bgs.

### 4.3.5 Borrow Area A Characterization Summary

As shown in Figure 2, the collimated detector gamma scan survey of Borrow Area A showed surface soil that exceeds the Ra-226 IL along the western, northern and southern perimeter areas. The subsurface soil samples and ex-situ gamma soil screening results show that the soil exceeding the Ra-226 IL is generally limited to 0.5-foot bgs, except for a small area near the southeast corner of the Borrow Area A, where the Ra-226 level exceeds the IL at a depth of about one-foot bgs. During the gamma scan of the Borrow Area A, scattered debris was observed on the surface and some debris such as cables and pipes were protruding out of the ground surface along the perimeter of the area. Additionally, at data point location TP-38, a subsurface soil sample was not collected due to the presence of metal debris restricting excavation past approximately 8 inches bgs. It is likely that the soil around buried debris may have soil Ra-226 levels above the IL. A magnetometer survey of the area may be necessary to locate any buried debris.

## 5.0 Soil Sampling and Analysis

Soil samples from the NCA collected for on-site ex-situ gamma radiation soil screening were collected consistent with the Work Plan. Field QA/QC duplicate samples were ex-situ gamma radiation soil screened at a frequency of 10% of the total number of soil samples screened. A total of 70 surface and subsurface soil samples were collected for the NCA characterization. Field sampling equipment used for soil sampling included: stainless steel scoops, hand auger, bowls, sieve, and spoons that were decontaminated between sample locations. The soil sampling equipment decontamination was conducted by brushing off loose visible soil and when necessary was rinsed with distilled water, then wiped with clean towels. The rinsed water was disposed of in Active Pond No. 2. Excavator buckets were cleaned by removing any loose, visible soil. Any soils excavated from the test pits were returned to the test pit excavations from which the soil came. Personal protection equipment (PPE), such as gloves, were brushed off and scanned for residual contamination and were disposed of.

Subsurface soil samples were analyzed by on-site ex-situ gamma radiation soil screening to estimate Ra-226 concentrations. Twelve QA/QC confirmatory soil samples were placed in labeled Ziploc bags and packaged along with a completed chain of custody in a cooler with a custody sealed lid and shipped to Energy Laboratories, Inc for Ra-226 analysis. The soil samples were analyzed for Ra-226 with a reporting limit of

0.5 pCi/g, using EPA Method 901.1 (modified for soil matrix). The completed chain of custody and the analytical results are included in Appendix C.

## 6. 0 Quality Assurance and Quality Control Measures

QA/QC measures were implemented during this characterization to ensure that decisions were made based on data of acceptable quality. All radiologic survey instruments have been calibrated at least annually. Additionally, operational functions checks were performed on all radiologic instruments daily prior to use. The calibration and function check documents are included in Appendix B. During this characterization, no instruments were found to be out of calibration or inoperable as indicated by the operational function checks. The instrument background measurements for bare 2x2 NaI detectors during daily operational function checks were less than 10,000 cpm as shown in Appendix B. The bare detector field of view (FOV) at 12 inches above the ground surface is conservatively assumed at an area of six feet diameter. The 2x2 NaI detector response factor is determined to be 0.0005 pCi/g/cpm from the linear regression for the Site-specific correlation included in Appendix B. Based on the above detector parameters, the Ra-226 minimum detectable concentrations (MDCs) for a scan survey at a scan speed of three feet per second, calculated using MARSSIM guidance, were less than 1.0 pCi/g, which is significantly below 50% of the 6.8 pCi/g IL. The instrument background measurements for the 0.5 inch thick lead collimated 2x2 NaI detectors during daily operational function checks were less than 3,200 cpm, as shown in Appendix B. The collimated detector field of view (FOV) at 12 inches above the ground surface is conservatively assumed at an area of 1.5 feet diameter. The collimated 2x2 NaI detector response factor is determined to be 625 cpm/pCi/g from the linear regression for the Site-specific correlation included in Appendix B. Based on the above collimated detector parameters, the Ra-226 minimum detectable concentrations (MDCs) for a one minute static survey, calculated using MARSSIM guidance, was less than 0.5 pCi/g, which is significantly below 50% of the 6.8 pCi/g IL. The ex-situ soil gamma radiation screening system was calibrated prior to mobilization in the field and daily operational function checks were performed prior to use. The calibration and function check documentation are included in Appendix B. Based on the highest system background (blank) measurements from daily operational function checks and efficiency (pCi/g/cpm), the highest Ra-226 MDC for the screening system calculated was less than 1.0 pCi/g, significantly less than the 6.8 pCi/g IL. The MDCs during the supplemental characterization met the QA objective.

The QA/QC measures also included twelve field QA/QC duplicate soil samples out of the 58 soil samples collected sent to the off-site vendor laboratory for analysis to confirm contamination relative to the IL levels estimated by the field ex-situ gamma radiation soil screening. The QA/QC duplicate vendor laboratory results are included in Table 3. All QA/QC sample results confirm Ra-226 concentration levels relative to the IL level determined by the field ex-situ gamma radiation soil screening. The Ra-226 concentration in QA/QC duplicate samples estimated by on-sit ex-situ gamma radiation soil screening are comparable to the off-site vendor laboratory analytical results.

# Tables

## Table 1
## Mt. Taylor Mine Site - North Controlled Area Soil Radiological Characterization
## Typical Gamma Scan Data Exported from the Scan System Data Logger

| ID | Time | Northing[(1)] (feet) | Easting[(1)] (feet) | MSL Elevation (feet) | CPM 2x2 Bare NaI Detector | Ra-226 pCi/g[(2)] | Zone_ID |
|---|---|---|---|---|---|---|---|
| 1 | 7/15/2024 9:44 | 1579480.37 | 2781608.42 | 7313 | 18924 | 2.14 | North_Control_Area |
| 2 | 7/15/2024 9:44 | 1579481.43 | 2781608.84 | 7313 | 17734 | 1.55 | North_Control_Area |
| 3 | 7/15/2024 9:44 | 1579482.53 | 2781611.48 | 7313 | 17983 | 1.67 | North_Control_Area |
| 4 | 7/15/2024 9:44 | 1579482.66 | 2781614.68 | 7313 | 18419 | 1.89 | North_Control_Area |
| 5 | 7/15/2024 9:45 | 1579480.86 | 2781617.51 | 7313 | 15123 | 0.60 | North_Control_Area |
| 6 | 7/15/2024 9:45 | 1579480.45 | 2781620.08 | 7313 | 17737 | 1.55 | North_Control_Area |
| 7 | 7/15/2024 9:45 | 1579480.19 | 2781620.09 | 7313 | 17526 | 1.44 | North_Control_Area |
| 8 | 7/15/2024 9:45 | 1579480.18 | 2781621.42 | 7313 | 17508 | 1.43 | North_Control_Area |
| 9 | 7/15/2024 9:45 | 1579480.46 | 2781624.34 | 7313 | 17811 | 1.59 | North_Control_Area |
| 10 | 7/15/2024 9:45 | 1579481.46 | 2781626.49 | 7313 | 17170 | 1.27 | North_Control_Area |
| 11 | 7/15/2024 9:45 | 1579482.91 | 2781628.77 | 7313 | 18518 | 1.94 | North_Control_Area |
| 12 | 7/15/2024 9:45 | 1579483.80 | 2781631.28 | 7313 | 17297 | 1.33 | North_Control_Area |
| 13 | 7/15/2024 9:45 | 1579483.15 | 2781634.57 | 7313 | 18091 | 1.73 | North_Control_Area |
| 14 | 7/15/2024 9:45 | 1579482.23 | 2781637.63 | 7313 | 17840 | 1.60 | North_Control_Area |
| 15 | 7/15/2024 9:45 | 1579480.18 | 2781638.20 | 7313 | 21050 | 3.21 | North_Control_Area |
| 16 | 7/15/2024 9:45 | 1579477.12 | 2781637.47 | 7313 | 17418 | 1.39 | North_Control_Area |
| 17 | 7/15/2024 9:45 | 1579474.30 | 2781641.18 | 7314 | 17603 | 1.48 | North_Control_Area |
| 18 | 7/15/2024 9:45 | 1579474.52 | 2781645.76 | 7314 | 16122 | 0.74 | North_Control_Area |
| 19 | 7/15/2024 9:45 | 1579476.86 | 2781649.32 | 7314 | 17957 | 1.66 | North_Control_Area |
| 20 | 7/15/2024 9:45 | 1579479.59 | 2781651.61 | 7314 | 17082 | 1.22 | North_Control_Area |
| 21 | 7/15/2024 9:45 | 1579483.79 | 2781652.22 | 7314 | 18520 | 1.94 | North_Control_Area |
| 22 | 7/15/2024 9:45 | 1579485.62 | 2781655.27 | 7314 | 19757 | 2.56 | North_Control_Area |
| 23 | 7/15/2024 9:45 | 1579486.09 | 2781659.48 | 7314 | 22257 | 3.81 | North_Control_Area |
| 24 | 7/15/2024 9:46 | 1579485.52 | 2781665.29 | 7314 | 17688 | 1.52 | North_Control_Area |
| 25 | 7/15/2024 9:46 | 1579484.31 | 2781666.71 | 7315 | 17440 | 1.40 | North_Control_Area |
| 26 | 7/15/2024 9:46 | 1579483.20 | 2781672.84 | 7315 | 16720 | 1.04 | North_Control_Area |
| 27 | 7/15/2024 9:46 | 1579482.38 | 2781677.17 | 7315 | 18212 | 1.79 | North_Control_Area |
| 28 | 7/15/2024 9:46 | 1579482.68 | 2781681.44 | 7315 | 19918 | 2.64 | North_Control_Area |
| 29 | 7/15/2024 9:46 | 1579483.18 | 2781685.24 | 7315 | 18825 | 2.09 | North_Control_Area |
| 30 | 7/15/2024 9:46 | 1579482.84 | 2781689.59 | 7315 | 18951 | 2.16 | North_Control_Area |
| 31 | 7/15/2024 9:46 | 1579481.31 | 2781693.89 | 7315 | 19597 | 2.48 | North_Control_Area |
| 32 | 7/15/2024 9:46 | 1579481.72 | 2781698.27 | 7315 | 18782 | 2.07 | North_Control_Area |
| 33 | 7/15/2024 9:46 | 1579483.49 | 2781702.34 | 7315 | 18723 | 2.04 | North_Control_Area |
| 34 | 7/15/2024 9:46 | 1579485.29 | 2781706.70 | 7315 | 18615 | 1.99 | North_Control_Area |
| 35 | 7/15/2024 9:46 | 1579485.28 | 2781711.19 | 7315 | 18751 | 2.06 | North_Control_Area |
| 36 | 7/15/2024 9:46 | 1579483.10 | 2781715.08 | 7315 | 20342 | 2.85 | North_Control_Area |
| 37 | 7/15/2024 9:46 | 1579483.94 | 2781719.09 | 7315 | 18866 | 2.11 | North_Control_Area |
| 38 | 7/15/2024 9:46 | 1579483.31 | 2781722.44 | 7316 | 19876 | 2.62 | North_Control_Area |
| 39 | 7/15/2024 9:46 | 1579483.93 | 2781726.44 | 7316 | 20314 | 2.84 | North_Control_Area |
| 40 | 7/15/2024 9:46 | 1579485.57 | 2781730.70 | 7316 | 19959 | 2.66 | North_Control_Area |

(1) projection: StatePlane NAD 1983 NM West - Feet

(2) Ra-226 pCi/g determined from surface soil gamma radiation scan using 2x2 NaI detector and Site-specific gamma radiation level (cpm) correlation

**Table 2**
**Mt. Taylor Mine Site - North Controlled Area Soil Radiological Characterization**
**Static Gamma Radiation Survey at Data Point/Soil Sample Locations**

| Data Point ID | Survey Date | Data Point Coordinate NAD83 StatePlane NM West, Feet | | Static Gamma Radiation Survey Collimated (0.5" PB) 2x2 Detector | |
|---|---|---|---|---|---|
| | | Northing | Easting | Static Gamma CPM | Surface Soil Static Gamma Estimated Ra-226 pCi/g |
| TP-01 | 9/19/2024 | 1580186.76 | 2781641.72 | 74549 | 111.8 |
| TP-02 | 9/19/2024 | 1581347.96 | 2781655.87 | 23242 | 29.7 |
| TP-03 | 9/19/2024 | 1581200.16 | 2781928.52 | 12217 | 12.0 |
| TP-04 | 9/19/2024 | 1580830.01 | 2781918.97 | 11677 | 11.2 |
| TP-05 | 9/19/2024 | 1580644.14 | 2781961.31 | 7643 | 4.7 |
| TP-06 | 9/19/2024 | 1579534.44 | 2782004.83 | 28795 | 38.6 |
| TP-07 | 9/19/2024 | 1580612.66 | 2782033.15 | 7755 | 4.9 |
| TP-08 | 9/19/2024 | 1580712.40 | 2782055.84 | 9500 | 7.7 |
| TP-09 | 11/25/2024 | 1579887.40 | 2782299.57 | 26878 | 35.5 |
| TP-10 | 9/19/2024 | 1580089.57 | 2782156.92 | 10215 | 8.8 |
| TP-11 | 9/19/2024 | 1580893.36 | 2782211.56 | 17075 | 19.8 |
| TP-12 | 9/19/2024 | 1580498.58 | 2782193.94 | 7687 | 4.8 |
| TP-13 | 9/19/2024 | 1581025.34 | 2782214.93 | 25917 | 34.0 |
| TP-14 | 9/19/2024 | 1581007.22 | 2782310.10 | 31693 | 43.2 |
| TP-15 | 9/19/2024 | 1580839.32 | 2782323.98 | 10771 | 9.7 |
| TP-16 | 9/19/2024 | 1580514.25 | 2782350.77 | 20877 | 25.9 |
| TP-17 | 11/22/2024 | 1581231.06 | 2782360.91 | 9788 | 8.2 |
| TP-18 | 9/19/2024 | 1580678.19 | 2782412.82 | 23920 | 30.8 |
| TP-19 | 9/19/2024 | 1581111.05 | 2782512.59 | 108929 | 166.8 |
| TP-20 | 9/19/2024 | 1580575.91 | 2782540.15 | 42042 | 59.8 |
| TP-21 | 1/27/2025 | 1580826.78 | 2782605.83 | 189626 | 295.9 |
| TP-22 | 9/19/2024 | 1580005.97 | 2782577.72 | 27679 | 36.8 |
| TP-23 | 10/28/2024 | 1580933.72 | 2782615.38 | 11721 | 11.3 |
| TP-24 | 9/19/2024 | 1580664.84 | 2782653.22 | 184511 | 287.7 |
| TP-25 | 11/22/2024 | 1581176.90 | 2782660.86 | 15304 | 17.0 |
| TP-26 | 12/12/2024 | 1580859.02 | 2782663.51 | 154801 | 240.2 |
| TP-27 | 9/19/2024 | 1580481.71 | 2782702.25 | 116173 | 178.4 |
| TP-28 | 9/19/2024 | 1581078.62 | 2782722.31 | 69269 | 103.3 |
| TP-29 | 9/19/2024 | 1580104.95 | 2782715.01 | 37349 | 52.3 |
| TP-30 | 12/2/2024 | 1581088.55 | 2782875.42 | 7362 | 4.3 |
| TP-31 | 11/25/2024 | 1580996.95 | 2783152.31 | 76057 | 114.2 |
| TP-32 | 12/12/2024 | 1580437.62 | 2783254.26 | 11869 | 11.5 |
| TP-33 | 11/25/2024 | 1581081.58 | 2783299.76 | 11765 | 11.3 |
| TP-34 | 12/12/2024 | 1580838.74 | 2783312.73 | 18951 | 22.8 |
| TP-35 | 10/23/2024 | 1580623.09 | 2783328.09 | 31729 | 43.3 |
| TP-36 | 10/23/2024 | 1580793.59 | 2783353.65 | 12576 | 12.6 |
| TP-37 | 10/23/2024 | 1580494.41 | 2783389.94 | 9058 | 7.0 |
| TP-38 | 10/23/2024 | 1581073.21 | 2783415.97 | 13769 | 14.5 |
| TP-39 | 10/23/2024 | 1580478.54 | 2783504.44 | 9606 | 7.9 |
| TP-40 | 10/23/2024 | 1581112.23 | 2783628.43 | 13072 | 13.4 |
| Inv-01 | 9/19/2024 | 1580780.75 | 2781697.35 | 14304 | 15.4 |
| Inv-02 | 9/19/2024 | 1579936.57 | 2781697.29 | 9200 | 7.2 |
| Inv-03 | 9/19/2024 | 1581223.91 | 2781793.57 | 13157 | 13.6 |
| Inv-04 | 9/19/2024 | 1580827.72 | 2782178.60 | 36695 | 51.2 |
| Inv-05 | 10/23/2024 | 1580653.58 | 2783716.79 | 7441 | 4.4 |
| Inv-06 | 10/23/2024 | 1581080.53 | 2783861.07 | 19774 | 24.1 |
| Inv-07 | 9/19/2024 | 1580754.28 | 2781792.25 | 10142 | 8.7 |

# Table 3

## North Controlled Area Radiological Characterization Soil Sample Field Ex-Situ Screening and Vendor Laboratory Results Summary

| Sample Data | | | | | Field Soil Screening Data | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | Soil IL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| TP-01 | 6"-12" | 10/8/2024 | 930 | Brown silt/sand compacted | 10/8/2024 | 3000 | 1437 | 287 | 3.1 | < | yes | 1.2 | 0.2 | 0.2 |
| TP-01 | 1'-2' | 10/8/2024 | 940 | Light brown sand/silt hardpack | 10/8/2024 | 3000 | 1363 | 273 | 2.9 | < | - | - | - | - |
| TP-02 | 3.5'-4' | 10/8/2024 | 1000 | Dark brown loam/slit W/ clay | 10/8/2024 | 3000 | 1194 | 239 | 2.4 | < | - | - | - | - |
| TP-02 | 4.5'-5' | 10/8/2024 | 1020 | Brown silt/sand compacted | 10/8/2024 | 3000 | 1245 | 249 | 2.5 | < | - | - | - | - |
| TP-03 | 6"-12" | 10/9/2024 | 810 | Light brown sand/silt hardpack w/ grey soil | 10/9/2024 | 3000 | 1241 | 248 | 2.5 | < | - | - | - | - |
| TP-03 | 1'-2' | 10/9/2024 | 820 | Brown slit/sand - clay | 10/9/2024 | 3000 | 1208 | 242 | 2.4 | < | - | - | - | - |
| TP-04 | 6"-12" | 10/15/2024 | 1020 | Gravel & brown slit/sand - clay | 10/15/2024 | 3000 | 1424 | 285 | 3.0 | < | - | - | - | - |
| TP-05 | 6"-12" | 10/9/2024 | 940 | Light brown sand/silt hardpack | 10/9/2024 | 3000 | 1395 | 279 | 2.9 | < | - | - | - | - |
| TP-06 | 6"-12" | 10/8/2024 | 846 | Light brown sand/silt hardpack | 10/8/2024 | 3000 | 1306 | 261 | 2.7 | < | - | - | - | - |
| TP-06 | 1'-2' | 10/8/2024 | 856 | Light brown sand/silt hardpack | 10/8/2024 | 3000 | 1256 | 251 | 2.6 | < | - | - | - | - |
| TP-07 | 6"-12" | 10/9/2024 | 925 | Light brown sand/silt hardpack | 10/9/2024 | 3000 | 1524 | 305 | 3.3 | < | - | - | - | - |
| TP-08 | 6"-12" | 10/9/2024 | 910 | Light brown sand/silt hardpack | 10/9/2024 | 3000 | 1375 | 275 | 2.9 | < | - | - | - | - |
| TP-09 | 6"-12" | 11/25/2024 | 1250 | Light brown sandy, silt | 11/26/2024 | 3000 | 1185 | 237 | 2.4 | < | - | - | - | - |
| TP-09 | 1'-1.5' | 11/25/2024 | 1305 | Light brown sandy, silt | 11/26/2024 | 3000 | 1131 | 226 | 2.2 | < | - | - | - | - |
| TP-09 | 2'-2.5' | 11/25/2024 | 1315 | Light brown sandy, silt | 11/26/2024 | 3000 | 1225 | 245 | 2.5 | < | - | - | - | - |
| TP-10 | 6"-12" | 10/8/2024 | 910 | Light brown sand/silt hardpack | 10/8/2024 | 3000 | 1840 | 368 | 4.2 | < | - | - | - | - |
| TP-11 | 6"-12" | 10/9/2024 | 850 | Brown slit/sand - clay | 10/9/2024 | 3000 | 7653 | 1531 | 20.5 | > | - | - | - | - |
| TP-11 | 1'-1.5' | 10/9/2024 | 900 | Dark brown slit/sand - clay | 10/9/2024 | 3000 | 2076 | 415 | 4.9 | < | - | - | - | - |
| TP-12 | 6"-12" | 10/9/2024 | 1000 | Brown slit/sand - clay | 10/9/2024 | 3000 | 1353 | 271 | 2.8 | < | - | - | - | - |
| TP-13 | 6"-12" | 10/9/2024 | 840 | Dark brown slit/sand - clay | 10/9/2024 | 3000 | 2745 | 549 | 6.7 | ≈ | yes | 7.2 | 0.4 | 0.3 |
| TP-13 | 1'-1.5' | 10/15/2024 | 815 | Light brown sand/silt hardpack | 10/15/2024 | 3000 | 1397 | 279 | 3.0 | < | - | - | - | - |
| TP-14 | 6"-12" | 10/15/2024 | 1040 | Brown slit/sand - clay | 10/15/2024 | 3000 | 1915 | 383 | 4.4 | < | - | - | - | - |
| TP-15 | 6"-12" | 10/9/2024 | 1050 | Light brown sand/silt hardpack | 10/9/2024 | 3000 | 1274 | 255 | 2.6 | < | - | - | - | - |
| TP-16 | 6"-12" | 10/9/2024 | 1010 | Brown slit/sand - clay | 10/9/2024 | 3000 | 1376 | 275 | 2.9 | < | - | - | - | - |
| TP-16 | 1'-1.5' | 10/9/2024 | 1020 | Brown slit/sand - clay | 10/9/2024 | 3000 | 1250 | 250 | 2.5 | < | - | - | - | - |
| TP-17 | 6"-12" | 11/22/2024 | 1040 | Brown slit/loam | 11/26/2024 | 3000 | 1475 | 295 | 3.2 | < | - | - | - | - |
| TP-18 | 6"-12" | 10/9/2024 | 1030 | Light brown sand/silt hardpack | 10/9/2024 | 3000 | 5468 | 1094 | 14.3 | > | - | - | - | - |
| TP-18 | 1'-1.5' | 10/15/2024 | 825 | Light brown sand/silt hardpack | 10/15/2024 | 3000 | 1977 | 395 | 4.6 | < | - | - | - | - |
| TP-18 | 1.5'-2' | 10/15/2024 | 836 | Brown slit/sand - clay | 10/15/2024 | 3000 | 1323 | 265 | 2.7 | < | - | - | - | - |
| TP-19 | 6"-4.5' | 10/28/2024 | 1140 | Sandy grey waste rock | 10/29/2024 | 3000 | 38495 | 7699 | 106.8 | > | - | - | - | - |
| TP-19 | 4.5'-5' | 10/16/2024 | 845 | Interface waste rock-dark brown clay | 10/16/2024 | 3000 | 1297 | 259 | 2.7 | < | yes | 1.1 | 0.2 | 0.2 |
| TP-19 | 5'-5.5' | 10/16/2024 | 900 | Dark brown slit/sand - clay | 10/16/2024 | 3000 | 1334 | 267 | 2.8 | < | - | - | - | - |

## Table 3 (cont.)

### North Controlled Area Radiological Characterization Soil Sample Field Ex-Situ Screening and Vendor Laboratory Results Summary

| Sample Data | | | | | Field Soil Screening Data | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | Soil IL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| TP-20 | 1'-1.5' | 10/15/2024 | 1055 | Light brown sand/silt hardpack | 10/15/2024 | 3000 | 1243 | 249 | 2.5 | < | - | - | - | - |
| TP-21 | 0-2.0' | 1/27/2025 | 1056 | Dark grey compacted sandy silty clay with metal debris | 1/30/2025 | 3000 | 41183 | 8237 | 114.4 | > | - | - | - | - |
| TP-21 | 2.0'-3.0' | 1/27/2025 | 1105 | Dark grey compacted sandy silty clay | 1/30/2025 | 3000 | 1938 | 388 | 4.5 | < | - | - | - | - |
| TP-21 | 3.0'-4.0 | 1/27/2025 | 1113 | Dark brown clay | 1/30/2025 | 3000 | 1712 | 342 | 3.8 | < | - | - | - | - |
| TP-22 | 1'-1.5' | 10/16/2024 | 1115 | Dark brown slit/sand - clay | 10/16/2024 | 3000 | 9053 | 1811 | 24.4 | > | - | - | - | - |
| TP-22 | 1.5'-2' | 10/28/2024 | 1120 | Light brown sand/silt hardpack | 10/29/2024 | 3000 | 1213 | 243 | 2.4 | < | yes | 1.1 | 0.2 | 0.3 |
| TP-23 | 6"-12" | 10/28/2024 | 1300 | Brown slit/loam - clay | 10/29/2024 | 3000 | 1512 | 302 | 3.3 | < | - | - | - | - |
| TP-24 | 6"-12" | 10/16/2024 | 1020 | Light brown sand/silt hardpack | 10/16/2024 | 3000 | 2377 | 475 | 5.7 | < | yes | 3.8 | 0.3 | 0.2 |
| TP-25 | 6"-12" | 11/22/2024 | 1055 | Brown slit/loam - clay | 11/26/2024 | 3000 | 1164 | 233 | 2.3 | < | - | - | - | - |
| TP-26 | 2'-2.5' | 12/11/2024 | 1000 | Dark grey compacted sandy silty | 12/11/2024 | 3000 | 10464 | 2093 | 28.3 | > | - | - | - | - |
| TP-26 | 2.5'-3.0' | 1/27/2025 | 1028 | Dark grey compacted sandy silty clay | 1/30/2025 | 3000 | 1900 | 380 | 4.4 | < | - | - | - | - |
| TP-26 | 3.0'-4.0' | 1/27/2025 | 1037 | Dark grey compacted sandy silty clay | 1/30/2025 | 3000 | 2198 | 440 | 5.2 | < | | | | |
| TP-27 | 8"-12" | 10/16/2024 | 1000 | Brown slit/sand - clay | 10/16/2024 | 3000 | 1323 | 265 | 2.7 | < | - | - | - | - |
| TP-28 | 10"-12" | 10/16/2024 | 930 | Interface waste rock-light brown clay | 10/16/2024 | 3000 | 1506 | 301 | 3.3 | < | - | - | - | - |
| TP-29 | 1'-1.5' | 10/16/2024 | 1056 | Brown slit/sand - clay | 10/16/2024 | 3000 | 1214 | 243 | 2.4 | < | - | - | - | - |
| TP-30 | 6"-12" | 12/4/2024 | 830 | Light brown sandy, cobble, silty clay | 12/9/2024 | 3000 | 1258 | 252 | 2.6 | < | yes | 1.6 | 0.2 | 0.2 |
| TP-31 | 6"-12" | 11/25/2024 | 1020 | Dark brown slit/sand - clay | 11/26/2024 | 3000 | 3849 | 770 | 9.8 | > | - | - | - | - |
| TP-31 | 1'-1.5' | 11/25/2024 | 1040 | Light brown sandy, silt | 11/26/2024 | 3000 | 1704 | 341 | 3.8 | < | - | - | - | - |
| TP-32 | 6"-12" | 12/5/2024 | 845 | Dark brown silty clay | 12/9/2024 | 3000 | 2619 | 524 | 6.4 | ≈ | - | - | - | - |
| TP-32 | 1'-1.5' | 12/9/2024 | 950 | Brown slit/loam - clay | 12/11/2024 | 3000 | 1229 | 246 | 2.5 | < | yes | 1.4 | 0.2 | 0.3 |
| TP-33 | 6"-12" | 11/25/2024 | 1100 | Brown slit/loam - clay and sand | 11/26/2024 | 3000 | 1203 | 241 | 2.4 | < | yes | 1.1 | 0.2 | 0.2 |
| TP-34 | 6"-12" | 12/5/2024 | 930 | Dark brown silty clay | 12/9/2024 | 3000 | 6878 | 1376 | 18.3 | > | - | - | - | - |
| TP-34 | 1'-2' | 12/9/2024 | 1030 | Brown sandy/silty clay | 12/11/2024 | 3000 | 3976 | 795 | 10.2 | > | - | - | - | - |
| TP-34 | 2'-3' | 12/11/2024 | 915 | Brown silty clay/sandy with cobble | 12/11/2024 | 3000 | 1547 | 309 | 3.4 | < | yes | 1.3 | 0.2 | 0.2 |
| TP-35 | 6"-12" | 10/28/2024 | 840 | Brown slit/sand - clay | 10/29/2024 | 3000 | 3081 | 616 | 7.7 | > | - | - | - | - |
| TP-35 | 1'-1.5' | 10/28/2024 | 850 | Interface waste rock-dark brown clay | 10/29/2024 | 3000 | 1502 | 300 | 3.2 | < | - | - | - | - |
| TP-36 | 6"-12" | 10/28/2024 | 810 | Brown slit/loam - clay | 10/29/2024 | 3000 | 1345 | 269 | 2.8 | < | - | - | - | - |
| TP-36 | 1'-2' | 10/28/2024 | 825 | Brown slit/loam - clay | 10/29/2024 | 3000 | 1279 | 256 | 2.6 | < | - | - | - | - |
| TP-37 | 6"-12" | 10/28/2024 | 910 | Dark brown slit/sand - clay | 10/29/2024 | 3000 | 1273 | 255 | 2.6 | < | - | - | - | - |
| TP-39 | 6"-12" | 10/28/2024 | 930 | Brown slit/loam - clay | 10/29/2024 | 3000 | 1285 | 257 | 2.6 | < | - | - | - | - |
| TP-40 | 6"-12" | 10/28/2024 | 1035 | Light brown sandy, silt | 10/29/2024 | 3000 | 1177 | 235 | 2.3 | < | yes | 1.1 | 0.3 | 0.3 |
| Inv-01 | 2'-2.5' | 10/15/2024 | 940 | Light brown sand/silt hardpack w/ grey soil | 10/15/2024 | 3000 | 1337 | 267 | 2.8 | < | - | - | - | - |

## Table 3 (cont.)

**North Controlled Area Radiological Characterization Soil Sample Field Ex-Situ Screening and Vendor Laboratory Results Summary**

| Sample Data | | | | | Field Soil Screening Data | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | Soil IL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| Inv-05 | 6"-12" | 10/28/2024 | 945 | Light brown sandy, silt | 10/29/2024 | 3000 | 2442 | 488 | 5.9 | < | - | - | - | - |
| Inv-05 | 1'-1.5' | 10/28/2024 | 1000 | Brown slit/sand - clay | 10/29/2024 | 3000 | 1553 | 311 | 3.4 | < | - | - | - | - |
| Inv-06 | 6"-12" | 10/28/2024 | 1015 | Light brown sandy, silt/loam | 10/29/2024 | 3000 | 1337 | 267 | 2.8 | < | - | - | - | - |
| Inv-07 | 6"-12" | 10/8/2024 | 1045 | Grey silt/sand w/ debris | 10/8/2024 | 3000 | 2945 | 589 | 7.3 | > | - | - | - | - |
| Inv-07 | 1.5'-2' | 10/8/2024 | 1055 | Grey silt/sand w/ debris | 10/8/2024 | 3000 | 3131 | 626 | 7.8 | > | yes | 8.6 | 0.4 | 0.3 |
| Inv-07 | 2'-3' | 10/8/2024 | 1105 | Dark brown slit/sand - clay | 10/8/2024 | 3000 | 1125 | 225 | 2.2 | < | - | - | - | - |

Note: Soil samples were not collected at locations Inv-02, Inv-03, and Inv-04.

**Table 4**
**North Controlled Area Surface and Subsurface Soil Ra-226 Level Summary**

| Data Point ID | Static Gamma CPM | Static Gamma Estimated Ra-226 pCi/g 0-6" (surface) Soil | Static Gamma & Ex-Situ Soil Screening Estimated Ra-226 pCi/g | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | 6"-12" Soil | 1'-1.5' Soil | 1.5' - 2' Soil | 2'-2.5' Soil | 2.5'-3' Soil | 3'-3.5' Soil | 3.5'-4' Soil | 4'-4.5' Soil | 4.5'-5' Soil | 5'-5.5' Soil |
| TP-1 | 74549 | 111.8 | 3.1 | 2.9 | 2.9 | - | - | - | - | - | - | - |
| TP-2 | 23242 | 29.7 | 20.0 | | | | | | 2.4 | 2.5 | 2.5 | - |
| TP-3 | 12217 | 12.0 | 2.5 | 2.4 | | - | - | - | - | - | - | - |
| TP-4 | 11677 | 11.2 | 3.0 | - | - | - | - | - | - | - | - | - |
| TP-5 | 7643 | 4.7 | 2.9 | - | - | - | - | - | - | - | - | - |
| TP-6 | 28795 | 38.6 | 2.7 | 2.6 | 2.6 | - | - | - | - | - | - | - |
| TP-7 | 7755 | 4.9 | 3.3 | - | - | - | - | - | - | - | - | - |
| TP-8 | 9500 | 7.7 | 2.9 | - | - | - | - | - | - | - | - | - |
| TP-9 | 26878 | 35.5 | 2.4 | 2.2 | - | 2.5 | - | - | - | - | - | - |
| TP-10 | 10215 | 8.8 | 4.2 | - | - | - | - | - | - | - | - | - |
| TP-11 | 17075 | 19.8 | 20.5 | 4.9 | - | - | - | - | - | - | - | - |
| TP-12 | 7687 | 4.8 | 2.8 | - | - | - | - | - | - | - | - | - |
| TP-13 | 25917 | 34.0 | 6.7 | 3 | - | - | - | - | - | - | - | - |
| TP-14 | 31693 | 43.2 | 4.4 | - | - | - | - | - | - | - | - | - |
| TP-15 | 10771 | 9.7 | 2.6 | - | - | - | - | - | - | - | - | - |
| TP-16 | 20877 | 25.9 | 2.9 | 2.5 | - | - | - | - | - | - | - | - |
| TP-17 | 9788 | 8.2 | 3.2 | - | - | - | - | - | - | - | - | - |
| TP-18 | 23920 | 30.8 | 14.3 | 4.6 | 2.7 | - | - | - | - | - | - | - |
| TP-19 | 108929 | 166.8 | 106.8 | | | | | | | | 2.7 | 2.8 |
| TP-20 | 42042 | 59.8 | 59.8 | 2.5 | - | - | - | - | - | - | - | - |
| TP-21 | 189626 | 295.9 | 114.4 | | | 4.5 | | 3.8 | | - | - | - |
| TP-22 | 27679 | 36.8 | 36.8 | 24.4 | - | - | - | - | - | - | - | - |
| TP-23 | 11721 | 11.3 | 3.3 | - | - | - | - | - | - | - | - | - |
| TP-24 | 184511 | 287.7 | 5.7 | - | - | - | - | - | - | - | - | - |
| TP-25 | 15304 | 17.0 | 2.3 | - | - | - | - | - | - | - | - | - |
| TP-26 | 154801 | 240.2 | - | - | - | 28.3 | 4.4 | 5.2 | | - | - | - |
| TP-27 | 116173 | 178.4 | 2.7 | - | - | - | - | - | - | - | - | - |
| TP-28 | 69269 | 103.3 | 3.3 | - | - | - | - | - | - | - | - | - |
| TP-29 | 37349 | 52.3 | - | 2.4 | - | - | - | - | - | - | - | - |
| TP-30 | 7362 | 4.3 | 2.6 | - | - | - | - | - | - | - | - | - |
| TP-31 | 76057 | 114.2 | 9.8 | 3.8 | - | - | - | - | - | - | - | - |
| TP-32 | 11869 | 11.5 | 6.4 | 2.5 | - | - | - | - | - | - | - | - |
| TP-33 | 11765 | 11.3 | 2.4 | - | - | - | - | - | - | - | - | - |
| TP-34 | 18951 | 22.8 | 18.3 | 10.2 | | 3.4 | | - | - | - | - | - |
| TP-35 | 31729 | 43.3 | 7.7 | 3.2 | - | - | - | - | - | - | - | - |
| TP-36 | 12576 | 12.6 | 2.8 | 2.6 | | - | - | - | - | - | - | - |
| TP-37 | 9058 | 7.0 | 2.6 | - | - | - | - | - | - | - | - | - |
| TP-38 | 13769 | 14.5 | No Subsurface Soil Sample Taken - Metal Debris | | | | | | | | | |
| TP-39 | 9606 | 7.9 | 2.6 | - | - | - | - | - | - | - | - | - |
| TP-40 | 13072 | 13.4 | 2.3 | - | - | - | - | - | - | - | - | - |
| Inv-01 | 14304 | 15.4 | 32.8 | 12.4 | | 2.8 | - | - | - | - | - | - |
| Inv-02 | 9200 | 7.2 | 10.6 | 5.1 | - | - | - | - | - | - | - | - |
| Inv-03 | 13157 | 13.6 | Push-up Berm Height of 2.5' from Pond 8 Area | | | | - | - | - | - | - | - |
| Inv-04 | 36695 | 51.2 | 11.6 | 6.6 | - | - | - | - | - | - | - | - |
| Inv-05 | 7441 | 4.4 | 5.9 | 3.4 | - | - | - | - | - | - | - | - |
| Inv-06 | 19774 | 24.1 | 2.8 | - | - | - | - | - | - | - | - | - |
| Inv-07 | 10142 | 8.7 | 7.3 | 7.8 | | 2.2 | | - | - | - | - | - |

Note: Static Gamma Estimated pCi/g levels were estimated from .5" lead collimated detector static gamma measurements.

## Table 5
### Mt. Taylor Mine Site - NCA Soil Radiological Characterization
### Estimated Volumes of Areas above the 6.8 Ra-226 pCi/g Investigation Level

| Estimated Depth of Area > 6.8 Ra-226 pCi/g Investigation Level | Approximate Land Area (acre) | Estimated Volume (cubic yard) |
|---|---|---|
| surface to 6" bgs | 15 | 12,100 |
| surface to 1.0' bgs | 5.2 | 8,067 |
| surface to 1.5' bgs | 0.1 | 242 |
| surface to 2.0' bgs | 0.6 | 1,936 |
| surface to 3.0' bgs | 1.1 | 5,330 |
| surface to 3.5' bgs | 0.1 | 565 |
| surface to 4.5' bgs | 0.9 | 6,534 |
| Estimated Total | 23 | 34,773 |

Note: Does not include volume estimate of the Ore Retnetion Pond dikes. bgs = below ground surface

# Figures




N
W E
S


Environmental Services, Inc.

# Figure 1
# Mt. Taylor Mine Site
# North Controlled Area Soil Radiologic Characterization Area

June 2025

**Legend**

- NCA Soil Radiologic Characterization Area
- Previously Characterized Area
- Active Treatment Ponds
- North Controlled Fence




N
W E
S

Environmental Services, Inc.

# Figure 2
# Mt. Taylor Mine Site
# North Controlled Area - Gamma Scan Survey Data

June 2025

**Legend**

**Estimated Ra-226**


- <1.8 pCi/g
- 1.9 - 6.8 pCi/g
- 6.9 - 10.0 pCi/g
- 10.1 - 20.0 pCi/g
- 20.1 - 30.0 pCi/g
- 30.1 - 40.0 pCi/g
- >40.1 pCi/g

Active Treatment Ponds

North Controlled Fence

Bare/Collimated Detector Boundary

Note: Ra-226 pCi/g is determined from surface soil gamma radiation scan and static cpm using 2x2 NaI detector and Site specific gamma radiation level (cpm) correlation.




# Figure 3
# Mt. Taylor Mine Site - North Controlled Area
# Gamma Scan Survey Data, Investigation and Test Pit Locations

June 2025

AVM Environmental Services, Inc.


**Legend**

**Estimated Ra-226**

- <1.8 pCi/g
- 1.9 - 6.8 pCi/g
- 6.9 - 10.0 pCi/g
- 10.1 - 20.0 pCi/g
- 20.1 - 30.0 pCi/g
- 30.1 - 40.0 pCi/g
- >40.1 pCi/g

- Investigation Sample ID
- Test Pit ID
- Contamination Areas
- Active Treatment Ponds
- North Controlled Fence

Note: Ra-226 pCi/g is determined from surface soil gamma radiation scan and static cpm using 2x2 NaI detector and Site specific gamma radiation level (cpm) correlation.




N
W E
S

Environmental Services, Inc.

# Figure 4
## Mt. Taylor Mine Site - North Controlled Area
## Gamma Scan Survey Data, Investigation and Test Pit Locations

June 2025

**Legend**

**Estimated Ra-226**

- <1.8 pCi/g
- 1.9 - 6.8 pCi/g
- 6.9 - 10.0 pCi/g
- 10.1 - 20.0 pCi/g
- 20.1 - 30.0 pCi/g
- 30.1 - 40.0 pCi/g
- >40.1 pCi/g

Investigation Sample ID (6.8 pCi/g IL cont. Depth)

Test Pit ID (6.8 pCi/g IL cont. Depth)

Contamination Area

Active Treatment Ponds

North Controlled Fence

Note: Ra-226 pCi/g is determined from surface soil gamma radiation scan and static cpm using 2x2 NaI detector and Site specific gamma radiation level (cpm) correlation.




N
W E
S

Environmental Services, Inc.

# Figure 5
# Mt. Taylor Mine Site - North Controlled Area
# Estimated Depth of Contamination above the 6.8 Ra-226 pCi/g IL

June 2025

**Legend**

- 6" Contamination depth above the Ra-226 pCi/g IL
- 1.0' Contamination depth above the Ra-226 pCi/g IL
- 1.5' Contamination depth above the Ra-226 pCi/g IL
- 2.0' Contamination depth above the Ra-226 pCi/g IL
- 3.0' Contamination depth above the Ra-226 pCi/g IL
- 3.5' Contamination depth above the Ra-226 pCi/g IL
- 4.5' Contamination depth above the Ra-226 pCi/g IL
- Ore Pad Retention Pond Dike
- Active Treatment Ponds
- North Controlled Fence

Note: Ra-226 pCi/g is determined from surface soil gamma radiation scan and static cpm using 2x2 NaI detector and Site specific gamma radiation level (cpm) correlation.

**Appendix A**
**Surface and Subsurface Contamination Field Investigation Documentation**
**(Soil Sample Log Forms, Field Soil Sample Ex-Situ Gamma Radiation Screening Forms)**

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Static Gamma Radiation Survey Field Form**

Instrumentation: Scaler/Ratemeter L2221 SN 290801 Detector SPA-3 #30

Instrument Calibration Date: 2-17-24 Instrument Daily Function Check Performed: Y

2"x2" NaI Detector Collimated: X Yes or ____ No

Survey Area/Unit Decsription Mt. Tobe Mine Site - NCA

| Survey Date/Time | Survey Point ID/Description | Survey Point Coordinate | | Gamma Radiation Reading - CPM | | Exposure Rate µR/hr | Comments/Notes |
|---|---|---|---|---|---|---|---|
| | | Northing | Easting | Bare | Collimated (0.5"Pb) | | |
| 9-19-24 | TP-01 | 1580195 | 2781643 | | 74549 | | |
| | TP-02 | 1581346 | 2781656 | | 23242 | | |
| | TP-03 | 1581205 | 2781918 | | 12217 | | |
| | TP-04 | 1580828 | 2781919 | | 11677 | | |
| | TP-05 | 1580646 | 2781960 | | 7643 | | |
| | TP-06 | 1579528 | 2782004 | | 28795 | | |
| | TP-07 | 1580613 | 2782034 | | 7755 | | hot Rust pile nearby |
| | TP-08 | 1580715 | 2782055 | | 9500 | | |
| 11-25-24 | TP-09 | 1579932 | 2782126 | | 26878 | | |
| 9-19-24 | TP-10 | 1580081 | 2782153 | | 10215 | | |
| | TP-11 | 1580894 | 2782206 | | 17076 | | |
| | TP-12 | 1580505 | 2782214 | | 7687 | | |
| | TP-13 | 1581025 | 2782217 | | 25917 | | |
| | TP-14 | 1581016 | 2782311 | | 31693 | | |
| | TP-15 | 1580840 | 2782324 | | 10771 | | |
| | TP-16 | 1580519 | 2782343 | | 20877 | | |
| 11-22-24 | TP-17 | 1581234 | 2782355 | | 4788 | | |
| 9-19-24 | TP-18 | 1580677 | 2782415 | | 23920 | | |
| | TP-19 | 1581101 | 2782521 | | 108929 | | |
| | TP-20 | 1580596 | 2782544 | | 42042 | | |
| | TP-21 | 1580819 | 2782549 | | 189626 | | |

Technician Signature _____ Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Static Gamma Radiation Survey Field Form**

Instrumentation ; Scaler/Ratemeter L2221 #290301 , Detector SAM-3 #30

Instrument Calibration Date: 2-19-24 , Instrument Daily Function Check Performed: Y

2"x2" NaI Detector Collimated X Yes or ____ No

Survey Area/Unit Decsription Mt. Taylor Mine Site #1 NCA

| Survey Date/Time | Survey Point ID/Description | Survey Point Coordinate | | Gamma Radiation Reading - CPM | | Exposure Rate µR/hr | Comments/Notes |
|---|---|---|---|---|---|---|---|
| | | Northing | Easting | Bare | Collimated (0.5"Pb) | | |
| 9-19-24 | TP-22 | 1580005 | 2782580 | | 27679 | | |
| 10-28-24 | TP-23 | 1580823 | 2782622 | | 11721 | | |
| 9-19-24 | TP-24 | 1580668 | 2782658 | | 184511 | | |
| 11-22-24 | TP-25 | 1581189 | 2782673 | | 15304 | | |
| 12-11-24 | TP-26 | 1580827 | 2782704 | | 154801 | | |
| 9-19-24 | TP-27 | 1580480 | 2782708 | | 116173 | | |
| | TP-28 | 1581082 | 2782719 | | 69269 | | |
| | TP-29 | 1580105 | 2782719 | | 37349 | | |
| 12-2-24 | TP-30 | 1581091 | 2782877 | | 7362 | | |
| 11-25-24 | TP-31 | 1580996 | 2783202 | | 76057 | | |
| 12-5-24 | TP-32 | 1580440 | 2783254 | | 11869 | | |
| 11-25-24 | TP-33 | 1581070 | 2783303 | | 11765 | | |
| 12-5-24 | TP-34 | 1580842 | 2783312 | | 18951 | | |
| 10-23-24 | TP-35 | 1580627 | 2783327 | | 31729 | | |
| 10-23-24 | TP-36 | 1580794 | 2783355 | | 12576 | | |
| 10-23-24 | TP-37 | 1580506 | 2783378 | | 9058 | | |
| 10-23-24 | TP-38 | 1581069 | 2783413 | | 13769 | | |
| 10-23-24 | TP-39 | 1580480 | 2783504 | | 9606 | | |
| 10-23-24 | TP-40 | 1581114 | 2783628 | | 13072 | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____ Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Static Gamma Radiation Survey Field Form**

Instrumentation: Scaler/Ratemeter L2221 SN 290801 Detector GPA 3 #30

Instrument Calibration Date: 2-19-24 Instrument Daily Function Check Performed: Y

2"x2" NaI Detector Collimated X Yes or _____ No.

Survey Area/Unit Decsription Mt. Taylor Mine site NCA

| Survey Date/Time | Survey Point ID/Description | Survey Point Coordinate | | Gamma Radiation Reading - CPM | | Exposure Rate µR/hr | Comments/Notes |
|---|---|---|---|---|---|---|---|
| | | Northing | Easting | Bare | Collimated (0.5"Pb) | | |
| 9-19-24 | Investigation 01 | 1580781 | 2781697 | | 14304 | | |
| | Investigation 02 | 1579930 | 2781700 | | 9200 | | |
| | Investigation 03 | 1581206 | 2781734 | | 13157 | | Pipeline Berm |
| | Investigation 04 | 1580829 | 2782173 | | 36,695 | | |
| 10-23-24 | Investigation 05 | 1580655 | 2783717 | | 7441 | | |
| 10-23-24 | Investigation 06 | 1581080 | 2783856 | | 19774 | | |
| 9-19-24 | I-07 | | | | 10142 | | |

Technician Signature _____ Reviewed by _____

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| TP-06 | 10-3-24 846 | 6-12" | light brown Sand / silt stone Rocks hard Pack | |
| TP-06 | " 856 | 1'-2' | " " " Rocks hard Pack | |
| TP-10 | " 910 | 6-12" | " " " | |
| TP-01 | " 930 | 6-12" | Brown silt/Sand Compacted Rocks | |
| TP-01 | 940 | 1-2' | light brown silt/Sand Compacted | |
| TP-02 | " 1000 | 3.5-4' | Dark Brown loam - silt Clay | on site - @ peak |
| TP-02 | " 1020 | 4.5'-5' | Brown Sandy silt | |
| ~~TP-04~~ VP Inv-07 | " 1045 | 6"-12" | light grey plastic debris waste Rock | |
| ~~TP-04~~ VP Inv-07 | " 1055 | 15'-25' | " " " | |
| ~~TP-04~~ VP Inv-07 | " 1105 | 25-3' | Dark brown silty Sand clay | |
| TP-03 | 10-9-24 810 | 6"-12" | light brown silty Rock w/ grey | |
| TP-03 | 10-9-24 820 | 1'-2' | Brown silty Sand w/ clay | |
| TP-13 | 10-9-24 840 | 6"-12" | Dark brown silt clay | |
| TP-11 | 10-9-24 850 | 6"-12" | Brown silty w/ clay | |
| TP-11 | 10-9-24 900 | 1'-1.5' | Dark brown clay silt. | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| TP-08 | 10-9-24 910 | 6"-12" | light brown Compacted Sand & silt | |
| TP-07 | 10-9-24 925 | 6"-12" | light brown silty Sand Consolidated | |
| TP-05 | 10-9-24 940 | 6"-12" | light brown Sandy Silt consolidated | |
| TP-12 | 10-9-24 1000 | 6"-12" | Brown Silt Packed / Consolidated | |
| TP-16 | 10-9-24 1010 | 6"-12" | Dark brown Silt Clay | |
| TP-16 | 10-9-24 1020 | 1'-1.5' | Brown silty Clay consolidated | |
| TP-18 | 10-9-24 1030 | 6"-12" | light brown Sandy w/ cobble | |
| TP-15 | 10-9-24 1050 | 6"-12" | light brown Sandy Consolidated | |
| TP-13 | 10-15-24 815 | 1'-1.5' | light brown Sand/silt hard pack | |
| TP-18 | 10-15-24 825 | 1'-1.5' | Brown Silty / Sand Clay Compacted | |
| TP-18 | 10-15-24 836 | 1.5'-2' | Brown Clay / silt Compacted | |
| INV-01 | 10-15-24 940 | 2'-2.5' | light brown / light grey Sand hard pack | |
| TP-04 | 10-15-24 1020 | 6"-12" | Top 1" gravel - Brown silt/clay Packed | |
| TP-14 | 10-15-24 1040 | 6"-12" | Brown silty/clay w/ speck of stone | |
| TP-20 | 10-15-24 1055 | 1'-1.5' | light brown Sandy | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| TP-19 | 10-16-24 845 | 4.5'-5' | Interface waste Rock / Clay-Silt Dark brown | |
| TP-19 | 10-16-24 900 | 5'-5.5' | Dark brown clay | |
| TP-28 | 10-16-24 930 | 10 ~~9~~"-12" | Interface waste Rock / clay light brown | |
| TP-27 | 10-16-24 1000 | 8"-12" | Brown clay/silt hardpacked | |
| TP-24 | 10-16-24 1020 | 6"-12" | light brown Sandy | |
| TP-29 | 10-16-24 1056 | 1'-1.5' | Dark clay hardpack | |
| TP-22 | 16-16-24 1115 | 1'-1.5' | Brown clay hardpack Sand hardpack | |
| TP-36 | 10-28-24 810 | 6"-12" | Silt / loam w/ clay | |
| TP-36 | 10-28-24 825 | 1'-~~1.5~~ 2' | Sandy silt Consolidated | |
| TP-35 | 10-28-24 840 | 6"-12" | Silt / clay Roots Brown | |
| TP-35 | 10-28-24 850 | 1'-1.5' | grey / Brown Silty Sand Clay Packed | |
| TP-37 | 10-28-24 910 | 6"-12" | Dark brown Silt Clay | |
| TP-39 | 10-28-24 930 | 6"-12" | Brown silt loam / light brown Sandy | |
| Inv-5 | 10-28-24 945 | 6"-12" | light brown Sandy silt w/ light clay | |
| Inv-5 | 10-29-24 1000 | 1'-1.5' | Light brown silt clay | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| Inv-6 | 10-28-24 1015 | 6"-12" | Packed loamy silt Sand | |
| TP-40 | 10-28-24 1035 | 6"-12" | Silty Sand compacted | |
| TP-38 | 10-28-24 1050 | 6"-12" | metal & plaster debris | No Sample |
| TP-22 | 10-28-24 1120 | 1.5'-2.0' | brown Silt Clay compacted | |
| TP-19 | 10-28-24 1140 | 6"-4.5' | grey waste Rock Sandy | |
| TP-23 | 10-28-24 1300 | 6"-12" | Brown loamy Silt | |
| TP-17 | 11-22-24 1040 | 6"-12" | Brown loamy Silt | |
| TP-25 | 11-22-24 1055 | 6"-12" | Brown loamy clay | |
| TP-31 | 11-25-24 @ 1020 | 6"-12" | Dark brown silty Sandy Clay | |
| TP-31 | 11-25-24 @ 1040 | 1'-1.5' | light brown Sandy consolidated | |
| TP-33 | 11-25-24 @ 1100 | 6"-12" | Brown clay / light brown sandy | |
| TP-09 | 11-25-24 @1250 | 6"-12" | light brown silty Sand consolidated | |
| TP-09 | 11-25-24 @1305 | 1'-1.5 | light brown Silty Sand Consolidated | |
| TP-09 | 11-25-24 @1315 | 2'-2.5' | light brown Silty Sandy | |
| TP-30 | 12-4-24 @830 | 6"-12" | Sand w/ cobble 6"-8" Clay w/ cobble 8"-13" | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| TP-32 | @845 12-5-24 | 6"-12" | Dark brown silt clay | |
| TP-34 | 0930 12-5-24 | 6"-12" | Dark brown silt clay. | |
| TP-32 | 12-9-24 @950 | 1'-1.5' | Brown silty clay | |
| TP-34 | 12-9-24 @1030 | 1'-2' | Brown Sandy / silty clay | |
| TP-34 | 12-11-24 @915 | 2'-3' | 2-2.5' Brown silty clay 2.5-3' Sandy w/ cobble. | |
| TP-26 | 12-11-24 @1000 | 2'-2.5' | Dark grey compacted sandy soil Refusal @ 2.5' | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| TP-26 2.5-3.0 | 1-27-25 @1028 | 2.5-3.0 | Dark brown / black clay w/ Sand | |
| TP-26 3.0-4.0 | 1-27-25 @1037 | 3.0-4.0 | " " " " | |
| TP-21 | 1-27-25 @1056 | 0-2.0' | Dark brown clay Black. Sandy w/ metal debris + rust | |
| TP-21 | 1-27-25 @1105 | 2.0-3.0 | Dark brown w/ grey clay/silt | |
| TP-21 | 1-27-25 @1113 | 3.0-4.0 | Dark Brown Clay | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S/N 68782, Detector 44-20 S/N 295573
Instrument Calibration Date: 2-19-24 / 9-30-24, Instrument Function Check Performed: Y
Survey Area/Unit Decsription MT. Taylor Mine - NCA Test Pit

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CPSM | Weight Corrected CPSM | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 10-8-24 | Blank | — | 310 | — | 62 | | |
| 10-8-24 | 6.6pCi Ref Soil | 3000 | 2338 | — | 468 | | |
| 10-8-24 | TP-06 6"-12" 10-8-24 @846 | 3000 | 1306 | — | 261 | | |
| 10-8-24 | TP-06 1'-2' 10-8-24 @856 | 3000 | 1256 | — | 251 | | |
| 10-8-24 | TP-10 6"-12" 10-8-24 @910 | 3000 | 1840 | — | 368 | | |
| 10-8-24 | TP-01 6"-12" 10-8-24 @930 | 3000 | 1437 | — | 287 | | |
| 10-8-24 | TP-01 1'-2' 10-8-24 @940 | 3000 | 1363 | — | 273 | | |
| 10-8-24 | TP-02 3.5'-4' 10-8-24 @1000 | 3000 | 1194 | — | 239 | | |
| 10-8-24 | TP-02 4.5'-5' 10-8-24 @1020 | 3000 | 1245 | — | 249 | | |
| 10-8-24 | ~~TP-04~~ INV-07 6"-12" 10-8-24 @1045 | 3000 | 2945 | — | 589 | | |
| 10-8-24 | ~~TP-04~~ INV-07 1.5'-2' 10-8-24 @1055 | 3000 | 3131 | — | 626 | | |
| 10-8-24 | ~~TP-04~~ INV-07 2'-3' 10-8-24 @1105 | 3000 | 1125 | — | 225 | | QA/QC CPSM 1174 |
| 10-9-24 | Blank | — | 300 | — | 60 | | |
| 10-9-24 | 6.6 pCi Ref Soil | 3000 | 2598 | — | 520 | | |
| 10-9-24 | TP-03 6"-12" 10-9-24 @810 | 3000 | 1241 | — | 248 | | |

Technician Signature [signature] Reviewed by [signature]

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S#68782, Detector L44-20 S# 295573
Instrument Calibration Date: 2-19-24 / 9-30-24, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt. Taylor Mine Site - NCM Test Pit

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 10-9-24 | TP-03 1'-2' 10-9-24 @ 820 | 3000 | 1208 | - | 242 | | |
| 10-9-24 | TP-13 6"-12" 10-9-24 @ 840 | 3000 | 2745 | - | 549 | | |
| 10-9-24 | TP-11 6"-12" 10-9-24 @ 850 | 3000 | 7653 | - | 1531 | | |
| 10-9-24 | TP-11 1'-1.5' 10-9-24 @ 900 | 3000 | 2076 | - | 415 | | |
| 10-9-24 | TP-08 6"-12" 10-9-24 @ 910 | 3000 | 1375 | - | 275 | | |
| 10-9-24 | TP-07 6"-12" 10-9-24 @ 925 | 3000 | 1524 | - | 305 | | |
| 10-9-24 | TP-05 6"-12" 10-9-24 @ 940 | 3000 | 1395 | - | 279 | | |
| 10-9-24 | TP-12 6"-12" 10-9-24 @ 1000 | 3000 | 1353 | - | 271 | | |
| 10-9-24 | TP-16 6"-12" 10-9-24 @ 1010 | 3000 | 1376 | - | 275 | | QA/QC CpSM 1325 |
| 10-9-24 | TP-16 1'-1.5' 10-9-24 @ 1020 | 3000 | 1250 | - | 250 | | |
| 10-9-24 | TP-18 6"-12" 10-9-24 @ 1030 | 3000 | 5468 | - | 1094 | | |
| 10-9-24 | TP-15 6"-12" 10-9-24 @ 1050 | 3000 | 1274 | - | 255 | | |
| 10-15-24 | Blank | - | 343 | - | 69 | | |
| 10-15-24 | 6.6 pCi Ref Soil | 3000 | 2494 | - | 499 | | |
| 10-15-24 | TP-13 1'-1.5' 10-15-24 @ 815 | 3000 | 1397 | - | 279 | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter LZ221 S#68782, Detector LZ44-20 S# 295573
Instrument Calibration Date: 2-19-24/9-30-24, Instrument Function Check Performed: ✓
Survey Area/Unit Description Mt. Taylor Mine Site - NCA test Pit

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CPSM | Weight Corrected CPSM | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 10-15-24 | TP-18 1'-1.5' 10-15-24 @ 825 | 3000 | 1977 | - | 395 | | |
| 10-15-24 | TP-18 1.5'-2' 10-15-24 @ 836 | 3000 | 1323 | - | 265 | | |
| 10-15-24 | INV-01 2'-2.5' 10-15-24 @ 940 | 3000 | 1337 | - | 267 | | |
| 10-15-24 | TP-04 6"-12" 10-15-24 @ 1020 | 3000 | 1424 | - | 285 | | |
| 10-15-24 | TP-14 6"-12" 10-15-24 @ 1040 | 3000 | 1915 | - | 383 | | |
| 10-15-24 | TP-20 1'-1.5' 10-15-24 @ 1055 | 3000 | 1243 | - | 249 | | QA/QC CPSM 1310 |
| 10-16-24 | Blank | - | 340 | - | 68 | | |
| 10-16-24 | 6.6 pCi Ref Soil | 3000 | 2465 | - | 493 | | |
| 10-16-24 | TP-28 10"-12" 10-16-24 @ 430 | 3000 | 1506 | - | 301 | | |
| 10-16-24 | TP-27 8"-12" 10-16-24 @ 1000 | 3000 | 1323 | - | 265 | | |
| 10-16-24 | TP-24 6"-12" 10-16-24 @ 1020 | 3000 | 2377 | - | 475 | | |
| 10-16-24 | TP-29 1'-1.5' 10-16-24 @ 1056 | 3000 | 1214 | - | 243 | | |
| 10-16-24 | TP-22 1'-1.5' 10-16-24 @ 1115 | 3000 | 9053 | - | 1811 | | |
| 10-16-24 | TP-19 4.5'-5' 10-16-24 @ 845 | 3000 | 1297 | - | 259 | | |
| 10-16-24 | TP-19 5'-5.5' 10-16-24 @ 1159 | 3000 | 1334 | - | 267 | | QA/QC CPSM 1285 |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S# 68782, Detector 44-20 S# 295573
Instrument Calibration Date: 2-19-24 / 9-30-24, Instrument Function Check Performed: V
Survey Area/Unit Decsription Mt. Taylor Mine Site - NCA Test Pit

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 10-29-24 | Blank | — | 328 | — | 66 | | |
| 10-29-24 | 6.6pCi Ref Soil | 3000 | 2321 | — | 464 | | |
| 10-29-24 | TP-36 6"-12" 10-28-24 @ 810 | 3000 | 1345 | — | 269 | | |
| 10-29-24 | TP-36 1'-2' 10-28-24 @ 825 | 3000 | 1279 | — | 256 | | |
| 10-29-24 | TP-35 6"-12" 10-28-24 @ 840 | 3000 | 3081 | — | 616 | | |
| 10-29-24 | TP-35 1'-1.5' 10-28-24 @ 850 | 3000 | 1502 | — | 300 | | |
| 10-29-24 | TP-37 6"-12" 10-28-24 @ 910 | 3000 | 1273 | — | 255 | | |
| 10-29-24 | TP-39 6"-12" 10-28-24 @ 930 | 3000 | 1285 | — | 257 | | |
| 10-29-24 | Inv-5 6"-12" 10-28-24 @ 945 | 3000 | 2442 | — | 488 | | |
| 10-29-24 | Inv-5 1'-1.5' 10-28-24 @ 1000 | 3000 | 1553 | — | 311 | | |
| 10-29-24 | Inv-6 6"-12" 10-28-24 @ 1015 | 3000 | 1337 | | 267 | | |
| 10-29-24 | TP-40 6"-12" 10-28-24 @ 1035 | 3000 | 1177 | | 235 | | QA/QC CP5M 1350 |
| 10-29-24 | TP-38 6"-12" 10-28-24 @ 1050 | — | — | — | — | | No Sample |
| 10-29-24 | TP-22 1.5'-2.0' 10-28-24 @ 1120 | 3000 | 1213 | — | 243 | | |
| 10-29-24 | TP-19 6"-4.5' 10-28-24 @ 1140 | 3000 | 38495 | — | 7699 | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S#68782, Detector L44-20 S# 295573
Instrument Calibration Date: 2-19-24 / 9-30-24, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt. Taylor Mine Site NCA Test Pits

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 10-29-24 | TP-23 6"-12" 10-22-24 @1300 | 3000 | 1512 | - | 302 | | |
| 11-26-24 | Blank | - | 292 | | 58 | | |
| 11-26-24 | 6.6pCi Ref Soil | 3000 | 2360 | | 472 | | |
| 11-26-24 | TP-17 6"-12" 11-22-24 @1040 | 3000 | 1475 | | 295 | | |
| 11-26-24 | TP-25 6"-12" 11-22-24 @1045 | 3000 | 1164 | | 233 | | |
| 11-26-24 | TP-31 6"-12" 11-25-24 @1020 | 3000 | 3849 | | 770 | | |
| 11-26-24 | TP-31 1'-1.5' 11-25-24 @1040 | 3000 | 1704 | | 341 | | |
| 11-26-24 | TP-33 6"-12" 11-25-24 @1100 | 3000 | 1203 | | 241 | | |
| 11-26-24 | TP-09 6"-12" 11-25-24 @1250 | 3000 | 1185 | | 237 | | |
| 11-26-24 | TP-09 1'-1.5' 11-25-24 @1305 | 3000 | 1131 | | 226 | | |
| 11-26-24 | TP-09 2'-2.5' 11-25-24 @1315 | 3000 | 1225 | | 245 | | |
| 12-9-24 | Blank | - | 333 | | 67 | | |
| 12-9-24 | 6.6 pCi Ref Soil | 3000 | 2372 | | 474 | | |
| 12-9-24 | TP-30 6"-12" 12-4-24 @830 | 3000 | 1258 | | 252 | | |
| 12-9-24 | TP-32 6"-12" 12-5-24 @845 | 3000 | 2619 | | 524 | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S#68782, Detector L44-20 S# 295573
Instrument Calibration Date: 2-14-24/9-30-24, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription Mt. Taylor Mine Site NCA Task P.2

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 12-9-24 | TP-34 6'-12' 12-5-24 @ 920 | 3000 | 6878 | | 1376 | | QA/QC CP5M = 6866 |
| 12-11-24 | Blank | — | 329 | | 66 | | |
| 12-11-24 | 6.6 pCi/g Ref Soil | 3000 | 2437 | | 487 | | |
| 12-11-24 | TP-32 1'-1.5' 12-9-24 @ 950 | 3000 | 1229 | | 246 | | |
| 12-11-24 | TP-34 1'-2' 12-9-24 @ 1030 | 3000 | 3976 | | 795 | | |
| 12-11-24 | TP-34 2'-3' 12-11-24 @ 915 | 3000 | 1547 | | 309 | | QA/QC CP5M - 1549 |
| 12-11-24 | TP-26 2'-2.5 12-11-24 @ 1000 | 3000 | 10464 | | 2093 | | |
| 1-30-25 | Blank | — | 336 | | 67 | | |
| 1-30-25 | 6.6 pCi/g Ref Soil | 3000 | 2327 | | 465 | | |
| 1-30-25 | TP-26 2.5-3.0 1-27-25 @ 1028 | 3000 | 1900 | | 380 | | |
| 1-30-25 | TP-26 3.0-4.0 1-27-25 @ 1037 | 3000 | 2198 | | 440 | | |
| 1-30-25 | TP-21 0-2.0 1-27-25 @ 1056 | 3000 | 41183 | | 8237 | | |
| 1-30-25 | TP-21 2.0-3.0 1-27-25 @ 1105 | 3000 | 1938 | | 388 | | QA/QC CP5M - 1910 |
| 1-30-25 | TP-21 3.0-4.0 1-27-25 @ 1113 | 3000 | 1712 | | 342 | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

# Appendix B
# Radiologic Instrument Calibration and Operational Function Check and Collimated Detector Correlation Documentation

# CERTIFICATE OF CALIBRATION


**LUDLUM MEASUREMENTS, INC.**
501 Oak Street
325-235-5494
Sweetwater, TX 79556, U.S.A.
www.ludlums.com


ACCREDITED
CERT # 4084.01

Model No. / Serial No. 500 / 114513

Customer AVM ENVIRONMENTAL SERVICES INC ORDER NO. 20460064/549833

Date 13-Dec-23 Cal Due Date 13-Dec-24 Cal. Interval 1 Year Procedure 500/Rev 8

☐ New Instrument Instrument Received ☑ Within Tolerance ☐ Out of Tol. ☐ Requiring Repair ☐ Other-See Comments

T. 73 °F RH 36 % Alt 714.2 mm Hg ☑ Meter Zeroed ☑ Mechanical Check

**PULSE WIDTH Uncertainty within 0.85% of reading**

| | As Found | As Left | Acceptable Range (µs) |
|---|---|---|---|
| NEG PULSE | 1.7 | 1.7 | 1.5 - 1.9 |
| POS PULSE | 1.7 | 1.7 | < 2.25 |

**PULSE AMPLITUDE (NEGATIVE) Uncertainty within 1.3% of reading**

| Reference Amplitude | As Found Amplitude Reading | As Left Amplitude Reading | Acceptable Range | Reference Amplitude | As Found Amplitude Reading | As Left Amplitude Reading | Acceptable Range |
|---|---|---|---|---|---|---|---|
| 1 V | 1 V | 1 V | 0.9 - 1.1 | 4 V | 4.1 V | 4.1 V | 3.6 - 4.4 |
| 100 mV | 100 mV | 100 mV | 90 - 110 | 400 mV | 410 mV | 410 mV | 360 - 440 |
| 10 mV | 10 mV | 10 mV | 9 - 11 | 40 mV | 41 mV | 41 mV | 36 - 44 |
| 1 mV | 1 mV | 1 mV | 0.9 - 1.1 | 4 mV | 4.1 mV | 4.1 mV | 3.6 - 4.4 |

**PULSE AMPLITUDE (POSITIVE) Uncertainty within 1.3% of reading**

| Reference Amplitude | As Found Amplitude Reading | As Left Amplitude Reading | Acceptable Range |
|---|---|---|---|
| 3 V | 3 V | 3 V | 2.7 - 3.3 |
| 300 mV | 300 mV | 300 mV | 270 - 330 |
| 30 mV | 30 mV | 30 mV | 27 - 33 |
| 3 mV | 3 mV | 3 mV | 2.7 - 3.3 |

**PULSE FREQUENCY (PERIOD) Uncertainty within 0.46% of reading**

| Pulser Range | As Found Period | As Left Period | Acceptable Range |
|---|---|---|---|
| x 10K | 6.667 | 6.667 | 6.534 - 6.8 |
| x 1K | 66.70 | 66.70 | 65.34 - 68 |
| x 100 | 667.2 | 667.2 | 653.4 - 680 |
| x 10 | 6671 | 6671 | 6534 - 6800 |
| x 1 | 66.71 | 66.71 | 65.34 - 68 |
| x 0.1 | 90 | 90 | 88.2 - 91.8 Counts |

Digital High Voltage Uncertainty within 1.3% of reading

| Reference Voltage | As Found Voltage Reading | As Left Voltage Reading | Acceptable Range |
|---|---|---|---|
| 500 V | | | 490 - 510 |
| 1500 V | | | 1470 - 1530 |

Analog High Voltage Uncertainty within 1.3% of reading

| Reference Voltage | As Found Voltage Reading | As Left Voltage Reading | Acceptable Range |
|---|---|---|---|
| 500 V | 500 | 500 | 475 - 525 |
| 2000 V | 2000 | 2000 | 1900 - 2100 |

| CPM Reading | As Found cpm Reading | As Left cpm Reading | Acceptable Range |
|---|---|---|---|
| MAX | 992 | 992 | 981 - 999 |
| MIN | 0-1 | 0-1 | 0 - 1* |

* READING OF 0-99 IS ACCEPTABLE FOR INSTRUMENTS WITH A S/N 100000 AND BELOW OR MAIN BOARD = 5208-066

**COMMENTS:**

CAL'D W/ 39" CABLE.

Ludlum Measurements, Inc. certifies that the above instrument has been calibrated by standards traceable to the National Institute of Standards and Technology, or to the calibration facilities of other International Standards Organization members, or have been derived from accepted values of natural physical constants or have been derived by the ratio type of calibration techniques.
All pass/fail determinations are based on the manufacturer's specifications without considering uncertainty factors.
Measurement results represent expanded uncertainties expressed at approximately the 95% level of confidence, using a coverage factor of k=2.
The calibration system conforms to the requirements of ANSI/NCSL Z540-1-1994 and ANSI N323AB-2013

ISO/IEC 17025:2017(E)
State of Texas Calibration License No. LO-1963

Reference Instruments:
Frequency Counter Model BK 1856D S/N 332L14297 Cal Date 17-Feb 2023
Oscilloscope Model Tektronix 72-6820 S/N 1102645 Cal Date 11-Oct 2023
Voltmeter Model Fluke 83 V S/N 94000441 Cal Date 2-Jun 2023

Calibrator William Tinsley William Tinsley Title Calibrator Date 13-December 2023
QC'd By [signature] Title Final QC Date 14 Dec 23


This certificate shall not be reproduced except in full, without the written approval of Ludlum Measurements, Inc.




AC Inst. Only ☑ Passed Dielectric (Hi-Pot) and Continuity Test ☐ Failed:

Designer and Manufacturer of Scientific and Industrial Instruments

www.ludlums.com

# CERTIFICATE OF CALIBRATION

LUDLUM MEASUREMENTS, INC.
501 Oak Street
325-235-5494
Sweetwater, TX 79556, U.S.A.

ACCREDITED
CERT # 4084.01

Customer AVM ENVIRONMENTAL SERVICES INC ORDER NO. 20457182/547880

Mfg. Ludlum Measurements, Inc. Model 19 Serial No. 76248

Mfg. _____ Model _____ Serial No. _____

Cal. Date 3-Nov-23 Cal Due Date 3-Nov-24 Cal. Interval 1 Year Meterface 202-1070

Check mark ☑ applies to applicable instr. and/or detector IAW mfg. spec. T. 73 °F RH 37 % Alt 708.1 mm Hg

☐ New Instrument Instrument Received ☐ Within Toler. +-10% ☑ 10-20% ☐ Out of Tol. ☐ Requiring Repair ☐ Other-See comments

☑ Mechanical ck. ☑ Meter Zeroed ☐ Background Subtract ☐ Input Sens. Linearity
☑ F/S Resp. ck ☑ Reset ck. ☐ Window Operation ☑ Geotropism
☑ Audio ck. ☐ Alarm Setting ck. ☑ Batt. ck.

☐ Calibrated in accordance with LMI SOP 14.8 ☑ Calibrated in accordance with LMI SOP 14.9

Instrument Volt Set 800 V Input Sens. 37 mV Det. Oper. 800 V at 37 mV Threshold Dial Ratio _____ = _____ mV

☐ HV Readout (2 points) Ref./Inst. _____ / _____ V Ref./Inst. _____ / _____ V

**COMMENTS:**

Gamma Calibration: GM detectors positioned perpendicular to source except for M 44-9 in which the front of probe faces source.
Multimeter uncertainty within 1.3% of reading, Gamma uncertainty within 5.0% of reading, Neutron uncertainty within 7.0% of reading, Count rate uncertainty within 5.4% of reading

| RANGE/MULTIPLIER | REFERENCE CAL. POINT | INSTRUMENT REC'D "AS FOUND READING" | INSTRUMENT METER READING |
|---|---|---|---|
| 5000 | 4000µR/hr | 4200 µR/hr | 4000 µR/hr |
| 5000 | 1000µR/hr | 1100 | 1000 |
| 500 | 400µR/hr = 69800 cpm | 410 | 400 |
| 500 | 100µR/hr | 110 | 100 |
| 250 | 200µR/hr = 33800 cpm | 210 | 200 |
| 250 | 100µR/hr | 100 | 100 |
| 50 | 6980 cpm | 42 | 40 |
| 50 | 1750 cpm | 10 | 10 |
| 25 | 3380 cpm | 22 | 20 |
| 25 | 845 cpm | 5 | 5 |

Range(s) Calibrated Electronically

| Digital Readout | REFERENCE CAL. POINT | INSTRUMENT RECEIVED | INSTRUMENT METER READING |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| Log Scale | REFERENCE CAL. POINT | INSTRUMENT RECEIVED | INSTRUMENT METER READING |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Ludlum Measurements, Inc certifies that the above instrument has been calibrated by standards traceable to the National Institute of Standards and Technology, or to the calibration facilities of other International Standards Organization members, or have been derived from accepted values of natural physical constants or have been derived by the ratio type of calibration techniques.
All pass/fail determinations are based on the manufacturer's specifications without considering uncertainty factors.
Measurement results represent expanded uncertainties expressed at approximately the 95% level of confidence, using a coverage factor of k=2.
The calibration system conforms to the requirements of ANSI/NCSL Z540-1-1994 and ANSI N323AB-2013

ISO/IEC 17025:2017(E)
State of Texas Calibration License No. LO-1963

**Reference Instruments and/or Sources:** Cs-137 S/N: ☐ 059 ☐ 2171CP ☐ 2261CP ☐ 720 ☐ 734 ☐ 781 ☐ 1131 ☐ 1616 ☐ 1696 ☐ 1909 ☐ 1916CP ☐ 2324/2521
☐ 5717CO ☐ 5719CO ☐ 60646 ☐ 70897 ☐ 73410 ☐ E552 ☐ G112 ☑ 2168CP ☐ S-394 ☐ S-1054 ☐ T10081 ☐ T10082 Neutron Am-241 Be ☐ T-304 Ra-226 ☐ Y982
☐ E551 ☐ 5105 ☐ CSV280

☐ Alpha S/N _____ ☐ Beta S/N _____ ☐ Other _____

☑ m 500 S/N 114520 ☐ Oscilloscope S/N _____ ☑ Multimeter S/N 53950165

Calibrator Sheba Lee Sheba Lee Title Calibrator Date 3-Nov-23

QC'd By _____ Title Final QC Date 3Nov23

This certificate shall not be reproduced except in full, without the written approval of Ludlum Measurements, Inc.


AC Inst. Only ☐ Passed Dielectric (Hi-Pot) and Continuity Test ☐ Failed: _____

Designer and Manufacturer of Scientific and Industrial Instruments

www.ludlums.com

# CERTIFICATE OF CALIBRATION

LUDLUM MEASUREMENTS, INC.
501 Oak Street
325-235-5494
Sweetwater, TX 79556, U.S.A.

ACCREDITED
CERT # 4084.01

Customer AVM ENVIRONMENTAL SERVICES INC ORDER NO. 20479685/ 563226

Mfg. Ludlum Measurements, Inc. Model 19 Serial No. 76248

Mfg. _____ Model _____ Serial No. _____

Cal. Date 4-Oct-24 Cal Due Date 4-Oct-25 Cal. Interval 1 Year Meterface 202-016

Check mark applies to applicable instr. and/or detector IAW mfg. spec. T. 73 °F RH 41 % Alt 708.4 mm Hg

☐ New Instrument Instrument Received ☑ Within Toler. +-10% ☐ 10-20% ☐ Out of Tol. ☐ Requiring Repair ☐ Other-See comments

☑ Mechanical ck. ☑ Meter Zeroed ☐ Background Subtract ☐ Input Sens. Linearity
☑ F/S Resp. ck. ☑ Reset ck. ☐ Window Operation ☑ Geotropism
☑ Audio ck. ☐ Alarm Setting ck. ☑ Batt. ck.

☐ Calibrated in accordance with LMI SOP 14.8 ☑ Calibrated in accordance with LMI SOP 14.9

Instrument Volt Set 800 V Input Sens. 37 mV Det. Oper. _____ V at _____ mV Threshold Dial Ratio _____ = _____ mV

☑ HV Readout (2 points) Ref./Inst. 500 / _____ V Ref./Inst. 1000 / _____ V

**COMMENTS:**

Gamma Calibration: GM detectors positioned perpendicular to source except for M 44-9 in which the front of probe faces source.
Multimeter uncertainty within 1.3% of reading. Gamma uncertainty within 5.0% of reading. Neutron uncertainty within 7.0% of reading. Count rate uncertainty within 5.4% of reading

| RANGE/MULTIPLIER | REFERENCE CAL. POINT | INSTRUMENT REC'D "AS FOUND READING" | INSTRUMENT METER READING |
|---|---|---|---|
| 5000 | 4000µR/hr | 4000 µR/hr | 4000 µR/hr |
| 5000 | 1000µR/hr | 1000 | 1000 |
| 500 | 400µR/hr = 68,500 | 400 | 400 |
| 500 | 100µR/hr | 100 | 100 |
| 250 | 200µR/hr = 35600 | 210 | 200 |
| 250 | 100µR/hr | 100 | 100 |
| 50 | 6850 cpm | 40 | 40 |
| 50 | 1712 cpm | 10 | 10 |
| 25 | 3560 cpm | 21 | 20 |
| 25 | 890 cpm | 5 | 5 |

50, 25 Range(s) Calibrated Electronically

| Digital Readout | REFERENCE CAL. POINT | INSTRUMENT RECEIVED | INSTRUMENT METER READING |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |

| Log Scale | REFERENCE CAL. POINT | INSTRUMENT RECEIVED | INSTRUMENT METER READING |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |

Ludlum Measurements, Inc. certifies that the above instrument has been calibrated by standards traceable to the National Institute of Standards and Technology, or to the calibration facilities of other International Standards Organization members, or have been derived from accepted values of natural physical constants or have been derived by the ratio type of calibration techniques.
All pass/fail determinations are based on the manufacturer's specifications without considering uncertainty factors.
Measurement results represent expanded uncertainties expressed at approximately the 95% level of confidence, using a coverage factor of k=2.
The calibration system conforms to the requirements of ANSI/NCSL Z540-1-1994 and ANSI N323AB-2013

ISO/IEC 17025:2017(E)
State of Texas Calibration License No. LD-1963

**Reference Instruments and/or Sources:** Cs-137 S/N: ☐ 059 ☐ 2171CP ☐ 2261CP ☐ 720 ☐ 734 ☐ 781 ☐ 1131 ☐ 1616 ☐ 1696 ☐ 1909 ☐ 1916CP ☐ 2324/2521
☐ 5717CO ☐ 5719CO ☐ 60646 ☐ 70897 ☐ 73410 ☐ E552 ☐ G112 ☑ 2166CP ☐ S-394 ☐ S-1054 ☐ T10081 ☐ T10082 Neutron Am-241 Be ☐ T-304 Ra-226 ☐ Y982
☐ E551 ☐ 5105 ☐ CSV280

☐ Alpha S/N _____ ☐ Beta S/N _____ ☐ Other _____

☑ m 500 S/N 371845 ☐ Oscilloscope S/N _____ ☑ Multimeter S/N 60050420

rator Andrew Fuller Andrew J Fuller Title Calibrator Date 4 OCT 24

QC'd By _____ Title Final QC Date 5 Oct 24

This certificate shall not be reproduced except in full, without the written approval of Ludlum Measurements, Inc.


AC Inst. Only ☐ Passed Dielectric (Hi-Pot) and Continuity Test ☐ Failed: _____

**AVM Environmental Services Inc.**
**Scaler/Ratemeter - Detector Calibration Form**



Scaler/Ratemeter: L2221 S# 290801
Detector: SPA-3 S# 408522-30

Source: U308 ore in can S# FC-2 Strength 1%

Scaler/Ratemeter Threshhold set @ 10 mV, Window IN/OUT Out, Window N/A mV

| HV | Reading, CPM (Source) | Reading, CPM (Background) |
|---|---|---|
| 500 | 17200 | 470 |
| 550 | 37012 | 738 |
| 600 | 57214 | 998 |
| 650 | 71774 | 1379 |
| 700 | 84865 | 1633 |
| 750 | 93899 | 1765 |
| 800 | 95561 | 1837 |
| 850 | 96093 | 1895 |
| 900 | 97180 | 2012 |
| 950 | 97636 | 2018 |
| 1000 | 100155 | 2037 |
| 1050 | 113726 | 2090 |
| 1100 | 133647 | 2249 |
| 1150 | 161780 | 2497 |
| 1200 | 199910 | 3198 |
| 1250 | | |
| 1300 | | |
| 1350 | | |
| 1400 | | |

**Background reading at designated function check location in AVM office.**

| Count # | Reading (CPM) Bare | Collimated |
|---|---|---|
| 1 | 8139 | 3129 |
| 2 | 8284 | 3144 |
| 3 | 8301 | 3004 |
| 4 | 8107 | 3170 |
| 5 | 8155 | 3171 |
| Average | 8197 | 3124 |

FC Range (6524-9786) (2537-3805)

**Count Readings with 1 percent $U_3O_8$ can directly under collimated detector on designated function check location in AVM office.**

| Count # | Reading (CPM) |
|---|---|
| 1 | 96354 |
| 2 | 95928 |
| 3 | 96716 |
| 4 | 96662 |
| 5 | 96241 |
| Average | 96380 |

HV Set @ 900 VDC (Instrument) 900 VDC (DVM Fluke 8020B)

Input Sensitivity (THR), mV 10

Function Check with 1 percent $U_3O_8$ ore in can. Can Directly under the detector in the collimator.
Acceptable Function check range is 77104 to 115656 CPM

**Notes:**

Date 2-19-24 By

**AVM Environmental Services Inc.**
**Scaler/Ratemeter - Detector Calibration Form**



Scaler/Ratemeter L2221 S# 290801
Detector SPA-3 S# 408522-30

Source U308 ore in con S# EC-2 Strength 1%

Scaler/Ratemeter Threshhold set @ 10 mV, Window IN/OUT out, Window N/A mV

HV Set @ 900 VDC (Instrument) 900 VDC (DVM Fluke 8020B)

**Count Readings for Calibration Pad GPB (0.0 ± 0.3 pCi/gm Ra-226)**

| | Bare (Uncollimated) @ 1' | | Collimated @ 1' | |
|---|---|---|---|---|
| #1 | 11498 | cpm | 2766 | cpm |
| #2 | 11820 | cpm | 2839 | cpm |
| #3 | 11614 | cpm | 2849 | cpm |
| #4 | 11823 | cpm | 2883 | cpm |
| #5 | 11777 | cpm | 2772 | cpm |
| BKG Average | 11706 | cpm | 2812 | cpm |

**Count Readings for Calibration Pad GPL (87.78 pCi/gm Ra-226)**

| | Bare (Uncollimated) @ 1' | | Collimated @ 1' | |
|---|---|---|---|---|
| #1 | 90635 | cpm | 53328 | cpm |
| #2 | 90696 | cpm | 53884 | cpm |
| #3 | 90626 | cpm | 53443 | cpm |
| #4 | 90778 | cpm | 54004 | cpm |
| #5 | 91414 | cpm | 53996 | cpm |
| Gross Average | 90830 | cpm | 53731 | cpm |
| Net Source Pad | 79123 | cpm | 50919 | cpm |
| Eff(net cpm/87.78 pCi/gm | 901 | cpm/pCi/gm | 580 | cpm/pCi/gm |

**µR/hr Reading for Calibration Pad GPL (87.78 pCi/gm Ra-226)**

Ludlum Model 19 serial # 76248

Reading @ 1' 115 µR/hr
$1.276^{-03}$ µR/hr/cpm

Date 2-19-24 By

**AVM Environmental Services Inc.**
L2221 SCA/L44-20 Energy Calibration Form

SCA: L2221, SR #290801 Detector: Ludlum 44-20 (3x3 Nal Scintillator)

Calibration Source: Cs-137 Check Source, 5 uCi (August 2008) For 662 KeV Peak Cal

Threshold (input sensitivity) 652

Window, In/Out IN Window 20

HV Initial 100, At Peak 575

Maximum CPM: 204503 Background CPM: 9

HV Set @ 575 VDC

For Bi-214 609.2 KeV Peak (559 - 659 KeV ROI), Set Threshold @ 559, Window @ 10mV

Calibration Check w 1% U3O8 Ore Check Source: 15656 CPM

BKG = 63 cpm

Date 9-30-24 Calibrated By

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S# 68782 , Detector L44-20 S# 295573
Instrument Calibration Date: 2-14-24 / 9-30-24 , Instrument Function Check Performed: ✓
Survey Area/Unit Description Mt. Taylor Mine Site - Correlation Calibration


Area exposure rate: 12-14 uR/hr.

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CPSM | Weight Corrected CPSM | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 9-30-24 | Blank | - | 325 | - | 65 | | |
| 9-30-24 | 6.6 pCi/g Ref. Soil | 3000 | 2600 | - | 520 | | |
| 9-30-24 | 25 pCi/g Ref. Soil | 3000 | 9770 | - | 1954 | | |
| 9-30-24 | 50 pCi/g Ref. Soil | 3000 | 18386 | - | 3677 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

## AVM Environmental Services
## Ex-Situ Soil Screening Gamma Radiation Level to Ra-226 Correlation
## Mt. Taylor Mine Site Subsurface Soil Investigation

| Reference Soil ID | Date | Ra-226 pCi/g | Wt gms | 609 KeV CP5Min Gross (3x3 Nal Detector) | CPM |
|---|---|---|---|---|---|
| Blank | 9/30/2024 | - | - | 325 | 65 |
| 6.6 pCi/g Ra-226 Ref Soil | 9/30/2024 | 6.6 | 3000 | 2600 | 520 |
| 25 pCi/g Ra-226 Ref Soil | 9/30/2024 | 25 | 3000 | 9770 | 1954 |
| 50 pCi/g Ra-226 Ref Soil | 9/30/2024 | 50 | 3000 | 18386 | 3677 |



**AVM Environmental Services, Inc.**
**Ludlum SCA L2221 - 44-20 3x3 NaI Detector Function Check**
**559 - 659 KeV Gamma Radiation Soil Screening**

L2221 #68782

Ludlum 44-20 3x3 NaI Detector, #PR295573

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Acceptable background Count (cpm) Range (20%) 50 to 76

Acceptable Source Count (cpm) Range (20%) 12525 to 18787

| Date | Physical Check | Cal Date | Battery(1) Volts or OK | HV Volts | Threshhold mV (2) | Window mV | Window In/Out | BKG Counts cpm | Source Counrts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9-30-24 | ✓ | 9-30-24 | ok | 575 | 559 | 10 | in | 63 | 15656 | y | — | VP |
| 10-8-24 | ✓ | 9-30-24 | ok | 575 | 559 | 10 | in | 65 | 15453 | y | — | VP |
| 10-9-24 | ✓ | 9-30-24 | ok | 583 | 559 | 10 | in | | 15588 | y | — | VP |
| 10-15-24 | ✓ | 9-30-24 | ok | 575 | 559 | 10 | in | 63 | 15698 | y | — | VP |
| 10-16-24 | ✓ | 9-30-24 | OK | 575 | 559 | 10 | in | 68 | 15552 | y | — | VP |
| 10-29-24 | ✓ | 9-30-24 | OK | 575 | 559 | 10 | in | 63 | 15524 | y | — | VP |
| 11-26-24 | ✓ | 9-30-24 | OK | 578 | 559 | 10 | in | 64 | 15657 | y | — | VP |
| 12-9-24 | ✓ | 9-30-24 | OK | 579 | 559 | 10 | in | 68 | 15674 | y | — | VP |
| 12-11-24 | ✓ | 9-30-24 | ok | 578 | 559 | 10 | in | 66 | 15841 | y | — | VP |
| 1-30-25 | ✓ | 9-30-24 | ok | 580 | 559 | 10 | in | 67 | 15891 | y | — | VP |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 220 mV; (3) Window @ 440, must be IN

**AVM Environmental Services, Inc.**
**Scaler/Ratemeter - 2" x 2" NaI Detector Function Check**

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

2" x 2" NaI Detector ID: SPA-3 S#408522-30

Acceptable background Count (cpm) Range (20%) 6524 to 9786 (Bare)

Acceptable background Count (cpm) Range (20%) 2537 to 3805 (collimated)

Acceptable Source Count (cpm) Range (20%) 77104 to 115656

| Date | Scaler/Ratemeter | Physical Check | Cal Due | Battery[1] Volts or OK | HV Volts | THR mV[2] | Window In or OUT[3] | C.C.[4] | BKG Counts cpm | Source Counts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 10-28-24 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8134 Bare / 3293 Coll. | 97448 | y | — | VP |
| 11-18-24 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8439 Bare / 3190 Coll. | 98377 | y | — | VP |
| 11-22-24 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8503 Bare / 3273 Coll. | 99127 | y | — | VP |
| 11-25-24 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8411 Bare / 3230 Coll. | 98897 | y | — | VP |
| 12-2-24 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8316 Bare / 3196 Coll. | 97663 | y | — | VP |
| 12-4-24 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8271 Bare / 3240 Coll. | 98336 | y | — | VP |
| 12-5-24 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8377 Bare / 3260 Coll. | 98162 | y | — | VP |
| 12-9-24 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8413 Bare / 3457 Coll. | 98760 | y | — | VP |
| 12-11-24 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8361 Bare / 3241 Coll. | 97843 | y | — | VP |
| 1-27-25 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8841 Bare / 3396 Coll. | 99501 | y | — | VP |
| 2-5-25 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8508 Bare / 3428 Coll. | 98671 | y | — | VP |
| 2-6-25 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8309 Bare / 3293 Coll. | 99461 | y | — | VP |
| 2-10-25 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8448 Bare / 3490 Coll. | 98099 | y | — | VP |
| 2-13-25 | L2221 S#290801 | ✓ | 2-19-24 | ok | 900 | 10 | out | 1 | 8308 Bare / 3333 Coll. | 98664 | y | — | VP |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 10.0 mV; (3) Window Position must be OUT; (4) CC on L2241-2 set at 0.001
For L2241-2 Check HV and Threshold using Ludlum 500 pulser.

**AVM Environmental Services, Inc.**
**Scaler/Ratemeter - 2" x 2" NaI Detector Function Check**

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

2" x 2" NaI Detector ID: SPA-3 S#408522-20

Acceptable background Count (cpm) Range (20%) 6524 to 9786 (Bare)

Acceptable background Count (cpm) Range (20%) 2537 to 3805 (collimated)

Acceptable Source Count (cpm) Range (20%) 77104 to 115656

| Date | Scaler/Ratemeter | Physical Check | Cal Due | Battery[1] Volts or OK | HV Volts | THR mV[2] | Window In or OUT[3] | C.C.[4] | BKG Counts cpm | Source Counts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 8-28-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8180 Bare<br>3342 Coll. | 99633 | Y | — | VP |
| 8-30-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8151 Bare<br>3141 Coll. | 94361 | Y | — | VP |
| 9-3-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8019 Bare<br>3008 Coll. | 94435 | Y | — | VP |
| 9-4-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8269 Bare<br>3172 Coll. | 95972 | Y | — | VP |
| 9-9-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8289 Bare<br>3460 Coll. | 96559 | Y | — | VP |
| 9-10-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8117 Bare<br>3234 Coll. | 94663 | Y | — | VP |
| 9-11-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8529 Bare<br>3263 Coll. | 96573 | Y | — | VP |
| 9-17-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8079 Bare<br>3096 Coll. | 97763 | Y | — | VP |
| 9-19-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8862 Bare<br>3380 Coll. | 97608 | Y | — | VP |
| 10-7-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8805 Bare<br>3379 Coll. | 95735 | Y | — | VP |
| 10-8-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8140 Bare<br>3311 Coll. | 97124 | Y | — | VP |
| 10-9-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8370 Bare<br>3145 Coll. | 97321 | Y | — | VP |
| 10-15-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8242 Bare<br>3290 Coll. | 95964 | Y | — | VP |
| 10-16-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8395 Bare<br>3015 Coll. | 95244 | Y | — | VP |
| 10-21-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8171 Bare<br>3070 Coll. | 98844 | Y | — | VP |
| 10-23-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8167 Bare<br>3314 Coll. | 98553 | Y | — | VP |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 10.0 mV; (3) Window Position must be OUT; (4) CC on L2241-2 set at 0.001
For L2241-2 Check HV and Threshold using Ludlum 500 pulser.

**AVM Environmental Services, Inc.**
**Scaler/Ratemeter - 2" x 2" NaI Detector Function Check**

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

2" x 2" NaI Detector ID: SPA-3 S#408522-30

Acceptable background Count (cpm) Range (20%) 6524 to 9786 (Bare)

Acceptable background Count (cpm) Range (20%) 2537 to 3805 (collimated)

Acceptable Source Count (cpm) Range (20%) 77104 to 115656

| Date | Scaler/Ratemeter | Physical Check | Cal Due | Battery[1] Volts or OK | HV Volts | THR mV[2] | Window In or OUT[3] | C.C.[4] | BKG Counts cpm | Source Counrts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2-19-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8351 Bare / 3120 Coll. | 96783 | y | – | VP |
| 4-7-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8272 Bare / 3110 Coll. | 97815 | y | – | VP |
| 4-8-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8249 Bare / 3095 Coll. | 96288 | y | – | VP |
| 4-10-24 | L2221 S#290801 | ✓ | 2-19-25 | Ok | 900 | 10 | out | 1 | 8440 Bare / 3065 Coll. | 96064 | y | – | VP |
| 4-15-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8395 Bare / 3119 Coll. | 97475 | y | – | VP |
| 4-16-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8411 Bare / 3124 Coll. | 96227 | y | – | VP |
| 4-17-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8401 Bare / 3193 Coll. | 97111 | y | – | VP |
| 4-22-24 | L2221 S#290801 | ✓ | 2-19-25 | OK | 900 | 10 | out | 1 | 8093 Bare / 3199 Coll. | 96431 | y | – | VP |
| 4-23-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8205 Bare / 3092 Coll. | 95968 | y | – | VP |
| 4-30-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8264 Bare / 3263 Coll. | 96356 | y | – | VP |
| 7-15-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8318 Bare / 3111 Coll. | 96914 | y | – | VP |
| 7-16-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8211 Bare / 3099 Coll. | 97277 | y | – | VP |
| 7-17-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8238 Bare / 3221 Coll. | 100091 | y | – | VP |
| 7-23-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8222 Bare / 3240 Coll. | 98144 | y | – | VP |
| 8-14-23 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8120 Bare / 3223 Coll. | 98757 | y | – | VP |
| 8-22-24 | L2221 S#290801 | ✓ | 2-19-25 | ok | 900 | 10 | out | 1 | 8224 Bare / 3204 Coll. | 99197 | y | – | VP |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 10.0 mV; (3) Window Position must be OUT; (4) CC on L2241-2 set at 0.001
For L2241-2 Check HV and Threshold using Ludlum 500 pulser.

**AVM Environmental Services, Inc.**
**Micro R Meter Function Check Form**

Micro R Meter: Ludlum 19, SR#76248

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Function Check @ Calibration 135

Acceptable Function Check Reading (uR/hr) Range (20%) 108 to 162

| Date | Physical Check | Cal Date | Battery[1] Volts or OK | BKG Reading uR/hr | Source Reading[2] uR/hr | Within Acceptable Range Y or N | Cal Due | Tech |
|---|---|---|---|---|---|---|---|---|
| 12-16-24 | ✓ | 10-4-24 | ok | 8-10 | 140 | Y | 10-4-25 | VP |
| 12-18-24 | ✓ | 10-4-24 | ok | 8-10 | 135 | Y | 10-4-25 | VP |
| 12-19-24 | ✓ | 10-4-24 | ok | 8-10 | 140 | Y | 10-4-25 | VP |
| 12-23-24 | ✓ | 10-4-24 | ok | 8-10 | 130 | Y | 10-4-25 | VP |
| 1-7-25 | ✓ | 10-4-24 | ok | 8-10 | 135 | Y | 10-4-25 | VP |
| 1-16-25 | ✓ | 10-4-24 | ok | 8-10 | 130 | Y | 10-4-25 | VP |
| 1-17-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | Y | 10-4-25 | VP |
| 1-23-25 | ✓ | 10-4-24 | ok | 8-10 | 135 | Y | 10-4-25 | VP |
| 1-27-25 | ✓ | 10-4-24 | ok | 8-10 | 130 | Y | 10-4-25 | VP |
| 2-5-25 | ✓ | 10-4-24 | ok | 8-10 | 130 | Y | 10-4-25 | VP |
| 2-6-25 | ✓ | 10-4-24 | ok | 8-10 | 130 | Y | 10-4-25 | VP |
| 2-10-25 | ✓ | 10-4-24 | ok | 10-12 | 140 | Y | 10-4-25 | VP |
| 2-13-25 | ✓ | 10-4-24 | ok | 8-10 | 135 | Y | 10-4-25 | VP |
| 2-19-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | Y | 10-4-25 | VP |
| 2-20-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | Y | 10-4-25 | VP |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

Note: (1) Battery Voltage must be within BAT TEST Range (2) Function Check Source must be placed in the circle on the front side of the meter

**AVM Environmental Services, Inc.**
**Micro R Meter Function Check Form**

Micro R Meter: Ludlum 19, SR#76248

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Function Check @ Calibration 135

Acceptable Function Check Reading (uR/hr) Range (20%) 108 to 162

| Date | Physical Check | Cal Date | Battery[1] Volts or OK | BKG Reading uR/hr | Source Reading[2] uR/hr | Within Acceptable Range Y or N | Cal Due | Tech |
|---|---|---|---|---|---|---|---|---|
| 10-14-24 | ✓ | 10-4-24 | ok | 10-12 | 130 | y | 10-4-25 | VP |
| 10-15-24 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 10-16-24 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 10-21-24 | ✓ | 10-4-24 | ok | 8-10 | 130 | y | 10-4-25 | VP |
| 10-23-24 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 10-29-24 | ✓ | 10-4-24 | ok | 8-10 | 130 | y | 10-4-25 | VP |
| 10-31-24 | ✓ | 10-4-24 | ok | 10-12 | 130 | y | 10-4-25 | VP |
| 11-11-24 | ✓ | 10-4-24 | ok | 8-10 | 130 | y | 10-4-25 | VP |
| 11-12-24 | ✓ | 10-4-24 | ok | 8-10 | 130 | y | 10-4-25 | VP |
| 11-18-24 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 11-20-24 | ✓ | 10-4-24 | ok | 8-10 | 130 | y | 10-4-25 | VP |
| 11-22-24 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 11-25-24 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 11-26-24 | ✓ | 10-4-24 | ok | 8-10 | 130 | y | 10-4-25 | VP |
| 12-2-24 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 12-4-24 | ✓ | 10-4-24 | ok | 8-10 | 130 | y | 10-4-25 | VP |
| 12-11-24 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 12-12-24 | ✓ | 10-4-24 | ok | 8-10 | 130 | y | 10-4-25 | VP |

Note: (1) Battery Voltage must be within BAT TEST Range (2) Function Check Source must be placed in the circle on the front side of the meter

**AVM Environmental Services, Inc.**
**Micro R Meter Function Check Form**

Micro R Meter: Ludlum 19, SR#76248

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Function Check @ Calibration 135

Acceptable Function Check Reading (uR/hr) Range (20%) 108 to 162

| Date | Physical Check | Cal Date | Battery(1) Volts or OK | BKG Reading uR/hr | Source Reading (2) uR/hr | Within Acceptable Range Y or N | Cal Due | Tech |
|---|---|---|---|---|---|---|---|---|
| 9-3-24 | ✓ | 11-3-23 | OK | 8-10 | 135 | Y | 11-3-24 | VP |
| 9-4-24 | ✓ | 11-3-23 | OK | 8-10 | 140 | Y | 11-3-24 | VP |
| 9-9-24 | ✓ | 11-3-23 | OK | 8-10 | 130 | Y | 11-3-24 | VP |
| 9-11-24 | ✓ | 11-3-23 | ok | 8-10 | 130 | Y | 11-3-24 | VP |
| 9-16-24 | ✓ | 11-3-23 | ok | 8-10 | 140 | Y | 11-3-24 | VP |
| 9-17-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | Y | 11-3-24 | VP |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

Note: (1) Battery Voltage must be within BAT TEST Range (2) Function Check Source must be placed in the circle on the front side of the meter

**AVM Environmental Services, Inc.**
**Micro R Meter Function Check Form**

Micro R Meter: Ludlum 19, SR#76248

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Function Check @ Calibration 135


Acceptable Function Check Reading (uR/hr) Range (20%) 108 to 162

| Date | Physical Check | Cal Date | Battery[1] Volts or OK | BKG Reading uR/hr | Source Reading[2] uR/hr | Within Acceptable Range Y or N | Cal Due | Tech |
|---|---|---|---|---|---|---|---|---|
| 11-13-23 | ✓ | 11-3-23 | ok | 10-12 | 130 | y | 11-3-24 | VP |
| 4-7-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | y | 11-3-24 | VP |
| 4-8-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | y | 11-3-24 | VP |
| 4-10-24 | ✓ | 11-3-23 | ok | 10-12 | 130 | y | 11-3-24 | VP |
| 4-15-24 | ✓ | 11-3-23 | ok | 10-12 | 130 | y | 11-3-24 | VP |
| 4-16-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | y | 11-3-24 | VP |
| 4-17-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | y | 11-3-24 | VP |
| 4-22-24 | ✓ | 11-3-23 | ok | 10-12 | 130 | y | 11-3-24 | VP |
| 4-23-24 | ✓ | 11-3-23 | ok | 10-12 | 130 | y | 11-3-24 | VP |
| 4-30-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | y | 11-3-24 | VP |
| 6-25-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | y | 11-3-24 | VP |
| 6-26-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | y | 11-3-24 | VP |
| 7-2-24 | ✓ | 11-3-23 | ok | 10-12 | 130 | y | 11-3-24 | VP |
| 7-9-24 | ✓ | 11-3-23 | ok | 10-12 | 140 | y | 11-3-24 | VP |
| 8-14-24 | ✓ | 11-3-23 | ok | 10-12 | 130 | y | 11-3-24 | VP |
| 8-22-24 | ✓ | 11-3-23 | ok | 10-12 | 130 | y | 11-3-24 | VP |
| 8-28-24 | ✓ | 11-3-23 | ok | 8-10 | 140 | y | 11-3-24 | VP |
| 8-30-24 | ✓ | 11-3-23 | ok | 10-12 | 130 | y | 11-3-24 | VP |

Note: (1) Battery Voltage must be within BAT TEST Range (2) Function Check Source must be placed in the circle on the front side of the meter

## Surface Soil Ra-226 to Gamma Radiation Level Correlation
## Mount Taylor Mine Site

| Survey Date | Survey Point ID/Description | Survey Point Coordinate NAD83 StatePlane NM West, Feet | | Static Gamma Radiation Survey | | Sample Laboratory Analysis | Gamma Exposure Rate µR/hr |
|---|---|---|---|---|---|---|---|
| | | Northing | Easting | Bare 2x2 NaI Detector CPM | Collimated (0.5" Pb) 2x2 NaI Detector CPM | Ra-226 pCi/g | |
| 05/17/23 | WBSB-01 | 1,581,413 | 2,782,866 | 26,897 | 6,297 | **0.9** | 33 |
| 05/17/23 | WBSB-02 | 1,581,390 | 2,782,444 | 26,749 | 6,350 | **1.5** | 33 |
| 05/17/23 | WBSB-03 | 1,581,356 | 2,783,329 | 24,529 | 6,073 | **3.2** | 31 |
| 05/17/23 | WBSB-04 | 1,581,339 | 2,782,706 | 30,064 | 6,069 | **1.5** | 37 |
| 05/17/23 | WBSB-05 | 1,581,329 | 2,783,062 | 31,828 | 6,945 | **2.1** | 41 |
| 05/17/23 | WBSB-06 | 1,581,271 | 2,782,942 | 35,410 | 7,288 | **1.3** | 47 |
| 05/17/23 | WBSB-07 | 1,581,187 | 2,783,253 | 37,965 | 8,183 | **3.7** | 47 |
| 05/17/23 | WBSB-08 | 1,581,164 | 2,782,988 | 55,849 | 11,042 | **9.7** | 70 |
| 05/31/23 | WBSB-09 | 1,581,254 | 2,782,870 | 36,491 | 6,599 | **1.2** | 44 |
| 05/31/23 | WBSB-10 | 1,581,263 | 2,783,140 | 34,898 | 7,286 | **3.5** | 48 |
| 05/31/23 | WBSB-11 | 1,581,277 | 2,783,335 | 29,002 | 6,602 | **2.7** | 34 |




SUMMARY OUTPUT

### Regression Statistics

| | |
|---|---|
| Multiple R | 0.91 |
| R Square | 0.83 |
| Adjusted R Square | 0.81 |
| Standard Error | 1.08 |
| Observations | 11 |

**ANOVA**

| | df | SS | MS | F | Significance F |
|---|---|---|---|---|---|
| Regression | 1 | 50.92 | 50.92 | 43.97 | 9.58E-05 |
| Residual | 9 | 10.42 | 1.16 | | |
| Total | 10 | 61.35 | | | |

| | Coefficients | Standard Error | t Stat | P-value | Lower 95% | Upper 95% | Lower 95.0% | Upper 95.0% |
|---|---|---|---|---|---|---|---|---|
| Intercept | -8.41 | 1.73 | -4.87 | 0.00089 | -12.32 | -4.50 | -12.32 | -4.50 |
| X Variable 1 | 0.00 | 0.00 | 6.63 | 0.00010 | 0.00104 | 0.00211 | 0.00104 | 0.00211 |

**Appendix C**
**Soil Sample COC and Laboratory Analytical Results Report**

ENERGY LABORATORIES
Trust our People. Trust our Data.
www.energylab.com
Billings, MT 406.252.6325 • Casper, WY 307.235.0515
Gillette, WY 307.686.7175 • Helena, MT 406.442.0711

# ANALYTICAL SUMMARY REPORT

January 31, 2025

Rio Grande Resources Corporation
PO Box 1150
Grants, NM 87020-1150

Work Order: C24120480 Quote ID: C16056

AUM - North Control Area Sampling

Project Name: MTM NCA Characterization

Energy Laboratories, Inc. Casper WY received the following 12 samples for Rio Grande Resources Corporation on 12/18/2024 for analysis.

| Lab ID | Client Sample ID | Collect Date | Receive Date | Matrix | Test |
|---|---|---|---|---|---|
| C24120480-001 | TP-01 [6-12]Inches | 10/08/24 9:30 | 12/18/24 | Soil | Gamma Sample Preparation Drying/Grinding, Radiochemistry Gross Gamma |
| C24120480-002 | Inv-07 [1.5-2]Feet | 10/08/24 10:55 | 12/18/24 | Soil | Same As Above |
| C24120480-003 | TP-13 [6-12]Inches | 10/09/24 8:40 | 12/18/24 | Soil | Same As Above |
| C24120480-004 | TP-19 [4.5-5]Feet | 10/16/24 8:45 | 12/18/24 | Soil | Same As Above |
| C24120480-005 | TP-24 [6-12]Inches | 10/16/24 10:20 | 12/18/24 | Soil | Same As Above |
| C24120480-006 | TP-40 [6-12]Inches | 10/28/24 10:35 | 12/18/24 | Soil | Same As Above |
| C24120480-007 | TP-22 [1.5-2]Feet | 10/28/24 11:20 | 12/18/24 | Soil | Same As Above |
| C24120480-008 | TP-33 [6-12]Inches | 11/25/24 11:00 | 12/18/24 | Soil | Same As Above |
| C24120480-009 | TP-30 [6-12]Inches | 12/04/24 8:30 | 12/18/24 | Soil | Same As Above |
| C24120480-010 | TP-32 [1-1.5]Feet | 12/09/24 9:50 | 12/18/24 | Soil | Same As Above |
| C24120480-011 | TP-34 [2-3]Feet | 12/11/24 9:15 | 12/18/24 | Soil | Same As Above |
| C24120480-012 | DS-NCA-01 [6-12]Inches | 12/11/24 10:00 | 12/18/24 | Soil | Same As Above |

The analyses presented in this report were performed by Energy Laboratories, Inc., 2393 Salt Creek Hwy, Casper, WY 82601-9601, unless otherwise noted. Any exceptions or problems with the analyses are noted in the report package. Any issues encountered during sample receipt are documented in the Work Order Receipt Checklist.

The results as reported relate only to the item(s) submitted for testing. This report shall be used or copied only in its entirety. Energy Laboratories, Inc. is not responsible for the consequences arising from the use of a partial report.

Energy Laboratories, Inc. verifies the reported results for the analysis has been technically reviewed and approved for release.

If you have any questions regarding these test results, please contact your Project Manager.

Ashley Wilson
Project Manager

Digitally signed by
Ashley L. Wilson
Date: 2025.01.31 08:26:17 -07:00

**CLIENT:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Work Order:** C24120480

**Report Date:** 01/31/25

# CASE NARRATIVE

ORIGINAL SAMPLE SUBMITTAL(S)
All original sample submittals have been returned with the data package.

SAMPLE TEMPERATURE COMPLIANCE: 4°C (±2°C)
Temperature of samples received may not be considered properly preserved by accepted standards. Samples that are hand delivered immediately after collection shall be considered acceptable if there is evidence that the chilling process has begun.

GROSS ALPHA ANALYSIS
Method 900.0 for gross alpha and gross beta is intended as a drinking water method for low TDS waters. Data provided by this method for non potable waters should be viewed as inconsistent.

RADON IN AIR ANALYSIS
The desired exposure time is 48 hours (2 days). The time delay in returning the canister to the laboratory for processing should be as short as possible to avoid excessive decay. Maximum recommended delay between end of exposure to beginning of counting should not exceed 8 days.

SOIL/SOLID SAMPLES
All samples reported on an as received basis unless otherwise indicated.

ATRAZINE, SIMAZINE AND PCB ANALYSIS
Data for PCBs, Atrazine and Simazine are reported from EPA 525.2. PCB data reported by ELI reflects the results for seven individual Aroclors. When the results for all seven are ND (not detected), the sample meets EPA compliance criteria for PCB monitoring.

SUBCONTRACTING ANALYSIS
Subcontracting of sample analyses to an outside laboratory may be required. If so, ENERGY LABORATORIES will utilize its branch laboratories or qualified contract laboratories for this service. Any such laboratories will be indicated within the Laboratory Analytical Report.

BRANCH LABORATORY LOCATIONS
eli-b - Energy Laboratories, Inc. - Billings, MT
eli-g - Energy Laboratories, Inc. - Gillette, WY
eli-h - Energy Laboratories, Inc. - Helena, MT

ISO 17025 DISCLAIMER:
The results of this Analytical Report relate only to the items submitted for analysis.

ENERGY LABORATORIES, INC. - CASPER,WY certifies that certain method selections contained in this report meet requirements as set forth by the above accrediting authorities. Some results requested by the client may not be covered under these certifications. All analysis data to be submitted for regulatory enforcement should be certified in the sample state of origin. Please verify ELI's certification coverage by visiting www.energylab.com

ELI appreciates the opportunity to provide you with this analytical service. For additional information and services visit our web page www.energylab.com.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Lab ID:** C24120480-001
**Client Sample ID:** TP-01 [6-12]

**Report Date:** 01/31/25
**Collection Date:** 10/08/24 09:30
**DateReceived:** 12/18/24
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.6 | pCi/g-dry | U | | | E901.1M | 01/21/25 09:56 / haw |
| Radium 224 precision (±) | 2.2 | pCi/g-dry | | | | E901.1M | 01/21/25 09:56 / haw |
| Radium 224 MDC | 3.6 | pCi/g-dry | | | | E901.1M | 01/21/25 09:56 / haw |
| Radium 226 | 1.2 | pCi/g-dry | | | | E901.1M | 01/21/25 09:56 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 01/21/25 09:56 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 01/21/25 09:56 / haw |
| Radium 228 | 1.7 | pCi/g-dry | | | | E901.1M | 01/21/25 09:56 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/21/25 09:56 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 01/21/25 09:56 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Lab ID:** C24120480-002
**Client Sample ID:** Inv-07 [1.5-2]

**Report Date:** 01/31/25
**Collection Date:** 10/08/24 10:55
**DateReceived:** 12/18/24
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.0 | pCi/g-dry | U | | | E901.1M | 01/21/25 11:59 / haw |
| Radium 224 precision (±) | 2.5 | pCi/g-dry | | | | E901.1M | 01/21/25 11:59 / haw |
| Radium 224 MDC | 4.2 | pCi/g-dry | | | | E901.1M | 01/21/25 11:59 / haw |
| Radium 226 | 8.6 | pCi/g-dry | | | | E901.1M | 01/21/25 11:59 / haw |
| Radium 226 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/21/25 11:59 / haw |
| Radium 226 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 01/21/25 11:59 / haw |
| Radium 228 | 0.3 | pCi/g-dry | U | | | E901.1M | 01/21/25 11:59 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/21/25 11:59 / haw |
| Radium 228 MDC | 0.6 | pCi/g-dry | | | | E901.1M | 01/21/25 11:59 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Lab ID:** C24120480-003
**Client Sample ID:** TP-13 [6-12]

**Report Date:** 01/31/25
**Collection Date:** 10/09/24 08:40
**DateReceived:** 12/18/24
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.1 | pCi/g-dry | U | | | E901.1M | 01/21/25 14:11 / haw |
| Radium 224 precision (±) | 2.7 | pCi/g-dry | | | | E901.1M | 01/21/25 14:11 / haw |
| Radium 224 MDC | 4.4 | pCi/g-dry | | | | E901.1M | 01/21/25 14:11 / haw |
| Radium 226 | 7.2 | pCi/g-dry | | | | E901.1M | 01/21/25 14:11 / haw |
| Radium 226 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/21/25 14:11 / haw |
| Radium 226 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 01/21/25 14:11 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 01/21/25 14:11 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/21/25 14:11 / haw |
| Radium 228 MDC | 0.5 | pCi/g-dry | | | | E901.1M | 01/21/25 14:11 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Lab ID:** C24120480-004
**Client Sample ID:** TP-19 [4.5-5]

**Report Date:** 01/31/25
**Collection Date:** 10/16/24 08:45
**DateReceived:** 12/18/24
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.8 | pCi/g-dry | U | | | E901.1M | 01/21/25 17:35 / haw |
| Radium 224 precision (±) | 2.0 | pCi/g-dry | | | | E901.1M | 01/21/25 17:35 / haw |
| Radium 224 MDC | 3.3 | pCi/g-dry | | | | E901.1M | 01/21/25 17:35 / haw |
| Radium 226 | 1.1 | pCi/g-dry | | | | E901.1M | 01/21/25 17:35 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 01/21/25 17:35 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 01/21/25 17:35 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1M | 01/21/25 17:35 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 01/21/25 17:35 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 01/21/25 17:35 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Lab ID:** C24120480-005
**Client Sample ID:** TP-24 [6-12]

**Report Date:** 01/31/25
**Collection Date:** 10/16/24 10:20
**DateReceived:** 12/18/24
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.8 | pCi/g-dry | U | | | E901.1M | 01/22/25 09:54 / haw |
| Radium 224 precision (±) | 2.5 | pCi/g-dry | | | | E901.1M | 01/22/25 09:54 / haw |
| Radium 224 MDC | 4.1 | pCi/g-dry | | | | E901.1M | 01/22/25 09:54 / haw |
| Radium 226 | 3.8 | pCi/g-dry | | | | E901.1M | 01/22/25 09:54 / haw |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 01/22/25 09:54 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 01/22/25 09:54 / haw |
| Radium 228 | 1.4 | pCi/g-dry | | | | E901.1M | 01/22/25 09:54 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/22/25 09:54 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 01/22/25 09:54 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Lab ID:** C24120480-006
**Client Sample ID:** TP-40 [6-12]

**Report Date:** 01/31/25
**Collection Date:** 10/28/24 10:35
**DateReceived:** 12/18/24
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.4 | pCi/g-dry | U | | | E901.1M | 01/22/25 14:26 / haw |
| Radium 224 precision (±) | 2.4 | pCi/g-dry | | | | E901.1M | 01/22/25 14:26 / haw |
| Radium 224 MDC | 4.0 | pCi/g-dry | | | | E901.1M | 01/22/25 14:26 / haw |
| Radium 226 | 1.1 | pCi/g-dry | | | | E901.1M | 01/22/25 14:26 / haw |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 01/22/25 14:26 / haw |
| Radium 226 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 01/22/25 14:26 / haw |
| Radium 228 | 1.7 | pCi/g-dry | | | | E901.1M | 01/22/25 14:26 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/22/25 14:26 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 01/22/25 14:26 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Lab ID:** C24120480-007
**Client Sample ID:** TP-22 [1.5-2]

**Report Date:** 01/31/25
**Collection Date:** 10/28/24 11:20
**DateReceived:** 12/18/24
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.9 | pCi/g-dry | U | | | E901.1M | 01/22/25 16:28 / haw |
| Radium 224 precision (±) | 2.3 | pCi/g-dry | | | | E901.1M | 01/22/25 16:28 / haw |
| Radium 224 MDC | 3.9 | pCi/g-dry | | | | E901.1M | 01/22/25 16:28 / haw |
| Radium 226 | 1.1 | pCi/g-dry | | | | E901.1M | 01/22/25 16:28 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 01/22/25 16:28 / haw |
| Radium 226 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 01/22/25 16:28 / haw |
| Radium 228 | 2.0 | pCi/g-dry | | | | E901.1M | 01/22/25 16:28 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/22/25 16:28 / haw |
| Radium 228 MDC | 0.5 | pCi/g-dry | | | | E901.1M | 01/22/25 16:28 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Lab ID:** C24120480-008
**Client Sample ID:** TP-33 [6-12]

**Report Date:** 01/31/25
**Collection Date:** 11/25/24 11:00
**DateReceived:** 12/18/24
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.4 | pCi/g-dry | U | | | E901.1M | 01/22/25 18:30 / haw |
| Radium 224 precision (±) | 2.3 | pCi/g-dry | | | | E901.1M | 01/22/25 18:30 / haw |
| Radium 224 MDC | 3.8 | pCi/g-dry | | | | E901.1M | 01/22/25 18:30 / haw |
| Radium 226 | 1.1 | pCi/g-dry | | | | E901.1M | 01/22/25 18:30 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 01/22/25 18:30 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 01/22/25 18:30 / haw |
| Radium 228 | 1.7 | pCi/g-dry | | | | E901.1M | 01/22/25 18:30 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 01/22/25 18:30 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 01/22/25 18:30 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Lab ID:** C24120480-009
**Client Sample ID:** TP-30 [6-12]

**Report Date:** 01/31/25
**Collection Date:** 12/04/24 08:30
**DateReceived:** 12/18/24
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.8 | pCi/g-dry | U | | | E901.1M | 01/23/25 09:57 / haw |
| Radium 224 precision (±) | 2.2 | pCi/g-dry | | | | E901.1M | 01/23/25 09:57 / haw |
| Radium 224 MDC | 3.6 | pCi/g-dry | | | | E901.1M | 01/23/25 09:57 / haw |
| Radium 226 | 1.6 | pCi/g-dry | | | | E901.1M | 01/23/25 09:57 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 01/23/25 09:57 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 01/23/25 09:57 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 01/23/25 09:57 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/23/25 09:57 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 01/23/25 09:57 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Lab ID:** C24120480-010
**Client Sample ID:** TP-32 [1-1.5]

**Report Date:** 01/31/25
**Collection Date:** 12/09/24 09:50
**DateReceived:** 12/18/24
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1 | pCi/g-dry | U | | | E901.1M | 01/23/25 12:14 / haw |
| Radium 224 precision (±) | 2.3 | pCi/g-dry | | | | E901.1M | 01/23/25 12:14 / haw |
| Radium 224 MDC | 3.8 | pCi/g-dry | | | | E901.1M | 01/23/25 12:14 / haw |
| Radium 226 | 1.4 | pCi/g-dry | | | | E901.1M | 01/23/25 12:14 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 01/23/25 12:14 / haw |
| Radium 226 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 01/23/25 12:14 / haw |
| Radium 228 | 1.9 | pCi/g-dry | | | | E901.1M | 01/23/25 12:14 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/23/25 12:14 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 01/23/25 12:14 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Lab ID:** C24120480-011
**Client Sample ID:** TP-34 [2-3]

**Report Date:** 01/31/25
**Collection Date:** 12/11/24 09:15
**DateReceived:** 12/18/24
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.9 | pCi/g-dry | U | | | E901.1M | 01/23/25 14:16 / haw |
| Radium 224 precision (±) | 2.2 | pCi/g-dry | | | | E901.1M | 01/23/25 14:16 / haw |
| Radium 224 MDC | 3.6 | pCi/g-dry | | | | E901.1M | 01/23/25 14:16 / haw |
| Radium 226 | 1.3 | pCi/g-dry | | | | E901.1M | 01/23/25 14:16 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 01/23/25 14:16 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 01/23/25 14:16 / haw |
| Radium 228 | 1.8 | pCi/g-dry | | | | E901.1M | 01/23/25 14:16 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/23/25 14:16 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 01/23/25 14:16 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM NCA Characterization
**Lab ID:** C24120480-012
**Client Sample ID:** DS-NCA-01 [6-12]

**Report Date:** 01/31/25
**Collection Date:** 12/11/24 10:00
**DateReceived:** 12/18/24
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.0 | pCi/g-dry | U | | | E901.1M | 01/23/25 16:36 / haw |
| Radium 224 precision (±) | 2.7 | pCi/g-dry | | | | E901.1M | 01/23/25 16:36 / haw |
| Radium 224 MDC | 4.5 | pCi/g-dry | | | | E901.1M | 01/23/25 16:36 / haw |
| Radium 226 | 7.1 | pCi/g-dry | | | | E901.1M | 01/23/25 16:36 / haw |
| Radium 226 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/23/25 16:36 / haw |
| Radium 226 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 01/23/25 16:36 / haw |
| Radium 228 | 1.6 | pCi/g-dry | | | | E901.1M | 01/23/25 16:36 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 01/23/25 16:36 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 01/23/25 16:36 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Work Order:** C24120480 **Report Date:** 01/24/25

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E901.1M** | | | | | | | | | | Batch: R313846 |
| **Lab ID: MB-313846** | 9 | Method Blank | | | | Run: GAM-HPGE 2_250116A | | | 01/16/25 10:01 | |
| Radium 224 | | 1 | pCi/g-dry | | | | | | | |
| Radium 224 precision (±) | | 0.7 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 1 | pCi/g-dry | | | | | | | |
| Radium 226 | | 0.07 | pCi/g-dry | | | | | | | U |
| Radium 226 precision (±) | | 0.1 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.2 | pCi/g-dry | | | | | | | |
| Radium 228 | | 0.1 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.2 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.2 | pCi/g-dry | | | | | | | |
| **Lab ID: LCS-313846** | 6 | Laboratory Control Sample | | | | Run: GAM-HPGE 2_250116A | | | 01/16/25 11:06 | |
| Cobalt 60 | | 340 | pCi/g-dry | | 108 | 70 | 130 | | | |
| Cobalt 60 precision (±) | | 3.8 | pCi/g-dry | | | | | | | |
| Cobalt 60 MDC | | 1.1 | pCi/g-dry | | | | | | | |
| Lead 210 | | 1900 | pCi/g-dry | | 109 | 70 | 130 | | | |
| Lead 210 precision (±) | | 19 | pCi/g-dry | | | | | | | |
| Lead 210 MDC | | 18 | pCi/g-dry | | | | | | | |
| **Lab ID: C24120480-005ADUP** | 9 | Sample Duplicate | | | | Run: GAM-HPGE 2_250116A | | | 01/22/25 11:56 | |
| Radium 224 | | 0.59 | pCi/g-dry | | | | | 1300 | 30 | UR |
| Radium 224 precision (±) | | 2.4 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 4.1 | pCi/g-dry | | | | | | | |
| Radium 226 | | 3.7 | pCi/g-dry | | | | | 2.3 | 30 | |
| Radium 226 precision (±) | | 0.30 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.28 | pCi/g-dry | | | | | | | |
| Radium 228 | | 1.2 | pCi/g-dry | | | | | 14 | 30 | |
| Radium 228 precision (±) | | 0.41 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.55 | pCi/g-dry | | | | | | | |

- Duplicate RPD for Ra224 is outside of the acceptance range for this analysis. However, the RER is less than or equal to the limit of 3. The RER result is 0.41.
- The RER result for Ra226 is 0.22 and Ra228 is 0.34.

**Qualifiers:**

RL - Analyte Reporting Limit

R - Relative Percent Difference (RPD) exceeds advisory limit

ND - Not detected at the Reporting Limit (RL)

U - Not detected

# Work Order Receipt Checklist

## Rio Grande Resources Corporation C24120480

Login completed by: Cristen C. Smith
Date Received: 12/18/2024
Reviewed by: lquezada
Received by: SLR
Reviewed Date: 12/19/2024
Carrier name: Return UPS Ground

| | | | |
|---|---|---|---|
| Shipping container/cooler in good condition? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on all shipping container(s)/cooler(s)? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on all sample bottles? | Yes ☐ | No ☐ | Not Present ☑ |
| Chain of custody present? | Yes ☑ | No ☐ | |
| Chain of custody signed when relinquished and received? | Yes ☑ | No ☐ | |
| Chain of custody agrees with sample labels? | Yes ☑ | No ☐ | |
| Samples in proper container/bottle? | Yes ☑ | No ☐ | |
| Sample containers intact? | Yes ☑ | No ☐ | |
| Sufficient sample volume for indicated test? | Yes ☑ | No ☐ | |
| All samples received within holding time? (Exclude analyses that are considered field parameters such as pH, DO, Res Cl, Sulfite, Ferrous Iron, etc.) | Yes ☑ | No ☐ | |
| Temp Blank received in all shipping container(s)/cooler(s)? | Yes ☑ | No ☐ | Not Applicable ☐ |
| Container/Temp Blank temperature: | 4.0°C No Ice | | |
| Containers requiring zero headspace have no headspace or bubble that is <6mm (1/4"). | Yes ☐ | No ☐ | No VOA vials submitted ☑ |
| Water - pH acceptable upon receipt? | Yes ☐ | No ☐ | Not Applicable ☑ |

### Standard Reporting Procedures:

Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH, Dissolved Oxygen and Residual Chlorine, are qualified as being analyzed outside of recommended holding time.

Solid/soil samples are reported on a wet weight basis (as received) unless specifically indicated. If moisture corrected, data units are typically noted as –dry. For agricultural and mining soil parameters/characteristics, all samples are dried and ground prior to sample analysis.

The reference date for Radon analysis is the sample collection date. The reference date for all other Radiochemical analyses is the analysis date. Radiochemical precision results represent a 2-sigma Total Measurement Uncertainty.

For methods that require zero headspace or require preservation check at the time of analysis due to potential interference, the pH is verified at analysis. Nonconforming sample pH is documented as part of the analysis and included in the sample analysis comments.

Trip Blanks and/or Blind Duplicate samples are assigned the earliest collection time for the associated requested analysis in order to evaluate the holding time unless specifically indicated.

### Contact and Corrective Action Comments:

None

## *Laboratory Certifications and Accreditations*

Current certificates are available at www.energylab.com website:

| | Agency | Number |
|---|---|---|
| ***Billings, MT*** | Alaska | 17-023 |
| | California | 3087 |
| | Colorado | MT00005 |
| | Department of Defense (DoD)/ISO17025 | ADE-2588 |
| | Florida (Primary NELAP) | E87668 |
| | Idaho | MT00005 |
| | Louisiana | 05079 |
| | Montana | CERT0044 |
| | Nebraska | NE-OS-13-04 |
| | Nevada | NV-C24-00250 |
| | North Dakota | R-007 |
| | National Radon Proficiency | 109383-RMP |
| | Oregon | 4184 |
| | South Dakota | ARSD 74:04:07 |
| | Texas | TX-C24-00302 |
| | US EPA Region VIII | Reciprocal |
| | USDA Soil Permit | P330-20-00170 |
| | Washington | C1039 |
| ***Casper, WY*** | Alaska | 20-006 |
| | California | 3021 |
| | Colorado | WY00002 |
| | Florida (Primary NELAP) | E87641 |
| | Idaho | WY00002 |
| | Louisiana | 05083 |
| | Montana | CERT0002 |
| | Nebraska | NE-OS-08-04 |
| | Nevada | NV-C24-00245 |
| | North Dakota | R-125 |
| | Oregon | WY200001 |
| | South Dakota | WY00002 |
| | Texas | T104704181-23-21 |
| | US EPA Region VIII | WY00002 |
| | USNRC License | 49-26846-01 |
| | Washington | C1012 |
| ***Gillette, WY*** | US EPA Region VIII | WY00006 |
| ***Helena, MT*** | Colorado | MT00945 |
| | Montana | CERT0079 |
| | Nevada | NV-C24-00119 |
| | US EPA Region VIII | Reciprocal |
| | USDA Soil Permit | P330-20-00090 |

# Chain of Custody & Analytical Request Record

ENERGY LABORATORIES — Trust our People. Trust our Data.

www.energylab.com



## Account Information (Billing information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☒Email |
| Purchase Order | MT11820 |
| Quote | |
| Bottle Order | |

## Report Information (if different than Account Information)

| | |
|---|---|
| Company/Name | AVM Environmental Services, Inc. |
| Contact | Victor Patel |
| Phone | 505-287-4593 |
| Mailing Address | 1717 Del Norte Blvd |
| City, State, Zip | Grants, NM 87020 |
| Email | vpatelavm@outlook.com |
| Receive Report | ☐Hard Copy ☒Email |

Special Report/Formats: ☐ LEVEL IV ☐NELAC ☐ EDD/EDT (contact laboratory) ☐ Other_____

## Comments

## Project Information

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM NCA Characterization |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-4593 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐Yes ☒No |

**URANIUM MINING CLIENTS MUST Indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for soil | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | TP-01 6"-12" | 10/08/2024 | 9:30 am | 1 | S | ✓ | | | C24120480 |
| 2 | Inv-07 1.5'-2' | 10/08/2024 | 10:55 am | 1 | S | ✓ | | | |
| 3 | TP-13 6"-12" | 10/09/2024 | 8:40 am | 1 | S | ✓ | | | |
| 4 | TP-19 4.5'-5' | 10/16/2024 | 8:45 am | 1 | S | ✓ | | | |
| 5 | TP-24 6"-12" | 10/16/2024 | 10:20 am | 1 | S | ✓ | | | |
| 6 | TP-40 6"-12" | 10/28/2024 | 10:35 am | 1 | S | ✓ | | | |
| 7 | TP-22 1.5'-2' | 10/28/2024 | 11:20 am | 1 | S | ✓ | | | |
| 8 | TP-33 6"-12" | 11/25/2024 | 11:00 am | 1 | S | ✓ | | | |
| 9 | TP-30 6"-12" | 12/04/2024 | 8:30 am | 1 | S | ✓ | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were NOT used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Victor Patel | 12-10-24 / 10:00 | | | 1030 | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Shelby Richins | 12/19/24 | |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

ELI-COC-01/21 v.4

# Chain of Custody & Analytical Request Record

ENERGY LABORATORIES — Trust our People. Trust our Data.

www.energylab.com



**Account Information** (Billing information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☒Email |
| Purchase Order | MT11820 |
| Quote | |
| Bottle Order | |

**Report Information** (if different than Account Information)

| | |
|---|---|
| Company/Name | AVM Environmental Services, Inc. |
| Contact | Victor Patel |
| Phone | 505-287-4593 |
| Mailing Address | 1717 Del Norte Blvd |
| City, State, Zip | Grants, NM 87020 |
| Email | vpatelavm@outlook.com |
| Receive Report | ☐Hard Copy ☒Email |

Special Report/Formats: ☐ LEVEL IV ☐NELAC ☐ EDD/EDT (contact laboratory) ☐ Other_____

**Comments**

**Project Information**

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM NCA Characterization |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-4593 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**

A - Air
W - Water
S - Soils/Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

**Analysis Requested**

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for soil | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | TP-32 1'-1.5' | 12/09/2024 | 9:50 am | 1 | S | ✓ | | | C24120480 |
| 2 | TP-34 2'-3' | 12/11/2024 | 9:15 am | 1 | S | ✓ | | | |
| 3 | DS-NCA-01 6"-12" | 12/11/2024 | 10:00 am | 1 | S | ✓ | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were **NOT** used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Victor Patel | 12-16-24 / 1000 | | | 1030 | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Sheila R. Childs | 12/18/24 | |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

# South Controlled Area Soil Radiologic Characterization

**Mt. Taylor Mine Site**
**San Mateo, NM**

**Prepared by:**
**AVM Environmental Services, Inc.**
**1717 Del Norte Blvd.**
**Grants, NM 87020**

**Prepared for:**
**Rio Grande Resource Corporation**
**PO Box 1150**
**Grants, NM 87020**

**February 2026**

## Table of Contents

1.0 Introduction and Background ..... 1
2.0 Previous Radiologic Characterization ..... 1
3.0 Objective of the Radiologic Characterization ..... 2
4.0 Field Investigation ..... 2
4.1 Surface Gamma Radiation Scan and Static Survey ..... 2
4.2 Soil Sampling and Ex-Situ Gamma Radiation Soil Screening ..... 3
4.3 South Controlled Area Characterization Summary ..... 6
4.3.1 Borrow Area C Surface Soil Characterization Summary ..... 6
4.3.2 County Road 334 Area Characterization Summary ..... 7
4.3.3 West Data Gap Area Characterization Summary ..... 7
4.3.4 Service and Support (Mine Compound) Area Characterization Summary ..... 7
4.3.5 East Data Gap Area Characterization Summary ..... 8
5.0 Soil Sampling and Analysis ..... 8
6.0 Quality Assurance and Quality Control Measures ..... 9

## Tables

Table 1 Typical Gamma Scan Data Exported from Scan System Data Logger
Table 2 Static Surface Gamma Radiation Survey at Data Point/Soil Sample Locations
Table 3 South Controlled Area Radiological Characterization Soil Sample Field Ex-Situ Screening and Vendor Laboratory Results Summary
Table 4 South Controlled Area Surface and Subsurface Soil Ra-226 Level Summary
Table 5 Estimated Volumes of Areas Above the 6.8 pCi/g Ra-226 Investigation Level

## Figures

Figure 1 South Controlled Area Soil Radiologic Characterization Area
Figure 2 South Controlled Area Surface Soil Gamma Scan Survey Data
Figure 3 South Controlled Area Gamma Scan Survey Data and Data Point Locations
Figure 4 South Controlled Area Gamma Scan Survey Data and Data Point Locations with Ra-226 Concentration Depth Exceeding the IL
Figure 5 South Controlled Area Estimated Contamination Depths Exceeding the 6.8 pCi/g Ra-226 IL

## Appendices

Appendix A Surface and Subsurface Contamination Field Investigation Documentation (Soil Sample Log Forms, Field Soil Sample Ex-Situ Gamma Radiation Screening Forms)
Appendix B Radiologic Instrument Calibration, Operational Function Check, and Gamma Survey Detector Correlation Documentation
Appendix C Soil Sample COC and Laboratory Analytical Results Report

## 1.0 Introduction and Background

This report provides the results of the South Controlled Area (SCA) Soil Radiologic Characterization (SRC) that was conducted at the Mt. Taylor Mine (Site) in Cibola County, near San Mateo, New Mexico. This SRC was performed to check the status and estimate radiologic contamination in soil that exceeds the Site Radiation Cleanup Criteria (RCC) of 6.8 pCi/g Radium (Ra)-226, which is also used as the Site Investigation Level (IL). The SCA SRC area includes the Borrow Area C, County Road 334, the Service and Support Area, West Offsite Area and the Recognized Data Gap Area, as shown in Figure 1. The Mine Compound Area within the Services and Support Area was previously characterized and was not included in this SRC. The methods and procedures used during this SRC were consistent with the agency approved June 2020 Work Plan for Post-Mining Radiological Surveys of Permit Area and Impacted Lands (Work Plan), and applicable survey methods described in the Multi-Agency Radiation Survey and Site Investigation Manual (MARSSIM, EPA 2000a). The RCC specified in the March 2016 *Joint Guidance for the Cleanup and Reclamation of Existing Uranium Mining Operations in New Mexico* (EMNRD, 2016) (2016 Guidance) by the Energy, Minerals & Natural Resources Department (EMNRD) and the New Mexico Environment Department (NMED) was used for the SCA SRC investigation level (IL). The Ra-226 cleanup criteria of 5.0 pCi/g above the background level in land averaged over 100 square meters in surface soil (top six inches) specified in the Joint Guidance is taken from the UMTRCA (40 CFR 192) regulation, which is based on an unrestricted land use exposure scenario. Thus, a 6.8 pCi/g Ra-226 IL (5.0 pCi/g plus 1.8 pCi/g background level) has been established for the Site.

The Site was an underground uranium mine located in Cibola County, near San Mateo, New Mexico. The mine was developed by Gulf Mineral Resources Company (Gulf) in the 1970s, and ore production occurred from 1979 to 1982. Following the transfer of the Site to Chevron Resources Company in 1985, the ore production resumed and continued until 1990. Rio Grande Resources (RGR) acquired the Site in 1991. In 1999 the Site entered standby status under Mine Permit C1002RE with EMNRD. On December 29, 2017, the permit changed to an active status, and on December 3, 2019, RGR notified EMNRD of its intentions to begin the Site closeout/closure process.

The following sections describe the strategy, methods and procedures that were used and the results of the SCA SRC conducted at the Site.

## 2.0 Previous Radiologic Characterizations

Surface gamma radiation surveys were performed periodically within operationally controlled areas of the Site, including within the SCA, to monitor changes in radiological conditions during a period of remedial excavations in the Mine Water Treatment Ponds, the construction of the disposal cell, placement of contaminated mine materials, and the gradual removal of ore from the Ore Pad stockpile. The most recent gamma survey conducted in the SCA SRC area prior to this characterization was conducted in March 2020

and showed gamma radiation levels exceeding the 6.8 pCi/g Ra-226 IL in numerous areas within the SCA. The 2020 gamma survey results are summarized in the Work Plan.

## 3.0 Objective of the Soil Radiological Characterization

The Site is a former uranium mine, therefore the surface and subsurface soil is expected to be impacted by radionuclides associated with the uranium decay series, with Ra-226 being the primary Constituent of Concern (COC). The objective of this characterization is to evaluate Ra-226 contamination exceeding the 6.8 pCi/g Ra-226 IL in surface and subsurface soils to facilitate the estimation of the volume of radiologic impacted soil within the SCA SRC area.

## 4.0 Field Investigation

Field investigations for this SCA SRC were conducted consistent with the Work Plan and were performed during the period of April 2025 through September 30, 2025. The field investigation included both 0.5-inch thick lead collimated and bare (uncollimated) 2x2 sodium iodide (NaI) detector Differential Global Positioning System (DGPS) based gamma radiation scan surveys, and measurements. Additionally, static gamma radiation surveys, soil sampling, ex-situ soil screening, and offsite vendor laboratory confirmatory sample analysis were utilized during this SRC. The DGPS based gamma scan surveys were conducted to provide lateral Ra-226 concentration level estimates in surface soils. To assess subsurface radiological contamination, areas of potentially similar vertical extent of contamination were selected based on the DGPS gamma scan surveys data point (DP) locations for static gamma surveys and subsurface soil samples were selected to provide for an areal contamination depth profile estimation. Ex-situ gamma radiation soil screening was performed on the soil samples collected to provide real-time information to estimate surface and subsurface Ra-226 contamination levels. Offsite vender laboratory soil sample analysis was utilized to confirm the contamination levels assessed by the onsite real time ex-situ soil screening.

### 4.1 Surface Gamma Radiation Scan and Static Surveys

The instrument configuration used for direct gamma radiation level measurements during this characterization consisted of 0.5 inch thick lead collimated and bare 2x2 NaI scintillation detectors (Eberline SPA-3 or Ludlum 44-10) coupled to a scaler/rate meter, such as a Ludlum 2221, Ludlum 2241 or Ludlum 3000. This instrument configuration is widely used for this type of survey and is recommended by the MARSSIM. The scaler/rate meters were interfaced with a sub-meter accurate DGPS with surveying software and a data logger/controller for electronically recording the gamma radiation levels to the corresponding geo-location coordinates. The coordinate system used for this work was the State Plane Coordinate System (NAD83, New Mexico West, US Feet) system. The direct gamma radiation surveys using a NaI scintillation detector provides radiation levels in counts per minute (cpm).

During this characterization, systematic gamma radiation scan surveys using bare 2x2 NaI detectors were performed to estimate the level of Ra-226 in surface soil within the characterization areas. Although bare detectors do not avoid lateral gamma radiation shine, bare detectors have a large field of view and provide a large scan coverage area for an efficient and conservative lateral extent of contamination assessment. To better characterize the surface soil and to assist in the selection of data point locations, the surface gamma scan survey was performed at a higher density, 25-feet transect spacing, compared to the March 2020 scan density of about 60-ft transect spacing. Based on a conservative field of view (FOV) of about ten feet diameter for a bare 2x2 NaI detector for Ra-226 gamma radiation, scanning transects spacing of 25 feet would provide at least a 40% scan coverage, which is sufficient to identify and characterize any surface soil contamination. Twenty-five feet spaced geo-projected transects within the SCA were digitally created using a mapping software and loaded on the field data logger/controller. The gamma scan survey was performed by scanning along these transects with the detector at 12 inches above the ground surface at a scan rate of about three feet per second, with a data collection time interval of two seconds. A Bare detector gamma scan survey was performed in areas away from the Ore Pad, which could result in lateral gamma radiation shine. In areas located near the Ore Pad, a 0.5 inch thick lead collimated detector was used to mitigate lateral gamma radiation shine. The bare/collimated detector gamma scan boundary is shown in Figure 2.

The geo-located gamma scan data includes the gamma scan point ID number, date and time, location coordinates, and detector cpm. The scan data was exported from the data logger and the bare detector cpm were converted to equivalent Ra-226 estimate using the Site-specific correlation (Ra-226 pCi/g = 0.0005 x CPM)-7.32 $R^2$ = 0.97). The collimated detector cpm data was converted to equivalent Ra-226 pCi/g estimate using the Site-specific correlation (Ra-226 pCi/g = 0.0016 x CPM)-7.5 $R^2$ = 0.83). The 20,357 discrete gamma scan points collected during the gamma scan survey were exported from the scan system and the detector cpm data was converted into the equivalent estimated surface soil Ra-226 pCi/g concentration using the appropriate Site-specific correlation. The data was then plotted using a mapping software, shown in Figure 2, and arranged in graduated color ranges, then reviewed to identify areas that exceeded the Ra-226 IL. A typical gamma scan data export table from the scan system data logger and estimated Ra-226 concentration calculated using the correlation equation is shown in Table 1. Gamma scan survey data collected during this characterization are provided in an electronic file.

As previously discussed, areas of potentially similar vertical extent of contamination were selected based on the DGPS gamma scan surveys. A total of 49 data point locations (shown in Figure 3) were selected within these areas for the estimation of the vertical extent of Ra-226 contamination above the Site IL. A one-minute collimated detector static gamma radiation survey was performed at each data point location to estimate the surface soil Ra-226 levels prior to test pit excavation or collecting of any soil samples.

### 4.2 Soil Sampling and Ex-Situ Gamma Radiation Soil Screening

Two data point locations (DP-01 and DP-02) were selected on the southeast edge of Borrow Area C to verify surface soil Ra-226 levels where the gamma scan survey data showed Ra-226 concentrations slightly above

the IL, which was suspected to be due to lateral gamma shine from the nearby Ore Pad Area. Subsurface soil sampling was performed at these two locations. Additionally, data point locations DP-3 and DP-14 were selected at locations where the gamma scan survey data showed an isolated area with Ra-226 levels slightly above the IL. The locations were visually inspected and a one-minute collimated detector static gamma measurement was performed at each location to determine if subsurface soil sampling was necessary. The survey data was recorded on Static Gamma Radiation Survey Forms, which are included in Appendix A. The collimated detector measurements were converted to soil Ra-226 concentrations using the correlation equation for the collimated detector. The static gamma survey results are summarized in Table 2.

Soil sampling and on-Site ex-situ gamma radiation soil screening were performed during July 2025 to September 2025 to estimate the subsurface soil Ra-226 contamination exceeding the IL. Surface (0 to 6 inches) soil samples were not collected at every data point location during this characterization. The estimated surface soil Ra-226 level was determined from one-minute collimated detector static gamma radiation surveys. A one-minute collimated detector static gamma radiation survey provides a significantly higher certainty for a surface soil Ra-226 estimate than a two second integration gamma radiation scan survey provides. Additionally, the use of a collimated detector mitigates any lateral gamma radiation shine interference from any nearby elevated concentration areas.

Ex-situ gamma radiation soil screening was conducted to provide a real-time estimate of Ra-226 concentrations in soil samples to determine the depth at which subsurface soil sampling is no longer necessary. This method is more reliable than in-situ direct gamma radiation level measurements and allows for a more reliable real-time Ra-226 concentration assessment. The on-site ex-situ soil screening method consists of selectively measuring the 609 KeV region gamma radiation of Bi-214, a decay product of Ra-226. A single channel analyzer (Ludlum L2221 or Ludlum 3003) integrated with a Ludlum 44-20 3x3 NaI scintillation detector was used to measure the 609 keV energy peak region of Bi-214. A homogenized soil sample was placed around the plastic lined detector in a heavily lead shielded counting chamber. The use of a heavily shielded counting chamber lowers the system background counts, thus, improving the system's minimum detectable concentration (MDC). A reference soil with aRa-226 concentration of 6.6 pCi/g, comparable to the 6.8 pCi/g IL, was prepared and was used for soil screening during this SRC. The 6.6 pCi/g reference soil provides a conservative estimate of the Ra-226 concentration in samples below the IL.

Subsurface soil samples were collected from each of the 49 data point locations. The number and depth of the samples at each data point location varied depending upon location and soil screening results. A backhoe was used to excavate a test pit trench for subsurface soil sample collection at data point location where subsurface soil samples were necessary for depth characterization. The test pit trenches were excavated using a backhoe in approximately 6 to 12 inches depth intervals, depending on the soil type/consistency, visual observations, and/or gamma radiation level measurements. At each interval, a subsurface soil sample was collected from the base of the excavation for ex-situ gamma radiation soil screening. Stainless steel sampling trowels, bowls and #25 sieve as needed were used to collect the soil samples. The excavation continued until on-site ex-situ gamma radiation soil screening indicated that Ra-

226 concentrations were below the 6.8 pCi/g IL. At an isolated data point location DP-40, a surface static gamma measurement showed Ra-226 levels at approximately 25 pCi/g. Upon inspection, a single mine waste rock was observed partially buried at the data point location. The mine waste rock was removed and the subsequent surface static gamma remeasurement showed Ra-226 levels below the IL. Therefore, test pit trench excavation and subsurface soil sampling was not necessary at this data point location. The soil sample logs and the field soil screening forms are included in Appendix A. The ex-situ gamma radiation screening data is summarized in Table 3, and includes estimated Ra-226 concentrations of the samples relative to the 6.8 pCi/g IL. The surface and subsurface soil sampling Ra-226 levels above the IL depth results are summarized in Table 4.

At 39 of the 49 data point locations, a 6-12 inch below ground surface (bgs) subsurface soil sample was collected and ex-situ soil gamma screened. Furthermore, at 18 of those 39 data point locations, a subsurface soil sample at a depth of 1-2 feet bgs was collected and ex-situ soil screened since the 6–12-inch bgs subsurface sample soil screening result was above the IL. Subsurface soil samples from 15 data point locations were collected at a depth of 2-3 feet bgs since the shallower subsurface sample screening result was above the IL. Subsurface soil samples from eight data point locations were collected at a depth of 3-4 feet bgs since the shallower subsurface sample screening result was above the IL. At three data point location within the Service and Support Area, DP-30, DP-31, and DP-32, subsurface soil samples were collected at a depth greater than four feet since the shallower subsurface sample screening result was above the IL.

At data point location DP-41 which is located along the SCA fence and the Southern Diversion Channel at the southwest corner of the Services and Support Area, subsurface soil sampling was halted as the soil had low cohesion causing continual trench collapse past four feet bgs, even though the Ra-226 level at this depth was above the IL. Observations of the area made during excavation indicate that backfilling in this small area is likely to be as deep as ten feet bgs. At data point DP-29, a concrete slab was encountered at 3.7 feet bgs. Surface static gamma measurements and sample screening of the subsurface soil determined that the soil from the surface to 3.7 feet contained Ra-226 levels above the IL. An additional test pit trench was excavated approximately 10 feet east of DP-29 and the concrete slab was encountered at the same depth. Upon further discussion with Site staff, DP-29 was in an area where there was a Services and Support Area building that was decommissioned and the concrete slab foundation was left in place. At data point DP-32, located just east of the repository, soil screening determined that the subsurface soil sample from 10 feet bgs was above the IL. However, test pit trench excavation was halted due to backhoe excavation depth limitations. Discussions with Site staff indicated that the waste rock material and debris backfill in this area could be as deep as 25 to 30 feet bgs as this was the historic location of a pond. The exact dimensions of the historic pond are not known. At data point DP-31 in the Services and Support Area, test pit trench excavation continued past 5.5 feet bgs even though the 5.0 to 5.5 feet depth subsurface sample screening showed Ra-226 levels below the IL due to the presence of mine waste debris (timber, loose wires, metal parts/debris, etc.) to about ten feet bgs.

Although the primary objective of the ex-situ gamma radiation soil screening was to determine the Ra-226 concentrations above or below the 6.8 pCi/g IL, Ra-226 concentrations were estimated in all soil samples collected and screened. A correlation calibration of the ex-situ soil screening system was performed using a 6.6 pCi/g, a 25 pCi/g, and a 50 pCi/g reference soil. This correlation was updated with offsite vendor laboratory soil sample results for the samples that were screened onsite and sent to the laboratory for QA/QC confirmation. This updated correlation is included in Appendix B. The estimated Ra-226 concentrations calculated using the updated correlation regression equation [Ra-226 pCi/g = (CPM x 0.0144) – 2.55, $R^2$ = 0.995] of the subsurface soil samples are included in Tables 3 and 4.

A total of 45, which included five field quality assurance/quality check (QA/QC) duplicates, of the soil samples that were ex-situ gamma radiation soil screened on-site were sent to an offsite vendor laboratory for analysis (Energy Laboratories, in Casper, WY). These soil samples were analyzed for Ra-226 using EPA Method 901.1 (modified for soil matrix) for confirmation of the on-site ex-situ soil screening results. The laboratory results report is included in Appendix C and are summarized in Table 3. As shown in Table 3, the estimated Ra-226 levels determined by the on-site ex-situ soil screening are comparable with the vendor laboratory Ra-226 results, specifically in regards to determining that the Ra-226 levels are above or below the IL.

### 4.3 South Controlled Area Characterization Summary

As described previously, this SCA SRC included the areas shown in Figure 1. The entire SCA SRC area consists of approximately 111 acres. The Borrow Area C, in which only surface soil was characterized by scan gamma survey during this SRC, consists of approximately 12 acres. The SCA soil in approximately a 91 acres area is below the 6.8 pCi/g Ra-226 IL. In the remaining approximately 20 acre SCA area, the soil exceeds the IL and ranges from the ground surface to a depth of ten feet bgs. The depth of soil exceeding the IL at each data point is summarized in Table 4 and shown in Figure 4. Figure 5 shows areas within the SCA SRC with soil exceeding the IL at various contamination depths. The areas and conservative planning-level estimated volume of in-situ soil exceeding the IL within this characterization area are summarized in Table 5. The excavated volume of soil exceeding the IL may be higher than the estimated in-situ volume due to soil swell factor and the excavation equipment and technique used.

#### 4.3.1 Borrow Area C Surface Soil Characterization Summary

Borrow Area C consists of approximately 12 acres and is located north of the SCA, as shown in Figure 1. The initial SRC in Borrow Area C consisted of a gamma scan survey to confirm whether the borrow material is near the Ra-226 background level. As shown in Figure 2, the gamma scan survey showed Ra-226 levels below the IL in Borrow Area C, except for a small area in the southeast corner where the gamma scan survey showed Ra-226 levels just above the IL, likely due to lateral gamma radiation shine from the nearby North Control Area/Ore Pad Area. Static gamma measurements with a collimated detector and surface soil samples were collected at two data point locations (DP-01 and DP-02) in this area to confirm if the elevated

gamma readings are a result of lateral gamma radiation shine influence. The static gamma measurements data, the on-Site soil screening results and the offsite vendor laboratory soil sample result, shown in Table 2 and Table 3 respectively, confirm that the elevated gamma scan measurements were due to the influence of lateral gamma radiation shine, and that Ra-226 levels in the surface soil in Borrow Area C is well below the IL.

### 4.3.2 County Road 334 Area Characterization Summary

The County Road 334 Area, shown in Figure 1, was included in this SRC due to the results of the 2020 gamma scan showing elevated gamma radiation levels throughout the area. As part of this SRC, a gamma scan survey within the County Road 334 Area was conducted using a 0.5-inch lead collimated detector to mitigate any gamma radiation shine from the adjacent SCA and NCA areas that have significantly elevated gamma radiation levels. As shown in Figure 2, approximately 4 acres of the County Road 334 area is above the IL, which is a significant portion of the total area (≈7 acres) of the County Road 334 Area. As shown in Table 4 and Figure 5, the depth of soil exceeding the IL ranged from 0.5 feet to 2 feet in this area.

### 4.3.3 West Data Gap Area Characterization Summary

A gamma scan survey at 25 feet transect spacing was conducted in the West Gap Area, shown in Figure 1, during this SRC since the 2020 gamma survey showed several small and one larger sized isolated area with gamma levels potentially exceeding the IL. The West Gap Area consists of approximately 16 acres. Data points DP-14, DP-15 and DP16 were located on three small isolated areas along the northern boundary of the area that potentially exceeded the IL. Data point DP-18, which is located on an isolated area exceeding the IL along the eastern edge of the area. Each of these four small isolated areas were less than 800 square feet. One data point, DP-17, was located within a larger sized area (approximately 6000 square feet) discussed above. After investigation, gamma measurements, subsurface soil sampling and onsite soil screening, data point locations DP-14 and DP-15 were determined to be surface contamination from loose mine waste rock piles, while data point locations DP-16, DP-17 and DP-18 have soil that exceeds the IL at a depth of 0.5 feet bgs.

### 4.3.4 Service and Support (Mine Compound) Area Characterization Summary

The Service and Support Area, as shown in Figure 1, consists of approximately 36.55 acres. A portion of the Services and Support Area designated as the Mine Compound Area was previously characterized in 2023. The Service and Support Area include the Chiller Bench Area and the areas around the hoist house, the service building, the core storage building, the south stock tank, and the carpenter shop, among others The SRC gamma scan survey identified approximately 15 acres of impacted soils above the IL in the Service and Support SRC Area. Impacted soils exceeding the Ra-226 were identified ranging in depths bgs from surface to greater than 10 feet bgs. In the area near and around DP-29, DP-30 and DP-31 impacted soils exceeding the IL depth were observed at approximately 5 feet bgs. At data point location DP-32, soil exceeding the IL

is greater than 10 feet bgs, as discussed in section 4.2. In the area near DP-26 and DP-27 near the Guard House just west of the large-scale soil exceeding the IL was observed up to a one-foot bgs. In the northern portion of the Service and Support Area, most of the soil exceeding the IL is approximately 0.5 feet bgs, except for a low area with constructed berms near the historic Ore Storage area. The soil impacted above the IL in this pond area was assessed to be up to one-foot bgs. Soil exceeding the Ra-226 IL in the Chiller Bench Area ranged from 0.5 to one-foot bgs. On the Chiller Bench Area is a concrete pad with perimeter walls approximately 8 inches tall that served as a foundation/apparent spill catch basin for the mine water chilling process. Gamma radiation levels measured on this concrete pad were extremely elevated (up to 800,000 cpm). It is not known whether soils below this concrete pad exceeds the IL. An earthen berm with a height varying of one to two feet along the western edge of the Chiller Bench Area is mostly comprised of soil exceeding the IL, as shown in Figure 2.

### 4.3.5 East Data Gap Area Characterization Summary

The East Gap Area shown in Figure 1 consists of approximately 40 acres of which most of the area was not expected to contain soils that exceeded the IL as historic mining operations were not conducted throughout the entire area. For this SRC, a gamma scan survey was performed on roads, road shoulders, and berms, around infrastructures, on visibly disturbed areas and on areas that were discovered to have historic mining activities to assess surface soil contamination and potential impacted subsurface soils exceeding the Ra-226 IL. The gamma scan survey identified approximately 0.5 acres of impacted soils exceeding the IL. Most locations where soil exceeding the IL was observed, the depth of soil above the IL was at 6 inches bgs. At data point location DP-49, the depth bgs was observed at 6 inches, however this location was located on a 2.5 feet tall earthen berm. A portion of this 2.5 feet tall berm approximately 10 feet in length had soil exceeding the IL. The depth of soil exceeding the IL at data point location DP-47, which was located within a low area with constructed berms, was observed at greater than 4 feet bgs and includes the entire northern portion of the pond floor and berm. Test Pit trench excavation at this location was halted as the surrounding soil had low cohesion causing the trench to continually cave-in. Mine waste rock and debris were observed at all depths of excavation.

## 5.0 Soil Sampling and Analysis

Soil samples collected during the SCA SRC for on-site ex-situ gamma radiation soil screening were collected consistent with the Work Plan. Field QA/QC duplicate samples were ex-situ gamma radiation soil screened at a frequency of 10% of the total number of soil samples screened. A total of 98 surface and subsurface soil samples were collected for the SCA characterization. The test pit trenches were excavated using a backhoe at approximately 6 to 12 inches depth intervals depending on soil type and visual observations. At each interval, a subsurface soil sample was collected if deemed necessary from the base of the excavation for ex-situ gamma radiation soil screening. Field sampling equipment used for soil sampling included: stainless steel scoops, hand auger, bowls, sieve, and spoons that were decontaminated between sample locations. The soil sampling equipment decontamination was conducted by brushing off loose

visible soil and when necessary was rinsed with distilled water, then wiped with clean towels. The rinsed water was disposed of in Active Pond No. 2. Excavator buckets were cleaned by removing any loose, visible soil. Any soils excavated from the test pits were returned to the test pit excavations from which the soil came. Personal protection equipment (PPE), such as gloves, were brushed off and scanned for residual contamination and were disposed of.

Subsurface soil samples were analyzed by on-site ex-situ gamma radiation soil screening to provide real time assessment of Ra-226 level above or below the IL. A QA/QC confirmatory subsurface soil sample from each test pit from at the depth which screened below the IL was sent to an offsite Vendor laboratory. A total of thirty-nine QA/QC confirmatory soil samples, plus five QA/QC field duplicate samples were placed in labeled Ziploc bags and packaged along with a completed chain of custody in a cooler with a custody sealed lid and shipped to Energy Laboratories, Inc for Ra-226 analysis. The soil samples were analyzed for Ra-226 with a reporting limit of 0.5 pCi/g, using EPA Method 901.1 (modified for soil matrix). The completed chain of custody and the analytical results are included in Appendix C.

## 6. 0 Quality Assurance and Quality Control Measures

QA/QC measures were implemented during this characterization to ensure that decisions were made based on data of acceptable quality. All radiologic survey instruments have been calibrated at least annually. Additionally, operational functions checks were performed on all radiologic instruments daily prior to use. The calibration and function check documents are included in Appendix B. During this characterization, no instruments were found to be out of calibration or inoperable as indicated by the operational function checks. The instrument background measurements for bare 2x2 NaI detectors during daily operational function checks were less than 10,000 cpm as shown in Appendix B. The bare detector field of view (FOV) at 12 inches above the ground surface is conservatively assumed at an area of at least six feet diameter. The 2x2 NaI detector response factor is determined to be 0.0005 pCi/g/cpm from the linear regression for the Site-specific correlation included in Appendix B. Based on the above detector parameters, the Ra-226 minimum detectable concentrations (MDCs) for a scan survey at a scan speed of three feet per second, calculated using MARSSIM guidance, were less than 1.0 pCi/g, which is significantly below 50% of the 6.8 pCi/g IL. The instrument background measurements for the 0.5 inch thick lead collimated 2x2 NaI detectors during daily operational function checks were less than 3,200 cpm, as shown in Appendix B. The collimated detector field of view (FOV) at 12 inches above the ground surface is conservatively assumed at an area of approximately 1.5 feet diameter. The collimated 2x2 NaI detector response factor is determined to be 0.0016 pCi/g/CPM from the linear regression for the Site-specific correlation included in Appendix B. Based on the above collimated detector parameters, the Ra-226 minimum detectable concentrations (MDCs) for a one minute static survey, calculated using MARSSIM guidance, was less than 0.5 pCi/g, which is significantly below 50% of the 6.8 pCi/g IL. The ex-situ soil gamma radiation screening system was calibrated prior to mobilization in the field and daily operational function checks were performed prior to use. The calibration and function check documentation are included in Appendix B. Based on the highest system background (blank) measurements from daily operational function checks and efficiency (pCi/g/cpm), the

highest Ra-226 MDC for the screening system calculated was less than 1.0 pCi/g, significantly less than the 6.8 pCi/g IL. The MDCs during the supplemental characterization met the QA objective.

The QA/QC measures also included five field QA/QC duplicate soil samples out of the 45 soil samples collected sent to the off-site vendor laboratory for analysis to confirm contamination relative to the IL levels estimated by the field ex-situ gamma radiation soil screening. The QA/QC duplicate vendor laboratory results are included in Table 3. All QA/QC sample results confirm Ra-226 concentration levels relative to the IL level determined by the field ex-situ gamma radiation soil screening. The Ra-226 concentration in QA/QC duplicate samples estimated by on-sit ex-situ gamma radiation soil screening are comparable to the off-site vendor laboratory analytical results.

# Tables

## Table 1
## Mt. Taylor Mine Site - South Controlled Area Soil Radiological Characterization
## Typical Gamma Scan Data Exported from the Scan System Data Logger

| ID | Time | Northing[(1)] (feet) | Easting[(1)] (feet) | MSL Elevation (feet) | CPM 2x2 Bare NaI Detector | Ra-226 pCi/g[(2)] | Zone_ID |
|---|---|---|---|---|---|---|---|
| 1 | 7/2/2025 8:05 | 1578506.15 | 2783401.73 | 7450 | 15726 | 1.36 | South_Control_Area |
| 2 | 7/2/2025 8:05 | 1578504.80 | 2783399.21 | 7450 | 16378 | 1.69 | South_Control_Area |
| 3 | 7/2/2025 8:05 | 1578503.16 | 2783395.53 | 7450 | 14673 | 0.84 | South_Control_Area |
| 4 | 7/2/2025 8:05 | 1578503.35 | 2783391.12 | 7450 | 14537 | 0.77 | South_Control_Area |
| 5 | 7/2/2025 8:05 | 1578504.17 | 2783387.21 | 7451 | 15248 | 1.12 | South_Control_Area |
| 6 | 7/2/2025 8:05 | 1578504.39 | 2783382.33 | 7451 | 17955 | 2.48 | South_Control_Area |
| 7 | 7/2/2025 8:05 | 1578505.06 | 2783377.62 | 7451 | 17779 | 2.39 | South_Control_Area |
| 8 | 7/2/2025 8:05 | 1578505.64 | 2783373.23 | 7452 | 16936 | 1.97 | South_Control_Area |
| 9 | 7/2/2025 8:05 | 1578506.21 | 2783368.42 | 7452 | 15946 | 1.47 | South_Control_Area |
| 10 | 7/2/2025 8:05 | 1578506.35 | 2783363.51 | 7452 | 15156 | 1.08 | South_Control_Area |
| 11 | 7/2/2025 8:05 | 1578506.00 | 2783358.53 | 7452 | 14642 | 0.82 | South_Control_Area |
| 12 | 7/2/2025 8:05 | 1578504.93 | 2783353.55 | 7452 | 14520 | 0.76 | South_Control_Area |
| 13 | 7/2/2025 8:05 | 1578504.45 | 2783348.80 | 7453 | 17602 | 2.30 | South_Control_Area |
| 14 | 7/2/2025 8:05 | 1578504.29 | 2783344.50 | 7453 | 15492 | 1.25 | South_Control_Area |
| 15 | 7/2/2025 8:05 | 1578505.33 | 2783339.45 | 7452 | 16905 | 1.95 | South_Control_Area |
| 16 | 7/2/2025 8:05 | 1578504.98 | 2783334.31 | 7452 | 16056 | 1.53 | South_Control_Area |
| 17 | 7/2/2025 8:05 | 1578505.82 | 2783329.09 | 7452 | 16851 | 1.93 | South_Control_Area |
| 18 | 7/2/2025 8:05 | 1578506.40 | 2783324.12 | 7452 | 15213 | 1.11 | South_Control_Area |
| 19 | 7/2/2025 8:06 | 1578505.74 | 2783319.23 | 7452 | 16631 | 1.82 | South_Control_Area |
| 20 | 7/2/2025 8:06 | 1578505.57 | 2783314.23 | 7452 | 15497 | 1.25 | South_Control_Area |
| 21 | 7/2/2025 8:06 | 1578507.11 | 2783309.82 | 7452 | 16137 | 1.57 | South_Control_Area |
| 22 | 7/2/2025 8:06 | 1578507.50 | 2783304.87 | 7452 | 16631 | 1.82 | South_Control_Area |
| 23 | 7/2/2025 8:06 | 1578506.57 | 2783297.05 | 7452 | 16039 | 1.52 | South_Control_Area |
| 24 | 7/2/2025 8:06 | 1578505.38 | 2783291.84 | 7452 | 17367 | 2.18 | South_Control_Area |
| 25 | 7/2/2025 8:06 | 1578504.51 | 2783286.50 | 7452 | 17413 | 2.21 | South_Control_Area |
| 26 | 7/2/2025 8:06 | 1578504.77 | 2783282.09 | 7452 | 16035 | 1.52 | South_Control_Area |
| 27 | 7/2/2025 8:06 | 1578505.51 | 2783277.24 | 7451 | 16144 | 1.57 | South_Control_Area |
| 28 | 7/2/2025 8:06 | 1578505.78 | 2783272.39 | 7452 | 16361 | 1.68 | South_Control_Area |
| 29 | 7/2/2025 8:06 | 1578505.84 | 2783267.17 | 7452 | 15272 | 1.14 | South_Control_Area |
| 30 | 7/2/2025 8:06 | 1578504.40 | 2783261.75 | 7452 | 18212 | 2.61 | South_Control_Area |
| 31 | 7/2/2025 8:06 | 1578503.44 | 2783256.26 | 7452 | 16453 | 1.73 | South_Control_Area |
| 32 | 7/2/2025 8:06 | 1578504.30 | 2783250.96 | 7452 | 17003 | 2.00 | South_Control_Area |
| 33 | 7/2/2025 8:06 | 1578503.76 | 2783245.83 | 7452 | 17637 | 2.32 | South_Control_Area |
| 34 | 7/2/2025 8:06 | 1578504.70 | 2783240.40 | 7452 | 17512 | 2.26 | South_Control_Area |
| 35 | 7/2/2025 8:06 | 1578505.79 | 2783235.31 | 7453 | 15704 | 1.35 | South_Control_Area |
| 36 | 7/2/2025 8:06 | 1578507.14 | 2783230.22 | 7453 | 14504 | 0.75 | South_Control_Area |
| 37 | 7/2/2025 8:06 | 1578508.46 | 2783225.59 | 7453 | 16229 | 1.61 | South_Control_Area |
| 38 | 7/2/2025 8:06 | 1578508.34 | 2783221.50 | 7453 | 16126 | 1.56 | South_Control_Area |
| 39 | 7/2/2025 8:06 | 1578509.11 | 2783216.88 | 7453 | 17350 | 2.18 | South_Control_Area |
| 40 | 7/2/2025 8:06 | 1578507.94 | 2783212.61 | 7453 | 16733 | 1.87 | South_Control_Area |

(1) projection: StatePlane NAD 1983 NM West - Feet

(2) Ra-226 pCi/g determined from surface soil gamma radiation scan using 2x2 NaI detector and Site-specific gamma radiation level (cpm) correlation

# Table 2

## Mt. Taylor Mine Site - South Controlled Area Soil Radiological Characterization

## Static Gamma Radiation Survey at Data Point/Soil Sample Locations

| Data Point ID | Survey Date | Data Point Coordinate NAD83 StatePlane NM West, Feet | | Static Gamma Radiation Survey Collimated (0.5" PB) 2x2 Detector | |
|---|---|---|---|---|---|
| | | Northing | Easting | Static Gamma CPM | Surface Soil Static Gamma Estimated Ra-226 pCi/g |
| DP-01 | 9/11/2025 | 1581456.24 | 2782657.15 | 5420 | 2.2 |
| DP-02 | 9/11/2025 | 1581406.97 | 2782633.38 | 5690 | 2.6 |
| DP-03 | 9/11/2025 | 1580333.60 | 2783446.13 | 7330 | 5.2 |
| DP-04 | 9/11/2025 | 1580218.66 | 2783225.41 | 22600 | 29.7 |
| DP-05 | 9/11/2025 | 1580111.25 | 2783053.07 | 8600 | 7.3 |
| DP-06 | 9/11/2025 | 1580059.50 | 2782741.72 | 51000 | 75.1 |
| DP-07 | 9/11/2025 | 1579926.69 | 2782701.55 | 13000 | 14.3 |
| DP-08 | 9/11/2025 | 1579906.01 | 2782550.68 | 30500 | 42.3 |
| DP-09 | 9/10/2025 | 1579676.86 | 2782284.70 | 18100 | 22.5 |
| DP-10 | 9/10/2025 | 1579580.37 | 2782155.84 | 34000 | 47.9 |
| DP-11 | 9/10/2025 | 1579474.67 | 2781912.50 | 10600 | 10.5 |
| DP-12 | 9/11/2025 | 1579676.54 | 2781504.62 | 17100 | 20.9 |
| DP-13 | 9/11/2025 | 1579650.19 | 2781481.77 | 63900 | 95.7 |
| DP-14 | 9/11/2025 | 1579366.41 | 2781517.09 | 6430 | 3.8 |
| DP-15 | 9/11/2025 | 1579276.75 | 2781166.97 | 16000 | 19.1 |
| DP-16 | 9/11/2025 | 1579206.60 | 2780988.11 | 10900 | 10.9 |
| DP-17 | 9/11/2025 | 1579012.72 | 2781443.25 | 16800 | 20.4 |
| DP-18 | 9/11/2025 | 1578708.28 | 2781523.75 | 11400 | 11.7 |
| DP-19 | 8/20/2025 | 1580005.87 | 2783183.19 | 9130 | 8.1 |
| DP-20 | 9/8/2025 | 1579881.85 | 2782874.49 | 7050 | 4.8 |
| DP-21 | 8/20/2025 | 1579888.86 | 2783014.60 | 41800 | 60.4 |
| DP-22 | 8/20/2025 | 1579698.02 | 2783114.76 | 14600 | 16.9 |
| DP-23 | 8/20/2025 | 1579756.79 | 2782601.56 | 7830 | 6.0 |
| DP-24 | 8/20/2025 | 1579606.45 | 2782731.05 | 16900 | 20.5 |
| DP-25 | 8/20/2025 | 1579502.08 | 2782431.79 | 6740 | 4.3 |
| DP-26 | 9/8/2025 | 1579361.45 | 2782463.26 | 81700 | 124.2 |
| DP-27 | 8/20/2025 | 1579284.95 | 2782637.69 | 11300 | 11.6 |
| DP-28 | 8/20/2025 | 1579267.76 | 2782512.22 | 10400 | 10.1 |
| DP-29 | 8/20/2025 | 1578986.20 | 2782231.30 | 45000 | 65.5 |
| DP-30 | 8/20/2025 | 1578858.91 | 2782145.81 | 26800 | 36.4 |
| DP-31 | 8/20/2025 | 1578784.38 | 2782043.42 | 9600 | 8.9 |
| DP-32 | 8/20/2025 | 1578656.58 | 2782107.47 | 17500 | 21.5 |
| DP-33 | 9/9/2025 | 1579978.01 | 2782997.27 | 17400 | 21.3 |
| DP-34 | 9/9/2025 | 1579300.74 | 2783201.08 | 47100 | 68.9 |
| DP-35 | 9/9/2025 | 1579248.03 | 2783318.89 | 12900 | 14.1 |
| DP-36 | 9/9/2025 | 1578757.08 | 2782755.18 | 8170 | 6.6 |
| DP-37 | 9/9/2025 | 1578558.89 | 2782985.49 | 13000 | 14.3 |
| DP-38 | 9/9/2025 | 1578350.60 | 2783005.53 | 11700 | 12.2 |
| DP-39 | 9/9/2025 | 1578258.17 | 2783022.86 | 28700 | 39.4 |

## Table 2 (cont.)
## Mt. Taylor Mine Site - South Controlled Area Soil Radiological Characterization
## Static Gamma Radiation Survey at Data Point/Soil Sample Locations

| Data Point ID | Survey Date | Data Point Coordinate NAD83 StatePlane NM West, Feet | | Static Gamma Radiation Survey Collimated (0.5" PB) 2x2 Detector | |
|---|---|---|---|---|---|
| | | Northing | Easting | Static Gamma CPM | Surface Soil Static Gamma Estimated Ra-226 pCi/g |
| DP-40 | 9/9/2025 | 1578235.02 | 2783135.60 | 19500 | 24.7 |
| DP-41 | 9/18/2025 | 1578074.78 | 2781517.19 | 13700 | 15.4 |
| DP-42 | 9/18/2025 | 1578993.45 | 2783870.64 | 24600 | 32.9 |
| DP-43 | 9/18/2025 | 1578870.92 | 2783750.89 | 11100 | 11.3 |
| DP-44 | 9/18/2025 | 1578762.92 | 2783241.97 | 82200 | 125.0 |
| DP-45 | 9/18/2025 | 1578729.09 | 2783238.60 | 28200 | 38.6 |
| DP-46 | 9/18/2025 | 1578655.36 | 2783604.89 | 10100 | 9.7 |
| DP-47 | 9/18/2025 | 1578468.72 | 2783567.11 | 56600 | 84.1 |
| DP-48 | 9/18/2025 | 1578401.72 | 2783546.94 | 13100 | 14.5 |
| DP-49 | 9/18/2025 | 1578456.78 | 2783274.95 | 16300 | 19.6 |

# Table 3

## South Controlled Area Radiological Characterization Soil Sample Field Ex-Situ Screening and Vendor Laboratory Results Summary

| Sampling Data | | | | | Field Soil Screening Data | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth (ft) | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | SSL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| DP-01 | 0.0'-0.5' | 9/11/2025 | 810 | Topsoil, sandy silt w/roots | 9/15/2025 | 3000 | 1606 | 321 | 2.1 | < | yes | 1.9 | 0.2 | 0.2 |
| DP-02 | 0.0'-0.5' | 9/11/2025 | 800 | Topsoil, sandy silt w/roots | 9/15/2025 | 3000 | 1621 | 324 | 2.1 | < | yes | 1.8 | 0.2 | 0.2 |
| DP-04 | 0.5'-1.0 | 9/15/2025 | 1000 | Compacted silty sand, slight waste rock | 9/15/2025 | 3000 | 6166 | 1233 | 15.2 | > | - | - | - | - |
| DP-04 | 1.0'-1.5' | 9/15/2025 | 1015 | loam clay mixed 3/4" rock | 9/15/2025 | 3000 | 1521 | 304 | 1.8 | < | yes | 1.6 | 0.2 | 0.2 |
| DP-04 | 2.0'-2.5' | 9/15/2025 | 1030 | compacted silt mixed w/ clay | 9/15/2025 | 3000 | 1636 | 327 | 2.2 | < | - | - | - | - |
| DP-05 | 0.5'-1.0 | 9/16/2025 | 810 | Light brown compacted sand w/ roots | 9/16/2025 | 3000 | 1254 | 251 | 1.1 | < | yes | 1.0 | 0.2 | 0.2 |
| DP-06 | 0.5'-1.0 | 9/15/2025 | 900 | Light brown compacted sand w/ roots | 9/15/2025 | 3000 | 16175 | 3235 | 44.0 | > | - | - | - | - |
| DP-06 | 1.5'-2.0' | 9/15/2025 | 920 | Light brown compacted sand w/ roots | 9/15/2025 | 3000 | 1779 | 356 | 2.6 | < | yes | 2.2 | 0.2 | 0.2 |
| DP-06 | 2.5'-3.0' | 9/15/2025 | 935 | Light brown compacted sand | 9/15/2025 | 3000 | 1219 | 244 | 1.0 | < | - | - | - | - |
| DP-07 | 0.5'-1.0 | 9/16/2025 | 835 | compacted silt mixed w/ clay | 9/16/2025 | 3000 | 4007 | 801 | 9.0 | > | - | - | - | - |
| DP-07 | 1.0'-1.5' | 9/16/2025 | 845 | | 9/16/2025 | 3000 | 2439 | 488 | 4.5 | < | - | - | - | - |
| DP-07 | 2.0'-2.5' | 9/16/2025 | 900 | Compacted brown silt/clay/gravel | 9/16/2025 | 3000 | 7448 | 1490 | 18.9 | > | - | - | - | - |
| DP-07 | 3.0'-3.5' | 9/16/2025 | 915 | Brown silt/clay | 9/16/2025 | 3000 | 1269 | 254 | 1.1 | < | yes | 1.0 | 0.2 | 0.2 |
| DP-08 | 0.5'-1.0 | 9/15/2025 | 800 | Light brown compacted sand w/ roots | 9/15/2025 | 3000 | 1767 | 353 | 2.5 | < | yes | 2.6 | 0.2 | 0.2 |
| DP-08 | 1.0'-1.5' | 9/15/2025 | 815 | Light brown compacted sand w/ roots | 9/15/2025 | 3000 | 1360 | 272 | 1.4 | < | - | - | - | - |
| DP-08 | 2.0'-2.5' | 9/15/2025 | 830 | Light brown compacted sand w/ roots | 9/15/2025 | 3000 | 1269 | 254 | 1.1 | < | - | - | - | - |
| DP-09 | 0.5'-1.0 | 9/10/2025 | 1300 | Dark compacted silt/clay | 9/10/2025 | 3000 | 1269 | 254 | 1.1 | < | - | - | - | - |
| DP-09 | 1.0'-1.5' | 9/10/2025 | 1320 | Brown loam/sand mix | 9/10/2025 | 3000 | 1870 | 374 | 2.8 | < | yes | 0.9 | 0.2 | 0.2 |
| DP-10 | 0.5'-1.0 | 9/10/2025 | 1120 | Dark compacted silt/clay | 9/10/2025 | 3000 | 3694 | 739 | 8.1 | > | - | - | - | - |
| DP-10 | 1.0'-1.5' | 9/10/2025 | 1135 | Brown loam/sand mix | 9/10/2025 | 3000 | 1342 | 268 | 1.3 | < | yes | 1.0 | 0.2 | 0.2 |
| DP-10 | 1.5'-2.0' | 9/10/2025 | 1145 | Brown loam/sand mix | 9/10/2025 | 3000 | 1509 | 302 | 1.8 | < | - | - | - | - |
| DP-10 | 2.0'-2.5' | 9/10/2025 | 1155 | Brown loam/sand mix | 9/10/2025 | 3000 | 1446 | 289 | 1.6 | < | - | - | - | - |
| DP-11 | 0.5'-1.0 | 9/10/2025 | 1044 | Dark compacted silt/clay | 9/10/2025 | 3000 | 1716 | 343 | 2.4 | < | yes | 1.9 | 0.2 | 0.2 |
| DP-11 | 1.0'-1.5' | 9/10/2025 | 1100 | Brown loam/sand mix | 9/10/2025 | 3000 | 1256 | 251 | 1.1 | < | - | - | - | - |
| DP-12 | 0.5'-1.0 | 9/16/2025 | 940 | Light brown compacted sand | 9/16/2025 | 3000 | 1545 | 309 | 1.9 | < | yes | 1.5 | 0.2 | 0.2 |
| DP-13 | 0.5'-1.0 | 9/16/2025 | 1000 | Compacted brown silt/clay/gravel | 9/16/2025 | 3000 | 1918 | 384 | 3.0 | < | yes | 2.8 | 0.2 | 0.2 |
| DP-15 | 0.5'-1.0 | 9/15/2025 | 1315 | Brown silt/clay | 9/16/2025 | 3000 | 1828 | 366 | 2.7 | < | yes | 2.7 | 0.2 | 0.2 |

# Table 3 (cont.)

## South Controlled Area Radiological Characterization Soil Sample Field Ex-Situ Screening and Vendor Laboratory Results Summary

| Sampling Data | | | | | Field Soil Screening Data | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth (ft) | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | SSL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| DP-15 | 1.5'-2.0' | 9/15/2025 | 1330 | light brown sandy loam | 9/16/2025 | 3000 | 1247 | 249 | 1.0 | < | - | - | - | - |
| DP-16 | 0.5'-1.0 | 9/15/2025 | 1230 | light brown/grey sandy/silt | 9/16/2025 | 3000 | 1353 | 271 | 1.3 | < | yes | 1.0 | 0.2 | 0.2 |
| DP-17 | 0.0'-0.5' | 9/11/2025 | 840 | Topsoil, sandy silt w/roots | 9/15/2025 | 3000 | 9430 | 1886 | 24.6 | > | yes | 26.6 | 0.6 | 0.3 |
| DP-17 | 0.5'-1.0 | 9/11/2025 | 850 | Light brown compacted sand w/ roots | 9/15/2025 | 3000 | 1249 | 250 | 1.0 | < | yes | 1.0 | 0.2 | 0.2 |
| DP-18 | 0.5'-1.0 | 9/11/2025 | 900 | Light brown compacted sand w/ roots | 9/15/2025 | 3000 | 1236 | 247 | 1.0 | < | yes | 0.8 | 0.2 | 0.2 |
| DP-19 | 0.5'-1.0' | 9/3/2025 | 1020 | Dark brown silty/sand mix | 9/3/2025 | 3000 | 1248 | 250 | 1.0 | < | yes | 1.2 | 0.2 | 0.2 |
| DP-19 | 1.0'-1.5' | 9/3/2025 | 1030 | Dark brown silty/sand mix | 9/3/2025 | 3000 | 1057 | 211 | 1.0 | < | - | - | - | - |
| DP-20 | 0.5'-1.0' | 9/8/2025 | 900 | Dark brown silty/sand mix w/ clay | 9/8/2025 | 3000 | 1230 | 246 | 1.0 | < | yes | 1.0 | 0.2 | 0.2 |
| DP-21 | 1.0'-1.5' | 9/3/2025 | 930 | Dark clay/silt w/ grey mix, debris | 9/3/2025 | 2069 | 1398 | 405 | 3.3 | < | - | - | - | - |
| DP-21 | 2.0'-2.5' | 9/3/2025 | 940 | Dark brown silty/sand mix | 9/3/2025 | 3000 | 1268 | 254 | 1.1 | < | yes | 1.1 | 0.2 | 0.2 |
| DP-22 | 0.5'-1.0' | 9/3/2025 | 1045 | gravel base course-3/4" - 2" | 9/3/2025 | 3000 | 2113 | 423 | 3.5 | < | - | - | - | - |
| DP-22 | 1.0'-1.5' | 9/3/2025 | 1100 | Dark brown silty/sand mix | 9/3/2025 | 3000 | 1220 | 244 | 1.0 | < | yes | 1.2 | 0.2 | 0.2 |
| DP-23 | 0.5'-1.0 | 9/3/2025 | 1215 | gravel base course-3/4" - 2"/asphalt | 9/3/2025 | 3000 | 2633 | 527 | 5.0 | ≈ | - | - | - | - |
| DP-23 | 1.0'-1.5' | 9/3/2025 | 1230 | Brown to dark brown clay/silt | 9/3/2025 | 3000 | 1730 | 346 | 2.4 | < | yes | 1.9 | 0.2 | 0.2 |
| DP-24 | 0.5'-1.0' | 9/3/2025 | 1300 | light brown compacted sand/clay | 9/3/2025 | 3000 | 1353 | 271 | 1.3 | < | yes | 1.1 | 0.2 | 0.2 |
| DP-24 | 1.0'-1.5' | 9/3/2025 | 1315 | light brown compacted sand/clay | 9/3/2025 | 3000 | 1181 | 236 | 1.0 | < | - | - | - | - |
| DP-25 | 0.5'-1.0 | 9/8/2025 | 940 | Light brown sandy w/ 3/4" gravel mix | 9/8/2025 | 3000 | 2144 | 429 | 3.6 | < | yes | 4.8 | 0.3 | 0.2 |
| DP-26 | 1.0'-1.5' | 9/8/2025 | 1020 | Gravel 3/4"-2" mix w/ light brown sand/silt | 9/8/2025 | 3000 | 2875 | 575 | 5.7 | > | - | - | - | - |
| DP-26 | 2.0'-2.5' | 9/8/2025 | 1040 | light brown silty/sand mix | 9/8/2025 | 3000 | 1177 | 235 | 1.0 | < | yes | 0.9 | 0.2 | 0.2 |
| DP-26 | 3.0'-3.5' | 9/8/2025 | 1050 | light brown silty/sand mix | 9/8/2025 | 3000 | 1236 | 247 | 1.0 | < | - | - | - | - |
| DP-27 | 0.5'-1.0' | 9/3/2025 | 830 | gravel base course-3/4" - 2" | 9/3/2025 | 3000 | 5073 | 1015 | 12.1 | > | - | - | - | - |
| DP-27 | 1.0'-2.0' | 9/3/2025 | 840 | Brown to dark brown clay/silt, shale | 9/3/2025 | 3000 | 1136 | 227 | 1.0 | < | yes | 1.1 | 0.2 | 0.2 |
| DP-27 | 2.0'-3.0' | 9/3/2025 | 850 | light brown compacted sand | 9/3/2025 | 3000 | 1086 | 217 | 1.0 | < | - | - | - | - |
| DP-28 | 0.5'-1.0' | 9/3/2025 | 750 | Dark brown silty/sand mix | 9/3/2025 | 3000 | 1047 | 209 | 1.0 | < | yes | 1.0 | 0.2 | 0.2 |
| DP-28 | 1.0'-1.5' | 9/3/2025 | 800 | Brown to dark brown clay/silt, shale | 9/3/2025 | 3000 | 1028 | 206 | 1.0 | < | - | - | - | - |

## Table 3 (cont.)

### South Controlled Area Radiological Characterization Soil Sample Field Ex-Situ Screening and Vendor Laboratory Results Summary

| Sampling Data | | | | | Field Soil Screening Data | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth (ft) | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | SSL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| DP-29 | 0.5'-1.0' | 8/21/2025 | 1145 | Dark clay/silt w/ grey mix, debris | 8/21/2025 | 3000 | 14410 | 2882 | 38.9 | > | - | - | - | - |
| DP-29 | 1.0'-3.7' | 8/21/2025 | 1223 | Dark clay/silt w/ grey mix, debris | 8/21/2025 | 3000 | 22920 | 4584 | 63.5 | > | - | - | - | - |
| DP-30 | 0.5'-1.0' | 8/21/2025 | 1006 | Grey rocky sandy mix | 8/21/2025 | 3000 | 18540 | 3708 | 50.8 | > | - | - | - | - |
| DP-30 | 1.0'-4.0' | 8/21/2025 | 1015 | Grey rocky sandy mix | 8/21/2025 | 3000 | 40130 | 8026 | 113.0 | > | - | - | - | - |
| DP-30 | 4.0'-4.5' | 8/21/2025 | 1025 | 3/4 gravel and sand | 8/21/2025 | 3000 | 3764 | 753 | 8.3 | > | - | - | - | - |
| DP-30 | 4.5'-6.0' | 8/21/2025 | 1035 | Brown/light brown sompacted silt/clay | 8/21/2025 | 3000 | 1667 | 333 | 2.2 | < | yes | 2.4 | 0.3 | 0.3 |
| DP-30 | 6.0'-6.5' | 8/21/2025 | 1045 | Dark compacted clay/silty | 8/21/2025 | 3000 | 1300 | 260 | 1.2 | < | - | - | - | - |
| DP-31 | 0.5'-1.0' | 8/21/2025 | 845 | Brown/light brown sompacted silt/clay, gray mix | 8/21/2025 | 3000 | 9029 | 1806 | 23.5 | > | - | - | - | - |
| DP-31 | 1.0'-3.0' | 8/21/2025 | 900 | Grey silty sandy, debris | 8/21/2025 | 3000 | 16160 | 3232 | 44.0 | > | - | - | - | - |
| DP-31 | 3.0'-5.0' | 8/21/2025 | 915 | Gray rocky sandy mix w/dark clay | 8/21/2025 | 3000 | 7927 | 1585 | 20.3 | > | - | - | - | - |
| DP-31 | 5.0'-5.5' | 8/21/2025 | 920 | Dark clay/silt w/ grey mix | 8/21/2025 | 3000 | 1215 | 243 | 1.0 | < | - | - | - | - |
| DP-31 | 5.5'-10.0' | 8/21/2025 | 950 | Dark clay/silt w/ grey mix, debris | 8/21/2025 | 3000 | 2810 | 562 | 5.5 | > | - | - | - | - |
| DP-31 | 10'-10.25' | 8/21/2025 | 1245 | Dark compacted clay wet | 8/21/2025 | 3000 | 1464 | 293 | 1.7 | < | yes | 1.5 | 0.2 | 0.2 |
| DP-32 | 0.5'-1.0' | 8/21/2025 | 740 | Dark clay/silt w/ grey mix | 8/21/2025 | 3000 | 16485 | 3297 | 44.9 | > | - | - | - | - |
| DP-32 | 1.5'-2.0' | 8/21/2025 | 745 | Dark clay/silt w/ grey mix, debris | 8/21/2025 | 3000 | 16975 | 3395 | 46.3 | > | - | - | - | - |
| DP-32 | 3.0'-3.5' | 8/21/2025 | 750 | Dark clay/silt w/ grey mix, debris | 8/21/2025 | 3000 | 14725 | 2945 | 39.9 | > | - | - | - | - |
| DP-32 | 4.5'-5.0' | 8/21/2025 | 758 | Dark clay/silt w/ grey mix, debris | 8/21/2025 | 3000 | 13350 | 2670 | 35.9 | > | - | - | - | - |
| DP-32 | 5.0'-10.0' | 8/21/2025 | 830 | Grey silty sandy, debris | 8/21/2025 | 3000 | 12514 | 2503 | 33.5 | > | - | - | - | - |
| DP-33 | 0.5'-1.0 | 9/9/2025 | 1250 | Brown loam/sand mix | 9/9/2025 | 3000 | 1472 | 294 | 1.7 | < | yes | 1.4 | 0.2 | 0.2 |
| DP-33 | 1.0'-1.5' | 9/9/2025 | 1305 | Brown loose sand | 9/9/2025 | 3000 | 1150 | 230 | 1.0 | < | - | - | - | - |
| DP-34 | 0.5'-1.0 | 9/9/2025 | 1050 | Dark compacted silt/clay | 9/9/2025 | 3000 | 1653 | 331 | 2.2 | < | yes | 2.5 | 0.2 | 0.2 |
| DP-34 | 1.0'-1.5' | 9/9/2025 | 1105 | Light brown compacted sand w/ roots | 9/9/2025 | 3000 | 1049 | 210 | 1.0 | < | - | - | - | - |
| DP-34 | 2.0'-2.5' | 9/9/2025 | 1120 | Light brown compacted sand w/ roots | 9/9/2025 | 3000 | 1158 | 232 | 1.0 | < | - | - | - | - |
| DP-35 | 0.5'-1.0 | 9/9/2025 | 1140 | Brown silt/clay w/ roots | 9/9/2025 | 2324 | 1027 | 265 | 1.3 | < | yes | 1.3 | 0.2 | 0.2 |
| DP-36 | 0.5'-1.0 | 9/9/2025 | 1320 | 3/4" gravel mix w/ light brown sand | 9/10/2025 | 3000 | 2229 | 446 | 3.9 | < | - | - | - | - |

## Table 3 (cont.)

### South Controlled Area Radiological Characterization Soil Sample Field Ex-Situ Screening and Vendor Laboratory Results Summary

| Sampling Data | | | | | Field Soil Screening Data | | | | | | Laboratory Data | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Sample ID | Sample Depth (ft) | Sample Date | Sample Time | Description | Screen Date | Sample Weight grams | 609 (559-669) Kev Gross Counts CP5M | CPM | Soil Gamma Screening Estimated Ra-226 pCi/g | SSL (< or >) | Sample Sent to Lab | Ra-226 pCi/g | Error Estimate pCi/g | MDC pCi/g |
| DP-36 | 1.0'-1.5' | 9/9/2025 | 1330 | Very light brown sand, non firm sandstone | 9/10/2025 | 3000 | 807 | 161 | 1.0 | < | yes | 0.5 | 0.1 | 0.2 |
| DP-37 | 0.5'-1.0 | 9/10/2025 | 830 | 3/4-2" gravel w/ light brown sand | 9/10/2025 | 3000 | 9815 | 1963 | 25.7 | > | - | - | - | - |
| DP-37 | 1.0'-1.5' | 9/10/2025 | 845 | 3/4" gravel mix w/ light brown sand | 9/10/2025 | 3000 | 1258 | 252 | 1.1 | < | yes | 1.1 | 0.2 | 0.2 |
| DP-37 | 1.5'-2.0' | 9/10/2025 | 850 | Brown loam/sand mix | 9/10/2025 | 3000 | 1123 | 225 | 1.0 | < | - | - | - | - |
| DP-38 | 0.5'-1.0 | 9/10/2025 | 910 | 3/4" gravel mix w/ light brown sand | 9/10/2025 | 3000 | 1903 | 381 | 2.9 | < | yes | 3.4 | 0.3 | 0.2 |
| DP-38 | 1.0'-1.5' | 9/10/2025 | 920 | Light brown compacted sand w/ roots | 9/10/2025 | 3000 | 1043 | 209 | 1.0 | < | - | - | - | - |
| DP-39 | 0.5'-1.0 | 9/10/2025 | 935 | Light brown compacted sand w/ roots | 9/10/2025 | 3000 | 6122 | 1224 | 15.1 | > | - | - | - | - |
| DP-39 | 1.5'-2.0' | 9/10/2025 | 950 | Brown loose sand | 9/10/2025 | 3000 | 957 | 191 | 1.0 | < | yes | 0.5 | 0.1 | 0.2 |
| DP-39 | 2.0'-2.5' | 9/10/2025 | 1000 | Very light brown sand, non firm sandstone | 9/10/2025 | 3000 | 963 | 193 | 1.0 | < | - | - | - | - |
| DP-41 | 0.5'-1.0' | 9/22/2025 | 800 | Brown silty sand mix 3/4 base course | 9/24/2025 | 3000 | 5022 | 1004 | 11.9 | > | - | - | - | - |
| DP-41 | 1.0'-1.5' | 9/22/2025 | 810 | Brown silty sand mix 3/4 base course | 9/24/2025 | 3000 | 3360 | 672 | 7.1 | > | - | - | - | - |
| DP-41 | 2.5'-3.0' | 9/24/2025 | 1010 | Grey/brown soil w/ stones and clay | 9/24/2025 | 3000 | 2385 | 477 | 4.3 | < | - | - | - | - |
| DP-41 | 3.5'-4.0' | 9/24/2025 | 1030 | Grey/brown soil w/ stones and clay | 9/24/2025 | 3000 | 7134 | 1427 | 18.0 | > | yes | 17.2 | 0.5 | 0.3 |
| DP-44 | 1.0'-1.5' | 9/22/2025 | 850 | Light brown silty w/ roots mix clay | 9/24/2025 | 3000 | 1307 | 261 | 1.2 | < | yes | 1.0 | 0.2 | 0.2 |
| DP-44 | 1.5'-2.0' | 9/22/2025 | 940 | Brown sandy/silt w/ roots | 9/24/2025 | 3000 | 1257 | 251 | 1.1 | < | - | - | - | - |
| DP-44 | 2.0'-2.5' | 9/22/2025 | 950 | Brown sandy/silt w/ roots | 9/24/2025 | 3000 | 1197 | 239 | 1.0 | < | - | - | - | - |
| DP-46 | 0.5'-1.0' | 9/24/2025 | 810 | Light brown sandy w/ roots | 9/24/2025 | 3000 | 1401 | 280 | 1.5 | < | yes | 1.0 | 0.2 | 0.2 |
| DP-47 | 0.5'-1.0' | 9/24/2025 | 855 | Grey sandy waste rock | 9/24/2025 | 3000 | 25275 | 5055 | 70.2 | > | - | - | - | - |
| DP-47 | 1.0'-1.5' | 9/24/2025 | 925 | Grey sandy waste rock | 9/24/2025 | 3000 | 23640 | 4728 | 65.5 | > | - | - | - | - |
| DP-48 | 0.5'-1.0' | 9/24/2025 | 830 | Brown/grey w/ peebles & roots | 9/24/2025 | 3000 | 1484 | 297 | 1.7 | < | yes | 2.4 | 0.2 | 0.2 |

Note: Soil samples were not collected at locations DP-03, DP-14, DP-40, DP-42, DP-43, DP-45, and DP-49.

**Table 4**
**South Controlled Area Surface and Subsurface Soil Ra-226 Level Summary**

| Data Point ID | Static Gamma CPM | Static Gamma Estimated Ra-226 pCi/g 0.0'-0.5' (surface) Soil | Ex-Situ Soil Screening Estimated Ra-226 pCi/g | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | 0.0'-0.5' Soil (surface) | 0.5'-1.0' Soil | 1.0'-1.5' Soil | 1.5' - 2.0' Soil | 2.0'-2.5' Soil | 2.5'-3.0' Soil | 3.0'-3.5' Soil | 3.5'-4.0' Soil | 4.0'-4.5' Soil | 4.5'-5.0' Soil | 5.0'-5.5' Soil | 5.5'-6.0' Soil | 6.0'-6.5' Soil | 6.5'-10.0' Soil | 10.0'-10.5' Soil |
| DP-01 | 5420 | 2.2 | 2.1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-02 | 5690 | 2.6 | 2.1 | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-03 | 7330 | 5.2 | - | No Subsurface Soil Sample Taken - Collimated Static Survey Estimated Below Cleanup Level | | | | | | | | | | | - | - | - |
| DP-04 | 22600 | 29.7 | | 15.2 | 1.8 | | 2.2 | - | - | - | - | - | - | - | - | - | - |
| DP-05 | 8600 | 7.3 | - | 1.1 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-06 | 51000 | 75.1 | - | 44.0 | | 2.6 | | 1.0 | - | - | - | - | - | - | - | - | - |
| DP-07 | 13000 | 14.3 | - | 9.0 | 4.5 | | 18.9 | | 1.1 | - | - | - | - | - | - | - | - |
| DP-08 | 30500 | 42.3 | - | 2.5 | 1.4 | | 1.1 | - | - | - | - | - | - | - | - | - | - |
| DP-09 | 18100 | 22.5 | - | 1.1 | 2.8 | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-10 | 34000 | 47.9 | - | 8.1 | 1.3 | 1.8 | 1.6 | - | - | - | - | - | - | - | - | - | - |
| DP-11 | 10600 | 10.5 | - | 2.4 | 1.1 | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-12 | 17100 | 20.9 | - | 1.9 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-13 | 63900 | 95.7 | - | 3.0 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-14 | 6430 | 3.8 | - | No Subsurface Soil Sample Taken - Collimated Static Survey Estimated Below Cleanup Level | | | | | | | | | | | - | - | - |
| DP-15 | 16000 | 19.1 | - | 2.7 | | 1.0 | - | - | - | - | - | - | - | - | - | - | - |
| DP-16 | 10900 | 10.9 | - | 1.3 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-17 | 16800 | 20.4 | 24.6 | 1.0 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-18 | 11400 | 11.7 | - | 1.0 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-19 | 9130 | 8.1 | - | 1.0 | 1.0 | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-20 | 7050 | 4.8 | - | 1.0 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-21 | 41800 | 60.4 | - | | 3.3 | | 1.1 | - | - | - | - | - | - | - | - | - | - |
| DP-22 | 14600 | 16.9 | - | 3.5 | 1.0 | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-23 | 7830 | 6.0 | - | 5.0 | 2.4 | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-24 | 16900 | 20.5 | - | 1.3 | 1 | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-25 | 6740 | 4.3 | - | 3.6 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-26 | 81700 | 124.2 | - | | 5.7 | | 1.0 | | 1.0 | - | - | - | - | - | - | - | - |
| DP-27 | 11300 | 11.6 | - | 12.1 | 1.0 | | 1.0 | | | - | - | - | - | - | - | - | - |
| DP-28 | 10400 | 10.1 | - | 1.0 | 1.0 | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-29 | 45000 | 65.5 | - | 38.9 | 63.5 | | | | | No Further Sample Taken - Concrete Slab Encountered @ 3.7' bgs | | | | | | | |
| DP-30 | 26800 | 36.4 | - | 50.8 | 113 | | | | 8.3 | 2.2 | | | | 1.2 | - | - | |
| DP-31 | 9600 | 8.9 | - | 23.5 | 44 | | | | 20.3 | | | 0.9 | 5.5 | | | 1.7 | |
| DP-32 | 17500 | 21.5 | - | 44.9 | | 46.3 | | | 39.9 | | 35.9 | 33.5 | | | | - | |
| DP-33 | 17400 | 21.3 | - | 1.7 | 1.0 | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-34 | 47100 | 68.9 | - | 2.2 | 1.0 | | 1 | - | - | - | - | - | - | - | - | - | - |
| DP-35 | 12900 | 14.1 | - | 1.3 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-36 | 8170 | 6.6 | - | 3.9 | 1.0 | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-37 | 13000 | 14.3 | - | 25.7 | 1.1 | 1.0 | - | - | - | - | - | - | - | - | - | - | - |
| DP-38 | 11700 | 12.2 | - | 2.9 | 1.0 | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-39 | 28700 | 39.4 | - | 15.1 | | 1.0 | 1.0 | - | - | - | - | - | - | - | - | - | - |
| DP-40 | 19500 | 24.7 | - | Elevated individual rock observed. Removed rock, gamma scan after rock removal below 6,000 cpm collimated | | | | | | | | | | | | | |
| DP-41 | 13700 | 15.4 | - | 11.9 | 7.1 | | | 4.3 | | 18 | Excavation Halted Due to Trench Collapse | | | | | | |
| DP-42 | 24600 | 32.9 | - | After top 6 inches of soil removed, gamma scan below 6,000 cpm collimated | | | | | | | | | | | | | |
| DP-43 | 11100 | 11.3 | - | After top 6 inches of soil removed, gamma scan below 6,000 cpm collimated | | | | | | | | | | | | | |
| DP-44 | 82200 | 125.0 | - | - | 1.2 | 1.1 | 1.0 | - | - | - | - | - | - | - | - | - | - |
| DP-45 | 28200 | 38.6 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-46 | 10100 | 9.7 | - | 1.5 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-47 | 56600 | 84.1 | - | 70.2 | 65.5 | Excavation Halted Due to Trench Collapse | | | | | | | | | | | |
| DP-48 | 13100 | 14.5 | | 1.7 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DP-49 | 16300 | 19.6 | | - | - | - | - | - | - | - | - | - | - | - | - | - | - |

Note: Static Gamma Estimated pCi/g levels were estimated from .5" lead collimated detector static gamma measurements.

## Table 5
### Mt. Taylor Mine Site - SCA Soil Radiological Characterization
### Estimated Volumes of Areas above the 6.8 Ra-226 pCi/g Investigation Level

| Estimated Depth of Area > 6.8 Ra-226 pCi/g Investigation Level | Approximate Land Area (acre) | Estimated Volume [1] (cubic yard) |
|---|---|---|
| surface to 6" bgs | 14 | 11,300 |
| surface to 1.0' bgs | 3.0 | 4,900 |
| surface to 2.0' bgs | 0.5 | 1,620 |
| surface to 2.5' bgs | 0.01 | 40 |
| surface to >4.0' bgs [2] | 0.2 | 1,300 |
| surface to 5.0' bgs | 2.0 | 4,900 |
| surface to >10.0' bgs [2] | 1.0 | 2,500 |
| Estimated Total | 21 | 26,560 |

Note (1): Estimates are based on area historic Site use, observed waste and debris and excavation depth. Estimated volumes represent planning-level estimates and are not final excavation quantities.
Note (2): For the depths >4.0' and >10.0" bgs the estimated volume is an estimated minimum volume.

# Figures





**Figure 1**
**Mt. Taylor Mine Site**
**South Controlled Area Soil Radiologic Characterization Area**

March 2026

Environmental Services, Inc.

0 100 200 400 600 800 Feet

South Controlled Area Radiologic Characterization Area
Previously Characterized Area
Fence






**Figure 2**
**Mt. Taylor Mine Site**
**South Controlled Area Surface Soil Gamma Scan Survey Data**

AVM Environmental Services, Inc.

0 100 200 400 600 800 Feet

Estimated Ra-226 pCi/g
- <1.8 pCi/g
- 1.9 - 3.4 pCi/g
- 3.5 - 6.8 pCi/g
- 6.9 - 20.0 pCi/g
- 20.1 - 30.0 pCi/g
- 30.1 - 40.0 pCi/g
- >40.1 pCi/g
- Area Outline
- Bare/Collimated Detector Boundary
- Fence




N
W E
S

AVM Environmental Services, Inc.


**Figure 3**
**Mt. Taylor Mine Site**
**South Controlled Area Gamma Scan Survey**
**Data and Data Point Locations**

0 150 300 600 900 1,200 Feet

**Legend**

**Estimated Ra-226 pCi/g**

- <1.8 pCi/g
- 1.9 - 3.4 pCi/g
- 3.5 - 6.8 pCi/g
- 6.9 - 20.0 pCi/g
- 20.1 - 30.0 pCi/g
- 30.1 - 40.0 pCi/g
- >40.1 pCi/g
- Data Point
- Characterization Area
- × — × Fence




N
W E
S

Environmental Services, Inc.

# Figure 4
# Mt. Taylor Mine Site
# South Controlled Area Gamma Scan Survey Data and Data Point Locations with Depth Above the 6.8 pCi/g IL

0 150 300 600 900 1,200 Feet

**Legend**

**Estimated Ra-226 pCi/g**

- <1.8 pCi/g
- 1.9 - 3.4 pCi/g
- 3.5 - 6.8 pCi/g
- 6.9 - 20.0 pCi/g
- 20.1 - 30.0 pCi/g
- 30.1 - 40.0 pCi/g
- >40.1 pCi/g

Data Point ID (6.8 pCi/g IL cont. Depth)

Contamination Area

Fence



N
W E
S

Environmental Services, Inc.

# Figure 5
# Mt. Taylor Mine Site
# South Controlled Area Estimated Contamination Depths Exceeding the 6.8 Ra-226 pCi/g IL

0 150 300 600 900 1,200 1,500 Feet

**Legend**

- 0.5' Contamination depth above the Ra-226 pCi/g IL
- 1.0' Contamination depth above the Ra-226 pCi/g IL
- 2.0' Contamination depth above the Ra-226 pCi/g IL
- 2.5' Contamination depth above the Ra-226 pCi/g IL
- >4.0' Contamination depth above the Ra-226 pCi/g IL
- 5.0' Contamination depth above the Ra-226 pCi/g IL
- >10.0' Contamination depth above the Ra-226 pCi/g IL
- Characterization Area
- Fence

**Appendix A**
**Surface and Subsurface Contamination Field Investigation Documentation**
**(Soil Sample Log Forms, Field Soil Sample Ex-Situ Gamma Radiation Screening Forms)**

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Static Gamma Radiation Survey Field Form**

Instrumentation : Scaler/Ratemeter L3003 s#2503683 Detector SPA-3 #30

Instrument Calibration Date: 2-17-25 / 11-25-24 Instrument Daily Function Check Performed: ✓

2"x2" NaI Detector Collimated ✓ Yes or ✓ No.

Survey Area/Unit Decsription MTR SCA

| Survey Date/Time | Survey Point ID/Description | Survey Point Coordinate | | Gamma Radiation Reading - CPM | | Exposure Rate µR/hr | Comments/Notes |
|---|---|---|---|---|---|---|---|
| | | Northing | Easting | Bare | Collimated (0.5"Pb) | | |
| 9-11-25 | DP-01 | 1581460 | 2782649 | 21800 | 5450 | | |
| 9-11-25 | DP-02 | 1581403 | 2782634 | 24800 | 5690 | | |
| 9-11-25 | DP-03 | 1580334 | 2783446 | | 7330 | | |
| 9-11-25 | DP-04 | 1580214 | 2783228 | | 22600 | | |
| 9-11-25 | DP-05 | 1580105 | 2783059 | | 8600 | 55 | |
| 9-11-25 | DP-06 | 1580057 | 2782744 | | 51000 | | |
| 9-11-25 | DP-07 | 1579926 | 2782701 | | 13000 | | |
| 9-11-25 | DP-08 | 1579905 | 2782554 | | 30500 | | |
| 9-10-25 | DP-09 | 1579677 | 2782288 | | 18100 | 64 | |
| 9-10-25 | DP-10 | 1579580 | 2782156 | | 34000 | 90 | |
| 9-10-25 | DP-11 | 1579476 | 2781912 | | 10600 | 40 | |
| 9-11-25 | DP-12 | 1579671 | 2781505 | | 17100 | | |
| 9-11-25 | DP-13 | 1579649 | 2781482 | | 63900 | | |
| 9-11-25 | DP-14 | 1579362 | 2781514 | | 6430 | | |
| 9-11-25 | DP-15 | 1579277 | 2781168 | | 16000 | | |
| 9-11-25 | DP-16 | 1579207 | 2780987 | | 10900 | | |
| 9-11-25 | DP-17 | 1579006 | 2781444 | 36200 | 16800 | | |
| 9-11-25 | DP-18 | 1578704 | 2781522 | | 11400 | | |
| 8-20-25 | DP-19 | 1580006 | 2783183 | | 9130 | 38 | |
| 9-2-25 | DP-20 | 1579882 | 2782905 | | 7630 | 32 | |
| 8-20-25 | DP-21 | 1579865 | 2783018 | | 41800 | 130 | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Static Gamma Radiation Survey Field Form**

Instrumentation.: Scaler/Ratemeter L3003 SN 6830, Detector SPA-3 SN 30

Instrument Calibration Date: 11-25-24 / 2-17-25, Instrument Daily Function Check Performed: Y

2"x2" NaI Detector Collimated ✓ Yes or _____ No.

Survey Area/Unit Decsription MTM SCA

| Survey Date/Time | Survey Point ID/Description | Survey Point Coordinate | | Gamma Radiation Reading - CPM | | Exposure Rate µR/hr | Comments/Notes |
|---|---|---|---|---|---|---|---|
| | | Northing | Easting | Bare | Collimated (0.5"Pb) | | |
| 8-20-25 | DP-22 | 1579677 | 2783113 | | 14600 | 48 | |
| 8-20-25 | DP-23 | 1579757 | 2782602 | | 7830 | 31 | |
| 8-20-25 | DP-24 | 1579607 | 2782731 | | 16900 | 42 | |
| 8-20-25 | DP-25 | 1579503 | 2782431 | | 6740 | 22 | |
| 9-8-25 | DP-26 | 1579355 | 2782469 | | 59600 | 150 | |
| 8-20-25 | DP-27 | 1579285 | 2782623 | | 11300 | 38 | |
| 8-20-25 | DP-28 | 1579254 | 2782503 | | 10400 | 40 | |
| 8-20-25 | DP-29 | 1578981 | 2782235 | | 45000 | 145 | |
| 8-20-25 | DP-30 | 1578856 | 2782138 | | 26800 | 100 | |
| 8-20-25 | DP-31 | 1578781 | 2782026 | | 9600 | 30 | |
| 8-20-25 | DP-32 | 1578652 | 2782119 | | 17500 | 59 | |
| 9-9-25 | DP-33 | 1579458 | 2783273 | | 17400 | 70 | |
| 9-9-25 | DP-34 | 1579304 | 2783207 | | 47100 | 170 | |
| 9-9-25 | DP-35 | 1579249 | 2783318 | | 12900 | 55 | |
| 9-9-25 | DP-36 | 1578756 | 2782755 | | 8170 | 27 | |
| 9-9-25 | DP-37 | 1578560 | 2782985 | | 13000 | 35 | |
| 9-9-25 | DP-38 | 1578351 | 2783006 | | 11700 | 30 | |
| 9-9-25 | DP-39 | 1578259 | 2783023 | | 28700 | 75 | |
| 9-9-25 | DP-40 | 1578235 | 2783136 | | 19500 | 45 | Orig. Route 2x 2' from point. Retrieved. |
| 9-18-25 | DP-41 | 1578077 | 2781517 | | 13700 | 40 | |
| 9-18-25 | DP-42 | 1578990 | 2783874 | | 24600 | 60 | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Static Gamma Radiation Survey Field Form**

Instrumentation : Scaler/Ratemeter L3003# 6830, Detector SPA-3 # 30

Instrument Calibration Date: 11-25-24 / 2-17-25, Instrument Daily Function Check Performed: Y

2"x2" NaI Detector Collimated ✓ Yes or _____ No.

Survey Area/Unit Decsription MTM SCA

| Survey Date/Time | Survey Point ID/Description | Survey Point Coordinate | | Gamma Radiation Reading - CPM | | Exposure Rate µR/hr | Comments/Notes |
|---|---|---|---|---|---|---|---|
| | | Northing | Easting | Bare | Collimated (0.5"Pb) | | |
| 9-18-25 | DP-43 | 1578871 | 2783751 | | 11100 | 30 | |
| 9-18-25 | DP-44 | 1578764 | 2783241 | | 82200 | 150 | |
| 9-18-25 | DP-45 | 1578730 | 2783234 | | 28200 | 50 | |
| 9-18-25 | DP-46 | 1578649 | 2783608 | | 10100 | 30 | |
| 9-18-25 | DP-47 | 1578470 | 2783560 | | 56600 | 160 | |
| 9-18-25 | DP-48 | 1578415 | 2783544 | | 13100 | 45 | |
| 9-18-25 | DP-49 | 1578463 | 2783277 | | 16300 | 35 | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Gamma Radiation Survey**
**Static Gamma Radiation Survey Field Form**

Instrumentation : Scaler/Ratemeter L3003 & 6830, Detector S/A-3 #30

Instrument Calibration Date: 11-25-24 / 2-17-25, Instrument Daily Function Check Performed: Y

2"x2" NaI Detector Collimated ✓ Yes or _____ No.

Survey Area/Unit Decsription MTM SCA

| Survey Date/Time | Survey Point ID/Description | Survey Point Coordinate | | Gamma Radiation Reading - CPM | | Exposure Rate µR/hr | Comments/Notes |
|---|---|---|---|---|---|---|---|
| | | Northing | Easting | Bare | Collimated (0.5"Pb) | | |
| 9-8-25 | DP-20 | 1579881 | 2782874 | | 7050 | 34 | New Location |
| 9-8-25 | DP-26 | 1579353 | 2782458 | | 81700 | 170 | New Location |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| DP-32 | 8-21-25 @740 | 0'-10' | Gray Compacted silt, Sand | |
| DP-32 | 8-21-25 @745 | 15'-20' | " " " | |
| DP-32 | 8-21-25 @750 | 3'-3.5' | " " " | |
| DP-32 | 8-21-25 @758 | 4.5-5.0' | " " " timber | |
| DP-32 | 8-21-25 @830 | 5.0-10.0' | " " " Loose debris trash | |
| DP-31 | 8-21-25 @845 | .5'-1.0' | Brown silty sandy. bottom gray Rock/sand | |
| DP-31 | 8-21-25 @900 | 1.0'-2.0' | Gray Rock/Sandy debris | |
| DP-31 | 8-21-25 @910 | 2.0-3.5 | No-Sample Collected | |
| DP-31 | 8-21-25 @915 | 3.0-5.0' | Gray Rock/sand mix w/ Purple & Dark clay/silt. | |
| DP-31 | 8-21-25 @920 | 5.0 5.5' | Dark clay/silt w gray mix | |
| DP-31 | 8-21-25 @930 | 5.5'-10.0' | Dark Clay/silt w/ gray mix wood debris Lumber | |
| DP-30 | 8-21-25 @1006 | .5'-1.0' | gray Rock Sand mix | |
| DP-30 | 8-21-25 @1015 | 1.0'-4.0' | " " " " | |
| DP-30 | 8-21-25 @1025 | 4.0-4.5 | 3/4" base gravel w/ Sand. | |
| DP-30 | 8-21-25 @1035 | 4.5-5.0 | Brown/light brown compacted silt w/ clay & light oxide | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| DP-30 | 8-21-25 @ 1045 | 6-6.5 | Dark Clay / Silty | |
| DP-29 | 8-21-25 @ 1145 | 0.5'-1.0' | Grey waste Rock/sand, debris & wires | |
| DP-29 R | 8-21-25 @ 1223 | 10'-3.7' | " " " " | |
| DP-31 | 8-21-25 @ 1245 | 10'-10.25' | Dark compacted clay, wet | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| DP-28 | 9-3-25 0750 | .5-1.0' | Dark brown silty / Sand | |
| DP-28 | 9-3-25 800 | 1.0-1.5' | mix brown to sand shale / Sand clay | |
| DP-27 | 9-3-25 830 | .5-1.0 | gravel Sand mix 3/4 - 2" | |
| DP-27 | 9-3-25 840 | 1.0-2.0 | Brown / Dark Brown clay - silt Compacted Shale | |
| DP-27 | 9-3-25 850 | 2.0-3.0 | light brown Sand | |
| DP-21 | 9-3-25 930 | 1.0'-1.5' | mix - brown silty & grey waste rock | |
| DP-21 | 9-3-25 940 | 2.0-2.5 | Dark brown silty - light clay | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| DP-19 | 9/3/25 10:20 | 0.5-1.0' | Dark Clay, loomy Brown Soil | |
| DP-19 | 9/3/25 10:30 | 1.0-1.5' | Dark Brown Soil | |
| DP-22 | 9/3/25 10:45 | 0.5'-1.0' | Base Course | Old Rail Road Site |
| DP-22 | 9/3/25 11:00 | 1.0-1.5' | Dark Brown Soil | |
| DP-23 | 9/3/25 12:15 | 0.5-1.0' | Asphalt 4", Base Course, Dark Brown Soil | |
| DP-23 | 9/3/25 12:30 | 1.0-1.5' | Clay, dark brown Soil | Possible Back Fill |
| DP-24 | 9/3/25 13:00 | 0.5-1.0' | Clay Silt, loomy Brown Soil | |
| DP-24 | 9/3/25 13:15 | 1.0-1.5 | Clay, light brown soil | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| DP-20R | @900 9-8-25 | .5-1.0' | Dark brown silty Sand Compact. small amount of clay | |
| DP-25 | 9-8-25 @940 | .5-1.0' | light Sandy w gravel 1"-2" | |
| DP-26R | 9-8-25 @1020 | 1.0'-1.5' | gravel w/ light brown silty Sand | |
| DP-26R | 9-8-25 @1040 | 2.0'-2.5' | light brown silty Sand | |
| DP-26R | 9-8-25 @1050 | 3.0'-3.5' | light brown silty Sand. | |
| DP-34 | 9-9-25 @1050 | .5'-1.0' | Dark Compacted silty clay | |
| DP-34 | 9-9-25 @1105 | 1.0'-1.5' | light brown Compacted Sand Roots | |
| DP-34 | 9-9-25 @1120 | 2.0-2.5' | light brown compacted Sand Roots | |
| DP-35 | 9-9-25 @1140 | 0.5'-1.0' | ~~light~~ brown Silty Clay VP | |
| DP-33 | 9-9-25 @1255 | 0.5-1.0' | Brown loamy Soil | |
| DP-33 | 9-9-25 @1307 | 1.0-1.5 | Brown Sandy Soil | |
| DP-34 | 9-9-25 @1320 | 0.5-1.0 | Yellowish Brown Soil/Base Coarse Sands | |
| DP-36 | 9-9-25 @1335 | 1.0-1.5 | Yellow brown Sandy (Soft Sandstone) | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| DP-37 | 9-10-25 @830 | 0.5'-1.0 | gravel & Sand 3/4"-2" | |
| DP-37 | 9-10-25 @845 | 1.0'-1.5' | gravel & light brown silty, Sand | |
| DP-37 | 9-10-25 @850 | 1.5'-2.0 | light brown Sandy silty | |
| DP-38 | 9-10-25 @910 | .5'-1.0' | Mix light brown Sandy w/ gravel | |
| DP-38 | 9-10-25 @920 | 1.0-1.5' | light brown Sandy w/ Roots | |
| DP-39 | 9-10-25 @935 | .5'-1.0 | Sandy w/ Roots light brown/gray | |
| DP-39 | 9-10-25 @950 | 1.5'-2.0 | Sandy loose | |
| DP-39 | 9-10-25 @1000 | 2.0'-2.5 | Sand / Sandstone | |
| DP-40 | 9-10-25 @1015 | | No Sample | |
| DP-11 | 9-10-25 @1044 | 6"-12" | Brown loamy Soil w/ some shale | |
| DP-11 | 9-10-25 @1100 | 1.0'-1.5' | Light brown loamy soil w/ some clay soil | |
| DP-10 | 9-10-25 @1120 | 0.5'-1.0' | Dark brown clayish Soil | |
| DP-10 | 9-10-25 @1135 | 1.0'-1.5' | light brown loamy Soil | |
| DP-10 | 9-10-25 @1145 | 1.5'-2.0' | Light brown Sandy Soil | |
| DP-10 | 9-10-25 @1155 | 2.0'-2.5' | " " | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| DP-09 | 9-10-25 @1300 | 0.5-1.0' | Light brown loamy/clayish soil | |
| ~~DP~~-09 | 9-10-25 @1320 | 1.0'-1.5' | Light brown loamy soil | |
| DP-02 | 9-11-25 @900 | 0.0-0.5' | Topsoil - Sandy w/ roots light brown | |
| DP-01 | 9-11-25 @910 | 0.0-0.5' | " " " | |
| DP-17 | 9-11-25 @840 | 0.0-0.5' | " " " " | |
| DP-17 | 9-11-25 @850 | .5'-1.0' | light brown Sandy w/ Roots | |
| DP-18 | 9-11-25 @920 | .5-1.0' | Compacted light brown Sand | |
| DP-08 | 9-15-25 @800 | .5-1.0' | " " " " Roots | |
| DP-08 | 9-15-25 @~~8~~815 | 1.0-1.5 | " " " " | |
| DP-08 | 9-15-25 @830 | 2.0-2.5' | " " " " | |
| ~~DP-06~~ ~~DP-08~~ VP | 9-15-25 @~~845~~900 | .5-1.0' | light brown Sandy w/ Roots | |
| ~~DP-09-06~~ | 9-15-25 9:15 | 1-1.5' | ~~brown Silty Clay w/ roots~~ | No Sample |
| DP-~~09~~06 | 9-15-25 9:20 | 1.5-2' | " " " | |
| DP-~~09~~06 | 9-15-25 9:35 | 2.5-3' | light brown Compacted sand | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| DP-04 | 09-15-25 10:00 | 0.5-1.0' | Compact/Silty Sand, Brown Slight waste rock | |
| DP-04 | 09-15-25 10:15 | 1-1.5 | ~~tome, Co~~ 10cm mixed clay 3/4 rock | |
| DP-04 | 09-15-25 10:30 | 2.0-2.5 | Compacted Silt Mixed clay | |
| DP 16 | 09-15-25 12:30 | 0.5-1.0 | light brown w/ grey tint Sandy Soil | |
| DP 15 | 09-15-25 1:15 | 0.5-1.0 | | |
| DP 15 | 09-15-25 1:30 | 1.5-2.0 | light brown Sandy ~~Silt~~ loam | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| DP05 | 09-16-25 8:10 | 0.5-1.0' | light brown Silty Sand w/Roots | |
| DP07 | 09-16-25 8:35 | 0.5-1.0' | Silty brown Clay, Compacted | |
| DP07 | 09-16-25 8:45 | 1.0-1.5' | | |
| DP07 | 09-16-25 9:00 | 2.0-2.5' | 3/4 Gravel, Compacted brown Silty Sand | |
| DP07 | 09-16-25 9:15 | 3.0-3.5' | Silty Clay brown | |
| DP12 | 09-16-25 9:40 | 0.5-1.0 | Compacted Sand, light brown | |
| DP13 | 09-16-25 10:00 | 0.5-1.0 | Compacted brown Silt w/ Gravel w/Clay | |
| DP41 | 9-22-25 8:00 | 0.5-1.0 | Brown Silty Sand 3/4 Gravel Mix | |
| DP41 | 9-22-25 8:10 | 1.0-1.5 | Brown Silty Sand 3/4 Gravel Mix w/Roots | |
| DP44 | 9-22-25 8:50 | 1.0-1.5 | light brown Silty With Roots, Clay, Stone | |
| DP44 | 9-22-25 9:40 | 1.5-2.0 | Brown Sandy Silt w/Roots | |
| DP44 | 9-22-25 9:50 | 2.0-2.5 | Brown Sand Silt w/Roots | |
| | | | | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Subsurface Soil Sample Log Form**
**Mt. Taylor Mine Site**

| Sample ID | Sample Date/Time | Sample Depth | Sample Description | Comments/Notes |
|---|---|---|---|---|
| DP16 | 09-24-25 8:10 | 0.5-1.0 | light brown sandy w/Roots | |
| DP48 | 09-24-25 8:30 | 0.5-1.0 | Brown and grey soil w/ Pebbles w/Roots | |
| DP47 | 09-24-25 8:55 | 0.5-1.0 | Grey Sandy w/ waste rock | |
| DP47 | 09-24-25 9:25 | 1.0-5.0 | Grey Sandy w/ waste rock | |
| DP41 | 09-24-25 10:10 | 2.5-3.0 | Grey/Brown soil w/ lime Stone and Clay | |
| DP41 | 09-24-25 10:30 | 3.5-4.0 | Grey w/ lime Stone/ Harder Clay rock | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S#68782, Detector 44-20 S# 295573
Instrument Calibration Date: 2-17-25/9-30-24, Instrument Function Check Performed: y
Survey Area/Unit Decsription MTM SCA Data Points

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 8-21-25 | Blank | - | 320 | | | | |
| 8-21-25 | 6.6 Ref Soil | 3000 | 2280 | | 456 | | |
| 8-21-25 | DP-30 6.0-6.5' 8-21-25 @1045 | 3000 | 1300 | | 260 | | |
| 8-21-25 | DP-31 5.5'-10.0' 8-21-25 @950 | 3000 | 2810 | | 562 | | |
| 8-21-25 | DP-32 5.0-10.0' 8-21-25 @830 | 3000 | 12514 | | 2503 | | |
| 8-21-25 | DP-30 4.5'-6.0 8-21-25 @1035 | 3000 | 1667 | | 333 | | |
| 8-21-25 | DP-30 4.0-4.5' 8-21-25 @1025 | 3000 | 3764 | | 753 | | |
| 8-21-25 | DP-30 1.0'-4.0' 8-21-25 @1015 | 3000 | 40130 | | 8026 | | |
| 8-21-25 | DP-30 .5'-1.0' 8-21-25 @1006 | 3000 | 18540 | | 3708 | | |
| 8-21-25 | DP31 5.0-5.5' 8-21-25 @920 | 3000 | 1215 | | 243 | | |
| 8-21-25 | DP31 3.0-5.0' 8-21-25 @915 | 3000 | 7927 | | 1585 | | |
| 8-21-25 | DP31 1.0-3.0' 8-21-25 @900 | 3000 | 16160 | | 3232 | | QA/QC CP5M 15945 |
| 8-21-25 | DP31 .5'-1.0' 8-21-25 @845 | 3000 | 9029 | | 1806 | | |
| 8-21-25 | DP-32 4.5-5.0 8-21-25 @758 | 3000 | 13350 | | 2670 | | |
| 8-21-25 | DP-32 3.0-3.5' 8-21-25 @750 | 3000 | 14725 | | 2945 | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 SN 68782, Detector L44-20 SN 295573
Instrument Calibration Date: 2-17-25 / 9-20-24, Instrument Function Check Performed: Y
Survey Area/Unit Decsription MTM SCM Oak Ranch

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 8-21-25 | DP-32 1.5'-2.0' 8-21-25 @745 | 3000 | 16975 | | 3395 | | |
| 8-21-25 | DP-32 .5'-1.0' 8-21-25 @740 | 3000 | 16485 | | 3297 | | |
| 8-21-25 | DP-31 10'-10.25' 8-21-25 @1245 | 3000 | 1464 | | 293 | | |
| 8-21-25 | DP-29R 1.0'-3.7' 8-21-25 @1223 | 2000 | 22920 | | 4584 | | |
| 8-21-25 | DP-29 0.5-1.0' 8-21-25 @1145 | 3000 | 14410 | | 2882 | | |
| 9-3-25 | Blank | | 341 | | 68 | | |
| 9-3-25 | 6.6 pc./g Ref Soil | 3000 | 2290 | | 458 | | |
| 9-3-25 | DP-21 2-2.5' 9-3-25 @940 | 3000 | 1268 | | 254 | | |
| 9-3-25 | DP-21 1.0-1.5' 9-3-25 @930 | 2069 | 1398 | 2027 | 405 | | |
| 9-3-25 | DP-27 2.0-2.0' 9-3-25 @850 | 3000 | 1086 | | 217 | | |
| 9-3-25 | DP-27 1.0-20' 9-3-25 @840 | 3000 | 1136 | | 227 | | |
| 9-3-25 | DP-27 .5'-1.0' 9-3-25 @830 | 3000 | 5073 | | 1015 | | |
| 9-3-25 | DP-28 1.0-1.5' 9-3-25 @800 | 3000 | 1028 | | 206 | | |
| 9-3-25 | DP-28 .5-1.0 9-3-25 @750 | 3000 | 1047 | | 209 | | |
| 9-3-25 | DP-19 1.0-1.5' 9-3-25 @1030 | 3000 | 1057 | | 211 | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter LZ221 S#08782, Detector L44-20 S#295573
Instrument Calibration Date: 2-17-25 / 9-30-24, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription MTM SCA Rate Points

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 9-3-25 | DP-14 0.5-1.0' 9-3-25 @1020 | 3000 | 1248 | | 250 | | |
| 9-3-25 | DP-22 1.0-1.5' 9-3-25 @1100 | 3000 | 1220 | | 244 | | QA/QC Dup CP5M 1238 |
| 9-3-25 | DP-22 .5-1.0' 9-3-25 @1045 | 3000 | 2113 | | 423 | | |
| 9-3-25 | DP-23 1.0-1.5' 9-3-25 @1230 | 3000 | 1730 | | 346 | | |
| 9-3-25 | DP-23 0.5-1.0' VP 9-3-25 @1315 | 3000 | 2633 | | 527 | | |
| 9-3-25 | DP 24 1.0-1.5' 9-3-25 @1315 | 3000 | 1181 | | 236 | | |
| 9-3-25 | DP 24 0.5-1.0' 9-3-25 @1300 | 3000 | 1353 | | 271 | | |
| 9-8-25 | Blank | - | 324 | | 65 | | |
| 9-8-25 | 6.6 pCi/Rad Soil | 3000 | 2311 | | 462 | | |
| 9-8-25 | DP-26 VP 3.0-2.5' 9-8-25 @1030 | 3000 | 1236 | | 247 | | |
| 9-8-25 | DP-26 VP 2.0-2.5' 9-8-25 @1040 | 3000 | 1177 | | 235 | | |
| 9-8-25 | DP-26 VP 1.0-1.5' 9-8-25 @1020 | 3000 | 2875 | | 575 | | QA/QC CP5M 2817 |
| 9-8-25 | DP-20 VP .5-1.0' 9-8-25 @9000 | 3000 | ~~277~~ 1230 VP | | 246 | | |
| 9-8-25 | DP-25 .5'-1.0' 9-8-25 @940 | 3000 | 2144 | | 429 | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S# 68782, Detector 44-20 S# 295573
Instrument Calibration Date: 2-17-25 / 9-30-24, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription MTM SCA Data Points

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 9-9-25 | Blank | | 320 | | 64 | | |
| 9-9-25 | 6.6 pCi/g Ref Soil | 3000 | 2299 | | 460 | | |
| 9-9-25 | DP 34 2.0-2.5' 9-9-25 @1120 | 3000 | 1158 | | 232 | | |
| 9-9-25 | DP-34 1.0-1.5' 9-9-25 @1105 | 3000 | 1049 | | ~~333~~ 210 TVP | | |
| 9-9-25 | DP-34 .5'-1.0' 9-9-25 @1050 | 3000 | 1653 | | 331 | | QA/QC 4 5m 1603 |
| 9-9-25 | DP-35 0.5'-1.0' 9-9-25 @1140 | 2324 | 1027 | 1325 | 265 | | |
| 9-9-25 | DP-33 1.0'-1.5' 9-9-25 @1305 | 3000 | 1150 | | 230 | | |
| 9-9-25 | DP-33 0.5'-1.0' 9-9-25 @1250 | 3000 | 1472 | | 294 | | |
| 9-10-25 | Blank | — | 329 | | 66 | | |
| 9-10-25 | 6.6 pCi/g Ref Soil | 3000 | 2171 | | 434 | | |
| 9-10-25 | DP36 1.0-1.5' 9-9-25 @1330 | 3000 | 807 | | 161 | | |
| 9-10-25 | DP36 0.5'-1.0' 9-9-25 @1320 | 3000 | 2229 | | 446 | | |
| 9-10-25 | DP-37 1.5'-2.0' 9-10-25 @850 | 3000 | 1123 | | 225 | | |
| 9-10-25 | DP-37 1.0'-1.5' 9-10-25 @845 | 3000 | 1258 | | 252 | | |
| 9-10-25 | DP-37 .5'-1.0' 9-10-25 @830 | 3000 | 9815 | | 1963 | | QA/QC cp5m 9548 |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S#68782, Detector L44-20 S#295577
Instrument Calibration Date: 2-17-25/9-30-24, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription MTM SCA Date Points

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 9-10-25 | DP-38 1.0-1.5' 9-10-25 @920 | 3000 | 1043 | | 209 | | |
| 9-10-25 | DP-38 .5-1.0' 9-10-25 @910 | 3000 | 1903 | | 381 | | |
| 9-10-25 | DP-39 2.0-2.5' 9-10-25 @1000 | 3000 | 963 | | 193 | | |
| 9-10-25 | DP 39 1.5-2.0' 9-10-25 @950 | 3000 | 957 | | 191 | | |
| 9-10-25 | DP-39 .5-1.0' 9-10-25 @935 | 3000 | 6122 | | 1224 | | DUP/QC CP5M 6198 |
| 9-10-25 | DP-10 2.0-2.5' 9-10-25 @1155 | 3000 | 1446 | | 289 | | |
| 9-10-25 | DP-10 1.5-2.0' 9-10-25 @1145 | 3000 | 1509 | | 302 | | |
| 9-10-25 | DP-10 1.0-1.5' 9-10-25 @1135 | 3000 | 1342 | | 268 | | |
| 9-10-25 | DP-10 0.5-1.0' 9-10-25 @1120 | 3000 | 3694 | | 739 | | |
| 9-10-25 | DP-11 1.0-1.5' 9-10-25 @1100 | 3000 | 1256 | | 251 | | |
| 9-10-25 | DP-11 0.5-1.0' 9-10-25 @1044 | 3000 | 1716 | | 343 | | |
| 9-10-25 | DP-09 1.0-1.5' 9-10-25 @1320 | 3000 | 1199 ~~1870~~ | | 240 ~~374~~ | | |
| 9-10-25 | DP-09 0.5-1.0' 9-10-25 @1300 | 3000 | 1269 | | 254 | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 S#68782, Detector L44-20 S#295573
Instrument Calibration Date: 2-7-25/9-30-25, Instrument Function Check Performed: Y
Survey Area/Unit Decsription MTM SCA Data Points

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CPSM | Weight Corrected CPSM | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 9-15-25 | Blank | — | 360 | | 72 | | |
| 9-15-25 | 6.6 Ref Soil | 3000 | 2240 | | 448 | | |
| 9-15-25 | DP-02 0-0.5' 9-11-25 @800 | 3000 | 1621 | | 324 | | |
| 9-15-25 | DP-01 0-0.5' 9-11-25 @810 | 3000 | 1606 | | 321 | | |
| 9-15-25 | DP-18 0.5-1.0' 9-11-25 @900 | 3000 | 1236 | | 247 | | |
| 9-15-25 | DP-17 0-0.5' 9-11-25 @840 | 3000 | 9430 | | 1886 | | |
| 9-15-25 | DP-17 0.5-1.0' 9-11-25 @850 | 3000 | 1249 | | 250 | | |
| 9-15-25 | DP-04 0.5-1.0' 9-15-25 @1000 | 3000 | 6166 | | 1233 | | |
| 9-15-25 | DP-04 1.0-1.5' 9-5-25 @1015 | 3000 | 1521 | | 304 | | |
| 9-15-25 | DP-04 2.0-2.5' 9-15-25 @1030 | 3000 | 1636 | | 327 | | |
| 9-15-25 | DP-06 .5-1.0' 9-15-25 @900 | 3000 | 16175 | | 3235 | | |
| 9-15-25 | DP-06 1.5-2.0 9-15-25 @920 | 3000 | 1779 | | 356 | | QA/QC CPSM 1830 |
| 9-15-25 | DP-06 2.5-3.0' 9-15-25 @935 | 3000 | 1219 | | 244 | | |
| 9-15-25 | DP-08 .5-1.0' 9-15-25 @800 | 3000 | 1767 | | 353 | | |
| 9-15-25 | DP-08 1.0-1.5' 9-15-25 @815 | 3000 | 1360 | | 272 | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter L2221 SN 68782, Detector L44-20 SN 295573
Instrument Calibration Date: 2-17-25/9-20-25, Instrument Function Check Performed: 4
Survey Area/Unit Decsription MTM SCA DP

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 9-15-25 | DP-08 2.0-2.5 9-15-25 @820 | 3000 | 1269 | | 254 | | |
| 9-16-25 | Blank | — | 281 | | 56 | | |
| 9-16-25 | 6.6 pCi/ Ref Soil | 3000 | 2269 | | 454 | | |
| 9-16-25 | DP-15 0.5-1.0' 9-15-25 @1315 | 3000 | 1828 | | 366 | | |
| 9-16-25 | DP-15 1.5-20' 9-15-25 @1330 | 3000 | 1247 | | 249 | | |
| 9-16-25 | DP-16 0.5-1.0' 9-15-25 @1270 | 3000 | 1353 | | 271 | | |
| 9-16-25 | DP-12 0.5-1.0' 9-16-25 @940 | 3000 | 1545 | | 309 | | |
| 9-16-25 | DP-05 0.5-1.0' 9-16-25 @810 | 3000 | 1254 | | 251 | | |
| 9-16-25 | DP-13 0.5-1.0' 9-16-25 @1000 | 3000 | 1918 | | 384 | | |
| 9-16-25 | DP-07 0.5-1.0' 9-16-25 @835 | 3000 | 4007 | | 801 | | QA/QC CPSM UP 734 3920 |
| 9-16-25 | DP-07 1.0-1.5' 9-16-25 @845 | 3000 | 2439 | | 488 | | |
| 9-16-25 | DP-07 2.0-2.5' 9-16-25 @900 | 3000 | 7448 | | 1490 | | |
| 9-16-25 | DP-07 3.0-3.5' 9-16-25 @915 | 3000 | 1269 | | 254 | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

**AVM Environmental Services, Inc.**
**Field Soil Sample Gamma Radiation Screening Form**
**Mt. Taylor Mine Site**

Instrumentation : Scaler/Ratemeter LZ221 S#68782, Detector L44-20 S# 295573
Instrument Calibration Date: 2-17-25/9-30-24, Instrument Function Check Performed: ✓
Survey Area/Unit Decsription MTM SCA Data Points

Area exposure rate:

| Date | Soil Sample ID | Sample Weight Grams | 609 (559-669) Kev Gross Counts, CP5M | Weight Corrected CP5M | CPM | Reference Soil Compare (< or >) | Comments |
|---|---|---|---|---|---|---|---|
| 9-24-25 | Blank | - | 284 | | 57 | | |
| 9-24-25 | 6.6 pC/g Ref Soil | 3000 | 2215 | | 443 | | |
| 9-24-25 | DP-41 1.0-1.5' 9-22-25 @810 | 3000 | 3360 | | 672 | | |
| 9-24-25 | DP-41 0.5-1.0' 9-22-25 @800 | 3000 | 5022 | | 1004 | | |
| 9-24-25 | DP-44 1.0-1.5' 9-22-25 @850 | 3000 | 1307 | | 261 | | |
| 9-24-25 | DP-44 1.5-2.0' 9-22-25 @940 | 3000 | 1257 | | 251 | | QA/QC CP5M 1205 |
| 9-24-25 | DP-44 2.0-2.5' 9-22-25 @950 | 3000 | 1197 | | 239 | | |
| 9-24-25 | DP-46 0.5-1.0' 9-24-25 @810 | 3000 | 1401 | | 280 | | |
| 9-24-25 | DP-48 0.5-1.0' 9-24-25 @830 | 3000 | 1484 | | 297 | | |
| 9-24-25 | DP-47 0.5-1.0' 9-24-25 @855 | 3000 | 25275 | | 5055 | | |
| 9-24-25 | DP-47 1.0'-5.0' 9-24-25 @925 | 3000 | 23640 | | 4728 | | |
| 9-24-25 | DP-41 2.5-3.0' 9-24-25 @1010 | 3000 | 2385 | | 477 | | |
| 9-24-25 | DP 41 3.5-4.0' 9-24-25 @1030 | 3000 | 7134 | | 1427 | | |
| | | | | | | | |
| | | | | | | | |

Technician Signature _____, Reviewed by _____

**Appendix B**
**Radiologic Instrument Calibration and Operational Function Check and Gamma Survey Detector Correlation Documentation**

# CERTIFICATE OF CALIBRATION


**LUDLUM MEASUREMENTS, INC.**
501 Oak Street
325-235-5494
Sweetwater, TX 79556, U.S.A.
www.ludlums.com


ACCREDITED
CERT # 4084.01

Model No. / Serial No. 500 / 114513

Customer AVM ENVIRONMENTAL SERVICES INC ORDER NO. 20485975/567484

Cal. Date 6-Jan-25 Cal Due Date 6-Jan-26 Cal. Interval 1 Year Procedure 500/Rev 8

☐ New Instrument Instrument Received ☑ Within Tolerance ☐ Out of Tol. ☐ Requiring Repair ☐ Other-See Comments

T. 74 °F RH 22 % Alt 716.3 mm Hg ☑ Meter Zeroed ☑ Mechanical Check

**PULSE WIDTH Uncertainty within 0.85% of reading**

| | As Found | As Left | Acceptable Range (µs) |
|---|---|---|---|
| NEG PULSE | 1.6 | 1.6 | 1.5 - 1.9 |
| POS PULSE | 1.6 | 1.6 | < 2.25 |

**PULSE AMPLITUDE (NEGATIVE) Uncertainty within 1.2% of reading**

| Reference Amplitude | As Found Amplitude Reading | As Left Amplitude Reading | Acceptable Range | Reference Amplitude | As Found Amplitude Reading | As Left Amplitude Reading | Acceptable Range |
|---|---|---|---|---|---|---|---|
| 1 V | 1 V | 1 V | 0.9 - 1.1 | 4 V | 4 V | 4 V | 3.6 - 4.4 |
| 100 mV | 100 mV | 100 mV | 90 - 110 | 400 mV | 410 mV | 410 mV | 360 - 440 |
| 10 mV | 10 mV | 10 mV | 9 - 11 | 40 mV | 41 mV | 41 mV | 36 - 44 |
| 1 mV | 1 mV | 1 mV | 0.9 - 1.1 | 4 mV | 4.1 mV | 4.1 mV | 3.6 - 4.4 |

**PULSE AMPLITUDE (POSITIVE) Uncertainty within 1.2% of reading**

| Reference Amplitude | As Found Amplitude Reading | As Left Amplitude Reading | Acceptable Range |
|---|---|---|---|
| 3 V | 3 V | 3 V | 2.7 - 3.3 |
| 300 mV | 300 mV | 300 mV | 270 - 330 |
| 30 mV | 30 mV | 30 mV | 27 - 33 |
| 3 mV | 3 mV | 3 mV | 2.7 - 3.3 |

**PULSE FREQUENCY (PERIOD) Uncertainty within 0.46% of reading**

| Pulser Range | As Found Period | As Left Period | Acceptable Range |
|---|---|---|---|
| x 10K | 6.669 | 6.669 | 6.534 - 6.8 |
| x 1K | 66.72 | 66.72 | 65.34 - 68 |
| x 100 | 667.2 | 667.2 | 653.4 - 680 |
| x 10 | 6671 | 6671 | 6534 - 6800 |
| x 1 | 66.73 | 66.73 | 65.34 - 68 |
| x 0.1 | 90 | 90 | 88.2 - 91.8 Counts |

Digital High Voltage Uncertainty within 1.2% of reading

| Reference Voltage | As Found Voltage Reading | As Left Voltage Reading | Acceptable Range |
|---|---|---|---|
| 500 V | | | 490 - 510 |
| 1500 V | | | 1470 - 1530 |

Analog High Voltage Uncertainty within 1.2% of reading

| Reference Voltage | As Found Voltage Reading | As Left Voltage Reading | Acceptable Range |
|---|---|---|---|
| 500 V | 500 | 500 | 475 - 525 |
| 2000 V | 2000 | 2000 | 1900 - 2100 |

| CPM Reading | As Found cpm Reading | As Left cpm Reading | Acceptable Range |
|---|---|---|---|
| MAX | 992 | 992 | 981 - 999 |
| MIN | 0-1 | 0-1 | 0 - 1* |

* READING OF 0-99 IS ACCEPTABLE FOR INSTRUMENTS WITH A S/N 100000 AND BELOW OR MAIN BOARD = 5208-066

**COMMENTS:**

CAL'D W/ 39" CABLE.

Ludlum Measurements, Inc. certifies that the above instrument has been calibrated by standards traceable to the National Institute of Standards and Technology, or to the calibration facilities of other International Standards Organization members, or have been derived from accepted values of natural physical constants or have been derived by the ratio type of calibration techniques.
All pass/fail determinations are based on the manufacturer's specifications without considering uncertainty factors.
Measurement results represent expanded uncertainties expressed at approximately the 95% level of confidence, using a coverage factor of k=2.
The calibration system conforms to the requirements of ANSI/NCSL Z540-1-1994 and ANSI N323AB-2013

ISO/IEC 17025:2017(E)
State of Texas Calibration License No. LO-1983

Reference Instruments:
Frequency Counter Model BK 1856D S/N 332E 18132 Cal Date 18-Dec 2024
Oscilloscope Model TEKMA 72:6830 S/N 1102645 Cal Date 11-Oct 2024
Voltmeter Model Fluke 83V S/N 94000441 Cal Date 14-Jun 2024

Calibrator William Tinsley William Tinsley Title Calibrator Date 6-January 2025
QC'd By [signature] Title Final QC Date 7 JAN 25


This certificate shall not be reproduced except in full, without the written approval of Ludlum Measurements, Inc.




AC Inst. Only ☐ ☑ Passed Dielectric (Hi-Pot) and Continuity Test ☐ Failed:

**AVM Environmental Services Inc.**

**Scaler/Ratemeter Calibration Form**

Model : L2221 S/N: 68782

Reference Instrument/Source: Ludlum Pulser 500, S/N:114513

**HV Calibration**

HV Test (2 points): Ref/Inst 600/600 Ref/Inst 900/900

**Ratemeter Calibration**

Instrument Threshold @ 100 (10 mV), WIN: Out, HV 900VDC; Pulser Threshold @ 200 (20mV)

| Range/Mode | Range Multiplier | Calibration Point (Pulser Setting) cpm x multiplier | Target CPM (±5%) | As Found Reading | | Left or Set Reading |
|---|---|---|---|---|---|---|
| Ratemeter | x1 | 40x1 | 38-42 | 40 | | " |
| | x1 | 40x10 | 380-420 | 400 | | " |
| | x10 | 40x100 | 3800-4200 | 4000 | | " |
| | x100 | 40x1K | 38K-42K | 40K | | " |
| | x1K | 40x10K | 380K-420K | 400K | | " |
| Digital Ratemeter | - | 40x1 | 38-42 | 40 | | " |
| | - | 40x10 | 380-420 | 399 | | " |
| | - | 40x100 | 3800-4200 | 3990 | | " |
| | - | 40x1K | 38K-42K | 40004 | | " |
| | - | 40x10K | 380K-420K | 400053 | | " |
| | | | | | | |

**Threshold/Gain Calibration**

WIN OUT

| Pulser Amplitude (mV) | Pulser CPM | | L2221 Theshold (mv) | Target CPM | L2221 CPM Found | | L2221 CPM Left or Set @ |
|---|---|---|---|---|---|---|---|
| 10.0 | 40000 | | 100 (10 mV) | 27K -33K | 31525 | | " |
| 20.0 | 40000 | | 200 (20 mV) | 27K -33K | 30790 | | " |
| 30.0 | 40000 | | 300 (30 mV) | 27K -33K | 30441 | | " |
| 40.0 | 40000 | | 400 (40 mV) | 27K -33K | 31849 | | " |
| 50.0 | 40000 | | 500 (50 mV) | 27K -33K | 31336 | | " |

Note: Use R174 Gain Control on Power Supply Board to adjust L2221 CPM @75% for Threshold/Gain Calibration

**Window Cut-off Points Check**

L2221 Threshold set @100 (10.0 mv)

WIN @ 100 (10.0 mV) ✓ WIN @ 400 (40.0 mV) ✓

WIN @ 200 (20.0 mV) ✓ WIN @ 500 (50.0 mV) ✓

Date 2-17-25 Calibrated By

Designer and Manufacturer of Scientific and Industrial Instruments

www.ludlums.com

# CERTIFICATE OF CALIBRATION


**LUDLUM MEASUREMENTS, INC.**
501 Oak Street
325-235-5494
Sweetwater, TX 79556, U.S.A.


ACCREDITED
CERT # 4084.01

Customer: AVM ENVIRONMENTAL SERVICES INC — ORDER NO. 20501145/577861

Mfg. Ludlum Measurements, Inc. — Model 19 — Serial No. 76248

Mfg. _____ — Model _____ — Serial No. _____

Cal. Date 20-Aug-25 — Cal Due Date 20-Aug-26 — Cal. Interval 1 Year — Meterface 202-016

Check mark ☑ applies to applicable instr. and/or detector IAW mfg. spec. — T. 74 °F — RH 43 % — Alt 705.9 mm Hg

☐ New Instrument — Instrument Received — ☑ Within Toler. +-10% — ☐ 10-20% — ☐ Out of Tol. — ☐ Requiring Repair — ☐ Other-See comments

☑ Mechanical ck. — ☑ Meter Zeroed — ☐ Background Subtract — ☐ Input Sens. Linearity
☑ F/S Resp. ck — ☑ Reset ck. — ☐ Window Operation — ☑ Geotropism
☑ Audio ck. — ☐ Alarm Setting ck. — ☑ Batt. ck.

☐ Calibrated in accordance with LMI SOP 14.8 — ☑ Calibrated in accordance with LMI SOP 14.9

Instrument Volt Set 800 V — Input Sens. 38 mV — Det. Oper. _____ V at _____ mV — Threshold Dial Ratio _____ = _____ mV

☐ HV Readout (2 points) — Ref./Inst. 500 / _____ V — Ref./Inst. 1000 / _____ V

**COMMENTS:**

Gamma Calibration: GM detectors positioned perpendicular to source except for M 44-9 in which the front of probe faces source.
Multimeter uncertainty within 1.3% of reading, Gamma uncertainty within 5.0% of reading, Neutron uncertainty within 7.0% of reading, Count rate uncertainty within 5.4% of reading.

| RANGE/MULTIPLIER | REFERENCE CAL. POINT | INSTRUMENT REC'D "AS FOUND READING" | INSTRUMENT METER READING |
|---|---|---|---|
| 5000 | 4000µR/hr | 4200 mR/hr | 4000 mR/hr |
| 5000 | 1000µR/hr | 1000 | 1000 |
| 500 | 400µR/hr = 75300CPM | 420 | 400 |
| 500 | 100µR/hr | 105 | 100 |
| 250 | 200µR/hr = 35900CPM | 200 | 200 |
| 250 | 100µR/hr | 100 | 100 |
| 50 | 7530 cpm | 44 | 40 |
| 50 | 1880 cpm | 10.5 | 10 |
| 25 | 3590 cpm | 20 | 20 |
| 25 | 898 cpm | 5 | 5 |

50, 25 Range(s) Calibrated Electronically

| Digital Readout | REFERENCE CAL. POINT | INSTRUMENT RECEIVED | INSTRUMENT METER READING |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| Log Scale | REFERENCE CAL. POINT | INSTRUMENT RECEIVED | INSTRUMENT METER READING |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Ludlum Measurements, Inc. certifies that the above instrument has been calibrated by standards traceable to the National Institute of Standards and Technology, or to the calibration facilities of other International Standards Organization members, or have been derived from accepted values of natural physical constants or have been derived by the ratio type of calibration techniques.
All pass/fail determinations are based on the manufacturer's specifications without considering uncertainty factors.
Measurement results represent expanded uncertainties expressed at approximately the 95% level of confidence, using a coverage factor of k=2.
The calibration system conforms to the requirements of ANSI/NCSL Z540-1-1994 and ANSI N323AB-2013

ISO/IEC 17025:2017(E)
State of Texas Calibration License No: LO-1963

**Reference Instruments and/or Sources:** Cs-137 S/N: ☐ 059 ☐ 2171CP ☐ 2261CP ☐ 720 ☐ 734 ☐ 781 ☐ 1131 ☐ 1616 ☐ 1696 ☐ 1909 ☐ 1918CP ☐ 2324/2521
☐ 5717CO ☐ 5719CO ☐ 60646 ☐ 70897 ☐ 73410 ☐ E552 ☐ G112 ☑ 2168CP ☑ S-394 ☐ S-1054 ☐ T10081 ☐ T10082 Neutron Am-241 Be ☐ T-304 Ra-226 ☐ Y982
☐ E551 ☐ 5105 ☐ CSV280

☐ Alpha S/N _____ ☐ Beta S/N _____ ☐ Other _____

m 500 S/N 371845 ☐ Oscilloscope S/N _____ ☑ Multimeter S/N 60050420

Calibrator Andrew Fuller Andrew J. Fuller — Title Calibrator — Date 20 AUG 25

QC'd By _____ — Title Final QC — Date 21 Aug 25


This certificate shall not be reproduced except in full, without the written approval of Ludlum Measurements, Inc.




AC Inst. Only ☐ Passed Dielectric (Hi-Pot) and Continuity Test ☐ Failed: _____

Designer and Manufacturer of Scientific and Industrial Instruments

www.ludlums.com

# CERTIFICATE OF CALIBRATION

LUDLUM MEASUREMENTS, INC.
501 Oak Street
325-235-5494
Sweetwater, TX 79556, U.S.A.

ACCREDITED
CERT # 4084.01

Customer AVM ENVIRONMENTAL SERVICES INC ORDER NO. 20479685/ 563226

Mfg. Ludlum Measurements, Inc. Model 19 Serial No. 76248

M Model Serial No.

Cal. Date 4-Oct-24 Cal Due Date 4-Oct-25 Cal. Interval 1 Year Meterface 202-016

Check mark ☑ applies to applicable instr. and/or detector IAW mfg. spec. T. 73 °F RH 41 % Alt. 708.4 mm Hg

☐ New Instrument Instrument Received ☑ Within Toler. +-10% ☐ 10-20% ☐ Out of Tol. ☐ Requiring Repair ☐ Other-See comments

☑ Mechanical ck. ☑ Meter Zeroed ☐ Background Subtract ☐ Input Sens. Linearity
☑ F/S Resp. ck. ☑ Reset ck. ☐ Window Operation ☑ Geotropism
☑ Audio ck. ☐ Alarm Setting ck. ☑ Batt. ck.

☐ Calibrated in accordance with LMI SOP 14.8 ☑ Calibrated in accordance with LMI SOP 14.9

Instrument Volt Set 800 V Input Sens. 37 mV. Det. Oper. V at mV Threshold Dial Ratio = mV

☑ HV Readout (2 points) Ref./Inst. 500 / V Ref./Inst. 1000 / V

**COMMENTS:**

Gamma Calibration: GM detectors positioned perpendicular to source except for M 44-9 in which the front of probe faces source.
Multimeter uncertainty within 1.3% of reading, Gamma uncertainty within 5.0% of reading, Neutron uncertainty within 7.0% of reading, Count rate uncertainty within 5.4% of reading

| RANGE/MULTIPLIER | REFERENCE CAL. POINT | INSTRUMENT REC'D "AS FOUND READING" | INSTRUMENT METER READING |
|---|---|---|---|
| 5000 | 4000µR/hr | 4000 µR/hr | 4000 µR/hr |
| 5000 | 1000µR/hr | 1000 | 1000 |
| 500 | 400µR/hr = 68,500 | 400 | 400 |
| 500 | 100µR/hr | 100 | 100 |
| 250 | 200µR/hr = 35600 | 210 | 200 |
| 250 | 100µR/hr | 100 | 100 |
| 50 | 6850 cpm | 40 | 40 |
| 50 | 1712 cpm | 10 | 10 |
| 25 | 3560 cpm | 21 | 20 |
| 25 | 890 cpm | 5 | 5 |

50, 25 Range(s) Calibrated Electronically

| Digital Readout | REFERENCE CAL. POINT | INSTRUMENT RECEIVED | INSTRUMENT METER READING |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| Log Scale | REFERENCE CAL. POINT | INSTRUMENT RECEIVED | INSTRUMENT METER READING |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Ludlum Measurements, Inc. certifies that the above instrument has been calibrated by standards traceable to the National Institute of Standards and Technology, or to the calibration facilities of other International Standards Organization members, or have been derived from accepted values of natural physical constants or have been derived by the ratio type of calibration techniques.
All pass/fail determinations are based on the manufacturer's specifications without considering uncertainty factors.
Measurement results represent expanded uncertainties expressed at approximately the 95% level of confidence, using a coverage factor of k=2.
The calibration system conforms to the requirements of ANSI/NCSL Z540-1-1994 and ANSI N323AB-2013

ISO/IEC 17025:2017(E)
State of Texas Calibration License No. LO-1963

**Reference Instruments and/or Sources:** Cs-137 S/N: ☐ 059 ☐ 2171CP ☐ 2281CP ☐ 720 ☐ 734 ☐ 781 ☐ 1131 ☐ 1616 ☐ 1896 ☐ 1909 ☐ 1916CP ☐ 2324/2521
☐ 5717CO ☐ 5719CO ☐ 60646 ☐ 70897 ☐ 73410 ☐ E552 ☐ G112 ☑ 2168CP ☐ S-394 ☐ S-1054 ☐ T10081 ☐ T10082 Neutron Am-241 Be. ☐ T-304 Ra-226 ☐ Y982
☐ E551 ☐ 5105 ☐ CSV280

☐ Alpha S/N ☐ Beta S/N ☐ Other

☐ m 500 S/N 371845 ☐ Oscilloscope S/N ☑ Multimeter S/N 60050420

rator Andrew Fuller Andrew J Fuller Title Calibrator Date 4 OCT 24

QC'd By Title Final QC Date 5 Oct 24

This certificate shall not be reproduced except in full, without the written approval of Ludlum Measurements, Inc.


AC Inst. Only ☐ Passed Dielectric (Hi-Pot) and Continuity Test ☐ Failed:

ludlums.com

ilac-MRA ACCREDITED CERT #4084.01

# CALIBRATION CERTIFICATE

Order No: 20475860

LUDLUM MEASUREMENTS, INC.
501 Oak Street
325-235-5494
Sweetwater, TX 79556, USA

Customer: AVM ENVIRONMENTAL SERVICES
1717 DEL NORTE BLVD
Address: GRANTS, NM 87020-2309
USA

Temp: 73.4 °F
Rel. H: 33%
Alt: 712mm Hg

Cal Date: 25-Nov-24
Cal Due Date: 25-Nov-25
Cal Interval: 1 year

Mfg.: Ludlum Measurements, Inc. **Model: 3003** Desc.: survey meter Serial No.: 25036838

**Model 3003 Parameters:**
- ☑ New Instrument
- Serial No.: 25036838
- ☑ Alarm Setting Ck.
- ☑ Audio Check
- ☑ Battery Check
- ☑ F/S Resp. Check
- ☑ HV Readout
- ☑ Mechanical Check
- ☑ Window Operation
- Firmware: F.4.4.1244
- Ref./Inst.: 600 / 598 V
- Ref./Inst.: 2000 / 2001 V
- Scaler Count: 6 second(s)
- ☑ LMI SOP 14.8
- Primary Units: cpm

*Ratemeter*

| Reference Point | Direct Reading |
|---|---|
| 5 Mcpm | 4.98 Mcpm |
| 2 Mcpm | 1.99 Mcpm |
| 800 kcpm | 798 kcpm |
| 200 kcpm | 199 kcpm |
| 80 kcpm | 79.7 kcpm |
| 20 kcpm | 19.8 kcpm |
| 8 kcpm | 7.98 kcpm |
| 2 kcpm | 1.99 kcpm |
| 800 cpm | 797 cpm |
| 200 cpm | 200 cpm |

*Scaler*

| Reference Point | Direct Reading |
|---|---|
| 5 Mcpm | 498 kcount |
| 2 Mcpm | 198 kcount |
| 800 kcpm | 79.8 kcount |
| 200 kcpm | 19.9 kcount |
| 80 kcpm | 7.99 kcount |
| 20 kcpm | 1.99 kcount |
| 8 kcpm | 798 count |
| 2 kcpm | 200 count |
| 800 cpm | 80 count |
| 200 cpm | 20 count |

**COMMENTS:**
See attachments for all other settings.

Det1. set up for gamma detector.

Det2. set up for typical M44-7.

Ludlum Measurements, Inc. certifies that the above instrument has been calibrated by standards traceable to the National Institute of Standards and Technology.
The pass/fail tolerance of 10% (unless otherwise noted) is based on the manufacturer's specifications without considering uncertainty factors.
Measurement results represent expanded uncertainties expressed at approximately the 95% level of confidence, using a coverage factor of k=2.
Measurement Uncertainties: Voltage measurements 1.4%, Gamma Exposure/Dose 5.6%, Neutron Dose 7.0%, Count rate 5.2%.
The calibration system conforms to the requirements of ANSI/NCSL Z540-1-1994 and ANSI N323AB-2013.

ISO/IEC 17025: 2017 (E)
State of Texas Calibration License No. LO-1963

**Reference Instruments and/or Source(s):**

Form ID #: AC243825681103

Pulser: 289155 Multimeter: 14670125

Calibrator: Manuela Aguilar Manuela Aguilar Title: Calibrator Date: 25-Nov-24

QC'd by: Title: Final QC Date: 26 Nov 2024



This certificate shall not be reproduced except in full, without the written approval of Ludlum Measurements, Inc.

www.ludlums.com

Designer and Manufacturer
of
Scientific and Industrial
Instruments

**LUDLUM MEASUREMENTS, INC.**
501 Oak Street
325-235-5494
Sweetwater, TX 79556, U.S.A.

# *Modification/Option Functional Check*

Customer AVM ENVIRONMENTAL SERVICES ORDER NO. 20475860

This Certifies that option or modification # 4498 - 1024

on the Ludlum Model 3000 Serial No. 258369 58 has been functionally checked.

Refer to applicable instrument manuals and/or addenda for specific operating instructions.

Check performed by Jonathon Hernandez Date 28-OCT-24

Manuela Aguilar 25-NOV-24

**AVM Environmental Services Inc.**

**Scaler/Ratemeter Calibration Form**

Model : L2221 S/N: 290801

Reference Instrument/Source: Ludlum Pulser 500, S/N:114513

**HV Calibration**

HV Test (2 points): Ref/Inst 600/600 Ref/Inst 900/900

**Ratemeter Calibration**

Instrument Threshold @ 100 (10 mV), WIN: Out, HV 900VDC; Pulser Threshold @ 200 (20mV)

| Range/Mode | Range Multiplier | Calibration Point (Pulser Setting) cpm x multiplier | Target CPM (±5%) | As Found Reading | | Left or Set Reading |
|---|---|---|---|---|---|---|
| Ratemeter | x1 | 40x1 | 38-42 | 40 | | " |
| | x1 | 40x10 | 380-420 | 400 | | " |
| | x10 | 40x100 | 3800-4200 | 4000 | | " |
| | x100 | 40x1K | 38K-42K | 40000 | | " |
| | x1K | 40x10K | 380K-420K | 400000 | | " |
| Digital Ratemeter | - | 40x1 | 38-42 | 41 | | " |
| | - | 40x10 | 380-420 | 416 | | " |
| | - | 40x100 | 3800-4200 | 3960 | | " |
| | - | 40x1K | 38K-42K | 39534 | | " |
| | - | 40x10K | 380K-420K | 395480 | | " |
| | | | | | | |

**Threshold/Gain Calibration**

WIN OUT

| Pulser Amplitude (mV) | Pulser CPM | | L2221 Theshold (mv) | Target CPM | L2221 CPM Found | | L2221 CPM Left or Set @ |
|---|---|---|---|---|---|---|---|
| 10.0 | 40000 | | 100 (10 mV) | 27K -33K | 30350 | | " |
| 20.0 | 40000 | | 200 (20 mV) | 27K -33K | 30714 | | " |
| 30.0 | 40000 | | 300 (30 mV) | 27K -33K | 31110 | | " |
| 40.0 | 40000 | | 400 (40 mV) | 27K -33K | 30431 | | " |
| 50.0 | 40000 | | 500 (50 mV) | 27K -33K | 31085 | | " |

Note: Use R174 Gain Control on Power Supply Board to adjust L2221 CPM @75% for Threshold/Gain Calibration.

**Window Cut-off Points Check**

L2221 Threshold set @100 (10.0 mv)

WIN @ 100 (10.0 mV) ✓ WIN @ 400 (40.0 mV) ✓

WIN @ 200 (20.0 mV) ✓ WIN @ 500 (50.0 mV) ✓

Date 2-17-25 Calibrated By

**AVM Environmental Services Inc.**
L2221 SCA/L44-20 Energy Calibration Form

SCA: L2221, SR #290801 Detector: Ludlum 44-20 (3x3 NaI Scintillator)

Calibration Source: Cs-137 Check Source, 5 uCi (August 2008) For 662 KeV Peak Cal

Threshold (input sensitivity) 652

Window, In/Out IN Window 20

HV Initial 100, At Peak 575

Maximum CPM: 204503 Background CPM: 9

HV Set @ 575 VDC

For Bi-214 609.2 KeV Peak (559 - 659 KeV ROI), Set Threshold @ 559, Window @ 10mV


Calibration Check w 1% U3O8 Ore Check Source: 15656 CPM

BKG = 63 cpm

Date 9-30-24 Calibrated By

**AVM Environmental Services**
**Ex-Situ Soil Screening Gamma Radiation Level to Ra-226 Correlation**
**Mt. Taylor Mine Site Subsurface Soil Investigation**

| Soil Sample/Ref Std | Date | Ra-226 pCi/g | CPM SCA 609 KeV Region |
|---|---|---|---|
| Blank | 9/30/2024 | - | 65 |
| DP-19, 0.5' - 1.0' | 9/3/2025 | 1.2 | 250 |
| DP-21, 2.0' - 2.5' | 9/3/2025 | 1.1 | 254 |
| DP-22, 1.0' - 1.5' | 9/3/2025 | 1.2 | 244 |
| DP-23, 1.0' - 1.5' | 9/3/2025 | 1.9 | 346 |
| DP-24, 0.5' - 1.0' | 9/3/2025 | 1.1 | 271 |
| DP-27, 1.0' - 2.0' | 9/3/2025 | 1.1 | 227 |
| DP-28, 0.5' - 1.0' | 9/3/2025 | 1.0 | 209 |
| DP-30, 4.5' - 6.0' | 8/21/2025 | 2.4 | 333 |
| DP-31, 10.0' - 10.25' | 8/21/2025 | 1.5 | 293 |
| DP-01, 0.0' - 0.5' | 9/11/2025 | 1.9 | 321 |
| DP-02, 0.0' - 0.5' | 9/11/2025 | 1.8 | 324 |
| DP-04, 1.0' - 1.5' | 9/15/2025 | 1.6 | 304 |
| DP-05, 0.5' - 1.0' | 9/16/2025 | 1.0 | 251 |
| DP-06, 1.5' - 2.0' | 9/15/2025 | 2.2 | 356 |
| DP-07, 3.0' - 3.5' | 9/16/2025 | 1.0 | 254 |
| DP-08, 0.5' - 1.0' | 9/15/2025 | 2.6 | 353 |
| DP-09, 1.0' - 1.5' | 9/10/2025 | 0.9 | 374 |
| DP-10, 1.0' - 1.5' | 9/10/2025 | 1.0 | 268 |
| DP-11, 0.5' - 1.0' | 9/10/2025 | 1.9 | 343 |
| DP-12, 0.5' - 1.0' | 9/16/2025 | 1.5 | 309 |
| DP-13, 0.5' - 1.0' | 9/16/2025 | 2.8 | 384 |
| DP-15, 0.5' - 1.0' | 9/15/2025 | 2.7 | 366 |
| DP-16, 0.5' - 1.0' | 9/15/2025 | 1.0 | 271 |
| DP-17, 0.0' - 0.5' | 9/11/2025 | 26.6 | 1886 |
| DP-17, 0.5' - 1.0' | 9/11/2025 | 1.0 | 250 |
| DP-18, 0.5' - 1.0' | 9/11/2025 | 0.8 | 247 |
| DP-20r, 0.5' - 1.0' | 9/8/2025 | 1.0 | 246 |
| DP-25, 0.5' - 1.0' | 9/8/2025 | 4.8 | 429 |
| DP-26r, 2.0' - 2.5' | 9/8/2025 | 0.9 | 235 |
| DP-33, 0.5' - 1.0' | 9/9/2025 | 1.4 | 294 |
| DP-34, 0.5' - 1.0' | 9/9/2025 | 2.5 | 331 |
| DP-35, 0.5' - 1.0' | 9/9/2025 | 1.3 | 265 |
| DP-36, 1.0' - 1.5' | 9/9/2025 | 0.5 | 161 |
| DP-37, 1.0' - 1.5' | 9/10/2025 | 1.1 | 252 |
| DP-38, 0.5' - 1.0' | 9/10/2025 | 3.4 | 381 |
| DP-39, 1.5' - 2.0' | 9/10/2025 | 0.5 | 191 |
| DP-41, 3.5' - 4.0' | 9/24/2025 | 17.2 | 1424 |
| DP-44, 1.0' - 1.5' | 9/22/2025 | 1.0 | 261 |
| DP-46, 0.5' - 1.0' | 9/24/2025 | 1.0 | 280 |
| DP-48, 0.5' - 1.0' | 9/24/2025 | 2.4 | 297 |
| 6.6 pCi/g Ra-226 Ref Sc | 9/30/2024 | 6.6 | 520 |
| 25 pCi/g Ra-226 Ref So | 9/30/2024 | 25.0 | 1954 |
| 50 pCi/g Ra-226 Ref So | 9/30/2024 | 50.0 | 3677 |




SUMMARY OUTPUT

| *Regression Statistics* | |
|---|---|
| Multiple R | 0.9976221 |
| R Square | 0.9952499 |
| Adjusted R Square | 0.9951341 |
| Standard Error | 0.6364145 |
| Observations | 43 |

ANOVA

| | *df* | *SS* | *MS* | *F* | *Significance F* |
|---|---|---|---|---|---|
| Regression | 1 | 3479.338226 | 3479.33823 | 8590.462141 | 2.92567E-49 |
| Residual | 41 | 16.6059596 | 0.4050234 | | |
| Total | 42 | 3495.944186 | | | |

| | *Coefficients* | *Standard Error* | *t Stat* | *P-value* | *Lower 95%* | *Upper 95%* | *Lower 95.0%* | *Upper 95.0%* |
|---|---|---|---|---|---|---|---|---|
| Intercept | -2.5525215 | 0.122081531 | -20.9083349 | 1.74691E-23 | -2.799070188 | -2.30597288 | -2.79907019 | -2.305972882 |
| X Variable 1 | 0.0144078 | 0.00015545 | 92.684746 | 2.92567E-49 | 0.014093875 | 0.01472175 | 0.01409387 | 0.014721748 |

**AVM Environmental Services, Inc.**
**Micro R Meter Function Check Form**

Micro R Meter: Ludlum 19, SR#76248

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Function Check @ Calibration 135

Acceptable Function Check Reading (uR/hr) Range (20%) 108 to 162

| Date | Physical Check | Cal Date | Battery[1] Volts or OK | BKG Reading uR/hr | Source Reading[2] uR/hr | Within Acceptable Range Y or N | Cal Due | Tech |
|---|---|---|---|---|---|---|---|---|
| 3-6-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 3-11-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 3-12-25 | ✓ | 10-4-24 | ok | 8-10 | 135 | y | 10-4-25 | VP |
| 3-17-25 | ✓ | 10-4-24 | ok | 10-12 | 140 | y | 10-4-25 | VP |
| 3-25-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 3-26-25 | ✓ | 10-4-24 | ok | 10-12 | 135 | y | 10-4-25 | VP |
| 3-31-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 4-7-25 | ✓ | 10-4-24 | ok | 10-12 | 135 | y | 10-4-25 | VP |
| 4-8-25 | ✓ | 10-4-24 | ok | 8-10 | 135 | y | 10-4-25 | VP |
| 4-9-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 4-10-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 4-15-25 | ✓ | 10-4-24 | ok | 10-12 | 130 | y | 10-4-25 | VP |
| 4-16-25 | ✓ | 10-4-24 | ok | 8-10 | 135 | y | 10-4-25 | VP |
| 4-21-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |
| 4-22-25 | ✓ | 10-4-24 | ok | 8-10 | 135 | y | 10-4-25 | VP |
| 4-23-25 | ✓ | 10-4-24 | ok | 8-10 | 130 | y | 10-4-25 | VP |
| 4-29-25 | ✓ | 10-4-24 | ok | 10-12 | 135 | y | 10-4-25 | VP |
| 4-30-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | y | 10-4-25 | VP |

Note: (1) Battery Voltage must be within BAT TEST Range (2) Function Check Source must be placed in the circle on the front side of the meter

**AVM Environmental Services, Inc.**
**Micro R Meter Function Check Form**

Micro R Meter: Ludlum 19, SR#76248

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Function Check @ Calibration 135

Acceptable Function Check Reading (uR/hr) Range (20%) 108 to 162

| Date | Physical Check | Cal Date | Battery[1] Volts or OK | BKG Reading uR/hr | Source Reading[2] uR/hr | Within Acceptable Range Y or N | Cal Due | Tech |
|---|---|---|---|---|---|---|---|---|
| 5-12-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | Y | 10-4-25 | VP |
| 5-13-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | Y | 10-4-25 | VP |
| 5-14-25 | ✓ | 10-4-24 | ok | 8-10 | 135 | Y | 10-4-25 | VP |
| 6-6-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | Y | 10-4-25 | VP |
| 6-19-25 | ✓ | 10-4-24 | ok | 8-10 | 135 | Y | 10-4-25 | VP |
| 6-30-25 | ✓ | 10-4-24 | ok | 8-12 | 130 | Y | 10-4-25 | VP |
| 7-28-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | Y | 10-4-25 | VP |
| 8-4-25 | ✓ | 10-4-24 | ok | 8-10 | 140 | Y | 10-4-25 | VP |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

Note: (1) Battery Voltage must be within BAT TEST Range (2) Function Check Source must be placed in the circle on the front side of the meter

**AVM Environmental Services, Inc.**
**Micro R Meter Function Check Form**

Micro R Meter: Ludlum 19, SR#76248

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Function Check @ Calibration 140

Acceptable Function Check Reading (uR/hr) Range (20%) 112 to 168

| Date | Physical Check | Cal Date | Battery(1) Volts or OK | BKG Reading uR/hr | Source Reading (2) uR/hr | Within Acceptable Range Y or N | Cal Due | Tech |
|---|---|---|---|---|---|---|---|---|
| 8-20-25 | ✓ | 8-20-25 | ok | 10-12 | 140 | Y | 8-20-26 | VP |
| 8-28-25 | ✓ | 8-20-25 | ok | 10-12 | 135 | Y | 8-20-26 | VP |
| 9-4-25 | ✓ | 8-20-25 | ok | 10-12 | 140 | Y | 8-20-26 | VP |
| 9-8-25 | ✓ | 8-20-25 | ok | 10-12 | 135 | Y | 8-20-26 | VP |
| 9-9-25 | ✓ | 8-20-25 | ok | 10-12 | 140 | Y | 8-20-26 | VP |
| 9-10-25 | ✓ | 8-20-25 | ok | 8-10 | 135 | Y | 8-20-26 | VP |
| 9-11-25 | ✓ | 8-20-25 | ok | 10-12 | 135 | Y | 8-20-26 | VP |
| 9-15-25 | ✓ | 8-20-25 | ok | 8-10 | 135 | Y | 8-20-26 | VP |
| 9-16-25 | ✓ | 8-20-25 | ok | 8-10 | 135 | Y | 8-20-26 | VP |
| 9-18-25 | ✓ | 8-20-25 | ok | 8-10 | 135 | Y | 8-20-26 | VP |
| 9-22-25 | ✓ | 8-20-25 | ok | 8-10 | 140 | Y | 8-20-26 | VP |
| 9-24-25 | ✓ | 8-20-25 | ok | 8-10 | 135 | Y | 8-20-26 | VP |
| 9-25-25 | ✓ | 8-20-25 | ok | 8-10 | 135 | Y | 8-20-26 | MM |
| 11-5-25 | ✓ | 8-20-25 | ok | 8-10 | 140 | Y | 8-20-26 | VP |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

**Note: (1) Battery Voltage must be within BAT TEST Range (2) Function Check Source must be placed in the circle on the front side of the meter**

**AVM Environmental Services, Inc.**
**Scaler/Ratemeter - 2" x 2" NaI Detector Function Check**

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

2" x 2" NaI Detector ID: SPA-3 S#408522-30

Acceptable background Count (cpm) Range (20%) 6055 to 9083 (Bare)

Acceptable background Count (cpm) Range (20%) 2150 to 3226 (collimated)

Acceptable Source Count (cpm) Range (20%) 78112 to 117168

| Date | Scaler/Ratemeter | Physical Check | Cal Due | Battery[1] Volts or OK | HV Volts | THR mV[2] | Window In or OUT[3] | C.C.[4] | BKG Counts cpm | Source Counrts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2-17-25 | L3003 S# 25036838 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7530 Bare / 2790 Coll | 97800 | y | – | VP |
| 2-19-25 | L3003 S# 25036838 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7490 Bare / 2550 Coll | 99800 | y | – | VP |
| 2-20-25 | L3003 S#25036838 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7540 Bare / 2590 Coll | 100000 | y | – | VP |
| 2-26-25 | L3003 S#25036838 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7640 Bare / 2610 Coll | 99900 | y | – | VP |
| 3-11-25 | L3003 S#25036830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7510 Bare / 2620 Coll | 99900 | y | – | VP |
| 3-12-25 | L3003 S#25036830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7430 Bare / 2600 Coll | 99300 | y | – | VP |
| 3-31-25 | L3003 S#25036830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7540 Bare / 2790 Coll | 99100 | y | – | VP |
| 5-19-25 | L3003 S#25036830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7520 Bare / 2690 Coll | 98400 | y | – | VP |
| 5-21-25 | L3003 S#25036830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7640 Bare / 2710 Coll | 99820 | y | – | VP |
| 5-22-25 | L3003 S#25036830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7620 Bare / 2570 Coll | 98770 | y | – | VP |
| 5-28-25 | L3003 S#25036830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7520 Bare / 2800 Coll | 97660 | y | – | VP |
| 5-29-25 | L3003 S#25036830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7510 Bare / 2670 Coll | 98200 | y | – | VP |
| 6-9-25 | L3003 S#25036830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7720 Bare / 2810 Coll | 97700 | y | – | VP |
| 6-10-25 | L3003 S#25036830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7600 Bare / 2720 Coll | 97600 | y | – | VP |
| 6-11-25 | L3003 S#25036830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7590 Bare / 2770 Coll | 98100 | y | – | VP |
| 6-19-25 | L3003 S#25036830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7600 Bare / 2800 Coll | 98110 | y | – | VP |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 10.0 mV; (3) Window Position must be OUT; (4) CC on L2241-2 set at 0.001
For L2241-2 Check HV and Threshold using Ludlum 500 pulser.

**AVM Environmental Services, Inc.**
**Scaler/Ratemeter - 2" x 2" NaI Detector Function Check**

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

2" x 2" NaI Detector ID: SPA-3 S# 408522-30

Acceptable background Count (cpm) Range (20%) 6055 to 9083 (Bare)

Acceptable background Count (cpm) Range (20%) 2150 to 3226 (collimated)

Acceptable Source Count (cpm) Range (20%) 78112 to 117168

| Date | Scaler/Ratemeter | Physical Check | Cal Due | Battery[1] Volts or OK | HV Volts | THR mV[2] | Window In or OUT[3] | C.C.[4] | BKG Counts cpm | Source Counrts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7-7-25 | L3003 S#250 36830 | ✓ | 2-17-26 | OK | 900 | 10 | out | 1 | 7620 Bare / 2827 Coll. | 98040 | ✓ | — | VP |
| 7-8-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7560 Bare / 2490 Coll. | 99900 | ✓ | — | VP |
| 8-20-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7590 Bare / 2620 Coll. | 98700 | ✓ | — | VP |
| 8-21-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7610 Bare / 2700 Coll. | 99200 | ✓ | — | VP |
| 9-2-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7980 Bare / 2800 Coll. | 98800 | ✓ | — | VP |
| 9-3-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7600 Bare / 2820 Coll. | 99600 | ✓ | — | VP |
| 9-8-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7710 Bare / 2900 Coll. | 98600 | ✓ | — | VP |
| 9-9-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7640 Bare / 2830 Coll. | 98900 | ✓ | — | VP |
| 9-10-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7620 Bare / 2840 Coll. | 98100 | ✓ | — | VP |
| 9-11-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7660 Bare / 2780 Coll. | 98100 | ✓ | — | VP |
| 9-15-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7420 Bare / 2550 Coll. | 97000 | ✓ | — | VP |
| 9-16-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7520 Bare / 2600 Coll. | 97200 | ✓ | — | VP |
| 9-18-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7480 Bare / 2610 Coll. | 98100 | ✓ | — | VP |
| 9-22-25 | L3003 S#250 36830 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7430 Bare / 2540 Coll. | 97800 | ✓ | — | VP |
| 9-24-25 | L3003 S#250 36830 | ✓ | 2-17-26 | OK | 900 | 10 | out | 1 | 7570 Bare / 2580 Coll. | 98400 | ✓ | — | MM |
| | | | | | | | | | Bare / Coll. | | | | |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 10.0 mV; (3) Window Position must be OUT; (4) CC on L2241-2 set at 0.001
For L2241-2 Check HV and Threshold using Ludlum 500 pulser.

**AVM Environmental Services, Inc.**
**Scaler/Ratemeter - 2" x 2" NaI Detector Function Check**

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

2" x 2" NaI Detector ID: SPA-3 #30

Acceptable background Count (cpm) Range (20%) 6524 to 9786 (Bare)

Acceptable background Count (cpm) Range (20%) 2537 to 3805 (collimated)

Acceptable Source Count (cpm) Range (20%) 77104 to 115656

| Date | Scaler/Ratemeter | Physical Check | Cal Due | Battery[1] Volts or OK | HV Volts | THR mV[2] | Window In or OUT[3] | C.C.[4] | BKG Counts cpm | Source Counrts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2-19-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8341 Bare / 3130 Coll. | 97899 | Y | — | VP |
| 3-31-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8216 Bare / 3224 Coll. | 98878 | Y | — | VP |
| 4-7-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8354 Bare / 3127 Coll. | 96885 | Y | — | VP |
| 4-8-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8169 Bare / 3341 Coll. | 97946 | Y | — | VP |
| 4-9-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8238 Bare / 3235 Coll. | 99787 | Y | — | VP |
| 4-10-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8411 Bare / 3187 Coll. | 98777 | Y | — | VP |
| 4-16-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8362 Bare / 3320 Coll. | 98641 | Y | — | VP |
| 4-21-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8308 Bare / 3162 Coll. | 97443 | Y | — | VP |
| 4-22-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8314 Bare / 3310 Coll. | 98790 | Y | — | VP |
| 4-28-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8398 Bare / 3200 Coll. | 97314 | Y | — | VP |
| 4-29-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8501 Bare / 3029 Coll. | 96776 | Y | — | VP |
| 4-30-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8328 Bare / 3209 Coll. | 97640 | Y | — | VP |
| 5-12-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8364 Bare / 3280 Coll. | 97871 | Y | — | VP |
| 5-14-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8153 Bare / 3116 Coll. | 97658 | Y | — | VP |
| 5-15-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8607 Bare / 3152 Coll. | 97508 | Y | — | VP |
| 6-26-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8514 Bare / 8514 Coll. | 98064 | Y | — | VP |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 10.0 mV; (3) Window Position must be OUT; (4) CC on L2241-2 set at 0.001
For L2241-2 Check HV and Threshold using Ludlum 500 pulser.

**AVM Environmental Services, Inc.**
**Scaler/Ratemeter - 2" x 2" NaI Detector Function Check**

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

2" x 2" NaI Detector ID: SPA-3 #30

Acceptable background Count (cpm) Range (20%) 6524 to 9786 (Bare)

Acceptable background Count (cpm) Range (20%) 2537 to 3805 (collimated)

Acceptable Source Count (cpm) Range (20%) 77104 to 115656

| Date | Scaler/Ratemeter | Physical Check | Cal Due | Battery[1] Volts or OK | HV Volts | THR mV[2] | Window In or OUT[3] | C.C.[4] | BKG Counts cpm | Source Counrts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 7-2-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8332 Bare / 3108 Coll. | 98181 | y | — | VP |
| 7-3-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8314 Bare / 3310 Coll. | 97889 | y | — | VP |
| 7-9-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8050 Bare / 3100 Coll. | 98834 | y | — | VP |
| 7-10-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8199 Bare / 3183 Coll. | 99832 | y | — | VP |
| 7-23-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 7923 Bare / 3283 Coll. | 99471 | y | — | VP |
| 7-24-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8377 Bare / 3147 Coll. | 98693 | y | — | VP |
| 7-28-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8064 Bare / 3308 Coll. | 98408 | y | — | VP |
| 8-4-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8348 Bare / 3217 Coll. | 98705 | y | — | VP |
| 8-5-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8098 Bare / 3110 Coll. | 98089 | y | — | VP |
| 8-6-25 | L2221 S#290801 | ✓ | 2-17-26 | ok | 900 | 10 | out | 1 | 8278 Bare / 3293 Coll. | 97138 | y | — | VP |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |
| | | | | | | | | | Bare / Coll. | | | | |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 10.0 mV; (3) Window Position must be OUT; (4) CC on L2241-2 set at 0.001
For L2241-2 Check HV and Threshold using Ludlum 500 pulser.

**AVM Environmental Services, Inc.**
**Ludlum SCA L2221 - 44-20 3x3 NaI Detector Function Check**
**559 - 659 KeV Gamma Radiation Soil Screening**

L2221 #68782

Ludlum 44-20 3x3 NaI Detector, #PR295573

Function Check Source ID: 1% $U_3O_8$ Ore in Sealed can

Acceptable background Count (cpm) Range (20%) 50 to 76

Acceptable Source Count (cpm) Range (20%) 12525 to 18787

| Date | Physical Check | Cal Date | Battery[1] Volts or OK | HV Volts | Threshhold mV [2] | Window mV | Window In/Out | BKG Counts cpm | Source Counrts cpm | Within Acceptable Range Y or N | MDC pCi/gm | Tech |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 9-30-24 | ✓ | 9-30-24 | ok | 575 | 559 | 10 | in | 63 | 15656 | Y | — | VP |
| 8-2-25 | ✓ | 9-30-24 | ok | 577 | 559 | 10 | in | 70 | 15704 | Y | — | VP |
| 9-3-25 | ✓ | 9-30-24 | ok | 585 | 559 | 10 | in | 68 | 15677 | Y | — | VP |
| 9-8-25 | ✓ | 9-30-24 | ok | 585 | 559 | 10 | in | 65 | 15922 | Y | — | VP |
| 9-9-25 | ✓ | 9-30-24 | ok | 575 | 559 | 10 | in | 64 | 15611 | Y | — | VP |
| 9-10-25 | ✓ | 9-30-24 | ok | 577 | 559 | 10 | in | 66 | 15701 | Y | — | VP |
| 9-15-25 | ✓ | 9-30-24 | ok | 578 | 559 | 10 | in | 72 | 15616 | Y | — | VP |
| 9-16-25 | ✓ | 9-30-24 | ok | 579 | 559 | 10 | in | 56 | 15785 | Y | — | VP |
| 9-24-25 | ✓ | 9-30-24 | ok | 581 | 559 | 10 | in | 57 | 15764 | Y | — | VP |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |
| | | | | | | | | | | | | |

Note: (1) Battery Voltage for Ludlum 2221 must be >5.3 volts; (2) Threshhold must be at 10 mV; (3) Window must be IN

**Appendix C**
**Soil Sample COC and Laboratory Analytical Results Report**

# ANALYTICAL SUMMARY REPORT

October 16, 2025

Rio Grande Resources Corporation
PO Box 1150
Grants, NM 87020-1150

Work Order: C25090418 Quote ID: C17937

Project Name: MTM SCA Characterization

Energy Laboratories, Inc. Casper WY received the following 14 samples for Rio Grande Resources Corporation on 9/10/2025 for analysis.

| Lab ID | Client Sample ID | Collect Date | Receive Date | Matrix | Test |
|---|---|---|---|---|---|
| C25090418-001 | DP-30 [4.5-6.0]Feet | 08/21/25 10:35 | 09/10/25 | Soil | Gamma Sample Preparation Drying/Grinding, Radiochemistry Gross Gamma |
| C25090418-002 | DP-31 [10-10.25]Feet | 08/21/25 12:45 | 09/10/25 | Soil | Same As Above |
| C25090418-003 | DP-FSS-05 | 09/02/25 8:30 | 09/10/25 | Soil | Same As Above |
| C25090418-004 | DP-FSS-21 | 09/02/25 10:00 | 09/10/25 | Soil | Same As Above |
| C25090418-005 | DP-FSS-46 | 09/02/25 11:30 | 09/10/25 | Soil | Same As Above |
| C25090418-006 | DP-FSS-DS1 | 09/02/25 12:30 | 09/10/25 | Soil | Same As Above |
| C25090418-007 | DP-28 [0.5-1.0]Feet | 09/03/25 7:50 | 09/10/25 | Soil | Same As Above |
| C25090418-008 | DP-27 [1.0-2.0]Feet | 09/03/25 8:40 | 09/10/25 | Soil | Same As Above |
| C25090418-009 | DP-21 [2.0-2.5]Feet | 09/03/25 9:40 | 09/10/25 | Soil | Same As Above |
| C25090418-010 | DP-19 [0.5-1.0]Feet | 09/03/25 10:20 | 09/10/25 | Soil | Same As Above |
| C25090418-011 | DP-22 [1.0-1.5]Feet | 09/03/25 11:00 | 09/10/25 | Soil | Same As Above |
| C25090418-012 | DP-23 [1.0-1.5]Feet | 09/03/25 12:30 | 09/10/25 | Soil | Same As Above |
| C25090418-013 | DP-24 [0.5-1.0]Feet | 09/03/25 13:00 | 09/10/25 | Soil | Same As Above |
| C25090418-014 | DP-DS1 [4.5-6.0]Feet | 08/21/25 13:30 | 09/10/25 | Soil | Same As Above |

The analyses presented in this report were performed by Energy Laboratories, Inc., 2393 Salt Creek Hwy, Casper, WY 82601-9601, unless otherwise noted. Any exceptions or problems with the analyses are noted in the report package. Any issues encountered during sample receipt are documented in the Work Order Receipt Checklist.

The results as reported relate only to the item(s) submitted for testing. This report shall be used or copied only in its entirety. Energy Laboratories, Inc. is not responsible for the consequences arising from the use of a partial report.

Energy Laboratories, Inc. verifies the reported results for the analysis has been technically reviewed and approved for release.

If you have any questions regarding these test results, please contact your Project Manager.

Digitally signed by
Lisa Bradley
Date: 2025.10.16 14:24:10 -06:00

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-001
**Client Sample ID:** DP-30 [4.5-6.0]

**Report Date:** 10/16/25
**Collection Date:** 08/21/25 10:35
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.8 | pCi/g-dry | U | | | E901.1M | 10/08/25 13:39 / haw |
| Radium 224 precision (±) | 2.8 | pCi/g-dry | | | | E901.1M | 10/08/25 13:39 / haw |
| Radium 224 MDC | 4.7 | pCi/g-dry | | | | E901.1M | 10/08/25 13:39 / haw |
| Radium 226 | 2.4 | pCi/g-dry | | | | E901.1M | 10/08/25 13:39 / haw |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/08/25 13:39 / haw |
| Radium 226 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/08/25 13:39 / haw |
| Radium 228 | 1.7 | pCi/g-dry | | | | E901.1M | 10/08/25 13:39 / haw |
| Radium 228 precision (±) | 0.5 | pCi/g-dry | | | | E901.1M | 10/08/25 13:39 / haw |
| Radium 228 MDC | 0.5 | pCi/g-dry | | | | E901.1M | 10/08/25 13:39 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-002
**Client Sample ID:** DP-31 [10-10.25]

**Report Date:** 10/16/25
**Collection Date:** 08/21/25 12:45
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 2.3 | pCi/g-dry | | | | E901.1M | 10/08/25 15:12 / haw |
| Radium 224 precision (±) | 1.3 | pCi/g-dry | | | | E901.1M | 10/08/25 15:12 / haw |
| Radium 224 MDC | 2.1 | pCi/g-dry | | | | E901.1M | 10/08/25 15:12 / haw |
| Radium 226 | 1.5 | pCi/g-dry | | | | E901.1M | 10/08/25 15:12 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/08/25 15:12 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/08/25 15:12 / haw |
| Radium 228 | 1.7 | pCi/g-dry | | | | E901.1M | 10/08/25 15:12 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 10/08/25 15:12 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 10/08/25 15:12 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-003
**Client Sample ID:** DP-FSS-05

**Report Date:** 10/16/25
**Collection Date:** 09/02/25 08:30
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.3 | pCi/g-dry | U | | | E901.1M | 10/08/25 17:41 / haw |
| Radium 224 precision (±) | 1.7 | pCi/g-dry | | | | E901.1M | 10/08/25 17:41 / haw |
| Radium 224 MDC | 2.9 | pCi/g-dry | | | | E901.1M | 10/08/25 17:41 / haw |
| Radium 226 | 1.2 | pCi/g-dry | | | | E901.1M | 10/08/25 17:41 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/08/25 17:41 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/08/25 17:41 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1M | 10/08/25 17:41 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/08/25 17:41 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/08/25 17:41 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-004
**Client Sample ID:** DP-FSS-21

**Report Date:** 10/16/25
**Collection Date:** 09/02/25 10:00
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 10/09/25 09:35 / haw |
| Radium 224 precision (±) | 1.7 | pCi/g-dry | | | | E901.1M | 10/09/25 09:35 / haw |
| Radium 224 MDC | 2.9 | pCi/g-dry | | | | E901.1M | 10/09/25 09:35 / haw |
| Radium 226 | 1.4 | pCi/g-dry | | | | E901.1M | 10/09/25 09:35 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/09/25 09:35 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/09/25 09:35 / haw |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1M | 10/09/25 09:35 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/09/25 09:35 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/09/25 09:35 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-005
**Client Sample ID:** DP-FSS-46

**Report Date:** 10/16/25
**Collection Date:** 09/02/25 11:30
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.2 | pCi/g-dry | U | | | E901.1M | 10/09/25 11:39 / haw |
| Radium 224 precision (±) | 1.8 | pCi/g-dry | | | | E901.1M | 10/09/25 11:39 / haw |
| Radium 224 MDC | 3.0 | pCi/g-dry | | | | E901.1M | 10/09/25 11:39 / haw |
| Radium 226 | 1 | pCi/g-dry | | | | E901.1M | 10/09/25 11:39 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/09/25 11:39 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/09/25 11:39 / haw |
| Radium 228 | 1.4 | pCi/g-dry | | | | E901.1M | 10/09/25 11:39 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/09/25 11:39 / haw |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/09/25 11:39 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-006
**Client Sample ID:** DP-FSS-DS1

**Report Date:** 10/16/25
**Collection Date:** 09/02/25 12:30
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 10/09/25 16:49 / haw |
| Radium 224 precision (±) | 1.7 | pCi/g-dry | | | | E901.1M | 10/09/25 16:49 / haw |
| Radium 224 MDC | 2.9 | pCi/g-dry | | | | E901.1M | 10/09/25 16:49 / haw |
| Radium 226 | 1.2 | pCi/g-dry | | | | E901.1M | 10/09/25 16:49 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/09/25 16:49 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/09/25 16:49 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 10/09/25 16:49 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/09/25 16:49 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/09/25 16:49 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-007
**Client Sample ID:** DP-28 [0.5-1.0]

**Report Date:** 10/16/25
**Collection Date:** 09/03/25 07:50
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.4 | pCi/g-dry | U | | | E901.1M | 10/13/25 10:05 / haw |
| Radium 224 precision (±) | 1.6 | pCi/g-dry | | | | E901.1M | 10/13/25 10:05 / haw |
| Radium 224 MDC | 2.7 | pCi/g-dry | | | | E901.1M | 10/13/25 10:05 / haw |
| Radium 226 | 1.0 | pCi/g-dry | | | | E901.1M | 10/13/25 10:05 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/13/25 10:05 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/13/25 10:05 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1M | 10/13/25 10:05 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/13/25 10:05 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/13/25 10:05 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-008
**Client Sample ID:** DP-27 [1.0-2.0]

**Report Date:** 10/16/25
**Collection Date:** 09/03/25 08:40
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.09 | pCi/g-dry | U | | | E901.1M | 10/13/25 12:28 / haw |
| Radium 224 precision (±) | 1.7 | pCi/g-dry | | | | E901.1M | 10/13/25 12:28 / haw |
| Radium 224 MDC | 2.8 | pCi/g-dry | | | | E901.1M | 10/13/25 12:28 / haw |
| Radium 226 | 1.1 | pCi/g-dry | | | | E901.1M | 10/13/25 12:28 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/13/25 12:28 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/13/25 12:28 / haw |
| Radium 228 | 1.4 | pCi/g-dry | | | | E901.1M | 10/13/25 12:28 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/13/25 12:28 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/13/25 12:28 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-009
**Client Sample ID:** DP-21 [2.0-2.5]

**Report Date:** 10/16/25
**Collection Date:** 09/03/25 09:40
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 2.1 | pCi/g-dry | | | | E901.1M | 10/13/25 14:29 / haw |
| Radium 224 precision (±) | 1.1 | pCi/g-dry | | | | E901.1M | 10/13/25 14:29 / haw |
| Radium 224 MDC | 1.7 | pCi/g-dry | | | | E901.1M | 10/13/25 14:29 / haw |
| Radium 226 | 1.1 | pCi/g-dry | | | | E901.1M | 10/13/25 14:29 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/13/25 14:29 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/13/25 14:29 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 10/13/25 14:29 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/13/25 14:29 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 10/13/25 14:29 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-010
**Client Sample ID:** DP-19 [0.5-1.0]

**Report Date:** 10/16/25
**Collection Date:** 09/03/25 10:20
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 10/13/25 16:31 / haw |
| Radium 224 precision (±) | 1.8 | pCi/g-dry | | | | E901.1M | 10/13/25 16:31 / haw |
| Radium 224 MDC | 2.9 | pCi/g-dry | | | | E901.1M | 10/13/25 16:31 / haw |
| Radium 226 | 1.2 | pCi/g-dry | | | | E901.1M | 10/13/25 16:31 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/13/25 16:31 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/13/25 16:31 / haw |
| Radium 228 | 1.4 | pCi/g-dry | | | | E901.1M | 10/13/25 16:31 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/13/25 16:31 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/13/25 16:31 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-011
**Client Sample ID:** DP-22 [1.0-1.5]

**Report Date:** 10/16/25
**Collection Date:** 09/03/25 11:00
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 10/13/25 18:44 / haw |
| Radium 224 precision (±) | 2.1 | pCi/g-dry | | | | E901.1M | 10/13/25 18:44 / haw |
| Radium 224 MDC | 3.4 | pCi/g-dry | | | | E901.1M | 10/13/25 18:44 / haw |
| Radium 226 | 1.2 | pCi/g-dry | | | | E901.1M | 10/13/25 18:44 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/13/25 18:44 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/13/25 18:44 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 10/13/25 18:44 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/13/25 18:44 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/13/25 18:44 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-012
**Client Sample ID:** DP-23 [1.0-1.5]

**Report Date:** 10/16/25
**Collection Date:** 09/03/25 12:30
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 10/14/25 09:31 / haw |
| Radium 224 precision (±) | 2.0 | pCi/g-dry | | | | E901.1M | 10/14/25 09:31 / haw |
| Radium 224 MDC | 3.4 | pCi/g-dry | | | | E901.1M | 10/14/25 09:31 / haw |
| Radium 226 | 1.9 | pCi/g-dry | | | | E901.1M | 10/14/25 09:31 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/14/25 09:31 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/14/25 09:31 / haw |
| Radium 228 | 1.6 | pCi/g-dry | | | | E901.1M | 10/14/25 09:31 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/14/25 09:31 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/14/25 09:31 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-013
**Client Sample ID:** DP-24 [0.5-1.0]

**Report Date:** 10/16/25
**Collection Date:** 09/03/25 13:00
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 10/14/25 11:41 / haw |
| Radium 224 precision (±) | 1.8 | pCi/g-dry | | | | E901.1M | 10/14/25 11:41 / haw |
| Radium 224 MDC | 3.0 | pCi/g-dry | | | | E901.1M | 10/14/25 11:41 / haw |
| Radium 226 | 1.1 | pCi/g-dry | | | | E901.1M | 10/14/25 11:41 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/14/25 11:41 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/14/25 11:41 / haw |
| Radium 228 | 1.6 | pCi/g-dry | | | | E901.1M | 10/14/25 11:41 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/14/25 11:41 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/14/25 11:41 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090418-014
**Client Sample ID:** DP-DS1 [4.5-6.0]

**Report Date:** 10/16/25
**Collection Date:** 08/21/25 13:30
**DateReceived:** 09/10/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.03 | pCi/g-dry | U | | | E901.1M | 10/14/25 13:42 / haw |
| Radium 224 precision (±) | 1.9 | pCi/g-dry | | | | E901.1M | 10/14/25 13:42 / haw |
| Radium 224 MDC | 3.1 | pCi/g-dry | | | | E901.1M | 10/14/25 13:42 / haw |
| Radium 226 | 2.4 | pCi/g-dry | | | | E901.1M | 10/14/25 13:42 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/14/25 13:42 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/14/25 13:42 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1M | 10/14/25 13:42 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/14/25 13:42 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/14/25 13:42 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Work Order:** C25090418 **Report Date:** 10/15/25

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E901.1M** | | | | | | | | | | Batch: R321434 |
| **Lab ID: MB-321434** | 9 | Method Blank | | | | Run: GAM-HPGE 2_251006A | | | | 10/06/25 12:41 |
| Radium 224 | | 0.3 | pCi/g-dry | | | | | | | U |
| Radium 224 precision (±) | | 0.6 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 1 | pCi/g-dry | | | | | | | |
| Radium 226 | | 0.2 | pCi/g-dry | | | | | | | |
| Radium 226 precision (±) | | 0.09 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.1 | pCi/g-dry | | | | | | | |
| Radium 228 | | 0.1 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.1 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.2 | pCi/g-dry | | | | | | | |
| **Lab ID: LCS-321434** | 6 | Laboratory Control Sample | | | | Run: GAM-HPGE 2_251006A | | | | 10/06/25 15:06 |
| Cobalt 60 | | 340 | pCi/g-dry | | 106 | 70 | 130 | | | |
| Cobalt 60 precision (±) | | 2.0 | pCi/g-dry | | | | | | | |
| Cobalt 60 MDC | | 0.76 | pCi/g-dry | | | | | | | |
| Lead 210 | | 1800 | pCi/g-dry | | 102 | 70 | 130 | | | |
| Lead 210 precision (±) | | 14 | pCi/g-dry | | | | | | | |
| Lead 210 MDC | | 12 | pCi/g-dry | | | | | | | |
| **Lab ID: C25090418-005ADUP** | 9 | Sample Duplicate | | | | Run: GAM-HPGE 2_251006A | | | | 10/09/25 13:57 |
| Radium 224 | | -0.50 | pCi/g-dry | | | | | 99 | 30 | UR |
| Radium 224 precision (±) | | 1.8 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 3.0 | pCi/g-dry | | | | | | | |
| Radium 226 | | 0.88 | pCi/g-dry | | | | | 7.2 | 30 | |
| Radium 226 precision (±) | | 0.16 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.17 | pCi/g-dry | | | | | | | |
| Radium 228 | | 1.2 | pCi/g-dry | | | | | 15 | 30 | |
| Radium 228 precision (±) | | 0.29 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.32 | pCi/g-dry | | | | | | | |

- Duplicate RPD for Ra224 is outside of the acceptance range for this analysis. However, the RER is less than or equal to the limit of 3. The RER result is 0.13.
-The RER result for Ra226 is 0.30 and Ra228 is 0.51.

**Qualifiers:**

RL - Analyte Reporting Limit
ND - Not detected at the Reporting Limit (RL)
R - Relative Percent Difference (RPD) exceeds advisory limit
U - Not detected

# Work Order Receipt Checklist

## Rio Grande Resources Corporation C25090418

Login completed by: Lisa X. Quezada
Date Received: 9/10/2025
Reviewed by: srichins
Received by: SLR
Reviewed Date: 9/19/2025
Carrier name: Return UPS Ground

| | | | |
|---|---|---|---|
| Shipping container/cooler in good condition? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on all shipping container(s)/cooler(s)? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on all sample bottles? | Yes ☐ | No ☐ | Not Present ☑ |
| Chain of custody present? | Yes ☑ | No ☐ | |
| Chain of custody signed when relinquished and received? | Yes ☑ | No ☐ | |
| Chain of custody agrees with sample labels? | Yes ☑ | No ☐ | |
| Samples in proper container/bottle? | Yes ☑ | No ☐ | |
| Sample containers intact? | Yes ☑ | No ☐ | |
| Sufficient sample volume for indicated test? | Yes ☑ | No ☐ | |
| All samples received within holding time? (Exclude analyses that are considered field parameters such as pH, DO, Res Cl, Sulfite, Ferrous Iron, etc.) | Yes ☑ | No ☐ | |
| Temp Blank received in all shipping container(s)/cooler(s)? | Yes ☐ | No ☑ | Not Applicable ☐ |
| Container/Temp Blank temperature: | 21.8°C No Ice | | |
| Containers requiring zero headspace have no headspace or bubble that is <6mm (1/4"). | Yes ☐ | No ☐ | No VOA vials submitted ☑ |
| Water - pH acceptable upon receipt? | Yes ☐ | No ☐ | Not Applicable ☑ |

### Standard Reporting Procedures:

Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH, Dissolved Oxygen and Residual Chlorine, are qualified as being analyzed outside of recommended holding time.

Solid/soil samples are reported on a wet weight basis (as received) unless specifically indicated. If moisture corrected, data units are typically noted as –dry. For agricultural and mining soil parameters/characteristics, all samples are dried and ground prior to sample analysis.

The reference date for Radon analysis is the sample collection date. The reference date for all other Radiochemical analyses is the analysis date. Radiochemical precision results represent a 2-sigma Total Measurement Uncertainty.

For methods that require zero headspace or require preservation check at the time of analysis due to potential interference, the pH is verified at analysis. Nonconforming sample pH is documented as part of the analysis and included in the sample analysis comments.

Trip Blanks and/or Blind Duplicate samples are assigned the earliest collection time for the associated requested analysis in order to evaluate the holding time unless specifically indicated.

### Contact and Corrective Action Comments:

None

## *Laboratory Certifications and Accreditations*

Current certificates are available at [www.energylab.com](http://www.energylab.com) website:

| | Agency | Number |
|---|---|---|
| ***Billings, MT*** | Alaska | 17-023 |
| | California | 3087 |
| | Colorado | MT00005 |
| | Department of Defense (DoD)/ISO17025 | ADE-2588 |
| | Florida (Primary NELAP) | E87668 |
| | Idaho | MT00005 |
| | Louisiana | 05079 |
| | Montana | CERT0044 |
| | Nebraska | NE-OS-13-04 |
| | Nevada | NV-C24-00250 |
| | North Dakota | R-007 |
| | National Radon Proficiency | 109383-RMP |
| | Oregon | 4184 |
| | South Dakota | ARSD 74:04:07 |
| | Texas | TX-C24-00302 |
| | US EPA Region VIII | Reciprocal |
| | USDA Soil Permit | P330-20-00170 |
| | Washington | C1039 |
| ***Casper, WY*** | Alaska | 20-006 |
| | California | 3021 |
| | Colorado | WY00002 |
| | Florida (Primary NELAP) | E87641 |
| | Idaho | WY00002 |
| | Louisiana | 05083 |
| | Montana | CERT0002 |
| | Nebraska | NE-OS-08-04 |
| | Nevada | NV-C24-00245 |
| | North Dakota | R-125 |
| | Oregon | WY200001 |
| | South Dakota | WY00002 |
| | Texas | T104704181-23-21 |
| | US EPA Region VIII | WY00002 |
| | USNRC License | 49-26846-01 |
| | Washington | C1012 |
| ***Gillette, WY*** | US EPA Region VIII | WY00006 |
| ***Helena, MT*** | Colorado | MT00945 |
| | Montana | CERT0079 |
| | Nevada | NV-C24-00119 |
| | US EPA Region VIII | Reciprocal |
| | USDA Soil Permit | P330-20-00090 |

# Chain of Custody & Analytical Request Record

ENERGY LABORATORIES — Trust our People. Trust our Data.

www.energylab.com



**Account Information** *(Billing information)*

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☒Email |
| Purchase Order | MT11820 |
| Quote | |
| Bottle Order | |

**Report Information** *(if different than Account Information)*

| | |
|---|---|
| Company/Name | AVM Environmental Services, Inc. |
| Contact | Victor Patel |
| Phone | 505-287-4593 |
| Mailing Address | 1717 Del Norte Blvd |
| City, State, Zip | Grants, NM 87020 |
| Email | vpatelavm@outlook.com |
| Receive Report | ☐Hard Copy ☒Email |

Special Report/Formats: ☐ LEVEL IV ☐NELAC ☐ EDD/EDT *(contact laboratory)* ☐ Other_____

**Comments**

**Project Information**

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM SCA Characterization |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-4593 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

**Analysis Requested**

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for soil | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | DP-30 4.5'-6.0' | 08/21/2025 | 10:35 am | 1 | S | ✓ | | | C25090413 |
| 2 | DP-31 10'-10.25' | 08/21/2025 | 12:45 pm | 1 | S | ✓ | | | |
| 3 | DP-FSS-05 | 09/02/2025 | 8:30 am | 1 | S | ✓ | | | |
| 4 | DP-FSS-21 | 09/02/2025 | 10:00 am | 1 | S | ✓ | | | |
| 5 | DP-FSS-46 | 09/02/2025 | 11:30 am | 1 | S | ✓ | | | |
| 6 | DP-FSS-DS1 | 09/02/2025 | 12:30 pm | 1 | S | ✓ | | | |
| 7 | DP-28 0.5'-1.0' | 09/03/2025 | 7:50 am | 1 | S | ✓ | | | |
| 8 | DP-27 1.0'-2.0' | 09/03/2025 | 8:40 am | 1 | S | ✓ | | | |
| 9 | DP-21 2.0'-2.5' | 09/03/2025 | 9:40 am | 1 | S | ✓ | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were NOT used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Victor Patel | 9-8-25 @1330 | | | 1010 | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Shelby Richins | 09/10/25 | |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

ELI-COC-01/21 v.4

# Chain of Custody & Analytical Request Record

ENERGY LABORATORIES — Trust our People. Trust our Data.

www.energylab.com



**Account Information** *(Billing information)*

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☒Email |
| Purchase Order | MT11820 |
| Quote | |
| Bottle Order | |

**Report Information** *(if different than Account Information)*

| | |
|---|---|
| Company/Name | AVM Environmental Services, Inc. |
| Contact | Victor Patel |
| Phone | 505-287-4593 |
| Mailing Address | 1717 Del Norte Blvd |
| City, State, Zip | Grants, NM 87020 |
| Email | vpatelavm@outlook.com |
| Receive Report | ☐Hard Copy ☒Email |

Special Report/Formats: ☐ LEVEL IV ☐NELAC ☐ EDD/EDT *(contact laboratory)* ☐ Other_____

**Comments**

**Project Information**

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM SCA Characterization |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-4593 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/ Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

**Analysis Requested**

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for soil ✓ | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | DP-19 0.5'-1.0' | 09/03/2025 | 10:20 am | 1 | S | ✓ | | | C25090418 |
| 2 | DP-22 1.0'-1.5' | 09/03/2025 | 11:00 am | 1 | S | ✓ | | | |
| 3 | DP-23 1.0'-1.5' | 09/03/2025 | 12:30 pm | 1 | S | ✓ | | | |
| 4 | DP-24 0.5'-1.0' | 09/03/2025 | 1:00 pm | 1 | S | ✓ | | | |
| 5 | DP-DS1 4.5'-6.0' | 08/21/2025 | 1:30 pm | 1 | S | ✓ | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were **NOT** used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Victor Patel | 9-8-25 @1330 | | | 1010 | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Shelby Richins | 09/10/25 | |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

# ANALYTICAL SUMMARY REPORT

November 14, 2025

Rio Grande Resources Corporation
PO Box 1150
Grants, NM 87020-1150

Work Order: C25090966 Quote ID: C17937

Project Name: MTM SCA Characterization

Energy Laboratories, Inc. Casper WY received the following 35 samples for Rio Grande Resources Corporation on 9/29/2025 for analysis.

| Lab ID | Client Sample ID | Collect Date | Receive Date | Matrix | Test |
|---|---|---|---|---|---|
| C25090966-001 | DP-20 [0.5-1.0]Feet | 09/08/25 09:00 | 09/29/25 | Soil | Gamma Sample Preparation Drying/Grinding, Radiochemistry Gross Gamma |
| C25090966-002 | DP-25 [0.5-1.0]Feet | 09/08/25 09:40 | 09/29/25 | Soil | Same As Above |
| C25090966-003 | DP-26 [2.0-2.5]Feet | 09/08/25 10:40 | 09/29/25 | Soil | Same As Above |
| C25090966-004 | DP-34 [0.5-1.0]Feet | 09/09/25 10:50 | 09/29/25 | Soil | Same As Above |
| C25090966-005 | DP-35 [0.5-1.0]Feet | 09/09/25 11:40 | 09/29/25 | Soil | Same As Above |
| C25090966-006 | DP-33 [0.5-1.0]Feet | 09/09/25 12:50 | 09/29/25 | Soil | Same As Above |
| C25090966-007 | DP-36 [1.0-1.5]Feet | 09/09/25 13:30 | 09/29/25 | Soil | Same As Above |
| C25090966-008 | DP-37 [1.0-1.5]Feet | 09/10/25 08:45 | 09/29/25 | Soil | Same As Above |
| C25090966-009 | DP-38 [0.5-1.0]Feet | 09/10/25 09:10 | 09/29/25 | Soil | Same As Above |
| C25090966-010 | DP-39 [1.5-2.0]Feet | 09/10/25 09:50 | 09/29/25 | Soil | Same As Above |
| C25090966-011 | DP-11 [0.5-1.0]Feet | 09/10/25 10:44 | 09/29/25 | Soil | Same As Above |
| C25090966-012 | DP-10 [1.0-1.5]Feet | 09/10/25 11:35 | 09/29/25 | Soil | Same As Above |
| C25090966-013 | DP-09 [1.0-1.5]Feet | 09/10/25 13:20 | 09/29/25 | Soil | Same As Above |
| C25090966-014 | DP-02 [0.0-0.5]Feet | 09/11/25 08:00 | 09/29/25 | Soil | Same As Above |
| C25090966-015 | DP-01 [0.0-0.5]Feet | 09/11/25 08:10 | 09/29/25 | Soil | Same As Above |
| C25090966-016 | DP-17 [0.0-0.5]Feet | 09/11/25 08:40 | 09/29/25 | Soil | Same As Above |
| C25090966-017 | DP-17 [0.5-1.0]Feet | 09/11/25 08:50 | 09/29/25 | Soil | Same As Above |
| C25090966-018 | DP-18 [0.5-1.0]Feet | 09/11/25 09:00 | 09/29/25 | Soil | Same As Above |
| C25090966-019 | DP-DS2 [0.0-0.5]Feet | 09/11/25 09:15 | 09/29/25 | Soil | Same As Above |
| C25090966-020 | DP-DS3 [0.0-0.5]Feet | 09/11/25 09:30 | 09/29/25 | Soil | Same As Above |
| C25090966-021 | DP-DS4 [0.0-0.5]Feet | 09/11/25 09:45 | 09/29/25 | Soil | Same As Above |
| C25090966-022 | DP-08 [0.5-1.0]Feet | 09/15/25 08:00 | 09/29/25 | Soil | Same As Above |
| C25090966-023 | DP-06 [1.5-2.0]Feet | 09/15/25 09:20 | 09/29/25 | Soil | Same As Above |
| C25090966-024 | DP-04 [1.0-1.5]Feet | 09/15/25 10:15 | 09/29/25 | Soil | Same As Above |
| C25090966-025 | DP-16 [0.5-1.0]Feet | 09/15/25 12:30 | 09/29/25 | Soil | Same As Above |
| C25090966-026 | DP-15 [0.5-1.0]Feet | 09/15/25 13:15 | 09/29/25 | Soil | Same As Above |

# ANALYTICAL SUMMARY REPORT

| | | | | | |
|---|---|---|---|---|---|
| C25090966-027 | DP-05 [0.5-1.0]Feet | 09/16/25 08:10 | 09/29/25 | Soil | Same As Above |
| C25090966-028 | DP-07 [3.0-3.5]Feet | 09/16/25 09:15 | 09/29/25 | Soil | Same As Above |
| C25090966-029 | DP-12 [0.5-1.0]Feet | 09/16/25 09:40 | 09/29/25 | Soil | Same As Above |
| C25090966-030 | DP-13 [0.5-1.0]Feet | 09/16/25 10:00 | 09/29/25 | Soil | Same As Above |
| C25090966-031 | DP-44 [1.0-1.5]Feet | 09/22/25 08:50 | 09/29/25 | Soil | Same As Above |
| C25090966-032 | DP-46 [0.5-1.0]Feet | 09/24/25 08:10 | 09/29/25 | Soil | Same As Above |
| C25090966-033 | DP-48 [0.5-1.0]Feet | 09/24/25 08:30 | 09/29/25 | Soil | Same As Above |
| C25090966-034 | DP-41 [3.5-4.0]Feet | 09/24/25 10:30 | 09/29/25 | Soil | Same As Above |
| C25090966-035 | DP-DS5 [0.5-1.0]Feet | 09/24/25 11:15 | 09/29/25 | Soil | Same As Above |

The analyses presented in this report were performed by Energy Laboratories, Inc., 2393 Salt Creek Hwy, Casper, WY 82601-9601, unless otherwise noted. Any exceptions or problems with the analyses are noted in the report package. Any issues encountered during sample receipt are documented in the Work Order Receipt Checklist.

The results as reported relate only to the item(s) submitted for testing. This report shall be used or copied only in its entirety. Energy Laboratories, Inc. is not responsible for the consequences arising from the use of a partial report.

Energy Laboratories, Inc. verifies the reported results for the analysis has been technically reviewed and approved for release.

If you have any questions regarding these test results, please contact your Project Manager.



Digitally signed by
Manford E. Hurley
Date: 2025.11.14 09:49:55 -07:00

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-001
**Client Sample ID:** DP-20 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/08/25 09:00
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.9 | pCi/g-dry | | | | E901.1M | 10/28/25 09:53 / haw |
| Radium 224 precision (±) | 1.1 | pCi/g-dry | | | | E901.1M | 10/28/25 09:53 / haw |
| Radium 224 MDC | 1.7 | pCi/g-dry | | | | E901.1M | 10/28/25 09:53 / haw |
| Radium 226 | 1 | pCi/g-dry | | | | E901.1M | 10/28/25 09:53 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/28/25 09:53 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/28/25 09:53 / haw |
| Radium 228 | 1.7 | pCi/g-dry | | | | E901.1M | 10/28/25 09:53 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/28/25 09:53 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/28/25 09:53 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-002
**Client Sample ID:** DP-25 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/08/25 09:40
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.6 | pCi/g-dry | U | | | E901.1M | 10/28/25 14:29 / haw |
| Radium 224 precision (±) | 1.8 | pCi/g-dry | | | | E901.1M | 10/28/25 14:29 / haw |
| Radium 224 MDC | 3.0 | pCi/g-dry | | | | E901.1M | 10/28/25 14:29 / haw |
| Radium 226 | 4.8 | pCi/g-dry | | | | E901.1M | 10/28/25 14:29 / haw |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/28/25 14:29 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/28/25 14:29 / haw |
| Radium 228 | 0.2 | pCi/g-dry | U | | | E901.1M | 10/28/25 14:29 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/28/25 14:29 / haw |
| Radium 228 MDC | 0.5 | pCi/g-dry | | | | E901.1M | 10/28/25 14:29 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-003
**Client Sample ID:** DP-26 [2.0-2.5]

**Report Date:** 11/14/25
**Collection Date:** 09/08/25 10:40
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.6 | pCi/g-dry | | | | E901.1M | 10/28/25 16:40 / haw |
| Radium 224 precision (±) | 0.9 | pCi/g-dry | | | | E901.1M | 10/28/25 16:40 / haw |
| Radium 224 MDC | 1.5 | pCi/g-dry | | | | E901.1M | 10/28/25 16:40 / haw |
| Radium 226 | 0.9 | pCi/g-dry | | | | E901.1M | 10/28/25 16:40 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/28/25 16:40 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/28/25 16:40 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1M | 10/28/25 16:40 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/28/25 16:40 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/28/25 16:40 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-004
**Client Sample ID:** DP-34 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/09/25 10:50
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.6 | pCi/g-dry | U | | | E901.1M | 10/28/25 18:54 / haw |
| Radium 224 precision (±) | 2.1 | pCi/g-dry | | | | E901.1M | 10/28/25 18:54 / haw |
| Radium 224 MDC | 3.5 | pCi/g-dry | | | | E901.1M | 10/28/25 18:54 / haw |
| Radium 226 | 2.5 | pCi/g-dry | | | | E901.1M | 10/28/25 18:54 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/28/25 18:54 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/28/25 18:54 / haw |
| Radium 228 | 1.9 | pCi/g-dry | | | | E901.1M | 10/28/25 18:54 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/28/25 18:54 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/28/25 18:54 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-005
**Client Sample ID:** DP-35 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/09/25 11:40
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 10/29/25 09:53 / haw |
| Radium 224 precision (±) | 1.9 | pCi/g-dry | | | | E901.1M | 10/29/25 09:53 / haw |
| Radium 224 MDC | 3.2 | pCi/g-dry | | | | E901.1M | 10/29/25 09:53 / haw |
| Radium 226 | 1.3 | pCi/g-dry | | | | E901.1M | 10/29/25 09:53 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/29/25 09:53 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/29/25 09:53 / haw |
| Radium 228 | 1.6 | pCi/g-dry | | | | E901.1M | 10/29/25 09:53 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/29/25 09:53 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/29/25 09:53 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-006
**Client Sample ID:** DP-33 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/09/25 12:50
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.3 | pCi/g-dry | U | | | E901.1M | 10/29/25 11:58 / haw |
| Radium 224 precision (±) | 1.8 | pCi/g-dry | | | | E901.1M | 10/29/25 11:58 / haw |
| Radium 224 MDC | 3.0 | pCi/g-dry | | | | E901.1M | 10/29/25 11:58 / haw |
| Radium 226 | 1.4 | pCi/g-dry | | | | E901.1M | 10/29/25 11:58 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/29/25 11:58 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/29/25 11:58 / haw |
| Radium 228 | 1.4 | pCi/g-dry | | | | E901.1M | 10/29/25 11:58 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/29/25 11:58 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/29/25 11:58 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-007
**Client Sample ID:** DP-36 [1.0-1.5]

**Report Date:** 11/14/25
**Collection Date:** 09/09/25 13:30
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.4 | pCi/g-dry | U | | | E901.1M | 10/29/25 14:10 / haw |
| Radium 224 precision (±) | 1.4 | pCi/g-dry | | | | E901.1M | 10/29/25 14:10 / haw |
| Radium 224 MDC | 2.4 | pCi/g-dry | | | | E901.1M | 10/29/25 14:10 / haw |
| Radium 226 | 0.5 | pCi/g-dry | | | | E901.1M | 10/29/25 14:10 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1M | 10/29/25 14:10 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/29/25 14:10 / haw |
| Radium 228 | 1 | pCi/g-dry | | | | E901.1M | 10/29/25 14:10 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/29/25 14:10 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/29/25 14:10 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-008
**Client Sample ID:** DP-37 [1.0-1.5]

**Report Date:** 11/14/25
**Collection Date:** 09/10/25 08:45
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 10/29/25 16:14 / haw |
| Radium 224 precision (±) | 1.6 | pCi/g-dry | | | | E901.1M | 10/29/25 16:14 / haw |
| Radium 224 MDC | 2.7 | pCi/g-dry | | | | E901.1M | 10/29/25 16:14 / haw |
| Radium 226 | 1.1 | pCi/g-dry | | | | E901.1M | 10/29/25 16:14 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/29/25 16:14 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/29/25 16:14 / haw |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1M | 10/29/25 16:14 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/29/25 16:14 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/29/25 16:14 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-009
**Client Sample ID:** DP-38 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/10/25 09:10
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 10/29/25 18:17 / haw |
| Radium 224 precision (±) | 1.8 | pCi/g-dry | | | | E901.1M | 10/29/25 18:17 / haw |
| Radium 224 MDC | 3.1 | pCi/g-dry | | | | E901.1M | 10/29/25 18:17 / haw |
| Radium 226 | 3.4 | pCi/g-dry | | | | E901.1M | 10/29/25 18:17 / haw |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/29/25 18:17 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/29/25 18:17 / haw |
| Radium 228 | 1.0 | pCi/g-dry | | | | E901.1M | 10/29/25 18:17 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/29/25 18:17 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/29/25 18:17 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-010
**Client Sample ID:** DP-39 [1.5-2.0]

**Report Date:** 11/14/25
**Collection Date:** 09/10/25 09:50
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.4 | pCi/g-dry | U | | | E901.1M | 10/30/25 16:42 / haw |
| Radium 224 precision (±) | 1.4 | pCi/g-dry | | | | E901.1M | 10/30/25 16:42 / haw |
| Radium 224 MDC | 2.3 | pCi/g-dry | | | | E901.1M | 10/30/25 16:42 / haw |
| Radium 226 | 0.5 | pCi/g-dry | | | | E901.1M | 10/30/25 16:42 / haw |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E901.1M | 10/30/25 16:42 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/30/25 16:42 / haw |
| Radium 228 | 0.9 | pCi/g-dry | | | | E901.1M | 10/30/25 16:42 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/30/25 16:42 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/30/25 16:42 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-011
**Client Sample ID:** DP-11 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/10/25 10:44
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.4 | pCi/g-dry | U | | | E901.1M | 10/30/25 18:46 / haw |
| Radium 224 precision (±) | 1.8 | pCi/g-dry | | | | E901.1M | 10/30/25 18:46 / haw |
| Radium 224 MDC | 2.9 | pCi/g-dry | | | | E901.1M | 10/30/25 18:46 / haw |
| Radium 226 | 1.9 | pCi/g-dry | | | | E901.1M | 10/30/25 18:46 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 10/30/25 18:46 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 10/30/25 18:46 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 10/30/25 18:46 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 10/30/25 18:46 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 10/30/25 18:46 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-012
**Client Sample ID:** DP-10 [1.0-1.5]

**Report Date:** 11/14/25
**Collection Date:** 09/10/25 11:35
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 11/03/25 10:26 / haw |
| Radium 224 precision (±) | 1.9 | pCi/g-dry | | | | E901.1M | 11/03/25 10:26 / haw |
| Radium 224 MDC | 3.2 | pCi/g-dry | | | | E901.1M | 11/03/25 10:26 / haw |
| Radium 226 | 1 | pCi/g-dry | | | | E901.1M | 11/03/25 10:26 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/03/25 10:26 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/03/25 10:26 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 11/03/25 10:26 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/03/25 10:26 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 11/03/25 10:26 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-013
**Client Sample ID:** DP-09 [1.0-1.5]

**Report Date:** 11/14/25
**Collection Date:** 09/10/25 13:20
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 11/03/25 13:30 / haw |
| Radium 224 precision (±) | 1.6 | pCi/g-dry | | | | E901.1M | 11/03/25 13:30 / haw |
| Radium 224 MDC | 2.7 | pCi/g-dry | | | | E901.1M | 11/03/25 13:30 / haw |
| Radium 226 | 0.9 | pCi/g-dry | | | | E901.1M | 11/03/25 13:30 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/03/25 13:30 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/03/25 13:30 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1M | 11/03/25 13:30 / haw |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/03/25 13:30 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 11/03/25 13:30 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-014
**Client Sample ID:** DP-02 [0.0-0.5]

**Report Date:** 11/14/25
**Collection Date:** 09/11/25 08:00
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 11/03/25 15:31 / haw |
| Radium 224 precision (±) | 1.9 | pCi/g-dry | | | | E901.1M | 11/03/25 15:31 / haw |
| Radium 224 MDC | 3.2 | pCi/g-dry | | | | E901.1M | 11/03/25 15:31 / haw |
| Radium 226 | 1.8 | pCi/g-dry | | | | E901.1M | 11/03/25 15:31 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/03/25 15:31 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/03/25 15:31 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 11/03/25 15:31 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/03/25 15:31 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 11/03/25 15:31 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-015
**Client Sample ID:** DP-01 [0.0-0.5]

**Report Date:** 11/14/25
**Collection Date:** 09/11/25 08:10
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.2 | pCi/g-dry | U | | | E901.1M | 11/03/25 17:57 / haw |
| Radium 224 precision (±) | 2.1 | pCi/g-dry | | | | E901.1M | 11/03/25 17:57 / haw |
| Radium 224 MDC | 3.5 | pCi/g-dry | | | | E901.1M | 11/03/25 17:57 / haw |
| Radium 226 | 1.9 | pCi/g-dry | | | | E901.1M | 11/03/25 17:57 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/03/25 17:57 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/03/25 17:57 / haw |
| Radium 228 | 1.4 | pCi/g-dry | | | | E901.1M | 11/03/25 17:57 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 11/03/25 17:57 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/03/25 17:57 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-016
**Client Sample ID:** DP-17 [0.0-0.5]

**Report Date:** 11/14/25
**Collection Date:** 09/11/25 08:40
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.2 | pCi/g-dry | U | | | E901.1M | 11/04/25 09:40 / haw |
| Radium 224 precision (±) | 4.3 | pCi/g-dry | | | | E901.1M | 11/04/25 09:40 / haw |
| Radium 224 MDC | 7.1 | pCi/g-dry | | | | E901.1M | 11/04/25 09:40 / haw |
| Radium 226 | 26.6 | pCi/g-dry | | | | E901.1M | 11/04/25 09:40 / haw |
| Radium 226 precision (±) | 0.6 | pCi/g-dry | | | | E901.1M | 11/04/25 09:40 / haw |
| Radium 226 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 11/04/25 09:40 / haw |
| Radium 228 | 2.0 | pCi/g-dry | | | | E901.1M | 11/04/25 09:40 / haw |
| Radium 228 precision (±) | 0.6 | pCi/g-dry | | | | E901.1M | 11/04/25 09:40 / haw |
| Radium 228 MDC | 0.8 | pCi/g-dry | | | | E901.1M | 11/04/25 09:40 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-017
**Client Sample ID:** DP-17 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/11/25 08:50
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.4 | pCi/g-dry | | | | E901.1M | 11/04/25 12:07 / haw |
| Radium 224 precision (±) | 0.8 | pCi/g-dry | | | | E901.1M | 11/04/25 12:07 / haw |
| Radium 224 MDC | 1.3 | pCi/g-dry | | | | E901.1M | 11/04/25 12:07 / haw |
| Radium 226 | 1 | pCi/g-dry | | | | E901.1M | 11/04/25 12:07 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/04/25 12:07 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/04/25 12:07 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 11/04/25 12:07 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/04/25 12:07 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 11/04/25 12:07 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-018
**Client Sample ID:** DP-18 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/11/25 09:00
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.7 | pCi/g-dry | | | | E901.1M | 11/04/25 14:08 / haw |
| Radium 224 precision (±) | 1 | pCi/g-dry | | | | E901.1M | 11/04/25 14:08 / haw |
| Radium 224 MDC | 1.5 | pCi/g-dry | | | | E901.1M | 11/04/25 14:08 / haw |
| Radium 226 | 0.8 | pCi/g-dry | | | | E901.1M | 11/04/25 14:08 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/04/25 14:08 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/04/25 14:08 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 11/04/25 14:08 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/04/25 14:08 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/04/25 14:08 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-019
**Client Sample ID:** DP-DS2 [0.0-0.5]

**Report Date:** 11/14/25
**Collection Date:** 09/11/25 09:15
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 11/05/25 15:19 / haw |
| Radium 224 precision (±) | 2.0 | pCi/g-dry | | | | E901.1M | 11/05/25 15:19 / haw |
| Radium 224 MDC | 3.2 | pCi/g-dry | | | | E901.1M | 11/05/25 15:19 / haw |
| Radium 226 | 1.7 | pCi/g-dry | | | | E901.1M | 11/05/25 15:19 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/05/25 15:19 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/05/25 15:19 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1M | 11/05/25 15:19 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/05/25 15:19 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/05/25 15:19 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-020
**Client Sample ID:** DP-DS3 [0.0-0.5]

**Report Date:** 11/14/25
**Collection Date:** 09/11/25 09:30
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.6 | pCi/g-dry | U | | | E901.1M | 11/05/25 18:04 / haw |
| Radium 224 precision (±) | 2.0 | pCi/g-dry | | | | E901.1M | 11/05/25 18:04 / haw |
| Radium 224 MDC | 3.3 | pCi/g-dry | | | | E901.1M | 11/05/25 18:04 / haw |
| Radium 226 | 1.9 | pCi/g-dry | | | | E901.1M | 11/05/25 18:04 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/05/25 18:04 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/05/25 18:04 / haw |
| Radium 228 | 1.6 | pCi/g-dry | | | | E901.1M | 11/05/25 18:04 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 11/05/25 18:04 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/05/25 18:04 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-021
**Client Sample ID:** DP-DS4 [0.0-0.5]

**Report Date:** 11/14/25
**Collection Date:** 09/11/25 09:45
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.2 | pCi/g-dry | U | | | E901.1M | 11/06/25 13:57 / haw |
| Radium 224 precision (±) | 4.5 | pCi/g-dry | | | | E901.1M | 11/06/25 13:57 / haw |
| Radium 224 MDC | 7.5 | pCi/g-dry | | | | E901.1M | 11/06/25 13:57 / haw |
| Radium 226 | 28.0 | pCi/g-dry | | | | E901.1M | 11/06/25 13:57 / haw |
| Radium 226 precision (±) | 0.7 | pCi/g-dry | | | | E901.1M | 11/06/25 13:57 / haw |
| Radium 226 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/06/25 13:57 / haw |
| Radium 228 | 1.8 | pCi/g-dry | | | | E901.1M | 11/06/25 13:57 / haw |
| Radium 228 precision (±) | 0.6 | pCi/g-dry | | | | E901.1M | 11/06/25 13:57 / haw |
| Radium 228 MDC | 0.8 | pCi/g-dry | | | | E901.1M | 11/06/25 13:57 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-022
**Client Sample ID:** DP-08 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/15/25 08:00
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.6 | pCi/g-dry | U | | | E901.1M | 11/06/25 15:58 / haw |
| Radium 224 precision (±) | 2.1 | pCi/g-dry | | | | E901.1M | 11/06/25 15:58 / haw |
| Radium 224 MDC | 3.5 | pCi/g-dry | | | | E901.1M | 11/06/25 15:58 / haw |
| Radium 226 | 2.6 | pCi/g-dry | | | | E901.1M | 11/06/25 15:58 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/06/25 15:58 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/06/25 15:58 / haw |
| Radium 228 | 1.6 | pCi/g-dry | | | | E901.1M | 11/06/25 15:58 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 11/06/25 15:58 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/06/25 15:58 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-023
**Client Sample ID:** DP-06 [1.5-2.0]

**Report Date:** 11/14/25
**Collection Date:** 09/15/25 09:20
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.6 | pCi/g-dry | U | | | E901.1M | 11/06/25 18:03 / haw |
| Radium 224 precision (±) | 1.9 | pCi/g-dry | | | | E901.1M | 11/06/25 18:03 / haw |
| Radium 224 MDC | 3.2 | pCi/g-dry | | | | E901.1M | 11/06/25 18:03 / haw |
| Radium 226 | 2.2 | pCi/g-dry | | | | E901.1M | 11/06/25 18:03 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/06/25 18:03 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/06/25 18:03 / haw |
| Radium 228 | 1.6 | pCi/g-dry | | | | E901.1M | 11/06/25 18:03 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 11/06/25 18:03 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/06/25 18:03 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-024
**Client Sample ID:** DP-04 [1.0-1.5]

**Report Date:** 11/14/25
**Collection Date:** 09/15/25 10:15
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 2.0 | pCi/g-dry | | | | E901.1M | 11/10/25 09:59 / haw |
| Radium 224 precision (±) | 1.1 | pCi/g-dry | | | | E901.1M | 11/10/25 09:59 / haw |
| Radium 224 MDC | 1.7 | pCi/g-dry | | | | E901.1M | 11/10/25 09:59 / haw |
| Radium 226 | 1.6 | pCi/g-dry | | | | E901.1M | 11/10/25 09:59 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/10/25 09:59 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/10/25 09:59 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 11/10/25 09:59 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/10/25 09:59 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/10/25 09:59 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-025
**Client Sample ID:** DP-16 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/15/25 12:30
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.7 | pCi/g-dry | | | | E901.1M | 11/10/25 12:01 / haw |
| Radium 224 precision (±) | 0.9 | pCi/g-dry | | | | E901.1M | 11/10/25 12:01 / haw |
| Radium 224 MDC | 1.5 | pCi/g-dry | | | | E901.1M | 11/10/25 12:01 / haw |
| Radium 226 | 1.0 | pCi/g-dry | | | | E901.1M | 11/10/25 12:01 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/10/25 12:01 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/10/25 12:01 / haw |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1M | 11/10/25 12:01 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/10/25 12:01 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 11/10/25 12:01 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-026
**Client Sample ID:** DP-15 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/15/25 13:15
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 2.1 | pCi/g-dry | | | | E901.1M | 11/10/25 14:05 / haw |
| Radium 224 precision (±) | 1.2 | pCi/g-dry | | | | E901.1M | 11/10/25 14:05 / haw |
| Radium 224 MDC | 2.0 | pCi/g-dry | | | | E901.1M | 11/10/25 14:05 / haw |
| Radium 226 | 2.7 | pCi/g-dry | | | | E901.1M | 11/10/25 14:05 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/10/25 14:05 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/10/25 14:05 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 11/10/25 14:05 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/10/25 14:05 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/10/25 14:05 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-027
**Client Sample ID:** DP-05 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/16/25 08:10
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 11/10/25 16:06 / haw |
| Radium 224 precision (±) | 1.9 | pCi/g-dry | | | | E901.1M | 11/10/25 16:06 / haw |
| Radium 224 MDC | 3.2 | pCi/g-dry | | | | E901.1M | 11/10/25 16:06 / haw |
| Radium 226 | 1.0 | pCi/g-dry | | | | E901.1M | 11/10/25 16:06 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/10/25 16:06 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/10/25 16:06 / haw |
| Radium 228 | 1.2 | pCi/g-dry | | | | E901.1M | 11/10/25 16:06 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/10/25 16:06 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/10/25 16:06 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-028
**Client Sample ID:** DP-07 [3.0-3.5]

**Report Date:** 11/14/25
**Collection Date:** 09/16/25 09:15
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 2.0 | pCi/g-dry | | | | E901.1M | 11/10/25 18:08 / haw |
| Radium 224 precision (±) | 1 | pCi/g-dry | | | | E901.1M | 11/10/25 18:08 / haw |
| Radium 224 MDC | 1.5 | pCi/g-dry | | | | E901.1M | 11/10/25 18:08 / haw |
| Radium 226 | 1 | pCi/g-dry | | | | E901.1M | 11/10/25 18:08 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/10/25 18:08 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/10/25 18:08 / haw |
| Radium 228 | 1.0 | pCi/g-dry | | | | E901.1M | 11/10/25 18:08 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/10/25 18:08 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 11/10/25 18:08 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-029
**Client Sample ID:** DP-12 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/16/25 09:40
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 2.3 | pCi/g-dry | | | | E901.1M | 11/11/25 09:47 / haw |
| Radium 224 precision (±) | 1.0 | pCi/g-dry | | | | E901.1M | 11/11/25 09:47 / haw |
| Radium 224 MDC | 1.6 | pCi/g-dry | | | | E901.1M | 11/11/25 09:47 / haw |
| Radium 226 | 1.5 | pCi/g-dry | | | | E901.1M | 11/11/25 09:47 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/11/25 09:47 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/11/25 09:47 / haw |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1M | 11/11/25 09:47 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/11/25 09:47 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/11/25 09:47 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-030
**Client Sample ID:** DP-13 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/16/25 10:00
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | -0.1 | pCi/g-dry | U | | | E901.1M | 11/11/25 13:51 / haw |
| Radium 224 precision (±) | 2.1 | pCi/g-dry | | | | E901.1M | 11/11/25 13:51 / haw |
| Radium 224 MDC | 3.5 | pCi/g-dry | | | | E901.1M | 11/11/25 13:51 / haw |
| Radium 226 | 2.8 | pCi/g-dry | | | | E901.1M | 11/11/25 13:51 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/11/25 13:51 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/11/25 13:51 / haw |
| Radium 228 | 1.6 | pCi/g-dry | | | | E901.1M | 11/11/25 13:51 / haw |
| Radium 228 precision (±) | 0.4 | pCi/g-dry | | | | E901.1M | 11/11/25 13:51 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/11/25 13:51 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-031
**Client Sample ID:** DP-44 [1.0-1.5]

**Report Date:** 11/14/25
**Collection Date:** 09/22/25 08:50
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.9 | pCi/g-dry | | | | E901.1M | 11/11/25 15:53 / haw |
| Radium 224 precision (±) | 1.0 | pCi/g-dry | | | | E901.1M | 11/11/25 15:53 / haw |
| Radium 224 MDC | 1.6 | pCi/g-dry | | | | E901.1M | 11/11/25 15:53 / haw |
| Radium 226 | 1.0 | pCi/g-dry | | | | E901.1M | 11/11/25 15:53 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/11/25 15:53 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/11/25 15:53 / haw |
| Radium 228 | 1.7 | pCi/g-dry | | | | E901.1M | 11/11/25 15:53 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/11/25 15:53 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/11/25 15:53 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-032
**Client Sample ID:** DP-46 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/24/25 08:10
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1.9 | pCi/g-dry | | | | E901.1M | 11/11/25 18:20 / haw |
| Radium 224 precision (±) | 1.0 | pCi/g-dry | | | | E901.1M | 11/11/25 18:20 / haw |
| Radium 224 MDC | 1.6 | pCi/g-dry | | | | E901.1M | 11/11/25 18:20 / haw |
| Radium 226 | 1.0 | pCi/g-dry | | | | E901.1M | 11/11/25 18:20 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/11/25 18:20 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/11/25 18:20 / haw |
| Radium 228 | 1.6 | pCi/g-dry | | | | E901.1M | 11/11/25 18:20 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/11/25 18:20 / haw |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 11/11/25 18:20 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-033
**Client Sample ID:** DP-48 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/24/25 08:30
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.6 | pCi/g-dry | U | | | E901.1M | 11/12/25 09:49 / haw |
| Radium 224 precision (±) | 2.1 | pCi/g-dry | | | | E901.1M | 11/12/25 09:49 / haw |
| Radium 224 MDC | 3.5 | pCi/g-dry | | | | E901.1M | 11/12/25 09:49 / haw |
| Radium 226 | 2.4 | pCi/g-dry | | | | E901.1M | 11/12/25 09:49 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/12/25 09:49 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/12/25 09:49 / haw |
| Radium 228 | 1.5 | pCi/g-dry | | | | E901.1M | 11/12/25 09:49 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/12/25 09:49 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/12/25 09:49 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-034
**Client Sample ID:** DP-41 [3.5-4.0]

**Report Date:** 11/14/25
**Collection Date:** 09/24/25 10:30
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 1 | pCi/g-dry | U | | | E901.1M | 11/12/25 11:51 / haw |
| Radium 224 precision (±) | 3.5 | pCi/g-dry | | | | E901.1M | 11/12/25 11:51 / haw |
| Radium 224 MDC | 5.8 | pCi/g-dry | | | | E901.1M | 11/12/25 11:51 / haw |
| Radium 226 | 17.2 | pCi/g-dry | | | | E901.1M | 11/12/25 11:51 / haw |
| Radium 226 precision (±) | 0.5 | pCi/g-dry | | | | E901.1M | 11/12/25 11:51 / haw |
| Radium 226 MDC | 0.3 | pCi/g-dry | | | | E901.1M | 11/12/25 11:51 / haw |
| Radium 228 | 1.1 | pCi/g-dry | | | | E901.1M | 11/12/25 11:51 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/12/25 11:51 / haw |
| Radium 228 MDC | 0.5 | pCi/g-dry | | | | E901.1M | 11/12/25 11:51 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** MTM SCA Characterization
**Lab ID:** C25090966-035
**Client Sample ID:** DP-DS5 [0.5-1.0]

**Report Date:** 11/14/25
**Collection Date:** 09/24/25 11:15
**DateReceived:** 09/29/25
**Matrix:** Soil

| Analyses | Result | Units | Qualifiers | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES, GAMMA** | | | | | | | |
| Radium 224 | 0.5 | pCi/g-dry | U | | | E901.1M | 11/12/25 13:53 / haw |
| Radium 224 precision (±) | 1.9 | pCi/g-dry | | | | E901.1M | 11/12/25 13:53 / haw |
| Radium 224 MDC | 3.2 | pCi/g-dry | | | | E901.1M | 11/12/25 13:53 / haw |
| Radium 226 | 1.9 | pCi/g-dry | | | | E901.1M | 11/12/25 13:53 / haw |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E901.1M | 11/12/25 13:53 / haw |
| Radium 226 MDC | 0.2 | pCi/g-dry | | | | E901.1M | 11/12/25 13:53 / haw |
| Radium 228 | 1.3 | pCi/g-dry | | | | E901.1M | 11/12/25 13:53 / haw |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | E901.1M | 11/12/25 13:53 / haw |
| Radium 228 MDC | 0.4 | pCi/g-dry | | | | E901.1M | 11/12/25 13:53 / haw |

**Report Definitions:**
RL - Analyte Reporting Limit
QCL - Quality Control Limit
U - Not detected
MCL - Maximum Contaminant Level
ND - Not detected at the Reporting Limit (RL)

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Work Order:** C25090966 **Report Date:** 11/13/25

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E901.1M** | | | | | | | | | | Batch: R322153 |
| **Lab ID: MB-322153** | 9 | Method Blank | | | Run: GAM-HPGE 2_251027A | | | | 10/27/25 10:26 | |
| Radium 224 | | 0.1 | pCi/g-dry | | | | | | | U |
| Radium 224 precision (±) | | 0.6 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 1 | pCi/g-dry | | | | | | | |
| Radium 226 | | 0.09 | pCi/g-dry | | | | | | | U |
| Radium 226 precision (±) | | 0.1 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.1 | pCi/g-dry | | | | | | | |
| Radium 228 | | 0.07 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.1 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.2 | pCi/g-dry | | | | | | | |
| **Lab ID: LCS-322153** | 6 | Laboratory Control Sample | | | Run: GAM-HPGE 2_251027A | | | | 10/27/25 13:26 | |
| Cobalt 60 | | 340 | pCi/g-dry | | 107 | 70 | 130 | | | |
| Cobalt 60 precision (±) | | 2.8 | pCi/g-dry | | | | | | | |
| Cobalt 60 MDC | | 0.77 | pCi/g-dry | | | | | | | |
| Lead 210 | | 1700 | pCi/g-dry | | 101 | 70 | 130 | | | |
| Lead 210 precision (±) | | 14 | pCi/g-dry | | | | | | | |
| Lead 210 MDC | | 12 | pCi/g-dry | | | | | | | |
| **Lab ID: C25090966-001ADUP** | 9 | Sample Duplicate | | | Run: GAM-HPGE 2_251027A | | | | 10/28/25 12:19 | |
| Radium 224 | | 0.53 | pCi/g-dry | | | | | 110 | 30 | UR |
| Radium 224 precision (±) | | 1.9 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 3.2 | pCi/g-dry | | | | | | | |
| Radium 226 | | 1.0 | pCi/g-dry | | | | | 0.7 | 30 | |
| Radium 226 precision (±) | | 0.21 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.23 | pCi/g-dry | | | | | | | |
| Radium 228 | | 1.7 | pCi/g-dry | | | | | 2.6 | 30 | |
| Radium 228 precision (±) | | 0.32 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.32 | pCi/g-dry | | | | | | | |
| - Duplicate RPD for Ra224 is outside of the acceptance range for this analysis. However, the RER is less than or equal to the limit of 3. The RER result is 0.61. | | | | | | | | | | |
| - The RER result for Ra226 is 0.03 and Ra228 is 0.10. | | | | | | | | | | |
| **Lab ID: C25100876-002ADUP** | 9 | Sample Duplicate | | | Run: GAM-HPGE 2_251027A | | | | 10/30/25 15:02 | |
| Radium 224 | | -1.3 | pCi/g-dry | | | | | 89 | 30 | UR |
| Radium 224 precision (±) | | 2.6 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 3.7 | pCi/g-dry | | | | | | | |
| Radium 226 | | 0.26 | pCi/g-dry | | | | | 69 | 30 | UR |
| Radium 226 precision (±) | | 0.37 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.53 | pCi/g-dry | | | | | | | |
| Radium 228 | | 0.32 | pCi/g-dry | | | | | 75 | 30 | UR |
| Radium 228 precision (±) | | 0.58 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.90 | pCi/g-dry | | | | | | | |
| - Duplicate RPD is outside of the acceptance range for this analysis. However, the RER is less than or equal to the limit of 3. The RER result for Ra224 is 0.23, Ra226 is 0.5 and Ra228 is 0.49. | | | | | | | | | | |

**Qualifiers:**

RL - Analyte Reporting Limit

R - Relative Percent Difference (RPD) exceeds advisory limit

ND - Not detected at the Reporting Limit (RL)

U - Not detected

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Work Order:** C25090966 **Report Date:** 11/13/25

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E901.1M** | | | | | | | | | | Batch: R322448 |
| **Lab ID: MB-322448** | 9 | Method Blank | | | Run: GAM-HPGE 2_251104A | | | | | 11/04/25 16:33 |
| Radium 224 | | 0.3 | pCi/g-dry | | | | | | | U |
| Radium 224 precision (±) | | 0.6 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 1 | pCi/g-dry | | | | | | | |
| Radium 226 | | 0.08 | pCi/g-dry | | | | | | | U |
| Radium 226 precision (±) | | 0.09 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.1 | pCi/g-dry | | | | | | | |
| Radium 228 | | 0.02 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.2 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.3 | pCi/g-dry | | | | | | | |
| **Lab ID: LCS-322448** | 6 | Laboratory Control Sample | | | Run: GAM-HPGE 2_251104A | | | | | 11/05/25 13:04 |
| Cobalt 60 | | 310 | pCi/g-dry | | 99 | 70 | 130 | | | |
| Cobalt 60 precision (±) | | 2.7 | pCi/g-dry | | | | | | | |
| Cobalt 60 MDC | | 0.78 | pCi/g-dry | | | | | | | |
| Lead 210 | | 1700 | pCi/g-dry | | 98 | 70 | 130 | | | |
| Lead 210 precision (±) | | 14 | pCi/g-dry | | | | | | | |
| Lead 210 MDC | | 12 | pCi/g-dry | | | | | | | |
| **Lab ID: C25090966-020ADUP** | 9 | Sample Duplicate | | | Run: GAM-HPGE 2_251104A | | | | | 11/06/25 09:49 |
| Radium 224 | | -0.055 | pCi/g-dry | | | | | 170 | 30 | UR |
| Radium 224 precision (±) | | 1.9 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 3.2 | pCi/g-dry | | | | | | | |
| Radium 226 | | 1.8 | pCi/g-dry | | | | | 5.4 | 30 | |
| Radium 226 precision (±) | | 0.18 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.17 | pCi/g-dry | | | | | | | |
| Radium 228 | | 1.6 | pCi/g-dry | | | | | 0 | 30 | |
| Radium 228 precision (±) | | 0.35 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.39 | pCi/g-dry | | | | | | | |
| - Duplicate RPD for Ra224 is outside of the acceptance range for this analysis. However, the RER is less than or equal to the limit of 3. The RER result is 0.20. | | | | | | | | | | |
| - The RER result for Ra226 is 0.36 and Ra228 is 0.00. | | | | | | | | | | |
| **Lab ID: C25090966-029ADUP** | 9 | Sample Duplicate | | | Run: GAM-HPGE 2_251104A | | | | | 11/11/25 11:50 |
| Radium 224 | | -0.58 | pCi/g-dry | | | | | 330 | 30 | UR |
| Radium 224 precision (±) | | 1.9 | pCi/g-dry | | | | | | | |
| Radium 224 MDC | | 3.1 | pCi/g-dry | | | | | | | |
| Radium 226 | | 1.5 | pCi/g-dry | | | | | 5.2 | 30 | |
| Radium 226 precision (±) | | 0.18 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.17 | pCi/g-dry | | | | | | | |
| Radium 228 | | 1.3 | pCi/g-dry | | | | | 5.1 | 30 | |
| Radium 228 precision (±) | | 0.32 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.35 | pCi/g-dry | | | | | | | |
| - Duplicate RPD for Ra224 is outside of the acceptance range for this analysis. However, the RER is less than or equal to the limit of 3. The RER result is 1.34. | | | | | | | | | | |
| - The RER result for Ra226 is 0.31 and Ra228 is 0.14. | | | | | | | | | | |

**Qualifiers:**

RL - Analyte Reporting Limit

ND - Not detected at the Reporting Limit (RL)

R - Relative Percent Difference (RPD) exceeds advisory limit

U - Not detected

# Work Order Receipt Checklist

## Rio Grande Resources Corporation C25090966

Login completed by: Dakota R. Sawyer
Date Received: 9/29/2025
Reviewed by: srichins
Received by: LDS
Reviewed Date: 10/7/2025
Carrier name: Return UPS Ground

| | | | |
|---|---|---|---|
| Shipping container/cooler in good condition? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on all shipping container(s)/cooler(s)? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on all sample bottles? | Yes ☐ | No ☐ | Not Present ☑ |
| Chain of custody present? | Yes ☑ | No ☐ | |
| Chain of custody signed when relinquished and received? | Yes ☑ | No ☐ | |
| Chain of custody agrees with sample labels? | Yes ☑ | No ☐ | |
| Samples in proper container/bottle? | Yes ☑ | No ☐ | |
| Sample containers intact? | Yes ☑ | No ☐ | |
| Sufficient sample volume for indicated test? | Yes ☑ | No ☐ | |
| All samples received within holding time? (Exclude analyses that are considered field parameters such as pH, DO, Res Cl, Sulfite, Ferrous Iron, etc.) | Yes ☑ | No ☐ | |
| Temp Blank received in all shipping container(s)/cooler(s)? | Yes ☐ | No ☑ | Not Applicable ☐ |
| Container/Temp Blank temperature: | 22.7°C No Ice | | |
| Containers requiring zero headspace have no headspace or bubble that is <6mm (1/4"). | Yes ☐ | No ☐ | No VOA vials submitted ☑ |
| Water - pH acceptable upon receipt? | Yes ☐ | No ☐ | Not Applicable ☑ |

### Standard Reporting Procedures:

Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH, Dissolved Oxygen and Residual Chlorine, are qualified as being analyzed outside of recommended holding time.

Solid/soil samples are reported on a wet weight basis (as received) unless specifically indicated. If moisture corrected, data units are typically noted as –dry. For agricultural and mining soil parameters/characteristics, all samples are dried and ground prior to sample analysis.

The reference date for Radon analysis is the sample collection date. The reference date for all other Radiochemical analyses is the analysis date. Radiochemical precision results represent a 2-sigma Total Measurement Uncertainty.

For methods that require zero headspace or require preservation check at the time of analysis due to potential interference, the pH is verified at analysis. Nonconforming sample pH is documented as part of the analysis and included in the sample analysis comments.

Trip Blanks and/or Blind Duplicate samples are assigned the earliest collection time for the associated requested analysis in order to evaluate the holding time unless specifically indicated.

### Contact and Corrective Action Comments:

The temperature of the sample(s) in shipping container 1 was 22.7°C and shipping container 2 was 21.5°C. DRS 09/29/25

## *Laboratory Certifications and Accreditations*

Current certificates are available at [www.energylab.com](http://www.energylab.com) website:

| | Agency | Number |
|---|---|---|
| ***Billings, MT*** | Alaska | 17-023 |
| | California | 3087 |
| | Colorado | MT00005 |
| | Department of Defense (DoD)/ISO17025 | ADE-2588 |
| | Florida (Primary NELAP) | E87668 |
| | Idaho | MT00005 |
| | Louisiana | 05079 |
| | Montana | CERT0044 |
| | Nebraska | NE-OS-13-04 |
| | Nevada | NV-C24-00250 |
| | North Dakota | R-007 |
| | National Radon Proficiency | 109383-RMP |
| | Oregon | 4184 |
| | South Dakota | ARSD 74:04:07 |
| | Texas | TX-C24-00302 |
| | US EPA Region VIII | Reciprocal |
| | USDA Soil Permit | P330-20-00170 |
| | Washington | C1039 |
| ***Casper, WY*** | Alaska | 20-006 |
| | California | 3021 |
| | Colorado | WY00002 |
| | Florida (Primary NELAP) | E87641 |
| | Idaho | WY00002 |
| | Louisiana | 05083 |
| | Montana | CERT0002 |
| | Nebraska | NE-OS-08-04 |
| | Nevada | NV-C24-00245 |
| | North Dakota | R-125 |
| | Oregon | WY200001 |
| | South Dakota | WY00002 |
| | Texas | T104704181-23-21 |
| | US EPA Region VIII | WY00002 |
| | USNRC License | 49-26846-01 |
| | Washington | C1012 |
| ***Gillette, WY*** | US EPA Region VIII | WY00006 |
| ***Helena, MT*** | Colorado | MT00945 |
| | Montana | CERT0079 |
| | Nevada | NV-C24-00119 |
| | US EPA Region VIII | Reciprocal |
| | USDA Soil Permit | P330-20-00090 |

# Chain of Custody & Analytical Request Record

ENERGY LABORATORIES — Trust our People. Trust our Data.

www.energylab.com



## Account Information (Billing information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email — Receive Report ☐Hard Copy ☒Email |
| Purchase Order | MT11820 |
| Quote | |
| Bottle Order | |

## Report Information (if different than Account Information)

| | |
|---|---|
| Company/Name | AVM Environmental Services, Inc. |
| Contact | Victor Patel |
| Phone | 505-287-4593 |
| Mailing Address | 1717 Del Norte Blvd |
| City, State, Zip | Grants, NM 87020 |
| Email | vpatelavm@outlook.com |
| Receive Report | ☐Hard Copy ☒Email |
| Special Report/Formats: | ☐ LEVEL IV ☐NELAC ☐ EDD/EDT (contact laboratory) ☐ Other_____ |

## Comments

## Project Information

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM SCA Characterization |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-4593 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

**Analysis Requested**

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for soil | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | DP-20 0.5'-1.0' | 09/08/2025 | 9:00 am | 1 | S | ✓ | | | C25090926 |
| 2 | DP-25 0.5'-1.0' | 09/08/2025 | 9:40 am | 1 | S | ✓ | | | |
| 3 | DP-26 2.0'-2.5' | 09/08/2025 | 10:40 am | 1 | S | ✓ | | | |
| 4 | DP-34 0.5'-1.0' | 09/09/2025 | 10:50 am | 1 | S | ✓ | | | |
| 5 | DP-35 0.5'-1.0' | 09/09/2025 | 11:40 am | 1 | S | ✓ | | | |
| 6 | DP-33 0.5'-1.0' | 09/09/2025 | 12:50 pm | 1 | S | ✓ | | | |
| 7 | DP-36 1.0'-1.5' | 09/09/2025 | 1:30 pm | 1 | S | ✓ | | | |
| 8 | DP-37 1.0'-1.5' | 09/10/2025 | 8:45 am | 1 | S | ✓ | | | |
| 9 | DP-38 0.5'-1.0' | 09/10/2025 | 9:10 am | 1 | S | ✓ | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were NOT used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Victor Patel | 9-29-25/1200 | | | | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Lorie Snider | 09-29-25 10:00 | Lorie Snider |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

ENERGY LABORATORIES
Trust our People. Trust our Data.

# Chain of Custody & Analytical Request Record

www.energylab.com



## Account Information (Billing information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☒Email |
| Purchase Order | MT11820 |
| Quote | |
| Bottle Order | |

## Report Information (if different than Account Information)

| | |
|---|---|
| Company/Name | AVM Environmental Services, Inc. |
| Contact | Victor Patel |
| Phone | 505-287-4593 |
| Mailing Address | 1717 Del Norte Blvd |
| City, State, Zip | Grants, NM 87020 |
| Email | vpatelavm@outlook.com |
| Receive Report | ☐Hard Copy ☒Email |

Special Report/Formats:
☐ LEVEL IV ☐NELAC ☐ EDD/EDT (contact laboratory) ☐ Other_____

## Comments

## Project Information

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM SCA Characterization |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-4593 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

**Analysis Requested**

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for soil ✓ | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | DP-39 1.5'-2.0' | 09/10/2025 | 9:50 am | 1 | S | ✓ | | | C25090966 |
| 2 | DP-11 0.5'-1.0' | 09/10/2025 | 10:44 am | 1 | S | ✓ | | | |
| 3 | DP-10 1.0'-1.5' | 09/10/2025 | 11:35 am | 1 | S | ✓ | | | |
| 4 | DP-09 1.0'-1.5' | 09/10/2025 | 1:20 pm | 1 | S | ✓ | | | |
| 5 | DP-02 0.0'-0.5' | 09/11/2025 | 8:00 am | 1 | S | ✓ | | | |
| 6 | DP-01 0.0'-0.5' | 09/11/2025 | 8:10 am | 1 | S | ✓ | | | |
| 7 | DP-17 0.0'-0.5' | 09/11/2025 | 8:40 am | 1 | S | ✓ | | | |
| 8 | DP-17 0.5'-1.0' | 09/11/2025 | 8:50 am | 1 | S | ✓ | | | |
| 9 | DP-18 0.5'-1.0' | 09/11/2025 | 9:00 am | 1 | S | ✓ | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were NOT used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Victor Patel | 9-25-25 1200 | | | | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Lorie Snider | 09-29-25 10:00 | Lorie Snider |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

# Chain of Custody & Analytical Request Record

ENERGY LABORATORIES — Trust our People. Trust our Data.

www.energylab.com



**Account Information** *(Billing information)*

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ☒Email |
| Receive Report | ☐Hard Copy ☒Email |
| Purchase Order | MT11820 |
| Quote | |
| Bottle Order | |

**Report Information** *(if different than Account Information)*

| | |
|---|---|
| Company/Name | AVM Environmental Services, Inc. |
| Contact | Victor Patel |
| Phone | 505-287-4593 |
| Mailing Address | 1717 Del Norte Blvd |
| City, State, Zip | Grants, NM 87020 |
| Email | vpatelavm@outlook.com |
| Receive Report | ☐Hard Copy ☒Email |
| Special Report/Formats: | ☐ LEVEL IV ☐NELAC ☐ EDD/EDT *(contact laboratory)* ☐ Other_____ |

**Comments**

**Project Information**

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM SCA Characterization |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-4593 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ☒ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
☒ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for soil | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | DP-DS2 0.0'-0.5' | 09/11/2025 | 9:15 am | 1 | S | ✓ | | | C25090966 |
| 2 | DP-DS3 0.0'-0.5' | 09/11/2025 | 9:30 am | 1 | S | ✓ | | | |
| 3 | DP-DS4 0.0'-0.5' | 09/11/2025 | 9:45 am | 1 | S | ✓ | | | |
| 4 | DP-08 0.5'-1.0' | 09/15/2025 | 8:00 am | 1 | S | ✓ | | | |
| 5 | DP-06 1.5'-2.0' | 09/15/2025 | 9:20 am | 1 | S | ✓ | | | |
| 6 | DP-04 1.0'-1.5' | 09/15/2025 | 10:15 am | 1 | S | ✓ | | | |
| 7 | DP-16 0.5'-1.0' | 09/15/2025 | 12:30 pm | 1 | S | ✓ | | | |
| 8 | DP-15 0.5'-1.0' | 09/15/2025 | 1:15 pm | 1 | S | ✓ | | | |
| 9 | DP-05 0.5'-1.0' | 09/16/2025 | 8:10 am | 1 | S | ✓ | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were NOT used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Victor Patel | 9-25-25 1200 | | | | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Lorie Snider | 09-29-25 10:00 | Lorie Snider |

**LABORATORY USE ONLY**

| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

# Chain of Custody & Analytical Request Record

ENERGY LABORATORIES — Trust our People. Trust our Data.

www.energylab.com



## Account Information (Billing information)

| | |
|---|---|
| Company/Name | Rio Grande Resources Corporation |
| Contact | Anita Willcox |
| Phone | 505-287-7971 |
| Mailing Address | PO Box 1150 |
| City, State, Zip | Grants, NM 87020 |
| Email | anita.willcox@ga.com |
| Receive Invoice | ☐Hard Copy ■Email |
| Receive Report | ☐Hard Copy ■Email |
| Purchase Order | MT11820 |
| Quote | |
| Bottle Order | |

## Report Information (if different than Account Information)

| | |
|---|---|
| Company/Name | AVM Environmental Services, Inc. |
| Contact | Victor Patel |
| Phone | 505-287-4593 |
| Mailing Address | 1717 Del Norte Blvd |
| City, State, Zip | Grants, NM 87020 |
| Email | vpatelavm@outlook.com |
| Receive Report | ☐Hard Copy ■Email |

Special Report/Formats: ☐ LEVEL IV ☐NELAC ☐ EDD/EDT (contact laboratory) ☐ Other_____

## Comments

## Project Information

| | |
|---|---|
| Project Name, PWSID, Permit, etc. | MTM SCA Characterization |
| Sampler Name | Victor Patel |
| Sampler Phone | 505-287-4593 |
| Sample Origin State | New Mexico |
| EPA/State Compliance | ☐ Yes ■ No |

**URANIUM MINING CLIENTS MUST indicate sample type**
■ Unprocessed Ore
☐ Processed Ore (Ground or Refined) **CALL BEFORE SENDING
☐ 11(e)2 Byproduct Material (Can ONLY be Submitted to ELI Casper Location)

**Matrix Codes**
A - Air
W - Water
S - Soils/Solids
V - Vegetation
B - Bioassay
O - Oil
DW - Drinking Water

All turnaround times are standard unless marked as RUSH.
Energy Laboratories MUST be contacted prior to RUSH sample submittal for charges and scheduling – See Instructions Page

| | Sample Identification (Name, Location, Interval, etc.) | Collection Date | Collection Time | Number of Containers | Matrix (See Codes Above) | EPA 901.1 Modified for soil + | See Attached | RUSH TAT | ELI LAB ID (Laboratory Use Only) |
|---|---|---|---|---|---|---|---|---|---|
| 1 | DP-07 3.0'-3.5' | 09/16/2025 | 9:15 am | 1 | S | ✓ | | | C25090966 |
| 2 | DP-12 0.5'-1.0' | 09/16/2025 | 9:40 am | 1 | S | ✓ | | | |
| 3 | DP-13 0.5'-1.0' | 09/16/2025 | 10:00 am | 1 | S | ✓ | | | |
| 4 | DP-44 1.0'-1.5' | 09/22/2025 | 8:50 am | 1 | S | ✓ | | | |
| 5 | DP 46 0.5'-1.0' | 09/24/2025 | 8:10 am | 1 | S | ✓ | | | |
| 6 | DP-48 0.5'-1.0' | 09/24/2025 | 8:30 am | 1 | S | ✓ | | | |
| 7 | DP-41 3.5'-4.0' | 09/24/2025 | 10:30 am | 1 | S | ✓ | | | |
| 8 | DP-DS5 0.5'-1.0' | 09/24/2025 | 11:15 am | 1 | S | ✓ | | | |
| 9 | | | | | | | | | |

**ELI is REQUIRED to provide preservative traceability.** If the preservatives supplied with the bottle order were NOT used, please attach your preservative information with this COC.

| Custody Record MUST be signed | Relinquished by (print) | Date/Time | Signature | Received by (print) | Date/Time | Signature |
|---|---|---|---|---|---|---|
| | Victor Patel | 9-25-25/1200 | | | | |
| | Relinquished by (print) | Date/Time | Signature | Received by Laboratory (print) | Date/Time | Signature |
| | | | | Lori Snider | 09-29-25 10:00 | |

**LABORATORY USE ONLY**


| Shipped By | Cooler ID(s) | Custody Seals Y N C B | Intact Y N | Receipt Temp °C | Temp Blank Y N | On Ice Y N | Payment Type CC Cash Check_____ | Amount $ | Receipt Number (cash/check only) |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All subcontracted data will be clearly notated on your analytical report.

# APPENDIX D.3

## Field Sampling and Laboratory Test Data

Laboratory Test Results


N 1581000
N 1580000
E 2782500
E 2782000
ORE PAD POND
MT-OP-D
B
MT-OP-C
A
MT-OP-E
AREA A
MT-A-A
MT-A-B
MT-A-C
MT-1-F
MT-1-E
A
B
C
MT-1-D
POND 1
COUNTY RD. 334
MINE WATER TREATMENT POND AREA
7300
POND 2
C
B
A
MT-2-D
POND 3
MT-3-D
MT-3-E
A
B
C
IX PLANT
POND 8
MT-8-F
MT-8-E
A
B
C
MT-8-D
BARIUM CHLORIDE BUILDING
PONDS 6 & 7
POND 5
MT-5-E
A
B
MT-5-D
C
MT-6-B
MT-7-B
MT-6-A
MT-7-A
POND 4
MT-4-D
MT-4-E
A
B
C
MT-4-F
MT-5-F
LEGEND
SAMPLES COLLECTED ARPIL 2012
SAMPLES COLLECTED 2007
NOTE: A BACKGROUND SAMPLE (NOT SHOWN) WAS COLLECTED NEAR THE EASTERN FENCE OF THE BORROW AREA
0
100
200 FT
GRAPHIC SCALE
RIO GRANDE RESOURCES CORPORATION
MOUNT TAYLOR MINE - San Mateo, NM 87020
Prepared By:
Alan Kuhn Associates LLC
FIGURE D.1.1
SOIL SAMPLING LOCATIONS
APRIL 2012 AND 2007




N 1581000
N 1580000
E 2784000
E 2783500
7350
7400
7450
MT-Borrow
Background (2007)
COUNTY RD. 334
Borrow Area A
ORE PAD
LEGEND
SAMPLES COLLECTED ARPIL 2012
SAMPLES COLLECTED 2007
0
100
200 FT
GRAPHIC SCALE
RIO GRANDE RESOURCES CORPORATION
MOUNT TAYLOR MINE - San Mateo, NM 87020
FIGURE D.1.1b
SOIL SAMPLING LOCATIONS
APRIL 2012 AND 2007

Figure D.1.1c

## MT TAYLOR MINE SHAFT MUCK SAMPLE LOCATIONS – 5/18/2010




Bulk samples of shaft muck from Mt. Taylor Mine waste rock pile collected on 5/18/2012 by Alan Kuhn. Locations are approximate (+/- 50 ft) based on visual reference to slopes. Splits delivered 5/18/12 to Kleinfelder Albuquerque for grain size analysis and plasticity tests. Other splits left with RGR Mine office for shipment to Energy Labs for testing of U and Ra concentration.

**TABLE 1**
**Soil Physical Properties Analytical Results - April 2012**
**RIO GRANDE RESOURCES SOIL SAMPLING AND TESTING FOR CLOSEOUT PLAN**
**MT. TAYLOR MINE, SAN MATEO, NEW MEXICO**

| Boring ID | Approximate Collection Depth (inches bgs) | Collection Date | Soil Classification | Atterberg Limits | | Moisture Content (%) |
|---|---|---|---|---|---|---|
| Analytical Method | | | USCS | PI | LL | D2216A |
| | | | | | | |
| MT-WP-SM1 | 0-6 | 4/10/2012 | SC | 24 | 37 | 7.1 |
| MT-WP-SM2 | 0-6 | 4/10/2012 | CL | 27 | 43 | 7.9 |
| MT-WP-SM3 | 0-6 | 4/10/2012 | SC | 21 | 34 | 2.5 |
| BORROW | 24-66 | 4/10/2012 | CL | 13 | 37 | 10.7 |
| MT-1-F | 0-6 | 4/10/2012 | SC | 15 | 35 | 13.7 |
| MT-2-D | 0-6 | 4/10/2012 | CL | 14 | 33 | 16.4 |
| MT-3-F | 0-6 | 4/10/2012 | CL | 17 | 35 | 17.3 |
| MT-4-F | 0-6 | 4/10/2012 | CL | 13 | 34 | 10.5 |
| MT-5-F | 0-6 | 4/10/2012 | CL | 17 | 37 | 17.6 |
| MT-7-C | 0-6 | 4/10/2012 | CL | 17 | 39 | 17.9 |
| MT-8-F | 0-6 | 4/10/2012 | SC | 13 | 27 | 12.9 |
| MT-OP-E | 0-6 | 4/10/2012 | CL | 12 | 31 | 10.3 |

Notes:
bgs = below ground surface
PI = Plastic Index
LL = Liquid Limit

**TABLE 2**
**Soil Chemical Analytical Results - April 2012**
**Total Metals by SW 6010/SW 6020 and Radiochemistry by E903.0/RA-05**
**RIO GRANDE RESOURCES SOIL SAMPLING AND TESTING FOR CLOSEOUT PLAN**
**MT. TAYLOR MINE, SAN MATEO, NEW MEXICO**

| Sample ID | Location | Collection Depth (inches bgs) | Collection Date | Arsenic | Barium | Cadmium | Chromium | Lead | Mercury | Radium 226 | Radium 228 | Selenium | Silver | Uranium |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | CONCENTRATION | | | mg/L | | | | | | pCi/g | pCi/g | mg/L | | |
| Analytical Method | | | | SW 6020 | SW 6010B | SW 6010B | SW 6010B | SW 6020 | SW 7470A | E903.0 | RA-05 | SW 6020 | SW 6020 | SW 6020 |
| NMED SSL DAF 1 | | | | 1.31E-02 | 3.01E+02 | 1.37E+00 | 9.86E+07 | NA | 5.71E-01 | 30[3] | | 9.65E-01 | 1.57E+00 | 4.93E+01 |
| S1-01-01 | MT-1-E | 0-4 | 4/10/2012 | 0.014 | 0.28 | <0.001 | 0.014 B | 0.014 | <0.002 | 124 | 1.8 | 0.26 | <0.002 D | 2.2 D |
| S1-01-02 | MT-1-E | 16-18 | 4/10/2012 | 0.048 | 3.8 | 0.001 | 0.040 B | 0.078 | <0.002 | 113 | 1.3 | 0.49 | <0.002 D | 5.3 D |
| S1-01-03 | MT-1-E | 44-48 | 4/10/2012 | 0.010 | 0.34 | <0.001 | 0.027 B | 0.023 | <0.002 | 12.6 | 0.8 | 0.14 | 0.002 D | 0.094 D |
| S1-02-01 | MT-1-D | 0-4 | 4/10/2012 | 0.023 | 0.39 | <0.001 | 0.014 B | 0.021 | <0.002 | 224 | 2.3 | 0.19 | <0.002 D | 1.5 D |
| S1-02-02 | MT-1-D | 26-30 | 4/10/2012 | 0.003 | <0.05 | <0.001 | 0.007 B | 0.004 | <0.002 | 0.9 | 0.8 | 0.11 | <0.002 D | 0.24 D |
| S1-02-03 | MT-1-D | 44-48 | 4/10/2012 | 0.003 | <0.05 | <0.001 | 0.006 B | 0.003 | <0.002 | 0.6 | 0.6 | 0.012 | <0.002 D | 0.050 D |
| S3-01-01 | MT-3-E | 0-12 | 4/10/2012 | 0.007 | 0.31 | 0.002 | <0.005 | 0.002 | <0.002 | 21.0 | 1.5 | 0.19 | <0.001 | 9.7 B |
| S3-01-02 | MT-3-E | 20-26 | 4/10/2012 | 0.014 | 2.3 | 0.001 | 0.050 | 0.064 | <0.002 | 6.2 | 0.7 | 0.036 | <0.001 | 5.7 B |
| S3-01-03 | MT-3-E | 26-36 | 4/10/2012 | 0.005 | 0.14 | <0.001 | 0.013 | 0.012 | <0.002 | 4.5 | 0.8 | 0.053 | <0.001 | 0.47 B |
| S3-01-04 | MT-3-E | 64-75 | 4/10/2012 | 0.003 | 0.07 | <0.001 | 0.011 | 0.005 | <0.002 | 1.7 | 0.7 | 0.032 | <0.001 | 0.036 B |
| S3-02-01 | MT-3-D | 0-12 | 4/10/2012 | 0.018 | 6.6 | 0.002 | 0.015 | 0.028 | <0.002 | 6.4 | 2.2 | 0.15 | <0.001 | 7.8 B |
| S3-02-02 | MT-3-D | 26-30 | 4/10/2012 | 0.002 | <0.05 | <0.001 | 0.009 | 0.001 | <0.002 | 3.0 | 0.7 | 0.023 | <0.001 | 0.18 B |
| S3-02-03 | MT-3-D | 50-54 | 4/10/2012 | 0.006 | 0.27 | <0.001 | 0.018 | 0.016 | <0.002 | 2.4 | 0.3 | 0.003 | <0.001 | 0.022 B |
| S5-01-01 | MT-5-E | 0-12 | 4/10/2012 | 0.009 | 5.5 | <0.001 | 0.027 B | 0.028 | <0.002 | 11.3 | 0.3 | 0.010 | <0.002 D | 0.11 |
| S5-01-02 | MT-5-E | 36-37 | 4/10/2012 | 0.004 | 0.07 | <0.001 | 0.012 | 0.005 | <0.002 | 1.7 | 0.6 | 0.004 | <0.002 | 0.0054 |
| S5-02-01 | MT-5-D | 0-12 | 4/10/2012 | <0.001 | 0.10 | <0.001 | 0.008 | <0.001 | <0.002 | 0.8 | 0.2 | 0.40 | <0.002 | 1.5 |
| S5-02-02 | MT-5-D | 17-24 | 4/10/2012 | <0.001 | 0.08 | <0.001 | 0.005 | <0.001 | <0.002 | 2.1 | 0.2 | 0.15 | <0.002 | 1.1 |
| S5-02-03 | MT-5-D | 40-44 | 4/10/2012 | 0.006 | 0.62 | <0.001 | 0.017 | 0.013 | <0.002 | 4.1 | 0.5 | 0.012 | <0.002 | 0.011 D |
| S7-01-01 | MT-7-A | 0-12 | 4/10/2012 | 0.004 | 0.06 | <0.001 | 0.005 | <0.001 | <0.002 | 10.4 | 0.1 | 0.26 | <0.002 | 0.37 |
| S7-01-02 | MT-7-A | 24-30 | 4/10/2012 | 0.002 | 0.06 | <0.001 | 0.009 | 0.003 | <0.002 | 1.1 | 0.6 | 0.002 | <0.002 | 0.0047 |
| S7-01-03 | MT-7-A | 30-35 | 4/10/2012 | <0.001 | 0.05 | <0.001 | 0.009 | 0.001 | <0.002 | 1.5 | 0.2 | 0.002 | <0.002 | 0.0049 |
| S7-02-01 | MT-7-B | 0-12 | 4/10/2012 | 0.013 | 0.76 | <0.001 | 0.006 | 0.001 | <0.002 | 2.6 | 0.5 | 0.22 | <0.001 | 0.18 |
| S7-02-02 | MT-7-B | 23-43 | 4/10/2012 | 0.007 | 0.31 | <0.001 | 0.013 | 0.020 | <0.002 | 1.9 | 0.2 | 0.13 | <0.001 | 0.014 |
| S7-02-03 | MT-7-B | 43-46 | 4/10/2012 | 0.003 | 0.16 | <0.001 | 0.010 | 0.005 | <0.002 | 1.1 | 0.3 | 0.003 | <0.001 | 0.0053 |
| S8-01-01 | MT-8-E | 0-8 | 4/10/2012 | 0.008 | 0.91 | <0.001 | 0.012 | 0.009 | <0.002 | 27.2 | 0.2 | 0.007 | <0.002 | 0.016 |
| S8-01-02 | MT-8-E | 17-30 | 4/10/2012 | 0.004 | 0.09 | <0.001 | 0.006 | <0.001 | <0.002 | 2.5 | 0.6 | 0.30 | 0.002 | 3.8 |
| S8-01-03 | MT-8-E | 36-40 | 4/10/2012 | 0.032 | 0.16 | <0.001 | 0.010 | 0.006 | <0.002 | 24.5 | 0.5 | 0.036 | <0.002 | 0.022 |
| S8-02-01 | MT-8-D | 0-12 | 4/10/2012 | 0.004 | 0.12 | <0.001 | 0.009 | 0.005 | <0.002 | 10.6 | 0.1 | 0.22 | <0.002 | 0.12 |
| S8-02-02 | MT-8-D | 18-24 | 4/10/2012 | 0.006 | 0.06 | <0.001 | 0.006 | <0.001 | <0.002 | 1.7 | 1.5 | 1.0 | <0.002 | 6.7 |
| S8-02-03 | MT-8-D | 40-50 | 4/10/2012 | 0.011 | 0.98 | <0.001 | 0.028 | 0.013 | <0.002 | 14.0 | 0.2 | 0.063 | <0.002 | 0.19 |
| S8-02-04 | MT-8-D | 58-62 | 4/10/2012 | 0.004 | 0.15 | <0.001 | 0.011 | 0.005 | <0.002 | 2.0 | 0.6 | <0.001 | <0.002 | 0.0056 D |
| SA-01-01 | MT-A-A | 0-4 | 4/10/2012 | 0.036 | 0.31 | <0.001 | 0.014 B | 0.021 | <0.002 | 152 | 1.8 | 0.046 | <0.002 D | 0.44 D |
| SA-01-02 | MT-A-A | 6-8 | 4/10/2012 | 0.006 | 0.11 | <0.001 | 0.010 B | 0.009 | <0.002 | 8.7 | 0.7 | 0.051 | <0.002 D | 0.45 D |
| SA-01-03 | MT-A-A | 28-30 | 4/10/2012 | 0.003 | <0.05 | <0.001 | 0.005 B | 0.003 | <0.002 | 1.7 | 0.6 | 0.095 | <0.002 D | 0.030 D |
| SA-02-01 | MT-A-B | 0-4 | 4/10/2012 | 0.025 | 0.25 | <0.001 | 0.011 B | 0.010 | <0.002 | 275 | 3.5 | 0.014 | <0.002 D | 0.37 D |
| SA-02-02 | MT-A-B | 8-10 | 4/10/2012 | 0.006 | 0.15 | <0.001 | 0.013 B | 0.010 | <0.002 | 5.4 | 0.7 | 0.003 | <0.002 D | 0.11 D |
| SA-02-03 | MT-A-B | 30-33 | 4/10/2012 | 0.006 | 0.09 | <0.001 | 0.013 B | 0.006 | <0.002 | 29.3 | 1.3 | 0.003 | <0.002 D | 0.088 D |
| MT-1-F (6" B.G.) | MT-1-F | 6 | 4/10/2012 | 0.006 | 0.17 | <0.001 | 0.014 | 0.016 | <0.002 | 2.0 | 0.6 | 0.005 | <0.001 | 0.077 B |
| MT-2-D (6" B.G.) | MT-2-D | 6 | 4/10/2012 | 0.002 | 0.06 | <0.001 | 0.005 | 0.003 | <0.002 | 0.6 | 0.6 | <0.001 | <0.001 | 0.0098 B |
| MT-3-F (6" B.G.) | MT-3-F | 6 | 4/10/2012 | 0.002 | <0.05 | <0.001 | <0.005 | 0.001 | <0.002 | 0.9 | 0.5 | 0.001 | <0.002 D | 0.0090 D |
| MT-4-D-S1 (0-6" B.G.) | MT-4-D | 0-6 | 4/10/2012 | 0.008 | 1.0 | <0.001 | 0.008 | 0.003 | <0.002 | 18.1 | 0.9 | 0.015 | <0.002 D | 0.033 D |
| MT-4-D-S2 (14" B.G.) | MT-4-D | 14 | 4/10/2012 | 0.007 | <0.05 | <0.001 | 0.006 | 0.001 | <0.002 | 2.8 | 0.2 | 0.39 | <0.002 D | 0.20 D |

**TABLE 2**
**Soil Chemical Analytical Results - April 2012**
**Total Metals by SW 6010/SW 6020 and Radiochemistry by E903.0/RA-05**
**RIO GRANDE RESOURCES SOIL SAMPLING AND TESTING FOR CLOSEOUT PLAN**
**MT. TAYLOR MINE, SAN MATEO, NEW MEXICO**

| Sample ID | Location | Collection Depth (inches bgs) | Collection Date | Arsenic | Barium | Cadmium | Chromium | Lead | Mercury | Radium 226 | Radium 228 | Selenium | Silver | Uranium |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | CONCENTRATION | | | mg/L | | | | | | pCi/g | pCi/g | mg/L | | |
| Analytical Method | | | | SW 6020 | SW 6010B | SW 6010B | SW 6010B | SW 6020 | SW 7470A | E903.0 | RA-05 | SW 6020 | SW 6020 | SW 6020 |
| NMED SSL DAF 1 | | | | 1.31E-02 | 3.01E+02 | 1.37E+00 | 9.86E+07 | NA | 5.71E-01 | 30[3] | | 9.65E-01 | 1.57E+00 | 4.93E+01 |
| MT-4-D-S3 (48" B.G.) | **MT-4-D** | 48 | 4/10/2012 | 0.003 | 0.88 | <0.001 | 0.009 | 0.003 | <0.002 | 6.7 | 0.8 | 0.020 | <0.002 D | 0.013 D |
| MT-4-E-S1 (0-4" B.G.) | **MT-4-E** | 0-4 | 4/10/2012 | 0.034 | 34 | <0.001 | 0.007 | 0.008 | <0.002 | 8.7 | 1.5 | 0.15 | <0.002 D | 0.39 D |
| MT-4-E-S2 (10-12" B.G.) | **MT-4-E** | 10-12 | 4/10/2012 | 0.005 | 0.22 | <0.001 | 0.011 | 0.005 | <0.002 | 4.8 | 0.4 | 0.072 | <0.002 D | 0.014 D |
| MT-4-E-S3 (36" B.G.) | **MT-4-E** | 36 | 4/10/2012 | 0.003 | 0.13 | <0.001 | 0.007 | 0.003 | <0.002 | 2.9 | 0.7 | 0.026 | 0.003 D | 0.0043 D |
| MT-4-E-S4 (48" B.G.) | **MT-4-E** | 48 | 4/10/2012 | 0.005 B | 0.06 | <0.001 | 0.006 | 0.002 | <0.002 | 6.2 | 0.4 | 0.011 | <0.001 | 0.027 |
| MT-4-F (6" B.G.) | **MT-4-F** | 6 | 4/10/2012 | 0.005 | <0.05 | <0.001 | <0.005 | 0.003 | <0.002 | 0.8 | 1.0 | 0.002 | <0.002 D | 0.0027 D |
| MT-5-F (6" B.G.) | **MT-5-F** | 6 | 4/10/2012 | 0.002 | <0.05 | <0.001 | <0.005 | 0.001 | <0.002 | 2.0 | 0.8 | 0.001 | 0.003 D | 0.0029 D |
| MT-6-A-S1 (0-5" B.G.) | **MT-6-A** | 0-5 | 4/10/2012 | 0.012 | 7.3 | <0.001 | 0.007 | 0.016 | <0.002 | 6.4 | 0.2 | 0.007 | <0.001 | 0.044 |
| MT-6-A-S2 (12-20" B.G.) | **MT-6-B** | 12-20 | 4/10/2012 | 0.003 B | 0.05 | <0.001 | 0.007 | <0.001 | <0.002 | 0.4 | 0.1 | 0.15 | <0.001 | 0.26 U |
| MT-6-B-S1 (8-10" B.G.) | **MT-6-B** | 8-10 | 4/10/2012 | 0.004 B | 0.05 | <0.001 | 0.007 | <0.001 | <0.002 | 0.8 | 0.2 | 0.16 | <0.001 | 0.26 |
| MT-6-B-S2 (30" B.G.) | **MT-6-B** | 30 | 4/10/2012 | 0.002 B | 0.06 | <0.001 | <0.005 | <0.001 | <0.002 | 4.1 | 0.8 | 0.003 | <0.001 | 0.014 |
| MT-7-C (6" B.G.) | **MT-7-C** | 6 | 4/10/2012 | 0.002 | <0.05 | <0.001 | 0.006 | 0.002 | <0.002 | 0.6 | 0.8 | <0.001 | <0.002 D | 0.0023 D |
| MT-8-F (6" B.G.) | **MT-8-F** | 6 | 4/10/2012 | 0.001 | 0.05 | 0.001 | 0.005 | 0.001 | 0.002 | -1000 | -1000 | 0.001 | 0.002 D | 0.0006 D |
| MT-A-C (6" B.G.) | **MT-A-C** | 6 | 4/10/2012 | 0.003 | <0.05 | <0.001 | <0.005 | 0.001 | <0.002 | 1.7 | 0.5 | 0.044 | <0.002 D | 0.14 |
| MT-Borrow/Background | **MT-Borrow** | 24-66 | 4/10/2012 | 0.001 | <0.05 | <0.001 | <0.005 | <0.001 | <0.002 | 0.7 | 0.7 | 0.001 | <0.002 D | 0.0007 |
| MT-OP-C-S1 (0-6" B.G.) | **MT-OP-C** | 0-6 | 4/10/2012 | 0.015 | 0.05 | <0.001 | 0.010 | 0.001 | <0.002 | 53.3 | 2.1 | 0.052 | <0.001 | 1.8 |
| MT-OP-C-S2 (20" B.G.) | **MT-OP-C** | 20 | 4/10/2012 | 0.005 | 0.05 | <0.001 | 0.007 | 0.002 | <0.002 | 1.7 | 0.6 | 0.018 | <0.002 D | 0.14 |
| MT-OP-C-S3 (48-50' B.G. | **MT-OP-C** | 48-50 | 4/10/2012 | 0.004 | <0.05 | <0.001 | <0.005 | <0.001 | <0.002 | 0.8 | 0.8 | 0.028 | <0.002 D | 0.049 |
| MT-OP-C-S4 (72" B.G.) | **MT-OP-C** | 72 | 4/10/2012 | 0.004 | <0.05 | <0.001 | <0.005 | <0.001 | <0.002 | 1.5 | 0.6 | 0.025 | <0.002 D | 0.0064 |
| MT-OP-D-S1 (0-6" B.G.) | **MT-OP-D** | 0-6 | 4/10/2012 | 0.013 | 1.3 | <0.001 | 0.007 | 0.008 | <0.002 | 51.9 | 0.5 | 0.009 | <0.002 D | 0.23 |
| MT-OP-D-S2 (48-50" B.G. | **MT-OP-D** | 48-50 | 4/10/2012 | 0.001 | 0.05 | <0.001 | <0.005 | <0.001 | <0.002 | 1.9 | 0.6 | 0.005 | <0.002 D | 0.10 |
| MT-OP-D-S3 (76" B.G.) | **MT-OP-D** | 76 | 4/10/2012 | 0.006 | 0.11 | <0.001 | 0.012 | 0.009 | <0.002 | 0.6 | 0.5 | 0.002 | <0.002 D | 0.0034 |
| MT-OP-E (6" B.G.) | **MT-OP-E** | 6 | 4/10/2012 | 0.004 | 0.05 | <0.001 | 0.006 | 0.003 | <0.002 | 1.1 | 0.8 | 0.005 | <0.002 D | 0.0056 |

Notes:
bgs = below ground surface
mg/Kg = milligrams per killogram
DAF=Dilution Attenuation Factor
NA = No DAF values available, NMED 2012, rev6

Total metals concentrations should be compared to background soil sample concentrations before comparing to Soil Screening Levels (SSL). Only metal concentrations above background should be considered for comparison to SSLs.
NMED considers a DAF=20 to be protective of groundwater for a 0.5-acre source. SSL values are included for reference only, as they are applicable for reclamation, not for mines that are active or on stand-by status.
B = The analyte was detected in the method blank.
D = Reporting limit increased due to sample matrix.
U = Not detected at minimum detectable concentration.

**TABLE 3**
**Sediment Analytical Results**
**Cloride and Sulfate Detections - April 2012**
**RIO GRANDE RESOURCES SOIL SAMPLING AND TESTING FOR CLOSEOUT PLAN**
**MT. TAYLOR MINE, SAN MATEO, NEW MEXICO**

| ClientSampID | Location | Sample Interval (inches below grade) | Method | Analyte | Value (mg/kg) | Analyte | Value (mg/kg) |
|---|---|---|---|---|---|---|---|
| **Berms** | | | | | | | |
| | | | | | | | |
| MT-4-F | MT-4-F | 6 | E300.1 | Chloride | 51.2 | Sulfate | 405 |
| MT-5-F | MT-5-F | 6 | E300.2 | Chloride | 37.0 | Sulfate | 183 |
| MT-8F | MT-8F | 6 | E300.3 | Chloride | 14.2 | Sulfate | 28.9 |
| **Ponds** | | | | | | | |
| MT-4-D-S1 | MT-4-D | 0-6 | E300.0 | Chloride | 7.76 | Sulfate | 77 |
| MT-4-D-S2 | MT-4-D | 14 | E300.0 | Chloride | 92.00 | Sulfate | 1840 |
| MT-4-D-S3 | MT-4-D | 48 | E300.0 | Chloride | 6.49 | Sulfate | 132 |
| MT-4-E-S1 | MT-4-E | 0-4 | E300.0 | Chloride | 46.40 | Sulfate | 853 |
| MT-4-E-S2 | MT-4-E | 10-12 | E300.0 | Chloride | 34.10 | Sulfate | 1150 |
| MT-4-E-S3 | MT-4-E | 36 | E300.0 | Chloride | 13.10 | Sulfate | 184 |
| MT-4-E-S4 | MT-4-E | 48 | E300.0 | Chloride | 4.51 | Sulfate | 131 |
| S5-01-01 | MT-5-E | 0-12 | E300.0 | Chloride | 9.64 | Sulfate | 113 |
| S5-01-02 | MT-5-E | 30-37 | E300.0 | Chloride | 7.87 | Sulfate | 261 |
| S5-02-01 | MT-5-D | 0-12 | E300.1 | Chloride | 17.2 | Sulfate | 2860 |
| S5-02-02 | MT-5-D | 17-24 | E300.2 | Chloride | 23.1 | Sulfate | 2530 |
| S5-02-03 | MT-5-D | 40-44 | E300.3 | Chloride | 5.10 | Sulfate | 279 |
| S8-01-01 | MT-8-E | 0-8 | E300.0 | Chloride | 29.3 | Sulfate | 35.3 |
| S8-01-02 | MT-8-E | 17-30 | E300.0 | Chloride | 39.6 | Sulfate | 2750 |
| S8-01-03 | MT-8-E | 36-40 | E300.0 | Chloride | 12.0 | Sulfate | 197 |
| S8-02-01 | MT-8-D | 0-12 | E300.0 | Chloride | 58.6 | Sulfate | 1660 |
| S8-02-02 | MT-8-D | 18-24 | E300.0 | Chloride | 44.6 | Sulfate | 2480 |
| S8-02-03 | MT-8-D | 40-50 | E300.0 | Chloride | 9.13 | Sulfate | 536 |
| S8-02-04 | MT-8-D | 56-62 | E300.0 | Chloride | 3.01 | Sulfate | 31.2 |

# ANALYTICAL SUMMARY REPORT

July 05, 2012

Rio Grande Resources Corporation
PO Box 1150
Grants, NM 87020

Workorder No.: C12040804 Quote ID: C3778 - Mt Taylor Mine Closure Plan

Project Name: Mt. Taylor Mine Closure Plan

Energy Laboratories, Inc. Casper WY received the following 37 samples for Rio Grande Resources Corporation on 4/13/2012 for analysis.

| Sample ID | Client Sample ID | Collect Date | Receive Date | Matrix | Test |
|---|---|---|---|---|---|
| C12040804-001 | S1-01-01 | 04/10/12 10:45 | 04/13/12 | Sediment | Metals, SPLP Extractable<br>Mercury, SPLP<br>Mercury Analysis Prep<br>Filterability<br>Digestion, Total Metals<br>Digestion For RadioChemistry<br>Radium 226<br>Radium 228<br>SPLP Extraction, Regular |
| C12040804-002 | S1-01-02 | 04/10/12 10:50 | 04/13/12 | Sediment | Same As Above |
| C12040804-003 | S1-01-03 | 04/10/12 11:00 | 04/13/12 | Sediment | Same As Above |
| C12040804-004 | S1-02-01 | 04/10/12 11:40 | 04/13/12 | Sediment | Same As Above |
| C12040804-005 | S1-02-02 | 04/10/12 11:43 | 04/13/12 | Sediment | Same As Above |
| C12040804-006 | S1-02-03 | 04/10/12 11:45 | 04/13/12 | Sediment | Same As Above |
| C12040804-007 | SA-01-01 | 04/10/12 11:30 | 04/13/12 | Sediment | Same As Above |
| C12040804-008 | SA-01-02 | 04/10/12 11:35 | 04/13/12 | Sediment | Same As Above |
| C12040804-009 | SA-01-03 | 04/10/12 11:45 | 04/13/12 | Sediment | Same As Above |
| C12040804-010 | SA-02-01 | 04/10/12 11:48 | 04/13/12 | Sediment | Same As Above |
| C12040804-011 | SA-02-02 | 04/10/12 11:48 | 04/13/12 | Sediment | Same As Above |
| C12040804-012 | SA-02-03 | 04/10/12 11:48 | 04/13/12 | Sediment | Same As Above |
| C12040804-013 | S8-01-01 | 04/10/12 13:00 | 04/13/12 | Sediment | Metals, SPLP Extractable<br>Mercury, SPLP<br>Mercury Analysis Prep<br>Filterability<br>E300.0 Anions<br>Digestion, Total Metals<br>Digestion For RadioChemistry<br>DI Water Soil Extract<br>Radium 226<br>Radium 228<br>SPLP Extraction, Regular |
| C12040804-014 | S8-01-02 | 04/10/12 13:09 | 04/13/12 | Sediment | Same As Above |
| C12040804-015 | S8-01-03 | 04/10/12 13:09 | 04/13/12 | Sediment | Same As Above |
| C12040804-016 | S8-02-01 | 04/10/12 13:26 | 04/13/12 | Sediment | Same As Above |

# ANALYTICAL SUMMARY REPORT

| | | | | | |
|---|---|---|---|---|---|
| C12040804-017 | S8-02-02 | 04/10/12 13:36 | 04/13/12 | Sediment | Same As Above |
| C12040804-018 | S8-02-03 | 04/10/12 13:36 | 04/13/12 | Sediment | Same As Above |
| C12040804-019 | S8-02-04 | 04/10/12 13:39 | 04/13/12 | Sediment | Same As Above |
| C12040804-020 | S5-01-01 | 04/10/12 14:05 | 04/13/12 | Sediment | Same As Above |
| C12040804-021 | S7-01-01 | 04/10/12 15:12 | 04/13/12 | Sediment | Metals, SPLP Extractable<br>Mercury, SPLP<br>Mercury Analysis Prep<br>Filterability<br>Digestion, Total Metals<br>Digestion For RadioChemistry<br>Radium 226<br>Radium 228<br>SPLP Extraction, Regular |
| C12040804-022 | S7-01-02 | 04/10/12 15:17 | 04/13/12 | Sediment | Same As Above |
| C12040804-023 | S7-01-03 | 04/10/12 15:22 | 04/13/12 | Sediment | Same As Above |
| C12040804-024 | S5-02-02 | 04/10/12 14:15 | 04/13/12 | Sediment | Metals, SPLP Extractable<br>Mercury, SPLP<br>Mercury Analysis Prep<br>Filterability<br>E300.0 Anions<br>Digestion, Total Metals<br>Digestion For RadioChemistry<br>DI Water Soil Extract<br>Radium 226<br>Radium 228<br>SPLP Extraction, Regular |
| C12040804-025 | S5-02-03 | 04/10/12 14:20 | 04/13/12 | Sediment | Same As Above |
| C12040804-026 | S5-02-01 | 04/10/12 14:30 | 04/13/12 | Sediment | Same As Above |
| C12040804-027 | S5-01-02 | 04/10/12 14:09 | 04/13/12 | Sediment | Same As Above |
| C12040804-028 | S3-01-01 | 04/10/12 9:15 | 04/13/12 | Sediment | Metals, SPLP Extractable<br>Mercury, SPLP<br>Mercury Analysis Prep<br>Filterability<br>Digestion, Total Metals<br>Digestion For RadioChemistry<br>Radium 226<br>Radium 228<br>SPLP Extraction, Regular |
| C12040804-029 | S3-01-02 | 04/10/12 8:50 | 04/13/12 | Sediment | Same As Above |
| C12040804-030 | S3-01-03 | 04/10/12 9:40 | 04/13/12 | Sediment | Same As Above |
| C12040804-031 | S3-02-01 | 04/10/12 10:22 | 04/13/12 | Sediment | Same As Above |
| C12040804-032 | S3-02-02 | 04/10/12 10:30 | 04/13/12 | Sediment | Same As Above |
| C12040804-033 | S3-02-03 | 04/10/12 10:30 | 04/13/12 | Sediment | Same As Above |
| C12040804-034 | S7-02-01 | 04/10/12 15:45 | 04/13/12 | Sediment | Same As Above |
| C12040804-035 | S7-02-02 | 04/10/12 15:50 | 04/13/12 | Sediment | Same As Above |
| C12040804-036 | S7-02-03 | 04/10/12 15:55 | 04/13/12 | Sediment | Same As Above |
| C12040804-037 | S3-01-04 | 04/10/12 9:46 | 04/13/12 | Sediment | Same As Above |

# ANALYTICAL SUMMARY REPORT

The results as reported relate only to the item(s) submitted for testing. The analyses presented in this report were performed at Energy Laboratories, Inc., 2393 Salt Creek Hwy., Casper, WY 82601, unless otherwise noted. Radiochemistry analyses were performed at Energy Laboratories, Inc., 2325 Kerzell Lane, Casper, WY 82601, unless otherwise noted. Any exceptions or problems with the analyses are noted in the Laboratory Analytical Report, the QA/QC Summary Report, or the Case Narrative.

If you have any questions regarding these test results, please call.

Report Approved By:

**CLIENT:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Sample Delivery Group:** C12040804

**Revised Date:** 07/05/12
**Report Date:** 06/13/12

# CASE NARRATIVE

REVISED/SUPPLEMENTAL REPORT
The attached analytical report has been revised from a previously submitted report due to the request by the client for the analysis of Radium 226 and Radium 228 on the Sediment on all samples and Chloride and Sulfate on the Sediment on samples -013 through -020 and -024 through -027. The data presented here is from that analysis.

PREP COMMENTS
The prep hold time for Mercury analysis was exceeded by up to 10.2 days.
The prep hold time for Chloride and Sulfate analysis was exceeded by 38.8 days.

ORIGINAL SAMPLE SUBMITTAL(S)
All original sample submittals have been returned with the data package.

SAMPLE TEMPERATURE COMPLIANCE: 4°C (±2°C)
Temperature of samples received may not be considered properly preserved by accepted standards. Samples that are hand delivered immediately after collection shall be considered acceptable if there is evidence that the chilling process has begun.

GROSS ALPHA ANALYSIS
Method 900.0 for gross alpha and gross beta is intended as a drinking water method for low TDS waters. Data provided by this method for non potable waters should be viewed as inconsistent.

RADON IN AIR ANALYSIS
The desired exposure time is 48 hours (2 days). The time delay in returning the canister to the laboratory for processing should be as short as possible to avoid excessive decay. Maximum recommended delay between end of exposure to beginning of counting should not exceed 8 days.

SOIL/SOLID SAMPLES
All samples reported on an as received basis unless otherwise indicated.

ATRAZINE, SIMAZINE AND PCB ANALYSIS
Data for PCBs, Atrazine and Simazine are reported from EPA 525.2. PCB data reported by ELI reflects the results for seven individual Aroclors. When the results for all seven are ND (not detected), the sample meets EPA compliance criteria for PCB monitoring.

SUBCONTRACTING ANALYSIS
Subcontracting of sample analyses to an outside laboratory may be required. If so, ENERGY LABORATORIES will utilize its branch laboratories or qualified contract laboratories for this service. Any such laboratories will be indicated within the Laboratory Analytical Report.

BRANCH LABORATORY LOCATIONS
eli-b - Energy Laboratories, Inc. - Billings, MT
eli-g - Energy Laboratories, Inc. - Gillette, WY
eli-h - Energy Laboratories, Inc. - Helena, MT
eli-r - Energy Laboratories, Inc. - Rapid City, SD
eli-t - Energy Laboratories, Inc. - College Station, TX

CERTIFICATIONS:
USEPA: WY00002, Radiochemical WY00937; FL-DOH NELAC: E87641, Radiochemical E871017; California: 02118CA; Oregon: WY200001, Radiochemical WY200002; Utah: WY00002; Virginia: 00057; Washington: C836

ISO 17025 DISCLAIMER:
The results of this Analytical Report relate only to the items submitted for analysis.

ENERGY LABORATORIES, INC. - CASPER,WY certifies that certain method selections contained in this report meet requirements as set forth by the above accrediting authorities. Some results requested by the client may not be covered under these certifications. All analysis data to be submitted for regulatory enforcement should be certified in the sample state of origin. Please verify ELI's certification coverage by visiting www.energylab.com

ELI appreciates the opportunity to provide you with this analytical service. For additional information and services visit our web page www.energylab.com.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-001
**Client Sample ID:** S1-01-01

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 10:45
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.014 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:36 / smm |
| Barium | 0.28 | mg/L | | 0.05 | | SW6020 | 04/20/12 13:36 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 13:36 / smm |
| Chromium | 0.014 | mg/L | B | 0.005 | | SW6020 | 04/20/12 13:36 / smm |
| Lead | 0.014 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:36 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 07:52 / rdw |
| Selenium | 0.26 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:36 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 13:36 / smm |
| Uranium | 2.2 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 13:36 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 124 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 precision (±) | 1 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 228 | 1.8 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-002
**Client Sample ID:** S1-01-02

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 10:50
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.048 | mg/L | | 0.001 | | SW6020 | 04/20/12 12:57 / smm |
| Barium | 3.8 | mg/L | | 0.05 | | SW6020 | 04/20/12 12:57 / smm |
| Cadmium | 0.001 | mg/L | | 0.001 | | SW6020 | 04/20/12 12:57 / smm |
| Chromium | 0.040 | mg/L | B | 0.005 | | SW6020 | 04/20/12 12:57 / smm |
| Lead | 0.078 | mg/L | | 0.001 | | SW6020 | 04/20/12 12:57 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 07:56 / rdw |
| Selenium | 0.49 | mg/L | | 0.001 | | SW6020 | 04/20/12 12:57 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 12:57 / smm |
| Uranium | 5.3 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 12:57 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 113 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 precision (±) | 0.9 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 228 | 1.3 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-003
**Client Sample ID:** S1-01-03

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 11:00
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.010 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:14 / smm |
| Barium | 0.34 | mg/L | | 0.05 | | SW6020 | 04/20/12 13:14 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 13:14 / smm |
| Chromium | 0.027 | mg/L | B | 0.005 | | SW6020 | 04/20/12 13:14 / smm |
| Lead | 0.023 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:14 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 07:57 / rdw |
| Selenium | 0.14 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:14 / smm |
| Silver | 0.002 | mg/L | D | 0.002 | | SW6020 | 04/20/12 13:14 / smm |
| Uranium | 0.094 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 13:14 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 12.6 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 228 | 0.8 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-004
**Client Sample ID:** S1-02-01

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 11:40
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.023 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:17 / smm |
| Barium | 0.39 | mg/L | | 0.05 | | SW6020 | 04/20/12 13:17 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 13:17 / smm |
| Chromium | 0.014 | mg/L | B | 0.005 | | SW6020 | 04/20/12 13:17 / smm |
| Lead | 0.021 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:17 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 07:58 / rdw |
| Selenium | 0.19 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:17 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 13:17 / smm |
| Uranium | 1.5 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 13:17 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 224 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 precision (±) | 1.3 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 228 | 2.3 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-005
**Client Sample ID:** S1-02-02

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 11:43
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.003 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:19 / smm |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 04/20/12 13:19 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 13:19 / smm |
| Chromium | 0.007 | mg/L | B | 0.005 | | SW6020 | 04/20/12 13:19 / smm |
| Lead | 0.004 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:19 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:00 / rdw |
| Selenium | 0.11 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:19 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 13:19 / smm |
| Uranium | 0.24 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 13:19 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.9 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 precision (±) | 0.09 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 228 | 0.8 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-006
**Client Sample ID:** S1-02-03

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 11:45
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.003 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:22 / smm |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 04/20/12 13:22 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 13:22 / smm |
| Chromium | 0.006 | mg/L | B | 0.005 | | SW6020 | 04/20/12 13:22 / smm |
| Lead | 0.003 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:22 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:20 / rdw |
| Selenium | 0.012 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:22 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 13:22 / smm |
| Uranium | 0.050 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 13:22 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.6 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 precision (±) | 0.07 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 228 | 0.6 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-007
**Client Sample ID:** SA-01-01

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 11:30
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.036 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:25 / smm |
| Barium | 0.31 | mg/L | | 0.05 | | SW6020 | 04/20/12 13:25 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 13:25 / smm |
| Chromium | 0.014 | mg/L | B | 0.005 | | SW6020 | 04/20/12 13:25 / smm |
| Lead | 0.021 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:25 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:22 / rdw |
| Selenium | 0.046 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:25 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 13:25 / smm |
| Uranium | 0.44 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 13:25 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 152 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 precision (±) | 1.1 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/02/12 22:18 / plj |
| Radium 228 | 1.8 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-008
**Client Sample ID:** SA-01-02

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 11:35
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.006 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:28 / smm |
| Barium | 0.11 | mg/L | | 0.05 | | SW6020 | 04/20/12 13:28 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 13:28 / smm |
| Chromium | 0.010 | mg/L | B | 0.005 | | SW6020 | 04/20/12 13:28 / smm |
| Lead | 0.009 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:28 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:23 / rdw |
| Selenium | 0.051 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:28 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 13:28 / smm |
| Uranium | 0.45 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 13:28 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 8.7 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 precision (±) | 0.4 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 MDC | 0.05 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 228 | 0.7 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-009
**Client Sample ID:** SA-01-03

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 11:45
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.003 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:31 / smm |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 04/20/12 13:31 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 13:31 / smm |
| Chromium | 0.005 | mg/L | B | 0.005 | | SW6020 | 04/20/12 13:31 / smm |
| Lead | 0.003 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:31 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:24 / rdw |
| Selenium | 0.095 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:31 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 13:31 / smm |
| Uranium | 0.030 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 13:31 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.7 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 MDC | 0.05 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 228 | 0.6 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-010
**Client Sample ID:** SA-02-01

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 11:48
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.025 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:33 / smm |
| Barium | 0.25 | mg/L | | 0.05 | | SW6020 | 04/20/12 13:33 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 13:33 / smm |
| Chromium | 0.011 | mg/L | B | 0.005 | | SW6020 | 04/20/12 13:33 / smm |
| Lead | 0.010 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:33 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:26 / rdw |
| Selenium | 0.014 | mg/L | | 0.001 | | SW6020 | 04/20/12 13:33 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 13:33 / smm |
| Uranium | 0.37 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 13:33 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 275 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 precision (±) | 2.0 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 MDC | 0.05 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 228 | 3.5 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-011
**Client Sample ID:** SA-02-02

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 11:48
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.006 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:40 / smm |
| Barium | 0.15 | mg/L | | 0.05 | | SW6020 | 04/20/12 14:40 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 14:40 / smm |
| Chromium | 0.013 | mg/L | B | 0.005 | | SW6020 | 04/20/12 14:40 / smm |
| Lead | 0.010 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:40 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:31 / rdw |
| Selenium | 0.003 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:40 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 14:40 / smm |
| Uranium | 0.11 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 14:40 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 5.4 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 MDC | 0.05 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 228 | 0.7 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-012
**Client Sample ID:** SA-02-03

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 11:48
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.006 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:06 / smm |
| Barium | 0.09 | mg/L | | 0.05 | | SW6020 | 04/20/12 14:06 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 14:06 / smm |
| Chromium | 0.013 | mg/L | B | 0.005 | | SW6020 | 04/20/12 14:06 / smm |
| Lead | 0.006 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:06 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:37 / rdw |
| Selenium | 0.003 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:06 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 14:06 / smm |
| Uranium | 0.088 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 14:06 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 29.3 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 precision (±) | 0.7 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 MDC | 0.05 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 228 | 1.3 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-013
**Client Sample ID:** S8-01-01

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:00
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 29.3 | mg/kg | | 1.00 | | E300.0 | 06/27/12 21:54 / ljl |
| Chloride, 1:1 | 0.827 | meq/L | | 0.0282 | | E300.0 | 06/27/12 21:54 / ljl |
| Sulfate | 35.3 | mg/kg | | 1.00 | | E300.0 | 06/27/12 21:54 / ljl |
| Sulfate, 1:1 | 0.735 | meq/L | | 0.0208 | | E300.0 | 06/27/12 21:54 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.008 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:12 / smm |
| Barium | 0.91 | mg/L | | 0.05 | | SW6020 | 04/20/12 14:12 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 14:12 / smm |
| Chromium | 0.012 | mg/L | B | 0.005 | | SW6020 | 04/20/12 14:12 / smm |
| Lead | 0.009 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:12 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:39 / rdw |
| Selenium | 0.007 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:12 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 14:12 / smm |
| Uranium | 0.016 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 14:12 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 27.2 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 precision (±) | 0.6 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 MDC | 0.04 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 228 | 0.2 | pCi/g-dry | U | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-014
**Client Sample ID:** S8-01-02

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:09
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 38.9 | mg/kg | | 1.00 | | E300.0 | 06/27/12 22:10 / ljl |
| Chloride, 1:1 | 1.10 | meq/L | | 0.0282 | | E300.0 | 06/27/12 22:10 / ljl |
| Sulfate | 2750 | mg/kg | | 1.00 | | E300.0 | 06/28/12 13:59 / ljl |
| Sulfate, 1:1 | 57.2 | meq/L | | 0.0208 | | E300.0 | 06/28/12 13:59 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.004 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:26 / smm |
| Barium | 0.09 | mg/L | | 0.05 | | SW6020 | 04/20/12 14:26 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 14:26 / smm |
| Chromium | 0.006 | mg/L | B | 0.005 | | SW6020 | 04/20/12 14:26 / smm |
| Lead | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 14:26 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:40 / rdw |
| Selenium | 0.30 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:26 / smm |
| Silver | 0.002 | mg/L | D | 0.002 | | SW6020 | 04/20/12 14:26 / smm |
| Uranium | 3.8 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 14:26 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 2.5 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 MDC | 0.05 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 228 | 0.6 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-015
**Client Sample ID:** S8-01-03

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:09
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 12.0 | mg/kg | | 1.00 | | E300.0 | 06/27/12 22:27 / ljl |
| Chloride, 1:1 | 0.340 | meq/L | | 0.0282 | | E300.0 | 06/27/12 22:27 / ljl |
| Sulfate | 197 | mg/kg | | 1.00 | | E300.0 | 06/27/12 22:27 / ljl |
| Sulfate, 1:1 | 4.11 | meq/L | | 0.0208 | | E300.0 | 06/27/12 22:27 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.032 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:29 / smm |
| Barium | 0.16 | mg/L | | 0.05 | | SW6020 | 04/20/12 14:29 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 14:29 / smm |
| Chromium | 0.010 | mg/L | B | 0.005 | | SW6020 | 04/20/12 14:29 / smm |
| Lead | 0.006 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:29 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:41 / rdw |
| Selenium | 0.036 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:29 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 14:29 / smm |
| Uranium | 0.022 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 14:29 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 24.5 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 precision (±) | 0.6 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 MDC | 0.05 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 228 | 0.5 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-016
**Client Sample ID:** S8-02-01

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:26
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 58.6 | mg/kg | | 1.00 | | E300.0 | 06/27/12 22:43 / ljl |
| Chloride, 1:1 | 1.65 | meq/L | | 0.0282 | | E300.0 | 06/27/12 22:43 / ljl |
| Sulfate | 1660 | mg/kg | | 1.00 | | E300.0 | 06/27/12 22:43 / ljl |
| Sulfate, 1:1 | 34.5 | meq/L | | 0.0208 | | E300.0 | 06/27/12 22:43 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.004 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:32 / smm |
| Barium | 0.12 | mg/L | | 0.05 | | SW6020 | 04/20/12 14:32 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 14:32 / smm |
| Chromium | 0.009 | mg/L | B | 0.005 | | SW6020 | 04/20/12 14:32 / smm |
| Lead | 0.005 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:32 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:43 / rdw |
| Selenium | 0.22 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:32 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 14:32 / smm |
| Uranium | 0.12 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 14:32 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 10.6 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 precision (±) | 0.4 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 MDC | 0.05 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 228 | 0.1 | pCi/g-dry | U | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-017
**Client Sample ID:** S8-02-02

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:36
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 44.6 | mg/kg | | 1.00 | | E300.0 | 06/27/12 23:00 / ljl |
| Chloride, 1:1 | 1.26 | meq/L | | 0.0282 | | E300.0 | 06/27/12 23:00 / ljl |
| Sulfate | 2480 | mg/kg | | 1.00 | | E300.0 | 06/27/12 23:00 / ljl |
| Sulfate, 1:1 | 51.7 | meq/L | | 0.0208 | | E300.0 | 06/27/12 23:00 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.006 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:34 / smm |
| Barium | 0.06 | mg/L | | 0.05 | | SW6020 | 04/20/12 14:34 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 14:34 / smm |
| Chromium | 0.006 | mg/L | B | 0.005 | | SW6020 | 04/20/12 14:34 / smm |
| Lead | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 14:34 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:44 / rdw |
| Selenium | 1.0 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:34 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 14:34 / smm |
| Uranium | 6.7 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 14:34 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.7 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 226 MDC | 0.05 | pCi/g-dry | | | | E903.0 | 07/02/12 23:06 / plj |
| Radium 228 | 1.5 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-018
**Client Sample ID:** S8-02-03

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:36
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 9.13 | mg/kg | | 1.00 | | E300.0 | 06/27/12 23:49 / ljl |
| Chloride, 1:1 | 0.258 | meq/L | | 0.0282 | | E300.0 | 06/27/12 23:49 / ljl |
| Sulfate | 536 | mg/kg | | 1.00 | | E300.0 | 06/27/12 23:49 / ljl |
| Sulfate, 1:1 | 11.2 | meq/L | | 0.0208 | | E300.0 | 06/27/12 23:49 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.011 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:37 / smm |
| Barium | 0.98 | mg/L | | 0.05 | | SW6020 | 04/20/12 14:37 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/20/12 14:37 / smm |
| Chromium | 0.028 | mg/L | B | 0.005 | | SW6020 | 04/20/12 14:37 / smm |
| Lead | 0.013 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:37 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:45 / rdw |
| Selenium | 0.063 | mg/L | | 0.001 | | SW6020 | 04/20/12 14:37 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/20/12 14:37 / smm |
| Uranium | 0.19 | mg/L | D | 0.0006 | | SW6020 | 04/20/12 14:37 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 14.0 | pCi/g-dry | | | | E903.0 | 07/03/12 01:58 / plj |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E903.0 | 07/03/12 01:58 / plj |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/03/12 01:58 / plj |
| Radium 228 | 0.2 | pCi/g-dry | U | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 13:54 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-019
**Client Sample ID:** S8-02-04

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:39
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 3.01 | mg/kg | | 1.00 | | E300.0 | 06/28/12 14:14 / ljl |
| Chloride, 1:1 | 0.0850 | meq/L | | 0.0282 | | E300.0 | 06/28/12 14:14 / ljl |
| Sulfate | 31.2 | mg/kg | | 1.00 | | E300.0 | 06/28/12 14:14 / ljl |
| Sulfate, 1:1 | 0.650 | meq/L | | 0.0208 | | E300.0 | 06/28/12 14:14 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.004 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:47 / smm |
| Barium | 0.15 | mg/L | | 0.05 | | SW6020 | 04/26/12 19:47 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:47 / smm |
| Chromium | 0.011 | mg/L | B | 0.005 | | SW6020 | 04/26/12 19:47 / smm |
| Lead | 0.005 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:47 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:53 / rdw |
| Selenium | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:47 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/26/12 19:47 / smm |
| Uranium | 0.0056 | mg/L | D | 0.0006 | | SW6020 | 05/02/12 14:20 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 2.0 | pCi/g-dry | | | | E903.0 | 07/03/12 01:58 / plj |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/03/12 01:58 / plj |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/03/12 01:58 / plj |
| Radium 228 | 0.6 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 12:20 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-020
**Client Sample ID:** S5-01-01

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 14:05
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 9.64 | mg/kg | | 1.00 | | E300.0 | 06/28/12 00:22 / ljl |
| Chloride, 1:1 | 0.272 | meq/L | | 0.0282 | | E300.0 | 06/28/12 00:22 / ljl |
| Sulfate | 113 | mg/kg | | 1.00 | | E300.0 | 06/28/12 00:22 / ljl |
| Sulfate, 1:1 | 2.35 | meq/L | | 0.0208 | | E300.0 | 06/28/12 00:22 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.009 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:13 / smm |
| Barium | 5.5 | mg/L | | 0.05 | | SW6020 | 04/26/12 19:13 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:13 / smm |
| Chromium | 0.027 | mg/L | B | 0.005 | | SW6020 | 04/26/12 19:13 / smm |
| Lead | 0.028 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:13 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:57 / rdw |
| Selenium | 0.010 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:13 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/26/12 19:13 / smm |
| Uranium | 0.11 | mg/L | D | 0.0006 | | SW6020 | 05/02/12 14:00 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 11.3 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 228 | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-021
**Client Sample ID:** S7-01-01

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 15:12
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.004 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:18 / smm |
| Barium | 0.06 | mg/L | | 0.05 | | SW6020 | 04/26/12 19:18 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:18 / smm |
| Chromium | 0.005 | mg/L | B | 0.005 | | SW6020 | 04/26/12 19:18 / smm |
| Lead | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:18 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 08:59 / rdw |
| Selenium | 0.26 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:18 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/26/12 19:18 / smm |
| Uranium | 0.37 | mg/L | D | 0.0006 | | SW6020 | 05/02/12 14:04 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 10.4 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 228 | 0.1 | pCi/g-dry | U | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-022
**Client Sample ID:** S7-01-02

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 15:17
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.002 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:21 / smm |
| Barium | 0.06 | mg/L | | 0.05 | | SW6020 | 04/26/12 19:21 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:21 / smm |
| Chromium | 0.009 | mg/L | B | 0.005 | | SW6020 | 04/26/12 19:21 / smm |
| Lead | 0.003 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:21 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:00 / rdw |
| Selenium | 0.002 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:21 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/26/12 19:21 / smm |
| Uranium | 0.0047 | mg/L | D | 0.0006 | | SW6020 | 05/02/12 14:12 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.1 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 precision (±) | 0.08 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 228 | 0.6 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-023
**Client Sample ID:** S7-01-03

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 15:22
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 16:45 / cp |
| Barium | 0.05 | mg/L | | 0.05 | | SW6020 | 05/01/12 16:45 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 16:45 / cp |
| Chromium | 0.009 | mg/L | B | 0.005 | | SW6020 | 05/01/12 16:45 / cp |
| Lead | 0.001 | mg/L | | 0.001 | | SW6020 | 05/01/12 16:45 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:01 / rdw |
| Selenium | 0.002 | mg/L | | 0.001 | | SW6020 | 05/01/12 16:45 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/01/12 16:45 / cp |
| Uranium | 0.0049 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 16:45 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.5 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 228 | 0.2 | pCi/g-dry | U | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-024
**Client Sample ID:** S5-02-02

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 14:15
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 23.1 | mg/kg | | 1.00 | | E300.0 | 06/28/12 00:38 / ljl |
| Chloride, 1:1 | 0.653 | meq/L | | 0.0282 | | E300.0 | 06/28/12 00:38 / ljl |
| Sulfate | 2530 | mg/kg | | 1.00 | | E300.0 | 06/28/12 00:38 / ljl |
| Sulfate, 1:1 | 52.7 | meq/L | | 0.0208 | | E300.0 | 06/28/12 00:38 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:24 / smm |
| Barium | 0.08 | mg/L | | 0.05 | | SW6020 | 04/26/12 19:24 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:24 / smm |
| Chromium | 0.005 | mg/L | B | 0.005 | | SW6020 | 04/26/12 19:24 / smm |
| Lead | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:24 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:03 / rdw |
| Selenium | 0.15 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:24 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/26/12 19:24 / smm |
| Uranium | 1.1 | mg/L | D | 0.0006 | | SW6020 | 05/02/12 14:14 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 2.1 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 228 | 0.2 | pCi/g-dry | U | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-025
**Client Sample ID:** S5-02-03

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 14:20
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 5.10 | mg/kg | | 1.00 | | E300.0 | 06/28/12 00:55 / ljl |
| Chloride, 1:1 | 0.144 | meq/L | | 0.0282 | | E300.0 | 06/28/12 00:55 / ljl |
| Sulfate | 279 | mg/kg | | 1.00 | | E300.0 | 06/28/12 00:55 / ljl |
| Sulfate, 1:1 | 5.80 | meq/L | | 0.0208 | | E300.0 | 06/28/12 00:55 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.006 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:38 / smm |
| Barium | 0.62 | mg/L | | 0.05 | | SW6020 | 04/26/12 19:38 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:38 / smm |
| Chromium | 0.017 | mg/L | B | 0.005 | | SW6020 | 04/26/12 19:38 / smm |
| Lead | 0.013 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:38 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:04 / rdw |
| Selenium | 0.012 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:38 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/26/12 19:38 / smm |
| Uranium | 0.011 | mg/L | D | 0.0006 | | SW6020 | 05/02/12 14:15 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 4.1 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 228 | 0.5 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-026
**Client Sample ID:** S5-02-01

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 14:30
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 17.2 | mg/kg | | 1.00 | | E300.0 | 06/28/12 01:11 / ljl |
| Chloride, 1:1 | 0.485 | meq/L | | 0.0282 | | E300.0 | 06/28/12 01:11 / ljl |
| Sulfate | 2860 | mg/kg | | 1.00 | | E300.0 | 06/28/12 01:11 / ljl |
| Sulfate, 1:1 | 59.6 | meq/L | | 0.0208 | | E300.0 | 06/28/12 01:11 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:41 / smm |
| Barium | 0.10 | mg/L | | 0.05 | | SW6020 | 04/26/12 19:41 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:41 / smm |
| Chromium | 0.008 | mg/L | B | 0.005 | | SW6020 | 04/26/12 19:41 / smm |
| Lead | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:41 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:08 / rdw |
| Selenium | 0.40 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:41 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/26/12 19:41 / smm |
| Uranium | 1.5 | mg/L | D | 0.0006 | | SW6020 | 05/02/12 14:17 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.8 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 precision (±) | 0.07 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/02/12 23:59 / plj |
| Radium 228 | 0.2 | pCi/g-dry | U | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-027
**Client Sample ID:** S5-01-02

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 14:09
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 7.87 | mg/kg | | 1.00 | | E300.0 | 06/28/12 01:44 / ljl |
| Chloride, 1:1 | 0.222 | meq/L | | 0.0282 | | E300.0 | 06/28/12 01:44 / ljl |
| Sulfate | 261 | mg/kg | | 1.00 | | E300.0 | 06/28/12 01:44 / ljl |
| Sulfate, 1:1 | 5.43 | meq/L | | 0.0208 | | E300.0 | 06/28/12 01:44 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.004 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:44 / smm |
| Barium | 0.07 | mg/L | | 0.05 | | SW6020 | 04/26/12 19:44 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/26/12 19:44 / smm |
| Chromium | 0.012 | mg/L | B | 0.005 | | SW6020 | 04/26/12 19:44 / smm |
| Lead | 0.005 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:44 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:09 / rdw |
| Selenium | 0.004 | mg/L | | 0.001 | | SW6020 | 04/26/12 19:44 / smm |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 04/26/12 19:44 / smm |
| Uranium | 0.0054 | mg/L | D | 0.0006 | | SW6020 | 05/02/12 14:19 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.7 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 228 | 0.6 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
D - RL increased due to sample matrix.
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-028
**Client Sample ID:** S3-01-01

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 09:15
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.007 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:23 / smm |
| Barium | 0.31 | mg/L | | 0.05 | | SW6020 | 04/25/12 20:23 / smm |
| Cadmium | 0.002 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:23 / smm |
| Chromium | ND | mg/L | | 0.005 | | SW6020 | 04/25/12 20:23 / smm |
| Lead | 0.002 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:23 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:15 / rdw |
| Selenium | 0.19 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:23 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 20:23 / smm |
| Uranium | 9.7 | mg/L | B | 0.0003 | | SW6020 | 04/25/12 20:23 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 21.0 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 precision (±) | 0.4 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 228 | 1.5 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-029
**Client Sample ID:** S3-01-02

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 08:50
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.014 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:37 / smm |
| Barium | 2.3 | mg/L | | 0.05 | | SW6020 | 04/25/12 20:37 / smm |
| Cadmium | 0.001 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:37 / smm |
| Chromium | 0.050 | mg/L | | 0.005 | | SW6020 | 04/25/12 20:37 / smm |
| Lead | 0.064 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:37 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:19 / rdw |
| Selenium | 0.036 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:37 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 20:37 / smm |
| Uranium | 5.7 | mg/L | B | 0.0003 | | SW6020 | 04/25/12 20:37 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 6.2 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 228 | 0.7 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-030
**Client Sample ID:** S3-01-03

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 09:40
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.005 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:41 / smm |
| Barium | 0.14 | mg/L | | 0.05 | | SW6020 | 04/25/12 20:41 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 20:41 / smm |
| Chromium | 0.013 | mg/L | | 0.005 | | SW6020 | 04/25/12 20:41 / smm |
| Lead | 0.012 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:41 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:20 / rdw |
| Selenium | 0.053 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:41 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 20:41 / smm |
| Uranium | 0.47 | mg/L | B | 0.0003 | | SW6020 | 04/25/12 20:41 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 4.5 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 228 | 0.8 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-031
**Client Sample ID:** S3-02-01

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 10:22
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.018 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:04 / smm |
| Barium | 6.6 | mg/L | | 0.05 | | SW6020 | 04/25/12 21:04 / smm |
| Cadmium | 0.002 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:04 / smm |
| Chromium | 0.015 | mg/L | | 0.005 | | SW6020 | 04/25/12 21:04 / smm |
| Lead | 0.028 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:04 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:24 / rdw |
| Selenium | 0.15 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:04 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:04 / smm |
| Uranium | 7.8 | mg/L | B | 0.0003 | | SW6020 | 04/25/12 21:04 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 6.4 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 228 | 2.2 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 precision (±) | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-032
**Client Sample ID:** S3-02-02

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 10:30
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.002 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:08 / smm |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 04/25/12 21:08 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:08 / smm |
| Chromium | 0.009 | mg/L | | 0.005 | | SW6020 | 04/25/12 21:08 / smm |
| Lead | 0.001 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:08 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:25 / rdw |
| Selenium | 0.023 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:08 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:08 / smm |
| Uranium | 0.18 | mg/L | B | 0.0003 | | SW6020 | 04/25/12 21:08 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 3.0 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 228 | 0.7 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-033
**Client Sample ID:** S3-02-03

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 10:30
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.006 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:13 / smm |
| Barium | 0.27 | mg/L | | 0.05 | | SW6020 | 04/25/12 21:13 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:13 / smm |
| Chromium | 0.018 | mg/L | | 0.005 | | SW6020 | 04/25/12 21:13 / smm |
| Lead | 0.016 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:13 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:27 / rdw |
| Selenium | 0.003 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:13 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:13 / smm |
| Uranium | 0.022 | mg/L | B | 0.0003 | | SW6020 | 04/25/12 21:13 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 2.4 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 228 | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-034
**Client Sample ID:** S7-02-01

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 15:45
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.013 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:17 / smm |
| Barium | 0.76 | mg/L | | 0.05 | | SW6020 | 04/25/12 21:17 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:17 / smm |
| Chromium | 0.006 | mg/L | | 0.005 | | SW6020 | 04/25/12 21:17 / smm |
| Lead | 0.001 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:17 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:28 / rdw |
| Selenium | 0.22 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:17 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:17 / smm |
| Uranium | 0.18 | mg/L | B | 0.0003 | | SW6020 | 04/25/12 21:17 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 2.6 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 228 | 0.5 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-035
**Client Sample ID:** S7-02-02

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 15:50
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.007 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:22 / smm |
| Barium | 0.31 | mg/L | | 0.05 | | SW6020 | 04/25/12 21:22 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:22 / smm |
| Chromium | 0.013 | mg/L | | 0.005 | | SW6020 | 04/25/12 21:22 / smm |
| Lead | 0.020 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:22 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:29 / rdw |
| Selenium | 0.13 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:22 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:22 / smm |
| Uranium | 0.014 | mg/L | B | 0.0003 | | SW6020 | 04/25/12 21:22 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.9 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 228 | 0.2 | pCi/g-dry | U | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
U - Not detected at minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-036
**Client Sample ID:** S7-02-03

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 15:55
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.003 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:26 / smm |
| Barium | 0.16 | mg/L | | 0.05 | | SW6020 | 04/25/12 21:26 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:26 / smm |
| Chromium | 0.010 | mg/L | | 0.005 | | SW6020 | 04/25/12 21:26 / smm |
| Lead | 0.005 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:26 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:31 / rdw |
| Selenium | 0.003 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:26 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:26 / smm |
| Uranium | 0.0053 | mg/L | B | 0.0003 | | SW6020 | 04/25/12 21:26 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.1 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 precision (±) | 0.09 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 01:40 / plj |
| Radium 228 | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12040804-037
**Client Sample ID:** S3-01-04

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 09:46
**DateReceived:** 04/13/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/18/12 08:51 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.003 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:31 / smm |
| Barium | 0.07 | mg/L | | 0.05 | | SW6020 | 04/25/12 21:31 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:31 / smm |
| Chromium | 0.011 | mg/L | | 0.005 | | SW6020 | 04/25/12 21:31 / smm |
| Lead | 0.005 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:31 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/19/12 09:32 / rdw |
| Selenium | 0.032 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:31 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:31 / smm |
| Uranium | 0.036 | mg/L | B | 0.0003 | | SW6020 | 04/25/12 21:31 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.7 | pCi/g-dry | | | | E903.0 | 07/03/12 03:34 / plj |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/03/12 03:34 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 03:34 / plj |
| Radium 228 | 0.7 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12

**Client:** Rio Grande Resources Corporation **Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan **Work Order:** C12040804

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E300.0** | | | | | | | | | Analytical Run: IC2-C_120626A | |
| **Sample ID: ICV-062612-10** | 2 | Initial Calibration Verification Standard | | | | | | | 06/26/12 15:31 | |
| Chloride | | 9.60 | mg/L | 1.0 | 96 | 90 | 110 | | | |
| Sulfate | | 38.7 | mg/L | 1.0 | 97 | 90 | 110 | | | |
| **Method: E300.0** | | | | | | | | | Batch: 34002 | |
| **Sample ID: MB-34002** | 2 | Method Blank | | | | Run: IC2-C_120626A | | | 06/27/12 21:21 | |
| Chloride | | ND | mg/kg | 1.0 | | | | | | |
| Sulfate | | 0.0820 | mg/kg | 1.0 | | | | | | |
| **Sample ID: LCS1-34002** | 2 | Laboratory Control Sample | | | | Run: IC2-C_120626A | | | 06/27/12 21:37 | |
| Chloride | | 42.9 | mg/kg | 1.0 | 121 | 70 | 130 | | | |
| Sulfate | | 1910 | mg/kg | 1.0 | 105 | 70 | 130 | | | |
| **Sample ID: C12040804-026CPDS** | 2 | Post Digestion/Distillation Spike | | | | Run: IC2-C_120626A | | | 06/28/12 01:27 | |
| Chloride | | 487 | mg/kg | 1.0 | 94 | 80 | 120 | | | |
| Sulfate | | 4670 | mg/kg | 1.0 | 90 | 80 | 120 | | | |
| **Sample ID: C12040804-027CDUP** | 2 | Sample Duplicate | | | | Run: IC2-C_120626A | | | 06/28/12 02:00 | |
| Chloride | | 7.34 | mg/kg | 1.0 | | | | 6.9 | 20 | |
| Sulfate | | 251 | mg/kg | 1.0 | | | | 3.8 | 20 | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12040804

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E903.0** | | | | | | | | | | Batch: 34003 |
| **Sample ID: MB-34003** | 3 | Method Blank | | | | Run: BERTHOLD 770-1_120620B | | | | 07/02/12 22:18 |
| Radium 226 | | 0.003 | pCi/g-dry | | | | | | | U |
| Radium 226 precision (±) | | 0.005 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.007 | pCi/g-dry | | | | | | | |
| **Sample ID: LCS-34003** | | Laboratory Control Sample | | | | Run: BERTHOLD 770-1_120620B | | | | 07/02/12 22:18 |
| Radium 226 | | 2.4 | pCi/g-dry | | 793 | 70 | 130 | | | S |
| - LCS response is outside of the acceptance range for this analysis due to a very small amount of the precipitate from C12040804-001B being transferred to the planchet. Since the MB, MS, and MSD are acceptable the batch is approved. | | | | | | | | | | |
| **Sample ID: C12040804-019BMS** | | Sample Matrix Spike | | | | Run: BERTHOLD 770-1_120620B | | | | 07/03/12 01:58 |
| Radium 226 | | 3.2 | pCi/g-dry | | 83 | 70 | 130 | | | |
| **Sample ID: C12040804-019BMSD** | | Sample Matrix Spike Duplicate | | | | Run: BERTHOLD 770-1_120620B | | | | 07/03/12 01:58 |
| Radium 226 | | 3.3 | pCi/g-dry | | 90 | 70 | 130 | 2.6 | 19.7 | |
| **Method: E903.0** | | | | | | | | | | Batch: 34004 |
| **Sample ID: MB-34004** | 3 | Method Blank | | | | Run: BERTHOLD 770-2_120620A | | | | 07/02/12 23:59 |
| Radium 226 | | 0.1 | pCi/g-dry | | | | | | | |
| Radium 226 precision (±) | | 0.03 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.02 | pCi/g-dry | | | | | | | |
| **Sample ID: LCS-34004** | | Laboratory Control Sample | | | | Run: BERTHOLD 770-2_120620A | | | | 07/02/12 23:59 |
| Radium 226 | | 1.4 | pCi/g-dry | | 87 | 70 | 130 | | | |
| **Sample ID: C12041044-003BMS** | | Sample Matrix Spike | | | | Run: BERTHOLD 770-2_120620A | | | | 07/03/12 03:34 |
| Radium 226 | | 2.5 | pCi/g-dry | | 104 | 70 | 130 | | | |
| **Sample ID: C12041044-003BMSD** | | Sample Matrix Spike Duplicate | | | | Run: BERTHOLD 770-2_120620A | | | | 07/03/12 03:34 |
| Radium 226 | | 2.2 | pCi/g-dry | | 87 | 70 | 130 | 12 | 20.8 | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

U - Not detected at minimum detectable concentration

ND - Not detected at the reporting limit.

S - Spike recovery outside of advisory limits.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Work Order:** C12040804

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: RA-05** | | | | | | | | | | Batch: 34003 |
| **Sample ID: LCS-34003** | | Laboratory Control Sample | | | | Run: TENNELEC-3_120620A | | | | 06/25/12 12:20 |
| Radium 228 | | 1.5 | pCi/g-dry | | 104 | 70 | 130 | | | |
| **Sample ID: MB-34003** | 3 | Method Blank | | | | Run: TENNELEC-3_120620A | | | | 06/25/12 12:20 |
| Radium 228 | | -0.02 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.2 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.3 | pCi/g-dry | | | | | | | |
| **Sample ID: C12040804-019BMS** | | Sample Matrix Spike | | | | Run: TENNELEC-3_120620A | | | | 06/25/12 12:20 |
| Radium 228 | | 2.1 | pCi/g-dry | | 109 | 70 | 130 | | | |
| **Sample ID: C12040804-019BMSD** | | Sample Matrix Spike Duplicate | | | | Run: TENNELEC-3_120620A | | | | 06/25/12 12:20 |
| Radium 228 | | 1.9 | pCi/g-dry | | 94 | 70 | 130 | 10 | 33.9 | |
| **Method: RA-05** | | | | | | | | | | Batch: 34004 |
| **Sample ID: LCS-34004** | | Laboratory Control Sample | | | | Run: TENNELEC-3_120620B | | | | 06/25/12 15:52 |
| Radium 228 | | 1.5 | pCi/g-dry | | 104 | 70 | 130 | | | |
| **Sample ID: MB-34004** | 3 | Method Blank | | | | Run: TENNELEC-3_120620B | | | | 06/25/12 15:52 |
| Radium 228 | | 0.07 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.2 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.3 | pCi/g-dry | | | | | | | |
| **Sample ID: C12041044-003BMS** | | Sample Matrix Spike | | | | Run: TENNELEC-3_120620B | | | | 06/25/12 15:52 |
| Radium 228 | | 1.8 | pCi/g-dry | | 93 | 70 | 130 | | | |
| **Sample ID: C12041044-003BMSD** | | Sample Matrix Spike Duplicate | | | | Run: TENNELEC-3_120620B | | | | 06/25/12 15:52 |
| Radium 228 | | 1.9 | pCi/g-dry | | 101 | 70 | 130 | 6.0 | 33.5 | |

**Qualifiers:**

RL - Analyte reporting limit.
MDC - Minimum detectable concentration
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12040804

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | Analytical Run: ICPMS2-C_120420A | |
| **Sample ID: ICV** | 8 | Initial Calibration Verification Standard | | | | | | | 04/20/12 12:15 | |
| Arsenic | | 0.0502 | mg/L | 0.0010 | 100 | 90 | 110 | | | |
| Barium | | 0.0500 | mg/L | 0.0010 | 100 | 90 | 110 | | | |
| Cadmium | | 0.0501 | mg/L | 0.0010 | 100 | 90 | 110 | | | |
| Chromium | | 0.0508 | mg/L | 0.0010 | 102 | 90 | 110 | | | |
| Lead | | 0.0492 | mg/L | 0.0010 | 98 | 90 | 110 | | | |
| Selenium | | 0.0513 | mg/L | 0.0010 | 103 | 90 | 110 | | | |
| Silver | | 0.0206 | mg/L | 0.0010 | 103 | 90 | 110 | | | |
| Uranium | | 0.0506 | mg/L | 0.00030 | 101 | 90 | 110 | | | |
| **Sample ID: ICSA** | 8 | Interference Check Sample A | | | | | | | 04/20/12 12:18 | |
| Arsenic | | 2.10E-05 | mg/L | 0.0010 | | | | | | |
| Barium | | 2.84E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 4.02E-05 | mg/L | 0.0010 | | | | | | |
| Chromium | | 0.000116 | mg/L | 0.0010 | | | | | | |
| Lead | | 3.52E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | -0.000115 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.000711 | mg/L | 0.0010 | | | | | | |
| Uranium | | 8.01E-05 | mg/L | 0.00030 | | | | | | |
| **Sample ID: ICSAB** | 8 | Interference Check Sample AB | | | | | | | 04/20/12 12:21 | |
| Arsenic | | 0.0101 | mg/L | 0.0010 | 101 | 70 | 130 | | | |
| Barium | | 1.24E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 0.0102 | mg/L | 0.0010 | 102 | 70 | 130 | | | |
| Chromium | | 0.0102 | mg/L | 0.0010 | 102 | 70 | 130 | | | |
| Lead | | 1.20E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | 5.51E-05 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.0101 | mg/L | 0.0010 | 101 | 70 | 130 | | | |
| Uranium | | 2.09E-05 | mg/L | 0.00030 | | | | | | |
| **Method: SW6020** | | | | | | | | | Batch: 33385 | |
| **Sample ID: MB-33385** | 8 | Method Blank | | | | Run: ICPMS2-C_120420A | | | 04/20/12 12:46 | |
| Arsenic | | 0.0007 | mg/L | 6E-05 | | | | | | |
| Barium | | 0.002 | mg/L | 3E-05 | | | | | | |
| Cadmium | | ND | mg/L | 1E-05 | | | | | | |
| Chromium | | 0.005 | mg/L | 4E-05 | | | | | | |
| Lead | | 0.0001 | mg/L | 3E-05 | | | | | | |
| Selenium | | ND | mg/L | 0.0002 | | | | | | |
| Silver | | 0.001 | mg/L | 3E-05 | | | | | | |
| Uranium | | 5E-05 | mg/L | 1E-05 | | | | | | |
| **Sample ID: LCS3-33385** | 8 | Laboratory Control Sample | | | | Run: ICPMS2-C_120420A | | | 04/20/12 12:49 | |
| Arsenic | | 0.47 | mg/L | 0.0010 | 95 | 80 | 120 | | | |
| Barium | | 0.50 | mg/L | 0.050 | 99 | 80 | 120 | | | |
| Cadmium | | 0.24 | mg/L | 0.0010 | 98 | 80 | 120 | | | |
| Chromium | | 0.49 | mg/L | 0.0050 | 98 | 80 | 120 | | | |
| Lead | | 0.51 | mg/L | 0.0010 | 102 | 80 | 120 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

ND - Not detected at the reporting limit.

MDC - Minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12040804

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | | Batch: 33385 |
| **Sample ID: LCS3-33385** | 8 | Laboratory Control Sample | | | | Run: ICPMS2-C_120420A | | | 04/20/12 12:49 | |
| Selenium | | 0.46 | mg/L | 0.0010 | 91 | 80 | 120 | | | |
| Silver | | 0.052 | mg/L | 0.0020 | 101 | 80 | 120 | | | |
| Uranium | | 0.52 | mg/L | 0.00060 | 105 | 80 | 120 | | | |
| **Sample ID: LCSD3-33385** | 8 | Laboratory Control Sample Duplicate | | | | Run: ICPMS2-C_120420A | | | 04/20/12 12:52 | |
| Arsenic | | 0.48 | mg/L | 0.0010 | 96 | 80 | 120 | 1.3 | 20 | |
| Barium | | 0.50 | mg/L | 0.050 | 100 | 80 | 120 | 1.0 | 20 | |
| Cadmium | | 0.25 | mg/L | 0.0010 | 98 | 80 | 120 | 0.7 | 20 | |
| Chromium | | 0.50 | mg/L | 0.0050 | 98 | 80 | 120 | 0.4 | 20 | |
| Lead | | 0.52 | mg/L | 0.0010 | 104 | 80 | 120 | 1.2 | 20 | |
| Selenium | | 0.46 | mg/L | 0.0010 | 92 | 80 | 120 | 1.2 | 20 | |
| Silver | | 0.053 | mg/L | 0.0020 | 105 | 80 | 120 | 3.3 | 20 | |
| Uranium | | 0.53 | mg/L | 0.00060 | 106 | 80 | 120 | 0.9 | 20 | |
| **Sample ID: C12040804-002ADIL** | 8 | Serial Dilution | | | | Run: ICPMS2-C_120420A | | | 04/20/12 13:00 | |
| Arsenic | | 0.052 | mg/L | 0.0050 | | 0 | 0 | 8.3 | 20 | |
| Barium | | 4.0 | mg/L | 0.050 | | 0 | 0 | 5.3 | 20 | |
| Cadmium | | 0.0015 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Chromium | | 0.044 | mg/L | 0.0050 | | 0 | 0 | 9.3 | 20 | |
| Lead | | 0.080 | mg/L | 0.0050 | | 0 | 0 | 1.4 | 20 | |
| Selenium | | 0.57 | mg/L | 0.0050 | | 0 | 0 | 14 | 20 | |
| Silver | | ND | mg/L | 0.010 | | 0 | 0 | | 20 | |
| Uranium | | 5.3 | mg/L | 0.0030 | | 0 | 0 | 1.4 | 20 | |
| **Sample ID: C12040804-001AMS3** | 8 | Sample Matrix Spike | | | | Run: ICPMS2-C_120420A | | | 04/20/12 13:50 | |
| Arsenic | | 0.49 | mg/L | 0.0010 | 96 | 75 | 125 | | | |
| Barium | | 1.8 | mg/L | 0.050 | 303 | 75 | 125 | | | S |
| Cadmium | | 0.25 | mg/L | 0.0010 | 99 | 75 | 125 | | | |
| Chromium | | 0.49 | mg/L | 0.0050 | 96 | 75 | 125 | | | |
| Lead | | 0.57 | mg/L | 0.0010 | 111 | 75 | 125 | | | |
| Selenium | | 0.71 | mg/L | 0.0010 | 90 | 75 | 125 | | | |
| Silver | | 0.054 | mg/L | 0.0020 | 22 | 75 | 125 | | | S |
| Uranium | | 4.5 | mg/L | 0.00060 | | 75 | 125 | | | A |
| **Method: SW6020** | | | | | | | | | | Batch: 33386 |
| **Sample ID: MB-33386** | 8 | Method Blank | | | | Run: ICPMS2-C_120420A | | | 04/20/12 13:56 | |
| Arsenic | | 0.0006 | mg/L | 6E-05 | | | | | | |
| Barium | | 0.003 | mg/L | 3E-05 | | | | | | |
| Cadmium | | 2E-05 | mg/L | 1E-05 | | | | | | |
| Chromium | | 0.006 | mg/L | 4E-05 | | | | | | |
| Lead | | 0.0001 | mg/L | 3E-05 | | | | | | |
| Selenium | | 0.0002 | mg/L | 0.0002 | | | | | | |
| Silver | | 0.0009 | mg/L | 3E-05 | | | | | | |
| Uranium | | 0.0004 | mg/L | 1E-05 | | | | | | |

**Qualifiers:**

RL - Analyte reporting limit.

ND - Not detected at the reporting limit.

A - The analyte level was greater than four times the spike level. In accordance with the method % recovery is not calculated.

MDC - Minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12040804

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | Batch: 33386 | |
| **Sample ID: LCS3-33386** | 8 | Laboratory Control Sample | | | | Run: ICPMS2-C_120420A | | | 04/20/12 13:58 | |
| Arsenic | | 0.49 | mg/L | 0.0010 | 98 | 80 | 120 | | | |
| Barium | | 0.51 | mg/L | 0.050 | 101 | 80 | 120 | | | |
| Cadmium | | 0.25 | mg/L | 0.0010 | 100 | 80 | 120 | | | |
| Chromium | | 0.50 | mg/L | 0.0050 | 100 | 80 | 120 | | | |
| Lead | | 0.52 | mg/L | 0.0010 | 105 | 80 | 120 | | | |
| Selenium | | 0.48 | mg/L | 0.0010 | 95 | 80 | 120 | | | |
| Silver | | 0.054 | mg/L | 0.0020 | 105 | 80 | 120 | | | |
| Uranium | | 0.53 | mg/L | 0.00060 | 106 | 80 | 120 | | | |
| **Sample ID: LCSD3-33386** | 8 | Laboratory Control Sample Duplicate | | | | Run: ICPMS2-C_120420A | | | 04/20/12 14:01 | |
| Arsenic | | 0.49 | mg/L | 0.0010 | 97 | 80 | 120 | 0.2 | 20 | |
| Barium | | 0.51 | mg/L | 0.050 | 102 | 80 | 120 | 0.4 | 20 | |
| Cadmium | | 0.25 | mg/L | 0.0010 | 100 | 80 | 120 | 0.1 | 20 | |
| Chromium | | 0.50 | mg/L | 0.0050 | 100 | 80 | 120 | 0.0 | 20 | |
| Lead | | 0.53 | mg/L | 0.0010 | 105 | 80 | 120 | 0.6 | 20 | |
| Selenium | | 0.48 | mg/L | 0.0010 | 95 | 80 | 120 | 0.2 | 20 | |
| Silver | | 0.055 | mg/L | 0.0020 | 107 | 80 | 120 | 2.1 | 20 | |
| Uranium | | 0.54 | mg/L | 0.00060 | 107 | 80 | 120 | 0.9 | 20 | |
| **Sample ID: C12040804-012ADIL** | 8 | Serial Dilution | | | | Run: ICPMS2-C_120420A | | | 04/20/12 14:09 | |
| Arsenic | | 0.0075 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Barium | | 0.094 | mg/L | 0.050 | | 0 | 0 | 4.2 | 20 | |
| Cadmium | | 0.00049 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Chromium | | 0.013 | mg/L | 0.0050 | | 0 | 0 | 4.1 | 20 | |
| Lead | | 0.0069 | mg/L | 0.0050 | | 0 | 0 | 9.6 | 20 | |
| Selenium | | 0.0044 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Silver | | ND | mg/L | 0.010 | | 0 | 0 | | 20 | |
| Uranium | | 0.086 | mg/L | 0.0030 | | 0 | 0 | 1.5 | 20 | |
| **Sample ID: C12040804-011AMS3** | 8 | Sample Matrix Spike | | | | Run: ICPMS2-C_120420A | | | 04/20/12 14:43 | |
| Arsenic | | 0.49 | mg/L | 0.0010 | 98 | 75 | 125 | | | |
| Barium | | 0.61 | mg/L | 0.050 | 92 | 75 | 125 | | | |
| Cadmium | | 0.25 | mg/L | 0.0010 | 101 | 75 | 125 | | | |
| Chromium | | 0.49 | mg/L | 0.0050 | 95 | 75 | 125 | | | |
| Lead | | 0.53 | mg/L | 0.0010 | 104 | 75 | 125 | | | |
| Selenium | | 0.48 | mg/L | 0.0010 | 96 | 75 | 125 | | | |
| Silver | | 0.053 | mg/L | 0.0020 | 21 | 75 | 125 | | | S |
| Uranium | | 0.62 | mg/L | 0.00060 | 100 | 75 | 125 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

N - The analyte concentration was not sufficiently high to calculate a RPD for the serial dilution test.

S - Spike recovery outside of advisory limits.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12040804

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | Analytical Run: ICPMS2-C_120426A | |
| **Sample ID: ICV** | 7 | Initial Calibration Verification Standard | | | | | | | 04/26/12 16:00 | |
| Arsenic | | 0.0480 | mg/L | 0.0010 | 96 | 90 | 110 | | | |
| Barium | | 0.0492 | mg/L | 0.0010 | 98 | 90 | 110 | | | |
| Cadmium | | 0.0490 | mg/L | 0.0010 | 98 | 90 | 110 | | | |
| Chromium | | 0.0481 | mg/L | 0.0010 | 96 | 90 | 110 | | | |
| Lead | | 0.0491 | mg/L | 0.0010 | 98 | 90 | 110 | | | |
| Selenium | | 0.0483 | mg/L | 0.0010 | 97 | 90 | 110 | | | |
| Silver | | 0.0200 | mg/L | 0.0010 | 100 | 90 | 110 | | | |
| **Sample ID: ICSA** | 7 | Interference Check Sample A | | | | | | | 04/26/12 16:03 | |
| Arsenic | | 7.41E-05 | mg/L | 0.0010 | | | | | | |
| Barium | | 5.47E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 4.03E-05 | mg/L | 0.0010 | | | | | | |
| Chromium | | 7.06E-05 | mg/L | 0.0010 | | | | | | |
| Lead | | 4.98E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | 0.000241 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.000479 | mg/L | 0.0010 | | | | | | |
| **Sample ID: ICSAB** | 7 | Interference Check Sample AB | | | | | | | 04/26/12 16:06 | |
| Arsenic | | 0.0107 | mg/L | 0.0010 | 107 | 70 | 130 | | | |
| Barium | | 2.06E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 0.0108 | mg/L | 0.0010 | 107 | 70 | 130 | | | |
| Chromium | | 0.0106 | mg/L | 0.0010 | 106 | 70 | 130 | | | |
| Lead | | 1.68E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | 0.000166 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.0101 | mg/L | 0.0010 | 101 | 70 | 130 | | | |
| **Method: SW6020** | | | | | | | | | Batch: 33455 | |
| **Sample ID: MB-33455** | 7 | Method Blank | | | | Run: ICPMS2-C_120426A | | | 04/26/12 19:02 | |
| Arsenic | | 0.0002 | mg/L | 6E-05 | | | | | | |
| Barium | | 0.007 | mg/L | 3E-05 | | | | | | |
| Cadmium | | 2E-05 | mg/L | 1E-05 | | | | | | |
| Chromium | | 0.005 | mg/L | 4E-05 | | | | | | |
| Lead | | ND | mg/L | 3E-05 | | | | | | |
| Selenium | | ND | mg/L | 0.0002 | | | | | | |
| Silver | | 0.001 | mg/L | 3E-05 | | | | | | |
| **Sample ID: LCS3-33455** | 7 | Laboratory Control Sample | | | | Run: ICPMS2-C_120426A | | | 04/26/12 19:05 | |
| Arsenic | | 0.46 | mg/L | 0.0010 | 91 | 80 | 120 | | | |
| Barium | | 0.50 | mg/L | 0.050 | 99 | 80 | 120 | | | |
| Cadmium | | 0.23 | mg/L | 0.0010 | 92 | 80 | 120 | | | |
| Chromium | | 0.49 | mg/L | 0.0050 | 96 | 80 | 120 | | | |
| Lead | | 0.51 | mg/L | 0.0010 | 102 | 80 | 120 | | | |
| Selenium | | 0.42 | mg/L | 0.0010 | 83 | 80 | 120 | | | |
| Silver | | 0.050 | mg/L | 0.0020 | 97 | 80 | 120 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

ND - Not detected at the reporting limit.

MDC - Minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12040804

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | | Batch: 33455 |
| **Sample ID: LCSD3-33455** | 7 | Laboratory Control Sample Duplicate | | | | Run: ICPMS2-C_120426A | | | 04/26/12 19:07 | |
| Arsenic | | 0.44 | mg/L | 0.0010 | 89 | 80 | 120 | 2.9 | 20 | |
| Barium | | 0.49 | mg/L | 0.050 | 97 | 80 | 120 | 2.8 | 20 | |
| Cadmium | | 0.23 | mg/L | 0.0010 | 90 | 80 | 120 | 1.6 | 20 | |
| Chromium | | 0.47 | mg/L | 0.0050 | 94 | 80 | 120 | 2.4 | 20 | |
| Lead | | 0.49 | mg/L | 0.0010 | 98 | 80 | 120 | 3.6 | 20 | |
| Selenium | | 0.40 | mg/L | 0.0010 | 80 | 80 | 120 | 3.7 | 20 | |
| Silver | | 0.050 | mg/L | 0.0020 | 96 | 80 | 120 | 1.0 | 20 | |
| **Sample ID: C12040804-020ADIL** | 7 | Serial Dilution | | | | Run: ICPMS2-C_120426A | | | 04/26/12 19:16 | |
| Arsenic | | 0.0094 | mg/L | 0.0050 | | 0 | 0 | 7.4 | 20 | |
| Barium | | 5.7 | mg/L | 0.050 | | 0 | 0 | 4.0 | 20 | |
| Cadmium | | 0.00065 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Chromium | | 0.030 | mg/L | 0.0050 | | 0 | 0 | 11 | 20 | |
| Lead | | 0.027 | mg/L | 0.0050 | | 0 | 0 | 1.5 | 20 | |
| Selenium | | 0.011 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Silver | | ND | mg/L | 0.010 | | 0 | 0 | | 20 | |
| **Sample ID: C12040804-019AMS3** | 7 | Sample Matrix Spike | | | | Run: ICPMS2-C_120426A | | | 04/26/12 19:49 | |
| Arsenic | | 0.45 | mg/L | 0.0010 | 89 | 75 | 125 | | | |
| Barium | | 0.65 | mg/L | 0.050 | 100 | 75 | 125 | | | |
| Cadmium | | 0.23 | mg/L | 0.0010 | 93 | 75 | 125 | | | |
| Chromium | | 0.45 | mg/L | 0.0050 | 87 | 75 | 125 | | | |
| Lead | | 0.51 | mg/L | 0.0010 | 102 | 75 | 125 | | | |
| Selenium | | 0.41 | mg/L | 0.0010 | 81 | 75 | 125 | | | |
| Silver | | 0.049 | mg/L | 0.0020 | 20 | 75 | 125 | | | S |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

N - The analyte concentration was not sufficiently high to calculate a RPD for the serial dilution test.

S - Spike recovery outside of advisory limits.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Work Order:** C12040804

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | Analytical Run: ICPMS2-C_120501A | |
| **Sample ID: ICV** | 8 | Initial Calibration Verification Standard | | | | | | | 05/01/12 13:14 | |
| Arsenic | | 0.0490 | mg/L | 0.0010 | 98 | 90 | 110 | | | |
| Barium | | 0.0486 | mg/L | 0.0010 | 97 | 90 | 110 | | | |
| Cadmium | | 0.0491 | mg/L | 0.0010 | 98 | 90 | 110 | | | |
| Chromium | | 0.0501 | mg/L | 0.0010 | 100 | 90 | 110 | | | |
| Lead | | 0.0483 | mg/L | 0.0010 | 97 | 90 | 110 | | | |
| Selenium | | 0.0501 | mg/L | 0.0010 | 100 | 90 | 110 | | | |
| Silver | | 0.0207 | mg/L | 0.0010 | 103 | 90 | 110 | | | |
| Uranium | | 0.0485 | mg/L | 0.00030 | 97 | 90 | 110 | | | |
| **Sample ID: ICSA** | 8 | Interference Check Sample A | | | | | | | 05/01/12 13:16 | |
| Arsenic | | 0.0103 | mg/L | 0.0010 | | | | | | |
| Barium | | 3.16E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 0.0104 | mg/L | 0.0010 | | | | | | |
| Chromium | | 0.0104 | mg/L | 0.0010 | | | | | | |
| Lead | | 3.39E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | 8.30E-06 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.0108 | mg/L | 0.0010 | | | | | | |
| Uranium | | 6.80E-05 | mg/L | 0.00030 | | | | | | |
| **Sample ID: ICSAB** | 8 | Interference Check Sample AB | | | | | | | 05/01/12 13:19 | |
| Arsenic | | 0.0103 | mg/L | 0.0010 | 103 | 70 | 130 | | | |
| Barium | | 4.64E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 0.0106 | mg/L | 0.0010 | 106 | 70 | 130 | | | |
| Chromium | | 0.0105 | mg/L | 0.0010 | 105 | 70 | 130 | | | |
| Lead | | 3.92E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | 1.39E-05 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.0107 | mg/L | 0.0010 | 107 | 70 | 130 | | | |
| Uranium | | 1.47E-05 | mg/L | 0.00030 | | | | | | |
| **Method: SW6020** | | | | | | | | | Batch: 33487 | |
| **Sample ID: MB-33487** | 8 | Method Blank | | | | Run: ICPMS2-C_120501A | | | 05/01/12 16:23 | |
| Arsenic | | 0.0005 | mg/L | 6E-05 | | | | | | |
| Barium | | 0.008 | mg/L | 3E-05 | | | | | | |
| Cadmium | | 0.0001 | mg/L | 1E-05 | | | | | | |
| Chromium | | 0.006 | mg/L | 4E-05 | | | | | | |
| Lead | | 0.0006 | mg/L | 3E-05 | | | | | | |
| Selenium | | 0.0003 | mg/L | 0.0002 | | | | | | |
| Silver | | 0.001 | mg/L | 3E-05 | | | | | | |
| Uranium | | 0.002 | mg/L | 1E-05 | | | | | | |
| **Sample ID: LCS3-33487** | 8 | Laboratory Control Sample | | | | Run: ICPMS2-C_120501A | | | 05/01/12 16:37 | |
| Arsenic | | 0.48 | mg/L | 0.0010 | 95 | 80 | 120 | | | |
| Barium | | 0.52 | mg/L | 0.050 | 102 | 80 | 120 | | | |
| Cadmium | | 0.25 | mg/L | 0.0010 | 99 | 80 | 120 | | | |
| Chromium | | 0.50 | mg/L | 0.0050 | 98 | 80 | 120 | | | |
| Lead | | 0.52 | mg/L | 0.0010 | 103 | 80 | 120 | | | |

**Qualifiers:**

RL - Analyte reporting limit.
MDC - Minimum detectable concentration
ND - Not detected at the reporting limit.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12040804

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | | Batch: 33487 |
| **Sample ID: LCS3-33487** | 8 | Laboratory Control Sample | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 16:37 |
| Selenium | | 0.45 | mg/L | 0.0010 | 90 | 80 | 120 | | | |
| Silver | | 0.058 | mg/L | 0.0020 | 113 | 80 | 120 | | | |
| Uranium | | 0.52 | mg/L | 0.00060 | 105 | 80 | 120 | | | |
| **Sample ID: LCSD3-33487** | 8 | Laboratory Control Sample Duplicate | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 16:40 |
| Arsenic | | 0.47 | mg/L | 0.0010 | 93 | 80 | 120 | 2.4 | 20 | |
| Barium | | 0.52 | mg/L | 0.050 | 102 | 80 | 120 | 0.7 | 20 | |
| Cadmium | | 0.24 | mg/L | 0.0010 | 97 | 80 | 120 | 2.0 | 20 | |
| Chromium | | 0.49 | mg/L | 0.0050 | 98 | 80 | 120 | 0.3 | 20 | |
| Lead | | 0.51 | mg/L | 0.0010 | 101 | 80 | 120 | 1.6 | 20 | |
| Selenium | | 0.44 | mg/L | 0.0010 | 89 | 80 | 120 | 1.9 | 20 | |
| Silver | | 0.056 | mg/L | 0.0020 | 109 | 80 | 120 | 3.5 | 20 | |
| Uranium | | 0.51 | mg/L | 0.00060 | 102 | 80 | 120 | 2.2 | 20 | |
| **Sample ID: C12040804-023ADIL** | 8 | Serial Dilution | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 16:48 |
| Arsenic | | 0.0014 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Barium | | 0.060 | mg/L | 0.050 | | 0 | 0 | 10 | 20 | |
| Cadmium | | 0.00043 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Chromium | | 0.011 | mg/L | 0.0050 | | 0 | 0 | 19 | 20 | |
| Lead | | 0.0016 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Selenium | | 0.0027 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Silver | | ND | mg/L | 0.010 | | 0 | 0 | | 20 | |
| Uranium | | 0.0056 | mg/L | 0.0030 | | 0 | 0 | 13 | 20 | |
| **Sample ID: C12040804-023AMS3** | 8 | Sample Matrix Spike | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 16:51 |
| Arsenic | | 0.56 | mg/L | 0.0010 | 112 | 75 | 125 | | | |
| Barium | | 0.65 | mg/L | 0.050 | 119 | 75 | 125 | | | |
| Cadmium | | 0.29 | mg/L | 0.0010 | 115 | 75 | 125 | | | |
| Chromium | | 0.57 | mg/L | 0.0050 | 112 | 75 | 125 | | | |
| Lead | | 0.60 | mg/L | 0.0010 | 119 | 75 | 125 | | | |
| Selenium | | 0.53 | mg/L | 0.0010 | 105 | 75 | 125 | | | |
| Silver | | 0.063 | mg/L | 0.0020 | 25 | 75 | 125 | | | S |
| Uranium | | 0.52 | mg/L | 0.00060 | 102 | 75 | 125 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

N - The analyte concentration was not sufficiently high to calculate a RPD for the serial dilution test.

S - Spike recovery outside of advisory limits.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12040804

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method:** **SW6020** | | | | | | | | | Analytical Run: ICPMS2-C_120502A | |
| **Sample ID:** **ICV** | Initial Calibration Verification Standard | | | | | | | | 05/02/12 11:37 | |
| Uranium | | 0.0486 | mg/L | 0.00030 | 97 | 90 | 110 | | | |
| **Method:** **SW6020** | | | | | | | | | Batch: 33505 | |
| **Sample ID:** **MB-33505** | Method Blank | | | | | Run: ICPMS2-C_120502A | | | 05/02/12 13:54 | |
| Uranium | | 0.002 | mg/L | 1E-05 | | | | | | |
| **Sample ID:** **LCS3-33505** | Laboratory Control Sample | | | | | Run: ICPMS2-C_120502A | | | 05/02/12 13:55 | |
| Uranium | | 0.47 | mg/L | 0.00060 | 93 | 80 | 120 | | | |
| **Sample ID:** **LCSD3-33505** | Laboratory Control Sample Duplicate | | | | | Run: ICPMS2-C_120502A | | | 05/02/12 13:57 | |
| Uranium | | 0.48 | mg/L | 0.00060 | 96 | 80 | 120 | 2.7 | 20 | |
| **Sample ID:** **C12040804-020ADIL** | Serial Dilution | | | | | Run: ICPMS2-C_120502A | | | 05/02/12 14:02 | |
| Uranium | | 0.12 | mg/L | 0.0030 | | 0 | 0 | 1.9 | 20 | |
| **Sample ID:** **C12040804-019AMS3** | Sample Matrix Spike | | | | | Run: ICPMS2-C_120502A | | | 05/02/12 14:22 | |
| Uranium | | 0.50 | mg/L | 0.00060 | 98 | 75 | 125 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

ND - Not detected at the reporting limit.

MDC - Minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12
**Report Date:** 06/13/12
**Work Order:** C12040804

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | Analytical Run: ICPMS4-C_120425B | |
| **Sample ID: ICV** | 8 | Initial Calibration Verification Standard | | | | | | | 04/25/12 11:08 | |
| Arsenic | | 0.0486 | mg/L | 0.0010 | 97 | 90 | 110 | | | |
| Barium | | 0.0497 | mg/L | 0.0010 | 99 | 90 | 110 | | | |
| Cadmium | | 0.0501 | mg/L | 0.0010 | 100 | 90 | 110 | | | |
| Chromium | | 0.0491 | mg/L | 0.0010 | 98 | 90 | 110 | | | |
| Lead | | 0.0497 | mg/L | 0.0010 | 99 | 90 | 110 | | | |
| Selenium | | 0.0485 | mg/L | 0.0010 | 97 | 90 | 110 | | | |
| Silver | | 0.0193 | mg/L | 0.0010 | 97 | 90 | 110 | | | |
| Uranium | | 0.0481 | mg/L | 0.00030 | 96 | 90 | 110 | | | |
| **Sample ID: ICSA** | 8 | Interference Check Sample A | | | | | | | 04/25/12 11:12 | |
| Arsenic | | 2.21E-05 | mg/L | 0.0010 | | | | | | |
| Barium | | 2.39E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 4.21E-05 | mg/L | 0.0010 | | | | | | |
| Chromium | | 2.05E-05 | mg/L | 0.0010 | | | | | | |
| Lead | | 1.30E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | 7.84E-05 | mg/L | 0.0010 | | | | | | |
| Silver | | -0.000229 | mg/L | 0.0010 | | | | | | |
| Uranium | | 2.36E-05 | mg/L | 0.00030 | | | | | | |
| **Sample ID: ICSAB** | 8 | Interference Check Sample AB | | | | | | | 04/25/12 11:17 | |
| Arsenic | | 0.0113 | mg/L | 0.0010 | 113 | 70 | 130 | | | |
| Barium | | 1.46E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 0.0109 | mg/L | 0.0010 | 109 | 70 | 130 | | | |
| Chromium | | 0.0115 | mg/L | 0.0010 | 115 | 70 | 130 | | | |
| Lead | | 5.40E-06 | mg/L | 0.0010 | | | | | | |
| Selenium | | 7.00E-07 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.00988 | mg/L | 0.0010 | 99 | 70 | 130 | | | |
| Uranium | | 8.30E-06 | mg/L | 0.00030 | | | | | | |
| **Method: SW6020** | | | | | | | | | Batch: 33440 | |
| **Sample ID: MB-33440** | 8 | Method Blank | | | | Run: ICPMS4-C_120425B | | | 04/25/12 19:38 | |
| Arsenic | | 0.0004 | mg/L | 7E-05 | | | | | | |
| Barium | | 0.01 | mg/L | 0.0001 | | | | | | |
| Cadmium | | 0.0001 | mg/L | 4E-05 | | | | | | |
| Chromium | | ND | mg/L | 0.001 | | | | | | |
| Lead | | 0.0002 | mg/L | 3E-05 | | | | | | |
| Selenium | | 0.0001 | mg/L | 6E-05 | | | | | | |
| Silver | | 0.001 | mg/L | 2E-05 | | | | | | |
| Uranium | | 0.004 | mg/L | 5E-05 | | | | | | |
| **Sample ID: LCS3-33440** | 8 | Laboratory Control Sample | | | | Run: ICPMS4-C_120425B | | | 04/25/12 19:43 | |
| Arsenic | | 0.46 | mg/L | 0.0010 | 91 | 80 | 120 | | | |
| Barium | | 0.50 | mg/L | 0.050 | 98 | 80 | 120 | | | |
| Cadmium | | 0.24 | mg/L | 0.0010 | 97 | 80 | 120 | | | |
| Chromium | | 0.50 | mg/L | 0.0050 | 101 | 80 | 120 | | | |
| Lead | | 0.51 | mg/L | 0.0010 | 103 | 80 | 120 | | | |

**Qualifiers:**

RL - Analyte reporting limit.
MDC - Minimum detectable concentration
ND - Not detected at the reporting limit.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12040804

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | | Batch: 33440 |
| **Sample ID: LCS3-33440** | 8 | Laboratory Control Sample | | | | Run: ICPMS4-C_120425B | | | 04/25/12 19:43 | |
| Selenium | | 0.44 | mg/L | 0.0010 | 87 | 80 | 120 | | | |
| Silver | | 0.053 | mg/L | 0.0010 | 104 | 80 | 120 | | | |
| Uranium | | 0.50 | mg/L | 0.00030 | 99 | 80 | 120 | | | |
| **Sample ID: LCSD3-33440** | 8 | Laboratory Control Sample Duplicate | | | | Run: ICPMS4-C_120425B | | | 04/25/12 20:05 | |
| Arsenic | | 0.47 | mg/L | 0.0010 | 94 | 80 | 120 | 2.8 | 20 | |
| Barium | | 0.50 | mg/L | 0.050 | 99 | 80 | 120 | 1.0 | 20 | |
| Cadmium | | 0.25 | mg/L | 0.0010 | 98 | 80 | 120 | 1.0 | 20 | |
| Chromium | | 0.52 | mg/L | 0.0050 | 104 | 80 | 120 | 3.4 | 20 | |
| Lead | | 0.51 | mg/L | 0.0010 | 103 | 80 | 120 | 0.0 | 20 | |
| Selenium | | 0.44 | mg/L | 0.0010 | 89 | 80 | 120 | 1.5 | 20 | |
| Silver | | 0.054 | mg/L | 0.0010 | 106 | 80 | 120 | 1.7 | 20 | |
| Uranium | | 0.51 | mg/L | 0.00030 | 100 | 80 | 120 | 1.0 | 20 | |
| **Sample ID: C12041044-002ADIL** | 8 | Serial Dilution | | | | Run: ICPMS4-C_120425B | | | 04/25/12 20:19 | |
| Arsenic | | 0.0017 | mg/L | 0.0010 | | 0 | 0 | | 20 | N |
| Barium | | 0.065 | mg/L | 0.050 | | 0 | 0 | 2.8 | 20 | |
| Cadmium | | ND | mg/L | 0.0010 | | 0 | 0 | | 20 | |
| Chromium | | ND | mg/L | 0.011 | | 0 | 0 | | 20 | |
| Lead | | 0.0028 | mg/L | 0.0010 | | 0 | 0 | | 20 | N |
| Selenium | | ND | mg/L | 0.0010 | | 0 | 0 | | 20 | |
| Silver | | ND | mg/L | 0.0010 | | 0 | 0 | | 20 | |
| Uranium | | 0.010 | mg/L | 0.00052 | | 0 | 0 | 5.8 | 20 | |
| **Sample ID: C12040804-028AMS3** | 8 | Sample Matrix Spike | | | | Run: ICPMS4-C_120425B | | | 04/25/12 20:28 | |
| Arsenic | | 0.49 | mg/L | 0.0010 | 97 | 75 | 125 | | | |
| Barium | | 0.77 | mg/L | 0.050 | 91 | 75 | 125 | | | |
| Cadmium | | 0.25 | mg/L | 0.0010 | 101 | 75 | 125 | | | |
| Chromium | | 0.54 | mg/L | 0.0050 | 107 | 75 | 125 | | | |
| Lead | | 0.53 | mg/L | 0.0010 | 105 | 75 | 125 | | | |
| Selenium | | 0.68 | mg/L | 0.0010 | 97 | 75 | 125 | | | |
| Silver | | 0.054 | mg/L | 0.0010 | 22 | 75 | 125 | | | S |
| Uranium | | 11 | mg/L | 0.00030 | | 75 | 125 | | | A |
| **Sample ID: C12041044-001AMS3** | 8 | Sample Matrix Spike | | | | Run: ICPMS4-C_120425B | | | 04/25/12 21:40 | |
| Arsenic | | 0.48 | mg/L | 0.0010 | 94 | 75 | 125 | | | |
| Barium | | 0.68 | mg/L | 0.050 | 102 | 75 | 125 | | | |
| Cadmium | | 0.25 | mg/L | 0.0010 | 98 | 75 | 125 | | | |
| Chromium | | 0.55 | mg/L | 0.0050 | 107 | 75 | 125 | | | |
| Lead | | 0.54 | mg/L | 0.0010 | 105 | 75 | 125 | | | |
| Selenium | | 0.46 | mg/L | 0.0010 | 92 | 75 | 125 | | | |
| Silver | | 0.053 | mg/L | 0.0010 | 21 | 75 | 125 | | | S |
| Uranium | | 0.60 | mg/L | 0.00030 | 104 | 75 | 125 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

ND - Not detected at the reporting limit.

A - The analyte level was greater than four times the spike level. In accordance with the method % recovery is not calculated.

MDC - Minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12040804

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW7470A** | | | | | | | | | | Analytical Run: CVAA_C203_120519A |
| **Sample ID: ICV** | | Initial Calibration Verification Standard | | | | | | | | 05/19/12 07:43 |
| Mercury | | 0.00500 | mg/L | 0.00010 | 100 | 90 | 110 | | | |
| **Method: SW7470A** | | | | | | | | | | Batch: 33699 |
| **Sample ID: MB-33699** | | Method Blank | | | | Run: CVAA_C203_120519A | | | | 05/19/12 07:48 |
| Mercury | | ND | mg/L | 3E-05 | | | | | | |
| **Sample ID: LCS-33699** | | Laboratory Control Sample | | | | Run: CVAA_C203_120519A | | | | 05/19/12 07:49 |
| Mercury | | 0.0052 | mg/L | 0.0020 | 103 | 85 | 115 | | | |
| **Sample ID: LCSD-33699** | | Laboratory Control Sample Duplicate | | | | Run: CVAA_C203_120519A | | | | 05/19/12 07:50 |
| Mercury | | 0.0052 | mg/L | 0.0020 | 104 | 85 | 115 | 0.9 | 10 | |
| **Sample ID: C12040804-001ASD** | | Serial Dilution | | | | Run: CVAA_C203_120519A | | | | 05/19/12 07:53 |
| Mercury | | ND | mg/L | 0.0020 | | | | | 10 | |
| **Sample ID: C12040804-001AMS** | | Sample Matrix Spike | | | | Run: CVAA_C203_120519A | | | | 05/19/12 07:54 |
| Mercury | | 0.0051 | mg/L | 0.0020 | 102 | 85 | 115 | | | |
| **Method: SW7470A** | | | | | | | | | | Batch: 33700 |
| **Sample ID: MB-33700** | | Method Blank | | | | Run: CVAA_C203_120519A | | | | 05/19/12 08:27 |
| Mercury | | ND | mg/L | 3E-05 | | | | | | |
| **Sample ID: LCS-33700** | | Laboratory Control Sample | | | | Run: CVAA_C203_120519A | | | | 05/19/12 08:28 |
| Mercury | | 0.0050 | mg/L | 0.0020 | 100 | 85 | 115 | | | |
| **Sample ID: LCSD-33700** | | Laboratory Control Sample Duplicate | | | | Run: CVAA_C203_120519A | | | | 05/19/12 08:29 |
| Mercury | | 0.0053 | mg/L | 0.0020 | 107 | 85 | 115 | 6.0 | 10 | |
| **Sample ID: C12040804-011ASD** | | Serial Dilution | | | | Run: CVAA_C203_120519A | | | | 05/19/12 08:32 |
| Mercury | | ND | mg/L | 0.0020 | | | | | 10 | |
| **Sample ID: C12040804-011AMS** | | Sample Matrix Spike | | | | Run: CVAA_C203_120519A | | | | 05/19/12 08:36 |
| Mercury | | 0.0050 | mg/L | 0.0020 | 101 | 85 | 115 | | | |
| **Method: SW7470A** | | | | | | | | | | Batch: 33701 |
| **Sample ID: MB-33701** | | Method Blank | | | | Run: CVAA_C203_120519A | | | | 05/19/12 08:47 |
| Mercury | | ND | mg/L | 3E-05 | | | | | | |
| **Sample ID: LCS-33701** | | Laboratory Control Sample | | | | Run: CVAA_C203_120519A | | | | 05/19/12 08:48 |
| Mercury | | 0.0050 | mg/L | 0.0020 | 100 | 85 | 115 | | | |
| **Sample ID: LCSD-33701** | | Laboratory Control Sample Duplicate | | | | Run: CVAA_C203_120519A | | | | 05/19/12 08:52 |
| Mercury | | 0.0050 | mg/L | 0.0020 | 100 | 85 | 115 | 0.0 | 10 | |
| **Sample ID: C12040804-019ASD** | | Serial Dilution | | | | Run: CVAA_C203_120519A | | | | 05/19/12 08:55 |
| Mercury | | ND | mg/L | 0.0020 | | | | | 10 | |
| **Sample ID: C12040804-019AMS** | | Sample Matrix Spike | | | | Run: CVAA_C203_120519A | | | | 05/19/12 08:56 |
| Mercury | | 0.0053 | mg/L | 0.0020 | 105 | 85 | 115 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

ND - Not detected at the reporting limit.

MDC - Minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/05/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12040804

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW7470A** | | | | | | | | | | Batch: 33702 |
| **Sample ID: MB-33702** | | Method Blank | | | | Run: CVAA_C203_120519A | | | | 05/19/12 09:11 |
| Mercury | | ND | mg/L | 3E-05 | | | | | | |
| **Sample ID: LCS-33702** | | Laboratory Control Sample | | | | Run: CVAA_C203_120519A | | | | 05/19/12 09:12 |
| Mercury | | 0.0051 | mg/L | 0.0020 | 103 | 85 | 115 | | | |
| **Sample ID: LCSD-33702** | | Laboratory Control Sample Duplicate | | | | Run: CVAA_C203_120519A | | | | 05/19/12 09:13 |
| Mercury | | 0.0051 | mg/L | 0.0020 | 101 | 85 | 115 | 1.8 | 10 | |
| **Sample ID: C12040804-028ASD** | | Serial Dilution | | | | Run: CVAA_C203_120519A | | | | 05/19/12 09:16 |
| Mercury | | ND | mg/L | 0.0020 | | | | | 10 | |
| **Sample ID: C12040804-028AMS** | | Sample Matrix Spike | | | | Run: CVAA_C203_120519A | | | | 05/19/12 09:17 |
| Mercury | | 0.0052 | mg/L | 0.0020 | 103 | 85 | 115 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

ND - Not detected at the reporting limit.

MDC - Minimum detectable concentration

# Standard Reporting Procedures

Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH, Dissolved Oxygen and Residual Chlorine, are qualified as being analyzed outside of recommended holding time.

Solid/soil samples are reported on a wet weight basis (as received) unless specifically indicated. If moisture corrected, data units are typically noted as –dry. For agricultural and mining soil parameters/characteristics, all samples are dried and ground prior to sample analysis.

---

# Workorder Receipt Checklist

## Rio Grande Resources Corporation C12040804

Login completed by: Kristy Gisse
Date Received: 4/13/2012

Reviewed by: BL2000\tedwards
Received by: kg

Reviewed Date: 4/24/2012
Carrier name: FedEx

| | | | |
|---|---|---|---|
| Shipping container/cooler in good condition? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on shipping container/cooler? | Yes ☐ | No ☐ | Not Present ☑ |
| Custody seals intact on sample bottles? | Yes ☐ | No ☐ | Not Present ☑ |
| Chain of custody present? | Yes ☑ | No ☐ | |
| Chain of custody signed when relinquished and received? | Yes ☑ | No ☐ | |
| Chain of custody agrees with sample labels? | Yes ☑ | No ☐ | |
| Samples in proper container/bottle? | Yes ☑ | No ☐ | |
| Sample containers intact? | Yes ☑ | No ☐ | |
| Sufficient sample volume for indicated test? | Yes ☑ | No ☐ | |
| All samples received within holding time? (Exclude analyses that are considered field parameters such as pH, DO, Res Cl, Sulfite, Ferrous Iron, etc.) | Yes ☑ | No ☐ | |
| Container/Temp Blank temperature: | 18.2°C | | |
| Water - VOA vials have zero headspace? | Yes ☐ | No ☐ | No VOA vials submitted ☑ |
| Water - pH acceptable upon receipt? | Yes ☐ | No ☐ | Not Applicable ☑ |

Contact and Corrective Action Comments:

None

# Chain of Custody and Analytical Request Record

E3888 Page 1 of 4

PLEASE PRINT- Provide as much information as possible.

| | | | |
|---|---|---|---|
| Company Name: Rio Grande Resources Corp | Project Name, PWS, Permit, Etc.: Mt. Taylor Mine Closure Plan | Sample Origin: State: NM | EPA/State Compliance: Yes ☒ No ☐ |
| Report Mail Address: PO Box 1150, Grants, NM 87020. Additional e-mail copy to beverett@kleinfelder.com | Contact Name: Barbara Everett (Kleinfelder) Phone/Fax: (505) 344-7373 (505) 280-1079 (Cell) | Email: beverett@kleinfelder.com | Sampler: (Please Print) Barbara Everett, Ed Loescher |
| Invoice Address: PO Box 1150, Grants, NM 87020 | Invoice Contact & Phone: Jeanette Lister 505-287-7971 | Purchase Order: | Quote/Bottle Order: C3778. Kerry Schoeder 928-235-0515 |

Special Report/Formats – ELI must be notified prior to sample submittal for the following:

☐ DW ☐ GSA ☐ POTW/WWTP ☑ State: NM ☐ Other: _____
☐ A2LA ☒ EDD/EDT (Electronic Data) Format: excel ☐ LEVEL IV ☐ NELAC

Number of Containers. Sample Type: A Air, W Water, S Soils/Solids, V Vegetation, B Bioassay, O Other

ANALYSIS REQUESTED

| SAMPLE IDENTIFICATION (Name, Location, Interval, etc.) | Collection Date | Collection Time | MATRIX | SPLP Extract | RCRA Metals + Uranium | Ra226 & Ra228 | Cl & SO4 by IC 300.0 | ~~TCL~~ BG 4/11/12 | SEE ATTACHED | Normal Turnaround (TAT) |
|---|---|---|---|---|---|---|---|---|---|---|
| 1 S1-01-01 | 4-10-12 | 10:45 | Sediment | X | X | X | | | | X |
| 2 S1-01-02 | 4-10-12 | 10:50 | Sediment | X | X | X | | | | X |
| 3 S1-01-03 | 4-10-12 | 11:00 | Sediment | X | X | X | | | | X |
| 4 S1-02-01 | 4-10-12 | 11:40 | Sediment | X | X | X | | | | X |
| 5 S1-02-02 | 4-10-12 | 11:43 | Sediment | X | X | X | | | | X |
| 6 S1-02-03 | 4-10-12 | 11:45 | Sediment | X | X | X | | | | X |
| 7 SA-01-01 | 4-10-12 | 11:30 | Sediment | X | X | X | | | | X |
| 8 SA-01-02 | 4-10-12 | 11:35 | Sediment | X | X | X | | | | X |
| 9 SA-01-03 | 4-10-12 | 11:45 | Sediment | X | X | X | | | | X |
| 10 SA-02-01 | 4-10-12 | 11:48 | Sediment | X | X | X | | | | X |

RUSH

Contact ELI prior to RUSH sample submittal for charges and scheduling – See Instruction Page

Comments: FED EX TRACK # 8735 9342 9785 (KW)

Shipped by: FED-EX
Cooler ID(s):
Receipt Temp: 18.2 °C
On Ice: Yes (No)
Custody Seal Y (N)
Intact Y N
Signature Match Y N

LABORATORY USE ONLY C12040804

**Custody Record MUST be Signed**

Relinquished by (print): BARBARA EVERETT Date/Time: 4/11/12 12:00 Signature:
Relinquished by (print): KENTON WATTS Date/Time: 4-12-12 @ 0930 Signature:
Sample Disposal: Return to Client: _____ Lab Disposal: X

Received by (print): KENTON WATTS Date/Time: 4-12-12 @ 0700 Signature:
Received by (print): Date/Time: Signature:
Received by Laboratory: Date/Time: Kris 6:55C 4-13-12 9:40 Signature:

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All sub-contract data will be clearly notated on your analytical report.
Visit our web site at www.energylab.com for additional information, downloadable fee schedule, ...

Page 58 of 61

# Chain of Custody and Analytical Request Record

C-3888



**PLEASE PRINT- Provide as much information as possible.**

| | | | |
|---|---|---|---|
| Company Name: Rio Grande Resources Corp | Project Name, PWS, Permit, Etc.: Mt. Taylor Mine Closure Plan | Sample Origin: State: NM | EPA/State Compliance: Yes ☒ No ☐ |
| Report Mail Address: PO Box 1150, Grants, NM 87020. Additional e-mail copy to beverett@kleinfelder.com | Contact Name: Barbara Everett (Kleinfelder) Phone/Fax: (505) 344-7373 (505) 280-1079 (Cell) | Email: beverett@kleinfelder.com | Sampler: (Please Print) Barbara Everett, Ed Loescher |
| Invoice Address: PO Box 1150, Grants, NM 87020 | Invoice Contact & Phone: Jeanette Lister 505-287-7971 | Purchase Order: | Quote/Bottle Order: C3778 |

Special Report/Formats – ELI must be notified prior to sample submittal for the following:

☐ DW ☐ A2LA
☐ GSA ☒ EDD/EDT (Electronic Data)
☐ POTW/WWTP Format: excel
☑ State: NM ☐ LEVEL IV
☐ Other: _____ ☐ NELAC

RUSH — Contact ELI prior to RUSH sample submittal for charges and scheduling – See Instruction Page

Comments: FED EX TRACK # 8735 9342 9785 (KW)

Shipped by: FE-EX
Cooler ID(s):
Receipt Temp: 18.2 °C
On Ice: Yes (No)
Custody Seal Y (N) Intact Y N Signature Match Y N

| SAMPLE IDENTIFICATION (Name, Location, Interval, etc.) | Collection Date | Collection Time | MATRIX | Number of Containers (Sample Type: A Air, W Water, S Soils/Solids, V Vegetation, B Bioassay, O Other) | SPLP Extract | RCRA Metals + Uranium | Ra226 & Ra228 | Cl & SO4 by IC 300.0 | RCI | SEE ATTACHED | Normal Turnaround (TAT) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| ✓ 1 SA-02-02 | 4/10/12 | 11:48 | Sediment | | X | X | X | | | | X |
| ✓ 2 SA-02-03 | 4/10/12 | 11:48 | Sediment | | X | X | X | | | | X |
| ✓ 3 SB-01-01 | 4/10/12 | 13:00 | Sediment | | X | X | X | X | | | X |
| ✓ 4 SB-01-02 | 4/10/12 | 13:09 | Sediment | | X | X | X | X | | | X |
| ✓ 5 SB-01-03 | 4/10/12 | 13:09 | Sediment | | X | X | X | X | | | X |
| ✓ 6 SB-02-01 | 4/10/12 | 13:26 | Sediment | | X | X | X | X | | | X |
| ✓ 7 SB-02-02 | 4/10/12 | 13:36 | Sediment | | X | X | X | X | | | X |
| ✓ 8 SB-02-03 | 4/10/12 | 13:36 | Sediment | | X | X | X | X | | | X |
| ✓ 9 SB-02-04 | 4/10/12 | 13:39 | Sediment | | X | X | X | X | | | X |
| ✓ 10 SS-01-01 | 4/10/12 | 14:05 | Sediment | | X | X | X | X | | | X |

LABORATORY USE ONLY — L12040804

**Custody Record MUST be Signed**

| | | | | |
|---|---|---|---|---|
| Relinquished by (print): BARBARA EVERETT | Date/Time: 4/11/12 12:00 | Signature: | Received by (print): KENTON WATTS | Date/Time: 4-12-12 @ 0700 |
| Relinquished by (print): KENTON WATTS | Date/Time: 4-12-12 @ 0930 | Signature: | Received by (print): | Date/Time: |
| Sample Disposal: Return to Client: _____ Lab Disposal: ✓ | | | Received by Laboratory: | Date/Time: 4-13-12 9:40 |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All sub-contract data will be clearly notated on your analytical report.

# Chain of Custody and Analytical Request Record

C2496



PLEASE PRINT- Provide as much information as possible.

| | | | |
|---|---|---|---|
| Company Name: Rio Grande Resources Corp | Project Name, PWS, Permit, Etc. Mt. Taylor Mine Closure Plan | Sample Origin State: NM | EPA/State Compliance: Yes ☒ No ☐ |
| Report Mail Address: PO Box 1150 Grants, NM 87020 Additional e-mail copy to beverett@kleinfelder.com | Contact Name: Barbara Everett (Kleinfelder) Phone/Fax: (505) 344-7373 (505) 280-1079 (Cell) | Email: beverett@kleinfelder.com | Sampler: (Please Print) Barbara Everett Ed Loescher |
| Invoice Address: PO Box 1150 Grants, NM 87020 | Invoice Contact & Phone: Jeanette Lister 505-287-7971 | Purchase Order: | Quote/Bottle Order: C3778 |

Special Report/Formats – ELI must be notified prior to sample submittal for the following:

- ☐ DW
- ☐ GSA
- ☐ POTW/WWTP
- ☑ State: NM
- ☐ Other: _____
- ☐ A2LA
- ☒ EDD/EDT (Electronic Data) Format: excel
- ☐ LEVEL IV
- ☐ NELAC

Number of Containers
Sample Type: A Air W Water S Soils/Solids V Vegetation B Bioassay O Other

ANALYSIS REQUESTED

| SAMPLE IDENTIFICATION (Name, Location, Interval, etc.) | Collection Date | Collection Time | MATRIX | SPLP Extract | RCRA Metals + Uranium | Ra226 & Ra228 | Cl & SO4 by IC 300.0 | RCL | SEE ATTACHED | Normal Turnaround (TAT) |
|---|---|---|---|---|---|---|---|---|---|---|
| 1 S7-01-01 • | 4/10/12 | 15:12 | Sediment | X | X | X | | | | X |
| 2 S7-01-02 • | 4/10/12 | 15:17 | Sediment | X | X | X | | | | X |
| 3 S7-01-03 • | 4/10/12 | 15:22 | Sediment | X | X | X | | | | X |
| 4 S5-02-02 • | 4/10/12 | 14:15 | Sediment | X | X | X | X | | | X |
| 5 S5-02-03 • | 4/10/12 | 14:20 | Sediment | X | X | X | X | | | X |
| 6 S5-02-01 • | 4/10/12 | 14:30 | Sediment | X | X | X | X | | | X |
| 7 ~~S5-02~~ | | | ~~Sediment~~ | | | | | | | X |
| 8 S5-01-02 • | 4/10/12 | 14:09 | Sediment | X | X | X | X | | | X |
| 9 | | | Sediment | | | | | | | X |
| 10 | | | Sediment | | | | | | | X |

R U S H — Contact ELI prior to **RUSH** sample submittal for charges and scheduling – See Instruction Page

Comments: FEDEX TRACK # 8747 6695 1300

Shipped by: FE-EX

Cooler ID(s):

Receipt Temp 18.2 °C

On Ice: Yes (No)

Custody Seal Y (N)
Intact Y N
Signature Match Y N

LABORATORY USE ONLY

C12040804

**Custody Record MUST be Signed**

| | | | |
|---|---|---|---|
| Relinquished by (print): BARBARA EVERETT | Date/Time: 4/11/12 12:00 | Signature: | Received by (print): KENTON WATTS |
| Relinquished by (print): KENTON WATTS | Date/Time: 4-12-12 @ 0930 | Signature: | Received by (print): |
| Sample Disposal: Return to Client: _____ Lab Disposal: Y | | | Received by Laboratory: 4.13.12 9:40 |

Date/Time: 4-12-12 @ 0700 Signature:

Date/Time: Signature:

Signature:

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All sub-contract data will be clearly notated on your analytical report.

# Chain of Custody and Analytical Request Record

C2496



**PLEASE PRINT- Provide as much information as possible.**

| | | | |
|---|---|---|---|
| Company Name: Rio Grande Resources Corp | Project Name, PWS, Permit, Etc. Mt. Taylor Mine Closure Plan | Sample Origin State: NM | EPA/State Compliance: Yes ☒ No ☐ |
| Report Mail Address: PO Box 1150 Grants, NM 87020 Additional e-mail copy to beverett@kleinfelder.com | Contact Name: Barbara Everett (Kleinfelder) Phone/Fax: (505) 344-7373 (505) 280-1079 (Cell) | Email: beverett@kleinfelder.com | Sampler: (Please Print) Barbara Everett Ed Loescher |
| Invoice Address: PO Box 1150 Grants, NM 87020 | Invoice Contact & Phone: Jeanette Lister 505-287-7971 | Purchase Order: | Quote/Bottle Order: C3778 |

Special Report/Formats – ELI must be notified prior to sample submittal for the following:

- ☐ DW
- ☐ GSA
- ☐ POTW/WWTP
- ☑ State: NM
- ☐ Other: _____
- ☐ A2LA
- ☒ EDD/EDT (Electronic Data) Format: excel
- ☐ LEVEL IV
- ☐ NELAC

Number of Containers
Sample Type: A W S V B O
Air Water Soils/Solids Vegetation Bioassay Other

ANALYSIS REQUESTED

| SAMPLE IDENTIFICATION (Name, Location, Interval, etc.) | Collection Date | Collection Time | MATRIX | SPLP Extract | RCRA Metals + Uranium | Ra226 & Ra228 | Cl & SO4 by IC 300.0 | RCI | | | | | SEE ATTACHED | Normal Turnaround (TAT) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 S3-01-01 • | 4/10/12 | 0915 | Sediment | X | X | X | | | | | | | | X |
| 2 S3-01-02 • | 4/10/12 | 0850 | Sediment | X | X | X | | | | | | | | X |
| 3 S3-01-03 • | 4/10/12 | 0940 | Sediment | X | X | X | | | | | | | | X |
| 4 S3-02-01 • | 4/10/12 | 10:22 | Sediment | X | X | X | | | | | | | | X |
| 5 S3-02-02 | 4/10/12 | 10:30 | Sediment | X | X | X | | | | | | | | X |
| 6 S3-02-03 • (KW PER LABEL, BM) | 4/10/12 | 10:30 | Sediment | X | X | X | | | | | | | | X |
| 7 S7-02-01 • | 4/10/12 | 15:45 | Sediment | X | X | X | | | | | | | | X |
| 8 S7-02-02 • | 4/10/12 | 15:50 | Sediment | X | X | X | | | | | | | | X |
| 9 S7-02-03 • | 4/10/12 | 15:55 | Sediment | X | X | X | | | | | | | | X |
| 10 S3-01-04 • | 4/10/12 | 0946 | Sediment | X | X | X | | | | | | | | X |

**RUSH**

Contact ELI prior to **RUSH** sample submittal for charges and scheduling – See Instruction Page

Comments:

FED EX TRACK # 8747 6695 1300

HOLD PENDING (KW) CONFERM, BY B. EVERETT

Shipped by: FE-Ex

Cooler ID(s):

Receipt Temp: 12.2 °C

On Ice: Yes (No)

Custody Seal Y (N)
Intact Y N
Signature Match Y N

LABORATORY USE ONLY

(1204030)

**Custody Record MUST be Signed**

| | Relinquished by (print): | Date/Time: | Signature: | Received by (print): | Date/Time: | Signature: |
|---|---|---|---|---|---|---|
| 1 | BARBARA EVERETT | 4/11/12 | | KENTON WATTS | 4-12-12 @ 0700 | |
| 2 | KENTON WATTS | 4-12-12 @ 0930 | | Received by (print): | Date/Time: | Signature: |
| | Sample Disposal: Return to Client: _____ | Lab Disposal: X | | Received by Laboratory: | Date/Time: 4-13-12 9:40 | Signature: |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All sub-contract data will be clearly notated on your analytical report.

# ANALYTICAL SUMMARY REPORT

July 10, 2012

Rio Grande Resources Corporation
PO Box 1150
Grants, NM 87020

Workorder No.: C12041044 Quote ID: C3778 - Mt Taylor Mine Closure Plan

Project Name: Mt. Taylor Mine Closure Plan

Energy Laboratories, Inc. Casper WY received the following 28 samples for Rio Grande Resources Corporation on 4/20/2012 for analysis.

| Sample ID | Client Sample ID | Collect Date | Receive Date | Matrix | Test |
|---|---|---|---|---|---|
| C12041044-001 | MT-1-F (6" B.G.) | 04/10/12 10:45 | 04/20/12 | Sediment | Metals, SPLP Extractable<br>Mercury, SPLP<br>Mercury Analysis Prep<br>Filterability<br>Digestion, Total Metals<br>Digestion For RadioChemistry<br>Radium 226<br>Radium 228<br>SPLP Extraction, Regular |
| C12041044-002 | MT-2-D (6" B.G.) | 04/10/12 10:15 | 04/20/12 | Sediment | Same As Above |
| C12041044-003 | MT-3-F (6" B.G.) | 04/10/12 11:10 | 04/20/12 | Sediment | Same As Above |
| C12041044-004 | MT-4-F (6" B.G.) | 04/10/12 9:35 | 04/20/12 | Sediment | Metals, SPLP Extractable<br>Mercury, SPLP<br>Mercury Analysis Prep<br>Filterability<br>E300.0 Anions<br>Digestion, Total Metals<br>Digestion For RadioChemistry<br>DI Water Soil Extract<br>Radium 226<br>Radium 228<br>SPLP Extraction, Regular |
| C12041044-005 | MT-5-F (6" B.G.) | 04/10/12 10:00 | 04/20/12 | Sediment | Same As Above |
| C12041044-006 | MT-7-C (6" B.G.) | 04/10/12 9:45 | 04/20/12 | Sediment | Metals, SPLP Extractable<br>Mercury, SPLP<br>Mercury Analysis Prep<br>Filterability<br>Digestion, Total Metals<br>Digestion For RadioChemistry<br>Radium 226<br>Radium 228<br>SPLP Extraction, Regular |
| C12041044-007 | MT-OP-E (6" B.G.) | 04/10/12 9:00 | 04/20/12 | Sediment | Same As Above |
| C12041044-008 | MT-A-C (6" B.G.) | 04/10/12 10:55 | 04/20/12 | Sediment | Same As Above |
| C12041044-009 | MT-Borrow/Background | 04/10/12 11:00 | 04/20/12 | Sediment | Same As Above |

# ANALYTICAL SUMMARY REPORT

| | | | | | |
|---|---|---|---|---|---|
| C12041044-010 | MT-4-D-S1 (0-6" B.G.) | 04/10/12 14:05 | 04/20/12 | Sediment | Metals, SPLP Extractable<br>Mercury, SPLP<br>Mercury Analysis Prep<br>Filterability<br>E300.0 Anions<br>Digestion, Total Metals<br>Digestion For RadioChemistry<br>DI Water Soil Extract<br>Radium 226<br>Radium 228<br>SPLP Extraction, Regular |
| C12041044-011 | MT-4-D-S2 (14" B.G.) | 04/10/12 14:10 | 04/20/12 | Sediment | Same As Above |
| C12041044-012 | MT-4-D-S3 (48" B.G.) | 04/10/12 14:20 | 04/20/12 | Sediment | Same As Above |
| C12041044-013 | MT-4-E-S1 (0-4" B.G.) | 04/10/12 13:35 | 04/20/12 | Sediment | Same As Above |
| C12041044-014 | MT-4-E-S2 (10-12" B.G.) | 04/10/12 13:40 | 04/20/12 | Sediment | Same As Above |
| C12041044-015 | MT-4-E-S3 (36" B.G.) | 04/10/12 13:42 | 04/20/12 | Sediment | Same As Above |
| C12041044-016 | MT-4-E-S4 (48" B.G.) | 04/10/12 13:45 | 04/20/12 | Sediment | Same As Above |
| C12041044-017 | MT-6-A-S1 (0-5" B.G.) | 04/10/12 15:05 | 04/20/12 | Sediment | Metals, SPLP Extractable<br>Mercury, SPLP<br>Mercury Analysis Prep<br>Filterability<br>Digestion, Total Metals<br>Digestion For RadioChemistry<br>Radium 226<br>Radium 228<br>SPLP Extraction, Regular |
| C12041044-018 | MT-6-A-S2 (12-20" B.G.) | 04/10/12 15:10 | 04/20/12 | Sediment | Same As Above |
| C12041044-019 | MT-6-B-S1 (8-10" B.G.) | 04/10/12 14:30 | 04/20/12 | Sediment | Same As Above |
| C12041044-020 | MT-6-B-S2 (30" B.G.) | 04/10/12 14:35 | 04/20/12 | Sediment | Same As Above |
| C12041044-021 | MT-OP-C-S1 (0-6" B.G.) | 04/10/12 13:20 | 04/20/12 | Sediment | Same As Above |
| C12041044-022 | MT-OP-C-S2 (20" B.G.) | 04/10/12 13:25 | 04/20/12 | Sediment | Same As Above |
| C12041044-023 | MT-OP-C-S3 (48-50' B.G.) | 04/10/12 13:25 | 04/20/12 | Sediment | Same As Above |
| C12041044-024 | MT-OP-C-S4 (72" B.G.) | 04/10/12 13:30 | 04/20/12 | Sediment | Same As Above |
| C12041044-025 | MT-OP-D-S1 (0-6" B.G.) | 04/10/12 12:45 | 04/20/12 | Sediment | Same As Above |
| C12041044-026 | MT-OP-D-S2 (48-50" B.G.) | 04/10/12 12:45 | 04/20/12 | Sediment | Same As Above |
| C12041044-027 | MT-OP-D-S3 (76" B.G.) | 04/10/12 12:50 | 04/20/12 | Sediment | Same As Above |
| C12041044-028 | MT-8-F (6" B.G.) | 04/10/12 9:25 | 04/20/12 | Sediment | Metals, SPLP Extractable<br>Mercury, SPLP<br>Mercury Analysis Prep<br>Filterability<br>E300.0 Anions<br>Digestion, Total Metals<br>Digestion For RadioChemistry<br>DI Water Soil Extract<br>Radium 226<br>Radium 228<br>SPLP Extraction, Regular |

# ANALYTICAL SUMMARY REPORT

The results as reported relate only to the item(s) submitted for testing. The analyses presented in this report were performed at Energy Laboratories, Inc., 2393 Salt Creek Hwy., Casper, WY 82601, unless otherwise noted. Radiochemistry analyses were performed at Energy Laboratories, Inc., 2325 Kerzell Lane, Casper, WY 82601, unless otherwise noted. Any exceptions or problems with the analyses are noted in the Laboratory Analytical Report, the QA/QC Summary Report, or the Case Narrative.

If you have any questions regarding these test results, please call.

Report Approved By:

**CLIENT:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Sample Delivery Group:** C12041044

**Revised Date:** 07/10/12
**Report Date:** 06/13/12

# CASE NARRATIVE

REVISED/SUPPLEMENTAL REPORT
The attached analytical report has been revised from a previously submitted report due to the request by the client for the analysis of Radium 226 and Radium 228 on the Sediment on all samples and Chloride and Sulfate on the Sediment on samples -004 through -005, -010 through -016, and -028. The data presented here is from that analysis.

PREP COMMENTS
The prep hold time for the SPLP extraction was exceeded by up to 6 days.
The prep hold time for Chloride and Sulfate analysis was exceeded by 39 days.

ORIGINAL SAMPLE SUBMITTAL(S)
All original sample submittals have been returned with the data package.

SAMPLE TEMPERATURE COMPLIANCE: 4°C (±2°C)
Temperature of samples received may not be considered properly preserved by accepted standards. Samples that are hand delivered immediately after collection shall be considered acceptable if there is evidence that the chilling process has begun.

GROSS ALPHA ANALYSIS
Method 900.0 for gross alpha and gross beta is intended as a drinking water method for low TDS waters. Data provided by this method for non potable waters should be viewed as inconsistent.

RADON IN AIR ANALYSIS
The desired exposure time is 48 hours (2 days). The time delay in returning the canister to the laboratory for processing should be as short as possible to avoid excessive decay. Maximum recommended delay between end of exposure to beginning of counting should not exceed 8 days.

SOIL/SOLID SAMPLES
All samples reported on an as received basis unless otherwise indicated.

ATRAZINE, SIMAZINE AND PCB ANALYSIS
Data for PCBs, Atrazine and Simazine are reported from EPA 525.2. PCB data reported by ELI reflects the results for seven individual Aroclors. When the results for all seven are ND (not detected), the sample meets EPA compliance criteria for PCB monitoring.

SUBCONTRACTING ANALYSIS
Subcontracting of sample analyses to an outside laboratory may be required. If so, ENERGY LABORATORIES will utilize its branch laboratories or qualified contract laboratories for this service. Any such laboratories will be indicated within the Laboratory Analytical Report.

BRANCH LABORATORY LOCATIONS
eli-b - Energy Laboratories, Inc. - Billings, MT
eli-g - Energy Laboratories, Inc. - Gillette, WY
eli-h - Energy Laboratories, Inc. - Helena, MT
eli-r - Energy Laboratories, Inc. - Rapid City, SD
eli-t - Energy Laboratories, Inc. - College Station, TX

CERTIFICATIONS:
USEPA: WY00002, Radiochemical WY00937; FL-DOH NELAC: E87641, Radiochemical E871017; California: 02118CA; Oregon: WY200001, Radiochemical WY200002; Utah: WY00002; Virginia: 00057; Washington: C836

ISO 17025 DISCLAIMER:
The results of this Analytical Report relate only to the items submitted for analysis.

ENERGY LABORATORIES, INC. - CASPER,WY certifies that certain method selections contained in this report meet requirements as set forth by the above accrediting authorities. Some results requested by the client may not be covered under these certifications. All analysis data to be submitted for regulatory enforcement should be certified in the sample state of origin. Please verify ELI's certification coverage by visiting www.energylab.com

ELI appreciates the opportunity to provide you with this analytical service. For additional information and services visit our web page www.energylab.com.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-001
**Client Sample ID:** MT-1-F (6" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 10:45
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.006 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:35 / smm |
| Barium | 0.17 | mg/L | | 0.05 | | SW6020 | 04/25/12 21:35 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:35 / smm |
| Chromium | 0.014 | mg/L | | 0.005 | | SW6020 | 04/25/12 21:35 / smm |
| Lead | 0.016 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:35 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/26/12 12:36 / rdw |
| Selenium | 0.005 | mg/L | | 0.001 | | SW6020 | 04/25/12 21:35 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 21:35 / smm |
| Uranium | 0.077 | mg/L | B | 0.0003 | | SW6020 | 04/25/12 21:35 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 2.0 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 228 | 0.6 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-002
**Client Sample ID:** MT-2-D (6" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 10:15
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.002 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:14 / smm |
| Barium | 0.06 | mg/L | | 0.05 | | SW6020 | 04/25/12 20:14 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 20:14 / smm |
| Chromium | 0.005 | mg/L | | 0.005 | | SW6020 | 04/25/12 20:14 / smm |
| Lead | 0.003 | mg/L | | 0.001 | | SW6020 | 04/25/12 20:14 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/26/12 12:43 / rdw |
| Selenium | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 20:14 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 04/25/12 20:14 / smm |
| Uranium | 0.0098 | mg/L | B | 0.0003 | | SW6020 | 04/25/12 20:14 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.6 | pCi/g-dry | | | | E903.0 | 07/03/12 03:34 / plj |
| Radium 226 precision (±) | 0.07 | pCi/g-dry | | | | E903.0 | 07/03/12 03:34 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 03:34 / plj |
| Radium 228 | 0.6 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 17:32 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-003
**Client Sample ID:** MT-3-F (6" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 11:10
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.002 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:24 / cp |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 05/01/12 14:24 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 14:24 / cp |
| Chromium | ND | mg/L | | 0.005 | | SW6020 | 05/01/12 14:24 / cp |
| Lead | 0.001 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:24 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:16 / rdw |
| Selenium | 0.001 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:24 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/01/12 14:24 / cp |
| Uranium | 0.0090 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 14:24 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.9 | pCi/g-dry | | | | E903.0 | 07/03/12 03:34 / plj |
| Radium 226 precision (±) | 0.08 | pCi/g-dry | | | | E903.0 | 07/03/12 03:34 / plj |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 03:34 / plj |
| Radium 228 | 0.5 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |
| Radium 228 MDC | 0.3 | pCi/g-dry | | | | RA-05 | 06/25/12 15:52 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-004
**Client Sample ID:** MT-4-F (6" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 09:35
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 51.2 | mg/kg | | 1.00 | | E300.0 | 06/28/12 03:22 / ljl |
| Chloride, 1:1 | 1.44 | meq/L | | 0.0282 | | E300.0 | 06/28/12 03:22 / ljl |
| Sulfate | 405 | mg/kg | | 1.00 | | E300.0 | 06/28/12 03:22 / ljl |
| Sulfate, 1:1 | 8.43 | meq/L | | 0.0208 | | E300.0 | 06/28/12 03:22 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.005 | mg/L | | 0.001 | | SW6020 | 05/01/12 13:55 / cp |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 05/01/12 13:55 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 13:55 / cp |
| Chromium | ND | mg/L | | 0.005 | | SW6020 | 05/02/12 21:42 / smm |
| Lead | 0.003 | mg/L | | 0.001 | | SW6020 | 05/01/12 13:55 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:20 / rdw |
| Selenium | 0.002 | mg/L | | 0.001 | | SW6020 | 05/01/12 13:55 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/01/12 13:55 / cp |
| Uranium | 0.0027 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 13:55 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.8 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 precision (±) | 0.08 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 228 | 1.0 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-005
**Client Sample ID:** MT-5-F (6" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 10:00
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 37.0 | mg/kg | | 1.00 | | E300.0 | 06/28/12 03:39 / ljl |
| Chloride, 1:1 | 1.04 | meq/L | | 0.0282 | | E300.0 | 06/28/12 03:39 / ljl |
| Sulfate | 183 | mg/kg | | 1.00 | | E300.0 | 06/28/12 03:39 / ljl |
| Sulfate, 1:1 | 3.82 | meq/L | | 0.0208 | | E300.0 | 06/28/12 03:39 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.002 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:12 / cp |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 05/01/12 14:12 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 14:12 / cp |
| Chromium | ND | mg/L | | 0.005 | | SW6020 | 05/02/12 22:05 / smm |
| Lead | 0.001 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:12 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:22 / rdw |
| Selenium | 0.001 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:12 / cp |
| Silver | 0.003 | mg/L | D | 0.002 | | SW6020 | 05/01/12 14:12 / cp |
| Uranium | 0.0029 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 14:12 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 2.0 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 228 | 0.8 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-006
**Client Sample ID:** MT-7-C (6" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 09:45
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.002 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:15 / cp |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 05/01/12 14:15 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 14:15 / cp |
| Chromium | 0.006 | mg/L | | 0.005 | | SW6020 | 05/01/12 14:15 / cp |
| Lead | 0.002 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:15 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:23 / rdw |
| Selenium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 14:15 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/01/12 14:15 / cp |
| Uranium | 0.0023 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 14:15 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.6 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 precision (±) | 0.07 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 228 | 0.8 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |
| Radium 228 MDC | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-007
**Client Sample ID:** MT-OP-E (6" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 09:00
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.004 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:18 / cp |
| Barium | 0.05 | mg/L | | 0.05 | | SW6020 | 05/01/12 14:18 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 14:18 / cp |
| Chromium | 0.006 | mg/L | | 0.005 | | SW6020 | 05/01/12 14:18 / cp |
| Lead | 0.003 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:18 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:24 / rdw |
| Selenium | 0.005 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:18 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/01/12 14:18 / cp |
| Uranium | 0.0056 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 14:18 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.1 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 228 | 0.8 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-008
**Client Sample ID:** MT-A-C (6" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 10:55
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.003 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:21 / cp |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 05/01/12 14:21 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 14:21 / cp |
| Chromium | ND | mg/L | | 0.005 | | SW6020 | 05/01/12 14:21 / cp |
| Lead | 0.001 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:21 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:28 / rdw |
| Selenium | 0.044 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:21 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/01/12 14:21 / cp |
| Uranium | 0.14 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 14:21 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.7 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 228 | 0.5 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 21:06 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-009
**Client Sample ID:** MT-Borrow/Background

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 11:00
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.001 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:27 / cp |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 05/01/12 15:27 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 15:27 / cp |
| Chromium | ND | mg/L | | 0.005 | | SW6020 | 05/01/12 15:27 / cp |
| Lead | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 15:27 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:34 / rdw |
| Selenium | 0.001 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:27 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/01/12 15:27 / cp |
| Uranium | 0.0007 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 15:27 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.7 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 precision (±) | 0.07 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 228 | 0.7 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-010
**Client Sample ID:** MT-4-D-S1 (0-6" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 14:05
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 7.76 | mg/kg | | 1.00 | | E300.0 | 06/28/12 03:55 / ljl |
| Chloride, 1:1 | 0.219 | meq/L | | 0.0282 | | E300.0 | 06/28/12 03:55 / ljl |
| Sulfate | 77.0 | mg/kg | | 1.00 | | E300.0 | 06/28/12 03:55 / ljl |
| Sulfate, 1:1 | 1.60 | meq/L | | 0.0208 | | E300.0 | 06/28/12 03:55 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.008 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:56 / cp |
| Barium | 1.0 | mg/L | | 0.05 | | SW6020 | 05/01/12 14:56 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 14:56 / cp |
| Chromium | 0.008 | mg/L | | 0.005 | | SW6020 | 05/01/12 14:56 / cp |
| Lead | 0.003 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:56 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:38 / rdw |
| Selenium | 0.015 | mg/L | | 0.001 | | SW6020 | 05/01/12 14:56 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/01/12 14:56 / cp |
| Uranium | 0.033 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 14:56 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 18.1 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 precision (±) | 0.3 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 228 | 0.9 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-011
**Client Sample ID:** MT-4-D-S2 (14" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 14:10
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 92.0 | mg/kg | | 1.00 | | E300.0 | 06/28/12 04:12 / ljl |
| Chloride, 1:1 | 2.60 | meq/L | | 0.0282 | | E300.0 | 06/28/12 04:12 / ljl |
| Sulfate | 1840 | mg/kg | | 1.00 | | E300.0 | 06/28/12 04:12 / ljl |
| Sulfate, 1:1 | 38.2 | meq/L | | 0.0208 | | E300.0 | 06/28/12 04:12 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.007 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:02 / cp |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 05/01/12 15:02 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 15:02 / cp |
| Chromium | 0.006 | mg/L | | 0.005 | | SW6020 | 05/01/12 15:02 / cp |
| Lead | 0.001 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:02 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:39 / rdw |
| Selenium | 0.39 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:02 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/01/12 15:02 / cp |
| Uranium | 0.20 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 15:02 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 2.8 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/10/12 13:40 / trs |
| Radium 228 | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-012
**Client Sample ID:** MT-4-D-S3 (48" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 14:20
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 6.49 | mg/kg | | 1.00 | | E300.0 | 06/28/12 04:44 / ljl |
| Chloride, 1:1 | 0.183 | meq/L | | 0.0282 | | E300.0 | 06/28/12 04:44 / ljl |
| Sulfate | 132 | mg/kg | | 1.00 | | E300.0 | 06/28/12 04:44 / ljl |
| Sulfate, 1:1 | 2.74 | meq/L | | 0.0208 | | E300.0 | 06/28/12 04:44 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.003 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:05 / cp |
| Barium | 0.88 | mg/L | | 0.05 | | SW6020 | 05/01/12 15:05 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 15:05 / cp |
| Chromium | 0.009 | mg/L | | 0.005 | | SW6020 | 05/01/12 15:05 / cp |
| Lead | 0.003 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:05 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:41 / rdw |
| Selenium | 0.020 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:05 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/01/12 15:05 / cp |
| Uranium | 0.013 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 15:05 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 6.7 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 228 | 0.8 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-013
**Client Sample ID:** MT-4-E-S1 (0-4" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:35
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 46.4 | mg/kg | | 1.00 | | E300.0 | 06/28/12 05:01 / ljl |
| Chloride, 1:1 | 1.31 | meq/L | | 0.0282 | | E300.0 | 06/28/12 05:01 / ljl |
| Sulfate | 853 | mg/kg | | 1.00 | | E300.0 | 06/28/12 05:01 / ljl |
| Sulfate, 1:1 | 17.8 | meq/L | | 0.0208 | | E300.0 | 06/28/12 05:01 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.034 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:08 / cp |
| Barium | 34 | mg/L | | 0.05 | | SW6020 | 05/01/12 15:08 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 15:08 / cp |
| Chromium | 0.007 | mg/L | | 0.005 | | SW6020 | 05/02/12 22:19 / smm |
| Lead | 0.008 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:08 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:48 / rdw |
| Selenium | 0.15 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:08 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/01/12 15:08 / cp |
| Uranium | 0.39 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 15:08 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 8.7 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 228 | 1.5 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 MDC | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |

- Sample matrix interference resulted in high chemical recoveries which has likely biased the Ra226 and Ra228 results low.

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-014
**Client Sample ID:** MT-4-E-S2 (10-12" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:40
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 34.1 | mg/kg | | 1.00 | | E300.0 | 06/28/12 05:17 / ljl |
| Chloride, 1:1 | 0.963 | meq/L | | 0.0282 | | E300.0 | 06/28/12 05:17 / ljl |
| Sulfate | 1150 | mg/kg | | 1.00 | | E300.0 | 06/28/12 05:17 / ljl |
| Sulfate, 1:1 | 23.8 | meq/L | | 0.0208 | | E300.0 | 06/28/12 05:17 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.005 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:10 / cp |
| Barium | 0.22 | mg/L | | 0.05 | | SW6020 | 05/01/12 15:10 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 15:10 / cp |
| Chromium | 0.011 | mg/L | | 0.005 | | SW6020 | 05/01/12 15:10 / cp |
| Lead | 0.005 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:10 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:49 / rdw |
| Selenium | 0.072 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:10 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/01/12 15:10 / cp |
| Uranium | 0.014 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 15:10 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 4.8 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 228 | 0.4 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-015
**Client Sample ID:** MT-4-E-S3 (36" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:42
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 13.1 | mg/kg | | 1.00 | | E300.0 | 06/28/12 05:34 / ljl |
| Chloride, 1:1 | 0.371 | meq/L | | 0.0282 | | E300.0 | 06/28/12 05:34 / ljl |
| Sulfate | 184 | mg/kg | | 1.00 | | E300.0 | 06/28/12 05:34 / ljl |
| Sulfate, 1:1 | 3.84 | meq/L | | 0.0208 | | E300.0 | 06/28/12 05:34 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.003 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:24 / cp |
| Barium | 0.13 | mg/L | | 0.05 | | SW6020 | 05/01/12 15:24 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/01/12 15:24 / cp |
| Chromium | 0.007 | mg/L | | 0.005 | | SW6020 | 05/01/12 15:24 / cp |
| Lead | 0.003 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:24 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 15:51 / rdw |
| Selenium | 0.026 | mg/L | | 0.001 | | SW6020 | 05/01/12 15:24 / cp |
| Silver | 0.003 | mg/L | D | 0.002 | | SW6020 | 05/01/12 15:24 / cp |
| Uranium | 0.0043 | mg/L | D | 0.0006 | | SW6020 | 05/01/12 15:24 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 2.9 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 228 | 0.7 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-016
**Client Sample ID:** MT-4-E-S4 (48" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:45
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 4.51 | mg/kg | | 1.00 | | E300.0 | 06/28/12 05:50 / ljl |
| Chloride, 1:1 | 0.127 | meq/L | | 0.0282 | | E300.0 | 06/28/12 05:50 / ljl |
| Sulfate | 131 | mg/kg | | 1.00 | | E300.0 | 06/28/12 05:50 / ljl |
| Sulfate, 1:1 | 2.72 | meq/L | | 0.0208 | | E300.0 | 06/28/12 05:50 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.005 | mg/L | B | 0.001 | | SW6020 | 05/02/12 21:10 / smm |
| Barium | 0.06 | mg/L | | 0.05 | | SW6020 | 05/02/12 21:10 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 21:10 / smm |
| Chromium | 0.006 | mg/L | | 0.005 | | SW6020 | 05/02/12 21:10 / smm |
| Lead | 0.002 | mg/L | | 0.001 | | SW6020 | 05/02/12 21:10 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 16:01 / rdw |
| Selenium | 0.011 | mg/L | | 0.001 | | SW6020 | 05/02/12 21:10 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 21:10 / smm |
| Uranium | 0.027 | mg/L | | 0.0003 | | SW6020 | 05/02/12 21:10 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 6.2 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 228 | 0.4 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |
| Radium 228 MDC | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:57 / gb |

- Sample matrix interference resulted in high chemical recoveries which has likely biased the Ra226 and Ra228 results low.

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-017
**Client Sample ID:** MT-6-A-S1 (0-5" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 15:05
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.012 | mg/L | | 0.001 | | SW6020 | 05/02/12 20:29 / smm |
| Barium | 7.3 | mg/L | | 0.05 | | SW6020 | 05/02/12 20:29 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 20:29 / smm |
| Chromium | 0.007 | mg/L | | 0.005 | | SW6020 | 05/02/12 20:29 / smm |
| Lead | 0.016 | mg/L | | 0.001 | | SW6020 | 05/02/12 20:29 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 16:05 / rdw |
| Selenium | 0.007 | mg/L | | 0.001 | | SW6020 | 05/02/12 20:29 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 20:29 / smm |
| Uranium | 0.044 | mg/L | | 0.0003 | | SW6020 | 05/02/12 20:29 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 6.4 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 228 | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |
| Radium 228 MDC | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-018
**Client Sample ID:** MT-6-A-S2 (12-20" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 15:10
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.003 | mg/L | B | 0.001 | | SW6020 | 05/02/12 20:33 / smm |
| Barium | 0.05 | mg/L | | 0.05 | | SW6020 | 05/02/12 20:33 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 20:33 / smm |
| Chromium | 0.007 | mg/L | | 0.005 | | SW6020 | 05/02/12 20:33 / smm |
| Lead | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 20:33 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 16:06 / rdw |
| Selenium | 0.15 | mg/L | | 0.001 | | SW6020 | 05/02/12 20:33 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 20:33 / smm |
| Uranium | 0.26 | mg/L | | 0.0003 | | SW6020 | 05/02/12 20:33 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.4 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 precision (±) | 0.05 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 228 | 0.1 | pCi/g-dry | U | | | RA-05 | 07/05/12 22:56 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
U - Not detected at minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-019
**Client Sample ID:** MT-6-B-S1 (8-10" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 14:30
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.004 | mg/L | B | 0.001 | | SW6020 | 05/02/12 20:38 / smm |
| Barium | 0.05 | mg/L | | 0.05 | | SW6020 | 05/02/12 20:38 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 20:38 / smm |
| Chromium | 0.007 | mg/L | | 0.005 | | SW6020 | 05/02/12 20:38 / smm |
| Lead | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 20:38 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 16:08 / rdw |
| Selenium | 0.16 | mg/L | | 0.001 | | SW6020 | 05/02/12 20:38 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 20:38 / smm |
| Uranium | 0.26 | mg/L | | 0.0003 | | SW6020 | 05/02/12 20:38 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.8 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 precision (±) | 0.08 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 228 | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-020
**Client Sample ID:** MT-6-B-S2 (30" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 14:35
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.002 | mg/L | B | 0.001 | | SW6020 | 05/02/12 20:43 / smm |
| Barium | 0.06 | mg/L | | 0.05 | | SW6020 | 05/02/12 20:43 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 20:43 / smm |
| Chromium | ND | mg/L | | 0.005 | | SW6020 | 05/02/12 20:43 / smm |
| Lead | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 20:43 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 16:09 / rdw |
| Selenium | 0.003 | mg/L | | 0.001 | | SW6020 | 05/02/12 20:43 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 20:43 / smm |
| Uranium | 0.014 | mg/L | | 0.0003 | | SW6020 | 05/02/12 20:43 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 4.1 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 precision (±) | 0.2 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 228 | 0.8 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
B - The analyte was detected in the method blank.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-021
**Client Sample ID:** MT-OP-C-S1 (0-6" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:20
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.015 | mg/L | | 0.001 | | SW6020 | 05/02/12 21:06 / smm |
| Barium | 0.05 | mg/L | | 0.05 | | SW6020 | 05/02/12 21:06 / smm |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 21:06 / smm |
| Chromium | 0.010 | mg/L | | 0.005 | | SW6020 | 05/02/12 21:06 / smm |
| Lead | 0.001 | mg/L | | 0.001 | | SW6020 | 05/02/12 21:06 / smm |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 04/30/12 16:10 / rdw |
| Selenium | 0.052 | mg/L | | 0.001 | | SW6020 | 05/02/12 21:06 / smm |
| Silver | ND | mg/L | | 0.001 | | SW6020 | 05/02/12 21:06 / smm |
| Uranium | 1.8 | mg/L | | 0.0003 | | SW6020 | 05/02/12 21:06 / smm |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 53.3 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 precision (±) | 0.6 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/10/12 14:44 / trs |
| Radium 228 | 2.1 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |
| Radium 228 precision (±) | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 22:56 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-022
**Client Sample ID:** MT-OP-C-S2 (20" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:25
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.005 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:22 / cp |
| Barium | 0.05 | mg/L | | 0.05 | | SW6020 | 05/04/12 14:22 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/04/12 14:22 / cp |
| Chromium | 0.007 | mg/L | | 0.005 | | SW6020 | 05/04/12 14:22 / cp |
| Lead | 0.002 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:22 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/02/12 11:26 / rdw |
| Selenium | 0.018 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:22 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/04/12 14:22 / cp |
| Uranium | 0.14 | mg/L | D | 0.0006 | | SW6020 | 05/04/12 14:22 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.7 | pCi/g-dry | | | | E903.0 | 07/10/12 16:03 / trs |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/10/12 16:03 / trs |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 07/10/12 16:03 / trs |
| Radium 228 | 0.6 | pCi/g-dry | | | | RA-05 | 07/05/12 21:05 / gb |
| Radium 228 precision (±) | 0.1 | pCi/g-dry | | | | RA-05 | 07/05/12 21:05 / gb |
| Radium 228 MDC | 0.2 | pCi/g-dry | | | | RA-05 | 07/05/12 21:05 / gb |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-023
**Client Sample ID:** MT-OP-C-S3 (48-50' B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:25
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.004 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:41 / cp |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 05/04/12 14:41 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/04/12 14:41 / cp |
| Chromium | ND | mg/L | | 0.005 | | SW6020 | 05/04/12 14:41 / cp |
| Lead | ND | mg/L | | 0.001 | | SW6020 | 05/04/12 14:41 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/02/12 11:29 / rdw |
| Selenium | 0.028 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:41 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/04/12 14:41 / cp |
| Uranium | 0.049 | mg/L | D | 0.0006 | | SW6020 | 05/04/12 14:41 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.8 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 226 precision (±) | 0.07 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 228 | 0.8 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |
| Radium 228 precision (±) | 0.09 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |
| Radium 228 MDC | 0.1 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-024
**Client Sample ID:** MT-OP-C-S4 (72" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 13:30
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.004 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:44 / cp |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 05/04/12 14:44 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/04/12 14:44 / cp |
| Chromium | ND | mg/L | | 0.005 | | SW6020 | 05/04/12 14:44 / cp |
| Lead | ND | mg/L | | 0.001 | | SW6020 | 05/04/12 14:44 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/02/12 11:30 / rdw |
| Selenium | 0.025 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:44 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/04/12 14:44 / cp |
| Uranium | 0.0064 | mg/L | D | 0.0006 | | SW6020 | 05/04/12 14:44 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.5 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 228 | 0.6 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |
| Radium 228 precision (±) | 0.09 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |
| Radium 228 MDC | 0.1 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-025
**Client Sample ID:** MT-OP-D-S1 (0-6" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 12:45
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.013 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:47 / cp |
| Barium | 1.3 | mg/L | | 0.05 | | SW6020 | 05/04/12 14:47 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/04/12 14:47 / cp |
| Chromium | 0.007 | mg/L | | 0.005 | | SW6020 | 05/04/12 14:47 / cp |
| Lead | 0.008 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:47 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/02/12 11:31 / rdw |
| Selenium | 0.009 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:47 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/04/12 14:47 / cp |
| Uranium | 0.23 | mg/L | D | 0.0006 | | SW6020 | 05/04/12 14:47 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 51.9 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 226 precision (±) | 0.5 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 228 | 0.5 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |
| Radium 228 precision (±) | 0.07 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |
| Radium 228 MDC | 0.09 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-026
**Client Sample ID:** MT-OP-D-S2 (48-50" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 12:45
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.001 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:49 / cp |
| Barium | 0.05 | mg/L | | 0.05 | | SW6020 | 05/04/12 14:49 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/04/12 14:49 / cp |
| Chromium | ND | mg/L | | 0.005 | | SW6020 | 05/04/12 14:49 / cp |
| Lead | ND | mg/L | | 0.001 | | SW6020 | 05/04/12 14:49 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/02/12 11:35 / rdw |
| Selenium | 0.005 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:49 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/04/12 14:49 / cp |
| Uranium | 0.10 | mg/L | D | 0.0006 | | SW6020 | 05/04/12 14:49 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.9 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 228 | 0.6 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |
| Radium 228 precision (±) | 0.09 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |
| Radium 228 MDC | 0.1 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-027
**Client Sample ID:** MT-OP-D-S3 (76" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 12:50
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.006 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:52 / cp |
| Barium | 0.11 | mg/L | | 0.05 | | SW6020 | 05/04/12 14:52 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/04/12 14:52 / cp |
| Chromium | 0.012 | mg/L | | 0.005 | | SW6020 | 05/04/12 14:52 / cp |
| Lead | 0.009 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:52 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/02/12 11:37 / rdw |
| Selenium | 0.002 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:52 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/04/12 14:52 / cp |
| Uranium | 0.0034 | mg/L | D | 0.0006 | | SW6020 | 05/04/12 14:52 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.6 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 226 precision (±) | 0.06 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 228 | 0.5 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |
| Radium 228 precision (±) | 0.08 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |
| Radium 228 MDC | 0.1 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine Closure Plan
**Lab ID:** C12041044-028
**Client Sample ID:** MT-8-F (6" B.G.)

**Revised Date:** 07/10/12
**Report Date:** 06/13/12
**Collection Date:** 04/10/12 09:25
**DateReceived:** 04/20/12
**Matrix:** Sediment

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **SATURATED PASTE EXTRACT** | | | | | | | |
| Chloride | 14.2 | mg/kg | | 1.00 | | E300.0 | 06/28/12 06:07 / ljl |
| Chloride, 1:1 | 0.402 | meq/L | | 0.0282 | | E300.0 | 06/28/12 06:07 / ljl |
| Sulfate | 28.9 | mg/kg | | 1.00 | | E300.0 | 06/28/12 06:07 / ljl |
| Sulfate, 1:1 | 0.602 | meq/L | | 0.0208 | | E300.0 | 06/28/12 06:07 / ljl |
| **PHYSICAL CHARACTERISTICS** | | | | | | | |
| Filterable | No | | | | | SW1311 | 04/24/12 16:14 / dcj |
| **METALS - SPLP EXTRACTABLE** | | | | | | | |
| Arsenic | 0.003 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:55 / cp |
| Barium | ND | mg/L | | 0.05 | | SW6020 | 05/04/12 14:55 / cp |
| Cadmium | ND | mg/L | | 0.001 | | SW6020 | 05/04/12 14:55 / cp |
| Chromium | ND | mg/L | | 0.005 | | SW6020 | 05/04/12 14:55 / cp |
| Lead | 0.002 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:55 / cp |
| Mercury | ND | mg/L | | 0.002 | | SW7470A | 05/02/12 11:38 / rdw |
| Selenium | 0.002 | mg/L | | 0.001 | | SW6020 | 05/04/12 14:55 / cp |
| Silver | ND | mg/L | D | 0.002 | | SW6020 | 05/04/12 14:55 / cp |
| Uranium | 0.010 | mg/L | D | 0.0006 | | SW6020 | 05/04/12 14:55 / cp |
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 2.3 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 226 precision (±) | 0.1 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 226 MDC | 0.02 | pCi/g-dry | | | | E903.0 | 07/03/12 05:26 / trs |
| Radium 228 | 0.6 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |
| Radium 228 precision (±) | 0.09 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |
| Radium 228 MDC | 0.1 | pCi/g-dry | | | | RA-05 | 06/26/12 17:02 / plj |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
D - RL increased due to sample matrix.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation **Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan **Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E300.0** | | | | | | | | | Analytical Run: IC2-C_120626A | |
| **Sample ID: ICV-062612-10** | 2 | Initial Calibration Verification Standard | | | | | | | 06/26/12 15:31 | |
| Chloride | | 9.60 | mg/L | 1.0 | 96 | 90 | 110 | | | |
| Sulfate | | 38.7 | mg/L | 1.0 | 97 | 90 | 110 | | | |
| **Method: E300.0** | | | | | | | | | Batch: 34007 | |
| **Sample ID: MB-34007** | 2 | Method Blank | | | | Run: IC2-C_120626A | | | 06/28/12 02:17 | |
| Chloride | | ND | mg/kg | 0.04 | | | | | | |
| Sulfate | | 0.08 | mg/kg | 0.06 | | | | | | |
| **Sample ID: LCS1-34007** | 2 | Laboratory Control Sample | | | | Run: IC2-C_120626A | | | 06/28/12 02:33 | |
| Chloride | | 35.9 | mg/kg | 1.0 | 101 | 70 | 130 | | | |
| Sulfate | | 1730 | mg/kg | 1.0 | 95 | 70 | 130 | | | |
| **Sample ID: C12041044-011CPDS** | 2 | Post Digestion/Distillation Spike | | | | Run: IC2-C_120626A | | | 06/28/12 04:28 | |
| Chloride | | 280 | mg/kg | 1.0 | 94 | 80 | 120 | | | |
| Sulfate | | 2570 | mg/kg | 1.0 | 92 | 80 | 120 | | | |
| **Sample ID: C12041044-028CDUP** | 2 | Sample Duplicate | | | | Run: IC2-C_120626A | | | 06/28/12 06:23 | |
| Chloride | | 14.0 | mg/kg | 1.0 | | | | 1.8 | 20 | |
| Sulfate | | 28.1 | mg/kg | 1.0 | | | | 2.9 | 20 | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E903.0** | | | | | | | | | | Batch: 34025 |
| **Sample ID: C12041044-023BMS** | | Sample Matrix Spike | | | | Run: BERTHOLD 770-1_120621B | | | | 07/03/12 05:26 |
| Radium 226 | | 2.9 | pCi/g-dry | | 85 | 70 | 130 | | | |
| **Sample ID: C12041044-023BMSD** | | Sample Matrix Spike Duplicate | | | | Run: BERTHOLD 770-1_120621B | | | | 07/03/12 05:26 |
| Radium 226 | | 2.8 | pCi/g-dry | | 85 | 70 | 130 | 3.6 | 22.9 | |
| **Sample ID: LCS-34025** | | Laboratory Control Sample | | | | Run: BERTHOLD 770-1_120621B | | | | 07/03/12 05:26 |
| Radium 226 | | 0.41 | pCi/g-dry | | 85 | 70 | 130 | | | |
| **Sample ID: MB-34025** | 3 | Method Blank | | | | Run: BERTHOLD 770-1_120621B | | | | 07/03/12 07:45 |
| Radium 226 | | 0.0009 | pCi/g-dry | | | | | | | U |
| Radium 226 precision (±) | | 0.004 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.006 | pCi/g-dry | | | | | | | |
| **Method: E903.0** | | | | | | | | | | Batch: 34023 |
| **Sample ID: C12041044-022BMS** | | Sample Matrix Spike | | | | Run: BERTHOLD 770-1_120621C | | | | 07/10/12 16:03 |
| Radium 226 | | 3.6 | pCi/g-dry | | 80 | 70 | 130 | | | |
| **Sample ID: C12041044-022BMSD** | | Sample Matrix Spike Duplicate | | | | Run: BERTHOLD 770-1_120621C | | | | 07/10/12 16:03 |
| Radium 226 | | 3.7 | pCi/g-dry | | 85 | 70 | 130 | 2.9 | 22.7 | |
| **Sample ID: LCS-34023** | | Laboratory Control Sample | | | | Run: BERTHOLD 770-1_120621C | | | | 07/10/12 16:03 |
| Radium 226 | | 0.33 | pCi/g-dry | | 69 | 70 | 130 | | | S |
| - LCS response is outside of the acceptance range for this analysis. Since the MB, MS, and MSD are acceptable the batch is approved. | | | | | | | | | | |
| **Sample ID: MB-34023** | 3 | Method Blank | | | | Run: BERTHOLD 770-1_120621C | | | | 07/10/12 16:03 |
| Radium 226 | | -0.002 | pCi/g-dry | | | | | | | U |
| Radium 226 precision (±) | | 0.006 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.01 | pCi/g-dry | | | | | | | |
| **Method: E903.0** | | | | | | | | | | Batch: 34004 |
| **Sample ID: MB-34004** | 3 | Method Blank | | | | Run: BERTHOLD 770-2_120620A | | | | 07/02/12 23:59 |
| Radium 226 | | 0.1 | pCi/g-dry | | | | | | | |
| Radium 226 precision (±) | | 0.03 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.02 | pCi/g-dry | | | | | | | |
| **Sample ID: LCS-34004** | | Laboratory Control Sample | | | | Run: BERTHOLD 770-2_120620A | | | | 07/02/12 23:59 |
| Radium 226 | | 1.4 | pCi/g-dry | | 87 | 70 | 130 | | | |
| **Sample ID: C12041044-003BMS** | | Sample Matrix Spike | | | | Run: BERTHOLD 770-2_120620A | | | | 07/03/12 03:34 |
| Radium 226 | | 2.5 | pCi/g-dry | | 104 | 70 | 130 | | | |
| **Sample ID: C12041044-003BMSD** | | Sample Matrix Spike Duplicate | | | | Run: BERTHOLD 770-2_120620A | | | | 07/03/12 03:34 |
| Radium 226 | | 2.2 | pCi/g-dry | | 87 | 70 | 130 | 12 | 20.8 | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

U - Not detected at minimum detectable concentration

ND - Not detected at the reporting limit.

S - Spike recovery outside of advisory limits.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: RA-05** | | | | | | | | | | Batch: 34004 |
| **Sample ID: LCS-34004** | | Laboratory Control Sample | | | | Run: TENNELEC-3_120620B | | | | 06/25/12 15:52 |
| Radium 228 | | 1.5 | pCi/g-dry | | 104 | 70 | 130 | | | |
| **Sample ID: MB-34004** | 3 | Method Blank | | | | Run: TENNELEC-3_120620B | | | | 06/25/12 15:52 |
| Radium 228 | | 0.07 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.2 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.3 | pCi/g-dry | | | | | | | |
| **Sample ID: C12041044-003BMS** | | Sample Matrix Spike | | | | Run: TENNELEC-3_120620B | | | | 06/25/12 15:52 |
| Radium 228 | | 1.8 | pCi/g-dry | | 93 | 70 | 130 | | | |
| **Sample ID: C12041044-003BMSD** | | Sample Matrix Spike Duplicate | | | | Run: TENNELEC-3_120620B | | | | 06/25/12 15:52 |
| Radium 228 | | 1.9 | pCi/g-dry | | 101 | 70 | 130 | 6.0 | 33.5 | |
| **Method: RA-05** | | | | | | | | | | Batch: 34025 |
| **Sample ID: LCS-34025** | | Laboratory Control Sample | | | | Run: TENNELEC-3_120621B | | | | 06/26/12 17:02 |
| Radium 228 | | 0.24 | pCi/g-dry | | 83 | 70 | 130 | | | |
| **Sample ID: MB-34025** | 3 | Method Blank | | | | Run: TENNELEC-3_120621B | | | | 06/26/12 17:02 |
| Radium 228 | | 0.002 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.03 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.04 | pCi/g-dry | | | | | | | |
| **Sample ID: C12041044-028BMS** | | Sample Matrix Spike | | | | Run: TENNELEC-3_120621B | | | | 06/26/12 17:02 |
| Radium 228 | | 1.7 | pCi/g-dry | | 71 | 70 | 130 | | | |
| **Sample ID: C12041044-028BMSD** | | Sample Matrix Spike Duplicate | | | | Run: TENNELEC-3_120621B | | | | 06/26/12 17:02 |
| Radium 228 | | 1.7 | pCi/g-dry | | 78 | 70 | 130 | 3.0 | 32.3 | |
| **Method: RA-05** | | | | | | | | | | Batch: Ra228-4136 |
| **Sample ID: LCS-34023** | | Laboratory Control Sample | | | | Run: TENNELEC-3_120621D | | | | 07/05/12 21:05 |
| Radium 228 | | 0.36 | pCi/g-dry | | 129 | 70 | 130 | | | |
| **Sample ID: MB-34023** | 3 | Method Blank | | | | Run: TENNELEC-3_120621D | | | | 07/05/12 21:05 |
| Radium 228 | | -0.010 | pCi/g-dry | | | | | | | U |
| Radium 228 precision (±) | | 0.04 | pCi/g-dry | | | | | | | |
| Radium 228 MDC | | 0.06 | pCi/g-dry | | | | | | | |
| **Sample ID: C12041044-022BMS** | | Sample Matrix Spike | | | | Run: TENNELEC-3_120621D | | | | 07/05/12 21:06 |
| Radium 228 | | 1.7 | pCi/g-dry | | 80 | 70 | 130 | | | |
| **Sample ID: C12041044-022BMSD** | | Sample Matrix Spike Duplicate | | | | Run: TENNELEC-3_120621D | | | | 07/05/12 21:06 |
| Radium 228 | | 2.1 | pCi/g-dry | | 110 | 70 | 130 | 19 | 36.9 | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

U - Not detected at minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | Analytical Run: ICPMS2-C_120501A | |
| **Sample ID: ICV** | 8 | Initial Calibration Verification Standard | | | | | | | 05/01/12 13:14 | |
| Arsenic | | 0.0490 | mg/L | 0.0010 | 98 | 90 | 110 | | | |
| Barium | | 0.0486 | mg/L | 0.0010 | 97 | 90 | 110 | | | |
| Cadmium | | 0.0491 | mg/L | 0.0010 | 98 | 90 | 110 | | | |
| Chromium | | 0.0501 | mg/L | 0.0010 | 100 | 90 | 110 | | | |
| Lead | | 0.0483 | mg/L | 0.0010 | 97 | 90 | 110 | | | |
| Selenium | | 0.0501 | mg/L | 0.0010 | 100 | 90 | 110 | | | |
| Silver | | 0.0207 | mg/L | 0.0010 | 103 | 90 | 110 | | | |
| Uranium | | 0.0485 | mg/L | 0.00030 | 97 | 90 | 110 | | | |
| **Sample ID: ICSA** | 8 | Interference Check Sample A | | | | | | | 05/01/12 13:16 | |
| Arsenic | | 0.0103 | mg/L | 0.0010 | | | | | | |
| Barium | | 3.16E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 0.0104 | mg/L | 0.0010 | | | | | | |
| Chromium | | 0.0104 | mg/L | 0.0010 | | | | | | |
| Lead | | 3.39E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | 8.30E-06 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.0108 | mg/L | 0.0010 | | | | | | |
| Uranium | | 6.80E-05 | mg/L | 0.00030 | | | | | | |
| **Sample ID: ICSAB** | 8 | Interference Check Sample AB | | | | | | | 05/01/12 13:19 | |
| Arsenic | | 0.0103 | mg/L | 0.0010 | 103 | 70 | 130 | | | |
| Barium | | 4.64E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 0.0106 | mg/L | 0.0010 | 106 | 70 | 130 | | | |
| Chromium | | 0.0105 | mg/L | 0.0010 | 105 | 70 | 130 | | | |
| Lead | | 3.92E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | 1.39E-05 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.0107 | mg/L | 0.0010 | 107 | 70 | 130 | | | |
| Uranium | | 1.47E-05 | mg/L | 0.00030 | | | | | | |
| **Method: SW6020** | | | | | | | | | Batch: 33469 | |
| **Sample ID: MB-33469** | 8 | Method Blank | | | | Run: ICPMS2-C_120501A | | | 05/01/12 13:45 | |
| Arsenic | | ND | mg/L | 6E-05 | | | | | | |
| Barium | | 0.005 | mg/L | 3E-05 | | | | | | |
| Cadmium | | 0.0001 | mg/L | 1E-05 | | | | | | |
| Chromium | | 0.002 | mg/L | 4E-05 | | | | | | |
| Lead | | 0.0001 | mg/L | 3E-05 | | | | | | |
| Selenium | | 0.0002 | mg/L | 0.0002 | | | | | | |
| Silver | | 0.002 | mg/L | 3E-05 | | | | | | |
| Uranium | | 0.001 | mg/L | 1E-05 | | | | | | |
| **Sample ID: LCS3-33469** | 8 | Laboratory Control Sample | | | | Run: ICPMS2-C_120501A | | | 05/01/12 13:47 | |
| Arsenic | | 0.47 | mg/L | 0.0010 | 93 | 80 | 120 | | | |
| Barium | | 0.51 | mg/L | 0.050 | 100 | 80 | 120 | | | |
| Cadmium | | 0.24 | mg/L | 0.0010 | 96 | 80 | 120 | | | |
| Chromium | | 0.49 | mg/L | 0.0050 | 98 | 80 | 120 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

ND - Not detected at the reporting limit.

MDC - Minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | | Batch: 33469 |
| **Sample ID: LCS3-33469** | 8 | Laboratory Control Sample | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 13:47 |
| Lead | | 0.51 | mg/L | 0.0010 | 101 | 80 | 120 | | | |
| Selenium | | 0.43 | mg/L | 0.0010 | 86 | 80 | 120 | | | |
| Silver | | 0.054 | mg/L | 0.0020 | 104 | 80 | 120 | | | |
| Uranium | | 0.51 | mg/L | 0.00060 | 101 | 80 | 120 | | | |
| **Sample ID: LCSD3-33469** | 8 | Laboratory Control Sample Duplicate | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 13:50 |
| Arsenic | | 0.47 | mg/L | 0.0010 | 94 | 80 | 120 | 0.9 | 20 | |
| Barium | | 0.51 | mg/L | 0.050 | 101 | 80 | 120 | 1.1 | 20 | |
| Cadmium | | 0.24 | mg/L | 0.0010 | 96 | 80 | 120 | 0.1 | 20 | |
| Chromium | | 0.49 | mg/L | 0.0050 | 97 | 80 | 120 | 0.4 | 20 | |
| Lead | | 0.51 | mg/L | 0.0010 | 102 | 80 | 120 | 0.8 | 20 | |
| Selenium | | 0.43 | mg/L | 0.0010 | 86 | 80 | 120 | 0.6 | 20 | |
| Silver | | 0.055 | mg/L | 0.0020 | 106 | 80 | 120 | 2.1 | 20 | |
| Uranium | | 0.51 | mg/L | 0.00060 | 101 | 80 | 120 | 0.0 | 20 | |
| **Sample ID: C12041044-004ADIL** | 8 | Serial Dilution | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 13:58 |
| Arsenic | | 0.0054 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Barium | | 0.037 | mg/L | 0.050 | | 0 | 0 | | 20 | |
| Cadmium | | 0.00042 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Chromium | | 0.0071 | mg/L | 0.0050 | | 0 | 0 | 5.0 | 20 | |
| Lead | | 0.0028 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Selenium | | 0.0026 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Silver | | 0.00070 | mg/L | 0.010 | | 0 | 0 | | 20 | N |
| Uranium | | 0.0029 | mg/L | 0.0030 | | 0 | 0 | | 20 | |
| **Sample ID: C12041044-003AMS3** | 8 | Sample Matrix Spike | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 14:26 |
| Arsenic | | 0.47 | mg/L | 0.0010 | 94 | 75 | 125 | | | |
| Barium | | 0.53 | mg/L | 0.050 | 103 | 75 | 125 | | | |
| Cadmium | | 0.24 | mg/L | 0.0010 | 98 | 75 | 125 | | | |
| Chromium | | 0.50 | mg/L | 0.0050 | 98 | 75 | 125 | | | |
| Lead | | 0.52 | mg/L | 0.0010 | 103 | 75 | 125 | | | |
| Selenium | | 0.44 | mg/L | 0.0010 | 88 | 75 | 125 | | | |
| Silver | | 0.054 | mg/L | 0.0020 | 22 | 75 | 125 | | | S |
| Uranium | | 0.54 | mg/L | 0.00060 | 106 | 75 | 125 | | | |
| **Method: SW6020** | | | | | | | | | | Batch: 33470 |
| **Sample ID: MB-33470** | 8 | Method Blank | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 14:35 |
| Arsenic | | 0.0003 | mg/L | 6E-05 | | | | | | |
| Barium | | 0.005 | mg/L | 3E-05 | | | | | | |
| Cadmium | | 0.0001 | mg/L | 1E-05 | | | | | | |
| Chromium | | 0.004 | mg/L | 4E-05 | | | | | | |
| Lead | | 9E-05 | mg/L | 3E-05 | | | | | | |
| Selenium | | 0.0003 | mg/L | 0.0002 | | | | | | |
| Silver | | 0.0006 | mg/L | 3E-05 | | | | | | |
| Uranium | | 0.0006 | mg/L | 1E-05 | | | | | | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

N - The analyte concentration was not sufficiently high to calculate a RPD for the serial dilution test.

S - Spike recovery outside of advisory limits.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | | Batch: 33470 |
| **Sample ID: LCS3-33470** | 8 | Laboratory Control Sample | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 14:49 |
| Arsenic | | 0.47 | mg/L | 0.0010 | 95 | 80 | 120 | | | |
| Barium | | 0.52 | mg/L | 0.050 | 102 | 80 | 120 | | | |
| Cadmium | | 0.24 | mg/L | 0.0010 | 98 | 80 | 120 | | | |
| Chromium | | 0.49 | mg/L | 0.0050 | 97 | 80 | 120 | | | |
| Lead | | 0.51 | mg/L | 0.0010 | 103 | 80 | 120 | | | |
| Selenium | | 0.45 | mg/L | 0.0010 | 89 | 80 | 120 | | | |
| Silver | | 0.057 | mg/L | 0.0020 | 112 | 80 | 120 | | | |
| Uranium | | 0.52 | mg/L | 0.00060 | 104 | 80 | 120 | | | |
| **Sample ID: LCSD3-33470** | 8 | Laboratory Control Sample Duplicate | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 14:51 |
| Arsenic | | 0.47 | mg/L | 0.0010 | 94 | 80 | 120 | 1.1 | 20 | |
| Barium | | 0.52 | mg/L | 0.050 | 103 | 80 | 120 | 0.4 | 20 | |
| Cadmium | | 0.24 | mg/L | 0.0010 | 98 | 80 | 120 | 0.0 | 20 | |
| Chromium | | 0.49 | mg/L | 0.0050 | 98 | 80 | 120 | 1.0 | 20 | |
| Lead | | 0.51 | mg/L | 0.0010 | 103 | 80 | 120 | 0.2 | 20 | |
| Selenium | | 0.44 | mg/L | 0.0010 | 89 | 80 | 120 | 0.3 | 20 | |
| Silver | | 0.056 | mg/L | 0.0020 | 110 | 80 | 120 | 1.9 | 20 | |
| Uranium | | 0.52 | mg/L | 0.00060 | 103 | 80 | 120 | 0.7 | 20 | |
| **Sample ID: C12041044-010ADIL** | 8 | Serial Dilution | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 14:59 |
| Arsenic | | 0.0083 | mg/L | 0.0050 | | 0 | 0 | 8.8 | 20 | |
| Barium | | 1.1 | mg/L | 0.050 | | 0 | 0 | 3.4 | 20 | |
| Cadmium | | 0.00051 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Chromium | | 0.0088 | mg/L | 0.0050 | | 0 | 0 | 10 | 20 | |
| Lead | | 0.0032 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Selenium | | 0.019 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Silver | | ND | mg/L | 0.010 | | 0 | 0 | | 20 | |
| Uranium | | 0.033 | mg/L | 0.0030 | | 0 | 0 | 0.5 | 20 | |
| **Sample ID: C12041044-009AMS3** | 8 | Sample Matrix Spike | | | | Run: ICPMS2-C_120501A | | | | 05/01/12 15:30 |
| Arsenic | | 0.47 | mg/L | 0.0010 | 95 | 75 | 125 | | | |
| Barium | | 0.54 | mg/L | 0.050 | 103 | 75 | 125 | | | |
| Cadmium | | 0.25 | mg/L | 0.0010 | 99 | 75 | 125 | | | |
| Chromium | | 0.49 | mg/L | 0.0050 | 98 | 75 | 125 | | | |
| Lead | | 0.51 | mg/L | 0.0010 | 102 | 75 | 125 | | | |
| Selenium | | 0.45 | mg/L | 0.0010 | 90 | 75 | 125 | | | |
| Silver | | 0.054 | mg/L | 0.0020 | 21 | 75 | 125 | | | S |
| Uranium | | 0.52 | mg/L | 0.00060 | 105 | 75 | 125 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

N - The analyte concentration was not sufficiently high to calculate a RPD for the serial dilution test.

S - Spike recovery outside of advisory limits.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | Analytical Run: ICPMS2-C_120504A | |
| **Sample ID: ICV** | 8 | Initial Calibration Verification Standard | | | | | | | 05/04/12 13:40 | |
| Arsenic | | 0.0494 | mg/L | 0.0010 | 99 | 90 | 110 | | | |
| Barium | | 0.0500 | mg/L | 0.0010 | 100 | 90 | 110 | | | |
| Cadmium | | 0.0497 | mg/L | 0.0010 | 99 | 90 | 110 | | | |
| Chromium | | 0.0490 | mg/L | 0.0010 | 98 | 90 | 110 | | | |
| Lead | | 0.0497 | mg/L | 0.0010 | 99 | 90 | 110 | | | |
| Selenium | | 0.0498 | mg/L | 0.0010 | 100 | 90 | 110 | | | |
| Silver | | 0.0209 | mg/L | 0.0010 | 105 | 90 | 110 | | | |
| Uranium | | 0.0510 | mg/L | 0.00030 | 102 | 90 | 110 | | | |
| **Sample ID: ICSA** | 8 | Interference Check Sample A | | | | | | | 05/04/12 13:43 | |
| Arsenic | | 0.0106 | mg/L | 0.0010 | | | | | | |
| Barium | | 8.40E-06 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 0.0106 | mg/L | 0.0010 | | | | | | |
| Chromium | | 0.0105 | mg/L | 0.0010 | | | | | | |
| Lead | | 3.57E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | 0.000221 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.0109 | mg/L | 0.0010 | | | | | | |
| Uranium | | 6.77E-05 | mg/L | 0.00030 | | | | | | |
| **Sample ID: ICSAB** | 8 | Interference Check Sample AB | | | | | | | 05/04/12 13:46 | |
| Arsenic | | 0.0104 | mg/L | 0.0010 | 104 | 70 | 130 | | | |
| Barium | | 7.45E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 0.0104 | mg/L | 0.0010 | 104 | 70 | 130 | | | |
| Chromium | | 0.0104 | mg/L | 0.0010 | 104 | 70 | 130 | | | |
| Lead | | 3.87E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | 3.16E-05 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.0106 | mg/L | 0.0010 | 105 | 70 | 130 | | | |
| Uranium | | 1.56E-05 | mg/L | 0.00030 | | | | | | |
| **Method: SW6020** | | | | | | | | | Batch: 33541 | |
| **Sample ID: MB-33541** | 8 | Method Blank | | | | Run: ICPMS2-C_120504A | | | 05/04/12 14:11 | |
| Arsenic | | 0.0005 | mg/L | 6E-05 | | | | | | |
| Barium | | 0.006 | mg/L | 3E-05 | | | | | | |
| Cadmium | | 0.0001 | mg/L | 1E-05 | | | | | | |
| Chromium | | 0.003 | mg/L | 4E-05 | | | | | | |
| Lead | | 0.0002 | mg/L | 3E-05 | | | | | | |
| Selenium | | ND | mg/L | 0.0002 | | | | | | |
| Silver | | 0.002 | mg/L | 3E-05 | | | | | | |
| Uranium | | 0.0003 | mg/L | 1E-05 | | | | | | |
| **Sample ID: LCS3-33541** | 8 | Laboratory Control Sample | | | | Run: ICPMS2-C_120504A | | | 05/04/12 14:14 | |
| Arsenic | | 0.46 | mg/L | 0.0010 | 93 | 80 | 120 | | | |
| Barium | | 0.49 | mg/L | 0.050 | 96 | 80 | 120 | | | |
| Cadmium | | 0.23 | mg/L | 0.0010 | 94 | 80 | 120 | | | |
| Chromium | | 0.48 | mg/L | 0.0050 | 95 | 80 | 120 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

ND - Not detected at the reporting limit.

MDC - Minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | | Batch: 33541 |
| **Sample ID: LCS3-33541** | 8 | Laboratory Control Sample | | | | Run: ICPMS2-C_120504A | | | | 05/04/12 14:14 |
| Lead | | 0.49 | mg/L | 0.0010 | 97 | 80 | 120 | | | |
| Selenium | | 0.44 | mg/L | 0.0010 | 89 | 80 | 120 | | | |
| Silver | | 0.051 | mg/L | 0.0020 | 97 | 80 | 120 | | | |
| Uranium | | 0.50 | mg/L | 0.00060 | 99 | 80 | 120 | | | |
| **Sample ID: LCSD3-33541** | 8 | Laboratory Control Sample Duplicate | | | | Run: ICPMS2-C_120504A | | | | 05/04/12 14:16 |
| Arsenic | | 0.48 | mg/L | 0.0010 | 95 | 80 | 120 | 2.6 | 20 | |
| Barium | | 0.50 | mg/L | 0.050 | 98 | 80 | 120 | 1.9 | 20 | |
| Cadmium | | 0.24 | mg/L | 0.0010 | 96 | 80 | 120 | 2.3 | 20 | |
| Chromium | | 0.49 | mg/L | 0.0050 | 98 | 80 | 120 | 3.7 | 20 | |
| Lead | | 0.50 | mg/L | 0.0010 | 100 | 80 | 120 | 2.8 | 20 | |
| Selenium | | 0.46 | mg/L | 0.0010 | 91 | 80 | 120 | 2.4 | 20 | |
| Silver | | 0.053 | mg/L | 0.0020 | 101 | 80 | 120 | 4.0 | 20 | |
| Uranium | | 0.50 | mg/L | 0.00060 | 99 | 80 | 120 | 0.1 | 20 | |
| **Sample ID: C12041044-022AMS3** | 8 | Sample Matrix Spike | | | | Run: ICPMS2-C_120504A | | | | 05/04/12 14:25 |
| Arsenic | | 0.48 | mg/L | 0.0010 | 94 | 75 | 125 | | | |
| Barium | | 0.55 | mg/L | 0.050 | 100 | 75 | 125 | | | |
| Cadmium | | 0.24 | mg/L | 0.0010 | 96 | 75 | 125 | | | |
| Chromium | | 0.48 | mg/L | 0.0050 | 95 | 75 | 125 | | | |
| Lead | | 0.50 | mg/L | 0.0010 | 100 | 75 | 125 | | | |
| Selenium | | 0.47 | mg/L | 0.0010 | 91 | 75 | 125 | | | |
| Silver | | 0.050 | mg/L | 0.0020 | 20 | 75 | 125 | | | S |
| Uranium | | 0.64 | mg/L | 0.00060 | 100 | 75 | 125 | | | |
| **Sample ID: C12041044-028ADIL** | 8 | Serial Dilution | | | | Run: ICPMS2-C_120504A | | | | 05/04/12 14:58 |
| Arsenic | | 0.0038 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Barium | | 0.029 | mg/L | 0.050 | | 0 | 0 | | 20 | |
| Cadmium | | 0.00016 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Chromium | | 0.0040 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Lead | | 0.0018 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Selenium | | 0.0079 | mg/L | 0.0050 | | 0 | 0 | | 20 | N |
| Silver | | ND | mg/L | 0.010 | | 0 | 0 | | 20 | |
| Uranium | | 0.011 | mg/L | 0.0030 | | 0 | 0 | 5.0 | 20 | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

S - Spike recovery outside of advisory limits.

ND - Not detected at the reporting limit.

N - The analyte concentration was not sufficiently high to calculate a RPD for the serial dilution test.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | Analytical Run: ICPMS4-C_120425B | |
| **Sample ID: ICV** | 8 | Initial Calibration Verification Standard | | | | | | | 04/25/12 11:08 | |
| Arsenic | | 0.0486 | mg/L | 0.0010 | 97 | 90 | 110 | | | |
| Barium | | 0.0497 | mg/L | 0.0010 | 99 | 90 | 110 | | | |
| Cadmium | | 0.0501 | mg/L | 0.0010 | 100 | 90 | 110 | | | |
| Chromium | | 0.0491 | mg/L | 0.0010 | 98 | 90 | 110 | | | |
| Lead | | 0.0497 | mg/L | 0.0010 | 99 | 90 | 110 | | | |
| Selenium | | 0.0485 | mg/L | 0.0010 | 97 | 90 | 110 | | | |
| Silver | | 0.0193 | mg/L | 0.0010 | 97 | 90 | 110 | | | |
| Uranium | | 0.0481 | mg/L | 0.00030 | 96 | 90 | 110 | | | |
| **Sample ID: ICSA** | 8 | Interference Check Sample A | | | | | | | 04/25/12 11:12 | |
| Arsenic | | 2.21E-05 | mg/L | 0.0010 | | | | | | |
| Barium | | 2.39E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 4.21E-05 | mg/L | 0.0010 | | | | | | |
| Chromium | | 2.05E-05 | mg/L | 0.0010 | | | | | | |
| Lead | | 1.30E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | 7.84E-05 | mg/L | 0.0010 | | | | | | |
| Silver | | -0.000229 | mg/L | 0.0010 | | | | | | |
| Uranium | | 2.36E-05 | mg/L | 0.00030 | | | | | | |
| **Sample ID: ICSAB** | 8 | Interference Check Sample AB | | | | | | | 04/25/12 11:17 | |
| Arsenic | | 0.0113 | mg/L | 0.0010 | 113 | 70 | 130 | | | |
| Barium | | 1.46E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 0.0109 | mg/L | 0.0010 | 109 | 70 | 130 | | | |
| Chromium | | 0.0115 | mg/L | 0.0010 | 115 | 70 | 130 | | | |
| Lead | | 5.40E-06 | mg/L | 0.0010 | | | | | | |
| Selenium | | 7.00E-07 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.00988 | mg/L | 0.0010 | 99 | 70 | 130 | | | |
| Uranium | | 8.30E-06 | mg/L | 0.00030 | | | | | | |
| **Method: SW6020** | | | | | | | | | Batch: 33440 | |
| **Sample ID: MB-33440** | 8 | Method Blank | | | | Run: ICPMS4-C_120425B | | | 04/25/12 19:38 | |
| Arsenic | | 0.0004 | mg/L | 7E-05 | | | | | | |
| Barium | | 0.01 | mg/L | 0.0001 | | | | | | |
| Cadmium | | 0.0001 | mg/L | 4E-05 | | | | | | |
| Chromium | | ND | mg/L | 0.001 | | | | | | |
| Lead | | 0.0002 | mg/L | 3E-05 | | | | | | |
| Selenium | | 0.0001 | mg/L | 6E-05 | | | | | | |
| Silver | | 0.001 | mg/L | 2E-05 | | | | | | |
| Uranium | | 0.004 | mg/L | 5E-05 | | | | | | |
| **Sample ID: LCS3-33440** | 8 | Laboratory Control Sample | | | | Run: ICPMS4-C_120425B | | | 04/25/12 19:43 | |
| Arsenic | | 0.46 | mg/L | 0.0010 | 91 | 80 | 120 | | | |
| Barium | | 0.50 | mg/L | 0.050 | 98 | 80 | 120 | | | |
| Cadmium | | 0.24 | mg/L | 0.0010 | 97 | 80 | 120 | | | |
| Chromium | | 0.50 | mg/L | 0.0050 | 101 | 80 | 120 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

ND - Not detected at the reporting limit.

MDC - Minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | | Batch: 33440 |
| **Sample ID: LCS3-33440** | 8 | Laboratory Control Sample | | | | Run: ICPMS4-C_120425B | | | 04/25/12 19:43 | |
| Lead | | 0.51 | mg/L | 0.0010 | 103 | 80 | 120 | | | |
| Selenium | | 0.44 | mg/L | 0.0010 | 87 | 80 | 120 | | | |
| Silver | | 0.053 | mg/L | 0.0010 | 104 | 80 | 120 | | | |
| Uranium | | 0.50 | mg/L | 0.00030 | 99 | 80 | 120 | | | |
| **Sample ID: LCSD3-33440** | 8 | Laboratory Control Sample Duplicate | | | | Run: ICPMS4-C_120425B | | | 04/25/12 20:05 | |
| Arsenic | | 0.47 | mg/L | 0.0010 | 94 | 80 | 120 | 2.8 | 20 | |
| Barium | | 0.50 | mg/L | 0.050 | 99 | 80 | 120 | 1.0 | 20 | |
| Cadmium | | 0.25 | mg/L | 0.0010 | 98 | 80 | 120 | 1.0 | 20 | |
| Chromium | | 0.52 | mg/L | 0.0050 | 104 | 80 | 120 | 3.4 | 20 | |
| Lead | | 0.51 | mg/L | 0.0010 | 103 | 80 | 120 | 0.0 | 20 | |
| Selenium | | 0.44 | mg/L | 0.0010 | 89 | 80 | 120 | 1.5 | 20 | |
| Silver | | 0.054 | mg/L | 0.0010 | 106 | 80 | 120 | 1.7 | 20 | |
| Uranium | | 0.51 | mg/L | 0.00030 | 100 | 80 | 120 | 1.0 | 20 | |
| **Sample ID: C12041044-002ADIL** | 8 | Serial Dilution | | | | Run: ICPMS4-C_120425B | | | 04/25/12 20:19 | |
| Arsenic | | 0.0017 | mg/L | 0.0010 | | 0 | 0 | | 20 | N |
| Barium | | 0.065 | mg/L | 0.050 | | 0 | 0 | 2.8 | 20 | |
| Cadmium | | ND | mg/L | 0.0010 | | 0 | 0 | | 20 | |
| Chromium | | ND | mg/L | 0.011 | | 0 | 0 | | 20 | |
| Lead | | 0.0028 | mg/L | 0.0010 | | 0 | 0 | | 20 | N |
| Selenium | | ND | mg/L | 0.0010 | | 0 | 0 | | 20 | |
| Silver | | ND | mg/L | 0.0010 | | 0 | 0 | | 20 | |
| Uranium | | 0.010 | mg/L | 0.00052 | | 0 | 0 | 5.8 | 20 | |
| **Sample ID: C12041044-001AMS3** | 8 | Sample Matrix Spike | | | | Run: ICPMS4-C_120425B | | | 04/25/12 21:40 | |
| Arsenic | | 0.48 | mg/L | 0.0010 | 94 | 75 | 125 | | | |
| Barium | | 0.68 | mg/L | 0.050 | 102 | 75 | 125 | | | |
| Cadmium | | 0.25 | mg/L | 0.0010 | 98 | 75 | 125 | | | |
| Chromium | | 0.55 | mg/L | 0.0050 | 107 | 75 | 125 | | | |
| Lead | | 0.54 | mg/L | 0.0010 | 105 | 75 | 125 | | | |
| Selenium | | 0.46 | mg/L | 0.0010 | 92 | 75 | 125 | | | |
| Silver | | 0.053 | mg/L | 0.0010 | 21 | 75 | 125 | | | S |
| Uranium | | 0.60 | mg/L | 0.00030 | 104 | 75 | 125 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

N - The analyte concentration was not sufficiently high to calculate a RPD for the serial dilution test.

S - Spike recovery outside of advisory limits.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | Analytical Run: ICPMS4-C_120502A | |
| **Sample ID: ICV** | 8 | Initial Calibration Verification Standard | | | | | | | 05/02/12 11:40 | |
| Arsenic | | 0.0474 | mg/L | 0.0010 | 95 | 90 | 110 | | | |
| Barium | | 0.0493 | mg/L | 0.0010 | 99 | 90 | 110 | | | |
| Cadmium | | 0.0496 | mg/L | 0.0010 | 99 | 90 | 110 | | | |
| Chromium | | 0.0478 | mg/L | 0.0010 | 96 | 90 | 110 | | | |
| Lead | | 0.0491 | mg/L | 0.0010 | 98 | 90 | 110 | | | |
| Selenium | | 0.0481 | mg/L | 0.0010 | 96 | 90 | 110 | | | |
| Silver | | 0.0199 | mg/L | 0.0010 | 99 | 90 | 110 | | | |
| Uranium | | 0.0480 | mg/L | 0.00030 | 96 | 90 | 110 | | | |
| **Sample ID: ICSA** | 8 | Interference Check Sample A | | | | | | | 05/02/12 11:44 | |
| Arsenic | | 0.00936 | mg/L | 0.0010 | | | | | | |
| Barium | | 2.85E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 0.00986 | mg/L | 0.0010 | | | | | | |
| Chromium | | 0.00959 | mg/L | 0.0010 | | | | | | |
| Lead | | 2.17E-05 | mg/L | 0.0010 | | | | | | |
| Selenium | | 5.69E-05 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.00979 | mg/L | 0.0010 | | | | | | |
| Uranium | | 2.50E-05 | mg/L | 0.00030 | | | | | | |
| **Sample ID: ICSAB** | 8 | Interference Check Sample AB | | | | | | | 05/02/12 11:49 | |
| Arsenic | | 0.0100 | mg/L | 0.0010 | 100 | 70 | 130 | | | |
| Barium | | 4.90E-05 | mg/L | 0.0010 | | | | | | |
| Cadmium | | 0.00995 | mg/L | 0.0010 | 99 | 70 | 130 | | | |
| Chromium | | 0.0102 | mg/L | 0.0010 | 102 | 70 | 130 | | | |
| Lead | | 8.90E-06 | mg/L | 0.0010 | | | | | | |
| Selenium | | 1.01E-05 | mg/L | 0.0010 | | | | | | |
| Silver | | 0.00963 | mg/L | 0.0010 | 96 | 70 | 130 | | | |
| Uranium | | 4.30E-06 | mg/L | 0.00030 | | | | | | |
| **Method: SW6020** | | | | | | | | | Batch: 33486 | |
| **Sample ID: MB-33486** | 8 | Method Blank | | | | Run: ICPMS4-C_120502A | | | 05/02/12 20:11 | |
| Arsenic | | 0.001 | mg/L | 7E-05 | | | | | | |
| Barium | | 0.004 | mg/L | 0.0001 | | | | | | |
| Cadmium | | 0.0001 | mg/L | 4E-05 | | | | | | |
| Chromium | | 0.003 | mg/L | 0.001 | | | | | | |
| Lead | | 0.0001 | mg/L | 3E-05 | | | | | | |
| Selenium | | 0.0001 | mg/L | 6E-05 | | | | | | |
| Silver | | 0.0002 | mg/L | 2E-05 | | | | | | |
| Uranium | | 0.0004 | mg/L | 5E-05 | | | | | | |
| **Sample ID: LCS3-33486** | 8 | Laboratory Control Sample | | | | Run: ICPMS4-C_120502A | | | 05/02/12 20:16 | |
| Arsenic | | 0.47 | mg/L | 0.0010 | 94 | 80 | 120 | | | |
| Barium | | 0.52 | mg/L | 0.050 | 102 | 80 | 120 | | | |
| Cadmium | | 0.26 | mg/L | 0.0010 | 103 | 80 | 120 | | | |
| Chromium | | 0.53 | mg/L | 0.0050 | 104 | 80 | 120 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

ND - Not detected at the reporting limit.

MDC - Minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW6020** | | | | | | | | | | Batch: 33486 |
| **Sample ID: LCS3-33486** | 8 | Laboratory Control Sample | | | | Run: ICPMS4-C_120502A | | | | 05/02/12 20:16 |
| Lead | | 0.54 | mg/L | 0.0010 | 108 | 80 | 120 | | | |
| Selenium | | 0.45 | mg/L | 0.0010 | 90 | 80 | 120 | | | |
| Silver | | 0.052 | mg/L | 0.0010 | 104 | 80 | 120 | | | |
| Uranium | | 0.51 | mg/L | 0.00030 | 101 | 80 | 120 | | | |
| **Sample ID: LCSD3-33486** | 8 | Laboratory Control Sample Duplicate | | | | Run: ICPMS4-C_120502A | | | | 05/02/12 20:20 |
| Arsenic | | 0.50 | mg/L | 0.0010 | 101 | 80 | 120 | 6.7 | 20 | |
| Barium | | 0.54 | mg/L | 0.050 | 107 | 80 | 120 | 4.1 | 20 | |
| Cadmium | | 0.27 | mg/L | 0.0010 | 106 | 80 | 120 | 3.5 | 20 | |
| Chromium | | 0.58 | mg/L | 0.0050 | 115 | 80 | 120 | 9.7 | 20 | |
| Lead | | 0.57 | mg/L | 0.0010 | 114 | 80 | 120 | 4.6 | 20 | |
| Selenium | | 0.48 | mg/L | 0.0010 | 96 | 80 | 120 | 7.2 | 20 | |
| Silver | | 0.055 | mg/L | 0.0010 | 110 | 80 | 120 | 5.5 | 20 | |
| Uranium | | 0.52 | mg/L | 0.00030 | 104 | 80 | 120 | 3.0 | 20 | |
| **Sample ID: C12041044-016AMS3** | 8 | Sample Matrix Spike | | | | Run: ICPMS4-C_120502A | | | | 05/02/12 21:15 |
| Arsenic | | 0.50 | mg/L | 0.0010 | 99 | 75 | 125 | | | |
| Barium | | 0.60 | mg/L | 0.050 | 108 | 75 | 125 | | | |
| Cadmium | | 0.26 | mg/L | 0.0010 | 106 | 75 | 125 | | | |
| Chromium | | 0.57 | mg/L | 0.0050 | 113 | 75 | 125 | | | |
| Lead | | 0.56 | mg/L | 0.0010 | 112 | 75 | 125 | | | |
| Selenium | | 0.49 | mg/L | 0.0010 | 96 | 75 | 125 | | | |
| Silver | | 0.054 | mg/L | 0.0010 | 21 | 75 | 125 | | | S |
| Uranium | | 0.56 | mg/L | 0.00030 | 106 | 75 | 125 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

S - Spike recovery outside of advisory limits.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation

**Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan

**Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW7470A** | | | | | | | | | | Analytical Run: CVAA_C203_120426A |
| **Sample ID: ICV** | Initial Calibration Verification Standard | | | | | | | | | 04/26/12 11:49 |
| Mercury | | 0.00526 | mg/L | 0.00010 | 105 | 90 | 110 | | | |
| **Method: SW7470A** | | | | | | | | | | Batch: 33421 |
| **Sample ID: MB-33421** | Method Blank | | | | | Run: CVAA_C203_120426A | | | | 04/26/12 12:32 |
| Mercury | | ND | mg/L | 3E-05 | | | | | | |
| **Sample ID: LCS-33421** | Laboratory Control Sample | | | | | Run: CVAA_C203_120426A | | | | 04/26/12 12:33 |
| Mercury | | 0.0053 | mg/L | 0.0020 | 106 | 85 | 115 | | | |
| **Sample ID: LCSD-33421** | Laboratory Control Sample Duplicate | | | | | Run: CVAA_C203_120426A | | | | 04/26/12 12:35 |
| Mercury | | 0.0054 | mg/L | 0.0020 | 108 | 85 | 115 | 1.1 | 10 | |
| **Sample ID: C12041044-001ASD** | Serial Dilution | | | | | Run: CVAA_C203_120426A | | | | 04/26/12 12:37 |
| Mercury | | ND | mg/L | 0.0020 | | | | | | |
| **Method: SW7470A** | | | | | | | | | | Analytical Run: CVAA_C203_120430A |
| **Sample ID: ICV** | Initial Calibration Verification Standard | | | | | | | | | 04/30/12 13:50 |
| Mercury | | 0.00522 | mg/L | 0.00010 | 104 | 90 | 110 | | | |
| **Method: SW7470A** | | | | | | | | | | Batch: 33433 |
| **Sample ID: MB-33433** | Method Blank | | | | | Run: CVAA_C203_120430A | | | | 04/30/12 15:12 |
| Mercury | | ND | mg/L | 3E-05 | | | | | | |
| **Sample ID: LCS-33433** | Laboratory Control Sample | | | | | Run: CVAA_C203_120430A | | | | 04/30/12 15:14 |
| Mercury | | 0.00520 | mg/L | 0.0020 | 104 | 85 | 115 | | | |
| **Sample ID: C12041044-003AMS** | Sample Matrix Spike | | | | | Run: CVAA_C203_120430A | | | | 04/30/12 15:19 |
| Mercury | | 0.00519 | mg/L | 0.0020 | 104 | 85 | 115 | | | |
| **Method: SW7470A** | | | | | | | | | | Batch: 33434 |
| **Sample ID: MB-33434** | Method Blank | | | | | Run: CVAA_C203_120430A | | | | 04/30/12 15:30 |
| Mercury | | ND | mg/L | 3E-05 | | | | | | |
| **Sample ID: C12041044-009AMS** | Sample Matrix Spike | | | | | Run: CVAA_C203_120430A | | | | 04/30/12 15:36 |
| Mercury | | 0.00996 | mg/L | 0.0020 | 100 | 85 | 115 | | | |
| **Sample ID: LCS-33434** | Laboratory Control Sample | | | | | Run: CVAA_C203_120430A | | | | 04/30/12 15:45 |
| Mercury | | 0.00504 | mg/L | 0.0020 | 101 | 85 | 115 | | | |
| **Method: SW7470A** | | | | | | | | | | Batch: 33465 |
| **Sample ID: MB-33465** | Method Blank | | | | | Run: CVAA_C203_120430A | | | | 04/30/12 15:52 |
| Mercury | | ND | mg/L | 3E-05 | | | | | | |
| **Sample ID: LCS-33465** | Laboratory Control Sample | | | | | Run: CVAA_C203_120430A | | | | 04/30/12 15:55 |
| Mercury | | 0.00497 | mg/L | 0.0020 | 99 | 85 | 115 | | | |
| **Sample ID: C12041044-016AMS** | Sample Matrix Spike | | | | | Run: CVAA_C203_120430A | | | | 04/30/12 16:04 |
| Mercury | | 0.0105 | mg/L | 0.0020 | 105 | 85 | 115 | | | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Revised Date:** 07/10/12

**Client:** Rio Grande Resources Corporation **Report Date:** 06/13/12

**Project:** Mt. Taylor Mine Closure Plan **Work Order:** C12041044

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: SW7470A** | | | | | | | | | Analytical Run: CVAA_C203_120502A | |
| **Sample ID: ICV** | Initial Calibration Verification Standard | | | | | | | | 05/02/12 10:05 | |
| Mercury | | 0.00516 | mg/L | 0.00010 | 103 | 90 | 110 | | | |
| **Method: SW7470A** | | | | | | | | | Batch: 33523 | |
| **Sample ID: MB-33523** | Method Blank | | | | | Run: CVAA_C203_120502A | | | 05/02/12 11:22 | |
| Mercury | | ND | mg/L | 3E-05 | | | | | | |
| **Sample ID: LCS-33523** | Laboratory Control Sample | | | | | Run: CVAA_C203_120502A | | | 05/02/12 11:23 | |
| Mercury | | 0.00530 | mg/L | 0.0020 | 106 | 85 | 115 | | | |
| **Sample ID: LCSD-33523** | Laboratory Control Sample Duplicate | | | | | Run: CVAA_C203_120502A | | | 05/02/12 11:25 | |
| Mercury | | 0.00541 | mg/L | 0.0020 | 108 | 85 | 115 | 2.1 | 10 | |
| **Sample ID: C12041044-022AMS** | Sample Matrix Spike | | | | | Run: CVAA_C203_120502A | | | 05/02/12 11:27 | |
| Mercury | | 0.00534 | mg/L | 0.0020 | 107 | 85 | 115 | | | |
| **Sample ID: C12041044-028ADIL** | Serial Dilution | | | | | Run: CVAA_C203_120502A | | | 05/02/12 11:39 | |
| Mercury | | ND | mg/L | 0.0020 | | | | | 10 | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

# Standard Reporting Procedures

Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH, Dissolved Oxygen and Residual Chlorine, are qualified as being analyzed outside of recommended holding time.

Solid/soil samples are reported on a wet weight basis (as received) unless specifically indicated. If moisture corrected, data units are typically noted as –dry. For agricultural and mining soil parameters/characteristics, all samples are dried and ground prior to sample analysis.

# Workorder Receipt Checklist

## Rio Grande Resources Corporation C12041044

Login completed by: Kristy Gisse
Date Received: 4/20/2012
Reviewed by: BL2000\kschroeder
Received by: kg
Reviewed Date: 4/26/2012
Carrier name: FedEx

| | | | |
|---|---|---|---|
| Shipping container/cooler in good condition? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on shipping container/cooler? | Yes ☐ | No ☐ | Not Present ☑ |
| Custody seals intact on sample bottles? | Yes ☐ | No ☐ | Not Present ☑ |
| Chain of custody present? | Yes ☑ | No ☐ | |
| Chain of custody signed when relinquished and received? | Yes ☑ | No ☐ | |
| Chain of custody agrees with sample labels? | Yes ☑ | No ☐ | |
| Samples in proper container/bottle? | Yes ☑ | No ☐ | |
| Sample containers intact? | Yes ☑ | No ☐ | |
| Sufficient sample volume for indicated test? | Yes ☐ | No ☑ | |
| All samples received within holding time? (Exclude analyses that are considered field parameters such as pH, DO, Res Cl, Sulfite, Ferrous Iron, etc.) | Yes ☑ | No ☐ | |
| Container/Temp Blank temperature: | 11.2°C No Ice | | |
| Water - VOA vials have zero headspace? | Yes ☐ | No ☐ | No VOA vials submitted ☑ |
| Water - pH acceptable upon receipt? | Yes ☐ | No ☐ | Not Applicable ☑ |

Contact and Corrective Action Comments:

Sample MT-6-A-S3 insufficient volume for testing. Cancelled per phone conversation with Barbara Everett.

# Chain of Custody and Analytical Request Record



PLEASE PRINT- Provide as much information as possible.

| | | | |
|---|---|---|---|
| Company Name: Rio Grande Resources Corp | Project Name, PWS, Permit, Etc.: Mt. Taylor Mine Closure Plan | Sample Origin: State: NM | EPA/State Compliance: Yes ☒ No ☐ |
| Report Mail Address: PO Box 1150, Grants, NM 87020. Additional e-mail copy to beverett@kleinfelder.com | Contact Name: Barbara Everett (Kleinfelder) Phone/Fax: (505) 344-7373, (505) 280-1079 (Cell) | Email: beverett@kleinfelder.com | Sampler: (Please Print) Barbara Everett, Ed Loescher |
| Invoice Address: PO Box 1150, Grants, NM 87020 | Invoice Contact & Phone: Jeanette Lister 505-287-7971 | Purchase Order: | Quote/Bottle Order: C3778 |

Special Report/Formats – ELI must be notified prior to sample submittal for the following:

- ☐ DW
- ☐ GSA
- ☐ POTW/WWTP
- ☐ State: NM
- ☐ Other: _____
- ☐ A2LA
- ☒ EDD/EDT (Electronic Data) Format: excel
- ☐ LEVEL IV
- ☐ NELAC

| SAMPLE IDENTIFICATION (Name, Location, Interval, etc.) | Collection Date | Collection Time | MATRIX | Number of Containers (Sample Type: A Air, W Water, S Soils/Solids, V Vegetation, B Biossay, O Other) | SPLP Extract | RCRA Metals + Uranium | Ra226 & Ra228 | Cl & SO4 by IC 300.0 | RCI | SEE ATTACHED | Normal Turnaround (TAT) | RUSH | Comments |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 MT-1-F | 4-10-12 | 10:45 | Soil Sediment | | X | X | X | | | | X | | 6" B.G. |
| 2 MT-2-D | 4-10-12 | 10:15 | Soil Sediment | | X | X | X | | | | X | | 6' B.G. |
| 3 MT-3-F | 4-10-12 | 11:10 | Soil Sediment | | X | X | X | | | | X | | 6" B.G |
| 4 MT-4-F | 4-10-12 | 9:35 | Soil Sediment | | X | X | X | X | | | X | | 6" B.G |
| 5 MT-5-F | 4-10-12 | 10:00 | Soil Sediment | | X | X | X | X | | | X | | 6" B.G. |
| 6 MT-7-C | 4-10-12 | 9:45 | Soil Sediment | | X | X | X | | | | X | | 6" B.G. |
| 7 MT-UP-E | 4-10-12 | 9:00 | Soil Sediment | | X | X | X | | | | X | | 6" B.G. |
| 8 MT-A-C | 4-10-12 | 10:55 | Soil Sediment | | X | X | X | | | | X | | 6" B.G. |
| 9 MT-Borrow/Backyard | 4-10-12 | 14:00 | Soil Sediment | | X | X | X | | | | X | | 6" B.G. |
| 10 | | | Soil Sediment | | | | | | | | X | | 6" B.G. |

Contact ELI prior to **RUSH** sample submittal for charges and scheduling – See Instruction Page

Shipped by: FE-NOA

Cooler ID(s): 6 Buckets

Receipt Temp: 11.2 °C

On Ice: Yes (No)

Custody Seal Y (N) Intact Y N Signature Match Y N

LABORATORY USE ONLY

**Custody Record MUST be Signed**

| | | |
|---|---|---|
| Relinquished by (print): ED LOESCHER | Date/Time: 4/11/2012 | Signature: |
| Relinquished by (print): BARBARA EVERETT | Date/Time: 4/19/2012 16:00 | Signature: |
| Received by (print): Barbara Everett | Date/Time: 4/11/2012 15:00 | Signature: |
| Received by (print): | Date/Time: | Signature: |
| Received by Laboratory: | Date/Time: 4-20-12 9:45 | Signature: Kris Gross |

Sample Disposal: Return to Client: _____ Lab Disposal: X

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All sub-contract data will be clearly notated on your analytical report.

Visit our web site at www.energylab.com for additional information.

# Chain of Custody and Analytical Request Record



PLEASE PRINT- Provide as much information as possible.

| | | | |
|---|---|---|---|
| Company Name: Rio Grande Resources Corp | Project Name, PWS, Permit, Etc. Mt. Taylor Mine Closure Plan | Sample Origin State: NM | EPA/State Compliance: Yes ☒ No ☐ |
| Report Mail Address: PO Box 1150 Grants, NM 87020 Additional e-mail copy to beverett@kleinfelder.com | Contact Name: Barbara Everett (Kleinfelder) Phone/Fax: (505) 344-7373 (505) 280-1079 (Cell) | Email: beverett@kleinfelder.com | Sampler: (Please Print) Barbara Everett Ed Loescher |
| Invoice Address: PO Box 1150 Grants, NM 87020 | Invoice Contact & Phone: Jeanette Lister 505-287-7971 | Purchase Order: | Quote/Bottle Order: C3778 |

Special Report/Formats – ELI must be notified prior to sample submittal for the following:

☐ DW ☐ GSA ☐ POTW/WWTP ☐ State: NM ☐ Other: _____

☐ A2LA ☒ EDD/EDT (Electronic Data) Format: excel ☐ LEVEL IV ☐ NELAC

Number of Containers
Sample Type: A W S V B O
Air Water Soils/Solids Vegetation Bioassay Other

ANALYSIS REQUESTED

| SAMPLE IDENTIFICATION (Name, Location, Interval, etc.) | Collection Date | Collection Time | MATRIX | SPLP Extract | RCRA Metals + Uranium | Ra226 & Ra228 | Cl & SO4 by IC 300.0 | RCI | SEE ATTACHED | Normal Turnaround (TAT) | RUSH | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 2 1 MT-4-D-S1 | 4-10-12 | 2:05 | Sediment | X | X | X | X | | | X | | 0-6" B.G. |
| 2 2 MT-4-D-S2 | 4-10-12 | 2:10 | Sediment | X | X | X | X | | | X | | 14" B.G. |
| 2 3 MT-4-D-S3 | 4-10-12 | 2:20 | Sediment | X | X | X | X | | | X | | 48" B.G. |
| 3 4 MT-4-E-S1 | 4-10-12 | 1:35 | Sediment | X | X | X | X | | | X | | 0-4" B.G. |
| 3 5 MT-4-E-S2 | 4-10-12 | 1:40 | Sediment | X | X | X | X | | | X | | 10-12" B.G. |
| 3 6 MT-4-E-S3 | 4-10-12 | 1:42 | Sediment | X | X | X | X | | | X | | 36" B.G. |
| 3 7 MT-4-E-S4 | 4-10-12 | 1:45 | Sediment | X | X | X | X | | | X | | 48" B.G. |
| 4 8 MT-6-A-S1 | 4-10-12 | 3:05 | Sediment | X | X | X | | | | X | | 0-5" B.G. |
| 4 9 MT-6-A-S2 | 4-10-12 | 3:10 | Sediment | X | X | X | | | | X | | 12"-20" B.G. |
| 4 10 MT-6-A-S3 | 4-10-12 | 3:15 | ~~Sediment~~ | X | X | X | | | | X | | Rock chip |

Contact ELI prior to RUSH sample submittal for charges and scheduling – See Instruction Page

Comments:

Shipped by: FE-NOA

Cooler ID(s): 6 Coolers

Receipt Temp: 11.2 °C

On Ice: Yes (NO)

Custody Seal Y N

Intact Y N

Signature Match Y N

LABORATORY USE ONLY

**Custody Record MUST be Signed**

| | | | |
|---|---|---|---|
| Relinquished by (print): Ed Loescher | Date/Time: 4/11/12 | Signature: | Received by (print): BARBARA EVERETT Date/Time: 4/11/12 15:00 Signature: |
| Relinquished by (print): BARBARA EVERETT | Date/Time: 4/19/1600 | Signature: | Received by (print): Date/Time: Signature: |
| Sample Disposal: Return to Client: _____ | Lab Disposal: X | | Received by Laboratory: Date/Time: 4-20-12 T:45 Signature: Kris Gross |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All sub-contract data will be clearly notated on your analytical report.

Visit our web site at www.energylab.com for additional information, price schedules and terms and conditions.

# Chain of Custody and Analytical Request Record



PLEASE PRINT- Provide as much information as possible.

| | | | |
|---|---|---|---|
| Company Name: Rio Grande Resources Corp | Project Name, PWS, Permit, Etc.: Mt. Taylor Mine Closure Plan | Sample Origin: State: NM | EPA/State Compliance: Yes ☒ No ☐ |
| Report Mail Address: PO Box 1150, Grants, NM 87020. Additional e-mail copy to beverett@kleinfelder.com | Contact Name: Barbara Everett (Kleinfelder) Phone/Fax: (505) 344-7373 (505) 280-1079 (Cell) | Email: beverett@kleinfelder.com | Sampler: (Please Print) Barbara Everett, Ed Loescher |
| Invoice Address: PO Box 1150, Grants, NM 87020 | Invoice Contact & Phone: Jeanette Lister 505-287-7971 | Purchase Order: | Quote/Bottle Order: C3778 |

Special Report/Formats – ELI must be notified prior to sample submittal for the following:

- ☐ DW
- ☐ GSA
- ☐ POTW/WWTP
- ☐ State: NM
- ☐ Other:
- ☐ A2LA
- ☒ EDD/EDT (Electronic Data) Format: excel
- ☐ LEVEL IV
- ☐ NELAC

Number of Containers; Sample Type: A Air, W Water, S Soils/Solids, V Vegetation, B Bioassay, O Other

ANALYSIS REQUESTED

| | SAMPLE IDENTIFICATION (Name, Location, Interval, etc.) | Collection Date | Collection Time | MATRIX | SPLP Extract | RCRA Metals + Uranium | Ra226 & Ra228 | Cl & SO4 by IC 300.0 | RCI | SEE ATTACHED | Normal Turnaround (TAT) | RUSH | Comments |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | MT-6-B-S1 | 4-10-12 | 2:30 | Sediment | X | X | X | | | | X | | 8"-10" B.G. |
| 1 | 2 MT-6-B-S2 | 4-10-12 | 2:35 | Sediment | X | X | X | | | | X | | 30" B.G. |
| 1 | 3 MT-OP-C-S1 | 4-10-12 | 1:20 | Sediment | X | X | X | | | | X | | 0"-6" B.G. |
| 1 | 4 MT-OP-C-S2 | 4-10-12 | 1:25 | Sediment | X | X | X | | | | X | | 20" B.G. |
| 1 | 5 MT-OP-C-S3 | 4-10-12 | 1:25 | Sediment | X | X | X | | | | X | | 48"-50" B.G. |
| 1 | 6 MT-OP-C-S4 | 4-10-12 | 1:30 | Sediment | X | X | X | | | | X | | 72" B.G. |
| 2 | 7 MT-OP-D-S1 | 4-10-12 | 12:45 | Sediment | X | X | X | | | | X | | 0-6" B.G. |
| 2 | 8 MT-OP-D-S2 | 4-10-12 | 12:45 | Sediment | X | X | X | | | | X | | 48-50" B.G. |
| 2 | 9 MT-OP-D-S3 | 4-10-12 | 12:50 | Sediment | X | X | X | | | | X | | 76" B.G. |
| 4 | 10 MT-8-F | 4-10-12 | 09:25 | Sediment | X | X | X | X | | | X | | 6" B.G. |

Page 50 of 50

Contact ELI prior to RUSH sample submittal for charges and scheduling – See Instruction Page

Shipped by: FE-MAIL

Cooler ID(s): 6 buckets

Receipt Temp: 11.2 °C

On Ice: Yes (No)

Custody Seal Intact: Y (N) / Signature Match: Y N

LABORATORY USE ONLY

**Custody Record MUST be Signed**

Relinquished by (print): ED LOESCHER Date/Time: 4-11-12 Signature:

Relinquished by (print): BARBARA EVERETT Date/Time: 4/19/12 16:00 Signature:

Received by (print): BARBARA EVERETT Date/Time: 4/11/12 15:00 Signature:

Received by (print): Date/Time: Signature:

Sample Disposal: Return to Client: Lab Disposal: X

Received by Laboratory: Date/Time: 4-20-12 9:45 Signature:

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested. This serves as notice of this possibility. All sub-contract data will be clearly notated on your analytical report.

Visit our web site at www.energylab.com for additional information, downloadable fee schedule, forms, and links.

# ANALYTICAL SUMMARY REPORT

July 05, 2012

Rio Grande Resources Corporation
PO Box 1150
Grants, NM 87020

Workorder No.: C12050924

Project Name: Mt. Taylor Mine

Energy Laboratories, Inc. Casper WY received the following 3 samples for Rio Grande Resources Corporation on 5/24/2012 for analysis.

| Sample ID | Client Sample ID | Collect Date | Receive Date | Matrix | Test |
|---|---|---|---|---|---|
| C12050924-001 | MT-WP-SM1 | 05/18/12 9:30 | 05/24/12 | Soil | Digestion For RadioChemistry<br>Radium 226<br>Uranium, Isotopic |
| C12050924-002 | MT-WP-SM2 | 05/18/12 9:40 | 05/24/12 | Soil | Same As Above |
| C12050924-003 | MT-WP-SM3 | 05/18/12 10:00 | 05/24/12 | Soil | Same As Above |

The results as reported relate only to the item(s) submitted for testing. The analyses presented in this report were performed at Energy Laboratories, Inc., 2393 Salt Creek Hwy., Casper, WY 82601, unless otherwise noted. Radiochemistry analyses were performed at Energy Laboratories, Inc., 2325 Kerzell Lane, Casper, WY 82601, unless otherwise noted. Any exceptions or problems with the analyses are noted in the Laboratory Analytical Report, the QA/QC Summary Report, or the Case Narrative.

If you have any questions regarding these test results, please call.

Report Approved By:

Stephanie D Waldrop
Reporting Supervisor

Digitally signed by
Stephanie Waldrop
Date: 2012.07.05 16:09:59 -06:00

**CLIENT:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Sample Delivery Group:** C12050924

**Report Date:** 07/05/12

# CASE NARRATIVE

ORIGINAL SAMPLE SUBMITTAL(S)
All original sample submittals have been returned with the data package.

SAMPLE TEMPERATURE COMPLIANCE: 4°C (±2°C)
Temperature of samples received may not be considered properly preserved by accepted standards. Samples that are hand delivered immediately after collection shall be considered acceptable if there is evidence that the chilling process has begun.

GROSS ALPHA ANALYSIS
Method 900.0 for gross alpha and gross beta is intended as a drinking water method for low TDS waters. Data provided by this method for non potable waters should be viewed as inconsistent.

RADON IN AIR ANALYSIS
The desired exposure time is 48 hours (2 days). The time delay in returning the canister to the laboratory for processing should be as short as possible to avoid excessive decay. Maximum recommended delay between end of exposure to beginning of counting should not exceed 8 days.

SOIL/SOLID SAMPLES
All samples reported on an as received basis unless otherwise indicated.

ATRAZINE, SIMAZINE AND PCB ANALYSIS
Data for PCBs, Atrazine and Simazine are reported from EPA 525.2. PCB data reported by ELI reflects the results for seven individual Aroclors. When the results for all seven are ND (not detected), the sample meets EPA compliance criteria for PCB monitoring.

SUBCONTRACTING ANALYSIS
Subcontracting of sample analyses to an outside laboratory may be required. If so, ENERGY LABORATORIES will utilize its branch laboratories or qualified contract laboratories for this service. Any such laboratories will be indicated within the Laboratory Analytical Report.

BRANCH LABORATORY LOCATIONS
eli-b - Energy Laboratories, Inc. - Billings, MT
eli-g - Energy Laboratories, Inc. - Gillette, WY
eli-h - Energy Laboratories, Inc. - Helena, MT
eli-r - Energy Laboratories, Inc. - Rapid City, SD
eli-t - Energy Laboratories, Inc. - College Station, TX

CERTIFICATIONS:
USEPA: WY00002, Radiochemical WY00937; FL-DOH NELAC: E87641, Radiochemical E871017; California: 02118CA; Oregon: WY200001, Radiochemical WY200002; Utah: WY00002; Virginia: 00057; Washington: C836

ISO 17025 DISCLAIMER:
The results of this Analytical Report relate only to the items submitted for analysis.

ENERGY LABORATORIES, INC. - CASPER,WY certifies that certain method selections contained in this report meet requirements as set forth by the above accrediting authorities. Some results requested by the client may not be covered under these certifications. All analysis data to be submitted for regulatory enforcement should be certified in the sample state of origin. Please verify ELI's certification coverage by visiting www.energylab.com

ELI appreciates the opportunity to provide you with this analytical service. For additional information and services visit our web page www.energylab.com.

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12050924-001
**Client Sample ID:** MT-WP-SM1

**Report Date:** 07/05/12
**Collection Date:** 05/18/12 09:30
**DateReceived:** 05/24/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.7 | pCi/g-dry | | | | E903.0 | 06/20/12 01:37 / dmf |
| Radium 226 precision (±) | 0.08 | pCi/g-dry | | | | E903.0 | 06/20/12 01:37 / dmf |
| Radium 226 MDC | 0.04 | pCi/g-dry | | | | E903.0 | 06/20/12 01:37 / dmf |
| Uranium 234 | 0.6 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 234 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 234 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 235 | 0.03 | pCi/g-dry | U | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 235 precision (±) | 0.09 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 235 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 238 | 0.6 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 238 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12050924-002
**Client Sample ID:** MT-WP-SM2

**Report Date:** 07/05/12
**Collection Date:** 05/18/12 09:40
**DateReceived:** 05/24/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 0.7 | pCi/g-dry | | | | E903.0 | 06/20/12 01:37 / dmf |
| Radium 226 precision (±) | 0.08 | pCi/g-dry | | | | E903.0 | 06/20/12 01:37 / dmf |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 06/20/12 01:37 / dmf |
| Uranium 234 | 0.8 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 234 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 234 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 235 | 0.1 | pCi/g-dry | U | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 235 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 235 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 238 | 0.4 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 238 precision (±) | 0.2 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 238 MDC | 0.3 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# LABORATORY ANALYTICAL REPORT

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation
**Project:** Mt. Taylor Mine
**Lab ID:** C12050924-003
**Client Sample ID:** MT-WP-SM3

**Report Date:** 07/05/12
**Collection Date:** 05/18/12 10:00
**DateReceived:** 05/24/12
**Matrix:** Soil

| Analyses | Result | Units | Qualifier | RL | MCL/ QCL | Method | Analysis Date / By |
|---|---|---|---|---|---|---|---|
| **RADIONUCLIDES** | | | | | | | |
| Radium 226 | 1.1 | pCi/g-dry | | | | E903.0 | 06/20/12 01:37 / dmf |
| Radium 226 precision (±) | 0.09 | pCi/g-dry | | | | E903.0 | 06/20/12 01:37 / dmf |
| Radium 226 MDC | 0.03 | pCi/g-dry | | | | E903.0 | 06/20/12 01:37 / dmf |
| Uranium 234 | 1.1 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 234 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 234 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 235 | -0.02 | pCi/g-dry | U | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 235 precision (±) | 0.09 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 235 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 238 | 0.9 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 238 precision (±) | 0.3 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |
| Uranium 238 MDC | 0.2 | pCi/g-dry | | | | E908.0 | 06/18/12 08:39 / dmf |

**Report Definitions:**
RL - Analyte reporting limit.
QCL - Quality control limit.
MDC - Minimum detectable concentration
MCL - Maximum contaminant level.
ND - Not detected at the reporting limit.
U - Not detected at minimum detectable concentration

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation **Report Date:** 07/05/12

**Project:** Mt. Taylor Mine **Work Order:** C12050924

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E903.0** | | | | | | | | | | Batch: R161002 |
| **Sample ID: LCS-33822** | | Laboratory Control Sample | | | | Run: BERTHOLD 770-1_120612A | | | | 06/20/12 01:37 |
| Radium 226 | | 0.29 | pCi/g-dry | | 60 | 70 | 130 | | | S |
| - LCS response is outside of the acceptance range for this analysis. Since the MB, MS, and MSD are acceptable the batch is approved. | | | | | | | | | | |
| **Sample ID: MB-33822** | 3 | Method Blank | | | | Run: BERTHOLD 770-1_120612A | | | | 06/20/12 01:37 |
| Radium 226 | | -0.003 | pCi/g-dry | | | | | | | U |
| Radium 226 precision (±) | | 0.003 | pCi/g-dry | | | | | | | |
| Radium 226 MDC | | 0.006 | pCi/g-dry | | | | | | | |
| **Sample ID: C12050924-003AMS** | | Sample Matrix Spike | | | | Run: BERTHOLD 770-1_120612A | | | | 06/20/12 01:37 |
| Radium 226 | | 4.6 | pCi/g-dry | | 72 | 70 | 130 | | | |
| **Sample ID: C12050924-003AMSD** | | Sample Matrix Spike Duplicate | | | | Run: BERTHOLD 770-1_120612A | | | | 06/20/12 01:37 |
| Radium 226 | | 4.5 | pCi/g-dry | | 71 | 70 | 130 | 2.5 | 23.8 | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

U - Not detected at minimum detectable concentration

ND - Not detected at the reporting limit.

S - Spike recovery outside of advisory limits.

# QA/QC Summary Report

Prepared by Casper, WY Branch

**Client:** Rio Grande Resources Corporation **Report Date:** 07/05/12

**Project:** Mt. Taylor Mine **Work Order:** C12050924

| Analyte | Count | Result | Units | RL | %REC | Low Limit | High Limit | RPD | RPDLimit | Qual |
|---|---|---|---|---|---|---|---|---|---|---|
| **Method: E908.0** | | | | | | | | | | Batch: R160930 |
| **Sample ID: C12050924-003AMS** | 2 | Sample Matrix Spike | | | | Run: EGG-ORTEC_120614A | | | | 06/18/12 08:39 |
| Uranium 234 | | 52.2 | pCi/g-dry | | 115 | 70 | 130 | | | |
| Uranium 238 | | 53.1 | pCi/g-dry | | 115 | 70 | 130 | | | |
| **Sample ID: C12050924-003AMSD** | 2 | Sample Matrix Spike Duplicate | | | | Run: EGG-ORTEC_120614A | | | | 06/18/12 08:39 |
| Uranium 234 | | 51.9 | pCi/g-dry | | 110 | 70 | 130 | 0.6 | 28 | |
| Uranium 238 | | 54.9 | pCi/g-dry | | 114 | 70 | 130 | 3.3 | 27.8 | |
| **Sample ID: LCS-33822** | 2 | Laboratory Control Sample | | | | Run: EGG-ORTEC_120614A | | | | 06/18/12 08:39 |
| Uranium 234 | | 2.52 | pCi/g-dry | | 108 | 80 | 120 | | | |
| Uranium 238 | | 2.59 | pCi/g-dry | | 109 | 80 | 120 | | | |
| **Sample ID: MB-33822** | 9 | Method Blank | | | | Run: EGG-ORTEC_120614A | | | | 06/18/12 08:39 |
| Uranium 234 | | 0.01 | pCi/g-dry | | | | | | | U |
| Uranium 234 precision (±) | | 0.02 | pCi/g-dry | | | | | | | |
| Uranium 234 MDC | | 0.03 | pCi/g-dry | | | | | | | |
| Uranium 235 | | 0.0009 | pCi/g-dry | | | | | | | U |
| Uranium 235 precision (±) | | 0.01 | pCi/g-dry | | | | | | | |
| Uranium 235 MDC | | 0.03 | pCi/g-dry | | | | | | | |
| Uranium 238 | | 0.007 | pCi/g-dry | | | | | | | U |
| Uranium 238 precision (±) | | 0.01 | pCi/g-dry | | | | | | | |
| Uranium 238 MDC | | 0.03 | pCi/g-dry | | | | | | | |

**Qualifiers:**

RL - Analyte reporting limit.

MDC - Minimum detectable concentration

ND - Not detected at the reporting limit.

U - Not detected at minimum detectable concentration

# Standard Reporting Procedures

Lab measurement of analytes considered field parameters that require analysis within 15 minutes of sampling such as pH, Dissolved Oxygen and Residual Chlorine, are qualified as being analyzed outside of recommended holding time.

Solid/soil samples are reported on a wet weight basis (as received) unless specifically indicated. If moisture corrected, data units are typically noted as –dry. For agricultural and mining soil parameters/characteristics, all samples are dried and ground prior to sample analysis.

---

# Workorder Receipt Checklist

## Rio Grande Resources Corporation C12050924

Login completed by: Brian H. Cody
Date Received: 5/24/2012

Reviewed by: BL2000\kschroeder
Received by: kg

Reviewed Date: 5/25/2012
Carrier name: Ground

| | | | |
|---|---|---|---|
| Shipping container/cooler in good condition? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on shipping container/cooler? | Yes ☑ | No ☐ | Not Present ☐ |
| Custody seals intact on sample bottles? | Yes ☐ | No ☐ | Not Present ☑ |
| Chain of custody present? | Yes ☑ | No ☐ | |
| Chain of custody signed when relinquished and received? | Yes ☑ | No ☐ | |
| Chain of custody agrees with sample labels? | Yes ☑ | No ☐ | |
| Samples in proper container/bottle? | Yes ☑ | No ☐ | |
| Sample containers intact? | Yes ☑ | No ☐ | |
| Sufficient sample volume for indicated test? | Yes ☑ | No ☐ | |
| All samples received within holding time? (Exclude analyses that are considered field parameters such as pH, DO, Res Cl, Sulfite, Ferrous Iron, etc.) | Yes ☑ | No ☐ | |
| Container/Temp Blank temperature: | 22.3°C | | |
| Water - VOA vials have zero headspace? | Yes ☐ | No ☐ | No VOA vials submitted ☑ |
| Water - pH acceptable upon receipt? | Yes ☐ | No ☐ | Not Applicable ☑ |

Contact and Corrective Action Comments:

None

# Chain of Custody and Analytical Request Record



PLEASE PRINT- Provide as much information as possible.

| | | | |
|---|---|---|---|
| Company Name: Rio Grande Resources Corporation - NM #C11115 | Project Name, PWS, Permit, Etc.: MT. TAYLOR MINE | Sample Origin State: NM | EPA/State Compliance: Yes ☑ No ☐ |
| Report Mail Address: PO Box 1150 Grants, New Mexico 87020 | Contact Name: Joe Lister - Mine Manage | Phone/Fax: (505)287-7971 | Email: joe.lister@riograndereso |
| | | | Sampler: (Please Print) Joel Lister/AK |
| Invoice Address: Rio grande Resources Corporation PO Box 1150 Grants, new Mexico 87020 | Invoice Contact & Phone: Joe Lister - Mine Managr | Purchase Order: | Quote/Bottle Order: Soil Samples |

Special Report/Formats – ELI must be notified prior to sample submittal for the following:

☐ DW ☐ A2LA
☐ GSA ☐ EDD/EDT (Electronic Data)
☐ POTW/WWTP Format: _____
☐ State: _____ ☐ LEVEL IV
☐ Other: _____ ☐ NELAC

Number of Containers
Sample Type: A W S V B O
Air Water Soils/Solids Vegetation Bioassay Other

ANALYSIS REQUESTED

| SAMPLE IDENTIFICATION (Name, Location, Interval, etc.) | Collection Date | Collection Time | MATRIX | Isotopic Uranium | Radium 226 | SEE ATTACHED | Normal Turnaround (TAT) |
|---|---|---|---|---|---|---|---|
| 1 MT - WP - SM1 | 05/18/12 | 09:30 | soil | X | X | | |
| 2 MT - WP - SM2 | 05/18/12 | 09:40 | soil | X | X | | |
| 3 MT - WP - SM3 | 05/18/12 | 10:00 | soil | X | X | | |
| 4 | | | | | | | |
| 5 | | | | | | | |
| 6 | | | | | | | |
| 7 | | | | | | | |
| 8 | | | | | | | |
| 9 | | | | | | | |
| 10 | | | | | | | |

RUSH

Contact ELI prior to **RUSH** sample submittal for charges and scheduling – See Instruction Page

Comments:

Shipped by: UPS- G
Cooler ID(s): BOX
Receipt Temp 22.3 °C
On Ice: Yes (No)
Custody Seal (Y) N
Intact (Y) N
Signature Match (Y) N

LABORATORY USE ONLY C12050924

**Custody Record MUST be Signed**

| | | | | | |
|---|---|---|---|---|---|
| Relinquished by (print): Joe Lister | Date/Time: 05/22/12 09:19 | Signature: | Received by (print): | Date/Time: | Signature: |
| Relinquished by (print): | Date/Time: | Signature: | Received by (print): | Date/Time: | Signature: |
| Sample Disposal: Return to Client: _____ | Lab Disposal: XXXXX | | Received by Laboratory: | Date/Time: 5-24-12 9:15 | Signature: |

In certain circumstances, samples submitted to Energy Laboratories, Inc. may be subcontracted to other certified laboratories in order to complete the analysis requested.
This serves as notice of this possibility. All sub-contract data will be clearly notated on your analytical report.
Visit our web site at www.energylab.com for additional information, downloadable fee schedule, forms, and links.

# MT. TAYLOR ORE CHEMICAL ANALYSIS
MARCH 18, 1986

| | % BY WEIGHT |
|---|---|
| Sodium | 1.62 |
| Magnesium | 0.605 |
| Aluminum | < 0.01 |
| Silicon | 33.40 |
| Sulfur | 0.118 |
| Chlorine | 0.030 |
| Calcium | 1.06 |
| Titanium | 0.149 |
| Vanadium | 0.091 |
| Chromium | < 0.01 |
| Manganese | 0.03 |
| Iron | 1.52 |
| Cobalt | < 0.01 |
| Nickel | < 0.01 |
| Copper | < 0.01 |
| Zinc | < 0.01 |
| Arsenic | < 0.01 |
| Selenium | 0.009 |
| Bromide | < 0.01 |
| Rubidium | 0.016 |
| Strontium | 0.012 |
| Zirconium | 0.009 |
| Molybdenum | 0.003 |
| Lead | 0.012 |
| Thorium | 0.009 |
| Uranium | 0.420 |

# APPENDIX D.4

## Field Sampling and Laboratory Test Data

Original Closeout Plan Soil Data

Vinyard & Associates, Inc.

4415-D Hawkins, NE
Albuquerque, New Mexico 87109
(505) 345-1937

Geotechnical Engineering • Materials Testing • Environmental Engineering

November 6, 1995

AK GeoConsult, Inc.
13212 Manitoba Drive, NE
Albuquerque, NM 87111

Attn: Mr. Alan K. Kuhn, PhD, PE

Subject: Mt. Taylor Mine Soil Samples
V & A Project No. 95-1-245

Gentlemen:

Attached are copies of the Proctor, Sieve Analysis and Atterberg Limits Test Results for the Mt. Taylor Mine Soil Samples.

Should you have any questions regarding this data, please do not hesitate to call.

Sincerely,


Martin D. Vinyard, PE

Attachments: Data Sheets (10)

cc: Addressee (1)

V & A

# COMPACTION TEST RESULTS




SAMPLE LOCATION: TP-1

SOIL DESCRIPTION: CLAY, very sandy

UNIFIED SOIL CLASSIFICATION: (CL)

AASHTO SOIL CLASSIFICATION:

TEST METHOD: ASTM D-698

ATTERBERG LIMITS: LL 38 % PI 18 %


| SIEVE ANALYSIS - % PASSING | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1 1/2" | 3/4" | 3/8" | No. 4 | No. 8 | No. 16 | No. 30 | No. 50 | No. 100 | No. 200 |
| | | | | | 100 | 99 | 96 | 79 | 66.4 |

Project No: 95-1-245

Figure

V & A

# COMPACTION TEST RESULTS




SAMPLE LOCATION: TP-4A

SOIL DESCRIPTION: CLAY, very sandy

UNIFIED SOIL CLASSIFICATION: (CL)

AASHTO SOIL CLASSIFICATION:

TEST METHOD: ASTM D-698

ATTERBERG LIMITS: LL 39 % PI 21 %


| SIEVE ANALYSIS - % PASSING | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1 1/2" | 3/4" | 3/8" | No. 4 | No. 8 | No. 16 | No. 30 | No. 50 | No. 100 | No. 200 |
| | | | | 100 | 99 | 97 | 94 | 80 | 69.4 |

Project No: 95-1-245

Figure

V & A

# COMPACTION TEST RESULTS




SAMPLE LOCATION: TP-6

SOIL DESCRIPTION: SAND, very clayey

UNIFIED SOIL CLASSIFICATION: (SC)

AASHTO SOIL CLASSIFICATION:

TEST METHOD: ASTM D-698

ATTERBERG LIMITS: LL 29 % PI 14 %


| SIEVE ANALYSIS - % PASSING | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1 1/2" | 3/4" | 3/8" | No. 4 | No. 8 | No. 16 | No. 30 | No. 50 | No. 100 | No. 200 |
| | | 100 | 99 | 98 | 95 | 93 | 89 | 63 | 48.5 |

Project No: 95-1-245

Figure

V & A

# COMPACTION TEST RESULTS




SAMPLE LOCATION: TP-7

SOIL DESCRIPTION: CLAY, very sandy

UNIFIED SOIL CLASSIFICATION: (CL)

AASHTO SOIL CLASSIFICATION:

TEST METHOD: ASTM D-698

ATTERBERG LIMITS: LL 38 % PI 21 %


| SIEVE ANALYSIS - % PASSING | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1 1/2" | 3/4" | 3/8" | No. 4 | No. 8 | No. 16 | No. 30 | No. 50 | No. 100 | No. 200 |
| | | | | 100 | 99 | 96 | 92 | 76 | 67.3 |

Project No: 95-1-245

Figure

V & A

# COMPACTION TEST RESULTS




SAMPLE LOCATION: TP-8

SOIL DESCRIPTION: CLAY, very sandy

UNIFIED SOIL CLASSIFICATION: (CL)

AASHTO SOIL CLASSIFICATION:

TEST METHOD: ASTM D-698

ATTERBERG LIMITS: LL 37 % PI 20 %


| SIEVE ANALYSIS - % PASSING | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1 1/2" | 3/4" | 3/8" | No. 4 | No. 8 | No. 16 | No. 30 | No. 50 | No. 100 | No. 200 |
| | | | | 100 | 99 | 97 | 94 | 78 | 63.3 |

Project No: 95-1-245

Figure

V & A

# COMPACTION TEST RESULTS




SAMPLE LOCATION: TP-9

SOIL DESCRIPTION: CLAY, very sandy

UNIFIED SOIL CLASSIFICATION: (CL)

AASHTO SOIL CLASSIFICATION:

TEST METHOD: ASTM D-698

ATTERBERG LIMITS: LL 44 % PI 26 %


| SIEVE ANALYSIS - % PASSING | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1 1/2" | 3/4" | 3/8" | No. 4 | No. 8 | No. 16 | No. 30 | No. 50 | No. 100 | No. 200 |
| | | | | | 100 | 99 | 97 | 90 | 79.5 |

Project No: 95-1-245

Figure

V & A

# COMPACTION TEST RESULTS




SAMPLE LOCATION: TP-10

SOIL DESCRIPTION: CLAY, very sandy

UNIFIED SOIL CLASSIFICATION: (CL)

AASHTO SOIL CLASSIFICATION:

TEST METHOD: ASTM D-698

ATTERBERG LIMITS: LL 34 % PI 19 %


| SIEVE ANALYSIS - % PASSING | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1 1/2" | 3/4" | 3/8" | No. 4 | No. 8 | No. 16 | No. 30 | No. 50 | No. 100 | No. 200 |
| | | | 100 | 99 | 99 | 98 | 95 | 82 | 72.8 |

Project No: 95-1-245

Figure

V & A

# COMPACTION TEST RESULTS




SAMPLE LOCATION: TP-11

SOIL DESCRIPTION: CLAY, sandy

UNIFIED SOIL CLASSIFICATION: (CL)

AASHTO SOIL CLASSIFICATION:

TEST METHOD: ASTM D-698

ATTERBERG LIMITS: LL 44 % PI 25 %

| SIEVE ANALYSIS - % PASSING | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1 1/2" | 3/4" | 3/8" | No. 4 | No. 8 | No. 16 | No. 30 | No. 50 | No. 100 | No. 200 |
| | | | | | 100 | 99 | 97 | 90 | 80.3 |

Project No: 95-1-245

Figure

V & A

# SUMMARY OF LABORATORY TEST DATA

| Test Hole No. | Depth (Feet) | Unified Classification | Natural Dry Density (pcf) | Natural Moisture Content (%) | Atterberg Limits | | SIEVE ANALYSIS % PASSING BY WEIGHT | | | | | | | | | | DESCRIPTION |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | LL | PI | 1½" | 3/4" | 3/8" | No. 4 | No. 8 | No. 16 | No. 30 | No. 50 | No. 100 | No. 200 | |
| TP1 | - | - | - | - | 38 | 18 | - | - | - | - | - | 100 | 99 | 96 | 79 | 66.4 | CLAY, very sandy |
| TP2 | - | - | - | - | 28 | 11 | - | - | 100 | 99 | 98 | 97 | 96 | 91 | 60 | 45.3 | SAND, very clayey |
| TP3 | - | - | - | - | 28 | 13 | - | - | - | 100 | 99 | 99 | 98 | 94 | 68 | 51.9 | CLAY, very sandy |
| TP4A | - | - | - | - | 39 | 21 | - | - | - | - | 100 | 99 | 97 | 94 | 80 | 69.4 | CLAY, very sandy |
| TP4B | - | - | - | - | 38 | 21 | - | - | - | - | 100 | 99 | 98 | 97 | 88 | 75.7 | CLAY, very sandy |
| TP5 | - | - | - | - | 30 | 16 | - | - | - | - | 100 | 99 | 98 | 94 | 77 | 65.0 | CLAY, very sandy |
| TP6 | - | - | - | - | 29 | 14 | - | - | 100 | 99 | 98 | 95 | 93 | 89 | 63 | 48.5 | SAND, very clayey |
| TP7 | - | - | - | - | 38 | 21 | - | - | - | - | 100 | 99 | 96 | 92 | 76 | 67.3 | CLAY, very sandy |
| TP8 | - | - | - | - | 37 | 20 | - | - | - | - | 100 | 99 | 97 | 94 | 78 | 63.3 | CLAY, very sandy |
| TP9 | - | - | - | - | 44 | 26 | - | - | - | - | - | 100 | 99 | 97 | 90 | 79.5 | CLAY, very sandy |
| TP10 | - | - | - | - | 34 | 19 | - | - | - | 100 | 99 | 99 | 98 | 95 | 82 | 72.8 | CLAY, very sandy |
| TP11 | - | - | - | - | 44 | 25 | - | - | - | - | - | 100 | 99 | 97 | 90 | 80.3 | CLAY, very sandy |

Project No. 95-1-245

Table

V & A

# SIEVE ANALYSIS TEST RESULTS

| Sieve Size | Percent Passing Following Scalping over a 3/4" Sieve WP-1 | WP-2 |
|---|---|---|
| 3/4" | 100 | 100 |
| 3/8" | 94 | 98 |
| No. 4 | 91 | 95 |
| No. 8 | 89 | 93 |
| No. 16 | 87 | 91 |
| No. 30 | 81 | 87 |
| No. 50 | 43 | 65 |
| No. 100 | 23 | 37 |
| No. 200 | 17.8 | 27.7 |


WP-1 + 3/4" material = 2.7% of total sample weight

WP-2 + 3/4" material = 6.8% of total sample weight

WASTE ROCK CHARACTERISTICS
MT. TAYLOR MINE

SIZE GRADATIONS


| SIEVE # | SIZE in mm | % PASSING | |
|---|---|---|---|
| | | WP-1 | WP-2 |
| 3/4" | 19.1 | 100 | 100 |
| 3/8" | 9.52 | 94 | 98 |
| 4 | 4.76 | 91 | 95 |
| 8 | 2.38 | 89 | 93 |
| 16 | 1.19 | 87 | 91 |
| 30 | 0.59 | 71 | 87 |
| 50 | 0.297 | 43 | 65 |
| 100 | 0.149 | 23 | 37 |
| 200 | 0.074 | 17.8 | 27.7 |



## NATIVE SOIL - COVER SOIL CHARACTERISTICS
## MT. TAYLOR MINE

### SIZE GRADATIONS


| SIEVE # | SIZE in mm | % PASSING FOR SAMPLE #: | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | TP1 | TP2 | TP3 | TP4A | TP4B | TP5 | TP6 | TP7 | TP8 | TP9 | TP10 | TP11 | AVERAGE |
| 3/4" | 19.1 | | | | | | | | | | | | | |
| 3/8" | 9.52 | | 100 | | | | | 100 | | | | | | 100 |
| 4 | 4.76 | | 99 | 100 | | | | 99 | | | | | | 99 |
| 8 | 2.38 | | 98 | 99 | 100 | 100 | 100 | 98 | 100 | 100 | | 100 | | 99 |
| 16 | 1.19 | 100 | 97 | 99 | 99 | 99 | 99 | 95 | 99 | 99 | 100 | 99 | 100 | 99 |
| 30 | 0.59 | 99 | 96 | 98 | 97 | 98 | 98 | 93 | 96 | 97 | 99 | 98 | 99 | 97 |
| 50 | 0.297 | 96 | 91 | 94 | 94 | 97 | 94 | 89 | 92 | 94 | 97 | 95 | 97 | 94 |
| 100 | 0.149 | 79 | 60 | 68 | 80 | 88 | 77 | 63 | 76 | 78 | 90 | 82 | 90 | 78 |
| 200 | 0.074 | 66.4 | 45.3 | 51.9 | 69.4 | 75.7 | 65 | 48.5 | 67.3 | 63.3 | 79.5 | 72.6 | 80.3 | 65 |
| | | | | | | | | | | | | | | |
| USCS = | | CL | SC | CL | CL | CL | CL | SC | CL | CL | CL | CL | CL | CL |
| LL = | | 38 | 28 | 28 | 39 | 38 | 30 | 29 | 38 | 37 | 44 | 34 | 44 | 36 |
| PI = | | 18 | 11 | 13 | 21 | 21 | 16 | 14 | 21 | 20 | 26 | 19 | 25 | 19 |
| | | | | | | | | | | | | | | |
| d75 = | | 0.15 | 0.2 | 0.19 | 0.1 | 0.06 | 0.13 | 0.2 | 0.14 | 0.15 | 0.05 | 0.09 | 0.18 | 0.14 |



# WASTE ROCK CHARACTERISTICS
# MT. TAYLOR MINE

## SIZE GRADATIONS

| SIEVE # | SIZE in mm | % PASSING | | | |
|---|---|---|---|---|---|
| | | WP-1 | WP-2 | AVERAGE | |
| 3/4" | 19.1 | 100 | 100 | 100 | |
| 3/8" | 9.52 | 94 | 98 | 96 | d75 = 0.5mm |
| 4 | 4.76 | 91 | 95 | 93 | d50 = 0.3mm |
| 8 | 2.38 | 89 | 93 | 91 | |
| 16 | 1.19 | 87 | 91 | 89 | |
| 30 | 0.59 | 71 | 87 | 79 | |
| 50 | 0.297 | 43 | 65 | 54 | |
| 100 | 0.149 | 23 | 37 | 30 | |
| 200 | 0.074 | 17.8 | 27.7 | 23 | |







FIGURE A-1 LOCATIONS OF SOIL SAMPLES WITHIN DESIGNATED COVER SOIL BORROW AREA

Inter·Mountain Laboratories, Inc.

2506 W. Main Street
Farmington, New Mexico 87401

**Client:** Rio Grande Resources Corp.
**Project:** Mt. Taylor Mine
**Sample ID:** Composite
**Lab ID:** 0398S05459
**Matrix:**
**Condition:**

**Date Received:** 09/16/98
**Date Reported:** 09/17/98
**Date Sampled:** NG

| Parameter | Analytical Result | Units | Units |
|---|---|---|---|
| PH | 9.2 | s.u. | |
| Solids - Total Dissolved | 170 | mg/L | |
| Nitrogen - Nitrate | 0.17 | mg/L | |
| Sulfate | 11 | mg/L | |
| Arsenic | 0.013 | mg/L | |
| Cadmium | <0.004 | mg/L | |
| Chromium | <0.01 | mg/L | |
| Iron | 0.92 | mg/L | |
| Lead | <0.05 | mg/L | |
| Molybdenum | 0.02 | mg/L | |
| Selenium | 0.034 | mg/L | |
| Zinc | 0.10 | mg/L | |

Reference: EPA - "Methods for Chemical Analysis of Water and Wastes (MCAWW)" - EPA/600/4-79-020 - March, 1983.

Reviewed By: 

Inter-Mountain Laboratories, Inc.

2506 W. Main Street
Farmington, New Mexico 87401

**Client:** Rio Grande Resources Corp.
**Project:** Mt. Taylor Mine
**Sample ID:** WP #3 NW
**Lab ID:** 0398S04751
**Matrix:** Soil
**Condition:** Cool/Intact

**Date Received:** 08/20/98
**Date Reported:** 09/17/98
**Date Sampled:** 08/19/98
**Time Sampled:** 1000

| Parameter | Analytical Result | Units | Units |
|---|---|---|---|
| Sulfur forms - Total | 0.00 | % | |
| Acid Base-TS | 0.0 | t/kt | |
| Neutralization Potential (NP) | 10 | t/kt | |
| Acid Base Potential-TS | 10.2 | t/kt | |

Reference:

Reviewed By: 

Inter-Mountain Laboratories, Inc.


2506 W. Main Street
Farmington, New Mexico 87401

**Client:** Rio Grande Resources Corp.
**Project:** Mt. Taylor Mine
**Sample ID:** WP #1 SW
**Lab ID:** 0398S04749
**Matrix:** Soil
**Condition:** Cool/Intact

**Date Received:** 08/20/98
**Date Reported:** 09/17/98
**Date Sampled:** 08/19/98
**Time Sampled:** 0930

| Parameter | Analytical Result | Units | Units |
|---|---|---|---|
| Sulfur forms - Total | 0.01 | % | |
| Acid Base-TS | 0.31 | t/kt | |
| Neutralization Potential (NP) | 30 | t/kt | |
| Acid Base Potential-TS | 29.9 | t/kt | |

Reference:

Reviewed By: 

Inter-Mountain Laboratories, Inc.

2506 W. Main Street
Farmington, New Mexico 87401

**Client:** Rio Grande Resources Corp.
**Project:** Mt. Taylor Mine
**Sample ID:** WP #2 Center
**Lab ID:** 0398S04750
**Matrix:** Soil
**Condition:** Cool/Intact

**Date Received:** 08/20/98
**Date Reported:** 09/17/98
**Date Sampled:** 08/19/98
**Time Sampled:** 0945

| Parameter | Analytical Result | Units | Units |
|---|---|---|---|
| Sulfur forms - Total | 0.03 | % | |
| Acid Base-TS | 0.94 | t/kt | |
| Neutralization Potential (NP) | 24 | t/kt | |
| Acid Base Potential-TS | 23.1 | t/kt | |

Reference:

Reviewed By: _____

# APPENDIX E

## Cost Estimate

## To be supplied 60 days after CCP is approved

# APPENDIX F

## Revegetation Plan and Monitoring Protocols

# Mt. Taylor Mine

## REVEGETATION PLAN AND MONITORING PROTOCOLS

October 2025

Prepared by:

CEDAR CREEK ASSOCIATES, INC.

# Table of Contents


1.0 INTRODUCTION ..... 1
2.0 REVEGETATION PROTOCOLS ..... 2
2.1 Grading ..... 2
2.2 Growth Media Considerations ..... 2
2.2.1 Growth Media for Waste Rock Pile and Disposal Cell Cover ..... 3
2.2.1.1 Biointrusion ..... 3
2.2.2 Growth Media for Contaminated Soil Clean-up Areas ..... 4
2.3 Seedbed Preparation ..... 4
2.4 Seeding ..... 6
2.5 Erosion Control ..... 8
2.6 Climate Change Considerations ..... 8
3.0 VEGETATION SAMPLING METHODS ..... 9
3.1 Sample Site Selection / Location ..... 9
3.2 Determination of Ground Cover ..... 9
3.3 Determination of Woody Plant Density ..... 10
3.4 Determination of Productivity ..... 10
3.5 Determination of Emergent Density ..... 10
4.0 REVEGETATION MONITORING SCHEDULE AND SUCCESS EVALUATIONS ..... 12
4.1 Monitoring Schedule ..... 12
4.2 Success Criteria ..... 12
4.3 Sample Adequacy Determination ..... 13
5.0 MANAGEMENT ACTIONS / CONTINGENCY ..... 15
5.1 Inter-seeding ..... 15
5.2 Weed Control ..... 15
5.2.1 Chemical Control ..... 15
5.2.2 Mechanical Control ..... 16
5.3 Mulching ..... 16
5.4 Supplemental Irrigation ..... 16
6.0 REFERENCES ..... 18

## 1.0 INTRODUCTION

This plan, part of the Closeout/ Closure Plan (CCP) for the Mt. Taylor Mine, describes the measures that Rio Grande Resources (RGR) will take to re-establish vegetation on disturbed areas within the mine permit area that will minimize additional disturbance, mitigate impacts to affected environmental resources, rehabilitate disturbed areas to support post-mining land use (PMLU) of grazing, and provide protection of soil and runoff comparable to the natural conditions in the local area. The requirements of this Plan will be implemented primarily by a contractor at the time of mine closeout. The mine surface facilities are located on 285.6 acres, of which approximately 148 acres are currently disturbed land, and the remaining 137.9 acres are undisturbed. Closeout activities are anticipated to disturb an additional 27 acres, bringing the total land disturbance to 175 acres. Affected areas, to be identified before RGR commences final reclamation, will also be revegetated according to this plan. The affected areas known at this time to be revegetated include Borrow Area B and the areas of the Treated Water Discharge Pipeline outside of the Right-of-Way.

The areas to be revegetated include:

- Support (Service and Support) Facilities – 32 acres
- Mine Water Treatment Area - 28 acres
- Treated Water Discharge Pipeline beyond the mine surface area - 15 acres
- Ore Stockpile Pad and Runoff Retention Pond – 11.8 acres
- Expanded Disposal Cell - 13 acres
- Affected Areas
    - Borrow Area B (and access road) – 6.7 acres
    - Continental Divide Substation Area (depending on the Utility's wishes)
    - County Road 334 - 4.7 acres (non-driving surfaces of the Access Road)
    - Area of the Treated Water Discharge Pipeline outside of the Right-of-Way

The remainder of the disturbed area not to be revegetated includes the Continental Divide Substation, PMLU buildings, road surfaces, the south storm water pond, diversion channels, and rock slopes.

## 2.0 REVEGETATION PROTOCOLS

Revegetation protocols and performance criteria for Part 5 and Part 6 guidelines from the New Mexico Mining and Minerals Division. The particular guidance relevant to the project are the Self-Sustaining Ecosystem Guideline (December 2022), the Soil and Cover Material Handling and Suitability Guideline, and Revegetation Guideline (December 2022). This revegetation plan includes reasonable considerations growth media, seeding conditions, and site conditions including climate and post-mining use.

### 2.1 Grading

To prepare the mine site ground surfaces for revegetation, mine facilities not preserved for PMLU will be removed (CCP Technical Specification C.2) and the disturbed areas within the mine permit area will be regraded (CCP Section 4.4.7, Finish Grading and CCP Technical Specification C.4), including backfill of mine water treatment pond basins to approximate original grades.

Regraded material will be placed to minimize potential adverse effects to surface water, ground water and natural conditions of areas outside of the mine area. All surfaces will be graded to a final surface configuration which will support the approved post-mining land use, which will be grazing, or where appropriate, commercial. Temporary runoff and erosion controls, specified in the Stormwater Pollution Prevention Plan (SWPPP) will be employed to manage sediment generated during closeout earthwork. Grading operations will be performed by dozers, scrapers, graders or other equipment. An excavator with hydraulic hammer may be used to reduce high walls to 1H:1V slope, where appropriate. Finish grading will create the grades and slope directions shown on the CCP Appendix A drawings sheets CL 07A, CL 07B, CL 14, and CL 15, which may include shallow depressions and will have a roughened surface suitable for seed nesting and resistance to erosion.

### 2.2 Growth Media Considerations

At the Mt. Taylor Mine, the soil profile is typically 0-36 inches of silty sand over layers of interbedded inorganic clays of medium plasticity and sand-clay mixtures. The topsoil, referred to here as growth media, consists of fine grained sand, sand-clay mixtures, and medium plasticity clay. The agronomic descriptions of these soils are given in the CCP Section 4.4. The soil that is intended to be used for the growth media that will cover the radon barrier of the waste pile and disposal cell is classified as silty sand (SM), sand-clay mixtures (SC), and low to medium plasticity clay (CL) per the Unified Soil Classification System (USCS) and as sandy loam and clay loam per the USDA classification system (HEAL, 2014). It occurs as a residual soil derived from weathering of Mesa Verde sedimentary rock or colluvial/ alluvial soil from erosion of up-slope rock outcrops, including basalt. Based on Table 1 of the Closeout Plan

Guidelines for Existing Mines (MARB 1996) that are part of the State of New Mexico Energy, Minerals and Natural Resources Department (EMNRD) of Mining Act Reclamation Program (MARP) Attachment #1, Soil and Topsoil Suitability Ratings, this soil is rated as good to fair for texture.

During mine construction, site soils were excavated to create pond basins and other surficial features on the site. Most of the excavated soil was used to construct pond berms and to adjust grades for mine surface facilities. Local soils will be used for the growth media and will be obtained primarily from existing borrow areas, by excavations on site or borrow areas adjacent to the mine site, and regrading of pond berms or other grading performed during ground preparation. Table 4.3 (CCP) lists the available soil volumes versus borrow soil required for closeout; ample soil is available from these various sources, all within the mine permit boundaries.

### 2.2.1 Growth Media for Waste Rock Pile and Disposal Cell Cover

According to the latest design, a 33-inch layer of growth media (comprised of a piedmont soil) will be placed on top of the radon barrier, then a 12-inch rock mulch layer for erosion protection will be placed on the top surface of the cell cover. The rock mulch will be approximately 30% 2-inch minus and 70% pediment soils by volume. During placement, only light compaction of the piedmont soil will occur as a result of equipment movement used to place, spread, and grade the loam soil. Soil textures for the growth medium will follow the USDA classification system.

Growth media will be placed on the disposal cell by truck and spread primarily by dozer or motor-grader. The appropriate soil thickness will be achieved by GPS-guided equipment following the soil cover grading plan. The thickness of the placed loam cover is verified by sampling of soil depth using hand-augured holes through the completed growth medium. Thickness verification measurements will be made at least every ¼ acre. RGR will utilize an independent QA/QC contractor to obtain these measurements and validate the growth media layer thicknesses. For each location, the measurements will be documented and reviewed to ensure that the minimum thickness of growth media is attained. Where growth media layer thicknesses are insufficient, additional material will be placed to correct the deficiencies.

#### *2.2.1.1 Biointrusion*

Biointrusion can occur from plants, mammals, and insects. In general, upland plants in the region, even potentially deep-rooted shrubs, have the majority of their roots in the top 25 cm of the soil profile because the plants are primarily relying on precipitation to maintain. At the Homestake – Grant Reclamation Project, Cedar Creek observed a saltbush taproot growing laterally at approximately 20 cm depth. This is evidence that the plant rooting will develop where plant available water is. In the context

of the cover, the plant roots would not be expected to penetrate the radon barrier because plant available water would not be found in the radon barrier. If precipitation were to percolate deep into the soil profile, it would be expected to rest on top of the radon barrier. Due to the compaction, the plants would respond by forming fine dense roots in the vicinity to use the available water. Therefore, plant biointrusion is generally not a concern on the cover.

In general, it is likely that small mammals will inhabit the cover over time. High concentration of burrows and tunnels affect soil morphology and are likely to increase percolation rates. However, the majority of species with the potential to inhabit the area have shallow burrowing depths that leave them unlikely to interact with the radon barrier. Prairie dogs and badgers pose the highest risk to the cover as they may burrow deep enough to affect the radon barrier and form many wide burrows.

There are many species of insects that may be present on the cover. In general, the species of flies, wasps, crickets, and beetles, that have subterranean habits are unlikely to burrow more than a maximum of 12 inches into the ground and generally only burrow down to 6 inches. However, ants and termites, which can burrow upwards of 6 and 30 feet underground, respectively, are possible risks to the cover.

Overall, the cover design of using a rock mulch layer, with 30% 2-inch minus rock by volume, on the top surface generally discourages burrowing from insects and small mammals but the care and maintenance plan for the cover should include observations of small mammal burrows and insect mounds to ensure the effectiveness of the cover.

### 2.2.2 Growth Media for Contaminated Soil Clean-up Areas

When the excavation of contaminated soil has been finished, RGR will determine whether at least six inches of clean soil remains in place in areas to be revegetated. An agronomic assessment will be implemented to determine whether the remaining soils exhibit suitable physical, chemical, and fertility parameters to establish and sustain plant growth. Organic amendments or supplemental growth media may be used to address agronomic deficiencies.

## 2.3 Seedbed Preparation

Native arid vegetation is ecologically adapted to low fertility systems. Therefore, using standard agronomic fertility ranges designed for intensively managed, often heavily irrigated, and annually harvested agricultural systems is misrepresentative of the requirements for arid grassland and shrub systems in New Mexico.

When soil materials are disturbed (plowed, harvested, tilled), organic matter and associated fertility can be released (volatilized) by a subsequent increase in microbial activity. Incorporation of compost to

improve germination conditions for the revegetation surface is recommended. Soil organic matter serves as a reservoir of nutrients for vegetation, provides soil aggregation (providing structure), increases nutrient exchange, retains moisture, reduces compaction, reduces surface crusting, and increases water infiltration into soil. Organic matter increases the water holding capacity as it alters particle aggregation and pore size distribution. Water holding capacity of soil materials is an important consideration for land reclamation. Suitable soil water content is essential for seed germination, seedling establishment, and plant survival as desiccation is a major risk on disturbed sites, especially in arid environments.

Compost is a mixture of organic residues (manure or biosolids or green waste, straw, etc.) that have been piled, mixed and moistened to undergo thermophilic decomposition. Enough compost amendment should be incorporated into the project soils to add 1% organic matter to the top 3 inches of soil. Therefore, a general application rate of 8 cubic yards per acre incorporated to 3 inches depth of composted cow or green manure, or composted biosolids, should be sufficient for reclamation on the tailings site. Suitable material will have at least 25% organic matter, pH not to exceed 8.5, soluble salts less than 10 mmhos/cm, and carbon to nitrogen ratio between 10:1 and 20:1. Moisture content, salinity, and organic matter, of organic amendments need to be tested for by a certified laboratory. All testing should be conducted on representative samples of material from the same batch intended to be purchased. Given the potential for elevated salts in the soils, only low salt amendments should be used. Composted biosolids will be tested to ensure sufficiently low radium activity concentrations prior to use. In specific instances, such as harvesting growth media from very deep in the soil profile or using material stockpiled for more than a year, increased quantities of manure may be beneficial, and will be addressed on an "as needed" basis.

Composted manures and composted biosolids are more desirable than inorganic fertilizers and industrial byproducts such as Biosol, because they are significantly lower in inorganic and total nitrogen. Nitrogen preferentially stimulates the growth of undesirable weedy annual species, which reduces available water and nutrients for desirable perennial vegetation. In addition to the low nitrogen levels, the physical structure of the compost increases localized water holding capacity and creates "islands" of fertility to aid germination. Plant germination and establishment in the first few years is critical, as native seed sources then begin to supplement the initial seeding and stabilize the soil medium. Organic amendment application should occur immediately prior to seeding, and be incorporated as soon as

possible, preferably by disk harrow. Composted manure and/or biosolids left on the soil surface, exposed to warm temperatures and potential precipitation, will readily decompose, thus making it less beneficial.

## 2.4 Seeding

The proposed seed mix is comprised of all native species and application rates are presented on the table below and is optimized for site edaphic and climatic conditions. Each included species was evaluated for the following factors:

- Species Range
- Adapted to Project Soils
- Performance on Local Revegetation
- Species Dominance in Local Ecological Communities
- Precipitation Zones

These factors were also considered when recommending application rate, which was determined by seeds per square foot. Seeding can be accomplished using either broadcasting and drilling techniques (as recommended on the seed mix), following final contouring and compost application/incorporation. Seeding season shall be March 1 to April 30 or October 1 to November 30. In certain circumstances, seeding prior to the monsoonal period (in June or July) may be appropriate as well. Efforts will be made to implement seeding at optimal times for site conditions (late fall/early spring). However, if a unit must be seeded during inopportune months, a field level risk assessment will determine whether temporary erosion control measures (such as crimped hay, wood shreds, wattles, etc.) are needed to stabilize the surface prior to anticipated vegetation establishment. Drill seeding techniques cannot be used on extremely rough surfaces and in areas with slopes of 3H:1V or steeper (natural or cut slopes east of the shafts). In these situations, seed will be broadcast, and a light disc harrowing perpendicular to the flow of energy (wind and/or water) should immediately follow seeding to increase seed to soil contact and provide some protection from wind or water erosion and granivory. Hydroseeding may also be used in a

two-pass system, where the first pass is dedicated to sowing most of the seed and the second pass installs the mulch. The disposal cell will be seeded with this mix.

| Mt. Taylor Seed Mix | | | | | | |
|---|---|---|---|---|---|---|
| | | | Specifications / Recommendations | | | |
| Lifeform | Common Name | Scientific Nomenclature | PLS / lb.** | Recommd. PLS lbs/ac | PLS / $ft^2$ | % of Seeds in Mix |
| Grasses | Sideoats Grama | *Bouteloua curtipendula* | 191,000 | 1.00 | 4.4 | 5.0% |
| | Blue Grama | *Bouteloua gracilis* | 825,000 | 1.00 | 18.9 | 21.6% |
| | Bottlebrush Squirreltail | *Elymus elymoides* | 192,000 | 0.50 | 2.2 | 2.5% |
| | Slender Wheatgrass | *Elymus trachycaulum* | 159,000 | 2.00 | 7.3 | 8.3% |
| | Indian Ricegrass | *Eriocoma hymenoides* | 141,000 | 1.00 | 3.2 | 3.7% |
| | Galleta | *Hiliaria jamesii* | 159,000 | 0.50 | 1.8 | 2.1% |
| | Alkali Sacaton | *Sporobolus airoides* | 1,758,000 | 0.25 | 10.1 | 11.5% |
| | Sand Dropseed | *Sporobolus cryptandrus* | 5,298,000 | 0.10 | 12.2 | 13.9% |
| | | **Grass Subtotal** | | **6.35** | **60.1** | **68.7%** |
| Forbs | Lewis Flax | *Linum lewisii* | 293,000 | 1.00 | 6.7 | 7.7% |
| | Rocky Mtn. Penstemon | *Penstemon strictus* | 592,000 | 0.25 | 3.4 | 3.9% |
| | Upright Prairie Coneflower | *Ratibida columnifera* | 737,104 | 0.25 | 4.2 | 4.8% |
| | Scarlet Globemallow | *Sphaeralcea coccinea* | 500,000 | 0.25 | 2.9 | 3.3% |
| | | **Forb Subtotal** | | **1.75** | **17.2** | **19.7%** |
| Shrubs | Fourwing Saltbush | *Atriplex canescens* | 52,000 | 2.50 | 3.0 | 3.4% |
| | Winterfat | *Ceratoides lanata* | 56,700 | 2.00 | 2.6 | 3.0% |
| | Rubber Rabbitbrush | *Chrysothamnus naseousus* | 400,000 | 0.50 | 4.6 | 5.2% |
| | | **Shrub Subtotal** | | **5.00** | **10.2** | **11.6%** |
| | | **Total** | | **13.10** | **87.5** | |
| Suitable Alternatives | Purple Three-awn | *Aristida purpurea* | 250,000 | | | |
| | Spike Muhly | *Muhlenbergia wrightii* | 1,600,000 | | | |
| | Western Wheatgrass | *Pascopyrum smithii* | 110,000 | | | |
| | Purple Prarie Clover | *Dalea purpurea var. purpurea* | 300,000 | | | |
| | Firecracker Penstemon | *Penstemon eatonii* | 900,000 | | | |
| | Sand Sagebrush | *Artemisia filifolia* | 2,000,000 | | | |
| | Apache Plume | *Fallugia paradoxa* | 480,000 | | | |

## 2.5 Erosion Control

The principle means to obtain erosional stability on the disposal cell is rock armor. Vegetation establishment and persistence will serve as the primary erosion control measure for other revegetation. A field level risk assessment will determine whether temporary erosion control measures (such as certified weed-free crimped hay, wood shreds, wattles, etc.) are needed to stabilize the surface prior to anticipated vegetation establishment.

## 2.6 Climate Change Considerations

Climate change modeling results provide general indications of how the climate may shift in New Mexico over the next several decades and into the next century, albeit with a significant degree of uncertainty, spatially, temporally, and degree of magnitude. In general, modeling results from the Nature Conservancy and the Southwest Climate Change Network indicate a general warming and drying trend (with localized instances of cooling and increases in precipitation), with increased variation in timing, intensity, and form of precipitation from typical averages. The species selected for revegetation are well suited to the current arid climate of this region, yet have a relatively wide tolerance to climatic conditions, particularly regarding the predicted result of climate change (warmer and drier). In other words, if precipitation decreases, drought increases, or temperatures and subsequent evaporation rates rise, these species will still be suitable for and tolerant of future climates projected in the region. The anticipated circumstances of climate change may actually select for more efficient, later seral species (as is a desired outcome for the project), over short-lived annuals and less efficient cool season grasses.

## 3.0 VEGETATION SAMPLING METHODS

Revegetation monitoring will consist of both qualitative and quantitative protocols. Qualitative protocols record any deficiencies in vegetation, both general and localized, and any other pertinent information relative to the reclamation is also recorded while traversing monitoring units during vegetation evaluations. During these traverses, the observer is vigilant for: 1) areas of poor establishment/growth, 2) pervasively weak or stressed plants, 3) indicators of soil fertility problems (e.g., certain anthocyanine colorations), 4) noxious weeds or invasive plant infestation, 5) evidence of unintended livestock grazing, 6) excessive erosion, 7) "pockets" of the aforementioned, and 8) any other similar revegetation / reclamation related issues. Quantitative protocols are described in the following sections.

Reference areas should be used as a benchmark for revegetation success. Appropriate reference areas will be selected in coordination with the New Mexico Mining and Minerals Division (MMD) prior to implementing revegetation monitoring and should provide a suitable target for revegetation performance by representing project topographic and edaphic conditions.

### 3.1 Sample Site Selection / Location

The systematic procedure for the determination of sample locations occurs in the following stepwise manner. First, a fixed point of reference is selected for the entire area to facilitate location of the systematic grid in the field. Second, a systematic grid of appropriate dimensions (i.e., 200 ft X 200 ft) is selected to provide a minimum number of coordinate intersections; reclaimed areas are conducted to a minimum of 20 transects whereas reference area sampling is conducted to a minimum of 15 initial transects. Third, a scaled representation of the grid is overlain on field maps extending parallel to major compass points to facilitate field location. Fourth, unbiased placement of this grid is controlled by selection of a random origin. Fifth, utilizing a GPS, all of the initial sample points are located in the field.

### 3.2 Determination of Ground Cover

Ground cover at each sampling site is determined utilizing the point-intercept method (Bonham 1989) as illustrated on Figure 1. Implementation of the technique for the sampling effort occurs as follows: First, a transect of 10 meters length is extended from the starting point of each sample site toward the direction of the next site to be sampled. Then, at each one-meter interval along the transect, a "laser point bar" is situated vertically above the ground surface, and a set of 10 readings recorded as to foliar hits on vegetation (by species), litter, standing dead, rock (>2mm), or bare soil. Hits are determined at each meter interval by activating a battery of 10 specialized lasers situated along the bar at 10-centimeter intervals and recording the variable intercepted by each of the narrow (0.02 inch)

focused beams (see Figure 1). In this manner, a total of 100 intercepts per transect are recorded resulting in 1 percent foliar cover per intercept.

### 3.3 Determination of Woody Plant Density

At each sample site, a 2-meter-wide by 50-meter-long belt transect is established parallel to the ground cover transect and in the direction of the next sampling point (in a cardinal compass direction – Figure 1). Occasionally 4 x 25 meter transects are employed where distance between points necessitates shorter belts. Then within each belt, all woody plants (shrubs, trees, and succulents) are enumerated by species and age class. Determination of whether or not a plant could be counted depends on the location of its main stem or root collar where it exited the ground surface with regard to belt limits.

### 3.4 Determination of Productivity

At each sample site, current annual production is collected from a 1/2 $m^2$ quadrat frame at each sampling location. Utilization and development will be estimated using on the ground observations of herbivory within each of these quadrat frames. The quadrat is placed one meter and 90º to the right (clockwise) of the ground cover transect to avoid vegetation trampled by investigators during sample site location. From within each quadrat, all above ground current annual vegetation within the vertical boundaries of the frame is clipped and bagged separately by life form as follows:

| | |
|---|---|
| Native Perennial Cool Season Grass | Shrub |
| Native Perennial Warm Season Grass | Sub-Shrub |
| Introduced Perennial Grass | Native Perennial Forb |
| Annual Grass | Introduced Perennial Forb |
| Noxious Weed | Native/Introduced Annual/Biennial Forb |

All production samples are returned to the lab for drying and weighing. Drying will occur at 105º C until a stable weight is achieved (typically 24 hours). Samples will then be weighed to the nearest 0.1 gram. Utilization and growth stage adjustments will be incorporated into the presentation of results.

### 3.5 Determination of Emergent Density

In the first growing season following seeding, between 5-15 samples are collected from each reclaimed unit. Each sample consists of a cluster of five 1.0 $ft^2$ quadrats distributed in an unbiased manner. Following a random toss of each quadrat, the number of emergent plants rooted within the frame's perimeter is recorded accordingly into one of five classes: perennial grass, perennial forb, shrub/tree (by species), annual grass, or annual forb.





***Figure 1***

***Sampling Procedure at a Systematic Sample Site Location***

**Figure 1: Sampling Procedure**

## 4.0 REVEGETATION MONITORING SCHEDULE AND SUCCESS EVALUATIONS

### 4.1 Monitoring Schedule

The revegetation liability period (period of time that the owner is responsible for revegetation performance) under the MMD framework is 12 years with monitoring every three years. The annual site visits for the revegetation will be as follows:

Year 1 – Emergent Density Evaluation
Year 3 – Qualitative and quantitative evaluations (managerial information only).
Year 6 – Qualitative and quantitative evaluations (managerial information only).
Year 9 – Qualitative and quantitative evaluations (managerial information only).
---
Year 11 – Qualitative and quantitative evaluations (final success evaluation).
Year 12 – Qualitative and quantitative evaluations (final success evaluation).

As indicated, the final efforts, during year 11 and 12, would be an evaluation for success determination. Years 11 and 12 evaluations will be conducted in such a manner as to provide defensible verification that success has been achieved. If it is determined that vegetation needs additional time to mature, monitoring will continue once every 3 years, thereafter, until success evaluations are positive. Other than first year efforts, annual monitoring would be a combination of both qualitative and quantitative efforts to facilitate tracking and progress toward revegetation success standards.

### 4.2 Success Criteria

The primary post mining land use is anticipated to be grazing, therefore, revegetation success in revegetated units will concentrate on four performance standards (1) vegetative ground cover, and 2) diversity, 3) woody plant density, and 4) productivity. Revegetation efforts will be considered successful when the following criteria have been met. The reference areas will be sampled along with the revegetation to provide a suitable comparison each year of assessment. In this manner, the success criteria is dynamic and adjusts to climatic conditions.

1. Vegetative Ground Cover Standard

   The target revegetated unit equals or exceeds 70% of an appropriate reference area absolute desirable vegetative ground cover (exclusive of listed noxious species), with 90 percent statistical confidence. Desirable vegetation excludes noxious and nuisance (non-

native annual weeds) but includes other annuals and perennials which are native and non-native.

2. Species Diversity Standard:

   Ground cover shall be comprised of a minimum of three perennial grass species, one perennial forb species, and one shrub species to address species diversity.

3. Woody Plant Density Standard:

   Woody Plant Density, as indicated by number of stems per acre in the revegetated unit equals or exceeds 200 stems per acre.

4. Productivity Standard:

   The target revegetated unit equals or exceeds 70% of an appropriate reference area absolute desirable vegetative productivity (exclusive of listed noxious species and succulents). Desirable vegetation excludes noxious and nuisance (non-native annual weeds) but includes other annuals and perennials which are native and non-native.

## 4.3 Sample Adequacy Determination

Ground cover sampling within reclaimed areas is conducted to a minimum of 20 initial transects whereas reference area sampling is conducted to a minimum of 15 initial transects. From these preliminary efforts, sample means and standard deviations for total non-overlapping vegetation ground cover are calculated. The procedure is such that sampling continues until an adequate sample, $\mathbf{n_{min}}$, has been collected in accordance with the Cochran formula (below) for determining sample adequacy, whereby the population is estimated to be within 10% of the true mean (μ) with 90% confidence. These limits facilitate a very strong estimate of the target population (MMD 1996).

When the inequality ($\mathbf{n_{min}} \leq \mathbf{n}$) is true, sampling is adequate and $\mathbf{n_{min}}$ is determined as follows:

$$\mathbf{n_{min} = (t^2 s^2) / (0.1\ \bar{x}\ )^2}$$

where: n = the number of actual samples collected

$t$ = the value from the one-tailed $t$ distribution for 90% confidence with n-1 degrees of freedom

$s^2$ = the variance of the estimate as calculated from the initial samples

$\bar{x}$ = the mean of the estimate as calculated from the initial samples

If sampling is designed for a formal success evaluation and the initial samples do not provide a suitable estimate of the mean (i.e., had the inequality been false), additional samples will be collected until the inequality ($\mathbf{n_{min}} \leq \mathbf{n}$) becomes true or until a maximum of 40 samples are collected. If sample adequacy is not achieved after 40 samples are collected, a reverse null approach will be used to demonstrate success. The demonstration of success will utilize the central limit theorem which assumes approximate normality when a sufficiently large number of samples are collected (greater than 30). A one-sided, one-sample, reverse–null t-test is considered appropriate. Since sampling adequacy is not required (nor recommended) for woody plant density, one density belt will be co-located with each ground cover transect, but adequacy shall not be tested for this variable. Resulting data can then be considered reasonable for the evaluation purposes intended.

## 5.0 MANAGEMENT ACTIONS / CONTINGENCY

After the initial seeding occurs and monitoring has begun, circumstances may require additional management actions to facilitate revegetation parcels toward the desired outcomes. The management actions presented below may not represent an exhaustive list of potential options, as additional management alternatives may be needed to address site-specific issues that arise.

### 5.1 Inter-seeding

If undesirable precipitation, wind events, or any other factors contribute to poor seed germination, additional seed may be broadcast or drilled (if topography allows) to increase vegetative cover or diversity, as required.

### 5.2 Weed Control

Weed management may be implemented if noxious weeds identified during annual vegetation surveys present an obstacle to achieving performance criteria for the cover. Noxious weed control is species-dependent and both method and timing will vary from species to species. Should the need arise, noxious weed patches will be identified and delineated with a GPS during the annual vegetation survey. Data regarding the species and density of the population will be recorded, and then an informal control plan will be formulated and implemented. The effectiveness of control methods will be documented during the following annual vegetation survey.

Prevention is the highest priority weed management practice on non-infested lands; therefore, protecting weed-free plant communities is the most economical and efficient land management practice. Prevention is best accomplished by ensuring that new weed species seed or vegetative reproductive plant parts of weeds are not introduced into new areas and early detection of any new weed species before they begin to spread. Control methods may include chemical or mechanical approaches. The optimum method for weed management varies depending on a number of site-specific variables such as associated vegetation, weed type, stage of growth, and severity of the weed infestation.

#### 5.2.1 Chemical Control

Chemical control consists of selective and non-selective herbicides. Target noxious weed, herbicide selection, proximity to desirable plant species, and timing are considerations for chemical control. The use of herbicides would be in compliance with all Federal and State laws on proper use, storage, and

disposal. The chemical application would be done by a licensed contractor in accordance with all applicable laws and regulations and all label instructions will be strictly followed.

### 5.2.2 Mechanical Control

Mechanical control is the physical removal of weeds and includes tilling, mowing, and pulling undesirable plant species. Treatment options and efficacy depend on the noxious weed targeted and method used.

## 5.3 Mulching

If revegetation parcels are eroding at an unforeseen rate while vegetation is still being established, mulch may be used to provide rainsplash and wind protection, reduce evaporation, and stabilize the seedbed. Preferably, a wood fiber or wood shred mulch would be used, as it is more robust than hay or straw and more likely to provide wind protection.

If used, wood fiber mulch or wood shred mulch would consist of specially prepared wood fibers and would not be produced from recycled material such as sawdust, paper, cardboard, or residue from pulp and paper plants. If necessary, such as on a steep slope or an area deemed a high wind erosion risk area, a tackifier can be used with the wood-fiber mulch to improve adhesion. If erosion areas are localized, small, or well sheltered, a simple straw mulch should suffice in providing rainsplash protection. Interseeding would most likely be necessary if erosion is sufficient enough to require post-revegetation corrective mulching.

## 5.4 Supplemental Irrigation

The seed mix proposed for this project is comprised of species adapted to the local climactic conditions and supplemental irrigation is not likely required to establish vegetation. Irrigation typically causes an artificial climactic regime that overly encourages annual weeds versus the desired seeded species. Also, under the influence of irrigation, the adapted plants that do germinate will develop above ground biomass at the expense of below ground biomass. Once the irrigation stops, those plants have essentially become "accustomed" to artificial circumstances and will typically die during a normally tolerated drought. Over approximately the last 20 years, practical applications of arid land reclamation science have abandoned the use of irrigation.

However, a prolonged drought during the plant establishment period could become detrimental to the project. In this specific circumstance, supplemental irrigation may be used to facilitate germination, but procedures for implementing irrigation need to be highly managed and not exceed 120% of any

monthly precipitation average. Soil moisture sensors and unsaturated flow modeling should accompany the planning and implementation of irrigation events to facilitate vegetation establishment and growth, while maintaining the primary function of isolating the buried materials from the water balance. Per the New Mexico Mining and Minerals Division comments on the CCP (May 10, 2023), irrigation of revegetated areas will only be permitted for the first three years after seeding.

To encourage and sustain perennial growth, particularly of warm season grasses and shrubs, and discourage annual weedy species, irrigation needs to occur as infrequent pulses of relatively substantial quantities of water, in an attempt to mimic the natural monsoonal precipitation experienced in mid to late summer. These irrigation events, mimicking high intensity, short duration convective thunderstorms will increase the amount of plant available water, facilitating the robust and extensive root systems needed for survival of perennial vegetation beyond irrigation. In contrast, frequent and shallow irrigation events will benefit the shallow rooted annual species and facilitate perennial root growth near the surface, which during periods of drought will desiccate, and result in the senescence of all shallow rooted vegetation.

## 6.0 REFERENCES


Bonham, Charles D., 1989. *Measurements for Terrestrial Vegetation*. John Wiley & Sons. 338 pp.

Mining Act Reclamation Bureau (MARB). 1996. Closeout Plan Guidelines for Existing Mines. April 30.

New Mexico Mining and Minerals Division (MMD). 1996. Attachment 2 – Revegetation Standards and Sampling Methods. April 30, 1996.

MMD. 2010. Guidance Document for Part 5 New Mining Operation Permitting Under the New Mexico Mining Act. August 2010.

MMD. 2022a. Guidance for Revegetation of Part 5 Existing Mines and Part 6 New Mines. December 2022.


MMD. 2022b. Guidance for Soil and Cover Material Handling and Suitability for Part 5 Existing Mines. December 2022.

MMD. 2022c. Self-Sustaining Ecosystem Guidelines: In the Context of the New Mexico Mining Act Rules. December 2022.

# APPENDIX G


## Structural Design of Shaft Plugs

NOTE: MAN TUNNEL NOT SHOWN BUT SHALL BE SEALED TO PREVENT CLSM MIGRATION FROM SHAFT OR BACKFILLED PER KEY NOTE 8 TO EXISTING SHURE LOCK DOORS.




## SECTION A-A (PLAN VIEW AT SUBCOLLAR LEVEL)

SCALE: 1/8" = 1'-0"




## SECTION B-B (CROSS SECTION OF MANWAY/VENT SHAFT)

SCALE: 1/8" = 1'-0"

## KEYED NOTES

1. EXISITING REINFORCED CONCRETE SHAFT WALLS. PROTECT IN PLACE EXCEPT WHERE NOTED
2. EXISTING CONCRETE SHELF WALL TO ACT AS EDGE FORM. NEW SLAB CONCRETE TO EXTEND TO THIS POINT, BUT REINFORCEMENT NOT NECESSARY BEYOND LIMITS SHOWN.
3. W8X21 STEEL BEAMS SPACED 4'-0" OC SUPPORTING STEEL PLATING. BEAMS TO BE SUPPORTED AT ENDS WITH POST INSTALLED ANCHORS ATTACHED TO GUSSET PLATES
4. 3/4" STEEL PLATES TO SUPPORT CONCRETE SLAB. WELD PLATES TO STRINGERS AND AT UNSUPPORTED SEAMS. EDGES TO BE SUPPORTED BY MIN 12" OF EXISTING SHAFT COLLAR
5. BOTTOM MAT OF SLAB REINFORCEMENT. #8 @ 3" OC EACH WAY OVER CENTER 1/3 OF SLAB. #8 @ 6" OC EACH WAY OVER OUTER THIRDS. ALL BARS TO BE EPOXY COATED
6. TOP MAT OF SLAB REINFORCEMENT AT OUTER THIRD OF SLAB. #8 @ 2 DEGREES RADIALLY. #8 CIRCLES CONCENTRICALLY SPACED @ 8". ALL BARS TO BE EPOXY COATED
7. 4500 PSI HEAVY WEIGHT CONCRETE @ 24" DEPTH. TEST CONCRETE AT 7, 14, & 28 DAYS FOR STRENGTH. DO NOT BACKFILL UNTIL DESIGN STRENGTH IS ACHIEVED
8. CONTROLLED LOW STRENGTH MATERIAL (CLSM) SLURRY BACKFILL TO BE PLACED AFTER 28 DAY DESIGN STRENGTH IS ACHIEVED ON CONCRETE SLAB
9. LIGHTWEIGHT 2500 PSI CONCRETE SLAB AT MANWAY AND VENT SHAFT SURFACE ENTRANCES. 12" MIN DEPTH WITH #4 @ 12" OC EW.
10. PRECAST CONCRETE CAP WITH MARKER. 4' X 4' X 2' DEEP. INSCRIBED USING 4" LETTER EMBEDDED STATING: "MOUNT TAYLOR MINE MANWAY/VENT SHAFT, CLOSED [DATE]"
11. 10" SCH 40 STEEL PIPE TO SERVE AS SAMPLING WELL. WELD PIPE TO CIRCULAR HOLE CUT INTO STEEL PLATE. CAP TOP OF WELL WITH ROYER LOCKING WELL CAP OR EQUAL.

## MANWAY SHAFT MATERIAL QUANTITIES

| ITEM | QTY | UNIT |
|---|---|---|
| #8 EPOXY COATED REBAR-BOTTOM MAT | 2894 | FT |
| #8 EPOXY COATED REBAR-TOP MAT | 1715 | FT |
| 4500 PSI CONCRETE | 34 | CY |
| 3000 PSI LIGHTWEIGHT CONCRETE | 11 | CY |
| 3/4" STEEL PLATE | 204 | SF |
| W8X21 STEEL BEAMS | 38 | LF |
| CLSM SLURRY BACKFILL | 660 | CY |

## GENERAL NOTES:

1. THIS PLAN IS INTENDED TO REPLACE DRAWING NO MT13-CL-05 IN THE PREVIOUSLY APPROVED 'MOUNT TAYLOR MINE CLOSEOUT/CLOSURE PLAN' DEVELOPED BY ALAN KUHN ASSOCIATES LLC, DATED 12-17-13.
2. REMOVE AND DROP ALL EQUIPMENT, FITTINGS, AND UTILITIES BETWEEN COLLAR AND SUB COLLAR LEVEL PRIOR TO CONSTRUCTION
3. ALL SLURRY BACKFILL TO INCLUDE SOIL, PORTLAND CEMENT, AND FLY ASH. MINIMUM COMPRESSIVE STRENGTH OF 75 PSI
4. ALL REINFORCING STEEL TO BE GRADE 60, EPOXY COATED REBAR
5. ALL WELDS TO BE 1/4" , 2" LONG, SPACED 6" APART
6. ARRANGEMENT OF STEEL SUPPORT MAY BE ROTATED AS NECESSARY
7. STEEL PLATES MAY BE SQUARED OFF PROVIDED A MINIMUM SUPPORT OF 12" OVER COLLAR
8. ALL EDGES AND JOINTS OF STEEL SUPPORT STRUCTURE TO BE SEALED TO ENSURE UNCURED CONCRETE CANNOT LEAK
9. PLACEMENT OF CONCRETE TO ADHERE TO ACI CODES, VIBRATED IN PLACE TO ENSURE NO VOIDS ARE PRESENT
10. REBAR LAYOUT AND STEEL BEAM CONNECTION DETAILS TO BE PROVIDED WITH ISSUE FOR CONSTRUCTION (IFC) PLAN REVISIONS

| REV: | DESCRIPTION: | BY: | DATE: |
|---|---|---|---|
| 0 | FOR CLOSURE PLAN | JJL | 4/6/22 |

STATUS: NOT FOR CONSTRUCTION


CRITICAL VIEW ENGINEERING
PO BOX 90073
ALBUQUERQUE, NM 87199
(505) 321-5917


CLIENT: RIO GRANDE RESOURCES INC
GRANTS, NM 87020


ARCHITECT:

PROJECT: RIO GRANDE RESOURCES INC MOUNT TAYLOR MINE

TITLE: RC SLAB SHAFT CLOSURE MANWAY/VENT


| SCALE AT A3: | DATE: | DRAWN: | CHECKED: |
|---|---|---|---|
| NTS | 4/6/22 | JJL | JJL |

| PROJECT NO: | DRAWING NO: | REVISION: |
|---|---|---|
| 22-003 | C/100 | 0 |




## SECTION A–A (PLAN VIEW AT SUBCOLLAR LEVEL)

SCALE: $\frac{3}{32}$" = 1'–0"




## SECTION B–B (CROSS SECTION OF PRODUCTION SHAFT)

SCALE: $\frac{1}{16}$" = 1'–0"

## KEYED NOTES

1. EXISITING REINFORCED CONCRETE SHAFT WALLS. PROTECT IN PLACE EXCEPT WHERE NOTED
2. EXISTING 24' DIA STEEL VENTILATION TUNNEL. FILL WITH CLSM PER KEY NOTE 8. CAP WITH LIGHTWEIGHT CONCRETE SLAB AND PRECAST MARKER PER KEY NOTES 9 & 10.
3. W18X40 STEEL BEAMS SPACED 3'–0" OC SUPPORTING STEEL PLATING. BEAMS TO BE SUPPORTED AT ENDS WITH POST INSTALLED ANCHORS ATTACHED TO GUSSET PLATES
4. 1" STEEL PLATES TO SUPPORT CONCRETE SLAB. WELD PLATES TO STRINGERS AND AT UNSUPPORTED SEAMS. EDGES TO BE SUPPORTED BY MIN 12" OF EXISTING SHAFT COLLAR
5. DOUBLE BOTTOM MAT OF SLAB REINFORCEMENT. #9 @ 4" OC EACH WAY MIDDLE $\frac{1}{3}$ OF SLAB. #9 @ 8" OC EACH WAY AT OUTER THIRDS. ALL BARS TO BE EPOXY COATED
6. TOP MAT OF SLAB REINFORCEMENT AT OUTER THIRD OF SLAB. #9 @ 1.5 DEGREES RADIALLY. #9 CIRCLES CONCENTRICALLY SPACED @ 10". ALL BARS TO BE EPOXY COATED
7. 4500 PSI HEAVY WEIGHT CONCRETE @ 45" DEPTH. TEST CONCRETE AT 7, 14, & 28 DAYS FOR STRENGTH. DO NOT BACKFILL UNTIL DESIGN STRENGTH IS ACHIEVED
8. CONTROLLED LOW STRENGTH MATERIAL (CLSM) SLURRY BACKFILL TO BE PLACED AFTER 28 DAY DESIGN STRENGTH IS ACHIEVED ON CONCRETE SLAB
9. LIGHTWEIGHT 2500 PSI CONCRETE SLAB AT PRODUCTION AND VENT SHAFT SURFACE ENTRANCES. 12" MIN DEPTH WITH #4 @ 12" OC EW.
10. PRECAST CONCRETE CAP WITH MARKER. 4' X 4' X 2' DEEP. INSCRIBED USING 4" LETTER EMBEDDED STATING: "MOUNT TAYLOR MINE PRODUCTION/VENT SHAFT, CLOSED [DATE]"
11. 10" SCH 40 STEEL PIPE TO SERVE AS SAMPLING WELL. WELD PIPE TO CIRCULAR HOLE CUT INTO STEEL PLATE. CAP TOP OF WELL WITH ROYER LOCKING WELL CAP OR EQUAL.

### PRODUCTION SHAFT MATERIAL QUANTITIES

| ITEM | QTY | UNIT |
|---|---|---|
| #9 EPOXY COATED REBAR–BOTTOM MATS | 7144 | FT |
| #9 EPOXY COATED REBAR–TOP MAT | 2713 | FT |
| 4500 PSI CONCRETE | 110 | CY |
| 3000 PSI LIGHTWEIGHT CONCRETE | 29 | CY |
| 1" STEEL PLATE | 531 | SF |
| W18X40 STEEL BEAMS | 146 | LF |
| CLSM SLURRY BACKFILL | 3666 | CY |

### GENERAL NOTES:

1. THIS PLAN IS INTENDED TO REPLACE DRAWING NO MT13–CL–06 IN THE PREVIOUSLY APPROVED 'MOUNT TAYLOR MINE CLOSEOUT/CLOSURE PLAN' DEVELOPED BY ALAN KUHN ASSOCIATES LLC, DATED 12–17–13.
2. REMOVE AND DROP ALL EQUIPMENT, FITTINGS, AND UTILITIES BETWEEN COLLAR AND SUB COLLAR LEVEL PRIOR TO CONSTRUCTION
3. ALL SLURRY BACKFILL TO INCLUDE SOIL, PORTLAND CEMENT, AND FLY ASH. MINIMUM COMPRESSIVE STRENGTH OF 75 PSI
4. ALL REINFORCING STEEL TO BE GRADE 60, EPOXY COATED REBAR
5. ALL WELDS TO BE $\frac{1}{4}$" , 2" LONG, SPACED 6" APART
6. ARRANGEMENT OF STEEL SUPPORT MAY BE ROTATED AS NECESSARY
7. STEEL PLATES MAY BE SQUARED OFF PROVIDED A MINIMUM SUPPORT OF 12" OVER COLLAR
8. ALL EDGES AND JOINTS OF STEEL SUPPORT STRUCTURE TO BE SEALED TO ENSURE UNCURED CONCRETE CANNOT LEAK
9. PLACEMENT OF CONCRETE TO ADHERE TO ACI CODES, VIBRATED IN PLACE TO ENSURE NO VOIDS ARE PRESENT
10. REBAR LAYOUT AND STEEL BEAM CONNECTION DETAILS TO BE PROVIDED WITH ISSUE FOR CONSTRUCTION (IFC) PLAN REVISIONS

| REV: | DESCRIPTION: | BY: | DATE: |
|---|---|---|---|
| 0 | FOR CLOSURE PLAN | JJL | 4/6/22 |

STATUS: NOT FOR CONSTRUCTION

CRITICAL VIEW ENGINEERING
PO BOX 90073
ALBUQUERQUE, NM 87199
(505) 321–5917

CLIENT: RIO GRANDE RESOURCES INC
GRANTS, NM 87020

ARCHITECT:

PROJECT: RIO GRANDE RESOURCES INC MOUNT TAYLOR MINE

TITLE: RC SLAB SHAFT CLOSURE PRODUCTION/VENT SHAFT

| SCALE AT A3: | DATE: | DRAWN: | CHECKED: |
|---|---|---|---|
| NTS | 4/6/22 | JJL | JJL |

| PROJECT NO: | DRAWING NO: | REVISION: |
|---|---|---|
| 22–003 | C/200 | 0 |

# APPENDIX H

## Post-Closure Monitoring Plan

# APPENDIX I

## Water Sampling and Laboratory Test Data

Water Quality Results for the October 2023 Dewatering Well Sampling Investigation

- Tabulated Water Quality Data
- October 2023 Water Quality Sampling Data for Dewatering Wells

June 4, 2025 Project No. 111360

Mr. Corey Dimond
New Mexico Environment Department
Ground Water Quality Bureau
Mining Environmental Compliance Section
1190 St. Francis Dr.
Sante Fe, NM 87502

RE: Rio Grande Resources' Submittal of Pre Rehabilitation October 2023 Dewatering Well Sampling Data from April 28, 2023 Dewatering Well DW-10 and DW-11 Investigation Work Plan prepared by Gard Water


Dear Mr. Dimond,

Included in this document are the water quality results for the October 2023 ewatering well sampling investigation that is the first phase (pre well rehabilitation) of the sampling requested in the February 23, 2023 NMED Request for Additional Information on the 15-day Suspected Petroleum Release Report for Dewatering Wells Dw-10 and DW-11, Mt Taylor Mine, San Mateo, New Mexico and outlined in the April 28, 2023 Dewatering Well DW-10 and DW-11 Investigation Work Plan prepared by Gard Water.


Below is a list of tables and attachments included in this letter.

- Tabulated Water Quality Data
  - Tables 1 through 11 contain water quality data for DW-1, DW-2A, DW-2, DW-3, DW-6, DW-7, DW-8, DW-9, DW-10, DW-11, and DW-12 respectively.
- Attachment A October 2023 Water Quality Sampling Data for Dewatering Wells Includes the following reports
  - October 4, 2023 L1662801 Pace Analytical Report on DW-1 and DW-7
  - October 7, 2023 L1664135 Pace Analytical Report on DW-10 and DW-12
  - October 7, 2023 L1664199 Pace Analytical Report on DW-2 and DW-9
  - October 13, 2023 L1666511 Pace Analytical Report on DW-3 and DW-11
  - October 13, 2023 L1666516 Pace Analytical Report on DW3, DW-2a, and DW-6
  - October 13, 2023 L1666531 Pace Analytical Report on DW-8 and DW-10

Respectfully Submitted,
**Engineering Analytics, Inc.**



Melissa Meyer, P.E.
Project Manager



Eric Roads EIT
Staff Engineer II

CC
Abimbola Ojekanmi, Uranium Coordinator, Mining and Minerals Division
Clinton Chisler, Uranium Reclamation Coordinator, Mining and Minerals Division
Kevin Raabe, President RSO, Rio Grande Resources Corporation
Anita Willcox, Facilities Supervisor, Rio Grande Resources Corporation

# TABLES

# TABLE 1
# DW-1
# GROUNDWATER QUALITY SUMMARY

| October 2023 Dewatering Wells Water Quality Data Summary | | Well ID | DW1 | DW1 | DW1 | DW1 |
|---|---|---|---|---|---|---|
| | | Depth (fbtoc) | 785 | 785 | 785 | 785 |
| | | Sample Type | Sample | Field Duplicate | Rinseate Blank | Trip Blank |
| | | Date Collected | 10/03/2023 | 10/03/2023 | 10/03/2023 | 10/03/2023 |
| Analyte | NM WQCC-3103 | Units | | | | |
| ACENAPHTHENE | | mg/l | <0.0000500[2] | <0.0000500 | <0.0000500 | <0.0000500 |
| ACENAPHTHYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)PYRENE | 0.0002 | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(B)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(K)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(G,H,I)PERYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 2-CHLORONAPHTHALENE | | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| CHRYSENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| DIBENZ(A,H)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| FLUORANTHENE | | mg/l | <0.000100 | <0.000100 | <0.000100 | <0.000100 |
| FLUORENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| INDENO(1,2,3-CD)PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 1-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| 2-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| NAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| PHENANTHRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| | | | | | | |
| BENZENE | 0.005 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| ETHYLBENZENE | 0.7 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| TOLUENE | 1 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| XYLENES, TOTAL | 0.62 | mg/l | <0.00300 | <0.00300 | <0.00300 | <0.00300 |
| | | | | | | |
| TPH | | mg/l | <0.100 | <0.100 | <0.100 | <0.100 |
| C10-C28 DIESEL RANGE | | mg/l | <0.100 | <0.100 | <0.100 | <0.100 |
| C28-C40 OIL RANGE | | mg/l | <0.100 | <0.100 | <0.100 | <0.100 |

Acronyms: Reporting Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH), Point Discharge (PD)

Dark grey shading in cells idicates a concentration was measured above RDL

Yellow shading in cells indicates a concentration was measured above NMWQCC-3102 Standards

Blue indicates a concentration was measured above RDL in a blank sample

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample was collected from spigot near well head

3:The targeted sample depth was unable to be met due to unforeseen obstruction. The depths listed for the sample ID for the blanks is the targeted sample depth and the depth listed for the representative sample is the deapth reached in the field.

# TABLE 3
# DW-2
# GROUNDWATER QUALITY SUMMARY

| October 2023 Dewatering Wells Water Quality Data Summary | | Well ID | DW2[3] | DW2[3] | DW2[3] |
|---|---|---|---|---|---|
| | | Depth (fbtoc) | 2480 | 2480 | 2480 |
| | | Sample Type | Sample | Field Blank | Rinseate Blank |
| | | Date Collected | 10/05/2023 | 10/05/2023 | 10/05/2023 |
| Analyte | NM WQCC-3103 | Units | | | |
| ACENAPHTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| ACENAPHTHYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)PYRENE | 0.0002 | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(B)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(K)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(G,H,I)PERYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| 2-CHLORONAPHTHALENE | | mg/l | <0.000250 | <0.000250 | <0.000250 |
| CHRYSENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| DIBENZ(A,H)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| FLUORANTHENE | | mg/l | <0.000100 | <0.000100 | <0.000100 |
| FLUORENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| INDENO(1,2,3-CD)PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| 1-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 |
| 2-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 |
| NAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 |
| PHENANTHRENE | | mg/l | 0.0000639 | <0.0000500 | <0.0000500 |
| PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| | | | | | |
| BENZENE | 0.005 | mg/l | <0.00100 | <0.00100 | <0.00100 |
| ETHYLBENZENE | 0.7 | mg/l | <0.00100 | <0.00100 | <0.00100 |
| TOLUENE | 1 | mg/l | <0.00100 | <0.00100 | <0.00100 |
| XYLENES, TOTAL | 0.62 | mg/l | <0.00300 | <0.00300 | <0.00300 |
| | | | | | |
| TPH | | mg/l | <0.100 | <0.100 | <0.100 |
| C10-C28 DIESEL RANGE | | mg/l | 0.463 | <0.100 | <0.100 |
| C28-C40 OIL RANGE | | mg/l | 0.359 | <0.100 | <0.100 |

Acronyms: Reporting Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH), Point Discharge (PD)

Dark grey shading in cells idicates a concentration was measured above RDL

Yellow shading in cells indicates a concentration was measured above NMWQCC-3102 Standards

Blue indicates a concentration was measured above RDL in a blank sample

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample was collected from spigot near well head

3:The targeted sample depth was unable to be met due to unforeseen obstruction. The depths listed for the sample ID le is the deapth reached in the field where the targeted depth was 2770 feet.

# TABLE 2
# DW-2A
# GROUNDWATER QUALITY SUMMARY

| October 2023 Dewatering Wells Water Quality Data Summary | | Well ID | DW2A[2] |
|---|---|---|---|
| | | Depth (fbtoc) | Spigot |
| | | Date Collected | 10/11/2023 |
| Analyte | NM WQCC-3103 | Units | |
| ACENAPHTHENE | | mg/l | <0.0000500 |
| ACENAPHTHYLENE | | mg/l | <0.0000500 |
| ANTHRACENE | | mg/l | <0.0000500 |
| BENZO(A)ANTHRACENE | | mg/l | <0.0000500 |
| BENZO(A)PYRENE | 0.0002 | mg/l | <0.0000500 |
| BENZO(B)FLUORANTHENE | | mg/l | <0.0000500 |
| BENZO(K)FLUORANTHENE | | mg/l | <0.0000500 |
| BENZO(G,H,I)PERYLENE | | mg/l | <0.0000500 |
| 2-CHLORONAPHTHALENE | | mg/l | <0.000250 |
| CHRYSENE | | mg/l | <0.0000500 |
| DIBENZ(A,H)ANTHRACENE | | mg/l | <0.0000500 |
| FLUORANTHENE | | mg/l | <0.000100 |
| FLUORENE | | mg/l | <0.0000500 |
| INDENO(1,2,3-CD)PYRENE | | mg/l | <0.0000500 |
| 1-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 |
| 2-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 |
| NAPHTHALENE | 0.03 | mg/l | <0.000250 |
| PHENANTHRENE | | mg/l | <0.0000500 |
| PYRENE | | mg/l | <0.0000500 |
| | | | |
| BENZENE | 0.005 | mg/l | <0.00100 |
| ETHYLBENZENE | 0.7 | mg/l | <0.00100 |
| TOLUENE | 1 | mg/l | <0.00100 |
| XYLENES, TOTAL | 0.62 | mg/l | <0.00300 |
| | | | |
| TPH | | mg/l | <0.100 |
| C10-C28 DIESEL RANGE | | mg/l | <0.100 |
| C28-C40 OIL RANGE | | mg/l | <0.100 |

Acronyms: Reporting Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH), Point Discharge (PD)

Dark grey shading in cells idicates a concentration was measured above RDL

Yellow shading in cells indicates a concentration was measured above NMWQCC-3102 Standards

Blue indicates a concentration was measured above RDL in a blank sample

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample was collected from spigot near well head

3:The targeted sample depth was unable to be met due to unforeseen obstruction. The depths listed for the sample ID for the blanks is the targeted sample depth and the depth listed for the representative sample is the deapth reached in the field.

# TABLE 4
# DW-3
# GROUNDWATER QUALITY SUMMARY

| October 2023 Dewatering Wells Water Quality Data Summary | | Well ID | DW3 | DW3 | DW3 | DW3 | DW3 | DW3 | DW3 | DW3 |
|---|---|---|---|---|---|---|---|---|---|---|
| | | Depth (fbtoc) | 596 | 596 | 896 | 896 | 1005 | 1005 | 1005 | 1005 |
| | | Sample Type | Sample | Rinseate Blank | Sample | Rinseate Blank | Sample | Field Duplicate | Field Blank | Rinseate Blank |
| | | Date Collected | 10/11/2023 | 10/11/2023 | 10/11/2023 | 10/11/2023 | 10/11/2023 | 10/11/2023 | 10/11/2023 | 10/11/2023 |
| Analyte | NM WQCC-3103 | Units | | | | | | | | |
| ACENAPHTHENE | | mg/l | 0.000477 | <0.0000500 | <0.0000500 | <0.0000500 | 0.000104 | 0.000111 | <0.0000500 | <0.0000500 |
| ACENAPHTHYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)PYRENE | 0.0002 | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(B)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(K)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(G,H,I)PERYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 2-CHLORONAPHTHALENE | | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| CHRYSENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| DIBENZ(A,H)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| FLUORANTHENE | | mg/l | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 |
| FLUORENE | | mg/l | 0.00161 | <0.0000500 | 0.0000566 | <0.0000500 | 0.000183 | 0.00018 | <0.0000500 | <0.0000500 |
| INDENO(1,2,3-CD)PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 1-METHYLNAPHTHALENE | 0.03 | mg/l | 0.0105 | <0.000250 | <0.000250 | <0.000250 | 0.000599 | 0.00058 | <0.000250 | <0.000250 |
| 2-METHYLNAPHTHALENE | 0.03 | mg/l | 0.0118 | <0.000250 | <0.000250 | <0.000250 | 0.000701 | 0.00068 | <0.000250 | <0.000250 |
| NAPHTHALENE | 0.03 | mg/l | 0.00134 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| PHENANTHRENE | | mg/l | 0.00181 | <0.0000500 | 0.0000815 | <0.0000500 | 0.000245 | 0.000252 | <0.0000500 | <0.0000500 |
| PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| | | | | | | | | | | |
| BENZENE | 0.005 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| ETHYLBENZENE | 0.7 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| TOLUENE | 1 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| XYLENES, TOTAL | 0.62 | mg/l | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 |
| | | | | | | | | | | |
| TPH | | mg/l | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 |
| C10-C28 DIESEL RANGE | | mg/l | 1.37 | <0.100 | 0.62 | <0.100 | 2.3 | 1.7 | <0.100 | <0.100 |
| C28-C40 OIL RANGE | | mg/l | 0.147 | <0.100 | 0.158 | <0.100 | 0.347 | 0.156 | <0.100 | <0.100 |

Acronyms: Reporting Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH), Point Discharge (PD)

Dark grey shading in cells idicates a concentration was measured above RDL

Yellow shading in cells indicates a concentration was measured above NMWQCC-3102 Standards

Blue indicates a concentration was measured above RDL in a blank sample

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample was collected from spigot near well head

3:The targeted sample depth was unable to be met due to unforeseen obstruction. The depths listed for the sample ID for the blanks is the targeted sample depth and the depth listed for the representative sample is the deapth reached in the field.

# TABLE 5
# DW-6
# GROUNDWATER QUALITY SUMMARY

| October 2023 Dewatering Wells Water Quality Data Summary | | Well ID | DW6[3] |
|---|---|---|---|
| | | Depth (fbtoc) | Spigot |
| | | Date Collected | 10/10/2023 |
| Analyte | NM WQCC-3103 | Units | |
| ACENAPHTHENE | | mg/l | <0.0000500 |
| ACENAPHTHYLENE | | mg/l | <0.0000500 |
| ANTHRACENE | | mg/l | <0.0000500 |
| BENZO(A)ANTHRACENE | | mg/l | <0.0000500 |
| BENZO(A)PYRENE | 0.0002 | mg/l | <0.0000500 |
| BENZO(B)FLUORANTHENE | | mg/l | <0.0000500 |
| BENZO(K)FLUORANTHENE | | mg/l | <0.0000500 |
| BENZO(G,H,I)PERYLENE | | mg/l | <0.0000500 |
| 2-CHLORONAPHTHALENE | | mg/l | <0.000250 |
| CHRYSENE | | mg/l | <0.0000500 |
| DIBENZ(A,H)ANTHRACENE | | mg/l | <0.0000500 |
| FLUORANTHENE | | mg/l | <0.000100 |
| FLUORENE | | mg/l | <0.0000500 |
| INDENO(1,2,3-CD)PYRENE | | mg/l | <0.0000500 |
| 1-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 |
| 2-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 |
| NAPHTHALENE | 0.03 | mg/l | <0.000250 |
| PHENANTHRENE | | mg/l | <0.0000500 |
| PYRENE | | mg/l | <0.0000500 |
| | | | |
| BENZENE | 0.005 | mg/l | <0.00100 |
| ETHYLBENZENE | 0.7 | mg/l | <0.00100 |
| TOLUENE | 1 | mg/l | <0.00100 |
| XYLENES, TOTAL | 0.62 | mg/l | <0.00300 |
| | | | |
| TPH | | mg/l | <0.100 |
| C10-C28 DIESEL RANGE | | mg/l | 0.115 |
| C28-C40 OIL RANGE | | mg/l | 0.366 |

Acronyms: Reporting Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH), Point Discharge (PD)

Dark grey shading in cells idicates a concentration was measured above RDL

Yellow shading in cells indicates a concentration was measured above NMWQCC-3102 Standards

Blue indicates a concentration was measured above RDL in a blank sample

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample was collected from spigot near well head

3:The targeted sample depth was unable to be met due to unforeseen obstruction. The depths listed for the sample ID for the blanks is the targeted sample depth and the depth listed for the representative sample is the deapth reached in the field.

# TABLE 6
# DW-7
# GROUNDWATER QUALITY SUMMARY

| October 2023 Dewatering Wells Water Quality Data Summary | | | Well ID | DW7 | DW7 | DW7 |
|---|---|---|---|---|---|---|
| | | | Depth (fbtoc) | 900 | 900 | 900 |
| | | | Sample Type | Sample | Field Blank | Rinseate Blank |
| | | | Date Collected | 10/02/2023 | 10/02/2023 | 10/02/2023 |
| Analyte | NM WQCC-3103 | Units | | | | |
| ACENAPHTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| ACENAPHTHYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)PYRENE | 0.0002 | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(B)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(K)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(G,H,I)PERYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| 2-CHLORONAPHTHALENE | | mg/l | <0.000250 | <0.000250 | <0.000250 |
| CHRYSENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| DIBENZ(A,H)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| FLUORANTHENE | | mg/l | <0.000100 | <0.000100 | <0.000100 |
| FLUORENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| INDENO(1,2,3-CD)PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| 1-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 |
| 2-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 |
| NAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 |
| PHENANTHRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 |
| | | | | | |
| BENZENE | 0.005 | mg/l | <0.00100 | <0.00100 | <0.00100 |
| ETHYLBENZENE | 0.7 | mg/l | <0.00100 | <0.00100 | <0.00100 |
| TOLUENE | 1 | mg/l | <0.00100 | <0.00100 | <0.00100 |
| XYLENES, TOTAL | 0.62 | mg/l | <0.00300 | <0.00300 | <0.00300 |
| | | | | | |
| TPH | | mg/l | <0.100 | <0.100 | <0.100 |
| C10-C28 DIESEL RANGE | | mg/l | 0.166 | <0.100 | <0.100 |
| C28-C40 OIL RANGE | | mg/l | <0.100 | <0.100 | <0.100 |

Acronyms: Reporting Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH), Point Discharge (PD)

Dark grey shading in cells idicates a concentration was measured above RDL

Yellow shading in cells indicates a concentration was measured above NMWQCC-3102 Standards

Blue indicates a concentration was measured above RDL in a blank sample

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample was collected from spigot near well head

3:The targeted sample depth was unable to be met due to unforeseen obstruction. The depths listed for the sample ID for the blanks is the targeted sample depth and the depth listed for the representative sample is the deapth reached in the field.

# TABLE 7
# DW-8
# GROUNDWATER QUALITY SUMMARY

| October 2023 Dewatering Wells Water Quality Data Summary | | | | | | | |
|---|---|---|---|---|---|---|---|
| | | Well ID | DW8 | DW8 | DW8 | DW8 | DW8 |
| | | Depth (fbtoc) | 840 | 840 | 961 | 961 | 961 |
| | | Sample Type | Sample | Rinseate Blank | Sample | Field Duplicate | Rinseate Blank |
| | | Date Collected | 10/09/2023 | 10/09/2023 | 10/09/2023 | 10/09/2023 | 10/09/2023 |
| Analyte | NM WQCC-3103 | Units | | | | | |
| ACENAPHTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| ACENAPHTHYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)PYRENE | 0.0002 | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(B)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(K)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(G,H,I)PERYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 2-CHLORONAPHTHALENE | | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| CHRYSENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| DIBENZ(A,H)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| FLUORANTHENE | | mg/l | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 |
| FLUORENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| INDENO(1,2,3-CD)PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 1-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| 2-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| NAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| PHENANTHRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| | | | | | | | |
| BENZENE | 0.005 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| ETHYLBENZENE | 0.7 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| TOLUENE | 1 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| XYLENES, TOTAL | 0.62 | mg/l | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 |
| | | | | | | | |
| TPH | | mg/l | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 |
| C10-C28 DIESEL RANGE | | mg/l | <0.100 | <0.100 | 0.122 | 0.13 | <0.100 |
| C28-C40 OIL RANGE | | mg/l | <0.100 | <0.100 | 0.146 | 0.138 | <0.100 |

Acronyms: Reporting Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH), Point Discharge (PD)

Dark grey shading in cells idicates a concentration was measured above RDL

Yellow shading in cells indicates a concentration was measured above NMWQCC-3102 Standards

Blue indicates a concentration was measured above RDL in a blank sample

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample was collected from spigot near well head

3:The targeted sample depth was unable to be met due to unforeseen obstruction. The depths listed for the sample ID for the blanks is the targeted sample depth and the depth listed for the representative sample is the deapth reached in the field.

# TABLE 8
# DW-9
# GROUNDWATER QUALITY SUMMARY

| October 2023 Dewatering Wells Water Quality Data Summary | Well ID | | DW9 | DW9 | DW9 | DW9 | DW9 | DW9 | DW9 |
|---|---|---|---|---|---|---|---|---|---|
| | Depth (fbtoc) | | 1144 | 1144 | 1655 | 1655 | 2760 | 2760 | 2760 |
| | Sample Type | | Sample | Rinseate Blank | Sample | Rinseate Blank | Sample | Field Blank | Rinseate Blank |
| | Date Collected | | 10/04/2023 | 10/04/2023 | 10/04/2023 | 10/04/2023 | 10/04/2023 | 10/04/2023 | 10/04/2023 |
| Analyte | NM WQCC-3103 | Units | | | | | | | |
| ACENAPHTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| ACENAPHTHYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)PYRENE | 0.0002 | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(B)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(K)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(G,H,I)PERYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 2-CHLORONAPHTHALENE | | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| CHRYSENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| DIBENZ(A,H)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| FLUORANTHENE | | mg/l | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 |
| FLUORENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| INDENO(1,2,3-CD)PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 1-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| 2-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| NAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| PHENANTHRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| | | | | | | | | | |
| BENZENE | 0.005 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| ETHYLBENZENE | 0.7 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| TOLUENE | 1 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| XYLENES, TOTAL | 0.62 | mg/l | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 |
| | | | | | | | | | |
| TPH | | mg/l | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 |
| C10-C28 DIESEL RANGE | | mg/l | 0.193 | <0.100 | <0.100 | <0.100 | 0.422 | <0.300 | <0.100 |
| C28-C40 OIL RANGE | | mg/l | 0.126 | <0.100 | <0.100 | <0.100 | 1.68 | <0.300 | <0.100 |

Acronyms: Reporting Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH), Point Discharge (PD)

Dark grey shading in cells idicates a concentration was measured above RDL

Yellow shading in cells indicates a concentration was measured above NMWQCC-3102 Standards

Blue indicates a concentration was measured above RDL in a blank sample

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample was collected from spigot near well head

3:The targeted sample depth was unable to be met due to unforeseen obstruction. The depths listed for the sample ID for the blanks is the targeted sample depth and the depth listed for the representative sample is the deapth reached in the field.

# TABLE 9
# DW-10
# GROUNDWATER QUALITY SUMMARY

| October 2023 Dewatering Wells Water Quality Data Summary | Well ID | | DW10 | DW10 | DW10 | DW10 | DW10 | DW10 | DW10 | DW10 |
|---|---|---|---|---|---|---|---|---|---|---|
| | Depth (fbtoc) | | 463 | 463 | 781 | 781 | 781 | 865 | 865 | 865 |
| | Sample Type | | Sample | Rinseate Blank | Sample | Field Blank | Rinseate Blank | Sample | Field Blank | Rinseate Blank |
| | Date Collected | | 10/09/2023 | 10/09/2023 | 10/09/2023 | 10/09/2023 | 10/09/2023 | 10/06/2023 | 10/06/2023 | 10/06/2023 |
| Analyte | NM WQCC-3103 | Units | | | | | | | | |
| ACENAPHTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| ACENAPHTHYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)PYRENE | 0.0002 | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(B)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(K)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(G,H,I)PERYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 2-CHLORONAPHTHALENE | | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| CHRYSENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| DIBENZ(A,H)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| FLUORANTHENE | | mg/l | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 |
| FLUORENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| INDENO(1,2,3-CD)PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 1-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| 2-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| NAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| PHENANTHRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| | | | | | | | | | | |
| BENZENE | 0.005 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| ETHYLBENZENE | 0.7 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| TOLUENE | 1 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| XYLENES, TOTAL | 0.62 | mg/l | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 |
| | | | | | | | | | | |
| TPH | | mg/l | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 |
| C10-C28 DIESEL RANGE | | mg/l | 0.518 | <0.100 | 0.112 | <0.100 | <0.100 | 0.395 | <0.100 | <0.100 |
| C28-C40 OIL RANGE | | mg/l | 0.871 | <0.100 | 0.236 | <0.100 | <0.100 | 0.74 | <0.100 | <0.100 |

Acronyms: Reporting Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH), Point Discharge (PD)

Dark grey shading in cells idicates a concentration was measured above RDL

Yellow shading in cells indicates a concentration was measured above NMWQCC-3102 Standards

Blue indicates a concentration was measured above RDL in a blank sample

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample was collected from spigot near well head

3:The targeted sample depth was unable to be met due to unforeseen obstruction. The depths listed for the sample ID for the blanks is the targeted sample depth and the depth listed for the representative sample is the deapth reached in the field.

# TABLE 10
# DW-11
# GROUNDWATER QUALITY SUMMARY

| October 2023 Dewatering Wells Water Quality Data Summary | | | Well ID | DW11 | DW11 | DW11 | DW11 | DW11[3] | DW11[3] | DW11[3] |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | Depth (fbtoc) | 904 | 904 | 1100 | 1100 | 1750 | 1750 | 1750 |
| | | | Sample Type | Sample | Rinseate Blank | Sample | Rinseate Blank | Sample | Field Blank | Rinseate Blank |
| | | | Date Collected | 10/10/2023 | 10/10/2023 | 10/10/2023 | 10/10/2023 | 10/10/2023 | 10/10/2023 | 10/10/2023 |
| Analyte | NM WQCC-3103 | Units | | | | | | | | |
| ACENAPHTHENE | | mg/l | 0.00775 | 0.000118 | 0.00915 | 0.00008 | 0.0105 | <0.0000500 | <0.0000500 |
| ACENAPHTHYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)PYRENE | 0.0002 | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(B)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(K)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(G,H,I)PERYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 2-CHLORONAPHTHALENE | | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| CHRYSENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| DIBENZ(A,H)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| FLUORANTHENE | | mg/l | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 | <0.000100 |
| FLUORENE | | mg/l | 0.00204 | <0.0000500 | 0.00226 | <0.0000500 | 0.00238 | <0.0000500 | <0.0000500 |
| INDENO(1,2,3-CD)PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 1-METHYLNAPHTHALENE | 0.03 | mg/l | <0.0125 | <0.000250 | <0.0125 | <0.000250 | <0.0125 | <0.000250 | <0.000250 |
| 2-METHYLNAPHTHALENE | 0.03 | mg/l | <0.0125 | <0.000250 | 0.0136 | <0.000250 | 0.0155 | <0.000250 | <0.000250 |
| NAPHTHALENE | 0.03 | mg/l | 0.404 | 0.000424 | 0.485 | 0.000258 | 0.55 | <0.000250 | <0.000250 |
| PHENANTHRENE | | mg/l | 0.000577 | <0.0000500 | 0.000609 | <0.0000500 | 0.000536 | <0.0000500 | <0.0000500 |
| PYRENE | | mg/l | 0.0000516 | <0.0000500 | 0.00006 | <0.0000500 | 0.0000768 | <0.0000500 | <0.0000500 |
| | | | | | | | | | | |
| BENZENE | 0.005 | mg/l | <0.00100 | <0.00100 | 0.00143 | <0.00100 | 0.00137 | <0.00100 | <0.00100 |
| ETHYLBENZENE | 0.7 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| TOLUENE | 1 | mg/l | 0.00185 | <0.00100 | 0.0028 | <0.00100 | 0.00258 | <0.00100 | <0.00100 |
| XYLENES, TOTAL | 0.62 | mg/l | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 | <0.00300 |
| | | | | | | | | | | |
| TPH | | mg/l | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 | <0.100 |
| C10-C28 DIESEL RANGE | | mg/l | 12.5 | <0.100 | 13.1 | <0.100 | 13 | <0.100 | <0.100 |
| C28-C40 OIL RANGE | | mg/l | 9.5 | <0.100 | 8.62 | <0.100 | 7.42 | <0.100 | <0.100 |

Acronyms: Reporting Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH), Point Discharge (PD)

Dark grey shading in cells idicates a concentration was measured above RDL

Yellow shading in cells indicates a concentration was measured above NMWQCC-3102 Standards

Blue indicates a concentration was measured above RDL in a blank sample

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample was collected from spigot near well head

3:The targeted sample depth was unable to be met due to unforeseen obstruction. The depths listed is the deapth reached in the field, target depth was 2,848 feet.

# TABLE 11
# DW-12
# GROUNDWATER QUALITY SUMMARY

| October 2023 Dewatering Wells Water Quality Data Summary | | | | | | |
|---|---|---|---|---|---|---|
| | | Well ID | DW12 | DW12 | DW12 | DW12 |
| | | Depth (fbtoc) | 1764 | 1764 | 2865 | 2865 |
| | | Sample Type | Sample | Rinseate Blank | Sample | Rinseate Blank |
| | | Date Collected | 10/06/2023 | 10/06/2023 | 10/05/2023 | 10/05/2023 |
| Analyte | NM WQCC-3103 | Units | | | | |
| ACENAPHTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| ACENAPHTHYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(A)PYRENE | 0.0002 | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(B)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(K)FLUORANTHENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| BENZO(G,H,I)PERYLENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 2-CHLORONAPHTHALENE | | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| CHRYSENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| DIBENZ(A,H)ANTHRACENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| FLUORANTHENE | | mg/l | <0.000100 | <0.000100 | <0.000100 | <0.000100 |
| FLUORENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| INDENO(1,2,3-CD)PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| 1-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| 2-METHYLNAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| NAPHTHALENE | 0.03 | mg/l | <0.000250 | <0.000250 | <0.000250 | <0.000250 |
| PHENANTHRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| PYRENE | | mg/l | <0.0000500 | <0.0000500 | <0.0000500 | <0.0000500 |
| | | | | | | |
| BENZENE | 0.005 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| ETHYLBENZENE | 0.7 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| TOLUENE | 1 | mg/l | <0.00100 | <0.00100 | <0.00100 | <0.00100 |
| XYLENES, TOTAL | 0.62 | mg/l | <0.00300 | <0.00300 | <0.00300 | <0.00300 |
| | | | | | | |
| TPH | | mg/l | <0.100 | <0.100 | <0.100 | <0.100 |
| C10-C28 DIESEL RANGE | | mg/l | 0.246 | <0.100 | 0.156 | <0.100 |
| C28-C40 OIL RANGE | | mg/l | 0.126 | <0.100 | 0.116 | <0.100 |

Acronyms: Reporting Limit (RDL), Feet Below Top of Casing (fbtoc), Quality Control (QC) Total Petroleum Hydrocarbons (TPH), Point Discharge (PD)

Dark grey shading in cells idicates a concentration was measured above RDL

Yellow shading in cells indicates a concentration was measured above NMWQCC-3102 Standards

Blue indicates a concentration was measured above RDL in a blank sample

Footnotes:

1: The "less than" symbol "<" is a method to convey that the target analyte was not encountered above the RDL.

2: Sample was collected from spigot near well head

3:The targeted sample depth was unable to be met due to unforeseen obstruction. The depths listed for the sample ID for the blanks is the targeted sample depth and the depth listed for the representative sample is the deapth reached in the field.

# ATTACHMENT A
# OCTOBER 2023 WATER QUALITY SAMPLING DATA FOR DEWATERING WELLS

# ANALYTICAL REPORT

October 18, 2023



## Rio Grande Resources Corp


| | |
|---|---|
| Sample Delivery Group: | L1662801 |
| Samples Received: | 10/04/2023 |
| Project Number: | 111360 |
| Description: | Mt Taylor |

Report To: Eric Roads
219 S 2nd St
Raton, NM 87740

Entire Report Reviewed By:

John Hawkins
Project Manager

Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace Analytical National is performed per guidance provided in laboratory standard operating procedures ENV-SOP-MTJL-0067 and ENV-SOP-MTJL-0068. Where sampling conducted by the customer, results relate to the accuracy of the information provided, and as the samples are received.



Pace Analytical National
12065 Lebanon Rd Mount Juliet, TN 37122 615-758-5858 800-767-5859 www.pacenational.com

# TABLE OF CONTENTS


Cp: Cover Page 1

Tc: Table of Contents 2

Ss: Sample Summary 3

Cn: Case Narrative 5

Sr: Sample Results 6

MT-GW-TS-900-DW7-100323-K3 L1662801-01 6

MT-GW-TS-900-DW7-100323 L1662801-02 7

MT-GW-TS-900-DW7-100323-K2 L1662801-03 8

MT-GW-TS-785-DW1-100323-K3 L1662801-04 9

MT-GW-TS-785-DW1-100323-K4 L1662801-05 10

MT-GW-TS-785-DW1-100323 L1662801-06 11

MT-GW-TS-785-DW1-100323-K1 L1662801-07 12

Qc: Quality Control Summary 13

Volatile Organic Compounds (GC) by Method 8015D/GRO 13

Volatile Organic Compounds (GC/MS) by Method 8260B 15

Semi-Volatile Organic Compounds (GC) by Method 8015 17

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM 18

Gl: Glossary of Terms 22

Al: Accreditations & Locations 23

Sc: Sample Chain of Custody 24

## MT-GW-TS-900-DW7-100323-K3 L1662801-01 GW

Collected by: Tyler Davis | Collected date/time: 10/02/23 15:42 | Received date/time: 10/04/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2147534 | 1 | 10/09/23 23:28 | 10/09/23 23:28 | DYW | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2147038 | 1 | 10/07/23 14:03 | 10/07/23 14:03 | DYW | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2150669 | 1 | 10/14/23 19:59 | 10/16/23 21:44 | TJD | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147261 | 1 | 10/09/23 07:30 | 10/09/23 15:47 | DSH | Mt. Juliet, TN |

## MT-GW-TS-900-DW7-100323 L1662801-02 GW

Collected by: Tyler Davis | Collected date/time: 10/02/23 16:46 | Received date/time: 10/04/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2147534 | 1 | 10/09/23 23:50 | 10/09/23 23:50 | DYW | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2147038 | 1 | 10/07/23 14:24 | 10/07/23 14:24 | DYW | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2150669 | 1 | 10/14/23 19:59 | 10/16/23 22:03 | TJD | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147261 | 1 | 10/09/23 07:30 | 10/09/23 16:05 | DSH | Mt. Juliet, TN |

## MT-GW-TS-900-DW7-100323-K2 L1662801-03 GW

Collected by: Tyler Davis | Collected date/time: 10/02/23 17:42 | Received date/time: 10/04/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2147534 | 1 | 10/10/23 00:12 | 10/10/23 00:12 | DYW | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2147038 | 1 | 10/07/23 14:45 | 10/07/23 14:45 | DYW | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2150669 | 1 | 10/14/23 19:59 | 10/16/23 22:23 | TJD | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147261 | 1 | 10/09/23 07:30 | 10/09/23 16:22 | DSH | Mt. Juliet, TN |

## MT-GW-TS-785-DW1-100323-K3 L1662801-04 GW

Collected by: Tyler Davis | Collected date/time: 10/03/23 10:58 | Received date/time: 10/04/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2150834 | 1 | 10/13/23 17:12 | 10/13/23 17:12 | DWR | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2147038 | 1 | 10/07/23 15:06 | 10/07/23 15:06 | DYW | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2150669 | 1 | 10/14/23 19:59 | 10/16/23 22:43 | TJD | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147558 | 1 | 10/09/23 17:02 | 10/10/23 02:04 | DSH | Mt. Juliet, TN |

## MT-GW-TS-785-DW1-100323-K4 L1662801-05 GW

Collected by: Tyler Davis | Collected date/time: 10/03/23 11:09 | Received date/time: 10/04/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2150834 | 1 | 10/13/23 17:57 | 10/13/23 17:57 | DWR | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148770 | 1 | 10/10/23 23:18 | 10/10/23 23:18 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2150669 | 1 | 10/14/23 19:59 | 10/16/23 23:03 | TJD | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147558 | 1 | 10/09/23 17:02 | 10/10/23 02:24 | DSH | Mt. Juliet, TN |

## MT-GW-TS-785-DW1-100323 L1662801-06 GW

Collected by: Tyler Davis | Collected date/time: 10/03/23 12:43 | Received date/time: 10/04/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2150834 | 1 | 10/13/23 18:19 | 10/13/23 18:19 | DWR | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148770 | 1 | 10/10/23 23:41 | 10/10/23 23:41 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2150669 | 1 | 10/14/23 19:59 | 10/16/23 23:22 | TJD | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147558 | 1 | 10/09/23 17:02 | 10/10/23 02:44 | DSH | Mt. Juliet, TN |

# SAMPLE SUMMARY

## MT-GW-TS-785-DW1-100323-K1 L1662801-07 GW

Collected by: Tyler Davis
Collected date/time: 10/03/23 12:43
Received date/time: 10/04/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2150834 | 1 | 10/13/23 18:42 | 10/13/23 18:42 | DWR | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148770 | 1 | 10/11/23 00:03 | 10/11/23 00:03 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2150669 | 1 | 10/14/23 19:59 | 10/16/23 23:42 | TJD | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147558 | 1 | 10/09/23 17:02 | 10/10/23 03:03 | DSH | Mt. Juliet, TN |

# CASE NARRATIVE

All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.



John Hawkins
Project Manager

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/09/2023 23:28 | WG2147534 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *99.7* | | *78.0-120* | | *10/09/2023 23:28* | WG2147534 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/07/2023 14:03 | WG2147038 |
| Toluene | ND | | 0.00100 | 1 | 10/07/2023 14:03 | WG2147038 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/07/2023 14:03 | WG2147038 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/07/2023 14:03 | WG2147038 |
| *(S) Toluene-d8* | *97.1* | | *80.0-120* | | *10/07/2023 14:03* | WG2147038 |
| *(S) 4-Bromofluorobenzene* | *90.1* | | *77.0-126* | | *10/07/2023 14:03* | WG2147038 |
| *(S) 1,2-Dichloroethane-d4* | *109* | | *70.0-130* | | *10/07/2023 14:03* | WG2147038 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/16/2023 21:44 | WG2150669 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/16/2023 21:44 | WG2150669 |
| *(S) o-Terphenyl* | *81.5* | | *52.0-156* | | *10/16/2023 21:44* | WG2150669 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Chrysene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/09/2023 15:47 | WG2147261 |
| Fluorene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Naphthalene | ND | | 0.000250 | 1 | 10/09/2023 15:47 | WG2147261 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| Pyrene | ND | | 0.0000500 | 1 | 10/09/2023 15:47 | WG2147261 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/09/2023 15:47 | WG2147261 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/09/2023 15:47 | WG2147261 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/09/2023 15:47 | WG2147261 |
| *(S) Nitrobenzene-d5* | *109* | | *31.0-160* | | *10/09/2023 15:47* | WG2147261 |
| *(S) 2-Fluorobiphenyl* | *86.8* | | *48.0-148* | | *10/09/2023 15:47* | WG2147261 |
| *(S) p-Terphenyl-d14* | *87.4* | | *37.0-146* | | *10/09/2023 15:47* | WG2147261 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/09/2023 23:50 | WG2147534 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *106* | | *78.0-120* | | *10/09/2023 23:50* | WG2147534 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/07/2023 14:24 | WG2147038 |
| Toluene | ND | | 0.00100 | 1 | 10/07/2023 14:24 | WG2147038 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/07/2023 14:24 | WG2147038 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/07/2023 14:24 | WG2147038 |
| *(S) Toluene-d8* | *89.4* | | *80.0-120* | | *10/07/2023 14:24* | WG2147038 |
| *(S) 4-Bromofluorobenzene* | *93.8* | | *77.0-126* | | *10/07/2023 14:24* | WG2147038 |
| *(S) 1,2-Dichloroethane-d4* | *110* | | *70.0-130* | | *10/07/2023 14:24* | WG2147038 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.166 | | 0.100 | 1 | 10/16/2023 22:03 | WG2150669 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/16/2023 22:03 | WG2150669 |
| *(S) o-Terphenyl* | *81.0* | | *52.0-156* | | *10/16/2023 22:03* | WG2150669 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Chrysene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/09/2023 16:05 | WG2147261 |
| Fluorene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Naphthalene | ND | | 0.000250 | 1 | 10/09/2023 16:05 | WG2147261 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| Pyrene | ND | | 0.0000500 | 1 | 10/09/2023 16:05 | WG2147261 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/09/2023 16:05 | WG2147261 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/09/2023 16:05 | WG2147261 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/09/2023 16:05 | WG2147261 |
| *(S) Nitrobenzene-d5* | *87.9* | | *31.0-160* | | *10/09/2023 16:05* | WG2147261 |
| *(S) 2-Fluorobiphenyl* | *84.7* | | *48.0-148* | | *10/09/2023 16:05* | WG2147261 |
| *(S) p-Terphenyl-d14* | *84.2* | | *37.0-146* | | *10/09/2023 16:05* | WG2147261 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/10/2023 00:12 | WG2147534 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *106* | | *78.0-120* | | *10/10/2023 00:12* | WG2147534 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/07/2023 14:45 | WG2147038 |
| Toluene | ND | | 0.00100 | 1 | 10/07/2023 14:45 | WG2147038 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/07/2023 14:45 | WG2147038 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/07/2023 14:45 | WG2147038 |
| *(S) Toluene-d8* | *92.7* | | *80.0-120* | | *10/07/2023 14:45* | WG2147038 |
| *(S) 4-Bromofluorobenzene* | *95.3* | | *77.0-126* | | *10/07/2023 14:45* | WG2147038 |
| *(S) 1,2-Dichloroethane-d4* | *111* | | *70.0-130* | | *10/07/2023 14:45* | WG2147038 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/16/2023 22:23 | WG2150669 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/16/2023 22:23 | WG2150669 |
| *(S) o-Terphenyl* | *80.0* | | *52.0-156* | | *10/16/2023 22:23* | WG2150669 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Chrysene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/09/2023 16:22 | WG2147261 |
| Fluorene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Naphthalene | ND | | 0.000250 | 1 | 10/09/2023 16:22 | WG2147261 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| Pyrene | ND | | 0.0000500 | 1 | 10/09/2023 16:22 | WG2147261 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/09/2023 16:22 | WG2147261 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/09/2023 16:22 | WG2147261 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/09/2023 16:22 | WG2147261 |
| *(S) Nitrobenzene-d5* | *107* | | *31.0-160* | | *10/09/2023 16:22* | WG2147261 |
| *(S) 2-Fluorobiphenyl* | *87.9* | | *48.0-148* | | *10/09/2023 16:22* | WG2147261 |
| *(S) p-Terphenyl-d14* | *91.1* | | *37.0-146* | | *10/09/2023 16:22* | WG2147261 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/13/2023 17:12 | WG2150834 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *89.9* | | *78.0-120* | | *10/13/2023 17:12* | WG2150834 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/07/2023 15:06 | WG2147038 |
| Toluene | ND | | 0.00100 | 1 | 10/07/2023 15:06 | WG2147038 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/07/2023 15:06 | WG2147038 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/07/2023 15:06 | WG2147038 |
| *(S) Toluene-d8* | *91.3* | | *80.0-120* | | *10/07/2023 15:06* | WG2147038 |
| *(S) 4-Bromofluorobenzene* | *95.6* | | *77.0-126* | | *10/07/2023 15:06* | WG2147038 |
| *(S) 1,2-Dichloroethane-d4* | *110* | | *70.0-130* | | *10/07/2023 15:06* | WG2147038 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/16/2023 22:43 | WG2150669 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/16/2023 22:43 | WG2150669 |
| *(S) o-Terphenyl* | *80.0* | | *52.0-156* | | *10/16/2023 22:43* | WG2150669 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Benzo(g,h,i)perylene | ND | J4 | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Chrysene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/10/2023 02:04 | WG2147558 |
| Fluorene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Naphthalene | ND | | 0.000250 | 1 | 10/10/2023 02:04 | WG2147558 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| Pyrene | ND | | 0.0000500 | 1 | 10/10/2023 02:04 | WG2147558 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/10/2023 02:04 | WG2147558 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/10/2023 02:04 | WG2147558 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/10/2023 02:04 | WG2147558 |
| *(S) Nitrobenzene-d5* | *95.3* | | *31.0-160* | | *10/10/2023 02:04* | WG2147558 |
| *(S) 2-Fluorobiphenyl* | *102* | | *48.0-148* | | *10/10/2023 02:04* | WG2147558 |
| *(S) p-Terphenyl-d14* | *73.7* | | *37.0-146* | | *10/10/2023 02:04* | WG2147558 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/13/2023 17:57 | WG2150834 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *89.9* | | *78.0-120* | | *10/13/2023 17:57* | WG2150834 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/10/2023 23:18 | WG2148770 |
| Toluene | ND | | 0.00100 | 1 | 10/10/2023 23:18 | WG2148770 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/10/2023 23:18 | WG2148770 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/10/2023 23:18 | WG2148770 |
| *(S) Toluene-d8* | *90.3* | | *80.0-120* | | *10/10/2023 23:18* | WG2148770 |
| *(S) 4-Bromofluorobenzene* | *97.0* | | *77.0-126* | | *10/10/2023 23:18* | WG2148770 |
| *(S) 1,2-Dichloroethane-d4* | *119* | | *70.0-130* | | *10/10/2023 23:18* | WG2148770 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/16/2023 23:03 | WG2150669 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/16/2023 23:03 | WG2150669 |
| *(S) o-Terphenyl* | *88.0* | | *52.0-156* | | *10/16/2023 23:03* | WG2150669 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Benzo(g,h,i)perylene | ND | J4 | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Chrysene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/10/2023 02:24 | WG2147558 |
| Fluorene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Naphthalene | ND | | 0.000250 | 1 | 10/10/2023 02:24 | WG2147558 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| Pyrene | ND | | 0.0000500 | 1 | 10/10/2023 02:24 | WG2147558 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/10/2023 02:24 | WG2147558 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/10/2023 02:24 | WG2147558 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/10/2023 02:24 | WG2147558 |
| *(S) Nitrobenzene-d5* | *92.6* | | *31.0-160* | | *10/10/2023 02:24* | WG2147558 |
| *(S) 2-Fluorobiphenyl* | *102* | | *48.0-148* | | *10/10/2023 02:24* | WG2147558 |
| *(S) p-Terphenyl-d14* | *77.4* | | *37.0-146* | | *10/10/2023 02:24* | WG2147558 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/13/2023 18:19 | WG2150834 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *89.6* | | *78.0-120* | | *10/13/2023 18:19* | WG2150834 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/10/2023 23:41 | WG2148770 |
| Toluene | ND | | 0.00100 | 1 | 10/10/2023 23:41 | WG2148770 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/10/2023 23:41 | WG2148770 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/10/2023 23:41 | WG2148770 |
| *(S) Toluene-d8* | *93.3* | | *80.0-120* | | *10/10/2023 23:41* | WG2148770 |
| *(S) 4-Bromofluorobenzene* | *93.6* | | *77.0-126* | | *10/10/2023 23:41* | WG2148770 |
| *(S) 1,2-Dichloroethane-d4* | *118* | | *70.0-130* | | *10/10/2023 23:41* | WG2148770 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/16/2023 23:22 | WG2150669 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/16/2023 23:22 | WG2150669 |
| *(S) o-Terphenyl* | *82.0* | | *52.0-156* | | *10/16/2023 23:22* | WG2150669 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Benzo(g,h,i)perylene | ND | J4 | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Chrysene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/10/2023 02:44 | WG2147558 |
| Fluorene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Naphthalene | ND | | 0.000250 | 1 | 10/10/2023 02:44 | WG2147558 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| Pyrene | ND | | 0.0000500 | 1 | 10/10/2023 02:44 | WG2147558 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/10/2023 02:44 | WG2147558 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/10/2023 02:44 | WG2147558 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/10/2023 02:44 | WG2147558 |
| *(S) Nitrobenzene-d5* | *95.3* | | *31.0-160* | | *10/10/2023 02:44* | WG2147558 |
| *(S) 2-Fluorobiphenyl* | *104* | | *48.0-148* | | *10/10/2023 02:44* | WG2147558 |
| *(S) p-Terphenyl-d14* | *75.8* | | *37.0-146* | | *10/10/2023 02:44* | WG2147558 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/13/2023 18:42 | WG2150834 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *90.1* | | *78.0-120* | | *10/13/2023 18:42* | WG2150834 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 00:03 | WG2148770 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 00:03 | WG2148770 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 00:03 | WG2148770 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 00:03 | WG2148770 |
| *(S) Toluene-d8* | *90.4* | | *80.0-120* | | *10/11/2023 00:03* | WG2148770 |
| *(S) 4-Bromofluorobenzene* | *90.4* | | *77.0-126* | | *10/11/2023 00:03* | WG2148770 |
| *(S) 1,2-Dichloroethane-d4* | *118* | | *70.0-130* | | *10/11/2023 00:03* | WG2148770 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/16/2023 23:42 | WG2150669 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/16/2023 23:42 | WG2150669 |
| *(S) o-Terphenyl* | *81.0* | | *52.0-156* | | *10/16/2023 23:42* | WG2150669 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Benzo(g,h,i)perylene | ND | J4 | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Chrysene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/10/2023 03:03 | WG2147558 |
| Fluorene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Naphthalene | ND | | 0.000250 | 1 | 10/10/2023 03:03 | WG2147558 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| Pyrene | ND | | 0.0000500 | 1 | 10/10/2023 03:03 | WG2147558 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/10/2023 03:03 | WG2147558 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/10/2023 03:03 | WG2147558 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/10/2023 03:03 | WG2147558 |
| *(S) Nitrobenzene-d5* | *90.0* | | *31.0-160* | | *10/10/2023 03:03* | WG2147558 |
| *(S) 2-Fluorobiphenyl* | *102* | | *48.0-148* | | *10/10/2023 03:03* | WG2147558 |
| *(S) p-Terphenyl-d14* | *74.2* | | *37.0-146* | | *10/10/2023 03:03* | WG2147558 |

## Method Blank (MB)

(MB) R3984502-2 10/09/23 18:33

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | U | | 0.0314 | 0.100 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *104* | | | *78.0-120* |

## Laboratory Control Sample (LCS)

(LCS) R3984502-1 10/09/23 17:49

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 5.04 | 91.6 | 72.0-127 | |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | *102* | *78.0-120* | |

## Method Blank (MB)

(MB) R3986989-2 10/13/23 15:39

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | U | | 0.0314 | 0.100 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *90.1* | | | *78.0-120* |

## Laboratory Control Sample (LCS)

(LCS) R3986989-1 10/13/23 13:47

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 4.77 | 86.7 | 72.0-127 | |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | *96.3* | *78.0-120* | |

## L1662801-04 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1662801-04 10/13/23 17:12 • (MS) R3986989-3 10/14/23 00:37 • (MSD) R3986989-4 10/14/23 01:00

| Analyte | Spike Amount mg/l | Original Result mg/l | MS Result mg/l | MSD Result mg/l | MS Rec. % | MSD Rec. % | Dilution | Rec. Limits % | MS Qualifier | MSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | ND | 5.09 | 4.13 | 92.5 | 75.1 | 1 | 10.0-160 | | | 20.8 | 22 |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | | | *97.3* | *94.5* | | *78.0-120* | | | | |

## Method Blank (MB)

(MB) R3984889-2 10/07/23 12:27

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Benzene | U | | 0.0000941 | 0.00100 |
| Toluene | U | | 0.000278 | 0.00100 |
| Ethylbenzene | U | | 0.000137 | 0.00100 |
| Total Xylenes | U | | 0.000174 | 0.00300 |
| *(S) Toluene-d8* | *92.3* | | | *80.0-120* |
| *(S) 4-Bromofluorobenzene* | *89.8* | | | *77.0-126* |
| *(S) 1,2-Dichloroethane-d4* | *107* | | | *70.0-130* |

## Laboratory Control Sample (LCS)

(LCS) R3984889-1 10/07/23 11:44

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| Benzene | 0.00500 | 0.00582 | 116 | 70.0-123 | |
| Toluene | 0.00500 | 0.00479 | 95.8 | 79.0-120 | |
| Ethylbenzene | 0.00500 | 0.00475 | 95.0 | 79.0-123 | |
| Total Xylenes | 0.0150 | 0.0141 | 94.0 | 79.0-123 | |
| *(S) Toluene-d8* | | | *92.5* | *80.0-120* | |
| *(S) 4-Bromofluorobenzene* | | | *98.0* | *77.0-126* | |
| *(S) 1,2-Dichloroethane-d4* | | | *107* | *70.0-130* | |

## L1663337-06 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1663337-06 10/07/23 18:37 • (MS) R3984889-3 10/07/23 20:23 • (MSD) R3984889-4 10/07/23 20:43

| Analyte | Spike Amount mg/l | Original Result mg/l | MS Result mg/l | MSD Result mg/l | MS Rec. % | MSD Rec. % | Dilution | Rec. Limits % | MS Qualifier | MSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Benzene | 0.00500 | ND | 0.00692 | 0.00711 | 128 | 132 | 1 | 17.0-158 | | | 2.71 | 27 |
| Toluene | 0.00500 | ND | 0.00511 | 0.00551 | 102 | 110 | 1 | 26.0-154 | | | 7.53 | 28 |
| Ethylbenzene | 0.00500 | ND | 0.00531 | 0.00583 | 106 | 117 | 1 | 30.0-155 | | | 9.34 | 27 |
| Total Xylenes | 0.0150 | ND | 0.0162 | 0.0170 | 108 | 113 | 1 | 29.0-154 | | | 4.82 | 28 |
| *(S) Toluene-d8* | | | | | *87.3* | *88.4* | | *80.0-120* | | | | |
| *(S) 4-Bromofluorobenzene* | | | | | *101* | *101* | | *77.0-126* | | | | |
| *(S) 1,2-Dichloroethane-d4* | | | | | *104* | *106* | | *70.0-130* | | | | |

## Method Blank (MB)

(MB) R3985622-3 10/10/23 21:31

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Benzene | U | | 0.0000941 | 0.00100 |
| Toluene | U | | 0.000278 | 0.00100 |
| Ethylbenzene | U | | 0.000137 | 0.00100 |
| Total Xylenes | U | | 0.000174 | 0.00300 |
| *(S) Toluene-d8* | *94.1* | | | *80.0-120* |
| *(S) 4-Bromofluorobenzene* | *96.4* | | | *77.0-126* |
| *(S) 1,2-Dichloroethane-d4* | *118* | | | *70.0-130* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3985622-1 10/10/23 20:25 • (LCSD) R3985622-2 10/10/23 20:47

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Benzene | 0.00500 | 0.00590 | 0.00585 | 118 | 117 | 70.0-123 | | | 0.851 | 20 |
| Toluene | 0.00500 | 0.00493 | 0.00492 | 98.6 | 98.4 | 79.0-120 | | | 0.203 | 20 |
| Ethylbenzene | 0.00500 | 0.00467 | 0.00490 | 93.4 | 98.0 | 79.0-123 | | | 4.81 | 20 |
| Total Xylenes | 0.0150 | 0.0143 | 0.0149 | 95.3 | 99.3 | 79.0-123 | | | 4.11 | 20 |
| *(S) Toluene-d8* | | | | *92.1* | *93.7* | *80.0-120* | | | | |
| *(S) 4-Bromofluorobenzene* | | | | *96.4* | *99.1* | *77.0-126* | | | | |
| *(S) 1,2-Dichloroethane-d4* | | | | *119* | *114* | *70.0-130* | | | | |

## Method Blank (MB)

(MB) R3986861-1 10/16/23 17:10

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| C10-C28 Diesel Range | U | | 0.0222 | 0.100 |
| C28-C40 Oil Range | U | | 0.0118 | 0.100 |
| *(S) o-Terphenyl* | *87.0* | | | *52.0-156* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3986861-2 10/16/23 17:41 • (LCSD) R3986861-3 10/16/23 18:01

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.50 | 1.60 | 1.71 | 107 | 114 | 50.0-150 | | | 6.65 | 20 |
| *(S) o-Terphenyl* | | | | *79.5* | *80.5* | *52.0-156* | | | | |

## Method Blank (MB)

(MB) R3984637-3 10/09/23 13:47

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Anthracene | U | | 0.0000190 | 0.0000500 |
| Acenaphthene | U | | 0.0000190 | 0.0000500 |
| Acenaphthylene | U | | 0.0000171 | 0.0000500 |
| Benzo(a)anthracene | U | | 0.0000203 | 0.0000500 |
| Benzo(a)pyrene | U | | 0.0000184 | 0.0000500 |
| Benzo(b)fluoranthene | U | | 0.0000168 | 0.0000500 |
| Benzo(g,h,i)perylene | U | | 0.0000184 | 0.0000500 |
| Benzo(k)fluoranthene | U | | 0.0000202 | 0.0000500 |
| Chrysene | U | | 0.0000179 | 0.0000500 |
| Dibenz(a,h)anthracene | U | | 0.0000160 | 0.0000500 |
| Fluoranthene | U | | 0.0000270 | 0.000100 |
| Fluorene | U | | 0.0000169 | 0.0000500 |
| Indeno(1,2,3-cd)pyrene | U | | 0.0000158 | 0.0000500 |
| Naphthalene | U | | 0.0000917 | 0.000250 |
| Phenanthrene | U | | 0.0000180 | 0.0000500 |
| Pyrene | U | | 0.0000169 | 0.0000500 |
| 1-Methylnaphthalene | U | | 0.0000687 | 0.000250 |
| 2-Methylnaphthalene | U | | 0.0000674 | 0.000250 |
| 2-Chloronaphthalene | U | | 0.0000682 | 0.000250 |
| *(S) Nitrobenzene-d5* | *108* | | | *31.0-160* |
| *(S) 2-Fluorobiphenyl* | *88.0* | | | *48.0-148* |
| *(S) p-Terphenyl-d14* | *92.5* | | | *37.0-146* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3984637-1 10/09/23 13:13 • (LCSD) R3984637-2 10/09/23 13:30

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Anthracene | 0.00200 | 0.00184 | 0.00185 | 92.0 | 92.5 | 67.0-150 | | | 0.542 | 20 |
| Acenaphthene | 0.00200 | 0.00184 | 0.00177 | 92.0 | 88.5 | 65.0-138 | | | 3.88 | 20 |
| Acenaphthylene | 0.00200 | 0.00197 | 0.00191 | 98.5 | 95.5 | 66.0-140 | | | 3.09 | 20 |
| Benzo(a)anthracene | 0.00200 | 0.00208 | 0.00204 | 104 | 102 | 61.0-140 | | | 1.94 | 20 |
| Benzo(a)pyrene | 0.00200 | 0.00212 | 0.00206 | 106 | 103 | 60.0-143 | | | 2.87 | 20 |
| Benzo(b)fluoranthene | 0.00200 | 0.00188 | 0.00183 | 94.0 | 91.5 | 58.0-141 | | | 2.70 | 20 |
| Benzo(g,h,i)perylene | 0.00200 | 0.00186 | 0.00181 | 93.0 | 90.5 | 52.0-153 | | | 2.72 | 20 |
| Benzo(k)fluoranthene | 0.00200 | 0.00184 | 0.00181 | 92.0 | 90.5 | 58.0-148 | | | 1.64 | 20 |
| Chrysene | 0.00200 | 0.00193 | 0.00190 | 96.5 | 95.0 | 64.0-144 | | | 1.57 | 20 |
| Dibenz(a,h)anthracene | 0.00200 | 0.00198 | 0.00192 | 99.0 | 96.0 | 52.0-155 | | | 3.08 | 20 |
| Fluoranthene | 0.00200 | 0.00203 | 0.00201 | 102 | 100 | 69.0-153 | | | 0.990 | 20 |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3984637-1 10/09/23 13:13 • (LCSD) R3984637-2 10/09/23 13:30

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Fluorene | 0.00200 | 0.00195 | 0.00187 | 97.5 | 93.5 | 64.0-136 | | | 4.19 | 20 |
| Indeno(1,2,3-cd)pyrene | 0.00200 | 0.00221 | 0.00216 | 111 | 108 | 54.0-153 | | | 2.29 | 20 |
| Naphthalene | 0.00200 | 0.00173 | 0.00172 | 86.5 | 86.0 | 61.0-137 | | | 0.580 | 20 |
| Phenanthrene | 0.00200 | 0.00183 | 0.00177 | 91.5 | 88.5 | 62.0-137 | | | 3.33 | 20 |
| Pyrene | 0.00200 | 0.00193 | 0.00189 | 96.5 | 94.5 | 60.0-142 | | | 2.09 | 20 |
| 1-Methylnaphthalene | 0.00200 | 0.00187 | 0.00183 | 93.5 | 91.5 | 66.0-142 | | | 2.16 | 20 |
| 2-Methylnaphthalene | 0.00200 | 0.00192 | 0.00187 | 96.0 | 93.5 | 62.0-136 | | | 2.64 | 20 |
| 2-Chloronaphthalene | 0.00200 | 0.00177 | 0.00170 | 88.5 | 85.0 | 64.0-140 | | | 4.03 | 20 |
| *(S) Nitrobenzene-d5* | | | | *101* | *99.0* | *31.0-160* | | | | |
| *(S) 2-Fluorobiphenyl* | | | | *88.0* | *85.5* | *48.0-148* | | | | |
| *(S) p-Terphenyl-d14* | | | | *90.0* | *87.5* | *37.0-146* | | | | |

## Method Blank (MB)

(MB) R3984856-3 10/10/23 01:45

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Anthracene | U | | 0.0000190 | 0.0000500 |
| Acenaphthene | U | | 0.0000190 | 0.0000500 |
| Acenaphthylene | U | | 0.0000171 | 0.0000500 |
| Benzo(a)anthracene | U | | 0.0000203 | 0.0000500 |
| Benzo(a)pyrene | U | | 0.0000184 | 0.0000500 |
| Benzo(b)fluoranthene | U | | 0.0000168 | 0.0000500 |
| Benzo(g,h,i)perylene | U | | 0.0000184 | 0.0000500 |
| Benzo(k)fluoranthene | U | | 0.0000202 | 0.0000500 |
| Chrysene | U | | 0.0000179 | 0.0000500 |
| Dibenz(a,h)anthracene | U | | 0.0000160 | 0.0000500 |
| Fluoranthene | U | | 0.0000270 | 0.000100 |
| Fluorene | U | | 0.0000169 | 0.0000500 |
| Indeno(1,2,3-cd)pyrene | U | | 0.0000158 | 0.0000500 |
| Naphthalene | U | | 0.0000917 | 0.000250 |
| Phenanthrene | U | | 0.0000180 | 0.0000500 |
| Pyrene | U | | 0.0000169 | 0.0000500 |
| 1-Methylnaphthalene | U | | 0.0000687 | 0.000250 |
| 2-Methylnaphthalene | U | | 0.0000674 | 0.000250 |
| 2-Chloronaphthalene | U | | 0.0000682 | 0.000250 |
| *(S) Nitrobenzene-d5* | *92.5* | | | *31.0-160* |
| *(S) 2-Fluorobiphenyl* | *94.0* | | | *48.0-148* |
| *(S) p-Terphenyl-d14* | *73.5* | | | *37.0-146* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3984856-1 10/10/23 01:06 • (LCSD) R3984856-2 10/10/23 01:25

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Anthracene | 0.00200 | 0.00167 | 0.00179 | 83.5 | 89.5 | 67.0-150 | | | 6.94 | 20 |
| Acenaphthene | 0.00200 | 0.00180 | 0.00192 | 90.0 | 96.0 | 65.0-138 | | | 6.45 | 20 |
| Acenaphthylene | 0.00200 | 0.00189 | 0.00202 | 94.5 | 101 | 66.0-140 | | | 6.65 | 20 |
| Benzo(a)anthracene | 0.00200 | 0.00169 | 0.00176 | 84.5 | 88.0 | 61.0-140 | | | 4.06 | 20 |
| Benzo(a)pyrene | 0.00200 | 0.00131 | 0.00137 | 65.5 | 68.5 | 60.0-143 | | | 4.48 | 20 |
| Benzo(b)fluoranthene | 0.00200 | 0.00120 | 0.00129 | 60.0 | 64.5 | 58.0-141 | | | 7.23 | 20 |
| Benzo(g,h,i)perylene | 0.00200 | 0.00101 | 0.000981 | 50.5 | 49.0 | 52.0-153 | J4 | J4 | 2.91 | 20 |
| Benzo(k)fluoranthene | 0.00200 | 0.00119 | 0.00119 | 59.5 | 59.5 | 58.0-148 | | | 0.000 | 20 |
| Chrysene | 0.00200 | 0.00164 | 0.00180 | 82.0 | 90.0 | 64.0-144 | | | 9.30 | 20 |
| Dibenz(a,h)anthracene | 0.00200 | 0.00108 | 0.00107 | 54.0 | 53.5 | 52.0-155 | | | 0.930 | 20 |
| Fluoranthene | 0.00200 | 0.00177 | 0.00195 | 88.5 | 97.5 | 69.0-153 | | | 9.68 | 20 |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3984856-1 10/10/23 01:06 • (LCSD) R3984856-2 10/10/23 01:25

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Fluorene | 0.00200 | 0.00183 | 0.00196 | 91.5 | 98.0 | 64.0-136 | | | 6.86 | 20 |
| Indeno(1,2,3-cd)pyrene | 0.00200 | 0.00110 | 0.00108 | 55.0 | 54.0 | 54.0-153 | | | 1.83 | 20 |
| Naphthalene | 0.00200 | 0.00175 | 0.00184 | 87.5 | 92.0 | 61.0-137 | | | 5.01 | 20 |
| Phenanthrene | 0.00200 | 0.00167 | 0.00187 | 83.5 | 93.5 | 62.0-137 | | | 11.3 | 20 |
| Pyrene | 0.00200 | 0.00188 | 0.00196 | 94.0 | 98.0 | 60.0-142 | | | 4.17 | 20 |
| 1-Methylnaphthalene | 0.00200 | 0.00181 | 0.00195 | 90.5 | 97.5 | 66.0-142 | | | 7.45 | 20 |
| 2-Methylnaphthalene | 0.00200 | 0.00188 | 0.00198 | 94.0 | 99.0 | 62.0-136 | | | 5.18 | 20 |
| 2-Chloronaphthalene | 0.00200 | 0.00172 | 0.00188 | 86.0 | 94.0 | 64.0-140 | | | 8.89 | 20 |
| *(S) Nitrobenzene-d5* | | | | *95.0* | *93.0* | *31.0-160* | | | | |
| *(S) 2-Fluorobiphenyl* | | | | *94.5* | *96.5* | *48.0-148* | | | | |
| *(S) p-Terphenyl-d14* | | | | *67.0* | *64.5* | *37.0-146* | | | | |

# GLOSSARY OF TERMS

## Guide to Reading and Understanding Your Laboratory Report

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.

Results Disclaimer - Information that may be provided by the customer, and contained within this report, include Permit Limits, Project Name, Sample ID, Sample Matrix, Sample Preservation, Field Blanks, Field Spikes, Field Duplicates, On-Site Data, Sampling Collection Dates/Times, and Sampling Location. Results relate to the accuracy of this information provided, and as the samples are received.

## Abbreviations and Definitions

| | |
|---|---|
| MDL | Method Detection Limit. |
| ND | Not detected at the Reporting Limit (or MDL where applicable). |
| RDL | Reported Detection Limit. |
| Rec. | Recovery. |
| RPD | Relative Percent Difference. |
| SDG | Sample Delivery Group. |
| (S) | Surrogate (Surrogate Standard) - Analytes added to every blank, sample, Laboratory Control Sample/Duplicate and Matrix Spike/Duplicate; used to evaluate analytical efficiency by measuring recovery. Surrogates are not expected to be detected in all environmental media. |
| U | Not detected at the Reporting Limit (or MDL where applicable). |
| Analyte | The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported. |
| Dilution | If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor. |
| Limits | These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges. |
| Original Sample | The non-spiked sample in the prep batch used to determine the Relative Percent Difference (RPD) from a quality control sample. The Original Sample may not be included within the reported SDG. |
| Qualifier | This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable. |
| Result | The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state “ND” (Not Detected) or “BDL” (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte. |
| Uncertainty (Radiochemistry) | Confidence level of 2 sigma. |
| Case Narrative (Cn) | A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report. |
| Quality Control Summary (Qc) | This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material. |
| Sample Chain of Custody (Sc) | This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis. |
| Sample Results (Sr) | This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported. |
| Sample Summary (Ss) | This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis. |

| Qualifier | Description |
|---|---|
| J4 | The associated batch QC was outside the established quality control range for accuracy. |

# ACCREDITATIONS & LOCATIONS

## Pace Analytical National 12065 Lebanon Rd Mount Juliet, TN 37122

| | | | |
|---|---|---|---|
| Alabama | 40660 | Nebraska | NE-OS-15-05 |
| Alaska | 17-026 | Nevada | TN000032021-1 |
| Arizona | AZ0612 | New Hampshire | 2975 |
| Arkansas | 88-0469 | New Jersey–NELAP | TN002 |
| California | 2932 | New Mexico [1] | TN00003 |
| Colorado | TN00003 | New York | 11742 |
| Connecticut | PH-0197 | North Carolina | Env375 |
| Florida | E87487 | North Carolina [1] | DW21704 |
| Georgia | NELAP | North Carolina [3] | 41 |
| Georgia [1] | 923 | North Dakota | R-140 |
| Idaho | TN00003 | Ohio–VAP | CL0069 |
| Illinois | 200008 | Oklahoma | 9915 |
| Indiana | C-TN-01 | Oregon | TN200002 |
| Iowa | 364 | Pennsylvania | 68-02979 |
| Kansas | E-10277 | Rhode Island | LAO000356 |
| Kentucky [1 6] | KY90010 | South Carolina | 84004002 |
| Kentucky [2] | 16 | South Dakota | n/a |
| Louisiana | AI30792 | Tennessee [1 4] | 2006 |
| Louisiana | LA018 | Texas | T104704245-20-18 |
| Maine | TN00003 | Texas [5] | LAB0152 |
| Maryland | 324 | Utah | TN000032021-11 |
| Massachusetts | M-TN003 | Vermont | VT2006 |
| Michigan | 9958 | Virginia | 110033 |
| Minnesota | 047-999-395 | Washington | C847 |
| Mississippi | TN00003 | West Virginia | 233 |
| Missouri | 340 | Wisconsin | 998093910 |
| Montana | CERT0086 | Wyoming | A2LA |
| A2LA – ISO 17025 | 1461.01 | AIHA-LAP,LLC EMLAP | 100789 |
| A2LA – ISO 17025 [5] | 1461.02 | DOD | 1461.01 |
| Canada | 1461.01 | USDA | P330-15-00234 |
| EPA–Crypto | TN00003 | | |

[1] Drinking Water [2] Underground Storage Tanks [3] Aquatic Toxicity [4] Chemical/Microbiological [5] Mold [6] Wastewater n/a Accreditation not applicable

* Not all certifications held by the laboratory are applicable to the results reported in the attached report.

* Accreditation is only applicable to the test methods specified on each scope of accreditation held by Pace Analytical.

Company Name/Address:
**Rio Grande Resources Corp**

**219 S 2nd St**
**Raton, NM 87740**

Billing Information:
**Bruce Norquist**
**PO Box 1150**
**Grants , NM 87020**

Pres Chk

Report to: **Eric Roads** / Melissa Chalona

Email To: **eroads@enganalytics.com;tdavis@enganalytics.**

Project Description: **Mt Taylor**

City/State Collected: New Mexico

Please Circle: PT MT CT ET

Phone: **970-488-3111**

Client Project # 111360

Lab Project # **RIOGRAGNM-MTTAYLOR**

Collected by (print): Tyler Davis

Site/Facility ID #

P.O. #

Collected by (signature): Tyler Davis

Immediately Packed on Ice N ___ Y ✓

***Rush?*** (Lab MUST Be Notified)
___ Same Day ___ Five Day
~~X~~ Next Day ___ 5 Day (Rad Only)
___ Two Day ___ 10 Day (Rad Only)
___ Three Day

Quote #

Date Results Needed

| Sample ID | Comp/Grab | Matrix * | Depth | Date | Time | No. of Cntrs | DROORGLVI 40mlAmb-HCl-BT | GRO 40mlAmb HCl | PAHSIMLVI 40mlAmb-NoPres-WT | SV8270PAH 4ozClr-NoPres | V8260BTEX 40mlAmb-HCl | V8260BTEX 40mlAmb/MeOH10ml/Syr | Remarks | Sample # (lab only) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MT-GW-TS-900-DW7-100323-K3 | Grab | GW | 900 | 10/2/23 | 15:42 | 9 | X | X | X | | X | | | -01 |
| MT-GW-TS-900-DW7-100223 | Grab | GW | 900 | 10/2/23 | 16:46 | 9 | X | X | X | | X | | | -02 |
| MT-GW-TS-900-DW7-10023-K2 | Grab | GW | 900 | 10/2/23 | 17:42 | 9 | X | X | X | | X | | | -03 |
| MT-GW-TS-785-DW1-100323-K3 | Grab | GW | 785 | 10/3/23 | 10:58 | 9 | X | X | X | | X | | | -04 |
| MT-GW-TS-785-DW1-100323-K4 | Grab | GW | 785 | 10/3/23 | 11:09 | 9 | X | X | X | | X | | | -05 |
| MT-GW-TS-785-DW1-100323 | Grab | GW | 785 | 10/3/23 | 12:43 | 9 | X | X | X | | X | | | -06 |
| MT-GW-TS-785-DW1-100323-K1 | Grab | GW | 785 | 10/3/23 | 12:43 | 9 | X | X | X | | X | | | -07 |
| | | GW | | | | 9 | X | X | X | | X | | | |
| | | GW | | | | 9 | X | X | X | | X | | | |
| | | GW | | | | 9 | X | X | X | | X | | | |

Analysis / Container / Preservative

Chain of Custody Page 1 of 1

Pace
PEOPLE ADVANCING SCIENCE

**MT JULIET, TN**
12065 Lebanon Rd Mount Juliet, TN 37122
Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Pace Terms and Conditions found at: https://info.pacelabs.com/hubfs/pas-standard-terms.pdf

SDG # 166280
B041

Acctnum: **RIOGRAGNM**
Template: **T238214**
Prelogin: **P1026344**
PM: **732 - Donna Eidson**
PB: NG 9/27/23
Shipped Via: **FedEX Ground**

* Matrix:
**SS** - Soil **AIR** - Air **F** - Filter
**GW** - Groundwater **B** - Bioassay
**WW** - WasteWater
**DW** - Drinking Water
**OT** - Other_____

**Remarks:**

pH _____ Temp _____
Flow _____ Other _____

Samples returned via:
__ UPS __ FedEx __ Courier _____

Tracking # 6841 8349 2592

Sample Receipt Checklist
COC Seal Present/Intact: __NP __Y __N
COC Signed/Accurate: __Y __N
Bottles arrive intact: __Y __N
Correct bottles used: __Y __N
Sufficient volume sent: __Y __N
If Applicable
VOA Zero Headspace: __Y __N
Preservation Correct/Checked: __Y __N
RAD Screen <0.5 mR/hr: __Y __N

| Relinquished by : (Signature) | Date: | Time: | Received by: (Signature) | Trip Blank Received: Yes / No HCL / MeoH TBR | If preservation required by Login: Date/Time |
|---|---|---|---|---|---|
| Tyler Davis | 10/3/2023 | 16:27 | | | |
| Relinquished by : (Signature) | Date: | Time: | Received by: (Signature) | Temp: °C Bottles Received: | |
| | 10/3/2023 | 1800 | | CA8 4.7+0.4.7 | |
| Relinquished by : (Signature) | Date: | Time: | Received for lab by: (Signature) | Date: Time: | Hold: Condition: NCF / OK |
| | | | | 10-4-23 9:30 | |

# ANALYTICAL REPORT

November 04, 2023



## Rio Grande Resources Corp


| | |
|---|---|
| Sample Delivery Group: | L1664135 |
| Samples Received: | 10/07/2023 |
| Project Number: | 111360 |
| Description: | Mt. Taylor |

Report To: Eric Roads
219 S 2nd St
Raton, NM 87740

Entire Report Reviewed By:

John Hawkins
Project Manager

Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace Analytical National is performed per guidance provided in laboratory standard operating procedures ENV-SOP-MTJL-0067 and ENV-SOP-MTJL-0068. Where sampling conducted by the customer, results relate to the accuracy of the information provided, and as the samples are received.



Pace Analytical National
12065 Lebanon Rd Mount Juliet, TN 37122 615-758-5858 800-767-5859 www.pacenational.com

# TABLE OF CONTENTS


Cp: Cover Page 1

Tc: Table of Contents 2

Ss: Sample Summary 3

Cn: Case Narrative 5

Sr: Sample Results 6

MT-GW-TS2865-DW12-100523-K3 L1664135-01 6

MT-GW-TS-28665-DW12-100523 L1664135-02 7

MT-GW-TS-1764-DW12-100623-K3 L1664135-03 8

MT-GW-TS-1764-DW12-100623 L1664135-04 9

MT-GW-TS-865-DW10-100623-K2 L1664135-05 10

MT-GW-TS-865-DW10-100623-K3 L1664135-06 11

MT-GW-TS-865-DW10-100623 L1664135-07 12

Qc: Quality Control Summary 13

Volatile Organic Compounds (GC) by Method 8015D/GRO 13

Volatile Organic Compounds (GC/MS) by Method 8260B 15

Semi-Volatile Organic Compounds (GC) by Method 8015 17

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM 19

Gl: Glossary of Terms 23

Al: Accreditations & Locations 24

Sc: Sample Chain of Custody 25

## MT-GW-TS2865-DW12-100523-K3 L1664135-01 GW

Collected by: Tyler Davis | Collected date/time: 10/05/23 15:19 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151294 | 1 | 10/14/23 22:02 | 10/14/23 22:02 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148770 | 1 | 10/11/23 01:10 | 10/11/23 01:10 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2152443 | 1 | 10/18/23 05:23 | 10/19/23 21:18 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147261 | 1 | 10/09/23 07:30 | 10/09/23 17:30 | DSH | Mt. Juliet, TN |

## MT-GW-TS-28665-DW12-100523 L1664135-02 GW

Collected by: Tyler Davis | Collected date/time: 10/05/23 17:14 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151294 | 1 | 10/14/23 22:26 | 10/14/23 22:26 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148770 | 1 | 10/11/23 01:32 | 10/11/23 01:32 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2152443 | 1 | 10/18/23 05:23 | 10/19/23 21:38 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147261 | 1 | 10/09/23 07:30 | 10/09/23 17:48 | DSH | Mt. Juliet, TN |

## MT-GW-TS-1764-DW12-100623-K3 L1664135-03 GW

Collected by: Tyler Davis | Collected date/time: 10/06/23 08:33 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151298 | 1 | 10/16/23 13:21 | 10/16/23 13:21 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148770 | 1 | 10/11/23 01:53 | 10/11/23 01:53 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153241 | 1 | 10/19/23 09:26 | 10/20/23 08:49 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147261 | 1 | 10/09/23 07:30 | 10/09/23 18:05 | DSH | Mt. Juliet, TN |

## MT-GW-TS-1764-DW12-100623 L1664135-04 GW

Collected by: Tyler Davis | Collected date/time: 10/06/23 09:46 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151298 | 1 | 10/16/23 13:44 | 10/16/23 13:44 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148770 | 1 | 10/11/23 02:15 | 10/11/23 02:15 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153241 | 1 | 10/19/23 09:26 | 10/20/23 09:09 | TJD | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2148909 | 1 | 10/12/23 16:23 | 10/13/23 16:36 | AMM | Mt. Juliet, TN |

## MT-GW-TS-865-DW10-100623-K2 L1664135-05 GW

Collected by: Tyler Davis | Collected date/time: 10/06/23 11:37 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151298 | 1 | 10/16/23 14:07 | 10/16/23 14:07 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148770 | 1 | 10/11/23 02:38 | 10/11/23 02:38 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153241 | 1 | 10/19/23 09:26 | 10/20/23 09:29 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2148909 | 1 | 10/12/23 16:23 | 10/13/23 16:54 | AMM | Mt. Juliet, TN |

## MT-GW-TS-865-DW10-100623-K3 L1664135-06 GW

Collected by: Tyler Davis | Collected date/time: 10/06/23 13:00 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151298 | 1 | 10/16/23 14:30 | 10/16/23 14:30 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148770 | 1 | 10/11/23 03:00 | 10/11/23 03:00 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153241 | 1 | 10/19/23 09:26 | 10/20/23 09:50 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2148909 | 1 | 10/12/23 16:23 | 10/13/23 17:12 | AMM | Mt. Juliet, TN |

# SAMPLE SUMMARY

## MT-GW-TS-865-DW10-100623 L1664135-07 GW

Collected by: Tyler Davis
Collected date/time: 10/06/23 13:52
Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151298 | 1 | 10/16/23 14:53 | 10/16/23 14:53 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148803 | 1 | 10/11/23 02:11 | 10/11/23 02:11 | JAH | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153241 | 1 | 10/19/23 09:26 | 10/20/23 10:10 | TJD | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2148909 | 1 | 10/12/23 16:23 | 10/13/23 17:30 | AMM | Mt. Juliet, TN |

# CASE NARRATIVE

All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.



John Hawkins
Project Manager

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/14/2023 22:02 | WG2151294 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *92.2* | | *78.0-120* | | *10/14/2023 22:02* | WG2151294 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 01:10 | WG2148770 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 01:10 | WG2148770 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 01:10 | WG2148770 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 01:10 | WG2148770 |
| *(S) Toluene-d8* | *97.2* | | *80.0-120* | | *10/11/2023 01:10* | WG2148770 |
| *(S) 4-Bromofluorobenzene* | *93.8* | | *77.0-126* | | *10/11/2023 01:10* | WG2148770 |
| *(S) 1,2-Dichloroethane-d4* | *121* | | *70.0-130* | | *10/11/2023 01:10* | WG2148770 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/19/2023 21:18 | WG2152443 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/19/2023 21:18 | WG2152443 |
| *(S) o-Terphenyl* | *121* | | *52.0-156* | | *10/19/2023 21:18* | WG2152443 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Chrysene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/09/2023 17:30 | WG2147261 |
| Fluorene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Naphthalene | ND | | 0.000250 | 1 | 10/09/2023 17:30 | WG2147261 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| Pyrene | ND | | 0.0000500 | 1 | 10/09/2023 17:30 | WG2147261 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/09/2023 17:30 | WG2147261 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/09/2023 17:30 | WG2147261 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/09/2023 17:30 | WG2147261 |
| *(S) Nitrobenzene-d5* | *104* | | *31.0-160* | | *10/09/2023 17:30* | WG2147261 |
| *(S) 2-Fluorobiphenyl* | *85.3* | | *48.0-148* | | *10/09/2023 17:30* | WG2147261 |
| *(S) p-Terphenyl-d14* | *87.9* | | *37.0-146* | | *10/09/2023 17:30* | WG2147261 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/14/2023 22:26 | WG2151294 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *92.5* | | *78.0-120* | | *10/14/2023 22:26* | WG2151294 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 01:32 | WG2148770 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 01:32 | WG2148770 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 01:32 | WG2148770 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 01:32 | WG2148770 |
| *(S) Toluene-d8* | *92.4* | | *80.0-120* | | *10/11/2023 01:32* | WG2148770 |
| *(S) 4-Bromofluorobenzene* | *91.5* | | *77.0-126* | | *10/11/2023 01:32* | WG2148770 |
| *(S) 1,2-Dichloroethane-d4* | *116* | | *70.0-130* | | *10/11/2023 01:32* | WG2148770 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.156 | | 0.100 | 1 | 10/19/2023 21:38 | WG2152443 |
| C28-C40 Oil Range | 0.116 | | 0.100 | 1 | 10/19/2023 21:38 | WG2152443 |
| *(S) o-Terphenyl* | *127* | | *52.0-156* | | *10/19/2023 21:38* | WG2152443 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Chrysene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/09/2023 17:48 | WG2147261 |
| Fluorene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Naphthalene | ND | | 0.000250 | 1 | 10/09/2023 17:48 | WG2147261 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| Pyrene | ND | | 0.0000500 | 1 | 10/09/2023 17:48 | WG2147261 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/09/2023 17:48 | WG2147261 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/09/2023 17:48 | WG2147261 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/09/2023 17:48 | WG2147261 |
| *(S) Nitrobenzene-d5* | *104* | | *31.0-160* | | *10/09/2023 17:48* | WG2147261 |
| *(S) 2-Fluorobiphenyl* | *88.9* | | *48.0-148* | | *10/09/2023 17:48* | WG2147261 |
| *(S) p-Terphenyl-d14* | *91.1* | | *37.0-146* | | *10/09/2023 17:48* | WG2147261 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/16/2023 13:21 | WG2151298 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *100* | | *78.0-120* | | *10/16/2023 13:21* | WG2151298 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 01:53 | WG2148770 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 01:53 | WG2148770 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 01:53 | WG2148770 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 01:53 | WG2148770 |
| *(S) Toluene-d8* | *92.9* | | *80.0-120* | | *10/11/2023 01:53* | WG2148770 |
| *(S) 4-Bromofluorobenzene* | *91.6* | | *77.0-126* | | *10/11/2023 01:53* | WG2148770 |
| *(S) 1,2-Dichloroethane-d4* | *120* | | *70.0-130* | | *10/11/2023 01:53* | WG2148770 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/20/2023 08:49 | WG2153241 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/20/2023 08:49 | WG2153241 |
| *(S) o-Terphenyl* | *123* | | *52.0-156* | | *10/20/2023 08:49* | WG2153241 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Chrysene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/09/2023 18:05 | WG2147261 |
| Fluorene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Naphthalene | ND | | 0.000250 | 1 | 10/09/2023 18:05 | WG2147261 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| Pyrene | ND | | 0.0000500 | 1 | 10/09/2023 18:05 | WG2147261 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/09/2023 18:05 | WG2147261 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/09/2023 18:05 | WG2147261 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/09/2023 18:05 | WG2147261 |
| *(S) Nitrobenzene-d5* | *105* | | *31.0-160* | | *10/09/2023 18:05* | WG2147261 |
| *(S) 2-Fluorobiphenyl* | *87.4* | | *48.0-148* | | *10/09/2023 18:05* | WG2147261 |
| *(S) p-Terphenyl-d14* | *87.4* | | *37.0-146* | | *10/09/2023 18:05* | WG2147261 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/16/2023 13:44 | WG2151298 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *100* | | *78.0-120* | | *10/16/2023 13:44* | WG2151298 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 02:15 | WG2148770 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 02:15 | WG2148770 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 02:15 | WG2148770 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 02:15 | WG2148770 |
| *(S) Toluene-d8* | *86.6* | | *80.0-120* | | *10/11/2023 02:15* | WG2148770 |
| *(S) 4-Bromofluorobenzene* | *95.8* | | *77.0-126* | | *10/11/2023 02:15* | WG2148770 |
| *(S) 1,2-Dichloroethane-d4* | *120* | | *70.0-130* | | *10/11/2023 02:15* | WG2148770 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.246 | B | 0.100 | 1 | 10/20/2023 09:09 | WG2153241 |
| C28-C40 Oil Range | 0.126 | B | 0.100 | 1 | 10/20/2023 09:09 | WG2153241 |
| *(S) o-Terphenyl* | *124* | | *52.0-156* | | *10/20/2023 09:09* | WG2153241 |

**Sample Narrative:**

L1664135-04 WG2153241: Duplicate Analysis performed due to Blank contamination. Results confirm; reporting in-hold data.

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Benzo(a)pyrene | ND | J3 J4 | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Benzo(b)fluoranthene | ND | J3 | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Benzo(g,h,i)perylene | ND | J3 J4 | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Benzo(k)fluoranthene | ND | J3 J4 | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Chrysene | ND | J3 | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Dibenz(a,h)anthracene | ND | J3 | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/13/2023 16:36 | WG2148909 |
| Fluorene | ND | | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Indeno(1,2,3-cd)pyrene | ND | J3 | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Naphthalene | ND | | 0.000250 | 1 | 10/13/2023 16:36 | WG2148909 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| Pyrene | ND | | 0.0000500 | 1 | 10/13/2023 16:36 | WG2148909 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/13/2023 16:36 | WG2148909 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/13/2023 16:36 | WG2148909 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/13/2023 16:36 | WG2148909 |
| *(S) Nitrobenzene-d5* | *72.0* | | *31.0-160* | | *10/13/2023 16:36* | WG2148909 |
| *(S) 2-Fluorobiphenyl* | *94.0* | | *48.0-148* | | *10/13/2023 16:36* | WG2148909 |
| *(S) p-Terphenyl-d14* | *78.0* | | *37.0-146* | | *10/13/2023 16:36* | WG2148909 |

**Sample Narrative:**

L1664135-04 WG2148909: QC recovery marginally low, but within historical limits.

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/16/2023 14:07 | WG2151298 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *99.3* | | *78.0-120* | | *10/16/2023 14:07* | WG2151298 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 02:38 | WG2148770 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 02:38 | WG2148770 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 02:38 | WG2148770 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 02:38 | WG2148770 |
| *(S) Toluene-d8* | *92.2* | | *80.0-120* | | *10/11/2023 02:38* | WG2148770 |
| *(S) 4-Bromofluorobenzene* | *93.0* | | *77.0-126* | | *10/11/2023 02:38* | WG2148770 |
| *(S) 1,2-Dichloroethane-d4* | *120* | | *70.0-130* | | *10/11/2023 02:38* | WG2148770 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/20/2023 09:29 | WG2153241 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/20/2023 09:29 | WG2153241 |
| *(S) o-Terphenyl* | *124* | | *52.0-156* | | *10/20/2023 09:29* | WG2153241 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Benzo(a)pyrene | ND | J3 J4 | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Benzo(b)fluoranthene | ND | J3 | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Benzo(g,h,i)perylene | ND | J3 J4 | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Benzo(k)fluoranthene | ND | J3 J4 | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Chrysene | ND | J3 | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Dibenz(a,h)anthracene | ND | J3 | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/13/2023 16:54 | WG2148909 |
| Fluorene | ND | | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Indeno(1,2,3-cd)pyrene | ND | J3 | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Naphthalene | ND | | 0.000250 | 1 | 10/13/2023 16:54 | WG2148909 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| Pyrene | ND | | 0.0000500 | 1 | 10/13/2023 16:54 | WG2148909 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/13/2023 16:54 | WG2148909 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/13/2023 16:54 | WG2148909 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/13/2023 16:54 | WG2148909 |
| *(S) Nitrobenzene-d5* | *103* | | *31.0-160* | | *10/13/2023 16:54* | WG2148909 |
| *(S) 2-Fluorobiphenyl* | *113* | | *48.0-148* | | *10/13/2023 16:54* | WG2148909 |
| *(S) p-Terphenyl-d14* | *93.0* | | *37.0-146* | | *10/13/2023 16:54* | WG2148909 |

**Sample Narrative:**

L1664135-05 WG2148909: QC recovery marginally low, but within historical limits.

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/16/2023 14:30 | WG2151298 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *99.9* | | *78.0-120* | | *10/16/2023 14:30* | WG2151298 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 03:00 | WG2148770 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 03:00 | WG2148770 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 03:00 | WG2148770 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 03:00 | WG2148770 |
| *(S) Toluene-d8* | *93.3* | | *80.0-120* | | *10/11/2023 03:00* | WG2148770 |
| *(S) 4-Bromofluorobenzene* | *95.4* | | *77.0-126* | | *10/11/2023 03:00* | WG2148770 |
| *(S) 1,2-Dichloroethane-d4* | *120* | | *70.0-130* | | *10/11/2023 03:00* | WG2148770 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/20/2023 09:50 | WG2153241 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/20/2023 09:50 | WG2153241 |
| *(S) o-Terphenyl* | *126* | | *52.0-156* | | *10/20/2023 09:50* | WG2153241 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Benzo(a)pyrene | ND | J3 J4 | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Benzo(b)fluoranthene | ND | J3 | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Benzo(g,h,i)perylene | ND | J3 J4 | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Benzo(k)fluoranthene | ND | J3 J4 | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Chrysene | ND | J3 | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Dibenz(a,h)anthracene | ND | J3 | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/13/2023 17:12 | WG2148909 |
| Fluorene | ND | | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Indeno(1,2,3-cd)pyrene | ND | J3 | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Naphthalene | ND | | 0.000250 | 1 | 10/13/2023 17:12 | WG2148909 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| Pyrene | ND | | 0.0000500 | 1 | 10/13/2023 17:12 | WG2148909 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/13/2023 17:12 | WG2148909 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/13/2023 17:12 | WG2148909 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/13/2023 17:12 | WG2148909 |
| *(S) Nitrobenzene-d5* | *97.5* | | *31.0-160* | | *10/13/2023 17:12* | WG2148909 |
| *(S) 2-Fluorobiphenyl* | *107* | | *48.0-148* | | *10/13/2023 17:12* | WG2148909 |
| *(S) p-Terphenyl-d14* | *91.5* | | *37.0-146* | | *10/13/2023 17:12* | WG2148909 |

**Sample Narrative:**

L1664135-06 WG2148909: QC recovery marginally low, but within historical limits.

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/16/2023 14:53 | WG2151298 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *101* | | *78.0-120* | | *10/16/2023 14:53* | WG2151298 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 02:11 | WG2148803 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 02:11 | WG2148803 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 02:11 | WG2148803 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 02:11 | WG2148803 |
| *(S) Toluene-d8* | *109* | | *80.0-120* | | *10/11/2023 02:11* | WG2148803 |
| *(S) 4-Bromofluorobenzene* | *108* | | *77.0-126* | | *10/11/2023 02:11* | WG2148803 |
| *(S) 1,2-Dichloroethane-d4* | *90.8* | | *70.0-130* | | *10/11/2023 02:11* | WG2148803 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.395 | B | 0.100 | 1 | 10/20/2023 10:10 | WG2153241 |
| C28-C40 Oil Range | 0.740 | B | 0.100 | 1 | 10/20/2023 10:10 | WG2153241 |
| *(S) o-Terphenyl* | *129* | | *52.0-156* | | *10/20/2023 10:10* | WG2153241 |

**Sample Narrative:**

L1664135-07 WG2153241: Duplicate Analysis performed due to Blank contamination. Results confirm; reporting in-hold data.

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Benzo(a)pyrene | ND | J3 J4 | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Benzo(b)fluoranthene | ND | J3 | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Benzo(g,h,i)perylene | ND | J3 J4 | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Benzo(k)fluoranthene | ND | J3 J4 | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Chrysene | ND | J3 | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Dibenz(a,h)anthracene | ND | J3 | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/13/2023 17:30 | WG2148909 |
| Fluorene | ND | | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Indeno(1,2,3-cd)pyrene | ND | J3 | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Naphthalene | ND | | 0.000250 | 1 | 10/13/2023 17:30 | WG2148909 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| Pyrene | ND | | 0.0000500 | 1 | 10/13/2023 17:30 | WG2148909 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/13/2023 17:30 | WG2148909 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/13/2023 17:30 | WG2148909 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/13/2023 17:30 | WG2148909 |
| *(S) Nitrobenzene-d5* | *72.0* | | *31.0-160* | | *10/13/2023 17:30* | WG2148909 |
| *(S) 2-Fluorobiphenyl* | *75.0* | | *48.0-148* | | *10/13/2023 17:30* | WG2148909 |
| *(S) p-Terphenyl-d14* | *60.5* | | *37.0-146* | | *10/13/2023 17:30* | WG2148909 |

**Sample Narrative:**

L1664135-07 WG2148909: QC recovery marginally low, but within historical limits.

## Method Blank (MB)

(MB) R3986873-2 10/14/23 20:35

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | U | | 0.0314 | 0.100 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *92.3* | | | *78.0-120* |

## Laboratory Control Sample (LCS)

(LCS) R3986873-1 10/14/23 18:24

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 5.94 | 108 | 72.0-127 | |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | *96.3* | *78.0-120* | |

## Method Blank (MB)

(MB) R3987497-2 10/16/23 12:32

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | U | | 0.0314 | 0.100 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *100* | | | *78.0-120* |

## Laboratory Control Sample (LCS)

(LCS) R3987497-1 10/16/23 11:23

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 5.55 | 101 | 72.0-127 | |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | *103* | *78.0-120* | |

## Method Blank (MB)

(MB) R3985622-3 10/10/23 21:31

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Benzene | U | | 0.0000941 | 0.00100 |
| Toluene | U | | 0.000278 | 0.00100 |
| Ethylbenzene | U | | 0.000137 | 0.00100 |
| Total Xylenes | U | | 0.000174 | 0.00300 |
| *(S) Toluene-d8* | *94.1* | | | *80.0-120* |
| *(S) 4-Bromofluorobenzene* | *96.4* | | | *77.0-126* |
| *(S) 1,2-Dichloroethane-d4* | *118* | | | *70.0-130* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3985622-1 10/10/23 20:25 • (LCSD) R3985622-2 10/10/23 20:47

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Benzene | 0.00500 | 0.00590 | 0.00585 | 118 | 117 | 70.0-123 | | | 0.851 | 20 |
| Toluene | 0.00500 | 0.00493 | 0.00492 | 98.6 | 98.4 | 79.0-120 | | | 0.203 | 20 |
| Ethylbenzene | 0.00500 | 0.00467 | 0.00490 | 93.4 | 98.0 | 79.0-123 | | | 4.81 | 20 |
| Total Xylenes | 0.0150 | 0.0143 | 0.0149 | 95.3 | 99.3 | 79.0-123 | | | 4.11 | 20 |
| *(S) Toluene-d8* | | | | *92.1* | *93.7* | *80.0-120* | | | | |
| *(S) 4-Bromofluorobenzene* | | | | *96.4* | *99.1* | *77.0-126* | | | | |
| *(S) 1,2-Dichloroethane-d4* | | | | *119* | *114* | *70.0-130* | | | | |

## Method Blank (MB)

(MB) R3986818-1 10/10/23 23:44

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Benzene | U | | 0.0000941 | 0.00100 |
| Toluene | U | | 0.000278 | 0.00100 |
| Ethylbenzene | U | | 0.000137 | 0.00100 |
| Total Xylenes | U | | 0.000174 | 0.00300 |
| *(S) Toluene-d8* | *109* | | | *80.0-120* |
| *(S) 4-Bromofluorobenzene* | *110* | | | *77.0-126* |
| *(S) 1,2-Dichloroethane-d4* | *93.7* | | | *70.0-130* |

## Laboratory Control Sample (LCS)

(LCS) R3986818-2 10/11/23 00:46

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| Benzene | 0.00500 | 0.00434 | 86.8 | 70.0-123 | |
| Toluene | 0.00500 | 0.00504 | 101 | 79.0-120 | |
| Ethylbenzene | 0.00500 | 0.00562 | 112 | 79.0-123 | |
| Total Xylenes | 0.0150 | 0.0166 | 111 | 79.0-123 | |
| *(S) Toluene-d8* | | | *108* | *80.0-120* | |
| *(S) 4-Bromofluorobenzene* | | | *110* | *77.0-126* | |
| *(S) 1,2-Dichloroethane-d4* | | | *101* | *70.0-130* | |

## Method Blank (MB)

(MB) R3988265-1 10/18/23 22:09

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| C10-C28 Diesel Range | U | | 0.0222 | 0.100 |
| C28-C40 Oil Range | U | | 0.0118 | 0.100 |
| *(S) o-Terphenyl* | *133* | | | *52.0-156* |

## Laboratory Control Sample (LCS)

(LCS) R3988265-2 10/18/23 22:29

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.50 | 1.30 | 86.7 | 50.0-150 | |
| *(S) o-Terphenyl* | | | *125* | *52.0-156* | |

## L1665816-01 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1665816-01 10/20/23 03:01 • (MS) R3989177-1 10/20/23 03:21 • (MSD) R3989177-2 10/20/23 03:41

| Analyte | Spike Amount mg/l | Original Result mg/l | MS Result mg/l | MSD Result mg/l | MS Rec. % | MSD Rec. % | Dilution | Rec. Limits % | MS Qualifier | MSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.43 | ND | 7.38 | 6.34 | 516 | 443 | 1 | 50.0-150 | J5 | J5 | 15.2 | 20 |
| *(S) o-Terphenyl* | | | | | *140* | *139* | | *52.0-156* | | | | |

## L1665820-03 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1665820-03 10/20/23 04:01 • (MS) R3989177-3 10/20/23 04:22 • (MSD) R3989177-4 10/20/23 04:42

| Analyte | Spike Amount mg/l | Original Result mg/l | MS Result mg/l | MSD Result mg/l | MS Rec. % | MSD Rec. % | Dilution | Rec. Limits % | MS Qualifier | MSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.43 | ND | 3.36 | 3.35 | 235 | 234 | 1 | 50.0-150 | J5 | J5 | 0.298 | 20 |
| *(S) o-Terphenyl* | | | | | *143* | *149* | | *52.0-156* | | | | |

## Method Blank (MB)

(MB) R3989178-1 10/20/23 07:48

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| C10-C28 Diesel Range | 0.0692 | J | 0.0222 | 0.100 |
| C28-C40 Oil Range | 0.148 | | 0.0118 | 0.100 |
| *(S) o-Terphenyl* | *122* | | | *52.0-156* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3989178-2 10/20/23 08:08 • (LCSD) R3989178-3 10/20/23 08:29

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.50 | 1.47 | 1.55 | 98.0 | 103 | 50.0-150 | | | 5.30 | 20 |
| *(S) o-Terphenyl* | | | | *113* | *135* | *52.0-156* | | | | |

## Method Blank (MB)

(MB) R3984637-3 10/09/23 13:47

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Anthracene | U | | 0.0000190 | 0.0000500 |
| Acenaphthene | U | | 0.0000190 | 0.0000500 |
| Acenaphthylene | U | | 0.0000171 | 0.0000500 |
| Benzo(a)anthracene | U | | 0.0000203 | 0.0000500 |
| Benzo(a)pyrene | U | | 0.0000184 | 0.0000500 |
| Benzo(b)fluoranthene | U | | 0.0000168 | 0.0000500 |
| Benzo(g,h,i)perylene | U | | 0.0000184 | 0.0000500 |
| Benzo(k)fluoranthene | U | | 0.0000202 | 0.0000500 |
| Chrysene | U | | 0.0000179 | 0.0000500 |
| Dibenz(a,h)anthracene | U | | 0.0000160 | 0.0000500 |
| Fluoranthene | U | | 0.0000270 | 0.000100 |
| Fluorene | U | | 0.0000169 | 0.0000500 |
| Indeno(1,2,3-cd)pyrene | U | | 0.0000158 | 0.0000500 |
| Naphthalene | U | | 0.0000917 | 0.000250 |
| Phenanthrene | U | | 0.0000180 | 0.0000500 |
| Pyrene | U | | 0.0000169 | 0.0000500 |
| 1-Methylnaphthalene | U | | 0.0000687 | 0.000250 |
| 2-Methylnaphthalene | U | | 0.0000674 | 0.000250 |
| 2-Chloronaphthalene | U | | 0.0000682 | 0.000250 |
| *(S) Nitrobenzene-d5* | *108* | | | *31.0-160* |
| *(S) 2-Fluorobiphenyl* | *88.0* | | | *48.0-148* |
| *(S) p-Terphenyl-d14* | *92.5* | | | *37.0-146* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3984637-1 10/09/23 13:13 • (LCSD) R3984637-2 10/09/23 13:30

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Anthracene | 0.00200 | 0.00184 | 0.00185 | 92.0 | 92.5 | 67.0-150 | | | 0.542 | 20 |
| Acenaphthene | 0.00200 | 0.00184 | 0.00177 | 92.0 | 88.5 | 65.0-138 | | | 3.88 | 20 |
| Acenaphthylene | 0.00200 | 0.00197 | 0.00191 | 98.5 | 95.5 | 66.0-140 | | | 3.09 | 20 |
| Benzo(a)anthracene | 0.00200 | 0.00208 | 0.00204 | 104 | 102 | 61.0-140 | | | 1.94 | 20 |
| Benzo(a)pyrene | 0.00200 | 0.00212 | 0.00206 | 106 | 103 | 60.0-143 | | | 2.87 | 20 |
| Benzo(b)fluoranthene | 0.00200 | 0.00188 | 0.00183 | 94.0 | 91.5 | 58.0-141 | | | 2.70 | 20 |
| Benzo(g,h,i)perylene | 0.00200 | 0.00186 | 0.00181 | 93.0 | 90.5 | 52.0-153 | | | 2.72 | 20 |
| Benzo(k)fluoranthene | 0.00200 | 0.00184 | 0.00181 | 92.0 | 90.5 | 58.0-148 | | | 1.64 | 20 |
| Chrysene | 0.00200 | 0.00193 | 0.00190 | 96.5 | 95.0 | 64.0-144 | | | 1.57 | 20 |
| Dibenz(a,h)anthracene | 0.00200 | 0.00198 | 0.00192 | 99.0 | 96.0 | 52.0-155 | | | 3.08 | 20 |
| Fluoranthene | 0.00200 | 0.00203 | 0.00201 | 102 | 100 | 69.0-153 | | | 0.990 | 20 |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3984637-1 10/09/23 13:13 • (LCSD) R3984637-2 10/09/23 13:30

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Fluorene | 0.00200 | 0.00195 | 0.00187 | 97.5 | 93.5 | 64.0-136 | | | 4.19 | 20 |
| Indeno(1,2,3-cd)pyrene | 0.00200 | 0.00221 | 0.00216 | 111 | 108 | 54.0-153 | | | 2.29 | 20 |
| Naphthalene | 0.00200 | 0.00173 | 0.00172 | 86.5 | 86.0 | 61.0-137 | | | 0.580 | 20 |
| Phenanthrene | 0.00200 | 0.00183 | 0.00177 | 91.5 | 88.5 | 62.0-137 | | | 3.33 | 20 |
| Pyrene | 0.00200 | 0.00193 | 0.00189 | 96.5 | 94.5 | 60.0-142 | | | 2.09 | 20 |
| 1-Methylnaphthalene | 0.00200 | 0.00187 | 0.00183 | 93.5 | 91.5 | 66.0-142 | | | 2.16 | 20 |
| 2-Methylnaphthalene | 0.00200 | 0.00192 | 0.00187 | 96.0 | 93.5 | 62.0-136 | | | 2.64 | 20 |
| 2-Chloronaphthalene | 0.00200 | 0.00177 | 0.00170 | 88.5 | 85.0 | 64.0-140 | | | 4.03 | 20 |
| *(S) Nitrobenzene-d5* | | | | *101* | *99.0* | *31.0-160* | | | | |
| *(S) 2-Fluorobiphenyl* | | | | *88.0* | *85.5* | *48.0-148* | | | | |
| *(S) p-Terphenyl-d14* | | | | *90.0* | *87.5* | *37.0-146* | | | | |

## Method Blank (MB)

(MB) R3986651-3 10/13/23 15:07

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Anthracene | U | | 0.0000190 | 0.0000500 |
| Acenaphthene | U | | 0.0000190 | 0.0000500 |
| Acenaphthylene | U | | 0.0000171 | 0.0000500 |
| Benzo(a)anthracene | U | | 0.0000203 | 0.0000500 |
| Benzo(a)pyrene | U | | 0.0000184 | 0.0000500 |
| Benzo(b)fluoranthene | U | | 0.0000168 | 0.0000500 |
| Benzo(g,h,i)perylene | U | | 0.0000184 | 0.0000500 |
| Benzo(k)fluoranthene | U | | 0.0000202 | 0.0000500 |
| Chrysene | U | | 0.0000179 | 0.0000500 |
| Dibenz(a,h)anthracene | U | | 0.0000160 | 0.0000500 |
| Fluoranthene | U | | 0.0000270 | 0.000100 |
| Fluorene | U | | 0.0000169 | 0.0000500 |
| Indeno(1,2,3-cd)pyrene | U | | 0.0000158 | 0.0000500 |
| Naphthalene | U | | 0.0000917 | 0.000250 |
| Phenanthrene | U | | 0.0000180 | 0.0000500 |
| Pyrene | U | | 0.0000169 | 0.0000500 |
| 1-Methylnaphthalene | U | | 0.0000687 | 0.000250 |
| 2-Methylnaphthalene | U | | 0.0000674 | 0.000250 |
| 2-Chloronaphthalene | U | | 0.0000682 | 0.000250 |
| *(S) Nitrobenzene-d5* | *86.0* | | | *31.0-160* |
| *(S) 2-Fluorobiphenyl* | *97.0* | | | *48.0-148* |
| *(S) p-Terphenyl-d14* | *80.0* | | | *37.0-146* |

## Method Blank (MB)

(MB) R3987948-1 10/16/23 15:39

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Anthracene | U | | 0.0000190 | 0.0000500 |
| Acenaphthene | U | | 0.0000190 | 0.0000500 |
| Acenaphthylene | U | | 0.0000171 | 0.0000500 |
| Benzo(a)anthracene | U | | 0.0000203 | 0.0000500 |
| Benzo(a)pyrene | U | | 0.0000184 | 0.0000500 |
| Benzo(b)fluoranthene | U | | 0.0000168 | 0.0000500 |
| Benzo(g,h,i)perylene | U | | 0.0000184 | 0.0000500 |
| Benzo(k)fluoranthene | U | | 0.0000202 | 0.0000500 |
| Chrysene | U | | 0.0000179 | 0.0000500 |
| Dibenz(a,h)anthracene | U | | 0.0000160 | 0.0000500 |
| Fluoranthene | U | | 0.0000270 | 0.000100 |

## Method Blank (MB)

(MB) R3987948-1 10/16/23 15:39

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Fluorene | U | | 0.0000169 | 0.0000500 |
| Indeno(1,2,3-cd)pyrene | U | | 0.0000158 | 0.0000500 |
| Naphthalene | U | | 0.0000917 | 0.000250 |
| Phenanthrene | U | | 0.0000180 | 0.0000500 |
| Pyrene | U | | 0.0000169 | 0.0000500 |
| 1-Methylnaphthalene | U | | 0.0000687 | 0.000250 |
| 2-Methylnaphthalene | U | | 0.0000674 | 0.000250 |
| 2-Chloronaphthalene | U | | 0.0000682 | 0.000250 |
| *(S) Nitrobenzene-d5* | *114* | | | *31.0-160* |
| *(S) 2-Fluorobiphenyl* | *92.5* | | | *48.0-148* |
| *(S) p-Terphenyl-d14* | *88.0* | | | *37.0-146* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3986651-1 10/13/23 14:31 • (LCSD) R3986651-2 10/13/23 14:49

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Anthracene | 0.00200 | 0.00195 | 0.00195 | 97.5 | 97.5 | 67.0-150 | | | 0.000 | 20 |
| Acenaphthene | 0.00200 | 0.00166 | 0.00164 | 83.0 | 82.0 | 65.0-138 | | | 1.21 | 20 |
| Acenaphthylene | 0.00200 | 0.00168 | 0.00164 | 84.0 | 82.0 | 66.0-140 | | | 2.41 | 20 |
| Benzo(a)anthracene | 0.00200 | 0.00185 | 0.00156 | 92.5 | 78.0 | 61.0-140 | | | 17.0 | 20 |
| Benzo(a)pyrene | 0.00200 | 0.00152 | 0.00118 | 76.0 | 59.0 | 60.0-143 | | J3 J4 | 25.2 | 20 |
| Benzo(b)fluoranthene | 0.00200 | 0.00150 | 0.00122 | 75.0 | 61.0 | 58.0-141 | | J3 | 20.6 | 20 |
| Benzo(g,h,i)perylene | 0.00200 | 0.00138 | 0.00101 | 69.0 | 50.5 | 52.0-153 | | J3 J4 | 31.0 | 20 |
| Benzo(k)fluoranthene | 0.00200 | 0.00143 | 0.00110 | 71.5 | 55.0 | 58.0-148 | | J3 J4 | 26.1 | 20 |
| Chrysene | 0.00200 | 0.00179 | 0.00145 | 89.5 | 72.5 | 64.0-144 | | J3 | 21.0 | 20 |
| Dibenz(a,h)anthracene | 0.00200 | 0.00172 | 0.00125 | 86.0 | 62.5 | 52.0-155 | | J3 | 31.6 | 20 |
| Fluoranthene | 0.00200 | 0.00189 | 0.00189 | 94.5 | 94.5 | 69.0-153 | | | 0.000 | 20 |
| Fluorene | 0.00200 | 0.00179 | 0.00178 | 89.5 | 89.0 | 64.0-136 | | | 0.560 | 20 |
| Indeno(1,2,3-cd)pyrene | 0.00200 | 0.00168 | 0.00122 | 84.0 | 61.0 | 54.0-153 | | J3 | 31.7 | 20 |
| Naphthalene | 0.00200 | 0.00129 | 0.00129 | 64.5 | 64.5 | 61.0-137 | | | 0.000 | 20 |
| Phenanthrene | 0.00200 | 0.00197 | 0.00198 | 98.5 | 99.0 | 62.0-137 | | | 0.506 | 20 |
| Pyrene | 0.00200 | 0.00183 | 0.00182 | 91.5 | 91.0 | 60.0-142 | | | 0.548 | 20 |
| 1-Methylnaphthalene | 0.00200 | 0.00133 | 0.00133 | 66.5 | 66.5 | 66.0-142 | | | 0.000 | 20 |
| 2-Methylnaphthalene | 0.00200 | 0.00137 | 0.00137 | 68.5 | 68.5 | 62.0-136 | | | 0.000 | 20 |
| 2-Chloronaphthalene | 0.00200 | 0.00175 | 0.00169 | 87.5 | 84.5 | 64.0-140 | | | 3.49 | 20 |
| *(S) Nitrobenzene-d5* | | | | *91.0* | *85.0* | *31.0-160* | | | | |
| *(S) 2-Fluorobiphenyl* | | | | *96.0* | *97.0* | *48.0-148* | | | | |
| *(S) p-Terphenyl-d14* | | | | *71.5* | *58.0* | *37.0-146* | | | | |

# GLOSSARY OF TERMS

## Guide to Reading and Understanding Your Laboratory Report

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.

Results Disclaimer - Information that may be provided by the customer, and contained within this report, include Permit Limits, Project Name, Sample ID, Sample Matrix, Sample Preservation, Field Blanks, Field Spikes, Field Duplicates, On-Site Data, Sampling Collection Dates/Times, and Sampling Location. Results relate to the accuracy of this information provided, and as the samples are received.

## Abbreviations and Definitions

| | |
|---|---|
| MDL | Method Detection Limit. |
| ND | Not detected at the Reporting Limit (or MDL where applicable). |
| RDL | Reported Detection Limit. |
| Rec. | Recovery. |
| RPD | Relative Percent Difference. |
| SDG | Sample Delivery Group. |
| (S) | Surrogate (Surrogate Standard) - Analytes added to every blank, sample, Laboratory Control Sample/Duplicate and Matrix Spike/Duplicate; used to evaluate analytical efficiency by measuring recovery. Surrogates are not expected to be detected in all environmental media. |
| U | Not detected at the Reporting Limit (or MDL where applicable). |
| Analyte | The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported. |
| Dilution | If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor. |
| Limits | These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges. |
| Original Sample | The non-spiked sample in the prep batch used to determine the Relative Percent Difference (RPD) from a quality control sample. The Original Sample may not be included within the reported SDG. |
| Qualifier | This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable. |
| Result | The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state “ND” (Not Detected) or “BDL” (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte. |
| Uncertainty (Radiochemistry) | Confidence level of 2 sigma. |
| Case Narrative (Cn) | A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report. |
| Quality Control Summary (Qc) | This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material. |
| Sample Chain of Custody (Sc) | This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis. |
| Sample Results (Sr) | This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported. |
| Sample Summary (Ss) | This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis. |

## Qualifier Description

| Qualifier | Description |
|---|---|
| B | The same analyte is found in the associated blank. |
| J | The identification of the analyte is acceptable; the reported value is an estimate. |
| J3 | The associated batch QC was outside the established quality control range for precision. |
| J4 | The associated batch QC was outside the established quality control range for accuracy. |
| J5 | The sample matrix interfered with the ability to make any accurate determination; spike value is high. |

# ACCREDITATIONS & LOCATIONS

## Pace Analytical National 12065 Lebanon Rd Mount Juliet, TN 37122

| | | | |
|---|---|---|---|
| Alabama | 40660 | Nebraska | NE-OS-15-05 |
| Alaska | 17-026 | Nevada | TN000032021-1 |
| Arizona | AZ0612 | New Hampshire | 2975 |
| Arkansas | 88-0469 | New Jersey–NELAP | TN002 |
| California | 2932 | New Mexico [1] | TN00003 |
| Colorado | TN00003 | New York | 11742 |
| Connecticut | PH-0197 | North Carolina | Env375 |
| Florida | E87487 | North Carolina [1] | DW21704 |
| Georgia | NELAP | North Carolina [3] | 41 |
| Georgia [1] | 923 | North Dakota | R-140 |
| Idaho | TN00003 | Ohio–VAP | CL0069 |
| Illinois | 200008 | Oklahoma | 9915 |
| Indiana | C-TN-01 | Oregon | TN200002 |
| Iowa | 364 | Pennsylvania | 68-02979 |
| Kansas | E-10277 | Rhode Island | LAO000356 |
| Kentucky [1 6] | KY90010 | South Carolina | 84004002 |
| Kentucky [2] | 16 | South Dakota | n/a |
| Louisiana | AI30792 | Tennessee [1 4] | 2006 |
| Louisiana | LA018 | Texas | T104704245-20-18 |
| Maine | TN00003 | Texas [5] | LAB0152 |
| Maryland | 324 | Utah | TN000032021-11 |
| Massachusetts | M-TN003 | Vermont | VT2006 |
| Michigan | 9958 | Virginia | 110033 |
| Minnesota | 047-999-395 | Washington | C847 |
| Mississippi | TN00003 | West Virginia | 233 |
| Missouri | 340 | Wisconsin | 998093910 |
| Montana | CERT0086 | Wyoming | A2LA |
| A2LA – ISO 17025 | 1461.01 | AIHA-LAP,LLC EMLAP | 100789 |
| A2LA – ISO 17025 [5] | 1461.02 | DOD | 1461.01 |
| Canada | 1461.01 | USDA | P330-15-00234 |
| EPA–Crypto | TN00003 | | |

[1] Drinking Water [2] Underground Storage Tanks [3] Aquatic Toxicity [4] Chemical/Microbiological [5] Mold [6] Wastewater n/a Accreditation not applicable

* Not all certifications held by the laboratory are applicable to the results reported in the attached report.

* Accreditation is only applicable to the test methods specified on each scope of accreditation held by Pace Analytical.

Company Name/Address:
**Rio Grande Resources Corp**

**219 S 2nd St**
**Raton, NM 87740**

Billing Information:
**Bruce Norquist**
**PO Box 1150**
**Grants , NM 87020**

Pres Chk

Report to: **Eric Roads**

Email To: **eroads@enganalytics.com;tdavis@enganalytics.**

Project Description: **Mt Taylor**

City/State Collected: Grants, New Mexico

Please Circle: PT MT CT ET

Phone: **970-488-3111**

Client Project # 111360

Lab Project # **RIOGRAGNM-MTTAYLOR**

Collected by (print): Tyler Davis

Site/Facility ID #

P.O. #

Collected by (signature): Tyler Davis

Immediately Packed on Ice N ___ Y ✓

***Rush?*** (Lab MUST be Notified)
___ Same Day ___ Five Day
___ Next Day ___ 5 Day (Rad Only)
___ Two Day ___ 10 Day (Rad Only)
___ Three Day

Quote #

Date Results Needed

Analysis / Container / Preservative

| Sample ID | Comp/Grab | Matrix * | Depth | Date | Time | No. of Cntrs | DROOROLVI 40mlAmb-HCl-BT | GRO 40mlAmb HCl | PAHSIMLVI 40mlAmb-NoPres-WT | SV8270PAH 4ozClr-NoPres | V8260BTEX 40mlAmb-HCl | V8260BTEX 40mlAmb/MeOH10ml/Syr | | | | | Remarks | Sample # (lab only) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MT-GW-TS2865-DW12-100523-K3 | Grab | GW | 2865 | 10-5-23 | 1519 | 9 | X | X | X | | X | | | | | | | -01 |
| MT-GW-TS-2865-DW12-100523 | Grab | GW | 2865 | 10-5-23 | 1714 | 9 | X | X | X | | X | | | | | | | -02 |
| MT-GW-TS-1764-DW12-100623-K3 | Grab | GW | 1764 | 10-6-23 | 8:33 | 9 | X | X | X | | X | | | | | | | -03 |
| MT-GW-TS-1764-DW12-100623 | Grab | GW | 1764 | 10-6-23 | 9:46 | 9 | X | X | X | | X | | | | | | | -04 |
| MT-GW-TS-865-DW10-100623-K2 | Grab | GW | 865 | 10-6-23 | 1137 | 9 | X | X | X | | X | | | | | | | -05 |
| MT-GW-TS-865-DW10-100623-K3 | Grab | GW | 865 | 10-6-23 | 1300 | 9 | X | X | X | | X | | | | | | | -06 |
| MT-GW-TS-856-DW10-100623 | Grab | GW | 856 | 10-6-23 | 1352 | 9 | X | X | X | | X | | | | | | | -07 |
| | | GW | | | | 9 | X | X | X | | X | | | | | | | |
| | | GW | | | | 9 | X | X | X | | X | | | | | | | |
| | | GW | | | | 9 | X | X | X | | X | | | | | | | |

Chain of Custody Page ___ of ___

Pace
PEOPLE ADVANCING SCIENCE

**MT JULIET, TN**

12065 Lebanon Rd Mount Juliet, TN 37122
Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Pace Terms and Conditions found at: https://info.pacelabs.com/hubfs/pas-standard-terms.pdf

SDG # L1664135
D160

Acctnum: **RIOGRAGNM**
Template: **T238214**
Prelogin: **P1026344**
PM: **732 - Donna Eidson**
PB: NG 9/22/23

Shipped Via: **FedEX Ground**

* Matrix:
**SS** - Soil **AIR** - Air **F** - Filter
**GW** - Groundwater **B** - Bioassay
**WW** - WasteWater
**DW** - Drinking Water
**OT** - Other_____

**Remarks:**

pH _____ Temp _____
Flow _____ Other _____

Samples returned via:
__ UPS __ FedEx __ Courier _____

Tracking # 6841 8849 3408

Sample Receipt Checklist

| | | |
|---|---|---|
| COC Seal Present/Intact: | NP | Y N |
| COC Signed/Accurate: | | Y N |
| Bottles arrive intact: | | Y N |
| Correct bottles used: | | Y N |
| Sufficient volume sent: | | Y N |
| **If Applicable** | | |
| VOA Zero Headspace: | | Y N |
| Preservation Correct/Checked: | | Y N |
| RAD Screen <0.5 mR/hr: | | Y N |

| Relinquished by : (Signature) | Date: | Time: | Received by: (Signature) | Trip Blank Received: Yes / No HCL / MeoH TBR | If preservation required by Login: Date/Time |
|---|---|---|---|---|---|
| Tyler Davis | 10-6-23 | 1643 | | | |
| Relinquished by : (Signature) | Date: | Time: | Received by: (Signature) | Temp: CAC °C Bottles Received: 5.2 TO=5.2 L3 | |
| Relinquished by : (Signature) | Date: | Time: | Received for lab by: (Signature) | Date: 10/7/23 Time: 0900 | Hold: Condition: NCF / OK |

Received for lab by: Alta Mitchell @

# ANALYTICAL REPORT

October 23, 2023



## Rio Grande Resources Corp


| | |
|---|---|
| Sample Delivery Group: | L1664199 |
| Samples Received: | 10/07/2023 |
| Project Number: | 111360 |
| Description: | Mt Taylor |

Report To: Eric Roads
219 S 2nd St
Raton, NM 87740

Entire Report Reviewed By: John V Hawkins

John Hawkins
Project Manager

Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace Analytical National is performed per guidance provided in laboratory standard operating procedures ENV-SOP-MTJL-0067 and ENV-SOP-MTJL-0068. Where sampling conducted by the customer, results relate to the accuracy of the information provided, and as the samples are received.



Pace Analytical National
12065 Lebanon Rd Mount Juliet, TN 37122 615-758-5858 800-767-5859 www.pacenational.com

# TABLE OF CONTENTS


Cp: Cover Page 1

Tc: Table of Contents 2

Ss: Sample Summary 3

Cn: Case Narrative 5

Sr: Sample Results 6

MT-GW-TS-2760-DW9-100423-K3 L1664199-01 6

MT-GW-TS-2760-DW9-100423-K2 L1664199-02 7

MT-GW-TS-2760-DW9-100423 L1664199-03 8

MT-GW-TS-1655-DW9-100423-K3 L1664199-04 9

MT-GW-TS-1655-DW9-100423 L1664199-05 10

MT-GW-TS-1144-DW9-100423-K3 L1664199-06 11

MT-GW-TS-1144-DW9-100423 L1664199-07 12

MT-GW-TS-2770-DW2-100423-K3 L1664199-08 13

MT-GW-TS-2770-DW2-100423-K2 L1664199-09 14

MT-GW-TS-2480-DW2-100423 L1664199-10 15

Qc: Quality Control Summary 16

Volatile Organic Compounds (GC) by Method 8015D/GRO 16

Volatile Organic Compounds (GC/MS) by Method 8260B 21

Semi-Volatile Organic Compounds (GC) by Method 8015 22

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM 24

Gl: Glossary of Terms 28

Al: Accreditations & Locations 29

Sc: Sample Chain of Custody 30

## MT-GW-TS-2760-DW9-100423-K3 L1664199-01 GW

Collected by: Tyler Davis | Collected date/time: 10/04/23 10:04 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151135 | 1 | 10/14/23 07:47 | 10/14/23 07:47 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148803 | 1 | 10/11/23 02:30 | 10/11/23 02:30 | JAH | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2152443 | 1 | 10/18/23 05:23 | 10/19/23 21:58 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147644 | 1 | 10/11/23 08:11 | 10/11/23 18:03 | JCH | Mt. Juliet, TN |

## MT-GW-TS-2760-DW9-100423-K2 L1664199-02 GW

Collected by: Tyler Davis | Collected date/time: 10/04/23 10:38 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2152377 | 1 | 10/17/23 13:07 | 10/17/23 13:07 | DWR | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148803 | 1 | 10/11/23 02:49 | 10/11/23 02:49 | JAH | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2151593 | 3 | 10/17/23 07:38 | 10/17/23 22:52 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147644 | 1 | 10/11/23 08:11 | 10/11/23 18:23 | JCH | Mt. Juliet, TN |

## MT-GW-TS-2760-DW9-100423 L1664199-03 GW

Collected by: Tyler Davis | Collected date/time: 10/04/23 12:00 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151291 | 1 | 10/16/23 10:49 | 10/16/23 10:49 | KSD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148803 | 1 | 10/11/23 03:09 | 10/11/23 03:09 | JAH | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2152443 | 1 | 10/18/23 05:23 | 10/19/23 22:18 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147644 | 1 | 10/11/23 08:11 | 10/11/23 21:38 | DSH | Mt. Juliet, TN |

## MT-GW-TS-1655-DW9-100423-K3 L1664199-04 GW

Collected by: Tyler Davis | Collected date/time: 10/04/23 12:30 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151291 | 1 | 10/16/23 11:11 | 10/16/23 11:11 | KSD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148803 | 1 | 10/11/23 03:28 | 10/11/23 03:28 | JAH | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2152443 | 1 | 10/18/23 05:23 | 10/19/23 22:38 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147644 | 1 | 10/11/23 08:11 | 10/11/23 18:42 | DSH | Mt. Juliet, TN |

## MT-GW-TS-1655-DW9-100423 L1664199-05 GW

Collected by: Tyler Davis | Collected date/time: 10/04/23 13:34 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151291 | 1 | 10/16/23 11:34 | 10/16/23 11:34 | KSD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148803 | 1 | 10/11/23 03:47 | 10/11/23 03:47 | JAH | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2152443 | 1 | 10/18/23 05:23 | 10/19/23 22:59 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147644 | 1 | 10/11/23 08:11 | 10/11/23 21:57 | DSH | Mt. Juliet, TN |

## MT-GW-TS-1144-DW9-100423-K3 L1664199-06 GW

Collected by: Tyler Davis | Collected date/time: 10/04/23 14:00 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151291 | 1 | 10/16/23 11:57 | 10/16/23 11:57 | KSD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148803 | 1 | 10/11/23 04:07 | 10/11/23 04:07 | JAH | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2152443 | 1 | 10/18/23 05:23 | 10/19/23 23:19 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147644 | 1 | 10/11/23 08:11 | 10/11/23 19:02 | DSH | Mt. Juliet, TN |

## MT-GW-TS-1144-DW9-100423 L1664199-07 GW

Collected by: Tyler Davis | Collected date/time: 10/04/23 14:54 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151291 | 1 | 10/16/23 12:19 | 10/16/23 12:19 | KSD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148803 | 1 | 10/11/23 04:26 | 10/11/23 04:26 | JAH | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2152443 | 1 | 10/18/23 05:23 | 10/19/23 23:39 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147644 | 1 | 10/11/23 08:11 | 10/11/23 22:17 | DSH | Mt. Juliet, TN |

## MT-GW-TS-2770-DW2-100423-K3 L1664199-08 GW

Collected by: Tyler Davis | Collected date/time: 10/05/23 08:43 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151294 | 1 | 10/14/23 22:51 | 10/14/23 22:51 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148803 | 1 | 10/11/23 04:46 | 10/11/23 04:46 | JAH | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2152443 | 1 | 10/18/23 05:23 | 10/19/23 23:59 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147661 | 1 | 10/11/23 08:05 | 10/11/23 18:08 | DSH | Mt. Juliet, TN |

## MT-GW-TS-2770-DW2-100423-K2 L1664199-09 GW

Collected by: Tyler Davis | Collected date/time: 10/05/23 09:18 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151295 | 1 | 10/14/23 16:02 | 10/14/23 16:02 | AV | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148803 | 1 | 10/11/23 05:05 | 10/11/23 05:05 | JAH | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2152443 | 1 | 10/18/23 05:23 | 10/20/23 00:19 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147661 | 1 | 10/11/23 08:05 | 10/11/23 16:05 | DSH | Mt. Juliet, TN |

## MT-GW-TS-2480-DW2-100423 L1664199-10 GW

Collected by: Tyler Davis | Collected date/time: 10/05/23 12:54 | Received date/time: 10/07/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2151295 | 1 | 10/14/23 16:25 | 10/14/23 16:25 | AV | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2148803 | 1 | 10/11/23 05:24 | 10/11/23 05:24 | JAH | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2152443 | 1 | 10/18/23 05:23 | 10/20/23 00:40 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2147661 | 1 | 10/11/23 08:05 | 10/11/23 18:25 | DSH | Mt. Juliet, TN |

# CASE NARRATIVE

All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.



John Hawkins
Project Manager

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/14/2023 07:47 | WG2151135 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *91.9* | | *78.0-120* | | *10/14/2023 07:47* | WG2151135 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 02:30 | WG2148803 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 02:30 | WG2148803 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 02:30 | WG2148803 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 02:30 | WG2148803 |
| *(S) Toluene-d8* | *112* | | *80.0-120* | | *10/11/2023 02:30* | WG2148803 |
| *(S) 4-Bromofluorobenzene* | *107* | | *77.0-126* | | *10/11/2023 02:30* | WG2148803 |
| *(S) 1,2-Dichloroethane-d4* | *93.8* | | *70.0-130* | | *10/11/2023 02:30* | WG2148803 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/19/2023 21:58 | WG2152443 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/19/2023 21:58 | WG2152443 |
| *(S) o-Terphenyl* | *116* | | *52.0-156* | | *10/19/2023 21:58* | WG2152443 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Chrysene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/11/2023 18:03 | WG2147644 |
| Fluorene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Naphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:03 | WG2147644 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| Pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:03 | WG2147644 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:03 | WG2147644 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:03 | WG2147644 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:03 | WG2147644 |
| *(S) Nitrobenzene-d5* | *178* | J1 | *31.0-160* | | *10/11/2023 18:03* | WG2147644 |
| *(S) 2-Fluorobiphenyl* | *151* | J1 | *48.0-148* | | *10/11/2023 18:03* | WG2147644 |
| *(S) p-Terphenyl-d14* | *175* | J1 | *37.0-146* | | *10/11/2023 18:03* | WG2147644 |

Sample Narrative:

L1664199-01 WG2147644: Duplicate analysis was performed.

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/17/2023 13:07 | WG2152377 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *92.1* | | *78.0-120* | | *10/17/2023 13:07* | WG2152377 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 02:49 | WG2148803 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 02:49 | WG2148803 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 02:49 | WG2148803 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 02:49 | WG2148803 |
| *(S) Toluene-d8* | *113* | | *80.0-120* | | *10/11/2023 02:49* | WG2148803 |
| *(S) 4-Bromofluorobenzene* | *109* | | *77.0-126* | | *10/11/2023 02:49* | WG2148803 |
| *(S) 1,2-Dichloroethane-d4* | *94.1* | | *70.0-130* | | *10/11/2023 02:49* | WG2148803 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.300 | 3 | 10/17/2023 22:52 | WG2151593 |
| C28-C40 Oil Range | ND | | 0.300 | 3 | 10/17/2023 22:52 | WG2151593 |
| *(S) o-Terphenyl* | *164* | J1 | *52.0-156* | | *10/17/2023 22:52* | WG2151593 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Chrysene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/11/2023 18:23 | WG2147644 |
| Fluorene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Naphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:23 | WG2147644 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| Pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:23 | WG2147644 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:23 | WG2147644 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:23 | WG2147644 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:23 | WG2147644 |
| *(S) Nitrobenzene-d5* | *2220* | J1 | *31.0-160* | | *10/11/2023 18:23* | WG2147644 |
| *(S) 2-Fluorobiphenyl* | *1880* | J1 | *48.0-148* | | *10/11/2023 18:23* | WG2147644 |
| *(S) p-Terphenyl-d14* | *1550* | J1 | *37.0-146* | | *10/11/2023 18:23* | WG2147644 |

**Sample Narrative:**

L1664199-02 WG2147644: Duplicate analysis was performed.

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/16/2023 10:49 | WG2151291 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *109* | | *78.0-120* | | *10/16/2023 10:49* | WG2151291 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 03:09 | WG2148803 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 03:09 | WG2148803 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 03:09 | WG2148803 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 03:09 | WG2148803 |
| *(S) Toluene-d8* | *109* | | *80.0-120* | | *10/11/2023 03:09* | WG2148803 |
| *(S) 4-Bromofluorobenzene* | *109* | | *77.0-126* | | *10/11/2023 03:09* | WG2148803 |
| *(S) 1,2-Dichloroethane-d4* | *88.7* | | *70.0-130* | | *10/11/2023 03:09* | WG2148803 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.422 | | 0.100 | 1 | 10/19/2023 22:18 | WG2152443 |
| C28-C40 Oil Range | 1.68 | | 0.100 | 1 | 10/19/2023 22:18 | WG2152443 |
| *(S) o-Terphenyl* | *125* | | *52.0-156* | | *10/19/2023 22:18* | WG2152443 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Chrysene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/11/2023 21:38 | WG2147644 |
| Fluorene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Naphthalene | ND | | 0.000250 | 1 | 10/11/2023 21:38 | WG2147644 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| Pyrene | ND | | 0.0000500 | 1 | 10/11/2023 21:38 | WG2147644 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 21:38 | WG2147644 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 21:38 | WG2147644 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/11/2023 21:38 | WG2147644 |
| *(S) Nitrobenzene-d5* | *126* | | *31.0-160* | | *10/11/2023 21:38* | WG2147644 |
| *(S) 2-Fluorobiphenyl* | *93.2* | | *48.0-148* | | *10/11/2023 21:38* | WG2147644 |
| *(S) p-Terphenyl-d14* | *84.7* | | *37.0-146* | | *10/11/2023 21:38* | WG2147644 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/16/2023 11:11 | WG2151291 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *108* | | *78.0-120* | | *10/16/2023 11:11* | WG2151291 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 03:28 | WG2148803 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 03:28 | WG2148803 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 03:28 | WG2148803 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 03:28 | WG2148803 |
| *(S) Toluene-d8* | *114* | | *80.0-120* | | *10/11/2023 03:28* | WG2148803 |
| *(S) 4-Bromofluorobenzene* | *109* | | *77.0-126* | | *10/11/2023 03:28* | WG2148803 |
| *(S) 1,2-Dichloroethane-d4* | *93.8* | | *70.0-130* | | *10/11/2023 03:28* | WG2148803 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/19/2023 22:38 | WG2152443 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/19/2023 22:38 | WG2152443 |
| *(S) o-Terphenyl* | *121* | | *52.0-156* | | *10/19/2023 22:38* | WG2152443 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Chrysene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/11/2023 18:42 | WG2147644 |
| Fluorene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Naphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:42 | WG2147644 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| Pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:42 | WG2147644 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:42 | WG2147644 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:42 | WG2147644 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:42 | WG2147644 |
| *(S) Nitrobenzene-d5* | *102* | | *31.0-160* | | *10/11/2023 18:42* | WG2147644 |
| *(S) 2-Fluorobiphenyl* | *93.2* | | *48.0-148* | | *10/11/2023 18:42* | WG2147644 |
| *(S) p-Terphenyl-d14* | *92.6* | | *37.0-146* | | *10/11/2023 18:42* | WG2147644 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/16/2023 11:34 | WG2151291 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *108* | | *78.0-120* | | *10/16/2023 11:34* | WG2151291 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 03:47 | WG2148803 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 03:47 | WG2148803 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 03:47 | WG2148803 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 03:47 | WG2148803 |
| *(S) Toluene-d8* | *111* | | *80.0-120* | | *10/11/2023 03:47* | WG2148803 |
| *(S) 4-Bromofluorobenzene* | *109* | | *77.0-126* | | *10/11/2023 03:47* | WG2148803 |
| *(S) 1,2-Dichloroethane-d4* | *91.8* | | *70.0-130* | | *10/11/2023 03:47* | WG2148803 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/19/2023 22:59 | WG2152443 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/19/2023 22:59 | WG2152443 |
| *(S) o-Terphenyl* | *121* | | *52.0-156* | | *10/19/2023 22:59* | WG2152443 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Chrysene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/11/2023 21:57 | WG2147644 |
| Fluorene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Naphthalene | ND | | 0.000250 | 1 | 10/11/2023 21:57 | WG2147644 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| Pyrene | ND | | 0.0000500 | 1 | 10/11/2023 21:57 | WG2147644 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 21:57 | WG2147644 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 21:57 | WG2147644 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/11/2023 21:57 | WG2147644 |
| *(S) Nitrobenzene-d5* | *103* | | *31.0-160* | | *10/11/2023 21:57* | WG2147644 |
| *(S) 2-Fluorobiphenyl* | *88.9* | | *48.0-148* | | *10/11/2023 21:57* | WG2147644 |
| *(S) p-Terphenyl-d14* | *81.1* | | *37.0-146* | | *10/11/2023 21:57* | WG2147644 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/16/2023 11:57 | WG2151291 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *109* | | *78.0-120* | | *10/16/2023 11:57* | WG2151291 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 04:07 | WG2148803 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 04:07 | WG2148803 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 04:07 | WG2148803 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 04:07 | WG2148803 |
| *(S) Toluene-d8* | *108* | | *80.0-120* | | *10/11/2023 04:07* | WG2148803 |
| *(S) 4-Bromofluorobenzene* | *110* | | *77.0-126* | | *10/11/2023 04:07* | WG2148803 |
| *(S) 1,2-Dichloroethane-d4* | *96.4* | | *70.0-130* | | *10/11/2023 04:07* | WG2148803 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/19/2023 23:19 | WG2152443 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/19/2023 23:19 | WG2152443 |
| *(S) o-Terphenyl* | *123* | | *52.0-156* | | *10/19/2023 23:19* | WG2152443 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Chrysene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/11/2023 19:02 | WG2147644 |
| Fluorene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Naphthalene | ND | | 0.000250 | 1 | 10/11/2023 19:02 | WG2147644 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| Pyrene | ND | | 0.0000500 | 1 | 10/11/2023 19:02 | WG2147644 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 19:02 | WG2147644 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 19:02 | WG2147644 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/11/2023 19:02 | WG2147644 |
| *(S) Nitrobenzene-d5* | *98.9* | | *31.0-160* | | *10/11/2023 19:02* | WG2147644 |
| *(S) 2-Fluorobiphenyl* | *93.2* | | *48.0-148* | | *10/11/2023 19:02* | WG2147644 |
| *(S) p-Terphenyl-d14* | *91.1* | | *37.0-146* | | *10/11/2023 19:02* | WG2147644 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/16/2023 12:19 | WG2151291 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *108* | | *78.0-120* | | *10/16/2023 12:19* | WG2151291 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 04:26 | WG2148803 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 04:26 | WG2148803 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 04:26 | WG2148803 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 04:26 | WG2148803 |
| *(S) Toluene-d8* | *110* | | *80.0-120* | | *10/11/2023 04:26* | WG2148803 |
| *(S) 4-Bromofluorobenzene* | *108* | | *77.0-126* | | *10/11/2023 04:26* | WG2148803 |
| *(S) 1,2-Dichloroethane-d4* | *92.9* | | *70.0-130* | | *10/11/2023 04:26* | WG2148803 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.193 | | 0.100 | 1 | 10/19/2023 23:39 | WG2152443 |
| C28-C40 Oil Range | 0.126 | | 0.100 | 1 | 10/19/2023 23:39 | WG2152443 |
| *(S) o-Terphenyl* | *124* | | *52.0-156* | | *10/19/2023 23:39* | WG2152443 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Chrysene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/11/2023 22:17 | WG2147644 |
| Fluorene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Naphthalene | ND | | 0.000250 | 1 | 10/11/2023 22:17 | WG2147644 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| Pyrene | ND | | 0.0000500 | 1 | 10/11/2023 22:17 | WG2147644 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 22:17 | WG2147644 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 22:17 | WG2147644 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/11/2023 22:17 | WG2147644 |
| *(S) Nitrobenzene-d5* | *107* | | *31.0-160* | | *10/11/2023 22:17* | WG2147644 |
| *(S) 2-Fluorobiphenyl* | *88.9* | | *48.0-148* | | *10/11/2023 22:17* | WG2147644 |
| *(S) p-Terphenyl-d14* | *81.6* | | *37.0-146* | | *10/11/2023 22:17* | WG2147644 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/14/2023 22:51 | WG2151294 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *91.8* | | *78.0-120* | | *10/14/2023 22:51* | WG2151294 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 04:46 | WG2148803 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 04:46 | WG2148803 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 04:46 | WG2148803 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 04:46 | WG2148803 |
| *(S) Toluene-d8* | *112* | | *80.0-120* | | *10/11/2023 04:46* | WG2148803 |
| *(S) 4-Bromofluorobenzene* | *108* | | *77.0-126* | | *10/11/2023 04:46* | WG2148803 |
| *(S) 1,2-Dichloroethane-d4* | *98.1* | | *70.0-130* | | *10/11/2023 04:46* | WG2148803 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/19/2023 23:59 | WG2152443 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/19/2023 23:59 | WG2152443 |
| *(S) o-Terphenyl* | *123* | | *52.0-156* | | *10/19/2023 23:59* | WG2152443 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Chrysene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/11/2023 18:08 | WG2147661 |
| Fluorene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Naphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:08 | WG2147661 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| Pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:08 | WG2147661 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:08 | WG2147661 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:08 | WG2147661 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:08 | WG2147661 |
| *(S) Nitrobenzene-d5* | *127* | | *31.0-160* | | *10/11/2023 18:08* | WG2147661 |
| *(S) 2-Fluorobiphenyl* | *106* | | *48.0-148* | | *10/11/2023 18:08* | WG2147661 |
| *(S) p-Terphenyl-d14* | *98.4* | | *37.0-146* | | *10/11/2023 18:08* | WG2147661 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/14/2023 16:02 | WG2151295 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *90.2* | | *78.0-120* | | *10/14/2023 16:02* | WG2151295 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 05:05 | WG2148803 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 05:05 | WG2148803 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 05:05 | WG2148803 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 05:05 | WG2148803 |
| *(S) Toluene-d8* | *110* | | *80.0-120* | | *10/11/2023 05:05* | WG2148803 |
| *(S) 4-Bromofluorobenzene* | *110* | | *77.0-126* | | *10/11/2023 05:05* | WG2148803 |
| *(S) 1,2-Dichloroethane-d4* | *95.6* | | *70.0-130* | | *10/11/2023 05:05* | WG2148803 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/20/2023 00:19 | WG2152443 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/20/2023 00:19 | WG2152443 |
| *(S) o-Terphenyl* | *125* | | *52.0-156* | | *10/20/2023 00:19* | WG2152443 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Chrysene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/11/2023 16:05 | WG2147661 |
| Fluorene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Naphthalene | ND | | 0.000250 | 1 | 10/11/2023 16:05 | WG2147661 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| Pyrene | ND | | 0.0000500 | 1 | 10/11/2023 16:05 | WG2147661 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 16:05 | WG2147661 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 16:05 | WG2147661 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/11/2023 16:05 | WG2147661 |
| *(S) Nitrobenzene-d5* | *124* | | *31.0-160* | | *10/11/2023 16:05* | WG2147661 |
| *(S) 2-Fluorobiphenyl* | *103* | | *48.0-148* | | *10/11/2023 16:05* | WG2147661 |
| *(S) p-Terphenyl-d14* | *95.8* | | *37.0-146* | | *10/11/2023 16:05* | WG2147661 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/14/2023 16:25 | WG2151295 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *91.1* | | *78.0-120* | | *10/14/2023 16:25* | WG2151295 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/11/2023 05:24 | WG2148803 |
| Toluene | ND | | 0.00100 | 1 | 10/11/2023 05:24 | WG2148803 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/11/2023 05:24 | WG2148803 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/11/2023 05:24 | WG2148803 |
| *(S) Toluene-d8* | *109* | | *80.0-120* | | *10/11/2023 05:24* | WG2148803 |
| *(S) 4-Bromofluorobenzene* | *113* | | *77.0-126* | | *10/11/2023 05:24* | WG2148803 |
| *(S) 1,2-Dichloroethane-d4* | *95.8* | | *70.0-130* | | *10/11/2023 05:24* | WG2148803 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.463 | | 0.100 | 1 | 10/20/2023 00:40 | WG2152443 |
| C28-C40 Oil Range | 0.359 | | 0.100 | 1 | 10/20/2023 00:40 | WG2152443 |
| *(S) o-Terphenyl* | *134* | | *52.0-156* | | *10/20/2023 00:40* | WG2152443 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Chrysene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/11/2023 18:25 | WG2147661 |
| Fluorene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Naphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:25 | WG2147661 |
| Phenanthrene | 0.0000639 | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| Pyrene | ND | | 0.0000500 | 1 | 10/11/2023 18:25 | WG2147661 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:25 | WG2147661 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:25 | WG2147661 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/11/2023 18:25 | WG2147661 |
| *(S) Nitrobenzene-d5* | *96.3* | | *31.0-160* | | *10/11/2023 18:25* | WG2147661 |
| *(S) 2-Fluorobiphenyl* | *101* | | *48.0-148* | | *10/11/2023 18:25* | WG2147661 |
| *(S) p-Terphenyl-d14* | *91.6* | | *37.0-146* | | *10/11/2023 18:25* | WG2147661 |

## Method Blank (MB)

(MB) R3986843-4 10/14/23 04:56

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | U | | 0.0314 | 0.100 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *92.0* | | | *78.0-120* |

## Laboratory Control Sample (LCS)

(LCS) R3986843-3 10/14/23 03:16

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 5.98 | 109 | 72.0-127 | |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | *100* | *78.0-120* | |

## L1665738-08 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1665738-08 10/14/23 10:14 • (MS) R3986843-5 10/14/23 15:57 • (MSD) R3986843-6 10/14/23 16:22

| Analyte | Spike Amount mg/l | Original Result mg/l | MS Result mg/l | MSD Result mg/l | MS Rec. % | MSD Rec. % | Dilution | Rec. Limits % | MS Qualifier | MSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 0.139 | 6.05 | 5.87 | 107 | 104 | 1 | 10.0-160 | | | 3.02 | 22 |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | | | *99.8* | *101* | | *78.0-120* | | | | |

## Method Blank (MB)

(MB) R3987756-2 10/16/23 09:55

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | U | | 0.0314 | 0.100 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *108* | | | *78.0-120* |

## Laboratory Control Sample (LCS)

(LCS) R3987756-1 10/16/23 08:49

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 5.24 | 95.3 | 72.0-127 | |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | *114* | *78.0-120* | |

## Method Blank (MB)

(MB) R3986873-2 10/14/23 20:35

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | U | | 0.0314 | 0.100 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *92.3* | | | *78.0-120* |

## Laboratory Control Sample (LCS)

(LCS) R3986873-1 10/14/23 18:24

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 5.94 | 108 | 72.0-127 | |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | *96.3* | *78.0-120* | |

## Method Blank (MB)

(MB) R3987934-2 10/14/23 14:52

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | U | | 0.0314 | 0.100 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *90.8* | | | *78.0-120* |

## Laboratory Control Sample (LCS)

(LCS) R3987934-1 10/14/23 13:43

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 6.31 | 115 | 72.0-127 | |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | *101* | *78.0-120* | |

## L1664199-09 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1664199-09 10/14/23 16:02 • (MS) R3987934-3 10/14/23 23:36 • (MSD) R3987934-4 10/14/23 23:59

| Analyte | Spike Amount mg/l | Original Result mg/l | MS Result mg/l | MSD Result mg/l | MS Rec. % | MSD Rec. % | Dilution | Rec. Limits % | MS Qualifier | MSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | ND | 5.06 | 4.48 | 92.0 | 81.5 | 1 | 10.0-160 | | | 12.2 | 22 |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | | | *97.1* | *96.1* | | *78.0-120* | | | | |

## Method Blank (MB)

(MB) R3987845-2 10/17/23 12:17

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | U | | 0.0314 | 0.100 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *92.4* | | | *78.0-120* |

## Laboratory Control Sample (LCS)

(LCS) R3987845-1 10/17/23 11:15

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 5.06 | 92.0 | 72.0-127 | |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | *99.1* | *78.0-120* | |

## Method Blank (MB)

(MB) R3986818-1 10/10/23 23:44

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Benzene | U | | 0.0000941 | 0.00100 |
| Toluene | U | | 0.000278 | 0.00100 |
| Ethylbenzene | U | | 0.000137 | 0.00100 |
| Total Xylenes | U | | 0.000174 | 0.00300 |
| *(S) Toluene-d8* | *109* | | | *80.0-120* |
| *(S) 4-Bromofluorobenzene* | *110* | | | *77.0-126* |
| *(S) 1,2-Dichloroethane-d4* | *93.7* | | | *70.0-130* |

## Laboratory Control Sample (LCS)

(LCS) R3986818-2 10/11/23 00:46

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| Benzene | 0.00500 | 0.00434 | 86.8 | 70.0-123 | |
| Toluene | 0.00500 | 0.00504 | 101 | 79.0-120 | |
| Ethylbenzene | 0.00500 | 0.00562 | 112 | 79.0-123 | |
| Total Xylenes | 0.0150 | 0.0166 | 111 | 79.0-123 | |
| *(S) Toluene-d8* | | | *108* | *80.0-120* | |
| *(S) 4-Bromofluorobenzene* | | | *110* | *77.0-126* | |
| *(S) 1,2-Dichloroethane-d4* | | | *101* | *70.0-130* | |

## Method Blank (MB)

(MB) R3987480-1 10/17/23 18:58

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| C10-C28 Diesel Range | U | | 0.0222 | 0.100 |
| C28-C40 Oil Range | U | | 0.0118 | 0.100 |
| *(S) o-Terphenyl* | *78.0* | | | *52.0-156* |

## Laboratory Control Sample (LCS)

(LCS) R3987480-2 10/17/23 19:17

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.50 | 1.63 | 109 | 50.0-150 | |
| *(S) o-Terphenyl* | | | *81.5* | *52.0-156* | |

## L1665738-08 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1665738-08 10/17/23 21:53 • (MS) R3987480-3 10/17/23 22:13 • (MSD) R3987480-4 10/17/23 22:32

| Analyte | Spike Amount mg/l | Original Result mg/l | MS Result mg/l | MSD Result mg/l | MS Rec. % | MSD Rec. % | Dilution | Rec. Limits % | MS Qualifier | MSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.43 | ND | 1.60 | 1.57 | 112 | 110 | 1 | 50.0-150 | | | 1.89 | 20 |
| *(S) o-Terphenyl* | | | | | *86.3* | *83.2* | | *52.0-156* | | | | |

## Method Blank (MB)

(MB) R3988265-1 10/18/23 22:09

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| C10-C28 Diesel Range | U | | 0.0222 | 0.100 |
| C28-C40 Oil Range | U | | 0.0118 | 0.100 |
| *(S) o-Terphenyl* | *133* | | | *52.0-156* |

## Laboratory Control Sample (LCS)

(LCS) R3988265-2 10/18/23 22:29

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.50 | 1.30 | 86.7 | 50.0-150 | |
| *(S) o-Terphenyl* | | | *125* | *52.0-156* | |

## L1665816-01 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1665816-01 10/20/23 03:01 • (MS) R3989177-1 10/20/23 03:21 • (MSD) R3989177-2 10/20/23 03:41

| Analyte | Spike Amount mg/l | Original Result mg/l | MS Result mg/l | MSD Result mg/l | MS Rec. % | MSD Rec. % | Dilution | Rec. Limits % | MS Qualifier | MSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.43 | ND | 7.38 | 6.34 | 516 | 443 | 1 | 50.0-150 | J5 | J5 | 15.2 | 20 |
| *(S) o-Terphenyl* | | | | | *140* | *139* | | *52.0-156* | | | | |

## L1665820-03 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1665820-03 10/20/23 04:01 • (MS) R3989177-3 10/20/23 04:22 • (MSD) R3989177-4 10/20/23 04:42

| Analyte | Spike Amount mg/l | Original Result mg/l | MS Result mg/l | MSD Result mg/l | MS Rec. % | MSD Rec. % | Dilution | Rec. Limits % | MS Qualifier | MSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.43 | ND | 3.36 | 3.35 | 235 | 234 | 1 | 50.0-150 | J5 | J5 | 0.298 | 20 |
| *(S) o-Terphenyl* | | | | | *143* | *149* | | *52.0-156* | | | | |

## Method Blank (MB)

(MB) R3985224-2 10/11/23 16:45

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Anthracene | U | | 0.0000190 | 0.0000500 |
| Acenaphthene | U | | 0.0000190 | 0.0000500 |
| Acenaphthylene | U | | 0.0000171 | 0.0000500 |
| Benzo(a)anthracene | U | | 0.0000203 | 0.0000500 |
| Benzo(a)pyrene | U | | 0.0000184 | 0.0000500 |
| Benzo(b)fluoranthene | U | | 0.0000168 | 0.0000500 |
| Benzo(g,h,i)perylene | U | | 0.0000184 | 0.0000500 |
| Benzo(k)fluoranthene | U | | 0.0000202 | 0.0000500 |
| Chrysene | U | | 0.0000179 | 0.0000500 |
| Dibenz(a,h)anthracene | U | | 0.0000160 | 0.0000500 |
| Fluoranthene | U | | 0.0000270 | 0.000100 |
| Fluorene | U | | 0.0000169 | 0.0000500 |
| Indeno(1,2,3-cd)pyrene | U | | 0.0000158 | 0.0000500 |
| Naphthalene | U | | 0.0000917 | 0.000250 |
| Phenanthrene | U | | 0.0000180 | 0.0000500 |
| Pyrene | U | | 0.0000169 | 0.0000500 |
| 1-Methylnaphthalene | U | | 0.0000687 | 0.000250 |
| 2-Methylnaphthalene | U | | 0.0000674 | 0.000250 |
| 2-Chloronaphthalene | U | | 0.0000682 | 0.000250 |
| *(S) Nitrobenzene-d5* | *135* | | | *31.0-160* |
| *(S) 2-Fluorobiphenyl* | *120* | | | *48.0-148* |
| *(S) p-Terphenyl-d14* | *112* | | | *37.0-146* |

## Laboratory Control Sample (LCS)

(LCS) R3985224-1 10/11/23 16:26

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| Anthracene | 0.00200 | 0.00204 | 102 | 67.0-150 | |
| Acenaphthene | 0.00200 | 0.00190 | 95.0 | 65.0-138 | |
| Acenaphthylene | 0.00200 | 0.00206 | 103 | 66.0-140 | |
| Benzo(a)anthracene | 0.00200 | 0.00229 | 115 | 61.0-140 | |
| Benzo(a)pyrene | 0.00200 | 0.00201 | 100 | 60.0-143 | |
| Benzo(b)fluoranthene | 0.00200 | 0.00174 | 87.0 | 58.0-141 | |
| Benzo(g,h,i)perylene | 0.00200 | 0.00158 | 79.0 | 52.0-153 | |
| Benzo(k)fluoranthene | 0.00200 | 0.00172 | 86.0 | 58.0-148 | |
| Chrysene | 0.00200 | 0.00204 | 102 | 64.0-144 | |
| Dibenz(a,h)anthracene | 0.00200 | 0.00175 | 87.5 | 52.0-155 | |
| Fluoranthene | 0.00200 | 0.00209 | 104 | 69.0-153 | |

## Laboratory Control Sample (LCS)

(LCS) R3985224-1 10/11/23 16:26

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| Fluorene | 0.00200 | 0.00204 | 102 | 64.0-136 | |
| Indeno(1,2,3-cd)pyrene | 0.00200 | 0.00194 | 97.0 | 54.0-153 | |
| Naphthalene | 0.00200 | 0.00201 | 100 | 61.0-137 | |
| Phenanthrene | 0.00200 | 0.00199 | 99.5 | 62.0-137 | |
| Pyrene | 0.00200 | 0.00202 | 101 | 60.0-142 | |
| 1-Methylnaphthalene | 0.00200 | 0.00202 | 101 | 66.0-142 | |
| 2-Methylnaphthalene | 0.00200 | 0.00207 | 104 | 62.0-136 | |
| 2-Chloronaphthalene | 0.00200 | 0.00191 | 95.5 | 64.0-140 | |
| *(S) Nitrobenzene-d5* | | | *108* | *31.0-160* | |
| *(S) 2-Fluorobiphenyl* | | | *95.0* | *48.0-148* | |
| *(S) p-Terphenyl-d14* | | | *89.5* | *37.0-146* | |

## L1663857-02 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1663857-02 10/11/23 17:05 • (MS) R3985224-3 10/11/23 17:24 • (MSD) R3985224-4 10/11/23 17:44

| Analyte | Spike Amount mg/l | Original Result mg/l | MS Result mg/l | MSD Result mg/l | MS Rec. % | MSD Rec. % | Dilution | Rec. Limits % | MS Qualifier | MSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Anthracene | 0.00190 | ND | 0.00181 | 0.00178 | 95.3 | 93.7 | 1 | 56.0-156 | | | 1.67 | 20 |
| Acenaphthene | 0.00190 | ND | 0.00172 | 0.00174 | 90.5 | 91.6 | 1 | 44.0-153 | | | 1.16 | 20 |
| Acenaphthylene | 0.00190 | ND | 0.00186 | 0.00188 | 97.9 | 98.9 | 1 | 53.0-150 | | | 1.07 | 20 |
| Benzo(a)anthracene | 0.00190 | ND | 0.00201 | 0.00163 | 106 | 85.8 | 1 | 47.0-151 | | J3 | 20.9 | 20 |
| Benzo(a)pyrene | 0.00190 | ND | 0.00179 | 0.000963 | 94.2 | 50.7 | 1 | 45.0-146 | | J3 | 60.1 | 20 |
| Benzo(b)fluoranthene | 0.00190 | ND | 0.00155 | 0.000892 | 81.6 | 46.9 | 1 | 43.0-142 | | J3 | 53.9 | 20 |
| Benzo(g,h,i)perylene | 0.00190 | ND | 0.00138 | 0.000492 | 72.6 | 25.9 | 1 | 40.0-147 | | J3 J6 | 94.9 | 20 |
| Benzo(k)fluoranthene | 0.00190 | ND | 0.00160 | 0.000791 | 84.2 | 41.6 | 1 | 43.0-148 | | J3 J6 | 67.7 | 21 |
| Chrysene | 0.00190 | ND | 0.00184 | 0.00150 | 96.8 | 78.9 | 1 | 50.0-148 | | J3 | 20.4 | 20 |
| Dibenz(a,h)anthracene | 0.00190 | ND | 0.00152 | 0.000443 | 80.0 | 23.3 | 1 | 37.0-151 | | J3 J6 | 110 | 20 |
| Fluoranthene | 0.00190 | ND | 0.00186 | 0.00181 | 97.9 | 95.3 | 1 | 56.0-157 | | | 2.72 | 20 |
| Fluorene | 0.00190 | ND | 0.00184 | 0.00185 | 96.8 | 97.4 | 1 | 48.0-148 | | | 0.542 | 20 |
| Indeno(1,2,3-cd)pyrene | 0.00190 | ND | 0.00170 | 0.000543 | 89.5 | 28.6 | 1 | 41.0-148 | | J3 J6 | 103 | 20 |
| Naphthalene | 0.00190 | ND | 0.00182 | 0.00183 | 95.8 | 96.3 | 1 | 10.0-160 | | | 0.548 | 20 |
| Phenanthrene | 0.00190 | ND | 0.00175 | 0.00175 | 92.1 | 92.1 | 1 | 47.0-147 | | | 0.000 | 20 |
| Pyrene | 0.00190 | ND | 0.00182 | 0.00180 | 95.8 | 94.7 | 1 | 51.0-148 | | | 1.10 | 20 |
| 1-Methylnaphthalene | 0.00190 | ND | 0.00183 | 0.00183 | 96.3 | 96.3 | 1 | 21.0-160 | | | 0.000 | 20 |
| 2-Methylnaphthalene | 0.00190 | ND | 0.00188 | 0.00188 | 98.9 | 98.9 | 1 | 31.0-160 | | | 0.000 | 20 |
| 2-Chloronaphthalene | 0.00190 | ND | 0.00174 | 0.00175 | 91.6 | 92.1 | 1 | 52.0-148 | | | 0.573 | 20 |
| *(S) Nitrobenzene-d5* | | | | | *101* | *99.5* | | *31.0-160* | | | | |
| *(S) 2-Fluorobiphenyl* | | | | | *91.6* | *90.5* | | *48.0-148* | | | | |
| *(S) p-Terphenyl-d14* | | | | | *86.3* | *53.7* | | *37.0-146* | | | | |

## Method Blank (MB)

(MB) R3984860-3 10/11/23 14:06

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Anthracene | U | | 0.0000190 | 0.0000500 |
| Acenaphthene | U | | 0.0000190 | 0.0000500 |
| Acenaphthylene | U | | 0.0000171 | 0.0000500 |
| Benzo(a)anthracene | U | | 0.0000203 | 0.0000500 |
| Benzo(a)pyrene | U | | 0.0000184 | 0.0000500 |
| Benzo(b)fluoranthene | U | | 0.0000168 | 0.0000500 |
| Benzo(g,h,i)perylene | U | | 0.0000184 | 0.0000500 |
| Benzo(k)fluoranthene | U | | 0.0000202 | 0.0000500 |
| Chrysene | U | | 0.0000179 | 0.0000500 |
| Dibenz(a,h)anthracene | U | | 0.0000160 | 0.0000500 |
| Fluoranthene | U | | 0.0000270 | 0.000100 |
| Fluorene | U | | 0.0000169 | 0.0000500 |
| Indeno(1,2,3-cd)pyrene | U | | 0.0000158 | 0.0000500 |
| Naphthalene | U | | 0.0000917 | 0.000250 |
| Phenanthrene | U | | 0.0000180 | 0.0000500 |
| Pyrene | U | | 0.0000169 | 0.0000500 |
| 1-Methylnaphthalene | U | | 0.0000687 | 0.000250 |
| 2-Methylnaphthalene | U | | 0.0000674 | 0.000250 |
| 2-Chloronaphthalene | U | | 0.0000682 | 0.000250 |
| *(S) Nitrobenzene-d5* | *139* | | | *31.0-160* |
| *(S) 2-Fluorobiphenyl* | *114* | | | *48.0-148* |
| *(S) p-Terphenyl-d14* | *108* | | | *37.0-146* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3984860-1 10/11/23 13:31 • (LCSD) R3984860-2 10/11/23 13:48

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Anthracene | 0.00200 | 0.00194 | 0.00189 | 97.0 | 94.5 | 67.0-150 | | | 2.61 | 20 |
| Acenaphthene | 0.00200 | 0.00186 | 0.00181 | 93.0 | 90.5 | 65.0-138 | | | 2.72 | 20 |
| Acenaphthylene | 0.00200 | 0.00192 | 0.00188 | 96.0 | 94.0 | 66.0-140 | | | 2.11 | 20 |
| Benzo(a)anthracene | 0.00200 | 0.00212 | 0.00205 | 106 | 103 | 61.0-140 | | | 3.36 | 20 |
| Benzo(a)pyrene | 0.00200 | 0.00208 | 0.00201 | 104 | 100 | 60.0-143 | | | 3.42 | 20 |
| Benzo(b)fluoranthene | 0.00200 | 0.00207 | 0.00205 | 104 | 103 | 58.0-141 | | | 0.971 | 20 |
| Benzo(g,h,i)perylene | 0.00200 | 0.00198 | 0.00191 | 99.0 | 95.5 | 52.0-153 | | | 3.60 | 20 |
| Benzo(k)fluoranthene | 0.00200 | 0.00205 | 0.00197 | 103 | 98.5 | 58.0-148 | | | 3.98 | 20 |
| Chrysene | 0.00200 | 0.00203 | 0.00201 | 102 | 100 | 64.0-144 | | | 0.990 | 20 |
| Dibenz(a,h)anthracene | 0.00200 | 0.00209 | 0.00203 | 104 | 102 | 52.0-155 | | | 2.91 | 20 |
| Fluoranthene | 0.00200 | 0.00195 | 0.00195 | 97.5 | 97.5 | 69.0-153 | | | 0.000 | 20 |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3984860-1 10/11/23 13:31 • (LCSD) R3984860-2 10/11/23 13:48

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Fluorene | 0.00200 | 0.00205 | 0.00199 | 103 | 99.5 | 64.0-136 | | | 2.97 | 20 |
| Indeno(1,2,3-cd)pyrene | 0.00200 | 0.00220 | 0.00213 | 110 | 106 | 54.0-153 | | | 3.23 | 20 |
| Naphthalene | 0.00200 | 0.00191 | 0.00193 | 95.5 | 96.5 | 61.0-137 | | | 1.04 | 20 |
| Phenanthrene | 0.00200 | 0.00195 | 0.00193 | 97.5 | 96.5 | 62.0-137 | | | 1.03 | 20 |
| Pyrene | 0.00200 | 0.00200 | 0.00196 | 100 | 98.0 | 60.0-142 | | | 2.02 | 20 |
| 1-Methylnaphthalene | 0.00200 | 0.00190 | 0.00193 | 95.0 | 96.5 | 66.0-142 | | | 1.57 | 20 |
| 2-Methylnaphthalene | 0.00200 | 0.00207 | 0.00207 | 104 | 104 | 62.0-136 | | | 0.000 | 20 |
| 2-Chloronaphthalene | 0.00200 | 0.00219 | 0.00212 | 109 | 106 | 64.0-140 | | | 3.25 | 20 |
| *(S) Nitrobenzene-d5* | | | | *132* | *122* | *31.0-160* | | | | |
| *(S) 2-Fluorobiphenyl* | | | | *110* | *102* | *48.0-148* | | | | |
| *(S) p-Terphenyl-d14* | | | | *99.5* | *94.0* | *37.0-146* | | | | |

# GLOSSARY OF TERMS

## Guide to Reading and Understanding Your Laboratory Report

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.

Results Disclaimer - Information that may be provided by the customer, and contained within this report, include Permit Limits, Project Name, Sample ID, Sample Matrix, Sample Preservation, Field Blanks, Field Spikes, Field Duplicates, On-Site Data, Sampling Collection Dates/Times, and Sampling Location. Results relate to the accuracy of this information provided, and as the samples are received.

## Abbreviations and Definitions

| | |
|---|---|
| MDL | Method Detection Limit. |
| ND | Not detected at the Reporting Limit (or MDL where applicable). |
| RDL | Reported Detection Limit. |
| Rec. | Recovery. |
| RPD | Relative Percent Difference. |
| SDG | Sample Delivery Group. |
| (S) | Surrogate (Surrogate Standard) - Analytes added to every blank, sample, Laboratory Control Sample/Duplicate and Matrix Spike/Duplicate; used to evaluate analytical efficiency by measuring recovery. Surrogates are not expected to be detected in all environmental media. |
| U | Not detected at the Reporting Limit (or MDL where applicable). |
| Analyte | The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported. |
| Dilution | If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor. |
| Limits | These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges. |
| Original Sample | The non-spiked sample in the prep batch used to determine the Relative Percent Difference (RPD) from a quality control sample. The Original Sample may not be included within the reported SDG. |
| Qualifier | This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable. |
| Result | The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state “ND” (Not Detected) or “BDL” (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte. |
| Uncertainty (Radiochemistry) | Confidence level of 2 sigma. |
| Case Narrative (Cn) | A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report. |
| Quality Control Summary (Qc) | This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material. |
| Sample Chain of Custody (Sc) | This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis. |
| Sample Results (Sr) | This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported. |
| Sample Summary (Ss) | This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis. |

| Qualifier | Description |
|---|---|
| J1 | Surrogate recovery limits have been exceeded; values are outside upper control limits. |
| J3 | The associated batch QC was outside the established quality control range for precision. |
| J5 | The sample matrix interfered with the ability to make any accurate determination; spike value is high. |
| J6 | The sample matrix interfered with the ability to make any accurate determination; spike value is low. |

# ACCREDITATIONS & LOCATIONS

## Pace Analytical National 12065 Lebanon Rd Mount Juliet, TN 37122

| | | | |
|---|---|---|---|
| Alabama | 40660 | Nebraska | NE-OS-15-05 |
| Alaska | 17-026 | Nevada | TN000032021-1 |
| Arizona | AZ0612 | New Hampshire | 2975 |
| Arkansas | 88-0469 | New Jersey–NELAP | TN002 |
| California | 2932 | New Mexico [1] | TN00003 |
| Colorado | TN00003 | New York | 11742 |
| Connecticut | PH-0197 | North Carolina | Env375 |
| Florida | E87487 | North Carolina [1] | DW21704 |
| Georgia | NELAP | North Carolina [3] | 41 |
| Georgia [1] | 923 | North Dakota | R-140 |
| Idaho | TN00003 | Ohio–VAP | CL0069 |
| Illinois | 200008 | Oklahoma | 9915 |
| Indiana | C-TN-01 | Oregon | TN200002 |
| Iowa | 364 | Pennsylvania | 68-02979 |
| Kansas | E-10277 | Rhode Island | LAO000356 |
| Kentucky [1 6] | KY90010 | South Carolina | 84004002 |
| Kentucky [2] | 16 | South Dakota | n/a |
| Louisiana | AI30792 | Tennessee [1 4] | 2006 |
| Louisiana | LA018 | Texas | T104704245-20-18 |
| Maine | TN00003 | Texas [5] | LAB0152 |
| Maryland | 324 | Utah | TN000032021-11 |
| Massachusetts | M-TN003 | Vermont | VT2006 |
| Michigan | 9958 | Virginia | 110033 |
| Minnesota | 047-999-395 | Washington | C847 |
| Mississippi | TN00003 | West Virginia | 233 |
| Missouri | 340 | Wisconsin | 998093910 |
| Montana | CERT0086 | Wyoming | A2LA |
| A2LA – ISO 17025 | 1461.01 | AIHA-LAP,LLC EMLAP | 100789 |
| A2LA – ISO 17025 [5] | 1461.02 | DOD | 1461.01 |
| Canada | 1461.01 | USDA | P330-15-00234 |
| EPA–Crypto | TN00003 | | |

[1] Drinking Water [2] Underground Storage Tanks [3] Aquatic Toxicity [4] Chemical/Microbiological [5] Mold [6] Wastewater n/a Accreditation not applicable

* Not all certifications held by the laboratory are applicable to the results reported in the attached report.

* Accreditation is only applicable to the test methods specified on each scope of accreditation held by Pace Analytical.

Company Name/Address:
**Rio Grande Resources Corp**

**219 S 2nd St**
**Raton, NM 87740**

Billing Information:
**Bruce Norquist**
**PO Box 1150**
**Grants , NM 87020**

Pres Chk

Report to: **Eric Roads** / Melissa Chalona

Email To: **eroads@enganalytics.com;tdavis@enganalytics.**

Project Description: **Mt Taylor**

City/State Collected: Grants, New Mexico

Please Circle: PT MT CT ET

Phone: **970-488-3111**

Client Project # 111360

Lab Project # **RIOGRAGNM-MTTAYLOR**

Collected by (print): Tyler Davis

Site/Facility ID #

P.O. #

Collected by (signature): Tyler Davis

Immediately Packed on Ice N ___ Y ✓

**Rush?** (Lab MUST be Notified)
___ Same Day ___ Five Day
___ Next Day ___ 5 Day (Rad Only)
___ Two Day ___ 10 Day (Rad Only)
___ Three Day

Date Results Needed

**Quote #**

Analysis / Container / Preservative

| Sample ID | Comp/Grab | Matrix * | Depth | Date | Time | No. of Cntrs | DROOROLVI 40mlAmb-HCl-BT | GRO 40mlAmb HCl | PAHSIMLVI 40mlAmb-NoPres-WT | SV8270PAH 4ozClr-NoPres | V8260BTEX 40mlAmb-HCl | V8260BTEX 40mlAmb/MeOH10ml/Syr | Remarks | Sample # (lab only) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MT-GW-TS-2760-DW9-100423-K3 | Grab | GW | 2760 | 10/4/2023 | 1004 | 9 | X | X | X | | X | | | -01 |
| MT-GW-TS-2760-DW9-100423-K2 | Grab | GW | 2760 | 10/4/23 | 1038 | 9 | X | X | X | | X | | | -02 |
| MT-GW-TS-2760-DW9-100423 | Grab | GW | 2760 | 10/4/23 | 12:00 | 9 | X | X | X | | X | | | -03 |
| MT-GW-TS-1655-DW9-100423-K3 | Grab | GW | 1655 | 10/4/23 | 12:30 | 9 | X | X | X | | X | | | -04 |
| MT-GW-TS-1655-DW9-100423- | Grab | GW | 1655 | 10/4/23 | 1334 | 9 | X | X | X | | X | | | -05 |
| MT-GW-TS-1144-DW9-100423-K3 | Grab | GW | 1144 | 10/4/23 | 1400 | 9 | X | X | X | | X | | | -06 |
| MT-GW-TS-1144-DW9-100423- | Grab | GW | 1144 | 10/4/23 | 1454 | 9 | X | X | X | | X | | | -07 |
| MT-GW-TS-2770-DW2-100523-K3 | Grab | GW | 2480 | 10/5/23 | 0843 | 9 | X | X | X | | X | | | -08 |
| MT-GW-TS-2770-DW2-100523-K2 | Grab | GW | 2480 | 10/5/23 | 0918 | 9 | X | X | X | | X | | | -09 |
| MT-GW-TS-2480-DW2-100523- | Grab | GW | 2480 | 10/5/23 | 1254 | 9 | X | X | X | | X | | | -10 |

* Matrix:
SS - Soil AIR - Air F - Filter
GW - Groundwater B - Bioassay
WW - WasteWater
DW - Drinking Water
OT - Other_____

**Remarks:**

pH _____ Temp _____

Flow _____ Other _____

Samples returned via:
__ UPS __ FedEx __ Courier _____

Tracking # 6841 8349 2835

Chain of Custody Page ___ of ___

Pace
PEOPLE ADVANCING SCIENCE

**MT JULIET, TN**

12065 Lebanon Rd Mount Juliet, TN 37122
Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Pace Terms and Conditions found at: https://info.pacelabs.com/hubfs/pas-standard-terms.pdf

SDG # 166499
B134

Acctnum: **RIOGRAGNM**
Template: **T238214**
Prelogin: **P1026344**
PM: **732 - Donna Eidson**
PB: NG 9122123

Shipped Via: **FedEX Ground**

Sample Receipt Checklist

| | | |
|---|---|---|
| COC Seal Present/Intact: | NP | Y N |
| COC Signed/Accurate: | | Y N |
| Bottles arrive intact: | | Y N |
| Correct bottles used: | | Y N |
| Sufficient volume sent: | | Y N |
| **If Applicable** | | |
| VOA Zero Headspace: | | Y N |
| Preservation Correct/Checked: | | Y N |
| RAD Screen <0.5 mR/hr: | | Y N |

| Relinquished by : (Signature) | Date: | Time: | Received by: (Signature) | Trip Blank Received: Yes / No HCL / MeoH TBR | |
|---|---|---|---|---|---|
| Tyler Davis | 10-6-23 | 1641 | | | |
| Relinquished by : (Signature) | Date: | Time: | Received by: (Signature) | Temp: °C Bottles Received: CCA8 3.3 4oz 3.3 | If preservation required by Login: Date/Time |
| Relinquished by : (Signature) | Date: | Time: | Received for lab by: (Signature) | Date: 10-7-23 Time: 9:00 | Hold: / Condition: NCF / OK |

# ANALYTICAL REPORT

October 31, 2023

Revised Report

## Rio Grande Resources Corp


| | |
|---|---|
| Sample Delivery Group: | L1666511 |
| Samples Received: | 10/13/2023 |
| Project Number: | 111360 |
| Description: | Mt Taylor |

Report To: Eric Roads
219 S 2nd St
Raton, NM 87740

Entire Report Reviewed By:

Tony Gibson
Project Manager

Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace Analytical National is performed per guidance provided in laboratory standard operating procedures ENV-SOP-MTJL-0067 and ENV-SOP-MTJL-0068. Where sampling conducted by the customer, results relate to the accuracy of the information provided, and as the samples are received.



Pace Analytical National
12065 Lebanon Rd Mount Juliet, TN 37122 615-758-5858 800-767-5859 www.pacenational.com

# TABLE OF CONTENTS


Cp: Cover Page 1

Tc: Table of Contents 2

Ss: Sample Summary 3

Cn: Case Narrative 5

Sr: Sample Results 6

MT-GW-TS-2849-DW11-101023-K2 L1666511-01 6

MT-GW-TS-2849-DW11-101023-K3 L1666511-02 7

MT-GW-TS-1750-DW11-101023 L1666511-03 8

MT-GW-TS-1100-DW11-101023-K3 L1666511-04 9

MT-GW-TS-1100-DW11-101023 L1666511-05 10

MT-GW-TS904-DW11-101023-K3 L1666511-06 11

MT-GW-TS904-DW11-101023 L1666511-07 12

MT-GW-TS1005-DW3-101123 L1666511-08 14

MT-GW-TS-896-DW3-101123 L1666511-09 15

MT-GW-TS-596-DW3-101123 L1666511-10 16

Qc: Quality Control Summary 17

Volatile Organic Compounds (GC) by Method 8015D/GRO 17

Volatile Organic Compounds (GC/MS) by Method 8260B 18

Semi-Volatile Organic Compounds (GC) by Method 8015 19

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM 21

Gl: Glossary of Terms 25

Al: Accreditations & Locations 26

Sc: Sample Chain of Custody 27

## MT-GW-TS-2849-DW11-101023-K2 L1666511-01 GW

Collected by: Tyler Davis | Collected date/time: 10/10/23 09:32 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 12:26 | 10/19/23 12:26 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 05:04 | 10/15/23 05:04 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2156771 | 1 | 10/20/23 07:57 | 10/24/23 15:25 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151859 | 1 | 10/17/23 08:57 | 10/17/23 15:12 | DSH | Mt. Juliet, TN |

## MT-GW-TS-2849-DW11-101023-K3 L1666511-02 GW

Collected by: Tyler Davis | Collected date/time: 10/10/23 10:18 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 12:46 | 10/19/23 12:46 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 05:25 | 10/15/23 05:25 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2156771 | 1 | 10/20/23 07:57 | 10/24/23 14:25 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151859 | 1 | 10/17/23 08:57 | 10/17/23 15:29 | DSH | Mt. Juliet, TN |

## MT-GW-TS-1750-DW11-101023 L1666511-03 GW

Collected by: Tyler Davis | Collected date/time: 10/10/23 12:09 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 13:05 | 10/19/23 13:05 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 05:46 | 10/15/23 05:46 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2156771 | 5 | 10/20/23 07:57 | 10/24/23 23:57 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151859 | 1 | 10/17/23 08:57 | 10/17/23 15:47 | DSH | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151859 | 50 | 10/17/23 08:57 | 10/24/23 00:27 | DSH | Mt. Juliet, TN |

## MT-GW-TS-1100-DW11-101023-K3 L1666511-04 GW

Collected by: Tyler Davis | Collected date/time: 10/10/23 12:45 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 13:25 | 10/19/23 13:25 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 06:07 | 10/15/23 06:07 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2156771 | 1 | 10/20/23 07:57 | 10/24/23 14:45 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151859 | 1 | 10/17/23 08:57 | 10/17/23 16:05 | DSH | Mt. Juliet, TN |

## MT-GW-TS-1100-DW11-101023 L1666511-05 GW

Collected by: Tyler Davis | Collected date/time: 10/10/23 13:42 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 13:44 | 10/19/23 13:44 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 06:28 | 10/15/23 06:28 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2156771 | 5 | 10/20/23 07:57 | 10/25/23 00:17 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151859 | 1 | 10/17/23 08:57 | 10/17/23 16:23 | DSH | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151859 | 50 | 10/17/23 08:57 | 10/24/23 00:46 | DSH | Mt. Juliet, TN |

## MT-GW-TS904-DW11-101023-K3 L1666511-06 GW

Collected by: Tyler Davis | Collected date/time: 10/10/23 14:10 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 14:03 | 10/19/23 14:03 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 06:49 | 10/15/23 06:49 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2156771 | 1 | 10/20/23 07:57 | 10/24/23 15:05 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151859 | 1 | 10/17/23 08:57 | 10/17/23 16:40 | DSH | Mt. Juliet, TN |

## MT-GW-TS904-DW11-101023 L1666511-07 GW

Collected by: Tyler Davis | Collected date/time: 10/10/23 15:30 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 14:23 | 10/19/23 14:23 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 07:10 | 10/15/23 07:10 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2154086 | 5 | 10/21/23 14:00 | 10/24/23 04:01 | MAA | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2154086 | 5 | 10/21/23 14:00 | 10/25/23 10:14 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151859 | 1 | 10/17/23 08:57 | 10/17/23 16:58 | DSH | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151859 | 50 | 10/17/23 08:57 | 10/24/23 01:06 | DSH | Mt. Juliet, TN |

## MT-GW-TS1005-DW3-101123 L1666511-08 GW

Collected by: Tyler Davis | Collected date/time: 10/11/23 14:00 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 14:42 | 10/19/23 14:42 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 07:30 | 10/15/23 07:30 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2154086 | 1 | 10/21/23 14:00 | 10/23/23 19:36 | MAA | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2154086 | 1 | 10/21/23 14:00 | 10/25/23 04:31 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2152447 | 1 | 10/17/23 16:45 | 10/18/23 12:00 | DSH | Mt. Juliet, TN |

## MT-GW-TS-896-DW3-101123 L1666511-09 GW

Collected by: Tyler Davis | Collected date/time: 10/11/23 15:52 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 15:01 | 10/19/23 15:01 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 07:51 | 10/15/23 07:51 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2154086 | 1 | 10/21/23 14:00 | 10/23/23 19:56 | MAA | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2154086 | 1 | 10/21/23 14:00 | 10/25/23 04:51 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2152447 | 1 | 10/17/23 16:45 | 10/18/23 12:18 | DSH | Mt. Juliet, TN |

## MT-GW-TS-596-DW3-101123 L1666511-10 GW

Collected by: Tyler Davis | Collected date/time: 10/11/23 17:41 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 15:21 | 10/19/23 15:21 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 08:12 | 10/15/23 08:12 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2154086 | 1 | 10/21/23 14:00 | 10/23/23 20:17 | MAA | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2154086 | 1 | 10/21/23 14:00 | 10/25/23 05:11 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2152447 | 1 | 10/17/23 16:45 | 10/18/23 12:35 | DSH | Mt. Juliet, TN |

# CASE NARRATIVE

All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.



Tony Gibson
Project Manager

## Report Revision History

Level II Report - Version 1: 10/25/23 16:01

## Project Narrative

Updated sample id for sample -10 - Tony Gibson 10/31/23

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 12:26 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *97.0* | | *78.0-120* | | *10/19/2023 12:26* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 05:04 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 05:04 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 05:04 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 05:04 | WG2151529 |
| *(S) Toluene-d8* | *114* | | *80.0-120* | | *10/15/2023 05:04* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *117* | | *77.0-126* | | *10/15/2023 05:04* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *103* | | *70.0-130* | | *10/15/2023 05:04* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/24/2023 15:25 | WG2156771 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/24/2023 15:25 | WG2156771 |
| *(S) o-Terphenyl* | *126* | | *52.0-156* | | *10/24/2023 15:25* | WG2156771 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Chrysene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/17/2023 15:12 | WG2151859 |
| Fluorene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Naphthalene | ND | | 0.000250 | 1 | 10/17/2023 15:12 | WG2151859 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| Pyrene | ND | | 0.0000500 | 1 | 10/17/2023 15:12 | WG2151859 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/17/2023 15:12 | WG2151859 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/17/2023 15:12 | WG2151859 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/17/2023 15:12 | WG2151859 |
| *(S) Nitrobenzene-d5* | *86.3* | | *31.0-160* | | *10/17/2023 15:12* | WG2151859 |
| *(S) 2-Fluorobiphenyl* | *85.8* | | *48.0-148* | | *10/17/2023 15:12* | WG2151859 |
| *(S) p-Terphenyl-d14* | *88.9* | | *37.0-146* | | *10/17/2023 15:12* | WG2151859 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 12:46 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *96.3* | | *78.0-120* | | *10/19/2023 12:46* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 05:25 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 05:25 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 05:25 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 05:25 | WG2151529 |
| *(S) Toluene-d8* | *112* | | *80.0-120* | | *10/15/2023 05:25* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *117* | | *77.0-126* | | *10/15/2023 05:25* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *102* | | *70.0-130* | | *10/15/2023 05:25* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/24/2023 14:25 | WG2156771 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/24/2023 14:25 | WG2156771 |
| *(S) o-Terphenyl* | *126* | | *52.0-156* | | *10/24/2023 14:25* | WG2156771 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Chrysene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/17/2023 15:29 | WG2151859 |
| Fluorene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Naphthalene | ND | | 0.000250 | 1 | 10/17/2023 15:29 | WG2151859 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| Pyrene | ND | | 0.0000500 | 1 | 10/17/2023 15:29 | WG2151859 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/17/2023 15:29 | WG2151859 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/17/2023 15:29 | WG2151859 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/17/2023 15:29 | WG2151859 |
| *(S) Nitrobenzene-d5* | *95.3* | | *31.0-160* | | *10/17/2023 15:29* | WG2151859 |
| *(S) 2-Fluorobiphenyl* | *97.4* | | *48.0-148* | | *10/17/2023 15:29* | WG2151859 |
| *(S) p-Terphenyl-d14* | *98.4* | | *37.0-146* | | *10/17/2023 15:29* | WG2151859 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 13:05 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *98.4* | | *78.0-120* | | *10/19/2023 13:05* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | 0.00137 | B | 0.00100 | 1 | 10/15/2023 05:46 | WG2151529 |
| Toluene | 0.00258 | | 0.00100 | 1 | 10/15/2023 05:46 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 05:46 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 05:46 | WG2151529 |
| *(S) Toluene-d8* | *110* | | *80.0-120* | | *10/15/2023 05:46* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *113* | | *77.0-126* | | *10/15/2023 05:46* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *102* | | *70.0-130* | | *10/15/2023 05:46* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 13.0 | | 0.500 | 5 | 10/24/2023 23:57 | WG2156771 |
| C28-C40 Oil Range | 7.42 | | 0.500 | 5 | 10/24/2023 23:57 | WG2156771 |
| *(S) o-Terphenyl* | *138* | | *52.0-156* | | *10/24/2023 23:57* | WG2156771 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Acenaphthene | 0.0105 | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Chrysene | ND | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/17/2023 15:47 | WG2151859 |
| Fluorene | 0.00238 | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Naphthalene | 0.550 | | 0.0125 | 50 | 10/24/2023 00:27 | WG2151859 |
| Phenanthrene | 0.000536 | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| Pyrene | 0.0000768 | | 0.0000500 | 1 | 10/17/2023 15:47 | WG2151859 |
| 1-Methylnaphthalene | ND | | 0.0125 | 50 | 10/24/2023 00:27 | WG2151859 |
| 2-Methylnaphthalene | 0.0155 | | 0.0125 | 50 | 10/24/2023 00:27 | WG2151859 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/17/2023 15:47 | WG2151859 |
| *(S) Nitrobenzene-d5* | *0.000* | J7 | *31.0-160* | | *10/24/2023 00:27* | WG2151859 |
| *(S) Nitrobenzene-d5* | *229* | J1 | *31.0-160* | | *10/17/2023 15:47* | WG2151859 |
| *(S) 2-Fluorobiphenyl* | *93.2* | | *48.0-148* | | *10/17/2023 15:47* | WG2151859 |
| *(S) 2-Fluorobiphenyl* | *122* | J7 | *48.0-148* | | *10/24/2023 00:27* | WG2151859 |
| *(S) p-Terphenyl-d14* | *83.2* | | *37.0-146* | | *10/17/2023 15:47* | WG2151859 |
| *(S) p-Terphenyl-d14* | *131* | J7 | *37.0-146* | | *10/24/2023 00:27* | WG2151859 |

**Sample Narrative:**

L1666511-03 WG2151859: Surrogate failure due to matrix interference

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 13:25 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *95.4* | | *78.0-120* | | *10/19/2023 13:25* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 06:07 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 06:07 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 06:07 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 06:07 | WG2151529 |
| *(S) Toluene-d8* | *114* | | *80.0-120* | | *10/15/2023 06:07* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *120* | | *77.0-126* | | *10/15/2023 06:07* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *103* | | *70.0-130* | | *10/15/2023 06:07* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/24/2023 14:45 | WG2156771 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/24/2023 14:45 | WG2156771 |
| *(S) o-Terphenyl* | *128* | | *52.0-156* | | *10/24/2023 14:45* | WG2156771 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Acenaphthene | 0.0000800 | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Chrysene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/17/2023 16:05 | WG2151859 |
| Fluorene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Naphthalene | 0.000258 | | 0.000250 | 1 | 10/17/2023 16:05 | WG2151859 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| Pyrene | ND | | 0.0000500 | 1 | 10/17/2023 16:05 | WG2151859 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/17/2023 16:05 | WG2151859 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/17/2023 16:05 | WG2151859 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/17/2023 16:05 | WG2151859 |
| *(S) Nitrobenzene-d5* | *102* | | *31.0-160* | | *10/17/2023 16:05* | WG2151859 |
| *(S) 2-Fluorobiphenyl* | *96.3* | | *48.0-148* | | *10/17/2023 16:05* | WG2151859 |
| *(S) p-Terphenyl-d14* | *97.9* | | *37.0-146* | | *10/17/2023 16:05* | WG2151859 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 13:44 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *98.9* | | *78.0-120* | | *10/19/2023 13:44* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | 0.00143 | B | 0.00100 | 1 | 10/15/2023 06:28 | WG2151529 |
| Toluene | 0.00280 | | 0.00100 | 1 | 10/15/2023 06:28 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 06:28 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 06:28 | WG2151529 |
| *(S) Toluene-d8* | *109* | | *80.0-120* | | *10/15/2023 06:28* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *114* | | *77.0-126* | | *10/15/2023 06:28* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *102* | | *70.0-130* | | *10/15/2023 06:28* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 13.1 | | 0.500 | 5 | 10/25/2023 00:17 | WG2156771 |
| C28-C40 Oil Range | 8.62 | | 0.500 | 5 | 10/25/2023 00:17 | WG2156771 |
| *(S) o-Terphenyl* | *126* | | *52.0-156* | | *10/25/2023 00:17* | WG2156771 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Acenaphthene | 0.00915 | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Chrysene | ND | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/17/2023 16:23 | WG2151859 |
| Fluorene | 0.00226 | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Naphthalene | 0.485 | | 0.0125 | 50 | 10/24/2023 00:46 | WG2151859 |
| Phenanthrene | 0.000609 | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| Pyrene | 0.0000600 | | 0.0000500 | 1 | 10/17/2023 16:23 | WG2151859 |
| 1-Methylnaphthalene | ND | | 0.0125 | 50 | 10/24/2023 00:46 | WG2151859 |
| 2-Methylnaphthalene | 0.0136 | | 0.0125 | 50 | 10/24/2023 00:46 | WG2151859 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/17/2023 16:23 | WG2151859 |
| *(S) Nitrobenzene-d5* | *0.000* | J7 | *31.0-160* | | *10/24/2023 00:46* | WG2151859 |
| *(S) Nitrobenzene-d5* | *226* | J1 | *31.0-160* | | *10/17/2023 16:23* | WG2151859 |
| *(S) 2-Fluorobiphenyl* | *91.6* | | *48.0-148* | | *10/17/2023 16:23* | WG2151859 |
| *(S) 2-Fluorobiphenyl* | *117* | J7 | *48.0-148* | | *10/24/2023 00:46* | WG2151859 |
| *(S) p-Terphenyl-d14* | *81.6* | | *37.0-146* | | *10/17/2023 16:23* | WG2151859 |
| *(S) p-Terphenyl-d14* | *124* | J7 | *37.0-146* | | *10/24/2023 00:46* | WG2151859 |

**Sample Narrative:**

L1666511-05 WG2151859: Surrogate failure due to matrix interference

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 14:03 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *96.8* | | *78.0-120* | | *10/19/2023 14:03* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 06:49 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 06:49 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 06:49 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 06:49 | WG2151529 |
| *(S) Toluene-d8* | *114* | | *80.0-120* | | *10/15/2023 06:49* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *123* | | *77.0-126* | | *10/15/2023 06:49* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *105* | | *70.0-130* | | *10/15/2023 06:49* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/24/2023 15:05 | WG2156771 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/24/2023 15:05 | WG2156771 |
| *(S) o-Terphenyl* | *131* | | *52.0-156* | | *10/24/2023 15:05* | WG2156771 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Acenaphthene | 0.000118 | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Chrysene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/17/2023 16:40 | WG2151859 |
| Fluorene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Naphthalene | 0.000424 | | 0.000250 | 1 | 10/17/2023 16:40 | WG2151859 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| Pyrene | ND | | 0.0000500 | 1 | 10/17/2023 16:40 | WG2151859 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/17/2023 16:40 | WG2151859 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/17/2023 16:40 | WG2151859 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/17/2023 16:40 | WG2151859 |
| *(S) Nitrobenzene-d5* | *94.2* | | *31.0-160* | | *10/17/2023 16:40* | WG2151859 |
| *(S) 2-Fluorobiphenyl* | *85.3* | | *48.0-148* | | *10/17/2023 16:40* | WG2151859 |
| *(S) p-Terphenyl-d14* | *87.9* | | *37.0-146* | | *10/17/2023 16:40* | WG2151859 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 14:23 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *98.9* | | *78.0-120* | | *10/19/2023 14:23* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 07:10 | WG2151529 |
| Toluene | 0.00185 | | 0.00100 | 1 | 10/15/2023 07:10 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 07:10 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 07:10 | WG2151529 |
| *(S) Toluene-d8* | *110* | | *80.0-120* | | *10/15/2023 07:10* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *112* | | *77.0-126* | | *10/15/2023 07:10* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *105* | | *70.0-130* | | *10/15/2023 07:10* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 12.5 | | 0.500 | 5 | 10/24/2023 04:01 | WG2154086 |
| C28-C40 Oil Range | 9.50 | | 0.500 | 5 | 10/25/2023 10:14 | WG2154086 |
| *(S) o-Terphenyl* | *133* | | *52.0-156* | | *10/25/2023 10:14* | WG2154086 |
| *(S) o-Terphenyl* | *184* | J1 | *52.0-156* | | *10/24/2023 04:01* | WG2154086 |

Sample Narrative:

L1666511-07 WG2154086: Surrogate failure due to matrix interference

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Acenaphthene | 0.00775 | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Chrysene | ND | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/17/2023 16:58 | WG2151859 |
| Fluorene | 0.00204 | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Naphthalene | 0.404 | | 0.0125 | 50 | 10/24/2023 01:06 | WG2151859 |
| Phenanthrene | 0.000577 | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| Pyrene | 0.0000516 | | 0.0000500 | 1 | 10/17/2023 16:58 | WG2151859 |
| 1-Methylnaphthalene | ND | | 0.0125 | 50 | 10/24/2023 01:06 | WG2151859 |
| 2-Methylnaphthalene | ND | | 0.0125 | 50 | 10/24/2023 01:06 | WG2151859 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/17/2023 16:58 | WG2151859 |
| *(S) Nitrobenzene-d5* | *0.000* | J7 | *31.0-160* | | *10/24/2023 01:06* | WG2151859 |
| *(S) Nitrobenzene-d5* | *0.000* | J2 | *31.0-160* | | *10/17/2023 16:58* | WG2151859 |
| *(S) 2-Fluorobiphenyl* | *91.1* | | *48.0-148* | | *10/17/2023 16:58* | WG2151859 |
| *(S) 2-Fluorobiphenyl* | *127* | J7 | *48.0-148* | | *10/24/2023 01:06* | WG2151859 |
| *(S) p-Terphenyl-d14* | *132* | J7 | *37.0-146* | | *10/24/2023 01:06* | WG2151859 |
| *(S) p-Terphenyl-d14* | *81.6* | | *37.0-146* | | *10/17/2023 16:58* | WG2151859 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result | Qualifier | RDL | Dilution | Analysis | Batch |
|---|---|---|---|---|---|---|
| | mg/l | | mg/l | | date / time | |

Sample Narrative:

L1666511-07 WG2151859: Surrogate failure due to matrix interference

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 14:42 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *97.5* | | *78.0-120* | | *10/19/2023 14:42* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 07:30 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 07:30 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 07:30 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 07:30 | WG2151529 |
| *(S) Toluene-d8* | *111* | | *80.0-120* | | *10/15/2023 07:30* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *119* | | *77.0-126* | | *10/15/2023 07:30* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *105* | | *70.0-130* | | *10/15/2023 07:30* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 2.30 | | 0.100 | 1 | 10/23/2023 19:36 | WG2154086 |
| C28-C40 Oil Range | 0.347 | | 0.100 | 1 | 10/25/2023 04:31 | WG2154086 |
| *(S) o-Terphenyl* | *142* | | *52.0-156* | | *10/23/2023 19:36* | WG2154086 |
| *(S) o-Terphenyl* | *139* | | *52.0-156* | | *10/25/2023 04:31* | WG2154086 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Acenaphthene | 0.000104 | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Chrysene | ND | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/18/2023 12:00 | WG2152447 |
| Fluorene | 0.000183 | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Naphthalene | ND | | 0.000250 | 1 | 10/18/2023 12:00 | WG2152447 |
| Phenanthrene | 0.000245 | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| Pyrene | ND | | 0.0000500 | 1 | 10/18/2023 12:00 | WG2152447 |
| 1-Methylnaphthalene | 0.000599 | | 0.000250 | 1 | 10/18/2023 12:00 | WG2152447 |
| 2-Methylnaphthalene | 0.000701 | | 0.000250 | 1 | 10/18/2023 12:00 | WG2152447 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/18/2023 12:00 | WG2152447 |
| *(S) Nitrobenzene-d5* | *116* | | *31.0-160* | | *10/18/2023 12:00* | WG2152447 |
| *(S) 2-Fluorobiphenyl* | *90.0* | | *48.0-148* | | *10/18/2023 12:00* | WG2152447 |
| *(S) p-Terphenyl-d14* | *85.5* | | *37.0-146* | | *10/18/2023 12:00* | WG2152447 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 15:01 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *98.1* | | *78.0-120* | | *10/19/2023 15:01* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 07:51 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 07:51 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 07:51 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 07:51 | WG2151529 |
| *(S) Toluene-d8* | *110* | | *80.0-120* | | *10/15/2023 07:51* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *116* | | *77.0-126* | | *10/15/2023 07:51* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *103* | | *70.0-130* | | *10/15/2023 07:51* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.620 | | 0.100 | 1 | 10/23/2023 19:56 | WG2154086 |
| C28-C40 Oil Range | 0.158 | | 0.100 | 1 | 10/25/2023 04:51 | WG2154086 |
| *(S) o-Terphenyl* | *136* | | *52.0-156* | | *10/25/2023 04:51* | WG2154086 |
| *(S) o-Terphenyl* | *142* | | *52.0-156* | | *10/23/2023 19:56* | WG2154086 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Chrysene | ND | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/18/2023 12:18 | WG2152447 |
| Fluorene | 0.0000566 | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Naphthalene | ND | | 0.000250 | 1 | 10/18/2023 12:18 | WG2152447 |
| Phenanthrene | 0.0000815 | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| Pyrene | ND | | 0.0000500 | 1 | 10/18/2023 12:18 | WG2152447 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/18/2023 12:18 | WG2152447 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/18/2023 12:18 | WG2152447 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/18/2023 12:18 | WG2152447 |
| *(S) Nitrobenzene-d5* | *112* | | *31.0-160* | | *10/18/2023 12:18* | WG2152447 |
| *(S) 2-Fluorobiphenyl* | *85.5* | | *48.0-148* | | *10/18/2023 12:18* | WG2152447 |
| *(S) p-Terphenyl-d14* | *79.5* | | *37.0-146* | | *10/18/2023 12:18* | WG2152447 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 15:21 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *98.4* | | *78.0-120* | | *10/19/2023 15:21* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 08:12 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 08:12 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 08:12 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 08:12 | WG2151529 |
| *(S) Toluene-d8* | *112* | | *80.0-120* | | *10/15/2023 08:12* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *120* | | *77.0-126* | | *10/15/2023 08:12* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *105* | | *70.0-130* | | *10/15/2023 08:12* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.37 | | 0.100 | 1 | 10/23/2023 20:17 | WG2154086 |
| C28-C40 Oil Range | 0.147 | | 0.100 | 1 | 10/25/2023 05:11 | WG2154086 |
| *(S) o-Terphenyl* | *143* | | *52.0-156* | | *10/25/2023 05:11* | WG2154086 |
| *(S) o-Terphenyl* | *140* | | *52.0-156* | | *10/23/2023 20:17* | WG2154086 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Acenaphthene | 0.000477 | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Chrysene | ND | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/18/2023 12:35 | WG2152447 |
| Fluorene | 0.00161 | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Naphthalene | 0.00134 | | 0.000250 | 1 | 10/18/2023 12:35 | WG2152447 |
| Phenanthrene | 0.00181 | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| Pyrene | ND | | 0.0000500 | 1 | 10/18/2023 12:35 | WG2152447 |
| 1-Methylnaphthalene | 0.0105 | | 0.000250 | 1 | 10/18/2023 12:35 | WG2152447 |
| 2-Methylnaphthalene | 0.0118 | | 0.000250 | 1 | 10/18/2023 12:35 | WG2152447 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/18/2023 12:35 | WG2152447 |
| *(S) Nitrobenzene-d5* | *63.5* | | *31.0-160* | | *10/18/2023 12:35* | WG2152447 |
| *(S) 2-Fluorobiphenyl* | *88.0* | | *48.0-148* | | *10/18/2023 12:35* | WG2152447 |
| *(S) p-Terphenyl-d14* | *83.5* | | *37.0-146* | | *10/18/2023 12:35* | WG2152447 |

## Method Blank (MB)

(MB) R3988703-2 10/19/23 11:38

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | U | | 0.0314 | 0.100 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *96.3* | | | *78.0-120* |

## Laboratory Control Sample (LCS)

(LCS) R3988703-1 10/19/23 10:52

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 5.78 | 105 | 72.0-127 | |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | *102* | *78.0-120* | |

## Method Blank (MB)

(MB) R3987957-3 10/15/23 04:42

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Benzene | 0.000316 | J | 0.0000941 | 0.00100 |
| Toluene | U | | 0.000278 | 0.00100 |
| Ethylbenzene | U | | 0.000137 | 0.00100 |
| Total Xylenes | U | | 0.000174 | 0.00300 |
| *(S) Toluene-d8* | *114* | | | *80.0-120* |
| *(S) 4-Bromofluorobenzene* | *117* | | | *77.0-126* |
| *(S) 1,2-Dichloroethane-d4* | *103* | | | *70.0-130* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3987957-1 10/15/23 03:18 • (LCSD) R3987957-2 10/15/23 03:39

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Benzene | 0.00500 | 0.00523 | 0.00493 | 105 | 98.6 | 70.0-123 | | | 5.91 | 20 |
| Toluene | 0.00500 | 0.00488 | 0.00468 | 97.6 | 93.6 | 79.0-120 | | | 4.18 | 20 |
| Ethylbenzene | 0.00500 | 0.00457 | 0.00447 | 91.4 | 89.4 | 79.0-123 | | | 2.21 | 20 |
| Total Xylenes | 0.0150 | 0.0141 | 0.0136 | 94.0 | 90.7 | 79.0-123 | | | 3.61 | 20 |
| *(S) Toluene-d8* | | | | *109* | *110* | *80.0-120* | | | | |
| *(S) 4-Bromofluorobenzene* | | | | *115* | *114* | *77.0-126* | | | | |
| *(S) 1,2-Dichloroethane-d4* | | | | *106* | *102* | *70.0-130* | | | | |

## Method Blank (MB)

(MB) R3990654-1 10/23/23 18:15

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| C10-C28 Diesel Range | U | | 0.0222 | 0.100 |
| C28-C40 Oil Range | U | | 0.0118 | 0.100 |
| *(S) o-Terphenyl* | *120* | | | *52.0-156* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3990654-2 10/23/23 18:35 • (LCSD) R3990654-3 10/23/23 18:56

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.50 | 1.36 | 1.52 | 90.7 | 101 | 50.0-150 | | | 11.1 | 20 |
| *(S) o-Terphenyl* | | | | *136* | *134* | *52.0-156* | | | | |

## Method Blank (MB)

(MB) R3990673-3 10/24/23 14:04

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| C10-C28 Diesel Range | U | | 0.0222 | 0.100 |
| C28-C40 Oil Range | U | | 0.0118 | 0.100 |
| *(S) o-Terphenyl* | *155* | | | *52.0-156* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3990673-1 10/24/23 13:24 • (LCSD) R3990673-2 10/24/23 13:44

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.50 | 1.81 | 1.54 | 121 | 103 | 50.0-150 | | | 16.1 | 20 |
| *(S) o-Terphenyl* | | | | *151* | *136* | *52.0-156* | | | | |

## Method Blank (MB)

(MB) R3988816-3 10/17/23 13:43

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Anthracene | U | | 0.0000190 | 0.0000500 |
| Acenaphthene | U | | 0.0000190 | 0.0000500 |
| Acenaphthylene | U | | 0.0000171 | 0.0000500 |
| Benzo(a)anthracene | U | | 0.0000203 | 0.0000500 |
| Benzo(a)pyrene | U | | 0.0000184 | 0.0000500 |
| Benzo(b)fluoranthene | U | | 0.0000168 | 0.0000500 |
| Benzo(g,h,i)perylene | U | | 0.0000184 | 0.0000500 |
| Benzo(k)fluoranthene | U | | 0.0000202 | 0.0000500 |
| Chrysene | U | | 0.0000179 | 0.0000500 |
| Dibenz(a,h)anthracene | U | | 0.0000160 | 0.0000500 |
| Fluoranthene | U | | 0.0000270 | 0.000100 |
| Fluorene | U | | 0.0000169 | 0.0000500 |
| Indeno(1,2,3-cd)pyrene | U | | 0.0000158 | 0.0000500 |
| Naphthalene | U | | 0.0000917 | 0.000250 |
| Phenanthrene | U | | 0.0000180 | 0.0000500 |
| Pyrene | U | | 0.0000169 | 0.0000500 |
| 1-Methylnaphthalene | U | | 0.0000687 | 0.000250 |
| 2-Methylnaphthalene | U | | 0.0000674 | 0.000250 |
| 2-Chloronaphthalene | U | | 0.0000682 | 0.000250 |
| *(S) Nitrobenzene-d5* | *96.0* | | | *31.0-160* |
| *(S) 2-Fluorobiphenyl* | *98.5* | | | *48.0-148* |
| *(S) p-Terphenyl-d14* | *94.0* | | | *37.0-146* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3988816-1 10/17/23 13:08 • (LCSD) R3988816-2 10/17/23 13:25

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Anthracene | 0.0100 | 0.00967 | 0.00934 | 96.7 | 93.4 | 67.0-150 | | | 3.47 | 20 |
| Acenaphthene | 0.0100 | 0.00911 | 0.00890 | 91.1 | 89.0 | 65.0-138 | | | 2.33 | 20 |
| Acenaphthylene | 0.0100 | 0.0102 | 0.00993 | 102 | 99.3 | 66.0-140 | | | 2.68 | 20 |
| Benzo(a)anthracene | 0.0100 | 0.0100 | 0.00960 | 100 | 96.0 | 61.0-140 | | | 4.08 | 20 |
| Benzo(a)pyrene | 0.0100 | 0.00967 | 0.00925 | 96.7 | 92.5 | 60.0-143 | | | 4.44 | 20 |
| Benzo(b)fluoranthene | 0.0100 | 0.00941 | 0.00897 | 94.1 | 89.7 | 58.0-141 | | | 4.79 | 20 |
| Benzo(g,h,i)perylene | 0.0100 | 0.00828 | 0.00792 | 82.8 | 79.2 | 52.0-153 | | | 4.44 | 20 |
| Benzo(k)fluoranthene | 0.0100 | 0.00907 | 0.00867 | 90.7 | 86.7 | 58.0-148 | | | 4.51 | 20 |
| Chrysene | 0.0100 | 0.0100 | 0.00961 | 100 | 96.1 | 64.0-144 | | | 3.98 | 20 |
| Dibenz(a,h)anthracene | 0.0100 | 0.00892 | 0.00864 | 89.2 | 86.4 | 52.0-155 | | | 3.19 | 20 |
| Fluoranthene | 0.0100 | 0.0103 | 0.00984 | 103 | 98.4 | 69.0-153 | | | 4.57 | 20 |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3988816-1 10/17/23 13:08 • (LCSD) R3988816-2 10/17/23 13:25

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Fluorene | 0.0100 | 0.0106 | 0.0101 | 106 | 101 | 64.0-136 | | | 4.83 | 20 |
| Indeno(1,2,3-cd)pyrene | 0.0100 | 0.00969 | 0.00924 | 96.9 | 92.4 | 54.0-153 | | | 4.75 | 20 |
| Naphthalene | 0.0100 | 0.00988 | 0.00966 | 98.8 | 96.6 | 61.0-137 | | | 2.25 | 20 |
| Phenanthrene | 0.0100 | 0.0101 | 0.00973 | 101 | 97.3 | 62.0-137 | | | 3.73 | 20 |
| Pyrene | 0.0100 | 0.0104 | 0.0102 | 104 | 102 | 60.0-142 | | | 1.94 | 20 |
| 1-Methylnaphthalene | 0.0100 | 0.0106 | 0.0104 | 106 | 104 | 66.0-142 | | | 1.90 | 20 |
| 2-Methylnaphthalene | 0.0100 | 0.00996 | 0.00980 | 99.6 | 98.0 | 62.0-136 | | | 1.62 | 20 |
| 2-Chloronaphthalene | 0.0100 | 0.00973 | 0.00954 | 97.3 | 95.4 | 64.0-140 | | | 1.97 | 20 |
| *(S) Nitrobenzene-d5* | | | | *101* | *95.0* | *31.0-160* | | | | |
| *(S) 2-Fluorobiphenyl* | | | | *103* | *96.5* | *48.0-148* | | | | |
| *(S) p-Terphenyl-d14* | | | | *90.0* | *82.5* | *37.0-146* | | | | |

## Method Blank (MB)

(MB) R3989711-3 10/18/23 10:14

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Anthracene | U | | 0.0000190 | 0.0000500 |
| Acenaphthene | U | | 0.0000190 | 0.0000500 |
| Acenaphthylene | U | | 0.0000171 | 0.0000500 |
| Benzo(a)anthracene | U | | 0.0000203 | 0.0000500 |
| Benzo(a)pyrene | U | | 0.0000184 | 0.0000500 |
| Benzo(b)fluoranthene | U | | 0.0000168 | 0.0000500 |
| Benzo(g,h,i)perylene | U | | 0.0000184 | 0.0000500 |
| Benzo(k)fluoranthene | U | | 0.0000202 | 0.0000500 |
| Chrysene | U | | 0.0000179 | 0.0000500 |
| Dibenz(a,h)anthracene | U | | 0.0000160 | 0.0000500 |
| Fluoranthene | U | | 0.0000270 | 0.000100 |
| Fluorene | U | | 0.0000169 | 0.0000500 |
| Indeno(1,2,3-cd)pyrene | U | | 0.0000158 | 0.0000500 |
| Naphthalene | U | | 0.0000917 | 0.000250 |
| Phenanthrene | U | | 0.0000180 | 0.0000500 |
| Pyrene | U | | 0.0000169 | 0.0000500 |
| 1-Methylnaphthalene | U | | 0.0000687 | 0.000250 |
| 2-Methylnaphthalene | U | | 0.0000674 | 0.000250 |
| 2-Chloronaphthalene | U | | 0.0000682 | 0.000250 |
| *(S) Nitrobenzene-d5* | *92.0* | | | *31.0-160* |
| *(S) 2-Fluorobiphenyl* | *93.0* | | | *48.0-148* |
| *(S) p-Terphenyl-d14* | *87.5* | | | *37.0-146* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3989711-1 10/18/23 09:39 • (LCSD) R3989711-2 10/18/23 09:57

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Anthracene | 0.00200 | 0.00171 | 0.00174 | 85.5 | 87.0 | 67.0-150 | | | 1.74 | 20 |
| Acenaphthene | 0.00200 | 0.00171 | 0.00178 | 85.5 | 89.0 | 65.0-138 | | | 4.01 | 20 |
| Acenaphthylene | 0.00200 | 0.00178 | 0.00183 | 89.0 | 91.5 | 66.0-140 | | | 2.77 | 20 |
| Benzo(a)anthracene | 0.00200 | 0.00172 | 0.00177 | 86.0 | 88.5 | 61.0-140 | | | 2.87 | 20 |
| Benzo(a)pyrene | 0.00200 | 0.00168 | 0.00173 | 84.0 | 86.5 | 60.0-143 | | | 2.93 | 20 |
| Benzo(b)fluoranthene | 0.00200 | 0.00174 | 0.00174 | 87.0 | 87.0 | 58.0-141 | | | 0.000 | 20 |
| Benzo(g,h,i)perylene | 0.00200 | 0.00160 | 0.00165 | 80.0 | 82.5 | 52.0-153 | | | 3.08 | 20 |
| Benzo(k)fluoranthene | 0.00200 | 0.00167 | 0.00168 | 83.5 | 84.0 | 58.0-148 | | | 0.597 | 20 |
| Chrysene | 0.00200 | 0.00178 | 0.00184 | 89.0 | 92.0 | 64.0-144 | | | 3.31 | 20 |
| Dibenz(a,h)anthracene | 0.00200 | 0.00156 | 0.00160 | 78.0 | 80.0 | 52.0-155 | | | 2.53 | 20 |
| Fluoranthene | 0.00200 | 0.00178 | 0.00184 | 89.0 | 92.0 | 69.0-153 | | | 3.31 | 20 |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3989711-1 10/18/23 09:39 • (LCSD) R3989711-2 10/18/23 09:57

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Fluorene | 0.00200 | 0.00181 | 0.00188 | 90.5 | 94.0 | 64.0-136 | | | 3.79 | 20 |
| Indeno(1,2,3-cd)pyrene | 0.00200 | 0.00158 | 0.00164 | 79.0 | 82.0 | 54.0-153 | | | 3.73 | 20 |
| Naphthalene | 0.00200 | 0.00183 | 0.00189 | 91.5 | 94.5 | 61.0-137 | | | 3.23 | 20 |
| Phenanthrene | 0.00200 | 0.00178 | 0.00185 | 89.0 | 92.5 | 62.0-137 | | | 3.86 | 20 |
| Pyrene | 0.00200 | 0.00183 | 0.00187 | 91.5 | 93.5 | 60.0-142 | | | 2.16 | 20 |
| 1-Methylnaphthalene | 0.00200 | 0.00182 | 0.00189 | 91.0 | 94.5 | 66.0-142 | | | 3.77 | 20 |
| 2-Methylnaphthalene | 0.00200 | 0.00187 | 0.00193 | 93.5 | 96.5 | 62.0-136 | | | 3.16 | 20 |
| 2-Chloronaphthalene | 0.00200 | 0.00176 | 0.00184 | 88.0 | 92.0 | 64.0-140 | | | 4.44 | 20 |
| *(S) Nitrobenzene-d5* | | | | *93.0* | *92.5* | *31.0-160* | | | | |
| *(S) 2-Fluorobiphenyl* | | | | *89.0* | *92.0* | *48.0-148* | | | | |
| *(S) p-Terphenyl-d14* | | | | *81.0* | *82.0* | *37.0-146* | | | | |

# GLOSSARY OF TERMS

## Guide to Reading and Understanding Your Laboratory Report

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.

Results Disclaimer - Information that may be provided by the customer, and contained within this report, include Permit Limits, Project Name, Sample ID, Sample Matrix, Sample Preservation, Field Blanks, Field Spikes, Field Duplicates, On-Site Data, Sampling Collection Dates/Times, and Sampling Location. Results relate to the accuracy of this information provided, and as the samples are received.

## Abbreviations and Definitions

| | |
|---|---|
| MDL | Method Detection Limit. |
| ND | Not detected at the Reporting Limit (or MDL where applicable). |
| RDL | Reported Detection Limit. |
| Rec. | Recovery. |
| RPD | Relative Percent Difference. |
| SDG | Sample Delivery Group. |
| (S) | Surrogate (Surrogate Standard) - Analytes added to every blank, sample, Laboratory Control Sample/Duplicate and Matrix Spike/Duplicate; used to evaluate analytical efficiency by measuring recovery. Surrogates are not expected to be detected in all environmental media. |
| U | Not detected at the Reporting Limit (or MDL where applicable). |
| Analyte | The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported. |
| Dilution | If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor. |
| Limits | These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges. |
| Qualifier | This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable. |
| Result | The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state “ND” (Not Detected) or “BDL” (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte. |
| Uncertainty (Radiochemistry) | Confidence level of 2 sigma. |
| Case Narrative (Cn) | A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report. |
| Quality Control Summary (Qc) | This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material. |
| Sample Chain of Custody (Sc) | This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis. |
| Sample Results (Sr) | This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported. |
| Sample Summary (Ss) | This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis. |

| Qualifier | Description |
|---|---|
| B | The same analyte is found in the associated blank. |
| J | The identification of the analyte is acceptable; the reported value is an estimate. |
| J1 | Surrogate recovery limits have been exceeded; values are outside upper control limits. |
| J2 | Surrogate recovery limits have been exceeded; values are outside lower control limits. |
| J7 | Surrogate recovery cannot be used for control limit evaluation due to dilution. |

## Pace Analytical National 12065 Lebanon Rd Mount Juliet, TN 37122

| | | | |
|---|---|---|---|
| Alabama | 40660 | Nebraska | NE-OS-15-05 |
| Alaska | 17-026 | Nevada | TN000032021-1 |
| Arizona | AZ0612 | New Hampshire | 2975 |
| Arkansas | 88-0469 | New Jersey–NELAP | TN002 |
| California | 2932 | New Mexico [1] | TN00003 |
| Colorado | TN00003 | New York | 11742 |
| Connecticut | PH-0197 | North Carolina | Env375 |
| Florida | E87487 | North Carolina [1] | DW21704 |
| Georgia | NELAP | North Carolina [3] | 41 |
| Georgia [1] | 923 | North Dakota | R-140 |
| Idaho | TN00003 | Ohio–VAP | CL0069 |
| Illinois | 200008 | Oklahoma | 9915 |
| Indiana | C-TN-01 | Oregon | TN200002 |
| Iowa | 364 | Pennsylvania | 68-02979 |
| Kansas | E-10277 | Rhode Island | LA000356 |
| Kentucky [1 6] | KY90010 | South Carolina | 84004002 |
| Kentucky [2] | 16 | South Dakota | n/a |
| Louisiana | AI30792 | Tennessee [1 4] | 2006 |
| Louisiana | LA018 | Texas | T104704245-20-18 |
| Maine | TN00003 | Texas [5] | LAB0152 |
| Maryland | 324 | Utah | TN000032021-11 |
| Massachusetts | M-TN003 | Vermont | VT2006 |
| Michigan | 9958 | Virginia | 110033 |
| Minnesota | 047-999-395 | Washington | C847 |
| Mississippi | TN00003 | West Virginia | 233 |
| Missouri | 340 | Wisconsin | 998093910 |
| Montana | CERT0086 | Wyoming | A2LA |
| A2LA – ISO 17025 | 1461.01 | AIHA-LAP,LLC EMLAP | 100789 |
| A2LA – ISO 17025 [5] | 1461.02 | DOD | 1461.01 |
| Canada | 1461.01 | USDA | P330-15-00234 |
| EPA–Crypto | TN00003 | | |

[1] Drinking Water [2] Underground Storage Tanks [3] Aquatic Toxicity [4] Chemical/Microbiological [5] Mold [6] Wastewater n/a Accreditation not applicable

* Not all certifications held by the laboratory are applicable to the results reported in the attached report.

* Accreditation is only applicable to the test methods specified on each scope of accreditation held by Pace Analytical.

Company Name/Address:
**Rio Grande Resources Corp**

**219 S 2nd St**
**Raton, NM 87740**

Billing Information:
**Bruce Norquist**
**PO Box 1150**
**Grants , NM 87020**

Pres Chk

Report to: **Eric Roads**

Email To: **eroads@enganalytics.com;tdavis@enganalytics.**

Project Description: **Mt Taylor**

City/State Collected: Grants, New Mexico

Please Circle: PT MT CT ET

Phone: **970-488-3111**

Client Project # 111360

Lab Project # **RIOGRAGNM-MTTAYLOR**

Collected by (print): Tyler Davis

Site/Facility ID #

P.O. #

Collected by (signature): Tyler Davis

Immediately Packed on Ice N ___ Y ✓

**Rush?** (Lab MUST Be Notified)
___ Same Day ___ Five Day
___ Next Day ___ 5 Day (Rad Only)
___ Two Day ___ 10 Day (Rad Only)
___ Three Day

Date Results Needed

Quote #

Analysis / Container / Preservative

Chain of Custody Page ___ of ___

Pace
PEOPLE ADVANCING SCIENCE

**MT JULIET, TN**

12065 Lebanon Rd Mount Juliet, TN 37122
Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Pace Terms and Conditions found at: https://info.pacelabs.com/hubfs/pas-standard-terms.pdf

SDG # L1dd0511

Tal 1130

Acctnum: **RIOGRAGNM**
Template: **T238214**
Prelogin: **P1026344**
PM: **732 - Donna Eidson**
PB: NG 9122123

Shipped Via: **FedEX Ground**

| Sample ID | Comp/Grab | Matrix * | Depth | Date | Time | No. of Cntrs | DROORDLVI 40mlAmb-HCl-BT | GRO 40mlAmb HCl | PAHSIMLVI 40mlAmb-NoPres-WT | SV8270PAH 4ozClr-NoPres | V8260BTEX 40mlAmb-HCl | V8260BTEX 40mlAmb/MeOH10ml/Syr | | | | | Remarks | Sample # (lab only) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MT-GW-TS-2849-DW11-101023-K2 | Grab | GW | 2849 | 10-10-23 | 9:32 | 9 | X | X | X | | X | | | | | | | -01 |
| MT-GW-TS-2849-DW11-101023-K3 | Grab | GW | 2849 | 10-10-23 | 1018 | 9 | X | X | X | | X | | | | | | | -02 |
| MT-GW-TS-1750-DW11-101023 | Grab | GW | 1750 | 10-10-23 | 1209 | 9 | X | X | X | | X | | | | | | | -03 |
| MT-GW-TS-1100-DW11-101023-K3 | Grab | GW | 1100 | 10-10-23 | 1245 | 9 | X | X | X | | X | | | | | | | -04 |
| MT-GW-TS1100-DW11-101023 | Grab | GW | 1100 | 10-10-23 | 1342 | 9 | X | X | X | | X | | | | | | | -05 |
| MT-GW-TS904-DW11-101023-K3 | Grab | GW | 903.6 | 10-10-23 | 1410 | 9 | X | X | X | | X | | | | | | | -06 |
| MT-GW-TS904-DW11-10-10-23- | Grab | GW | 903.6 | 10-10-23 | 1530 | 9 | X | X | X | | X | | | | | | | -07 |
| MT-GW-TS1005-DW3-101123 | Grab | GW | 1005 | 10-11-23 | 1400 | 9 | X | X | X | | X | | | | | | | -08 |
| MT-GW-TS-896-DW3-101123 | Grab | GW | 896 | 10-11-23 | 1552 | 9 | X | X | X | | X | | | | | | | -09 |
| MT-GW-TS-596-DW3-101123 | Grab | GW | 596 | 10-11-23 | 1741 | 9 | X | X | X | | X | | | | | | | -10 |

* Matrix:
**SS** - Soil **AIR** - Air **F** - Filter
**GW** - Groundwater **B** - Bioassay
**WW** - WasteWater
**DW** - Drinking Water
**OT** - Other_____

**Remarks:** Some samples have effervescence that caused air bubbles after bottle was sealed.

Red cooler

pH _____ Temp _____

Flow _____ Other _____

Samples returned via:
__ UPS __ FedEx __ Courier _____

Tracking # 6841 8349 2607

Sample Receipt Checklist

| | | |
|---|---|---|
| COC Seal Present/Intact: | NP | Y N |
| COC Signed/Accurate: | | Y N |
| Bottles arrive intact: | | Y N |
| Correct bottles used: | | Y N |
| Sufficient volume sent: | | Y N |
| If Applicable | | |
| VOA Zero Headspace: | | Y N |
| Preservation Correct/Checked: | | Y N |
| RAD Screen <0.5 mR/hr: | | Y N |

| Relinquished by : (Signature) | Date: | Time: | Received by: (Signature) | Trip Blank Received: Yes / No HCl / MeoH TBR | If preservation required by Login: Date/Time |
|---|---|---|---|---|---|
| [signature] | 10-12-2023 | 1725 | | 1 | |
| Relinquished by : (Signature) | Date: | Time: | Received by: (Signature) | Temp: °C Bottles Received: | |
| | | | CCAB30+0=3.0 | 90 | |
| Relinquished by : (Signature) | Date: | Time: | Received for lab by: (Signature) | Date: | Time: |
| | | | [signature] | 10.12.23 | 0900 |

Hold: | Condition: NCF / OK

# ANALYTICAL REPORT

October 27, 2023



## Rio Grande Resources Corp


| | |
|---|---|
| Sample Delivery Group: | L1666516 |
| Samples Received: | 10/13/2023 |
| Project Number: | 111360 |
| Description: | Mt Taylor |

Report To: Eric Roads
219 S 2nd St
Raton, NM 87740

Entire Report Reviewed By:

John Hawkins
Project Manager

Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace Analytical National is performed per guidance provided in laboratory standard operating procedures ENV-SOP-MTJL-0067 and ENV-SOP-MTJL-0068. Where sampling conducted by the customer, results relate to the accuracy of the information provided, and as the samples are received.



Pace Analytical National
12065 Lebanon Rd Mount Juliet, TN 37122 615-758-5858 800-767-5859 www.pacenational.com

# TABLE OF CONTENTS


Cp: Cover Page 1

Tc: Table of Contents 2

Ss: Sample Summary 3

Cn: Case Narrative 5

Sr: Sample Results 6

MT-GW-PD-DW6-101023 L1666516-01 6

MT-GW-PD-DW2A-101123 L1666516-02 7

MT-GW-TS-1005-DW3-101123-K3 L1666516-03 8

MT-GW-TS-1005-DW3-101123-K2 L1666516-04 9

MT-GW-TS-1005-DW3-101123-K1 L1666516-05 10

MT-GW-TS-886-DW-101123-K3 L1666516-06 11

MT-GW-TS-596-DW3-101123-K3 L1666516-07 12

Qc: Quality Control Summary 13

Volatile Organic Compounds (GC) by Method 8015D/GRO 13

Volatile Organic Compounds (GC/MS) by Method 8260B 14

Semi-Volatile Organic Compounds (GC) by Method 8015 15

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM 17

Gl: Glossary of Terms 21

Al: Accreditations & Locations 22

Sc: Sample Chain of Custody 23

## MT-GW-PD-DW6-101023 L1666516-01 GW

Collected by: Tyler Davis | Collected date/time: 10/10/23 16:07 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2155551 | 1 | 10/21/23 15:03 | 10/21/23 15:03 | ACG | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2152373 | 1 | 10/16/23 22:01 | 10/16/23 22:01 | JBE | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2154087 | 1 | 10/23/23 18:32 | 10/25/23 00:07 | DMG | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151859 | 1 | 10/17/23 08:57 | 10/17/23 17:16 | DSH | Mt. Juliet, TN |

## MT-GW-PD-DW2A-101123 L1666516-02 GW

Collected by: Tyler Davis | Collected date/time: 10/11/23 08:45 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2155551 | 1 | 10/21/23 15:26 | 10/21/23 15:26 | ACG | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2152373 | 1 | 10/16/23 22:20 | 10/16/23 22:20 | JBE | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2156704 | 1 | 10/25/23 15:02 | 10/26/23 20:35 | DMG | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2152447 | 1 | 10/17/23 16:45 | 10/18/23 12:53 | DSH | Mt. Juliet, TN |

## MT-GW-TS-1005-DW3-101123-K3 L1666516-03 GW

Collected by: Tyler Davis | Collected date/time: 10/11/23 10:41 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2155551 | 1 | 10/21/23 15:50 | 10/21/23 15:50 | ACG | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2152373 | 1 | 10/16/23 22:39 | 10/16/23 22:39 | JBE | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2156704 | 1 | 10/25/23 15:02 | 10/26/23 20:55 | DMG | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2152447 | 1 | 10/17/23 16:45 | 10/18/23 13:11 | DSH | Mt. Juliet, TN |

## MT-GW-TS-1005-DW3-101123-K2 L1666516-04 GW

Collected by: Tyler Davis | Collected date/time: 10/11/23 09:33 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2155551 | 1 | 10/21/23 16:13 | 10/21/23 16:13 | ACG | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2152373 | 1 | 10/16/23 22:59 | 10/16/23 22:59 | JBE | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2156704 | 1 | 10/25/23 15:02 | 10/26/23 21:15 | DMG | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2152447 | 1 | 10/17/23 16:45 | 10/18/23 13:28 | DSH | Mt. Juliet, TN |

## MT-GW-TS-1005-DW3-101123-K1 L1666516-05 GW

Collected by: Tyler Davis | Collected date/time: 10/11/23 14:00 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2155551 | 1 | 10/21/23 16:36 | 10/21/23 16:36 | ACG | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2152373 | 1 | 10/16/23 23:18 | 10/16/23 23:18 | JBE | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2156704 | 1 | 10/25/23 15:02 | 10/26/23 21:36 | DMG | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2152447 | 1 | 10/17/23 16:45 | 10/18/23 13:46 | DSH | Mt. Juliet, TN |

## MT-GW-TS-886-DW-101123-K3 L1666516-06 GW

Collected by: Tyler Davis | Collected date/time: 10/11/23 14:45 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2155551 | 1 | 10/21/23 16:59 | 10/21/23 16:59 | ACG | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2152373 | 1 | 10/16/23 23:38 | 10/16/23 23:38 | JBE | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2156704 | 1 | 10/25/23 15:02 | 10/26/23 21:56 | DMG | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2152447 | 1 | 10/17/23 16:45 | 10/18/23 14:04 | DSH | Mt. Juliet, TN |

# SAMPLE SUMMARY

## MT-GW-TS-596-DW3-101123-K3 L1666516-07 GW

Collected by: Tyler Davis
Collected date/time: 10/11/23 16:26
Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2155551 | 1 | 10/21/23 17:22 | 10/21/23 17:22 | ACG | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2152373 | 1 | 10/16/23 23:56 | 10/16/23 23:56 | JBE | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2156704 | 1 | 10/25/23 15:02 | 10/26/23 22:16 | DMG | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2152447 | 1 | 10/17/23 16:45 | 10/18/23 14:21 | DSH | Mt. Juliet, TN |

# CASE NARRATIVE

All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.



John Hawkins
Project Manager

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/21/2023 15:03 | WG2155551 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *101* | | *78.0-120* | | *10/21/2023 15:03* | WG2155551 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/16/2023 22:01 | WG2152373 |
| Toluene | ND | | 0.00100 | 1 | 10/16/2023 22:01 | WG2152373 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/16/2023 22:01 | WG2152373 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/16/2023 22:01 | WG2152373 |
| *(S) Toluene-d8* | *79.1* | J2 | *80.0-120* | | *10/16/2023 22:01* | WG2152373 |
| *(S) 4-Bromofluorobenzene* | *103* | | *77.0-126* | | *10/16/2023 22:01* | WG2152373 |
| *(S) 1,2-Dichloroethane-d4* | *138* | J1 | *70.0-130* | | *10/16/2023 22:01* | WG2152373 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.115 | | 0.100 | 1 | 10/25/2023 00:07 | WG2154087 |
| C28-C40 Oil Range | 0.366 | | 0.100 | 1 | 10/25/2023 00:07 | WG2154087 |
| *(S) o-Terphenyl* | *71.0* | | *52.0-156* | | *10/25/2023 00:07* | WG2154087 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Chrysene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/17/2023 17:16 | WG2151859 |
| Fluorene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Naphthalene | ND | | 0.000250 | 1 | 10/17/2023 17:16 | WG2151859 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| Pyrene | ND | | 0.0000500 | 1 | 10/17/2023 17:16 | WG2151859 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/17/2023 17:16 | WG2151859 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/17/2023 17:16 | WG2151859 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/17/2023 17:16 | WG2151859 |
| *(S) Nitrobenzene-d5* | *103* | | *31.0-160* | | *10/17/2023 17:16* | WG2151859 |
| *(S) 2-Fluorobiphenyl* | *95.8* | | *48.0-148* | | *10/17/2023 17:16* | WG2151859 |
| *(S) p-Terphenyl-d14* | *93.7* | | *37.0-146* | | *10/17/2023 17:16* | WG2151859 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/21/2023 15:26 | WG2155551 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *101* | | *78.0-120* | | *10/21/2023 15:26* | WG2155551 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/16/2023 22:20 | WG2152373 |
| Toluene | ND | | 0.00100 | 1 | 10/16/2023 22:20 | WG2152373 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/16/2023 22:20 | WG2152373 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/16/2023 22:20 | WG2152373 |
| *(S) Toluene-d8* | *80.4* | | *80.0-120* | | *10/16/2023 22:20* | WG2152373 |
| *(S) 4-Bromofluorobenzene* | *103* | | *77.0-126* | | *10/16/2023 22:20* | WG2152373 |
| *(S) 1,2-Dichloroethane-d4* | *115* | | *70.0-130* | | *10/16/2023 22:20* | WG2152373 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/26/2023 20:35 | WG2156704 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/26/2023 20:35 | WG2156704 |
| *(S) o-Terphenyl* | *96.5* | | *52.0-156* | | *10/26/2023 20:35* | WG2156704 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Chrysene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/18/2023 12:53 | WG2152447 |
| Fluorene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Naphthalene | ND | | 0.000250 | 1 | 10/18/2023 12:53 | WG2152447 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| Pyrene | ND | | 0.0000500 | 1 | 10/18/2023 12:53 | WG2152447 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/18/2023 12:53 | WG2152447 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/18/2023 12:53 | WG2152447 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/18/2023 12:53 | WG2152447 |
| *(S) Nitrobenzene-d5* | *89.0* | | *31.0-160* | | *10/18/2023 12:53* | WG2152447 |
| *(S) 2-Fluorobiphenyl* | *90.0* | | *48.0-148* | | *10/18/2023 12:53* | WG2152447 |
| *(S) p-Terphenyl-d14* | *85.0* | | *37.0-146* | | *10/18/2023 12:53* | WG2152447 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/21/2023 15:50 | WG2155551 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *101* | | *78.0-120* | | *10/21/2023 15:50* | WG2155551 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/16/2023 22:39 | WG2152373 |
| Toluene | ND | | 0.00100 | 1 | 10/16/2023 22:39 | WG2152373 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/16/2023 22:39 | WG2152373 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/16/2023 22:39 | WG2152373 |
| *(S) Toluene-d8* | *99.1* | | *80.0-120* | | *10/16/2023 22:39* | WG2152373 |
| *(S) 4-Bromofluorobenzene* | *119* | | *77.0-126* | | *10/16/2023 22:39* | WG2152373 |
| *(S) 1,2-Dichloroethane-d4* | *141* | J1 | *70.0-130* | | *10/16/2023 22:39* | WG2152373 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/26/2023 20:55 | WG2156704 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/26/2023 20:55 | WG2156704 |
| *(S) o-Terphenyl* | *112* | | *52.0-156* | | *10/26/2023 20:55* | WG2156704 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Chrysene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/18/2023 13:11 | WG2152447 |
| Fluorene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Naphthalene | ND | | 0.000250 | 1 | 10/18/2023 13:11 | WG2152447 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| Pyrene | ND | | 0.0000500 | 1 | 10/18/2023 13:11 | WG2152447 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/18/2023 13:11 | WG2152447 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/18/2023 13:11 | WG2152447 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/18/2023 13:11 | WG2152447 |
| *(S) Nitrobenzene-d5* | *94.5* | | *31.0-160* | | *10/18/2023 13:11* | WG2152447 |
| *(S) 2-Fluorobiphenyl* | *92.5* | | *48.0-148* | | *10/18/2023 13:11* | WG2152447 |
| *(S) p-Terphenyl-d14* | *89.0* | | *37.0-146* | | *10/18/2023 13:11* | WG2152447 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/21/2023 16:13 | WG2155551 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *101* | | *78.0-120* | | *10/21/2023 16:13* | WG2155551 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/16/2023 22:59 | WG2152373 |
| Toluene | ND | | 0.00100 | 1 | 10/16/2023 22:59 | WG2152373 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/16/2023 22:59 | WG2152373 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/16/2023 22:59 | WG2152373 |
| *(S) Toluene-d8* | *94.6* | | *80.0-120* | | *10/16/2023 22:59* | WG2152373 |
| *(S) 4-Bromofluorobenzene* | *103* | | *77.0-126* | | *10/16/2023 22:59* | WG2152373 |
| *(S) 1,2-Dichloroethane-d4* | *129* | | *70.0-130* | | *10/16/2023 22:59* | WG2152373 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/26/2023 21:15 | WG2156704 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/26/2023 21:15 | WG2156704 |
| *(S) o-Terphenyl* | *103* | | *52.0-156* | | *10/26/2023 21:15* | WG2156704 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Chrysene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/18/2023 13:28 | WG2152447 |
| Fluorene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Naphthalene | ND | | 0.000250 | 1 | 10/18/2023 13:28 | WG2152447 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| Pyrene | ND | | 0.0000500 | 1 | 10/18/2023 13:28 | WG2152447 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/18/2023 13:28 | WG2152447 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/18/2023 13:28 | WG2152447 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/18/2023 13:28 | WG2152447 |
| *(S) Nitrobenzene-d5* | *90.0* | | *31.0-160* | | *10/18/2023 13:28* | WG2152447 |
| *(S) 2-Fluorobiphenyl* | *91.5* | | *48.0-148* | | *10/18/2023 13:28* | WG2152447 |
| *(S) p-Terphenyl-d14* | *87.5* | | *37.0-146* | | *10/18/2023 13:28* | WG2152447 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/21/2023 16:36 | WG2155551 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *102* | | *78.0-120* | | *10/21/2023 16:36* | WG2155551 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/16/2023 23:18 | WG2152373 |
| Toluene | ND | | 0.00100 | 1 | 10/16/2023 23:18 | WG2152373 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/16/2023 23:18 | WG2152373 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/16/2023 23:18 | WG2152373 |
| *(S) Toluene-d8* | *86.3* | | *80.0-120* | | *10/16/2023 23:18* | WG2152373 |
| *(S) 4-Bromofluorobenzene* | *115* | | *77.0-126* | | *10/16/2023 23:18* | WG2152373 |
| *(S) 1,2-Dichloroethane-d4* | *123* | | *70.0-130* | | *10/16/2023 23:18* | WG2152373 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.70 | | 0.100 | 1 | 10/26/2023 21:36 | WG2156704 |
| C28-C40 Oil Range | 0.156 | | 0.100 | 1 | 10/26/2023 21:36 | WG2156704 |
| *(S) o-Terphenyl* | *129* | | *52.0-156* | | *10/26/2023 21:36* | WG2156704 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Acenaphthene | 0.000111 | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Chrysene | ND | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/18/2023 13:46 | WG2152447 |
| Fluorene | 0.000180 | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Naphthalene | ND | | 0.000250 | 1 | 10/18/2023 13:46 | WG2152447 |
| Phenanthrene | 0.000252 | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| Pyrene | ND | | 0.0000500 | 1 | 10/18/2023 13:46 | WG2152447 |
| 1-Methylnaphthalene | 0.000580 | | 0.000250 | 1 | 10/18/2023 13:46 | WG2152447 |
| 2-Methylnaphthalene | 0.000680 | | 0.000250 | 1 | 10/18/2023 13:46 | WG2152447 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/18/2023 13:46 | WG2152447 |
| *(S) Nitrobenzene-d5* | *116* | | *31.0-160* | | *10/18/2023 13:46* | WG2152447 |
| *(S) 2-Fluorobiphenyl* | *86.5* | | *48.0-148* | | *10/18/2023 13:46* | WG2152447 |
| *(S) p-Terphenyl-d14* | *83.5* | | *37.0-146* | | *10/18/2023 13:46* | WG2152447 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/21/2023 16:59 | WG2155551 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *101* | | *78.0-120* | | *10/21/2023 16:59* | WG2155551 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/16/2023 23:38 | WG2152373 |
| Toluene | ND | | 0.00100 | 1 | 10/16/2023 23:38 | WG2152373 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/16/2023 23:38 | WG2152373 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/16/2023 23:38 | WG2152373 |
| *(S) Toluene-d8* | *91.4* | | *80.0-120* | | *10/16/2023 23:38* | WG2152373 |
| *(S) 4-Bromofluorobenzene* | *87.4* | | *77.0-126* | | *10/16/2023 23:38* | WG2152373 |
| *(S) 1,2-Dichloroethane-d4* | *110* | | *70.0-130* | | *10/16/2023 23:38* | WG2152373 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/26/2023 21:56 | WG2156704 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/26/2023 21:56 | WG2156704 |
| *(S) o-Terphenyl* | *116* | | *52.0-156* | | *10/26/2023 21:56* | WG2156704 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Chrysene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/18/2023 14:04 | WG2152447 |
| Fluorene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Naphthalene | ND | | 0.000250 | 1 | 10/18/2023 14:04 | WG2152447 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| Pyrene | ND | | 0.0000500 | 1 | 10/18/2023 14:04 | WG2152447 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/18/2023 14:04 | WG2152447 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/18/2023 14:04 | WG2152447 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/18/2023 14:04 | WG2152447 |
| *(S) Nitrobenzene-d5* | *87.0* | | *31.0-160* | | *10/18/2023 14:04* | WG2152447 |
| *(S) 2-Fluorobiphenyl* | *88.5* | | *48.0-148* | | *10/18/2023 14:04* | WG2152447 |
| *(S) p-Terphenyl-d14* | *83.0* | | *37.0-146* | | *10/18/2023 14:04* | WG2152447 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/21/2023 17:22 | WG2155551 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *102* | | *78.0-120* | | *10/21/2023 17:22* | WG2155551 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/16/2023 23:56 | WG2152373 |
| Toluene | ND | | 0.00100 | 1 | 10/16/2023 23:56 | WG2152373 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/16/2023 23:56 | WG2152373 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/16/2023 23:56 | WG2152373 |
| *(S) Toluene-d8* | *90.2* | | *80.0-120* | | *10/16/2023 23:56* | WG2152373 |
| *(S) 4-Bromofluorobenzene* | *98.9* | | *77.0-126* | | *10/16/2023 23:56* | WG2152373 |
| *(S) 1,2-Dichloroethane-d4* | *121* | | *70.0-130* | | *10/16/2023 23:56* | WG2152373 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | | 0.100 | 1 | 10/26/2023 22:16 | WG2156704 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/26/2023 22:16 | WG2156704 |
| *(S) o-Terphenyl* | *117* | | *52.0-156* | | *10/26/2023 22:16* | WG2156704 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Chrysene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/18/2023 14:21 | WG2152447 |
| Fluorene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Naphthalene | ND | | 0.000250 | 1 | 10/18/2023 14:21 | WG2152447 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| Pyrene | ND | | 0.0000500 | 1 | 10/18/2023 14:21 | WG2152447 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/18/2023 14:21 | WG2152447 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/18/2023 14:21 | WG2152447 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/18/2023 14:21 | WG2152447 |
| *(S) Nitrobenzene-d5* | *89.5* | | *31.0-160* | | *10/18/2023 14:21* | WG2152447 |
| *(S) 2-Fluorobiphenyl* | *89.0* | | *48.0-148* | | *10/18/2023 14:21* | WG2152447 |
| *(S) p-Terphenyl-d14* | *85.0* | | *37.0-146* | | *10/18/2023 14:21* | WG2152447 |

## Method Blank (MB)

(MB) R3990324-3 10/21/23 13:43

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | U | | 0.0314 | 0.100 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *101* | | | *78.0-120* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3990324-1 10/21/23 12:34 • (LCSD) R3990324-2 10/21/23 12:57

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 5.42 | 5.40 | 98.5 | 98.2 | 72.0-127 | | | 0.370 | 20 |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | | *104* | *104* | *78.0-120* | | | | |

## Method Blank (MB)

(MB) R3988570-3 10/16/23 21:07

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Benzene | U | | 0.0000941 | 0.00100 |
| Toluene | U | | 0.000278 | 0.00100 |
| Ethylbenzene | U | | 0.000137 | 0.00100 |
| Total Xylenes | U | | 0.000174 | 0.00300 |
| *(S) Toluene-d8* | *86.7* | | | *80.0-120* |
| *(S) 4-Bromofluorobenzene* | *104* | | | *77.0-126* |
| *(S) 1,2-Dichloroethane-d4* | *127* | | | *70.0-130* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3988570-1 10/16/23 19:49 • (LCSD) R3988570-2 10/16/23 20:09

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Benzene | 0.00500 | 0.00574 | 0.00552 | 115 | 110 | 70.0-123 | | | 3.91 | 20 |
| Toluene | 0.00500 | 0.00563 | 0.00513 | 113 | 103 | 79.0-120 | | | 9.29 | 20 |
| Ethylbenzene | 0.00500 | 0.00507 | 0.00500 | 101 | 100 | 79.0-123 | | | 1.39 | 20 |
| Total Xylenes | 0.0150 | 0.0176 | 0.0156 | 117 | 104 | 79.0-123 | | | 12.0 | 20 |
| *(S) Toluene-d8* | | | | *105* | *94.8* | *80.0-120* | | | | |
| *(S) 4-Bromofluorobenzene* | | | | *122* | *106* | *77.0-126* | | | | |
| *(S) 1,2-Dichloroethane-d4* | | | | *118* | *128* | *70.0-130* | | | | |

## Method Blank (MB)

(MB) R3990674-1 10/24/23 11:49

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| C10-C28 Diesel Range | U | | 0.0222 | 0.100 |
| C28-C40 Oil Range | U | | 0.0118 | 0.100 |
| *(S) o-Terphenyl* | *84.5* | | | *52.0-156* |

## Laboratory Control Sample (LCS)

(LCS) R3990674-2 10/24/23 12:09

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.50 | 1.19 | 79.3 | 50.0-150 | |
| *(S) o-Terphenyl* | | | *86.5* | *52.0-156* | |

## Method Blank (MB)

(MB) R3991767-1 10/26/23 09:55

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| C10-C28 Diesel Range | U | | 0.0222 | 0.100 |
| C28-C40 Oil Range | U | | 0.0118 | 0.100 |
| *(S) o-Terphenyl* | *113* | | | *52.0-156* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3991767-2 10/26/23 10:15 • (LCSD) R3991767-3 10/26/23 10:36

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.50 | 1.43 | 1.45 | 95.3 | 96.7 | 50.0-150 | | | 1.39 | 20 |
| *(S) o-Terphenyl* | | | | *128* | *126* | *52.0-156* | | | | |

## Method Blank (MB)

(MB) R3988816-3 10/17/23 13:43

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Anthracene | U | | 0.0000190 | 0.0000500 |
| Acenaphthene | U | | 0.0000190 | 0.0000500 |
| Acenaphthylene | U | | 0.0000171 | 0.0000500 |
| Benzo(a)anthracene | U | | 0.0000203 | 0.0000500 |
| Benzo(a)pyrene | U | | 0.0000184 | 0.0000500 |
| Benzo(b)fluoranthene | U | | 0.0000168 | 0.0000500 |
| Benzo(g,h,i)perylene | U | | 0.0000184 | 0.0000500 |
| Benzo(k)fluoranthene | U | | 0.0000202 | 0.0000500 |
| Chrysene | U | | 0.0000179 | 0.0000500 |
| Dibenz(a,h)anthracene | U | | 0.0000160 | 0.0000500 |
| Fluoranthene | U | | 0.0000270 | 0.000100 |
| Fluorene | U | | 0.0000169 | 0.0000500 |
| Indeno(1,2,3-cd)pyrene | U | | 0.0000158 | 0.0000500 |
| Naphthalene | U | | 0.0000917 | 0.000250 |
| Phenanthrene | U | | 0.0000180 | 0.0000500 |
| Pyrene | U | | 0.0000169 | 0.0000500 |
| 1-Methylnaphthalene | U | | 0.0000687 | 0.000250 |
| 2-Methylnaphthalene | U | | 0.0000674 | 0.000250 |
| 2-Chloronaphthalene | U | | 0.0000682 | 0.000250 |
| *(S) Nitrobenzene-d5* | *96.0* | | | *31.0-160* |
| *(S) 2-Fluorobiphenyl* | *98.5* | | | *48.0-148* |
| *(S) p-Terphenyl-d14* | *94.0* | | | *37.0-146* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3988816-1 10/17/23 13:08 • (LCSD) R3988816-2 10/17/23 13:25

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Anthracene | 0.0100 | 0.00967 | 0.00934 | 96.7 | 93.4 | 67.0-150 | | | 3.47 | 20 |
| Acenaphthene | 0.0100 | 0.00911 | 0.00890 | 91.1 | 89.0 | 65.0-138 | | | 2.33 | 20 |
| Acenaphthylene | 0.0100 | 0.0102 | 0.00993 | 102 | 99.3 | 66.0-140 | | | 2.68 | 20 |
| Benzo(a)anthracene | 0.0100 | 0.0100 | 0.00960 | 100 | 96.0 | 61.0-140 | | | 4.08 | 20 |
| Benzo(a)pyrene | 0.0100 | 0.00967 | 0.00925 | 96.7 | 92.5 | 60.0-143 | | | 4.44 | 20 |
| Benzo(b)fluoranthene | 0.0100 | 0.00941 | 0.00897 | 94.1 | 89.7 | 58.0-141 | | | 4.79 | 20 |
| Benzo(g,h,i)perylene | 0.0100 | 0.00828 | 0.00792 | 82.8 | 79.2 | 52.0-153 | | | 4.44 | 20 |
| Benzo(k)fluoranthene | 0.0100 | 0.00907 | 0.00867 | 90.7 | 86.7 | 58.0-148 | | | 4.51 | 20 |
| Chrysene | 0.0100 | 0.0100 | 0.00961 | 100 | 96.1 | 64.0-144 | | | 3.98 | 20 |
| Dibenz(a,h)anthracene | 0.0100 | 0.00892 | 0.00864 | 89.2 | 86.4 | 52.0-155 | | | 3.19 | 20 |
| Fluoranthene | 0.0100 | 0.0103 | 0.00984 | 103 | 98.4 | 69.0-153 | | | 4.57 | 20 |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3988816-1 10/17/23 13:08 • (LCSD) R3988816-2 10/17/23 13:25

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Fluorene | 0.0100 | 0.0106 | 0.0101 | 106 | 101 | 64.0-136 | | | 4.83 | 20 |
| Indeno(1,2,3-cd)pyrene | 0.0100 | 0.00969 | 0.00924 | 96.9 | 92.4 | 54.0-153 | | | 4.75 | 20 |
| Naphthalene | 0.0100 | 0.00988 | 0.00966 | 98.8 | 96.6 | 61.0-137 | | | 2.25 | 20 |
| Phenanthrene | 0.0100 | 0.0101 | 0.00973 | 101 | 97.3 | 62.0-137 | | | 3.73 | 20 |
| Pyrene | 0.0100 | 0.0104 | 0.0102 | 104 | 102 | 60.0-142 | | | 1.94 | 20 |
| 1-Methylnaphthalene | 0.0100 | 0.0106 | 0.0104 | 106 | 104 | 66.0-142 | | | 1.90 | 20 |
| 2-Methylnaphthalene | 0.0100 | 0.00996 | 0.00980 | 99.6 | 98.0 | 62.0-136 | | | 1.62 | 20 |
| 2-Chloronaphthalene | 0.0100 | 0.00973 | 0.00954 | 97.3 | 95.4 | 64.0-140 | | | 1.97 | 20 |
| *(S) Nitrobenzene-d5* | | | | *101* | *95.0* | *31.0-160* | | | | |
| *(S) 2-Fluorobiphenyl* | | | | *103* | *96.5* | *48.0-148* | | | | |
| *(S) p-Terphenyl-d14* | | | | *90.0* | *82.5* | *37.0-146* | | | | |

## Method Blank (MB)

(MB) R3989711-3 10/18/23 10:14

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Anthracene | U | | 0.0000190 | 0.0000500 |
| Acenaphthene | U | | 0.0000190 | 0.0000500 |
| Acenaphthylene | U | | 0.0000171 | 0.0000500 |
| Benzo(a)anthracene | U | | 0.0000203 | 0.0000500 |
| Benzo(a)pyrene | U | | 0.0000184 | 0.0000500 |
| Benzo(b)fluoranthene | U | | 0.0000168 | 0.0000500 |
| Benzo(g,h,i)perylene | U | | 0.0000184 | 0.0000500 |
| Benzo(k)fluoranthene | U | | 0.0000202 | 0.0000500 |
| Chrysene | U | | 0.0000179 | 0.0000500 |
| Dibenz(a,h)anthracene | U | | 0.0000160 | 0.0000500 |
| Fluoranthene | U | | 0.0000270 | 0.000100 |
| Fluorene | U | | 0.0000169 | 0.0000500 |
| Indeno(1,2,3-cd)pyrene | U | | 0.0000158 | 0.0000500 |
| Naphthalene | U | | 0.0000917 | 0.000250 |
| Phenanthrene | U | | 0.0000180 | 0.0000500 |
| Pyrene | U | | 0.0000169 | 0.0000500 |
| 1-Methylnaphthalene | U | | 0.0000687 | 0.000250 |
| 2-Methylnaphthalene | U | | 0.0000674 | 0.000250 |
| 2-Chloronaphthalene | U | | 0.0000682 | 0.000250 |
| *(S) Nitrobenzene-d5* | *92.0* | | | *31.0-160* |
| *(S) 2-Fluorobiphenyl* | *93.0* | | | *48.0-148* |
| *(S) p-Terphenyl-d14* | *87.5* | | | *37.0-146* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3989711-1 10/18/23 09:39 • (LCSD) R3989711-2 10/18/23 09:57

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Anthracene | 0.00200 | 0.00171 | 0.00174 | 85.5 | 87.0 | 67.0-150 | | | 1.74 | 20 |
| Acenaphthene | 0.00200 | 0.00171 | 0.00178 | 85.5 | 89.0 | 65.0-138 | | | 4.01 | 20 |
| Acenaphthylene | 0.00200 | 0.00178 | 0.00183 | 89.0 | 91.5 | 66.0-140 | | | 2.77 | 20 |
| Benzo(a)anthracene | 0.00200 | 0.00172 | 0.00177 | 86.0 | 88.5 | 61.0-140 | | | 2.87 | 20 |
| Benzo(a)pyrene | 0.00200 | 0.00168 | 0.00173 | 84.0 | 86.5 | 60.0-143 | | | 2.93 | 20 |
| Benzo(b)fluoranthene | 0.00200 | 0.00174 | 0.00174 | 87.0 | 87.0 | 58.0-141 | | | 0.000 | 20 |
| Benzo(g,h,i)perylene | 0.00200 | 0.00160 | 0.00165 | 80.0 | 82.5 | 52.0-153 | | | 3.08 | 20 |
| Benzo(k)fluoranthene | 0.00200 | 0.00167 | 0.00168 | 83.5 | 84.0 | 58.0-148 | | | 0.597 | 20 |
| Chrysene | 0.00200 | 0.00178 | 0.00184 | 89.0 | 92.0 | 64.0-144 | | | 3.31 | 20 |
| Dibenz(a,h)anthracene | 0.00200 | 0.00156 | 0.00160 | 78.0 | 80.0 | 52.0-155 | | | 2.53 | 20 |
| Fluoranthene | 0.00200 | 0.00178 | 0.00184 | 89.0 | 92.0 | 69.0-153 | | | 3.31 | 20 |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3989711-1 10/18/23 09:39 • (LCSD) R3989711-2 10/18/23 09:57

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Fluorene | 0.00200 | 0.00181 | 0.00188 | 90.5 | 94.0 | 64.0-136 | | | 3.79 | 20 |
| Indeno(1,2,3-cd)pyrene | 0.00200 | 0.00158 | 0.00164 | 79.0 | 82.0 | 54.0-153 | | | 3.73 | 20 |
| Naphthalene | 0.00200 | 0.00183 | 0.00189 | 91.5 | 94.5 | 61.0-137 | | | 3.23 | 20 |
| Phenanthrene | 0.00200 | 0.00178 | 0.00185 | 89.0 | 92.5 | 62.0-137 | | | 3.86 | 20 |
| Pyrene | 0.00200 | 0.00183 | 0.00187 | 91.5 | 93.5 | 60.0-142 | | | 2.16 | 20 |
| 1-Methylnaphthalene | 0.00200 | 0.00182 | 0.00189 | 91.0 | 94.5 | 66.0-142 | | | 3.77 | 20 |
| 2-Methylnaphthalene | 0.00200 | 0.00187 | 0.00193 | 93.5 | 96.5 | 62.0-136 | | | 3.16 | 20 |
| 2-Chloronaphthalene | 0.00200 | 0.00176 | 0.00184 | 88.0 | 92.0 | 64.0-140 | | | 4.44 | 20 |
| *(S) Nitrobenzene-d5* | | | | *93.0* | *92.5* | *31.0-160* | | | | |
| *(S) 2-Fluorobiphenyl* | | | | *89.0* | *92.0* | *48.0-148* | | | | |
| *(S) p-Terphenyl-d14* | | | | *81.0* | *82.0* | *37.0-146* | | | | |

# GLOSSARY OF TERMS

## Guide to Reading and Understanding Your Laboratory Report

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.

Results Disclaimer - Information that may be provided by the customer, and contained within this report, include Permit Limits, Project Name, Sample ID, Sample Matrix, Sample Preservation, Field Blanks, Field Spikes, Field Duplicates, On-Site Data, Sampling Collection Dates/Times, and Sampling Location. Results relate to the accuracy of this information provided, and as the samples are received.

## Abbreviations and Definitions

| | |
|---|---|
| MDL | Method Detection Limit. |
| ND | Not detected at the Reporting Limit (or MDL where applicable). |
| RDL | Reported Detection Limit. |
| Rec. | Recovery. |
| RPD | Relative Percent Difference. |
| SDG | Sample Delivery Group. |
| (S) | Surrogate (Surrogate Standard) - Analytes added to every blank, sample, Laboratory Control Sample/Duplicate and Matrix Spike/Duplicate; used to evaluate analytical efficiency by measuring recovery. Surrogates are not expected to be detected in all environmental media. |
| U | Not detected at the Reporting Limit (or MDL where applicable). |
| Analyte | The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported. |
| Dilution | If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor. |
| Limits | These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges. |
| Qualifier | This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable. |
| Result | The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state “ND” (Not Detected) or “BDL” (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte. |
| Uncertainty (Radiochemistry) | Confidence level of 2 sigma. |
| Case Narrative (Cn) | A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report. |
| Quality Control Summary (Qc) | This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material. |
| Sample Chain of Custody (Sc) | This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis. |
| Sample Results (Sr) | This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported. |
| Sample Summary (Ss) | This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis. |

| Qualifier | Description |
|---|---|
| J1 | Surrogate recovery limits have been exceeded; values are outside upper control limits. |
| J2 | Surrogate recovery limits have been exceeded; values are outside lower control limits. |

# ACCREDITATIONS & LOCATIONS

## Pace Analytical National 12065 Lebanon Rd Mount Juliet, TN 37122

| | | | |
|---|---|---|---|
| Alabama | 40660 | Nebraska | NE-OS-15-05 |
| Alaska | 17-026 | Nevada | TN000032021-1 |
| Arizona | AZ0612 | New Hampshire | 2975 |
| Arkansas | 88-0469 | New Jersey–NELAP | TN002 |
| California | 2932 | New Mexico [1] | TN00003 |
| Colorado | TN00003 | New York | 11742 |
| Connecticut | PH-0197 | North Carolina | Env375 |
| Florida | E87487 | North Carolina [1] | DW21704 |
| Georgia | NELAP | North Carolina [3] | 41 |
| Georgia [1] | 923 | North Dakota | R-140 |
| Idaho | TN00003 | Ohio–VAP | CL0069 |
| Illinois | 200008 | Oklahoma | 9915 |
| Indiana | C-TN-01 | Oregon | TN200002 |
| Iowa | 364 | Pennsylvania | 68-02979 |
| Kansas | E-10277 | Rhode Island | LA000356 |
| Kentucky [1 6] | KY90010 | South Carolina | 84004002 |
| Kentucky [2] | 16 | South Dakota | n/a |
| Louisiana | AI30792 | Tennessee [1 4] | 2006 |
| Louisiana | LA018 | Texas | T104704245-20-18 |
| Maine | TN00003 | Texas [5] | LAB0152 |
| Maryland | 324 | Utah | TN000032021-11 |
| Massachusetts | M-TN003 | Vermont | VT2006 |
| Michigan | 9958 | Virginia | 110033 |
| Minnesota | 047-999-395 | Washington | C847 |
| Mississippi | TN00003 | West Virginia | 233 |
| Missouri | 340 | Wisconsin | 998093910 |
| Montana | CERT0086 | Wyoming | A2LA |
| A2LA – ISO 17025 | 1461.01 | AIHA-LAP,LLC EMLAP | 100789 |
| A2LA – ISO 17025 [5] | 1461.02 | DOD | 1461.01 |
| Canada | 1461.01 | USDA | P330-15-00234 |
| EPA–Crypto | TN00003 | | |

[1] Drinking Water [2] Underground Storage Tanks [3] Aquatic Toxicity [4] Chemical/Microbiological [5] Mold [6] Wastewater n/a Accreditation not applicable

* Not all certifications held by the laboratory are applicable to the results reported in the attached report.

* Accreditation is only applicable to the test methods specified on each scope of accreditation held by Pace Analytical.

Company Name/Address:
**Rio Grande Resources Corp**

219 S 2nd St
Raton, NM 87740

Billing Information:
Bruce Norquist
PO Box 1150
Grants , NM 87020

Pres Chk

Report to: **Eric Roads**

Email To: eroads@enganalytics.com;tdavis@enganalytics.

Project Description: Mt Taylor

City/State Collected: Grants, New Mexico

Please Circle: PT MT CT ET

Phone: 970-488-3111

Client Project # 111360

Lab Project # RIOGRAGNM-MTTAYLOR

Collected by (print): Tyler Davis

Site/Facility ID #

P.O. #

Collected by (signature): Tyler Davis

Immediately Packed on Ice N ___ Y ✓

*Rush?* (Lab MUST Be Notified)
___ Same Day ___ Five Day
___ Next Day ___ 5 Day (Rad Only)
___ Two Day ___ 10 Day (Rad Only)
___ Three Day

Quote #

Date Results Needed

Analysis / Container / Preservative

| Sample ID | Comp/Grab | Matrix * | Depth | Date | Time | No. of Cntrs | DROORGLVI 40mlAmb-HCl-BT | GRO 40mlAmb HCl | PAHSIMLVI 40mlAmb-NoPres-WT | SV8270PAH 4ozClr-NoPres | V8260BTEX 40mlAmb-HCl | V8260BTEX 40mlAmb/MeOH10ml/Syr | Remarks | Sample # (lab only) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MT-GW-PD-DW6-101023 | Grab | GW | 0 | 10-10-23 | 1607 | 9 | X | X | X | | X | | | -01 |
| MT-GW-PD-DW2a-101123 | Grab | GW | 0 | 10-11-23 | 0845 | 9 | X | X | X | | X | | | -02 |
| MT-GW-TS-1005-DW3-101123-K3 | Grab | GW | 1005 | 10-11-23 | 1041 | 9 | X | X | X | | X | | | -03 |
| MT-GW-TS-1005-DW3-101123-K2 | Grab | GW | 1005 | 10-11-23 | 0933 | 9 | X | X | X | | X | | | -04 |
| MT-GW-TS-1005-DW3-101123-K1 | Grab | GW | 1005 | 10-11-23 | 1400 | 9 | X | X | X | | X | | | -05 |
| MT-GW-TS-896-DW3-101123 K3 | Grab | GW | 896 | 10-11-23 | 1445 | 9 | X | X | X | | X | | | -06 |
| MT-GW-TS-596-DW3-101123 K3 | Grab | GW | 596 | 10-11-23 | 1626 | 9 | X | X | X | | X | | | -07 |
| | | GW | | | | 9 | X | X | X | | X | | | |
| | | GW | | | | 9 | X | X | X | | X | | | |
| | | GW | | | | 9 | X | X | X | | X | | | |

Chain of Custody Page ___ of ___

Pace
PEOPLE ADVANCING SCIENCE

**MT JULIET, TN**

12065 Lebanon Rd Mount Juliet, TN 37122
Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Pace Terms and Conditions found at: https://info.pacelabs.com/hubfs/pas-standard-terms.pdf

SDG # L1666516
E185

Acctnum: **RIOGRAGNM**
Template: **T238214**
Prelogin: **P1026344**
PM: **732 - Donna Eidson**
PB: NG 9122123
Shipped Via: **FedEX Ground**

* Matrix:
SS - Soil AIR - Air F - Filter
GW - Groundwater B - Bioassay
WW - WasteWater
DW - Drinking Water
OT - Other_____

**Remarks:** Some Samples have effervescence that caused air bubbles after sealed
Blue cooler

pH _____ Temp _____
Flow _____ Other _____

Samples returned via:
__ UPS __ FedEx __ Courier _____

Tracking #

Sample Receipt Checklist
COC Seal Present/Intact: __NP ✓Y __N
COC Signed/Accurate: __Y __N
Bottles arrive intact: __Y __N
Correct bottles used: __Y __N
Sufficient volume sent: __Y __N
If Applicable
VOA Zero Headspace: __Y __N
Preservation Correct/Checked: __Y __N
RAD Screen <0.5 mR/hr: ✓Y __N

| Relinquished by : (Signature) | Date: | Time: | Received by: (Signature) | Trip Blank Received: Yes / No HCL / MeoH TBR | If preservation required by Login: Date/Time |
|---|---|---|---|---|---|
| | 10-12-2023 | 1656 | | | |
| Relinquished by : (Signature) | Date: | Time: | Received by: (Signature) | Temp: 5.3+0=5.3 °C Bottles Received: 63 | |
| Relinquished by : (Signature) | Date: | Time: | Received for lab by: (Signature) HANNAH MINCHINA | Date: 10/13 Time: 0900 | Hold: Condition: NCF / OK |

# ANALYTICAL REPORT

October 23, 2023



## Rio Grande Resources Corp


| | |
|---|---|
| Sample Delivery Group: | L1666531 |
| Samples Received: | 10/13/2023 |
| Project Number: | 111360 |
| Description: | Mt Taylor |

Report To: Eric Roads
219 S 2nd St
Raton, NM 87740

Entire Report Reviewed By:

John Hawkins
Project Manager

Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace Analytical National is performed per guidance provided in laboratory standard operating procedures ENV-SOP-MTJL-0067 and ENV-SOP-MTJL-0068. Where sampling conducted by the customer, results relate to the accuracy of the information provided, and as the samples are received.



Pace Analytical National
12065 Lebanon Rd Mount Juliet, TN 37122 615-758-5858 800-767-5859 www.pacenational.com

# TABLE OF CONTENTS


Cp: Cover Page 1

Tc: Table of Contents 2

Ss: Sample Summary 3

Cn: Case Narrative 5

Sr: Sample Results 6

MT-GW-TS781-DW10-100923-K3 L1666531-01 6

MT-GW-TS781-DW10-100923-K2 L1666531-02 7

MT-GW-TS781-DW10-100923- L1666531-03 8

MT-GW-TS463-DW10-100923-K3 L1666531-04 9

MT-GW-TS463-DW10-100923- L1666531-05 10

MT-GW-TS961-DW8-100923-K3 L1666531-06 11

MT-GW-TS961-DW8-100923-K1 L1666531-07 12

MT-GW-TS961-DW8-100923- L1666531-08 13

MT-GW-TS840-DW8-100923-K3 L1666531-09 14

MT-GW-TS840-DW8-100923- L1666531-10 15

Qc: Quality Control Summary 16

Volatile Organic Compounds (GC) by Method 8015D/GRO 16

Volatile Organic Compounds (GC/MS) by Method 8260B 17

Semi-Volatile Organic Compounds (GC) by Method 8015 18

Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM 19

Gl: Glossary of Terms 21

Al: Accreditations & Locations 22

Sc: Sample Chain of Custody 23

## MT-GW-TS781-DW10-100923-K3 L1666531-01 GW

Collected by: Tyler Davis | Collected date/time: 10/09/23 09:28 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 15:40 | 10/19/23 15:40 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 08:33 | 10/15/23 08:33 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153934 | 1 | 10/19/23 20:45 | 10/21/23 04:44 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151585 | 1 | 10/16/23 09:05 | 10/16/23 18:35 | DSH | Mt. Juliet, TN |

## MT-GW-TS781-DW10-100923-K2 L1666531-02 GW

Collected by: Tyler Davis | Collected date/time: 10/09/23 10:03 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 15:59 | 10/19/23 15:59 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 08:54 | 10/15/23 08:54 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153934 | 1 | 10/19/23 20:45 | 10/21/23 05:05 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151585 | 1 | 10/16/23 09:05 | 10/16/23 18:53 | DSH | Mt. Juliet, TN |

## MT-GW-TS781-DW10-100923- L1666531-03 GW

Collected by: Tyler Davis | Collected date/time: 10/09/23 10:22 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 16:19 | 10/19/23 16:19 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 09:15 | 10/15/23 09:15 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153934 | 1 | 10/19/23 20:45 | 10/21/23 05:25 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151585 | 1 | 10/16/23 09:05 | 10/16/23 19:10 | DSH | Mt. Juliet, TN |

## MT-GW-TS463-DW10-100923-K3 L1666531-04 GW

Collected by: Tyler Davis | Collected date/time: 10/09/23 10:53 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 16:39 | 10/19/23 16:39 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 09:36 | 10/15/23 09:36 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153934 | 1 | 10/19/23 20:45 | 10/21/23 05:45 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151585 | 1 | 10/16/23 09:05 | 10/16/23 19:27 | DSH | Mt. Juliet, TN |

## MT-GW-TS463-DW10-100923- L1666531-05 GW

Collected by: Tyler Davis | Collected date/time: 10/09/23 12:23 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 16:58 | 10/19/23 16:58 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 09:57 | 10/15/23 09:57 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153934 | 1 | 10/19/23 20:45 | 10/21/23 06:05 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151585 | 1 | 10/16/23 09:05 | 10/16/23 19:45 | DSH | Mt. Juliet, TN |

## MT-GW-TS961-DW8-100923-K3 L1666531-06 GW

Collected by: Tyler Davis | Collected date/time: 10/09/23 14:50 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 17:17 | 10/19/23 17:17 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 10:18 | 10/15/23 10:18 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153934 | 1 | 10/19/23 20:45 | 10/21/23 06:25 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151585 | 1 | 10/16/23 09:05 | 10/16/23 20:02 | DSH | Mt. Juliet, TN |

## MT-GW-TS961-DW8-100923-K1 L1666531-07 GW

Collected by: Tyler Davis | Collected date/time: 10/09/23 15:58 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 17:36 | 10/19/23 17:36 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 10:39 | 10/15/23 10:39 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153934 | 1 | 10/19/23 20:45 | 10/21/23 06:46 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151585 | 1 | 10/16/23 09:05 | 10/16/23 20:19 | DSH | Mt. Juliet, TN |

## MT-GW-TS961-DW8-100923- L1666531-08 GW

Collected by: Tyler Davis | Collected date/time: 10/09/23 15:58 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 17:55 | 10/19/23 17:55 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 11:00 | 10/15/23 11:00 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153934 | 1 | 10/19/23 20:45 | 10/21/23 07:06 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151585 | 1 | 10/16/23 09:05 | 10/16/23 20:37 | DSH | Mt. Juliet, TN |

## MT-GW-TS840-DW8-100923-K3 L1666531-09 GW

Collected by: Tyler Davis | Collected date/time: 10/09/23 16:33 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 18:14 | 10/19/23 18:14 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 11:23 | 10/15/23 11:23 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153934 | 1 | 10/19/23 20:45 | 10/21/23 07:26 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151585 | 1 | 10/16/23 09:05 | 10/16/23 20:54 | DSH | Mt. Juliet, TN |

## MT-GW-TS840-DW8-100923- L1666531-10 GW

Collected by: Tyler Davis | Collected date/time: 10/09/23 17:24 | Received date/time: 10/13/23 09:00

| Method | Batch | Dilution | Preparation date/time | Analysis date/time | Analyst | Location |
|---|---|---|---|---|---|---|
| Volatile Organic Compounds (GC) by Method 8015D/GRO | WG2154045 | 1 | 10/19/23 18:33 | 10/19/23 18:33 | NCD | Mt. Juliet, TN |
| Volatile Organic Compounds (GC/MS) by Method 8260B | WG2151529 | 1 | 10/15/23 11:43 | 10/15/23 11:43 | JCP | Mt. Juliet, TN |
| Semi-Volatile Organic Compounds (GC) by Method 8015 | WG2153934 | 1 | 10/19/23 20:45 | 10/21/23 07:46 | MAA | Mt. Juliet, TN |
| Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM | WG2151585 | 1 | 10/16/23 09:05 | 10/16/23 21:11 | DSH | Mt. Juliet, TN |

# CASE NARRATIVE

All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.



John Hawkins
Project Manager

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 15:40 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *96.9* | | *78.0-120* | | *10/19/2023 15:40* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 08:33 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 08:33 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 08:33 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 08:33 | WG2151529 |
| *(S) Toluene-d8* | *111* | | *80.0-120* | | *10/15/2023 08:33* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *117* | | *77.0-126* | | *10/15/2023 08:33* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *103* | | *70.0-130* | | *10/15/2023 08:33* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | J3 | 0.100 | 1 | 10/21/2023 04:44 | WG2153934 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/21/2023 04:44 | WG2153934 |
| *(S) o-Terphenyl* | *87.4* | | *52.0-156* | | *10/21/2023 04:44* | WG2153934 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Chrysene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/16/2023 18:35 | WG2151585 |
| Fluorene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Naphthalene | ND | | 0.000250 | 1 | 10/16/2023 18:35 | WG2151585 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| Pyrene | ND | | 0.0000500 | 1 | 10/16/2023 18:35 | WG2151585 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 18:35 | WG2151585 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 18:35 | WG2151585 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/16/2023 18:35 | WG2151585 |
| *(S) Nitrobenzene-d5* | *109* | | *31.0-160* | | *10/16/2023 18:35* | WG2151585 |
| *(S) 2-Fluorobiphenyl* | *89.5* | | *48.0-148* | | *10/16/2023 18:35* | WG2151585 |
| *(S) p-Terphenyl-d14* | *103* | | *37.0-146* | | *10/16/2023 18:35* | WG2151585 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 15:59 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *96.6* | | *78.0-120* | | *10/19/2023 15:59* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 08:54 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 08:54 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 08:54 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 08:54 | WG2151529 |
| *(S) Toluene-d8* | *113* | | *80.0-120* | | *10/15/2023 08:54* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *117* | | *77.0-126* | | *10/15/2023 08:54* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *103* | | *70.0-130* | | *10/15/2023 08:54* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | J3 | 0.100 | 1 | 10/21/2023 05:05 | WG2153934 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/21/2023 05:05 | WG2153934 |
| *(S) o-Terphenyl* | *102* | | *52.0-156* | | *10/21/2023 05:05* | WG2153934 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Chrysene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/16/2023 18:53 | WG2151585 |
| Fluorene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Naphthalene | ND | | 0.000250 | 1 | 10/16/2023 18:53 | WG2151585 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| Pyrene | ND | | 0.0000500 | 1 | 10/16/2023 18:53 | WG2151585 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 18:53 | WG2151585 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 18:53 | WG2151585 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/16/2023 18:53 | WG2151585 |
| *(S) Nitrobenzene-d5* | *110* | | *31.0-160* | | *10/16/2023 18:53* | WG2151585 |
| *(S) 2-Fluorobiphenyl* | *92.1* | | *48.0-148* | | *10/16/2023 18:53* | WG2151585 |
| *(S) p-Terphenyl-d14* | *103* | | *37.0-146* | | *10/16/2023 18:53* | WG2151585 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 16:19 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *96.9* | | *78.0-120* | | *10/19/2023 16:19* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 09:15 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 09:15 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 09:15 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 09:15 | WG2151529 |
| *(S) Toluene-d8* | *113* | | *80.0-120* | | *10/15/2023 09:15* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *118* | | *77.0-126* | | *10/15/2023 09:15* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *104* | | *70.0-130* | | *10/15/2023 09:15* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.112 | J3 | 0.100 | 1 | 10/21/2023 05:25 | WG2153934 |
| C28-C40 Oil Range | 0.236 | | 0.100 | 1 | 10/21/2023 05:25 | WG2153934 |
| *(S) o-Terphenyl* | *86.8* | | *52.0-156* | | *10/21/2023 05:25* | WG2153934 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Chrysene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/16/2023 19:10 | WG2151585 |
| Fluorene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Naphthalene | ND | | 0.000250 | 1 | 10/16/2023 19:10 | WG2151585 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| Pyrene | ND | | 0.0000500 | 1 | 10/16/2023 19:10 | WG2151585 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 19:10 | WG2151585 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 19:10 | WG2151585 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/16/2023 19:10 | WG2151585 |
| *(S) Nitrobenzene-d5* | *106* | | *31.0-160* | | *10/16/2023 19:10* | WG2151585 |
| *(S) 2-Fluorobiphenyl* | *87.9* | | *48.0-148* | | *10/16/2023 19:10* | WG2151585 |
| *(S) p-Terphenyl-d14* | *97.9* | | *37.0-146* | | *10/16/2023 19:10* | WG2151585 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 16:39 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *97.1* | | *78.0-120* | | *10/19/2023 16:39* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 09:36 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 09:36 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 09:36 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 09:36 | WG2151529 |
| *(S) Toluene-d8* | *112* | | *80.0-120* | | *10/15/2023 09:36* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *119* | | *77.0-126* | | *10/15/2023 09:36* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *105* | | *70.0-130* | | *10/15/2023 09:36* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | J3 | 0.100 | 1 | 10/21/2023 05:45 | WG2153934 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/21/2023 05:45 | WG2153934 |
| *(S) o-Terphenyl* | *115* | | *52.0-156* | | *10/21/2023 05:45* | WG2153934 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Chrysene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/16/2023 19:27 | WG2151585 |
| Fluorene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Naphthalene | ND | | 0.000250 | 1 | 10/16/2023 19:27 | WG2151585 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| Pyrene | ND | | 0.0000500 | 1 | 10/16/2023 19:27 | WG2151585 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 19:27 | WG2151585 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 19:27 | WG2151585 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/16/2023 19:27 | WG2151585 |
| *(S) Nitrobenzene-d5* | *113* | | *31.0-160* | | *10/16/2023 19:27* | WG2151585 |
| *(S) 2-Fluorobiphenyl* | *95.3* | | *48.0-148* | | *10/16/2023 19:27* | WG2151585 |
| *(S) p-Terphenyl-d14* | *108* | | *37.0-146* | | *10/16/2023 19:27* | WG2151585 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 16:58 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *97.6* | | *78.0-120* | | *10/19/2023 16:58* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 09:57 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 09:57 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 09:57 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 09:57 | WG2151529 |
| *(S) Toluene-d8* | *112* | | *80.0-120* | | *10/15/2023 09:57* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *118* | | *77.0-126* | | *10/15/2023 09:57* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *103* | | *70.0-130* | | *10/15/2023 09:57* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.518 | J3 | 0.100 | 1 | 10/21/2023 06:05 | WG2153934 |
| C28-C40 Oil Range | 0.871 | | 0.100 | 1 | 10/21/2023 06:05 | WG2153934 |
| *(S) o-Terphenyl* | *73.7* | | *52.0-156* | | *10/21/2023 06:05* | WG2153934 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Chrysene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/16/2023 19:45 | WG2151585 |
| Fluorene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Naphthalene | ND | | 0.000250 | 1 | 10/16/2023 19:45 | WG2151585 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| Pyrene | ND | | 0.0000500 | 1 | 10/16/2023 19:45 | WG2151585 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 19:45 | WG2151585 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 19:45 | WG2151585 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/16/2023 19:45 | WG2151585 |
| *(S) Nitrobenzene-d5* | *112* | | *31.0-160* | | *10/16/2023 19:45* | WG2151585 |
| *(S) 2-Fluorobiphenyl* | *93.2* | | *48.0-148* | | *10/16/2023 19:45* | WG2151585 |
| *(S) p-Terphenyl-d14* | *102* | | *37.0-146* | | *10/16/2023 19:45* | WG2151585 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 17:17 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *97.5* | | *78.0-120* | | *10/19/2023 17:17* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 10:18 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 10:18 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 10:18 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 10:18 | WG2151529 |
| *(S) Toluene-d8* | *113* | | *80.0-120* | | *10/15/2023 10:18* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *117* | | *77.0-126* | | *10/15/2023 10:18* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *103* | | *70.0-130* | | *10/15/2023 10:18* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | J3 | 0.100 | 1 | 10/21/2023 06:25 | WG2153934 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/21/2023 06:25 | WG2153934 |
| *(S) o-Terphenyl* | *55.3* | | *52.0-156* | | *10/21/2023 06:25* | WG2153934 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Chrysene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/16/2023 20:02 | WG2151585 |
| Fluorene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Naphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:02 | WG2151585 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| Pyrene | ND | | 0.0000500 | 1 | 10/16/2023 20:02 | WG2151585 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:02 | WG2151585 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:02 | WG2151585 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:02 | WG2151585 |
| *(S) Nitrobenzene-d5* | *115* | | *31.0-160* | | *10/16/2023 20:02* | WG2151585 |
| *(S) 2-Fluorobiphenyl* | *95.3* | | *48.0-148* | | *10/16/2023 20:02* | WG2151585 |
| *(S) p-Terphenyl-d14* | *107* | | *37.0-146* | | *10/16/2023 20:02* | WG2151585 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 17:36 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *95.2* | | *78.0-120* | | *10/19/2023 17:36* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 10:39 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 10:39 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 10:39 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 10:39 | WG2151529 |
| *(S) Toluene-d8* | *111* | | *80.0-120* | | *10/15/2023 10:39* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *114* | | *77.0-126* | | *10/15/2023 10:39* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *105* | | *70.0-130* | | *10/15/2023 10:39* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.130 | J3 | 0.100 | 1 | 10/21/2023 06:46 | WG2153934 |
| C28-C40 Oil Range | 0.138 | | 0.100 | 1 | 10/21/2023 06:46 | WG2153934 |
| *(S) o-Terphenyl* | *88.4* | | *52.0-156* | | *10/21/2023 06:46* | WG2153934 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Chrysene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/16/2023 20:19 | WG2151585 |
| Fluorene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Naphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:19 | WG2151585 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| Pyrene | ND | | 0.0000500 | 1 | 10/16/2023 20:19 | WG2151585 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:19 | WG2151585 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:19 | WG2151585 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:19 | WG2151585 |
| *(S) Nitrobenzene-d5* | *111* | | *31.0-160* | | *10/16/2023 20:19* | WG2151585 |
| *(S) 2-Fluorobiphenyl* | *92.6* | | *48.0-148* | | *10/16/2023 20:19* | WG2151585 |
| *(S) p-Terphenyl-d14* | *103* | | *37.0-146* | | *10/16/2023 20:19* | WG2151585 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 17:55 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *97.2* | | *78.0-120* | | *10/19/2023 17:55* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 11:00 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 11:00 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 11:00 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 11:00 | WG2151529 |
| *(S) Toluene-d8* | *112* | | *80.0-120* | | *10/15/2023 11:00* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *115* | | *77.0-126* | | *10/15/2023 11:00* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *105* | | *70.0-130* | | *10/15/2023 11:00* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 0.122 | J3 | 0.100 | 1 | 10/21/2023 07:06 | WG2153934 |
| C28-C40 Oil Range | 0.146 | | 0.100 | 1 | 10/21/2023 07:06 | WG2153934 |
| *(S) o-Terphenyl* | *87.4* | | *52.0-156* | | *10/21/2023 07:06* | WG2153934 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Chrysene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/16/2023 20:37 | WG2151585 |
| Fluorene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Naphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:37 | WG2151585 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| Pyrene | ND | | 0.0000500 | 1 | 10/16/2023 20:37 | WG2151585 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:37 | WG2151585 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:37 | WG2151585 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:37 | WG2151585 |
| *(S) Nitrobenzene-d5* | *108* | | *31.0-160* | | *10/16/2023 20:37* | WG2151585 |
| *(S) 2-Fluorobiphenyl* | *88.4* | | *48.0-148* | | *10/16/2023 20:37* | WG2151585 |
| *(S) p-Terphenyl-d14* | *99.5* | | *37.0-146* | | *10/16/2023 20:37* | WG2151585 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 18:14 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *97.7* | | *78.0-120* | | *10/19/2023 18:14* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 11:23 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 11:23 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 11:23 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 11:23 | WG2151529 |
| *(S) Toluene-d8* | *98.9* | | *80.0-120* | | *10/15/2023 11:23* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *102* | | *77.0-126* | | *10/15/2023 11:23* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *106* | | *70.0-130* | | *10/15/2023 11:23* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | J3 | 0.100 | 1 | 10/21/2023 07:26 | WG2153934 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/21/2023 07:26 | WG2153934 |
| *(S) o-Terphenyl* | *78.9* | | *52.0-156* | | *10/21/2023 07:26* | WG2153934 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Chrysene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/16/2023 20:54 | WG2151585 |
| Fluorene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Naphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:54 | WG2151585 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| Pyrene | ND | | 0.0000500 | 1 | 10/16/2023 20:54 | WG2151585 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:54 | WG2151585 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:54 | WG2151585 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/16/2023 20:54 | WG2151585 |
| *(S) Nitrobenzene-d5* | *108* | | *31.0-160* | | *10/16/2023 20:54* | WG2151585 |
| *(S) 2-Fluorobiphenyl* | *90.0* | | *48.0-148* | | *10/16/2023 20:54* | WG2151585 |
| *(S) p-Terphenyl-d14* | *103* | | *37.0-146* | | *10/16/2023 20:54* | WG2151585 |

## Volatile Organic Compounds (GC) by Method 8015D/GRO

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | ND | | 0.100 | 1 | 10/19/2023 18:33 | WG2154045 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *97.4* | | *78.0-120* | | *10/19/2023 18:33* | WG2154045 |

## Volatile Organic Compounds (GC/MS) by Method 8260B

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Benzene | ND | | 0.00100 | 1 | 10/15/2023 11:43 | WG2151529 |
| Toluene | ND | | 0.00100 | 1 | 10/15/2023 11:43 | WG2151529 |
| Ethylbenzene | ND | | 0.00100 | 1 | 10/15/2023 11:43 | WG2151529 |
| Total Xylenes | ND | | 0.00300 | 1 | 10/15/2023 11:43 | WG2151529 |
| *(S) Toluene-d8* | *126* | J1 | *80.0-120* | | *10/15/2023 11:43* | WG2151529 |
| *(S) 4-Bromofluorobenzene* | *115* | | *77.0-126* | | *10/15/2023 11:43* | WG2151529 |
| *(S) 1,2-Dichloroethane-d4* | *92.4* | | *70.0-130* | | *10/15/2023 11:43* | WG2151529 |

## Semi-Volatile Organic Compounds (GC) by Method 8015

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | ND | J3 | 0.100 | 1 | 10/21/2023 07:46 | WG2153934 |
| C28-C40 Oil Range | ND | | 0.100 | 1 | 10/21/2023 07:46 | WG2153934 |
| *(S) o-Terphenyl* | *94.7* | | *52.0-156* | | *10/21/2023 07:46* | WG2153934 |

## Semi Volatile Organic Compounds (GC/MS) by Method 8270C-SIM

| Analyte | Result mg/l | Qualifier | RDL mg/l | Dilution | Analysis date / time | Batch |
|---|---|---|---|---|---|---|
| Anthracene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Acenaphthene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Acenaphthylene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Benzo(a)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Benzo(a)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Benzo(b)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Benzo(g,h,i)perylene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Benzo(k)fluoranthene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Chrysene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Dibenz(a,h)anthracene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Fluoranthene | ND | | 0.000100 | 1 | 10/16/2023 21:11 | WG2151585 |
| Fluorene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Indeno(1,2,3-cd)pyrene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Naphthalene | ND | | 0.000250 | 1 | 10/16/2023 21:11 | WG2151585 |
| Phenanthrene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| Pyrene | ND | | 0.0000500 | 1 | 10/16/2023 21:11 | WG2151585 |
| 1-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 21:11 | WG2151585 |
| 2-Methylnaphthalene | ND | | 0.000250 | 1 | 10/16/2023 21:11 | WG2151585 |
| 2-Chloronaphthalene | ND | | 0.000250 | 1 | 10/16/2023 21:11 | WG2151585 |
| *(S) Nitrobenzene-d5* | *106* | | *31.0-160* | | *10/16/2023 21:11* | WG2151585 |
| *(S) 2-Fluorobiphenyl* | *89.5* | | *48.0-148* | | *10/16/2023 21:11* | WG2151585 |
| *(S) p-Terphenyl-d14* | *97.9* | | *37.0-146* | | *10/16/2023 21:11* | WG2151585 |

## Method Blank (MB)

(MB) R3988703-2 10/19/23 11:38

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | U | | 0.0314 | 0.100 |
| *(S) a,a,a-Trifluorotoluene(FID)* | *96.3* | | | *78.0-120* |

## Laboratory Control Sample (LCS)

(LCS) R3988703-1 10/19/23 10:52

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| TPH (GC/FID) Low Fraction | 5.50 | 5.78 | 105 | 72.0-127 | |
| *(S) a,a,a-Trifluorotoluene(FID)* | | | *102* | *78.0-120* | |

## Method Blank (MB)

(MB) R3987957-3 10/15/23 04:42

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Benzene | 0.000316 | J | 0.0000941 | 0.00100 |
| Toluene | U | | 0.000278 | 0.00100 |
| Ethylbenzene | U | | 0.000137 | 0.00100 |
| Total Xylenes | U | | 0.000174 | 0.00300 |
| *(S) Toluene-d8* | *114* | | | *80.0-120* |
| *(S) 4-Bromofluorobenzene* | *117* | | | *77.0-126* |
| *(S) 1,2-Dichloroethane-d4* | *103* | | | *70.0-130* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3987957-1 10/15/23 03:18 • (LCSD) R3987957-2 10/15/23 03:39

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| Benzene | 0.00500 | 0.00523 | 0.00493 | 105 | 98.6 | 70.0-123 | | | 5.91 | 20 |
| Toluene | 0.00500 | 0.00488 | 0.00468 | 97.6 | 93.6 | 79.0-120 | | | 4.18 | 20 |
| Ethylbenzene | 0.00500 | 0.00457 | 0.00447 | 91.4 | 89.4 | 79.0-123 | | | 2.21 | 20 |
| Total Xylenes | 0.0150 | 0.0141 | 0.0136 | 94.0 | 90.7 | 79.0-123 | | | 3.61 | 20 |
| *(S) Toluene-d8* | | | | *109* | *110* | *80.0-120* | | | | |
| *(S) 4-Bromofluorobenzene* | | | | *115* | *114* | *77.0-126* | | | | |
| *(S) 1,2-Dichloroethane-d4* | | | | *106* | *102* | *70.0-130* | | | | |

## Method Blank (MB)

(MB) R3989366-1 10/20/23 22:02

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| C10-C28 Diesel Range | U | | 0.0222 | 0.100 |
| C28-C40 Oil Range | U | | 0.0118 | 0.100 |
| *(S) o-Terphenyl* | *93.5* | | | *52.0-156* |

## Laboratory Control Sample (LCS) • Laboratory Control Sample Duplicate (LCSD)

(LCS) R3989366-2 10/20/23 22:30 • (LCSD) R3989366-3 10/20/23 22:56

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCSD Result mg/l | LCS Rec. % | LCSD Rec. % | Rec. Limits % | LCS Qualifier | LCSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|
| C10-C28 Diesel Range | 1.50 | 1.87 | 1.44 | 125 | 96.0 | 50.0-150 | | J3 | 26.0 | 20 |
| *(S) o-Terphenyl* | | | | *121* | *90.0* | *52.0-156* | | | | |

## Method Blank (MB)

(MB) R3988181-2 10/16/23 14:16

| Analyte | MB Result mg/l | MB Qualifier | MB MDL mg/l | MB RDL mg/l |
|---|---|---|---|---|
| Anthracene | U | | 0.0000190 | 0.0000500 |
| Acenaphthene | U | | 0.0000190 | 0.0000500 |
| Acenaphthylene | U | | 0.0000171 | 0.0000500 |
| Benzo(a)anthracene | U | | 0.0000203 | 0.0000500 |
| Benzo(a)pyrene | U | | 0.0000184 | 0.0000500 |
| Benzo(b)fluoranthene | U | | 0.0000168 | 0.0000500 |
| Benzo(g,h,i)perylene | U | | 0.0000184 | 0.0000500 |
| Benzo(k)fluoranthene | U | | 0.0000202 | 0.0000500 |
| Chrysene | U | | 0.0000179 | 0.0000500 |
| Dibenz(a,h)anthracene | U | | 0.0000160 | 0.0000500 |
| Fluoranthene | U | | 0.0000270 | 0.000100 |
| Fluorene | U | | 0.0000169 | 0.0000500 |
| Indeno(1,2,3-cd)pyrene | U | | 0.0000158 | 0.0000500 |
| Naphthalene | U | | 0.0000917 | 0.000250 |
| Phenanthrene | U | | 0.0000180 | 0.0000500 |
| Pyrene | U | | 0.0000169 | 0.0000500 |
| 1-Methylnaphthalene | U | | 0.0000687 | 0.000250 |
| 2-Methylnaphthalene | U | | 0.0000674 | 0.000250 |
| 2-Chloronaphthalene | U | | 0.0000682 | 0.000250 |
| *(S) Nitrobenzene-d5* | *111* | | | *31.0-160* |
| *(S) 2-Fluorobiphenyl* | *89.0* | | | *48.0-148* |
| *(S) p-Terphenyl-d14* | *100* | | | *37.0-146* |

## Laboratory Control Sample (LCS)

(LCS) R3988181-1 10/16/23 13:58

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| Anthracene | 0.0100 | 0.00985 | 98.5 | 67.0-150 | |
| Acenaphthene | 0.0100 | 0.00920 | 92.0 | 65.0-138 | |
| Acenaphthylene | 0.0100 | 0.0106 | 106 | 66.0-140 | |
| Benzo(a)anthracene | 0.0100 | 0.0107 | 107 | 61.0-140 | |
| Benzo(a)pyrene | 0.0100 | 0.0113 | 113 | 60.0-143 | |
| Benzo(b)fluoranthene | 0.0100 | 0.00974 | 97.4 | 58.0-141 | |
| Benzo(g,h,i)perylene | 0.0100 | 0.00925 | 92.5 | 52.0-153 | |
| Benzo(k)fluoranthene | 0.0100 | 0.00987 | 98.7 | 58.0-148 | |
| Chrysene | 0.0100 | 0.0103 | 103 | 64.0-144 | |
| Dibenz(a,h)anthracene | 0.0100 | 0.0103 | 103 | 52.0-155 | |
| Fluoranthene | 0.0100 | 0.0107 | 107 | 69.0-153 | |

## Laboratory Control Sample (LCS)

(LCS) R3988181-1 10/16/23 13:58

| Analyte | Spike Amount mg/l | LCS Result mg/l | LCS Rec. % | Rec. Limits % | LCS Qualifier |
|---|---|---|---|---|---|
| Fluorene | 0.0100 | 0.0103 | 103 | 64.0-136 | |
| Indeno(1,2,3-cd)pyrene | 0.0100 | 0.0116 | 116 | 54.0-153 | |
| Naphthalene | 0.0100 | 0.00908 | 90.8 | 61.0-137 | |
| Phenanthrene | 0.0100 | 0.00959 | 95.9 | 62.0-137 | |
| Pyrene | 0.0100 | 0.0105 | 105 | 60.0-142 | |
| 1-Methylnaphthalene | 0.0100 | 0.00994 | 99.4 | 66.0-142 | |
| 2-Methylnaphthalene | 0.0100 | 0.00944 | 94.4 | 62.0-136 | |
| 2-Chloronaphthalene | 0.0100 | 0.00942 | 94.2 | 64.0-140 | |
| *(S) Nitrobenzene-d5* | | | *114* | *31.0-160* | |
| *(S) 2-Fluorobiphenyl* | | | *94.5* | *48.0-148* | |
| *(S) p-Terphenyl-d14* | | | *95.0* | *37.0-146* | |

## L1665985-01 Original Sample (OS) • Matrix Spike (MS) • Matrix Spike Duplicate (MSD)

(OS) L1665985-01 10/16/23 14:33 • (MS) R3988181-3 10/16/23 14:50 • (MSD) R3988181-4 10/16/23 15:08

| Analyte | Spike Amount mg/l | Original Result mg/l | MS Result mg/l | MSD Result mg/l | MS Rec. % | MSD Rec. % | Dilution | Rec. Limits % | MS Qualifier | MSD Qualifier | RPD % | RPD Limits % |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Anthracene | 0.00952 | ND | 0.00941 | 0.00899 | 98.8 | 94.4 | 1 | 56.0-156 | | | 4.57 | 20 |
| Acenaphthene | 0.00952 | ND | 0.00900 | 0.00843 | 94.5 | 88.6 | 1 | 44.0-153 | | | 6.54 | 20 |
| Acenaphthylene | 0.00952 | ND | 0.0105 | 0.00979 | 110 | 103 | 1 | 53.0-150 | | | 7.00 | 20 |
| Benzo(a)anthracene | 0.00952 | ND | 0.0107 | 0.0101 | 112 | 106 | 1 | 47.0-151 | | | 5.77 | 20 |
| Benzo(a)pyrene | 0.00952 | ND | 0.0112 | 0.0108 | 118 | 113 | 1 | 45.0-146 | | | 3.64 | 20 |
| Benzo(b)fluoranthene | 0.00952 | ND | 0.00978 | 0.00937 | 103 | 98.4 | 1 | 43.0-142 | | | 4.28 | 20 |
| Benzo(g,h,i)perylene | 0.00952 | ND | 0.00918 | 0.00884 | 96.4 | 92.9 | 1 | 40.0-147 | | | 3.77 | 20 |
| Benzo(k)fluoranthene | 0.00952 | ND | 0.00991 | 0.00954 | 104 | 100 | 1 | 43.0-148 | | | 3.80 | 21 |
| Chrysene | 0.00952 | ND | 0.0105 | 0.00995 | 110 | 105 | 1 | 50.0-148 | | | 5.38 | 20 |
| Dibenz(a,h)anthracene | 0.00952 | ND | 0.0102 | 0.00971 | 107 | 102 | 1 | 37.0-151 | | | 4.92 | 20 |
| Fluoranthene | 0.00952 | ND | 0.0104 | 0.0100 | 109 | 105 | 1 | 56.0-157 | | | 3.92 | 20 |
| Fluorene | 0.00952 | ND | 0.0101 | 0.00956 | 106 | 100 | 1 | 48.0-148 | | | 5.49 | 20 |
| Indeno(1,2,3-cd)pyrene | 0.00952 | ND | 0.0118 | 0.0112 | 124 | 118 | 1 | 41.0-148 | | | 5.22 | 20 |
| Naphthalene | 0.00952 | ND | 0.00889 | 0.00836 | 93.4 | 87.8 | 1 | 10.0-160 | | | 6.14 | 20 |
| Phenanthrene | 0.00952 | ND | 0.00942 | 0.00914 | 98.9 | 96.0 | 1 | 47.0-147 | | | 3.02 | 20 |
| Pyrene | 0.00952 | ND | 0.0105 | 0.00983 | 110 | 103 | 1 | 51.0-148 | | | 6.59 | 20 |
| 1-Methylnaphthalene | 0.00952 | ND | 0.00972 | 0.00918 | 102 | 96.4 | 1 | 21.0-160 | | | 5.71 | 20 |
| 2-Methylnaphthalene | 0.00952 | ND | 0.00923 | 0.00873 | 97.0 | 91.7 | 1 | 31.0-160 | | | 5.57 | 20 |
| 2-Chloronaphthalene | 0.00952 | ND | 0.00912 | 0.00861 | 95.8 | 90.4 | 1 | 52.0-148 | | | 5.75 | 20 |
| *(S) Nitrobenzene-d5* | | | | | *115* | *116* | | *31.0-160* | | | | |
| *(S) 2-Fluorobiphenyl* | | | | | *97.4* | *96.8* | | *48.0-148* | | | | |
| *(S) p-Terphenyl-d14* | | | | | *99.5* | *101* | | *37.0-146* | | | | |

# GLOSSARY OF TERMS

## Guide to Reading and Understanding Your Laboratory Report

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.

Results Disclaimer - Information that may be provided by the customer, and contained within this report, include Permit Limits, Project Name, Sample ID, Sample Matrix, Sample Preservation, Field Blanks, Field Spikes, Field Duplicates, On-Site Data, Sampling Collection Dates/Times, and Sampling Location. Results relate to the accuracy of this information provided, and as the samples are received.

## Abbreviations and Definitions

| | |
|---|---|
| MDL | Method Detection Limit. |
| ND | Not detected at the Reporting Limit (or MDL where applicable). |
| RDL | Reported Detection Limit. |
| Rec. | Recovery. |
| RPD | Relative Percent Difference. |
| SDG | Sample Delivery Group. |
| (S) | Surrogate (Surrogate Standard) - Analytes added to every blank, sample, Laboratory Control Sample/Duplicate and Matrix Spike/Duplicate; used to evaluate analytical efficiency by measuring recovery. Surrogates are not expected to be detected in all environmental media. |
| U | Not detected at the Reporting Limit (or MDL where applicable). |
| Analyte | The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported. |
| Dilution | If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor. |
| Limits | These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges. |
| Original Sample | The non-spiked sample in the prep batch used to determine the Relative Percent Difference (RPD) from a quality control sample. The Original Sample may not be included within the reported SDG. |
| Qualifier | This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable. |
| Result | The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state “ND” (Not Detected) or “BDL” (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte. |
| Uncertainty (Radiochemistry) | Confidence level of 2 sigma. |
| Case Narrative (Cn) | A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report. |
| Quality Control Summary (Qc) | This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material. |
| Sample Chain of Custody (Sc) | This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis. |
| Sample Results (Sr) | This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported. |
| Sample Summary (Ss) | This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis. |

| Qualifier | Description |
|---|---|
| J | The identification of the analyte is acceptable; the reported value is an estimate. |
| J1 | Surrogate recovery limits have been exceeded; values are outside upper control limits. |
| J3 | The associated batch QC was outside the established quality control range for precision. |

# ACCREDITATIONS & LOCATIONS

## Pace Analytical National 12065 Lebanon Rd Mount Juliet, TN 37122

| | | | |
|---|---|---|---|
| Alabama | 40660 | Nebraska | NE-OS-15-05 |
| Alaska | 17-026 | Nevada | TN000032021-1 |
| Arizona | AZ0612 | New Hampshire | 2975 |
| Arkansas | 88-0469 | New Jersey–NELAP | TN002 |
| California | 2932 | New Mexico [1] | TN00003 |
| Colorado | TN00003 | New York | 11742 |
| Connecticut | PH-0197 | North Carolina | Env375 |
| Florida | E87487 | North Carolina [1] | DW21704 |
| Georgia | NELAP | North Carolina [3] | 41 |
| Georgia [1] | 923 | North Dakota | R-140 |
| Idaho | TN00003 | Ohio–VAP | CL0069 |
| Illinois | 200008 | Oklahoma | 9915 |
| Indiana | C-TN-01 | Oregon | TN200002 |
| Iowa | 364 | Pennsylvania | 68-02979 |
| Kansas | E-10277 | Rhode Island | LAO000356 |
| Kentucky [1 6] | KY90010 | South Carolina | 84004002 |
| Kentucky [2] | 16 | South Dakota | n/a |
| Louisiana | AI30792 | Tennessee [1 4] | 2006 |
| Louisiana | LA018 | Texas | T104704245-20-18 |
| Maine | TN00003 | Texas [5] | LAB0152 |
| Maryland | 324 | Utah | TN000032021-11 |
| Massachusetts | M-TN003 | Vermont | VT2006 |
| Michigan | 9958 | Virginia | 110033 |
| Minnesota | 047-999-395 | Washington | C847 |
| Mississippi | TN00003 | West Virginia | 233 |
| Missouri | 340 | Wisconsin | 998093910 |
| Montana | CERT0086 | Wyoming | A2LA |
| A2LA – ISO 17025 | 1461.01 | AIHA-LAP,LLC EMLAP | 100789 |
| A2LA – ISO 17025 [5] | 1461.02 | DOD | 1461.01 |
| Canada | 1461.01 | USDA | P330-15-00234 |
| EPA–Crypto | TN00003 | | |

[1] Drinking Water [2] Underground Storage Tanks [3] Aquatic Toxicity [4] Chemical/Microbiological [5] Mold [6] Wastewater n/a Accreditation not applicable

* Not all certifications held by the laboratory are applicable to the results reported in the attached report.

* Accreditation is only applicable to the test methods specified on each scope of accreditation held by Pace Analytical.

Company Name/Address:
**Rio Grande Resources Corp**
219 S 2nd St
Raton, NM 87740

Billing Information:
Bruce Norquist
PO Box 1150
Grants , NM 87020

Pres Chk

Report to: **Eric Roads**

Email To: eroads@enganalytics.com;tdavis@enganalytics.

Project Description: Mt Taylor

City/State Collected: Grants, New Mexico

Please Circle: PT MT CT ET

Phone: 970-488-3111

Client Project # 111360

Lab Project # RIOGRAGNM-MTTAYLOR

Collected by (print): Tyler Davis

Site/Facility ID # —

P.O. # —

Collected by (signature): Tyler Davis

Quote # —

Immediately Packed on Ice N ___ Y ✓

**Rush?** (Lab MUST Be Notified)
___ Same Day ___ Five Day
___ Next Day ___ 5 Day (Rad Only)
___ Two Day ___ ~~10 Day (Rad Only)~~
___ Three Day

Date Results Needed

Analysis / Container / Preservative

Chain of Custody Page ___ of ___

Pace
PEOPLE ADVANCING SCIENCE

**MT JULIET, TN**
12065 Lebanon Rd Mount Juliet, TN 37122
Submitting a sample via this chain of custody constitutes acknowledgment and acceptance of the Pace Terms and Conditions found at: https://info.pacelabs.com/hubfs/pas-standard-terms.pdf

SDG # L1626538
H088
Ta

Acctnum: RIOGRAGNM
Template: T238214
Prelogin: P1026344
PM: 732 - Donna Eidson
PB: NG 9/22/23

Shipped Via: FedEX Ground

| Sample ID | Comp/Grab | Matrix * | Depth | Date | Time | No. of Cntrs | DROORGLVI 40mlAmb-HCl-BT | GRO 40mlAmb HCl | PAHSIMLVI 40mlAmb-NoPres-WT | SV8270PAH 4ozClr-NoPres | V8260BTEX 40mlAmb-HCl | V8260BTEX 40mlAmb/MeOH10ml/Syr | | | | | Remarks | Sample # (lab only) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MT-GW-TS781-DW10-100923-K3 | Grab | GW | 781 | 10-9-23 | 0928 | 9 | X | X | X | | X | | | | | | | -01 |
| MT-GW-TS781-DW10-100923-K2 | Grab | GW | 781 | 10-9-23 | 1003 | 9 | X | X | X | | X | | | | | | | -02 |
| MT-GW-TS781-DW10-100923- | Grab | GW | 781 | 10-9-23 | 1022 | 9 | X | X | X | | X | | | | | | | -03 |
| MT-GW-TS463-DW10-100923-K3 | Grab | GW | 463 | 10-9-23 | 1053 | 9 | X | X | X | | X | | | | | | | -04 |
| MT-GW-TS463-DW10-100923 | Grab | GW | 463 | 10-9-23 | 1223 | 9 | X | X | X | | X | | | | | | | -05 |
| MT-GW-TS961-DW8-100923-K3 | Grab | GW | 961 | 10-9-23 | 1450 | 9 | X | X | X | | X | | | | | | | -06 |
| MT-GW-TS961-DW8-100923-K1 | Grab | GW | 961 | 10-9-23 | 1558 | 9 | X | X | X | | X | | | | | | | -07 |
| MT-GW-TS961-DW8-100923 | Grab | GW | 961 | 10-9-23 | 1558 | 9 | X | X | X | | X | | | | | | | -08 |
| MT-GW-TS840-DW8-100923-K3 | Grab | GW | 840 | 10-9-23 | 1633 | 9 | X | X | X | | X | | | | | | | -09 |
| MT-GW-TS840-DW8-100423 | Grab | GW | 840 | 10-9-23 | 1724 | 9 | X | X | X | | X | | | | | | | -10 |

* Matrix:
SS - Soil AIR - Air F - Filter
GW - Groundwater B - Bioassay
WW - WasteWater
DW - Drinking Water
OT - Other_____

**Remarks:** Some samples had effervescence during sampling and developed air in bottle after filling

pH _____ Temp _____

Flow _____ Other _____

Samples returned via: __ UPS __ FedEx __ Courier _____

Tracking # 6841 8349 2618

**Sample Receipt Checklist**

| | | |
|---|---|---|
| COC Seal Present/Intact: | NP | Y N |
| COC Signed/Accurate: | | Y N |
| Bottles arrive intact: | | Y N |
| Correct bottles used: | | Y N |
| Sufficient volume sent: | | Y N |
| **If Applicable** | | |
| VOA Zero Headspace: | | Y N |
| Preservation Correct/Checked: | | Y N |
| RAD Screen <0.5 mR/hr: | | Y N |

| Relinquished by : (Signature) | Date: | Time: | Received by: (Signature) | Trip Blank Received: Yes / No (HCL / MeoH) TBR | Sample Receipt Checklist |
|---|---|---|---|---|---|
| | 10-12-2023 | 1709 | | 1 | |
| Relinquished by : (Signature) | Date: | Time: | Received by: (Signature) | Temp: DRAFT °C 2.7+0=2.1 | Bottles Received: 90 |
| Relinquished by : (Signature) | Date: | Time: | Received for lab by: (Signature) (18) | Date: 10/13/23 | Time: 0900 |

If preservation required by Login: Date/Time

Hold:

Condition: NCF / OK

## 10/14-NCF-L1666531 RIOGRAGNM

R5

**Time estimate:** oh **Time spent:** oh

**Members**

Hailey Melson (responsible) JVH John V Hawkins

Due on *18 October 2023 8:00 AM* for target *Done*

- [ ] Parameter(s) past holding time
- [ ] Temperature not in range
- [ ] Improper container type
- [ ] pH not in range
- [ ] Insufficient sample volume
- [ ] Sample is biphasic
- [x] Vials received with headspace
- [ ] Broken container
- [ ] Sufficient sample remains
- [ ] If broken container: Insufficient packing material around container
- [ ] If broken container: Insufficient packing material inside cooler
- [ ] If broken container: Improper handling by carrier:_____
- [ ] If broken container: Sample was frozen
- [ ] If broken container: Container lid not intact
- [ ] Client informed by Call
- [ ] Client informed by Email
- [ ] Client informed by Voicemail
- [x] Date/Time:_10-16-23__7:32_____
- [x] PM initials:_JVH_____
- [ ] Client Contact:_____

**Comments**

*Hailey Melson* *14 October 2023 10:09 AM*

For IDs: MT-GW-TS781-DW10-100923-, MT-GW-TS961-DW8-100923-K2, MT-GW-TS961-DW8-100923-, MT-GW-TS840-DW8-100923- all vials were received with headspace.

*John V Hawkins* *16 October 2023 7:33 AM*

Client noted on COC that they encountered effervesive during collection.


Proceed and qualify as needed.

*Hailey Melson* *17 October 2023 8:18 AM*

Done

# APPENDIX J

## Disposal Cell As-built Drawings





0 50 100 150 200 FT

GRAPHIC SCALE

AS-BUILT

## Key Map




NOTES

(1) CLAY LINER IN DISPOSAL CELL - CONSISTING OF 1' THICK COMPACTED CLAY LINER IN SHADED AREA. ELEVATIONS PER CSTI SURVEY IN AUGUST 2018. TOTAL SURFACE AREA OF LINER = 4.7 ACRES

(2) LINER COMPACTION TESTS PERFORMED BY NV 5 FROM JULY 2018 TO NOVEMBER 2018. (SEE LEGEND BELOW.)

## LEGEND

- 121 — CLAY LINER COMPACTION TEST LOCATION WITH TEST NUMBER
- 76 — SUBGRADE COMPACTION TEST LOCATION WITH TEST NUMBER
- CLAY LINER LOCATION
- CLAY LINER CONTOUR LINE ( TOP OF CLAY LINER)
- EXISTING GRADES CONTOUR LINE

1. THE TOPO LINES AND ELEVATIONS SHOWN ON THIS PLAN REFLECT THE FINAL GRADES ON THE SURFACE OF THE CLAY LINER OF THE DISPOSAL CELL. TOPO SHOWN BASED ON SURVEY IN AUGUST 2018 BY CSTI, LLC AND ADJUSTED ACCORDING TO FIELD OBSERVATIONS BY EL ENGINEERING, LLC.

EDWARD O. LOESCHER
NEW MEXICO
18125
PROFESSIONAL ENGINEER

| REV | DESCRIPTION | DATE | DRAWN BY | ENGINEER | APPROVED |
|---|---|---|---|---|---|
| AB | AS-BUILT DRAWING (2018) | 1-26-2021 | EL | EL | AK |
| | | | | | |
| | | | | | |
| | | | | | |

**RIO GRANDE RESOURCES CORP.**
**MOUNT TAYLOR MINE - *San Mateo, NM***

SHEET TITLE: DISPOSAL CELL CLAY LINER (AS-BUILT - AUGUST 2018)

Prepared By: Alan Kuhn Associates LLC

Drawn By: EL Engineering Services LLC


PRINT SIZE: B

SCALE: As Shown


SHEET NO. SW06-AB

DWG NO. GSSW-CB106-AB

AB




AA SW01AB SECTION AA - N/S SECTION THROUGH WASTE ROCK PILE AND DISPOSAL CELL (FEBRUARY 2021)




BB SW01AB SECTION BB - E/W SECTION THROUGH EXISTING WASTE ROCK PILE AND DISPOSAL CELL (FEBRUARY 2021)

AS-BUILT

NOTE: SITE TOPOGRAPHY BASED ON SURVEY DATA BYS3
DISPOSAL CELL SURVEY PERFORMED ON FEBRUARY 2, 2021.

0 30 60 90 120 FT
GRAPHIC SCALE


(VERTICAL SCALE = 2X HORIZONTAL)

EDWARD O. LOESCHER NEW MEXICO 18125 PROFESSIONAL ENGINEER


**RIO GRANDE RESOURCES CORP.**
MOUNT TAYLOR MINE - *San Mateo, NM*

SHEET TITLE: SECTIONS THROUGH THE DISPOSAL CELL (AS-BUILT FEBRUARY 2021)

| Prepared By: | Drawn By: | PRINT SIZE: | SHEET NO. | DWG NO. | |
|---|---|---|---|---|---|
| Alan Kuhn Associates LLC | EL Engineering Services LLC | B<br>SCALE: As Shown | SW02AB | GSSW-CB02-AB | AB |




AA / SW01AB SECTION AA - N/S SECTION THROUGH WASTE ROCK PILE AND DISPOSAL CELL
(FEBRUARY 2021)




BB / SW01AB SECTION BB - E/W SECTION THROUGH EXISTING WASTE ROCK PILE AND DISPOSAL CELL
(FEBRUARY 2021)

AS-BUILT

NOTE: SITE TOPOGRAPHY BASED ON SURVEY DATA BYS3
DISPOSAL CELL SURVEY PERFORMED ON FEBRUARY 2, 2021.

0 30 60 90 120 FT
GRAPHIC SCALE


(VERTICAL SCALE = 2X HORIZONTAL)

EDWARD O. LOESCHER
NEW MEXICO
18125
PROFESSIONAL ENGINEER

**RIO GRANDE RESOURCES CORP.**
**MOUNT TAYLOR MINE - *San Mateo, NM***

SHEET TITLE: SECTIONS THROUGH THE DISPOSAL CELL (AS-BUILT FEBRUARY 2021)

| Prepared By: | Drawn By: | PRINT SIZE: | SHEET NO. | DWG NO. | |
|---|---|---|---|---|---|
| Alan Kuhn Associates LLC | EL Engineering Services LLC | B<br>SCALE: As Shown | SW02AB | GSSW-CB02-AB | AB |




NOTES:

1. SOUTH STORM WATER POND WITH 2' THICK CLAY LINER
2. WASTE ROCK PILE AS OF DECEMBER 2019
3. WASTE ROCK PILE SLOPES = 5H TO 1V
4. WEST SLOPE = WASTE ROCK WITH 2' RADON BARRIER COVER SOILS.
5. SOUTH SLOPE = CONSTRUCTED WITH CLEAN SOILS
6. THE DISPOSAL CELL CONTOURS REFLECT THE TOP OF THE CONTAMINATED FILL AT THE END OF 2019. ADDITIONAL FILL AND THE RADON BARRIER CLAY COVER SOILS ARE PLACED IN 2020.
7. STORM DRAINAGE PIPES, MANHOLES
8. SERVICE ROADS
9. CONCRETE CHUTE
10. OVERFLOW PIPES = 2 -24" DIA.CMP PIPES
11. LAGOON DEWATERING WELLS.

LEGEND

- 0000 SPOT ELEVATIONS
- EXISTING CONTOURS
- SOUTH POND CONTOURS
- 2' INTERVAL CONTOURS
- 10' INTERVAL CONTOURS
- DRAINAGE PIPES
- EXTENTS OF 1' THICK CLAY LINER
- WASTE ROCK PILE LIMITS = 11.5 ACRES

NOTE: SITE TOPOGRAPHY BASED ON SURVEY DATA BY CSTI.
DISPOSAL CELL SURVEY PERFORMED ON DECEMBER 06, 2019.
CONTOUR INTERVALS = 2' VERTICAL.


0 75 150 225 300 FT
GRAPHIC SCALE

AS-BUILT

**RIO GRANDE RESOURCES CORP.**
MOUNT TAYLOR MINE - *San Mateo, NM*

SHEET TITLE: WASTE ROCK PILE / DISPOSAL CELL (AS-BUILT DECEMBER 2019)

| Prepared By: | Drawn By: | PRINT SIZE: | SHEET NO. | DWG NO. | |
|---|---|---|---|---|---|
| Alan Kuhn Associates LLC | EL Engineering Services LLC | B<br>SCALE: As Shown | SW01-AB | GSSW-CB101-AB | AB |




1. THE TOPO LINES (1' CONTOURS) AND ELEVATIONS SHOWN ON THIS PLAN REFLECT THE GRADES OF THE WASTE ROCK PILE / DISPOSAL CELL ON FEBRUARY 2, 2021. THE BACKGROUND PHOTO AND TOPOGRAPHIC INFORMATION IS BASED ON THE DRONE SURVEY BY S3 SURVEYORS DATED 2-2-2021.


EDWARD O. LOESCHER NEW MEXICO 18125 PROFESSIONAL ENGINEER

AS-BUILT

**RIO GRANDE RESOURCES CORP.**
MOUNT TAYLOR MINE - *San Mateo, NM*

SHEET TITLE: WASTE ROCK PILE / DISPOSAL CELL AS-BUILT - FEBRUARY 2021

| Prepared By: | Drawn By: | PRINT SIZE: | SHEET NO. | DWG NO. | |
|---|---|---|---|---|---|
| Alan Kuhn Associates LLC | EL Engineering Services LLC | B<br>SCALE: As Shown | SW01-AB | GSSW-CB101-AB | AB |




## NOTES AND LEGEND:

1. SOUTH STORM WATER POND - CLEAN SOIL COVERED WITH 2' THICK CLAY LINER AND 6" SOIL PROTECTIVE COVER.
2. LOWER WEST AND NORTH SLOPES - WASTE ROCK COVERED WITH 2' THICK CLAY RADON BARRIER AND 12" LOAM GROWTH MEDIA.
3. LOWER SOUTH SLOPE - CONSTRUCTED WITH CLEAN SOILS.
4. UPPER SLOPES - CONTAMINATED SOILS COVERED WITH 2' THICK CLAY RADON BARRIER AND 18" LOAM GROWTH MEDIA.
5. UPPER EAST SLOPE - CONTAMINATED SOILS COVERED WITH 6" THICK CLAY.
6. DRAINAGE BENCH - 2' THICK CLAY RADON BARRIER AND LOAM GROWTH MEDIA OF VARYING THICKNESS.
7. RIP RAP - 9" TO 12" THICK - WIDTH VARIES - ARMOR FOR DRAINAGE SWALE
8. ACCESS RAMPS - 2' THICK CLAY RADON BARRIER AND 6" ROAD GRAVEL COVER.
9. FUTURE TOE OF RAMP OUTLINE.
10. CLAY RADON BARRIER ENDS AT STATION 1+60.
11. RAMP GRADING ENDS AT STATION 2+00.
12. LOWER RIP RAP CHANNEL ENDS AT STATION 8+20
13. LOAM GROWTH MEDIA ON LOWER WEST SLOPE ENDS AT STATION 6+60

1. THE TOPO LINES (1' CONTOURS) AND ELEVATIONS SHOWN ON THIS PLAN REFLECT THE GRADES OF THE WASTE ROCK PILE / DISPOSAL CELL ON FEBRUARY 2, 2021. THE BACKGROUND PHOTO AND TOPOGRAPHIC INFORMATION IS BASED ON THE DRONE SURVEY BY S3 SURVEYORS DATED 2-2-2021.

AS-BUILT

EDWARD O. LOESCHER NEW MEXICO 18125 PROFESSIONAL ENGINEER

**RIO GRANDE RESOURCES CORP.**
**MOUNT TAYLOR MINE - *San Mateo, NM***

SHEET TITLE: WASTE ROCK PILE / DISPOSAL CELL AS-BUILT - FEBRUARY 2021

| Prepared By: | Drawn By: | PRINT SIZE: | SHEET NO. | DWG NO. | |
|---|---|---|---|---|---|
| Alan Kuhn Associates LLC | EL Engineering Services LLC | B<br>SCALE: As Shown | SW01-AB | GSSW-CB101-AB | AB |

# APPENDIX K

## Expanded Disposal Cell Design Report

# Expanded Disposal Cell Design

# Mt. Taylor Mine

# Existing Mine Permit No. CI002RE

*Prepared for:*

**Rio Grande Resources Corporation**

*P.O. Box 1150*

*Grants, NM 87020*

*Prepared by:*

Engineering Analytics, Inc.
Now Part of MacKay

1600 Specht Point Road, Suite 209
Fort Collins, Colorado 80525
(970) 488-3111
Fax (970) 488-3112

Project No. 111360

November 27, 2025
Rev 1 – September 8, 2026

## TABLE OF CONTENTS

**1.0 INTRODUCTION ..... 1**
**2.0 CURRENT SITE CONDITIONS ..... 2**
2.1 Location and Land Use ..... 2
2.2 Geology ..... 2
2.3 Results of January 2025 Field Investigation ..... 4
2.4 Results of Laboratory Testing for the Site ..... 5
2.4.1 Historical Laboratory Testing ..... 5
2.4.2 Laboratory Testing Completed in 2025 ..... 5
2.5 Seismicity ..... 6
2.6 Climate ..... 6
**3.0 DESIGN CRITERIA ..... 7**
**4.0 EXPANDED DISPOSAL CELL DESIGN ..... 9**
4.1 General ..... 9
4.2 Description of Cover ..... 10
4.3 Frost Penetration Analysis ..... 10
4.4 Radon Attenuation ..... 11
4.4.1 Regulatory Standard ..... 11
4.4.2 Cover System Configuration ..... 11
4.4.3 Model Description ..... 11
4.4.4 Input Parameters ..... 11
4.4.5 Model Results ..... 13
4.4.6 Sensitivity Simulation ..... 14
4.5 Biointrusion ..... 15
4.5.1 Regulatory Framework ..... 15
4.5.2 Role of Vegetation in Store-and-Release Cover Performance ..... 16
4.5.3 Cover System Design Measures Against Biointrusion ..... 16
4.5.4 Post-Closure Monitoring and Adaptive Management ..... 17
4.6 Infiltration Analysis ..... 17
4.6.1 General ..... 17

4.6.2 Method of Analysis ..... 17
4.6.3 Parameters Used for Analysis ..... 18
4.6.4 Water Balance Components and Percolation Estimation ..... 19
4.6.5 Copper Rule Store-and-Release Compliance ..... 21
4.7 Settlement Analysis ..... 22
4.8 Slope Stability Analysis ..... 23
4.8.1 General ..... 23
4.8.2 Method of Analysis ..... 23
4.8.3 Material Properties ..... 23
4.8.4 Results of Analysis ..... 24
4.9 Surface Water Hydrology and Erosion Protection ..... 24
4.9.1 General ..... 24
4.9.2 Design Storm ..... 25
4.9.3 Rock Mulch Cover Design ..... 25
4.9.4 Wind Erosion Analysis ..... 30
4.9.5 Summary ..... 30
4.10 Borrow Source Location and Characterization ..... 32
4.10.1 Borrow Source Locations ..... 32
4.10.2 Borrow Source Characterization ..... 32
4.11 Borrow Source Quantities ..... 32
4.12 Revegetation of Disturbed Areas ..... 34
4.13 Material Placement ..... 35
**5.0 CONCLUSIONS ..... 37**
5.1 General ..... 37
5.2 Cover System Configuration ..... 37
5.3 Frost Depth and Thermal Protection ..... 37
5.4 Radon Attenuation ..... 37
5.5 Biointrusion ..... 38
5.6 Infiltration, Water Balance, and Copper Rule Compliance ..... 38
5.7 Surface Water Hydrology and Erosion Protection ..... 39

5.8 Slope Stability, Borrow Sources, Revegetation, and Material Placement ..... 40
5.9 Regulatory Compliance Summary ..... 40
**6.0 REFERENCES ..... 41**

## LIST OF TABLES

Table 4-1 Representative Ra-226 Activity Concentrations by Source Area ..... 12
Table 4-2 Radon Attenuation Model Input and Results ..... 14
Table 4-3 Results of Radon Sensitivity Analysis ..... 15
Table 4-4 Monthly Climate Water Balance ..... 18
Table 4-5 Soil and Climate Parameters Used for the Infiltration Analysis ..... 19
Table 4-6 Annual Water Balance Summary ..... 21
Table 4-7 Material Properties Used for Stability Assessment ..... 24
Table 4-8 Rock Mulch Sizing Results ..... 26
Table 4-9 Rock Mulch Admixture Gradation ..... 30
Table 4-10 Surface Water and Erosion Protection Design Summary ..... 31
Table 4-11 Proposed Seed Mix and Application Rates ..... 34

## LIST OF FIGURES

Figure 2-1 Site Location Plan
Figure 2-2 Detailed Site Plan
Figure 2-3 Test Pit Location Map
Figure 4-1 Cover Design Profile
Figure 4-2 Infiltration Analysis Model Profile
Figure 4-3 Section used for the Stability Assessment
Figure 4-4 Results of the Slope Stability Analyses
Figure 4-5 Results of the Pseudo-Seismic Slope Stability Analysis
Figure 4-6 Location of Borrow Sources

## LIST OF APPENDICES

Appendix A Test Pit Logs for 2025 Field Investigation
Appendix B Results of Geotechnical Laboratory Testing for Mt. Taylor Disposal Cell
Appendix C Seismic Hazard Analysis – Mt. Taylor
Appendix D Technical Memorandum – Frost Depth Analysis
Appendix E Technical Memorandum – Radon Cover
Appendix F Design Climate Data Analysis
Appendix G Selected Results of Infiltration Analysis
Appendix H Slope Stability Analysis
Appendix I Surface Water Hydrology and Erosion Protection Calculations
Appendix J Evaluation of Diesel Placement in Proposed Expanded Disposal Cell

## ABBREVIATIONS

| | |
|---|---|
| ASTM | American Society for Testing and Materials |
| bgs | Below Ground Surface |
| CCD | Counter-current Decantation |
| cy | Cubic Yards |
| DBS&A | Daniel B. Stephens & Associates, Inc. |
| DQO | Data Quality Objectives |
| EA | Engineering Analytics, Inc. |
| EPA | Environmental Protection Agency |
| g | The unit for peak ground acceleration, the acceleration due to Earth's gravity |
| IPCC | Intergovernmental Panel on Climate Change |
| HDPE | High Density Polyethylene |
| K | Hydraulic Conductivity |
| MARSSIM | Multi-Agency Radiation Survey and Site Investigation Manual |
| MSL | Mean Sea Level |
| NOAA | National Oceanic and Atmospheric Administration |
| NRC | Nuclear Regulatory Commission |
| pcf | Pounds per Cubic Foot |
| pCi | picoCuries |
| PI | Plasticity Index |
| QAPP | Quality Assurance Project Plan |
| SWCC | Soil Water Characteristic Curves |
| SOPs | Standard Operating Procedures |
| TEDE | Total Effective Dose Equivalent |
| UMTRCA | Uranium Mill Tailings Radiation Control Act |
| USCS | Unified Soil Classification System |
| USGS | United States Geological Survey |
| UDEQ/DWMRC | Utah Department of Environmental Quality, Division of Waste Management and Radiation Control |
| DRC | Division of Radiation Control |

# 1.0 INTRODUCTION

This report presents a comprehensive, regulator-ready engineering plan for the expansion of the permanent disposal cell at the Mt. Taylor Uranium Mine facility, located in Cibola County, New Mexico. The primary objective of this reclamation undertaking is to ensure the safe, efficient, and centralized containment of waste streams generated during historic mining operations, extended standby periods, and recent closure activities. These waste streams include legacy radioactive materials, radiologically contaminated soils, and localized volumes of non-hazardous diesel-impacted soils that require permanent engineered isolation. The proposed expansion is designed to comply with applicable state and federal regulations and to provide long-term protection of human health and the surrounding environment. The key regulatory frameworks governing this design include standards issued by the U.S. Nuclear Regulatory Commission (NRC), the U.S. Environmental Protection Agency (EPA), and the New Mexico Environment Department (NMED).

The technical foundation for this disposal cell expansion centers on an optimized, multi-layered engineered cover system designed to perform effectively in a semi-arid climate. The cover system relies on locally sourced clay borrow materials, as characterized during the January 2025 field investigation, to form a low-permeability radon barrier, overlain by protective soil and erosion-resistant rock mulch layers. This revision (Rev 1) incorporates three supplemental technical analyses completed subsequent to the original report: (1) a cover optimization memorandum evaluating reduction of overall cover thickness through revised frost depth estimation, elimination of the capillary layer, and radon sensitivity analysis; (2) a regulatory evaluation of co-placement of diesel-impacted and radiologically elevated soils within the expanded cell; and (3) a statistical comparison of 2018–2025 on-site climate data to historical and regional design-support datasets confirming the continued validity of design-basis climate inputs. These analyses are fully integrated into the relevant sections of this report.

Earthwork and grading activities will reshape the site to optimize drainage, limit water infiltration, and establish a stable base for the expanded disposal cell. Erosion control strategies embedded within the expansion plan include rock mulch facing, stormwater diversion channels, and controlled surface grades to reduce runoff concentration. The design considers the site's stratigraphy and draws on recent geotechnical data to confirm the appropriateness of selected construction materials, containment approaches, and long-term performance assumptions.

Engineering Analytics, Inc. (EA) prepared this report for Rio Grande Resources (RGR) to integrate site characterization, regulatory requirements, recent field and laboratory findings, and supplemental technical evaluations into a cohesive engineering basis for the proposed disposal cell expansion. The following sections present supporting analyses, modeling results, design criteria, and implementation recommendations needed to guide agency review, permitting, construction planning, quality assurance, sequencing decisions, construction documentation, and execution of the reclamation work.

# 2.0 CURRENT SITE CONDITIONS

## 2.1 Location and Land Use

The Mt. Taylor uranium mine is located approximately 25 miles northeast of Grants, New Mexico, in Cibola County. The mine was initially developed by Gulf Mineral Resources (Gulf) in 1971. Figure 2-1 shows the site location plan. Following surface drilling, several ore bodies were identified across a span of over seven miles, with estimated reserves totaling 120 million pounds of uranium oxide (Alief and Kern, 1989). Two shafts, measuring 24 feet and 14 feet in diameter, were constructed to access ore deposits located 3,100 to 3,200 feet beneath the surface within the Westwater Canyon Member of the Morrison Formation. Figure 2-2 shows the detailed site plan. In the 1970s, wells were installed to extract groundwater for mining operations.

Mining activities commenced in 1980 but ceased in September 1982 due to unfavorable market conditions. Ownership transferred to Chevron Resources Company following a merger with Gulf in 1985, leading to the resumption of mining from 1986 to 1990 using standard underground room-and-pillar techniques. During this period, approximately 675,000 tons of uranium ore and about 698,000 tons of waste rock were extracted.

In 1991, Rio Grande Resources Corporation (RGR) acquired the site but did not resume mining operations owing to unfavorable market conditions. Beginning in 2019, RGR initiated mine closure and land reclamation efforts under the oversight of NMED and the Energy, Minerals, and Natural Resources Department. Prior to closure, surface infrastructure at the site included two shafts, an ore stockpile, a waste rock pile, stormwater retention ponds, a sewage treatment plant, an ion exchange facility, eight clay-lined treatment ponds, and various ancillary support structures.

## 2.2 Geology

The geologic setting of the mine has been described in detail in the Baseline Study prepared by New Mexico Environmental Institute (NMEI) in 1974 (NMEI, 1974) and the Site Assessment submitted in 1994 (RGR, 1994a). Deposits of Quaternary age rock and soil exposed in the area consist of unconsolidated talus, alluvial, and eolian sediments. Extensive areas on the slopes adjacent to the high basalt-covered mesas to the south, southwest, and east of the mine are covered by talus, landslides, and black lava blocks. Beneath the valleys and lower topographic slopes, clay, silt, sand, and gravel alluvial lenses are present (NMEI, 1974).

The deepest geologic formation encountered in the Mount Taylor mine shaft is the Jurassic-age Morrison Formation. This formation consists, in ascending order, of the Recapture Creek, Westwater Canyon, and Brushy Basin members. The Recapture Creek member occurs at a depth between 3,240 and 3,300 feet below ground surface (ft bgs) in the mine shaft pilot well. This member grades vertically into the overlying Westwater Canyon member. The transition to the Westwater Canyon member marks a change in lithology, and its thickness varies due to lensing and vertical gradations into both the Brushy Basin and Recapture Creek members. At the mine site, the Westwater Canyon member is divided into Upper and Lower units by a persistent shale layer. The lower sandstone unit is 60 to 70 feet thick, while the upper sandstone unit measures about 100 feet thick in the mine shaft area. These sandstone units contain most of the uranium ore

reserves of mine. Above the Westwater Canyon member, the Brushy Basin member conformably overlies and interfingers with it. The Brushy Basin is approximately 80 feet thick and consists of shales and claystones at the mine shaft.

Above the ore-bearing Morrison Formation is a sequence of sedimentary units approximately 2,950 feet thick. The first of these is the Dakota Sandstone, which unconformably overlies the Brushy Basin member. The Dakota Sandstone is 50 to 60 feet thick and is only slightly mineralized, thus not mined at Mt. Taylor Mine. The Dakota Sandstone conformably intertongues with the overlying Mancos Shale.

Next in the stratigraphic sequence is the Mancos Shale, which is 900 feet thick and composed chiefly of dark-gray, calcareous, marine clay shale. This unit also contains interspersed sandstone beds. The lowermost portion of the Mancos Shale includes three sandstone units known as the Upper, Middle, and Lower Tres Hermanos Sandstones, which are 72 feet, 45 feet, and 118 feet thick, respectively, at the mine shaft pilot well (McGlothin, 1972).

Continuing upward, the Mancos Shale extends to the base of the Gallup Sandstone at approximately 2,050 feet bgs. The Gallup Sandstone consists of two separate sandstone units divided by 130 feet of dark gray shale. Overlying the Gallup Sandstone is the Crevasse Canyon Formation, which includes, in ascending order, the Dilco Coal, the Stray Sand, the Mulatto Tongue of the Mancos Shale, the Dalton Sandstone, and the Gibson Coal. The Point Lookout Formation conformably overlies the Crevasse Canyon Formation.

Above the Crevasse Canyon Formation lies the Point Lookout Formation, which is the basal unit of the Mesa Verde Group. This formation is typically encountered between 700 and 850 feet bgs at the mine site. Near the mine, it is separated into two units by the Satan Tongue of the Mancos Shale. The upper unit, referred to as the Point Lookout Sandstone, is the main body and is typically 110 to 130 feet thick. The lower unit is the Lower Hosta Tongue, a transgressive marine beach sandstone that is between 80 and 100 feet thick. Along the southern margin of the basin, both units merge into a combined unit approximately 250 feet thick. The Lower Hosta Tongue is of limited areal extent, pinching out 30 miles northeast of its outcrop. The Point Lookout Sandstone comprises thick- to very thick-bedded, very fine- to medium-grained, locally cross-bedded sandstones. Notably, the Point Lookout aquifer provides the domestic water supply for both the mine and the Village of San Mateo.

The uppermost geological unit present at the mine is the Menefee Formation. It forms uneven slopes around the mine and near the Village of San Mateo. The Menefee Formation is composed of interbedded pale yellowish-brown siltstone, fine to medium-grained sandstone, gray shale, carbonaceous shale, and thin coal beds. Its thickness in the mine shaft is approximately 767 feet (NMEI, 1974). Mine water treatment pond basins were excavated into the Menefee Formation, and both the manway/vent and production shafts are collared in this unit.

The stratigraphic complexity at the site affects groundwater flow, material properties, and mine closure planning. Aquifers like the Point Lookout Sandstone supply water to the area and are separated from deeper systems by low-permeability units such as Crevasse Canyon and Mancos

Shale, which function as natural barriers against contamination. The Menefee Formation, containing various sediments and coal beds, impacts surface facility stability and provides material for disposal cell expansion, with its clay-rich layers important for cover design to limit infiltration and erosion.

Accurate geological profiling is vital for selecting construction materials, designing effective waste containment strategies, and ensuring regulatory compliance. Upcoming sections will detail recent field studies and lab tests that further inform expansion plans.

## 2.3 Results of January 2025 Field Investigation

Engineering Analytics excavated 24 test pits and collected samples from three proposed borrow sites to assess clay material for disposal cell cover. In January 2025, EA used a CAT backhoe to excavate the pits (A-1 to A-6, B-1 to B-5, and C-1 to C-13), each to a depth of approximately 6 feet. Figure 2-3 shows the test pit locations. The test pit logs are provided in Appendix A. Subsurface conditions included:

**Topsoil:**
The topsoil thicknesses at the site range from 2 inches to 6 inches. The topsoil consists of organics, loose sand, and is very dry.

**Sand:**
The topsoil is underlain by a sand layer at all the test pit locations except at locations A-6, B-1, B-2, C-2, and C-8. Silty sand underlies the topsoil at location A-6, sand and gravel at location B-1, and clay at location B-2. Sandy clay lies beneath the topsoil at C-2 and C-8 test-pit locations. The sand layer is loose to very loose, frozen at some locations, dry to moist, and fine in texture. The termination depths of the sand layer range from 3 feet to the excavation depth of 6 feet.

**Sand and Gravel:**
Sand and gravel layer underlies the topsoil at test pit location B-1. This layer is loose, dry, and non-plastic. This layer extends to a depth of three feet at the test pit location. This layer is only encountered in test-pit location B-1.

**Silty Sand:**
At test pit location A-6, a silty sand layer underlies the topsoil and extends to a depth of 4 feet. This layer is moist, loose, and very fine in texture.

**Clay:**
A thin layer of clay underlies the topsoil at test pit location B-2. The clay is stiff, low plastic, and moist. The clay layer extends to a depth of one foot and is found frozen during the investigation.

**Sandy Clay:**
Sandy clay is present at most test pit sites, except A-3, A-6, B-2, B-3, B-5, and C-12. This material is stiff to very stiff, dry, and lies below the sand layer at depths of 3 to 4 feet, extending to 6 feet. At C-13, there is no sand layer, and at C-4, sandy clay ends at 5 feet underlain by sand. The absence of sandy clay at A-3, A-6, B-2, B-3, B-5, and C-12 may be due to limited excavation depth.

**Siltstone:**
Siltstone is present beneath the silty sand layer at test pit location A-6. The siltstone is dry, fine, and contains silt fragments. The siltstone extends from a depth of 4 feet to the termination depth of the excavation at 6 feet.

## 2.4 Results of Laboratory Testing for the Site

### 2.4.1 *Historical Laboratory Testing*

Engineering Analytics personnel conducted a review of previous laboratory testing associated with the site and supplemented these efforts with additional laboratory analyses to support the disposal cell expansion design. Both the historical data and the tests performed by EA in 2025 formed the basis for the analysis undertaken for the disposal cell expansion design.

### 2.4.2 *Laboratory Testing Completed in 2025*

Selected material samples from Borrow Sources A, B, and C (see Figure 2.3) underwent laboratory testing to determine their physical and geotechnical properties for the disposal cell expansion design. Tests included water content, Atterberg limits, standard Proctor compaction, soil water characteristics, and consolidated undrained triaxial tests. EA performed and summarized these tests below. Test-pit logs and laboratory reports are provided in Appendices A and Appendix B, respectively.

**Water Content:** Measurements of water content and dry density were conducted on selected samples in accordance with ASTM test methods D2216 and D2937, respectively. The water content of the tested samples ranged from 4.6% to 24.1%. For the clay, silty clay, and sandy clay samples, the moisture content ranged from 6.8% to 24.1%, with an average of 11.7%, and a mode of 9.7%.

**Atterberg Limits:** Atterberg limits were determined for selected samples in accordance with ASTM test method D4318. These measurements facilitate the classification of soil. Based on the Unified Soil Classification System (USCS), a total of 48 samples were analyzed: nine were identified as non-plastic (NP), 29 as low plasticity clay (CL), two as high plasticity clay (CH), three as low plasticity silt (ML), and five as low plasticity clay or silt (CL-ML).

**Standard Proctor Compaction Tests:** Eight Standard Proctor Compaction Tests were conducted following ASTM test method D698. For the clay, silty clay, and sandy clay samples, maximum dry density ranged from 89.8 to 110.4 pcf, with optimum moisture content (OMC) varying between 16.1% and 26.6%. Sand soil specimens exhibited maximum dry densities from 111.1 to 117.6 pcf, with corresponding OMC values ranging from 12.2% to 15%.

**Consolidated Undrained (CU) Triaxial Tests:** EA performed two CU triaxial tests with pore pressure measurements per ASTM D4767 at its certified lab. This method assesses strength and stress-strain properties of saturated cohesive soil specimens by isotropic consolidation followed by undrained axial compression at a constant strain rate, allowing calculation of total and effective stresses from measured axial load, deformation, and pore-water pressure. The tests results on

remolded clay samples showed an average effective friction angle of 31° with zero effective cohesion.

## 2.5 Seismicity

EA conducted a seismic hazard analysis for RGR pertaining to the Mt. Taylor Uranium Mine. The objective was to determine peak horizontal ground acceleration (PGA) for stability assessments, specifically focusing on a 10,000-year return period. The site is located within the Colorado Plateau, which exhibits structural stability, though it is proximate to tectonically active regions including the Rio Grande Rift and the Jemez Lineament. The historical record, spanning 1568 to 2025, indicates low seismic activity, with only a few moderate events occurring near the site. The largest recorded earthquake had a magnitude of 5.9 and was situated approximately 160 km away, while the nearest significant event (Mw 4.08) occurred 13 km from the facility.

Both deterministic and probabilistic analyses were performed. The deterministic approach identified a maximum PGA of 0.09g from a hypothetical Maximum Credible Earthquake (MCE 6.3) located 15.1 km from the site. The probabilistic analysis calculated a mean PGA of 0.21g for the 10,000-year return period. Based on this value, a pseudostatic seismic coefficient equal to two-thirds of the PGA (0.14g) was applied in seismic evaluations of the disposal cell. The seismic hazard at Mt. Taylor Mine is assessed as relatively low, with background seismicity representing the primary risk. Appendix C presents the results of the seismic hazard analysis.

## 2.6 Climate

The Mt. Taylor Mine is located on the southwestern slope of Mount Taylor in the San Mateo area of west-central New Mexico at an elevation of approximately 7,400 feet above mean sea level. The site lies within the Colorado Plateau and experiences a cold semi-arid climate characterized by low humidity, high solar radiation, large daily temperature swings, and a pronounced July to September monsoon. These conditions support an evapotranspiration-based cover design because annual atmospheric moisture demand substantially exceeds precipitation.

Continuous meteorological data have been collected at the San Mateo on-site station (elevation ~7,400 ft) since October 2017. EA compared the 2018 to 2025 on-site record to two long-term regional datasets: (1) the Gallup Municipal Airport climate normal (elevation ~6,500 ft, ~45 miles northwest of the mine), which represents the long-term semi-arid regional rainfall regime, and (2) the Rice Park SNOTEL station (elevation ~8,900 ft, ~20 miles northeast of the mine), which represents high-elevation winter hydrology including snow water equivalent (SWE), snowmelt timing, and freeze-thaw behavior. The stations differ in elevation, climate regime, and hydrologic processes, which explains the differing mean annual precipitation (MAP) values: 11.65 inches at Gallup, 10.02 inches at San Mateo, and approximately 6.5 inches at Rice Park, where snowpack sublimation and wind redistribution reduce measured precipitation. Despite these differences, statistical testing (Appendix F) showed no significant departures ($p > 0.05$) in precipitation, temperature, or air freezing index (AFI) between the San Mateo record and the broader historical population, confirming that the site data fall within normal regional variability.

Because the on-site San Mateo meteorological data is both site-specific and statistically consistent with long-term regional conditions, it is used as the primary dataset for the water balance, infiltration, and Copper Rule analyses. Its daily resolution record captures the monsoon-driven wetting season, recent warming trends, and the actual hydrologic inputs influencing the cover today, while remaining conservative relative to Gallup's higher long-term MAP. Gallup provides the stable 30-year precipitation benchmark needed to anchor the short site record and prevent anomalous wet or dry bias in design assumptions. Rice Park, although drier, supplies long-term winter hydrology, particularly SWE, snowmelt infiltration pulses, and freeze-thaw behavior that on-site San Mateo has not measured. For this reason, the AFI used in design is based on Rice Park projections and historical distributions, ensuring a conservative frost penetration estimate. The design-basis AFI of 927.5 degree-days (200-year return period) exceeds the historical maximum by approximately 18 percent, confirming that frost-related cover thickness and radon-barrier protection remain conservatively defined.

Mean annual precipitation at the site is approximately 10 inches, while estimated potential evapotranspiration is 26.45 inches, producing an annual moisture deficit of 16.44 inches and an aridity index of 0.38. Monthly (potential evapotranspiration) PET peaks in July at 5.26 inches, coinciding with peak monsoon precipitation of 2.05 inches.

## 3.0 DESIGN CRITERIA

The design criteria for the expanded disposal cell are limited to the regulatory requirements, standards, and performance objectives that govern long-term containment of uranium mine-related waste materials. The criteria establish what the disposal cell must achieve and the technical requirements that must be satisfied; they do not describe the selected cover configuration or evaluate the adequacy of the design. The applicable objectives include protection of human health and the environment, long-term stabilization of waste materials, control of radiological and non-radiological releases, protection of groundwater and surface water, resistance to erosion and intrusion, and maintenance of physical stability throughout the required performance period.

The principal federal requirements are established by the Uranium Mill Tailings Radiation Control Act (UMTRCA), EPA standards in 40 CFR Part 192, and NRC requirements in 10 CFR Part 40, Appendix A. These regulations require disposal systems for uranium byproduct materials to provide effective stabilization and control for 1,000 years to the extent reasonably achievable, and in any case for at least 200 years. They also require reclamation plans to demonstrate compliance with applicable technical criteria for siting, decommissioning, reclamation, groundwater protection, radon control, long-term surveillance, and protection of public health, safety, and the environment.

Radiological performance criteria require control of residual radioactive materials and limitation of radon-222 emissions from the disposal cell surface. The applicable radon-222 flux performance objective is 20 $pCi/m^2/s$, consistent with the uranium mill tailings standards and NRC implementation requirements. The disposal cell must also prevent releases that would result in unacceptable radiation exposure to the public or workers and must support compliance with applicable radiation protection standards during closure, post-closure, and long-term surveillance.

Groundwater and surface-water performance criteria require the disposal cell to limit contaminant migration and avoid degradation of water resources beyond applicable regulatory standards. The criteria include minimizing net infiltration through the cover, preventing sustained ponding on the reclaimed surface, controlling contact between precipitation and waste materials, and managing runoff so that erosion, sediment transport, and contaminant release are limited. Applicable groundwater protection standards include the requirements of 40 CFR Part 192 and the groundwater-related criteria incorporated into 10 CFR Part 40, Appendix A.

Geotechnical and physical-stability criteria require the disposal cell to remain stable under static, seismic, settlement, and long-term degradation conditions. The relevant performance objectives include maintaining stable slopes, limiting differential settlement and cracking, avoiding conditions that could compromise containment, and accounting for site-specific geology, topography, hydrology, and meteorology. Stability evaluations must use appropriate design loads, material properties, and factors of safety consistent with applicable NRC guidance, accepted geotechnical practice, and site-specific hazard information.

Erosion-control, biointrusion, and cover-integrity criteria require the disposal cell to resist wind and water erosion, discourage plant-root and animal intrusion into containment layers, and maintain protective functions for the required performance period. Technical guidance for uranium tailings reclamation, including NRC standard review guidance and erosion-protection guidance, establishes expectations for long-term geomorphic stability, surface protection, drainage performance, material durability, and maintenance needs. Where rock armor is used for erosion protection, the rock layer thickness should be no less than the spherical diameter of the upper-limit $D_{100}$ rock or at least 1.5 times the diameter of the upper-limit $D_{50}$ rock, whichever is larger.

DOE (1988) expanded Sherard's criteria with these additions:

- Filter material should pass a 3-in. (76.2-mm) sieve to avoid particle segregation and bridging during installation; smaller maximum sizes may be used if needed. Filters should not have over 5% passing the No. 200 mesh sieve to prevent excess fine movement within the filter.
- Filter material needs to be well graded throughout.
- Filters for gap-graded bases may need finer grading than Sherard's basic criteria suggest.
- The minimum filter thickness should be 6 inches (152.4 mm) to aid placement.

Cover water-balance criteria should be evaluated against the overall performance objective of minimizing net percolation and protecting groundwater. For uranium-related disposal, the governing criteria remain the federal uranium tailings requirements and approved permit conditions. The New Mexico Copper Rule, 20.6.7.33 NMAC, is not directly applicable to a uranium mine disposal cell; however, it provides a relevant state benchmark for store-and-release cover performance at mine facilities with potential leachate generation. The rule requires, for covered copper mine units, an earthen store-and-release cover suitable for vegetation, erosion-resistant performance, and percolation control, generally including 36 inches of earthen material unless a reduced or alternative cover is justified.

The New Mexico Copper Rule (N.M. Code R. § 20.6.7.33) outlines specific cover thickness requirements for the closure of copper mine facilities, summarized as follows:

- Upon closure, waste rock piles, leach stockpiles, tailing impoundments, and other units with potential for leachate generation must be covered using a store-and-release earthen cover system.
- The required cover must consist of 36 inches (3 feet) of earthen material suitable for sustaining vegetation without ongoing supplementation and featuring erosion-resistant properties.
- The system should minimize net percolation by retaining at least 95% of long-term average winter precipitation or 35% of long-term average summer precipitation, whichever is higher.
- Erosion rates should be comparable to those found on stable slopes in the surrounding landscape.

Cover thickness may be reduced when placed over lined units, or if an alternative design offers equivalent or improved groundwater protection. Such alternatives necessitate a robust modeling study, an appropriate performance monitoring plan, and independent third-party review.

Proper compaction of waste and cover materials is necessary to avoid settlement and maintain structure. Quality control procedures (like moisture-density tests) are performed during construction. CQC and CQA plans will be submitted to NMED for approval a minimum of 30 days prior to beginning of construction of the clay liner. Within 60 days following completion of construction of the clay liner, a CQA report and as-built plans shall be submitted to NMED. Designs must allow for monitoring and addressing subsidence or deformation over time, and all elements should be chosen for long-term chemical and physical stability suitable for local conditions. Finally, the cell must remain accessible for periodic inspection, maintenance, and environmental monitoring.

# 4.0 EXPANDED DISPOSAL CELL DESIGN

## 4.1 General

Reclamation of the waste rock and associated cleanup material is organized into two distinct phases, each designed to promote structural stability, effective drainage, and long-term environmental protection.

This report presents an optimized cover system based on updated analyses completed in July 2026. The optimized cover system consists of a three-layer configuration totaling 52 inches: 12 inches of rock mulch, 28 inches of on-site soil cover, and a 12-inch compacted clay radon barrier. The revised design meets or exceeds applicable regulatory performance requirements, as demonstrated in Sections 4.3 through 4.9 and detailed in Appendices E through I.

The integrated disposal cell cover is engineered to address frost penetration, radon attenuation, biointrusion, infiltration, surface water control, slope stability, and erosion protection, as detailed in Sections 4.3 through 4.9. The revised three-layer system consists of: (1) a 12-inch rock mulch

layer for erosion control; (2) a 28-inch on-site soil cover layer for biointrusion protection, frost buffering, and store-and-release moisture storage; and (3) a 12-inch compacted clay radon barrier for radon attenuation and infiltration control. Cover performance has been validated against applicable regulatory and design criteria, including radon flux below the 20 pCi/m²/s limit, frost-depth protection of the clay barrier, design-basis percolation of 0.40 in/yr, and PMP-based erosion resistance for unsupported slope runs up to 250 feet.

The reclamation and cover system addresses the applicable federal uranium tailings performance requirements in 40 CFR Part 192 and 10 CFR Part 40, Appendix A, Criterion 6, and uses the New Mexico Copper Rule (20.6.7.33 NMAC) as a relevant state performance benchmark for store-and-release cover behavior.

## 4.2 Description of Cover

After filling and grading, the expanded disposal cell cover will be placed over the waste material. The final cover system will consist of the following layers, from top to bottom:

- 12 inches of rock mulch cover for erosion protection
- 28 inches of on-site soil cover for biointrusion and frost protection
- 12 inches of compacted clay to minimize infiltration and radon gas emanation

A schematic of the revised cover is illustrated in Figure 4-1.

## 4.3 Frost Penetration Analysis

EA evaluated frost penetration depth into the expanded disposal cell cover, as explained in Appendix D. Using a method developed by the U.S. Department of Energy (DOE, 1989) and endorsed by the Nuclear Regulatory Commission, the analysis considered local climate, soil type, and moisture levels over the lifetime of the cover. The approach, based on Berggren's work (1943), uses site-specific calculations to estimate frost depth. Smith and Rager (2002) advanced these ideas to determine the required thickness of protective soil above compacted layers to shield against frost. All derivations and thermal parameter values are provided in Appendix D.

The analysis used a 200-year recurrence interval Air Freezing Index (AFI) of 927.5°F·days, corresponding to the design-basis value at the 200-year return period. The statistical comparison of 2018–2025 site climate data presented in Appendix F confirms that the design-basis AFI exceeds the highest observed site AFI (524 degree-days in 2022) by a substantial margin, providing confidence that the design freeze event is appropriately conservative.

The optimized cover system provides 28 inches of on-site soil cover above the clay radon barrier, matching the design frost depth. The on-site soil cover layer serves as the primary thermal buffer, ensuring the clay radon barrier remains below the active frost zone under the design freeze event. The rock mulch surface layer provides additional thermal damping. Engineering implications are as follows: the clay radon barrier remains below the 28-inch frost depth and is protected from freeze-thaw cycling; the small μ value indicates frost penetration is relatively insensitive to

moderate variations in soil thermal properties; and the revised frost depth supports the reduced cover thickness without compromising radon attenuation or long-term barrier performance.

## 4.4 Radon Attenuation

### 4.4.1 *Regulatory Standard*

The engineered cover system over the expanded disposal cell is required to limit the surface flux of radon-222 to no more than 20 pCi/m²/s averaged over the disposal cell surface, as established under 40 CFR Part 192 and 10 CFR Part 40, Appendix A, Criterion 6. Radon attenuation modeling was performed to confirm that the proposed three-layer cover system satisfies this standard.

### 4.4.2 *Cover System Configuration*

The three-layer cover system evaluated in the radon attenuation analysis consists of the following layers, from top to bottom:

- 12 inches (30.5 cm) of rock mulch for erosion protection (uppermost layer)
- 28 inches (71.1 cm) of on-site soil for biointrusion and frost protection
- 12 inches (30.5 cm) of compacted clay as the primary radon barrier

The contaminated materials below the cover are assumed to be 5 meters (16.4 feet, or approximately 197 inches) thick for modeling purposes. The cover system configuration is shown in Figure E-1 (Appendix E).

### 4.4.3 *Model Description*

Radon emanation calculations were performed using the Wise Uranium Project Uranium Mill Tailings Cover Calculator, which implements the one-dimensional steady-state radon diffusion model described in NRC Regulatory Guide 3.64 (NRC, 1989). The model evaluates radon-222 diffusion from a radium-226 source through layered cover materials and computes the exit radon flux at the top of each layer. The calculator was executed in metric units with four model layers: contaminated materials, clay radon barrier, on-site soil, and rock mulch.

The key input parameters for the model are layer thickness, radium-226 activity concentration for the contaminated materials layer, radon emanation coefficient, porosity, long-term moisture content, and radon diffusion coefficient calculated by the model from material properties.

### 4.4.4 *Input Parameters*

#### 4.4.4.1 *Radium-226 Activity Concentration*

Radium-226 activity concentrations were derived from static gamma radiation surveys conducted by AVM Environmental Services, Inc. (AVM) across five distinct source area zones within the mine site. The representative mean activity values for each source area are summarized in Table 4-1.

**Table 4-1 Representative Ra-226 Activity Concentrations by Source Area**

| Source Area | Survey Date(s) | No. of Survey Locations | Mean Ra-226 Activity (pCi/g) | Reference |
|---|---|---|---|---|
| Windblown Area (WA) | May 17 and May 31, 2023 | 12 | 9.8 | AVM (2023) |
| Ore Pad Area (OPA) | May 31, 2023 | 5 | 431.6 | AVM (2023) |
| Mine Compound Area (MCA) | May 18–May 31, 2023 | 20 | 13.1 | AVM (2023) |
| Pond Area (PA) | October 18, 2023 | 40 | 4.8 | AVM (2024) |
| North Controlled Area (NCA) | September 19–December 12, 2024 | 47 | 47.1 | AVM (2025) |
| Arithmetic Mean (all areas) | — | 124 (total) | 101.3 | Calculated |

The arithmetic mean Ra-226 activity across all five source areas is approximately 101 pCi/g. For modeling purposes, a conservative design value of 115 pCi/g was used for the contaminated materials layer, which exceeds the five-area mean by 14 percent. This conservative assumption bounds the potential variability in source material composition across the disposal cell footprint. It is recommended that materials from the Ore Pad Area, which exhibit the highest mean Ra-226 activity (431.6 pCi/g), be placed at the base of the disposal cell during construction to minimize the thickness of high-activity materials near the cover interface.

#### 4.4.4.2 *Radon Emanation Coefficient*

A radon emanation coefficient of 0.35 was applied to all modeled layers, including the contaminated materials and cover materials. This is the conservative default value specified in the Uranium Mill Tailings Cover Calculator, consistent with NRC Regulatory Guide 3.64 (NRC, 1989).

#### 4.4.4.3 *Density and Porosity*

Material densities were assigned as follows: contaminated materials, 100 pcf (1.60 g/cm³), representative of a mixed sand, silt, and clay waste mass; clay radon barrier, 99 pcf (1.59 g/cm³), corresponding to 90 percent of the standard Proctor maximum dry density of sample EA-BSC09 (silty clay) collected from Borrow Area A-B in January 2025; on-site soil, 94 pcf (1.51 g/cm³), corresponding to 85 percent of the mean standard Proctor maximum dry density of samples EA-BSB04 (sand), EA-BSC12 (sandy clay), and EA-BSC09 (silty clay) from Borrow Area A-B; and rock mulch, 94 pcf (1.51 g/cm³), consistent with the on-site soil layer because the soil matrix of the rock mulch admixture is anticipated to be of similar composition.

Porosity values were assigned as follows: contaminated materials, 0.35, assumed for mixed sand, silt, and clay; clay radon barrier, 0.38, derived from the compaction test report for sample EA-BSC09 (void ratio = 0.62; porosity = e/(1+e) = 0.38); in-situ soil, 0.35, assumed for mixed sand, silt, and clay; and rock mulch, 0.35, consistent with the in-situ soil layer.

#### 4.4.4.4 *Long-Term Moisture Content*

Long-term moisture contents were assigned as follows: On -site soil and rock mulch, 6 percent, consistent with NRC guidance for long-term dry cover conditions (NRC, 1989). Clay radon barrier, 15.1 percent, determined from the soil water characteristic curve 15-bar permanent wilting point moisture content for sample EA-BSC09 (silty clay) remolded to 90 percent of standard Proctor density. Contaminated materials, 15.1 percent, equal to the clay barrier long-term moisture because the waste materials are below the depth of influence of surface evapotranspiration.

The long-term moisture content of the clay radon barrier is a sensitive model parameter. Use of the 15-bar SWCC moisture content is conservative and represents the equilibrium moisture condition under sustained drying; it produces a higher diffusion coefficient and therefore a higher, more conservative, radon flux estimate relative to higher moisture content assumptions.

#### 4.4.4.5 *Radon Diffusion Coefficient*

Radon diffusion coefficients for each layer were calculated internally by the Uranium Mill Tailings Cover Calculator based on the assigned porosity and long-term moisture content, consistent with the methodology of NRC Regulatory Guide 3.64 (NRC, 1989). The resulting diffusion coefficients are $1.69 \times 10^{-7}$ m²/s for contaminated materials, $4.62 \times 10^{-7}$ m²/s for the clay radon barrier, $2.01 \times 10^{-6}$ m²/s for the on-site soil layer, and $2.01 \times 10^{-6}$ m²/s for the rock mulch.

The clay radon barrier has a diffusion coefficient approximately 4.3 times lower than the on-site soil layer, reflecting the combined effect of higher density, higher moisture content, and finer texture. Lower diffusion coefficients correspond to lower radon transport rates through the layer.

### 4.4.5 *Model Results*

The input parameters and model results are summarized in Table 4-2. Full model output is provided in Appendix E. The radon attenuation model results indicate that the three-layer cover system reduces the radon-222 surface flux from a bare-source flux of 42.10 pCi/m²/s to a design surface flux of 13.99 pCi/m²/s at the top of the rock mulch layer. The total cover retention efficiency is 66.77 percent. The calculated surface flux of 13.99 pCi/m²/s is 30 percent below the NRC regulatory limit of 20 pCi/m²/s, confirming that the proposed cover system satisfies the radon attenuation performance standard.

The clay radon barrier provides the dominant attenuation effect, reducing flux from 31.17 pCi/m²/s at the top of the contaminated materials to 22.22 pCi/m²/s at the top of the clay layer. The on-site soil layer provides additional attenuation from 22.22 pCi/m²/s to 14.67 pCi/m²/s. The rock mulch layer provides the final attenuation step from 14.67 pCi/m²/s to 13.99 pCi/m²/s at the exposed surface. The progressive reduction in flux through each layer is consistent with the physics of one-dimensional steady-state diffusion and confirms the layered design is functioning as intended.

**Table 4-2 Radon Attenuation Model Input and Results**

| Layer No. | Layer Description | Thickness (in) | Porosity | Ra-226 Activity (pCi/g) | Emanation Coefficient | Diffusion Coeff. ($m^2/s$) | Exit Radon Flux ($pCi/m^2/s$) |
|---|---|---|---|---|---|---|---|
| 4 | Rock mulch | 12 | 0.35 | 0 | 0.35 | $2.01\times10^{-6}$ | 13.99 |
| 3 | On-site soil (frost protection and biointrusion) | 28 | 0.35 | 0 | 0.35 | $2.01\times10^{-6}$ | 14.67 |
| 2 | Clay layer (radon barrier) | 12 | 0.38 | 0 | 0.35 | $4.62\times10^{-7}$ | 22.22 |
| 1 | Contaminated materials | 197 | 0.35 | 115 | 0.35 | $1.69\times10^{-7}$ | 31.17 (bare source: 42.10) |

### 4.4.6 *Sensitivity Simulation*

Table 4-3 contains the results of the sensitivity analyses cases based on the Appendix E cover configuration and base radon flux of 13.99 $pCi/m^2/s$ for the 12-inch compacted clay barrier overlain by 28 inches of on-site soil cover. Consistent with the approach described in the Radon Attenuation Handbook for Uranium Mill Tailings Cover Design, the sensitivity cases evaluate how variations in on-site soil cover thickness, clay barrier thickness, and effective radon diffusion coefficients influence flux through the layered earthen cover system.

The revised sensitivity results summarized in Table 4-3 indicate that the base design flux of 13.99 $pCi/m^2/s$ provided in Appendix E remains below the 20 $pCi/m^2/s$ regulatory criterion. The on-site soil cover thickness cases show that reducing the overlying soil thickness increases calculated flux by shortening the diffusion path length, while increasing the thickness provides additional attenuation. The clay barrier thickness cases show that the compacted clay layer remains the controlling attenuation element because reduced clay thickness produces a larger loss of margin than a comparable change in the overlying on-site soil cover. The diffusion coefficient cases show that less favorable effective diffusion behavior increases calculated flux, while lower effective diffusion coefficients improve performance. All evaluated cases remain below the regulatory criterion, but the reduced clay and higher diffusion coefficient cases have the smallest margins and therefore define the most important construction quality control checks.

**Table 4-3 Results of Radon Sensitivity Analysis**

| Case | On-Site Soil Cover Thickness (in) | Clay Barrier Thickness (in) | Radon Diffusion Coefficient Assumption | Surface Flux (pCi/m²/s) |
|---|---|---|---|---|
| Appendix E base design | 28 | 12 | Appendix E design value | 13.99 |
| Reduced on-site soil cover | 20 | 12 | Appendix E design value | 16.21 |
| Increased on-site soil cover | 36 | 12 | Appendix E design value | 12.08 |
| Reduced clay barrier | 28 | 9 | Appendix E design value | 17.62 |
| Higher diffusion coefficient | 28 | 12 | 1.5 × Appendix E value | 18.74 |
| Lower diffusion coefficient | 28 | 12 | 0.75 × Appendix E value | 11.34 |

Model sensitivity testing indicates that radon flux is not strongly sensitive to the porosity of the waste materials, on-site soil, or rock mulch layers. However, the clay radon barrier porosity is a sensitive parameter: a 20 percent reduction in clay porosity reduces calculated flux to near zero, while a 20 percent increase can approximately double the calculated flux. The design clay porosity of 0.38 is based on laboratory data and is considered representative of the as-compacted condition.

## 4.5 Biointrusion

### 4.5.1 *Regulatory Framework*

The disposal cell cover system is designed to satisfy the biointrusion-relevant requirements of the U.S. Nuclear Regulatory Commission (NRC) under 10 CFR Part 40, Appendix A, Criterion 6, and the U.S. Environmental Protection Agency (EPA) under 40 CFR Part 192. Under Criterion 6 of 10 CFR Part 40, Appendix A, the cover system must provide reasonable assurance of control of radiological hazards for 1,000 years to an extent reasonably achievable, and in any case for at least 200 years. The New Mexico Environment Department (NMED) implementing regulations are consistent with these federal standards.

10 CFR Part 40, Appendix A, Criterion 6 further requires that either a full self-sustaining vegetative cover or rock cover be established to reduce wind and water erosion to negligible levels. In semi-arid and arid regions where a self-sustaining vegetative cover is not reliably achievable, rock cover must be employed on impoundment slopes. The Mt. Taylor disposal cell uses rock mulch on all exposed slopes consistent with this requirement, as described in Section 4.2.

### 4.5.2 *Role of Vegetation in Store-and-Release Cover Performance*

While not necessary, proposed, nor modeled in EA's infiltration analyses the current NRC and DOE guidance on evapotranspiration (ET) and store-and-release (SAR) cover systems recognizes that shallow-rooted native vegetation is a functionally integral component of cover performance. Native grasses and forbs with shallow root systems actively remove stored soil moisture through transpiration, thereby enhancing the cover's water-balance performance and reducing the fraction of precipitation available for deep percolation. This is consistent with the passive SAR design philosophy adopted for the Mt. Taylor disposal cell.

The primary biointrusion concern is the potential for deep-rooted woody plants, including shrubs and trees, and burrowing mammals to penetrate and compromise the clay radon barrier. The cover design addresses these threats through the physical deterrents described in Section 4.5.3, and the revegetation plan in Section 4.13 restricts planting to shallow-rooted native grass species consistent with the semi-arid climate.

### 4.5.3 *Cover System Design Measures Against Biointrusion*

The three-layer, 52-inch cover system provides redundant physical deterrents against biointrusion while maintaining the erosion-control, water-balance, and radon-attenuation functions of the final cover. Biointrusion protection is achieved through a combination of a coarse rock mulch surface that discourages animal burrowing, a compacted on-site soil cover layer that separates routine biological activity from the radon barrier, and a compacted clay layer that provides the low-permeability and low-diffusivity containment function at the base of the cover.

**Rock Mulch Layer (12 inches, uppermost).** The rock mulch layer is the first line of defense against biological disturbance. In addition to resisting wind and water erosion, the coarse, discontinuous surface reduces the suitability of the cover as burrowing habitat and makes excavation by small to medium burrowing animals more difficult. The rock mulch admixture consists of 30 percent AASHTO No. 1 gravel and 70 percent on-site soil, provides a durable surface layer while retaining sufficient fines to support the intended revegetation strategy.

**On-Site Soil Cover Layer (28 inches).** The compacted on-site soil cover layer provides the primary separation distance between surface biological activity and the compacted clay radon barrier. This layer can support shallow-rooted native grass community, provides frost buffering above the clay layer, and limits the likelihood that routine root growth, insect activity, or shallow animal disturbance will reach the radon barrier. The 28-inch thickness is therefore a key design feature because it maintains physical separation while preserving the store-and-release function of the cover.

**Compacted Clay Radon Barrier (12 inches).** The compacted clay layer is the principal radon-attenuation and infiltration-control layer and is protected from direct biological contact by the overlying 40 inches of rock mulch and on-site soil cover. Its cohesive texture, compacted condition, and low saturated hydraulic conductivity of $7.6\times10^{-6}$ cm/s reduce the likelihood of root penetration, insect excavation, and preferential pathway formation. Maintaining the continuity,

thickness, moisture condition, and compaction of this layer during construction is essential to preserving the biointrusion, radon-control, and infiltration-control functions of the cover system.

### 4.5.4 *Post-Closure Monitoring and Adaptive Management*

Post-closure stewardship will include periodic inspection of the cover surface for evidence of biointrusion, including the establishment of deep-rooted woody vegetation, active burrowing activity, and visible cracking or surface disturbance. Inspection frequency and corrective action thresholds will be established in the Post-Closure Stewardship Plan consistent with NRC and NMED requirements. Corrective actions may include manual removal of encroaching woody vegetation, backfilling of burrow openings, and localized cover repair as needed to maintain the integrity of the radon barrier and overall cover system.

The adaptive management framework is designed to detect and address biointrusion before cumulative damage to the cover system can occur, consistent with the long-term performance objectives of 10 CFR Part 40, Appendix A, Criterion 6.

## 4.6 Infiltration Analysis

### 4.6.1 *General*

The infiltration analysis evaluates long-term percolation through the engineered cover system and compliance with the New Mexico Copper Rule (20.6.7.33 NMAC) store-and-release performance standard. The cover system is designed as a passive store-and-release (SAR) barrier that relies on the soil moisture storage capacity of the on-site soil cover layer and the prevailing semi-arid climate to limit deep percolation into the underlying waste. The analysis integrates site-specific climate data, analytical water balance methods, and numerical seepage modeling.

### 4.6.2 *Method of Analysis*

The infiltration assessment employs a two-tiered approach:

1. Analytical Water Balance — The Budyko (1948) exponential equation is applied to estimate annual actual evapotranspiration (AET). Surface runoff is estimated using the Soil Conservation Service (SCS) Curve Number method applied on a monthly time step. Annual percolation is derived as the residual of precipitation minus AET and surface runoff.
2. Numerical Seepage Model (SEEP/W) — A two-dimensional transient finite-element model was developed using GeoStudio SEEP/W to simulate unsaturated and saturated flow through the proposed cover profile. Model results provide the adopted design-basis percolation rate. Model inputs, boundary conditions, and results are summarized in Appendix G.

The analytical water balance provides an independent upper-bound estimate of percolation to bracket SEEP/W results and confirm that the numerical model is reasonable.

### 4.6.3 *Parameters Used for Analysis*

Table 4-4 contains a summary of the monthly distribution of precipitation and PET for the 2018–2025 San Mateo station record. The data show a strong seasonal water-balance pattern: precipitation is greatest during the summer monsoon period, particularly July through September, but PET also reaches its maximum during the same interval. As a result, every month from March through October exhibits a moisture deficit, with the largest monthly deficits occurring in June, July, and August. Positive monthly balances occur only during the low-PET winter months and are small in magnitude. On an annual basis, precipitation totals 10.01 inches compared with 26.45 inches of PET, producing a net annual moisture deficit of 16.44 inches. This monthly pattern indicates that stored soil water is expected to be depleted during the growing season, limiting the amount of water available for sustained downward percolation through the cover profile.

Soil hydraulic parameters, climate inputs, and SCS runoff parameters used in the analytical water balance and numerical seepage model are summarized in Table 4-5. Laboratory test methods and data reduction procedures are documented in Appendix B; climate data derivation is documented in Appendix F.

**Table 4-4 Monthly Climate Water Balance**

| Month | Precipitation, P (in) | PET (in) | Surplus / Deficit (in) |
|---|---|---|---|
| January | 0.38 | 0.00 | +0.38 |
| February | 0.26 | 0.16 | +0.10 |
| March | 0.48 | 0.69 | −0.21 |
| April | 0.28 | 1.76 | −1.48 |
| May | 0.71 | 3.15 | −2.44 |
| June | 0.94 | 4.74 | −3.80 |
| July | 2.05 | 5.26 | −3.21 |
| August | 1.71 | 4.70 | −2.99 |
| September | 1.45 | 3.46 | −2.01 |
| October | 0.86 | 1.83 | −0.97 |
| November | 0.59 | 0.57 | +0.02 |
| December | 0.30 | 0.13 | +0.17 |
| **Annual Total** | **10.01** | **26.45** | **−16.44** |

**Table 4-5 Soil and Climate Parameters Used for the Infiltration Analysis**

| Parameter | Layer / Station | Value | Source |
|---|---|---|---|
| Saturated hydraulic conductivity, ksat | On-site soil cover | 1.2×10−4 cm/s | Lab testing, Appendix B |
| Saturated hydraulic conductivity, ksat | Compacted clay barrier | 7.6×10−6 cm/s | Design specification |
| Volumetric water content at field capacity, θfc | On-site soil cover (CL-ML) | 0.20 | SWCC, Appendix B |
| Volumetric water content at wilting point, θwp | On-site soil cover (CL-ML) | 0.10 | SWCC, Appendix B |
| Available water holding capacity, AWHC | On-site soil cover | 0.10 in/in | θfc − θwp |
| SCS Curve Number, CN | Cover surface (rock mulch, rangeland HSG B) | 55 | TR-55 (USDA, 1986) |
| Mean annual precipitation, P | San Mateo on-site station | 10.01 in/yr | Appendix F (2018–2025) |
| Potential evapotranspiration, PET | Thornthwaite (1948) | 26.45 in/yr | Appendix F |

### 4.6.4 *Water Balance Components and Percolation Estimation*

#### 4.6.4.1 *Aridity Index*

The ratio of potential evapotranspiration to mean annual precipitation characterizes the degree of water limitation at the site. The dimensionless aridity index φ is defined as:

$$\varphi = \text{PET} / P = 26.45 / 10.01 = 2.64$$

An aridity index greater than 2.0 indicates a strongly water-limited environment. Under these conditions, the dominant fate of infiltrated precipitation is evapotranspiration rather than deep percolation or runoff. The site value of 2.64 is consistent with the semi-arid character of the San Mateo area in northwestern New Mexico.

#### 4.6.4.2 *Actual Evapotranspiration*

Actual evapotranspiration (AET) was estimated using the Budyko (1948) exponential equation, which captures the long-term partitioning of precipitation between evapotranspiration and drainage under water-limited conditions:

$$\text{AET} = P(1 - e^{-\text{PET}/P})$$

Substituting the site-specific annual precipitation and PET values from Table 4-4:

$$\text{AET} = 10.01(1 - e^{-2.64}) = 10.01(1 - 0.071) = 10.01 \times 0.929 = 9.30 \text{ in/yr}$$

This result is consistent with the expectation that AET approaches MAP in a strongly arid climate, as the available soil water is nearly completely depleted through evapotranspiration before deep

drainage can occur. The fraction of precipitation lost to AET is 92.9 percent, leaving a limited residual available for surface runoff or percolation.

#### 4.6.4.3 *Surface Runoff*

Surface runoff was estimated using the SCS Curve Number method (USDA TR-55, 1986) applied on a monthly time step. A Curve Number of 55 was selected for rangeland conditions with rock mulch cover and Hydrologic Soil Group B soils, consistent with the cover surface description in Section 4.2. The maximum potential retention S and initial abstraction Ia are defined as:

$$S = 1000 / \mathrm{CN} - 10 = 1000 / 55 - 10 = 8.18 \text{ in}$$

$$I_a = 0.2S = 0.2 \times 8.18 = 1.64 \text{ in}$$

Runoff Q for any month with precipitation (Pm) greater than the initial abstraction threshold (Ia) is calculated as:

$$Q = (P_m - I_a)^2 / (P_m + 0.8S)$$

Applying the SCS Curve Number runoff equation to each month of the 2018–2025 mean monthly precipitation record shown in Table 4-4, only July (P = 2.05 in) and August (P = 1.71 in) exceed the threshold of 1.64 in. Monthly runoff calculations for the two generating months are as follows:

$$\text{July: } Q = (2.05 - 1.64)^2 / (2.05 + 0.8 \times 8.18) = 0.1681 / 8.594 = 0.0196 \text{ in} \approx 0.020 \text{ in}$$

$$\text{August: } Q = (1.71 - 1.64)^2 / (1.71 + 0.8 \times 8.18) = 0.0049 / 8.254 = 0.0006 \text{ in} \approx 0.001 \text{ in}$$

All remaining months produce no runoff because mean monthly precipitation does not exceed the initial abstraction threshold of 1.64 in. Annual surface runoff is the sum of monthly values:

$$R = \sum_{m=1}^{12} Q_m = 0.020 + 0.001 = 0.021 \text{ in/yr}$$

This low runoff magnitude is physically consistent with the rock mulch surface layer and semi-arid climate; the majority of precipitation events are low-intensity, sub-threshold occurrences that are fully retained within surface storage and subsequently lost to evapotranspiration.

#### 4.6.4.4 *Annual Percolation — Analytical Upper Bound*

Under steady-state annual conditions (ΔS = 0), the water balance residual provides an upper-bound estimate of potential deep percolation:

$$\text{Percolation} = P - \mathrm{AET} - R$$

$$\text{Percolation} = 10.01 - 9.30 - 0.021 = 0.689 \text{ in/yr} \approx 0.69 \text{ in/yr}$$

This result represents approximately 6.9 percent of mean annual precipitation and constitutes an analytical upper bound. The SEEP/W transient model accounts for unsaturated storage dynamics and produces a lower design-basis percolation value, as discussed in Section 4.6.6.

**Table 4-6 Annual Water Balance Summary**

| Component | Value (in/yr) | Percentage of MAP |
|---|---|---|
| Mean annual precipitation (P) | 10.01 | 100.0% |
| Actual evapotranspiration (AET) | 9.30 | 92.9% |
| Surface runoff (R) | 0.02 | 0.2% |
| Percolation — analytical upper bound (Eq. 4-8) | 0.69 | 6.9% |

Note: MAP = mean annual precipitation based on the 2018–2025 San Mateo on-site climate record summarized in Table 4-4 and Appendix D. Components may not sum exactly to 100% due to rounding.

### 4.6.5 *Copper Rule Store-and-Release Compliance*

Under the New Mexico Copper Rule (20.6.7.33 NMAC), a passive store-and-release cover system must demonstrate that the available water storage capacity of the soil layer equals or exceeds 95 percent of the mean winter precipitation or 35 percent of the mean summer precipitation, whichever is greater. This standard ensures that the cover can buffer episodic precipitation events without allowing percolation into the underlying waste mass.

#### 4.6.5.1 *Seasonal Precipitation from Site Climate Record*

Seasonal precipitation totals were derived from the 2018–2025 San Mateo on-site climate record summarized in Table 4-4 and compiled in Appendix D. Seasonal periods follow the Copper Rule convention: winter season spans October through March; summer season spans April through September. Mean monthly precipitation values from the site record are applied to each seasonal summation.

Winter precipitation, $P_w$:

$$P_w = P_{Oct} + P_{Nov} + P_{Dec} + P_{Jan} + P_{Feb} + P_{Mar}$$

$$P_w = 0.86 + 0.59 + 0.30 + 0.38 + 0.26 + 0.48 = 2.87 \text{ in}$$

Summer precipitation, $P_s$:

$$P_s = P_{Apr} + P_{May} + P_{Jun} + P_{Jul} + P_{Aug} + P_{Sep}$$

$$P_s = 0.28 + 0.71 + 0.94 + 2.05 + 1.71 + 1.45 = 7.14 \text{ in}$$

#### 4.6.5.2 *Required Storage*

The Copper Rule storage requirement is the greater of the two seasonal threshold values:

$$S_{req} = \max(0.95P_w, 0.35P_s)$$

$$0.95P_w = 0.95 \times 2.87 = 2.73 \text{ in} \quad \text{(winter threshold)}$$

$$0.35P_s = 0.35 \times 7.14 = 2.50 \text{ in} \quad \text{(summer threshold)}$$

The winter threshold governs. The Copper Rule required storage is:

$$S_{req} = 2.73 \text{ in}$$

#### 4.6.5.3 *Storage Provided*

The 28-inch on-site soil cover layer provides water storage capacity determined by the available water holding capacity (AWHC) of the soil profile:

$$S_{cap} = \text{AWHC} \times d = 0.10 \text{ in/in} \times 28 \text{ in} = 2.80 \text{ in}$$

The provided storage of 2.80 in exceeds the required storage of 2.73 in by 0.07 in, confirming compliance with the New Mexico Copper Rule (20.6.7.33 NMAC) store and release performance standard under nominal design conditions.

#### 4.6.5.4 *Results of Infiltration Analysis*

The SEEP/W transient numerical model was developed using the cover profile described in Section 4.2. The model layout is shown on Figure 4-2. The model was applied using the daily precipitation records from the Gallup, NM weather station as the upper boundary condition, with atmospheric evapotranspiration prescribed using the Thornthwaite (1948) PET estimates summarized in Table 4-4. Material hydraulic properties are defined by the laboratory-derived soil-water characteristic curves (Appendix B) and the saturated hydraulic conductivity values in Table 4-5. Model inputs, boundary conditions, calibration, and output time series are documented in Appendix G.

Under the design precipitation record, the transient numerical model produces a long-term mean annual percolation rate of 0.40 in/yr at the base of the cover system, as documented in Appendix G. This design-basis rate is approximately 4.0 percent of mean annual precipitation and is below the analytical upper bound of 0.69 in/yr, or 6.9 percent of mean annual precipitation, computed using the Budyko and SCS water balance in Section 4.6.4. The lower numerical result is physically consistent because the transient model captures unsaturated soil moisture storage during low-intensity precipitation intervals, thereby reducing the fraction of precipitation that reaches the compacted clay radon barrier. Together, the numerical design basis and analytical upper bound confirm that the cover system limits deep percolation to a small fraction of mean annual precipitation under site design conditions.

The analytical and numerical results together confirm that the proposed 52-inch three-layer cover system, comprising a 12-inch rock mulch surface layer, a 28-inch on-site soil cover storage layer, and a 12-inch compacted clay radon barrier, provides the hydrologic performance required under the design climate. Percolation through the cover is effectively controlled by the combined effects of high evapotranspirative demand, negligible surface runoff generation, and the moisture storage capacity of the on-site soil cover layer.

## 4.7 Settlement Analysis

Settlement of the compacted disposal cell will be evaluated during material placement. Before construction, representative waste samples will be collected, remolded to 95 percent of the standard Proctor maximum dry density, and tested for consolidation and swell under wetting conditions. These data will be used to confirm that sufficient camber has been incorporated into the final grading surface to maintain positive surface drainage. Tanks or other vessels that could collapse over time will be flow-filled or otherwise stabilized to limit potential future settlement.

## 4.8 Slope Stability Analysis

### 4.8.1 *General*

The slope stability assessment evaluates the global stability of the expanded disposal cell after placement of the final cover system. Detailed slope stability calculations, model output, and supporting figures are provided in Appendix H. The cover system is designed with exterior slopes of 5H:1V, equivalent to a 20 percent grade. Stability sections were developed to represent the combined new disposal cell configuration tied into the steepest section of the existing cell without terraces. This configuration provides a conservative assessment section for evaluating potential deep-seated and shallow translational failure mechanisms through the cover, waste, and foundation materials.

### 4.8.2 *Method of Analysis*

EA evaluated global stability using the Morgenstern-Price limit equilibrium method (Morgenstern and Price, 1965) in SLOPE/W (GeoStudio, 2021). The Figure 4-3 section represents the combined new disposal cell and steepest existing-cell section without terraces. Static and pseudo-static seismic cases were evaluated for circular and non-circular failure surfaces using target FOS values of 1.5 and 1.1, respectively. Model setup, search criteria, geometry, and supporting output are documented in Appendix H; results are shown in Figures 4-4 and 4-5.

Section 2.5 describes the probabilistic seismic hazard analysis for the facility, which indicates a peak horizontal ground acceleration (PGA) of 0.21g for a 10,000-year return period. For the pseudo-static analyses, a horizontal seismic coefficient of 0.14 was applied, corresponding to two-thirds of the 10,000-year PGA. This coefficient was applied as a horizontal inertial load in the seismic stability cases.

### 4.8.3 *Material Properties*

Material properties used in the stability analyses were selected from the lower band of available laboratory test results, design specifications, and conservative engineering judgment for materials in the analyzed section. This approach is consistent with the SLOPE/W assessment presented in Appendix H and avoids using average laboratory strength values where lower band values govern design. The material set represents the final cover system, compacted disposal cell fill and waste, and foundation soil or overburden. Bedrock is not included in the analyzed section and is therefore not represented as a separate model material. The adopted parameters are summarized in Table 4-7.

**Table 4-7 Material Properties Used for Stability Assessment**

| Material / Zone | Unit Weight, γ (pcf) | Cohesion, c′ (psf) | Friction Angle, φ′ (degrees) |
|---|---|---|---|
| Rock mulch cover | 115 | 0 | 35 |
| On-site soil cover | 110 | 0 | 25 |
| Compacted clay radon barrier | 120 | 0 | 24 |
| Compacted disposal-cell fill / waste | 102 | 0 | 25 |
| Foundation soil / overburden | 122 | 0 | 25 |

### 4.8.4 *Results of Analysis*

The stability results indicate that the combined disposal cell configuration with 5H:1V final cover slopes satisfy the applicable static and pseudo-static stability criteria for the analyzed section. The static analysis produced a factor of safety greater than the NRC target value of 1.5, and the pseudo-static seismic analysis using a horizontal coefficient of 0.14 produced a factor of safety greater than the target value of 1.1. These results indicate adequate global stability for the analyzed section, including the steepest existing-cell segment without terraces, using the material zones and lower band strength parameters summarized in Table 4-7. Detailed SLOPE/W output and supporting stability figures are provided in Appendix H; the summary results are presented in Figures 4-4 and 4-5.

## 4.9 Surface Water Hydrology and Erosion Protection

The reclaimed disposal cell surface is protected from water and wind erosion through a combination of offsite runoff diversion and rock mulch admixture surface facing. These two elements are designed independently and are discussed in separate subsections below. Erosion protection design follows the procedures specified in NUREG-1623 (NRC, 2002) and NUREG/CR-4620 (Nelson et al., 1986), which are the NRC-recommended standards for long-term stabilization of uranium mill tailings impoundments. The design life for the erosion protection system is 1,000 years, consistent with 40 CFR 192 and 10 CFR Part 40, Appendix A, Criterion 6. Supporting hydrology, hydraulic, rock mulch sizing, gully formation, stable-slope, riprap, filter-bedding, and wind-erosion calculations are provided in Appendix I.

### 4.9.1 *General*

The expanded disposal cell cover will be graded at a 20 percent slope, equivalent to 5H:1V, and will include a 12-inch-thick rock mulch surface layer composed of a rock-soil admixture. The admixture will consist of 30 percent AASHTO No. 1 gravel and 70 percent onsite on-site soil material by volume. This configuration provides durable erosion resistance under the site's semi-arid climate and high-intensity precipitation regime while supporting vegetation establishment through a soil matrix suitable for root development. Gravel-soil admixture covers used in analogous uranium mill tailings closures in the Grants Mineral Belt have effectively controlled water and wind erosion while allowing native vegetation to establish without materially reducing evapotranspiration. Erosion and water-balance studies support moderate gravel fractions,

generally 25 to 35 percent by volume, to meet the dual objectives of erosion control and evapotranspiration performance. As wind and water act on the admixture surface, fines are winnowed away, forming a vegetated desert pavement that provides long-term, self-reinforcing erosion resistance.

### 4.9.2 *Design Storm*

The design storm for long-term erosion stability is the Probable Maximum Precipitation (PMP), consistent with NUREG-1623 and NUREG/CR-4620. The PMP produces the Probable Maximum Flood (PMF), which governs rock mulch and riprap sizing for the 1,000-year erosion-protection design life. Appendix I provides design-storm selection, rainfall-depth development, and hydrologic calculations used for the cover and diversion channel evaluations.

The Mt. Taylor Mine site is located approximately 7,400 feet above mean sea level and west of the 103rd meridian. Therefore, the Appendix I calculation applies the NUREG/CR-4620 procedures for the generalized 6-hour storm and the local 1-hour, 1-square-mile storm. PMP rainfall depths were obtained from HMR-49 (NOAA, 1984), with elevation adjustments applied for site conditions and no drainage-area scale reduction for areas less than one square mile.

For cover design, the short-duration PMP governs the rock mulch erosion checks because the cover has short times of concentration. For the diversion channel, the PMP-derived PMF governs the longer-duration watershed response and channel lining design. The 100-year, 24-hour precipitation depth of 2.56 inches is documented in Appendix F, but Appendix I confirms that the PMP condition is substantially more severe and therefore governs erosion-protection design.

### 4.9.3 *Rock Mulch Cover Design*

#### 4.9.3.1 *Contributing Area and Time of Concentration*

Design flows for rock mulch sizing were computed using the Rational Method with contributing areas defined on a unit width basis to simulate sheet flow across the cover surface, consistent with NUREG-1623. The contributing area for each slope segment is therefore defined as 1 foot multiplied by the cumulative slope length from the ridgeline.

$$A = 1 \text{ ft} \times L$$

where $L$ is the cumulative slope length from the ridgeline. Time of concentration was calculated using the Kirpich (1940) formula as recommended in NUREG/CR-4620:

$$t_c = 0.0078 \times L^{0.770} \times S^{-0.385}$$

where $t_c$ is time of concentration in minutes, $L$ is slope length in feet, and $S$ is ground slope in feet per foot. At the design cover slope of 20 percent ($S$ = 0.20 ft/ft), the Kirpich formula yields short times of concentration for disposal cell cover slope segments. Where computed values fall below the minimum PMP duration increment used in NUREG/CR-4620, the minimum duration governs the applied rainfall intensity. The detailed slope-length increments, contributing areas, times of concentration, and governing rainfall intensities are provided in Appendix I.

#### 4.9.3.2 *Peak Discharge, Rational Method*

Peak runoff rates were computed using the Rational Method as recommended in NUREG-1623:

$$Q = C \times I \times A$$

where $Q$ is peak discharge in cfs per foot of unit width, $C$ is the runoff coefficient, $I$ is rainfall intensity in inches per hour, and $A$ is contributing area in acres per foot of width. A runoff coefficient of 0.80 was assigned to the rock mulch admixture cover surface, consistent with precedent for rock mulch cover surfaces. Appendix I provides the Rational Method worksheets used to calculate design discharges for the cover-slope erosion protection evaluation.

Velocity and flow depth on the cover surface were computed using Manning's equation for a wide rectangular flow section. A Manning's roughness coefficient of $n = 0.035$ was assigned to the rock mulch admixture cover, consistent with rocky soil cover surface guidance in NUREG/CR-4620.

#### 4.9.3.3 *Rock Mulch Sizing, Abt Johnson Method*

The median stone diameter of the rock mulch was sized using the Abt Johnson method, as recommended in NUREG-1623 and NUREG/CR-4620:

$$D_{50} = 5.23 \times q^{0.56} \times S^{0.43}$$

where $D_{50}$ is median rock size in inches, $q$ is unit discharge in cfs per foot, and $S$ is cover slope in feet per foot. A flow concentration factor of 3 is applied to the unit discharge to provide an appropriate degree of conservatism, consistent with NUREG-1623 guidance and comparable rock-mulch cover design practice. Appendix I documents the design discharges, flow depths, velocities, and computed $D_{50}$ values at representative slope-length increments. The results indicate that the AASHTO No. 1 gravel component, with a nominal $D_{50}$ of approximately 2.2 inches, provides adequate erosion resistance where unsupported slope runs are limited by interceptor berms or grade breaks. The adopted design standard limits maximum unsupported slope runs to 250 feet, providing a nominal factor of safety of at least approximately 1.08 for the provided gravel size based on the Appendix I Abt-Johnson calculations.

**Table 4-8 Rock Mulch Sizing Results**

| Slope Length L (ft) | Required D50 (in) | Provided D50 (in) | Factor of Safety |
|---|---|---|---|
| 50 | 0.83 | 2.20 | 2.65 |
| 100 | 1.22 | 2.20 | 1.80 |
| 150 | 1.54 | 2.20 | 1.43 |
| 200 | 1.80 | 2.20 | 1.22 |
| 250 | 2.04 | 2.20 | 1.08 |
| 300 | 2.26 | 2.20 | 0.97 |

As summarized in Table 4-8, the provided AASHTO No. 1 gravel $D_{50}$ of 2.20 inches exceeds the required $D_{50}$ for slope lengths up to 250 feet, but the factor of safety drops below unity at 300 feet. The rock mulch layer thickness is specified at 12 inches. Per NUREG-1623 guidance, the layer thickness must equal or exceed 1.5 times the $D_{50}$ diameter to prevent layer penetration under design

flow conditions. The 12-inch layer thickness exceeds 1.5 × 2.20 = 3.3 inches, satisfying this criterion by a wide margin.

#### 4.9.3.4 *Filter Requirement — Leps (1973)*

The need for a separate filter layer beneath the rock mulch admixture was evaluated in accordance with NUREG-1623 and NUREG/CR-4620 using the Leps (1973) relationship for interstitial flow through rockfill. The evaluation was completed to determine whether flow through the voids of the rock mulch could exceed filter-design thresholds and potentially require an additional transition layer between the rock mulch and the underlying on-site soil cover.

$$V_v = W_m^{0.5} \times i^{0.54}$$

In the Leps relationship, $V_v$ is the average interstitial velocity in the voids of rockfill, $W_m^{0.5}$ is an empirical coefficient dependent on rock size from the NUREG/CR-4620 tabulated values, and $i$ is the hydraulic gradient. For this evaluation, the hydraulic gradient was taken as the cover slope, $S$ = 0.20 ft/ft. Because the cover surface is a gravel-soil admixture rather than clean rockfill, the analysis was completed in two steps, as documented in Appendix I, Section I-3.

The first step provides a conservative screening calculation using only the AASHTO No. 1 gravel component. For the gravel fraction, $D_{50}$ = 2.20 inches and $W_m^{0.5}$ = 4.75 $in^{0.5}/s$. Substitution into the Leps equation at the design hydraulic gradient gives:

$$V_v = 4.75 \times (0.20)^{0.54} = 1.99 \text{ ft/s}$$

This screening value exceeds the NUREG-1623 threshold of 1.0 ft/s; however, it represents clean gravel behavior and is not the governing condition for the proposed cover. The constructed surface will be a blended admixture consisting of 30 percent AASHTO No. 1 gravel and 70 percent on-site soil cover material by volume. The fine-grained soil fraction fills the voids between gravel particles and controls the effective pore-throat dimension, so applying the gravel-only result directly would overstate the interstitial velocity through the constructed layer.

The second step therefore evaluates the blended admixture. On a simple volume-weighted basis, the blend of 30 percent gravel ($D_{50}$ = 2.20 inches) and 70 percent on-site soil cover material ($D_{50}$ = 0.0106 inches) gives:

$$D_{50,blend} = 0.30 \times 2.20 + 0.70 \times 0.0106 = 0.667 \text{ in}$$

As described in Appendix I, Section I-3.2.1, the effective blended $D_{50}$ for interstitial-flow behavior is governed by the finer on-site soil cover fraction rather than by the volume-weighted arithmetic value. On a mass-weighted and pore-control basis, the finer fraction fills the gravel voids and determines the effective pore size; therefore, the governing blended value is $D_{50,blend}$ = 0.0106 inches. Using this governing value, the corresponding Leps coefficient is:

$$W_m^{0.5} \ (D_{50} = 0.0106 \text{ in}) \approx 0.010 \ in^{0.5}/s$$

$$V_v = 0.010 \times (0.20)^{0.54} = 0.004 \text{ ft/s} << 1.0 \text{ ft/s}$$

The refined interstitial velocity of 0.004 ft/s is well below both the 1.0 ft/s screening threshold and the 0.5 ft/s no-filter threshold. This refined result is the governing Leps result for the constructed admixture because it reflects the effective pore structure created by the combined gravel and on-

site soil cover material. Accordingly, the blended admixture functions as its own filter at the interface with the underlying on-site soil cover, and a separate filter layer beneath the rock mulch cover is not required.

A Terzaghi (1943) filter-compatibility check was also completed to confirm that the admixture is compatible with the underlying on-site soil cover layer. The check was performed in accordance with Appendix I, Section I-3.2.3:

$$D_{15,\text{blend}} / D_{85,\text{subgrade}} = 0.045 \leq 5.0 \text{ [COMPATIBLE — criterion satisfied]}$$

The Terzaghi ratio is substantially below the criterion of 5.0, confirming compatibility between the blended admixture and the underlying on-site soil cover. The Leps and Terzaghi evaluations therefore support the same design conclusion: the rock mulch admixture provides adequate internal filtering and interface compatibility without a separate filter layer.

#### 4.9.3.5 *Gully Formation Analysis*

Gully formation within the rock mulch admixture cover was evaluated using NUREG-1623 and EPA (2012) guidance. Design flows for gully formation were computed using the Rational Method with a contributing area width equal to one quarter of the slope length, consistent with EPA (2012). Mean annual flow was estimated as 20 percent of the Probable Maximum Flood peak runoff:

$$Q_m = 0.20 \times Q_{PMF}$$

Gully channel geometry at the critical flow condition was estimated using EPA (2012) empirical equations relating mean annual flow, soil silt and clay content, and channel width-to-depth ratio. The percent silts and clays used in the calculation is the fraction passing the No. 200 sieve in the admixture gradation, approximately 17 percent for the 30 percent AASHTO No. 1 gravel and 70 percent on-site soil blend. Appendix I documents the gully-formation calculations, including mean annual flow, incipient particle size, armor-layer development, and calculated scour depth.

The incipient particle size was computed using Shield's equation:

$$D_c = \tau / [F_s \times (\gamma_s - \gamma)]$$

where $\tau$ is average bed shear stress, $F_s$ is Shield's dimensionless shear stress, $\gamma_s$ is specific weight of soil, and $\gamma$ is the unit weight of water. The depth of scour required to develop an armor layer was calculated using the Pemberton and Lara (1984) equation:

$$Y_s = Y_a \times [(1 / P_c) - 1]$$

where $Y_s$ is scour depth, $Y_a$ is armor-layer thickness, and $P_c$ is the decimal fraction of admixture material coarser than the incipient particle size. For the design slope length of 250 feet, the Appendix I Shield's incipient motion analysis yields a critical particle size of approximately 4.15 inches; gravel particles larger than that threshold resist movement and form the armor layer. The Pemberton-Lara equation yields a scour depth of approximately 10.3 inches, which is less than the 12-inch admixture layer thickness. Gully formation calculations therefore confirm that the armor layer develops within the depth of the rock mulch admixture before reaching the underlying on-site soil cover, protecting cover integrity under design flow conditions. This outcome also supports the adopted 250-foot maximum unsupported slope run because the calculated scour remains within

the sacrificial admixture layer before the design storm can expose the moisture-storage soil layer. Construction verification of gradation and thickness will be required to maintain this margin.

#### 4.9.3.6 *Stable Slope Analysis*

Long-term slope stability of the rock mulch admixture cover under PMP conditions was evaluated using two complementary approaches: the Abt-Johnson critical slope run length analysis, which governs the design, and the allowable shear stress method from Temple et al. (1987) and NUREG-1623, which provides a confirmatory check. The Abt-Johnson analysis establishes that the AASHTO No. 1 gravel component provides a factor of safety of approximately 1.08 at a slope length of 250 feet, declining below unity beyond approximately 286 feet. This establishes the governing design constraint that interceptor berms or grade breaks must be provided at a maximum spacing of 250 feet along the 20 percent cover slope.

$$\tau_a = 0.4 \times D_{75}$$

$$S_s^{7/6} = [65 \times \tau_a^{5/3}] / [I \times L \times F \times n]$$

where $S_s$ is maximum stable slope, $D_{75}$ is the 75th-percentile rock size in the admixture, $\tau_a$ is allowable shear stress, $I$ is PMP rainfall intensity, $L$ is slope length, $F$ is the flow concentration factor, and $n$ is Manning's roughness coefficient. For the AASHTO No. 1 gravel component, $D_{75}$ is approximately 3.5 inches, resulting in an allowable shear stress of approximately 1.40 psf. At the design cover slope and maximum berm spacing of 250 feet, computed bed shear stresses remain below the allowable shear stress, confirming the Abt-Johnson result. Stable-slope calculations are provided in Appendix I.

#### 4.9.3.7 *Rock Mulch Admixture Gradation*

The rock mulch admixture consists of 30 percent AASHTO No. 1 gravel and 70 percent on-site soil material by volume, consistent with EPA (2012) guidance for aggregate amended covers in arid and semi-arid environments. The 30 percent gravel fraction is specified to provide enhanced erosion resistance while maintaining sufficient finer soil matrix to support vegetation establishment. The gradations of the AASHTO No. 1 gravel, on-site soil material, and blended admixture are presented in Table 4-9.

**Table 4-9 Rock Mulch Admixture Gradation**

| Sieve Size | AASHTO No. 1 Gravel % Passing | On-Site Soil Material % Passing | Blended Admixture % Passing |
|---|---|---|---|
| 4 in (101.6 mm) | 100 | 100 | 100 |
| 3.5 in (88.9 mm) | 95 | 100 | 99 |
| 2.5 in (63.5 mm) | 50 | 100 | 85 |
| 1.5 in (38.1 mm) | 8 | 100 | 72 |
| 3/4 in (19.05 mm) | 3 | 100 | 71 |
| 3/8 in (9.525 mm) | 0 | 96 | 67 |
| No. 4 (4.76 mm) | 0 | 92 | 64 |
| No. 10 (2.00 mm) | 0 | 86 | 60 |
| No. 40 (0.420 mm) | 0 | 80 | 56 |
| No. 100 (0.149 mm) | 0 | 59 | 42 |
| No. 200 (0.074 mm) | 0 | 24 | 17 |

Note: Gradations are based on representative AASHTO No. 1 gravel and site on-site soil material used in the Appendix I erosion-protection calculations. Final admixture gradation shall be verified by blending trials before construction. The percent passing the No. 200 sieve in the blended admixture, approximately 17 percent, provides the silt and clay fraction input to the gully formation analysis in Section 4.9.3.5. The median size of the AASHTO No. 1 gravel component is nominally 2.2 inches, consistent with the specified gradation.

### 4.9.4 *Wind Erosion Analysis*

Wind erosion from the admixture cover surface was evaluated using the Wind Erosion Prediction System (WEPS), a USDA developed procedural simulation model that generates continuous weather simulations for site specific field conditions. WEPS produces an estimated annual soil loss in tons per acre per year. Site inputs for the WEPS analysis included site latitude, longitude, and elevation consistent with the site. A sandy loam soil with 30 percent rock fragment volume was used to represent the admixture surface. The 30 percent rock fragment input reflects the design gravel fraction and simulates the naturally developing armored surface expected on the cover over time.

EPA (1991) guidance for RCRA/CERCLA final covers identifies a soil loss target of less than 2 tons per acre per year as an acceptable benchmark for cover performance. The Mt. Taylor admixture design with 30 percent gravel will produce an annual erosion of 0.13 tons/acre/year. This is substantially below the 2-ton guidance threshold. Final site-specific WEPS results are provided in Appendix I.

### 4.9.5 *Summary*

The surface water hydrology and erosion protection design for the Mt. Taylor Mine expanded disposal cell integrates cover-slope armoring, gully-resistance checks, and wind-erosion protection. The design is based on the PMP/PMF framework and the procedures in NUREG-1623, NUREG/CR-4620, and 40 CFR Part 192, with supporting calculations provided in Appendix I. The resulting design limits erosion of the 20 percent cover slopes controls offsite inflow around the disposal cell and provides redundant protection at the diversion channel and embankment interface.

Table 4-10 summarizes the principal design elements and shows how each component contributes to the overall erosion-protection system. The design storm rows establish the hydrologic basis for the cover, using the local PMP storm for cover erosion. The time-of-concentration and peak-discharge rows identify the routing assumptions used to convert the design rainfall into cover-slope flow conditions, including the Kirpich equation, Rational Method, unit-width sheet-flow basis, and a runoff coefficient of 0.80 for the rock mulch admixture surface.

The table also documents the key erosion-resistance checks for the rock mulch cover. The Abt-Johnson rock-sizing method, with a flow concentration factor of 3, confirms that the AASHTO No. 1 gravel fraction provides adequate resistance for unsupported slope runs up to 250 feet. Manning's roughness value of 0.035 represents the rocky soil admixture surface used in the hydraulic calculations. The filter and gully-formation rows demonstrate that the blended rock-soil admixture functions as its own filter and that the calculated armor layer develops within the 12-inch rock mulch layer before scour reaches the underlying On-site soil cover.

**Table 4-100 Surface Water and Erosion Protection Design Summary**

| Design Element | Design Basis / Method | Key Parameter |
|---|---|---|
| Design storm for cover | PMP local storm from HMR-49 | West of 103rd meridian; site elevation approximately 7,400 ft |
| Time of concentration | Kirpich (1940), per NUREG/CR-4620 | Short cover times of concentration govern rainfall intensity |
| Peak discharge for cover | Rational Method with runoff coefficient $C = 0.80$ | Unit-width sheet-flow basis for cover slopes |
| Rock mulch size | Abt-Johnson method with flow concentration factor = 3 | $D_{50} = 5.23q^{0.56}S^{0.43}$; provided gravel $D_{50}$ approximately 2.2 in |
| Cover Manning's *n* | Rocky soil admixture surface | $n = 0.035$ |
| Cover filter requirement | Leps (1973) interstitial velocity and Terzaghi filter compatibility | Separate filter not required; admixture acts as filter |
| Gully formation | EPA (2012), Shields equation, and Pemberton and Lara (1984) | Armor layer develops within 12-inch rock mulch cover |
| Stable slope | Temple et al. (1987), NUREG-1623, and Abt-Johnson confirmation | Maximum unsupported slope run = 250 ft |
| Admixture design | 30 percent AASHTO No. 1 gravel and 70 percent on-site soil material | Nominal gravel $D_{50}$ approximately 2.2 in |
| Wind erosion | WEPS, USDA | Less than 2 tons/acre/year benchmark |

The rock mulch admixture protects the disposal cell surface from rainfall impact, sheet flow, gully formation, and wind erosion. These elements provide a technically consistent erosion-protection

design for the 1,000-year performance period, subject to construction verification of material gradations and layer thicknesses. This summary also provides a cross-check that the selected design assumptions are internally consistent across hydrology, hydraulics, gradation, filter compatibility, and long-term maintenance requirements, reducing the likelihood that any single component controls performance without supporting redundancy.

## 4.10 Borrow Source Location and Characterization

The disposal cell cover system will consist of (from bottom to top) clay radon barrier, on-site soil cover for biointrusion and frost protection, and a rock mulch layer for erosion protection. The proposed cover system is shown in Figure 4-1. This section discusses the location and characterization of the borrow source areas for the proposed cover materials.

### 4.10.1 *Borrow Source Locations*

The EA site investigation showed that the clay for the radon barrier and the on-site soil cover materials are procurable from the site. Figure 2-2 includes the locations of the potential borrow sources at the site.

### 4.10.2 *Borrow Source Characterization*

#### 4.10.2.1 *Clay Borrow Source*

The field investigation of the clay borrow source, conducted by EA, included excavation of 24 test pits as discussed in Section 2.3. The test pit locations are shown on Figure 2-3, and the test pit logs are included in Appendix A. EA encountered clay, silty clay, clayey silt, sandy clay, sand, and sandstone in the test pits.

#### 4.10.2.2 *On-Site Soil Cover Borrow Source*

A borrow source for the on-site soil cover exists at the Facility as shown on Figure 4-6. As discussed in Section 2.4.2, samples of the borrow source materials were collected for laboratory testing. The laboratory test results are included in Appendix B.

#### 4.10.2.3 *Rock Mulch Borrow Source*

The rock mulch cover layer will be locally sourced where suitable material is available. The material will comprise 30 percent AASHTO No. 1 gravel and 70 percent on-site soil cover material by volume. The source rock for the mixture may be imported if a suitable local source is not identified. NUREG-1623 provides specific criteria for the use of sandstone in reclamation applications, including fine-grained quartz cementation, low porosity, insignificant vertical and horizontal joints or fractures, and sourcing from massive bedding formations. Before final design, a borrow source for the rock will be identified and tested.

## 4.11 Borrow Source Quantities

The optimized 52-inch cover system requires three principal borrow material quantities: approximately 31,833 cubic yards of 12-inch rock cover, 70,620 cubic yards of 28-inch on-site soil cover, and 28,740 cubic yards of 12-inch compacted clay for the radon barrier. These quantities

are based on the revised cover configuration described in Section 4.2 and supersede the previous bulk borrow-source quantity estimate.

Borrow Source C has an approximate plan area of 522,920 square feet, or about 12.0 acres. Based on that area, each foot of recoverable material represents approximately 19,367 cubic yards of in-place soil before shrinkage, processing losses, oversize removal, or selective excavation. The required 28,740 cubic yards of compacted clay therefore corresponds to about 1.48 feet of average in-place clayey material across the Borrow Source C footprint before adjustment for construction yield. Allowing for approximately 15 percent loss or shrinkage, the required average recoverable thickness increases to about 1.70 feet.

The January 2025 test pit descriptions summarized in Section 2.3 indicate that sandy clay was encountered at most test pit locations and commonly occurs beneath the surficial sand at depths of approximately 3 to 4 feet, extending to the 6-foot exploration depth. Within Borrow Source C specifically, sandy clay was observed immediately below topsoil at C-2 and C-8, was present below sand at most other C-series test pits, and was absent at C-12 based on the limited excavation depth described in the logs. This distribution indicates that Borrow Source C contains a laterally extensive clayey soil interval, although the clayey material is not uniformly present from the ground surface and will require selective stripping of topsoil and overlying sand before excavation of the clayey borrow material.

For planning purposes, if the average recoverable clayey thickness within Borrow Source C is assumed to be 2.0 feet, the estimated available in-place clayey volume is approximately 38,735 cubic yards. If the average recoverable thickness is 2.5 feet, the estimated volume increases to approximately 48,419 cubic yards; at 3.0 feet, the estimated volume is approximately 58,102 cubic yards. These estimates indicate that Borrow Source C can reasonably supply the 28,740 cubic yards of compacted clay required for the 12-inch radon barrier if at least about 1.7 feet of suitable clayey material can be selectively recovered on average across the borrow area after allowances for shrinkage and unsuitable material.

The on-site soil cover requirement of 70,620 cubic yards is greater than the clay radon barrier requirement but may be satisfied using the overlying sand, sandy clay, and other suitable onsite on-site soil materials from Borrow Source C and other onsite borrow areas, subject to gradation, organic-content, oversize, moisture-density, and hydraulic suitability requirements. The 31,833 cubic yards of rock cover will be supplied from the approved rock mulch source or imported aggregate source and blended as specified in Section 4.9.

The borrow quantity estimate should be treated as preliminary because the uploaded test pit log file could not be read directly in this editing session. The estimate is therefore based on the test pit descriptions already summarized in Section 2.3 of this report. Before construction, Borrow Source C should be confirmed by field staking, additional shallow test pits or dozer cuts, laboratory classification and compaction testing, and construction quality assurance documentation to verify that the clayey material meets the compacted clay barrier specifications and that sufficient suitable volume remains after stripping and processing.

## 4.12 Revegetation of Disturbed Areas

Revegetation of the borrow areas will follow the Closeout/Closure Plan (EA, 2025) and use native, drought-adapted species suited to the Mt. Taylor Mine setting in the western plateau and high-valley region of northwestern New Mexico. The region receives approximately 10 to 14 inches of annual precipitation and supports native grassland and shrubland communities that include grama grasses, Indian ricegrass, galleta, and fourwing saltbush. The seed mix in Table 4-11 is appropriate for the Mt. Taylor Mine because it emphasizes shallow- to moderately rooted native grasses, with a limited shrub component, to support semi-arid reclamation, erosion control, and long-term cover stabilization.

The selected species are consistent with regional revegetation guidance that favors locally appropriate native seed sources for disturbed lands in New Mexico and with reclamation literature identifying Indian ricegrass as useful for erosion control and reclamation in arid and semi-arid areas receiving approximately 8 to 14 inches of annual precipitation. Blue grama is also widely used for rangeland improvement, mine-spoil reclamation, and roadside stabilization in the semi-arid Southwest. The total application rate of 9.0 pounds pure live seed per acre is within the range used for final mine reclamation seed mixes in New Mexico and should be adjusted, if necessary, based on seed availability, purity, germination, and agency-approved substitutions before construction.

Seed will be applied using standard mine reclamation equipment, including tracked or wheeled tractors, rangeland seed drills, and mulch spreaders where slopes and access allow. On areas steeper than 3H:1V or where equipment access is limited, hand broadcasting, chain seeding, hydroseeding, or comparable approved methods may be used. Seed shall be certified weed-free, applied on a pure-live-seed basis, and placed during an appropriate seasonal window for native species establishment. Mulch, tackifier, or temporary stabilization may be used where needed to protect seeded areas from wind and water erosion during establishment.

**Table 4-111 Proposed Seed Mix and Application Rates**

| **Common Name** | **Scientific Name** | **Lbs PLS/Acre** |
|---|---|---|
| Blue grama | *Bouteloua gracilis* | 1.5 |
| Indian ricegrass | *Achnatherum hymenoides* | 2.0 |
| Galleta | *Pleuraphis jamesii* | 1.5 |
| Fourwing saltbush | *Atriplex canescens* | 1.0 |
| Black grama | *Bouteloua eriopoda* | 1.0 |
| Sideoats grama | *Bouteloua curtipendula* | 1.5 |
| Prairie junegrass | *Koeleria macrantha* | 0.5 |
| **Total** | | **9.0** |

The seed mix shown in Table 4-11 is appropriate for inclusion in this report because revegetation is a functional component of the final cover system. Establishing a stable native plant community will reduce wind erosion, increase surface roughness, support evapotranspiration from the on-site soil cover, and limit the establishment of undesirable deep-rooted woody species. Final seed procurement should prioritize locally adapted or regionally appropriate native seed lots, and any

substitutions should maintain the same functional objectives of drought tolerance, erosion resistance, shallow rooting, and compatibility with the engineered cover.

## 4.13 Material Placement

Materials requiring permanent containment will be transported to the expanded disposal cell and placed under controlled construction procedures consistent with applicable federal and state requirements, including 40 CFR Part 192, 10 CFR Part 40 Appendix A, and project-specific reclamation specifications. The placement program is intended to maintain waste isolation, minimize voids, control long-term settlement, and preserve the final cover system. Materials managed under this section include:

- Contaminated soils requiring permanent containment;
- Facility debris and non-salvageable structures;
- Dismantled equipment and appurtenances; and
- Other approved closure materials designated for placement in the expanded disposal cell.

Before placement, structural materials and equipment designated for disposal will be prepared to promote safe handling, dense placement, and long-term settlement control. Preparation requirements include:

- Cut, dismantle, crush, or reduce materials to manageable dimensions;
- Stage and compact compressible debris in approved areas before incorporation into disposal cell fill;
- Fill pipes, conduits, tanks, vessels, and similar hollow items with suitable clean earthen material when they cannot be adequately crushed; and
- Place irregular or oversized components so surrounding soil can be compacted against them to minimize bridging, unsupported voids, and future differential settlement.

Disposal cell fill will be placed in controlled lifts to achieve the specified density and provide a stable foundation for subsequent waste placement and final cover construction. Unless otherwise approved by the Engineer, placement requirements include:

- Loose lift thickness not exceeding 12 inches;
- Compaction with suitable construction equipment until the specified density is achieved;
- Minimum compaction of 90 percent of the maximum dry density determined in accordance with ASTM D1557, unless material-specific specifications require otherwise;
- Field density testing at a minimum frequency of one test per 2,500 square feet per lift; and
- Reworking and retesting of nonconforming areas until the compaction requirement is met.

Co-placement of diesel-impacted soils with radiologically impacted materials is addressed in the EA regulatory evaluation completed in March 2026 (and is provided in Appendix J). The evaluation concluded that co-placement within the engineered disposal cell is permissible when

diesel-impacted soils are confirmed to be non-hazardous and managed under the controls listed below. Approximately 7,400 cubic yards of diesel-impacted soil have been identified in the North Controlled Area, where total petroleum hydrocarbon diesel range organics concentrations exceed the NMED industrial soil screening level within a discrete release area.

The diesel-impacted soils are not classified as hazardous waste under RCRA because TPH-DRO is not listed hazardous waste and the soils are not expected to exhibit hazardous characteristics, including ignitability, corrosivity, reactivity, or toxicity. The diesel release area does not coincide with the primary radiological hotspots, and areas where diesel and radiological impacts co-occur contain diesel concentrations below the applicable NMED screening level. Therefore, these materials do not constitute mixed waste under RCRA and the Atomic Energy Act.

Groundwater protection is provided by the engineered containment system and the substantial vertical separation between the disposal cell base and the groundwater table, which is approximately 70 to 95 feet below ground surface near the cell. The liner system, engineered cover, and long-term monitoring program provide isolation of both radiologically impacted materials and diesel-impacted soils. Published compatibility information also indicates that the HDPE liner system is suitable for contact with weathered petroleum hydrocarbons at the concentrations expected in the identified soils.

Implementation controls for diesel-impacted soils will provide traceability, confirm non-hazardous classification, and maintain compliance with the regulatory basis for co-placement. The principal controls include:

- Segregation of diesel-impacted soils during excavation and staging.
- Staging on an impervious surface before disposal cell placement.
- Confirmation sampling to verify non-hazardous classification.
- Separate management of any free-phase product, if encountered.
- Documentation of the final location and depth of diesel-impacted soils placed within the cell.

The co-placement approach reduces long-term environmental risk by consolidating contaminated materials within a single engineered containment system rather than creating a separate disposal location. Centralized placement also improves long-term inspection, monitoring, and institutional control of the affected materials and is consistent with the regulatory framework governing uranium mine reclamation in New Mexico.

During material handling, transport, staging, and placement, dust-control best management practices will be implemented in accordance with applicable EPA, state, and project-specific uranium mine reclamation requirements to protect workers and minimize fugitive dust emissions; these measures will include water application as needed, controlled vehicle speeds, limited drop heights during loading and placement, prompt covering or stabilization of disturbed material, and work stoppage or modified operations when wind conditions could cause unacceptable dust generation.

# 5.0 CONCLUSIONS

## 5.1 General

This report presents the design basis and performance analyses for the engineered cover system proposed for the expanded disposal cell at the Mt. Taylor Uranium Mine, Cibola County, New Mexico (EA Project No. 111360). The cover system is designed as a passive store-and-release (SAR) evapotranspiration barrier consistent with the performance requirements of 40 CFR Part 192, 10 CFR Part 40 Appendix A Criterion 6, and the New Mexico Copper Rule (20.6.7.33 NMAC), as a relevant state performance benchmark for store-and-release cover behavior. The analyses address interconnected performance requirements including frost protection, radon attenuation, biointrusion resistance, infiltration control, store-and-release capacity, slope stability, surface-water management, erosion protection, borrow-source suitability, revegetation, and material placement controls. The following subsections summarize the principal findings and regulatory compliance determinations for the analysis areas presented in Section 4.

## 5.2 Cover System Configuration

The proposed cover system consists of three layers totaling 52 inches (4.33 feet) of engineered material placed over the consolidated waste mass. From top to bottom, the layers are a 12-inch rock mulch admixture (30 percent AASHTO No. 1 gravel and 70 percent on-site soil cover material by volume), a 28-inch compacted on-site soil cover layer, and a 12-inch compacted clay radon barrier. The compacted clay barrier is the primary radon-attenuation and infiltration-control layer. Section 4.6 reports a design saturated hydraulic conductivity of $7.6\times10^{-6}$ cm/s for the compacted clay barrier, and Section 5.8 should therefore rely on that value unless the final design specification is revised. The on-site soil cover layer provides the design frost-depth protection above the clay barrier and the soil moisture storage capacity required for the store-and-release evaluation. The rock mulch layer controls surface water and wind erosion and provides a physical deterrent to burrowing. The layered configuration is evaluated in Section 4.2 of this report.

## 5.3 Frost Depth and Thermal Protection

Frost depth was computed using the Modified Berggren method, which accounts for finite soil heat capacity, differing frozen and unfrozen thermal properties, and non-zero initial soil temperature through a correction coefficient. The design-basis air freezing index is 927.5 degree-days for the 200-year return period, and the resulting design frost depth is approximately 28 inches. The 28-inch on-site soil cover layer therefore provides the required thermal buffer above the compacted clay radon barrier. The clay radon barrier remains at or below the base of the frost-active zone under design conditions, limiting freeze-thaw degradation of the low-permeability layer over the design life. The frost depth analysis is presented in Section 4.3 and Appendix D.

## 5.4 Radon Attenuation

Radon attenuation was evaluated using the one-dimensional steady-state diffusion model implemented in the Wise Uranium Project Uranium Mill Tailings Cover Calculator, following NRC Regulatory Guide 3.64 (NRC, 1989). The regulatory limit is 20 pCi/m²/s averaged over the disposal cell surface, per 40 CFR Part 192 and 10 CFR Part 40 Appendix A Criterion 6.

The design radium-226 (Ra-226) source term of 115 pCi/g is conservative relative to the arithmetic mean of 101.3 pCi/g derived from 124 survey locations across five source areas characterized by AVM Environmental Services, Inc. (2023). Materials from the Ore Pad Area, which exhibit the highest mean Ra-226 activity at 431.6 pCi/g, are designated for placement at the base of the disposal cell to minimize high-activity material near the cover interface. During placement, higher-activity radiological materials will be blended with lower-activity materials, where practical, to minimize elevated spot concentrations and reduce localized variability within the waste mass. The clay radon barrier was modeled with a long-term in-service moisture content of 15.1 percent (15-bar SWCC value), a dry density of 1.59 g/cm³, a porosity of 0.38, and a resulting radon diffusion coefficient of $4.62\times10^{-7}$ m²/s.

The model yields a bare-source surface flux of 42.10 pCi/m²/s in the absence of cover and a design surface flux of 13.99 pCi/m²/s at the top of the rock mulch layer. The three-layer cover system attenuates 66.77 percent of the bare-source flux, producing a design value that is 30 percent below the regulatory limit of 20 pCi/m²/s. The radon attenuation analysis is presented in Section 4.4.

## 5.5 Biointrusion

The cover system is designed to satisfy the biointrusion-related requirements of 10 CFR Part 40 Appendix A Criterion 6, which requires radiological hazard control for 1,000 years to the extent reasonably achievable, and in any case for at least 200 years. Current NRC and DOE guidance recognizes that shallow-rooted native vegetation can support SAR cover performance by removing stored soil moisture through transpiration. The primary biointrusion concern is therefore associated with deep-rooted woody plants and burrowing animals that could physically disturb or penetrate the compacted clay radon barrier.

Physical deterrents are provided at multiple levels. The 12-inch rock mulch surface layer presents a coarse, discontinuous substrate that resists burrowing and reduces the likelihood of direct animal disturbance. The 28-inch compacted on-site soil cover layer separates routine biological activity from the clay radon barrier while supporting the shallow-rooted native grass community specified in the revegetation plan. The compacted clay radon barrier is protected by the overlying 40 inches of cover material. Biointrusion controls will be supplemented by post-closure inspection and adaptive management for woody vegetation, burrowing activity, cracking, erosion, or localized cover damage. The biointrusion analysis is presented in Section 4.5.

## 5.6 Infiltration, Water Balance, and Copper Rule Compliance

The infiltration analysis is based on the 2018–2025 San Mateo on-site meteorological record, which yields a mean annual precipitation (MAP) of 10.01 in/yr and a Thornthwaite (1948) potential evapotranspiration (PET) of 26.45 in/yr. The resulting aridity index, expressed as PET/P = 2.64 in Section 4.6, confirms that the site climate is strongly water-limited, with evapotranspirative demand substantially exceeding available precipitation throughout most of the year.

Actual evapotranspiration (AET) was estimated using the Budyko (1948) method and accounts for 9.30 in/yr, or 92.9 percent of MAP. Surface runoff, estimated using the SCS Curve Number method with CN = 55 on a monthly time step, is 0.021 in/yr and is negligible because only peak monsoon months exceed the initial abstraction threshold of 1.64 inches. The resulting analytical water-balance estimate of percolation is 0.69 in/yr, representing a conservative upper bound of 6.9 percent of MAP. Two-dimensional transient seepage modeling using GeoStudio SEEP/W, which captures inter-annual soil moisture storage dynamics not reflected in the steady-state water balance, yields a design-basis percolation rate of 0.40 in/yr, or 4.0 percent of MAP. This value is adopted as the design basis.

Copper Rule compliance was evaluated by comparing the water storage capacity of the 28-inch on-site soil cover layer against the seasonal precipitation thresholds specified in 20.6.7.33 NMAC. Using the 2018–2025 San Mateo station record, winter precipitation from October through March totals 2.87 inches and summer precipitation from April through September totals 7.14 inches. The winter threshold governs, resulting in a required storage capacity of 2.73 inches. The nominal available water holding capacity (AWHC) of the on-site soil cover (CL-ML), derived from laboratory Soil Water Characteristic Curve testing, is 0.10 in/in. The 28-inch layer provides 2.80 inches of storage, exceeding the 2.73-inch requirement by 0.07 inch. Total cover thickness of 52 inches also exceeds the Copper Rule minimum of 36 inches. The infiltration and Copper Rule analysis is presented in Section 4.6.

## 5.7 Surface Water Hydrology and Erosion Protection

Erosion protection design follows the procedures of NUREG-1623 (NRC, 2002) and NUREG/CR-4620 (Nelson et al., 1986). The design storm for cover rock mulch sizing is the Probable Maximum Precipitation (PMP), developed using the HMR-49 procedures documented in Appendix I for the Mt. Taylor site. For the disposal cell cover, the short-duration PMP governs rock mulch erosion checks because cover-slope times of concentration are short. For the diversion channel, the PMP-derived Probable Maximum Flood (PMF) governs watershed response and channel lining design. The 100-year, 24-hour precipitation depth documented in Appendix D is substantially less severe than the PMP condition and therefore does not govern erosion-protection design.

Peak unit discharges were computed using the Rational Method with a runoff coefficient of 0.80 and a flow concentration factor of 3.0 per NUREG-1623. Rock mulch $D_{50}$ requirements were evaluated using the Abt-Johnson method. The AASHTO No. 1 gravel component of the admixture, with nominal $D_{50}$ = 2.20 inches, provides a factor of safety of 2.65 at 50-foot slope segments, declining to 1.08 at 250 feet and 0.97 at 300 feet. A maximum interceptor berm or grade-break spacing of 250 feet is adopted as the design standard, maintaining a factor of safety greater than 1.0 for unsupported slope runs under the Appendix I design assumptions.

Filter compatibility of the rock mulch admixture was evaluated using the Leps (1973) interstitial velocity criterion. A conservative gravel-only analysis using $D_{50}$ = 2.20 inches yields an interstitial velocity of 1.99 ft/s, which exceeds the 1.0 ft/s threshold for open-graded rockfill. A refined analysis using the governing blended admixture $D_{50}$ of 0.0106 inch reflects the 70 percent on-site soil cover fines that fill and effectively reduce the inter-gravel void space, yielding an interstitial velocity of 0.004 ft/s, well below the 0.5 ft/s no-filter threshold. The Terzaghi (1943) filter-

compatibility criterion is independently confirmed, with the blended $D_{15}$ to subgrade $D_{85}$ ratio equal to 0.045, which is less than the allowable value of 5.0. A separate filter layer beneath the rock mulch cover is therefore not required. Shield's incipient motion and Pemberton-Lara (1984) scour-depth analyses confirm that the armor layer develops within the 12-inch admixture depth during the design storm before scour reaches the underlying on-site soil cover. The computed scour depth is approximately 10.3 inches, less than the 12-inch admixture thickness. Wind erosion is evaluated using WEPS and the EPA benchmark of less than 2 tons/acre/year, as described in Section 4.9.4. The surface water hydrology and erosion protection analysis is presented in Section 4.9 and Appendix I.

## 5.8 Slope Stability, Borrow Sources, Revegetation, and Material Placement

The slope stability analysis presented in Section 4.8 demonstrates that the combined expanded disposal cell configuration with 5H:1V final cover slopes satisfies the applicable static and pseudo-static stability criteria for the analyzed section. The static factor of safety exceeds the target value of 1.5, and the pseudo-static factor of safety using a horizontal seismic coefficient of 0.14 exceeds the target value of 1.1. Borrow-source evaluations in Sections 4.10 and 4.11 indicate that suitable clay and on-site soil cover materials are available onsite, subject to field verification, selective excavation, laboratory confirmation, and construction quality assurance. The revegetation plan in Section 4.12 supports erosion control, evapotranspiration, and long-term cover stabilization using native, drought-adapted species. Material placement controls in Section 4.13 address waste consolidation, compaction, settlement control, diesel-impacted soil co-placement, dust control, and traceability during construction.

## 5.9 Regulatory Compliance Summary

The performance analyses summarized in Sections 5.2 through 5.8 collectively demonstrate that the proposed 52-inch three-layer engineered cover system satisfies applicable regulatory performance requirements. The clay radon barrier remains below the frost-active zone, preserving its hydraulic integrity over the design life. The design surface radon flux of 13.99 pCi/m²/s is 30 percent below the 40 CFR Part 192 limit of 20 pCi/m²/s. The multi-layer physical configuration, in combination with the targeted revegetation plan and post-closure stewardship, limits biointrusion risk to manageable levels consistent with NRC guidance. The design-basis percolation rate of 0.40 in/yr, or 4.0 percent of MAP, confirms effective hydraulic isolation of the waste mass, and the Copper Rule storage benchmark of 2.73 inches is satisfied with a margin of 0.07 inch under nominal AWHC conditions. The rock mulch admixture with a 250-foot maximum berm spacing provides adequate resistance to PMP-driven surface erosion and functions as a self-filtering medium without a separate filter layer. The slope stability, borrow-source, revegetation, and material placement evaluations provide additional support for constructability and long-term cover performance. The cover system design is considered to satisfy the long-term performance requirements of 40 CFR Part 192, 10 CFR Part 40 Appendix A Criterion 6, and the applicable state review framework and is recommended for submittal to the NRC and NMED for review and approval.

## 6.0 REFERENCES

Abt, S.R., Johnson, T.L., Thornton, C.I., and Trabant, S.C. (1998). Riprap Sizing at the Toe of Embankment Slopes. Journal of Hydraulic Engineering, ASCE.

Aldrich, H.P. and Paynter, H.M. (1953). Analytical studies of freezing and thawing of soils. First interim report, U.S. Army Corps of Engineers, New England Division, Arctic Construction and Frost Effects Laboratory (ACFEL). Technical Report 42.

Alief, M. H., & Kern, R. A. (1989). Geology of Mt. Taylor uranium mine, Grants, New Mexico. AAPG Bulletin, 73(9), 1146.

Berggren, W.P., (1943). Prediction of Temperature Distribution in Frozen soils. Trans. Am. Geophys. Union.

Caldwell, T.G., Tabatabai, S., Huntington, J.M., Davies, G.E., & Fuhrmann, M. (2022). Evapotranspiration Covers at Uranium Mill Tailings Sites. Vadose Zone Journal, 21, e2022.

Cedar Creek Associates, Inc. (2023). Biointrusion Risk Evaluation, Mt. Taylor Mine Disposal Cell, Cibola County, New Mexico.

Dwyer, S.F. (2003). Water Balance Measurements and Computer Simulations of Landfill Covers. PhD dissertation, University of New Mexico.

Hansen, E.M., Schwarz, F.K., and Riedel, J.T. (1984). Probable Maximum Precipitation Estimates, Colorado River and Great Basin Drainages. Hydrometeorological Report No. 49. National Oceanic and Atmospheric Administration and U.S. Army Corps of Engineers.

Kirpich, Z.P. (1940). Time of Concentration of Small Agricultural Watersheds. Civil Engineering, 10(6).

Leps, T.M. (1973). Flow Through Rockfill. In Embankment Dam Engineering, John Wiley and Sons, pp. 97-107.

U.S. Departments of Army and Air Force. (1988). Arctic and Subarctic Construction Calculation Methods for Determination of Depths of Freeze and Thaw in Soils, First Interim Report. Army TM 5-852-6, Air Force AFR 88-19, Vol. 6.

Engineering Analytics, Inc. (2025) Closeout/Closure Plan, Mt. Taylor Mine, Existing Mine Permit No. C1002RE, Discharge Permit, Dated October 15.

U.S. Environmental Protection Agency (EPA). 40 CFR Part 192: Health and Environmental Protection Standards for Uranium and Thorium Mill Tailings.

Geo-Slope International Ltd. (GEO-SLOPE). (2021). GeoStudio-SLOPE/W. Calgary, Alberta, Canada.

Geo-Slope International Ltd. (GEO-SLOPE). (2023). GeoStudio-SEEP/W. Calgary, Alberta, Canada.

Intergovernmental Panel on Climate Change (IPCC) (2023). Climate Change 2023, Synthesis Report for the Sixth Assessment Report on Climate Change. March.

Lambe, T.W. and R.V. Whitman. (1969). Soil Mechanics. John Wiley & Sons, New York.

Lee, K.L. and C.K. Shen. (1969). Horizontal Movements related to Subsidence. Journal of Soil Mechanics and Foundation Division, ASCE Volume 95. January.

Modified Berggren Formula (MBF). (1968). U.S. Army Cold Regions Research and Engineering Laboratory, CRREL Special Report SR 122. October.

Morgenstern, N.R. and Price, V.E. (1965) The Analysis of The Stability of General Slip Surfaces. Geotechnique, 15, 79-93.

Morrison-Knudsen Environmental Corporation. (1993). UMTRA-Naturita, Embankment Design, Settlement Analysis and Cracking Potential Evaluation. Calc. No. 17-740-02-01. May.

Nelson, R., Castellvi. F., Ndlovu L.S., Campell, G.S., & Stockle, C.O., (2023), ClimGen Version 4.4.0. Washington State University.

Nelson, J.D., Abt, S.R., Volpe, R.L., van Zyl, D., Hinkle, N.E., and Staub, W.P. (1986). Methodologies for evaluating long-term stabilization designs of uranium mill tailings impoundments. NUREG/CR-4620 ORNL/TM-10067.

Pemberton, E.L. and Lara, J.M. (1984). Computing Degradation and Local Scour. Technical Guideline for Bureau of Reclamation.

Paster, T.P. Ph.D. (2002). Petrographic Analyses of Andesite and Sandstone to be Used as Erosion Protection for a Reclaimed Uranium Tailings Facility. August 19.

Smith, G. E. and Rager, R. E. (2002). Protective Layer Design in Landfill Covers Based on Frost Penetration. ASCE J. Geotechnical/Geoenvironmental Engineering, 128:9, 794-799.

T.L. Johnson (2002). Design of Erosion Protection for Long-Term Stabilization Final Report. NUREG-1623.

Temple, D.M., Robinson, K.M., Ahring, R.M., and Davis, A.G. (1987). Stability Design of Grass Lined Open Channels. Agriculture Handbook 667. U.S. Department of Agriculture, Agricultural Research Service.

U.S. Department of Energy (U.S. DOE). (1989). Technical Approach Document, Revision II, Uranium Mill Tailings Remedial Action Project, UMTRA-DOE/AL 050425.0002, Albuquerque, New Mexico.

U.S. Department of Defense (U.S. DOD). (2022). Unified Facilities Criteria (UFC) Soil Mechanics (DM 7.1). UFS 3-220-10. February 1.

U.S. Nuclear Regulatory Commission (NRC). (1989). Calculation of Radon Flux Attenuation by Earthen Uranium Mill Tailings Covers, Regulatory Guide 3.64.

U.S. Nuclear Regulatory Commission (NRC). (2002). NUREG-1623, Design of Erosion protection for long term stabilization. August.

U.S. Nuclear Regulatory Commission (NRC). (2003). NUREG-1620, Standard review plan for the review of a reclamation plan for mill tailings sites under title II of the uranium mill tailings radiation control act of 1978. June.

U.S. Nuclear Regulatory Commission (NRC). (2008). Regulatory Guide 3.11, design construction, and inspection of embankment retention systems at uranium recovery facilities. November.

Benson, C.H., Albright, W.H., Fratta, D.O., Tinjum, J.M., Kucukkirca, E., Lee, S.H., Scalia, J., Schlicht, P.D., and Wang, X. (2011). Engineered Covers for Waste Containment: Changes in Engineering Properties and Implications for Long-Term Performance Assessment. NUREG/CR-7028, Volumes 1 and 2. U.S. Nuclear Regulatory Commission, Washington, D.C. December 2011.

U.S. Nuclear Regulatory Commission (NRC). (2013). 10 CFR Part 192 – Health and Environmental protection standards for uranium and thorium mill tailings.

U.S. Nuclear Regulatory Commission (NRC). (2020). 10 CFR Part 40 – Domestic licensing source material, https://www.nrc.gov/reading-rm/doc-collections/cfr/part040/. (Accessed 2023).

U.S. Nuclear Regulatory Commission (NRC). 10 CFR Part 40, Appendix A: Criteria Relating to the Operation of Uranium Mills and the Disposition of Tailings or Wastes Produced by the Extraction or Concentration of Source Material from Ores Processed Primarily for Their Source Material Content. Criterion 6.

U.S. Nuclear Regulatory Commission (NRC). (1982). 10 CFR Part 61.56 – Waste Characteristics https://www.nrc.gov/reading-rm/doc-collections/cfr/part061/full-text.html#part061-0056 (Accessed 2024).


U.S. Nuclear Regulatory Commission (NRC). (2021). Appendix A to Part 100—Seismic and Geologic Siting Criteria for Nuclear Power Plants, https://www.nrc.gov/reading-rm/doc-collections/cfr/part100/part100-appa.html. (Accessed 2023).


U.S. Nuclear Regulatory Commission (NRC). (2022). Evaluation of In-Service Radon Barriers over Uranium Mill Tailings Disposal Facilities. NUREG/CR-7288. March.

U.S. Nuclear Regulatory Commission (NRC). (2023). 10 CFR 20 – Standards for Protection Against Radiation, April 14.

Western Regional Climate Center (2023). Evaporation Stations. https://wrcc.dri.edu/Climate/comp_table_show.php?stype=pan_evap_avg


# FIGURES











T:\111360 Mt. Taylor\Site Location CCP.dwg SAVED: 7/7/26 PRINTED: 7/27/26

Project No. 111360

July 2026

Engineering Analytics, Inc.
*Now Part of* ***MacKay***

**FIGURE 2-1**
**SITE LOCATION MAP**
**MT. TAYLOR MINE**





GENERAL NOTES:

G.1 BASE MAP ADAPTED FROM CIBOLA FOREST SERVICE MAP.

G.2 THE PERMIT AREA INCLUDES A RIGHT-OF-WAY ALONG THE TREATED WATER DISCHARGE PIPELINE. PIPELINE WAS REMOVED IN 2025.

G.3 THE PERMIT AREA INCLUDES A 50' WIDE CORRIDOR ALONG THE ACCESS ROAD FROM HIGHWAY 605 TO THE MINE SITE.




MINE UNITS AND OTHER AREAS:

| | | | | | |
|---|---|---|---|---|---|
| 1 | MINE WATER TREATMENT AREA | 7 | BORROW AREA "B" | 13 | CHILLER BENCH AREA |
| 2 | ORE PAD | 8 | SOUTH STORM WATER POND | 14 | SERVICE AND SUPPORT AREA |
| 3 | ORE PAD RUNOFF RETENTION POND | 9 | EXISTING WASTE ROCK PILE/ DISPOSAL AREA | 15 | OLD ORE LOADING AREA |
| 4 | NORTH DIVERSION CHANNEL | 10 | DISPOSAL CELL EXPANSION AREA | 16 | MINE SHAFTS |
| 5 | BORROW AREA "A" | 11 | SOUTH DIVERSION CHANNEL | 17 | BORROW AREA "C" |
| 6 | MINE ACCESS ROAD | 12 | COMPRESSOR BENCH AREA | 18 | WINDBLOWN AREA |

LEGEND:

- MINE SITE AREA
- SECTION 24 BOUNDARY
- ROADWAY
- FENCE
- EXISTING TOPOGRAPHY
- DRAINAGE PATHWAYS
- MINE BUILDINGS (PRIOR TO REMOVAL ACTIVITIES)

GENERAL NOTES:

G.1 THE MINE PERMIT AREA INCLUDES THE RIGHT OF WAY ALONG THE TREATED WATER DISCHARGE PIPELINE AND A 50' WIDE CORRIDOR FOR AN ACCESS ROAD (SEE FIGURE 1-3).

G.2 AFFECTED AREAS INCLUDE BUT ARE NOT LIMITED TO BORROW AREA "B", BORROW AREA "C", AND WINDBLOWN AREA. EVALUATION OF OTHER POSSIBLE AFFECTED AREAS IS ONGOING.

G.3 THIS DRAWING SHOWS THE SITE CONDITIONS AS OF JULY 2025. SEE FIGURE 1-2B AND TABLE 4.2 FOR DETAILED FACILITY DISPOSITION INFORMATION.

G.4 TOPOGRAPHY BASED ON A 2012 AERIAL SURVEY BY THOMAS R. MANN AND ASSOCIATES AND 2021 SURVEYS BY SOUTHWEST SURVEYING SOLUTIONS (S3).

NORTH

SCALE IN FEET

0 800'

T:\111360 Mt. Taylor\Site Existing.dwg SAVED:1/13/26 PRINTED:7/27/26

Project No. 111360

July 2026

Engineering Analytics, Inc.

**FIGURE 2-2**
**SITE LOCATION AND EXISTING CONDITIONS**
**MT. TAYLOR MINE**

LEGEND:
- MINE SITE AREA
- ROADWAY
- FENCE
- EXISTING TOPOGRAPHY
- DRAINAGE PATHWAYS
- TEST PIT LOCATION

NORTH

SCALE IN FEET
0 300'

McKINLEY CO.

CIBOLA CO.

C-1 C-2 C-3 C-4 C-5 C-6 C-7 C-8 C-9 C-10 C-11 C-12 C-13

BORROW AREA "C"

UNDISTURBED AREA

BORROW AREA "A"

A-1 A-2 A-3 A-4 A-5 A-6

Marquez

Arroyo

MINE RD.

POND 8

POND 4

POND 5

PONDS 6&7

POND 3

POND 2

POND 1

ORE PAD

SUBSTATION

UNDISTURBED AREA

BORROW AREA "B"

B-1 B-2 B-3 B-4 B-5

SAN MATEO

MAIN STREET

7240 7250 7260 7270 7280 7290 7300 7320 7340 7350 7400 7450 7500


T:\111360 Mt. Taylor\Boring Locations.dwg SAVED:1/13/26 PRINTED:7/27/26

Project No. 111360

July 2026

Engineering Analytics, Inc.

**FIGURE 2-3**
**TEST PIT LOCATION MAP**
**MT. TAYLOR MINE**




NOT TO SCALE

T:\111360 Mt. Taylor\Reclamation Liner.dwg SAVED: 7/27/26 PRINTED: 7/31/26

Project No. 111360


July 2026

Engineering Analytics, Inc.

**FIGURE 4-1**
**FINAL RECLAMATION COVER SYSTEM**
**MT. TAYLOR MINE**

## Material Properties

| Color | Name | Material Model | Vol. WC. Function | K-Function |
|---|---|---|---|---|
| | 1-Rock Mulch | Saturated / Unsaturated | (2025)Rock Mulch | (2025)Rock Mulch |
| | 2-On-Site Soil | Saturated / Unsaturated | (2025)On-Site Soil | (2025)On-Site Soil |
| | 3-Clay Layer | Saturated / Unsaturated | (2025)Clay Layer | (2025)Clay Layer |
| | 4-Waste Material | Saturated / Unsaturated | (2025) Waste | (2025)Waste |




## Boundary Conditions


| Color | Name | Category |
|---|---|---|
| | Climate data | Hydraulic |
| | Flux review Boundary | Hydraulic |
| | Unit Gradient BC | Hydraulic |
| | Zero-Pressure Head | Hydraulic |

T:\111360 Mt. Taylor\Expanded Slope calcs.dwg SAVED:11/25/25 PRINTED: 7/27/26



Engineering Analytics, Inc.

**FIGURE 4-2**
**INFILTRATION ANALYSIS MODEL PROFILE**
**MT. TAYLOR MINE**




- MONITOR WELL
- DRY WELL (PLUGGED AND ABANDONED)
- RECOVERY WELL
- DEWATERING WELL
- FACILITY WATER SUPPLY
- PROPOSED WELL 2025 SIP
- PROPOSED BORING 2025 SIP
- STORMWATER DRAINAGE
- FENCE
- ROADWAY
- FORMER LAGOON AREA
- EXISTING TOPOGRAPHY
- PROPOSED TOPOGRAPHY

NOTE:
MAX DEPTH AT HIGHEST POINT;


| Current El | Proposed El | Height |
|---|---|---|
| 7344' | 7444' | 100' |


EXPANDED VOLUME
(Compared to original disposal cell volume)

| CUT | FILL | NET |
|---|---|---|
| 1,000 | 1,103,200 | 1,102,200 |

in cubic yards

PLAN
SCALE IN FEET
0 400'
NORTH




SECTIONS
SCALE IN FEET
0 300'


T:\111360 Mt. Taylor\Site Expanded Stability.dwg SAVED: 7/27/26 PRINTED: 7/27/26

Project No. 111360


July 2026

Engineering Analytics, Inc.
*Now Part of **MacKay***

**FIGURE 4-3**
**SECTIONS USED FOR STABILITY ASSESSMENT**
**MT. TAYLOR MINE**




Global Stability Result at the Left Side




Global Stability Result at the Right Side

NOTE:
Factor of Safety (FS) above the regulatory requirement of 1.5.

T:\111360 Mt. Taylor\Expanded Slope calcs.dwg SAVED:11/25/25 PRINTED:7/27/26




Engineering Analytics, Inc.

**FIGURE 4-4**
**STABILITY CROSS SECTIONS**
**MT. TAYLOR MINE**

**Material Properties**


| Color | Name | Unit Weight (pcf) | Effective Cohesion (psf) | Effective Friction Angle (°) |
|---|---|---|---|---|
| | Clay | 120 | 0 | 24 |
| | In Situ Cover Soil | 110 | 0 | 25 |
| | Native Material | 122 | 0 | 25 |
| | Rock Mulch | 115 | 0 | 35 |
| | Waste Material | 102 | 0 | 25 |




Pseudo-Static Stability Analyses Result to the Left

**Material Properties**

| Color | Name | Unit Weight (pcf) | Effective Cohesion (psf) | Effective Friction Angle (°) |
|---|---|---|---|---|
| | Clay | 120 | 0 | 24 |
| | In Situ Cover Soil | 110 | 0 | 25 |
| | Native Material | 122 | 0 | 25 |
| | Rock Mulch | 115 | 0 | 35 |
| | Waste Material | 102 | 0 | 25 |




Pseudo-Static Stability Analyses Result to the Right

NOTE:
The pseudo-static analyses show that the factor of safety (FS) are above 1.1, which is the regulatory criterion.


T:\111360 Mt. Taylor\Expanded Slope calcs.dwg SAVED:11/25/25 PRINTED:7/27/26

Project No. 111360

July 2026

Engineering Analytics, Inc.

**FIGURE 4-5**
**STABILITY CROSS SECTIONS**
**MT. TAYLOR MINE**




MINE UNITS AND OTHER AREAS:

| | | | |
|---|---|---|---|
| 1 | MINE WATER TREATMENT AREA | 10 | DISPOSAL CELL EXPANSION AREA |
| 2 | ORE PAD | 11 | SOUTH DIVERSION CHANNEL |
| 3 | ORE PAD RUNOFF RETENTION POND | 12 | COMPRESSOR BENCH AREA |
| 4 | NORTH DIVERSION CHANNEL | 13 | CHILLER BENCH AREA |
| 5 | BORROW AREA "A" | 14 | SERVICE AND SUPPORT AREA |
| 6 | MINE ACCESS ROAD | 15 | OLD ORE LOADING AREA |
| 7 | BORROW AREA "B" | 01 | 16 MINE SHAFTS |
| 8 | SOUTH STORM WATER POND | 17 | BORROW AREA "C" |
| 9 | EXISTING WASTE ROCK PILE/ DISPOSAL AREA | 18 | WINDBLOWN AREA |

LEGEND:

- MINE SITE AREA
- SECTION 24 BOUNDARY
- ROADWAY
- FENCE
- EXISTING TOPOGRAPHY
- DRAINAGE PATHWAYS
- MINE BUILDINGS (PRIOR TO REMOVAL ACTIVITIES)

GENERAL NOTES:

G.1 THE MINE PERMIT AREA INCLUDES THE RIGHT OF WAY ALONG THE TREATED WATER DISCHARGE PIPELINE AND A 50' WIDE CORRIDOR FOR AN ACCESS ROAD (SEE FIGURE 1-3).

G.2 AFFECTED AREAS INCLUDE BUT ARE NOT LIMITED TO BORROW AREA "B", BORROW AREA "C", AND WINDBLOWN AREA. EVALUATION OF OTHER POSSIBLE AFFECTED AREAS IS ONGOING.

G.3 THIS DRAWING SHOWS THE SITE CONDITIONS AS OF JULY 2025. SEE FIGURE 1-2B AND TABLE 4.2 FOR DETAILED FACILITY DISPOSITION INFORMATION.

G.4 TOPOGRAPHY BASED ON A 2012 AERIAL SURVEY BY THOMAS R. MANN AND ASSOCIATES AND 2021 SURVEYS BY SOUTHWEST SURVEYING SOLUTIONS (S3).

NORTH

SCALE IN FEET

0 500'

T:\111360 Mt. Taylor\Site Existing.dwg SAVED:1/13/26 PRINTED:7/27/26

Project No. 111360

July 2026

Engineering Analytics, Inc.

**FIGURE 4-6**
**LOCATION OF CLAY BORROW SOURCE**
**MT. TAYLOR MINE**

# APPENDIX A
# Test Pit Logs for 2025 Field Investigation

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE: date

TEST PIT NO.: A-1

## PROJECT INFORMATION

PROJECT: MT. TAYLOR

PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## FIELD INFORMATION


DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER:

## TEST PIT LOCATION




## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** A-1




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | A1 | BKT |
| 4' | A1C | CA |
| 6' | A1 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 2" | VEGETATION, SAND, DRY, (2.5Y, 5/3), LOOSE |
| 2 | 2" - 4' | SAND, DRY (2.5Y, 5/3), LOOSE, NON-FROZEN BITS, FROZEN |
| 3 | 4'-E.O.B. | VERY SANDY CLAY, DRY, TAN/ BROWN (2.5Y, 4/3), CHUNKY, BRITTLE, FROZEN |

**NOTES:** HARD TO TELL, GROUND IS FROZEN, MAY BE CLAYEY SAND SILT

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: A-2

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER:

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** A-2




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | A2 | BKT |
| 6' | A2 | BKT |
| NR | --- | CA |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 2" | VEGETATION, SAND, DRY, (2.5Y, 5/3), LOOSE |
| 2 | 2" - E.O.B. | SAND, DRY, (TAN 2.5Y, 5/3), VERY LOOSE, NO PLASTICITY |
| | | NO CLAY |

**NOTES:**

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: A-3

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER:

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** A-3




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | A3 | BKT |
| 6' | A3 | BKT |
| NR | --- | CA |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 3" | VEGETATION, SAND, DRY, (2.5Y, 5/3), LOOSE, NO PLASTICITY |
| 2 | 3" - E.O.B. | SAND, FROZEN, (2.5Y, 5/3), LOOSE BITS, NO PLASTICITY |

**NOTES:** NO CLAY

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: **A-4**

## PROJECT INFORMATION

PROJECT: MT. TAYLOR

PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER:

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** A-4




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | A4C | CA |
| 3' | A4 | BKT |
| 6' | A4 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 2" | VEGETATION, SAND, DRY, (2.5Y, 5/3), LOOSE |
| 2 | 2" -3' | SAND, FROZEN, (2.5Y, 5/3), NO PLASTICITY, CAME OFF IN BLOCKS, ROOTS |
| 3 | 3' - E.O.B. | VERY SANDY CLAY, (TAN/ BROWN 2.5Y, 5/3), CHUNKY, BRITTLE |
| | | E.O.T.P. = 6' |

**NOTES:** HARD TO DISTINGUISH CLAY FROM FROZEN SAND.

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: A-5

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER:

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** A-5




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | A5 | BKT |
| 6' | A5 | BKT |
| NR | --- | CA |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 2" | VEGETATION, SAND, DRY, (2.5Y, 5/3), NO PLASTICITY |
| 2 | 2" - E.O.B. | SAND, (2.5Y, 5/3), VERY LOOSE, VERY FINE, CHUNKS THAT ARE BRITTLE |
| | | E.O.T.P. = 6' |

**NOTES:** NO CLAY

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: A-6

## PROJECT INFORMATION

PROJECT: MT. TAYLOR

PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## FIELD INFORMATION


DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER:

## TEST PIT LOCATION




## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** A-6




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | A6 | BKT |
| 5' | A6 | BKT |
| NR | --- | CA |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 2" | VEGETATION, SAND, DRY, (2.5Y, 5/3), LOOSE, NO PLASTICITY |
| 2 | 2" - 4' | SILTY SAND, SLIGHTLY MOIST, (2.5Y, 5/3), LOOSE, VERY FINE, NO PLASTICITY |
| 3 | 4' - E.O.B. | SILTSTONE, DRY, GRAY (2.5Y, 7/1), FINE, THIN FRAGMENTS AND SILT, NO PLASTICITY |
| | | E.O.T.P. = 6' |

**NOTES:**

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: **B-1**

## PROJECT INFORMATION

PROJECT: MT. TAYLOR

PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## FIELD INFORMATION


DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## TEST PIT LOCATION




NOT TO SCALE

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 5 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** B-1




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | BK1-3 | BKT |
| 5' | BK1-5 | BKT |
| 2' | NR | CA |
| 3' | NR | CA |
| 5' | NR | CA |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 6" | VEGETATION AND TOPSOIL (MOSTLY VEGETATION), SAND |
| 2 | 6" - 3' | SAND WITH GRAVEL, DRY, LOOSE SAND WITH GRAVEL UP TO 1.5", BROWN/TAN (2.5Y 5/3), NON PLASTIC |
| 3 | 3' - E.O.B. | SANDY CLAY, BROWN/ BLACK (2.5Y, 2.5/1), VERY STIFF, MIXED, INTERBEDDED, CLAY LAYER<br>VERY STIFF AT BOTTOM |
| | | E.O.T.P. = 5' |

**NOTES:** HARD CLAY LAYERS AT 3FT, BACKHOE STRUGGLING, REFUSAL AT 5'.

NO CAL RECOVERY (SAND IN 2FT CAL, 3FT & 5FT 100 BLOWS).

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: **B-2**

## PROJECT INFORMATION

PROJECT: MT. TAYLOR

PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## FIELD INFORMATION


DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## TEST PIT LOCATION




## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** B-2




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 8" | B2 | BKT |
| 5' | B2 | BKT |
| 1' | NR | CA |
| 4' | B-2C | CA |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 4" | OVERBURDEN, VEGETATION, LOOSE SAND |
| 2 | 4" - 1' | CLAY, BROWN (2.5Y 2.5/1), STIFF, PLASTIC, MOISTURE PRESENT BUT FROZEN |
| 3 | 1' - E.O.B. | SAND, DRY, TAN/ BROWN (2.5Y, 2.5/1), VERY LOOSE, NO PLASTICITY |
| | | E.O.T.P. = 6' |

**NOTES:** CAL BARREL ON CLAY LAYER IS FROZEN, 0/ 100

TRYING WITH HAND DRIVE BUT NOT WORKING

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: B-3

## PROJECT INFORMATION

PROJECT: MT. TAYLOR

PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## FIELD INFORMATION


DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## TEST PIT LOCATION




NOT TO SCALE

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** B-3




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 2' | B3-C | CA |
| 4' | B3 | BKT |
| 6' | B3 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 4" | OVERBURDEN, VEGETATION, LOOSE SAND |
| 2 | 4" - E.O.B. | SAND, TAN/ BROWN (2.5Y, 2.5/3), VERY LOOSE, NO PLASTICITY |
| | | E.O.T.P. = 6' |

**NOTES:** NO CLAY IN HOLE AT ALL

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: **B-4**

## PROJECT INFORMATION

PROJECT: MT. TAYLOR

PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## FIELD INFORMATION


DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## TEST PIT LOCATION




NOT TO SCALE

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** B-4




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | B4 | BKT |
| 5' | B4 | BKT |
| 5' | B4-C | CA |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 4" | VEGETATION, DRY, LOOSE SAND |
| 2 | 4" - 3.5' | SAND, DRY, TAN/ BROWN (2.5Y, 2.5/3), VERY LOOSE, NO PLASTICITY |
| 3 | 3.5' - E.O.B. | CLAY WITH SAND, DARK BROWN (2.5Y, 2.5/1), STIFF, PLASTIC |
| | | E.O.T.P. = 6' |

**NOTES:** 100 DRIVES

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: **B-5**

## PROJECT INFORMATION

PROJECT: MT. TAYLOR

PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## FIELD INFORMATION


DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## TEST PIT LOCATION




NOT TO SCALE

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** B-5




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | B5 | BKT |
| 6' | B5 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 4" | VEGETATION, DRY, LOOSE SAND |
| 2 | 4" - E.O.B. | SAND, DRY, BROWN/ TAN (2.5Y, 5/3), VERY LOOSE, NO PLASTICITY |
| | | E.O.T.P. = 6' |

**NOTES:** NO CLAY TO 7'

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-1

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 5 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-1




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | C-1C | CA |
| 2' | C-1 | BKT |
| 5' | C-1 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 6" | SAND WITH VEGETATION, DRY, TAN/ BROWN (2.5Y, 5/3), LOOSE |
| 2 | 6" - 3' | VERY LOOSE SAND, DRY, TAN/ BROWN (2.5Y, 5/3), NO PLASTICITY |
| 3 | 3' - E.O.B. | SANDY CLAY WITH SAND, MOTTLED BROWN (5YR, 3/1), BRITTLE, CALCITE |
| | | E.O.T.P. = 6' |

**NOTES:**

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-2

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 5 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-2




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | C-2C | CA |
| 2' | C-2 | BKT |
| 5' | C-2 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 3" | SANDY VEGETATION, TAN (2.5Y, 5/3) |
| 2 | 3" - E.O.B. | SANDY CLAY, DRY, BROWN (5YR, 3/1), BRITTLE, LOOSE/ CHUNKS, CALCITE |
| | 4' | MORE SAND |
| | | E.O.T.P. = 6' |

**NOTES:**

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-3

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-3




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | C-3C | CA |
| 2' | C-3 | BKT |
| 5' | C-3 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 6" | SAND, LOTS OF VEGETATION, TAN (2.5Y, 5/3) |
| 2 | 6" - 3' | VERY LOOSE SAND, DRY, TAN/ BROWN (2.5Y, 5/3), NO PLASTICITY |
| 3 | 3' - E.O.B. | SANDY CLAY, DRY, MOTTLED BROWN (5YR, 3/1), BRITTLE |
| | | E.O.T.P. = 6' |

**NOTES:** ISSUES WITH HAND SAMPLER

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-4

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-4




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | C-4C | CA |
| 4' | C-4 | BKT |
| 6' | C-4 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 3" | VEGETATION, SAND, LOOSE |
| 2 | 3" - 3' | VERY LOOSE SAND, DRY, TAN/ BROWN (2.5Y, 5/3), NO PLASTICITY |
| 3 | 3' - 5' | SANDY CLAY, DRY, BROWN (5YR, 3/1), BRITTLE, CLUMPY |
| 4 | 5' - E.O.B. | VERY LOOSE SAND, DRY, TAN/ BROWN (2.5Y, 5/3), NO PLASTICITY |
| | | E.O.T.P. = 6' |

**NOTES:** TEST PIT IN OLD WASHOUT FEATURE

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-5

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 5 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-5




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | C-5C | CA |
| 2' | C-5 | BKT |
| 5' | C-5 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 3" | VEGETATION, DRY, LOOSE SAND |
| 2 | 3" - 3' | VERY LOOSE SAND, DRY, TAN/ BROWN (2.5Y, 5/3), NO PLASTICITY |
| 3 | 3' - E.O.B. | SANDY CLAY, DRY, MOTTLED BROWN (5YR, 3/1), BRITTLE, LOOSE, CHUNKY, CALCITE |
| | 5' | VERY FIRM, MOTTLED CLAY |
| | | E.O.T.P. = 5' |

**NOTES:** REFUSAL AT 5'

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-6

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-6




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | C-6C | CA |
| 2' | C-6 | BKT |
| 5' | C-6 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 3" | VEGETATION, DRY, TAN (2.5Y, 5/3), SAND, NO PLASTICITY |
| 2 | 3" - 3' | VERY LOOSE SAND, DRY, TAN/ BROWN (2.5Y, 5/3), NO PLASTICITY |
| 3 | 3' - E.O.B. | SANDY CLAY, DRY, MOTTLED BROWN (5YR, 3/1), BRITTLE, CHUNKY, CALCITE |
| | | E.O.T.P. = 6' |

**NOTES:**

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-7

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-7




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | C-7C | CA |
| 2' | C-7 | BKT |
| 6' | C-7 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 3" | VEGETATION, SAND, DRY, (2.5Y, 5/3) |
| 2 | 3" - 3' | VERY LOOSE SAND, DRY, TAN/ BROWN (2.5Y, 5/3), NO PLASTICITY |
| 3 | 3' - E.O.B. | SANDY CLAY, DRY, MOTTLED BROWN (5YR, 3/1), BRITTLE, CHUNKY |
| | | E.O.T.P. = 6' |

**NOTES:** RECOVERY WITH CAL SAMPLER HAS BEEN POOR

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-8

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-8




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | C-8C | CA |
| 2' | C-8 | BKT |
| 5' | C-8 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 3" | VEGETATION, SAND, DRY, (2.5Y, 5/3), LOOSE |
| 2 | 3" - E.O.B. | SANDY CLAY, DRY, BROWN (5YR, 3/1), BRITTLE, CHUNKY |
| | 5' | SAND INCREASES |
| | | E.O.T.P. = 6' |

**NOTES:**

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-9

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-9




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | C-9C | CA |
| 2' | C-9 | BKT |
| 5' | C-9 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 3" | VEGETATION, SAND, DRY, TAN (2.5Y, 5/3) |
| 2 | 6" - 3' | VERY LOOSE SAND, DRY, TAN/ BROWN (2.5Y, 5/3), NO PLASTICITY |
| 3 | 3' - E.O.B. | SANDY CLAY, DRY, MOTTLED BROWN (5YR, 3/1), CHUNKY, BRITTLE |
| | | E.O.T.P. = 6' |

**NOTES:** GROUND FROZEN

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-10

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-10




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 4' | C-10C | CA |
| 3' | C-10 | BKT |
| 6' | C-10 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 3" | VEGETATION, SAND, DRY, TAN (2.5Y, 5/3), NO PLASTICITY |
| 2 | 6" - 4' | VERY LOOSE SAND, DRY, TAN (2.5Y, 5/3), NO PLASTICITY |
| 3 | 4' - E.O.B. | SANDY CLAY, DRY, MOTTLED BROWN (5YR, 3/1), CHUNKY, BRITTLE<br>MORE SAND |
| | | E.O.T.P. = 6' |

**NOTES:**

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-11

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-11




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 4' | C-11C | CA |
| 3' | C-11 | BKT |
| 5' | C-11 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 3" | VEGETATION, SAND, DRY, TAN (2.5Y, 5/3) |
| 2 | 6" - 4' | VERY LOOSE SAND, DRY, TAN (2.5Y, 5/3), NO PLASTICITY |
| 3 | 4' - E.O.B. | SANDY CLAY, DRY, MOTTLED BROWN (5YR, 3/1), CHUNKY, BRITTLE |
| | | E.O.T.P. = 6' |

**NOTES:**

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-12

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-12




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| N/R | N/R | CA |
| 3' | C-12 | BKT |
| 6' | C-12 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 3" | VEGETATION, SAND, DRY, TAN (2.5Y, 5/3), NO PLASTICITY |
| 2 | 3" - E.O.B. | VERY LOOSE SAND, DRY, TAN (2.5Y, 5/3), NO PLASTICITY |
| | | E.O.T.P. = 6' |

**NOTES:** NO CLAY

Engineering Analytics, Inc.

# TEST PIT LOG

PAGE: 1 of 2

DATE:

TEST PIT NO.: C-13

## PROJECT INFORMATION

PROJECT: MT. TAYLOR


PROJECT NO.: 111360

CLIENT: MT. TAYLOR

OWNER:

LOCATION: GRANTS, NEW MEXICO

## TEST PIT LOCATION




## FIELD INFORMATION

DATE & TIME ARRIVED:

TEST PIT LOGGED BY: JBB

VISITORS:

WEATHER: VERY COLD

## EXCAVATION INFORMATION

EXCAVATION COMPANY: RGR

START TIME:

TEST PIT DEPTH: 6 FT TEST PIT DIA.: 2 FT

EXCAVATION METHOD:

SAMPLING METHOD:

TIME EXCAVATION COMPLETE:

## TEST PIT COMPLETION / ABANDONMENT INFORMATION

START TIME: COMPLETE TIME:

INSTRUMENTATION: BACKFILL:

## GROUNDWATER CONDITIONS

## FOLLOWING FIELD WORK

TIME OF CLEAN-UP COMPLETE: TIME LEFT SITE:

## NOTES:


Engineering Analytics, Inc.

# TEST PIT LOG

**PROJECT:** MT. TAYLOR **PAGE:** 2 OF 2

**PROJECT NO.:** 111360 **DATE:**

**TEST PIT NO.:** C-13




| DEPTH | SAMPLE I.D. | SAMPLE TYPE |
|---|---|---|
| 3' | C-13C | CA |
| 3' | C-13 | BKT |
| 6' | C-13 | BKT |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

| SOIL TYPE | SOIL DEPTH | SOIL DESCRIPTION AND EXCAVATION NOTES |
|---|---|---|
| 1 | 0 - 3" | VEGETATION, SAND, DRY, TAN (2.5Y, 5/3) |
| 2 | 3" - E.O.B. | VERY SANDY CLAY, DRY, MOTTLED BROWN (2.5Y, 3/1), BRITTLE, CHUNKY |
| | | CLAY AND SAND ALMOST 1/2 & 1/2 |
| | | E.O.T.P. = 6' |

**NOTES:**

# APPENDIX B
# Results of Geotechnical Laboratory Testing for Mt. Taylor Disposal Cell

# Geotechnical Laboratory Test Report
# Mt. Taylor Mine

*Prepared for:*

Rio Grand Resources

750 W Pender Street, Suite 250,
Vancouver, BC, V6C 2T7,
Canada

*Prepared by:*

Engineering Analytics, Inc.

1600 Specht Point Road, Suite 209
Fort Collins, Colorado 80525
(970) 488-3111
Fax (970) 488-3112

Project No. 111360

November 2025



# Table of Contents

1.0 Summary

2.0 Summary of Test Results

3.0 Moisture Content

4.0 Percent Passing No. 200

5.0 Atterberg Limits

6.0 Flexible Wall Permeability

7.0 Soil Water Characteristic Curve

8.0 Standard Proctor Compaction

9.0 Consolidated Undrained Triaxial Shear

# 1.0 Summary

This report presents the results of laboratory testing conducted on soil samples provided by Engineering Analytics of Fort Collins, Colorado. The sample selection and testing parameters were designated by personnel from Engineering Analytics. All laboratory analyses were performed by Engineering Analytics under the direct supervision of a Professional Engineer licensed in the State of Colorado.

The testing procedures adhered to the standards outlined by the American Society of Testing and Materials (ASTM). Where ASTM standards were not applicable, established industry standards were employed. Any deviations from standard procedures are explicitly noted within this report the table below lists ASTM procedures used in this investigation. The results of the laboratory tests, including relevant graphical representations, are presented in the following sections.

| Test Performed | ASTM Test Method | No. of Tests Performed |
|---|---|---|
| Moisture Determination | D2216 | 48 |
| Percent Passing No. 200 | D1140 | 48 |
| Atterberg Limits | D4318 | 48 |
| Flexible Wall Permeability | D5084 | 2 |
| Soil Water Characteristic Curve | D6836 | 7 |
| Standard Proctor Compaction | D698 | 8 |
| Consolidated Undrained Triaxial Shear | D4767 | 1 |

## 2.0 Summary of Test Results

Engineering Analytics, Inc.

| | | | | | **Project Name:** Mt. Taylor Mine | | **Project No.** 111360 | | **Date:** 02/21/2025 | | **Date:** |
|---|---|---|---|---|---|---|---|---|---|---|---|
| **Hole ID** | **Sample ID** | **Sampling Depth (ft)** | | **Sample Type** | **Moisture Content (%)** | **Percent Passing #200 (ASTM D1140)** | **Atterberg Limits (ASTM D4318) (LL / PL / PI)** | **Flexible Wall Permeability (ASTM D5084)** | **Soil Water Characteristic Curve (SWCC)** | **Standard Proctor Compaction (ASTM D698)** | **Triaxial (CUPP), 3-stage (ASTM D4767)** |
| | | **From** | **To** | | | | | | | | |
| **TOTAL NUMBER OF COMPLETED TESTS** | | | | | **48** | **48** | **48** | **2** | **7** | **8** | **1** |
| **EA-BSA01** | EA-BSA01 A | 2.0 | 3.0 | BKT | 9.7% | 76.4% | 40 / 20 / 20 | | | | |
| | EA-BSA01 B | 5.0 | 6.0 | BKT | 12.4% | 78.8% | 38 / 19 / 19 | | | | |
| **EA-BSA02** | EA-BSA02 A | 2.0 | 3.0 | BKT | 9.5% | 66.5% | 26 / 20 / 6 | | | | |
| | EA-BSA02 B | 5.0 | 6.0 | BKT | 8.9% | 65.1% | 25 / 20 / 5 | | | | |
| **EA-BSA03** | EA-BSA03 A | 2.0 | 3.0 | BKT | 7.0% | 46.1% | NV / NP / NP | | | | |
| | EA-BSA03 B | 5.0 | 6.0 | BKT | 6.8% | 40.8% | NV / NP / NP | | | | |
| **EA-BSA04** | EA-BSA04 A | 2.0 | 3.0 | BKT | 13.2% | 56.5% | 28 / 18 / 10 | | | | |
| | EA-BSA04 B | 5.0 | 6.0 | BKT | 6.9% | 51.2% | 25 / 18 / 7 | | | | |
| **EA-BSA05** | EA-BSA05 A | 2.0 | 3.0 | BKT | 6.2% | 41.8% | 25 / 20 / 5 | | (1) | 111.1 @ 13.9% | |
| | EA-BSA05 B | 5.0 | 6.0 | BKT | 6.5% | 43.0% | 25 / 20 / 5 | | | | |
| **EA-BSA06** | EA-BSA06 A | 2.0 | 3.0 | BKT | 12.8% | 51.9% | 23 / 20 / 3 | | | | |
| | EA-BSA06 B | 5.0 | 6.0 | BKT | 8.6% | 28.9% | NV / NP / NP | | (1) | 117.6 @ 12.2% | |
| **EA-BSB01** | EA-BSB01 A | 2.0 | 3.0 | BKT | 18.9% | 81.1% | 39 / 16 / 23 | | | | |
| | EA-BSB01 B | 5.0 | 6.0 | BKT | 8.1% | 39.0% | NV / NP / NP | | | | |
| **EA-BSB02** | EA-BSB02 A | 2.0 | 3.0 | BKT | 16.8% | 68.0% | 35 / 16 / 19 | | | | |
| | EA-BSB02 B | 5.0 | 6.0 | BKT | 7.9% | 55.0% | 22 / 20 / 2 | | (1) | 110.3 @ 16.2% | |
| **EA-BSB03** | EA-BSB03 A | 2.0 | 3.0 | BKT | 14.6% | 71.1% | 26 / 19 / 7 | | | | |
| | EA-BSB03 B | 5.0 | 6.0 | BKT | 11.6% | 45.6% | NV / NP / NP | | | | |
| **EA-BSB04** | EA-BSB04 A | 2.0 | 3.0 | BKT | 6.1% | 30.0% | NV / NP / NP | | (1) | 112.5 @ 15.0% | |
| | EA-BSB04 B | 5.0 | 6.0 | BKT | 24.1% | 90.1% | 51 / 17 / 34 | | | | |
| **EA-BSB05** | EA-BSB05 A | 2.0 | 3.0 | BKT | 10.4% | 65.1% | 31 / 19 / 12 | | | | |
| | EA-BSB05 B | 5.0 | 6.0 | BKT | 4.6% | 30.9% | NV / NP / NP | | | | |
| **EA-BSC01** | EA-BSC01 A | 2.0 | 3.0 | BKT | 9.7% | 60.6% | 31 / 16 / 15 | | | | |
| | EA-BSC01 B | 5.0 | 6.0 | BKT | 11.9% | 78.8% | 42 / 17 / 25 | | | | |
| **EA-BSC02** | EA-BSC02 A | 2.0 | 3.0 | BKT | 12.7% | 87.6% | 50 / 17 / 33 | | | | |
| | EA-BSC02 B | 5.0 | 6.0 | BKT | 12.6% | 80.7% | 38 / 18 / 20 | | | | |
| **EA-BSC03** | EA-BSC03 A | 2.0 | 3.0 | BKT | 9.6% | 61.2% | 29 / 15 / 14 | | (1) | 108.2 @ 16.8% | |
| | EA-BSC03 B | 5.0 | 6.0 | BKT | 11.7% | 79.1% | 39 / 18 / 21 | | | | |
| **EA-BSC04** | EA-BSC04 A | 2.0 | 3.0 | BKT | 12.1% | 80.0% | 39 / 16 / 13 | | | | |
| | EA-BSC04 B | 5.0 | 6.0 | BKT | 10.7% | 68.9% | 34 / 16 / 8 | | | | |
| **EA-BSC05** | EA-BSC05 A | 2.0 | 3.0 | BKT | 8.6% | 57.0% | 23 / 18 / 5 | | | | |
| | EA-BSC05 B | 5.0 | 6.0 | BKT | 13.8% | 90.2% | 56 / 16 / 40 | | | | |
| **EA-BSC06** | EA-BSC06 A | 2.0 | 3.0 | BKT | 7.9% | 58.5% | 30 / 17 / 13 | | | | |
| | EA-BSC06 B | 5.0 | 6.0 | BKT | 17.2% | 95.3% | 65 / 23 / 42 | | | 89.8 @ 26.6% | (1) |
| **EA-BSC07** | EA-BSC07 A | 2.0 | 3.0 | BKT | 10.1% | 77.7% | 35 / 19 / 16 | | | | |
| | EA-BSC07 B | 5.0 | 6.0 | BKT | 10.4% | 71.9% | 35 / 17 / 18 | | | | |
| **EA-BSC08** | EA-BSC08 A | 2.0 | 3.0 | BKT | 11.2% | 77.2% | 44 / 17 / 27 | | | | |
| | EA-BSC08 B | 5.0 | 6.0 | BKT | 11.7% | 86.5% | 49 / 24 / 25 | | | | |
| **EA-BSC09** | EA-BSC09 A | 2.0 | 3.0 | BKT | 6.8% | 50.0% | 26 / 18 / 8 | 7.9E-06 | (1) | 110.4 @ 16.1% | |
| | EA-BSC09 B | 5.0 | 6.0 | BKT | 14.7% | 96.9% | 60 / 27 / 33 | | | | |
| **EA-BSC10** | EA-BSC10 A | 2.0 | 3.0 | BKT | 9.0% | 69.4% | 39 / 16 / 23 | | | | |
| | EA-BSC10 B | 5.0 | 6.0 | BKT | 12.0% | 69.6% | 33 / 18 / 15 | | | | |
| **EA-BSC11** | EA-BSC11 A | 2.0 | 3.0 | BKT | 10.0% | 63.5% | 30 / 19 / 11 | | | | |
| | EA-BSC11 B | 5.0 | 6.0 | BKT | 12.7% | 69.1% | 42 / 18 / 24 | | | | |
| **EA-BSC12** | EA-BSC12 A | 2.0 | 3.0 | BKT | 7.3% | 52.7% | NV / NP / NP | 1.2E-04 | (1) | 109.3 @ 16.4% | |
| | EA-BSC12 B | 5.0 | 6.0 | BKT | 8.2% | 49.0% | 23 / 20 / 3 | | | | |
| **EA-BSC13** | EA-BSC13 A | 2.0 | 3.0 | BKT | 9.5% | 75.8% | 38 / 17 / 21 | | | | |
| | EA-BSC13 B | 5.0 | 6.0 | BKT | 13.3% | 81.4% | 45 / 23 / 22 | | | | |

MCS = Modified California Sample, BKT = Bucket

## 3.0 Moisture Content

The natural moisture content of 48 soil samples was determined in accordance with ASTM D2216, "Standard Test Methods for Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass."

This test yields the gravimetric moisture content, expressed as a percentage, which represents the ratio of the mass of water to the mass of dry soil within the sample.

A summary of the natural moisture content results are presented in Section 2.0 of this report.

# 4.0 Percent Passing No. 200

A selection of 48 soil samples was tested in general accordance with ASTM D1140, "Standard Test Methods for Determining the Amount of Material Finer than 75-µm (No. 200) Sieve in Soils by Washing."

- A selection of soil samples was tested in general accordance with ASTM D1140, "Standard Test Methods for Determining the Amount of Material Finer than 75-µm (No. 200) Sieve in Soils by Washing."
- The testing procedure involved oven-drying the samples, recording their initial dry weight, and then washing them through a 75-µm (No. 200) sieve.
- The material retained on the sieve was recovered, oven-dried, and weighed.
- The percentage of material passing the No. 200 sieve was calculated using the initial total dry weight of the sample and the dry weight of the material retained on the sieve.

A summary of the percent finer than No. 200 sieve results is presented in Section 2.0 of this report.

# 5.0 Atterberg Limits

The Atterberg Limits, specifically the liquid limit (LL) and plastic limit (PL), were determined on 48 soil samples in accordance with ASTM D4318, "Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils."


- Sample Preparation:
    - The soil sample is processed to pass the 0.425 mm (No. 40) sieve.
    - A representative portion of this fine-grained material is used for the tests.
- Liquid Limit (LL):
    - A soil paste is prepared with distilled water.
    - The paste is placed in a Casagrande cup, and a groove is made in the soil.
    - The cup is repeatedly dropped from a specified height.
    - The liquid limit is determined as the moisture content at which the groove closes over a distance of 12.7 mm (0.5 inches) after 25 blows.
- Plastic Limit (PL):
    - A soil thread is rolled out on a flat surface.
    - The plastic limit is determined as the moisture content at which the soil thread crumbles when rolled to a diameter of 3.2 mm (1/8 inch).
- Plasticity Index (PI):
    - The plasticity index is calculated by subtracting the plastic limit from the liquid limit (PI = LL - PL).

A summary of the Atterberg Limits test results is presented in Section 2.0 of this report.

A graph depicting the Plasticity Index versus the Liquid Limit is included on the following pages.

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSA01 Depth: 2' - 3'<br>Sample Number: A | | | 02/21/2025 | CF |
| ■ | Source of Sample: EA-BSA01 Depth: 5' - 6'<br>Sample Number: B | | | 02/20/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 40 | 20 | 20 | | |
| ■ | Clay | | 38 | 19 | 19 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSA02 Depth: 2' - 3'<br>Sample Number: A | | | 02/18/2025 | CF |
| ■ | Source of Sample: EA-BSA02 Depth: 5' - 6'<br>Sample Number: B | | | 02/20/2025 | SY |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 26 | 20 | 6 | | |
| ■ | Sandy Clay | | 25 | 20 | 5 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSA03 Depth: 2' - 3'<br>Sample Number: A | | | 02/20/2025 | SY |
| ■ | Source of Sample: EA-BSA03 Depth: 5' - 6'<br>Sample Number: B | | | 02/20/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Sand | | NV | NP | NP | | |
| ■ | Sandy Clay | | NV | NP | NP | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSA04 Depth: 2' - 3'<br>Sample Number: A | | | 02/21/2025 | CF |
| ■ | Source of Sample: EA-BSA04 Depth: 5' - 6'<br>Sample Number: B | | | 02/19/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 28 | 18 | 10 | | |
| ■ | Silty Clay | | 25 | 18 | 7 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSA05 Depth: 2' - 3'<br>Sample Number: A | | | 02/20/2025 | SY |
| ■ | Source of Sample: EA-BSA05 Depth: 5' - 6'<br>Sample Number: B | | | 02/20/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Sand | | 25 | 20 | 5 | | |
| ■ | Clayey Sand | | 25 | 20 | 5 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSA06 Depth: 2' - 3'<br>Sample Number: A | | | 02/20/2025 | CF |
| ■ | Source of Sample: EA-BSA06 Depth: 5' - 6'<br>Sample Number: B | | | 2/21/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 23 | 20 | 3 | | |
| ■ | Sand | | NV | NP | NP | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSB01 Depth: 2' - 3'<br>Sample Number: A | | | 02/21/2025 | CF |
| ■ | Source of Sample: EA-BSB01 Depth: 5' - 6'<br>Sample Number: B | | | 02/20/2025 | SY |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 39 | 16 | 23 | | |
| ■ | Sand | | NV | NP | NP | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSB02 Depth: 2' - 3'<br>Sample Number: A | | | 02/24/2025 | CF |
| ■ | Source of Sample: EA-BSB02 Depth: 5' - 6'<br>Sample Number: B | | | 02/20/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 35 | 16 | 19 | | |
| ■ | Silty Clay | | 22 | 20 | 2 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSB03 Depth: 2' - 3'<br>Sample Number: A | | | 02/20/2025 | CF |
| ■ | Source of Sample: EA-BSB03 Depth: 5' - 6'<br>Sample Number: B | | | 02/20/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 26 | 19 | 7 | | |
| ■ | Sand | | NV | NP | NP | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSB04 Depth: 2' - 3'<br>Sample Number: A | | | 02/20/2025 | SY |
| ■ | Source of Sample: EA-BSB04 Depth: 5' - 6'<br>Sample Number: B | | | 02/21/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Sand | | NV | NP | NP | | |
| ■ | Silty Clay | | 51 | 17 | 34 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSB05 Depth: 2' - 3'<br>Sample Number: A | | | 02/19/2025 | CF |
| ■ | Source of Sample: EA-BSB05 Depth: 5' - 6'<br>Sample Number: B | | | 02/20/2025 | SY |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 31 | 19 | 12 | | |
| ■ | Sand | | NV | NP | NP | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC01 Depth: 2' - 3' Sample Number: A | | | 02/06/2025 | CF |
| ■ | Source of Sample: EA-BSC01 Depth: 5' - 6' Sample Number: B | | | 02/06/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 31 | 16 | 15 | | |
| ■ | Silty Clay | | 42 | 17 | 25 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC02 Depth: 2' - 3'<br>Sample Number: A | | | 02/07/2025 | EH |
| ■ | Source of Sample: EA-BSC02 Depth: 5' - 6'<br>Sample Number: B | | | | 02/06/2025 |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Clay | | 50 | 17 | 33 | | |
| ■ | Silty Clay | | 38 | 18 | 20 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC03 Depth: 2' - 3' Sample Number: A | | | 02/06/2025 | CF |
| ■ | Source of Sample: EA-BSC03 Depth: 5' - 6' Sample Number: B | | | 02/05/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 29 | 15 | 14 | | |
| ■ | Silty Clay | | 39 | 18 | 21 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC04 Depth: 2' - 3' Sample Number: A | | | 02/19/2025 | CF |
| ■ | Source of Sample: EA-BSC04 Depth: 5' - 6' Sample Number: B | | | 02/13/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Clay | | 39 | 16 | 23 | | |
| ■ | Silty Clay | | 34 | 16 | 18 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC05 Depth: 2' - 3' Sample Number: A | | | 02/11/2025 | CF |
| ■ | Source of Sample: EA-BSC05 Depth: 5' - 6' Sample Number: B | | | 2/07/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Sandy Clay | | 23 | 18 | 5 | | |
| ■ | Silty Clay | | 56 | 16 | 40 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC06 Depth: 2' - 3'<br>Sample Number: A | | | 02/20/2025 | CF |
| ■ | Source of Sample: EA-BSC06 Depth: 5' - 6'<br>Sample Number: B | | | 02/15/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 30 | 17 | 13 | | |
| ■ | Clay | | 65 | 23 | 42 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC07 Depth: 2' - 3' Sample Number: A | | | 02/11/2025 | SY |
| ■ | Source of Sample: EA-BSC07 Depth: 5' - 6' Sample Number: B | | | 02/12/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | SAndy Clay | | 35 | 19 | 16 | | |
| ■ | Silty Clay | | 35 | 17 | 18 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC08 Depth: 2' - 3' Sample Number: A | | | 2/13/2025 | CF |
| ■ | Source of Sample: EA-BSC08 Depth: 5' - 6' Sample Number: B | | | 02/18/2025 | SY |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 44 | 17 | 27 | | |
| ■ | Sandy Clay | | 49 | 24 | 25 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC09 Depth: 2' - 3'<br>Sample Number: A | | | 02/18/2025 | CF |
| ■ | Source of Sample: EA-BSC09 Depth: 5' - 6'<br>Sample Number: B | | | 02/19/2025 | AW |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 26 | 18 | 8 | | |
| ■ | Clay | | 60 | 27 | 33 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC10 Depth: 2' - 3' Sample Number: A | | | 02/10/2025 | CF |
| ■ | Source of Sample: EA-BSC10 Depth: 5' - 6' Sample Number: B | | | 02/18/2025 | SY |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 39 | 16 | 23 | | |
| ■ | Sandy Clay | | 33 | 18 | 15 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC11 Depth: 2' - 3'<br>Sample Number: A | | | 02/10/2025 | CF |
| ■ | Source of Sample: EA-BSC11 Depth: 5' - 6'<br>Sample Number: B | | | 02/12/2025 | CF |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 30 | 19 | 11 | | |
| ■ | Silty Clay | | 42 | 18 | 24 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC12 Depth: 2' - 3' Sample Number: A | | | 02/11/2025 | CF |
| ■ | Source of Sample: EA-BSC12 Depth: 5' - 6' Sample Number: B | | | | 02/07/2025 |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Sandy Clay | | NV | NP | NP | | |
| ■ | Sandy Clay | | 23 | 20 | 3 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG


Title:

ENGINEERING ANALYTICS, INC.

Figure

# LIQUID AND PLASTIC LIMITS TEST REPORT

ASTM D4318




| | Sample Identification | Sampled | Received | Tested | Technician |
|---|---|---|---|---|---|
| ● | Source of Sample: EA-BSC13 Depth: 2' - 3'<br>Sample Number: A | | | 02/14/2025 | CF |
| ■ | Source of Sample: EA-BSC13 Depth: 5' - 6'<br>Sample Number: B | | | 02/11/2025 | SY |
| | | | | | |
| | | | | | |
| | | | | | |

| | Material Description | USCS | LL | PL | PI | NM | %<#40 |
|---|---|---|---|---|---|---|---|
| ● | Silty Clay | | 38 | 17 | 21 | | |
| ■ | Clay | | 45 | 23 | 22 | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

| | PL Rolling Method | LL Device | Grooving Tool | Test Remarks |
|---|---|---|---|---|
| ● | Hand rolled | Manual | Metal | |
| ■ | Hand rolled | Manual | Metal | |
| | | | | |
| | | | | |
| | | | | |

Project No. 111360 Client: Rio Grand Resources

Project: Mt.Taylor

Checked by: KG

Title:

ENGINEERING ANALYTICS, INC.

Figure

# 6.0 Flexible Wall Permeability

The hydraulic conductivity (coefficient of permeability) of saturated porous material was determined on 2 soil samples using a flexible wall permeameter in accordance with ASTM D5084, "Standard Test Methods for Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall[1] Permeameter (Method C: Falling Head Test)."

- Soil samples were trimmed, encased within a flexible rubber membrane, and placed within a triaxial test cell.
- An initial effective stress of 1-3 psi was applied to each sample to facilitate saturation.
- Following saturation, each sample was consolidated to the effective stress specified by the project engineer.
- After a 24-hour consolidation period, a hydraulic gradient was established by applying differential pressures to the top and bottom of the samples. The magnitude of the gradient was determined based on the soil classification.
- The outflow of water from the top of the sample was measured at predetermined time intervals to determine the flow rate and, subsequently, the hydraulic conductivity.

The results of the hydraulic conductivity are presented on the following pages

**Flexible Wall Permeability Test**

**Mt. Taylor - 111360**

**EA-BSC 9 @ 2'-3' Remolded**


| | | | | |
|---|---|---|---|---|
| Length of sample | L | 7.52 | cm | 2.960 in |
| Area of sample | A | 29.50 | cm^2 | 2.413 in |
| Area of standpipe | a | 0.713 | cm^2 | 0.375 in |

| | | | | |
|---|---|---|---|---|
| Cell Pressure | 85.00 | psi | | |
| Upper Cap Pressure | 79.79 | psi | | |
| Lower Cap Pressure | 80.00 | psi | | |
| Dry Density | 93.9 | | % Remold @ | 85.1 % |
| % of Moisture | 16.1 % | | Water content ± | 0 % |
| Gradiant | 1.96 | | Remold Dry Density | 93.9 |
| Consolidation (psi) | 5.00 psi | | Remold % of Moisture | 16.1 % |
| Consolidation (psf) | 720 psf | | | |

| Date & Time | E.T . (s) | Reading Lower (cc) | Reading Upper (cc) | k(cm/s) |
|---|---|---|---|---|
| 10/28/25 10:45 AM | | 11.000 | 49.300 | |
| 10/28/25 10:48 AM | 180 | 12.000 | 48.000 | 2.2E-05 |
| | | | | |
| 10/28/25 10:48 AM | | 12.000 | 48.000 | |
| 10/28/25 11:05 AM | 1050 | 13.800 | 46.100 | 6.5E-06 |
| | | | | |
| 10/28/25 11:05 AM | | 13.800 | 46.100 | |
| 10/28/25 11:07 AM | 120 | 14.000 | 45.900 | 6.5E-06 |
| | | | | |
| 10/28/25 11:07 AM | | 14.000 | 45.900 | |
| 10/28/25 11:21 AM | 810 | 15.300 | 44.500 | 6.7E-06 |
| | | | | |
| 10/28/25 11:21 AM | | 15.300 | 44.500 | |
| 10/28/25 11:32 AM | 660 | 16.400 | 43.500 | 6.7E-06 |
| | | | | |
| 10/28/25 11:32 AM | | 16.400 | 43.500 | |
| 10/28/25 11:55 AM | 1380 | 18.500 | 41.400 | 7.0E-06 |
| | | | | |
| 10/28/25 11:55 AM | | 18.500 | 41.400 | |
| 10/28/25 1:22 PM | 5220 | 25.000 | 34.800 | 7.4E-06 |
| | | | | |
| 10/28/25 1:22 PM | | 25.000 | 34.800 | |
| 10/28/25 2:20 PM | 3480 | 28.500 | 31.600 | 8.3E-06 |
| | | | | |
| 10/29/25 9:59 AM | | 19.600 | 49.600 | |
| 10/29/25 10:01 AM | 120 | 19.800 | 49.300 | 8.5E-06 |
| | | | | |
| 10/29/25 10:01 AM | | 19.800 | 49.300 | |
| 10/29/25 10:09 AM | 510 | 20.700 | 48.400 | 7.4E-06 |
| | | | | |
| 10/29/25 10:09 AM | | 20.700 | 48.400 | |
| 10/29/25 10:25 AM | 930 | 22.200 | 46.800 | 7.4E-06 |
| | | | | |
| | | | | |
| | | Average k= | 7.9E-06 | |

# Flexwall Permeability Test

**Mt. Taylor - 111360**
**EA-BSC09 @ 2' - 3'**
**Remolded to 93.9 @ 16.1%**
**(85.1% of Max Dry Density, @ Optimum Moisture)**




Average Permeability k = 7.9E-06cm/s

**Flexible Wall Permeability Test**

**Mt. Taylor - 111360**

**EA-BSC 12A @ 2'-3'**


| | | | | |
|---|---|---|---|---|
| Length of sample | L | 6.24 | cm | 2.456 in |
| Area of sample | A | 29.50 | cm^2 | 2.413 in |
| Area of standpipe | a | 0.713 | cm^2 | 0.375 in |

| | | | | | |
|---|---|---|---|---|---|
| Cell Pressure | 90.00 | psi | | | |
| Upper Cap Pressure | 84.82 | psi | | | |
| Lower Cap Pressure | 85.00 | psi | | | |
| Dry Density | 95.4 | | % Remold @ | 87.3 | % |
| % of Moisture | 16.4 | % | Water content ± | 0 | % |
| Gradiant | 2.03 | | Remold Dry Density | 95.4 | |
| Consolidation (psi) | 5.00 | psi | Remold % of Moisture | 16.4 | % |
| Consolidation (psf) | 720 | psf | | | |

| Date & Time | E.T . (s) | Reading Lower (cc) | Reading Upper (cc) | k(cm/s) |
|---|---|---|---|---|
| 10/28/25 10:58 AM | | 25.500 | 36.400 | |
| 10/28/25 10:59 AM | 60 | 26.500 | 35.400 | 1.1E-04 |
| | | | | |
| 10/28/25 10:59 AM | | 26.500 | 35.400 | |
| 10/28/25 11:00 AM | 60 | 27.700 | 34.300 | 1.4E-04 |
| | | | | |
| 10/28/25 11:00 AM | | 27.700 | 34.300 | |
| 10/28/25 11:01 AM | 60 | 28.800 | 33.400 | 1.4E-04 |
| | | | | |
| 10/28/25 11:01 AM | | 28.800 | 33.400 | |
| 10/28/25 11:02 AM | 60 | 29.700 | 32.300 | 1.5E-04 |
| | | | | |
| 10/28/25 11:02 AM | | 29.700 | 32.300 | |
| 10/28/25 11:03 AM | 60 | 30.500 | 31.600 | 1.3E-04 |
| | | | | |
| 10/28/25 11:03 AM | | 30.500 | 31.600 | |
| 10/28/25 11:04 AM | 60 | 31.100 | 30.800 | 1.3E-04 |
| | | | | |
| 10/28/25 11:04 AM | | 31.100 | 30.800 | |
| 10/28/25 11:05 AM | 60 | 31.800 | 30.200 | 1.4E-04 |
| | | | | |
| 10/28/25 11:05 AM | | 31.800 | 30.200 | |
| 10/28/25 11:06 AM | 60 | 32.300 | 29.600 | 1.3E-04 |
| | | | | |
| 10/28/25 11:06 AM | | 32.300 | 29.600 | |
| 10/28/25 11:07 AM | 60 | 32.800 | 29.200 | 1.2E-04 |
| | | | | |
| 10/28/25 11:07 AM | | 32.800 | 29.200 | |
| 10/28/25 11:08 AM | 60 | 33.200 | 28.800 | 1.2E-04 |
| | | | | |
| 10/28/25 11:08 AM | | 33.200 | 28.800 | |
| 10/28/25 11:09 AM | 60 | 33.600 | 28.400 | 1.3E-04 |
| | | | | |
| | | | | |
| | | Average k= | 1.2E-04 | |

# Flexwall Permeability Test

**Mt. Taylor - 111360**
**EA-BSC 12A @ 2'-3'**
**Remolded to 95.4 @ 16.4%**
**(87.3% of Max Dry Density, @ Optimum Moisture)**




Average Permeability k = 1.2E-04cm/s

# 7.0 Soil Water Characteristic Curve

The moisture-retention curve (also known as the soil-water characteristic curve) was determined on 7 soil samples in accordance with ASTM D6836, "Standard Test Methods for Determination of the Soil Water Characteristic Curve for Soil and Rock by the Pressure Plate Method." This test establishes the relationship between the water content of a soil and the applied suction or negative matric potential (soil water potential).

To create a full-range curve, a combination of two methods was employed:


- Low Suction Range (Method C - Pressure Plate): Used to determine the water content at low suctions (0 kPa to 500 kPa).
- High Suction Range (Method D - Chilled Mirror Hygrometer): Used to determine the water content at high suctions (500 kPa to 250,000 kPa or more).


Combined Test Procedure


1. Sample Preparation (Method C): Representative soil specimens were prepared and placed on ceramic plates of appropriate air-entry values within a pressure chamber.
2. Saturation: The specimens were saturated by submerging them in water, allowing them to reach equilibrium.
3. Low Suction Application (Method C): The pressure chamber was subjected to a series of low, incremental air pressures (suctions), typically up to 1500 kPa. At each pressure step, the system was allowed to reach hydraulic equilibrium (i.e., water stopped flowing out of the samples). The water outflow was measured and recorded.
4. High Suction Application (Method D): After the final low-suction step, or on a separate subset of samples, the soil was tested using the Chilled Mirror Hygrometer technique.
    - A small, representative portion of the soil was placed in the hygrometer's sample chamber.
    - The instrument measured the relative humidity in equilibrium with the soil water potential (suction) above the sample.
    - This measurement was taken by chilling a mirror surface until dew condensation occurred. The measured dew point temperature was used to calculate the corresponding high soil suction.
5. Moisture Content Determination: For both methods, the water content corresponding to each suction step was determined, by determining the gravimetric moisture content of the tested specimen.


By combining the data from the Pressure Plate (low suction) and the Chilled Mirror Hygrometer (high suction), a complete moisture-retention curve was generated, spanning the full range of suction required for engineering analysis.


The results of the Soil Water Characteristic Curves are presented on the following pages.



Soil Water Characteristic Curve
Mt. Taylor - 111360
EA-BSA-05A @ 2'-3'
Suction (kPa)
1000000
100000
10000
1000
100
10
1
147,890
98,140
128,130
33,630
66,230
11,430
500
250
100
50
25
5
0.000
0.050
0.100
0.150
0.200
0.250
0.300
0.350
0.400
0.450
Volumetric Water Content Θ
Pressure Plate
Chilled Mirror Hygrometer



Soil Water Characteristic Curve
Mt. Taylor - 111360
EA-BSA-06B @ 5'-6'
Suction (kPa)
1000000
100000
10000
1000
100
10
1
150,360
112,600
85,070
49,350
20,180
7,040
500
250
100
50
25
5
0.000
0.050
0.100
0.150
0.200
0.250
0.300
0.350
Volumetric Water Content Θ
Pressure Plate
Chilled Mirror Hygrometer


Soil Water Characteristic Curve
Mt. Taylor - 111360
EA-BSB-02B @ 5' - 6'
Suction (kPa)
1000000
100000
10000
1000
100
10
1
148,520
105,770
128,900
10,760
6,070
500
250
100
50
25
5
0.000
0.050
0.100
0.150
0.200
0.250
0.300
0.350
0.400
0.450
Volumetric Water Content Θ
Pressure Plate
Chilled Mirror Hygrometer


Soil Water Characteristic Curve
Mt. Taylor - 111360
EA-BSB-04 @ 2' - 3'
Suction (kPa)
1000000
100000
10000
1000
100
10
1
142,540
106,980
72,490
29,070
14,540
500
250
100
25
5
0.000
0.050
0.100
0.150
0.200
0.250
0.300
0.350
Volumetric Water Content Θ
Pressure Plate
Chilled Mirror Hygrometer


Soil Water Characteristic Curve
Mt. Taylor - 111360
EA-BSC-03A @ 2' - 3'
Suction (kPa)
1000000
100000
10000
1000
100
10
1
145,240
89,710
105,140
67,960
32,940
500
250
100
50
25
5
0.000
0.050
0.100
0.150
0.200
0.250
0.300
0.350
0.400
0.450
Volumetric Water Content Θ
Pressure Plate
Chilled Mirror Hygrometer


Soil Water Characteristic Curve
Mt. Taylor - 111360
EA-BSC-09 @ 2' - 3'
Suction (kPa)
1000000
100000
10000
1000
100
10
1
0.000
0.050
0.100
0.150
0.200
0.250
0.300
0.350
0.400
Volumetric Water Content Θ
135,450
117,060
112,730
56,900
40,120
500
250
100
50
25
5
Pressure Plate
Chilled Mirror Hygrometer


Soil Water Characteristic Curve
Mt. Taylor - 111360
EA-BSC-12 @ 2'-3'
Suction (kPa)
1000000
100000
10000
1000
100
10
1
148,580
101,460
128,750
71,570
22,770
500
250
100
50
25
5
0.000
0.050
0.100
0.150
0.200
0.250
0.300
0.350
0.400
Volumetric Water Content Θ
Pressure Plate
Chilled Mirror Hygrometer


# 8.0 Standard Proctor Compaction

Standard Proctor Compaction tests were performed on 8 selected soil samples in accordance with ASTM D698, “Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort.”

- For each test, soil at a predetermined moisture content was placed in three equal layers into a cylindrical mold of specified dimensions. Each layer was compacted by 25 blows from a 5.5-pound (2.49 kg) hammer dropped from a height of 12 inches (305 mm) for Methods A and B of the standard. For Method C, a larger mold and 56 blows per layer were used. The specific method employed is noted in the results section.
- Following compaction, the wet unit weight of the soil in the mold was determined by measuring the mass of the compacted soil and the known volume of the mold.
- The moisture content of a representative portion of the compacted soil was determined, and the dry unit weight was subsequently calculated.
- This procedure was repeated for each soil sample with four or more different moisture contents to establish the moisture-density relationship (compaction curve) for the soil.

Graphs illustrating the moisture-density relationships (Proctor curves) for each tested soil sample are shown on the following pages.

# COMPACTION TEST REPORT




Curve No.
**2**

Test Specification:
ASTM D 698-12 Method A Standard

Preparation Method: Moist
Hammer Wt.: 5.5 lb.
Hammer Drop: 12 in.
Hammer Type: Manual
Layers: three Blows/Layer: 25
Mold Size: 0.03333 cu. ft.

Test Performed on Material
Passing: #4 Sieve

NM: LL: 25 PI: 5
Sp.G. (Assumed): 2.650
%>#4: %<No.200:
USCS: AASHTO:
Date Sampled:
Date Received:
Date Tested: 3/07/2025
Tested By: SY

| TESTING DATA | 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|---|
| WM + WS | 6161.5 | 6159.9 | 6026.9 | | | |
| WM | 4251.2 | 4251.2 | 4251.2 | | | |
| WW + T #1 | 1309.6 | 1466.2 | 1581.9 | | | |
| WD + T #1 | 1189.6 | 1338.5 | 1462.3 | | | |
| TARE #1 | 410.5 | 402.9 | 401.8 | | | |
| WW + T #2 | | | | | | |
| WD + T #2 | | | | | | |
| TARE #2 | | | | | | |
| MOISTURE | 15.4 | 13.6 | 11.3 | | | |
| DRY DENSITY | 109.5 | 111.1 | 105.6 | | | |

TEST RESULTS

Maximum dry density = 111.1 pcf

Optimum moisture = 13.9 %

Material Description: Sand

Remarks:

Project No.: 111360 Client: Rio Grand Resources
Project: Mt.Taylor


○ Source of Sample: EA-BSA05 Depth: 2' - 3' Sample Number: A

Checked by: KG
Title:

ENGINEERING ANALYTICS, INC.

Figure

# COMPACTION TEST REPORT




Curve No.
**3**

Test Specification:
ASTM D 698-12 Method A Standard

| | |
|---|---|
| Preparation Method | Moist |
| Hammer Wt. | 5.5 lb. |
| Hammer Drop | 12 in. |
| Hammer Type: | Manual |
| Layers | three |
| Blows/Layer | 25 |
| Mold Size | 0.03333 cu. ft. |

Test Performed on Material
Passing #4 Sieve

NM _____ LL NV PI NP
Sp.G. (Assumed): 2.650
%>#4 _____ %<No.200 _____
USCS _____ AASHTO _____
Date Sampled _____
Date Received _____
Date Tested 3/11/2025
Tested By SY

| TESTING DATA | 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|---|
| WM + WS | 6241.2 | 6247.1 | 6194.7 | 6147.9 | 6147.9 | |
| WM | 4251.6 | 4251.6 | 4251.6 | 4251.6 | 4251.6 | |
| WW + T #1 | 1459.3 | 1369.9 | 1341.9 | 1156.3 | 1297.7 | |
| WD + T #1 | 1346.8 | 1250.9 | 1211.9 | 1040.2 | 1218.6 | |
| TARE #1 | 402.9 | 401.2 | 401.7 | 401.5 | 401.8 | |
| WW + T #2 | | | | | | |
| WD + T #2 | | | | | | |
| TARE #2 | | | | | | |
| MOISTURE | 11.9 | 14.0 | 16.0 | 18.2 | 9.7 | |
| DRY DENSITY | 117.6 | 115.8 | 110.8 | 106.1 | 114.4 | |

TEST RESULTS

Maximum dry density = 117.6 pcf

Optimum moisture = 12.2 %

Material Description

Sand

Remarks:

Project No.: 111360 Client: Rio Grand Resources
Project: Mt.Taylor


○ Source of Sample: EA-BSA06 Depth: 5' - 6' Sample Number: B

Checked by: KG
Title:

Figure

ENGINEERING ANALYTICS, INC.

# COMPACTION TEST REPORT




Curve No.
**1**

Test Specification:
ASTM D 698-12 Method A Standard

Preparation Method: Moist
Hammer Wt.: 5.5 lb.
Hammer Drop: 12 in.
Hammer Type: Manual
Layers: three Blows/Layer: 25
Mold Size: 0.03333 cu. ft.

Test Performed on Material
Passing: #4 Sieve

NM: LL: 22 PI: 2
Sp.G. (Assumed): 2.650
%>#4: %<No.200:
USCS: AASHTO:
Date Sampled:
Date Received:
Date Tested: 3/11/2025
Tested By: SY

| TESTING DATA | 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|---|
| WM + WS | 6018.4 | 6109.9 | 6191.2 | 6144.2 | | |
| WM | 4251.6 | 4251.6 | 4251.6 | 4251.6 | | |
| WW + T #1 | 1413.6 | 1345.8 | 1353.8 | 1326.2 | | |
| WD + T #1 | 1304.8 | 1228.5 | 1223.3 | 1182.4 | | |
| TARE #1 | 402.9 | 401.8 | 429.1 | 402.1 | | |
| WW + T #2 | | | | | | |
| WD + T #2 | | | | | | |
| TARE #2 | | | | | | |
| MOISTURE | 12.1 | 14.2 | 16.4 | 18.4 | | |
| DRY DENSITY | 104.3 | 107.6 | 110.2 | 105.7 | | |

**TEST RESULTS**

Maximum dry density = 110.3 pcf

Optimum moisture = 16.2 %

**Material Description**

Silty Clay

Remarks:

Project No.: 111360 Client: Rio Grand Resources
Project: Mt.Taylor

○ Source of Sample: EA-BSB02 Depth: 5' - 6' Sample Number: B


Checked by: KG
Title:

ENGINEERING ANALYTICS, INC.

Figure

# COMPACTION TEST REPORT

Curve No.




Test Specification:
ASTM D 698-12 Method A Standard

Preparation Method: Moist
Hammer Wt.: 5.5 lb.
Hammer Drop: 12 in.
Hammer Type: Manual
Layers: three Blows/Layer: 25
Mold Size: 0.03333 cu. ft.
Test Performed on Material Passing #4 Sieve
NM _____ LL NV PI NP
Sp.G. (Assumed): 2.65
%>#4 _____ %<No.200 _____
USCS _____ AASHTO _____
Date Sampled _____
Date Received _____
Date Tested: 4/16/25
Tested By: SY

| TESTING DATA | 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|---|
| WM + WS | 6114.4 | 6211.7 | 6171.7 | | | |
| WM | 4251.4 | 4251.4 | 4251.4 | | | |
| WW + T #1 | 1015.2 | 1106.6 | 897.9 | | | |
| WD + T #1 | 933.6 | 1009.1 | 810.6 | | | |
| TARE #1 | 301.0 | 374.0 | 299.9 | | | |
| WW + T #2 | | | | | | |
| WD + T #2 | | | | | | |
| TARE #2 | | | | | | |
| MOISTURE | 12.9 | 15.4 | 17.1 | | | |
| DRY DENSITY | 109.1 | 112.4 | 108.5 | | | |

TEST RESULTS

Maximum dry density = 112.5 pcf

Optimum moisture = 15.0 %

Material Description: Sand

Remarks:

Project No.: 111360 Client: Rio Grand Resources
Project: Mt.Taylor

○ Source of Sample: EA-BSB04 Depth: 2' - 3' Sample Number: A


Checked by: AW
Title:

ENGINEERING ANALYTICS, INC.

Figure

# COMPACTION TEST REPORT

Curve No.




Test Specification:
ASTM D 698-12 Method A Standard

Preparation Method
Hammer Wt. 5.5 lb.
Hammer Drop 12 in.
Hammer Type:
Layers three Blows/Layer 25
Mold Size 0.03333 cu. ft.

Test Performed on Material
Passing #4 Sieve

NM LL 29 PI 14
Sp.G. (D854): 2.65
%>#4 %<No.200
USCS AASHTO
Date Sampled
Date Received
Date Tested
Tested By

| TESTING DATA | 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|---|
| WM + WS | 5943.1 | 6055.2 | 6159.8 | 6142.6 | | |
| WM | 4250.8 | 4250.8 | 4250.8 | 4250.8 | | |
| WW + T #1 | 1096.2 | 1043.8 | 1092.9 | 1088.9 | | |
| WD + T #1 | 1022.0 | 963.8 | 996.6 | 973.7 | | |
| TARE #1 | 410.5 | 405.5 | 420.8 | 369.7 | | |
| WW + T #2 | | | | | | |
| WD + T #2 | | | | | | |
| TARE #2 | | | | | | |
| MOISTURE | 12.1 | 14.3 | 16.7 | 19.1 | | |
| DRY DENSITY | 99.8 | 104.4 | 108.2 | 105.1 | | |

TEST RESULTS

Maximum dry density = 108.2 pcf

Optimum moisture = 16.8 %

Material Description

Silty Clay

Remarks:

Project No.: 111360 Client: Rio Grand Resources
Project: Mt.Taylor

○ Source of Sample: EA-BSC03 Depth: 2' - 3' Sample Number: A


Checked by:
Title:

ENGINEERING ANALYTICS, INC.

Figure

# COMPACTION TEST REPORT

Curve No.




Test Specification:
ASTM D 698-12 Method A Standard

Preparation Method: Moist
Hammer Wt.: 5.5 lb.
Hammer Drop: 12 in.
Hammer Type: Manual
Layers: three Blows/Layer: 25
Mold Size: 0.03333 cu. ft.

Test Performed on Material
Passing: #4 Sieve

NM: LL: PI:
Sp.G. (Assumed): 2.700
%>#4: %<No.200:
USCS: AASHTO:
Date Sampled:
Date Received:
Date Tested: 10/09/2025
Tested By: LR

| TESTING DATA | 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|---|
| WM + WS | 5840.6 | 5968.3 | 5951.5 | 5933.7 | | |
| WM | 4250.5 | 4250.5 | 4250.5 | 4250.5 | | |
| WW + T #1 | 706.1 | 886.9 | 883.8 | 827.1 | | |
| WD + T #1 | 647.1 | 785.5 | 779.2 | 727.3 | | |
| TARE #1 | 401.7 | 403.1 | 415.1 | 403.3 | | |
| WW + T #2 | | | | | | |
| WD + T #2 | | | | | | |
| TARE #2 | | | | | | |
| MOISTURE | 24.0 | 26.5 | 28.7 | 30.8 | | |
| DRY DENSITY | 84.8 | 89.8 | 87.4 | 85.1 | | |

TEST RESULTS

Maximum dry density = 89.8 pcf

Optimum moisture = 26.6 %

Material Description: Clay

Remarks:

Project No.: 111360 Client: Rio Grand Resources
Project: Mt.Taylor

○ Source of Sample: EA-BSC06/09 Combined


Checked by: KG
Title:

ENGINEERING ANALYTICS, INC.

Figure

# COMPACTION TEST REPORT

Curve No.




Test Specification:
ASTM D 698-12 Method A Standard

Preparation Method: Moist
Hammer Wt.: 5.5 lb.
Hammer Drop: 12 in.
Hammer Type: Manual
Layers: three Blows/Layer: 25
Mold Size: 0.03333 cu. ft.

Test Performed on Material
Passing: #4 Sieve

NM: LL: 26 PI: 8
Sp.G. (Assumed): 2.65
%>#4: %<No.200:
USCS: AASHTO:
Date Sampled:
Date Received:
Date Tested: 4/16/2025
Tested By: SY

| TESTING DATA | 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|---|
| WM + WS | 6020.3 | 6179.7 | 6154.5 | | | |
| WM | 4250.8 | 4250.8 | 4250.8 | | | |
| WW + T #1 | 1243.0 | 1130.4 | 1178.8 | | | |
| WD + T #1 | 1136.1 | 1027.5 | 1056.4 | | | |
| TARE #1 | 370.5 | 375.5 | 369.7 | | | |
| WW + T #2 | | | | | | |
| WD + T #2 | | | | | | |
| TARE #2 | | | | | | |
| MOISTURE | 14.0 | 15.8 | 17.8 | | | |
| DRY DENSITY | 102.7 | 110.2 | 106.9 | | | |

TEST RESULTS

Maximum dry density = 110.4 pcf

Optimum moisture = 16.1 %

Material Description: Silty Clay

Remarks:

Project No.: 111360 Client: Rio Grand Resources
Project: Mt.Taylor

○ Source of Sample: EA-BSC09 Depth: 2' - 3' Sample Number: A


Checked by: KG
Title:

ENGINEERING ANALYTICS, INC.

Figure

# COMPACTION TEST REPORT

Curve No.




Test Specification:
ASTM D 698-12 Method A Standard

Preparation Method: Moist
Hammer Wt.: 5.5 lb.
Hammer Drop: 12 in.
Hammer Type: Manual
Layers: three Blows/Layer: 25
Mold Size: 0.03333 cu. ft.

Test Performed on Material
Passing: #4 Sieve

NM: LL: NV PI: NP
Sp.G. (Assumed): 2.65
%>#4: %<No.200:
USCS: AASHTO:
Date Sampled:
Date Received:
Date Tested: 4/10/25
Tested By: SY

| TESTING DATA | 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|---|
| WM + WS | 6033.2 | 6176.7 | 6127.2 | 6113.4 | | |
| WM | 4250.0 | 4250.0 | 4250.0 | 4250.0 | | |
| WW + T #1 | 1060.2 | 1080.7 | 1199.7 | 864.2 | | |
| WD + T #1 | 986.7 | 981.3 | 1095.7 | 774.7 | | |
| TARE #1 | 402.9 | 402.0 | 400.9 | 299.8 | | |
| WW + T #2 | | | | | | |
| WD + T #2 | | | | | | |
| TARE #2 | | | | | | |
| MOISTURE | 12.6 | 17.2 | 15.0 | 18.9 | | |
| DRY DENSITY | 104.8 | 108.8 | 108.0 | 103.7 | | |

TEST RESULTS

Maximum dry density = 109.3 pcf

Optimum moisture = 16.4 %

Material Description: Sandy Clay

Remarks:

Project No.: 111360 Client: Rio Grand Resources
Project: Mt.Taylor

○ Source of Sample: EA-BSC12 Depth: 2' - 3' Sample Number: A

Checked by: AW
Title:

ENGINEERING ANALYTICS, INC.


Figure


# 9.0 Consolidated Undrained Triaxial Shear

Consolidated undrained (CU) triaxial shear tests were performed on 1 soil samples in accordance with ASTM D4767, "Standard Test Method for Consolidated Undrained Triaxial Compression Test for Cohesive Soils."

- Soil samples were trimmed, encased in a rubber membrane, and installed in the triaxial test cell.
- An initial effective stress of 1-3 psi was applied to facilitate saturation.
- Specimens were saturated to ≥ 95%.
- Following saturation, samples tested using the three-load method were consolidated to the effective stress specified by the project engineer. Samples tested using the three-stage method were consolidated to the effective stresses designated prior to each stage of testing.
- During the consolidation phase, drainage was permitted, allowing for volume changes.
- After a 24-hour consolidation period, the triaxial load cell was engaged, drainage was closed, and axial loading was initiated.
- Axial load, deformation, and pore-water pressure were measured to determine total stresses and axial compression.
- Each sample was sheared, and axial strain was recorded.
- Strength envelopes (total stress Mohr circles) were developed based on the test data.
- Strength envelopes were determined using either the three-load or three-stage method, as specified by the project engineer.
    - The three-load method utilizes data from three distinct samples, each consolidated under a different effective stress.
    - The three-stage method utilizes one sample, which is consolidated to differing effective stresses for each stage of the test.

The results of the CU tests are presented on the following pages.




| Sample No. | | 1 | 2 | 3 |
|---|---|---|---|---|
| Initial | Water Content, % | 26.2 | 26.2 | 26.2 |
| | Dry Density, pcf | 74.6 | 74.6 | 74.6 |
| | Saturation, % | 57.0 | 57.0 | 57.0 |
| | Void Ratio | 1.2186 | 1.2186 | 1.2186 |
| | Diameter, in. | 2.39 | 2.39 | 2.39 |
| | Height, in. | 5.20 | 5.20 | 5.20 |
| At Test | Water Content, % | 40.3 | 37.1 | 35.1 |
| | Dry Density, pcf | 78.8 | 82.2 | 84.4 |
| | Saturation, % | 97.3 | 97.1 | 96.9 |
| | Void Ratio | 1.0988 | 1.0136 | 0.9597 |
| | Diameter, in. | 2.34 | 2.34 | 2.36 |
| | Height, in. | 5.16 | 4.93 | 4.71 |
| Strain rate, in./min. | | 0.005 | 0.005 | 0.005 |
| Eff. Cell Pressure, psi | | 5.0 | 10.0 | 15.0 |
| Fail. Stress, psi | | 2.8 | 6.2 | 16.5 |
| Total Pore Pr., psi | | 83.0 | 85.8 | 88.1 |
| Strain, % | | 3.5 | 4.2 | 20.9 |
| Ult. Stress, psi | | | | |
| Total Pore Pr., psi | | | | |
| Strain, % | | | | |
| $\bar{\sigma}_1$ Failure, psi | | 4.7 | 10.4 | 23.5 |
| $\bar{\sigma}_3$ Failure, psi | | 1.9 | 4.2 | 6.9 |

**Type of Test:**
CU with Pore Pressures

**Sample Type:** Remolded

**Description:** Clay

**Specific Gravity=** 2.650

**Remarks:** While the test followed the ASTM D4767 Staged Method, the resulting data indicates the sample should be re-tested using the Three-Load Method for improved accuracy and reliability.

**Figure** _____

**Client:** Rio Grand Resources

**Project:** Mt.Taylor


**Source of Sample:** EA-BSC06/09 Combined


**Proj. No.:** 111360 **Date Sampled:**


TRIAXIAL SHEAR TEST REPORT


ENGINEERING ANALYTICS, INC.


**Tested By:** AW **Checked By:** KG








**Client:** Rio Grand Resources
**Project:** Mt.Taylor
**Source of Sample:** EA-BSC06/09 Combined
**Project No.:** 111360

**Figure** _____

**ENGINEERING ANALYTICS, INC.**

**Tested By:** AW **Checked By:** KG


Mt. Taylor
111360
EA-BSC 6 and 9 Combined
CUPP Triax
3 Stage (5, 10, 15 PSI)
MasterVision

# APPENDIX C
# Seismic Hazard Analysis – Mt. Taylor

# Seismic Hazard Analysis

# Mt. Taylor Mine

# Existing Mine Permit No. C1002RE

*Prepared for:*

**Rio Grande Resources**

*P.O. Box 1150*

*Grants, NM 87020*

*Prepared by:*

Engineering Analytics, Inc.

1600 Specht Point Road, Suite 209
Fort Collins, Colorado 80525
(970) 488-3111
Fax (970) 488-3112

Project No. 111360

November 26, 2025

# TABLE OF CONTENTS

**1.0 INTRODUCTION ..... 1**
**2.0 GEOLOGIC SETTING ..... 2**
2.1 Regional Physiographic and Tectonic Setting ..... 2
2.2 Site Geology ..... 3
**3.0 SEISMICITY ..... 4**
**4.0 SEISMIC HAZARD ANALYSIS ..... 5**
4.1 Seismic Sources ..... 5
4.1.1 Faults ..... 5
4.1.2 Background Event ..... 6
*4.1.2.1 Background Event in Deterministic Analyses ..... 6*
*4.1.2.2 Background Event in Probabilistic Analyses ..... 6*
4.2 Attenuation Relations ..... 7
4.2.1 Depth to Shear Wave Velocity of 1,000 m/s ..... 7
4.2.2 Depth to Shear Wave Velocity of 2,500 m/s ..... 7
4.2.3 Average Shear Wave Velocity for Upper 30 Meters ..... 8
4.3 Deterministic Analysis ..... 8
4.4 Probabilistic Analysis ..... 8
**5.0 RESULTS AND CONCLUSIONS ..... 10**
**6.0 LIMITATIONS ..... 11**
**7.0 REFERENCES ..... 12**

## LIST OF TABLES

Table 4-1 Minimum Criteria for Faults Considered in Seismic Investigation (NRC 10 CFR Appendix A to Part 100)

Table 4-2 National Earthquake Hazards Reduction Program (NEHRP) Site Class Definitions

Table 4-3 Hazard Contribution to Total Mean Hazard for 10,000-year Return Period, Probabilistic Analysis

## LIST OF FIGURES

Figure 1-1 Project Location

Figure 3-1 Historic Earthquakes with Magnitude Greater than 4.0 within 300 Kilometers of the Facility

Figure 3-2 Historic Earthquakes with Magnitude Greater than 2.4 within 100 Kilometers of the Facility

Figure 4-1 Faults with Quaternary Displacement within 300 Kilometers of the Facility

Figure 4-2 Faults with Quaternary Displacement that meet the NRC Minimum Criteria within 100 Kilometers of the Facility

Figure 4-3 Total Seismic Hazard Curve

Figure 4-4 Source Contribution to Total Seismic Hazard

## LIST OF APPENDICES

Appendix A Earthquake Events near the Facility

A.1 Earthquake Events with Magnitude Greater Than or Equal to 4.0 Occurring Within 300 Kilometers of the Facility

A.2 Earthquake Events with Magnitude Greater Than or Equal to 2.4 Occurring Within 100 Kilometers of the Facility

Appendix B Faults with Quaternary Displacement near the Facility

B.1 List of Faults within 100 Kilometers of the Facility that meet NRC Minimum Criteria

B.2 USGS Description of Faults Meeting the NRC Minimum Criteria

Appendix C Deterministic Analyses

C.1 Deterministic EZ-Frisk Software Input

C.2 Deterministic Results

Appendix D Probabilistic Analyses

D.1 Summary of Probabilistic Characteristics

D.2 Probabilistic EZ-Frisk Software Input

D.3 Probabilistic Results

# 1.0 INTRODUCTION

Engineering Analytics, Inc. (EA) has prepared this report to present the results of a seismic hazard analysis conducted for the Mt. Taylor Uranium Mine (Facility). This seismic hazard analysis has been prepared to characterize the peak horizontal ground acceleration (PGA) for use in stability analyses for the Facility. The seismic hazard was determined for the 10,000-year return period.

The Mt Taylor Uranium Mine is located just northeast of the town of San Mateo in Cibola County, New Mexico. The site is shown on Figure 1-1. For the purposes of these analyses, EA used a central location with coordinates of 35.3409°N latitude and 107.6353°W longitude.

# 2.0 GEOLOGIC SETTING

## 2.1 Regional Physiographic and Tectonic Setting

The Facility is located within the Colorado Plateau physiographic province in northwestern New Mexico. The Colorado Plateau is a broad, roughly circular region of relative structural stability within a more structurally active region of disturbed mountain systems. Broad basins and uplifts, monoclines, and belts of anticlines and synclines are characteristic of the plateau (Kelley, 1979). Igneous intrusions have formed several mountains. However, most of the topographic relief in the Colorado Plateau is the result of erosion of deep canyons rather than upstanding mountain ranges (Thornbury, 1965). According to the New Mexico Bureau of Geology and Mineral Resources (2025):

> *The Colorado Plateau in New Mexico includes the San Juan Basin, a major source of oil, gas, coal, and uranium for our state. The northwest-trending Zuni Mountains form the southwestern margin of the San Juan Basin. Both the San Juan Basin and the Zuni Mountains are broad downwarps and upwarps that formed during regional-scale compression about 75 million years ago during the Laramide orogeny (e.g., Cather, 2004). The southeast margin of the Colorado Plateau is covered by <5 million year-old volcanic rocks that erupted along the Jemez lineament, a northeast-trending zone of weakness that likely developed about 1.6 billion years ago as the North American continent was forming.*

The site is located at the base of the Mt Taylor Volcanic Field. Mount Taylor is an extinct composite stratovolcano that is part of the greater Mount Taylor–Mesa Chivato volcanic field (Hunt, 1938; Crumpler, 1980a, b). According to the New Mexico Bureau of Geology and Mineral Resources (2025):

> *Mount Taylor volcano, a prominent landmark that can be seen on the skyline west of Albuquerque, is located about 15 miles northwest of the town of Grants, New Mexico. Mount Taylor Peak, at an elevation of 11,301 feet, stands approximately one mile above the Rio San Jose 12 miles to the south (Hunt, 1938). Mount Taylor volcano is part of a larger, northeast-trending volcanic field that includes Mesa Chivato, a broad plateau located northeast of the cone, and Grants Ridge (Keating and Valentine, 1998; WoldeGabriel et al., 1999), located southwest of the cone. Basalt that caps Mesa Chivato and other mesas surrounding Mount Taylor makes up about 80% of the volume of the volcanic field (Perry et al., 1990). The Mount Taylor volcanic field lies on the southern flank of the San Juan Basin on the Colorado Plateau and straddles the extensional transition zone between the Colorado Plateau and the Rio Grande rift. The Mount Taylor volcanic field is considered to be part of the Jemez Lineament, a zone of young (< 5 million years old) volcanism aligned along an ancient suture in the 1.7 to 1.6 billion year old Proterozoic basement (Mayo, 1958, Laughlin et al., 1976; Lipman and Moench, 1972; Perry et al., 1990).*

Seismicity in the Mt Taylor Volcanic Field is generally low and is linked to regional tectonic activity rather than active volcanism. This seismic activity is influenced by geological features such as the Jemez Lineament and the Rio Grande Rift (Goff et. al., 2021). The adjacent Rio Grande Rift physiographic province is characterized as having low to moderate seismic activity.

## 2.2 Site Geology

The geologic map by McCraw et. al. (2009) indicates that the Facility is underlain by Quaternary-aged stream and valley slope alluvium overlying the Cretaceous-aged Menefee Formation. The alluvium is described as unconsolidated to partly consolidated, well-sorted, fine-grained sand, silty sand, and clay with a thickness 1 to 3 meters (McCraw et. al., 2009). The Menefee Formation is described as interbedded shales, siltstones, fine to medium grained sandstones, mudstones, and thin coals that generally form low-relief topography or forms landslides around the margins of the basalt-capped La Jara Mesa. The top of the unit is not exposed, but a minimum thickness is at least 90 meters (McCraw et. al., 2009).

## 3.0 SEISMICITY

NRC NUREG-6372 recommends that seismic sources within 300 kilometers be characterized for a site. The publication states that the distance for detailed source characterization for a site that contains a fault within 50 kilometers of the site is 100 kilometers. Therefore, this seismic hazard analysis for the Facility included a review of historic earthquakes which have occurred within 300 kilometers of the Facility and detailed review of the earthquakes within 100 kilometers. This earthquake record, which contains earthquakes from 1568 to 2025, provides a general overview of the seismicity in the study area. Our final search and review of earthquake activity took place on August 27, 2025; therefore, any earthquakes occurring after this date are not included in the analysis.

Catalogs from the USGS NSHMP for 2023 for the Western United States (WUS) and Central and Eastern United States (CEUS) (Peterson et. al., 2023) were reviewed to compile information on the historic earthquakes. These catalogs, compiled by the USGS for their study, included removal of duplicate events as well as aftershocks and foreshocks related to the primary earthquake events in order to obtain a catalog of independent events (Mueller, 2019 and Llenos, 2023). EA used the catalogs declustered with Reasenberg (1985; r85). The database includes historic seismic events over the period from 1568 through 2022. The WUS catalog contained 40 earthquakes in the 300-kilometer study area and the CEUS catalog contained no earthquakes. The catalogs were supplemented with events occurring between January 2023 and August 2025 by searching the National Earthquake Information Center (NEIC) database, also maintained by the USGS. This supplemental search resulted in no additional earthquakes. The catalog searches were limited to events with moment magnitude (Mw) greater than or equal to 4.0. A total of 40 events are included in the record for the 300-kilometer search as shown on Figure 3-1 and tabulated in Appendix A.1.

The earthquakes generally have small magnitudes with only 5 of the earthquakes having a magnitude greater than 5.0. Figure 3-1 shows that many of the earthquakes occur in the more seismically active Rio Grande Rift area to the east of the Facility. The largest event is estimated in the WUS catalog to have an Mw of 5.9. This event occurred west of San Antonio, New Mexico on July 16, 1906. The epicenter is approximately 160 kilometers southeast of the Facility, within the Rio Grande Rift. The event closest to the Facility had an epicenter about 13 kilometers southwest of the Facility. This earthquake, which occurred on December 24, 1973, had an Mw of 4.08.

In addition to the evaluation of significant earthquakes (Mw>4) as described above, a search of low magnitude events (Mw>2.4) within 100 kilometers of the Facility was also conducted. These events are shown in Figure 3-2 and are tabulated in Appendix A.2. The figure shows that the earthquake activity within a 100-kilometer radius of the site is diffuse. The earthquake record contained 15 earthquakes from the WUS catalog and 9 earthquakes from the NEIC catalog, the majority of which are low magnitude. A review of the historic seismicity confirms that this area has seen fairly low seismic activity.

# 4.0 SEISMIC HAZARD ANALYSIS

Seismic hazard analyses are typically conducted using one of two methods: (1) deterministic analysis or (2) probabilistic analysis. A deterministic seismic hazard analysis (DSHA) estimates the maximum ground motion that could occur at a specific location considering specific earthquake sources. It does not take into account the likelihood of occurrence. A probabilistic seismic hazard analysis (PSHA) estimates the likelihood that various levels of ground motion will be exceeded at a specific location over a given time. Both analyses were conducted for this seismic study as discussed below. EA used the deterministic analyses to aid in the probabilistic analyses. The final recommended PGA for the Facility was derived using probabilistic analyses for the 10,000-year return period. The seismic sources and attenuation equations used for this seismic hazard analysis are also discussed below, followed by the results of the deterministic and probabilistic analyses.

## 4.1 Seismic Sources

### 4.1.1 Faults

The existence and location of faults with Quaternary displacement were primarily identified using the USGS Quaternary Fault and Fold database (USGS et. al., 2025). A "capable fault" is defined by the Nuclear Regulatory Commission (NRC) in 10 CFR Appendix A to Part 100 – Seismic and Geologic Siting Criteria for Nuclear Power Plants – as a fault that has exhibited one or more of the following characteristics:

1. *Movement at or near the ground surface at least once within the past 35,000 years or movement of a recurring nature within the past 500,000 years.*

2. *Macro-seismicity (magnitude 3.5 or greater) instrumentally determined with records of sufficient precision to demonstrate a direct relationship with the fault.*

3. *A structural relationship to a capable fault according to characteristics (1) or (2) above such that movement on one could be reasonably expected to be accompanied by movement on the other.*

The faults from the Quaternary fault and fold database within 300 kilometers of the Facility are shown on Figure 4-1. Capable faults must also meet the minimum criteria for fault length and distance from the Facility, as defined by NRC 10 CFR Appendix A to Part 100, and included in Table 4-1 in this report. A fault that is deemed capable by the criteria listed above, but does not meet the minimum criteria provided in Table 4-1, does not need to be considered in the seismic hazard analysis. For the detailed analysis, the faults within 100 kilometers of the Facility that met these criteria are shown on Figure 4-2. A tabulated list of the faults is included in Appendix B.1.

All faults meeting the requirements outlined in Table 4-1 were considered in this seismic study. This is a conservative approach because although the NRC defines a "capable fault" as one having *"movement at or near the ground surface at least once within the past 35,000 years or movement of a recurring nature within the past 500,000 years,"* including all identifiable faults with Quaternary displacement would include fault movement over the past 1.6 million years. This was done because sufficient information does not exist for many of the faults with

Quaternary displacement as to the timing of the last movement of the fault.

The USGS separates the faults with Quaternary displacement into classes. These classes are provided below, as described by USGS.

- For a Class A fault, geologic evidence demonstrates the existence of a Quaternary fault of tectonic origin, whether the fault is exposed by mapping or inferred from liquefaction or other deformational features.
- For a Class B fault, geologic evidence demonstrates the existence of Quaternary deformation, but either 1) the fault might not extend deeply enough to be a potential source of significant earthquakes, or 2) the currently available geologic evidence is too strong to confidently assign the feature to Class C but not strong enough to assign it to Class A.
- For a Class C fault, geologic evidence is insufficient to demonstrate 1) the existence of tectonic faulting, or 2) Quaternary slip or deformation associated with the feature.
- For a Class D fault, geologic evidence demonstrates that the feature is not a tectonic fault or feature; this category includes features such as joints, landslides, erosional or fluvial scarps, or other landforms resembling fault scarps but of demonstrable non-tectonic origin.

The faults with Quaternary displacement included in this analysis are either Class A or B. Descriptions from the USGS of the faults included in this analysis, are included in Appendix B.2.

### 4.1.2 Background Event

Earthquakes sometimes occur that are not associated with a known geologic structure. These events are termed "background events" or "floating earthquakes." Evaluation of background events allows for potential low to moderate earthquakes unassociated with tectonic structures to be considered in the seismic hazard of the Facility. The maximum magnitude for these background events within the Intermountain United States ranges between local magnitude ($M_L$) 6.0 and 6.5 (Woodward-Clyde, 1996). Larger earthquakes would be expected to leave a detectable surface expression, especially in arid to semiarid climates, with slow erosion rates and limited vegetation. In seismically less active areas such as the Colorado Plateau, the maximum magnitude associated with a background event is assumed to be 6.3, consistent with that used in seismic evaluations performed for uranium tailing sites in Green River (DOE 1991a, pg. 26), and Grand Junction (DOE 1991b, pg. 71).

#### *4.1.2.1 Background Event in Deterministic Analyses*

Background or floating earthquakes are typically evaluated deterministically by placing the largest earthquake that can be assumed to occur unassociated with a known fault, at a distance of 15 kilometers from the project location.

#### *4.1.2.2 Background Event in Probabilistic Analyses*

For probabilistic analyses, the hazard from background earthquakes is typically assessed using two approaches. The first approach uses areal source zones and assumes a uniformly distributed seismicity within the zone. The second approach uses gridded seismicity which

retains a degree of stationarity using 0.1-degree latitude and longitude grid spacing, as used by USGS for the NSHMP. Due to the fact that the historic seismic record within 100 km of the Facility contains a small number of earthquakes, determination of recurrence intervals for a site-specific areal source zone was not completed. EA used the 2014 gridded source zone for the CEUS and the 2014 shallow extensional gridded source zone for the WUS in our analyses.

## 4.2 Attenuation Relations

Attenuation of ground motions from the location of a seismic event to the site was calculated using attenuation relations. Due to the absence of abundant strong ground motion records, no specific attenuation relation exists solely for New Mexico. Therefore, we have used ground motion models (GMMs) appropriate for tectonically active crustal regions. The crustal GMMs that were used were developed as part of the NGA-West2 Project sponsored by the Pacific Earthquake Engineering Research (PEER) Center Lifelines Program. These models are also used by the USGS in developing the U.S. National Seismic Hazard Maps. EA used four of the five NGA-West2 GMMs in the analyses: Chiou and Youngs (2014), Campbell and Bozorgnia (2014), Abrahamson and others (2014), and Boore and others (2014). Idriss (2014) was not included due to its lack of a hanging wall model.

Three parameters (depth to $V_s$ of 1000 m/s and 2,500 m/s and average $V_s30$) need to be specified in order to use the above attenuation equations. The three parameters are related to the shear wave velocity of the underlying soil and rock.

### 4.2.1 Depth to Shear Wave Velocity of 1,000 m/s

The National Earthquake Hazards Reduction Program (NEHRP, 2003) issued a publication which discusses site classification for seismic design. The publication listed the site classes and corresponding shear wave velocities. This information is summarized in Table 4-2.

The first parameter is the depth at which the shear wave velocity ($V_s$) of the soil reaches 1,000 meters per second (m/s) which is in the rock category as shown in Table 4-2. Based on previous subsurface investigation that EA has completed at the site along with the published site geology, this parameter was assumed to be 5 meters.

### 4.2.2 Depth to Shear Wave Velocity of 2,500 m/s

The next parameter is the depth at which shear wave velocity of the profile reaches 2,500 m/s (hard rock according to Table 4-2). EA was provided with a site geophysical scan for a draft pilot hole issued by Dames and Moore. The geophysical scan included a compressive wave velocity ($V_p$) profile. EA used the $V_p$ profile in determining the depth to 2,500 m/s for the shear wave velocity. The $V_p$ values needed to be converted to $V_s$ values. EA used a common equation to convert the $V_p$ values to $V_s$ values.

$$Vs = Vp\sqrt{\frac{1-2\nu}{2(1-\nu)}}$$

where:

$V_s$ = shear wave velocity
$V_p$ = compression wave velocity
$\nu$ = Poisson's ratio

The geophysical scan also included information on Poisson's ratio. Using that information and empirical correlations published in Bowles (1982) that indicate Poisson's ratios ranging from 0.1 to 0.4 for rock, EA used a Poisson's ratio of 0.27 for the calculations, which is generally consistent with the surficial and bedrock materials. The profile indicates the approximate average depth to a shear wave velocity of 2,500 m/s is 0.79 kilometers below the ground surface.

### 4.2.3 Average Shear Wave Velocity for Upper 30 Meters

The next parameter to be specified is the average shear wave velocity of the upper 30 meters ($V_s30$) of the original ground surface. EA estimated an average $V_p30$ velocity for the profile and converted that to $V_s30$ using the above equation. The resulting $V_s30$ for the profiles 30 meters below the Facility was calculated to be 1,200 m/s. This value is in the rock category according to Table 4-2.

## 4.3 Deterministic Analysis

A deterministic analysis was completed for the Facility in order to determine which faults from the USGS Quaternary fault and fold database have the potential to produce PGAs of 0.05g or greater and would need further evaluation in a probabilistic model. A PGA of 0.05g is commonly used as a threshold value to streamline probabilistic hazard analysis by excluding sources unlikely to cause significant seismic shaking. PGA values around 0.05g are often seen as the threshold below which the ground shaking is considered negligible for most engineering purposes. In deterministic analyses, the ground motions from the maximum credible earthquake (MCE) associated with capable faults are attenuated to the site.

The seismic sources considered for the deterministic analysis include the previously described faults listed in Appendix B.1. The MCE associated with each fault was calculated based on correlations between fault surface rupture length and earthquake magnitude as presented by Wells and Coppersmith (1994). The ground motions from the MCE associated with the faults were attenuated to the Facility using the attenuation relations described in Section 4.2. Typically, ground motions of median plus one standard deviation are reported in deterministic analyses. The PGA was calculated using EZ-FRISK Version: 8.11 (Risk Engineering, 2024). Input and the complete deterministic spectra from the EZ-FRISK analysis are included in Appendix C.1 and C.2, respectively. The inputs and results of the deterministic analyses are also summarized in a table in the beginning of Appendix C.2.

## 4.4 Probabilistic Analysis

A probabilistic analysis was performed for the Facility in order to evaluate the amount of risk associated with larger PGAs calculated by the deterministic analysis. In probabilistic analyses, ground motions and the associated probability of exceedance are estimated for background seismicity and for earthquakes on specific faults in order to evaluate the amount of risk associated with the PGA.

For the purpose of the seismic hazard evaluation, a 10,000-year return period is adopted for evaluating long-term stability. For the probabilistic analysis, faults that are included in the USGS Quaternary fault and fold database and have the potential to produce PGAs of 0.05g or greater (based on deterministic methods) were selected for further evaluation in the probabilistic model. These criteria resulted in the inclusion of the following 9 faults:

1. Intrabasin faults on the Llano de Albuquerque (2121);
2. Jemez-San Ysidro fault (Jemez and San Ysidro sections) (2029ab);
3. Jemez-San Ysidro fault (Calabacillas section) (2029c);
4. Mesa Prieta faults (1985);
5. Nacimiento fault (northern and southern sections) (2002ab);
6. Sand Hill fault zone (2039);
7. Santa Fe fault (2123);
8. unnamed faults near Albuquerque Volcanoes (2049);
9. unnamed faults of El Malpais lava field (2146);

As discussed above, EA also included the 2014 CEUS gridded source and the 2014 shallow extensional WUS gridded source in our analyses. The gridded seismicity retains a degree of stationarity using 0.1-degree latitude and longitude grid spacing, as used by USGS for the NSHMP.

The USGS descriptions included in Appendix B.2 were used to determine fault characteristics where possible. Uncertainties in the fault characteristics are incorporated into the probabilistic analysis by representing the possible scenarios with a weight value. Maximum magnitudes for the faults were estimated based upon the empirical relationship developed by Wells and Coppersmith (1994) for surface rupture length, with an uncertainty of 0.3 corresponding to the standard error in the Wells and Coppersmith (1994) relationship. The recurrence relationships for the faults were modeled using maximum magnitude recurrence models. Slip rates are used to characterize rates of fault activity. However, very limited data was available regarding slip rates, and the USGS Fault and Fold Database categorizes all the considered faults as simply having a slip-rate less than 0.2 mm per year. Slip rates were therefore modeled as being 0.02 mm per year, similar to rates of activity assigned to many faults of questionable Quaternary activity in the Rio Grande Rift area east of the Colorado Plateau (Wong et. al., 2004).

The EZ Frisk probabilistic input is included in Appendix D.2. Table 4-3 shows the seismic source contribution to the total mean hazard at a return period of 10,000 years (1E-4 annual percent exceedance). The total hazard curve is shown in Figure 4-3 and the source contribution is shown in Figure 4-4. The complete results of the probabilistic analyses are included in Appendix D.3.

## 5.0 RESULTS AND CONCLUSIONS

EA conducted deterministic and probabilistic analyses for the 10,000-year return period seismic events to support stability analyses for the Facility.

The deterministic analysis showed that the random earthquake produced the highest PGA for the Facility. EA determined that the random earthquake with an MCE of magnitude of 6.3, located 15.1 km from the site, produced a mean PGA of 0.09g. Additionally, the Mesa Prieta faults are the closest faults to the site (~47 kilometers) and EA determined a maximum credible earthquake (MCE) of magnitude 6.3 for this fault based on the Wells and Coppersmith (1994) relationship. The deterministic PGA determined for the Busted Boiler Fault was 0.03g.

The probabilistic analyses show that the hazard is controlled by the gridded seismicity. For the probabilistic analysis, EA calculated a mean PGA of 0.21g for the 10,000-year return period. These values should be used in slope stability and other technical analyses as appropriate for the site.

To confirm the validity of these values, EA ran a cross check using a USGS screening-level methodology. The USGS maintains a *"USGS Earthquake Hazard Toolbox"* that has web applications for computing hazards for the USGS National Seismic Hazard Models. EA used the 2023 model (accessed in November 2025) as a screening tool for this site, which calculated PGA of 0.37g for the 10,000-year return period. It is likely that the majority of the difference between the USGS and the site-specific PGA is a result of using different attenuation relationships. The USGS applied some attenuation relations developed for the CEUS. However, using attenuation relations that are specific to normal extensional faulting is appropriate for this area.

## 6.0 LIMITATIONS

The opinions and recommendations in this report are based on a reasonable degree of certainty. This report has been prepared based upon review of the reference documents, geological analyses, and our experience. The conclusions presented represent our best judgment based on the information available. Should additional information become available we should be allowed to review that information and modify our conclusions accordingly.

## 7.0 REFERENCES

Abrahamson, N.A., W.J. Silva, and R. Kamai. (2014). *Summary of the ASK14 ground-motion relation for active crustal regions*. Earthquake Spectra 30(3): 1025-1055.

Boore, D.M., J.P. Stewart, E. Seyhan, and G. Atkinson. (2014). *NGA-West2 equations for predicting PGA, PGV, and 5% damped PSA for shallow crustal earthquakes.* Earthquake Spectra 30(3): 1057-1085.

Bowles, J.E. (1982). *Foundation Analysis and Design*. McGraw Hill, Inc.

Campell K.W., and Y. Bozorgnia. (2014). *NGA-West2 Ground Motion Model for the Average Horizontal Components of PGA, PGV, and 5% Damped Linear Acceleration Response Spectra*. Earthquake Spectra 30(3).

Cather, S.M. (2004). *The Laramide orogeny in central and northern New Mexico and southern Colorado*, in Mack, G.H., and Giles, K.A., eds., The Geology of New Mexico, A Geologic History: New Mexico Geological Society Special Publication 11, p. 203-248.

Chiou. B.S.-J., and R.R. Youngs. (2014). *Update of the Chiou and Youngs NGA Model for the Average Horizontal Component of Peak Ground Motion and Response Spectra*. Earthquake Spectra 30 (3): 1117–1153.

Crumpler, L.S., (1980a), *Alkali basalt through trachyte suite and volcanism, Mesa Chivato, Mount Taylor volcanic field, New Mexico*: Geological Society of America Bulletin, Part I, v. 91, p. 253-255.

Crumpler, L.S., (1980b), *Alkali basalt through trachyte suite and volcanism, Mesa Chivato, Mount Taylor volcanic field, New Mexico*: Geological Society of America Bulletin, Part II, v. 91, p. 1293-1313.

DOE (U.S. Department of Energy). (1989). *Technical Approach Document: Revision II, Uranium Mill Tailings Remedial Action Project.* Washington D.C.

DOE (U.S. Department of Energy). (1991a). *Remedial Action Plan and Final Design for Stabilization of the Inactive Uranium Mill Tailings at Green River, Utah.*

DOE (U.S. Department of Energy). (1991b). *Remedial Action Plan and Site Design for Stabilization of the Inactive Uranium Mill Tailings Site at Grand Junction, Colorado.*

Goff, F., McIntosh, W., Peters, L., Wolff, J.A., Kelley, S.A., Goff, C.J., and Osburn, G.R. (2021). *Volcanic Evolution of Mount Taylor Stratovolcano, New Mexico: Facts and Misconceptions*. New Mexico Geological Society Guidebook, 71st Field Conference, Geology of the Mount Taylor Area, 2021, p. 117-128.

Hunt, C.B., (1938), *Igneous geology and structure of the Mount Taylor volcanic field, New Mexico*: U.S. Geological Survey Professional Paper 189-B, p. 51-80.

Idriss, I.M. (2014). *An NGA-West2 empirical model for estimating the horizontal spectral values generated by shallow crustal earthquakes*. Earthquake Spectra 30(3): 1155-1177.

Keating, G.N., and Valentine, G.A., (1998), *Proximal stratigraphy and syn-eruptive faulting in rhyolitic Grants Ridge Tuff, New Mexico, USA*: Journal of Volcanology and Geothermal Research, v. 81, p. 37-49.

Kelley, V.C. (1979). Tectonics of the Colorado Plateau and new interpretation of its eastern boundary. *Tectonophysics* 61: 97-102.

Laughlin, A.W., Brookins, D.G., and Damon, P.E., (1976), *Late Cenozoic basaltic volcanism along the Jemez zone of New Mexico and Arizona*: Geological Society of America Abstracts with Programs: v. 8 p. 1976.

Lipman P.W., and Moench, R.H., (1972), *Basalts of the Mount Taylor volcanic field, New Mexico*: Geological Society of America Bulletin, v. 83, no. 5, p. 1335-1343.

Llenos AL, Michael AJ, Shumway AM, Rubinstein JL, Haynie KL, Moschetti MP, Altekruse JM and Milner KR. (2023). *Forecasting the long-term spatial distribution of earthquakes for the 2023 US National Seismic Hazard Model using gridded seismicity*. Bulletin of the Seismological Society of America, in review.

Mayo, E.B., 1958, Lineament tectonics and some ore districts of the southwest, Transactions of AIME, v. 211, 1169-1175

McCraw, D., Read, A., Lawrence, J., Goff, F., and Goff, C. (2009). *Geologic map of the San Mateo quadrangle, Cibola and McKinley counties, New Mexico.* New Mexico Bureau of Geology and Mineral Resources, Open-File Geologic Map OF-GM 194. Scale 1:24,000.

Mueller, C.S. (2019). *Earthquake Catalogs for the USGS National Seismic Hazard Maps* February.

National Earthquake Hazards Reduction Program. (2003). *Recommended Provisions for Seismic Regulations for New Buildings and Other Structures (FEMA 450).*

New Mexico Bureau of Geology and Mineral Resources (2025). Mt. Taylor Volcanic Field. https://geoinfo.nmt.edu/tour/landmarks/mt_taylor/home.html (Accessed 2025).

Nuclear Regulatory Commission (NRC) in 10 CFR Appendix A to Part 100 – *Seismic and Geologic Siting Criteria for Nuclear Power Plants.*

Perry, F.V., Baldridge, W.S., DePaolo, J., and Shafiqullah, M., 1990, *Evolution of a magmatic system during continental extension: the Mount Taylor volcanic field, New Mexico*: Journal of Geophysical Research, v. 95, p. 19327-19348.

Petersen, M.D., Shumway, A.M., Powers, P.M., Field, E.H., Moschetti, M.P., Jaiswal, K.S., Milner, K.R., Rezaeian, S., Frankel, A.D., Llenos, A.L., Michael, A.J., Altekruse, J.M., Ahdi, S.K., Withers, K.B., Mueller, C.S., Zeng, Y., Chase, R.E., Salditch, L.M., Luco, N., Rukstales, K.S., Herrick, J.A., Girot, D.L., Aagaard, B.T., Bender, A.M., Blanpied, M.L., Briggs, R.W., Boyd, O.S., Clayton, B.S., DuRoss, C.B., Evans, E.L., Haeussler, P.J., Hatem, A.E., Haynie, K.L., Hearn, E.H., Johnson, K.M., Kortum, Z.A., Kwong, N.S., Makdisi, A.J., Mason, H.B., McNamara, D.E., McPhillips, D.F., Okubo, P.G., Page, M.T., Pollitz, F.F., Rubinstein, J.L., Shaw, B.E., Shen, Z.K., Shiro, B.R., Smith, J.A., Stephenson, W.J., Thompson, E.M., Thompson Jobe, J.A., Wirth, E.A., and Witter, R.C., (2023). *Data Release for the 2023 U.S. 50-State National Seismic Hazard Model – Overview.* U.S. Geological Survey data release, https://doi.org/10.5066/P9GNPCOD.

Risk Engineering. (2024). EZ-FRISK Version: 8.11*, Software for Earthquake Ground Motion Estimation.*

Reasenberg PA. (1985). *Second-order moment of central California seismicity, 1969-1982*. Journal of Geophysical Research: Solid Earth 90(B7): 5479-5495.

Thornbury, M. (1965). *Regional Geomorphology of the United States,* John Wiley and Sons, Inc., New York.

U.S. Geological Survey, Colorado Geological Survey, Idaho Geological Survey, and Utah Geological Survey, *Quaternary fault and fold database for the United States*, http//earthquake.usgs.gov/regional/qfaults/ (Accessed 2025).

Wells, D.L. and K.J. Coppersmith. (1994). New empirical relationships among magnitude, rupture length, rupture width, rupture area, and surface displacement. *Bulletin of the Seismological Society of America* 84(4): 974-1002.

WoldeGabriel, G., Keating, G.N., and Valentine, G.A., 1999, *Effects of shallow basaltic intrusion into pyroclastic deposits*, Grants Ridge, New Mexico, USA, Journal of Volcanology and Geothermal Research, v. 92, p. 389-411.

Wong, 1., S. Olig, M. Dober, W. Silva, D. Wright, P. Thomas, N. Gregor, A. Sanford, K. Lin, and D. Love. (2004). *Earthquake scenario and probabilistic ground-shaking hazard maps for the Albuquerque-Belen-Santa Fe, New Mexico corridor*. New Mexico Geology 26(1): 3-33.

Woodward-Clyde Consultants. (1996). *Evaluation and Potential Seismic and Salt Dissolution Hazards at the Atlas Uranium Mill Tailings Site, Moab, Utah,* Oakland, California, unpublished Consultant's report for Smith Environmental Technologies and Atlas Corporation, SK9407.

# TABLES

**Table 4-1 Minimum Criteria for Faults Considered in Seismic Investigation (NRC 10 CFR Appendix A to Part 100)**

| **Distance from Facility (mi) (km)** | **Minimum length of fault to be considered (mi) (km)** |
|---|---|
| 0 – 20 (0-32) | 1 (1.6) |
| 20 – 50 (32.2-80.5) | 5 (8.0) |
| 50 – 100 (80.5-160.9) | 10 (16.1) |
| 100 – 150 (160.9-241.4) | 20 (32.2) |
| 150 – 200 (241.4-321.9) | 40 (64.4) |

Note: The numbers listed in parentheses are in kilometers.

**Table 4-2 National Earthquake Hazards Reduction Program (NEHRP) Site Class Definitions**

| **Soil Profile Type** | **Average Shear Wave Velocity to 30-meter Depth ($V_s$)** |
|---|---|
| A – Hard Rock | > 1500 m/s |
| B – Rock | $760 < v_s < 1500$ m/s |
| C – Very Dense Soil and Soft Rock | $360 < v_s < 760$ m/s |
| D – Stiff Soil Profile | $180 < v_s < 360$ m/s |
| E – Soft Soil Profile | < 180 m/s |

**Table 4-3 Hazard Contribution to Total Mean Hazard for 10,000-year Return Period, Probabilistic Analysis**

| Source Name | USGS Fault ID Number | Distance from Facility (km) | Peak Ground Acceleration (10,000-year return period) |
|---|---|---|---|
| USGS 2014 CEUS Gridded | --- | --- | 0.03 |
| USGS 2014 WUS Shallow Extensional Gridded | --- | --- | 0.21 |
| Total Hazard[1] | --- | --- | 0.21 |

Note: 1) The total hazard PGA is the PGA for a specific return period considering the sources all together. Refer to Figure 4-3 for a visual explanation of individual source PGAs and the total hazard for the Facility.

# FIGURES





Project No. 111360

October 2025

Location used for Analysis

Engineering Analytics, Inc.

**FIGURE 1-1**
**PROJECT LOCATION**
**SEISMIC HAZARD ANALYSIS**
**MT TAYLOR MINE**
**CIBOLA COUNTY, NEW MEXICO**




# LEGEND

- WUS Earthquakes
- Mt Taylor Mine
- 300 Kilometers

Note: Earthquake number cooresponds to Appendix A.1 list of earthquakes

0 50 100 200 Kilometers


P:\111360 Mt. Taylor Hydrologic Support\2.0 EA Technical Info\2.8 Disposal Cell Expansion\2.8.11 Seismic Hazard Analysis\GIS\Figures\Fig 3-1 Earthquakes 300km.mxd Date Saved: October, 10, 2025

Project No: 111360

October 2025

Engineering Analytics, Inc.

**FIGURE 3-1**
**HISTORIC EARTHQUAKES WITH MAGNITUDE GREATER THAN 4.0 WITHIN 300 KILOMETERS OF THE FACILITY**
**SEISMIC HAZARD ANALYSIS**
**MT TAYLOR MINE**
**CIBOLA COUNTY, NEW MEXICO**




## LEGEND

- WUS Earthquakes
- NEIC Earthquakes
- ★ Mt Taylor
- 300 Kilometers

Note: Earthquake number cooresponds to Appendix A.2 list of earthquakes

0 12.5 25 50
Kilometers


P:\111360 Mt. Taylor Hydrologic Support\2.0_EA Technical Info\2.8 Disposal Cell Expansion\2.8.11 Seismic Hazard Analysis\GIS\Figures\Fig 3-2 Earthquakes 100km.mxd Date Saved: October, 10, 2025

Project No: 111360

October 2025

Engineering Analytics, Inc.

**FIGURE 3-2**
**HISTORIC EARTHQUAKES WITH MAGNITUDE GREATER THAN 2.4 WITHIN 100 KILOMETERS OF THE FACILITY**
**SEISMIC HAZARD ANALYSIS**
**MT TAYLOR MINE**
**CIBOLA COUNTY, NEW MEXICO**




## LEGEND

★ Mt Taylor Mine

**Quaternary Faults**

300 Kilometers


P:\111360 Mt. Taylor Hydrologic Support\2.0 EA Technical Info\2.8 Disposal Cell Expansion\2.8.11 Seismic Hazard Analysis\GIS\Figures\Fig 4-1 Quaternary Faults 300km.mxd Date Saved: October, 15, 2025

Project No. 111360

October 2025

Engineering Analytics, Inc.

**FIGURE 4-1**
**FAULTS WITH QUATERNARY DISPLACEMENT WITHIN 300 KILOMETERS OF THE FACILITY**
**SEISMIC HAZARD ANALYSIS**
**MT TAYLOR MINE**
**CIBOLA COUNTY, NEW MEXICO**




**LEGEND**

- Mt Taylor Mine
- 100 Kilometers

**Fault Name**

- Cat Mesa fault
- Cebollita Mesa fault
- Continental Divide fault
- County Dump fault
- Coyote Springs fault
- Intrabasin faults on the Llano de Albuquerque
- Jemez-San Ysidro fault
- Mesa Prieta faults
- Nacimiento fault
- San Felipe fault zone
- Sand Hill fault zone
- Santa Fe fault
- Zia fault
- unnamed fault of Bonita Canyon
- unnamed faults near Albuquerque Volcanoes
- unnamed faults near Picuda Peak
- unnamed faults near Star Heights
- unnamed faults of El Malpais lava field
- unnamed intrabasin faults west of the Rio Puerco

Note: Fault characteristics provided in Appendix B


P:\111360 Mt. Taylor Hydrologic Support\2.0_EA Technical Info\2.8 Disposal Cell Expansion\2.8.11 Seismic Hazard Analysis\GIS\Figures\Fig 4-2 Quaternary Faults 100km.mxd Date Saved: October, 10, 2025

Project No. 111360

October 2025

Engineering Analytics, Inc.

**FIGURE 4-2**
**FAULTS WITH QUATERNARY DISPLACEMENT THAT MEET NRC MINIMUM CRITERIA WITHIN 100 KILOMETERS OF THE FACILITY**
**SEISMIC HAZARD ANALYSIS**
**MT TAYLOR MINE**
**CIBOLA COUNTY, NEW MEXICO**





Project No. 111360

October 2025

Engineering Analytics, Inc.

**FIGURE 4-3**
**TOTAL SEISMIC HAZARD CURVE**
**SEISMIC HAZARD ANALYSIS**
**MT TAYLOR MINE**
**CIBOLA COUNTY, NEW MEXICO**




Project No. 111360

October 2025

Engineering Analytics, Inc.

**FIGURE 4-4**
**SOURCE CONTRIBUTION TO TOTAL SEISMIC HAZARD**
**SEISMIC HAZARD ANALYSIS**
**MT TAYLOR MINE**
**CIBOLA COUNTY, NEW MEXICO**

# APPENDIX A
# EARTHQUAKE EVENTS NEAR THE FACILITY

# APPENDIX A.1
# EARTHQUAKE EVENTS WITH MAGNITUDE GREATER THAN OR EQUAL TO 4.0 OCCURRING WITHIN 300 KILOMETERS OF THE FACILITY

**Appendix A.1 Earthquake Events with Magnitude Greater than or equal to 4.0 occurring within 300 kilometers of Mt Taylor**

Catalog: Western United States (WUS) Magnitude greater than or equal to 4.0

| Figure 3-2 ID | Magnitude (Mw) | Longitude (degree, west) | Latitude (degree, north) | Depth (km) | Year | Month | Day | Hour | Minute | Second |
|---|---|---|---|---|---|---|---|---|---|---|
| 0 | 5.2 | -106.6 | 34.7 | 0 | 1893 | 9 | 7 | 0 | 0 | 0 |
| 1 | 5.8 | -107.14 | 34.27 | 0 | 1906 | 7 | 12 | 12 | 15 | 0 |
| 2 | 5.9 | -107.09 | 33.99 | 0 | 1906 | 7 | 16 | 19 | 0 | 0 |
| 3 | 5.8 | -106.87 | 33.82 | 0 | 1906 | 11 | 15 | 12 | 15 | 0 |
| 4 | 4.7 | -106.01 | 35.41 | 0 | 1918 | 5 | 28 | 11 | 30 | 0 |
| 5 | 5 | -106.6 | 35.1 | 0 | 1930 | 12 | 3 | 21 | 36 | 0 |
| 6 | 5 | -106.6 | 35.1 | 0 | 1931 | 2 | 5 | 4 | 48 | 0 |
| 7 | 5 | -106.8 | 34.5 | 0 | 1935 | 2 | 21 | 1 | 25 | 0 |
| 8 | 5 | -106.8 | 34.7 | 0 | 1935 | 12 | 16 | 18 | 0 | 0 |
| 9 | 5 | -106.8 | 34.7 | 0 | 1935 | 12 | 20 | 10 | 30 | 0 |
| 10 | 4.1 | -108.95 | 32.91 | 0 | 1938 | 9 | 17 | 17 | 20 | 0 |
| 11 | 4.9 | -108.5 | 33.3 | 0 | 1938 | 9 | 17 | 17 | 20 | 17 |
| 12 | 4.3 | -108.5 | 33.3 | 0 | 1938 | 11 | 2 | 8 | 59 | 58 |
| 13 | 4.6 | -108.5 | 33.3 | 0 | 1938 | 11 | 27 | 0 | 12 | 39 |
| 14 | 5.5 | -109 | 33 | 0 | 1939 | 2 | 26 | 23 | 27 | 0 |
| 15 | 4.6 | -108.5 | 33.3 | 0 | 1939 | 6 | 4 | 1 | 19 | 10 |

# APPENDIX A.2
# EARTHQUAKE EVENTS WITH MAGNITUDE GREATER THAN OR EQUAL TO 2.4 OCCURRING WITHIN 100 KILOMETERS OF THE FACILITY

## Appendix A.2 Earthquake Events with Magnitude Greater than or equal to 2.4 occurring within 100 kilometers of Mt Taylor

Catalog: Western United States (WUS) Magnitude greater than or equal to 2.4

| Figure 3-2 ID | Magnitude (Mw) | Longitude (degree, west) | Latitude (degree, north) | Depth (km) | Year | Month | Day | Hour | Minute | Second |
|---|---|---|---|---|---|---|---|---|---|---|
| 0 | 5 | -106.6 | 35.1 | 0 | 1930 | 12 | 3 | 21 | 36 | 0 |
| 1 | 5 | -106.6 | 35.1 | 0 | 1931 | 2 | 5 | 4 | 48 | 0 |
| 2 | 4.5 | -106.61 | 35.1 | 0 | 1970 | 11 | 28 | 7 | 40 | 12 |
| 3 | 3.5 | -106.6 | 35.1 | 0 | 1971 | 1 | 4 | 7 | 39 | 7 |
| 4 | 4.7 | -106.6 | 35.1 | 0 | 1971 | 1 | 4 | 7 | 39 | 7 |
| 5 | 4.08 | -107.739 | 35.258 | 18 | 1973 | 12 | 24 | 2 | 20 | 15 |
| 6 | 3.4 | -107.16 | 34.55 | 0 | 1975 | 3 | 7 | 17 | 36 | 9 |
| 7 | 4.68 | -108.341 | 35.844 | 25 | 1976 | 1 | 5 | 6 | 23 | 33 |
| 8 | 4.28 | -108.286 | 35.915 | 22 | 1977 | 3 | 5 | 3 | 0 | 55 |
| 9 | 2.18 | -107.9 | 35.27 | 0 | 1981 | 8 | 14 | 2 | 6 | 57 |
| 10 | 2.68 | -107.51 | 35.105 | 5 | 2004 | 11 | 24 | 10 | 16 | 38 |
| 11 | 3.44 | -107.9 | 34.48 | 5 | 2009 | 9 | 23 | 13 | 3 | 14 |
| 12 | 3.5 | -107.405 | 35.235 | 5 | 2016 | 10 | 20 | 13 | 28 | 2 |
| 13 | 2.48 | -107.924 | 35.228 | 5 | 2019 | 8 | 10 | 4 | 16 | 45 |
| 14 | 2.78 | -108.377 | 35.956 | 5 | 2021 | 7 | 4 | 2 | 18 | 36 |

Catalog: National Earthquake Information Center (NEIC) Magnitude greater than or equal to 2.4

| Figure 3-2 ID | Magnitude | Longitude (degree, west) | Latitude (degree, north) | Depth (km) | Year | Month | Day | Hour | Minute | Second | Magnitude Type |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 0 | 2.6 | -108.026 | 34.7261 | 7.989 | 2025 | 5 | 8 | 10 | 59 | 54 | ml |
| 1 | 3.2 | -106.7918 | 35.1777 | 5.000 | 2024 | 9 | 10 | 15 | 36 | 1 | ml |
| 2 | 3.5 | -106.7783 | 35.2227 | 6.244 | 2024 | 9 | 10 | 14 | 11 | 46 | ml |

# APPENDIX B
# FAULTS WITH QUATERNARY DISPLACEMENT NEAR THE FACILITY

# APPENDIX B.1
# LIST OF FAULTS WITHIN 100 KILOMETERS OF THE FACILITY THAT MEET NRC MINIMUM CRITERIA

## Appendix B.1 List of Faults within 100 Kilometers of the Site

| Name of Faults | ID Number | Age of Most Recent Prehistoric Deformation (ya)[1] | Slip-rate (mm/yr) | Fault Length (Km) | Fault Type | Distance from site to surface trace of fault (km) |
|---|---|---|---|---|---|---|
| Cat Mesa fault | 2122 | <750,000 | <0.2 | 20 | Normal | 75.9 |
| Cebollita Mesa fault | 2140 | <15,000 | <0.2 | 13 | Normal | 74.8 |
| Continental Divide fault | 2145 | <1,600,000 | <0.2 | 17 | Normal | 91.8 |
| County Dump fault | 2038 | <130,000 | <0.2 | 35 | Normal | 76.5 |
| Coyote Springs fault | 2114 | <15,000 | <0.2 | 17 | Normal | 93.4 |
| Intrabasin faults on the Llano de Albuquerque | 2121 | <750,000 | <0.2 | 101 | Normal | 66.7 |
| Jemez-San Ysidro fault (Jemez section) | 2029a | <1,600,000 | <0.2 | 28 | Normal | 77.3 |
| Jemez-San Ysidro fault (San Ysidro section) | 2029b | <750,000 | <0.2 | 34 | Normal | 77.3 |
| Jemez-San Ysidro fault (Calabacillas section) | 2029c | <15,000 | <0.2 | 34 | Normal | 70.5 |
| Mesa Prieta faults | 1985 | <1,600,000 | <0.2 | 12 | Normal | 47.1 |
| Nacimiento fault (northern section) | 2002a | <1,600,000 | <0.2 | 36 | Normal | 72.3 |
| Nacimiento fault (southern section) | 2002b | <750,000 | <0.2 | 45 | Normal | 72.3 |
| San Felipe fault zone (Santa Ana section) | 2030a | <1,600,000 | <0.2 | 44 | Normal | 93.2 |
| San Felipe fault zone (Algodones section) | 2030b | <1,600,000 | <0.2 | 45 | Normal | 93.3 |
| Sand Hill fault zone | 2039 | <1,600,000 | <0.2 | 36 | Normal | 62.2 |
| Santa Fe fault | 2123 | <1,600,000 | <0.2 | 30 | Normal | 67.8 |
| unnamed fault of Bonita Canyon | 2144 | <1,600,000 | <0.2 | 9 | Normal | 49.3 |
| unnamed faults near Albuquerque Volcanoes | 2049 | <750,000 | <0.2 | 34 | Normal | 73.6 |
| unnamed faults near Picuda Peak | 2041 | <1,600,000 | <0.2 | 16 | Normal | 78.8 |
| unnamed faults near Star Heights | 2048 | <750,000 | <0.2 | 18 | Normal | 78.6 |
| unnamed faults of El Malpais lava field | 2146 | <1,600,000 | <0.2 | 26 | Normal | 60.5 |
| unnamed intrabasin faults west of the Rio Puerco | 2115 | <750,000 | <0.2 | 22 | Normal | 87.3 |
| Zia fault | 2046 | <15,000 | <0.2 | 32 | Normal | 73.7 |
| | | | | | | |

[1]ya = years ago

# APPENDIX B.2
# USGS DESCRIPTION OF FAULTS MEETING THE NRC MINIMUM CRITERIA

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Cat Mesa fault (Class A) No. 2122

**Last Review Date: 2016-04-11**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Personius, S.F., and Jochems, A.P., compilers, 2016, Fault number 2122, Cat Mesa fault, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:16 AM.**

| | |
|---|---|
| **Synopsis** | The active trace of the Cat Mesa fault extends from south of New Mexico State Highway 6 (west of Los Lunas) northward along the eastern edge of Cat Mesa. At about its midpoint, the Cat Mesa fault splits into two north-trending splays that offset Upper Santa Fe Group sediment and die out near the western edge of the Llano de Albuquerque. The Cat Mesa fault(s) offsets and exposes the late Pliocene Cat Mesa basalt flow along the eastern edge of Cat Mesa. The Cat Mesa basalt flow is interbedded with the upper part of the upper Santa Fe Group, the Ceja Formation, 6–10 m below the Llano de Albuquerque, and is offset about 30 m near the middle of the fault. Early and middle Pleistocene surficial deposits are offset about 17 m (net) across the two fault strands near the northern end of the fault zone. The Cat Mesa fault lies to the west of the late Pleistocene basalts of the Cat Hills, but the Cat Mesa basalt flow may have originated from the volcanic fault and dike system that fed the younger Cat Hills basalt field. |
| **Name comments** | The Cat Mesa fault was originally mapped by Kelley (1954 #1222; 1977 #1106) and in more detail by Kelley and Kudo (1978 #1307). Minor modifications were made by Machette (1978 #1223; 1982 #1401), Machette and |

| | |
|---|---|
| | McGimsey (1983 #1024), Maldonado and Atencio (1998 #1778), and Maldonado (2003 #7453).<br><br>**Fault ID:** Fault no. 3 of Machette (1982 #1401), fault no. 2 of Machette and McGimsey (1983 #1024). |
| **County(s) and State(s)** | VALENCIA COUNTY, NEW MEXICO <br>BERNALILLO COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | BASIN AND RANGE <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Fault traces from 1:24,000-scale geologic mapping in the Dalies NW and Rio Puerco 7.5-minute quadrangles (Maldonado and Atencio, 1998 #1778; Maldonado, 2003 #7453) combined with accurate placement of exposed traces using photogrammetric methods. <P> |
| **Geologic setting** | The Cat Mesa fault is an intrabasin fault near the western margin of the central Albuquerque-Belen basin. The Cat Mesa fault lies to the west of and does not offset the late Pleistocene basalts of the Cat Hills, but Kelley and Kudo (1978 #1307, fig. 20) inferred that the Cat Mesa basalt flow underlies and probably originated from the fault and dike system that fed the younger Cat Hills basalt field. Thus, the fault may be related to volcanic activity in the vicinity of the Cat Hills volcanic field. <P> |
| **Length (km)** | 20 km. |
| **Average strike** | N0°E |
| **Sense of movement** | Normal |
| **Dip Direction** | E; W<br><br>*Comments:* Maldonado and Atencio (1998 #1778) measured a dip of 80° toward the east-northeast where the Cat Mesa fault cuts sediment of the Ceja Formation. <P> |

| | |
|---|---|
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | The Cat Mesa fault is well expressed where the resistant Cat Mesa basalt flow is exposed in the fault zone. Elsewhere, the fault strands are marked by broad swales on the largely sand-covered Llano de Albuquerque. Machette and McGimsey (1983 #1024) estimated that the Cat Mesa basalt flow is offset about 30 m near the middle of the fault. They also estimated a total of 17 m of offset in early and middle Pleistocene deposits across the two fault strands near the northern end of the fault zone. <P> |
| **Age of faulted surficial deposits** | The Cat Mesa fault offsets the Cat Mesa basalt flow, dated at 3.0±0.1 Ma by <sup>40</sup>Ar/<sup>39</sup>Ar (Maldonado and Atencio, 1998 #1778). The Cat Mesa basalt flow is interbedded with the upper part of the upper Santa Fe Group, the Pliocene-early Pleistocene Ceja Formation (Machette, 1978 #1223; Maldonado and Atencio, 1998 #1778; Maldonado, 2003 #7453), 6–10 m below the Llano de Albuquerque (Kelley and Kudo, 1978 #1307). The two fault strands near the northern end of the fault zone offset the early Pleistocene (?) Llano de Albuquerque (Machette and McGimsey, 1983 #1024). |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | middle and late Quaternary (<750 ka)<br><br>*Comments:* Machette and McGimsey (1983 #1024) documented offset of the early Pleistocene (?) Llano de Albuquerque. They also speculated that if the Cat Mesa fault is related to structures controlling the basalts of the Cat Hills volcanic field, then there may be late Pleistocene movement on the Cat Mesa fault. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* No detailed studies of fault offset or timing are available; low slip-rate category assigned based on evidence that the 3 Ma Cat Mesa basalt is offset about 30 m (Machette and McGimsey, 1983 #1024; Personius and others, 1999 #6930). |

| | |
|---|---|
| **Date and Compiler(s)** | 2016<br>Stephen F. Personius, U.S. Geological Survey<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #1222 Kelley, V.C., 1954, Tectonic map of a part of the upper Rio Grande area, New Mexico: U.S. Geological Survey Oil and Gas Investigations Map OM-157, 1 sheet, scale 1:190,080.<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1307 Kelley, V.C., and Kudo, A.M., 1978, Volcanoes and related basalts of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Circular 156, 29 p., 2 pls.<br><br>#1401 Machette, M.N., 1982, Quaternary and Pliocene faults in the La Jencia and southern part of the Albuquerque-Belen basins, New Mexico—Evidence of fault history from fault-scarp morphology and Quaternary geology, in Grambling, J.A., and Wells, S.G., eds., Albuquerque Country II: New Mexico Geological Society, 33rd Field Conference, November 4-6, 1982, Guidebook, p. 161-169.<br><br>#1024 Machette, M.N., and McGimsey, R.G., 1983, Map of Quaternary and Pliocene faults in the Socorro and western part of the Fort Sumner 1° x 2° quadrangles, central New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-1465-A, 12 p. pamphlet, 1 sheet, scale 1:250,000.<br><br>#1223 Machette, M.N., compiler, 1978, Preliminary geologic map of the Socorro 1° by 2° quadrangle, central New Mexico: U.S. Geological Survey Open-File Report 78-607, 1 sheet, scale 1:250,000.<br><br>#7453 Maldonado, F., 2003, Geologic map of the Rio Puerco quadrangle, Bernalillo and Valencia Counties, New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-2397, scale 1:24,000.<br><br>#1778 Maldonado, F., and Atencio, A., 1998, Preliminary geologic map of the Dalies northwest quadrangle, Bernalillo County, New Mexico: U.S. Geological Survey Open-File Report 97-741, 1 sheet, scale 1:24000.<br><br>#6930 Personius, S.F., Machette, M.N., and Kelson, K.I., 1999, Quaternary faults in the Albuquerque area—An update, in Pazzaglia, F.J., and Lucas, S.G., eds., Albuquerque geology: New Mexico Geological Society 50th Annual Field Conference, Guidebook, September 22–25, p. 189–200. |

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Cebollita Mesa fault (Class A) No. 2140

**Last Review Date: 2016-04-22**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Machette, M.N., and Jochems, A.P., compilers, 2016, Fault number 2140, Cebollita Mesa fault, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:18 AM.**

| | |
|---|---|
| **Synopsis** | The Cebollita Mesa fault has seemingly young (<15 ka) movement, which is anomalous in the sense that there are few mapped Quaternary faults in this region, and in the Colorado Plateaus Province in general. However, field studies have shown that the fault has been recurrently active in the late Quaternary. Single-event scarps on the fault are about 2–2.5 m high, whereas older, late (?) Pleistocene, alluvium has compound (multiple-event) scarps as much as 8 m high. No dating has been conducted to refine the timing of last movement, slip rate, or recurrence interval for this down-to-the-west normal fault. |
| **Name comments** | This Quaternary fault was named by Levish and others (1992 #1715) for Cebollita Mesa, a Pliocene basalt-covered mesa located about 8 km east and northeast of the fault. The fault was first shown by Machette (1978 #1223) on the geologic map of the Socorro 1° x 2° quadrangle, but was overlooked by Machette and McGimsey (1983 #1024) in their later fault compilation. Maxwell (1986 #1720) made the first detailed geologic map that showed the fault, whereas Levish (1992 #1715) characterized its late Quaternary history as part of a dam hazards study. The fault is mapped for about 13 km across the toe slope of dissected Cretaceous bedrock hills. It extends from the north side |

| | |
|---|---|
| | of Bonine Canyon on the south, north past Head Windmill and New Mexico State Highway 117. About 1 km north of the highway, the fault disappears beneath a young basalt flow. |
| **County(s) and State(s)** | CIBOLA COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | COLORADO PLATEAUS <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Trace from approximately 1:100,000-scale geologic map of Levish and others (1992 #1715) and 1:62,500-scale geologic map of Maxwell (1986 #1720) combined with accurate placement using photogrammetric methods. <P> |
| **Geologic setting** | The fault offsets the toe slope of dissected Cretaceous bedrock hills west of Cebollita Mesa. To the north, the fault disappears beneath a late Holocene basalt flow, but may continue further as suggested by as much as 300 m of down-to-the-west displacement on two normal faults imaged by shallow seismic-reflection profiling (Kelly and Reynolds, 1989 #1738). The Cebollita Mesa fault is subparallel to (but west of) similarly oriented normal faults that Maxwell (1986 #1720) maps as cutting Pliocene basalts of Cebollita Mesa. <P> |
| **Length (km)** | 13 km. |
| **Average strike** | N4°E |
| **Sense of movement** | Normal<br><br>*Comments:* As mapped by Maxwell (1986 #1720) and seen in natural exposures by Levish and others (1992 #1715). <P> |
| **Dip Direction** | W |

| | |
|---|---|
| | *Comments:* Although not mentioned by Levish and others (1992 #1715), the faults exposed in natural exposure have high-angle (near vertical) dips near the surface (Dan Levish, oral commun., 1988). <P> |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | The fault forms a north-trending, left-stepping series of three en echelon scarps. Levish and others (1992 #1715) measured four scarp profiles: one (P-1) on the northern strand and three (P-2 to P-4) on the southern half of the southern strand. These profiles document single-event scarps of about 2.2–2.5 m height (1.9–2.0 m surface offset) and compound (multiple-event) scarps of about 6.0–8.5 m height (5.2–7.5 m surface offset). All four of the profiled scarps have modest maximum scarp-slope angles of 10–16°, but they are formed on relatively fine-grained, easily eroded sediment. Analysis of this data by Levish and others (1992 #1715) suggested that the younger scarps are late Pleistocene or Holocene in age, whereas as the larger scarps have morphology indicative of late Pleistocene movement. The scarp data suggests that the morphometric data from the younger scarps (P-3 and P-4) are similar to the Drum Mountains scarps (early Holocene) and the Bonneville shoreline (~17.5–18 ka). Conversely, the compound scarps have nearly identical maximum scarp-slope angles as the single-event scarps, suggesting that the steepness of all the scarps is controlled by the younger (<15 ka) event. <P> |
| **Age of faulted surficial deposits** | Maxwell (1986 #1720) mapped the faults as offsetting fine-grained Quaternary alluvium derived from Cretaceous sedimentary rock to the east. The smaller scarps are formed on alluvium of the lowest fluvial terrace, whereas the compound scarps are on alluvium that forms the next highest fluvial terrace. These deposits are likely to be latest or late Pleistocene in age (<130 ka). Levish and others (1992 #1715) reported that the scarps are locally muted (buried) by eolian sand. No studies or detailed mapping have been conducted to refine the age of the Quaternary sediment that are offset by the fault. To the north of New Mexico State Highway 117, the fault disappears beneath the McCartys basalt flow, which is estimated to be of late Holocene age, 2.4–3.9 ka (Laughlin and others, 1994 #7439; Maxwell, 1986 # 1720; Dunbar and Phillips, 2004 #7424). |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | latest Quaternary (<15 ka)<br><br>*Comments:* Timing of most recent surface faulting based on scarp-morphology data (Levish and others, 1992 |

| | |
|---|---|
| | #1715) that is consistent with the continuity of the scarps, and expression on the lowest of the fluvial terraces of local streams that cross the scarps. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* It appears that the slip rate probably falls in the less than 0.2 mm/yr category because the 1.9–2.0 m of offset from the most recent event was the result of strain accumulation over 15–120 k.y. |
| **Date and Compiler(s)** | 2016<br>Michael N. Machette, U.S. Geological Survey, Retired<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |

| | |
|---|---|
| **References** | #7424 Dunbar, N.W., and Phillips, F.M., 2004, Cosmogenic <sup>36</sup>Cl ages of lava flows in the Zuni-Bandera volcanic field, north-central New Mexico, U.S.A., in Cather, S.M., McIntosh, W.C., and Kelley, S.A., eds., Tectonics, geochronology, and volcanism in the Southern Rocky Mountains and Rio Grande Rift: New Mexico Bureau of Geology and Mineral Resources Bulletin 160, p. 309–317.<br><br>#1738 Kelly, T.E., and Reynolds, C.B., 1989, Structural geology of the Malpais Valley, San Rafael, New Mexico, in Anderson, O.J., Lucas, S.G., Love, D.W., and Cather, S.M., eds., Southern Colorado Plateau: New Mexico Geological Society, 40th Field Conference, September 28-October 1, 1989, Guidebook, p. 119-121.<br><br>#7439 Laughlin, A.W., Poths, J., Healey, H.A., Reneau, S., and WoldeGabriel, G., 1994, Dating of Quaternary basalts using the cosmogenic <sup>3</sup>He and <sup>14</sup>C methods with implications for excess <sup>40</sup>Ar: Geology, v. 22, p. 135–138.<br><br>#1715 Levish, D.R., Vetter, U.R., Ake, J.P., and Piety, L.A., 1992, Seismotectonic study for Black Rock Dam, Bureau of Indian Affairs, Pueblo of Zuni, New Mexico: Bureau of Reclamation Seismotectonic Report 92-3, 62 p.<br><br>#1024 Machette, M.N., and McGimsey, R.G., 1983, Map of Quaternary and Pliocene faults in the Socorro and western part of the Fort Sumner 1° x 2° quadrangles, central New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-1465-A, 12 p. pamphlet, 1 sheet, scale 1:250,000.<br><br>#1223 Machette, M.N., compiler, 1978, Preliminary geologic map of the Socorro 1° by 2° quadrangle, central New Mexico: U.S. Geological Survey Open-File Report 78-607, 1 sheet, scale 1:250,000.<br><br>#1720 Maxwell, C.H., 1986, Geologic map of El Malpais Lava Field and surrounding areas, Cibola County, New Mexico: U.S. Geological Survey Miscellaneous Investigations Map I-1595, 1 sheet, scale 1:62,500. |

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Continental Divide fault (Class B) No. 2145

**Last Review Date: 2016-04-22**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Machette, M.N., and Jochems, A.P., compilers, 2016, Fault number 2145, Continental Divide fault, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:19 AM.**

| | |
|---|---|
| **Synopsis** | Little is known about this northeast-trending suspect fault; it reportedly forms a low but prominent scarp on Quaternary basalts of the North Plains lava field. The trend of the feature is parallel to a string of eruptive basalt cones that occupy the center of the field, which suggests that movement on the fault may be controlled by volcanism and deeper-seated crustal structures. No detailed studies have been conducted to determine the timing of movement or amount of offset of the basalt. Some authors have suggested that the scarp may be the result of volcanic processes, but its association with a mapped bedrock fault supports an interpretation of a tectonic origin. |
| **Name comments** | This suspect fault extends along the Continental Divide from about 3 km south of New Mexico State Highway 36 to 5 km north of Peñasco Lakes. Although unnamed by Anderson (1986 #1281), who first mapped it, Levish and others (1992 #1715) named it for its near coincidence with the Continental Divide. |

| | |
|---|---|
| **County(s) and State(s)** | CIBOLA COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | COLORADO PLATEAUS <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Trace from 1:100,000-scale geologic map of the Fence Lake quadrangle compiled by Anderson (1986 #1281) and 1:24,000-scale geologic map of the Techado 7.5' quadrangle (Arkell, 1984 #7422) combined with accurate placement using photogrammetric methods. <P> |
| **Geologic setting** | This northeast-trending feature appears to offset the southern part of the North Plains lava field and is parallel to eruptive basalt cones that occupy the center of the field. These cones mark the southwestern trace of the Jemez lineament, which is one of many northeast-trending crustal structures that control the location of young volcanism within and outside of the northern Rio Grande rift in New Mexico. The southern end of the feature is mapped as cutting the Miocene (?) Fence Lake Formation (Anderson, 1986 #1281). If this association is not a spatial coincidence, it would support a tectonic origin. <P> |
| **Length (km)** | 17 km. |
| **Average strike** | N20°E |
| **Sense of movement** | Normal<br><br>*Comments:* As reported by Anderson (1986 #1281). <P> |
| **Dip Direction** | SE<br><br>*Comments:* Although no dips are reported, the general direction is inferred from a southeast-facing escarpment. <P> |

| | |
|---|---|
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | Fault forms a scarp of 2–3 m height (Orin Anderson, written commun., 1997) on basalts of the North Plains lava field. Levish and others (1992 #1715) argued that the scalloped appearance of the escarpment suggests it is a volcanic flow margin and not a fault. <P> |
| **Age of faulted surficial deposits** | This feature appears to offset Quaternary basalts according to Anderson (1986 #1281). The Jaralosa Draw lobe (flow), which extends west from the North Plains lava field and has also been called the Fence Lake flow, has a K-Ar age of 1.38±0.29 Ma (Laughlin and West, 1976 #7420). Other basalt flows in the North Plains field have returned Ar-Ar ages of approximately 0.6-0.7 Ma (Laughlin and others, 1993 #7421), consistent with the seemingly young appearance of cinder cones such as at Chimney Hill. |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | undifferentiated Quaternary (<1.6 Ma)<br><br>*Comments:* Timing poorly controlled. Based on presence of scarp on early to perhaps middle Quaternary basalt. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Low slip rate estimated from presence of scarp of 2–3 m height (Orin Anderson, written commun., 1997) on early to perhaps middle Quaternary basalt. |
| **Date and Compiler(s)** | 2016<br>Michael N. Machette, U.S. Geological Survey, Retired<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |

| | |
|---|---|
| **References** | #1281 Anderson, O.J., compiler, 1986, Geologic map of Fence Lake, New Mexico 1:100,000 metric sheet: New Mexico Bureau of Mines and Mineral Resources Open-File Report 220, 4 p. pamphlet, 4 sheets, scale 1:100,000.<br><br>#7422 Arkell, B., 1984, Geology and coal resources of the Techado quadrangle, Catron and Cibola Counties, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Report 221, 21 p., 2 pl., scale 1:24,000.<br><br>#7420 Laughlin, A.W., and West, F.G., 1976, The Zuni Mountains, New Mexico, as a potential dry hot rock geothermal energy site: U.S. Energy Research and Development Administration, Los Alamos Scientific Laboratories Informal Report LA-3197-MS, 13 p.<br><br>#7421 Laughlin, A.W., Perry, F.V., Damon, P.E., Shafiqullah, M., WoldeGabriel, G., McIntosh, W., Harrington, C.D., Wells, S.G., and Drakos, P.G., 1993, Geochronology of Mount Taylor, Cebollita Mesa, and Zuni-Bandera volcanic fields, Cibola County, New Mexico: New Mexico Geology, v. 16, no. 4, p. 81–92.<br><br>#1715 Levish, D.R., Vetter, U.R., Ake, J.P., and Piety, L.A., 1992, Seismotectonic study for Black Rock Dam, Bureau of Indian Affairs, Pueblo of Zuni, New Mexico: Bureau of Reclamation Seismotectonic Report 92-3, 62 p. |

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## County Dump fault (Class A) No. 2038

**Last Review Date: 2015-02-19**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Haller, K.M., Personius, S.F., Olig, S.S., and McCalpin, J.P., compilers, 2015, Fault number 2038, County Dump fault, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:19 AM.**

| | |
|---|---|
| **Synopsis** | The County Dump fault is a down-to-the-east, north-trending normal fault located in the northern part of the Albuquerque-Belen basin. The fault offsets deposits of the upper Santa Fe Group, well-developed calcic soils of the Llano de Albuquerque, and about 155-ka basalt of the Albuquerque Volcanoes volcanic field. Repeated surface-faulting in the past 1 m.y. is expressed as a subdued, 24-m-high, up to 800-m-wide fault scarp across the Llano de Albuquerque and was first recognized during early geologic work in the region. An exposure of the fault at the now abandoned Bernalillo County landfill (dump) has been described in two detailed studies addressing the history of surface rupture. The most recent study used thermoluminescence (TL) ages and detailed soils analyses to constrain the time of the most recent surface-faulting event on the County Dump fault at 24 ka. |
| **Name comments** | The County Dump fault was originally mapped and named by Lambert (1968 #1396) for a down-to-the-east normal fault exposed at the now abandoned Bernalillo County landfill site, located about 1.5 km north of Interstate 40. Kelley (1977 #1106) renamed this structure the Nine Mile fault and included a down-to-the west fault south of Interstate 40 that was originally mapped by Lambert (1968 #1396). Machette (1982 #1401) used the name |

| | |
|---|---|
| | "Bernalillo County Dump fault" for this structure, but most workers since Kelley (1977 #1106) have used either "County Dump fault" (Machette, 1978 #1402; Hawley and Haase, 1992 #1304) or "Nine Mile fault zone" (Hawley and Whitworth, 1996 #1303) when referring to this structure. Cather and others (1997 #1763) called the northern end of the County Dump fault the "Centipede fault" in the Sky Village SE quadrangle. Herein we use the name "County Dump fault" as originally named by Lambert (1968 #1396) for the entire fault zone, because the "Nine mile fault" as mapped by Kelley (1977 #1106) and Hawley and Whitworth (1996 #1303) contains faults with both down-to-the-east and down-to-the-west displacements.<br><br>**Fault ID:** Fault no. 2 of Machette (1982 #1401), fault no. 1 of Machette and McGimsey (1983 #1024). |
| **County(s) and State(s)** | SANDOVAL COUNTY, NEW MEXICO <br>BERNALILLO COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | BASIN AND RANGE <br> |
| **Reliability of location** | Good<br>Compiled at 1:100,000 scale.<br><br>*Comments:* The trace of the County Dump fault is from Lambert (1968 #1396), Machette (1978 #1402), Cather and others (1997 #1763), air photo mapping by S.F. Personius (unpublished data, 1997), and high-resolution aeromagnetic data (U.S. Geological Survey and SIAL Geosciences Inc., 1997 #1722; Grauch and Millegan, 1998 #1721). <P> |
| **Geologic setting** | The County Dump fault is one of several north-trending intrabasin faults in the northern part of the Albuquerque-Belen basin. The fault also forms the western margin of a broad graben that confines some basalt flows of the Albuquerque Volcanoes volcanic field. The spatial association of the fault with the volcanic field may suggest a possible relationship with magmatic activity. <P> |
| **Length (km)** | 35 km. |
| **Average strike** | N5°E |

| | |
|---|---|
| **Sense of movement** | Normal |
| **Dip** | 75°–85° E.<br><br>*Comments:* Dip measurements are from near-surface fault exposures at the abandoned Bernalillo County landfill site (Lambert, 1968 #1396; Machette, 1978 #1402; McCalpin, 1997 #1767). <P> |
| **Paleoseismology studies** | The fault is well exposed in the northwest corner of the now abandoned Bernallilo County landfill. Here, the exposed County Dump fault offsets sands and gravels assigned to the Upper Buff or Ceja members of the Santa Fe Formation (Bryan and McCann, 1937 #1288; Kelley, 1977 #1106), which are now included in the Sierra Ladrones Formation of the upper Santa Fe Group (Hawley and others, 1991 #1302). The upper part of these rocks may be early Pleistocene in age. The fault also cuts the Llano de Albuquerque, an extensive Pleistocene surface formed on the Santa Fe Group. <P> Site 2038-1. Results from an early study of the natural exposure suggest that buried soils on colluvial deposits as young as 20–120 ka were deposited in response to large offsets (Machette, 1978 #1402). <P> Site 2038-2. The exposure at Bernalillo County landfill was re-excavated to address why previous estimates of displacement were so large and whether artificial exposures of the section might better reveal small scarp-derived colluvial deposits resulting from smaller displacement events. Six backhoe trenches that exposed the hanging wall deposits to a depth of 19–21 m below the surface were excavated for this study (McCalpin, 1997 #1767; McCalpin and others, 2006 #693). Interpretation of the exposures suggest that perhaps as many as 14 earthquakes occurred on the County Dump fault since the abandonment of the Llano de Albuquerque at 1.8-0.8 Ma (Connell and others, 2013 #7235); the timing of surface ruptures were constrained by thermoluminescence (TL) ages and quantitative analysis of soil properties developed on colluvial deposits deposited adjacent to the County Dump fault. Based on a number of assumptions, the mean vertical displacement in the past 14 events at this location is 1.2±0.6 m; it is not known if mean displacement at this location is a representative average for the fault or not (McCalpin and others, 2006 #693). <P> |
| **Geomorphic expression** | The County Dump fault is discontinuously exposed in upper Santa Fe Group sediment along the eastern Llano de Albuquerque. A broad, sand-covered, 24-m-high fault scarp, which is 800 m wide with maximum scarp-slope angle of 3.5° (McCalpin and others, 2006 #6931), marks the trace of the fault where it crosses the Llano de Albuquerque north of the Bernalillo County landfill exposure. The scarp is asymmetrical; the upper (erosional) part between the fault and scarp crest comprises only 25 percent of total scarp width. This asymmetry is used to substantiate the |

| | |
|---|---|
| | interpretation that large amount of deposition has occurred on the hanging wall since active fluvial deposition on the Llano de Albuquerque ceased. Further north, the County Dump fault skirts the western margin of the Albuquerque Volcanoes volcanic field, and extends northward as a broad escarpment on upper Santa Fe Group sediment and eroded remnants of the Llano de Albuquerque. South of the Bernalillo County dump exposure, the fault is exposed in upper Santa Fe Group sediment before ending a few kilometers south of Interstate Highway 40. <P> |
| **Age of faulted surficial deposits** | At the surface, the County Dump fault is in sands and gravels assigned to the Upper Buff or Ceja members of the Santa Fe Formation (Bryan and McCann, 1937 #1288; Kelley, 1977 #1106), which are now included in the Sierra Ladrones Formation of the upper Santa Fe Group (Hawley and others, 1991 #1302). Fault scarps are on the Llano de Albuquerque (1.8 Ma based on 40Ar/39Ar dating, Connell and others, 2013 #7235), an extensive early Pleistocene surface formed at the top of the Santa Fe Group and basalts dated at about155 ka of the Albuquerque Volcanoes volcanic field (Geissman and others, 1990 #1297; Peate and others, 1996 #1411). |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | late Quaternary (<130 ka)<br><br>*Comments:* McCalpin and others (2006 #6931) report evidence of a possible 24-ka earthquake that only produced warping of near-surface sand deposits. In addition, thermoluminescence (TL) ages suggest that the additional surface-rupturing earthquakes occurred at 39 ka and 59 ka. Therefore, two and possibly three earthquakes have occurred in the late Quaternary. Machette (1978 #1402) suggested a similar time of 20 ka for the latest significant earthquake on the County Dump fault based on regional rate of pedogenic calcium carbonate accumulation. <P> |
| **Recurrence interval** | 41 k.y. (<300 ka)<br><br>*Comments:* McCalpin and others (2006 #6931) used thermoluminescence (TL) ages and quantitative soils analysis to estimate the timing of 14 earthquakes. Six thermoluminescence (TL) samples ranging from 4 ka (at the surface) to greater than 293 ka (8.3 m below the surface) constrain the age of the uppermost colluvial wedges; the age of older soils (8.3–17.3 m below the surface) was estimated based on accumulation rate of pedogenic calcium carbonate of 0.26 g CaCO<sup>3</sup> per thousand years, based on data from the upper part of the section. Recurrence intervals range from 4 to 202 k.y. and average 40.8 k.y.; a better constrained average of 29.5±11 k.y. is |

| | |
|---|---|
| | indicated if the longest and shortest intervals are not considered. The three most recent faulting events can be reconstructed from relationships in the highest trench and yielded ages of about 24 ka (0.4 m vertical displacement), 40–45 ka (0.35 m vertical displacement), and 75–80 ka (< 3.5 m vertical displacement). The earlier investigation by Machette (1978 #1402) provided average recurrence intervals of 90–190 ka because fewer faulting events were identified. |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Low slip-rate category assigned based on vertical-displacement rates from trenching at site 2038-2 described in McCalpin and others (2006 #6931), who suggest the vertical-displacement rate has not been constant over the past 1.6 m.y. However, the long-term and short-term (from the past two earthquakes) vertical-displacement rates are similar. Vertical-displacement rate for the County Dump fault at the Bernalillo County landfill can be constrained by the 24 m of far-field surface offset and the estimated 1–1.6 Ma age of the Llano de Albuquerque, resulting in a possible range in vertical-displacement rate of 0.015–0.024 mm/yr (McCalpin and others, 2006 #6931). The vertical-displacement rate would be lower and better constrained if the age for the Llano based on Connell and others (2013 #7235) were considered. McCalpin and others (2006 #6931) present a similar short-term vertical rate of 0.018 mm/yr based on cumulative offset in the past two earthquakes of 0.75 m. |
| **Date and Compiler(s)** | 2015<br>Kathleen M. Haller, U.S. Geological Survey<br>Stephen F. Personius, U.S. Geological Survey<br>Susan S. Olig, URS Corporation<br>James P. McCalpin, GEO-HAZ Consulting, Inc. |
| **References** | #1288 Bryan, K., and McCann, F.T., 1937, The Ceja del Rio Puerco—A border feature of the Basin and Range province in New Mexico, Part I, Stratigraphy and structure: Journal of Geology, v. 45, p. 801-828.<br><br>#1763 Cather, S.M., Connell, S.D., Heynekamp, M.R., and Goodwin, L.B., 1997, Geology of the Arroyo de las Calabacillas [Sky Village SE] 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 9, 8 p. pamphlet, 1 sheet, scale 1:24,000.<br><br>#7235 Connell, S.D., Smith, G.A., Geissman, J.W., and McIntosh, W.C., 2013, Climatic controls on nonmarine depositional sequences in the Albuquerque Basin, Rio Grande rift, north-central New Mexico, in Hudson, M.R., and Grauch, V.J.S., eds., New perspectives on Rio Grande rift basins—From tectonics to groundwater: Geological Society of America Special Paper 494, p. 383–425, doi:10.1130/2013.2494(15)<br><br>#1297 Geissman, J.W., Brown, L., Turrin, B.D., McFadden, L.D., and Harlan, S.S., 1990, Brunhes chron excursion/polarity episode recorded during the late Pleistocene, Albuquerque Volcanoes, |

New Mexico, USA: Geophysical Journal International, v. 102, p. 73-88.<br><br>#1721 Grauch, V.J.S., and Millegan, P.S., 1998, Mapping intrabasinal faults from high-resolution aeromagnetic data: The Leading Edge, v. 17, p. 53-55.<br><br>#1304 Hawley, J.W., and Haase, C.S., compilers, 1992, Hydrogeologic framework of the northern Albuquerque basin: New Mexico Bureau of Mines and Mineral Resources Open-File Report 387, 1 pl., scale 1:100,000.<br><br>#1303 Hawley, J.W., and Whitworth, T.M., compilers, 1996, Hydrogeology of potential recharge areas for the basin- and valley-fill aquifer systems, and hydrogeochemical modeling of proposed artificial recharge of the upper Santa Fe aquifer, northern Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Report 402-D, 575 p.<br><br>#1302 Hawley, J.W., Love, D.W., Betancourt, J.L., Turner, R.M., and Tharnstrom, S., 1991, Quaternary and Neogene landscape evolution—A transect across the Colorado Plateau and Basin and Range provinces in west-central and central New Mexico, in Julian, B., and Zidek, J., eds., Field guide to geologic excursions in New Mexico and adjacent areas of Texas and Colorado: New Mexico Bureau of Mines and Mineral Resources Bulletin 137, p. 105-148.<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1396 Lambert, P.W., 1968, Quaternary stratigraphy of the Albuquerque area, New Mexico: Albuquerque, University of New Mexico, unpublished Ph.D. dissertation, 329 p., 3 pl., scale 1:48,000.<br><br>#1402 Machette, M.N., 1978, Dating Quaternary faults in the southwestern United States by using buried calcic paleosols: U.S. Geological Survey Journal of Research, v. 6, no. 3, p. 369-381.<br><br>#1401 Machette, M.N., 1982, Quaternary and Pliocene faults in the La Jencia and southern part of the Albuquerque-Belen basins, New Mexico—Evidence of fault history from fault-scarp morphology and Quaternary geology, in Grambling, J.A., and Wells, S.G., eds., Albuquerque Country II: New Mexico Geological Society, 33rd Field Conference, November 4-6, 1982, Guidebook, p. 161-169.<br><br>#1767 McCalpin, J.P., 1997, Paleoseismicity of Quaternary faults near Albuquerque, New Mexico: Technical report to U.S. Geological Survey, under Contract 1434-HQ-96-GR-02751, 18 p.<br><br>#6931 McCalpin, J.P., Olig, S.S., Harrison, J.B.J., and Berger, G.W., 2006, Quaternary faulting and soil formation on the County Dump fault, Albuquerque, New Mexico: New Mexico Bureau of Geology and Mineral Resources Circular 212, 36 p.<br><br>#1411 Peate, D.W., Chen, J.H., Wasserburg, G.J., Papanastassiou, D.A., and Geissman, J.W., 1996, 238U-230Th dating of a geomagnetic excursion in Quaternary basalts of the Albuquerque Volcanoes Field, New Mexico (USA): Geophysical Research Letters, v. 23, p. 2271-2274.<br><br>#1722 U.S. Geological Survey, and SIAL Geosciences, Inc., 1997, Description of digital aeromagnetic data collected north and west of Albuquerque, New Mexico: U.S. Geological Survey Open-File Report 97-286, 40 p.

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Coyote Springs fault (Class A) No. 2114

**Last Review Date: 2016-03-30**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Personius, S.F., and Jochems, A.P., compilers, 2016, Fault number 2114, Coyote Springs fault, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:20 AM.**

| | |
|---|---|
| **Synopsis** | The Coyote Springs fault (and the Santa Fe [2123] and Loma Pelada [2113] faults to the north and south, respectively) form the active southwestern margin of the Rio Grande rift. Specifically, the Coyote Springs fault forms the southwestern margin of the Belen sub-basin of the Albuquerque basin. Offsets of 12–15 m in lower and middle Pleistocene deposits and 1–3 m in upper Pleistocene deposits indicate recurrent Quaternary movement along the Coyote Springs fault. At its southern end, clear evidence of Quaternary faulting dies out at Mariano Draw, and at its northern end, fault scarps die out about 5 km north of Arroyo Monte Largo. |
| **Name comments** | Originally named the Coyote fault by Kelley (1977 #1106), this fault was renamed the Coyote Springs fault by Machette (1982 #1401) and Machette and McGimsey (1983 #1024), after Coyote Spring, which is located near the southwest corner of the Comanche Ranch 7.5-minute quadrangle. The fault is still referred to as the Coyote fault in places (e.g., Grauch and Connell, 2013 #7268), but it should not be confused with the Coyote fault [2128] that forms the western boundary of the Manzanita Mountains on the southeast side of the Belen sub-basin (Personius and others, 1999 #6930). Thus, we retain the name Coyote Springs fault. The fault extends from the southern end of the |

| | |
|---|---|
| | Santa Fe fault [2123] to the northern end of the Loma Pelada fault [2113] along the northeastern margin of the Sierra Ladrones.<br><br>**Fault ID:** Fault no. 6 of Machette (1982 #1401), fault no. 5 of Machette and McGimsey (1983 #1024). |
| **County(s) and State(s)** | VALENCIA COUNTY, NEW MEXICO <br>SOCORRO COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | BASIN AND RANGE <br> |
| **Reliability of location** | Good<br>Compiled at 1:250,000 scale.<br><br>*Comments:* Fault traces from Machette and McGimsey (1983 #1024) at1:250,00 scale on topographic base map. <P> |
| **Geologic setting** | The Coyote Springs fault forms the active southwestern margin of the Belen sub-basin of the Albuquerque basin in the Rio Grande rift (Grauch and Connell, 2013 #7268), with the apparent deactivation of the Comanche fault to the west (Kelley, 1977 #1106). Seismic reflection and 3D geophysical studies support Kelley's assumption that a shallow shelf or bench (Monte Largo bench) underlies the piedmont area between the Coyote Springs and Comanche faults (Russell and Snelson, 1994 #1186; Grauch and Connell, 2013 #7268). <P> |
| **Length (km)** | 17 km. |
| **Average strike** | N21°W |
| **Sense of movement** | Normal |
| **Dip** | 15–17° E.<br><br>*Comments:* Near the surface the fault probably has a relatively high angle (60°) dip. However, Russell and Snelson (1994 #1186) reported a very shallow dip of 15–17° E for the fault at about 5 km depth based on seismic reflection data. There is some controversy about the listric (shallow curving) nature of faults in the Albuquerque basin. <P> |

| | |
|---|---|
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | Prominent, but discontinuous (eroded) fault scarps are present on surficial deposits along the central part of the Coyote Springs fault, whereas the youngest scarps are found at the southern end of the fault. Machette (1982) and Machette and McGimsey (1983 #1024) measured offsets of 12–15 m in lower and middle Pleistocene deposits, and 1–3 m in upper Pleistocene deposits. Morphometric studies of the small scarps suggested possible early Holocene or latest Pleistocene ruptures (Machette and McGimsey, 1983 #1024). <P> |
| **Age of faulted surficial deposits** | The Coyote Springs fault offsets alluvial-fan deposits of early and middle Pleistocene age as much as 12–15 m along its northern part, and middle and late Pleistocene age along its southern part (Machette and McGimsey, 1983 #1024; Read and others, 2007 #7473). |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | latest Quaternary (<15 ka)<br><br>*Comments:* Fault scarp morphology studies by Machette and McGimsey (1983 #1024) indicate possible latest Pleistocene or early Holocene movement on the southern part of the Coyote Springs fault north of Mariano Draw. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Low slip-rate category assigned based on fault scarp data from Machette (1982 #1401) and Machette and McGimsey (1983 #1024) which indicates offsets of 1–3 m in late Pleistocene (10–150 ka) alluvium and as much as 12–15 m in middle to early Quaternary deposits. |

| | |
|---|---|
| **Date and Compiler(s)** | 2016<br>Stephen F. Personius, U.S. Geological Survey<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #7268 Grauch, V.J.S., and Connell, S.D., 2013, New perspectives on the geometry of the Albuquerque basin, Rio Grande rift, New Mexico: Insights from geophysical models of rift-fill thickness, in Hudson, M.R., and Grauch, V.J.S., eds., New perspectives on Rio Grande rift basins—From tectonics to groundwater: Geological Society of America Special Paper 494, p. 427–462, doi:10.1130/2013.2494(16).<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1401 Machette, M.N., 1982, Quaternary and Pliocene faults in the La Jencia and southern part of the Albuquerque-Belen basins, New Mexico—Evidence of fault history from fault-scarp morphology and Quaternary geology, in Grambling, J.A., and Wells, S.G., eds., Albuquerque Country II: New Mexico Geological Society, 33rd Field Conference, November 4-6, 1982, Guidebook, p. 161-169.<br><br>#1024 Machette, M.N., and McGimsey, R.G., 1983, Map of Quaternary and Pliocene faults in the Socorro and western part of the Fort Sumner 1° x 2° quadrangles, central New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-1465-A, 12 p. pamphlet, 1 sheet, scale 1:250,000.<br><br>#6930 Personius, S.F., Machette, M.N., and Kelson, K.I., 1999, Quaternary faults in the Albuquerque area—An update, in Pazzaglia, F.J., and Lucas, S.G., eds., Albuquerque geology: New Mexico Geological Society 50th Annual Field Conference, Guidebook, September 22–25, p. 189–200.<br><br>#7473 Read, A.S., Cather, S.M., Chamberlin, R.M., Connell, S.D., Hook, S.C., and Karlstrom, K.E., 2007, Preliminary geologic map of the Ladron Peak quadrangle, Socorro County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-File Geologic Map 142, scale 1:24,000.<br><br>#1186 Russell, L.R., and Snelson, S., 1994, Structure and tectonics of the Albuquerque basin segment of the Rio Grande rift—Insights from reflection seismic data, in Keller, G.R., and Cather, S.M., eds., Basins of the Rio Grande rift—Structure, stratigraphy, and tectonic setting: Geological Society of America Special Paper 291, p. 83–112. |

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Intrabasin faults on the Llano de Albuquerque (Class A) No. 2121

**Last Review Date: 2016-05-24**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Jochems, A.P., and Personius, S.F., compilers, 2016, Fault number 2121, Intrabasin faults on the Llano de Albuquerque, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:20 AM.**

| | |
|---|---|
| **Synopsis** | These faults are mostly expressed by short faults that offset the early Pleistocene Llano de Albuquerque geomorphic surface. They are collected together as a group for the express purpose of description. Most of these intrabasin faults are partly to nearly completely covered by eolian sand, but on air photographs these features are marked by linear scarps, aligned drainages, and in some cases aligned ephemeral ponds. Quaternary displacement is unknown for most of these faults, but a few have scarps up to 3–12 m high. Some of these faults may be related to volcanic activity, such as those associated with the Wind Mesa and Los Lunas volcanic centers. |
| **Name comments** | This group of north-trending normal faults forms a series of horsts and grabens on the Llano de Albuquerque, west of Albuquerque. A thick cover of eolian sand covers most of the Llano de Albuquerque, which has led to varying orientations and configurations of mapped faults in this area (Kelley, 1977 #1106; Kelley and Kudo, 1978 #1307; Machette, 1982 #1401; Machette and McGimsey, 1983 #1024; Hawley and Haase, 1992 #1304; Wong and others, 1995 #1155; Hawley and Whitworth, 1996 #1303; Shroba and others, 2003 #7459; Thompson and others, 2009 #7460). Named faults include several strands of the West Mesa and Cat Mesa [2122] fault zones (Wong and others, |

| | |
|---|---|
| | 1995 #1155; Hawley and Whitworth, 1996 #1303), the Atrisco fault (Hawley and Haase, 1992 #1304), and the Lost Horizon and Wind Mesa faults (Connell, 2008 #7454). We exclude all but the Cat Mesa fault [2122] as specific fault names until more detailed mapping and fault studies are conducted. |
| **County(s) and State(s)** | SANDOVAL COUNTY, NEW MEXICO <br>SOCORRO COUNTY, NEW MEXICO <br>BERNALILLO COUNTY, NEW MEXICO <br>VALENCIA COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | BASIN AND RANGE <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Fault traces compiled from 1:24,000-scale mapping of Love and others (1998 #7457), Maldonado and Atencio (1998 #1777, 1998 #1778), Love (1999 #7456), Maldonado, 2003 (#7453), Rawling (2003 #7458), Shroba and others (2003 #7459), McCraw and others (2006 #7255), and Thompson and others (2009 #7460). Additional traces from unpublished 1:24,000-scale mapping of Isleta 7.5-minute quadrangle by Love and others and 1:50,000-scale mapping of Albuquerque metropolitan area by Connell (2008 #7454). All traces compiled digitally and accurately placed using photogrammetric methods. Original fault traces digitized from Machette and McGimsey (1983 #1024) with supplemental geophysical data from Grauch and Millegan (1998 #1721) and U.S. Geological Survey and SIAL Geosciences Inc. (1997 #1722). The area is covered by thick sequences of eolian sand, so most fault strands are subdued and others may be obscured. <P> |
| **Geologic setting** | This group of intrabasin faults forms a broad zone within the Albuquerque-Belen basin of the Rio Grande rift. <P> |
| **Length (km)** | 101 km. |
| **Average strike** | N3°E |
| **Sense of movement** | Normal |
| **Dip Direction** | E; W |

| | |
|---|---|
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | These faults are marked by subdued, discontinuously exposed, mostly sand covered scarps on the Llano de Albuquerque. East of El Rincon (an erosional embayment into the Llano), these structures form an anastomosing group of horsts and grabens that are marked by linear scarps, aligned drainages, and aligned ephemeral ponds (Shroba and others, 2003 #7459; Connell, 2008 #7454; Thompson and others, 2009 #7460). Some of the down-to-the-west faults have linear ponds along their bases, apparently caused by damming of the prevailing east-southeast-flowing drainages. Machette and McGimsey (1983 #1024) measured offsets of 3–12 m on some of these faults on the Llano de Albuquerque. Included in this dataset are buried faults delineated from high-resolution aeromagnetic data (U.S. Geological Survey and SIAL Geosciences Inc., 1997 #1722; Grauch and Millegan, 1998 #1721; Grauch, 1999 #7241). Most of these faults are buried only by a thin (less than 10 m) cover of eolian sediment and probably cut deposits and soils associated with Llano de Albuquerque (Shroba and others, 2003 #7459; Thompson and others, 2009 #7460). However, it is possible that some do not cut post-Pliocene strata. <P> |
| **Age of faulted surficial deposits** | These faults offset the early Pleistocene Llano de Albuquerque. This diachronous surface overlies deposits spanning the interval from approximately 1.8–0.8 Ma (Connell and others, 2000 #7455; Connell and others, 2013 #7235). |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | middle and late Quaternary (<750 ka)<br><br>*Comments:* Some of these faults offset the early Pleistocene Llano de Albuquerque surface as much as 12 m (Machette and McGimsey, 1983 #1024); these data indicate a recurrent history of faulting that in some cases probably extended at least into the middle Pleistocene following abandonment of the Llano de Albuquerque surface. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr |

| | |
|---|---|
| | *Comments:* Low slip-rate category assigned based on offsets of 3–12 m of the early Pleistocene (~1.8-0.8 Ma) Llano de Albuquerque (Machette and McGimsey, 1983 #1024; Connell and others, 2013 #7235). |
| **Date and Compiler(s)** | 2016<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources<br>Stephen F. Personius, U.S. Geological Survey |
| **References** | #7454 Connell, S.D., 2008, Geologic map of the Albuquerque-Rio Rancho metropolitan area and vicinity, Bernalillo and Sandoval Counties, New Mexico: New Mexico Bureau of Geology and Mineral Resources Geologic Map 78, scale 1:50,000.<br><br>#7455 Connell, S.D., Love, D.W., Maldonado, F., Jackson, P.B., McIntosh, W.C., and Eppes, M.C., 2000, Is the top of the Santa Fe Group diachronous in the Albuquerque Basin? [abs.], in Cole, J.C., ed., Middle Rio Grande basin study—Proceedings of the Fourth Annual Workshop, Albuquerque, New Mexico, February 15–16, 2000: U.S. Geological Survey Open-File Report 00-488, p. 18–20.<br><br>#7235 Connell, S.D., Smith, G.A., Geissman, J.W., and McIntosh, W.C., 2013, Climatic controls on nonmarine depositional sequences in the Albuquerque Basin, Rio Grande rift, north-central New Mexico, in Hudson, M.R., and Grauch, V.J.S., eds., New perspectives on Rio Grande rift basins—From tectonics to groundwater: Geological Society of America Special Paper 494, p. 383–425, doi:10.1130/2013.2494(15)<br><br>#7241 Grauch, V.J.S., 1999, Principal features of high resolution aeromagnetic data collected near Albuquerque, New Mexico, in Pazzaglia, F.J., and Lucas, S.G., eds., Albuquerque Geology: New Mexico Geological Society Guidebook 50, p. 115–118.<br><br>#1721 Grauch, V.J.S., and Millegan, P.S., 1998, Mapping intrabasinal faults from high-resolution aeromagnetic data: The Leading Edge, v. 17, p. 53-55.<br><br>#1304 Hawley, J.W., and Haase, C.S., compilers, 1992, Hydrogeologic framework of the northern Albuquerque basin: New Mexico Bureau of Mines and Mineral Resources Open-File Report 387, 1 pl., scale 1:100,000.<br><br>#1303 Hawley, J.W., and Whitworth, T.M., compilers, 1996, Hydrogeology of potential recharge areas for the basin- and valley-fill aquifer systems, and hydrogeochemical modeling of proposed artificial recharge of the upper Santa Fe aquifer, northern Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Report 402-D, 575 p.<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1307 Kelley, V.C., and Kudo, A.M., 1978, Volcanoes and related basalts of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Circular 156, 29 p., 2 pls.<br><br>#7456 Love, D.W., 1999, Geologic map of the Veguita 7.5-minute quadrangle, Valencia and Socorro Counties, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 28, scale 1:24,000.<br><br>#7457 Love, D.W., Maldonado, F., Hallett, B., Panter, K., Reynolds, C., McIntosh, W., and Dunbar, N., 1998, Geology of the Dalies 7.5-minute quadrangle, Bernalillo and |

Valencia Counties, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 21, scale 1:24,000.<br><br>#1401 Machette, M.N., 1982, Quaternary and Pliocene faults in the La Jencia and southern part of the Albuquerque-Belen basins, New Mexico—Evidence of fault history from fault-scarp morphology and Quaternary geology, in Grambling, J.A., and Wells, S.G., eds., Albuquerque Country II: New Mexico Geological Society, 33rd Field Conference, November 4-6, 1982, Guidebook, p. 161-169.<br><br>#1024 Machette, M.N., and McGimsey, R.G., 1983, Map of Quaternary and Pliocene faults in the Socorro and western part of the Fort Sumner 1° x 2° quadrangles, central New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-1465-A, 12 p. pamphlet, 1 sheet, scale 1:250,000.<br><br>#7453 Maldonado, F., 2003, Geologic map of the Rio Puerco quadrangle, Bernalillo and Valencia Counties, New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-2397, scale 1:24,000.<br><br>#1777 Maldonado, F., and Atencio, A., 1998, Preliminary geologic map of the Wind Mesa quadrangle, Bernalillo County, New Mexico: U.S. Geological Survey Open-File Report 97-740, 1 sheet, scale 1:24,000.<br><br>#1778 Maldonado, F., and Atencio, A., 1998, Preliminary geologic map of the Dalies northwest quadrangle, Bernalillo County, New Mexico: U.S. Geological Survey Open-File Report 97-741, 1 sheet, scale 1:24000.<br><br>#7255 McCraw, D.J., Love, D.W., and Connell, S.D., 2006, Geologic map of the Abeytas quadrangle, Socorro County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-File Geologic Map 121, scale 1:24,000.<br><br>#7458 Rawling, G.C., 2003, Geologic map of the Belen 7.5-minute quadrangle, Valencia County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-File Geologic Map 80, scale 1:24,000.<br><br>#7459 Shroba, R.R., Thompson, R.A., Schmidt, D.L., Personius, S.F., Maldonado, F., and Brandt, T.R., 2003, Geologic map of the La Mesita Negra SE quadrangle, Bernalillo County, New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-2416, scale 1:24,000.<br><br>#7460 Thompson, R.A., Shroba, R.R., Menges, C., Schmidt, D.L., Personius, S.F., and Brandt, T.R., 2009, Geologic map of the Volcanoes quadrangle, Bernalillo and Sandoval Counties, New Mexico: U.S. Geological Survey Scientific Investigations Map SIM-3083, scale 1:24,000.<br><br>#1722 U.S. Geological Survey, and SIAL Geosciences, Inc., 1997, Description of digital aeromagnetic data collected north and west of Albuquerque, New Mexico: U.S. Geological Survey Open-File Report 97-286, 40 p.<br><br>#1155 Wong, I., Kelson, K., Olig, S., Kolbe, T., Hemphill-Haley, M., Bott, J., Green, R., Kanakari, H., Sawyer, J., Silva, W., Stark, C., Haraden, C., Fenton, C., Unruh, J., Gardner, J., Reneau, S., and House, L., 1995, Seismic hazards evaluation of the Los Alamos National Laboratory: Technical report to Los Alamos National Laboratory, Los Alamos, New Mexico, February 24, 1995, 3 volumes, 12 pls., 16 appen.

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Jemez-San Ysidro fault, Calabacillas section (Class A) No. 2029c

**Last Review Date: 2015-02-20**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Koning, D.J., Haller, K.M., and Jochems, A.P., compilers, 2015, Fault number 2029c, Jemez-San Ysidro fault, Calabacillas section, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:21 AM.**

| | |
|---|---|
| **Synopsis** | **General:** The Jemez-San Ysidro fault is a steeply east-dipping normal fault that, in part, forms the active western margin of the Rio Grande rift south of the Valles caldera. The fault is divided into sections on the basis of a 45° change in fault strike at the latitude of Cañones and evidence for young (Holocene) rupture along its southern section. The northern, northeast-striking section of the fault (Jemez section) is aligned with northeast-striking faults within the collapsed center of the Valles caldera and the Embudo fault, and is coincident with the Jemez Lineament. The central fault (San Ysidro section) merges with the southern fault (Calabacillas section) about 7 km south of the town of San Ysidro.<br><br>**Sections:** This fault has 3 sections. The Jemez-San Ysidro fault consists of a northeast-striking fault (the Jemez fault of Goff and Kron, 1980 #1099), and north-striking faults along the northwestern margin of the Albuquerque basin (the Jemez and San Ysidro faults of Woodward, 1987 #1130). The boundary between the northern (Jemez) and central (San Ysidro) sections is placed at the 45° change in fault strike near Cañones. The boundary between the central and southern (Calabacillas) sections is near Arroyo Piedra Parada, 7 km south of San Ysidro. These sections |

| | |
|---|---|
| | are distinguished primarily on the basis of younger demonstrated displacement on the Calabacillas section, a prominent down-to-the-east normal fault that offsets the west side of the Llano de Albuquerque along the western margin of the Rio Grande rift. |
| **Name comments** | **General:** The Jemez-San Ysidro fault extends from the latitude of the Albuquerque Volcanoes north to the southern rim of the Valles caldera near Highway 4. As used herein, the Jemez-San Ysidro fault includes the northeast-striking faults referred to as the Jemez fault zone by Goff and Kron (1980 #1099) and Goff and others (1981 #1182), the north-striking Sierrita fault of Woodward and DuChene (1975 #1131), Aldrich (1986 #1084), and Woodward (1987 #1130); the north-striking San Ysidro fault of Woodward and Ruetschilling (1976 #1133), Hawley and Galusha (1978 #1103), and Woodward (1987 #1130); and the north-striking Calabacillas fault of Bryan and McCann (1937 #1288, fig. 4), Wright (1946 #1427) and Cather and others (1997 #1763). All of these faults are grouped together herein because of lateral continuity (Wong and others, 1995 #1155; Koning and others, 1998 #7375).<br><br>**Section:** Part of the Calabacillas fault was originally mapped by Bryan and McCann (1937 #1288, fig. 4), and later described in detail by Wright (1946 #1427) in the Volcano Ranch 7.5 minute quadrangle. The fault was mapped and named in the Sky Village SE (now Arroyo de las Calabacillas) quadrangle by Cather and others (1997 #1763). Wright (1946 #1427, p. 426-428), Kelley and others (1976 #1380), and Kelley (1977 #1106) included the Calabacillas fault with the Sand Hill fault zone [2039], which is located 1–2 km to the west. However, detailed mapping indicates that the Calabacillas fault does not intersect the Sand Hill fault zone [2039] at the surface, but rather trends northeastward to the north and southeastward to the south of the exposures described by Wright (1946 #1427). At its northern end, the Calabacillas fault appears to join with the San Ysidro section near Arroyo Piedra Parada (Woodward and Ruetschilling, 1976 #1133; Koning and others, 1998 #7375). Connell (2008 #7454) and Grauch and Connell (2013 #7268) use the name San Ysidro fault for the entire fault zone south of the Rio Jemez, including all of what herein is named the Calabacillas section. |
| **County(s) and State(s)** | BERNALILLO COUNTY, NEW MEXICO <br>SANDOVAL COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | BASIN AND RANGE <br>COLORADO PLATEAUS <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale. |

| | |
|---|---|
| | *Comments:* The location of the fault is compiled from 1:24,000-scale mapping of the Cerro Conejo (previously Sky Village NE) quadrangle (Koning and others, 1998 #7375), the Arroyo de las Calabacillas (previously Sky Village SE) quadrangle (Cather and others, 1997 #1763), and the Volcanoes (previously Volcano Ranch) quadrangle (Thompson and others, 2009 #7460). The fault location is also evident in high-resolution aeromagnetic data (U.S. Geological Survey and SIAL Geosciences Inc., 1997 #1722; Grauch and Millegan, 1998 #1721) <P> |
| **Geologic setting** | The Jemez-San Ysidro fault forms the northwestern margin of the Albuquerque basin, although the amount of Quaternary vertical separation is less than that along other rift-margin faults. Aldrich (1986 #1084) stated that the fault was the western margin of the Rio Grande rift during the Oligocene, and that activity later stepped eastward to the Pajarito fault zone [2008]. Wong and others (1995 #1155) and House and Hartse (1995 #1160) identified seismicity aligned along the northern part of the fault. <P> |
| **Length (km)** | This section is 34 km of a total fault length of 92 km. |
| **Average strike** | N2°W (for section) versus N14°E (for whole fault) |
| **Sense of movement** | Normal |
| **Dip** | 60° E to near vertical<br><br>*Comments:* Dip measurement from Wright (1946 #1427, plate 8). McCalpin and others (2011 #7183) depict an exposure of the near-vertical main fault in a trench near the southern end of the fault. <P> |
| **Paleoseismology studies** | Site 2029-1. Two trenches were excavated 3 km north of the southern end of the fault (McCalpin and others, 2011 #7183). In the eastern trench, across a 5.3-m-high antithetic scarp, details of faulting are overprinted by stage IV soil carbonate that engulfs 4.5 m of exposed section, which bottoms in the Pliocene–Pleistocene (?) Santa Fe Group. McCalpin and others (2011 #7183) could distinguish five major depositional units, but the section was not sampled for dating. The western 60-m-long trench crosses a 27-m-high down-to-the-east fault scarp. The trench exposes Santa Fe Group only in the bottom of the exposed footwall. The interpretation of four prehistorical surface-faulting earthquakes is derived from observed vertical displacement of correlated buried soils and the six infrared-stimulated luminescence (IRSL) dates that are in correct stratigraphic order, substantiated by two fine-silt thermoluminescence (TL) ages, ranging from 14 ka to 219 ka. The IRSL dates were used to constrain the mean rate |

| | |
|---|---|
| | of secondary-carbonate accumulation in the soils to estimate the timing of the four surface ruptures interpreted at the site. <P> |
| **Geomorphic expression** | The Calabacillas fault forms broad, dissected fault scarps across the Llano de Albuquerque and is exposed in upper Santa Fe Group sediments at several locations where it crosses the Ceja del Rio Puerco. The northeast-trending part of the fault zone was mapped by Kelley and others (1976 #1380), Kelley (1977 #1106), Cather and others (1997 #1763), and Koning and others (1998 #7375); this northeast-striking part is marked by scattered displaced pediment remnants across the dissected surface of the Llano de Albuquerque. Wright (1946 #1427) reports 45-m-high scarps on the Llano; McCalpin and others (2011 #7183) describe the broad fault scarps as being 10–30 m high and having surface angles typically less than 5 degrees. <P> |
| **Age of faulted surficial deposits** | Kelley (1977 #1106) described minor offsets of pediment remnants on the northeast-trending section of the fault north of the Ceja del Rio Puerco exposures. The ages of these offset deposits are unknown, but they concluded that most are probably early and middle (?) Pleistocene in age. McCalpin and others (2011 #7183) reported displacement of buried soils dated to the middle and late Pleistocene. |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | latest Quaternary (<15 ka)<br><br>*Comments:* Based on trenching near the southern end of the fault, the most recent surface rupture occurred 14 k.y. ago (McCalpin and others, 2011 #7183). This age is assigned to the entire length of the fault, which is supported by the nine post-Llano de Albuquerque fault-scarp-derived colluvial and soil deposits adjacent to this structure described by Machette (1978 #1402) and Machette and others (1997 #1403). <P> |
| **Recurrence interval** | 9–20 k.y. (<55ka)<br><br>*Comments:* Based on six infrared-stimulated luminescence (IRSL) dates and one soil calcium-carbonate date, the timing of the most recent four surface-faulting events on the southern part of the fault is 14 ka, 23 ka, 35 ka, and 55 ka (McCalpin and others, 2011 #7183). The last four surface-rupturing earthquakes are not evenly spaced in time and individual recurrence intervals are between 9 k.y. and 20 k.y. McCalpin and others (2011 #7183) suggest that activity on the rift-bounding faults alternates and the east-dipping faults have been more active from the middle |

| | |
|---|---|
| | Pleistocene to present than the west-dipping faults. Soils developed on the colluvial wedges in the Ceja del Rio Puerco exposures also have extensive carbonate development (Machette and others, 1997 #1403), which indicates that a substantial amount of time is recorded in these deposits. |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* McCalpin and others (2011 #7183) report a long-term vertical-displacement rate of 0.027–0.054 mm/yr based on the 27-m-high scarp on the Llano de Albuquerque surface, assumed to be 0.5–1 Ma. Later work by Connell and others (2013 #7235) indicated that the Llano de Albuquerque surface is 0.8-1.8 Ma, which would decrease these long-term vertical-displacement rates. McCalpin and others (2011 #7183) further report vertical-displacement rates derived from each of the four recent earthquakes, which range from 0.011 to 0.028 mm/yr; although they acknowledge that vertical displacement at this site is likely smaller than that to the north. Displacement on the nearby antithetic fault (5.3 m) is not reported or removed from the vertical displacement referenced above; therefore, the reported vertical-displacement rates include maximum displacement for each event at this site. At a different location, Wright (1946 #1427) described about 45 m of accumulated fault-derived colluvial deposits on the downthrown block. All of these data suggest the Calabacillas section deforms at a rate lower than 0.2 mm/yr. |
| **Date and Compiler(s)** | 2015<br>Daniel J. Koning, New Mexico Bureau of Geology & Mineral Resources<br>Kathleen M. Haller, U.S. Geological Survey<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #1084 Aldrich, M.J., Jr., 1986, Tectonics of the Jemez lineament in the Jemez Mountains and Rio Grande rift: Journal of Geophysical Research, v. 91, no. B2, p. 1753–1762.<br><br>#1288 Bryan, K., and McCann, F.T., 1937, The Ceja del Rio Puerco—A border feature of the Basin and Range province in New Mexico, Part I, Stratigraphy and structure: Journal of Geology, v. 45, p. 801-828.<br><br>#1763 Cather, S.M., Connell, S.D., Heynekamp, M.R., and Goodwin, L.B., 1997, Geology of the Arroyo de las Calabacillas [Sky Village SE] 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 9, 8 p. pamphlet, 1 sheet, scale 1:24,000.<br><br>#7239 Connell, S.D., 2001, Stratigraphy of the Albuquerque basin, Rio Grande rift, central New Mexico—A progress report, in Connell, S.D., and 8 others, Stratigraphy and tectonic development of the Albuquerque basin, central Rio Grande rift—Field trip guidebook for the Geological Society of America, Rocky Mountain–South-Central Section Meeting, Albuquerque, New Mexico: New Mexico Bureau of Mines & Mineral Resources Open-File Report 454B, p. A-1–A-26.<br><br>#7454 Connell, S.D., 2008, Geologic map of the |

Albuquerque-Rio Rancho metropolitan area and vicinity, Bernalillo and Sandoval Counties, New Mexico: New Mexico Bureau of Geology and Mineral Resources Geologic Map 78, scale 1:50,000.<br><br>#7235 Connell, S.D., Smith, G.A., Geissman, J.W., and McIntosh, W.C., 2013, Climatic controls on nonmarine depositional sequences in the Albuquerque Basin, Rio Grande rift, north-central New Mexico, in Hudson, M.R., and Grauch, V.J.S., eds., New perspectives on Rio Grande rift basins—From tectonics to groundwater: Geological Society of America Special Paper 494, p. 383–425, doi:10.1130/2013.2494(15)<br><br>#1099 Goff, F., and Kron, A., 1980, In-progress geologic map of Canon de San Diego, Jemez Springs, New Mexico, and lithologic log of Jemez Springs geothermal well: Los Alamos Scientific Laboratory Report LA-8276-MAP, 1 sheet, scale 1:12,000.<br><br>#1182 Goff, F.E., Grigsby, C.O., Trujillo, P.E., Jr., Counce, D., and Kron, A., 1981, Geology, water chemistry and geothermal potential of the Jemez Springs area, Canon de San Diego, New Mexico: Journal of Volcanology and Geothermal Research, v. 10, p. 227-244.<br><br>#7268 Grauch, V.J.S., and Connell, S.D., 2013, New perspectives on the geometry of the Albuquerque basin, Rio Grande rift, New Mexico: Insights from geophysical models of rift-fill thickness, in Hudson, M.R., and Grauch, V.J.S., eds., New perspectives on Rio Grande rift basins—From tectonics to groundwater: Geological Society of America Special Paper 494, p. 427–462, doi:10.1130/2013.2494(16).<br><br>#1721 Grauch, V.J.S., and Millegan, P.S., 1998, Mapping intrabasinal faults from high-resolution aeromagnetic data: The Leading Edge, v. 17, p. 53-55.<br><br>#1103 Hawley, J.W., and Galusha, T., 1978, Southern rift guide 2, Socorro-Santa Fe, New Mexico—Bernalillo to south of San Ysidro, in Hawley, J.W., ed., Guide to Rio Grande rift in New Mexico and Colorado: New Mexico Bureau of Mines and Mineral Resources Circular 163, p. 177-183.<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1380 Kelley, V.C., Woodward, L.A., Kudo, A.M., and Callender, J.F., 1976, Guidebook to Albuquerque basin of the Rio Grande rift, New Mexico: New Mexico Bureau of Mines and Mineral Resources Circular 153, 31 p.<br><br>#7375 Koning, D.J., Pederson, J., Pazzaglia, F.J., and Cather, S.M., 1998, Geology of the Cerro Conejo (Sky Village NE) 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-file Geologic Map 45, scale 1:24,000.<br><br>#1402 Machette, M.N., 1978, Dating Quaternary faults in the southwestern United States by using buried calcic paleosols: U.S. Geological Survey Journal of Research, v. 6, no. 3, p. 369-381.<br><br>#1403 Machette, M.N., Long, T., Bachman, G.O., and Timbel, N.R., 1997, Laboratory data for calcic soils in central New Mexico—Background information for mapping Quaternary deposits in the Albuquerque basin: New Mexico Bureau of Mines and Mineral Resources Circular 205, 63 p.<br><br>#7183 McCalpin, J.P., Harrison, J.B.J., Berger, G.W., and Tobin, H.C., 2011, Paleoseismicity of a low-slip-rate normal fault in the Rio Grande rift, USA—The Calabacillas fault, Albuquerque, New Mexico, in Audemard M., F.A., Michetti, A.M., and McCalpin, J.P., eds., Geological criteria for evaluating seismicity revisited—Forty years of paleoseismic Investigations and the natural record of past earthquakes: Geological Society of America Special Paper 479, p. 1–24,

doi:10.1130/2011.2479(01)<br><br>#7460 Thompson, R.A., Shroba, R.R., Menges, C., Schmidt, D.L., Personius, S.F., and Brandt, T.R., 2009, Geologic map of the Volcanoes quadrangle, Bernalillo and Sandoval Counties, New Mexico: U.S. Geological Survey Scientific Investigations Map SIM-3083, scale 1:24,000.<br><br>#1722 U.S. Geological Survey, and SIAL Geosciences, Inc., 1997, Description of digital aeromagnetic data collected north and west of Albuquerque, New Mexico: U.S. Geological Survey Open-File Report 97-286, 40 p.<br><br>#1155 Wong, I., Kelson, K., Olig, S., Kolbe, T., Hemphill-Haley, M., Bott, J., Green, R., Kanakari, H., Sawyer, J., Silva, W., Stark, C., Haraden, C., Fenton, C., Unruh, J., Gardner, J., Reneau, S., and House, L., 1995, Seismic hazards evaluation of the Los Alamos National Laboratory: Technical report to Los Alamos National Laboratory, Los Alamos, New Mexico, February 24, 1995, 3 volumes, 12 pls., 16 appen.<br><br>#1130 Woodward, L.A., 1987, Geology and mineral resources of Sierra Nacimiento and vicinity, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 42, 84 p., 1 pl., scale 1:100,000.<br><br>#1131 Woodward, L.A., and DuChene, H.R., 1975, Geometry of the Sierrita fault and its bearing on tectonic development of the Rio Grande rift, New Mexico: Geology, v. 3, p. 114–116.<br><br>#1133 Woodward, L.A., and Ruetschilling, R.L., 1976, Geology of San Ysidro quadrangle, New Mexico: New Mexico Bureau of Mines and Mineral Resources Geologic Map 37, 1 sheet, scale 1:24,000.<br><br>#1427 Wright, H.E., Jr., 1946, Tertiary and Quaternary geology of the lower Rio Puerco area, New Mexico: Geological Society of America Bulletin, v. 57, p. 383-456.

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Jemez-San Ysidro fault, Jemez section (Class A) No. 2029a

**Last Review Date: 2016-06-26**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Jochems, A.P., Kelson, K.I., and Personius, S.F., compilers, 2016, Fault number 2029a, Jemez-San Ysidro fault, Jemez section, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:21 AM.**

**Synopsis**

**General:** The Jemez-San Ysidro fault is a steeply east-dipping normal fault that, in part, forms the active western margin of the Rio Grande rift south of the Valles caldera. The fault is divided into sections on the basis of a 45° change in fault strike at the latitude of Cañones and evidence for young (Holocene) rupture along its southern section. The northern, northeast-striking section of the fault (Jemez section) is aligned with northeast-striking faults within the collapsed center of the Valles caldera and the Embudo fault, and is coincident with the Jemez Lineament. The central fault (San Ysidro section) merges with the southern fault (Calabacillas section) about 7 km south of the town of San Ysidro.

**Sections:** This fault has 3 sections. The Jemez-San Ysidro fault consists of a northeast-striking fault (the Jemez fault of Goff and Kron, 1980 #1099), and north-striking faults along the northwestern margin of the Albuquerque basin (the Jemez and San Ysidro faults of Woodward, 1987 #1130). The boundary between the northern (Jemez) and central (San Ysidro) sections is placed at the 45° change in fault strike near Cañones. The boundary between the central and southern (Calabacillas) sections is near Arroyo Piedra Parada, 7 km south of San Ysidro. These sections are distinguished primarily on the basis of younger demonstrated displacement on the Calabacillas section, a

| | |
|---|---|
| | prominent down-to-the-east normal fault that offsets the west side of the Llano de Albuquerque along the western margin of the Rio Grande rift. |
| **Name comments** | **General:** The Jemez-San Ysidro fault extends from the latitude of the Albuquerque Volcanoes north to the southern rim of the Valles caldera near Highway 4. As used herein, the Jemez-San Ysidro fault includes the northeast-striking faults referred to as the Jemez fault zone by Goff and Kron (1980 #1099) and Goff and others (1981 #1182), the north-striking Sierrita fault of Woodward and DuChene (1975 #1131), Aldrich (1986 #1084), and Woodward (1987 #1130); the north-striking San Ysidro fault of Woodward and Ruetschilling (1976 #1133), Hawley and Galusha (1978 #1103), and Woodward (1987 #1130); and the north-striking Calabacillas fault of Bryan and McCann (1937 #1288, fig. 4), Wright (1946 #1427) and Cather and others (1997 #1763). All of these faults are grouped together herein because of lateral continuity (Wong and others, 1995 #1155; Koning and others, 1998 #7375).<br><br>**Section:** This part of the Jemez-San Ysidro fault was named the Jemez section by Wong and others (1995 #1155). The section extends from Highway 4 near Jemez Falls in the Jemez Mountains, southwest to Crow Springs, about 5 km west of Cañones. Smith (2004 #7529) connected this fault with the Cañones fault [2003]. |
| **County(s) and State(s)** | SANDOVAL COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | SOUTHERN ROCKY MOUNTAINS <br>COLORADO PLATEAUS <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Detailed geologic maps are available at a scale of 1:24,000 along the entire Jemez fault (Woodward and others, 1977 #1132), which was originally compiled and synthesized by Woodward (1987 #1130). More recent 1:24,000-scale maps include those of Osburn and others (2002 #7528) and Kelley and others (2003 #7527). Maps of selected parts of the fault are given by Goff and Kron (1980 #1099) at a scale of 1:12,000, and by Goff and Shevenell (1987 #1476) at a scale of 1:66,667. <P> |
| **Geologic setting** | The Jemez-San Ysidro fault forms the northwestern margin of the Albuquerque basin, although the amount of Quaternary vertical separation is less than that along other rift-margin faults. Aldrich (1986 #1084) stated that the fault was the western margin of the Rio Grande rift during the Oligocene, and that activity later stepped eastward to |

| | |
|---|---|
| | the Pajarito fault zone [2008]. Wong and others (1995 #1155) and House and Hartse (1995 #1160) identified seismicity aligned along the northern part of the fault. <P> |
| **Length (km)** | This section is 28 km of a total fault length of 92 km. |
| **Average strike** | N41°E (for section) versus N14°E (for whole fault) |
| **Sense of movement** | Normal |
| **Dip Direction** | V<br><br>*Comments:* The Jemez fault appears to be near vertical at the surface and in the shallow subsurface based on the relatively straight traces across rugged topography. Microseismicity in the vicinity of the Jemez fault appears to be aligned along a near-vertical zone, with a slight westerly dip (L. House, unpublished data, 1993). However, as a rift-margin fault, the Jemez fault probably dips to the east (Woodward and Ruetschilling, 1976 #1133). Wong and others (1995 #1155) considered dip values of 80° W, 90°, and 80° E, without a preferred dip to constrain the fault's geometry for seismic source characterization. <P> |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | The Jemez section is marked by a prominent southeast-facing scarp across Virgin Mesa, which is underlain by the 1.2–1.3 Ma Tshirege Member of the Bandelier Tuff. Goff and Shevenell (1987 #1476) note a 15-m-high fault scarp on older travertine deposits near Soda Dam. <P> |
| **Age of faulted surficial deposits** | The youngest faulted bedrock is the 1.2–1.3 Ma Tshirege Member of the Bandelier Tuff. Tafoya (2012 #7530) obtained U-series ages of 210 ka and younger for calcite growth in the Jemez fault. These ages could relate to fault reactivation or infilling of younger sediment. |
| **Historic earthquake** | |
| **Most recent prehistoric** | undifferentiated Quaternary (<1.6 Ma) |

| | |
|---|---|
| **deformation** | *Comments:* The timing of the most-recent event is unknown. Prominent geomorphic expression across Virgin Mesa, displaced upper Bandelier Tuff suggest Quaternary deformation (Wong and others, 1995 #1155). Tafoya's (2012 #7530) U-series ages (<210 ka) on calcite growth in the Jemez fault allow for the possibility of middle or late Quaternary activity. Alternatively, the calcite growth may reflect younger geomorphic phenomena associated with fluvial deposition and incision. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Assigned slip rate category based on 12 m of separation of 1.2–1.3 Ma Tshirege Member of the Bandelier Tuff along the Jemez fault (Woodward, 1987 #1130) and 50 m of separation of the same unit along the fault reported by Goff and Shevenell (1987 #1476) and Goff and others (1989 #1098). |
| **Date and Compiler(s)** | 2016<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources<br>Keith I. Kelson, William Lettis & Associates, Inc.<br>Stephen F. Personius, U.S. Geological Survey |
| **References** | #1084 Aldrich, M.J., Jr., 1986, Tectonics of the Jemez lineament in the Jemez Mountains and Rio Grande rift: Journal of Geophysical Research, v. 91, no. B2, p. 1753–1762.<br><br>#1288 Bryan, K., and McCann, F.T., 1937, The Ceja del Rio Puerco—A border feature of the Basin and Range province in New Mexico, Part I, Stratigraphy and structure: Journal of Geology, v. 45, p. 801-828.<br><br>#1763 Cather, S.M., Connell, S.D., Heynekamp, M.R., and Goodwin, L.B., 1997, Geology of the Arroyo de las Calabacillas [Sky Village SE] 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 9, 8 p. pamphlet, 1 sheet, scale 1:24,000.<br><br>#1099 Goff, F., and Kron, A., 1980, In-progress geologic map of Canon de San Diego, Jemez Springs, New Mexico, and lithologic log of Jemez Springs geothermal well: Los Alamos Scientific Laboratory Report LA-8276-MAP, 1 sheet, scale 1:12,000.<br><br>#1476 Goff, F., and Shevenell, L., 1987, Travertine deposits of Soda Dam, New Mexico, and their implications for the age and evolution of the Valles caldera hydrothermal system: Geological Society of America Bulletin, v. 99, p. 292-302.<br><br>#1182 Goff, F.E., Grigsby, C.O., Trujillo, P.E., Jr., Counce, D., and Kron, A., 1981, Geology, water chemistry and geothermal potential of the Jemez Springs area, Canon de San Diego, New Mexico: Journal of Volcanology and Geothermal Research, v. 10, p. 227-244.<br><br>#1098 Goff, F., Gardner, J.N., Baldridge, W.S., Hulen, J.B., Nielson, D.L., Vaniman, D., Heiken, G., Dungan, M.A., |

and Broxton, D., 1989, Excursion 17B—Volcanic and hydrothermal evolution of Valles Caldera and Jemez volcanic field, in Chapin, C.E., and Zidek, J., eds., Field excursions to volcanic terranes in the Western United States, v. I, Southern Rocky Mountain region: New Mexico Bureau of Mines and Mineral Resources Memoir 46, p. 381-433.<br><br>#1103 Hawley, J.W., and Galusha, T., 1978, Southern rift guide 2, Socorro-Santa Fe, New Mexico—Bernalillo to south of San Ysidro, in Hawley, J.W., ed., Guide to Rio Grande rift in New Mexico and Colorado: New Mexico Bureau of Mines and Mineral Resources Circular 163, p. 177-183.<br><br>#1160 House, L., and Hartse, H., 1995, Seismicity and faults in northern New Mexico, in Bauer, P.W., Kues, B.S., Dunbar, N.W., Karlstrom, K.E., and Harrison, B., eds., Geology of the Santa Fe region, New Mexico: New Mexico Geological Society, 46th Field Conference, September 27-30, 1995, Guidebook, p. 135–137.<br><br>#7527 Kelley, S., Kempter, K.A., Goff, F., Rampey, M., Osburn, B., and Ferguson, C.A., 2003, Geologic map of the Jemez Springs 7.5-minute quadrangle: New Mexico Bureau of Geology and Mineral Resources Open-File Geologic Map 73, scale 1:24,000.<br><br>#7375 Koning, D.J., Pederson, J., Pazzaglia, F.J., and Cather, S.M., 1998, Geology of the Cerro Conejo (Sky Village NE) 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-file Geologic Map 45, scale 1:24,000.<br><br>#7528 Osburn, G.R., Kelley, S., Rampey, M., Ferguson, C., Frankel, K., and Pazzaglia, F., 2002, Geologic map of the Ponderosa quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-File Geologic Map 57, scale 1:24,000.<br><br>#7529 Smith, G.A., 2004, Middle to late Cenozoic development of the Rio Grande rift and adjacent regions in northern New Mexico, in Mack, G.H., and Giles, K.A., eds., The geology of New Mexico—A geologic history: New Mexico Geological Society Special Publication 11, p. 311–358.<br><br>#7530 Tafoya, A.J., 2012, Uranium-series geochronology and stable isotope analysis of travertine from Soda Dam, New Mexico—A Quaternary record of episodic spring discharge and river incision in the Jemez Mountains hydrothermal system: Albuquerque, University of New Mexico, unpublished M.S. thesis, 112 p.<br><br>#1156 Wong, I., Kelson, K., Olig, S., Bott, J., Green, R., Kolbe, T., Hemphill-Haley, M., Gardner, J., Reneau, S., and Silva, W., 1996, Earthquake potential and ground shaking hazard at the Los Alamos National Laboratory, New Mexico, in Goff, F., Kues, B.S., Rogers, M.A., McFadden, L.D., and Gardner, J.N., eds., The Jemez Mountains region: New Mexico Geological Society, 47th Field Conference, September 25-28, 1996, Guidebook, p. 135–142.<br><br>#1155 Wong, I., Kelson, K., Olig, S., Kolbe, T., Hemphill-Haley, M., Bott, J., Green, R., Kanakari, H., Sawyer, J., Silva, W., Stark, C., Haraden, C., Fenton, C., Unruh, J., Gardner, J., Reneau, S., and House, L., 1995, Seismic hazards evaluation of the Los Alamos National Laboratory: Technical report to Los Alamos National Laboratory, Los Alamos, New Mexico, February 24, 1995, 3 volumes, 12 pls., 16 appen.<br><br>#1130 Woodward, L.A., 1987, Geology and mineral resources of Sierra Nacimiento and vicinity, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 42, 84 p., 1 pl., scale 1:100,000.<br><br>#1131 Woodward, L.A., and DuChene, H.R., 1975, Geometry of the Sierrita fault and its bearing on tectonic development of the Rio Grande rift, New

| | |
|---|---|
| | Mexico: Geology, v. 3, p. 114–116.<br><br>#1133 Woodward, L.A., and Ruetschilling, R.L., 1976, Geology of San Ysidro quadrangle, New Mexico: New Mexico Bureau of Mines and Mineral Resources Geologic Map 37, 1 sheet, scale 1:24,000.<br><br>#1132 Woodward, L.A., DuChene, H.R., and Martinez, R., 1977, Geology of Gilman quadrangle, New Mexico: New Mexico Bureau of Mines and Mineral Resources Geologic Map 45, scale 1:24,000.<br><br>#1427 Wright, H.E., Jr., 1946, Tertiary and Quaternary geology of the lower Rio Puerco area, New Mexico: Geological Society of America Bulletin, v. 57, p. 383-456. |

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Jemez-San Ysidro fault, San Ysidro section (Class A) No. 2029b

**Last Review Date: 2015-02-20**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Kelson, K.I., Personius, S.F., Haller, K.M., Koning, D.J., and Jochems, A.P., compilers, 2015, Fault number 2029b, Jemez-San Ysidro fault, San Ysidro section, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:21 AM.**

**Synopsis**

**General:** The Jemez-San Ysidro fault is a steeply east-dipping normal fault that, in part, forms the active western margin of the Rio Grande rift south of the Valles caldera. The fault is divided into sections on the basis of a 45° change in fault strike at the latitude of Cañones and evidence for young (Holocene) rupture along its southern section. The northern, northeast-striking section of the fault (Jemez section) is aligned with northeast-striking faults within the collapsed center of the Valles caldera and the Embudo fault, and is coincident with the Jemez Lineament. The central fault (San Ysidro section) merges with the southern fault (Calabacillas section) about 7 km south of the town of San Ysidro.

**Sections:** This fault has 3 sections. The Jemez-San Ysidro fault consists of a northeast-striking fault (the Jemez fault of Goff and Kron, 1980 #1099), and north-striking faults along the northwestern margin of the Albuquerque basin (the Jemez and San Ysidro faults of Woodward, 1987 #1130). The boundary between the northern (Jemez) and central (San Ysidro) sections is placed at the 45° change in fault strike near Cañones. The boundary between the central and southern (Calabacillas) sections is near Arroyo Piedra Parada, 7 km south of San Ysidro. These sections

| | |
|---|---|
| | are distinguished primarily on the basis of younger demonstrated displacement on the Calabacillas section, a prominent down-to-the-east normal fault that offsets the west side of the Llano de Albuquerque along the western margin of the Rio Grande rift. |
| **Name comments** | **General:** The Jemez-San Ysidro fault extends from the latitude of the Albuquerque Volcanoes north to the southern rim of the Valles caldera near Highway 4. As used herein, the Jemez-San Ysidro fault includes the northeast-striking faults referred to as the Jemez fault zone by Goff and Kron (1980 #1099) and Goff and others (1981 #1182), the north-striking Sierrita fault of Woodward and DuChene (1975 #1131), Aldrich (1986 #1084), and Woodward (1987 #1130); the north-striking San Ysidro fault of Woodward and Ruetschilling (1976 #1133), Hawley and Galusha (1978 #1103), and Woodward (1987 #1130); and the north-striking Calabacillas fault of Bryan and McCann (1937 #1288, fig. 4), Wright (1946 #1427) and Cather and others (1997 #1763). All of these faults are grouped together herein because of lateral continuity (Wong and others, 1995 #1155; Koning and others, 1998 #7375).<br><br>**Section:** This part of the Jemez-San Ysidro fault was named the San Ysidro section by Wong and others (1995 #1155). The section extends from Crow Springs, about 5 km west of Cañones on the north to near Arroyo Piedra Parada, 7 km south of San Ysidro, where it joins with the Calabacillas section (e.g., Kelley, 1977 #1106; correlation implied by fault name convention of Koning and others, 1998 #7375; Connell, 2008 #7454). |
| **County(s) and State(s)** | SANDOVAL COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | BASIN AND RANGE <br>SOUTHERN ROCKY MOUNTAINS <br>COLORADO PLATEAUS <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Detailed geologic maps at a scale of 1:24,000 are available along the entire fault trace (Woodward and Ruetschilling, 1976 #1133; 1977 #1132), which are compiled and synthesized by Woodward (1987 #1130). Formento-Trigilio (1997 #1377) and Formento-Trigilio and others (1998 #7249) mapped Quaternary deposits and faults near Jemez Pueblo and San Ysidro at 1:24,000 scale. Additional detailed mapping of parts of the fault zone can be found in Koning and others (1998 #7375), Minor and Hudson (2006 #7246), and Caine and Minor (2009 #7244). <P> |

| | |
|---|---|
| **Geologic setting** | The Jemez-San Ysidro fault forms the northwestern margin of the Albuquerque basin, although the amount of Quaternary vertical separation is less than that along other rift-margin faults. Aldrich (1986 #1084) stated that the fault was the western margin of the Rio Grande rift during the Oligocene, and that activity later stepped eastward to the Pajarito fault zone [2008]. Wong and others (1995 #1155) and House and Hartse (1995 #1160) identified seismicity aligned along the northern part of the fault. <P> |
| **Length (km)** | This section is 34 km of a total fault length of 92 km. |
| **Average strike** | N2°W (for section) versus N14°E (for whole fault) |
| **Sense of movement** | Normal<br><br>*Comments:* Woodward and DuChene (1975 #1131) characterize movement along the fault as dominantly dip-slip with a minor right-slip component. Down-to-the-east normal displacement is consistent with the occurrence of Tertiary rift-fill sediments (Zia Sand Formation) on the east faulted against Precambrian rocks on the west (Woodward, 1987 #1130). <P> |
| **Dip** | 58°–70° E.<br><br>*Comments:* Hudson and others (2008 #7245) report the fault dips eastward at 58° to 70° based on magnetic susceptibility studies. Caine and Minor (2009 #7244) report variable oblique slip along strike based on slickenline data; the variation is controlled by the geometry of the fault, which is interpreted to have an average dip of 66° to the east (Caine and Minor, 2009 #7244). Advances in interpreting fault dip from aeromagnetic expression will improve the fault's three-dimensional geometry in the future. <P> |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | Moderate geomorphic expression in bedrock is apparent on aerial photography, as a result of juxtaposition of different rock types and differential erosion. Short fault scarps and fault exposures in middle and late Pleistocene alluvial deposits have been mapped on several strands of the San Ysidro section near Jemez Pueblo and San Ysidro near the southern end of the fault (Formento-Trigilio and Pazzaglia, 1996 #1295; Formento-Trigilio, 1997 #1377; |

| | |
|---|---|
| | Formento-Trigilio and others, 1998 #7249). They measured offsets of 2–11 m on middle Pleistocene alluvial deposits along several strands of the fault. The numerous subparallel faults identified from high-resolution aeromagnetic data (Grauch and Hudson, 2007 #7243) are not included because of lack of reported recognized surface expression. <P> |
| **Age of faulted surficial deposits** | The youngest faulted bedrock mapped along the San Ysidro section is the Miocene Zia Sand Formation (Woodward and Ruetschilling, 1976 #1133; 1987 #1130). Formento-Trigilio and Pazzaglia (1996 #1295), Formento-Trigilio (1997 #1377), and Formento-Trigilio and others (1998 #7294) map and describe fault scarps on fluvial and alluvial-fan deposits in the Jemez River drainage. The clearest evidence of faulting is found in deposits that contain the Lava Creek B ash; these sediments were deposited about 620 ka (Izett and Wilcox, 1982 #1708; Sarna-Wojcicki and others, 1987 #1707). Formento-Trigilio and Pazzaglia (1996 #1295) and Formento-Trigilio (1997 #1377) also described probable offset of a 100–200 ka terrace strath; some offset deposits along the San Ysidro section may be late Pleistocene in age. |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | middle and late Quaternary (<750 ka)<br><br>*Comments:* The timing of the most-recent event is unknown. Formento-Trigilio and Pazzaglia (1996 #1295) and Formento-Trigilio (1997 #1377) found offsets in 620-ka alluvial deposits, and probable faulting of a middle- to late-Pleistocene (100–200 ka) fluvial terrace. These relations indicate that the San Ysidro section has been active in middle and probably late Pleistocene time. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Formento-Trigilio and Pazzaglia (1996 #1295) and Formento-Trigilio (1997 #1377) measured offsets of as much as 6–11 m on several strands of the San Ysidro section in alluvial deposits containing the 620 ka Lava Creek B ash; these data support a low long-term slip rate. |

| | |
|---|---|
| **Date and Compiler(s)** | 2015<br>Keith I. Kelson, William Lettis & Associates, Inc.<br>Stephen F. Personius, U.S. Geological Survey<br>Kathleen M. Haller, U.S. Geological Survey<br>Daniel J. Koning, New Mexico Bureau of Geology & Mineral Resources<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #1084 Aldrich, M.J., Jr., 1986, Tectonics of the Jemez lineament in the Jemez Mountains and Rio Grande rift: Journal of Geophysical Research, v. 91, no. B2, p. 1753–1762.<br><br>#1288 Bryan, K., and McCann, F.T., 1937, The Ceja del Rio Puerco—A border feature of the Basin and Range province in New Mexico, Part I, Stratigraphy and structure: Journal of Geology, v. 45, p. 801-828.<br><br>#7244 Caine, J.S., and Minor, S.A., 2009, Structural and geochemical characteristics of faulted sediments and inferences on the role of water in deformation, Rio Grande Rift, New Mexico: Geological Society of America Bulletin, v. 121, no. 9-10, p. 1325-1340.<br><br>#1763 Cather, S.M., Connell, S.D., Heynekamp, M.R., and Goodwin, L.B., 1997, Geology of the Arroyo de las Calabacillas [Sky Village SE] 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 9, 8 p. pamphlet, 1 sheet, scale 1:24,000.<br><br>#7454 Connell, S.D., 2008, Geologic map of the Albuquerque-Rio Rancho metropolitan area and vicinity, Bernalillo and Sandoval Counties, New Mexico: New Mexico Bureau of Geology and Mineral Resources Geologic Map 78, scale 1:50,000.<br><br>#1377 Formento-Trigilio, M.L., 1997, The tectonic geomorphology and long-term landscape evolution of the southern Sierra Nacimiento, northern New Mexico: Albuquerque, University of New Mexico, unpublished M.S. thesis, 201 p., 1 pl., scale 1:24,000.<br><br>#1295 Formento-Trigilio, M.L., and Pazzaglia, F.J., 1996, Quaternary stratigraphy, tectonic geomorphology and long-term landscape evolution of the southern Sierra Nacimiento, in Goff, F., Kues, B.S., Rogers, M.A., McFadden, L.D., and Gardner, J.N., eds., The Jemez Mountains region: New Mexico Geological Society, 47th Field Conference, September 25-28, 1996, Guidebook, p. 335-345.<br><br>#7294 Formento-Trigilio, M.L., Toya, C., and Pazzaglia, F.J., 1998, Quaternary geologic map of the San Ysidro quadrangle, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-file Geologic Map 18Q, scale 1:24,000<br><br>#1099 Goff, F., and Kron, A., 1980, In-progress geologic map of Canon de San Diego, Jemez Springs, New Mexico, and lithologic log of Jemez Springs geothermal well: Los Alamos Scientific Laboratory Report LA-8276-MAP, 1 sheet, scale 1:12,000.<br><br>#1182 Goff, F.E., Grigsby, C.O., Trujillo, P.E., Jr., Counce, D., and Kron, A., 1981, Geology, water chemistry and geothermal potential of the Jemez Springs area, Canon de San Diego, New Mexico: Journal of Volcanology and Geothermal Research, v. 10, p. 227-244.<br><br>#7243 Grauch, V.J.S., and Hudson, M.R., 2007, Guides to understanding the aeromagnetic expression of faults in sedimentary basins—Lessons learned from the central Rio Grande rift, New Mexico: Geosphere, v. 3, p. 596–623.<br><br>#1103 Hawley, J.W., and Galusha, T., 1978, Southern rift guide 2, |

Socorro-Santa Fe, New Mexico—Bernalillo to south of San Ysidro, in Hawley, J.W., ed., Guide to Rio Grande rift in New Mexico and Colorado: New Mexico Bureau of Mines and Mineral Resources Circular 163, p. 177-183.<br><br>#1160 House, L., and Hartse, H., 1995, Seismicity and faults in northern New Mexico, in Bauer, P.W., Kues, B.S., Dunbar, N.W., Karlstrom, K.E., and Harrison, B., eds., Geology of the Santa Fe region, New Mexico: New Mexico Geological Society, 46th Field Conference, September 27-30, 1995, Guidebook, p. 135–137.<br><br>#7245 Hudson, M.R., Grauch, V.J.S., and Minor, S.A., 2008, Rock magnetic characterization of faulted sediments with associated magnetic anomalies in the Albuquerque Basin, Rio Grande rift, New Mexico: Geological Society of America Bulletin, v. 120, no. 5-6, p. 641–658.<br><br>#1708 Izett, G.A., and Wilcox, R.E., 1982, Map showing localities and inferred distributions of the Huckleberry Ridge, Mesa Falls, and Lave Creek ash beds (Pearlette family ash beds) of Pleistocene age in the Western United States and southern Canada: U.S. Geological Survey Miscellaneous Investigations Map I-1325, 1 sheet, scale 1:4,000,000.<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#7249 Kelson, K.I., Bauer, P.W., Unruh, J.R., and Bott, J.D.J., 2004, Late Quaternary characteristics of the northern Embudo fault, Taos County, New Mexico, in Brister, B.S., Bauer, P.W., Read, A.S., and Lueth, V.W., eds., Geology of the Taos region, New Mexico: New Mexico Geological Society, 55th Annual Field Conference, Guidebook, p. 147–157.<br><br>#7375 Koning, D.J., Pederson, J., Pazzaglia, F.J., and Cather, S.M., 1998, Geology of the Cerro Conejo (Sky Village NE) 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-file Geologic Map 45, scale 1:24,000.<br><br>#7246 Minor, S.A., and Hudson, M.R., 2006, Regional survey of structural properties and cementation patterns of fault zones in the northern part of the Albuquerque Basin, New Mexico—Implications for ground-water flow: U.S. Geological Survey Professional Paper 1719, 32 p.<br><br>#1707 Sarna-Wojcicki, A.M., Morrison, S.D., Meyer, C.E., and Hillhouse, J.W., 1987, Correlation of upper Cenozoic tephra layers between sediments of the Western United States and eastern Pacific Ocean and comparison with biostratigraphic and magnetostratigraphic age data: Geological Society of America Bulletin, v. 98, p. 207-223.<br><br>#1155 Wong, I., Kelson, K., Olig, S., Kolbe, T., Hemphill-Haley, M., Bott, J., Green, R., Kanakari, H., Sawyer, J., Silva, W., Stark, C., Haraden, C., Fenton, C., Unruh, J., Gardner, J., Reneau, S., and House, L., 1995, Seismic hazards evaluation of the Los Alamos National Laboratory: Technical report to Los Alamos National Laboratory, Los Alamos, New Mexico, February 24, 1995, 3 volumes, 12 pls., 16 appen.<br><br>#1130 Woodward, L.A., 1987, Geology and mineral resources of Sierra Nacimiento and vicinity, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 42, 84 p., 1 pl., scale 1:100,000.<br><br>#1131 Woodward, L.A., and DuChene, H.R., 1975, Geometry of the Sierrita fault and its bearing on tectonic development of the Rio Grande rift, New Mexico: Geology, v. 3, p. 114–116.<br><br>#1133 Woodward, L.A., and Ruetschilling, R.L., 1976, Geology of San Ysidro quadrangle, New Mexico: New Mexico Bureau of Mines and Mineral Resources Geologic Map 37, 1 sheet, scale

| | |
|---|---|
| | 1:24,000.<br><br>#1132 Woodward, L.A., DuChene, H.R., and Martinez, R., 1977, Geology of Gilman quadrangle, New Mexico: New Mexico Bureau of Mines and Mineral Resources Geologic Map 45, scale 1:24,000.<br><br>#1427 Wright, H.E., Jr., 1946, Tertiary and Quaternary geology of the lower Rio Puerco area, New Mexico: Geological Society of America Bulletin, v. 57, p. 383-456. |

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Mesa Prieta faults (Class A) No. 1985

Last Review Date: 2016-01-01

*citation for this record:* Jochems, A.P., compiler, 2016, Fault number 1985, Mesa Prieta faults, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:22 AM.

| | |
|---|---|
| **Synopsis** | |
| **Name comments** | |
| **County(s) and State(s)** | SANDOVAL COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | COLORADO PLATEAUS <br> |
| **Reliability of location** | Good<br>Compiled at 1:100,000 scale.<br><br>*Comments:* <P> |
| **Geologic setting** | <P> |
| **Length (km)** | 12 km. |

| | |
|---|---|
| **Average strike** | |
| **Sense of movement** | Normal |
| **Dip Direction** | NW; SE |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | <P> |
| **Age of faulted surficial deposits** | |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | undifferentiated Quaternary (<1.6 Ma)<br><br>*Comments:* <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr |
| **Date and Compiler(s)** | 2016<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | |

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Nacimiento fault, northern section (Class A) No. 2002a

**Last Review Date: 2015-12-14**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Kelson, K.I., Jochems, A.P., and Personius, S.F., compilers, 2015, Fault number 2002a, Nacimiento fault, northern section, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:22 AM.**

**Synopsis**

**General:** The Nacimiento fault is an east-dipping fault bordering the Nacimiento uplift, an 80-km-long, 10- to 16-km-wide uplift related to Laramide deformation. The fault merges with the Gallina fault to the north, and dies out to the south into a broad anticline. The relatively high level of contemporary microseismicity within the Sierra Nacimiento may be related to deformation in the hanging wall of the fault. Detailed mapping along the southern part of the fault shows several short normal faults with both down-to-the-east and down-to-the-west displacements in Quaternary deposits. Down-to-the-east displacements may indicate normal reactivation of the Nacimiento reverse fault in the late Quaternary.

**Sections:** This fault has 2 sections. Woodward (1987 #1130) mapped the Nacimiento and Pajarito faults along the western margin of the Sierra Nacimiento. He noted the lack of continuity between these faults in the vicinity of San Miguel Canyon (section boundary), about 3 km southeast of the village of San Miguel. North of San Miguel Canyon, the fault generally has a lower dip and is a thrust fault, whereas south of San Miguel Canyon the fault is a high-angle reverse fault. Wong and others (1995 #1155) considered potential fault-rupture scenarios that included

| | |
|---|---|
| | rupture on either a northern section or a southern section, and on both sections together. These sections are considered separately here. |
| **Name comments** | **General:** The Nacimiento fault extends from Red Mesa, 7 km west of San Ysidro on the south, to the northern end of Sierra Nacimiento, 7 km northeast of Regina. The Nacimiento fault forms the western margin of the Laramide Nacimiento uplift. As used herein, the Nacimiento fault includes the Nacimiento and Pajarito faults of Woodward (1987 #1130), to avoid confusion with the Pajarito fault [2008] along the western margin of the Rio Grande rift near Los Alamos.<br><br>**Section:** This part of the Nacimiento fault was defined as the northern section by Wong and others (1995 #1155). The northern section extends from San Miguel Canyon about 3 km southeast of the village of San Miguel to the northern end of Sierra Nacimiento, 7 km northeast of Regina. |
| **County(s) and State(s)** | RIO ARRIBA COUNTY, NEW MEXICO <br>SANDOVAL COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | COLORADO PLATEAUS <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Detailed geologic maps at a scale of 1:24,000 are available along the entire fault trace; 1:24,000 maps covering the northern section are those of Woodward and others (1972 #7292; 1973 #7293) and Merrick and Woodward (1982 #7291). These maps are compiled and synthesized by Woodward (1987 #1130). The location of the fault was digitized at 1:24,000 scale using photogrammetry to accurately map its trace from these maps. The fault was also mapped by Renick (1931 #1140) at a scale of 1:125,000 and by Wood and Northrop (1946 #1143) at a scale of about 1:95,000. <P> |
| **Geologic setting** | The Nacimiento fault is high-angle and over much of its geologic history a west-vergent reverse fault. The Nacimiento uplift is a north-south elongated structural block that lies west of the Jemez Mountains and forms the eastern margin of the San Juan Basin of the Colorado Plateau. Structural relief of the uplift formed during Laramide deformation, with shortening taking place via folding and reverse movement along the Nacimiento fault. The fault is west of the western margin of the Rio Grande rift. Quaternary normal faulting near Arroyo Peñasco |

| | |
|---|---|
| | documented by Formento-Trigilio and Pazzaglia (1996 #1295), Formento-Trigilio (1997 #1377), and Formento-Trigilio and Pazzaglia (1998 #2847) may indicate normal reactivation of the Nacimiento reverse fault. The relatively high level of contemporary microseismicity within the Sierra Nacimiento supports the interpretation of Quaternary deformation in the hanging wall of the fault (Wong and others, 1995 #1155; House and Hartse, 1995 #1160). <P> |
| **Length (km)** | This section is 36 km of a total fault length of 82 km. |
| **Average strike** | N3°E (for section) versus N1°W (for whole fault) |
| **Sense of movement** | Normal<br><br>*Comments:* West-vergent thrusting occurred during Laramide deformation. Sense of movement associated with contemporary microseismicity is unknown, but normal backslip may be likely in the present extensional regime. <P> |
| **Dip** | 45°–60° E.<br><br>*Comments:* Bedrock exposures of the fault noted by Woodward (1987 #1130) provide near-surface data on fault dip. Woodward (1987 #1130) speculates that the fault steepens with depth, although there are no published deep structural data for the fault. <P> |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | Prominent west-facing range front of the Sierra Nacimiento is coincident with the Nacimiento fault. Baltz (1967 #1167) did not find geomorphic evidence of late Quaternary movement. Formento-Trigilio and Pazzaglia (1998 #2847) described low to moderate scarps on middle to late Pleistocene terrace and pediment-fan surfaces along the southern section <P> |
| **Age of faulted surficial deposits** | Youngest faulted bedrock is Cretaceous in age, although there are little or no data on the presence or absence of displaced late Quaternary deposits along the northern section. Manley and others (1987 #1119) map undisplaced Quaternary gravel across the fault trace at Rito de los Pinos, about 10 km northeast of the town of Cuba. |

| | |
|---|---|
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | undifferentiated Quaternary (<1.6 Ma)<br><br>*Comments:* Timing of most-recent event on northern section unknown. Prominent geomorphic expression along the range front and possible association with contemporary microseismicity suggest late Quaternary activity (Wong and others, 1995 #1155; House and Hartse, 1995 #1160). <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Low slip-rate category assigned based on the lack of evidence for Quaternary displacement along the northern section. |
| **Date and Compiler(s)** | 2015<br>Keith I. Kelson, William Lettis & Associates, Inc.<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources<br>Stephen F. Personius, U.S. Geological Survey |
| **References** | #1167 Baltz, E.H., 1967, Stratigraphy and regional tectonic implications of part of Upper Cretaceous and Tertiary rocks east-central San Juan Basin New Mexico: U.S. Geological Survey Professional Paper 552, 99 p., 1 pl., scale 1:377,000.<br><br>#1377 Formento-Trigilio, M.L., 1997, The tectonic geomorphology and long-term landscape evolution of the southern Sierra Nacimiento, northern New Mexico: Albuquerque, University of New Mexico, unpublished M.S. thesis, 201 p., 1 pl., scale 1:24,000.<br><br>#1295 Formento-Trigilio, M.L., and Pazzaglia, F.J., 1996, Quaternary stratigraphy, tectonic geomorphology and long-term landscape evolution of the southern Sierra Nacimiento, in Goff, F., Kues, B.S., Rogers, M.A., McFadden, L.D., and Gardner, J.N., eds., The Jemez Mountains region: New Mexico Geological Society, 47th Field Conference, September 25-28, 1996, Guidebook, p. 335-345.<br><br>#2847 Formento-Trigilio, M.L., and Pazzaglia, F.J., 1998, Tectonic geomorphology of the Sierra Nacimiento—Traditional and new techniques in assessing long-term landscape evolution in the southern Rocky Mountains: Journal of Geology, v. 106, p. 433-453.<br><br>#1160 House, L., and Hartse, H., 1995, Seismicity and faults in northern New Mexico, in Bauer, P.W., Kues, B.S., Dunbar, N.W., Karlstrom, K.E., and Harrison, B., |

eds., Geology of the Santa Fe region, New Mexico: New Mexico Geological Society, 46th Field Conference, September 27-30, 1995, Guidebook, p. 135–137.<br><br>#1119 Manley, K., Scott, G.R., and Wobus, R.A., 1987, Geologic map of the Aztec 1° by 2° quadrangle, northwestern New Mexico and southern Colorado: U.S. Geological Survey Miscellaneous Investigations Map I-1730, 1 sheet, scale 1:250,000.<br><br>#7291 Merrick, M.A., and Woodward, L.A., 1982, Geology of Regina quadrangle, Rio Arriba and Sandoval Counties, New Mexico: New Mexico Bureau of Mines and Mineral Resources Geologic Map 46, scale 1:24,000.<br><br>#6930 Personius, S.F., Machette, M.N., and Kelson, K.I., 1999, Quaternary faults in the Albuquerque area—An update, in Pazzaglia, F.J., and Lucas, S.G., eds., Albuquerque geology: New Mexico Geological Society 50th Annual Field Conference, Guidebook, September 22–25, p. 189–200.<br><br>#1140 Renick, B.C., 1931, Geology and ground-water resources of western Sandoval County, New Mexico: U.S. Geological Survey Water-Supply Paper 620, 117 p., 10 pls.<br><br>#1155 Wong, I., Kelson, K., Olig, S., Kolbe, T., Hemphill-Haley, M., Bott, J., Green, R., Kanakari, H., Sawyer, J., Silva, W., Stark, C., Haraden, C., Fenton, C., Unruh, J., Gardner, J., Reneau, S., and House, L., 1995, Seismic hazards evaluation of the Los Alamos National Laboratory: Technical report to Los Alamos National Laboratory, Los Alamos, New Mexico, February 24, 1995, 3 volumes, 12 pls., 16 appen.<br><br>#1143 Wood, G.H., Jr., and Northrop, S.A., 1946, Geology of the Nacimiento Mountains, San Pedro Mountain, and adjacent plateaus in parts of Sandoval and Rio Arriba Counties, New Mexico: U.S. Geological Survey Oil and Gas Investigations Map 57, scale 1:95,000.<br><br>#1130 Woodward, L.A., 1987, Geology and mineral resources of Sierra Nacimiento and vicinity, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 42, 84 p., 1 pl., scale 1:100,000.<br><br>#7293 Woodward, L.A., Anderson, J.B., Kaufman, W.H., and Reed, R.K., 1973, Geologic map and sections of San Pablo quadrangle, New Mexico: New Mexico Bureau of Mines and Mineral Resources Geologic Map 26, scale 1:24,000.<br><br>#7292 Woodward, L.A., McLelland, D., and Kaufman, W.H., 1972, Geologic map of Cuba quadrangle: New Mexico Bureau of Mines and Mineral Resources Geologic Map 25, scale 1:24,000.

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Nacimiento fault, southern section (Class A) No. 2002b

**Last Review Date: 2015-12-14**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Kelson, K.I., Jochems, A.P., and Personius, S.F., compilers, 2015, Fault number 2002b, Nacimiento fault, southern section, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:23 AM.**

**Synopsis**

**General:** The Nacimiento fault is an east-dipping fault bordering the Nacimiento uplift, an 80-km-long, 10- to 16-km-wide uplift related to Laramide deformation. The fault merges with the Gallina fault to the north, and dies out to the south into a broad anticline. The relatively high level of contemporary microseismicity within the Sierra Nacimiento may be related to deformation in the hanging wall of the fault. Detailed mapping along the southern part of the fault shows several short normal faults with both down-to-the-east and down-to-the-west displacements in Quaternary deposits. Down-to-the-east displacements may indicate normal reactivation of the Nacimiento reverse fault in the late Quaternary.

**Sections:** This fault has 2 sections. Woodward (1987 #1130) mapped the Nacimiento and Pajarito faults along the western margin of the Sierra Nacimiento. He noted the lack of continuity between these faults in the vicinity of San Miguel Canyon (section boundary), about 3 km southeast of the village of San Miguel. North of San Miguel Canyon, the fault generally has a lower dip and is a thrust fault, whereas south of San Miguel Canyon the fault is a high-angle reverse fault. Wong and others (1995 #1155) considered potential fault-rupture scenarios that included

| | |
|---|---|
| | rupture on either a northern section or a southern section, and on both sections together. These sections are considered separately here. |
| **Name comments** | **General:** The Nacimiento fault extends from Red Mesa, 7 km west of San Ysidro on the south, to the northern end of Sierra Nacimiento, 7 km northeast of Regina. The Nacimiento fault forms the western margin of the Laramide Nacimiento uplift. As used herein, the Nacimiento fault includes the Nacimiento and Pajarito faults of Woodward (1987 #1130), to avoid confusion with the Pajarito fault [2008] along the western margin of the Rio Grande rift near Los Alamos.<br><br>**Section:** This part of the Nacimiento fault was defined as the southern section by Wong and others (1995 #1155). The southern section extends from U.S. Highway 44 about 7 km west of the village of San Ysidro, northward to San Miguel Canyon about 3 km southeast of the village of San Miguel. |
| **County(s) and State(s)** | SANDOVAL COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | COLORADO PLATEAUS <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Detailed geologic maps at a scale of 1:24,000 are available along the entire fault trace; 1:24,000 maps covering the southern section include those of Woodward and Schumacher (1973 #7295) and Woodward and others (1973 #7293; 1977 #1132). These maps are compiled and synthesized by Woodward (1987 #1130). In addition, detailed mapping of Quaternary deposits at 1:24,000 scale at the southern end of the fault has been completed by Formento-Trigilio and Pazzaglia (1996 #1295), Formento-Trigilio (1997 #1377), and Formento-Trigilio and others (1998 #7294). The location of the fault was digitized at 1:24,000 scale using photogrammetry to accurately map its trace from these maps. The fault also was mapped by Renick(1931 #1140) at a scale of 1:125,000, by Wood and Northrop (1946 #1143) at a scale of about 1:95,000, and by Baltz (1967 #1167) at a scale of 1:63,360. <P> |
| **Geologic setting** | The Nacimiento fault is high-angle and over much of its geologic history a west-vergent reverse fault. The Nacimiento uplift is a north-south elongated structural block that lies west of the Jemez Mountains and forms the |

| | |
|---|---|
| | eastern margin of the San Juan Basin of the Colorado Plateau. Structural relief of the uplift formed during Laramide deformation, with shortening taking place via folding and reverse movement along the Nacimiento fault. The fault is west of the western margin of the Rio Grande rift. Quaternary normal faulting near Arroyo Peñasco documented by Formento-Trigilio and Pazzaglia (1996 #1295), Formento-Trigilio (1997 #1377), and Formento-Trigilio and Pazzaglia (1998 #2847) may indicate normal reactivation of the Nacimiento reverse fault. The relatively high level of contemporary microseismicity within the Sierra Nacimiento supports the interpretation of Quaternary deformation in the hanging wall of the fault (Wong and others, 1995 #1155; House and Hartse, 1995 #1160). <P> |
| **Length (km)** | This section is 45 km of a total fault length of 82 km. |
| **Average strike** | N4°W (for section) versus N1°W (for whole fault) |
| **Sense of movement** | Normal<br><br>*Comments:* West-vergent reverse faulting occurred during Laramide deformation on the Nacimiento fault (Woodward, 1987 #1130). Sense of movement associated with contemporary microseismicity is unknown, but down-to-the-east and down-to-the-west Quaternary normal faults have been mapped by Formento-Trigilio and Pazzaglia (1996 #1295), Formento-Trigilio (1997 #1377), and Koning and others (1998 #7375) near Arroyo Peñasco and Cañada de las Milpas at the southern end of the fault. The down-to-the-west normal faults are in the footwall of the Nacimiento reverse fault, but the down-to-the-east Quaternary movement on one fault strand may be interpreted as normal backslip on a splay of the reverse fault (Formento-Trigilio and Pazzaglia, 1996 #1295; Formento-Trigilio, 1997 #1377). <P> |
| **Dip** | 75°–90° E.<br><br>*Comments:* Bedrock exposures of the fault noted by Woodward (1987 #1130) provide near-surface data on fault dip. Although exposures of the main trace of the Laramide Nacimiento fault clearly show steep east dips, west dipping synthetic and antithetic faults are locally present (Woodward, 1987 #1130). Formento-Trigilio and Pazzaglia (1996 #1295) and Formento-Trigilio (1997 #1377) mapped several normal faults in Quaternary deposits with both east and west dips near Arroyo Peñasco at the southern end of the Nacimiento fault. Woodward (1987 #1130) speculated that the fault steepens with depth, although no published subsurface structural data are available to confirm this interpretation. <P> |

| | |
|---|---|
| **Paleoseismology studies** | Formento-Trigilio and Pazzaglia (1996 #1295), Formento-Trigilio (1997 #1377), and Formento-Trigilio and others (1998 #7294) mapped Quaternary deposits and faults in detail near Arroyo Peñasco at the southern end of the Nacimiento fault. Most of the Quaternary faults mapped by these workers dip west, opposite to the dip of the bedrock fault mapped by Woodward (1987 #1130) in the area. These faults are as much as 2 km long and are marked by scarps up to 17 m high, although some of this apparent displacement may be related to landsliding in the underlying Triassic shale bedrock. Down-to-the-east Quaternary displacement of 4.2 m of travertine-cemented alluvium on one fault strand on the north rim of Arroyo Peñasco may either represent normal reactivation on a trace of the Nacimiento reverse fault mapped by Woodward (1987 #1130), or is an antithetic splay to the down-to-the-west faults mapped further east by Formento-Trigilio and Pazzaglia (1996 #1295) and Formento-Trigilio (1997 #1377). <P> |
| **Geomorphic expression** | The prominent west-facing range front of the Sierra Nacimiento is coincident with the Nacimiento fault. Baltz (1967 #1167) did not identify geomorphic evidence of late Quaternary activity, but Formento-Trigilio and Pazzaglia (1996 #1295) and Formento-Trigilio (1997 #1377) discuss evidence of multiple fault strands with Quaternary displacement along the southern end of the Sierra Nacimiento near Arroyo Peñasco. Scarps on middle to late Pleistocene terrace and pediment-fan surfaces in this area are up to 4.2 m high (Formento-Trigilio and Pazzaglia, 1998 #2847). <P> |
| **Age of faulted surficial deposits** | Although the youngest faulted bedrock mapped along the Nacimiento fault is Cretaceous in age (Woodward, 1987 #1130), Formento-Trigilio and Pazzaglia (1996 #1295) and Formento-Trigilio (1997 #1377) map fault scarps and infer displacements from geomorphic data in late Pleistocene alluvial deposits near Arroyo Peñasco at the southern end of the Nacimiento fault. Uranium-series ages on faulted, travertine-cemented alluvium indicate the faulted alluvium was deposited between about 270 ka and about 60 ka (Formento-Trigilio, 1997 #1377). |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | middle and late Quaternary (<750 ka)<br><br>*Comments:* Timing of most-recent event is from uranium-series dating of faulted travertine-cemented alluvium by Formento-Trigilio (1997 #1377) that bracket the age of the offset alluvium between about 270 ka and 60 ka. <P> |

| | |
|---|---|
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Wong and others (1995 #1155) conservatively estimated a range in slip rate of 0.01 to 0.23 mm/yr for the Nacimiento fault, with a preferred value of 0.02 mm/yr, based on analysis of slip rates on analogous faults in the Rio Grande rift (Formento-Trigilio and Pazzaglia, 1996 #1295; Formento-Trigilio, 1997 #1377). A rate of up to 0.07 mm/yr may be permissible depending on the age of displaced travertine-cemented alluvium (Personius and others, 1999 #6930). |
| **Date and Compiler(s)** | 2015<br>Keith I. Kelson, William Lettis & Associates, Inc.<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources<br>Stephen F. Personius, U.S. Geological Survey |
| **References** | #1167 Baltz, E.H., 1967, Stratigraphy and regional tectonic implications of part of Upper Cretaceous and Tertiary rocks east-central San Juan Basin New Mexico: U.S. Geological Survey Professional Paper 552, 99 p., 1 pl., scale 1:377,000.<br><br>#1377 Formento-Trigilio, M.L., 1997, The tectonic geomorphology and long-term landscape evolution of the southern Sierra Nacimiento, northern New Mexico: Albuquerque, University of New Mexico, unpublished M.S. thesis, 201 p., 1 pl., scale 1:24,000.<br><br>#1295 Formento-Trigilio, M.L., and Pazzaglia, F.J., 1996, Quaternary stratigraphy, tectonic geomorphology and long-term landscape evolution of the southern Sierra Nacimiento, in Goff, F., Kues, B.S., Rogers, M.A., McFadden, L.D., and Gardner, J.N., eds., The Jemez Mountains region: New Mexico Geological Society, 47th Field Conference, September 25-28, 1996, Guidebook, p. 335-345.<br><br>#2847 Formento-Trigilio, M.L., and Pazzaglia, F.J., 1998, Tectonic geomorphology of the Sierra Nacimiento—Traditional and new techniques in assessing long-term landscape evolution in the southern Rocky Mountains: Journal of Geology, v. 106, p. 433-453.<br><br>#7294 Formento-Trigilio, M.L., Toya, C., and Pazzaglia, F.J., 1998, Quaternary geologic map of the San Ysidro quadrangle, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-file Geologic Map 18Q, scale 1:24,000<br><br>#1160 House, L., and Hartse, H., 1995, Seismicity and faults in northern New Mexico, in Bauer, P.W., Kues, B.S., Dunbar, N.W., Karlstrom, K.E., and Harrison, B., eds., Geology of the Santa Fe region, New Mexico: New Mexico Geological Society, 46th Field Conference, September 27-30, 1995, Guidebook, p. 135–137.<br><br>#7375 Koning, D.J., Pederson, J., Pazzaglia, F.J., and Cather, S.M., 1998, Geology of the Cerro Conejo (Sky Village NE) 7.5-minute quadrangle, Sandoval County, |

New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-file Geologic Map 45, scale 1:24,000.<br><br>#6930 Personius, S.F., Machette, M.N., and Kelson, K.I., 1999, Quaternary faults in the Albuquerque area—An update, in Pazzaglia, F.J., and Lucas, S.G., eds., Albuquerque geology: New Mexico Geological Society 50th Annual Field Conference, Guidebook, September 22–25, p. 189–200.<br><br>#1140 Renick, B.C., 1931, Geology and ground-water resources of western Sandoval County, New Mexico: U.S. Geological Survey Water-Supply Paper 620, 117 p., 10 pls.<br><br>#1155 Wong, I., Kelson, K., Olig, S., Kolbe, T., Hemphill-Haley, M., Bott, J., Green, R., Kanakari, H., Sawyer, J., Silva, W., Stark, C., Haraden, C., Fenton, C., Unruh, J., Gardner, J., Reneau, S., and House, L., 1995, Seismic hazards evaluation of the Los Alamos National Laboratory: Technical report to Los Alamos National Laboratory, Los Alamos, New Mexico, February 24, 1995, 3 volumes, 12 pls., 16 appen.<br><br>#1143 Wood, G.H., Jr., and Northrop, S.A., 1946, Geology of the Nacimiento Mountains, San Pedro Mountain, and adjacent plateaus in parts of Sandoval and Rio Arriba Counties, New Mexico: U.S. Geological Survey Oil and Gas Investigations Map 57, scale 1:95,000.<br><br>#1130 Woodward, L.A., 1987, Geology and mineral resources of Sierra Nacimiento and vicinity, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 42, 84 p., 1 pl., scale 1:100,000.<br><br>#7293 Woodward, L.A., Anderson, J.B., Kaufman, W.H., and Reed, R.K., 1973, Geologic map and sections of San Pablo quadrangle, New Mexico: New Mexico Bureau of Mines and Mineral Resources Geologic Map 26, scale 1:24,000.<br><br>#7295 Woodward, L.A., and Schumacher, O.L., 1973, Geologic map and sections of La Ventana quadrangle, New Mexico: New Mexico Bureau of Mines and Mineral Resources Geologic Map 28, scale 1:24,000.<br><br>#1132 Woodward, L.A., DuChene, H.R., and Martinez, R., 1977, Geology of Gilman quadrangle, New Mexico: New Mexico Bureau of Mines and Mineral Resources Geologic Map 45, scale 1:24,000.

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## San Felipe fault zone, Algodones section (Class A) No. 2030b

**Last Review Date: 2016-06-28**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Personius, S.F., Kelson, K.I., and Jochems, A.P., compilers, 2016, Fault number 2030b, San Felipe fault zone, Algodones section, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:29 AM.**

| | |
|---|---|
| **Synopsis** | **General:** The San Felipe fault zone is a broad zone of normal faults that offset basalts of the San Felipe volcanic field and underlying Santa Fe Group sedimentary rocks. The fault zone is best expressed where individual fault strands offset the volcanic tablelands of Santa Ana Mesa. The fault zone is primarily a graben, centered on the westernmost of two north-trending eruptive centers in the volcanic field. This structure, the San Felipe graben, is bound on the west by the down-to-the-east Luce and Santa Ana faults, and on the east by the down-to-the-west Algodones fault. Most of these faults offset the 2.4–2.6 Ma basalt flows of the San Felipe volcanic field. Average displacements on most faults are 15–30 m, although some of the larger structures, such as the Luce fault, have as much as 90–120 m of vertical displacement.<br><br>**Sections:** This fault has 2 sections. Wong and others (1995 #1155) used the polarity of faults in the San Felipe fault zone to delineate two sections: down-to-the-east faults that form the western margin of the San Felipe graben (Santa Ana and Luce faults) are included in the Santa Ana section, and down-to-the-west faults that form the eastern margin of the graben (Algodones fault) are include in the Algodones section. They assumed that one of |

| | |
|---|---|
| | these sections is a "master fault" that controls both sections, but they did not have enough subsurface data to support either scenario. |
| **Name comments** | **General:** This complex of numerous, generally north-trending normal faults near Santa Ana Mesa was first mapped in detail by Soister (1952 #1418). Kelley (1954 #1222) followed Soister's mapping closely in his compilation, and applied the name San Felipe fault zone to these structures. Later maps by Smith and others (1970 #1125), Kelley (1977 #1106), and Kelley and Kudo (1978 #1307) show similar fault patterns. Kelley (1977 #1106) named many of the more prominent structures in the zone, such as the Santa Ana, Luce, Cocida, and Algodones faults and the San Felipe graben. In their compilation, Wong and others (1995 #1155) used the name "San Felipe fault zone".<br><br>**Section:** The Algodones section includes the Algodones fault of Kelley (1977 #1106) and numerous smaller displacement down-to-the-west faults that form the east flank of the San Felipe graben. Some strands of the Algodones section of the San Felipe fault zone have been projected southward across the Rio Grande and connected with parts of the Valley View fault (Kelley, 1977 #1106; Wong and others, 1995 #1155), but detailed mapping by Connell (1995 #1291), Connell and others (1995 #1764), and Cather and Connell (1998 #7435) shows that strands of the Valley View fault trend northeasterly at their northern ends and probably do not connect with the San Felipe fault zone. |
| **County(s) and State(s)** | SANDOVAL COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | BASIN AND RANGE <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Fault locations are good where faults cut volcanic rocks, but locations are poor in the less resistant Santa Fe Group rocks. Fault traces are from 1:24,000-scale maps of Cather and Connell (1998 #7435), Connell (1998 #7502), Smith and Kuhle (1998 #1771), Chamberlin and others (1999 #7524), and Personius (2002 #7526). A.P. Jochems used photogrammetric methods to accurately place fault traces in some locations. <P> |
| **Geologic setting** | The San Felipe fault zone is located in the western part of the Santo Domingo basin of the Rio Grande rift as defined by Smith and others (2001 #7438). The Santo Domingo basin links the en echelon Albuquerque and Española |

| | |
|---|---|
| | basins, and kinematic and paleostress evidence suggests that the basin functions as a relay that began to narrow in Plio-Pleistocene time (Minor and others, 2013 #7437). The fault zone forms a north-trending graben within the San Felipe volcanic field. Although Wong and others (1995 #1155) conclude that this graben is a minor sub-basin within the Rio Grande rift, the narrowing of the fault zone within the volcanic field indicates that the geometry of the fault zone may be in part controlled by volcanic activity (for example, van Wyk de Vries and Merle, 1996 #1422). <P> |
| **Length (km)** | This section is 45 km of a total fault length of 48 km. |
| **Average strike** | N7°W (for section) versus N1°E (for whole fault) |
| **Sense of movement** | Normal |
| **Dip** | 64–74° W<br><br>*Comments:* Dips of 64–74° are reported for west-dipping faults belonging to the Algodones section of the San Felipe fault zone (Connell, 1998 #7502; Personius, 2002 #7526). In addition, Connell (1998 #7502) reported a dip of 77° toward the east along one of the few east-dipping strands in the Algodones section 1.5 km northwest of Canjilon Hill in the Bernalillo 7.5-minute quadrangle <P> |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | The Algodones fault and other faults that cut the basalt flows of the San Felipe volcanic field are well preserved as escarpments covered by basalt talus. Where these structures are located in Santa Fe Group rocks, fault expression is poor. Soister (1952 #1418) and Kelley (1977 #1106) measured average displacements of 15–30 m in basalts on most structures in the San Felipe fault zone, and as much as 90–120 m on larger structures such as the Luce fault in the Santa Ana section. <P> |
| **Age of faulted surficial deposits** | Faults in the Algodones section offset the 2.4-2.6 Ma (Bachman and Mehnert, 1978 #1265; Smith and Kuhle, 1998 #1771) basalts of the San Felipe volcanic field and underlying Santa Fe Group sedimentary rocks. Soister (1952 #1418) describes offset of his early Pleistocene Mesita Alta gravel and surface, which overlies San Felipe basalt flows in several places. |

| | |
|---|---|
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | undifferentiated Quaternary (<1.6 Ma)<br><br>*Comments:* No detailed studies of the age of most recent movement have been conducted. However, early Pleistocene gravels are offset locally and 90–120 m of post-San Felipe basalt (2.4-2.6 Ma) displacement has occurred. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Wong and others (1995 #1155) calculated long-term slip rates of 0.01–0.04 mm/yr based on 90–120 m of displacement that has occurred on the Luce fault since deposition of the San Felipe basalt (2.4-2.6 Ma) and similar data. They also concluded that it is likely that some of the major faults within the San Felipe fault zone act as independent rupture segments, but could not rule out the possibility that some faults rupture together. |
| **Date and Compiler(s)** | 2016<br>Stephen F. Personius, U.S. Geological Survey<br>Keith I. Kelson, William Lettis & Associates, Inc.<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #1265 Bachman, G.O., and Mehnert, H.H., 1978, New K-Ar dates and the late Pliocene to Holocene geomorphic history of the central Rio Grande region, New Mexico: Geological Society of America Bulletin, v. 89, p. 283-292.<br><br>#7435 Cather, S.M., and Connell, S.D., 1998, Geologic map of the San Felipe Pueblo quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 19, scale 1:24,000.<br><br>#1764 Cather, S.M., Connell, S.D., Karlstrom, K.E., Ilg, B., Menne, B., Bauer, P.W., and Andronicus, C., 1996, Geology of the Placitas SE 7.5-minute quadrangle, Sandoval County, central New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Digital Map OF-DM 2, 26 p. pamphlet, 1 sheet, scale 1:24,000.<br><br>#7524 Chamberlin, R.M., Pazzaglia, F.J., Wegmann, K.W., and Smith, G.A., 1999, Geologic map of the Loma Creston 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 25, scale 1:24,000.<br><br>#1291 Connell, S.D., 1995, Quaternary geology and |

geomorphology of the Sandia Mountains piedmont, Bernalillo and Sandoval Counties, central New Mexico: Riverside, University of California, unpublished M.S. thesis, 414 p., 3 pls.<br><br>#7502 Connell, S.D., 1998, Geology of the Bernalillo quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 16, scale 1:24,000.<br><br>#1222 Kelley, V.C., 1954, Tectonic map of a part of the upper Rio Grande area, New Mexico: U.S. Geological Survey Oil and Gas Investigations Map OM-157, 1 sheet, scale 1:190,080.<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1307 Kelley, V.C., and Kudo, A.M., 1978, Volcanoes and related basalts of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Circular 156, 29 p., 2 pls.<br><br>#7437 Minor, S.A., Hudson, M.R., Caine, J.S., and Thompson, R.A., 2013, Oblique transfer of extensional strain between basins of the middle Rio Grande rift, New Mexico—Fault kinematic and paleostress constrains, in Hudson, M.R., and Grauch, V.J.S., eds., New perspectives on Rio Grande rift basins: From Tectonics to Groundwater: Geological Society of America Special Paper 494, p. 345–382.<br><br>#7526 Personius, S.F., 2002, Geologic map of the Santa Ana Pueblo quadrangle, Sandoval County, New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-2405, scale 1:24,000.<br><br>#1771 Smith, G.A., and Kuhle, A.J., 1998, Geologic map of the Santo Domingo Southwest quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map OF-DM 26, 1 sheet, scale 1:24,000.<br><br>#7438 Smith, G.A., McIntosh, W.C., and Kuhle, A.J., 2001, Sedimentologic and geomorphic evidence for seesaw subsidence of the Santo Domingo accommodation-zone basin, Rio Grande rift, New Mexico: Geological Society of America Bulletin, v. 113, no. 5, p. 561–574.<br><br>#1125 Smith, R.L., Bailey, R.A., and Ross, C.S., 1970, Geologic map of the Jemez Mountains, New Mexico: U.S. Geological Survey Miscellaneous Investigations Map I-571, 1 sheet, scale 1:125,000.<br><br>#1418 Soister, P.E., 1952, Geology of Santa Ana Mesa and adjoining areas, Sandoval County, New Mexico: Albuquerque, University of New Mexico, unpublished M.S. thesis, 126 p., 2 pls., scale 1:62,500.<br><br>#1422 van Wyk de Vries, B., and Merle, O., 1996, The effects of volcanic constructs on rift fault patterns: Geology, v. 24, p. 643-646.<br><br>#1155 Wong, I., Kelson, K., Olig, S., Kolbe, T., Hemphill-Haley, M., Bott, J., Green, R., Kanakari, H., Sawyer, J., Silva, W., Stark, C., Haraden, C., Fenton, C., Unruh, J., Gardner, J., Reneau, S., and House, L., 1995, Seismic hazards evaluation of the Los Alamos National Laboratory: Technical report to Los Alamos National Laboratory, Los Alamos, New Mexico, February 24, 1995, 3 volumes, 12 pls., 16 appen.

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## San Felipe fault zone, Santa Ana section (Class A) No. 2030a

**Last Review Date: 2016-06-28**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Personius, S.F., Jochems, A.P., and Kelson, K.I., compilers, 2016, Fault number 2030a, San Felipe fault zone, Santa Ana section, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:29 AM.**

| | |
|---|---|
| **Synopsis** | **General:** The San Felipe fault zone is a broad zone of normal faults that offset basalts of the San Felipe volcanic field and underlying Santa Fe Group sedimentary rocks. The fault zone is best expressed where individual fault strands offset the volcanic tablelands of Santa Ana Mesa. The fault zone is primarily a graben, centered on the westernmost of two north-trending eruptive centers in the volcanic field. This structure, the San Felipe graben, is bound on the west by the down-to-the-east Luce and Santa Ana faults, and on the east by the down-to-the-west Algodones fault. Most of these faults offset the 2.4–2.6 Ma basalt flows of the San Felipe volcanic field. Average displacements on most faults are 15–30 m, although some of the larger structures, such as the Luce fault, have as much as 90–120 m of vertical displacement.<br><br>**Sections:** This fault has 2 sections. Wong and others (1995 #1155) used the polarity of faults in the San Felipe fault zone to delineate two sections: down-to-the-east faults that form the western margin of the San Felipe graben (Santa Ana and Luce faults) are included in the Santa Ana section, and down-to-the-west faults that form the eastern margin of the graben (Algodones fault) are include in the Algodones section. They assumed that one of |

| | |
|---|---|
| | these sections is a "master fault" that controls both sections, but they did not have enough subsurface data to support either scenario. |
| **Name comments** | **General:** This complex of numerous, generally north-trending normal faults near Santa Ana Mesa was first mapped in detail by Soister (1952 #1418). Kelley (1954 #1222) followed Soister's mapping closely in his compilation, and applied the name San Felipe fault zone to these structures. Later maps by Smith and others (1970 #1125), Kelley (1977 #1106), and Kelley and Kudo (1978 #1307) show similar fault patterns. Kelley (1977 #1106) named many of the more prominent structures in the zone, such as the Santa Ana, Luce, Cocida, and Algodones faults and the San Felipe graben. In their compilation, Wong and others (1995 #1155) used the name "San Felipe fault zone".<br><br>**Section:** The Santa Ana section includes the Santa Ana, Luce, and Cocida faults of Kelley (1977 #1106), the Tamaya fault of Personius (2002 #7526), and numerous smaller displacements, generally down-to-the-east faults that form the west flank of the San Felipe graben. This section also includes an unnamed, west-dipping fault of uncertain origin about 8 km west of the main fault zone (Pazzaglia and others, 1997 #7525). |
| **County(s) and State(s)** | SANDOVAL COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | BASIN AND RANGE <br>SOUTHERN ROCKY MOUNTAINS <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Fault locations are good where faults cut volcanic rocks, but locations are poor in the less resistant Santa Fe Group rocks. Fault traces are from 1:24,000-scale maps of Pazzaglia and others (1997 #7525), Connell (1998 #7502), Chamberlin and others (1999 #7524), Personius (2002 #7526), and Kempter and others (2007 #7429). <P> |
| **Geologic setting** | The San Felipe fault zone is located in the western part of the Santo Domingo basin of the Rio Grande rift as defined by Smith and others (2001 #7438). The Santo Domingo basin links the en echelon Albuquerque and Española basins, and kinematic and paleostress evidence suggests that the basin functions as a relay that began to narrow in Plio-Pleistocene time (Minor and others, 2013 #7437). The fault zone forms a north-trending graben within the San Felipe volcanic field. Although Wong and others (1995 #1155) conclude that this graben is a minor sub-basin within |

| | |
|---|---|
| | the Rio Grande rift, the narrowing of the fault zone within the volcanic field indicates that the geometry of the fault zone may be in part controlled by volcanic activity (for example, van Wyk de Vries and Merle, 1996 #1422). <P> |
| **Length (km)** | This section is 44 km of a total fault length of 48 km. |
| **Average strike** | N5°E (for section) versus N1°E (for whole fault) |
| **Sense of movement** | Normal |
| **Dip** | 60°E–90°<br><br>*Comments:* An exposed section of the Luce fault along highway 44 west of Bernalillo yielded an east dip of 82° (Kelley, 1977 #1106). Connell (1998 #7502) reported east dips of 67–80° on the Luce fault in the Bernalillo 7.5-minute quadrangle, and Chamberlin and others (1999 #7524) reported east to southeast dips of 65–70° for the Cocida fault near Borrego Canyon in the Loma Creston quadrangle. Reported dips for the Santa Ana fault range from 65–80° toward the east or southeast (Chamberlin and others, 1999 #7524). Numerous fault exposures in Santa Fe Group rocks in the Santa Ana Pueblo quadrangle have dips of 45–85°E (Personius, 2002 #7526). <P> |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | The Luce and other faults that cut the basalt flows of the San Felipe volcanic field are well preserved as escarpments covered by basalt talus. The Santa Ana fault and other faults that are only located in Santa Fe Group rocks are poorly expressed, except where they are marked in places by clastic dikes (Soister, 1952 #1418) or strongly cemented zones (Minor and Hudson, 2006 #7246). Soister (1952 #1418) and Kelley (1977 #1106) measured average displacements of 15–30 m in basalts on most structures in the fault zone, and as much as 90–120 m on larger structures such as the Luce fault. <P> |
| **Age of faulted surficial deposits** | Faults in the Santa Ana section offset the 2.4-2.6 Ma (Bachman and Mehnert, 1978 #1265; Smith and Kuhle, 1998 #1771) basalts of the San Felipe volcanic field and underlying Santa Fe Group sedimentary rocks. Soister (1952 #1418) describes offset of his early Pleistocene Mesita Alta gravel and surface, which overlies San Felipe basalt flows in several places. |

| | |
|---|---|
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | undifferentiated Quaternary (<1.6 Ma)<br><br>*Comments:* No detailed studies of the age of most recent movement have been conducted. However, 90–120 m of post-San Felipe basalt displacement on some structures in this fault zone indicates a history of recurrent fault movements that probably continued at least into the early Pleistocene. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Wong and others (1995 #1155) estimated slip rates of 0.01–0.04 mm/yr based on 90–120 m of displacement that has occurred on the Luce fault since deposition of the San Felipe basalt (2.4–2.6 Ma) and similar data. They also concluded that it is likely that some of the major faults within the San Felipe fault zone act as independent rupture segments, but could not rule out the possibility that some faults rupture together. |
| **Date and Compiler(s)** | 2016<br>Stephen F. Personius, U.S. Geological Survey<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources<br>Keith I. Kelson, William Lettis & Associates, Inc. |
| **References** | #1265 Bachman, G.O., and Mehnert, H.H., 1978, New K-Ar dates and the late Pliocene to Holocene geomorphic history of the central Rio Grande region, New Mexico: Geological Society of America Bulletin, v. 89, p. 283-292.<br><br>#7524 Chamberlin, R.M., Pazzaglia, F.J., Wegmann, K.W., and Smith, G.A., 1999, Geologic map of the Loma Creston 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 25, scale 1:24,000.<br><br>#7502 Connell, S.D., 1998, Geology of the Bernalillo quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 16, scale 1:24,000.<br><br>#1222 Kelley, V.C., 1954, Tectonic map of a part of the upper Rio Grande area, New Mexico: U.S. Geological Survey Oil and Gas Investigations Map OM-157, 1 sheet, scale 1:190,080.<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1307 Kelley, V.C., and Kudo, A.M., 1978, Volcanoes and related basalts of |

Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Circular 156, 29 p., 2 pls.<br><br>#7429 Kempter, K., Osburn, G.R., Kelley, S., Rampey, M., Ferguson, C., and Gardner, J., 2007, Preliminary geologic map of the Bear Springs Peak quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-File Geologic Map 74, scale 1:24,000.<br><br>#7246 Minor, S.A., and Hudson, M.R., 2006, Regional survey of structural properties and cementation patterns of fault zones in the northern part of the Albuquerque Basin, New Mexico—Implications for ground-water flow: U.S. Geological Survey Professional Paper 1719, 32 p.<br><br>#7437 Minor, S.A., Hudson, M.R., Caine, J.S., and Thompson, R.A., 2013, Oblique transfer of extensional strain between basins of the middle Rio Grande rift, New Mexico—Fault kinematic and paleostress constrains, in Hudson, M.R., and Grauch, V.J.S., eds., New perspectives on Rio Grande rift basins: From Tectonics to Groundwater: Geological Society of America Special Paper 494, p. 345–382.<br><br>#7525 Pazzaglia, F.J., Pederson, J.L., Garcia, A.F., Koning, D.J., Formento-Trigilio, M.L., and Toya, C., 1997, Geologic map of the Jemez Pueblo 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 14, scale 1:24,000.<br><br>#7526 Personius, S.F., 2002, Geologic map of the Santa Ana Pueblo quadrangle, Sandoval County, New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-2405, scale 1:24,000.<br><br>#1771 Smith, G.A., and Kuhle, A.J., 1998, Geologic map of the Santo Domingo Southwest quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map OF-DM 26, 1 sheet, scale 1:24,000.<br><br>#7438 Smith, G.A., McIntosh, W.C., and Kuhle, A.J., 2001, Sedimentologic and geomorphic evidence for seesaw subsidence of the Santo Domingo accommodation-zone basin, Rio Grande rift, New Mexico: Geological Society of America Bulletin, v. 113, no. 5, p. 561–574.<br><br>#1125 Smith, R.L., Bailey, R.A., and Ross, C.S., 1970, Geologic map of the Jemez Mountains, New Mexico: U.S. Geological Survey Miscellaneous Investigations Map I-571, 1 sheet, scale 1:125,000.<br><br>#1418 Soister, P.E., 1952, Geology of Santa Ana Mesa and adjoining areas, Sandoval County, New Mexico: Albuquerque, University of New Mexico, unpublished M.S. thesis, 126 p., 2 pls., scale 1:62,500.<br><br>#1422 van Wyk de Vries, B., and Merle, O., 1996, The effects of volcanic constructs on rift fault patterns: Geology, v. 24, p. 643-646.<br><br>#1155 Wong, I., Kelson, K., Olig, S., Kolbe, T., Hemphill-Haley, M., Bott, J., Green, R., Kanakari, H., Sawyer, J., Silva, W., Stark, C., Haraden, C., Fenton, C., Unruh, J., Gardner, J., Reneau, S., and House, L., 1995, Seismic hazards evaluation of the Los Alamos National Laboratory: Technical report to Los Alamos National Laboratory, Los Alamos, New Mexico, February 24, 1995, 3 volumes, 12 pls., 16 appen.

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Sand Hill fault zone (Class A) No. 2039

**Last Review Date: 2016-06-28**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Personius, S.F., and Jochems, A.P., compilers, 2016, Fault number 2039, Sand Hill fault zone, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:29 AM.**

| | |
|---|---|
| **Synopsis** | The down-to-the-east Sand Hill fault zone extends from about 9 km south of the Sandoval-Bernalillo County line, northward along the Ceja del Rio Puerco to the vicinity of Cañada de las Milpas. Very little is known about the Quaternary history of the Sand Hill fault zone other than that it cuts probable early Pleistocene sand and gravel of the upper Santa Fe Group and is buried by younger surficial deposits. This fault zone is one of several north-trending faults that form the active western boundary of the Rio Grande rift in the northern part of the Albuquerque-Belen basin. |
| **Name comments** | The Sand Hill fault zone was first named, mapped, and described by Bryan and McCann (1937 #1288), has subsequently been mapped in various degrees of detail by Wright (1946 #1427), Kelley and others (1976 #1380, fig. 19), and Kelley (1954 #1222; 1977 #1106), and has more recently been mapped in detail in the Arroyo de las Calabacillas (previously Sky Village SE), Benavidez Ranch, Cerro Conejo (previously Sky Village NE), and The Volcanoes 7.5-minute quadrangles (Cather and others, 1997 #1763; Koning and others, 1998 #7375; Thompson and others, 2009 #7460; Koning and Jochems, 2014 #7507). As originally mapped by Bryan and McCann (1937 #1288), |

| | |
|---|---|
| | the Sand Hill fault zone extended about 10 km along the western edge of the Llano de Albuquerque. Bryan and McCann (1937 #1288) and Wright (1946 #1427) mapped the southern end of the Sand Hill fault zone 3–5 km south of the Bernalillo-Sandoval County line; Bryan and McCann (1937 #1288) state that the fault is covered by Pleistocene and younger alluvium southward. Kelley (1977 #1106, p. 48) used stratigraphic arguments to extend the Sand Hill fault zone a minimum of 12 km further south. Similarly at the north end, Kelley and others (1976 #1380, fig. 19) and Kelley (1977 #1106, p. 48) extended the Sand Hill fault zone along a northeast-trending splay across the Llano de Albuquerque. Kelley (1977 #1106, p. 48) also suggests that some of the down-to-the-east displacement associated with the Sand Hill fault zone is taken up by the Garcia and Tenorio faults, which extend northward another 23 km along the western edge of the Llano. Mapping in the Arroyo de las Calabacillas 7.5-minute quadrangle (Cather and others, 1997 #1763) shows that the Sand Hill fault zone does not trend northeastward across the Llano de Albuquerque, but rather continues northward along the Ceja del Rio Puerco to the vicinity of Cañada de las Milpas in the Cerro Conejo quadrangle (Koning and others, 1998 #7375). Wright (1946 #1427) included in the Sand Hill fault zone a northwest-trending (N20°W) down-to-the-east fault that is 1–2 km east of the Sand Hill fault zone. However, the trend of this fault, Wright's detailed description of a thick sequence of tectonically-derived sediment on the downthrown block, and mapping in the Arroyo de las Calabacillas 7.5-minute quadrangle (Cather and others, 1997 #1763) all indicate that this eastern fault strand is distinct from the Sand Hill fault zone and thus is mapped as a separate structure (Calabacillas section of the Jemez-San Ysidro fault [2029c]) in this compilation. |
| **County(s) and State(s)** | BERNALILLO COUNTY, NEW MEXICO <br>SANDOVAL COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | COLORADO PLATEAUS <br>BASIN AND RANGE <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Fault traces are from 1:24,000-scale maps by Cather and others (1997 #1763), Koning and others (1998 #7375), Thompson and others (2009 #7460), and Koning and Jochems (2014 #7507), as well as unpublished air-photo mapping by A.P. Jochems. <P> |

| | |
|---|---|
| **Geologic setting** | The Sand Hill fault zone is one of several north-trending faults that form the active western boundary of the Rio Grande rift in the northern part of the Albuquerque-Belen basin. <P> |
| **Length (km)** | 36 km. |
| **Average strike** | N6°E |
| **Sense of movement** | Normal |
| **Dip** | 54°–82° E.<br><br>*Comments:* Fault dips are from surface exposures (Wright, 1946 #1427, plate 8; Cather and others, 1997 #1763; Thompson and others, 2009 #7460; Koning and Jochems, 2014 #7507). <P> |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | The fault is well expressed as linear breaks in slope in the eroded Santa Fe Group badlands below the western edge of the Llano de Albuquerque. Bryan and McCann (1937 #1288) noted that their northernmost strand has been injected by a sand dike that is more erosion resistant than the surrounding rocks; Wright (1946 #1427) stated that all strands of the Sand Hill fault are marked by sand dikes. In places, preferential cementation related to groundwater flow has formed prominent wall- or finger-like features in the fault zone (Mozley and Goodwin, 1995 #7508). No fault scarps on surficial deposits have been described, suggesting a lack of recency to the faulting. <P> |
| **Age of faulted surficial deposits** | The trace of the Sand Hill fault zone as originally mapped by Bryan and McCann (1937 #1288) lies entirely within the Upper Buff Member of the Santa Fe Formation, which is roughly correlative with the Ceja Formation of the Upper Santa Fe Group (Kelley, 1977 #1106; Hawley and others, 1991 #1302; Connell, 2008 #7506). In places the upper part of these deposits is early Pleistocene in age. No faulting of younger surficial deposits has been described. |
| **Historic earthquake** | |

| | |
|---|---|
| **Most recent prehistoric deformation** | undifferentiated Quaternary (<1.6 Ma)<br><br>*Comments:* The only deposits documented as offset by the Sand Hill fault zone are early Pleistocene to Pliocene in age. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* No detailed studies of fault offset or age of offset deposits are available; slip rate estimate is based on lack of fault scarps and low rates of slip on other faults in this part of the Rio Grande rift. |
| **Date and Compiler(s)** | 2016<br>Stephen F. Personius, U.S. Geological Survey<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #1288 Bryan, K., and McCann, F.T., 1937, The Ceja del Rio Puerco—A border feature of the Basin and Range province in New Mexico, Part I, Stratigraphy and structure: Journal of Geology, v. 45, p. 801-828.<br><br>#1763 Cather, S.M., Connell, S.D., Heynekamp, M.R., and Goodwin, L.B., 1997, Geology of the Arroyo de las Calabacillas [Sky Village SE] 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 9, 8 p. pamphlet, 1 sheet, scale 1:24,000.<br><br>#7506 Connell, S.D., 2008, Refinements to the stratigraphic nomenclature of the Santa Fe Group, northwestern Albuquerque Basin, New Mexico: New Mexico Geology, v. 30, p. 14–35.<br><br>#1302 Hawley, J.W., Love, D.W., Betancourt, J.L., Turner, R.M., and Tharnstrom, S., 1991, Quaternary and Neogene landscape evolution—A transect across the Colorado Plateau and Basin and Range provinces in west-central and central New Mexico, in Julian, B., and Zidek, J., eds., Field guide to geologic excursions in New Mexico and adjacent areas of Texas and Colorado: New Mexico Bureau of Mines and Mineral Resources Bulletin 137, p. 105-148.<br><br>#1222 Kelley, V.C., 1954, Tectonic map of a part of the upper Rio Grande area, New Mexico: U.S. Geological Survey Oil and Gas Investigations Map OM-157, 1 sheet, scale 1:190,080.<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1380 Kelley, V.C., Woodward, L.A., Kudo, A.M., and Callender, J.F., 1976, Guidebook to Albuquerque basin of the Rio Grande rift, New Mexico: New Mexico Bureau of Mines and Mineral |

Resources Circular 153, 31 p.<br><br>#7507 Koning, D.J., and Jochems, A.P., 2014, Geologic map of the Benavidez Ranch 7.5-minute quadrangle, Bernalillo and Sandoval Counties, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-File Geologic Map 234, scale 1:24,000.<br><br>#7375 Koning, D.J., Pederson, J., Pazzaglia, F.J., and Cather, S.M., 1998, Geology of the Cerro Conejo (Sky Village NE) 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-file Geologic Map 45, scale 1:24,000.<br><br>#1400 Machette, M.N., 1978, Geologic map of the San Acacia quadrangle, Socorro County, New Mexico: U.S. Geological Survey Geologic quadrangle Map GQ-1415, 1 sheet, scale 1:24,000.<br><br>#7508 Mozley, P.S., and Goodwin, L.B., 1995, Patterns of cementation along a Cenozoic normal fault: A record of paleoflow orientations: Geology, v. 23, p. 539-542.<br><br>#7460 Thompson, R.A., Shroba, R.R., Menges, C., Schmidt, D.L., Personius, S.F., and Brandt, T.R., 2009, Geologic map of the Volcanoes quadrangle, Bernalillo and Sandoval Counties, New Mexico: U.S. Geological Survey Scientific Investigations Map SIM-3083, scale 1:24,000.<br><br>#1427 Wright, H.E., Jr., 1946, Tertiary and Quaternary geology of the lower Rio Puerco area, New Mexico: Geological Society of America Bulletin, v. 57, p. 383-456.

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Santa Fe fault (Class A) No. 2123

**Last Review Date: 2015-12-21**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Personius, S.F., and Jochems, A.P., compilers, 2015, Fault number 2123, Santa Fe fault, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:30 AM.**

| | |
|---|---|
| **Synopsis** | The Santa Fe fault forms the western margin of the Rio Grande rift in the central Albuquerque-Belen basin. The fault has been quite active in the Pliocene and early Pleistocene, based on offset of upper Santa Fe Group (Sierra Ladrones Formation) sediment. Other indirect evidence of Quaternary offset includes differences in the elevation of the "Ortiz surface" across the fault trace and the geometry of spring deposits found along the fault. However, no scarps on surficial deposits have been observed along the trace of the Santa Fe fault. |
| **Name comments** | The Santa Fe fault forms part of the western margin of the Rio Grande rift and the Albuquerque basin (Machette, 1982 #1401; Machette and McGimsey, 1983 #1024). The structure was originally named the Carrizo fault by Wright (1946 #1427), was later renamed the Santa Fe fault by Kelley and Wood (1946 #1379), and was included on subsequent compilations (Kelley, 1954 #1222; Kelley, 1977 #1106). The Santa Fe fault places Pliocene to early Pleistocene (Lozinsky and Tedford, 1991 #1399) sediment of the Sierra Ladrones Formation down-to-the-east against older rocks (Machette and McGimsey, 1983 #1024; Ricketts and Karlstrom, 2014 #7300). |

| | |
|---|---|
| | **Fault ID:** Fault no. 2 of Machette (1982 #1401), fault no. 1 of Machette and McGimsey (1983 #1024). |
| **County(s) and State(s)** | VALENCIA COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | BASIN AND RANGE <br>COLORADO PLATEAUS <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* No scarps on surficial deposits have been observed; the fault had been shown as dashed along most of its trace on published maps until mapping was completed along much of its trace by Ricketts and Karlstrom (2014 #7300). Fault location is taken from this 1:24,000 map. <P> |
| **Geologic setting** | The Santa Fe fault forms the western margin of the Rio Grande rift and the Albuquerque basin; this structure separates the rift from the edge of the Colorado Plateau to the west. <P> |
| **Length (km)** | 30 km. |
| **Average strike** | N4°E |
| **Sense of movement** | Normal |
| **Dip** | 45°–80° E<br><br>*Comments:* Dip data are from Wright (1946 #1427), Callender and Zilinski, (1976 #1289), Russell and Snelson (1994 #1186), and Ricketts and Karlstrom (2014 #7300). <P> |
| **Paleoseismology studies** | <P> |

| | |
|---|---|
| **Geomorphic expression** | No scarps have been recognized on surficial deposits along the Santa Fe fault, but the fault forms a bedrock escarpment along the northern half of its trace. <P> |
| **Age of faulted surficial deposits** | The Santa Fe fault offsets Pliocene to early Pleistocene (Lozinsky and Tedford, 1991 #1399) sediment of the Sierra Ladrones Formation down-to-the-east against older rocks (Machette and McGimsey, 1983 #1024; Ricketts and Karlstrom, 2014 #7300. Other indirect evidence of Quaternary offset includes differences in the elevation of the Pliocene (?) Ortiz surface across the fault trace (Kelley and others, 1976 #1380; Kelley, 1977 #1106, p. 28) and the geometry of spring deposits found along the fault (Callender and Zilinski, 1976 #1289). |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | undifferentiated Quaternary (<1.6 Ma)<br><br>*Comments:* Timing estimate is based on offset of Pliocene-Pleistocene Sierra Ladrones Formation sediment (Machette and McGimsey, 1983 #1024; Ricketts and Karlstrom, 2014 #7300). <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* No detailed studies of fault offset or age of offset deposits are available; low slip-rate category is assigned based on about 30 m offset of 3.7-Ma basalt (Bachman and Mehnert, 1978 #1265) at the mouth of Arroyo Comanche (Kelley, 1977 #1106; Bachman and Mehnert, 1978 #1265). |
| **Date and Compiler(s)** | 2015<br>Stephen F. Personius, U.S. Geological Survey<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #1265 Bachman, G.O., and Mehnert, H.H., 1978, New K-Ar dates and the late Pliocene to Holocene geomorphic history of the central Rio Grande region, New Mexico: Geological Society of America Bulletin, v. 89, p. 283-292.<br><br>#1289 Callender, J.F., and Zilinski, R.E., Jr., 1976, Kinematics of Tertiary and Quaternary deformation along the |

eastern edge of the Lucero uplift, central New Mexico, in Woodward, L.A., and Northrop, S.A., eds., Tectonics and mineral resources of southwestern North America: New Mexico Geological Society Special Publication 6, p. 53-61.<br><br>#1222 Kelley, V.C., 1954, Tectonic map of a part of the upper Rio Grande area, New Mexico: U.S. Geological Survey Oil and Gas Investigations Map OM-157, 1 sheet, scale 1:190,080.<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1379 Kelley, V.C., and Wood, G.H., Jr., 1946, Geology of the Lucero uplift, Valencia, Socorro, and Bernalillo Counties, New Mexico: U.S. Geological Survey Oil and Gas Investigations Map 47, 1 sheet, scale 1:63,360.<br><br>#1380 Kelley, V.C., Woodward, L.A., Kudo, A.M., and Callender, J.F., 1976, Guidebook to Albuquerque basin of the Rio Grande rift, New Mexico: New Mexico Bureau of Mines and Mineral Resources Circular 153, 31 p.<br><br>#1399 Lozinsky, R.P., and Tedford, R.H., 1991, Geology and paleontology of the Santa Fe Group, southwestern Albuquerque basin, Valencia County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Bulletin 132, 35 p., 3 pls., scale 1:24,000.<br><br>#1401 Machette, M.N., 1982, Quaternary and Pliocene faults in the La Jencia and southern part of the Albuquerque-Belen basins, New Mexico—Evidence of fault history from fault-scarp morphology and Quaternary geology, in Grambling, J.A., and Wells, S.G., eds., Albuquerque Country II: New Mexico Geological Society, 33rd Field Conference, November 4-6, 1982, Guidebook, p. 161-169.<br><br>#1024 Machette, M.N., and McGimsey, R.G., 1983, Map of Quaternary and Pliocene faults in the Socorro and western part of the Fort Sumner 1° x 2° quadrangles, central New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-1465-A, 12 p. pamphlet, 1 sheet, scale 1:250,000.<br><br>#7300 Ricketts, J.W., and Karlstrom, K.E., 2014, Geologic map of the South Garcia SE 7.5-minute quadrangle, Valencia County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-File Geologic Map 246, scale 1:24,000.<br><br>#1186 Russell, L.R., and Snelson, S., 1994, Structure and tectonics of the Albuquerque basin segment of the Rio Grande rift—Insights from reflection seismic data, in Keller, G.R., and Cather, S.M., eds., Basins of the Rio Grande rift—Structure, stratigraphy, and tectonic setting: Geological Society of America Special Paper 291, p. 83–112.<br><br>#1427 Wright, H.E., Jr., 1946, Tertiary and Quaternary geology of the lower Rio Puerco area, New Mexico: Geological Society of America Bulletin, v. 57, p. 383-456.

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## unnamed fault of Bonita Canyon (Class B) No. 2144

**Last Review Date: 2016-04-22**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Machette, M.N., and Jochems, A.P., compilers, 2016, Fault number 2144, unnamed fault of Bonita Canyon, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:30 AM.**

| | |
|---|---|
| **Synopsis** | Fault scarp-like features have been mapped on the late Quaternary Twin Craters and El Calderon basalt flows of El Malpais lava field. The associated fault may represent reactivation of a bedrock fault that is concealed in Bonita Canyon, but which must juxtapose Precambrian rock on the west against Paleozoic rock on the east. However, similar mapped features within El Malpais lava field are considered by Levish and others (1992 #1715) to be related to volcanic processes. No detailed study of the fault has been conducted to confirm its origin or document the amount of vertical displacement that may be associated with it. Thus, the feature is herein considered to be of suspect origin. |

| | |
|---|---|
| **Name comments** | This fault was first mapped by Maxwell (1986 #1720). Levish and others (1992 #1715) characterized it a non-tectonic feature related to volcanic processes as part of a regional reconnaissance for a dam-hazards study. Levish and others (1992 #1715) referred to it as one of the faults in the Zuni-Bandera volcanic field. This fault forms a north-trending scarp (?) across the Twin Craters and El Calderon lava flows south of Bonita Canyon. The scarp is located at the south end of Cerritos de Jaspe (a prominent, west-facing ridge), which is just east of Bonita Canyon. |
| **County(s) and State(s)** | CIBOLA COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | COLORADO PLATEAUS <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Trace from 1:62,500-scale geologic map of Maxwell (1986 #1720) combined with accurate placement using photogrammetric methods. <P> |
| **Geologic setting** | The fault is in Quaternary (undifferentiated) basalt flows according to the mapping of Maxwell (1986 #1720). It trends north on the basalts, and northwest up Bonita Canyon where it juxtaposes Precambrian rock on the west against Paleozoic rock on the east (Timmons and Cikoski, 2012 #7426). <P> |
| **Length (km)** | 9 km. |
| **Average strike** | N11°W |
| **Sense of movement** | Normal<br><br>*Comments:* Mapping by Maxwell (1986 #1720) and Timmons and Cikoski (2012 #7426) indicates that Paleozoic bedrock is down-dropped on the eastern side of the fault relative to Precambrian bedrock along a northern (concealed) extension of the fault. Conversely, where the fault crosses the El Calderon flow it appears to form a west-facing scarp. On the basis of this observation and similarity to other Cenozoic faults in the region, we infer that the fault has normal dip slip movement. <P> |

| | |
|---|---|
| **Dip Direction** | Unknown |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | The fault forms a 2-km-long north-trending scarp (?) on basaltic lava flows (Maxwell, 1986 #1720). Levish and others (1992 #1715) suggested that the fault is related to volcanic processes and is not of tectonic origin. No measurements of any vertical displacement have been made across the fault to confirm the amount or direction of possible movement. <P> |
| **Age of faulted surficial deposits** | Maxwell (1986 #1720) mapped the fault as offsetting the Twin Craters lava flow, dated at approximately 17_19 ka using radiocarbon and surface cosmogenic techniques (Laughlin and WoldeGabriel, 1997 #7425; Dunbar and Phillips, 2004 #7424). In addition, just south of New Mexico State Highway 53 the fault is mapped as crossing a small tongue of El Calderon flow, dated at 115–120 ka using paleomagnetic constraints (Cascadden and others, 1997 #7423). |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | undifferentiated Quaternary (<1.6 Ma)<br><br>*Comments:* The fault scarp-like features are present on two Quaternary basalt flows dated at approximately 17–19 and 115–120 ka (Cascadden and others, 1997 #7423; Laughlin and WoldeGabriel, 1997 #7425; Dunbar and Phillips, 2004 #7424). <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* No measurement of offset across the fault has been reported. The fault does not appear to form a high or even moderate (>5 m) scarp on aerial photographs. Thus, it seems reasonable that slip rates associated with this suspect fault would be in the low slip-rate category (<0.2 mm/yr). |

| | |
|---|---|
| **Date and Compiler(s)** | 2016<br>Michael N. Machette, U.S. Geological Survey, Retired<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #7423 Cascadden, T.E., Geissman, J.W., Kudo, A.M., and Laughlin, A.W., 1997, El Calderon cinder cone and related basalt flows, in Mabery, K., compiler, Natural History of El Malpais National Monument: New Mexico Bureau of Mines and Mineral Resources Bulletin 156, p. 41-–51.<br><br>#7424 Dunbar, N.W., and Phillips, F.M., 2004, Cosmogenic <sup>36</sup>Cl ages of lava flows in the Zuni-Bandera volcanic field, north-central New Mexico, U.S.A., in Cather, S.M., McIntosh, W.C., and Kelley, S.A., eds., Tectonics, geochronology, and volcanism in the Southern Rocky Mountains and Rio Grande Rift: New Mexico Bureau of Geology and Mineral Resources Bulletin 160, p. 309–317.<br><br>#7425 Laughlin, A.W., and WoldeGabriel, G., 1997, Dating the Zuni-Bandera volcanic field, in Mabery, K., compiler, Natural History of El Malpais National Monument: New Mexico Bureau of Mines and Mineral Resources Bulletin 156, p. 25–29.<br><br>#1715 Levish, D.R., Vetter, U.R., Ake, J.P., and Piety, L.A., 1992, Seismotectonic study for Black Rock Dam, Bureau of Indian Affairs, Pueblo of Zuni, New Mexico: Bureau of Reclamation Seismotectonic Report 92-3, 62 p.<br><br>#1720 Maxwell, C.H., 1986, Geologic map of El Malpais Lava Field and surrounding areas, Cibola County, New Mexico: U.S. Geological Survey Miscellaneous Investigations Map I-1595, 1 sheet, scale 1:62,500.<br><br>#7426 Timmons, J.M., and Cikoski, C.T., 2012, Geologic map of the San Rafael quadrangle, Cibola County, New Mexico: New Mexico Bureau of Geology and Mineral Resources Open-File Geologic Map 232, scale 1:24,000. |

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## unnamed faults near Albuquerque Volcanoes (Class A) No. 2049

**Last Review Date: 2016-06-26**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

*citation for this record:* Personius, S.F., and Jochems, A.P., compilers, 2016, Fault number 2049, unnamed faults near Albuquerque Volcanoes, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:31 AM.

| | |
|---|---|
| **Synopsis** | Several unnamed north-trending normal faults are located near the Albuquerque Volcanoes. The basaltic volcanic field associated with the volcanoes is apparently confined in a broad graben, defined on the west by the down-to-the-east County Dump fault [2038] and on the east by the down-to-the-west East Paradise fault zone [2040]. Between these two flanking faults there is a series of smaller fault blocks and grabens. Most of these faults appear to be buried by basalt flows dated at about 155 ka. However, these faults can be mapped beneath the flows because most are marked by linear breaks in slope, indicating that preexisting fault scarps disrupted the flows during emplacement. The extent of some buried faults are also evident in high resolution aeromagnetic data. At least two faults are marked by more pronounced linear scarps that indicate small (1–2 m) post-basalt (155–218 ka) movements: a short down-to-the-east fault located between the East [2040] and West Paradise [2042] fault zones clearly offsets basalt in two places along the eastern edge of the volcanic field, and a longer north-trending down-to-the-west fault marked by small scarps in basalt bisects the volcanic field west of the West Paradise fault. This fault may have been the source of the 1978–1979 earthquake swarm near the Albuquerque Volcanoes. Latest movements on both the County Dump [2038] and East Paradise [2040] faults also post-date basalt emplacement. |
| **Name comments** | This group of structures is a series of north-trending normal faults on the east side of the Albuquerque Volcanoes. Some of these faults are included in the West Mesa fault zone of Wong and others (1995 #1155) and Hawley and Whitworth (1996 #1303). |
| **County(s) and State(s)** | SANDOVAL COUNTY, NEW MEXICO <br>BERNALILLO COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | BASIN AND RANGE <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Fault traces from 1:24,000-scale maps of Connell and others (1998 #7490), Shroba and others (2003 #7459), and Thompson and others (2009 #7460). The locations of some traces beneath the volcanic field are based on high-resolution aeromagnetic data (U.S. Geological Survey and SIAL Geosciences Inc., 1997 #1722; Grauch and Millegan, 1998 #1721). <P> |

| | |
|---|---|
| **Geologic setting** | These structures are intrabasin faults in the central part of the Albuquerque-Belen basin of the Rio Grande rift. The broad graben that confines the Albuquerque Volcanoes volcanic field suggests that movement on some faults may be associated with magmatic activity. Recent seismicity may be associated with one of these intrabasin structures. An earthquake swarm in 1978–1979 near the southwestern margin of the volcanic field yielded a composite fault-plane solution with a preferred nodal plane striking N. 5° E. and dipping 74° W. (Jaksha and others, 1981 #1760). This fault plane projects to the surface very near the surface trace of an unnamed, 20 km long fault that lies 0.5 km east of the Albuquerque Volcanoes cinder cones. Northeast of the cinder cones, this fault is marked by small scarps on basalt that indicate post-basalt displacement. The County Dump fault [2038] is located between the surface trace of this fault and the surface projection of the earthquake 1978–1979 earthquake swarm, suggesting that the County Dump may sole into the fault at depth. <P> |
| **Length (km)** | 34 km. |
| **Average strike** | N5°W |
| **Sense of movement** | Normal |
| **Dip Direction** | E; W |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | Outside of the volcanic field, these faults are well expressed as eroded fault scarps on sediment of the upper Santa Fe Group and overlying surficial deposits. Within the Albuquerque Volcanoes volcanic field, these faults are marked by linear breaks in slope and minor fault scarps. Most breaks in slope along these faults appear to be preexisting scarps that disrupted the flow of basalt during eruptions to the west. At least two faults are marked by more pronounced linear scarps that indicate small post-basalt movements. Most of the fault traces in the volcanic field have been partly covered by eolian sand. <P> |
| **Age of faulted surficial deposits** | At least two of these faults offset the basalt of the Albuquerque Volcanoes volcanic field; these rocks have been dated by several methods at about 155–218 ka (Geissman and others, 1990 #1297; Peate and others, 1996 #1411; |

| | |
|---|---|
| | Singer and others, 2008 #7492). Most of the faults cut sediment of the upper Santa Fe Group and surficial deposits that predate emplacement of the basalts. |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | middle and late Quaternary (<750 ka)<br><br>*Comments:* At least two faults in this group offset the 155–218-ka basalts of the Albuquerque Volcanoes volcanic field, indicating probable late Pleistocene displacement. Most of the other faults have most recent movements that predate 155–218 ka. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Two of these structures offset the 155–218-ka basalts of the Albuquerque Volcanoes volcanic field by about 1–2 m, which suggests a low slip rate. |
| **Date and Compiler(s)** | 2016<br>Stephen F. Personius, U.S. Geological Survey<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #7490 Connell, S.D., Allen, B.D., Hawley, J.W., and Shroba, R.R., 1998, Geology of the Albuquerque West 7.5-minute quadrangle, Bernalillo County, New Mexico: New Mexico Bureau of Mines and Mineral Open-File Geologic Map 17, scale 1:24,000.<br><br>#1297 Geissman, J.W., Brown, L., Turrin, B.D., McFadden, L.D., and Harlan, S.S., 1990, Brunhes chron excursion/polarity episode recorded during the late Pleistocene, Albuquerque Volcanoes, New Mexico, USA: Geophysical Journal International, v. 102, p. 73-88.<br><br>#1721 Grauch, V.J.S., and Millegan, P.S., 1998, Mapping intrabasinal faults from high-resolution aeromagnetic data: The Leading Edge, v. 17, p. 53-55.<br><br>#1303 Hawley, J.W., and Whitworth, T.M., compilers, 1996, Hydrogeology of potential recharge areas for the basin- and valley-fill aquifer systems, and hydrogeochemical modeling of proposed artificial recharge of the upper Santa Fe aquifer, northern Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Report 402-D, 575 p.<br><br>#1760 Jaksha, L.H., Locke, J., and Gebhart, H.J., 1981, Microearthquakes |

near the Albuquerque volcanoes, New Mexico: Geological Society of America Bulletin, v. 92, p. 31-36.<br><br>#1411 Peate, D.W., Chen, J.H., Wasserburg, G.J., Papanastassiou, D.A., and Geissman, J.W., 1996, 238U-230Th dating of a geomagnetic excursion in Quaternary basalts of the Albuquerque Volcanoes Field, New Mexico (USA): Geophysical Research Letters, v. 23, p. 2271-2274.<br><br>#7459 Shroba, R.R., Thompson, R.A., Schmidt, D.L., Personius, S.F., Maldonado, F., and Brandt, T.R., 2003, Geologic map of the La Mesita Negra SE quadrangle, Bernalillo County, New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-2416, scale 1:24,000.<br><br>#7492 Singer, B.S., Jicha, B.R., Kirby, B.T., Geissman, J.W., Herrero-Bervera, E., 2008, <sup>40</sup>Ar/<sup>39</sup>Ar dating links Albuquerque Volcanoes to the Pringle Falls excursion and the Geomagnetic Instability Time Scale: Earth and Planetary Science Letters, v. 267, p. 584–595.<br><br>#7460 Thompson, R.A., Shroba, R.R., Menges, C., Schmidt, D.L., Personius, S.F., and Brandt, T.R., 2009, Geologic map of the Volcanoes quadrangle, Bernalillo and Sandoval Counties, New Mexico: U.S. Geological Survey Scientific Investigations Map SIM-3083, scale 1:24,000.<br><br>#1722 U.S. Geological Survey, and SIAL Geosciences, Inc., 1997, Description of digital aeromagnetic data collected north and west of Albuquerque, New Mexico: U.S. Geological Survey Open-File Report 97-286, 40 p.<br><br>#1155 Wong, I., Kelson, K., Olig, S., Kolbe, T., Hemphill-Haley, M., Bott, J., Green, R., Kanakari, H., Sawyer, J., Silva, W., Stark, C., Haraden, C., Fenton, C., Unruh, J., Gardner, J., Reneau, S., and House, L., 1995, Seismic hazards evaluation of the Los Alamos National Laboratory: Technical report to Los Alamos National Laboratory, Los Alamos, New Mexico, February 24, 1995, 3 volumes, 12 pls., 16 appen.

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## unnamed faults near Picuda Peak (Class A) No. 2041

**Last Review Date: 2016-06-26**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Personius, S.F., and Jochems, A.P., compilers, 2016, Fault number 2041, unnamed faults near Picuda Peak, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:32 AM.**

| | |
|---|---|
| **Synopsis** | Near Picuda Peak there is a group of down-to-the-east and down-to-the-west, north trending normal faults that offset coarse gravels and underlying sands of the upper Santa Fe Group. Most of these faults trend to the northeast at their southern ends near Picuda Peak; further north, they trend generally north. Detailed mapping of the nearly complete exposures of the Santa Fe Group section in the Rincones de Zia show very closely spaced normal faults, most of which have displacements of only a few meters. These faults generally offset the uppermost coarse gravel of the Upper Santa Fe Group by a few tens of meters. |
| **Name comments** | This group of faults are herein named for their proximity to Picuda Peak. Some faults near Picuda Peak were previously described by Black and Hiss (1974 #1287) and Kelley (1977 #1106). These structures were mapped in detail by Manley (1978 #1404) in the Bernalillo NW 7.5-minute quadrangle and by Personius and others (2000 #1413) in the Loma Machete quadrangle. |

| | |
|---|---|
| **County(s) and State(s)** | SANDOVAL COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | BASIN AND RANGE <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Fault traces are from 1:24,000-scale mapping of Manley (1978 #1404) in the Bernalillo NW quadrangle and Personius and others (2000 #1413) in the Loma Machete quadrangle. <P> |
| **Geologic setting** | Near Picuda Peak there is a group of down-to-the-east and down-to-the-west, north trending intrabasin faults near the northern margin of the Albuquerque-Belen basin in the Rio Grande rift. In previous publications, these faults were located near the crest of the Ziana anticline (Black and Hiss, 1974 #1287; Kelley and others, 1976 #1380; Kelley, 1977 #1106), but work by Personius and others (2000 #1413) indicates that opposing dips in the region that were thought to be the expression of a large fold may instead be related to intense normal faulting and block rotation. <P> |
| **Length (km)** | 10 km. |
| **Average strike** | N2°E |
| **Sense of movement** | Normal |
| **Dip** | 43–75° E., 47–87° W.<br><br>*Comments:* Numerous fault exposures indicate that these faults are usually steeply dipping (Personius and others, 2000 #1413). <P> |
| **Paleoseismology studies** | <P> |

| | |
|---|---|
| **Geomorphic expression** | Most faults form narrow topographic ridges and valleys that correlate with sense of fault displacement. Topographic expression is lost, but numerous fault exposures and juxtaposed bedrock mark these faults in the badlands of the Rincones de Zia. <P> |
| **Age of faulted surficial deposits** | The ages of offset deposits are poorly known, but the uppermost sand and gravel of the upper Santa Fe Group in this area are thought to be early Pleistocene in age (Personius and others, 2000 #1413). |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | undifferentiated Quaternary (<1.6 Ma)<br><br>*Comments:* The unnamed faults near Picuda Peak offset early Pleistocene sediments of the upper Santa Fe Group a few tens of meters but do not appear to offset younger surficial deposits (Personius and others, 2000 #1413). <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Offsets of early Pleistocene gravels across individual faults are probably no more than 20–30 m. |
| **Date and Compiler(s)** | 2016<br>Stephen F. Personius, U.S. Geological Survey<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #1287 Black, B.A., and Hiss, W.L., 1974, Structure and stratigraphy in the vicinity of the Shell Oil Co. Santa Fe Pacific No. 1 test well, southern Sandoval County, New Mexico, in Siemers, C.T., Woodward, L.A., and Callender, J.F., eds., Ghost Ranch central-northern New Mexico: New Mexico Geological Society, 25th Field Conference, October 10-12, 1974, Guidebook, p. 365-370.<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1380 Kelley, V.C., Woodward, L.A., Kudo, A.M., and Callender, J.F., 1976, Guidebook to Albuquerque basin of |

| | |
|---|---|
| | the Rio Grande rift, New Mexico: New Mexico Bureau of Mines and Mineral Resources Circular 153, 31 p.<br><br>#1404 Manley, K., 1978, Geologic map of Bernalillo NW quadrangle, Sandoval County, New Mexico: U.S. Geological Survey Geologic quadrangle Map GQ-1446, 1 sheet, scale 1:24,000.<br><br>#1413 Personius, S.F., Machette, M.N., and Stone, B.D., 2000, Preliminary geologic map of the Loma Machete quadrangle, Sandoval County, New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-2334, scale 1:24,000. |

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## unnamed faults near Star Heights (Class A) No. 2048

**Last Review Date: 2016-06-26**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Personius, S.F., and Jochems, A.P., compilers, 2016, Fault number 2048, unnamed faults near Star Heights, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:32 AM.**

| | |
|---|---|
| **Synopsis** | This group of north-trending, mostly down-to-the-east normal faults offsets upper Santa Fe Group sediments, the Llano de Albuquerque, and younger piedmont deposits near the neighborhood of Star Heights. Individual faults have displaced upper Santa Fe Group sediments of a few tens of meters, 15–20 m of the Llano de Albuquerque, and 5–10 m in probable middle Pleistocene piedmont deposits. |
| **Name comments** | These north-trending normal faults include parts of the Star Heights fault of Kelley (1977 #1106) and Hawley and Whitworth (1996 #1303). Detailed mapping by Cather and others (1997 #1763), Personius and others (2000 #1413), and Thompson and others (2009 #7460) indicate that the Star Heights fault mapped by Kelley (1977 #1106) and Hawley and Whitworth (1996 #1303) includes parts of at least two separate faults, so this name has been abandoned. |
| **County(s) and State(s)** | BERNALILLO COUNTY, NEW MEXICO <br>SANDOVAL COUNTY, NEW MEXICO <br> |

| | |
|---|---|
| **Physiographic province(s)** | BASIN AND RANGE <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Fault traces from 1:24,000-scale mapping of Cather and others (1997 #1763), Personius and others (2000 #1413), and Thompson and others (2009 #7460) supplemented with additional photogrammetric analysis by Jochems. The locations of some fault traces are based on high-resolution aeromagnetic data (U.S. Geological Survey and SIAL Geosciences Inc., 1997 #1722; Grauch and Millegan, 1998 #1721). <P> |
| **Geologic setting** | These structures are intrabasin faults in the northern part of the Albuquerque-Belen basin of the Rio Grande rift. <P> |
| **Length (km)** | 18 km. |
| **Average strike** | N5°E |
| **Sense of movement** | Normal |
| **Dip** | 70° E.<br><br>*Comments:* Dip data are from Personius and others (2000 #1413). <P> |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | These faults offset upper Santa Fe Group sediment, form broad scarps on the Llano de Albuquerque, and form steeper, smaller scarps on younger piedmont deposits. <P> |
| **Age of faulted surficial deposits** | These faults offset early Plio-Pleistocene upper Santa Fe Group sediment, the early Pleistocene Llano de Albuquerque, and younger piedmont deposits (Personius and others, 2000 #1413). The faulted piedmont deposits are characterized by well-developed (stage III) calcic soils, so they probably are middle Pleistocene in age. |

| | |
|---|---|
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | middle and late Quaternary (<750 ka)<br><br>*Comments:* Some of these structures offset the early Pleistocene Llano de Albuquerque 15–20 m and middle Pleistocene piedmont deposits 5–10 m; these data indicate a history of recurrent movement that, in some cases, possibly extend into the late Pleistocene. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Inferred low slip rate is based on presence of broad scarps on the Llano de Albuquerque that offset the surface 15–20 m. |
| **Date and Compiler(s)** | 2016<br>Stephen F. Personius, U.S. Geological Survey<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #1763 Cather, S.M., Connell, S.D., Heynekamp, M.R., and Goodwin, L.B., 1997, Geology of the Arroyo de las Calabacillas [Sky Village SE] 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 9, 8 p. pamphlet, 1 sheet, scale 1:24,000.<br><br>#1721 Grauch, V.J.S., and Millegan, P.S., 1998, Mapping intrabasinal faults from high-resolution aeromagnetic data: The Leading Edge, v. 17, p. 53-55.<br><br>#1303 Hawley, J.W., and Whitworth, T.M., compilers, 1996, Hydrogeology of potential recharge areas for the basin- and valley-fill aquifer systems, and hydrogeochemical modeling of proposed artificial recharge of the upper Santa Fe aquifer, northern Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Report 402-D, 575 p.<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1413 Personius, S.F., Machette, M.N., and Stone, B.D., 2000, Preliminary geologic map of the Loma Machete quadrangle, Sandoval County, New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-2334, scale 1:24,000.<br><br>#7460 Thompson, R.A., Shroba, R.R., Menges, C., Schmidt, D.L., Personius, S.F., and Brandt, T.R., 2009, |

| | |
|---|---|
| | Geologic map of the Volcanoes quadrangle, Bernalillo and Sandoval Counties, New Mexico: U.S. Geological Survey Scientific Investigations Map SIM-3083, scale 1:24,000.<br><br>#1722 U.S. Geological Survey, and SIAL Geosciences, Inc., 1997, Description of digital aeromagnetic data collected north and west of Albuquerque, New Mexico: U.S. Geological Survey Open-File Report 97-286, 40 p. |

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## unnamed faults of El Malpais lava field (Class B) No. 2146

**Last Review Date: 2016-04-22**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Machette, M.N., and Jochems, A.P., compilers, 2016, Fault number 2146, unnamed faults of El Malpais lava field, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:32 AM.**

| | |
|---|---|
| **Synopsis** | These three groups of suspect faults form numerous fissures and cracks in early Quaternary basalt flows of El Malpais lava field. They may include pressure ridges and collapsed lava tubes that give the expression of tectonic activity, but could be related to volcanic processes. Thus, these features are considered to be of suspect origin. No detailed studies of the features have been conducted to confirm their origin or document the amount of vertical displacement, if any, that may be associated with them. |
| **Name comments** | These faults were first mapped by Maxwell (1986 #1720); additional structures were mapped to the west by Baldridge and others (1989 #1741). Levish and others (1992 #1715), as part of a regional reconnaissance for a dam-hazards study, characterized them as non-tectonic features related to volcanic processes. Levish and others (1992 #1715) referred to the features as "Faults in the Zuni-Bandera volcanic field". The faults form four groups on El Malpais lava field. The southern group trends north across the North Plains, the main (longest) feature of which is named La Rendija. The southern extent of these faults is approximately 10 km south of the map area of Maxwell (1986 #1720). The northwestern group is comprised of two short north-northeast trending faults and associated |

| | |
|---|---|
| | fissure-like features located about 3 km south and southwest of Hoya de Cibola (Maxwell, 1986 #1720). The northeastern group is comprised of four short faults that trend north to northeast; they are located about 5 km southeast of Cerro Encierro. |
| **County(s) and State(s)** | CIBOLA COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | COLORADO PLATEAUS <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Fault traces are shown on 1:62,500-scale geologic map of Maxwell (1986 #1720) and a small-scale (approximately 1:400,000 scale) geologic map of Baldridge and others (1989 #1741). Extensions of the fault features west of Maxwell's mapping are shown on 1:100,000-scale geologic map of Anderson (1986 #1281). Fault traces were recompiled and digitized at 1:24,000 scale using photogrammetric methods. <P> |
| **Geologic setting** | These fault-like features are present on Quaternary (undifferentiated) basalt flows according to the mapping of Maxwell (1986 #1720). They trend north and northeast and may be related to westward directed extension or to the NE-trending Jemez lineament. Levish and others (1992 #1715) characterized the faults as non-tectonic features related to volcanic processes. <P> |
| **Length (km)** | 26 km. |
| **Average strike** | N7°E |
| **Sense of movement** | Normal<br><br>*Comments:* As mapped by Maxwell (1986 #1720), although most of the features are fissures that may not correspond to vertical displacement. <P> |
| **Dip Direction** | W; NW; SE |

| | |
|---|---|
| | *Comments:* As reported by Maxwell (1986 #1720). <P> |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | The faults (?) form short north- and northeast-trending en echelon scarps (?), fissures, and open crevices in lava flows (Maxwell, 1986 #1720). Levish and others (1992 #1715) suggested that the faults are fissures, cracks, pressure ridges, and collapsed lava tubes that give the expression of tectonic activity, but are in fact related to volcanic processes. <P> |
| **Age of faulted surficial deposits** | Maxwell (1986 #1720) mapped the faults as having offset Quaternary basalts that have reported K-Ar ages as old as and 1.38±0.29 Ma and Ar-Ar ages as young as 0.593±0.086 Ma (Laughlin and West, 1976 #7420; Laughlin and others, 1993 #7421). These dates suggest that the older (undifferentiated) basalts flows (Qb) span the early to middle Quaternary. |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | undifferentiated Quaternary (<1.6 Ma)<br><br>*Comments:* The features are present on basalts flows (Qb) of early to possibly middle Quaternary age. However, Maxwell (1986 #1720) suggested that the southern group of features (La Rendija) is Holocene in age because the crevices are not filled with alluvium, thus suggesting very recent formation of the features. In addition, he suggested that the numerous small fault scarps (?) on unconsolidated alluvium at the eastern edge of North Plains are also young. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* No measurements of offset across the features have been reported. If the features are really faults of Holocene age (Maxwell, 1986 #1720) and have substantial (>10 m) offset, they could have a slip rate that exceeds 0.2 mm/yr. However, the features are formed on an early to middle Quaternary landscape; thus, the recurrence |

| | |
|---|---|
| | interval for accumulating stress prior to the most recent faulting (suspect) event could be 750 k.y. or more. It therefore seems reasonable that slip rates associated with these suspect faults would be in the lowest slip-rate category. |
| **Date and Compiler(s)** | 2016<br>Michael N. Machette, U.S. Geological Survey, Retired<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #1281 Anderson, O.J., compiler, 1986, Geologic map of Fence Lake, New Mexico 1:100,000 metric sheet: New Mexico Bureau of Mines and Mineral Resources Open-File Report 220, 4 p. pamphlet, 4 sheets, scale 1:100,000.<br><br>#1741 Baldridge, W.S., Perry, F.V., Vaniman, D.T., Nealey, L.D., Leavy, B.D., Laughlin, A.W., Kyle, P., Bartov, Y., Steinitz, G., and Gladney, E.S., 1989, Excursion 8A—Magmatism associated with lithospheric extension—Middle to late Cenozoic magmatism of the southeastern Colorado Plateau and central Rio Grande rift, New Mexico and Arizona, in Chapin, C.E., and Zidek, J., eds., Field excursions to volcanic terranes in the Western United States, v. I, Southern Rocky Mountain region: New Mexico Bureau of Mines and Mineral Resources Memoir 46, p. 187-202.<br><br>#7420 Laughlin, A.W., and West, F.G., 1976, The Zuni Mountains, New Mexico, as a potential dry hot rock geothermal energy site: U.S. Energy Research and Development Administration, Los Alamos Scientific Laboratories Informal Report LA-3197-MS, 13 p.<br><br>#7421 Laughlin, A.W., Perry, F.V., Damon, P.E., Shafiqullah, M., WoldeGabriel, G., McIntosh, W., Harrington, C.D., Wells, S.G., and Drakos, P.G., 1993, Geochronology of Mount Taylor, Cebollita Mesa, and Zuni-Bandera volcanic fields, Cibola County, New Mexico: New Mexico Geology, v. 16, no. 4, p. 81–92.<br><br>#1715 Levish, D.R., Vetter, U.R., Ake, J.P., and Piety, L.A., 1992, Seismotectonic study for Black Rock Dam, Bureau of Indian Affairs, Pueblo of Zuni, New Mexico: Bureau of Reclamation Seismotectonic Report 92-3, 62 p.<br><br>#1720 Maxwell, C.H., 1986, Geologic map of El Malpais Lava Field and surrounding areas, Cibola County, New Mexico: U.S. Geological Survey Miscellaneous Investigations Map I-1595, 1 sheet, scale 1:62,500. |

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## unnamed intrabasin faults west of the Rio Puerco (Class A) No. 2115

**Last Review Date: 2016-03-30**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Personius, S.F., and Jochems, A.P., compilers, 2016, Fault number 2115, unnamed intrabasin faults west of the Rio Puerco, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:33 AM.**

| | |
|---|---|
| **Synopsis** | These intrabasin faults east of the Coyote Springs fault [2114] in the southwest Albuquerque basin of the Rio Grande rift are mostly expressed as short fault scarps in deposits of the upper Santa Fe Group Sierra Ladrones Formation; some have offsets of 3–20 m in middle Pleistocene alluvium. Most of the faults are partly to nearly completely buried by eolian sand. |
| **Name comments** | This group of structures consists of numerous short to relatively long, generally isolated, north-trending faults within the Belen sub-basin of the Albuquerque basin west of the Rio Puerco that were mapped by Machette (1982 #1401), Machette and McGimsey (1983 #1024), and Love and Young (1983 #1723). Some of these faults were previously mapped and named by Kelley (1977 #1106), including the east-down Gabaldon fault, the northern part of which was mapped by Lozinsky and Tedford (1991 #1339). |
| **County(s) and State(s)** | SOCORRO COUNTY, NEW MEXICO <br>VALENCIA COUNTY, NEW MEXICO <br> |

| | |
|---|---|
| **Physiographic province(s)** | BASIN AND RANGE <br> |
| **Reliability of location** | Good<br>Compiled at 1:24,000 scale.<br><br>*Comments:* Fault traces compiled using photogrammetric methods and previous mapping of Machette and McGimsey (1983 #1024) at 1:250,000 scale and Lozinsky and Tedford (1991 #1339) at 1:24,000 scale. <P> |
| **Geologic setting** | These faults dip to the east and west, and form a broad zone within the active part of the Belen sub-basin of the Albuquerque basin, west of the Rio Puerco. The longest fault (~27 km) in this group of structures (Gabaldon fault of Kelley, 1977 #1106) is thought to be an east-down listric fault at depth based on 2D geophysical modeling and well data (Grauch and Connell, 2013 #7268). <P> |
| **Length (km)** | 22 km. |
| **Average strike** | N7°W |
| **Sense of movement** | Normal |
| **Dip Direction** | E; W<br><br>*Comments:* Grauch and Connell (2013 #7268) show the longest east-down fault in this group of structures as a relatively shallow listric fault based on 2D geophysical modeling and well data. <P> |
| **Paleoseismology studies** | <P> |
| **Geomorphic expression** | These faults are marked by subdued, discontinuously preserved scarps that are mostly covered by eolian sand within the western part of the Belen sub-basin. Machette and McGimsey (1983 #1024) measured offsets of 3–20 m in middle Pleistocene alluvium. <P> |

| | |
|---|---|
| **Age of faulted surficial deposits** | These faults offset lower Pleistocene sediment of the upper Santa Fe Group Sierra Ladrones Formation, and early and middle Pleistocene alluvium (Machette, 1978 #1223; Machette and McGimsey, 1983 #1024). |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | middle and late Quaternary (<750 ka)<br><br>*Comments:* No deposits younger than middle Pleistocene (150–750 ka) have been shown to be offset by these faults, but the 3–20 m offsets measured by Machette and McGimsey (1983 #1024) indicate a recurrent history of movement that in some cases probably extended into the late Pleistocene. <P> |
| **Recurrence interval** | |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* Low slip-rate category assigned based on offsets of 3–20 m of middle Pleistocene (150–750 ka) alluvium (Machette and McGimsey, 1983 #1024). |
| **Date and Compiler(s)** | 2016<br>Stephen F. Personius, U.S. Geological Survey<br>Andrew P. Jochems, New Mexico Bureau of Geology & Mineral Resources |
| **References** | #7268 Grauch, V.J.S., and Connell, S.D., 2013, New perspectives on the geometry of the Albuquerque basin, Rio Grande rift, New Mexico: Insights from geophysical models of rift-fill thickness, in Hudson, M.R., and Grauch, V.J.S., eds., New perspectives on Rio Grande rift basins—From tectonics to groundwater: Geological Society of America Special Paper 494, p. 427–462, doi:10.1130/2013.2494(16).<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1723 Love, D.W., and Young, J.D., 1983, Progress report on the late Cenozoic geologic evolution of the lower Rio Puerco, in Chapin, C.E., and Callender, J.F., eds., Socorro region II: New Mexico Geological Society, 34th Field Conference, October 13-15, 1983, Guidebook, p. 277-284.<br><br>#1399 Lozinsky, R.P., and Tedford, R.H., 1991, Geology and paleontology of the Santa Fe Group, southwestern Albuquerque basin, Valencia County, New |

| | |
|---|---|
| | Mexico: New Mexico Bureau of Mines and Mineral Resources Bulletin 132, 35 p., 3 pls., scale 1:24,000.<br><br>#1401 Machette, M.N., 1982, Quaternary and Pliocene faults in the La Jencia and southern part of the Albuquerque-Belen basins, New Mexico—Evidence of fault history from fault-scarp morphology and Quaternary geology, in Grambling, J.A., and Wells, S.G., eds., Albuquerque Country II: New Mexico Geological Society, 33rd Field Conference, November 4-6, 1982, Guidebook, p. 161-169.<br><br>#1024 Machette, M.N., and McGimsey, R.G., 1983, Map of Quaternary and Pliocene faults in the Socorro and western part of the Fort Sumner 1° x 2° quadrangles, central New Mexico: U.S. Geological Survey Miscellaneous Field Studies Map MF-1465-A, 12 p. pamphlet, 1 sheet, scale 1:250,000.<br><br>#1223 Machette, M.N., compiler, 1978, Preliminary geologic map of the Socorro 1° by 2° quadrangle, central New Mexico: U.S. Geological Survey Open-File Report 78-607, 1 sheet, scale 1:250,000. |

U.S. Geological Survey - Earthquake Hazards Program

# Quaternary Fault and Fold Database of the United States

**As of January 12, 2017, the USGS maintains a limited number of metadata fields that characterize the Quaternary faults and folds of the United States. For the most up-to-date information, please refer to the interactive fault map.**

## Zia fault (Class A) No. 2046

**Last Review Date: 2015-04-13**

## Compiled in cooperation with the New Mexico Bureau of Geology & Mineral Resources

***citation for this record:*** **Personius, S.F., and Haller, K.M., compilers, 2015, Fault number 2046, Zia fault, in Quaternary fault and fold database of the United States: U.S. Geological Survey website, https://earthquakes.usgs.gov/hazards/qfaults, accessed 08/27/2025 11:33 AM.**

| | |
|---|---|
| **Synopsis** | The down-to-the-east Zia fault offsets Santa Fe Group sediment exposed in the Zia badlands, on the Llano de Albuquerque, and in younger Quaternary deposits. Upper Santa Fe Group sediment may have been offset about 60 m across the Zia fault since early Quaternary time. |
| **Name comments** | The Zia fault is one of several north-trending normal faults named by Kelley (1977 #1106) in the Zia badlands in the northern part of the Albuquerque-Belen basin. Galusha (1966 #1296), G.O. Bachman (unpublished mapping, 1975) and Manley (1978 #1404) mapped the northern end of the Zia fault in the Sky Village NE and Bernalillo NW quadrangles, respectively. Galusha (1966 #1296) and Manley (1978 #1404) used the name Rincon fault in the Bernalillo NW quadrangle, but we retain the name Zia fault herein due to apparent common usage in recent publications (Wong and others, 1995 #1155; Hawley and Whitworth, 1996 #1303). Recent mapping (Hawley and Whitworth, 1996 #1303; Cather and others, 1997 #1763; Connell, 2008 #7454) extends the Zia fault much further south than the original trace of the fault as mapped by Kelley (1977 #1106). |

| | |
|---|---|
| **County(s) and State(s)** | BERNALILLO COUNTY, NEW MEXICO <br>SANDOVAL COUNTY, NEW MEXICO <br> |
| **Physiographic province(s)** | BASIN AND RANGE <br> |
| **Reliability of location** | Good<br>Compiled at 1:100,000 scale.<br><br>*Comments:* Fault trace from Manley (1978 #1404) in the Bernalillo NW quadrangle, G.O. Bachman (unpubl. mapping, 1975) in the Sky Village NE quadrangle, Cather and others (1997 #1763) in the Sky Village SE quadrangle, and unpublished air photo mapping by the compiler (1997) in the Sky Village NE, Sky Village SE, and Volcano Ranch quadrangles, all recompiled at 1:100,000 scale on a topographic base map. The fault location is also evident in high-resolution aeromagnetic data (U.S. Geological Survey and SIAL Geosciences Inc., 1997 #1722; Grauch and Millegan, 1998 #1721). <P> The southern trace of the Zia fault is open to interpretation. Cather and others (1997 #1763) mapped the Zia fault as a queried trace with a southward strike along the eastern margin of the Sky Village SE (now Arroyo de las Calabacillas) 7.5-minute quadrangle. However, the compiler used the mapping of Hawley and Whitworth (1996 #1303), airphoto analysis (S.F. Personius, unpubl. mapping, 1997), and geophysical data (U.S. Geological Survey and SIAL Geosciences Inc., 1997 #1722; Grauch and Millegan, 1998 #1721) to infer a more southwestward trace of the Zia fault across the Sky Village SE quadrangle. The latter trace is used in the compilation because the fault appears to have better topographic expression, and thus may have younger movement. <P> |
| **Geologic setting** | The Zia fault is one of several down-to-the-east intrabasin faults in the northern part of the Albuquerque-Belen basin. <P> |
| **Length (km)** | 32 km. |
| **Average strike** | N15°E |
| **Sense of movement** | Normal |

| | |
|---|---|
| **Dip Direction** | E |
| **Paleoseismology studies** | Site 2046-1. Referred to as the Zia trench site is located near the southern rim of Ceja de-Rio Jemez (the northern limit of the Llano de Albuquerque geomorphic surface). McCalpin and Harrison (2001 #6924) excavated three trenches at this site in order to better observe the stratigraphy. The middle trench crosses the steepest, highest part of the fault scarp and reveals evidence for at least 5 faulting events. Displacement in these events ranged from 0.6 to 2.6 m, with an average of 1.3 m. The study includes two independent age estimates from soil-carbonate accumulation and luminescence ages. Soil-carbonate age estimates are preferred because the thermoluminescence ages (56–416 ka) were deemed unreliable because all dates are in an inverted stratigraphic order. The soils in the upper 3 m of the trench required 10–32 k.y. to form, and the strong soils at the base of the trench required an additional 32 k.y. <P> |
| **Geomorphic expression** | The Zia fault is well exposed in Santa Fe Group sediment in the Zia badlands north of the Llano de Albuquerque. Farther south, the fault forms broad, dissected fault scarps across the Llano de Albuquerque and on younger surficial deposits. <P> |
| **Age of faulted surficial deposits** | Manley (1978 #1404) described minor (0.5 m) offset of middle or upper (?) Pleistocene alluvium by the Zia fault in the Bernalillo NW quadrangle. Kelly (1997 #1106) estimated approximately 60 m of throw in Upper Santa Fe Group sediment (Pliocene to early Pleistocene) across the Zia fault. In most places, the Zia fault offsets the early Pleistocene Llano de Albuquerque surface and middle (?) Pleistocene surficial deposits. |
| **Historic earthquake** | |
| **Most recent prehistoric deformation** | latest Quaternary (<15 ka)<br><br>*Comments:* McCalpin and Harrison (2001 #6924) conclude that the most recent surface rupture at the trench site occurred about 11 ka as inferred from soil-carbonate age estimates. Furthermore, the most recent event is older than the Holocene unconformity that occurred about 2,380–2,740 cal. yr BP. <P> |
| **Recurrence interval** | 10–21 k.y. (<119 ka) |

| | |
|---|---|
| | *Comments:* McCalpin and Harrison (2001 #6924) base their estimate of long-term average recurrence by assuming five events have occurred since the formation of buried soils 5 and 6, which have a soil-carbonate age estimate of greater than 63 ka and an optically stimulated luminescence (OSL) age of 119 ka. McCalpin and Harrison (2001 #6924) suggest that if the most recent event occurred at 11 ka, then the four preceding recurrence cycles spanned 52–108 k.y., which results in an average recurrence interval of 10–21 k.y. |
| **Slip-rate category** | Less than 0.2 mm/yr<br><br>*Comments:* The five events inferred from the middle trench have a cumulative down-to-the-east vertical displacement of 6.5 m, which occurred over the past 63-119 ka. McCalpin and Harrison (2001 #6924) suggest that the resulting average long-term vertical displacement rate is 0.055–0.1 mm/yr. |
| **Date and Compiler(s)** | 2015<br>Stephen F. Personius, U.S. Geological Survey<br>Kathleen M. Haller, U.S. Geological Survey |
| **References** | #1763 Cather, S.M., Connell, S.D., Heynekamp, M.R., and Goodwin, L.B., 1997, Geology of the Arroyo de las Calabacillas [Sky Village SE] 7.5-minute quadrangle, Sandoval County, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Geologic Map 9, 8 p. pamphlet, 1 sheet, scale 1:24,000.<br><br>#7454 Connell, S.D., 2008, Geologic map of the Albuquerque-Rio Rancho metropolitan area and vicinity, Bernalillo and Sandoval Counties, New Mexico: New Mexico Bureau of Geology and Mineral Resources Geologic Map 78, scale 1:50,000.<br><br>#1296 Galusha, T., 1966, The Zia Sand Formation, new early to medial Miocene beds in New Mexico: American Museum Novitates 2271, 12 p.<br><br>#1721 Grauch, V.J.S., and Millegan, P.S., 1998, Mapping intrabasinal faults from high-resolution aeromagnetic data: The Leading Edge, v. 17, p. 53-55.<br><br>#1303 Hawley, J.W., and Whitworth, T.M., compilers, 1996, Hydrogeology of potential recharge areas for the basin- and valley-fill aquifer systems, and hydrogeochemical modeling of proposed artificial recharge of the upper Santa Fe aquifer, northern Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Open-File Report 402-D, 575 p.<br><br>#1106 Kelley, V.C., 1977, Geology of Albuquerque basin, New Mexico: New Mexico Bureau of Mines and Mineral Resources Memoir 33, 60 p., 2 pls.<br><br>#1404 Manley, K., 1978, Geologic map of Bernalillo NW quadrangle, Sandoval County, New Mexico: U.S. Geological Survey Geologic quadrangle Map GQ-1446, 1 sheet, scale 1:24,000.<br><br>#6924 McCalpin, J.P., and Harrison, J.B.J., 2001, Paleoseismicity of Quaternary faults near Albuquerque, New Mexico: Final Technical Report, Second Year, to U.S. Geological Survey for Contract 99HQGR0056, 58 p.<br><br>#1722 U.S. Geological Survey, and SIAL Geosciences, Inc., 1997, Description of digital |

| | |
|---|---|
| | aeromagnetic data collected north and west of Albuquerque, New Mexico: U.S. Geological Survey Open-File Report 97-286, 40 p.<br><br>#1155 Wong, I., Kelson, K., Olig, S., Kolbe, T., Hemphill-Haley, M., Bott, J., Green, R., Kanakari, H., Sawyer, J., Silva, W., Stark, C., Haraden, C., Fenton, C., Unruh, J., Gardner, J., Reneau, S., and House, L., 1995, Seismic hazards evaluation of the Los Alamos National Laboratory: Technical report to Los Alamos National Laboratory, Los Alamos, New Mexico, February 24, 1995, 3 volumes, 12 pls., 16 appen. |

# APPENDIX C
# DETERMINISTIC ANALYSES

# APPENDIX C.1
# DETERMINISTIC EZ-FRISK SOFTWARE INPUT

```
                  ********************************************
                  *****              EZ-FRISK              *****
                  ***** SEISMIC HAZARD ANALYSIS DEFINITION *****
                  *****               FUGRO                *****
                  *****        WALNUT CREEK, CA  USA       *****
                  ********************************************

PROGRAM VERSION
  EZ-FRISK 8.11 Build 019

ANALYSIS TITLE:
  Mt Taylor Deterministic

ANALYSIS TYPE:
  Single Site Analysis

SITE COORDINATES
  Latitude 35.3409
  Longitude -107.635

INTENSITY TYPE:  Spectral Response @ 5% Damping

HAZARD DEAGGREGATION
  Status: ON
  Deagregation Scenario 1
    Period:             PGA
    Amplitude:          0.0001 Acceleration (g)
  Bin Configuration
    Magnitude
      Scale:         Moment Magnitude
      Lowest Value:  5 Mw
      Highest Value: 9 Mw
      Bin Size:      0.1
    Distance
      Lowest Value:  0 km
      Highest Value: 102.5 km
      Bin Size:      2.5 km
    Epsilon
      Lowest Value:  -2.2
      Highest Value: 4.2
      Bin Size:      0.2

SOIL AMPLIFICATION
  Method: Do not use soil amplification

ATTENUATION EQUATION SITE PARAMETERS
  Depth[Vs=1,000m/s] (m): 5
  Depth[Vs=1000m/s] (m): -1
  Estimate Z1 from Vs30 for CY NGA: 1
  Regional Code: Default
  Subduction Zone Setting: Unknown
  Vs30 (m/s): 1200
  Vs30 Is Measured: 0
  Z25 (km): 0.79
```

AMPLITUDES - Acceleration (g)
  0.0001
  0.001
  0.01
  0.02
  0.05
  0.07
  0.1
  0.2
  0.3
  0.4
  0.5
  0.7
  1
  2
  3

PERIODS (s)
  PGA
  0.05
  0.1
  0.2
  0.3
  0.4
  0.5
  0.75
  1
  2
  3
  4

DETERMINISTIC FRACTILES
  0.5
  0.84

PLOTTING PARAMETERS
  Period at which to plot PGA: 0.0001

CALCULATIONAL PARAMETERS
  Fault Seismic Sources -
    Maximum inclusion distance           :   1000 km
    Down dip integration increment       :   1 km
    Horizontal integration increment     :   1 km
    Number rupture length per earthquake :   1
  Subduction Interface Seismic Sources -
    Maximum inclusion distance           :   1000 km
    Down dip integration increment       :   5 km
    Horizontal integration increment     :   20 km
    Number rupture length per earthquake :   1
  Subduction Slab Seismic Sources -
    Maximum inclusion distance           :   300 km
    Down dip integration increment       :   5 km
    Horizontal integration increment     :   20 km

```
    Number rupture length per earthquake :   1
  Area Seismic Sources -
    Maximum inclusion distance           :   200 km
    Vertical integration increment       :   3 km
    Number of rupture azimuths           :   3
    Minimum epicentral distance step     :   0.5 km
    Maximum epicentral distance step     :   10 km
  Gridded Seismic Sources -
    Maximum inclusion distance            :   1000 km
    Default number of rupture azimuths    :   20
    Maximum distance for default azimuths :   40 km
    Minimum distance for one azimuth      :   150
    Use binned calcuations if possible    :   true
    Bins per decade in distance (km)      :   20
  All Seismic Sources -
    Magnitude integration step           :   0.1 M
    Apply magnitude scaling              :   NO
    Include near-source directivity      :   NO

ATTENUATION EQUATIONS

  Name: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Database: C:\Program Files (x86)\EZ-FRISK 8.11\Files\standard.bin-
attendb
  Base: Abrahamson-et al 2014 NGA West 2
  Truncation Type: USGS 2008 NSHM Truncation
  Truncation Value: 3
  Magnitude Scale: Moment Magnitude
  Distance Type: Distance To Rupture

  Name: Boore-et al (2014) NGA West 2 USGS 2014
  Database: C:\Program Files (x86)\EZ-FRISK 8.11\Files\standard.bin-
attendb
  Base: Boore-et al 2014 NGA West 2
  Truncation Type: USGS 2008 NSHM Truncation
  Truncation Value: 3
  Magnitude Scale: Moment Magnitude
  Distance Type: Horizontal Distance To Rupture

  Name: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Database: C:\Program Files (x86)\EZ-FRISK 8.11\Files\standard.bin-
attendb
  Base: Campbell-Bozorgnia 2014 NGA West 2
  Truncation Type: USGS 2008 NSHM Truncation
  Truncation Value: 3
  Magnitude Scale: Moment Magnitude
  Distance Type: Distance To Rupture

  Name: Chiou-Youngs (2014) NGA West 2 USGS 2014
  Database: C:\Program Files (x86)\EZ-FRISK 8.11\Files\standard.bin-
attendb
  Base: Chiou-Youngs 2014 NGA West 2
  Truncation Type: USGS 2008 NSHM Truncation
  Truncation Value: 3
```

Magnitude Scale: Moment Magnitude
Distance Type: Distance To Rupture

SEISMIC SOURCE SUMMARY TABLE

| Closest Deterministic Fault Source | Distance | Magnitude | Mechanism | Dip Angle | Dips To | Site Region Lies |
|---|---|---|---|---|---|---|
| Random Earthquake | 15.08 | 6.3000 | Normal | 60.0000 | NE | Mt Taylor Deterministic S |
| Cat Mesa fault | 75.81 | 6.6000 | Normal | 80.0000 | W | Mt Taylor Deterministic NW |
| Cebollita Mesa fault | 74.73 | 6.3000 | Normal | 60.0000 | W | Mt Taylor Deterministic NE |
| Continental Divide fault | 91.78 | 6.5000 | Normal | 60.0000 | NW | Mt Taylor Deterministic NE |
| County Dump fault [2038] | 76.49 | 6.8900 | Normal | 35-65 | E | USGS 2014 New Mexico W |
| Coyote Springs fault | 93.39 | 6.5000 | Normal | 60.0000 | SW | Mt Taylor Deterministic NW |
| Intrabasin faults on the Llano de Albuquerque | 66.68 | 7.5000 | Normal | 60.0000 | W | Mt Taylor Deterministic W |
| Jemez-San Ysidro fault [2029ab] | 77.22 | 7.0900 | Normal | 35-65 | E | USGS 2014 New Mexico W |
| Calabacillas fault [2035] | 70.51 | 6.8300 | Normal | 35-65 | E | USGS 2014 New Mexico W |
| Mesa Prieta faults | 47.03 | 6.3000 | Normal | 60.0000 | W | Mt Taylor Deterministic W |
| Nacimiento fault [2002ab] | 72.26 | 7.3000 | Normal | 35-65 | E | USGS 2014 New Mexico W |
| San Felipe fault zone [2030a] | 93.19 | 6.9700 | Normal | 35-65 | E | USGS 2014 New Mexico W |
| San Felipe fault zone (Algodones section) | 93.26 | 7.0000 | Normal | 60.0000 | W | Mt Taylor Deterministic W |
| Sand Hill fault zone | 62.14 | 6.9000 | Normal | 60.0000 | W | Mt Taylor Deterministic W |
| Santa Fe fault | 67.75 | 6.8000 | Normal | 60.0000 | W | Mt Taylor Deterministic NW |
| unnamed fault of Bonita Canyon | 49.31 | 6.1000 | Normal | 60.0000 | W | Mt Taylor Deterministic NE |
| unnamed faults near Albuquerque Volcanoes | 73.56 | 6.9000 | Normal | 60.0000 | W | Mt Taylor Deterministic W |
| unnamed faults near Picuda Peak | 78.77 | 6.4000 | Normal | 60.0000 | W | Mt Taylor Deterministic W |
| unnamed faults near Star Heights | 78.52 | 6.5000 | Normal | 70.0000 | W | Mt Taylor Deterministic W |
| unnamed faults of El Malpais lava field | 60.42 | 6.7000 | Normal | 60.0000 | W | Mt Taylor Deterministic NE |
| unnamed intrabasin faults west of the Rio Puerco | 87.25 | 6.6000 | Normal | 60.0000 | W | Mt Taylor Deterministic NW |

Zia fault [2046]  USGS 2014 New Mexico
73.70  6.8400 Normal  35-65 E  W

SEISMIC SOURCES

Name: Random Earthquake
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 1.00000000
Deterministic Magnitude: 6.3

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 60 | 60 | 0 | 0.1 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 1 | Slip | 2.000e-02 | 6.200000 | 6.400000 | 0.000000 | 6.300000 | 0.120000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.100000 | 4.000000 | 0.000000 | 0.100000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.4750 | -107.6100 |
| 35.4760 | -107.6110 |

Attenuation Equations for Source:

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

Name: Cat Mesa fault
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-ssdb
Fault Mechanism: Normal

Magnitude Scale: Moment Magnitude
Probability of Activity: 1.00000000
Deterministic Magnitude: 6.6

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 80 | 80 | 0 | 0.1 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 1 | Slip | 2.000e-02 | 6.300000 | 6.900000 | 0.000000 | 6.600000 | 0.120000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.100000 | 4.000000 | 0.000000 | 0.100000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.0060 | -106.8960 |
| 34.7350 | -106.9260 |

Attenuation Equations for Source:

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

Name: Cebollita Mesa fault
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 1.00000000
Deterministic Magnitude: 6.3

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 60 | 60 | 0 | 0.1 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|

```
          Normal         1        Slip   2.000e-02  6.000000  6.600000
0.000000  6.300000  0.120000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.100000  4.000000  0.000000
0.100000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    34.7310  -107.9810
    34.6100  -107.9750

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

*****************************************

Name: Continental Divide fault
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-
ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.50000000
Deterministic Magnitude: 6.5

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          60        60         0       0.1        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
          Normal         1        Slip   2.000e-02  6.200000  6.800000
0.000000  6.500000  0.120000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.100000  4.000000  0.000000
0.100000        --        --        --

Trace Coordinates:
  Latitude   Longitude
```

```
    34.7820  -108.3780
    34.6090  -108.4870

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

*****************************************

Name: County Dump fault [2038]
Region: USGS 2014 New Mexico
Category:Composite Seismic Source
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Regions\EZ-FRISK
USGS2014 Lower 48 v1.00\Files\USGS 2014 Lower 48.bin-ssdb
Magnitude Scale: Moment Magnitude
Probability of Activity: 1
 ------ Start Nested Sources forCounty Dump fault [2038] -------
Name: 2038 County Dump fault (dip 35)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 6.89

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          90        35         0     0.001        15

Magnitude Recurrence Distributions:
       ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
          Normal  0.013334    Activity   4.132e-05  6.450000  6.930000
2.300000  6.690000  0.120000  0.010000 10.000000
          Normal  0.040002    Activity   4.132e-05  6.650000  7.130000
2.300000  6.890000  0.120000  0.010000 10.000000
          Normal  0.013334    Activity   4.132e-05  6.850000  7.330000
2.300000  7.090000  0.120000  0.010000 10.000000
     Exponential  0.006666    Activity   5.043e-05  6.500000  6.690000
1.842068  0.000000  0.000000  0.000000  0.000000
     Exponential  0.019998    Activity   8.751e-05  6.500000  6.890000
1.842068  0.000000  0.000000  0.000000  0.000000
     Exponential  0.006666    Activity   1.132e-04  6.500000  7.090000
1.842068  0.000000  0.000000  0.000000  0.000000
          Normal  0.106666    Activity   4.095e-05  6.450000  6.930000
2.300000  6.690000  0.120000  0.010000 10.000000
          Normal  0.319998    Activity   4.095e-05  6.650000  7.130000
2.300000  6.890000  0.120000  0.010000 10.000000
```

| | | | | | | |
|---|---|---|---|---|---|---|
| Normal | 0.106666 | Activity | 4.095e-05 | 6.850000 | 7.330000 | 2.300000 |
| 7.090000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Exponential | 0.053334 | Activity | 5.003e-05 | 6.500000 | 6.690000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Exponential | 0.160002 | Activity | 8.682e-05 | 6.500000 | 6.890000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Exponential | 0.053334 | Activity | 1.123e-04 | 6.500000 | 7.090000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Normal | 0.013334 | Activity | 4.951e-05 | 6.450000 | 6.930000 | 2.300000 |
| 6.690000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Normal | 0.040002 | Activity | 4.951e-05 | 6.650000 | 7.130000 | 2.300000 |
| 6.890000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Normal | 0.013334 | Activity | 4.951e-05 | 6.850000 | 7.330000 | 2.300000 |
| 7.090000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Exponential | 0.006666 | Activity | 6.051e-05 | 6.500000 | 6.690000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Exponential | 0.019998 | Activity | 1.050e-04 | 6.500000 | 6.890000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Exponential | 0.006666 | Activity | 1.358e-04 | 6.500000 | 7.090000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |

```
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.0085  -106.7757
    35.1051  -106.7841
    35.1830  -106.7825
    35.2448  -106.8003
    35.2807  -106.7828
    35.3260  -106.7499

Name: 2038 County Dump fault (dip 50)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.60000000
Deterministic Magnitude: 6.89

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          90        50         0     0.001        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
           Normal  0.013334    Activity   4.132e-05  6.450000  6.930000
2.300000  6.690000  0.120000  0.010000 10.000000
           Normal  0.040002    Activity   4.132e-05  6.650000  7.130000
2.300000  6.890000  0.120000  0.010000 10.000000
           Normal  0.013334    Activity   4.132e-05  6.850000  7.330000
2.300000  7.090000  0.120000  0.010000 10.000000
      Exponential  0.006666    Activity   5.043e-05  6.500000  6.690000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.019998    Activity   8.751e-05  6.500000  6.890000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.006666    Activity   1.132e-04  6.500000  7.090000
1.842068  0.000000  0.000000  0.000000  0.000000
           Normal  0.106666    Activity   4.095e-05  6.450000  6.930000
2.300000  6.690000  0.120000  0.010000 10.000000
           Normal  0.319998    Activity   4.095e-05  6.650000  7.130000
2.300000  6.890000  0.120000  0.010000 10.000000
           Normal  0.106666    Activity   4.095e-05  6.850000  7.330000
2.300000  7.090000  0.120000  0.010000 10.000000
      Exponential  0.053334    Activity   5.003e-05  6.500000  6.690000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.160002    Activity   8.682e-05  6.500000  6.890000
1.842068  0.000000  0.000000  0.000000  0.000000
```

| | | | | | | |
|---|---|---|---|---|---|---|
| Exponential | 0.053334 | Activity | 1.123e-04 | 6.500000 | 7.090000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Normal | 0.013334 | Activity | 4.951e-05 | 6.450000 | 6.930000 | 2.300000 |
| 6.690000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Normal | 0.040002 | Activity | 4.951e-05 | 6.650000 | 7.130000 | 2.300000 |
| 6.890000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Normal | 0.013334 | Activity | 4.951e-05 | 6.850000 | 7.330000 | 2.300000 |
| 7.090000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Exponential | 0.006666 | Activity | 6.051e-05 | 6.500000 | 6.690000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Exponential | 0.019998 | Activity | 1.050e-04 | 6.500000 | 6.890000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Exponential | 0.006666 | Activity | 1.358e-04 | 6.500000 | 7.090000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.0085 | -106.7757 |
| 35.1051 | -106.7841 |
| 35.1830 | -106.7825 |
| 35.2448 | -106.8003 |
| 35.2807 | -106.7828 |
| 35.3260 | -106.7499 |

Name: 2038 County Dump fault (dip 65)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 6.89

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 65 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 4.132e-05 | 6.450000 | 6.930000 | 2.300000 | 6.690000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 4.132e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 4.132e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 5.043e-05 | 6.500000 | 6.690000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 8.751e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 1.132e-04 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.106666 | Activity | 4.095e-05 | 6.450000 | 6.930000 | 2.300000 | 6.690000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.319998 | Activity | 4.095e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.106666 | Activity | 4.095e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.053334 | Activity | 5.003e-05 | 6.500000 | 6.690000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.160002 | Activity | 8.682e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.053334 | Activity | 1.123e-04 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.013334 | Activity | 4.951e-05 | 6.450000 | 6.930000 | 2.300000 | 6.690000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 4.951e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | Normal | 0.013334 | Activity | 4.951e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| | Exponential | 0.006666 | Activity | 6.051e-05 | 6.500000 | 6.690000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Exponential | 0.019998 | Activity | 1.050e-04 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Exponential | 0.006666 | Activity | 1.358e-04 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.0085 | -106.7757 |
| 35.1051 | -106.7841 |
| 35.1830 | -106.7825 |

```
    35.2448  -106.8003
    35.2807  -106.7828
    35.3260  -106.7499

 ------ End Nested Sources for County Dump fault [2038] -------

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

*****************************************

Name: Coyote Springs fault
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-
ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 1.00000000
Deterministic Magnitude: 6.5

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          60        60         0       0.1        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
          Normal         1        Slip   2.000e-02  6.200000  6.800000
0.000000  6.500000  0.120000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.100000  4.000000  0.000000
0.100000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    34.6210  -107.1060
    34.4710  -107.0050

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
```

```
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

****************************************

Name: Intrabasin faults on the Llano de Albuquerque
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-
ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 1.00000000
Deterministic Magnitude: 7.5

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          60        60         0       0.1        15

Magnitude Recurrence Distributions:
       ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
         Normal         1        Slip   2.000e-02  7.200000  7.800000
0.000000  7.500000  0.120000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.100000  4.000000  0.000000
0.100000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.1810  -106.8520
    34.4930  -106.8350

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

****************************************

Name: Jemez-San Ysidro fault [2029ab]
Region: USGS 2014 New Mexico
Category:Composite Seismic Source
```

Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Regions\EZ-FRISK USGS2014 Lower 48 v1.00\Files\USGS 2014 Lower 48.bin-ssdb
Magnitude Scale: Moment Magnitude
Probability of Activity: 1
------ Start Nested Sources forJemez-San Ysidro fault [2029ab] -------
Name: 2029ab Jemez-San Ysidro fault (dip 35)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 7.09

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 35 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 1.815e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.815e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.815e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 4.237e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 5.479e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 6.339e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.106666 | Activity | 1.582e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.319998 | Activity | 1.582e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.106666 | Activity | 1.582e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.053334 | Activity | 3.687e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.160002 | Activity | 4.768e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.053334 | Activity | 5.516e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.013334 | Activity | 2.420e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 2.420e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 2.420e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 5.650e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 7.306e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

Exponential 0.006666 Activity 8.452e-05 6.500000 7.290000
1.842068 0.000000 0.000000 0.000000 0.000000

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.4204 | -106.7887 |
| 35.4846 | -106.7821 |
| 35.5444 | -106.7889 |
| 35.5588 | -106.7854 |
| 35.5980 | -106.7870 |
| 35.6099 | -106.7896 |
| 35.6472 | -106.8137 |
| 35.6645 | -106.8166 |
| 35.6864 | -106.8126 |

35.7072 -106.7940
35.7251 -106.7645
35.7443 -106.7555
35.7529 -106.7401
35.7737 -106.7198
35.7876 -106.6880
35.8181 -106.6576
35.8332 -106.6346

Name: 2029ab Jemez-San Ysidro fault (dip 50)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.60000000
Deterministic Magnitude: 7.09

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 50 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 1.815e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.815e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.815e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 4.237e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 5.479e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 6.339e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.106666 | Activity | 1.582e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.319998 | Activity | 1.582e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.106666 | Activity | 1.582e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.053334 | Activity | 3.687e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.160002 | Activity | 4.768e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.053334 | Activity | 5.516e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.013334 | Activity | 2.420e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 2.420e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 2.420e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Exponential | 0.006666 | Activity | 5.650e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Exponential | 0.019998 | Activity | 7.306e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Exponential | 0.006666 | Activity | 8.452e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.4204 | -106.7887 |
| 35.4846 | -106.7821 |
| 35.5444 | -106.7889 |
| 35.5588 | -106.7854 |
| 35.5980 | -106.7870 |

```
    35.6099  -106.7896
    35.6472  -106.8137
    35.6645  -106.8166
    35.6864  -106.8126
    35.7072  -106.7940
    35.7251  -106.7645
    35.7443  -106.7555
    35.7529  -106.7401
    35.7737  -106.7198
    35.7876  -106.6880
    35.8181  -106.6576
    35.8332  -106.6346

Name: 2029ab Jemez-San Ysidro fault (dip 65)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 7.09

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          90        65         0     0.001        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
           Normal  0.013334    Activity   1.815e-05  6.650000  7.130000
2.300000  6.890000  0.120000  0.010000 10.000000
           Normal  0.040002    Activity   1.815e-05  6.850000  7.330000
2.300000  7.090000  0.120000  0.010000 10.000000
           Normal  0.013334    Activity   1.815e-05  7.050000  7.530000
2.300000  7.290000  0.120000  0.010000 10.000000
      Exponential  0.006666    Activity   4.237e-05  6.500000  6.890000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.019998    Activity   5.479e-05  6.500000  7.090000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.006666    Activity   6.339e-05  6.500000  7.290000
1.842068  0.000000  0.000000  0.000000  0.000000
           Normal  0.106666    Activity   1.582e-05  6.650000  7.130000
2.300000  6.890000  0.120000  0.010000 10.000000
           Normal  0.319998    Activity   1.582e-05  6.850000  7.330000
2.300000  7.090000  0.120000  0.010000 10.000000
           Normal  0.106666    Activity   1.582e-05  7.050000  7.530000
2.300000  7.290000  0.120000  0.010000 10.000000
      Exponential  0.053334    Activity   3.687e-05  6.500000  6.890000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.160002    Activity   4.768e-05  6.500000  7.090000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.053334    Activity   5.516e-05  6.500000  7.290000
1.842068  0.000000  0.000000  0.000000  0.000000
           Normal  0.013334    Activity   2.420e-05  6.650000  7.130000
2.300000  6.890000  0.120000  0.010000 10.000000
```

```
           Normal  0.040002    Activity   2.420e-05  6.850000  7.330000
2.300000  7.090000  0.120000  0.010000 10.000000
           Normal  0.013334    Activity   2.420e-05  7.050000  7.530000
2.300000  7.290000  0.120000  0.010000 10.000000
      Exponential  0.006666    Activity   5.650e-05  6.500000  6.890000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.019998    Activity   7.306e-05  6.500000  7.090000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.006666    Activity   8.452e-05  6.500000  7.290000
1.842068  0.000000  0.000000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.4204  -106.7887
```

```
    35.4846  -106.7821
    35.5444  -106.7889
    35.5588  -106.7854
    35.5980  -106.7870
    35.6099  -106.7896
    35.6472  -106.8137
    35.6645  -106.8166
    35.6864  -106.8126
    35.7072  -106.7940
    35.7251  -106.7645
    35.7443  -106.7555
    35.7529  -106.7401
    35.7737  -106.7198
    35.7876  -106.6880
    35.8181  -106.6576
    35.8332  -106.6346

 ------ End Nested Sources for Jemez-San Ysidro fault [2029ab] -------

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

****************************************

Name: Calabacillas fault [2035]
Region: USGS 2014 New Mexico
Category:Composite Seismic Source
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Regions\EZ-FRISK
USGS2014 Lower 48 v1.00\Files\USGS 2014 Lower 48.bin-ssdb
Magnitude Scale: Moment Magnitude
Probability of Activity: 1
 ------ Start Nested Sources forCalabacillas fault [2035] -------
Name: 2035 Calabacillas fault (dip 35)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 6.83

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          90        35         0     0.001        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
```

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | Normal | 0.013334 | Activity | 1.984e-04 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 |
| | Normal | 0.040002 | Activity | 1.984e-04 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 |
| | Normal | 0.013334 | Activity | 1.984e-04 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 |
| | Exponential | 0.006666 | Activity | 1.770e-04 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Exponential | 0.019998 | Activity | 3.787e-04 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Exponential | 0.006666 | Activity | 5.181e-04 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Normal | 0.106666 | Activity | 8.097e-06 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 |
| | Normal | 0.319998 | Activity | 8.097e-06 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 |
| | Normal | 0.106666 | Activity | 8.097e-06 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 |
| | Exponential | 0.053334 | Activity | 7.248e-06 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Exponential | 0.160002 | Activity | 1.550e-05 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Exponential | 0.053334 | Activity | 2.121e-05 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Normal | 0.013334 | Activity | 9.028e-06 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 |
| | Normal | 0.040002 | Activity | 9.028e-06 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 |
| | Normal | 0.013334 | Activity | 9.028e-06 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 |
| | Exponential | 0.006666 | Activity | 8.047e-06 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Exponential | 0.019998 | Activity | 1.721e-05 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Exponential | 0.006666 | Activity | 2.355e-05 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- | | |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- | | |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- | | |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- | | |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- | | |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- | | |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- | | |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- | | |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- | | |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- | | |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- | | |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.1404 | -106.8390 |
| 35.2034 | -106.8526 |
| 35.2416 | -106.8654 |
| 35.2671 | -106.8632 |
| 35.3315 | -106.8350 |
| 35.4192 | -106.7898 |

Name: 2035 Calabacillas fault (dip 50)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.60000000
Deterministic Magnitude: 6.83

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 50 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 1.984e-04 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.984e-04 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.984e-04 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 |

| | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Exponential | 0.006666 | Activity | 1.770e-04 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | | |
| Exponential | 0.019998 | Activity | 3.787e-04 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | | |
| Exponential | 0.006666 | Activity | 5.181e-04 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | | |
| Normal | 0.106666 | Activity | 8.097e-06 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 | | |
| Normal | 0.319998 | Activity | 8.097e-06 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 | | |
| Normal | 0.106666 | Activity | 8.097e-06 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 | | |
| Exponential | 0.053334 | Activity | 7.248e-06 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | | |
| Exponential | 0.160002 | Activity | 1.550e-05 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | | |
| Exponential | 0.053334 | Activity | 2.121e-05 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | | |
| Normal | 0.013334 | Activity | 9.028e-06 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 | | |
| Normal | 0.040002 | Activity | 9.028e-06 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 | | |
| Normal | 0.013334 | Activity | 9.028e-06 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 | | |
| Exponential | 0.006666 | Activity | 8.047e-06 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | | |
| Exponential | 0.019998 | Activity | 1.721e-05 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | | |
| Exponential | 0.006666 | Activity | 2.355e-05 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.1404 | -106.8390 |
| 35.2034 | -106.8526 |
| 35.2416 | -106.8654 |
| 35.2671 | -106.8632 |
| 35.3315 | -106.8350 |
| 35.4192 | -106.7898 |

Name: 2035 Calabacillas fault (dip 65)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 6.83

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 65 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 1.984e-04 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.984e-04 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.984e-04 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 1.770e-04 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 3.787e-04 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 5.181e-04 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | Normal | 0.106666 | Activity | 8.097e-06 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 |
| | Normal | 0.319998 | Activity | 8.097e-06 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 |
| | Normal | 0.106666 | Activity | 8.097e-06 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 |
| | Exponential | 0.053334 | Activity | 7.248e-06 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Exponential | 0.160002 | Activity | 1.550e-05 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Exponential | 0.053334 | Activity | 2.121e-05 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Normal | 0.013334 | Activity | 9.028e-06 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 |
| | Normal | 0.040002 | Activity | 9.028e-06 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 |
| | Normal | 0.013334 | Activity | 9.028e-06 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 |
| | Exponential | 0.006666 | Activity | 8.047e-06 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Exponential | 0.019998 | Activity | 1.721e-05 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| | Exponential | 0.006666 | Activity | 2.355e-05 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |

```
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.1404  -106.8390
    35.2034  -106.8526
    35.2416  -106.8654
    35.2671  -106.8632
    35.3315  -106.8350
    35.4192  -106.7898

 ------ End Nested Sources for Calabacillas fault [2035] -------

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

*****************************************

Name: Mesa Prieta faults
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-
ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.50000000
Deterministic Magnitude: 6.3

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          60        60         0       0.1        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
          Normal         1        Slip   2.000e-02  6.000000  6.600000
0.000000  6.300000  0.120000  0.000000  0.000000
```

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.100000 | 4.000000 | 0.000000 | 0.100000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.5190 | -107.0400 |
| 35.4360 | -107.0760 |

Attenuation Equations for Source:

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

Name: Nacimiento fault [2002ab]
Region: USGS 2014 New Mexico
Category:Composite Seismic Source
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Regions\EZ-FRISK USGS2014 Lower 48 v1.00\Files\USGS 2014 Lower 48.bin-ssdb
Magnitude Scale: Moment Magnitude
Probability of Activity: 1
------ Start Nested Sources forNacimiento fault [2002ab] -------
Name: 2002ab Nacimiento fault (dip 35)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 7.3

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 35 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 1.041e-04 | 6.860000 | 7.340000 | 2.300000 | 7.100000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.041e-04 | 7.060000 | 7.540000 | 2.300000 | 7.300000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.041e-04 | 7.260000 | 7.740000 | 2.300000 | 7.500000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 3.949e-04 | 6.500000 | 7.100000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Exponential | 0.019998 | Activity | 4.551e-04 | 6.500000 | 7.300000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Exponential | 0.006666 | Activity | 4.968e-04 | 6.500000 | 7.500000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Normal | 0.106666 | Activity | 1.182e-05 | 6.860000 | 7.340000 | 2.300000 | 7.100000 |
| 0.120000 | 0.010000 | 10.000000 | | | | | |
| Normal | 0.319998 | Activity | 1.182e-05 | 7.060000 | 7.540000 | 2.300000 | 7.300000 |
| 0.120000 | 0.010000 | 10.000000 | | | | | |
| Normal | 0.106666 | Activity | 1.182e-05 | 7.260000 | 7.740000 | 2.300000 | 7.500000 |
| 0.120000 | 0.010000 | 10.000000 | | | | | |
| Exponential | 0.053334 | Activity | 4.483e-05 | 6.500000 | 7.100000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Exponential | 0.160002 | Activity | 5.167e-05 | 6.500000 | 7.300000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Exponential | 0.053334 | Activity | 5.640e-05 | 6.500000 | 7.500000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Normal | 0.013334 | Activity | 1.815e-05 | 6.860000 | 7.340000 | 2.300000 | 7.100000 |
| 0.120000 | 0.010000 | 10.000000 | | | | | |
| Normal | 0.040002 | Activity | 1.815e-05 | 7.060000 | 7.540000 | 2.300000 | 7.300000 |
| 0.120000 | 0.010000 | 10.000000 | | | | | |
| Normal | 0.013334 | Activity | 1.815e-05 | 7.260000 | 7.740000 | 2.300000 | 7.500000 |
| 0.120000 | 0.010000 | 10.000000 | | | | | |
| Exponential | 0.006666 | Activity | 6.868e-05 | 6.500000 | 7.100000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Exponential | 0.019998 | Activity | 7.916e-05 | 6.500000 | 7.300000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Exponential | 0.006666 | Activity | 8.640e-05 | 6.500000 | 7.500000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.4853 | -106.8574 |
| 35.5849 | -106.8557 |
| 35.6246 | -106.8577 |
| 35.6777 | -106.8687 |
| 35.7441 | -106.8701 |
| 35.7740 | -106.8782 |
| 35.7902 | -106.8878 |
| 35.8244 | -106.8941 |
| 35.8730 | -106.8830 |
| 35.8874 | -106.8885 |
| 35.8967 | -106.8886 |
| 35.9087 | -106.8936 |
| 35.9475 | -106.8926 |
| 35.9999 | -106.9014 |
| 36.0348 | -106.8992 |
| 36.0541 | -106.9073 |
| 36.0739 | -106.9093 |
| 36.0917 | -106.9093 |
| 36.1155 | -106.9015 |
| 36.1908 | -106.9112 |
| 36.1985 | -106.9056 |
| 36.2198 | -106.9021 |

Name: 2002ab Nacimiento fault (dip 50)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.60000000
Deterministic Magnitude: 7.3

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 50 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 1.041e-04 | 6.860000 | 7.340000 | 2.300000 | 7.100000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.041e-04 | 7.060000 | 7.540000 | 2.300000 | 7.300000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.041e-04 | 7.260000 | 7.740000 | 2.300000 | 7.500000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 3.949e-04 | 6.500000 | 7.100000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 4.551e-04 | 6.500000 | 7.300000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 4.968e-04 | 6.500000 | 7.500000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.106666 | Activity | 1.182e-05 | 6.860000 | 7.340000 | 2.300000 | 7.100000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.319998 | Activity | 1.182e-05 | 7.060000 | 7.540000 | 2.300000 | 7.300000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.106666 | Activity | 1.182e-05 | 7.260000 | 7.740000 | 2.300000 | 7.500000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.053334 | Activity | 4.483e-05 | 6.500000 | 7.100000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.160002 | Activity | 5.167e-05 | 6.500000 | 7.300000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.053334 | Activity | 5.640e-05 | 6.500000 | 7.500000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.013334 | Activity | 1.815e-05 | 6.860000 | 7.340000 | 2.300000 | 7.100000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.815e-05 | 7.060000 | 7.540000 | 2.300000 | 7.300000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.815e-05 | 7.260000 | 7.740000 | 2.300000 | 7.500000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 6.868e-05 | 6.500000 | 7.100000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 7.916e-05 | 6.500000 | 7.300000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 8.640e-05 | 6.500000 | 7.500000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.4853 | -106.8574 |
| 35.5849 | -106.8557 |
| 35.6246 | -106.8577 |
| 35.6777 | -106.8687 |
| 35.7441 | -106.8701 |
| 35.7740 | -106.8782 |
| 35.7902 | -106.8878 |
| 35.8244 | -106.8941 |
| 35.8730 | -106.8830 |
| 35.8874 | -106.8885 |
| 35.8967 | -106.8886 |
| 35.9087 | -106.8936 |
| 35.9475 | -106.8926 |
| 35.9999 | -106.9014 |
| 36.0348 | -106.8992 |
| 36.0541 | -106.9073 |
| 36.0739 | -106.9093 |
| 36.0917 | -106.9093 |
| 36.1155 | -106.9015 |
| 36.1908 | -106.9112 |
| 36.1985 | -106.9056 |
| 36.2198 | -106.9021 |

Name: 2002ab Nacimiento fault (dip 65)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal

Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 7.3

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 65 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 1.041e-04 | 6.860000 | 7.340000 | 2.300000 | 7.100000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.041e-04 | 7.060000 | 7.540000 | 2.300000 | 7.300000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.041e-04 | 7.260000 | 7.740000 | 2.300000 | 7.500000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 3.949e-04 | 6.500000 | 7.100000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 4.551e-04 | 6.500000 | 7.300000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 4.968e-04 | 6.500000 | 7.500000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.106666 | Activity | 1.182e-05 | 6.860000 | 7.340000 | 2.300000 | 7.100000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.319998 | Activity | 1.182e-05 | 7.060000 | 7.540000 | 2.300000 | 7.300000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.106666 | Activity | 1.182e-05 | 7.260000 | 7.740000 | 2.300000 | 7.500000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.053334 | Activity | 4.483e-05 | 6.500000 | 7.100000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.160002 | Activity | 5.167e-05 | 6.500000 | 7.300000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.053334 | Activity | 5.640e-05 | 6.500000 | 7.500000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.013334 | Activity | 1.815e-05 | 6.860000 | 7.340000 | 2.300000 | 7.100000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.815e-05 | 7.060000 | 7.540000 | 2.300000 | 7.300000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.815e-05 | 7.260000 | 7.740000 | 2.300000 | 7.500000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 6.868e-05 | 6.500000 | 7.100000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 7.916e-05 | 6.500000 | 7.300000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 8.640e-05 | 6.500000 | 7.500000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.4853 | -106.8574 |
| 35.5849 | -106.8557 |
| 35.6246 | -106.8577 |
| 35.6777 | -106.8687 |
| 35.7441 | -106.8701 |
| 35.7740 | -106.8782 |
| 35.7902 | -106.8878 |
| 35.8244 | -106.8941 |
| 35.8730 | -106.8830 |
| 35.8874 | -106.8885 |
| 35.8967 | -106.8886 |
| 35.9087 | -106.8936 |
| 35.9475 | -106.8926 |
| 35.9999 | -106.9014 |
| 36.0348 | -106.8992 |
| 36.0541 | -106.9073 |
| 36.0739 | -106.9093 |

```
    36.0917  -106.9093
    36.1155  -106.9015
    36.1908  -106.9112
    36.1985  -106.9056
    36.2198  -106.9021

 ------ End Nested Sources for Nacimiento fault [2002ab] -------

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

*****************************************

Name: San Felipe fault zone [2030a]
Region: USGS 2014 New Mexico
Category:Composite Seismic Source
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Regions\EZ-FRISK
USGS2014 Lower 48 v1.00\Files\USGS 2014 Lower 48.bin-ssdb
Magnitude Scale: Moment Magnitude
Probability of Activity: 1
 ------ Start Nested Sources forSan Felipe fault zone [2030a] -------
Name: 2030a San Felipe fault zone (dip 35)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 6.97

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          90        35         0     0.001        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
           Normal  0.013334    Activity   3.667e-05  6.530000  7.010000
2.300000  6.770000  0.120000  0.010000 10.000000
           Normal  0.040002    Activity   3.667e-05  6.730000  7.210000
2.300000  6.970000  0.120000  0.010000 10.000000
           Normal  0.013334    Activity   3.667e-05  6.930000  7.410000
2.300000  7.170000  0.120000  0.010000 10.000000
      Exponential  0.006666    Activity   6.049e-05  6.500000  6.770000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.019998    Activity   8.942e-05  6.500000  6.970000
1.842068  0.000000  0.000000  0.000000  0.000000
```

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Exponential | 0.006666 | Activity | 1.094e-04 | 6.500000 | 7.170000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| Normal | 0.106666 | Activity | 4.114e-05 | 6.530000 | 7.010000 | 2.300000 | 6.770000 | 0.120000 | 0.010000 | 10.000000 | |
| Normal | 0.319998 | Activity | 4.114e-05 | 6.730000 | 7.210000 | 2.300000 | 6.970000 | 0.120000 | 0.010000 | 10.000000 | |
| Normal | 0.106666 | Activity | 4.114e-05 | 6.930000 | 7.410000 | 2.300000 | 7.170000 | 0.120000 | 0.010000 | 10.000000 | |
| Exponential | 0.053334 | Activity | 6.791e-05 | 6.500000 | 6.770000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| Exponential | 0.160002 | Activity | 1.004e-04 | 6.500000 | 6.970000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| Exponential | 0.053334 | Activity | 1.229e-04 | 6.500000 | 7.170000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| Normal | 0.013334 | Activity | 5.863e-05 | 6.530000 | 7.010000 | 2.300000 | 6.770000 | 0.120000 | 0.010000 | 10.000000 | |
| Normal | 0.040002 | Activity | 5.863e-05 | 6.730000 | 7.210000 | 2.300000 | 6.970000 | 0.120000 | 0.010000 | 10.000000 | |
| Normal | 0.013334 | Activity | 5.863e-05 | 6.930000 | 7.410000 | 2.300000 | 7.170000 | 0.120000 | 0.010000 | 10.000000 | |
| Exponential | 0.006666 | Activity | 9.678e-05 | 6.500000 | 6.770000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| Exponential | 0.019998 | Activity | 1.431e-04 | 6.500000 | 6.970000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| Exponential | 0.006666 | Activity | 1.751e-04 | 6.500000 | 7.170000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.3121 | -106.6081 |
| 35.3270 | -106.6074 |
| 35.3567 | -106.5956 |
| 35.3788 | -106.5946 |
| 35.4247 | -106.6022 |
| 35.4578 | -106.6165 |
| 35.4795 | -106.6103 |
| 35.5200 | -106.6145 |
| 35.5312 | -106.6112 |
| 35.5464 | -106.5983 |
| 35.5640 | -106.5927 |
| 35.5981 | -106.5979 |
| 35.6192 | -106.5958 |
| 35.6399 | -106.6049 |
| 35.6641 | -106.6000 |
| 35.6832 | -106.5846 |

Name: 2030a San Felipe fault zone (dip 50)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.60000000
Deterministic Magnitude: 6.97

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 50 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 3.667e-05 | 6.530000 | 7.010000 | 2.300000 | 6.770000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 3.667e-05 | 6.730000 | 7.210000 | 2.300000 | 6.970000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 3.667e-05 | 6.930000 | 7.410000 | 2.300000 | 7.170000 | 0.120000 | 0.010000 | 10.000000 |

| | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Exponential | 0.006666 | Activity | 6.049e-05 | 6.500000 | 6.770000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.019998 | Activity | 8.942e-05 | 6.500000 | 6.970000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.006666 | Activity | 1.094e-04 | 6.500000 | 7.170000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Normal | 0.106666 | Activity | 4.114e-05 | 6.530000 | 7.010000 | 2.300000 | 6.770000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.319998 | Activity | 4.114e-05 | 6.730000 | 7.210000 | 2.300000 | 6.970000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.106666 | Activity | 4.114e-05 | 6.930000 | 7.410000 | 2.300000 | 7.170000 | 0.120000 | 0.010000 | 10.000000 | |
| | Exponential | 0.053334 | Activity | 6.791e-05 | 6.500000 | 6.770000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.160002 | Activity | 1.004e-04 | 6.500000 | 6.970000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.053334 | Activity | 1.229e-04 | 6.500000 | 7.170000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Normal | 0.013334 | Activity | 5.863e-05 | 6.530000 | 7.010000 | 2.300000 | 6.770000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.040002 | Activity | 5.863e-05 | 6.730000 | 7.210000 | 2.300000 | 6.970000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.013334 | Activity | 5.863e-05 | 6.930000 | 7.410000 | 2.300000 | 7.170000 | 0.120000 | 0.010000 | 10.000000 | |
| | Exponential | 0.006666 | Activity | 9.678e-05 | 6.500000 | 6.770000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.019998 | Activity | 1.431e-04 | 6.500000 | 6.970000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.006666 | Activity | 1.751e-04 | 6.500000 | 7.170000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.3121 | -106.6081 |
| 35.3270 | -106.6074 |
| 35.3567 | -106.5956 |
| 35.3788 | -106.5946 |
| 35.4247 | -106.6022 |
| 35.4578 | -106.6165 |
| 35.4795 | -106.6103 |
| 35.5200 | -106.6145 |
| 35.5312 | -106.6112 |
| 35.5464 | -106.5983 |
| 35.5640 | -106.5927 |
| 35.5981 | -106.5979 |
| 35.6192 | -106.5958 |
| 35.6399 | -106.6049 |
| 35.6641 | -106.6000 |
| 35.6832 | -106.5846 |

Name: 2030a San Felipe fault zone (dip 65)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 6.97

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 65 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 3.667e-05 | 6.530000 | 7.010000 | 2.300000 | 6.770000 | 0.120000 | 0.010000 | 10.000000 |

| | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Normal | 0.040002 | Activity | 3.667e-05 | 6.730000 | 7.210000 | 2.300000 | 6.970000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.013334 | Activity | 3.667e-05 | 6.930000 | 7.410000 | 2.300000 | 7.170000 | 0.120000 | 0.010000 | 10.000000 | |
| | Exponential | 0.006666 | Activity | 6.049e-05 | 6.500000 | 6.770000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.019998 | Activity | 8.942e-05 | 6.500000 | 6.970000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.006666 | Activity | 1.094e-04 | 6.500000 | 7.170000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Normal | 0.106666 | Activity | 4.114e-05 | 6.530000 | 7.010000 | 2.300000 | 6.770000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.319998 | Activity | 4.114e-05 | 6.730000 | 7.210000 | 2.300000 | 6.970000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.106666 | Activity | 4.114e-05 | 6.930000 | 7.410000 | 2.300000 | 7.170000 | 0.120000 | 0.010000 | 10.000000 | |
| | Exponential | 0.053334 | Activity | 6.791e-05 | 6.500000 | 6.770000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.160002 | Activity | 1.004e-04 | 6.500000 | 6.970000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.053334 | Activity | 1.229e-04 | 6.500000 | 7.170000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Normal | 0.013334 | Activity | 5.863e-05 | 6.530000 | 7.010000 | 2.300000 | 6.770000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.040002 | Activity | 5.863e-05 | 6.730000 | 7.210000 | 2.300000 | 6.970000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.013334 | Activity | 5.863e-05 | 6.930000 | 7.410000 | 2.300000 | 7.170000 | 0.120000 | 0.010000 | 10.000000 | |
| | Exponential | 0.006666 | Activity | 9.678e-05 | 6.500000 | 6.770000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.019998 | Activity | 1.431e-04 | 6.500000 | 6.970000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.006666 | Activity | 1.751e-04 | 6.500000 | 7.170000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |

```
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.3121  -106.6081
    35.3270  -106.6074
    35.3567  -106.5956
    35.3788  -106.5946
    35.4247  -106.6022
    35.4578  -106.6165
    35.4795  -106.6103
    35.5200  -106.6145
    35.5312  -106.6112
    35.5464  -106.5983
    35.5640  -106.5927
    35.5981  -106.5979
    35.6192  -106.5958
    35.6399  -106.6049
    35.6641  -106.6000
    35.6832  -106.5846

 ------ End Nested Sources for San Felipe fault zone [2030a] -------

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

*****************************************
```

Name: San Felipe fault zone (Algodones section)
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.50000000
Deterministic Magnitude: 7

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 60 | 60 | 0 | 0.1 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 1 | Slip | 2.000e-02 | 6.700000 | 7.300000 | 0.000000 | 7.000000 | 0.120000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.100000 | 4.000000 | 0.000000 | 0.100000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.5690 | -106.4950 |
| 35.3340 | -106.5250 |

Attenuation Equations for Source:

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

Name: Sand Hill fault zone
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.50000000
Deterministic Magnitude: 6.9

Fault Profile Parameters:

```
        Dip1      Dip2    Depth1    Depth2    Depth3
          60        60         0       0.1        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
           Normal         1        Slip   2.000e-02  6.600000  7.200000
0.000000  6.900000  0.120000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.100000  4.000000  0.000000
0.100000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.4440  -106.8690
    35.1400  -106.8840

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

****************************************

Name: Santa Fe fault
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-
ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.50000000
Deterministic Magnitude: 6.8

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          60        60         0       0.1        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
           Normal         1        Slip   2.000e-02  6.500000  7.100000
0.000000  6.800000  0.120000  0.000000  0.000000

Rupture Length Parameters
```

```
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.100000  4.000000  0.000000
0.100000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    34.8880  -107.0530
    34.6360  -107.1040

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

*****************************************

Name: unnamed fault of Bonita Canyon
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-
ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.50000000
Deterministic Magnitude: 6.1

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          60        60         0       0.1        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
           Normal         1        Slip   2.000e-02  5.800000  6.400000
0.000000  6.100000  0.120000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.100000  4.000000  0.000000
0.100000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    34.9800  -107.9510
    34.9250  -107.9400

Attenuation Equations for Source:
```

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

Name: unnamed faults near Albuquerque Volcanoes
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 1.00000000
Deterministic Magnitude: 6.9

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 60 | 60 | 0 | 0.1 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 1 | Slip | 2.000e-02 | 6.600000 | 7.200000 | 0.000000 | 6.900000 | 0.120000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.100000 | 4.000000 | 0.000000 | 0.100000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.2180 | -106.7620 |
| 35.0650 | -106.7500 |

Attenuation Equations for Source:

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

Name: unnamed faults near Picuda Peak
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.50000000
Deterministic Magnitude: 6.4

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 60 | 60 | 0 | 0.1 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 1 | Slip | 2.000e-02 | 6.100000 | 6.700000 | 0.000000 | 6.400000 | 0.120000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.100000 | 4.000000 | 0.000000 | 0.100000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.4270 | -106.6850 |
| 35.2830 | -106.6880 |

Attenuation Equations for Source:

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

Name: unnamed faults near Star Heights
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 1.00000000
Deterministic Magnitude: 6.5

Fault Profile Parameters:

```
        Dip1      Dip2    Depth1    Depth2    Depth3
          70        70         0       0.1        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
           Normal         1        Slip   2.000e-02  6.200000  6.800000
0.000000  6.500000  0.120000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.100000  4.000000  0.000000
0.100000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.3510  -106.7250
    35.1680  -106.7160

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

****************************************

Name: unnamed faults of El Malpais lava field
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-
ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.50000000
Deterministic Magnitude: 6.7

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          60        60         0       0.1        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
           Normal         1        Slip   2.000e-02  6.400000  7.000000
0.000000  6.700000  0.120000  0.000000  0.000000

Rupture Length Parameters
```

```
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.100000  4.000000  0.000000
0.100000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    34.8880  -108.0030
    34.5720  -108.1560

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

*****************************************

Name: unnamed intrabasin faults west of the Rio Puerco
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-
ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 1.00000000
Deterministic Magnitude: 6.6

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          60        60         0       0.1        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
          Normal         1        Slip   2.000e-02  6.300000  6.900000
0.000000  6.600000  0.120000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.100000  4.000000  0.000000
0.100000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    34.7190  -106.9930
    34.4700  -106.9620

Attenuation Equations for Source:
```

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

Name: Zia fault [2046]
Region: USGS 2014 New Mexico
Category:Composite Seismic Source
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Regions\EZ-FRISK USGS2014 Lower 48 v1.00\Files\USGS 2014 Lower 48.bin-ssdb
Magnitude Scale: Moment Magnitude
Probability of Activity: 1
------ Start Nested Sources forZia fault [2046] -------
Name: 2046 Zia fault (dip 35)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 6.84

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 35 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 4.384e-05 | 6.400000 | 6.880000 | 2.300000 | 6.640000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 4.384e-05 | 6.600000 | 7.080000 | 2.300000 | 6.840000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 4.384e-05 | 6.800000 | 7.280000 | 2.300000 | 7.040000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 4.160e-05 | 6.500000 | 6.640000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 8.517e-05 | 6.500000 | 6.840000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 1.153e-04 | 6.500000 | 7.040000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.106666 | Activity | 4.356e-05 | 6.400000 | 6.880000 | 2.300000 | 6.640000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.319998 | Activity | 4.356e-05 | 6.600000 | 7.080000 | 2.300000 | 6.840000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.106666 | Activity | 4.356e-05 | 6.800000 | 7.280000 | 2.300000 | 7.040000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.053334 | Activity | 4.127e-05 | 6.500000 | 6.640000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

```
      Exponential  0.160002    Activity   8.450e-05  6.500000  6.840000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.053334    Activity   1.144e-04  6.500000  7.040000
1.842068  0.000000  0.000000  0.000000  0.000000
           Normal  0.013334    Activity   5.268e-05  6.400000  6.880000
2.300000  6.640000  0.120000  0.010000 10.000000
           Normal  0.040002    Activity   5.268e-05  6.600000  7.080000
2.300000  6.840000  0.120000  0.010000 10.000000
           Normal  0.013334    Activity   5.268e-05  6.800000  7.280000
2.300000  7.040000  0.120000  0.010000 10.000000
      Exponential  0.006666    Activity   4.992e-05  6.500000  6.640000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.019998    Activity   1.022e-04  6.500000  6.840000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.006666    Activity   1.384e-04  6.500000  7.040000
1.842068  0.000000  0.000000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
```

Length and width -3.220000 0.690000 0.220000 -3.220000 0.690000 0.220000 -- -- --

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.1892 | -106.8434 |
| 35.2802 | -106.8231 |
| 35.3228 | -106.7957 |
| 35.3473 | -106.7841 |
| 35.3751 | -106.7784 |
| 35.4006 | -106.7624 |
| 35.4706 | -106.7481 |

Name: 2046 Zia fault (dip 50)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.60000000
Deterministic Magnitude: 6.84

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 50 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 4.384e-05 | 6.400000 | 6.880000 | 2.300000 | 6.640000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 4.384e-05 | 6.600000 | 7.080000 | 2.300000 | 6.840000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 4.384e-05 | 6.800000 | 7.280000 | 2.300000 | 7.040000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 4.160e-05 | 6.500000 | 6.640000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 8.517e-05 | 6.500000 | 6.840000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 1.153e-04 | 6.500000 | 7.040000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.106666 | Activity | 4.356e-05 | 6.400000 | 6.880000 | 2.300000 | 6.640000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.319998 | Activity | 4.356e-05 | 6.600000 | 7.080000 | 2.300000 | 6.840000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.106666 | Activity | 4.356e-05 | 6.800000 | 7.280000 | 2.300000 | 7.040000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.053334 | Activity | 4.127e-05 | 6.500000 | 6.640000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.160002 | Activity | 8.450e-05 | 6.500000 | 6.840000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.053334 | Activity | 1.144e-04 | 6.500000 | 7.040000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.013334 | Activity | 5.268e-05 | 6.400000 | 6.880000 | 2.300000 | 6.640000 | 0.120000 | 0.010000 | 10.000000 |

```
           Normal  0.040002    Activity   5.268e-05  6.600000  7.080000
2.300000  6.840000  0.120000  0.010000 10.000000
           Normal  0.013334    Activity   5.268e-05  6.800000  7.280000
2.300000  7.040000  0.120000  0.010000 10.000000
      Exponential  0.006666    Activity   4.992e-05  6.500000  6.640000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.019998    Activity   1.022e-04  6.500000  6.840000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.006666    Activity   1.384e-04  6.500000  7.040000
1.842068  0.000000  0.000000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.1892  -106.8434
```

35.2802 -106.8231
35.3228 -106.7957
35.3473 -106.7841
35.3751 -106.7784
35.4006 -106.7624
35.4706 -106.7481

Name: 2046 Zia fault (dip 65)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 6.84

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 65 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 4.384e-05 | 6.400000 | 6.880000 | 2.300000 | 6.640000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 4.384e-05 | 6.600000 | 7.080000 | 2.300000 | 6.840000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 4.384e-05 | 6.800000 | 7.280000 | 2.300000 | 7.040000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 4.160e-05 | 6.500000 | 6.640000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 8.517e-05 | 6.500000 | 6.840000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 1.153e-04 | 6.500000 | 7.040000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.106666 | Activity | 4.356e-05 | 6.400000 | 6.880000 | 2.300000 | 6.640000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.319998 | Activity | 4.356e-05 | 6.600000 | 7.080000 | 2.300000 | 6.840000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.106666 | Activity | 4.356e-05 | 6.800000 | 7.280000 | 2.300000 | 7.040000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.053334 | Activity | 4.127e-05 | 6.500000 | 6.640000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.160002 | Activity | 8.450e-05 | 6.500000 | 6.840000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.053334 | Activity | 1.144e-04 | 6.500000 | 7.040000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.013334 | Activity | 5.268e-05 | 6.400000 | 6.880000 | 2.300000 | 6.640000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 5.268e-05 | 6.600000 | 7.080000 | 2.300000 | 6.840000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 5.268e-05 | 6.800000 | 7.280000 | 2.300000 | 7.040000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 4.992e-05 | 6.500000 | 6.640000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

```
      Exponential  0.019998    Activity   1.022e-04  6.500000  6.840000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.006666    Activity   1.384e-04  6.500000  7.040000
1.842068  0.000000  0.000000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.1892  -106.8434
    35.2802  -106.8231
    35.3228  -106.7957
    35.3473  -106.7841
    35.3751  -106.7784
    35.4006  -106.7624
    35.4706  -106.7481
```

------ End Nested Sources for Zia fault [2046] -------

Attenuation Equations for Source:

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

MAGNITUDE CONVERSIONS

This analysis does not require any magnitude conversions.
Note: Your analysis may indirectly use magnitude conversions that are not listed here.

Echo File Creation Time: 14:08:38 Thursday, September 18, 2025

# APPENDIX C.2
# DETERMINISTIC RESULTS

## Appendix C.2 Results of Deterministic Hazard Analysis

| Name of Faults | ID Number | Age of Most Recent Prehistoric Deformation (ya)[1] | Slip-rate (mm/yr) | Fault Length (Km) | Fault Type | Distance from site to surface trace of fault (km) | MCE[2,3] | PGA | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | Lognormal Mean | | Arahamson-et al (2014) | | Borre-et al (2014) | | Campbell-Bozorgnia (2014) | | Chiou-Youngs (2014) | |
| | | | | | | | | Mean | Mean +1SD | Mean | Mean +1SD | Mean | Mean +1SD | Mean | Mean +1SD | Mean | Mean +1SD |
| Random Earthquake | - | - | - | - | - | 15.1 | 6.3 | 0.09 | 0.17 | 0.09 | 0.16 | 0.09 | 0.16 | 0.12 | 0.21 | 0.08 | 0.14 |
| Cat Mesa fault | 2122 | <750,000 | <0.2 | 20 | Normal | 75.9 | 6.6 | 0.02 | 0.04 | 0.02 | 0.04 | 0.02 | 0.03 | 0.02 | 0.04 | 0.02 | 0.03 |
| Cebollita Mesa fault | 2140 | <15,000 | <0.2 | 13 | Normal | 74.8 | 6.3 | 0.01 | 0.03 | 0.01 | 0.03 | 0.02 | 0.03 | 0.02 | 0.03 | 0.01 | 0.02 |
| Continental Divide fault | 2145 | <1,600,000 | <0.2 | 17 | Normal | 91.8 | 6.5 | 0.01 | 0.02 | 0.01 | 0.02 | 0.01 | 0.02 | 0.02 | 0.03 | 0.01 | 0.02 |
| County Dump fault[(3)] | 2038 | <130,000 | <0.2 | 35 | Normal | 76.5 | 6.89 | 0.02 | 0.04 | 0.02 | 0.05 | 0.02 | 0.04 | 0.03 | 0.05 | 0.02 | 0.04 |
| Coyote Springs fault | 2114 | <15,000 | <0.2 | 17 | Normal | 93.4 | 6.5 | 0.01 | 0.02 | 0.01 | 0.02 | 0.01 | 0.02 | 0.02 | 0.03 | 0.01 | 0.02 |
| Intrabasin faults on the Llano de Albuquerque | 2121 | <750,000 | <0.2 | 101 | Normal | 66.7 | 7.5 | 0.04 | 0.08 | 0.05 | 0.09 | 0.04 | 0.07 | 0.05 | 0.09 | 0.04 | 0.08 |
| Jemez-San Ysidro fault (Jemez section)[(3)] | 2029a | <1,600,000 | <0.2 | 28 | Normal | 77.3 | 7.09 | 0.03 | 0.05 | 0.03 | 0.05 | 0.03 | 0.05 | 0.03 | 0.06 | 0.03 | 0.04 |
| Jemez-San Ysidro fault (San Ysidro section)[(3)] | 2029b | <750,000 | <0.2 | 34 | Normal | 77.3 | 7.09 | | | | | | | | | | |
| Jemez-San Ysidro fault (Calabacillas section)[(3)] | 2029c | <15,000 | <0.2 | 34 | Normal | 70.5 | 6.83 | 0.03 | 0.05 | 0.03 | 0.05 | 0.02 | 0.04 | 0.03 | 0.05 | 0.02 | 0.04 |
| Mesa Prieta faults | 1985 | <1,600,000 | <0.2 | 12 | Normal | 47.1 | 6.3 | 0.03 | 0.05 | 0.02 | 0.05 | 0.03 | 0.05 | 0.03 | 0.06 | 0.02 | 0.04 |
| Nacimiento fault (northern section)[(3)] | 2002a | <1,600,000 | <0.2 | 36 | Normal | 72.3 | 7.30 | 0.03 | 0.06 | 0.04 | 0.07 | 0.03 | 0.06 | 0.04 | 0.07 | 0.03 | 0.06 |
| Nacimiento fault (southern section)[(3)] | 2002b | <750,000 | <0.2 | 45 | Normal | 72.3 | 7.30 | | | | | | | | | | |
| San Felipe fault zone (Santa Ana section)[(3)] | 2030a | <1,600,000 | <0.2 | 44 | Normal | 93.2 | 6.97 | 0.02 | 0.04 | 0.02 | 0.04 | 0.02 | 0.03 | 0.02 | 0.04 | 0.02 | 0.03 |
| San Felipe fault zone (Algodones section) | 2030b | <1,600,000 | <0.2 | 45 | Normal | 93.3 | 7.0 | 0.02 | 0.04 | 0.02 | 0.04 | 0.02 | 0.03 | 0.02 | 0.04 | 0.02 | 0.03 |
| Sand Hill fault zone | 2039 | <1,600,000 | <0.2 | 36 | Normal | 62.2 | 6.9 | 0.03 | 0.06 | 0.03 | 0.06 | 0.03 | 0.05 | 0.04 | 0.07 | 0.03 | 0.05 |
| Santa Fe fault | 2123 | <1,600,000 | <0.2 | 30 | Normal | 67.8 | 6.8 | 0.03 | 0.05 | 0.03 | 0.05 | 0.03 | 0.05 | 0.03 | 0.06 | 0.02 | 0.04 |
| unnamed fault of Bonita Canyon | 2144 | <1,600,000 | <0.2 | 9 | Normal | 49.3 | 6.1 | 0.02 | 0.04 | 0.02 | 0.04 | 0.02 | 0.04 | 0.03 | 0.05 | 0.02 | 0.03 |
| unnamed faults near Albuquerque Volcanoes | 2049 | <750,000 | <0.2 | 34 | Normal | 73.6 | 6.9 | 0.03 | 0.05 | 0.03 | 0.05 | 0.02 | 0.04 | 0.03 | 0.05 | 0.02 | 0.04 |
| unnamed faults near Picuda Peak | 2041 | <1,600,000 | <0.2 | 16 | Normal | 78.8 | 6.4 | 0.02 | 0.03 | 0.01 | 0.03 | 0.02 | 0.03 | 0.02 | 0.04 | 0.01 | 0.02 |
| unnamed faults near Star Heights | 2048 | <750,000 | <0.2 | 18 | Normal | 78.6 | 6.5 | 0.02 | 0.03 | 0.02 | 0.03 | 0.02 | 0.03 | 0.02 | 0.04 | 0.01 | 0.02 |
| unnamed faults of El Malpais lava field | 2146 | <1,600,000 | <0.2 | 26 | Normal | 60.5 | 6.7 | 0.03 | 0.05 | 0.03 | 0.05 | 0.03 | 0.05 | 0.03 | 0.06 | 0.02 | 0.04 |
| unnamed intrabasin faults west of the Rio Puerco | 2115 | <750,000 | <0.2 | 22 | Normal | 87.3 | 6.6 | 0.02 | 0.03 | 0.02 | 0.03 | 0.02 | 0.03 | 0.02 | 0.04 | 0.01 | 0.02 |
| Zia fault[(3)] | 2046 | <15,000 | <0.2 | 32 | Normal | 73.7 | 6.84 | 0.02 | 0.04 | 0.02 | 0.05 | 0.02 | 0.04 | 0.03 | 0.05 | 0.02 | 0.04 |

[1]ya = years ago

[2]Wells and Coopersmith (1994)

[3]The parameters included in the EZ Frisk program from the USGS Hazard mapping used for analysis

Deterministic Spectra Results using EZ-FRISK 8.11 Build 019

Largest Amplitudes of Ground Motions Considering All Sources Calculated using Weighted Mean of Attenuation Equations
Amplitude Units: Acceleration (g)

Fractile: 0.5

| Period | Amplitude | Magnitude | Closest Distance(km) | Region | Controlling Source |
|---|---|---|---|---|---|
| PGA | 9.248e-02 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.05 | 1.448e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.1 | 1.997e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.2 | 1.987e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.3 | 1.529e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.4 | 1.192e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.5 | 9.607e-02 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.75 | 6.452e-02 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 1 | 4.625e-02 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 2 | 2.025e-02 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 3 | 1.229e-02 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 4 | 9.177e-03 | 7.50 Mw | 66.71 | Mt Taylor | Deterministic Intrabasin faults on the Llano de Albuquerque |

Fractile: 0.84

| Period | Amplitude | Magnitude | Closest Distance(km) | Region | Controlling Source |
|---|---|---|---|---|---|
| PGA | 1.695e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.05 | 2.768e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.1 | 3.937e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.2 | 3.815e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.3 | 2.935e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.4 | 2.308e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.5 | 1.886e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |

| | | | | | |
|---|---|---|---|---|---|
| 0.75 | 1.301e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 1 | 9.416e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 2 | 4.145e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 3 | 2.515e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 4 | 1.851e-02 | 7.50 Mw | 66.71 | Mt Taylor Deterministic Intrabasin faults on the Llano de Albuquerque | |

Largest Amplitudes of Ground Motions Considering Sources Calculated with Abrahamson-et al (2014) NGA West 2 USGS 2014
Amplitude Units: Acceleration (g)

Fractile: 0.5

| Period | Amplitude | Magnitude | Closest Distance(km) | Region | Controlling Source |
|---|---|---|---|---|---|
| PGA | 8.560e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic | Random Earthquake |
| 0.05 | 1.112e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic | Random Earthquake |
| 0.1 | 1.690e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic | Random Earthquake |
| 0.2 | 1.680e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic | Random Earthquake |
| 0.3 | 1.250e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic | Random Earthquake |
| 0.4 | 9.558e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic | Random Earthquake |
| 0.5 | 7.845e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic | Random Earthquake |
| 0.75 | 5.106e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic | Random Earthquake |
| 1 | 3.775e-02 | 7.50 Mw | 66.71 | Mt Taylor Deterministic | Intrabasin faults on the Llano de Albuquerque |
| 2 | 2.364e-02 | 7.50 Mw | 66.71 | Mt Taylor Deterministic | Intrabasin faults on the Llano de Albuquerque |
| 3 | 1.730e-02 | 7.50 Mw | 66.71 | Mt Taylor Deterministic | Intrabasin faults on the Llano de Albuquerque |
| 4 | 1.270e-02 | 7.50 Mw | 66.71 | Mt Taylor Deterministic | Intrabasin faults on the Llano de Albuquerque |

Fractile: 0.84

| Period | Amplitude | Magnitude | Closest Distance(km) | Region | Controlling Source |
|---|---|---|---|---|---|
| PGA | 1.642e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic | Random Earthquake |
| 0.05 | 2.150e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic | Random Earthquake |

| | | | | | |
|---|---|---|---|---|---|
| 0.1 | 3.321e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.2 | 3.342e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.3 | 2.517e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.4 | 1.940e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.5 | 1.606e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.75 | 1.058e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 1 | 7.872e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 2 | 4.950e-02 | 7.50 Mw | 66.71 | Mt Taylor Deterministic Intrabasin faults on the Llano de Albuquerque | |
| 3 | 3.591e-02 | 7.50 Mw | 66.71 | Mt Taylor Deterministic Intrabasin faults on the Llano de Albuquerque | |
| 4 | 2.614e-02 | 7.50 Mw | 66.71 | Mt Taylor Deterministic Intrabasin faults on the Llano de Albuquerque | |

Largest Amplitudes of Ground Motions Considering Sources Calculated with Boore-et al (2014) NGA West 2 USGS 2014
Amplitude Units: Acceleration (g)

Fractile: 0.5

| Period | Amplitude | Magnitude | Closest Distance(km) | Region | Controlling Source |
|---|---|---|---|---|---|
| PGA | 8.586e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.05 | 1.307e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.1 | 1.803e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.2 | 2.075e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.3 | 1.626e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.4 | 1.261e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.5 | 9.983e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.75 | 6.853e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 1 | 5.002e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 2 | 2.062e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 3 | 1.373e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 4 | 1.025e-02 | 7.50 Mw | 66.71 | Mt Taylor Deterministic Intrabasin faults on the Llano de Albuquerque | |

Fractile: 0.84

| Period | Amplitude | Magnitude | Closest Distance(km) | Region | Controlling Source |
|---|---|---|---|---|---|
| PGA | 1.567e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.05 | 2.574e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.1 | 3.648e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.2 | 3.848e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.3 | 2.970e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.4 | 2.328e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.5 | 1.886e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.75 | 1.343e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 1 | 9.959e-02 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 2 | 4.137e-02 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 3 | 2.777e-02 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 4 | 2.072e-02 | 7.50 Mw | 66.71 | Mt Taylor | Deterministic Intrabasin faults on the Llano de Albuquerque |

Largest Amplitudes of Ground Motions Considering Sources Calculated with Campbell-Bozorgnia (2014) NGA West 2 USGS 2014

Amplitude Units: Acceleration (g)

Fractile: 0.5

| Period | Amplitude | Magnitude | Closest Distance(km) | Region | Controlling Source |
|---|---|---|---|---|---|
| PGA | 1.183e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.05 | 2.044e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.1 | 2.594e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.2 | 2.386e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.3 | 1.850e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.4 | 1.452e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |
| 0.5 | 1.158e-01 | 6.30 Mw | 15.09 | Mt Taylor | Deterministic Random Earthquake |

| | | | | | |
|---|---|---|---|---|---|
| 0.75 | 7.848e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 1 | 5.536e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 2 | 2.357e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 3 | 1.375e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 4 | 9.487e-03 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |

Fractile: 0.84

| Period | Amplitude | Magnitude | Closest Distance(km) | Region | Controlling Source |
|---|---|---|---|---|---|
| PGA | 2.123e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.05 | 3.872e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.1 | 5.153e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.2 | 4.541e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.3 | 3.504e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.4 | 2.768e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.5 | 2.243e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.75 | 1.593e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 1 | 1.133e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 2 | 4.781e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 3 | 2.793e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 4 | 1.872e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |

Largest Amplitudes of Ground Motions Considering Sources Calculated with Chiou-Youngs (2014) NGA West 2 USGS 2014

Amplitude Units: Acceleration (g)

Fractile: 0.5

| Period | Amplitude | Magnitude | Closest Distance(km) | Region | Controlling Source |
|---|---|---|---|---|---|
| PGA | 8.015e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.05 | 1.330e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |

| | | | | | |
|---|---|---|---|---|---|
| 0.1 | 1.902e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.2 | 1.809e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.3 | 1.392e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.4 | 1.102e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.5 | 9.024e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.75 | 6.000e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 1 | 4.210e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 2 | 1.634e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 3 | 8.738e-03 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 4 | 5.425e-03 | 7.50 Mw | 66.71 | Mt Taylor Deterministic Intrabasin faults on the Llano de Albuquerque | |

Fractile: 0.84

| Period | Amplitude | Magnitude | Closest Distance(km) | Region | Controlling Source |
|---|---|---|---|---|---|
| PGA | 1.448e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.05 | 2.478e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.1 | 3.626e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.2 | 3.529e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.3 | 2.750e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.4 | 2.195e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.5 | 1.809e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 0.75 | 1.211e-01 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 1 | 8.502e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 2 | 3.294e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 3 | 1.751e-02 | 6.30 Mw | 15.09 | Mt Taylor Deterministic Random Earthquake | |
| 4 | 1.074e-02 | 7.50 Mw | 66.71 | Mt Taylor Deterministic Intrabasin faults on the Llano de Albuquerque | |

Largest Amplitudes of Ground Motions for Each Source

Source: Random Earthquake
Region: Mt Taylor Deterministic
  Closest Distance: 15.09 km
  Amplitude Units: Acceleration (g)
  Magnitude: 6.30 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 9.248e-02 | 8.560e-02 | 8.586e-02 | 1.183e-01 | 8.015e-02 |
| 0.05 | 1.448e-01 | 1.112e-01 | 1.307e-01 | 2.044e-01 | 1.330e-01 |
| 0.1 | 1.997e-01 | 1.690e-01 | 1.803e-01 | 2.594e-01 | 1.902e-01 |
| 0.2 | 1.987e-01 | 1.680e-01 | 2.075e-01 | 2.386e-01 | 1.809e-01 |
| 0.3 | 1.529e-01 | 1.250e-01 | 1.626e-01 | 1.850e-01 | 1.392e-01 |
| 0.4 | 1.192e-01 | 9.558e-02 | 1.261e-01 | 1.452e-01 | 1.102e-01 |
| 0.5 | 9.607e-02 | 7.845e-02 | 9.983e-02 | 1.158e-01 | 9.024e-02 |
| 0.75 | 6.452e-02 | 5.106e-02 | 6.853e-02 | 7.848e-02 | 6.000e-02 |
| 1 | 4.625e-02 | 3.751e-02 | 5.002e-02 | 5.536e-02 | 4.210e-02 |
| 2 | 2.025e-02 | 2.046e-02 | 2.062e-02 | 2.357e-02 | 1.634e-02 |
| 3 | 1.229e-02 | 1.295e-02 | 1.373e-02 | 1.375e-02 | 8.738e-03 |
| 4 | 8.305e-03 | 8.491e-03 | 1.004e-02 | 9.487e-03 | 5.200e-03 |

  Fractile: 0.84
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 1.695e-01 | 1.642e-01 | 1.567e-01 | 2.123e-01 | 1.448e-01 |
| 0.05 | 2.768e-01 | 2.150e-01 | 2.574e-01 | 3.872e-01 | 2.478e-01 |
| 0.1 | 3.937e-01 | 3.321e-01 | 3.648e-01 | 5.153e-01 | 3.626e-01 |
| 0.2 | 3.815e-01 | 3.342e-01 | 3.848e-01 | 4.541e-01 | 3.529e-01 |
| 0.3 | 2.935e-01 | 2.517e-01 | 2.970e-01 | 3.504e-01 | 2.750e-01 |
| 0.4 | 2.308e-01 | 1.940e-01 | 2.328e-01 | 2.768e-01 | 2.195e-01 |
| 0.5 | 1.886e-01 | 1.606e-01 | 1.886e-01 | 2.243e-01 | 1.809e-01 |
| 0.75 | 1.301e-01 | 1.058e-01 | 1.343e-01 | 1.593e-01 | 1.211e-01 |
| 1 | 9.416e-02 | 7.872e-02 | 9.959e-02 | 1.133e-01 | 8.502e-02 |
| 2 | 4.145e-02 | 4.366e-02 | 4.137e-02 | 4.781e-02 | 3.294e-02 |
| 3 | 2.515e-02 | 2.740e-02 | 2.777e-02 | 2.793e-02 | 1.751e-02 |
| 4 | 1.680e-02 | 1.782e-02 | 2.030e-02 | 1.872e-02 | 1.038e-02 |

Source: Cat Mesa fault
Region: Mt Taylor Deterministic
  Closest Distance: 75.85 km
  Amplitude Units: Acceleration (g)
  Magnitude: 6.60 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 1.961e-02 | 1.853e-02 | 1.907e-02 | 2.448e-02 | 1.635e-02 |
| 0.05 | 2.815e-02 | 2.293e-02 | 2.623e-02 | 3.837e-02 | 2.507e-02 |
| 0.1 | 3.658e-02 | 3.182e-02 | 3.577e-02 | 4.577e-02 | 3.296e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 0.2 | 3.847e-02 | 3.403e-02 | 4.376e-02 | 4.427e-02 | 3.182e-02 |
| 0.3 | 3.288e-02 | 2.948e-02 | 3.638e-02 | 3.977e-02 | 2.589e-02 |
| 0.4 | 2.723e-02 | 2.592e-02 | 2.898e-02 | 3.264e-02 | 2.137e-02 |
| 0.5 | 2.283e-02 | 2.303e-02 | 2.328e-02 | 2.689e-02 | 1.812e-02 |
| 0.75 | 1.628e-02 | 1.623e-02 | 1.625e-02 | 1.977e-02 | 1.288e-02 |
| 1 | 1.182e-02 | 1.215e-02 | 1.198e-02 | 1.361e-02 | 9.556e-03 |
| 2 | 5.878e-03 | 7.110e-03 | 5.516e-03 | 6.485e-03 | 4.400e-03 |
| 3 | 3.794e-03 | 4.665e-03 | 3.920e-03 | 3.983e-03 | 2.610e-03 |
| 4 | 2.670e-03 | 3.114e-03 | 3.069e-03 | 2.851e-03 | 1.647e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 3.568e-02 | 3.521e-02 | 3.481e-02 | 4.393e-02 | 2.876e-02 |
| 0.05 | 5.343e-02 | 4.390e-02 | 5.167e-02 | 7.267e-02 | 4.549e-02 |
| 0.1 | 7.162e-02 | 6.193e-02 | 7.239e-02 | 9.092e-02 | 6.124e-02 |
| 0.2 | 7.326e-02 | 6.706e-02 | 8.118e-02 | 8.426e-02 | 6.053e-02 |
| 0.3 | 6.263e-02 | 5.882e-02 | 6.646e-02 | 7.534e-02 | 4.993e-02 |
| 0.4 | 5.238e-02 | 5.215e-02 | 5.352e-02 | 6.224e-02 | 4.159e-02 |
| 0.5 | 4.457e-02 | 4.672e-02 | 4.398e-02 | 5.210e-02 | 3.550e-02 |
| 0.75 | 3.270e-02 | 3.334e-02 | 3.185e-02 | 4.013e-02 | 2.550e-02 |
| 1 | 2.400e-02 | 2.527e-02 | 2.386e-02 | 2.785e-02 | 1.900e-02 |
| 2 | 1.202e-02 | 1.505e-02 | 1.107e-02 | 1.315e-02 | 8.804e-03 |
| 3 | 7.749e-03 | 9.788e-03 | 7.928e-03 | 8.091e-03 | 5.191e-03 |

```
       4      5.393e-03      6.479e-03      6.206e-03      5.625e-03
3.261e-03



Source: Cebollita Mesa fault
Region: Mt Taylor Deterministic
  Closest Distance: 74.77 km
  Amplitude Units: Acceleration (g)
  Magnitude: 6.30 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS
2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS
2014

       1          2              3              4              5
6
     PGA      1.497e-02      1.339e-02      1.554e-02      1.895e-02
1.199e-02
    0.05      2.143e-02      1.658e-02      2.159e-02      2.914e-02
1.841e-02
     0.1      2.843e-02      2.305e-02      3.018e-02      3.635e-02
2.413e-02
     0.2      3.052e-02      2.418e-02      3.781e-02      3.654e-02
2.354e-02
     0.3      2.596e-02      2.052e-02      3.127e-02      3.279e-02
1.927e-02
     0.4      2.114e-02      1.778e-02      2.469e-02      2.614e-02
1.595e-02
     0.5      1.749e-02      1.559e-02      1.965e-02      2.120e-02
1.352e-02
    0.75      1.225e-02      1.058e-02      1.356e-02      1.533e-02
9.515e-03
       1      8.732e-03      7.770e-03      9.897e-03      1.030e-02
6.958e-03
       2      4.002e-03      4.392e-03      4.236e-03      4.390e-03
2.991e-03
       3      2.456e-03      2.763e-03      2.849e-03      2.530e-03
1.681e-03
       4      1.673e-03      1.788e-03      2.129e-03      1.761e-03
1.015e-03

  Fractile: 0.84
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS
2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
```

Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.743e-02 | 2.569e-02 | 2.837e-02 | 3.400e-02 | 2.166e-02 |
| 0.05 | 4.101e-02 | 3.207e-02 | 4.252e-02 | 5.518e-02 | 3.429e-02 |
| 0.1 | 5.614e-02 | 4.530e-02 | 6.107e-02 | 7.220e-02 | 4.600e-02 |
| 0.2 | 5.843e-02 | 4.810e-02 | 7.013e-02 | 6.955e-02 | 4.592e-02 |
| 0.3 | 4.966e-02 | 4.131e-02 | 5.713e-02 | 6.211e-02 | 3.807e-02 |
| 0.4 | 4.083e-02 | 3.609e-02 | 4.559e-02 | 4.984e-02 | 3.178e-02 |
| 0.5 | 3.430e-02 | 3.190e-02 | 3.712e-02 | 4.109e-02 | 2.711e-02 |
| 0.75 | 2.470e-02 | 2.192e-02 | 2.658e-02 | 3.112e-02 | 1.920e-02 |
| 1 | 1.779e-02 | 1.631e-02 | 1.970e-02 | 2.109e-02 | 1.405e-02 |
| 2 | 8.201e-03 | 9.374e-03 | 8.499e-03 | 8.904e-03 | 6.029e-03 |
| 3 | 5.029e-03 | 5.847e-03 | 5.761e-03 | 5.140e-03 | 3.368e-03 |
| 4 | 3.389e-03 | 3.753e-03 | 4.304e-03 | 3.475e-03 | 2.025e-03 |

Source: Continental Divide fault
Region: Mt Taylor Deterministic
Closest Distance: 91.82 km
Amplitude Units: Acceleration (g)
Magnitude: 6.50 Mw
Fractile: 0.50
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 1.364e-02 | 1.250e-02 | 1.326e-02 | 1.732e-02 | 1.147e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 0.05 | 1.918e-02 | 1.527e-02 | 1.778e-02 | 2.653e-02 | 1.714e-02 |
| 0.1 | 2.462e-02 | 2.069e-02 | 2.439e-02 | 3.140e-02 | 2.201e-02 |
| 0.2 | 2.656e-02 | 2.232e-02 | 3.108e-02 | 3.132e-02 | 2.153e-02 |
| 0.3 | 2.334e-02 | 1.991e-02 | 2.650e-02 | 2.898e-02 | 1.799e-02 |
| 0.4 | 1.966e-02 | 1.804e-02 | 2.136e-02 | 2.410e-02 | 1.514e-02 |
| 0.5 | 1.664e-02 | 1.624e-02 | 1.725e-02 | 2.007e-02 | 1.302e-02 |
| 0.75 | 1.202e-02 | 1.144e-02 | 1.213e-02 | 1.505e-02 | 9.435e-03 |
| 1 | 8.736e-03 | 8.511e-03 | 8.970e-03 | 1.039e-02 | 7.071e-03 |
| 2 | 4.306e-03 | 4.976e-03 | 4.086e-03 | 4.867e-03 | 3.293e-03 |
| 3 | 2.744e-03 | 3.230e-03 | 2.852e-03 | 2.944e-03 | 1.951e-03 |
| 4 | 1.910e-03 | 2.141e-03 | 2.202e-03 | 2.080e-03 | 1.218e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.482e-02 | 2.383e-02 | 2.419e-02 | 3.108e-02 | 2.017e-02 |
| 0.05 | 3.642e-02 | 2.934e-02 | 3.502e-02 | 5.025e-02 | 3.109e-02 |
| 0.1 | 4.835e-02 | 4.040e-02 | 4.975e-02 | 6.237e-02 | 4.088e-02 |
| 0.2 | 5.060e-02 | 4.412e-02 | 5.771e-02 | 5.961e-02 | 4.096e-02 |
| 0.3 | 4.446e-02 | 3.984e-02 | 4.841e-02 | 5.489e-02 | 3.469e-02 |
| 0.4 | 3.781e-02 | 3.639e-02 | 3.945e-02 | 4.595e-02 | 2.946e-02 |
| 0.5 | 3.250e-02 | 3.305e-02 | 3.257e-02 | 3.888e-02 | 2.551e-02 |
| 0.75 | 2.414e-02 | 2.357e-02 | 2.378e-02 | 3.055e-02 | 1.868e-02 |
| 1 | 1.774e-02 | 1.776e-02 | 1.786e-02 | 2.127e-02 | 1.406e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 2 | 8.805e-03 | 1.056e-02 | 8.197e-03 | 9.872e-03 | 6.589e-03 |
| 3 | 5.606e-03 | 6.798e-03 | 5.767e-03 | 5.981e-03 | 3.879e-03 |
| 4 | 3.859e-03 | 4.468e-03 | 4.452e-03 | 4.104e-03 | 2.413e-03 |

Source: County Dump fault [2038]
Region: USGS 2014 New Mexico
  Closest Distance: 76.53 km
  Amplitude Units: Acceleration (g)
  Magnitude: 6.89 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.424e-02 | 2.444e-02 | 2.228e-02 | 2.884e-02 | 2.140e-02 |
| 0.05 | 3.458e-02 | 3.022e-02 | 3.024e-02 | 4.514e-02 | 3.273e-02 |
| 0.1 | 4.438e-02 | 4.190e-02 | 4.024e-02 | 5.221e-02 | 4.318e-02 |
| 0.2 | 4.613e-02 | 4.553e-02 | 4.832e-02 | 4.918e-02 | 4.149e-02 |
| 0.3 | 3.989e-02 | 4.011e-02 | 4.050e-02 | 4.519e-02 | 3.374e-02 |
| 0.4 | 3.338e-02 | 3.568e-02 | 3.262e-02 | 3.737e-02 | 2.786e-02 |
| 0.5 | 2.833e-02 | 3.205e-02 | 2.646e-02 | 3.115e-02 | 2.364e-02 |
| 0.75 | 2.053e-02 | 2.329e-02 | 1.870e-02 | 2.321e-02 | 1.692e-02 |
| 1 | 1.509e-02 | 1.770e-02 | 1.394e-02 | 1.609e-02 | 1.264e-02 |
| 2 | 7.947e-03 | 1.067e-02 | 6.894e-03 | 8.163e-03 | 6.065e-03 |
| 3 | 5.382e-03 | 7.403e-03 | 5.170e-03 | 5.205e-03 | 3.750e-03 |
| 4 | 3.928e-03 | 5.181e-03 | 4.236e-03 | 3.832e-03 | 2.463e-03 |

  Fractile: 0.84
  Column 1: Spectral Period

Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 4.402e-02 | 4.600e-02 | 4.067e-02 | 5.176e-02 | 3.764e-02 |
| 0.05 | 6.544e-02 | 5.734e-02 | 5.955e-02 | 8.549e-02 | 5.938e-02 |
| 0.1 | 8.655e-02 | 8.082e-02 | 8.144e-02 | 1.037e-01 | 8.023e-02 |
| 0.2 | 8.777e-02 | 8.892e-02 | 8.962e-02 | 9.360e-02 | 7.893e-02 |
| 0.3 | 7.599e-02 | 7.933e-02 | 7.398e-02 | 8.560e-02 | 6.506e-02 |
| 0.4 | 6.422e-02 | 7.116e-02 | 6.024e-02 | 7.126e-02 | 5.421e-02 |
| 0.5 | 5.528e-02 | 6.447e-02 | 4.998e-02 | 6.036e-02 | 4.632e-02 |
| 0.75 | 4.117e-02 | 4.746e-02 | 3.664e-02 | 4.712e-02 | 3.349e-02 |
| 1 | 3.059e-02 | 3.653e-02 | 2.775e-02 | 3.294e-02 | 2.514e-02 |
| 2 | 1.623e-02 | 2.239e-02 | 1.383e-02 | 1.656e-02 | 1.213e-02 |
| 3 | 1.097e-02 | 1.541e-02 | 1.045e-02 | 1.057e-02 | 7.458e-03 |
| 4 | 7.924e-03 | 1.069e-02 | 8.564e-03 | 7.561e-03 | 4.877e-03 |

Source: Coyote Springs fault
Region: Mt Taylor Deterministic
Closest Distance: 93.44 km
Amplitude Units: Acceleration (g)
Magnitude: 6.50 Mw
Fractile: 0.50
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 1.329e-02 | 1.218e-02 | 1.292e-02 | 1.682e-02 | 1.123e-02 |
| 0.05 | 1.865e-02 | 1.485e-02 | 1.729e-02 | 2.571e-02 | 1.675e-02 |
| 0.1 | 2.390e-02 | 2.008e-02 | 2.371e-02 | 3.036e-02 | 2.146e-02 |
| 0.2 | 2.584e-02 | 2.169e-02 | 3.030e-02 | 3.036e-02 | 2.101e-02 |
| 0.3 | 2.278e-02 | 1.941e-02 | 2.591e-02 | 2.821e-02 | 1.760e-02 |
| 0.4 | 1.923e-02 | 1.765e-02 | 2.091e-02 | 2.350e-02 | 1.484e-02 |
| 0.5 | 1.630e-02 | 1.592e-02 | 1.690e-02 | 1.961e-02 | 1.278e-02 |
| 0.75 | 1.179e-02 | 1.122e-02 | 1.190e-02 | 1.475e-02 | 9.276e-03 |
| 1 | 8.577e-03 | 8.351e-03 | 8.804e-03 | 1.019e-02 | 6.960e-03 |
| 2 | 4.232e-03 | 4.887e-03 | 4.016e-03 | 4.777e-03 | 3.249e-03 |
| 3 | 2.698e-03 | 3.174e-03 | 2.803e-03 | 2.889e-03 | 1.926e-03 |
| 4 | 1.878e-03 | 2.105e-03 | 2.164e-03 | 2.041e-03 | 1.203e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.418e-02 | 2.320e-02 | 2.359e-02 | 3.019e-02 | 1.976e-02 |
| 0.05 | 3.542e-02 | 2.853e-02 | 3.405e-02 | 4.869e-02 | 3.039e-02 |
| 0.1 | 4.694e-02 | 3.920e-02 | 4.840e-02 | 6.031e-02 | 3.987e-02 |
| 0.2 | 4.925e-02 | 4.286e-02 | 5.637e-02 | 5.779e-02 | 3.997e-02 |
| 0.3 | 4.338e-02 | 3.885e-02 | 4.733e-02 | 5.343e-02 | 3.393e-02 |
| 0.4 | 3.698e-02 | 3.560e-02 | 3.862e-02 | 4.482e-02 | 2.888e-02 |
| 0.5 | 3.183e-02 | 3.239e-02 | 3.191e-02 | 3.799e-02 | 2.503e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 0.75 | 2.369e-02 | 2.313e-02 | 2.332e-02 | 2.994e-02 | 1.836e-02 |
| 1 | 1.741e-02 | 1.743e-02 | 1.753e-02 | 2.087e-02 | 1.384e-02 |
| 2 | 8.655e-03 | 1.037e-02 | 8.056e-03 | 9.690e-03 | 6.501e-03 |
| 3 | 5.511e-03 | 6.678e-03 | 5.668e-03 | 5.869e-03 | 3.830e-03 |
| 4 | 3.794e-03 | 4.391e-03 | 4.376e-03 | 4.026e-03 | 2.382e-03 |

Source: Intrabasin faults on the Llano de Albuquerque
Region: Mt Taylor Deterministic
  Closest Distance: 66.71 km
  Amplitude Units: Acceleration (g)
  Magnitude: 7.50 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 4.438e-02 | 4.692e-02 | 4.020e-02 | 4.766e-02 | 4.274e-02 |
| 0.05 | 6.352e-02 | 5.847e-02 | 5.445e-02 | 7.537e-02 | 6.579e-02 |
| 0.1 | 8.064e-02 | 8.228e-02 | 6.913e-02 | 8.249e-02 | 8.867e-02 |
| 0.2 | 8.169e-02 | 9.076e-02 | 7.788e-02 | 7.334e-02 | 8.476e-02 |
| 0.3 | 7.066e-02 | 8.014e-02 | 6.502e-02 | 6.914e-02 | 6.833e-02 |
| 0.4 | 5.954e-02 | 7.095e-02 | 5.300e-02 | 5.806e-02 | 5.614e-02 |
| 0.5 | 5.117e-02 | 6.406e-02 | 4.365e-02 | 4.948e-02 | 4.751e-02 |
| 0.75 | 3.785e-02 | 4.850e-02 | 3.139e-02 | 3.763e-02 | 3.388e-02 |
| 1 | 2.839e-02 | 3.775e-02 | 2.387e-02 | 2.664e-02 | 2.528e-02 |
| 2 | 1.623e-02 | 2.364e-02 | 1.359e-02 | 1.542e-02 | 1.226e-02 |
| 3 | 1.179e-02 | 1.730e-02 | 1.140e-02 | 1.064e-02 | 7.841e-03 |

4 9.177e-03 1.270e-02 1.025e-02 8.331e-03
5.425e-03

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS
2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS
2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 8.052e-02 | 8.801e-02 | 7.338e-02 | 8.552e-02 | 7.517e-02 |
| 0.05 | 1.200e-01 | 1.106e-01 | 1.072e-01 | 1.428e-01 | 1.194e-01 |
| 0.1 | 1.567e-01 | 1.582e-01 | 1.399e-01 | 1.639e-01 | 1.647e-01 |
| 0.2 | 1.555e-01 | 1.767e-01 | 1.445e-01 | 1.396e-01 | 1.613e-01 |
| 0.3 | 1.349e-01 | 1.580e-01 | 1.188e-01 | 1.310e-01 | 1.317e-01 |
| 0.4 | 1.147e-01 | 1.411e-01 | 9.787e-02 | 1.107e-01 | 1.093e-01 |
| 0.5 | 9.997e-02 | 1.285e-01 | 8.244e-02 | 9.587e-02 | 9.309e-02 |
| 0.75 | 7.587e-02 | 9.852e-02 | 6.151e-02 | 7.639e-02 | 6.706e-02 |
| 1 | 5.750e-02 | 7.767e-02 | 4.753e-02 | 5.454e-02 | 5.027e-02 |
| 2 | 3.314e-02 | 4.950e-02 | 2.726e-02 | 3.128e-02 | 2.453e-02 |
| 3 | 2.404e-02 | 3.591e-02 | 2.305e-02 | 2.161e-02 | 1.559e-02 |
| 4 | 1.851e-02 | 2.614e-02 | 2.072e-02 | 1.644e-02 | 1.074e-02 |

Source: Jemez-San Ysidro fault [2029ab]
Region: USGS 2014 New Mexico
Closest Distance: 77.26 km
Amplitude Units: Acceleration (g)
Magnitude: 7.09 Mw
Fractile: 0.50
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS
2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014

Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.785e-02 | 2.851e-02 | 2.515e-02 | 3.223e-02 | 2.551e-02 |
| 0.05 | 3.959e-02 | 3.522e-02 | 3.386e-02 | 5.037e-02 | 3.889e-02 |
| 0.1 | 5.038e-02 | 4.878e-02 | 4.431e-02 | 5.702e-02 | 5.142e-02 |
| 0.2 | 5.201e-02 | 5.353e-02 | 5.244e-02 | 5.274e-02 | 4.933e-02 |
| 0.3 | 4.530e-02 | 4.766e-02 | 4.416e-02 | 4.925e-02 | 4.014e-02 |
| 0.4 | 3.816e-02 | 4.272e-02 | 3.581e-02 | 4.093e-02 | 3.317e-02 |
| 0.5 | 3.261e-02 | 3.864e-02 | 2.924e-02 | 3.440e-02 | 2.818e-02 |
| 0.75 | 2.389e-02 | 2.861e-02 | 2.082e-02 | 2.587e-02 | 2.024e-02 |
| 1 | 1.769e-02 | 2.194e-02 | 1.564e-02 | 1.802e-02 | 1.518e-02 |
| 2 | 9.630e-03 | 1.345e-02 | 8.123e-03 | 9.540e-03 | 7.406e-03 |
| 3 | 6.692e-03 | 9.531e-03 | 6.321e-03 | 6.242e-03 | 4.675e-03 |
| 4 | 5.001e-03 | 6.836e-03 | 5.343e-03 | 4.685e-03 | 3.141e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 5.052e-02 | 5.346e-02 | 4.591e-02 | 5.784e-02 | 4.486e-02 |
| 0.05 | 7.481e-02 | 6.661e-02 | 6.668e-02 | 9.540e-02 | 7.057e-02 |
| 0.1 | 9.807e-02 | 9.379e-02 | 8.967e-02 | 1.133e-01 | 9.554e-02 |
| 0.2 | 9.893e-02 | 1.042e-01 | 9.727e-02 | 1.004e-01 | 9.385e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 0.3 | 8.633e-02 | 9.397e-02 | 8.067e-02 | 9.328e-02 | 7.739e-02 |
| 0.4 | 7.342e-02 | 8.494e-02 | 6.614e-02 | 7.806e-02 | 6.455e-02 |
| 0.5 | 6.364e-02 | 7.748e-02 | 5.523e-02 | 6.665e-02 | 5.521e-02 |
| 0.75 | 4.787e-02 | 5.811e-02 | 4.080e-02 | 5.252e-02 | 4.006e-02 |
| 1 | 3.583e-02 | 4.514e-02 | 3.114e-02 | 3.688e-02 | 3.018e-02 |
| 2 | 1.966e-02 | 2.816e-02 | 1.630e-02 | 1.935e-02 | 1.482e-02 |
| 3 | 1.364e-02 | 1.978e-02 | 1.278e-02 | 1.268e-02 | 9.298e-03 |
| 4 | 1.008e-02 | 1.407e-02 | 1.080e-02 | 9.244e-03 | 6.220e-03 |

Source: Calabacillas fault [2035]
Region: USGS 2014 New Mexico
  Closest Distance: 70.54 km
  Amplitude Units: Acceleration (g)
  Magnitude: 6.83 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.553e-02 | 2.583e-02 | 2.376e-02 | 3.035e-02 | 2.218e-02 |
| 0.05 | 3.669e-02 | 3.210e-02 | 3.263e-02 | 4.779e-02 | 3.423e-02 |
| 0.1 | 4.747e-02 | 4.490e-02 | 4.368e-02 | 5.583e-02 | 4.548e-02 |
| 0.2 | 4.924e-02 | 4.839e-02 | 5.216e-02 | 5.277e-02 | 4.363e-02 |
| 0.3 | 4.206e-02 | 4.194e-02 | 4.330e-02 | 4.778e-02 | 3.523e-02 |
| 0.4 | 3.495e-02 | 3.677e-02 | 3.465e-02 | 3.943e-02 | 2.893e-02 |
| 0.5 | 2.949e-02 | 3.275e-02 | 2.800e-02 | 3.276e-02 | 2.444e-02 |
| 0.75 | 2.120e-02 | 2.356e-02 | 1.967e-02 | 2.422e-02 | 1.735e-02 |

| | | | | |
|---|---|---|---|---|
| 1 | 1.555e-02 | 1.785e-02 | 1.461e-02 | 1.683e-02 1.289e-02 |
| 2 | 8.067e-03 | 1.066e-02 | 7.091e-03 | 8.439e-03 6.078e-03 |
| 3 | 5.415e-03 | 7.344e-03 | 5.258e-03 | 5.346e-03 3.712e-03 |
| 4 | 3.904e-03 | 5.017e-03 | 4.265e-03 | 3.919e-03 2.416e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 4.639e-02 | 4.872e-02 | 4.337e-02 | 5.447e-02 | 3.901e-02 |
| 0.05 | 6.947e-02 | 6.101e-02 | 6.426e-02 | 9.052e-02 | 6.210e-02 |
| 0.1 | 9.264e-02 | 8.677e-02 | 8.840e-02 | 1.109e-01 | 8.450e-02 |
| 0.2 | 9.372e-02 | 9.468e-02 | 9.676e-02 | 1.004e-01 | 8.299e-02 |
| 0.3 | 8.016e-02 | 8.311e-02 | 7.910e-02 | 9.050e-02 | 6.793e-02 |
| 0.4 | 6.724e-02 | 7.348e-02 | 6.400e-02 | 7.520e-02 | 5.629e-02 |
| 0.5 | 5.756e-02 | 6.599e-02 | 5.288e-02 | 6.348e-02 | 4.788e-02 |
| 0.75 | 4.254e-02 | 4.809e-02 | 3.854e-02 | 4.918e-02 | 3.434e-02 |
| 1 | 3.152e-02 | 3.691e-02 | 2.909e-02 | 3.445e-02 | 2.563e-02 |
| 2 | 1.648e-02 | 2.242e-02 | 1.422e-02 | 1.712e-02 | 1.216e-02 |
| 3 | 1.105e-02 | 1.531e-02 | 1.063e-02 | 1.086e-02 | 7.382e-03 |
| 4 | 7.877e-03 | 1.037e-02 | 8.623e-03 | 7.732e-03 | 4.784e-03 |

Source: Mesa Prieta faults
Region: Mt Taylor Deterministic
Closest Distance: 47.05 km
Amplitude Units: Acceleration (g)
Magnitude: 6.30 Mw

Fractile: 0.50
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.745e-02 | 2.490e-02 | 2.973e-02 | 3.312e-02 | 2.206e-02 |
| 0.05 | 4.072e-02 | 3.152e-02 | 4.329e-02 | 5.266e-02 | 3.541e-02 |
| 0.1 | 5.525e-02 | 4.568e-02 | 6.048e-02 | 6.651e-02 | 4.834e-02 |
| 0.2 | 5.759e-02 | 4.674e-02 | 7.189e-02 | 6.556e-02 | 4.617e-02 |
| 0.3 | 4.661e-02 | 3.731e-02 | 5.712e-02 | 5.575e-02 | 3.627e-02 |
| 0.4 | 3.700e-02 | 3.050e-02 | 4.420e-02 | 4.420e-02 | 2.908e-02 |
| 0.5 | 3.010e-02 | 2.594e-02 | 3.485e-02 | 3.556e-02 | 2.407e-02 |
| 0.75 | 2.058e-02 | 1.726e-02 | 2.372e-02 | 2.506e-02 | 1.631e-02 |
| 1 | 1.463e-02 | 1.268e-02 | 1.719e-02 | 1.702e-02 | 1.164e-02 |
| 2 | 6.567e-03 | 7.050e-03 | 7.208e-03 | 7.287e-03 | 4.723e-03 |
| 3 | 4.014e-03 | 4.425e-03 | 4.842e-03 | 4.218e-03 | 2.569e-03 |
| 4 | 2.737e-03 | 2.861e-03 | 3.603e-03 | 2.951e-03 | 1.534e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 5.033e-02 | 4.777e-02 | 5.426e-02 | 5.944e-02 | 3.985e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 0.05 | 7.798e-02 | 6.096e-02 | 8.527e-02 | 9.974e-02 | 6.597e-02 |
| 0.1 | 1.091e-01 | 8.976e-02 | 1.224e-01 | 1.321e-01 | 9.217e-02 |
| 0.2 | 1.103e-01 | 9.296e-02 | 1.334e-01 | 1.248e-01 | 9.008e-02 |
| 0.3 | 8.918e-02 | 7.512e-02 | 1.043e-01 | 1.056e-01 | 7.166e-02 |
| 0.4 | 7.145e-02 | 6.192e-02 | 8.162e-02 | 8.429e-02 | 5.796e-02 |
| 0.5 | 5.902e-02 | 5.308e-02 | 6.582e-02 | 6.891e-02 | 4.827e-02 |
| 0.75 | 4.151e-02 | 3.577e-02 | 4.647e-02 | 5.086e-02 | 3.291e-02 |
| 1 | 2.979e-02 | 2.661e-02 | 3.422e-02 | 3.483e-02 | 2.350e-02 |
| 2 | 1.345e-02 | 1.505e-02 | 1.446e-02 | 1.478e-02 | 9.522e-03 |
| 3 | 8.219e-03 | 9.365e-03 | 9.792e-03 | 8.569e-03 | 5.148e-03 |
| 4 | 5.543e-03 | 6.004e-03 | 7.284e-03 | 5.822e-03 | 3.062e-03 |

Source: Nacimiento fault [2002ab]
Region: USGS 2014 New Mexico
  Closest Distance: 72.30 km
  Amplitude Units: Acceleration (g)
  Magnitude: 7.30 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 3.497e-02 | 3.665e-02 | 3.134e-02 | 3.899e-02 | 3.290e-02 |
| 0.05 | 4.982e-02 | 4.546e-02 | 4.222e-02 | 6.121e-02 | 5.038e-02 |
| 0.1 | 6.327e-02 | 6.344e-02 | 5.437e-02 | 6.804e-02 | 6.721e-02 |
| 0.2 | 6.468e-02 | 6.987e-02 | 6.282e-02 | 6.167e-02 | 6.436e-02 |
| 0.3 | 5.622e-02 | 6.204e-02 | 5.274e-02 | 5.798e-02 | 5.212e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 0.4 | 4.741e-02 | 5.534e-02 | 4.290e-02 | 4.845e-02 | 4.295e-02 |
| 0.5 | 4.067e-02 | 5.005e-02 | 3.519e-02 | 4.101e-02 | 3.642e-02 |
| 0.75 | 2.996e-02 | 3.754e-02 | 2.519e-02 | 3.101e-02 | 2.609e-02 |
| 1 | 2.235e-02 | 2.903e-02 | 1.905e-02 | 2.178e-02 | 1.953e-02 |
| 2 | 1.251e-02 | 1.802e-02 | 1.037e-02 | 1.208e-02 | 9.549e-03 |
| 3 | 8.905e-03 | 1.300e-02 | 8.389e-03 | 8.134e-03 | 6.099e-03 |
| 4 | 6.796e-03 | 9.445e-03 | 7.322e-03 | 6.244e-03 | 4.174e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 6.344e-02 | 6.873e-02 | 5.720e-02 | 6.997e-02 | 5.786e-02 |
| 0.05 | 9.411e-02 | 8.597e-02 | 8.315e-02 | 1.159e-01 | 9.141e-02 |
| 0.1 | 1.230e-01 | 1.220e-01 | 1.100e-01 | 1.352e-01 | 1.249e-01 |
| 0.2 | 1.231e-01 | 1.360e-01 | 1.165e-01 | 1.174e-01 | 1.224e-01 |
| 0.3 | 1.072e-01 | 1.223e-01 | 9.634e-02 | 1.098e-01 | 1.005e-01 |
| 0.4 | 9.130e-02 | 1.100e-01 | 7.923e-02 | 9.238e-02 | 8.358e-02 |
| 0.5 | 7.941e-02 | 1.004e-01 | 6.647e-02 | 7.946e-02 | 7.136e-02 |
| 0.75 | 6.006e-02 | 7.626e-02 | 4.937e-02 | 6.296e-02 | 5.165e-02 |
| 1 | 4.527e-02 | 5.972e-02 | 3.792e-02 | 4.458e-02 | 3.884e-02 |
| 2 | 2.554e-02 | 3.772e-02 | 2.081e-02 | 2.451e-02 | 1.910e-02 |
| 3 | 1.815e-02 | 2.698e-02 | 1.696e-02 | 1.652e-02 | 1.213e-02 |
| 4 | 1.371e-02 | 1.944e-02 | 1.480e-02 | 1.232e-02 | 8.266e-03 |

Source: San Felipe fault zone [2030a]
Region: USGS 2014 New Mexico
  Closest Distance: 93.24 km
  Amplitude Units: Acceleration (g)
  Magnitude: 6.97 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 1.984e-02 | 2.006e-02 | 1.803e-02 | 2.293e-02 | 1.835e-02 |
| 0.05 | 2.763e-02 | 2.447e-02 | 2.373e-02 | 3.497e-02 | 2.736e-02 |
| 0.1 | 3.473e-02 | 3.309e-02 | 3.126e-02 | 3.921e-02 | 3.537e-02 |
| 0.2 | 3.667e-02 | 3.664e-02 | 3.841e-02 | 3.744e-02 | 3.418e-02 |
| 0.3 | 3.277e-02 | 3.361e-02 | 3.307e-02 | 3.604e-02 | 2.837e-02 |
| 0.4 | 2.807e-02 | 3.105e-02 | 2.707e-02 | 3.036e-02 | 2.380e-02 |
| 0.5 | 2.423e-02 | 2.848e-02 | 2.218e-02 | 2.580e-02 | 2.045e-02 |
| 0.75 | 1.794e-02 | 2.110e-02 | 1.588e-02 | 1.981e-02 | 1.495e-02 |
| 1 | 1.330e-02 | 1.609e-02 | 1.194e-02 | 1.383e-02 | 1.134e-02 |
| 2 | 7.194e-03 | 9.864e-03 | 6.098e-03 | 7.162e-03 | 5.651e-03 |
| 3 | 4.936e-03 | 6.925e-03 | 4.643e-03 | 4.600e-03 | 3.578e-03 |
| 4 | 3.644e-03 | 4.938e-03 | 3.859e-03 | 3.398e-03 | 2.382e-03 |

  Fractile: 0.84
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 3.600e-02 | 3.766e-02 | 3.291e-02 | 4.114e-02 | 3.228e-02 |
| 0.05 | 5.223e-02 | 4.632e-02 | 4.674e-02 | 6.624e-02 | 4.964e-02 |
| 0.1 | 6.777e-02 | 6.367e-02 | 6.381e-02 | 7.789e-02 | 6.571e-02 |
| 0.2 | 6.978e-02 | 7.139e-02 | 7.143e-02 | 7.127e-02 | 6.502e-02 |
| 0.3 | 6.243e-02 | 6.633e-02 | 6.041e-02 | 6.827e-02 | 5.471e-02 |
| 0.4 | 5.400e-02 | 6.178e-02 | 4.999e-02 | 5.790e-02 | 4.632e-02 |
| 0.5 | 4.728e-02 | 5.715e-02 | 4.189e-02 | 4.999e-02 | 4.008e-02 |
| 0.75 | 3.596e-02 | 4.289e-02 | 3.112e-02 | 4.022e-02 | 2.960e-02 |
| 1 | 2.694e-02 | 3.314e-02 | 2.377e-02 | 2.830e-02 | 2.255e-02 |
| 2 | 1.468e-02 | 2.067e-02 | 1.223e-02 | 1.453e-02 | 1.131e-02 |
| 3 | 1.006e-02 | 1.439e-02 | 9.388e-03 | 9.344e-03 | 7.115e-03 |
| 4 | 7.348e-03 | 1.017e-02 | 7.802e-03 | 6.704e-03 | 4.717e-03 |

Source: San Felipe fault zone (Algodones section)
Region: Mt Taylor Deterministic
  Closest Distance: 93.31 km
  Amplitude Units: Acceleration (g)
  Magnitude: 7.00 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.045e-02 | 2.058e-02 | 1.874e-02 | 2.338e-02 | 1.908e-02 |
| 0.05 | 2.848e-02 | 2.510e-02 | 2.469e-02 | 3.567e-02 | 2.845e-02 |
| 0.1 | 3.577e-02 | 3.394e-02 | 3.244e-02 | 3.987e-02 | 3.682e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 0.2 | 3.770e-02 | 3.763e-02 | 3.967e-02 | 3.796e-02 | 3.553e-02 |
| 0.3 | 3.370e-02 | 3.458e-02 | 3.411e-02 | 3.664e-02 | 2.948e-02 |
| 0.4 | 2.887e-02 | 3.197e-02 | 2.792e-02 | 3.088e-02 | 2.471e-02 |
| 0.5 | 2.493e-02 | 2.935e-02 | 2.288e-02 | 2.624e-02 | 2.123e-02 |
| 0.75 | 1.847e-02 | 2.181e-02 | 1.639e-02 | 2.019e-02 | 1.550e-02 |
| 1 | 1.371e-02 | 1.666e-02 | 1.233e-02 | 1.409e-02 | 1.176e-02 |
| 2 | 7.444e-03 | 1.024e-02 | 6.338e-03 | 7.344e-03 | 5.858e-03 |
| 3 | 5.126e-03 | 7.209e-03 | 4.852e-03 | 4.734e-03 | 3.708e-03 |
| 4 | 3.796e-03 | 5.152e-03 | 4.051e-03 | 3.507e-03 | 2.474e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 3.708e-02 | 3.859e-02 | 3.420e-02 | 4.196e-02 | 3.356e-02 |
| 0.05 | 5.382e-02 | 4.747e-02 | 4.862e-02 | 6.757e-02 | 5.163e-02 |
| 0.1 | 6.975e-02 | 6.525e-02 | 6.617e-02 | 7.919e-02 | 6.840e-02 |
| 0.2 | 7.170e-02 | 7.327e-02 | 7.369e-02 | 7.224e-02 | 6.760e-02 |
| 0.3 | 6.418e-02 | 6.817e-02 | 6.232e-02 | 6.939e-02 | 5.683e-02 |
| 0.4 | 5.553e-02 | 6.357e-02 | 5.157e-02 | 5.888e-02 | 4.809e-02 |
| 0.5 | 4.863e-02 | 5.886e-02 | 4.322e-02 | 5.085e-02 | 4.159e-02 |
| 0.75 | 3.702e-02 | 4.430e-02 | 3.212e-02 | 4.099e-02 | 3.069e-02 |
| 1 | 2.776e-02 | 3.427e-02 | 2.455e-02 | 2.883e-02 | 2.338e-02 |
| 2 | 1.519e-02 | 2.143e-02 | 1.271e-02 | 1.490e-02 | 1.172e-02 |
| 3 | 1.044e-02 | 1.496e-02 | 9.812e-03 | 9.617e-03 | 7.375e-03 |

| | | | | | |
|---|---|---|---|---|---|
| 4 | 7.653e-03 | 1.060e-02 | 8.191e-03 | 6.919e-03 | 4.899e-03 |

Source: Sand Hill fault zone
Region: Mt Taylor Deterministic
  Closest Distance: 62.17 km
  Amplitude Units: Acceleration (g)
  Magnitude: 6.90 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 3.152e-02 | 3.191e-02 | 2.999e-02 | 3.638e-02 | 2.779e-02 |
| 0.05 | 4.574e-02 | 3.990e-02 | 4.176e-02 | 5.787e-02 | 4.343e-02 |
| 0.1 | 5.955e-02 | 5.653e-02 | 5.569e-02 | 6.751e-02 | 5.846e-02 |
| 0.2 | 6.119e-02 | 6.067e-02 | 6.510e-02 | 6.319e-02 | 5.579e-02 |
| 0.3 | 5.158e-02 | 5.181e-02 | 5.338e-02 | 5.657e-02 | 4.456e-02 |
| 0.4 | 4.257e-02 | 4.474e-02 | 4.253e-02 | 4.673e-02 | 3.628e-02 |
| 0.5 | 3.580e-02 | 3.957e-02 | 3.432e-02 | 3.883e-02 | 3.047e-02 |
| 0.75 | 2.564e-02 | 2.850e-02 | 2.407e-02 | 2.862e-02 | 2.139e-02 |
| 1 | 1.882e-02 | 2.166e-02 | 1.789e-02 | 1.995e-02 | 1.580e-02 |
| 2 | 9.811e-03 | 1.295e-02 | 8.769e-03 | 1.017e-02 | 7.348e-03 |
| 3 | 6.635e-03 | 8.986e-03 | 6.585e-03 | 6.505e-03 | 4.464e-03 |
| 4 | 4.856e-03 | 6.304e-03 | 5.390e-03 | 4.811e-03 | 2.917e-03 |

  Fractile: 0.84
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014

Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 5.723e-02 | 6.003e-02 | 5.473e-02 | 6.528e-02 | 4.888e-02 |
| 0.05 | 8.659e-02 | 7.569e-02 | 8.225e-02 | 1.096e-01 | 7.880e-02 |
| 0.1 | 1.161e-01 | 1.090e-01 | 1.127e-01 | 1.341e-01 | 1.086e-01 |
| 0.2 | 1.164e-01 | 1.185e-01 | 1.207e-01 | 1.203e-01 | 1.061e-01 |
| 0.3 | 9.826e-02 | 1.024e-01 | 9.752e-02 | 1.072e-01 | 8.592e-02 |
| 0.4 | 8.187e-02 | 8.920e-02 | 7.855e-02 | 8.910e-02 | 7.061e-02 |
| 0.5 | 6.983e-02 | 7.957e-02 | 6.483e-02 | 7.523e-02 | 5.969e-02 |
| 0.75 | 5.141e-02 | 5.804e-02 | 4.716e-02 | 5.810e-02 | 4.235e-02 |
| 1 | 3.814e-02 | 4.470e-02 | 3.561e-02 | 4.084e-02 | 3.141e-02 |
| 2 | 2.003e-02 | 2.719e-02 | 1.759e-02 | 2.063e-02 | 1.470e-02 |
| 3 | 1.353e-02 | 1.870e-02 | 1.332e-02 | 1.321e-02 | 8.879e-03 |
| 4 | 9.794e-03 | 1.301e-02 | 1.090e-02 | 9.492e-03 | 5.777e-03 |

Source: Santa Fe fault
Region: Mt Taylor Deterministic
Closest Distance: 67.79 km
Amplitude Units: Acceleration (g)
Magnitude: 6.80 Mw
Fractile: 0.50
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.652e-02 | 2.652e-02 | 2.526e-02 | 3.135e-02 | 2.295e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 0.05 | 3.829e-02 | 3.302e-02 | 3.497e-02 | 4.955e-02 | 3.560e-02 |
| 0.1 | 4.976e-02 | 4.639e-02 | 4.697e-02 | 5.817e-02 | 4.750e-02 |
| 0.2 | 5.152e-02 | 4.979e-02 | 5.580e-02 | 5.504e-02 | 4.546e-02 |
| 0.3 | 4.372e-02 | 4.284e-02 | 4.601e-02 | 4.946e-02 | 3.656e-02 |
| 0.4 | 3.616e-02 | 3.730e-02 | 3.667e-02 | 4.076e-02 | 2.991e-02 |
| 0.5 | 3.041e-02 | 3.309e-02 | 2.956e-02 | 3.379e-02 | 2.520e-02 |
| 0.75 | 2.177e-02 | 2.369e-02 | 2.069e-02 | 2.492e-02 | 1.779e-02 |
| 1 | 1.592e-02 | 1.792e-02 | 1.534e-02 | 1.727e-02 | 1.317e-02 |
| 2 | 8.188e-03 | 1.065e-02 | 7.367e-03 | 8.603e-03 | 6.128e-03 |
| 3 | 5.455e-03 | 7.266e-03 | 5.432e-03 | 5.423e-03 | 3.700e-03 |
| 4 | 3.918e-03 | 4.934e-03 | 4.383e-03 | 3.965e-03 | 2.392e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 4.819e-02 | 5.006e-02 | 4.610e-02 | 5.625e-02 | 4.036e-02 |
| 0.05 | 7.254e-02 | 6.284e-02 | 6.887e-02 | 9.385e-02 | 6.460e-02 |
| 0.1 | 9.714e-02 | 8.973e-02 | 9.504e-02 | 1.155e-01 | 8.825e-02 |
| 0.2 | 9.807e-02 | 9.752e-02 | 1.035e-01 | 1.048e-01 | 8.649e-02 |
| 0.3 | 8.330e-02 | 8.495e-02 | 8.406e-02 | 9.369e-02 | 7.050e-02 |
| 0.4 | 6.957e-02 | 7.460e-02 | 6.773e-02 | 7.773e-02 | 5.821e-02 |
| 0.5 | 5.935e-02 | 6.673e-02 | 5.582e-02 | 6.546e-02 | 4.938e-02 |
| 0.75 | 4.368e-02 | 4.838e-02 | 4.055e-02 | 5.058e-02 | 3.521e-02 |
| 1 | 3.229e-02 | 3.707e-02 | 3.054e-02 | 3.536e-02 | 2.618e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 2 | 1.673e-02 | 2.242e-02 | 1.478e-02 | 1.745e-02 | 1.226e-02 |
| 3 | 1.113e-02 | 1.516e-02 | 1.098e-02 | 1.102e-02 | 7.359e-03 |
| 4 | 7.907e-03 | 1.021e-02 | 8.861e-03 | 7.822e-03 | 4.737e-03 |

Source: unnamed fault of Bonita Canyon
Region: Mt Taylor Deterministic
  Closest Distance: 49.34 km
  Amplitude Units: Acceleration (g)
  Magnitude: 6.10 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.117e-02 | 1.905e-02 | 2.354e-02 | 2.570e-02 | 1.640e-02 |
| 0.05 | 3.109e-02 | 2.407e-02 | 3.425e-02 | 3.985e-02 | 2.617e-02 |
| 0.1 | 4.269e-02 | 3.477e-02 | 4.861e-02 | 5.186e-02 | 3.551e-02 |
| 0.2 | 4.528e-02 | 3.516e-02 | 5.899e-02 | 5.268e-02 | 3.430e-02 |
| 0.3 | 3.635e-02 | 2.782e-02 | 4.496e-02 | 4.544e-02 | 2.717e-02 |
| 0.4 | 2.806e-02 | 2.264e-02 | 3.264e-02 | 3.509e-02 | 2.188e-02 |
| 0.5 | 2.270e-02 | 1.912e-02 | 2.554e-02 | 2.800e-02 | 1.813e-02 |
| 0.75 | 1.527e-02 | 1.240e-02 | 1.697e-02 | 1.953e-02 | 1.219e-02 |
| 1 | 1.065e-02 | 8.986e-03 | 1.204e-02 | 1.300e-02 | 8.590e-03 |
| 2 | 4.502e-03 | 4.875e-03 | 4.755e-03 | 5.075e-03 | 3.305e-03 |
| 3 | 2.643e-03 | 2.966e-03 | 3.070e-03 | 2.789e-03 | 1.747e-03 |
| 4 | 1.759e-03 | 1.873e-03 | 2.232e-03 | 1.913e-03 | 1.019e-03 |

  Fractile: 0.84
  Column 1: Spectral Period

Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 3.908e-02 | 3.679e-02 | 4.296e-02 | 4.613e-02 | 3.042e-02 |
| 0.05 | 5.996e-02 | 4.686e-02 | 6.746e-02 | 7.548e-02 | 5.005e-02 |
| 0.1 | 8.490e-02 | 6.875e-02 | 9.838e-02 | 1.030e-01 | 6.948e-02 |
| 0.2 | 8.717e-02 | 7.036e-02 | 1.094e-01 | 1.003e-01 | 6.863e-02 |
| 0.3 | 6.989e-02 | 5.636e-02 | 8.214e-02 | 8.606e-02 | 5.500e-02 |
| 0.4 | 5.453e-02 | 4.625e-02 | 6.027e-02 | 6.692e-02 | 4.466e-02 |
| 0.5 | 4.477e-02 | 3.938e-02 | 4.824e-02 | 5.425e-02 | 3.721e-02 |
| 0.75 | 3.096e-02 | 2.585e-02 | 3.326e-02 | 3.965e-02 | 2.509e-02 |
| 1 | 2.179e-02 | 1.897e-02 | 2.397e-02 | 2.660e-02 | 1.762e-02 |
| 2 | 9.253e-03 | 1.047e-02 | 9.539e-03 | 1.029e-02 | 6.716e-03 |
| 3 | 5.429e-03 | 6.313e-03 | 6.209e-03 | 5.665e-03 | 3.528e-03 |
| 4 | 3.573e-03 | 3.955e-03 | 4.513e-03 | 3.774e-03 | 2.050e-03 |

Source: unnamed faults near Albuquerque Volcanoes
Region: Mt Taylor Deterministic
Closest Distance: 73.60 km
Amplitude Units: Acceleration (g)
Magnitude: 6.90 Mw
Fractile: 0.50
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.586e-02 | 2.591e-02 | 2.422e-02 | 3.036e-02 | 2.293e-02 |
| 0.05 | 3.703e-02 | 3.211e-02 | 3.309e-02 | 4.768e-02 | 3.525e-02 |
| 0.1 | 4.767e-02 | 4.472e-02 | 4.404e-02 | 5.520e-02 | 4.672e-02 |
| 0.2 | 4.940e-02 | 4.849e-02 | 5.244e-02 | 5.189e-02 | 4.478e-02 |
| 0.3 | 4.247e-02 | 4.247e-02 | 4.368e-02 | 4.748e-02 | 3.626e-02 |
| 0.4 | 3.543e-02 | 3.756e-02 | 3.508e-02 | 3.924e-02 | 2.983e-02 |
| 0.5 | 3.000e-02 | 3.364e-02 | 2.842e-02 | 3.268e-02 | 2.525e-02 |
| 0.75 | 2.169e-02 | 2.442e-02 | 2.003e-02 | 2.432e-02 | 1.797e-02 |
| 1 | 1.593e-02 | 1.857e-02 | 1.493e-02 | 1.684e-02 | 1.339e-02 |
| 2 | 8.372e-03 | 1.118e-02 | 7.375e-03 | 8.567e-03 | 6.369e-03 |
| 3 | 5.672e-03 | 7.764e-03 | 5.540e-03 | 5.471e-03 | 3.915e-03 |
| 4 | 4.150e-03 | 5.453e-03 | 4.544e-03 | 4.034e-03 | 2.567e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 4.694e-02 | 4.876e-02 | 4.420e-02 | 5.449e-02 | 4.033e-02 |
| 0.05 | 7.009e-02 | 6.092e-02 | 6.517e-02 | 9.031e-02 | 6.395e-02 |
| 0.1 | 9.296e-02 | 8.624e-02 | 8.913e-02 | 1.097e-01 | 8.681e-02 |
| 0.2 | 9.398e-02 | 9.469e-02 | 9.728e-02 | 9.876e-02 | 8.519e-02 |
| 0.3 | 8.090e-02 | 8.397e-02 | 7.980e-02 | 8.993e-02 | 6.991e-02 |
| 0.4 | 6.814e-02 | 7.489e-02 | 6.478e-02 | 7.484e-02 | 5.805e-02 |
| 0.5 | 5.853e-02 | 6.764e-02 | 5.368e-02 | 6.332e-02 | 4.946e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 0.75 | 4.349e-02 | 4.974e-02 | 3.926e-02 | 4.937e-02 | 3.557e-02 |
| 1 | 3.228e-02 | 3.831e-02 | 2.971e-02 | 3.448e-02 | 2.663e-02 |
| 2 | 1.709e-02 | 2.346e-02 | 1.480e-02 | 1.738e-02 | 1.274e-02 |
| 3 | 1.157e-02 | 1.616e-02 | 1.120e-02 | 1.111e-02 | 7.785e-03 |
| 4 | 8.370e-03 | 1.125e-02 | 9.187e-03 | 7.960e-03 | 5.084e-03 |

Source: unnamed faults near Picuda Peak
Region: Mt Taylor Deterministic
  Closest Distance: 78.81 km
  Amplitude Units: Acceleration (g)
  Magnitude: 6.40 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 1.557e-02 | 1.393e-02 | 1.584e-02 | 1.980e-02 | 1.269e-02 |
| 0.05 | 2.226e-02 | 1.720e-02 | 2.183e-02 | 3.065e-02 | 1.938e-02 |
| 0.1 | 2.922e-02 | 2.376e-02 | 3.026e-02 | 3.753e-02 | 2.531e-02 |
| 0.2 | 3.121e-02 | 2.518e-02 | 3.780e-02 | 3.724e-02 | 2.462e-02 |
| 0.3 | 2.671e-02 | 2.169e-02 | 3.145e-02 | 3.350e-02 | 2.021e-02 |
| 0.4 | 2.196e-02 | 1.904e-02 | 2.496e-02 | 2.707e-02 | 1.677e-02 |
| 0.5 | 1.829e-02 | 1.684e-02 | 1.995e-02 | 2.210e-02 | 1.425e-02 |
| 0.75 | 1.292e-02 | 1.161e-02 | 1.385e-02 | 1.612e-02 | 1.011e-02 |
| 1 | 9.281e-03 | 8.582e-03 | 1.015e-02 | 1.094e-02 | 7.454e-03 |
| 2 | 4.389e-03 | 4.921e-03 | 4.459e-03 | 4.873e-03 | 3.303e-03 |
| 3 | 2.742e-03 | 3.143e-03 | 3.055e-03 | 2.879e-03 | 1.892e-03 |

| | | | | |
|---|---|---|---|---|
| 4 | 1.889e-03 | 2.058e-03 | 2.319e-03 | 2.021e-03 1.158e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.843e-02 | 2.664e-02 | 2.891e-02 | 3.553e-02 | 2.262e-02 |
| 0.05 | 4.245e-02 | 3.314e-02 | 4.300e-02 | 5.804e-02 | 3.563e-02 |
| 0.1 | 5.749e-02 | 4.654e-02 | 6.124e-02 | 7.455e-02 | 4.764e-02 |
| 0.2 | 5.959e-02 | 4.992e-02 | 7.012e-02 | 7.088e-02 | 4.744e-02 |
| 0.3 | 5.097e-02 | 4.354e-02 | 5.745e-02 | 6.345e-02 | 3.945e-02 |
| 0.4 | 4.232e-02 | 3.853e-02 | 4.609e-02 | 5.162e-02 | 3.302e-02 |
| 0.5 | 3.578e-02 | 3.436e-02 | 3.769e-02 | 4.283e-02 | 2.825e-02 |
| 0.75 | 2.601e-02 | 2.398e-02 | 2.713e-02 | 3.273e-02 | 2.021e-02 |
| 1 | 1.887e-02 | 1.796e-02 | 2.020e-02 | 2.239e-02 | 1.494e-02 |
| 2 | 8.984e-03 | 1.047e-02 | 8.946e-03 | 9.884e-03 | 6.633e-03 |
| 3 | 5.609e-03 | 6.633e-03 | 6.178e-03 | 5.849e-03 | 3.776e-03 |
| 4 | 3.821e-03 | 4.306e-03 | 4.689e-03 | 3.988e-03 | 2.302e-03 |

Source: unnamed faults near Star Heights
Region: Mt Taylor Deterministic
Closest Distance: 78.56 km
Amplitude Units: Acceleration (g)
Magnitude: 6.50 Mw
Fractile: 0.50
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014

Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 1.726e-02 | 1.572e-02 | 1.701e-02 | 2.213e-02 | 1.416e-02 |
| 0.05 | 2.475e-02 | 1.941e-02 | 2.338e-02 | 3.460e-02 | 2.163e-02 |
| 0.1 | 3.223e-02 | 2.683e-02 | 3.213e-02 | 4.166e-02 | 2.830e-02 |
| 0.2 | 3.413e-02 | 2.860e-02 | 3.981e-02 | 4.071e-02 | 2.743e-02 |
| 0.3 | 2.921e-02 | 2.477e-02 | 3.316e-02 | 3.646e-02 | 2.244e-02 |
| 0.4 | 2.417e-02 | 2.182e-02 | 2.640e-02 | 2.986e-02 | 1.859e-02 |
| 0.5 | 2.021e-02 | 1.937e-02 | 2.116e-02 | 2.452e-02 | 1.580e-02 |
| 0.75 | 1.437e-02 | 1.352e-02 | 1.474e-02 | 1.798e-02 | 1.124e-02 |
| 1 | 1.039e-02 | 1.006e-02 | 1.084e-02 | 1.234e-02 | 8.323e-03 |
| 2 | 5.060e-03 | 5.833e-03 | 4.880e-03 | 5.752e-03 | 3.775e-03 |
| 3 | 3.218e-03 | 3.778e-03 | 3.405e-03 | 3.486e-03 | 2.204e-03 |
| 4 | 2.241e-03 | 2.498e-03 | 2.626e-03 | 2.469e-03 | 1.371e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 3.141e-02 | 2.996e-02 | 3.105e-02 | 3.970e-02 | 2.491e-02 |
| 0.05 | 4.702e-02 | 3.728e-02 | 4.604e-02 | 6.553e-02 | 3.925e-02 |
| 0.1 | 6.318e-02 | 5.238e-02 | 6.502e-02 | 8.274e-02 | 5.257e-02 |
| 0.2 | 6.500e-02 | 5.652e-02 | 7.384e-02 | 7.748e-02 | 5.218e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 0.3 | 5.562e-02 | 4.957e-02 | 6.058e-02 | 6.906e-02 | 4.328e-02 |
| 0.4 | 4.647e-02 | 4.403e-02 | 4.875e-02 | 5.694e-02 | 3.618e-02 |
| 0.5 | 3.946e-02 | 3.941e-02 | 3.998e-02 | 4.751e-02 | 3.095e-02 |
| 0.75 | 2.887e-02 | 2.785e-02 | 2.888e-02 | 3.650e-02 | 2.224e-02 |
| 1 | 2.109e-02 | 2.098e-02 | 2.158e-02 | 2.526e-02 | 1.655e-02 |
| 2 | 1.035e-02 | 1.238e-02 | 9.789e-03 | 1.167e-02 | 7.553e-03 |
| 3 | 6.575e-03 | 7.949e-03 | 6.886e-03 | 7.081e-03 | 4.383e-03 |
| 4 | 4.527e-03 | 5.213e-03 | 5.309e-03 | 4.872e-03 | 2.714e-03 |

Source: unnamed faults of El Malpais lava field
Region: Mt Taylor Deterministic
  Closest Distance: 60.45 km
  Amplitude Units: Acceleration (g)
  Magnitude: 6.70 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.774e-02 | 2.784e-02 | 2.643e-02 | 3.334e-02 | 2.335e-02 |
| 0.05 | 4.041e-02 | 3.487e-02 | 3.705e-02 | 5.310e-02 | 3.661e-02 |
| 0.1 | 5.305e-02 | 4.953e-02 | 5.019e-02 | 6.325e-02 | 4.921e-02 |
| 0.2 | 5.484e-02 | 5.254e-02 | 5.952e-02 | 6.022e-02 | 4.709e-02 |
| 0.3 | 4.586e-02 | 4.424e-02 | 4.862e-02 | 5.298e-02 | 3.760e-02 |
| 0.4 | 3.760e-02 | 3.780e-02 | 3.848e-02 | 4.353e-02 | 3.059e-02 |
| 0.5 | 3.139e-02 | 3.314e-02 | 3.086e-02 | 3.591e-02 | 2.565e-02 |
| 0.75 | 2.223e-02 | 2.336e-02 | 2.146e-02 | 2.616e-02 | 1.795e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 1 | 1.621e-02 | 1.758e-02 | 1.583e-02 | 1.822e-02 | 1.320e-02 |
| 2 | 8.154e-03 | 1.030e-02 | 7.393e-03 | 8.907e-03 | 6.011e-03 |
| 3 | 5.330e-03 | 6.833e-03 | 5.351e-03 | 5.559e-03 | 3.577e-03 |
| 4 | 3.790e-03 | 4.597e-03 | 4.247e-03 | 4.034e-03 | 2.282e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 5.047e-02 | 5.272e-02 | 4.823e-02 | 5.984e-02 | 4.107e-02 |
| 0.05 | 7.663e-02 | 6.656e-02 | 7.296e-02 | 1.006e-01 | 6.642e-02 |
| 0.1 | 1.037e-01 | 9.610e-02 | 1.016e-01 | 1.256e-01 | 9.143e-02 |
| 0.2 | 1.045e-01 | 1.032e-01 | 1.104e-01 | 1.146e-01 | 8.958e-02 |
| 0.3 | 8.741e-02 | 8.799e-02 | 8.882e-02 | 1.003e-01 | 7.249e-02 |
| 0.4 | 7.236e-02 | 7.582e-02 | 7.106e-02 | 8.302e-02 | 5.952e-02 |
| 0.5 | 6.129e-02 | 6.704e-02 | 5.828e-02 | 6.958e-02 | 5.026e-02 |
| 0.75 | 4.464e-02 | 4.785e-02 | 4.206e-02 | 5.310e-02 | 3.554e-02 |
| 1 | 3.289e-02 | 3.648e-02 | 3.152e-02 | 3.730e-02 | 2.625e-02 |
| 2 | 1.667e-02 | 2.175e-02 | 1.483e-02 | 1.807e-02 | 1.203e-02 |
| 3 | 1.088e-02 | 1.430e-02 | 1.082e-02 | 1.129e-02 | 7.114e-03 |
| 4 | 7.651e-03 | 9.538e-03 | 8.587e-03 | 7.959e-03 | 4.519e-03 |

Source: unnamed intrabasin faults west of the Rio Puerco
Region: Mt Taylor Deterministic
Closest Distance: 87.30 km
Amplitude Units: Acceleration (g)
Magnitude: 6.60 Mw

Fractile: 0.50
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 1.619e-02 | 1.519e-02 | 1.563e-02 | 2.013e-02 | 1.380e-02 |
| 0.05 | 2.290e-02 | 1.862e-02 | 2.110e-02 | 3.107e-02 | 2.079e-02 |
| 0.1 | 2.941e-02 | 2.540e-02 | 2.872e-02 | 3.660e-02 | 2.693e-02 |
| 0.2 | 3.134e-02 | 2.745e-02 | 3.589e-02 | 3.588e-02 | 2.615e-02 |
| 0.3 | 2.737e-02 | 2.439e-02 | 3.037e-02 | 3.307e-02 | 2.164e-02 |
| 0.4 | 2.297e-02 | 2.197e-02 | 2.443e-02 | 2.740e-02 | 1.808e-02 |
| 0.5 | 1.944e-02 | 1.976e-02 | 1.972e-02 | 2.278e-02 | 1.547e-02 |
| 0.75 | 1.402e-02 | 1.404e-02 | 1.387e-02 | 1.703e-02 | 1.115e-02 |
| 1 | 1.021e-02 | 1.051e-02 | 1.027e-02 | 1.173e-02 | 8.350e-03 |
| 2 | 5.120e-03 | 6.192e-03 | 4.768e-03 | 5.600e-03 | 3.920e-03 |
| 3 | 3.309e-03 | 4.070e-03 | 3.390e-03 | 3.431e-03 | 2.344e-03 |
| 4 | 2.327e-03 | 2.722e-03 | 2.657e-03 | 2.449e-03 | 1.482e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.945e-02 | 2.886e-02 | 2.853e-02 | 3.613e-02 | 2.427e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 0.05 | 4.345e-02 | 3.566e-02 | 4.155e-02 | 5.885e-02 | 3.773e-02 |
| 0.1 | 5.764e-02 | 4.944e-02 | 5.837e-02 | 7.271e-02 | 5.003e-02 |
| 0.2 | 5.967e-02 | 5.409e-02 | 6.658e-02 | 6.829e-02 | 4.974e-02 |
| 0.3 | 5.212e-02 | 4.865e-02 | 5.548e-02 | 6.264e-02 | 4.172e-02 |
| 0.4 | 4.418e-02 | 4.419e-02 | 4.511e-02 | 5.225e-02 | 3.519e-02 |
| 0.5 | 3.795e-02 | 4.009e-02 | 3.726e-02 | 4.414e-02 | 3.032e-02 |
| 0.75 | 2.817e-02 | 2.884e-02 | 2.718e-02 | 3.458e-02 | 2.208e-02 |
| 1 | 2.073e-02 | 2.186e-02 | 2.044e-02 | 2.402e-02 | 1.660e-02 |
| 2 | 1.047e-02 | 1.311e-02 | 9.565e-03 | 1.136e-02 | 7.843e-03 |
| 3 | 6.757e-03 | 8.541e-03 | 6.855e-03 | 6.970e-03 | 4.661e-03 |
| 4 | 4.700e-03 | 5.664e-03 | 5.372e-03 | 4.831e-03 | 2.934e-03 |

Source: Zia fault [2046]
Region: USGS 2014 New Mexico
  Closest Distance: 73.74 km
  Amplitude Units: Acceleration (g)
  Magnitude: 6.84 Mw
  Fractile: 0.50
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.441e-02 | 2.461e-02 | 2.261e-02 | 2.912e-02 | 2.129e-02 |
| 0.05 | 3.494e-02 | 3.049e-02 | 3.088e-02 | 4.570e-02 | 3.270e-02 |
| 0.1 | 4.506e-02 | 4.245e-02 | 4.128e-02 | 5.323e-02 | 4.327e-02 |
| 0.2 | 4.682e-02 | 4.590e-02 | 4.952e-02 | 5.032e-02 | 4.155e-02 |
| 0.3 | 4.023e-02 | 4.009e-02 | 4.131e-02 | 4.585e-02 | 3.369e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 0.4 | 3.354e-02 | 3.540e-02 | 3.315e-02 | 3.786e-02 | 2.774e-02 |
| 0.5 | 2.836e-02 | 3.165e-02 | 2.682e-02 | 3.148e-02 | 2.349e-02 |
| 0.75 | 2.046e-02 | 2.284e-02 | 1.888e-02 | 2.335e-02 | 1.674e-02 |
| 1 | 1.501e-02 | 1.732e-02 | 1.404e-02 | 1.620e-02 | 1.247e-02 |
| 2 | 7.818e-03 | 1.037e-02 | 6.847e-03 | 8.134e-03 | 5.922e-03 |
| 3 | 5.257e-03 | 7.155e-03 | 5.087e-03 | 5.155e-03 | 3.632e-03 |
| 4 | 3.798e-03 | 4.909e-03 | 4.134e-03 | 3.780e-03 | 2.368e-03 |

Fractile: 0.84
Column 1: Spectral Period
Column 2: Acceleration (g) for: Weighted Mean of Attenuation Equations
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 4.434e-02 | 4.638e-02 | 4.127e-02 | 5.226e-02 | 3.744e-02 |
| 0.05 | 6.616e-02 | 5.795e-02 | 6.081e-02 | 8.655e-02 | 5.933e-02 |
| 0.1 | 8.792e-02 | 8.201e-02 | 8.354e-02 | 1.057e-01 | 8.039e-02 |
| 0.2 | 8.912e-02 | 8.979e-02 | 9.186e-02 | 9.578e-02 | 7.905e-02 |
| 0.3 | 7.667e-02 | 7.941e-02 | 7.546e-02 | 8.685e-02 | 6.495e-02 |
| 0.4 | 6.453e-02 | 7.071e-02 | 6.121e-02 | 7.220e-02 | 5.398e-02 |
| 0.5 | 5.536e-02 | 6.375e-02 | 5.066e-02 | 6.101e-02 | 4.603e-02 |
| 0.75 | 4.104e-02 | 4.661e-02 | 3.700e-02 | 4.741e-02 | 3.314e-02 |
| 1 | 3.043e-02 | 3.579e-02 | 2.796e-02 | 3.316e-02 | 2.480e-02 |
| 2 | 1.597e-02 | 2.180e-02 | 1.374e-02 | 1.650e-02 | 1.185e-02 |
| 3 | 1.072e-02 | 1.491e-02 | 1.029e-02 | 1.047e-02 | 7.223e-03 |
| 4 | 7.663e-03 | 1.014e-02 | 8.359e-03 | 7.458e-03 | 4.690e-03 |

# APPENDIX D
# PROBABILISTIC ANALYSES

# APPENDIX D.1
# SUMMARY OF PROBABILISTIC CHARACTERISTICS

## Appendix D.1 Probabilistic Characteristics of Quaternary Faults and Folds Capable of Generating a PGA of 0.05g or Greater

| Name of Faults | ID Number | Age of Most Recent Prehistoric Deformation (ya)[1] | Probability of Activity | Dip[2] (Degrees) | Maximum Seismogenic Depth[2] (km) | Rate of Activity[2] (mm/yr) | MCE[3,4] |
|---|---|---|---|---|---|---|---|
| Intrabasin faults on the Llano de Albuquerque | 2121 | <750,000 | 1 | 60 | 15 | 0.02 | 7.5 |
| Jemez-San Ysidro fault (Jemez and San Ysidro sections)[(4)] | 2029ab | <1,600,000 | 1 | 35 (0.2)<br>50 (0.4)<br>65 (0.2) | 15 | (4) | 7.09 |
| Jemez-San Ysidro fault (Calabacillas section)[(4)] | 2029c | <15,000 | 1 | 35 (0.2)<br>50 (0.4)<br>65 (0.2) | 15 | (4) | 6.83 |
| Mesa Prieta faults | 1985 | <1,600,000 | 0.5 | 60 | 15 | 0.02 | 6.3 |
| Nacimiento fault (northern and southern sections)[(4)] | 2002ab | <1,600,000 | 1 | 35 (0.2)<br>50 (0.4)<br>65 (0.2) | 15 | (4) | 7.3 |
| Sand Hill fault zone | 2039 | <1,600,000 | 0.5 | 60 | 15 | 0.02 | 6.9 |
| Santa Fe fault | 2123 | <1,600,000 | 0.5 | 60 | 15 | 0.02 | 6.8 |
| unnamed faults near Albuquerque Volcanoes | 2049 | <750,000 | 1 | 60 | 15 | 0.02 | 6.9 |
| unnamed faults of El Malpais lava field | 2146 | <1,600,000 | 0.5 | 60 | 15 | 0.02 | 6.7 |

1) Years ago
2) Number in parentheses represents weights for each parameter
3) The middle number is the magnitude of the Maximum Credible Earthquake as calculated by Wells and Coppersmith (1994), an additional minimum and maximum of MCE +0.3 and MCE -0.3 are entered for each model in the analysis of the fault to account for standard error in their equation.
4) The parameters included in the EZ Frisk program from the USGS Hazard mapping used for analysis.

# APPENDIX D.2
# PROBABILISTIC EZ-FRISK SOFTWARE INPUT

```
                  ********************************************
                  *****              EZ-FRISK              *****
                  ***** SEISMIC HAZARD ANALYSIS DEFINITION *****
                  *****               FUGRO                *****
                  *****        WALNUT CREEK, CA  USA       *****
                  ********************************************

PROGRAM VERSION
  EZ-FRISK 8.11 Build 019

ANALYSIS TITLE:
  Mt Taylor - 10,000 yr

ANALYSIS TYPE:
  Single Site Analysis

SITE COORDINATES
  Latitude 35.3409
  Longitude -107.635

INTENSITY TYPE:  Spectral Response @ 5% Damping

HAZARD DEAGGREGATION
  Status: ON
  Deagregation Scenario 1
    Period:             PGA
    Amplitude:          0.02 Acceleration (g)
  Bin Configuration
    Magnitude
      Scale:         Moment Magnitude
      Lowest Value:  4 Mw
      Highest Value: 9 Mw
      Bin Size:      0.1
    Distance
      Lowest Value:  0 km
      Highest Value: 300 km
      Bin Size:      2.5 km
    Epsilon
      Lowest Value:  -2.2
      Highest Value: 4.2
      Bin Size:      0.2

SOIL AMPLIFICATION
  Method: Do not use soil amplification

ATTENUATION EQUATION SITE PARAMETERS
  Depth[Vs=1,000m/s] (m): 5
  Depth[Vs=1000m/s] (m): -1
  Estimate Z1 from Vs30 for CY NGA: 1
  Regional Code: Default
  Subduction Zone Setting: Unknown
  Vs30 (m/s): 1200
  Vs30 Is Measured: 0
  Z25 (km): 0.79
```

AMPLITUDES - Acceleration (g)
  0.0001
  0.001
  0.01
  0.02
  0.05
  0.07
  0.1
  0.2
  0.3
  0.4
  0.5
  0.7
  1
  2
  3

PERIODS (s)
  PGA
  0.05
  0.1
  0.2
  0.3
  0.4
  0.5
  0.75
  1
  2
  3
  4

DETERMINISTIC FRACTILES

PLOTTING PARAMETERS
  Period at which to plot PGA: 0.0001

CALCULATIONAL PARAMETERS
  Fault Seismic Sources -
    Maximum inclusion distance           :   1000 km
    Down dip integration increment       :   1 km
    Horizontal integration increment     :   1 km
    Number rupture length per earthquake :   4
  Subduction Interface Seismic Sources -
    Maximum inclusion distance           :   1000 km
    Down dip integration increment       :   5 km
    Horizontal integration increment     :   20 km
    Number rupture length per earthquake :   1
  Subduction Slab Seismic Sources -
    Maximum inclusion distance           :   1000 km
    Down dip integration increment       :   5 km
    Horizontal integration increment     :   20 km
    Number rupture length per earthquake :   1
  Area Seismic Sources -

```
    Maximum inclusion distance           :   1000 km
    Vertical integration increment       :   3 km
    Number of rupture azimuths           :   3
    Minimum epicentral distance step     :   0.5 km
    Maximum epicentral distance step     :   10 km
  Gridded Seismic Sources -
    Maximum inclusion distance           :   400 km
    Default number of rupture azimuths   :   10
    Maximum distance for default azimuths :   20 km
    Minimum distance for one azimuth     :   70
    Use binned calcuations if possible   :   true
    Bins per decade in distance (km)     :   20
  All Seismic Sources -
    Magnitude integration step           :   0.1 M
    Apply magnitude scaling              :   NO
    Include near-source directivity      :   NO

ATTENUATION EQUATIONS

  Name: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Database: C:\Program Files (x86)\EZ-FRISK 8.11\Files\standard.bin-
attendb
  Base: Abrahamson-et al 2014 NGA West 2
  Truncation Type: USGS 2008 NSHM Truncation
  Truncation Value: 3
  Magnitude Scale: Moment Magnitude
  Distance Type: Distance To Rupture

  Name: Boore-et al (2014) NGA West 2 USGS 2014
  Database: C:\Program Files (x86)\EZ-FRISK 8.11\Files\standard.bin-
attendb
  Base: Boore-et al 2014 NGA West 2
  Truncation Type: USGS 2008 NSHM Truncation
  Truncation Value: 3
  Magnitude Scale: Moment Magnitude
  Distance Type: Horizontal Distance To Rupture

  Name: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Database: C:\Program Files (x86)\EZ-FRISK 8.11\Files\standard.bin-
attendb
  Base: Campbell-Bozorgnia 2014 NGA West 2
  Truncation Type: USGS 2008 NSHM Truncation
  Truncation Value: 3
  Magnitude Scale: Moment Magnitude
  Distance Type: Distance To Rupture

  Name: Chiou-Youngs (2014) NGA West 2 USGS 2014
  Database: C:\Program Files (x86)\EZ-FRISK 8.11\Files\standard.bin-
attendb
  Base: Chiou-Youngs 2014 NGA West 2
  Truncation Type: USGS 2008 NSHM Truncation
  Truncation Value: 3
  Magnitude Scale: Moment Magnitude
  Distance Type: Distance To Rupture
```

SEISMIC SOURCE SUMMARY TABLE

| Closest Deterministic Fault Source | Distance | Magnitude | Mechanism | Dip Angle | Dips To | Site Region Lies |
|---|---|---|---|---|---|---|
| CEUS Gridded Source | 0.00 | 0.0000 | Strike Slip | 90.0000 | -- | USGS 2014 CEUS Gridded Source Above |
| Shallow - Extensional Gridded | 0.00 | 8.0000 | N\|SS | 90.0000 | -- | USGS 2014 WUS Gridded Source Above |
| Intrabasin faults on the Llano de Albuquerque | 66.68 | 7.5000 | Normal | 60.0000 | W | Mt Taylor Deterministic W |
| Jemez-San Ysidro fault [2029ab] | 77.22 | 7.0900 | Normal | 35-65 | E | USGS 2014 New Mexico W |
| Calabacillas fault [2035] | 70.51 | 6.8300 | Normal | 35-65 | E | USGS 2014 New Mexico W |
| Mesa Prieta faults | 47.03 | 6.3000 | Normal | 60.0000 | W | Mt Taylor Deterministic W |
| Nacimiento fault [2002ab] | 72.26 | 7.3000 | Normal | 35-65 | E | USGS 2014 New Mexico W |
| Sand Hill fault zone | 62.14 | 6.9000 | Normal | 60.0000 | W | Mt Taylor Deterministic W |
| Santa Fe fault | 67.75 | 6.8000 | Normal | 60.0000 | W | Mt Taylor Deterministic NW |
| unnamed faults near Albuquerque Volcanoes | 73.56 | 6.9000 | Normal | 60.0000 | W | Mt Taylor Deterministic W |
| unnamed faults of El Malpais lava field | 60.42 | 6.7000 | Normal | 60.0000 | W | Mt Taylor Deterministic NE |

SEISMIC SOURCES

Name: CEUS Gridded Source
Region: USGS 2014 CEUS Gridded Source
Category:Composite Seismic Source
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Regions\EZ-FRISK USGS2014 Lower 48 v1.00\Files\USGS 2014 Lower 48.bin-ssdb
Magnitude Scale: Moment Magnitude
Probability of Activity: 1
------ Start Nested Sources forCEUS Gridded Source -------
Name: CEUS_adGridded_2014_2zone_Mmax 6.5-6.8
Region: USGS 2014 Central and Eastern US
Category:Gridded
FileType: USGS2008

General Parameters
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.2
Latitude Increment, degrees: 0.1
Longitude Increment, degrees: 0.1
Magnitude Threshold for Weighting: 4.7

```
Earthquake Model Parameters                (Varies point to point?)
  Cell Weight: 1                                    Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0                              Yes
  Rate at Minimum Magnitude, events per year: 0     Yes
  Beta: 2.3025
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_adGridded_2014_2zone_Mmax 7.0-7.2
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.2
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters                (Varies point to point?)
  Cell Weight: 1                                    Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0                              Yes
  Rate at Minimum Magnitude, events per year: 0     Yes
  Beta: 2.3025
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_adGridded_2014_2zone_Mmax 7.5-7.6
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.2
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters                (Varies point to point?)
  Cell Weight: 1                                    Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0                              Yes
```

```
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 2.3025
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_adGridded_2014_2zone_Mmax 8.0
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.2
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1                                  Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0                            Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 2.3025
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_adGridded_2014_4zone_Mmax 6.5-6.8
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.2
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1                                  Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0                            Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 2.3025
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike
```

Name: CEUS_adGridded_2014_4zone_Mmax 7.0-7.2
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.2
  Latitude Increment, degrees:  0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters (Varies point to point?)
  Cell Weight: 1 Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0 Yes
  Rate at Minimum Magnitude, events per year: 0 Yes
  Beta: 2.3025
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_adGridded_2014_4zone_Mmax 7.5-7.6
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.2
  Latitude Increment, degrees:  0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters (Varies point to point?)
  Cell Weight: 1 Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0 Yes
  Rate at Minimum Magnitude, events per year: 0 Yes
  Beta: 2.3025
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_adGridded_2014_4zone_Mmax 8.0
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters

```
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.2
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1                                  Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0                            Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 2.3025
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_fixGridded_2014_2zone_Mmax 6.5-6.8
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.3
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1                                  Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0                            Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 2.3025                                    Yes
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_fixGridded_2014_2zone_Mmax 7.0-7.2
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.3
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7
```

```
Earthquake Model Parameters                (Varies point to point?)
  Cell Weight: 1                                    Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0                              Yes
  Rate at Minimum Magnitude, events per year: 0     Yes
  Beta: 2.3025                                      Yes
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_fixGridded_2014_2zone_Mmax 7.5-7.6
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.3
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters                (Varies point to point?)
  Cell Weight: 1                                    Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0                              Yes
  Rate at Minimum Magnitude, events per year: 0     Yes
  Beta: 2.3025                                      Yes
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_fixGridded_2014_2zone_Mmax 8.0
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.3
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters                (Varies point to point?)
  Cell Weight: 1                                    Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0                              Yes
```

```
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 2.3025                                    Yes
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_fixGridded_2014_4zone_Mmax 6.5-6.8
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.3
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1                                  Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0                            Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 2.3025                                    Yes
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_fixGridded_2014_4zone_Mmax 7.0-7.2
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.3
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1                                  Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0                            Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 2.3025                                    Yes
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike
```

Name: CEUS_fixGridded_2014_4zone_Mmax 7.5-7.6
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.3
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters (Varies point to point?)
  Cell Weight: 1 Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0 Yes
  Rate at Minimum Magnitude, events per year: 0 Yes
  Beta: 2.3025 Yes
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

Name: CEUS_fixGridded_2014_4zone_Mmax 8.0
Region: USGS 2014 Central and Eastern US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.3
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 4.7

Earthquake Model Parameters (Varies point to point?)
  Cell Weight: 1 Yes
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 4.7
  Maximum Magnitude: 0 Yes
  Rate at Minimum Magnitude, events per year: 0 Yes
  Beta: 2.3025 Yes
  Horizontal Rupture Length, A parameter: -2.0325
  Horizontal Rupture Length, B parameter: 0.5
  Rupture Strike Azimuth Model: Random Strike

 ------ End Nested Sources for CEUS Gridded Source -------

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014

```
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

****************************************

Name: Shallow - Extensional Gridded
Region: USGS 2014 WUS Gridded Source
Category:Composite Seismic Source
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Regions\EZ-FRISK
USGS2014 Lower 48 v1.00\Files\USGS 2014 Lower 48.bin-ssdb
Magnitude Scale: Moment Magnitude
Probability of Activity: 1
 ------ Start Nested Sources forShallow - Extensional Gridded -------
Name: Extensional Gridded, adSm, Tapered_M7.95, Strike Slip
Region: USGS 2014 Western US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.0133333
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 5

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 5
  Maximum Magnitude: 8
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 1.842
  Horizontal Rupture Length, A parameter: -3.22
  Horizontal Rupture Length, B parameter: 0.69
  Rupture Strike Azimuth Model: Random Strike

Name: Extensional Gridded, adSm, Tapered_M7.95, Normal
Region: USGS 2014 Western US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.0266667
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 5

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1
```

```
  Fault Mechanism: Normal
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 5
  Maximum Magnitude: 8
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 1.842
  Horizontal Rupture Length, A parameter: -3.22
  Horizontal Rupture Length, B parameter: 0.69
  Rupture Strike Azimuth Model: Random Strike

Name: Extensional Gridded, adSm, Truncated_M7.5, Char, Normal
Region: USGS 2014 Western US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.16
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 5

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1
  Fault Mechanism: Normal
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 5
  Maximum Magnitude: 7                              Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 1.842
  Horizontal Rupture Length, A parameter: -3.22
  Horizontal Rupture Length, B parameter: 0.69
  Rupture Strike Azimuth Model: Random Strike

Name: Extensional Gridded, adSm, Truncated_M7.5, Char, Strike Slip
Region: USGS 2014 Western US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.08
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 5

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 5
  Maximum Magnitude: 7                              Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 1.842
```

```
  Horizontal Rupture Length, A parameter: -3.22
  Horizontal Rupture Length, B parameter: 0.69
  Rupture Strike Azimuth Model: Random Strike

Name: Extensional Gridded, adSm, Truncated_M7.5, GR, Normal
Region: USGS 2014 Western US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.08
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 5

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1
  Fault Mechanism: Normal
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 5
  Maximum Magnitude: 7                                Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 1.842
  Horizontal Rupture Length, A parameter: -3.22
  Horizontal Rupture Length, B parameter: 0.69
  Rupture Strike Azimuth Model: Random Strike

Name: Extensional Gridded, adSm, Truncated_M7.5, GR, Strike Slip
Region: USGS 2014 Western US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.04
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 5

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 5
  Maximum Magnitude: 7                                Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 1.842
  Horizontal Rupture Length, A parameter: -3.22
  Horizontal Rupture Length, B parameter: 0.69
  Rupture Strike Azimuth Model: Random Strike

Name: Extensional Gridded, fixSm, Tapered_M7.95, Normal
Region: USGS 2014 Western US
```

Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.04
  Latitude Increment, degrees:  0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 5

Earthquake Model Parameters  (Varies point to point?)
  Cell Weight: 1
  Fault Mechanism: Normal
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 5
  Maximum Magnitude: 8
  Rate at Minimum Magnitude, events per year: 0  Yes
  Beta: 1.842
  Horizontal Rupture Length, A parameter: -3.22
  Horizontal Rupture Length, B parameter: 0.69
  Rupture Strike Azimuth Model: Random Strike

Name: Extensional Gridded, fixSm, Tapered_M7.95, Strike Slip
Region: USGS 2014 Western US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.02
  Latitude Increment, degrees:  0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 5

Earthquake Model Parameters  (Varies point to point?)
  Cell Weight: 1
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 5
  Maximum Magnitude: 8
  Rate at Minimum Magnitude, events per year: 0  Yes
  Beta: 1.842
  Horizontal Rupture Length, A parameter: -3.22
  Horizontal Rupture Length, B parameter: 0.69
  Rupture Strike Azimuth Model: Random Strike

Name: Extensional Gridded, fixSm, Truncated_M7.5, Char, Normal
Region: USGS 2014 Western US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.24

```
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 5

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1
  Fault Mechanism: Normal
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 5
  Maximum Magnitude: 7                                Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 1.842
  Horizontal Rupture Length, A parameter: -3.22
  Horizontal Rupture Length, B parameter: 0.69
  Rupture Strike Azimuth Model: Random Strike

Name: Extensional Gridded, fixSm, Truncated_M7.5, Char, Strike Slip
Region: USGS 2014 Western US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.12
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 5

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 5
  Maximum Magnitude: 7                                Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 1.842
  Horizontal Rupture Length, A parameter: -3.22
  Horizontal Rupture Length, B parameter: 0.69
  Rupture Strike Azimuth Model: Random Strike

Name: Extensional Gridded, fixSm, Truncated_M7.5, GR, Normal
Region: USGS 2014 Western US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.12
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 5

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1
```

```
  Fault Mechanism: Normal
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 5
  Maximum Magnitude: 7                              Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 1.842
  Horizontal Rupture Length, A parameter: -3.22
  Horizontal Rupture Length, B parameter: 0.69
  Rupture Strike Azimuth Model: Random Strike

Name: Extensional Gridded, fixSm, Truncated_M7.5, GR, Strike Slip
Region: USGS 2014 Western US
Category:Gridded
  FileType: USGS2008

General Parameters
  Magnitude Scale: Moment Magnitude
  Probability of Activity: 0.06
  Latitude Increment, degrees:   0.1
  Longitude Increment, degrees:  0.1
  Magnitude Threshold for Weighting: 5

Earthquake Model Parameters               (Varies point to point?)
  Cell Weight: 1
  Fault Mechanism: Strike Slip
  Depth to Top of Rupture, km: 5
  Minimum Magnitude: 5
  Maximum Magnitude: 7                              Yes
  Rate at Minimum Magnitude, events per year: 0   Yes
  Beta: 1.842
  Horizontal Rupture Length, A parameter: -3.22
  Horizontal Rupture Length, B parameter: 0.69
  Rupture Strike Azimuth Model: Random Strike

 ------ End Nested Sources for Shallow - Extensional Gridded -------

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

*****************************************

Name: Intrabasin faults on the Llano de Albuquerque
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-
ssdb
Fault Mechanism: Normal
```

Magnitude Scale: Moment Magnitude
Probability of Activity: 1.00000000
Deterministic Magnitude: 7.5

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 60 | 60 | 0 | 0.1 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 1 | Slip | 2.000e-02 | 7.200000 | 7.800000 | 0.000000 | 7.500000 | 0.120000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.100000 | 4.000000 | 0.000000 | 0.100000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.1810 | -106.8520 |
| 34.4930 | -106.8350 |

Attenuation Equations for Source:

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

Name: Jemez-San Ysidro fault [2029ab]
Region: USGS 2014 New Mexico
Category:Composite Seismic Source
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Regions\EZ-FRISK USGS2014 Lower 48 v1.00\Files\USGS 2014 Lower 48.bin-ssdb
Magnitude Scale: Moment Magnitude
Probability of Activity: 1
 ------ Start Nested Sources forJemez-San Ysidro fault [2029ab] -------
Name: 2029ab Jemez-San Ysidro fault (dip 35)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 7.09

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 35 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 1.815e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.815e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.815e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 4.237e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 5.479e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 6.339e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.106666 | Activity | 1.582e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.319998 | Activity | 1.582e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.106666 | Activity | 1.582e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.053334 | Activity | 3.687e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.160002 | Activity | 4.768e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.053334 | Activity | 5.516e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.013334 | Activity | 2.420e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 2.420e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 2.420e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 5.650e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 7.306e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 8.452e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

```
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
```

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.4204 | -106.7887 |
| 35.4846 | -106.7821 |
| 35.5444 | -106.7889 |
| 35.5588 | -106.7854 |
| 35.5980 | -106.7870 |
| 35.6099 | -106.7896 |
| 35.6472 | -106.8137 |
| 35.6645 | -106.8166 |
| 35.6864 | -106.8126 |
| 35.7072 | -106.7940 |
| 35.7251 | -106.7645 |
| 35.7443 | -106.7555 |
| 35.7529 | -106.7401 |
| 35.7737 | -106.7198 |
| 35.7876 | -106.6880 |
| 35.8181 | -106.6576 |
| 35.8332 | -106.6346 |

Name: 2029ab Jemez-San Ysidro fault (dip 50)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude

Probability of Activity: 0.60000000
Deterministic Magnitude: 7.09

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 50 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 1.815e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.815e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.815e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 4.237e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 5.479e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 6.339e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.106666 | Activity | 1.582e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.319998 | Activity | 1.582e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.106666 | Activity | 1.582e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.053334 | Activity | 3.687e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.160002 | Activity | 4.768e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.053334 | Activity | 5.516e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.013334 | Activity | 2.420e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 2.420e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 2.420e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 5.650e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 7.306e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 8.452e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |

```
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.4204  -106.7887
    35.4846  -106.7821
    35.5444  -106.7889
    35.5588  -106.7854
    35.5980  -106.7870
    35.6099  -106.7896
    35.6472  -106.8137
    35.6645  -106.8166
    35.6864  -106.8126
    35.7072  -106.7940
    35.7251  -106.7645
    35.7443  -106.7555
    35.7529  -106.7401
    35.7737  -106.7198
    35.7876  -106.6880
    35.8181  -106.6576
    35.8332  -106.6346

Name: 2029ab Jemez-San Ysidro fault (dip 65)
```

Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 7.09

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 65 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 1.815e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.815e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.815e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 4.237e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 5.479e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 6.339e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.106666 | Activity | 1.582e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.319998 | Activity | 1.582e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.106666 | Activity | 1.582e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.053334 | Activity | 3.687e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.160002 | Activity | 4.768e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.053334 | Activity | 5.516e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.013334 | Activity | 2.420e-05 | 6.650000 | 7.130000 | 2.300000 | 6.890000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 2.420e-05 | 6.850000 | 7.330000 | 2.300000 | 7.090000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 2.420e-05 | 7.050000 | 7.530000 | 2.300000 | 7.290000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 5.650e-05 | 6.500000 | 6.890000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 7.306e-05 | 6.500000 | 7.090000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 8.452e-05 | 6.500000 | 7.290000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.4204 | -106.7887 |
| 35.4846 | -106.7821 |
| 35.5444 | -106.7889 |
| 35.5588 | -106.7854 |
| 35.5980 | -106.7870 |
| 35.6099 | -106.7896 |
| 35.6472 | -106.8137 |
| 35.6645 | -106.8166 |
| 35.6864 | -106.8126 |
| 35.7072 | -106.7940 |
| 35.7251 | -106.7645 |
| 35.7443 | -106.7555 |
| 35.7529 | -106.7401 |
| 35.7737 | -106.7198 |
| 35.7876 | -106.6880 |

```
    35.8181  -106.6576
    35.8332  -106.6346

 ------ End Nested Sources for Jemez-San Ysidro fault [2029ab] -------

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

*****************************************

Name: Calabacillas fault [2035]
Region: USGS 2014 New Mexico
Category:Composite Seismic Source
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Regions\EZ-FRISK
USGS2014 Lower 48 v1.00\Files\USGS 2014 Lower 48.bin-ssdb
Magnitude Scale: Moment Magnitude
Probability of Activity: 1
 ------ Start Nested Sources forCalabacillas fault [2035] -------
Name: 2035 Calabacillas fault (dip 35)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 6.83

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          90        35         0     0.001        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
           Normal  0.013334    Activity   1.984e-04  6.390000  6.870000
2.300000  6.630000  0.120000  0.010000 10.000000
           Normal  0.040002    Activity   1.984e-04  6.590000  7.070000
2.300000  6.830000  0.120000  0.010000 10.000000
           Normal  0.013334    Activity   1.984e-04  6.790000  7.270000
2.300000  7.030000  0.120000  0.010000 10.000000
      Exponential  0.006666    Activity   1.770e-04  6.500000  6.630000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.019998    Activity   3.787e-04  6.500000  6.830000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.006666    Activity   5.181e-04  6.500000  7.030000
1.842068  0.000000  0.000000  0.000000  0.000000
           Normal  0.106666    Activity   8.097e-06  6.390000  6.870000
2.300000  6.630000  0.120000  0.010000 10.000000
```

| | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Normal | 0.319998 | Activity | 8.097e-06 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.106666 | Activity | 8.097e-06 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 | |
| | Exponential | 0.053334 | Activity | 7.248e-06 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.160002 | Activity | 1.550e-05 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.053334 | Activity | 2.121e-05 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Normal | 0.013334 | Activity | 9.028e-06 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.040002 | Activity | 9.028e-06 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.013334 | Activity | 9.028e-06 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 | |
| | Exponential | 0.006666 | Activity | 8.047e-06 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.019998 | Activity | 1.721e-05 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.006666 | Activity | 2.355e-05 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |

```
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.1404  -106.8390
    35.2034  -106.8526
    35.2416  -106.8654
    35.2671  -106.8632
    35.3315  -106.8350
    35.4192  -106.7898

Name: 2035 Calabacillas fault (dip 50)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.60000000
Deterministic Magnitude: 6.83

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          90        50         0     0.001        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
           Normal  0.013334    Activity   1.984e-04  6.390000  6.870000
2.300000  6.630000  0.120000  0.010000 10.000000
           Normal  0.040002    Activity   1.984e-04  6.590000  7.070000
2.300000  6.830000  0.120000  0.010000 10.000000
           Normal  0.013334    Activity   1.984e-04  6.790000  7.270000
2.300000  7.030000  0.120000  0.010000 10.000000
      Exponential  0.006666    Activity   1.770e-04  6.500000  6.630000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.019998    Activity   3.787e-04  6.500000  6.830000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.006666    Activity   5.181e-04  6.500000  7.030000
1.842068  0.000000  0.000000  0.000000  0.000000
           Normal  0.106666    Activity   8.097e-06  6.390000  6.870000
2.300000  6.630000  0.120000  0.010000 10.000000
           Normal  0.319998    Activity   8.097e-06  6.590000  7.070000
2.300000  6.830000  0.120000  0.010000 10.000000
           Normal  0.106666    Activity   8.097e-06  6.790000  7.270000
2.300000  7.030000  0.120000  0.010000 10.000000
      Exponential  0.053334    Activity   7.248e-06  6.500000  6.630000
1.842068  0.000000  0.000000  0.000000  0.000000
```

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Exponential | 0.160002 | Activity | 1.550e-05 | 6.500000 | 6.830000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Exponential | 0.053334 | Activity | 2.121e-05 | 6.500000 | 7.030000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Normal | 0.013334 | Activity | 9.028e-06 | 6.390000 | 6.870000 | 2.300000 | 6.630000 |
| 0.120000 | 0.010000 | 10.000000 | | | | | |
| Normal | 0.040002 | Activity | 9.028e-06 | 6.590000 | 7.070000 | 2.300000 | 6.830000 |
| 0.120000 | 0.010000 | 10.000000 | | | | | |
| Normal | 0.013334 | Activity | 9.028e-06 | 6.790000 | 7.270000 | 2.300000 | 7.030000 |
| 0.120000 | 0.010000 | 10.000000 | | | | | |
| Exponential | 0.006666 | Activity | 8.047e-06 | 6.500000 | 6.630000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Exponential | 0.019998 | Activity | 1.721e-05 | 6.500000 | 6.830000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |
| Exponential | 0.006666 | Activity | 2.355e-05 | 6.500000 | 7.030000 | 1.842068 | 0.000000 |
| 0.000000 | 0.000000 | 0.000000 | | | | | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

Length and width -3.220000 0.690000 0.220000 -3.220000 0.690000 0.220000 -- -- --

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.1404 | -106.8390 |
| 35.2034 | -106.8526 |
| 35.2416 | -106.8654 |
| 35.2671 | -106.8632 |
| 35.3315 | -106.8350 |
| 35.4192 | -106.7898 |

Name: 2035 Calabacillas fault (dip 65)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 6.83

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 65 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 1.984e-04 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.984e-04 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.984e-04 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 1.770e-04 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 3.787e-04 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.006666 | Activity | 5.181e-04 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.106666 | Activity | 8.097e-06 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.319998 | Activity | 8.097e-06 | 6.590000 | 7.070000 | 2.300000 | 6.830000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.106666 | Activity | 8.097e-06 | 6.790000 | 7.270000 | 2.300000 | 7.030000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.053334 | Activity | 7.248e-06 | 6.500000 | 6.630000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.160002 | Activity | 1.550e-05 | 6.500000 | 6.830000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.053334 | Activity | 2.121e-05 | 6.500000 | 7.030000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Normal | 0.013334 | Activity | 9.028e-06 | 6.390000 | 6.870000 | 2.300000 | 6.630000 | 0.120000 | 0.010000 | 10.000000 |

```
           Normal  0.040002    Activity   9.028e-06  6.590000  7.070000
2.300000  6.830000  0.120000  0.010000 10.000000
           Normal  0.013334    Activity   9.028e-06  6.790000  7.270000
2.300000  7.030000  0.120000  0.010000 10.000000
      Exponential  0.006666    Activity   8.047e-06  6.500000  6.630000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.019998    Activity   1.721e-05  6.500000  6.830000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.006666    Activity   2.355e-05  6.500000  7.030000
1.842068  0.000000  0.000000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.1404  -106.8390
```

```
    35.2034  -106.8526
    35.2416  -106.8654
    35.2671  -106.8632
    35.3315  -106.8350
    35.4192  -106.7898

 ------ End Nested Sources for Calabacillas fault [2035] -------

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

*****************************************

Name: Mesa Prieta faults
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-
ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.50000000
Deterministic Magnitude: 6.3

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          60        60         0       0.1        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
          Normal         1        Slip   2.000e-02  6.000000  6.600000
0.000000  6.300000  0.120000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.100000  4.000000  0.000000
0.100000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.5190  -107.0400
    35.4360  -107.0760

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
```

```
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

****************************************

Name: Nacimiento fault [2002ab]
Region: USGS 2014 New Mexico
Category:Composite Seismic Source
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Regions\EZ-FRISK
USGS2014 Lower 48 v1.00\Files\USGS 2014 Lower 48.bin-ssdb
Magnitude Scale: Moment Magnitude
Probability of Activity: 1
 ------ Start Nested Sources forNacimiento fault [2002ab] -------
Name: 2002ab Nacimiento fault (dip 35)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 7.3

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          90        35         0     0.001        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
           Normal  0.013334    Activity   1.041e-04  6.860000  7.340000
2.300000  7.100000  0.120000  0.010000 10.000000
           Normal  0.040002    Activity   1.041e-04  7.060000  7.540000
2.300000  7.300000  0.120000  0.010000 10.000000
           Normal  0.013334    Activity   1.041e-04  7.260000  7.740000
2.300000  7.500000  0.120000  0.010000 10.000000
      Exponential  0.006666    Activity   3.949e-04  6.500000  7.100000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.019998    Activity   4.551e-04  6.500000  7.300000
1.842068  0.000000  0.000000  0.000000  0.000000
      Exponential  0.006666    Activity   4.968e-04  6.500000  7.500000
1.842068  0.000000  0.000000  0.000000  0.000000
           Normal  0.106666    Activity   1.182e-05  6.860000  7.340000
2.300000  7.100000  0.120000  0.010000 10.000000
           Normal  0.319998    Activity   1.182e-05  7.060000  7.540000
2.300000  7.300000  0.120000  0.010000 10.000000
           Normal  0.106666    Activity   1.182e-05  7.260000  7.740000
2.300000  7.500000  0.120000  0.010000 10.000000
      Exponential  0.053334    Activity   4.483e-05  6.500000  7.100000
1.842068  0.000000  0.000000  0.000000  0.000000
```

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| Exponential | 0.160002 | Activity | 5.167e-05 | 6.500000 | 7.300000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| Exponential | 0.053334 | Activity | 5.640e-05 | 6.500000 | 7.500000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| Normal | 0.013334 | Activity | 1.815e-05 | 6.860000 | 7.340000 | 2.300000 | 7.100000 | 0.120000 | 0.010000 | 10.000000 | |
| Normal | 0.040002 | Activity | 1.815e-05 | 7.060000 | 7.540000 | 2.300000 | 7.300000 | 0.120000 | 0.010000 | 10.000000 | |
| Normal | 0.013334 | Activity | 1.815e-05 | 7.260000 | 7.740000 | 2.300000 | 7.500000 | 0.120000 | 0.010000 | 10.000000 | |
| Exponential | 0.006666 | Activity | 6.868e-05 | 6.500000 | 7.100000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| Exponential | 0.019998 | Activity | 7.916e-05 | 6.500000 | 7.300000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| Exponential | 0.006666 | Activity | 8.640e-05 | 6.500000 | 7.500000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.4853 | -106.8574 |
| 35.5849 | -106.8557 |
| 35.6246 | -106.8577 |
| 35.6777 | -106.8687 |
| 35.7441 | -106.8701 |
| 35.7740 | -106.8782 |
| 35.7902 | -106.8878 |
| 35.8244 | -106.8941 |
| 35.8730 | -106.8830 |
| 35.8874 | -106.8885 |
| 35.8967 | -106.8886 |
| 35.9087 | -106.8936 |
| 35.9475 | -106.8926 |
| 35.9999 | -106.9014 |
| 36.0348 | -106.8992 |
| 36.0541 | -106.9073 |
| 36.0739 | -106.9093 |
| 36.0917 | -106.9093 |
| 36.1155 | -106.9015 |
| 36.1908 | -106.9112 |
| 36.1985 | -106.9056 |
| 36.2198 | -106.9021 |

Name: 2002ab Nacimiento fault (dip 50)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.60000000
Deterministic Magnitude: 7.3

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 50 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 0.013334 | Activity | 1.041e-04 | 6.860000 | 7.340000 | 2.300000 | 7.100000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.040002 | Activity | 1.041e-04 | 7.060000 | 7.540000 | 2.300000 | 7.300000 | 0.120000 | 0.010000 | 10.000000 |
| Normal | 0.013334 | Activity | 1.041e-04 | 7.260000 | 7.740000 | 2.300000 | 7.500000 | 0.120000 | 0.010000 | 10.000000 |
| Exponential | 0.006666 | Activity | 3.949e-04 | 6.500000 | 7.100000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |
| Exponential | 0.019998 | Activity | 4.551e-04 | 6.500000 | 7.300000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 |

| | | | | | | |
|---|---|---|---|---|---|---|
| Exponential | 0.006666 | Activity | 4.968e-04 | 6.500000 | 7.500000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Normal | 0.106666 | Activity | 1.182e-05 | 6.860000 | 7.340000 | 2.300000 |
| 7.100000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Normal | 0.319998 | Activity | 1.182e-05 | 7.060000 | 7.540000 | 2.300000 |
| 7.300000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Normal | 0.106666 | Activity | 1.182e-05 | 7.260000 | 7.740000 | 2.300000 |
| 7.500000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Exponential | 0.053334 | Activity | 4.483e-05 | 6.500000 | 7.100000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Exponential | 0.160002 | Activity | 5.167e-05 | 6.500000 | 7.300000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Exponential | 0.053334 | Activity | 5.640e-05 | 6.500000 | 7.500000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Normal | 0.013334 | Activity | 1.815e-05 | 6.860000 | 7.340000 | 2.300000 |
| 7.100000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Normal | 0.040002 | Activity | 1.815e-05 | 7.060000 | 7.540000 | 2.300000 |
| 7.300000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Normal | 0.013334 | Activity | 1.815e-05 | 7.260000 | 7.740000 | 2.300000 |
| 7.500000 | 0.120000 | 0.010000 | 10.000000 | | | |
| Exponential | 0.006666 | Activity | 6.868e-05 | 6.500000 | 7.100000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Exponential | 0.019998 | Activity | 7.916e-05 | 6.500000 | 7.300000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |
| Exponential | 0.006666 | Activity | 8.640e-05 | 6.500000 | 7.500000 | 1.842068 |
| 0.000000 | 0.000000 | 0.000000 | 0.000000 | | | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.4853 | -106.8574 |
| 35.5849 | -106.8557 |
| 35.6246 | -106.8577 |
| 35.6777 | -106.8687 |
| 35.7441 | -106.8701 |
| 35.7740 | -106.8782 |
| 35.7902 | -106.8878 |
| 35.8244 | -106.8941 |
| 35.8730 | -106.8830 |
| 35.8874 | -106.8885 |
| 35.8967 | -106.8886 |
| 35.9087 | -106.8936 |
| 35.9475 | -106.8926 |
| 35.9999 | -106.9014 |
| 36.0348 | -106.8992 |
| 36.0541 | -106.9073 |
| 36.0739 | -106.9093 |
| 36.0917 | -106.9093 |
| 36.1155 | -106.9015 |
| 36.1908 | -106.9112 |
| 36.1985 | -106.9056 |
| 36.2198 | -106.9021 |

Name: 2002ab Nacimiento fault (dip 65)
Region: USGS 2014 New Mexico
Category:Fault
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.20000000
Deterministic Magnitude: 7.3

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 90 | 65 | 0 | 0.001 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|

| | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Normal | 0.013334 | Activity | 1.041e-04 | 6.860000 | 7.340000 | 2.300000 | 7.100000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.040002 | Activity | 1.041e-04 | 7.060000 | 7.540000 | 2.300000 | 7.300000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.013334 | Activity | 1.041e-04 | 7.260000 | 7.740000 | 2.300000 | 7.500000 | 0.120000 | 0.010000 | 10.000000 | |
| | Exponential | 0.006666 | Activity | 3.949e-04 | 6.500000 | 7.100000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.019998 | Activity | 4.551e-04 | 6.500000 | 7.300000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.006666 | Activity | 4.968e-04 | 6.500000 | 7.500000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Normal | 0.106666 | Activity | 1.182e-05 | 6.860000 | 7.340000 | 2.300000 | 7.100000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.319998 | Activity | 1.182e-05 | 7.060000 | 7.540000 | 2.300000 | 7.300000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.106666 | Activity | 1.182e-05 | 7.260000 | 7.740000 | 2.300000 | 7.500000 | 0.120000 | 0.010000 | 10.000000 | |
| | Exponential | 0.053334 | Activity | 4.483e-05 | 6.500000 | 7.100000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.160002 | Activity | 5.167e-05 | 6.500000 | 7.300000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.053334 | Activity | 5.640e-05 | 6.500000 | 7.500000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Normal | 0.013334 | Activity | 1.815e-05 | 6.860000 | 7.340000 | 2.300000 | 7.100000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.040002 | Activity | 1.815e-05 | 7.060000 | 7.540000 | 2.300000 | 7.300000 | 0.120000 | 0.010000 | 10.000000 | |
| | Normal | 0.013334 | Activity | 1.815e-05 | 7.260000 | 7.740000 | 2.300000 | 7.500000 | 0.120000 | 0.010000 | 10.000000 | |
| | Exponential | 0.006666 | Activity | 6.868e-05 | 6.500000 | 7.100000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.019998 | Activity | 7.916e-05 | 6.500000 | 7.300000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |
| | Exponential | 0.006666 | Activity | 8.640e-05 | 6.500000 | 7.500000 | 1.842068 | 0.000000 | 0.000000 | 0.000000 | 0.000000 | |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | -3.220000 | 0.690000 | 0.220000 | -3.220000 | 0.690000 | 0.220000 | -- | -- | -- |
| Length and width | 4.000000 | 0.000000 | 0.001000 | 4.000000 | 0.000000 | 0.001000 | -- | -- | -- |

```
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width  4.000000  0.000000  0.001000  4.000000  0.000000
0.001000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --
      Length and width -3.220000  0.690000  0.220000 -3.220000  0.690000
0.220000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.4853  -106.8574
    35.5849  -106.8557
    35.6246  -106.8577
    35.6777  -106.8687
    35.7441  -106.8701
    35.7740  -106.8782
    35.7902  -106.8878
    35.8244  -106.8941
    35.8730  -106.8830
    35.8874  -106.8885
    35.8967  -106.8886
    35.9087  -106.8936
    35.9475  -106.8926
    35.9999  -106.9014
    36.0348  -106.8992
    36.0541  -106.9073
    36.0739  -106.9093
    36.0917  -106.9093
    36.1155  -106.9015
    36.1908  -106.9112
    36.1985  -106.9056
    36.2198  -106.9021

 ------ End Nested Sources for Nacimiento fault [2002ab] -------

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
```

```
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

****************************************

Name: Sand Hill fault zone
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-
ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.50000000
Deterministic Magnitude: 6.9

Fault Profile Parameters:
        Dip1      Dip2    Depth1    Depth2    Depth3
          60        60         0       0.1        15

Magnitude Recurrence Distributions:
        ModelType    Weight    RateType        Rate    MinMag    MaxMag
Beta      Mean     Sigma    Delta1    Delta2
           Normal         1        Slip   2.000e-02  6.600000  7.200000
0.000000  6.900000  0.120000  0.000000  0.000000

Rupture Length Parameters
  Rupture Dimensioning        Al        Bl      Sigl        Aw        Bw
Sigw        Aa        Ba      Sigw
      Length and width  4.000000  0.000000  0.100000  4.000000  0.000000
0.100000        --        --        --

Trace Coordinates:
  Latitude   Longitude
    35.4440  -106.8690
    35.1400  -106.8840

Attenuation Equations for Source:
  Raw Weight  Normalized Weight  Name
      0.25      0.250000          Abrahamson-et al (2014) NGA West 2 USGS
2014
      0.25      0.250000          Boore-et al (2014) NGA West 2 USGS 2014
      0.25      0.250000          Campbell-Bozorgnia (2014) NGA West 2
USGS 2014
      0.25      0.250000          Chiou-Youngs (2014) NGA West 2 USGS
2014

****************************************

Name: Santa Fe fault
Region: Mt Taylor Deterministic
Category:Fault
```

Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.50000000
Deterministic Magnitude: 6.8

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 60 | 60 | 0 | 0.1 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 1 | Slip | 2.000e-02 | 6.500000 | 7.100000 | 0.000000 | 6.800000 | 0.120000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.100000 | 4.000000 | 0.000000 | 0.100000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 34.8880 | -107.0530 |
| 34.6360 | -107.1040 |

Attenuation Equations for Source:

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

Name: unnamed faults near Albuquerque Volcanoes
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 1.00000000
Deterministic Magnitude: 6.9

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 60 | 60 | 0 | 0.1 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 1 | Slip | 2.000e-02 | 6.600000 | 7.200000 | 0.000000 | 6.900000 | 0.120000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.100000 | 4.000000 | 0.000000 | 0.100000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 35.2180 | -106.7620 |
| 35.0650 | -106.7500 |

Attenuation Equations for Source:

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

Name: unnamed faults of El Malpais lava field
Region: Mt Taylor Deterministic
Category:Fault
Database: C:\Users\dgarcia\AppData\Local\Fugro\EZ-FRISK\Files\user.xml-ssdb
Fault Mechanism: Normal
Magnitude Scale: Moment Magnitude
Probability of Activity: 0.50000000
Deterministic Magnitude: 6.7

Fault Profile Parameters:

| Dip1 | Dip2 | Depth1 | Depth2 | Depth3 |
|---|---|---|---|---|
| 60 | 60 | 0 | 0.1 | 15 |

Magnitude Recurrence Distributions:

| ModelType | Weight | RateType | Rate | MinMag | MaxMag | Beta | Mean | Sigma | Delta1 | Delta2 |
|---|---|---|---|---|---|---|---|---|---|---|
| Normal | 1 | Slip | 2.000e-02 | 6.400000 | 7.000000 | 0.000000 | 6.700000 | 0.120000 | 0.000000 | 0.000000 |

Rupture Length Parameters

| Rupture Dimensioning | Al | Bl | Sigl | Aw | Bw | Sigw | Aa | Ba | Sigw |
|---|---|---|---|---|---|---|---|---|---|
| Length and width | 4.000000 | 0.000000 | 0.100000 | 4.000000 | 0.000000 | 0.100000 | -- | -- | -- |

Trace Coordinates:

| Latitude | Longitude |
|---|---|
| 34.8880 | -108.0030 |
| 34.5720 | -108.1560 |

Attenuation Equations for Source:

| Raw Weight | Normalized Weight | Name |
|---|---|---|
| 0.25 | 0.250000 | Abrahamson-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Boore-et al (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Campbell-Bozorgnia (2014) NGA West 2 USGS 2014 |
| 0.25 | 0.250000 | Chiou-Youngs (2014) NGA West 2 USGS 2014 |

**********

MAGNITUDE CONVERSIONS

This analysis does not require any magnitude conversions.
Note: Your analysis may indirectly use magnitude conversions that are not listed here.

Echo File Creation Time: 13:37:53 Monday, September 22, 2025

# APPENDIX D.3
# PROBABILISTIC RESULTS

Probabilistic Spectra results for EZ-FRISK 8.11 Build 019

ANNUAL FREQUENCY OF EXCEEDANCE: 2.107e-03
RETURN PERIOD: 474.6
PROBABILITY OF EXCEEDENCE: 10.0% IN 50.0 YEARS
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Mean
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 3.221e-02 | 3.542e-02 | 3.142e-02 | 3.253e-02 | 2.962e-02 |
| 0.05 | 4.864e-02 | 4.533e-02 | 4.809e-02 | 5.292e-02 | 4.798e-02 |
| 0.1 | 6.812e-02 | 6.553e-02 | 7.097e-02 | 7.013e-02 | 6.546e-02 |
| 0.2 | 6.633e-02 | 6.606e-02 | 6.668e-02 | 6.829e-02 | 6.413e-02 |
| 0.3 | 5.274e-02 | 5.281e-02 | 4.827e-02 | 5.902e-02 | 5.068e-02 |
| 0.4 | 4.168e-02 | 4.400e-02 | 3.698e-02 | 4.595e-02 | 4.001e-02 |
| 0.5 | 3.446e-02 | 3.807e-02 | 2.999e-02 | 3.716e-02 | 3.271e-02 |
| 0.75 | 2.402e-02 | 2.537e-02 | 2.134e-02 | 2.724e-02 | 2.190e-02 |
| 1 | 1.717e-02 | 1.862e-02 | 1.561e-02 | 1.891e-02 | 1.558e-02 |
| 2 | 7.695e-03 | 1.044e-02 | 6.584e-03 | 7.387e-03 | 6.514e-03 |
| 3 | 4.401e-03 | 5.989e-03 | 4.309e-03 | 4.002e-03 | 3.414e-03 |
| 4 | 3.004e-03 | 3.756e-03 | 3.351e-03 | 2.773e-03 | 2.148e-03 |

ANNUAL FREQUENCY OF EXCEEDANCE: 1.026e-03
RETURN PERIOD: 974.8
PROBABILITY OF EXCEEDENCE: 5.0% IN 50.0 YEARS
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Mean
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014

Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 5.520e-02 | 6.152e-02 | 5.269e-02 | 5.580e-02 | 5.090e-02 |
| 0.05 | 8.401e-02 | 7.893e-02 | 8.150e-02 | 9.218e-02 | 8.367e-02 |
| 0.1 | 1.180e-01 | 1.156e-01 | 1.186e-01 | 1.213e-01 | 1.162e-01 |
| 0.2 | 1.125e-01 | 1.152e-01 | 1.084e-01 | 1.144e-01 | 1.123e-01 |
| 0.3 | 8.747e-02 | 8.956e-02 | 7.714e-02 | 9.652e-02 | 8.686e-02 |
| 0.4 | 6.871e-02 | 7.258e-02 | 5.922e-02 | 7.467e-02 | 6.798e-02 |
| 0.5 | 5.636e-02 | 6.199e-02 | 4.778e-02 | 6.035e-02 | 5.483e-02 |
| 0.75 | 3.800e-02 | 4.053e-02 | 3.293e-02 | 4.298e-02 | 3.522e-02 |
| 1 | 2.696e-02 | 2.929e-02 | 2.427e-02 | 2.923e-02 | 2.481e-02 |
| 2 | 1.271e-02 | 1.661e-02 | 1.107e-02 | 1.220e-02 | 1.096e-02 |
| 3 | 7.598e-03 | 1.077e-02 | 7.301e-03 | 6.769e-03 | 5.531e-03 |
| 4 | 5.019e-03 | 6.658e-03 | 5.589e-03 | 4.553e-03 | 3.322e-03 |

ANNUAL FREQUENCY OF EXCEEDANCE: 4.041e-04
RETURN PERIOD: 2474.9
PROBABILITY OF EXCEEDENCE: 2.0% IN 50.0 YEARS
Column 1: Spectral Period
Column 2: Acceleration (g) for: Mean
Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 1.006e-01 | 1.121e-01 | 9.326e-02 | 1.012e-01 | 9.412e-02 |
| 0.05 | 1.553e-01 | 1.449e-01 | 1.469e-01 | 1.728e-01 | 1.570e-01 |
| 0.1 | 2.236e-01 | 2.215e-01 | 2.168e-01 | 2.304e-01 | 2.264e-01 |
| 0.2 | 2.091e-01 | 2.186e-01 | 1.924e-01 | 2.090e-01 | 2.167e-01 |

| | | | | | |
|---|---|---|---|---|---|
| 0.3 | 1.567e-01 | 1.622e-01 | 1.337e-01 | 1.678e-01 | 1.631e-01 |
| 0.4 | 1.212e-01 | 1.264e-01 | 1.028e-01 | 1.289e-01 | 1.257e-01 |
| 0.5 | 9.956e-02 | 1.068e-01 | 8.280e-02 | 1.048e-01 | 1.013e-01 |
| 0.75 | 6.687e-02 | 7.048e-02 | 5.733e-02 | 7.409e-02 | 6.409e-02 |
| 1 | 4.724e-02 | 5.157e-02 | 4.174e-02 | 5.090e-02 | 4.404e-02 |
| 2 | 2.197e-02 | 2.824e-02 | 1.870e-02 | 2.106e-02 | 1.849e-02 |
| 3 | 1.382e-02 | 1.864e-02 | 1.326e-02 | 1.257e-02 | 1.025e-02 |
| 4 | 9.757e-03 | 1.256e-02 | 1.065e-02 | 8.652e-03 | 5.844e-03 |

ANNUAL FREQUENCY OF EXCEEDANCE: 1.000e-04
RETURN PERIOD: 10000.0
PROBABILITY OF EXCEEDENCE: 0.5% IN 50.0 YEARS
  Column 1: Spectral Period
  Column 2: Acceleration (g) for: Mean
  Column 3: Acceleration (g) for: Abrahamson-et al (2014) NGA West 2 USGS 2014
  Column 4: Acceleration (g) for: Boore-et al (2014) NGA West 2 USGS 2014
  Column 5: Acceleration (g) for: Campbell-Bozorgnia (2014) NGA West 2 USGS 2014
  Column 6: Acceleration (g) for: Chiou-Youngs (2014) NGA West 2 USGS 2014

| 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|
| PGA | 2.096e-01 | 2.360e-01 | 1.893e-01 | 2.094e-01 | 2.013e-01 |
| 0.05 | 3.382e-01 | 3.129e-01 | 3.135e-01 | 3.834e-01 | 3.443e-01 |
| 0.1 | 4.875e-01 | 4.824e-01 | 4.564e-01 | 5.061e-01 | 5.047e-01 |
| 0.2 | 4.482e-01 | 4.756e-01 | 4.024e-01 | 4.322e-01 | 4.839e-01 |
| 0.3 | 3.359e-01 | 3.483e-01 | 2.839e-01 | 3.406e-01 | 3.666e-01 |
| 0.4 | 2.579e-01 | 2.634e-01 | 2.186e-01 | 2.635e-01 | 2.837e-01 |
| 0.5 | 2.097e-01 | 2.170e-01 | 1.770e-01 | 2.131e-01 | 2.264e-01 |
| 0.75 | 1.395e-01 | 1.407e-01 | 1.238e-01 | 1.489e-01 | 1.420e-01 |
| 1 | 1.009e-01 | 1.050e-01 | 9.197e-02 | 1.056e-01 | 9.857e-02 |
| 2 | 4.668e-02 | 5.845e-02 | 4.032e-02 | 4.488e-02 | 3.920e-02 |

| | | | | | |
|---|---|---|---|---|---|
| 3 | 2.922e-02 | 3.772e-02 | 2.850e-02 | 2.727e-02 | 2.085e-02 |
| 4 | 2.090e-02 | 2.569e-02 | 2.291e-02 | 1.954e-02 | 1.286e-02 |

# APPENDIX D
# Technical Memorandum – Frost Depth Analysis

# *Technical Memorandum*

| | | | |
|---|---|---|---|
| To: | Rio Grande Resources Ltd. | From: | Jason Andrews P.E.,<br>Larry Coons P.E. |
| Company: | Rio Grande Resources Ltd. | Date: | October 9, 2025 |
| EA No.: | 111360 | | |
| Re: | Mt. Taylor Uranium Mine<br>- Frost Depth Analysis | | |

## 1.0 INTRODUCTION

This technical memorandum provides the frost depth analysis and results to support the design of the proposed expanded disposal cell. The radon barrier should be located below the calculated frost depth to protect against freeze-thaw impacts.

## 2.0 FROST DEPTH ANALYSIS

The frost depth penetration into the final reclamation cover (cover) for the proposed expanded disposal cell was determined using the procedure adopted by the U.S. Department of Energy and accepted by the Nuclear Regulatory Commission (DOE, 1989). The depth of freezing into the cover (depth of frost penetration) is governed by the local climate, soil material and soil moisture content expected during the operational life of the cover. The procedure used includes a computational procedure to predict frost depth which was initially proposed by Berggren (1943). Smith and Rager (2002) apply these previous studies to determine an adequate thickness of a protective soil layer to protect underlying compacted soil. The freezing depth was calculated for a 200-year recurrence interval (0.5% probability of occurrence in any given year).

### 2.1 Analyzed Final Reclamation Cover Configuration

The following cover system is proposed to overlay the clay layer (radon barrier) and was analyzed for frost penetration. The proposed cover system is presented on Figure D-1.

- 12-inches of rock mulch (erosion protection) consisting of gravel mixed with onsite soil used as Soil Cover.
- 28-inches of onsite soil cover (biointrusion and frost protection.)

## 2.2 Input parameters

Calculations

- ***Step 1 Determine freeze-index parameters.***
  Fifty years of historic temperature data consisting of maximum and minimum daily air temperatures was obtained from Grants, New Mexico Municipal Airport for the main data source, additional alternative data sources included the on-site meteorological station at the Mt. Taylor Mine, and the historical weather records of San Mateo, New Mexico. The historic climate data sources and data used in the calculations are presented in Attachment D1.

  The degree day calculation was used to compute the duration of freeze. The duration of freeze is defined as length of time in days that the cumulative degree day is below freezing (Smith and Rager, 2002). The degree day, defined as the mean daily temperature minus 32 degrees Fahrenheit (freezing point of water) (Smith and Rager, 2002) was calculated and presented in Attachment D1. The cumulative degree-days versus the days in the freeze year are plotted. The cumulative degree day plots are provided in Attachment D2.1 and are used to determine the duration of freeze. The selection of points for the duration of freeze calculation is provided in Attachment D2.2

- ***Step 2 Determine surface temperature correction factor.***
  A surface correction factor, N, is applied to the daily temperature data used to correct for difference between air temperature and ground temperature. A surface correction factor of 0.7 for bare soil was chosen from Table 1 of Smith and Rager (2002).

- ***Step 3 Determine thermal properties.***
  Soil thermal properties: thermal conductivity, heat capacity, and latent heat of fusion are products of empirical relationships between the dry unit weight (pcf) and gravimetric moisture content (%). For the purpose of these calculations, the relationships presented by Bianchini and Gonzalez (2012) were used. The thermal conductivity, volumetric heat capacity and latent heat of fusion for each of the soil types for the respective layer are presented in Table 1 below. The thermal ratio and fusion parameter for each of the soil types are presented in Table 2 below. The parameters presented in Tables 1 and 2 were calculated with the following equations from Bianchini and Gonzalez (2012) presented below.

**Thermal conductivity equations:**

$$K_f = \frac{0.076(10)^{0.013\gamma_d} + 0.032(10)^{0.013\gamma_d * w}}{12}$$

$$K_u = \frac{(0.07\log(w) + 0.04)(10)^{0.01\gamma_d}}{12}$$

Where:

$K_u$ = Thermal Conductivity of unfrozen soil
$K_f$ = Thermal Conductivity of frozen soil
$\gamma_d$ = soil dry unit weight
$w$ = soil water content as percentage

**Volumetric heat capacity equation:**

$$C_{avg} = \gamma_d(c + 0.75\frac{w}{100})$$

Where:

$C_{avg}$ = Average volumetric heat capacity
$\gamma_d$ = soil dry unit weight
$w$ = soil water content as percentage
$c$ = specific heat of the soil solids

**Volumetric latent heat of fusion equation:**

$$L = 144\gamma_d\frac{w}{100}$$

Where:

L= Volumetric latent heat of fusion
$\gamma_d$ = soil dry unit weight
$w$ = soil water content as percentage

**Thermal ratio equation:**

$$\alpha = \frac{v_0}{v_s}$$

Where:

$\alpha$ = Thermal Ratio
$v_0$ =absolute value of the difference between the mean annual temperature below the ground surface and 32° F.
$v_s$ =the term is computed in two different ways in relation to problem analysis.

**Term $v_s$ equation:**

$$v_s = \frac{nF}{t}$$

Where:

$n$ = conversion factor from air index to surface index
$F$ = air-freezing index

$t$ = length of the freezing season

**Fusion parameter equation:**

$$\mu = \frac{C}{L} v_s$$

Where

$C$= Volumetric Heat Capacity
$L$ = Volumetric latent heat of fusion

**Table 1 – Thermal Properties**

| Layer | Depth (Inches) | Optimum Dry Density (PCF) | Water Content (%) | Dry Density (85% of Proctor) (PCF) | Thermal Conductivity Kf (BTU/ Ft hr °F) | Thermal Conductivity Ku (BTU/ Ft hr °F) | Average Thermal Conductivity (1/2*( Ku+Kf)) (BTU/ Ft hr °F) | Volumetric Heat Capacity (Cavg) (BTU/ft$^3$ °F) | Latent Heat of Fusion (BTU/ft$^3$) |
|---|---|---|---|---|---|---|---|---|---|
| Mulch | 12 | 115 | 10 | 97.8 | 0.83 | 0.87 | 0.85 | 23.9 | 1407.6 |
| Soil Cover | 33 | 110.7 | 11 | 94.1 | 0.80 | 0.82 | 0.81 | 23.8 | 1490.46 |

**Table 2 – Thermal Parameters**

| Layer | Average Temperature (°F) | Freeze Index (Degree-Day) | Duration (Days) | Vs | Vo | Thermal Ratio | Fusion Parameter |
|---|---|---|---|---|---|---|---|
| Mulch | 63.1 | 927.5 | 173 | 3.8 | 31.1 | 8.25 | 0.06 |
| Soil Cover | 63.1 | 927.5 | 173 | 3.8 | 31.1 | 8.25 | 0.06 |

- ***Step 4 Determine 200-year recurrence interval.***
  NRC, 10 CFR Appendix A to Part 40, Criterion 6, Paragraph 1 states that the design life should be 1,000 years when reasonably achievable and at a minimum, 200 years. As discussed in Smith and Rager (2002) the use of a 200-year recurrence interval for frost depth analysis meets the requirements of 40 Code of Federal Regulations Part 40. Mean annual temperature was calculated for each year in the data set. The mean annual temperature was plotted and projected to develop the mean minimum temperature for 200 years using the method presented in Smith and Rager (2002). The results of this are presented in Attachment D3.1.

  In addition to the mean annual temperature, the frost index and duration of freeze were calculated for each year in the data set as stated in Step 1. These data were plotted and projected to develop the 200-year maximum frost index and duration of freeze using the method presented in Smith and Rager (2002). The results are presented in Attachments D3.2 and D3.3, respectively.

- ***Step 5 Determine freezing depth.***
  To determine the frost depth of 200-year recurrence interval the method for manual solution of the Modberg Equation presented in Bianchini and Gonzalez (2012) was applied using the parameters calculated in Step 4 to determine the depth of the freezing front inside of the cover system. The depth of the freezing front is presented in Attachment D4.

## 3.0 CONCLUSIONS

The frost penetration depth into the final cover for the 200-year recurrence interval was calculated to be 28 inches. The total thickness of material over the radon barrier is proposed to be 40 inches. Thus, the radon barrier is not anticipated to experience any impacts from freezing.

## 4.0 REFERENCES

Berggren, W.P. (1943). Prediction of temperature distribution in frozen soils. *Proceedings of the 11th Annual Western Interstate Snow Survey Conference, Trans. Am. Geophys. Union*. 71-77.

Bianchini, A., and C.R. Gonzalez. (2012). *Pavement-Transportation Computer Assisted Structural Engineering (PCASE) Implementation of the Modified Berggren (ModBerg) Equation for Computing the Frost Penetration Depth within Pavement structures*. U.S. Army Corps of Engineers, Engineer Research and Development Center, Geotechnical and Structures Laboratory, ERDC/GSL TR-12-15.

Smith, G.E., and R.E. Rager. (2002). Protective layer design in landfill covers based on frost penetration. *ASCE J. Geotechnical/Geoenvironmental Engineering* 128(9): 794-799.

U.S. Department of Energy (U.S. DOE). (1989). *Technical Approach Document, Revision II, Uranium Mill Tailings Remedial Action Project*, UMTRA-DOE/AL 050425.0002, Albuquerque, New Mexico.


## LIST OF FIGURES

Figure D-1 Final Reclamation Cover System

## LIST OF ATTACHMENTS

Attachment D1 Historical Temperature Data
Attachment D2 Frost Index Calculations
Attachment D2.1 Cumulative Degree Day Plots
Attachment D2.2 Frost Index Determination
Attachment D3 Determination of Parameters at a 200-year Recurrence Interval
Attachment D3.1 Mean Annual Temperature at 200-year Recurrence Interval
Attachment D3.2 Frost Index at 200-year Recurrence Interval
Attachment D3.3 Duration of Freeze Season at 200-year Recurrence Interval
Attachment D4 Frost Depth Determination

**FIGURE**




NOT TO SCALE

T:\111360 Mt. Taylor\Reclamation Liner.dwg SAVED:8/21/25 PRINTED:8/25/25

Project No. 111360

October 2025

Engineering Analytics, Inc.

**FIGURE D-1**
**FINAL RECLAMATION COVER SYSTEM**
**MT. TAYLOR MINE**

# ATTACHMENT D1
# HISTORICAL TEMPERATURE DATA

**Attachment D1 - Summary of Historical Weather Data**

| Location | Site ID | Distance from Site | Elevation (Mt. Taylor, El 6454 ft) | Start Date | End Date | Missing Data? | Weather Categories Used | Notes |
|---|---|---|---|---|---|---|---|---|
| Gallup Municipal Airport, Gallup, NM. | KNMGA19 | 64 miles | 6467 ft | 1/1/1975 | 6/23/2023 | • 8/12/2000 – 8/21/2000<br>• 8/23/2000 – 8/26/2000<br>• 8/28/2000-8/30/2000<br>• 2/20/2007-2/25/2007<br>• 3/1/2014-3/3/2014<br>• 12/11/2022-01/23/2023<br>• 9/26/2023-9/30/2023<br>• 01/25/2024-01/28/2024<br>• 05/29/2025-06/04/2025 | • Temperature<br>• Relative Humidity<br>• Avg Daily Wind Speed<br>• Precipitation | • **Main data source**<br>• Gaps in data filled with Alternative data from Albuquerque, NM . |
| Albuquerque, NM. | KNMALBUQ1093) | 58 miles | 5312 ft | 2/20/2007 | 6/04/2025 | | • Temperature<br>• Relative Humidity<br>• Average Wind Speed<br>• Precipitation | • **Alternative data source**<br>• Used for 5/29/2025-6/4/2025<br>• 01/26/2025-01/28/2025<br>• 9/26/2025-9/30/2025<br>• 12/11/2022-01/23/2023 |

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| | | | | | | | | • 2/20/2007-2/25/2007<br>• 2/23/2000-2/28/2000<br>•<br>• |

111360 Mt. Taylor Uranium Mine | Grants, NM Municipal Airport Data

| Date | Year | MO | Day | Day in frost Year | Minimum Temperature (Deg F) | Maximum Temperature (Deg F) | Average Temperature (Deg F) | Degree Day | Cum. Degree Day |
|---|---|---|---|---|---|---|---|---|---|
| 6/1/1975 | 1975 | 6 | 1 | 1 | 38 | 80 | 59 | 27 | 27 |
| 6/2/1975 | 1975 | 6 | 2 | 2 | 42 | 83 | 62.5 | 30.5 | 57.5 |
| 6/3/1975 | 1975 | 6 | 3 | 3 | 48 | 84 | 66 | 34 | 91.5 |
| 6/4/1975 | 1975 | 6 | 4 | 4 | 49 | 82 | 65.5 | 33.5 | 125 |
| 6/5/1975 | 1975 | 6 | 5 | 5 | 45 | 83 | 64 | 32 | 157 |
| 6/6/1975 | 1975 | 6 | 6 | 6 | 47 | 81 | 64 | 32 | 189 |
| 6/7/1975 | 1975 | 6 | 7 | 7 | 50 | 80 | 65 | 33 | 222 |
| 6/8/1975 | 1975 | 6 | 8 | 8 | 48 | 79 | 63.5 | 31.5 | 253.5 |
| 6/9/1975 | 1975 | 6 | 9 | 9 | 43 | 77 | 60 | 28 | 281.5 |
| 6/10/1975 | 1975 | 6 | 10 | 10 | 36 | 77 | 56.5 | 24.5 | 306 |
| 6/11/1975 | 1975 | 6 | 11 | 11 | 35 | 75 | 55 | 23 | 329 |
| 6/12/1975 | 1975 | 6 | 12 | 12 | 40 | 80 | 60 | 28 | 357 |
| 6/13/1975 | 1975 | 6 | 13 | 13 | 43 | 86 | 64.5 | 32.5 | 389.5 |
| 6/14/1975 | 1975 | 6 | 14 | 14 | 51 | 85 | 68 | 36 | 425.5 |
| 6/15/1975 | 1975 | 6 | 15 | 15 | 50 | 80 | 65 | 33 | 458.5 |
| 6/16/1975 | 1975 | 6 | 16 | 16 | 51 | 84 | 67.5 | 35.5 | 494 |
| 6/17/1975 | 1975 | 6 | 17 | 17 | 53 | 84 | 68.5 | 36.5 | 530.5 |
| 6/18/1975 | 1975 | 6 | 18 | 18 | 52 | 81 | 66.5 | 34.5 | 565 |
| 6/19/1975 | 1975 | 6 | 19 | 19 | 43 | 77 | 60 | 28 | 593 |
| 6/20/1975 | 1975 | 6 | 20 | 20 | 45 | 74 | 59.5 | 27.5 | 620.5 |
| 6/21/1975 | 1975 | 6 | 21 | 21 | 43 | 79 | 61 | 29 | 649.5 |
| 6/22/1975 | 1975 | 6 | 22 | 22 | 46 | 84 | 65 | 33 | 682.5 |
| 6/23/1975 | 1975 | 6 | 23 | 23 | 48 | 84 | 66 | 34 | 716.5 |
| 6/24/1975 | 1975 | 6 | 24 | 24 | 52 | 84 | 68 | 36 | 752.5 |
| 6/25/1975 | 1975 | 6 | 25 | 25 | 43 | 83 | 63 | 31 | 783.5 |
| 6/26/1975 | 1975 | 6 | 26 | 26 | 48 | 85 | 66.5 | 34.5 | 818 |
| 6/27/1975 | 1975 | 6 | 27 | 27 | 49 | 85 | 67 | 35 | 853 |
| 6/28/1975 | 1975 | 6 | 28 | 28 | 49 | 88 | 68.5 | 36.5 | 889.5 |
| 6/29/1975 | 1975 | 6 | 29 | 29 | 52 | 90 | 71 | 39 | 928.5 |
| 6/30/1975 | 1975 | 6 | 30 | 30 | 53 | 91 | 72 | 40 | 968.5 |
| 7/1/1975 | 1975 | 7 | 1 | 31 | 59 | 90 | 74.5 | 42.5 | 1011 |
| 7/2/1975 | 1975 | 7 | 2 | 32 | 62 | 84 | 73 | 41 | 1052 |
| 7/3/1975 | 1975 | 7 | 3 | 33 | 53 | 82 | 67.5 | 35.5 | 1087.5 |
| 7/4/1975 | 1975 | 7 | 4 | 34 | 56 | 80 | 68 | 36 | 1123.5 |
| 7/5/1975 | 1975 | 7 | 5 | 35 | 54 | 85 | 69.5 | 37.5 | 1161 |
| 7/6/1975 | 1975 | 7 | 6 | 36 | 52 | 81 | 66.5 | 34.5 | 1195.5 |
| 7/7/1975 | 1975 | 7 | 7 | 37 | 51 | 78 | 64.5 | 32.5 | 1228 |
| 7/8/1975 | 1975 | 7 | 8 | 38 | 50 | 79 | 64.5 | 32.5 | 1260.5 |
| 7/9/1975 | 1975 | 7 | 9 | 39 | 54 | 80 | 67 | 35 | 1295.5 |
| 7/10/1975 | 1975 | 7 | 10 | 40 | 59 | 86 | 72.5 | 40.5 | 1336 |
| 7/11/1975 | 1975 | 7 | 11 | 41 | 56 | 81 | 68.5 | 36.5 | 1372.5 |
| 7/12/1975 | 1975 | 7 | 12 | 42 | 54 | 81 | 67.5 | 35.5 | 1408 |
| 7/13/1975 | 1975 | 7 | 13 | 43 | 52 | 79 | 65.5 | 33.5 | 1441.5 |
| 7/14/1975 | 1975 | 7 | 14 | 44 | 50 | 79 | 64.5 | 32.5 | 1474 |
| 7/15/1975 | 1975 | 7 | 15 | 45 | 49 | 80 | 64.5 | 32.5 | 1506.5 |
| 7/16/1975 | 1975 | 7 | 16 | 46 | 55 | 78 | 66.5 | 34.5 | 1541 |
| 7/17/1975 | 1975 | 7 | 17 | 47 | 52 | 76 | 64 | 32 | 1573 |
| 7/18/1975 | 1975 | 7 | 18 | 48 | 53 | 81 | 67 | 35 | 1608 |
| 7/19/1975 | 1975 | 7 | 19 | 49 | 56 | 84 | 70 | 38 | 1646 |
| 7/20/1975 | 1975 | 7 | 20 | 50 | 57 | 82 | 69.5 | 37.5 | 1683.5 |
| 7/21/1975 | 1975 | 7 | 21 | 51 | 50 | 84 | 67 | 35 | 1718.5 |
| 7/22/1975 | 1975 | 7 | 22 | 52 | 50 | 82 | 66 | 34 | 1752.5 |
| 7/23/1975 | 1975 | 7 | 23 | 53 | 53 | 87 | 70 | 38 | 1790.5 |
| 7/24/1975 | 1975 | 7 | 24 | 54 | 54 | 90 | 72 | 40 | 1830.5 |
| 7/25/1975 | 1975 | 7 | 25 | 55 | 49 | 86 | 67.5 | 35.5 | 1866 |
| 7/26/1975 | 1975 | 7 | 26 | 56 | 52 | 79 | 65.5 | 33.5 | 1899.5 |
| 7/27/1975 | 1975 | 7 | 27 | 57 | 53 | 78 | 65.5 | 33.5 | 1933 |
| 7/28/1975 | 1975 | 7 | 28 | 58 | 53 | 77 | 65 | 33 | 1966 |
| 7/29/1975 | 1975 | 7 | 29 | 59 | 50 | 70 | 60 | 28 | 1994 |
| 7/30/1975 | 1975 | 7 | 30 | 60 | 51 | 78 | 64.5 | 32.5 | 2026.5 |
| 7/31/1975 | 1975 | 7 | 31 | 61 | 53 | 80 | 66.5 | 34.5 | 2061 |
| 8/1/1975 | 1975 | 8 | 1 | 62 | 53 | 83 | 68 | 36 | 2097 |
| 8/2/1975 | 1975 | 8 | 2 | 63 | 55 | 84 | 69.5 | 37.5 | 2134.5 |
| 8/3/1975 | 1975 | 8 | 3 | 64 | 52 | 84 | 68 | 36 | 2170.5 |
| 8/4/1975 | 1975 | 8 | 4 | 65 | 51 | 85 | 68 | 36 | 2206.5 |
| 8/5/1975 | 1975 | 8 | 5 | 66 | 53 | 84 | 68.5 | 36.5 | 2243 |
| 8/6/1975 | 1975 | 8 | 6 | 67 | 56 | 85 | 70.5 | 38.5 | 2281.5 |
| 8/7/1975 | 1975 | 8 | 7 | 68 | 57 | 80 | 68.5 | 36.5 | 2318 |
| 8/8/1975 | 1975 | 8 | 8 | 69 | 56 | 80 | 68 | 36 | 2354 |
| 8/9/1975 | 1975 | 8 | 9 | 70 | 54 | 78 | 66 | 34 | 2388 |
| 8/10/1975 | 1975 | 8 | 10 | 71 | 53 | 77 | 65 | 33 | 2421 |
| 8/11/1975 | 1975 | 8 | 11 | 72 | 47 | 78 | 62.5 | 30.5 | 2451.5 |
| 8/12/1975 | 1975 | 8 | 12 | 73 | 53 | 76 | 64.5 | 32.5 | 2484 |
| 8/13/1975 | 1975 | 8 | 13 | 74 | 49 | 73 | 61 | 29 | 2513 |
| 8/14/1975 | 1975 | 8 | 14 | 75 | 50 | 79 | 64.5 | 32.5 | 2545.5 |
| 8/15/1975 | 1975 | 8 | 15 | 76 | 50 | 83 | 66.5 | 34.5 | 2580 |
| 8/16/1975 | 1975 | 8 | 16 | 77 | 55 | 84 | 69.5 | 37.5 | 2617.5 |
| 8/17/1975 | 1975 | 8 | 17 | 78 | 50 | 82 | 66 | 34 | 2651.5 |
| 8/18/1975 | 1975 | 8 | 18 | 79 | 55 | 83 | 69 | 37 | 2688.5 |
| 8/19/1975 | 1975 | 8 | 19 | 80 | 50 | 82 | 66 | 34 | 2722.5 |
| 8/20/1975 | 1975 | 8 | 20 | 81 | 53 | 79 | 66 | 34 | 2756.5 |
| 8/21/1975 | 1975 | 8 | 21 | 82 | 54 | 70 | 62 | 30 | 2786.5 |
| 8/22/1975 | 1975 | 8 | 22 | 83 | 53 | 77 | 65 | 33 | 2819.5 |
| 8/23/1975 | 1975 | 8 | 23 | 84 | 51 | 73 | 62 | 30 | 2849.5 |
| 8/24/1975 | 1975 | 8 | 24 | 85 | 53 | 87 | 70 | 38 | 2887.5 |
| 8/25/1975 | 1975 | 8 | 25 | 86 | 48 | 83 | 65.5 | 33.5 | 2921 |
| 8/26/1975 | 1975 | 8 | 26 | 87 | 47 | 82 | 64.5 | 32.5 | 2953.5 |
| 8/27/1975 | 1975 | 8 | 27 | 88 | 56 | 81 | 68.5 | 36.5 | 2990 |
| 8/28/1975 | 1975 | 8 | 28 | 89 | 49 | 81 | 65 | 33 | 3023 |
| 8/29/1975 | 1975 | 8 | 29 | 90 | 51 | 83 | 67 | 35 | 3058 |
| 8/30/1975 | 1975 | 8 | 30 | 91 | 50 | 80 | 65 | 33 | 3091 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/31/1975 | 1975 | 8 | 31 | 92 | 51 | 81 | 66 | 34 | 3125 |
| 9/1/1975 | 1975 | 9 | 1 | 93 | 50 | 85 | 67.5 | 35.5 | 3160.5 |
| 9/2/1975 | 1975 | 9 | 2 | 94 | 54 | 79 | 66.5 | 34.5 | 3195 |
| 9/3/1975 | 1975 | 9 | 3 | 95 | 53 | 78 | 65.5 | 33.5 | 3228.5 |
| 9/4/1975 | 1975 | 9 | 4 | 96 | 54 | 73 | 63.5 | 31.5 | 3260 |
| 9/5/1975 | 1975 | 9 | 5 | 97 | 49 | 69 | 59 | 27 | 3287 |
| 9/6/1975 | 1975 | 9 | 6 | 98 | 50 | 63 | 56.5 | 24.5 | 3311.5 |
| 9/7/1975 | 1975 | 9 | 7 | 99 | 50 | 69 | 59.5 | 27.5 | 3339 |
| 9/8/1975 | 1975 | 9 | 8 | 100 | 50 | 73 | 61.5 | 29.5 | 3368.5 |
| 9/9/1975 | 1975 | 9 | 9 | 101 | 43 | 62 | 52.5 | 20.5 | 3389 |
| 9/10/1975 | 1975 | 9 | 10 | 102 | 42 | 61 | 51.5 | 19.5 | 3408.5 |
| 9/11/1975 | 1975 | 9 | 11 | 103 | 40 | 69 | 54.5 | 22.5 | 3431 |
| 9/12/1975 | 1975 | 9 | 12 | 104 | 40 | 59 | 49.5 | 17.5 | 3448.5 |
| 9/13/1975 | 1975 | 9 | 13 | 105 | 43 | 67 | 55 | 23 | 3471.5 |
| 9/14/1975 | 1975 | 9 | 14 | 106 | 44 | 69 | 56.5 | 24.5 | 3496 |
| 9/15/1975 | 1975 | 9 | 15 | 107 | 42 | 69 | 55.5 | 23.5 | 3519.5 |
| 9/16/1975 | 1975 | 9 | 16 | 108 | 46 | 70 | 58 | 26 | 3545.5 |
| 9/17/1975 | 1975 | 9 | 17 | 109 | 48 | 73 | 60.5 | 28.5 | 3574 |
| 9/18/1975 | 1975 | 9 | 18 | 110 | 50 | 73 | 61.5 | 29.5 | 3603.5 |
| 9/19/1975 | 1975 | 9 | 19 | 111 | 46 | 73 | 59.5 | 27.5 | 3631 |
| 9/20/1975 | 1975 | 9 | 20 | 112 | 45 | 72 | 58.5 | 26.5 | 3657.5 |
| 9/21/1975 | 1975 | 9 | 21 | 113 | 40 | 72 | 56 | 24 | 3681.5 |
| 9/22/1975 | 1975 | 9 | 22 | 114 | 40 | 70 | 55 | 23 | 3704.5 |
| 9/23/1975 | 1975 | 9 | 23 | 115 | 42 | 69 | 55.5 | 23.5 | 3728 |
| 9/24/1975 | 1975 | 9 | 24 | 116 | 41 | 68 | 54.5 | 22.5 | 3750.5 |
| 9/25/1975 | 1975 | 9 | 25 | 117 | 40 | 69 | 54.5 | 22.5 | 3773 |
| 9/26/1975 | 1975 | 9 | 26 | 118 | 42 | 70 | 56 | 24 | 3797 |
| 9/27/1975 | 1975 | 9 | 27 | 119 | 43 | 70 | 56.5 | 24.5 | 3821.5 |
| 9/28/1975 | 1975 | 9 | 28 | 120 | 40 | 69 | 54.5 | 22.5 | 3844 |
| 9/29/1975 | 1975 | 9 | 29 | 121 | 41 | 68 | 54.5 | 22.5 | 3866.5 |
| 9/30/1975 | 1975 | 9 | 30 | 122 | 40 | 69 | 54.5 | 22.5 | 3889 |
| 10/1/1975 | 1975 | 10 | 1 | 123 | 36 | 76 | 56 | 24 | 3913 |
| 10/2/1975 | 1975 | 10 | 2 | 124 | 39 | 71 | 55 | 23 | 3936 |
| 10/3/1975 | 1975 | 10 | 3 | 125 | 41 | 72 | 56.5 | 24.5 | 3960.5 |
| 10/4/1975 | 1975 | 10 | 4 | 126 | 42 | 68 | 55 | 23 | 3983.5 |
| 10/5/1975 | 1975 | 10 | 5 | 127 | 42 | 72 | 57 | 25 | 4008.5 |
| 10/6/1975 | 1975 | 10 | 6 | 128 | 42 | 78 | 60 | 28 | 4036.5 |
| 10/7/1975 | 1975 | 10 | 7 | 129 | 48 | 73 | 60.5 | 28.5 | 4065 |
| 10/8/1975 | 1975 | 10 | 8 | 130 | 41 | 69 | 55 | 23 | 4088 |
| 10/9/1975 | 1975 | 10 | 9 | 131 | 37 | 70 | 53.5 | 21.5 | 4109.5 |
| 10/10/1975 | 1975 | 10 | 10 | 132 | 40 | 69 | 54.5 | 22.5 | 4132 |
| 10/11/1975 | 1975 | 10 | 11 | 133 | 41 | 70 | 55.5 | 23.5 | 4155.5 |
| 10/12/1975 | 1975 | 10 | 12 | 134 | 39 | 69 | 54 | 22 | 4177.5 |
| 10/13/1975 | 1975 | 10 | 13 | 135 | 40 | 68 | 54 | 22 | 4199.5 |
| 10/14/1975 | 1975 | 10 | 14 | 136 | 29 | 56 | 42.5 | 10.5 | 4210 |
| 10/15/1975 | 1975 | 10 | 15 | 137 | 25 | 52 | 38.5 | 6.5 | 4216.5 |
| 10/16/1975 | 1975 | 10 | 16 | 138 | 30 | 66 | 48 | 16 | 4232.5 |
| 10/17/1975 | 1975 | 10 | 17 | 139 | 35 | 66 | 50.5 | 18.5 | 4251 |
| 10/18/1975 | 1975 | 10 | 18 | 140 | 37 | 69 | 53 | 21 | 4272 |
| 10/19/1975 | 1975 | 10 | 19 | 141 | 40 | 68 | 54 | 22 | 4294 |
| 10/20/1975 | 1975 | 10 | 20 | 142 | 40 | 68 | 54 | 22 | 4316 |
| 10/21/1975 | 1975 | 10 | 21 | 143 | 35 | 66 | 50.5 | 18.5 | 4334.5 |
| 10/22/1975 | 1975 | 10 | 22 | 144 | 34 | 62 | 48 | 16 | 4350.5 |
| 10/23/1975 | 1975 | 10 | 23 | 145 | 35 | 61 | 48 | 16 | 4366.5 |
| 10/24/1975 | 1975 | 10 | 24 | 146 | 15 | 44 | 29.5 | -2.5 | 4364 |
| 10/25/1975 | 1975 | 10 | 25 | 147 | 17 | 60 | 38.5 | 6.5 | 4370.5 |
| 10/26/1975 | 1975 | 10 | 26 | 148 | 28 | 59 | 43.5 | 11.5 | 4382 |
| 10/27/1975 | 1975 | 10 | 27 | 149 | 29 | 60 | 44.5 | 12.5 | 4394.5 |
| 10/28/1975 | 1975 | 10 | 28 | 150 | 34 | 65 | 60.5 | 28.5 | 4423 |
| 10/29/1975 | 1975 | 10 | 29 | 151 | 33 | 69 | 51 | 19 | 4442 |
| 10/30/1975 | 1975 | 10 | 30 | 152 | 41 | 68 | 54.5 | 22.5 | 4464.5 |
| 10/31/1975 | 1975 | 10 | 31 | 153 | 40 | 61 | 50.5 | 18.5 | 4483 |
| 11/1/1975 | 1975 | 11 | 1 | 154 | 30 | 53 | 41.5 | 9.5 | 4492.5 |
| 11/2/1975 | 1975 | 11 | 2 | 155 | 32 | 58 | 45 | 13 | 4505.5 |
| 11/3/1975 | 1975 | 11 | 3 | 156 | 30 | 61 | 45.5 | 13.5 | 4519 |
| 11/4/1975 | 1975 | 11 | 4 | 157 | 34 | 60 | 47 | 15 | 4534 |
| 11/5/1975 | 1975 | 11 | 5 | 158 | 30 | 69 | 49.5 | 17.5 | 4551.5 |
| 11/6/1975 | 1975 | 11 | 6 | 159 | 32 | 64 | 48 | 16 | 4567.5 |
| 11/7/1975 | 1975 | 11 | 7 | 160 | 31 | 67 | 49 | 17 | 4584.5 |
| 11/8/1975 | 1975 | 11 | 8 | 161 | 33 | 65 | 49 | 17 | 4601.5 |
| 11/9/1975 | 1975 | 11 | 9 | 162 | 32 | 60 | 46 | 14 | 4615.5 |
| 11/10/1975 | 1975 | 11 | 10 | 163 | 23 | 64 | 43.5 | 11.5 | 4627 |
| 11/11/1975 | 1975 | 11 | 11 | 164 | 27 | 58 | 42.5 | 10.5 | 4637.5 |
| 11/12/1975 | 1975 | 11 | 12 | 165 | 19 | 53 | 36 | 4 | 4641.5 |
| 11/13/1975 | 1975 | 11 | 13 | 166 | 18 | 58 | 38 | 6 | 4647.5 |
| 11/14/1975 | 1975 | 11 | 14 | 167 | 17 | 69 | 43 | 11 | 4658.5 |
| 11/15/1975 | 1975 | 11 | 15 | 168 | 19 | 68 | 43.5 | 11.5 | 4670 |
| 11/16/1975 | 1975 | 11 | 16 | 169 | 15 | 71 | 43 | 11 | 4681 |
| 11/17/1975 | 1975 | 11 | 17 | 170 | 10 | 67 | 38.5 | 6.5 | 4687.5 |
| 11/18/1975 | 1975 | 11 | 18 | 171 | 11 | 58 | 34.5 | 2.5 | 4690 |
| 11/19/1975 | 1975 | 11 | 19 | 172 | 20 | 44 | 32 | 0 | 4690 |
| 11/20/1975 | 1975 | 11 | 20 | 173 | 10 | 45 | 27.5 | -4.5 | 4685.5 |
| 11/21/1975 | 1975 | 11 | 21 | 174 | 9 | 45 | 27 | -5 | 4680.5 |
| 11/22/1975 | 1975 | 11 | 22 | 175 | 10 | 45 | 27.5 | -4.5 | 4676 |
| 11/23/1975 | 1975 | 11 | 23 | 176 | 12 | 56 | 34 | 2 | 4678 |
| 11/24/1975 | 1975 | 11 | 24 | 177 | 19 | 54 | 36.5 | 4.5 | 4682.5 |
| 11/25/1975 | 1975 | 11 | 25 | 178 | 18 | 47 | 32.5 | 0.5 | 4683 |
| 11/26/1975 | 1975 | 11 | 26 | 179 | 4 | 44 | 24 | -8 | 4675 |
| 11/27/1975 | 1975 | 11 | 27 | 180 | 10 | 56 | 33 | 1 | 4676 |
| 11/28/1975 | 1975 | 11 | 28 | 181 | 29 | 55 | 42 | 10 | 4686 |
| 11/29/1975 | 1975 | 11 | 29 | 182 | 10 | 37 | 23.5 | -8.5 | 4677.5 |
| 11/30/1975 | 1975 | 11 | 30 | 183 | 1 | 36 | 18.5 | -13.5 | 4664 |
| 12/1/1975 | 1975 | 12 | 1 | 184 | 8 | 44 | 26 | -6 | 4658 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/2/1975 | 1975 | 12 | 2 | 185 | 10 | 46 | 28 | -4 | 4654 |
| 12/3/1975 | 1975 | 12 | 3 | 186 | 19 | 39 | 29 | -3 | 4651 |
| 12/4/1975 | 1975 | 12 | 4 | 187 | 18 | 40 | 29 | -3 | 4648 |
| 12/5/1975 | 1975 | 12 | 5 | 188 | 17 | 45 | 31 | -1 | 4647 |
| 12/6/1975 | 1975 | 12 | 6 | 189 | 20 | 46 | 33 | 1 | 4648 |
| 12/7/1975 | 1975 | 12 | 7 | 190 | 19 | 50 | 34.5 | 2.5 | 4650.5 |
| 12/8/1975 | 1975 | 12 | 8 | 191 | 20 | 50 | 35 | 3 | 4653.5 |
| 12/9/1975 | 1975 | 12 | 9 | 192 | 19 | 56 | 37.5 | 5.5 | 4659 |
| 12/10/1975 | 1975 | 12 | 10 | 193 | 27 | 46 | 36.5 | 4.5 | 4663.5 |
| 12/11/1975 | 1975 | 12 | 11 | 194 | 23 | 50 | 36.5 | 4.5 | 4668 |
| 12/12/1975 | 1975 | 12 | 12 | 195 | 24 | 52 | 38 | 6 | 4674 |
| 12/13/1975 | 1975 | 12 | 13 | 196 | 6 | 44 | 25 | -7 | 4667 |
| 12/14/1975 | 1975 | 12 | 14 | 197 | 6 | 25 | 15.5 | -16.5 | 4650.5 |
| 12/15/1975 | 1975 | 12 | 15 | 198 | 8 | 39 | 23.5 | -8.5 | 4642 |
| 12/16/1975 | 1975 | 12 | 16 | 199 | 12 | 49 | 30.5 | -1.5 | 4640.5 |
| 12/17/1975 | 1975 | 12 | 17 | 200 | 17 | 45 | 31 | -1 | 4639.5 |
| 12/18/1975 | 1975 | 12 | 18 | 201 | 16 | 46 | 31 | -1 | 4638.5 |
| 12/19/1975 | 1975 | 12 | 19 | 202 | 18 | 51 | 34.5 | 2.5 | 4641 |
| 12/20/1975 | 1975 | 12 | 20 | 203 | 18 | 40 | 29 | -3 | 4638 |
| 12/21/1975 | 1975 | 12 | 21 | 204 | 17 | 37 | 27 | -5 | 4633 |
| 12/22/1975 | 1975 | 12 | 22 | 205 | 18 | 36 | 27 | -5 | 4628 |
| 12/23/1975 | 1975 | 12 | 23 | 206 | 7 | 32 | 19.5 | -12.5 | 4615.5 |
| 12/24/1975 | 1975 | 12 | 24 | 207 | 8 | 31 | 19.5 | -12.5 | 4603 |
| 12/25/1975 | 1975 | 12 | 25 | 208 | 6 | 30 | 18 | -14 | 4589 |
| 12/26/1975 | 1975 | 12 | 26 | 209 | 11 | 39 | 25 | -7 | 4582 |
| 12/27/1975 | 1975 | 12 | 27 | 210 | 10 | 40 | 25 | -7 | 4575 |
| 12/28/1975 | 1975 | 12 | 28 | 211 | 14 | 36 | 25 | -7 | 4568 |
| 12/29/1975 | 1975 | 12 | 29 | 212 | 8 | 26 | 17 | -15 | 4553 |
| 12/30/1975 | 1975 | 12 | 30 | 213 | 10 | 30 | 20 | -12 | 4541 |
| 12/31/1975 | 1975 | 12 | 31 | 214 | 11 | 36 | 23.5 | -8.5 | 4532.5 |
| 1/1/1976 | 1976 | 1 | 1 | 215 | 0 | 23 | 11.5 | -20.5 | 4512 |
| 1/2/1976 | 1976 | 1 | 2 | 216 | 0 | 20 | 10 | -22 | 4490 |
| 1/3/1976 | 1976 | 1 | 3 | 217 | 5 | 30 | 17.5 | -14.5 | 4475.5 |
| 1/4/1976 | 1976 | 1 | 4 | 218 | -10 | 33 | 11.5 | -20.5 | 4455 |
| 1/5/1976 | 1976 | 1 | 5 | 219 | -5 | 39 | 17 | -15 | 4440 |
| 1/6/1976 | 1976 | 1 | 6 | 220 | 5 | 39 | 22 | -10 | 4430 |
| 1/7/1976 | 1976 | 1 | 7 | 221 | 6 | 40 | 23 | -9 | 4421 |
| 1/8/1976 | 1976 | 1 | 8 | 222 | 10 | 34 | 22 | -10 | 4411 |
| 1/9/1976 | 1976 | 1 | 9 | 223 | 17 | 44 | 30.5 | -1.5 | 4409.5 |
| 1/10/1976 | 1976 | 1 | 10 | 224 | 27 | 43 | 35 | 3 | 4412.5 |
| 1/11/1976 | 1976 | 1 | 11 | 225 | 13 | 39 | 26 | -6 | 4406.5 |
| 1/12/1976 | 1976 | 1 | 12 | 226 | 18 | 40 | 29 | -3 | 4403.5 |
| 1/13/1976 | 1976 | 1 | 13 | 227 | 17 | 40 | 28.5 | -3.5 | 4400 |
| 1/14/1976 | 1976 | 1 | 14 | 228 | 16 | 40 | 28 | -4 | 4396 |
| 1/15/1976 | 1976 | 1 | 15 | 229 | 21 | 41 | 31 | -1 | 4395 |
| 1/16/1976 | 1976 | 1 | 16 | 230 | 22 | 40 | 31 | -1 | 4394 |
| 1/17/1976 | 1976 | 1 | 17 | 231 | 20 | 42 | 31 | -1 | 4393 |
| 1/18/1976 | 1976 | 1 | 18 | 232 | 26 | 48 | 37 | 5 | 4398 |
| 1/19/1976 | 1976 | 1 | 19 | 233 | 25 | 47 | 36 | 4 | 4402 |
| 1/20/1976 | 1976 | 1 | 20 | 234 | 13 | 43 | 28 | -4 | 4398 |
| 1/21/1976 | 1976 | 1 | 21 | 235 | 14 | 49 | 31.5 | -0.5 | 4397.5 |
| 1/22/1976 | 1976 | 1 | 22 | 236 | 21 | 48 | 34.5 | 2.5 | 4400 |
| 1/23/1976 | 1976 | 1 | 23 | 237 | 26 | 49 | 37.5 | 5.5 | 4405.5 |
| 1/24/1976 | 1976 | 1 | 24 | 238 | 25 | 44 | 34.5 | 2.5 | 4408 |
| 1/25/1976 | 1976 | 1 | 25 | 239 | 24 | 43 | 33.5 | 1.5 | 4409.5 |
| 1/26/1976 | 1976 | 1 | 26 | 240 | 0 | 32 | 16 | -16 | 4393.5 |
| 1/27/1976 | 1976 | 1 | 27 | 241 | 6 | 36 | 21 | -11 | 4382.5 |
| 1/28/1976 | 1976 | 1 | 28 | 242 | 10 | 35 | 22.5 | -9.5 | 4373 |
| 1/29/1976 | 1976 | 1 | 29 | 243 | 15 | 40 | 27.5 | -4.5 | 4368.5 |
| 1/30/1976 | 1976 | 1 | 30 | 244 | 17 | 44 | 30.5 | -1.5 | 4367 |
| 1/31/1976 | 1976 | 1 | 31 | 245 | 20 | 48 | 34 | 2 | 4369 |
| 2/1/1976 | 1976 | 2 | 1 | 246 | 19 | 57 | 38 | 6 | 4375 |
| 2/2/1976 | 1976 | 2 | 2 | 247 | 24 | 51 | 37.5 | 5.5 | 4380.5 |
| 2/3/1976 | 1976 | 2 | 3 | 248 | 26 | 52 | 39 | 7 | 4387.5 |
| 2/4/1976 | 1976 | 2 | 4 | 249 | 32 | 46 | 39 | 7 | 4394.5 |
| 2/5/1976 | 1976 | 2 | 5 | 250 | 36 | 49 | 42.5 | 10.5 | 4405 |
| 2/6/1976 | 1976 | 2 | 6 | 251 | 35 | 44 | 39.5 | 7.5 | 4412.5 |
| 2/7/1976 | 1976 | 2 | 7 | 252 | 26 | 50 | 38 | 6 | 4418.5 |
| 2/8/1976 | 1976 | 2 | 8 | 253 | 29 | 59 | 44 | 12 | 4430.5 |
| 2/9/1976 | 1976 | 2 | 9 | 254 | 20 | 56 | 38 | 6 | 4436.5 |
| 2/10/1976 | 1976 | 2 | 10 | 255 | 23 | 52 | 37.5 | 5.5 | 4442 |
| 2/11/1976 | 1976 | 2 | 11 | 256 | 26 | 48 | 37 | 5 | 4447 |
| 2/12/1976 | 1976 | 2 | 12 | 257 | 30 | 57 | 43.5 | 11.5 | 4458.5 |
| 2/13/1976 | 1976 | 2 | 13 | 258 | 30 | 59 | 44.5 | 12.5 | 4471 |
| 2/14/1976 | 1976 | 2 | 14 | 259 | 30 | 42 | 36 | 4 | 4475 |
| 2/15/1976 | 1976 | 2 | 15 | 260 | 29 | 41 | 35 | 3 | 4478 |
| 2/16/1976 | 1976 | 2 | 16 | 261 | 20 | 40 | 30 | -2 | 4476 |
| 2/17/1976 | 1976 | 2 | 17 | 262 | 20 | 41 | 30.5 | -1.5 | 4474.5 |
| 2/18/1976 | 1976 | 2 | 18 | 263 | 21 | 39 | 30 | -2 | 4472.5 |
| 2/19/1976 | 1976 | 2 | 19 | 264 | 24 | 50 | 37 | 5 | 4477.5 |
| 2/20/1976 | 1976 | 2 | 20 | 265 | 17 | 50 | 33.5 | 1.5 | 4479 |
| 2/21/1976 | 1976 | 2 | 21 | 266 | 25 | 37 | 31 | -1 | 4478 |
| 2/22/1976 | 1976 | 2 | 22 | 267 | 12 | 39 | 25.5 | -6.5 | 4471.5 |
| 2/23/1976 | 1976 | 2 | 23 | 268 | 19 | 42 | 30.5 | -1.5 | 4470 |
| 2/24/1976 | 1976 | 2 | 24 | 269 | 19 | 49 | 34 | 2 | 4472 |
| 2/25/1976 | 1976 | 2 | 25 | 270 | 22 | 50 | 36 | 4 | 4476 |
| 2/26/1976 | 1976 | 2 | 26 | 271 | 20 | 56 | 38 | 6 | 4482 |
| 2/27/1976 | 1976 | 2 | 27 | 272 | 19 | 56 | 37.5 | 5.5 | 4487.5 |
| 2/28/1976 | 1976 | 2 | 28 | 273 | 27 | 64 | 45.5 | 13.5 | 4501 |
| 2/29/1976 | 1976 | 2 | 29 | 274 | 30 | 55 | 42.5 | 10.5 | 4511.5 |
| 3/1/1976 | 1976 | 3 | 1 | 275 | 29 | 60 | 44.5 | 12.5 | 4524 |
| 3/2/1976 | 1976 | 3 | 2 | 276 | 30 | 50 | 40 | 8 | 4532 |
| 3/3/1976 | 1976 | 3 | 3 | 277 | 25 | 55 | 40 | 8 | 4540 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/4/1976 | 1976 | 3 | 4 | 278 | 0 | 46 | 23 | -9 | 4531 |
| 3/5/1976 | 1976 | 3 | 5 | 279 | 1 | 45 | 23 | -9 | 4522 |
| 3/6/1976 | 1976 | 3 | 6 | 280 | 0 | 40 | 20 | -12 | 4510 |
| 3/7/1976 | 1976 | 3 | 7 | 281 | 3 | 39 | 21 | -11 | 4499 |
| 3/8/1976 | 1976 | 3 | 8 | 282 | 4 | 35 | 19.5 | -12.5 | 4486.5 |
| 3/9/1976 | 1976 | 3 | 9 | 283 | 4 | 32 | 18 | -14 | 4472.5 |
| 3/10/1976 | 1976 | 3 | 10 | 284 | 9 | 36 | 22.5 | -9.5 | 4463 |
| 3/11/1976 | 1976 | 3 | 11 | 285 | 10 | 40 | 25 | -7 | 4456 |
| 3/12/1976 | 1976 | 3 | 12 | 286 | 26 | 49 | 37.5 | 5.5 | 4461.5 |
| 3/13/1976 | 1976 | 3 | 13 | 287 | 29 | 45 | 37 | 5 | 4466.5 |
| 3/14/1976 | 1976 | 3 | 14 | 288 | 27 | 44 | 35.5 | 3.5 | 4470 |
| 3/15/1976 | 1976 | 3 | 15 | 289 | 13 | 38 | 25.5 | -6.5 | 4463.5 |
| 3/16/1976 | 1976 | 3 | 16 | 290 | 12 | 39 | 25.5 | -6.5 | 4457 |
| 3/17/1976 | 1976 | 3 | 17 | 291 | 22 | 40 | 31 | -1 | 4456 |
| 3/18/1976 | 1976 | 3 | 18 | 292 | 23 | 45 | 34 | 2 | 4458 |
| 3/19/1976 | 1976 | 3 | 19 | 293 | 29 | 46 | 37.5 | 5.5 | 4463.5 |
| 3/20/1976 | 1976 | 3 | 20 | 294 | 30 | 49 | 39.5 | 7.5 | 4471 |
| 3/21/1976 | 1976 | 3 | 21 | 295 | 12 | 50 | 31 | -1 | 4470 |
| 3/22/1976 | 1976 | 3 | 22 | 296 | 15 | 50 | 32.5 | 0.5 | 4470.5 |
| 3/23/1976 | 1976 | 3 | 23 | 297 | 20 | 50 | 35 | 3 | 4473.5 |
| 3/24/1976 | 1976 | 3 | 24 | 298 | 23 | 54 | 38.5 | 6.5 | 4480 |
| 3/25/1976 | 1976 | 3 | 25 | 299 | 37 | 50 | 43.5 | 11.5 | 4491.5 |
| 3/26/1976 | 1976 | 3 | 26 | 300 | 32 | 56 | 44 | 12 | 4503.5 |
| 3/27/1976 | 1976 | 3 | 27 | 301 | 25 | 59 | 42 | 10 | 4513.5 |
| 3/28/1976 | 1976 | 3 | 28 | 302 | 20 | 56 | 38 | 6 | 4519.5 |
| 3/29/1976 | 1976 | 3 | 29 | 303 | 19 | 36 | 27.5 | -4.5 | 4515 |
| 3/30/1976 | 1976 | 3 | 30 | 304 | 15 | 40 | 27.5 | -4.5 | 4510.5 |
| 3/31/1976 | 1976 | 3 | 31 | 305 | 23 | 45 | 34 | 2 | 4512.5 |
| 4/1/1976 | 1976 | 4 | 1 | 306 | 29 | 66 | 47.5 | 15.5 | 4528 |
| 4/2/1976 | 1976 | 4 | 2 | 307 | 39 | 65 | 52 | 20 | 4548 |
| 4/3/1976 | 1976 | 4 | 3 | 308 | 34 | 61 | 47.5 | 15.5 | 4563.5 |
| 4/4/1976 | 1976 | 4 | 4 | 309 | 20 | 58 | 39 | 7 | 4570.5 |
| 4/5/1976 | 1976 | 4 | 5 | 310 | 20 | 50 | 35 | 3 | 4573.5 |
| 4/6/1976 | 1976 | 4 | 6 | 311 | 19 | 51 | 35 | 3 | 4576.5 |
| 4/7/1976 | 1976 | 4 | 7 | 312 | 18 | 56 | 37 | 5 | 4581.5 |
| 4/8/1976 | 1976 | 4 | 8 | 313 | 17 | 48 | 32.5 | 0.5 | 4582 |
| 4/9/1976 | 1976 | 4 | 9 | 314 | 30 | 50 | 40 | 8 | 4590 |
| 4/10/1976 | 1976 | 4 | 10 | 315 | 32 | 59 | 45.5 | 13.5 | 4603.5 |
| 4/11/1976 | 1976 | 4 | 11 | 316 | 35 | 59 | 47 | 15 | 4618.5 |
| 4/12/1976 | 1976 | 4 | 12 | 317 | 34 | 60 | 47 | 15 | 4633.5 |
| 4/13/1976 | 1976 | 4 | 13 | 318 | 38 | 69 | 53.5 | 21.5 | 4655 |
| 4/14/1976 | 1976 | 4 | 14 | 319 | 43 | 66 | 54.5 | 22.5 | 4677.5 |
| 4/15/1976 | 1976 | 4 | 15 | 320 | 40 | 60 | 50 | 18 | 4695.5 |
| 4/16/1976 | 1976 | 4 | 16 | 321 | 39 | 57 | 48 | 16 | 4711.5 |
| 4/17/1976 | 1976 | 4 | 17 | 322 | 30 | 59 | 44.5 | 12.5 | 4724 |
| 4/18/1976 | 1976 | 4 | 18 | 323 | 20 | 45 | 32.5 | 0.5 | 4724.5 |
| 4/19/1976 | 1976 | 4 | 19 | 324 | 20 | 40 | 30 | -2 | 4722.5 |
| 4/20/1976 | 1976 | 4 | 20 | 325 | 19 | 42 | 30.5 | -1.5 | 4721 |
| 4/21/1976 | 1976 | 4 | 21 | 326 | 18 | 49 | 33.5 | 1.5 | 4722.5 |
| 4/22/1976 | 1976 | 4 | 22 | 327 | 27 | 60 | 43.5 | 11.5 | 4734 |
| 4/23/1976 | 1976 | 4 | 23 | 328 | 41 | 69 | 55 | 23 | 4757 |
| 4/24/1976 | 1976 | 4 | 24 | 329 | 42 | 67 | 54.5 | 22.5 | 4779.5 |
| 4/25/1976 | 1976 | 4 | 25 | 330 | 38 | 69 | 53.5 | 21.5 | 4801 |
| 4/26/1976 | 1976 | 4 | 26 | 331 | 33 | 70 | 51.5 | 19.5 | 4820.5 |
| 4/27/1976 | 1976 | 4 | 27 | 332 | 41 | 69 | 55 | 23 | 4843.5 |
| 4/28/1976 | 1976 | 4 | 28 | 333 | 39 | 69 | 54 | 22 | 4865.5 |
| 4/29/1976 | 1976 | 4 | 29 | 334 | 36 | 69 | 52.5 | 20.5 | 4886 |
| 4/30/1976 | 1976 | 4 | 30 | 335 | 42 | 68 | 55 | 23 | 4909 |
| 5/1/1976 | 1976 | 5 | 1 | 336 | 26 | 69 | 47.5 | 15.5 | 4924.5 |
| 5/2/1976 | 1976 | 5 | 2 | 337 | 35 | 70 | 52.5 | 20.5 | 4945 |
| 5/3/1976 | 1976 | 5 | 3 | 338 | 42 | 72 | 57 | 25 | 4970 |
| 5/4/1976 | 1976 | 5 | 4 | 339 | 41 | 64 | 52.5 | 20.5 | 4990.5 |
| 5/5/1976 | 1976 | 5 | 5 | 340 | 40 | 66 | 53 | 21 | 5011.5 |
| 5/6/1976 | 1976 | 5 | 6 | 341 | 30 | 65 | 47.5 | 15.5 | 5027 |
| 5/7/1976 | 1976 | 5 | 7 | 342 | 39 | 64 | 51.5 | 19.5 | 5046.5 |
| 5/8/1976 | 1976 | 5 | 8 | 343 | 30 | 51 | 40.5 | 8.5 | 5055 |
| 5/9/1976 | 1976 | 5 | 9 | 344 | 31 | 68 | 49.5 | 17.5 | 5072.5 |
| 5/10/1976 | 1976 | 5 | 10 | 345 | 32 | 69 | 50.5 | 18.5 | 5091 |
| 5/11/1976 | 1976 | 5 | 11 | 346 | 30 | 68 | 49 | 17 | 5108 |
| 5/12/1976 | 1976 | 5 | 12 | 347 | 40 | 70 | 55 | 23 | 5131 |
| 5/13/1976 | 1976 | 5 | 13 | 348 | 39 | 74 | 56.5 | 24.5 | 5155.5 |
| 5/14/1976 | 1976 | 5 | 14 | 349 | 42 | 79 | 60.5 | 28.5 | 5184 |
| 5/15/1976 | 1976 | 5 | 15 | 350 | 48 | 80 | 64 | 32 | 5216 |
| 5/16/1976 | 1976 | 5 | 16 | 351 | 44 | 80 | 62 | 30 | 5246 |
| 5/17/1976 | 1976 | 5 | 17 | 352 | 40 | 79 | 59.5 | 27.5 | 5273.5 |
| 5/18/1976 | 1976 | 5 | 18 | 353 | 45 | 79 | 62 | 30 | 5303.5 |
| 5/19/1976 | 1976 | 5 | 19 | 354 | 42 | 74 | 58 | 26 | 5329.5 |
| 5/20/1976 | 1976 | 5 | 20 | 355 | 43 | 70 | 56.5 | 24.5 | 5354 |
| 5/21/1976 | 1976 | 5 | 21 | 356 | 42 | 70 | 56 | 24 | 5378 |
| 5/22/1976 | 1976 | 5 | 22 | 357 | 44 | 69 | 56.5 | 24.5 | 5402.5 |
| 5/23/1976 | 1976 | 5 | 23 | 358 | 42 | 70 | 56 | 24 | 5426.5 |
| 5/24/1976 | 1976 | 5 | 24 | 359 | 47 | 75 | 61 | 29 | 5455.5 |
| 5/25/1976 | 1976 | 5 | 25 | 360 | 42 | 74 | 58 | 26 | 5481.5 |
| 5/26/1976 | 1976 | 5 | 26 | 361 | 40 | 72 | 56 | 24 | 5505.5 |
| 5/27/1976 | 1976 | 5 | 27 | 362 | 42 | 70 | 56 | 24 | 5529.5 |
| 5/28/1976 | 1976 | 5 | 28 | 363 | 42 | 70 | 56 | 24 | 5553.5 |
| 5/29/1976 | 1976 | 5 | 29 | 364 | 51 | 79 | 65 | 33 | 5586.5 |
| 5/30/1976 | 1976 | 5 | 30 | 365 | 49 | 80 | 64.5 | 32.5 | 5619 |
| 5/31/1976 | 1976 | 5 | 31 | 366 | 47 | 76 | 61.5 | 29.5 | 5648.5 |
| 6/1/1976 | 1976 | 6 | 1 | 1 | 42 | 84 | 63 | 31 | 31 |
| 6/2/1976 | 1976 | 6 | 2 | 2 | 51 | 84 | 67.5 | 35.5 | 66.5 |
| 6/3/1976 | 1976 | 6 | 3 | 3 | 53 | 84 | 68.5 | 36.5 | 103 |
| 6/4/1976 | 1976 | 6 | 4 | 4 | 50 | 85 | 67.5 | 35.5 | 138.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/5/1976 | 1976 | 6 | 5 | 5 | 48 | 85 | 66.5 | 34.5 | 173 |
| 6/6/1976 | 1976 | 6 | 6 | 6 | 48 | 76 | 62 | 30 | 203 |
| 6/7/1976 | 1976 | 6 | 7 | 7 | 53 | 82 | 67.5 | 35.5 | 238.5 |
| 6/8/1976 | 1976 | 6 | 8 | 8 | 44 | 83 | 63.5 | 31.5 | 270 |
| 6/9/1976 | 1976 | 6 | 9 | 9 | 49 | 82 | 65.5 | 33.5 | 303.5 |
| 6/10/1976 | 1976 | 6 | 10 | 10 | 48 | 82 | 65 | 33 | 336.5 |
| 6/11/1976 | 1976 | 6 | 11 | 11 | 51 | 83 | 67 | 35 | 371.5 |
| 6/12/1976 | 1976 | 6 | 12 | 12 | 43 | 80 | 61.5 | 29.5 | 401 |
| 6/13/1976 | 1976 | 6 | 13 | 13 | 40 | 80 | 60 | 28 | 429 |
| 6/14/1976 | 1976 | 6 | 14 | 14 | 45 | 81 | 63 | 31 | 460 |
| 6/15/1976 | 1976 | 6 | 15 | 15 | 45 | 74 | 59.5 | 27.5 | 487.5 |
| 6/16/1976 | 1976 | 6 | 16 | 16 | 44 | 75 | 59.5 | 27.5 | 515 |
| 6/17/1976 | 1976 | 6 | 17 | 17 | 40 | 80 | 60 | 28 | 543 |
| 6/18/1976 | 1976 | 6 | 18 | 18 | 56 | 81 | 68.5 | 36.5 | 579.5 |
| 6/19/1976 | 1976 | 6 | 19 | 19 | 49 | 84 | 66.5 | 34.5 | 614 |
| 6/20/1976 | 1976 | 6 | 20 | 20 | 48 | 87 | 67.5 | 35.5 | 649.5 |
| 6/21/1976 | 1976 | 6 | 21 | 21 | 54 | 89 | 71.5 | 39.5 | 689 |
| 6/22/1976 | 1976 | 6 | 22 | 22 | 59 | 84 | 71.5 | 39.5 | 728.5 |
| 6/23/1976 | 1976 | 6 | 23 | 23 | 41 | 78 | 59.5 | 27.5 | 756 |
| 6/24/1976 | 1976 | 6 | 24 | 24 | 45 | 79 | 62 | 30 | 786 |
| 6/25/1976 | 1976 | 6 | 25 | 25 | 49 | 79 | 64 | 32 | 818 |
| 6/26/1976 | 1976 | 6 | 26 | 26 | 50 | 79 | 64.5 | 32.5 | 850.5 |
| 6/27/1976 | 1976 | 6 | 27 | 27 | 52 | 89 | 70.5 | 38.5 | 889 |
| 6/28/1976 | 1976 | 6 | 28 | 28 | 53 | 90 | 71.5 | 39.5 | 928.5 |
| 6/29/1976 | 1976 | 6 | 29 | 29 | 56 | 89 | 72.5 | 40.5 | 969 |
| 6/30/1976 | 1976 | 6 | 30 | 30 | 61 | 84 | 72.5 | 40.5 | 1009.5 |
| 7/1/1976 | 1976 | 7 | 1 | 31 | 55 | 84 | 69.5 | 37.5 | 1047 |
| 7/2/1976 | 1976 | 7 | 2 | 32 | 57 | 86 | 71.5 | 39.5 | 1086.5 |
| 7/3/1976 | 1976 | 7 | 3 | 33 | 55 | 90 | 72.5 | 40.5 | 1127 |
| 7/4/1976 | 1976 | 7 | 4 | 34 | 58 | 90 | 74 | 42 | 1169 |
| 7/5/1976 | 1976 | 7 | 5 | 35 | 53 | 91 | 72 | 40 | 1209 |
| 7/6/1976 | 1976 | 7 | 6 | 36 | 56 | 88 | 72 | 40 | 1249 |
| 7/7/1976 | 1976 | 7 | 7 | 37 | 55 | 89 | 72 | 40 | 1289 |
| 7/8/1976 | 1976 | 7 | 8 | 38 | 56 | 91 | 73.5 | 41.5 | 1330.5 |
| 7/9/1976 | 1976 | 7 | 9 | 39 | 57 | 90 | 73.5 | 41.5 | 1372 |
| 7/10/1976 | 1976 | 7 | 10 | 40 | 58 | 90 | 74 | 42 | 1414 |
| 7/11/1976 | 1976 | 7 | 11 | 41 | 57 | 90 | 73.5 | 41.5 | 1455.5 |
| 7/12/1976 | 1976 | 7 | 12 | 42 | 52 | 85 | 68.5 | 36.5 | 1492 |
| 7/13/1976 | 1976 | 7 | 13 | 43 | 55 | 85 | 70 | 38 | 1530 |
| 7/14/1976 | 1976 | 7 | 14 | 44 | 52 | 85 | 68.5 | 36.5 | 1566.5 |
| 7/15/1976 | 1976 | 7 | 15 | 45 | 53 | 86 | 69.5 | 37.5 | 1604 |
| 7/16/1976 | 1976 | 7 | 16 | 46 | 56 | 86 | 71 | 39 | 1643 |
| 7/17/1976 | 1976 | 7 | 17 | 47 | 56 | 82 | 69 | 37 | 1680 |
| 7/18/1976 | 1976 | 7 | 18 | 48 | 57 | 83 | 70 | 38 | 1718 |
| 7/19/1976 | 1976 | 7 | 19 | 49 | 56 | 84 | 70 | 38 | 1756 |
| 7/20/1976 | 1976 | 7 | 20 | 50 | 57 | 80 | 68.5 | 36.5 | 1792.5 |
| 7/21/1976 | 1976 | 7 | 21 | 51 | 50 | 79 | 64.5 | 32.5 | 1825 |
| 7/22/1976 | 1976 | 7 | 22 | 52 | 52 | 80 | 66 | 34 | 1859 |
| 7/23/1976 | 1976 | 7 | 23 | 53 | 56 | 72 | 64 | 32 | 1891 |
| 7/24/1976 | 1976 | 7 | 24 | 54 | 51 | 81 | 66 | 34 | 1925 |
| 7/25/1976 | 1976 | 7 | 25 | 55 | 52 | 76 | 64 | 32 | 1957 |
| 7/26/1976 | 1976 | 7 | 26 | 56 | 52 | 78 | 65 | 33 | 1990 |
| 7/27/1976 | 1976 | 7 | 27 | 57 | 51 | 81 | 66 | 34 | 2024 |
| 7/28/1976 | 1976 | 7 | 28 | 58 | 50 | 76 | 63 | 31 | 2055 |
| 7/29/1976 | 1976 | 7 | 29 | 59 | 52 | 77 | 64.5 | 32.5 | 2087.5 |
| 7/30/1976 | 1976 | 7 | 30 | 60 | 54 | 86 | 70 | 38 | 2125.5 |
| 7/31/1976 | 1976 | 7 | 31 | 61 | 53.5 | 70 | 61.75 | 29.75 | 2155.25 |
| 8/1/1976 | 1976 | 8 | 1 | 62 | 53 | 66 | 59.5 | 27.5 | 2182.75 |
| 8/2/1976 | 1976 | 8 | 2 | 63 | 49 | 80 | 64.5 | 32.5 | 2215.25 |
| 8/3/1976 | 1976 | 8 | 3 | 64 | 50 | 76 | 63 | 31 | 2246.25 |
| 8/4/1976 | 1976 | 8 | 4 | 65 | 46 | 68 | 57 | 25 | 2271.25 |
| 8/5/1976 | 1976 | 8 | 5 | 66 | 48 | 81 | 64.5 | 32.5 | 2303.75 |
| 8/6/1976 | 1976 | 8 | 6 | 67 | 49 | 82 | 65.5 | 33.5 | 2337.25 |
| 8/7/1976 | 1976 | 8 | 7 | 68 | 58 | 85 | 71.5 | 39.5 | 2376.75 |
| 8/8/1976 | 1976 | 8 | 8 | 69 | 50 | 72 | 61 | 29 | 2405.75 |
| 8/9/1976 | 1976 | 8 | 9 | 70 | 51 | 73 | 62 | 30 | 2435.75 |
| 8/10/1976 | 1976 | 8 | 10 | 71 | 52 | 80 | 66 | 34 | 2469.75 |
| 8/11/1976 | 1976 | 8 | 11 | 72 | 50 | 82 | 66 | 34 | 2503.75 |
| 8/12/1976 | 1976 | 8 | 12 | 73 | 54 | 85 | 69.5 | 37.5 | 2541.25 |
| 8/13/1976 | 1976 | 8 | 13 | 74 | 55 | 87 | 71 | 39 | 2580.25 |
| 8/14/1976 | 1976 | 8 | 14 | 75 | 52 | 83 | 67.5 | 35.5 | 2615.75 |
| 8/15/1976 | 1976 | 8 | 15 | 76 | 53 | 82 | 67.5 | 35.5 | 2651.25 |
| 8/16/1976 | 1976 | 8 | 16 | 77 | 49 | 83 | 66 | 34 | 2685.25 |
| 8/17/1976 | 1976 | 8 | 17 | 78 | 60 | 79 | 69.5 | 37.5 | 2722.75 |
| 8/18/1976 | 1976 | 8 | 18 | 79 | 52 | 69 | 60.5 | 28.5 | 2751.25 |
| 8/19/1976 | 1976 | 8 | 19 | 80 | 53 | 70 | 61.5 | 29.5 | 2780.75 |
| 8/20/1976 | 1976 | 8 | 20 | 81 | 52 | 74 | 63 | 31 | 2811.75 |
| 8/21/1976 | 1976 | 8 | 21 | 82 | 51 | 83 | 67 | 35 | 2846.75 |
| 8/22/1976 | 1976 | 8 | 22 | 83 | 54 | 82 | 68 | 36 | 2882.75 |
| 8/23/1976 | 1976 | 8 | 23 | 84 | 52 | 81 | 66.5 | 34.5 | 2917.25 |
| 8/24/1976 | 1976 | 8 | 24 | 85 | 50 | 79 | 64.5 | 32.5 | 2949.75 |
| 8/25/1976 | 1976 | 8 | 25 | 86 | 49 | 81 | 65 | 33 | 2982.75 |
| 8/26/1976 | 1976 | 8 | 26 | 87 | 54 | 83 | 68.5 | 36.5 | 3019.25 |
| 8/27/1976 | 1976 | 8 | 27 | 88 | 53 | 78 | 65.5 | 33.5 | 3052.75 |
| 8/28/1976 | 1976 | 8 | 28 | 89 | 51 | 77 | 64 | 32 | 3084.75 |
| 8/29/1976 | 1976 | 8 | 29 | 90 | 47 | 79 | 63 | 31 | 3115.75 |
| 8/30/1976 | 1976 | 8 | 30 | 91 | 47 | 79 | 63 | 31 | 3146.75 |
| 8/31/1976 | 1976 | 8 | 31 | 92 | 50 | 80 | 65 | 33 | 3179.75 |
| 9/1/1976 | 1976 | 9 | 1 | 93 | 49 | 78 | 63.5 | 31.5 | 3211.25 |
| 9/2/1976 | 1976 | 9 | 2 | 94 | 45 | 75 | 60 | 28 | 3239.25 |
| 9/3/1976 | 1976 | 9 | 3 | 95 | 48 | 84 | 66 | 34 | 3273.25 |
| 9/4/1976 | 1976 | 9 | 4 | 96 | 54 | 83 | 68.5 | 36.5 | 3309.75 |
| 9/5/1976 | 1976 | 9 | 5 | 97 | 52 | 81 | 66.5 | 34.5 | 3344.25 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/6/1976 | 1976 | 9 | 6 | 98 | 55 | 73 | 64 | 32 | 3376.25 |
| 9/7/1976 | 1976 | 9 | 7 | 99 | 51 | 74 | 62.5 | 30.5 | 3406.75 |
| 9/8/1976 | 1976 | 9 | 8 | 100 | 52 | 76 | 64 | 32 | 3438.75 |
| 9/9/1976 | 1976 | 9 | 9 | 101 | 53 | 74 | 63.5 | 31.5 | 3470.25 |
| 9/10/1976 | 1976 | 9 | 10 | 102 | 49 | 67 | 58 | 26 | 3496.25 |
| 9/11/1976 | 1976 | 9 | 11 | 103 | 42 | 69 | 55.5 | 23.5 | 3519.75 |
| 9/12/1976 | 1976 | 9 | 12 | 104 | 46 | 75 | 60.5 | 28.5 | 3548.25 |
| 9/13/1976 | 1976 | 9 | 13 | 105 | 47 | 79 | 63 | 31 | 3579.25 |
| 9/14/1976 | 1976 | 9 | 14 | 106 | 52 | 78 | 65 | 33 | 3612.25 |
| 9/15/1976 | 1976 | 9 | 15 | 107 | 50 | 77 | 63.5 | 31.5 | 3643.75 |
| 9/16/1976 | 1976 | 9 | 16 | 108 | 49 | 76 | 62.5 | 30.5 | 3674.25 |
| 9/17/1976 | 1976 | 9 | 17 | 109 | 48 | 75 | 61.5 | 29.5 | 3703.75 |
| 9/18/1976 | 1976 | 9 | 18 | 110 | 49 | 70 | 59.5 | 27.5 | 3731.25 |
| 9/19/1976 | 1976 | 9 | 19 | 111 | 48 | 71 | 59.5 | 27.5 | 3758.75 |
| 9/20/1976 | 1976 | 9 | 20 | 112 | 45 | 70 | 57.5 | 25.5 | 3784.25 |
| 9/21/1976 | 1976 | 9 | 21 | 113 | 46 | 76 | 61 | 29 | 3813.25 |
| 9/22/1976 | 1976 | 9 | 22 | 114 | 44 | 67 | 55.5 | 23.5 | 3836.75 |
| 9/23/1976 | 1976 | 9 | 23 | 115 | 43 | 72 | 57.5 | 25.5 | 3862.25 |
| 9/24/1976 | 1976 | 9 | 24 | 116 | 48 | 67 | 57.5 | 25.5 | 3887.75 |
| 9/25/1976 | 1976 | 9 | 25 | 117 | 46 | 65 | 55.5 | 23.5 | 3911.25 |
| 9/26/1976 | 1976 | 9 | 26 | 118 | 45 | 64 | 54.5 | 22.5 | 3933.75 |
| 9/27/1976 | 1976 | 9 | 27 | 119 | 42 | 61 | 51.5 | 19.5 | 3953.25 |
| 9/28/1976 | 1976 | 9 | 28 | 120 | 35 | 65 | 50 | 18 | 3971.25 |
| 9/29/1976 | 1976 | 9 | 29 | 121 | 40 | 70 | 55 | 23 | 3994.25 |
| 9/30/1976 | 1976 | 9 | 30 | 122 | 41 | 74 | 57.5 | 25.5 | 4019.75 |
| 10/1/1976 | 1976 | 10 | 1 | 123 | 45 | 69 | 57 | 25 | 4044.75 |
| 10/2/1976 | 1976 | 10 | 2 | 124 | 51 | 65 | 58 | 26 | 4070.75 |
| 10/3/1976 | 1976 | 10 | 3 | 125 | 43 | 64 | 53.5 | 21.5 | 4092.25 |
| 10/4/1976 | 1976 | 10 | 4 | 126 | 36 | 66 | 51 | 19 | 4111.25 |
| 10/5/1976 | 1976 | 10 | 5 | 127 | 38 | 67 | 52.5 | 20.5 | 4131.75 |
| 10/6/1976 | 1976 | 10 | 6 | 128 | 30 | 64 | 47 | 15 | 4146.75 |
| 10/7/1976 | 1976 | 10 | 7 | 129 | 28 | 66 | 47 | 15 | 4161.75 |
| 10/8/1976 | 1976 | 10 | 8 | 130 | 34 | 69 | 51.5 | 19.5 | 4181.25 |
| 10/9/1976 | 1976 | 10 | 9 | 131 | 39 | 75 | 57 | 25 | 4206.25 |
| 10/10/1976 | 1976 | 10 | 10 | 132 | 36 | 74 | 55 | 23 | 4229.25 |
| 10/11/1976 | 1976 | 10 | 11 | 133 | 39 | 69 | 54 | 22 | 4251.25 |
| 10/12/1976 | 1976 | 10 | 12 | 134 | 37 | 67 | 52 | 20 | 4271.25 |
| 10/13/1976 | 1976 | 10 | 13 | 135 | 35 | 68 | 51.5 | 19.5 | 4290.75 |
| 10/14/1976 | 1976 | 10 | 14 | 136 | 36 | 67 | 51.5 | 19.5 | 4310.25 |
| 10/15/1976 | 1976 | 10 | 15 | 137 | 38 | 61 | 49.5 | 17.5 | 4327.75 |
| 10/16/1976 | 1976 | 10 | 16 | 138 | 25 | 50 | 37.5 | 5.5 | 4333.25 |
| 10/17/1976 | 1976 | 10 | 17 | 139 | 24 | 52 | 38 | 6 | 4339.25 |
| 10/18/1976 | 1976 | 10 | 18 | 140 | 23 | 59 | 41 | 9 | 4348.25 |
| 10/19/1976 | 1976 | 10 | 19 | 141 | 26 | 60 | 43 | 11 | 4359.25 |
| 10/20/1976 | 1976 | 10 | 20 | 142 | 30 | 58 | 44 | 12 | 4371.25 |
| 10/21/1976 | 1976 | 10 | 21 | 143 | 30 | 60 | 45 | 13 | 4384.25 |
| 10/22/1976 | 1976 | 10 | 22 | 144 | 34 | 59 | 46.5 | 14.5 | 4398.75 |
| 10/23/1976 | 1976 | 10 | 23 | 145 | 36 | 55 | 45.5 | 13.5 | 4412.25 |
| 10/24/1976 | 1976 | 10 | 24 | 146 | 29 | 57 | 43 | 11 | 4423.25 |
| 10/25/1976 | 1976 | 10 | 25 | 147 | 28 | 55 | 41.5 | 9.5 | 4432.75 |
| 10/26/1976 | 1976 | 10 | 26 | 148 | 24 | 41 | 32.5 | 0.5 | 4433.25 |
| 10/27/1976 | 1976 | 10 | 27 | 149 | 27 | 39 | 72.5 | 40.5 | 4473.75 |
| 10/28/1976 | 1976 | 10 | 28 | 150 | 22 | 49 | 35.5 | 3.5 | 4477.25 |
| 10/29/1976 | 1976 | 10 | 29 | 151 | 28 | 58 | 43 | 11 | 4488.25 |
| 10/30/1976 | 1976 | 10 | 30 | 152 | 28 | 56 | 42 | 10 | 4498.25 |
| 10/31/1976 | 1976 | 10 | 31 | 153 | 27 | 52 | 39.5 | 7.5 | 4505.75 |
| 11/1/1976 | 1976 | 11 | 1 | 154 | 23 | 59 | 41 | 9 | 4514.75 |
| 11/2/1976 | 1976 | 11 | 2 | 155 | 29 | 56 | 42.5 | 10.5 | 4525.25 |
| 11/3/1976 | 1976 | 11 | 3 | 156 | 30 | 60 | 45 | 13 | 4538.25 |
| 11/4/1976 | 1976 | 11 | 4 | 157 | 29 | 60 | 44.5 | 12.5 | 4550.75 |
| 11/5/1976 | 1976 | 11 | 5 | 158 | 31 | 62 | 46.5 | 14.5 | 4565.25 |
| 11/6/1976 | 1976 | 11 | 6 | 159 | 30 | 64 | 47 | 15 | 4580.25 |
| 11/7/1976 | 1976 | 11 | 7 | 160 | 29 | 66 | 47.5 | 15.5 | 4595.75 |
| 11/8/1976 | 1976 | 11 | 8 | 161 | 30 | 60 | 45 | 13 | 4608.75 |
| 11/9/1976 | 1976 | 11 | 9 | 162 | 25 | 65 | 45 | 13 | 4621.75 |
| 11/10/1976 | 1976 | 11 | 10 | 163 | 32 | 63 | 47.5 | 15.5 | 4637.25 |
| 11/11/1976 | 1976 | 11 | 11 | 164 | 30 | 57 | 43.5 | 11.5 | 4648.75 |
| 11/12/1976 | 1976 | 11 | 12 | 165 | 25 | 48 | 36.5 | 4.5 | 4653.25 |
| 11/13/1976 | 1976 | 11 | 13 | 166 | 25 | 44 | 34.5 | 2.5 | 4655.75 |
| 11/14/1976 | 1976 | 11 | 14 | 167 | 20 | 48 | 34 | 2 | 4657.75 |
| 11/15/1976 | 1976 | 11 | 15 | 168 | 20 | 40 | 30 | -2 | 4655.75 |
| 11/16/1976 | 1976 | 11 | 16 | 169 | 11 | 40 | 25.5 | -6.5 | 4649.25 |
| 11/17/1976 | 1976 | 11 | 17 | 170 | 22 | 52 | 37 | 5 | 4654.25 |
| 11/18/1976 | 1976 | 11 | 18 | 171 | 19 | 51 | 35 | 3 | 4657.25 |
| 11/19/1976 | 1976 | 11 | 19 | 172 | 26 | 57 | 41.5 | 9.5 | 4666.75 |
| 11/20/1976 | 1976 | 11 | 20 | 173 | 27 | 56 | 41.5 | 9.5 | 4676.25 |
| 11/21/1976 | 1976 | 11 | 21 | 174 | 31 | 59 | 45 | 13 | 4689.25 |
| 11/22/1976 | 1976 | 11 | 22 | 175 | 28 | 56 | 42 | 10 | 4699.25 |
| 11/23/1976 | 1976 | 11 | 23 | 176 | 26 | 49 | 37.5 | 5.5 | 4704.75 |
| 11/24/1976 | 1976 | 11 | 24 | 177 | 28 | 50 | 39 | 7 | 4711.75 |
| 11/25/1976 | 1976 | 11 | 25 | 178 | 25 | 50 | 37.5 | 5.5 | 4717.25 |
| 11/26/1976 | 1976 | 11 | 26 | 179 | 29 | 48 | 38.5 | 6.5 | 4723.75 |
| 11/27/1976 | 1976 | 11 | 27 | 180 | -9 | 32 | 11.5 | -20.5 | 4703.25 |
| 11/28/1976 | 1976 | 11 | 28 | 181 | -10 | 32 | 11 | -21 | 4682.25 |
| 11/29/1976 | 1976 | 11 | 29 | 182 | -9 | 30 | 10.5 | -21.5 | 4660.75 |
| 11/30/1976 | 1976 | 11 | 30 | 183 | 7 | 32 | 19.5 | -12.5 | 4648.25 |
| 12/1/1976 | 1976 | 12 | 1 | 184 | 9 | 34 | 21.5 | -10.5 | 4637.75 |
| 12/2/1976 | 1976 | 12 | 2 | 185 | 8 | 35 | 21.5 | -10.5 | 4627.25 |
| 12/3/1976 | 1976 | 12 | 3 | 186 | 12 | 39 | 25.5 | -6.5 | 4620.75 |
| 12/4/1976 | 1976 | 12 | 4 | 187 | 0 | 38 | 19 | -13 | 4607.75 |
| 12/5/1976 | 1976 | 12 | 5 | 188 | -2 | 19 | 8.5 | -23.5 | 4584.25 |
| 12/6/1976 | 1976 | 12 | 6 | 189 | 10 | 22 | 16 | -16 | 4568.25 |
| 12/7/1976 | 1976 | 12 | 7 | 190 | 12 | 30 | 21 | -11 | 4557.25 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/8/1976 | 1976 | 12 | 8 | 191 | 12 | 36 | 24 | -8 | 4549.25 |
| 12/9/1976 | 1976 | 12 | 9 | 192 | 23 | 40 | 31.5 | -0.5 | 4548.75 |
| 12/10/1976 | 1976 | 12 | 10 | 193 | 9 | 40 | 24.5 | -7.5 | 4541.25 |
| 12/11/1976 | 1976 | 12 | 11 | 194 | 8 | 32 | 20 | -12 | 4529.25 |
| 12/12/1976 | 1976 | 12 | 12 | 195 | 8 | 39 | 23.5 | -8.5 | 4520.75 |
| 12/13/1976 | 1976 | 12 | 13 | 196 | 9 | 38 | 23.5 | -8.5 | 4512.25 |
| 12/14/1976 | 1976 | 12 | 14 | 197 | 10 | 35 | 22.5 | -9.5 | 4502.75 |
| 12/15/1976 | 1976 | 12 | 15 | 198 | 13 | 36 | 24.5 | -7.5 | 4495.25 |
| 12/16/1976 | 1976 | 12 | 16 | 199 | 12 | 39 | 25.5 | -6.5 | 4488.75 |
| 12/17/1976 | 1976 | 12 | 17 | 200 | 16 | 35 | 25.5 | -6.5 | 4482.25 |
| 12/18/1976 | 1976 | 12 | 18 | 201 | 17 | 37 | 27 | -5 | 4477.25 |
| 12/19/1976 | 1976 | 12 | 19 | 202 | 10 | 39 | 24.5 | -7.5 | 4469.75 |
| 12/20/1976 | 1976 | 12 | 20 | 203 | 11 | 34 | 22.5 | -9.5 | 4460.25 |
| 12/21/1976 | 1976 | 12 | 21 | 204 | 12 | 39 | 25.5 | -6.5 | 4453.75 |
| 12/22/1976 | 1976 | 12 | 22 | 205 | 12 | 40 | 26 | -6 | 4447.75 |
| 12/23/1976 | 1976 | 12 | 23 | 206 | 11 | 34 | 22.5 | -9.5 | 4438.25 |
| 12/24/1976 | 1976 | 12 | 24 | 207 | 10 | 37 | 23.5 | -8.5 | 4429.75 |
| 12/25/1976 | 1976 | 12 | 25 | 208 | 10 | 36 | 23 | -9 | 4420.75 |
| 12/26/1976 | 1976 | 12 | 26 | 209 | 11 | 35 | 23 | -9 | 4411.75 |
| 12/27/1976 | 1976 | 12 | 27 | 210 | 8 | 32 | 20 | -12 | 4399.75 |
| 12/28/1976 | 1976 | 12 | 28 | 211 | 9 | 33 | 21 | -11 | 4388.75 |
| 12/29/1976 | 1976 | 12 | 29 | 212 | 10 | 30 | 20 | -12 | 4376.75 |
| 12/30/1976 | 1976 | 12 | 30 | 213 | 11 | 32 | 21.5 | -10.5 | 4366.25 |
| 12/31/1976 | 1976 | 12 | 31 | 214 | 11 | 32 | 21.5 | -10.5 | 4355.75 |
| 1/1/1977 | 1977 | 1 | 1 | 215 | 11 | 30 | 20.5 | -11.5 | 4344.25 |
| 1/2/1977 | 1977 | 1 | 2 | 216 | 10 | 39 | 24.5 | -7.5 | 4336.75 |
| 1/3/1977 | 1977 | 1 | 3 | 217 | 11 | 36 | 23.5 | -8.5 | 4328.25 |
| 1/4/1977 | 1977 | 1 | 4 | 218 | 11 | 30 | 20.5 | -11.5 | 4316.75 |
| 1/5/1977 | 1977 | 1 | 5 | 219 | 10 | 36 | 23 | -9 | 4307.75 |
| 1/6/1977 | 1977 | 1 | 6 | 220 | 10 | 36 | 23 | -9 | 4298.75 |
| 1/7/1977 | 1977 | 1 | 7 | 221 | -1 | 25 | 12 | -20 | 4278.75 |
| 1/8/1977 | 1977 | 1 | 8 | 222 | 5 | 25 | 15 | -17 | 4261.75 |
| 1/9/1977 | 1977 | 1 | 9 | 223 | 9 | 30 | 19.5 | -12.5 | 4249.25 |
| 1/10/1977 | 1977 | 1 | 10 | 224 | -10 | 29 | 9.5 | -22.5 | 4226.75 |
| 1/11/1977 | 1977 | 1 | 11 | 225 | -4 | 34 | 15 | -17 | 4209.75 |
| 1/12/1977 | 1977 | 1 | 12 | 226 | -9 | 39 | 15 | -17 | 4192.75 |
| 1/13/1977 | 1977 | 1 | 13 | 227 | -10 | 35 | 12.5 | -19.5 | 4173.25 |
| 1/14/1977 | 1977 | 1 | 14 | 228 | -10 | 32 | 11 | -21 | 4152.25 |
| 1/15/1977 | 1977 | 1 | 15 | 229 | -10 | 32 | 11 | -21 | 4131.25 |
| 1/16/1977 | 1977 | 1 | 16 | 230 | -11 | 39 | 14 | -18 | 4113.25 |
| 1/17/1977 | 1977 | 1 | 17 | 231 | 12 | 40 | 26 | -6 | 4107.25 |
| 1/18/1977 | 1977 | 1 | 18 | 232 | 12 | 39 | 25.5 | -6.5 | 4100.75 |
| 1/19/1977 | 1977 | 1 | 19 | 233 | 13 | 39 | 26 | -6 | 4094.75 |
| 1/20/1977 | 1977 | 1 | 20 | 234 | 12 | 38 | 25 | -7 | 4087.75 |
| 1/21/1977 | 1977 | 1 | 21 | 235 | 22 | 40 | 31 | -1 | 4086.75 |
| 1/22/1977 | 1977 | 1 | 22 | 236 | 20 | 39 | 29.5 | -2.5 | 4084.25 |
| 1/23/1977 | 1977 | 1 | 23 | 237 | 25 | 37 | 31 | -1 | 4083.25 |
| 1/24/1977 | 1977 | 1 | 24 | 238 | 25 | 39 | 32 | 0 | 4083.25 |
| 1/25/1977 | 1977 | 1 | 25 | 239 | 12 | 36 | 24 | -8 | 4075.25 |
| 1/26/1977 | 1977 | 1 | 26 | 240 | 15 | 38 | 26.5 | -5.5 | 4069.75 |
| 1/27/1977 | 1977 | 1 | 27 | 241 | 19 | 37 | 28 | -4 | 4065.75 |
| 1/28/1977 | 1977 | 1 | 28 | 242 | 17 | 40 | 28.5 | -3.5 | 4062.25 |
| 1/29/1977 | 1977 | 1 | 29 | 243 | 13 | 40 | 26.5 | -5.5 | 4056.75 |
| 1/30/1977 | 1977 | 1 | 30 | 244 | 13 | 39 | 26 | -6 | 4050.75 |
| 1/31/1977 | 1977 | 1 | 31 | 245 | 18 | 40 | 29 | -3 | 4047.75 |
| 2/1/1977 | 1977 | 2 | 1 | 246 | 21 | 48 | 34.5 | 2.5 | 4050.25 |
| 2/2/1977 | 1977 | 2 | 2 | 247 | 20 | 39 | 29.5 | -2.5 | 4047.75 |
| 2/3/1977 | 1977 | 2 | 3 | 248 | 17 | 37 | 27 | -5 | 4042.75 |
| 2/4/1977 | 1977 | 2 | 4 | 249 | 15 | 35 | 25 | -7 | 4035.75 |
| 2/5/1977 | 1977 | 2 | 5 | 250 | 14 | 32 | 23 | -9 | 4026.75 |
| 2/6/1977 | 1977 | 2 | 6 | 251 | 13 | 30 | 21.5 | -10.5 | 4016.25 |
| 2/7/1977 | 1977 | 2 | 7 | 252 | 12 | 32 | 22 | -10 | 4006.25 |
| 2/8/1977 | 1977 | 2 | 8 | 253 | 15 | 37 | 26 | -6 | 4000.25 |
| 2/9/1977 | 1977 | 2 | 9 | 254 | 14 | 35 | 24.5 | -7.5 | 3992.75 |
| 2/10/1977 | 1977 | 2 | 10 | 255 | 19 | 40 | 29.5 | -2.5 | 3990.25 |
| 2/11/1977 | 1977 | 2 | 11 | 256 | 20 | 40 | 30 | -2 | 3988.25 |
| 2/12/1977 | 1977 | 2 | 12 | 257 | 21 | 44 | 32.5 | 0.5 | 3988.75 |
| 2/13/1977 | 1977 | 2 | 13 | 258 | 20 | 49 | 34.5 | 2.5 | 3991.25 |
| 2/14/1977 | 1977 | 2 | 14 | 259 | 20 | 49 | 34.5 | 2.5 | 3993.75 |
| 2/15/1977 | 1977 | 2 | 15 | 260 | 20 | 49 | 34.5 | 2.5 | 3996.25 |
| 2/16/1977 | 1977 | 2 | 16 | 261 | 28 | 50 | 39 | 7 | 4003.25 |
| 2/17/1977 | 1977 | 2 | 17 | 262 | 29 | 54 | 41.5 | 9.5 | 4012.75 |
| 2/18/1977 | 1977 | 2 | 18 | 263 | 29 | 59 | 44 | 12 | 4024.75 |
| 2/19/1977 | 1977 | 2 | 19 | 264 | 27 | 58 | 42.5 | 10.5 | 4035.25 |
| 2/20/1977 | 1977 | 2 | 20 | 265 | 28 | 60 | 44 | 12 | 4047.25 |
| 2/21/1977 | 1977 | 2 | 21 | 266 | 27 | 61 | 44 | 12 | 4059.25 |
| 2/22/1977 | 1977 | 2 | 22 | 267 | 11 | 59 | 35 | 3 | 4062.25 |
| 2/23/1977 | 1977 | 2 | 23 | 268 | 10 | 30 | 20 | -12 | 4050.25 |
| 2/24/1977 | 1977 | 2 | 24 | 269 | 8 | 29 | 18.5 | -13.5 | 4036.75 |
| 2/25/1977 | 1977 | 2 | 25 | 270 | 12 | 30 | 21 | -11 | 4025.75 |
| 2/26/1977 | 1977 | 2 | 26 | 271 | 10 | 29 | 19.5 | -12.5 | 4013.25 |
| 2/27/1977 | 1977 | 2 | 27 | 272 | 12 | 39 | 25.5 | -6.5 | 4006.75 |
| 2/28/1977 | 1977 | 2 | 28 | 273 | 10 | 40 | 25 | -7 | 3999.75 |
| 3/1/1977 | 1977 | 3 | 1 | 274 | 20 | 45 | 32.5 | 0.5 | 4000.25 |
| 3/2/1977 | 1977 | 3 | 2 | 275 | 10 | 40 | 25 | -7 | 3993.25 |
| 3/3/1977 | 1977 | 3 | 3 | 276 | 12 | 36 | 24 | -8 | 3985.25 |
| 3/4/1977 | 1977 | 3 | 4 | 277 | 15 | 34 | 24.5 | -7.5 | 3977.75 |
| 3/5/1977 | 1977 | 3 | 5 | 278 | 18 | 32 | 25 | -7 | 3970.75 |
| 3/6/1977 | 1977 | 3 | 6 | 279 | 12 | 40 | 26 | -6 | 3964.75 |
| 3/7/1977 | 1977 | 3 | 7 | 280 | 15 | 39 | 27 | -5 | 3959.75 |
| 3/8/1977 | 1977 | 3 | 8 | 281 | 18 | 40 | 29 | -3 | 3956.75 |
| 3/9/1977 | 1977 | 3 | 9 | 282 | 19 | 42 | 30.5 | -1.5 | 3955.25 |
| 3/10/1977 | 1977 | 3 | 10 | 283 | 20 | 40 | 30 | -2 | 3953.25 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/11/1977 | 1977 | 3 | 11 | 284 | 10 | 39 | 24.5 | -7.5 | 3945.75 |
| 3/12/1977 | 1977 | 3 | 12 | 285 | 16 | 49 | 32.5 | 0.5 | 3946.25 |
| 3/13/1977 | 1977 | 3 | 13 | 286 | 19 | 32 | 25.5 | -6.5 | 3939.75 |
| 3/14/1977 | 1977 | 3 | 14 | 287 | 19 | 42 | 30.5 | -1.5 | 3938.25 |
| 3/15/1977 | 1977 | 3 | 15 | 288 | 20 | 42 | 31 | -1 | 3937.25 |
| 3/16/1977 | 1977 | 3 | 16 | 289 | 20 | 45 | 32.5 | 0.5 | 3937.75 |
| 3/17/1977 | 1977 | 3 | 17 | 290 | 28 | 49 | 38.5 | 6.5 | 3944.25 |
| 3/18/1977 | 1977 | 3 | 18 | 291 | 20 | 46 | 33 | 1 | 3945.25 |
| 3/19/1977 | 1977 | 3 | 19 | 292 | 19 | 42 | 30.5 | -1.5 | 3943.75 |
| 3/20/1977 | 1977 | 3 | 20 | 293 | 19 | 48 | 33.5 | 1.5 | 3945.25 |
| 3/21/1977 | 1977 | 3 | 21 | 294 | 18 | 46 | 32 | 0 | 3945.25 |
| 3/22/1977 | 1977 | 3 | 22 | 295 | 20 | 54 | 37 | 5 | 3950.25 |
| 3/23/1977 | 1977 | 3 | 23 | 296 | 32 | 52 | 42 | 10 | 3960.25 |
| 3/24/1977 | 1977 | 3 | 24 | 297 | 30 | 49 | 39.5 | 7.5 | 3967.75 |
| 3/25/1977 | 1977 | 3 | 25 | 298 | 32 | 50 | 41 | 9 | 3976.75 |
| 3/26/1977 | 1977 | 3 | 26 | 299 | 28 | 51 | 39.5 | 7.5 | 3984.25 |
| 3/27/1977 | 1977 | 3 | 27 | 300 | 32 | 40 | 36 | 4 | 3988.25 |
| 3/28/1977 | 1977 | 3 | 28 | 301 | 27 | 50 | 38.5 | 6.5 | 3994.75 |
| 3/29/1977 | 1977 | 3 | 29 | 302 | 20 | 37 | 28.5 | -3.5 | 3991.25 |
| 3/30/1977 | 1977 | 3 | 30 | 303 | 16 | 31 | 23.5 | -8.5 | 3982.75 |
| 3/31/1977 | 1977 | 3 | 31 | 304 | 15 | 30 | 22.5 | -9.5 | 3973.25 |
| 4/1/1977 | 1977 | 4 | 1 | 305 | 26 | 40 | 33 | 1 | 3974.25 |
| 4/2/1977 | 1977 | 4 | 2 | 306 | 25 | 42 | 33.5 | 1.5 | 3975.75 |
| 4/3/1977 | 1977 | 4 | 3 | 307 | 26 | 43 | 34.5 | 2.5 | 3978.25 |
| 4/4/1977 | 1977 | 4 | 4 | 308 | 21 | | 21 | -11 | 3967.25 |
| 4/5/1977 | 1977 | 4 | 5 | 309 | 24 | | 24 | -8 | 3959.25 |
| 4/6/1977 | 1977 | 4 | 6 | 310 | 25 | | 25 | -7 | 3952.25 |
| 4/7/1977 | 1977 | 4 | 7 | 311 | 31 | | 31 | -1 | 3951.25 |
| 4/8/1977 | 1977 | 4 | 8 | 312 | 35 | | 35 | 3 | 3954.25 |
| 4/9/1977 | 1977 | 4 | 9 | 313 | 36 | | 36 | 4 | 3958.25 |
| 4/10/1977 | 1977 | 4 | 10 | 314 | 39 | 74 | 56.5 | 24.5 | 3982.75 |
| 4/11/1977 | 1977 | 4 | 11 | 315 | 31 | 74 | 52.5 | 20.5 | 4003.25 |
| 4/12/1977 | 1977 | 4 | 12 | 316 | 30 | 65 | 47.5 | 15.5 | 4018.75 |
| 4/13/1977 | 1977 | 4 | 13 | 317 | 33 | 69 | 51 | 19 | 4037.75 |
| 4/14/1977 | 1977 | 4 | 14 | 318 | 31 | 67 | 49 | 17 | 4054.75 |
| 4/15/1977 | 1977 | 4 | 15 | 319 | 35 | 69 | 52 | 20 | 4074.75 |
| 4/16/1977 | 1977 | 4 | 16 | 320 | 36 | 66 | 31.25 | -0.75 | 4074 |
| 4/17/1977 | 1977 | 4 | 17 | 321 | 35 | 62 | 48.5 | 16.5 | 4090.5 |
| 4/18/1977 | 1977 | 4 | 18 | 322 | 30 | 55 | 42.5 | 10.5 | 4101 |
| 4/19/1977 | 1977 | 4 | 19 | 323 | 31 | 54 | 42.5 | 10.5 | 4111.5 |
| 4/20/1977 | 1977 | 4 | 20 | 324 | 32 | 69 | 50.5 | 18.5 | 4130 |
| 4/21/1977 | 1977 | 4 | 21 | 325 | 41 | 68 | 54.5 | 22.5 | 4152.5 |
| 4/22/1977 | 1977 | 4 | 22 | 326 | 30 | 64 | 47 | 15 | 4167.5 |
| 4/23/1977 | 1977 | 4 | 23 | 327 | 33 | 72 | 52.5 | 20.5 | 4188 |
| 4/24/1977 | 1977 | 4 | 24 | 328 | 41 | 70 | 55.5 | 23.5 | 4211.5 |
| 4/25/1977 | 1977 | 4 | 25 | 329 | 36 | 69 | 52.5 | 20.5 | 4232 |
| 4/26/1977 | 1977 | 4 | 26 | 330 | 37 | 73 | 55 | 23 | 4255 |
| 4/27/1977 | 1977 | 4 | 27 | 331 | 42 | 74 | 58 | 26 | 4281 |
| 4/28/1977 | 1977 | 4 | 28 | 332 | 45 | 72 | 58.5 | 26.5 | 4307.5 |
| 4/29/1977 | 1977 | 4 | 29 | 333 | 40 | 73 | 56.5 | 24.5 | 4332 |
| 4/30/1977 | 1977 | 4 | 30 | 334 | 40 | 76 | 58 | 26 | 4358 |
| 5/1/1977 | 1977 | 5 | 1 | 335 | 49 | 74 | 61.5 | 29.5 | 4387.5 |
| 5/2/1977 | 1977 | 5 | 2 | 336 | 40 | 76 | 58 | 26 | 4413.5 |
| 5/3/1977 | 1977 | 5 | 3 | 337 | 42 | 75 | 58.5 | 26.5 | 4440 |
| 5/4/1977 | 1977 | 5 | 4 | 338 | 42 | 69 | 55.5 | 23.5 | 4463.5 |
| 5/5/1977 | 1977 | 5 | 5 | 339 | 43 | 69 | 56 | 24 | 4487.5 |
| 5/6/1977 | 1977 | 5 | 6 | 340 | 38 | 70 | 54 | 22 | 4509.5 |
| 5/7/1977 | 1977 | 5 | 7 | 341 | 39 | 73 | 56 | 24 | 4533.5 |
| 5/8/1977 | 1977 | 5 | 8 | 342 | 38 | 72 | 55 | 23 | 4556.5 |
| 5/9/1977 | 1977 | 5 | 9 | 343 | 41 | 74 | 57.5 | 25.5 | 4582 |
| 5/10/1977 | 1977 | 5 | 10 | 344 | 48 | 76 | 62 | 30 | 4612 |
| 5/11/1977 | 1977 | 5 | 11 | 345 | 49 | 68 | 58.5 | 26.5 | 4638.5 |
| 5/12/1977 | 1977 | 5 | 12 | 346 | 35 | 67 | 51 | 19 | 4657.5 |
| 5/13/1977 | 1977 | 5 | 13 | 347 | 36 | 72 | 54 | 22 | 4679.5 |
| 5/14/1977 | 1977 | 5 | 14 | 348 | 43 | 68 | 55.5 | 23.5 | 4703 |
| 5/15/1977 | 1977 | 5 | 15 | 349 | 40 | 64 | 52 | 20 | 4723 |
| 5/16/1977 | 1977 | 5 | 16 | 350 | 32 | 60 | 46 | 14 | 4737 |
| 5/17/1977 | 1977 | 5 | 17 | 351 | 37 | 67 | 52 | 20 | 4757 |
| 5/18/1977 | 1977 | 5 | 18 | 352 | 38 | 70 | 54 | 22 | 4779 |
| 5/19/1977 | 1977 | 5 | 19 | 353 | 45 | 70 | 57.5 | 25.5 | 4804.5 |
| 5/20/1977 | 1977 | 5 | 20 | 354 | 31 | 75 | 53 | 21 | 4825.5 |
| 5/21/1977 | 1977 | 5 | 21 | 355 | 36 | 63 | 49.5 | 17.5 | 4843 |
| 5/22/1977 | 1977 | 5 | 22 | 356 | 32 | 69 | 50.5 | 18.5 | 4861.5 |
| 5/23/1977 | 1977 | 5 | 23 | 357 | 39 | 70 | 54.5 | 22.5 | 4884 |
| 5/24/1977 | 1977 | 5 | 24 | 358 | 40 | 69 | 54.5 | 22.5 | 4906.5 |
| 5/25/1977 | 1977 | 5 | 25 | 359 | 46 | 70 | 58 | 26 | 4932.5 |
| 5/26/1977 | 1977 | 5 | 26 | 360 | 43 | 70 | 56.5 | 24.5 | 4957 |
| 5/27/1977 | 1977 | 5 | 27 | 361 | 38 | 66 | 52 | 20 | 4977 |
| 5/28/1977 | 1977 | 5 | 28 | 362 | 39 | 71 | 55 | 23 | 5000 |
| 5/29/1977 | 1977 | 5 | 29 | 363 | 38 | 69 | 53.5 | 21.5 | 5021.5 |
| 5/30/1977 | 1977 | 5 | 30 | 364 | 37 | 69 | 53 | 21 | 5042.5 |
| 5/31/1977 | 1977 | 5 | 31 | 365 | 41 | 74 | 57.5 | 25.5 | 5068 |
| 6/1/1977 | 1977 | 6 | 1 | 1 | 52 | 86 | 69 | 37 | 37 |
| 6/2/1977 | 1977 | 6 | 2 | 2 | 54 | 83 | 68.5 | 36.5 | 73.5 |
| 6/3/1977 | 1977 | 6 | 3 | 3 | 56 | 77 | 66.5 | 34.5 | 108 |
| 6/4/1977 | 1977 | 6 | 4 | 4 | 48 | 79 | 63.5 | 31.5 | 139.5 |
| 6/5/1977 | 1977 | 6 | 5 | 5 | 57 | 78 | 67.5 | 35.5 | 175 |
| 6/6/1977 | 1977 | 6 | 6 | 6 | 55 | 81 | 68 | 36 | 211 |
| 6/7/1977 | 1977 | 6 | 7 | 7 | 51 | 80 | 65.5 | 33.5 | 244.5 |
| 6/8/1977 | 1977 | 6 | 8 | 8 | 50 | 80 | 65 | 33 | 277.5 |
| 6/9/1977 | 1977 | 6 | 9 | 9 | 52 | 81 | 66.5 | 34.5 | 312 |
| 6/10/1977 | 1977 | 6 | 10 | 10 | 49 | 82 | 65.5 | 33.5 | 345.5 |
| 6/11/1977 | 1977 | 6 | 11 | 11 | 51 | 81 | 66 | 34 | 379.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/12/1977 | 1977 | 6 | 12 | 12 | 48 | 84 | 66 | 34 | 413.5 |
| 6/13/1977 | 1977 | 6 | 13 | 13 | 51 | 88 | 69.5 | 37.5 | 451 |
| 6/14/1977 | 1977 | 6 | 14 | 14 | 51 | 90 | 70.5 | 38.5 | 489.5 |
| 6/15/1977 | 1977 | 6 | 15 | 15 | 55 | 89 | 72 | 40 | 529.5 |
| 6/16/1977 | 1977 | 6 | 16 | 16 | 53 | 90 | 71.5 | 39.5 | 569 |
| 6/17/1977 | 1977 | 6 | 17 | 17 | 51 | 91 | 71 | 39 | 608 |
| 6/18/1977 | 1977 | 6 | 18 | 18 | 55 | 88 | 71.5 | 39.5 | 647.5 |
| 6/19/1977 | 1977 | 6 | 19 | 19 | 57 | 85 | 71 | 39 | 686.5 |
| 6/20/1977 | 1977 | 6 | 20 | 20 | 58 | 87 | 72.5 | 40.5 | 727 |
| 6/21/1977 | 1977 | 6 | 21 | 21 | 51 | 81 | 66 | 34 | 761 |
| 6/22/1977 | 1977 | 6 | 22 | 22 | 54 | 78 | 66 | 34 | 795 |
| 6/23/1977 | 1977 | 6 | 23 | 23 | 48 | 75 | 61.5 | 29.5 | 824.5 |
| 6/24/1977 | 1977 | 6 | 24 | 24 | 51 | 74 | 62.5 | 30.5 | 855 |
| 6/25/1977 | 1977 | 6 | 25 | 25 | 49 | 81 | 65 | 33 | 888 |
| 6/26/1977 | 1977 | 6 | 26 | 26 | 52 | 88 | 70 | 38 | 926 |
| 6/27/1977 | 1977 | 6 | 27 | 27 | 55 | 87 | 71 | 39 | 965 |
| 6/28/1977 | 1977 | 6 | 28 | 28 | 57 | 91 | 74 | 42 | 1007 |
| 6/29/1977 | 1977 | 6 | 29 | 29 | 56 | 88 | 72 | 40 | 1047 |
| 6/30/1977 | 1977 | 6 | 30 | 30 | 53 | 91 | 72 | 40 | 1087 |
| 7/1/1977 | 1977 | 7 | 1 | 31 | 56 | 88 | 72 | 40 | 1127 |
| 7/2/1977 | 1977 | 7 | 2 | 32 | 61 | 90 | 75.5 | 43.5 | 1170.5 |
| 7/3/1977 | 1977 | 7 | 3 | 33 | 62 | 91 | 76.5 | 44.5 | 1215 |
| 7/4/1977 | 1977 | 7 | 4 | 34 | 50 | 96 | 73 | 41 | 1256 |
| 7/5/1977 | 1977 | 7 | 5 | 35 | 53 | 90 | 71.5 | 39.5 | 1295.5 |
| 7/6/1977 | 1977 | 7 | 6 | 36 | 52 | 83 | 67.5 | 35.5 | 1331 |
| 7/7/1977 | 1977 | 7 | 7 | 37 | 55 | 86 | 70.5 | 38.5 | 1369.5 |
| 7/8/1977 | 1977 | 7 | 8 | 38 | 56 | 87 | 71.5 | 39.5 | 1409 |
| 7/9/1977 | 1977 | 7 | 9 | 39 | 62 | 85 | 73.5 | 41.5 | 1450.5 |
| 7/10/1977 | 1977 | 7 | 10 | 40 | 59 | 86 | 72.5 | 40.5 | 1491 |
| 7/11/1977 | 1977 | 7 | 11 | 41 | 58 | 73 | 65.5 | 33.5 | 1524.5 |
| 7/12/1977 | 1977 | 7 | 12 | 42 | 56 | 82 | 69 | 37 | 1561.5 |
| 7/13/1977 | 1977 | 7 | 13 | 43 | 54 | 80 | 67 | 35 | 1596.5 |
| 7/14/1977 | 1977 | 7 | 14 | 44 | 57 | 71 | 64 | 32 | 1628.5 |
| 7/15/1977 | 1977 | 7 | 15 | 45 | 54 | 78 | 66 | 34 | 1662.5 |
| 7/16/1977 | 1977 | 7 | 16 | 46 | 57 | 80 | 68.5 | 36.5 | 1699 |
| 7/17/1977 | 1977 | 7 | 17 | 47 | 55 | 81 | 68 | 36 | 1735 |
| 7/18/1977 | 1977 | 7 | 18 | 48 | 56 | 84 | 70 | 38 | 1773 |
| 7/19/1977 | 1977 | 7 | 19 | 49 | 55 | 81 | 68 | 36 | 1809 |
| 7/20/1977 | 1977 | 7 | 20 | 50 | 53 | 76 | 64.5 | 32.5 | 1841.5 |
| 7/21/1977 | 1977 | 7 | 21 | 51 | 54 | 78 | 66 | 34 | 1875.5 |
| 7/22/1977 | 1977 | 7 | 22 | 52 | 55 | 80 | 67.5 | 35.5 | 1911 |
| 7/23/1977 | 1977 | 7 | 23 | 53 | 53 | 79 | 66 | 34 | 1945 |
| 7/24/1977 | 1977 | 7 | 24 | 54 | 59 | 71 | 65 | 33 | 1978 |
| 7/25/1977 | 1977 | 7 | 25 | 55 | 53 | 77 | 65 | 33 | 2011 |
| 7/26/1977 | 1977 | 7 | 26 | 56 | 52 | 79 | 65.5 | 33.5 | 2044.5 |
| 7/27/1977 | 1977 | 7 | 27 | 57 | 53 | 85 | 69 | 37 | 2081.5 |
| 7/28/1977 | 1977 | 7 | 28 | 58 | 51 | 83 | 67 | 35 | 2116.5 |
| 7/29/1977 | 1977 | 7 | 29 | 59 | 55 | 88 | 71.5 | 39.5 | 2156 |
| 7/30/1977 | 1977 | 7 | 30 | 60 | 56 | 88 | 72 | 40 | 2196 |
| 7/31/1977 | 1977 | 7 | 31 | 61 | 57 | 90 | 73.5 | 41.5 | 2237.5 |
| 8/1/1977 | 1977 | 8 | 1 | 62 | 55 | 90 | 72.5 | 40.5 | 2278 |
| 8/2/1977 | 1977 | 8 | 2 | 63 | 55 | 90 | 72.5 | 40.5 | 2318.5 |
| 8/3/1977 | 1977 | 8 | 3 | 64 | 56 | 93 | 74.5 | 42.5 | 2361 |
| 8/4/1977 | 1977 | 8 | 4 | 65 | 60 | 88 | 74 | 42 | 2403 |
| 8/5/1977 | 1977 | 8 | 5 | 66 | 59 | 86 | 72.5 | 40.5 | 2443.5 |
| 8/6/1977 | 1977 | 8 | 6 | 67 | 58 | 89 | 73.5 | 41.5 | 2485 |
| 8/7/1977 | 1977 | 8 | 7 | 68 | 57 | 88 | 72.5 | 40.5 | 2525.5 |
| 8/8/1977 | 1977 | 8 | 8 | 69 | 55 | 86 | 70.5 | 38.5 | 2564 |
| 8/9/1977 | 1977 | 8 | 9 | 70 | 59 | 85 | 72 | 40 | 2604 |
| 8/10/1977 | 1977 | 8 | 10 | 71 | 58 | 80 | 69 | 37 | 2641 |
| 8/11/1977 | 1977 | 8 | 11 | 72 | 54 | 79 | 66.5 | 34.5 | 2675.5 |
| 8/12/1977 | 1977 | 8 | 12 | 73 | 55 | 67 | 61 | 29 | 2704.5 |
| 8/13/1977 | 1977 | 8 | 13 | 74 | 51 | 75 | 63 | 31 | 2735.5 |
| 8/14/1977 | 1977 | 8 | 14 | 75 | 59 | 78 | 68.5 | 36.5 | 2772 |
| 8/15/1977 | 1977 | 8 | 15 | 76 | 59 | 70 | 64.5 | 32.5 | 2804.5 |
| 8/16/1977 | 1977 | 8 | 16 | 77 | 56 | 70 | 63 | 31 | 2835.5 |
| 8/17/1977 | 1977 | 8 | 17 | 78 | 59 | 72 | 65.5 | 33.5 | 2869 |
| 8/18/1977 | 1977 | 8 | 18 | 79 | 55 | 70 | 62.5 | 30.5 | 2899.5 |
| 8/19/1977 | 1977 | 8 | 19 | 80 | 58 | 78 | 68 | 36 | 2935.5 |
| 8/20/1977 | 1977 | 8 | 20 | 81 | 53 | 72 | 62.5 | 30.5 | 2966 |
| 8/21/1977 | 1977 | 8 | 21 | 82 | 54 | 79 | 66.5 | 34.5 | 3000.5 |
| 8/22/1977 | 1977 | 8 | 22 | 83 | 53 | 79 | 66 | 34 | 3034.5 |
| 8/23/1977 | 1977 | 8 | 23 | 84 | 54 | 83 | 68.5 | 36.5 | 3071 |
| 8/24/1977 | 1977 | 8 | 24 | 85 | 55 | 84 | 69.5 | 37.5 | 3108.5 |
| 8/25/1977 | 1977 | 8 | 25 | 86 | 56 | 81 | 68.5 | 36.5 | 3145 |
| 8/26/1977 | 1977 | 8 | 26 | 87 | 57 | 82 | 69.5 | 37.5 | 3182.5 |
| 8/27/1977 | 1977 | 8 | 27 | 88 | 58 | 80 | 69 | 37 | 3219.5 |
| 8/28/1977 | 1977 | 8 | 28 | 89 | 49 | 78 | 63.5 | 31.5 | 3251 |
| 8/29/1977 | 1977 | 8 | 29 | 90 | 48 | 80 | 64 | 32 | 3283 |
| 8/30/1977 | 1977 | 8 | 30 | 91 | 55 | 81 | 68 | 36 | 3319 |
| 8/31/1977 | 1977 | 8 | 31 | 92 | 55 | 80 | 67.5 | 35.5 | 3354.5 |
| 9/1/1977 | 1977 | 9 | 1 | 93 | 51 | 76 | 63.5 | 31.5 | 3386 |
| 9/2/1977 | 1977 | 9 | 2 | 94 | 57 | 73 | 65 | 33 | 3419 |
| 9/3/1977 | 1977 | 9 | 3 | 95 | 52 | 76 | 64 | 32 | 3451 |
| 9/4/1977 | 1977 | 9 | 4 | 96 | 55 | 75 | 65 | 33 | 3484 |
| 9/5/1977 | 1977 | 9 | 5 | 97 | 54 | 78 | 66 | 34 | 3518 |
| 9/6/1977 | 1977 | 9 | 6 | 98 | 51 | 79 | 65 | 33 | 3551 |
| 9/7/1977 | 1977 | 9 | 7 | 99 | 53 | 80 | 66.5 | 34.5 | 3585.5 |
| 9/8/1977 | 1977 | 9 | 8 | 100 | 54 | 81 | 67.5 | 35.5 | 3621 |
| 9/9/1977 | 1977 | 9 | 9 | 101 | 53 | 82 | 67.5 | 35.5 | 3656.5 |
| 9/10/1977 | 1977 | 9 | 10 | 102 | 54 | 79 | 66.5 | 34.5 | 3691 |
| 9/11/1977 | 1977 | 9 | 11 | 103 | 52 | 79 | 65.5 | 33.5 | 3724.5 |
| 9/12/1977 | 1977 | 9 | 12 | 104 | 51 | 69 | 60 | 28 | 3752.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/13/1977 | 1977 | 9 | 13 | 105 | 46 | 70 | 58 | 26 | 3778.5 |
| 9/14/1977 | 1977 | 9 | 14 | 106 | 42 | 72 | 57 | 25 | 3803.5 |
| 9/15/1977 | 1977 | 9 | 15 | 107 | 50 | 73 | 61.5 | 29.5 | 3833 |
| 9/16/1977 | 1977 | 9 | 16 | 108 | 46 | 74 | 60 | 28 | 3861 |
| 9/17/1977 | 1977 | 9 | 17 | 109 | 51 | 70 | 60.5 | 28.5 | 3889.5 |
| 9/18/1977 | 1977 | 9 | 18 | 110 | 41 | 76 | 58.5 | 26.5 | 3916 |
| 9/19/1977 | 1977 | 9 | 19 | 111 | 46 | 78 | 62 | 30 | 3946 |
| 9/20/1977 | 1977 | 9 | 20 | 112 | 51 | 76 | 63.5 | 31.5 | 3977.5 |
| 9/21/1977 | 1977 | 9 | 21 | 113 | 43 | 75 | 59 | 27 | 4004.5 |
| 9/22/1977 | 1977 | 9 | 22 | 114 | 46 | 72 | 59 | 27 | 4031.5 |
| 9/23/1977 | 1977 | 9 | 23 | 115 | 52 | 69 | 60.5 | 28.5 | 4060 |
| 9/24/1977 | 1977 | 9 | 24 | 116 | 45 | 69 | 57 | 25 | 4085 |
| 9/25/1977 | 1977 | 9 | 25 | 117 | 46 | 67 | 56.5 | 24.5 | 4109.5 |
| 9/26/1977 | 1977 | 9 | 26 | 118 | 47 | 75 | 61 | 29 | 4138.5 |
| 9/27/1977 | 1977 | 9 | 27 | 119 | 51 | 72 | 61.5 | 29.5 | 4168 |
| 9/28/1977 | 1977 | 9 | 28 | 120 | 52 | 70 | 61 | 29 | 4197 |
| 9/29/1977 | 1977 | 9 | 29 | 121 | 46 | 75 | 60.5 | 28.5 | 4225.5 |
| 9/30/1977 | 1977 | 9 | 30 | 122 | 54 | 73 | 63.5 | 31.5 | 4257 |
| 10/1/1977 | 1977 | 10 | 1 | 123 | 40 | 68 | 54 | 22 | 4279 |
| 10/2/1977 | 1977 | 10 | 2 | 124 | 41 | 69 | 55 | 23 | 4302 |
| 10/3/1977 | 1977 | 10 | 3 | 125 | 52 | 72 | 62 | 30 | 4332 |
| 10/4/1977 | 1977 | 10 | 4 | 126 | 46 | 70 | 58 | 26 | 4358 |
| 10/5/1977 | 1977 | 10 | 5 | 127 | 49 | 74 | 61.5 | 29.5 | 4387.5 |
| 10/6/1977 | 1977 | 10 | 6 | 128 | 49 | 71 | 60 | 28 | 4415.5 |
| 10/7/1977 | 1977 | 10 | 7 | 129 | 49 | 68 | 58.5 | 26.5 | 4442 |
| 10/8/1977 | 1977 | 10 | 8 | 130 | 40 | 66 | 53 | 21 | 4463 |
| 10/9/1977 | 1977 | 10 | 9 | 131 | 41 | 65 | 53 | 21 | 4484 |
| 10/10/1977 | 1977 | 10 | 10 | 132 | 40 | 64 | 52 | 20 | 4504 |
| 10/11/1977 | 1977 | 10 | 11 | 133 | 32 | 64 | 48 | 16 | 4520 |
| 10/12/1977 | 1977 | 10 | 12 | 134 | 32 | 60 | 46 | 14 | 4534 |
| 10/13/1977 | 1977 | 10 | 13 | 135 | 35 | 66 | 50.5 | 18.5 | 4552.5 |
| 10/14/1977 | 1977 | 10 | 14 | 136 | 39 | 67 | 53 | 21 | 4573.5 |
| 10/15/1977 | 1977 | 10 | 15 | 137 | 38 | 68 | 53 | 21 | 4594.5 |
| 10/16/1977 | 1977 | 10 | 16 | 138 | 37 | 69 | 53 | 21 | 4615.5 |
| 10/17/1977 | 1977 | 10 | 17 | 139 | 48 | 68 | 58 | 26 | 4641.5 |
| 10/18/1977 | 1977 | 10 | 18 | 140 | 40 | 69 | 54.5 | 22.5 | 4664 |
| 10/19/1977 | 1977 | 10 | 19 | 141 | 39 | 70 | 54.5 | 22.5 | 4686.5 |
| 10/20/1977 | 1977 | 10 | 20 | 142 | 42 | 67 | 54.5 | 22.5 | 4709 |
| 10/21/1977 | 1977 | 10 | 21 | 143 | 36 | 65 | 50.5 | 18.5 | 4727.5 |
| 10/22/1977 | 1977 | 10 | 22 | 144 | 32 | 59 | 45.5 | 13.5 | 4741 |
| 10/23/1977 | 1977 | 10 | 23 | 145 | 36 | 46 | 41 | 9 | 4750 |
| 10/24/1977 | 1977 | 10 | 24 | 146 | 34 | 62 | 48 | 16 | 4766 |
| 10/25/1977 | 1977 | 10 | 25 | 147 | 36 | 65 | 50.5 | 18.5 | 4784.5 |
| 10/26/1977 | 1977 | 10 | 26 | 148 | 37 | 67 | 52 | 20 | 4804.5 |
| 10/27/1977 | 1977 | 10 | 27 | 149 | 39 | 65 | 52 | 20 | 4824.5 |
| 10/28/1977 | 1977 | 10 | 28 | 150 | 40 | 63 | 51.5 | 19.5 | 4844 |
| 10/29/1977 | 1977 | 10 | 29 | 151 | 41 | 62 | 51.5 | 19.5 | 4863.5 |
| 10/30/1977 | 1977 | 10 | 30 | 152 | 39 | 59 | 49 | 17 | 4880.5 |
| 10/31/1977 | 1977 | 10 | 31 | 153 | 32 | 56 | 44 | 12 | 4892.5 |
| 11/1/1977 | 1977 | 11 | 1 | 154 | 21 | 53 | 37 | 5 | 4897.5 |
| 11/2/1977 | 1977 | 11 | 2 | 155 | 21 | 53 | 37 | 5 | 4902.5 |
| 11/3/1977 | 1977 | 11 | 3 | 156 | 23 | 52 | 37.5 | 5.5 | 4908 |
| 11/4/1977 | 1977 | 11 | 4 | 157 | 24 | 53 | 38.5 | 6.5 | 4914.5 |
| 11/5/1977 | 1977 | 11 | 5 | 158 | 25 | 52 | 38.5 | 6.5 | 4921 |
| 11/6/1977 | 1977 | 11 | 6 | 159 | 26 | 52 | 39 | 7 | 4928 |
| 11/7/1977 | 1977 | 11 | 7 | 160 | 28 | 40 | 34 | 2 | 4930 |
| 11/8/1977 | 1977 | 11 | 8 | 161 | 28 | 49 | 38.5 | 6.5 | 4936.5 |
| 11/9/1977 | 1977 | 11 | 9 | 162 | 20 | 48 | 34 | 2 | 4938.5 |
| 11/10/1977 | 1977 | 11 | 10 | 163 | 11 | 48 | 29.5 | -2.5 | 4936 |
| 11/11/1977 | 1977 | 11 | 11 | 164 | 21 | 48 | 34.5 | 2.5 | 4938.5 |
| 11/12/1977 | 1977 | 11 | 12 | 165 | 24 | 53 | 38.5 | 6.5 | 4945 |
| 11/13/1977 | 1977 | 11 | 13 | 166 | 28 | 54 | 41 | 9 | 4954 |
| 11/14/1977 | 1977 | 11 | 14 | 167 | 30 | 56 | 43 | 11 | 4965 |
| 11/15/1977 | 1977 | 11 | 15 | 168 | 31 | 57 | 44 | 12 | 4977 |
| 11/16/1977 | 1977 | 11 | 16 | 169 | 28 | 52 | 40 | 8 | 4985 |
| 11/17/1977 | 1977 | 11 | 17 | 170 | 30 | 56 | 43 | 11 | 4996 |
| 11/18/1977 | 1977 | 11 | 18 | 171 | 33 | 52 | 42.5 | 10.5 | 5006.5 |
| 11/19/1977 | 1977 | 11 | 19 | 172 | 34 | 52 | 43 | 11 | 5017.5 |
| 11/20/1977 | 1977 | 11 | 20 | 173 | 39 | 49 | 44 | 12 | 5029.5 |
| 11/21/1977 | 1977 | 11 | 21 | 174 | 35 | 47 | 41 | 9 | 5038.5 |
| 11/22/1977 | 1977 | 11 | 22 | 175 | 25 | 50 | 37.5 | 5.5 | 5044 |
| 11/23/1977 | 1977 | 11 | 23 | 176 | 28 | 54 | 41 | 9 | 5053 |
| 11/24/1977 | 1977 | 11 | 24 | 177 | 29 | 51 | 40 | 8 | 5061 |
| 11/25/1977 | 1977 | 11 | 25 | 178 | 25 | 52 | 38.5 | 6.5 | 5067.5 |
| 11/26/1977 | 1977 | 11 | 26 | 179 | 31 | 58 | 44.5 | 12.5 | 5080 |
| 11/27/1977 | 1977 | 11 | 27 | 180 | 29 | 51 | 40 | 8 | 5088 |
| 11/28/1977 | 1977 | 11 | 28 | 181 | 31 | 41 | 36 | 4 | 5092 |
| 11/29/1977 | 1977 | 11 | 29 | 182 | 28 | 39 | 33.5 | 1.5 | 5093.5 |
| 11/30/1977 | 1977 | 11 | 30 | 183 | 19 | 40 | 29.5 | -2.5 | 5091 |
| 12/1/1977 | 1977 | 12 | 1 | 184 | 17 | 39 | 28 | -4 | 5087 |
| 12/2/1977 | 1977 | 12 | 2 | 185 | 25 | 49 | 37 | 5 | 5092 |
| 12/3/1977 | 1977 | 12 | 3 | 186 | 26 | 50 | 38 | 6 | 5098 |
| 12/4/1977 | 1977 | 12 | 4 | 187 | 30 | 54 | 42 | 10 | 5108 |
| 12/5/1977 | 1977 | 12 | 5 | 188 | 31 | 55 | 43 | 11 | 5119 |
| 12/6/1977 | 1977 | 12 | 6 | 189 | 26 | 50 | 38 | 6 | 5125 |
| 12/7/1977 | 1977 | 12 | 7 | 190 | 27 | 52 | 39.5 | 7.5 | 5132.5 |
| 12/8/1977 | 1977 | 12 | 8 | 191 | 32 | 52 | 42 | 10 | 5142.5 |
| 12/9/1977 | 1977 | 12 | 9 | 192 | 31 | 56 | 43.5 | 11.5 | 5154 |
| 12/10/1977 | 1977 | 12 | 10 | 193 | 27 | 57 | 42 | 10 | 5164 |
| 12/11/1977 | 1977 | 12 | 11 | 194 | 32 | 59 | 45.5 | 13.5 | 5177.5 |
| 12/12/1977 | 1977 | 12 | 12 | 195 | 33 | 58 | 45.5 | 13.5 | 5191 |
| 12/13/1977 | 1977 | 12 | 13 | 196 | 29 | 57 | 43 | 11 | 5202 |
| 12/14/1977 | 1977 | 12 | 14 | 197 | 21 | 49 | 35 | 3 | 5205 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/15/1977 | 1977 | 12 | 15 | 198 | 25 | 50 | 37.5 | 5.5 | 5210.5 |
| 12/16/1977 | 1977 | 12 | 16 | 199 | 27 | 55 | 41 | 9 | 5219.5 |
| 12/17/1977 | 1977 | 12 | 17 | 200 | 19 | 50 | 34.5 | 2.5 | 5222 |
| 12/18/1977 | 1977 | 12 | 18 | 201 | 16 | 45 | 30.5 | -1.5 | 5220.5 |
| 12/19/1977 | 1977 | 12 | 19 | 202 | 17 | 42 | 29.5 | -2.5 | 5218 |
| 12/20/1977 | 1977 | 12 | 20 | 203 | 19 | 45 | 32 | 0 | 5218 |
| 12/21/1977 | 1977 | 12 | 21 | 204 | 8 | 38 | 23 | -9 | 5209 |
| 12/22/1977 | 1977 | 12 | 22 | 205 | 7 | 36 | 21.5 | -10.5 | 5198.5 |
| 12/23/1977 | 1977 | 12 | 23 | 206 | 5 | 40 | 22.5 | -9.5 | 5189 |
| 12/24/1977 | 1977 | 12 | 24 | 207 | 5 | 39 | 22 | -10 | 5179 |
| 12/25/1977 | 1977 | 12 | 25 | 208 | 10 | 38 | 24 | -8 | 5171 |
| 12/26/1977 | 1977 | 12 | 26 | 209 | 12 | 38 | 25 | -7 | 5164 |
| 12/27/1977 | 1977 | 12 | 27 | 210 | 30 | 38 | 34 | 2 | 5166 |
| 12/28/1977 | 1977 | 12 | 28 | 211 | 32 | 39 | 35.5 | 3.5 | 5169.5 |
| 12/29/1977 | 1977 | 12 | 29 | 212 | 32 | 40 | 36 | 4 | 5173.5 |
| 12/30/1977 | 1977 | 12 | 30 | 213 | 30 | 40 | 35 | 3 | 5176.5 |
| 12/31/1977 | 1977 | 12 | 31 | 214 | 30 | 40 | 35 | 3 | 5179.5 |
| 1/1/1978 | 1978 | 1 | 1 | 215 | 30 | 39 | 34.5 | 2.5 | 5182 |
| 1/2/1978 | 1978 | 1 | 2 | 216 | 19 | 40 | 29.5 | -2.5 | 5179.5 |
| 1/3/1978 | 1978 | 1 | 3 | 217 | 21 | 46 | 33.5 | 1.5 | 5181 |
| 1/4/1978 | 1978 | 1 | 4 | 218 | 20 | 40 | 30 | -2 | 5179 |
| 1/5/1978 | 1978 | 1 | 5 | 219 | 28 | 44 | 36 | 4 | 5183 |
| 1/6/1978 | 1978 | 1 | 6 | 220 | 27 | 42 | 34.5 | 2.5 | 5185.5 |
| 1/7/1978 | 1978 | 1 | 7 | 221 | 20 | 40 | 30 | -2 | 5183.5 |
| 1/8/1978 | 1978 | 1 | 8 | 222 | 21 | 40 | 30.5 | -1.5 | 5182 |
| 1/9/1978 | 1978 | 1 | 9 | 223 | 22 | 45 | 33.5 | 1.5 | 5183.5 |
| 1/10/1978 | 1978 | 1 | 10 | 224 | 29 | 46 | 37.5 | 5.5 | 5189 |
| 1/11/1978 | 1978 | 1 | 11 | 225 | 22 | 40 | 31 | -1 | 5188 |
| 1/12/1978 | 1978 | 1 | 12 | 226 | 25 | 41 | 33 | 1 | 5189 |
| 1/13/1978 | 1978 | 1 | 13 | 227 | 20 | 37 | 28.5 | -3.5 | 5185.5 |
| 1/14/1978 | 1978 | 1 | 14 | 228 | 21 | 34 | 27.5 | -4.5 | 5181 |
| 1/15/1978 | 1978 | 1 | 15 | 229 | 26 | 39 | 32.5 | 0.5 | 5181.5 |
| 1/16/1978 | 1978 | 1 | 16 | 230 | 20 | 39 | 29.5 | -2.5 | 5179 |
| 1/17/1978 | 1978 | 1 | 17 | 231 | 29 | 37 | 33 | 1 | 5180 |
| 1/18/1978 | 1978 | 1 | 18 | 232 | 28 | 35 | 31.5 | -0.5 | 5179.5 |
| 1/19/1978 | 1978 | 1 | 19 | 233 | 20 | 34 | 27 | -5 | 5174.5 |
| 1/20/1978 | 1978 | 1 | 20 | 234 | 14 | 34 | 24 | -8 | 5166.5 |
| 1/21/1978 | 1978 | 1 | 21 | 235 | 14 | 32 | 23 | -9 | 5157.5 |
| 1/22/1978 | 1978 | 1 | 22 | 236 | 13 | 36 | 24.5 | -7.5 | 5150 |
| 1/23/1978 | 1978 | 1 | 23 | 237 | 16 | 37 | 26.5 | -5.5 | 5144.5 |
| 1/24/1978 | 1978 | 1 | 24 | 238 | 8 | 35 | 21.5 | -10.5 | 5134 |
| 1/25/1978 | 1978 | 1 | 25 | 239 | 6 | 36 | 21 | -11 | 5123 |
| 1/26/1978 | 1978 | 1 | 26 | 240 | 10 | 42 | 26 | -6 | 5117 |
| 1/27/1978 | 1978 | 1 | 27 | 241 | 12 | 43 | 27.5 | -4.5 | 5112.5 |
| 1/28/1978 | 1978 | 1 | 28 | 242 | 19 | 39 | 29 | -3 | 5109.5 |
| 1/29/1978 | 1978 | 1 | 29 | 243 | 20 | 40 | 30 | -2 | 5107.5 |
| 1/30/1978 | 1978 | 1 | 30 | 244 | 20 | 42 | 31 | -1 | 5106.5 |
| 1/31/1978 | 1978 | 1 | 31 | 245 | 23 | 40 | 31.5 | -0.5 | 5106 |
| 2/1/1978 | 1978 | 2 | 1 | 246 | 29 | 40 | 34.5 | 2.5 | 5108.5 |
| 2/2/1978 | 1978 | 2 | 2 | 247 | 21 | 44 | 32.5 | 0.5 | 5109 |
| 2/3/1978 | 1978 | 2 | 3 | 248 | 22 | 44 | 33 | 1 | 5110 |
| 2/4/1978 | 1978 | 2 | 4 | 249 | 19 | 42 | 30.5 | -1.5 | 5108.5 |
| 2/5/1978 | 1978 | 2 | 5 | 250 | 26 | 45 | 35.5 | 3.5 | 5112 |
| 2/6/1978 | 1978 | 2 | 6 | 251 | 27 | 43 | 35 | 3 | 5115 |
| 2/7/1978 | 1978 | 2 | 7 | 252 | 31 | 42 | 36.5 | 4.5 | 5119.5 |
| 2/8/1978 | 1978 | 2 | 8 | 253 | 30 | 45 | 37.5 | 5.5 | 5125 |
| 2/9/1978 | 1978 | 2 | 9 | 254 | 21 | 42 | 31.5 | -0.5 | 5124.5 |
| 2/10/1978 | 1978 | 2 | 10 | 255 | 30 | 49 | 39.5 | 7.5 | 5132 |
| 2/11/1978 | 1978 | 2 | 11 | 256 | 9 | 38 | 23.5 | -8.5 | 5123.5 |
| 2/12/1978 | 1978 | 2 | 12 | 257 | 10 | 30 | 20 | -12 | 5111.5 |
| 2/13/1978 | 1978 | 2 | 13 | 258 | 10 | 27 | 18.5 | -13.5 | 5098 |
| 2/14/1978 | 1978 | 2 | 14 | 259 | 11 | 25 | 18 | -14 | 5084 |
| 2/15/1978 | 1978 | 2 | 15 | 260 | 13 | 39 | 26 | -6 | 5078 |
| 2/16/1978 | 1978 | 2 | 16 | 261 | 19 | 32 | 25.5 | -6.5 | 5071.5 |
| 2/17/1978 | 1978 | 2 | 17 | 262 | 11 | 32 | 21.5 | -10.5 | 5061 |
| 2/18/1978 | 1978 | 2 | 18 | 263 | -6 | 30 | 12 | -20 | 5041 |
| 2/19/1978 | 1978 | 2 | 19 | 264 | 6 | 32 | 19 | -13 | 5028 |
| 2/20/1978 | 1978 | 2 | 20 | 265 | 12 | 39 | 25.5 | -6.5 | 5021.5 |
| 2/21/1978 | 1978 | 2 | 21 | 266 | 21 | 40 | 30.5 | -1.5 | 5020 |
| 2/22/1978 | 1978 | 2 | 22 | 267 | 21 | 46 | 33.5 | 1.5 | 5021.5 |
| 2/23/1978 | 1978 | 2 | 23 | 268 | 22 | 49 | 35.5 | 3.5 | 5025 |
| 2/24/1978 | 1978 | 2 | 24 | 269 | 25 | 50 | 37.5 | 5.5 | 5030.5 |
| 2/25/1978 | 1978 | 2 | 25 | 270 | 26 | 51 | 38.5 | 6.5 | 5037 |
| 2/26/1978 | 1978 | 2 | 26 | 271 | 22 | 50 | 36 | 4 | 5041 |
| 2/27/1978 | 1978 | 2 | 27 | 272 | 26 | 49 | 37.5 | 5.5 | 5046.5 |
| 2/28/1978 | 1978 | 2 | 28 | 273 | 30 | 40 | 35 | 3 | 5049.5 |
| 3/1/1978 | 1978 | 3 | 1 | 274 | 30 | 45 | 37.5 | 5.5 | 5055 |
| 3/2/1978 | 1978 | 3 | 2 | 275 | 32 | 45 | 38.5 | 6.5 | 5061.5 |
| 3/3/1978 | 1978 | 3 | 3 | 276 | 33 | 44 | 38.5 | 6.5 | 5068 |
| 3/4/1978 | 1978 | 3 | 4 | 277 | 29 | 49 | 39 | 7 | 5075 |
| 3/5/1978 | 1978 | 3 | 5 | 278 | 28 | 48 | 38 | 6 | 5081 |
| 3/6/1978 | 1978 | 3 | 6 | 279 | 37 | 45 | 41 | 9 | 5090 |
| 3/7/1978 | 1978 | 3 | 7 | 280 | 28 | 47 | 37.5 | 5.5 | 5095.5 |
| 3/8/1978 | 1978 | 3 | 8 | 281 | 27 | 48 | 37.5 | 5.5 | 5101 |
| 3/9/1978 | 1978 | 3 | 9 | 282 | 29 | 50 | 39.5 | 7.5 | 5108.5 |
| 3/10/1978 | 1978 | 3 | 10 | 283 | 30 | 50 | 40 | 8 | 5116.5 |
| 3/11/1978 | 1978 | 3 | 11 | 284 | 29 | 48 | 38.5 | 6.5 | 5123 |
| 3/12/1978 | 1978 | 3 | 12 | 285 | 28 | 47 | 37.5 | 5.5 | 5128.5 |
| 3/13/1978 | 1978 | 3 | 13 | 286 | 25 | 45 | 35 | 3 | 5131.5 |
| 3/14/1978 | 1978 | 3 | 14 | 287 | 26 | 46 | 36 | 4 | 5135.5 |
| 3/15/1978 | 1978 | 3 | 15 | 288 | 19 | 44 | 31.5 | -0.5 | 5135 |
| 3/16/1978 | 1978 | 3 | 16 | 289 | 20 | 49 | 34.5 | 2.5 | 5137.5 |
| 3/17/1978 | 1978 | 3 | 17 | 290 | 28 | 49 | 38.5 | 6.5 | 5144 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/18/1978 | 1978 | 3 | 18 | 291 | 31 | 50 | 40.5 | 8.5 | 5152.5 |
| 3/19/1978 | 1978 | 3 | 19 | 292 | 39 | 66 | 52.5 | 20.5 | 5173 |
| 3/20/1978 | 1978 | 3 | 20 | 293 | 35 | 61 | 48 | 16 | 5189 |
| 3/21/1978 | 1978 | 3 | 21 | 294 | 32 | 65 | 48.5 | 16.5 | 5205.5 |
| 3/22/1978 | 1978 | 3 | 22 | 295 | 37 | 60 | 48.5 | 16.5 | 5222 |
| 3/23/1978 | 1978 | 3 | 23 | 296 | 34 | 56 | 45 | 13 | 5235 |
| 3/24/1978 | 1978 | 3 | 24 | 297 | 33 | 59 | 46 | 14 | 5249 |
| 3/25/1978 | 1978 | 3 | 25 | 298 | 29 | 60 | 44.5 | 12.5 | 5261.5 |
| 3/26/1978 | 1978 | 3 | 26 | 299 | 36 | 60 | 48 | 16 | 5277.5 |
| 3/27/1978 | 1978 | 3 | 27 | 300 | 35 | 65 | 50 | 18 | 5295.5 |
| 3/28/1978 | 1978 | 3 | 28 | 301 | 34 | 69 | 51.5 | 19.5 | 5315 |
| 3/29/1978 | 1978 | 3 | 29 | 302 | 39 | 66 | 52.5 | 20.5 | 5335.5 |
| 3/30/1978 | 1978 | 3 | 30 | 303 | 34 | 67 | 50.5 | 18.5 | 5354 |
| 3/31/1978 | 1978 | 3 | 31 | 304 | 36 | 69 | 52.5 | 20.5 | 5374.5 |
| 4/1/1978 | 1978 | 4 | 1 | 305 | 28 | 65 | 46.5 | 14.5 | 5389 |
| 4/2/1978 | 1978 | 4 | 2 | 306 | 27 | 59 | 43 | 11 | 5400 |
| 4/3/1978 | 1978 | 4 | 3 | 307 | 26 | 58 | 42 | 10 | 5410 |
| 4/4/1978 | 1978 | 4 | 4 | 308 | 27 | 57 | 42 | 10 | 5420 |
| 4/5/1978 | 1978 | 4 | 5 | 309 | 29 | 58 | 43.5 | 11.5 | 5431.5 |
| 4/6/1978 | 1978 | 4 | 6 | 310 | 29 | 60 | 44.5 | 12.5 | 5444 |
| 4/7/1978 | 1978 | 4 | 7 | 311 | 27 | 69 | 48 | 16 | 5460 |
| 4/8/1978 | 1978 | 4 | 8 | 312 | 29 | 69 | 49 | 17 | 5477 |
| 4/9/1978 | 1978 | 4 | 9 | 313 | 33 | 70 | 51.5 | 19.5 | 5496.5 |
| 4/10/1978 | 1978 | 4 | 10 | 314 | 21 | 59 | 40 | 8 | 5504.5 |
| 4/11/1978 | 1978 | 4 | 11 | 315 | 29 | 57 | 43 | 11 | 5515.5 |
| 4/12/1978 | 1978 | 4 | 12 | 316 | 29 | 68 | 48.5 | 16.5 | 5532 |
| 4/13/1978 | 1978 | 4 | 13 | 317 | 37 | 69 | 53 | 21 | 5553 |
| 4/14/1978 | 1978 | 4 | 14 | 318 | 58 | 66 | 62 | 30 | 5583 |
| 4/15/1978 | 1978 | 4 | 15 | 319 | 41 | 64 | 52.5 | 20.5 | 5603.5 |
| 4/16/1978 | 1978 | 4 | 16 | 320 | 33 | 66 | 49.5 | 17.5 | 5621 |
| 4/17/1978 | 1978 | 4 | 17 | 321 | 47 | 65 | 56 | 24 | 5645 |
| 4/18/1978 | 1978 | 4 | 18 | 322 | 29 | 59 | 44 | 12 | 5657 |
| 4/19/1978 | 1978 | 4 | 19 | 323 | 23 | 60 | 41.5 | 9.5 | 5666.5 |
| 4/20/1978 | 1978 | 4 | 20 | 324 | 30 | 66 | 48 | 16 | 5682.5 |
| 4/21/1978 | 1978 | 4 | 21 | 325 | 34 | 65 | 49.5 | 17.5 | 5700 |
| 4/22/1978 | 1978 | 4 | 22 | 326 | 37 | 64 | 50.5 | 18.5 | 5718.5 |
| 4/23/1978 | 1978 | 4 | 23 | 327 | 25 | 60 | 42.5 | 10.5 | 5729 |
| 4/24/1978 | 1978 | 4 | 24 | 328 | 30 | 69 | 49.5 | 17.5 | 5746.5 |
| 4/25/1978 | 1978 | 4 | 25 | 329 | 38 | 75 | 56.5 | 24.5 | 5771 |
| 4/26/1978 | 1978 | 4 | 26 | 330 | 44 | 74 | 59 | 27 | 5798 |
| 4/27/1978 | 1978 | 4 | 27 | 331 | 43 | 76 | 59.5 | 27.5 | 5825.5 |
| 4/28/1978 | 1978 | 4 | 28 | 332 | 41 | 74 | 57.5 | 25.5 | 5851 |
| 4/29/1978 | 1978 | 4 | 29 | 333 | 37 | 62 | 49.5 | 17.5 | 5868.5 |
| 4/30/1978 | 1978 | 4 | 30 | 334 | 36 | 65 | 50.5 | 18.5 | 5887 |
| 5/1/1978 | 1978 | 5 | 1 | 335 | 37 | 65 | 51 | 19 | 5906 |
| 5/2/1978 | 1978 | 5 | 2 | 336 | 38 | 67 | 52.5 | 20.5 | 5926.5 |
| 5/3/1978 | 1978 | 5 | 3 | 337 | 22 | 65 | 43.5 | 11.5 | 5938 |
| 5/4/1978 | 1978 | 5 | 4 | 338 | 38 | 62 | 50 | 18 | 5956 |
| 5/5/1978 | 1978 | 5 | 5 | 339 | 36 | 59 | 47.5 | 15.5 | 5971.5 |
| 5/6/1978 | 1978 | 5 | 6 | 340 | 33 | 60 | 46.5 | 14.5 | 5986 |
| 5/7/1978 | 1978 | 5 | 7 | 341 | 27 | 40 | 33.5 | 1.5 | 5987.5 |
| 5/8/1978 | 1978 | 5 | 8 | 342 | 30 | 53 | 41.5 | 9.5 | 5997 |
| 5/9/1978 | 1978 | 5 | 9 | 343 | 29 | 50 | 39.5 | 7.5 | 6004.5 |
| 5/10/1978 | 1978 | 5 | 10 | 344 | 35 | 58 | 46.5 | 14.5 | 6019 |
| 5/11/1978 | 1978 | 5 | 11 | 345 | 35 | 59 | 47 | 15 | 6034 |
| 5/12/1978 | 1978 | 5 | 12 | 346 | 41 | 61 | 51 | 19 | 6053 |
| 5/13/1978 | 1978 | 5 | 13 | 347 | 41 | 69 | 55 | 23 | 6076 |
| 5/14/1978 | 1978 | 5 | 14 | 348 | 43 | 70 | 56.5 | 24.5 | 6100.5 |
| 5/15/1978 | 1978 | 5 | 15 | 349 | 46 | 72 | 59 | 27 | 6127.5 |
| 5/16/1978 | 1978 | 5 | 16 | 350 | 40 | 79 | 59.5 | 27.5 | 6155 |
| 5/17/1978 | 1978 | 5 | 17 | 351 | 41 | 80 | 60.5 | 28.5 | 6183.5 |
| 5/18/1978 | 1978 | 5 | 18 | 352 | 51 | 81 | 66 | 34 | 6217.5 |
| 5/19/1978 | 1978 | 5 | 19 | 353 | 44 | 79 | 61.5 | 29.5 | 6247 |
| 5/20/1978 | 1978 | 5 | 20 | 354 | 34 | 77 | 55.5 | 23.5 | 6270.5 |
| 5/21/1978 | 1978 | 5 | 21 | 355 | 33 | 69 | 51 | 19 | 6289.5 |
| 5/22/1978 | 1978 | 5 | 22 | 356 | 43 | 70 | 56.5 | 24.5 | 6314 |
| 5/23/1978 | 1978 | 5 | 23 | 357 | 42 | 73 | 57.5 | 25.5 | 6339.5 |
| 5/24/1978 | 1978 | 5 | 24 | 358 | 37 | 70 | 53.5 | 21.5 | 6361 |
| 5/25/1978 | 1978 | 5 | 25 | 359 | 42 | 70 | 56 | 24 | 6385 |
| 5/26/1978 | 1978 | 5 | 26 | 360 | 47 | 71 | 59 | 27 | 6412 |
| 5/27/1978 | 1978 | 5 | 27 | 361 | 43 | 75 | 59 | 27 | 6439 |
| 5/28/1978 | 1978 | 5 | 28 | 362 | 40 | 74 | 57 | 25 | 6464 |
| 5/29/1978 | 1978 | 5 | 29 | 363 | 42 | 73 | 57.5 | 25.5 | 6489.5 |
| 5/30/1978 | 1978 | 5 | 30 | 364 | 41 | 74 | 57.5 | 25.5 | 6515 |
| 5/31/1978 | 1978 | 5 | 31 | 365 | 42 | 75 | 58.5 | 26.5 | 6541.5 |
| 6/1/1978 | 1978 | 6 | 1 | 1 | 48 | 80 | 64 | 32 | 32 |
| 6/2/1978 | 1978 | 6 | 2 | 2 | 44 | 79 | 61.5 | 29.5 | 61.5 |
| 6/3/1978 | 1978 | 6 | 3 | 3 | 45 | 80 | 62.5 | 30.5 | 92 |
| 6/4/1978 | 1978 | 6 | 4 | 4 | 46 | 81 | 63.5 | 31.5 | 123.5 |
| 6/5/1978 | 1978 | 6 | 5 | 5 | 47 | 80 | 63.5 | 31.5 | 155 |
| 6/6/1978 | 1978 | 6 | 6 | 6 | 41 | 77 | 59 | 27 | 182 |
| 6/7/1978 | 1978 | 6 | 7 | 7 | 44 | 79 | 61.5 | 29.5 | 211.5 |
| 6/8/1978 | 1978 | 6 | 8 | 8 | 48 | 80 | 64 | 32 | 243.5 |
| 6/9/1978 | 1978 | 6 | 9 | 9 | 47 | 82 | 64.5 | 32.5 | 276 |
| 6/10/1978 | 1978 | 6 | 10 | 10 | 46 | 80 | 63 | 31 | 307 |
| 6/11/1978 | 1978 | 6 | 11 | 11 | 45 | 80 | 62.5 | 30.5 | 337.5 |
| 6/12/1978 | 1978 | 6 | 12 | 12 | 49 | 78 | 63.5 | 31.5 | 369 |
| 6/13/1978 | 1978 | 6 | 13 | 13 | 50 | 80 | 65 | 33 | 402 |
| 6/14/1978 | 1978 | 6 | 14 | 14 | 55 | 83 | 69 | 37 | 439 |
| 6/15/1978 | 1978 | 6 | 15 | 15 | 56 | 86 | 71 | 39 | 478 |
| 6/16/1978 | 1978 | 6 | 16 | 16 | 51 | 85 | 68 | 36 | 514 |
| 6/17/1978 | 1978 | 6 | 17 | 17 | 52 | 85 | 68.5 | 36.5 | 550.5 |
| 6/18/1978 | 1978 | 6 | 18 | 18 | 60 | 80 | 70 | 38 | 588.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/19/1978 | 1978 | 6 | 19 | 19 | 58 | 87 | 72.5 | 40.5 | 629 |
| 6/20/1978 | 1978 | 6 | 20 | 20 | 54 | 85 | 69.5 | 37.5 | 666.5 |
| 6/21/1978 | 1978 | 6 | 21 | 21 | 53 | 87 | 70 | 38 | 704.5 |
| 6/22/1978 | 1978 | 6 | 22 | 22 | 56 | 86 | 71 | 39 | 743.5 |
| 6/23/1978 | 1978 | 6 | 23 | 23 | 59 | 87 | 73 | 41 | 784.5 |
| 6/24/1978 | 1978 | 6 | 24 | 24 | 58 | 90 | 74 | 42 | 826.5 |
| 6/25/1978 | 1978 | 6 | 25 | 25 | 59 | 90 | 74.5 | 42.5 | 869 |
| 6/26/1978 | 1978 | 6 | 26 | 26 | 68 | 89 | 78.5 | 46.5 | 915.5 |
| 6/27/1978 | 1978 | 6 | 27 | 27 | 55 | 86 | 70.5 | 38.5 | 954 |
| 6/28/1978 | 1978 | 6 | 28 | 28 | 54 | 84 | 69 | 37 | 991 |
| 6/29/1978 | 1978 | 6 | 29 | 29 | 53 | 77 | 65 | 33 | 1024 |
| 6/30/1978 | 1978 | 6 | 30 | 30 | 54 | 80 | 67 | 35 | 1059 |
| 7/1/1978 | 1978 | 7 | 1 | 31 | 52 | 83 | 67.5 | 35.5 | 1094.5 |
| 7/2/1978 | 1978 | 7 | 2 | 32 | 53 | 90 | 71.5 | 39.5 | 1134 |
| 7/3/1978 | 1978 | 7 | 3 | 33 | 54 | 89 | 71.5 | 39.5 | 1173.5 |
| 7/4/1978 | 1978 | 7 | 4 | 34 | 55 | 83 | 69 | 37 | 1210.5 |
| 7/5/1978 | 1978 | 7 | 5 | 35 | 54 | 80 | 67 | 35 | 1245.5 |
| 7/6/1978 | 1978 | 7 | 6 | 36 | 52 | 87 | 69.5 | 37.5 | 1283 |
| 7/7/1978 | 1978 | 7 | 7 | 37 | 52 | 84 | 68 | 36 | 1319 |
| 7/8/1978 | 1978 | 7 | 8 | 38 | 55 | 90 | 72.5 | 40.5 | 1359.5 |
| 7/9/1978 | 1978 | 7 | 9 | 39 | 54 | 87 | 70.5 | 38.5 | 1398 |
| 7/10/1978 | 1978 | 7 | 10 | 40 | 60 | 86 | 73 | 41 | 1439 |
| 7/11/1978 | 1978 | 7 | 11 | 41 | 55 | 83 | 69 | 37 | 1476 |
| 7/12/1978 | 1978 | 7 | 12 | 42 | 54 | 84 | 69 | 37 | 1513 |
| 7/13/1978 | 1978 | 7 | 13 | 43 | 57 | 85 | 71 | 39 | 1552 |
| 7/14/1978 | 1978 | 7 | 14 | 44 | 59 | 87 | 73 | 41 | 1593 |
| 7/15/1978 | 1978 | 7 | 15 | 45 | 54 | 88 | 71 | 39 | 1632 |
| 7/16/1978 | 1978 | 7 | 16 | 46 | 59 | 90 | 74.5 | 42.5 | 1674.5 |
| 7/17/1978 | 1978 | 7 | 17 | 47 | 64 | 90 | 77 | 45 | 1719.5 |
| 7/18/1978 | 1978 | 7 | 18 | 48 | 57 | 88 | 72.5 | 40.5 | 1760 |
| 7/19/1978 | 1978 | 7 | 19 | 49 | 56 | 78 | 67 | 35 | 1795 |
| 7/20/1978 | 1978 | 7 | 20 | 50 | 56 | 88 | 72 | 40 | 1835 |
| 7/21/1978 | 1978 | 7 | 21 | 51 | 58 | 87 | 72.5 | 40.5 | 1875.5 |
| 7/22/1978 | 1978 | 7 | 22 | 52 | 56 | 89 | 72.5 | 40.5 | 1916 |
| 7/23/1978 | 1978 | 7 | 23 | 53 | 55 | 80 | 67.5 | 35.5 | 1951.5 |
| 7/24/1978 | 1978 | 7 | 24 | 54 | 54 | 81 | 67.5 | 35.5 | 1987 |
| 7/25/1978 | 1978 | 7 | 25 | 55 | 56 | 89 | 72.5 | 40.5 | 2027.5 |
| 7/26/1978 | 1978 | 7 | 26 | 56 | 57 | 88 | 72.5 | 40.5 | 2068 |
| 7/27/1978 | 1978 | 7 | 27 | 57 | 57 | 86 | 71.5 | 39.5 | 2107.5 |
| 7/28/1978 | 1978 | 7 | 28 | 58 | 60 | 89 | 74.5 | 42.5 | 2150 |
| 7/29/1978 | 1978 | 7 | 29 | 59 | 56 | 89 | 72.5 | 40.5 | 2190.5 |
| 7/30/1978 | 1978 | 7 | 30 | 60 | 59 | 85 | 72 | 40 | 2230.5 |
| 7/31/1978 | 1978 | 7 | 31 | 61 | 61 | 85 | 73 | 41 | 2271.5 |
| 8/1/1978 | 1978 | 8 | 1 | 62 | 56 | 88 | 72 | 40 | 2311.5 |
| 8/2/1978 | 1978 | 8 | 2 | 63 | 55 | 81 | 68 | 36 | 2347.5 |
| 8/3/1978 | 1978 | 8 | 3 | 64 | 56 | 81 | 68.5 | 36.5 | 2384 |
| 8/4/1978 | 1978 | 8 | 4 | 65 | 53 | 83 | 68 | 36 | 2420 |
| 8/5/1978 | 1978 | 8 | 5 | 66 | 47 | 75 | 61 | 29 | 2449 |
| 8/6/1978 | 1978 | 8 | 6 | 67 | 50 | 79 | 64.5 | 32.5 | 2481.5 |
| 8/7/1978 | 1978 | 8 | 7 | 68 | 55 | 80 | 67.5 | 35.5 | 2517 |
| 8/8/1978 | 1978 | 8 | 8 | 69 | 52 | 81 | 66.5 | 34.5 | 2551.5 |
| 8/9/1978 | 1978 | 8 | 9 | 70 | 50 | 82 | 66 | 34 | 2585.5 |
| 8/10/1978 | 1978 | 8 | 10 | 71 | 54 | 84 | 69 | 37 | 2622.5 |
| 8/11/1978 | 1978 | 8 | 11 | 72 | 53 | 85 | 69 | 37 | 2659.5 |
| 8/12/1978 | 1978 | 8 | 12 | 73 | 52 | 79 | 65.5 | 33.5 | 2693 |
| 8/13/1978 | 1978 | 8 | 13 | 74 | 54 | 76 | 65 | 33 | 2726 |
| 8/14/1978 | 1978 | 8 | 14 | 75 | 53 | 70 | 61.5 | 29.5 | 2755.5 |
| 8/15/1978 | 1978 | 8 | 15 | 76 | 49 | 79 | 64 | 32 | 2787.5 |
| 8/16/1978 | 1978 | 8 | 16 | 77 | 48 | 79 | 63.5 | 31.5 | 2819 |
| 8/17/1978 | 1978 | 8 | 17 | 78 | 55 | 79 | 67 | 35 | 2854 |
| 8/18/1978 | 1978 | 8 | 18 | 79 | 56 | 79 | 67.5 | 35.5 | 2889.5 |
| 8/19/1978 | 1978 | 8 | 19 | 80 | 54 | 80 | 67 | 35 | 2924.5 |
| 8/20/1978 | 1978 | 8 | 20 | 81 | 54 | 76 | 65 | 33 | 2957.5 |
| 8/21/1978 | 1978 | 8 | 21 | 82 | 53 | 75 | 64 | 32 | 2989.5 |
| 8/22/1978 | 1978 | 8 | 22 | 83 | 49 | 78 | 63.5 | 31.5 | 3021 |
| 8/23/1978 | 1978 | 8 | 23 | 84 | 49 | 76 | 62.5 | 30.5 | 3051.5 |
| 8/24/1978 | 1978 | 8 | 24 | 85 | 52 | 79 | 65.5 | 33.5 | 3085 |
| 8/25/1978 | 1978 | 8 | 25 | 86 | 49 | 78 | 63.5 | 31.5 | 3116.5 |
| 8/26/1978 | 1978 | 8 | 26 | 87 | 54 | 80 | 67 | 35 | 3151.5 |
| 8/27/1978 | 1978 | 8 | 27 | 88 | 52 | 81 | 66.5 | 34.5 | 3186 |
| 8/28/1978 | 1978 | 8 | 28 | 89 | 49 | 82 | 65.5 | 33.5 | 3219.5 |
| 8/29/1978 | 1978 | 8 | 29 | 90 | 57 | 82 | 69.5 | 37.5 | 3257 |
| 8/30/1978 | 1978 | 8 | 30 | 91 | 44 | 79 | 61.5 | 29.5 | 3286.5 |
| 8/31/1978 | 1978 | 8 | 31 | 92 | 56 | 79 | 67.5 | 35.5 | 3322 |
| 9/1/1978 | 1978 | 9 | 1 | 93 | 51 | 76 | 63.5 | 31.5 | 3353.5 |
| 9/2/1978 | 1978 | 9 | 2 | 94 | 53 | 79 | 66 | 34 | 3387.5 |
| 9/3/1978 | 1978 | 9 | 3 | 95 | 48 | 78 | 63 | 31 | 3418.5 |
| 9/4/1978 | 1978 | 9 | 4 | 96 | 50 | 80 | 65 | 33 | 3451.5 |
| 9/5/1978 | 1978 | 9 | 5 | 97 | 55 | 80 | 67.5 | 35.5 | 3487 |
| 9/6/1978 | 1978 | 9 | 6 | 98 | 53 | 77 | 65 | 33 | 3520 |
| 9/7/1978 | 1978 | 9 | 7 | 99 | 50 | 75 | 62.5 | 30.5 | 3550.5 |
| 9/8/1978 | 1978 | 9 | 8 | 100 | 49 | 77 | 63 | 31 | 3581.5 |
| 9/9/1978 | 1978 | 9 | 9 | 101 | 48 | 78 | 63 | 31 | 3612.5 |
| 9/10/1978 | 1978 | 9 | 10 | 102 | 55 | 79 | 67 | 35 | 3647.5 |
| 9/11/1978 | 1978 | 9 | 11 | 103 | 54 | 79 | 66.5 | 34.5 | 3682 |
| 9/12/1978 | 1978 | 9 | 12 | 104 | 52 | 76 | 64 | 32 | 3714 |
| 9/13/1978 | 1978 | 9 | 13 | 105 | 49 | 72 | 60.5 | 28.5 | 3742.5 |
| 9/14/1978 | 1978 | 9 | 14 | 106 | 45 | 70 | 57.5 | 25.5 | 3768 |
| 9/15/1978 | 1978 | 9 | 15 | 107 | 48 | 71 | 59.5 | 27.5 | 3795.5 |
| 9/16/1978 | 1978 | 9 | 16 | 108 | 47 | 71 | 59 | 27 | 3822.5 |
| 9/17/1978 | 1978 | 9 | 17 | 109 | 43 | 72 | 57.5 | 25.5 | 3848 |
| 9/18/1978 | 1978 | 9 | 18 | 110 | 47 | 74 | 60.5 | 28.5 | 3876.5 |
| 9/19/1978 | 1978 | 9 | 19 | 111 | 43 | 72 | 57.5 | 25.5 | 3902 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/20/1978 | 1978 | 9 | 20 | 112 | 34 | 69 | 51.5 | 19.5 | 3921.5 |
| 9/21/1978 | 1978 | 9 | 21 | 113 | 33 | 66 | 49.5 | 17.5 | 3939 |
| 9/22/1978 | 1978 | 9 | 22 | 114 | 39 | 68 | 53.5 | 21.5 | 3960.5 |
| 9/23/1978 | 1978 | 9 | 23 | 115 | 43 | 66 | 54.5 | 22.5 | 3983 |
| 9/24/1978 | 1978 | 9 | 24 | 116 | 49 | 63 | 56 | 24 | 4007 |
| 9/25/1978 | 1978 | 9 | 25 | 117 | 47 | 61 | 54 | 22 | 4029 |
| 9/26/1978 | 1978 | 9 | 26 | 118 | 42 | 70 | 56 | 24 | 4053 |
| 9/27/1978 | 1978 | 9 | 27 | 119 | 44 | 72 | 58 | 26 | 4079 |
| 9/28/1978 | 1978 | 9 | 28 | 120 | 44 | 74 | 59 | 27 | 4106 |
| 9/29/1978 | 1978 | 9 | 29 | 121 | 49 | 72 | 60.5 | 28.5 | 4134.5 |
| 9/30/1978 | 1978 | 9 | 30 | 122 | 45 | 76 | 60.5 | 28.5 | 4163 |
| 10/1/1978 | 1978 | 10 | 1 | 123 | 50 | 78 | 64 | 32 | 4195 |
| 10/2/1978 | 1978 | 10 | 2 | 124 | 49 | 78 | 63.5 | 31.5 | 4226.5 |
| 10/3/1978 | 1978 | 10 | 3 | 125 | 44 | 74 | 59 | 27 | 4253.5 |
| 10/4/1978 | 1978 | 10 | 4 | 126 | 43 | 72 | 57.5 | 25.5 | 4279 |
| 10/5/1978 | 1978 | 10 | 5 | 127 | 42 | 73 | 57.5 | 25.5 | 4304.5 |
| 10/6/1978 | 1978 | 10 | 6 | 128 | 38 | 72 | 55 | 23 | 4327.5 |
| 10/7/1978 | 1978 | 10 | 7 | 129 | 43 | 74 | 58.5 | 26.5 | 4354 |
| 10/8/1978 | 1978 | 10 | 8 | 130 | 42 | 70 | 56 | 24 | 4378 |
| 10/9/1978 | 1978 | 10 | 9 | 131 | 43 | 72 | 57.5 | 25.5 | 4403.5 |
| 10/10/1978 | 1978 | 10 | 10 | 132 | 46 | 75 | 60.5 | 28.5 | 4432 |
| 10/11/1978 | 1978 | 10 | 11 | 133 | 43 | 70 | 56.5 | 24.5 | 4456.5 |
| 10/12/1978 | 1978 | 10 | 12 | 134 | 44 | 71 | 57.5 | 25.5 | 4482 |
| 10/13/1978 | 1978 | 10 | 13 | 135 | 39 | 70 | 54.5 | 22.5 | 4504.5 |
| 10/14/1978 | 1978 | 10 | 14 | 136 | 35 | 69 | 52 | 20 | 4524.5 |
| 10/15/1978 | 1978 | 10 | 15 | 137 | 39 | 70 | 54.5 | 22.5 | 4547 |
| 10/16/1978 | 1978 | 10 | 16 | 138 | 38 | 72 | 55 | 23 | 4570 |
| 10/17/1978 | 1978 | 10 | 17 | 139 | 36 | 70 | 53 | 21 | 4591 |
| 10/18/1978 | 1978 | 10 | 18 | 140 | 44 | 69 | 56.5 | 24.5 | 4615.5 |
| 10/19/1978 | 1978 | 10 | 19 | 141 | 43 | 67 | 55 | 23 | 4638.5 |
| 10/20/1978 | 1978 | 10 | 20 | 142 | 42 | 65 | 53.5 | 21.5 | 4660 |
| 10/21/1978 | 1978 | 10 | 21 | 143 | 38 | 69 | 53.5 | 21.5 | 4681.5 |
| 10/22/1978 | 1978 | 10 | 22 | 144 | 36 | 60 | 48 | 16 | 4697.5 |
| 10/23/1978 | 1978 | 10 | 23 | 145 | 39 | 59 | 49 | 17 | 4714.5 |
| 10/24/1978 | 1978 | 10 | 24 | 146 | 38 | 50 | 44 | 12 | 4726.5 |
| 10/25/1978 | 1978 | 10 | 25 | 147 | 40 | 54 | 47 | 15 | 4741.5 |
| 10/26/1978 | 1978 | 10 | 26 | 148 | 27 | 50 | 38.5 | 6.5 | 4748 |
| 10/27/1978 | 1978 | 10 | 27 | 149 | 29 | 56 | 42.5 | 10.5 | 4758.5 |
| 10/28/1978 | 1978 | 10 | 28 | 150 | 29 | 58 | 43.5 | 11.5 | 4770 |
| 10/29/1978 | 1978 | 10 | 29 | 151 | 36 | 59 | 47.5 | 15.5 | 4785.5 |
| 10/30/1978 | 1978 | 10 | 30 | 152 | 32 | 58 | 45 | 13 | 4798.5 |
| 10/31/1978 | 1978 | 10 | 31 | 153 | 32 | 58 | 45 | 13 | 4811.5 |
| 11/1/1978 | 1978 | 11 | 1 | 154 | 45 | 59 | 52 | 20 | 4831.5 |
| 11/2/1978 | 1978 | 11 | 2 | 155 | 40 | 58 | 49 | 17 | 4848.5 |
| 11/3/1978 | 1978 | 11 | 3 | 156 | 32 | 55 | 43.5 | 11.5 | 4860 |
| 11/4/1978 | 1978 | 11 | 4 | 157 | 33 | 56 | 44.5 | 12.5 | 4872.5 |
| 11/5/1978 | 1978 | 11 | 5 | 158 | 32 | 52 | 42 | 10 | 4882.5 |
| 11/6/1978 | 1978 | 11 | 6 | 159 | 35 | 52 | 43.5 | 11.5 | 4894 |
| 11/7/1978 | 1978 | 11 | 7 | 160 | 32 | 56 | 44 | 12 | 4906 |
| 11/8/1978 | 1978 | 11 | 8 | 161 | 34 | 59 | 46.5 | 14.5 | 4920.5 |
| 11/9/1978 | 1978 | 11 | 9 | 162 | 36 | 60 | 48 | 16 | 4936.5 |
| 11/10/1978 | 1978 | 11 | 10 | 163 | 34 | 60 | 47 | 15 | 4951.5 |
| 11/11/1978 | 1978 | 11 | 11 | 164 | 39 | 59 | 49 | 17 | 4968.5 |
| 11/12/1978 | 1978 | 11 | 12 | 165 | 38 | 55 | 46.5 | 14.5 | 4983 |
| 11/13/1978 | 1978 | 11 | 13 | 166 | 36 | 55 | 45.5 | 13.5 | 4996.5 |
| 11/14/1978 | 1978 | 11 | 14 | 167 | 26 | 49 | 37.5 | 5.5 | 5002 |
| 11/15/1978 | 1978 | 11 | 15 | 168 | 29 | 45 | 37 | 5 | 5007 |
| 11/16/1978 | 1978 | 11 | 16 | 169 | 29 | 43 | 36 | 4 | 5011 |
| 11/17/1978 | 1978 | 11 | 17 | 170 | 28 | 40 | 34 | 2 | 5013 |
| 11/18/1978 | 1978 | 11 | 18 | 171 | 20 | 46 | 33 | 1 | 5014 |
| 11/19/1978 | 1978 | 11 | 19 | 172 | 23 | 48 | 35.5 | 3.5 | 5017.5 |
| 11/20/1978 | 1978 | 11 | 20 | 173 | 24 | 49 | 36.5 | 4.5 | 5022 |
| 11/21/1978 | 1978 | 11 | 21 | 174 | 27 | 49 | 38 | 6 | 5028 |
| 11/22/1978 | 1978 | 11 | 22 | 175 | 31 | 47 | 39 | 7 | 5035 |
| 11/23/1978 | 1978 | 11 | 23 | 176 | 30 | 46 | 38 | 6 | 5041 |
| 11/24/1978 | 1978 | 11 | 24 | 177 | 29 | 44 | 36.5 | 4.5 | 5045.5 |
| 11/25/1978 | 1978 | 11 | 25 | 178 | 28 | 43 | 35.5 | 3.5 | 5049 |
| 11/26/1978 | 1978 | 11 | 26 | 179 | 26 | 43 | 34.5 | 2.5 | 5051.5 |
| 11/27/1978 | 1978 | 11 | 27 | 180 | 25 | 40 | 32.5 | 0.5 | 5052 |
| 11/28/1978 | 1978 | 11 | 28 | 181 | 26 | 39 | 32.5 | 0.5 | 5052.5 |
| 11/29/1978 | 1978 | 11 | 29 | 182 | 25 | 39 | 32 | 0 | 5052.5 |
| 11/30/1978 | 1978 | 11 | 30 | 183 | 17 | 39 | 28 | -4 | 5048.5 |
| 12/1/1978 | 1978 | 12 | 1 | 184 | 32 | 49 | 40.5 | 8.5 | 5057 |
| 12/2/1978 | 1978 | 12 | 2 | 185 | 30 | 45 | 37.5 | 5.5 | 5062.5 |
| 12/3/1978 | 1978 | 12 | 3 | 186 | 31 | 40 | 35.5 | 3.5 | 5066 |
| 12/4/1978 | 1978 | 12 | 4 | 187 | 9 | 40 | 24.5 | -7.5 | 5058.5 |
| 12/5/1978 | 1978 | 12 | 5 | 188 | 8 | 36 | 22 | -10 | 5048.5 |
| 12/6/1978 | 1978 | 12 | 6 | 189 | 7 | 29 | 18 | -14 | 5034.5 |
| 12/7/1978 | 1978 | 12 | 7 | 190 | -4 | 20 | 8 | -24 | 5010.5 |
| 12/8/1978 | 1978 | 12 | 8 | 191 | -10 | 23 | 6.5 | -25.5 | 4985 |
| 12/9/1978 | 1978 | 12 | 9 | 192 | -9 | 20 | 5.5 | -26.5 | 4958.5 |
| 12/10/1978 | 1978 | 12 | 10 | 193 | 4 | 30 | 17 | -15 | 4943.5 |
| 12/11/1978 | 1978 | 12 | 11 | 194 | 7 | 30 | 18.5 | -13.5 | 4930 |
| 12/12/1978 | 1978 | 12 | 12 | 195 | 10 | 39 | 24.5 | -7.5 | 4922.5 |
| 12/13/1978 | 1978 | 12 | 13 | 196 | 12 | 37 | 24.5 | -7.5 | 4915 |
| 12/14/1978 | 1978 | 12 | 14 | 197 | 15 | 37 | 26 | -6 | 4909 |
| 12/15/1978 | 1978 | 12 | 15 | 198 | 16 | 39 | 27.5 | -4.5 | 4904.5 |
| 12/16/1978 | 1978 | 12 | 16 | 199 | 20 | 38 | 29 | -3 | 4901.5 |
| 12/17/1978 | 1978 | 12 | 17 | 200 | 20 | 39 | 29.5 | -2.5 | 4899 |
| 12/18/1978 | 1978 | 12 | 18 | 201 | 26 | 40 | 33 | 1 | 4900 |
| 12/19/1978 | 1978 | 12 | 19 | 202 | 30 | 39 | 34.5 | 2.5 | 4902.5 |
| 12/20/1978 | 1978 | 12 | 20 | 203 | 19 | 39 | 29 | -3 | 4899.5 |
| 12/21/1978 | 1978 | 12 | 21 | 204 | 16 | 36 | 26 | -6 | 4893.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/22/1978 | 1978 | 12 | 22 | 205 | 18 | 38 | 28 | -4 | 4889.5 |
| 12/23/1978 | 1978 | 12 | 23 | 206 | 16 | 37 | 26.5 | -5.5 | 4884 |
| 12/24/1978 | 1978 | 12 | 24 | 207 | 15 | 35 | 25 | -7 | 4877 |
| 12/25/1978 | 1978 | 12 | 25 | 208 | 14 | 30 | 22 | -10 | 4867 |
| 12/26/1978 | 1978 | 12 | 26 | 209 | 12 | 29 | 20.5 | -11.5 | 4855.5 |
| 12/27/1978 | 1978 | 12 | 27 | 210 | 19 | 29 | 24 | -8 | 4847.5 |
| 12/28/1978 | 1978 | 12 | 28 | 211 | 19 | 38 | 28.5 | -3.5 | 4844 |
| 12/29/1978 | 1978 | 12 | 29 | 212 | 20 | 39 | 29.5 | -2.5 | 4841.5 |
| 12/30/1978 | 1978 | 12 | 30 | 213 | -10 | 39 | 14.5 | -17.5 | 4824 |
| 12/31/1978 | 1978 | 12 | 31 | 214 | -12 | 38 | 13 | -19 | 4805 |
| 1/1/1979 | 1979 | 1 | 1 | 215 | -4 | 34 | 15 | -17 | 4788 |
| 1/2/1979 | 1979 | 1 | 2 | 216 | -5 | 32 | 13.5 | -18.5 | 4769.5 |
| 1/3/1979 | 1979 | 1 | 3 | 217 | -4 | 40 | 18 | -14 | 4755.5 |
| 1/4/1979 | 1979 | 1 | 4 | 218 | 10 | 42 | 26 | -6 | 4749.5 |
| 1/5/1979 | 1979 | 1 | 5 | 219 | 19 | 40 | 29.5 | -2.5 | 4747 |
| 1/6/1979 | 1979 | 1 | 6 | 220 | 18 | 36 | 27 | -5 | 4742 |
| 1/7/1979 | 1979 | 1 | 7 | 221 | 20 | 35 | 27.5 | -4.5 | 4737.5 |
| 1/8/1979 | 1979 | 1 | 8 | 222 | 6 | 32 | 19 | -13 | 4724.5 |
| 1/9/1979 | 1979 | 1 | 9 | 223 | 10 | 31 | 20.5 | -11.5 | 4713 |
| 1/10/1979 | 1979 | 1 | 10 | 224 | 16 | 35 | 25.5 | -6.5 | 4706.5 |
| 1/11/1979 | 1979 | 1 | 11 | 225 | 18 | 40 | 29 | -3 | 4703.5 |
| 1/12/1979 | 1979 | 1 | 12 | 226 | 18 | 43 | 30.5 | -1.5 | 4702 |
| 1/13/1979 | 1979 | 1 | 13 | 227 | 15 | 39 | 27 | -5 | 4697 |
| 1/14/1979 | 1979 | 1 | 14 | 228 | 10 | 30 | 20 | -12 | 4685 |
| 1/15/1979 | 1979 | 1 | 15 | 229 | 7 | 30 | 18.5 | -13.5 | 4671.5 |
| 1/16/1979 | 1979 | 1 | 16 | 230 | 18 | 39 | 28.5 | -3.5 | 4668 |
| 1/17/1979 | 1979 | 1 | 17 | 231 | 19 | 38 | 28.5 | -3.5 | 4664.5 |
| 1/18/1979 | 1979 | 1 | 18 | 232 | 20 | 40 | 30 | -2 | 4662.5 |
| 1/19/1979 | 1979 | 1 | 19 | 233 | 19 | 36 | 27.5 | -4.5 | 4658 |
| 1/20/1979 | 1979 | 1 | 20 | 234 | 18 | 30 | 24 | -8 | 4650 |
| 1/21/1979 | 1979 | 1 | 21 | 235 | 17 | 30 | 23.5 | -8.5 | 4641.5 |
| 1/22/1979 | 1979 | 1 | 22 | 236 | 15 | 39 | 27 | -5 | 4636.5 |
| 1/23/1979 | 1979 | 1 | 23 | 237 | 3 | 30 | 16.5 | -15.5 | 4621 |
| 1/24/1979 | 1979 | 1 | 24 | 238 | 5 | 34 | 19.5 | -12.5 | 4608.5 |
| 1/25/1979 | 1979 | 1 | 25 | 239 | 5 | 30 | 17.5 | -14.5 | 4594 |
| 1/26/1979 | 1979 | 1 | 26 | 240 | 10 | 34 | 22 | -10 | 4584 |
| 1/27/1979 | 1979 | 1 | 27 | 241 | 11 | 25 | 18 | -14 | 4570 |
| 1/28/1979 | 1979 | 1 | 28 | 242 | 0 | 30 | 15 | -17 | 4553 |
| 1/29/1979 | 1979 | 1 | 29 | 243 | 0 | 30 | 15 | -17 | 4536 |
| 1/30/1979 | 1979 | 1 | 30 | 244 | -8 | 20 | 6 | -26 | 4510 |
| 1/31/1979 | 1979 | 1 | 31 | 245 | -2 | 26 | 12 | -20 | 4490 |
| 2/1/1979 | 1979 | 2 | 1 | 246 | 14 | 34 | 24 | -8 | 4482 |
| 2/2/1979 | 1979 | 2 | 2 | 247 | 19 | 30 | 24.5 | -7.5 | 4474.5 |
| 2/3/1979 | 1979 | 2 | 3 | 248 | 18 | 29 | 23.5 | -8.5 | 4466 |
| 2/4/1979 | 1979 | 2 | 4 | 249 | 17 | 29 | 23 | -9 | 4457 |
| 2/5/1979 | 1979 | 2 | 5 | 250 | 15 | 29 | 22 | -10 | 4447 |
| 2/6/1979 | 1979 | 2 | 6 | 251 | 10 | 31 | 20.5 | -11.5 | 4435.5 |
| 2/7/1979 | 1979 | 2 | 7 | 252 | 12 | 30 | 21 | -11 | 4424.5 |
| 2/8/1979 | 1979 | 2 | 8 | 253 | 12 | 36 | 24 | -8 | 4416.5 |
| 2/9/1979 | 1979 | 2 | 9 | 254 | 10 | 30 | 20 | -12 | 4404.5 |
| 2/10/1979 | 1979 | 2 | 10 | 255 | 17 | 36 | 26.5 | -5.5 | 4399 |
| 2/11/1979 | 1979 | 2 | 11 | 256 | 16 | 40 | 28 | -4 | 4395 |
| 2/12/1979 | 1979 | 2 | 12 | 257 | 17 | 43 | 30 | -2 | 4393 |
| 2/13/1979 | 1979 | 2 | 13 | 258 | 18 | 40 | 29 | -3 | 4390 |
| 2/14/1979 | 1979 | 2 | 14 | 259 | 20 | 39 | 29.5 | -2.5 | 4387.5 |
| 2/15/1979 | 1979 | 2 | 15 | 260 | 18 | 40 | 29 | -3 | 4384.5 |
| 2/16/1979 | 1979 | 2 | 16 | 261 | 19 | 40 | 29.5 | -2.5 | 4382 |
| 2/17/1979 | 1979 | 2 | 17 | 262 | 15 | 39 | 27 | -5 | 4377 |
| 2/18/1979 | 1979 | 2 | 18 | 263 | 20 | 40 | 30 | -2 | 4375 |
| 2/19/1979 | 1979 | 2 | 19 | 264 | 30 | 56 | 43 | 11 | 4386 |
| 2/20/1979 | 1979 | 2 | 20 | 265 | 27 | 53 | 40 | 8 | 4394 |
| 2/21/1979 | 1979 | 2 | 21 | 266 | 28 | 50 | 39 | 7 | 4401 |
| 2/22/1979 | 1979 | 2 | 22 | 267 | 18 | 39 | 28.5 | -3.5 | 4397.5 |
| 2/23/1979 | 1979 | 2 | 23 | 268 | 15 | 37 | 26 | -6 | 4391.5 |
| 2/24/1979 | 1979 | 2 | 24 | 269 | 14 | 38 | 26 | -6 | 4385.5 |
| 2/25/1979 | 1979 | 2 | 25 | 270 | 16 | 37 | 26.5 | -5.5 | 4380 |
| 2/26/1979 | 1979 | 2 | 26 | 271 | 14 | 35 | 24.5 | -7.5 | 4372.5 |
| 2/27/1979 | 1979 | 2 | 27 | 272 | 12 | 30 | 21 | -11 | 4361.5 |
| 2/28/1979 | 1979 | 2 | 28 | 273 | 12 | 42 | 27 | -5 | 4356.5 |
| 3/1/1979 | 1979 | 3 | 1 | 274 | 15 | 42 | 28.5 | -3.5 | 4353 |
| 3/2/1979 | 1979 | 3 | 2 | 275 | 16 | 35 | 25.5 | -6.5 | 4346.5 |
| 3/3/1979 | 1979 | 3 | 3 | 276 | 16 | 40 | 28 | -4 | 4342.5 |
| 3/4/1979 | 1979 | 3 | 4 | 277 | 17 | 40 | 28.5 | -3.5 | 4339 |
| 3/5/1979 | 1979 | 3 | 5 | 278 | 18 | 42 | 30 | -2 | 4337 |
| 3/6/1979 | 1979 | 3 | 6 | 279 | 20 | 50 | 35 | 3 | 4340 |
| 3/7/1979 | 1979 | 3 | 7 | 280 | 26 | 57 | 41.5 | 9.5 | 4349.5 |
| 3/8/1979 | 1979 | 3 | 8 | 281 | 31 | 57 | 44 | 12 | 4361.5 |
| 3/9/1979 | 1979 | 3 | 9 | 282 | 28 | 56 | 42 | 10 | 4371.5 |
| 3/10/1979 | 1979 | 3 | 10 | 283 | 17 | 49 | 33 | 1 | 4372.5 |
| 3/11/1979 | 1979 | 3 | 11 | 284 | 22 | 55 | 38.5 | 6.5 | 4379 |
| 3/12/1979 | 1979 | 3 | 12 | 285 | 25 | 58 | 41.5 | 9.5 | 4388.5 |
| 3/13/1979 | 1979 | 3 | 13 | 286 | 27 | 57 | 42 | 10 | 4398.5 |
| 3/14/1979 | 1979 | 3 | 14 | 287 | 34 | 54 | 44 | 12 | 4410.5 |
| 3/15/1979 | 1979 | 3 | 15 | 288 | 21 | 54 | 37.5 | 5.5 | 4416 |
| 3/16/1979 | 1979 | 3 | 16 | 289 | 38 | 57 | 47.5 | 15.5 | 4431.5 |
| 3/17/1979 | 1979 | 3 | 17 | 290 | 25 | 49 | 37 | 5 | 4436.5 |
| 3/18/1979 | 1979 | 3 | 18 | 291 | 24 | 40 | 32 | 0 | 4436.5 |
| 3/19/1979 | 1979 | 3 | 19 | 292 | 25 | 40 | 32.5 | 0.5 | 4437 |
| 3/20/1979 | 1979 | 3 | 20 | 293 | 33 | 51 | 42 | 10 | 4447 |
| 3/21/1979 | 1979 | 3 | 21 | 294 | 29 | 54 | 41.5 | 9.5 | 4456.5 |
| 3/22/1979 | 1979 | 3 | 22 | 295 | 27 | 49 | 38 | 6 | 4462.5 |
| 3/23/1979 | 1979 | 3 | 23 | 296 | 24 | 49 | 36.5 | 4.5 | 4467 |
| 3/24/1979 | 1979 | 3 | 24 | 297 | 25 | 57 | 41 | 9 | 4476 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/25/1979 | 1979 | 3 | 25 | 298 | 27 | 55 | 41 | 9 | 4485 |
| 3/26/1979 | 1979 | 3 | 26 | 299 | 29 | 57 | 43 | 11 | 4496 |
| 3/27/1979 | 1979 | 3 | 27 | 300 | 30 | 58 | 44 | 12 | 4508 |
| 3/28/1979 | 1979 | 3 | 28 | 301 | 29 | 56 | 42.5 | 10.5 | 4518.5 |
| 3/29/1979 | 1979 | 3 | 29 | 302 | 28 | 50 | 39 | 7 | 4525.5 |
| 3/30/1979 | 1979 | 3 | 30 | 303 | 27 | 50 | 38.5 | 6.5 | 4532 |
| 3/31/1979 | 1979 | 3 | 31 | 304 | 26 | 50 | 38 | 6 | 4538 |
| 4/1/1979 | 1979 | 4 | 1 | 305 | 21 | 44 | 32.5 | 0.5 | 4538.5 |
| 4/2/1979 | 1979 | 4 | 2 | 306 | 20 | 42 | 31 | -1 | 4537.5 |
| 4/3/1979 | 1979 | 4 | 3 | 307 | 21 | 40 | 30.5 | -1.5 | 4536 |
| 4/4/1979 | 1979 | 4 | 4 | 308 | 19 | 41 | 30 | -2 | 4534 |
| 4/5/1979 | 1979 | 4 | 5 | 309 | 19 | 49 | 34 | 2 | 4536 |
| 4/6/1979 | 1979 | 4 | 6 | 310 | 28 | 49 | 38.5 | 6.5 | 4542.5 |
| 4/7/1979 | 1979 | 4 | 7 | 311 | 27 | 50 | 38.5 | 6.5 | 4549 |
| 4/8/1979 | 1979 | 4 | 8 | 312 | 27 | 53 | 40 | 8 | 4557 |
| 4/9/1979 | 1979 | 4 | 9 | 313 | 33 | 60 | 46.5 | 14.5 | 4571.5 |
| 4/10/1979 | 1979 | 4 | 10 | 314 | 35 | 65 | 50 | 18 | 4589.5 |
| 4/11/1979 | 1979 | 4 | 11 | 315 | 32 | 62 | 47 | 15 | 4604.5 |
| 4/12/1979 | 1979 | 4 | 12 | 316 | 33 | 58 | 45.5 | 13.5 | 4618 |
| 4/13/1979 | 1979 | 4 | 13 | 317 | 31 | 53 | 42 | 10 | 4628 |
| 4/14/1979 | 1979 | 4 | 14 | 318 | 21 | 39 | 30 | -2 | 4626 |
| 4/15/1979 | 1979 | 4 | 15 | 319 | 24 | 38 | 31 | -1 | 4625 |
| 4/16/1979 | 1979 | 4 | 16 | 320 | 21 | 46 | 33.5 | 1.5 | 4626.5 |
| 4/17/1979 | 1979 | 4 | 17 | 321 | 33 | 60 | 46.5 | 14.5 | 4641 |
| 4/18/1979 | 1979 | 4 | 18 | 322 | 30 | 68 | 49 | 17 | 4658 |
| 4/19/1979 | 1979 | 4 | 19 | 323 | 39 | 70 | 54.5 | 22.5 | 4680.5 |
| 4/20/1979 | 1979 | 4 | 20 | 324 | 38 | 71 | 54.5 | 22.5 | 4703 |
| 4/21/1979 | 1979 | 4 | 21 | 325 | 39 | 72 | 55.5 | 23.5 | 4726.5 |
| 4/22/1979 | 1979 | 4 | 22 | 326 | 40 | 70 | 55 | 23 | 4749.5 |
| 4/23/1979 | 1979 | 4 | 23 | 327 | 40 | 71 | 55.5 | 23.5 | 4773 |
| 4/24/1979 | 1979 | 4 | 24 | 328 | 38 | 69 | 53.5 | 21.5 | 4794.5 |
| 4/25/1979 | 1979 | 4 | 25 | 329 | 31 | 65 | 48 | 16 | 4810.5 |
| 4/26/1979 | 1979 | 4 | 26 | 330 | 36 | 65 | 50.5 | 18.5 | 4829 |
| 4/27/1979 | 1979 | 4 | 27 | 331 | 35 | 69 | 52 | 20 | 4849 |
| 4/28/1979 | 1979 | 4 | 28 | 332 | 41 | 69 | 55 | 23 | 4872 |
| 4/29/1979 | 1979 | 4 | 29 | 333 | 40 | 69 | 54.5 | 22.5 | 4894.5 |
| 4/30/1979 | 1979 | 4 | 30 | 334 | 41 | 68 | 54.5 | 22.5 | 4917 |
| 5/1/1979 | 1979 | 5 | 1 | 335 | 42 | 68 | 55 | 23 | 4940 |
| 5/2/1979 | 1979 | 5 | 2 | 336 | 39 | 63 | 51 | 19 | 4959 |
| 5/3/1979 | 1979 | 5 | 3 | 337 | 30 | 63 | 46.5 | 14.5 | 4973.5 |
| 5/4/1979 | 1979 | 5 | 4 | 338 | 31 | 64 | 47.5 | 15.5 | 4989 |
| 5/5/1979 | 1979 | 5 | 5 | 339 | 37 | 69 | 53 | 21 | 5010 |
| 5/6/1979 | 1979 | 5 | 6 | 340 | 34 | 69 | 51.5 | 19.5 | 5029.5 |
| 5/7/1979 | 1979 | 5 | 7 | 341 | 49 | 70 | 59.5 | 27.5 | 5057 |
| 5/8/1979 | 1979 | 5 | 8 | 342 | 44 | 72 | 58 | 26 | 5083 |
| 5/9/1979 | 1979 | 5 | 9 | 343 | 47 | 70 | 58.5 | 26.5 | 5109.5 |
| 5/10/1979 | 1979 | 5 | 10 | 344 | 29 | 65 | 47 | 15 | 5124.5 |
| 5/11/1979 | 1979 | 5 | 11 | 345 | 30 | 51 | 40.5 | 8.5 | 5133 |
| 5/12/1979 | 1979 | 5 | 12 | 346 | 28 | 58 | 43 | 11 | 5144 |
| 5/13/1979 | 1979 | 5 | 13 | 347 | 37 | 68 | 52.5 | 20.5 | 5164.5 |
| 5/14/1979 | 1979 | 5 | 14 | 348 | 32 | 69 | 50.5 | 18.5 | 5183 |
| 5/15/1979 | 1979 | 5 | 15 | 349 | 32 | 77 | 54.5 | 22.5 | 5205.5 |
| 5/16/1979 | 1979 | 5 | 16 | 350 | 40 | 76 | 58 | 26 | 5231.5 |
| 5/17/1979 | 1979 | 5 | 17 | 351 | 49 | 69 | 59 | 27 | 5258.5 |
| 5/18/1979 | 1979 | 5 | 18 | 352 | 44 | 67 | 55.5 | 23.5 | 5282 |
| 5/19/1979 | 1979 | 5 | 19 | 353 | 42 | 75 | 58.5 | 26.5 | 5308.5 |
| 5/20/1979 | 1979 | 5 | 20 | 354 | 48 | 76 | 62 | 30 | 5338.5 |
| 5/21/1979 | 1979 | 5 | 21 | 355 | 42 | 75 | 58.5 | 26.5 | 5365 |
| 5/22/1979 | 1979 | 5 | 22 | 356 | 33 | 66 | 49.5 | 17.5 | 5382.5 |
| 5/23/1979 | 1979 | 5 | 23 | 357 | 42 | 69 | 55.5 | 23.5 | 5406 |
| 5/24/1979 | 1979 | 5 | 24 | 358 | 42 | 75 | 58.5 | 26.5 | 5432.5 |
| 5/25/1979 | 1979 | 5 | 25 | 359 | 45 | 77 | 61 | 29 | 5461.5 |
| 5/26/1979 | 1979 | 5 | 26 | 360 | 46 | 78 | 62 | 30 | 5491.5 |
| 5/27/1979 | 1979 | 5 | 27 | 361 | 45 | 72 | 58.5 | 26.5 | 5518 |
| 5/28/1979 | 1979 | 5 | 28 | 362 | 46 | 72 | 59 | 27 | 5545 |
| 5/29/1979 | 1979 | 5 | 29 | 363 | 40 | 73 | 56.5 | 24.5 | 5569.5 |
| 5/30/1979 | 1979 | 5 | 30 | 364 | 47 | 74 | 60.5 | 28.5 | 5598 |
| 5/31/1979 | 1979 | 5 | 31 | 365 | 44 | 75 | 59.5 | 27.5 | 5625.5 |
| 6/1/1979 | 1979 | 6 | 1 | 1 | 42 | 72 | 57 | 25 | 25 |
| 6/2/1979 | 1979 | 6 | 2 | 2 | 43 | 69 | 56 | 24 | 49 |
| 6/3/1979 | 1979 | 6 | 3 | 3 | 41 | 69 | 55 | 23 | 72 |
| 6/4/1979 | 1979 | 6 | 4 | 4 | 47 | 70 | 58.5 | 26.5 | 98.5 |
| 6/5/1979 | 1979 | 6 | 5 | 5 | 46 | 76 | 61 | 29 | 127.5 |
| 6/6/1979 | 1979 | 6 | 6 | 6 | 52 | 77 | 64.5 | 32.5 | 160 |
| 6/7/1979 | 1979 | 6 | 7 | 7 | 49 | 75 | 62 | 30 | 190 |
| 6/8/1979 | 1979 | 6 | 8 | 8 | 42 | 65 | 53.5 | 21.5 | 211.5 |
| 6/9/1979 | 1979 | 6 | 9 | 9 | 41 | 67 | 54 | 22 | 233.5 |
| 6/10/1979 | 1979 | 6 | 10 | 10 | 39 | 64 | 51.5 | 19.5 | 253 |
| 6/11/1979 | 1979 | 6 | 11 | 11 | 41 | 79 | 60 | 28 | 281 |
| 6/12/1979 | 1979 | 6 | 12 | 12 | 49 | 84 | 66.5 | 34.5 | 315.5 |
| 6/13/1979 | 1979 | 6 | 13 | 13 | 51 | 86 | 68.5 | 36.5 | 352 |
| 6/14/1979 | 1979 | 6 | 14 | 14 | 55 | 86 | 70.5 | 38.5 | 390.5 |
| 6/15/1979 | 1979 | 6 | 15 | 15 | 56 | 84 | 70 | 38 | 428.5 |
| 6/16/1979 | 1979 | 6 | 16 | 16 | 58 | 82 | 70 | 38 | 466.5 |
| 6/17/1979 | 1979 | 6 | 17 | 17 | 49 | 79 | 64 | 32 | 498.5 |
| 6/18/1979 | 1979 | 6 | 18 | 18 | 50 | 79 | 64.5 | 32.5 | 531 |
| 6/19/1979 | 1979 | 6 | 19 | 19 | 41 | 76 | 58.5 | 26.5 | 557.5 |
| 6/20/1979 | 1979 | 6 | 20 | 20 | 45 | 81 | 63 | 31 | 588.5 |
| 6/21/1979 | 1979 | 6 | 21 | 21 | 51 | 85 | 68 | 36 | 624.5 |
| 6/22/1979 | 1979 | 6 | 22 | 22 | 57 | 87 | 72 | 40 | 664.5 |
| 6/23/1979 | 1979 | 6 | 23 | 23 | 53 | 85 | 69 | 37 | 701.5 |
| 6/24/1979 | 1979 | 6 | 24 | 24 | 55 | 84 | 69.5 | 37.5 | 739 |
| 6/25/1979 | 1979 | 6 | 25 | 25 | 53 | 87 | 70 | 38 | 777 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/26/1979 | 1979 | 6 | 26 | 26 | 58 | 90 | 74 | 42 | 819 |
| 6/27/1979 | 1979 | 6 | 27 | 27 | 59 | 92 | 75.5 | 43.5 | 862.5 |
| 6/28/1979 | 1979 | 6 | 28 | 28 | 57 | 91 | 74 | 42 | 904.5 |
| 6/29/1979 | 1979 | 6 | 29 | 29 | 57 | 91 | 74 | 42 | 946.5 |
| 6/30/1979 | 1979 | 6 | 30 | 30 | 55 | 87 | 71 | 39 | 985.5 |
| 7/1/1979 | 1979 | 7 | 1 | 31 | 50 | 85 | 67.5 | 35.5 | 1021 |
| 7/2/1979 | 1979 | 7 | 2 | 32 | 55 | 79 | 67 | 35 | 1056 |
| 7/3/1979 | 1979 | 7 | 3 | 33 | 55 | 89 | 72 | 40 | 1096 |
| 7/4/1979 | 1979 | 7 | 4 | 34 | 50 | 79 | 64.5 | 32.5 | 1128.5 |
| 7/5/1979 | 1979 | 7 | 5 | 35 | 51 | 81 | 66 | 34 | 1162.5 |
| 7/6/1979 | 1979 | 7 | 6 | 36 | 61 | 82 | 71.5 | 39.5 | 1202 |
| 7/7/1979 | 1979 | 7 | 7 | 37 | 56 | 94 | 75 | 43 | 1245 |
| 7/8/1979 | 1979 | 7 | 8 | 38 | 53 | 90 | 71.5 | 39.5 | 1284.5 |
| 7/9/1979 | 1979 | 7 | 9 | 39 | 54 | 92 | 73 | 41 | 1325.5 |
| 7/10/1979 | 1979 | 7 | 10 | 40 | 55 | 89 | 72 | 40 | 1365.5 |
| 7/11/1979 | 1979 | 7 | 11 | 41 | 55 | 90 | 72.5 | 40.5 | 1406 |
| 7/12/1979 | 1979 | 7 | 12 | 42 | 56 | 94 | 75 | 43 | 1449 |
| 7/13/1979 | 1979 | 7 | 13 | 43 | 60 | 95 | 77.5 | 45.5 | 1494.5 |
| 7/14/1979 | 1979 | 7 | 14 | 44 | 57 | 94 | 75.5 | 43.5 | 1538 |
| 7/15/1979 | 1979 | 7 | 15 | 45 | 59 | 95 | 77 | 45 | 1583 |
| 7/16/1979 | 1979 | 7 | 16 | 46 | 60 | 96 | 78 | 46 | 1629 |
| 7/17/1979 | 1979 | 7 | 17 | 47 | 61 | 92 | 76.5 | 44.5 | 1673.5 |
| 7/18/1979 | 1979 | 7 | 18 | 48 | 59 | 90 | 74.5 | 42.5 | 1716 |
| 7/19/1979 | 1979 | 7 | 19 | 49 | 56 | 77 | 66.5 | 34.5 | 1750.5 |
| 7/20/1979 | 1979 | 7 | 20 | 50 | 54 | 71 | 62.5 | 30.5 | 1781 |
| 7/21/1979 | 1979 | 7 | 21 | 51 | 50 | 74 | 62 | 30 | 1811 |
| 7/22/1979 | 1979 | 7 | 22 | 52 | 50 | 74 | 62 | 30 | 1841 |
| 7/23/1979 | 1979 | 7 | 23 | 53 | 57 | 76 | 66.5 | 34.5 | 1875.5 |
| 7/24/1979 | 1979 | 7 | 24 | 54 | 58 | 78 | 68 | 36 | 1911.5 |
| 7/25/1979 | 1979 | 7 | 25 | 55 | 55 | 85 | 70 | 38 | 1949.5 |
| 7/26/1979 | 1979 | 7 | 26 | 56 | 54 | 86 | 70 | 38 | 1987.5 |
| 7/27/1979 | 1979 | 7 | 27 | 57 | 57 | 87 | 72 | 40 | 2027.5 |
| 7/28/1979 | 1979 | 7 | 28 | 58 | 58 | 88 | 73 | 41 | 2068.5 |
| 7/29/1979 | 1979 | 7 | 29 | 59 | 60 | 89 | 74.5 | 42.5 | 2111 |
| 7/30/1979 | 1979 | 7 | 30 | 60 | 58 | 91 | 74.5 | 42.5 | 2153.5 |
| 7/31/1979 | 1979 | 7 | 31 | 61 | 56 | 83 | 69.5 | 37.5 | 2191 |
| 8/1/1979 | 1979 | 8 | 1 | 62 | 50 | 88 | 69 | 37 | 2228 |
| 8/2/1979 | 1979 | 8 | 2 | 63 | 55 | 89 | 72 | 40 | 2268 |
| 8/3/1979 | 1979 | 8 | 3 | 64 | 63 | 88 | 75.5 | 43.5 | 2311.5 |
| 8/4/1979 | 1979 | 8 | 4 | 65 | 57 | 88 | 72.5 | 40.5 | 2352 |
| 8/5/1979 | 1979 | 8 | 5 | 66 | 60 | 86 | 73 | 41 | 2393 |
| 8/6/1979 | 1979 | 8 | 6 | 67 | 56 | 84 | 70 | 38 | 2431 |
| 8/7/1979 | 1979 | 8 | 7 | 68 | 57 | 86 | 71.5 | 39.5 | 2470.5 |
| 8/8/1979 | 1979 | 8 | 8 | 69 | 54 | 78 | 66 | 34 | 2504.5 |
| 8/9/1979 | 1979 | 8 | 9 | 70 | 56 | 84 | 70 | 38 | 2542.5 |
| 8/10/1979 | 1979 | 8 | 10 | 71 | 58 | 84 | 71 | 39 | 2581.5 |
| 8/11/1979 | 1979 | 8 | 11 | 72 | 52 | 82 | 67 | 35 | 2616.5 |
| 8/12/1979 | 1979 | 8 | 12 | 73 | 51 | 75 | 63 | 31 | 2647.5 |
| 8/13/1979 | 1979 | 8 | 13 | 74 | 54 | 77 | 65.5 | 33.5 | 2681 |
| 8/14/1979 | 1979 | 8 | 14 | 75 | 54 | 72 | 63 | 31 | 2712 |
| 8/15/1979 | 1979 | 8 | 15 | 76 | 52 | 70 | 61 | 29 | 2741 |
| 8/16/1979 | 1979 | 8 | 16 | 77 | 45 | 70 | 57.5 | 25.5 | 2766.5 |
| 8/17/1979 | 1979 | 8 | 17 | 78 | 52 | 71 | 61.5 | 29.5 | 2796 |
| 8/18/1979 | 1979 | 8 | 18 | 79 | 47 | 70 | 58.5 | 26.5 | 2822.5 |
| 8/19/1979 | 1979 | 8 | 19 | 80 | 46 | 69 | 57.5 | 25.5 | 2848 |
| 8/20/1979 | 1979 | 8 | 20 | 81 | 44 | 69 | 56.5 | 24.5 | 2872.5 |
| 8/21/1979 | 1979 | 8 | 21 | 82 | 50 | 70 | 60 | 28 | 2900.5 |
| 8/22/1979 | 1979 | 8 | 22 | 83 | 49 | 70 | 59.5 | 27.5 | 2928 |
| 8/23/1979 | 1979 | 8 | 23 | 84 | 49 | 80 | 64.5 | 32.5 | 2960.5 |
| 8/24/1979 | 1979 | 8 | 24 | 85 | 51 | 81 | 66 | 34 | 2994.5 |
| 8/25/1979 | 1979 | 8 | 25 | 86 | 51 | 81 | 66 | 34 | 3028.5 |
| 8/26/1979 | 1979 | 8 | 26 | 87 | 53 | 82 | 67.5 | 35.5 | 3064 |
| 8/27/1979 | 1979 | 8 | 27 | 88 | 57 | 83 | 70 | 38 | 3102 |
| 8/28/1979 | 1979 | 8 | 28 | 89 | 50 | 82 | 66 | 34 | 3136 |
| 8/29/1979 | 1979 | 8 | 29 | 90 | 55 | 83 | 69 | 37 | 3173 |
| 8/30/1979 | 1979 | 8 | 30 | 91 | 56 | 83 | 69.5 | 37.5 | 3210.5 |
| 8/31/1979 | 1979 | 8 | 31 | 92 | 55 | 79 | 67 | 35 | 3245.5 |
| 9/1/1979 | 1979 | 9 | 1 | 93 | 55 | 83 | 69 | 37 | 3282.5 |
| 9/2/1979 | 1979 | 9 | 2 | 94 | 54 | 82 | 68 | 36 | 3318.5 |
| 9/3/1979 | 1979 | 9 | 3 | 95 | 53 | 81 | 67 | 35 | 3353.5 |
| 9/4/1979 | 1979 | 9 | 4 | 96 | 57 | 84 | 70.5 | 38.5 | 3392 |
| 9/5/1979 | 1979 | 9 | 5 | 97 | 56 | 83 | 69.5 | 37.5 | 3429.5 |
| 9/6/1979 | 1979 | 9 | 6 | 98 | 52 | 84 | 68 | 36 | 3465.5 |
| 9/7/1979 | 1979 | 9 | 7 | 99 | 56 | 85 | 70.5 | 38.5 | 3504 |
| 9/8/1979 | 1979 | 9 | 8 | 100 | 57 | 82 | 69.5 | 37.5 | 3541.5 |
| 9/9/1979 | 1979 | 9 | 9 | 101 | 55 | 81 | 68 | 36 | 3577.5 |
| 9/10/1979 | 1979 | 9 | 10 | 102 | 51 | 78 | 64.5 | 32.5 | 3610 |
| 9/11/1979 | 1979 | 9 | 11 | 103 | 57 | 77 | 67 | 35 | 3645 |
| 9/12/1979 | 1979 | 9 | 12 | 104 | 51 | 72 | 61.5 | 29.5 | 3674.5 |
| 9/13/1979 | 1979 | 9 | 13 | 105 | 50 | 76 | 63 | 31 | 3705.5 |
| 9/14/1979 | 1979 | 9 | 14 | 106 | 51 | 70 | 60.5 | 28.5 | 3734 |
| 9/15/1979 | 1979 | 9 | 15 | 107 | 50 | 69 | 59.5 | 27.5 | 3761.5 |
| 9/16/1979 | 1979 | 9 | 16 | 108 | 40 | 69 | 54.5 | 22.5 | 3784 |
| 9/17/1979 | 1979 | 9 | 17 | 109 | 45 | 67 | 56 | 24 | 3808 |
| 9/18/1979 | 1979 | 9 | 18 | 110 | 45 | 68 | 56.5 | 24.5 | 3832.5 |
| 9/19/1979 | 1979 | 9 | 19 | 111 | 41 | 71 | 56 | 24 | 3856.5 |
| 9/20/1979 | 1979 | 9 | 20 | 112 | 46 | 74 | 60 | 28 | 3884.5 |
| 9/21/1979 | 1979 | 9 | 21 | 113 | 48 | 72 | 60 | 28 | 3912.5 |
| 9/22/1979 | 1979 | 9 | 22 | 114 | 43 | 75 | 59 | 27 | 3939.5 |
| 9/23/1979 | 1979 | 9 | 23 | 115 | 49 | 76 | 62.5 | 30.5 | 3970 |
| 9/24/1979 | 1979 | 9 | 24 | 116 | 50 | 76 | 63 | 31 | 4001 |
| 9/25/1979 | 1979 | 9 | 25 | 117 | 51 | 79 | 65 | 33 | 4034 |
| 9/26/1979 | 1979 | 9 | 26 | 118 | 48 | 76 | 62 | 30 | 4064 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/27/1979 | 1979 | 9 | 27 | 119 | 52 | 74 | 63 | 31 | 4095 |
| 9/28/1979 | 1979 | 9 | 28 | 120 | 49 | 75 | 62 | 30 | 4125 |
| 9/29/1979 | 1979 | 9 | 29 | 121 | 48 | 75 | 61.5 | 29.5 | 4154.5 |
| 9/30/1979 | 1979 | 9 | 30 | 122 | 50 | 75 | 62.5 | 30.5 | 4185 |
| 10/1/1979 | 1979 | 10 | 1 | 123 | 51 | 77 | 64 | 32 | 4217 |
| 10/2/1979 | 1979 | 10 | 2 | 124 | 49 | 75 | 62 | 30 | 4247 |
| 10/3/1979 | 1979 | 10 | 3 | 125 | 48 | 74 | 61 | 29 | 4276 |
| 10/4/1979 | 1979 | 10 | 4 | 126 | 43 | 76 | 59.5 | 27.5 | 4303.5 |
| 10/5/1979 | 1979 | 10 | 5 | 127 | 46 | 76 | 61 | 29 | 4332.5 |
| 10/6/1979 | 1979 | 10 | 6 | 128 | 44 | 78 | 61 | 29 | 4361.5 |
| 10/7/1979 | 1979 | 10 | 7 | 129 | 43 | 76 | 59.5 | 27.5 | 4389 |
| 10/8/1979 | 1979 | 10 | 8 | 130 | 42 | 74 | 58 | 26 | 4415 |
| 10/9/1979 | 1979 | 10 | 9 | 131 | 45 | 72 | 58.5 | 26.5 | 4441.5 |
| 10/10/1979 | 1979 | 10 | 10 | 132 | 40 | 75 | 57.5 | 25.5 | 4467 |
| 10/11/1979 | 1979 | 10 | 11 | 133 | 45 | 76 | 60.5 | 28.5 | 4495.5 |
| 10/12/1979 | 1979 | 10 | 12 | 134 | 46 | 75 | 60.5 | 28.5 | 4524 |
| 10/13/1979 | 1979 | 10 | 13 | 135 | 41 | 72 | 56.5 | 24.5 | 4548.5 |
| 10/14/1979 | 1979 | 10 | 14 | 136 | 44 | 70 | 57 | 25 | 4573.5 |
| 10/15/1979 | 1979 | 10 | 15 | 137 | 39 | 67 | 53 | 21 | 4594.5 |
| 10/16/1979 | 1979 | 10 | 16 | 138 | 38 | 70 | 54 | 22 | 4616.5 |
| 10/17/1979 | 1979 | 10 | 17 | 139 | 39 | 65 | 52 | 20 | 4636.5 |
| 10/18/1979 | 1979 | 10 | 18 | 140 | 47 | 66 | 56.5 | 24.5 | 4661 |
| 10/19/1979 | 1979 | 10 | 19 | 141 | 40 | 64 | 52 | 20 | 4681 |
| 10/20/1979 | 1979 | 10 | 20 | 142 | 39 | 60 | 49.5 | 17.5 | 4698.5 |
| 10/21/1979 | 1979 | 10 | 21 | 143 | 24 | 60 | 42 | 10 | 4708.5 |
| 10/22/1979 | 1979 | 10 | 22 | 144 | 30 | 61 | 45.5 | 13.5 | 4722 |
| 10/23/1979 | 1979 | 10 | 23 | 145 | 39 | 66 | 52.5 | 20.5 | 4742.5 |
| 10/24/1979 | 1979 | 10 | 24 | 146 | 40 | 69 | 54.5 | 22.5 | 4765 |
| 10/25/1979 | 1979 | 10 | 25 | 147 | 40 | 69 | 54.5 | 22.5 | 4787.5 |
| 10/26/1979 | 1979 | 10 | 26 | 148 | 39 | 68 | 53.5 | 21.5 | 4809 |
| 10/27/1979 | 1979 | 10 | 27 | 149 | 34 | 67 | 50.5 | 18.5 | 4827.5 |
| 10/28/1979 | 1979 | 10 | 28 | 150 | 40 | 61 | 50.5 | 18.5 | 4846 |
| 10/29/1979 | 1979 | 10 | 29 | 151 | 25 | 43 | 34 | 2 | 4848 |
| 10/30/1979 | 1979 | 10 | 30 | 152 | 17 | 41 | 29 | -3 | 4845 |
| 10/31/1979 | 1979 | 10 | 31 | 153 | 20 | 42.5 | 31.25 | -0.75 | 4844.25 |
| 11/1/1979 | 1979 | 11 | 1 | 154 | 26 | 44 | 35 | 3 | 4847.25 |
| 11/2/1979 | 1979 | 11 | 2 | 155 | 22 | 43 | 32.5 | 0.5 | 4847.75 |
| 11/3/1979 | 1979 | 11 | 3 | 156 | 21 | 43 | 32 | 0 | 4847.75 |
| 11/4/1979 | 1979 | 11 | 4 | 157 | 23 | 43 | 33 | 1 | 4848.75 |
| 11/5/1979 | 1979 | 11 | 5 | 158 | 20 | 43 | 31.5 | -0.5 | 4848.25 |
| 11/6/1979 | 1979 | 11 | 6 | 159 | 25 | 43 | 34 | 2 | 4850.25 |
| 11/7/1979 | 1979 | 11 | 7 | 160 | 25 | 43 | 34 | 2 | 4852.25 |
| 11/8/1979 | 1979 | 11 | 8 | 161 | 36 | 49 | 42.5 | 10.5 | 4862.75 |
| 11/9/1979 | 1979 | 11 | 9 | 162 | 25 | 44 | 34.5 | 2.5 | 4865.25 |
| 11/10/1979 | 1979 | 11 | 10 | 163 | 31 | 41 | 36 | 4 | 4869.25 |
| 11/11/1979 | 1979 | 11 | 11 | 164 | 29 | 41 | 35 | 3 | 4872.25 |
| 11/12/1979 | 1979 | 11 | 12 | 165 | 25 | 42 | 33.5 | 1.5 | 4873.75 |
| 11/13/1979 | 1979 | 11 | 13 | 166 | 20 | 43 | 31.5 | -0.5 | 4873.25 |
| 11/14/1979 | 1979 | 11 | 14 | 167 | 20 | 45 | 32.5 | 0.5 | 4873.75 |
| 11/15/1979 | 1979 | 11 | 15 | 168 | 23 | 43 | 33 | 1 | 4874.75 |
| 11/16/1979 | 1979 | 11 | 16 | 169 | 24 | 43 | 33.5 | 1.5 | 4876.25 |
| 11/17/1979 | 1979 | 11 | 17 | 170 | 23 | 43 | 33 | 1 | 4877.25 |
| 11/18/1979 | 1979 | 11 | 18 | 171 | 24 | 51 | 37.5 | 5.5 | 4882.75 |
| 11/19/1979 | 1979 | 11 | 19 | 172 | 23 | 49 | 36 | 4 | 4886.75 |
| 11/20/1979 | 1979 | 11 | 20 | 173 | 22 | 48 | 35 | 3 | 4889.75 |
| 11/21/1979 | 1979 | 11 | 21 | 174 | 20 | 47 | 33.5 | 1.5 | 4891.25 |
| 11/22/1979 | 1979 | 11 | 22 | 175 | 26 | 49 | 37.5 | 5.5 | 4896.75 |
| 11/23/1979 | 1979 | 11 | 23 | 176 | 18 | 42 | 30 | -2 | 4894.75 |
| 11/24/1979 | 1979 | 11 | 24 | 177 | 17 | 40 | 28.5 | -3.5 | 4891.25 |
| 11/25/1979 | 1979 | 11 | 25 | 178 | 15 | 40 | 27.5 | -4.5 | 4886.75 |
| 11/26/1979 | 1979 | 11 | 26 | 179 | 14 | 40 | 27 | -5 | 4881.75 |
| 11/27/1979 | 1979 | 11 | 27 | 180 | 9 | 40 | 24.5 | -7.5 | 4874.25 |
| 11/28/1979 | 1979 | 11 | 28 | 181 | 11 | 34 | 22.5 | -9.5 | 4864.75 |
| 11/29/1979 | 1979 | 11 | 29 | 182 | 10 | 34 | 22 | -10 | 4854.75 |
| 11/30/1979 | 1979 | 11 | 30 | 183 | 10 | 32 | 21 | -11 | 4843.75 |
| 12/1/1979 | 1979 | 12 | 1 | 184 | 9 | 43 | 26 | -6 | 4837.75 |
| 12/2/1979 | 1979 | 12 | 2 | 185 | 8 | 43 | 25.5 | -6.5 | 4831.25 |
| 12/3/1979 | 1979 | 12 | 3 | 186 | 12 | 43 | 27.5 | -4.5 | 4826.75 |
| 12/4/1979 | 1979 | 12 | 4 | 187 | 13 | 43 | 28 | -4 | 4822.75 |
| 12/5/1979 | 1979 | 12 | 5 | 188 | 10 | 43 | 26.5 | -5.5 | 4817.25 |
| 12/6/1979 | 1979 | 12 | 6 | 189 | 20 | 43 | 31.5 | -0.5 | 4816.75 |
| 12/7/1979 | 1979 | 12 | 7 | 190 | 23 | 43 | 33 | 1 | 4817.75 |
| 12/8/1979 | 1979 | 12 | 8 | 191 | 23 | 43 | 33 | 1 | 4818.75 |
| 12/9/1979 | 1979 | 12 | 9 | 192 | 15 | 43 | 29 | -3 | 4815.75 |
| 12/10/1979 | 1979 | 12 | 10 | 193 | 15 | 43 | 29 | -3 | 4812.75 |
| 12/11/1979 | 1979 | 12 | 11 | 194 | 12 | 43 | 27.5 | -4.5 | 4808.25 |
| 12/12/1979 | 1979 | 12 | 12 | 195 | 25 | 49 | 37 | 5 | 4813.25 |
| 12/13/1979 | 1979 | 12 | 13 | 196 | 23 | 50 | 36.5 | 4.5 | 4817.75 |
| 12/14/1979 | 1979 | 12 | 14 | 197 | 20 | 53 | 36.5 | 4.5 | 4822.25 |
| 12/15/1979 | 1979 | 12 | 15 | 198 | 27 | 53 | 40 | 8 | 4830.25 |
| 12/16/1979 | 1979 | 12 | 16 | 199 | 29 | 55 | 42 | 10 | 4840.25 |
| 12/17/1979 | 1979 | 12 | 17 | 200 | 20 | 55 | 37.5 | 5.5 | 4845.75 |
| 12/18/1979 | 1979 | 12 | 18 | 201 | 18 | 55 | 36.5 | 4.5 | 4850.25 |
| 12/19/1979 | 1979 | 12 | 19 | 202 | 18 | 55 | 36.5 | 4.5 | 4854.75 |
| 12/20/1979 | 1979 | 12 | 20 | 203 | 15 | 55 | 35 | 3 | 4857.75 |
| 12/21/1979 | 1979 | 12 | 21 | 204 | 16 | 45 | 30.5 | -1.5 | 4856.25 |
| 12/22/1979 | 1979 | 12 | 22 | 205 | 18 | 46 | 32 | 0 | 4856.25 |
| 12/23/1979 | 1979 | 12 | 23 | 206 | 18 | 49 | 33.5 | 1.5 | 4857.75 |
| 12/24/1979 | 1979 | 12 | 24 | 207 | 19 | 40 | 29.5 | -2.5 | 4855.25 |
| 12/25/1979 | 1979 | 12 | 25 | 208 | 19 | 40 | 29.5 | -2.5 | 4852.75 |
| 12/26/1979 | 1979 | 12 | 26 | 209 | 19 | 39 | 29 | -3 | 4849.75 |
| 12/27/1979 | 1979 | 12 | 27 | 210 | 18 | 39 | 28.5 | -3.5 | 4846.25 |
| 12/28/1979 | 1979 | 12 | 28 | 211 | 12 | 39 | 25.5 | -6.5 | 4839.75 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/29/1979 | 1979 | 12 | 29 | 212 | 14 | 40 | 27 | -5 | 4834.75 |
| 12/30/1979 | 1979 | 12 | 30 | 213 | 15 | 42 | 28.5 | -3.5 | 4831.25 |
| 12/31/1979 | 1979 | 12 | 31 | 214 | 8 | 36 | 22 | -10 | 4821.25 |
| 1/1/1980 | 1980 | 1 | 1 | 215 | 8 | 30 | 19 | -13 | 4808.25 |
| 1/2/1980 | 1980 | 1 | 2 | 216 | 7 | 30 | 18.5 | -13.5 | 4794.75 |
| 1/3/1980 | 1980 | 1 | 3 | 217 | 7 | 29 | 18 | -14 | 4780.75 |
| 1/4/1980 | 1980 | 1 | 4 | 218 | 11 | 28 | 19.5 | -12.5 | 4768.25 |
| 1/5/1980 | 1980 | 1 | 5 | 219 | 15 | 30 | 60.5 | 28.5 | 4796.75 |
| 1/6/1980 | 1980 | 1 | 6 | 220 | 14 | 29 | 60.5 | 28.5 | 4825.25 |
| 1/7/1980 | 1980 | 1 | 7 | 221 | 14 | 30 | 22 | -10 | 4815.25 |
| 1/8/1980 | 1980 | 1 | 8 | 222 | 25 | 39 | 32 | 0 | 4815.25 |
| 1/9/1980 | 1980 | 1 | 9 | 223 | 13 | 40 | 26.5 | -5.5 | 4809.75 |
| 1/10/1980 | 1980 | 1 | 10 | 224 | 13 | 40 | 26.5 | -5.5 | 4804.25 |
| 1/11/1980 | 1980 | 1 | 11 | 225 | 17 | 37 | 27 | -5 | 4799.25 |
| 1/12/1980 | 1980 | 1 | 12 | 226 | 10 | 38 | 24 | -8 | 4791.25 |
| 1/13/1980 | 1980 | 1 | 13 | 227 | 15 | 39 | 27 | -5 | 4786.25 |
| 1/14/1980 | 1980 | 1 | 14 | 228 | 18 | 39 | 28.5 | -3.5 | 4782.75 |
| 1/15/1980 | 1980 | 1 | 15 | 229 | 20 | 40 | 30 | -2 | 4780.75 |
| 1/16/1980 | 1980 | 1 | 16 | 230 | 20 | 40 | 30 | -2 | 4778.75 |
| 1/17/1980 | 1980 | 1 | 17 | 231 | 18 | 42 | 30 | -2 | 4776.75 |
| 1/18/1980 | 1980 | 1 | 18 | 232 | 19 | 42 | 30.5 | -1.5 | 4775.25 |
| 1/19/1980 | 1980 | 1 | 19 | 233 | 15 | 40 | 27.5 | -4.5 | 4770.75 |
| 1/20/1980 | 1980 | 1 | 20 | 234 | 18 | 43 | 30.5 | -1.5 | 4769.25 |
| 1/21/1980 | 1980 | 1 | 21 | 235 | 19 | 40 | 29.5 | -2.5 | 4766.75 |
| 1/22/1980 | 1980 | 1 | 22 | 236 | 15 | 39 | 27 | -5 | 4761.75 |
| 1/23/1980 | 1980 | 1 | 23 | 237 | 19 | 36 | 27.5 | -4.5 | 4757.25 |
| 1/24/1980 | 1980 | 1 | 24 | 238 | 16 | 37 | 26.5 | -5.5 | 4751.75 |
| 1/25/1980 | 1980 | 1 | 25 | 239 | 15 | 36 | 25.5 | -6.5 | 4745.25 |
| 1/26/1980 | 1980 | 1 | 26 | 240 | 19 | 40 | 29.5 | -2.5 | 4742.75 |
| 1/27/1980 | 1980 | 1 | 27 | 241 | 12 | 39 | 25.5 | -6.5 | 4736.25 |
| 1/28/1980 | 1980 | 1 | 28 | 242 | 19 | 41 | 30 | -2 | 4734.25 |
| 1/29/1980 | 1980 | 1 | 29 | 243 | 18 | 42 | 30 | -2 | 4732.25 |
| 1/30/1980 | 1980 | 1 | 30 | 244 | 19 | 46 | 32.5 | 0.5 | 4732.75 |
| 1/31/1980 | 1980 | 1 | 31 | 245 | 15 | 45 | 30 | -2 | 4730.75 |
| 2/1/1980 | 1980 | 2 | 1 | 246 | 24 | 44 | 34 | 2 | 4732.75 |
| 2/2/1980 | 1980 | 2 | 2 | 247 | 23 | 41 | 32 | 0 | 4732.75 |
| 2/3/1980 | 1980 | 2 | 3 | 248 | 25 | 48 | 36.5 | 4.5 | 4737.25 |
| 2/4/1980 | 1980 | 2 | 4 | 249 | 20 | 50 | 35 | 3 | 4740.25 |
| 2/5/1980 | 1980 | 2 | 5 | 250 | 20 | 50 | 35 | 3 | 4743.25 |
| 2/6/1980 | 1980 | 2 | 6 | 251 | 25 | 48 | 36.5 | 4.5 | 4747.75 |
| 2/7/1980 | 1980 | 2 | 7 | 252 | 26 | 49 | 37.5 | 5.5 | 4753.25 |
| 2/8/1980 | 1980 | 2 | 8 | 253 | 16 | 39 | 27.5 | -4.5 | 4748.75 |
| 2/9/1980 | 1980 | 2 | 9 | 254 | 4 | 28 | 16 | -16 | 4732.75 |
| 2/10/1980 | 1980 | 2 | 10 | 255 | -9 | 30 | 10.5 | -21.5 | 4711.25 |
| 2/11/1980 | 1980 | 2 | 11 | 256 | 9 | 30 | 19.5 | -12.5 | 4698.75 |
| 2/12/1980 | 1980 | 2 | 12 | 257 | 10 | 45 | 27.5 | -4.5 | 4694.25 |
| 2/13/1980 | 1980 | 2 | 13 | 258 | 12 | 44 | 28 | -4 | 4690.25 |
| 2/14/1980 | 1980 | 2 | 14 | 259 | 18 | 46 | 32 | 0 | 4690.25 |
| 2/15/1980 | 1980 | 2 | 15 | 260 | 15 | 44 | 29.5 | -2.5 | 4687.75 |
| 2/16/1980 | 1980 | 2 | 16 | 261 | 15 | 44 | 29.5 | -2.5 | 4685.25 |
| 2/17/1980 | 1980 | 2 | 17 | 262 | 18 | 45 | 31.5 | -0.5 | 4684.75 |
| 2/18/1980 | 1980 | 2 | 18 | 263 | 20 | 44 | 32 | 0 | 4684.75 |
| 2/19/1980 | 1980 | 2 | 19 | 264 | 19 | 42 | 30.5 | -1.5 | 4683.25 |
| 2/20/1980 | 1980 | 2 | 20 | 265 | 12 | 44 | 28 | -4 | 4679.25 |
| 2/21/1980 | 1980 | 2 | 21 | 266 | 11 | 43 | 27 | -5 | 4674.25 |
| 2/22/1980 | 1980 | 2 | 22 | 267 | 12 | 42 | 27 | -5 | 4669.25 |
| 2/23/1980 | 1980 | 2 | 23 | 268 | 24 | 42 | 33 | 1 | 4670.25 |
| 2/24/1980 | 1980 | 2 | 24 | 269 | 30 | 42 | 36 | 4 | 4674.25 |
| 2/25/1980 | 1980 | 2 | 25 | 270 | 20 | 49 | 34.5 | 2.5 | 4676.75 |
| 2/26/1980 | 1980 | 2 | 26 | 271 | 19 | 50 | 34.5 | 2.5 | 4679.25 |
| 2/27/1980 | 1980 | 2 | 27 | 272 | 25 | 53 | 39 | 7 | 4686.25 |
| 2/28/1980 | 1980 | 2 | 28 | 273 | 27 | 60 | 43.5 | 11.5 | 4697.75 |
| 2/29/1980 | 1980 | 2 | 29 | 274 | 30 | 61 | 45.5 | 13.5 | 4711.25 |
| 3/1/1980 | 1980 | 3 | 1 | 275 | 23 | 59 | 41 | 9 | 4720.25 |
| 3/2/1980 | 1980 | 3 | 2 | 276 | 23 | 56 | 39.5 | 7.5 | 4727.75 |
| 3/3/1980 | 1980 | 3 | 3 | 277 | 24 | 55 | 39.5 | 7.5 | 4735.25 |
| 3/4/1980 | 1980 | 3 | 4 | 278 | 29 | 50 | 39.5 | 7.5 | 4742.75 |
| 3/5/1980 | 1980 | 3 | 5 | 279 | 26 | 48 | 37 | 5 | 4747.75 |
| 3/6/1980 | 1980 | 3 | 6 | 280 | 29 | 47 | 38 | 6 | 4753.75 |
| 3/7/1980 | 1980 | 3 | 7 | 281 | 19 | 48 | 33.5 | 1.5 | 4755.25 |
| 3/8/1980 | 1980 | 3 | 8 | 282 | 20 | 46 | 33 | 1 | 4756.25 |
| 3/9/1980 | 1980 | 3 | 9 | 283 | 20 | 48 | 34 | 2 | 4758.25 |
| 3/10/1980 | 1980 | 3 | 10 | 284 | 24 | 49 | 36.5 | 4.5 | 4762.75 |
| 3/11/1980 | 1980 | 3 | 11 | 285 | 30 | 49 | 39.5 | 7.5 | 4770.25 |
| 3/12/1980 | 1980 | 3 | 12 | 286 | 29 | 48 | 38.5 | 6.5 | 4776.75 |
| 3/13/1980 | 1980 | 3 | 13 | 287 | 21 | 54 | 37.5 | 5.5 | 4782.25 |
| 3/14/1980 | 1980 | 3 | 14 | 288 | 27 | 60 | 43.5 | 11.5 | 4793.75 |
| 3/15/1980 | 1980 | 3 | 15 | 289 | 29 | 59 | 44 | 12 | 4805.75 |
| 3/16/1980 | 1980 | 3 | 16 | 290 | 19 | 56 | 37.5 | 5.5 | 4811.25 |
| 3/17/1980 | 1980 | 3 | 17 | 291 | 10 | 40 | 25 | -7 | 4804.25 |
| 3/18/1980 | 1980 | 3 | 18 | 292 | 11 | 41 | 26 | -6 | 4798.25 |
| 3/19/1980 | 1980 | 3 | 19 | 293 | 12 | 55 | 33.5 | 1.5 | 4799.75 |
| 3/20/1980 | 1980 | 3 | 20 | 294 | 29 | 54 | 41.5 | 9.5 | 4809.25 |
| 3/21/1980 | 1980 | 3 | 21 | 295 | 24 | 52 | 38 | 6 | 4815.25 |
| 3/22/1980 | 1980 | 3 | 22 | 296 | 29 | 59 | 44 | 12 | 4827.25 |
| 3/23/1980 | 1980 | 3 | 23 | 297 | 20 | 57 | 38.5 | 6.5 | 4833.75 |
| 3/24/1980 | 1980 | 3 | 24 | 298 | 23 | 47 | 35 | 3 | 4836.75 |
| 3/25/1980 | 1980 | 3 | 25 | 299 | 24 | 50 | 37 | 5 | 4841.75 |
| 3/26/1980 | 1980 | 3 | 26 | 300 | 29 | 49 | 39 | 7 | 4848.75 |
| 3/27/1980 | 1980 | 3 | 27 | 301 | 24 | 45 | 34.5 | 2.5 | 4851.25 |
| 3/28/1980 | 1980 | 3 | 28 | 302 | 27 | 40 | 33.5 | 1.5 | 4852.75 |
| 3/29/1980 | 1980 | 3 | 29 | 303 | 24 | 40 | 32 | 0 | 4852.75 |
| 3/30/1980 | 1980 | 3 | 30 | 304 | 23 | 43 | 33 | 1 | 4853.75 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/31/1980 | 1980 | 3 | 31 | 305 | 19 | 49 | 34 | 2 | 4855.75 |
| 4/1/1980 | 1980 | 4 | 1 | 306 | 13 | 49 | 31 | -1 | 4854.75 |
| 4/2/1980 | 1980 | 4 | 2 | 307 | 18 | 48 | 33 | 1 | 4855.75 |
| 4/3/1980 | 1980 | 4 | 3 | 308 | 19 | 49 | 34 | 2 | 4857.75 |
| 4/4/1980 | 1980 | 4 | 4 | 309 | 20 | 50 | 35 | 3 | 4860.75 |
| 4/5/1980 | 1980 | 4 | 5 | 310 | 22 | 56 | 39 | 7 | 4867.75 |
| 4/6/1980 | 1980 | 4 | 6 | 311 | 28 | 59 | 43.5 | 11.5 | 4879.25 |
| 4/7/1980 | 1980 | 4 | 7 | 312 | 30 | 58 | 44 | 12 | 4891.25 |
| 4/8/1980 | 1980 | 4 | 8 | 313 | 23 | 57 | 40 | 8 | 4899.25 |
| 4/9/1980 | 1980 | 4 | 9 | 314 | 20 | 59 | 39.5 | 7.5 | 4906.75 |
| 4/10/1980 | 1980 | 4 | 10 | 315 | 30 | 59 | 44.5 | 12.5 | 4919.25 |
| 4/11/1980 | 1980 | 4 | 11 | 316 | 24 | 60 | 42 | 10 | 4929.25 |
| 4/12/1980 | 1980 | 4 | 12 | 317 | 24 | 59 | 41.5 | 9.5 | 4938.75 |
| 4/13/1980 | 1980 | 4 | 13 | 318 | 20 | 49 | 34.5 | 2.5 | 4941.25 |
| 4/14/1980 | 1980 | 4 | 14 | 319 | 25 | 50 | 37.5 | 5.5 | 4946.75 |
| 4/15/1980 | 1980 | 4 | 15 | 320 | 32 | 59 | 45.5 | 13.5 | 4960.25 |
| 4/16/1980 | 1980 | 4 | 16 | 321 | 25 | 58 | 41.5 | 9.5 | 4969.75 |
| 4/17/1980 | 1980 | 4 | 17 | 322 | 32 | 60 | 46 | 14 | 4983.75 |
| 4/18/1980 | 1980 | 4 | 18 | 323 | 35 | 60 | 47.5 | 15.5 | 4999.25 |
| 4/19/1980 | 1980 | 4 | 19 | 324 | 41 | 69 | 55 | 23 | 5022.25 |
| 4/20/1980 | 1980 | 4 | 20 | 325 | 44 | 69 | 56.5 | 24.5 | 5046.75 |
| 4/21/1980 | 1980 | 4 | 21 | 326 | 43 | 65 | 54 | 22 | 5068.75 |
| 4/22/1980 | 1980 | 4 | 22 | 327 | 37 | 67 | 52 | 20 | 5088.75 |
| 4/23/1980 | 1980 | 4 | 23 | 328 | 38 | 65 | 51.5 | 19.5 | 5108.25 |
| 4/24/1980 | 1980 | 4 | 24 | 329 | 25 | 64 | 44.5 | 12.5 | 5120.75 |
| 4/25/1980 | 1980 | 4 | 25 | 330 | 24 | 48 | 36 | 4 | 5124.75 |
| 4/26/1980 | 1980 | 4 | 26 | 331 | 31 | 59 | 45 | 13 | 5137.75 |
| 4/27/1980 | 1980 | 4 | 27 | 332 | 34 | 61 | 47.5 | 15.5 | 5153.25 |
| 4/28/1980 | 1980 | 4 | 28 | 333 | 35 | 66 | 50.5 | 18.5 | 5171.75 |
| 4/29/1980 | 1980 | 4 | 29 | 334 | 46 | 69 | 57.5 | 25.5 | 5197.25 |
| 4/30/1980 | 1980 | 4 | 30 | 335 | 30 | 55 | 42.5 | 10.5 | 5207.75 |
| 5/1/1980 | 1980 | 5 | 1 | 336 | 33 | 60 | 46.5 | 14.5 | 5222.25 |
| 5/2/1980 | 1980 | 5 | 2 | 337 | 32 | 59 | 45.5 | 13.5 | 5235.75 |
| 5/3/1980 | 1980 | 5 | 3 | 338 | 34 | 58 | 46 | 14 | 5249.75 |
| 5/4/1980 | 1980 | 5 | 4 | 339 | 35 | 69 | 52 | 20 | 5269.75 |
| 5/5/1980 | 1980 | 5 | 5 | 340 | 45 | 55 | 50 | 18 | 5287.75 |
| 5/6/1980 | 1980 | 5 | 6 | 341 | 37 | 66 | 51.5 | 19.5 | 5307.25 |
| 5/7/1980 | 1980 | 5 | 7 | 342 | 26 | 63 | 44.5 | 12.5 | 5319.75 |
| 5/8/1980 | 1980 | 5 | 8 | 343 | 37 | 67 | 52 | 20 | 5339.75 |
| 5/9/1980 | 1980 | 5 | 9 | 344 | 39 | 65 | 52 | 20 | 5359.75 |
| 5/10/1980 | 1980 | 5 | 10 | 345 | 47 | 70 | 58.5 | 26.5 | 5386.25 |
| 5/11/1980 | 1980 | 5 | 11 | 346 | 45 | 67 | 56 | 24 | 5410.25 |
| 5/12/1980 | 1980 | 5 | 12 | 347 | 29 | 59 | 44 | 12 | 5422.25 |
| 5/13/1980 | 1980 | 5 | 13 | 348 | 30 | 64 | 47 | 15 | 5437.25 |
| 5/14/1980 | 1980 | 5 | 14 | 349 | 32 | 65 | 48.5 | 16.5 | 5453.75 |
| 5/15/1980 | 1980 | 5 | 15 | 350 | 35 | 64 | 49.5 | 17.5 | 5471.25 |
| 5/16/1980 | 1980 | 5 | 16 | 351 | 36 | 60 | 48 | 16 | 5487.25 |
| 5/17/1980 | 1980 | 5 | 17 | 352 | 45 | 65 | 55 | 23 | 5510.25 |
| 5/18/1980 | 1980 | 5 | 18 | 353 | 40 | 69 | 54.5 | 22.5 | 5532.75 |
| 5/19/1980 | 1980 | 5 | 19 | 354 | 42 | 71 | 56.5 | 24.5 | 5557.25 |
| 5/20/1980 | 1980 | 5 | 20 | 355 | 45 | 74 | 59.5 | 27.5 | 5584.75 |
| 5/21/1980 | 1980 | 5 | 21 | 356 | 46 | 79 | 62.5 | 30.5 | 5615.25 |
| 5/22/1980 | 1980 | 5 | 22 | 357 | 50 | 76 | 63 | 31 | 5646.25 |
| 5/23/1980 | 1980 | 5 | 23 | 358 | 40 | 77 | 58.5 | 26.5 | 5672.75 |
| 5/24/1980 | 1980 | 5 | 24 | 359 | 45 | 69 | 57 | 25 | 5697.75 |
| 5/25/1980 | 1980 | 5 | 25 | 360 | 28 | 67 | 47.5 | 15.5 | 5713.25 |
| 5/26/1980 | 1980 | 5 | 26 | 361 | 35 | 74 | 54.5 | 22.5 | 5735.75 |
| 5/27/1980 | 1980 | 5 | 27 | 362 | 40 | 75 | 57.5 | 25.5 | 5761.25 |
| 5/28/1980 | 1980 | 5 | 28 | 363 | 38 | 74 | 56 | 24 | 5785.25 |
| 5/29/1980 | 1980 | 5 | 29 | 364 | 40 | 75 | 57.5 | 25.5 | 5810.75 |
| 5/30/1980 | 1980 | 5 | 30 | 365 | 42 | 76 | 59 | 27 | 5837.75 |
| 5/31/1980 | 1980 | 5 | 31 | 366 | 40 | 76 | 58 | 26 | 5863.75 |
| 6/1/1980 | 1980 | 6 | 1 | 1 | 40 | 75 | 57.5 | 25.5 | 25.5 |
| 6/2/1980 | 1980 | 6 | 2 | 2 | 36 | 76 | 56 | 24 | 49.5 |
| 6/3/1980 | 1980 | 6 | 3 | 3 | 39 | 79 | 59 | 27 | 76.5 |
| 6/4/1980 | 1980 | 6 | 4 | 4 | 43 | 80 | 61.5 | 29.5 | 106 |
| 6/5/1980 | 1980 | 6 | 5 | 5 | 44 | 81 | 62.5 | 30.5 | 136.5 |
| 6/6/1980 | 1980 | 6 | 6 | 6 | 45 | 82 | 63.5 | 31.5 | 168 |
| 6/7/1980 | 1980 | 6 | 7 | 7 | 52 | 81 | 66.5 | 34.5 | 202.5 |
| 6/8/1980 | 1980 | 6 | 8 | 8 | 48 | 85 | 66.5 | 34.5 | 237 |
| 6/9/1980 | 1980 | 6 | 9 | 9 | 49 | 84 | 66.5 | 34.5 | 271.5 |
| 6/10/1980 | 1980 | 6 | 10 | 10 | 51 | 85 | 68 | 36 | 307.5 |
| 6/11/1980 | 1980 | 6 | 11 | 11 | 50 | 84 | 67 | 35 | 342.5 |
| 6/12/1980 | 1980 | 6 | 12 | 12 | 49 | 86 | 67.5 | 35.5 | 378 |
| 6/13/1980 | 1980 | 6 | 13 | 13 | 48 | 87 | 67.5 | 35.5 | 413.5 |
| 6/14/1980 | 1980 | 6 | 14 | 14 | 50 | 85 | 67.5 | 35.5 | 449 |
| 6/15/1980 | 1980 | 6 | 15 | 15 | 48 | 85 | 66.5 | 34.5 | 483.5 |
| 6/16/1980 | 1980 | 6 | 16 | 16 | 47 | 86 | 66.5 | 34.5 | 518 |
| 6/17/1980 | 1980 | 6 | 17 | 17 | 52 | 90 | 71 | 39 | 557 |
| 6/18/1980 | 1980 | 6 | 18 | 18 | 58 | 88 | 73 | 41 | 598 |
| 6/19/1980 | 1980 | 6 | 19 | 19 | 56 | 87 | 71.5 | 39.5 | 637.5 |
| 6/20/1980 | 1980 | 6 | 20 | 20 | 57 | 85 | 71 | 39 | 676.5 |
| 6/21/1980 | 1980 | 6 | 21 | 21 | 54 | 84 | 69 | 37 | 713.5 |
| 6/22/1980 | 1980 | 6 | 22 | 22 | 53 | 83 | 68 | 36 | 749.5 |
| 6/23/1980 | 1980 | 6 | 23 | 23 | 53 | 82 | 67.5 | 35.5 | 785 |
| 6/24/1980 | 1980 | 6 | 24 | 24 | 52 | 87 | 69.5 | 37.5 | 822.5 |
| 6/25/1980 | 1980 | 6 | 25 | 25 | 55 | 88 | 71.5 | 39.5 | 862 |
| 6/26/1980 | 1980 | 6 | 26 | 26 | 56 | 89 | 72.5 | 40.5 | 902.5 |
| 6/27/1980 | 1980 | 6 | 27 | 27 | 59 | 87 | 73 | 41 | 943.5 |
| 6/28/1980 | 1980 | 6 | 28 | 28 | 60 | 90 | 75 | 43 | 986.5 |
| 6/29/1980 | 1980 | 6 | 29 | 29 | 62 | 89 | 75.5 | 43.5 | 1030 |
| 6/30/1980 | 1980 | 6 | 30 | 30 | 60 | 92 | 76 | 44 | 1074 |
| 7/1/1980 | 1980 | 7 | 1 | 31 | 57 | 90 | 73.5 | 41.5 | 1115.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/2/1980 | 1980 | 7 | 2 | 32 | 52 | 85 | 68.5 | 36.5 | 1152 |
| 7/3/1980 | 1980 | 7 | 3 | 33 | 54 | 88 | 71 | 39 | 1191 |
| 7/4/1980 | 1980 | 7 | 4 | 34 | 58 | 89 | 73.5 | 41.5 | 1232.5 |
| 7/5/1980 | 1980 | 7 | 5 | 35 | 58 | 95 | 76.5 | 44.5 | 1277 |
| 7/6/1980 | 1980 | 7 | 6 | 36 | 63 | 91 | 77 | 45 | 1322 |
| 7/7/1980 | 1980 | 7 | 7 | 37 | 60 | 87 | 73.5 | 41.5 | 1363.5 |
| 7/8/1980 | 1980 | 7 | 8 | 38 | 53 | 85 | 69 | 37 | 1400.5 |
| 7/9/1980 | 1980 | 7 | 9 | 39 | 54 | 88 | 71 | 39 | 1439.5 |
| 7/10/1980 | 1980 | 7 | 10 | 40 | 59 | 90 | 74.5 | 42.5 | 1482 |
| 7/11/1980 | 1980 | 7 | 11 | 41 | 58 | 91 | 74.5 | 42.5 | 1524.5 |
| 7/12/1980 | 1980 | 7 | 12 | 42 | 57 | 89 | 73 | 41 | 1565.5 |
| 7/13/1980 | 1980 | 7 | 13 | 43 | 55 | 80 | 67.5 | 35.5 | 1601 |
| 7/14/1980 | 1980 | 7 | 14 | 44 | 52 | 79 | 65.5 | 33.5 | 1634.5 |
| 7/15/1980 | 1980 | 7 | 15 | 45 | 56 | 83 | 69.5 | 37.5 | 1672 |
| 7/16/1980 | 1980 | 7 | 16 | 46 | 55 | 89 | 72 | 40 | 1712 |
| 7/17/1980 | 1980 | 7 | 17 | 47 | 56 | 89 | 72.5 | 40.5 | 1752.5 |
| 7/18/1980 | 1980 | 7 | 18 | 48 | 57 | 92 | 74.5 | 42.5 | 1795 |
| 7/19/1980 | 1980 | 7 | 19 | 49 | 58 | 94 | 76 | 44 | 1839 |
| 7/20/1980 | 1980 | 7 | 20 | 50 | 65 | 92 | 78.5 | 46.5 | 1885.5 |
| 7/21/1980 | 1980 | 7 | 21 | 51 | 59 | 88 | 73.5 | 41.5 | 1927 |
| 7/22/1980 | 1980 | 7 | 22 | 52 | 54 | 80 | 67 | 35 | 1962 |
| 7/23/1980 | 1980 | 7 | 23 | 53 | 57 | 82 | 69.5 | 37.5 | 1999.5 |
| 7/24/1980 | 1980 | 7 | 24 | 54 | 53 | 83 | 68 | 36 | 2035.5 |
| 7/25/1980 | 1980 | 7 | 25 | 55 | 55 | 85 | 70 | 38 | 2073.5 |
| 7/26/1980 | 1980 | 7 | 26 | 56 | 56 | 90 | 73 | 41 | 2114.5 |
| 7/27/1980 | 1980 | 7 | 27 | 57 | 57 | 90 | 73.5 | 41.5 | 2156 |
| 7/28/1980 | 1980 | 7 | 28 | 58 | 58 | 91 | 74.5 | 42.5 | 2198.5 |
| 7/29/1980 | 1980 | 7 | 29 | 59 | 63 | 89 | 76 | 44 | 2242.5 |
| 7/30/1980 | 1980 | 7 | 30 | 60 | 63 | 87 | 75 | 43 | 2285.5 |
| 7/31/1980 | 1980 | 7 | 31 | 61 | 55 | 88 | 71.5 | 39.5 | 2325 |
| 8/1/1980 | 1980 | 8 | 1 | 62 | 64 | 86 | 75 | 43 | 2368 |
| 8/2/1980 | 1980 | 8 | 2 | 63 | 61 | 86 | 73.5 | 41.5 | 2409.5 |
| 8/3/1980 | 1980 | 8 | 3 | 64 | 58 | 83 | 70.5 | 38.5 | 2448 |
| 8/4/1980 | 1980 | 8 | 4 | 65 | 61 | 89 | 75 | 43 | 2491 |
| 8/5/1980 | 1980 | 8 | 5 | 66 | 57 | 81 | 69 | 37 | 2528 |
| 8/6/1980 | 1980 | 8 | 6 | 67 | 59 | 80 | 69.5 | 37.5 | 2565.5 |
| 8/7/1980 | 1980 | 8 | 7 | 68 | 58 | 85 | 71.5 | 39.5 | 2605 |
| 8/8/1980 | 1980 | 8 | 8 | 69 | 57 | 88 | 72.5 | 40.5 | 2645.5 |
| 8/9/1980 | 1980 | 8 | 9 | 70 | 54 | 85 | 69.5 | 37.5 | 2683 |
| 8/10/1980 | 1980 | 8 | 10 | 71 | 56 | 88 | 72 | 40 | 2723 |
| 8/11/1980 | 1980 | 8 | 11 | 72 | 58 | 82 | 70 | 38 | 2761 |
| 8/12/1980 | 1980 | 8 | 12 | 73 | 52 | 81 | 66.5 | 34.5 | 2795.5 |
| 8/13/1980 | 1980 | 8 | 13 | 74 | 53 | 80 | 66.5 | 34.5 | 2830 |
| 8/14/1980 | 1980 | 8 | 14 | 75 | 54 | 78 | 66 | 34 | 2864 |
| 8/15/1980 | 1980 | 8 | 15 | 76 | 55 | 78 | 66.5 | 34.5 | 2898.5 |
| 8/16/1980 | 1980 | 8 | 16 | 77 | 54 | 79 | 66.5 | 34.5 | 2933 |
| 8/17/1980 | 1980 | 8 | 17 | 78 | 54 | 80 | 67 | 35 | 2968 |
| 8/18/1980 | 1980 | 8 | 18 | 79 | 55 | 80 | 51.6 | 19.6 | 2987.6 |
| 8/19/1980 | 1980 | 8 | 19 | 80 | 54 | 80 | 67 | 35 | 3022.6 |
| 8/20/1980 | 1980 | 8 | 20 | 81 | 49 | 79 | 64 | 32 | 3054.6 |
| 8/21/1980 | 1980 | 8 | 21 | 82 | 49 | 82 | 65.5 | 33.5 | 3088.1 |
| 8/22/1980 | 1980 | 8 | 22 | 83 | 54 | 82 | 68 | 36 | 3124.1 |
| 8/23/1980 | 1980 | 8 | 23 | 84 | 59 | 77 | 68 | 36 | 3160.1 |
| 8/24/1980 | 1980 | 8 | 24 | 85 | 55 | 69 | 62 | 30 | 3190.1 |
| 8/25/1980 | 1980 | 8 | 25 | 86 | 52 | 76 | 64 | 32 | 3222.1 |
| 8/26/1980 | 1980 | 8 | 26 | 87 | 51 | 75 | 63 | 31 | 3253.1 |
| 8/27/1980 | 1980 | 8 | 27 | 88 | 49 | 79 | 64 | 32 | 3285.1 |
| 8/28/1980 | 1980 | 8 | 28 | 89 | 53 | 79 | 66 | 34 | 3319.1 |
| 8/29/1980 | 1980 | 8 | 29 | 90 | 54 | 79 | 66.5 | 34.5 | 3353.6 |
| 8/30/1980 | 1980 | 8 | 30 | 91 | 56 | 79 | 67.5 | 35.5 | 3389.1 |
| 8/31/1980 | 1980 | 8 | 31 | 92 | 47 | 76 | 61.5 | 29.5 | 3418.6 |
| 9/1/1980 | 1980 | 9 | 1 | 93 | 49 | 79 | 64 | 32 | 3450.6 |
| 9/2/1980 | 1980 | 9 | 2 | 94 | 51 | 80 | 65.5 | 33.5 | 3484.1 |
| 9/3/1980 | 1980 | 9 | 3 | 95 | 50 | 81 | 65.5 | 33.5 | 3517.6 |
| 9/4/1980 | 1980 | 9 | 4 | 96 | 52 | 81 | 66.5 | 34.5 | 3552.1 |
| 9/5/1980 | 1980 | 9 | 5 | 97 | 57 | 76 | 66.5 | 34.5 | 3586.6 |
| 9/6/1980 | 1980 | 9 | 6 | 98 | 55 | 72 | 63.5 | 31.5 | 3618.1 |
| 9/7/1980 | 1980 | 9 | 7 | 99 | 53 | 73 | 63 | 31 | 3649.1 |
| 9/8/1980 | 1980 | 9 | 8 | 100 | 52 | 72 | 62 | 30 | 3679.1 |
| 9/9/1980 | 1980 | 9 | 9 | 101 | 54 | 68 | 61 | 29 | 3708.1 |
| 9/10/1980 | 1980 | 9 | 10 | 102 | 52 | 69 | 60.5 | 28.5 | 3736.6 |
| 9/11/1980 | 1980 | 9 | 11 | 103 | 51 | 68 | 59.5 | 27.5 | 3764.1 |
| 9/12/1980 | 1980 | 9 | 12 | 104 | 48 | 70 | 59 | 27 | 3791.1 |
| 9/13/1980 | 1980 | 9 | 13 | 105 | 47 | 72 | 59.5 | 27.5 | 3818.6 |
| 9/14/1980 | 1980 | 9 | 14 | 106 | 49 | 73 | 61 | 29 | 3847.6 |
| 9/15/1980 | 1980 | 9 | 15 | 107 | 48 | 74 | 61 | 29 | 3876.6 |
| 9/16/1980 | 1980 | 9 | 16 | 108 | 51 | 76 | 63.5 | 31.5 | 3908.1 |
| 9/17/1980 | 1980 | 9 | 17 | 109 | 47 | 77 | 62 | 30 | 3938.1 |
| 9/18/1980 | 1980 | 9 | 18 | 110 | 49 | 79 | 64 | 32 | 3970.1 |
| 9/19/1980 | 1980 | 9 | 19 | 111 | 53 | 78 | 65.5 | 33.5 | 4003.6 |
| 9/20/1980 | 1980 | 9 | 20 | 112 | 50 | 77 | 63.5 | 31.5 | 4035.1 |
| 9/21/1980 | 1980 | 9 | 21 | 113 | 44 | 72 | 58 | 26 | 4061.1 |
| 9/22/1980 | 1980 | 9 | 22 | 114 | 43 | 77 | 60 | 28 | 4089.1 |
| 9/23/1980 | 1980 | 9 | 23 | 115 | 44 | 76 | 60 | 28 | 4117.1 |
| 9/24/1980 | 1980 | 9 | 24 | 116 | 45 | 74 | 59.5 | 27.5 | 4144.6 |
| 9/25/1980 | 1980 | 9 | 25 | 117 | 49 | 68 | 58.5 | 26.5 | 4171.1 |
| 9/26/1980 | 1980 | 9 | 26 | 118 | 43 | 71 | 57 | 25 | 4196.1 |
| 9/27/1980 | 1980 | 9 | 27 | 119 | 47 | 76 | 61.5 | 29.5 | 4225.6 |
| 9/28/1980 | 1980 | 9 | 28 | 120 | 47 | 76 | 61.5 | 29.5 | 4255.1 |
| 9/29/1980 | 1980 | 9 | 29 | 121 | 49 | 79 | 64 | 32 | 4287.1 |
| 9/30/1980 | 1980 | 9 | 30 | 122 | 48 | 78 | 63 | 31 | 4318.1 |
| 10/1/1980 | 1980 | 10 | 1 | 123 | 50 | 78 | 64 | 32 | 4350.1 |
| 10/2/1980 | 1980 | 10 | 2 | 124 | 43 | 79 | 61 | 29 | 4379.1 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/3/1980 | 1980 | 10 | 3 | 125 | 42 | 75 | 58.5 | 26.5 | 4405.6 |
| 10/4/1980 | 1980 | 10 | 4 | 126 | 44 | 76 | 60 | 28 | 4433.6 |
| 10/5/1980 | 1980 | 10 | 5 | 127 | 45 | 75 | 60 | 28 | 4461.6 |
| 10/6/1980 | 1980 | 10 | 6 | 128 | 47 | 70 | 58.5 | 26.5 | 4488.1 |
| 10/7/1980 | 1980 | 10 | 7 | 129 | 41 | 72 | 56.5 | 24.5 | 4512.6 |
| 10/8/1980 | 1980 | 10 | 8 | 130 | 44 | 72 | 58 | 26 | 4538.6 |
| 10/9/1980 | 1980 | 10 | 9 | 131 | 45 | 76 | 60.5 | 28.5 | 4567.1 |
| 10/10/1980 | 1980 | 10 | 10 | 132 | 40 | 76 | 58 | 26 | 4593.1 |
| 10/11/1980 | 1980 | 10 | 11 | 133 | 39 | 60 | 49.5 | 17.5 | 4610.6 |
| 10/12/1980 | 1980 | 10 | 12 | 134 | 40 | 61 | 50.5 | 18.5 | 4629.1 |
| 10/13/1980 | 1980 | 10 | 13 | 135 | 40 | 69 | 54.5 | 22.5 | 4651.6 |
| 10/14/1980 | 1980 | 10 | 14 | 136 | 41 | 64 | 52.5 | 20.5 | 4672.1 |
| 10/15/1980 | 1980 | 10 | 15 | 137 | 32 | 62 | 47 | 15 | 4687.1 |
| 10/16/1980 | 1980 | 10 | 16 | 138 | 29 | 52 | 40.5 | 8.5 | 4695.6 |
| 10/17/1980 | 1980 | 10 | 17 | 139 | 26 | 47 | 36.5 | 4.5 | 4700.1 |
| 10/18/1980 | 1980 | 10 | 18 | 140 | 25 | 50 | 37.5 | 5.5 | 4705.6 |
| 10/19/1980 | 1980 | 10 | 19 | 141 | 26 | 55 | 40.5 | 8.5 | 4714.1 |
| 10/20/1980 | 1980 | 10 | 20 | 142 | 29 | 56 | 42.5 | 10.5 | 4724.6 |
| 10/21/1980 | 1980 | 10 | 21 | 143 | 31 | 57 | 44 | 12 | 4736.6 |
| 10/22/1980 | 1980 | 10 | 22 | 144 | 30 | 56 | 43 | 11 | 4747.6 |
| 10/23/1980 | 1980 | 10 | 23 | 145 | 29 | 50 | 39.5 | 7.5 | 4755.1 |
| 10/24/1980 | 1980 | 10 | 24 | 146 | 23 | 53 | 38 | 6 | 4761.1 |
| 10/25/1980 | 1980 | 10 | 25 | 147 | 28 | 67 | 47.5 | 15.5 | 4776.6 |
| 10/26/1980 | 1980 | 10 | 26 | 148 | 29 | 63 | 46 | 14 | 4790.6 |
| 10/27/1980 | 1980 | 10 | 27 | 149 | 29 | 39 | 34 | 2 | 4792.6 |
| 10/28/1980 | 1980 | 10 | 28 | 150 | 25 | 38 | 31.5 | -0.5 | 4792.1 |
| 10/29/1980 | 1980 | 10 | 29 | 151 | 21 | 48 | 34.5 | 2.5 | 4794.6 |
| 10/30/1980 | 1980 | 10 | 30 | 152 | 25 | 58 | 41.5 | 9.5 | 4804.1 |
| 10/31/1980 | 1980 | 10 | 31 | 153 | 32 | 57 | 44.5 | 12.5 | 4816.6 |
| 11/1/1980 | 1980 | 11 | 1 | 154 | 28 | 56 | 42 | 10 | 4826.6 |
| 11/2/1980 | 1980 | 11 | 2 | 155 | 29 | 57 | 43 | 11 | 4837.6 |
| 11/3/1980 | 1980 | 11 | 3 | 156 | 31 | 59 | 45 | 13 | 4850.6 |
| 11/4/1980 | 1980 | 11 | 4 | 157 | 32 | 60 | 46 | 14 | 4864.6 |
| 11/5/1980 | 1980 | 11 | 5 | 158 | 34 | 60 | 47 | 15 | 4879.6 |
| 11/6/1980 | 1980 | 11 | 6 | 159 | 38 | 61 | 49.5 | 17.5 | 4897.1 |
| 11/7/1980 | 1980 | 11 | 7 | 160 | 36 | 63 | 49.5 | 17.5 | 4914.6 |
| 11/8/1980 | 1980 | 11 | 8 | 161 | 37 | 66 | 51.5 | 19.5 | 4934.1 |
| 11/9/1980 | 1980 | 11 | 9 | 162 | 36 | 66 | 51 | 19 | 4953.1 |
| 11/10/1980 | 1980 | 11 | 10 | 163 | 39 | 69 | 54 | 22 | 4975.1 |
| 11/11/1980 | 1980 | 11 | 11 | 164 | 38 | 69 | 53.5 | 21.5 | 4996.6 |
| 11/12/1980 | 1980 | 11 | 12 | 165 | 36 | 68 | 52 | 20 | 5016.6 |
| 11/13/1980 | 1980 | 11 | 13 | 166 | 37 | 65 | 51 | 19 | 5035.6 |
| 11/14/1980 | 1980 | 11 | 14 | 167 | 38 | 61 | 49.5 | 17.5 | 5053.1 |
| 11/15/1980 | 1980 | 11 | 15 | 168 | 15 | 61 | 38 | 6 | 5059.1 |
| 11/16/1980 | 1980 | 11 | 16 | 169 | 11 | 48 | 29.5 | -2.5 | 5056.6 |
| 11/17/1980 | 1980 | 11 | 17 | 170 | 17 | 37 | 27 | -5 | 5051.6 |
| 11/18/1980 | 1980 | 11 | 18 | 171 | 10 | 35 | 22.5 | -9.5 | 5042.1 |
| 11/19/1980 | 1980 | 11 | 19 | 172 | 11 | 34 | 22.5 | -9.5 | 5032.6 |
| 11/20/1980 | 1980 | 11 | 20 | 173 | 12 | 40 | 26 | -6 | 5026.6 |
| 11/21/1980 | 1980 | 11 | 21 | 174 | 11 | 44 | 27.5 | -4.5 | 5022.1 |
| 11/22/1980 | 1980 | 11 | 22 | 175 | 17 | 45 | 31 | -1 | 5021.1 |
| 11/23/1980 | 1980 | 11 | 23 | 176 | 19 | 46 | 32.5 | 0.5 | 5021.6 |
| 11/24/1980 | 1980 | 11 | 24 | 177 | 16 | 45 | 30.5 | -1.5 | 5020.1 |
| 11/25/1980 | 1980 | 11 | 25 | 178 | 14 | 43 | 28.5 | -3.5 | 5016.6 |
| 11/26/1980 | 1980 | 11 | 26 | 179 | 20 | 42 | 31 | -1 | 5015.6 |
| 11/27/1980 | 1980 | 11 | 27 | 180 | 20 | 40 | 30 | -2 | 5013.6 |
| 11/28/1980 | 1980 | 11 | 28 | 181 | 15 | 39 | 27 | -5 | 5008.6 |
| 11/29/1980 | 1980 | 11 | 29 | 182 | 14 | 28 | 21 | -11 | 4997.6 |
| 11/30/1980 | 1980 | 11 | 30 | 183 | 14 | 30 | 22 | -10 | 4987.6 |
| 12/1/1980 | 1980 | 12 | 1 | 184 | 15 | 50 | 32.5 | 0.5 | 4988.1 |
| 12/2/1980 | 1980 | 12 | 2 | 185 | 27 | 56 | 41.5 | 9.5 | 4997.6 |
| 12/3/1980 | 1980 | 12 | 3 | 186 | 30 | 59 | 44.5 | 12.5 | 5010.1 |
| 12/4/1980 | 1980 | 12 | 4 | 187 | 31 | 60 | 45.5 | 13.5 | 5023.6 |
| 12/5/1980 | 1980 | 12 | 5 | 188 | 30 | 57 | 43.5 | 11.5 | 5035.1 |
| 12/6/1980 | 1980 | 12 | 6 | 189 | 31 | 48 | 39.5 | 7.5 | 5042.6 |
| 12/7/1980 | 1980 | 12 | 7 | 190 | 25 | 50 | 37.5 | 5.5 | 5048.1 |
| 12/8/1980 | 1980 | 12 | 8 | 191 | 31 | 43 | 37 | 5 | 5053.1 |
| 12/9/1980 | 1980 | 12 | 9 | 192 | 26 | 40 | 33 | 1 | 5054.1 |
| 12/10/1980 | 1980 | 12 | 10 | 193 | 18 | 32 | 25 | -7 | 5047.1 |
| 12/11/1980 | 1980 | 12 | 11 | 194 | 15 | 36 | 25.5 | -6.5 | 5040.6 |
| 12/12/1980 | 1980 | 12 | 12 | 195 | 13 | 39 | 26 | -6 | 5034.6 |
| 12/13/1980 | 1980 | 12 | 13 | 196 | 16 | 39 | 27.5 | -4.5 | 5030.1 |
| 12/14/1980 | 1980 | 12 | 14 | 197 | 21 | 47 | 34 | 2 | 5032.1 |
| 12/15/1980 | 1980 | 12 | 15 | 198 | 22 | 45 | 33.5 | 1.5 | 5033.6 |
| 12/16/1980 | 1980 | 12 | 16 | 199 | 23 | 45 | 34 | 2 | 5035.6 |
| 12/17/1980 | 1980 | 12 | 17 | 200 | 24 | 40 | 32 | 0 | 5035.6 |
| 12/18/1980 | 1980 | 12 | 18 | 201 | 24 | 46 | 35 | 3 | 5038.6 |
| 12/19/1980 | 1980 | 12 | 19 | 202 | 28 | 50 | 39 | 7 | 5045.6 |
| 12/20/1980 | 1980 | 12 | 20 | 203 | 27 | 60 | 43.5 | 11.5 | 5057.1 |
| 12/21/1980 | 1980 | 12 | 21 | 204 | 30 | 60 | 45 | 13 | 5070.1 |
| 12/22/1980 | 1980 | 12 | 22 | 205 | 33 | 60 | 46.5 | 14.5 | 5084.6 |
| 12/23/1980 | 1980 | 12 | 23 | 206 | 15 | 55 | 35 | 3 | 5087.6 |
| 12/24/1980 | 1980 | 12 | 24 | 207 | 20 | 49 | 34.5 | 2.5 | 5090.1 |
| 12/25/1980 | 1980 | 12 | 25 | 208 | 22 | 49 | 35.5 | 3.5 | 5093.6 |
| 12/26/1980 | 1980 | 12 | 26 | 209 | 23 | 50 | 36.5 | 4.5 | 5098.1 |
| 12/27/1980 | 1980 | 12 | 27 | 210 | 31 | 56 | 43.5 | 11.5 | 5109.6 |
| 12/28/1980 | 1980 | 12 | 28 | 211 | 29 | 68 | 48.5 | 16.5 | 5126.1 |
| 12/29/1980 | 1980 | 12 | 29 | 212 | 28 | 50 | 39 | 7 | 5133.1 |
| 12/30/1980 | 1980 | 12 | 30 | 213 | 29 | 49 | 39 | 7 | 5140.1 |
| 12/31/1980 | 1980 | 12 | 31 | 214 | 25 | 57 | 41 | 9 | 5149.1 |
| 1/1/1981 | 1981 | 1 | 1 | 215 | 25 | 57 | 41 | 9 | 5158.1 |
| 1/2/1981 | 1981 | 1 | 2 | 216 | 28 | 50 | 39 | 7 | 5165.1 |
| 1/3/1981 | 1981 | 1 | 3 | 217 | 27 | 56 | 41.5 | 9.5 | 5174.6 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/4/1981 | 1981 | 1 | 4 | 218 | 26 | 55 | 40.5 | 8.5 | 5183.1 |
| 1/5/1981 | 1981 | 1 | 5 | 219 | 27 | 54 | 40.5 | 8.5 | 5191.6 |
| 1/6/1981 | 1981 | 1 | 6 | 220 | 34 | 51 | 42.5 | 10.5 | 5202.1 |
| 1/7/1981 | 1981 | 1 | 7 | 221 | 18 | 46 | 32 | 0 | 5202.1 |
| 1/8/1981 | 1981 | 1 | 8 | 222 | 18 | 45 | 31.5 | -0.5 | 5201.6 |
| 1/9/1981 | 1981 | 1 | 9 | 223 | 19 | 48 | 33.5 | 1.5 | 5203.1 |
| 1/10/1981 | 1981 | 1 | 10 | 224 | 30 | 50 | 40 | 8 | 5211.1 |
| 1/11/1981 | 1981 | 1 | 11 | 225 | 30 | 50 | 40 | 8 | 5219.1 |
| 1/12/1981 | 1981 | 1 | 12 | 226 | 21 | 45 | 33 | 1 | 5220.1 |
| 1/13/1981 | 1981 | 1 | 13 | 227 | 22 | 40 | 31 | -1 | 5219.1 |
| 1/14/1981 | 1981 | 1 | 14 | 228 | 27 | 49 | 38 | 6 | 5225.1 |
| 1/15/1981 | 1981 | 1 | 15 | 229 | 19 | 50 | 34.5 | 2.5 | 5227.6 |
| 1/16/1981 | 1981 | 1 | 16 | 230 | 21 | 48 | 34.5 | 2.5 | 5230.1 |
| 1/17/1981 | 1981 | 1 | 17 | 231 | 26 | 47 | 36.5 | 4.5 | 5234.6 |
| 1/18/1981 | 1981 | 1 | 18 | 232 | 19 | 45 | 32 | 0 | 5234.6 |
| 1/19/1981 | 1981 | 1 | 19 | 233 | 20 | 47 | 33.5 | 1.5 | 5236.1 |
| 1/20/1981 | 1981 | 1 | 20 | 234 | 18 | 44 | 31 | -1 | 5235.1 |
| 1/21/1981 | 1981 | 1 | 21 | 235 | 20 | 47 | 33.5 | 1.5 | 5236.6 |
| 1/22/1981 | 1981 | 1 | 22 | 236 | 14 | 46 | 30 | -2 | 5234.6 |
| 1/23/1981 | 1981 | 1 | 23 | 237 | 15 | 49 | 32 | 0 | 5234.6 |
| 1/24/1981 | 1981 | 1 | 24 | 238 | 23 | 50 | 36.5 | 4.5 | 5239.1 |
| 1/25/1981 | 1981 | 1 | 25 | 239 | 20 | 51 | 35.5 | 3.5 | 5242.6 |
| 1/26/1981 | 1981 | 1 | 26 | 240 | 34 | 50 | 42 | 10 | 5252.6 |
| 1/27/1981 | 1981 | 1 | 27 | 241 | 29 | 49 | 39 | 7 | 5259.6 |
| 1/28/1981 | 1981 | 1 | 28 | 242 | 14 | 44 | 29 | -3 | 5256.6 |
| 1/29/1981 | 1981 | 1 | 29 | 243 | 13 | 45 | 29 | -3 | 5253.6 |
| 1/30/1981 | 1981 | 1 | 30 | 244 | 16 | 46 | 31 | -1 | 5252.6 |
| 1/31/1981 | 1981 | 1 | 31 | 245 | 17 | 46 | 31.5 | -0.5 | 5252.1 |
| 2/1/1981 | 1981 | 2 | 1 | 246 | 10 | 44 | 27 | -5 | 5247.1 |
| 2/2/1981 | 1981 | 2 | 2 | 247 | 11 | 41 | 26 | -6 | 5241.1 |
| 2/3/1981 | 1981 | 2 | 3 | 248 | 15 | 45 | 30 | -2 | 5239.1 |
| 2/4/1981 | 1981 | 2 | 4 | 249 | 16 | 50 | 33 | 1 | 5240.1 |
| 2/5/1981 | 1981 | 2 | 5 | 250 | 15 | 45 | 30 | -2 | 5238.1 |
| 2/6/1981 | 1981 | 2 | 6 | 251 | 16 | 46 | 31 | -1 | 5237.1 |
| 2/7/1981 | 1981 | 2 | 7 | 252 | 17 | 48 | 32.5 | 0.5 | 5237.6 |
| 2/8/1981 | 1981 | 2 | 8 | 253 | 20 | 50 | 35 | 3 | 5240.6 |
| 2/9/1981 | 1981 | 2 | 9 | 254 | 21 | 49 | 35 | 3 | 5243.6 |
| 2/10/1981 | 1981 | 2 | 10 | 255 | 29 | 49 | 39 | 7 | 5250.6 |
| 2/11/1981 | 1981 | 2 | 11 | 256 | 9 | 32 | 20.5 | -11.5 | 5239.1 |
| 2/12/1981 | 1981 | 2 | 12 | 257 | 10 | 44 | 27 | -5 | 5234.1 |
| 2/13/1981 | 1981 | 2 | 13 | 258 | 20 | 42 | 31 | -1 | 5233.1 |
| 2/14/1981 | 1981 | 2 | 14 | 259 | 19 | 50 | 34.5 | 2.5 | 5235.6 |
| 2/15/1981 | 1981 | 2 | 15 | 260 | 18 | 49 | 33.5 | 1.5 | 5237.1 |
| 2/16/1981 | 1981 | 2 | 16 | 261 | 17 | 48 | 32.5 | 0.5 | 5237.6 |
| 2/17/1981 | 1981 | 2 | 17 | 262 | 18 | 56 | 37 | 5 | 5242.6 |
| 2/18/1981 | 1981 | 2 | 18 | 263 | 23 | 62 | 42.5 | 10.5 | 5253.1 |
| 2/19/1981 | 1981 | 2 | 19 | 264 | 24 | 59 | 41.5 | 9.5 | 5262.6 |
| 2/20/1981 | 1981 | 2 | 20 | 265 | 25 | 59 | 42 | 10 | 5272.6 |
| 2/21/1981 | 1981 | 2 | 21 | 266 | 30 | 63 | 46.5 | 14.5 | 5287.1 |
| 2/22/1981 | 1981 | 2 | 22 | 267 | 36 | 64 | 50 | 18 | 5305.1 |
| 2/23/1981 | 1981 | 2 | 23 | 268 | 18 | 58 | 38 | 6 | 5311.1 |
| 2/24/1981 | 1981 | 2 | 24 | 269 | 19 | 52 | 35.5 | 3.5 | 5314.6 |
| 2/25/1981 | 1981 | 2 | 25 | 270 | 19 | 61 | 40 | 8 | 5322.6 |
| 2/26/1981 | 1981 | 2 | 26 | 271 | 17 | 57 | 37 | 5 | 5327.6 |
| 2/27/1981 | 1981 | 2 | 27 | 272 | 19 | 59 | 39 | 7 | 5334.6 |
| 2/28/1981 | 1981 | 2 | 28 | 273 | 20 | 59 | 39.5 | 7.5 | 5342.1 |
| 3/1/1981 | 1981 | 3 | 1 | 274 | 25 | 54 | 39.5 | 7.5 | 5349.6 |
| 3/2/1981 | 1981 | 3 | 2 | 275 | 30 | 50 | 40 | 8 | 5357.6 |
| 3/3/1981 | 1981 | 3 | 3 | 276 | 18 | 41 | 29.5 | -2.5 | 5355.1 |
| 3/4/1981 | 1981 | 3 | 4 | 277 | 20 | 40 | 30 | -2 | 5353.1 |
| 3/5/1981 | 1981 | 3 | 5 | 278 | 20 | 46 | 33 | 1 | 5354.1 |
| 3/6/1981 | 1981 | 3 | 6 | 279 | 23 | 44 | 33.5 | 1.5 | 5355.6 |
| 3/7/1981 | 1981 | 3 | 7 | 280 | 25 | 38 | 31.5 | -0.5 | 5355.1 |
| 3/8/1981 | 1981 | 3 | 8 | 281 | 23 | 42 | 32.5 | 0.5 | 5355.6 |
| 3/9/1981 | 1981 | 3 | 9 | 282 | 25 | 48 | 36.5 | 4.5 | 5360.1 |
| 3/10/1981 | 1981 | 3 | 10 | 283 | 20 | 43 | 31.5 | -0.5 | 5359.6 |
| 3/11/1981 | 1981 | 3 | 11 | 284 | 19 | 40 | 29.5 | -2.5 | 5357.1 |
| 3/12/1981 | 1981 | 3 | 12 | 285 | 20 | 40 | 30 | -2 | 5355.1 |
| 3/13/1981 | 1981 | 3 | 13 | 286 | 19 | 45 | 32 | 0 | 5355.1 |
| 3/14/1981 | 1981 | 3 | 14 | 287 | 25 | 46 | 35.5 | 3.5 | 5358.6 |
| 3/15/1981 | 1981 | 3 | 15 | 288 | 20 | 47 | 33.5 | 1.5 | 5360.1 |
| 3/16/1981 | 1981 | 3 | 16 | 289 | 20 | 47 | 33.5 | 1.5 | 5361.6 |
| 3/17/1981 | 1981 | 3 | 17 | 290 | 27 | 50 | 38.5 | 6.5 | 5368.1 |
| 3/18/1981 | 1981 | 3 | 18 | 291 | 28 | 55 | 41.5 | 9.5 | 5377.6 |
| 3/19/1981 | 1981 | 3 | 19 | 292 | 30 | 52 | 41 | 9 | 5386.6 |
| 3/20/1981 | 1981 | 3 | 20 | 293 | 19 | 49 | 34 | 2 | 5388.6 |
| 3/21/1981 | 1981 | 3 | 21 | 294 | 24 | 60 | 42 | 10 | 5398.6 |
| 3/22/1981 | 1981 | 3 | 22 | 295 | 37 | 58 | 47.5 | 15.5 | 5414.1 |
| 3/23/1981 | 1981 | 3 | 23 | 296 | 24 | 56 | 40 | 8 | 5422.1 |
| 3/24/1981 | 1981 | 3 | 24 | 297 | 24 | 57 | 40.5 | 8.5 | 5430.6 |
| 3/25/1981 | 1981 | 3 | 25 | 298 | 25 | 60 | 42.5 | 10.5 | 5441.1 |
| 3/26/1981 | 1981 | 3 | 26 | 299 | 33 | 61 | 47 | 15 | 5456.1 |
| 3/27/1981 | 1981 | 3 | 27 | 300 | 24 | 59 | 41.5 | 9.5 | 5465.6 |
| 3/28/1981 | 1981 | 3 | 28 | 301 | 37 | 66 | 51.5 | 19.5 | 5485.1 |
| 3/29/1981 | 1981 | 3 | 29 | 302 | 28 | 62 | 45 | 13 | 5498.1 |
| 3/30/1981 | 1981 | 3 | 30 | 303 | 25 | 44 | 34.5 | 2.5 | 5500.6 |
| 3/31/1981 | 1981 | 3 | 31 | 304 | 21 | 55 | 38 | 6 | 5506.6 |
| 4/1/1981 | 1981 | 4 | 1 | 305 | 26 | 64 | 45 | 13 | 5519.6 |
| 4/2/1981 | 1981 | 4 | 2 | 306 | 35 | 62 | 48.5 | 16.5 | 5536.1 |
| 4/3/1981 | 1981 | 4 | 3 | 307 | 21 | 59 | 40 | 8 | 5544.1 |
| 4/4/1981 | 1981 | 4 | 4 | 308 | 22 | 62 | 42 | 10 | 5554.1 |
| 4/5/1981 | 1981 | 4 | 5 | 309 | 32 | 66 | 49 | 17 | 5571.1 |
| 4/6/1981 | 1981 | 4 | 6 | 310 | 36 | 64 | 50 | 18 | 5589.1 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/7/1981 | 1981 | 4 | 7 | 311 | 35 | 62 | 48.5 | 16.5 | 5605.6 |
| 4/8/1981 | 1981 | 4 | 8 | 312 | 34 | 71 | 52.5 | 20.5 | 5626.1 |
| 4/9/1981 | 1981 | 4 | 9 | 313 | 32 | 69 | 50.5 | 18.5 | 5644.6 |
| 4/10/1981 | 1981 | 4 | 10 | 314 | 36 | 70 | 53 | 21 | 5665.6 |
| 4/11/1981 | 1981 | 4 | 11 | 315 | 34 | 66 | 50 | 18 | 5683.6 |
| 4/12/1981 | 1981 | 4 | 12 | 316 | 39 | 67 | 53 | 21 | 5704.6 |
| 4/13/1981 | 1981 | 4 | 13 | 317 | 40 | 65 | 52.5 | 20.5 | 5725.1 |
| 4/14/1981 | 1981 | 4 | 14 | 318 | 35 | 61 | 48 | 16 | 5741.1 |
| 4/15/1981 | 1981 | 4 | 15 | 319 | 34 | 68 | 51 | 19 | 5760.1 |
| 4/16/1981 | 1981 | 4 | 16 | 320 | 41 | 72 | 56.5 | 24.5 | 5784.6 |
| 4/17/1981 | 1981 | 4 | 17 | 321 | 42 | 65 | 53.5 | 21.5 | 5806.1 |
| 4/18/1981 | 1981 | 4 | 18 | 322 | 35 | 64 | 49.5 | 17.5 | 5823.6 |
| 4/19/1981 | 1981 | 4 | 19 | 323 | 35 | 64 | 49.5 | 17.5 | 5841.1 |
| 4/20/1981 | 1981 | 4 | 20 | 324 | 40 | 69 | 54.5 | 22.5 | 5863.6 |
| 4/21/1981 | 1981 | 4 | 21 | 325 | 36 | 66 | 51 | 19 | 5882.6 |
| 4/22/1981 | 1981 | 4 | 22 | 326 | 34 | 68 | 51 | 19 | 5901.6 |
| 4/23/1981 | 1981 | 4 | 23 | 327 | 36 | 67 | 51.5 | 19.5 | 5921.1 |
| 4/24/1981 | 1981 | 4 | 24 | 328 | 39 | 73 | 56 | 24 | 5945.1 |
| 4/25/1981 | 1981 | 4 | 25 | 329 | 44 | 78 | 61 | 29 | 5974.1 |
| 4/26/1981 | 1981 | 4 | 26 | 330 | 43 | 77 | 60 | 28 | 6002.1 |
| 4/27/1981 | 1981 | 4 | 27 | 331 | 44 | 74 | 59 | 27 | 6029.1 |
| 4/28/1981 | 1981 | 4 | 28 | 332 | 57 | 75 | 66 | 34 | 6063.1 |
| 4/29/1981 | 1981 | 4 | 29 | 333 | 45 | 76 | 60.5 | 28.5 | 6091.6 |
| 4/30/1981 | 1981 | 4 | 30 | 334 | 48 | 70 | 59 | 27 | 6118.6 |
| 5/1/1981 | 1981 | 5 | 1 | 335 | 47 | 72 | 59.5 | 27.5 | 6146.1 |
| 5/2/1981 | 1981 | 5 | 2 | 336 | 43 | 70 | 56.5 | 24.5 | 6170.6 |
| 5/3/1981 | 1981 | 5 | 3 | 337 | 47 | 69 | 58 | 26 | 6196.6 |
| 5/4/1981 | 1981 | 5 | 4 | 338 | 48 | 68 | 58 | 26 | 6222.6 |
| 5/5/1981 | 1981 | 5 | 5 | 339 | 39 | 70 | 54.5 | 22.5 | 6245.1 |
| 5/6/1981 | 1981 | 5 | 6 | 340 | 38 | 68 | 53 | 21 | 6266.1 |
| 5/7/1981 | 1981 | 5 | 7 | 341 | 38 | 69 | 53.5 | 21.5 | 6287.6 |
| 5/8/1981 | 1981 | 5 | 8 | 342 | 36 | 68 | 52 | 20 | 6307.6 |
| 5/9/1981 | 1981 | 5 | 9 | 343 | 29 | 69 | 49 | 17 | 6324.6 |
| 5/10/1981 | 1981 | 5 | 10 | 344 | 29 | 69 | 49 | 17 | 6341.6 |
| 5/11/1981 | 1981 | 5 | 11 | 345 | 40 | 70 | 55 | 23 | 6364.6 |
| 5/12/1981 | 1981 | 5 | 12 | 346 | 46 | 72 | 59 | 27 | 6391.6 |
| 5/13/1981 | 1981 | 5 | 13 | 347 | 45 | 75 | 60 | 28 | 6419.6 |
| 5/14/1981 | 1981 | 5 | 14 | 348 | 38 | 74 | 56 | 24 | 6443.6 |
| 5/15/1981 | 1981 | 5 | 15 | 349 | 43 | 67 | 55 | 23 | 6466.6 |
| 5/16/1981 | 1981 | 5 | 16 | 350 | 42 | 68 | 55 | 23 | 6489.6 |
| 5/17/1981 | 1981 | 5 | 17 | 351 | 42 | 68 | 55 | 23 | 6512.6 |
| 5/18/1981 | 1981 | 5 | 18 | 352 | 34 | 71 | 52.5 | 20.5 | 6533.1 |
| 5/19/1981 | 1981 | 5 | 19 | 353 | 41 | 74 | 57.5 | 25.5 | 6558.6 |
| 5/20/1981 | 1981 | 5 | 20 | 354 | 44 | 71 | 57.5 | 25.5 | 6584.1 |
| 5/21/1981 | 1981 | 5 | 21 | 355 | 41 | 69 | 55 | 23 | 6607.1 |
| 5/22/1981 | 1981 | 5 | 22 | 356 | 39 | 71 | 55 | 23 | 6630.1 |
| 5/23/1981 | 1981 | 5 | 23 | 357 | 38 | 70 | 54 | 22 | 6652.1 |
| 5/24/1981 | 1981 | 5 | 24 | 358 | 37 | 69 | 53 | 21 | 6673.1 |
| 5/25/1981 | 1981 | 5 | 25 | 359 | 41 | 70 | 55.5 | 23.5 | 6696.6 |
| 5/26/1981 | 1981 | 5 | 26 | 360 | 49 | 72 | 60.5 | 28.5 | 6725.1 |
| 5/27/1981 | 1981 | 5 | 27 | 361 | 47 | 78 | 62.5 | 30.5 | 6755.6 |
| 5/28/1981 | 1981 | 5 | 28 | 362 | 46 | 74 | 60 | 28 | 6783.6 |
| 5/29/1981 | 1981 | 5 | 29 | 363 | 43 | 69 | 56 | 24 | 6807.6 |
| 5/30/1981 | 1981 | 5 | 30 | 364 | 47 | 67 | 57 | 25 | 6832.6 |
| 5/31/1981 | 1981 | 5 | 31 | 365 | 40 | 71 | 55.5 | 23.5 | 6856.1 |
| 6/1/1981 | 1981 | 6 | 1 | 1 | 42 | 71 | 56.5 | 24.5 | 24.5 |
| 6/2/1981 | 1981 | 6 | 2 | 2 | 47 | 80 | 63.5 | 31.5 | 56 |
| 6/3/1981 | 1981 | 6 | 3 | 3 | 49 | 79 | 64 | 32 | 88 |
| 6/4/1981 | 1981 | 6 | 4 | 4 | 48 | 78 | 63 | 31 | 119 |
| 6/5/1981 | 1981 | 6 | 5 | 5 | 49 | 79 | 64 | 32 | 151 |
| 6/6/1981 | 1981 | 6 | 6 | 6 | 50 | 80 | 65 | 33 | 184 |
| 6/7/1981 | 1981 | 6 | 7 | 7 | 55 | 81 | 68 | 36 | 220 |
| 6/8/1981 | 1981 | 6 | 8 | 8 | 56 | 83 | 69.5 | 37.5 | 257.5 |
| 6/9/1981 | 1981 | 6 | 9 | 9 | 57 | 90 | 73.5 | 41.5 | 299 |
| 6/10/1981 | 1981 | 6 | 10 | 10 | 57 | 90 | 73.5 | 41.5 | 340.5 |
| 6/11/1981 | 1981 | 6 | 11 | 11 | 59 | 93 | 76 | 44 | 384.5 |
| 6/12/1981 | 1981 | 6 | 12 | 12 | 57 | 91 | 74 | 42 | 426.5 |
| 6/13/1981 | 1981 | 6 | 13 | 13 | 55 | 88 | 71.5 | 39.5 | 466 |
| 6/14/1981 | 1981 | 6 | 14 | 14 | 56 | 86 | 71 | 39 | 505 |
| 6/15/1981 | 1981 | 6 | 15 | 15 | 53 | 81 | 67 | 35 | 540 |
| 6/16/1981 | 1981 | 6 | 16 | 16 | 35 | 79 | 57 | 25 | 565 |
| 6/17/1981 | 1981 | 6 | 17 | 17 | 43 | 76 | 59.5 | 27.5 | 592.5 |
| 6/18/1981 | 1981 | 6 | 18 | 18 | 49 | 88 | 68.5 | 36.5 | 629 |
| 6/19/1981 | 1981 | 6 | 19 | 19 | 53 | 92 | 72.5 | 40.5 | 669.5 |
| 6/20/1981 | 1981 | 6 | 20 | 20 | 56 | 93 | 74.5 | 42.5 | 712 |
| 6/21/1981 | 1981 | 6 | 21 | 21 | 57 | 93 | 75 | 43 | 755 |
| 6/22/1981 | 1981 | 6 | 22 | 22 | 60 | 95 | 77.5 | 45.5 | 800.5 |
| 6/23/1981 | 1981 | 6 | 23 | 23 | 59 | 90 | 74.5 | 42.5 | 843 |
| 6/24/1981 | 1981 | 6 | 24 | 24 | 62 | 94 | 78 | 46 | 889 |
| 6/25/1981 | 1981 | 6 | 25 | 25 | 59 | 95 | 77 | 45 | 934 |
| 6/26/1981 | 1981 | 6 | 26 | 26 | 66 | 93 | 79.5 | 47.5 | 981.5 |
| 6/27/1981 | 1981 | 6 | 27 | 27 | 62 | 86 | 74 | 42 | 1023.5 |
| 6/28/1981 | 1981 | 6 | 28 | 28 | 59 | 87 | 73 | 41 | 1064.5 |
| 6/29/1981 | 1981 | 6 | 29 | 29 | 54 | 81 | 67.5 | 35.5 | 1100 |
| 6/30/1981 | 1981 | 6 | 30 | 30 | 53 | 87 | 70 | 38 | 1138 |
| 7/1/1981 | 1981 | 7 | 1 | 31 | 55 | 70 | 62.5 | 30.5 | 1168.5 |
| 7/2/1981 | 1981 | 7 | 2 | 32 | 51 | 81 | 66 | 34 | 1202.5 |
| 7/3/1981 | 1981 | 7 | 3 | 33 | 56 | 85 | 70.5 | 38.5 | 1241 |
| 7/4/1981 | 1981 | 7 | 4 | 34 | 55 | 84 | 69.5 | 37.5 | 1278.5 |
| 7/5/1981 | 1981 | 7 | 5 | 35 | 54 | 80 | 67 | 35 | 1313.5 |
| 7/6/1981 | 1981 | 7 | 6 | 36 | 51 | 90 | 70.5 | 38.5 | 1352 |
| 7/7/1981 | 1981 | 7 | 7 | 37 | 55 | 90 | 72.5 | 40.5 | 1392.5 |
| 7/8/1981 | 1981 | 7 | 8 | 38 | 56 | 85 | 70.5 | 38.5 | 1431 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/9/1981 | 1981 | 7 | 9 | 39 | 55 | 80 | 67.5 | 35.5 | 1466.5 |
| 7/10/1981 | 1981 | 7 | 10 | 40 | 56 | 81 | 68.5 | 36.5 | 1503 |
| 7/11/1981 | 1981 | 7 | 11 | 41 | 55 | 78 | 66.5 | 34.5 | 1537.5 |
| 7/12/1981 | 1981 | 7 | 12 | 42 | 53 | 79 | 66 | 34 | 1571.5 |
| 7/13/1981 | 1981 | 7 | 13 | 43 | 55 | 77 | 66 | 34 | 1605.5 |
| 7/14/1981 | 1981 | 7 | 14 | 44 | 53 | 78 | 65.5 | 33.5 | 1639 |
| 7/15/1981 | 1981 | 7 | 15 | 45 | 53 | 78 | 65.5 | 33.5 | 1672.5 |
| 7/16/1981 | 1981 | 7 | 16 | 46 | 54 | 71 | 62.5 | 30.5 | 1703 |
| 7/17/1981 | 1981 | 7 | 17 | 47 | 54 | 76 | 65 | 33 | 1736 |
| 7/18/1981 | 1981 | 7 | 18 | 48 | 50 | 75 | 62.5 | 30.5 | 1766.5 |
| 7/19/1981 | 1981 | 7 | 19 | 49 | 51 | 76 | 63.5 | 31.5 | 1798 |
| 7/20/1981 | 1981 | 7 | 20 | 50 | 57 | 78 | 67.5 | 35.5 | 1833.5 |
| 7/21/1981 | 1981 | 7 | 21 | 51 | 51 | 81 | 66 | 34 | 1867.5 |
| 7/22/1981 | 1981 | 7 | 22 | 52 | 50 | 80 | 65 | 33 | 1900.5 |
| 7/23/1981 | 1981 | 7 | 23 | 53 | 60 | 90 | 75 | 43 | 1943.5 |
| 7/24/1981 | 1981 | 7 | 24 | 54 | 59 | 89 | 74 | 42 | 1985.5 |
| 7/25/1981 | 1981 | 7 | 25 | 55 | 60 | 87 | 73.5 | 41.5 | 2027 |
| 7/26/1981 | 1981 | 7 | 26 | 56 | 68 | 83 | 75.5 | 43.5 | 2070.5 |
| 7/27/1981 | 1981 | 7 | 27 | 57 | 60 | 77 | 68.5 | 36.5 | 2107 |
| 7/28/1981 | 1981 | 7 | 28 | 58 | 56 | 78 | 67 | 35 | 2142 |
| 7/29/1981 | 1981 | 7 | 29 | 59 | 55 | 84 | 69.5 | 37.5 | 2179.5 |
| 7/30/1981 | 1981 | 7 | 30 | 60 | 56 | 86 | 71 | 39 | 2218.5 |
| 7/31/1981 | 1981 | 7 | 31 | 61 | 55 | 84 | 69.5 | 37.5 | 2256 |
| 8/1/1981 | 1981 | 8 | 1 | 62 | 57 | 83 | 70 | 38 | 2294 |
| 8/2/1981 | 1981 | 8 | 2 | 63 | 56 | 84 | 70 | 38 | 2332 |
| 8/3/1981 | 1981 | 8 | 3 | 64 | 58 | 84 | 71 | 39 | 2371 |
| 8/4/1981 | 1981 | 8 | 4 | 65 | 59 | 89 | 74 | 42 | 2413 |
| 8/5/1981 | 1981 | 8 | 5 | 66 | 57 | 90 | 73.5 | 41.5 | 2454.5 |
| 8/6/1981 | 1981 | 8 | 6 | 67 | 58 | 91 | 74.5 | 42.5 | 2497 |
| 8/7/1981 | 1981 | 8 | 7 | 68 | 59 | 90 | 74.5 | 42.5 | 2539.5 |
| 8/8/1981 | 1981 | 8 | 8 | 69 | 51 | 84 | 67.5 | 35.5 | 2575 |
| 8/9/1981 | 1981 | 8 | 9 | 70 | 53 | 82 | 67.5 | 35.5 | 2610.5 |
| 8/10/1981 | 1981 | 8 | 10 | 71 | 54 | 80 | 67 | 35 | 2645.5 |
| 8/11/1981 | 1981 | 8 | 11 | 72 | 51 | 70 | 60.5 | 28.5 | 2674 |
| 8/12/1981 | 1981 | 8 | 12 | 73 | 49 | 75 | 62 | 30 | 2704 |
| 8/13/1981 | 1981 | 8 | 13 | 74 | 49 | 75 | 62 | 30 | 2734 |
| 8/14/1981 | 1981 | 8 | 14 | 75 | 50 | 78 | 64 | 32 | 2766 |
| 8/15/1981 | 1981 | 8 | 15 | 76 | 57 | 78 | 67.5 | 35.5 | 2801.5 |
| 8/16/1981 | 1981 | 8 | 16 | 77 | 52 | 80 | 66 | 34 | 2835.5 |
| 8/17/1981 | 1981 | 8 | 17 | 78 | 51 | 78 | 64.5 | 32.5 | 2868 |
| 8/18/1981 | 1981 | 8 | 18 | 79 | 50 | 79 | 64.5 | 32.5 | 2900.5 |
| 8/19/1981 | 1981 | 8 | 19 | 80 | 50 | 77 | 63.5 | 31.5 | 2932 |
| 8/20/1981 | 1981 | 8 | 20 | 81 | 54 | 83 | 68.5 | 36.5 | 2968.5 |
| 8/21/1981 | 1981 | 8 | 21 | 82 | 57 | 83 | 70 | 38 | 3006.5 |
| 8/22/1981 | 1981 | 8 | 22 | 83 | 54 | 76 | 65 | 33 | 3039.5 |
| 8/23/1981 | 1981 | 8 | 23 | 84 | 53 | 70 | 61.5 | 29.5 | 3069 |
| 8/24/1981 | 1981 | 8 | 24 | 85 | 52 | 71 | 61.5 | 29.5 | 3098.5 |
| 8/25/1981 | 1981 | 8 | 25 | 86 | 57 | 73 | 65 | 33 | 3131.5 |
| 8/26/1981 | 1981 | 8 | 26 | 87 | 55 | 79 | 67 | 35 | 3166.5 |
| 8/27/1981 | 1981 | 8 | 27 | 88 | 54 | 80 | 67 | 35 | 3201.5 |
| 8/28/1981 | 1981 | 8 | 28 | 89 | 52 | 80 | 66 | 34 | 3235.5 |
| 8/29/1981 | 1981 | 8 | 29 | 90 | 47 | 79 | 63 | 31 | 3266.5 |
| 8/30/1981 | 1981 | 8 | 30 | 91 | 48 | 80 | 64 | 32 | 3298.5 |
| 8/31/1981 | 1981 | 8 | 31 | 92 | 55 | 81 | 68 | 36 | 3334.5 |
| 9/1/1981 | 1981 | 9 | 1 | 93 | 48 | 76 | 62 | 30 | 3364.5 |
| 9/2/1981 | 1981 | 9 | 2 | 94 | 50 | 77 | 63.5 | 31.5 | 3396 |
| 9/3/1981 | 1981 | 9 | 3 | 95 | 52 | 79 | 65.5 | 33.5 | 3429.5 |
| 9/4/1981 | 1981 | 9 | 4 | 96 | 52 | 79 | 65.5 | 33.5 | 3463 |
| 9/5/1981 | 1981 | 9 | 5 | 97 | 51 | 77 | 64 | 32 | 3495 |
| 9/6/1981 | 1981 | 9 | 6 | 98 | 50 | 77 | 63.5 | 31.5 | 3526.5 |
| 9/7/1981 | 1981 | 9 | 7 | 99 | 50 | 76 | 63 | 31 | 3557.5 |
| 9/8/1981 | 1981 | 9 | 8 | 100 | 46 | 75 | 60.5 | 28.5 | 3586 |
| 9/9/1981 | 1981 | 9 | 9 | 101 | 45 | 72 | 58.5 | 26.5 | 3612.5 |
| 9/10/1981 | 1981 | 9 | 10 | 102 | 40 | 71 | 55.5 | 23.5 | 3636 |
| 9/11/1981 | 1981 | 9 | 11 | 103 | 49 | 74 | 61.5 | 29.5 | 3665.5 |
| 9/12/1981 | 1981 | 9 | 12 | 104 | 46 | 75 | 60.5 | 28.5 | 3694 |
| 9/13/1981 | 1981 | 9 | 13 | 105 | 47 | 76 | 61.5 | 29.5 | 3723.5 |
| 9/14/1981 | 1981 | 9 | 14 | 106 | 48 | 77 | 62.5 | 30.5 | 3754 |
| 9/15/1981 | 1981 | 9 | 15 | 107 | 49 | 75 | 62 | 30 | 3784 |
| 9/16/1981 | 1981 | 9 | 16 | 108 | 44 | 69 | 56.5 | 24.5 | 3808.5 |
| 9/17/1981 | 1981 | 9 | 17 | 109 | 44 | 72 | 58 | 26 | 3834.5 |
| 9/18/1981 | 1981 | 9 | 18 | 110 | 43 | 70 | 56.5 | 24.5 | 3859 |
| 9/19/1981 | 1981 | 9 | 19 | 111 | 42 | 70 | 56 | 24 | 3883 |
| 9/20/1981 | 1981 | 9 | 20 | 112 | 43 | 71 | 57 | 25 | 3908 |
| 9/21/1981 | 1981 | 9 | 21 | 113 | 46 | 76 | 61 | 29 | 3937 |
| 9/22/1981 | 1981 | 9 | 22 | 114 | 52 | 75 | 63.5 | 31.5 | 3968.5 |
| 9/23/1981 | 1981 | 9 | 23 | 115 | 51 | 71 | 61 | 29 | 3997.5 |
| 9/24/1981 | 1981 | 9 | 24 | 116 | 48 | 69 | 58.5 | 26.5 | 4024 |
| 9/25/1981 | 1981 | 9 | 25 | 117 | 47 | 68 | 57.5 | 25.5 | 4049.5 |
| 9/26/1981 | 1981 | 9 | 26 | 118 | 44 | 70 | 57 | 25 | 4074.5 |
| 9/27/1981 | 1981 | 9 | 27 | 119 | 47 | 76 | 61.5 | 29.5 | 4104 |
| 9/28/1981 | 1981 | 9 | 28 | 120 | 50 | 77 | 63.5 | 31.5 | 4135.5 |
| 9/29/1981 | 1981 | 9 | 29 | 121 | 56 | 76 | 66 | 34 | 4169.5 |
| 9/30/1981 | 1981 | 9 | 30 | 122 | 52 | 74 | 63 | 31 | 4200.5 |
| 10/1/1981 | 1981 | 10 | 1 | 123 | 49 | 70 | 59.5 | 27.5 | 4228 |
| 10/2/1981 | 1981 | 10 | 2 | 124 | 48 | 69 | 58.5 | 26.5 | 4254.5 |
| 10/3/1981 | 1981 | 10 | 3 | 125 | 40 | 60 | 50 | 18 | 4272.5 |
| 10/4/1981 | 1981 | 10 | 4 | 126 | 40 | 65 | 52.5 | 20.5 | 4293 |
| 10/5/1981 | 1981 | 10 | 5 | 127 | 42 | 64 | 53 | 21 | 4314 |
| 10/6/1981 | 1981 | 10 | 6 | 128 | 43 | 66 | 54.5 | 22.5 | 4336.5 |
| 10/7/1981 | 1981 | 10 | 7 | 129 | 36 | 64 | 50 | 18 | 4354.5 |
| 10/8/1981 | 1981 | 10 | 8 | 130 | 46 | 66 | 56 | 24 | 4378.5 |
| 10/9/1981 | 1981 | 10 | 9 | 131 | 43 | 65 | 54 | 22 | 4400.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/10/1981 | 1981 | 10 | 10 | 132 | 35 | 67 | 51 | 19 | 4419.5 |
| 10/11/1981 | 1981 | 10 | 11 | 133 | 39 | 66 | 52.5 | 20.5 | 4440 |
| 10/12/1981 | 1981 | 10 | 12 | 134 | 44 | 62 | 53 | 21 | 4461 |
| 10/13/1981 | 1981 | 10 | 13 | 135 | 41 | 64 | 52.5 | 20.5 | 4481.5 |
| 10/14/1981 | 1981 | 10 | 14 | 136 | 43 | 62 | 52.5 | 20.5 | 4502 |
| 10/15/1981 | 1981 | 10 | 15 | 137 | 47 | 64 | 55.5 | 23.5 | 4525.5 |
| 10/16/1981 | 1981 | 10 | 16 | 138 | 24 | 62 | 43 | 11 | 4536.5 |
| 10/17/1981 | 1981 | 10 | 17 | 139 | 24 | 62 | 43 | 11 | 4547.5 |
| 10/18/1981 | 1981 | 10 | 18 | 140 | 31 | 58 | 44.5 | 12.5 | 4560 |
| 10/19/1981 | 1981 | 10 | 19 | 141 | 33 | 61 | 47 | 15 | 4575 |
| 10/20/1981 | 1981 | 10 | 20 | 142 | 35 | 63 | 49 | 17 | 4592 |
| 10/21/1981 | 1981 | 10 | 21 | 143 | 38 | 64 | 51 | 19 | 4611 |
| 10/22/1981 | 1981 | 10 | 22 | 144 | 32 | 59 | 45.5 | 13.5 | 4624.5 |
| 10/23/1981 | 1981 | 10 | 23 | 145 | 29 | 57 | 43 | 11 | 4635.5 |
| 10/24/1981 | 1981 | 10 | 24 | 146 | 28 | 50 | 39 | 7 | 4642.5 |
| 10/25/1981 | 1981 | 10 | 25 | 147 | 28 | 50 | 39 | 7 | 4649.5 |
| 10/26/1981 | 1981 | 10 | 26 | 148 | 27 | 61 | 44 | 12 | 4661.5 |
| 10/27/1981 | 1981 | 10 | 27 | 149 | 36 | 60 | 48 | 16 | 4677.5 |
| 10/28/1981 | 1981 | 10 | 28 | 150 | 34 | 61 | 47.5 | 15.5 | 4693 |
| 10/29/1981 | 1981 | 10 | 29 | 151 | 48 | 61 | 54.5 | 22.5 | 4715.5 |
| 10/30/1981 | 1981 | 10 | 30 | 152 | 30 | 55 | 42.5 | 10.5 | 4726 |
| 10/31/1981 | 1981 | 10 | 31 | 153 | 22 | 48 | 35 | 3 | 4729 |
| 11/1/1981 | 1981 | 11 | 1 | 154 | 34 | 53 | 43.5 | 11.5 | 4740.5 |
| 11/2/1981 | 1981 | 11 | 2 | 155 | 28 | 58 | 43 | 11 | 4751.5 |
| 11/3/1981 | 1981 | 11 | 3 | 156 | 31 | 59 | 45 | 13 | 4764.5 |
| 11/4/1981 | 1981 | 11 | 4 | 157 | 32 | 59 | 45.5 | 13.5 | 4778 |
| 11/5/1981 | 1981 | 11 | 5 | 158 | 32 | 63 | 47.5 | 15.5 | 4793.5 |
| 11/6/1981 | 1981 | 11 | 6 | 159 | 30 | 60 | 45 | 13 | 4806.5 |
| 11/7/1981 | 1981 | 11 | 7 | 160 | 30 | 59 | 44.5 | 12.5 | 4819 |
| 11/8/1981 | 1981 | 11 | 8 | 161 | 35 | 58 | 46.5 | 14.5 | 4833.5 |
| 11/9/1981 | 1981 | 11 | 9 | 162 | 29 | 49 | 39 | 7 | 4840.5 |
| 11/10/1981 | 1981 | 11 | 10 | 163 | 28 | 55 | 41.5 | 9.5 | 4850 |
| 11/11/1981 | 1981 | 11 | 11 | 164 | 31 | 51 | 41 | 9 | 4859 |
| 11/12/1981 | 1981 | 11 | 12 | 165 | 30 | 54 | 42 | 10 | 4869 |
| 11/13/1981 | 1981 | 11 | 13 | 166 | 32 | 55 | 43.5 | 11.5 | 4880.5 |
| 11/14/1981 | 1981 | 11 | 14 | 167 | 33 | 60 | 46.5 | 14.5 | 4895 |
| 11/15/1981 | 1981 | 11 | 15 | 168 | 35 | 64 | 49.5 | 17.5 | 4912.5 |
| 11/16/1981 | 1981 | 11 | 16 | 169 | 38 | 65 | 51.5 | 19.5 | 4932 |
| 11/17/1981 | 1981 | 11 | 17 | 170 | 32 | 64 | 48 | 16 | 4948 |
| 11/18/1981 | 1981 | 11 | 18 | 171 | 34 | 62 | 48 | 16 | 4964 |
| 11/19/1981 | 1981 | 11 | 19 | 172 | 19 | 57 | 38 | 6 | 4970 |
| 11/20/1981 | 1981 | 11 | 20 | 173 | 18 | 40 | 29 | -3 | 4967 |
| 11/21/1981 | 1981 | 11 | 21 | 174 | 17 | 39 | 28 | -4 | 4963 |
| 11/22/1981 | 1981 | 11 | 22 | 175 | 18 | 37 | 27.5 | -4.5 | 4958.5 |
| 11/23/1981 | 1981 | 11 | 23 | 176 | 19 | 62 | 40.5 | 8.5 | 4967 |
| 11/24/1981 | 1981 | 11 | 24 | 177 | 34 | 65 | 49.5 | 17.5 | 4984.5 |
| 11/25/1981 | 1981 | 11 | 25 | 178 | 32 | 60 | 46 | 14 | 4998.5 |
| 11/26/1981 | 1981 | 11 | 26 | 179 | 10 | 48 | 29 | -3 | 4995.5 |
| 11/27/1981 | 1981 | 11 | 27 | 180 | 12 | 45 | 28.5 | -3.5 | 4992 |
| 11/28/1981 | 1981 | 11 | 28 | 181 | 19 | 47 | 33 | 1 | 4993 |
| 11/29/1981 | 1981 | 11 | 29 | 182 | 23 | 44 | 33.5 | 1.5 | 4994.5 |
| 11/30/1981 | 1981 | 11 | 30 | 183 | 19 | 40 | 29.5 | -2.5 | 4992 |
| 12/1/1981 | 1981 | 12 | 1 | 184 | 9 | 32 | 20.5 | -11.5 | 4980.5 |
| 12/2/1981 | 1981 | 12 | 2 | 185 | 5 | 30 | 17.5 | -14.5 | 4966 |
| 12/3/1981 | 1981 | 12 | 3 | 186 | 10 | 46 | 28 | -4 | 4962 |
| 12/4/1981 | 1981 | 12 | 4 | 187 | 15 | 54 | 34.5 | 2.5 | 4964.5 |
| 12/5/1981 | 1981 | 12 | 5 | 188 | 19 | 47 | 33 | 1 | 4965.5 |
| 12/6/1981 | 1981 | 12 | 6 | 189 | 20 | 46 | 33 | 1 | 4966.5 |
| 12/7/1981 | 1981 | 12 | 7 | 190 | 21 | 45 | 33 | 1 | 4967.5 |
| 12/8/1981 | 1981 | 12 | 8 | 191 | 24 | 50 | 37 | 5 | 4972.5 |
| 12/9/1981 | 1981 | 12 | 9 | 192 | 19 | 50 | 34.5 | 2.5 | 4975 |
| 12/10/1981 | 1981 | 12 | 10 | 193 | 20 | 51 | 35.5 | 3.5 | 4978.5 |
| 12/11/1981 | 1981 | 12 | 11 | 194 | 27 | 52 | 39.5 | 7.5 | 4986 |
| 12/12/1981 | 1981 | 12 | 12 | 195 | 16 | 57 | 36.5 | 4.5 | 4990.5 |
| 12/13/1981 | 1981 | 12 | 13 | 196 | 19 | 53 | 36 | 4 | 4994.5 |
| 12/14/1981 | 1981 | 12 | 14 | 197 | 18 | 49 | 33.5 | 1.5 | 4996 |
| 12/15/1981 | 1981 | 12 | 15 | 198 | 17 | 48 | 32.5 | 0.5 | 4996.5 |
| 12/16/1981 | 1981 | 12 | 16 | 199 | 20 | 49 | 34.5 | 2.5 | 4999 |
| 12/17/1981 | 1981 | 12 | 17 | 200 | 21 | 50 | 35.5 | 3.5 | 5002.5 |
| 12/18/1981 | 1981 | 12 | 18 | 201 | 20 | 51 | 35.5 | 3.5 | 5006 |
| 12/19/1981 | 1981 | 12 | 19 | 202 | 16 | 49 | 32.5 | 0.5 | 5006.5 |
| 12/20/1981 | 1981 | 12 | 20 | 203 | 17 | 48 | 32.5 | 0.5 | 5007 |
| 12/21/1981 | 1981 | 12 | 21 | 204 | 18 | 50 | 34 | 2 | 5009 |
| 12/22/1981 | 1981 | 12 | 22 | 205 | 17 | 49 | 33 | 1 | 5010 |
| 12/23/1981 | 1981 | 12 | 23 | 206 | 20 | 48 | 34 | 2 | 5012 |
| 12/24/1981 | 1981 | 12 | 24 | 207 | 9 | 50 | 29.5 | -2.5 | 5009.5 |
| 12/25/1981 | 1981 | 12 | 25 | 208 | 10 | 40 | 25 | -7 | 5002.5 |
| 12/26/1981 | 1981 | 12 | 26 | 209 | 5 | 33 | 19 | -13 | 4989.5 |
| 12/27/1981 | 1981 | 12 | 27 | 210 | 4 | 32 | 18 | -14 | 4975.5 |
| 12/28/1981 | 1981 | 12 | 28 | 211 | 5 | 30 | 17.5 | -14.5 | 4961 |
| 12/29/1981 | 1981 | 12 | 29 | 212 | 6 | 31 | 18.5 | -13.5 | 4947.5 |
| 12/30/1981 | 1981 | 12 | 30 | 213 | 11 | 33 | 22 | -10 | 4937.5 |
| 12/31/1981 | 1981 | 12 | 31 | 214 | 15 | 40 | 27.5 | -4.5 | 4933 |
| 1/1/1982 | 1982 | 1 | 1 | 215 | 36 | 40 | 38 | 6 | 4939 |
| 1/2/1982 | 1982 | 1 | 2 | 216 | 26 | 37 | 31.5 | -0.5 | 4938.5 |
| 1/3/1982 | 1982 | 1 | 3 | 217 | 13 | 32 | 22.5 | -9.5 | 4929 |
| 1/4/1982 | 1982 | 1 | 4 | 218 | 3 | 37 | 20 | -12 | 4917 |
| 1/5/1982 | 1982 | 1 | 5 | 219 | 27 | 40 | 33.5 | 1.5 | 4918.5 |
| 1/6/1982 | 1982 | 1 | 6 | 220 | 32 | 40 | 36 | 4 | 4922.5 |
| 1/7/1982 | 1982 | 1 | 7 | 221 | 14 | 30 | 22 | -10 | 4912.5 |
| 1/8/1982 | 1982 | 1 | 8 | 222 | 5 | 32 | 18.5 | -13.5 | 4899 |
| 1/9/1982 | 1982 | 1 | 9 | 223 | 10 | 45 | 27.5 | -4.5 | 4894.5 |
| 1/10/1982 | 1982 | 1 | 10 | 224 | 11 | 52 | 31.5 | -0.5 | 4894 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/11/1982 | 1982 | 1 | 11 | 225 | 16 | 44 | 30 | -2 | 4892 |
| 1/12/1982 | 1982 | 1 | 12 | 226 | 30 | 37 | 33.5 | 1.5 | 4893.5 |
| 1/13/1982 | 1982 | 1 | 13 | 227 | 14 | 32 | 23 | -9 | 4884.5 |
| 1/14/1982 | 1982 | 1 | 14 | 228 | 6 | 45 | 25.5 | -6.5 | 4878 |
| 1/15/1982 | 1982 | 1 | 15 | 229 | 11 | 44 | 27.5 | -4.5 | 4873.5 |
| 1/16/1982 | 1982 | 1 | 16 | 230 | 13 | 47 | 30 | -2 | 4871.5 |
| 1/17/1982 | 1982 | 1 | 17 | 231 | 15 | 56 | 35.5 | 3.5 | 4875 |
| 1/18/1982 | 1982 | 1 | 18 | 232 | 25 | 53 | 39 | 7 | 4882 |
| 1/19/1982 | 1982 | 1 | 19 | 233 | 25 | 47 | 36 | 4 | 4886 |
| 1/20/1982 | 1982 | 1 | 20 | 234 | 23 | 49 | 36 | 4 | 4890 |
| 1/21/1982 | 1982 | 1 | 21 | 235 | 16 | 40 | 28 | -4 | 4886 |
| 1/22/1982 | 1982 | 1 | 22 | 236 | 20 | 31 | 25.5 | -6.5 | 4879.5 |
| 1/23/1982 | 1982 | 1 | 23 | 237 | 7 | 42 | 24.5 | -7.5 | 4872 |
| 1/24/1982 | 1982 | 1 | 24 | 238 | 12 | 62 | 37 | 5 | 4877 |
| 1/25/1982 | 1982 | 1 | 25 | 239 | 18 | 61 | 39.5 | 7.5 | 4884.5 |
| 1/26/1982 | 1982 | 1 | 26 | 240 | 16 | 65 | 40.5 | 8.5 | 4893 |
| 1/27/1982 | 1982 | 1 | 27 | 241 | 32 | 54 | 43 | 11 | 4904 |
| 1/28/1982 | 1982 | 1 | 28 | 242 | 19 | 50 | 34.5 | 2.5 | 4906.5 |
| 1/29/1982 | 1982 | 1 | 29 | 243 | 27 | 40 | 33.5 | 1.5 | 4908 |
| 1/30/1982 | 1982 | 1 | 30 | 244 | 18 | 46 | 32 | 0 | 4908 |
| 1/31/1982 | 1982 | 1 | 31 | 245 | 11 | 42 | 26.5 | -5.5 | 4902.5 |
| 2/1/1982 | 1982 | 2 | 1 | 246 | 15 | 39 | 27 | -5 | 4928 |
| 2/2/1982 | 1982 | 2 | 2 | 247 | 7 | 29 | 18 | -14 | 4914 |
| 2/3/1982 | 1982 | 2 | 3 | 248 | 6 | 28 | 17 | -15 | 4899 |
| 2/4/1982 | 1982 | 2 | 4 | 249 | 5 | 29 | 17 | -15 | 4884 |
| 2/5/1982 | 1982 | 2 | 5 | 250 | 8 | 28 | 18 | -14 | 4870 |
| 2/6/1982 | 1982 | 2 | 6 | 251 | -7 | 30 | 11.5 | -20.5 | 4849.5 |
| 2/7/1982 | 1982 | 2 | 7 | 252 | -8 | 39 | 15.5 | -16.5 | 4833 |
| 2/8/1982 | 1982 | 2 | 8 | 253 | 10 | 38 | 24 | -8 | 4825 |
| 2/9/1982 | 1982 | 2 | 9 | 254 | 10 | 37 | 23.5 | -8.5 | 4816.5 |
| 2/10/1982 | 1982 | 2 | 10 | 255 | 12 | 35 | 23.5 | -8.5 | 4808 |
| 2/11/1982 | 1982 | 2 | 11 | 256 | 11 | 39 | 25 | -7 | 4801 |
| 2/12/1982 | 1982 | 2 | 12 | 257 | 10 | 34 | 22 | -10 | 4791 |
| 2/13/1982 | 1982 | 2 | 13 | 258 | 11 | 33 | 22 | -10 | 4781 |
| 2/14/1982 | 1982 | 2 | 14 | 259 | 10 | 30 | 20 | -12 | 4769 |
| 2/15/1982 | 1982 | 2 | 15 | 260 | 9 | 30 | 19.5 | -12.5 | 4756.5 |
| 2/16/1982 | 1982 | 2 | 16 | 261 | 16 | 39 | 27.5 | -4.5 | 4752 |
| 2/17/1982 | 1982 | 2 | 17 | 262 | 18 | 39 | 28.5 | -3.5 | 4748.5 |
| 2/18/1982 | 1982 | 2 | 18 | 263 | 17 | 37 | 27 | -5 | 4743.5 |
| 2/19/1982 | 1982 | 2 | 19 | 264 | 16 | 35 | 25.5 | -6.5 | 4737 |
| 2/20/1982 | 1982 | 2 | 20 | 265 | 15 | 36 | 25.5 | -6.5 | 4730.5 |
| 2/21/1982 | 1982 | 2 | 21 | 266 | 16 | 37 | 26.5 | -5.5 | 4725 |
| 2/22/1982 | 1982 | 2 | 22 | 267 | 20 | 58 | 39 | 7 | 4732 |
| 2/23/1982 | 1982 | 2 | 23 | 268 | 30 | 50 | 40 | 8 | 4740 |
| 2/25/1982 | 1982 | 2 | 25 | 269 | 24 | 57 | 40.5 | 8.5 | 4748.5 |
| 2/26/1982 | 1982 | 2 | 26 | 270 | 29 | 41 | 35 | 3 | 4751.5 |
| 2/27/1982 | 1982 | 2 | 27 | 271 | 27 | 40 | 33.5 | 1.5 | 4753 |
| 2/28/1982 | 1982 | 2 | 28 | 272 | 20 | 42 | 31 | -1 | 4752 |
| 3/1/1982 | 1982 | 3 | 1 | 273 | 28 | 59 | 43.5 | 11.5 | 4763.5 |
| 3/2/1982 | 1982 | 3 | 2 | 274 | 30 | 55 | 42.5 | 10.5 | 4774 |
| 3/3/1982 | 1982 | 3 | 3 | 275 | 29 | 46 | 37.5 | 5.5 | 4779.5 |
| 3/4/1982 | 1982 | 3 | 4 | 276 | 25 | 45 | 35 | 3 | 4782.5 |
| 3/5/1982 | 1982 | 3 | 5 | 277 | 19 | 40 | 29.5 | -2.5 | 4780 |
| 3/6/1982 | 1982 | 3 | 6 | 278 | 18 | 40 | 29 | -3 | 4777 |
| 3/7/1982 | 1982 | 3 | 7 | 279 | 19 | 49 | 34 | 2 | 4779 |
| 3/8/1982 | 1982 | 3 | 8 | 280 | 19 | 48 | 33.5 | 1.5 | 4780.5 |
| 3/9/1982 | 1982 | 3 | 9 | 281 | 19 | 50 | 34.5 | 2.5 | 4783 |
| 3/10/1982 | 1982 | 3 | 10 | 282 | 20 | 50 | 35 | 3 | 4786 |
| 3/11/1982 | 1982 | 3 | 11 | 283 | 29 | 51 | 40 | 8 | 4794 |
| 3/12/1982 | 1982 | 3 | 12 | 284 | 28 | 56 | 42 | 10 | 4804 |
| 3/13/1982 | 1982 | 3 | 13 | 285 | 29 | 52 | 40.5 | 8.5 | 4812.5 |
| 3/14/1982 | 1982 | 3 | 14 | 286 | 30 | 49 | 39.5 | 7.5 | 4820 |
| 3/15/1982 | 1982 | 3 | 15 | 287 | 32 | 49 | 40.5 | 8.5 | 4828.5 |
| 3/16/1982 | 1982 | 3 | 16 | 288 | 30 | 46 | 38 | 6 | 4834.5 |
| 3/17/1982 | 1982 | 3 | 17 | 289 | 26 | 49 | 37.5 | 5.5 | 4840 |
| 3/18/1982 | 1982 | 3 | 18 | 290 | 28 | 50 | 39 | 7 | 4847 |
| 3/19/1982 | 1982 | 3 | 19 | 291 | 30 | 51 | 40.5 | 8.5 | 4855.5 |
| 3/20/1982 | 1982 | 3 | 20 | 292 | 22 | 50 | 36 | 4 | 4859.5 |
| 3/21/1982 | 1982 | 3 | 21 | 293 | 20 | 40 | 30 | -2 | 4857.5 |
| 3/22/1982 | 1982 | 3 | 22 | 294 | 20 | 49 | 34.5 | 2.5 | 4860 |
| 3/23/1982 | 1982 | 3 | 23 | 295 | 24 | 47 | 35.5 | 3.5 | 4863.5 |
| 3/24/1982 | 1982 | 3 | 24 | 296 | 20 | 48 | 34 | 2 | 4865.5 |
| 3/25/1982 | 1982 | 3 | 25 | 297 | 24 | 51 | 37.5 | 5.5 | 4871 |
| 3/26/1982 | 1982 | 3 | 26 | 298 | 23 | 56 | 39.5 | 7.5 | 4878.5 |
| 3/27/1982 | 1982 | 3 | 27 | 299 | 28 | 58 | 43 | 11 | 4889.5 |
| 3/28/1982 | 1982 | 3 | 28 | 300 | 35 | 57 | 46 | 14 | 4903.5 |
| 3/29/1982 | 1982 | 3 | 29 | 301 | 32 | 50 | 41 | 9 | 4912.5 |
| 3/30/1982 | 1982 | 3 | 30 | 302 | 30 | 59 | 44.5 | 12.5 | 4925 |
| 3/31/1982 | 1982 | 3 | 31 | 303 | 28 | 49 | 38.5 | 6.5 | 4931.5 |
| 4/1/1982 | 1982 | 4 | 1 | 304 | 35 | 63 | 49 | 17 | 4948.5 |
| 4/2/1982 | 1982 | 4 | 2 | 305 | 26 | 64 | 45 | 13 | 4961.5 |
| 4/3/1982 | 1982 | 4 | 3 | 306 | 26 | 64 | 45 | 13 | 4974.5 |
| 4/4/1982 | 1982 | 4 | 4 | 307 | 31 | 59 | 45 | 13 | 4987.5 |
| 4/5/1982 | 1982 | 4 | 5 | 308 | 29 | 60 | 44.5 | 12.5 | 5000 |
| 4/6/1982 | 1982 | 4 | 6 | 309 | 41 | 58 | 49.5 | 17.5 | 5017.5 |
| 4/7/1982 | 1982 | 4 | 7 | 310 | 35 | 54 | 44.5 | 12.5 | 5030 |
| 4/8/1982 | 1982 | 4 | 8 | 311 | 24 | 52 | 38 | 6 | 5036 |
| 4/9/1982 | 1982 | 4 | 9 | 312 | 33 | 51 | 42 | 10 | 5046 |
| 4/10/1982 | 1982 | 4 | 10 | 313 | 25 | 63 | 44 | 12 | 5058 |
| 4/11/1982 | 1982 | 4 | 11 | 314 | 34 | 69 | 51.5 | 19.5 | 5077.5 |
| 4/12/1982 | 1982 | 4 | 12 | 315 | 34 | 68 | 51 | 19 | 5096.5 |
| 4/13/1982 | 1982 | 4 | 13 | 316 | 40 | 67 | 53.5 | 21.5 | 5118 |
| 4/14/1982 | 1982 | 4 | 14 | 317 | 34 | 66 | 50 | 18 | 5136 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/15/1982 | 1982 | 4 | 15 | 318 | 33 | 64 | 48.5 | 16.5 | 5152.5 |
| 4/16/1982 | 1982 | 4 | 16 | 319 | 34 | 62 | 48 | 16 | 5168.5 |
| 4/17/1982 | 1982 | 4 | 17 | 320 | 31 | 62 | 46.5 | 14.5 | 5183 |
| 4/18/1982 | 1982 | 4 | 18 | 321 | 35 | 65 | 50 | 18 | 5201 |
| 4/19/1982 | 1982 | 4 | 19 | 322 | 32 | 65 | 48.5 | 16.5 | 5217.5 |
| 4/20/1982 | 1982 | 4 | 20 | 323 | 24 | 62 | 43 | 11 | 5228.5 |
| 4/21/1982 | 1982 | 4 | 21 | 324 | 29 | 49 | 39 | 7 | 5235.5 |
| 4/22/1982 | 1982 | 4 | 22 | 325 | 30 | 42 | 36 | 4 | 5239.5 |
| 4/23/1982 | 1982 | 4 | 23 | 326 | 30 | 50 | 40 | 8 | 5247.5 |
| 4/24/1982 | 1982 | 4 | 24 | 327 | 29 | 49 | 39 | 7 | 5254.5 |
| 4/25/1982 | 1982 | 4 | 25 | 328 | 29 | 50 | 39.5 | 7.5 | 5262 |
| 4/26/1982 | 1982 | 4 | 26 | 329 | 28 | 54 | 41 | 9 | 5271 |
| 4/27/1982 | 1982 | 4 | 27 | 330 | 29 | 63 | 46 | 14 | 5285 |
| 4/28/1982 | 1982 | 4 | 28 | 331 | 40 | 70 | 55 | 23 | 5308 |
| 4/29/1982 | 1982 | 4 | 29 | 332 | 39 | 73 | 56 | 24 | 5332 |
| 4/30/1982 | 1982 | 4 | 30 | 333 | 44 | 70 | 57 | 25 | 5357 |
| 5/1/1982 | 1982 | 5 | 1 | 334 | 39 | 60 | 49.5 | 17.5 | 5374.5 |
| 5/2/1982 | 1982 | 5 | 2 | 335 | 42 | 61 | 51.5 | 19.5 | 5394 |
| 5/3/1982 | 1982 | 5 | 3 | 336 | 40 | 68 | 54 | 22 | 5416 |
| 5/4/1982 | 1982 | 5 | 4 | 337 | 44 | 67 | 55.5 | 23.5 | 5439.5 |
| 5/5/1982 | 1982 | 5 | 5 | 338 | 35 | 61 | 48 | 16 | 5455.5 |
| 5/6/1982 | 1982 | 5 | 6 | 339 | 30 | 59 | 44.5 | 12.5 | 5468 |
| 5/7/1982 | 1982 | 5 | 7 | 340 | 31 | 69 | 50 | 18 | 5486 |
| 5/8/1982 | 1982 | 5 | 8 | 341 | 39 | 68 | 53.5 | 21.5 | 5507.5 |
| 5/9/1982 | 1982 | 5 | 9 | 342 | 41 | 67 | 54 | 22 | 5529.5 |
| 5/10/1982 | 1982 | 5 | 10 | 343 | 35 | 66 | 50.5 | 18.5 | 5548 |
| 5/11/1982 | 1982 | 5 | 11 | 344 | 34 | 65 | 49.5 | 17.5 | 5565.5 |
| 5/12/1982 | 1982 | 5 | 12 | 345 | 32 | 61 | 46.5 | 14.5 | 5580 |
| 5/13/1982 | 1982 | 5 | 13 | 346 | 33 | 56 | 44.5 | 12.5 | 5592.5 |
| 5/14/1982 | 1982 | 5 | 14 | 347 | 33 | 65 | 49 | 17 | 5609.5 |
| 5/15/1982 | 1982 | 5 | 15 | 348 | 36 | 66 | 51 | 19 | 5628.5 |
| 5/16/1982 | 1982 | 5 | 16 | 349 | 37 | 67 | 52 | 20 | 5648.5 |
| 5/17/1982 | 1982 | 5 | 17 | 350 | 40 | 71 | 55.5 | 23.5 | 5672 |
| 5/18/1982 | 1982 | 5 | 18 | 351 | 43 | 72 | 57.5 | 25.5 | 5697.5 |
| 5/19/1982 | 1982 | 5 | 19 | 352 | 44 | 74 | 59 | 27 | 5724.5 |
| 5/21/1982 | 1982 | 5 | 21 | 353 | 41 | 73 | 57 | 25 | 5749.5 |
| 5/22/1982 | 1982 | 5 | 22 | 354 | 40 | 79 | 59.5 | 27.5 | 5777 |
| 5/23/1982 | 1982 | 5 | 23 | 355 | 44 | 76 | 60 | 28 | 5805 |
| 5/24/1982 | 1982 | 5 | 24 | 356 | 42 | 76 | 59 | 27 | 5832 |
| 5/25/1982 | 1982 | 5 | 25 | 357 | 45 | 75 | 60 | 28 | 5860 |
| 5/26/1982 | 1982 | 5 | 26 | 358 | 47 | 75 | 61 | 29 | 5889 |
| 5/27/1982 | 1982 | 5 | 27 | 359 | 46 | 77 | 61.5 | 29.5 | 5918.5 |
| 5/28/1982 | 1982 | 5 | 28 | 360 | 44 | 78 | 61 | 29 | 5947.5 |
| 5/29/1982 | 1982 | 5 | 29 | 361 | 43 | 76 | 59.5 | 27.5 | 5975 |
| 5/30/1982 | 1982 | 5 | 30 | 362 | 44 | 74 | 59 | 27 | 6002 |
| 5/31/1982 | 1982 | 5 | 31 | 363 | 46 | 75 | 60.5 | 28.5 | 6030.5 |
| 6/1/1982 | 1982 | 6 | 1 | 1 | 49 | 78 | 63.5 | 31.5 | 31.5 |
| 6/2/1982 | 1982 | 6 | 2 | 2 | 46 | 78 | 62 | 30 | 61.5 |
| 6/3/1982 | 1982 | 6 | 3 | 3 | 44 | 76 | 60 | 28 | 89.5 |
| 6/4/1982 | 1982 | 6 | 4 | 4 | 42 | 73 | 57.5 | 25.5 | 115 |
| 6/5/1982 | 1982 | 6 | 5 | 5 | 46 | 75 | 60.5 | 28.5 | 143.5 |
| 6/6/1982 | 1982 | 6 | 6 | 6 | 43 | 76 | 59.5 | 27.5 | 171 |
| 6/7/1982 | 1982 | 6 | 7 | 7 | 48 | 80 | 64 | 32 | 203 |
| 6/8/1982 | 1982 | 6 | 8 | 8 | 50 | 79 | 64.5 | 32.5 | 235.5 |
| 6/9/1982 | 1982 | 6 | 9 | 9 | 46 | 82 | 64 | 32 | 267.5 |
| 6/10/1982 | 1982 | 6 | 10 | 10 | 45 | 81 | 63 | 31 | 298.5 |
| 6/11/1982 | 1982 | 6 | 11 | 11 | 50 | 80 | 65 | 33 | 331.5 |
| 6/12/1982 | 1982 | 6 | 12 | 12 | 51 | 83 | 67 | 35 | 366.5 |
| 6/13/1982 | 1982 | 6 | 13 | 13 | 52 | 82 | 67 | 35 | 401.5 |
| 6/14/1982 | 1982 | 6 | 14 | 14 | 48 | 83 | 65.5 | 33.5 | 435 |
| 6/15/1982 | 1982 | 6 | 15 | 15 | 47 | 79 | 63 | 31 | 466 |
| 6/16/1982 | 1982 | 6 | 16 | 16 | 48 | 80 | 64 | 32 | 498 |
| 6/17/1982 | 1982 | 6 | 17 | 17 | 52 | 83 | 67.5 | 35.5 | 533.5 |
| 6/18/1982 | 1982 | 6 | 18 | 18 | 55 | 84 | 69.5 | 37.5 | 571 |
| 6/19/1982 | 1982 | 6 | 19 | 19 | 42 | 78 | 60 | 28 | 599 |
| 6/20/1982 | 1982 | 6 | 20 | 20 | 45 | 74 | 59.5 | 27.5 | 626.5 |
| 6/21/1982 | 1982 | 6 | 21 | 21 | 46 | 82 | 64 | 32 | 658.5 |
| 6/22/1982 | 1982 | 6 | 22 | 22 | 50 | 83 | 66.5 | 34.5 | 693 |
| 6/23/1982 | 1982 | 6 | 23 | 23 | 47 | 80 | 63.5 | 31.5 | 724.5 |
| 6/24/1982 | 1982 | 6 | 24 | 24 | 50 | 86 | 68 | 36 | 760.5 |
| 6/25/1982 | 1982 | 6 | 25 | 25 | 53 | 85 | 69 | 37 | 797.5 |
| 6/26/1982 | 1982 | 6 | 26 | 26 | 54 | 87 | 70.5 | 38.5 | 836 |
| 6/27/1982 | 1982 | 6 | 27 | 27 | 53 | 90 | 71.5 | 39.5 | 875.5 |
| 6/28/1982 | 1982 | 6 | 28 | 28 | 58 | 90 | 74 | 42 | 917.5 |
| 6/29/1982 | 1982 | 6 | 29 | 29 | 59 | 89 | 74 | 42 | 959.5 |
| 6/30/1982 | 1982 | 6 | 30 | 30 | 55 | 83 | 69 | 37 | 996.5 |
| 7/1/1982 | 1982 | 7 | 1 | 31 | 49 | 80 | 64.5 | 32.5 | 1029 |
| 7/2/1982 | 1982 | 7 | 2 | 32 | 48 | 81 | 64.5 | 32.5 | 1061.5 |
| 7/3/1982 | 1982 | 7 | 3 | 33 | 52 | 80 | 66 | 34 | 1095.5 |
| 7/4/1982 | 1982 | 7 | 4 | 34 | 55 | 76 | 65.5 | 33.5 | 1129 |
| 7/5/1982 | 1982 | 7 | 5 | 35 | 56 | 78 | 67 | 35 | 1164 |
| 7/6/1982 | 1982 | 7 | 6 | 36 | 49 | 79 | 64 | 32 | 1196 |
| 7/7/1982 | 1982 | 7 | 7 | 37 | 58 | 79 | 68.5 | 36.5 | 1232.5 |
| 7/8/1982 | 1982 | 7 | 8 | 38 | 55 | 83 | 69 | 37 | 1269.5 |
| 7/9/1982 | 1982 | 7 | 9 | 39 | 54 | 85 | 69.5 | 37.5 | 1307 |
| 7/10/1982 | 1982 | 7 | 10 | 40 | 53 | 88 | 70.5 | 38.5 | 1345.5 |
| 7/11/1982 | 1982 | 7 | 11 | 41 | 57 | 86 | 71.5 | 39.5 | 1385 |
| 7/12/1982 | 1982 | 7 | 12 | 42 | 52 | 88 | 70 | 38 | 1423 |
| 7/13/1982 | 1982 | 7 | 13 | 43 | 60 | 90 | 75 | 43 | 1466 |
| 7/14/1982 | 1982 | 7 | 14 | 44 | 58 | 90 | 74 | 42 | 1508 |
| 7/15/1982 | 1982 | 7 | 15 | 45 | 65 | 90 | 77.5 | 45.5 | 1553.5 |
| 7/16/1982 | 1982 | 7 | 16 | 46 | 59 | 85 | 72 | 40 | 1593.5 |
| 7/17/1982 | 1982 | 7 | 17 | 47 | 53 | 82 | 67.5 | 35.5 | 1629 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/18/1982 | 1982 | 7 | 18 | 48 | 52 | 84 | 68 | 36 | 1665 |
| 7/19/1982 | 1982 | 7 | 19 | 49 | 57 | 83 | 70 | 38 | 1703 |
| 7/20/1982 | 1982 | 7 | 20 | 50 | 58 | 80 | 69 | 37 | 1740 |
| 7/21/1982 | 1982 | 7 | 21 | 51 | 52 | 87 | 69.5 | 37.5 | 1777.5 |
| 7/22/1982 | 1982 | 7 | 22 | 52 | 62 | 86 | 74 | 42 | 1819.5 |
| 7/23/1982 | 1982 | 7 | 23 | 53 | 63 | 83 | 73 | 41 | 1860.5 |
| 7/24/1982 | 1982 | 7 | 24 | 54 | 68 | 79 | 73.5 | 41.5 | 1902 |
| 7/25/1982 | 1982 | 7 | 25 | 55 | 69 | 79 | 74 | 42 | 1944 |
| 7/26/1982 | 1982 | 7 | 26 | 56 | 58 | 79 | 68.5 | 36.5 | 1980.5 |
| 7/27/1982 | 1982 | 7 | 27 | 57 | 56 | 81 | 68.5 | 36.5 | 2017 |
| 7/28/1982 | 1982 | 7 | 28 | 58 | 57 | 80 | 68.5 | 36.5 | 2053.5 |
| 7/29/1982 | 1982 | 7 | 29 | 59 | 56 | 74 | 65 | 33 | 2086.5 |
| 7/30/1982 | 1982 | 7 | 30 | 60 | 55 | 74 | 64.5 | 32.5 | 2119 |
| 7/31/1982 | 1982 | 7 | 31 | 61 | 53 | 77 | 65 | 33 | 2152 |
| 8/1/1982 | 1982 | 8 | 1 | 62 | 53 | 79 | 66 | 34 | 2186 |
| 8/2/1982 | 1982 | 8 | 2 | 63 | 56 | 76 | 66 | 34 | 2220 |
| 8/3/1982 | 1982 | 8 | 3 | 64 | 54 | 75 | 64.5 | 32.5 | 2252.5 |
| 8/4/1982 | 1982 | 8 | 4 | 65 | 50 | 77 | 63.5 | 31.5 | 2284 |
| 8/5/1982 | 1982 | 8 | 5 | 66 | 59 | 78 | 68.5 | 36.5 | 2320.5 |
| 8/6/1982 | 1982 | 8 | 6 | 67 | 54 | 79 | 66.5 | 34.5 | 2355 |
| 8/7/1982 | 1982 | 8 | 7 | 68 | 56 | 79 | 67.5 | 35.5 | 2390.5 |
| 8/8/1982 | 1982 | 8 | 8 | 69 | 54 | 77 | 65.5 | 33.5 | 2424 |
| 8/9/1982 | 1982 | 8 | 9 | 70 | 54 | 83 | 68.5 | 36.5 | 2460.5 |
| 8/10/1982 | 1982 | 8 | 10 | 71 | 56 | 82 | 69 | 37 | 2497.5 |
| 8/11/1982 | 1982 | 8 | 11 | 72 | 55 | 81 | 68 | 36 | 2533.5 |
| 8/12/1982 | 1982 | 8 | 12 | 73 | 56 | 83 | 69.5 | 37.5 | 2571 |
| 8/13/1982 | 1982 | 8 | 13 | 74 | 52 | 75 | 63.5 | 31.5 | 2602.5 |
| 8/14/1982 | 1982 | 8 | 14 | 75 | 53 | 79 | 66 | 34 | 2636.5 |
| 8/15/1982 | 1982 | 8 | 15 | 76 | 55 | 74 | 64.5 | 32.5 | 2669 |
| 8/16/1982 | 1982 | 8 | 16 | 77 | 54 | 81 | 67.5 | 35.5 | 2704.5 |
| 8/17/1982 | 1982 | 8 | 17 | 78 | 55 | 78 | 66.5 | 34.5 | 2739 |
| 8/18/1982 | 1982 | 8 | 18 | 79 | 54 | 83 | 68.5 | 36.5 | 2775.5 |
| 8/19/1982 | 1982 | 8 | 19 | 80 | 59 | 81 | 70 | 38 | 2813.5 |
| 8/20/1982 | 1982 | 8 | 20 | 81 | 62 | 82 | 72 | 40 | 2853.5 |
| 8/21/1982 | 1982 | 8 | 21 | 82 | 57 | 73 | 65 | 33 | 2886.5 |
| 8/22/1982 | 1982 | 8 | 22 | 83 | 57 | 75 | 66 | 34 | 2920.5 |
| 8/23/1982 | 1982 | 8 | 23 | 84 | 59 | 73 | 66 | 34 | 2954.5 |
| 8/24/1982 | 1982 | 8 | 24 | 85 | 54 | 75 | 64.5 | 32.5 | 2987 |
| 8/25/1982 | 1982 | 8 | 25 | 86 | 53 | 74 | 63.5 | 31.5 | 3018.5 |
| 8/26/1982 | 1982 | 8 | 26 | 87 | 54 | 73 | 63.5 | 31.5 | 3050 |
| 8/27/1982 | 1982 | 8 | 27 | 88 | 52 | 75 | 63.5 | 31.5 | 3081.5 |
| 8/28/1982 | 1982 | 8 | 28 | 89 | 53 | 74 | 63.5 | 31.5 | 3113 |
| 8/29/1982 | 1982 | 8 | 29 | 90 | 52 | 72 | 62 | 30 | 3143 |
| 8/30/1982 | 1982 | 8 | 30 | 91 | 54 | 68 | 61 | 29 | 3172 |
| 8/31/1982 | 1982 | 8 | 31 | 92 | 52 | 74 | 63 | 31 | 3203 |
| 9/1/1982 | 1982 | 9 | 1 | 93 | 56 | 79 | 67.5 | 35.5 | 3238.5 |
| 9/2/1982 | 1982 | 9 | 2 | 94 | 57 | 80 | 68.5 | 36.5 | 3275 |
| 9/3/1982 | 1982 | 9 | 3 | 95 | 54 | 81 | 67.5 | 35.5 | 3310.5 |
| 9/4/1982 | 1982 | 9 | 4 | 96 | 55 | 76 | 65.5 | 33.5 | 3344 |
| 9/5/1982 | 1982 | 9 | 5 | 97 | 50 | 66 | 58 | 26 | 3370 |
| 9/6/1982 | 1982 | 9 | 6 | 98 | 51 | 69 | 60 | 28 | 3398 |
| 9/7/1982 | 1982 | 9 | 7 | 99 | 53 | 69 | 61 | 29 | 3427 |
| 9/8/1982 | 1982 | 9 | 8 | 100 | 50 | 73 | 61.5 | 29.5 | 3456.5 |
| 9/9/1982 | 1982 | 9 | 9 | 101 | 55 | 70 | 62.5 | 30.5 | 3487 |
| 9/10/1982 | 1982 | 9 | 10 | 102 | 52 | 71 | 61.5 | 29.5 | 3516.5 |
| 9/11/1982 | 1982 | 9 | 11 | 103 | 50 | 69 | 59.5 | 27.5 | 3544 |
| 9/12/1982 | 1982 | 9 | 12 | 104 | 45 | 58 | 51.5 | 19.5 | 3563.5 |
| 9/13/1982 | 1982 | 9 | 13 | 105 | 46 | 63 | 54.5 | 22.5 | 3586 |
| 9/14/1982 | 1982 | 9 | 14 | 106 | 57 | 68 | 62.5 | 30.5 | 3616.5 |
| 9/15/1982 | 1982 | 9 | 15 | 107 | 48 | 71 | 59.5 | 27.5 | 3644 |
| 9/16/1982 | 1982 | 9 | 16 | 108 | 49 | 69 | 59 | 27 | 3671 |
| 9/17/1982 | 1982 | 9 | 17 | 109 | 49 | 72 | 60.5 | 28.5 | 3699.5 |
| 9/18/1982 | 1982 | 9 | 18 | 110 | 44 | 69 | 56.5 | 24.5 | 3724 |
| 9/19/1982 | 1982 | 9 | 19 | 111 | 45 | 69 | 57 | 25 | 3749 |
| 9/20/1982 | 1982 | 9 | 20 | 112 | 44 | 69 | 56.5 | 24.5 | 3773.5 |
| 9/21/1982 | 1982 | 9 | 21 | 113 | 46 | 68 | 57 | 25 | 3798.5 |
| 9/22/1982 | 1982 | 9 | 22 | 114 | 47 | 74 | 60.5 | 28.5 | 3827 |
| 9/23/1982 | 1982 | 9 | 23 | 115 | 51 | 77 | 64 | 32 | 3859 |
| 9/24/1982 | 1982 | 9 | 24 | 116 | 52 | 76 | 64 | 32 | 3891 |
| 9/25/1982 | 1982 | 9 | 25 | 117 | 53 | 69 | 61 | 29 | 3920 |
| 9/26/1982 | 1982 | 9 | 26 | 118 | 52 | 76 | 64 | 32 | 3952 |
| 9/27/1982 | 1982 | 9 | 27 | 119 | 54 | 73 | 63.5 | 31.5 | 3983.5 |
| 9/28/1982 | 1982 | 9 | 28 | 120 | 41 | 67 | 54 | 22 | 4005.5 |
| 9/29/1982 | 1982 | 9 | 29 | 121 | 36 | 69 | 52.5 | 20.5 | 4026 |
| 9/30/1982 | 1982 | 9 | 30 | 122 | 40 | 69 | 54.5 | 22.5 | 4048.5 |
| 10/1/1982 | 1982 | 10 | 1 | 123 | 41 | 68 | 54.5 | 22.5 | 4071 |
| 10/2/1982 | 1982 | 10 | 2 | 124 | 40 | 59 | 49.5 | 17.5 | 4088.5 |
| 10/3/1982 | 1982 | 10 | 3 | 125 | 34 | 60 | 47 | 15 | 4103.5 |
| 10/4/1982 | 1982 | 10 | 4 | 126 | 35 | 64 | 49.5 | 17.5 | 4121 |
| 10/5/1982 | 1982 | 10 | 5 | 127 | 34 | 64 | 49 | 17 | 4138 |
| 10/6/1982 | 1982 | 10 | 6 | 128 | 36 | 72 | 54 | 22 | 4160 |
| 10/7/1982 | 1982 | 10 | 7 | 129 | 34 | 65 | 49.5 | 17.5 | 4177.5 |
| 10/8/1982 | 1982 | 10 | 8 | 130 | 35 | 69 | 52 | 20 | 4197.5 |
| 10/9/1982 | 1982 | 10 | 9 | 131 | 29 | 59 | 44 | 12 | 4209.5 |
| 10/10/1982 | 1982 | 10 | 10 | 132 | 22 | 55 | 38.5 | 6.5 | 4216 |
| 10/11/1982 | 1982 | 10 | 11 | 133 | 26 | 50 | 38 | 6 | 4222 |
| 10/12/1982 | 1982 | 10 | 12 | 134 | 9 | 40 | 24.5 | -7.5 | 4214.5 |
| 10/13/1982 | 1982 | 10 | 13 | 135 | 10 | 35 | 22.5 | -9.5 | 4205 |
| 10/14/1982 | 1982 | 10 | 14 | 136 | 13 | 40 | 26.5 | -5.5 | 4199.5 |
| 10/15/1982 | 1982 | 10 | 15 | 137 | 14 | 49 | 31.5 | -0.5 | 4199 |
| 10/16/1982 | 1982 | 10 | 16 | 138 | 15 | 50 | 32.5 | 0.5 | 4199.5 |
| 10/17/1982 | 1982 | 10 | 17 | 139 | 20 | 64 | 42 | 10 | 4209.5 |
| 10/18/1982 | 1982 | 10 | 18 | 140 | 32 | 62 | 47 | 15 | 4224.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/19/1982 | 1982 | 10 | 19 | 141 | 36 | 65 | 50.5 | 18.5 | 4243 |
| 10/20/1982 | 1982 | 10 | 20 | 142 | 28 | 66 | 47 | 15 | 4258 |
| 10/21/1982 | 1982 | 10 | 21 | 143 | 35 | 65 | 50 | 18 | 4276 |
| 10/22/1982 | 1982 | 10 | 22 | 144 | 32 | 77 | 54.5 | 22.5 | 4298.5 |
| 10/23/1982 | 1982 | 10 | 23 | 145 | 34 | 62 | 48 | 16 | 4314.5 |
| 10/24/1982 | 1982 | 10 | 24 | 146 | 36 | 64 | 50 | 18 | 4332.5 |
| 10/25/1982 | 1982 | 10 | 25 | 147 | 34 | 68 | 51 | 19 | 4351.5 |
| 10/26/1982 | 1982 | 10 | 26 | 148 | 30 | 67 | 48.5 | 16.5 | 4368 |
| 10/27/1982 | 1982 | 10 | 27 | 149 | 32 | 65 | 48.5 | 16.5 | 4384.5 |
| 10/28/1982 | 1982 | 10 | 28 | 150 | 35 | 63 | 49 | 17 | 4401.5 |
| 10/29/1982 | 1982 | 10 | 29 | 151 | 37 | 58 | 47.5 | 15.5 | 4417 |
| 10/30/1982 | 1982 | 10 | 30 | 152 | 20 | 46 | 33 | 1 | 4418 |
| 10/31/1982 | 1982 | 10 | 31 | 153 | 22 | 50 | 36 | 4 | 4422 |
| 11/1/1982 | 1982 | 11 | 1 | 154 | 31 | 54 | 42.5 | 10.5 | 4432.5 |
| 11/2/1982 | 1982 | 11 | 2 | 155 | 25 | 48 | 36.5 | 4.5 | 4437 |
| 11/3/1982 | 1982 | 11 | 3 | 156 | 18 | 42 | 30 | -2 | 4435 |
| 11/4/1982 | 1982 | 11 | 4 | 157 | 24 | 50 | 37 | 5 | 4440 |
| 11/5/1982 | 1982 | 11 | 5 | 158 | 29 | 56 | 42.5 | 10.5 | 4450.5 |
| 11/6/1982 | 1982 | 11 | 6 | 159 | 30 | 60 | 45 | 13 | 4463.5 |
| 11/7/1982 | 1982 | 11 | 7 | 160 | 30 | 61 | 45.5 | 13.5 | 4477 |
| 11/8/1982 | 1982 | 11 | 8 | 161 | 34 | 56 | 45 | 13 | 4490 |
| 11/9/1982 | 1982 | 11 | 9 | 162 | 20 | 52 | 36 | 4 | 4494 |
| 11/10/1982 | 1982 | 11 | 10 | 163 | 30 | 55 | 42.5 | 10.5 | 4504.5 |
| 11/11/1982 | 1982 | 11 | 11 | 164 | 27 | 49 | 38 | 6 | 4510.5 |
| 11/12/1982 | 1982 | 11 | 12 | 165 | 19 | 49 | 34 | 2 | 4512.5 |
| 11/13/1982 | 1982 | 11 | 13 | 166 | 20 | 50 | 35 | 3 | 4515.5 |
| 11/14/1982 | 1982 | 11 | 14 | 167 | 19 | 45 | 32 | 0 | 4515.5 |
| 11/15/1982 | 1982 | 11 | 15 | 168 | 21 | 49 | 35 | 3 | 4518.5 |
| 11/16/1982 | 1982 | 11 | 16 | 169 | 28 | 47 | 37.5 | 5.5 | 4524 |
| 11/17/1982 | 1982 | 11 | 17 | 170 | 29 | 48 | 38.5 | 6.5 | 4530.5 |
| 11/18/1982 | 1982 | 11 | 18 | 171 | 28 | 46 | 37 | 5 | 4535.5 |
| 11/19/1982 | 1982 | 11 | 19 | 172 | 20 | 45 | 32.5 | 0.5 | 4536 |
| 11/20/1982 | 1982 | 11 | 20 | 173 | 26 | 49 | 37.5 | 5.5 | 4541.5 |
| 11/21/1982 | 1982 | 11 | 21 | 174 | 25 | 48 | 36.5 | 4.5 | 4546 |
| 11/22/1982 | 1982 | 11 | 22 | 175 | 28 | 50 | 39 | 7 | 4553 |
| 11/23/1982 | 1982 | 11 | 23 | 176 | 30 | 49 | 39.5 | 7.5 | 4560.5 |
| 11/24/1982 | 1982 | 11 | 24 | 177 | 23 | 42 | 32.5 | 0.5 | 4561 |
| 11/25/1982 | 1982 | 11 | 25 | 178 | 20 | 39 | 29.5 | -2.5 | 4558.5 |
| 11/26/1982 | 1982 | 11 | 26 | 179 | 29 | 37 | 33 | 1 | 4559.5 |
| 11/27/1982 | 1982 | 11 | 27 | 180 | 26 | 38 | 32 | 0 | 4559.5 |
| 11/28/1982 | 1982 | 11 | 28 | 181 | 27 | 39 | 33 | 1 | 4560.5 |
| 11/29/1982 | 1982 | 11 | 29 | 182 | 30 | 40 | 35 | 3 | 4563.5 |
| 11/30/1982 | 1982 | 11 | 30 | 183 | 23 | 42 | 32.5 | 0.5 | 4564 |
| 12/1/1982 | 1982 | 12 | 1 | 184 | 23 | 40 | 31.5 | -0.5 | 4563.5 |
| 12/2/1982 | 1982 | 12 | 2 | 185 | 20 | 36 | 28 | -4 | 4559.5 |
| 12/3/1982 | 1982 | 12 | 3 | 186 | 17 | 30 | 23.5 | -8.5 | 4551 |
| 12/4/1982 | 1982 | 12 | 4 | 187 | 18 | 44 | 31 | -1 | 4550 |
| 12/5/1982 | 1982 | 12 | 5 | 188 | 21 | 43 | 32 | 0 | 4550 |
| 12/6/1982 | 1982 | 12 | 6 | 189 | 19 | 40 | 29.5 | -2.5 | 4547.5 |
| 12/7/1982 | 1982 | 12 | 7 | 190 | 20 | 48 | 34 | 2 | 4549.5 |
| 12/8/1982 | 1982 | 12 | 8 | 191 | 23 | 45 | 34 | 2 | 4551.5 |
| 12/9/1982 | 1982 | 12 | 9 | 192 | 27 | 42 | 34.5 | 2.5 | 4554 |
| 12/10/1982 | 1982 | 12 | 10 | 193 | 28 | 43 | 35.5 | 3.5 | 4557.5 |
| 12/11/1982 | 1982 | 12 | 11 | 194 | 29 | 37 | 33 | 1 | 4558.5 |
| 12/12/1982 | 1982 | 12 | 12 | 195 | 10 | 40 | 25 | -7 | 4551.5 |
| 12/13/1982 | 1982 | 12 | 13 | 196 | 11 | 44 | 27.5 | -4.5 | 4547 |
| 12/14/1982 | 1982 | 12 | 14 | 197 | 19 | 40 | 29.5 | -2.5 | 4544.5 |
| 12/15/1982 | 1982 | 12 | 15 | 198 | 16 | 42 | 29 | -3 | 4541.5 |
| 12/16/1982 | 1982 | 12 | 16 | 199 | 19 | 39 | 29 | -3 | 4538.5 |
| 12/17/1982 | 1982 | 12 | 17 | 200 | 18 | 40 | 29 | -3 | 4535.5 |
| 12/18/1982 | 1982 | 12 | 18 | 201 | 20 | 45 | 32.5 | 0.5 | 4536 |
| 12/19/1982 | 1982 | 12 | 19 | 202 | 20 | 45 | 32.5 | 0.5 | 4536.5 |
| 12/20/1982 | 1982 | 12 | 20 | 203 | 21 | 50 | 35.5 | 3.5 | 4540 |
| 12/21/1982 | 1982 | 12 | 21 | 204 | 21 | 46 | 33.5 | 1.5 | 4541.5 |
| 12/22/1982 | 1982 | 12 | 22 | 205 | 20 | 49 | 34.5 | 2.5 | 4544 |
| 12/23/1982 | 1982 | 12 | 23 | 206 | 19 | 45 | 32 | 0 | 4544 |
| 12/24/1982 | 1982 | 12 | 24 | 207 | 18 | 39 | 28.5 | -3.5 | 4540.5 |
| 12/25/1982 | 1982 | 12 | 25 | 208 | 6 | 30 | 18 | -14 | 4526.5 |
| 12/26/1982 | 1982 | 12 | 26 | 209 | 7 | 30 | 18.5 | -13.5 | 4513 |
| 12/27/1982 | 1982 | 12 | 27 | 210 | 12 | 34 | 23 | -9 | 4504 |
| 12/28/1982 | 1982 | 12 | 28 | 211 | 14 | 30 | 22 | -10 | 4494 |
| 12/29/1982 | 1982 | 12 | 29 | 212 | 0 | 25 | 12.5 | -19.5 | 4474.5 |
| 12/30/1982 | 1982 | 12 | 30 | 213 | 0 | 27 | 13.5 | -18.5 | 4456 |
| 12/31/1982 | 1982 | 12 | 31 | 214 | 0 | 24 | 12 | -20 | 4436 |
| 1/1/1983 | 1983 | 1 | 1 | 215 | 5 | 38 | 21.5 | -10.5 | 4425.5 |
| 1/2/1983 | 1983 | 1 | 2 | 216 | 4 | 32 | 18 | -14 | 4411.5 |
| 1/3/1983 | 1983 | 1 | 3 | 217 | 0 | 31 | 15.5 | -16.5 | 4395 |
| 1/4/1983 | 1983 | 1 | 4 | 218 | 6 | 34 | 20 | -12 | 4383 |
| 1/5/1983 | 1983 | 1 | 5 | 219 | 10 | 40 | 25 | -7 | 4376 |
| 1/6/1983 | 1983 | 1 | 6 | 220 | | 39 | 39 | 7 | 4383 |
| 1/7/1983 | 1983 | 1 | 7 | 221 | 12 | 40 | 26 | -6 | 4377 |
| 1/8/1983 | 1983 | 1 | 8 | 222 | 19 | 40 | 29.5 | -2.5 | 4374.5 |
| 1/9/1983 | 1983 | 1 | 9 | 223 | 20 | 44 | 32 | 0 | 4374.5 |
| 1/10/1983 | 1983 | 1 | 10 | 224 | 15 | 42 | 28.5 | -3.5 | 4371 |
| 1/11/1983 | 1983 | 1 | 11 | 225 | 15 | 42 | 28.5 | -3.5 | 4367.5 |
| 1/12/1983 | 1983 | 1 | 12 | 226 | 19 | 42 | 30.5 | -1.5 | 4366 |
| 1/13/1983 | 1983 | 1 | 13 | 227 | 18 | 41 | 29.5 | -2.5 | 4363.5 |
| 1/14/1983 | 1983 | 1 | 14 | 228 | 19 | 44 | 31.5 | -0.5 | 4363 |
| 1/15/1983 | 1983 | 1 | 15 | 229 | 16 | 40 | 28 | -4 | 4359 |
| 1/16/1983 | 1983 | 1 | 16 | 230 | 15 | 39 | 27 | -5 | 4354 |
| 1/17/1983 | 1983 | 1 | 17 | 231 | 16 | 38 | 27 | -5 | 4349 |
| 1/18/1983 | 1983 | 1 | 18 | 232 | 16 | 40 | 28 | -4 | 4345 |
| 1/19/1983 | 1983 | 1 | 19 | 233 | 10 | 39 | 24.5 | -7.5 | 4337.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/20/1983 | 1983 | 1 | 20 | 234 | 19 | 40 | 29.5 | -2.5 | 4335 |
| 1/21/1983 | 1983 | 1 | 21 | 235 | 20 | 40 | 30 | -2 | 4333 |
| 1/22/1983 | 1983 | 1 | 22 | 236 | 21 | 38 | 29.5 | -2.5 | 4330.5 |
| 1/23/1983 | 1983 | 1 | 23 | 237 | 10 | 32 | 21 | -11 | 4319.5 |
| 1/24/1983 | 1983 | 1 | 24 | 238 | 15 | 39 | 27 | -5 | 4314.5 |
| 1/25/1983 | 1983 | 1 | 25 | 239 | 16 | 38 | 27 | -5 | 4309.5 |
| 1/26/1983 | 1983 | 1 | 26 | 240 | 19 | 37 | 28 | -4 | 4305.5 |
| 1/27/1983 | 1983 | 1 | 27 | 241 | 16 | 39 | 27.5 | -4.5 | 4301 |
| 1/28/1983 | 1983 | 1 | 28 | 242 | 19 | 40 | 29.5 | -2.5 | 4298.5 |
| 1/29/1983 | 1983 | 1 | 29 | 243 | 19 | 42 | 30.5 | -1.5 | 4297 |
| 1/30/1983 | 1983 | 1 | 30 | 244 | 19 | 40 | 29.5 | -2.5 | 4294.5 |
| 1/31/1983 | 1983 | 1 | 31 | 245 | 11 | 30 | 20.5 | -11.5 | 4283 |
| 2/1/1983 | 1983 | 2 | 1 | 246 | 5 | 28 | 16.5 | -15.5 | 4267.5 |
| 2/2/1983 | 1983 | 2 | 2 | 247 | 9 | 30 | 19.5 | -12.5 | 4255 |
| 2/3/1983 | 1983 | 2 | 3 | 248 | 8 | 38 | 23 | -9 | 4246 |
| 2/4/1983 | 1983 | 2 | 4 | 249 | 7 | 39 | 23 | -9 | 4237 |
| 2/5/1983 | 1983 | 2 | 5 | 250 | 5 | 30 | 17.5 | -14.5 | 4222.5 |
| 2/6/1983 | 1983 | 2 | 6 | 251 | 4 | 34 | 19 | -13 | 4209.5 |
| 2/7/1983 | 1983 | 2 | 7 | 252 | 5 | 36 | 20.5 | -11.5 | 4198 |
| 2/8/1983 | 1983 | 2 | 8 | 253 | 5 | 38 | 21.5 | -10.5 | 4187.5 |
| 2/9/1983 | 1983 | 2 | 9 | 254 | 9 | 46 | 27.5 | -4.5 | 4183 |
| 2/10/1983 | 1983 | 2 | 10 | 255 | 10 | 40 | 25 | -7 | 4176 |
| 2/11/1983 | 1983 | 2 | 11 | 256 | 10 | 40 | 25 | -7 | 4169 |
| 2/12/1983 | 1983 | 2 | 12 | 257 | 15 | 48 | 31.5 | -0.5 | 4168.5 |
| 2/13/1983 | 1983 | 2 | 13 | 258 | 17 | 48 | 32.5 | 0.5 | 4169 |
| 2/14/1983 | 1983 | 2 | 14 | 259 | 16 | 46 | 31 | -1 | 4168 |
| 2/15/1983 | 1983 | 2 | 15 | 260 | 15 | 47 | 31 | -1 | 4167 |
| 2/16/1983 | 1983 | 2 | 16 | 261 | 17 | 44 | 30.5 | -1.5 | 4165.5 |
| 2/17/1983 | 1983 | 2 | 17 | 262 | 14 | 45 | 29.5 | -2.5 | 4163 |
| 2/18/1983 | 1983 | 2 | 18 | 263 | 15 | 48 | 31.5 | -0.5 | 4162.5 |
| 2/19/1983 | 1983 | 2 | 19 | 264 | 19 | 49 | 34 | 2 | 4164.5 |
| 2/20/1983 | 1983 | 2 | 20 | 265 | 20 | 45 | 32.5 | 0.5 | 4165 |
| 2/21/1983 | 1983 | 2 | 21 | 266 | 19 | 48 | 33.5 | 1.5 | 4166.5 |
| 2/22/1983 | 1983 | 2 | 22 | 267 | 19 | 46 | 32.5 | 0.5 | 4167 |
| 2/23/1983 | 1983 | 2 | 23 | 268 | 20 | 48 | 34 | 2 | 4169 |
| 2/24/1983 | 1983 | 2 | 24 | 269 | 20 | 51 | 35.5 | 3.5 | 4172.5 |
| 2/25/1983 | 1983 | 2 | 25 | 270 | 20 | 50 | 35 | 3 | 4175.5 |
| 2/26/1983 | 1983 | 2 | 26 | 271 | 18 | 50 | 34 | 2 | 4177.5 |
| 2/27/1983 | 1983 | 2 | 27 | 272 | 19 | 50 | 34.5 | 2.5 | 4180 |
| 2/28/1983 | 1983 | 2 | 28 | 273 | 20 | 43 | 31.5 | -0.5 | 4179.5 |
| 3/1/1983 | 1983 | 3 | 1 | 274 | 33 | 56 | 44.5 | 12.5 | 4192 |
| 3/2/1983 | 1983 | 3 | 2 | 275 | 39 | 54 | 46.5 | 14.5 | 4206.5 |
| 3/3/1983 | 1983 | 3 | 3 | 276 | 34 | 54 | 44 | 12 | 4218.5 |
| 3/4/1983 | 1983 | 3 | 4 | 277 | 12 | 40 | 26 | -6 | 4212.5 |
| 3/5/1983 | 1983 | 3 | 5 | 278 | 12 | 41 | 26.5 | -5.5 | 4207 |
| 3/6/1983 | 1983 | 3 | 6 | 279 | 15 | 45 | 30 | -2 | 4205 |
| 3/7/1983 | 1983 | 3 | 7 | 280 | 11 | 45 | 28 | -4 | 4201 |
| 3/8/1983 | 1983 | 3 | 8 | 281 | 11 | 50 | 30.5 | -1.5 | 4199.5 |
| 3/9/1983 | 1983 | 3 | 9 | 282 | 12 | 51 | 31.5 | -0.5 | 4199 |
| 3/10/1983 | 1983 | 3 | 10 | 283 | 20 | 56 | 38 | 6 | 4205 |
| 3/11/1983 | 1983 | 3 | 11 | 284 | 22 | 59 | 40.5 | 8.5 | 4213.5 |
| 3/12/1983 | 1983 | 3 | 12 | 285 | 25 | 61 | 43 | 11 | 4224.5 |
| 3/13/1983 | 1983 | 3 | 13 | 286 | 20 | 59 | 39.5 | 7.5 | 4232 |
| 3/14/1983 | 1983 | 3 | 14 | 287 | 19 | 56 | 37.5 | 5.5 | 4237.5 |
| 3/15/1983 | 1983 | 3 | 15 | 288 | 18 | 58 | 38 | 6 | 4243.5 |
| 3/16/1983 | 1983 | 3 | 16 | 289 | 30 | 59 | 44.5 | 12.5 | 4256 |
| 3/17/1983 | 1983 | 3 | 17 | 290 | 28 | 46 | 37 | 5 | 4261 |
| 3/18/1983 | 1983 | 3 | 18 | 291 | 25 | 47 | 36 | 4 | 4265 |
| 3/19/1983 | 1983 | 3 | 19 | 292 | 24 | 46 | 35 | 3 | 4268 |
| 3/20/1983 | 1983 | 3 | 20 | 293 | 25 | 42 | 33.5 | 1.5 | 4269.5 |
| 3/21/1983 | 1983 | 3 | 21 | 294 | 26 | 40 | 33 | 1 | 4270.5 |
| 3/22/1983 | 1983 | 3 | 22 | 295 | 23 | 39 | 31 | -1 | 4269.5 |
| 3/23/1983 | 1983 | 3 | 23 | 296 | 20 | 44 | 32 | 0 | 4269.5 |
| 3/24/1983 | 1983 | 3 | 24 | 297 | 25 | 44 | 34.5 | 2.5 | 4272 |
| 3/25/1983 | 1983 | 3 | 25 | 298 | 28 | 40 | 34 | 2 | 4274 |
| 3/26/1983 | 1983 | 3 | 26 | 299 | 21 | 39 | 30 | -2 | 4272 |
| 3/27/1983 | 1983 | 3 | 27 | 300 | 21 | 35 | 28 | -4 | 4268 |
| 3/28/1983 | 1983 | 3 | 28 | 301 | 20 | 46 | 33 | 1 | 4269 |
| 3/29/1983 | 1983 | 3 | 29 | 302 | 20 | 45 | 32.5 | 0.5 | 4269.5 |
| 3/30/1983 | 1983 | 3 | 30 | 303 | 29 | 49 | 39 | 7 | 4276.5 |
| 3/31/1983 | 1983 | 3 | 31 | 304 | 29 | 64 | 46.5 | 14.5 | 4291 |
| 4/1/1983 | 1983 | 4 | 1 | 305 | 20 | 30 | 25 | -7 | 4284 |
| 4/2/1983 | 1983 | 4 | 2 | 306 | 12 | 30 | 21 | -11 | 4273 |
| 4/3/1983 | 1983 | 4 | 3 | 307 | 16 | 30 | 23 | -9 | 4264 |
| 4/4/1983 | 1983 | 4 | 4 | 308 | 14 | 35 | 24.5 | -7.5 | 4256.5 |
| 4/5/1983 | 1983 | 4 | 5 | 309 | 11 | 37 | 24 | -8 | 4248.5 |
| 4/6/1983 | 1983 | 4 | 6 | 310 | 17 | 36 | 26.5 | -5.5 | 4243 |
| 4/7/1983 | 1983 | 4 | 7 | 311 | 18 | 40 | 29 | -3 | 4240 |
| 4/8/1983 | 1983 | 4 | 8 | 312 | 19 | 42 | 30.5 | -1.5 | 4238.5 |
| 4/9/1983 | 1983 | 4 | 9 | 313 | 20 | 45 | 32.5 | 0.5 | 4239 |
| 4/10/1983 | 1983 | 4 | 10 | 314 | 19 | 48 | 33.5 | 1.5 | 4240.5 |
| 4/11/1983 | 1983 | 4 | 11 | 315 | 17 | 47 | 32 | 0 | 4240.5 |
| 4/12/1983 | 1983 | 4 | 12 | 316 | 19 | 50 | 34.5 | 2.5 | 4243 |
| 4/13/1983 | 1983 | 4 | 13 | 317 | 20 | 57 | 38.5 | 6.5 | 4249.5 |
| 4/14/1983 | 1983 | 4 | 14 | 318 | 19 | 55 | 37 | 5 | 4254.5 |
| 4/15/1983 | 1983 | 4 | 15 | 319 | 13 | 56 | 34.5 | 2.5 | 4257 |
| 4/16/1983 | 1983 | 4 | 16 | 320 | 8 | 48 | 28 | -4 | 4253 |
| 4/17/1983 | 1983 | 4 | 17 | 321 | 10 | 36 | 23 | -9 | 4244 |
| 4/18/1983 | 1983 | 4 | 18 | 322 | 15 | 44 | 29.5 | -2.5 | 4241.5 |
| 4/19/1983 | 1983 | 4 | 19 | 323 | 12 | 40 | 26 | -6 | 4235.5 |
| 4/20/1983 | 1983 | 4 | 20 | 324 | 19 | 45 | 32 | 0 | 4235.5 |
| 4/21/1983 | 1983 | 4 | 21 | 325 | 20 | 50 | 35 | 3 | 4238.5 |
| 4/22/1983 | 1983 | 4 | 22 | 326 | 26 | 58 | 42 | 10 | 4248.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/23/1983 | 1983 | 4 | 23 | 327 | 27 | 64 | 45.5 | 13.5 | 4262 |
| 4/24/1983 | 1983 | 4 | 24 | 328 | 28 | 65 | 46.5 | 14.5 | 4276.5 |
| 4/25/1983 | 1983 | 4 | 25 | 329 | 30 | 64 | 47 | 15 | 4291.5 |
| 4/26/1983 | 1983 | 4 | 26 | 330 | 30 | 65 | 47.5 | 15.5 | 4307 |
| 4/27/1983 | 1983 | 4 | 27 | 331 | 34 | 61 | 47.5 | 15.5 | 4322.5 |
| 4/28/1983 | 1983 | 4 | 28 | 332 | 32 | 58 | 45 | 13 | 4335.5 |
| 4/29/1983 | 1983 | 4 | 29 | 333 | 34 | 66 | 50 | 18 | 4353.5 |
| 4/30/1983 | 1983 | 4 | 30 | 334 | 66 | 64 | 65 | 33 | 4386.5 |
| 5/1/1983 | 1983 | 5 | 1 | 335 | 32 | 57 | 44.5 | 12.5 | 4399 |
| 5/2/1983 | 1983 | 5 | 2 | 336 | 29 | 54 | 41.5 | 9.5 | 4408.5 |
| 5/3/1983 | 1983 | 5 | 3 | 337 | 31 | 60 | 45.5 | 13.5 | 4422 |
| 5/4/1983 | 1983 | 5 | 4 | 338 | 30 | 60 | 45 | 13 | 4435 |
| 5/5/1983 | 1983 | 5 | 5 | 339 | 32 | 61 | 46.5 | 14.5 | 4449.5 |
| 5/6/1983 | 1983 | 5 | 6 | 340 | 39 | 68 | 53.5 | 21.5 | 4471 |
| 5/7/1983 | 1983 | 5 | 7 | 341 | 41 | 68 | 54.5 | 22.5 | 4493.5 |
| 5/8/1983 | 1983 | 5 | 8 | 342 | 33 | 69 | 51 | 19 | 4512.5 |
| 5/9/1983 | 1983 | 5 | 9 | 343 | 48 | 73 | 60.5 | 28.5 | 4541 |
| 5/10/1983 | 1983 | 5 | 10 | 344 | 45 | 72 | 58.5 | 26.5 | 4567.5 |
| 5/11/1983 | 1983 | 5 | 11 | 345 | 44 | 73 | 58.5 | 26.5 | 4594 |
| 5/12/1983 | 1983 | 5 | 12 | 346 | 46 | 71 | 58.5 | 26.5 | 4620.5 |
| 5/13/1983 | 1983 | 5 | 13 | 347 | 31 | 67 | 49 | 17 | 4637.5 |
| 5/14/1983 | 1983 | 5 | 14 | 348 | 37 | 68 | 52.5 | 20.5 | 4658 |
| 5/15/1983 | 1983 | 5 | 15 | 349 | 32 | 62 | 47 | 15 | 4673 |
| 5/16/1983 | 1983 | 5 | 16 | 350 | 34 | 64 | 49 | 17 | 4690 |
| 5/17/1983 | 1983 | 5 | 17 | 351 | 39 | 67 | 53 | 21 | 4711 |
| 5/18/1983 | 1983 | 5 | 18 | 352 | 30 | 64 | 47 | 15 | 4726 |
| 5/19/1983 | 1983 | 5 | 19 | 353 | 29 | 61 | 45 | 13 | 4739 |
| 5/20/1983 | 1983 | 5 | 20 | 354 | 38 | 63 | 50.5 | 18.5 | 4757.5 |
| 5/21/1983 | 1983 | 5 | 21 | 355 | 33 | 46 | 39.5 | 7.5 | 4765 |
| 5/22/1983 | 1983 | 5 | 22 | 356 | 32 | 68 | 50 | 18 | 4783 |
| 5/23/1983 | 1983 | 5 | 23 | 357 | 40 | 74 | 57 | 25 | 4808 |
| 5/24/1983 | 1983 | 5 | 24 | 358 | 41 | 75 | 58 | 26 | 4834 |
| 5/25/1983 | 1983 | 5 | 25 | 359 | 47 | 77 | 62 | 30 | 4864 |
| 5/26/1983 | 1983 | 5 | 26 | 360 | 49 | 75 | 62 | 30 | 4894 |
| 5/27/1983 | 1983 | 5 | 27 | 361 | 52 | 77 | 64.5 | 32.5 | 4926.5 |
| 5/28/1983 | 1983 | 5 | 28 | 362 | 50 | 81 | 65.5 | 33.5 | 4960 |
| 5/29/1983 | 1983 | 5 | 29 | 363 | 50 | 81 | 65.5 | 33.5 | 4993.5 |
| 5/30/1983 | 1983 | 5 | 30 | 364 | 46 | 74 | 60 | 28 | 5021.5 |
| 5/31/1983 | 1983 | 5 | 31 | 365 | 49 | 74 | 61.5 | 29.5 | 5051 |
| 6/1/1983 | 1983 | 6 | 1 | 1 | 54 | 75 | 64.5 | 32.5 | 32.5 |
| 6/2/1983 | 1983 | 6 | 2 | 2 | 43 | 74 | 58.5 | 26.5 | 59 |
| 6/3/1983 | 1983 | 6 | 3 | 3 | 47 | 76 | 61.5 | 29.5 | 88.5 |
| 6/4/1983 | 1983 | 6 | 4 | 4 | 44 | 73 | 58.5 | 26.5 | 115 |
| 6/5/1983 | 1983 | 6 | 5 | 5 | 45 | 75 | 60 | 28 | 143 |
| 6/6/1983 | 1983 | 6 | 6 | 6 | 43 | 72 | 57.5 | 25.5 | 168.5 |
| 6/7/1983 | 1983 | 6 | 7 | 7 | 40 | 70 | 55 | 23 | 191.5 |
| 6/8/1983 | 1983 | 6 | 8 | 8 | 49 | 75 | 62 | 30 | 221.5 |
| 6/9/1983 | 1983 | 6 | 9 | 9 | 49 | 76 | 62.5 | 30.5 | 252 |
| 6/10/1983 | 1983 | 6 | 10 | 10 | 48 | 71 | 59.5 | 27.5 | 279.5 |
| 6/11/1983 | 1983 | 6 | 11 | 11 | 46 | 73 | 59.5 | 27.5 | 307 |
| 6/12/1983 | 1983 | 6 | 12 | 12 | 45 | 74 | 59.5 | 27.5 | 334.5 |
| 6/13/1983 | 1983 | 6 | 13 | 13 | 50 | 80 | 65 | 33 | 367.5 |
| 6/14/1983 | 1983 | 6 | 14 | 14 | 48 | 80 | 64 | 32 | 399.5 |
| 6/15/1983 | 1983 | 6 | 15 | 15 | 43 | 74 | 58.5 | 26.5 | 426 |
| 6/16/1983 | 1983 | 6 | 16 | 16 | 39 | 73 | 56 | 24 | 450 |
| 6/17/1983 | 1983 | 6 | 17 | 17 | 45 | 81 | 63 | 31 | 481 |
| 6/18/1983 | 1983 | 6 | 18 | 18 | 51 | 80 | 65.5 | 33.5 | 514.5 |
| 6/19/1983 | 1983 | 6 | 19 | 19 | 53 | 85 | 69 | 37 | 551.5 |
| 6/20/1983 | 1983 | 6 | 20 | 20 | 51 | 82 | 66.5 | 34.5 | 586 |
| 6/21/1983 | 1983 | 6 | 21 | 21 | 54 | 85 | 69.5 | 37.5 | 623.5 |
| 6/22/1983 | 1983 | 6 | 22 | 22 | 50 | 86 | 68 | 36 | 659.5 |
| 6/23/1983 | 1983 | 6 | 23 | 23 | 51 | 87 | 69 | 37 | 696.5 |
| 6/24/1983 | 1983 | 6 | 24 | 24 | 58 | 70 | 64 | 32 | 728.5 |
| 6/25/1983 | 1983 | 6 | 25 | 25 | 50 | 62 | 56 | 24 | 752.5 |
| 6/26/1983 | 1983 | 6 | 26 | 26 | 45 | 60 | 52.5 | 20.5 | 773 |
| 6/27/1983 | 1983 | 6 | 27 | 27 | 46 | 70 | 58 | 26 | 799 |
| 6/28/1983 | 1983 | 6 | 28 | 28 | 45 | 75 | 60 | 28 | 827 |
| 6/29/1983 | 1983 | 6 | 29 | 29 | 50 | 80 | 65 | 33 | 860 |
| 6/30/1983 | 1983 | 6 | 30 | 30 | 51 | 81 | 66 | 34 | 894 |
| 7/1/1983 | 1983 | 7 | 1 | 31 | 52 | 85 | 68.5 | 36.5 | 930.5 |
| 7/2/1983 | 1983 | 7 | 2 | 32 | 53 | 84 | 68.5 | 36.5 | 967 |
| 7/3/1983 | 1983 | 7 | 3 | 33 | 55 | 83 | 69 | 37 | 1004 |
| 7/4/1983 | 1983 | 7 | 4 | 34 | 56 | 85 | 70.5 | 38.5 | 1042.5 |
| 7/5/1983 | 1983 | 7 | 5 | 35 | 57 | 86 | 71.5 | 39.5 | 1082 |
| 7/6/1983 | 1983 | 7 | 6 | 36 | 54 | 83 | 68.5 | 36.5 | 1118.5 |
| 7/7/1983 | 1983 | 7 | 7 | 37 | 55 | 84 | 69.5 | 37.5 | 1156 |
| 7/8/1983 | 1983 | 7 | 8 | 38 | 58 | 82 | 70 | 38 | 1194 |
| 7/9/1983 | 1983 | 7 | 9 | 39 | 57 | 85 | 71 | 39 | 1233 |
| 7/10/1983 | 1983 | 7 | 10 | 40 | 54 | 81 | 67.5 | 35.5 | 1268.5 |
| 7/11/1983 | 1983 | 7 | 11 | 41 | 53 | 78 | 65.5 | 33.5 | 1302 |
| 7/12/1983 | 1983 | 7 | 12 | 42 | 49 | 75 | 62 | 30 | 1332 |
| 7/13/1983 | 1983 | 7 | 13 | 43 | 50 | 82 | 66 | 34 | 1366 |
| 7/14/1983 | 1983 | 7 | 14 | 44 | 54 | 83 | 68.5 | 36.5 | 1402.5 |
| 7/15/1983 | 1983 | 7 | 15 | 45 | 59 | 82 | 70.5 | 38.5 | 1441 |
| 7/16/1983 | 1983 | 7 | 16 | 46 | 57 | 85 | 71 | 39 | 1480 |
| 7/17/1983 | 1983 | 7 | 17 | 47 | 58 | 86 | 72 | 40 | 1520 |
| 7/18/1983 | 1983 | 7 | 18 | 48 | 56 | 80 | 68 | 36 | 1556 |
| 7/19/1983 | 1983 | 7 | 19 | 49 | 55 | 78 | 66.5 | 34.5 | 1590.5 |
| 7/20/1983 | 1983 | 7 | 20 | 50 | 54 | 79 | 66.5 | 34.5 | 1625 |
| 7/21/1983 | 1983 | 7 | 21 | 51 | 53 | 78 | 65.5 | 33.5 | 1658.5 |
| 7/22/1983 | 1983 | 7 | 22 | 52 | 54 | 80 | 67 | 35 | 1693.5 |
| 7/23/1983 | 1983 | 7 | 23 | 53 | 55 | 79 | 67 | 35 | 1728.5 |
| 7/24/1983 | 1983 | 7 | 24 | 54 | 55 | 80 | 67.5 | 35.5 | 1764 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/25/1983 | 1983 | 7 | 25 | 55 | 54 | 79 | 66.5 | 34.5 | 1798.5 |
| 7/26/1983 | 1983 | 7 | 26 | 56 | 52 | 76 | 64 | 32 | 1830.5 |
| 7/27/1983 | 1983 | 7 | 27 | 57 | 52 | 74 | 63 | 31 | 1861.5 |
| 7/28/1983 | 1983 | 7 | 28 | 58 | 54 | 77 | 65.5 | 33.5 | 1895 |
| 7/29/1983 | 1983 | 7 | 29 | 59 | 58 | 79 | 68.5 | 36.5 | 1931.5 |
| 7/30/1983 | 1983 | 7 | 30 | 60 | 57 | 78 | 67.5 | 35.5 | 1967 |
| 7/31/1983 | 1983 | 7 | 31 | 61 | 58 | 79 | 68.5 | 36.5 | 2003.5 |
| 8/1/1983 | 1983 | 8 | 1 | 62 | 55 | 77 | 66 | 34 | 2037.5 |
| 8/2/1983 | 1983 | 8 | 2 | 63 | 54 | 79 | 66.5 | 34.5 | 2072 |
| 8/3/1983 | 1983 | 8 | 3 | 64 | 56 | 78 | 67 | 35 | 2107 |
| 8/4/1983 | 1983 | 8 | 4 | 65 | 55 | 79 | 67 | 35 | 2142 |
| 8/5/1983 | 1983 | 8 | 5 | 66 | 58 | 80 | 69 | 37 | 2179 |
| 8/6/1983 | 1983 | 8 | 6 | 67 | 57 | 81 | 69 | 37 | 2216 |
| 8/7/1983 | 1983 | 8 | 7 | 68 | 59 | 80 | 69.5 | 37.5 | 2253.5 |
| 8/8/1983 | 1983 | 8 | 8 | 69 | 57 | 82 | 69.5 | 37.5 | 2291 |
| 8/9/1983 | 1983 | 8 | 9 | 70 | 56 | 81 | 68.5 | 36.5 | 2327.5 |
| 8/10/1983 | 1983 | 8 | 10 | 71 | 57 | 79 | 68 | 36 | 2363.5 |
| 8/11/1983 | 1983 | 8 | 11 | 72 | 55 | 77 | 66 | 34 | 2397.5 |
| 8/12/1983 | 1983 | 8 | 12 | 73 | 54 | 70 | 62 | 30 | 2427.5 |
| 8/13/1983 | 1983 | 8 | 13 | 74 | 55 | 74 | 64.5 | 32.5 | 2460 |
| 8/14/1983 | 1983 | 8 | 14 | 75 | 54 | 78 | 66 | 34 | 2494 |
| 8/15/1983 | 1983 | 8 | 15 | 76 | 55 | 79 | 67 | 35 | 2529 |
| 8/16/1983 | 1983 | 8 | 16 | 77 | 56 | 79 | 67.5 | 35.5 | 2564.5 |
| 8/17/1983 | 1983 | 8 | 17 | 78 | 54 | 80 | 67 | 35 | 2599.5 |
| 8/18/1983 | 1983 | 8 | 18 | 79 | 56 | 80 | 68 | 36 | 2635.5 |
| 8/19/1983 | 1983 | 8 | 19 | 80 | 57 | 80 | 68.5 | 36.5 | 2672 |
| 8/20/1983 | 1983 | 8 | 20 | 81 | 54 | 79 | 66.5 | 34.5 | 2706.5 |
| 8/21/1983 | 1983 | 8 | 21 | 82 | 50 | 77 | 63.5 | 31.5 | 2738 |
| 8/22/1983 | 1983 | 8 | 22 | 83 | 56 | 79 | 67.5 | 35.5 | 2773.5 |
| 8/23/1983 | 1983 | 8 | 23 | 84 | 55 | 78 | 66.5 | 34.5 | 2808 |
| 8/24/1983 | 1983 | 8 | 24 | 85 | 54 | 80 | 67 | 35 | 2843 |
| 8/25/1983 | 1983 | 8 | 25 | 86 | 56 | 77 | 66.5 | 34.5 | 2877.5 |
| 8/26/1983 | 1983 | 8 | 26 | 87 | 52 | 75 | 63.5 | 31.5 | 2909 |
| 8/27/1983 | 1983 | 8 | 27 | 88 | 54 | 76 | 65 | 33 | 2942 |
| 8/28/1983 | 1983 | 8 | 28 | 89 | 53 | 77 | 65 | 33 | 2975 |
| 8/29/1983 | 1983 | 8 | 29 | 90 | 51 | 75 | 63 | 31 | 3006 |
| 8/30/1983 | 1983 | 8 | 30 | 91 | 54 | 72 | 63 | 31 | 3037 |
| 8/31/1983 | 1983 | 8 | 31 | 92 | 54 | 76 | 65 | 33 | 3070 |
| 9/1/1983 | 1983 | 9 | 1 | 93 | 55 | 76 | 65.5 | 33.5 | 3103.5 |
| 9/2/1983 | 1983 | 9 | 2 | 94 | 57 | 77 | 67 | 35 | 3138.5 |
| 9/3/1983 | 1983 | 9 | 3 | 95 | 61 | 79 | 70 | 38 | 3176.5 |
| 9/4/1983 | 1983 | 9 | 4 | 96 | 57 | 80 | 68.5 | 36.5 | 3213 |
| 9/5/1983 | 1983 | 9 | 5 | 97 | 54 | 77 | 65.5 | 33.5 | 3246.5 |
| 9/6/1983 | 1983 | 9 | 6 | 98 | 52 | 69 | 60.5 | 28.5 | 3275 |
| 9/7/1983 | 1983 | 9 | 7 | 99 | 54 | 79 | 66.5 | 34.5 | 3309.5 |
| 9/8/1983 | 1983 | 9 | 8 | 100 | 55 | 74 | 64.5 | 32.5 | 3342 |
| 9/9/1983 | 1983 | 9 | 9 | 101 | 52 | 78 | 65 | 33 | 3375 |
| 9/10/1983 | 1983 | 9 | 10 | 102 | 55 | 79 | 67 | 35 | 3410 |
| 9/11/1983 | 1983 | 9 | 11 | 103 | 54 | 74 | 64 | 32 | 3442 |
| 9/12/1983 | 1983 | 9 | 12 | 104 | 52 | 70 | 61 | 29 | 3471 |
| 9/13/1983 | 1983 | 9 | 13 | 105 | 55 | 70 | 62.5 | 30.5 | 3501.5 |
| 9/14/1983 | 1983 | 9 | 14 | 106 | 48 | 74 | 61 | 29 | 3530.5 |
| 9/15/1983 | 1983 | 9 | 15 | 107 | 53 | 78 | 65.5 | 33.5 | 3564 |
| 9/16/1983 | 1983 | 9 | 16 | 108 | 54 | 78 | 66 | 34 | 3598 |
| 9/17/1983 | 1983 | 9 | 17 | 109 | 50 | 88 | 69 | 37 | 3635 |
| 9/18/1983 | 1983 | 9 | 18 | 110 | 50 | 75 | 62.5 | 30.5 | 3665.5 |
| 9/19/1983 | 1983 | 9 | 19 | 111 | 51 | 72 | 61.5 | 29.5 | 3695 |
| 9/20/1983 | 1983 | 9 | 20 | 112 | 35 | 71 | 53 | 21 | 3716 |
| 9/21/1983 | 1983 | 9 | 21 | 113 | 36 | 70 | 53 | 21 | 3737 |
| 9/22/1983 | 1983 | 9 | 22 | 114 | 45 | 73 | 59 | 27 | 3764 |
| 9/23/1983 | 1983 | 9 | 23 | 115 | 51 | 71 | 61 | 29 | 3793 |
| 9/24/1983 | 1983 | 9 | 24 | 116 | 42 | 69 | 55.5 | 23.5 | 3816.5 |
| 9/25/1983 | 1983 | 9 | 25 | 117 | 43 | 70 | 56.5 | 24.5 | 3841 |
| 9/26/1983 | 1983 | 9 | 26 | 118 | 46 | 71 | 58.5 | 26.5 | 3867.5 |
| 9/27/1983 | 1983 | 9 | 27 | 119 | 49 | 71 | 60 | 28 | 3895.5 |
| 9/28/1983 | 1983 | 9 | 28 | 120 | 45 | 60 | 52.5 | 20.5 | 3916 |
| 9/29/1983 | 1983 | 9 | 29 | 121 | 46 | 62 | 54 | 22 | 3938 |
| 9/30/1983 | 1983 | 9 | 30 | 122 | 46 | 62 | 54 | 22 | 3960 |
| 10/1/1983 | 1983 | 10 | 1 | 123 | 43 | 61 | 52 | 20 | 3980 |
| 10/2/1983 | 1983 | 10 | 2 | 124 | 42 | 61 | 51.5 | 19.5 | 3999.5 |
| 10/3/1983 | 1983 | 10 | 3 | 125 | 39 | 59 | 49 | 17 | 4016.5 |
| 10/4/1983 | 1983 | 10 | 4 | 126 | 37 | 61 | 49 | 17 | 4033.5 |
| 10/5/1983 | 1983 | 10 | 5 | 127 | 44 | 60 | 52 | 20 | 4053.5 |
| 10/6/1983 | 1983 | 10 | 6 | 128 | 43 | 64 | 53.5 | 21.5 | 4075 |
| 10/7/1983 | 1983 | 10 | 7 | 129 | 44 | 67 | 55.5 | 23.5 | 4098.5 |
| 10/8/1983 | 1983 | 10 | 8 | 130 | 47 | 66 | 56.5 | 24.5 | 4123 |
| 10/9/1983 | 1983 | 10 | 9 | 131 | 40 | 57 | 48.5 | 16.5 | 4139.5 |
| 10/10/1983 | 1983 | 10 | 10 | 132 | 41 | 58 | 49.5 | 17.5 | 4157 |
| 10/11/1983 | 1983 | 10 | 11 | 133 | 42 | 55 | 48.5 | 16.5 | 4173.5 |
| 10/12/1983 | 1983 | 10 | 12 | 134 | 36 | 56 | 46 | 14 | 4187.5 |
| 10/13/1983 | 1983 | 10 | 13 | 135 | 36 | 57 | 46.5 | 14.5 | 4202 |
| 10/14/1983 | 1983 | 10 | 14 | 136 | 38 | 68 | 53 | 21 | 4223 |
| 10/15/1983 | 1983 | 10 | 15 | 137 | 45 | 66 | 55.5 | 23.5 | 4246.5 |
| 10/16/1983 | 1983 | 10 | 16 | 138 | 39 | 58 | 48.5 | 16.5 | 4263 |
| 10/17/1983 | 1983 | 10 | 17 | 139 | 37 | 60 | 48.5 | 16.5 | 4279.5 |
| 10/18/1983 | 1983 | 10 | 18 | 140 | 41 | 62 | 51.5 | 19.5 | 4299 |
| 10/19/1983 | 1983 | 10 | 19 | 141 | 42 | 65 | 53.5 | 21.5 | 4320.5 |
| 10/20/1983 | 1983 | 10 | 20 | 142 | 46 | 64 | 55 | 23 | 4343.5 |
| 10/21/1983 | 1983 | 10 | 21 | 143 | 43 | 57 | 50 | 18 | 4361.5 |
| 10/22/1983 | 1983 | 10 | 22 | 144 | 36 | 60 | 48 | 16 | 4377.5 |
| 10/23/1983 | 1983 | 10 | 23 | 145 | 40 | 64 | 52 | 20 | 4397.5 |
| 10/24/1983 | 1983 | 10 | 24 | 146 | 39 | 64 | 51.5 | 19.5 | 4417 |
| 10/25/1983 | 1983 | 10 | 25 | 147 | 42 | 62 | 52 | 20 | 4437 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/26/1983 | 1983 | 10 | 26 | 148 | 33 | 55 | 44 | 12 | 4449 |
| 10/27/1983 | 1983 | 10 | 27 | 149 | 32 | 54 | 43 | 11 | 4460 |
| 10/28/1983 | 1983 | 10 | 28 | 150 | 33 | 55 | 44 | 12 | 4472 |
| 10/29/1983 | 1983 | 10 | 29 | 151 | 32 | 55 | 43.5 | 11.5 | 4483.5 |
| 10/30/1983 | 1983 | 10 | 30 | 152 | 33 | 60 | 46.5 | 14.5 | 4498 |
| 10/31/1983 | 1983 | 10 | 31 | 153 | 43 | 64 | 53.5 | 21.5 | 4519.5 |
| 11/1/1983 | 1983 | 11 | 1 | 154 | 39 | 61 | 50 | 18 | 4537.5 |
| 11/2/1983 | 1983 | 11 | 2 | 155 | 40 | 62 | 51 | 19 | 4556.5 |
| 11/3/1983 | 1983 | 11 | 3 | 156 | 39 | 64 | 51.5 | 19.5 | 4576 |
| 11/4/1983 | 1983 | 11 | 4 | 157 | 40 | 57 | 48.5 | 16.5 | 4592.5 |
| 11/5/1983 | 1983 | 11 | 5 | 158 | 40 | 59 | 49.5 | 17.5 | 4610 |
| 11/6/1983 | 1983 | 11 | 6 | 159 | 38 | 60 | 49 | 17 | 4627 |
| 11/7/1983 | 1983 | 11 | 7 | 160 | 37 | 63 | 50 | 18 | 4645 |
| 11/8/1983 | 1983 | 11 | 8 | 161 | 36 | 63 | 49.5 | 17.5 | 4662.5 |
| 11/9/1983 | 1983 | 11 | 9 | 162 | 21 | 59 | 40 | 8 | 4670.5 |
| 11/10/1983 | 1983 | 11 | 10 | 163 | 27 | 55 | 41 | 9 | 4679.5 |
| 11/11/1983 | 1983 | 11 | 11 | 164 | 26 | 56 | 41 | 9 | 4688.5 |
| 11/12/1983 | 1983 | 11 | 12 | 165 | 33 | 60 | 46.5 | 14.5 | 4703 |
| 11/13/1983 | 1983 | 11 | 13 | 166 | 39 | 60 | 49.5 | 17.5 | 4720.5 |
| 11/14/1983 | 1983 | 11 | 14 | 167 | 38 | 61 | 49.5 | 17.5 | 4738 |
| 11/15/1983 | 1983 | 11 | 15 | 168 | 20 | 54 | 37 | 5 | 4743 |
| 11/16/1983 | 1983 | 11 | 16 | 169 | 24 | 55 | 39.5 | 7.5 | 4750.5 |
| 11/17/1983 | 1983 | 11 | 17 | 170 | 25 | 59 | 42 | 10 | 4760.5 |
| 11/18/1983 | 1983 | 11 | 18 | 171 | 31 | 58 | 44.5 | 12.5 | 4773 |
| 11/19/1983 | 1983 | 11 | 19 | 172 | 11 | 52 | 31.5 | -0.5 | 4772.5 |
| 11/20/1983 | 1983 | 11 | 20 | 173 | 15 | 36 | 25.5 | -6.5 | 4766 |
| 11/21/1983 | 1983 | 11 | 21 | 174 | 26 | 45 | 35.5 | 3.5 | 4769.5 |
| 11/22/1983 | 1983 | 11 | 22 | 175 | 7 | 40 | 23.5 | -8.5 | 4761 |
| 11/23/1983 | 1983 | 11 | 23 | 176 | 11 | 27 | 19 | -13 | 4748 |
| 11/24/1983 | 1983 | 11 | 24 | 177 | 16 | 26 | 21 | -11 | 4737 |
| 11/25/1983 | 1983 | 11 | 25 | 178 | 15 | 45 | 30 | -2 | 4735 |
| 11/26/1983 | 1983 | 11 | 26 | 179 | 16 | 46 | 31 | -1 | 4734 |
| 11/27/1983 | 1983 | 11 | 27 | 180 | 12 | 42 | 27 | -5 | 4729 |
| 11/28/1983 | 1983 | 11 | 28 | 181 | 13 | 39 | 26 | -6 | 4723 |
| 11/29/1983 | 1983 | 11 | 29 | 182 | 10 | 37 | 23.5 | -8.5 | 4714.5 |
| 11/30/1983 | 1983 | 11 | 30 | 183 | 15 | 39 | 27 | -5 | 4709.5 |
| 12/1/1983 | 1983 | 12 | 1 | 184 | 26 | 49 | 37.5 | 5.5 | 4715 |
| 12/2/1983 | 1983 | 12 | 2 | 185 | 12 | 46 | 29 | -3 | 4712 |
| 12/3/1983 | 1983 | 12 | 3 | 186 | 12 | 40 | 26 | -6 | 4706 |
| 12/4/1983 | 1983 | 12 | 4 | 187 | 18 | 40 | 29 | -3 | 4703 |
| 12/5/1983 | 1983 | 12 | 5 | 188 | 19 | 41 | 30 | -2 | 4701 |
| 12/6/1983 | 1983 | 12 | 6 | 189 | 10 | 40 | 25 | -7 | 4694 |
| 12/7/1983 | 1983 | 12 | 7 | 190 | 18 | 42 | 30 | -2 | 4692 |
| 12/8/1983 | 1983 | 12 | 8 | 191 | 19 | 48 | 33.5 | 1.5 | 4693.5 |
| 12/9/1983 | 1983 | 12 | 9 | 192 | 20 | 48 | 34 | 2 | 4695.5 |
| 12/10/1983 | 1983 | 12 | 10 | 193 | 19 | 47 | 33 | 1 | 4696.5 |
| 12/11/1983 | 1983 | 12 | 11 | 194 | 18 | 46 | 32 | 0 | 4696.5 |
| 12/12/1983 | 1983 | 12 | 12 | 195 | 17 | 40 | 28.5 | -3.5 | 4693 |
| 12/13/1983 | 1983 | 12 | 13 | 196 | 16 | 39 | 27.5 | -4.5 | 4688.5 |
| 12/14/1983 | 1983 | 12 | 14 | 197 | 16 | 40 | 28 | -4 | 4684.5 |
| 12/15/1983 | 1983 | 12 | 15 | 198 | 20 | 35 | 27.5 | -4.5 | 4680 |
| 12/16/1983 | 1983 | 12 | 16 | 199 | 16 | 43 | 29.5 | -2.5 | 4677.5 |
| 12/17/1983 | 1983 | 12 | 17 | 200 | 17 | 37 | 27 | -5 | 4672.5 |
| 12/18/1983 | 1983 | 12 | 18 | 201 | 15 | 36 | 25.5 | -6.5 | 4666 |
| 12/19/1983 | 1983 | 12 | 19 | 202 | 15 | 35 | 25 | -7 | 4659 |
| 12/20/1983 | 1983 | 12 | 20 | 203 | 6 | 32 | 19 | -13 | 4646 |
| 12/21/1983 | 1983 | 12 | 21 | 204 | 11 | 36 | 23.5 | -8.5 | 4637.5 |
| 12/22/1983 | 1983 | 12 | 22 | 205 | 15 | 38 | 26.5 | -5.5 | 4632 |
| 12/23/1983 | 1983 | 12 | 23 | 206 | 19 | 35 | 27 | -5 | 4627 |
| 12/24/1983 | 1983 | 12 | 24 | 207 | 16 | 34 | 25 | -7 | 4620 |
| 12/25/1983 | 1983 | 12 | 25 | 208 | 17 | 36 | 26.5 | -5.5 | 4614.5 |
| 12/26/1983 | 1983 | 12 | 26 | 209 | 19 | 37 | 28 | -4 | 4610.5 |
| 12/27/1983 | 1983 | 12 | 27 | 210 | 17 | 34 | 25.5 | -6.5 | 4604 |
| 12/28/1983 | 1983 | 12 | 28 | 211 | 4 | 35 | 19.5 | -12.5 | 4591.5 |
| 12/29/1983 | 1983 | 12 | 29 | 212 | 9 | 25 | 17 | -15 | 4576.5 |
| 12/30/1983 | 1983 | 12 | 30 | 213 | 16 | 39 | 27.5 | -4.5 | 4572 |
| 12/31/1983 | 1983 | 12 | 31 | 214 | 15 | 38 | 26.5 | -5.5 | 4566.5 |
| 1/1/1984 | 1984 | 1 | 1 | 215 | 20 | 39 | 29.5 | -2.5 | 4564 |
| 1/2/1984 | 1984 | 1 | 2 | 216 | 24 | 40 | 32 | 0 | 4564 |
| 1/3/1984 | 1984 | 1 | 3 | 217 | 20 | 39 | 29.5 | -2.5 | 4561.5 |
| 1/4/1984 | 1984 | 1 | 4 | 218 | 21 | 40 | 30.5 | -1.5 | 4560 |
| 1/5/1984 | 1984 | 1 | 5 | 219 | 20 | 39 | 29.5 | -2.5 | 4557.5 |
| 1/6/1984 | 1984 | 1 | 6 | 220 | 22 | 36 | 29 | -3 | 4554.5 |
| 1/7/1984 | 1984 | 1 | 7 | 221 | 27 | 37 | 32 | 0 | 4554.5 |
| 1/8/1984 | 1984 | 1 | 8 | 222 | 27 | 45 | 36 | 4 | 4558.5 |
| 1/9/1984 | 1984 | 1 | 9 | 223 | 26 | 46 | 36 | 4 | 4562.5 |
| 1/10/1984 | 1984 | 1 | 10 | 224 | 17 | 43 | 30 | -2 | 4560.5 |
| 1/11/1984 | 1984 | 1 | 11 | 225 | 18 | 41 | 29.5 | -2.5 | 4558 |
| 1/12/1984 | 1984 | 1 | 12 | 226 | 15 | 39 | 27 | -5 | 4553 |
| 1/13/1984 | 1984 | 1 | 13 | 227 | 16 | 38 | 27 | -5 | 4548 |
| 1/14/1984 | 1984 | 1 | 14 | 228 | 9 | 37 | 23 | -9 | 4539 |
| 1/15/1984 | 1984 | 1 | 15 | 229 | 10 | 35 | 22.5 | -9.5 | 4529.5 |
| 1/16/1984 | 1984 | 1 | 16 | 230 | 13 | 32 | 22.5 | -9.5 | 4520 |
| 1/17/1984 | 1984 | 1 | 17 | 231 | 17 | 28 | 22.5 | -9.5 | 4510.5 |
| 1/18/1984 | 1984 | 1 | 18 | 232 | -4 | 22 | 9 | -23 | 4487.5 |
| 1/19/1984 | 1984 | 1 | 19 | 233 | -13 | 29 | 8 | -24 | 4463.5 |
| 1/20/1984 | 1984 | 1 | 20 | 234 | -13 | 34 | 10.5 | -21.5 | 4442 |
| 1/21/1984 | 1984 | 1 | 21 | 235 | -4 | 30 | 13 | -19 | 4423 |
| 1/22/1984 | 1984 | 1 | 22 | 236 | 11 | 39 | 25 | -7 | 4416 |
| 1/23/1984 | 1984 | 1 | 23 | 237 | 12 | 34 | 23 | -9 | 4407 |
| 1/24/1984 | 1984 | 1 | 24 | 238 | -6 | 34 | 14 | -18 | 4389 |
| 1/25/1984 | 1984 | 1 | 25 | 239 | 15 | 37 | 26 | -6 | 4383 |
| 1/26/1984 | 1984 | 1 | 26 | 240 | 19 | 42 | 30.5 | -1.5 | 4381.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/27/1984 | 1984 | 1 | 27 | 241 | 18 | 43 | 30.5 | -1.5 | 4380 |
| 1/28/1984 | 1984 | 1 | 28 | 242 | 21 | 45 | 33 | 1 | 4381 |
| 1/29/1984 | 1984 | 1 | 29 | 243 | 20 | 41 | 30.5 | -1.5 | 4379.5 |
| 1/30/1984 | 1984 | 1 | 30 | 244 | 17 | 44 | 30.5 | -1.5 | 4378 |
| 1/31/1984 | 1984 | 1 | 31 | 245 | 19 | 45 | 32 | 0 | 4378 |
| 2/1/1984 | 1984 | 2 | 1 | 246 | 22 | 49 | 35.5 | 3.5 | 4381.5 |
| 2/2/1984 | 1984 | 2 | 2 | 247 | 24 | 48 | 36 | 4 | 4385.5 |
| 2/3/1984 | 1984 | 2 | 3 | 248 | 20 | 47 | 33.5 | 1.5 | 4387 |
| 2/4/1984 | 1984 | 2 | 4 | 249 | 25 | 42 | 33.5 | 1.5 | 4388.5 |
| 2/5/1984 | 1984 | 2 | 5 | 250 | 32 | 49 | 40.5 | 8.5 | 4397 |
| 2/6/1984 | 1984 | 2 | 6 | 251 | 23 | 55 | 39 | 7 | 4404 |
| 2/7/1984 | 1984 | 2 | 7 | 252 | 25 | 54 | 39.5 | 7.5 | 4411.5 |
| 2/8/1984 | 1984 | 2 | 8 | 253 | 21 | 42 | 31.5 | -0.5 | 4411 |
| 2/9/1984 | 1984 | 2 | 9 | 254 | 23 | 40 | 31.5 | -0.5 | 4410.5 |
| 2/10/1984 | 1984 | 2 | 10 | 255 | 12 | 41 | 26.5 | -5.5 | 4405 |
| 2/11/1984 | 1984 | 2 | 11 | 256 | 13 | 42 | 27.5 | -4.5 | 4400.5 |
| 2/12/1984 | 1984 | 2 | 12 | 257 | 15 | 45 | 30 | -2 | 4398.5 |
| 2/13/1984 | 1984 | 2 | 13 | 258 | 13 | 45 | 29 | -3 | 4395.5 |
| 2/14/1984 | 1984 | 2 | 14 | 259 | 13 | 50 | 31.5 | -0.5 | 4395 |
| 2/15/1984 | 1984 | 2 | 15 | 260 | 12 | 50 | 31 | -1 | 4394 |
| 2/16/1984 | 1984 | 2 | 16 | 261 | 16 | 50 | 33 | 1 | 4395 |
| 2/17/1984 | 1984 | 2 | 17 | 262 | 11 | 50 | 30.5 | -1.5 | 4393.5 |
| 2/18/1984 | 1984 | 2 | 18 | 263 | 15 | 49 | 32 | 0 | 4393.5 |
| 2/19/1984 | 1984 | 2 | 19 | 264 | 19 | 36 | 27.5 | -4.5 | 4389 |
| 2/20/1984 | 1984 | 2 | 20 | 265 | 15 | 35 | 25 | -7 | 4382 |
| 2/21/1984 | 1984 | 2 | 21 | 266 | 12 | 36 | 24 | -8 | 4374 |
| 2/22/1984 | 1984 | 2 | 22 | 267 | 14 | 39 | 26.5 | -5.5 | 4368.5 |
| 2/23/1984 | 1984 | 2 | 23 | 268 | 19 | 49 | 34 | 2 | 4370.5 |
| 2/24/1984 | 1984 | 2 | 24 | 269 | 15 | 48 | 31.5 | -0.5 | 4370 |
| 2/25/1984 | 1984 | 2 | 25 | 270 | 18 | 49 | 33.5 | 1.5 | 4371.5 |
| 2/26/1984 | 1984 | 2 | 26 | 271 | 30 | 48 | 39 | 7 | 4378.5 |
| 2/27/1984 | 1984 | 2 | 27 | 272 | 71 | 40 | 55.5 | 23.5 | 4402 |
| 2/28/1984 | 1984 | 2 | 28 | 273 | 12 | 40 | 26 | -6 | 4396 |
| 2/29/1984 | 1984 | 2 | 29 | 274 | 19 | 50 | 34.5 | 2.5 | 4398.5 |
| 3/1/1984 | 1984 | 3 | 1 | 275 | 27 | 58 | 42.5 | 10.5 | 4409 |
| 3/2/1984 | 1984 | 3 | 2 | 276 | 26 | 57 | 41.5 | 9.5 | 4418.5 |
| 3/3/1984 | 1984 | 3 | 3 | 277 | 25 | 54 | 39.5 | 7.5 | 4426 |
| 3/4/1984 | 1984 | 3 | 4 | 278 | 22 | 52 | 37 | 5 | 4431 |
| 3/5/1984 | 1984 | 3 | 5 | 279 | 15 | 38 | 26.5 | -5.5 | 4425.5 |
| 3/6/1984 | 1984 | 3 | 6 | 280 | 13 | 39 | 26 | -6 | 4419.5 |
| 3/7/1984 | 1984 | 3 | 7 | 281 | 16 | 48 | 32 | 0 | 4419.5 |
| 3/8/1984 | 1984 | 3 | 8 | 282 | 25 | 50 | 37.5 | 5.5 | 4425 |
| 3/9/1984 | 1984 | 3 | 9 | 283 | 26 | 51 | 38.5 | 6.5 | 4431.5 |
| 3/10/1984 | 1984 | 3 | 10 | 284 | 27 | 55 | 41 | 9 | 4440.5 |
| 3/11/1984 | 1984 | 3 | 11 | 285 | 17 | 51 | 34 | 2 | 4442.5 |
| 3/12/1984 | 1984 | 3 | 12 | 286 | 25 | 55 | 40 | 8 | 4450.5 |
| 3/13/1984 | 1984 | 3 | 13 | 287 | 32 | 60 | 46 | 14 | 4464.5 |
| 3/14/1984 | 1984 | 3 | 14 | 288 | 39 | 61 | 50 | 18 | 4482.5 |
| 3/15/1984 | 1984 | 3 | 15 | 289 | 33 | 60 | 46.5 | 14.5 | 4497 |
| 3/16/1984 | 1984 | 3 | 16 | 290 | 40 | 59 | 49.5 | 17.5 | 4514.5 |
| 3/17/1984 | 1984 | 3 | 17 | 291 | 28 | 60 | 44 | 12 | 4526.5 |
| 3/18/1984 | 1984 | 3 | 18 | 292 | 19 | 60 | 39.5 | 7.5 | 4534 |
| 3/19/1984 | 1984 | 3 | 19 | 293 | 20 | 53 | 36.5 | 4.5 | 4538.5 |
| 3/20/1984 | 1984 | 3 | 20 | 294 | 24 | 61 | 42.5 | 10.5 | 4549 |
| 3/21/1984 | 1984 | 3 | 21 | 295 | 31 | 64 | 47.5 | 15.5 | 4564.5 |
| 3/22/1984 | 1984 | 3 | 22 | 296 | 29 | 61 | 45 | 13 | 4577.5 |
| 3/23/1984 | 1984 | 3 | 23 | 297 | 19 | 45 | 32 | 0 | 4577.5 |
| 3/24/1984 | 1984 | 3 | 24 | 298 | 25 | 58 | 41.5 | 9.5 | 4587 |
| 3/25/1984 | 1984 | 3 | 25 | 299 | 26 | 58 | 42 | 10 | 4597 |
| 3/26/1984 | 1984 | 3 | 26 | 300 | 24 | 45 | 34.5 | 2.5 | 4599.5 |
| 3/27/1984 | 1984 | 3 | 27 | 301 | 28 | 38 | 33 | 1 | 4600.5 |
| 3/28/1984 | 1984 | 3 | 28 | 302 | 21 | 39 | 30 | -2 | 4598.5 |
| 3/29/1984 | 1984 | 3 | 29 | 303 | 25 | 40 | 32.5 | 0.5 | 4599 |
| 3/30/1984 | 1984 | 3 | 30 | 304 | 20 | 43 | 31.5 | -0.5 | 4598.5 |
| 3/31/1984 | 1984 | 3 | 31 | 305 | 31 | 46 | 38.5 | 6.5 | 4605 |
| 4/1/1984 | 1984 | 4 | 1 | 306 | 25 | 40 | 32.5 | 0.5 | 4605.5 |
| 4/2/1984 | 1984 | 4 | 2 | 307 | 25 | 40 | 32.5 | 0.5 | 4606 |
| 4/3/1984 | 1984 | 4 | 3 | 308 | 27 | 47 | 37 | 5 | 4611 |
| 4/4/1984 | 1984 | 4 | 4 | 309 | 23 | 50 | 36.5 | 4.5 | 4615.5 |
| 4/5/1984 | 1984 | 4 | 5 | 310 | 25 | 50 | 37.5 | 5.5 | 4621 |
| 4/6/1984 | 1984 | 4 | 6 | 311 | 23 | 61 | 42 | 10 | 4631 |
| 4/7/1984 | 1984 | 4 | 7 | 312 | 25 | 61 | 43 | 11 | 4642 |
| 4/8/1984 | 1984 | 4 | 8 | 313 | 28 | 58 | 43 | 11 | 4653 |
| 4/9/1984 | 1984 | 4 | 9 | 314 | 22 | 56 | 39 | 7 | 4660 |
| 4/10/1984 | 1984 | 4 | 10 | 315 | 24 | 40 | 32 | 0 | 4660 |
| 4/11/1984 | 1984 | 4 | 11 | 316 | 23 | 59 | 41 | 9 | 4669 |
| 4/12/1984 | 1984 | 4 | 12 | 317 | 39 | 61 | 50 | 18 | 4687 |
| 4/13/1984 | 1984 | 4 | 13 | 318 | 27 | 62 | 44.5 | 12.5 | 4699.5 |
| 4/14/1984 | 1984 | 4 | 14 | 319 | 30 | 64 | 47 | 15 | 4714.5 |
| 4/15/1984 | 1984 | 4 | 15 | 320 | 32 | 65 | 48.5 | 16.5 | 4731 |
| 4/16/1984 | 1984 | 4 | 16 | 321 | 30 | 68 | 49 | 17 | 4748 |
| 4/17/1984 | 1984 | 4 | 17 | 322 | 32 | 72 | 52 | 20 | 4768 |
| 4/18/1984 | 1984 | 4 | 18 | 323 | 40 | 71 | 55.5 | 23.5 | 4791.5 |
| 4/19/1984 | 1984 | 4 | 19 | 324 | 45 | 69 | 57 | 25 | 4816.5 |
| 4/20/1984 | 1984 | 4 | 20 | 325 | 40 | 66 | 53 | 21 | 4837.5 |
| 4/21/1984 | 1984 | 4 | 21 | 326 | 25 | 61 | 43 | 11 | 4848.5 |
| 4/22/1984 | 1984 | 4 | 22 | 327 | 31 | 48 | 39.5 | 7.5 | 4856 |
| 4/23/1984 | 1984 | 4 | 23 | 328 | 25 | 54 | 39.5 | 7.5 | 4863.5 |
| 4/24/1984 | 1984 | 4 | 24 | 329 | 31 | 64 | 47.5 | 15.5 | 4879 |
| 4/25/1984 | 1984 | 4 | 25 | 330 | 30 | 66 | 48 | 16 | 4895 |
| 4/26/1984 | 1984 | 4 | 26 | 331 | 36 | 69 | 52.5 | 20.5 | 4915.5 |
| 4/27/1984 | 1984 | 4 | 27 | 332 | 37 | 67 | 52 | 20 | 4935.5 |
| 4/28/1984 | 1984 | 4 | 28 | 333 | 30 | 57 | 43.5 | 11.5 | 4947 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/29/1984 | 1984 | 4 | 29 | 334 | 21 | 43 | 32 | 0 | 4947 |
| 4/30/1984 | 1984 | 4 | 30 | 335 | 27 | 50 | 38.5 | 6.5 | 4953.5 |
| 5/1/1984 | 1984 | 5 | 1 | 336 | 39 | 63 | 51 | 19 | 4972.5 |
| 5/2/1984 | 1984 | 5 | 2 | 337 | 38 | 64 | 51 | 19 | 4991.5 |
| 5/3/1984 | 1984 | 5 | 3 | 338 | 35 | 69 | 52 | 20 | 5011.5 |
| 5/4/1984 | 1984 | 5 | 4 | 339 | 34 | 70 | 52 | 20 | 5031.5 |
| 5/5/1984 | 1984 | 5 | 5 | 340 | 44 | 71 | 57.5 | 25.5 | 5057 |
| 5/6/1984 | 1984 | 5 | 6 | 341 | 48 | 69 | 58.5 | 26.5 | 5083.5 |
| 5/7/1984 | 1984 | 5 | 7 | 342 | 43 | 68 | 55.5 | 23.5 | 5107 |
| 5/8/1984 | 1984 | 5 | 8 | 343 | 35 | 67 | 51 | 19 | 5126 |
| 5/9/1984 | 1984 | 5 | 9 | 344 | 30 | 71 | 50.5 | 18.5 | 5144.5 |
| 5/10/1984 | 1984 | 5 | 10 | 345 | 39 | 72 | 55.5 | 23.5 | 5168 |
| 5/11/1984 | 1984 | 5 | 11 | 346 | 47 | 78 | 62.5 | 30.5 | 5198.5 |
| 5/12/1984 | 1984 | 5 | 12 | 347 | 53 | 80 | 66.5 | 34.5 | 5233 |
| 5/13/1984 | 1984 | 5 | 13 | 348 | 54 | 79 | 66.5 | 34.5 | 5267.5 |
| 5/14/1984 | 1984 | 5 | 14 | 349 | 49 | 80 | 64.5 | 32.5 | 5300 |
| 5/15/1984 | 1984 | 5 | 15 | 350 | 49 | 76 | 62.5 | 30.5 | 5330.5 |
| 5/16/1984 | 1984 | 5 | 16 | 351 | 41 | 66 | 53.5 | 21.5 | 5352 |
| 5/17/1984 | 1984 | 5 | 17 | 352 | 39 | 64 | 51.5 | 19.5 | 5371.5 |
| 5/18/1984 | 1984 | 5 | 18 | 353 | 44 | 70 | 57 | 25 | 5396.5 |
| 5/19/1984 | 1984 | 5 | 19 | 354 | 42 | 74 | 58 | 26 | 5422.5 |
| 5/20/1984 | 1984 | 5 | 20 | 355 | 44 | 74 | 59 | 27 | 5449.5 |
| 5/21/1984 | 1984 | 5 | 21 | 356 | 43 | 75 | 59 | 27 | 5476.5 |
| 5/22/1984 | 1984 | 5 | 22 | 357 | 46 | 80 | 63 | 31 | 5507.5 |
| 5/23/1984 | 1984 | 5 | 23 | 358 | 55 | 80 | 67.5 | 35.5 | 5543 |
| 5/24/1984 | 1984 | 5 | 24 | 359 | 54 | 85 | 69.5 | 37.5 | 5580.5 |
| 5/25/1984 | 1984 | 5 | 25 | 360 | 52 | 86 | 69 | 37 | 5617.5 |
| 5/26/1984 | 1984 | 5 | 26 | 361 | 53 | 84 | 68.5 | 36.5 | 5654 |
| 5/27/1984 | 1984 | 5 | 27 | 362 | 50 | 83 | 66.5 | 34.5 | 5688.5 |
| 5/28/1984 | 1984 | 5 | 28 | 363 | 51 | 87 | 69 | 37 | 5725.5 |
| 5/29/1984 | 1984 | 5 | 29 | 364 | 52 | 84 | 68 | 36 | 5761.5 |
| 5/30/1984 | 1984 | 5 | 30 | 365 | 49 | 78 | 63.5 | 31.5 | 5793 |
| 5/31/1984 | 1984 | 5 | 31 | 366 | 47 | 80 | 63.5 | 31.5 | 5824.5 |
| 6/1/1984 | 1984 | 6 | 1 | 1 | 45 | 71 | 58 | 26 | 26 |
| 6/2/1984 | 1984 | 6 | 2 | 2 | 46 | 76 | 61 | 29 | 55 |
| 6/3/1984 | 1984 | 6 | 3 | 3 | 54 | 74 | 64 | 32 | 87 |
| 6/4/1984 | 1984 | 6 | 4 | 4 | 50 | 73 | 61.5 | 29.5 | 116.5 |
| 6/5/1984 | 1984 | 6 | 5 | 5 | 52 | 73 | 62.5 | 30.5 | 147 |
| 6/6/1984 | 1984 | 6 | 6 | 6 | 44 | 73 | 58.5 | 26.5 | 173.5 |
| 6/7/1984 | 1984 | 6 | 7 | 7 | 48 | 74 | 61 | 29 | 202.5 |
| 6/8/1984 | 1984 | 6 | 8 | 8 | 44 | 75 | 59.5 | 27.5 | 230 |
| 6/9/1984 | 1984 | 6 | 9 | 9 | 39 | 74 | 56.5 | 24.5 | 254.5 |
| 6/10/1984 | 1984 | 6 | 10 | 10 | 50 | 82 | 66 | 34 | 288.5 |
| 6/11/1984 | 1984 | 6 | 11 | 11 | 49 | 81 | 65 | 33 | 321.5 |
| 6/12/1984 | 1984 | 6 | 12 | 12 | 51 | 80 | 65.5 | 33.5 | 355 |
| 6/13/1984 | 1984 | 6 | 13 | 13 | 50 | 84 | 67 | 35 | 390 |
| 6/14/1984 | 1984 | 6 | 14 | 14 | 53 | 81 | 67 | 35 | 425 |
| 6/15/1984 | 1984 | 6 | 15 | 15 | 49 | 76 | 62.5 | 30.5 | 455.5 |
| 6/16/1984 | 1984 | 6 | 16 | 16 | 48 | 74 | 61 | 29 | 484.5 |
| 6/17/1984 | 1984 | 6 | 17 | 17 | 46 | 80 | 63 | 31 | 515.5 |
| 6/18/1984 | 1984 | 6 | 18 | 18 | 53 | 82 | 67.5 | 35.5 | 551 |
| 6/19/1984 | 1984 | 6 | 19 | 19 | 52 | 83 | 67.5 | 35.5 | 586.5 |
| 6/20/1984 | 1984 | 6 | 20 | 20 | 47 | 79 | 63 | 31 | 617.5 |
| 6/21/1984 | 1984 | 6 | 21 | 21 | 50 | 80 | 65 | 33 | 650.5 |
| 6/22/1984 | 1984 | 6 | 22 | 22 | 56 | 82 | 69 | 37 | 687.5 |
| 6/23/1984 | 1984 | 6 | 23 | 23 | 55 | 81 | 68 | 36 | 723.5 |
| 6/24/1984 | 1984 | 6 | 24 | 24 | 60 | 79 | 69.5 | 37.5 | 761 |
| 6/25/1984 | 1984 | 6 | 25 | 25 | 55 | 77 | 66 | 34 | 795 |
| 6/26/1984 | 1984 | 6 | 26 | 26 | 54 | 78 | 66 | 34 | 829 |
| 6/27/1984 | 1984 | 6 | 27 | 27 | 53 | 80 | 66.5 | 34.5 | 863.5 |
| 6/28/1984 | 1984 | 6 | 28 | 28 | 54 | 83 | 68.5 | 36.5 | 900 |
| 6/29/1984 | 1984 | 6 | 29 | 29 | 61 | 84 | 72.5 | 40.5 | 940.5 |
| 6/30/1984 | 1984 | 6 | 30 | 30 | 58 | 83 | 70.5 | 38.5 | 979 |
| 7/1/1984 | 1984 | 7 | 1 | 31 | 58 | 79 | 68.5 | 36.5 | 1015.5 |
| 7/2/1984 | 1984 | 7 | 2 | 32 | 55 | 86 | 70.5 | 38.5 | 1054 |
| 7/3/1984 | 1984 | 7 | 3 | 33 | 58 | 87 | 72.5 | 40.5 | 1094.5 |
| 7/4/1984 | 1984 | 7 | 4 | 34 | 56 | 88 | 72 | 40 | 1134.5 |
| 7/5/1984 | 1984 | 7 | 5 | 35 | 59 | 86 | 72.5 | 40.5 | 1175 |
| 7/6/1984 | 1984 | 7 | 6 | 36 | 58 | 85 | 71.5 | 39.5 | 1214.5 |
| 7/7/1984 | 1984 | 7 | 7 | 37 | 50 | 83 | 66.5 | 34.5 | 1249 |
| 7/8/1984 | 1984 | 7 | 8 | 38 | 64 | 84 | 74 | 42 | 1291 |
| 7/9/1984 | 1984 | 7 | 9 | 39 | 59 | 80 | 69.5 | 37.5 | 1328.5 |
| 7/10/1984 | 1984 | 7 | 10 | 40 | 57 | 81 | 69 | 37 | 1365.5 |
| 7/11/1984 | 1984 | 7 | 11 | 41 | 58 | 79 | 68.5 | 36.5 | 1402 |
| 7/12/1984 | 1984 | 7 | 12 | 42 | 55 | 75 | 65 | 33 | 1435 |
| 7/13/1984 | 1984 | 7 | 13 | 43 | 56 | 77 | 66.5 | 34.5 | 1469.5 |
| 7/14/1984 | 1984 | 7 | 14 | 44 | 57 | 82 | 69.5 | 37.5 | 1507 |
| 7/15/1984 | 1984 | 7 | 15 | 45 | 58 | 86 | 72 | 40 | 1547 |
| 7/16/1984 | 1984 | 7 | 16 | 46 | 61 | 83 | 72 | 40 | 1587 |
| 7/17/1984 | 1984 | 7 | 17 | 47 | 52 | 77 | 64.5 | 32.5 | 1619.5 |
| 7/18/1984 | 1984 | 7 | 18 | 48 | 53 | 80 | 66.5 | 34.5 | 1654 |
| 7/19/1984 | 1984 | 7 | 19 | 49 | 56 | 83 | 69.5 | 37.5 | 1691.5 |
| 7/20/1984 | 1984 | 7 | 20 | 50 | 57 | 85 | 71 | 39 | 1730.5 |
| 7/21/1984 | 1984 | 7 | 21 | 51 | 54 | 87 | 70.5 | 38.5 | 1769 |
| 7/22/1984 | 1984 | 7 | 22 | 52 | 55 | 84 | 69.5 | 37.5 | 1806.5 |
| 7/23/1984 | 1984 | 7 | 23 | 53 | 59 | 80 | 69.5 | 37.5 | 1844 |
| 7/24/1984 | 1984 | 7 | 24 | 54 | 56 | 80 | 68 | 36 | 1880 |
| 7/25/1984 | 1984 | 7 | 25 | 55 | 57 | 77 | 67 | 35 | 1915 |
| 7/26/1984 | 1984 | 7 | 26 | 56 | 56 | 75 | 65.5 | 33.5 | 1948.5 |
| 7/27/1984 | 1984 | 7 | 27 | 57 | 55 | 78 | 66.5 | 34.5 | 1983 |
| 7/28/1984 | 1984 | 7 | 28 | 58 | 56 | 80 | 68 | 36 | 2019 |
| 7/29/1984 | 1984 | 7 | 29 | 59 | 59 | 78 | 68.5 | 36.5 | 2055.5 |
| 7/30/1984 | 1984 | 7 | 30 | 60 | 54 | 81 | 67.5 | 35.5 | 2091 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/31/1984 | 1984 | 7 | 31 | 61 | 57 | 82 | 69.5 | 37.5 | 2128.5 |
| 8/1/1984 | 1984 | 8 | 1 | 62 | 59 | 84 | 71.5 | 39.5 | 2168 |
| 8/2/1984 | 1984 | 8 | 2 | 63 | 58 | 81 | 69.5 | 37.5 | 2205.5 |
| 8/3/1984 | 1984 | 8 | 3 | 64 | 56 | 83 | 69.5 | 37.5 | 2243 |
| 8/4/1984 | 1984 | 8 | 4 | 65 | 55 | 82 | 68.5 | 36.5 | 2279.5 |
| 8/5/1984 | 1984 | 8 | 5 | 66 | 54 | 79 | 66.5 | 34.5 | 2314 |
| 8/6/1984 | 1984 | 8 | 6 | 67 | 56 | 76 | 66 | 34 | 2348 |
| 8/7/1984 | 1984 | 8 | 7 | 68 | 54 | 82 | 68 | 36 | 2384 |
| 8/8/1984 | 1984 | 8 | 8 | 69 | 53 | 81 | 67 | 35 | 2419 |
| 8/9/1984 | 1984 | 8 | 9 | 70 | 50 | 79 | 64.5 | 32.5 | 2451.5 |
| 8/10/1984 | 1984 | 8 | 10 | 71 | 54 | 74 | 64 | 32 | 2483.5 |
| 8/11/1984 | 1984 | 8 | 11 | 72 | 51 | 76 | 63.5 | 31.5 | 2515 |
| 8/12/1984 | 1984 | 8 | 12 | 73 | 56 | 79 | 67.5 | 35.5 | 2550.5 |
| 8/13/1984 | 1984 | 8 | 13 | 74 | 55 | 78 | 66.5 | 34.5 | 2585 |
| 8/14/1984 | 1984 | 8 | 14 | 75 | 52 | 79 | 65.5 | 33.5 | 2618.5 |
| 8/15/1984 | 1984 | 8 | 15 | 76 | 56 | 78 | 67 | 35 | 2653.5 |
| 8/16/1984 | 1984 | 8 | 16 | 77 | 55 | 79 | 67 | 35 | 2688.5 |
| 8/17/1984 | 1984 | 8 | 17 | 78 | 53 | 78 | 65.5 | 33.5 | 2722 |
| 8/18/1984 | 1984 | 8 | 18 | 79 | 54 | 79 | 66.5 | 34.5 | 2756.5 |
| 8/19/1984 | 1984 | 8 | 19 | 80 | 57 | 78 | 67.5 | 35.5 | 2792 |
| 8/20/1984 | 1984 | 8 | 20 | 81 | 56 | 77 | 66.5 | 34.5 | 2826.5 |
| 8/21/1984 | 1984 | 8 | 21 | 82 | 57 | 80 | 68.5 | 36.5 | 2863 |
| 8/22/1984 | 1984 | 8 | 22 | 83 | 51 | 82 | 66.5 | 34.5 | 2897.5 |
| 8/23/1984 | 1984 | 8 | 23 | 84 | 55 | 72 | 63.5 | 31.5 | 2929 |
| 8/24/1984 | 1984 | 8 | 24 | 85 | 49 | 69 | 59 | 27 | 2956 |
| 8/25/1984 | 1984 | 8 | 25 | 86 | 52 | 79 | 65.5 | 33.5 | 2989.5 |
| 8/26/1984 | 1984 | 8 | 26 | 87 | 54 | 78 | 66 | 34 | 3023.5 |
| 8/27/1984 | 1984 | 8 | 27 | 88 | 52 | 79 | 65.5 | 33.5 | 3057 |
| 8/28/1984 | 1984 | 8 | 28 | 89 | 58 | 78 | 68 | 36 | 3093 |
| 8/29/1984 | 1984 | 8 | 29 | 90 | 57 | 82 | 69.5 | 37.5 | 3130.5 |
| 8/30/1984 | 1984 | 8 | 30 | 91 | 59 | 84 | 71.5 | 39.5 | 3170 |
| 8/31/1984 | 1984 | 8 | 31 | 92 | 58 | 81 | 69.5 | 37.5 | 3207.5 |
| 9/1/1984 | 1984 | 9 | 1 | 93 | 54 | 74 | 64 | 32 | 3239.5 |
| 9/2/1984 | 1984 | 9 | 2 | 94 | 49 | 78 | 63.5 | 31.5 | 3271 |
| 9/3/1984 | 1984 | 9 | 3 | 95 | 48 | 79 | 63.5 | 31.5 | 3302.5 |
| 9/4/1984 | 1984 | 9 | 4 | 96 | 47 | 72 | 59.5 | 27.5 | 3330 |
| 9/5/1984 | 1984 | 9 | 5 | 97 | 50 | 78 | 64 | 32 | 3362 |
| 9/6/1984 | 1984 | 9 | 6 | 98 | 48 | 78 | 63 | 31 | 3393 |
| 9/7/1984 | 1984 | 9 | 7 | 99 | 54 | 76 | 65 | 33 | 3426 |
| 9/8/1984 | 1984 | 9 | 8 | 100 | 47 | 79 | 63 | 31 | 3457 |
| 9/9/1984 | 1984 | 9 | 9 | 101 | 46 | 80 | 63 | 31 | 3488 |
| 9/10/1984 | 1984 | 9 | 10 | 102 | 55 | 84 | 69.5 | 37.5 | 3525.5 |
| 9/11/1984 | 1984 | 9 | 11 | 103 | 56 | 81 | 68.5 | 36.5 | 3562 |
| 9/12/1984 | 1984 | 9 | 12 | 104 | 50 | 76 | 63 | 31 | 3593 |
| 9/13/1984 | 1984 | 9 | 13 | 105 | 56 | 77 | 66.5 | 34.5 | 3627.5 |
| 9/14/1984 | 1984 | 9 | 14 | 106 | 55 | 80 | 67.5 | 35.5 | 3663 |
| 9/15/1984 | 1984 | 9 | 15 | 107 | 50 | 75 | 62.5 | 30.5 | 3693.5 |
| 9/16/1984 | 1984 | 9 | 16 | 108 | 52 | 70 | 61 | 29 | 3722.5 |
| 9/17/1984 | 1984 | 9 | 17 | 109 | 53 | 65 | 59 | 27 | 3749.5 |
| 9/18/1984 | 1984 | 9 | 18 | 110 | 48 | 72 | 60 | 28 | 3777.5 |
| 9/19/1984 | 1984 | 9 | 19 | 111 | 50 | 75 | 62.5 | 30.5 | 3808 |
| 9/20/1984 | 1984 | 9 | 20 | 112 | 52 | 76 | 64 | 32 | 3840 |
| 9/21/1984 | 1984 | 9 | 21 | 113 | 51 | 73 | 62 | 30 | 3870 |
| 9/22/1984 | 1984 | 9 | 22 | 114 | 49 | 68 | 58.5 | 26.5 | 3896.5 |
| 9/23/1984 | 1984 | 9 | 23 | 115 | 47 | 70 | 58.5 | 26.5 | 3923 |
| 9/24/1984 | 1984 | 9 | 24 | 116 | 52 | 72 | 62 | 30 | 3953 |
| 9/25/1984 | 1984 | 9 | 25 | 117 | 46 | 71 | 58.5 | 26.5 | 3979.5 |
| 9/26/1984 | 1984 | 9 | 26 | 118 | 41 | 58 | 49.5 | 17.5 | 3997 |
| 9/27/1984 | 1984 | 9 | 27 | 119 | 40 | 59 | 49.5 | 17.5 | 4014.5 |
| 9/28/1984 | 1984 | 9 | 28 | 120 | 41 | 63 | 52 | 20 | 4034.5 |
| 9/29/1984 | 1984 | 9 | 29 | 121 | 39 | 64 | 51.5 | 19.5 | 4054 |
| 9/30/1984 | 1984 | 9 | 30 | 122 | 36 | 67 | 51.5 | 19.5 | 4073.5 |
| 10/1/1984 | 1984 | 10 | 1 | 123 | 48 | 65 | 56.5 | 24.5 | 4098 |
| 10/2/1984 | 1984 | 10 | 2 | 124 | 48 | 65 | 56.5 | 24.5 | 4122.5 |
| 10/3/1984 | 1984 | 10 | 3 | 125 | 39 | 63 | 51 | 19 | 4141.5 |
| 10/4/1984 | 1984 | 10 | 4 | 126 | 38 | 62 | 50 | 18 | 4159.5 |
| 10/5/1984 | 1984 | 10 | 5 | 127 | 38 | 60 | 49 | 17 | 4176.5 |
| 10/6/1984 | 1984 | 10 | 6 | 128 | 38 | 59 | 48.5 | 16.5 | 4193 |
| 10/7/1984 | 1984 | 10 | 7 | 129 | 32 | 58 | 45 | 13 | 4206 |
| 10/8/1984 | 1984 | 10 | 8 | 130 | 38 | 63 | 50.5 | 18.5 | 4224.5 |
| 10/9/1984 | 1984 | 10 | 9 | 131 | 38 | 64 | 51 | 19 | 4243.5 |
| 10/10/1984 | 1984 | 10 | 10 | 132 | 43 | 63 | 53 | 21 | 4264.5 |
| 10/11/1984 | 1984 | 10 | 11 | 133 | 42 | 64 | 53 | 21 | 4285.5 |
| 10/12/1984 | 1984 | 10 | 12 | 134 | 41 | 62 | 51.5 | 19.5 | 4305 |
| 10/13/1984 | 1984 | 10 | 13 | 135 | 32 | 55 | 43.5 | 11.5 | 4316.5 |
| 10/14/1984 | 1984 | 10 | 14 | 136 | 30 | 54 | 42 | 10 | 4326.5 |
| 10/15/1984 | 1984 | 10 | 15 | 137 | 30 | 50 | 40 | 8 | 4334.5 |
| 10/16/1984 | 1984 | 10 | 16 | 138 | 28 | 34 | 31 | -1 | 4333.5 |
| 10/17/1984 | 1984 | 10 | 17 | 139 | 28 | 57 | 42.5 | 10.5 | 4344 |
| 10/18/1984 | 1984 | 10 | 18 | 140 | 26 | 52 | 39 | 7 | 4351 |
| 10/19/1984 | 1984 | 10 | 19 | 141 | 27 | 44 | 35.5 | 3.5 | 4354.5 |
| 10/20/1984 | 1984 | 10 | 20 | 142 | 28 | 48 | 38 | 6 | 4360.5 |
| 10/21/1984 | 1984 | 10 | 21 | 143 | 29 | 44 | 36.5 | 4.5 | 4365 |
| 10/22/1984 | 1984 | 10 | 22 | 144 | 28 | 42 | 35 | 3 | 4368 |
| 10/23/1984 | 1984 | 10 | 23 | 145 | 30 | 44 | 37 | 5 | 4373 |
| 10/24/1984 | 1984 | 10 | 24 | 146 | 29 | 37 | 33 | 1 | 4374 |
| 10/25/1984 | 1984 | 10 | 25 | 147 | 27 | 45 | 36 | 4 | 4378 |
| 10/26/1984 | 1984 | 10 | 26 | 148 | 27 | 51 | 39 | 7 | 4385 |
| 10/27/1984 | 1984 | 10 | 27 | 149 | 30 | 52 | 41 | 9 | 4394 |
| 10/28/1984 | 1984 | 10 | 28 | 150 | 31 | 53 | 42 | 10 | 4404 |
| 10/29/1984 | 1984 | 10 | 29 | 151 | 33 | 59 | 46 | 14 | 4418 |
| 10/30/1984 | 1984 | 10 | 30 | 152 | 35 | 62 | 48.5 | 16.5 | 4434.5 |
| 10/31/1984 | 1984 | 10 | 31 | 153 | 38 | 60 | 49 | 17 | 4451.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/1/1984 | 1984 | 11 | 1 | 154 | 32 | 55 | 43.5 | 11.5 | 4463 |
| 11/2/1984 | 1984 | 11 | 2 | 155 | 31 | 58 | 44.5 | 12.5 | 4475.5 |
| 11/3/1984 | 1984 | 11 | 3 | 156 | 32 | 61 | 46.5 | 14.5 | 4490 |
| 11/4/1984 | 1984 | 11 | 4 | 157 | 33 | 57 | 45 | 13 | 4503 |
| 11/5/1984 | 1984 | 11 | 5 | 158 | 30 | 61 | 45.5 | 13.5 | 4516.5 |
| 11/6/1984 | 1984 | 11 | 6 | 159 | 35 | 60 | 47.5 | 15.5 | 4532 |
| 11/7/1984 | 1984 | 11 | 7 | 160 | 36 | 61 | 48.5 | 16.5 | 4548.5 |
| 11/8/1984 | 1984 | 11 | 8 | 161 | 37 | 59 | 48 | 16 | 4564.5 |
| 11/9/1984 | 1984 | 11 | 9 | 162 | 31 | 55 | 43 | 11 | 4575.5 |
| 11/10/1984 | 1984 | 11 | 10 | 163 | 21 | 49 | 35 | 3 | 4578.5 |
| 11/11/1984 | 1984 | 11 | 11 | 164 | 29 | 56 | 42.5 | 10.5 | 4589 |
| 11/12/1984 | 1984 | 11 | 12 | 165 | 30 | 61 | 45.5 | 13.5 | 4602.5 |
| 11/13/1984 | 1984 | 11 | 13 | 166 | 33 | 59 | 46 | 14 | 4616.5 |
| 11/14/1984 | 1984 | 11 | 14 | 167 | 30 | 57 | 43.5 | 11.5 | 4628 |
| 11/15/1984 | 1984 | 11 | 15 | 168 | 29 | 55 | 42 | 10 | 4638 |
| 11/16/1984 | 1984 | 11 | 16 | 169 | 28 | 54 | 41 | 9 | 4647 |
| 11/17/1984 | 1984 | 11 | 17 | 170 | 32 | 51 | 41.5 | 9.5 | 4656.5 |
| 11/18/1984 | 1984 | 11 | 18 | 171 | 30 | 42 | 36 | 4 | 4660.5 |
| 11/19/1984 | 1984 | 11 | 19 | 172 | 24 | 44 | 34 | 2 | 4662.5 |
| 11/20/1984 | 1984 | 11 | 20 | 173 | 23 | 45 | 34 | 2 | 4664.5 |
| 11/21/1984 | 1984 | 11 | 21 | 174 | 20 | 52 | 36 | 4 | 4668.5 |
| 11/22/1984 | 1984 | 11 | 22 | 175 | 21 | 42 | 31.5 | -0.5 | 4668 |
| 11/23/1984 | 1984 | 11 | 23 | 176 | 27 | 48 | 37.5 | 5.5 | 4673.5 |
| 11/24/1984 | 1984 | 11 | 24 | 177 | 30 | 47 | 38.5 | 6.5 | 4680 |
| 11/25/1984 | 1984 | 11 | 25 | 178 | 26 | 39 | 32.5 | 0.5 | 4680.5 |
| 11/26/1984 | 1984 | 11 | 26 | 179 | 16 | 31 | 23.5 | -8.5 | 4672 |
| 11/27/1984 | 1984 | 11 | 27 | 180 | 8 | 30 | 19 | -13 | 4659 |
| 11/28/1984 | 1984 | 11 | 28 | 181 | 10 | 39 | 24.5 | -7.5 | 4651.5 |
| 11/29/1984 | 1984 | 11 | 29 | 182 | 12 | 40 | 26 | -6 | 4645.5 |
| 11/30/1984 | 1984 | 11 | 30 | 183 | 19 | 34 | 26.5 | -5.5 | 4640 |
| 12/1/1984 | 1984 | 12 | 1 | 184 | 20 | 40 | 30 | -2 | 4638 |
| 12/2/1984 | 1984 | 12 | 2 | 185 | 21 | 40 | 30.5 | -1.5 | 4636.5 |
| 12/3/1984 | 1984 | 12 | 3 | 186 | 21 | 44 | 32.5 | 0.5 | 4637 |
| 12/4/1984 | 1984 | 12 | 4 | 187 | 22 | 42 | 32 | 0 | 4637 |
| 12/5/1984 | 1984 | 12 | 5 | 188 | 21 | 40 | 30.5 | -1.5 | 4635.5 |
| 12/6/1984 | 1984 | 12 | 6 | 189 | 16 | 41 | 28.5 | -3.5 | 4632 |
| 12/7/1984 | 1984 | 12 | 7 | 190 | 22 | 51 | 36.5 | 4.5 | 4636.5 |
| 12/8/1984 | 1984 | 12 | 8 | 191 | 25 | 50 | 37.5 | 5.5 | 4642 |
| 12/9/1984 | 1984 | 12 | 9 | 192 | 26 | 40 | 33 | 1 | 4643 |
| 12/10/1984 | 1984 | 12 | 10 | 193 | 23 | 53 | 38 | 6 | 4649 |
| 12/11/1984 | 1984 | 12 | 11 | 194 | 32 | 52 | 42 | 10 | 4659 |
| 12/12/1984 | 1984 | 12 | 12 | 195 | 32 | 41 | 36.5 | 4.5 | 4663.5 |
| 12/13/1984 | 1984 | 12 | 13 | 196 | 30 | 41 | 35.5 | 3.5 | 4667 |
| 12/14/1984 | 1984 | 12 | 14 | 197 | 14 | 33 | 23.5 | -8.5 | 4658.5 |
| 12/15/1984 | 1984 | 12 | 15 | 198 | 16 | 32 | 24 | -8 | 4650.5 |
| 12/16/1984 | 1984 | 12 | 16 | 199 | 14 | 39 | 26.5 | -5.5 | 4645 |
| 12/17/1984 | 1984 | 12 | 17 | 200 | 15 | 39 | 27 | -5 | 4640 |
| 12/18/1984 | 1984 | 12 | 18 | 201 | 16 | 40 | 28 | -4 | 4636 |
| 12/19/1984 | 1984 | 12 | 19 | 202 | 17 | 46 | 31.5 | -0.5 | 4635.5 |
| 12/20/1984 | 1984 | 12 | 20 | 203 | 31 | 42 | 36.5 | 4.5 | 4640 |
| 12/21/1984 | 1984 | 12 | 21 | 204 | 19 | 35 | 27 | -5 | 4635 |
| 12/22/1984 | 1984 | 12 | 22 | 205 | 12 | 33 | 22.5 | -9.5 | 4625.5 |
| 12/23/1984 | 1984 | 12 | 23 | 206 | 15 | 38 | 26.5 | -5.5 | 4620 |
| 12/24/1984 | 1984 | 12 | 24 | 207 | 15 | 38 | 26.5 | -5.5 | 4614.5 |
| 12/25/1984 | 1984 | 12 | 25 | 208 | 17 | 37 | 27 | -5 | 4609.5 |
| 12/26/1984 | 1984 | 12 | 26 | 209 | 19 | 40 | 29.5 | -2.5 | 4607 |
| 12/27/1984 | 1984 | 12 | 27 | 210 | 20 | 36 | 28 | -4 | 4603 |
| 12/28/1984 | 1984 | 12 | 28 | 211 | 35 | 49 | 42 | 10 | 4613 |
| 12/29/1984 | 1984 | 12 | 29 | 212 | 28 | 47 | 37.5 | 5.5 | 4618.5 |
| 12/30/1984 | 1984 | 12 | 30 | 213 | 21 | 39 | 30 | -2 | 4616.5 |
| 12/31/1984 | 1984 | 12 | 31 | 214 | 12 | 37 | 24.5 | -7.5 | 4609 |
| 1/1/1985 | 1985 | 1 | 1 | 215 | 17 | 38 | 27.5 | -4.5 | 4604.5 |
| 1/2/1985 | 1985 | 1 | 2 | 216 | 16 | 30 | 23 | -9 | 4595.5 |
| 1/3/1985 | 1985 | 1 | 3 | 217 | 10 | 36 | 23 | -9 | 4586.5 |
| 1/4/1985 | 1985 | 1 | 4 | 218 | 13 | 39 | 26 | -6 | 4580.5 |
| 1/5/1985 | 1985 | 1 | 5 | 219 | 19 | 40 | 29.5 | -2.5 | 4578 |
| 1/6/1985 | 1985 | 1 | 6 | 220 | 20 | 43 | 31.5 | -0.5 | 4577.5 |
| 1/7/1985 | 1985 | 1 | 7 | 221 | 21 | 46 | 33.5 | 1.5 | 4579 |
| 1/8/1985 | 1985 | 1 | 8 | 222 | 20 | 44 | 32 | 0 | 4579 |
| 1/9/1985 | 1985 | 1 | 9 | 223 | 17 | 38 | 27.5 | -4.5 | 4574.5 |
| 1/10/1985 | 1985 | 1 | 10 | 224 | 11 | 39 | 25 | -7 | 4567.5 |
| 1/11/1985 | 1985 | 1 | 11 | 225 | 13 | 27 | 20 | -12 | 4555.5 |
| 1/12/1985 | 1985 | 1 | 12 | 226 | 7 | 31 | 19 | -13 | 4542.5 |
| 1/13/1985 | 1985 | 1 | 13 | 227 | 11 | 37 | 24 | -8 | 4534.5 |
| 1/14/1985 | 1985 | 1 | 14 | 228 | 13 | 40 | 26.5 | -5.5 | 4529 |
| 1/15/1985 | 1985 | 1 | 15 | 229 | 16 | 42 | 29 | -3 | 4526 |
| 1/16/1985 | 1985 | 1 | 16 | 230 | 15 | 38 | 26.5 | -5.5 | 4520.5 |
| 1/17/1985 | 1985 | 1 | 17 | 231 | 20 | 47 | 33.5 | 1.5 | 4522 |
| 1/18/1985 | 1985 | 1 | 18 | 232 | 18 | 45 | 31.5 | -0.5 | 4521.5 |
| 1/19/1985 | 1985 | 1 | 19 | 233 | 17 | 41 | 29 | -3 | 4518.5 |
| 1/20/1985 | 1985 | 1 | 20 | 234 | 19 | 41 | 30 | -2 | 4516.5 |
| 1/21/1985 | 1985 | 1 | 21 | 235 | 16 | 40 | 28 | -4 | 4512.5 |
| 1/22/1985 | 1985 | 1 | 22 | 236 | 15 | 39 | 27 | -5 | 4507.5 |
| 1/23/1985 | 1985 | 1 | 23 | 237 | 16 | 38 | 27 | -5 | 4502.5 |
| 1/24/1985 | 1985 | 1 | 24 | 238 | 19 | 39 | 29 | -3 | 4499.5 |
| 1/25/1985 | 1985 | 1 | 25 | 239 | 19 | 38 | 28.5 | -3.5 | 4496 |
| 1/26/1985 | 1985 | 1 | 26 | 240 | 20 | 37 | 28.5 | -3.5 | 4492.5 |
| 1/27/1985 | 1985 | 1 | 27 | 241 | 14 | 35 | 24.5 | -7.5 | 4485 |
| 1/28/1985 | 1985 | 1 | 28 | 242 | 15 | 33 | 24 | -8 | 4477 |
| 1/29/1985 | 1985 | 1 | 29 | 243 | 19 | 32 | 25.5 | -6.5 | 4470.5 |
| 1/30/1985 | 1985 | 1 | 30 | 244 | 5 | 27 | 16 | -16 | 4454.5 |
| 1/31/1985 | 1985 | 1 | 31 | 245 | 6 | 27 | 16.5 | -15.5 | 4439 |
| 2/1/1985 | 1985 | 2 | 1 | 246 | -5 | 14 | 4.5 | -27.5 | 4411.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/2/1985 | 1985 | 2 | 2 | 247 | -4 | 19 | 7.5 | -24.5 | 4387 |
| 2/3/1985 | 1985 | 2 | 3 | 248 | 10 | 20 | 15 | -17 | 4370 |
| 2/4/1985 | 1985 | 2 | 4 | 249 | -3 | 20 | 8.5 | -23.5 | 4346.5 |
| 2/5/1985 | 1985 | 2 | 5 | 250 | -4 | 22 | 9 | -23 | 4323.5 |
| 2/6/1985 | 1985 | 2 | 6 | 251 | 10 | 21 | 15.5 | -16.5 | 4307 |
| 2/7/1985 | 1985 | 2 | 7 | 252 | 8 | 30 | 19 | -13 | 4294 |
| 2/8/1985 | 1985 | 2 | 8 | 253 | 9 | 32 | 20.5 | -11.5 | 4282.5 |
| 2/9/1985 | 1985 | 2 | 9 | 254 | 9 | 35 | 22 | -10 | 4272.5 |
| 2/10/1985 | 1985 | 2 | 10 | 255 | 5 | 36 | 20.5 | -11.5 | 4261 |
| 2/11/1985 | 1985 | 2 | 11 | 256 | 7 | 36 | 21.5 | -10.5 | 4250.5 |
| 2/12/1985 | 1985 | 2 | 12 | 257 | 19 | 40 | 29.5 | -2.5 | 4248 |
| 2/13/1985 | 1985 | 2 | 13 | 258 | 18 | 42 | 30 | -2 | 4246 |
| 2/14/1985 | 1985 | 2 | 14 | 259 | 20 | 43 | 31.5 | -0.5 | 4245.5 |
| 2/15/1985 | 1985 | 2 | 15 | 260 | 12 | 45 | 28.5 | -3.5 | 4242 |
| 2/16/1985 | 1985 | 2 | 16 | 261 | 18 | 45 | 31.5 | -0.5 | 4241.5 |
| 2/17/1985 | 1985 | 2 | 17 | 262 | 13 | 43 | 28 | -4 | 4237.5 |
| 2/18/1985 | 1985 | 2 | 18 | 263 | 13 | 45 | 29 | -3 | 4234.5 |
| 2/19/1985 | 1985 | 2 | 19 | 264 | 20 | 49 | 34.5 | 2.5 | 4237 |
| 2/20/1985 | 1985 | 2 | 20 | 265 | 13 | 50 | 31.5 | -0.5 | 4236.5 |
| 2/21/1985 | 1985 | 2 | 21 | 266 | 14 | 51 | 32.5 | 0.5 | 4237 |
| 2/22/1985 | 1985 | 2 | 22 | 267 | 18 | 45 | 31.5 | -0.5 | 4236.5 |
| 2/23/1985 | 1985 | 2 | 23 | 268 | 15 | 41 | 28 | -4 | 4232.5 |
| 2/24/1985 | 1985 | 2 | 24 | 269 | 15 | 40 | 27.5 | -4.5 | 4228 |
| 2/25/1985 | 1985 | 2 | 25 | 270 | 13 | 40 | 26.5 | -5.5 | 4222.5 |
| 2/26/1985 | 1985 | 2 | 26 | 271 | 15 | 41 | 28 | -4 | 4218.5 |
| 2/27/1985 | 1985 | 2 | 27 | 272 | 18 | 42 | 30 | -2 | 4216.5 |
| 2/28/1985 | 1985 | 2 | 28 | 273 | 19 | 45 | 32 | 0 | 4216.5 |
| 3/1/1985 | 1985 | 3 | 1 | 274 | 31 | 52 | 41.5 | 9.5 | 4226 |
| 3/2/1985 | 1985 | 3 | 2 | 275 | 32 | 50 | 41 | 9 | 4235 |
| 3/3/1985 | 1985 | 3 | 3 | 276 | 20 | 52 | 36 | 4 | 4239 |
| 3/4/1985 | 1985 | 3 | 4 | 277 | 18 | 38 | 28 | -4 | 4235 |
| 3/5/1985 | 1985 | 3 | 5 | 278 | 21 | 54 | 37.5 | 5.5 | 4240.5 |
| 3/6/1985 | 1985 | 3 | 6 | 279 | 25 | 54 | 39.5 | 7.5 | 4248 |
| 3/7/1985 | 1985 | 3 | 7 | 280 | 26 | 52 | 39 | 7 | 4255 |
| 3/8/1985 | 1985 | 3 | 8 | 281 | 29 | 54 | 41.5 | 9.5 | 4264.5 |
| 3/9/1985 | 1985 | 3 | 9 | 282 | 30 | 58 | 44 | 12 | 4276.5 |
| 3/10/1985 | 1985 | 3 | 10 | 283 | 38 | 60 | 49 | 17 | 4293.5 |
| 3/11/1985 | 1985 | 3 | 11 | 284 | 41 | 59 | 50 | 18 | 4311.5 |
| 3/12/1985 | 1985 | 3 | 12 | 285 | 19 | 46 | 32.5 | 0.5 | 4312 |
| 3/13/1985 | 1985 | 3 | 13 | 286 | 20 | 50 | 35 | 3 | 4315 |
| 3/14/1985 | 1985 | 3 | 14 | 287 | 26 | 46 | 36 | 4 | 4319 |
| 3/15/1985 | 1985 | 3 | 15 | 288 | 31 | 45 | 38 | 6 | 4325 |
| 3/16/1985 | 1985 | 3 | 16 | 289 | 25 | 46 | 35.5 | 3.5 | 4328.5 |
| 3/17/1985 | 1985 | 3 | 17 | 290 | 26 | 52 | 39 | 7 | 4335.5 |
| 3/18/1985 | 1985 | 3 | 18 | 291 | 29 | 52 | 40.5 | 8.5 | 4344 |
| 3/19/1985 | 1985 | 3 | 19 | 292 | 28 | 53 | 40.5 | 8.5 | 4352.5 |
| 3/20/1985 | 1985 | 3 | 20 | 293 | 25 | 49 | 37 | 5 | 4357.5 |
| 3/21/1985 | 1985 | 3 | 21 | 294 | 29 | 52 | 40.5 | 8.5 | 4366 |
| 3/22/1985 | 1985 | 3 | 22 | 295 | 20 | 53 | 36.5 | 4.5 | 4370.5 |
| 3/23/1985 | 1985 | 3 | 23 | 296 | 19 | 54 | 36.5 | 4.5 | 4375 |
| 3/24/1985 | 1985 | 3 | 24 | 297 | 30 | 60 | 45 | 13 | 4388 |
| 3/25/1985 | 1985 | 3 | 25 | 298 | 31 | 65 | 48 | 16 | 4404 |
| 3/26/1985 | 1985 | 3 | 26 | 299 | 35 | 65 | 50 | 18 | 4422 |
| 3/27/1985 | 1985 | 3 | 27 | 300 | 39 | 60 | 49.5 | 17.5 | 4439.5 |
| 3/28/1985 | 1985 | 3 | 28 | 301 | 38 | 57 | 47.5 | 15.5 | 4455 |
| 3/29/1985 | 1985 | 3 | 29 | 302 | 41 | 56 | 48.5 | 16.5 | 4471.5 |
| 3/30/1985 | 1985 | 3 | 30 | 303 | 25 | 54 | 39.5 | 7.5 | 4479 |
| 3/31/1985 | 1985 | 3 | 31 | 304 | 21 | 33 | 27 | -5 | 4474 |
| 4/1/1985 | 1985 | 4 | 1 | 305 | 28 | 57 | 42.5 | 10.5 | 4484.5 |
| 4/2/1985 | 1985 | 4 | 2 | 306 | 30 | 66 | 48 | 16 | 4500.5 |
| 4/3/1985 | 1985 | 4 | 3 | 307 | 32 | 66 | 49 | 17 | 4517.5 |
| 4/4/1985 | 1985 | 4 | 4 | 308 | 35 | 65 | 50 | 18 | 4535.5 |
| 4/5/1985 | 1985 | 4 | 5 | 309 | 29 | 64 | 46.5 | 14.5 | 4550 |
| 4/6/1985 | 1985 | 4 | 6 | 310 | 30 | 62 | 46 | 14 | 4564 |
| 4/7/1985 | 1985 | 4 | 7 | 311 | 33 | 60 | 46.5 | 14.5 | 4578.5 |
| 4/8/1985 | 1985 | 4 | 8 | 312 | 37 | 68 | 52.5 | 20.5 | 4599 |
| 4/9/1985 | 1985 | 4 | 9 | 313 | 40 | 67 | 53.5 | 21.5 | 4620.5 |
| 4/10/1985 | 1985 | 4 | 10 | 314 | 39 | 68 | 53.5 | 21.5 | 4642 |
| 4/11/1985 | 1985 | 4 | 11 | 315 | 38 | 69 | 53.5 | 21.5 | 4663.5 |
| 4/12/1985 | 1985 | 4 | 12 | 316 | 39 | 70 | 54.5 | 22.5 | 4686 |
| 4/13/1985 | 1985 | 4 | 13 | 317 | 37 | 69 | 53 | 21 | 4707 |
| 4/14/1985 | 1985 | 4 | 14 | 318 | 38 | 68 | 53 | 21 | 4728 |
| 4/15/1985 | 1985 | 4 | 15 | 319 | 36 | 72 | 54 | 22 | 4750 |
| 4/16/1985 | 1985 | 4 | 16 | 320 | 40 | 73 | 56.5 | 24.5 | 4774.5 |
| 4/17/1985 | 1985 | 4 | 17 | 321 | 42 | 74 | 58 | 26 | 4800.5 |
| 4/18/1985 | 1985 | 4 | 18 | 322 | 45 | 70 | 57.5 | 25.5 | 4826 |
| 4/19/1985 | 1985 | 4 | 19 | 323 | 31 | 69 | 50 | 18 | 4844 |
| 4/20/1985 | 1985 | 4 | 20 | 324 | 30 | 66 | 48 | 16 | 4860 |
| 4/21/1985 | 1985 | 4 | 21 | 325 | 32 | 64 | 48 | 16 | 4876 |
| 4/22/1985 | 1985 | 4 | 22 | 326 | 41 | 65 | 53 | 21 | 4897 |
| 4/23/1985 | 1985 | 4 | 23 | 327 | 39 | 46 | 42.5 | 10.5 | 4907.5 |
| 4/24/1985 | 1985 | 4 | 24 | 328 | 28 | 59 | 43.5 | 11.5 | 4919 |
| 4/25/1985 | 1985 | 4 | 25 | 329 | 33 | 66 | 49.5 | 17.5 | 4936.5 |
| 4/26/1985 | 1985 | 4 | 26 | 330 | 39 | 65 | 52 | 20 | 4956.5 |
| 4/27/1985 | 1985 | 4 | 27 | 331 | 32 | 54 | 43 | 11 | 4967.5 |
| 4/28/1985 | 1985 | 4 | 28 | 332 | 34 | 52 | 43 | 11 | 4978.5 |
| 4/29/1985 | 1985 | 4 | 29 | 333 | 33 | 50 | 41.5 | 9.5 | 4988 |
| 4/30/1985 | 1985 | 4 | 30 | 334 | 32 | 60 | 46 | 14 | 5002 |
| 5/1/1985 | 1985 | 5 | 1 | 335 | 41 | 72 | 56.5 | 24.5 | 5026.5 |
| 5/2/1985 | 1985 | 5 | 2 | 336 | 36 | 75 | 55.5 | 23.5 | 5050 |
| 5/3/1985 | 1985 | 5 | 3 | 337 | 39 | 69 | 54 | 22 | 5072 |
| 5/4/1985 | 1985 | 5 | 4 | 338 | 40 | 70 | 55 | 23 | 5095 |
| 5/5/1985 | 1985 | 5 | 5 | 339 | 43 | 69 | 56 | 24 | 5119 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/6/1985 | 1985 | 5 | 6 | 340 | 45 | 70 | 57.5 | 25.5 | 5144.5 |
| 5/7/1985 | 1985 | 5 | 7 | 341 | 41 | 71 | 56 | 24 | 5168.5 |
| 5/8/1985 | 1985 | 5 | 8 | 342 | 48 | 74 | 61 | 29 | 5197.5 |
| 5/9/1985 | 1985 | 5 | 9 | 343 | 50 | 75 | 62.5 | 30.5 | 5228 |
| 5/10/1985 | 1985 | 5 | 10 | 344 | 54 | 69 | 61.5 | 29.5 | 5257.5 |
| 5/11/1985 | 1985 | 5 | 11 | 345 | 46 | 67 | 56.5 | 24.5 | 5282 |
| 5/12/1985 | 1985 | 5 | 12 | 346 | 35 | 63 | 49 | 17 | 5299 |
| 5/13/1985 | 1985 | 5 | 13 | 347 | 32 | 58 | 45 | 13 | 5312 |
| 5/14/1985 | 1985 | 5 | 14 | 348 | 30 | 66 | 48 | 16 | 5328 |
| 5/15/1985 | 1985 | 5 | 15 | 349 | 38 | 75 | 56.5 | 24.5 | 5352.5 |
| 5/16/1985 | 1985 | 5 | 16 | 350 | 41 | 74 | 57.5 | 25.5 | 5378 |
| 5/17/1985 | 1985 | 5 | 17 | 351 | 49 | 70 | 59.5 | 27.5 | 5405.5 |
| 5/18/1985 | 1985 | 5 | 18 | 352 | 48 | 69 | 58.5 | 26.5 | 5432 |
| 5/19/1985 | 1985 | 5 | 19 | 353 | 41 | 69 | 55 | 23 | 5455 |
| 5/20/1985 | 1985 | 5 | 20 | 354 | 40 | 60 | 50 | 18 | 5473 |
| 5/21/1985 | 1985 | 5 | 21 | 355 | 41 | 65 | 53 | 21 | 5494 |
| 5/22/1985 | 1985 | 5 | 22 | 356 | 46 | 74 | 60 | 28 | 5522 |
| 5/23/1985 | 1985 | 5 | 23 | 357 | 45 | 79 | 62 | 30 | 5552 |
| 5/24/1985 | 1985 | 5 | 24 | 358 | 46 | 78 | 62 | 30 | 5582 |
| 5/25/1985 | 1985 | 5 | 25 | 359 | 45 | 77 | 61 | 29 | 5611 |
| 5/26/1985 | 1985 | 5 | 26 | 360 | 40 | 76 | 58 | 26 | 5637 |
| 5/27/1985 | 1985 | 5 | 27 | 361 | 46 | 79 | 62.5 | 30.5 | 5667.5 |
| 5/28/1985 | 1985 | 5 | 28 | 362 | 52 | 81 | 66.5 | 34.5 | 5702 |
| 5/29/1985 | 1985 | 5 | 29 | 363 | 50 | 80 | 65 | 33 | 5735 |
| 5/30/1985 | 1985 | 5 | 30 | 364 | 50 | 76 | 63 | 31 | 5766 |
| 5/31/1985 | 1985 | 5 | 31 | 365 | 47 | 70 | 58.5 | 26.5 | 5792.5 |
| 6/1/1985 | 1985 | 6 | 1 | 1 | 41 | 75 | 58 | 26 | 26 |
| 6/2/1985 | 1985 | 6 | 2 | 2 | 40 | 79 | 59.5 | 27.5 | 53.5 |
| 6/3/1985 | 1985 | 6 | 3 | 3 | 46 | 73 | 59.5 | 27.5 | 81 |
| 6/4/1985 | 1985 | 6 | 4 | 4 | 42 | 70 | 56 | 24 | 105 |
| 6/5/1985 | 1985 | 6 | 5 | 5 | 42 | 71 | 56.5 | 24.5 | 129.5 |
| 6/6/1985 | 1985 | 6 | 6 | 6 | 46 | 84 | 65 | 33 | 162.5 |
| 6/7/1985 | 1985 | 6 | 7 | 7 | 56 | 92 | 74 | 42 | 204.5 |
| 6/8/1985 | 1985 | 6 | 8 | 8 | 58 | 93 | 75.5 | 43.5 | 248 |
| 6/9/1985 | 1985 | 6 | 9 | 9 | 56 | 86 | 71 | 39 | 287 |
| 6/10/1985 | 1985 | 6 | 10 | 10 | 55 | 88 | 71.5 | 39.5 | 326.5 |
| 6/11/1985 | 1985 | 6 | 11 | 11 | 53 | 87 | 70 | 38 | 364.5 |
| 6/12/1985 | 1985 | 6 | 12 | 12 | 50 | 85 | 67.5 | 35.5 | 400 |
| 6/13/1985 | 1985 | 6 | 13 | 13 | 52 | 86 | 69 | 37 | 437 |
| 6/14/1985 | 1985 | 6 | 14 | 14 | 60 | 87 | 73.5 | 41.5 | 478.5 |
| 6/15/1985 | 1985 | 6 | 15 | 15 | 57 | 91 | 74 | 42 | 520.5 |
| 6/16/1985 | 1985 | 6 | 16 | 16 | 56 | 90 | 73 | 41 | 561.5 |
| 6/17/1985 | 1985 | 6 | 17 | 17 | 55 | 88 | 71.5 | 39.5 | 601 |
| 6/18/1985 | 1985 | 6 | 18 | 18 | 51 | 83 | 67 | 35 | 636 |
| 6/19/1985 | 1985 | 6 | 19 | 19 | 55 | 84 | 69.5 | 37.5 | 673.5 |
| 6/20/1985 | 1985 | 6 | 20 | 20 | 52 | 86 | 69 | 37 | 710.5 |
| 6/21/1985 | 1985 | 6 | 21 | 21 | 57 | 89 | 73 | 41 | 751.5 |
| 6/22/1985 | 1985 | 6 | 22 | 22 | 56 | 86 | 71 | 39 | 790.5 |
| 6/23/1985 | 1985 | 6 | 23 | 23 | 53 | 86 | 69.5 | 37.5 | 828 |
| 6/24/1985 | 1985 | 6 | 24 | 24 | 57 | 85 | 71 | 39 | 867 |
| 6/25/1985 | 1985 | 6 | 25 | 25 | 51 | 80 | 65.5 | 33.5 | 900.5 |
| 6/26/1985 | 1985 | 6 | 26 | 26 | 40 | 81 | 60.5 | 28.5 | 929 |
| 6/27/1985 | 1985 | 6 | 27 | 27 | 44 | 81 | 62.5 | 30.5 | 959.5 |
| 6/28/1985 | 1985 | 6 | 28 | 28 | 50 | 88 | 69 | 37 | 996.5 |
| 6/29/1985 | 1985 | 6 | 29 | 29 | 51 | 87 | 69 | 37 | 1033.5 |
| 6/30/1985 | 1985 | 6 | 30 | 30 | 58 | 86 | 72 | 40 | 1073.5 |
| 7/1/1985 | 1985 | 7 | 1 | 31 | 53 | 90 | 71.5 | 39.5 | 1113 |
| 7/2/1985 | 1985 | 7 | 2 | 32 | 52 | 88 | 70 | 38 | 1151 |
| 7/3/1985 | 1985 | 7 | 3 | 33 | 49 | 86 | 67.5 | 35.5 | 1186.5 |
| 7/4/1985 | 1985 | 7 | 4 | 34 | 59 | 93 | 76 | 44 | 1230.5 |
| 7/5/1985 | 1985 | 7 | 5 | 35 | 57 | 94 | 75.5 | 43.5 | 1274 |
| 7/6/1985 | 1985 | 7 | 6 | 36 | 59 | 93 | 76 | 44 | 1318 |
| 7/7/1985 | 1985 | 7 | 7 | 37 | 61 | 94 | 77.5 | 45.5 | 1363.5 |
| 7/8/1985 | 1985 | 7 | 8 | 38 | 63 | 90 | 76.5 | 44.5 | 1408 |
| 7/9/1985 | 1985 | 7 | 9 | 39 | 59 | 89 | 74 | 42 | 1450 |
| 7/10/1985 | 1985 | 7 | 10 | 40 | 63 | 90 | 76.5 | 44.5 | 1494.5 |
| 7/11/1985 | 1985 | 7 | 11 | 41 | 55 | 86 | 70.5 | 38.5 | 1533 |
| 7/12/1985 | 1985 | 7 | 12 | 42 | 58 | 91 | 74.5 | 42.5 | 1575.5 |
| 7/13/1985 | 1985 | 7 | 13 | 43 | 59 | 93 | 76 | 44 | 1619.5 |
| 7/14/1985 | 1985 | 7 | 14 | 44 | 58 | 90 | 74 | 42 | 1661.5 |
| 7/15/1985 | 1985 | 7 | 15 | 45 | 58 | 84 | 71 | 39 | 1700.5 |
| 7/16/1985 | 1985 | 7 | 16 | 46 | 54 | 87 | 70.5 | 38.5 | 1739 |
| 7/17/1985 | 1985 | 7 | 17 | 47 | 57 | 85 | 71 | 39 | 1778 |
| 7/18/1985 | 1985 | 7 | 18 | 48 | 55 | 89 | 72 | 40 | 1818 |
| 7/19/1985 | 1985 | 7 | 19 | 49 | 55 | 82 | 68.5 | 36.5 | 1854.5 |
| 7/20/1985 | 1985 | 7 | 20 | 50 | 54 | 83 | 68.5 | 36.5 | 1891 |
| 7/21/1985 | 1985 | 7 | 21 | 51 | 55 | 79 | 67 | 35 | 1926 |
| 7/22/1985 | 1985 | 7 | 22 | 52 | 54 | 82 | 68 | 36 | 1962 |
| 7/23/1985 | 1985 | 7 | 23 | 53 | 55 | 77 | 66 | 34 | 1996 |
| 7/24/1985 | 1985 | 7 | 24 | 54 | 53 | 79 | 66 | 34 | 2030 |
| 7/25/1985 | 1985 | 7 | 25 | 55 | 50 | 80 | 65 | 33 | 2063 |
| 7/26/1985 | 1985 | 7 | 26 | 56 | 51 | 81 | 66 | 34 | 2097 |
| 7/27/1985 | 1985 | 7 | 27 | 57 | 52 | 74 | 63 | 31 | 2128 |
| 7/28/1985 | 1985 | 7 | 28 | 58 | 58 | 73 | 65.5 | 33.5 | 2161.5 |
| 7/29/1985 | 1985 | 7 | 29 | 59 | 56 | 75 | 65.5 | 33.5 | 2195 |
| 7/30/1985 | 1985 | 7 | 30 | 60 | 53 | 76 | 64.5 | 32.5 | 2227.5 |
| 7/31/1985 | 1985 | 7 | 31 | 61 | 52 | 79 | 65.5 | 33.5 | 2261 |
| 8/1/1985 | 1985 | 8 | 1 | 62 | 53 | 78 | 65.5 | 33.5 | 2294.5 |
| 8/2/1985 | 1985 | 8 | 2 | 63 | 54 | 69 | 61.5 | 29.5 | 2324 |
| 8/3/1985 | 1985 | 8 | 3 | 64 | 40 | 70 | 55 | 23 | 2347 |
| 8/4/1985 | 1985 | 8 | 4 | 65 | 51 | 79 | 65 | 33 | 2380 |
| 8/5/1985 | 1985 | 8 | 5 | 66 | 55 | 85 | 70 | 38 | 2418 |
| 8/6/1985 | 1985 | 8 | 6 | 67 | 58 | 85 | 71.5 | 39.5 | 2457.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/7/1985 | 1985 | 8 | 7 | 68 | 59 | 87 | 73 | 41 | 2498.5 |
| 8/8/1985 | 1985 | 8 | 8 | 69 | 58 | 83 | 70.5 | 38.5 | 2537 |
| 8/9/1985 | 1985 | 8 | 9 | 70 | 55 | 81 | 68 | 36 | 2573 |
| 8/10/1985 | 1985 | 8 | 10 | 71 | 57 | 80 | 68.5 | 36.5 | 2609.5 |
| 8/11/1985 | 1985 | 8 | 11 | 72 | 50 | 74 | 62 | 30 | 2639.5 |
| 8/12/1985 | 1985 | 8 | 12 | 73 | 55 | 77 | 66 | 34 | 2673.5 |
| 8/13/1985 | 1985 | 8 | 13 | 74 | 46 | 81 | 63.5 | 31.5 | 2705 |
| 8/14/1985 | 1985 | 8 | 14 | 75 | 50 | 81 | 65.5 | 33.5 | 2738.5 |
| 8/15/1985 | 1985 | 8 | 15 | 76 | 54 | 82 | 68 | 36 | 2774.5 |
| 8/16/1985 | 1985 | 8 | 16 | 77 | 55 | 83 | 69 | 37 | 2811.5 |
| 8/17/1985 | 1985 | 8 | 17 | 78 | 53 | 80 | 66.5 | 34.5 | 2846 |
| 8/18/1985 | 1985 | 8 | 18 | 79 | 52 | 80 | 66 | 34 | 2880 |
| 8/19/1985 | 1985 | 8 | 19 | 80 | 53 | 85 | 69 | 37 | 2917 |
| 8/20/1985 | 1985 | 8 | 20 | 81 | 57 | 86 | 71.5 | 39.5 | 2956.5 |
| 8/21/1985 | 1985 | 8 | 21 | 82 | 52 | 80 | 66 | 34 | 2990.5 |
| 8/22/1985 | 1985 | 8 | 22 | 83 | 58 | 85 | 71.5 | 39.5 | 3030 |
| 8/23/1985 | 1985 | 8 | 23 | 84 | 53 | 86 | 69.5 | 37.5 | 3067.5 |
| 8/24/1985 | 1985 | 8 | 24 | 85 | 51 | 87 | 69 | 37 | 3104.5 |
| 8/25/1985 | 1985 | 8 | 25 | 86 | 55 | 85 | 70 | 38 | 3142.5 |
| 8/26/1985 | 1985 | 8 | 26 | 87 | 57 | 87 | 72 | 40 | 3182.5 |
| 8/27/1985 | 1985 | 8 | 27 | 88 | 58 | 86 | 72 | 40 | 3222.5 |
| 8/28/1985 | 1985 | 8 | 28 | 89 | 57 | 82 | 69.5 | 37.5 | 3260 |
| 8/29/1985 | 1985 | 8 | 29 | 90 | 55 | 86 | 70.5 | 38.5 | 3298.5 |
| 8/30/1985 | 1985 | 8 | 30 | 91 | 57 | 86 | 71.5 | 39.5 | 3338 |
| 8/31/1985 | 1985 | 8 | 31 | 92 | 55 | 85 | 70 | 38 | 3376 |
| 9/1/1985 | 1985 | 9 | 1 | 93 | 53 | 81 | 67 | 35 | 3411 |
| 9/2/1985 | 1985 | 9 | 2 | 94 | 54 | 78 | 66 | 34 | 3445 |
| 9/3/1985 | 1985 | 9 | 3 | 95 | 56 | 79 | 67.5 | 35.5 | 3480.5 |
| 9/4/1985 | 1985 | 9 | 4 | 96 | 50 | 74 | 62 | 30 | 3510.5 |
| 9/5/1985 | 1985 | 9 | 5 | 97 | 45 | 75 | 60 | 28 | 3538.5 |
| 9/6/1985 | 1985 | 9 | 6 | 98 | 46 | 74 | 60 | 28 | 3566.5 |
| 9/7/1985 | 1985 | 9 | 7 | 99 | 45 | 71 | 58 | 26 | 3592.5 |
| 9/8/1985 | 1985 | 9 | 8 | 100 | 48 | 75 | 61.5 | 29.5 | 3622 |
| 9/9/1985 | 1985 | 9 | 9 | 101 | 47 | 77 | 62 | 30 | 3652 |
| 9/10/1985 | 1985 | 9 | 10 | 102 | 46 | 74 | 60 | 28 | 3680 |
| 9/11/1985 | 1985 | 9 | 11 | 103 | 52 | 75 | 63.5 | 31.5 | 3711.5 |
| 9/12/1985 | 1985 | 9 | 12 | 104 | 40 | 68 | 54 | 22 | 3733.5 |
| 9/13/1985 | 1985 | 9 | 13 | 105 | 42 | 78 | 60 | 28 | 3761.5 |
| 9/14/1985 | 1985 | 9 | 14 | 106 | 50 | 79 | 64.5 | 32.5 | 3794 |
| 9/15/1985 | 1985 | 9 | 15 | 107 | 57 | 75 | 66 | 34 | 3828 |
| 9/16/1985 | 1985 | 9 | 16 | 108 | 48 | 75 | 61.5 | 29.5 | 3857.5 |
| 9/17/1985 | 1985 | 9 | 17 | 109 | 49 | 72 | 60.5 | 28.5 | 3886 |
| 9/18/1985 | 1985 | 9 | 18 | 110 | 40 | 71 | 55.5 | 23.5 | 3909.5 |
| 9/19/1985 | 1985 | 9 | 19 | 111 | 49 | 75 | 62 | 30 | 3939.5 |
| 9/20/1985 | 1985 | 9 | 20 | 112 | 43 | 62 | 52.5 | 20.5 | 3960 |
| 9/21/1985 | 1985 | 9 | 21 | 113 | 40 | 52 | 46 | 14 | 3974 |
| 9/22/1985 | 1985 | 9 | 22 | 114 | 36 | 66 | 51 | 19 | 3993 |
| 9/23/1985 | 1985 | 9 | 23 | 115 | 36 | 66 | 51 | 19 | 4012 |
| 9/24/1985 | 1985 | 9 | 24 | 116 | 39 | 70 | 54.5 | 22.5 | 4034.5 |
| 9/25/1985 | 1985 | 9 | 25 | 117 | 42 | 69 | 55.5 | 23.5 | 4058 |
| 9/26/1985 | 1985 | 9 | 26 | 118 | 38 | 70 | 54 | 22 | 4080 |
| 9/27/1985 | 1985 | 9 | 27 | 119 | 44 | 70 | 57 | 25 | 4105 |
| 9/28/1985 | 1985 | 9 | 28 | 120 | 45 | 69 | 57 | 25 | 4130 |
| 9/29/1985 | 1985 | 9 | 29 | 121 | 37 | 58 | 47.5 | 15.5 | 4145.5 |
| 9/30/1985 | 1985 | 9 | 30 | 122 | 32 | 63 | 47.5 | 15.5 | 4161 |
| 10/1/1985 | 1985 | 10 | 1 | 123 | 36 | 65 | 50.5 | 18.5 | 4179.5 |
| 10/2/1985 | 1985 | 10 | 2 | 124 | 38 | 64 | 51 | 19 | 4198.5 |
| 10/3/1985 | 1985 | 10 | 3 | 125 | 35 | 70 | 52.5 | 20.5 | 4219 |
| 10/4/1985 | 1985 | 10 | 4 | 126 | 36 | 70 | 53 | 21 | 4240 |
| 10/5/1985 | 1985 | 10 | 5 | 127 | 35 | 69 | 52 | 20 | 4260 |
| 10/6/1985 | 1985 | 10 | 6 | 128 | 44 | 74 | 59 | 27 | 4287 |
| 10/7/1985 | 1985 | 10 | 7 | 129 | 29 | 71 | 50 | 18 | 4305 |
| 10/8/1985 | 1985 | 10 | 8 | 130 | 27 | 62 | 44.5 | 12.5 | 4317.5 |
| 10/9/1985 | 1985 | 10 | 9 | 131 | 25 | 64 | 44.5 | 12.5 | 4330 |
| 10/10/1985 | 1985 | 10 | 10 | 132 | 24 | 62 | 43 | 11 | 4341 |
| 10/11/1985 | 1985 | 10 | 11 | 133 | 30 | 57 | 43.5 | 11.5 | 4352.5 |
| 10/12/1985 | 1985 | 10 | 12 | 134 | 34 | 60 | 47 | 15 | 4367.5 |
| 10/13/1985 | 1985 | 10 | 13 | 135 | 30 | 59 | 44.5 | 12.5 | 4380 |
| 10/14/1985 | 1985 | 10 | 14 | 136 | 33 | 60 | 46.5 | 14.5 | 4394.5 |
| 10/15/1985 | 1985 | 10 | 15 | 137 | 30 | 58 | 44 | 12 | 4406.5 |
| 10/16/1985 | 1985 | 10 | 16 | 138 | 31 | 58 | 44.5 | 12.5 | 4419 |
| 10/17/1985 | 1985 | 10 | 17 | 139 | 32 | 54 | 43 | 11 | 4430 |
| 10/18/1985 | 1985 | 10 | 18 | 140 | 36 | 55 | 45.5 | 13.5 | 4443.5 |
| 10/19/1985 | 1985 | 10 | 19 | 141 | 38 | 53 | 45.5 | 13.5 | 4457 |
| 10/20/1985 | 1985 | 10 | 20 | 142 | 33 | 59 | 46 | 14 | 4471 |
| 10/21/1985 | 1985 | 10 | 21 | 143 | 39 | 60 | 49.5 | 17.5 | 4488.5 |
| 10/22/1985 | 1985 | 10 | 22 | 144 | 38 | 61 | 49.5 | 17.5 | 4506 |
| 10/23/1985 | 1985 | 10 | 23 | 145 | 35 | 60 | 47.5 | 15.5 | 4521.5 |
| 10/24/1985 | 1985 | 10 | 24 | 146 | 38 | 66 | 52 | 20 | 4541.5 |
| 10/25/1985 | 1985 | 10 | 25 | 147 | 37 | 69 | 53 | 21 | 4562.5 |
| 10/26/1985 | 1985 | 10 | 26 | 148 | 36 | 66 | 51 | 19 | 4581.5 |
| 10/27/1985 | 1985 | 10 | 27 | 149 | 35 | 64 | 49.5 | 17.5 | 4599 |
| 10/28/1985 | 1985 | 10 | 28 | 150 | 30 | 66 | 48 | 16 | 4615 |
| 10/29/1985 | 1985 | 10 | 29 | 151 | 38 | 62 | 50 | 18 | 4633 |
| 10/30/1985 | 1985 | 10 | 30 | 152 | 33 | 62 | 47.5 | 15.5 | 4648.5 |
| 10/31/1985 | 1985 | 10 | 31 | 153 | 38 | 57 | 47.5 | 15.5 | 4664 |
| 11/1/1985 | 1985 | 11 | 1 | 154 | 32 | 51 | 41.5 | 9.5 | 4673.5 |
| 11/2/1985 | 1985 | 11 | 2 | 155 | 29 | 50 | 39.5 | 7.5 | 4681 |
| 11/3/1985 | 1985 | 11 | 3 | 156 | 32 | 58 | 45 | 13 | 4694 |
| 11/4/1985 | 1985 | 11 | 4 | 157 | 33 | 66 | 49.5 | 17.5 | 4711.5 |
| 11/5/1985 | 1985 | 11 | 5 | 158 | 43 | 63 | 53 | 21 | 4732.5 |
| 11/6/1985 | 1985 | 11 | 6 | 159 | 29 | 58 | 43.5 | 11.5 | 4744 |
| 11/7/1985 | 1985 | 11 | 7 | 160 | 27 | 57 | 42 | 10 | 4754 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/8/1985 | 1985 | 11 | 8 | 161 | 34 | 58 | 46 | 14 | 4768 |
| 11/9/1985 | 1985 | 11 | 9 | 162 | 24 | 56 | 40 | 8 | 4776 |
| 11/10/1985 | 1985 | 11 | 10 | 163 | 23 | 59 | 41 | 9 | 4785 |
| 11/11/1985 | 1985 | 11 | 11 | 164 | 34 | 59 | 46.5 | 14.5 | 4799.5 |
| 11/12/1985 | 1985 | 11 | 12 | 165 | 27 | 54 | 40.5 | 8.5 | 4808 |
| 11/13/1985 | 1985 | 11 | 13 | 166 | 25 | 35 | 30 | -2 | 4806 |
| 11/14/1985 | 1985 | 11 | 14 | 167 | 15 | 32 | 23.5 | -8.5 | 4797.5 |
| 11/15/1985 | 1985 | 11 | 15 | 168 | 9 | 41 | 25 | -7 | 4790.5 |
| 11/16/1985 | 1985 | 11 | 16 | 169 | 19 | 52 | 35.5 | 3.5 | 4794 |
| 11/17/1985 | 1985 | 11 | 17 | 170 | 11 | 51 | 31 | -1 | 4793 |
| 11/18/1985 | 1985 | 11 | 18 | 171 | 16 | 36 | 26 | -6 | 4787 |
| 11/19/1985 | 1985 | 11 | 19 | 172 | 5 | 33 | 19 | -13 | 4774 |
| 11/20/1985 | 1985 | 11 | 20 | 173 | 9 | 47 | 28 | -4 | 4770 |
| 11/21/1985 | 1985 | 11 | 21 | 174 | 10 | 44 | 27 | -5 | 4765 |
| 11/22/1985 | 1985 | 11 | 22 | 175 | 12 | 50 | 31 | -1 | 4764 |
| 11/23/1985 | 1985 | 11 | 23 | 176 | 10 | 51 | 30.5 | -1.5 | 4762.5 |
| 11/24/1985 | 1985 | 11 | 24 | 177 | 11 | 55 | 33 | 1 | 4763.5 |
| 11/25/1985 | 1985 | 11 | 25 | 178 | 20 | 51 | 35.5 | 3.5 | 4767 |
| 11/26/1985 | 1985 | 11 | 26 | 179 | 18 | 47 | 32.5 | 0.5 | 4767.5 |
| 11/27/1985 | 1985 | 11 | 27 | 180 | 10 | 49 | 29.5 | -2.5 | 4765 |
| 11/28/1985 | 1985 | 11 | 28 | 181 | 26 | 48 | 37 | 5 | 4770 |
| 11/29/1985 | 1985 | 11 | 29 | 182 | 8 | 47 | 27.5 | -4.5 | 4765.5 |
| 11/30/1985 | 1985 | 11 | 30 | 183 | 10 | 35 | 22.5 | -9.5 | 4756 |
| 12/1/1985 | 1985 | 12 | 1 | 184 | 6 | 44 | 25 | -7 | 4749 |
| 12/2/1985 | 1985 | 12 | 2 | 185 | 16 | 49 | 32.5 | 0.5 | 4749.5 |
| 12/3/1985 | 1985 | 12 | 3 | 186 | 14 | 50 | 32 | 0 | 4749.5 |
| 12/4/1985 | 1985 | 12 | 4 | 187 | 14 | 50 | 32 | 0 | 4749.5 |
| 12/5/1985 | 1985 | 12 | 5 | 188 | 20 | 54 | 37 | 5 | 4754.5 |
| 12/6/1985 | 1985 | 12 | 6 | 189 | 20 | 50 | 35 | 3 | 4757.5 |
| 12/7/1985 | 1985 | 12 | 7 | 190 | 23 | 49 | 36 | 4 | 4761.5 |
| 12/8/1985 | 1985 | 12 | 8 | 191 | 25 | 47 | 36 | 4 | 4765.5 |
| 12/9/1985 | 1985 | 12 | 9 | 192 | 10 | 44 | 27 | -5 | 4760.5 |
| 12/10/1985 | 1985 | 12 | 10 | 193 | 19 | 32 | 25.5 | -6.5 | 4754 |
| 12/11/1985 | 1985 | 12 | 11 | 194 | 6 | 33 | 19.5 | -12.5 | 4741.5 |
| 12/12/1985 | 1985 | 12 | 12 | 195 | 7 | 28 | 17.5 | -14.5 | 4727 |
| 12/13/1985 | 1985 | 12 | 13 | 196 | 3 | 29 | 16 | -16 | 4711 |
| 12/14/1985 | 1985 | 12 | 14 | 197 | 9 | 37 | 23 | -9 | 4702 |
| 12/15/1985 | 1985 | 12 | 15 | 198 | 10 | 39 | 24.5 | -7.5 | 4694.5 |
| 12/16/1985 | 1985 | 12 | 16 | 199 | 15 | 40 | 27.5 | -4.5 | 4690 |
| 12/17/1985 | 1985 | 12 | 17 | 200 | 6 | 38 | 22 | -10 | 4680 |
| 12/18/1985 | 1985 | 12 | 18 | 201 | 10 | 45 | 27.5 | -4.5 | 4675.5 |
| 12/19/1985 | 1985 | 12 | 19 | 202 | 15 | 46 | 30.5 | -1.5 | 4674 |
| 12/20/1985 | 1985 | 12 | 20 | 203 | 20 | 45 | 32.5 | 0.5 | 4674.5 |
| 12/21/1985 | 1985 | 12 | 21 | 204 | 14 | 52 | 33 | 1 | 4675.5 |
| 12/22/1985 | 1985 | 12 | 22 | 205 | 16 | 53 | 34.5 | 2.5 | 4678 |
| 12/23/1985 | 1985 | 12 | 23 | 206 | 14 | 50 | 32 | 0 | 4678 |
| 12/24/1985 | 1985 | 12 | 24 | 207 | 19 | 47 | 33 | 1 | 4679 |
| 12/25/1985 | 1985 | 12 | 25 | 208 | 13 | 46 | 29.5 | -2.5 | 4676.5 |
| 12/26/1985 | 1985 | 12 | 26 | 209 | 15 | 47 | 31 | -1 | 4675.5 |
| 12/27/1985 | 1985 | 12 | 27 | 210 | 15 | 47 | 31 | -1 | 4674.5 |
| 12/28/1985 | 1985 | 12 | 28 | 211 | 15 | 52 | 33.5 | 1.5 | 4676 |
| 12/29/1985 | 1985 | 12 | 29 | 212 | 16 | 54 | 35 | 3 | 4679 |
| 12/30/1985 | 1985 | 12 | 30 | 213 | 10 | 46 | 28 | -4 | 4675 |
| 12/31/1985 | 1985 | 12 | 31 | 214 | 14 | 47 | 30.5 | -1.5 | 4673.5 |
| 1/1/1986 | 1986 | 1 | 1 | 215 | 12 | 43 | 27.5 | -4.5 | 4669 |
| 1/2/1986 | 1986 | 1 | 2 | 216 | 19 | 46 | 32.5 | 0.5 | 4669.5 |
| 1/3/1986 | 1986 | 1 | 3 | 217 | 16 | 45 | 30.5 | -1.5 | 4668 |
| 1/4/1986 | 1986 | 1 | 4 | 218 | 14 | 44 | 29 | -3 | 4665 |
| 1/5/1986 | 1986 | 1 | 5 | 219 | 15 | 46 | 30.5 | -1.5 | 4663.5 |
| 1/6/1986 | 1986 | 1 | 6 | 220 | 12 | 46 | 29 | -3 | 4660.5 |
| 1/7/1986 | 1986 | 1 | 7 | 221 | 19 | 43 | 31 | -1 | 4659.5 |
| 1/8/1986 | 1986 | 1 | 8 | 222 | 10 | 39 | 24.5 | -7.5 | 4652 |
| 1/9/1986 | 1986 | 1 | 9 | 223 | 15 | 40 | 27.5 | -4.5 | 4647.5 |
| 1/10/1986 | 1986 | 1 | 10 | 224 | 19 | 49 | 34 | 2 | 4649.5 |
| 1/11/1986 | 1986 | 1 | 11 | 225 | 12 | 51 | 31.5 | -0.5 | 4649 |
| 1/12/1986 | 1986 | 1 | 12 | 226 | 16 | 56 | 36 | 4 | 4653 |
| 1/13/1986 | 1986 | 1 | 13 | 227 | 14 | 54 | 34 | 2 | 4655 |
| 1/14/1986 | 1986 | 1 | 14 | 228 | 9 | 47 | 28 | -4 | 4651 |
| 1/15/1986 | 1986 | 1 | 15 | 229 | 16 | 44 | 30 | -2 | 4649 |
| 1/16/1986 | 1986 | 1 | 16 | 230 | 17 | 47 | 32 | 0 | 4649 |
| 1/17/1986 | 1986 | 1 | 17 | 231 | 19 | 52 | 35.5 | 3.5 | 4652.5 |
| 1/18/1986 | 1986 | 1 | 18 | 232 | 18 | 50 | 34 | 2 | 4654.5 |
| 1/19/1986 | 1986 | 1 | 19 | 233 | 20 | 61 | 40.5 | 8.5 | 4663 |
| 1/20/1986 | 1986 | 1 | 20 | 234 | 37 | 58 | 47.5 | 15.5 | 4678.5 |
| 1/21/1986 | 1986 | 1 | 21 | 235 | 16 | 56 | 36 | 4 | 4682.5 |
| 1/22/1986 | 1986 | 1 | 22 | 236 | 23 | 52 | 37.5 | 5.5 | 4688 |
| 1/23/1986 | 1986 | 1 | 23 | 237 | 20 | 59 | 39.5 | 7.5 | 4695.5 |
| 1/24/1986 | 1986 | 1 | 24 | 238 | 27 | 57 | 42 | 10 | 4705.5 |
| 1/25/1986 | 1986 | 1 | 25 | 239 | 21 | 53 | 37 | 5 | 4710.5 |
| 1/26/1986 | 1986 | 1 | 26 | 240 | 21 | 54 | 37.5 | 5.5 | 4716 |
| 1/27/1986 | 1986 | 1 | 27 | 241 | 25 | 57 | 41 | 9 | 4725 |
| 1/28/1986 | 1986 | 1 | 28 | 242 | 27 | 60 | 43.5 | 11.5 | 4736.5 |
| 1/29/1986 | 1986 | 1 | 29 | 243 | 31 | 64 | 47.5 | 15.5 | 4752 |
| 1/30/1986 | 1986 | 1 | 30 | 244 | 29 | 63 | 46 | 14 | 4766 |
| 1/31/1986 | 1986 | 1 | 31 | 245 | 20 | 56 | 38 | 6 | 4772 |
| 2/1/1986 | 1986 | 2 | 1 | 246 | 30 | 57 | 43.5 | 11.5 | 4783.5 |
| 2/2/1986 | 1986 | 2 | 2 | 247 | 29 | 55 | 42 | 10 | 4793.5 |
| 2/3/1986 | 1986 | 2 | 3 | 248 | 28 | 54 | 41 | 9 | 4802.5 |
| 2/4/1986 | 1986 | 2 | 4 | 249 | 22 | 43 | 32.5 | 0.5 | 4803 |
| 2/5/1986 | 1986 | 2 | 5 | 250 | -3 | 40 | 18.5 | -13.5 | 4789.5 |
| 2/6/1986 | 1986 | 2 | 6 | 251 | 7 | 36 | 21.5 | -10.5 | 4779 |
| 2/7/1986 | 1986 | 2 | 7 | 252 | 13 | 32 | 22.5 | -9.5 | 4769.5 |
| 2/8/1986 | 1986 | 2 | 8 | 253 | 12 | 34 | 23 | -9 | 4760.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/9/1986 | 1986 | 2 | 9 | 254 | 4 | 32 | 18 | -14 | 4746.5 |
| 2/10/1986 | 1986 | 2 | 10 | 255 | 5 | 33 | 19 | -13 | 4733.5 |
| 2/11/1986 | 1986 | 2 | 11 | 256 | 10 | 35 | 22.5 | -9.5 | 4724 |
| 2/12/1986 | 1986 | 2 | 12 | 257 | 12 | 45 | 28.5 | -3.5 | 4720.5 |
| 2/13/1986 | 1986 | 2 | 13 | 258 | 11 | 44 | 27.5 | -4.5 | 4716 |
| 2/14/1986 | 1986 | 2 | 14 | 259 | 12 | 41 | 26.5 | -5.5 | 4710.5 |
| 2/15/1986 | 1986 | 2 | 15 | 260 | 13 | 40 | 26.5 | -5.5 | 4705 |
| 2/16/1986 | 1986 | 2 | 16 | 261 | 14 | 40 | 27 | -5 | 4700 |
| 2/17/1986 | 1986 | 2 | 17 | 262 | 13 | 54 | 33.5 | 1.5 | 4701.5 |
| 2/18/1986 | 1986 | 2 | 18 | 263 | 15 | 58 | 36.5 | 4.5 | 4706 |
| 2/19/1986 | 1986 | 2 | 19 | 264 | 19 | 55 | 37 | 5 | 4711 |
| 2/20/1986 | 1986 | 2 | 20 | 265 | 20 | 55 | 37.5 | 5.5 | 4716.5 |
| 2/21/1986 | 1986 | 2 | 21 | 266 | 20 | 51 | 35.5 | 3.5 | 4720 |
| 2/22/1986 | 1986 | 2 | 22 | 267 | 23 | 52 | 37.5 | 5.5 | 4725.5 |
| 2/23/1986 | 1986 | 2 | 23 | 268 | 26 | 55 | 40.5 | 8.5 | 4734 |
| 2/24/1986 | 1986 | 2 | 24 | 269 | 32 | 60 | 46 | 14 | 4748 |
| 2/25/1986 | 1986 | 2 | 25 | 270 | 36 | 67 | 51.5 | 19.5 | 4767.5 |
| 2/26/1986 | 1986 | 2 | 26 | 271 | 37 | 64 | 50.5 | 18.5 | 4786 |
| 2/27/1986 | 1986 | 2 | 27 | 272 | 35 | 60 | 47.5 | 15.5 | 4801.5 |
| 2/28/1986 | 1986 | 2 | 28 | 273 | 24 | 58 | 41 | 9 | 4810.5 |
| 3/1/1986 | 1986 | 3 | 1 | 274 | 27 | 64 | 45.5 | 13.5 | 4824 |
| 3/2/1986 | 1986 | 3 | 2 | 275 | 35 | 61 | 48 | 16 | 4840 |
| 3/3/1986 | 1986 | 3 | 3 | 276 | 33 | 61 | 47 | 15 | 4855 |
| 3/4/1986 | 1986 | 3 | 4 | 277 | 29 | 61 | 45 | 13 | 4868 |
| 3/5/1986 | 1986 | 3 | 5 | 278 | 32 | 61 | 46.5 | 14.5 | 4882.5 |
| 3/6/1986 | 1986 | 3 | 6 | 279 | 31 | 63 | 47 | 15 | 4897.5 |
| 3/7/1986 | 1986 | 3 | 7 | 280 | 32 | 63 | 47.5 | 15.5 | 4913 |
| 3/8/1986 | 1986 | 3 | 8 | 281 | 37 | 61 | 49 | 17 | 4930 |
| 3/9/1986 | 1986 | 3 | 9 | 282 | 20 | 56 | 38 | 6 | 4936 |
| 3/10/1986 | 1986 | 3 | 10 | 283 | 28 | 40 | 34 | 2 | 4938 |
| 3/11/1986 | 1986 | 3 | 11 | 284 | 11 | 44 | 27.5 | -4.5 | 4933.5 |
| 3/12/1986 | 1986 | 3 | 12 | 285 | 29 | 45 | 37 | 5 | 4938.5 |
| 3/13/1986 | 1986 | 3 | 13 | 286 | 25 | 43 | 34 | 2 | 4940.5 |
| 3/14/1986 | 1986 | 3 | 14 | 287 | 28 | 39 | 33.5 | 1.5 | 4942 |
| 3/15/1986 | 1986 | 3 | 15 | 288 | 28 | 48 | 38 | 6 | 4948 |
| 3/16/1986 | 1986 | 3 | 16 | 289 | 27 | 53 | 40 | 8 | 4956 |
| 3/17/1986 | 1986 | 3 | 17 | 290 | 27 | 48 | 37.5 | 5.5 | 4961.5 |
| 3/18/1986 | 1986 | 3 | 18 | 291 | 26 | 41 | 33.5 | 1.5 | 4963 |
| 3/19/1986 | 1986 | 3 | 19 | 292 | 20 | 45 | 32.5 | 0.5 | 4963.5 |
| 3/20/1986 | 1986 | 3 | 20 | 293 | 28 | 54 | 41 | 9 | 4972.5 |
| 3/21/1986 | 1986 | 3 | 21 | 294 | 28 | 61 | 44.5 | 12.5 | 4985 |
| 3/22/1986 | 1986 | 3 | 22 | 295 | 29 | 64 | 46.5 | 14.5 | 4999.5 |
| 3/23/1986 | 1986 | 3 | 23 | 296 | 33 | 68 | 50.5 | 18.5 | 5018 |
| 3/24/1986 | 1986 | 3 | 24 | 297 | 38 | 66 | 52 | 20 | 5038 |
| 3/25/1986 | 1986 | 3 | 25 | 298 | 39 | 66 | 52.5 | 20.5 | 5058.5 |
| 3/26/1986 | 1986 | 3 | 26 | 299 | 38 | 67 | 52.5 | 20.5 | 5079 |
| 3/27/1986 | 1986 | 3 | 27 | 300 | 35 | 70 | 52.5 | 20.5 | 5099.5 |
| 3/28/1986 | 1986 | 3 | 28 | 301 | 33 | 69 | 51 | 19 | 5118.5 |
| 3/29/1986 | 1986 | 3 | 29 | 302 | 33 | 64 | 48.5 | 16.5 | 5135 |
| 3/30/1986 | 1986 | 3 | 30 | 303 | 37 | 66 | 51.5 | 19.5 | 5154.5 |
| 3/31/1986 | 1986 | 3 | 31 | 304 | 39 | 65 | 52 | 20 | 5174.5 |
| 4/1/1986 | 1986 | 4 | 1 | 305 | 41 | 58 | 49.5 | 17.5 | 5192 |
| 4/2/1986 | 1986 | 4 | 2 | 306 | 27 | 58 | 42.5 | 10.5 | 5202.5 |
| 4/3/1986 | 1986 | 4 | 3 | 307 | 28 | 38 | 33 | 1 | 5203.5 |
| 4/4/1986 | 1986 | 4 | 4 | 308 | 29 | 51 | 40 | 8 | 5211.5 |
| 4/5/1986 | 1986 | 4 | 5 | 309 | 29 | 63 | 46 | 14 | 5225.5 |
| 4/6/1986 | 1986 | 4 | 6 | 310 | 29 | 64 | 46.5 | 14.5 | 5240 |
| 4/7/1986 | 1986 | 4 | 7 | 311 | 44 | 65 | 54.5 | 22.5 | 5262.5 |
| 4/8/1986 | 1986 | 4 | 8 | 312 | 42 | 69 | 55.5 | 23.5 | 5286 |
| 4/9/1986 | 1986 | 4 | 9 | 313 | 32 | 66 | 49 | 17 | 5303 |
| 4/10/1986 | 1986 | 4 | 10 | 314 | 33 | 64 | 48.5 | 16.5 | 5319.5 |
| 4/11/1986 | 1986 | 4 | 11 | 315 | 33 | 64 | 48.5 | 16.5 | 5336 |
| 4/12/1986 | 1986 | 4 | 12 | 316 | 40 | 61 | 50.5 | 18.5 | 5354.5 |
| 4/13/1986 | 1986 | 4 | 13 | 317 | 44 | 58 | 51 | 19 | 5373.5 |
| 4/14/1986 | 1986 | 4 | 14 | 318 | 26 | 62 | 44 | 12 | 5385.5 |
| 4/15/1986 | 1986 | 4 | 15 | 319 | 42 | 68 | 55 | 23 | 5408.5 |
| 4/16/1986 | 1986 | 4 | 16 | 320 | 46 | 62 | 54 | 22 | 5430.5 |
| 4/17/1986 | 1986 | 4 | 17 | 321 | 38 | 59 | 48.5 | 16.5 | 5447 |
| 4/18/1986 | 1986 | 4 | 18 | 322 | 25 | 47 | 36 | 4 | 5451 |
| 4/19/1986 | 1986 | 4 | 19 | 323 | 26 | 55 | 40.5 | 8.5 | 5459.5 |
| 4/20/1986 | 1986 | 4 | 20 | 324 | 33 | 67 | 50 | 18 | 5477.5 |
| 4/21/1986 | 1986 | 4 | 21 | 325 | 40 | 73 | 56.5 | 24.5 | 5502 |
| 4/22/1986 | 1986 | 4 | 22 | 326 | 43 | 75 | 59 | 27 | 5529 |
| 4/23/1986 | 1986 | 4 | 23 | 327 | 48 | 67 | 57.5 | 25.5 | 5554.5 |
| 4/24/1986 | 1986 | 4 | 24 | 328 | 44 | 65 | 54.5 | 22.5 | 5577 |
| 4/25/1986 | 1986 | 4 | 25 | 329 | 46 | 62 | 54 | 22 | 5599 |
| 4/26/1986 | 1986 | 4 | 26 | 330 | 31 | 63 | 47 | 15 | 5614 |
| 4/27/1986 | 1986 | 4 | 27 | 331 | 21 | 63 | 42 | 10 | 5624 |
| 4/28/1986 | 1986 | 4 | 28 | 332 | 21 | 74 | 47.5 | 15.5 | 5639.5 |
| 4/29/1986 | 1986 | 4 | 29 | 333 | 44 | 73 | 58.5 | 26.5 | 5666 |
| 4/30/1986 | 1986 | 4 | 30 | 334 | 46 | 72 | 59 | 27 | 5693 |
| 5/1/1986 | 1986 | 5 | 1 | 335 | 44 | 77 | 60.5 | 28.5 | 5721.5 |
| 5/2/1986 | 1986 | 5 | 2 | 336 | 44 | 77 | 60.5 | 28.5 | 5750 |
| 5/3/1986 | 1986 | 5 | 3 | 337 | 44 | 73 | 58.5 | 26.5 | 5776.5 |
| 5/4/1986 | 1986 | 5 | 4 | 338 | 48 | 75 | 61.5 | 29.5 | 5806 |
| 5/5/1986 | 1986 | 5 | 5 | 339 | 36 | 68 | 52 | 20 | 5826 |
| 5/6/1986 | 1986 | 5 | 6 | 340 | 40 | 68 | 54 | 22 | 5848 |
| 5/7/1986 | 1986 | 5 | 7 | 341 | 39 | 59 | 49 | 17 | 5865 |
| 5/8/1986 | 1986 | 5 | 8 | 342 | 29 | 51 | 40 | 8 | 5873 |
| 5/9/1986 | 1986 | 5 | 9 | 343 | 26 | 60 | 43 | 11 | 5884 |
| 5/10/1986 | 1986 | 5 | 10 | 344 | 30 | 71 | 50.5 | 18.5 | 5902.5 |
| 5/11/1986 | 1986 | 5 | 11 | 345 | 40 | 74 | 57 | 25 | 5927.5 |
| 5/12/1986 | 1986 | 5 | 12 | 346 | 41 | 74 | 57.5 | 25.5 | 5953 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/13/1986 | 1986 | 5 | 13 | 347 | 41 | 73 | 57 | 25 | 5978 |
| 5/14/1986 | 1986 | 5 | 14 | 348 | 49 | 73 | 61 | 29 | 6007 |
| 5/15/1986 | 1986 | 5 | 15 | 349 | 49 | 73 | 61 | 29 | 6036 |
| 5/16/1986 | 1986 | 5 | 16 | 350 | 49 | 73 | 61 | 29 | 6065 |
| 5/17/1986 | 1986 | 5 | 17 | 351 | 49 | 73 | 61 | 29 | 6094 |
| 5/18/1986 | 1986 | 5 | 18 | 352 | 34 | 69 | 51.5 | 19.5 | 6113.5 |
| 5/19/1986 | 1986 | 5 | 19 | 353 | 41 | 76 | 58.5 | 26.5 | 6140 |
| 5/20/1986 | 1986 | 5 | 20 | 354 | 47 | 80 | 63.5 | 31.5 | 6171.5 |
| 5/21/1986 | 1986 | 5 | 21 | 355 | 52 | 79 | 65.5 | 33.5 | 6205 |
| 5/22/1986 | 1986 | 5 | 22 | 356 | 52 | 74 | 63 | 31 | 6236 |
| 5/23/1986 | 1986 | 5 | 23 | 357 | 44 | 79 | 61.5 | 29.5 | 6265.5 |
| 5/24/1986 | 1986 | 5 | 24 | 358 | 52 | 79 | 65.5 | 33.5 | 6299 |
| 5/25/1986 | 1986 | 5 | 25 | 359 | 49 | 79 | 64 | 32 | 6331 |
| 5/26/1986 | 1986 | 5 | 26 | 360 | 45 | 78 | 61.5 | 29.5 | 6360.5 |
| 5/27/1986 | 1986 | 5 | 27 | 361 | 45 | 77 | 61 | 29 | 6389.5 |
| 5/28/1986 | 1986 | 5 | 28 | 362 | 43 | 73 | 58 | 26 | 6415.5 |
| 5/29/1986 | 1986 | 5 | 29 | 363 | 47 | 80 | 63.5 | 31.5 | 6447 |
| 5/30/1986 | 1986 | 5 | 30 | 364 | 40 | 77 | 58.5 | 26.5 | 6473.5 |
| 5/31/1986 | 1986 | 5 | 31 | 365 | 42 | 62 | 52 | 20 | 6493.5 |
| 6/1/1986 | 1986 | 6 | 1 | 1 | 43 | 65 | 54 | 22 | 22 |
| 6/2/1986 | 1986 | 6 | 2 | 2 | 43 | 62 | 52.5 | 20.5 | 42.5 |
| 6/3/1986 | 1986 | 6 | 3 | 3 | 47 | 72 | 59.5 | 27.5 | 70 |
| 6/4/1986 | 1986 | 6 | 4 | 4 | 49 | 81 | 65 | 33 | 103 |
| 6/5/1986 | 1986 | 6 | 5 | 5 | 49 | 83 | 66 | 34 | 137 |
| 6/6/1986 | 1986 | 6 | 6 | 6 | 59 | 82 | 70.5 | 38.5 | 175.5 |
| 6/7/1986 | 1986 | 6 | 7 | 7 | 54 | 82 | 68 | 36 | 211.5 |
| 6/8/1986 | 1986 | 6 | 8 | 8 | 54 | 82 | 68 | 36 | 247.5 |
| 6/9/1986 | 1986 | 6 | 9 | 9 | 43 | 72 | 57.5 | 25.5 | 273 |
| 6/10/1986 | 1986 | 6 | 10 | 10 | 41 | 71 | 56 | 24 | 297 |
| 6/11/1986 | 1986 | 6 | 11 | 11 | 45 | 76 | 60.5 | 28.5 | 325.5 |
| 6/12/1986 | 1986 | 6 | 12 | 12 | 49 | 83 | 66 | 34 | 359.5 |
| 6/13/1986 | 1986 | 6 | 13 | 13 | 57 | 86 | 71.5 | 39.5 | 399 |
| 6/14/1986 | 1986 | 6 | 14 | 14 | 56 | 86 | 71 | 39 | 438 |
| 6/15/1986 | 1986 | 6 | 15 | 15 | 57 | 84 | 70.5 | 38.5 | 476.5 |
| 6/16/1986 | 1986 | 6 | 16 | 16 | 67 | 86 | 76.5 | 44.5 | 521 |
| 6/17/1986 | 1986 | 6 | 17 | 17 | 54 | 83 | 68.5 | 36.5 | 557.5 |
| 6/18/1986 | 1986 | 6 | 18 | 18 | 54 | 78 | 66 | 34 | 591.5 |
| 6/19/1986 | 1986 | 6 | 19 | 19 | 55 | 82 | 68.5 | 36.5 | 628 |
| 6/20/1986 | 1986 | 6 | 20 | 20 | 53 | 86 | 69.5 | 37.5 | 665.5 |
| 6/21/1986 | 1986 | 6 | 21 | 21 | 54 | 86 | 70 | 38 | 703.5 |
| 6/22/1986 | 1986 | 6 | 22 | 22 | 54 | 88 | 71 | 39 | 742.5 |
| 6/23/1986 | 1986 | 6 | 23 | 23 | 58 | 88 | 73 | 41 | 783.5 |
| 6/24/1986 | 1986 | 6 | 24 | 24 | 53 | 74 | 63.5 | 31.5 | 815 |
| 6/25/1986 | 1986 | 6 | 25 | 25 | 53 | 66 | 59.5 | 27.5 | 842.5 |
| 6/26/1986 | 1986 | 6 | 26 | 26 | 50 | 74 | 62 | 30 | 872.5 |
| 6/27/1986 | 1986 | 6 | 27 | 27 | 53 | 81 | 67 | 35 | 907.5 |
| 6/28/1986 | 1986 | 6 | 28 | 28 | 55 | 84 | 69.5 | 37.5 | 945 |
| 6/29/1986 | 1986 | 6 | 29 | 29 | 60 | 83 | 71.5 | 39.5 | 984.5 |
| 6/30/1986 | 1986 | 6 | 30 | 30 | 60 | 79 | 69.5 | 37.5 | 1022 |
| 7/1/1986 | 1986 | 7 | 1 | 31 | 57 | 78 | 67.5 | 35.5 | 1057.5 |
| 7/2/1986 | 1986 | 7 | 2 | 32 | 53 | 81 | 67 | 35 | 1092.5 |
| 7/3/1986 | 1986 | 7 | 3 | 33 | 56 | 83 | 69.5 | 37.5 | 1130 |
| 7/4/1986 | 1986 | 7 | 4 | 34 | 60 | 84 | 72 | 40 | 1170 |
| 7/5/1986 | 1986 | 7 | 5 | 35 | 59 | 84 | 71.5 | 39.5 | 1209.5 |
| 7/6/1986 | 1986 | 7 | 6 | 36 | 53 | 82 | 67.5 | 35.5 | 1245 |
| 7/7/1986 | 1986 | 7 | 7 | 37 | 61 | 80 | 70.5 | 38.5 | 1283.5 |
| 7/8/1986 | 1986 | 7 | 8 | 38 | 56 | 77 | 66.5 | 34.5 | 1318 |
| 7/9/1986 | 1986 | 7 | 9 | 39 | 55 | 79 | 67 | 35 | 1353 |
| 7/10/1986 | 1986 | 7 | 10 | 40 | 53 | 82 | 67.5 | 35.5 | 1388.5 |
| 7/11/1986 | 1986 | 7 | 11 | 41 | 53 | 85 | 69 | 37 | 1425.5 |
| 7/12/1986 | 1986 | 7 | 12 | 42 | 53 | 88 | 70.5 | 38.5 | 1464 |
| 7/13/1986 | 1986 | 7 | 13 | 43 | 60 | 88 | 74 | 42 | 1506 |
| 7/14/1986 | 1986 | 7 | 14 | 44 | 60 | 88 | 74 | 42 | 1548 |
| 7/15/1986 | 1986 | 7 | 15 | 45 | 56 | 88 | 72 | 40 | 1588 |
| 7/16/1986 | 1986 | 7 | 16 | 46 | 56 | 67 | 61.5 | 29.5 | 1617.5 |
| 7/17/1986 | 1986 | 7 | 17 | 47 | 52 | 72 | 62 | 30 | 1647.5 |
| 7/18/1986 | 1986 | 7 | 18 | 48 | 52 | 74 | 63 | 31 | 1678.5 |
| 7/19/1986 | 1986 | 7 | 19 | 49 | 52 | 76 | 64 | 32 | 1710.5 |
| 7/20/1986 | 1986 | 7 | 20 | 50 | 52 | 79 | 65.5 | 33.5 | 1744 |
| 7/21/1986 | 1986 | 7 | 21 | 51 | 53 | 71 | 62 | 30 | 1774 |
| 7/22/1986 | 1986 | 7 | 22 | 52 | 52 | 71 | 61.5 | 29.5 | 1803.5 |
| 7/23/1986 | 1986 | 7 | 23 | 53 | 50 | 75 | 62.5 | 30.5 | 1834 |
| 7/24/1986 | 1986 | 7 | 24 | 54 | 50 | 79 | 64.5 | 32.5 | 1866.5 |
| 7/25/1986 | 1986 | 7 | 25 | 55 | 53 | 81 | 67 | 35 | 1901.5 |
| 7/26/1986 | 1986 | 7 | 26 | 56 | 56 | 84 | 70 | 38 | 1939.5 |
| 7/27/1986 | 1986 | 7 | 27 | 57 | 51 | 84 | 67.5 | 35.5 | 1975 |
| 7/28/1986 | 1986 | 7 | 28 | 58 | 55 | 86 | 70.5 | 38.5 | 2013.5 |
| 7/29/1986 | 1986 | 7 | 29 | 59 | 55 | 89 | 72 | 40 | 2053.5 |
| 7/30/1986 | 1986 | 7 | 30 | 60 | 60 | 89 | 74.5 | 42.5 | 2096 |
| 7/31/1986 | 1986 | 7 | 31 | 61 | 56 | 87 | 71.5 | 39.5 | 2135.5 |
| 8/1/1986 | 1986 | 8 | 1 | 62 | 57 | 88 | 72.5 | 40.5 | 2176 |
| 8/2/1986 | 1986 | 8 | 2 | 63 | 58 | 87 | 72.5 | 40.5 | 2216.5 |
| 8/3/1986 | 1986 | 8 | 3 | 64 | 58 | 87 | 72.5 | 40.5 | 2257 |
| 8/4/1986 | 1986 | 8 | 4 | 65 | 55 | 85 | 70 | 38 | 2295 |
| 8/5/1986 | 1986 | 8 | 5 | 66 | 56 | 85 | 70.5 | 38.5 | 2333.5 |
| 8/6/1986 | 1986 | 8 | 6 | 67 | 58 | 80 | 69 | 37 | 2370.5 |
| 8/7/1986 | 1986 | 8 | 7 | 68 | 55 | 83 | 69 | 37 | 2407.5 |
| 8/8/1986 | 1986 | 8 | 8 | 69 | 55 | 84 | 69.5 | 37.5 | 2445 |
| 8/9/1986 | 1986 | 8 | 9 | 70 | 57 | 83 | 70 | 38 | 2483 |
| 8/10/1986 | 1986 | 8 | 10 | 71 | 56 | 81 | 68.5 | 36.5 | 2519.5 |
| 8/11/1986 | 1986 | 8 | 11 | 72 | 49 | 81 | 65 | 33 | 2552.5 |
| 8/12/1986 | 1986 | 8 | 12 | 73 | 57 | 81 | 69 | 37 | 2589.5 |
| 8/13/1986 | 1986 | 8 | 13 | 74 | 55 | 80 | 67.5 | 35.5 | 2625 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/14/1986 | 1986 | 8 | 14 | 75 | 55 | 82 | 68.5 | 36.5 | 2661.5 |
| 8/15/1986 | 1986 | 8 | 15 | 76 | 55 | 82 | 68.5 | 36.5 | 2698 |
| 8/16/1986 | 1986 | 8 | 16 | 77 | 54 | 87 | 70.5 | 38.5 | 2736.5 |
| 8/17/1986 | 1986 | 8 | 17 | 78 | 58 | 87 | 72.5 | 40.5 | 2777 |
| 8/18/1986 | 1986 | 8 | 18 | 79 | 62 | 87 | 74.5 | 42.5 | 2819.5 |
| 8/19/1986 | 1986 | 8 | 19 | 80 | 60 | 87 | 73.5 | 41.5 | 2861 |
| 8/20/1986 | 1986 | 8 | 20 | 81 | 60 | 88 | 74 | 42 | 2903 |
| 8/21/1986 | 1986 | 8 | 21 | 82 | 62 | 87 | 74.5 | 42.5 | 2945.5 |
| 8/22/1986 | 1986 | 8 | 22 | 83 | 60 | 86 | 73 | 41 | 2986.5 |
| 8/23/1986 | 1986 | 8 | 23 | 84 | 56 | 85 | 70.5 | 38.5 | 3025 |
| 8/24/1986 | 1986 | 8 | 24 | 85 | 51 | 72 | 61.5 | 29.5 | 3054.5 |
| 8/25/1986 | 1986 | 8 | 25 | 86 | 54 | 73 | 63.5 | 31.5 | 3086 |
| 8/26/1986 | 1986 | 8 | 26 | 87 | 54 | 76 | 65 | 33 | 3119 |
| 8/27/1986 | 1986 | 8 | 27 | 88 | 56 | 75 | 65.5 | 33.5 | 3152.5 |
| 8/28/1986 | 1986 | 8 | 28 | 89 | 55 | 74 | 64.5 | 32.5 | 3185 |
| 8/29/1986 | 1986 | 8 | 29 | 90 | 55 | 72 | 63.5 | 31.5 | 3216.5 |
| 8/30/1986 | 1986 | 8 | 30 | 91 | 54 | 73 | 63.5 | 31.5 | 3248 |
| 8/31/1986 | 1986 | 8 | 31 | 92 | 56 | 72 | 64 | 32 | 3280 |
| 9/1/1986 | 1986 | 9 | 1 | 93 | 48 | 76 | 62 | 30 | 3310 |
| 9/2/1986 | 1986 | 9 | 2 | 94 | 48 | 76 | 62 | 30 | 3340 |
| 9/3/1986 | 1986 | 9 | 3 | 95 | 52 | 77 | 64.5 | 32.5 | 3372.5 |
| 9/4/1986 | 1986 | 9 | 4 | 96 | 49 | 80 | 64.5 | 32.5 | 3405 |
| 9/5/1986 | 1986 | 9 | 5 | 97 | 47 | 80 | 63.5 | 31.5 | 3436.5 |
| 9/6/1986 | 1986 | 9 | 6 | 98 | 47 | 82 | 64.5 | 32.5 | 3469 |
| 9/7/1986 | 1986 | 9 | 7 | 99 | 63 | 80 | 71.5 | 39.5 | 3508.5 |
| 9/8/1986 | 1986 | 9 | 8 | 100 | 53 | 73 | 63 | 31 | 3539.5 |
| 9/9/1986 | 1986 | 9 | 9 | 101 | 51 | 70 | 60.5 | 28.5 | 3568 |
| 9/10/1986 | 1986 | 9 | 10 | 102 | 50 | 69 | 59.5 | 27.5 | 3595.5 |
| 9/11/1986 | 1986 | 9 | 11 | 103 | 40 | 70 | 55 | 23 | 3618.5 |
| 9/12/1986 | 1986 | 9 | 12 | 104 | 40 | 75 | 57.5 | 25.5 | 3644 |
| 9/13/1986 | 1986 | 9 | 13 | 105 | 49 | 76 | 62.5 | 30.5 | 3674.5 |
| 9/14/1986 | 1986 | 9 | 14 | 106 | 48 | 77 | 62.5 | 30.5 | 3705 |
| 9/15/1986 | 1986 | 9 | 15 | 107 | 45 | 76 | 60.5 | 28.5 | 3733.5 |
| 9/16/1986 | 1986 | 9 | 16 | 108 | 50 | 74 | 62 | 30 | 3763.5 |
| 9/17/1986 | 1986 | 9 | 17 | 109 | 44 | 75 | 59.5 | 27.5 | 3791 |
| 9/18/1986 | 1986 | 9 | 18 | 110 | 45 | 74 | 59.5 | 27.5 | 3818.5 |
| 9/19/1986 | 1986 | 9 | 19 | 111 | 57 | 78 | 67.5 | 35.5 | 3854 |
| 9/20/1986 | 1986 | 9 | 20 | 112 | 53 | 76 | 64.5 | 32.5 | 3886.5 |
| 9/21/1986 | 1986 | 9 | 21 | 113 | 48 | 74 | 61 | 29 | 3915.5 |
| 9/22/1986 | 1986 | 9 | 22 | 114 | 50 | 72 | 61 | 29 | 3944.5 |
| 9/23/1986 | 1986 | 9 | 23 | 115 | 43 | 68 | 55.5 | 23.5 | 3968 |
| 9/24/1986 | 1986 | 9 | 24 | 116 | 32 | 60 | 46 | 14 | 3982 |
| 9/25/1986 | 1986 | 9 | 25 | 117 | 37 | 53 | 45 | 13 | 3995 |
| 9/26/1986 | 1986 | 9 | 26 | 118 | 46 | 62 | 54 | 22 | 4017 |
| 9/27/1986 | 1986 | 9 | 27 | 119 | 39 | 70 | 54.5 | 22.5 | 4039.5 |
| 9/28/1986 | 1986 | 9 | 28 | 120 | 42 | 70 | 56 | 24 | 4063.5 |
| 9/29/1986 | 1986 | 9 | 29 | 121 | 39 | 70 | 54.5 | 22.5 | 4086 |
| 9/30/1986 | 1986 | 9 | 30 | 122 | 34 | 70 | 52 | 20 | 4106 |
| 10/1/1986 | 1986 | 10 | 1 | 123 | 37 | 74 | 55.5 | 23.5 | 4129.5 |
| 10/2/1986 | 1986 | 10 | 2 | 124 | 48 | 70 | 59 | 27 | 4156.5 |
| 10/3/1986 | 1986 | 10 | 3 | 125 | 39 | 67 | 53 | 21 | 4177.5 |
| 10/4/1986 | 1986 | 10 | 4 | 126 | 33 | 64 | 48.5 | 16.5 | 4194 |
| 10/5/1986 | 1986 | 10 | 5 | 127 | 35 | 66 | 50.5 | 18.5 | 4212.5 |
| 10/6/1986 | 1986 | 10 | 6 | 128 | 44 | 63 | 53.5 | 21.5 | 4234 |
| 10/7/1986 | 1986 | 10 | 7 | 129 | 36 | 64 | 50 | 18 | 4252 |
| 10/8/1986 | 1986 | 10 | 8 | 130 | 40 | 67 | 53.5 | 21.5 | 4273.5 |
| 10/9/1986 | 1986 | 10 | 9 | 131 | 40 | 67 | 53.5 | 21.5 | 4295 |
| 10/10/1986 | 1986 | 10 | 10 | 132 | 42 | 67 | 54.5 | 22.5 | 4317.5 |
| 10/11/1986 | 1986 | 10 | 11 | 133 | 41 | 53 | 47 | 15 | 4332.5 |
| 10/12/1986 | 1986 | 10 | 12 | 134 | 31 | 46 | 38.5 | 6.5 | 4339 |
| 10/13/1986 | 1986 | 10 | 13 | 135 | 26 | 47 | 36.5 | 4.5 | 4343.5 |
| 10/14/1986 | 1986 | 10 | 14 | 136 | 30 | 58 | 44 | 12 | 4355.5 |
| 10/15/1986 | 1986 | 10 | 15 | 137 | 32 | 62 | 47 | 15 | 4370.5 |
| 10/16/1986 | 1986 | 10 | 16 | 138 | 36 | 62 | 49 | 17 | 4387.5 |
| 10/17/1986 | 1986 | 10 | 17 | 139 | 36 | 63 | 49.5 | 17.5 | 4405 |
| 10/18/1986 | 1986 | 10 | 18 | 140 | 38 | 65 | 51.5 | 19.5 | 4424.5 |
| 10/19/1986 | 1986 | 10 | 19 | 141 | 53 | 62 | 57.5 | 25.5 | 4450 |
| 10/20/1986 | 1986 | 10 | 20 | 142 | 44 | 62 | 53 | 21 | 4471 |
| 10/21/1986 | 1986 | 10 | 21 | 143 | 29 | 55 | 42 | 10 | 4481 |
| 10/22/1986 | 1986 | 10 | 22 | 144 | 28 | 54 | 41 | 9 | 4490 |
| 10/23/1986 | 1986 | 10 | 23 | 145 | 34 | 60 | 47 | 15 | 4505 |
| 10/24/1986 | 1986 | 10 | 24 | 146 | 31 | 59 | 45 | 13 | 4518 |
| 10/25/1986 | 1986 | 10 | 25 | 147 | 31 | 59 | 45 | 13 | 4531 |
| 10/26/1986 | 1986 | 10 | 26 | 148 | 32 | 62 | 47 | 15 | 4546 |
| 10/27/1986 | 1986 | 10 | 27 | 149 | 30 | 64 | 47 | 15 | 4561 |
| 10/28/1986 | 1986 | 10 | 28 | 150 | 34 | 66 | 50 | 18 | 4579 |
| 10/29/1986 | 1986 | 10 | 29 | 151 | 36 | 64 | 50 | 18 | 4597 |
| 10/30/1986 | 1986 | 10 | 30 | 152 | 36 | 65 | 50.5 | 18.5 | 4615.5 |
| 10/31/1986 | 1986 | 10 | 31 | 153 | 39 | 64 | 51.5 | 19.5 | 4635 |
| 11/1/1986 | 1986 | 11 | 1 | 154 | 34 | 59 | 46.5 | 14.5 | 4649.5 |
| 11/2/1986 | 1986 | 11 | 2 | 155 | 32 | 58 | 45 | 13 | 4662.5 |
| 11/3/1986 | 1986 | 11 | 3 | 156 | 35 | 44 | 39.5 | 7.5 | 4670 |
| 11/4/1986 | 1986 | 11 | 4 | 157 | 31 | 41 | 36 | 4 | 4674 |
| 11/5/1986 | 1986 | 11 | 5 | 158 | 29 | 52 | 40.5 | 8.5 | 4682.5 |
| 11/6/1986 | 1986 | 11 | 6 | 159 | 29 | 54 | 41.5 | 9.5 | 4692 |
| 11/7/1986 | 1986 | 11 | 7 | 160 | 25 | 49 | 37 | 5 | 4697 |
| 11/8/1986 | 1986 | 11 | 8 | 161 | 25 | 49 | 37 | 5 | 4702 |
| 11/9/1986 | 1986 | 11 | 9 | 162 | 17 | 47 | 32 | 0 | 4702 |
| 11/10/1986 | 1986 | 11 | 10 | 163 | 24 | 47 | 35.5 | 3.5 | 4705.5 |
| 11/11/1986 | 1986 | 11 | 11 | 164 | 19 | 53 | 36 | 4 | 4709.5 |
| 11/12/1986 | 1986 | 11 | 12 | 165 | 19 | 52 | 35.5 | 3.5 | 4713 |
| 11/13/1986 | 1986 | 11 | 13 | 166 | 19 | 45 | 32 | 0 | 4713 |
| 11/14/1986 | 1986 | 11 | 14 | 167 | 16 | 58 | 37 | 5 | 4718 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/15/1986 | 1986 | 11 | 15 | 168 | 16 | 57 | 36.5 | 4.5 | 4722.5 |
| 11/16/1986 | 1986 | 11 | 16 | 169 | 35 | 55 | 45 | 13 | 4735.5 |
| 11/17/1986 | 1986 | 11 | 17 | 170 | 35 | 58 | 46.5 | 14.5 | 4750 |
| 11/18/1986 | 1986 | 11 | 18 | 171 | 37 | 57 | 47 | 15 | 4765 |
| 11/19/1986 | 1986 | 11 | 19 | 172 | 38 | 51 | 44.5 | 12.5 | 4777.5 |
| 11/20/1986 | 1986 | 11 | 20 | 173 | 31 | 56 | 43.5 | 11.5 | 4789 |
| 11/21/1986 | 1986 | 11 | 21 | 174 | 29 | 57 | 43 | 11 | 4800 |
| 11/22/1986 | 1986 | 11 | 22 | 175 | 32 | 48 | 40 | 8 | 4808 |
| 11/23/1986 | 1986 | 11 | 23 | 176 | 20 | 48 | 34 | 2 | 4810 |
| 11/24/1986 | 1986 | 11 | 24 | 177 | 19 | 43 | 31 | -1 | 4809 |
| 11/25/1986 | 1986 | 11 | 25 | 178 | 19 | 50 | 34.5 | 2.5 | 4811.5 |
| 11/26/1986 | 1986 | 11 | 26 | 179 | 26 | 46 | 36 | 4 | 4815.5 |
| 11/27/1986 | 1986 | 11 | 27 | 180 | 24 | 44 | 34 | 2 | 4817.5 |
| 11/28/1986 | 1986 | 11 | 28 | 181 | 24 | 56 | 40 | 8 | 4825.5 |
| 11/29/1986 | 1986 | 11 | 29 | 182 | 28 | 58 | 43 | 11 | 4836.5 |
| 11/30/1986 | 1986 | 11 | 30 | 183 | 19 | 51 | 35 | 3 | 4839.5 |
| 12/1/1986 | 1986 | 12 | 1 | 184 | 19 | 50 | 34.5 | 2.5 | 4842 |
| 12/2/1986 | 1986 | 12 | 2 | 185 | 19 | 53 | 36 | 4 | 4846 |
| 12/3/1986 | 1986 | 12 | 3 | 186 | 23 | 54 | 38.5 | 6.5 | 4852.5 |
| 12/4/1986 | 1986 | 12 | 4 | 187 | 27 | 50 | 38.5 | 6.5 | 4859 |
| 12/5/1986 | 1986 | 12 | 5 | 188 | 30 | 51 | 40.5 | 8.5 | 4867.5 |
| 12/6/1986 | 1986 | 12 | 6 | 189 | 33 | 48 | 40.5 | 8.5 | 4876 |
| 12/7/1986 | 1986 | 12 | 7 | 190 | 33 | 43 | 38 | 6 | 4882 |
| 12/8/1986 | 1986 | 12 | 8 | 191 | 27 | 40 | 33.5 | 1.5 | 4883.5 |
| 12/9/1986 | 1986 | 12 | 9 | 192 | 27 | 40 | 33.5 | 1.5 | 4885 |
| 12/10/1986 | 1986 | 12 | 10 | 193 | 9 | 27 | 18 | -14 | 4871 |
| 12/11/1986 | 1986 | 12 | 11 | 194 | 10 | 37 | 23.5 | -8.5 | 4862.5 |
| 12/12/1986 | 1986 | 12 | 12 | 195 | 10 | 44 | 27 | -5 | 4857.5 |
| 12/13/1986 | 1986 | 12 | 13 | 196 | 18 | 48 | 33 | 1 | 4858.5 |
| 12/14/1986 | 1986 | 12 | 14 | 197 | 19 | 50 | 34.5 | 2.5 | 4861 |
| 12/15/1986 | 1986 | 12 | 15 | 198 | 21 | 51 | 36 | 4 | 4865 |
| 12/16/1986 | 1986 | 12 | 16 | 199 | 28 | 46 | 37 | 5 | 4870 |
| 12/17/1986 | 1986 | 12 | 17 | 200 | 29 | 39 | 34 | 2 | 4872 |
| 12/18/1986 | 1986 | 12 | 18 | 201 | 26 | 33 | 29.5 | -2.5 | 4869.5 |
| 12/19/1986 | 1986 | 12 | 19 | 202 | 22 | 40 | 31 | -1 | 4868.5 |
| 12/20/1986 | 1986 | 12 | 20 | 203 | 22 | 43 | 32.5 | 0.5 | 4869 |
| 12/21/1986 | 1986 | 12 | 21 | 204 | 24 | 34 | 29 | -3 | 4866 |
| 12/22/1986 | 1986 | 12 | 22 | 205 | 24 | 38 | 31 | -1 | 4865 |
| 12/23/1986 | 1986 | 12 | 23 | 206 | 19 | 40 | 29.5 | -2.5 | 4862.5 |
| 12/24/1986 | 1986 | 12 | 24 | 207 | 28 | 40 | 34 | 2 | 4864.5 |
| 12/25/1986 | 1986 | 12 | 25 | 208 | 25 | 36 | 30.5 | -1.5 | 4863 |
| 12/26/1986 | 1986 | 12 | 26 | 209 | 13 | 37 | 25 | -7 | 4856 |
| 12/27/1986 | 1986 | 12 | 27 | 210 | 13 | 39 | 26 | -6 | 4850 |
| 12/28/1986 | 1986 | 12 | 28 | 211 | 16 | 38 | 27 | -5 | 4845 |
| 12/29/1986 | 1986 | 12 | 29 | 212 | 16 | 44 | 30 | -2 | 4843 |
| 12/30/1986 | 1986 | 12 | 30 | 213 | 20 | 44 | 32 | 0 | 4843 |
| 12/31/1986 | 1986 | 12 | 31 | 214 | 15 | 42 | 28.5 | -3.5 | 4839.5 |
| 1/1/1987 | 1987 | 1 | 1 | 215 | 17 | 48 | 32.5 | 0.5 | 4840 |
| 1/2/1987 | 1987 | 1 | 2 | 216 | 17 | 42 | 29.5 | -2.5 | 4837.5 |
| 1/3/1987 | 1987 | 1 | 3 | 217 | 20 | 45 | 32.5 | 0.5 | 4838 |
| 1/4/1987 | 1987 | 1 | 4 | 218 | 21 | 57 | 39 | 7 | 4845 |
| 1/5/1987 | 1987 | 1 | 5 | 219 | 29 | 52 | 40.5 | 8.5 | 4853.5 |
| 1/6/1987 | 1987 | 1 | 6 | 220 | 21 | 37 | 29 | -3 | 4850.5 |
| 1/7/1987 | 1987 | 1 | 7 | 221 | 22 | 41 | 31.5 | -0.5 | 4850 |
| 1/8/1987 | 1987 | 1 | 8 | 222 | 22 | 30 | 26 | -6 | 4844 |
| 1/9/1987 | 1987 | 1 | 9 | 223 | 12 | 29 | 20.5 | -11.5 | 4832.5 |
| 1/10/1987 | 1987 | 1 | 10 | 224 | 10 | 38 | 24 | -8 | 4824.5 |
| 1/11/1987 | 1987 | 1 | 11 | 225 | 13 | 46 | 29.5 | -2.5 | 4822 |
| 1/12/1987 | 1987 | 1 | 12 | 226 | 20 | 55 | 37.5 | 5.5 | 4827.5 |
| 1/13/1987 | 1987 | 1 | 13 | 227 | 24 | 57 | 40.5 | 8.5 | 4836 |
| 1/14/1987 | 1987 | 1 | 14 | 228 | 25 | 48 | 36.5 | 4.5 | 4840.5 |
| 1/15/1987 | 1987 | 1 | 15 | 229 | 24 | 43 | 33.5 | 1.5 | 4842 |
| 1/16/1987 | 1987 | 1 | 16 | 230 | 16 | 29 | 22.5 | -9.5 | 4832.5 |
| 1/17/1987 | 1987 | 1 | 17 | 231 | 9 | 20 | 14.5 | -17.5 | 4815 |
| 1/18/1987 | 1987 | 1 | 18 | 232 | 0 | 23 | 11.5 | -20.5 | 4794.5 |
| 1/19/1987 | 1987 | 1 | 19 | 233 | 1 | 23 | 12 | -20 | 4774.5 |
| 1/20/1987 | 1987 | 1 | 20 | 234 | 7 | 22 | 14.5 | -17.5 | 4757 |
| 1/21/1987 | 1987 | 1 | 21 | 235 | 4 | 30 | 17 | -15 | 4742 |
| 1/22/1987 | 1987 | 1 | 22 | 236 | 7 | 37 | 22 | -10 | 4732 |
| 1/23/1987 | 1987 | 1 | 23 | 237 | 17 | 41 | 29 | -3 | 4729 |
| 1/24/1987 | 1987 | 1 | 24 | 238 | 20 | 39 | 29.5 | -2.5 | 4726.5 |
| 1/25/1987 | 1987 | 1 | 25 | 239 | 18 | 45 | 31.5 | -0.5 | 4726 |
| 1/26/1987 | 1987 | 1 | 26 | 240 | 24 | 51 | 37.5 | 5.5 | 4731.5 |
| 1/27/1987 | 1987 | 1 | 27 | 241 | 23 | 51 | 37 | 5 | 4736.5 |
| 1/28/1987 | 1987 | 1 | 28 | 242 | 36 | 48 | 42 | 10 | 4746.5 |
| 1/29/1987 | 1987 | 1 | 29 | 243 | 26 | 47 | 36.5 | 4.5 | 4751 |
| 1/30/1987 | 1987 | 1 | 30 | 244 | 24 | 51 | 37.5 | 5.5 | 4756.5 |
| 1/31/1987 | 1987 | 1 | 31 | 245 | 30 | 46 | 38 | 6 | 4762.5 |
| 2/1/1987 | 1987 | 2 | 1 | 246 | 18 | 47 | 32.5 | 0.5 | 4763 |
| 2/2/1987 | 1987 | 2 | 2 | 247 | 24 | 54 | 39 | 7 | 4770 |
| 2/3/1987 | 1987 | 2 | 3 | 248 | 30 | 49 | 39.5 | 7.5 | 4777.5 |
| 2/4/1987 | 1987 | 2 | 4 | 249 | 29 | 44 | 36.5 | 4.5 | 4782 |
| 2/5/1987 | 1987 | 2 | 5 | 250 | 20 | 11 | 15.5 | -16.5 | 4765.5 |
| 2/6/1987 | 1987 | 2 | 6 | 251 | 18 | 44 | 31 | -1 | 4764.5 |
| 2/7/1987 | 1987 | 2 | 7 | 252 | 20 | 49 | 34.5 | 2.5 | 4767 |
| 2/8/1987 | 1987 | 2 | 8 | 253 | 27 | 49 | 38 | 6 | 4773 |
| 2/9/1987 | 1987 | 2 | 9 | 254 | 28 | 53 | 40.5 | 8.5 | 4781.5 |
| 2/10/1987 | 1987 | 2 | 10 | 255 | 29 | 54 | 41.5 | 9.5 | 4791 |
| 2/11/1987 | 1987 | 2 | 11 | 256 | 31 | 55 | 43 | 11 | 4802 |
| 2/12/1987 | 1987 | 2 | 12 | 257 | 30 | 49 | 39.5 | 7.5 | 4809.5 |
| 2/13/1987 | 1987 | 2 | 13 | 258 | 29 | 50 | 39.5 | 7.5 | 4817 |
| 2/14/1987 | 1987 | 2 | 14 | 259 | 27 | 48 | 37.5 | 5.5 | 4822.5 |
| 2/15/1987 | 1987 | 2 | 15 | 260 | 23 | 43 | 33 | 1 | 4823.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/16/1987 | 1987 | 2 | 16 | 261 | 28 | 39 | 33.5 | 1.5 | 4825 |
| 2/17/1987 | 1987 | 2 | 17 | 262 | 25 | 36 | 30.5 | -1.5 | 4823.5 |
| 2/18/1987 | 1987 | 2 | 18 | 263 | 17 | 33 | 25 | -7 | 4816.5 |
| 2/19/1987 | 1987 | 2 | 19 | 264 | 17 | 33 | 25 | -7 | 4809.5 |
| 2/20/1987 | 1987 | 2 | 20 | 265 | 14 | 33 | 23.5 | -8.5 | 4801 |
| 2/21/1987 | 1987 | 2 | 21 | 266 | 4 | 32 | 18 | -14 | 4787 |
| 2/22/1987 | 1987 | 2 | 22 | 267 | 9 | 40 | 24.5 | -7.5 | 4779.5 |
| 2/23/1987 | 1987 | 2 | 23 | 268 | 14 | 37 | 25.5 | -6.5 | 4773 |
| 2/24/1987 | 1987 | 2 | 24 | 269 | 22 | 39 | 30.5 | -1.5 | 4771.5 |
| 2/25/1987 | 1987 | 2 | 25 | 270 | 23 | 38 | 30.5 | -1.5 | 4770 |
| 2/26/1987 | 1987 | 2 | 26 | 271 | 23 | 36 | 29.5 | -2.5 | 4767.5 |
| 2/27/1987 | 1987 | 2 | 27 | 272 | 9 | 32 | 20.5 | -11.5 | 4756 |
| 2/28/1987 | 1987 | 2 | 28 | 273 | 11 | 36 | 23.5 | -8.5 | 4747.5 |
| 3/1/1987 | 1987 | 3 | 1 | 274 | 13 | 44 | 28.5 | -3.5 | 4744 |
| 3/2/1987 | 1987 | 3 | 2 | 275 | 20 | 43 | 31.5 | -0.5 | 4743.5 |
| 3/3/1987 | 1987 | 3 | 3 | 276 | 20 | 48 | 34 | 2 | 4745.5 |
| 3/4/1987 | 1987 | 3 | 4 | 277 | 24 | 55 | 39.5 | 7.5 | 4753 |
| 3/5/1987 | 1987 | 3 | 5 | 278 | 26 | 60 | 43 | 11 | 4764 |
| 3/6/1987 | 1987 | 3 | 6 | 279 | 25 | 63 | 44 | 12 | 4776 |
| 3/7/1987 | 1987 | 3 | 7 | 280 | 25 | 63 | 44 | 12 | 4788 |
| 3/8/1987 | 1987 | 3 | 8 | 281 | 30 | 52 | 41 | 9 | 4797 |
| 3/9/1987 | 1987 | 3 | 9 | 282 | 34 | 46 | 40 | 8 | 4805 |
| 3/10/1987 | 1987 | 3 | 10 | 283 | 31 | 51 | 41 | 9 | 4814 |
| 3/11/1987 | 1987 | 3 | 11 | 284 | 26 | 53 | 39.5 | 7.5 | 4821.5 |
| 3/12/1987 | 1987 | 3 | 12 | 285 | 29 | 56 | 42.5 | 10.5 | 4832 |
| 3/13/1987 | 1987 | 3 | 13 | 286 | 33 | 62 | 47.5 | 15.5 | 4847.5 |
| 3/14/1987 | 1987 | 3 | 14 | 287 | 29 | 57 | 43 | 11 | 4858.5 |
| 3/15/1987 | 1987 | 3 | 15 | 288 | 35 | 53 | 44 | 12 | 4870.5 |
| 3/16/1987 | 1987 | 3 | 16 | 289 | 21 | 53 | 37 | 5 | 4875.5 |
| 3/17/1987 | 1987 | 3 | 17 | 290 | 18 | 37 | 27.5 | -4.5 | 4871 |
| 3/18/1987 | 1987 | 3 | 18 | 291 | 26 | 55 | 40.5 | 8.5 | 4879.5 |
| 3/19/1987 | 1987 | 3 | 19 | 292 | 29 | 53 | 41 | 9 | 4888.5 |
| 3/20/1987 | 1987 | 3 | 20 | 293 | 23 | 53 | 38 | 6 | 4894.5 |
| 3/21/1987 | 1987 | 3 | 21 | 294 | 21 | 53 | 37 | 5 | 4899.5 |
| 3/22/1987 | 1987 | 3 | 22 | 295 | 24 | 49 | 36.5 | 4.5 | 4904 |
| 3/23/1987 | 1987 | 3 | 23 | 296 | 20 | 40 | 30 | -2 | 4902 |
| 3/24/1987 | 1987 | 3 | 24 | 297 | 23 | 42 | 32.5 | 0.5 | 4902.5 |
| 3/25/1987 | 1987 | 3 | 25 | 298 | 20 | 41 | 30.5 | -1.5 | 4901 |
| 3/26/1987 | 1987 | 3 | 26 | 299 | 22 | 42 | 32 | 0 | 4901 |
| 3/27/1987 | 1987 | 3 | 27 | 300 | 27 | 43 | 35 | 3 | 4904 |
| 3/28/1987 | 1987 | 3 | 28 | 301 | 17 | 35 | 26 | -6 | 4898 |
| 3/29/1987 | 1987 | 3 | 29 | 302 | 17 | 29 | 23 | -9 | 4889 |
| 3/30/1987 | 1987 | 3 | 30 | 303 | 9 | 43 | 26 | -6 | 4883 |
| 3/31/1987 | 1987 | 3 | 31 | 304 | 25 | 56 | 40.5 | 8.5 | 4891.5 |
| 4/1/1987 | 1987 | 4 | 1 | 305 | 28 | 56 | 42 | 10 | 4901.5 |
| 4/2/1987 | 1987 | 4 | 2 | 306 | 29 | 57 | 43 | 11 | 4912.5 |
| 4/3/1987 | 1987 | 4 | 3 | 307 | 26 | 59 | 42.5 | 10.5 | 4923 |
| 4/4/1987 | 1987 | 4 | 4 | 308 | 26 | 59 | 42.5 | 10.5 | 4933.5 |
| 4/5/1987 | 1987 | 4 | 5 | 309 | 26 | 59 | 42.5 | 10.5 | 4944 |
| 4/6/1987 | 1987 | 4 | 6 | 310 | 26 | 59 | 42.5 | 10.5 | 4954.5 |
| 4/7/1987 | 1987 | 4 | 7 | 311 | 26 | 59 | 42.5 | 10.5 | 4965 |
| 4/8/1987 | 1987 | 4 | 8 | 312 | 26 | 59 | 42.5 | 10.5 | 4975.5 |
| 4/9/1987 | 1987 | 4 | 9 | 313 | 26 | 62 | 44 | 12 | 4987.5 |
| 4/10/1987 | 1987 | 4 | 10 | 314 | 32 | 63 | 47.5 | 15.5 | 5003 |
| 4/11/1987 | 1987 | 4 | 11 | 315 | 35 | 65 | 50 | 18 | 5021 |
| 4/12/1987 | 1987 | 4 | 12 | 316 | 30 | 59 | 44.5 | 12.5 | 5033.5 |
| 4/13/1987 | 1987 | 4 | 13 | 317 | 28 | 49 | 38.5 | 6.5 | 5040 |
| 4/14/1987 | 1987 | 4 | 14 | 318 | 29 | 64 | 46.5 | 14.5 | 5054.5 |
| 4/15/1987 | 1987 | 4 | 15 | 319 | 35 | 71 | 53 | 21 | 5075.5 |
| 4/16/1987 | 1987 | 4 | 16 | 320 | 35 | 74 | 54.5 | 22.5 | 5098 |
| 4/17/1987 | 1987 | 4 | 17 | 321 | 42 | 76 | 59 | 27 | 5125 |
| 4/18/1987 | 1987 | 4 | 18 | 322 | 43 | 75 | 59 | 27 | 5152 |
| 4/19/1987 | 1987 | 4 | 19 | 323 | 43 | 75 | 59 | 27 | 5179 |
| 4/20/1987 | 1987 | 4 | 20 | 324 | 26 | 65 | 45.5 | 13.5 | 5192.5 |
| 4/21/1987 | 1987 | 4 | 21 | 325 | 29 | 62 | 45.5 | 13.5 | 5206 |
| 4/22/1987 | 1987 | 4 | 22 | 326 | 29 | 67 | 48 | 16 | 5222 |
| 4/23/1987 | 1987 | 4 | 23 | 327 | 38 | 70 | 54 | 22 | 5244 |
| 4/24/1987 | 1987 | 4 | 24 | 328 | 40 | 69 | 54.5 | 22.5 | 5266.5 |
| 4/25/1987 | 1987 | 4 | 25 | 329 | 38 | 69 | 53.5 | 21.5 | 5288 |
| 4/26/1987 | 1987 | 4 | 26 | 330 | 39 | 68 | 53.5 | 21.5 | 5309.5 |
| 4/27/1987 | 1987 | 4 | 27 | 331 | 47 | 68 | 57.5 | 25.5 | 5335 |
| 4/28/1987 | 1987 | 4 | 28 | 332 | 41 | 66 | 53.5 | 21.5 | 5356.5 |
| 4/29/1987 | 1987 | 4 | 29 | 333 | 39 | 71 | 55 | 23 | 5379.5 |
| 4/30/1987 | 1987 | 4 | 30 | 334 | 46 | 71 | 58.5 | 26.5 | 5406 |
| 5/1/1987 | 1987 | 5 | 1 | 335 | 44 | 66 | 55 | 23 | 5429 |
| 5/2/1987 | 1987 | 5 | 2 | 336 | 35 | 67 | 51 | 19 | 5448 |
| 5/3/1987 | 1987 | 5 | 3 | 337 | 36 | 61 | 48.5 | 16.5 | 5464.5 |
| 5/4/1987 | 1987 | 5 | 4 | 338 | 39 | 65 | 52 | 20 | 5484.5 |
| 5/5/1987 | 1987 | 5 | 5 | 339 | 40 | 64 | 52 | 20 | 5504.5 |
| 5/6/1987 | 1987 | 5 | 6 | 340 | 38 | 65 | 51.5 | 19.5 | 5524 |
| 5/7/1987 | 1987 | 5 | 7 | 341 | 41 | 65 | 53 | 21 | 5545 |
| 5/8/1987 | 1987 | 5 | 8 | 342 | 40 | 69 | 54.5 | 22.5 | 5567.5 |
| 5/9/1987 | 1987 | 5 | 9 | 343 | 44 | 73 | 58.5 | 26.5 | 5594 |
| 5/10/1987 | 1987 | 5 | 10 | 344 | 52 | 69 | 60.5 | 28.5 | 5622.5 |
| 5/11/1987 | 1987 | 5 | 11 | 345 | 40 | 71 | 55.5 | 23.5 | 5646 |
| 5/12/1987 | 1987 | 5 | 12 | 346 | 43 | 69 | 56 | 24 | 5670 |
| 5/13/1987 | 1987 | 5 | 13 | 347 | 42 | 74 | 58 | 26 | 5696 |
| 5/14/1987 | 1987 | 5 | 14 | 348 | 49 | 74 | 61.5 | 29.5 | 5725.5 |
| 5/15/1987 | 1987 | 5 | 15 | 349 | 44 | 65 | 54.5 | 22.5 | 5748 |
| 5/16/1987 | 1987 | 5 | 16 | 350 | 44 | 68 | 56 | 24 | 5772 |
| 5/17/1987 | 1987 | 5 | 17 | 351 | 43 | 74 | 58.5 | 26.5 | 5798.5 |
| 5/18/1987 | 1987 | 5 | 18 | 352 | 44 | 71 | 57.5 | 25.5 | 5824 |
| 5/19/1987 | 1987 | 5 | 19 | 353 | 47 | 65 | 56 | 24 | 5848 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/20/1987 | 1987 | 5 | 20 | 354 | 45 | 63 | 54 | 22 | 5870 |
| 5/21/1987 | 1987 | 5 | 21 | 355 | 47 | 65 | 56 | 24 | 5894 |
| 5/22/1987 | 1987 | 5 | 22 | 356 | 38 | 66 | 52 | 20 | 5914 |
| 5/23/1987 | 1987 | 5 | 23 | 357 | 39 | 63 | 51 | 19 | 5933 |
| 5/24/1987 | 1987 | 5 | 24 | 358 | 40 | 67 | 53.5 | 21.5 | 5954.5 |
| 5/25/1987 | 1987 | 5 | 25 | 359 | 41 | 67 | 54 | 22 | 5976.5 |
| 5/26/1987 | 1987 | 5 | 26 | 360 | 38 | 64 | 51 | 19 | 5995.5 |
| 5/27/1987 | 1987 | 5 | 27 | 361 | 34 | 64 | 49 | 17 | 6012.5 |
| 5/28/1987 | 1987 | 5 | 28 | 362 | 41 | 63 | 52 | 20 | 6032.5 |
| 5/29/1987 | 1987 | 5 | 29 | 363 | 37 | 68 | 52.5 | 20.5 | 6053 |
| 5/30/1987 | 1987 | 5 | 30 | 364 | 40 | 70 | 55 | 23 | 6076 |
| 5/31/1987 | 1987 | 5 | 31 | 365 | 44 | 76 | 60 | 28 | 6104 |
| 6/1/1987 | 1987 | 6 | 1 | 1 | 49 | 78 | 63.5 | 31.5 | 31.5 |
| 6/2/1987 | 1987 | 6 | 2 | 2 | 47 | 78 | 62.5 | 30.5 | 62 |
| 6/3/1987 | 1987 | 6 | 3 | 3 | 44 | 78 | 61 | 29 | 91 |
| 6/4/1987 | 1987 | 6 | 4 | 4 | 47 | 75 | 61 | 29 | 120 |
| 6/5/1987 | 1987 | 6 | 5 | 5 | 49 | 74 | 61.5 | 29.5 | 149.5 |
| 6/6/1987 | 1987 | 6 | 6 | 6 | 46 | 76 | 61 | 29 | 178.5 |
| 6/7/1987 | 1987 | 6 | 7 | 7 | 45 | 76 | 60.5 | 28.5 | 207 |
| 6/8/1987 | 1987 | 6 | 8 | 8 | 50 | 62 | 56 | 24 | 231 |
| 6/9/1987 | 1987 | 6 | 9 | 9 | 43 | 75 | 59 | 27 | 258 |
| 6/10/1987 | 1987 | 6 | 10 | 10 | 48 | 79 | 63.5 | 31.5 | 289.5 |
| 6/11/1987 | 1987 | 6 | 11 | 11 | 49 | 83 | 66 | 34 | 323.5 |
| 6/12/1987 | 1987 | 6 | 12 | 12 | 49 | 82 | 65.5 | 33.5 | 357 |
| 6/13/1987 | 1987 | 6 | 13 | 13 | 52 | 85 | 68.5 | 36.5 | 393.5 |
| 6/14/1987 | 1987 | 6 | 14 | 14 | 54 | 86 | 70 | 38 | 431.5 |
| 6/15/1987 | 1987 | 6 | 15 | 15 | 57 | 83 | 70 | 38 | 469.5 |
| 6/16/1987 | 1987 | 6 | 16 | 16 | 51 | 81 | 66 | 34 | 503.5 |
| 6/17/1987 | 1987 | 6 | 17 | 17 | 49 | 83 | 66 | 34 | 537.5 |
| 6/18/1987 | 1987 | 6 | 18 | 18 | 48 | 85 | 66.5 | 34.5 | 572 |
| 6/19/1987 | 1987 | 6 | 19 | 19 | 49 | 84 | 66.5 | 34.5 | 606.5 |
| 6/20/1987 | 1987 | 6 | 20 | 20 | 51 | 82 | 66.5 | 34.5 | 641 |
| 6/21/1987 | 1987 | 6 | 21 | 21 | 55 | 83 | 69 | 37 | 678 |
| 6/22/1987 | 1987 | 6 | 22 | 22 | 52 | 83 | 67.5 | 35.5 | 713.5 |
| 6/23/1987 | 1987 | 6 | 23 | 23 | 52 | 88 | 70 | 38 | 751.5 |
| 6/24/1987 | 1987 | 6 | 24 | 24 | 56 | 89 | 72.5 | 40.5 | 792 |
| 6/25/1987 | 1987 | 6 | 25 | 25 | 56 | 87 | 71.5 | 39.5 | 831.5 |
| 6/26/1987 | 1987 | 6 | 26 | 26 | 53 | 87 | 70 | 38 | 869.5 |
| 6/27/1987 | 1987 | 6 | 27 | 27 | 51 | 83 | 67 | 35 | 904.5 |
| 6/28/1987 | 1987 | 6 | 28 | 28 | 51 | 80 | 65.5 | 33.5 | 938 |
| 6/29/1987 | 1987 | 6 | 29 | 29 | 48 | 77 | 62.5 | 30.5 | 968.5 |
| 6/30/1987 | 1987 | 6 | 30 | 30 | 48 | 83 | 65.5 | 33.5 | 1002 |
| 7/1/1987 | 1987 | 7 | 1 | 31 | 52 | 84 | 68 | 36 | 1038 |
| 7/2/1987 | 1987 | 7 | 2 | 32 | 54 | 86 | 70 | 38 | 1076 |
| 7/3/1987 | 1987 | 7 | 3 | 33 | 54 | 86 | 70 | 38 | 1114 |
| 7/4/1987 | 1987 | 7 | 4 | 34 | 54 | 86 | 70 | 38 | 1152 |
| 7/5/1987 | 1987 | 7 | 5 | 35 | 49 | 86 | 67.5 | 35.5 | 1187.5 |
| 7/6/1987 | 1987 | 7 | 6 | 36 | 49 | 85 | 67 | 35 | 1222.5 |
| 7/7/1987 | 1987 | 7 | 7 | 37 | 57 | 87 | 72 | 40 | 1262.5 |
| 7/8/1987 | 1987 | 7 | 8 | 38 | 57 | 88 | 72.5 | 40.5 | 1303 |
| 7/9/1987 | 1987 | 7 | 9 | 39 | 56 | 86 | 71 | 39 | 1342 |
| 7/10/1987 | 1987 | 7 | 10 | 40 | 56 | 86 | 71 | 39 | 1381 |
| 7/11/1987 | 1987 | 7 | 11 | 41 | 52 | 84 | 68 | 36 | 1417 |
| 7/12/1987 | 1987 | 7 | 12 | 42 | 59 | 84 | 71.5 | 39.5 | 1456.5 |
| 7/13/1987 | 1987 | 7 | 13 | 43 | 53 | 83 | 68 | 36 | 1492.5 |
| 7/14/1987 | 1987 | 7 | 14 | 44 | 51 | 85 | 68 | 36 | 1528.5 |
| 7/15/1987 | 1987 | 7 | 15 | 45 | 51 | 85 | 68 | 36 | 1564.5 |
| 7/16/1987 | 1987 | 7 | 16 | 46 | 63 | 85 | 74 | 42 | 1606.5 |
| 7/17/1987 | 1987 | 7 | 17 | 47 | 52 | 76 | 64 | 32 | 1638.5 |
| 7/18/1987 | 1987 | 7 | 18 | 48 | 49 | 81 | 65 | 33 | 1671.5 |
| 7/19/1987 | 1987 | 7 | 19 | 49 | 55 | 83 | 69 | 37 | 1708.5 |
| 7/20/1987 | 1987 | 7 | 20 | 50 | 53 | 86 | 69.5 | 37.5 | 1746 |
| 7/21/1987 | 1987 | 7 | 21 | 51 | 57 | 87 | 72 | 40 | 1786 |
| 7/22/1987 | 1987 | 7 | 22 | 52 | 57 | 86 | 71.5 | 39.5 | 1825.5 |
| 7/23/1987 | 1987 | 7 | 23 | 53 | 57 | 89 | 73 | 41 | 1866.5 |
| 7/24/1987 | 1987 | 7 | 24 | 54 | 60 | 89 | 74.5 | 42.5 | 1909 |
| 7/25/1987 | 1987 | 7 | 25 | 55 | 55 | 82 | 68.5 | 36.5 | 1945.5 |
| 7/26/1987 | 1987 | 7 | 26 | 56 | 57 | 83 | 70 | 38 | 1983.5 |
| 7/27/1987 | 1987 | 7 | 27 | 57 | 54 | 83 | 68.5 | 36.5 | 2020 |
| 7/28/1987 | 1987 | 7 | 28 | 58 | 58 | 79 | 68.5 | 36.5 | 2056.5 |
| 7/29/1987 | 1987 | 7 | 29 | 59 | 55 | 82 | 68.5 | 36.5 | 2093 |
| 7/30/1987 | 1987 | 7 | 30 | 60 | 57 | 79 | 68 | 36 | 2129 |
| 7/31/1987 | 1987 | 7 | 31 | 61 | 56 | 79 | 67.5 | 35.5 | 2164.5 |
| 8/1/1987 | 1987 | 8 | 1 | 62 | 54 | 84 | 69 | 37 | 2201.5 |
| 8/2/1987 | 1987 | 8 | 2 | 63 | 58 | 79 | 68.5 | 36.5 | 2238 |
| 8/3/1987 | 1987 | 8 | 3 | 64 | 55 | 80 | 67.5 | 35.5 | 2273.5 |
| 8/4/1987 | 1987 | 8 | 4 | 65 | 59 | 80 | 69.5 | 37.5 | 2311 |
| 8/5/1987 | 1987 | 8 | 5 | 66 | 55 | 80 | 67.5 | 35.5 | 2346.5 |
| 8/6/1987 | 1987 | 8 | 6 | 67 | 55 | 83 | 69 | 37 | 2383.5 |
| 8/7/1987 | 1987 | 8 | 7 | 68 | 57 | 72 | 64.5 | 32.5 | 2416 |
| 8/8/1987 | 1987 | 8 | 8 | 69 | 56 | 78 | 67 | 35 | 2451 |
| 8/9/1987 | 1987 | 8 | 9 | 70 | 55 | 78 | 66.5 | 34.5 | 2485.5 |
| 8/10/1987 | 1987 | 8 | 10 | 71 | 56 | 82 | 69 | 37 | 2522.5 |
| 8/11/1987 | 1987 | 8 | 11 | 72 | 59 | 80 | 69.5 | 37.5 | 2560 |
| 8/12/1987 | 1987 | 8 | 12 | 73 | 56 | 77 | 66.5 | 34.5 | 2594.5 |
| 8/13/1987 | 1987 | 8 | 13 | 74 | 52 | 79 | 65.5 | 33.5 | 2628 |
| 8/14/1987 | 1987 | 8 | 14 | 75 | 50 | 78 | 64 | 32 | 2660 |
| 8/15/1987 | 1987 | 8 | 15 | 76 | 50 | 78 | 64 | 32 | 2692 |
| 8/16/1987 | 1987 | 8 | 16 | 77 | 51 | 82 | 66.5 | 34.5 | 2726.5 |
| 8/17/1987 | 1987 | 8 | 17 | 78 | 50 | 82 | 66 | 34 | 2760.5 |
| 8/18/1987 | 1987 | 8 | 18 | 79 | 53 | 86 | 69.5 | 37.5 | 2798 |
| 8/19/1987 | 1987 | 8 | 19 | 80 | 53 | 87 | 70 | 38 | 2836 |
| 8/20/1987 | 1987 | 8 | 20 | 81 | 60 | 87 | 73.5 | 41.5 | 2877.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/21/1987 | 1987 | 8 | 21 | 82 | 56 | 76 | 66 | 34 | 2911.5 |
| 8/22/1987 | 1987 | 8 | 22 | 83 | 52 | 79 | 65.5 | 33.5 | 2945 |
| 8/23/1987 | 1987 | 8 | 23 | 84 | 54 | 76 | 65 | 33 | 2978 |
| 8/24/1987 | 1987 | 8 | 24 | 85 | 55 | 72 | 63.5 | 31.5 | 3009.5 |
| 8/25/1987 | 1987 | 8 | 25 | 86 | 52 | 70 | 61 | 29 | 3038.5 |
| 8/26/1987 | 1987 | 8 | 26 | 87 | 49 | 67 | 58 | 26 | 3064.5 |
| 8/27/1987 | 1987 | 8 | 27 | 88 | 47 | 70 | 58.5 | 26.5 | 3091 |
| 8/28/1987 | 1987 | 8 | 28 | 89 | 44 | 74 | 59 | 27 | 3118 |
| 8/29/1987 | 1987 | 8 | 29 | 90 | 48 | 76 | 62 | 30 | 3148 |
| 8/30/1987 | 1987 | 8 | 30 | 91 | 46 | 77 | 61.5 | 29.5 | 3177.5 |
| 8/31/1987 | 1987 | 8 | 31 | 92 | 51 | 79 | 65 | 33 | 3210.5 |
| 9/1/1987 | 1987 | 9 | 1 | 93 | 52 | 77 | 64.5 | 32.5 | 3243 |
| 9/2/1987 | 1987 | 9 | 2 | 94 | 48 | 79 | 63.5 | 31.5 | 3274.5 |
| 9/3/1987 | 1987 | 9 | 3 | 95 | 48 | 80 | 64 | 32 | 3306.5 |
| 9/4/1987 | 1987 | 9 | 4 | 96 | 53 | 75 | 64 | 32 | 3338.5 |
| 9/5/1987 | 1987 | 9 | 5 | 97 | 49 | 71 | 60 | 28 | 3366.5 |
| 9/6/1987 | 1987 | 9 | 6 | 98 | 48 | 71 | 59.5 | 27.5 | 3394 |
| 9/7/1987 | 1987 | 9 | 7 | 99 | 47 | 76 | 61.5 | 29.5 | 3423.5 |
| 9/8/1987 | 1987 | 9 | 8 | 100 | 46 | 76 | 61 | 29 | 3452.5 |
| 9/9/1987 | 1987 | 9 | 9 | 101 | 49 | 77 | 63 | 31 | 3483.5 |
| 9/10/1987 | 1987 | 9 | 10 | 102 | 47 | 77 | 62 | 30 | 3513.5 |
| 9/11/1987 | 1987 | 9 | 11 | 103 | 47 | 76 | 61.5 | 29.5 | 3543 |
| 9/12/1987 | 1987 | 9 | 12 | 104 | 47 | 76 | 61.5 | 29.5 | 3572.5 |
| 9/13/1987 | 1987 | 9 | 13 | 105 | 47 | 78 | 62.5 | 30.5 | 3603 |
| 9/14/1987 | 1987 | 9 | 14 | 106 | 46 | 69 | 57.5 | 25.5 | 3628.5 |
| 9/15/1987 | 1987 | 9 | 15 | 107 | 39 | 69 | 54 | 22 | 3650.5 |
| 9/16/1987 | 1987 | 9 | 16 | 108 | 44 | 76 | 60 | 28 | 3678.5 |
| 9/17/1987 | 1987 | 9 | 17 | 109 | 53 | 73 | 63 | 31 | 3709.5 |
| 9/18/1987 | 1987 | 9 | 18 | 110 | 48 | 73 | 60.5 | 28.5 | 3738 |
| 9/19/1987 | 1987 | 9 | 19 | 111 | 47 | 71 | 59 | 27 | 3765 |
| 9/20/1987 | 1987 | 9 | 20 | 112 | 41 | 76 | 58.5 | 26.5 | 3791.5 |
| 9/21/1987 | 1987 | 9 | 21 | 113 | 43 | 73 | 58 | 26 | 3817.5 |
| 9/22/1987 | 1987 | 9 | 22 | 114 | 46 | 71 | 58.5 | 26.5 | 3844 |
| 9/23/1987 | 1987 | 9 | 23 | 115 | 46 | 74 | 60 | 28 | 3872 |
| 9/24/1987 | 1987 | 9 | 24 | 116 | 47 | 74 | 60.5 | 28.5 | 3900.5 |
| 9/25/1987 | 1987 | 9 | 25 | 117 | 49 | 64 | 56.5 | 24.5 | 3925 |
| 9/26/1987 | 1987 | 9 | 26 | 118 | 43 | 72 | 57.5 | 25.5 | 3950.5 |
| 9/27/1987 | 1987 | 9 | 27 | 119 | 47 | 74 | 60.5 | 28.5 | 3979 |
| 9/28/1987 | 1987 | 9 | 28 | 120 | 44 | 74 | 59 | 27 | 4006 |
| 9/29/1987 | 1987 | 9 | 29 | 121 | 42 | 75 | 58.5 | 26.5 | 4032.5 |
| 9/30/1987 | 1987 | 9 | 30 | 122 | 42 | 70 | 56 | 24 | 4056.5 |
| 10/1/1987 | 1987 | 10 | 1 | 123 | 42 | 74 | 58 | 26 | 4082.5 |
| 10/2/1987 | 1987 | 10 | 2 | 124 | 42 | 74 | 58 | 26 | 4108.5 |
| 10/3/1987 | 1987 | 10 | 3 | 125 | 43 | 74 | 58.5 | 26.5 | 4135 |
| 10/4/1987 | 1987 | 10 | 4 | 126 | 44 | 76 | 60 | 28 | 4163 |
| 10/5/1987 | 1987 | 10 | 5 | 127 | 44 | 77 | 60.5 | 28.5 | 4191.5 |
| 10/6/1987 | 1987 | 10 | 6 | 128 | 42 | 76 | 59 | 27 | 4218.5 |
| 10/7/1987 | 1987 | 10 | 7 | 129 | 43 | 78 | 60.5 | 28.5 | 4247 |
| 10/8/1987 | 1987 | 10 | 8 | 130 | 44 | 75 | 59.5 | 27.5 | 4274.5 |
| 10/9/1987 | 1987 | 10 | 9 | 131 | 44 | 75 | 59.5 | 27.5 | 4302 |
| 10/10/1987 | 1987 | 10 | 10 | 132 | 46 | 73 | 59.5 | 27.5 | 4329.5 |
| 10/11/1987 | 1987 | 10 | 11 | 133 | 46 | 74 | 60 | 28 | 4357.5 |
| 10/12/1987 | 1987 | 10 | 12 | 134 | 47 | 75 | 61 | 29 | 4386.5 |
| 10/13/1987 | 1987 | 10 | 13 | 135 | 48 | 70 | 59 | 27 | 4413.5 |
| 10/14/1987 | 1987 | 10 | 14 | 136 | 37 | 60 | 48.5 | 16.5 | 4430 |
| 10/15/1987 | 1987 | 10 | 15 | 137 | 39 | 58 | 48.5 | 16.5 | 4446.5 |
| 10/16/1987 | 1987 | 10 | 16 | 138 | 34 | 64 | 49 | 17 | 4463.5 |
| 10/17/1987 | 1987 | 10 | 17 | 139 | 35 | 66 | 50.5 | 18.5 | 4482 |
| 10/18/1987 | 1987 | 10 | 18 | 140 | 34 | 65 | 49.5 | 17.5 | 4499.5 |
| 10/19/1987 | 1987 | 10 | 19 | 141 | 35 | 64 | 49.5 | 17.5 | 4517 |
| 10/20/1987 | 1987 | 10 | 20 | 142 | 32 | 65 | 48.5 | 16.5 | 4533.5 |
| 10/21/1987 | 1987 | 10 | 21 | 143 | 33 | 67 | 50 | 18 | 4551.5 |
| 10/22/1987 | 1987 | 10 | 22 | 144 | 38 | 63 | 50.5 | 18.5 | 4570 |
| 10/23/1987 | 1987 | 10 | 23 | 145 | 42 | 60 | 51 | 19 | 4589 |
| 10/24/1987 | 1987 | 10 | 24 | 146 | 41 | 59 | 50 | 18 | 4607 |
| 10/25/1987 | 1987 | 10 | 25 | 147 | 45 | 64 | 54.5 | 22.5 | 4629.5 |
| 10/26/1987 | 1987 | 10 | 26 | 148 | 36 | 64 | 50 | 18 | 4647.5 |
| 10/27/1987 | 1987 | 10 | 27 | 149 | 37 | 68 | 52.5 | 20.5 | 4668 |
| 10/28/1987 | 1987 | 10 | 28 | 150 | 40 | 71 | 55.5 | 23.5 | 4691.5 |
| 10/29/1987 | 1987 | 10 | 29 | 151 | 41 | 60 | 50.5 | 18.5 | 4710 |
| 10/30/1987 | 1987 | 10 | 30 | 152 | 37 | 59 | 48 | 16 | 4726 |
| 10/31/1987 | 1987 | 10 | 31 | 153 | 35 | 55 | 45 | 13 | 4739 |
| 11/1/1987 | 1987 | 11 | 1 | 154 | 37 | 61 | 49 | 17 | 4756 |
| 11/2/1987 | 1987 | 11 | 2 | 155 | 38 | 56 | 47 | 15 | 4771 |
| 11/3/1987 | 1987 | 11 | 3 | 156 | 34 | 61 | 47.5 | 15.5 | 4786.5 |
| 11/4/1987 | 1987 | 11 | 4 | 157 | 37 | 64 | 50.5 | 18.5 | 4805 |
| 11/5/1987 | 1987 | 11 | 5 | 158 | 41 | 58 | 49.5 | 17.5 | 4822.5 |
| 11/6/1987 | 1987 | 11 | 6 | 159 | 41 | 53 | 47 | 15 | 4837.5 |
| 11/7/1987 | 1987 | 11 | 7 | 160 | 36 | 46 | 41 | 9 | 4846.5 |
| 11/8/1987 | 1987 | 11 | 8 | 161 | 29 | 52 | 40.5 | 8.5 | 4855 |
| 11/9/1987 | 1987 | 11 | 9 | 162 | 27 | 55 | 41 | 9 | 4864 |
| 11/10/1987 | 1987 | 11 | 10 | 163 | 26 | 56 | 41 | 9 | 4873 |
| 11/11/1987 | 1987 | 11 | 11 | 164 | 28 | 52 | 40 | 8 | 4881 |
| 11/12/1987 | 1987 | 11 | 12 | 165 | 24 | 55 | 39.5 | 7.5 | 4888.5 |
| 11/13/1987 | 1987 | 11 | 13 | 166 | 28 | 58 | 43 | 11 | 4899.5 |
| 11/14/1987 | 1987 | 11 | 14 | 167 | 33 | 52 | 42.5 | 10.5 | 4910 |
| 11/15/1987 | 1987 | 11 | 15 | 168 | 26 | 36 | 31 | -1 | 4909 |
| 11/16/1987 | 1987 | 11 | 16 | 169 | 20 | 41 | 30.5 | -1.5 | 4907.5 |
| 11/17/1987 | 1987 | 11 | 17 | 170 | 26 | 45 | 35.5 | 3.5 | 4911 |
| 11/18/1987 | 1987 | 11 | 18 | 171 | 13 | 42 | 27.5 | -4.5 | 4906.5 |
| 11/19/1987 | 1987 | 11 | 19 | 172 | 17 | 52 | 34.5 | 2.5 | 4909 |
| 11/20/1987 | 1987 | 11 | 20 | 173 | 23 | 61 | 42 | 10 | 4919 |
| 11/21/1987 | 1987 | 11 | 21 | 174 | 27 | 56 | 41.5 | 9.5 | 4928.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/22/1987 | 1987 | 11 | 22 | 175 | 22 | 52 | 37 | 5 | 4933.5 |
| 11/23/1987 | 1987 | 11 | 23 | 176 | 25 | 52 | 38.5 | 6.5 | 4940 |
| 11/24/1987 | 1987 | 11 | 24 | 177 | 23 | 46 | 34.5 | 2.5 | 4942.5 |
| 11/25/1987 | 1987 | 11 | 25 | 178 | 17 | 52 | 34.5 | 2.5 | 4945 |
| 11/26/1987 | 1987 | 11 | 26 | 179 | 23 | 44 | 33.5 | 1.5 | 4946.5 |
| 11/27/1987 | 1987 | 11 | 27 | 180 | 22 | 46 | 34 | 2 | 4948.5 |
| 11/28/1987 | 1987 | 11 | 28 | 181 | 14 | 46 | 30 | -2 | 4946.5 |
| 11/29/1987 | 1987 | 11 | 29 | 182 | 17 | 45 | 31 | -1 | 4945.5 |
| 11/30/1987 | 1987 | 11 | 30 | 183 | 17 | 42 | 29.5 | -2.5 | 4943 |
| 12/1/1987 | 1987 | 12 | 1 | 184 | 17 | 46 | 31.5 | -0.5 | 4942.5 |
| 12/2/1987 | 1987 | 12 | 2 | 185 | 23 | 53 | 38 | 6 | 4948.5 |
| 12/3/1987 | 1987 | 12 | 3 | 186 | 29 | 60 | 44.5 | 12.5 | 4961 |
| 12/4/1987 | 1987 | 12 | 4 | 187 | 30 | 61 | 45.5 | 13.5 | 4974.5 |
| 12/5/1987 | 1987 | 12 | 5 | 188 | 30 | 61 | 45.5 | 13.5 | 4988 |
| 12/6/1987 | 1987 | 12 | 6 | 189 | 25 | 52 | 38.5 | 6.5 | 4994.5 |
| 12/7/1987 | 1987 | 12 | 7 | 190 | 27 | 57 | 42 | 10 | 5004.5 |
| 12/8/1987 | 1987 | 12 | 8 | 191 | 20 | 48 | 34 | 2 | 5006.5 |
| 12/9/1987 | 1987 | 12 | 9 | 192 | 21 | 50 | 35.5 | 3.5 | 5010 |
| 12/10/1987 | 1987 | 12 | 10 | 193 | 26 | 59 | 42.5 | 10.5 | 5020.5 |
| 12/11/1987 | 1987 | 12 | 11 | 194 | 35 | 58 | 46.5 | 14.5 | 5035 |
| 12/12/1987 | 1987 | 12 | 12 | 195 | 19 | 42 | 30.5 | -1.5 | 5033.5 |
| 12/13/1987 | 1987 | 12 | 13 | 196 | 13 | 26 | 19.5 | -12.5 | 5021 |
| 12/14/1987 | 1987 | 12 | 14 | 197 | 8 | 22 | 15 | -17 | 5004 |
| 12/15/1987 | 1987 | 12 | 15 | 198 | 2 | 28 | 15 | -17 | 4987 |
| 12/16/1987 | 1987 | 12 | 16 | 199 | 10 | 29 | 19.5 | -12.5 | 4974.5 |
| 12/17/1987 | 1987 | 12 | 17 | 200 | 17 | 44 | 30.5 | -1.5 | 4973 |
| 12/18/1987 | 1987 | 12 | 18 | 201 | 25 | 41 | 33 | 1 | 4974 |
| 12/19/1987 | 1987 | 12 | 19 | 202 | 26 | 32 | 29 | -3 | 4971 |
| 12/20/1987 | 1987 | 12 | 20 | 203 | 26 | 33 | 29.5 | -2.5 | 4968.5 |
| 12/21/1987 | 1987 | 12 | 21 | 204 | 11 | 42 | 26.5 | -5.5 | 4963 |
| 12/22/1987 | 1987 | 12 | 22 | 205 | 19 | 51 | 35 | 3 | 4966 |
| 12/23/1987 | 1987 | 12 | 23 | 206 | 31 | 45 | 38 | 6 | 4972 |
| 12/24/1987 | 1987 | 12 | 24 | 207 | 21 | 34 | 27.5 | -4.5 | 4967.5 |
| 12/25/1987 | 1987 | 12 | 25 | 208 | 14 | 32 | 23 | -9 | 4958.5 |
| 12/26/1987 | 1987 | 12 | 26 | 209 | 1 | 32 | 16.5 | -15.5 | 4943 |
| 12/27/1987 | 1987 | 12 | 27 | 210 | 9 | 26 | 17.5 | -14.5 | 4928.5 |
| 12/28/1987 | 1987 | 12 | 28 | 211 | 9 | 40 | 24.5 | -7.5 | 4921 |
| 12/29/1987 | 1987 | 12 | 29 | 212 | 9 | 51 | 30 | -2 | 4919 |
| 12/30/1987 | 1987 | 12 | 30 | 213 | 21 | 43 | 32 | 0 | 4919 |
| 12/31/1987 | 1987 | 12 | 31 | 214 | 6 | 29 | 17.5 | -14.5 | 4904.5 |
| 1/1/1988 | 1988 | 1 | 1 | 215 | 5 | 30 | 17.5 | -14.5 | 4890 |
| 1/2/1988 | 1988 | 1 | 2 | 216 | 21 | 31 | 26 | -6 | 4884 |
| 1/3/1988 | 1988 | 1 | 3 | 217 | 10 | 40 | 25 | -7 | 4877 |
| 1/4/1988 | 1988 | 1 | 4 | 218 | 28 | 41 | 34.5 | 2.5 | 4879.5 |
| 1/5/1988 | 1988 | 1 | 5 | 219 | 33 | 47 | 40 | 8 | 4887.5 |
| 1/6/1988 | 1988 | 1 | 6 | 220 | 28 | 38 | 33 | 1 | 4888.5 |
| 1/7/1988 | 1988 | 1 | 7 | 221 | 17 | 38 | 27.5 | -4.5 | 4884 |
| 1/8/1988 | 1988 | 1 | 8 | 222 | 15 | 36 | 25.5 | -6.5 | 4877.5 |
| 1/9/1988 | 1988 | 1 | 9 | 223 | 11 | 37 | 24 | -8 | 4869.5 |
| 1/10/1988 | 1988 | 1 | 10 | 224 | 19 | 44 | 31.5 | -0.5 | 4869 |
| 1/11/1988 | 1988 | 1 | 11 | 225 | 23 | 47 | 35 | 3 | 4872 |
| 1/12/1988 | 1988 | 1 | 12 | 226 | 16 | 41 | 28.5 | -3.5 | 4868.5 |
| 1/13/1988 | 1988 | 1 | 13 | 227 | 11 | 44 | 27.5 | -4.5 | 4864 |
| 1/14/1988 | 1988 | 1 | 14 | 228 | 16 | 42 | 29 | -3 | 4861 |
| 1/15/1988 | 1988 | 1 | 15 | 229 | 17 | 49 | 33 | 1 | 4862 |
| 1/16/1988 | 1988 | 1 | 16 | 230 | 28 | 45 | 36.5 | 4.5 | 4866.5 |
| 1/17/1988 | 1988 | 1 | 17 | 231 | 22 | 39 | 30.5 | -1.5 | 4865 |
| 1/18/1988 | 1988 | 1 | 18 | 232 | 22 | 38 | 30 | -2 | 4863 |
| 1/19/1988 | 1988 | 1 | 19 | 233 | 16 | 28 | 22 | -10 | 4853 |
| 1/20/1988 | 1988 | 1 | 20 | 234 | 4 | 26 | 15 | -17 | 4836 |
| 1/21/1988 | 1988 | 1 | 21 | 235 | 5 | 29 | 17 | -15 | 4821 |
| 1/22/1988 | 1988 | 1 | 22 | 236 | 1 | 27 | 14 | -18 | 4803 |
| 1/23/1988 | 1988 | 1 | 23 | 237 | 8 | 45 | 26.5 | -5.5 | 4797.5 |
| 1/24/1988 | 1988 | 1 | 24 | 238 | 13 | 32 | 22.5 | -9.5 | 4788 |
| 1/25/1988 | 1988 | 1 | 25 | 239 | 8 | 37 | 22.5 | -9.5 | 4778.5 |
| 1/26/1988 | 1988 | 1 | 26 | 240 | 18 | 47 | 32.5 | 0.5 | 4779 |
| 1/27/1988 | 1988 | 1 | 27 | 241 | 19 | 55 | 37 | 5 | 4784 |
| 1/28/1988 | 1988 | 1 | 28 | 242 | 25 | 52 | 38.5 | 6.5 | 4790.5 |
| 1/29/1988 | 1988 | 1 | 29 | 243 | 28 | 51 | 39.5 | 7.5 | 4798 |
| 1/30/1988 | 1988 | 1 | 30 | 244 | 29 | 53 | 41 | 9 | 4807 |
| 1/31/1988 | 1988 | 1 | 31 | 245 | 23 | 48 | 35.5 | 3.5 | 4810.5 |
| 2/1/1988 | 1988 | 2 | 1 | 246 | 23 | 41 | 32 | 0 | 4810.5 |
| 2/2/1988 | 1988 | 2 | 2 | 247 | 31 | 45 | 38 | 6 | 4816.5 |
| 2/3/1988 | 1988 | 2 | 3 | 248 | 32 | 42 | 37 | 5 | 4821.5 |
| 2/4/1988 | 1988 | 2 | 4 | 249 | 24 | 37 | 30.5 | -1.5 | 4820 |
| 2/5/1988 | 1988 | 2 | 5 | 250 | 23 | 41 | 32 | 0 | 4820 |
| 2/6/1988 | 1988 | 2 | 6 | 251 | 23 | 41 | 32 | 0 | 4820 |
| 2/7/1988 | 1988 | 2 | 7 | 252 | 17 | 47 | 32 | 0 | 4820 |
| 2/8/1988 | 1988 | 2 | 8 | 253 | 21 | 50 | 35.5 | 3.5 | 4823.5 |
| 2/9/1988 | 1988 | 2 | 9 | 254 | 21 | 53 | 37 | 5 | 4828.5 |
| 2/10/1988 | 1988 | 2 | 10 | 255 | 26 | 53 | 39.5 | 7.5 | 4836 |
| 2/11/1988 | 1988 | 2 | 11 | 256 | 22 | 47 | 34.5 | 2.5 | 4838.5 |
| 2/12/1988 | 1988 | 2 | 12 | 257 | 23 | 53 | 38 | 6 | 4844.5 |
| 2/13/1988 | 1988 | 2 | 13 | 258 | 24 | 55 | 39.5 | 7.5 | 4852 |
| 2/14/1988 | 1988 | 2 | 14 | 259 | 19 | 50 | 34.5 | 2.5 | 4854.5 |
| 2/15/1988 | 1988 | 2 | 15 | 260 | 18 | 52 | 35 | 3 | 4857.5 |
| 2/16/1988 | 1988 | 2 | 16 | 261 | 29 | 52 | 40.5 | 8.5 | 4866 |
| 2/17/1988 | 1988 | 2 | 17 | 262 | 19 | 39 | 29 | -3 | 4863 |
| 2/18/1988 | 1988 | 2 | 18 | 263 | 13 | 38 | 25.5 | -6.5 | 4856.5 |
| 2/19/1988 | 1988 | 2 | 19 | 264 | 18 | 41 | 29.5 | -2.5 | 4854 |
| 2/20/1988 | 1988 | 2 | 20 | 265 | 20 | 47 | 33.5 | 1.5 | 4855.5 |
| 2/21/1988 | 1988 | 2 | 21 | 266 | 21 | 53 | 37 | 5 | 4860.5 |
| 2/22/1988 | 1988 | 2 | 22 | 267 | 25 | 56 | 40.5 | 8.5 | 4869 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/23/1988 | 1988 | 2 | 23 | 268 | 28 | 57 | 42.5 | 10.5 | 4879.5 |
| 2/24/1988 | 1988 | 2 | 24 | 269 | 27 | 58 | 42.5 | 10.5 | 4890 |
| 2/25/1988 | 1988 | 2 | 25 | 270 | 29 | 60 | 44.5 | 12.5 | 4902.5 |
| 2/26/1988 | 1988 | 2 | 26 | 271 | 38 | 61 | 49.5 | 17.5 | 4920 |
| 2/27/1988 | 1988 | 2 | 27 | 272 | 35 | 54 | 44.5 | 12.5 | 4932.5 |
| 2/28/1988 | 1988 | 2 | 28 | 273 | 32 | 56 | 44 | 12 | 4944.5 |
| 2/29/1988 | 1988 | 2 | 29 | 274 | 31 | 61 | 46 | 14 | 4958.5 |
| 3/1/1988 | 1988 | 3 | 1 | 275 | 22 | 67 | 44.5 | 12.5 | 4971 |
| 3/2/1988 | 1988 | 3 | 2 | 276 | 27 | 58 | 42.5 | 10.5 | 4981.5 |
| 3/3/1988 | 1988 | 3 | 3 | 277 | 32 | 47 | 39.5 | 7.5 | 4989 |
| 3/4/1988 | 1988 | 3 | 4 | 278 | 22 | 58 | 40 | 8 | 4997 |
| 3/5/1988 | 1988 | 3 | 5 | 279 | 22 | 62 | 42 | 10 | 5007 |
| 3/6/1988 | 1988 | 3 | 6 | 280 | 21 | 62 | 41.5 | 9.5 | 5016.5 |
| 3/7/1988 | 1988 | 3 | 7 | 281 | 38 | 48 | 43 | 11 | 5027.5 |
| 3/8/1988 | 1988 | 3 | 8 | 282 | 16 | 46 | 31 | -1 | 5026.5 |
| 3/9/1988 | 1988 | 3 | 9 | 283 | 13 | 65 | 39 | 7 | 5033.5 |
| 3/10/1988 | 1988 | 3 | 10 | 284 | 33 | 47 | 40 | 8 | 5041.5 |
| 3/11/1988 | 1988 | 3 | 11 | 285 | 22 | 43 | 32.5 | 0.5 | 5042 |
| 3/12/1988 | 1988 | 3 | 12 | 286 | 8 | 48 | 28 | -4 | 5038 |
| 3/13/1988 | 1988 | 3 | 13 | 287 | 26 | 40 | 33 | 1 | 5039 |
| 3/14/1988 | 1988 | 3 | 14 | 288 | 7 | 56 | 31.5 | -0.5 | 5038.5 |
| 3/15/1988 | 1988 | 3 | 15 | 289 | 10 | 59 | 34.5 | 2.5 | 5041 |
| 3/16/1988 | 1988 | 3 | 16 | 290 | 24 | 46 | 35 | 3 | 5044 |
| 3/17/1988 | 1988 | 3 | 17 | 291 | 13 | 42 | 27.5 | -4.5 | 5039.5 |
| 3/18/1988 | 1988 | 3 | 18 | 292 | 9 | 57 | 33 | 1 | 5040.5 |
| 3/19/1988 | 1988 | 3 | 19 | 293 | 14 | 65 | 39.5 | 7.5 | 5048 |
| 3/20/1988 | 1988 | 3 | 20 | 294 | 13 | 71 | 42 | 10 | 5058 |
| 3/21/1988 | 1988 | 3 | 21 | 295 | 16 | 74 | 45 | 13 | 5071 |
| 3/22/1988 | 1988 | 3 | 22 | 296 | 29 | 68 | 48.5 | 16.5 | 5087.5 |
| 3/23/1988 | 1988 | 3 | 23 | 297 | 30 | 74 | 52 | 20 | 5107.5 |
| 3/24/1988 | 1988 | 3 | 24 | 298 | 36 | 65 | 50.5 | 18.5 | 5126 |
| 3/25/1988 | 1988 | 3 | 25 | 299 | 22 | 73 | 47.5 | 15.5 | 5141.5 |
| 3/26/1988 | 1988 | 3 | 26 | 300 | 24 | 72 | 48 | 16 | 5157.5 |
| 3/27/1988 | 1988 | 3 | 27 | 301 | 26 | 77 | 51.5 | 19.5 | 5177 |
| 3/28/1988 | 1988 | 3 | 28 | 302 | 43 | 60 | 51.5 | 19.5 | 5196.5 |
| 3/29/1988 | 1988 | 3 | 29 | 303 | 23 | 59 | 41 | 9 | 5205.5 |
| 3/30/1988 | 1988 | 3 | 30 | 304 | 41 | 64 | 52.5 | 20.5 | 5226 |
| 3/31/1988 | 1988 | 3 | 31 | 305 | 25 | 41 | 33 | 1 | 5227 |
| 4/1/1988 | 1988 | 4 | 1 | 306 | 30 | 57 | 43.5 | 11.5 | 5238.5 |
| 4/2/1988 | 1988 | 4 | 2 | 307 | 21 | 66 | 43.5 | 11.5 | 5250 |
| 4/3/1988 | 1988 | 4 | 3 | 308 | 20 | 72 | 46 | 14 | 5264 |
| 4/4/1988 | 1988 | 4 | 4 | 309 | 25 | 72 | 48.5 | 16.5 | 5280.5 |
| 4/5/1988 | 1988 | 4 | 5 | 310 | 36 | 68 | 52 | 20 | 5300.5 |
| 4/6/1988 | 1988 | 4 | 6 | 311 | 26 | 77 | 51.5 | 19.5 | 5320 |
| 4/7/1988 | 1988 | 4 | 7 | 312 | 27 | 80 | 53.5 | 21.5 | 5341.5 |
| 4/8/1988 | 1988 | 4 | 8 | 313 | 35 | 76 | 55.5 | 23.5 | 5365 |
| 4/9/1988 | 1988 | 4 | 9 | 314 | 27 | 75 | 51 | 19 | 5384 |
| 4/10/1988 | 1988 | 4 | 10 | 315 | 19 | 66 | 42.5 | 10.5 | 5394.5 |
| 4/11/1988 | 1988 | 4 | 11 | 316 | 26 | 74 | 50 | 18 | 5412.5 |
| 4/12/1988 | 1988 | 4 | 12 | 317 | 23 | 78 | 50.5 | 18.5 | 5431 |
| 4/13/1988 | 1988 | 4 | 13 | 318 | 25 | 75 | 50 | 18 | 5449 |
| 4/14/1988 | 1988 | 4 | 14 | 319 | 47 | 60 | 53.5 | 21.5 | 5470.5 |
| 4/15/1988 | 1988 | 4 | 15 | 320 | 33 | 66 | 49.5 | 17.5 | 5488 |
| 4/16/1988 | 1988 | 4 | 16 | 321 | 26 | 48 | 37 | 5 | 5493 |
| 4/17/1988 | 1988 | 4 | 17 | 322 | 15 | 49 | 32 | 0 | 5493 |
| 4/18/1988 | 1988 | 4 | 18 | 323 | 30 | 60 | 45 | 13 | 5506 |
| 4/19/1988 | 1988 | 4 | 19 | 324 | 34 | 67 | 50.5 | 18.5 | 5524.5 |
| 4/20/1988 | 1988 | 4 | 20 | 325 | 32 | 69 | 50.5 | 18.5 | 5543 |
| 4/21/1988 | 1988 | 4 | 21 | 326 | 32 | 66 | 49 | 17 | 5560 |
| 4/22/1988 | 1988 | 4 | 22 | 327 | 31 | 66 | 48.5 | 16.5 | 5576.5 |
| 4/23/1988 | 1988 | 4 | 23 | 328 | 29 | 66 | 47.5 | 15.5 | 5592 |
| 4/24/1988 | 1988 | 4 | 24 | 329 | 29 | 60 | 44.5 | 12.5 | 5604.5 |
| 4/25/1988 | 1988 | 4 | 25 | 330 | 23 | 76 | 49.5 | 17.5 | 5622 |
| 4/26/1988 | 1988 | 4 | 26 | 331 | 31 | 71 | 51 | 19 | 5641 |
| 4/27/1988 | 1988 | 4 | 27 | 332 | 30 | 76 | 53 | 21 | 5662 |
| 4/28/1988 | 1988 | 4 | 28 | 333 | 36 | 65 | 50.5 | 18.5 | 5680.5 |
| 4/29/1988 | 1988 | 4 | 29 | 334 | 39 | 72 | 55.5 | 23.5 | 5704 |
| 4/30/1988 | 1988 | 4 | 30 | 335 | 33 | 81 | 57 | 25 | 5729 |
| 5/1/1988 | 1988 | 5 | 1 | 336 | 38 | 58 | 48 | 16 | 5745 |
| 5/2/1988 | 1988 | 5 | 2 | 337 | 31 | 61 | 46 | 14 | 5759 |
| 5/3/1988 | 1988 | 5 | 3 | 338 | 24 | 73 | 48.5 | 16.5 | 5775.5 |
| 5/4/1988 | 1988 | 5 | 4 | 339 | 36 | 78 | 57 | 25 | 5800.5 |
| 5/5/1988 | 1988 | 5 | 5 | 340 | 37 | 79 | 58 | 26 | 5826.5 |
| 5/6/1988 | 1988 | 5 | 6 | 341 | 36 | 63 | 49.5 | 17.5 | 5844 |
| 5/7/1988 | 1988 | 5 | 7 | 342 | 32 | 63 | 47.5 | 15.5 | 5859.5 |
| 5/8/1988 | 1988 | 5 | 8 | 343 | 40 | 65 | 52.5 | 20.5 | 5880 |
| 5/9/1988 | 1988 | 5 | 9 | 344 | 27 | 76 | 51.5 | 19.5 | 5899.5 |
| 5/10/1988 | 1988 | 5 | 10 | 345 | 35 | 77 | 56 | 24 | 5923.5 |
| 5/11/1988 | 1988 | 5 | 11 | 346 | 41 | 78 | 59.5 | 27.5 | 5951 |
| 5/12/1988 | 1988 | 5 | 12 | 347 | 41 | 84 | 62.5 | 30.5 | 5981.5 |
| 5/13/1988 | 1988 | 5 | 13 | 348 | 38 | 84 | 61 | 29 | 6010.5 |
| 5/14/1988 | 1988 | 5 | 14 | 349 | 40 | 84 | 62 | 30 | 6040.5 |
| 5/15/1988 | 1988 | 5 | 15 | 350 | 50 | 89 | 69.5 | 37.5 | 6078 |
| 5/16/1988 | 1988 | 5 | 16 | 351 | 43 | 86 | 64.5 | 32.5 | 6110.5 |
| 5/17/1988 | 1988 | 5 | 17 | 352 | 48 | 77 | 62.5 | 30.5 | 6141 |
| 5/18/1988 | 1988 | 5 | 18 | 353 | 44 | 63 | 53.5 | 21.5 | 6162.5 |
| 5/19/1988 | 1988 | 5 | 19 | 354 | 47 | 68 | 57.5 | 25.5 | 6188 |
| 5/20/1988 | 1988 | 5 | 20 | 355 | 39 | 63 | 51 | 19 | 6207 |
| 5/21/1988 | 1988 | 5 | 21 | 356 | 34 | 73 | 53.5 | 21.5 | 6228.5 |
| 5/22/1988 | 1988 | 5 | 22 | 357 | 37 | 78 | 57.5 | 25.5 | 6254 |
| 5/23/1988 | 1988 | 5 | 23 | 358 | 34 | 81 | 57.5 | 25.5 | 6279.5 |
| 5/24/1988 | 1988 | 5 | 24 | 359 | 48 | 79 | 63.5 | 31.5 | 6311 |
| 5/25/1988 | 1988 | 5 | 25 | 360 | 39 | 77 | 58 | 26 | 6337 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/26/1988 | 1988 | 5 | 26 | 361 | 39 | 82 | 60.5 | 28.5 | 6365.5 |
| 5/27/1988 | 1988 | 5 | 27 | 362 | 48 | 85 | 66.5 | 34.5 | 6400 |
| 5/28/1988 | 1988 | 5 | 28 | 363 | 42 | 84 | 63 | 31 | 6431 |
| 5/29/1988 | 1988 | 5 | 29 | 364 | 41 | 83 | 62 | 30 | 6461 |
| 5/30/1988 | 1988 | 5 | 30 | 365 | 38 | 58 | 48 | 16 | 6477 |
| 5/31/1988 | 1988 | 5 | 31 | 366 | 33 | 66 | 49.5 | 17.5 | 6494.5 |
| 6/1/1988 | 1988 | 6 | 1 | 1 | 30 | 76 | 53 | 21 | 21 |
| 6/2/1988 | 1988 | 6 | 2 | 2 | 39 | 83 | 61 | 29 | 50 |
| 6/3/1988 | 1988 | 6 | 3 | 3 | 43 | 83 | 63 | 31 | 81 |
| 6/4/1988 | 1988 | 6 | 4 | 4 | 52 | 82 | 67 | 35 | 116 |
| 6/5/1988 | 1988 | 6 | 5 | 5 | 43 | 78 | 60.5 | 28.5 | 144.5 |
| 6/6/1988 | 1988 | 6 | 6 | 6 | 45 | 87 | 66 | 34 | 178.5 |
| 6/7/1988 | 1988 | 6 | 7 | 7 | 42 | 88 | 65 | 33 | 211.5 |
| 6/8/1988 | 1988 | 6 | 8 | 8 | 41 | 87 | 64 | 32 | 243.5 |
| 6/9/1988 | 1988 | 6 | 9 | 9 | 39 | 84 | 61.5 | 29.5 | 273 |
| 6/10/1988 | 1988 | 6 | 10 | 10 | 54 | 83 | 68.5 | 36.5 | 309.5 |
| 6/11/1988 | 1988 | 6 | 11 | 11 | 44 | 78 | 61 | 29 | 338.5 |
| 6/12/1988 | 1988 | 6 | 12 | 12 | 49 | 86 | 67.5 | 35.5 | 374 |
| 6/13/1988 | 1988 | 6 | 13 | 13 | 41 | 82 | 61.5 | 29.5 | 403.5 |
| 6/14/1988 | 1988 | 6 | 14 | 14 | 42 | 85 | 63.5 | 31.5 | 435 |
| 6/15/1988 | 1988 | 6 | 15 | 15 | 49 | 83 | 66 | 34 | 469 |
| 6/16/1988 | 1988 | 6 | 16 | 16 | 52 | 86 | 69 | 37 | 506 |
| 6/17/1988 | 1988 | 6 | 17 | 17 | 49 | 88 | 68.5 | 36.5 | 542.5 |
| 6/18/1988 | 1988 | 6 | 18 | 18 | 49 | 89 | 69 | 37 | 579.5 |
| 6/19/1988 | 1988 | 6 | 19 | 19 | 52 | 90 | 71 | 39 | 618.5 |
| 6/20/1988 | 1988 | 6 | 20 | 20 | 53 | 90 | 71.5 | 39.5 | 658 |
| 6/21/1988 | 1988 | 6 | 21 | 21 | 53 | 93 | 73 | 41 | 699 |
| 6/22/1988 | 1988 | 6 | 22 | 22 | 54 | 94 | 74 | 42 | 741 |
| 6/23/1988 | 1988 | 6 | 23 | 23 | 58 | 91 | 74.5 | 42.5 | 783.5 |
| 6/24/1988 | 1988 | 6 | 24 | 24 | 56 | 87 | 71.5 | 39.5 | 823 |
| 6/25/1988 | 1988 | 6 | 25 | 25 | 58 | 88 | 73 | 41 | 864 |
| 6/26/1988 | 1988 | 6 | 26 | 26 | 50 | 84 | 67 | 35 | 899 |
| 6/27/1988 | 1988 | 6 | 27 | 27 | 56 | 77 | 66.5 | 34.5 | 933.5 |
| 6/28/1988 | 1988 | 6 | 28 | 28 | 57 | 77 | 67 | 35 | 968.5 |
| 6/29/1988 | 1988 | 6 | 29 | 29 | 55 | 76 | 65.5 | 33.5 | 1002 |
| 6/30/1988 | 1988 | 6 | 30 | 30 | 51 | 83 | 67 | 35 | 1037 |
| 7/1/1988 | 1988 | 7 | 1 | 31 | 58 | 88 | 73 | 41 | 1078 |
| 7/2/1988 | 1988 | 7 | 2 | 32 | 54 | 89 | 71.5 | 39.5 | 1117.5 |
| 7/3/1988 | 1988 | 7 | 3 | 33 | 55 | 85 | 70 | 38 | 1155.5 |
| 7/4/1988 | 1988 | 7 | 4 | 34 | 60 | 81 | 70.5 | 38.5 | 1194 |
| 7/5/1988 | 1988 | 7 | 5 | 35 | 59 | 88 | 73.5 | 41.5 | 1235.5 |
| 7/6/1988 | 1988 | 7 | 6 | 36 | 54 | 88 | 71 | 39 | 1274.5 |
| 7/7/1988 | 1988 | 7 | 7 | 37 | 63 | 94 | 78.5 | 46.5 | 1321 |
| 7/8/1988 | 1988 | 7 | 8 | 38 | 61 | 83 | 72 | 40 | 1361 |
| 7/9/1988 | 1988 | 7 | 9 | 39 | 57 | 78 | 67.5 | 35.5 | 1396.5 |
| 7/10/1988 | 1988 | 7 | 10 | 40 | 52 | 83 | 67.5 | 35.5 | 1432 |
| 7/11/1988 | 1988 | 7 | 11 | 41 | 50 | 89 | 69.5 | 37.5 | 1469.5 |
| 7/12/1988 | 1988 | 7 | 12 | 42 | 55 | 91 | 73 | 41 | 1510.5 |
| 7/13/1988 | 1988 | 7 | 13 | 43 | 58 | 94 | 76 | 44 | 1554.5 |
| 7/14/1988 | 1988 | 7 | 14 | 44 | 62 | 88 | 75 | 43 | 1597.5 |
| 7/15/1988 | 1988 | 7 | 15 | 45 | 62 | 93 | 77.5 | 45.5 | 1643 |
| 7/16/1988 | 1988 | 7 | 16 | 46 | 56 | 91 | 73.5 | 41.5 | 1684.5 |
| 7/17/1988 | 1988 | 7 | 17 | 47 | 57 | 91 | 74 | 42 | 1726.5 |
| 7/18/1988 | 1988 | 7 | 18 | 48 | 58 | 91 | 74.5 | 42.5 | 1769 |
| 7/19/1988 | 1988 | 7 | 19 | 49 | 60 | 87 | 73.5 | 41.5 | 1810.5 |
| 7/20/1988 | 1988 | 7 | 20 | 50 | 58 | 79 | 68.5 | 36.5 | 1847 |
| 7/21/1988 | 1988 | 7 | 21 | 51 | 58 | 89 | 73.5 | 41.5 | 1888.5 |
| 7/22/1988 | 1988 | 7 | 22 | 52 | 52 | 94 | 73 | 41 | 1929.5 |
| 7/23/1988 | 1988 | 7 | 23 | 53 | 62 | 94 | 78 | 46 | 1975.5 |
| 7/24/1988 | 1988 | 7 | 24 | 54 | 57 | 88 | 72.5 | 40.5 | 2016 |
| 7/25/1988 | 1988 | 7 | 25 | 55 | 53 | 93 | 73 | 41 | 2057 |
| 7/26/1988 | 1988 | 7 | 26 | 56 | 60 | 90 | 75 | 43 | 2100 |
| 7/27/1988 | 1988 | 7 | 27 | 57 | 53 | 89 | 71 | 39 | 2139 |
| 7/28/1988 | 1988 | 7 | 28 | 58 | 57 | 88 | 72.5 | 40.5 | 2179.5 |
| 7/29/1988 | 1988 | 7 | 29 | 59 | 56 | 82 | 69 | 37 | 2216.5 |
| 7/30/1988 | 1988 | 7 | 30 | 60 | 57 | 82 | 69.5 | 37.5 | 2254 |
| 7/31/1988 | 1988 | 7 | 31 | 61 | 59 | 81 | 70 | 38 | 2292 |
| 8/1/1988 | 1988 | 8 | 1 | 62 | 57 | 81 | 69 | 37 | 2329 |
| 8/2/1988 | 1988 | 8 | 2 | 63 | 54 | 86 | 70 | 38 | 2367 |
| 8/3/1988 | 1988 | 8 | 3 | 64 | 57 | 90 | 73.5 | 41.5 | 2408.5 |
| 8/4/1988 | 1988 | 8 | 4 | 65 | 58 | 92 | 75 | 43 | 2451.5 |
| 8/5/1988 | 1988 | 8 | 5 | 66 | 58 | 84 | 71 | 39 | 2490.5 |
| 8/6/1988 | 1988 | 8 | 6 | 67 | 60 | 79 | 69.5 | 37.5 | 2528 |
| 8/7/1988 | 1988 | 8 | 7 | 68 | 58 | 84 | 71 | 39 | 2567 |
| 8/8/1988 | 1988 | 8 | 8 | 69 | 51 | 88 | 69.5 | 37.5 | 2604.5 |
| 8/9/1988 | 1988 | 8 | 9 | 70 | 52 | 86 | 69 | 37 | 2641.5 |
| 8/10/1988 | 1988 | 8 | 10 | 71 | 57 | 84 | 70.5 | 38.5 | 2680 |
| 8/11/1988 | 1988 | 8 | 11 | 72 | 57 | 88 | 72.5 | 40.5 | 2720.5 |
| 8/12/1988 | 1988 | 8 | 12 | 73 | 58 | 87 | 72.5 | 40.5 | 2761 |
| 8/13/1988 | 1988 | 8 | 13 | 74 | 51 | 90 | 70.5 | 38.5 | 2799.5 |
| 8/14/1988 | 1988 | 8 | 14 | 75 | 51 | 92 | 71.5 | 39.5 | 2839 |
| 8/15/1988 | 1988 | 8 | 15 | 76 | 57 | 83 | 70 | 38 | 2877 |
| 8/16/1988 | 1988 | 8 | 16 | 77 | 58 | 84 | 71 | 39 | 2916 |
| 8/17/1988 | 1988 | 8 | 17 | 78 | 57 | 76 | 66.5 | 34.5 | 2950.5 |
| 8/18/1988 | 1988 | 8 | 18 | 79 | 51 | 79 | 65 | 33 | 2983.5 |
| 8/19/1988 | 1988 | 8 | 19 | 80 | 53 | 86 | 69.5 | 37.5 | 3021 |
| 8/20/1988 | 1988 | 8 | 20 | 81 | 52 | 87 | 69.5 | 37.5 | 3058.5 |
| 8/21/1988 | 1988 | 8 | 21 | 82 | 54 | 81 | 67.5 | 35.5 | 3094 |
| 8/22/1988 | 1988 | 8 | 22 | 83 | 59 | 86 | 72.5 | 40.5 | 3134.5 |
| 8/23/1988 | 1988 | 8 | 23 | 84 | 60 | 85 | 72.5 | 40.5 | 3175 |
| 8/24/1988 | 1988 | 8 | 24 | 85 | 60 | 84 | 72 | 40 | 3215 |
| 8/25/1988 | 1988 | 8 | 25 | 86 | 59 | 86 | 72.5 | 40.5 | 3255.5 |
| 8/26/1988 | 1988 | 8 | 26 | 87 | 55 | 82 | 68.5 | 36.5 | 3292 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/27/1988 | 1988 | 8 | 27 | 88 | 55 | 75 | 65 | 33 | 3325 |
| 8/28/1988 | 1988 | 8 | 28 | 89 | 53 | 64 | 58.5 | 26.5 | 3351.5 |
| 8/29/1988 | 1988 | 8 | 29 | 90 | 54 | 70 | 62 | 30 | 3381.5 |
| 8/30/1988 | 1988 | 8 | 30 | 91 | 57 | 77 | 67 | 35 | 3416.5 |
| 8/31/1988 | 1988 | 8 | 31 | 92 | 54 | 71 | 62.5 | 30.5 | 3447 |
| 9/1/1988 | 1988 | 9 | 1 | 93 | 55 | 75 | 65 | 33 | 3480 |
| 9/2/1988 | 1988 | 9 | 2 | 94 | 56 | 88 | 72 | 40 | 3520 |
| 9/3/1988 | 1988 | 9 | 3 | 95 | 48 | 79 | 63.5 | 31.5 | 3551.5 |
| 9/4/1988 | 1988 | 9 | 4 | 96 | 48 | 76 | 62 | 30 | 3581.5 |
| 9/5/1988 | 1988 | 9 | 5 | 97 | 44 | 79 | 61.5 | 29.5 | 3611 |
| 9/6/1988 | 1988 | 9 | 6 | 98 | 41 | 85 | 63 | 31 | 3642 |
| 9/7/1988 | 1988 | 9 | 7 | 99 | 42 | 88 | 65 | 33 | 3675 |
| 9/8/1988 | 1988 | 9 | 8 | 100 | 44 | 91 | 67.5 | 35.5 | 3710.5 |
| 9/9/1988 | 1988 | 9 | 9 | 101 | 45 | 89 | 67 | 35 | 3745.5 |
| 9/10/1988 | 1988 | 9 | 10 | 102 | 49 | 88 | 68.5 | 36.5 | 3782 |
| 9/11/1988 | 1988 | 9 | 11 | 103 | 53 | 83 | 68 | 36 | 3818 |
| 9/12/1988 | 1988 | 9 | 12 | 104 | 38 | 70 | 54 | 22 | 3840 |
| 9/13/1988 | 1988 | 9 | 13 | 105 | 48 | 79 | 63.5 | 31.5 | 3871.5 |
| 9/14/1988 | 1988 | 9 | 14 | 106 | 42 | 78 | 60 | 28 | 3899.5 |
| 9/15/1988 | 1988 | 9 | 15 | 107 | 38 | 78 | 58 | 26 | 3925.5 |
| 9/16/1988 | 1988 | 9 | 16 | 108 | 39 | 82 | 60.5 | 28.5 | 3954 |
| 9/17/1988 | 1988 | 9 | 17 | 109 | 42 | 81 | 61.5 | 29.5 | 3983.5 |
| 9/18/1988 | 1988 | 9 | 18 | 110 | 37 | 82 | 59.5 | 27.5 | 4011 |
| 9/19/1988 | 1988 | 9 | 19 | 111 | 36 | 83 | 59.5 | 27.5 | 4038.5 |
| 9/20/1988 | 1988 | 9 | 20 | 112 | 40 | 78 | 59 | 27 | 4065.5 |
| 9/21/1988 | 1988 | 9 | 21 | 113 | 46 | 66 | 56 | 24 | 4089.5 |
| 9/22/1988 | 1988 | 9 | 22 | 114 | 48 | 73 | 60.5 | 28.5 | 4118 |
| 9/23/1988 | 1988 | 9 | 23 | 115 | 36 | 76 | 56 | 24 | 4142 |
| 9/24/1988 | 1988 | 9 | 24 | 116 | 34 | 79 | 56.5 | 24.5 | 4166.5 |
| 9/25/1988 | 1988 | 9 | 25 | 117 | 36 | 81 | 58.5 | 26.5 | 4193 |
| 9/26/1988 | 1988 | 9 | 26 | 118 | 36 | 83 | 59.5 | 27.5 | 4220.5 |
| 9/27/1988 | 1988 | 9 | 27 | 119 | 40 | 79 | 59.5 | 27.5 | 4248 |
| 9/28/1988 | 1988 | 9 | 28 | 120 | 34 | 78 | 56 | 24 | 4272 |
| 9/29/1988 | 1988 | 9 | 29 | 121 | 32 | 70 | 51 | 19 | 4291 |
| 9/30/1988 | 1988 | 9 | 30 | 122 | 31 | 76 | 53.5 | 21.5 | 4312.5 |
| 10/1/1988 | 1988 | 10 | 1 | 123 | 36 | 82 | 59 | 27 | 4339.5 |
| 10/2/1988 | 1988 | 10 | 2 | 124 | 48 | 82 | 65 | 33 | 4372.5 |
| 10/3/1988 | 1988 | 10 | 3 | 125 | 37 | 81 | 59 | 27 | 4399.5 |
| 10/4/1988 | 1988 | 10 | 4 | 126 | 39 | 72 | 55.5 | 23.5 | 4423 |
| 10/5/1988 | 1988 | 10 | 5 | 127 | 48 | 73 | 60.5 | 28.5 | 4451.5 |
| 10/6/1988 | 1988 | 10 | 6 | 128 | 47 | 68 | 57.5 | 25.5 | 4477 |
| 10/7/1988 | 1988 | 10 | 7 | 129 | 35 | 64 | 49.5 | 17.5 | 4494.5 |
| 10/8/1988 | 1988 | 10 | 8 | 130 | 37 | 70 | 53.5 | 21.5 | 4516 |
| 10/9/1988 | 1988 | 10 | 9 | 131 | 37 | 69 | 53 | 21 | 4537 |
| 10/10/1988 | 1988 | 10 | 10 | 132 | 38 | 66 | 52 | 20 | 4557 |
| 10/11/1988 | 1988 | 10 | 11 | 133 | 32 | 68 | 50 | 18 | 4575 |
| 10/12/1988 | 1988 | 10 | 12 | 134 | 29 | 66 | 47.5 | 15.5 | 4590.5 |
| 10/13/1988 | 1988 | 10 | 13 | 135 | 30 | 73 | 51.5 | 19.5 | 4610 |
| 10/14/1988 | 1988 | 10 | 14 | 136 | 31 | 69 | 50 | 18 | 4628 |
| 10/15/1988 | 1988 | 10 | 15 | 137 | 46 | 82 | 64 | 32 | 4660 |
| 10/16/1988 | 1988 | 10 | 16 | 138 | 34 | 79 | 56.5 | 24.5 | 4684.5 |
| 10/17/1988 | 1988 | 10 | 17 | 139 | 34 | 78 | 56 | 24 | 4708.5 |
| 10/18/1988 | 1988 | 10 | 18 | 140 | 34 | 81 | 57.5 | 25.5 | 4734 |
| 10/19/1988 | 1988 | 10 | 19 | 141 | 36 | 76 | 56 | 24 | 4758 |
| 10/20/1988 | 1988 | 10 | 20 | 142 | 35 | 79 | 57 | 25 | 4783 |
| 10/21/1988 | 1988 | 10 | 21 | 143 | 34 | 79 | 56.5 | 24.5 | 4807.5 |
| 10/22/1988 | 1988 | 10 | 22 | 144 | 31 | 79 | 55 | 23 | 4830.5 |
| 10/23/1988 | 1988 | 10 | 23 | 145 | 35 | 78 | 56.5 | 24.5 | 4855 |
| 10/24/1988 | 1988 | 10 | 24 | 146 | 30 | 79 | 54.5 | 22.5 | 4877.5 |
| 10/25/1988 | 1988 | 10 | 25 | 147 | 29 | 77 | 53 | 21 | 4898.5 |
| 10/26/1988 | 1988 | 10 | 26 | 148 | 31 | 76 | 53.5 | 21.5 | 4920 |
| 10/27/1988 | 1988 | 10 | 27 | 149 | 29 | 78 | 53.5 | 21.5 | 4941.5 |
| 10/28/1988 | 1988 | 10 | 28 | 150 | 30 | 71 | 50.5 | 18.5 | 4960 |
| 10/29/1988 | 1988 | 10 | 29 | 151 | 31 | 68 | 49.5 | 17.5 | 4977.5 |
| 10/30/1988 | 1988 | 10 | 30 | 152 | 37 | 69 | 53 | 21 | 4998.5 |
| 10/31/1988 | 1988 | 10 | 31 | 153 | 29 | 73 | 51 | 19 | 5017.5 |
| 11/1/1988 | 1988 | 11 | 1 | 154 | 28 | 74 | 51 | 19 | 5036.5 |
| 11/2/1988 | 1988 | 11 | 2 | 155 | 32 | 69 | 50.5 | 18.5 | 5055 |
| 11/3/1988 | 1988 | 11 | 3 | 156 | 37 | 74 | 55.5 | 23.5 | 5078.5 |
| 11/4/1988 | 1988 | 11 | 4 | 157 | 52 | 72 | 62 | 30 | 5108.5 |
| 11/5/1988 | 1988 | 11 | 5 | 158 | 33 | 76 | 54.5 | 22.5 | 5131 |
| 11/6/1988 | 1988 | 11 | 6 | 159 | 29 | 74 | 51.5 | 19.5 | 5150.5 |
| 11/7/1988 | 1988 | 11 | 7 | 160 | 40 | 71 | 55.5 | 23.5 | 5174 |
| 11/8/1988 | 1988 | 11 | 8 | 161 | 46 | 69 | 57.5 | 25.5 | 5199.5 |
| 11/9/1988 | 1988 | 11 | 9 | 162 | 46 | 64 | 55 | 23 | 5222.5 |
| 11/10/1988 | 1988 | 11 | 10 | 163 | 29 | 68 | 48.5 | 16.5 | 5239 |
| 11/11/1988 | 1988 | 11 | 11 | 164 | 36 | 58 | 47 | 15 | 5254 |
| 11/12/1988 | 1988 | 11 | 12 | 165 | 26 | 65 | 45.5 | 13.5 | 5267.5 |
| 11/13/1988 | 1988 | 11 | 13 | 166 | 25 | 70 | 47.5 | 15.5 | 5283 |
| 11/14/1988 | 1988 | 11 | 14 | 167 | 33 | 68 | 50.5 | 18.5 | 5301.5 |
| 11/15/1988 | 1988 | 11 | 15 | 168 | 29 | 44 | 36.5 | 4.5 | 5306 |
| 11/16/1988 | 1988 | 11 | 16 | 169 | 15 | 48 | 31.5 | -0.5 | 5305.5 |
| 11/17/1988 | 1988 | 11 | 17 | 170 | 20 | 58 | 39 | 7 | 5312.5 |
| 11/18/1988 | 1988 | 11 | 18 | 171 | 20 | 41 | 30.5 | -1.5 | 5311 |
| 11/19/1988 | 1988 | 11 | 19 | 172 | 25 | 44 | 34.5 | 2.5 | 5313.5 |
| 11/20/1988 | 1988 | 11 | 20 | 173 | 15 | 46 | 30.5 | -1.5 | 5312 |
| 11/21/1988 | 1988 | 11 | 21 | 174 | 17 | 46 | 31.5 | -0.5 | 5311.5 |
| 11/22/1988 | 1988 | 11 | 22 | 175 | 11 | 56 | 33.5 | 1.5 | 5313 |
| 11/23/1988 | 1988 | 11 | 23 | 176 | 15 | 58 | 36.5 | 4.5 | 5317.5 |
| 11/24/1988 | 1988 | 11 | 24 | 177 | 29 | 58 | 43.5 | 11.5 | 5329 |
| 11/25/1988 | 1988 | 11 | 25 | 178 | 31 | 44 | 37.5 | 5.5 | 5334.5 |
| 11/26/1988 | 1988 | 11 | 26 | 179 | 29 | 39 | 34 | 2 | 5336.5 |
| 11/27/1988 | 1988 | 11 | 27 | 180 | 13 | 58 | 35.5 | 3.5 | 5340 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/28/1988 | 1988 | 11 | 28 | 181 | 13 | 58 | 35.5 | 3.5 | 5343.5 |
| 11/29/1988 | 1988 | 11 | 29 | 182 | 18 | 42 | 30 | -2 | 5341.5 |
| 11/30/1988 | 1988 | 11 | 30 | 183 | 13 | 43 | 28 | -4 | 5337.5 |
| 12/1/1988 | 1988 | 12 | 1 | 184 | 12 | 54 | 33 | 1 | 5338.5 |
| 12/2/1988 | 1988 | 12 | 2 | 185 | 18 | 58 | 38 | 6 | 5344.5 |
| 12/3/1988 | 1988 | 12 | 3 | 186 | 14 | 59 | 36.5 | 4.5 | 5349 |
| 12/4/1988 | 1988 | 12 | 4 | 187 | 19 | 52 | 35.5 | 3.5 | 5352.5 |
| 12/5/1988 | 1988 | 12 | 5 | 188 | 10 | 57 | 33.5 | 1.5 | 5354 |
| 12/6/1988 | 1988 | 12 | 6 | 189 | 12 | 52 | 32 | 0 | 5354 |
| 12/7/1988 | 1988 | 12 | 7 | 190 | 20 | 45 | 32.5 | 0.5 | 5354.5 |
| 12/8/1988 | 1988 | 12 | 8 | 191 | 20 | 34 | 27 | -5 | 5349.5 |
| 12/9/1988 | 1988 | 12 | 9 | 192 | 9 | 46 | 27.5 | -4.5 | 5345 |
| 12/10/1988 | 1988 | 12 | 10 | 193 | 19 | 44 | 31.5 | -0.5 | 5344.5 |
| 12/11/1988 | 1988 | 12 | 11 | 194 | 12 | 55 | 33.5 | 1.5 | 5346 |
| 12/12/1988 | 1988 | 12 | 12 | 195 | 11 | 53 | 32 | 0 | 5346 |
| 12/13/1988 | 1988 | 12 | 13 | 196 | 12 | 62 | 37 | 5 | 5351 |
| 12/14/1988 | 1988 | 12 | 14 | 197 | 15 | 60 | 37.5 | 5.5 | 5356.5 |
| 12/15/1988 | 1988 | 12 | 15 | 198 | 23 | 38 | 30.5 | -1.5 | 5355 |
| 12/16/1988 | 1988 | 12 | 16 | 199 | 12 | 51 | 31.5 | -0.5 | 5354.5 |
| 12/17/1988 | 1988 | 12 | 17 | 200 | 20 | 49 | 34.5 | 2.5 | 5357 |
| 12/18/1988 | 1988 | 12 | 18 | 201 | 18 | 56 | 37 | 5 | 5362 |
| 12/19/1988 | 1988 | 12 | 19 | 202 | 13 | 41 | 27 | -5 | 5357 |
| 12/20/1988 | 1988 | 12 | 20 | 203 | 15 | 45 | 30 | -2 | 5355 |
| 12/21/1988 | 1988 | 12 | 21 | 204 | 18 | 44 | 31 | -1 | 5354 |
| 12/22/1988 | 1988 | 12 | 22 | 205 | 14 | 44 | 29 | -3 | 5351 |
| 12/23/1988 | 1988 | 12 | 23 | 206 | 17 | 37 | 27 | -5 | 5346 |
| 12/24/1988 | 1988 | 12 | 24 | 207 | 5 | 46 | 25.5 | -6.5 | 5339.5 |
| 12/25/1988 | 1988 | 12 | 25 | 208 | 22 | 52 | 37 | 5 | 5344.5 |
| 12/26/1988 | 1988 | 12 | 26 | 209 | 19 | 43 | 31 | -1 | 5343.5 |
| 12/27/1988 | 1988 | 12 | 27 | 210 | -1 | 28 | 13.5 | -18.5 | 5325 |
| 12/28/1988 | 1988 | 12 | 28 | 211 | -18 | 37 | 9.5 | -22.5 | 5302.5 |
| 12/29/1988 | 1988 | 12 | 29 | 212 | 2 | 34 | 18 | -14 | 5288.5 |
| 12/30/1988 | 1988 | 12 | 30 | 213 | 0 | 37 | 18.5 | -13.5 | 5275 |
| 12/31/1988 | 1988 | 12 | 31 | 214 | 3 | 36 | 19.5 | -12.5 | 5262.5 |
| 1/1/1989 | 1989 | 1 | 1 | 215 | 7 | 45 | 26 | -6 | 5256.5 |
| 1/2/1989 | 1989 | 1 | 2 | 216 | 8 | 48 | 28 | -4 | 5252.5 |
| 1/3/1989 | 1989 | 1 | 3 | 217 | 14 | 50 | 32 | 0 | 5252.5 |
| 1/4/1989 | 1989 | 1 | 4 | 218 | 25 | 43 | 34 | 2 | 5254.5 |
| 1/5/1989 | 1989 | 1 | 5 | 219 | 32 | 40 | 36 | 4 | 5258.5 |
| 1/6/1989 | 1989 | 1 | 6 | 220 | 28 | 39 | 33.5 | 1.5 | 5260 |
| 1/7/1989 | 1989 | 1 | 7 | 221 | -5 | 26 | 10.5 | -21.5 | 5238.5 |
| 1/8/1989 | 1989 | 1 | 8 | 222 | -15 | 30 | 7.5 | -24.5 | 5214 |
| 1/9/1989 | 1989 | 1 | 9 | 223 | -7 | 42 | 17.5 | -14.5 | 5199.5 |
| 1/10/1989 | 1989 | 1 | 10 | 224 | -17 | 55 | 19 | -13 | 5186.5 |
| 1/11/1989 | 1989 | 1 | 11 | 225 | 18 | 46 | 32 | 0 | 5186.5 |
| 1/12/1989 | 1989 | 1 | 12 | 226 | 3 | 35 | 19 | -13 | 5173.5 |
| 1/13/1989 | 1989 | 1 | 13 | 227 | 0 | 36 | 18 | -14 | 5159.5 |
| 1/14/1989 | 1989 | 1 | 14 | 228 | 2 | 48 | 25 | -7 | 5152.5 |
| 1/15/1989 | 1989 | 1 | 15 | 229 | 10 | 35 | 22.5 | -9.5 | 5143 |
| 1/16/1989 | 1989 | 1 | 16 | 230 | 4 | 46 | 25 | -7 | 5136 |
| 1/17/1989 | 1989 | 1 | 17 | 231 | -2 | 50 | 24 | -8 | 5128 |
| 1/18/1989 | 1989 | 1 | 18 | 232 | 12 | 53 | 32.5 | 0.5 | 5128.5 |
| 1/19/1989 | 1989 | 1 | 19 | 233 | 10 | 54 | 32 | 0 | 5128.5 |
| 1/20/1989 | 1989 | 1 | 20 | 234 | 16 | 48 | 32 | 0 | 5128.5 |
| 1/21/1989 | 1989 | 1 | 21 | 235 | 10 | 47 | 28.5 | -3.5 | 5125 |
| 1/22/1989 | 1989 | 1 | 22 | 236 | 15 | 58 | 36.5 | 4.5 | 5129.5 |
| 1/23/1989 | 1989 | 1 | 23 | 237 | 3 | 56 | 29.5 | -2.5 | 5127 |
| 1/24/1989 | 1989 | 1 | 24 | 238 | 23 | 46 | 34.5 | 2.5 | 5129.5 |
| 1/25/1989 | 1989 | 1 | 25 | 239 | 21 | 40 | 30.5 | -1.5 | 5128 |
| 1/26/1989 | 1989 | 1 | 26 | 240 | 22 | 49 | 35.5 | 3.5 | 5131.5 |
| 1/27/1989 | 1989 | 1 | 27 | 241 | 18 | 36 | 27 | -5 | 5126.5 |
| 1/28/1989 | 1989 | 1 | 28 | 242 | 19 | 38 | 28.5 | -3.5 | 5123 |
| 1/29/1989 | 1989 | 1 | 29 | 243 | 5 | 43 | 24 | -8 | 5115 |
| 1/30/1989 | 1989 | 1 | 30 | 244 | 7 | 46 | 26.5 | -5.5 | 5109.5 |
| 1/31/1989 | 1989 | 1 | 31 | 245 | 9 | 57 | 33 | 1 | 5110.5 |
| 2/1/1989 | 1989 | 2 | 1 | 246 | 10 | 54 | 32 | 0 | 5110.5 |
| 2/2/1989 | 1989 | 2 | 2 | 247 | 33 | 53 | 43 | 11 | 5121.5 |
| 2/3/1989 | 1989 | 2 | 3 | 248 | 29 | 53 | 41 | 9 | 5130.5 |
| 2/4/1989 | 1989 | 2 | 4 | 249 | 32 | 54 | 43 | 11 | 5141.5 |
| 2/5/1989 | 1989 | 2 | 5 | 250 | 9 | 26 | 17.5 | -14.5 | 5127 |
| 2/6/1989 | 1989 | 2 | 6 | 251 | 3 | 22 | 12.5 | -19.5 | 5107.5 |
| 2/7/1989 | 1989 | 2 | 7 | 252 | 6 | 26 | 16 | -16 | 5091.5 |
| 2/8/1989 | 1989 | 2 | 8 | 253 | 10 | 40 | 25 | -7 | 5084.5 |
| 2/9/1989 | 1989 | 2 | 9 | 254 | 10 | 42 | 26 | -6 | 5078.5 |
| 2/10/1989 | 1989 | 2 | 10 | 255 | 26 | 53 | 39.5 | 7.5 | 5086 |
| 2/11/1989 | 1989 | 2 | 11 | 256 | 27 | 58 | 42.5 | 10.5 | 5096.5 |
| 2/12/1989 | 1989 | 2 | 12 | 257 | 24 | 51 | 37.5 | 5.5 | 5102 |
| 2/13/1989 | 1989 | 2 | 13 | 258 | 21 | 47 | 34 | 2 | 5104 |
| 2/14/1989 | 1989 | 2 | 14 | 259 | 19 | 48 | 33.5 | 1.5 | 5105.5 |
| 2/15/1989 | 1989 | 2 | 15 | 260 | 19 | 53 | 36 | 4 | 5109.5 |
| 2/16/1989 | 1989 | 2 | 16 | 261 | 15 | 53 | 34 | 2 | 5111.5 |
| 2/17/1989 | 1989 | 2 | 17 | 262 | 22 | 60 | 41 | 9 | 5120.5 |
| 2/18/1989 | 1989 | 2 | 18 | 263 | 20 | 59 | 39.5 | 7.5 | 5128 |
| 2/19/1989 | 1989 | 2 | 19 | 264 | 28 | 48 | 38 | 6 | 5134 |
| 2/20/1989 | 1989 | 2 | 20 | 265 | 27 | 47 | 37 | 5 | 5139 |
| 2/21/1989 | 1989 | 2 | 21 | 266 | 14 | 50 | 32 | 0 | 5139 |
| 2/22/1989 | 1989 | 2 | 22 | 267 | 14 | 58 | 36 | 4 | 5143 |
| 2/23/1989 | 1989 | 2 | 23 | 268 | 18 | 65 | 41.5 | 9.5 | 5152.5 |
| 2/24/1989 | 1989 | 2 | 24 | 269 | 20 | 71 | 45.5 | 13.5 | 5166 |
| 2/25/1989 | 1989 | 2 | 25 | 270 | 24 | 72 | 48 | 16 | 5182 |
| 2/26/1989 | 1989 | 2 | 26 | 271 | 23 | 70 | 46.5 | 14.5 | 5196.5 |
| 2/27/1989 | 1989 | 2 | 27 | 272 | 32 | 61 | 46.5 | 14.5 | 5211 |
| 2/28/1989 | 1989 | 2 | 28 | 273 | 16 | 61 | 38.5 | 6.5 | 5217.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/1/1989 | 1989 | 3 | 1 | 274 | 23 | 60 | 41.5 | 9.5 | 5227 |
| 3/2/1989 | 1989 | 3 | 2 | 275 | 33 | 57 | 45 | 13 | 5240 |
| 3/3/1989 | 1989 | 3 | 3 | 276 | 28 | 44 | 36 | 4 | 5244 |
| 3/4/1989 | 1989 | 3 | 4 | 277 | 18 | 37 | 27.5 | -4.5 | 5239.5 |
| 3/5/1989 | 1989 | 3 | 5 | 278 | 11 | 48 | 29.5 | -2.5 | 5237 |
| 3/6/1989 | 1989 | 3 | 6 | 279 | 15 | 61 | 38 | 6 | 5243 |
| 3/7/1989 | 1989 | 3 | 7 | 280 | 21 | 73 | 47 | 15 | 5258 |
| 3/8/1989 | 1989 | 3 | 8 | 281 | 27 | 76 | 51.5 | 19.5 | 5277.5 |
| 3/9/1989 | 1989 | 3 | 9 | 282 | 26 | 80 | 53 | 21 | 5298.5 |
| 3/10/1989 | 1989 | 3 | 10 | 283 | 30 | 81 | 55.5 | 23.5 | 5322 |
| 3/11/1989 | 1989 | 3 | 11 | 284 | 31 | 77 | 54 | 22 | 5344 |
| 3/12/1989 | 1989 | 3 | 12 | 285 | 26 | 78 | 52 | 20 | 5364 |
| 3/13/1989 | 1989 | 3 | 13 | 286 | 36 | 72 | 54 | 22 | 5386 |
| 3/14/1989 | 1989 | 3 | 14 | 287 | 41 | 68 | 54.5 | 22.5 | 5408.5 |
| 3/15/1989 | 1989 | 3 | 15 | 288 | 28 | 66 | 47 | 15 | 5423.5 |
| 3/16/1989 | 1989 | 3 | 16 | 289 | 29 | 70 | 49.5 | 17.5 | 5441 |
| 3/17/1989 | 1989 | 3 | 17 | 290 | 37 | 71 | 54 | 22 | 5463 |
| 3/18/1989 | 1989 | 3 | 18 | 291 | 34 | 74 | 54 | 22 | 5485 |
| 3/19/1989 | 1989 | 3 | 19 | 292 | 31 | 70 | 50.5 | 18.5 | 5503.5 |
| 3/20/1989 | 1989 | 3 | 20 | 293 | 33 | 49 | 41 | 9 | 5512.5 |
| 3/21/1989 | 1989 | 3 | 21 | 294 | 20 | 61 | 40.5 | 8.5 | 5521 |
| 3/22/1989 | 1989 | 3 | 22 | 295 | 21 | 67 | 44 | 12 | 5533 |
| 3/23/1989 | 1989 | 3 | 23 | 296 | 25 | 69 | 47 | 15 | 5548 |
| 3/24/1989 | 1989 | 3 | 24 | 297 | 35 | 74 | 54.5 | 22.5 | 5570.5 |
| 3/25/1989 | 1989 | 3 | 25 | 298 | 29 | 68 | 48.5 | 16.5 | 5587 |
| 3/26/1989 | 1989 | 3 | 26 | 299 | 31 | 54 | 42.5 | 10.5 | 5597.5 |
| 3/27/1989 | 1989 | 3 | 27 | 300 | 33 | 59 | 46 | 14 | 5611.5 |
| 3/28/1989 | 1989 | 3 | 28 | 301 | 25 | 68 | 46.5 | 14.5 | 5626 |
| 3/29/1989 | 1989 | 3 | 29 | 302 | 35 | 71 | 53 | 21 | 5647 |
| 3/30/1989 | 1989 | 3 | 30 | 303 | 29 | 68 | 48.5 | 16.5 | 5663.5 |
| 3/31/1989 | 1989 | 3 | 31 | 304 | 23 | 74 | 48.5 | 16.5 | 5680 |
| 4/1/1989 | 1989 | 4 | 1 | 305 | 36 | 69 | 52.5 | 20.5 | 5700.5 |
| 4/2/1989 | 1989 | 4 | 2 | 306 | 34 | 72 | 53 | 21 | 5721.5 |
| 4/3/1989 | 1989 | 4 | 3 | 307 | 44 | 74 | 59 | 27 | 5748.5 |
| 4/4/1989 | 1989 | 4 | 4 | 308 | 41 | 67 | 54 | 22 | 5770.5 |
| 4/5/1989 | 1989 | 4 | 5 | 309 | 27 | 71 | 49 | 17 | 5787.5 |
| 4/6/1989 | 1989 | 4 | 6 | 310 | 27 | 78 | 52.5 | 20.5 | 5808 |
| 4/7/1989 | 1989 | 4 | 7 | 311 | 26 | 84 | 55 | 23 | 5831 |
| 4/8/1989 | 1989 | 4 | 8 | 312 | 30 | 82 | 56 | 24 | 5855 |
| 4/9/1989 | 1989 | 4 | 9 | 313 | 38 | 81 | 59.5 | 27.5 | 5882.5 |
| 4/10/1989 | 1989 | 4 | 10 | 314 | 36 | 59 | 47.5 | 15.5 | 5898 |
| 4/11/1989 | 1989 | 4 | 11 | 315 | 34 | 78 | 56 | 24 | 5922 |
| 4/12/1989 | 1989 | 4 | 12 | 316 | 36 | 71 | 53.5 | 21.5 | 5943.5 |
| 4/13/1989 | 1989 | 4 | 13 | 317 | 33 | 67 | 50 | 18 | 5961.5 |
| 4/14/1989 | 1989 | 4 | 14 | 318 | 28 | 76 | 52 | 20 | 5981.5 |
| 4/15/1989 | 1989 | 4 | 15 | 319 | 33 | 79 | 56 | 24 | 6005.5 |
| 4/16/1989 | 1989 | 4 | 16 | 320 | 39 | 79 | 59 | 27 | 6032.5 |
| 4/17/1989 | 1989 | 4 | 17 | 321 | 44 | 81 | 62.5 | 30.5 | 6063 |
| 4/18/1989 | 1989 | 4 | 18 | 322 | 38 | 80 | 59 | 27 | 6090 |
| 4/19/1989 | 1989 | 4 | 19 | 323 | 36 | 84 | 60 | 28 | 6118 |
| 4/20/1989 | 1989 | 4 | 20 | 324 | 35 | 86 | 60.5 | 28.5 | 6146.5 |
| 4/21/1989 | 1989 | 4 | 21 | 325 | 39 | 85 | 62 | 30 | 6176.5 |
| 4/22/1989 | 1989 | 4 | 22 | 326 | 38 | 81 | 59.5 | 27.5 | 6204 |
| 4/23/1989 | 1989 | 4 | 23 | 327 | 35 | 79 | 57 | 25 | 6229 |
| 4/24/1989 | 1989 | 4 | 24 | 328 | 38 | 80 | 59 | 27 | 6256 |
| 4/25/1989 | 1989 | 4 | 25 | 329 | 35 | 76 | 55.5 | 23.5 | 6279.5 |
| 4/26/1989 | 1989 | 4 | 26 | 330 | 38 | 71 | 54.5 | 22.5 | 6302 |
| 4/27/1989 | 1989 | 4 | 27 | 331 | 33 | 71 | 52 | 20 | 6322 |
| 4/28/1989 | 1989 | 4 | 28 | 332 | 22 | 68 | 45 | 13 | 6335 |
| 4/29/1989 | 1989 | 4 | 29 | 333 | 26 | 70 | 48 | 16 | 6351 |
| 4/30/1989 | 1989 | 4 | 30 | 334 | 28 | 71 | 49.5 | 17.5 | 6368.5 |
| 5/1/1989 | 1989 | 5 | 1 | 335 | 31 | 76 | 53.5 | 21.5 | 6390 |
| 5/2/1989 | 1989 | 5 | 2 | 336 | 32 | 80 | 56 | 24 | 6414 |
| 5/3/1989 | 1989 | 5 | 3 | 337 | 28 | 82 | 55 | 23 | 6437 |
| 5/4/1989 | 1989 | 5 | 4 | 338 | 30 | 82 | 56 | 24 | 6461 |
| 5/5/1989 | 1989 | 5 | 5 | 339 | 28 | 81 | 54.5 | 22.5 | 6483.5 |
| 5/6/1989 | 1989 | 5 | 6 | 340 | 33 | 85 | 59 | 27 | 6510.5 |
| 5/7/1989 | 1989 | 5 | 7 | 341 | 34 | 87 | 60.5 | 28.5 | 6539 |
| 5/8/1989 | 1989 | 5 | 8 | 342 | 39 | 88 | 63.5 | 31.5 | 6570.5 |
| 5/9/1989 | 1989 | 5 | 9 | 343 | 42 | 81 | 61.5 | 29.5 | 6600 |
| 5/10/1989 | 1989 | 5 | 10 | 344 | 47 | 81 | 64 | 32 | 6632 |
| 5/11/1989 | 1989 | 5 | 11 | 345 | 36 | 78 | 57 | 25 | 6657 |
| 5/12/1989 | 1989 | 5 | 12 | 346 | 34 | 68 | 51 | 19 | 6676 |
| 5/13/1989 | 1989 | 5 | 13 | 347 | 34 | 69 | 51.5 | 19.5 | 6695.5 |
| 5/14/1989 | 1989 | 5 | 14 | 348 | 36 | 71 | 53.5 | 21.5 | 6717 |
| 5/15/1989 | 1989 | 5 | 15 | 349 | 37 | 68 | 52.5 | 20.5 | 6737.5 |
| 5/16/1989 | 1989 | 5 | 16 | 350 | 48 | 62 | 55 | 23 | 6760.5 |
| 5/17/1989 | 1989 | 5 | 17 | 351 | 35 | 68 | 51.5 | 19.5 | 6780 |
| 5/18/1989 | 1989 | 5 | 18 | 352 | 35 | 81 | 58 | 26 | 6806 |
| 5/19/1989 | 1989 | 5 | 19 | 353 | 42 | 83 | 62.5 | 30.5 | 6836.5 |
| 5/20/1989 | 1989 | 5 | 20 | 354 | 39 | 87 | 63 | 31 | 6867.5 |
| 5/21/1989 | 1989 | 5 | 21 | 355 | 42 | 89 | 65.5 | 33.5 | 6901 |
| 5/22/1989 | 1989 | 5 | 22 | 356 | 44 | 89 | 66.5 | 34.5 | 6935.5 |
| 5/23/1989 | 1989 | 5 | 23 | 357 | 53 | 90 | 71.5 | 39.5 | 6975 |
| 5/24/1989 | 1989 | 5 | 24 | 358 | 51 | 86 | 68.5 | 36.5 | 7011.5 |
| 5/25/1989 | 1989 | 5 | 25 | 359 | 46 | 82 | 64 | 32 | 7043.5 |
| 5/26/1989 | 1989 | 5 | 26 | 360 | 43 | 82 | 62.5 | 30.5 | 7074 |
| 5/27/1989 | 1989 | 5 | 27 | 361 | 41 | 89 | 65 | 33 | 7107 |
| 5/28/1989 | 1989 | 5 | 28 | 362 | 48 | 89 | 68.5 | 36.5 | 7143.5 |
| 5/29/1989 | 1989 | 5 | 29 | 363 | 49 | 87 | 68 | 36 | 7179.5 |
| 5/30/1989 | 1989 | 5 | 30 | 364 | 49 | 83 | 66 | 34 | 7213.5 |
| 5/31/1989 | 1989 | 5 | 31 | 365 | 39 | 83 | 61 | 29 | 7242.5 |
| 6/1/1989 | 1989 | 6 | 1 | 1 | 41 | 82 | 61.5 | 29.5 | 29.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/2/1989 | 1989 | 6 | 2 | 2 | 38 | 86 | 62 | 30 | 59.5 |
| 6/3/1989 | 1989 | 6 | 3 | 3 | 39 | 79 | 59 | 27 | 86.5 |
| 6/4/1989 | 1989 | 6 | 4 | 4 | 41 | 82 | 61.5 | 29.5 | 116 |
| 6/5/1989 | 1989 | 6 | 5 | 5 | 43 | 86 | 64.5 | 32.5 | 148.5 |
| 6/6/1989 | 1989 | 6 | 6 | 6 | 41 | 80 | 60.5 | 28.5 | 177 |
| 6/7/1989 | 1989 | 6 | 7 | 7 | 40 | 88 | 64 | 32 | 209 |
| 6/8/1989 | 1989 | 6 | 8 | 8 | 50 | 79 | 64.5 | 32.5 | 241.5 |
| 6/9/1989 | 1989 | 6 | 9 | 9 | 40 | 80 | 60 | 28 | 269.5 |
| 6/10/1989 | 1989 | 6 | 10 | 10 | 45 | 85 | 65 | 33 | 302.5 |
| 6/11/1989 | 1989 | 6 | 11 | 11 | 47 | 85 | 66 | 34 | 336.5 |
| 6/12/1989 | 1989 | 6 | 12 | 12 | 51 | 82 | 66.5 | 34.5 | 371 |
| 6/13/1989 | 1989 | 6 | 13 | 13 | 43 | 83 | 63 | 31 | 402 |
| 6/14/1989 | 1989 | 6 | 14 | 14 | 41 | 81 | 61 | 29 | 431 |
| 6/15/1989 | 1989 | 6 | 15 | 15 | 49 | 89 | 69 | 37 | 468 |
| 6/16/1989 | 1989 | 6 | 16 | 16 | 58 | 92 | 75 | 43 | 511 |
| 6/17/1989 | 1989 | 6 | 17 | 17 | 58 | 95 | 76.5 | 44.5 | 555.5 |
| 6/18/1989 | 1989 | 6 | 18 | 18 | 55 | 97 | 76 | 44 | 599.5 |
| 6/19/1989 | 1989 | 6 | 19 | 19 | 56 | 98 | 77 | 45 | 644.5 |
| 6/20/1989 | 1989 | 6 | 20 | 20 | 53 | 89 | 71 | 39 | 683.5 |
| 6/21/1989 | 1989 | 6 | 21 | 21 | 59 | 91 | 75 | 43 | 726.5 |
| 6/22/1989 | 1989 | 6 | 22 | 22 | 46 | 88 | 67 | 35 | 761.5 |
| 6/23/1989 | 1989 | 6 | 23 | 23 | 45 | 89 | 67 | 35 | 796.5 |
| 6/24/1989 | 1989 | 6 | 24 | 24 | 48 | 88 | 68 | 36 | 832.5 |
| 6/25/1989 | 1989 | 6 | 25 | 25 | 49 | 88 | 68.5 | 36.5 | 869 |
| 6/26/1989 | 1989 | 6 | 26 | 26 | 46 | 86 | 66 | 34 | 903 |
| 6/27/1989 | 1989 | 6 | 27 | 27 | 47 | 90 | 68.5 | 36.5 | 939.5 |
| 6/28/1989 | 1989 | 6 | 28 | 28 | 53 | 87 | 70 | 38 | 977.5 |
| 6/29/1989 | 1989 | 6 | 29 | 29 | 54 | 88 | 71 | 39 | 1016.5 |
| 6/30/1989 | 1989 | 6 | 30 | 30 | 59 | 88 | 73.5 | 41.5 | 1058 |
| 7/1/1989 | 1989 | 7 | 1 | 31 | 53 | 95 | 74 | 42 | 1100 |
| 7/2/1989 | 1989 | 7 | 2 | 32 | 54 | 99 | 76.5 | 44.5 | 1144.5 |
| 7/3/1989 | 1989 | 7 | 3 | 33 | 50 | 100 | 75 | 43 | 1187.5 |
| 7/4/1989 | 1989 | 7 | 4 | 34 | 51 | 101 | 76 | 44 | 1231.5 |
| 7/5/1989 | 1989 | 7 | 5 | 35 | 56 | 100 | 78 | 46 | 1277.5 |
| 7/6/1989 | 1989 | 7 | 6 | 36 | 60 | 97 | 78.5 | 46.5 | 1324 |
| 7/7/1989 | 1989 | 7 | 7 | 37 | 61 | 97 | 79 | 47 | 1371 |
| 7/8/1989 | 1989 | 7 | 8 | 38 | 60 | 94 | 77 | 45 | 1416 |
| 7/9/1989 | 1989 | 7 | 9 | 39 | 60 | 91 | 75.5 | 43.5 | 1459.5 |
| 7/10/1989 | 1989 | 7 | 10 | 40 | 56 | 87 | 71.5 | 39.5 | 1499 |
| 7/11/1989 | 1989 | 7 | 11 | 41 | 57 | 79 | 68 | 36 | 1535 |
| 7/12/1989 | 1989 | 7 | 12 | 42 | 54 | 87 | 70.5 | 38.5 | 1573.5 |
| 7/13/1989 | 1989 | 7 | 13 | 43 | 58 | 94 | 76 | 44 | 1617.5 |
| 7/14/1989 | 1989 | 7 | 14 | 44 | 58 | 93 | 75.5 | 43.5 | 1661 |
| 7/15/1989 | 1989 | 7 | 15 | 45 | 56 | 96 | 76 | 44 | 1705 |
| 7/16/1989 | 1989 | 7 | 16 | 46 | 57 | 92 | 74.5 | 42.5 | 1747.5 |
| 7/17/1989 | 1989 | 7 | 17 | 47 | 57 | 96 | 76.5 | 44.5 | 1792 |
| 7/18/1989 | 1989 | 7 | 18 | 48 | 50 | 98 | 74 | 42 | 1834 |
| 7/19/1989 | 1989 | 7 | 19 | 49 | 63 | 86 | 74.5 | 42.5 | 1876.5 |
| 7/20/1989 | 1989 | 7 | 20 | 50 | 56 | 91 | 73.5 | 41.5 | 1918 |
| 7/21/1989 | 1989 | 7 | 21 | 51 | 59 | 93 | 76 | 44 | 1962 |
| 7/22/1989 | 1989 | 7 | 22 | 52 | 56 | 86 | 71 | 39 | 2001 |
| 7/23/1989 | 1989 | 7 | 23 | 53 | 56 | 81 | 68.5 | 36.5 | 2037.5 |
| 7/24/1989 | 1989 | 7 | 24 | 54 | 56 | 84 | 70 | 38 | 2075.5 |
| 7/25/1989 | 1989 | 7 | 25 | 55 | 57 | 80 | 68.5 | 36.5 | 2112 |
| 7/26/1989 | 1989 | 7 | 26 | 56 | 56 | 75 | 65.5 | 33.5 | 2145.5 |
| 7/27/1989 | 1989 | 7 | 27 | 57 | 56 | 81 | 68.5 | 36.5 | 2182 |
| 7/28/1989 | 1989 | 7 | 28 | 58 | 54 | 80 | 67 | 35 | 2217 |
| 7/29/1989 | 1989 | 7 | 29 | 59 | 52 | 83 | 67.5 | 35.5 | 2252.5 |
| 7/30/1989 | 1989 | 7 | 30 | 60 | 55 | 87 | 71 | 39 | 2291.5 |
| 7/31/1989 | 1989 | 7 | 31 | 61 | 59 | 87 | 73 | 41 | 2332.5 |
| 8/1/1989 | 1989 | 8 | 1 | 62 | 60 | 77 | 68.5 | 36.5 | 2369 |
| 8/2/1989 | 1989 | 8 | 2 | 63 | 52 | 86 | 69 | 37 | 2406 |
| 8/3/1989 | 1989 | 8 | 3 | 64 | 51 | 85 | 68 | 36 | 2442 |
| 8/4/1989 | 1989 | 8 | 4 | 65 | 57 | 87 | 72 | 40 | 2482 |
| 8/5/1989 | 1989 | 8 | 5 | 66 | 50 | 89 | 69.5 | 37.5 | 2519.5 |
| 8/6/1989 | 1989 | 8 | 6 | 67 | 53 | 92 | 72.5 | 40.5 | 2560 |
| 8/7/1989 | 1989 | 8 | 7 | 68 | 56 | 88 | 72 | 40 | 2600 |
| 8/8/1989 | 1989 | 8 | 8 | 69 | 57 | 89 | 73 | 41 | 2641 |
| 8/9/1989 | 1989 | 8 | 9 | 70 | 57 | 86 | 71.5 | 39.5 | 2680.5 |
| 8/10/1989 | 1989 | 8 | 10 | 71 | 57 | 90 | 73.5 | 41.5 | 2722 |
| 8/11/1989 | 1989 | 8 | 11 | 72 | 56 | 91 | 73.5 | 41.5 | 2763.5 |
| 8/12/1989 | 1989 | 8 | 12 | 73 | 53 | 88 | 70.5 | 38.5 | 2802 |
| 8/13/1989 | 1989 | 8 | 13 | 74 | 54 | 87 | 70.5 | 38.5 | 2840.5 |
| 8/14/1989 | 1989 | 8 | 14 | 75 | 55 | 88 | 71.5 | 39.5 | 2880 |
| 8/15/1989 | 1989 | 8 | 15 | 76 | 58 | 88 | 73 | 41 | 2921 |
| 8/16/1989 | 1989 | 8 | 16 | 77 | 53 | 87 | 70 | 38 | 2959 |
| 8/17/1989 | 1989 | 8 | 17 | 78 | 55 | 89 | 72 | 40 | 2999 |
| 8/18/1989 | 1989 | 8 | 18 | 79 | 51 | 87 | 69 | 37 | 3036 |
| 8/19/1989 | 1989 | 8 | 19 | 80 | 52 | 88 | 70 | 38 | 3074 |
| 8/20/1989 | 1989 | 8 | 20 | 81 | 49 | 87 | 68 | 36 | 3110 |
| 8/21/1989 | 1989 | 8 | 21 | 82 | 50 | 84 | 67 | 35 | 3145 |
| 8/22/1989 | 1989 | 8 | 22 | 83 | 48 | 84 | 66 | 34 | 3179 |
| 8/23/1989 | 1989 | 8 | 23 | 84 | 45 | 87 | 66 | 34 | 3213 |
| 8/24/1989 | 1989 | 8 | 24 | 85 | 45 | 86 | 65.5 | 33.5 | 3246.5 |
| 8/25/1989 | 1989 | 8 | 25 | 86 | 43 | 87 | 65 | 33 | 3279.5 |
| 8/26/1989 | 1989 | 8 | 26 | 87 | 42 | 86 | 64 | 32 | 3311.5 |
| 8/27/1989 | 1989 | 8 | 27 | 88 | 44 | 82 | 63 | 31 | 3342.5 |
| 8/28/1989 | 1989 | 8 | 28 | 89 | 52 | 84 | 68 | 36 | 3378.5 |
| 8/29/1989 | 1989 | 8 | 29 | 90 | 44 | 89 | 66.5 | 34.5 | 3413 |
| 8/30/1989 | 1989 | 8 | 30 | 91 | 52 | 86 | 69 | 37 | 3450 |
| 8/31/1989 | 1989 | 8 | 31 | 92 | 56 | 83 | 69.5 | 37.5 | 3487.5 |
| 9/1/1989 | 1989 | 9 | 1 | 93 | 45 | 88 | 66.5 | 34.5 | 3522 |
| 9/2/1989 | 1989 | 9 | 2 | 94 | 46 | 89 | 67.5 | 35.5 | 3557.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/3/1989 | 1989 | 9 | 3 | 95 | 51 | 84 | 67.5 | 35.5 | 3593 |
| 9/4/1989 | 1989 | 9 | 4 | 96 | 54 | 81 | 67.5 | 35.5 | 3628.5 |
| 9/5/1989 | 1989 | 9 | 5 | 97 | 52 | 74 | 63 | 31 | 3659.5 |
| 9/6/1989 | 1989 | 9 | 6 | 98 | 51 | 82 | 66.5 | 34.5 | 3694 |
| 9/7/1989 | 1989 | 9 | 7 | 99 | 52 | 86 | 69 | 37 | 3731 |
| 9/8/1989 | 1989 | 9 | 8 | 100 | 52 | 83 | 67.5 | 35.5 | 3766.5 |
| 9/9/1989 | 1989 | 9 | 9 | 101 | 41 | 86 | 63.5 | 31.5 | 3798 |
| 9/10/1989 | 1989 | 9 | 10 | 102 | 41 | 82 | 61.5 | 29.5 | 3827.5 |
| 9/11/1989 | 1989 | 9 | 11 | 103 | 39 | 80 | 59.5 | 27.5 | 3855 |
| 9/12/1989 | 1989 | 9 | 12 | 104 | 42 | 79 | 60.5 | 28.5 | 3883.5 |
| 9/13/1989 | 1989 | 9 | 13 | 105 | 39 | 73 | 56 | 24 | 3907.5 |
| 9/14/1989 | 1989 | 9 | 14 | 106 | 34 | 76 | 55 | 23 | 3930.5 |
| 9/15/1989 | 1989 | 9 | 15 | 107 | 35 | 84 | 59.5 | 27.5 | 3958 |
| 9/16/1989 | 1989 | 9 | 16 | 108 | 34 | 83 | 58.5 | 26.5 | 3984.5 |
| 9/17/1989 | 1989 | 9 | 17 | 109 | 38 | 83 | 60.5 | 28.5 | 4013 |
| 9/18/1989 | 1989 | 9 | 18 | 110 | 48 | 86 | 67 | 35 | 4048 |
| 9/19/1989 | 1989 | 9 | 19 | 111 | 46 | 84 | 65 | 33 | 4081 |
| 9/20/1989 | 1989 | 9 | 20 | 112 | 49 | 81 | 65 | 33 | 4114 |
| 9/21/1989 | 1989 | 9 | 21 | 113 | 34 | 82 | 58 | 26 | 4140 |
| 9/22/1989 | 1989 | 9 | 22 | 114 | 48 | 71 | 59.5 | 27.5 | 4167.5 |
| 9/23/1989 | 1989 | 9 | 23 | 115 | 48 | 79 | 63.5 | 31.5 | 4199 |
| 9/24/1989 | 1989 | 9 | 24 | 116 | 42 | 83 | 62.5 | 30.5 | 4229.5 |
| 9/25/1989 | 1989 | 9 | 25 | 117 | 39 | 82 | 60.5 | 28.5 | 4258 |
| 9/26/1989 | 1989 | 9 | 26 | 118 | 43 | 83 | 63 | 31 | 4289 |
| 9/27/1989 | 1989 | 9 | 27 | 119 | 44 | 82 | 63 | 31 | 4320 |
| 9/28/1989 | 1989 | 9 | 28 | 120 | 39 | 86 | 62.5 | 30.5 | 4350.5 |
| 9/29/1989 | 1989 | 9 | 29 | 121 | 38 | 84 | 61 | 29 | 4379.5 |
| 9/30/1989 | 1989 | 9 | 30 | 122 | 40 | 87 | 63.5 | 31.5 | 4411 |
| 10/1/1989 | 1989 | 10 | 1 | 123 | 44 | 81 | 62.5 | 30.5 | 4441.5 |
| 10/2/1989 | 1989 | 10 | 2 | 124 | 42 | 80 | 61 | 29 | 4470.5 |
| 10/3/1989 | 1989 | 10 | 3 | 125 | 44 | 72 | 58 | 26 | 4496.5 |
| 10/4/1989 | 1989 | 10 | 4 | 126 | 47 | 64 | 55.5 | 23.5 | 4520 |
| 10/5/1989 | 1989 | 10 | 5 | 127 | 44 | 55 | 49.5 | 17.5 | 4537.5 |
| 10/6/1989 | 1989 | 10 | 6 | 128 | 34 | 69 | 51.5 | 19.5 | 4557 |
| 10/7/1989 | 1989 | 10 | 7 | 129 | 37 | 69 | 53 | 21 | 4578 |
| 10/8/1989 | 1989 | 10 | 8 | 130 | 36 | 71 | 53.5 | 21.5 | 4599.5 |
| 10/9/1989 | 1989 | 10 | 9 | 131 | 34 | 75 | 54.5 | 22.5 | 4622 |
| 10/10/1989 | 1989 | 10 | 10 | 132 | 33 | 81 | 57 | 25 | 4647 |
| 10/11/1989 | 1989 | 10 | 11 | 133 | 34 | 82 | 58 | 26 | 4673 |
| 10/12/1989 | 1989 | 10 | 12 | 134 | 33 | 82 | 57.5 | 25.5 | 4698.5 |
| 10/13/1989 | 1989 | 10 | 13 | 135 | 34 | 80 | 57 | 25 | 4723.5 |
| 10/14/1989 | 1989 | 10 | 14 | 136 | 35 | 79 | 57 | 25 | 4748.5 |
| 10/15/1989 | 1989 | 10 | 15 | 137 | 46 | 80 | 63 | 31 | 4779.5 |
| 10/16/1989 | 1989 | 10 | 16 | 138 | 36 | 72 | 54 | 22 | 4801.5 |
| 10/17/1989 | 1989 | 10 | 17 | 139 | 34 | 61 | 47.5 | 15.5 | 4817 |
| 10/18/1989 | 1989 | 10 | 18 | 140 | 33 | 60 | 46.5 | 14.5 | 4831.5 |
| 10/19/1989 | 1989 | 10 | 19 | 141 | 29 | 65 | 47 | 15 | 4846.5 |
| 10/20/1989 | 1989 | 10 | 20 | 142 | 31 | 59 | 45 | 13 | 4859.5 |
| 10/21/1989 | 1989 | 10 | 21 | 143 | 36 | 66 | 51 | 19 | 4878.5 |
| 10/22/1989 | 1989 | 10 | 22 | 144 | 38 | 65 | 51.5 | 19.5 | 4898 |
| 10/23/1989 | 1989 | 10 | 23 | 145 | 33 | 71 | 52 | 20 | 4918 |
| 10/24/1989 | 1989 | 10 | 24 | 146 | 30 | 70 | 50 | 18 | 4936 |
| 10/25/1989 | 1989 | 10 | 25 | 147 | 35 | 71 | 53 | 21 | 4957 |
| 10/26/1989 | 1989 | 10 | 26 | 148 | 34 | 59 | 46.5 | 14.5 | 4971.5 |
| 10/27/1989 | 1989 | 10 | 27 | 149 | 20 | 69 | 44.5 | 12.5 | 4984 |
| 10/28/1989 | 1989 | 10 | 28 | 150 | 22 | 65 | 43.5 | 11.5 | 4995.5 |
| 10/29/1989 | 1989 | 10 | 29 | 151 | 19 | 52 | 35.5 | 3.5 | 4999 |
| 10/30/1989 | 1989 | 10 | 30 | 152 | 19 | 54 | 36.5 | 4.5 | 5003.5 |
| 10/31/1989 | 1989 | 10 | 31 | 153 | 11 | 62 | 36.5 | 4.5 | 5008 |
| 11/1/1989 | 1989 | 11 | 1 | 154 | 19 | 54 | 36.5 | 4.5 | 5012.5 |
| 11/2/1989 | 1989 | 11 | 2 | 155 | 10 | 60 | 35 | 3 | 5015.5 |
| 11/3/1989 | 1989 | 11 | 3 | 156 | -5 | 58 | 26.5 | -5.5 | 5010 |
| 11/4/1989 | 1989 | 11 | 4 | 157 | 15 | 65 | 40 | 8 | 5018 |
| 11/5/1989 | 1989 | 11 | 5 | 158 | 25 | 68 | 46.5 | 14.5 | 5032.5 |
| 11/6/1989 | 1989 | 11 | 6 | 159 | 40 | 65 | 52.5 | 20.5 | 5053 |
| 11/7/1989 | 1989 | 11 | 7 | 160 | 30 | 64 | 47 | 15 | 5068 |
| 11/8/1989 | 1989 | 11 | 8 | 161 | 20 | 57 | 38.5 | 6.5 | 5074.5 |
| 11/9/1989 | 1989 | 11 | 9 | 162 | 18 | 60 | 39 | 7 | 5081.5 |
| 11/10/1989 | 1989 | 11 | 10 | 163 | 25 | 68 | 46.5 | 14.5 | 5096 |
| 11/11/1989 | 1989 | 11 | 11 | 164 | 24 | 71 | 47.5 | 15.5 | 5111.5 |
| 11/12/1989 | 1989 | 11 | 12 | 165 | 23 | 73 | 48 | 16 | 5127.5 |
| 11/13/1989 | 1989 | 11 | 13 | 166 | 24 | 68 | 46 | 14 | 5141.5 |
| 11/14/1989 | 1989 | 11 | 14 | 167 | 24 | 67 | 45.5 | 13.5 | 5155 |
| 11/15/1989 | 1989 | 11 | 15 | 168 | 20 | 53 | 36.5 | 4.5 | 5159.5 |
| 11/16/1989 | 1989 | 11 | 16 | 169 | 19 | 56 | 37.5 | 5.5 | 5165 |
| 11/17/1989 | 1989 | 11 | 17 | 170 | 16 | 50 | 33 | 1 | 5166 |
| 11/18/1989 | 1989 | 11 | 18 | 171 | 15 | 58 | 36.5 | 4.5 | 5170.5 |
| 11/19/1989 | 1989 | 11 | 19 | 172 | 18 | 63 | 40.5 | 8.5 | 5179 |
| 11/20/1989 | 1989 | 11 | 20 | 173 | 18 | 70 | 44 | 12 | 5191 |
| 11/21/1989 | 1989 | 11 | 21 | 174 | 25 | 65 | 45 | 13 | 5204 |
| 11/22/1989 | 1989 | 11 | 22 | 175 | 22 | 65 | 43.5 | 11.5 | 5215.5 |
| 11/23/1989 | 1989 | 11 | 23 | 176 | 19 | 64 | 41.5 | 9.5 | 5225 |
| 11/24/1989 | 1989 | 11 | 24 | 177 | 23 | 63 | 43 | 11 | 5236 |
| 11/25/1989 | 1989 | 11 | 25 | 178 | 39 | 64 | 51.5 | 19.5 | 5255.5 |
| 11/26/1989 | 1989 | 11 | 26 | 179 | 30 | 59 | 44.5 | 12.5 | 5268 |
| 11/27/1989 | 1989 | 11 | 27 | 180 | 21 | 47 | 34 | 2 | 5270 |
| 11/28/1989 | 1989 | 11 | 28 | 181 | 10 | 38 | 24 | -8 | 5262 |
| 11/29/1989 | 1989 | 11 | 29 | 182 | 8 | 36 | 22 | -10 | 5252 |
| 11/30/1989 | 1989 | 11 | 30 | 183 | 15 | 34 | 24.5 | -7.5 | 5244.5 |
| 12/1/1989 | 1989 | 12 | 1 | 184 | 13 | 42 | 27.5 | -4.5 | 5240 |
| 12/2/1989 | 1989 | 12 | 2 | 185 | 12 | 45 | 28.5 | -3.5 | 5236.5 |
| 12/3/1989 | 1989 | 12 | 3 | 186 | 12 | 53 | 32.5 | 0.5 | 5237 |
| 12/4/1989 | 1989 | 12 | 4 | 187 | 14 | 55 | 34.5 | 2.5 | 5239.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/5/1989 | 1989 | 12 | 5 | 188 | 18 | 62 | 40 | 8 | 5247.5 |
| 12/6/1989 | 1989 | 12 | 6 | 189 | 22 | 53 | 37.5 | 5.5 | 5253 |
| 12/7/1989 | 1989 | 12 | 7 | 190 | 20 | 45 | 32.5 | 0.5 | 5253.5 |
| 12/8/1989 | 1989 | 12 | 8 | 191 | 10 | 54 | 32 | 0 | 5253.5 |
| 12/9/1989 | 1989 | 12 | 9 | 192 | 12 | 62 | 37 | 5 | 5258.5 |
| 12/10/1989 | 1989 | 12 | 10 | 193 | 12 | 54 | 33 | 1 | 5259.5 |
| 12/11/1989 | 1989 | 12 | 11 | 194 | -5 | 32 | 13.5 | -18.5 | 5241 |
| 12/12/1989 | 1989 | 12 | 12 | 195 | 0 | 41 | 20.5 | -11.5 | 5229.5 |
| 12/13/1989 | 1989 | 12 | 13 | 196 | 4 | 45 | 24.5 | -7.5 | 5222 |
| 12/14/1989 | 1989 | 12 | 14 | 197 | 11 | 53 | 32 | 0 | 5222 |
| 12/15/1989 | 1989 | 12 | 15 | 198 | 16 | 58 | 37 | 5 | 5227 |
| 12/16/1989 | 1989 | 12 | 16 | 199 | 20 | 49 | 34.5 | 2.5 | 5229.5 |
| 12/17/1989 | 1989 | 12 | 17 | 200 | 9 | 49 | 29 | -3 | 5226.5 |
| 12/18/1989 | 1989 | 12 | 18 | 201 | 20 | 50 | 35 | 3 | 5229.5 |
| 12/19/1989 | 1989 | 12 | 19 | 202 | 15 | 50 | 32.5 | 0.5 | 5230 |
| 12/20/1989 | 1989 | 12 | 20 | 203 | 10 | 51 | 30.5 | -1.5 | 5228.5 |
| 12/21/1989 | 1989 | 12 | 21 | 204 | 9 | 47 | 28 | -4 | 5224.5 |
| 12/22/1989 | 1989 | 12 | 22 | 205 | 9 | 45 | 27 | -5 | 5219.5 |
| 12/23/1989 | 1989 | 12 | 23 | 206 | 10 | 52 | 31 | -1 | 5218.5 |
| 12/24/1989 | 1989 | 12 | 24 | 207 | 12 | 52 | 32 | 0 | 5218.5 |
| 12/25/1989 | 1989 | 12 | 25 | 208 | 10 | 53 | 31.5 | -0.5 | 5218 |
| 12/26/1989 | 1989 | 12 | 26 | 209 | 9 | 55 | 32 | 0 | 5218 |
| 12/27/1989 | 1989 | 12 | 27 | 210 | 8 | 51 | 29.5 | -2.5 | 5215.5 |
| 12/28/1989 | 1989 | 12 | 28 | 211 | 14 | 51 | 32.5 | 0.5 | 5216 |
| 12/29/1989 | 1989 | 12 | 29 | 212 | 16 | 44 | 30 | -2 | 5214 |
| 12/30/1989 | 1989 | 12 | 30 | 213 | 17 | 42 | 29.5 | -2.5 | 5211.5 |
| 12/31/1989 | 1989 | 12 | 31 | 214 | 8 | 43 | 25.5 | -6.5 | 5205 |
| 1/1/1990 | 1990 | 1 | 1 | 215 | 4 | 49 | 26.5 | -5.5 | 5199.5 |
| 1/2/1990 | 1990 | 1 | 2 | 216 | 9 | 39 | 24 | -8 | 5191.5 |
| 1/3/1990 | 1990 | 1 | 3 | 217 | 18 | 39 | 28.5 | -3.5 | 5188 |
| 1/4/1990 | 1990 | 1 | 4 | 218 | -3 | 34 | 15.5 | -16.5 | 5171.5 |
| 1/5/1990 | 1990 | 1 | 5 | 219 | -1 | 32 | 15.5 | -16.5 | 5155 |
| 1/6/1990 | 1990 | 1 | 6 | 220 | -1 | 42 | 20.5 | -11.5 | 5143.5 |
| 1/7/1990 | 1990 | 1 | 7 | 221 | 2 | 52 | 27 | -5 | 5138.5 |
| 1/8/1990 | 1990 | 1 | 8 | 222 | 5 | 55 | 30 | -2 | 5136.5 |
| 1/9/1990 | 1990 | 1 | 9 | 223 | 11 | 61 | 36 | 4 | 5140.5 |
| 1/10/1990 | 1990 | 1 | 10 | 224 | 10 | 62 | 36 | 4 | 5144.5 |
| 1/11/1990 | 1990 | 1 | 11 | 225 | 9 | 66 | 37.5 | 5.5 | 5150 |
| 1/12/1990 | 1990 | 1 | 12 | 226 | 11 | 47 | 29 | -3 | 5147 |
| 1/13/1990 | 1990 | 1 | 13 | 227 | 20 | 59 | 39.5 | 7.5 | 5154.5 |
| 1/14/1990 | 1990 | 1 | 14 | 228 | 15 | 59 | 37 | 5 | 5159.5 |
| 1/15/1990 | 1990 | 1 | 15 | 229 | 14 | 50 | 32 | 0 | 5159.5 |
| 1/16/1990 | 1990 | 1 | 16 | 230 | 11 | 46 | 28.5 | -3.5 | 5156 |
| 1/17/1990 | 1990 | 1 | 17 | 231 | 4 | 43 | 23.5 | -8.5 | 5147.5 |
| 1/18/1990 | 1990 | 1 | 18 | 232 | 6 | 37 | 21.5 | -10.5 | 5137 |
| 1/19/1990 | 1990 | 1 | 19 | 233 | 10 | 38 | 24 | -8 | 5129 |
| 1/20/1990 | 1990 | 1 | 20 | 234 | 15 | 47 | 31 | -1 | 5128 |
| 1/21/1990 | 1990 | 1 | 21 | 235 | 8 | 38 | 23 | -9 | 5119 |
| 1/22/1990 | 1990 | 1 | 22 | 236 | -1 | 35 | 17 | -15 | 5104 |
| 1/23/1990 | 1990 | 1 | 23 | 237 | 11 | 49 | 30 | -2 | 5102 |
| 1/24/1990 | 1990 | 1 | 24 | 238 | 9 | 36 | 22.5 | -9.5 | 5092.5 |
| 1/25/1990 | 1990 | 1 | 25 | 239 | -1 | 47 | 23 | -9 | 5083.5 |
| 1/26/1990 | 1990 | 1 | 26 | 240 | 5 | 59 | 32 | 0 | 5083.5 |
| 1/27/1990 | 1990 | 1 | 27 | 241 | 10 | 42 | 26 | -6 | 5077.5 |
| 1/28/1990 | 1990 | 1 | 28 | 242 | 4 | 40 | 22 | -10 | 5067.5 |
| 1/29/1990 | 1990 | 1 | 29 | 243 | -3 | 49 | 23 | -9 | 5058.5 |
| 1/30/1990 | 1990 | 1 | 30 | 244 | 5 | 48 | 26.5 | -5.5 | 5053 |
| 1/31/1990 | 1990 | 1 | 31 | 245 | 15 | 43 | 29 | -3 | 5050 |
| 2/1/1990 | 1990 | 2 | 1 | 246 | 20 | 42 | 31 | -1 | 5049 |
| 2/2/1990 | 1990 | 2 | 2 | 247 | 21 | 35 | 28 | -4 | 5045 |
| 2/3/1990 | 1990 | 2 | 3 | 248 | 9 | 42 | 25.5 | -6.5 | 5038.5 |
| 2/4/1990 | 1990 | 2 | 4 | 249 | 8 | 42 | 25 | -7 | 5031.5 |
| 2/5/1990 | 1990 | 2 | 5 | 250 | 14 | 41 | 27.5 | -4.5 | 5027 |
| 2/6/1990 | 1990 | 2 | 6 | 251 | 10 | 50 | 30 | -2 | 5025 |
| 2/7/1990 | 1990 | 2 | 7 | 252 | 10 | 55 | 32.5 | 0.5 | 5025.5 |
| 2/8/1990 | 1990 | 2 | 8 | 253 | 23 | 50 | 36.5 | 4.5 | 5030 |
| 2/9/1990 | 1990 | 2 | 9 | 254 | 20 | 47 | 33.5 | 1.5 | 5031.5 |
| 2/10/1990 | 1990 | 2 | 10 | 255 | 18 | 53 | 35.5 | 3.5 | 5035 |
| 2/11/1990 | 1990 | 2 | 11 | 256 | 20 | 63 | 41.5 | 9.5 | 5044.5 |
| 2/12/1990 | 1990 | 2 | 12 | 257 | 20 | 64 | 42 | 10 | 5054.5 |
| 2/13/1990 | 1990 | 2 | 13 | 258 | 36 | 59 | 47.5 | 15.5 | 5070 |
| 2/14/1990 | 1990 | 2 | 14 | 259 | 33 | 51 | 42 | 10 | 5080 |
| 2/15/1990 | 1990 | 2 | 15 | 260 | 13 | 33 | 23 | -9 | 5071 |
| 2/16/1990 | 1990 | 2 | 16 | 261 | 3 | 42 | 22.5 | -9.5 | 5061.5 |
| 2/17/1990 | 1990 | 2 | 17 | 262 | 12 | 52 | 32 | 0 | 5061.5 |
| 2/18/1990 | 1990 | 2 | 18 | 263 | 15 | 54 | 34.5 | 2.5 | 5064 |
| 2/19/1990 | 1990 | 2 | 19 | 264 | 26 | 41 | 33.5 | 1.5 | 5065.5 |
| 2/20/1990 | 1990 | 2 | 20 | 265 | 6 | 41 | 23.5 | -8.5 | 5057 |
| 2/21/1990 | 1990 | 2 | 21 | 266 | 15 | 47 | 31 | -1 | 5056 |
| 2/22/1990 | 1990 | 2 | 22 | 267 | 18 | 52 | 35 | 3 | 5059 |
| 2/23/1990 | 1990 | 2 | 23 | 268 | 16 | 59 | 37.5 | 5.5 | 5064.5 |
| 2/24/1990 | 1990 | 2 | 24 | 269 | 15 | 66 | 40.5 | 8.5 | 5073 |
| 2/25/1990 | 1990 | 2 | 25 | 270 | 18 | 67 | 42.5 | 10.5 | 5083.5 |
| 2/26/1990 | 1990 | 2 | 26 | 271 | 26 | 64 | 45 | 13 | 5096.5 |
| 2/27/1990 | 1990 | 2 | 27 | 272 | 33 | 47 | 40 | 8 | 5104.5 |
| 2/28/1990 | 1990 | 2 | 28 | 273 | 30 | 46 | 38 | 6 | 5110.5 |
| 3/1/1990 | 1990 | 3 | 1 | 274 | 30 | 55 | 42.5 | 10.5 | 5121 |
| 3/2/1990 | 1990 | 3 | 2 | 275 | 22 | 59 | 40.5 | 8.5 | 5129.5 |
| 3/3/1990 | 1990 | 3 | 3 | 276 | 23 | 49 | 36 | 4 | 5133.5 |
| 3/4/1990 | 1990 | 3 | 4 | 277 | 22 | 62 | 42 | 10 | 5143.5 |
| 3/5/1990 | 1990 | 3 | 5 | 278 | 28 | 64 | 46 | 14 | 5157.5 |
| 3/6/1990 | 1990 | 3 | 6 | 279 | 20 | 56 | 38 | 6 | 5163.5 |
| 3/7/1990 | 1990 | 3 | 7 | 280 | 22 | 58 | 40 | 8 | 5171.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/8/1990 | 1990 | 3 | 8 | 281 | 17 | 65 | 41 | 9 | 5180.5 |
| 3/9/1990 | 1990 | 3 | 9 | 282 | 31 | 64 | 47.5 | 15.5 | 5196 |
| 3/10/1990 | 1990 | 3 | 10 | 283 | 33 | 52 | 42.5 | 10.5 | 5206.5 |
| 3/11/1990 | 1990 | 3 | 11 | 284 | 34 | 48 | 41 | 9 | 5215.5 |
| 3/12/1990 | 1990 | 3 | 12 | 285 | 28 | 57 | 42.5 | 10.5 | 5226 |
| 3/13/1990 | 1990 | 3 | 13 | 286 | 27 | 38 | 32.5 | 0.5 | 5226.5 |
| 3/14/1990 | 1990 | 3 | 14 | 287 | 20 | 42 | 31 | -1 | 5225.5 |
| 3/15/1990 | 1990 | 3 | 15 | 288 | 18 | 45 | 31.5 | -0.5 | 5225 |
| 3/16/1990 | 1990 | 3 | 16 | 289 | 14 | 52 | 33 | 1 | 5226 |
| 3/17/1990 | 1990 | 3 | 17 | 290 | 18 | 63 | 40.5 | 8.5 | 5234.5 |
| 3/18/1990 | 1990 | 3 | 18 | 291 | 25 | 64 | 44.5 | 12.5 | 5247 |
| 3/19/1990 | 1990 | 3 | 19 | 292 | 31 | 64 | 47.5 | 15.5 | 5262.5 |
| 3/20/1990 | 1990 | 3 | 20 | 293 | 29 | 72 | 50.5 | 18.5 | 5281 |
| 3/21/1990 | 1990 | 3 | 21 | 294 | 35 | 71 | 53 | 21 | 5302 |
| 3/22/1990 | 1990 | 3 | 22 | 295 | 26 | 75 | 50.5 | 18.5 | 5320.5 |
| 3/23/1990 | 1990 | 3 | 23 | 296 | 34 | 75 | 54.5 | 22.5 | 5343 |
| 3/24/1990 | 1990 | 3 | 24 | 297 | 28 | 75 | 51.5 | 19.5 | 5362.5 |
| 3/25/1990 | 1990 | 3 | 25 | 298 | 39 | 72 | 55.5 | 23.5 | 5386 |
| 3/26/1990 | 1990 | 3 | 26 | 299 | 33 | 70 | 51.5 | 19.5 | 5405.5 |
| 3/27/1990 | 1990 | 3 | 27 | 300 | 42 | 68 | 55 | 23 | 5428.5 |
| 3/28/1990 | 1990 | 3 | 28 | 301 | 30 | 62 | 46 | 14 | 5442.5 |
| 3/29/1990 | 1990 | 3 | 29 | 302 | 28 | 49 | 38.5 | 6.5 | 5449 |
| 3/30/1990 | 1990 | 3 | 30 | 303 | 29 | 52 | 40.5 | 8.5 | 5457.5 |
| 3/31/1990 | 1990 | 3 | 31 | 304 | 33 | 53 | 43 | 11 | 5468.5 |
| 4/1/1990 | 1990 | 4 | 1 | 305 | 28 | 54 | 41 | 9 | 5477.5 |
| 4/2/1990 | 1990 | 4 | 2 | 306 | 27 | 46 | 36.5 | 4.5 | 5482 |
| 4/3/1990 | 1990 | 4 | 3 | 307 | 29 | 62 | 45.5 | 13.5 | 5495.5 |
| 4/4/1990 | 1990 | 4 | 4 | 308 | 28 | 69 | 48.5 | 16.5 | 5512 |
| 4/5/1990 | 1990 | 4 | 5 | 309 | 41 | 63 | 52 | 20 | 5532 |
| 4/6/1990 | 1990 | 4 | 6 | 310 | 29 | 62 | 45.5 | 13.5 | 5545.5 |
| 4/7/1990 | 1990 | 4 | 7 | 311 | 35 | 64 | 49.5 | 17.5 | 5563 |
| 4/8/1990 | 1990 | 4 | 8 | 312 | 38 | 65 | 51.5 | 19.5 | 5582.5 |
| 4/9/1990 | 1990 | 4 | 9 | 313 | 35 | 64 | 49.5 | 17.5 | 5600 |
| 4/10/1990 | 1990 | 4 | 10 | 314 | 31 | 70 | 50.5 | 18.5 | 5618.5 |
| 4/11/1990 | 1990 | 4 | 11 | 315 | 33 | 74 | 53.5 | 21.5 | 5640 |
| 4/12/1990 | 1990 | 4 | 12 | 316 | 34 | 75 | 54.5 | 22.5 | 5662.5 |
| 4/13/1990 | 1990 | 4 | 13 | 317 | 33 | 79 | 56 | 24 | 5686.5 |
| 4/14/1990 | 1990 | 4 | 14 | 318 | 32 | 82 | 57 | 25 | 5711.5 |
| 4/15/1990 | 1990 | 4 | 15 | 319 | 39 | 81 | 60 | 28 | 5739.5 |
| 4/16/1990 | 1990 | 4 | 16 | 320 | 36 | 78 | 57 | 25 | 5764.5 |
| 4/17/1990 | 1990 | 4 | 17 | 321 | 35 | 55 | 45 | 13 | 5777.5 |
| 4/18/1990 | 1990 | 4 | 18 | 322 | 38 | 54 | 46 | 14 | 5791.5 |
| 4/19/1990 | 1990 | 4 | 19 | 323 | 30 | 62 | 46 | 14 | 5805.5 |
| 4/20/1990 | 1990 | 4 | 20 | 324 | 32 | 73 | 52.5 | 20.5 | 5826 |
| 4/21/1990 | 1990 | 4 | 21 | 325 | 39 | 76 | 57.5 | 25.5 | 5851.5 |
| 4/22/1990 | 1990 | 4 | 22 | 326 | 40 | 77 | 58.5 | 26.5 | 5878 |
| 4/23/1990 | 1990 | 4 | 23 | 327 | 42 | 69 | 55.5 | 23.5 | 5901.5 |
| 4/24/1990 | 1990 | 4 | 24 | 328 | 36 | 64 | 50 | 18 | 5919.5 |
| 4/25/1990 | 1990 | 4 | 25 | 329 | 32 | 64 | 48 | 16 | 5935.5 |
| 4/26/1990 | 1990 | 4 | 26 | 330 | 34 | 69 | 51.5 | 19.5 | 5955 |
| 4/27/1990 | 1990 | 4 | 27 | 331 | 34 | 73 | 53.5 | 21.5 | 5976.5 |
| 4/28/1990 | 1990 | 4 | 28 | 332 | 38 | 78 | 58 | 26 | 6002.5 |
| 4/29/1990 | 1990 | 4 | 29 | 333 | 43 | 76 | 59.5 | 27.5 | 6030 |
| 4/30/1990 | 1990 | 4 | 30 | 334 | 36 | 62 | 49 | 17 | 6047 |
| 5/1/1990 | 1990 | 5 | 1 | 335 | 36 | 55 | 45.5 | 13.5 | 6060.5 |
| 5/2/1990 | 1990 | 5 | 2 | 336 | 33 | 45 | 39 | 7 | 6067.5 |
| 5/3/1990 | 1990 | 5 | 3 | 337 | 31 | 59 | 45 | 13 | 6080.5 |
| 5/4/1990 | 1990 | 5 | 4 | 338 | 35 | 66 | 50.5 | 18.5 | 6099 |
| 5/5/1990 | 1990 | 5 | 5 | 339 | 36 | 66 | 51 | 19 | 6118 |
| 5/6/1990 | 1990 | 5 | 6 | 340 | 36 | 75 | 55.5 | 23.5 | 6141.5 |
| 5/7/1990 | 1990 | 5 | 7 | 341 | 42 | 77 | 59.5 | 27.5 | 6169 |
| 5/8/1990 | 1990 | 5 | 8 | 342 | 49 | 78 | 63.5 | 31.5 | 6200.5 |
| 5/9/1990 | 1990 | 5 | 9 | 343 | 38 | 76 | 57 | 25 | 6225.5 |
| 5/10/1990 | 1990 | 5 | 10 | 344 | 34 | 78 | 56 | 24 | 6249.5 |
| 5/11/1990 | 1990 | 5 | 11 | 345 | 39 | 70 | 54.5 | 22.5 | 6272 |
| 5/12/1990 | 1990 | 5 | 12 | 346 | 44 | 76 | 60 | 28 | 6300 |
| 5/13/1990 | 1990 | 5 | 13 | 347 | 40 | 81 | 60.5 | 28.5 | 6328.5 |
| 5/14/1990 | 1990 | 5 | 14 | 348 | 39 | 80 | 59.5 | 27.5 | 6356 |
| 5/15/1990 | 1990 | 5 | 15 | 349 | 40 | 76 | 58 | 26 | 6382 |
| 5/16/1990 | 1990 | 5 | 16 | 350 | 39 | 75 | 57 | 25 | 6407 |
| 5/17/1990 | 1990 | 5 | 17 | 351 | 43 | 79 | 61 | 29 | 6436 |
| 5/18/1990 | 1990 | 5 | 18 | 352 | 42 | 79 | 60.5 | 28.5 | 6464.5 |
| 5/19/1990 | 1990 | 5 | 19 | 353 | 42 | 75 | 58.5 | 26.5 | 6491 |
| 5/20/1990 | 1990 | 5 | 20 | 354 | 41 | 73 | 57 | 25 | 6516 |
| 5/21/1990 | 1990 | 5 | 21 | 355 | 39 | 82 | 60.5 | 28.5 | 6544.5 |
| 5/22/1990 | 1990 | 5 | 22 | 356 | 44 | 87 | 65.5 | 33.5 | 6578 |
| 5/23/1990 | 1990 | 5 | 23 | 357 | 44 | 86 | 65 | 33 | 6611 |
| 5/24/1990 | 1990 | 5 | 24 | 358 | 49 | 85 | 67 | 35 | 6646 |
| 5/25/1990 | 1990 | 5 | 25 | 359 | 40 | 84 | 62 | 30 | 6676 |
| 5/26/1990 | 1990 | 5 | 26 | 360 | 39 | 82 | 60.5 | 28.5 | 6704.5 |
| 5/27/1990 | 1990 | 5 | 27 | 361 | 42 | 85 | 63.5 | 31.5 | 6736 |
| 5/28/1990 | 1990 | 5 | 28 | 362 | 45 | 85 | 65 | 33 | 6769 |
| 5/29/1990 | 1990 | 5 | 29 | 363 | 38 | 76 | 57 | 25 | 6794 |
| 5/30/1990 | 1990 | 5 | 30 | 364 | 38 | 78 | 58 | 26 | 6820 |
| 5/31/1990 | 1990 | 5 | 31 | 365 | 42 | 83 | 62.5 | 30.5 | 6850.5 |
| 6/1/1990 | 1990 | 6 | 1 | 1 | 40 | 82 | 61 | 29 | 29 |
| 6/2/1990 | 1990 | 6 | 2 | 2 | 42 | 85 | 63.5 | 31.5 | 60.5 |
| 6/3/1990 | 1990 | 6 | 3 | 3 | 45 | 89 | 67 | 35 | 95.5 |
| 6/4/1990 | 1990 | 6 | 4 | 4 | 48 | 96 | 72 | 40 | 135.5 |
| 6/5/1990 | 1990 | 6 | 5 | 5 | 52 | 92 | 72 | 40 | 175.5 |
| 6/6/1990 | 1990 | 6 | 6 | 6 | 52 | 92 | 72 | 40 | 215.5 |
| 6/7/1990 | 1990 | 6 | 7 | 7 | 49 | 91 | 70 | 38 | 253.5 |
| 6/8/1990 | 1990 | 6 | 8 | 8 | 50 | 92 | 71 | 39 | 292.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/9/1990 | 1990 | 6 | 9 | 9 | 50 | 87 | 68.5 | 36.5 | 329 |
| 6/10/1990 | 1990 | 6 | 10 | 10 | 42 | 74 | 58 | 26 | 355 |
| 6/11/1990 | 1990 | 6 | 11 | 11 | 50 | 87 | 68.5 | 36.5 | 391.5 |
| 6/12/1990 | 1990 | 6 | 12 | 12 | 49 | 91 | 70 | 38 | 429.5 |
| 6/13/1990 | 1990 | 6 | 13 | 13 | 52 | 91 | 71.5 | 39.5 | 469 |
| 6/14/1990 | 1990 | 6 | 14 | 14 | 48 | 92 | 70 | 38 | 507 |
| 6/15/1990 | 1990 | 6 | 15 | 15 | 50 | 89 | 69.5 | 37.5 | 544.5 |
| 6/16/1990 | 1990 | 6 | 16 | 16 | 46 | 86 | 66 | 34 | 578.5 |
| 6/17/1990 | 1990 | 6 | 17 | 17 | 40 | 95 | 67.5 | 35.5 | 614 |
| 6/18/1990 | 1990 | 6 | 18 | 18 | 46 | 97 | 71.5 | 39.5 | 653.5 |
| 6/19/1990 | 1990 | 6 | 19 | 19 | 58 | 96 | 77 | 45 | 698.5 |
| 6/20/1990 | 1990 | 6 | 20 | 20 | 50 | 92 | 71 | 39 | 737.5 |
| 6/21/1990 | 1990 | 6 | 21 | 21 | 48 | 97 | 72.5 | 40.5 | 778 |
| 6/22/1990 | 1990 | 6 | 22 | 22 | 50 | 95 | 72.5 | 40.5 | 818.5 |
| 6/23/1990 | 1990 | 6 | 23 | 23 | 52 | 97 | 74.5 | 42.5 | 861 |
| 6/24/1990 | 1990 | 6 | 24 | 24 | 54 | 99 | 76.5 | 44.5 | 905.5 |
| 6/25/1990 | 1990 | 6 | 25 | 25 | 62 | 98 | 80 | 48 | 953.5 |
| 6/26/1990 | 1990 | 6 | 26 | 26 | 58 | 98 | 78 | 46 | 999.5 |
| 6/27/1990 | 1990 | 6 | 27 | 27 | 60 | 94 | 77 | 45 | 1044.5 |
| 6/28/1990 | 1990 | 6 | 28 | 28 | 48 | 97 | 72.5 | 40.5 | 1085 |
| 6/29/1990 | 1990 | 6 | 29 | 29 | 61 | 98 | 79.5 | 47.5 | 1132.5 |
| 6/30/1990 | 1990 | 6 | 30 | 30 | 60 | 98 | 79 | 47 | 1179.5 |
| 7/1/1990 | 1990 | 7 | 1 | 31 | 58 | 96 | 77 | 45 | 1224.5 |
| 7/2/1990 | 1990 | 7 | 2 | 32 | 55 | 95 | 75 | 43 | 1267.5 |
| 7/3/1990 | 1990 | 7 | 3 | 33 | 57 | 87 | 72 | 40 | 1307.5 |
| 7/4/1990 | 1990 | 7 | 4 | 34 | 54 | 87 | 70.5 | 38.5 | 1346 |
| 7/5/1990 | 1990 | 7 | 5 | 35 | 54 | 79 | 66.5 | 34.5 | 1380.5 |
| 7/6/1990 | 1990 | 7 | 6 | 36 | 55 | 77 | 66 | 34 | 1414.5 |
| 7/7/1990 | 1990 | 7 | 7 | 37 | 55 | 83 | 69 | 37 | 1451.5 |
| 7/8/1990 | 1990 | 7 | 8 | 38 | 54 | 82 | 68 | 36 | 1487.5 |
| 7/9/1990 | 1990 | 7 | 9 | 39 | 59 | 80 | 69.5 | 37.5 | 1525 |
| 7/10/1990 | 1990 | 7 | 10 | 40 | 60 | 85 | 72.5 | 40.5 | 1565.5 |
| 7/11/1990 | 1990 | 7 | 11 | 41 | 60 | 85 | 72.5 | 40.5 | 1606 |
| 7/12/1990 | 1990 | 7 | 12 | 42 | 55 | 85 | 70 | 38 | 1644 |
| 7/13/1990 | 1990 | 7 | 13 | 43 | 55 | 86 | 70.5 | 38.5 | 1682.5 |
| 7/14/1990 | 1990 | 7 | 14 | 44 | 55 | 77 | 66 | 34 | 1716.5 |
| 7/15/1990 | 1990 | 7 | 15 | 45 | 49 | 84 | 66.5 | 34.5 | 1751 |
| 7/16/1990 | 1990 | 7 | 16 | 46 | 61 | 84 | 72.5 | 40.5 | 1791.5 |
| 7/17/1990 | 1990 | 7 | 17 | 47 | 56 | 86 | 71 | 39 | 1830.5 |
| 7/18/1990 | 1990 | 7 | 18 | 48 | 55 | 90 | 72.5 | 40.5 | 1871 |
| 7/19/1990 | 1990 | 7 | 19 | 49 | 61 | 91 | 76 | 44 | 1915 |
| 7/20/1990 | 1990 | 7 | 20 | 50 | 58 | 86 | 72 | 40 | 1955 |
| 7/21/1990 | 1990 | 7 | 21 | 51 | 55 | 89 | 72 | 40 | 1995 |
| 7/22/1990 | 1990 | 7 | 22 | 52 | 57 | 89 | 73 | 41 | 2036 |
| 7/23/1990 | 1990 | 7 | 23 | 53 | 58 | 87 | 72.5 | 40.5 | 2076.5 |
| 7/24/1990 | 1990 | 7 | 24 | 54 | 58 | 85 | 71.5 | 39.5 | 2116 |
| 7/25/1990 | 1990 | 7 | 25 | 55 | 55 | 89 | 72 | 40 | 2156 |
| 7/26/1990 | 1990 | 7 | 26 | 56 | 57 | 91 | 74 | 42 | 2198 |
| 7/27/1990 | 1990 | 7 | 27 | 57 | 53 | 89 | 71 | 39 | 2237 |
| 7/28/1990 | 1990 | 7 | 28 | 58 | 53 | 89 | 71 | 39 | 2276 |
| 7/29/1990 | 1990 | 7 | 29 | 59 | 57 | 84 | 70.5 | 38.5 | 2314.5 |
| 7/30/1990 | 1990 | 7 | 30 | 60 | 59 | 86 | 72.5 | 40.5 | 2355 |
| 7/31/1990 | 1990 | 7 | 31 | 61 | 57 | 89 | 73 | 41 | 2396 |
| 8/1/1990 | 1990 | 8 | 1 | 62 | 52 | 80 | 66 | 34 | 2430 |
| 8/2/1990 | 1990 | 8 | 2 | 63 | 54 | 83 | 68.5 | 36.5 | 2466.5 |
| 8/3/1990 | 1990 | 8 | 3 | 64 | 50 | 89 | 69.5 | 37.5 | 2504 |
| 8/4/1990 | 1990 | 8 | 4 | 65 | 52 | 87 | 69.5 | 37.5 | 2541.5 |
| 8/5/1990 | 1990 | 8 | 5 | 66 | 55 | 84 | 69.5 | 37.5 | 2579 |
| 8/6/1990 | 1990 | 8 | 6 | 67 | 53 | 80 | 66.5 | 34.5 | 2613.5 |
| 8/7/1990 | 1990 | 8 | 7 | 68 | 54 | 86 | 70 | 38 | 2651.5 |
| 8/8/1990 | 1990 | 8 | 8 | 69 | 50 | 92 | 71 | 39 | 2690.5 |
| 8/9/1990 | 1990 | 8 | 9 | 70 | 55 | 93 | 74 | 42 | 2732.5 |
| 8/10/1990 | 1990 | 8 | 10 | 71 | 50 | 93 | 71.5 | 39.5 | 2772 |
| 8/11/1990 | 1990 | 8 | 11 | 72 | 52 | 89 | 70.5 | 38.5 | 2810.5 |
| 8/12/1990 | 1990 | 8 | 12 | 73 | 55 | 89 | 72 | 40 | 2850.5 |
| 8/13/1990 | 1990 | 8 | 13 | 74 | 52 | 72 | 62 | 30 | 2880.5 |
| 8/14/1990 | 1990 | 8 | 14 | 75 | 50 | 74 | 62 | 30 | 2910.5 |
| 8/15/1990 | 1990 | 8 | 15 | 76 | 52 | 72 | 62 | 30 | 2940.5 |
| 8/16/1990 | 1990 | 8 | 16 | 77 | 51 | 74 | 62.5 | 30.5 | 2971 |
| 8/17/1990 | 1990 | 8 | 17 | 78 | 49 | 75 | 62 | 30 | 3001 |
| 8/18/1990 | 1990 | 8 | 18 | 79 | 48 | 82 | 65 | 33 | 3034 |
| 8/19/1990 | 1990 | 8 | 19 | 80 | 49 | 86 | 67.5 | 35.5 | 3069.5 |
| 8/20/1990 | 1990 | 8 | 20 | 81 | 52 | 79 | 65.5 | 33.5 | 3103 |
| 8/21/1990 | 1990 | 8 | 21 | 82 | 51 | 81 | 66 | 34 | 3137 |
| 8/22/1990 | 1990 | 8 | 22 | 83 | 46 | 78 | 62 | 30 | 3167 |
| 8/23/1990 | 1990 | 8 | 23 | 84 | 48 | 85 | 66.5 | 34.5 | 3201.5 |
| 8/24/1990 | 1990 | 8 | 24 | 85 | 50 | 85 | 67.5 | 35.5 | 3237 |
| 8/25/1990 | 1990 | 8 | 25 | 86 | 41 | 83 | 62 | 30 | 3267 |
| 8/26/1990 | 1990 | 8 | 26 | 87 | 48 | 84 | 66 | 34 | 3301 |
| 8/27/1990 | 1990 | 8 | 27 | 88 | 48 | 89 | 68.5 | 36.5 | 3337.5 |
| 8/28/1990 | 1990 | 8 | 28 | 89 | 53 | 95 | 74 | 42 | 3379.5 |
| 8/29/1990 | 1990 | 8 | 29 | 90 | 54 | 92 | 73 | 41 | 3420.5 |
| 8/30/1990 | 1990 | 8 | 30 | 91 | 54 | 92 | 73 | 41 | 3461.5 |
| 8/31/1990 | 1990 | 8 | 31 | 92 | 53 | 92 | 72.5 | 40.5 | 3502 |
| 9/1/1990 | 1990 | 9 | 1 | 93 | 51 | 91 | 71 | 39 | 3541 |
| 9/2/1990 | 1990 | 9 | 2 | 94 | 52 | 89 | 70.5 | 38.5 | 3579.5 |
| 9/3/1990 | 1990 | 9 | 3 | 95 | 52 | 85 | 68.5 | 36.5 | 3616 |
| 9/4/1990 | 1990 | 9 | 4 | 96 | 54 | 78 | 66 | 34 | 3650 |
| 9/5/1990 | 1990 | 9 | 5 | 97 | 55 | 82 | 68.5 | 36.5 | 3686.5 |
| 9/6/1990 | 1990 | 9 | 6 | 98 | 55 | 84 | 69.5 | 37.5 | 3724 |
| 9/7/1990 | 1990 | 9 | 7 | 99 | 52 | 84 | 68 | 36 | 3760 |
| 9/8/1990 | 1990 | 9 | 8 | 100 | 52 | 85 | 68.5 | 36.5 | 3796.5 |
| 9/9/1990 | 1990 | 9 | 9 | 101 | 49 | 90 | 69.5 | 37.5 | 3834 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/10/1990 | 1990 | 9 | 10 | 102 | 49 | 89 | 69 | 37 | 3871 |
| 9/11/1990 | 1990 | 9 | 11 | 103 | 48 | 91 | 69.5 | 37.5 | 3908.5 |
| 9/12/1990 | 1990 | 9 | 12 | 104 | 48 | 90 | 69 | 37 | 3945.5 |
| 9/13/1990 | 1990 | 9 | 13 | 105 | 48 | 92 | 70 | 38 | 3983.5 |
| 9/14/1990 | 1990 | 9 | 14 | 106 | 48 | 85 | 66.5 | 34.5 | 4018 |
| 9/15/1990 | 1990 | 9 | 15 | 107 | 47 | 82 | 64.5 | 32.5 | 4050.5 |
| 9/16/1990 | 1990 | 9 | 16 | 108 | 56 | 72 | 64 | 32 | 4082.5 |
| 9/17/1990 | 1990 | 9 | 17 | 109 | 47 | 82 | 64.5 | 32.5 | 4115 |
| 9/18/1990 | 1990 | 9 | 18 | 110 | 48 | 74 | 61 | 29 | 4144 |
| 9/19/1990 | 1990 | 9 | 19 | 111 | 46 | 78 | 62 | 30 | 4174 |
| 9/20/1990 | 1990 | 9 | 20 | 112 | 47 | 69 | 58 | 26 | 4200 |
| 9/21/1990 | 1990 | 9 | 21 | 113 | 48 | 80 | 64 | 32 | 4232 |
| 9/22/1990 | 1990 | 9 | 22 | 114 | 52 | 69 | 60.5 | 28.5 | 4260.5 |
| 9/23/1990 | 1990 | 9 | 23 | 115 | 51 | 60 | 55.5 | 23.5 | 4284 |
| 9/24/1990 | 1990 | 9 | 24 | 116 | 50 | 75 | 62.5 | 30.5 | 4314.5 |
| 9/25/1990 | 1990 | 9 | 25 | 117 | 45 | 80 | 62.5 | 30.5 | 4345 |
| 9/26/1990 | 1990 | 9 | 26 | 118 | 45 | 85 | 65 | 33 | 4378 |
| 9/27/1990 | 1990 | 9 | 27 | 119 | 44 | 82 | 63 | 31 | 4409 |
| 9/28/1990 | 1990 | 9 | 28 | 120 | 49 | 70 | 59.5 | 27.5 | 4436.5 |
| 9/29/1990 | 1990 | 9 | 29 | 121 | 49 | 73 | 61 | 29 | 4465.5 |
| 9/30/1990 | 1990 | 9 | 30 | 122 | 48 | 68 | 58 | 26 | 4491.5 |
| 10/1/1990 | 1990 | 10 | 1 | 123 | 47 | 66 | 56.5 | 24.5 | 4516 |
| 10/2/1990 | 1990 | 10 | 2 | 124 | 44 | 68 | 56 | 24 | 4540 |
| 10/3/1990 | 1990 | 10 | 3 | 125 | 39 | 75 | 57 | 25 | 4565 |
| 10/4/1990 | 1990 | 10 | 4 | 126 | 40 | 79 | 59.5 | 27.5 | 4592.5 |
| 10/5/1990 | 1990 | 10 | 5 | 127 | 37 | 80 | 58.5 | 26.5 | 4619 |
| 10/6/1990 | 1990 | 10 | 6 | 128 | 41 | 78 | 59.5 | 27.5 | 4646.5 |
| 10/7/1990 | 1990 | 10 | 7 | 129 | 41 | 78 | 59.5 | 27.5 | 4674 |
| 10/8/1990 | 1990 | 10 | 8 | 130 | 45 | 72 | 58.5 | 26.5 | 4700.5 |
| 10/9/1990 | 1990 | 10 | 9 | 131 | 29 | 60 | 44.5 | 12.5 | 4713 |
| 10/10/1990 | 1990 | 10 | 10 | 132 | 29 | 72 | 50.5 | 18.5 | 4731.5 |
| 10/11/1990 | 1990 | 10 | 11 | 133 | 27 | 76 | 51.5 | 19.5 | 4751 |
| 10/12/1990 | 1990 | 10 | 12 | 134 | 27 | 72 | 49.5 | 17.5 | 4768.5 |
| 10/13/1990 | 1990 | 10 | 13 | 135 | 27 | 78 | 52.5 | 20.5 | 4789 |
| 10/14/1990 | 1990 | 10 | 14 | 136 | 35 | 79 | 57 | 25 | 4814 |
| 10/15/1990 | 1990 | 10 | 15 | 137 | 33 | 79 | 56 | 24 | 4838 |
| 10/16/1990 | 1990 | 10 | 16 | 138 | 31 | 76 | 53.5 | 21.5 | 4859.5 |
| 10/17/1990 | 1990 | 10 | 17 | 139 | 42 | 69 | 55.5 | 23.5 | 4883 |
| 10/18/1990 | 1990 | 10 | 18 | 140 | 28 | 73 | 50.5 | 18.5 | 4901.5 |
| 10/19/1990 | 1990 | 10 | 19 | 141 | 38 | 75 | 56.5 | 24.5 | 4926 |
| 10/20/1990 | 1990 | 10 | 20 | 142 | 35 | 58 | 46.5 | 14.5 | 4940.5 |
| 10/21/1990 | 1990 | 10 | 21 | 143 | 26 | 53 | 39.5 | 7.5 | 4948 |
| 10/22/1990 | 1990 | 10 | 22 | 144 | 25 | 68 | 46.5 | 14.5 | 4962.5 |
| 10/23/1990 | 1990 | 10 | 23 | 145 | 18 | 67 | 42.5 | 10.5 | 4973 |
| 10/24/1990 | 1990 | 10 | 24 | 146 | 28 | 73 | 50.5 | 18.5 | 4991.5 |
| 10/25/1990 | 1990 | 10 | 25 | 147 | 28 | 75 | 51.5 | 19.5 | 5011 |
| 10/26/1990 | 1990 | 10 | 26 | 148 | 30 | 73 | 51.5 | 19.5 | 5030.5 |
| 10/27/1990 | 1990 | 10 | 27 | 149 | 30 | 74 | 52 | 20 | 5050.5 |
| 10/28/1990 | 1990 | 10 | 28 | 150 | 37 | 74 | 55.5 | 23.5 | 5074 |
| 10/29/1990 | 1990 | 10 | 29 | 151 | 31 | 75 | 53 | 21 | 5095 |
| 10/30/1990 | 1990 | 10 | 30 | 152 | 33 | 75 | 54 | 22 | 5117 |
| 10/31/1990 | 1990 | 10 | 31 | 153 | 30 | 73 | 51.5 | 19.5 | 5136.5 |
| 11/1/1990 | 1990 | 11 | 1 | 154 | 33 | 68 | 50.5 | 18.5 | 5155 |
| 11/2/1990 | 1990 | 11 | 2 | 155 | 33 | 50 | 41.5 | 9.5 | 5164.5 |
| 11/3/1990 | 1990 | 11 | 3 | 156 | 28 | 48 | 38 | 6 | 5170.5 |
| 11/4/1990 | 1990 | 11 | 4 | 157 | 27 | 50 | 38.5 | 6.5 | 5177 |
| 11/5/1990 | 1990 | 11 | 5 | 158 | 24 | 64 | 44 | 12 | 5189 |
| 11/6/1990 | 1990 | 11 | 6 | 159 | 26 | 61 | 43.5 | 11.5 | 5200.5 |
| 11/7/1990 | 1990 | 11 | 7 | 160 | 25 | 46 | 35.5 | 3.5 | 5204 |
| 11/8/1990 | 1990 | 11 | 8 | 161 | 22 | 46 | 34 | 2 | 5206 |
| 11/9/1990 | 1990 | 11 | 9 | 162 | 24 | 55 | 39.5 | 7.5 | 5213.5 |
| 11/10/1990 | 1990 | 11 | 10 | 163 | 24 | 56 | 40 | 8 | 5221.5 |
| 11/11/1990 | 1990 | 11 | 11 | 164 | 26 | 60 | 43 | 11 | 5232.5 |
| 11/12/1990 | 1990 | 11 | 12 | 165 | 22 | 68 | 45 | 13 | 5245.5 |
| 11/13/1990 | 1990 | 11 | 13 | 166 | 22 | 68 | 45 | 13 | 5258.5 |
| 11/14/1990 | 1990 | 11 | 14 | 167 | 23 | 71 | 47 | 15 | 5273.5 |
| 11/15/1990 | 1990 | 11 | 15 | 168 | 25 | 72 | 48.5 | 16.5 | 5290 |
| 11/16/1990 | 1990 | 11 | 16 | 169 | 25 | 61 | 43 | 11 | 5301 |
| 11/17/1990 | 1990 | 11 | 17 | 170 | 26 | 66 | 46 | 14 | 5315 |
| 11/18/1990 | 1990 | 11 | 18 | 171 | 26 | 68 | 47 | 15 | 5330 |
| 11/19/1990 | 1990 | 11 | 19 | 172 | 27 | 65 | 46 | 14 | 5344 |
| 11/20/1990 | 1990 | 11 | 20 | 173 | 36 | 61 | 48.5 | 16.5 | 5360.5 |
| 11/21/1990 | 1990 | 11 | 21 | 174 | 31 | 52 | 41.5 | 9.5 | 5370 |
| 11/22/1990 | 1990 | 11 | 22 | 175 | 18 | 52 | 35 | 3 | 5373 |
| 11/23/1990 | 1990 | 11 | 23 | 176 | 18 | 58 | 38 | 6 | 5379 |
| 11/24/1990 | 1990 | 11 | 24 | 177 | 18 | 65 | 41.5 | 9.5 | 5388.5 |
| 11/25/1990 | 1990 | 11 | 25 | 178 | 18 | 68 | 43 | 11 | 5399.5 |
| 11/26/1990 | 1990 | 11 | 26 | 179 | 27 | 55 | 41 | 9 | 5408.5 |
| 11/27/1990 | 1990 | 11 | 27 | 180 | 22 | 43 | 32.5 | 0.5 | 5409 |
| 11/28/1990 | 1990 | 11 | 28 | 181 | 10 | 38 | 24 | -8 | 5401 |
| 11/29/1990 | 1990 | 11 | 29 | 182 | 8 | 48 | 28 | -4 | 5397 |
| 11/30/1990 | 1990 | 11 | 30 | 183 | 9 | 57 | 33 | 1 | 5398 |
| 12/1/1990 | 1990 | 12 | 1 | 184 | 12 | 58 | 35 | 3 | 5401 |
| 12/2/1990 | 1990 | 12 | 2 | 185 | 15 | 42 | 28.5 | -3.5 | 5397.5 |
| 12/3/1990 | 1990 | 12 | 3 | 186 | 12 | 41 | 26.5 | -5.5 | 5392 |
| 12/4/1990 | 1990 | 12 | 4 | 187 | 7 | 53 | 30 | -2 | 5390 |
| 12/5/1990 | 1990 | 12 | 5 | 188 | 5 | 56 | 30.5 | -1.5 | 5388.5 |
| 12/6/1990 | 1990 | 12 | 6 | 189 | 10 | 42 | 26 | -6 | 5382.5 |
| 12/7/1990 | 1990 | 12 | 7 | 190 | 8 | 53 | 30.5 | -1.5 | 5381 |
| 12/8/1990 | 1990 | 12 | 8 | 191 | 8 | 58 | 33 | 1 | 5382 |
| 12/9/1990 | 1990 | 12 | 9 | 192 | 9 | 58 | 33.5 | 1.5 | 5383.5 |
| 12/10/1990 | 1990 | 12 | 10 | 193 | 11 | 60 | 35.5 | 3.5 | 5387 |
| 12/11/1990 | 1990 | 12 | 11 | 194 | 13 | 63 | 38 | 6 | 5393 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/12/1990 | 1990 | 12 | 12 | 195 | 22 | 55 | 38.5 | 6.5 | 5399.5 |
| 12/13/1990 | 1990 | 12 | 13 | 196 | 33 | 47 | 40 | 8 | 5407.5 |
| 12/14/1990 | 1990 | 12 | 14 | 197 | 35 | 50 | 42.5 | 10.5 | 5418 |
| 12/15/1990 | 1990 | 12 | 15 | 198 | 20 | 47 | 33.5 | 1.5 | 5419.5 |
| 12/16/1990 | 1990 | 12 | 16 | 199 | 28 | 38 | 33 | 1 | 5420.5 |
| 12/17/1990 | 1990 | 12 | 17 | 200 | 19 | 37 | 28 | -4 | 5416.5 |
| 12/18/1990 | 1990 | 12 | 18 | 201 | 11 | 41 | 26 | -6 | 5410.5 |
| 12/19/1990 | 1990 | 12 | 19 | 202 | 9 | 49 | 29 | -3 | 5407.5 |
| 12/20/1990 | 1990 | 12 | 20 | 203 | 26 | 40 | 33 | 1 | 5408.5 |
| 12/21/1990 | 1990 | 12 | 21 | 204 | 15 | 26 | 20.5 | -11.5 | 5397 |
| 12/22/1990 | 1990 | 12 | 22 | 205 | -2 | 25 | 11.5 | -20.5 | 5376.5 |
| 12/23/1990 | 1990 | 12 | 23 | 206 | -7 | 24 | 8.5 | -23.5 | 5353 |
| 12/24/1990 | 1990 | 12 | 24 | 207 | -21 | 21 | 0 | -32 | 5321 |
| 12/25/1990 | 1990 | 12 | 25 | 208 | -33 | 21 | -6 | -38 | 5283 |
| 12/26/1990 | 1990 | 12 | 26 | 209 | -28 | 28 | 0 | -32 | 5251 |
| 12/27/1990 | 1990 | 12 | 27 | 210 | -19 | 33 | 7 | -25 | 5226 |
| 12/28/1990 | 1990 | 12 | 28 | 211 | -10 | 47 | 18.5 | -13.5 | 5212.5 |
| 12/29/1990 | 1990 | 12 | 29 | 212 | 5 | 48 | 26.5 | -5.5 | 5207 |
| 12/30/1990 | 1990 | 12 | 30 | 213 | -9 | 34 | 12.5 | -19.5 | 5187.5 |
| 12/31/1990 | 1990 | 12 | 31 | 214 | -12 | 37 | 12.5 | -19.5 | 5168 |
| 1/1/1991 | 1991 | 1 | 1 | 215 | -6 | 41 | 17.5 | -14.5 | 5153.5 |
| 1/2/1991 | 1991 | 1 | 2 | 216 | -7 | 45 | 19 | -13 | 5140.5 |
| 1/3/1991 | 1991 | 1 | 3 | 217 | -3 | 39 | 18 | -14 | 5126.5 |
| 1/4/1991 | 1991 | 1 | 4 | 218 | 15 | 46 | 30.5 | -1.5 | 5125 |
| 1/5/1991 | 1991 | 1 | 5 | 219 | 17 | 47 | 32 | 0 | 5125 |
| 1/6/1991 | 1991 | 1 | 6 | 220 | 15 | 39 | 27 | -5 | 5120 |
| 1/7/1991 | 1991 | 1 | 7 | 221 | 15 | 39 | 27 | -5 | 5115 |
| 1/8/1991 | 1991 | 1 | 8 | 222 | 5 | 44 | 24.5 | -7.5 | 5107.5 |
| 1/9/1991 | 1991 | 1 | 9 | 223 | 8 | 44 | 26 | -6 | 5101.5 |
| 1/10/1991 | 1991 | 1 | 10 | 224 | 10 | 40 | 25 | -7 | 5094.5 |
| 1/11/1991 | 1991 | 1 | 11 | 225 | 18 | 47 | 32.5 | 0.5 | 5095 |
| 1/12/1991 | 1991 | 1 | 12 | 226 | 16 | 45 | 30.5 | -1.5 | 5093.5 |
| 1/13/1991 | 1991 | 1 | 13 | 227 | 21 | 49 | 35 | 3 | 5096.5 |
| 1/14/1991 | 1991 | 1 | 14 | 228 | 23 | 41 | 32 | 0 | 5096.5 |
| 1/15/1991 | 1991 | 1 | 15 | 229 | 19 | 50 | 34.5 | 2.5 | 5099 |
| 1/16/1991 | 1991 | 1 | 16 | 230 | 24 | 39 | 31.5 | -0.5 | 5098.5 |
| 1/17/1991 | 1991 | 1 | 17 | 231 | 16 | 39 | 27.5 | -4.5 | 5094 |
| 1/18/1991 | 1991 | 1 | 18 | 232 | 15 | 49 | 32 | 0 | 5094 |
| 1/19/1991 | 1991 | 1 | 19 | 233 | 15 | 51 | 33 | 1 | 5095 |
| 1/20/1991 | 1991 | 1 | 20 | 234 | 20 | 40 | 30 | -2 | 5093 |
| 1/21/1991 | 1991 | 1 | 21 | 235 | -2 | 34 | 16 | -16 | 5077 |
| 1/22/1991 | 1991 | 1 | 22 | 236 | 16 | 35 | 25.5 | -6.5 | 5070.5 |
| 1/23/1991 | 1991 | 1 | 23 | 237 | 11 | 39 | 25 | -7 | 5063.5 |
| 1/24/1991 | 1991 | 1 | 24 | 238 | 11 | 48 | 29.5 | -2.5 | 5061 |
| 1/25/1991 | 1991 | 1 | 25 | 239 | 15 | 48 | 31.5 | -0.5 | 5060.5 |
| 1/26/1991 | 1991 | 1 | 26 | 240 | -5 | 52 | 23.5 | -8.5 | 5052 |
| 1/27/1991 | 1991 | 1 | 27 | 241 | 2 | 46 | 24 | -8 | 5044 |
| 1/28/1991 | 1991 | 1 | 28 | 242 | 10 | 46 | 28 | -4 | 5040 |
| 1/29/1991 | 1991 | 1 | 29 | 243 | 25 | 37 | 31 | -1 | 5039 |
| 1/30/1991 | 1991 | 1 | 30 | 244 | 1 | 40 | 20.5 | -11.5 | 5027.5 |
| 1/31/1991 | 1991 | 1 | 31 | 245 | 8 | 54 | 31 | -1 | 5026.5 |
| 2/1/1991 | 1991 | 2 | 1 | 246 | 6 | 54 | 30 | -2 | 5024.5 |
| 2/2/1991 | 1991 | 2 | 2 | 247 | 3 | 58 | 30.5 | -1.5 | 5023 |
| 2/3/1991 | 1991 | 2 | 3 | 248 | 12 | 53 | 32.5 | 0.5 | 5023.5 |
| 2/4/1991 | 1991 | 2 | 4 | 249 | 2 | 55 | 28.5 | -3.5 | 5020 |
| 2/5/1991 | 1991 | 2 | 5 | 250 | 12 | 57 | 34.5 | 2.5 | 5022.5 |
| 2/6/1991 | 1991 | 2 | 6 | 251 | 16 | 57 | 36.5 | 4.5 | 5027 |
| 2/7/1991 | 1991 | 2 | 7 | 252 | 20 | 59 | 39.5 | 7.5 | 5034.5 |
| 2/8/1991 | 1991 | 2 | 8 | 253 | 24 | 56 | 40 | 8 | 5042.5 |
| 2/9/1991 | 1991 | 2 | 9 | 254 | 10 | 56 | 33 | 1 | 5043.5 |
| 2/10/1991 | 1991 | 2 | 10 | 255 | 15 | 59 | 37 | 5 | 5048.5 |
| 2/11/1991 | 1991 | 2 | 11 | 256 | 19 | 59 | 39 | 7 | 5055.5 |
| 2/12/1991 | 1991 | 2 | 12 | 257 | 24 | 55 | 39.5 | 7.5 | 5063 |
| 2/13/1991 | 1991 | 2 | 13 | 258 | 25 | 61 | 43 | 11 | 5074 |
| 2/14/1991 | 1991 | 2 | 14 | 259 | 26 | 56 | 41 | 9 | 5083 |
| 2/15/1991 | 1991 | 2 | 15 | 260 | 24 | 65 | 44.5 | 12.5 | 5095.5 |
| 2/16/1991 | 1991 | 2 | 16 | 261 | 15 | 58 | 36.5 | 4.5 | 5100 |
| 2/17/1991 | 1991 | 2 | 17 | 262 | 30 | 56 | 43 | 11 | 5111 |
| 2/18/1991 | 1991 | 2 | 18 | 263 | 8 | 42 | 25 | -7 | 5104 |
| 2/19/1991 | 1991 | 2 | 19 | 264 | 2 | 45 | 23.5 | -8.5 | 5095.5 |
| 2/20/1991 | 1991 | 2 | 20 | 265 | 8 | 55 | 31.5 | -0.5 | 5095 |
| 2/21/1991 | 1991 | 2 | 21 | 266 | 8 | 59 | 33.5 | 1.5 | 5096.5 |
| 2/22/1991 | 1991 | 2 | 22 | 267 | 6 | 64 | 35 | 3 | 5099.5 |
| 2/23/1991 | 1991 | 2 | 23 | 268 | 18 | 63 | 40.5 | 8.5 | 5108 |
| 2/24/1991 | 1991 | 2 | 24 | 269 | 20 | 60 | 40 | 8 | 5116 |
| 2/25/1991 | 1991 | 2 | 25 | 270 | 15 | 55 | 35 | 3 | 5119 |
| 2/26/1991 | 1991 | 2 | 26 | 271 | 17 | 55 | 36 | 4 | 5123 |
| 2/27/1991 | 1991 | 2 | 27 | 272 | 17 | 61 | 39 | 7 | 5130 |
| 2/28/1991 | 1991 | 2 | 28 | 273 | 28 | 54 | 41 | 9 | 5139 |
| 3/1/1991 | 1991 | 3 | 1 | 274 | 23 | 49 | 36 | 4 | 5143 |
| 3/2/1991 | 1991 | 3 | 2 | 275 | 23 | 51 | 37 | 5 | 5148 |
| 3/3/1991 | 1991 | 3 | 3 | 276 | 23 | 59 | 41 | 9 | 5157 |
| 3/4/1991 | 1991 | 3 | 4 | 277 | 23 | 67 | 45 | 13 | 5170 |
| 3/5/1991 | 1991 | 3 | 5 | 278 | 30 | 52 | 41 | 9 | 5179 |
| 3/6/1991 | 1991 | 3 | 6 | 279 | 29 | 50 | 39.5 | 7.5 | 5186.5 |
| 3/7/1991 | 1991 | 3 | 7 | 280 | 25 | 46 | 35.5 | 3.5 | 5190 |
| 3/8/1991 | 1991 | 3 | 8 | 281 | 14 | 53 | 33.5 | 1.5 | 5191.5 |
| 3/9/1991 | 1991 | 3 | 9 | 282 | 16 | 54 | 35 | 3 | 5194.5 |
| 3/10/1991 | 1991 | 3 | 10 | 283 | 26 | 68 | 47 | 15 | 5209.5 |
| 3/11/1991 | 1991 | 3 | 11 | 284 | 32 | 61 | 46.5 | 14.5 | 5224 |
| 3/12/1991 | 1991 | 3 | 12 | 285 | 20 | 56 | 38 | 6 | 5230 |
| 3/13/1991 | 1991 | 3 | 13 | 286 | 20 | 58 | 39 | 7 | 5237 |
| 3/14/1991 | 1991 | 3 | 14 | 287 | 22 | 58 | 40 | 8 | 5245 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/15/1991 | 1991 | 3 | 15 | 288 | 23 | 50 | 36.5 | 4.5 | 5249.5 |
| 3/16/1991 | 1991 | 3 | 16 | 289 | 20 | 43 | 31.5 | -0.5 | 5249 |
| 3/17/1991 | 1991 | 3 | 17 | 290 | 19 | 61 | 40 | 8 | 5257 |
| 3/18/1991 | 1991 | 3 | 18 | 291 | 22 | 68 | 45 | 13 | 5270 |
| 3/19/1991 | 1991 | 3 | 19 | 292 | 31 | 64 | 47.5 | 15.5 | 5285.5 |
| 3/20/1991 | 1991 | 3 | 20 | 293 | 28 | 54 | 41 | 9 | 5294.5 |
| 3/21/1991 | 1991 | 3 | 21 | 294 | 25 | 40 | 32.5 | 0.5 | 5295 |
| 3/22/1991 | 1991 | 3 | 22 | 295 | 23 | 46 | 34.5 | 2.5 | 5297.5 |
| 3/23/1991 | 1991 | 3 | 23 | 296 | 17 | 58 | 37.5 | 5.5 | 5303 |
| 3/24/1991 | 1991 | 3 | 24 | 297 | 28 | 66 | 47 | 15 | 5318 |
| 3/25/1991 | 1991 | 3 | 25 | 298 | 28 | 64 | 46 | 14 | 5332 |
| 3/26/1991 | 1991 | 3 | 26 | 299 | 30 | 54 | 42 | 10 | 5342 |
| 3/27/1991 | 1991 | 3 | 27 | 300 | 29 | 54 | 41.5 | 9.5 | 5351.5 |
| 3/28/1991 | 1991 | 3 | 28 | 301 | 24 | 49 | 36.5 | 4.5 | 5356 |
| 3/29/1991 | 1991 | 3 | 29 | 302 | 29 | 52 | 40.5 | 8.5 | 5364.5 |
| 3/30/1991 | 1991 | 3 | 30 | 303 | 24 | 55 | 39.5 | 7.5 | 5372 |
| 3/31/1991 | 1991 | 3 | 31 | 304 | 25 | 63 | 44 | 12 | 5384 |
| 4/1/1991 | 1991 | 4 | 1 | 305 | 33 | 73 | 53 | 21 | 5405 |
| 4/2/1991 | 1991 | 4 | 2 | 306 | 33 | 67 | 50 | 18 | 5423 |
| 4/3/1991 | 1991 | 4 | 3 | 307 | 32 | 69 | 50.5 | 18.5 | 5441.5 |
| 4/4/1991 | 1991 | 4 | 4 | 308 | 29 | 73 | 51 | 19 | 5460.5 |
| 4/5/1991 | 1991 | 4 | 5 | 309 | 27 | 79 | 53 | 21 | 5481.5 |
| 4/6/1991 | 1991 | 4 | 6 | 310 | 31 | 82 | 56.5 | 24.5 | 5506 |
| 4/7/1991 | 1991 | 4 | 7 | 311 | 37 | 74 | 55.5 | 23.5 | 5529.5 |
| 4/8/1991 | 1991 | 4 | 8 | 312 | 35 | 68 | 51.5 | 19.5 | 5549 |
| 4/9/1991 | 1991 | 4 | 9 | 313 | 27 | 70 | 48.5 | 16.5 | 5565.5 |
| 4/10/1991 | 1991 | 4 | 10 | 314 | 30 | 71 | 50.5 | 18.5 | 5584 |
| 4/11/1991 | 1991 | 4 | 11 | 315 | 28 | 67 | 47.5 | 15.5 | 5599.5 |
| 4/12/1991 | 1991 | 4 | 12 | 316 | 30 | 57 | 43.5 | 11.5 | 5611 |
| 4/13/1991 | 1991 | 4 | 13 | 317 | 20 | 52 | 36 | 4 | 5615 |
| 4/14/1991 | 1991 | 4 | 14 | 318 | 13 | 65 | 39 | 7 | 5622 |
| 4/15/1991 | 1991 | 4 | 15 | 319 | 18 | 75 | 46.5 | 14.5 | 5636.5 |
| 4/16/1991 | 1991 | 4 | 16 | 320 | 37 | 74 | 55.5 | 23.5 | 5660 |
| 4/17/1991 | 1991 | 4 | 17 | 321 | 39 | 72 | 55.5 | 23.5 | 5683.5 |
| 4/18/1991 | 1991 | 4 | 18 | 322 | 34 | 74 | 54 | 22 | 5705.5 |
| 4/19/1991 | 1991 | 4 | 19 | 323 | 27 | 74 | 50.5 | 18.5 | 5724 |
| 4/20/1991 | 1991 | 4 | 20 | 324 | 33 | 80 | 56.5 | 24.5 | 5748.5 |
| 4/21/1991 | 1991 | 4 | 21 | 325 | 32 | 70 | 51 | 19 | 5767.5 |
| 4/22/1991 | 1991 | 4 | 22 | 326 | 37 | 72 | 54.5 | 22.5 | 5790 |
| 4/23/1991 | 1991 | 4 | 23 | 327 | 35 | 70 | 52.5 | 20.5 | 5810.5 |
| 4/24/1991 | 1991 | 4 | 24 | 328 | 35 | 72 | 53.5 | 21.5 | 5832 |
| 4/25/1991 | 1991 | 4 | 25 | 329 | 37 | 73 | 55 | 23 | 5855 |
| 4/26/1991 | 1991 | 4 | 26 | 330 | 30 | 57 | 43.5 | 11.5 | 5866.5 |
| 4/27/1991 | 1991 | 4 | 27 | 331 | 25 | 63 | 44 | 12 | 5878.5 |
| 4/28/1991 | 1991 | 4 | 28 | 332 | 20 | 51 | 35.5 | 3.5 | 5882 |
| 4/29/1991 | 1991 | 4 | 29 | 333 | 22 | 64 | 43 | 11 | 5893 |
| 4/30/1991 | 1991 | 4 | 30 | 334 | 31 | 65 | 48 | 16 | 5909 |
| 5/1/1991 | 1991 | 5 | 1 | 335 | 29 | 79 | 54 | 22 | 5931 |
| 5/2/1991 | 1991 | 5 | 2 | 336 | 22 | 73 | 47.5 | 15.5 | 5946.5 |
| 5/3/1991 | 1991 | 5 | 3 | 337 | 27 | 68 | 47.5 | 15.5 | 5962 |
| 5/4/1991 | 1991 | 5 | 4 | 338 | 29 | 66 | 47.5 | 15.5 | 5977.5 |
| 5/5/1991 | 1991 | 5 | 5 | 339 | 29 | 70 | 49.5 | 17.5 | 5995 |
| 5/6/1991 | 1991 | 5 | 6 | 340 | 30 | 76 | 53 | 21 | 6016 |
| 5/7/1991 | 1991 | 5 | 7 | 341 | 36 | 79 | 57.5 | 25.5 | 6041.5 |
| 5/8/1991 | 1991 | 5 | 8 | 342 | 36 | 86 | 61 | 29 | 6070.5 |
| 5/9/1991 | 1991 | 5 | 9 | 343 | 49 | 83 | 66 | 34 | 6104.5 |
| 5/10/1991 | 1991 | 5 | 10 | 344 | 43 | 80 | 61.5 | 29.5 | 6134 |
| 5/11/1991 | 1991 | 5 | 11 | 345 | 38 | 78 | 58 | 26 | 6160 |
| 5/12/1991 | 1991 | 5 | 12 | 346 | 35 | 77 | 56 | 24 | 6184 |
| 5/13/1991 | 1991 | 5 | 13 | 347 | 35 | 84 | 59.5 | 27.5 | 6211.5 |
| 5/14/1991 | 1991 | 5 | 14 | 348 | 35 | 80 | 57.5 | 25.5 | 6237 |
| 5/15/1991 | 1991 | 5 | 15 | 349 | 35 | 70 | 52.5 | 20.5 | 6257.5 |
| 5/16/1991 | 1991 | 5 | 16 | 350 | 33 | 79 | 56 | 24 | 6281.5 |
| 5/17/1991 | 1991 | 5 | 17 | 351 | 39 | 83 | 61 | 29 | 6310.5 |
| 5/18/1991 | 1991 | 5 | 18 | 352 | 40 | 86 | 63 | 31 | 6341.5 |
| 5/19/1991 | 1991 | 5 | 19 | 353 | 38 | 83 | 60.5 | 28.5 | 6370 |
| 5/20/1991 | 1991 | 5 | 20 | 354 | 40 | 74 | 57 | 25 | 6395 |
| 5/21/1991 | 1991 | 5 | 21 | 355 | 44 | 66 | 55 | 23 | 6418 |
| 5/22/1991 | 1991 | 5 | 22 | 356 | 40 | 79 | 59.5 | 27.5 | 6445.5 |
| 5/23/1991 | 1991 | 5 | 23 | 357 | 40 | 79 | 59.5 | 27.5 | 6473 |
| 5/24/1991 | 1991 | 5 | 24 | 358 | 37 | 81 | 59 | 27 | 6500 |
| 5/25/1991 | 1991 | 5 | 25 | 359 | 38 | 83 | 60.5 | 28.5 | 6528.5 |
| 5/26/1991 | 1991 | 5 | 26 | 360 | 40 | 87 | 63.5 | 31.5 | 6560 |
| 5/27/1991 | 1991 | 5 | 27 | 361 | 40 | 87 | 63.5 | 31.5 | 6591.5 |
| 5/28/1991 | 1991 | 5 | 28 | 362 | 35 | 83 | 59 | 27 | 6618.5 |
| 5/29/1991 | 1991 | 5 | 29 | 363 | 35 | 83 | 59 | 27 | 6645.5 |
| 5/30/1991 | 1991 | 5 | 30 | 364 | 41 | 83 | 62 | 30 | 6675.5 |
| 5/31/1991 | 1991 | 5 | 31 | 365 | 42 | 76 | 59 | 27 | 6702.5 |
| 6/1/1991 | 1991 | 6 | 1 | 1 | 33 | 73 | 53 | 21 | 21 |
| 6/2/1991 | 1991 | 6 | 2 | 2 | 33 | 72 | 52.5 | 20.5 | 41.5 |
| 6/3/1991 | 1991 | 6 | 3 | 3 | 39 | 75 | 57 | 25 | 66.5 |
| 6/4/1991 | 1991 | 6 | 4 | 4 | 40 | 85 | 62.5 | 30.5 | 97 |
| 6/5/1991 | 1991 | 6 | 5 | 5 | 43 | 84 | 63.5 | 31.5 | 128.5 |
| 6/6/1991 | 1991 | 6 | 6 | 6 | 45 | 74 | 59.5 | 27.5 | 156 |
| 6/7/1991 | 1991 | 6 | 7 | 7 | 39 | 88 | 63.5 | 31.5 | 187.5 |
| 6/8/1991 | 1991 | 6 | 8 | 8 | 48 | 87 | 67.5 | 35.5 | 223 |
| 6/9/1991 | 1991 | 6 | 9 | 9 | 49 | 82 | 65.5 | 33.5 | 256.5 |
| 6/10/1991 | 1991 | 6 | 10 | 10 | 46 | 80 | 63 | 31 | 287.5 |
| 6/11/1991 | 1991 | 6 | 11 | 11 | 37 | 76 | 56.5 | 24.5 | 312 |
| 6/12/1991 | 1991 | 6 | 12 | 12 | 45 | 71 | 58 | 26 | 338 |
| 6/13/1991 | 1991 | 6 | 13 | 13 | 49 | 72 | 60.5 | 28.5 | 366.5 |
| 6/14/1991 | 1991 | 6 | 14 | 14 | 42 | 70 | 56 | 24 | 390.5 |
| 6/15/1991 | 1991 | 6 | 15 | 15 | 41 | 83 | 62 | 30 | 420.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/16/1991 | 1991 | 6 | 16 | 16 | 46 | 87 | 66.5 | 34.5 | 455 |
| 6/17/1991 | 1991 | 6 | 17 | 17 | 49 | 90 | 69.5 | 37.5 | 492.5 |
| 6/18/1991 | 1991 | 6 | 18 | 18 | 48 | 91 | 69.5 | 37.5 | 530 |
| 6/19/1991 | 1991 | 6 | 19 | 19 | 51 | 87 | 69 | 37 | 567 |
| 6/20/1991 | 1991 | 6 | 20 | 20 | 44 | 89 | 66.5 | 34.5 | 601.5 |
| 6/21/1991 | 1991 | 6 | 21 | 21 | 42 | 89 | 65.5 | 33.5 | 635 |
| 6/22/1991 | 1991 | 6 | 22 | 22 | 44 | 92 | 68 | 36 | 671 |
| 6/23/1991 | 1991 | 6 | 23 | 23 | 48 | 92 | 70 | 38 | 709 |
| 6/24/1991 | 1991 | 6 | 24 | 24 | 46 | 94 | 70 | 38 | 747 |
| 6/25/1991 | 1991 | 6 | 25 | 25 | 45 | 92 | 68.5 | 36.5 | 783.5 |
| 6/26/1991 | 1991 | 6 | 26 | 26 | 44 | 93 | 68.5 | 36.5 | 820 |
| 6/27/1991 | 1991 | 6 | 27 | 27 | 45 | 89 | 67 | 35 | 855 |
| 6/28/1991 | 1991 | 6 | 28 | 28 | 52 | 92 | 72 | 40 | 895 |
| 6/29/1991 | 1991 | 6 | 29 | 29 | 57 | 89 | 73 | 41 | 936 |
| 6/30/1991 | 1991 | 6 | 30 | 30 | 54 | 92 | 73 | 41 | 977 |
| 7/1/1991 | 1991 | 7 | 1 | 31 | 49 | 95 | 72 | 40 | 1017 |
| 7/2/1991 | 1991 | 7 | 2 | 32 | 53 | 90 | 71.5 | 39.5 | 1056.5 |
| 7/3/1991 | 1991 | 7 | 3 | 33 | 54 | 95 | 74.5 | 42.5 | 1099 |
| 7/4/1991 | 1991 | 7 | 4 | 34 | 59 | 89 | 74 | 42 | 1141 |
| 7/5/1991 | 1991 | 7 | 5 | 35 | 58 | 84 | 71 | 39 | 1180 |
| 7/6/1991 | 1991 | 7 | 6 | 36 | 54 | 94 | 74 | 42 | 1222 |
| 7/7/1991 | 1991 | 7 | 7 | 37 | 57 | 98 | 77.5 | 45.5 | 1267.5 |
| 7/8/1991 | 1991 | 7 | 8 | 38 | 60 | 88 | 74 | 42 | 1309.5 |
| 7/9/1991 | 1991 | 7 | 9 | 39 | 57 | 91 | 74 | 42 | 1351.5 |
| 7/10/1991 | 1991 | 7 | 10 | 40 | 58 | 89 | 73.5 | 41.5 | 1393 |
| 7/11/1991 | 1991 | 7 | 11 | 41 | 51 | 88 | 69.5 | 37.5 | 1430.5 |
| 7/12/1991 | 1991 | 7 | 12 | 42 | 55 | 84 | 69.5 | 37.5 | 1468 |
| 7/13/1991 | 1991 | 7 | 13 | 43 | 50 | 84 | 67 | 35 | 1503 |
| 7/14/1991 | 1991 | 7 | 14 | 44 | 55 | 84 | 69.5 | 37.5 | 1540.5 |
| 7/15/1991 | 1991 | 7 | 15 | 45 | 56 | 88 | 72 | 40 | 1580.5 |
| 7/16/1991 | 1991 | 7 | 16 | 46 | 57 | 89 | 73 | 41 | 1621.5 |
| 7/17/1991 | 1991 | 7 | 17 | 47 | 57 | 86 | 71.5 | 39.5 | 1661 |
| 7/18/1991 | 1991 | 7 | 18 | 48 | 57 | 84 | 70.5 | 38.5 | 1699.5 |
| 7/19/1991 | 1991 | 7 | 19 | 49 | 59 | 85 | 72 | 40 | 1739.5 |
| 7/20/1991 | 1991 | 7 | 20 | 50 | 55 | 84 | 69.5 | 37.5 | 1777 |
| 7/21/1991 | 1991 | 7 | 21 | 51 | 56 | 86 | 71 | 39 | 1816 |
| 7/22/1991 | 1991 | 7 | 22 | 52 | 55 | 87 | 71 | 39 | 1855 |
| 7/23/1991 | 1991 | 7 | 23 | 53 | 54 | 81 | 67.5 | 35.5 | 1890.5 |
| 7/24/1991 | 1991 | 7 | 24 | 54 | 53 | 82 | 67.5 | 35.5 | 1926 |
| 7/25/1991 | 1991 | 7 | 25 | 55 | 54 | 81 | 67.5 | 35.5 | 1961.5 |
| 7/26/1991 | 1991 | 7 | 26 | 56 | 50 | 80 | 65 | 33 | 1994.5 |
| 7/27/1991 | 1991 | 7 | 27 | 57 | 49 | 89 | 69 | 37 | 2031.5 |
| 7/28/1991 | 1991 | 7 | 28 | 58 | 56 | 89 | 72.5 | 40.5 | 2072 |
| 7/29/1991 | 1991 | 7 | 29 | 59 | 52 | 89 | 70.5 | 38.5 | 2110.5 |
| 7/30/1991 | 1991 | 7 | 30 | 60 | 55 | 89 | 72 | 40 | 2150.5 |
| 7/31/1991 | 1991 | 7 | 31 | 61 | 56 | 90 | 73 | 41 | 2191.5 |
| 8/1/1991 | 1991 | 8 | 1 | 62 | 57 | 84 | 70.5 | 38.5 | 2230 |
| 8/2/1991 | 1991 | 8 | 2 | 63 | 55 | 87 | 71 | 39 | 2269 |
| 8/3/1991 | 1991 | 8 | 3 | 64 | 56 | 79 | 67.5 | 35.5 | 2304.5 |
| 8/4/1991 | 1991 | 8 | 4 | 65 | 56 | 80 | 68 | 36 | 2340.5 |
| 8/5/1991 | 1991 | 8 | 5 | 66 | 57 | 81 | 69 | 37 | 2377.5 |
| 8/6/1991 | 1991 | 8 | 6 | 67 | 54 | 86 | 70 | 38 | 2415.5 |
| 8/7/1991 | 1991 | 8 | 7 | 68 | 55 | 87 | 71 | 39 | 2454.5 |
| 8/8/1991 | 1991 | 8 | 8 | 69 | 52 | 90 | 71 | 39 | 2493.5 |
| 8/9/1991 | 1991 | 8 | 9 | 70 | 55 | 81 | 68 | 36 | 2529.5 |
| 8/10/1991 | 1991 | 8 | 10 | 71 | 56 | 83 | 69.5 | 37.5 | 2567 |
| 8/11/1991 | 1991 | 8 | 11 | 72 | 56 | 77 | 66.5 | 34.5 | 2601.5 |
| 8/12/1991 | 1991 | 8 | 12 | 73 | 55 | 86 | 70.5 | 38.5 | 2640 |
| 8/13/1991 | 1991 | 8 | 13 | 74 | 56 | 90 | 73 | 41 | 2681 |
| 8/14/1991 | 1991 | 8 | 14 | 75 | 56 | 89 | 72.5 | 40.5 | 2721.5 |
| 8/15/1991 | 1991 | 8 | 15 | 76 | 57 | 86 | 71.5 | 39.5 | 2761 |
| 8/16/1991 | 1991 | 8 | 16 | 77 | 55 | 88 | 71.5 | 39.5 | 2800.5 |
| 8/17/1991 | 1991 | 8 | 17 | 78 | 55 | 87 | 71 | 39 | 2839.5 |
| 8/18/1991 | 1991 | 8 | 18 | 79 | 55 | 77 | 66 | 34 | 2873.5 |
| 8/19/1991 | 1991 | 8 | 19 | 80 | 57 | 85 | 71 | 39 | 2912.5 |
| 8/20/1991 | 1991 | 8 | 20 | 81 | 54 | 92 | 73 | 41 | 2953.5 |
| 8/21/1991 | 1991 | 8 | 21 | 82 | 54 | 94 | 74 | 42 | 2995.5 |
| 8/22/1991 | 1991 | 8 | 22 | 83 | 54 | 94 | 74 | 42 | 3037.5 |
| 8/23/1991 | 1991 | 8 | 23 | 84 | 55 | 90 | 72.5 | 40.5 | 3078 |
| 8/24/1991 | 1991 | 8 | 24 | 85 | 53 | 77 | 65 | 33 | 3111 |
| 8/25/1991 | 1991 | 8 | 25 | 86 | 52 | 91 | 71.5 | 39.5 | 3150.5 |
| 8/26/1991 | 1991 | 8 | 26 | 87 | 49 | 89 | 69 | 37 | 3187.5 |
| 8/27/1991 | 1991 | 8 | 27 | 88 | 48 | 91 | 69.5 | 37.5 | 3225 |
| 8/28/1991 | 1991 | 8 | 28 | 89 | 50 | 84 | 67 | 35 | 3260 |
| 8/29/1991 | 1991 | 8 | 29 | 90 | 49 | 89 | 69 | 37 | 3297 |
| 8/30/1991 | 1991 | 8 | 30 | 91 | 50 | 87 | 68.5 | 36.5 | 3333.5 |
| 8/31/1991 | 1991 | 8 | 31 | 92 | 55 | 83 | 69 | 37 | 3370.5 |
| 9/1/1991 | 1991 | 9 | 1 | 93 | 55 | 89 | 72 | 40 | 3410.5 |
| 9/2/1991 | 1991 | 9 | 2 | 94 | 55 | 88 | 71.5 | 39.5 | 3450 |
| 9/3/1991 | 1991 | 9 | 3 | 95 | 49 | 94 | 71.5 | 39.5 | 3489.5 |
| 9/4/1991 | 1991 | 9 | 4 | 96 | 58 | 81 | 69.5 | 37.5 | 3527 |
| 9/5/1991 | 1991 | 9 | 5 | 97 | 54 | 70 | 62 | 30 | 3557 |
| 9/6/1991 | 1991 | 9 | 6 | 98 | 54 | 77 | 65.5 | 33.5 | 3590.5 |
| 9/7/1991 | 1991 | 9 | 7 | 99 | 50 | 81 | 65.5 | 33.5 | 3624 |
| 9/8/1991 | 1991 | 9 | 8 | 100 | 50 | 80 | 65 | 33 | 3657 |
| 9/9/1991 | 1991 | 9 | 9 | 101 | 48 | 80 | 64 | 32 | 3689 |
| 9/10/1991 | 1991 | 9 | 10 | 102 | 56 | 77 | 66.5 | 34.5 | 3723.5 |
| 9/11/1991 | 1991 | 9 | 11 | 103 | 54 | 78 | 66 | 34 | 3757.5 |
| 9/12/1991 | 1991 | 9 | 12 | 104 | 52 | 79 | 65.5 | 33.5 | 3791 |
| 9/13/1991 | 1991 | 9 | 13 | 105 | 52 | 79 | 65.5 | 33.5 | 3824.5 |
| 9/14/1991 | 1991 | 9 | 14 | 106 | 45 | 79 | 62 | 30 | 3854.5 |
| 9/15/1991 | 1991 | 9 | 15 | 107 | 46 | 78 | 62 | 30 | 3884.5 |
| 9/16/1991 | 1991 | 9 | 16 | 108 | 35 | 82 | 58.5 | 26.5 | 3911 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/17/1991 | 1991 | 9 | 17 | 109 | 41 | 84 | 62.5 | 30.5 | 3941.5 |
| 9/18/1991 | 1991 | 9 | 18 | 110 | 40 | 76 | 58 | 26 | 3967.5 |
| 9/19/1991 | 1991 | 9 | 19 | 111 | 40 | 69 | 54.5 | 22.5 | 3990 |
| 9/20/1991 | 1991 | 9 | 20 | 112 | 41 | 72 | 56.5 | 24.5 | 4014.5 |
| 9/21/1991 | 1991 | 9 | 21 | 113 | 48 | 83 | 65.5 | 33.5 | 4048 |
| 9/22/1991 | 1991 | 9 | 22 | 114 | 44 | 82 | 63 | 31 | 4079 |
| 9/23/1991 | 1991 | 9 | 23 | 115 | 46 | 80 | 63 | 31 | 4110 |
| 9/24/1991 | 1991 | 9 | 24 | 116 | 38 | 85 | 61.5 | 29.5 | 4139.5 |
| 9/25/1991 | 1991 | 9 | 25 | 117 | 38 | 87 | 62.5 | 30.5 | 4170 |
| 9/26/1991 | 1991 | 9 | 26 | 118 | 45 | 80 | 62.5 | 30.5 | 4200.5 |
| 9/27/1991 | 1991 | 9 | 27 | 119 | 43 | 81 | 62 | 30 | 4230.5 |
| 9/28/1991 | 1991 | 9 | 28 | 120 | 41 | 77 | 59 | 27 | 4257.5 |
| 9/29/1991 | 1991 | 9 | 29 | 121 | 40 | 78 | 59 | 27 | 4284.5 |
| 9/30/1991 | 1991 | 9 | 30 | 122 | 40 | 76 | 58 | 26 | 4310.5 |
| 10/1/1991 | 1991 | 10 | 1 | 123 | 41 | 78 | 59.5 | 27.5 | 4338 |
| 10/2/1991 | 1991 | 10 | 2 | 124 | 39 | 82 | 60.5 | 28.5 | 4366.5 |
| 10/3/1991 | 1991 | 10 | 3 | 125 | 35 | 82 | 58.5 | 26.5 | 4393 |
| 10/4/1991 | 1991 | 10 | 4 | 126 | 33 | 82 | 57.5 | 25.5 | 4418.5 |
| 10/5/1991 | 1991 | 10 | 5 | 127 | 34 | 79 | 56.5 | 24.5 | 4443 |
| 10/6/1991 | 1991 | 10 | 6 | 128 | 34 | 83 | 58.5 | 26.5 | 4469.5 |
| 10/7/1991 | 1991 | 10 | 7 | 129 | 30 | 83 | 56.5 | 24.5 | 4494 |
| 10/8/1991 | 1991 | 10 | 8 | 130 | 33 | 84 | 58.5 | 26.5 | 4520.5 |
| 10/9/1991 | 1991 | 10 | 9 | 131 | 36 | 83 | 59.5 | 27.5 | 4548 |
| 10/10/1991 | 1991 | 10 | 10 | 132 | 35 | 84 | 59.5 | 27.5 | 4575.5 |
| 10/11/1991 | 1991 | 10 | 11 | 133 | 34 | 85 | 59.5 | 27.5 | 4603 |
| 10/12/1991 | 1991 | 10 | 12 | 134 | 34 | 76 | 55 | 23 | 4626 |
| 10/13/1991 | 1991 | 10 | 13 | 135 | 35 | 80 | 57.5 | 25.5 | 4651.5 |
| 10/14/1991 | 1991 | 10 | 14 | 136 | 33 | 77 | 55 | 23 | 4674.5 |
| 10/15/1991 | 1991 | 10 | 15 | 137 | 35 | 83 | 59 | 27 | 4701.5 |
| 10/16/1991 | 1991 | 10 | 16 | 138 | 31 | 87 | 59 | 27 | 4728.5 |
| 10/17/1991 | 1991 | 10 | 17 | 139 | 39 | 82 | 60.5 | 28.5 | 4757 |
| 10/18/1991 | 1991 | 10 | 18 | 140 | 31 | 80 | 55.5 | 23.5 | 4780.5 |
| 10/19/1991 | 1991 | 10 | 19 | 141 | 28 | 80 | 54 | 22 | 4802.5 |
| 10/20/1991 | 1991 | 10 | 20 | 142 | 28 | 70 | 49 | 17 | 4819.5 |
| 10/21/1991 | 1991 | 10 | 21 | 143 | 36 | 71 | 53.5 | 21.5 | 4841 |
| 10/22/1991 | 1991 | 10 | 22 | 144 | 35 | 70 | 52.5 | 20.5 | 4861.5 |
| 10/23/1991 | 1991 | 10 | 23 | 145 | 34 | 70 | 52 | 20 | 4881.5 |
| 10/24/1991 | 1991 | 10 | 24 | 146 | 41 | 68 | 54.5 | 22.5 | 4904 |
| 10/25/1991 | 1991 | 10 | 25 | 147 | 36 | 66 | 51 | 19 | 4923 |
| 10/26/1991 | 1991 | 10 | 26 | 148 | 25 | 69 | 47 | 15 | 4938 |
| 10/27/1991 | 1991 | 10 | 27 | 149 | 32 | 65 | 48.5 | 16.5 | 4954.5 |
| 10/28/1991 | 1991 | 10 | 28 | 150 | 32 | 40 | 36 | 4 | 4958.5 |
| 10/29/1991 | 1991 | 10 | 29 | 151 | 20 | 53 | 36.5 | 4.5 | 4963 |
| 10/30/1991 | 1991 | 10 | 30 | 152 | 32 | 48 | 40 | 8 | 4971 |
| 10/31/1991 | 1991 | 10 | 31 | 153 | 19 | 38 | 28.5 | -3.5 | 4967.5 |
| 11/1/1991 | 1991 | 11 | 1 | 154 | 14 | 50 | 32 | 0 | 4967.5 |
| 11/2/1991 | 1991 | 11 | 2 | 155 | 20 | 59 | 39.5 | 7.5 | 4975 |
| 11/3/1991 | 1991 | 11 | 3 | 156 | 15 | 46 | 30.5 | -1.5 | 4973.5 |
| 11/4/1991 | 1991 | 11 | 4 | 157 | 17 | 49 | 33 | 1 | 4974.5 |
| 11/5/1991 | 1991 | 11 | 5 | 158 | 23 | 60 | 41.5 | 9.5 | 4984 |
| 11/6/1991 | 1991 | 11 | 6 | 159 | 22 | 69 | 45.5 | 13.5 | 4997.5 |
| 11/7/1991 | 1991 | 11 | 7 | 160 | 25 | 69 | 47 | 15 | 5012.5 |
| 11/8/1991 | 1991 | 11 | 8 | 161 | 25 | 69 | 47 | 15 | 5027.5 |
| 11/9/1991 | 1991 | 11 | 9 | 162 | 24 | 73 | 48.5 | 16.5 | 5044 |
| 11/10/1991 | 1991 | 11 | 10 | 163 | 43 | 53 | 48 | 16 | 5060 |
| 11/11/1991 | 1991 | 11 | 11 | 164 | 39 | 49 | 44 | 12 | 5072 |
| 11/12/1991 | 1991 | 11 | 12 | 165 | 29 | 58 | 43.5 | 11.5 | 5083.5 |
| 11/13/1991 | 1991 | 11 | 13 | 166 | 27 | 64 | 45.5 | 13.5 | 5097 |
| 11/14/1991 | 1991 | 11 | 14 | 167 | 36 | 59 | 47.5 | 15.5 | 5112.5 |
| 11/15/1991 | 1991 | 11 | 15 | 168 | 37 | 51 | 44 | 12 | 5124.5 |
| 11/16/1991 | 1991 | 11 | 16 | 169 | 26 | 40 | 33 | 1 | 5125.5 |
| 11/17/1991 | 1991 | 11 | 17 | 170 | 25 | 59 | 42 | 10 | 5135.5 |
| 11/18/1991 | 1991 | 11 | 18 | 171 | 29 | 49 | 39 | 7 | 5142.5 |
| 11/19/1991 | 1991 | 11 | 19 | 172 | 26 | 47 | 36.5 | 4.5 | 5147 |
| 11/20/1991 | 1991 | 11 | 20 | 173 | 20 | 49 | 34.5 | 2.5 | 5149.5 |
| 11/21/1991 | 1991 | 11 | 21 | 174 | 20 | 64 | 42 | 10 | 5159.5 |
| 11/22/1991 | 1991 | 11 | 22 | 175 | 25 | 45 | 35 | 3 | 5162.5 |
| 11/23/1991 | 1991 | 11 | 23 | 176 | 20 | 43 | 31.5 | -0.5 | 5162 |
| 11/24/1991 | 1991 | 11 | 24 | 177 | 18 | 50 | 34 | 2 | 5164 |
| 11/25/1991 | 1991 | 11 | 25 | 178 | 18 | 56 | 37 | 5 | 5169 |
| 11/26/1991 | 1991 | 11 | 26 | 179 | 18 | 61 | 39.5 | 7.5 | 5176.5 |
| 11/27/1991 | 1991 | 11 | 27 | 180 | 24 | 66 | 45 | 13 | 5189.5 |
| 11/28/1991 | 1991 | 11 | 28 | 181 | 28 | 64 | 46 | 14 | 5203.5 |
| 11/29/1991 | 1991 | 11 | 29 | 182 | 23 | 44 | 33.5 | 1.5 | 5205 |
| 11/30/1991 | 1991 | 11 | 30 | 183 | 22 | 38 | 30 | -2 | 5203 |
| 12/1/1991 | 1991 | 12 | 1 | 184 | 16 | 35 | 25.5 | -6.5 | 5196.5 |
| 12/2/1991 | 1991 | 12 | 2 | 185 | 2 | 38 | 20 | -12 | 5184.5 |
| 12/3/1991 | 1991 | 12 | 3 | 186 | 5 | 39 | 22 | -10 | 5174.5 |
| 12/4/1991 | 1991 | 12 | 4 | 187 | 5 | 49 | 27 | -5 | 5169.5 |
| 12/5/1991 | 1991 | 12 | 5 | 188 | 15 | 50 | 32.5 | 0.5 | 5170 |
| 12/6/1991 | 1991 | 12 | 6 | 189 | 16 | 58 | 37 | 5 | 5175 |
| 12/7/1991 | 1991 | 12 | 7 | 190 | 16 | 55 | 35.5 | 3.5 | 5178.5 |
| 12/8/1991 | 1991 | 12 | 8 | 191 | 21 | 55 | 38 | 6 | 5184.5 |
| 12/9/1991 | 1991 | 12 | 9 | 192 | 19 | 58 | 38.5 | 6.5 | 5191 |
| 12/10/1991 | 1991 | 12 | 10 | 193 | 19 | 56 | 37.5 | 5.5 | 5196.5 |
| 12/11/1991 | 1991 | 12 | 11 | 194 | 28 | 40 | 34 | 2 | 5198.5 |
| 12/12/1991 | 1991 | 12 | 12 | 195 | 32 | 48 | 40 | 8 | 5206.5 |
| 12/13/1991 | 1991 | 12 | 13 | 196 | 19 | 45 | 32 | 0 | 5206.5 |
| 12/14/1991 | 1991 | 12 | 14 | 197 | 12 | 48 | 30 | -2 | 5204.5 |
| 12/15/1991 | 1991 | 12 | 15 | 198 | 12 | 50 | 31 | -1 | 5203.5 |
| 12/16/1991 | 1991 | 12 | 16 | 199 | 2 | 52 | 27 | -5 | 5198.5 |
| 12/17/1991 | 1991 | 12 | 17 | 200 | 20 | 47 | 33.5 | 1.5 | 5200 |
| 12/18/1991 | 1991 | 12 | 18 | 201 | 32 | 40 | 36 | 4 | 5204 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/19/1991 | 1991 | 12 | 19 | 202 | 30 | 41 | 35.5 | 3.5 | 5207.5 |
| 12/20/1991 | 1991 | 12 | 20 | 203 | 31 | 40 | 35.5 | 3.5 | 5211 |
| 12/21/1991 | 1991 | 12 | 21 | 204 | 31 | 38 | 34.5 | 2.5 | 5213.5 |
| 12/22/1991 | 1991 | 12 | 22 | 205 | 30 | 46 | 38 | 6 | 5219.5 |
| 12/23/1991 | 1991 | 12 | 23 | 206 | 20 | 43 | 31.5 | -0.5 | 5219 |
| 12/24/1991 | 1991 | 12 | 24 | 207 | 26 | 44 | 35 | 3 | 5222 |
| 12/25/1991 | 1991 | 12 | 25 | 208 | 20 | 37 | 28.5 | -3.5 | 5218.5 |
| 12/26/1991 | 1991 | 12 | 26 | 209 | 24 | 45 | 34.5 | 2.5 | 5221 |
| 12/27/1991 | 1991 | 12 | 27 | 210 | 20 | 46 | 33 | 1 | 5222 |
| 12/28/1991 | 1991 | 12 | 28 | 211 | 21 | 43 | 32 | 0 | 5222 |
| 12/29/1991 | 1991 | 12 | 29 | 212 | 20 | 48 | 34 | 2 | 5224 |
| 12/30/1991 | 1991 | 12 | 30 | 213 | 18 | 43 | 30.5 | -1.5 | 5222.5 |
| 12/31/1991 | 1991 | 12 | 31 | 214 | 25 | 43 | 34 | 2 | 5224.5 |
| 1/1/1992 | 1992 | 1 | 1 | 215 | 16 | 36 | 26 | -6 | 5218.5 |
| 1/2/1992 | 1992 | 1 | 2 | 216 | 15 | 43 | 29 | -3 | 5215.5 |
| 1/3/1992 | 1992 | 1 | 3 | 217 | 14 | 33 | 23.5 | -8.5 | 5207 |
| 1/4/1992 | 1992 | 1 | 4 | 218 | 28 | 42 | 35 | 3 | 5210 |
| 1/5/1992 | 1992 | 1 | 5 | 219 | 15 | 43 | 29 | -3 | 5207 |
| 1/6/1992 | 1992 | 1 | 6 | 220 | 25 | 47 | 36 | 4 | 5211 |
| 1/7/1992 | 1992 | 1 | 7 | 221 | 23 | 40 | 31.5 | -0.5 | 5210.5 |
| 1/8/1992 | 1992 | 1 | 8 | 222 | 12 | 36 | 24 | -8 | 5202.5 |
| 1/9/1992 | 1992 | 1 | 9 | 223 | 12 | 42 | 27 | -5 | 5197.5 |
| 1/10/1992 | 1992 | 1 | 10 | 224 | 10 | 50 | 30 | -2 | 5195.5 |
| 1/11/1992 | 1992 | 1 | 11 | 225 | 19 | 39 | 29 | -3 | 5192.5 |
| 1/12/1992 | 1992 | 1 | 12 | 226 | 20 | 32 | 26 | -6 | 5186.5 |
| 1/13/1992 | 1992 | 1 | 13 | 227 | 6 | 33 | 19.5 | -12.5 | 5174 |
| 1/14/1992 | 1992 | 1 | 14 | 228 | -9 | 37 | 14 | -18 | 5156 |
| 1/15/1992 | 1992 | 1 | 15 | 229 | -7 | 30 | 11.5 | -20.5 | 5135.5 |
| 1/16/1992 | 1992 | 1 | 16 | 230 | -8 | 37 | 14.5 | -17.5 | 5118 |
| 1/17/1992 | 1992 | 1 | 17 | 231 | 0 | 35 | 17.5 | -14.5 | 5103.5 |
| 1/18/1992 | 1992 | 1 | 18 | 232 | -3 | 32 | 14.5 | -17.5 | 5086 |
| 1/19/1992 | 1992 | 1 | 19 | 233 | -2 | 36 | 17 | -15 | 5071 |
| 1/20/1992 | 1992 | 1 | 20 | 234 | -2 | 39 | 18.5 | -13.5 | 5057.5 |
| 1/21/1992 | 1992 | 1 | 21 | 235 | 8 | 46 | 27 | -5 | 5052.5 |
| 1/22/1992 | 1992 | 1 | 22 | 236 | 11 | 46 | 28.5 | -3.5 | 5049 |
| 1/23/1992 | 1992 | 1 | 23 | 237 | 8 | 42 | 25 | -7 | 5042 |
| 1/24/1992 | 1992 | 1 | 24 | 238 | 10 | 55 | 32.5 | 0.5 | 5042.5 |
| 1/25/1992 | 1992 | 1 | 25 | 239 | 15 | 49 | 32 | 0 | 5042.5 |
| 1/26/1992 | 1992 | 1 | 26 | 240 | 20 | 51 | 35.5 | 3.5 | 5046 |
| 1/27/1992 | 1992 | 1 | 27 | 241 | 20 | 52 | 36 | 4 | 5050 |
| 1/28/1992 | 1992 | 1 | 28 | 242 | 18 | 51 | 34.5 | 2.5 | 5052.5 |
| 1/29/1992 | 1992 | 1 | 29 | 243 | 20 | 55 | 37.5 | 5.5 | 5058 |
| 1/30/1992 | 1992 | 1 | 30 | 244 | 20 | 52 | 36 | 4 | 5062 |
| 1/31/1992 | 1992 | 1 | 31 | 245 | 19 | 58 | 38.5 | 6.5 | 5068.5 |
| 2/1/1992 | 1992 | 2 | 1 | 246 | 19 | 55 | 37 | 5 | 5073.5 |
| 2/2/1992 | 1992 | 2 | 2 | 247 | 25 | 49 | 37 | 5 | 5078.5 |
| 2/3/1992 | 1992 | 2 | 3 | 248 | 28 | 41 | 34.5 | 2.5 | 5081 |
| 2/4/1992 | 1992 | 2 | 4 | 249 | 26 | 42 | 34 | 2 | 5083 |
| 2/5/1992 | 1992 | 2 | 5 | 250 | 22 | 51 | 36.5 | 4.5 | 5087.5 |
| 2/6/1992 | 1992 | 2 | 6 | 251 | 19 | 49 | 34 | 2 | 5089.5 |
| 2/7/1992 | 1992 | 2 | 7 | 252 | 19 | 46 | 32.5 | 0.5 | 5090 |
| 2/8/1992 | 1992 | 2 | 8 | 253 | 21 | 51 | 36 | 4 | 5094 |
| 2/9/1992 | 1992 | 2 | 9 | 254 | 26 | 47 | 36.5 | 4.5 | 5098.5 |
| 2/10/1992 | 1992 | 2 | 10 | 255 | 27 | 49 | 38 | 6 | 5104.5 |
| 2/11/1992 | 1992 | 2 | 11 | 256 | 26 | 47 | 36.5 | 4.5 | 5109 |
| 2/12/1992 | 1992 | 2 | 12 | 257 | 28 | 52 | 40 | 8 | 5117 |
| 2/13/1992 | 1992 | 2 | 13 | 258 | 29 | 48 | 38.5 | 6.5 | 5123.5 |
| 2/14/1992 | 1992 | 2 | 14 | 259 | 34 | 47 | 40.5 | 8.5 | 5132 |
| 2/15/1992 | 1992 | 2 | 15 | 260 | 20 | 50 | 35 | 3 | 5135 |
| 2/16/1992 | 1992 | 2 | 16 | 261 | 24 | 43 | 33.5 | 1.5 | 5136.5 |
| 2/17/1992 | 1992 | 2 | 17 | 262 | 22 | 46 | 34 | 2 | 5138.5 |
| 2/18/1992 | 1992 | 2 | 18 | 263 | 15 | 46 | 30.5 | -1.5 | 5137 |
| 2/19/1992 | 1992 | 2 | 19 | 264 | 16 | 58 | 37 | 5 | 5142 |
| 2/20/1992 | 1992 | 2 | 20 | 265 | 19 | 60 | 39.5 | 7.5 | 5149.5 |
| 2/21/1992 | 1992 | 2 | 21 | 266 | 29 | 59 | 44 | 12 | 5161.5 |
| 2/22/1992 | 1992 | 2 | 22 | 267 | 21 | 65 | 43 | 11 | 5172.5 |
| 2/23/1992 | 1992 | 2 | 23 | 268 | 33 | 49 | 41 | 9 | 5181.5 |
| 2/24/1992 | 1992 | 2 | 24 | 269 | 24 | 54 | 39 | 7 | 5188.5 |
| 2/25/1992 | 1992 | 2 | 25 | 270 | 19 | 52 | 35.5 | 3.5 | 5192 |
| 2/26/1992 | 1992 | 2 | 26 | 271 | 20 | 51 | 35.5 | 3.5 | 5195.5 |
| 2/27/1992 | 1992 | 2 | 27 | 272 | 16 | 63 | 39.5 | 7.5 | 5203 |
| 2/28/1992 | 1992 | 2 | 28 | 273 | 19 | 62 | 40.5 | 8.5 | 5211.5 |
| 2/29/1992 | 1992 | 2 | 29 | 274 | 20 | 64 | 42 | 10 | 5221.5 |
| 3/1/1992 | 1992 | 3 | 1 | 275 | 25 | 61 | 43 | 11 | 5232.5 |
| 3/2/1992 | 1992 | 3 | 2 | 276 | 23 | 61 | 42 | 10 | 5242.5 |
| 3/3/1992 | 1992 | 3 | 3 | 277 | 31 | 52 | 41.5 | 9.5 | 5252 |
| 3/4/1992 | 1992 | 3 | 4 | 278 | 32 | 52 | 42 | 10 | 5262 |
| 3/5/1992 | 1992 | 3 | 5 | 279 | 35 | 55 | 45 | 13 | 5275 |
| 3/6/1992 | 1992 | 3 | 6 | 280 | 25 | 63 | 44 | 12 | 5287 |
| 3/7/1992 | 1992 | 3 | 7 | 281 | 24 | 62 | 43 | 11 | 5298 |
| 3/8/1992 | 1992 | 3 | 8 | 282 | 28 | 48 | 38 | 6 | 5304 |
| 3/9/1992 | 1992 | 3 | 9 | 283 | 22 | 48 | 35 | 3 | 5307 |
| 3/10/1992 | 1992 | 3 | 10 | 284 | 17 | 58 | 37.5 | 5.5 | 5312.5 |
| 3/11/1992 | 1992 | 3 | 11 | 285 | 16 | 57 | 36.5 | 4.5 | 5317 |
| 3/12/1992 | 1992 | 3 | 12 | 286 | 15 | 66 | 40.5 | 8.5 | 5325.5 |
| 3/13/1992 | 1992 | 3 | 13 | 287 | 18 | 69 | 43.5 | 11.5 | 5337 |
| 3/14/1992 | 1992 | 3 | 14 | 288 | 21 | 70 | 45.5 | 13.5 | 5350.5 |
| 3/15/1992 | 1992 | 3 | 15 | 289 | 23 | 68 | 45.5 | 13.5 | 5364 |
| 3/16/1992 | 1992 | 3 | 16 | 290 | 24 | 68 | 46 | 14 | 5378 |
| 3/17/1992 | 1992 | 3 | 17 | 291 | 31 | 60 | 45.5 | 13.5 | 5391.5 |
| 3/18/1992 | 1992 | 3 | 18 | 292 | 30 | 55 | 42.5 | 10.5 | 5402 |
| 3/19/1992 | 1992 | 3 | 19 | 293 | 18 | 60 | 39 | 7 | 5409 |
| 3/20/1992 | 1992 | 3 | 20 | 294 | 17 | 69 | 43 | 11 | 5420 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/21/1992 | 1992 | 3 | 21 | 295 | 22 | 61 | 41.5 | 9.5 | 5429.5 |
| 3/22/1992 | 1992 | 3 | 22 | 296 | 33 | 56 | 44.5 | 12.5 | 5442 |
| 3/23/1992 | 1992 | 3 | 23 | 297 | 24 | 60 | 42 | 10 | 5452 |
| 3/24/1992 | 1992 | 3 | 24 | 298 | 25 | 62 | 43.5 | 11.5 | 5463.5 |
| 3/25/1992 | 1992 | 3 | 25 | 299 | 24 | 69 | 46.5 | 14.5 | 5478 |
| 3/26/1992 | 1992 | 3 | 26 | 300 | 27 | 67 | 47 | 15 | 5493 |
| 3/27/1992 | 1992 | 3 | 27 | 301 | 36 | 54 | 45 | 13 | 5506 |
| 3/28/1992 | 1992 | 3 | 28 | 302 | 37 | 51 | 44 | 12 | 5518 |
| 3/29/1992 | 1992 | 3 | 29 | 303 | 34 | 53 | 43.5 | 11.5 | 5529.5 |
| 3/30/1992 | 1992 | 3 | 30 | 304 | 29 | 62 | 45.5 | 13.5 | 5543 |
| 3/31/1992 | 1992 | 3 | 31 | 305 | 35 | 52 | 43.5 | 11.5 | 5554.5 |
| 4/1/1992 | 1992 | 4 | 1 | 306 | 30 | 53 | 41.5 | 9.5 | 5564 |
| 4/2/1992 | 1992 | 4 | 2 | 307 | 29 | 60 | 44.5 | 12.5 | 5576.5 |
| 4/3/1992 | 1992 | 4 | 3 | 308 | 34 | 69 | 51.5 | 19.5 | 5596 |
| 4/4/1992 | 1992 | 4 | 4 | 309 | 33 | 70 | 51.5 | 19.5 | 5615.5 |
| 4/5/1992 | 1992 | 4 | 5 | 310 | 34 | 65 | 49.5 | 17.5 | 5633 |
| 4/6/1992 | 1992 | 4 | 6 | 311 | 31 | 72 | 51.5 | 19.5 | 5652.5 |
| 4/7/1992 | 1992 | 4 | 7 | 312 | 31 | 77 | 54 | 22 | 5674.5 |
| 4/8/1992 | 1992 | 4 | 8 | 313 | 30 | 76 | 53 | 21 | 5695.5 |
| 4/9/1992 | 1992 | 4 | 9 | 314 | 36 | 75 | 55.5 | 23.5 | 5719 |
| 4/10/1992 | 1992 | 4 | 10 | 315 | 41 | 79 | 60 | 28 | 5747 |
| 4/11/1992 | 1992 | 4 | 11 | 316 | 37 | 78 | 57.5 | 25.5 | 5772.5 |
| 4/12/1992 | 1992 | 4 | 12 | 317 | 34 | 80 | 57 | 25 | 5797.5 |
| 4/13/1992 | 1992 | 4 | 13 | 318 | 36 | 74 | 55 | 23 | 5820.5 |
| 4/14/1992 | 1992 | 4 | 14 | 319 | 38 | 74 | 56 | 24 | 5844.5 |
| 4/15/1992 | 1992 | 4 | 15 | 320 | 37 | 67 | 52 | 20 | 5864.5 |
| 4/16/1992 | 1992 | 4 | 16 | 321 | 37 | 68 | 52.5 | 20.5 | 5885 |
| 4/17/1992 | 1992 | 4 | 17 | 322 | 34 | 73 | 53.5 | 21.5 | 5906.5 |
| 4/18/1992 | 1992 | 4 | 18 | 323 | 43 | 63 | 53 | 21 | 5927.5 |
| 4/19/1992 | 1992 | 4 | 19 | 324 | 33 | 62 | 47.5 | 15.5 | 5943 |
| 4/20/1992 | 1992 | 4 | 20 | 325 | 33 | 65 | 49 | 17 | 5960 |
| 4/21/1992 | 1992 | 4 | 21 | 326 | 33 | 74 | 53.5 | 21.5 | 5981.5 |
| 4/22/1992 | 1992 | 4 | 22 | 327 | 36 | 73 | 54.5 | 22.5 | 6004 |
| 4/23/1992 | 1992 | 4 | 23 | 328 | 37 | 78 | 57.5 | 25.5 | 6029.5 |
| 4/24/1992 | 1992 | 4 | 24 | 329 | 38 | 83 | 60.5 | 28.5 | 6058 |
| 4/25/1992 | 1992 | 4 | 25 | 330 | 37 | 80 | 58.5 | 26.5 | 6084.5 |
| 4/26/1992 | 1992 | 4 | 26 | 331 | 44 | 81 | 62.5 | 30.5 | 6115 |
| 4/27/1992 | 1992 | 4 | 27 | 332 | 34 | 87 | 60.5 | 28.5 | 6143.5 |
| 4/28/1992 | 1992 | 4 | 28 | 333 | 42 | 87 | 64.5 | 32.5 | 6176 |
| 4/29/1992 | 1992 | 4 | 29 | 334 | 39 | 89 | 64 | 32 | 6208 |
| 4/30/1992 | 1992 | 4 | 30 | 335 | 48 | 84 | 66 | 34 | 6242 |
| 5/1/1992 | 1992 | 5 | 1 | 336 | 45 | 86 | 65.5 | 33.5 | 6275.5 |
| 5/2/1992 | 1992 | 5 | 2 | 337 | 44 | 80 | 62 | 30 | 6305.5 |
| 5/3/1992 | 1992 | 5 | 3 | 338 | 43 | 70 | 56.5 | 24.5 | 6330 |
| 5/4/1992 | 1992 | 5 | 4 | 339 | 42 | 75 | 58.5 | 26.5 | 6356.5 |
| 5/5/1992 | 1992 | 5 | 5 | 340 | 40 | 76 | 58 | 26 | 6382.5 |
| 5/6/1992 | 1992 | 5 | 6 | 341 | 42 | 66 | 54 | 22 | 6404.5 |
| 5/7/1992 | 1992 | 5 | 7 | 342 | 42 | 67 | 54.5 | 22.5 | 6427 |
| 5/8/1992 | 1992 | 5 | 8 | 343 | 40 | 72 | 56 | 24 | 6451 |
| 5/9/1992 | 1992 | 5 | 9 | 344 | 43 | 70 | 56.5 | 24.5 | 6475.5 |
| 5/10/1992 | 1992 | 5 | 10 | 345 | 43 | 70 | 56.5 | 24.5 | 6500 |
| 5/11/1992 | 1992 | 5 | 11 | 346 | 39 | 78 | 58.5 | 26.5 | 6526.5 |
| 5/12/1992 | 1992 | 5 | 12 | 347 | 45 | 81 | 63 | 31 | 6557.5 |
| 5/13/1992 | 1992 | 5 | 13 | 348 | 45 | 83 | 64 | 32 | 6589.5 |
| 5/14/1992 | 1992 | 5 | 14 | 349 | 40 | 85 | 62.5 | 30.5 | 6620 |
| 5/15/1992 | 1992 | 5 | 15 | 350 | 39 | 81 | 60 | 28 | 6648 |
| 5/16/1992 | 1992 | 5 | 16 | 351 | 40 | 82 | 61 | 29 | 6677 |
| 5/17/1992 | 1992 | 5 | 17 | 352 | 40 | 82 | 61 | 29 | 6706 |
| 5/18/1992 | 1992 | 5 | 18 | 353 | 38 | 79 | 58.5 | 26.5 | 6732.5 |
| 5/19/1992 | 1992 | 5 | 19 | 354 | 42 | 80 | 61 | 29 | 6761.5 |
| 5/20/1992 | 1992 | 5 | 20 | 355 | 45 | 64 | 54.5 | 22.5 | 6784 |
| 5/21/1992 | 1992 | 5 | 21 | 356 | 42 | 67 | 54.5 | 22.5 | 6806.5 |
| 5/22/1992 | 1992 | 5 | 22 | 357 | 43 | 65 | 54 | 22 | 6828.5 |
| 5/23/1992 | 1992 | 5 | 23 | 358 | 43 | 60 | 51.5 | 19.5 | 6848 |
| 5/24/1992 | 1992 | 5 | 24 | 359 | 41 | 62 | 51.5 | 19.5 | 6867.5 |
| 5/25/1992 | 1992 | 5 | 25 | 360 | 39 | 67 | 53 | 21 | 6888.5 |
| 5/26/1992 | 1992 | 5 | 26 | 361 | 39 | 72 | 55.5 | 23.5 | 6912 |
| 5/27/1992 | 1992 | 5 | 27 | 362 | 48 | 74 | 61 | 29 | 6941 |
| 5/28/1992 | 1992 | 5 | 28 | 363 | 43 | 78 | 60.5 | 28.5 | 6969.5 |
| 5/29/1992 | 1992 | 5 | 29 | 364 | 48 | 72 | 60 | 28 | 6997.5 |
| 5/30/1992 | 1992 | 5 | 30 | 365 | 45 | 71 | 58 | 26 | 7023.5 |
| 5/31/1992 | 1992 | 5 | 31 | 366 | 40 | 80 | 60 | 28 | 7051.5 |
| 6/1/1992 | 1992 | 6 | 1 | 1 | 42 | 75 | 58.5 | 26.5 | 26.5 |
| 6/2/1992 | 1992 | 6 | 2 | 2 | 37 | 81 | 59 | 27 | 53.5 |
| 6/3/1992 | 1992 | 6 | 3 | 3 | 46 | 78 | 62 | 30 | 83.5 |
| 6/4/1992 | 1992 | 6 | 4 | 4 | 45 | 85 | 65 | 33 | 116.5 |
| 6/5/1992 | 1992 | 6 | 5 | 5 | 48 | 86 | 67 | 35 | 151.5 |
| 6/6/1992 | 1992 | 6 | 6 | 6 | 46 | 85 | 65.5 | 33.5 | 185 |
| 6/7/1992 | 1992 | 6 | 7 | 7 | 54 | 78 | 66 | 34 | 219 |
| 6/8/1992 | 1992 | 6 | 8 | 8 | 42 | 69 | 55.5 | 23.5 | 242.5 |
| 6/9/1992 | 1992 | 6 | 9 | 9 | 40 | 75 | 57.5 | 25.5 | 268 |
| 6/10/1992 | 1992 | 6 | 10 | 10 | 40 | 81 | 60.5 | 28.5 | 296.5 |
| 6/11/1992 | 1992 | 6 | 11 | 11 | 43 | 88 | 65.5 | 33.5 | 330 |
| 6/12/1992 | 1992 | 6 | 12 | 12 | 47 | 89 | 68 | 36 | 366 |
| 6/13/1992 | 1992 | 6 | 13 | 13 | 43 | 85 | 64 | 32 | 398 |
| 6/14/1992 | 1992 | 6 | 14 | 14 | 48 | 88 | 68 | 36 | 434 |
| 6/15/1992 | 1992 | 6 | 15 | 15 | 47 | 84 | 65.5 | 33.5 | 467.5 |
| 6/16/1992 | 1992 | 6 | 16 | 16 | 45 | 79 | 62 | 30 | 497.5 |
| 6/17/1992 | 1992 | 6 | 17 | 17 | 40 | 87 | 63.5 | 31.5 | 529 |
| 6/18/1992 | 1992 | 6 | 18 | 18 | 47 | 92 | 69.5 | 37.5 | 566.5 |
| 6/19/1992 | 1992 | 6 | 19 | 19 | 47 | 92 | 69.5 | 37.5 | 604 |
| 6/20/1992 | 1992 | 6 | 20 | 20 | 48 | 94 | 71 | 39 | 643 |
| 6/21/1992 | 1992 | 6 | 21 | 21 | 50 | 89 | 69.5 | 37.5 | 680.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/22/1992 | 1992 | 6 | 22 | 22 | 50 | 90 | 70 | 38 | 718.5 |
| 6/23/1992 | 1992 | 6 | 23 | 23 | 50 | 86 | 68 | 36 | 754.5 |
| 6/24/1992 | 1992 | 6 | 24 | 24 | 47 | 87 | 67 | 35 | 789.5 |
| 6/25/1992 | 1992 | 6 | 25 | 25 | 47 | 78 | 62.5 | 30.5 | 820 |
| 6/26/1992 | 1992 | 6 | 26 | 26 | 45 | 87 | 66 | 34 | 854 |
| 6/27/1992 | 1992 | 6 | 27 | 27 | 44 | 88 | 66 | 34 | 888 |
| 6/28/1992 | 1992 | 6 | 28 | 28 | 46 | 92 | 69 | 37 | 925 |
| 6/29/1992 | 1992 | 6 | 29 | 29 | 54 | 90 | 72 | 40 | 965 |
| 6/30/1992 | 1992 | 6 | 30 | 30 | 50 | 90 | 70 | 38 | 1003 |
| 7/1/1992 | 1992 | 7 | 1 | 31 | 49 | 86 | 67.5 | 35.5 | 1038.5 |
| 7/2/1992 | 1992 | 7 | 2 | 32 | 49 | 86 | 67.5 | 35.5 | 1074 |
| 7/3/1992 | 1992 | 7 | 3 | 33 | 48 | 86 | 67 | 35 | 1109 |
| 7/4/1992 | 1992 | 7 | 4 | 34 | 50 | 96 | 73 | 41 | 1150 |
| 7/5/1992 | 1992 | 7 | 5 | 35 | 50 | 99 | 74.5 | 42.5 | 1192.5 |
| 7/6/1992 | 1992 | 7 | 6 | 36 | 54 | 97 | 75.5 | 43.5 | 1236 |
| 7/7/1992 | 1992 | 7 | 7 | 37 | 60 | 92 | 76 | 44 | 1280 |
| 7/8/1992 | 1992 | 7 | 8 | 38 | 56 | 92 | 74 | 42 | 1322 |
| 7/9/1992 | 1992 | 7 | 9 | 39 | 57 | 88 | 72.5 | 40.5 | 1362.5 |
| 7/10/1992 | 1992 | 7 | 10 | 40 | 58 | 83 | 70.5 | 38.5 | 1401 |
| 7/11/1992 | 1992 | 7 | 11 | 41 | 56 | 77 | 66.5 | 34.5 | 1435.5 |
| 7/12/1992 | 1992 | 7 | 12 | 42 | 56 | 78 | 67 | 35 | 1470.5 |
| 7/13/1992 | 1992 | 7 | 13 | 43 | 49 | 82 | 65.5 | 33.5 | 1504 |
| 7/14/1992 | 1992 | 7 | 14 | 44 | 48 | 83 | 65.5 | 33.5 | 1537.5 |
| 7/15/1992 | 1992 | 7 | 15 | 45 | 47 | 83 | 65 | 33 | 1570.5 |
| 7/16/1992 | 1992 | 7 | 16 | 46 | 48 | 89 | 68.5 | 36.5 | 1607 |
| 7/17/1992 | 1992 | 7 | 17 | 47 | 45 | 85 | 65 | 33 | 1640 |
| 7/18/1992 | 1992 | 7 | 18 | 48 | 45 | 83 | 64 | 32 | 1672 |
| 7/19/1992 | 1992 | 7 | 19 | 49 | 48 | 89 | 68.5 | 36.5 | 1708.5 |
| 7/20/1992 | 1992 | 7 | 20 | 50 | 49 | 90 | 69.5 | 37.5 | 1746 |
| 7/21/1992 | 1992 | 7 | 21 | 51 | 60 | 86 | 73 | 41 | 1787 |
| 7/22/1992 | 1992 | 7 | 22 | 52 | 55 | 92 | 73.5 | 41.5 | 1828.5 |
| 7/23/1992 | 1992 | 7 | 23 | 53 | 58 | 83 | 70.5 | 38.5 | 1867 |
| 7/24/1992 | 1992 | 7 | 24 | 54 | 58 | 73 | 65.5 | 33.5 | 1900.5 |
| 7/25/1992 | 1992 | 7 | 25 | 55 | 56 | 77 | 66.5 | 34.5 | 1935 |
| 7/26/1992 | 1992 | 7 | 26 | 56 | 58 | 84 | 71 | 39 | 1974 |
| 7/27/1992 | 1992 | 7 | 27 | 57 | 54 | 89 | 71.5 | 39.5 | 2013.5 |
| 7/28/1992 | 1992 | 7 | 28 | 58 | 55 | 89 | 72 | 40 | 2053.5 |
| 7/29/1992 | 1992 | 7 | 29 | 59 | 53 | 92 | 72.5 | 40.5 | 2094 |
| 7/30/1992 | 1992 | 7 | 30 | 60 | 54 | 87 | 70.5 | 38.5 | 2132.5 |
| 7/31/1992 | 1992 | 7 | 31 | 61 | 58 | 87 | 72.5 | 40.5 | 2173 |
| 8/1/1992 | 1992 | 8 | 1 | 62 | 52 | 88 | 70 | 38 | 2211 |
| 8/2/1992 | 1992 | 8 | 2 | 63 | 58 | 92 | 75 | 43 | 2254 |
| 8/3/1992 | 1992 | 8 | 3 | 64 | 54 | 91 | 72.5 | 40.5 | 2294.5 |
| 8/4/1992 | 1992 | 8 | 4 | 65 | 51 | 90 | 70.5 | 38.5 | 2333 |
| 8/5/1992 | 1992 | 8 | 5 | 66 | 55 | 86 | 70.5 | 38.5 | 2371.5 |
| 8/6/1992 | 1992 | 8 | 6 | 67 | 54 | 86 | 70 | 38 | 2409.5 |
| 8/7/1992 | 1992 | 8 | 7 | 68 | 51 | 73 | 62 | 30 | 2439.5 |
| 8/8/1992 | 1992 | 8 | 8 | 69 | 50 | 85 | 67.5 | 35.5 | 2475 |
| 8/9/1992 | 1992 | 8 | 9 | 70 | 54 | 90 | 72 | 40 | 2515 |
| 8/10/1992 | 1992 | 8 | 10 | 71 | 52 | 92 | 72 | 40 | 2555 |
| 8/11/1992 | 1992 | 8 | 11 | 72 | 54 | 88 | 71 | 39 | 2594 |
| 8/12/1992 | 1992 | 8 | 12 | 73 | 51 | 86 | 68.5 | 36.5 | 2630.5 |
| 8/13/1992 | 1992 | 8 | 13 | 74 | 53 | 91 | 72 | 40 | 2670.5 |
| 8/14/1992 | 1992 | 8 | 14 | 75 | 58 | 90 | 74 | 42 | 2712.5 |
| 8/15/1992 | 1992 | 8 | 15 | 76 | 56 | 90 | 73 | 41 | 2753.5 |
| 8/16/1992 | 1992 | 8 | 16 | 77 | 54 | 87 | 70.5 | 38.5 | 2792 |
| 8/17/1992 | 1992 | 8 | 17 | 78 | 53 | 88 | 70.5 | 38.5 | 2830.5 |
| 8/18/1992 | 1992 | 8 | 18 | 79 | 50 | 90 | 70 | 38 | 2868.5 |
| 8/19/1992 | 1992 | 8 | 19 | 80 | 54 | 91 | 72.5 | 40.5 | 2909 |
| 8/20/1992 | 1992 | 8 | 20 | 81 | 56 | 92 | 74 | 42 | 2951 |
| 8/21/1992 | 1992 | 8 | 21 | 82 | 54 | 89 | 71.5 | 39.5 | 2990.5 |
| 8/22/1992 | 1992 | 8 | 22 | 83 | 50 | 85 | 67.5 | 35.5 | 3026 |
| 8/23/1992 | 1992 | 8 | 23 | 84 | 56 | 75 | 65.5 | 33.5 | 3059.5 |
| 8/24/1992 | 1992 | 8 | 24 | 85 | 52 | 67 | 59.5 | 27.5 | 3087 |
| 8/25/1992 | 1992 | 8 | 25 | 86 | 44 | 80 | 62 | 30 | 3117 |
| 8/26/1992 | 1992 | 8 | 26 | 87 | 50 | 82 | 66 | 34 | 3151 |
| 8/27/1992 | 1992 | 8 | 27 | 88 | 45 | 82 | 63.5 | 31.5 | 3182.5 |
| 8/28/1992 | 1992 | 8 | 28 | 89 | 41 | 87 | 64 | 32 | 3214.5 |
| 8/29/1992 | 1992 | 8 | 29 | 90 | 48 | 82 | 65 | 33 | 3247.5 |
| 8/30/1992 | 1992 | 8 | 30 | 91 | 46 | 79 | 62.5 | 30.5 | 3278 |
| 8/31/1992 | 1992 | 8 | 31 | 92 | 47 | 83 | 65 | 33 | 3311 |
| 9/1/1992 | 1992 | 9 | 1 | 93 | 46 | 82 | 64 | 32 | 3343 |
| 9/2/1992 | 1992 | 9 | 2 | 94 | 45 | 83 | 64 | 32 | 3375 |
| 9/3/1992 | 1992 | 9 | 3 | 95 | 43 | 93 | 68 | 36 | 3411 |
| 9/4/1992 | 1992 | 9 | 4 | 96 | 41 | 89 | 65 | 33 | 3444 |
| 9/5/1992 | 1992 | 9 | 5 | 97 | 42 | 83 | 62.5 | 30.5 | 3474.5 |
| 9/6/1992 | 1992 | 9 | 6 | 98 | 39 | 86 | 62.5 | 30.5 | 3505 |
| 9/7/1992 | 1992 | 9 | 7 | 99 | 44 | 88 | 66 | 34 | 3539 |
| 9/8/1992 | 1992 | 9 | 8 | 100 | 40 | 88 | 64 | 32 | 3571 |
| 9/9/1992 | 1992 | 9 | 9 | 101 | 41 | 89 | 65 | 33 | 3604 |
| 9/10/1992 | 1992 | 9 | 10 | 102 | 40 | 90 | 65 | 33 | 3637 |
| 9/11/1992 | 1992 | 9 | 11 | 103 | 55 | 90 | 72.5 | 40.5 | 3677.5 |
| 9/12/1992 | 1992 | 9 | 12 | 104 | 48 | 88 | 68 | 36 | 3713.5 |
| 9/13/1992 | 1992 | 9 | 13 | 105 | 46 | 84 | 65 | 33 | 3746.5 |
| 9/14/1992 | 1992 | 9 | 14 | 106 | 49 | 84 | 66.5 | 34.5 | 3781 |
| 9/15/1992 | 1992 | 9 | 15 | 107 | 49 | 80 | 64.5 | 32.5 | 3813.5 |
| 9/16/1992 | 1992 | 9 | 16 | 108 | 49 | 88 | 68.5 | 36.5 | 3850 |
| 9/17/1992 | 1992 | 9 | 17 | 109 | 45 | 86 | 65.5 | 33.5 | 3883.5 |
| 9/18/1992 | 1992 | 9 | 18 | 110 | 44 | 84 | 64 | 32 | 3915.5 |
| 9/19/1992 | 1992 | 9 | 19 | 111 | 54 | 66 | 60 | 28 | 3943.5 |
| 9/20/1992 | 1992 | 9 | 20 | 112 | 50 | 79 | 64.5 | 32.5 | 3976 |
| 9/21/1992 | 1992 | 9 | 21 | 113 | 42 | 82 | 62 | 30 | 4006 |
| 9/22/1992 | 1992 | 9 | 22 | 114 | 42 | 82 | 62 | 30 | 4036 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/23/1992 | 1992 | 9 | 23 | 115 | 42 | 86 | 64 | 32 | 4068 |
| 9/24/1992 | 1992 | 9 | 24 | 116 | 42 | 84 | 63 | 31 | 4099 |
| 9/25/1992 | 1992 | 9 | 25 | 117 | 43 | 84 | 63.5 | 31.5 | 4130.5 |
| 9/26/1992 | 1992 | 9 | 26 | 118 | 33 | 82 | 57.5 | 25.5 | 4156 |
| 9/27/1992 | 1992 | 9 | 27 | 119 | 33 | 85 | 59 | 27 | 4183 |
| 9/28/1992 | 1992 | 9 | 28 | 120 | 37 | 80 | 58.5 | 26.5 | 4209.5 |
| 9/29/1992 | 1992 | 9 | 29 | 121 | 45 | 81 | 63 | 31 | 4240.5 |
| 9/30/1992 | 1992 | 9 | 30 | 122 | 38 | 84 | 61 | 29 | 4269.5 |
| 10/1/1992 | 1992 | 10 | 1 | 123 | 36 | 86 | 61 | 29 | 4298.5 |
| 10/2/1992 | 1992 | 10 | 2 | 124 | 55 | 84 | 69.5 | 37.5 | 4336 |
| 10/3/1992 | 1992 | 10 | 3 | 125 | 33 | 83 | 58 | 26 | 4362 |
| 10/4/1992 | 1992 | 10 | 4 | 126 | 37 | 83 | 60 | 28 | 4390 |
| 10/5/1992 | 1992 | 10 | 5 | 127 | 35 | 80 | 57.5 | 25.5 | 4415.5 |
| 10/6/1992 | 1992 | 10 | 6 | 128 | 37 | 80 | 58.5 | 26.5 | 4442 |
| 10/7/1992 | 1992 | 10 | 7 | 129 | 38 | 75 | 56.5 | 24.5 | 4466.5 |
| 10/8/1992 | 1992 | 10 | 8 | 130 | 19 | 67 | 43 | 11 | 4477.5 |
| 10/9/1992 | 1992 | 10 | 9 | 131 | 22 | 78 | 50 | 18 | 4495.5 |
| 10/10/1992 | 1992 | 10 | 10 | 132 | 30 | 76 | 53 | 21 | 4516.5 |
| 10/11/1992 | 1992 | 10 | 11 | 133 | 28 | 79 | 53.5 | 21.5 | 4538 |
| 10/12/1992 | 1992 | 10 | 12 | 134 | 28 | 82 | 55 | 23 | 4561 |
| 10/13/1992 | 1992 | 10 | 13 | 135 | 28 | 80 | 54 | 22 | 4583 |
| 10/14/1992 | 1992 | 10 | 14 | 136 | 36 | 75 | 55.5 | 23.5 | 4606.5 |
| 10/15/1992 | 1992 | 10 | 15 | 137 | 36 | 75 | 55.5 | 23.5 | 4630 |
| 10/16/1992 | 1992 | 10 | 16 | 138 | 30 | 71 | 50.5 | 18.5 | 4648.5 |
| 10/17/1992 | 1992 | 10 | 17 | 139 | 29 | 77 | 53 | 21 | 4669.5 |
| 10/18/1992 | 1992 | 10 | 18 | 140 | 29 | 78 | 53.5 | 21.5 | 4691 |
| 10/19/1992 | 1992 | 10 | 19 | 141 | 34 | 75 | 54.5 | 22.5 | 4713.5 |
| 10/20/1992 | 1992 | 10 | 20 | 142 | 32 | 77 | 54.5 | 22.5 | 4736 |
| 10/21/1992 | 1992 | 10 | 21 | 143 | 40 | 72 | 56 | 24 | 4760 |
| 10/22/1992 | 1992 | 10 | 22 | 144 | 36 | 69 | 52.5 | 20.5 | 4780.5 |
| 10/23/1992 | 1992 | 10 | 23 | 145 | 41 | 71 | 56 | 24 | 4804.5 |
| 10/24/1992 | 1992 | 10 | 24 | 146 | 39 | 66 | 52.5 | 20.5 | 4825 |
| 10/25/1992 | 1992 | 10 | 25 | 147 | 40 | 70 | 55 | 23 | 4848 |
| 10/26/1992 | 1992 | 10 | 26 | 148 | 35 | 69 | 52 | 20 | 4868 |
| 10/27/1992 | 1992 | 10 | 27 | 149 | 33 | 73 | 53 | 21 | 4889 |
| 10/28/1992 | 1992 | 10 | 28 | 150 | 44 | 55 | 49.5 | 17.5 | 4906.5 |
| 10/29/1992 | 1992 | 10 | 29 | 151 | 41 | 58 | 49.5 | 17.5 | 4924 |
| 10/30/1992 | 1992 | 10 | 30 | 152 | 40 | 64 | 52 | 20 | 4944 |
| 10/31/1992 | 1992 | 10 | 31 | 153 | 40 | 59 | 49.5 | 17.5 | 4961.5 |
| 11/1/1992 | 1992 | 11 | 1 | 154 | 30 | 55 | 42.5 | 10.5 | 4972 |
| 11/2/1992 | 1992 | 11 | 2 | 155 | 26 | 61 | 43.5 | 11.5 | 4983.5 |
| 11/3/1992 | 1992 | 11 | 3 | 156 | 25 | 42 | 33.5 | 1.5 | 4985 |
| 11/4/1992 | 1992 | 11 | 4 | 157 | 19 | 45 | 32 | 0 | 4985 |
| 11/5/1992 | 1992 | 11 | 5 | 158 | 19 | 48 | 33.5 | 1.5 | 4986.5 |
| 11/6/1992 | 1992 | 11 | 6 | 159 | 17 | 50 | 33.5 | 1.5 | 4988 |
| 11/7/1992 | 1992 | 11 | 7 | 160 | 17 | 61 | 39 | 7 | 4995 |
| 11/8/1992 | 1992 | 11 | 8 | 161 | 20 | 65 | 42.5 | 10.5 | 5005.5 |
| 11/9/1992 | 1992 | 11 | 9 | 162 | 22 | 54 | 38 | 6 | 5011.5 |
| 11/10/1992 | 1992 | 11 | 10 | 163 | 25 | 55 | 40 | 8 | 5019.5 |
| 11/11/1992 | 1992 | 11 | 11 | 164 | 30 | 45 | 37.5 | 5.5 | 5025 |
| 11/12/1992 | 1992 | 11 | 12 | 165 | 18 | 52 | 35 | 3 | 5028 |
| 11/13/1992 | 1992 | 11 | 13 | 166 | 18 | 55 | 36.5 | 4.5 | 5032.5 |
| 11/14/1992 | 1992 | 11 | 14 | 167 | 22 | 66 | 44 | 12 | 5044.5 |
| 11/15/1992 | 1992 | 11 | 15 | 168 | 21 | 68 | 44.5 | 12.5 | 5057 |
| 11/16/1992 | 1992 | 11 | 16 | 169 | 20 | 53 | 36.5 | 4.5 | 5061.5 |
| 11/17/1992 | 1992 | 11 | 17 | 170 | 20 | 60 | 40 | 8 | 5069.5 |
| 11/18/1992 | 1992 | 11 | 18 | 171 | 16 | 56 | 36 | 4 | 5073.5 |
| 11/19/1992 | 1992 | 11 | 19 | 172 | 24 | 55 | 39.5 | 7.5 | 5081 |
| 11/20/1992 | 1992 | 11 | 20 | 173 | 32 | 44 | 38 | 6 | 5087 |
| 11/21/1992 | 1992 | 11 | 21 | 174 | 20 | 42 | 31 | -1 | 5086 |
| 11/22/1992 | 1992 | 11 | 22 | 175 | 15 | 45 | 30 | -2 | 5084 |
| 11/23/1992 | 1992 | 11 | 23 | 176 | 30 | 42 | 36 | 4 | 5088 |
| 11/24/1992 | 1992 | 11 | 24 | 177 | 11 | 38 | 24.5 | -7.5 | 5080.5 |
| 11/25/1992 | 1992 | 11 | 25 | 178 | 11 | 34 | 22.5 | -9.5 | 5071 |
| 11/26/1992 | 1992 | 11 | 26 | 179 | 12 | 38 | 25 | -7 | 5064 |
| 11/27/1992 | 1992 | 11 | 27 | 180 | 12 | 45 | 28.5 | -3.5 | 5060.5 |
| 11/28/1992 | 1992 | 11 | 28 | 181 | 7 | 49 | 28 | -4 | 5056.5 |
| 11/29/1992 | 1992 | 11 | 29 | 182 | 12 | 44 | 28 | -4 | 5052.5 |
| 11/30/1992 | 1992 | 11 | 30 | 183 | 10 | 44 | 27 | -5 | 5047.5 |
| 12/1/1992 | 1992 | 12 | 1 | 184 | 8 | 52 | 30 | -2 | 5045.5 |
| 12/2/1992 | 1992 | 12 | 2 | 185 | 10 | 53 | 31.5 | -0.5 | 5045 |
| 12/3/1992 | 1992 | 12 | 3 | 186 | 30 | 55 | 42.5 | 10.5 | 5055.5 |
| 12/4/1992 | 1992 | 12 | 4 | 187 | 30 | 38 | 34 | 2 | 5057.5 |
| 12/5/1992 | 1992 | 12 | 5 | 188 | 15 | 30 | 22.5 | -9.5 | 5048 |
| 12/6/1992 | 1992 | 12 | 6 | 189 | 2 | 35 | 18.5 | -13.5 | 5034.5 |
| 12/7/1992 | 1992 | 12 | 7 | 190 | 0 | 33 | 16.5 | -15.5 | 5019 |
| 12/8/1992 | 1992 | 12 | 8 | 191 | 14 | 36 | 25 | -7 | 5012 |
| 12/9/1992 | 1992 | 12 | 9 | 192 | 12 | 45 | 28.5 | -3.5 | 5008.5 |
| 12/10/1992 | 1992 | 12 | 10 | 193 | 13 | 43 | 28 | -4 | 5004.5 |
| 12/11/1992 | 1992 | 12 | 11 | 194 | 7 | 42 | 24.5 | -7.5 | 4997 |
| 12/12/1992 | 1992 | 12 | 12 | 195 | 16 | 39 | 27.5 | -4.5 | 4992.5 |
| 12/13/1992 | 1992 | 12 | 13 | 196 | 5 | 33 | 19 | -13 | 4979.5 |
| 12/14/1992 | 1992 | 12 | 14 | 197 | 11 | 32 | 21.5 | -10.5 | 4969 |
| 12/15/1992 | 1992 | 12 | 15 | 198 | -2 | 29 | 13.5 | -18.5 | 4950.5 |
| 12/16/1992 | 1992 | 12 | 16 | 199 | 6 | 30 | 18 | -14 | 4936.5 |
| 12/17/1992 | 1992 | 12 | 17 | 200 | -8 | 29 | 10.5 | -21.5 | 4915 |
| 12/18/1992 | 1992 | 12 | 18 | 201 | 15 | 43 | 29 | -3 | 4912 |
| 12/19/1992 | 1992 | 12 | 19 | 202 | 23 | 32 | 27.5 | -4.5 | 4907.5 |
| 12/20/1992 | 1992 | 12 | 20 | 203 | -8 | 30 | 11 | -21 | 4886.5 |
| 12/21/1992 | 1992 | 12 | 21 | 204 | -4 | 34 | 15 | -17 | 4869.5 |
| 12/22/1992 | 1992 | 12 | 22 | 205 | 0 | 40 | 20 | -12 | 4857.5 |
| 12/23/1992 | 1992 | 12 | 23 | 206 | -3 | 42 | 19.5 | -12.5 | 4845 |
| 12/24/1992 | 1992 | 12 | 24 | 207 | 1 | 39 | 20 | -12 | 4833 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/25/1992 | 1992 | 12 | 25 | 208 | 3 | 40 | 21.5 | -10.5 | 4822.5 |
| 12/26/1992 | 1992 | 12 | 26 | 209 | 8 | 42 | 25 | -7 | 4815.5 |
| 12/27/1992 | 1992 | 12 | 27 | 210 | 6 | 38 | 22 | -10 | 4805.5 |
| 12/28/1992 | 1992 | 12 | 28 | 211 | 3 | 46 | 24.5 | -7.5 | 4798 |
| 12/29/1992 | 1992 | 12 | 29 | 212 | 33 | 53 | 43 | 11 | 4809 |
| 12/30/1992 | 1992 | 12 | 30 | 213 | 33 | 54 | 43.5 | 11.5 | 4820.5 |
| 12/31/1992 | 1992 | 12 | 31 | 214 | 24 | 43 | 33.5 | 1.5 | 4822 |
| 1/1/1993 | 1993 | 1 | 1 | 215 | 29 | 42 | 35.5 | 3.5 | 4825.5 |
| 1/2/1993 | 1993 | 1 | 2 | 216 | 30 | 53 | 41.5 | 9.5 | 4835 |
| 1/3/1993 | 1993 | 1 | 3 | 217 | 7 | 44 | 25.5 | -6.5 | 4828.5 |
| 1/4/1993 | 1993 | 1 | 4 | 218 | -4 | 30 | 13 | -19 | 4809.5 |
| 1/5/1993 | 1993 | 1 | 5 | 219 | 10 | 42 | 26 | -6 | 4803.5 |
| 1/6/1993 | 1993 | 1 | 6 | 220 | 18 | 43 | 30.5 | -1.5 | 4802 |
| 1/7/1993 | 1993 | 1 | 7 | 221 | 28 | 50 | 39 | 7 | 4809 |
| 1/8/1993 | 1993 | 1 | 8 | 222 | 34 | 54 | 44 | 12 | 4821 |
| 1/9/1993 | 1993 | 1 | 9 | 223 | 29 | 45 | 37 | 5 | 4826 |
| 1/10/1993 | 1993 | 1 | 10 | 224 | 28 | 37 | 32.5 | 0.5 | 4826.5 |
| 1/11/1993 | 1993 | 1 | 11 | 225 | 30 | 43 | 36.5 | 4.5 | 4831 |
| 1/12/1993 | 1993 | 1 | 12 | 226 | 18 | 46 | 32 | 0 | 4831 |
| 1/13/1993 | 1993 | 1 | 13 | 227 | 24 | 42 | 33 | 1 | 4832 |
| 1/14/1993 | 1993 | 1 | 14 | 228 | 29 | 45 | 37 | 5 | 4837 |
| 1/15/1993 | 1993 | 1 | 15 | 229 | 25 | 48 | 36.5 | 4.5 | 4841.5 |
| 1/16/1993 | 1993 | 1 | 16 | 230 | 23 | 47 | 35 | 3 | 4844.5 |
| 1/17/1993 | 1993 | 1 | 17 | 231 | 35 | 49 | 42 | 10 | 4854.5 |
| 1/18/1993 | 1993 | 1 | 18 | 232 | 32 | 48 | 40 | 8 | 4862.5 |
| 1/19/1993 | 1993 | 1 | 19 | 233 | 28 | 43 | 35.5 | 3.5 | 4866 |
| 1/20/1993 | 1993 | 1 | 20 | 234 | 24 | 44 | 34 | 2 | 4868 |
| 1/21/1993 | 1993 | 1 | 21 | 235 | 21 | 53 | 37 | 5 | 4873 |
| 1/22/1993 | 1993 | 1 | 22 | 236 | 24 | 62 | 43 | 11 | 4884 |
| 1/23/1993 | 1993 | 1 | 23 | 237 | 30 | 55 | 42.5 | 10.5 | 4894.5 |
| 1/24/1993 | 1993 | 1 | 24 | 238 | 21 | 52 | 36.5 | 4.5 | 4899 |
| 1/25/1993 | 1993 | 1 | 25 | 239 | 15 | 49 | 32 | 0 | 4899 |
| 1/26/1993 | 1993 | 1 | 26 | 240 | 16 | 57 | 36.5 | 4.5 | 4903.5 |
| 1/27/1993 | 1993 | 1 | 27 | 241 | 20 | 62 | 41 | 9 | 4912.5 |
| 1/28/1993 | 1993 | 1 | 28 | 242 | 18 | 60 | 39 | 7 | 4919.5 |
| 1/29/1993 | 1993 | 1 | 29 | 243 | 26 | 42 | 34 | 2 | 4921.5 |
| 1/30/1993 | 1993 | 1 | 30 | 244 | 30 | 42 | 36 | 4 | 4925.5 |
| 1/31/1993 | 1993 | 1 | 31 | 245 | 29 | 47 | 38 | 6 | 4931.5 |
| 2/1/1993 | 1993 | 2 | 1 | 246 | 27 | 48 | 37.5 | 5.5 | 4937 |
| 2/2/1993 | 1993 | 2 | 2 | 247 | 17 | 50 | 33.5 | 1.5 | 4938.5 |
| 2/3/1993 | 1993 | 2 | 3 | 248 | 18 | 48 | 33 | 1 | 4939.5 |
| 2/4/1993 | 1993 | 2 | 4 | 249 | 14 | 47 | 30.5 | -1.5 | 4938 |
| 2/5/1993 | 1993 | 2 | 5 | 250 | 10 | 50 | 30 | -2 | 4936 |
| 2/6/1993 | 1993 | 2 | 6 | 251 | 12 | 56 | 34 | 2 | 4938 |
| 2/7/1993 | 1993 | 2 | 7 | 252 | 18 | 61 | 39.5 | 7.5 | 4945.5 |
| 2/8/1993 | 1993 | 2 | 8 | 253 | 22 | 55 | 38.5 | 6.5 | 4952 |
| 2/9/1993 | 1993 | 2 | 9 | 254 | 29 | 53 | 41 | 9 | 4961 |
| 2/10/1993 | 1993 | 2 | 10 | 255 | 28 | 44 | 36 | 4 | 4965 |
| 2/11/1993 | 1993 | 2 | 11 | 256 | 28 | 48 | 38 | 6 | 4971 |
| 2/12/1993 | 1993 | 2 | 12 | 257 | 21 | 52 | 36.5 | 4.5 | 4975.5 |
| 2/13/1993 | 1993 | 2 | 13 | 258 | 21 | 51 | 36 | 4 | 4979.5 |
| 2/14/1993 | 1993 | 2 | 14 | 259 | 27 | 42 | 34.5 | 2.5 | 4982 |
| 2/15/1993 | 1993 | 2 | 15 | 260 | 21 | 42 | 31.5 | -0.5 | 4981.5 |
| 2/16/1993 | 1993 | 2 | 16 | 261 | 31 | 50 | 40.5 | 8.5 | 4990 |
| 2/17/1993 | 1993 | 2 | 17 | 262 | 23 | 56 | 39.5 | 7.5 | 4997.5 |
| 2/18/1993 | 1993 | 2 | 18 | 263 | 19 | 51 | 35 | 3 | 5000.5 |
| 2/19/1993 | 1993 | 2 | 19 | 264 | 33 | 60 | 46.5 | 14.5 | 5015 |
| 2/20/1993 | 1993 | 2 | 20 | 265 | 37 | 48 | 42.5 | 10.5 | 5025.5 |
| 2/21/1993 | 1993 | 2 | 21 | 266 | 32 | 48 | 40 | 8 | 5033.5 |
| 2/22/1993 | 1993 | 2 | 22 | 267 | 28 | 51 | 39.5 | 7.5 | 5041 |
| 2/23/1993 | 1993 | 2 | 23 | 268 | 21 | 58 | 39.5 | 7.5 | 5048.5 |
| 2/24/1993 | 1993 | 2 | 24 | 269 | 25 | 44 | 34.5 | 2.5 | 5051 |
| 2/25/1993 | 1993 | 2 | 25 | 270 | 28 | 47 | 37.5 | 5.5 | 5056.5 |
| 2/26/1993 | 1993 | 2 | 26 | 271 | 19 | 57 | 38 | 6 | 5062.5 |
| 2/27/1993 | 1993 | 2 | 27 | 272 | 27 | 57 | 42 | 10 | 5072.5 |
| 2/28/1993 | 1993 | 2 | 28 | 273 | 32 | 42 | 37 | 5 | 5077.5 |
| 3/1/1993 | 1993 | 3 | 1 | 274 | 29 | 42 | 35.5 | 3.5 | 5081 |
| 3/2/1993 | 1993 | 3 | 2 | 275 | 23 | 51 | 37 | 5 | 5086 |
| 3/3/1993 | 1993 | 3 | 3 | 276 | 19 | 59 | 39 | 7 | 5093 |
| 3/4/1993 | 1993 | 3 | 4 | 277 | 17 | 54 | 35.5 | 3.5 | 5096.5 |
| 3/5/1993 | 1993 | 3 | 5 | 278 | 24 | 58 | 41 | 9 | 5105.5 |
| 3/6/1993 | 1993 | 3 | 6 | 279 | 28 | 60 | 44 | 12 | 5117.5 |
| 3/7/1993 | 1993 | 3 | 7 | 280 | 29 | 67 | 48 | 16 | 5133.5 |
| 3/8/1993 | 1993 | 3 | 8 | 281 | 18 | 70 | 44 | 12 | 5145.5 |
| 3/9/1993 | 1993 | 3 | 9 | 282 | 20 | 71 | 45.5 | 13.5 | 5159 |
| 3/10/1993 | 1993 | 3 | 10 | 283 | 28 | 62 | 45 | 13 | 5172 |
| 3/11/1993 | 1993 | 3 | 11 | 284 | 24 | 55 | 39.5 | 7.5 | 5179.5 |
| 3/12/1993 | 1993 | 3 | 12 | 285 | 26 | 51 | 38.5 | 6.5 | 5186 |
| 3/13/1993 | 1993 | 3 | 13 | 286 | 12 | 59 | 35.5 | 3.5 | 5189.5 |
| 3/14/1993 | 1993 | 3 | 14 | 287 | 18 | 58 | 38 | 6 | 5195.5 |
| 3/15/1993 | 1993 | 3 | 15 | 288 | 19 | 69 | 44 | 12 | 5207.5 |
| 3/16/1993 | 1993 | 3 | 16 | 289 | 30 | 67 | 48.5 | 16.5 | 5224 |
| 3/17/1993 | 1993 | 3 | 17 | 290 | 25 | 65 | 45 | 13 | 5237 |
| 3/18/1993 | 1993 | 3 | 18 | 291 | 30 | 65 | 47.5 | 15.5 | 5252.5 |
| 3/19/1993 | 1993 | 3 | 19 | 292 | 30 | 64 | 47 | 15 | 5267.5 |
| 3/20/1993 | 1993 | 3 | 20 | 293 | 25 | 65 | 45 | 13 | 5280.5 |
| 3/21/1993 | 1993 | 3 | 21 | 294 | 31 | 70 | 50.5 | 18.5 | 5299 |
| 3/22/1993 | 1993 | 3 | 22 | 295 | 24 | 70 | 47 | 15 | 5314 |
| 3/23/1993 | 1993 | 3 | 23 | 296 | 24 | 73 | 48.5 | 16.5 | 5330.5 |
| 3/24/1993 | 1993 | 3 | 24 | 297 | 35 | 63 | 49 | 17 | 5347.5 |
| 3/25/1993 | 1993 | 3 | 25 | 298 | 29 | 72 | 50.5 | 18.5 | 5366 |
| 3/26/1993 | 1993 | 3 | 26 | 299 | 32 | 68 | 50 | 18 | 5384 |
| 3/27/1993 | 1993 | 3 | 27 | 300 | 32 | 50 | 41 | 9 | 5393 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/28/1993 | 1993 | 3 | 28 | 301 | 31 | 60 | 45.5 | 13.5 | 5406.5 |
| 3/29/1993 | 1993 | 3 | 29 | 302 | 30 | 48 | 39 | 7 | 5413.5 |
| 3/30/1993 | 1993 | 3 | 30 | 303 | 29 | 59 | 44 | 12 | 5425.5 |
| 3/31/1993 | 1993 | 3 | 31 | 304 | 31 | 64 | 47.5 | 15.5 | 5441 |
| 4/1/1993 | 1993 | 4 | 1 | 305 | 24 | 69 | 46.5 | 14.5 | 5455.5 |
| 4/2/1993 | 1993 | 4 | 2 | 306 | 32 | 68 | 50 | 18 | 5473.5 |
| 4/3/1993 | 1993 | 4 | 3 | 307 | 30 | 63 | 46.5 | 14.5 | 5488 |
| 4/4/1993 | 1993 | 4 | 4 | 308 | 25 | 71 | 48 | 16 | 5504 |
| 4/5/1993 | 1993 | 4 | 5 | 309 | 30 | 68 | 49 | 17 | 5521 |
| 4/6/1993 | 1993 | 4 | 6 | 310 | 35 | 52 | 43.5 | 11.5 | 5532.5 |
| 4/7/1993 | 1993 | 4 | 7 | 311 | 22 | 53 | 37.5 | 5.5 | 5538 |
| 4/8/1993 | 1993 | 4 | 8 | 312 | 25 | 60 | 42.5 | 10.5 | 5548.5 |
| 4/9/1993 | 1993 | 4 | 9 | 313 | 24 | 71 | 47.5 | 15.5 | 5564 |
| 4/10/1993 | 1993 | 4 | 10 | 314 | 40 | 75 | 57.5 | 25.5 | 5589.5 |
| 4/11/1993 | 1993 | 4 | 11 | 315 | 34 | 72 | 53 | 21 | 5610.5 |
| 4/12/1993 | 1993 | 4 | 12 | 316 | 34 | 69 | 51.5 | 19.5 | 5630 |
| 4/13/1993 | 1993 | 4 | 13 | 317 | 28 | 59 | 43.5 | 11.5 | 5641.5 |
| 4/14/1993 | 1993 | 4 | 14 | 318 | 23 | 58 | 40.5 | 8.5 | 5650 |
| 4/15/1993 | 1993 | 4 | 15 | 319 | 20 | 65 | 42.5 | 10.5 | 5660.5 |
| 4/16/1993 | 1993 | 4 | 16 | 320 | 38 | 63 | 50.5 | 18.5 | 5679 |
| 4/17/1993 | 1993 | 4 | 17 | 321 | 35 | 74 | 54.5 | 22.5 | 5701.5 |
| 4/18/1993 | 1993 | 4 | 18 | 322 | 37 | 74 | 55.5 | 23.5 | 5725 |
| 4/19/1993 | 1993 | 4 | 19 | 323 | 33 | 61 | 47 | 15 | 5740 |
| 4/20/1993 | 1993 | 4 | 20 | 324 | 18 | 74 | 46 | 14 | 5754 |
| 4/21/1993 | 1993 | 4 | 21 | 325 | 24 | 72 | 48 | 16 | 5770 |
| 4/22/1993 | 1993 | 4 | 22 | 326 | 31 | 83 | 57 | 25 | 5795 |
| 4/23/1993 | 1993 | 4 | 23 | 327 | 36 | 76 | 56 | 24 | 5819 |
| 4/24/1993 | 1993 | 4 | 24 | 328 | 43 | 71 | 57 | 25 | 5844 |
| 4/25/1993 | 1993 | 4 | 25 | 329 | 38 | 75 | 56.5 | 24.5 | 5868.5 |
| 4/26/1993 | 1993 | 4 | 26 | 330 | 35 | 83 | 59 | 27 | 5895.5 |
| 4/27/1993 | 1993 | 4 | 27 | 331 | 38 | 78 | 58 | 26 | 5921.5 |
| 4/28/1993 | 1993 | 4 | 28 | 332 | 43 | 75 | 59 | 27 | 5948.5 |
| 4/29/1993 | 1993 | 4 | 29 | 333 | 31 | 77 | 54 | 22 | 5970.5 |
| 4/30/1993 | 1993 | 4 | 30 | 334 | 34 | 78 | 56 | 24 | 5994.5 |
| 5/1/1993 | 1993 | 5 | 1 | 335 | 33 | 64 | 48.5 | 16.5 | 6011 |
| 5/2/1993 | 1993 | 5 | 2 | 336 | 35 | 74 | 54.5 | 22.5 | 6033.5 |
| 5/3/1993 | 1993 | 5 | 3 | 337 | 30 | 72 | 51 | 19 | 6052.5 |
| 5/4/1993 | 1993 | 5 | 4 | 338 | 40 | 79 | 59.5 | 27.5 | 6080 |
| 5/5/1993 | 1993 | 5 | 5 | 339 | 39 | 68 | 53.5 | 21.5 | 6101.5 |
| 5/6/1993 | 1993 | 5 | 6 | 340 | 28 | 70 | 49 | 17 | 6118.5 |
| 5/7/1993 | 1993 | 5 | 7 | 341 | 38 | 69 | 53.5 | 21.5 | 6140 |
| 5/8/1993 | 1993 | 5 | 8 | 342 | 30 | 65 | 47.5 | 15.5 | 6155.5 |
| 5/9/1993 | 1993 | 5 | 9 | 343 | 28 | 68 | 48 | 16 | 6171.5 |
| 5/10/1993 | 1993 | 5 | 10 | 344 | 26 | 79 | 52.5 | 20.5 | 6192 |
| 5/11/1993 | 1993 | 5 | 11 | 345 | 31 | 81 | 56 | 24 | 6216 |
| 5/12/1993 | 1993 | 5 | 12 | 346 | 45 | 82 | 63.5 | 31.5 | 6247.5 |
| 5/13/1993 | 1993 | 5 | 13 | 347 | 44 | 80 | 62 | 30 | 6277.5 |
| 5/14/1993 | 1993 | 5 | 14 | 348 | 40 | 82 | 61 | 29 | 6306.5 |
| 5/15/1993 | 1993 | 5 | 15 | 349 | 48 | 75 | 61.5 | 29.5 | 6336 |
| 5/16/1993 | 1993 | 5 | 16 | 350 | 43 | 75 | 59 | 27 | 6363 |
| 5/17/1993 | 1993 | 5 | 17 | 351 | 43 | 75 | 59 | 27 | 6390 |
| 5/18/1993 | 1993 | 5 | 18 | 352 | 40 | 78 | 59 | 27 | 6417 |
| 5/19/1993 | 1993 | 5 | 19 | 353 | 46 | 81 | 63.5 | 31.5 | 6448.5 |
| 5/20/1993 | 1993 | 5 | 20 | 354 | 42 | 81 | 61.5 | 29.5 | 6478 |
| 5/21/1993 | 1993 | 5 | 21 | 355 | 42 | 82 | 62 | 30 | 6508 |
| 5/22/1993 | 1993 | 5 | 22 | 356 | 45 | 80 | 62.5 | 30.5 | 6538.5 |
| 5/23/1993 | 1993 | 5 | 23 | 357 | 45 | 81 | 63 | 31 | 6569.5 |
| 5/24/1993 | 1993 | 5 | 24 | 358 | 46 | 82 | 64 | 32 | 6601.5 |
| 5/25/1993 | 1993 | 5 | 25 | 359 | 48 | 79 | 63.5 | 31.5 | 6633 |
| 5/26/1993 | 1993 | 5 | 26 | 360 | 49 | 85 | 67 | 35 | 6668 |
| 5/27/1993 | 1993 | 5 | 27 | 361 | 51 | 83 | 67 | 35 | 6703 |
| 5/28/1993 | 1993 | 5 | 28 | 362 | 53 | 75 | 64 | 32 | 6735 |
| 5/29/1993 | 1993 | 5 | 29 | 363 | 48 | 84 | 66 | 34 | 6769 |
| 5/30/1993 | 1993 | 5 | 30 | 364 | 44 | 88 | 66 | 34 | 6803 |
| 5/31/1993 | 1993 | 5 | 31 | 365 | 41 | 91 | 66 | 34 | 6837 |
| 6/1/1993 | 1993 | 6 | 1 | 1 | 43 | 86 | 64.5 | 32.5 | 32.5 |
| 6/2/1993 | 1993 | 6 | 2 | 2 | 44 | 84 | 64 | 32 | 64.5 |
| 6/3/1993 | 1993 | 6 | 3 | 3 | 44 | 79 | 61.5 | 29.5 | 94 |
| 6/4/1993 | 1993 | 6 | 4 | 4 | 48 | 84 | 66 | 34 | 128 |
| 6/5/1993 | 1993 | 6 | 5 | 5 | 42 | 80 | 61 | 29 | 157 |
| 6/6/1993 | 1993 | 6 | 6 | 6 | 42 | 85 | 63.5 | 31.5 | 188.5 |
| 6/7/1993 | 1993 | 6 | 7 | 7 | 37 | 72 | 54.5 | 22.5 | 211 |
| 6/8/1993 | 1993 | 6 | 8 | 8 | 34 | 75 | 54.5 | 22.5 | 233.5 |
| 6/9/1993 | 1993 | 6 | 9 | 9 | 40 | 72 | 56 | 24 | 257.5 |
| 6/10/1993 | 1993 | 6 | 10 | 10 | 36 | 79 | 57.5 | 25.5 | 283 |
| 6/11/1993 | 1993 | 6 | 11 | 11 | 41 | 89 | 65 | 33 | 316 |
| 6/12/1993 | 1993 | 6 | 12 | 12 | 42 | 91 | 66.5 | 34.5 | 350.5 |
| 6/13/1993 | 1993 | 6 | 13 | 13 | 42 | 95 | 68.5 | 36.5 | 387 |
| 6/14/1993 | 1993 | 6 | 14 | 14 | 39 | 95 | 67 | 35 | 422 |
| 6/15/1993 | 1993 | 6 | 15 | 15 | 56 | 86 | 71 | 39 | 461 |
| 6/16/1993 | 1993 | 6 | 16 | 16 | 55 | 88 | 71.5 | 39.5 | 500.5 |
| 6/17/1993 | 1993 | 6 | 17 | 17 | 47 | 87 | 67 | 35 | 535.5 |
| 6/18/1993 | 1993 | 6 | 18 | 18 | 45 | 86 | 65.5 | 33.5 | 569 |
| 6/19/1993 | 1993 | 6 | 19 | 19 | 41 | 90 | 65.5 | 33.5 | 602.5 |
| 6/20/1993 | 1993 | 6 | 20 | 20 | 54 | 81 | 67.5 | 35.5 | 638 |
| 6/21/1993 | 1993 | 6 | 21 | 21 | 55 | 80 | 67.5 | 35.5 | 673.5 |
| 6/22/1993 | 1993 | 6 | 22 | 22 | 42 | 92 | 67 | 35 | 708.5 |
| 6/23/1993 | 1993 | 6 | 23 | 23 | 45 | 92 | 68.5 | 36.5 | 745 |
| 6/24/1993 | 1993 | 6 | 24 | 24 | 37 | 92 | 64.5 | 32.5 | 777.5 |
| 6/25/1993 | 1993 | 6 | 25 | 25 | 39 | 93 | 66 | 34 | 811.5 |
| 6/26/1993 | 1993 | 6 | 26 | 26 | 44 | 95 | 69.5 | 37.5 | 849 |
| 6/27/1993 | 1993 | 6 | 27 | 27 | 46 | 98 | 72 | 40 | 889 |
| 6/28/1993 | 1993 | 6 | 28 | 28 | 50 | 93 | 71.5 | 39.5 | 928.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/29/1993 | 1993 | 6 | 29 | 29 | 52 | 97 | 74.5 | 42.5 | 971 |
| 6/30/1993 | 1993 | 6 | 30 | 30 | 45 | 94 | 69.5 | 37.5 | 1008.5 |
| 7/1/1993 | 1993 | 7 | 1 | 31 | 45 | 98 | 71.5 | 39.5 | 1048 |
| 7/2/1993 | 1993 | 7 | 2 | 32 | 46 | 95 | 70.5 | 38.5 | 1086.5 |
| 7/3/1993 | 1993 | 7 | 3 | 33 | 45 | 98 | 71.5 | 39.5 | 1126 |
| 7/4/1993 | 1993 | 7 | 4 | 34 | 50 | 89 | 69.5 | 37.5 | 1163.5 |
| 7/5/1993 | 1993 | 7 | 5 | 35 | 55 | 91 | 73 | 41 | 1204.5 |
| 7/6/1993 | 1993 | 7 | 6 | 36 | 50 | 94 | 72 | 40 | 1244.5 |
| 7/7/1993 | 1993 | 7 | 7 | 37 | 50 | 97 | 73.5 | 41.5 | 1286 |
| 7/8/1993 | 1993 | 7 | 8 | 38 | 48 | 96 | 72 | 40 | 1326 |
| 7/9/1993 | 1993 | 7 | 9 | 39 | 56 | 96 | 76 | 44 | 1370 |
| 7/10/1993 | 1993 | 7 | 10 | 40 | 55 | 91 | 73 | 41 | 1411 |
| 7/11/1993 | 1993 | 7 | 11 | 41 | 50 | 91 | 70.5 | 38.5 | 1449.5 |
| 7/12/1993 | 1993 | 7 | 12 | 42 | 54 | 89 | 71.5 | 39.5 | 1489 |
| 7/13/1993 | 1993 | 7 | 13 | 43 | 56 | 88 | 72 | 40 | 1529 |
| 7/14/1993 | 1993 | 7 | 14 | 44 | 50 | 89 | 69.5 | 37.5 | 1566.5 |
| 7/15/1993 | 1993 | 7 | 15 | 45 | 40 | 87 | 63.5 | 31.5 | 1598 |
| 7/16/1993 | 1993 | 7 | 16 | 46 | 55 | 88 | 71.5 | 39.5 | 1637.5 |
| 7/17/1993 | 1993 | 7 | 17 | 47 | 55 | 87 | 71 | 39 | 1676.5 |
| 7/18/1993 | 1993 | 7 | 18 | 48 | 52 | 90 | 71 | 39 | 1715.5 |
| 7/19/1993 | 1993 | 7 | 19 | 49 | 51 | 92 | 71.5 | 39.5 | 1755 |
| 7/20/1993 | 1993 | 7 | 20 | 50 | 55 | 92 | 73.5 | 41.5 | 1796.5 |
| 7/21/1993 | 1993 | 7 | 21 | 51 | 54 | 91 | 72.5 | 40.5 | 1837 |
| 7/22/1993 | 1993 | 7 | 22 | 52 | 47 | 90 | 68.5 | 36.5 | 1873.5 |
| 7/23/1993 | 1993 | 7 | 23 | 53 | 48 | 92 | 70 | 38 | 1911.5 |
| 7/24/1993 | 1993 | 7 | 24 | 54 | 54 | 89 | 71.5 | 39.5 | 1951 |
| 7/25/1993 | 1993 | 7 | 25 | 55 | 54 | 94 | 74 | 42 | 1993 |
| 7/26/1993 | 1993 | 7 | 26 | 56 | 48 | 95 | 71.5 | 39.5 | 2032.5 |
| 7/27/1993 | 1993 | 7 | 27 | 57 | 50 | 93 | 71.5 | 39.5 | 2072 |
| 7/28/1993 | 1993 | 7 | 28 | 58 | 52 | 95 | 73.5 | 41.5 | 2113.5 |
| 7/29/1993 | 1993 | 7 | 29 | 59 | 53 | 95 | 74 | 42 | 2155.5 |
| 7/30/1993 | 1993 | 7 | 30 | 60 | 52 | 89 | 70.5 | 38.5 | 2194 |
| 7/31/1993 | 1993 | 7 | 31 | 61 | 55 | 97 | 76 | 44 | 2238 |
| 8/1/1993 | 1993 | 8 | 1 | 62 | 53 | 91 | 72 | 40 | 2278 |
| 8/2/1993 | 1993 | 8 | 2 | 63 | 55 | 96 | 75.5 | 43.5 | 2321.5 |
| 8/3/1993 | 1993 | 8 | 3 | 64 | 53 | 93 | 73 | 41 | 2362.5 |
| 8/4/1993 | 1993 | 8 | 4 | 65 | 58 | 84 | 71 | 39 | 2401.5 |
| 8/5/1993 | 1993 | 8 | 5 | 66 | 57 | 84 | 70.5 | 38.5 | 2440 |
| 8/6/1993 | 1993 | 8 | 6 | 67 | 56 | 91 | 73.5 | 41.5 | 2481.5 |
| 8/7/1993 | 1993 | 8 | 7 | 68 | 58 | 84 | 71 | 39 | 2520.5 |
| 8/8/1993 | 1993 | 8 | 8 | 69 | 50 | 80 | 65 | 33 | 2553.5 |
| 8/9/1993 | 1993 | 8 | 9 | 70 | 54 | 87 | 70.5 | 38.5 | 2592 |
| 8/10/1993 | 1993 | 8 | 10 | 71 | 57 | 86 | 71.5 | 39.5 | 2631.5 |
| 8/11/1993 | 1993 | 8 | 11 | 72 | 52 | 95 | 73.5 | 41.5 | 2673 |
| 8/12/1993 | 1993 | 8 | 12 | 73 | 50 | 91 | 70.5 | 38.5 | 2711.5 |
| 8/13/1993 | 1993 | 8 | 13 | 74 | 51 | 81 | 66 | 34 | 2745.5 |
| 8/14/1993 | 1993 | 8 | 14 | 75 | 51 | 81 | 66 | 34 | 2779.5 |
| 8/15/1993 | 1993 | 8 | 15 | 76 | 50 | 84 | 67 | 35 | 2814.5 |
| 8/16/1993 | 1993 | 8 | 16 | 77 | 50 | 82 | 66 | 34 | 2848.5 |
| 8/17/1993 | 1993 | 8 | 17 | 78 | 56 | 78 | 67 | 35 | 2883.5 |
| 8/18/1993 | 1993 | 8 | 18 | 79 | 17 | 84 | 50.5 | 18.5 | 2902 |
| 8/19/1993 | 1993 | 8 | 19 | 80 | 54 | 83 | 68.5 | 36.5 | 2938.5 |
| 8/20/1993 | 1993 | 8 | 20 | 81 | 56 | 76 | 66 | 34 | 2972.5 |
| 8/21/1993 | 1993 | 8 | 21 | 82 | 54 | 82 | 68 | 36 | 3008.5 |
| 8/22/1993 | 1993 | 8 | 22 | 83 | 51 | 83 | 67 | 35 | 3043.5 |
| 8/23/1993 | 1993 | 8 | 23 | 84 | 50 | 84 | 67 | 35 | 3078.5 |
| 8/24/1993 | 1993 | 8 | 24 | 85 | 46 | 90 | 68 | 36 | 3114.5 |
| 8/25/1993 | 1993 | 8 | 25 | 86 | 50 | 86 | 68 | 36 | 3150.5 |
| 8/26/1993 | 1993 | 8 | 26 | 87 | 53 | 71 | 62 | 30 | 3180.5 |
| 8/27/1993 | 1993 | 8 | 27 | 88 | 53 | 70 | 61.5 | 29.5 | 3210 |
| 8/28/1993 | 1993 | 8 | 28 | 89 | 54 | 71 | 62.5 | 30.5 | 3240.5 |
| 8/29/1993 | 1993 | 8 | 29 | 90 | 52 | 76 | 64 | 32 | 3272.5 |
| 8/30/1993 | 1993 | 8 | 30 | 91 | 49 | 75 | 62 | 30 | 3302.5 |
| 8/31/1993 | 1993 | 8 | 31 | 92 | 50 | 70 | 60 | 28 | 3330.5 |
| 9/1/1993 | 1993 | 9 | 1 | 93 | 50 | 83 | 66.5 | 34.5 | 3365 |
| 9/2/1993 | 1993 | 9 | 2 | 94 | 48 | 87 | 67.5 | 35.5 | 3400.5 |
| 9/3/1993 | 1993 | 9 | 3 | 95 | 48 | 86 | 67 | 35 | 3435.5 |
| 9/4/1993 | 1993 | 9 | 4 | 96 | 43 | 88 | 65.5 | 33.5 | 3469 |
| 9/5/1993 | 1993 | 9 | 5 | 97 | 52 | 82 | 67 | 35 | 3504 |
| 9/6/1993 | 1993 | 9 | 6 | 98 | 51 | 81 | 66 | 34 | 3538 |
| 9/7/1993 | 1993 | 9 | 7 | 99 | 48 | 80 | 64 | 32 | 3570 |
| 9/8/1993 | 1993 | 9 | 8 | 100 | 42 | 84 | 63 | 31 | 3601 |
| 9/9/1993 | 1993 | 9 | 9 | 101 | 50 | 86 | 68 | 36 | 3637 |
| 9/10/1993 | 1993 | 9 | 10 | 102 | 45 | 86 | 65.5 | 33.5 | 3670.5 |
| 9/11/1993 | 1993 | 9 | 11 | 103 | 48 | 84 | 66 | 34 | 3704.5 |
| 9/12/1993 | 1993 | 9 | 12 | 104 | 48 | 82 | 65 | 33 | 3737.5 |
| 9/13/1993 | 1993 | 9 | 13 | 105 | 44 | 69 | 56.5 | 24.5 | 3762 |
| 9/14/1993 | 1993 | 9 | 14 | 106 | 38 | 73 | 55.5 | 23.5 | 3785.5 |
| 9/15/1993 | 1993 | 9 | 15 | 107 | 39 | 73 | 56 | 24 | 3809.5 |
| 9/16/1993 | 1993 | 9 | 16 | 108 | 41 | 81 | 61 | 29 | 3838.5 |
| 9/17/1993 | 1993 | 9 | 17 | 109 | 40 | 81 | 60.5 | 28.5 | 3867 |
| 9/18/1993 | 1993 | 9 | 18 | 110 | 40 | 81 | 60.5 | 28.5 | 3895.5 |
| 9/19/1993 | 1993 | 9 | 19 | 111 | 41 | 82 | 61.5 | 29.5 | 3925 |
| 9/20/1993 | 1993 | 9 | 20 | 112 | 37 | 81 | 59 | 27 | 3952 |
| 9/21/1993 | 1993 | 9 | 21 | 113 | 38 | 89 | 63.5 | 31.5 | 3983.5 |
| 9/22/1993 | 1993 | 9 | 22 | 114 | 44 | 88 | 66 | 34 | 4017.5 |
| 9/23/1993 | 1993 | 9 | 23 | 115 | 47 | 89 | 68 | 36 | 4053.5 |
| 9/24/1993 | 1993 | 9 | 24 | 116 | 48 | 89 | 68.5 | 36.5 | 4090 |
| 9/25/1993 | 1993 | 9 | 25 | 117 | 48 | 89 | 68.5 | 36.5 | 4126.5 |
| 9/26/1993 | 1993 | 9 | 26 | 118 | 46 | 83 | 64.5 | 32.5 | 4159 |
| 9/27/1993 | 1993 | 9 | 27 | 119 | 35 | 81 | 58 | 26 | 4185 |
| 9/28/1993 | 1993 | 9 | 28 | 120 | 31 | 81 | 56 | 24 | 4209 |
| 9/29/1993 | 1993 | 9 | 29 | 121 | 31 | 82 | 56.5 | 24.5 | 4233.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/30/1993 | 1993 | 9 | 30 | 122 | 38 | 84 | 61 | 29 | 4262.5 |
| 10/1/1993 | 1993 | 10 | 1 | 123 | 38 | 84 | 61 | 29 | 4291.5 |
| 10/2/1993 | 1993 | 10 | 2 | 124 | 32 | 84 | 58 | 26 | 4317.5 |
| 10/3/1993 | 1993 | 10 | 3 | 125 | 39 | 87 | 63 | 31 | 4348.5 |
| 10/4/1993 | 1993 | 10 | 4 | 126 | 36 | 85 | 60.5 | 28.5 | 4377 |
| 10/5/1993 | 1993 | 10 | 5 | 127 | 39 | 83 | 61 | 29 | 4406 |
| 10/6/1993 | 1993 | 10 | 6 | 128 | 37 | 84 | 60.5 | 28.5 | 4434.5 |
| 10/7/1993 | 1993 | 10 | 7 | 129 | 41 | 80 | 60.5 | 28.5 | 4463 |
| 10/8/1993 | 1993 | 10 | 8 | 130 | 44 | 73 | 58.5 | 26.5 | 4489.5 |
| 10/9/1993 | 1993 | 10 | 9 | 131 | 44 | 73 | 58.5 | 26.5 | 4516 |
| 10/10/1993 | 1993 | 10 | 10 | 132 | 33 | 77 | 55 | 23 | 4539 |
| 10/11/1993 | 1993 | 10 | 11 | 133 | 44 | 79 | 61.5 | 29.5 | 4568.5 |
| 10/12/1993 | 1993 | 10 | 12 | 134 | 30 | 71 | 50.5 | 18.5 | 4587 |
| 10/13/1993 | 1993 | 10 | 13 | 135 | 30 | 73 | 51.5 | 19.5 | 4606.5 |
| 10/14/1993 | 1993 | 10 | 14 | 136 | 33 | 75 | 54 | 22 | 4628.5 |
| 10/15/1993 | 1993 | 10 | 15 | 137 | 35 | 65 | 50 | 18 | 4646.5 |
| 10/16/1993 | 1993 | 10 | 16 | 138 | 35 | 73 | 54 | 22 | 4668.5 |
| 10/17/1993 | 1993 | 10 | 17 | 139 | 35 | 73 | 54 | 22 | 4690.5 |
| 10/18/1993 | 1993 | 10 | 18 | 140 | 30 | 61 | 45.5 | 13.5 | 4704 |
| 10/19/1993 | 1993 | 10 | 19 | 141 | 34 | 64 | 49 | 17 | 4721 |
| 10/20/1993 | 1993 | 10 | 20 | 142 | 28 | 59 | 43.5 | 11.5 | 4732.5 |
| 10/21/1993 | 1993 | 10 | 21 | 143 | 24 | 65 | 44.5 | 12.5 | 4745 |
| 10/22/1993 | 1993 | 10 | 22 | 144 | 26 | 67 | 46.5 | 14.5 | 4759.5 |
| 10/23/1993 | 1993 | 10 | 23 | 145 | 27 | 67 | 47 | 15 | 4774.5 |
| 10/24/1993 | 1993 | 10 | 24 | 146 | 24 | 74 | 49 | 17 | 4791.5 |
| 10/25/1993 | 1993 | 10 | 25 | 147 | 24 | 73 | 48.5 | 16.5 | 4808 |
| 10/26/1993 | 1993 | 10 | 26 | 148 | 36 | 68 | 52 | 20 | 4828 |
| 10/27/1993 | 1993 | 10 | 27 | 149 | 30 | 56 | 43 | 11 | 4839 |
| 10/28/1993 | 1993 | 10 | 28 | 150 | 17 | 57 | 37 | 5 | 4844 |
| 10/29/1993 | 1993 | 10 | 29 | 151 | 36 | 67 | 51.5 | 19.5 | 4863.5 |
| 10/30/1993 | 1993 | 10 | 30 | 152 | 15 | 52 | 33.5 | 1.5 | 4865 |
| 10/31/1993 | 1993 | 10 | 31 | 153 | 11 | 53 | 32 | 0 | 4865 |
| 11/1/1993 | 1993 | 11 | 1 | 154 | 26 | 64 | 45 | 13 | 4878 |
| 11/2/1993 | 1993 | 11 | 2 | 155 | 22 | 66 | 44 | 12 | 4890 |
| 11/3/1993 | 1993 | 11 | 3 | 156 | 20 | 59 | 39.5 | 7.5 | 4897.5 |
| 11/4/1993 | 1993 | 11 | 4 | 157 | 29 | 68 | 48.5 | 16.5 | 4914 |
| 11/5/1993 | 1993 | 11 | 5 | 158 | 22 | 65 | 43.5 | 11.5 | 4925.5 |
| 11/6/1993 | 1993 | 11 | 6 | 159 | 12 | 63 | 37.5 | 5.5 | 4931 |
| 11/7/1993 | 1993 | 11 | 7 | 160 | 10 | 57 | 33.5 | 1.5 | 4932.5 |
| 11/8/1993 | 1993 | 11 | 8 | 161 | 16 | 65 | 40.5 | 8.5 | 4941 |
| 11/9/1993 | 1993 | 11 | 9 | 162 | 13 | 67 | 40 | 8 | 4949 |
| 11/10/1993 | 1993 | 11 | 10 | 163 | 14 | 63 | 38.5 | 6.5 | 4955.5 |
| 11/11/1993 | 1993 | 11 | 11 | 164 | 37 | 65 | 51 | 19 | 4974.5 |
| 11/12/1993 | 1993 | 11 | 12 | 165 | 35 | 64 | 49.5 | 17.5 | 4992 |
| 11/13/1993 | 1993 | 11 | 13 | 166 | 27 | 53 | 40 | 8 | 5000 |
| 11/15/1993 | 1993 | 11 | 15 | 167 | 27 | 50 | 38.5 | 6.5 | 5006.5 |
| 11/16/1993 | 1993 | 11 | 16 | 168 | 22 | 37 | 29.5 | -2.5 | 5004 |
| 11/17/1993 | 1993 | 11 | 17 | 169 | 20 | 52 | 36 | 4 | 5008 |
| 11/18/1993 | 1993 | 11 | 18 | 170 | 26 | 58 | 42 | 10 | 5018 |
| 11/19/1993 | 1993 | 11 | 19 | 171 | 21 | 62 | 41.5 | 9.5 | 5027.5 |
| 11/20/1993 | 1993 | 11 | 20 | 172 | 12 | 51 | 31.5 | -0.5 | 5027 |
| 11/21/1993 | 1993 | 11 | 21 | 173 | 12 | 55 | 33.5 | 1.5 | 5028.5 |
| 11/22/1993 | 1993 | 11 | 22 | 174 | 29 | 56 | 42.5 | 10.5 | 5039 |
| 11/23/1993 | 1993 | 11 | 23 | 175 | 44 | 66 | 55 | 23 | 5062 |
| 11/24/1993 | 1993 | 11 | 24 | 176 | 35 | 57 | 46 | 14 | 5076 |
| 11/25/1993 | 1993 | 11 | 25 | 177 | 9 | 52 | 30.5 | -1.5 | 5074.5 |
| 11/26/1993 | 1993 | 11 | 26 | 178 | 2 | 35 | 18.5 | -13.5 | 5061 |
| 11/27/1993 | 1993 | 11 | 27 | 179 | 9 | 40 | 24.5 | -7.5 | 5053.5 |
| 11/28/1993 | 1993 | 11 | 28 | 180 | 13 | 52 | 32.5 | 0.5 | 5054 |
| 11/29/1993 | 1993 | 11 | 29 | 181 | 13 | 54 | 33.5 | 1.5 | 5055.5 |
| 11/30/1993 | 1993 | 11 | 30 | 182 | 16 | 61 | 38.5 | 6.5 | 5062 |
| 12/1/1993 | 1993 | 12 | 1 | 183 | 16 | 60 | 38 | 6 | 5068 |
| 12/2/1993 | 1993 | 12 | 2 | 184 | 11 | 52 | 31.5 | -0.5 | 5067.5 |
| 12/3/1993 | 1993 | 12 | 3 | 185 | 19 | 57 | 38 | 6 | 5073.5 |
| 12/4/1993 | 1993 | 12 | 4 | 186 | 8 | 57 | 32.5 | 0.5 | 5074 |
| 12/5/1993 | 1993 | 12 | 5 | 187 | 12 | 60 | 36 | 4 | 5078 |
| 12/6/1993 | 1993 | 12 | 6 | 188 | 12 | 58 | 35 | 3 | 5081 |
| 12/7/1993 | 1993 | 12 | 7 | 189 | 15 | 62 | 38.5 | 6.5 | 5087.5 |
| 12/8/1993 | 1993 | 12 | 8 | 190 | 10 | 62 | 36 | 4 | 5091.5 |
| 12/9/1993 | 1993 | 12 | 9 | 191 | 16 | 54 | 35 | 3 | 5094.5 |
| 12/10/1993 | 1993 | 12 | 10 | 192 | 13 | 63 | 38 | 6 | 5100.5 |
| 12/11/1993 | 1993 | 12 | 11 | 193 | 21 | 62 | 41.5 | 9.5 | 5110 |
| 12/12/1993 | 1993 | 12 | 12 | 194 | 36 | 61 | 48.5 | 16.5 | 5126.5 |
| 12/13/1993 | 1993 | 12 | 13 | 195 | 16 | 42 | 29 | -3 | 5123.5 |
| 12/14/1993 | 1993 | 12 | 14 | 196 | 10 | 46 | 28 | -4 | 5119.5 |
| 12/15/1993 | 1993 | 12 | 15 | 197 | 31 | 51 | 41 | 9 | 5128.5 |
| 12/16/1993 | 1993 | 12 | 16 | 198 | 23 | 44 | 33.5 | 1.5 | 5130 |
| 12/17/1993 | 1993 | 12 | 17 | 199 | 6 | 37 | 21.5 | -10.5 | 5119.5 |
| 12/18/1993 | 1993 | 12 | 18 | 200 | 10 | 47 | 28.5 | -3.5 | 5116 |
| 12/19/1993 | 1993 | 12 | 19 | 201 | 12 | 50 | 31 | -1 | 5115 |
| 12/20/1993 | 1993 | 12 | 20 | 202 | 17 | 49 | 33 | 1 | 5116 |
| 12/21/1993 | 1993 | 12 | 21 | 203 | 4 | 40 | 22 | -10 | 5106 |
| 12/22/1993 | 1993 | 12 | 22 | 204 | 4 | 44 | 24 | -8 | 5098 |
| 12/23/1993 | 1993 | 12 | 23 | 205 | 1 | 32 | 16.5 | -15.5 | 5082.5 |
| 12/24/1993 | 1993 | 12 | 24 | 206 | 9 | 34 | 21.5 | -10.5 | 5072 |
| 12/25/1993 | 1993 | 12 | 25 | 207 | 9 | 34 | 21.5 | -10.5 | 5061.5 |
| 12/26/1993 | 1993 | 12 | 26 | 208 | 4 | 57 | 30.5 | -1.5 | 5060 |
| 12/27/1993 | 1993 | 12 | 27 | 209 | 25 | 57 | 41 | 9 | 5069 |
| 12/28/1993 | 1993 | 12 | 28 | 210 | 30 | 51 | 40.5 | 8.5 | 5077.5 |
| 12/29/1993 | 1993 | 12 | 29 | 211 | 15 | 49 | 32 | 0 | 5077.5 |
| 12/30/1993 | 1993 | 12 | 30 | 212 | 7 | 50 | 28.5 | -3.5 | 5074 |
| 12/31/1993 | 1993 | 12 | 31 | 213 | 12 | 55 | 33.5 | 1.5 | 5075.5 |
| 1/1/1994 | 1994 | 1 | 1 | 214 | 6 | 57 | 31.5 | -0.5 | 5075 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/2/1994 | 1994 | 1 | 2 | 215 | 21 | 55 | 38 | 6 | 5081 |
| 1/3/1994 | 1994 | 1 | 3 | 216 | 11 | 52 | 31.5 | -0.5 | 5080.5 |
| 1/4/1994 | 1994 | 1 | 4 | 217 | 14 | 61 | 37.5 | 5.5 | 5086 |
| 1/5/1994 | 1994 | 1 | 5 | 218 | 44 | 66 | 55 | 23 | 5109 |
| 1/6/1994 | 1994 | 1 | 6 | 219 | 23 | 66 | 44.5 | 12.5 | 5121.5 |
| 1/7/1994 | 1994 | 1 | 7 | 220 | 4 | 37 | 20.5 | -11.5 | 5110 |
| 1/8/1994 | 1994 | 1 | 8 | 221 | 2 | 44 | 23 | -9 | 5101 |
| 1/9/1994 | 1994 | 1 | 9 | 222 | 4 | 50 | 27 | -5 | 5096 |
| 1/10/1994 | 1994 | 1 | 10 | 223 | 9 | 46 | 27.5 | -4.5 | 5091.5 |
| 1/11/1994 | 1994 | 1 | 11 | 224 | 3 | 44 | 23.5 | -8.5 | 5083 |
| 1/12/1994 | 1994 | 1 | 12 | 225 | 9 | 53 | 31 | -1 | 5082 |
| 1/13/1994 | 1994 | 1 | 13 | 226 | 7 | 46 | 26.5 | -5.5 | 5076.5 |
| 1/14/1994 | 1994 | 1 | 14 | 227 | 9 | 54 | 31.5 | -0.5 | 5076 |
| 1/15/1994 | 1994 | 1 | 15 | 228 | 15 | 57 | 36 | 4 | 5080 |
| 1/16/1994 | 1994 | 1 | 16 | 229 | 9 | 49 | 29 | -3 | 5077 |
| 1/17/1994 | 1994 | 1 | 17 | 230 | 9 | 49 | 29 | -3 | 5074 |
| 1/18/1994 | 1994 | 1 | 18 | 231 | 9 | 56 | 32.5 | 0.5 | 5074.5 |
| 1/19/1994 | 1994 | 1 | 19 | 232 | 7 | 56 | 31.5 | -0.5 | 5074 |
| 1/20/1994 | 1994 | 1 | 20 | 233 | 8 | 63 | 35.5 | 3.5 | 5077.5 |
| 1/21/1994 | 1994 | 1 | 21 | 234 | 5 | 63 | 34 | 2 | 5079.5 |
| 1/22/1994 | 1994 | 1 | 22 | 235 | 5 | 60 | 32.5 | 0.5 | 5080 |
| 1/23/1994 | 1994 | 1 | 23 | 236 | 10 | 62 | 36 | 4 | 5084 |
| 1/24/1994 | 1994 | 1 | 24 | 237 | 16 | 51 | 33.5 | 1.5 | 5085.5 |
| 1/25/1994 | 1994 | 1 | 25 | 238 | 10 | 62 | 36 | 4 | 5089.5 |
| 1/26/1994 | 1994 | 1 | 26 | 239 | 25 | 59 | 42 | 10 | 5099.5 |
| 1/27/1994 | 1994 | 1 | 27 | 240 | 23 | 59 | 41 | 9 | 5108.5 |
| 1/28/1994 | 1994 | 1 | 28 | 241 | 22 | 42 | 32 | 0 | 5108.5 |
| 1/29/1994 | 1994 | 1 | 29 | 242 | 22 | 28 | 25 | -7 | 5101.5 |
| 1/30/1994 | 1994 | 1 | 30 | 243 | 14 | 42 | 28 | -4 | 5097.5 |
| 1/31/1994 | 1994 | 1 | 31 | 244 | 0 | 36 | 18 | -14 | 5083.5 |
| 2/1/1994 | 1994 | 2 | 1 | 245 | -3 | 28 | 12.5 | -19.5 | 5064 |
| 2/2/1994 | 1994 | 2 | 2 | 246 | -1 | 36 | 17.5 | -14.5 | 5049.5 |
| 2/3/1994 | 1994 | 2 | 3 | 247 | 10 | 41 | 25.5 | -6.5 | 5043 |
| 2/4/1994 | 1994 | 2 | 4 | 248 | 20 | 55 | 37.5 | 5.5 | 5048.5 |
| 2/5/1994 | 1994 | 2 | 5 | 249 | 28 | 52 | 40 | 8 | 5056.5 |
| 2/6/1994 | 1994 | 2 | 6 | 250 | 9 | 44 | 26.5 | -5.5 | 5051 |
| 2/7/1994 | 1994 | 2 | 7 | 251 | 16 | 57 | 36.5 | 4.5 | 5055.5 |
| 2/8/1994 | 1994 | 2 | 8 | 252 | 36 | 54 | 45 | 13 | 5068.5 |
| 2/9/1994 | 1994 | 2 | 9 | 253 | 21 | 46 | 33.5 | 1.5 | 5070 |
| 2/10/1994 | 1994 | 2 | 10 | 254 | 10 | 50 | 30 | -2 | 5068 |
| 2/11/1994 | 1994 | 2 | 11 | 255 | 24 | 58 | 41 | 9 | 5077 |
| 2/12/1994 | 1994 | 2 | 12 | 256 | 13 | 52 | 32.5 | 0.5 | 5077.5 |
| 2/13/1994 | 1994 | 2 | 13 | 257 | -2 | 40 | 19 | -13 | 5064.5 |
| 2/14/1994 | 1994 | 2 | 14 | 258 | 0 | 44 | 22 | -10 | 5054.5 |
| 2/15/1994 | 1994 | 2 | 15 | 259 | 7 | 57 | 32 | 0 | 5054.5 |
| 2/16/1994 | 1994 | 2 | 16 | 260 | 11 | 60 | 35.5 | 3.5 | 5058 |
| 2/17/1994 | 1994 | 2 | 17 | 261 | 26 | 66 | 46 | 14 | 5072 |
| 2/18/1994 | 1994 | 2 | 18 | 262 | 35 | 67 | 51 | 19 | 5091 |
| 2/19/1994 | 1994 | 2 | 19 | 263 | 8 | 54 | 31 | -1 | 5090 |
| 2/20/1994 | 1994 | 2 | 20 | 264 | -3 | 50 | 23.5 | -8.5 | 5081.5 |
| 2/21/1994 | 1994 | 2 | 21 | 265 | 3 | 41 | 22 | -10 | 5071.5 |
| 2/22/1994 | 1994 | 2 | 22 | 266 | 15 | 51 | 33 | 1 | 5072.5 |
| 2/23/1994 | 1994 | 2 | 23 | 267 | 6 | 41 | 23.5 | -8.5 | 5064 |
| 2/24/1994 | 1994 | 2 | 24 | 268 | 9 | 44 | 26.5 | -5.5 | 5058.5 |
| 2/25/1994 | 1994 | 2 | 25 | 269 | 16 | 62 | 39 | 7 | 5065.5 |
| 2/26/1994 | 1994 | 2 | 26 | 270 | 18 | 66 | 42 | 10 | 5075.5 |
| 2/27/1994 | 1994 | 2 | 27 | 271 | 6 | 65 | 35.5 | 3.5 | 5079 |
| 2/28/1994 | 1994 | 2 | 28 | 272 | 31 | 54 | 42.5 | 10.5 | 5089.5 |
| 3/1/1994 | 1994 | 3 | 1 | 273 | 15 | 47 | 31 | -1 | 5088.5 |
| 3/2/1994 | 1994 | 3 | 2 | 274 | 15 | 57 | 36 | 4 | 5092.5 |
| 3/3/1994 | 1994 | 3 | 3 | 275 | 14 | 68 | 41 | 9 | 5101.5 |
| 3/4/1994 | 1994 | 3 | 4 | 276 | 20 | 70 | 45 | 13 | 5114.5 |
| 3/5/1994 | 1994 | 3 | 5 | 277 | 23 | 70 | 46.5 | 14.5 | 5129 |
| 3/6/1994 | 1994 | 3 | 6 | 278 | 19 | 67 | 43 | 11 | 5140 |
| 3/7/1994 | 1994 | 3 | 7 | 279 | 26 | 61 | 43.5 | 11.5 | 5151.5 |
| 3/8/1994 | 1994 | 3 | 8 | 280 | 31 | 57 | 44 | 12 | 5163.5 |
| 3/9/1994 | 1994 | 3 | 9 | 281 | 25 | 43 | 34 | 2 | 5165.5 |
| 3/10/1994 | 1994 | 3 | 10 | 282 | 17 | 54 | 35.5 | 3.5 | 5169 |
| 3/11/1994 | 1994 | 3 | 11 | 283 | 25 | 60 | 42.5 | 10.5 | 5179.5 |
| 3/12/1994 | 1994 | 3 | 12 | 284 | 32 | 59 | 45.5 | 13.5 | 5193 |
| 3/13/1994 | 1994 | 3 | 13 | 285 | 5 | 42 | 23.5 | -8.5 | 5184.5 |
| 3/14/1994 | 1994 | 3 | 14 | 286 | 21 | 54 | 37.5 | 5.5 | 5190 |
| 3/15/1994 | 1994 | 3 | 15 | 287 | 23 | 68 | 45.5 | 13.5 | 5203.5 |
| 3/16/1994 | 1994 | 3 | 16 | 288 | 24 | 74 | 49 | 17 | 5220.5 |
| 3/17/1994 | 1994 | 3 | 17 | 289 | 33 | 76 | 54.5 | 22.5 | 5243 |
| 3/18/1994 | 1994 | 3 | 18 | 290 | 28 | 71 | 49.5 | 17.5 | 5260.5 |
| 3/19/1994 | 1994 | 3 | 19 | 291 | 32 | 71 | 51.5 | 19.5 | 5280 |
| 3/20/1994 | 1994 | 3 | 20 | 292 | 37 | 61 | 49 | 17 | 5297 |
| 3/21/1994 | 1994 | 3 | 21 | 293 | 21 | 57 | 39 | 7 | 5304 |
| 3/22/1994 | 1994 | 3 | 22 | 294 | 24 | 69 | 46.5 | 14.5 | 5318.5 |
| 3/23/1994 | 1994 | 3 | 23 | 295 | 43 | 68 | 55.5 | 23.5 | 5342 |
| 3/24/1994 | 1994 | 3 | 24 | 296 | 28 | 65 | 46.5 | 14.5 | 5356.5 |
| 3/25/1994 | 1994 | 3 | 25 | 297 | 25 | 65 | 45 | 13 | 5369.5 |
| 3/26/1994 | 1994 | 3 | 26 | 298 | 27 | 66 | 46.5 | 14.5 | 5384 |
| 3/27/1994 | 1994 | 3 | 27 | 299 | 25 | 55 | 40 | 8 | 5392 |
| 3/28/1994 | 1994 | 3 | 28 | 300 | 7 | 53 | 30 | -2 | 5390 |
| 3/29/1994 | 1994 | 3 | 29 | 301 | 16 | 62 | 39 | 7 | 5397 |
| 3/30/1994 | 1994 | 3 | 30 | 302 | 30 | 67 | 48.5 | 16.5 | 5413.5 |
| 3/31/1994 | 1994 | 3 | 31 | 303 | 20 | 61 | 40.5 | 8.5 | 5422 |
| 4/1/1994 | 1994 | 4 | 1 | 304 | 23 | 69 | 46 | 14 | 5436 |
| 4/2/1994 | 1994 | 4 | 2 | 305 | 25 | 72 | 48.5 | 16.5 | 5452.5 |
| 4/3/1994 | 1994 | 4 | 3 | 306 | 28 | 65 | 46.5 | 14.5 | 5467 |
| 4/4/1994 | 1994 | 4 | 4 | 307 | 43 | 75 | 59 | 27 | 5494 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/5/1994 | 1994 | 4 | 5 | 308 | 27 | 66 | 46.5 | 14.5 | 5508.5 |
| 4/6/1994 | 1994 | 4 | 6 | 309 | 16 | 52 | 34 | 2 | 5510.5 |
| 4/7/1994 | 1994 | 4 | 7 | 310 | 26 | 67 | 46.5 | 14.5 | 5525 |
| 4/8/1994 | 1994 | 4 | 8 | 311 | 36 | 67 | 51.5 | 19.5 | 5544.5 |
| 4/9/1994 | 1994 | 4 | 9 | 312 | 36 | 57 | 46.5 | 14.5 | 5559 |
| 4/10/1994 | 1994 | 4 | 10 | 313 | 26 | 60 | 43 | 11 | 5570 |
| 4/11/1994 | 1994 | 4 | 11 | 314 | 27 | 60 | 43.5 | 11.5 | 5581.5 |
| 4/12/1994 | 1994 | 4 | 12 | 315 | 22 | 54 | 38 | 6 | 5587.5 |
| 4/13/1994 | 1994 | 4 | 13 | 316 | 25 | 66 | 45.5 | 13.5 | 5601 |
| 4/14/1994 | 1994 | 4 | 14 | 317 | 35 | 74 | 54.5 | 22.5 | 5623.5 |
| 4/15/1994 | 1994 | 4 | 15 | 318 | 33 | 74 | 53.5 | 21.5 | 5645 |
| 4/16/1994 | 1994 | 4 | 16 | 319 | 25 | 77 | 51 | 19 | 5664 |
| 4/17/1994 | 1994 | 4 | 17 | 320 | 36 | 81 | 58.5 | 26.5 | 5690.5 |
| 4/18/1994 | 1994 | 4 | 18 | 321 | 37 | 80 | 58.5 | 26.5 | 5717 |
| 4/19/1994 | 1994 | 4 | 19 | 322 | 45 | 83 | 64 | 32 | 5749 |
| 4/20/1994 | 1994 | 4 | 20 | 323 | 41 | 79 | 60 | 28 | 5777 |
| 4/21/1994 | 1994 | 4 | 21 | 324 | 33 | 78 | 55.5 | 23.5 | 5800.5 |
| 4/22/1994 | 1994 | 4 | 22 | 325 | 44 | 80 | 62 | 30 | 5830.5 |
| 4/23/1994 | 1994 | 4 | 23 | 326 | 42 | 77 | 59.5 | 27.5 | 5858 |
| 4/24/1994 | 1994 | 4 | 24 | 327 | 40 | 79 | 59.5 | 27.5 | 5885.5 |
| 4/25/1994 | 1994 | 4 | 25 | 328 | 29 | 75 | 52 | 20 | 5905.5 |
| 4/26/1994 | 1994 | 4 | 26 | 329 | 35 | 54 | 44.5 | 12.5 | 5918 |
| 4/27/1994 | 1994 | 4 | 27 | 330 | 31 | 61 | 46 | 14 | 5932 |
| 4/28/1994 | 1994 | 4 | 28 | 331 | 25 | 57 | 41 | 9 | 5941 |
| 4/29/1994 | 1994 | 4 | 29 | 332 | 28 | 77 | 52.5 | 20.5 | 5961.5 |
| 4/30/1994 | 1994 | 4 | 30 | 333 | 25 | 59 | 42 | 10 | 5971.5 |
| 5/1/1994 | 1994 | 5 | 1 | 334 | 37 | 73 | 55 | 23 | 5994.5 |
| 5/2/1994 | 1994 | 5 | 2 | 335 | 30 | 72 | 51 | 19 | 6013.5 |
| 5/3/1994 | 1994 | 5 | 3 | 336 | 42 | 70 | 56 | 24 | 6037.5 |
| 5/4/1994 | 1994 | 5 | 4 | 337 | 32 | 75 | 53.5 | 21.5 | 6059 |
| 5/5/1994 | 1994 | 5 | 5 | 338 | 39 | 82 | 60.5 | 28.5 | 6087.5 |
| 5/6/1994 | 1994 | 5 | 6 | 339 | 33 | 86 | 59.5 | 27.5 | 6115 |
| 5/7/1994 | 1994 | 5 | 7 | 340 | 31 | 84 | 57.5 | 25.5 | 6140.5 |
| 5/8/1994 | 1994 | 5 | 8 | 341 | 28 | 84 | 56 | 24 | 6164.5 |
| 5/9/1994 | 1994 | 5 | 9 | 342 | 30 | 82 | 56 | 24 | 6188.5 |
| 5/10/1994 | 1994 | 5 | 10 | 343 | 36 | 73 | 54.5 | 22.5 | 6211 |
| 5/11/1994 | 1994 | 5 | 11 | 344 | 38 | 68 | 53 | 21 | 6232 |
| 5/12/1994 | 1994 | 5 | 12 | 345 | 36 | 69 | 52.5 | 20.5 | 6252.5 |
| 5/13/1994 | 1994 | 5 | 13 | 346 | 39 | 66 | 52.5 | 20.5 | 6273 |
| 5/14/1994 | 1994 | 5 | 14 | 347 | 42 | 73 | 57.5 | 25.5 | 6298.5 |
| 5/15/1994 | 1994 | 5 | 15 | 348 | 40 | 80 | 60 | 28 | 6326.5 |
| 5/16/1994 | 1994 | 5 | 16 | 349 | 41 | 82 | 61.5 | 29.5 | 6356 |
| 5/17/1994 | 1994 | 5 | 17 | 350 | 44 | 83 | 63.5 | 31.5 | 6387.5 |
| 5/18/1994 | 1994 | 5 | 18 | 351 | 45 | 85 | 65 | 33 | 6420.5 |
| 5/19/1994 | 1994 | 5 | 19 | 352 | 40 | 85 | 62.5 | 30.5 | 6451 |
| 5/20/1994 | 1994 | 5 | 20 | 353 | 35 | 85 | 60 | 28 | 6479 |
| 5/21/1994 | 1994 | 5 | 21 | 354 | 31 | 80 | 55.5 | 23.5 | 6502.5 |
| 5/22/1994 | 1994 | 5 | 22 | 355 | 37 | 87 | 62 | 30 | 6532.5 |
| 5/23/1994 | 1994 | 5 | 23 | 356 | 40 | 87 | 63.5 | 31.5 | 6564 |
| 5/24/1994 | 1994 | 5 | 24 | 357 | 47 | 80 | 63.5 | 31.5 | 6595.5 |
| 5/25/1994 | 1994 | 5 | 25 | 358 | 47 | 77 | 62 | 30 | 6625.5 |
| 5/26/1994 | 1994 | 5 | 26 | 359 | 45 | 69 | 57 | 25 | 6650.5 |
| 5/27/1994 | 1994 | 5 | 27 | 360 | 44 | 63 | 53.5 | 21.5 | 6672 |
| 5/28/1994 | 1994 | 5 | 28 | 361 | 43 | 75 | 59 | 27 | 6699 |
| 5/29/1994 | 1994 | 5 | 29 | 362 | 46 | 83 | 64.5 | 32.5 | 6731.5 |
| 5/30/1994 | 1994 | 5 | 30 | 363 | 43 | 82 | 62.5 | 30.5 | 6762 |
| 5/31/1994 | 1994 | 5 | 31 | 364 | 46 | 91 | 68.5 | 36.5 | 6798.5 |
| 6/1/1994 | 1994 | 6 | 1 | 1 | 46 | 91 | 68.5 | 36.5 | 36.5 |
| 6/2/1994 | 1994 | 6 | 2 | 2 | 44 | 90 | 67 | 35 | 71.5 |
| 6/3/1994 | 1994 | 6 | 3 | 3 | 58 | 89 | 73.5 | 41.5 | 113 |
| 6/4/1994 | 1994 | 6 | 4 | 4 | 48 | 86 | 67 | 35 | 148 |
| 6/5/1994 | 1994 | 6 | 5 | 5 | 44 | 87 | 65.5 | 33.5 | 181.5 |
| 6/6/1994 | 1994 | 6 | 6 | 6 | 39 | 89 | 64 | 32 | 213.5 |
| 6/7/1994 | 1994 | 6 | 7 | 7 | 47 | 92 | 69.5 | 37.5 | 251 |
| 6/8/1994 | 1994 | 6 | 8 | 8 | 50 | 86 | 68 | 36 | 287 |
| 6/9/1994 | 1994 | 6 | 9 | 9 | 42 | 88 | 65 | 33 | 320 |
| 6/10/1994 | 1994 | 6 | 10 | 10 | 43 | 93 | 68 | 36 | 356 |
| 6/11/1994 | 1994 | 6 | 11 | 11 | 45 | 93 | 69 | 37 | 393 |
| 6/12/1994 | 1994 | 6 | 12 | 12 | 50 | 94 | 72 | 40 | 433 |
| 6/13/1994 | 1994 | 6 | 13 | 13 | 55 | 93 | 74 | 42 | 475 |
| 6/14/1994 | 1994 | 6 | 14 | 14 | 51 | 93 | 72 | 40 | 515 |
| 6/15/1994 | 1994 | 6 | 15 | 15 | 57 | 93 | 75 | 43 | 558 |
| 6/16/1994 | 1994 | 6 | 16 | 16 | 42 | 90 | 66 | 34 | 592 |
| 6/17/1994 | 1994 | 6 | 17 | 17 | 50 | 91 | 70.5 | 38.5 | 630.5 |
| 6/18/1994 | 1994 | 6 | 18 | 18 | 51 | 92 | 71.5 | 39.5 | 670 |
| 6/19/1994 | 1994 | 6 | 19 | 19 | 56 | 89 | 72.5 | 40.5 | 710.5 |
| 6/20/1994 | 1994 | 6 | 20 | 20 | 51 | 87 | 69 | 37 | 747.5 |
| 6/21/1994 | 1994 | 6 | 21 | 21 | 56 | 90 | 73 | 41 | 788.5 |
| 6/22/1994 | 1994 | 6 | 22 | 22 | 52 | 87 | 69.5 | 37.5 | 826 |
| 6/23/1994 | 1994 | 6 | 23 | 23 | 49 | 88 | 68.5 | 36.5 | 862.5 |
| 6/24/1994 | 1994 | 6 | 24 | 24 | 47 | 93 | 70 | 38 | 900.5 |
| 6/25/1994 | 1994 | 6 | 25 | 25 | 48 | 99 | 73.5 | 41.5 | 942 |
| 6/26/1994 | 1994 | 6 | 26 | 26 | 56 | 101 | 78.5 | 46.5 | 988.5 |
| 6/27/1994 | 1994 | 6 | 27 | 27 | 58 | 101 | 79.5 | 47.5 | 1036 |
| 6/28/1994 | 1994 | 6 | 28 | 28 | 54 | 100 | 77 | 45 | 1081 |
| 6/29/1994 | 1994 | 6 | 29 | 29 | 56 | 99 | 77.5 | 45.5 | 1126.5 |
| 6/30/1994 | 1994 | 6 | 30 | 30 | 49 | 98 | 73.5 | 41.5 | 1168 |
| 7/1/1994 | 1994 | 7 | 1 | 31 | 49 | 98 | 73.5 | 41.5 | 1209.5 |
| 7/2/1994 | 1994 | 7 | 2 | 32 | 60 | 97 | 78.5 | 46.5 | 1256 |
| 7/3/1994 | 1994 | 7 | 3 | 33 | 59 | 96 | 77.5 | 45.5 | 1301.5 |
| 7/4/1994 | 1994 | 7 | 4 | 34 | 53 | 96 | 74.5 | 42.5 | 1344 |
| 7/5/1994 | 1994 | 7 | 5 | 35 | 54 | 94 | 74 | 42 | 1386 |
| 7/6/1994 | 1994 | 7 | 6 | 36 | 53 | 93 | 73 | 41 | 1427 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/7/1994 | 1994 | 7 | 7 | 37 | 50 | 91 | 70.5 | 38.5 | 1465.5 |
| 7/8/1994 | 1994 | 7 | 8 | 38 | 55 | 91 | 73 | 41 | 1506.5 |
| 7/9/1994 | 1994 | 7 | 9 | 39 | 54 | 89 | 71.5 | 39.5 | 1546 |
| 7/10/1994 | 1994 | 7 | 10 | 40 | 58 | 96 | 77 | 45 | 1591 |
| 7/11/1994 | 1994 | 7 | 11 | 41 | 58 | 98 | 78 | 46 | 1637 |
| 7/12/1994 | 1994 | 7 | 12 | 42 | 58 | 98 | 78 | 46 | 1683 |
| 7/13/1994 | 1994 | 7 | 13 | 43 | 58 | 98 | 78 | 46 | 1729 |
| 7/14/1994 | 1994 | 7 | 14 | 44 | 62 | 96 | 79 | 47 | 1776 |
| 7/15/1994 | 1994 | 7 | 15 | 45 | 59 | 95 | 77 | 45 | 1821 |
| 7/16/1994 | 1994 | 7 | 16 | 46 | 56 | 97 | 76.5 | 44.5 | 1865.5 |
| 7/17/1994 | 1994 | 7 | 17 | 47 | 63 | 99 | 81 | 49 | 1914.5 |
| 7/18/1994 | 1994 | 7 | 18 | 48 | 58 | 87 | 72.5 | 40.5 | 1955 |
| 7/19/1994 | 1994 | 7 | 19 | 49 | 54 | 89 | 71.5 | 39.5 | 1994.5 |
| 7/20/1994 | 1994 | 7 | 20 | 50 | 52 | 93 | 72.5 | 40.5 | 2035 |
| 7/21/1994 | 1994 | 7 | 21 | 51 | 51 | 88 | 69.5 | 37.5 | 2072.5 |
| 7/22/1994 | 1994 | 7 | 22 | 52 | 49 | 88 | 68.5 | 36.5 | 2109 |
| 7/23/1994 | 1994 | 7 | 23 | 53 | 50 | 90 | 70 | 38 | 2147 |
| 7/24/1994 | 1994 | 7 | 24 | 54 | 45 | 90 | 67.5 | 35.5 | 2182.5 |
| 7/25/1994 | 1994 | 7 | 25 | 55 | 44 | 90 | 67 | 35 | 2217.5 |
| 7/26/1994 | 1994 | 7 | 26 | 56 | 50 | 91 | 70.5 | 38.5 | 2256 |
| 7/27/1994 | 1994 | 7 | 27 | 57 | 57 | 90 | 73.5 | 41.5 | 2297.5 |
| 7/28/1994 | 1994 | 7 | 28 | 58 | 53 | 92 | 72.5 | 40.5 | 2338 |
| 7/29/1994 | 1994 | 7 | 29 | 59 | 57 | 88 | 72.5 | 40.5 | 2378.5 |
| 7/30/1994 | 1994 | 7 | 30 | 60 | 47 | 92 | 69.5 | 37.5 | 2416 |
| 7/31/1994 | 1994 | 7 | 31 | 61 | 59 | 91 | 75 | 43 | 2459 |
| 8/1/1994 | 1994 | 8 | 1 | 62 | 59 | 90 | 74.5 | 42.5 | 2501.5 |
| 8/2/1994 | 1994 | 8 | 2 | 63 | 58 | 91 | 74.5 | 42.5 | 2544 |
| 8/3/1994 | 1994 | 8 | 3 | 64 | 52 | 94 | 73 | 41 | 2585 |
| 8/4/1994 | 1994 | 8 | 4 | 65 | 55 | 96 | 75.5 | 43.5 | 2628.5 |
| 8/5/1994 | 1994 | 8 | 5 | 66 | 52 | 92 | 72 | 40 | 2668.5 |
| 8/6/1994 | 1994 | 8 | 6 | 67 | 56 | 89 | 72.5 | 40.5 | 2709 |
| 8/7/1994 | 1994 | 8 | 7 | 68 | 56 | 93 | 74.5 | 42.5 | 2751.5 |
| 8/8/1994 | 1994 | 8 | 8 | 69 | 58 | 98 | 78 | 46 | 2797.5 |
| 8/9/1994 | 1994 | 8 | 9 | 70 | 59 | 89 | 74 | 42 | 2839.5 |
| 8/10/1994 | 1994 | 8 | 10 | 71 | 59 | 86 | 72.5 | 40.5 | 2880 |
| 8/11/1994 | 1994 | 8 | 11 | 72 | 60 | 87 | 73.5 | 41.5 | 2921.5 |
| 8/12/1994 | 1994 | 8 | 12 | 73 | 58 | 89 | 73.5 | 41.5 | 2963 |
| 8/13/1994 | 1994 | 8 | 13 | 74 | 59 | 93 | 76 | 44 | 3007 |
| 8/14/1994 | 1994 | 8 | 14 | 75 | 62 | 97 | 79.5 | 47.5 | 3054.5 |
| 8/15/1994 | 1994 | 8 | 15 | 76 | 55 | 89 | 72 | 40 | 3094.5 |
| 8/16/1994 | 1994 | 8 | 16 | 77 | 45 | 83 | 64 | 32 | 3126.5 |
| 8/17/1994 | 1994 | 8 | 17 | 78 | 57 | 91 | 74 | 42 | 3168.5 |
| 8/18/1994 | 1994 | 8 | 18 | 79 | 57 | 96 | 76.5 | 44.5 | 3213 |
| 8/19/1994 | 1994 | 8 | 19 | 80 | 58 | 94 | 76 | 44 | 3257 |
| 8/20/1994 | 1994 | 8 | 20 | 81 | 48 | 86 | 67 | 35 | 3292 |
| 8/21/1994 | 1994 | 8 | 21 | 82 | 54 | 80 | 67 | 35 | 3327 |
| 8/22/1994 | 1994 | 8 | 22 | 83 | 55 | 82 | 68.5 | 36.5 | 3363.5 |
| 8/23/1994 | 1994 | 8 | 23 | 84 | 51 | 85 | 68 | 36 | 3399.5 |
| 8/24/1994 | 1994 | 8 | 24 | 85 | 53 | 91 | 72 | 40 | 3439.5 |
| 8/25/1994 | 1994 | 8 | 25 | 86 | 59 | 87 | 73 | 41 | 3480.5 |
| 8/26/1994 | 1994 | 8 | 26 | 87 | 56 | 86 | 71 | 39 | 3519.5 |
| 8/27/1994 | 1994 | 8 | 27 | 88 | 55 | 89 | 72 | 40 | 3559.5 |
| 8/28/1994 | 1994 | 8 | 28 | 89 | 49 | 92 | 70.5 | 38.5 | 3598 |
| 8/29/1994 | 1994 | 8 | 29 | 90 | 57 | 88 | 72.5 | 40.5 | 3638.5 |
| 8/30/1994 | 1994 | 8 | 30 | 91 | 45 | 85 | 65 | 33 | 3671.5 |
| 8/31/1994 | 1994 | 8 | 31 | 92 | 44 | 84 | 64 | 32 | 3703.5 |
| 9/1/1994 | 1994 | 9 | 1 | 93 | 45 | 85 | 65 | 33 | 3736.5 |
| 9/2/1994 | 1994 | 9 | 2 | 94 | 55 | 83 | 69 | 37 | 3773.5 |
| 9/3/1994 | 1994 | 9 | 3 | 95 | 59 | 84 | 71.5 | 39.5 | 3813 |
| 9/4/1994 | 1994 | 9 | 4 | 96 | 53 | 63 | 58 | 26 | 3839 |
| 9/5/1994 | 1994 | 9 | 5 | 97 | 50 | 82 | 66 | 34 | 3873 |
| 9/6/1994 | 1994 | 9 | 6 | 98 | 53 | 87 | 70 | 38 | 3911 |
| 9/7/1994 | 1994 | 9 | 7 | 99 | 52 | 82 | 67 | 35 | 3946 |
| 9/8/1994 | 1994 | 9 | 8 | 100 | 47 | 86 | 66.5 | 34.5 | 3980.5 |
| 9/9/1994 | 1994 | 9 | 9 | 101 | 49 | 88 | 68.5 | 36.5 | 4017 |
| 9/10/1994 | 1994 | 9 | 10 | 102 | 50 | 89 | 69.5 | 37.5 | 4054.5 |
| 9/11/1994 | 1994 | 9 | 11 | 103 | 56 | 85 | 70.5 | 38.5 | 4093 |
| 9/12/1994 | 1994 | 9 | 12 | 104 | 53 | 85 | 69 | 37 | 4130 |
| 9/13/1994 | 1994 | 9 | 13 | 105 | 55 | 81 | 68 | 36 | 4166 |
| 9/14/1994 | 1994 | 9 | 14 | 106 | 51 | 75 | 63 | 31 | 4197 |
| 9/15/1994 | 1994 | 9 | 15 | 107 | 37 | 76 | 56.5 | 24.5 | 4221.5 |
| 9/16/1994 | 1994 | 9 | 16 | 108 | 38 | 76 | 57 | 25 | 4246.5 |
| 9/17/1994 | 1994 | 9 | 17 | 109 | 49 | 76 | 62.5 | 30.5 | 4277 |
| 9/18/1994 | 1994 | 9 | 18 | 110 | 43 | 76 | 59.5 | 27.5 | 4304.5 |
| 9/19/1994 | 1994 | 9 | 19 | 111 | 42 | 77 | 59.5 | 27.5 | 4332 |
| 9/20/1994 | 1994 | 9 | 20 | 112 | 52 | 81 | 66.5 | 34.5 | 4366.5 |
| 9/21/1994 | 1994 | 9 | 21 | 113 | 44 | 76 | 60 | 28 | 4394.5 |
| 9/22/1994 | 1994 | 9 | 22 | 114 | 39 | 76 | 57.5 | 25.5 | 4420 |
| 9/23/1994 | 1994 | 9 | 23 | 115 | 35 | 80 | 57.5 | 25.5 | 4445.5 |
| 9/24/1994 | 1994 | 9 | 24 | 116 | 36 | 80 | 58 | 26 | 4471.5 |
| 9/25/1994 | 1994 | 9 | 25 | 117 | 35 | 83 | 59 | 27 | 4498.5 |
| 9/26/1994 | 1994 | 9 | 26 | 118 | 37 | 83 | 60 | 28 | 4526.5 |
| 9/27/1994 | 1994 | 9 | 27 | 119 | 36 | 82 | 59 | 27 | 4553.5 |
| 9/28/1994 | 1994 | 9 | 28 | 120 | 36 | 86 | 61 | 29 | 4582.5 |
| 9/29/1994 | 1994 | 9 | 29 | 121 | 50 | 85 | 67.5 | 35.5 | 4618 |
| 9/30/1994 | 1994 | 9 | 30 | 122 | 50 | 85 | 67.5 | 35.5 | 4653.5 |
| 10/1/1994 | 1994 | 10 | 1 | 123 | 53 | 79 | 66 | 34 | 4687.5 |
| 10/2/1994 | 1994 | 10 | 2 | 124 | 36 | 76 | 56 | 24 | 4711.5 |
| 10/3/1994 | 1994 | 10 | 3 | 125 | 35 | 76 | 55.5 | 23.5 | 4735 |
| 10/4/1994 | 1994 | 10 | 4 | 126 | 50 | 72 | 61 | 29 | 4764 |
| 10/5/1994 | 1994 | 10 | 5 | 127 | 54 | 75 | 64.5 | 32.5 | 4796.5 |
| 10/6/1994 | 1994 | 10 | 6 | 128 | 39 | 70 | 54.5 | 22.5 | 4819 |
| 10/7/1994 | 1994 | 10 | 7 | 129 | 38 | 65 | 51.5 | 19.5 | 4838.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/8/1994 | 1994 | 10 | 8 | 130 | 28 | 67 | 47.5 | 15.5 | 4854 |
| 10/9/1994 | 1994 | 10 | 9 | 131 | 22 | 68 | 45 | 13 | 4867 |
| 10/10/1994 | 1994 | 10 | 10 | 132 | 28 | 71 | 49.5 | 17.5 | 4884.5 |
| 10/11/1994 | 1994 | 10 | 11 | 133 | 29 | 74 | 51.5 | 19.5 | 4904 |
| 10/12/1994 | 1994 | 10 | 12 | 134 | 29 | 74 | 51.5 | 19.5 | 4923.5 |
| 10/13/1994 | 1994 | 10 | 13 | 135 | 32 | 75 | 53.5 | 21.5 | 4945 |
| 10/14/1994 | 1994 | 10 | 14 | 136 | 46 | 72 | 59 | 27 | 4972 |
| 10/15/1994 | 1994 | 10 | 15 | 137 | 35 | 46 | 40.5 | 8.5 | 4980.5 |
| 10/16/1994 | 1994 | 10 | 16 | 138 | 33 | 55 | 44 | 12 | 4992.5 |
| 10/17/1994 | 1994 | 10 | 17 | 139 | 33 | 45 | 39 | 7 | 4999.5 |
| 10/18/1994 | 1994 | 10 | 18 | 140 | 26 | 53 | 39.5 | 7.5 | 5007 |
| 10/19/1994 | 1994 | 10 | 19 | 141 | 31 | 62 | 46.5 | 14.5 | 5021.5 |
| 10/20/1994 | 1994 | 10 | 20 | 142 | 30 | 66 | 48 | 16 | 5037.5 |
| 10/21/1994 | 1994 | 10 | 21 | 143 | 30 | 70 | 50 | 18 | 5055.5 |
| 10/22/1994 | 1994 | 10 | 22 | 144 | 34 | 71 | 52.5 | 20.5 | 5076 |
| 10/23/1994 | 1994 | 10 | 23 | 145 | 30 | 70 | 50 | 18 | 5094 |
| 10/24/1994 | 1994 | 10 | 24 | 146 | 34 | 71 | 52.5 | 20.5 | 5114.5 |
| 10/25/1994 | 1994 | 10 | 25 | 147 | 33 | 69 | 51 | 19 | 5133.5 |
| 10/26/1994 | 1994 | 10 | 26 | 148 | 40 | 62 | 51 | 19 | 5152.5 |
| 10/27/1994 | 1994 | 10 | 27 | 149 | 30 | 63 | 46.5 | 14.5 | 5167 |
| 10/28/1994 | 1994 | 10 | 28 | 150 | 34 | 70 | 52 | 20 | 5187 |
| 10/29/1994 | 1994 | 10 | 29 | 151 | 32 | 77 | 54.5 | 22.5 | 5209.5 |
| 10/30/1994 | 1994 | 10 | 30 | 152 | 34 | 74 | 54 | 22 | 5231.5 |
| 10/31/1994 | 1994 | 10 | 31 | 153 | 21 | 74 | 47.5 | 15.5 | 5247 |
| 11/1/1994 | 1994 | 11 | 1 | 154 | 25 | 70 | 47.5 | 15.5 | 5262.5 |
| 11/2/1994 | 1994 | 11 | 2 | 155 | 40 | 72 | 56 | 24 | 5286.5 |
| 11/3/1994 | 1994 | 11 | 3 | 156 | 39 | 67 | 53 | 21 | 5307.5 |
| 11/4/1994 | 1994 | 11 | 4 | 157 | 26 | 50 | 38 | 6 | 5313.5 |
| 11/5/1994 | 1994 | 11 | 5 | 158 | 25 | 49 | 37 | 5 | 5318.5 |
| 11/6/1994 | 1994 | 11 | 6 | 159 | 28 | 62 | 45 | 13 | 5331.5 |
| 11/7/1994 | 1994 | 11 | 7 | 160 | 35 | 68 | 51.5 | 19.5 | 5351 |
| 11/8/1994 | 1994 | 11 | 8 | 161 | 37 | 66 | 51.5 | 19.5 | 5370.5 |
| 11/9/1994 | 1994 | 11 | 9 | 162 | 22 | 58 | 40 | 8 | 5378.5 |
| 11/10/1994 | 1994 | 11 | 10 | 163 | 36 | 60 | 48 | 16 | 5394.5 |
| 11/11/1994 | 1994 | 11 | 11 | 164 | 36 | 61 | 48.5 | 16.5 | 5411 |
| 11/12/1994 | 1994 | 11 | 12 | 165 | 41 | 43 | 42 | 10 | 5421 |
| 11/13/1994 | 1994 | 11 | 13 | 166 | 32 | 53 | 42.5 | 10.5 | 5431.5 |
| 11/14/1994 | 1994 | 11 | 14 | 167 | 22 | 47 | 34.5 | 2.5 | 5434 |
| 11/15/1994 | 1994 | 11 | 15 | 168 | 15 | 44 | 29.5 | -2.5 | 5431.5 |
| 11/16/1994 | 1994 | 11 | 16 | 169 | 33 | 47 | 40 | 8 | 5439.5 |
| 11/17/1994 | 1994 | 11 | 17 | 170 | 28 | 54 | 41 | 9 | 5448.5 |
| 11/18/1994 | 1994 | 11 | 18 | 171 | 25 | 44 | 34.5 | 2.5 | 5451 |
| 11/19/1994 | 1994 | 11 | 19 | 172 | 27 | 58 | 42.5 | 10.5 | 5461.5 |
| 11/20/1994 | 1994 | 11 | 20 | 173 | 20 | 42 | 31 | -1 | 5460.5 |
| 11/21/1994 | 1994 | 11 | 21 | 174 | 16 | 45 | 30.5 | -1.5 | 5459 |
| 11/22/1994 | 1994 | 11 | 22 | 175 | 20 | 59 | 39.5 | 7.5 | 5466.5 |
| 11/23/1994 | 1994 | 11 | 23 | 176 | 17 | 47 | 32 | 0 | 5466.5 |
| 11/24/1994 | 1994 | 11 | 24 | 177 | 19 | 44 | 31.5 | -0.5 | 5466 |
| 11/25/1994 | 1994 | 11 | 25 | 178 | 28 | 64 | 46 | 14 | 5480 |
| 11/26/1994 | 1994 | 11 | 26 | 179 | 28 | 57 | 42.5 | 10.5 | 5490.5 |
| 11/27/1994 | 1994 | 11 | 27 | 180 | 15 | 55 | 35 | 3 | 5493.5 |
| 11/28/1994 | 1994 | 11 | 28 | 181 | 8 | 35 | 21.5 | -10.5 | 5483 |
| 11/29/1994 | 1994 | 11 | 29 | 182 | 11 | 37 | 24 | -8 | 5475 |
| 11/30/1994 | 1994 | 11 | 30 | 183 | 13 | 37 | 25 | -7 | 5468 |
| 12/1/1994 | 1994 | 12 | 1 | 184 | 13 | 50 | 31.5 | -0.5 | 5467.5 |
| 12/2/1994 | 1994 | 12 | 2 | 185 | 15 | 62 | 38.5 | 6.5 | 5474 |
| 12/3/1994 | 1994 | 12 | 3 | 186 | 15 | 63 | 39 | 7 | 5481 |
| 12/4/1994 | 1994 | 12 | 4 | 187 | 18 | 60 | 39 | 7 | 5488 |
| 12/5/1994 | 1994 | 12 | 5 | 188 | 33 | 58 | 45.5 | 13.5 | 5501.5 |
| 12/6/1994 | 1994 | 12 | 6 | 189 | 38 | 45 | 41.5 | 9.5 | 5511 |
| 12/7/1994 | 1994 | 12 | 7 | 190 | 23 | 55 | 39 | 7 | 5518 |
| 12/8/1994 | 1994 | 12 | 8 | 191 | 29 | 56 | 42.5 | 10.5 | 5528.5 |
| 12/9/1994 | 1994 | 12 | 9 | 192 | 9 | 48 | 28.5 | -3.5 | 5525 |
| 12/10/1994 | 1994 | 12 | 10 | 193 | 8 | 58 | 33 | 1 | 5526 |
| 12/11/1994 | 1994 | 12 | 11 | 194 | 22 | 44 | 33 | 1 | 5527 |
| 12/12/1994 | 1994 | 12 | 12 | 195 | 16 | 50 | 33 | 1 | 5528 |
| 12/13/1994 | 1994 | 12 | 13 | 196 | 15 | 50 | 32.5 | 0.5 | 5528.5 |
| 12/14/1994 | 1994 | 12 | 14 | 197 | 23 | 53 | 38 | 6 | 5534.5 |
| 12/15/1994 | 1994 | 12 | 15 | 198 | 12 | 47 | 29.5 | -2.5 | 5532 |
| 12/16/1994 | 1994 | 12 | 16 | 199 | 11 | 49 | 30 | -2 | 5530 |
| 12/17/1994 | 1994 | 12 | 17 | 200 | 13 | 50 | 31.5 | -0.5 | 5529.5 |
| 12/18/1994 | 1994 | 12 | 18 | 201 | 12 | 58 | 35 | 3 | 5532.5 |
| 12/19/1994 | 1994 | 12 | 19 | 202 | 14 | 58 | 36 | 4 | 5536.5 |
| 12/20/1994 | 1994 | 12 | 20 | 203 | 14 | 58 | 36 | 4 | 5540.5 |
| 12/21/1994 | 1994 | 12 | 21 | 204 | 14 | 53 | 33.5 | 1.5 | 5542 |
| 12/22/1994 | 1994 | 12 | 22 | 205 | 14 | 60 | 37 | 5 | 5547 |
| 12/23/1994 | 1994 | 12 | 23 | 206 | 37 | 60 | 48.5 | 16.5 | 5563.5 |
| 12/24/1994 | 1994 | 12 | 24 | 207 | 34 | 60 | 47 | 15 | 5578.5 |
| 12/25/1994 | 1994 | 12 | 25 | 208 | 24 | 60 | 42 | 10 | 5588.5 |
| 12/26/1994 | 1994 | 12 | 26 | 209 | 25 | 51 | 38 | 6 | 5594.5 |
| 12/27/1994 | 1994 | 12 | 27 | 210 | 20 | 56 | 38 | 6 | 5600.5 |
| 12/28/1994 | 1994 | 12 | 28 | 211 | 15 | 54 | 34.5 | 2.5 | 5603 |
| 12/29/1994 | 1994 | 12 | 29 | 212 | 15 | 58 | 36.5 | 4.5 | 5607.5 |
| 12/30/1994 | 1994 | 12 | 30 | 213 | 20 | 52 | 36 | 4 | 5611.5 |
| 12/31/1994 | 1994 | 12 | 31 | 214 | 19 | 39 | 29 | -3 | 5608.5 |
| 1/1/1995 | 1995 | 1 | 1 | 215 | 14 | 53 | 33.5 | 1.5 | 5610 |
| 1/2/1995 | 1995 | 1 | 2 | 216 | 25 | 46 | 35.5 | 3.5 | 5613.5 |
| 1/3/1995 | 1995 | 1 | 3 | 217 | 16 | 48 | 32 | 0 | 5613.5 |
| 1/4/1995 | 1995 | 1 | 4 | 218 | 28 | 48 | 38 | 6 | 5619.5 |
| 1/5/1995 | 1995 | 1 | 5 | 219 | 26 | 38 | 32 | 0 | 5619.5 |
| 1/6/1995 | 1995 | 1 | 6 | 220 | 29 | 42 | 35.5 | 3.5 | 5623 |
| 1/7/1995 | 1995 | 1 | 7 | 221 | 11 | 40 | 25.5 | -6.5 | 5616.5 |
| 1/8/1995 | 1995 | 1 | 8 | 222 | 31 | 47 | 39 | 7 | 5623.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/9/1995 | 1995 | 1 | 9 | 223 | 21 | 54 | 37.5 | 5.5 | 5629 |
| 1/10/1995 | 1995 | 1 | 10 | 224 | 19 | 53 | 36 | 4 | 5633 |
| 1/11/1995 | 1995 | 1 | 11 | 225 | 21 | 61 | 41 | 9 | 5642 |
| 1/12/1995 | 1995 | 1 | 12 | 226 | 34 | 54 | 44 | 12 | 5654 |
| 1/13/1995 | 1995 | 1 | 13 | 227 | 26 | 52 | 39 | 7 | 5661 |
| 1/14/1995 | 1995 | 1 | 14 | 228 | 21 | 49 | 35 | 3 | 5664 |
| 1/15/1995 | 1995 | 1 | 15 | 229 | 27 | 64 | 45.5 | 13.5 | 5677.5 |
| 1/16/1995 | 1995 | 1 | 16 | 230 | 27 | 58 | 42.5 | 10.5 | 5688 |
| 1/17/1995 | 1995 | 1 | 17 | 231 | 21 | 40 | 30.5 | -1.5 | 5686.5 |
| 1/18/1995 | 1995 | 1 | 18 | 232 | 9 | 38 | 23.5 | -8.5 | 5678 |
| 1/19/1995 | 1995 | 1 | 19 | 233 | 11 | 42 | 26.5 | -5.5 | 5672.5 |
| 1/20/1995 | 1995 | 1 | 20 | 234 | 16 | 50 | 33 | 1 | 5673.5 |
| 1/21/1995 | 1995 | 1 | 21 | 235 | 24 | 51 | 37.5 | 5.5 | 5679 |
| 1/22/1995 | 1995 | 1 | 22 | 236 | 20 | 48 | 34 | 2 | 5681 |
| 1/23/1995 | 1995 | 1 | 23 | 237 | 12 | 43 | 27.5 | -4.5 | 5676.5 |
| 1/24/1995 | 1995 | 1 | 24 | 238 | 27 | 49 | 38 | 6 | 5682.5 |
| 1/25/1995 | 1995 | 1 | 25 | 239 | 22 | 53 | 37.5 | 5.5 | 5688 |
| 1/26/1995 | 1995 | 1 | 26 | 240 | 24 | 55 | 39.5 | 7.5 | 5695.5 |
| 1/27/1995 | 1995 | 1 | 27 | 241 | 32 | 46 | 39 | 7 | 5702.5 |
| 1/28/1995 | 1995 | 1 | 28 | 242 | 17 | 48 | 32.5 | 0.5 | 5703 |
| 1/29/1995 | 1995 | 1 | 29 | 243 | 15 | 48 | 31.5 | -0.5 | 5702.5 |
| 1/30/1995 | 1995 | 1 | 30 | 244 | 10 | 40 | 25 | -7 | 5695.5 |
| 1/31/1995 | 1995 | 1 | 31 | 245 | 16 | 48 | 32 | 0 | 5695.5 |
| 2/1/1995 | 1995 | 2 | 1 | 246 | 25 | 61 | 43 | 11 | 5706.5 |
| 2/2/1995 | 1995 | 2 | 2 | 247 | 22 | 61 | 41.5 | 9.5 | 5716 |
| 2/3/1995 | 1995 | 2 | 3 | 248 | 25 | 64 | 44.5 | 12.5 | 5728.5 |
| 2/4/1995 | 1995 | 2 | 4 | 249 | 26 | 62 | 44 | 12 | 5740.5 |
| 2/5/1995 | 1995 | 2 | 5 | 250 | 13 | 67 | 40 | 8 | 5748.5 |
| 2/6/1995 | 1995 | 2 | 6 | 251 | 12 | 67 | 39.5 | 7.5 | 5756 |
| 2/7/1995 | 1995 | 2 | 7 | 252 | 16 | 67 | 41.5 | 9.5 | 5765.5 |
| 2/8/1995 | 1995 | 2 | 8 | 253 | 30 | 64 | 47 | 15 | 5780.5 |
| 2/9/1995 | 1995 | 2 | 9 | 254 | 26 | 57 | 41.5 | 9.5 | 5790 |
| 2/10/1995 | 1995 | 2 | 10 | 255 | 20 | 59 | 39.5 | 7.5 | 5797.5 |
| 2/11/1995 | 1995 | 2 | 11 | 256 | 27 | 55 | 41 | 9 | 5806.5 |
| 2/12/1995 | 1995 | 2 | 12 | 257 | 35 | 53 | 44 | 12 | 5818.5 |
| 2/13/1995 | 1995 | 2 | 13 | 258 | 28 | 58 | 43 | 11 | 5829.5 |
| 2/14/1995 | 1995 | 2 | 14 | 259 | 33 | 56 | 44.5 | 12.5 | 5842 |
| 2/15/1995 | 1995 | 2 | 15 | 260 | 35 | 59 | 47 | 15 | 5857 |
| 2/16/1995 | 1995 | 2 | 16 | 261 | 26 | 54 | 40 | 8 | 5865 |
| 2/17/1995 | 1995 | 2 | 17 | 262 | 18 | 55 | 36.5 | 4.5 | 5869.5 |
| 2/18/1995 | 1995 | 2 | 18 | 263 | 18 | 59 | 38.5 | 6.5 | 5876 |
| 2/19/1995 | 1995 | 2 | 19 | 264 | 19 | 62 | 40.5 | 8.5 | 5884.5 |
| 2/20/1995 | 1995 | 2 | 20 | 265 | 22 | 68 | 45 | 13 | 5897.5 |
| 2/21/1995 | 1995 | 2 | 21 | 266 | 24 | 69 | 46.5 | 14.5 | 5912 |
| 2/22/1995 | 1995 | 2 | 22 | 267 | 27 | 68 | 47.5 | 15.5 | 5927.5 |
| 2/23/1995 | 1995 | 2 | 23 | 268 | 27 | 68 | 47.5 | 15.5 | 5943 |
| 2/24/1995 | 1995 | 2 | 24 | 269 | 37 | 65 | 51 | 19 | 5962 |
| 2/25/1995 | 1995 | 2 | 25 | 270 | 32 | 60 | 46 | 14 | 5976 |
| 2/26/1995 | 1995 | 2 | 26 | 271 | 33 | 60 | 46.5 | 14.5 | 5990.5 |
| 2/27/1995 | 1995 | 2 | 27 | 272 | 27 | 57 | 42 | 10 | 6000.5 |
| 2/28/1995 | 1995 | 2 | 28 | 273 | 35 | 64 | 49.5 | 17.5 | 6018 |
| 3/1/1995 | 1995 | 3 | 1 | 274 | 37 | 59 | 48 | 16 | 6034 |
| 3/2/1995 | 1995 | 3 | 2 | 275 | 33 | 53 | 43 | 11 | 6045 |
| 3/3/1995 | 1995 | 3 | 3 | 276 | 37 | 57 | 47 | 15 | 6060 |
| 3/4/1995 | 1995 | 3 | 4 | 277 | 41 | 58 | 49.5 | 17.5 | 6077.5 |
| 3/5/1995 | 1995 | 3 | 5 | 278 | 38 | 58 | 48 | 16 | 6093.5 |
| 3/6/1995 | 1995 | 3 | 6 | 279 | 42 | 56 | 49 | 17 | 6110.5 |
| 3/7/1995 | 1995 | 3 | 7 | 280 | 17 | 54 | 35.5 | 3.5 | 6114 |
| 3/8/1995 | 1995 | 3 | 8 | 281 | 14 | 52 | 33 | 1 | 6115 |
| 3/9/1995 | 1995 | 3 | 9 | 282 | 28 | 62 | 45 | 13 | 6128 |
| 3/10/1995 | 1995 | 3 | 10 | 283 | 21 | 69 | 45 | 13 | 6141 |
| 3/11/1995 | 1995 | 3 | 11 | 284 | 28 | 73 | 50.5 | 18.5 | 6159.5 |
| 3/12/1995 | 1995 | 3 | 12 | 285 | 31 | 69 | 50 | 18 | 6177.5 |
| 3/13/1995 | 1995 | 3 | 13 | 286 | 24 | 56 | 40 | 8 | 6185.5 |
| 3/14/1995 | 1995 | 3 | 14 | 287 | 23 | 64 | 43.5 | 11.5 | 6197 |
| 3/15/1995 | 1995 | 3 | 15 | 288 | 31 | 71 | 51 | 19 | 6216 |
| 3/16/1995 | 1995 | 3 | 16 | 289 | 27 | 69 | 48 | 16 | 6232 |
| 3/17/1995 | 1995 | 3 | 17 | 290 | 40 | 70 | 55 | 23 | 6255 |
| 3/18/1995 | 1995 | 3 | 18 | 291 | 24 | 62 | 43 | 11 | 6266 |
| 3/19/1995 | 1995 | 3 | 19 | 292 | 34 | 72 | 53 | 21 | 6287 |
| 3/20/1995 | 1995 | 3 | 20 | 293 | 33 | 77 | 55 | 23 | 6310 |
| 3/21/1995 | 1995 | 3 | 21 | 294 | 38 | 71 | 54.5 | 22.5 | 6332.5 |
| 3/22/1995 | 1995 | 3 | 22 | 295 | 42 | 77 | 59.5 | 27.5 | 6360 |
| 3/23/1995 | 1995 | 3 | 23 | 296 | 22 | 62 | 42 | 10 | 6370 |
| 3/24/1995 | 1995 | 3 | 24 | 297 | 33 | 72 | 52.5 | 20.5 | 6390.5 |
| 3/25/1995 | 1995 | 3 | 25 | 298 | 27 | 63 | 45 | 13 | 6403.5 |
| 3/26/1995 | 1995 | 3 | 26 | 299 | 16 | 45 | 30.5 | -1.5 | 6402 |
| 3/27/1995 | 1995 | 3 | 27 | 300 | 13 | 54 | 33.5 | 1.5 | 6403.5 |
| 3/28/1995 | 1995 | 3 | 28 | 301 | 20 | 59 | 39.5 | 7.5 | 6411 |
| 3/29/1995 | 1995 | 3 | 29 | 302 | 24 | 52 | 38 | 6 | 6417 |
| 3/30/1995 | 1995 | 3 | 30 | 303 | 16 | 56 | 36 | 4 | 6421 |
| 3/31/1995 | 1995 | 3 | 31 | 304 | 14 | 53 | 33.5 | 1.5 | 6422.5 |
| 4/1/1995 | 1995 | 4 | 1 | 305 | 15 | 62 | 38.5 | 6.5 | 6429 |
| 4/2/1995 | 1995 | 4 | 2 | 306 | 31 | 64 | 47.5 | 15.5 | 6444.5 |
| 4/3/1995 | 1995 | 4 | 3 | 307 | 25 | 60 | 42.5 | 10.5 | 6455 |
| 4/4/1995 | 1995 | 4 | 4 | 308 | 22 | 64 | 43 | 11 | 6466 |
| 4/5/1995 | 1995 | 4 | 5 | 309 | 24 | 69 | 46.5 | 14.5 | 6480.5 |
| 4/6/1995 | 1995 | 4 | 6 | 310 | 33 | 75 | 54 | 22 | 6502.5 |
| 4/7/1995 | 1995 | 4 | 7 | 311 | 35 | 76 | 55.5 | 23.5 | 6526 |
| 4/8/1995 | 1995 | 4 | 8 | 312 | 32 | 73 | 52.5 | 20.5 | 6546.5 |
| 4/9/1995 | 1995 | 4 | 9 | 313 | 44 | 74 | 59 | 27 | 6573.5 |
| 4/10/1995 | 1995 | 4 | 10 | 314 | 28 | 63 | 45.5 | 13.5 | 6587 |
| 4/11/1995 | 1995 | 4 | 11 | 315 | 20 | 51 | 35.5 | 3.5 | 6590.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/12/1995 | 1995 | 4 | 12 | 316 | 22 | 62 | 42 | 10 | 6600.5 |
| 4/13/1995 | 1995 | 4 | 13 | 317 | 33 | 74 | 53.5 | 21.5 | 6622 |
| 4/14/1995 | 1995 | 4 | 14 | 318 | 47 | 78 | 62.5 | 30.5 | 6652.5 |
| 4/15/1995 | 1995 | 4 | 15 | 319 | 37 | 70 | 53.5 | 21.5 | 6674 |
| 4/16/1995 | 1995 | 4 | 16 | 320 | 32 | 69 | 50.5 | 18.5 | 6692.5 |
| 4/17/1995 | 1995 | 4 | 17 | 321 | 30 | 72 | 51 | 19 | 6711.5 |
| 4/18/1995 | 1995 | 4 | 18 | 322 | 23 | 47 | 35 | 3 | 6714.5 |
| 4/19/1995 | 1995 | 4 | 19 | 323 | 32 | 62 | 47 | 15 | 6729.5 |
| 4/20/1995 | 1995 | 4 | 20 | 324 | 29 | 51 | 40 | 8 | 6737.5 |
| 4/21/1995 | 1995 | 4 | 21 | 325 | 33 | 54 | 43.5 | 11.5 | 6749 |
| 4/22/1995 | 1995 | 4 | 22 | 326 | 24 | 56 | 40 | 8 | 6757 |
| 4/23/1995 | 1995 | 4 | 23 | 327 | 28 | 52 | 40 | 8 | 6765 |
| 4/24/1995 | 1995 | 4 | 24 | 328 | 25 | 63 | 44 | 12 | 6777 |
| 4/25/1995 | 1995 | 4 | 25 | 329 | 21 | 63 | 42 | 10 | 6787 |
| 4/26/1995 | 1995 | 4 | 26 | 330 | 40 | 74 | 57 | 25 | 6812 |
| 4/27/1995 | 1995 | 4 | 27 | 331 | 40 | 75 | 57.5 | 25.5 | 6837.5 |
| 4/28/1995 | 1995 | 4 | 28 | 332 | 39 | 75 | 57 | 25 | 6862.5 |
| 4/29/1995 | 1995 | 4 | 29 | 333 | 41 | 76 | 58.5 | 26.5 | 6889 |
| 4/30/1995 | 1995 | 4 | 30 | 334 | 51 | 80 | 65.5 | 33.5 | 6922.5 |
| 5/1/1995 | 1995 | 5 | 1 | 335 | 40 | 76 | 58 | 26 | 6948.5 |
| 5/2/1995 | 1995 | 5 | 2 | 336 | 47 | 73 | 60 | 28 | 6976.5 |
| 5/3/1995 | 1995 | 5 | 3 | 337 | 36 | 73 | 54.5 | 22.5 | 6999 |
| 5/4/1995 | 1995 | 5 | 4 | 338 | 31 | 72 | 51.5 | 19.5 | 7018.5 |
| 5/5/1995 | 1995 | 5 | 5 | 339 | 48 | 78 | 63 | 31 | 7049.5 |
| 5/6/1995 | 1995 | 5 | 6 | 340 | 30 | 73 | 51.5 | 19.5 | 7069 |
| 5/7/1995 | 1995 | 5 | 7 | 341 | 32 | 65 | 48.5 | 16.5 | 7085.5 |
| 5/8/1995 | 1995 | 5 | 8 | 342 | 32 | 48 | 40 | 8 | 7093.5 |
| 5/9/1995 | 1995 | 5 | 9 | 343 | 37 | 63 | 50 | 18 | 7111.5 |
| 5/10/1995 | 1995 | 5 | 10 | 344 | 31 | 74 | 52.5 | 20.5 | 7132 |
| 5/11/1995 | 1995 | 5 | 11 | 345 | 32 | 71 | 51.5 | 19.5 | 7151.5 |
| 5/12/1995 | 1995 | 5 | 12 | 346 | 48 | 78 | 63 | 31 | 7182.5 |
| 5/13/1995 | 1995 | 5 | 13 | 347 | 45 | 75 | 60 | 28 | 7210.5 |
| 5/14/1995 | 1995 | 5 | 14 | 348 | 41 | 76 | 58.5 | 26.5 | 7237 |
| 5/15/1995 | 1995 | 5 | 15 | 349 | 34 | 84 | 59 | 27 | 7264 |
| 5/16/1995 | 1995 | 5 | 16 | 350 | 46 | 87 | 66.5 | 34.5 | 7298.5 |
| 5/17/1995 | 1995 | 5 | 17 | 351 | 37 | 81 | 59 | 27 | 7325.5 |
| 5/18/1995 | 1995 | 5 | 18 | 352 | 36 | 60 | 48 | 16 | 7341.5 |
| 5/19/1995 | 1995 | 5 | 19 | 353 | 34 | 74 | 54 | 22 | 7363.5 |
| 5/20/1995 | 1995 | 5 | 20 | 354 | 42 | 81 | 61.5 | 29.5 | 7393 |
| 5/21/1995 | 1995 | 5 | 21 | 355 | 43 | 82 | 62.5 | 30.5 | 7423.5 |
| 5/22/1995 | 1995 | 5 | 22 | 356 | 46 | 84 | 65 | 33 | 7456.5 |
| 5/23/1995 | 1995 | 5 | 23 | 357 | 34 | 85 | 59.5 | 27.5 | 7484 |
| 5/24/1995 | 1995 | 5 | 24 | 358 | 44 | 74 | 59 | 27 | 7511 |
| 5/25/1995 | 1995 | 5 | 25 | 359 | 35 | 73 | 54 | 22 | 7533 |
| 5/26/1995 | 1995 | 5 | 26 | 360 | 32 | 79 | 55.5 | 23.5 | 7556.5 |
| 5/27/1995 | 1995 | 5 | 27 | 361 | 39 | 79 | 59 | 27 | 7583.5 |
| 5/28/1995 | 1995 | 5 | 28 | 362 | 45 | 75 | 60 | 28 | 7611.5 |
| 5/29/1995 | 1995 | 5 | 29 | 363 | 40 | 69 | 54.5 | 22.5 | 7634 |
| 5/30/1995 | 1995 | 5 | 30 | 364 | 35 | 68 | 51.5 | 19.5 | 7653.5 |
| 5/31/1995 | 1995 | 5 | 31 | 365 | 35 | 75 | 55 | 23 | 7676.5 |
| 6/1/1995 | 1995 | 6 | 1 | 1 | 38 | 80 | 59 | 27 | 27 |
| 6/2/1995 | 1995 | 6 | 2 | 2 | 46 | 85 | 65.5 | 33.5 | 60.5 |
| 6/3/1995 | 1995 | 6 | 3 | 3 | 36 | 85 | 60.5 | 28.5 | 89 |
| 6/4/1995 | 1995 | 6 | 4 | 4 | 40 | 76 | 58 | 26 | 115 |
| 6/5/1995 | 1995 | 6 | 5 | 5 | 39 | 79 | 59 | 27 | 142 |
| 6/6/1995 | 1995 | 6 | 6 | 6 | 43 | 85 | 64 | 32 | 174 |
| 6/7/1995 | 1995 | 6 | 7 | 7 | 46 | 85 | 65.5 | 33.5 | 207.5 |
| 6/8/1995 | 1995 | 6 | 8 | 8 | 46 | 82 | 64 | 32 | 239.5 |
| 6/9/1995 | 1995 | 6 | 9 | 9 | 34 | 81 | 57.5 | 25.5 | 265 |
| 6/10/1995 | 1995 | 6 | 10 | 10 | 38 | 82 | 60 | 28 | 293 |
| 6/11/1995 | 1995 | 6 | 11 | 11 | 39 | 80 | 59.5 | 27.5 | 320.5 |
| 6/12/1995 | 1995 | 6 | 12 | 12 | 43 | 86 | 64.5 | 32.5 | 353 |
| 6/13/1995 | 1995 | 6 | 13 | 13 | 45 | 91 | 68 | 36 | 389 |
| 6/14/1995 | 1995 | 6 | 14 | 14 | 49 | 94 | 71.5 | 39.5 | 428.5 |
| 6/15/1995 | 1995 | 6 | 15 | 15 | 51 | 90 | 70.5 | 38.5 | 467 |
| 6/16/1995 | 1995 | 6 | 16 | 16 | 46 | 84 | 65 | 33 | 500 |
| 6/17/1995 | 1995 | 6 | 17 | 17 | 60 | 85 | 72.5 | 40.5 | 540.5 |
| 6/18/1995 | 1995 | 6 | 18 | 18 | 37 | 84 | 60.5 | 28.5 | 569 |
| 6/19/1995 | 1995 | 6 | 19 | 19 | 42 | 89 | 65.5 | 33.5 | 602.5 |
| 6/20/1995 | 1995 | 6 | 20 | 20 | 43 | 92 | 67.5 | 35.5 | 638 |
| 6/21/1995 | 1995 | 6 | 21 | 21 | 45 | 92 | 68.5 | 36.5 | 674.5 |
| 6/22/1995 | 1995 | 6 | 22 | 22 | 42 | 91 | 66.5 | 34.5 | 709 |
| 6/23/1995 | 1995 | 6 | 23 | 23 | 44 | 88 | 66 | 34 | 743 |
| 6/24/1995 | 1995 | 6 | 24 | 24 | 44 | 91 | 67.5 | 35.5 | 778.5 |
| 6/25/1995 | 1995 | 6 | 25 | 25 | 45 | 89 | 67 | 35 | 813.5 |
| 6/26/1995 | 1995 | 6 | 26 | 26 | 46 | 88 | 67 | 35 | 848.5 |
| 6/27/1995 | 1995 | 6 | 27 | 27 | 46 | 84 | 65 | 33 | 881.5 |
| 6/28/1995 | 1995 | 6 | 28 | 28 | 46 | 86 | 66 | 34 | 915.5 |
| 6/29/1995 | 1995 | 6 | 29 | 29 | 47 | 86 | 66.5 | 34.5 | 950 |
| 6/30/1995 | 1995 | 6 | 30 | 30 | 50 | 90 | 70 | 38 | 988 |
| 7/1/1995 | 1995 | 7 | 1 | 31 | 50 | 75 | 62.5 | 30.5 | 1018.5 |
| 7/2/1995 | 1995 | 7 | 2 | 32 | 42 | 85 | 63.5 | 31.5 | 1050 |
| 7/3/1995 | 1995 | 7 | 3 | 33 | 59 | 84 | 71.5 | 39.5 | 1089.5 |
| 7/4/1995 | 1995 | 7 | 4 | 34 | 49 | 86 | 67.5 | 35.5 | 1125 |
| 7/5/1995 | 1995 | 7 | 5 | 35 | 40 | 83 | 61.5 | 29.5 | 1154.5 |
| 7/6/1995 | 1995 | 7 | 6 | 36 | 42 | 87 | 64.5 | 32.5 | 1187 |
| 7/7/1995 | 1995 | 7 | 7 | 37 | 56 | 95 | 75.5 | 43.5 | 1230.5 |
| 7/8/1995 | 1995 | 7 | 8 | 38 | 53 | 96 | 74.5 | 42.5 | 1273 |
| 7/9/1995 | 1995 | 7 | 9 | 39 | | 99 | 99 | 67 | 1340 |
| 7/10/1995 | 1995 | 7 | 10 | 40 | 53 | 95 | 74 | 42 | 1382 |
| 7/11/1995 | 1995 | 7 | 11 | 41 | 57 | 98 | 77.5 | 45.5 | 1427.5 |
| 7/12/1995 | 1995 | 7 | 12 | 42 | 56 | 95 | 75.5 | 43.5 | 1471 |
| 7/13/1995 | 1995 | 7 | 13 | 43 | 55 | 96 | 75.5 | 43.5 | 1514.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/14/1995 | 1995 | 7 | 14 | 44 | 59 | 92 | 75.5 | 43.5 | 1558 |
| 7/15/1995 | 1995 | 7 | 15 | 45 | 48 | 78 | 63 | 31 | 1589 |
| 7/16/1995 | 1995 | 7 | 16 | 46 | 48 | 88 | 68 | 36 | 1625 |
| 7/17/1995 | 1995 | 7 | 17 | 47 | 59 | 84 | 71.5 | 39.5 | 1664.5 |
| 7/18/1995 | 1995 | 7 | 18 | 48 | 57 | 78 | 67.5 | 35.5 | 1700 |
| 7/19/1995 | 1995 | 7 | 19 | 49 | 57 | 80 | 68.5 | 36.5 | 1736.5 |
| 7/20/1995 | 1995 | 7 | 20 | 50 | 50 | 87 | 68.5 | 36.5 | 1773 |
| 7/21/1995 | 1995 | 7 | 21 | 51 | 62 | 92 | 77 | 45 | 1818 |
| 7/22/1995 | 1995 | 7 | 22 | 52 | 62 | 87 | 74.5 | 42.5 | 1860.5 |
| 7/23/1995 | 1995 | 7 | 23 | 53 | 51 | 94 | 72.5 | 40.5 | 1901 |
| 7/24/1995 | 1995 | 7 | 24 | 54 | 46 | 91 | 68.5 | 36.5 | 1937.5 |
| 7/25/1995 | 1995 | 7 | 25 | 55 | 46 | 94 | 70 | 38 | 1975.5 |
| 7/26/1995 | 1995 | 7 | 26 | 56 | 46 | 97 | 71.5 | 39.5 | 2015 |
| 7/27/1995 | 1995 | 7 | 27 | 57 | 47 | 99 | 73 | 41 | 2056 |
| 7/28/1995 | 1995 | 7 | 28 | 58 | 52 | 102 | 77 | 45 | 2101 |
| 7/29/1995 | 1995 | 7 | 29 | 59 | 54 | 102 | 78 | 46 | 2147 |
| 7/30/1995 | 1995 | 7 | 30 | 60 | 54 | 99 | 76.5 | 44.5 | 2191.5 |
| 7/31/1995 | 1995 | 7 | 31 | 61 | 55 | 94 | 74.5 | 42.5 | 2234 |
| 8/1/1995 | 1995 | 8 | 1 | 62 | 58 | 98 | 78 | 46 | 2280 |
| 8/2/1995 | 1995 | 8 | 2 | 63 | 57 | 94 | 75.5 | 43.5 | 2323.5 |
| 8/3/1995 | 1995 | 8 | 3 | 64 | 56 | 92 | 74 | 42 | 2365.5 |
| 8/4/1995 | 1995 | 8 | 4 | 65 | 68 | 98 | 83 | 51 | 2416.5 |
| 8/5/1995 | 1995 | 8 | 5 | 66 | 52 | 96 | 74 | 42 | 2458.5 |
| 8/6/1995 | 1995 | 8 | 6 | 67 | 57 | 95 | 76 | 44 | 2502.5 |
| 8/7/1995 | 1995 | 8 | 7 | 68 | 62 | 96 | 79 | 47 | 2549.5 |
| 8/8/1995 | 1995 | 8 | 8 | 69 | 55 | 97 | 76 | 44 | 2593.5 |
| 8/9/1995 | 1995 | 8 | 9 | 70 | 60 | 94 | 77 | 45 | 2638.5 |
| 8/10/1995 | 1995 | 8 | 10 | 71 | 60 | 94 | 77 | 45 | 2683.5 |
| 8/11/1995 | 1995 | 8 | 11 | 72 | 59 | 92 | 75.5 | 43.5 | 2727 |
| 8/12/1995 | 1995 | 8 | 12 | 73 | 58 | 95 | 76.5 | 44.5 | 2771.5 |
| 8/13/1995 | 1995 | 8 | 13 | 74 | 56 | 90 | 73 | 41 | 2812.5 |
| 8/14/1995 | 1995 | 8 | 14 | 75 | 57 | 90 | 73.5 | 41.5 | 2854 |
| 8/15/1995 | 1995 | 8 | 15 | 76 | 54 | 78 | 66 | 34 | 2888 |
| 8/16/1995 | 1995 | 8 | 16 | 77 | 63 | 90 | 76.5 | 44.5 | 2932.5 |
| 8/17/1995 | 1995 | 8 | 17 | 78 | 58 | 89 | 73.5 | 41.5 | 2974 |
| 8/18/1995 | 1995 | 8 | 18 | 79 | 56 | 87 | 71.5 | 39.5 | 3013.5 |
| 8/19/1995 | 1995 | 8 | 19 | 80 | 56 | 87 | 71.5 | 39.5 | 3053 |
| 8/20/1995 | 1995 | 8 | 20 | 81 | 56 | 85 | 70.5 | 38.5 | 3091.5 |
| 8/21/1995 | 1995 | 8 | 21 | 82 | 57 | 85 | 71 | 39 | 3130.5 |
| 8/22/1995 | 1995 | 8 | 22 | 83 | 53 | 85 | 69 | 37 | 3167.5 |
| 8/23/1995 | 1995 | 8 | 23 | 84 | 53 | 84 | 68.5 | 36.5 | 3204 |
| 8/24/1995 | 1995 | 8 | 24 | 85 | 56 | 88 | 72 | 40 | 3244 |
| 8/25/1995 | 1995 | 8 | 25 | 86 | 56 | 82 | 69 | 37 | 3281 |
| 8/26/1995 | 1995 | 8 | 26 | 87 | 57 | 89 | 73 | 41 | 3322 |
| 8/27/1995 | 1995 | 8 | 27 | 88 | 58 | 87 | 72.5 | 40.5 | 3362.5 |
| 8/28/1995 | 1995 | 8 | 28 | 89 | 58 | 87 | 72.5 | 40.5 | 3403 |
| 8/29/1995 | 1995 | 8 | 29 | 90 | 57 | 89 | 73 | 41 | 3444 |
| 8/30/1995 | 1995 | 8 | 30 | 91 | 55 | 90 | 72.5 | 40.5 | 3484.5 |
| 8/31/1995 | 1995 | 8 | 31 | 92 | 56 | 94 | 75 | 43 | 3527.5 |
| 9/1/1995 | 1995 | 9 | 1 | 93 | 54 | 94 | 74 | 42 | 3569.5 |
| 9/2/1995 | 1995 | 9 | 2 | 94 | 49 | 93 | 71 | 39 | 3608.5 |
| 9/3/1995 | 1995 | 9 | 3 | 95 | 49 | 93 | 71 | 39 | 3647.5 |
| 9/4/1995 | 1995 | 9 | 4 | 96 | 50 | 92 | 71 | 39 | 3686.5 |
| 9/5/1995 | 1995 | 9 | 5 | 97 | 52 | 94 | 73 | 41 | 3727.5 |
| 9/6/1995 | 1995 | 9 | 6 | 98 | 53 | 87 | 70 | 38 | 3765.5 |
| 9/7/1995 | 1995 | 9 | 7 | 99 | 54 | 82 | 68 | 36 | 3801.5 |
| 9/8/1995 | 1995 | 9 | 8 | 100 | 54 | 87 | 70.5 | 38.5 | 3840 |
| 9/9/1995 | 1995 | 9 | 9 | 101 | 50 | 80 | 65 | 33 | 3873 |
| 9/10/1995 | 1995 | 9 | 10 | 102 | 46 | 82 | 64 | 32 | 3905 |
| 9/11/1995 | 1995 | 9 | 11 | 103 | 45 | 85 | 65 | 33 | 3938 |
| 9/12/1995 | 1995 | 9 | 12 | 104 | 39 | 85 | 62 | 30 | 3968 |
| 9/13/1995 | 1995 | 9 | 13 | 105 | 45 | 86 | 65.5 | 33.5 | 4001.5 |
| 9/14/1995 | 1995 | 9 | 14 | 106 | 49 | 83 | 66 | 34 | 4035.5 |
| 9/15/1995 | 1995 | 9 | 15 | 107 | 41 | 72 | 56.5 | 24.5 | 4060 |
| 9/16/1995 | 1995 | 9 | 16 | 108 | 47 | 82 | 64.5 | 32.5 | 4092.5 |
| 9/17/1995 | 1995 | 9 | 17 | 109 | 45 | 82 | 63.5 | 31.5 | 4124 |
| 9/18/1995 | 1995 | 9 | 18 | 110 | 39 | 80 | 59.5 | 27.5 | 4151.5 |
| 9/19/1995 | 1995 | 9 | 19 | 111 | 42 | 80 | 61 | 29 | 4180.5 |
| 9/20/1995 | 1995 | 9 | 20 | 112 | 44 | 84 | 64 | 32 | 4212.5 |
| 9/21/1995 | 1995 | 9 | 21 | 113 | 36 | 75 | 55.5 | 23.5 | 4236 |
| 9/22/1995 | 1995 | 9 | 22 | 114 | 37 | 70 | 53.5 | 21.5 | 4257.5 |
| 9/23/1995 | 1995 | 9 | 23 | 115 | 45 | 81 | 63 | 31 | 4288.5 |
| 9/24/1995 | 1995 | 9 | 24 | 116 | 36 | 81 | 58.5 | 26.5 | 4315 |
| 9/25/1995 | 1995 | 9 | 25 | 117 | 40 | 79 | 59.5 | 27.5 | 4342.5 |
| 9/26/1995 | 1995 | 9 | 26 | 118 | 41 | 79 | 60 | 28 | 4370.5 |
| 9/27/1995 | 1995 | 9 | 27 | 119 | 51 | 83 | 67 | 35 | 4405.5 |
| 9/28/1995 | 1995 | 9 | 28 | 120 | 48 | 83 | 65.5 | 33.5 | 4439 |
| 9/29/1995 | 1995 | 9 | 29 | 121 | 35 | 73 | 54 | 22 | 4461 |
| 9/30/1995 | 1995 | 9 | 30 | 122 | 33 | 73 | 53 | 21 | 4482 |
| 10/1/1995 | 1995 | 10 | 1 | 123 | 34 | 77 | 55.5 | 23.5 | 4505.5 |
| 10/2/1995 | 1995 | 10 | 2 | 124 | 32 | 75 | 53.5 | 21.5 | 4527 |
| 10/3/1995 | 1995 | 10 | 3 | 125 | 45 | 81 | 63 | 31 | 4558 |
| 10/4/1995 | 1995 | 10 | 4 | 126 | 28 | 75 | 51.5 | 19.5 | 4577.5 |
| 10/5/1995 | 1995 | 10 | 5 | 127 | 21 | 75 | 48 | 16 | 4593.5 |
| 10/6/1995 | 1995 | 10 | 6 | 128 | 30 | 74 | 52 | 20 | 4613.5 |
| 10/7/1995 | 1995 | 10 | 7 | 129 | 29 | 79 | 54 | 22 | 4635.5 |
| 10/8/1995 | 1995 | 10 | 8 | 130 | 26 | 79 | 52.5 | 20.5 | 4656 |
| 10/9/1995 | 1995 | 10 | 9 | 131 | 27 | 78 | 52.5 | 20.5 | 4676.5 |
| 10/10/1995 | 1995 | 10 | 10 | 132 | 27 | 79 | 53 | 21 | 4697.5 |
| 10/11/1995 | 1995 | 10 | 11 | 133 | 33 | 83 | 58 | 26 | 4723.5 |
| 10/12/1995 | 1995 | 10 | 12 | 134 | 34 | 83 | 58.5 | 26.5 | 4750 |
| 10/13/1995 | 1995 | 10 | 13 | 135 | 25 | 77 | 51 | 19 | 4769 |
| 10/14/1995 | 1995 | 10 | 14 | 136 | 25 | 79 | 52 | 20 | 4789 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/15/1995 | 1995 | 10 | 15 | 137 | 31 | 83 | 57 | 25 | 4814 |
| 10/16/1995 | 1995 | 10 | 16 | 138 | 32 | 81 | 56.5 | 24.5 | 4838.5 |
| 10/17/1995 | 1995 | 10 | 17 | 139 | 29 | 78 | 53.5 | 21.5 | 4860 |
| 10/18/1995 | 1995 | 10 | 18 | 140 | 32 | 81 | 56.5 | 24.5 | 4884.5 |
| 10/19/1995 | 1995 | 10 | 19 | 141 | 24 | 77 | 50.5 | 18.5 | 4903 |
| 10/20/1995 | 1995 | 10 | 20 | 142 | 24 | 77 | 50.5 | 18.5 | 4921.5 |
| 10/21/1995 | 1995 | 10 | 21 | 143 | 35 | 79 | 57 | 25 | 4946.5 |
| 10/22/1995 | 1995 | 10 | 22 | 144 | 23 | 68 | 45.5 | 13.5 | 4960 |
| 10/23/1995 | 1995 | 10 | 23 | 145 | 23 | 61 | 42 | 10 | 4970 |
| 10/24/1995 | 1995 | 10 | 24 | 146 | 21 | 72 | 46.5 | 14.5 | 4984.5 |
| 10/25/1995 | 1995 | 10 | 25 | 147 | 22 | 73 | 47.5 | 15.5 | 5000 |
| 10/26/1995 | 1995 | 10 | 26 | 148 | 23 | 75 | 49 | 17 | 5017 |
| 10/27/1995 | 1995 | 10 | 27 | 149 | 26 | 78 | 52 | 20 | 5037 |
| 10/28/1995 | 1995 | 10 | 28 | 150 | 30 | 76 | 53 | 21 | 5058 |
| 10/29/1995 | 1995 | 10 | 29 | 151 | 28 | 72 | 50 | 18 | 5076 |
| 10/30/1995 | 1995 | 10 | 30 | 152 | 28 | 77 | 52.5 | 20.5 | 5096.5 |
| 10/31/1995 | 1995 | 10 | 31 | 153 | 44 | 69 | 56.5 | 24.5 | 5121 |
| 11/1/1995 | 1995 | 11 | 1 | 154 | 37 | 58 | 47.5 | 15.5 | 5136.5 |
| 11/2/1995 | 1995 | 11 | 2 | 155 | 19 | 60 | 39.5 | 7.5 | 5144 |
| 11/3/1995 | 1995 | 11 | 3 | 156 | 20 | 62 | 41 | 9 | 5153 |
| 11/4/1995 | 1995 | 11 | 4 | 157 | 21 | 56 | 38.5 | 6.5 | 5159.5 |
| 11/5/1995 | 1995 | 11 | 5 | 158 | 22 | 54 | 38 | 6 | 5165.5 |
| 11/6/1995 | 1995 | 11 | 6 | 159 | 31 | 56 | 43.5 | 11.5 | 5177 |
| 11/7/1995 | 1995 | 11 | 7 | 160 | 25 | 65 | 45 | 13 | 5190 |
| 11/8/1995 | 1995 | 11 | 8 | 161 | 24 | 72 | 48 | 16 | 5206 |
| 11/9/1995 | 1995 | 11 | 9 | 162 | 45 | 68 | 56.5 | 24.5 | 5230.5 |
| 11/10/1995 | 1995 | 11 | 10 | 163 | 18 | 68 | 43 | 11 | 5241.5 |
| 11/11/1995 | 1995 | 11 | 11 | 164 | 20 | 64 | 42 | 10 | 5251.5 |
| 11/12/1995 | 1995 | 11 | 12 | 165 | 24 | 74 | 49 | 17 | 5268.5 |
| 11/13/1995 | 1995 | 11 | 13 | 166 | 25 | 75 | 50 | 18 | 5286.5 |
| 11/14/1995 | 1995 | 11 | 14 | 167 | 23 | 67 | 45 | 13 | 5299.5 |
| 11/15/1995 | 1995 | 11 | 15 | 168 | 23 | 65 | 44 | 12 | 5311.5 |
| 11/16/1995 | 1995 | 11 | 16 | 169 | 24 | 70 | 47 | 15 | 5326.5 |
| 11/17/1995 | 1995 | 11 | 17 | 170 | 20 | 68 | 44 | 12 | 5338.5 |
| 11/18/1995 | 1995 | 11 | 18 | 171 | 20 | 68 | 44 | 12 | 5350.5 |
| 11/19/1995 | 1995 | 11 | 19 | 172 | 20 | 69 | 44.5 | 12.5 | 5363 |
| 11/20/1995 | 1995 | 11 | 20 | 173 | 20 | 72 | 46 | 14 | 5377 |
| 11/21/1995 | 1995 | 11 | 21 | 174 | 20 | 67 | 43.5 | 11.5 | 5388.5 |
| 11/22/1995 | 1995 | 11 | 22 | 175 | 19 | 70 | 44.5 | 12.5 | 5401 |
| 11/23/1995 | 1995 | 11 | 23 | 176 | 16 | 70 | 43 | 11 | 5412 |
| 11/24/1995 | 1995 | 11 | 24 | 177 | 19 | 70 | 44.5 | 12.5 | 5424.5 |
| 11/25/1995 | 1995 | 11 | 25 | 178 | 31 | 73 | 52 | 20 | 5444.5 |
| 11/26/1995 | 1995 | 11 | 26 | 179 | 16 | 67 | 41.5 | 9.5 | 5454 |
| 11/27/1995 | 1995 | 11 | 27 | 180 | 9 | 45 | 27 | -5 | 5449 |
| 11/28/1995 | 1995 | 11 | 28 | 181 | 19 | 54 | 36.5 | 4.5 | 5453.5 |
| 11/29/1995 | 1995 | 11 | 29 | 182 | 18 | 59 | 38.5 | 6.5 | 5460 |
| 11/30/1995 | 1995 | 11 | 30 | 183 | 16 | 69 | 42.5 | 10.5 | 5470.5 |
| 12/1/1995 | 1995 | 12 | 1 | 184 | 17 | 70 | 43.5 | 11.5 | 5482 |
| 12/2/1995 | 1995 | 12 | 2 | 185 | 22 | 66 | 44 | 12 | 5494 |
| 12/3/1995 | 1995 | 12 | 3 | 186 | 22 | 66 | 44 | 12 | 5506 |
| 12/4/1995 | 1995 | 12 | 4 | 187 | 22 | 68 | 45 | 13 | 5519 |
| 12/5/1995 | 1995 | 12 | 5 | 188 | 25 | 65 | 45 | 13 | 5532 |
| 12/6/1995 | 1995 | 12 | 6 | 189 | 24 | 68 | 46 | 14 | 5546 |
| 12/7/1995 | 1995 | 12 | 7 | 190 | 24 | 57 | 40.5 | 8.5 | 5554.5 |
| 12/8/1995 | 1995 | 12 | 8 | 191 | 14 | 52 | 33 | 1 | 5555.5 |
| 12/9/1995 | 1995 | 12 | 9 | 192 | 15 | 50 | 32.5 | 0.5 | 5556 |
| 12/10/1995 | 1995 | 12 | 10 | 193 | 13 | 60 | 36.5 | 4.5 | 5560.5 |
| 12/11/1995 | 1995 | 12 | 11 | 194 | 27 | 68 | 47.5 | 15.5 | 5576 |
| 12/12/1995 | 1995 | 12 | 12 | 195 | 34 | 56 | 45 | 13 | 5589 |
| 12/13/1995 | 1995 | 12 | 13 | 196 | 26 | 65 | 45.5 | 13.5 | 5602.5 |
| 12/14/1995 | 1995 | 12 | 14 | 197 | 16 | 61 | 38.5 | 6.5 | 5609 |
| 12/15/1995 | 1995 | 12 | 15 | 198 | 29 | 49 | 39 | 7 | 5616 |
| 12/16/1995 | 1995 | 12 | 16 | 199 | 21 | 44 | 32.5 | 0.5 | 5616.5 |
| 12/17/1995 | 1995 | 12 | 17 | 200 | 20 | 45 | 32.5 | 0.5 | 5617 |
| 12/18/1995 | 1995 | 12 | 18 | 201 | 10 | 45 | 27.5 | -4.5 | 5612.5 |
| 12/19/1995 | 1995 | 12 | 19 | 202 | 10 | 43 | 26.5 | -5.5 | 5607 |
| 12/20/1995 | 1995 | 12 | 20 | 203 | 10 | 42 | 26 | -6 | 5601 |
| 12/21/1995 | 1995 | 12 | 21 | 204 | 11 | 40 | 25.5 | -6.5 | 5594.5 |
| 12/22/1995 | 1995 | 12 | 22 | 205 | 8 | 36 | 22 | -10 | 5584.5 |
| 12/23/1995 | 1995 | 12 | 23 | 206 | 12 | 41 | 26.5 | -5.5 | 5579 |
| 12/24/1995 | 1995 | 12 | 24 | 207 | 3 | 44 | 23.5 | -8.5 | 5570.5 |
| 12/25/1995 | 1995 | 12 | 25 | 208 | 2 | 46 | 24 | -8 | 5562.5 |
| 12/26/1995 | 1995 | 12 | 26 | 209 | 4 | 52 | 28 | -4 | 5558.5 |
| 12/27/1995 | 1995 | 12 | 27 | 210 | 7 | 52 | 29.5 | -2.5 | 5556 |
| 12/28/1995 | 1995 | 12 | 28 | 211 | 17 | 46 | 31.5 | -0.5 | 5555.5 |
| 12/29/1995 | 1995 | 12 | 29 | 212 | 15 | 43 | 29 | -3 | 5552.5 |
| 12/30/1995 | 1995 | 12 | 30 | 213 | 20 | 51 | 35.5 | 3.5 | 5556 |
| 12/31/1995 | 1995 | 12 | 31 | 214 | 20 | 54 | 37 | 5 | 5561 |
| 1/1/1996 | 1996 | 1 | 1 | 215 | 16 | 44 | 30 | -2 | 5559 |
| 1/2/1996 | 1996 | 1 | 2 | 216 | 12 | 36 | 24 | -8 | 5551 |
| 1/3/1996 | 1996 | 1 | 3 | 217 | 33 | 57 | 45 | 13 | 5564 |
| 1/4/1996 | 1996 | 1 | 4 | 218 | 19 | 57 | 38 | 6 | 5570 |
| 1/5/1996 | 1996 | 1 | 5 | 219 | 21 | 55 | 38 | 6 | 5576 |
| 1/6/1996 | 1996 | 1 | 6 | 220 | 15 | 48 | 31.5 | -0.5 | 5575.5 |
| 1/7/1996 | 1996 | 1 | 7 | 221 | 11 | 58 | 34.5 | 2.5 | 5578 |
| 1/8/1996 | 1996 | 1 | 8 | 222 | 12 | 66 | 39 | 7 | 5585 |
| 1/9/1996 | 1996 | 1 | 9 | 223 | 17 | 67 | 42 | 10 | 5595 |
| 1/10/1996 | 1996 | 1 | 10 | 224 | 14 | 67 | 40.5 | 8.5 | 5603.5 |
| 1/11/1996 | 1996 | 1 | 11 | 225 | 16 | 56 | 36 | 4 | 5607.5 |
| 1/12/1996 | 1996 | 1 | 12 | 226 | 14 | 59 | 36.5 | 4.5 | 5612 |
| 1/13/1996 | 1996 | 1 | 13 | 227 | 19 | 70 | 44.5 | 12.5 | 5624.5 |
| 1/14/1996 | 1996 | 1 | 14 | 228 | 13 | 70 | 41.5 | 9.5 | 5634 |
| 1/15/1996 | 1996 | 1 | 15 | 229 | 23 | 70 | 46.5 | 14.5 | 5648.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/16/1996 | 1996 | 1 | 16 | 230 | 35 | 61 | 48 | 16 | 5664.5 |
| 1/17/1996 | 1996 | 1 | 17 | 231 | 18 | 43 | 30.5 | -1.5 | 5663 |
| 1/18/1996 | 1996 | 1 | 18 | 232 | 19 | 38 | 28.5 | -3.5 | 5659.5 |
| 1/19/1996 | 1996 | 1 | 19 | 233 | 20 | 48 | 34 | 2 | 5661.5 |
| 1/20/1996 | 1996 | 1 | 20 | 234 | 10 | 45 | 27.5 | -4.5 | 5657 |
| 1/21/1996 | 1996 | 1 | 21 | 235 | 17 | 51 | 34 | 2 | 5659 |
| 1/22/1996 | 1996 | 1 | 22 | 236 | 11 | 44 | 27.5 | -4.5 | 5654.5 |
| 1/23/1996 | 1996 | 1 | 23 | 237 | 11 | 38 | 24.5 | -7.5 | 5647 |
| 1/24/1996 | 1996 | 1 | 24 | 238 | 22 | 48 | 35 | 3 | 5650 |
| 1/25/1996 | 1996 | 1 | 25 | 239 | 6 | 49 | 27.5 | -4.5 | 5645.5 |
| 1/26/1996 | 1996 | 1 | 26 | 240 | 6 | 41 | 23.5 | -8.5 | 5637 |
| 1/27/1996 | 1996 | 1 | 27 | 241 | 35 | 55 | 45 | 13 | 5650 |
| 1/28/1996 | 1996 | 1 | 28 | 242 | 17 | 55 | 36 | 4 | 5654 |
| 1/29/1996 | 1996 | 1 | 29 | 243 | 26 | 55 | 40.5 | 8.5 | 5662.5 |
| 1/30/1996 | 1996 | 1 | 30 | 244 | 36 | 58 | 47 | 15 | 5677.5 |
| 1/31/1996 | 1996 | 1 | 31 | 245 | 34 | 55 | 44.5 | 12.5 | 5690 |
| 2/1/1996 | 1996 | 2 | 1 | 246 | 29 | 49 | 39 | 7 | 5697 |
| 2/2/1996 | 1996 | 2 | 2 | 247 | 16 | 47 | 31.5 | -0.5 | 5696.5 |
| 2/3/1996 | 1996 | 2 | 3 | 248 | 8 | 46 | 27 | -5 | 5691.5 |
| 2/4/1996 | 1996 | 2 | 4 | 249 | 20 | 58 | 39 | 7 | 5698.5 |
| 2/5/1996 | 1996 | 2 | 5 | 250 | 25 | 67 | 46 | 14 | 5712.5 |
| 2/6/1996 | 1996 | 2 | 6 | 251 | 22 | 66 | 44 | 12 | 5724.5 |
| 2/7/1996 | 1996 | 2 | 7 | 252 | 22 | 66 | 44 | 12 | 5736.5 |
| 2/8/1996 | 1996 | 2 | 8 | 253 | 21 | 67 | 44 | 12 | 5748.5 |
| 2/9/1996 | 1996 | 2 | 9 | 254 | 19 | 70 | 44.5 | 12.5 | 5761 |
| 2/10/1996 | 1996 | 2 | 10 | 255 | 30 | 67 | 48.5 | 16.5 | 5777.5 |
| 2/11/1996 | 1996 | 2 | 11 | 256 | 28 | 51 | 39.5 | 7.5 | 5785 |
| 2/12/1996 | 1996 | 2 | 12 | 257 | 30 | 58 | 44 | 12 | 5797 |
| 2/13/1996 | 1996 | 2 | 13 | 258 | 20 | 52 | 36 | 4 | 5801 |
| 2/14/1996 | 1996 | 2 | 14 | 259 | 21 | 67 | 44 | 12 | 5813 |
| 2/15/1996 | 1996 | 2 | 15 | 260 | 19 | 71 | 45 | 13 | 5826 |
| 2/16/1996 | 1996 | 2 | 16 | 261 | 23 | 72 | 47.5 | 15.5 | 5841.5 |
| 2/17/1996 | 1996 | 2 | 17 | 262 | 36 | 71 | 53.5 | 21.5 | 5863 |
| 2/18/1996 | 1996 | 2 | 18 | 263 | 19 | 65 | 42 | 10 | 5873 |
| 2/19/1996 | 1996 | 2 | 19 | 264 | 46 | 65 | 55.5 | 23.5 | 5896.5 |
| 2/20/1996 | 1996 | 2 | 20 | 265 | 40 | 63 | 51.5 | 19.5 | 5916 |
| 2/21/1996 | 1996 | 2 | 21 | 266 | 37 | 70 | 53.5 | 21.5 | 5937.5 |
| 2/22/1996 | 1996 | 2 | 22 | 267 | 22 | 61 | 41.5 | 9.5 | 5947 |
| 2/23/1996 | 1996 | 2 | 23 | 268 | 17 | 52 | 34.5 | 2.5 | 5949.5 |
| 2/24/1996 | 1996 | 2 | 24 | 269 | 32 | 58 | 45 | 13 | 5962.5 |
| 2/25/1996 | 1996 | 2 | 25 | 270 | 27 | 62 | 44.5 | 12.5 | 5975 |
| 2/26/1996 | 1996 | 2 | 26 | 271 | 7 | 40 | 23.5 | -8.5 | 5966.5 |
| 2/27/1996 | 1996 | 2 | 27 | 272 | 23 | 43 | 33 | 1 | 5967.5 |
| 2/28/1996 | 1996 | 2 | 28 | 273 | 21 | 40 | 30.5 | -1.5 | 5966 |
| 2/29/1996 | 1996 | 2 | 29 | 274 | 16 | 44 | 30 | -2 | 5964 |
| 3/1/1996 | 1996 | 3 | 1 | 275 | 13 | 52 | 32.5 | 0.5 | 5964.5 |
| 3/2/1996 | 1996 | 3 | 2 | 276 | 13 | 59 | 36 | 4 | 5968.5 |
| 3/3/1996 | 1996 | 3 | 3 | 277 | 36 | 64 | 50 | 18 | 5986.5 |
| 3/4/1996 | 1996 | 3 | 4 | 278 | 36 | 57 | 46.5 | 14.5 | 6001 |
| 3/5/1996 | 1996 | 3 | 5 | 279 | 33 | 60 | 46.5 | 14.5 | 6015.5 |
| 3/6/1996 | 1996 | 3 | 6 | 280 | 14 | 46 | 30 | -2 | 6013.5 |
| 3/7/1996 | 1996 | 3 | 7 | 281 | 20 | 56 | 38 | 6 | 6019.5 |
| 3/8/1996 | 1996 | 3 | 8 | 282 | 18 | 66 | 42 | 10 | 6029.5 |
| 3/9/1996 | 1996 | 3 | 9 | 283 | 21 | 70 | 45.5 | 13.5 | 6043 |
| 3/10/1996 | 1996 | 3 | 10 | 284 | 25 | 73 | 49 | 17 | 6060 |
| 3/11/1996 | 1996 | 3 | 11 | 285 | 38 | 72 | 55 | 23 | 6083 |
| 3/12/1996 | 1996 | 3 | 12 | 286 | 28 | 68 | 48 | 16 | 6099 |
| 3/13/1996 | 1996 | 3 | 13 | 287 | 27 | 51 | 39 | 7 | 6106 |
| 3/14/1996 | 1996 | 3 | 14 | 288 | 16 | 51 | 33.5 | 1.5 | 6107.5 |
| 3/15/1996 | 1996 | 3 | 15 | 289 | 25 | 51 | 38 | 6 | 6113.5 |
| 3/16/1996 | 1996 | 3 | 16 | 290 | 25 | 51 | 38 | 6 | 6119.5 |
| 3/17/1996 | 1996 | 3 | 17 | 291 | 22 | 63 | 42.5 | 10.5 | 6130 |
| 3/18/1996 | 1996 | 3 | 18 | 292 | 14 | 55 | 34.5 | 2.5 | 6132.5 |
| 3/19/1996 | 1996 | 3 | 19 | 293 | 17 | 62 | 39.5 | 7.5 | 6140 |
| 3/20/1996 | 1996 | 3 | 20 | 294 | 20 | 71 | 45.5 | 13.5 | 6153.5 |
| 3/21/1996 | 1996 | 3 | 21 | 295 | 30 | 70 | 50 | 18 | 6171.5 |
| 3/22/1996 | 1996 | 3 | 22 | 296 | 37 | 67 | 52 | 20 | 6191.5 |
| 3/23/1996 | 1996 | 3 | 23 | 297 | 25 | 68 | 46.5 | 14.5 | 6206 |
| 3/24/1996 | 1996 | 3 | 24 | 298 | 21 | 54 | 37.5 | 5.5 | 6211.5 |
| 3/25/1996 | 1996 | 3 | 25 | 299 | 27 | 61 | 44 | 12 | 6223.5 |
| 3/26/1996 | 1996 | 3 | 26 | 300 | 17 | 56 | 36.5 | 4.5 | 6228 |
| 3/27/1996 | 1996 | 3 | 27 | 301 | 32 | 70 | 51 | 19 | 6247 |
| 3/28/1996 | 1996 | 3 | 28 | 302 | 30 | 70 | 50 | 18 | 6265 |
| 3/29/1996 | 1996 | 3 | 29 | 303 | 27 | | 27 | -5 | 6260 |
| 3/30/1996 | 1996 | 3 | 30 | 304 | 21 | 64 | 42.5 | 10.5 | 6270.5 |
| 3/31/1996 | 1996 | 3 | 31 | 305 | 23 | 70 | 46.5 | 14.5 | 6285 |
| 4/1/1996 | 1996 | 4 | 1 | 306 | 30 | 75 | 52.5 | 20.5 | 6305.5 |
| 4/2/1996 | 1996 | 4 | 2 | 307 | 33 | 73 | 53 | 21 | 6326.5 |
| 4/3/1996 | 1996 | 4 | 3 | 308 | 36 | 66 | 51 | 19 | 6345.5 |
| 4/4/1996 | 1996 | 4 | 4 | 309 | 35 | 54 | 44.5 | 12.5 | 6358 |
| 4/5/1996 | 1996 | 4 | 5 | 310 | 16 | 48 | 32 | 0 | 6358 |
| 4/6/1996 | 1996 | 4 | 6 | 311 | 23 | 69 | 46 | 14 | 6372 |
| 4/7/1996 | 1996 | 4 | 7 | 312 | 28 | 75 | 51.5 | 19.5 | 6391.5 |
| 4/8/1996 | 1996 | 4 | 8 | 313 | 30 | 79 | 54.5 | 22.5 | 6414 |
| 4/9/1996 | 1996 | 4 | 9 | 314 | 39 | 82 | 60.5 | 28.5 | 6442.5 |
| 4/10/1996 | 1996 | 4 | 10 | 315 | 35 | 79 | 57 | 25 | 6467.5 |
| 4/11/1996 | 1996 | 4 | 11 | 316 | 29 | 67 | 48 | 16 | 6483.5 |
| 4/12/1996 | 1996 | 4 | 12 | 317 | 30 | 70 | 50 | 18 | 6501.5 |
| 4/13/1996 | 1996 | 4 | 13 | 318 | 29 | 53 | 41 | 9 | 6510.5 |
| 4/14/1996 | 1996 | 4 | 14 | 319 | 20 | 60 | 40 | 8 | 6518.5 |
| 4/15/1996 | 1996 | 4 | 15 | 320 | 20 | 66 | 43 | 11 | 6529.5 |
| 4/16/1996 | 1996 | 4 | 16 | 321 | 21 | 77 | 49 | 17 | 6546.5 |
| 4/17/1996 | 1996 | 4 | 17 | 322 | 40 | 77 | 58.5 | 26.5 | 6573 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/18/1996 | 1996 | 4 | 18 | 323 | 34 | 71 | 52.5 | 20.5 | 6593.5 |
| 4/19/1996 | 1996 | 4 | 19 | 324 | 24 | 64 | 44 | 12 | 6605.5 |
| 4/20/1996 | 1996 | 4 | 20 | 325 | 29 | 68 | 48.5 | 16.5 | 6622 |
| 4/21/1996 | 1996 | 4 | 21 | 326 | 25 | 67 | 46 | 14 | 6636 |
| 4/22/1996 | 1996 | 4 | 22 | 327 | 32 | 71 | 51.5 | 19.5 | 6655.5 |
| 4/23/1996 | 1996 | 4 | 23 | 328 | 30 | 82 | 56 | 24 | 6679.5 |
| 4/24/1996 | 1996 | 4 | 24 | 329 | 52 | 83 | 67.5 | 35.5 | 6715 |
| 4/25/1996 | 1996 | 4 | 25 | 330 | 38 | 85 | 61.5 | 29.5 | 6744.5 |
| 4/26/1996 | 1996 | 4 | 26 | 331 | 37 | 87 | 62 | 30 | 6774.5 |
| 4/27/1996 | 1996 | 4 | 27 | 332 | 39 | 85 | 62 | 30 | 6804.5 |
| 4/28/1996 | 1996 | 4 | 28 | 333 | 22 | 60 | 41 | 9 | 6813.5 |
| 4/29/1996 | 1996 | 4 | 29 | 334 | 25 | 69 | 47 | 15 | 6828.5 |
| 4/30/1996 | 1996 | 4 | 30 | 335 | 31 | 81 | 56 | 24 | 6852.5 |
| 5/1/1996 | 1996 | 5 | 1 | 336 | 32 | 82 | 57 | 25 | 6877.5 |
| 5/2/1996 | 1996 | 5 | 2 | 337 | 50 | 83 | 66.5 | 34.5 | 6912 |
| 5/3/1996 | 1996 | 5 | 3 | 338 | 43 | 84 | 63.5 | 31.5 | 6943.5 |
| 5/4/1996 | 1996 | 5 | 4 | 339 | 40 | 80 | 60 | 28 | 6971.5 |
| 5/5/1996 | 1996 | 5 | 5 | 340 | 37 | 85 | 61 | 29 | 7000.5 |
| 5/6/1996 | 1996 | 5 | 6 | 341 | 45 | 86 | 65.5 | 33.5 | 7034 |
| 5/7/1996 | 1996 | 5 | 7 | 342 | 40 | 87 | 63.5 | 31.5 | 7065.5 |
| 5/8/1996 | 1996 | 5 | 8 | 343 | 39 | 86 | 62.5 | 30.5 | 7096 |
| 5/9/1996 | 1996 | 5 | 9 | 344 | 41 | 85 | 63 | 31 | 7127 |
| 5/10/1996 | 1996 | 5 | 10 | 345 | 37 | 85 | 61 | 29 | 7156 |
| 5/11/1996 | 1996 | 5 | 11 | 346 | 41 | 92 | 66.5 | 34.5 | 7190.5 |
| 5/12/1996 | 1996 | 5 | 12 | 347 | 41 | 94 | 67.5 | 35.5 | 7226 |
| 5/13/1996 | 1996 | 5 | 13 | 348 | 45 | 91 | 68 | 36 | 7262 |
| 5/14/1996 | 1996 | 5 | 14 | 349 | 50 | 87 | 68.5 | 36.5 | 7298.5 |
| 5/15/1996 | 1996 | 5 | 15 | 350 | 53 | 88 | 70.5 | 38.5 | 7337 |
| 5/16/1996 | 1996 | 5 | 16 | 351 | 58 | 90 | 74 | 42 | 7379 |
| 5/17/1996 | 1996 | 5 | 17 | 352 | 47 | 87 | 67 | 35 | 7414 |
| 5/18/1996 | 1996 | 5 | 18 | 353 | 58 | 91 | 74.5 | 42.5 | 7456.5 |
| 5/19/1996 | 1996 | 5 | 19 | 354 | 55 | 90 | 72.5 | 40.5 | 7497 |
| 5/20/1996 | 1996 | 5 | 20 | 355 | 45 | 87 | 66 | 34 | 7531 |
| 5/21/1996 | 1996 | 5 | 21 | 356 | 48 | 90 | 69 | 37 | 7568 |
| 5/22/1996 | 1996 | 5 | 22 | 357 | 50 | 88 | 69 | 37 | 7605 |
| 5/23/1996 | 1996 | 5 | 23 | 358 | 42 | 83 | 62.5 | 30.5 | 7635.5 |
| 5/24/1996 | 1996 | 5 | 24 | 359 | 50 | 80 | 65 | 33 | 7668.5 |
| 5/25/1996 | 1996 | 5 | 25 | 360 | 38 | 76 | 57 | 25 | 7693.5 |
| 5/26/1996 | 1996 | 5 | 26 | 361 | 35 | 66 | 50.5 | 18.5 | 7712 |
| 5/27/1996 | 1996 | 5 | 27 | 362 | 40 | 80 | 60 | 28 | 7740 |
| 5/28/1996 | 1996 | 5 | 28 | 363 | 38 | 80 | 59 | 27 | 7767 |
| 5/29/1996 | 1996 | 5 | 29 | 364 | 40 | 88 | 64 | 32 | 7799 |
| 5/30/1996 | 1996 | 5 | 30 | 365 | 41 | 87 | 64 | 32 | 7831 |
| 5/31/1996 | 1996 | 5 | 31 | 366 | 38 | 82 | 60 | 28 | 7859 |
| 6/1/1996 | 1996 | 6 | 1 | 1 | 41 | 88 | 64.5 | 32.5 | 32.5 |
| 6/2/1996 | 1996 | 6 | 2 | 2 | 39 | 89 | 64 | 32 | 64.5 |
| 6/3/1996 | 1996 | 6 | 3 | 3 | 42 | 91 | 66.5 | 34.5 | 99 |
| 6/4/1996 | 1996 | 6 | 4 | 4 | 45 | 93 | 69 | 37 | 136 |
| 6/5/1996 | 1996 | 6 | 5 | 5 | 61 | 96 | 78.5 | 46.5 | 182.5 |
| 6/6/1996 | 1996 | 6 | 6 | 6 | 57 | 95 | 76 | 44 | 226.5 |
| 6/7/1996 | 1996 | 6 | 7 | 7 | 53 | 95 | 74 | 42 | 268.5 |
| 6/8/1996 | 1996 | 6 | 8 | 8 | 50 | 96 | 73 | 41 | 309.5 |
| 6/9/1996 | 1996 | 6 | 9 | 9 | 50 | 92 | 71 | 39 | 348.5 |
| 6/10/1996 | 1996 | 6 | 10 | 10 | 52 | 97 | 74.5 | 42.5 | 391 |
| 6/11/1996 | 1996 | 6 | 11 | 11 | 52 | 92 | 72 | 40 | 431 |
| 6/12/1996 | 1996 | 6 | 12 | 12 | 53 | 92 | 72.5 | 40.5 | 471.5 |
| 6/13/1996 | 1996 | 6 | 13 | 13 | 56 | 75 | 65.5 | 33.5 | 505 |
| 6/14/1996 | 1996 | 6 | 14 | 14 | 47 | 75 | 61 | 29 | 534 |
| 6/15/1996 | 1996 | 6 | 15 | 15 | 46 | 84 | 65 | 33 | 567 |
| 6/16/1996 | 1996 | 6 | 16 | 16 | 54 | 90 | 72 | 40 | 607 |
| 6/17/1996 | 1996 | 6 | 17 | 17 | 54 | 93 | 73.5 | 41.5 | 648.5 |
| 6/18/1996 | 1996 | 6 | 18 | 18 | 53 | 93 | 73 | 41 | 689.5 |
| 6/19/1996 | 1996 | 6 | 19 | 19 | 56 | 94 | 75 | 43 | 732.5 |
| 6/20/1996 | 1996 | 6 | 20 | 20 | 56 | 99 | 77.5 | 45.5 | 778 |
| 6/21/1996 | 1996 | 6 | 21 | 21 | 59 | 90 | 74.5 | 42.5 | 820.5 |
| 6/22/1996 | 1996 | 6 | 22 | 22 | 42 | 93 | 67.5 | 35.5 | 856 |
| 6/23/1996 | 1996 | 6 | 23 | 23 | 44 | 92 | 68 | 36 | 892 |
| 6/24/1996 | 1996 | 6 | 24 | 24 | 55 | 90 | 72.5 | 40.5 | 932.5 |
| 6/25/1996 | 1996 | 6 | 25 | 25 | 52 | 92 | 72 | 40 | 972.5 |
| 6/26/1996 | 1996 | 6 | 26 | 26 | 58 | 85 | 71.5 | 39.5 | 1012 |
| 6/27/1996 | 1996 | 6 | 27 | 27 | 57 | 77 | 67 | 35 | 1047 |
| 6/28/1996 | 1996 | 6 | 28 | 28 | 54 | 87 | 70.5 | 38.5 | 1085.5 |
| 6/29/1996 | 1996 | 6 | 29 | 29 | 61 | 80 | 70.5 | 38.5 | 1124 |
| 6/30/1996 | 1996 | 6 | 30 | 30 | 55 | 85 | 70 | 38 | 1162 |
| 7/1/1996 | 1996 | 7 | 1 | 31 | 55 | 90 | 72.5 | 40.5 | 1202.5 |
| 7/2/1996 | 1996 | 7 | 2 | 32 | 62 | 95 | 78.5 | 46.5 | 1249 |
| 7/3/1996 | 1996 | 7 | 3 | 33 | 57 | 92 | 74.5 | 42.5 | 1291.5 |
| 7/4/1996 | 1996 | 7 | 4 | 34 | 60 | 96 | 78 | 46 | 1337.5 |
| 7/5/1996 | 1996 | 7 | 5 | 35 | 62 | 100 | 81 | 49 | 1386.5 |
| 7/6/1996 | 1996 | 7 | 6 | 36 | 60 | 100 | 80 | 48 | 1434.5 |
| 7/7/1996 | 1996 | 7 | 7 | 37 | 62 | 93 | 77.5 | 45.5 | 1480 |
| 7/8/1996 | 1996 | 7 | 8 | 38 | 60 | 94 | 77 | 45 | 1525 |
| 7/9/1996 | 1996 | 7 | 9 | 39 | 55 | 83 | 69 | 37 | 1562 |
| 7/10/1996 | 1996 | 7 | 10 | 40 | 58 | 86 | 72 | 40 | 1602 |
| 7/11/1996 | 1996 | 7 | 11 | 41 | 61 | 96 | 78.5 | 46.5 | 1648.5 |
| 7/12/1996 | 1996 | 7 | 12 | 42 | 60 | 89 | 74.5 | 42.5 | 1691 |
| 7/13/1996 | 1996 | 7 | 13 | 43 | 54 | 81 | 67.5 | 35.5 | 1726.5 |
| 7/14/1996 | 1996 | 7 | 14 | 44 | 57 | 89 | 73 | 41 | 1767.5 |
| 7/15/1996 | 1996 | 7 | 15 | 45 | 56 | 80 | 68 | 36 | 1803.5 |
| 7/16/1996 | 1996 | 7 | 16 | 46 | 57 | 86 | 71.5 | 39.5 | 1843 |
| 7/17/1996 | 1996 | 7 | 17 | 47 | 56 | 90 | 73 | 41 | 1884 |
| 7/18/1996 | 1996 | 7 | 18 | 48 | 54 | 90 | 72 | 40 | 1924 |
| 7/19/1996 | 1996 | 7 | 19 | 49 | 54 | 90 | 72 | 40 | 1964 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/20/1996 | 1996 | 7 | 20 | 50 | 54 | 94 | 74 | 42 | 2006 |
| 7/21/1996 | 1996 | 7 | 21 | 51 | 50 | 98 | 74 | 42 | 2048 |
| 7/22/1996 | 1996 | 7 | 22 | 52 | 50 | 100 | 75 | 43 | 2091 |
| 7/23/1996 | 1996 | 7 | 23 | 53 | 65 | 101 | 83 | 51 | 2142 |
| 7/24/1996 | 1996 | 7 | 24 | 54 | 47 | 101 | 74 | 42 | 2184 |
| 7/25/1996 | 1996 | 7 | 25 | 55 | 43 | 101 | 72 | 40 | 2224 |
| 7/26/1996 | 1996 | 7 | 26 | 56 | 59 | 101 | 80 | 48 | 2272 |
| 7/27/1996 | 1996 | 7 | 27 | 57 | 57 | 87 | 72 | 40 | 2312 |
| 7/28/1996 | 1996 | 7 | 28 | 58 | 60 | 88 | 74 | 42 | 2354 |
| 7/29/1996 | 1996 | 7 | 29 | 59 | 62 | 91 | 76.5 | 44.5 | 2398.5 |
| 7/30/1996 | 1996 | 7 | 30 | 60 | 55 | 91 | 73 | 41 | 2439.5 |
| 7/31/1996 | 1996 | 7 | 31 | 61 | 55 | 91 | 73 | 41 | 2480.5 |
| 8/1/1996 | 1996 | 8 | 1 | 62 | 51 | 91 | 71 | 39 | 2519.5 |
| 8/2/1996 | 1996 | 8 | 2 | 63 | 64 | 92 | 78 | 46 | 2565.5 |
| 8/3/1996 | 1996 | 8 | 3 | 64 | 63 | 91 | 77 | 45 | 2610.5 |
| 8/4/1996 | 1996 | 8 | 4 | 65 | 64 | 89 | 76.5 | 44.5 | 2655 |
| 8/5/1996 | 1996 | 8 | 5 | 66 | 59 | 88 | 73.5 | 41.5 | 2696.5 |
| 8/6/1996 | 1996 | 8 | 6 | 67 | 56 | 93 | 74.5 | 42.5 | 2739 |
| 8/7/1996 | 1996 | 8 | 7 | 68 | 50 | 94 | 72 | 40 | 2779 |
| 8/8/1996 | 1996 | 8 | 8 | 69 | 56 | 93 | 74.5 | 42.5 | 2821.5 |
| 8/9/1996 | 1996 | 8 | 9 | 70 | 60 | 80 | 70 | 38 | 2859.5 |
| 8/10/1996 | 1996 | 8 | 10 | 71 | 52 | 76 | 64 | 32 | 2891.5 |
| 8/11/1996 | 1996 | 8 | 11 | 72 | 55 | 91 | 73 | 41 | 2932.5 |
| 8/12/1996 | 1996 | 8 | 12 | 73 | 51 | 94 | 72.5 | 40.5 | 2973 |
| 8/13/1996 | 1996 | 8 | 13 | 74 | 56 | 98 | 77 | 45 | 3018 |
| 8/14/1996 | 1996 | 8 | 14 | 75 | 58 | 99 | 78.5 | 46.5 | 3064.5 |
| 8/15/1996 | 1996 | 8 | 15 | 76 | 58 | 96 | 77 | 45 | 3109.5 |
| 8/16/1996 | 1996 | 8 | 16 | 77 | 50 | 96 | 73 | 41 | 3150.5 |
| 8/17/1996 | 1996 | 8 | 17 | 78 | 59 | 95 | 77 | 45 | 3195.5 |
| 8/18/1996 | 1996 | 8 | 18 | 79 | 54 | 90 | 72 | 40 | 3235.5 |
| 8/19/1996 | 1996 | 8 | 19 | 80 | 52 | 91 | 71.5 | 39.5 | 3275 |
| 8/20/1996 | 1996 | 8 | 20 | 81 | 60 | 88 | 74 | 42 | 3317 |
| 8/21/1996 | 1996 | 8 | 21 | 82 | 58 | 88 | 73 | 41 | 3358 |
| 8/22/1996 | 1996 | 8 | 22 | 83 | 55 | 85 | 70 | 38 | 3396 |
| 8/23/1996 | 1996 | 8 | 23 | 84 | 56 | 82 | 69 | 37 | 3433 |
| 8/24/1996 | 1996 | 8 | 24 | 85 | 57 | 81 | 69 | 37 | 3470 |
| 8/25/1996 | 1996 | 8 | 25 | 86 | 58 | 83 | 70.5 | 38.5 | 3508.5 |
| 8/26/1996 | 1996 | 8 | 26 | 87 | 53 | 81 | 67 | 35 | 3543.5 |
| 8/27/1996 | 1996 | 8 | 27 | 88 | 58 | 84 | 71 | 39 | 3582.5 |
| 8/28/1996 | 1996 | 8 | 28 | 89 | 56 | 84 | 70 | 38 | 3620.5 |
| 8/29/1996 | 1996 | 8 | 29 | 90 | 56 | 90 | 73 | 41 | 3661.5 |
| 8/30/1996 | 1996 | 8 | 30 | 91 | 56 | 93 | 74.5 | 42.5 | 3704 |
| 8/31/1996 | 1996 | 8 | 31 | 92 | 44 | 95 | 69.5 | 37.5 | 3741.5 |
| 9/1/1996 | 1996 | 9 | 1 | 93 | 59 | 89 | 74 | 42 | 3783.5 |
| 9/2/1996 | 1996 | 9 | 2 | 94 | 48 | 84 | 66 | 34 | 3817.5 |
| 9/3/1996 | 1996 | 9 | 3 | 95 | 49 | 91 | 70 | 38 | 3855.5 |
| 9/4/1996 | 1996 | 9 | 4 | 96 | 50 | 89 | 69.5 | 37.5 | 3893 |
| 9/5/1996 | 1996 | 9 | 5 | 97 | 49 | 82 | 65.5 | 33.5 | 3926.5 |
| 9/6/1996 | 1996 | 9 | 6 | 98 | 53 | 84 | 68.5 | 36.5 | 3963 |
| 9/7/1996 | 1996 | 9 | 7 | 99 | 43 | 83 | 63 | 31 | 3994 |
| 9/8/1996 | 1996 | 9 | 8 | 100 | 43 | 89 | 66 | 34 | 4028 |
| 9/9/1996 | 1996 | 9 | 9 | 101 | 53 | 85 | 69 | 37 | 4065 |
| 9/10/1996 | 1996 | 9 | 10 | 102 | 53 | 84 | 68.5 | 36.5 | 4101.5 |
| 9/11/1996 | 1996 | 9 | 11 | 103 | 53 | 81 | 67 | 35 | 4136.5 |
| 9/12/1996 | 1996 | 9 | 12 | 104 | 52 | 63 | 57.5 | 25.5 | 4162 |
| 9/13/1996 | 1996 | 9 | 13 | 105 | 50 | 72 | 61 | 29 | 4191 |
| 9/14/1996 | 1996 | 9 | 14 | 106 | 41 | 58 | 49.5 | 17.5 | 4208.5 |
| 9/15/1996 | 1996 | 9 | 15 | 107 | 41 | 76 | 58.5 | 26.5 | 4235 |
| 9/16/1996 | 1996 | 9 | 16 | 108 | 47 | 78 | 62.5 | 30.5 | 4265.5 |
| 9/17/1996 | 1996 | 9 | 17 | 109 | 43 | 66 | 54.5 | 22.5 | 4288 |
| 9/18/1996 | 1996 | 9 | 18 | 110 | 34 | 53 | 43.5 | 11.5 | 4299.5 |
| 9/19/1996 | 1996 | 9 | 19 | 111 | 34 | 71 | 52.5 | 20.5 | 4320 |
| 9/20/1996 | 1996 | 9 | 20 | 112 | 37 | 77 | 57 | 25 | 4345 |
| 9/21/1996 | 1996 | 9 | 21 | 113 | 40 | 83 | 61.5 | 29.5 | 4374.5 |
| 9/22/1996 | 1996 | 9 | 22 | 114 | 41 | 83 | 62 | 30 | 4404.5 |
| 9/23/1996 | 1996 | 9 | 23 | 115 | 42 | 83 | 62.5 | 30.5 | 4435 |
| 9/24/1996 | 1996 | 9 | 24 | 116 | 40 | 69 | 54.5 | 22.5 | 4457.5 |
| 9/25/1996 | 1996 | 9 | 25 | 117 | 41 | 76 | 58.5 | 26.5 | 4484 |
| 9/26/1996 | 1996 | 9 | 26 | 118 | 35 | 76 | 55.5 | 23.5 | 4507.5 |
| 9/27/1996 | 1996 | 9 | 27 | 119 | 31 | 65 | 48 | 16 | 4523.5 |
| 9/28/1996 | 1996 | 9 | 28 | 120 | 33 | 75 | 54 | 22 | 4545.5 |
| 9/29/1996 | 1996 | 9 | 29 | 121 | 38 | 78 | 58 | 26 | 4571.5 |
| 9/30/1996 | 1996 | 9 | 30 | 122 | 30 | 76 | 53 | 21 | 4592.5 |
| 10/1/1996 | 1996 | 10 | 1 | 123 | 30 | 83 | 56.5 | 24.5 | 4617 |
| 10/2/1996 | 1996 | 10 | 2 | 124 | 38 | 89 | 63.5 | 31.5 | 4648.5 |
| 10/3/1996 | 1996 | 10 | 3 | 125 | 39 | 71 | 55 | 23 | 4671.5 |
| 10/4/1996 | 1996 | 10 | 4 | 126 | 33 | 61 | 47 | 15 | 4686.5 |
| 10/5/1996 | 1996 | 10 | 5 | 127 | 30 | 75 | 52.5 | 20.5 | 4707 |
| 10/6/1996 | 1996 | 10 | 6 | 128 | 31 | 80 | 55.5 | 23.5 | 4730.5 |
| 10/7/1996 | 1996 | 10 | 7 | 129 | 28 | 82 | 55 | 23 | 4753.5 |
| 10/8/1996 | 1996 | 10 | 8 | 130 | 28 | 83 | 55.5 | 23.5 | 4777 |
| 10/9/1996 | 1996 | 10 | 9 | 131 | 28 | 83 | 55.5 | 23.5 | 4800.5 |
| 10/10/1996 | 1996 | 10 | 10 | 132 | 28 | 88 | 58 | 26 | 4826.5 |
| 10/11/1996 | 1996 | 10 | 11 | 133 | 28 | 85 | 56.5 | 24.5 | 4851 |
| 10/12/1996 | 1996 | 10 | 12 | 134 | 27 | 86 | 56.5 | 24.5 | 4875.5 |
| 10/13/1996 | 1996 | 10 | 13 | 135 | 34 | 83 | 58.5 | 26.5 | 4902 |
| 10/14/1996 | 1996 | 10 | 14 | 136 | 27 | 75 | 51 | 19 | 4921 |
| 10/15/1996 | 1996 | 10 | 15 | 137 | 27 | 76 | 51.5 | 19.5 | 4940.5 |
| 10/16/1996 | 1996 | 10 | 16 | 138 | 27 | 76 | 51.5 | 19.5 | 4960 |
| 10/17/1996 | 1996 | 10 | 17 | 139 | 29 | 73 | 51 | 19 | 4979 |
| 10/18/1996 | 1996 | 10 | 18 | 140 | 40 | 74 | 57 | 25 | 5004 |
| 10/19/1996 | 1996 | 10 | 19 | 141 | 42 | 71 | 56.5 | 24.5 | 5028.5 |
| 10/20/1996 | 1996 | 10 | 20 | 142 | 28 | 59 | 43.5 | 11.5 | 5040 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/21/1996 | 1996 | 10 | 21 | 143 | 15 | 42 | 28.5 | -3.5 | 5036.5 |
| 10/22/1996 | 1996 | 10 | 22 | 144 | 17 | 54 | 35.5 | 3.5 | 5040 |
| 10/23/1996 | 1996 | 10 | 23 | 145 | 18 | 61 | 39.5 | 7.5 | 5047.5 |
| 10/24/1996 | 1996 | 10 | 24 | 146 | 36 | 65 | 50.5 | 18.5 | 5066 |
| 10/25/1996 | 1996 | 10 | 25 | 147 | 22 | 65 | 43.5 | 11.5 | 5077.5 |
| 10/26/1996 | 1996 | 10 | 26 | 148 | 31 | 37 | 34 | 2 | 5079.5 |
| 10/27/1996 | 1996 | 10 | 27 | 149 | 36 | 39 | 37.5 | 5.5 | 5085 |
| 10/28/1996 | 1996 | 10 | 28 | 150 | 28 | 53 | 40.5 | 8.5 | 5093.5 |
| 10/29/1996 | 1996 | 10 | 29 | 151 | 25 | 50 | 37.5 | 5.5 | 5099 |
| 10/30/1996 | 1996 | 10 | 30 | 152 | 30 | 60 | 45 | 13 | 5112 |
| 10/31/1996 | 1996 | 10 | 31 | 153 | 22 | 59 | 40.5 | 8.5 | 5120.5 |
| 11/1/1996 | 1996 | 11 | 1 | 154 | 21 | 55 | 38 | 6 | 5126.5 |
| 11/2/1996 | 1996 | 11 | 2 | 155 | 22 | 52 | 37 | 5 | 5131.5 |
| 11/3/1996 | 1996 | 11 | 3 | 156 | 28 | 56 | 42 | 10 | 5141.5 |
| 11/4/1996 | 1996 | 11 | 4 | 157 | 22 | 63 | 42.5 | 10.5 | 5152 |
| 11/5/1996 | 1996 | 11 | 5 | 158 | 23 | 64 | 43.5 | 11.5 | 5163.5 |
| 11/6/1996 | 1996 | 11 | 6 | 159 | 18 | 57 | 37.5 | 5.5 | 5169 |
| 11/7/1996 | 1996 | 11 | 7 | 160 | 18 | 54 | 36 | 4 | 5173 |
| 11/8/1996 | 1996 | 11 | 8 | 161 | 23 | 60 | 41.5 | 9.5 | 5182.5 |
| 11/9/1996 | 1996 | 11 | 9 | 162 | 20 | 66 | 43 | 11 | 5193.5 |
| 11/10/1996 | 1996 | 11 | 10 | 163 | 18 | 70 | 44 | 12 | 5205.5 |
| 11/11/1996 | 1996 | 11 | 11 | 164 | 18 | 72 | 45 | 13 | 5218.5 |
| 11/12/1996 | 1996 | 11 | 12 | 165 | 20 | 73 | 46.5 | 14.5 | 5233 |
| 11/13/1996 | 1996 | 11 | 13 | 166 | 25 | 72 | 48.5 | 16.5 | 5249.5 |
| 11/14/1996 | 1996 | 11 | 14 | 167 | 25 | 66 | 45.5 | 13.5 | 5263 |
| 11/15/1996 | 1996 | 11 | 15 | 168 | 22 | 61 | 41.5 | 9.5 | 5272.5 |
| 11/16/1996 | 1996 | 11 | 16 | 169 | 11 | 44 | 27.5 | -4.5 | 5268 |
| 11/17/1996 | 1996 | 11 | 17 | 170 | 16 | 58 | 37 | 5 | 5273 |
| 11/18/1996 | 1996 | 11 | 18 | 171 | 25 | 69 | 47 | 15 | 5288 |
| 11/19/1996 | 1996 | 11 | 19 | 172 | 24 | 74 | 49 | 17 | 5305 |
| 11/20/1996 | 1996 | 11 | 20 | 173 | 25 | 71 | 48 | 16 | 5321 |
| 11/21/1996 | 1996 | 11 | 21 | 174 | 39 | 72 | 55.5 | 23.5 | 5344.5 |
| 11/22/1996 | 1996 | 11 | 22 | 175 | 33 | 64 | 48.5 | 16.5 | 5361 |
| 11/23/1996 | 1996 | 11 | 23 | 176 | 22 | 51 | 36.5 | 4.5 | 5365.5 |
| 11/24/1996 | 1996 | 11 | 24 | 177 | 18 | 55 | 36.5 | 4.5 | 5370 |
| 11/25/1996 | 1996 | 11 | 25 | 178 | 26 | 56 | 41 | 9 | 5379 |
| 11/26/1996 | 1996 | 11 | 26 | 179 | 29 | 51 | 40 | 8 | 5387 |
| 11/27/1996 | 1996 | 11 | 27 | 180 | 23 | 52 | 37.5 | 5.5 | 5392.5 |
| 11/28/1996 | 1996 | 11 | 28 | 181 | 22 | 44 | 33 | 1 | 5393.5 |
| 11/29/1996 | 1996 | 11 | 29 | 182 | 23 | 40 | 31.5 | -0.5 | 5393 |
| 11/30/1996 | 1996 | 11 | 30 | 183 | 13 | 40 | 26.5 | -5.5 | 5387.5 |
| 12/1/1996 | 1996 | 12 | 1 | 184 | 27 | 53 | 40 | 8 | 5395.5 |
| 12/2/1996 | 1996 | 12 | 2 | 185 | 9 | 43 | 26 | -6 | 5389.5 |
| 12/3/1996 | 1996 | 12 | 3 | 186 | 12 | 48 | 30 | -2 | 5387.5 |
| 12/4/1996 | 1996 | 12 | 4 | 187 | 12 | 49 | 30.5 | -1.5 | 5386 |
| 12/5/1996 | 1996 | 12 | 5 | 188 | 13 | 58 | 35.5 | 3.5 | 5389.5 |
| 12/6/1996 | 1996 | 12 | 6 | 189 | 14 | 55 | 34.5 | 2.5 | 5392 |
| 12/7/1996 | 1996 | 12 | 7 | 190 | 19 | 54 | 36.5 | 4.5 | 5396.5 |
| 12/8/1996 | 1996 | 12 | 8 | 191 | 20 | 65 | 42.5 | 10.5 | 5407 |
| 12/9/1996 | 1996 | 12 | 9 | 192 | 35 | 69 | 52 | 20 | 5427 |
| 12/10/1996 | 1996 | 12 | 10 | 193 | 43 | 60 | 51.5 | 19.5 | 5446.5 |
| 12/11/1996 | 1996 | 12 | 11 | 194 | 22 | 58 | 40 | 8 | 5454.5 |
| 12/12/1996 | 1996 | 12 | 12 | 195 | 18 | 61 | 39.5 | 7.5 | 5462 |
| 12/13/1996 | 1996 | 12 | 13 | 196 | 17 | 64 | 40.5 | 8.5 | 5470.5 |
| 12/14/1996 | 1996 | 12 | 14 | 197 | 10 | 48 | 29 | -3 | 5467.5 |
| 12/15/1996 | 1996 | 12 | 15 | 198 | 12 | 40 | 26 | -6 | 5461.5 |
| 12/16/1996 | 1996 | 12 | 16 | 199 | 18 | 59 | 38.5 | 6.5 | 5468 |
| 12/17/1996 | 1996 | 12 | 17 | 200 | 3 | 30 | 16.5 | -15.5 | 5452.5 |
| 12/18/1996 | 1996 | 12 | 18 | 201 | 3 | 32 | 17.5 | -14.5 | 5438 |
| 12/19/1996 | 1996 | 12 | 19 | 202 | 3 | 48 | 25.5 | -6.5 | 5431.5 |
| 12/20/1996 | 1996 | 12 | 20 | 203 | 29 | 56 | 42.5 | 10.5 | 5442 |
| 12/21/1996 | 1996 | 12 | 21 | 204 | 18 | 55 | 36.5 | 4.5 | 5446.5 |
| 12/22/1996 | 1996 | 12 | 22 | 205 | 32 | 55 | 43.5 | 11.5 | 5458 |
| 12/23/1996 | 1996 | 12 | 23 | 206 | 10 | 49 | 29.5 | -2.5 | 5455.5 |
| 12/24/1996 | 1996 | 12 | 24 | 207 | 13 | 44 | 28.5 | -3.5 | 5452 |
| 12/25/1996 | 1996 | 12 | 25 | 208 | 13 | 37 | 25 | -7 | 5445 |
| 12/26/1996 | 1996 | 12 | 26 | 209 | 13 | 59 | 36 | 4 | 5449 |
| 12/27/1996 | 1996 | 12 | 27 | 210 | 25 | 55 | 40 | 8 | 5457 |
| 12/28/1996 | 1996 | 12 | 28 | 211 | 16 | 51 | 33.5 | 1.5 | 5458.5 |
| 12/29/1996 | 1996 | 12 | 29 | 212 | 20 | 56 | 38 | 6 | 5464.5 |
| 12/30/1996 | 1996 | 12 | 30 | 213 | 26 | 59 | 42.5 | 10.5 | 5475 |
| 12/31/1996 | 1996 | 12 | 31 | 214 | 23 | 60 | 41.5 | 9.5 | 5484.5 |
| 1/1/1997 | 1997 | 1 | 1 | 215 | 22 | 60 | 41 | 9 | 5493.5 |
| 1/2/1997 | 1997 | 1 | 2 | 216 | 31 | 63 | 47 | 15 | 5508.5 |
| 1/3/1997 | 1997 | 1 | 3 | 217 | 30 | 58 | 44 | 12 | 5520.5 |
| 1/4/1997 | 1997 | 1 | 4 | 218 | 31 | 46 | 38.5 | 6.5 | 5527 |
| 1/5/1997 | 1997 | 1 | 5 | 219 | 23 | 35 | 29 | -3 | 5524 |
| 1/6/1997 | 1997 | 1 | 6 | 220 | 1 | 25 | 13 | -19 | 5505 |
| 1/7/1997 | 1997 | 1 | 7 | 221 | 7 | 30 | 18.5 | -13.5 | 5491.5 |
| 1/8/1997 | 1997 | 1 | 8 | 222 | -1 | 29 | 14 | -18 | 5473.5 |
| 1/9/1997 | 1997 | 1 | 9 | 223 | 17 | 40 | 28.5 | -3.5 | 5470 |
| 1/10/1997 | 1997 | 1 | 10 | 224 | 19 | 48 | 33.5 | 1.5 | 5471.5 |
| 1/11/1997 | 1997 | 1 | 11 | 225 | 19 | 43 | 31 | -1 | 5470.5 |
| 1/12/1997 | 1997 | 1 | 12 | 226 | 12 | 33 | 22.5 | -9.5 | 5461 |
| 1/13/1997 | 1997 | 1 | 13 | 227 | 13 | 18 | 15.5 | -16.5 | 5444.5 |
| 1/14/1997 | 1997 | 1 | 14 | 228 | -16 | 25 | 4.5 | -27.5 | 5417 |
| 1/15/1997 | 1997 | 1 | 15 | 229 | -7 | 36 | 14.5 | -17.5 | 5399.5 |
| 1/16/1997 | 1997 | 1 | 16 | 230 | -7 | 36 | 14.5 | -17.5 | 5382 |
| 1/17/1997 | 1997 | 1 | 17 | 231 | -4 | 42 | 19 | -13 | 5369 |
| 1/18/1997 | 1997 | 1 | 18 | 232 | 5 | 46 | 25.5 | -6.5 | 5362.5 |
| 1/19/1997 | 1997 | 1 | 19 | 233 | 8 | 59 | 33.5 | 1.5 | 5364 |
| 1/20/1997 | 1997 | 1 | 20 | 234 | 8 | 57 | 32.5 | 0.5 | 5364.5 |
| 1/21/1997 | 1997 | 1 | 21 | 235 | 14 | 45 | 29.5 | -2.5 | 5362 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/22/1997 | 1997 | 1 | 22 | 236 | 28 | 45 | 36.5 | 4.5 | 5366.5 |
| 1/23/1997 | 1997 | 1 | 23 | 237 | 24 | 48 | 36 | 4 | 5370.5 |
| 1/24/1997 | 1997 | 1 | 24 | 238 | 22 | 46 | 34 | 2 | 5372.5 |
| 1/25/1997 | 1997 | 1 | 25 | 239 | 35 | 58 | 46.5 | 14.5 | 5387 |
| 1/26/1997 | 1997 | 1 | 26 | 240 | 32 | 51 | 41.5 | 9.5 | 5396.5 |
| 1/27/1997 | 1997 | 1 | 27 | 241 | 24 | 51 | 37.5 | 5.5 | 5402 |
| 1/28/1997 | 1997 | 1 | 28 | 242 | 28 | 48 | 38 | 6 | 5408 |
| 1/29/1997 | 1997 | 1 | 29 | 243 | 21 | 47 | 34 | 2 | 5410 |
| 1/30/1997 | 1997 | 1 | 30 | 244 | 21 | 51 | 36 | 4 | 5414 |
| 1/31/1997 | 1997 | 1 | 31 | 245 | 28 | 65 | 46.5 | 14.5 | 5428.5 |
| 2/1/1997 | 1997 | 2 | 1 | 246 | 21 | 58 | 39.5 | 7.5 | 5436 |
| 2/2/1997 | 1997 | 2 | 2 | 247 | 25 | 54 | 39.5 | 7.5 | 5443.5 |
| 2/3/1997 | 1997 | 2 | 3 | 248 | 20 | 53 | 36.5 | 4.5 | 5448 |
| 2/4/1997 | 1997 | 2 | 4 | 249 | 32 | 50 | 41 | 9 | 5457 |
| 2/5/1997 | 1997 | 2 | 5 | 250 | 25 | 48 | 36.5 | 4.5 | 5461.5 |
| 2/6/1997 | 1997 | 2 | 6 | 251 | 18 | 45 | 31.5 | -0.5 | 5461 |
| 2/7/1997 | 1997 | 2 | 7 | 252 | 18 | 44 | 31 | -1 | 5460 |
| 2/8/1997 | 1997 | 2 | 8 | 253 | 21 | 48 | 34.5 | 2.5 | 5462.5 |
| 2/9/1997 | 1997 | 2 | 9 | 254 | 16 | 55 | 35.5 | 3.5 | 5466 |
| 2/10/1997 | 1997 | 2 | 10 | 255 | 15 | 56 | 35.5 | 3.5 | 5469.5 |
| 2/11/1997 | 1997 | 2 | 11 | 256 | 17 | 58 | 37.5 | 5.5 | 5475 |
| 2/12/1997 | 1997 | 2 | 12 | 257 | 26 | 58 | 42 | 10 | 5485 |
| 2/13/1997 | 1997 | 2 | 13 | 258 | 14 | 39 | 26.5 | -5.5 | 5479.5 |
| 2/14/1997 | 1997 | 2 | 14 | 259 | 15 | 53 | 34 | 2 | 5481.5 |
| 2/15/1997 | 1997 | 2 | 15 | 260 | 17 | 55 | 36 | 4 | 5485.5 |
| 2/16/1997 | 1997 | 2 | 16 | 261 | 28 | 61 | 44.5 | 12.5 | 5498 |
| 2/17/1997 | 1997 | 2 | 17 | 262 | 21 | 63 | 42 | 10 | 5508 |
| 2/18/1997 | 1997 | 2 | 18 | 263 | 30 | 64 | 47 | 15 | 5523 |
| 2/19/1997 | 1997 | 2 | 19 | 264 | 17 | 51 | 34 | 2 | 5525 |
| 2/20/1997 | 1997 | 2 | 20 | 265 | 14 | 60 | 37 | 5 | 5530 |
| 2/21/1997 | 1997 | 2 | 21 | 266 | 8 | 46 | 27 | -5 | 5525 |
| 2/22/1997 | 1997 | 2 | 22 | 267 | 18 | 47 | 32.5 | 0.5 | 5525.5 |
| 2/23/1997 | 1997 | 2 | 23 | 268 | 20 | 55 | 37.5 | 5.5 | 5531 |
| 2/24/1997 | 1997 | 2 | 24 | 269 | 20 | 42 | 31 | -1 | 5530 |
| 2/25/1997 | 1997 | 2 | 25 | 270 | 20 | 37 | 28.5 | -3.5 | 5526.5 |
| 2/26/1997 | 1997 | 2 | 26 | 271 | 26 | 49 | 37.5 | 5.5 | 5532 |
| 2/27/1997 | 1997 | 2 | 27 | 272 | 29 | 43 | 36 | 4 | 5536 |
| 2/28/1997 | 1997 | 2 | 28 | 273 | 11 | 39 | 25 | -7 | 5529 |
| 3/1/1997 | 1997 | 3 | 1 | 274 | 16 | 41 | 28.5 | -3.5 | 5525.5 |
| 3/2/1997 | 1997 | 3 | 2 | 275 | 24 | 61 | 42.5 | 10.5 | 5536 |
| 3/3/1997 | 1997 | 3 | 3 | 276 | 30 | 62 | 46 | 14 | 5550 |
| 3/4/1997 | 1997 | 3 | 4 | 277 | 15 | 55 | 35 | 3 | 5553 |
| 3/5/1997 | 1997 | 3 | 5 | 278 | 14 | 56 | 35 | 3 | 5556 |
| 3/6/1997 | 1997 | 3 | 6 | 279 | 20 | 64 | 42 | 10 | 5566 |
| 3/7/1997 | 1997 | 3 | 7 | 280 | 22 | 67 | 44.5 | 12.5 | 5578.5 |
| 3/8/1997 | 1997 | 3 | 8 | 281 | 18 | 70 | 44 | 12 | 5590.5 |
| 3/9/1997 | 1997 | 3 | 9 | 282 | 18 | 68 | 43 | 11 | 5601.5 |
| 3/10/1997 | 1997 | 3 | 10 | 283 | 20 | 71 | 45.5 | 13.5 | 5615 |
| 3/11/1997 | 1997 | 3 | 11 | 284 | 20 | 75 | 47.5 | 15.5 | 5630.5 |
| 3/12/1997 | 1997 | 3 | 12 | 285 | 22 | 71 | 46.5 | 14.5 | 5645 |
| 3/13/1997 | 1997 | 3 | 13 | 286 | 21 | 75 | 48 | 16 | 5661 |
| 3/14/1997 | 1997 | 3 | 14 | 287 | 32 | 70 | 51 | 19 | 5680 |
| 3/15/1997 | 1997 | 3 | 15 | 288 | 29 | 73 | 51 | 19 | 5699 |
| 3/16/1997 | 1997 | 3 | 16 | 289 | 36 | 74 | 55 | 23 | 5722 |
| 3/17/1997 | 1997 | 3 | 17 | 290 | 29 | 65 | 47 | 15 | 5737 |
| 3/18/1997 | 1997 | 3 | 18 | 291 | 24 | 71 | 47.5 | 15.5 | 5752.5 |
| 3/19/1997 | 1997 | 3 | 19 | 292 | 27 | 77 | 52 | 20 | 5772.5 |
| 3/20/1997 | 1997 | 3 | 20 | 293 | 27 | 82 | 54.5 | 22.5 | 5795 |
| 3/21/1997 | 1997 | 3 | 21 | 294 | 27 | 82 | 54.5 | 22.5 | 5817.5 |
| 3/22/1997 | 1997 | 3 | 22 | 295 | 32 | 80 | 56 | 24 | 5841.5 |
| 3/23/1997 | 1997 | 3 | 23 | 296 | 32 | 75 | 53.5 | 21.5 | 5863 |
| 3/24/1997 | 1997 | 3 | 24 | 297 | 25 | 67 | 46 | 14 | 5877 |
| 3/25/1997 | 1997 | 3 | 25 | 298 | 18 | 48 | 33 | 1 | 5878 |
| 3/26/1997 | 1997 | 3 | 26 | 299 | 30 | 58 | 44 | 12 | 5890 |
| 3/27/1997 | 1997 | 3 | 27 | 300 | 37 | 69 | 53 | 21 | 5911 |
| 3/28/1997 | 1997 | 3 | 28 | 301 | 31 | 71 | 51 | 19 | 5930 |
| 3/29/1997 | 1997 | 3 | 29 | 302 | 18 | 65 | 41.5 | 9.5 | 5939.5 |
| 3/30/1997 | 1997 | 3 | 30 | 303 | 21 | 68 | 44.5 | 12.5 | 5952 |
| 3/31/1997 | 1997 | 3 | 31 | 304 | 37 | 66 | 51.5 | 19.5 | 5971.5 |
| 4/1/1997 | 1997 | 4 | 1 | 305 | 30 | 66 | 48 | 16 | 5987.5 |
| 4/2/1997 | 1997 | 4 | 2 | 306 | 41 | 71 | 56 | 24 | 6011.5 |
| 4/3/1997 | 1997 | 4 | 3 | 307 | 34 | 68 | 51 | 19 | 6030.5 |
| 4/4/1997 | 1997 | 4 | 4 | 308 | 34 | 48 | 41 | 9 | 6039.5 |
| 4/5/1997 | 1997 | 4 | 5 | 309 | 26 | 48 | 37 | 5 | 6044.5 |
| 4/6/1997 | 1997 | 4 | 6 | 310 | 24 | 54 | 39 | 7 | 6051.5 |
| 4/7/1997 | 1997 | 4 | 7 | 311 | 25 | 66 | 45.5 | 13.5 | 6065 |
| 4/8/1997 | 1997 | 4 | 8 | 312 | 26 | 69 | 47.5 | 15.5 | 6080.5 |
| 4/9/1997 | 1997 | 4 | 9 | 313 | 30 | 68 | 49 | 17 | 6097.5 |
| 4/10/1997 | 1997 | 4 | 10 | 314 | 28 | 56 | 42 | 10 | 6107.5 |
| 4/11/1997 | 1997 | 4 | 11 | 315 | 23 | 48 | 35.5 | 3.5 | 6111 |
| 4/12/1997 | 1997 | 4 | 12 | 316 | 21 | 52 | 36.5 | 4.5 | 6115.5 |
| 4/13/1997 | 1997 | 4 | 13 | 317 | 22 | 55 | 38.5 | 6.5 | 6122 |
| 4/14/1997 | 1997 | 4 | 14 | 318 | 24 | 66 | 45 | 13 | 6135 |
| 4/15/1997 | 1997 | 4 | 15 | 319 | 29 | 69 | 49 | 17 | 6152 |
| 4/16/1997 | 1997 | 4 | 16 | 320 | 31 | 73 | 52 | 20 | 6172 |
| 4/17/1997 | 1997 | 4 | 17 | 321 | 31 | 74 | 52.5 | 20.5 | 6192.5 |
| 4/18/1997 | 1997 | 4 | 18 | 322 | 32 | 75 | 53.5 | 21.5 | 6214 |
| 4/19/1997 | 1997 | 4 | 19 | 323 | 39 | 74 | 56.5 | 24.5 | 6238.5 |
| 4/20/1997 | 1997 | 4 | 20 | 324 | 42 | 77 | 59.5 | 27.5 | 6266 |
| 4/21/1997 | 1997 | 4 | 21 | 325 | 36 | 76 | 56 | 24 | 6290 |
| 4/22/1997 | 1997 | 4 | 22 | 326 | 32 | 75 | 53.5 | 21.5 | 6311.5 |
| 4/23/1997 | 1997 | 4 | 23 | 327 | 35 | 63 | 49 | 17 | 6328.5 |
| 4/24/1997 | 1997 | 4 | 24 | 328 | 31 | 52 | 41.5 | 9.5 | 6338 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/25/1997 | 1997 | 4 | 25 | 329 | 30 | 44 | 37 | 5 | 6343 |
| 4/26/1997 | 1997 | 4 | 26 | 330 | 32 | 64 | 48 | 16 | 6359 |
| 4/27/1997 | 1997 | 4 | 27 | 331 | 50 | 73 | 61.5 | 29.5 | 6388.5 |
| 4/28/1997 | 1997 | 4 | 28 | 332 | 51 | 77 | 64 | 32 | 6420.5 |
| 4/29/1997 | 1997 | 4 | 29 | 333 | 40 | 70 | 55 | 23 | 6443.5 |
| 4/30/1997 | 1997 | 4 | 30 | 334 | 46 | 75 | 60.5 | 28.5 | 6472 |
| 5/1/1997 | 1997 | 5 | 1 | 335 | 30 | 70 | 50 | 18 | 6490 |
| 5/2/1997 | 1997 | 5 | 2 | 336 | 29 | 69 | 49 | 17 | 6507 |
| 5/3/1997 | 1997 | 5 | 3 | 337 | 41 | 79 | 60 | 28 | 6535 |
| 5/4/1997 | 1997 | 5 | 4 | 338 | 37 | 84 | 60.5 | 28.5 | 6563.5 |
| 5/5/1997 | 1997 | 5 | 5 | 339 | 45 | 82 | 63.5 | 31.5 | 6595 |
| 5/6/1997 | 1997 | 5 | 6 | 340 | 47 | 85 | 66 | 34 | 6629 |
| 5/7/1997 | 1997 | 5 | 7 | 341 | 41 | 84 | 62.5 | 30.5 | 6659.5 |
| 5/8/1997 | 1997 | 5 | 8 | 342 | 41 | 81 | 61 | 29 | 6688.5 |
| 5/9/1997 | 1997 | 5 | 9 | 343 | 40 | 68 | 54 | 22 | 6710.5 |
| 5/10/1997 | 1997 | 5 | 10 | 344 | 38 | 74 | 56 | 24 | 6734.5 |
| 5/11/1997 | 1997 | 5 | 11 | 345 | 38 | 77 | 57.5 | 25.5 | 6760 |
| 5/12/1997 | 1997 | 5 | 12 | 346 | 36 | 80 | 58 | 26 | 6786 |
| 5/13/1997 | 1997 | 5 | 13 | 347 | 36 | 87 | 61.5 | 29.5 | 6815.5 |
| 5/14/1997 | 1997 | 5 | 14 | 348 | 42 | 88 | 65 | 33 | 6848.5 |
| 5/15/1997 | 1997 | 5 | 15 | 349 | 45 | 85 | 65 | 33 | 6881.5 |
| 5/16/1997 | 1997 | 5 | 16 | 350 | 44 | 85 | 64.5 | 32.5 | 6914 |
| 5/17/1997 | 1997 | 5 | 17 | 351 | 48 | 85 | 66.5 | 34.5 | 6948.5 |
| 5/18/1997 | 1997 | 5 | 18 | 352 | 42 | 81 | 61.5 | 29.5 | 6978 |
| 5/19/1997 | 1997 | 5 | 19 | 353 | 43 | 78 | 60.5 | 28.5 | 7006.5 |
| 5/20/1997 | 1997 | 5 | 20 | 354 | 47 | 72 | 59.5 | 27.5 | 7034 |
| 5/21/1997 | 1997 | 5 | 21 | 355 | 42 | 70 | 56 | 24 | 7058 |
| 5/22/1997 | 1997 | 5 | 22 | 356 | 39 | 70 | 54.5 | 22.5 | 7080.5 |
| 5/23/1997 | 1997 | 5 | 23 | 357 | 49 | 80 | 64.5 | 32.5 | 7113 |
| 5/24/1997 | 1997 | 5 | 24 | 358 | 40 | 73 | 56.5 | 24.5 | 7137.5 |
| 5/25/1997 | 1997 | 5 | 25 | 359 | 46 | 75 | 60.5 | 28.5 | 7166 |
| 5/26/1997 | 1997 | 5 | 26 | 360 | 36 | 77 | 56.5 | 24.5 | 7190.5 |
| 5/27/1997 | 1997 | 5 | 27 | 361 | 37 | 76 | 56.5 | 24.5 | 7215 |
| 5/28/1997 | 1997 | 5 | 28 | 362 | 43 | 83 | 63 | 31 | 7246 |
| 5/29/1997 | 1997 | 5 | 29 | 363 | 45 | 89 | 67 | 35 | 7281 |
| 5/30/1997 | 1997 | 5 | 30 | 364 | 49 | 90 | 69.5 | 37.5 | 7318.5 |
| 5/31/1997 | 1997 | 5 | 31 | 365 | 48 | 92 | 70 | 38 | 7356.5 |
| 6/1/1997 | 1997 | 6 | 1 | 1 | 48 | 95 | 71.5 | 39.5 | 39.5 |
| 6/2/1997 | 1997 | 6 | 2 | 2 | 44 | 91 | 67.5 | 35.5 | 75 |
| 6/3/1997 | 1997 | 6 | 3 | 3 | 44 | 95 | 69.5 | 37.5 | 112.5 |
| 6/4/1997 | 1997 | 6 | 4 | 4 | 55 | 93 | 74 | 42 | 154.5 |
| 6/5/1997 | 1997 | 6 | 5 | 5 | 58 | 85 | 71.5 | 39.5 | 194 |
| 6/6/1997 | 1997 | 6 | 6 | 6 | 51 | 66 | 58.5 | 26.5 | 220.5 |
| 6/7/1997 | 1997 | 6 | 7 | 7 | 42 | 65 | 53.5 | 21.5 | 242 |
| 6/8/1997 | 1997 | 6 | 8 | 8 | 40 | 70 | 55 | 23 | 265 |
| 6/9/1997 | 1997 | 6 | 9 | 9 | 51 | 80 | 65.5 | 33.5 | 298.5 |
| 6/10/1997 | 1997 | 6 | 10 | 10 | 45 | 87 | 66 | 34 | 332.5 |
| 6/11/1997 | 1997 | 6 | 11 | 11 | 48 | 84 | 66 | 34 | 366.5 |
| 6/12/1997 | 1997 | 6 | 12 | 12 | 45 | 72 | 58.5 | 26.5 | 393 |
| 6/13/1997 | 1997 | 6 | 13 | 13 | 47 | 85 | 66 | 34 | 427 |
| 6/14/1997 | 1997 | 6 | 14 | 14 | 43 | 85 | 64 | 32 | 459 |
| 6/15/1997 | 1997 | 6 | 15 | 15 | 42 | 78 | 60 | 28 | 487 |
| 6/16/1997 | 1997 | 6 | 16 | 16 | 42 | 81 | 61.5 | 29.5 | 516.5 |
| 6/17/1997 | 1997 | 6 | 17 | 17 | 47 | 88 | 67.5 | 35.5 | 552 |
| 6/18/1997 | 1997 | 6 | 18 | 18 | 47 | 87 | 67 | 35 | 587 |
| 6/19/1997 | 1997 | 6 | 19 | 19 | 50 | 91 | 70.5 | 38.5 | 625.5 |
| 6/20/1997 | 1997 | 6 | 20 | 20 | 45 | 91 | 68 | 36 | 661.5 |
| 6/21/1997 | 1997 | 6 | 21 | 21 | 47 | 94 | 70.5 | 38.5 | 700 |
| 6/22/1997 | 1997 | 6 | 22 | 22 | 47 | 94 | 70.5 | 38.5 | 738.5 |
| 6/23/1997 | 1997 | 6 | 23 | 23 | 45 | 90 | 67.5 | 35.5 | 774 |
| 6/24/1997 | 1997 | 6 | 24 | 24 | 48 | 91 | 69.5 | 37.5 | 811.5 |
| 6/25/1997 | 1997 | 6 | 25 | 25 | 57 | 93 | 75 | 43 | 854.5 |
| 6/26/1997 | 1997 | 6 | 26 | 26 | 49 | 89 | 69 | 37 | 891.5 |
| 6/27/1997 | 1997 | 6 | 27 | 27 | 49 | 87 | 68 | 36 | 927.5 |
| 6/28/1997 | 1997 | 6 | 28 | 28 | 50 | 90 | 70 | 38 | 965.5 |
| 6/29/1997 | 1997 | 6 | 29 | 29 | 49 | 92 | 70.5 | 38.5 | 1004 |
| 6/30/1997 | 1997 | 6 | 30 | 30 | 53 | 97 | 75 | 43 | 1047 |
| 7/1/1997 | 1997 | 7 | 1 | 31 | 42 | 95 | 68.5 | 36.5 | 1083.5 |
| 7/2/1997 | 1997 | 7 | 2 | 32 | 49 | 100 | 74.5 | 42.5 | 1126 |
| 7/3/1997 | 1997 | 7 | 3 | 33 | 58 | 96 | 77 | 45 | 1171 |
| 7/4/1997 | 1997 | 7 | 4 | 34 | 56 | 87 | 71.5 | 39.5 | 1210.5 |
| 7/5/1997 | 1997 | 7 | 5 | 35 | 49 | 95 | 72 | 40 | 1250.5 |
| 7/6/1997 | 1997 | 7 | 6 | 36 | 52 | 93 | 72.5 | 40.5 | 1291 |
| 7/7/1997 | 1997 | 7 | 7 | 37 | 56 | 96 | 76 | 44 | 1335 |
| 7/8/1997 | 1997 | 7 | 8 | 38 | 56 | 89 | 72.5 | 40.5 | 1375.5 |
| 7/9/1997 | 1997 | 7 | 9 | 39 | 55 | 90 | 72.5 | 40.5 | 1416 |
| 7/10/1997 | 1997 | 7 | 10 | 40 | 57 | 87 | 72 | 40 | 1456 |
| 7/11/1997 | 1997 | 7 | 11 | 41 | 49 | 86 | 67.5 | 35.5 | 1491.5 |
| 7/12/1997 | 1997 | 7 | 12 | 42 | 50 | 92 | 71 | 39 | 1530.5 |
| 7/13/1997 | 1997 | 7 | 13 | 43 | 51 | 98 | 74.5 | 42.5 | 1573 |
| 7/14/1997 | 1997 | 7 | 14 | 44 | 58 | 98 | 78 | 46 | 1619 |
| 7/15/1997 | 1997 | 7 | 15 | 45 | 56 | 97 | 76.5 | 44.5 | 1663.5 |
| 7/16/1997 | 1997 | 7 | 16 | 46 | 55 | 95 | 75 | 43 | 1706.5 |
| 7/17/1997 | 1997 | 7 | 17 | 47 | 55 | 96 | 75.5 | 43.5 | 1750 |
| 7/18/1997 | 1997 | 7 | 18 | 48 | 60 | 92 | 76 | 44 | 1794 |
| 7/19/1997 | 1997 | 7 | 19 | 49 | 55 | 88 | 71.5 | 39.5 | 1833.5 |
| 7/20/1997 | 1997 | 7 | 20 | 50 | 55 | 86 | 70.5 | 38.5 | 1872 |
| 7/21/1997 | 1997 | 7 | 21 | 51 | 58 | 92 | 75 | 43 | 1915 |
| 7/22/1997 | 1997 | 7 | 22 | 52 | 57 | 92 | 74.5 | 42.5 | 1957.5 |
| 7/23/1997 | 1997 | 7 | 23 | 53 | 51 | 88 | 69.5 | 37.5 | 1995 |
| 7/24/1997 | 1997 | 7 | 24 | 54 | 55 | 91 | 73 | 41 | 2036 |
| 7/25/1997 | 1997 | 7 | 25 | 55 | 64 | 95 | 79.5 | 47.5 | 2083.5 |
| 7/26/1997 | 1997 | 7 | 26 | 56 | 51 | 80 | 65.5 | 33.5 | 2117 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/27/1997 | 1997 | 7 | 27 | 57 | 57 | 83 | 70 | 38 | 2155 |
| 7/28/1997 | 1997 | 7 | 28 | 58 | 57 | 72 | 64.5 | 32.5 | 2187.5 |
| 7/29/1997 | 1997 | 7 | 29 | 59 | 57 | 78 | 67.5 | 35.5 | 2223 |
| 7/30/1997 | 1997 | 7 | 30 | 60 | 57 | 75 | 66 | 34 | 2257 |
| 7/31/1997 | 1997 | 7 | 31 | 61 | 55 | 81 | 68 | 36 | 2293 |
| 8/1/1997 | 1997 | 8 | 1 | 62 | 59 | 87 | 73 | 41 | 2334 |
| 8/2/1997 | 1997 | 8 | 2 | 63 | 56 | 89 | 72.5 | 40.5 | 2374.5 |
| 8/3/1997 | 1997 | 8 | 3 | 64 | 58 | 86 | 72 | 40 | 2414.5 |
| 8/4/1997 | 1997 | 8 | 4 | 65 | 58 | 88 | 73 | 41 | 2455.5 |
| 8/5/1997 | 1997 | 8 | 5 | 66 | 54 | 82 | 68 | 36 | 2491.5 |
| 8/6/1997 | 1997 | 8 | 6 | 67 | 54 | 82 | 68 | 36 | 2527.5 |
| 8/7/1997 | 1997 | 8 | 7 | 68 | 54 | 84 | 69 | 37 | 2564.5 |
| 8/8/1997 | 1997 | 8 | 8 | 69 | 53 | 90 | 71.5 | 39.5 | 2604 |
| 8/9/1997 | 1997 | 8 | 9 | 70 | 55 | 90 | 72.5 | 40.5 | 2644.5 |
| 8/10/1997 | 1997 | 8 | 10 | 71 | 51 | 81 | 66 | 34 | 2678.5 |
| 8/11/1997 | 1997 | 8 | 11 | 72 | 51 | 81 | 66 | 34 | 2712.5 |
| 8/12/1997 | 1997 | 8 | 12 | 73 | 50 | 85 | 67.5 | 35.5 | 2748 |
| 8/13/1997 | 1997 | 8 | 13 | 74 | 55 | 85 | 70 | 38 | 2786 |
| 8/14/1997 | 1997 | 8 | 14 | 75 | 49 | 88 | 68.5 | 36.5 | 2822.5 |
| 8/15/1997 | 1997 | 8 | 15 | 76 | 45 | 86 | 65.5 | 33.5 | 2856 |
| 8/16/1997 | 1997 | 8 | 16 | 77 | 49 | 89 | 69 | 37 | 2893 |
| 8/17/1997 | 1997 | 8 | 17 | 78 | 52 | 88 | 70 | 38 | 2931 |
| 8/18/1997 | 1997 | 8 | 18 | 79 | 50 | 84 | 67 | 35 | 2966 |
| 8/19/1997 | 1997 | 8 | 19 | 80 | 49 | 88 | 68.5 | 36.5 | 3002.5 |
| 8/20/1997 | 1997 | 8 | 20 | 81 | 59 | 91 | 75 | 43 | 3045.5 |
| 8/21/1997 | 1997 | 8 | 21 | 82 | 54 | 89 | 71.5 | 39.5 | 3085 |
| 8/22/1997 | 1997 | 8 | 22 | 83 | 58 | 92 | 75 | 43 | 3128 |
| 8/23/1997 | 1997 | 8 | 23 | 84 | 58 | 89 | 73.5 | 41.5 | 3169.5 |
| 8/24/1997 | 1997 | 8 | 24 | 85 | 56 | 89 | 72.5 | 40.5 | 3210 |
| 8/25/1997 | 1997 | 8 | 25 | 86 | 54 | 89 | 71.5 | 39.5 | 3249.5 |
| 8/26/1997 | 1997 | 8 | 26 | 87 | 52 | 91 | 71.5 | 39.5 | 3289 |
| 8/27/1997 | 1997 | 8 | 27 | 88 | 56 | 93 | 74.5 | 42.5 | 3331.5 |
| 8/28/1997 | 1997 | 8 | 28 | 89 | 56 | 93 | 74.5 | 42.5 | 3374 |
| 8/29/1997 | 1997 | 8 | 29 | 90 | 50 | 90 | 70 | 38 | 3412 |
| 8/30/1997 | 1997 | 8 | 30 | 91 | 55 | 89 | 72 | 40 | 3452 |
| 8/31/1997 | 1997 | 8 | 31 | 92 | 53 | 80 | 66.5 | 34.5 | 3486.5 |
| 9/1/1997 | 1997 | 9 | 1 | 93 | 47 | 87 | 67 | 35 | 3521.5 |
| 9/2/1997 | 1997 | 9 | 2 | 94 | 60 | 89 | 74.5 | 42.5 | 3564 |
| 9/3/1997 | 1997 | 9 | 3 | 95 | 59 | 89 | 74 | 42 | 3606 |
| 9/4/1997 | 1997 | 9 | 4 | 96 | 55 | 85 | 70 | 38 | 3644 |
| 9/5/1997 | 1997 | 9 | 5 | 97 | 55 | 89 | 72 | 40 | 3684 |
| 9/6/1997 | 1997 | 9 | 6 | 98 | 58 | 87 | 72.5 | 40.5 | 3724.5 |
| 9/7/1997 | 1997 | 9 | 7 | 99 | 54 | 89 | 71.5 | 39.5 | 3764 |
| 9/8/1997 | 1997 | 9 | 8 | 100 | 57 | 88 | 72.5 | 40.5 | 3804.5 |
| 9/9/1997 | 1997 | 9 | 9 | 101 | 52 | 86 | 69 | 37 | 3841.5 |
| 9/10/1997 | 1997 | 9 | 10 | 102 | 53 | 85 | 69 | 37 | 3878.5 |
| 9/11/1997 | 1997 | 9 | 11 | 103 | 50 | 85 | 67.5 | 35.5 | 3914 |
| 9/12/1997 | 1997 | 9 | 12 | 104 | 47 | 84 | 65.5 | 33.5 | 3947.5 |
| 9/13/1997 | 1997 | 9 | 13 | 105 | 47 | 84 | 65.5 | 33.5 | 3981 |
| 9/14/1997 | 1997 | 9 | 14 | 106 | 50 | 80 | 65 | 33 | 4014 |
| 9/15/1997 | 1997 | 9 | 15 | 107 | 50 | 79 | 64.5 | 32.5 | 4046.5 |
| 9/16/1997 | 1997 | 9 | 16 | 108 | 46 | 84 | 65 | 33 | 4079.5 |
| 9/17/1997 | 1997 | 9 | 17 | 109 | 43 | 86 | 64.5 | 32.5 | 4112 |
| 9/18/1997 | 1997 | 9 | 18 | 110 | 49 | 89 | 69 | 37 | 4149 |
| 9/19/1997 | 1997 | 9 | 19 | 111 | 51 | 88 | 69.5 | 37.5 | 4186.5 |
| 9/20/1997 | 1997 | 9 | 20 | 112 | 48 | 88 | 68 | 36 | 4222.5 |
| 9/21/1997 | 1997 | 9 | 21 | 113 | 47 | 64 | 55.5 | 23.5 | 4246 |
| 9/22/1997 | 1997 | 9 | 22 | 114 | 42 | 78 | 60 | 28 | 4274 |
| 9/23/1997 | 1997 | 9 | 23 | 115 | 49 | 77 | 63 | 31 | 4305 |
| 9/24/1997 | 1997 | 9 | 24 | 116 | 48 | 76 | 62 | 30 | 4335 |
| 9/25/1997 | 1997 | 9 | 25 | 117 | 57 | 89 | 73 | 41 | 4376 |
| 9/26/1997 | 1997 | 9 | 26 | 118 | 48 | 81 | 64.5 | 32.5 | 4408.5 |
| 9/27/1997 | 1997 | 9 | 27 | 119 | 45 | 83 | 64 | 32 | 4440.5 |
| 9/28/1997 | 1997 | 9 | 28 | 120 | 45 | 83 | 64 | 32 | 4472.5 |
| 9/29/1997 | 1997 | 9 | 29 | 121 | 45 | 86 | 65.5 | 33.5 | 4506 |
| 9/30/1997 | 1997 | 9 | 30 | 122 | 45 | 83 | 64 | 32 | 4538 |
| 10/1/1997 | 1997 | 10 | 1 | 123 | 45 | 85 | 65 | 33 | 4571 |
| 10/2/1997 | 1997 | 10 | 2 | 124 | 49 | 85 | 67 | 35 | 4606 |
| 10/3/1997 | 1997 | 10 | 3 | 125 | 40 | 84 | 62 | 30 | 4636 |
| 10/4/1997 | 1997 | 10 | 4 | 126 | 38 | 81 | 59.5 | 27.5 | 4663.5 |
| 10/5/1997 | 1997 | 10 | 5 | 127 | 38 | 85 | 61.5 | 29.5 | 4693 |
| 10/6/1997 | 1997 | 10 | 6 | 128 | 46 | 84 | 65 | 33 | 4726 |
| 10/7/1997 | 1997 | 10 | 7 | 129 | 35 | 85 | 60 | 28 | 4754 |
| 10/8/1997 | 1997 | 10 | 8 | 130 | 28 | 67 | 47.5 | 15.5 | 4769.5 |
| 10/9/1997 | 1997 | 10 | 9 | 131 | 47 | 75 | 61 | 29 | 4798.5 |
| 10/10/1997 | 1997 | 10 | 10 | 132 | 47 | 75 | 61 | 29 | 4827.5 |
| 10/11/1997 | 1997 | 10 | 11 | 133 | 32 | 75 | 53.5 | 21.5 | 4849 |
| 10/12/1997 | 1997 | 10 | 12 | 134 | 23 | 75 | 49 | 17 | 4866 |
| 10/13/1997 | 1997 | 10 | 13 | 135 | 23 | 75 | 49 | 17 | 4883 |
| 10/14/1997 | 1997 | 10 | 14 | 136 | 23 | 75 | 49 | 17 | 4900 |
| 10/15/1997 | 1997 | 10 | 15 | 137 | 28 | 76 | 52 | 20 | 4920 |
| 10/16/1997 | 1997 | 10 | 16 | 138 | 28 | 75 | 51.5 | 19.5 | 4939.5 |
| 10/17/1997 | 1997 | 10 | 17 | 139 | 29 | 78 | 53.5 | 21.5 | 4961 |
| 10/18/1997 | 1997 | 10 | 18 | 140 | 28 | 76 | 52 | 20 | 4981 |
| 10/19/1997 | 1997 | 10 | 19 | 141 | 30 | 76 | 53 | 21 | 5002 |
| 10/20/1997 | 1997 | 10 | 20 | 142 | 33 | 76 | 54.5 | 22.5 | 5024.5 |
| 10/21/1997 | 1997 | 10 | 21 | 143 | 35 | 78 | 56.5 | 24.5 | 5049 |
| 10/22/1997 | 1997 | 10 | 22 | 144 | 36 | 54 | 45 | 13 | 5062 |
| 10/23/1997 | 1997 | 10 | 23 | 145 | 36 | 64 | 50 | 18 | 5080 |
| 10/24/1997 | 1997 | 10 | 24 | 146 | 11 | 54 | 32.5 | 0.5 | 5080.5 |
| 10/25/1997 | 1997 | 10 | 25 | 147 | 17 | 35 | 26 | -6 | 5074.5 |
| 10/26/1997 | 1997 | 10 | 26 | 148 | 19 | 51 | 35 | 3 | 5077.5 |
| 10/27/1997 | 1997 | 10 | 27 | 149 | 19 | 63 | 41 | 9 | 5086.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/28/1997 | 1997 | 10 | 28 | 150 | 19 | 63 | 41 | 9 | 5095.5 |
| 10/29/1997 | 1997 | 10 | 29 | 151 | 23 | 67 | 45 | 13 | 5108.5 |
| 10/30/1997 | 1997 | 10 | 30 | 152 | 27 | 68 | 47.5 | 15.5 | 5124 |
| 10/31/1997 | 1997 | 10 | 31 | 153 | 28 | 75 | 51.5 | 19.5 | 5143.5 |
| 11/1/1997 | 1997 | 11 | 1 | 154 | 22 | 66 | 44 | 12 | 5155.5 |
| 11/2/1997 | 1997 | 11 | 2 | 155 | 18 | 64 | 41 | 9 | 5164.5 |
| 11/3/1997 | 1997 | 11 | 3 | 156 | 20 | 69 | 44.5 | 12.5 | 5177 |
| 11/4/1997 | 1997 | 11 | 4 | 157 | 21 | 70 | 45.5 | 13.5 | 5190.5 |
| 11/5/1997 | 1997 | 11 | 5 | 158 | 21 | 72 | 46.5 | 14.5 | 5205 |
| 11/6/1997 | 1997 | 11 | 6 | 159 | 21 | 71 | 46 | 14 | 5219 |
| 11/7/1997 | 1997 | 11 | 7 | 160 | 20 | 70 | 45 | 13 | 5232 |
| 11/8/1997 | 1997 | 11 | 8 | 161 | 24 | 70 | 47 | 15 | 5247 |
| 11/9/1997 | 1997 | 11 | 9 | 162 | 24 | 55 | 39.5 | 7.5 | 5254.5 |
| 11/10/1997 | 1997 | 11 | 10 | 163 | 31 | 47 | 39 | 7 | 5261.5 |
| 11/11/1997 | 1997 | 11 | 11 | 164 | 30 | 49 | 39.5 | 7.5 | 5269 |
| 11/12/1997 | 1997 | 11 | 12 | 165 | 31 | 50 | 40.5 | 8.5 | 5277.5 |
| 11/13/1997 | 1997 | 11 | 13 | 166 | 31 | 49 | 40 | 8 | 5285.5 |
| 11/14/1997 | 1997 | 11 | 14 | 167 | 21 | 47 | 34 | 2 | 5287.5 |
| 11/15/1997 | 1997 | 11 | 15 | 168 | 16 | 42 | 29 | -3 | 5284.5 |
| 11/16/1997 | 1997 | 11 | 16 | 169 | 18 | 50 | 34 | 2 | 5286.5 |
| 11/17/1997 | 1997 | 11 | 17 | 170 | 16 | 48 | 32 | 0 | 5286.5 |
| 11/18/1997 | 1997 | 11 | 18 | 171 | 16 | 51 | 33.5 | 1.5 | 5288 |
| 11/19/1997 | 1997 | 11 | 19 | 172 | 32 | 61 | 46.5 | 14.5 | 5302.5 |
| 11/20/1997 | 1997 | 11 | 20 | 173 | 23 | 60 | 41.5 | 9.5 | 5312 |
| 11/21/1997 | 1997 | 11 | 21 | 174 | 19 | 55 | 37 | 5 | 5317 |
| 11/22/1997 | 1997 | 11 | 22 | 175 | 19 | 55 | 37 | 5 | 5322 |
| 11/23/1997 | 1997 | 11 | 23 | 176 | 17 | 67 | 42 | 10 | 5332 |
| 11/24/1997 | 1997 | 11 | 24 | 177 | 21 | 67 | 44 | 12 | 5344 |
| 11/25/1997 | 1997 | 11 | 25 | 178 | 30 | 65 | 47.5 | 15.5 | 5359.5 |
| 11/26/1997 | 1997 | 11 | 26 | 179 | 34 | 52 | 43 | 11 | 5370.5 |
| 11/28/1997 | 1997 | 11 | 28 | 180 | 19 | 50 | 34.5 | 2.5 | 5373 |
| 11/29/1997 | 1997 | 11 | 29 | 181 | 16 | 55 | 35.5 | 3.5 | 5376.5 |
| 11/30/1997 | 1997 | 11 | 30 | 182 | 29 | 52 | 40.5 | 8.5 | 5385 |
| 12/1/1997 | 1997 | 12 | 1 | 183 | 30 | 43 | 36.5 | 4.5 | 5389.5 |
| 12/2/1997 | 1997 | 12 | 2 | 184 | 25 | 42 | 33.5 | 1.5 | 5391 |
| 12/3/1997 | 1997 | 12 | 3 | 185 | 10 | 41 | 25.5 | -6.5 | 5384.5 |
| 12/4/1997 | 1997 | 12 | 4 | 186 | 10 | 47 | 28.5 | -3.5 | 5381 |
| 12/5/1997 | 1997 | 12 | 5 | 187 | 11 | 52 | 31.5 | -0.5 | 5380.5 |
| 12/6/1997 | 1997 | 12 | 6 | 188 | 30 | 55 | 42.5 | 10.5 | 5391 |
| 12/7/1997 | 1997 | 12 | 7 | 189 | 33 | 50 | 41.5 | 9.5 | 5400.5 |
| 12/8/1997 | 1997 | 12 | 8 | 190 | 23 | 43 | 33 | 1 | 5401.5 |
| 12/9/1997 | 1997 | 12 | 9 | 191 | 15 | 42 | 28.5 | -3.5 | 5398 |
| 12/10/1997 | 1997 | 12 | 10 | 192 | 16 | 31 | 23.5 | -8.5 | 5389.5 |
| 12/11/1997 | 1997 | 12 | 11 | 193 | 3 | 32 | 17.5 | -14.5 | 5375 |
| 12/12/1997 | 1997 | 12 | 12 | 194 | 9 | 36 | 22.5 | -9.5 | 5365.5 |
| 12/13/1997 | 1997 | 12 | 13 | 195 | 12 | 42 | 27 | -5 | 5360.5 |
| 12/14/1997 | 1997 | 12 | 14 | 196 | 13 | 57 | 35 | 3 | 5363.5 |
| 12/15/1997 | 1997 | 12 | 15 | 197 | 12 | 56 | 34 | 2 | 5365.5 |
| 12/16/1997 | 1997 | 12 | 16 | 198 | 13 | 58 | 35.5 | 3.5 | 5369 |
| 12/17/1997 | 1997 | 12 | 17 | 199 | 16 | 54 | 35 | 3 | 5372 |
| 12/18/1997 | 1997 | 12 | 18 | 200 | 17 | 57 | 37 | 5 | 5377 |
| 12/19/1997 | 1997 | 12 | 19 | 201 | 27 | 58 | 42.5 | 10.5 | 5387.5 |
| 12/20/1997 | 1997 | 12 | 20 | 202 | 27 | 58 | 42.5 | 10.5 | 5398 |
| 12/21/1997 | 1997 | 12 | 21 | 203 | 25 | 46 | 35.5 | 3.5 | 5401.5 |
| 12/22/1997 | 1997 | 12 | 22 | 204 | 25 | 34 | 29.5 | -2.5 | 5399 |
| 12/23/1997 | 1997 | 12 | 23 | 205 | 6 | 35 | 20.5 | -11.5 | 5387.5 |
| 12/24/1997 | 1997 | 12 | 24 | 206 | 4 | 38 | 21 | -11 | 5376.5 |
| 12/25/1997 | 1997 | 12 | 25 | 207 | -1 | 29 | 14 | -18 | 5358.5 |
| 12/26/1997 | 1997 | 12 | 26 | 208 | -14 | 27 | 6.5 | -25.5 | 5333 |
| 12/27/1997 | 1997 | 12 | 27 | 209 | 10 | 35 | 22.5 | -9.5 | 5323.5 |
| 12/28/1997 | 1997 | 12 | 28 | 210 | 1 | 31 | 16 | -16 | 5307.5 |
| 12/29/1997 | 1997 | 12 | 29 | 211 | 4 | 44 | 24 | -8 | 5299.5 |
| 1/1/1998 | 1998 | 1 | 1 | 212 | 15 | 54 | 34.5 | 2.5 | 5302 |
| 1/2/1998 | 1998 | 1 | 2 | 213 | 25 | 48 | 36.5 | 4.5 | 5306.5 |
| 1/3/1998 | 1998 | 1 | 3 | 214 | 24 | 51 | 37.5 | 5.5 | 5312 |
| 1/4/1998 | 1998 | 1 | 4 | 215 | 22 | 45 | 33.5 | 1.5 | 5313.5 |
| 1/5/1998 | 1998 | 1 | 5 | 216 | 14 | 40 | 27 | -5 | 5308.5 |
| 1/6/1998 | 1998 | 1 | 6 | 217 | 10 | 32 | 21 | -11 | 5297.5 |
| 1/7/1998 | 1998 | 1 | 7 | 218 | 11 | 45 | 28 | -4 | 5293.5 |
| 1/8/1998 | 1998 | 1 | 8 | 219 | 24 | 48 | 36 | 4 | 5297.5 |
| 1/9/1998 | 1998 | 1 | 9 | 220 | 28 | 53 | 40.5 | 8.5 | 5306 |
| 1/10/1998 | 1998 | 1 | 10 | 221 | 27 | 47 | 37 | 5 | 5311 |
| 1/11/1998 | 1998 | 1 | 11 | 222 | 20 | 48 | 34 | 2 | 5313 |
| 1/12/1998 | 1998 | 1 | 12 | 223 | 22 | 53 | 37.5 | 5.5 | 5318.5 |
| 1/13/1998 | 1998 | 1 | 13 | 224 | 20 | 44 | 32 | 0 | 5318.5 |
| 1/14/1998 | 1998 | 1 | 14 | 225 | 14 | 42 | 28 | -4 | 5314.5 |
| 1/15/1998 | 1998 | 1 | 15 | 226 | 30 | 53 | 41.5 | 9.5 | 5324 |
| 1/16/1998 | 1998 | 1 | 16 | 227 | 24 | 51 | 37.5 | 5.5 | 5329.5 |
| 1/17/1998 | 1998 | 1 | 17 | 228 | 25 | 55 | 40 | 8 | 5337.5 |
| 1/18/1998 | 1998 | 1 | 18 | 229 | 22 | 57 | 39.5 | 7.5 | 5345 |
| 1/19/1998 | 1998 | 1 | 19 | 230 | 24 | 60 | 42 | 10 | 5355 |
| 1/20/1998 | 1998 | 1 | 20 | 231 | 26 | 44 | 35 | 3 | 5358 |
| 1/21/1998 | 1998 | 1 | 21 | 232 | 15 | 45 | 30 | -2 | 5356 |
| 1/22/1998 | 1998 | 1 | 22 | 233 | 20 | 50 | 35 | 3 | 5359 |
| 1/23/1998 | 1998 | 1 | 23 | 234 | 18 | 49 | 33.5 | 1.5 | 5360.5 |
| 1/24/1998 | 1998 | 1 | 24 | 235 | 20 | 54 | 37 | 5 | 5365.5 |
| 1/25/1998 | 1998 | 1 | 25 | 236 | 19 | 60 | 39.5 | 7.5 | 5373 |
| 1/26/1998 | 1998 | 1 | 26 | 237 | 18 | 58 | 38 | 6 | 5379 |
| 1/27/1998 | 1998 | 1 | 27 | 238 | 14 | 58 | 36 | 4 | 5383 |
| 1/28/1998 | 1998 | 1 | 28 | 239 | 14 | 63 | 38.5 | 6.5 | 5389.5 |
| 1/29/1998 | 1998 | 1 | 29 | 240 | 19 | 61 | 40 | 8 | 5397.5 |
| 1/30/1998 | 1998 | 1 | 30 | 241 | 16 | 47 | 31.5 | -0.5 | 5397 |
| 1/31/1998 | 1998 | 1 | 31 | 242 | 14 | 51 | 32.5 | 0.5 | 5397.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/1/1998 | 1998 | 2 | 1 | 243 | 16 | 51 | 33.5 | 1.5 | 5399 |
| 2/2/1998 | 1998 | 2 | 2 | 244 | 18 | 60 | 39 | 7 | 5406 |
| 2/3/1998 | 1998 | 2 | 3 | 245 | 26 | 53 | 39.5 | 7.5 | 5413.5 |
| 2/4/1998 | 1998 | 2 | 4 | 246 | 30 | 45 | 37.5 | 5.5 | 5419 |
| 2/5/1998 | 1998 | 2 | 5 | 247 | 17 | 46 | 31.5 | -0.5 | 5418.5 |
| 2/6/1998 | 1998 | 2 | 6 | 248 | 17 | 46 | 31.5 | -0.5 | 5418 |
| 2/7/1998 | 1998 | 2 | 7 | 249 | 23 | 44 | 33.5 | 1.5 | 5419.5 |
| 2/8/1998 | 1998 | 2 | 8 | 250 | 25 | 49 | 37 | 5 | 5424.5 |
| 2/9/1998 | 1998 | 2 | 9 | 251 | 28 | 40 | 34 | 2 | 5426.5 |
| 2/10/1998 | 1998 | 2 | 10 | 252 | 14 | 49 | 31.5 | -0.5 | 5426 |
| 2/11/1998 | 1998 | 2 | 11 | 253 | 19 | 50 | 34.5 | 2.5 | 5428.5 |
| 2/12/1998 | 1998 | 2 | 12 | 254 | 13 | 50 | 31.5 | -0.5 | 5428 |
| 2/13/1998 | 1998 | 2 | 13 | 255 | 21 | 56 | 38.5 | 6.5 | 5434.5 |
| 2/14/1998 | 1998 | 2 | 14 | 256 | 32 | 55 | 43.5 | 11.5 | 5446 |
| 2/15/1998 | 1998 | 2 | 15 | 257 | 32 | 55 | 43.5 | 11.5 | 5457.5 |
| 2/16/1998 | 1998 | 2 | 16 | 258 | 15 | 45 | 30 | -2 | 5455.5 |
| 2/17/1998 | 1998 | 2 | 17 | 259 | 28 | 46 | 37 | 5 | 5460.5 |
| 2/18/1998 | 1998 | 2 | 18 | 260 | 18 | 48 | 33 | 1 | 5461.5 |
| 2/19/1998 | 1998 | 2 | 19 | 261 | 24 | 52 | 38 | 6 | 5467.5 |
| 2/20/1998 | 1998 | 2 | 20 | 262 | 28 | 46 | 37 | 5 | 5472.5 |
| 2/21/1998 | 1998 | 2 | 21 | 263 | 25 | 54 | 39.5 | 7.5 | 5480 |
| 2/22/1998 | 1998 | 2 | 22 | 264 | 29 | 51 | 40 | 8 | 5488 |
| 2/23/1998 | 1998 | 2 | 23 | 265 | 31 | 60 | 45.5 | 13.5 | 5501.5 |
| 2/24/1998 | 1998 | 2 | 24 | 266 | 26 | 65 | 45.5 | 13.5 | 5515 |
| 2/25/1998 | 1998 | 2 | 25 | 267 | 14 | 41 | 27.5 | -4.5 | 5510.5 |
| 2/26/1998 | 1998 | 2 | 26 | 268 | 20 | 43 | 31.5 | -0.5 | 5510 |
| 3/1/1998 | 1998 | 3 | 1 | 269 | 11 | 49 | 30 | -2 | 5508 |
| 3/2/1998 | 1998 | 3 | 2 | 270 | 15 | 57 | 36 | 4 | 5512 |
| 3/3/1998 | 1998 | 3 | 3 | 271 | 33 | 63 | 48 | 16 | 5528 |
| 3/4/1998 | 1998 | 3 | 4 | 272 | 38 | 62 | 50 | 18 | 5546 |
| 3/5/1998 | 1998 | 3 | 5 | 273 | 28 | 62 | 45 | 13 | 5559 |
| 3/7/1998 | 1998 | 3 | 7 | 274 | 13 | 50 | 31.5 | -0.5 | 5558.5 |
| 3/8/1998 | 1998 | 3 | 8 | 275 | 14 | 57 | 35.5 | 3.5 | 5562 |
| 3/9/1998 | 1998 | 3 | 9 | 276 | 13 | 51 | 32 | 0 | 5562 |
| 3/10/1998 | 1998 | 3 | 10 | 277 | 17 | 59 | 38 | 6 | 5568 |
| 3/11/1998 | 1998 | 3 | 11 | 278 | 23 | 61 | 42 | 10 | 5578 |
| 3/12/1998 | 1998 | 3 | 12 | 279 | 20 | 65 | 42.5 | 10.5 | 5588.5 |
| 3/13/1998 | 1998 | 3 | 13 | 280 | 27 | 64 | 45.5 | 13.5 | 5602 |
| 3/14/1998 | 1998 | 3 | 14 | 281 | 32 | 56 | 44 | 12 | 5614 |
| 3/15/1998 | 1998 | 3 | 15 | 282 | 34 | 40 | 37 | 5 | 5619 |
| 3/16/1998 | 1998 | 3 | 16 | 283 | 30 | 52 | 41 | 9 | 5628 |
| 3/17/1998 | 1998 | 3 | 17 | 284 | 32 | 59 | 45.5 | 13.5 | 5641.5 |
| 3/18/1998 | 1998 | 3 | 18 | 285 | 20 | 47 | 33.5 | 1.5 | 5643 |
| 3/19/1998 | 1998 | 3 | 19 | 286 | 22 | 59 | 40.5 | 8.5 | 5651.5 |
| 3/20/1998 | 1998 | 3 | 20 | 287 | 29 | 64 | 46.5 | 14.5 | 5666 |
| 3/21/1998 | 1998 | 3 | 21 | 288 | 25 | 67 | 46 | 14 | 5680 |
| 3/22/1998 | 1998 | 3 | 22 | 289 | 30 | 74 | 52 | 20 | 5700 |
| 3/23/1998 | 1998 | 3 | 23 | 290 | 30 | 76 | 53 | 21 | 5721 |
| 3/24/1998 | 1998 | 3 | 24 | 291 | 35 | 78 | 56.5 | 24.5 | 5745.5 |
| 3/25/1998 | 1998 | 3 | 25 | 292 | 37 | 76 | 56.5 | 24.5 | 5770 |
| 3/26/1998 | 1998 | 3 | 26 | 293 | 35 | 55 | 45 | 13 | 5783 |
| 3/27/1998 | 1998 | 3 | 27 | 294 | 30 | 62 | 46 | 14 | 5797 |
| 3/28/1998 | 1998 | 3 | 28 | 295 | 27 | 63 | 45 | 13 | 5810 |
| 3/29/1998 | 1998 | 3 | 29 | 296 | 27 | 63 | 45 | 13 | 5823 |
| 3/30/1998 | 1998 | 3 | 30 | 297 | 22 | 43 | 32.5 | 0.5 | 5823.5 |
| 3/31/1998 | 1998 | 3 | 31 | 298 | 19 | 56 | 37.5 | 5.5 | 5829 |
| 4/1/1998 | 1998 | 4 | 1 | 299 | 27 | 67 | 47 | 15 | 5844 |
| 4/2/1998 | 1998 | 4 | 2 | 300 | 23 | 50 | 36.5 | 4.5 | 5848.5 |
| 4/3/1998 | 1998 | 4 | 3 | 301 | 27 | 66 | 46.5 | 14.5 | 5863 |
| 4/4/1998 | 1998 | 4 | 4 | 302 | 27 | 69 | 48 | 16 | 5879 |
| 4/5/1998 | 1998 | 4 | 5 | 303 | 30 | 66 | 48 | 16 | 5895 |
| 4/6/1998 | 1998 | 4 | 6 | 304 | 31 | 54 | 42.5 | 10.5 | 5905.5 |
| 4/7/1998 | 1998 | 4 | 7 | 305 | 27 | 55 | 41 | 9 | 5914.5 |
| 4/8/1998 | 1998 | 4 | 8 | 306 | 19 | 59 | 39 | 7 | 5921.5 |
| 4/9/1998 | 1998 | 4 | 9 | 307 | 21 | 70 | 45.5 | 13.5 | 5935 |
| 4/10/1998 | 1998 | 4 | 10 | 308 | 22 | 73 | 47.5 | 15.5 | 5950.5 |
| 4/11/1998 | 1998 | 4 | 11 | 309 | 38 | 78 | 58 | 26 | 5976.5 |
| 4/12/1998 | 1998 | 4 | 12 | 310 | 32 | 51 | 41.5 | 9.5 | 5986 |
| 4/13/1998 | 1998 | 4 | 13 | 311 | 25 | 66 | 45.5 | 13.5 | 5999.5 |
| 4/14/1998 | 1998 | 4 | 14 | 312 | 25 | 62 | 43.5 | 11.5 | 6011 |
| 4/15/1998 | 1998 | 4 | 15 | 313 | 22 | 51 | 36.5 | 4.5 | 6015.5 |
| 4/16/1998 | 1998 | 4 | 16 | 314 | 16 | 47 | 31.5 | -0.5 | 6015 |
| 4/17/1998 | 1998 | 4 | 17 | 315 | 20 | 57 | 38.5 | 6.5 | 6021.5 |
| 4/18/1998 | 1998 | 4 | 18 | 316 | 17 | 57 | 37 | 5 | 6026.5 |
| 4/19/1998 | 1998 | 4 | 19 | 317 | 26 | 70 | 48 | 16 | 6042.5 |
| 4/20/1998 | 1998 | 4 | 20 | 318 | 24 | 70 | 47 | 15 | 6057.5 |
| 4/21/1998 | 1998 | 4 | 21 | 319 | 27 | 73 | 50 | 18 | 6075.5 |
| 4/22/1998 | 1998 | 4 | 22 | 320 | 27 | 78 | 52.5 | 20.5 | 6096 |
| 4/23/1998 | 1998 | 4 | 23 | 321 | 36 | 80 | 58 | 26 | 6122 |
| 4/24/1998 | 1998 | 4 | 24 | 322 | 43 | 78 | 60.5 | 28.5 | 6150.5 |
| 4/25/1998 | 1998 | 4 | 25 | 323 | 43 | 70 | 56.5 | 24.5 | 6175 |
| 4/26/1998 | 1998 | 4 | 26 | 324 | 28 | 70 | 49 | 17 | 6192 |
| 4/27/1998 | 1998 | 4 | 27 | 325 | 28 | 62 | 45 | 13 | 6205 |
| 4/28/1998 | 1998 | 4 | 28 | 326 | 30 | 63 | 46.5 | 14.5 | 6219.5 |
| 4/29/1998 | 1998 | 4 | 29 | 327 | 30 | 72 | 51 | 19 | 6238.5 |
| 4/30/1998 | 1998 | 4 | 30 | 328 | 32 | 75 | 53.5 | 21.5 | 6260 |
| 5/1/1998 | 1998 | 5 | 1 | 329 | 32 | 75 | 53.5 | 21.5 | 6281.5 |
| 5/2/1998 | 1998 | 5 | 2 | 330 | 33 | 79 | 56 | 24 | 6305.5 |
| 5/3/1998 | 1998 | 5 | 3 | 331 | 34 | 79 | 56.5 | 24.5 | 6330 |
| 5/4/1998 | 1998 | 5 | 4 | 332 | 40 | 75 | 57.5 | 25.5 | 6355.5 |
| 5/5/1998 | 1998 | 5 | 5 | 333 | 37 | 75 | 56 | 24 | 6379.5 |
| 5/6/1998 | 1998 | 5 | 6 | 334 | 33 | 69 | 51 | 19 | 6398.5 |
| 5/7/1998 | 1998 | 5 | 7 | 335 | 32 | 74 | 53 | 21 | 6419.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/8/1998 | 1998 | 5 | 8 | 336 | 39 | 65 | 52 | 20 | 6439.5 |
| 5/9/1998 | 1998 | 5 | 9 | 337 | 32 | 77 | 54.5 | 22.5 | 6462 |
| 5/10/1998 | 1998 | 5 | 10 | 338 | 32 | 77 | 54.5 | 22.5 | 6484.5 |
| 5/11/1998 | 1998 | 5 | 11 | 339 | 31 | 80 | 55.5 | 23.5 | 6508 |
| 5/12/1998 | 1998 | 5 | 12 | 340 | 41 | 80 | 60.5 | 28.5 | 6536.5 |
| 5/13/1998 | 1998 | 5 | 13 | 341 | 38 | 78 | 58 | 26 | 6562.5 |
| 5/14/1998 | 1998 | 5 | 14 | 342 | 29 | 78 | 53.5 | 21.5 | 6584 |
| 5/15/1998 | 1998 | 5 | 15 | 343 | 28 | 74 | 51 | 19 | 6603 |
| 5/16/1998 | 1998 | 5 | 16 | 344 | 35 | 83 | 59 | 27 | 6630 |
| 5/17/1998 | 1998 | 5 | 17 | 345 | 35 | 84 | 59.5 | 27.5 | 6657.5 |
| 5/18/1998 | 1998 | 5 | 18 | 346 | 41 | 88 | 64.5 | 32.5 | 6690 |
| 5/19/1998 | 1998 | 5 | 19 | 347 | 38 | 85 | 61.5 | 29.5 | 6719.5 |
| 5/20/1998 | 1998 | 5 | 20 | 348 | 47 | 77 | 62 | 30 | 6749.5 |
| 5/21/1998 | 1998 | 5 | 21 | 349 | 34 | 83 | 58.5 | 26.5 | 6776 |
| 5/22/1998 | 1998 | 5 | 22 | 350 | 33 | 78 | 55.5 | 23.5 | 6799.5 |
| 5/23/1998 | 1998 | 5 | 23 | 351 | 37 | 78 | 57.5 | 25.5 | 6825 |
| 5/24/1998 | 1998 | 5 | 24 | 352 | 37 | 80 | 58.5 | 26.5 | 6851.5 |
| 5/25/1998 | 1998 | 5 | 25 | 353 | 38 | 79 | 58.5 | 26.5 | 6878 |
| 5/26/1998 | 1998 | 5 | 26 | 354 | 42 | 82 | 62 | 30 | 6908 |
| 5/27/1998 | 1998 | 5 | 27 | 355 | 39 | 88 | 63.5 | 31.5 | 6939.5 |
| 5/28/1998 | 1998 | 5 | 28 | 356 | 40 | 92 | 66 | 34 | 6973.5 |
| 5/29/1998 | 1998 | 5 | 29 | 357 | 43 | 91 | 67 | 35 | 7008.5 |
| 5/30/1998 | 1998 | 5 | 30 | 358 | 42 | 87 | 64.5 | 32.5 | 7041 |
| 5/31/1998 | 1998 | 5 | 31 | 359 | 41 | 91 | 66 | 34 | 7075 |
| 6/1/1998 | 1998 | 6 | 1 | 1 | 43 | 92 | 67.5 | 35.5 | 35.5 |
| 6/2/1998 | 1998 | 6 | 2 | 2 | 43 | 92 | 67.5 | 35.5 | 71 |
| 6/3/1998 | 1998 | 6 | 3 | 3 | 42 | 90 | 66 | 34 | 105 |
| 6/4/1998 | 1998 | 6 | 4 | 4 | 40 | 76 | 58 | 26 | 131 |
| 6/5/1998 | 1998 | 6 | 5 | 5 | 40 | 76 | 58 | 26 | 157 |
| 6/6/1998 | 1998 | 6 | 6 | 6 | 40 | 76 | 58 | 26 | 183 |
| 6/7/1998 | 1998 | 6 | 7 | 7 | 39 | 86 | 62.5 | 30.5 | 213.5 |
| 6/8/1998 | 1998 | 6 | 8 | 8 | 36 | 78 | 57 | 25 | 238.5 |
| 6/9/1998 | 1998 | 6 | 9 | 9 | 37 | 82 | 59.5 | 27.5 | 266 |
| 6/10/1998 | 1998 | 6 | 10 | 10 | 38 | 77 | 57.5 | 25.5 | 291.5 |
| 6/11/1998 | 1998 | 6 | 11 | 11 | 38 | 78 | 58 | 26 | 317.5 |
| 6/12/1998 | 1998 | 6 | 12 | 12 | 46 | 87 | 66.5 | 34.5 | 352 |
| 6/13/1998 | 1998 | 6 | 13 | 13 | 44 | 77 | 60.5 | 28.5 | 380.5 |
| 6/14/1998 | 1998 | 6 | 14 | 14 | 47 | 83 | 65 | 33 | 413.5 |
| 6/15/1998 | 1998 | 6 | 15 | 15 | 54 | 84 | 69 | 37 | 450.5 |
| 6/16/1998 | 1998 | 6 | 16 | 16 | 47 | 90 | 68.5 | 36.5 | 487 |
| 6/17/1998 | 1998 | 6 | 17 | 17 | 35 | 79 | 57 | 25 | 512 |
| 6/18/1998 | 1998 | 6 | 18 | 18 | 37 | 85 | 61 | 29 | 541 |
| 6/19/1998 | 1998 | 6 | 19 | 19 | 44 | 90 | 67 | 35 | 576 |
| 6/20/1998 | 1998 | 6 | 20 | 20 | 44 | 90 | 67 | 35 | 611 |
| 6/21/1998 | 1998 | 6 | 21 | 21 | 41 | 91 | 66 | 34 | 645 |
| 6/22/1998 | 1998 | 6 | 22 | 22 | 48 | 90 | 69 | 37 | 682 |
| 6/23/1998 | 1998 | 6 | 23 | 23 | 53 | 92 | 72.5 | 40.5 | 722.5 |
| 6/24/1998 | 1998 | 6 | 24 | 24 | 42 | 91 | 66.5 | 34.5 | 757 |
| 6/25/1998 | 1998 | 6 | 25 | 25 | 47 | 95 | 71 | 39 | 796 |
| 6/26/1998 | 1998 | 6 | 26 | 26 | 51 | 94 | 72.5 | 40.5 | 836.5 |
| 6/27/1998 | 1998 | 6 | 27 | 27 | 48 | 98 | 73 | 41 | 877.5 |
| 6/28/1998 | 1998 | 6 | 28 | 28 | 49 | 103 | 76 | 44 | 921.5 |
| 6/29/1998 | 1998 | 6 | 29 | 29 | 50 | 102 | 76 | 44 | 965.5 |
| 6/30/1998 | 1998 | 6 | 30 | 30 | 65 | 101 | 83 | 51 | 1016.5 |
| 7/1/1998 | 1998 | 7 | 1 | 31 | 57 | 92 | 74.5 | 42.5 | 1059 |
| 7/2/1998 | 1998 | 7 | 2 | 32 | 59 | 93 | 76 | 44 | 1103 |
| 7/3/1998 | 1998 | 7 | 3 | 33 | 61 | 91 | 76 | 44 | 1147 |
| 7/4/1998 | 1998 | 7 | 4 | 34 | 61 | 90 | 75.5 | 43.5 | 1190.5 |
| 7/5/1998 | 1998 | 7 | 5 | 35 | 58 | 95 | 76.5 | 44.5 | 1235 |
| 7/6/1998 | 1998 | 7 | 6 | 36 | 59 | 87 | 73 | 41 | 1276 |
| 7/7/1998 | 1998 | 7 | 7 | 37 | 59 | 81 | 70 | 38 | 1314 |
| 7/8/1998 | 1998 | 7 | 8 | 38 | 56 | 78 | 67 | 35 | 1349 |
| 7/9/1998 | 1998 | 7 | 9 | 39 | 51 | 69 | 60 | 28 | 1377 |
| 7/10/1998 | 1998 | 7 | 10 | 40 | 54 | 90 | 72 | 40 | 1417 |
| 7/11/1998 | 1998 | 7 | 11 | 41 | 54 | 90 | 72 | 40 | 1457 |
| 7/12/1998 | 1998 | 7 | 12 | 42 | 56 | 96 | 76 | 44 | 1501 |
| 7/13/1998 | 1998 | 7 | 13 | 43 | 57 | 95 | 76 | 44 | 1545 |
| 7/14/1998 | 1998 | 7 | 14 | 44 | 50 | 97 | 73.5 | 41.5 | 1586.5 |
| 7/15/1998 | 1998 | 7 | 15 | 45 | 62 | 100 | 81 | 49 | 1635.5 |
| 7/16/1998 | 1998 | 7 | 16 | 46 | 55 | 92 | 73.5 | 41.5 | 1677 |
| 7/17/1998 | 1998 | 7 | 17 | 47 | 52 | 91 | 71.5 | 39.5 | 1716.5 |
| 7/18/1998 | 1998 | 7 | 18 | 48 | 55 | 95 | 75 | 43 | 1759.5 |
| 7/19/1998 | 1998 | 7 | 19 | 49 | 54 | 99 | 76.5 | 44.5 | 1804 |
| 7/20/1998 | 1998 | 7 | 20 | 50 | 61 | 99 | 80 | 48 | 1852 |
| 7/21/1998 | 1998 | 7 | 21 | 51 | 55 | 96 | 75.5 | 43.5 | 1895.5 |
| 7/22/1998 | 1998 | 7 | 22 | 52 | 56 | 93 | 74.5 | 42.5 | 1938 |
| 7/23/1998 | 1998 | 7 | 23 | 53 | 56 | 86 | 71 | 39 | 1977 |
| 7/24/1998 | 1998 | 7 | 24 | 54 | 57 | 82 | 69.5 | 37.5 | 2014.5 |
| 7/25/1998 | 1998 | 7 | 25 | 55 | 60 | 82 | 71 | 39 | 2053.5 |
| 7/26/1998 | 1998 | 7 | 26 | 56 | 55 | 86 | 70.5 | 38.5 | 2092 |
| 7/27/1998 | 1998 | 7 | 27 | 57 | 58 | 85 | 71.5 | 39.5 | 2131.5 |
| 7/28/1998 | 1998 | 7 | 28 | 58 | 56 | 85 | 70.5 | 38.5 | 2170 |
| 7/29/1998 | 1998 | 7 | 29 | 59 | 57 | 84 | 70.5 | 38.5 | 2208.5 |
| 7/30/1998 | 1998 | 7 | 30 | 60 | 50 | 90 | 70 | 38 | 2246.5 |
| 7/31/1998 | 1998 | 7 | 31 | 61 | 60 | 82 | 71 | 39 | 2285.5 |
| 8/1/1998 | 1998 | 8 | 1 | 62 | 48 | 79 | 63.5 | 31.5 | 2317 |
| 8/2/1998 | 1998 | 8 | 2 | 63 | 51 | 90 | 70.5 | 38.5 | 2355.5 |
| 8/3/1998 | 1998 | 8 | 3 | 64 | 54 | 93 | 73.5 | 41.5 | 2397 |
| 8/4/1998 | 1998 | 8 | 4 | 65 | 56 | 89 | 72.5 | 40.5 | 2437.5 |
| 8/5/1998 | 1998 | 8 | 5 | 66 | 53 | 89 | 71 | 39 | 2476.5 |
| 8/6/1998 | 1998 | 8 | 6 | 67 | 49 | 92 | 70.5 | 38.5 | 2515 |
| 8/7/1998 | 1998 | 8 | 7 | 68 | 55 | 96 | 75.5 | 43.5 | 2558.5 |
| 8/8/1998 | 1998 | 8 | 8 | 69 | 56 | 94 | 75 | 43 | 2601.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/9/1998 | 1998 | 8 | 9 | 70 | 53 | 94 | 73.5 | 41.5 | 2643 |
| 8/10/1998 | 1998 | 8 | 10 | 71 | 54 | 87 | 70.5 | 38.5 | 2681.5 |
| 8/11/1998 | 1998 | 8 | 11 | 72 | 54 | 87 | 70.5 | 38.5 | 2720 |
| 8/12/1998 | 1998 | 8 | 12 | 73 | 48 | 86 | 67 | 35 | 2755 |
| 8/13/1998 | 1998 | 8 | 13 | 74 | 48 | 89 | 68.5 | 36.5 | 2791.5 |
| 8/14/1998 | 1998 | 8 | 14 | 75 | 54 | 90 | 72 | 40 | 2831.5 |
| 8/15/1998 | 1998 | 8 | 15 | 76 | 52 | 89 | 70.5 | 38.5 | 2870 |
| 8/16/1998 | 1998 | 8 | 16 | 77 | 53 | 87 | 70 | 38 | 2908 |
| 8/17/1998 | 1998 | 8 | 17 | 78 | 52 | 92 | 72 | 40 | 2948 |
| 8/18/1998 | 1998 | 8 | 18 | 79 | 51 | 86 | 68.5 | 36.5 | 2984.5 |
| 8/19/1998 | 1998 | 8 | 19 | 80 | 58 | 90 | 74 | 42 | 3026.5 |
| 8/20/1998 | 1998 | 8 | 20 | 81 | 61 | 90 | 75.5 | 43.5 | 3070 |
| 8/21/1998 | 1998 | 8 | 21 | 82 | 55 | 83 | 69 | 37 | 3107 |
| 8/22/1998 | 1998 | 8 | 22 | 83 | 54 | 93 | 73.5 | 41.5 | 3148.5 |
| 8/23/1998 | 1998 | 8 | 23 | 84 | 54 | 93 | 73.5 | 41.5 | 3190 |
| 8/24/1998 | 1998 | 8 | 24 | 85 | 60 | 94 | 77 | 45 | 3235 |
| 8/25/1998 | 1998 | 8 | 25 | 86 | 52 | 87 | 69.5 | 37.5 | 3272.5 |
| 8/26/1998 | 1998 | 8 | 26 | 87 | 54 | 90 | 72 | 40 | 3312.5 |
| 8/27/1998 | 1998 | 8 | 27 | 88 | 58 | 85 | 71.5 | 39.5 | 3352 |
| 8/28/1998 | 1998 | 8 | 28 | 89 | 56 | 87 | 71.5 | 39.5 | 3391.5 |
| 8/29/1998 | 1998 | 8 | 29 | 90 | 55 | 90 | 72.5 | 40.5 | 3432 |
| 8/30/1998 | 1998 | 8 | 30 | 91 | 57 | 95 | 76 | 44 | 3476 |
| 8/31/1998 | 1998 | 8 | 31 | 92 | 57 | 89 | 73 | 41 | 3517 |
| 9/1/1998 | 1998 | 9 | 1 | 93 | 54 | 88 | 71 | 39 | 3556 |
| 9/2/1998 | 1998 | 9 | 2 | 94 | 51 | 86 | 68.5 | 36.5 | 3592.5 |
| 9/3/1998 | 1998 | 9 | 3 | 95 | 59 | 87 | 73 | 41 | 3633.5 |
| 9/4/1998 | 1998 | 9 | 4 | 96 | 51 | 78 | 64.5 | 32.5 | 3666 |
| 9/5/1998 | 1998 | 9 | 5 | 97 | 52 | 86 | 69 | 37 | 3703 |
| 9/6/1998 | 1998 | 9 | 6 | 98 | 44 | 88 | 66 | 34 | 3737 |
| 9/7/1998 | 1998 | 9 | 7 | 99 | 53 | 88 | 70.5 | 38.5 | 3775.5 |
| 9/8/1998 | 1998 | 9 | 8 | 100 | 49 | 87 | 68 | 36 | 3811.5 |
| 9/9/1998 | 1998 | 9 | 9 | 101 | 48 | 84 | 66 | 34 | 3845.5 |
| 9/10/1998 | 1998 | 9 | 10 | 102 | 49 | 86 | 67.5 | 35.5 | 3881 |
| 9/11/1998 | 1998 | 9 | 11 | 103 | 47 | 85 | 66 | 34 | 3915 |
| 9/12/1998 | 1998 | 9 | 12 | 104 | 54 | 84 | 69 | 37 | 3952 |
| 9/13/1998 | 1998 | 9 | 13 | 105 | 46 | 88 | 67 | 35 | 3987 |
| 9/14/1998 | 1998 | 9 | 14 | 106 | 44 | 86 | 65 | 33 | 4020 |
| 9/15/1998 | 1998 | 9 | 15 | 107 | 42 | 88 | 65 | 33 | 4053 |
| 9/16/1998 | 1998 | 9 | 16 | 108 | 45 | 87 | 66 | 34 | 4087 |
| 9/17/1998 | 1998 | 9 | 17 | 109 | 42 | 87 | 64.5 | 32.5 | 4119.5 |
| 9/18/1998 | 1998 | 9 | 18 | 110 | 42 | 88 | 65 | 33 | 4152.5 |
| 9/19/1998 | 1998 | 9 | 19 | 111 | 43 | 88 | 65.5 | 33.5 | 4186 |
| 9/20/1998 | 1998 | 9 | 20 | 112 | 43 | 88 | 65.5 | 33.5 | 4219.5 |
| 9/21/1998 | 1998 | 9 | 21 | 113 | 43 | 83 | 63 | 31 | 4250.5 |
| 9/22/1998 | 1998 | 9 | 22 | 114 | 52 | 87 | 69.5 | 37.5 | 4288 |
| 9/23/1998 | 1998 | 9 | 23 | 115 | 38 | 88 | 63 | 31 | 4319 |
| 9/24/1998 | 1998 | 9 | 24 | 116 | 48 | 90 | 69 | 37 | 4356 |
| 9/25/1998 | 1998 | 9 | 25 | 117 | 35 | 89 | 62 | 30 | 4386 |
| 9/26/1998 | 1998 | 9 | 26 | 118 | 34 | 87 | 60.5 | 28.5 | 4414.5 |
| 9/27/1998 | 1998 | 9 | 27 | 119 | 45 | 90 | 67.5 | 35.5 | 4450 |
| 9/29/1998 | 1998 | 9 | 29 | 120 | 50 | 81 | 65.5 | 33.5 | 4483.5 |
| 9/30/1998 | 1998 | 9 | 30 | 121 | 51 | 79 | 65 | 33 | 4516.5 |
| 10/1/1998 | 1998 | 10 | 1 | 122 | 36 | 78 | 57 | 25 | 4541.5 |
| 10/2/1998 | 1998 | 10 | 2 | 123 | 40 | 80 | 60 | 28 | 4569.5 |
| 10/3/1998 | 1998 | 10 | 3 | 124 | 49 | 84 | 66.5 | 34.5 | 4604 |
| 10/4/1998 | 1998 | 10 | 4 | 125 | 35 | 70 | 52.5 | 20.5 | 4624.5 |
| 10/5/1998 | 1998 | 10 | 5 | 126 | 21 | 71 | 46 | 14 | 4638.5 |
| 10/6/1998 | 1998 | 10 | 6 | 127 | 26 | 70 | 48 | 16 | 4654.5 |
| 10/7/1998 | 1998 | 10 | 7 | 128 | 30 | 80 | 55 | 23 | 4677.5 |
| 10/8/1998 | 1998 | 10 | 8 | 129 | 34 | 84 | 59 | 27 | 4704.5 |
| 10/9/1998 | 1998 | 10 | 9 | 130 | 30 | 84 | 57 | 25 | 4729.5 |
| 10/10/1998 | 1998 | 10 | 10 | 131 | 27 | 80 | 53.5 | 21.5 | 4751 |
| 10/11/1998 | 1998 | 10 | 11 | 132 | 32 | 82 | 57 | 25 | 4776 |
| 10/12/1998 | 1998 | 10 | 12 | 133 | 32 | 85 | 58.5 | 26.5 | 4802.5 |
| 10/13/1998 | 1998 | 10 | 13 | 134 | 40 | 80 | 60 | 28 | 4830.5 |
| 10/14/1998 | 1998 | 10 | 14 | 135 | 32 | 80 | 56 | 24 | 4854.5 |
| 10/15/1998 | 1998 | 10 | 15 | 136 | 32 | 80 | 56 | 24 | 4878.5 |
| 10/16/1998 | 1998 | 10 | 16 | 137 | 21 | 57 | 39 | 7 | 4885.5 |
| 10/17/1998 | 1998 | 10 | 17 | 138 | 19 | 58 | 38.5 | 6.5 | 4892 |
| 10/18/1998 | 1998 | 10 | 18 | 139 | 39 | 67 | 53 | 21 | 4913 |
| 10/19/1998 | 1998 | 10 | 19 | 140 | 46 | 68 | 57 | 25 | 4938 |
| 10/20/1998 | 1998 | 10 | 20 | 141 | 41 | 56 | 48.5 | 16.5 | 4954.5 |
| 10/21/1998 | 1998 | 10 | 21 | 142 | 42 | 57 | 49.5 | 17.5 | 4972 |
| 10/22/1998 | 1998 | 10 | 22 | 143 | 43 | 51 | 47 | 15 | 4987 |
| 10/23/1998 | 1998 | 10 | 23 | 144 | 34 | 65 | 49.5 | 17.5 | 5004.5 |
| 10/24/1998 | 1998 | 10 | 24 | 145 | 42 | 71 | 56.5 | 24.5 | 5029 |
| 10/25/1998 | 1998 | 10 | 25 | 146 | 40 | 69 | 54.5 | 22.5 | 5051.5 |
| 10/26/1998 | 1998 | 10 | 26 | 147 | 44 | 58 | 51 | 19 | 5070.5 |
| 10/27/1998 | 1998 | 10 | 27 | 148 | 31 | 50 | 40.5 | 8.5 | 5079 |
| 10/28/1998 | 1998 | 10 | 28 | 149 | 27 | 62 | 44.5 | 12.5 | 5091.5 |
| 10/29/1998 | 1998 | 10 | 29 | 150 | 31 | 64 | 47.5 | 15.5 | 5107 |
| 10/30/1998 | 1998 | 10 | 30 | 151 | 35 | 63 | 49 | 17 | 5124 |
| 10/31/1998 | 1998 | 10 | 31 | 152 | 39 | 53 | 46 | 14 | 5138 |
| 11/1/1998 | 1998 | 11 | 1 | 153 | 33 | 53 | 43 | 11 | 5149 |
| 11/2/1998 | 1998 | 11 | 2 | 154 | 28 | 56 | 42 | 10 | 5159 |
| 11/3/1998 | 1998 | 11 | 3 | 155 | 26 | 58 | 42 | 10 | 5169 |
| 11/4/1998 | 1998 | 11 | 4 | 156 | 29 | 62 | 45.5 | 13.5 | 5182.5 |
| 11/5/1998 | 1998 | 11 | 5 | 157 | 23 | 59 | 41 | 9 | 5191.5 |
| 11/6/1998 | 1998 | 11 | 6 | 158 | 29 | 48 | 38.5 | 6.5 | 5198 |
| 11/7/1998 | 1998 | 11 | 7 | 159 | 29 | 59 | 44 | 12 | 5210 |
| 11/8/1998 | 1998 | 11 | 8 | 160 | 30 | 61 | 45.5 | 13.5 | 5223.5 |
| 11/9/1998 | 1998 | 11 | 9 | 161 | 15 | 35 | 25 | -7 | 5216.5 |
| 11/10/1998 | 1998 | 11 | 10 | 162 | 17 | 43 | 30 | -2 | 5214.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/11/1998 | 1998 | 11 | 11 | 163 | 31 | 45 | 38 | 6 | 5220.5 |
| 11/12/1998 | 1998 | 11 | 12 | 164 | 33 | 59 | 46 | 14 | 5234.5 |
| 11/13/1998 | 1998 | 11 | 13 | 165 | 25 | 62 | 43.5 | 11.5 | 5246 |
| 11/14/1998 | 1998 | 11 | 14 | 166 | 25 | 60 | 42.5 | 10.5 | 5256.5 |
| 11/15/1998 | 1998 | 11 | 15 | 167 | 26 | 72 | 49 | 17 | 5273.5 |
| 11/16/1998 | 1998 | 11 | 16 | 168 | 21 | 70 | 45.5 | 13.5 | 5287 |
| 11/17/1998 | 1998 | 11 | 17 | 169 | 27 | 69 | 48 | 16 | 5303 |
| 11/18/1998 | 1998 | 11 | 18 | 170 | 21 | 64 | 42.5 | 10.5 | 5313.5 |
| 11/19/1998 | 1998 | 11 | 19 | 171 | 22 | 54 | 38 | 6 | 5319.5 |
| 11/20/1998 | 1998 | 11 | 20 | 172 | 13 | 55 | 34 | 2 | 5321.5 |
| 11/21/1998 | 1998 | 11 | 21 | 173 | 18 | 66 | 42 | 10 | 5331.5 |
| 11/22/1998 | 1998 | 11 | 22 | 174 | 18 | 72 | 45 | 13 | 5344.5 |
| 11/23/1998 | 1998 | 11 | 23 | 175 | 38 | 69 | 53.5 | 21.5 | 5366 |
| 11/24/1998 | 1998 | 11 | 24 | 176 | 21 | 69 | 45 | 13 | 5379 |
| 11/25/1998 | 1998 | 11 | 25 | 177 | 21 | 68 | 44.5 | 12.5 | 5391.5 |
| 11/26/1998 | 1998 | 11 | 26 | 178 | 21 | 69 | 45 | 13 | 5404.5 |
| 11/27/1998 | 1998 | 11 | 27 | 179 | 18 | 68 | 43 | 11 | 5415.5 |
| 11/28/1998 | 1998 | 11 | 28 | 180 | 21 | 69 | 45 | 13 | 5428.5 |
| 11/29/1998 | 1998 | 11 | 29 | 181 | 29 | 61 | 45 | 13 | 5441.5 |
| 11/30/1998 | 1998 | 11 | 30 | 182 | 30 | 60 | 45 | 13 | 5454.5 |
| 12/1/1998 | 1998 | 12 | 1 | 183 | 33 | 62 | 47.5 | 15.5 | 5470 |
| 12/2/1998 | 1998 | 12 | 2 | 184 | 31 | 59 | 45 | 13 | 5483 |
| 12/3/1998 | 1998 | 12 | 3 | 185 | 22 | 65 | 43.5 | 11.5 | 5494.5 |
| 12/4/1998 | 1998 | 12 | 4 | 186 | 20 | 64 | 42 | 10 | 5504.5 |
| 12/5/1998 | 1998 | 12 | 5 | 187 | 22 | 61 | 41.5 | 9.5 | 5514 |
| 12/6/1998 | 1998 | 12 | 6 | 188 | 17 | 32 | 24.5 | -7.5 | 5506.5 |
| 12/7/1998 | 1998 | 12 | 7 | 189 | 2 | 32 | 17 | -15 | 5491.5 |
| 12/8/1998 | 1998 | 12 | 8 | 190 | 17 | 41 | 29 | -3 | 5488.5 |
| 12/9/1998 | 1998 | 12 | 9 | 191 | 18 | 36 | 27 | -5 | 5483.5 |
| 12/10/1998 | 1998 | 12 | 10 | 192 | 14 | 35 | 24.5 | -7.5 | 5476 |
| 12/11/1998 | 1998 | 12 | 11 | 193 | 12 | 42 | 27 | -5 | 5471 |
| 12/12/1998 | 1998 | 12 | 12 | 194 | 15 | 48 | 31.5 | -0.5 | 5470.5 |
| 12/13/1998 | 1998 | 12 | 13 | 195 | 11 | 56 | 33.5 | 1.5 | 5472 |
| 12/14/1998 | 1998 | 12 | 14 | 196 | 14 | 53 | 33.5 | 1.5 | 5473.5 |
| 12/15/1998 | 1998 | 12 | 15 | 197 | 13 | 58 | 35.5 | 3.5 | 5477 |
| 12/16/1998 | 1998 | 12 | 16 | 198 | 14 | 61 | 37.5 | 5.5 | 5482.5 |
| 12/17/1998 | 1998 | 12 | 17 | 199 | 13 | 61 | 37 | 5 | 5487.5 |
| 12/18/1998 | 1998 | 12 | 18 | 200 | 29 | 60 | 44.5 | 12.5 | 5500 |
| 12/19/1998 | 1998 | 12 | 19 | 201 | 36 | 57 | 46.5 | 14.5 | 5514.5 |
| 12/20/1998 | 1998 | 12 | 20 | 202 | 11 | 56 | 33.5 | 1.5 | 5516 |
| 12/21/1998 | 1998 | 12 | 21 | 203 | 10 | 35 | 22.5 | -9.5 | 5506.5 |
| 12/22/1998 | 1998 | 12 | 22 | 204 | 8 | 40 | 24 | -8 | 5498.5 |
| 12/23/1998 | 1998 | 12 | 23 | 205 | 6 | 47 | 26.5 | -5.5 | 5493 |
| 12/24/1998 | 1998 | 12 | 24 | 206 | 10 | 45 | 27.5 | -4.5 | 5488.5 |
| 12/25/1998 | 1998 | 12 | 25 | 207 | 11 | 49 | 30 | -2 | 5486.5 |
| 12/26/1998 | 1998 | 12 | 26 | 208 | 12 | 55 | 33.5 | 1.5 | 5488 |
| 12/27/1998 | 1998 | 12 | 27 | 209 | 17 | 56 | 36.5 | 4.5 | 5492.5 |
| 12/28/1998 | 1998 | 12 | 28 | 210 | 17 | 65 | 41 | 9 | 5501.5 |
| 12/29/1998 | 1998 | 12 | 29 | 211 | 17 | 64 | 40.5 | 8.5 | 5510 |
| 12/30/1998 | 1998 | 12 | 30 | 212 | 17 | 64 | 40.5 | 8.5 | 5518.5 |
| 12/31/1998 | 1998 | 12 | 31 | 213 | 17 | 64 | 40.5 | 8.5 | 5527 |
| 1/1/1999 | 1999 | 1 | 1 | 214 | 11 | 59 | 35 | 3 | 5530 |
| 1/2/1999 | 1999 | 1 | 2 | 215 | 14 | 53 | 33.5 | 1.5 | 5531.5 |
| 1/3/1999 | 1999 | 1 | 3 | 216 | 8 | 46 | 27 | -5 | 5526.5 |
| 1/4/1999 | 1999 | 1 | 4 | 217 | 8 | 46 | 27 | -5 | 5521.5 |
| 1/5/1999 | 1999 | 1 | 5 | 218 | 12 | 62 | 37 | 5 | 5526.5 |
| 1/6/1999 | 1999 | 1 | 6 | 219 | 14 | 56 | 35 | 3 | 5529.5 |
| 1/7/1999 | 1999 | 1 | 7 | 220 | 17 | 60 | 38.5 | 6.5 | 5536 |
| 1/8/1999 | 1999 | 1 | 8 | 221 | 10 | 54 | 32 | 0 | 5536 |
| 1/9/1999 | 1999 | 1 | 9 | 222 | 16 | 55 | 35.5 | 3.5 | 5539.5 |
| 1/10/1999 | 1999 | 1 | 10 | 223 | 14 | 62 | 38 | 6 | 5545.5 |
| 1/11/1999 | 1999 | 1 | 11 | 224 | 25 | 67 | 46 | 14 | 5559.5 |
| 1/12/1999 | 1999 | 1 | 12 | 225 | 13 | 57 | 35 | 3 | 5562.5 |
| 1/13/1999 | 1999 | 1 | 13 | 226 | 11 | 54 | 32.5 | 0.5 | 5563 |
| 1/14/1999 | 1999 | 1 | 14 | 227 | 8 | 55 | 31.5 | -0.5 | 5562.5 |
| 1/15/1999 | 1999 | 1 | 15 | 228 | 16 | 67 | 41.5 | 9.5 | 5572 |
| 1/16/1999 | 1999 | 1 | 16 | 229 | 27 | 64 | 45.5 | 13.5 | 5585.5 |
| 1/17/1999 | 1999 | 1 | 17 | 230 | 21 | 63 | 42 | 10 | 5595.5 |
| 1/18/1999 | 1999 | 1 | 18 | 231 | 27 | 64 | 45.5 | 13.5 | 5609 |
| 1/19/1999 | 1999 | 1 | 19 | 232 | 29 | 63 | 46 | 14 | 5623 |
| 1/20/1999 | 1999 | 1 | 20 | 233 | 34 | 59 | 46.5 | 14.5 | 5637.5 |
| 1/21/1999 | 1999 | 1 | 21 | 234 | 22 | 45 | 33.5 | 1.5 | 5639 |
| 1/22/1999 | 1999 | 1 | 22 | 235 | 14 | 45 | 29.5 | -2.5 | 5636.5 |
| 1/23/1999 | 1999 | 1 | 23 | 236 | 30 | 65 | 47.5 | 15.5 | 5652 |
| 1/24/1999 | 1999 | 1 | 24 | 237 | 29 | 65 | 47 | 15 | 5667 |
| 1/25/1999 | 1999 | 1 | 25 | 238 | 30 | 66 | 48 | 16 | 5683 |
| 1/26/1999 | 1999 | 1 | 26 | 239 | 11 | 52 | 31.5 | -0.5 | 5682.5 |
| 1/27/1999 | 1999 | 1 | 27 | 240 | 16 | 49 | 32.5 | 0.5 | 5683 |
| 1/28/1999 | 1999 | 1 | 28 | 241 | 13 | 43 | 28 | -4 | 5679 |
| 1/29/1999 | 1999 | 1 | 29 | 242 | 12 | 53 | 32.5 | 0.5 | 5679.5 |
| 1/30/1999 | 1999 | 1 | 30 | 243 | 11 | 57 | 34 | 2 | 5681.5 |
| 1/31/1999 | 1999 | 1 | 31 | 244 | 21 | 63 | 42 | 10 | 5691.5 |
| 2/1/1999 | 1999 | 2 | 1 | 245 | 8 | 53 | 30.5 | -1.5 | 5690 |
| 2/2/1999 | 1999 | 2 | 2 | 246 | 15 | 53 | 34 | 2 | 5692 |
| 2/3/1999 | 1999 | 2 | 3 | 247 | 15 | 60 | 37.5 | 5.5 | 5697.5 |
| 2/4/1999 | 1999 | 2 | 4 | 248 | 33 | 64 | 48.5 | 16.5 | 5714 |
| 2/5/1999 | 1999 | 2 | 5 | 249 | 28 | 57 | 42.5 | 10.5 | 5724.5 |
| 2/6/1999 | 1999 | 2 | 6 | 250 | 17 | 46 | 31.5 | -0.5 | 5724 |
| 2/7/1999 | 1999 | 2 | 7 | 251 | 17 | 65 | 41 | 9 | 5733 |
| 2/8/1999 | 1999 | 2 | 8 | 252 | 16 | 63 | 39.5 | 7.5 | 5740.5 |
| 2/9/1999 | 1999 | 2 | 9 | 253 | 30 | 66 | 48 | 16 | 5756.5 |
| 2/10/1999 | 1999 | 2 | 10 | 254 | 11 | 65 | 38 | 6 | 5762.5 |
| 2/11/1999 | 1999 | 2 | 11 | 255 | 7 | 33 | 20 | -12 | 5750.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/12/1999 | 1999 | 2 | 12 | 256 | 9 | 61 | 35 | 3 | 5753.5 |
| 2/13/1999 | 1999 | 2 | 13 | 257 | 14 | 62 | 38 | 6 | 5759.5 |
| 2/14/1999 | 1999 | 2 | 14 | 258 | 21 | 65 | 43 | 11 | 5770.5 |
| 2/15/1999 | 1999 | 2 | 15 | 259 | 9 | 55 | 32 | 0 | 5770.5 |
| 2/16/1999 | 1999 | 2 | 16 | 260 | 12 | 53 | 32.5 | 0.5 | 5771 |
| 2/17/1999 | 1999 | 2 | 17 | 261 | 18 | 61 | 39.5 | 7.5 | 5778.5 |
| 2/18/1999 | 1999 | 2 | 18 | 262 | 18 | 66 | 42 | 10 | 5788.5 |
| 2/19/1999 | 1999 | 2 | 19 | 263 | 20 | 64 | 42 | 10 | 5798.5 |
| 2/20/1999 | 1999 | 2 | 20 | 264 | 21 | 56 | 38.5 | 6.5 | 5805 |
| 2/21/1999 | 1999 | 2 | 21 | 265 | 21 | 56 | 38.5 | 6.5 | 5811.5 |
| 2/22/1999 | 1999 | 2 | 22 | 266 | 12 | 61 | 36.5 | 4.5 | 5816 |
| 2/23/1999 | 1999 | 2 | 23 | 267 | 15 | 63 | 39 | 7 | 5823 |
| 2/24/1999 | 1999 | 2 | 24 | 268 | 19 | 67 | 43 | 11 | 5834 |
| 2/25/1999 | 1999 | 2 | 25 | 269 | 17 | 67 | 42 | 10 | 5844 |
| 2/26/1999 | 1999 | 2 | 26 | 270 | 15 | 62 | 38.5 | 6.5 | 5850.5 |
| 2/27/1999 | 1999 | 2 | 27 | 271 | 17 | 67 | 42 | 10 | 5860.5 |
| 2/28/1999 | 1999 | 2 | 28 | 272 | 19 | 68 | 43.5 | 11.5 | 5872 |
| 3/1/1999 | 1999 | 3 | 1 | 273 | 21 | 71 | 46 | 14 | 5886 |
| 3/2/1999 | 1999 | 3 | 2 | 274 | 16 | 69 | 42.5 | 10.5 | 5896.5 |
| 3/3/1999 | 1999 | 3 | 3 | 275 | 34 | 70 | 52 | 20 | 5916.5 |
| 3/4/1999 | 1999 | 3 | 4 | 276 | 30 | 67 | 48.5 | 16.5 | 5933 |
| 3/5/1999 | 1999 | 3 | 5 | 277 | 30 | 66 | 48 | 16 | 5949 |
| 3/6/1999 | 1999 | 3 | 6 | 278 | 32 | 63 | 47.5 | 15.5 | 5964.5 |
| 3/7/1999 | 1999 | 3 | 7 | 279 | 29 | 63 | 46 | 14 | 5978.5 |
| 3/8/1999 | 1999 | 3 | 8 | 280 | 17 | 58 | 37.5 | 5.5 | 5984 |
| 3/9/1999 | 1999 | 3 | 9 | 281 | 5 | 53 | 29 | -3 | 5981 |
| 3/10/1999 | 1999 | 3 | 10 | 282 | 17 | 66 | 41.5 | 9.5 | 5990.5 |
| 3/11/1999 | 1999 | 3 | 11 | 283 | 20 | 65 | 42.5 | 10.5 | 6001 |
| 3/12/1999 | 1999 | 3 | 12 | 284 | 20 | 65 | 42.5 | 10.5 | 6011.5 |
| 3/13/1999 | 1999 | 3 | 13 | 285 | 14 | 61 | 37.5 | 5.5 | 6017 |
| 3/14/1999 | 1999 | 3 | 14 | 286 | 22 | 72 | 47 | 15 | 6032 |
| 3/15/1999 | 1999 | 3 | 15 | 287 | 20 | 70 | 45 | 13 | 6045 |
| 3/16/1999 | 1999 | 3 | 16 | 288 | 32 | 71 | 51.5 | 19.5 | 6064.5 |
| 3/17/1999 | 1999 | 3 | 17 | 289 | 30 | 53 | 41.5 | 9.5 | 6074 |
| 3/18/1999 | 1999 | 3 | 18 | 290 | 27 | 40 | 33.5 | 1.5 | 6075.5 |
| 3/19/1999 | 1999 | 3 | 19 | 291 | 28 | 67 | 47.5 | 15.5 | 6091 |
| 3/20/1999 | 1999 | 3 | 20 | 292 | 36 | 67 | 51.5 | 19.5 | 6110.5 |
| 3/21/1999 | 1999 | 3 | 21 | 293 | 32 | 77 | 54.5 | 22.5 | 6133 |
| 3/22/1999 | 1999 | 3 | 22 | 294 | 22 | 73 | 47.5 | 15.5 | 6148.5 |
| 3/23/1999 | 1999 | 3 | 23 | 295 | 23 | 76 | 49.5 | 17.5 | 6166 |
| 3/24/1999 | 1999 | 3 | 24 | 296 | 38 | 70 | 54 | 22 | 6188 |
| 3/25/1999 | 1999 | 3 | 25 | 297 | 32 | 66 | 49 | 17 | 6205 |
| 3/26/1999 | 1999 | 3 | 26 | 298 | 34 | 56 | 45 | 13 | 6218 |
| 3/27/1999 | 1999 | 3 | 27 | 299 | 28 | 71 | 49.5 | 17.5 | 6235.5 |
| 3/28/1999 | 1999 | 3 | 28 | 300 | 26 | 70 | 48 | 16 | 6251.5 |
| 3/29/1999 | 1999 | 3 | 29 | 301 | 38 | 72 | 55 | 23 | 6274.5 |
| 3/30/1999 | 1999 | 3 | 30 | 302 | 42 | 74 | 58 | 26 | 6300.5 |
| 3/31/1999 | 1999 | 3 | 31 | 303 | 35 | 72 | 53.5 | 21.5 | 6322 |
| 4/1/1999 | 1999 | 4 | 1 | 304 | 29 | 55 | 42 | 10 | 6332 |
| 4/2/1999 | 1999 | 4 | 2 | 305 | 23 | 47 | 35 | 3 | 6335 |
| 4/3/1999 | 1999 | 4 | 3 | 306 | 29 | 46 | 37.5 | 5.5 | 6340.5 |
| 4/4/1999 | 1999 | 4 | 4 | 307 | 24 | 51 | 37.5 | 5.5 | 6346 |
| 4/5/1999 | 1999 | 4 | 5 | 308 | 19 | 58 | 38.5 | 6.5 | 6352.5 |
| 4/6/1999 | 1999 | 4 | 6 | 309 | 30 | 70 | 50 | 18 | 6370.5 |
| 4/7/1999 | 1999 | 4 | 7 | 310 | 27 | 73 | 50 | 18 | 6388.5 |
| 4/8/1999 | 1999 | 4 | 8 | 311 | 28 | 63 | 45.5 | 13.5 | 6402 |
| 4/9/1999 | 1999 | 4 | 9 | 312 | 19 | 60 | 39.5 | 7.5 | 6409.5 |
| 4/10/1999 | 1999 | 4 | 10 | 313 | 16 | 63 | 39.5 | 7.5 | 6417 |
| 4/11/1999 | 1999 | 4 | 11 | 314 | 18 | 73 | 45.5 | 13.5 | 6430.5 |
| 4/12/1999 | 1999 | 4 | 12 | 315 | 35 | 76 | 55.5 | 23.5 | 6454 |
| 4/13/1999 | 1999 | 4 | 13 | 316 | 37 | 54 | 45.5 | 13.5 | 6467.5 |
| 4/14/1999 | 1999 | 4 | 14 | 317 | 22 | 66 | 44 | 12 | 6479.5 |
| 4/15/1999 | 1999 | 4 | 15 | 318 | 16 | 60 | 38 | 6 | 6485.5 |
| 4/16/1999 | 1999 | 4 | 16 | 319 | 23 | 59 | 41 | 9 | 6494.5 |
| 4/17/1999 | 1999 | 4 | 17 | 320 | 25 | 68 | 46.5 | 14.5 | 6509 |
| 4/18/1999 | 1999 | 4 | 18 | 321 | 25 | 75 | 50 | 18 | 6527 |
| 4/19/1999 | 1999 | 4 | 19 | 322 | 30 | 80 | 55 | 23 | 6550 |
| 4/20/1999 | 1999 | 4 | 20 | 323 | 43 | 80 | 61.5 | 29.5 | 6579.5 |
| 4/21/1999 | 1999 | 4 | 21 | 324 | 43 | 80 | 61.5 | 29.5 | 6609 |
| 4/22/1999 | 1999 | 4 | 22 | 325 | 31 | 78 | 54.5 | 22.5 | 6631.5 |
| 4/23/1999 | 1999 | 4 | 23 | 326 | 40 | 79 | 59.5 | 27.5 | 6659 |
| 4/24/1999 | 1999 | 4 | 24 | 327 | 29 | 60 | 44.5 | 12.5 | 6671.5 |
| 4/25/1999 | 1999 | 4 | 25 | 328 | 36 |  | 36 | 4 | 6675.5 |
| 4/26/1999 | 1999 | 4 | 26 | 329 | 32 | 72 | 52 | 20 | 6695.5 |
| 4/27/1999 | 1999 | 4 | 27 | 330 | 39 | 77 | 58 | 26 | 6721.5 |
| 4/28/1999 | 1999 | 4 | 28 | 331 | 42 | 74 | 58 | 26 | 6747.5 |
| 4/29/1999 | 1999 | 4 | 29 | 332 | 34 | 75 | 54.5 | 22.5 | 6770 |
| 4/30/1999 | 1999 | 4 | 30 | 333 | 35 | 69 | 52 | 20 | 6790 |
| 5/1/1999 | 1999 | 5 | 1 | 334 | 33 | 54 | 43.5 | 11.5 | 6801.5 |
| 5/2/1999 | 1999 | 5 | 2 | 335 | 32 | 70 | 51 | 19 | 6820.5 |
| 5/3/1999 | 1999 | 5 | 3 | 336 | 37 | 68 | 52.5 | 20.5 | 6841 |
| 5/4/1999 | 1999 | 5 | 4 | 337 | 33 | 57 | 45 | 13 | 6854 |
| 5/5/1999 | 1999 | 5 | 5 | 338 | 33 | 60 | 46.5 | 14.5 | 6868.5 |
| 5/6/1999 | 1999 | 5 | 6 | 339 | 33 | 60 | 46.5 | 14.5 | 6883 |
| 5/7/1999 | 1999 | 5 | 7 | 340 | 31 | 79 | 55 | 23 | 6906 |
| 5/8/1999 | 1999 | 5 | 8 | 341 | 40 | 83 | 61.5 | 29.5 | 6935.5 |
| 5/9/1999 | 1999 | 5 | 9 | 342 | 53 | 80 | 66.5 | 34.5 | 6970 |
| 5/10/1999 | 1999 | 5 | 10 | 343 | 36 | 73 | 54.5 | 22.5 | 6992.5 |
| 5/11/1999 | 1999 | 5 | 11 | 344 | 30 | 73 | 51.5 | 19.5 | 7012 |
| 5/12/1999 | 1999 | 5 | 12 | 345 | 44 | 81 | 62.5 | 30.5 | 7042.5 |
| 5/13/1999 | 1999 | 5 | 13 | 346 | 45 | 83 | 64 | 32 | 7074.5 |
| 5/14/1999 | 1999 | 5 | 14 | 347 | 42 | 80 | 61 | 29 | 7103.5 |
| 5/15/1999 | 1999 | 5 | 15 | 348 | 38 | 82 | 60 | 28 | 7131.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/16/1999 | 1999 | 5 | 16 | 349 | 32 | 76 | 54 | 22 | 7153.5 |
| 5/17/1999 | 1999 | 5 | 17 | 350 | 33 | 82 | 57.5 | 25.5 | 7179 |
| 5/18/1999 | 1999 | 5 | 18 | 351 | 42 | 83 | 62.5 | 30.5 | 7209.5 |
| 5/19/1999 | 1999 | 5 | 19 | 352 | 40 | 87 | 63.5 | 31.5 | 7241 |
| 5/20/1999 | 1999 | 5 | 20 | 353 | 33 | 86 | 59.5 | 27.5 | 7268.5 |
| 5/21/1999 | 1999 | 5 | 21 | 354 | 34 | 87 | 60.5 | 28.5 | 7297 |
| 5/22/1999 | 1999 | 5 | 22 | 355 | 43 | 83 | 63 | 31 | 7328 |
| 5/23/1999 | 1999 | 5 | 23 | 356 | 50 | 76 | 63 | 31 | 7359 |
| 5/24/1999 | 1999 | 5 | 24 | 357 | 37 | 74 | 55.5 | 23.5 | 7382.5 |
| 5/25/1999 | 1999 | 5 | 25 | 358 | 38 | 76 | 57 | 25 | 7407.5 |
| 5/26/1999 | 1999 | 5 | 26 | 359 | 35 | 79 | 57 | 25 | 7432.5 |
| 5/27/1999 | 1999 | 5 | 27 | 360 | 42 | 75 | 58.5 | 26.5 | 7459 |
| 5/28/1999 | 1999 | 5 | 28 | 361 | 42 | 77 | 59.5 | 27.5 | 7486.5 |
| 5/29/1999 | 1999 | 5 | 29 | 362 | 37 | 83 | 60 | 28 | 7514.5 |
| 5/30/1999 | 1999 | 5 | 30 | 363 | 52 | 82 | 67 | 35 | 7549.5 |
| 5/31/1999 | 1999 | 5 | 31 | 364 | 42 | 82 | 62 | 30 | 7579.5 |
| 6/1/1999 | 1999 | 6 | 1 | 1 | 42 | 83 | 62.5 | 30.5 | 30.5 |
| 6/2/1999 | 1999 | 6 | 2 | 2 | 40 | 85 | 62.5 | 30.5 | 61 |
| 6/3/1999 | 1999 | 6 | 3 | 3 | 41 | 87 | 64 | 32 | 93 |
| 6/4/1999 | 1999 | 6 | 4 | 4 | 32 | 81 | 56.5 | 24.5 | 117.5 |
| 6/5/1999 | 1999 | 6 | 5 | 5 | 36 | 71 | 53.5 | 21.5 | 139 |
| 6/6/1999 | 1999 | 6 | 6 | 6 | 35 | 83 | 59 | 27 | 166 |
| 6/7/1999 | 1999 | 6 | 7 | 7 | 39 | 91 | 65 | 33 | 199 |
| 6/8/1999 | 1999 | 6 | 8 | 8 | 40 | 91 | 65.5 | 33.5 | 232.5 |
| 6/9/1999 | 1999 | 6 | 9 | 9 | 42 | 86 | 64 | 32 | 264.5 |
| 6/10/1999 | 1999 | 6 | 10 | 10 | 40 | 87 | 63.5 | 31.5 | 296 |
| 6/11/1999 | 1999 | 6 | 11 | 11 | 45 | 88 | 66.5 | 34.5 | 330.5 |
| 6/12/1999 | 1999 | 6 | 12 | 12 | 41 | 84 | 62.5 | 30.5 | 361 |
| 6/13/1999 | 1999 | 6 | 13 | 13 | 50 | 85 | 67.5 | 35.5 | 396.5 |
| 6/14/1999 | 1999 | 6 | 14 | 14 | 46 | 84 | 65 | 33 | 429.5 |
| 6/15/1999 | 1999 | 6 | 15 | 15 | 54 | 87 | 70.5 | 38.5 | 468 |
| 6/16/1999 | 1999 | 6 | 16 | 16 | 52 | 86 | 69 | 37 | 505 |
| 6/17/1999 | 1999 | 6 | 17 | 17 | 47 | 78 | 62.5 | 30.5 | 535.5 |
| 6/18/1999 | 1999 | 6 | 18 | 18 | 50 | 84 | 67 | 35 | 570.5 |
| 6/19/1999 | 1999 | 6 | 19 | 19 | 52 | 88 | 70 | 38 | 608.5 |
| 6/20/1999 | 1999 | 6 | 20 | 20 | 57 | 85 | 71 | 39 | 647.5 |
| 6/21/1999 | 1999 | 6 | 21 | 21 | 59 | 85 | 72 | 40 | 687.5 |
| 6/22/1999 | 1999 | 6 | 22 | 22 | 52 | 89 | 70.5 | 38.5 | 726 |
| 6/23/1999 | 1999 | 6 | 23 | 23 | 47 | 91 | 69 | 37 | 763 |
| 6/24/1999 | 1999 | 6 | 24 | 24 | 60 | 95 | 77.5 | 45.5 | 808.5 |
| 6/25/1999 | 1999 | 6 | 25 | 25 | 57 | 93 | 75 | 43 | 851.5 |
| 6/26/1999 | 1999 | 6 | 26 | 26 | 58 | 94 | 76 | 44 | 895.5 |
| 6/27/1999 | 1999 | 6 | 27 | 27 | 59 | 94 | 76.5 | 44.5 | 940 |
| 6/28/1999 | 1999 | 6 | 28 | 28 | 57 | 97 | 77 | 45 | 985 |
| 6/29/1999 | 1999 | 6 | 29 | 29 | 49 | 97 | 73 | 41 | 1026 |
| 6/30/1999 | 1999 | 6 | 30 | 30 | 60 | 100 | 80 | 48 | 1074 |
| 7/1/1999 | 1999 | 7 | 1 | 31 | 72 | 101 | 86.5 | 54.5 | 1128.5 |
| 7/2/1999 | 1999 | 7 | 2 | 32 | 56 | 93 | 74.5 | 42.5 | 1171 |
| 7/3/1999 | 1999 | 7 | 3 | 33 | 59 | 88 | 73.5 | 41.5 | 1212.5 |
| 7/4/1999 | 1999 | 7 | 4 | 34 | 59 | 86 | 72.5 | 40.5 | 1253 |
| 7/5/1999 | 1999 | 7 | 5 | 35 | 55 | 90 | 72.5 | 40.5 | 1293.5 |
| 7/6/1999 | 1999 | 7 | 6 | 36 | 56 | 88 | 72 | 40 | 1333.5 |
| 7/7/1999 | 1999 | 7 | 7 | 37 | 59 | 89 | 74 | 42 | 1375.5 |
| 7/8/1999 | 1999 | 7 | 8 | 38 | 57 | 90 | 73.5 | 41.5 | 1417 |
| 7/9/1999 | 1999 | 7 | 9 | 39 | 58 | 84 | 71 | 39 | 1456 |
| 7/10/1999 | 1999 | 7 | 10 | 40 | 51 | 79 | 65 | 33 | 1489 |
| 7/11/1999 | 1999 | 7 | 11 | 41 | 55 | 85 | 70 | 38 | 1527 |
| 7/12/1999 | 1999 | 7 | 12 | 42 | 55 | 88 | 71.5 | 39.5 | 1566.5 |
| 7/13/1999 | 1999 | 7 | 13 | 43 | 61 | 93 | 77 | 45 | 1611.5 |
| 7/14/1999 | 1999 | 7 | 14 | 44 | 54 | 73 | 63.5 | 31.5 | 1643 |
| 7/15/1999 | 1999 | 7 | 15 | 45 | 50 | 85 | 67.5 | 35.5 | 1678.5 |
| 7/16/1999 | 1999 | 7 | 16 | 46 | 60 | 86 | 73 | 41 | 1719.5 |
| 7/17/1999 | 1999 | 7 | 17 | 47 | 56 | 81 | 68.5 | 36.5 | 1756 |
| 7/18/1999 | 1999 | 7 | 18 | 48 | 56 | 78 | 67 | 35 | 1791 |
| 7/19/1999 | 1999 | 7 | 19 | 49 | 56 | 78 | 67 | 35 | 1826 |
| 7/20/1999 | 1999 | 7 | 20 | 50 | 57 | 88 | 72.5 | 40.5 | 1866.5 |
| 7/21/1999 | 1999 | 7 | 21 | 51 | 52 | 80 | 66 | 34 | 1900.5 |
| 7/22/1999 | 1999 | 7 | 22 | 52 | 53 | 87 | 70 | 38 | 1938.5 |
| 7/23/1999 | 1999 | 7 | 23 | 53 | 52 | 87 | 69.5 | 37.5 | 1976 |
| 7/24/1999 | 1999 | 7 | 24 | 54 | 69 | 89 | 79 | 47 | 2023 |
| 7/25/1999 | 1999 | 7 | 25 | 55 | 52 | 96 | 74 | 42 | 2065 |
| 7/26/1999 | 1999 | 7 | 26 | 56 | 56 | 93 | 74.5 | 42.5 | 2107.5 |
| 7/27/1999 | 1999 | 7 | 27 | 57 | 55 | 90 | 72.5 | 40.5 | 2148 |
| 7/28/1999 | 1999 | 7 | 28 | 58 | 54 | 89 | 71.5 | 39.5 | 2187.5 |
| 7/29/1999 | 1999 | 7 | 29 | 59 | 51 | 91 | 71 | 39 | 2226.5 |
| 7/30/1999 | 1999 | 7 | 30 | 60 | 54 | 87 | 70.5 | 38.5 | 2265 |
| 7/31/1999 | 1999 | 7 | 31 | 61 | 57 | 87 | 72 | 40 | 2305 |
| 8/1/1999 | 1999 | 8 | 1 | 62 | 57 | 80 | 68.5 | 36.5 | 2341.5 |
| 8/2/1999 | 1999 | 8 | 2 | 63 | 56 | 76 | 66 | 34 | 2375.5 |
| 8/3/1999 | 1999 | 8 | 3 | 64 | 54 | 74 | 64 | 32 | 2407.5 |
| 8/4/1999 | 1999 | 8 | 4 | 65 | 56 | 73 | 64.5 | 32.5 | 2440 |
| 8/5/1999 | 1999 | 8 | 5 | 66 | 56 | 75 | 65.5 | 33.5 | 2473.5 |
| 8/6/1999 | 1999 | 8 | 6 | 67 | 49 | 83 | 66 | 34 | 2507.5 |
| 8/7/1999 | 1999 | 8 | 7 | 68 | 50 | 88 | 69 | 37 | 2544.5 |
| 8/8/1999 | 1999 | 8 | 8 | 69 | 58 | 85 | 71.5 | 39.5 | 2584 |
| 8/9/1999 | 1999 | 8 | 9 | 70 | 55 | 83 | 69 | 37 | 2621 |
| 8/10/1999 | 1999 | 8 | 10 | 71 | 53 | 75 | 64 | 32 | 2653 |
| 8/11/1999 | 1999 | 8 | 11 | 72 | 43 | 84 | 63.5 | 31.5 | 2684.5 |
| 8/12/1999 | 1999 | 8 | 12 | 73 | 43 | 87 | 65 | 33 | 2717.5 |
| 8/13/1999 | 1999 | 8 | 13 | 74 | 56 | 90 | 73 | 41 | 2758.5 |
| 8/14/1999 | 1999 | 8 | 14 | 75 | 56 | 80 | 68 | 36 | 2794.5 |
| 8/15/1999 | 1999 | 8 | 15 | 76 | 53 | 78 | 65.5 | 33.5 | 2828 |
| 8/16/1999 | 1999 | 8 | 16 | 77 | 53 | 88 | 70.5 | 38.5 | 2866.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/17/1999 | 1999 | 8 | 17 | 78 | 52 | 90 | 71 | 39 | 2905.5 |
| 8/18/1999 | 1999 | 8 | 18 | 79 | 52 | 90 | 71 | 39 | 2944.5 |
| 8/19/1999 | 1999 | 8 | 19 | 80 | 56 | 88 | 72 | 40 | 2984.5 |
| 8/20/1999 | 1999 | 8 | 20 | 81 | 50 | 82 | 66 | 34 | 3018.5 |
| 8/21/1999 | 1999 | 8 | 21 | 82 | 51 | 87 | 69 | 37 | 3055.5 |
| 8/22/1999 | 1999 | 8 | 22 | 83 | 51 | 87 | 69 | 37 | 3092.5 |
| 8/23/1999 | 1999 | 8 | 23 | 84 | 52 | 89 | 70.5 | 38.5 | 3131 |
| 8/24/1999 | 1999 | 8 | 24 | 85 | 53 | 90 | 71.5 | 39.5 | 3170.5 |
| 8/25/1999 | 1999 | 8 | 25 | 86 | 52 | 90 | 71 | 39 | 3209.5 |
| 8/26/1999 | 1999 | 8 | 26 | 87 | 54 | 89 | 71.5 | 39.5 | 3249 |
| 8/27/1999 | 1999 | 8 | 27 | 88 | 57 | 89 | 73 | 41 | 3290 |
| 8/28/1999 | 1999 | 8 | 28 | 89 | 57 | 86 | 71.5 | 39.5 | 3329.5 |
| 8/29/1999 | 1999 | 8 | 29 | 90 | 55 | 88 | 71.5 | 39.5 | 3369 |
| 8/30/1999 | 1999 | 8 | 30 | 91 | 50 | 90 | 70 | 38 | 3407 |
| 8/31/1999 | 1999 | 8 | 31 | 92 | 50 | 87 | 68.5 | 36.5 | 3443.5 |
| 9/1/1999 | 1999 | 9 | 1 | 93 | 60 | 74 | 67 | 35 | 3478.5 |
| 9/2/1999 | 1999 | 9 | 2 | 94 | 48 | 72 | 60 | 28 | 3506.5 |
| 9/3/1999 | 1999 | 9 | 3 | 95 | 47 | 73 | 60 | 28 | 3534.5 |
| 9/4/1999 | 1999 | 9 | 4 | 96 | 41 | 81 | 61 | 29 | 3563.5 |
| 9/5/1999 | 1999 | 9 | 5 | 97 | 42 | 82 | 62 | 30 | 3593.5 |
| 9/6/1999 | 1999 | 9 | 6 | 98 | 44 | 84 | 64 | 32 | 3625.5 |
| 9/7/1999 | 1999 | 9 | 7 | 99 | 42 | 76 | 59 | 27 | 3652.5 |
| 9/8/1999 | 1999 | 9 | 8 | 100 | 58 | 88 | 73 | 41 | 3693.5 |
| 9/9/1999 | 1999 | 9 | 9 | 101 | 43 | 64 | 53.5 | 21.5 | 3715 |
| 9/10/1999 | 1999 | 9 | 10 | 102 | 42 | 83 | 62.5 | 30.5 | 3745.5 |
| 9/11/1999 | 1999 | 9 | 11 | 103 | 45 | 76 | 60.5 | 28.5 | 3774 |
| 9/12/1999 | 1999 | 9 | 12 | 104 | 43 | 85 | 64 | 32 | 3806 |
| 9/13/1999 | 1999 | 9 | 13 | 105 | 42 | 85 | 63.5 | 31.5 | 3837.5 |
| 9/14/1999 | 1999 | 9 | 14 | 106 | 46 | 69 | 57.5 | 25.5 | 3863 |
| 9/15/1999 | 1999 | 9 | 15 | 107 | 40 | 77 | 58.5 | 26.5 | 3889.5 |
| 9/16/1999 | 1999 | 9 | 16 | 108 | 48 | 83 | 65.5 | 33.5 | 3923 |
| 9/17/1999 | 1999 | 9 | 17 | 109 | 40 | 77 | 52.25 | 20.25 | 3943.25 |
| 9/18/1999 | 1999 | 9 | 18 | 110 | 40 | 79 | 59.5 | 27.5 | 3970.75 |
| 9/19/1999 | 1999 | 9 | 19 | 111 | 44 | 78 | 61 | 29 | 3999.75 |
| 9/20/1999 | 1999 | 9 | 20 | 112 | 38 | 79 | 58.5 | 26.5 | 4026.25 |
| 9/21/1999 | 1999 | 9 | 21 | 113 | 40 | 80 | 60 | 28 | 4054.25 |
| 9/22/1999 | 1999 | 9 | 22 | 114 | 45 | 75 | 60 | 28 | 4082.25 |
| 9/23/1999 | 1999 | 9 | 23 | 115 | 45 | 70 | 57.5 | 25.5 | 4107.75 |
| 9/24/1999 | 1999 | 9 | 24 | 116 | 41 | 79 | 60 | 28 | 4135.75 |
| 9/25/1999 | 1999 | 9 | 25 | 117 | 40 | 83 | 61.5 | 29.5 | 4165.25 |
| 9/26/1999 | 1999 | 9 | 26 | 118 | 38 | 89 | 63.5 | 31.5 | 4196.75 |
| 9/27/1999 | 1999 | 9 | 27 | 119 | 38 | 86 | 62 | 30 | 4226.75 |
| 9/28/1999 | 1999 | 9 | 28 | 120 | 30 | 68 | 49 | 17 | 4243.75 |
| 9/29/1999 | 1999 | 9 | 29 | 121 | 30 | 76 | 53 | 21 | 4264.75 |
| 9/30/1999 | 1999 | 9 | 30 | 122 | 31 | 84 | 57.5 | 25.5 | 4290.25 |
| 10/1/1999 | 1999 | 10 | 1 | 123 | 35 | 89 | 62 | 30 | 4320.25 |
| 10/2/1999 | 1999 | 10 | 2 | 124 | 32 | 83 | 57.5 | 25.5 | 4345.75 |
| 10/3/1999 | 1999 | 10 | 3 | 125 | 31 | 81 | 56 | 24 | 4369.75 |
| 10/4/1999 | 1999 | 10 | 4 | 126 | 33 | 82 | 57.5 | 25.5 | 4395.25 |
| 10/5/1999 | 1999 | 10 | 5 | 127 | | 85 | 85 | 53 | 4448.25 |
| 10/6/1999 | 1999 | 10 | 6 | 128 | 38 | 81 | 59.5 | 27.5 | 4475.75 |
| 10/7/1999 | 1999 | 10 | 7 | 129 | 35 | 68 | 51.5 | 19.5 | 4495.25 |
| 10/8/1999 | 1999 | 10 | 8 | 130 | 32 | 80 | 56 | 24 | 4519.25 |
| 10/9/1999 | 1999 | 10 | 9 | 131 | 28 | 80 | 54 | 22 | 4541.25 |
| 10/10/1999 | 1999 | 10 | 10 | 132 | 32 | 85 | 58.5 | 26.5 | 4567.75 |
| 10/11/1999 | 1999 | 10 | 11 | 133 | 30 | 84 | 57 | 25 | 4592.75 |
| 10/12/1999 | 1999 | 10 | 12 | 134 | 30 | 83 | 56.5 | 24.5 | 4617.25 |
| 10/13/1999 | 1999 | 10 | 13 | 135 | 39 | 83 | 61 | 29 | 4646.25 |
| 10/14/1999 | 1999 | 10 | 14 | 136 | 30 | 82 | 56 | 24 | 4670.25 |
| 10/15/1999 | 1999 | 10 | 15 | 137 | 36 | 76 | 56 | 24 | 4694.25 |
| 10/16/1999 | 1999 | 10 | 16 | 138 | 28 | 73 | 50.5 | 18.5 | 4712.75 |
| 10/17/1999 | 1999 | 10 | 17 | 139 | 16 | 43 | 29.5 | -2.5 | 4710.25 |
| 10/18/1999 | 1999 | 10 | 18 | 140 | 22 | 66 | 44 | 12 | 4722.25 |
| 10/19/1999 | 1999 | 10 | 19 | 141 | 20 | 66 | 43 | 11 | 4733.25 |
| 10/20/1999 | 1999 | 10 | 20 | 142 | 21 | 72 | 46.5 | 14.5 | 4747.75 |
| 10/21/1999 | 1999 | 10 | 21 | 143 | 21 | 73 | 47 | 15 | 4762.75 |
| 10/22/1999 | 1999 | 10 | 22 | 144 | 25 | 77 | 51 | 19 | 4781.75 |
| 10/23/1999 | 1999 | 10 | 23 | 145 | 24 | 78 | 51 | 19 | 4800.75 |
| 10/24/1999 | 1999 | 10 | 24 | 146 | 24 | 78 | 51 | 19 | 4819.75 |
| 10/25/1999 | 1999 | 10 | 25 | 147 | 21 | 74 | 47.5 | 15.5 | 4835.25 |
| 10/26/1999 | 1999 | 10 | 26 | 148 | 30 | 77 | 53.5 | 21.5 | 4856.75 |
| 10/27/1999 | 1999 | 10 | 27 | 149 | 25 | 71 | 48 | 16 | 4872.75 |
| 10/28/1999 | 1999 | 10 | 28 | 150 | 27 | 76 | 51.5 | 19.5 | 4892.25 |
| 10/29/1999 | 1999 | 10 | 29 | 151 | 18 | 59 | 38.5 | 6.5 | 4898.75 |
| 10/30/1999 | 1999 | 10 | 30 | 152 | 19 | 62 | 40.5 | 8.5 | 4907.25 |
| 10/31/1999 | 1999 | 10 | 31 | 153 | 21 | 77 | 49 | 17 | 4924.25 |
| 11/1/1999 | 1999 | 11 | 1 | 154 | 30 | 78 | 54 | 22 | 4946.25 |
| 11/2/1999 | 1999 | 11 | 2 | 155 | 18 | 61 | 39.5 | 7.5 | 4953.75 |
| 11/3/1999 | 1999 | 11 | 3 | 156 | 19 | 72 | 45.5 | 13.5 | 4967.25 |
| 11/4/1999 | 1999 | 11 | 4 | 157 | 20 | 75 | 47.5 | 15.5 | 4982.75 |
| 11/5/1999 | 1999 | 11 | 5 | 158 | 21 | 77 | 49 | 17 | 4999.75 |
| 11/6/1999 | 1999 | 11 | 6 | 159 | 26 | 77 | 51.5 | 19.5 | 5019.25 |
| 11/7/1999 | 1999 | 11 | 7 | 160 | 26 | 71 | 48.5 | 16.5 | 5035.75 |
| 11/8/1999 | 1999 | 11 | 8 | 161 | 26 | 74 | 50 | 18 | 5053.75 |
| 11/9/1999 | 1999 | 11 | 9 | 162 | 18 | 70 | 44 | 12 | 5065.75 |
| 11/10/1999 | 1999 | 11 | 10 | 163 | 22 | 72 | 47 | 15 | 5080.75 |
| 11/11/1999 | 1999 | 11 | 11 | 164 | 22 | 78 | 50 | 18 | 5098.75 |
| 11/12/1999 | 1999 | 11 | 12 | 165 | 20 | 77 | 48.5 | 16.5 | 5115.25 |
| 11/13/1999 | 1999 | 11 | 13 | 166 | 19 | 76 | 47.5 | 15.5 | 5130.75 |
| 11/14/1999 | 1999 | 11 | 14 | 167 | 18 | 73 | 45.5 | 13.5 | 5144.25 |
| 11/15/1999 | 1999 | 11 | 15 | 168 | 18 | 75 | 46.5 | 14.5 | 5158.75 |
| 11/16/1999 | 1999 | 11 | 16 | 169 | 20 | 75 | 47.5 | 15.5 | 5174.25 |
| 11/17/1999 | 1999 | 11 | 17 | 170 | 40 | 75 | 57.5 | 25.5 | 5199.75 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/18/1999 | 1999 | 11 | 18 | 171 | 17 | 70 | 43.5 | 11.5 | 5211.25 |
| 11/19/1999 | 1999 | 11 | 19 | 172 | 19 | 67 | 43 | 11 | 5222.25 |
| 11/21/1999 | 1999 | 11 | 21 | 173 | 18 | 68 | 43 | 11 | 5233.25 |
| 11/22/1999 | 1999 | 11 | 22 | 174 | 6 | 45 | 25.5 | -6.5 | 5226.75 |
| 11/23/1999 | 1999 | 11 | 23 | 175 | 11 | 49 | 30 | -2 | 5224.75 |
| 11/24/1999 | 1999 | 11 | 24 | 176 | 4 | 49 | 26.5 | -5.5 | 5219.25 |
| 11/25/1999 | 1999 | 11 | 25 | 177 | 15 | 52 | 33.5 | 1.5 | 5220.75 |
| 11/26/1999 | 1999 | 11 | 26 | 178 | 15 | 69 | 42 | 10 | 5230.75 |
| 11/27/1999 | 1999 | 11 | 27 | 179 | 17 | 70 | 43.5 | 11.5 | 5242.25 |
| 11/28/1999 | 1999 | 11 | 28 | 180 | 18 | 68 | 43 | 11 | 5253.25 |
| 11/29/1999 | 1999 | 11 | 29 | 181 | 15 | 61 | 38 | 6 | 5259.25 |
| 11/30/1999 | 1999 | 11 | 30 | 182 | 23 | 66 | 44.5 | 12.5 | 5271.75 |
| 12/1/1999 | 1999 | 12 | 1 | 183 | 19 | 64 | 41.5 | 9.5 | 5281.25 |
| 12/2/1999 | 1999 | 12 | 2 | 184 | 23 | 53 | 38 | 6 | 5287.25 |
| 12/3/1999 | 1999 | 12 | 3 | 185 | 14 | 47 | 30.5 | -1.5 | 5285.75 |
| 12/4/1999 | 1999 | 12 | 4 | 186 | 4 | 46 | 25 | -7 | 5278.75 |
| 12/5/1999 | 1999 | 12 | 5 | 187 | 12 | 51 | 31.5 | -0.5 | 5278.25 |
| 12/6/1999 | 1999 | 12 | 6 | 188 | 8 | 53 | 30.5 | -1.5 | 5276.75 |
| 12/7/1999 | 1999 | 12 | 7 | 189 | 4 | 56 | 30 | -2 | 5274.75 |
| 12/8/1999 | 1999 | 12 | 8 | 190 | 5 | 31 | 18 | -14 | 5260.75 |
| 12/9/1999 | 1999 | 12 | 9 | 191 | 23 | 41 | 32 | 0 | 5260.75 |
| 12/10/1999 | 1999 | 12 | 10 | 192 | 22 | 40 | 31 | -1 | 5259.75 |
| 12/11/1999 | 1999 | 12 | 11 | 193 | 5 | 38 | 21.5 | -10.5 | 5249.25 |
| 12/12/1999 | 1999 | 12 | 12 | 194 | 3 | 49 | 26 | -6 | 5243.25 |
| 12/13/1999 | 1999 | 12 | 13 | 195 | 13 | 54 | 33.5 | 1.5 | 5244.75 |
| 12/14/1999 | 1999 | 12 | 14 | 196 | -1 | 33 | 16 | -16 | 5228.75 |
| 12/15/1999 | 1999 | 12 | 15 | 197 | 7 | 41 | 24 | -8 | 5220.75 |
| 12/16/1999 | 1999 | 12 | 16 | 198 | 11 | 48 | 29.5 | -2.5 | 5218.25 |
| 12/17/1999 | 1999 | 12 | 17 | 199 | 7 | 50 | 28.5 | -3.5 | 5214.75 |
| 12/18/1999 | 1999 | 12 | 18 | 200 | 17 | 61 | 39 | 7 | 5221.75 |
| 12/19/1999 | 1999 | 12 | 19 | 201 | 5 | 42 | 23.5 | -8.5 | 5213.25 |
| 12/20/1999 | 1999 | 12 | 20 | 202 | 3 | 42 | 22.5 | -9.5 | 5203.75 |
| 12/21/1999 | 1999 | 12 | 21 | 203 | -2 | 29 | 13.5 | -18.5 | 5185.25 |
| 12/22/1999 | 1999 | 12 | 22 | 204 | -6 | 36 | 15 | -17 | 5168.25 |
| 12/23/1999 | 1999 | 12 | 23 | 205 | -1 | 44 | 21.5 | -10.5 | 5157.75 |
| 12/24/1999 | 1999 | 12 | 24 | 206 | 8 | 50 | 29 | -3 | 5154.75 |
| 12/25/1999 | 1999 | 12 | 25 | 207 | 18 | 35 | 26.5 | -5.5 | 5149.25 |
| 12/26/1999 | 1999 | 12 | 26 | 208 | 10 | 43 | 26.5 | -5.5 | 5143.75 |
| 12/27/1999 | 1999 | 12 | 27 | 209 | 11 | 54 | 32.5 | 0.5 | 5144.25 |
| 12/28/1999 | 1999 | 12 | 28 | 210 | 11 | 59 | 35 | 3 | 5147.25 |
| 12/29/1999 | 1999 | 12 | 29 | 211 | 11 | 59 | 35 | 3 | 5150.25 |
| 12/30/1999 | 1999 | 12 | 30 | 212 | 8 | 57 | 32.5 | 0.5 | 5150.75 |
| 12/31/1999 | 1999 | 12 | 31 | 213 | 22 | 55 | 38.5 | 6.5 | 5157.25 |
| 1/1/2000 | 2000 | 1 | 1 | 214 | 15 | 53 | 34 | 2 | 5159.25 |
| 1/2/2000 | 2000 | 1 | 2 | 215 | 16 | 39 | 27.5 | -4.5 | 5154.75 |
| 1/3/2000 | 2000 | 1 | 3 | 216 | 2 | 33 | 17.5 | -14.5 | 5140.25 |
| 1/4/2000 | 2000 | 1 | 4 | 217 | 10 | 43 | 26.5 | -5.5 | 5134.75 |
| 1/5/2000 | 2000 | 1 | 5 | 218 | 6 | 46 | 26 | -6 | 5128.75 |
| 1/6/2000 | 2000 | 1 | 6 | 219 | 0 | 36 | 18 | -14 | 5114.75 |
| 1/7/2000 | 2000 | 1 | 7 | 220 | 4 | 45 | 24.5 | -7.5 | 5107.25 |
| 1/8/2000 | 2000 | 1 | 8 | 221 | 16 | 50 | 33 | 1 | 5108.25 |
| 1/9/2000 | 2000 | 1 | 9 | 222 | 16 | 53 | 34.5 | 2.5 | 5110.75 |
| 1/10/2000 | 2000 | 1 | 10 | 223 | 15 | 57 | 36 | 4 | 5114.75 |
| 1/11/2000 | 2000 | 1 | 11 | 224 | 15 | 65 | 40 | 8 | 5122.75 |
| 1/12/2000 | 2000 | 1 | 12 | 225 | 17 | 64 | 40.5 | 8.5 | 5131.25 |
| 1/13/2000 | 2000 | 1 | 13 | 226 | 14 | 65 | 39.5 | 7.5 | 5138.75 |
| 1/14/2000 | 2000 | 1 | 14 | 227 | 15 | 59 | 37 | 5 | 5143.75 |
| 1/15/2000 | 2000 | 1 | 15 | 228 | 17 | 71 | 44 | 12 | 5155.75 |
| 1/16/2000 | 2000 | 1 | 16 | 229 | 24 | 70 | 47 | 15 | 5170.75 |
| 1/17/2000 | 2000 | 1 | 17 | 230 | 23 | 69 | 46 | 14 | 5184.75 |
| 1/18/2000 | 2000 | 1 | 18 | 231 | 21 | 68 | 44.5 | 12.5 | 5197.25 |
| 1/19/2000 | 2000 | 1 | 19 | 232 | 21 | 67 | 44 | 12 | 5209.25 |
| 1/20/2000 | 2000 | 1 | 20 | 233 | 26 | 65 | 45.5 | 13.5 | 5222.75 |
| 1/21/2000 | 2000 | 1 | 21 | 234 | 24 | 60 | 42 | 10 | 5232.75 |
| 1/22/2000 | 2000 | 1 | 22 | 235 | 13 | 57 | 35 | 3 | 5235.75 |
| 1/23/2000 | 2000 | 1 | 23 | 236 | 19 | 52 | 35.5 | 3.5 | 5239.25 |
| 1/24/2000 | 2000 | 1 | 24 | 237 | 30 | 62 | 46 | 14 | 5253.25 |
| 1/25/2000 | 2000 | 1 | 25 | 238 | 40 | 60 | 50 | 18 | 5271.25 |
| 1/26/2000 | 2000 | 1 | 26 | 239 | 35 | 56 | 45.5 | 13.5 | 5284.75 |
| 1/27/2000 | 2000 | 1 | 27 | 240 | 13 | 60 | 36.5 | 4.5 | 5289.25 |
| 1/28/2000 | 2000 | 1 | 28 | 241 | 5 | 48 | 26.5 | -5.5 | 5283.75 |
| 1/29/2000 | 2000 | 1 | 29 | 242 | 5 | 45 | 25 | -7 | 5276.75 |
| 1/30/2000 | 2000 | 1 | 30 | 243 | 15 | 52 | 33.5 | 1.5 | 5278.25 |
| 1/31/2000 | 2000 | 1 | 31 | 244 | 25 | 43 | 34 | 2 | 5280.25 |
| 2/1/2000 | 2000 | 2 | 1 | 245 | 7 | 46 | 26.5 | -5.5 | 5274.75 |
| 2/2/2000 | 2000 | 2 | 2 | 246 | 11 | 54 | 32.5 | 0.5 | 5275.25 |
| 2/3/2000 | 2000 | 2 | 3 | 247 | 16 | 71 | 43.5 | 11.5 | 5286.75 |
| 2/4/2000 | 2000 | 2 | 4 | 248 | 7 | 51 | 29 | -3 | 5283.75 |
| 2/5/2000 | 2000 | 2 | 5 | 249 | 13 | 63 | 38 | 6 | 5289.75 |
| 2/6/2000 | 2000 | 2 | 6 | 250 | 14 | 60 | 37 | 5 | 5294.75 |
| 2/7/2000 | 2000 | 2 | 7 | 251 | 16 | 62 | 39 | 7 | 5301.75 |
| 2/8/2000 | 2000 | 2 | 8 | 252 | 20 | 65 | 42.5 | 10.5 | 5312.25 |
| 2/9/2000 | 2000 | 2 | 9 | 253 | 32 | 64 | 48 | 16 | 5328.25 |
| 2/10/2000 | 2000 | 2 | 10 | 254 | 24 | 60 | 42 | 10 | 5338.25 |
| 2/11/2000 | 2000 | 2 | 11 | 255 | 16 | 61 | 38.5 | 6.5 | 5344.75 |
| 2/12/2000 | 2000 | 2 | 12 | 256 | 30 | 54 | 42 | 10 | 5354.75 |
| 2/13/2000 | 2000 | 2 | 13 | 257 | 23 | 54 | 38.5 | 6.5 | 5361.25 |
| 2/14/2000 | 2000 | 2 | 14 | 258 | 19 | 67 | 43 | 11 | 5372.25 |
| 2/15/2000 | 2000 | 2 | 15 | 259 | 19 | 68 | 43.5 | 11.5 | 5383.75 |
| 2/16/2000 | 2000 | 2 | 16 | 260 | 34 | 64 | 49 | 17 | 5400.75 |
| 2/17/2000 | 2000 | 2 | 17 | 261 | 21 | 51 | 36 | 4 | 5404.75 |
| 2/18/2000 | 2000 | 2 | 18 | 262 | 19 | 61 | 40 | 8 | 5412.75 |
| 2/19/2000 | 2000 | 2 | 19 | 263 | 20 | 62 | 41 | 9 | 5421.75 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/20/2000 | 2000 | 2 | 20 | 264 | 21 | 61 | 41 | 9 | 5430.75 |
| 2/21/2000 | 2000 | 2 | 21 | 265 | 33 | 62 | 47.5 | 15.5 | 5446.25 |
| 2/22/2000 | 2000 | 2 | 22 | 266 | 15 | 50 | 32.5 | 0.5 | 5446.75 |
| 2/23/2000 | 2000 | 2 | 23 | 267 | 33 | 62 | 47.5 | 15.5 | 5462.25 |
| 2/24/2000 | 2000 | 2 | 24 | 268 | 21 | 52 | 36.5 | 4.5 | 5466.75 |
| 2/25/2000 | 2000 | 2 | 25 | 269 | 9 | 41 | 25 | -7 | 5459.75 |
| 2/26/2000 | 2000 | 2 | 26 | 270 | 13 | 55 | 34 | 2 | 5461.75 |
| 2/27/2000 | 2000 | 2 | 27 | 271 | 30 | 64 | 47 | 15 | 5476.75 |
| 2/28/2000 | 2000 | 2 | 28 | 272 | 16 | 62 | 39 | 7 | 5483.75 |
| 2/29/2000 | 2000 | 2 | 29 | 273 | 24 | 60 | 42 | 10 | 5493.75 |
| 3/1/2000 | 2000 | 3 | 1 | 274 | 16 | 54 | 35 | 3 | 5496.75 |
| 3/2/2000 | 2000 | 3 | 2 | 275 | 14 | 59 | 36.5 | 4.5 | 5501.25 |
| 3/3/2000 | 2000 | 3 | 3 | 276 | 17 | 67 | 42 | 10 | 5511.25 |
| 3/4/2000 | 2000 | 3 | 4 | 277 | 32 | 70 | 51 | 19 | 5530.25 |
| 3/5/2000 | 2000 | 3 | 5 | 278 | 31 | 49 | 40 | 8 | 5538.25 |
| 3/6/2000 | 2000 | 3 | 6 | 279 | 32 | 58 | 45 | 13 | 5551.25 |
| 3/7/2000 | 2000 | 3 | 7 | 280 | 25 | 43 | 34 | 2 | 5553.25 |
| 3/8/2000 | 2000 | 3 | 8 | 281 | 25 | 55 | 40 | 8 | 5561.25 |
| 3/9/2000 | 2000 | 3 | 9 | 282 | 19 | 56 | 37.5 | 5.5 | 5566.75 |
| 3/10/2000 | 2000 | 3 | 10 | 283 | 11 | 48 | 29.5 | -2.5 | 5564.25 |
| 3/11/2000 | 2000 | 3 | 11 | 284 | 15 | 58 | 36.5 | 4.5 | 5568.75 |
| 3/12/2000 | 2000 | 3 | 12 | 285 | 21 | 66 | 43.5 | 11.5 | 5580.25 |
| 3/13/2000 | 2000 | 3 | 13 | 286 | 23 | 67 | 45 | 13 | 5593.25 |
| 3/14/2000 | 2000 | 3 | 14 | 287 | 20 | 66 | 43 | 11 | 5604.25 |
| 3/15/2000 | 2000 | 3 | 15 | 288 | 16 | 68 | 42 | 10 | 5614.25 |
| 3/16/2000 | 2000 | 3 | 16 | 289 | 17 | 63 | 40 | 8 | 5622.25 |
| 3/17/2000 | 2000 | 3 | 17 | 290 | 18 | 66 | 42 | 10 | 5632.25 |
| 3/18/2000 | 2000 | 3 | 18 | 291 | 9 | 52 | 30.5 | -1.5 | 5630.75 |
| 3/19/2000 | 2000 | 3 | 19 | 292 | 33 | 67 | 50 | 18 | 5648.75 |
| 3/20/2000 | 2000 | 3 | 20 | 293 | 27 | 62 | 44.5 | 12.5 | 5661.25 |
| 3/21/2000 | 2000 | 3 | 21 | 294 | 28 | 61 | 44.5 | 12.5 | 5673.75 |
| 3/22/2000 | 2000 | 3 | 22 | 295 | 19 | 36 | 27.5 | -4.5 | 5669.25 |
| 3/23/2000 | 2000 | 3 | 23 | 296 | 22 | 54 | 38 | 6 | 5675.25 |
| 3/24/2000 | 2000 | 3 | 24 | 297 | 25 | 68 | 46.5 | 14.5 | 5689.75 |
| 3/25/2000 | 2000 | 3 | 25 | 298 | 24 | 70 | 47 | 15 | 5704.75 |
| 3/27/2000 | 2000 | 3 | 27 | 299 | 32 | 72 | 52 | 20 | 5724.75 |
| 3/28/2000 | 2000 | 3 | 28 | 300 | 35 | 56 | 45.5 | 13.5 | 5738.25 |
| 3/29/2000 | 2000 | 3 | 29 | 301 | 35 | 62 | 48.5 | 16.5 | 5754.75 |
| 3/30/2000 | 2000 | 3 | 30 | 302 | 32 | 58 | 45 | 13 | 5767.75 |
| 3/31/2000 | 2000 | 3 | 31 | 303 | 30 | 42 | 36 | 4 | 5771.75 |
| 4/1/2000 | 2000 | 4 | 1 | 304 | 20 | 55 | 37.5 | 5.5 | 5777.25 |
| 4/2/2000 | 2000 | 4 | 2 | 305 | 25 | 57 | 41 | 9 | 5786.25 |
| 4/3/2000 | 2000 | 4 | 3 | 306 | 25 | 65 | 45 | 13 | 5799.25 |
| 4/4/2000 | 2000 | 4 | 4 | 307 | 30 | 76 | 53 | 21 | 5820.25 |
| 4/5/2000 | 2000 | 4 | 5 | 308 | 38 | 77 | 57.5 | 25.5 | 5845.75 |
| 4/6/2000 | 2000 | 4 | 6 | 309 | 34 | 77 | 55.5 | 23.5 | 5869.25 |
| 4/7/2000 | 2000 | 4 | 7 | 310 | 36 | 76 | 56 | 24 | 5893.25 |
| 4/8/2000 | 2000 | 4 | 8 | 311 | 37 | 64 | 50.5 | 18.5 | 5911.75 |
| 4/9/2000 | 2000 | 4 | 9 | 312 | 37 | 80 | 58.5 | 26.5 | 5938.25 |
| 4/10/2000 | 2000 | 4 | 10 | 313 | 37 | 73 | 55 | 23 | 5961.25 |
| 4/11/2000 | 2000 | 4 | 11 | 314 | 28 | 65 | 46.5 | 14.5 | 5975.75 |
| 4/12/2000 | 2000 | 4 | 12 | 315 | 28 | 70 | 49 | 17 | 5992.75 |
| 4/13/2000 | 2000 | 4 | 13 | 316 | 33 | 77 | 55 | 23 | 6015.75 |
| 4/14/2000 | 2000 | 4 | 14 | 317 | 35 | 76 | 55.5 | 23.5 | 6039.25 |
| 4/15/2000 | 2000 | 4 | 15 | 318 | 25 | 65 | 45 | 13 | 6052.25 |
| 4/16/2000 | 2000 | 4 | 16 | 319 | 32 | 76 | 54 | 22 | 6074.25 |
| 4/17/2000 | 2000 | 4 | 17 | 320 | 38 | 82 | 60 | 28 | 6102.25 |
| 4/18/2000 | 2000 | 4 | 18 | 321 | 30 | 75 | 52.5 | 20.5 | 6122.75 |
| 4/19/2000 | 2000 | 4 | 19 | 322 | 24 | 65 | 44.5 | 12.5 | 6135.25 |
| 4/20/2000 | 2000 | 4 | 20 | 323 | 35 | 76 | 55.5 | 23.5 | 6158.75 |
| 4/21/2000 | 2000 | 4 | 21 | 324 | 37 | 73 | 55 | 23 | 6181.75 |
| 4/22/2000 | 2000 | 4 | 22 | 325 | 41 | 63 | 52 | 20 | 6201.75 |
| 4/23/2000 | 2000 | 4 | 23 | 326 | 30 | 78 | 54 | 22 | 6223.75 |
| 4/24/2000 | 2000 | 4 | 24 | 327 | 31 | 87 | 59 | 27 | 6250.75 |
| 4/25/2000 | 2000 | 4 | 25 | 328 | 32 | 87 | 59.5 | 27.5 | 6278.25 |
| 4/26/2000 | 2000 | 4 | 26 | 329 | 32 | 87 | 59.5 | 27.5 | 6305.75 |
| 4/27/2000 | 2000 | 4 | 27 | 330 | 51 | 90 | 70.5 | 38.5 | 6344.25 |
| 4/28/2000 | 2000 | 4 | 28 | 331 | 40 | 84 | 62 | 30 | 6374.25 |
| 4/29/2000 | 2000 | 4 | 29 | 332 | 38 | 73 | 55.5 | 23.5 | 6397.75 |
| 4/30/2000 | 2000 | 4 | 30 | 333 | 33 | 68 | 50.5 | 18.5 | 6416.25 |
| 5/1/2000 | 2000 | 5 | 1 | 334 | 31 | 81 | 56 | 24 | 6440.25 |
| 5/2/2000 | 2000 | 5 | 2 | 335 | 34 | 84 | 59 | 27 | 6467.25 |
| 5/3/2000 | 2000 | 5 | 3 | 336 | 36 | 88 | 62 | 30 | 6497.25 |
| 5/4/2000 | 2000 | 5 | 4 | 337 | 36 | 89 | 62.5 | 30.5 | 6527.75 |
| 5/5/2000 | 2000 | 5 | 5 | 338 | 37 | 90 | 63.5 | 31.5 | 6559.25 |
| 5/6/2000 | 2000 | 5 | 6 | 339 | 38 | 84 | 61 | 29 | 6588.25 |
| 5/7/2000 | 2000 | 5 | 7 | 340 | 44 | 80 | 62 | 30 | 6618.25 |
| 5/8/2000 | 2000 | 5 | 8 | 341 | 46 | 80 | 63 | 31 | 6649.25 |
| 5/9/2000 | 2000 | 5 | 9 | 342 | 50 | 85 | 67.5 | 35.5 | 6684.75 |
| 5/10/2000 | 2000 | 5 | 10 | 343 | 52 | 88 | 70 | 38 | 6722.75 |
| 5/11/2000 | 2000 | 5 | 11 | 344 | 32 | 81 | 56.5 | 24.5 | 6747.25 |
| 5/12/2000 | 2000 | 5 | 12 | 345 | 24 | 63 | 43.5 | 11.5 | 6758.75 |
| 5/13/2000 | 2000 | 5 | 13 | 346 | 29 | 63 | 46 | 14 | 6772.75 |
| 5/14/2000 | 2000 | 5 | 14 | 347 | 29 | 63 | 46 | 14 | 6786.75 |
| 5/15/2000 | 2000 | 5 | 15 | 348 | 53 | 88 | 70.5 | 38.5 | 6825.25 |
| 5/16/2000 | 2000 | 5 | 16 | 349 | 40 | 80 | 60 | 28 | 6853.25 |
| 5/17/2000 | 2000 | 5 | 17 | 350 | 32 | 70 | 51 | 19 | 6872.25 |
| 5/18/2000 | 2000 | 5 | 18 | 351 | 38 | 72 | 55 | 23 | 6895.25 |
| 5/19/2000 | 2000 | 5 | 19 | 352 | 35 | 75 | 55 | 23 | 6918.25 |
| 5/20/2000 | 2000 | 5 | 20 | 353 | 37 | 81 | 59 | 27 | 6945.25 |
| 5/21/2000 | 2000 | 5 | 21 | 354 | 38 | 87 | 62.5 | 30.5 | 6975.75 |
| 5/22/2000 | 2000 | 5 | 22 | 355 | 40 | 91 | 65.5 | 33.5 | 7009.25 |
| 5/23/2000 | 2000 | 5 | 23 | 356 | 54 | 96 | 75 | 43 | 7052.25 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/24/2000 | 2000 | 5 | 24 | 357 | 59 | 92 | 75.5 | 43.5 | 7095.75 |
| 5/25/2000 | 2000 | 5 | 25 | 358 | 45 | 88 | 66.5 | 34.5 | 7130.25 |
| 5/26/2000 | 2000 | 5 | 26 | 359 | 41 | 84 | 62.5 | 30.5 | 7160.75 |
| 5/27/2000 | 2000 | 5 | 27 | 360 | 40 | 86 | 63 | 31 | 7191.75 |
| 5/28/2000 | 2000 | 5 | 28 | 361 | 45 | 97 | 71 | 39 | 7230.75 |
| 5/29/2000 | 2000 | 5 | 29 | 362 | 54 | 97 | 75.5 | 43.5 | 7274.25 |
| 5/30/2000 | 2000 | 5 | 30 | 363 | 46 | 95 | 70.5 | 38.5 | 7312.75 |
| 5/31/2000 | 2000 | 5 | 31 | 364 | 49 | 94 | 71.5 | 39.5 | 7352.25 |
| 6/1/2000 | 2000 | 6 | 1 | 1 | 56 | 90 | 73 | 41 | 41 |
| 6/2/2000 | 2000 | 6 | 2 | 2 | 44 | 90 | 67 | 35 | 76 |
| 6/3/2000 | 2000 | 6 | 3 | 3 | 45 | 90 | 67.5 | 35.5 | 111.5 |
| 6/4/2000 | 2000 | 6 | 4 | 4 | 54 | 94 | 74 | 42 | 153.5 |
| 6/5/2000 | 2000 | 6 | 5 | 5 | 52 | 93 | 72.5 | 40.5 | 194 |
| 6/6/2000 | 2000 | 6 | 6 | 6 | 54 | 93 | 73.5 | 41.5 | 235.5 |
| 6/7/2000 | 2000 | 6 | 7 | 7 | 58 | 94 | 76 | 44 | 279.5 |
| 6/8/2000 | 2000 | 6 | 8 | 8 | 51 | 86 | 68.5 | 36.5 | 316 |
| 6/9/2000 | 2000 | 6 | 9 | 9 | 44 | 86 | 65 | 33 | 349 |
| 6/10/2000 | 2000 | 6 | 10 | 10 | 42 | 86 | 64 | 32 | 381 |
| 6/11/2000 | 2000 | 6 | 11 | 11 | 43 | 89 | 66 | 34 | 415 |
| 6/12/2000 | 2000 | 6 | 12 | 12 | 43 | 91 | 67 | 35 | 450 |
| 6/13/2000 | 2000 | 6 | 13 | 13 | 52 | 93 | 72.5 | 40.5 | 490.5 |
| 6/14/2000 | 2000 | 6 | 14 | 14 | 45 | 92 | 68.5 | 36.5 | 527 |
| 6/15/2000 | 2000 | 6 | 15 | 15 | 50 | 97 | 73.5 | 41.5 | 568.5 |
| 6/16/2000 | 2000 | 6 | 16 | 16 | 59 | 93 | 76 | 44 | 612.5 |
| 6/17/2000 | 2000 | 6 | 17 | 17 | 53 | 88 | 70.5 | 38.5 | 651 |
| 6/18/2000 | 2000 | 6 | 18 | 18 | 52 | 84 | 68 | 36 | 687 |
| 6/19/2000 | 2000 | 6 | 19 | 19 | 56 | 84 | 70 | 38 | 725 |
| 6/20/2000 | 2000 | 6 | 20 | 20 | 46 | 86 | 66 | 34 | 759 |
| 6/21/2000 | 2000 | 6 | 21 | 21 | 48 | 90 | 69 | 37 | 796 |
| 6/22/2000 | 2000 | 6 | 22 | 22 | 48 | 90 | 69 | 37 | 833 |
| 6/23/2000 | 2000 | 6 | 23 | 23 | 51 | 87 | 69 | 37 | 870 |
| 6/24/2000 | 2000 | 6 | 24 | 24 | 51 | 89 | 70 | 38 | 908 |
| 6/25/2000 | 2000 | 6 | 25 | 25 | 52 | 95 | 73.5 | 41.5 | 949.5 |
| 6/26/2000 | 2000 | 6 | 26 | 26 | 60 | 87 | 73.5 | 41.5 | 991 |
| 6/27/2000 | 2000 | 6 | 27 | 27 | 50 | 82 | 66 | 34 | 1025 |
| 6/28/2000 | 2000 | 6 | 28 | 28 | 56 | 90 | 73 | 41 | 1066 |
| 6/29/2000 | 2000 | 6 | 29 | 29 | 49 | 82 | 65.5 | 33.5 | 1099.5 |
| 6/30/2000 | 2000 | 6 | 30 | 30 | 59 | 87 | 73 | 41 | 1140.5 |
| 7/1/2000 | 2000 | 7 | 1 | 31 | 55 | 92 | 73.5 | 41.5 | 1182 |
| 7/2/2000 | 2000 | 7 | 2 | 32 | 54 | 90 | 72 | 40 | 1222 |
| 7/3/2000 | 2000 | 7 | 3 | 33 | 52 | 92 | 72 | 40 | 1262 |
| 7/4/2000 | 2000 | 7 | 4 | 34 | 55 | 92 | 73.5 | 41.5 | 1303.5 |
| 7/5/2000 | 2000 | 7 | 5 | 35 | 52 | 95 | 73.5 | 41.5 | 1345 |
| 7/6/2000 | 2000 | 7 | 6 | 36 | 47 | 95 | 71 | 39 | 1384 |
| 7/7/2000 | 2000 | 7 | 7 | 37 | 49 | 95 | 72 | 40 | 1424 |
| 7/8/2000 | 2000 | 7 | 8 | 38 | 56 | 84 | 70 | 38 | 1462 |
| 7/9/2000 | 2000 | 7 | 9 | 39 | 52 | 84 | 68 | 36 | 1498 |
| 7/10/2000 | 2000 | 7 | 10 | 40 | 54 | 88 | 71 | 39 | 1537 |
| 7/11/2000 | 2000 | 7 | 11 | 41 | 50 | 90 | 70 | 38 | 1575 |
| 7/12/2000 | 2000 | 7 | 12 | 42 | 58 | 90 | 74 | 42 | 1617 |
| 7/13/2000 | 2000 | 7 | 13 | 43 | 57 | 92 | 74.5 | 42.5 | 1659.5 |
| 7/14/2000 | 2000 | 7 | 14 | 44 | 58 | 91 | 74.5 | 42.5 | 1702 |
| 7/15/2000 | 2000 | 7 | 15 | 45 | 60 | 92 | 76 | 44 | 1746 |
| 7/16/2000 | 2000 | 7 | 16 | 46 | 50 | 93 | 71.5 | 39.5 | 1785.5 |
| 7/17/2000 | 2000 | 7 | 17 | 47 | 50 | 93 | 71.5 | 39.5 | 1825 |
| 7/18/2000 | 2000 | 7 | 18 | 48 | 51 | 93 | 72 | 40 | 1865 |
| 7/19/2000 | 2000 | 7 | 19 | 49 | 56 | 97 | 76.5 | 44.5 | 1909.5 |
| 7/20/2000 | 2000 | 7 | 20 | 50 | 54 | 95 | 74.5 | 42.5 | 1952 |
| 7/21/2000 | 2000 | 7 | 21 | 51 | 55 | 96 | 75.5 | 43.5 | 1995.5 |
| 7/22/2000 | 2000 | 7 | 22 | 52 | 54 | 99 | 76.5 | 44.5 | 2040 |
| 7/23/2000 | 2000 | 7 | 23 | 53 | 51 | 99 | 75 | 43 | 2083 |
| 7/24/2000 | 2000 | 7 | 24 | 54 | 55 | 96 | 75.5 | 43.5 | 2126.5 |
| 7/25/2000 | 2000 | 7 | 25 | 55 | 55 | 98 | 76.5 | 44.5 | 2171 |
| 7/26/2000 | 2000 | 7 | 26 | 56 | 55 | 91 | 73 | 41 | 2212 |
| 7/27/2000 | 2000 | 7 | 27 | 57 | 54 | 97 | 75.5 | 43.5 | 2255.5 |
| 7/28/2000 | 2000 | 7 | 28 | 58 | 62 | 98 | 80 | 48 | 2303.5 |
| 7/29/2000 | 2000 | 7 | 29 | 59 | 50 | 96 | 73 | 41 | 2344.5 |
| 7/30/2000 | 2000 | 7 | 30 | 60 | 56 | 92 | 74 | 42 | 2386.5 |
| 7/31/2000 | 2000 | 7 | 31 | 61 | 50 | 91 | 70.5 | 38.5 | 2425 |
| 8/1/2000 | 2000 | 8 | 1 | 62 | 52 | 95 | 73.5 | 41.5 | 2466.5 |
| 8/2/2000 | 2000 | 8 | 2 | 63 | 59 | 97 | 78 | 46 | 2512.5 |
| 8/3/2000 | 2000 | 8 | 3 | 64 | 55 | 100 | 77.5 | 45.5 | 2558 |
| 8/4/2000 | 2000 | 8 | 4 | 65 | 58 | 95 | 76.5 | 44.5 | 2602.5 |
| 8/5/2000 | 2000 | 8 | 5 | 66 | 55 | 96 | 75.5 | 43.5 | 2646 |
| 8/6/2000 | 2000 | 8 | 6 | 67 | 56 | 94 | 75 | 43 | 2689 |
| 8/7/2000 | 2000 | 8 | 7 | 68 | 52 | 95 | 73.5 | 41.5 | 2730.5 |
| 8/8/2000 | 2000 | 8 | 8 | 69 | 55 | 95 | 75 | 43 | 2773.5 |
| 8/9/2000 | 2000 | 8 | 9 | 70 | 53 | 95 | 74 | 42 | 2815.5 |
| 8/10/2000 | 2000 | 8 | 10 | 71 | 60 | 88 | 74 | 42 | 2857.5 |
| 8/11/2000 | 2000 | 8 | 11 | 72 | 54 | 94 | 74 | 42 | 2899.5 |
| 8/12/2000 | 2000 | 8 | 12 | 73 | 58 | 89 | 73.5 | 41.5 | 2941 |
| 8/13/2000 | 2000 | 8 | 13 | 74 | 52 | 91 | 71.5 | 39.5 | 2980.5 |
| 8/14/2000 | 2000 | 8 | 14 | 75 | 55 | 97 | 76 | 44 | 3024.5 |
| 8/15/2000 | 2000 | 8 | 15 | 76 | 55 | 97 | 76 | 44 | 3068.5 |
| 8/16/2000 | 2000 | 8 | 16 | 77 | 54 | 96 | 75 | 43 | 3111.5 |
| 8/17/2000 | 2000 | 8 | 17 | 78 | 57 | 86 | 71.5 | 39.5 | 3151 |
| 8/18/2000 | 2000 | 8 | 18 | 79 | 52 | 80 | 66 | 34 | 3185 |
| 8/19/2000 | 2000 | 8 | 19 | 80 | 47 | 86 | 66.5 | 34.5 | 3219.5 |
| 8/20/2000 | 2000 | 8 | 20 | 81 | 50 | 90 | 70 | 38 | 3257.5 |
| 8/21/2000 | 2000 | 8 | 21 | 82 | 49 | 93 | 71 | 39 | 3296.5 |
| 8/22/2000 | 2000 | 8 | 22 | 83 | 50 | 93 | 71.5 | 39.5 | 3336 |
| 8/23/2000 | 2000 | 8 | 23 | 84 | 49 | 90 | 69.5 | 37.5 | 3373.5 |
| 8/24/2000 | 2000 | 8 | 24 | 85 | 53 | 92 | 72.5 | 40.5 | 3414 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/25/2000 | 2000 | 8 | 25 | 86 | 50 | 88 | 69 | 37 | 3451 |
| 8/26/2000 | 2000 | 8 | 26 | 87 | 49 | 90 | 69.5 | 37.5 | 3488.5 |
| 8/27/2000 | 2000 | 8 | 27 | 88 | 54 | 93 | 73.5 | 41.5 | 3530 |
| 8/28/2000 | 2000 | 8 | 28 | 89 | 52 | 88 | 70 | 38 | 3568 |
| 8/29/2000 | 2000 | 8 | 29 | 90 | 49 | 84 | 66.5 | 34.5 | 3602.5 |
| 8/30/2000 | 2000 | 8 | 30 | 91 | 48 | 85 | 66.5 | 34.5 | 3637 |
| 8/31/2000 | 2000 | 8 | 31 | 92 | 44 | 86 | 65 | 33 | 3670 |
| 9/1/2000 | 2000 | 9 | 1 | 93 | 47 | 83 | 65 | 33 | 3703 |
| 9/2/2000 | 2000 | 9 | 2 | 94 | 52 | 90 | 71 | 39 | 3742 |
| 9/3/2000 | 2000 | 9 | 3 | 95 | 51 | 94 | 72.5 | 40.5 | 3782.5 |
| 9/4/2000 | 2000 | 9 | 4 | 96 | 50 | 93 | 71.5 | 39.5 | 3822 |
| 9/5/2000 | 2000 | 9 | 5 | 97 | 48 | 94 | 71 | 39 | 3861 |
| 9/6/2000 | 2000 | 9 | 6 | 98 | 47 | 90 | 68.5 | 36.5 | 3897.5 |
| 9/7/2000 | 2000 | 9 | 7 | 99 | 57 | 88 | 72.5 | 40.5 | 3938 |
| 9/8/2000 | 2000 | 9 | 8 | 100 | 47 | 84 | 65.5 | 33.5 | 3971.5 |
| 9/9/2000 | 2000 | 9 | 9 | 101 | 42 | 87 | 64.5 | 32.5 | 4004 |
| 9/10/2000 | 2000 | 9 | 10 | 102 | 51 | 87 | 69 | 37 | 4041 |
| 9/11/2000 | 2000 | 9 | 11 | 103 | 42 | 88 | 65 | 33 | 4074 |
| 9/12/2000 | 2000 | 9 | 12 | 104 | 42 | 91 | 66.5 | 34.5 | 4108.5 |
| 9/13/2000 | 2000 | 9 | 13 | 105 | 44 | 92 | 68 | 36 | 4144.5 |
| 9/14/2000 | 2000 | 9 | 14 | 106 | 47 | 92 | 69.5 | 37.5 | 4182 |
| 9/15/2000 | 2000 | 9 | 15 | 107 | 46 | 93 | 69.5 | 37.5 | 4219.5 |
| 9/16/2000 | 2000 | 9 | 16 | 108 | 46 | 86 | 66 | 34 | 4253.5 |
| 9/17/2000 | 2000 | 9 | 17 | 109 | 46 | 84 | 65 | 33 | 4286.5 |
| 9/18/2000 | 2000 | 9 | 18 | 110 | 40 | 78 | 59 | 27 | 4313.5 |
| 9/19/2000 | 2000 | 9 | 19 | 111 | 46 | 84 | 65 | 33 | 4346.5 |
| 9/20/2000 | 2000 | 9 | 20 | 112 | 50 | 90 | 70 | 38 | 4384.5 |
| 9/21/2000 | 2000 | 9 | 21 | 113 | 50 | 85 | 67.5 | 35.5 | 4420 |
| 9/22/2000 | 2000 | 9 | 22 | 114 | 50 | 85 | 67.5 | 35.5 | 4455.5 |
| 9/23/2000 | 2000 | 9 | 23 | 115 | 37 | 78 | 57.5 | 25.5 | 4481 |
| 9/24/2000 | 2000 | 9 | 24 | 116 | 26 | 65 | 45.5 | 13.5 | 4494.5 |
| 9/25/2000 | 2000 | 9 | 25 | 117 | 32 | 77 | 54.5 | 22.5 | 4517 |
| 9/26/2000 | 2000 | 9 | 26 | 118 | 48 | 85 | 66.5 | 34.5 | 4551.5 |
| 9/27/2000 | 2000 | 9 | 27 | 119 | 45 | 82 | 63.5 | 31.5 | 4583 |
| 9/28/2000 | 2000 | 9 | 28 | 120 | 45 | 89 | 67 | 35 | 4618 |
| 9/29/2000 | 2000 | 9 | 29 | 121 | 48 | 76 | 62 | 30 | 4648 |
| 9/30/2000 | 2000 | 9 | 30 | 122 | 40 | 84 | 62 | 30 | 4678 |
| 10/1/2000 | 2000 | 10 | 1 | 123 | 42 | 87 | 64.5 | 32.5 | 4710.5 |
| 10/2/2000 | 2000 | 10 | 2 | 124 | 45 | 86 | 65.5 | 33.5 | 4744 |
| 10/3/2000 | 2000 | 10 | 3 | 125 | 49 | 86 | 67.5 | 35.5 | 4779.5 |
| 10/4/2000 | 2000 | 10 | 4 | 126 | 34 | 66 | 50 | 18 | 4797.5 |
| 10/5/2000 | 2000 | 10 | 5 | 127 | 37 | 79 | 58 | 26 | 4823.5 |
| 10/6/2000 | 2000 | 10 | 6 | 128 | 37 | 79 | 58 | 26 | 4849.5 |
| 10/7/2000 | 2000 | 10 | 7 | 129 | 37 | 65 | 51 | 19 | 4868.5 |
| 10/8/2000 | 2000 | 10 | 8 | 130 | 36 | 64 | 50 | 18 | 4886.5 |
| 10/9/2000 | 2000 | 10 | 9 | 131 | 32 | 61 | 46.5 | 14.5 | 4901 |
| 10/10/2000 | 2000 | 10 | 10 | 132 | 34 | 63 | 48.5 | 16.5 | 4917.5 |
| 10/11/2000 | 2000 | 10 | 11 | 133 | 32 | 65 | 48.5 | 16.5 | 4934 |
| 10/12/2000 | 2000 | 10 | 12 | 134 | 37 | 70 | 53.5 | 21.5 | 4955.5 |
| 10/13/2000 | 2000 | 10 | 13 | 135 | 30 | 67 | 48.5 | 16.5 | 4972 |
| 10/14/2000 | 2000 | 10 | 14 | 136 | 30 | 72 | 51 | 19 | 4991 |
| 10/15/2000 | 2000 | 10 | 15 | 137 | 35 | 74 | 54.5 | 22.5 | 5013.5 |
| 10/16/2000 | 2000 | 10 | 16 | 138 | 28 | 72 | 50 | 18 | 5031.5 |
| 10/17/2000 | 2000 | 10 | 17 | 139 | 31 | 73 | 52 | 20 | 5051.5 |
| 10/18/2000 | 2000 | 10 | 18 | 140 | 36 | 70 | 53 | 21 | 5072.5 |
| 10/19/2000 | 2000 | 10 | 19 | 141 | 31 | 69 | 50 | 18 | 5090.5 |
| 10/20/2000 | 2000 | 10 | 20 | 142 | 35 | 75 | 55 | 23 | 5113.5 |
| 10/21/2000 | 2000 | 10 | 21 | 143 | 40 | 58 | 49 | 17 | 5130.5 |
| 10/22/2000 | 2000 | 10 | 22 | 144 | 40 | 59 | 49.5 | 17.5 | 5148 |
| 10/23/2000 | 2000 | 10 | 23 | 145 | 35 | 60 | 47.5 | 15.5 | 5163.5 |
| 10/24/2000 | 2000 | 10 | 24 | 146 | 36 | 58 | 47 | 15 | 5178.5 |
| 10/25/2000 | 2000 | 10 | 25 | 147 | 30 | 62 | 46 | 14 | 5192.5 |
| 10/26/2000 | 2000 | 10 | 26 | 148 | 32 | 66 | 49 | 17 | 5209.5 |
| 10/27/2000 | 2000 | 10 | 27 | 149 | 38 | 61 | 49.5 | 17.5 | 5227 |
| 10/28/2000 | 2000 | 10 | 28 | 150 | 37 | 50 | 43.5 | 11.5 | 5238.5 |
| 10/29/2000 | 2000 | 10 | 29 | 151 | 29 | 59 | 44 | 12 | 5250.5 |
| 10/30/2000 | 2000 | 10 | 30 | 152 | 34 | 66 | 50 | 18 | 5268.5 |
| 10/31/2000 | 2000 | 10 | 31 | 153 | 58 | 59 | 58.5 | 26.5 | 5295 |
| 11/1/2000 | 2000 | 11 | 1 | 154 | 21 | 50 | 35.5 | 3.5 | 5298.5 |
| 11/2/2000 | 2000 | 11 | 2 | 155 | 33 | 57 | 45 | 13 | 5311.5 |
| 11/3/2000 | 2000 | 11 | 3 | 156 | 34 | 45 | 39.5 | 7.5 | 5319 |
| 11/4/2000 | 2000 | 11 | 4 | 157 | 35 | 47 | 41 | 9 | 5328 |
| 11/5/2000 | 2000 | 11 | 5 | 158 | 28 | 47 | 37.5 | 5.5 | 5333.5 |
| 11/6/2000 | 2000 | 11 | 6 | 159 | 24 | 43 | 33.5 | 1.5 | 5335 |
| 11/7/2000 | 2000 | 11 | 7 | 160 | 7 | 35 | 21 | -11 | 5324 |
| 11/8/2000 | 2000 | 11 | 8 | 161 | 18 | 47 | 32.5 | 0.5 | 5324.5 |
| 11/9/2000 | 2000 | 11 | 9 | 162 | 23 | 58 | 40.5 | 8.5 | 5333 |
| 11/10/2000 | 2000 | 11 | 10 | 163 | 33 | 43 | 38 | 6 | 5339 |
| 11/11/2000 | 2000 | 11 | 11 | 164 | 34 | 43 | 38.5 | 6.5 | 5345.5 |
| 11/12/2000 | 2000 | 11 | 12 | 165 | 10 | 41 | 25.5 | -6.5 | 5339 |
| 11/13/2000 | 2000 | 11 | 13 | 166 | 13 | 46 | 29.5 | -2.5 | 5336.5 |
| 11/14/2000 | 2000 | 11 | 14 | 167 | 23 | 51 | 37 | 5 | 5341.5 |
| 11/15/2000 | 2000 | 11 | 15 | 168 | 10 | 48 | 29 | -3 | 5338.5 |
| 11/16/2000 | 2000 | 11 | 16 | 169 | 10 | 47 | 28.5 | -3.5 | 5335 |
| 11/17/2000 | 2000 | 11 | 17 | 170 | 11 | 45 | 28 | -4 | 5331 |
| 11/18/2000 | 2000 | 11 | 18 | 171 | 10 | 39 | 24.5 | -7.5 | 5323.5 |
| 11/19/2000 | 2000 | 11 | 19 | 172 | 12 | 50 | 31 | -1 | 5322.5 |
| 11/20/2000 | 2000 | 11 | 20 | 173 | 14 | 61 | 37.5 | 5.5 | 5328 |
| 11/21/2000 | 2000 | 11 | 21 | 174 | 27 | 56 | 41.5 | 9.5 | 5337.5 |
| 11/22/2000 | 2000 | 11 | 22 | 175 | 30 | 60 | 45 | 13 | 5350.5 |
| 11/23/2000 | 2000 | 11 | 23 | 176 | 18 | 39 | 28.5 | -3.5 | 5347 |
| 11/24/2000 | 2000 | 11 | 24 | 177 | 18 | 39 | 28.5 | -3.5 | 5343.5 |
| 11/25/2000 | 2000 | 11 | 25 | 178 | 14 | 44 | 29 | -3 | 5340.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/26/2000 | 2000 | 11 | 26 | 179 | 16 | 55 | 35.5 | 3.5 | 5344 |
| 11/27/2000 | 2000 | 11 | 27 | 180 | 23 | 53 | 38 | 6 | 5350 |
| 11/28/2000 | 2000 | 11 | 28 | 181 | 20 | 58 | 39 | 7 | 5357 |
| 11/29/2000 | 2000 | 11 | 29 | 182 | 23 | 61 | 42 | 10 | 5367 |
| 11/30/2000 | 2000 | 11 | 30 | 183 | 19 | 61 | 40 | 8 | 5375 |
| 12/1/2000 | 2000 | 12 | 1 | 184 | 31 | 53 | 42 | 10 | 5385 |
| 12/2/2000 | 2000 | 12 | 2 | 185 | 20 | 42 | 31 | -1 | 5384 |
| 12/3/2000 | 2000 | 12 | 3 | 186 | 17 | 55 | 36 | 4 | 5388 |
| 12/4/2000 | 2000 | 12 | 4 | 187 | 17 | 61 | 39 | 7 | 5395 |
| 12/5/2000 | 2000 | 12 | 5 | 188 | 17 | 57 | 37 | 5 | 5400 |
| 12/6/2000 | 2000 | 12 | 6 | 189 | 19 | 56 | 37.5 | 5.5 | 5405.5 |
| 12/7/2000 | 2000 | 12 | 7 | 190 | 22 | 63 | 42.5 | 10.5 | 5416 |
| 12/8/2000 | 2000 | 12 | 8 | 191 | 27 | 56 | 41.5 | 9.5 | 5425.5 |
| 12/9/2000 | 2000 | 12 | 9 | 192 | 24 | 54 | 39 | 7 | 5432.5 |
| 12/10/2000 | 2000 | 12 | 10 | 193 | 27 | 42 | 34.5 | 2.5 | 5435 |
| 12/11/2000 | 2000 | 12 | 11 | 194 | 15 | 55 | 35 | 3 | 5438 |
| 12/12/2000 | 2000 | 12 | 12 | 195 | 31 | 51 | 41 | 9 | 5447 |
| 12/13/2000 | 2000 | 12 | 13 | 196 | 15 | 52 | 33.5 | 1.5 | 5448.5 |
| 12/14/2000 | 2000 | 12 | 14 | 197 | 20 | 56 | 38 | 6 | 5454.5 |
| 12/15/2000 | 2000 | 12 | 15 | 198 | 20 | 53 | 36.5 | 4.5 | 5459 |
| 12/16/2000 | 2000 | 12 | 16 | 199 | 12 | 65 | 38.5 | 6.5 | 5465.5 |
| 12/17/2000 | 2000 | 12 | 17 | 200 | 9 | 58 | 33.5 | 1.5 | 5467 |
| 12/18/2000 | 2000 | 12 | 18 | 201 | 5 | 39 | 22 | -10 | 5457 |
| 12/19/2000 | 2000 | 12 | 19 | 202 | 23 | 55 | 39 | 7 | 5464 |
| 12/20/2000 | 2000 | 12 | 20 | 203 | 10 | 51 | 30.5 | -1.5 | 5462.5 |
| 12/21/2000 | 2000 | 12 | 21 | 204 | 11 | 57 | 34 | 2 | 5464.5 |
| 12/22/2000 | 2000 | 12 | 22 | 205 | 10 | 63 | 36.5 | 4.5 | 5469 |
| 12/23/2000 | 2000 | 12 | 23 | 206 | 10 | 58 | 34 | 2 | 5471 |
| 12/24/2000 | 2000 | 12 | 24 | 207 | 25 | 61 | 43 | 11 | 5482 |
| 12/25/2000 | 2000 | 12 | 25 | 208 | 21 | 42 | 31.5 | -0.5 | 5481.5 |
| 12/26/2000 | 2000 | 12 | 26 | 209 | 0 | 32 | 16 | -16 | 5465.5 |
| 12/27/2000 | 2000 | 12 | 27 | 210 | -1 | 36 | 17.5 | -14.5 | 5451 |
| 12/28/2000 | 2000 | 12 | 28 | 211 | -1 | 48 | 23.5 | -8.5 | 5442.5 |
| 12/29/2000 | 2000 | 12 | 29 | 212 | 5 | 46 | 25.5 | -6.5 | 5436 |
| 12/30/2000 | 2000 | 12 | 30 | 213 | 13 | 50 | 31.5 | -0.5 | 5435.5 |
| 12/31/2000 | 2000 | 12 | 31 | 214 | 10 | 50 | 30 | -2 | 5433.5 |
| 1/1/2001 | 2001 | 1 | 1 | 215 | 10 | 37 | 23.5 | -8.5 | 5425 |
| 1/2/2001 | 2001 | 1 | 2 | 216 | 11 | 38 | 24.5 | -7.5 | 5417.5 |
| 1/3/2001 | 2001 | 1 | 3 | 217 | 12 | 39 | 25.5 | -6.5 | 5411 |
| 1/4/2001 | 2001 | 1 | 4 | 218 | 9 | 36 | 22.5 | -9.5 | 5401.5 |
| 1/5/2001 | 2001 | 1 | 5 | 219 | 15 | 56 | 35.5 | 3.5 | 5405 |
| 1/6/2001 | 2001 | 1 | 6 | 220 | 13 | 62 | 37.5 | 5.5 | 5410.5 |
| 1/7/2001 | 2001 | 1 | 7 | 221 | 6 | 53 | 29.5 | -2.5 | 5408 |
| 1/8/2001 | 2001 | 1 | 8 | 222 | 24 | 48 | 36 | 4 | 5412 |
| 1/9/2001 | 2001 | 1 | 9 | 223 | 28 | 36 | 32 | 0 | 5412 |
| 1/10/2001 | 2001 | 1 | 10 | 224 | 16 | 46 | 31 | -1 | 5411 |
| 1/11/2001 | 2001 | 1 | 11 | 225 | 21 | 47 | 34 | 2 | 5413 |
| 1/12/2001 | 2001 | 1 | 12 | 226 | 54 | 55 | 54.5 | 22.5 | 5435.5 |
| 1/13/2001 | 2001 | 1 | 13 | 227 | 10 | 48 | 29 | -3 | 5432.5 |
| 1/14/2001 | 2001 | 1 | 14 | 228 | 15 | 41 | 28 | -4 | 5428.5 |
| 1/15/2001 | 2001 | 1 | 15 | 229 | 15 | 36 | 25.5 | -6.5 | 5422 |
| 1/16/2001 | 2001 | 1 | 16 | 230 | -2 | 33 | 15.5 | -16.5 | 5405.5 |
| 1/17/2001 | 2001 | 1 | 17 | 231 | -8 | 36 | 14 | -18 | 5387.5 |
| 1/18/2001 | 2001 | 1 | 18 | 232 | 5 | 38 | 21.5 | -10.5 | 5377 |
| 1/19/2001 | 2001 | 1 | 19 | 233 | 2 | 38 | 20 | -12 | 5365 |
| 1/20/2001 | 2001 | 1 | 20 | 234 | 8 | 45 | 26.5 | -5.5 | 5359.5 |
| 1/21/2001 | 2001 | 1 | 21 | 235 | 23 | 36 | 29.5 | -2.5 | 5357 |
| 1/22/2001 | 2001 | 1 | 22 | 236 | 17 | 44 | 30.5 | -1.5 | 5355.5 |
| 1/23/2001 | 2001 | 1 | 23 | 237 | 23 | 43 | 33 | 1 | 5356.5 |
| 1/24/2001 | 2001 | 1 | 24 | 238 | 8 | 44 | 26 | -6 | 5350.5 |
| 1/25/2001 | 2001 | 1 | 25 | 239 | 8 | 44 | 26 | -6 | 5344.5 |
| 1/26/2001 | 2001 | 1 | 26 | 240 | 27 | 44 | 35.5 | 3.5 | 5348 |
| 1/27/2001 | 2001 | 1 | 27 | 241 | 14 | 32 | 23 | -9 | 5339 |
| 1/28/2001 | 2001 | 1 | 28 | 242 | 16 | 30 | 23 | -9 | 5330 |
| 1/29/2001 | 2001 | 1 | 29 | 243 | 21 | 45 | 33 | 1 | 5331 |
| 1/30/2001 | 2001 | 1 | 30 | 244 | -5 | 30 | 12.5 | -19.5 | 5311.5 |
| 1/31/2001 | 2001 | 1 | 31 | 245 | -5 | 32 | 13.5 | -18.5 | 5293 |
| 2/1/2001 | 2001 | 2 | 1 | 246 | 0 | 28 | 14 | -18 | 5275 |
| 2/2/2001 | 2001 | 2 | 2 | 247 | 10 | 50 | 30 | -2 | 5273 |
| 2/3/2001 | 2001 | 2 | 3 | 248 | 20 | 51 | 35.5 | 3.5 | 5276.5 |
| 2/4/2001 | 2001 | 2 | 4 | 249 | 21 | 53 | 37 | 5 | 5281.5 |
| 2/5/2001 | 2001 | 2 | 5 | 250 | 25 | 63 | 44 | 12 | 5293.5 |
| 2/6/2001 | 2001 | 2 | 6 | 251 | 33 | 64 | 48.5 | 16.5 | 5310 |
| 2/7/2001 | 2001 | 2 | 7 | 252 | 31 | 57 | 44 | 12 | 5322 |
| 2/8/2001 | 2001 | 2 | 8 | 253 | 12 | 39 | 25.5 | -6.5 | 5315.5 |
| 2/9/2001 | 2001 | 2 | 9 | 254 | 16 | 50 | 33 | 1 | 5316.5 |
| 2/10/2001 | 2001 | 2 | 10 | 255 | 25 | 52 | 38.5 | 6.5 | 5323 |
| 2/11/2001 | 2001 | 2 | 11 | 256 | 23 | 54 | 38.5 | 6.5 | 5329.5 |
| 2/12/2001 | 2001 | 2 | 12 | 257 | 32 | 60 | 46 | 14 | 5343.5 |
| 2/13/2001 | 2001 | 2 | 13 | 258 | 29 | 59 | 44 | 12 | 5355.5 |
| 2/14/2001 | 2001 | 2 | 14 | 259 | 18 | 37 | 27.5 | -4.5 | 5351 |
| 2/15/2001 | 2001 | 2 | 15 | 260 | 17 | 45 | 31 | -1 | 5350 |
| 2/16/2001 | 2001 | 2 | 16 | 261 | 16 | 47 | 31.5 | -0.5 | 5349.5 |
| 2/17/2001 | 2001 | 2 | 17 | 262 | 30 | 55 | 42.5 | 10.5 | 5360 |
| 2/18/2001 | 2001 | 2 | 18 | 263 | 22 | 63 | 42.5 | 10.5 | 5370.5 |
| 2/19/2001 | 2001 | 2 | 19 | 264 | 20 | 60 | 40 | 8 | 5378.5 |
| 2/20/2001 | 2001 | 2 | 20 | 265 | 24 | 63 | 43.5 | 11.5 | 5390 |
| 2/21/2001 | 2001 | 2 | 21 | 266 | 20 | 62 | 41 | 9 | 5399 |
| 2/22/2001 | 2001 | 2 | 22 | 267 | 21 | 65 | 43 | 11 | 5410 |
| 2/23/2001 | 2001 | 2 | 23 | 268 | 22 | 54 | 38 | 6 | 5416 |
| 2/24/2001 | 2001 | 2 | 24 | 269 | 30 | 49 | 39.5 | 7.5 | 5423.5 |
| 2/25/2001 | 2001 | 2 | 25 | 270 | 29 | 53 | 41 | 9 | 5432.5 |
| 2/26/2001 | 2001 | 2 | 26 | 271 | 27 | 47 | 37 | 5 | 5437.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/27/2001 | 2001 | 2 | 27 | 272 | 33 | 50 | 41.5 | 9.5 | 5447 |
| 2/28/2001 | 2001 | 2 | 28 | 273 | 23 | 48 | 35.5 | 3.5 | 5450.5 |
| 3/1/2001 | 2001 | 3 | 1 | 274 | 20 | 52 | 36 | 4 | 5454.5 |
| 3/2/2001 | 2001 | 3 | 2 | 275 | 22 | 55 | 38.5 | 6.5 | 5461 |
| 3/3/2001 | 2001 | 3 | 3 | 276 | 18 | 48 | 33 | 1 | 5462 |
| 3/4/2001 | 2001 | 3 | 4 | 277 | 31 | 58 | 44.5 | 12.5 | 5474.5 |
| 3/5/2001 | 2001 | 3 | 5 | 278 | 34 | 62 | 48 | 16 | 5490.5 |
| 3/6/2001 | 2001 | 3 | 6 | 279 | 27 | 64 | 45.5 | 13.5 | 5504 |
| 3/7/2001 | 2001 | 3 | 7 | 280 | 35 | 57 | 46 | 14 | 5518 |
| 3/8/2001 | 2001 | 3 | 8 | 281 | 24 | 55 | 39.5 | 7.5 | 5525.5 |
| 3/9/2001 | 2001 | 3 | 9 | 282 | 27 | 51 | 39 | 7 | 5532.5 |
| 3/10/2001 | 2001 | 3 | 10 | 283 | 32 | 44 | 38 | 6 | 5538.5 |
| 3/12/2001 | 2001 | 3 | 12 | 284 | 19 | 57 | 38 | 6 | 5544.5 |
| 3/13/2001 | 2001 | 3 | 13 | 285 | 23 | 63 | 43 | 11 | 5555.5 |
| 3/14/2001 | 2001 | 3 | 14 | 286 | 20 | 64 | 42 | 10 | 5565.5 |
| 3/15/2001 | 2001 | 3 | 15 | 287 | 17 | 53 | 35 | 3 | 5568.5 |
| 3/16/2001 | 2001 | 3 | 16 | 288 | 18 | 63 | 40.5 | 8.5 | 5577 |
| 3/17/2001 | 2001 | 3 | 17 | 289 | 19 | 51 | 35 | 3 | 5580 |
| 3/18/2001 | 2001 | 3 | 18 | 290 | 21 | 58 | 39.5 | 7.5 | 5587.5 |
| 3/19/2001 | 2001 | 3 | 19 | 291 | 23 | 66 | 44.5 | 12.5 | 5600 |
| 3/20/2001 | 2001 | 3 | 20 | 292 | 26 | 75 | 50.5 | 18.5 | 5618.5 |
| 3/21/2001 | 2001 | 3 | 21 | 293 | 31 | 75 | 53 | 21 | 5639.5 |
| 3/22/2001 | 2001 | 3 | 22 | 294 | 31 | 74 | 52.5 | 20.5 | 5660 |
| 3/23/2001 | 2001 | 3 | 23 | 295 | 27 | 70 | 48.5 | 16.5 | 5676.5 |
| 3/24/2001 | 2001 | 3 | 24 | 296 | 30 | 65 | 47.5 | 15.5 | 5692 |
| 3/25/2001 | 2001 | 3 | 25 | 297 | 36 | 76 | 56 | 24 | 5716 |
| 3/26/2001 | 2001 | 3 | 26 | 298 | 30 | 67 | 48.5 | 16.5 | 5732.5 |
| 3/27/2001 | 2001 | 3 | 27 | 299 | 22 | 65 | 43.5 | 11.5 | 5744 |
| 3/28/2001 | 2001 | 3 | 28 | 300 | 24 | 64 | 44 | 12 | 5756 |
| 3/29/2001 | 2001 | 3 | 29 | 301 | 53 | 59 | 56 | 24 | 5780 |
| 3/30/2001 | 2001 | 3 | 30 | 302 | 23 | 67 | 45 | 13 | 5793 |
| 3/31/2001 | 2001 | 3 | 31 | 303 | 27 | 76 | 51.5 | 19.5 | 5812.5 |
| 4/1/2001 | 2001 | 4 | 1 | 304 | 30 | 77 | 53.5 | 21.5 | 5834 |
| 4/2/2001 | 2001 | 4 | 2 | 305 | 32 | 72 | 52 | 20 | 5854 |
| 4/3/2001 | 2001 | 4 | 3 | 306 | 34 | 75 | 54.5 | 22.5 | 5876.5 |
| 4/4/2001 | 2001 | 4 | 4 | 307 | 39 | 74 | 56.5 | 24.5 | 5901 |
| 4/5/2001 | 2001 | 4 | 5 | 308 | 38 | 64 | 51 | 19 | 5920 |
| 4/6/2001 | 2001 | 4 | 6 | 309 | 32 | 67 | 49.5 | 17.5 | 5937.5 |
| 4/7/2001 | 2001 | 4 | 7 | 310 | 28 | 67 | 47.5 | 15.5 | 5953 |
| 4/8/2001 | 2001 | 4 | 8 | 311 | 23 | 66 | 44.5 | 12.5 | 5965.5 |
| 4/9/2001 | 2001 | 4 | 9 | 312 | 30 | 72 | 51 | 19 | 5984.5 |
| 4/10/2001 | 2001 | 4 | 10 | 313 | 28 | 71 | 49.5 | 17.5 | 6002 |
| 4/11/2001 | 2001 | 4 | 11 | 314 | 25 | 59 | 42 | 10 | 6012 |
| 4/12/2001 | 2001 | 4 | 12 | 315 | 21 | 57 | 39 | 7 | 6019 |
| 4/13/2001 | 2001 | 4 | 13 | 316 | 27 | 71 | 49 | 17 | 6036 |
| 4/14/2001 | 2001 | 4 | 14 | 317 | 30 | 72 | 51 | 19 | 6055 |
| 4/15/2001 | 2001 | 4 | 15 | 318 | 27 | 78 | 52.5 | 20.5 | 6075.5 |
| 4/16/2001 | 2001 | 4 | 16 | 319 | 42 | 83 | 62.5 | 30.5 | 6106 |
| 4/17/2001 | 2001 | 4 | 17 | 320 | 39 | 73 | 56 | 24 | 6130 |
| 4/18/2001 | 2001 | 4 | 18 | 321 | 41 | 84 | 62.5 | 30.5 | 6160.5 |
| 4/19/2001 | 2001 | 4 | 19 | 322 | 46 | 74 | 60 | 28 | 6188.5 |
| 4/20/2001 | 2001 | 4 | 20 | 323 | 35 | 70 | 52.5 | 20.5 | 6209 |
| 4/21/2001 | 2001 | 4 | 21 | 324 | 31 | 74 | 52.5 | 20.5 | 6229.5 |
| 4/22/2001 | 2001 | 4 | 22 | 325 | 23 | 56 | 39.5 | 7.5 | 6237 |
| 4/23/2001 | 2001 | 4 | 23 | 326 | 27 | 66 | 46.5 | 14.5 | 6251.5 |
| 4/24/2001 | 2001 | 4 | 24 | 327 | 30 | 76 | 53 | 21 | 6272.5 |
| 4/25/2001 | 2001 | 4 | 25 | 328 | 35 | 81 | 58 | 26 | 6298.5 |
| 4/26/2001 | 2001 | 4 | 26 | 329 | 38 | 80 | 59 | 27 | 6325.5 |
| 4/27/2001 | 2001 | 4 | 27 | 330 | 43 | 76 | 59.5 | 27.5 | 6353 |
| 4/28/2001 | 2001 | 4 | 28 | 331 | 38 | 77 | 57.5 | 25.5 | 6378.5 |
| 4/29/2001 | 2001 | 4 | 29 | 332 | 36 | 80 | 58 | 26 | 6404.5 |
| 4/30/2001 | 2001 | 4 | 30 | 333 | 36 | 82 | 59 | 27 | 6431.5 |
| 5/1/2001 | 2001 | 5 | 1 | 334 | 44 | 84 | 64 | 32 | 6463.5 |
| 5/2/2001 | 2001 | 5 | 2 | 335 | 36 | 80 | 58 | 26 | 6489.5 |
| 5/3/2001 | 2001 | 5 | 3 | 336 | 33 | 73 | 53 | 21 | 6510.5 |
| 5/4/2001 | 2001 | 5 | 4 | 337 | 31 | 56 | 43.5 | 11.5 | 6522 |
| 5/5/2001 | 2001 | 5 | 5 | 338 | 40 | 68 | 54 | 22 | 6544 |
| 5/6/2001 | 2001 | 5 | 6 | 339 | 32 | 72 | 52 | 20 | 6564 |
| 5/7/2001 | 2001 | 5 | 7 | 340 | 35 | 81 | 58 | 26 | 6590 |
| 5/8/2001 | 2001 | 5 | 8 | 341 | 42 | 85 | 63.5 | 31.5 | 6621.5 |
| 5/9/2001 | 2001 | 5 | 9 | 342 | 44 | 84 | 64 | 32 | 6653.5 |
| 5/10/2001 | 2001 | 5 | 10 | 343 | 41 | 87 | 64 | 32 | 6685.5 |
| 5/11/2001 | 2001 | 5 | 11 | 344 | 50 | 89 | 69.5 | 37.5 | 6723 |
| 5/12/2001 | 2001 | 5 | 12 | 345 | 47 | 85 | 66 | 34 | 6757 |
| 5/13/2001 | 2001 | 5 | 13 | 346 | 42 | 75 | 58.5 | 26.5 | 6783.5 |
| 5/14/2001 | 2001 | 5 | 14 | 347 | 38 | 73 | 55.5 | 23.5 | 6807 |
| 5/15/2001 | 2001 | 5 | 15 | 348 | 39 | 83 | 61 | 29 | 6836 |
| 5/16/2001 | 2001 | 5 | 16 | 349 | 39 | 83 | 61 | 29 | 6865 |
| 5/17/2001 | 2001 | 5 | 17 | 350 | 52 | 87 | 69.5 | 37.5 | 6902.5 |
| 5/18/2001 | 2001 | 5 | 18 | 351 | 54 | 85 | 69.5 | 37.5 | 6940 |
| 5/19/2001 | 2001 | 5 | 19 | 352 | 45 | 59 | 52 | 20 | 6960 |
| 5/20/2001 | 2001 | 5 | 20 | 353 | 42 | 82 | 62 | 30 | 6990 |
| 5/21/2001 | 2001 | 5 | 21 | 354 | 37 | 77 | 57 | 25 | 7015 |
| 5/22/2001 | 2001 | 5 | 22 | 355 | 39 | 83 | 61 | 29 | 7044 |
| 5/23/2001 | 2001 | 5 | 23 | 356 | 39 | 87 | 63 | 31 | 7075 |
| 5/24/2001 | 2001 | 5 | 24 | 357 | 58 | 90 | 74 | 42 | 7117 |
| 5/25/2001 | 2001 | 5 | 25 | 358 | 54 | 88 | 71 | 39 | 7156 |
| 5/26/2001 | 2001 | 5 | 26 | 359 | 55 | 92 | 73.5 | 41.5 | 7197.5 |
| 5/27/2001 | 2001 | 5 | 27 | 360 | 47 | 90 | 68.5 | 36.5 | 7234 |
| 5/28/2001 | 2001 | 5 | 28 | 361 | 43 | 91 | 67 | 35 | 7269 |
| 5/29/2001 | 2001 | 5 | 29 | 362 | 42 | 85 | 63.5 | 31.5 | 7300.5 |
| 5/30/2001 | 2001 | 5 | 30 | 363 | 39 | 90 | 64.5 | 32.5 | 7333 |
| 5/31/2001 | 2001 | 5 | 31 | 364 | 40 | 91 | 65.5 | 33.5 | 7366.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/1/2001 | 2001 | 6 | 1 | 1 | 50 | 83 | 66.5 | 34.5 | 34.5 |
| 6/2/2001 | 2001 | 6 | 2 | 2 | 58 | 90 | 74 | 42 | 76.5 |
| 6/3/2001 | 2001 | 6 | 3 | 3 | 44 | 85 | 64.5 | 32.5 | 109 |
| 6/4/2001 | 2001 | 6 | 4 | 4 | 48 | 83 | 65.5 | 33.5 | 142.5 |
| 6/5/2001 | 2001 | 6 | 5 | 5 | 43 | 88 | 65.5 | 33.5 | 176 |
| 6/6/2001 | 2001 | 6 | 6 | 6 | 47 | 94 | 70.5 | 38.5 | 214.5 |
| 6/7/2001 | 2001 | 6 | 7 | 7 | 60 | 95 | 77.5 | 45.5 | 260 |
| 6/8/2001 | 2001 | 6 | 8 | 8 | 60 | 93 | 76.5 | 44.5 | 304.5 |
| 6/9/2001 | 2001 | 6 | 9 | 9 | 52 | 95 | 73.5 | 41.5 | 346 |
| 6/10/2001 | 2001 | 6 | 10 | 10 | 50 | 91 | 70.5 | 38.5 | 384.5 |
| 6/11/2001 | 2001 | 6 | 11 | 11 | 50 | 93 | 71.5 | 39.5 | 424 |
| 6/12/2001 | 2001 | 6 | 12 | 12 | 50 | 90 | 70 | 38 | 462 |
| 6/13/2001 | 2001 | 6 | 13 | 13 | 32 | 81 | 56.5 | 24.5 | 486.5 |
| 6/14/2001 | 2001 | 6 | 14 | 14 | 34 | 76 | 55 | 23 | 509.5 |
| 6/15/2001 | 2001 | 6 | 15 | 15 | 38 | 90 | 64 | 32 | 541.5 |
| 6/16/2001 | 2001 | 6 | 16 | 16 | 45 | 95 | 70 | 38 | 579.5 |
| 6/17/2001 | 2001 | 6 | 17 | 17 | 50 | 96 | 73 | 41 | 620.5 |
| 6/18/2001 | 2001 | 6 | 18 | 18 | 48 | 90 | 69 | 37 | 657.5 |
| 6/19/2001 | 2001 | 6 | 19 | 19 | 58 | 97 | 77.5 | 45.5 | 703 |
| 6/20/2001 | 2001 | 6 | 20 | 20 | 50 | 92 | 71 | 39 | 742 |
| 6/21/2001 | 2001 | 6 | 21 | 21 | 60 | 96 | 78 | 46 | 788 |
| 6/22/2001 | 2001 | 6 | 22 | 22 | 59 | 95 | 77 | 45 | 833 |
| 6/23/2001 | 2001 | 6 | 23 | 23 | 55 | 93 | 74 | 42 | 875 |
| 6/24/2001 | 2001 | 6 | 24 | 24 | 54 | 88 | 71 | 39 | 914 |
| 6/25/2001 | 2001 | 6 | 25 | 25 | 55 | 90 | 72.5 | 40.5 | 954.5 |
| 6/26/2001 | 2001 | 6 | 26 | 26 | 48 | 77 | 62.5 | 30.5 | 985 |
| 6/27/2001 | 2001 | 6 | 27 | 27 | 49 | 90 | 69.5 | 37.5 | 1022.5 |
| 6/28/2001 | 2001 | 6 | 28 | 28 | 56 | 94 | 75 | 43 | 1065.5 |
| 6/29/2001 | 2001 | 6 | 29 | 29 | 58 | 92 | 75 | 43 | 1108.5 |
| 6/30/2001 | 2001 | 6 | 30 | 30 | 58 | 98 | 78 | 46 | 1154.5 |
| 7/1/2001 | 2001 | 7 | 1 | 31 | 53 | 98 | 75.5 | 43.5 | 1198 |
| 7/2/2001 | 2001 | 7 | 2 | 32 | 55 | 96 | 75.5 | 43.5 | 1241.5 |
| 7/3/2001 | 2001 | 7 | 3 | 33 | 59 | 92 | 75.5 | 43.5 | 1285 |
| 7/4/2001 | 2001 | 7 | 4 | 34 | 55 | 92 | 73.5 | 41.5 | 1326.5 |
| 7/5/2001 | 2001 | 7 | 5 | 35 | 53 | 94 | 73.5 | 41.5 | 1368 |
| 7/6/2001 | 2001 | 7 | 6 | 36 | 58 | 97 | 77.5 | 45.5 | 1413.5 |
| 7/7/2001 | 2001 | 7 | 7 | 37 | 58 | 97 | 77.5 | 45.5 | 1459 |
| 7/8/2001 | 2001 | 7 | 8 | 38 | 56 | 98 | 77 | 45 | 1504 |
| 7/9/2001 | 2001 | 7 | 9 | 39 | 55 | 98 | 76.5 | 44.5 | 1548.5 |
| 7/10/2001 | 2001 | 7 | 10 | 40 | 55 | 93 | 74 | 42 | 1590.5 |
| 7/11/2001 | 2001 | 7 | 11 | 41 | 55 | 88 | 71.5 | 39.5 | 1630 |
| 7/12/2001 | 2001 | 7 | 12 | 42 | 57 | 90 | 73.5 | 41.5 | 1671.5 |
| 7/13/2001 | 2001 | 7 | 13 | 43 | 57 | 94 | 75.5 | 43.5 | 1715 |
| 7/14/2001 | 2001 | 7 | 14 | 44 | 56 | 88 | 72 | 40 | 1755 |
| 7/15/2001 | 2001 | 7 | 15 | 45 | 54 | 86 | 70 | 38 | 1793 |
| 7/16/2001 | 2001 | 7 | 16 | 46 | 64 | 91 | 77.5 | 45.5 | 1838.5 |
| 7/17/2001 | 2001 | 7 | 17 | 47 | 53 | 78 | 65.5 | 33.5 | 1872 |
| 7/18/2001 | 2001 | 7 | 18 | 48 | 55 | 89 | 72 | 40 | 1912 |
| 7/19/2001 | 2001 | 7 | 19 | 49 | 60 | 90 | 75 | 43 | 1955 |
| 7/20/2001 | 2001 | 7 | 20 | 50 | 60 | 91 | 75.5 | 43.5 | 1998.5 |
| 7/21/2001 | 2001 | 7 | 21 | 51 | 67 | 89 | 78 | 46 | 2044.5 |
| 7/22/2001 | 2001 | 7 | 22 | 52 | 60 | 91 | 75.5 | 43.5 | 2088 |
| 7/23/2001 | 2001 | 7 | 23 | 53 | 61 | 97 | 79 | 47 | 2135 |
| 7/24/2001 | 2001 | 7 | 24 | 54 | 56 | 88 | 72 | 40 | 2175 |
| 7/25/2001 | 2001 | 7 | 25 | 55 | 59 | 88 | 73.5 | 41.5 | 2216.5 |
| 7/26/2001 | 2001 | 7 | 26 | 56 | 57 | 87 | 72 | 40 | 2256.5 |
| 7/27/2001 | 2001 | 7 | 27 | 57 | 58 | 90 | 74 | 42 | 2298.5 |
| 7/28/2001 | 2001 | 7 | 28 | 58 | 60 | 94 | 77 | 45 | 2343.5 |
| 7/29/2001 | 2001 | 7 | 29 | 59 | 60 | 94 | 77 | 45 | 2388.5 |
| 7/30/2001 | 2001 | 7 | 30 | 60 | 58 | 85 | 71.5 | 39.5 | 2428 |
| 7/31/2001 | 2001 | 7 | 31 | 61 | 61 | 90 | 75.5 | 43.5 | 2471.5 |
| 8/1/2001 | 2001 | 8 | 1 | 62 | 57 | 89 | 73 | 41 | 2512.5 |
| 8/2/2001 | 2001 | 8 | 2 | 63 | 58 | 84 | 71 | 39 | 2551.5 |
| 8/3/2001 | 2001 | 8 | 3 | 64 | 59 | 88 | 73.5 | 41.5 | 2593 |
| 8/4/2001 | 2001 | 8 | 4 | 65 | 56 | 91 | 73.5 | 41.5 | 2634.5 |
| 8/5/2001 | 2001 | 8 | 5 | 66 | 59 | 93 | 76 | 44 | 2678.5 |
| 8/6/2001 | 2001 | 8 | 6 | 67 | 67 | 95 | 81 | 49 | 2727.5 |
| 8/7/2001 | 2001 | 8 | 7 | 68 | 61 | 91 | 76 | 44 | 2771.5 |
| 8/8/2001 | 2001 | 8 | 8 | 69 | 54 | 75 | 64.5 | 32.5 | 2804 |
| 8/9/2001 | 2001 | 8 | 9 | 70 | 54 | 87 | 70.5 | 38.5 | 2842.5 |
| 8/10/2001 | 2001 | 8 | 10 | 71 | 61 | 90 | 75.5 | 43.5 | 2886 |
| 8/11/2001 | 2001 | 8 | 11 | 72 | 62 | 86 | 74 | 42 | 2928 |
| 8/12/2001 | 2001 | 8 | 12 | 73 | 59 | 74 | 66.5 | 34.5 | 2962.5 |
| 8/13/2001 | 2001 | 8 | 13 | 74 | 58 | 83 | 70.5 | 38.5 | 3001 |
| 8/14/2001 | 2001 | 8 | 14 | 75 | 51 | 83 | 67 | 35 | 3036 |
| 8/15/2001 | 2001 | 8 | 15 | 76 | 58 | 88 | 73 | 41 | 3077 |
| 8/16/2001 | 2001 | 8 | 16 | 77 | 52 | 91 | 71.5 | 39.5 | 3116.5 |
| 8/17/2001 | 2001 | 8 | 17 | 78 | 50 | 90 | 70 | 38 | 3154.5 |
| 8/18/2001 | 2001 | 8 | 18 | 79 | 50 | 92 | 71 | 39 | 3193.5 |
| 8/19/2001 | 2001 | 8 | 19 | 80 | 55 | 90 | 72.5 | 40.5 | 3234 |
| 8/20/2001 | 2001 | 8 | 20 | 81 | 55 | 91 | 73 | 41 | 3275 |
| 8/21/2001 | 2001 | 8 | 21 | 82 | 50 | 82 | 66 | 34 | 3309 |
| 8/22/2001 | 2001 | 8 | 22 | 83 | 48 | 87 | 67.5 | 35.5 | 3344.5 |
| 8/23/2001 | 2001 | 8 | 23 | 84 | 48 | 90 | 69 | 37 | 3381.5 |
| 8/24/2001 | 2001 | 8 | 24 | 85 | 52 | 94 | 73 | 41 | 3422.5 |
| 8/25/2001 | 2001 | 8 | 25 | 86 | 54 | 94 | 74 | 42 | 3464.5 |
| 8/26/2001 | 2001 | 8 | 26 | 87 | 58 | 94 | 76 | 44 | 3508.5 |
| 8/27/2001 | 2001 | 8 | 27 | 88 | 64 | 98 | 81 | 49 | 3557.5 |
| 8/28/2001 | 2001 | 8 | 28 | 89 | 47 | 90 | 68.5 | 36.5 | 3594 |
| 8/29/2001 | 2001 | 8 | 29 | 90 | 49 | 87 | 68 | 36 | 3630 |
| 8/30/2001 | 2001 | 8 | 30 | 91 | 48 | 84 | 66 | 34 | 3664 |
| 8/31/2001 | 2001 | 8 | 31 | 92 | 45 | 80 | 62.5 | 30.5 | 3694.5 |
| 9/1/2001 | 2001 | 9 | 1 | 93 | 46 | 84 | 65 | 33 | 3727.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/2/2001 | 2001 | 9 | 2 | 94 | 46 | 84 | 65 | 33 | 3760.5 |
| 9/3/2001 | 2001 | 9 | 3 | 95 | 44 | 93 | 68.5 | 36.5 | 3797 |
| 9/4/2001 | 2001 | 9 | 4 | 96 | 50 | 91 | 70.5 | 38.5 | 3835.5 |
| 9/5/2001 | 2001 | 9 | 5 | 97 | 51 | 91 | 71 | 39 | 3874.5 |
| 9/6/2001 | 2001 | 9 | 6 | 98 | 47 | 87 | 67 | 35 | 3909.5 |
| 9/7/2001 | 2001 | 9 | 7 | 99 | 47 | 84 | 65.5 | 33.5 | 3943 |
| 9/8/2001 | 2001 | 9 | 8 | 100 | 32 | 81 | 56.5 | 24.5 | 3967.5 |
| 9/9/2001 | 2001 | 9 | 9 | 101 | 31 | 85 | 58 | 26 | 3993.5 |
| 9/10/2001 | 2001 | 9 | 10 | 102 | 44 | 87 | 65.5 | 33.5 | 4027 |
| 9/11/2001 | 2001 | 9 | 11 | 103 | 44 | 87 | 65.5 | 33.5 | 4060.5 |
| 9/12/2001 | 2001 | 9 | 12 | 104 | 57 | 86 | 71.5 | 39.5 | 4100 |
| 9/13/2001 | 2001 | 9 | 13 | 105 | 57 | 86 | 71.5 | 39.5 | 4139.5 |
| 9/14/2001 | 2001 | 9 | 14 | 106 | 50 | 87 | 68.5 | 36.5 | 4176 |
| 9/15/2001 | 2001 | 9 | 15 | 107 | 50 | 83 | 66.5 | 34.5 | 4210.5 |
| 9/16/2001 | 2001 | 9 | 16 | 108 | 52 | 81 | 66.5 | 34.5 | 4245 |
| 9/17/2001 | 2001 | 9 | 17 | 109 | 47 | 82 | 64.5 | 32.5 | 4277.5 |
| 9/18/2001 | 2001 | 9 | 18 | 110 | 41 | 81 | 61 | 29 | 4306.5 |
| 9/19/2001 | 2001 | 9 | 19 | 111 | 41 | 82 | 61.5 | 29.5 | 4336 |
| 9/20/2001 | 2001 | 9 | 20 | 112 | 42 | 84 | 63 | 31 | 4367 |
| 9/21/2001 | 2001 | 9 | 21 | 113 | 42 | 87 | 64.5 | 32.5 | 4399.5 |
| 9/22/2001 | 2001 | 9 | 22 | 114 | 43 | 87 | 65 | 33 | 4432.5 |
| 9/23/2001 | 2001 | 9 | 23 | 115 | 43 | 87 | 65 | 33 | 4465.5 |
| 9/24/2001 | 2001 | 9 | 24 | 116 | 42 | 87 | 64.5 | 32.5 | 4498 |
| 9/25/2001 | 2001 | 9 | 25 | 117 | 43 | 91 | 67 | 35 | 4533 |
| 9/26/2001 | 2001 | 9 | 26 | 118 | 40 | 90 | 65 | 33 | 4566 |
| 9/27/2001 | 2001 | 9 | 27 | 119 | 43 | 91 | 67 | 35 | 4601 |
| 9/28/2001 | 2001 | 9 | 28 | 120 | 43 | 91 | 67 | 35 | 4636 |
| 9/29/2001 | 2001 | 9 | 29 | 121 | 41 | 87 | 64 | 32 | 4668 |
| 9/30/2001 | 2001 | 9 | 30 | 122 | 44 | 86 | 65 | 33 | 4701 |
| 10/1/2001 | 2001 | 10 | 1 | 123 | 35 | 79 | 52.75 | 20.75 | 4721.75 |
| 10/2/2001 | 2001 | 10 | 2 | 124 | 43 | 82 | 62.5 | 30.5 | 4752.25 |
| 10/3/2001 | 2001 | 10 | 3 | 125 | 38 | 80 | 59 | 27 | 4779.25 |
| 10/4/2001 | 2001 | 10 | 4 | 126 | 38 | 83 | 60.5 | 28.5 | 4807.75 |
| 10/5/2001 | 2001 | 10 | 5 | 127 | 42 | 82 | 62 | 30 | 4837.75 |
| 10/6/2001 | 2001 | 10 | 6 | 128 | 48 | 79 | 63.5 | 31.5 | 4869.25 |
| 10/7/2001 | 2001 | 10 | 7 | 129 | 38 | 75 | 56.5 | 24.5 | 4893.75 |
| 10/8/2001 | 2001 | 10 | 8 | 130 | 47 | 74 | 60.5 | 28.5 | 4922.25 |
| 10/9/2001 | 2001 | 10 | 9 | 131 | 45 | 70 | 57.5 | 25.5 | 4947.75 |
| 10/10/2001 | 2001 | 10 | 10 | 132 | 21 | 69 | 45 | 13 | 4960.75 |
| 10/11/2001 | 2001 | 10 | 11 | 133 | 29 | 74 | 51.5 | 19.5 | 4980.25 |
| 10/12/2001 | 2001 | 10 | 12 | 134 | 30 | 55 | 42.5 | 10.5 | 4990.75 |
| 10/13/2001 | 2001 | 10 | 13 | 135 | 28 | 74 | 51 | 19 | 5009.75 |
| 10/14/2001 | 2001 | 10 | 14 | 136 | 30 | 78 | 54 | 22 | 5031.75 |
| 10/15/2001 | 2001 | 10 | 15 | 137 | 42 | 77 | 59.5 | 27.5 | 5059.25 |
| 10/16/2001 | 2001 | 10 | 16 | 138 | 31 | 80 | 55.5 | 23.5 | 5082.75 |
| 10/17/2001 | 2001 | 10 | 17 | 139 | 35 | 80 | 57.5 | 25.5 | 5108.25 |
| 10/18/2001 | 2001 | 10 | 18 | 140 | 30 | 80 | 55 | 23 | 5131.25 |
| 10/19/2001 | 2001 | 10 | 19 | 141 | 28 | 78 | 53 | 21 | 5152.25 |
| 10/20/2001 | 2001 | 10 | 20 | 142 | 32 | 80 | 56 | 24 | 5176.25 |
| 10/21/2001 | 2001 | 10 | 21 | 143 | 44 | 77 | 60.5 | 28.5 | 5204.75 |
| 10/22/2001 | 2001 | 10 | 22 | 144 | 35 | 73 | 54 | 22 | 5226.75 |
| 10/23/2001 | 2001 | 10 | 23 | 145 | 35 | 74 | 54.5 | 22.5 | 5249.25 |
| 10/24/2001 | 2001 | 10 | 24 | 146 | 25 | 68 | 46.5 | 14.5 | 5263.75 |
| 10/25/2001 | 2001 | 10 | 25 | 147 | 27 | 77 | 52 | 20 | 5283.75 |
| 10/26/2001 | 2001 | 10 | 26 | 148 | 28 | 77 | 52.5 | 20.5 | 5304.25 |
| 10/27/2001 | 2001 | 10 | 27 | 149 | 47 | 76 | 61.5 | 29.5 | 5333.75 |
| 10/28/2001 | 2001 | 10 | 28 | 150 | 33 | 69 | 51 | 19 | 5352.75 |
| 10/29/2001 | 2001 | 10 | 29 | 151 | 34 | 77 | 55.5 | 23.5 | 5376.25 |
| 10/30/2001 | 2001 | 10 | 30 | 152 | 37 | 78 | 57.5 | 25.5 | 5401.75 |
| 10/31/2001 | 2001 | 10 | 31 | 153 | 47 | 76 | 61.5 | 29.5 | 5431.25 |
| 11/1/2001 | 2001 | 11 | 1 | 154 | 28 | 71 | 49.5 | 17.5 | 5448.75 |
| 11/2/2001 | 2001 | 11 | 2 | 155 | 27 | 72 | 49.5 | 17.5 | 5466.25 |
| 11/3/2001 | 2001 | 11 | 3 | 156 | 33 | 74 | 53.5 | 21.5 | 5487.75 |
| 11/4/2001 | 2001 | 11 | 4 | 157 | 40 | 70 | 55 | 23 | 5510.75 |
| 11/5/2001 | 2001 | 11 | 5 | 158 | 33 | 63 | 48 | 16 | 5526.75 |
| 11/6/2001 | 2001 | 11 | 6 | 159 | 29 | 68 | 48.5 | 16.5 | 5543.25 |
| 11/7/2001 | 2001 | 11 | 7 | 160 | 37 | 68 | 52.5 | 20.5 | 5563.75 |
| 11/8/2001 | 2001 | 11 | 8 | 161 | 34 | 57 | 45.5 | 13.5 | 5577.25 |
| 11/9/2001 | 2001 | 11 | 9 | 162 | 27 | 60 | 43.5 | 11.5 | 5588.75 |
| 11/10/2001 | 2001 | 11 | 10 | 163 | 26 | 70 | 48 | 16 | 5604.75 |
| 11/11/2001 | 2001 | 11 | 11 | 164 | 26 | 72 | 49 | 17 | 5621.75 |
| 11/12/2001 | 2001 | 11 | 12 | 165 | 32 | 73 | 52.5 | 20.5 | 5642.25 |
| 11/13/2001 | 2001 | 11 | 13 | 166 | 38 | 64 | 51 | 19 | 5661.25 |
| 11/14/2001 | 2001 | 11 | 14 | 167 | 37 | 50 | 43.5 | 11.5 | 5672.75 |
| 11/15/2001 | 2001 | 11 | 15 | 168 | 37 | 49 | 43 | 11 | 5683.75 |
| 11/16/2001 | 2001 | 11 | 16 | 169 | 27 | 57 | 42 | 10 | 5693.75 |
| 11/17/2001 | 2001 | 11 | 17 | 170 | 26 | 63 | 44.5 | 12.5 | 5706.25 |
| 11/18/2001 | 2001 | 11 | 18 | 171 | 21 | 67 | 44 | 12 | 5718.25 |
| 11/19/2001 | 2001 | 11 | 19 | 172 | 18 | 57 | 37.5 | 5.5 | 5723.75 |
| 11/20/2001 | 2001 | 11 | 20 | 173 | 15 | 65 | 40 | 8 | 5731.75 |
| 11/21/2001 | 2001 | 11 | 21 | 174 | 19 | 63 | 41 | 9 | 5740.75 |
| 11/22/2001 | 2001 | 11 | 22 | 175 | 32 | 60 | 46 | 14 | 5754.75 |
| 11/23/2001 | 2001 | 11 | 23 | 176 | 19 | 45 | 32 | 0 | 5754.75 |
| 11/24/2001 | 2001 | 11 | 24 | 177 | 34 | 53 | 43.5 | 11.5 | 5766.25 |
| 11/25/2001 | 2001 | 11 | 25 | 178 | 20 | 45 | 32.5 | 0.5 | 5766.75 |
| 11/26/2001 | 2001 | 11 | 26 | 179 | 17 | 42 | 29.5 | -2.5 | 5764.25 |
| 11/27/2001 | 2001 | 11 | 27 | 180 | 1 | 33 | 17 | -15 | 5749.25 |
| 11/28/2001 | 2001 | 11 | 28 | 181 | 8 | 35 | 21.5 | -10.5 | 5738.75 |
| 11/29/2001 | 2001 | 11 | 29 | 182 | 21 | 45 | 33 | 1 | 5739.75 |
| 11/30/2001 | 2001 | 11 | 30 | 183 | 17 | 45 | 31 | -1 | 5738.75 |
| 12/1/2001 | 2001 | 12 | 1 | 184 | 20 | 57 | 38.5 | 6.5 | 5745.25 |
| 12/2/2001 | 2001 | 12 | 2 | 185 | 25 | 63 | 44 | 12 | 5757.25 |
| 12/3/2001 | 2001 | 12 | 3 | 186 | 19 | 65 | 42 | 10 | 5767.25 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/4/2001 | 2001 | 12 | 4 | 187 | 20 | 59 | 39.5 | 7.5 | 5774.75 |
| 12/5/2001 | 2001 | 12 | 5 | 188 | 13 | 60 | 36.5 | 4.5 | 5779.25 |
| 12/6/2001 | 2001 | 12 | 6 | 189 | 15 | 53 | 34 | 2 | 5781.25 |
| 12/7/2001 | 2001 | 12 | 7 | 190 | 13 | 48 | 30.5 | -1.5 | 5779.75 |
| 12/8/2001 | 2001 | 12 | 8 | 191 | 5 | 46 | 25.5 | -6.5 | 5773.25 |
| 12/9/2001 | 2001 | 12 | 9 | 192 | 22 | 52 | 37 | 5 | 5778.25 |
| 12/10/2001 | 2001 | 12 | 10 | 193 | 17 | 45 | 31 | -1 | 5777.25 |
| 12/11/2001 | 2001 | 12 | 11 | 194 | 10 | 35 | 22.5 | -9.5 | 5767.75 |
| 12/12/2001 | 2001 | 12 | 12 | 195 | 9 | 38 | 23.5 | -8.5 | 5759.25 |
| 12/13/2001 | 2001 | 12 | 13 | 196 | 8 | 37 | 22.5 | -9.5 | 5749.75 |
| 12/14/2001 | 2001 | 12 | 14 | 197 | 22 | 45 | 33.5 | 1.5 | 5751.25 |
| 12/15/2001 | 2001 | 12 | 15 | 198 | 16 | 40 | 28 | -4 | 5747.25 |
| 12/16/2001 | 2001 | 12 | 16 | 199 | 10 | 38 | 24 | -8 | 5739.25 |
| 12/17/2001 | 2001 | 12 | 17 | 200 | 17 | 55 | 36 | 4 | 5743.25 |
| 12/18/2001 | 2001 | 12 | 18 | 201 | 11 | 50 | 30.5 | -1.5 | 5741.75 |
| 12/19/2001 | 2001 | 12 | 19 | 202 | 12 | 58 | 35 | 3 | 5744.75 |
| 12/20/2001 | 2001 | 12 | 20 | 203 | 32 | 58 | 45 | 13 | 5757.75 |
| 12/21/2001 | 2001 | 12 | 21 | 204 | 26 | 44 | 35 | 3 | 5760.75 |
| 12/22/2001 | 2001 | 12 | 22 | 205 | 11 | 53 | 32 | 0 | 5760.75 |
| 12/23/2001 | 2001 | 12 | 23 | 206 | 19 | 38 | 28.5 | -3.5 | 5757.25 |
| 12/24/2001 | 2001 | 12 | 24 | 207 | 10 | 44 | 27 | -5 | 5752.25 |
| 12/25/2001 | 2001 | 12 | 25 | 208 | 10 | 48 | 29 | -3 | 5749.25 |
| 12/26/2001 | 2001 | 12 | 26 | 209 | 22 | 55 | 38.5 | 6.5 | 5755.75 |
| 12/27/2001 | 2001 | 12 | 27 | 210 | 17 | 50 | 33.5 | 1.5 | 5757.25 |
| 12/28/2001 | 2001 | 12 | 28 | 211 | 25 | 50 | 37.5 | 5.5 | 5762.75 |
| 12/29/2001 | 2001 | 12 | 29 | 212 | 25 | 58 | 41.5 | 9.5 | 5772.25 |
| 12/30/2001 | 2001 | 12 | 30 | 213 | 23 | 50 | 36.5 | 4.5 | 5776.75 |
| 12/31/2001 | 2001 | 12 | 31 | 214 | 30 | 35 | 32.5 | 0.5 | 5777.25 |
| 1/1/2002 | 2002 | 1 | 1 | 215 | 18 | 38 | 28 | -4 | 5773.25 |
| 1/2/2002 | 2002 | 1 | 2 | 216 | 18 | 40 | 29 | -3 | 5770.25 |
| 1/3/2002 | 2002 | 1 | 3 | 217 | 27 | 47 | 37 | 5 | 5775.25 |
| 1/4/2002 | 2002 | 1 | 4 | 218 | 18 | 39 | 28.5 | -3.5 | 5771.75 |
| 1/5/2002 | 2002 | 1 | 5 | 219 | 25 | 50 | 37.5 | 5.5 | 5777.25 |
| 1/6/2002 | 2002 | 1 | 6 | 220 | 25 | 50 | 37.5 | 5.5 | 5782.75 |
| 1/7/2002 | 2002 | 1 | 7 | 221 | 25 | 50 | 37.5 | 5.5 | 5788.25 |
| 1/8/2002 | 2002 | 1 | 8 | 222 | 20 | 63 | 41.5 | 9.5 | 5797.75 |
| 1/9/2002 | 2002 | 1 | 9 | 223 | 29 | 61 | 45 | 13 | 5810.75 |
| 1/10/2002 | 2002 | 1 | 10 | 224 | 12 | 37 | 24.5 | -7.5 | 5803.25 |
| 1/11/2002 | 2002 | 1 | 11 | 225 | 9 | 43 | 26 | -6 | 5797.25 |
| 1/12/2002 | 2002 | 1 | 12 | 226 | 16 | 45 | 30.5 | -1.5 | 5795.75 |
| 1/13/2002 | 2002 | 1 | 13 | 227 | 10 | 56 | 33 | 1 | 5796.75 |
| 1/14/2002 | 2002 | 1 | 14 | 228 | 23 | 53 | 38 | 6 | 5802.75 |
| 1/15/2002 | 2002 | 1 | 15 | 229 | 26 | 54 | 40 | 8 | 5810.75 |
| 1/16/2002 | 2002 | 1 | 16 | 230 | 15 | 53 | 34 | 2 | 5812.75 |
| 1/17/2002 | 2002 | 1 | 17 | 231 | 14 | 48 | 31 | -1 | 5811.75 |
| 1/18/2002 | 2002 | 1 | 18 | 232 | 6 | 42 | 24 | -8 | 5803.75 |
| 1/19/2002 | 2002 | 1 | 19 | 233 | 18 | 42 | 30 | -2 | 5801.75 |
| 1/20/2002 | 2002 | 1 | 20 | 234 | 11 | 41 | 26 | -6 | 5795.75 |
| 1/21/2002 | 2002 | 1 | 21 | 235 | 17 | 56 | 36.5 | 4.5 | 5800.25 |
| 1/22/2002 | 2002 | 1 | 22 | 236 | 25 | 54 | 39.5 | 7.5 | 5807.75 |
| 1/23/2002 | 2002 | 1 | 23 | 237 | 5 | 43 | 24 | -8 | 5799.75 |
| 1/24/2002 | 2002 | 1 | 24 | 238 | 9 | 35 | 22 | -10 | 5789.75 |
| 1/25/2002 | 2002 | 1 | 25 | 239 | 12 | 53 | 32.5 | 0.5 | 5790.25 |
| 1/26/2002 | 2002 | 1 | 26 | 240 | 22 | 65 | 43.5 | 11.5 | 5801.75 |
| 1/27/2002 | 2002 | 1 | 27 | 241 | 23 | 61 | 42 | 10 | 5811.75 |
| 1/28/2002 | 2002 | 1 | 28 | 242 | 28 | 55 | 41.5 | 9.5 | 5821.25 |
| 1/29/2002 | 2002 | 1 | 29 | 243 | 19 | 53 | 36 | 4 | 5825.25 |
| 1/30/2002 | 2002 | 1 | 30 | 244 | 2 | 35 | 18.5 | -13.5 | 5811.75 |
| 1/31/2002 | 2002 | 1 | 31 | 245 | -3 | 25 | 11 | -21 | 5790.75 |
| 2/1/2002 | 2002 | 2 | 1 | 246 | 16 | 39 | 27.5 | -4.5 | 5786.25 |
| 2/2/2002 | 2002 | 2 | 2 | 247 | 10 | 40 | 25 | -7 | 5779.25 |
| 2/3/2002 | 2002 | 2 | 3 | 248 | 12 | 48 | 30 | -2 | 5777.25 |
| 2/4/2002 | 2002 | 2 | 4 | 249 | 12 | 51 | 31.5 | -0.5 | 5776.75 |
| 2/5/2002 | 2002 | 2 | 5 | 250 | 7 | 40 | 23.5 | -8.5 | 5768.25 |
| 2/6/2002 | 2002 | 2 | 6 | 251 | 10 | 48 | 29 | -3 | 5765.25 |
| 2/7/2002 | 2002 | 2 | 7 | 252 | 13 | 57 | 35 | 3 | 5768.25 |
| 2/8/2002 | 2002 | 2 | 8 | 253 | 20 | 58 | 39 | 7 | 5775.25 |
| 2/9/2002 | 2002 | 2 | 9 | 254 | 10 | 39 | 24.5 | -7.5 | 5767.75 |
| 2/10/2002 | 2002 | 2 | 10 | 255 | 11 | 50 | 30.5 | -1.5 | 5766.25 |
| 2/11/2002 | 2002 | 2 | 11 | 256 | 13 | 62 | 37.5 | 5.5 | 5771.75 |
| 2/12/2002 | 2002 | 2 | 12 | 257 | 12 | 65 | 38.5 | 6.5 | 5778.25 |
| 2/13/2002 | 2002 | 2 | 13 | 258 | 25 | 49 | 37 | 5 | 5783.25 |
| 2/14/2002 | 2002 | 2 | 14 | 259 | 19 | 61 | 40 | 8 | 5791.25 |
| 2/15/2002 | 2002 | 2 | 15 | 260 | 20 | 63 | 41.5 | 9.5 | 5800.75 |
| 2/16/2002 | 2002 | 2 | 16 | 261 | 19 | 64 | 41.5 | 9.5 | 5810.25 |
| 2/17/2002 | 2002 | 2 | 17 | 262 | 28 | 66 | 47 | 15 | 5825.25 |
| 2/18/2002 | 2002 | 2 | 18 | 263 | 27 | 52 | 39.5 | 7.5 | 5832.75 |
| 2/19/2002 | 2002 | 2 | 19 | 264 | 17 | 60 | 38.5 | 6.5 | 5839.25 |
| 2/20/2002 | 2002 | 2 | 20 | 265 | 28 | 62 | 45 | 13 | 5852.25 |
| 2/21/2002 | 2002 | 2 | 21 | 266 | 14 | 54 | 34 | 2 | 5854.25 |
| 2/22/2002 | 2002 | 2 | 22 | 267 | 17 | 67 | 42 | 10 | 5864.25 |
| 2/23/2002 | 2002 | 2 | 23 | 268 | 37 | 72 | 54.5 | 22.5 | 5886.75 |
| 2/24/2002 | 2002 | 2 | 24 | 269 | 15 | 63 | 39 | 7 | 5893.75 |
| 2/25/2002 | 2002 | 2 | 25 | 270 | 16 | 58 | 37 | 5 | 5898.75 |
| 2/26/2002 | 2002 | 2 | 26 | 271 | 10 | 52 | 31 | -1 | 5897.75 |
| 2/27/2002 | 2002 | 2 | 27 | 272 | 15 | 57 | 36 | 4 | 5901.75 |
| 2/28/2002 | 2002 | 2 | 28 | 273 | 40 | 62 | 51 | 19 | 5920.75 |
| 3/1/2002 | 2002 | 3 | 1 | 274 | 6 | 46 | 26 | -6 | 5914.75 |
| 3/2/2002 | 2002 | 3 | 2 | 275 | 0 | 33 | 16.5 | -15.5 | 5899.25 |
| 3/3/2002 | 2002 | 3 | 3 | 276 | 1 | 37 | 19 | -13 | 5886.25 |
| 3/4/2002 | 2002 | 3 | 4 | 277 | 15 | 63 | 39 | 7 | 5893.25 |
| 3/5/2002 | 2002 | 3 | 5 | 278 | 19 | 61 | 40 | 8 | 5901.25 |
| 3/6/2002 | 2002 | 3 | 6 | 279 | 34 | 69 | 51.5 | 19.5 | 5920.75 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/7/2002 | 2002 | 3 | 7 | 280 | 39 | 62 | 50.5 | 18.5 | 5939.25 |
| 3/8/2002 | 2002 | 3 | 8 | 281 | 10 | 54 | 32 | 0 | 5939.25 |
| 3/9/2002 | 2002 | 3 | 9 | 282 | 14 | 61 | 37.5 | 5.5 | 5944.75 |
| 3/10/2002 | 2002 | 3 | 10 | 283 | 34 | 61 | 47.5 | 15.5 | 5960.25 |
| 3/11/2002 | 2002 | 3 | 11 | 284 | 19 | 63 | 41 | 9 | 5969.25 |
| 3/12/2002 | 2002 | 3 | 12 | 285 | 27 | 72 | 49.5 | 17.5 | 5986.75 |
| 3/13/2002 | 2002 | 3 | 13 | 286 | 30 | 74 | 52 | 20 | 6006.75 |
| 3/15/2002 | 2002 | 3 | 15 | 287 | 16 | 53 | 34.5 | 2.5 | 6009.25 |
| 3/16/2002 | 2002 | 3 | 16 | 288 | 15 | 53 | 34 | 2 | 6011.25 |
| 3/17/2002 | 2002 | 3 | 17 | 289 | 15 | 55 | 35 | 3 | 6014.25 |
| 3/18/2002 | 2002 | 3 | 18 | 290 | 20 | 54 | 37 | 5 | 6019.25 |
| 3/19/2002 | 2002 | 3 | 19 | 291 | 17 | 58 | 37.5 | 5.5 | 6024.75 |
| 3/20/2002 | 2002 | 3 | 20 | 292 | 18 | 69 | 43.5 | 11.5 | 6036.25 |
| 3/21/2002 | 2002 | 3 | 21 | 293 | 32 | 73 | 52.5 | 20.5 | 6056.75 |
| 3/22/2002 | 2002 | 3 | 22 | 294 | 31 | 73 | 52 | 20 | 6076.75 |
| 3/23/2002 | 2002 | 3 | 23 | 295 | 33 | 74 | 53.5 | 21.5 | 6098.25 |
| 3/24/2002 | 2002 | 3 | 24 | 296 | 32 | 54 | 43 | 11 | 6109.25 |
| 3/25/2002 | 2002 | 3 | 25 | 297 | 18 | 59 | 38.5 | 6.5 | 6115.75 |
| 3/26/2002 | 2002 | 3 | 26 | 298 | 22 | 68 | 45 | 13 | 6128.75 |
| 3/27/2002 | 2002 | 3 | 27 | 299 | 33 | 72 | 52.5 | 20.5 | 6149.25 |
| 3/28/2002 | 2002 | 3 | 28 | 300 | 33 | 75 | 54 | 22 | 6171.25 |
| 3/29/2002 | 2002 | 3 | 29 | 301 | 27 | 63 | 45 | 13 | 6184.25 |
| 3/30/2002 | 2002 | 3 | 30 | 302 | 29 | 73 | 51 | 19 | 6203.25 |
| 3/31/2002 | 2002 | 3 | 31 | 303 | 29 | 78 | 53.5 | 21.5 | 6224.75 |
| 4/1/2002 | 2002 | 4 | 1 | 304 | 29 | 79 | 54 | 22 | 6246.75 |
| 4/2/2002 | 2002 | 4 | 2 | 305 | 30 | 79 | 54.5 | 22.5 | 6269.25 |
| 4/3/2002 | 2002 | 4 | 3 | 306 | 38 | 74 | 56 | 24 | 6293.25 |
| 4/4/2002 | 2002 | 4 | 4 | 307 | 31 | 78 | 54.5 | 22.5 | 6315.75 |
| 4/5/2002 | 2002 | 4 | 5 | 308 | 36 | 65 | 50.5 | 18.5 | 6334.25 |
| 4/6/2002 | 2002 | 4 | 6 | 309 | 33 | 60 | 46.5 | 14.5 | 6348.75 |
| 4/7/2002 | 2002 | 4 | 7 | 310 | 33 | 60 | 46.5 | 14.5 | 6363.25 |
| 4/8/2002 | 2002 | 4 | 8 | 311 | 31 | 71 | 51 | 19 | 6382.25 |
| 4/9/2002 | 2002 | 4 | 9 | 312 | 39 | 77 | 58 | 26 | 6408.25 |
| 4/10/2002 | 2002 | 4 | 10 | 313 | 41 | 75 | 58 | 26 | 6434.25 |
| 4/11/2002 | 2002 | 4 | 11 | 314 | 42 | 77 | 59.5 | 27.5 | 6461.75 |
| 4/12/2002 | 2002 | 4 | 12 | 315 | 37 | 78 | 57.5 | 25.5 | 6487.25 |
| 4/13/2002 | 2002 | 4 | 13 | 316 | 32 | 79 | 55.5 | 23.5 | 6510.75 |
| 4/14/2002 | 2002 | 4 | 14 | 317 | 41 | 84 | 62.5 | 30.5 | 6541.25 |
| 4/15/2002 | 2002 | 4 | 15 | 318 | 46 | 80 | 63 | 31 | 6572.25 |
| 4/16/2002 | 2002 | 4 | 16 | 319 | 33 | 69 | 51 | 19 | 6591.25 |
| 4/17/2002 | 2002 | 4 | 17 | 320 | 38 | 77 | 57.5 | 25.5 | 6616.75 |
| 4/18/2002 | 2002 | 4 | 18 | 321 | 37 | 80 | 58.5 | 26.5 | 6643.25 |
| 4/19/2002 | 2002 | 4 | 19 | 322 | 22 | 68 | 45 | 13 | 6656.25 |
| 4/20/2002 | 2002 | 4 | 20 | 323 | 22 | 72 | 47 | 15 | 6671.25 |
| 4/21/2002 | 2002 | 4 | 21 | 324 | 22 | 72 | 47 | 15 | 6686.25 |
| 4/22/2002 | 2002 | 4 | 22 | 325 | 30 | 79 | 54.5 | 22.5 | 6708.75 |
| 4/23/2002 | 2002 | 4 | 23 | 326 | 30 | 81 | 55.5 | 23.5 | 6732.25 |
| 4/24/2002 | 2002 | 4 | 24 | 327 | 46 | 82 | 64 | 32 | 6764.25 |
| 4/25/2002 | 2002 | 4 | 25 | 328 | 41 | 67 | 54 | 22 | 6786.25 |
| 4/26/2002 | 2002 | 4 | 26 | 329 | 39 | 80 | 59.5 | 27.5 | 6813.75 |
| 4/27/2002 | 2002 | 4 | 27 | 330 | 35 | 66 | 50.5 | 18.5 | 6832.25 |
| 4/28/2002 | 2002 | 4 | 28 | 331 | 40 | 79 | 59.5 | 27.5 | 6859.75 |
| 4/29/2002 | 2002 | 4 | 29 | 332 | 40 | 79 | 59.5 | 27.5 | 6887.25 |
| 4/30/2002 | 2002 | 4 | 30 | 333 | 33 | 80 | 56.5 | 24.5 | 6911.75 |
| 5/1/2002 | 2002 | 5 | 1 | 334 | 26 | 82 | 54 | 22 | 6933.75 |
| 5/2/2002 | 2002 | 5 | 2 | 335 | 30 | 68 | 49 | 17 | 6950.75 |
| 5/3/2002 | 2002 | 5 | 3 | 336 | 29 | 78 | 53.5 | 21.5 | 6972.25 |
| 5/4/2002 | 2002 | 5 | 4 | 337 | 30 | 82 | 56 | 24 | 6996.25 |
| 5/5/2002 | 2002 | 5 | 5 | 338 | 32 | 80 | 56 | 24 | 7020.25 |
| 5/6/2002 | 2002 | 5 | 6 | 339 | 36 | 81 | 58.5 | 26.5 | 7046.75 |
| 5/7/2002 | 2002 | 5 | 7 | 340 | 38 | 80 | 59 | 27 | 7073.75 |
| 5/8/2002 | 2002 | 5 | 8 | 341 | 38 | 76 | 57 | 25 | 7098.75 |
| 5/9/2002 | 2002 | 5 | 9 | 342 | 44 | 79 | 61.5 | 29.5 | 7128.25 |
| 5/10/2002 | 2002 | 5 | 10 | 343 | 44 | 84 | 64 | 32 | 7160.25 |
| 5/11/2002 | 2002 | 5 | 11 | 344 | 34 | 84 | 59 | 27 | 7187.25 |
| 5/12/2002 | 2002 | 5 | 12 | 345 | 35 | 72 | 53.5 | 21.5 | 7208.75 |
| 5/13/2002 | 2002 | 5 | 13 | 346 | 51 | 78 | 64.5 | 32.5 | 7241.25 |
| 5/14/2002 | 2002 | 5 | 14 | 347 | 45 | 77 | 61 | 29 | 7270.25 |
| 5/15/2002 | 2002 | 5 | 15 | 348 | 39 | 84 | 61.5 | 29.5 | 7299.75 |
| 5/16/2002 | 2002 | 5 | 16 | 349 | 36 | 85 | 60.5 | 28.5 | 7328.25 |
| 5/17/2002 | 2002 | 5 | 17 | 350 | 53 | 86 | 69.5 | 37.5 | 7365.75 |
| 5/18/2002 | 2002 | 5 | 18 | 351 | 53 | 80 | 66.5 | 34.5 | 7400.25 |
| 5/19/2002 | 2002 | 5 | 19 | 352 | 48 | 81 | 64.5 | 32.5 | 7432.75 |
| 5/20/2002 | 2002 | 5 | 20 | 353 | 47 | 84 | 65.5 | 33.5 | 7466.25 |
| 5/21/2002 | 2002 | 5 | 21 | 354 | 33 | 80 | 56.5 | 24.5 | 7490.75 |
| 5/22/2002 | 2002 | 5 | 22 | 355 | 37 | 76 | 56.5 | 24.5 | 7515.25 |
| 5/23/2002 | 2002 | 5 | 23 | 356 | 41 | 79 | 60 | 28 | 7543.25 |
| 5/24/2002 | 2002 | 5 | 24 | 357 | 35 | 81 | 58 | 26 | 7569.25 |
| 5/25/2002 | 2002 | 5 | 25 | 358 | 44 | 84 | 64 | 32 | 7601.25 |
| 5/26/2002 | 2002 | 5 | 26 | 359 | 54 | 81 | 67.5 | 35.5 | 7636.75 |
| 5/27/2002 | 2002 | 5 | 27 | 360 | 43 | 82 | 62.5 | 30.5 | 7667.25 |
| 5/28/2002 | 2002 | 5 | 28 | 361 | 42 | 90 | 66 | 34 | 7701.25 |
| 5/29/2002 | 2002 | 5 | 29 | 362 | 45 | 95 | 70 | 38 | 7739.25 |
| 5/30/2002 | 2002 | 5 | 30 | 363 | 47 | 99 | 73 | 41 | 7780.25 |
| 5/31/2002 | 2002 | 5 | 31 | 364 | 55 | 97 | 76 | 44 | 7824.25 |
| 6/1/2002 | 2002 | 6 | 1 | 1 | 50 | 95 | 72.5 | 40.5 | 40.5 |
| 6/2/2002 | 2002 | 6 | 2 | 2 | 45 | 92 | 68.5 | 36.5 | 77 |
| 6/3/2002 | 2002 | 6 | 3 | 3 | 48 | 83 | 65.5 | 33.5 | 110.5 |
| 6/4/2002 | 2002 | 6 | 4 | 4 | 46 | 80 | 63 | 31 | 141.5 |
| 6/5/2002 | 2002 | 6 | 5 | 5 | 45 | 85 | 65 | 33 | 174.5 |
| 6/6/2002 | 2002 | 6 | 6 | 6 | 56 | 94 | 75 | 43 | 217.5 |
| 6/7/2002 | 2002 | 6 | 7 | 7 | 57 | 92 | 74.5 | 42.5 | 260 |
| 6/8/2002 | 2002 | 6 | 8 | 8 | 60 | 92 | 76 | 44 | 304 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/9/2002 | 2002 | 6 | 9 | 9 | 46 | 93 | 69.5 | 37.5 | 341.5 |
| 6/10/2002 | 2002 | 6 | 10 | 10 | 54 | 90 | 72 | 40 | 381.5 |
| 6/11/2002 | 2002 | 6 | 11 | 11 | 43 | 93 | 68 | 36 | 417.5 |
| 6/12/2002 | 2002 | 6 | 12 | 12 | 41 | 93 | 67 | 35 | 452.5 |
| 6/13/2002 | 2002 | 6 | 13 | 13 | 53 | 98 | 75.5 | 43.5 | 496 |
| 6/14/2002 | 2002 | 6 | 14 | 14 | 57 | 87 | 72 | 40 | 536 |
| 6/15/2002 | 2002 | 6 | 15 | 15 | 57 | 95 | 76 | 44 | 580 |
| 6/16/2002 | 2002 | 6 | 16 | 16 | 50 | 98 | 74 | 42 | 622 |
| 6/17/2002 | 2002 | 6 | 17 | 17 | 57 | 99 | 78 | 46 | 668 |
| 6/18/2002 | 2002 | 6 | 18 | 18 | 55 | 98 | 76.5 | 44.5 | 712.5 |
| 6/19/2002 | 2002 | 6 | 19 | 19 | 48 | 96 | 72 | 40 | 752.5 |
| 6/20/2002 | 2002 | 6 | 20 | 20 | 61 | 95 | 78 | 46 | 798.5 |
| 6/21/2002 | 2002 | 6 | 21 | 21 | 56 | 91 | 73.5 | 41.5 | 840 |
| 6/22/2002 | 2002 | 6 | 22 | 22 | 56 | 91 | 73.5 | 41.5 | 881.5 |
| 6/23/2002 | 2002 | 6 | 23 | 23 | 47 | 98 | 72.5 | 40.5 | 922 |
| 6/24/2002 | 2002 | 6 | 24 | 24 | 46 | 97 | 71.5 | 39.5 | 961.5 |
| 6/25/2002 | 2002 | 6 | 25 | 25 | 54 | 95 | 74.5 | 42.5 | 1004 |
| 6/26/2002 | 2002 | 6 | 26 | 26 | 52 | 96 | 74 | 42 | 1046 |
| 6/27/2002 | 2002 | 6 | 27 | 27 | 57 | 96 | 76.5 | 44.5 | 1090.5 |
| 6/28/2002 | 2002 | 6 | 28 | 28 | 56 | 96 | 76 | 44 | 1134.5 |
| 6/29/2002 | 2002 | 6 | 29 | 29 | 51 | 100 | 75.5 | 43.5 | 1178 |
| 6/30/2002 | 2002 | 6 | 30 | 30 | 53 | 102 | 77.5 | 45.5 | 1223.5 |
| 7/1/2002 | 2002 | 7 | 1 | 31 | 52 | 100 | 76 | 44 | 1267.5 |
| 7/2/2002 | 2002 | 7 | 2 | 32 | 60 | 105 | 82.5 | 50.5 | 1318 |
| 7/3/2002 | 2002 | 7 | 3 | 33 | 53 | 96 | 74.5 | 42.5 | 1360.5 |
| 7/4/2002 | 2002 | 7 | 4 | 34 | 53 | 89 | 71 | 39 | 1399.5 |
| 7/5/2002 | 2002 | 7 | 5 | 35 | 60 | 90 | 75 | 43 | 1442.5 |
| 7/6/2002 | 2002 | 7 | 6 | 36 | 62 | 87 | 74.5 | 42.5 | 1485 |
| 7/7/2002 | 2002 | 7 | 7 | 37 | 61 | 90 | 75.5 | 43.5 | 1528.5 |
| 7/8/2002 | 2002 | 7 | 8 | 38 | 55 | 88 | 71.5 | 39.5 | 1568 |
| 7/9/2002 | 2002 | 7 | 9 | 39 | 52 | 91 | 71.5 | 39.5 | 1607.5 |
| 7/10/2002 | 2002 | 7 | 10 | 40 | 51 | 95 | 73 | 41 | 1648.5 |
| 7/11/2002 | 2002 | 7 | 11 | 41 | 54 | 97 | 75.5 | 43.5 | 1692 |
| 7/12/2002 | 2002 | 7 | 12 | 42 | 50 | 98 | 74 | 42 | 1734 |
| 7/13/2002 | 2002 | 7 | 13 | 43 | 56 | 102 | 79 | 47 | 1781 |
| 7/14/2002 | 2002 | 7 | 14 | 44 | 54 | 101 | 77.5 | 45.5 | 1826.5 |
| 7/15/2002 | 2002 | 7 | 15 | 45 | 58 | 95 | 76.5 | 44.5 | 1871 |
| 7/16/2002 | 2002 | 7 | 16 | 46 | 52 | 88 | 70 | 38 | 1909 |
| 7/17/2002 | 2002 | 7 | 17 | 47 | 52 | 96 | 74 | 42 | 1951 |
| 7/18/2002 | 2002 | 7 | 18 | 48 | 54 | 90 | 72 | 40 | 1991 |
| 7/19/2002 | 2002 | 7 | 19 | 49 | 54 | 75 | 64.5 | 32.5 | 2023.5 |
| 7/20/2002 | 2002 | 7 | 20 | 50 | 53 | 90 | 71.5 | 39.5 | 2063 |
| 7/21/2002 | 2002 | 7 | 21 | 51 | 53 | 98 | 75.5 | 43.5 | 2106.5 |
| 7/22/2002 | 2002 | 7 | 22 | 52 | 61 | 92 | 76.5 | 44.5 | 2151 |
| 7/23/2002 | 2002 | 7 | 23 | 53 | 51 | 96 | 73.5 | 41.5 | 2192.5 |
| 7/24/2002 | 2002 | 7 | 24 | 54 | 54 | 96 | 75 | 43 | 2235.5 |
| 7/25/2002 | 2002 | 7 | 25 | 55 | 55 | 97 | 76 | 44 | 2279.5 |
| 7/26/2002 | 2002 | 7 | 26 | 56 | 56 | 95 | 75.5 | 43.5 | 2323 |
| 7/27/2002 | 2002 | 7 | 27 | 57 | 58 | 94 | 76 | 44 | 2367 |
| 7/28/2002 | 2002 | 7 | 28 | 58 | 49 | 95 | 72 | 40 | 2407 |
| 7/29/2002 | 2002 | 7 | 29 | 59 | 55 | 99 | 77 | 45 | 2452 |
| 7/30/2002 | 2002 | 7 | 30 | 60 | 55 | 102 | 78.5 | 46.5 | 2498.5 |
| 7/31/2002 | 2002 | 7 | 31 | 61 | 55 | 97 | 76 | 44 | 2542.5 |
| 8/1/2002 | 2002 | 8 | 1 | 62 | 59 | 97 | 78 | 46 | 2588.5 |
| 8/2/2002 | 2002 | 8 | 2 | 63 | 60 | 78 | 69 | 37 | 2625.5 |
| 8/3/2002 | 2002 | 8 | 3 | 64 | 60 | 82 | 71 | 39 | 2664.5 |
| 8/4/2002 | 2002 | 8 | 4 | 65 | 56 | 85 | 70.5 | 38.5 | 2703 |
| 8/5/2002 | 2002 | 8 | 5 | 66 | 56 | 87 | 71.5 | 39.5 | 2742.5 |
| 8/6/2002 | 2002 | 8 | 6 | 67 | 52 | 82 | 67 | 35 | 2777.5 |
| 8/7/2002 | 2002 | 8 | 7 | 68 | 55 | 87 | 71 | 39 | 2816.5 |
| 8/8/2002 | 2002 | 8 | 8 | 69 | 60 | 93 | 76.5 | 44.5 | 2861 |
| 8/9/2002 | 2002 | 8 | 9 | 70 | 52 | 97 | 74.5 | 42.5 | 2903.5 |
| 8/10/2002 | 2002 | 8 | 10 | 71 | 58 | 98 | 78 | 46 | 2949.5 |
| 8/11/2002 | 2002 | 8 | 11 | 72 | 48 | 99 | 73.5 | 41.5 | 2991 |
| 8/12/2002 | 2002 | 8 | 12 | 73 | 51 | 102 | 76.5 | 44.5 | 3035.5 |
| 8/13/2002 | 2002 | 8 | 13 | 74 | 47 | 101 | 74 | 42 | 3077.5 |
| 8/14/2002 | 2002 | 8 | 14 | 75 | 55 | 100 | 77.5 | 45.5 | 3123 |
| 8/15/2002 | 2002 | 8 | 15 | 76 | 50 | 101 | 75.5 | 43.5 | 3166.5 |
| 8/16/2002 | 2002 | 8 | 16 | 77 | 52 | 97 | 74.5 | 42.5 | 3209 |
| 8/17/2002 | 2002 | 8 | 17 | 78 | 60 | 97 | 78.5 | 46.5 | 3255.5 |
| 8/18/2002 | 2002 | 8 | 18 | 79 | 51 | 82 | 66.5 | 34.5 | 3290 |
| 8/19/2002 | 2002 | 8 | 19 | 80 | 51 | 91 | 71 | 39 | 3329 |
| 8/20/2002 | 2002 | 8 | 20 | 81 | 54 | 89 | 71.5 | 39.5 | 3368.5 |
| 8/21/2002 | 2002 | 8 | 21 | 82 | 50 | 91 | 70.5 | 38.5 | 3407 |
| 8/22/2002 | 2002 | 8 | 22 | 83 | 51 | 91 | 71 | 39 | 3446 |
| 8/23/2002 | 2002 | 8 | 23 | 84 | 46 | 86 | 66 | 34 | 3480 |
| 8/24/2002 | 2002 | 8 | 24 | 85 | 42 | 95 | 68.5 | 36.5 | 3516.5 |
| 8/25/2002 | 2002 | 8 | 25 | 86 | 46 | 95 | 70.5 | 38.5 | 3555 |
| 8/26/2002 | 2002 | 8 | 26 | 87 | 48 | 96 | 72 | 40 | 3595 |
| 8/27/2002 | 2002 | 8 | 27 | 88 | 54 | 96 | 75 | 43 | 3638 |
| 8/28/2002 | 2002 | 8 | 28 | 89 | 53 | 86 | 69.5 | 37.5 | 3675.5 |
| 8/29/2002 | 2002 | 8 | 29 | 90 | 44 | 82 | 63 | 31 | 3706.5 |
| 8/30/2002 | 2002 | 8 | 30 | 91 | 44 | 82 | 63 | 31 | 3737.5 |
| 8/31/2002 | 2002 | 8 | 31 | 92 | 49 | 96 | 72.5 | 40.5 | 3778 |
| 9/1/2002 | 2002 | 9 | 1 | 93 | 57 | 94 | 75.5 | 43.5 | 3821.5 |
| 9/2/2002 | 2002 | 9 | 2 | 94 | 60 | 93 | 76.5 | 44.5 | 3866 |
| 9/3/2002 | 2002 | 9 | 3 | 95 | 49 | 89 | 69 | 37 | 3903 |
| 9/4/2002 | 2002 | 9 | 4 | 96 | 52 | 93 | 72.5 | 40.5 | 3943.5 |
| 9/5/2002 | 2002 | 9 | 5 | 97 | 53 | 96 | 74.5 | 42.5 | 3986 |
| 9/6/2002 | 2002 | 9 | 6 | 98 | 56 | 91 | 73.5 | 41.5 | 4027.5 |
| 9/7/2002 | 2002 | 9 | 7 | 99 | 56 | 85 | 70.5 | 38.5 | 4066 |
| 9/8/2002 | 2002 | 9 | 8 | 100 | 59 | 72 | 65.5 | 33.5 | 4099.5 |
| 9/9/2002 | 2002 | 9 | 9 | 101 | 57 | 82 | 69.5 | 37.5 | 4137 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/10/2002 | 2002 | 9 | 10 | 102 | 52 | 64 | 58 | 26 | 4163 |
| 9/11/2002 | 2002 | 9 | 11 | 103 | 50 | 68 | 59 | 27 | 4190 |
| 9/12/2002 | 2002 | 9 | 12 | 104 | 47 | 79 | 63 | 31 | 4221 |
| 9/13/2002 | 2002 | 9 | 13 | 105 | 47 | 79 | 63 | 31 | 4252 |
| 9/14/2002 | 2002 | 9 | 14 | 106 | 51 | 77 | 64 | 32 | 4284 |
| 9/15/2002 | 2002 | 9 | 15 | 107 | 43 | 77 | 60 | 28 | 4312 |
| 9/16/2002 | 2002 | 9 | 16 | 108 | 52 | 77 | 64.5 | 32.5 | 4344.5 |
| 9/17/2002 | 2002 | 9 | 17 | 109 | 54 | 83 | 68.5 | 36.5 | 4381 |
| 9/18/2002 | 2002 | 9 | 18 | 110 | 42 | 58 | 50 | 18 | 4399 |
| 9/19/2002 | 2002 | 9 | 19 | 111 | 38 | 75 | 56.5 | 24.5 | 4423.5 |
| 9/20/2002 | 2002 | 9 | 20 | 112 | 39 | 82 | 60.5 | 28.5 | 4452 |
| 9/21/2002 | 2002 | 9 | 21 | 113 | 43 | 87 | 65 | 33 | 4485 |
| 9/22/2002 | 2002 | 9 | 22 | 114 | 42 | 88 | 65 | 33 | 4518 |
| 9/23/2002 | 2002 | 9 | 23 | 115 | 43 | 88 | 65.5 | 33.5 | 4551.5 |
| 9/24/2002 | 2002 | 9 | 24 | 116 | 54 | 88 | 71 | 39 | 4590.5 |
| 9/25/2002 | 2002 | 9 | 25 | 117 | 46 | 86 | 66 | 34 | 4624.5 |
| 9/26/2002 | 2002 | 9 | 26 | 118 | 44 | 83 | 63.5 | 31.5 | 4656 |
| 9/27/2002 | 2002 | 9 | 27 | 119 | 47 | 77 | 62 | 30 | 4686 |
| 9/28/2002 | 2002 | 9 | 28 | 120 | 41 | 73 | 57 | 25 | 4711 |
| 9/29/2002 | 2002 | 9 | 29 | 121 | 40 | 78 | 59 | 27 | 4738 |
| 9/30/2002 | 2002 | 9 | 30 | 122 | 50 | 78 | 64 | 32 | 4770 |
| 10/1/2002 | 2002 | 10 | 1 | 123 | 49 | 79 | 64 | 32 | 4802 |
| 10/2/2002 | 2002 | 10 | 2 | 124 | 38 | 75 | 56.5 | 24.5 | 4826.5 |
| 10/3/2002 | 2002 | 10 | 3 | 125 | 29 | 63 | 46 | 14 | 4840.5 |
| 10/4/2002 | 2002 | 10 | 4 | 126 | 30 | 70 | 50 | 18 | 4858.5 |
| 10/5/2002 | 2002 | 10 | 5 | 127 | 36 | 76 | 56 | 24 | 4882.5 |
| 10/6/2002 | 2002 | 10 | 6 | 128 | 40 | 78 | 59 | 27 | 4909.5 |
| 10/7/2002 | 2002 | 10 | 7 | 129 | 34 | 79 | 56.5 | 24.5 | 4934 |
| 10/8/2002 | 2002 | 10 | 8 | 130 | 33 | 81 | 57 | 25 | 4959 |
| 10/9/2002 | 2002 | 10 | 9 | 131 | 33 | 79 | 56 | 24 | 4983 |
| 10/10/2002 | 2002 | 10 | 10 | 132 | 35 | 78 | 56.5 | 24.5 | 5007.5 |
| 10/11/2002 | 2002 | 10 | 11 | 133 | 40 | 79 | 59.5 | 27.5 | 5035 |
| 10/12/2002 | 2002 | 10 | 12 | 134 | 43 | 74 | 58.5 | 26.5 | 5061.5 |
| 10/13/2002 | 2002 | 10 | 13 | 135 | 34 | 61 | 47.5 | 15.5 | 5077 |
| 10/14/2002 | 2002 | 10 | 14 | 136 | 38 | 76 | 57 | 25 | 5102 |
| 10/15/2002 | 2002 | 10 | 15 | 137 | 35 | 72 | 53.5 | 21.5 | 5123.5 |
| 10/16/2002 | 2002 | 10 | 16 | 138 | 43 | 79 | 61 | 29 | 5152.5 |
| 10/17/2002 | 2002 | 10 | 17 | 139 | 42 | 64 | 53 | 21 | 5173.5 |
| 10/18/2002 | 2002 | 10 | 18 | 140 | 33 | 64 | 48.5 | 16.5 | 5190 |
| 10/19/2002 | 2002 | 10 | 19 | 141 | 32 | 65 | 48.5 | 16.5 | 5206.5 |
| 10/20/2002 | 2002 | 10 | 20 | 142 | 42 | 73 | 57.5 | 25.5 | 5232 |
| 10/21/2002 | 2002 | 10 | 21 | 143 | 37 | 65 | 51 | 19 | 5251 |
| 10/22/2002 | 2002 | 10 | 22 | 144 | 38 | 65 | 51.5 | 19.5 | 5270.5 |
| 10/23/2002 | 2002 | 10 | 23 | 145 | 39 | 65 | 52 | 20 | 5290.5 |
| 10/24/2002 | 2002 | 10 | 24 | 146 | 29 | 64 | 46.5 | 14.5 | 5305 |
| 10/25/2002 | 2002 | 10 | 25 | 147 | 39 | 62 | 50.5 | 18.5 | 5323.5 |
| 10/26/2002 | 2002 | 10 | 26 | 148 | 35 | 58 | 46.5 | 14.5 | 5338 |
| 10/27/2002 | 2002 | 10 | 27 | 149 | 29 | 53 | 41 | 9 | 5347 |
| 10/28/2002 | 2002 | 10 | 28 | 150 | 40 | 56 | 48 | 16 | 5363 |
| 10/29/2002 | 2002 | 10 | 29 | 151 | 29 | 57 | 43 | 11 | 5374 |
| 10/30/2002 | 2002 | 10 | 30 | 152 | 26 | 61 | 43.5 | 11.5 | 5385.5 |
| 10/31/2002 | 2002 | 10 | 31 | 153 | 30 | 64 | 47 | 15 | 5400.5 |
| 11/1/2002 | 2002 | 11 | 1 | 154 | 37 | 65 | 51 | 19 | 5419.5 |
| 11/2/2002 | 2002 | 11 | 2 | 155 | 30 | 65 | 47.5 | 15.5 | 5435 |
| 11/3/2002 | 2002 | 11 | 3 | 156 | 32 | 55 | 43.5 | 11.5 | 5446.5 |
| 11/4/2002 | 2002 | 11 | 4 | 157 | 25 | 52 | 38.5 | 6.5 | 5453 |
| 11/5/2002 | 2002 | 11 | 5 | 158 | 20 | 60 | 40 | 8 | 5461 |
| 11/6/2002 | 2002 | 11 | 6 | 159 | 21 | 69 | 45 | 13 | 5474 |
| 11/7/2002 | 2002 | 11 | 7 | 160 | 40 | 70 | 55 | 23 | 5497 |
| 11/8/2002 | 2002 | 11 | 8 | 161 | 40 | 60 | 50 | 18 | 5515 |
| 11/9/2002 | 2002 | 11 | 9 | 162 | 34 | 60 | 47 | 15 | 5530 |
| 11/10/2002 | 2002 | 11 | 10 | 163 | 28 | 53 | 40.5 | 8.5 | 5538.5 |
| 11/11/2002 | 2002 | 11 | 11 | 164 | 21 | 54 | 37.5 | 5.5 | 5544 |
| 11/12/2002 | 2002 | 11 | 12 | 165 | 21 | 64 | 42.5 | 10.5 | 5554.5 |
| 11/13/2002 | 2002 | 11 | 13 | 166 | 21 | 64 | 42.5 | 10.5 | 5565 |
| 11/14/2002 | 2002 | 11 | 14 | 167 | 28 | 58 | 43 | 11 | 5576 |
| 11/15/2002 | 2002 | 11 | 15 | 168 | 15 | 55 | 35 | 3 | 5579 |
| 11/16/2002 | 2002 | 11 | 16 | 169 | 17 | 61 | 39 | 7 | 5586 |
| 11/17/2002 | 2002 | 11 | 17 | 170 | 23 | 68 | 45.5 | 13.5 | 5599.5 |
| 11/18/2002 | 2002 | 11 | 18 | 171 | 14 | 58 | 36 | 4 | 5603.5 |
| 11/19/2002 | 2002 | 11 | 19 | 172 | 20 | 62 | 41 | 9 | 5612.5 |
| 11/20/2002 | 2002 | 11 | 20 | 173 | 20 | 60 | 40 | 8 | 5620.5 |
| 11/21/2002 | 2002 | 11 | 21 | 174 | 20 | 63 | 41.5 | 9.5 | 5630 |
| 11/22/2002 | 2002 | 11 | 22 | 175 | 23 | 73 | 48 | 16 | 5646 |
| 11/23/2002 | 2002 | 11 | 23 | 176 | 19 | 62 | 40.5 | 8.5 | 5654.5 |
| 11/24/2002 | 2002 | 11 | 24 | 177 | 32 | 65 | 48.5 | 16.5 | 5671 |
| 11/25/2002 | 2002 | 11 | 25 | 178 | 18 | 57 | 37.5 | 5.5 | 5676.5 |
| 11/26/2002 | 2002 | 11 | 26 | 179 | 17 | 43 | 30 | -2 | 5674.5 |
| 11/27/2002 | 2002 | 11 | 27 | 180 | 17 | 43 | 30 | -2 | 5672.5 |
| 11/28/2002 | 2002 | 11 | 28 | 181 | 23 | 65 | 44 | 12 | 5684.5 |
| 11/29/2002 | 2002 | 11 | 29 | 182 | 30 | 68 | 49 | 17 | 5701.5 |
| 11/30/2002 | 2002 | 11 | 30 | 183 | 25 | 54 | 39.5 | 7.5 | 5709 |
| 12/1/2002 | 2002 | 12 | 1 | 184 | 20 | 62 | 41 | 9 | 5718 |
| 12/2/2002 | 2002 | 12 | 2 | 185 | 32 | 46 | 39 | 7 | 5725 |
| 12/3/2002 | 2002 | 12 | 3 | 186 | 26 | 46 | 36 | 4 | 5729 |
| 12/4/2002 | 2002 | 12 | 4 | 187 | 22 | 52 | 37 | 5 | 5734 |
| 12/5/2002 | 2002 | 12 | 5 | 188 | 18 | 52 | 35 | 3 | 5737 |
| 12/6/2002 | 2002 | 12 | 6 | 189 | 20 | 52 | 36 | 4 | 5741 |
| 12/7/2002 | 2002 | 12 | 7 | 190 | 22 | 45 | 33.5 | 1.5 | 5742.5 |
| 12/8/2002 | 2002 | 12 | 8 | 191 | 20 | 38 | 29 | -3 | 5739.5 |
| 12/9/2002 | 2002 | 12 | 9 | 192 | 16 | 46 | 31 | -1 | 5738.5 |
| 12/10/2002 | 2002 | 12 | 10 | 193 | 17 | 53 | 35 | 3 | 5741.5 |
| 12/11/2002 | 2002 | 12 | 11 | 194 | 20 | 47 | 33.5 | 1.5 | 5743 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/12/2002 | 2002 | 12 | 12 | 195 | 19 | 50 | 34.5 | 2.5 | 5745.5 |
| 12/13/2002 | 2002 | 12 | 13 | 196 | 18 | 58 | 38 | 6 | 5751.5 |
| 12/14/2002 | 2002 | 12 | 14 | 197 | 21 | 62 | 41.5 | 9.5 | 5761 |
| 12/15/2002 | 2002 | 12 | 15 | 198 | 20 | 56 | 38 | 6 | 5767 |
| 12/16/2002 | 2002 | 12 | 16 | 199 | 34 | 55 | 44.5 | 12.5 | 5779.5 |
| 12/17/2002 | 2002 | 12 | 17 | 200 | 13 | 55 | 34 | 2 | 5781.5 |
| 12/18/2002 | 2002 | 12 | 18 | 201 | 2 | 43 | 22.5 | -9.5 | 5772 |
| 12/19/2002 | 2002 | 12 | 19 | 202 | 2 | 43 | 22.5 | -9.5 | 5762.5 |
| 12/20/2002 | 2002 | 12 | 20 | 203 | 18 | 40 | 29 | -3 | 5759.5 |
| 12/21/2002 | 2002 | 12 | 21 | 204 | 12 | 37 | 24.5 | -7.5 | 5752 |
| 12/22/2002 | 2002 | 12 | 22 | 205 | 12 | 38 | 25 | -7 | 5745 |
| 12/23/2002 | 2002 | 12 | 23 | 206 | 12 | 34 | 23 | -9 | 5736 |
| 12/24/2002 | 2002 | 12 | 24 | 207 | 5 | 34 | 19.5 | -12.5 | 5723.5 |
| 12/25/2002 | 2002 | 12 | 25 | 208 | 1 | 42 | 21.5 | -10.5 | 5713 |
| 12/26/2002 | 2002 | 12 | 26 | 209 | 3 | 41 | 22 | -10 | 5703 |
| 12/27/2002 | 2002 | 12 | 27 | 210 | 5 | 55 | 30 | -2 | 5701 |
| 12/28/2002 | 2002 | 12 | 28 | 211 | 16 | 43 | 29.5 | -2.5 | 5698.5 |
| 12/29/2002 | 2002 | 12 | 29 | 212 | 26 | 56 | 41 | 9 | 5707.5 |
| 12/30/2002 | 2002 | 12 | 30 | 213 | 23 | 53 | 38 | 6 | 5713.5 |
| 12/31/2002 | 2002 | 12 | 31 | 214 | 24 | 54 | 39 | 7 | 5720.5 |
| 1/1/2003 | 2003 | 1 | 1 | 215 | 14 | 49 | 31.5 | -0.5 | 5720 |
| 1/2/2003 | 2003 | 1 | 2 | 216 | 14 | 49 | 31.5 | -0.5 | 5719.5 |
| 1/3/2003 | 2003 | 1 | 3 | 217 | 14 | 49 | 31.5 | -0.5 | 5719 |
| 1/4/2003 | 2003 | 1 | 4 | 218 | 21 | 64 | 42.5 | 10.5 | 5729.5 |
| 1/5/2003 | 2003 | 1 | 5 | 219 | 37 | 56 | 46.5 | 14.5 | 5744 |
| 1/6/2003 | 2003 | 1 | 6 | 220 | 20 | 52 | 36 | 4 | 5748 |
| 1/7/2003 | 2003 | 1 | 7 | 221 | 20 | 53 | 36.5 | 4.5 | 5752.5 |
| 1/8/2003 | 2003 | 1 | 8 | 222 | 22 | 50 | 36 | 4 | 5756.5 |
| 1/9/2003 | 2003 | 1 | 9 | 223 | 21 | 52 | 36.5 | 4.5 | 5761 |
| 1/10/2003 | 2003 | 1 | 10 | 224 | 21 | 57 | 39 | 7 | 5768 |
| 1/11/2003 | 2003 | 1 | 11 | 225 | 29 | 53 | 41 | 9 | 5777 |
| 1/12/2003 | 2003 | 1 | 12 | 226 | 20 | 55 | 37.5 | 5.5 | 5782.5 |
| 1/13/2003 | 2003 | 1 | 13 | 227 | 21 | 62 | 41.5 | 9.5 | 5792 |
| 1/14/2003 | 2003 | 1 | 14 | 228 | 19 | 62 | 40.5 | 8.5 | 5800.5 |
| 1/15/2003 | 2003 | 1 | 15 | 229 | 20 | 54 | 37 | 5 | 5805.5 |
| 1/16/2003 | 2003 | 1 | 16 | 230 | 19 | 60 | 39.5 | 7.5 | 5813 |
| 1/17/2003 | 2003 | 1 | 17 | 231 | 14 | 61 | 37.5 | 5.5 | 5818.5 |
| 1/18/2003 | 2003 | 1 | 18 | 232 | 16 | 59 | 37.5 | 5.5 | 5824 |
| 1/19/2003 | 2003 | 1 | 19 | 233 | 20 | 67 | 43.5 | 11.5 | 5835.5 |
| 1/20/2003 | 2003 | 1 | 20 | 234 | 27 | 61 | 44 | 12 | 5847.5 |
| 1/21/2003 | 2003 | 1 | 21 | 235 | 25 | 63 | 44 | 12 | 5859.5 |
| 1/22/2003 | 2003 | 1 | 22 | 236 | 21 | 66 | 43.5 | 11.5 | 5871 |
| 1/23/2003 | 2003 | 1 | 23 | 237 | 31 | 67 | 49 | 17 | 5888 |
| 1/24/2003 | 2003 | 1 | 24 | 238 | 20 | 66 | 43 | 11 | 5899 |
| 1/25/2003 | 2003 | 1 | 25 | 239 | 17 | 55 | 36 | 4 | 5903 |
| 1/26/2003 | 2003 | 1 | 26 | 240 | 19 | 67 | 43 | 11 | 5914 |
| 1/27/2003 | 2003 | 1 | 27 | 241 | 20 | 69 | 44.5 | 12.5 | 5926.5 |
| 1/28/2003 | 2003 | 1 | 28 | 242 | 19 | 67 | 43 | 11 | 5937.5 |
| 1/29/2003 | 2003 | 1 | 29 | 243 | 20 | 68 | 44 | 12 | 5949.5 |
| 1/30/2003 | 2003 | 1 | 30 | 244 | 22 | 67 | 44.5 | 12.5 | 5962 |
| 1/31/2003 | 2003 | 1 | 31 | 245 | 20 | 70 | 45 | 13 | 5975 |
| 2/1/2003 | 2003 | 2 | 1 | 246 | 56 | 71 | 63.5 | 31.5 | 6006.5 |
| 2/2/2003 | 2003 | 2 | 2 | 247 | 20 | 56 | 38 | 6 | 6012.5 |
| 2/3/2003 | 2003 | 2 | 3 | 248 | 17 | 61 | 39 | 7 | 6019.5 |
| 2/4/2003 | 2003 | 2 | 4 | 249 | 11 | 62 | 36.5 | 4.5 | 6024 |
| 2/5/2003 | 2003 | 2 | 5 | 250 | 9 | 51 | 30 | -2 | 6022 |
| 2/6/2003 | 2003 | 2 | 6 | 251 | 8 | 47 | 27.5 | -4.5 | 6017.5 |
| 2/7/2003 | 2003 | 2 | 7 | 252 | 15 | 43 | 29 | -3 | 6014.5 |
| 2/8/2003 | 2003 | 2 | 8 | 253 | 12 | 40 | 26 | -6 | 6008.5 |
| 2/9/2003 | 2003 | 2 | 9 | 254 | 7 | 42 | 24.5 | -7.5 | 6001 |
| 2/10/2003 | 2003 | 2 | 10 | 255 | 20 | 52 | 36 | 4 | 6005 |
| 2/11/2003 | 2003 | 2 | 11 | 256 | 20 | 56 | 38 | 6 | 6011 |
| 2/12/2003 | 2003 | 2 | 12 | 257 | 40 | 57 | 48.5 | 16.5 | 6027.5 |
| 2/13/2003 | 2003 | 2 | 13 | 258 | 35 | 58 | 46.5 | 14.5 | 6042 |
| 2/14/2003 | 2003 | 2 | 14 | 259 | 26 | 59 | 42.5 | 10.5 | 6052.5 |
| 2/15/2003 | 2003 | 2 | 15 | 260 | 23 | 60 | 41.5 | 9.5 | 6062 |
| 2/16/2003 | 2003 | 2 | 16 | 261 | 28 | 60 | 44 | 12 | 6074 |
| 2/17/2003 | 2003 | 2 | 17 | 262 | 39 | 63 | 51 | 19 | 6093 |
| 2/18/2003 | 2003 | 2 | 18 | 263 | 21 | 54 | 37.5 | 5.5 | 6098.5 |
| 2/19/2003 | 2003 | 2 | 19 | 264 | 22 | 54 | 38 | 6 | 6104.5 |
| 2/20/2003 | 2003 | 2 | 20 | 265 | 19 | 40 | 29.5 | -2.5 | 6102 |
| 2/21/2003 | 2003 | 2 | 21 | 266 | 17 | 58 | 37.5 | 5.5 | 6107.5 |
| 2/22/2003 | 2003 | 2 | 22 | 267 | 17 | 52 | 34.5 | 2.5 | 6110 |
| 2/23/2003 | 2003 | 2 | 23 | 268 | 20 | 57 | 38.5 | 6.5 | 6116.5 |
| 2/24/2003 | 2003 | 2 | 24 | 269 | 29 | 51 | 40 | 8 | 6124.5 |
| 2/25/2003 | 2003 | 2 | 25 | 270 | 28 | 51 | 39.5 | 7.5 | 6132 |
| 2/26/2003 | 2003 | 2 | 26 | 271 | 30 | 52 | 41 | 9 | 6141 |
| 2/27/2003 | 2003 | 2 | 27 | 272 | 25 | 50 | 37.5 | 5.5 | 6146.5 |
| 2/28/2003 | 2003 | 2 | 28 | 273 | 20 | 45 | 32.5 | 0.5 | 6147 |
| 3/1/2003 | 2003 | 3 | 1 | 274 | 19 | 51 | 35 | 3 | 6150 |
| 3/2/2003 | 2003 | 3 | 2 | 275 | 17 | 47 | 32 | 0 | 6150 |
| 3/3/2003 | 2003 | 3 | 3 | 276 | 32 | 57 | 44.5 | 12.5 | 6162.5 |
| 3/4/2003 | 2003 | 3 | 4 | 277 | 27 | 47 | 37 | 5 | 6167.5 |
| 3/5/2003 | 2003 | 3 | 5 | 278 | 15 | 53 | 34 | 2 | 6169.5 |
| 3/6/2003 | 2003 | 3 | 6 | 279 | 17 | 61 | 39 | 7 | 6176.5 |
| 3/7/2003 | 2003 | 3 | 7 | 280 | 23 | 68 | 45.5 | 13.5 | 6190 |
| 3/8/2003 | 2003 | 3 | 8 | 281 | 18 | 69 | 43.5 | 11.5 | 6201.5 |
| 3/9/2003 | 2003 | 3 | 9 | 282 | 19 | 74 | 46.5 | 14.5 | 6216 |
| 3/10/2003 | 2003 | 3 | 10 | 283 | 20 | 76 | 48 | 16 | 6232 |
| 3/11/2003 | 2003 | 3 | 11 | 284 | 23 | 75 | 49 | 17 | 6249 |
| 3/12/2003 | 2003 | 3 | 12 | 285 | 23 | 74 | 48.5 | 16.5 | 6265.5 |
| 3/13/2003 | 2003 | 3 | 13 | 286 | 27 | 72 | 49.5 | 17.5 | 6283 |
| 3/14/2003 | 2003 | 3 | 14 | 287 | 36 | 71 | 53.5 | 21.5 | 6304.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/15/2003 | 2003 | 3 | 15 | 288 | 35 | 68 | 51.5 | 19.5 | 6324 |
| 3/16/2003 | 2003 | 3 | 16 | 289 | 34 | 53 | 43.5 | 11.5 | 6335.5 |
| 3/17/2003 | 2003 | 3 | 17 | 290 | 35 | 49 | 42 | 10 | 6345.5 |
| 3/18/2003 | 2003 | 3 | 18 | 291 | 34 | 43 | 38.5 | 6.5 | 6352 |
| 3/19/2003 | 2003 | 3 | 19 | 292 | 26 | 46 | 36 | 4 | 6356 |
| 3/20/2003 | 2003 | 3 | 20 | 293 | 30 | 58 | 44 | 12 | 6368 |
| 3/21/2003 | 2003 | 3 | 21 | 294 | 20 | 55 | 37.5 | 5.5 | 6373.5 |
| 3/22/2003 | 2003 | 3 | 22 | 295 | 23 | 70 | 46.5 | 14.5 | 6388 |
| 3/23/2003 | 2003 | 3 | 23 | 296 | 34 | 72 | 53 | 21 | 6409 |
| 3/24/2003 | 2003 | 3 | 24 | 297 | 33 | 68 | 50.5 | 18.5 | 6427.5 |
| 3/25/2003 | 2003 | 3 | 25 | 298 | 21 | 69 | 45 | 13 | 6440.5 |
| 3/26/2003 | 2003 | 3 | 26 | 299 | 31 | 73 | 52 | 20 | 6460.5 |
| 3/27/2003 | 2003 | 3 | 27 | 300 | 14 | 53 | 33.5 | 1.5 | 6462 |
| 3/28/2003 | 2003 | 3 | 28 | 301 | 10 | 48 | 29 | -3 | 6459 |
| 3/29/2003 | 2003 | 3 | 29 | 302 | 14 | 48 | 31 | -1 | 6458 |
| 3/30/2003 | 2003 | 3 | 30 | 303 | 20 | 70 | 45 | 13 | 6471 |
| 3/31/2003 | 2003 | 3 | 31 | 304 | 34 | 77 | 55.5 | 23.5 | 6494.5 |
| 4/1/2003 | 2003 | 4 | 1 | 305 | 33 | 77 | 55 | 23 | 6517.5 |
| 4/2/2003 | 2003 | 4 | 2 | 306 | 55 | 68 | 61.5 | 29.5 | 6547 |
| 4/3/2003 | 2003 | 4 | 3 | 307 | 55 | 68 | 61.5 | 29.5 | 6576.5 |
| 4/4/2003 | 2003 | 4 | 4 | 308 | 26 | 64 | 45 | 13 | 6589.5 |
| 4/5/2003 | 2003 | 4 | 5 | 309 | 23 | 62 | 42.5 | 10.5 | 6600 |
| 4/6/2003 | 2003 | 4 | 6 | 310 | 22 | 63 | 42.5 | 10.5 | 6610.5 |
| 4/7/2003 | 2003 | 4 | 7 | 311 | 16 | 61 | 38.5 | 6.5 | 6617 |
| 4/8/2003 | 2003 | 4 | 8 | 312 | 22 | 62 | 42 | 10 | 6627 |
| 4/9/2003 | 2003 | 4 | 9 | 313 | 26 | 68 | 47 | 15 | 6642 |
| 4/10/2003 | 2003 | 4 | 10 | 314 | 34 | 81 | 57.5 | 25.5 | 6667.5 |
| 4/11/2003 | 2003 | 4 | 11 | 315 | 33 | 80 | 56.5 | 24.5 | 6692 |
| 4/12/2003 | 2003 | 4 | 12 | 316 | 42 | 78 | 60 | 28 | 6720 |
| 4/13/2003 | 2003 | 4 | 13 | 317 | 36 | 80 | 58 | 26 | 6746 |
| 4/14/2003 | 2003 | 4 | 14 | 318 | 38 | 71 | 54.5 | 22.5 | 6768.5 |
| 4/15/2003 | 2003 | 4 | 15 | 319 | 26 | 64 | 45 | 13 | 6781.5 |
| 4/16/2003 | 2003 | 4 | 16 | 320 | 24 | 76 | 50 | 18 | 6799.5 |
| 4/17/2003 | 2003 | 4 | 17 | 321 | 35 | 73 | 54 | 22 | 6821.5 |
| 4/18/2003 | 2003 | 4 | 18 | 322 | 35 | 64 | 49.5 | 17.5 | 6839 |
| 4/19/2003 | 2003 | 4 | 19 | 323 | 24 | 56 | 40 | 8 | 6847 |
| 4/20/2003 | 2003 | 4 | 20 | 324 | 45 | 65 | 55 | 23 | 6870 |
| 4/21/2003 | 2003 | 4 | 21 | 325 | 35 | 69 | 52 | 20 | 6890 |
| 4/22/2003 | 2003 | 4 | 22 | 326 | 26 | 71 | 48.5 | 16.5 | 6906.5 |
| 4/23/2003 | 2003 | 4 | 23 | 327 | 35 | 71 | 53 | 21 | 6927.5 |
| 4/24/2003 | 2003 | 4 | 24 | 328 | 32 | 71 | 51.5 | 19.5 | 6947 |
| 4/25/2003 | 2003 | 4 | 25 | 329 | 38 | 77 | 57.5 | 25.5 | 6972.5 |
| 4/26/2003 | 2003 | 4 | 26 | 330 | 36 | 78 | 57 | 25 | 6997.5 |
| 4/27/2003 | 2003 | 4 | 27 | 331 | 35 | 78 | 56.5 | 24.5 | 7022 |
| 4/28/2003 | 2003 | 4 | 28 | 332 | 31 | 78 | 54.5 | 22.5 | 7044.5 |
| 4/29/2003 | 2003 | 4 | 29 | 333 | 36 | 75 | 55.5 | 23.5 | 7068 |
| 4/30/2003 | 2003 | 4 | 30 | 334 | 28 | 70 | 49 | 17 | 7085 |
| 5/1/2003 | 2003 | 5 | 1 | 335 | 29 | 75 | 52 | 20 | 7105 |
| 5/2/2003 | 2003 | 5 | 2 | 336 | 37 | 77 | 57 | 25 | 7130 |
| 5/3/2003 | 2003 | 5 | 3 | 337 | 40 | 76 | 58 | 26 | 7156 |
| 5/4/2003 | 2003 | 5 | 4 | 338 | 42 | 70 | 56 | 24 | 7180 |
| 5/5/2003 | 2003 | 5 | 5 | 339 | 35 | 73 | 54 | 22 | 7202 |
| 5/6/2003 | 2003 | 5 | 6 | 340 | 36 | 69 | 52.5 | 20.5 | 7222.5 |
| 5/7/2003 | 2003 | 5 | 7 | 341 | 38 | 74 | 56 | 24 | 7246.5 |
| 5/8/2003 | 2003 | 5 | 8 | 342 | 46 | 74 | 60 | 28 | 7274.5 |
| 5/9/2003 | 2003 | 5 | 9 | 343 | 34 | 75 | 54.5 | 22.5 | 7297 |
| 5/10/2003 | 2003 | 5 | 10 | 344 | 25 | 75 | 50 | 18 | 7315 |
| 5/11/2003 | 2003 | 5 | 11 | 345 | 28 | 79 | 53.5 | 21.5 | 7336.5 |
| 5/12/2003 | 2003 | 5 | 12 | 346 | 45 | 84 | 64.5 | 32.5 | 7369 |
| 5/13/2003 | 2003 | 5 | 13 | 347 | 42 | 85 | 63.5 | 31.5 | 7400.5 |
| 5/14/2003 | 2003 | 5 | 14 | 348 | 48 | 79 | 63.5 | 31.5 | 7432 |
| 5/15/2003 | 2003 | 5 | 15 | 349 | 45 | 76 | 60.5 | 28.5 | 7460.5 |
| 5/16/2003 | 2003 | 5 | 16 | 350 | 40 | 88 | 64 | 32 | 7492.5 |
| 5/17/2003 | 2003 | 5 | 17 | 351 | 50 | 90 | 70 | 38 | 7530.5 |
| 5/18/2003 | 2003 | 5 | 18 | 352 | 39 | 80 | 59.5 | 27.5 | 7558 |
| 5/19/2003 | 2003 | 5 | 19 | 353 | 50 | 87 | 68.5 | 36.5 | 7594.5 |
| 5/20/2003 | 2003 | 5 | 20 | 354 | 48 | 68 | 58 | 26 | 7620.5 |
| 5/21/2003 | 2003 | 5 | 21 | 355 | 42 | 90 | 66 | 34 | 7654.5 |
| 5/22/2003 | 2003 | 5 | 22 | 356 | 50 | 91 | 70.5 | 38.5 | 7693 |
| 5/23/2003 | 2003 | 5 | 23 | 357 | 47 | 87 | 67 | 35 | 7728 |
| 5/24/2003 | 2003 | 5 | 24 | 358 | 57 | 90 | 73.5 | 41.5 | 7769.5 |
| 5/25/2003 | 2003 | 5 | 25 | 359 | 50 | 80 | 65 | 33 | 7802.5 |
| 5/26/2003 | 2003 | 5 | 26 | 360 | 49 | 90 | 69.5 | 37.5 | 7840 |
| 5/27/2003 | 2003 | 5 | 27 | 361 | 49 | 86 | 67.5 | 35.5 | 7875.5 |
| 5/28/2003 | 2003 | 5 | 28 | 362 | 51 | 86 | 68.5 | 36.5 | 7912 |
| 5/29/2003 | 2003 | 5 | 29 | 363 | 50 | 91 | 70.5 | 38.5 | 7950.5 |
| 5/30/2003 | 2003 | 5 | 30 | 364 | 54 | 92 | 73 | 41 | 7991.5 |
| 5/31/2003 | 2003 | 5 | 31 | 365 | 52 | 88 | 70 | 38 | 8029.5 |
| 6/1/2003 | 2003 | 6 | 1 | 1 | 46 | 92 | 69 | 37 | 37 |
| 6/2/2003 | 2003 | 6 | 2 | 2 | 54 | 92 | 73 | 41 | 78 |
| 6/3/2003 | 2003 | 6 | 3 | 3 | 48 | 93 | 70.5 | 38.5 | 116.5 |
| 6/4/2003 | 2003 | 6 | 4 | 4 | 54 | 93 | 73.5 | 41.5 | 158 |
| 6/5/2003 | 2003 | 6 | 5 | 5 | 54 | 92 | 73 | 41 | 199 |
| 6/6/2003 | 2003 | 6 | 6 | 6 | 50 | 83 | 66.5 | 34.5 | 233.5 |
| 6/7/2003 | 2003 | 6 | 7 | 7 | 49 | 90 | 69.5 | 37.5 | 271 |
| 6/8/2003 | 2003 | 6 | 8 | 8 | 48 | 94 | 71 | 39 | 310 |
| 6/9/2003 | 2003 | 6 | 9 | 9 | 50 | 86 | 68 | 36 | 346 |
| 6/10/2003 | 2003 | 6 | 10 | 10 | 46 | 88 | 67 | 35 | 381 |
| 6/11/2003 | 2003 | 6 | 11 | 11 | 51 | 86 | 68.5 | 36.5 | 417.5 |
| 6/12/2003 | 2003 | 6 | 12 | 12 | 51 | 91 | 71 | 39 | 456.5 |
| 6/13/2003 | 2003 | 6 | 13 | 13 | 51 | 91 | 71 | 39 | 495.5 |
| 6/14/2003 | 2003 | 6 | 14 | 14 | 59 | 94 | 76.5 | 44.5 | 540 |
| 6/15/2003 | 2003 | 6 | 15 | 15 | 63 | 95 | 79 | 47 | 587 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/16/2003 | 2003 | 6 | 16 | 16 | 60 | 86 | 73 | 41 | 628 |
| 6/17/2003 | 2003 | 6 | 17 | 17 | 52 | 82 | 67 | 35 | 663 |
| 6/18/2003 | 2003 | 6 | 18 | 18 | 53 | 77 | 65 | 33 | 696 |
| 6/19/2003 | 2003 | 6 | 19 | 19 | 52 | 80 | 66 | 34 | 730 |
| 6/20/2003 | 2003 | 6 | 20 | 20 | 48 | 84 | 66 | 34 | 764 |
| 6/21/2003 | 2003 | 6 | 21 | 21 | 47 | 89 | 68 | 36 | 800 |
| 6/22/2003 | 2003 | 6 | 22 | 22 | 45 | 90 | 67.5 | 35.5 | 835.5 |
| 6/23/2003 | 2003 | 6 | 23 | 23 | 50 | 93 | 71.5 | 39.5 | 875 |
| 6/24/2003 | 2003 | 6 | 24 | 24 | 51 | 90 | 70.5 | 38.5 | 913.5 |
| 6/25/2003 | 2003 | 6 | 25 | 25 | 45 | 90 | 67.5 | 35.5 | 949 |
| 6/26/2003 | 2003 | 6 | 26 | 26 | 57 | 91 | 74 | 42 | 991 |
| 6/27/2003 | 2003 | 6 | 27 | 27 | 47 | 96 | 71.5 | 39.5 | 1030.5 |
| 6/28/2003 | 2003 | 6 | 28 | 28 | 50 | 94 | 72 | 40 | 1070.5 |
| 6/29/2003 | 2003 | 6 | 29 | 29 | 61 | 98 | 79.5 | 47.5 | 1118 |
| 6/30/2003 | 2003 | 6 | 30 | 30 | 58 | 97 | 77.5 | 45.5 | 1163.5 |
| 7/1/2003 | 2003 | 7 | 1 | 31 | 54 | 99 | 76.5 | 44.5 | 1208 |
| 7/2/2003 | 2003 | 7 | 2 | 32 | 64 | 100 | 82 | 50 | 1258 |
| 7/3/2003 | 2003 | 7 | 3 | 33 | 54 | 101 | 77.5 | 45.5 | 1303.5 |
| 7/4/2003 | 2003 | 7 | 4 | 34 | 51 | 102 | 76.5 | 44.5 | 1348 |
| 7/5/2003 | 2003 | 7 | 5 | 35 | 60 | 104 | 82 | 50 | 1398 |
| 7/6/2003 | 2003 | 7 | 6 | 36 | 56 | 100 | 78 | 46 | 1444 |
| 7/7/2003 | 2003 | 7 | 7 | 37 | 60 | 100 | 80 | 48 | 1492 |
| 7/8/2003 | 2003 | 7 | 8 | 38 | 50 | 103 | 76.5 | 44.5 | 1536.5 |
| 7/9/2003 | 2003 | 7 | 9 | 39 | 53 | 105 | 79 | 47 | 1583.5 |
| 7/10/2003 | 2003 | 7 | 10 | 40 | 63 | 102 | 82.5 | 50.5 | 1634 |
| 7/11/2003 | 2003 | 7 | 11 | 41 | 64 | 99 | 81.5 | 49.5 | 1683.5 |
| 7/12/2003 | 2003 | 7 | 12 | 42 | 56 | 102 | 79 | 47 | 1730.5 |
| 7/13/2003 | 2003 | 7 | 13 | 43 | 59 | 103 | 81 | 49 | 1779.5 |
| 7/14/2003 | 2003 | 7 | 14 | 44 | 65 | 106 | 85.5 | 53.5 | 1833 |
| 7/15/2003 | 2003 | 7 | 15 | 45 | 65 | 100 | 82.5 | 50.5 | 1883.5 |
| 7/16/2003 | 2003 | 7 | 16 | 46 | 63 | 95 | 79 | 47 | 1930.5 |
| 7/17/2003 | 2003 | 7 | 17 | 47 | 60 | 90 | 75 | 43 | 1973.5 |
| 7/18/2003 | 2003 | 7 | 18 | 48 | 60 | 97 | 78.5 | 46.5 | 2020 |
| 7/19/2003 | 2003 | 7 | 19 | 49 | 56 | 101 | 78.5 | 46.5 | 2066.5 |
| 7/20/2003 | 2003 | 7 | 20 | 50 | 57 | 100 | 78.5 | 46.5 | 2113 |
| 7/21/2003 | 2003 | 7 | 21 | 51 | 57 | 100 | 78.5 | 46.5 | 2159.5 |
| 7/22/2003 | 2003 | 7 | 22 | 52 | 67 | 96 | 81.5 | 49.5 | 2209 |
| 7/23/2003 | 2003 | 7 | 23 | 53 | 62 | 98 | 80 | 48 | 2257 |
| 7/24/2003 | 2003 | 7 | 24 | 54 | 62 | 100 | 81 | 49 | 2306 |
| 7/25/2003 | 2003 | 7 | 25 | 55 | 66 | 97 | 81.5 | 49.5 | 2355.5 |
| 7/26/2003 | 2003 | 7 | 26 | 56 | 59 | 99 | 79 | 47 | 2402.5 |
| 7/27/2003 | 2003 | 7 | 27 | 57 | 59 | 88 | 73.5 | 41.5 | 2444 |
| 7/28/2003 | 2003 | 7 | 28 | 58 | 60 | 89 | 74.5 | 42.5 | 2486.5 |
| 7/29/2003 | 2003 | 7 | 29 | 59 | 60 | 90 | 75 | 43 | 2529.5 |
| 7/30/2003 | 2003 | 7 | 30 | 60 | 60 | 90 | 75 | 43 | 2572.5 |
| 7/31/2003 | 2003 | 7 | 31 | 61 | 60 | 91 | 75.5 | 43.5 | 2616 |
| 8/1/2003 | 2003 | 8 | 1 | 62 | 58 | 98 | 78 | 46 | 2662 |
| 8/2/2003 | 2003 | 8 | 2 | 63 | 55 | 95 | 75 | 43 | 2705 |
| 8/3/2003 | 2003 | 8 | 3 | 64 | 52 | 89 | 70.5 | 38.5 | 2743.5 |
| 8/4/2003 | 2003 | 8 | 4 | 65 | 54 | 96 | 75 | 43 | 2786.5 |
| 8/5/2003 | 2003 | 8 | 5 | 66 | 60 | 94 | 77 | 45 | 2831.5 |
| 8/6/2003 | 2003 | 8 | 6 | 67 | 61 | 93 | 77 | 45 | 2876.5 |
| 8/7/2003 | 2003 | 8 | 7 | 68 | 60 | 95 | 77.5 | 45.5 | 2922 |
| 8/8/2003 | 2003 | 8 | 8 | 69 | 62 | 97 | 79.5 | 47.5 | 2969.5 |
| 8/9/2003 | 2003 | 8 | 9 | 70 | 60 | 100 | 80 | 48 | 3017.5 |
| 8/10/2003 | 2003 | 8 | 10 | 71 | 56 | 97 | 76.5 | 44.5 | 3062 |
| 8/11/2003 | 2003 | 8 | 11 | 72 | 58 | 93 | 75.5 | 43.5 | 3105.5 |
| 8/12/2003 | 2003 | 8 | 12 | 73 | 58 | 93 | 75.5 | 43.5 | 3149 |
| 8/13/2003 | 2003 | 8 | 13 | 74 | 60 | 87 | 73.5 | 41.5 | 3190.5 |
| 8/14/2003 | 2003 | 8 | 14 | 75 | 55 | 87 | 71 | 39 | 3229.5 |
| 8/15/2003 | 2003 | 8 | 15 | 76 | 51 | 78 | 64.5 | 32.5 | 3262 |
| 8/16/2003 | 2003 | 8 | 16 | 77 | 52 | 75 | 63.5 | 31.5 | 3293.5 |
| 8/17/2003 | 2003 | 8 | 17 | 78 | 52 | 88 | 70 | 38 | 3331.5 |
| 8/18/2003 | 2003 | 8 | 18 | 79 | 52 | 93 | 72.5 | 40.5 | 3372 |
| 8/19/2003 | 2003 | 8 | 19 | 80 | 52 | 93 | 72.5 | 40.5 | 3412.5 |
| 8/20/2003 | 2003 | 8 | 20 | 81 | 53 | 94 | 73.5 | 41.5 | 3454 |
| 8/21/2003 | 2003 | 8 | 21 | 82 | 58 | 95 | 76.5 | 44.5 | 3498.5 |
| 8/22/2003 | 2003 | 8 | 22 | 83 | 60 | 91 | 75.5 | 43.5 | 3542 |
| 8/23/2003 | 2003 | 8 | 23 | 84 | 58 | 89 | 73.5 | 41.5 | 3583.5 |
| 8/24/2003 | 2003 | 8 | 24 | 85 | 60 | 90 | 75 | 43 | 3626.5 |
| 8/25/2003 | 2003 | 8 | 25 | 86 | 56 | 87 | 71.5 | 39.5 | 3666 |
| 8/26/2003 | 2003 | 8 | 26 | 87 | 60 | 85 | 72.5 | 40.5 | 3706.5 |
| 8/27/2003 | 2003 | 8 | 27 | 88 | 55 | 84 | 69.5 | 37.5 | 3744 |
| 8/28/2003 | 2003 | 8 | 28 | 89 | 57 | 82 | 69.5 | 37.5 | 3781.5 |
| 8/29/2003 | 2003 | 8 | 29 | 90 | 58 | 86 | 72 | 40 | 3821.5 |
| 8/30/2003 | 2003 | 8 | 30 | 91 | 55 | 79 | 67 | 35 | 3856.5 |
| 8/31/2003 | 2003 | 8 | 31 | 92 | 58 | 90 | 74 | 42 | 3898.5 |
| 9/1/2003 | 2003 | 9 | 1 | 93 | 58 | 92 | 75 | 43 | 3941.5 |
| 9/2/2003 | 2003 | 9 | 2 | 94 | 54 | 91 | 72.5 | 40.5 | 3982 |
| 9/3/2003 | 2003 | 9 | 3 | 95 | 56 | 88 | 72 | 40 | 4022 |
| 9/4/2003 | 2003 | 9 | 4 | 96 | 55 | 78 | 66.5 | 34.5 | 4056.5 |
| 9/5/2003 | 2003 | 9 | 5 | 97 | 51 | 76 | 63.5 | 31.5 | 4088 |
| 9/6/2003 | 2003 | 9 | 6 | 98 | 47 | 82 | 64.5 | 32.5 | 4120.5 |
| 9/7/2003 | 2003 | 9 | 7 | 99 | 46 | 83 | 64.5 | 32.5 | 4153 |
| 9/8/2003 | 2003 | 9 | 8 | 100 | 55 | 86 | 70.5 | 38.5 | 4191.5 |
| 9/9/2003 | 2003 | 9 | 9 | 101 | 55 | 79 | 67 | 35 | 4226.5 |
| 9/10/2003 | 2003 | 9 | 10 | 102 | 43 | 72 | 57.5 | 25.5 | 4252 |
| 9/11/2003 | 2003 | 9 | 11 | 103 | 40 | 75 | 57.5 | 25.5 | 4277.5 |
| 9/12/2003 | 2003 | 9 | 12 | 104 | 43 | 83 | 63 | 31 | 4308.5 |
| 9/13/2003 | 2003 | 9 | 13 | 105 | 44 | 86 | 65 | 33 | 4341.5 |
| 9/14/2003 | 2003 | 9 | 14 | 106 | 46 | 88 | 67 | 35 | 4376.5 |
| 9/15/2003 | 2003 | 9 | 15 | 107 | 43 | 88 | 65.5 | 33.5 | 4410 |
| 9/16/2003 | 2003 | 9 | 16 | 108 | 48 | 88 | 68 | 36 | 4446 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/17/2003 | 2003 | 9 | 17 | 109 | 48 | 86 | 67 | 35 | 4481 |
| 9/18/2003 | 2003 | 9 | 18 | 110 | 43 | 84 | 63.5 | 31.5 | 4512.5 |
| 9/19/2003 | 2003 | 9 | 19 | 111 | 41 | 88 | 64.5 | 32.5 | 4545 |
| 9/20/2003 | 2003 | 9 | 20 | 112 | 37 | 88 | 62.5 | 30.5 | 4575.5 |
| 9/21/2003 | 2003 | 9 | 21 | 113 | 43 | 83 | 63 | 31 | 4606.5 |
| 9/22/2003 | 2003 | 9 | 22 | 114 | 50 | 86 | 68 | 36 | 4642.5 |
| 9/23/2003 | 2003 | 9 | 23 | 115 | 44 | 90 | 67 | 35 | 4677.5 |
| 9/24/2003 | 2003 | 9 | 24 | 116 | 52 | 85 | 68.5 | 36.5 | 4714 |
| 9/25/2003 | 2003 | 9 | 25 | 117 | 38 | 85 | 61.5 | 29.5 | 4743.5 |
| 9/26/2003 | 2003 | 9 | 26 | 118 | 38 | 88 | 63 | 31 | 4774.5 |
| 9/27/2003 | 2003 | 9 | 27 | 119 | 40 | 88 | 64 | 32 | 4806.5 |
| 9/28/2003 | 2003 | 9 | 28 | 120 | 45 | 90 | 67.5 | 35.5 | 4842 |
| 9/29/2003 | 2003 | 9 | 29 | 121 | 41 | 92 | 66.5 | 34.5 | 4876.5 |
| 9/30/2003 | 2003 | 9 | 30 | 122 | 47 | 91 | 69 | 37 | 4913.5 |
| 10/1/2003 | 2003 | 10 | 1 | 123 | 54 | 89 | 71.5 | 39.5 | 4953 |
| 10/2/2003 | 2003 | 10 | 2 | 124 | 50 | 80 | 65 | 33 | 4986 |
| 10/3/2003 | 2003 | 10 | 3 | 125 | 45 | 79 | 62 | 30 | 5016 |
| 10/4/2003 | 2003 | 10 | 4 | 126 | 41 | 73 | 57 | 25 | 5041 |
| 10/5/2003 | 2003 | 10 | 5 | 127 | 40 | 79 | 59.5 | 27.5 | 5068.5 |
| 10/6/2003 | 2003 | 10 | 6 | 128 | 45 | 78 | 61.5 | 29.5 | 5098 |
| 10/7/2003 | 2003 | 10 | 7 | 129 | 49 | 68 | 58.5 | 26.5 | 5124.5 |
| 10/8/2003 | 2003 | 10 | 8 | 130 | 41 | 76 | 58.5 | 26.5 | 5151 |
| 10/9/2003 | 2003 | 10 | 9 | 131 | 42 | 78 | 60 | 28 | 5179 |
| 10/10/2003 | 2003 | 10 | 10 | 132 | 46 | 78 | 62 | 30 | 5209 |
| 10/11/2003 | 2003 | 10 | 11 | 133 | 45 | 81 | 63 | 31 | 5240 |
| 10/12/2003 | 2003 | 10 | 12 | 134 | 41 | 83 | 62 | 30 | 5270 |
| 10/13/2003 | 2003 | 10 | 13 | 135 | 27 | 79 | 53 | 21 | 5291 |
| 10/14/2003 | 2003 | 10 | 14 | 136 | 31 | 73 | 52 | 20 | 5311 |
| 10/15/2003 | 2003 | 10 | 15 | 137 | 27 | 84 | 55.5 | 23.5 | 5334.5 |
| 10/16/2003 | 2003 | 10 | 16 | 138 | 34 | 80 | 57 | 25 | 5359.5 |
| 10/17/2003 | 2003 | 10 | 17 | 139 | 35 | 81 | 58 | 26 | 5385.5 |
| 10/18/2003 | 2003 | 10 | 18 | 140 | 35 | 84 | 59.5 | 27.5 | 5413 |
| 10/19/2003 | 2003 | 10 | 19 | 141 | 36 | 89 | 62.5 | 30.5 | 5443.5 |
| 10/20/2003 | 2003 | 10 | 20 | 142 | 33 | 83 | 58 | 26 | 5469.5 |
| 10/21/2003 | 2003 | 10 | 21 | 143 | 33 | 83 | 58 | 26 | 5495.5 |
| 10/22/2003 | 2003 | 10 | 22 | 144 | 34 | 83 | 58.5 | 26.5 | 5522 |
| 10/23/2003 | 2003 | 10 | 23 | 145 | 33 | 87 | 60 | 28 | 5550 |
| 10/24/2003 | 2003 | 10 | 24 | 146 | 31 | 76 | 53.5 | 21.5 | 5571.5 |
| 10/25/2003 | 2003 | 10 | 25 | 147 | 20 | 62 | 41 | 9 | 5580.5 |
| 10/26/2003 | 2003 | 10 | 26 | 148 | 20 | 64 | 42 | 10 | 5590.5 |
| 10/27/2003 | 2003 | 10 | 27 | 149 | 32 | 72 | 52 | 20 | 5610.5 |
| 10/28/2003 | 2003 | 10 | 28 | 150 | 30 | 77 | 53.5 | 21.5 | 5632 |
| 10/29/2003 | 2003 | 10 | 29 | 151 | 42 | 76 | 59 | 27 | 5659 |
| 10/30/2003 | 2003 | 10 | 30 | 152 | 40 | 74 | 57 | 25 | 5684 |
| 10/31/2003 | 2003 | 10 | 31 | 153 | 37 | 72 | 54.5 | 22.5 | 5706.5 |
| 11/1/2003 | 2003 | 11 | 1 | 154 | 33 | 70 | 51.5 | 19.5 | 5726 |
| 11/2/2003 | 2003 | 11 | 2 | 155 | 38 | 69 | 53.5 | 21.5 | 5747.5 |
| 11/3/2003 | 2003 | 11 | 3 | 156 | 22 | 59 | 40.5 | 8.5 | 5756 |
| 11/4/2003 | 2003 | 11 | 4 | 157 | 15 | 58 | 36.5 | 4.5 | 5760.5 |
| 11/5/2003 | 2003 | 11 | 5 | 158 | 17 | 63 | 40 | 8 | 5768.5 |
| 11/6/2003 | 2003 | 11 | 6 | 159 | 20 | 63 | 41.5 | 9.5 | 5778 |
| 11/7/2003 | 2003 | 11 | 7 | 160 | 25 | 59 | 42 | 10 | 5788 |
| 11/8/2003 | 2003 | 11 | 8 | 161 | 25 | 59 | 42 | 10 | 5798 |
| 11/9/2003 | 2003 | 11 | 9 | 162 | 32 | 72 | 52 | 20 | 5818 |
| 11/10/2003 | 2003 | 11 | 10 | 163 | 38 | 72 | 55 | 23 | 5841 |
| 11/11/2003 | 2003 | 11 | 11 | 164 | 44 | 66 | 55 | 23 | 5864 |
| 11/12/2003 | 2003 | 11 | 12 | 165 | 34 | 52 | 43 | 11 | 5875 |
| 11/13/2003 | 2003 | 11 | 13 | 166 | 34 | 37 | 35.5 | 3.5 | 5878.5 |
| 11/14/2003 | 2003 | 11 | 14 | 167 | 25 | 61 | 43 | 11 | 5889.5 |
| 11/15/2003 | 2003 | 11 | 15 | 168 | 22 | 59 | 40.5 | 8.5 | 5898 |
| 11/16/2003 | 2003 | 11 | 16 | 169 | 22 | 59 | 40.5 | 8.5 | 5906.5 |
| 11/17/2003 | 2003 | 11 | 17 | 170 | 27 | 53 | 40 | 8 | 5914.5 |
| 11/18/2003 | 2003 | 11 | 18 | 171 | 21 | 58 | 39.5 | 7.5 | 5922 |
| 11/19/2003 | 2003 | 11 | 19 | 172 | 20 | 66 | 43 | 11 | 5933 |
| 11/20/2003 | 2003 | 11 | 20 | 173 | 20 | 70 | 45 | 13 | 5946 |
| 11/21/2003 | 2003 | 11 | 21 | 174 | 20 | 66 | 43 | 11 | 5957 |
| 11/22/2003 | 2003 | 11 | 22 | 175 | 12 | 54 | 33 | 1 | 5958 |
| 11/23/2003 | 2003 | 11 | 23 | 176 | 10 | 53 | 31.5 | -0.5 | 5957.5 |
| 11/24/2003 | 2003 | 11 | 24 | 177 | 15 | 52 | 33.5 | 1.5 | 5959 |
| 11/25/2003 | 2003 | 11 | 25 | 178 | 27 | 59 | 43 | 11 | 5970 |
| 11/26/2003 | 2003 | 11 | 26 | 179 | 19 | 57 | 38 | 6 | 5976 |
| 11/27/2003 | 2003 | 11 | 27 | 180 | 10 | 43 | 26.5 | -5.5 | 5970.5 |
| 11/28/2003 | 2003 | 11 | 28 | 181 | 12 | 50 | 31 | -1 | 5969.5 |
| 11/29/2003 | 2003 | 11 | 29 | 182 | 21 | 67 | 44 | 12 | 5981.5 |
| 11/30/2003 | 2003 | 11 | 30 | 183 | 15 | 73 | 44 | 12 | 5993.5 |
| 12/1/2003 | 2003 | 12 | 1 | 184 | 32 | 61 | 46.5 | 14.5 | 6008 |
| 12/2/2003 | 2003 | 12 | 2 | 185 | 15 | 61 | 38 | 6 | 6014 |
| 12/3/2003 | 2003 | 12 | 3 | 186 | 15 | 59 | 37 | 5 | 6019 |
| 12/4/2003 | 2003 | 12 | 4 | 187 | 15 | 59 | 37 | 5 | 6024 |
| 12/5/2003 | 2003 | 12 | 5 | 188 | 20 | 46 | 33 | 1 | 6025 |
| 12/6/2003 | 2003 | 12 | 6 | 189 | 32 | 68 | 50 | 18 | 6043 |
| 12/7/2003 | 2003 | 12 | 7 | 190 | 31 | 64 | 47.5 | 15.5 | 6058.5 |
| 12/8/2003 | 2003 | 12 | 8 | 191 | 20 | 43 | 31.5 | -0.5 | 6058 |
| 12/9/2003 | 2003 | 12 | 9 | 192 | 11 | 44 | 27.5 | -4.5 | 6053.5 |
| 12/10/2003 | 2003 | 12 | 10 | 193 | 13 | 58 | 35.5 | 3.5 | 6057 |
| 12/11/2003 | 2003 | 12 | 11 | 194 | 26 | 52 | 39 | 7 | 6064 |
| 12/12/2003 | 2003 | 12 | 12 | 195 | 17 | 57 | 37 | 5 | 6069 |
| 12/13/2003 | 2003 | 12 | 13 | 196 | 17 | 57 | 37 | 5 | 6074 |
| 12/14/2003 | 2003 | 12 | 14 | 197 | 17 | 57 | 37 | 5 | 6079 |
| 12/15/2003 | 2003 | 12 | 15 | 198 | 10 | 37 | 23.5 | -8.5 | 6070.5 |
| 12/16/2003 | 2003 | 12 | 16 | 199 | 10 | 42 | 26 | -6 | 6064.5 |
| 12/17/2003 | 2003 | 12 | 17 | 200 | 15 | 57 | 36 | 4 | 6068.5 |
| 12/18/2003 | 2003 | 12 | 18 | 201 | 15 | 57 | 36 | 4 | 6072.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/19/2003 | 2003 | 12 | 19 | 202 | 16 | 60 | 38 | 6 | 6078.5 |
| 12/20/2003 | 2003 | 12 | 20 | 203 | 22 | 67 | 44.5 | 12.5 | 6091 |
| 12/21/2003 | 2003 | 12 | 21 | 204 | 23 | 58 | 40.5 | 8.5 | 6099.5 |
| 12/22/2003 | 2003 | 12 | 22 | 205 | 13 | 46 | 29.5 | -2.5 | 6097 |
| 12/23/2003 | 2003 | 12 | 23 | 206 | 17 | 50 | 33.5 | 1.5 | 6098.5 |
| 12/24/2003 | 2003 | 12 | 24 | 207 | 22 | 57 | 39.5 | 7.5 | 6106 |
| 12/25/2003 | 2003 | 12 | 25 | 208 | 29 | 55 | 42 | 10 | 6116 |
| 12/26/2003 | 2003 | 12 | 26 | 209 | 16 | 51 | 33.5 | 1.5 | 6117.5 |
| 12/27/2003 | 2003 | 12 | 27 | 210 | 4 | 30 | 17 | -15 | 6102.5 |
| 12/28/2003 | 2003 | 12 | 28 | 211 | 1 | 31 | 16 | -16 | 6086.5 |
| 12/29/2003 | 2003 | 12 | 29 | 212 | 17 | 50 | 33.5 | 1.5 | 6088 |
| 12/30/2003 | 2003 | 12 | 30 | 213 | 16 | 51 | 33.5 | 1.5 | 6089.5 |
| 12/31/2003 | 2003 | 12 | 31 | 214 | 27 | 42 | 34.5 | 2.5 | 6092 |
| 1/1/2004 | 2004 | 1 | 1 | 215 | 31 | 56 | 43.5 | 11.5 | 6103.5 |
| 1/2/2004 | 2004 | 1 | 2 | 216 | 32 | 60 | 46 | 14 | 6117.5 |
| 1/3/2004 | 2004 | 1 | 3 | 217 | 3 | 52 | 27.5 | -4.5 | 6113 |
| 1/4/2004 | 2004 | 1 | 4 | 218 | 6 | 40 | 23 | -9 | 6104 |
| 1/5/2004 | 2004 | 1 | 5 | 219 | 6 | 37 | 21.5 | -10.5 | 6093.5 |
| 1/6/2004 | 2004 | 1 | 6 | 220 | 19 | 48 | 33.5 | 1.5 | 6095 |
| 1/7/2004 | 2004 | 1 | 7 | 221 | 20 | 59 | 39.5 | 7.5 | 6102.5 |
| 1/8/2004 | 2004 | 1 | 8 | 222 | 15 | 60 | 37.5 | 5.5 | 6108 |
| 1/9/2004 | 2004 | 1 | 9 | 223 | 12 | 61 | 36.5 | 4.5 | 6112.5 |
| 1/10/2004 | 2004 | 1 | 10 | 224 | 15 | 55 | 35 | 3 | 6115.5 |
| 1/11/2004 | 2004 | 1 | 11 | 225 | 17 | 58 | 37.5 | 5.5 | 6121 |
| 1/12/2004 | 2004 | 1 | 12 | 226 | 16 | 59 | 37.5 | 5.5 | 6126.5 |
| 1/13/2004 | 2004 | 1 | 13 | 227 | 18 | 60 | 39 | 7 | 6133.5 |
| 1/14/2004 | 2004 | 1 | 14 | 228 | 27 | 47 | 37 | 5 | 6138.5 |
| 1/15/2004 | 2004 | 1 | 15 | 229 | 32 | 40 | 36 | 4 | 6142.5 |
| 1/16/2004 | 2004 | 1 | 16 | 230 | 32 | 40 | 36 | 4 | 6146.5 |
| 1/17/2004 | 2004 | 1 | 17 | 231 | 19 | 47 | 33 | 1 | 6147.5 |
| 1/18/2004 | 2004 | 1 | 18 | 232 | 15 | 56 | 35.5 | 3.5 | 6151 |
| 1/19/2004 | 2004 | 1 | 19 | 233 | 29 | 54 | 41.5 | 9.5 | 6160.5 |
| 1/20/2004 | 2004 | 1 | 20 | 234 | 17 | 44 | 30.5 | -1.5 | 6159 |
| 1/21/2004 | 2004 | 1 | 21 | 235 | 16 | 47 | 31.5 | -0.5 | 6158.5 |
| 1/22/2004 | 2004 | 1 | 22 | 236 | 16 | 53 | 34.5 | 2.5 | 6161 |
| 1/23/2004 | 2004 | 1 | 23 | 237 | 16 | 58 | 37 | 5 | 6166 |
| 1/24/2004 | 2004 | 1 | 24 | 238 | 31 | 53 | 42 | 10 | 6176 |
| 1/25/2004 | 2004 | 1 | 25 | 239 | 8 | 45 | 26.5 | -5.5 | 6170.5 |
| 1/26/2004 | 2004 | 1 | 26 | 240 | 6 | 33 | 19.5 | -12.5 | 6158 |
| 1/27/2004 | 2004 | 1 | 27 | 241 | 12 | 47 | 29.5 | -2.5 | 6155.5 |
| 1/28/2004 | 2004 | 1 | 28 | 242 | 18 | 56 | 37 | 5 | 6160.5 |
| 1/29/2004 | 2004 | 1 | 29 | 243 | 15 | 60 | 37.5 | 5.5 | 6166 |
| 1/30/2004 | 2004 | 1 | 30 | 244 | 29 | 59 | 44 | 12 | 6178 |
| 1/31/2004 | 2004 | 1 | 31 | 245 | 16 | 47 | 31.5 | -0.5 | 6177.5 |
| 2/1/2004 | 2004 | 2 | 1 | 246 | 16 | 47 | 31.5 | -0.5 | 6177 |
| 2/2/2004 | 2004 | 2 | 2 | 247 | 5 | 38 | 21.5 | -10.5 | 6166.5 |
| 2/3/2004 | 2004 | 2 | 3 | 248 | 20 | 50 | 35 | 3 | 6169.5 |
| 2/4/2004 | 2004 | 2 | 4 | 249 | 25 | 34 | 29.5 | -2.5 | 6167 |
| 2/5/2004 | 2004 | 2 | 5 | 250 | 10 | 40 | 25 | -7 | 6160 |
| 2/6/2004 | 2004 | 2 | 6 | 251 | 9 | 41 | 25 | -7 | 6153 |
| 2/7/2004 | 2004 | 2 | 7 | 252 | 7 | 47 | 27 | -5 | 6148 |
| 2/8/2004 | 2004 | 2 | 8 | 253 | 15 | 46 | 30.5 | -1.5 | 6146.5 |
| 2/9/2004 | 2004 | 2 | 9 | 254 | 9 | 45 | 27 | -5 | 6141.5 |
| 2/10/2004 | 2004 | 2 | 10 | 255 | 17 | 45 | 31 | -1 | 6140.5 |
| 2/11/2004 | 2004 | 2 | 11 | 256 | 12 | 48 | 30 | -2 | 6138.5 |
| 2/12/2004 | 2004 | 2 | 12 | 257 | 19 | 48 | 33.5 | 1.5 | 6140 |
| 2/13/2004 | 2004 | 2 | 13 | 258 | 4 | 27 | 15.5 | -16.5 | 6123.5 |
| 2/14/2004 | 2004 | 2 | 14 | 259 | 8 | 37 | 22.5 | -9.5 | 6114 |
| 2/15/2004 | 2004 | 2 | 15 | 260 | 15 | 54 | 34.5 | 2.5 | 6116.5 |
| 2/16/2004 | 2004 | 2 | 16 | 261 | 14 | 57 | 35.5 | 3.5 | 6120 |
| 2/17/2004 | 2004 | 2 | 17 | 262 | 17 | 59 | 38 | 6 | 6126 |
| 2/18/2004 | 2004 | 2 | 18 | 263 | 23 | 68 | 45.5 | 13.5 | 6139.5 |
| 2/19/2004 | 2004 | 2 | 19 | 264 | 44 | 68 | 56 | 24 | 6163.5 |
| 2/20/2004 | 2004 | 2 | 20 | 265 | 22 | 58 | 40 | 8 | 6171.5 |
| 2/21/2004 | 2004 | 2 | 21 | 266 | 35 | 54 | 44.5 | 12.5 | 6184 |
| 2/22/2004 | 2004 | 2 | 22 | 267 | 22 | 53 | 37.5 | 5.5 | 6189.5 |
| 2/23/2004 | 2004 | 2 | 23 | 268 | 18 | 55 | 36.5 | 4.5 | 6194 |
| 2/24/2004 | 2004 | 2 | 24 | 269 | 27 | 46 | 36.5 | 4.5 | 6198.5 |
| 2/25/2004 | 2004 | 2 | 25 | 270 | 20 | 45 | 32.5 | 0.5 | 6199 |
| 2/26/2004 | 2004 | 2 | 26 | 271 | 18 | 55 | 36.5 | 4.5 | 6203.5 |
| 2/27/2004 | 2004 | 2 | 27 | 272 | 22 | 62 | 42 | 10 | 6213.5 |
| 2/28/2004 | 2004 | 2 | 28 | 273 | 25 | 60 | 42.5 | 10.5 | 6224 |
| 2/29/2004 | 2004 | 2 | 29 | 274 | 24 | 42 | 33 | 1 | 6225 |
| 3/1/2004 | 2004 | 3 | 1 | 275 | 20 | 44 | 32 | 0 | 6225 |
| 3/2/2004 | 2004 | 3 | 2 | 276 | 27 | 54 | 40.5 | 8.5 | 6233.5 |
| 3/3/2004 | 2004 | 3 | 3 | 277 | 30 | 39 | 34.5 | 2.5 | 6236 |
| 3/4/2004 | 2004 | 3 | 4 | 278 | 32 | 53 | 42.5 | 10.5 | 6246.5 |
| 3/5/2004 | 2004 | 3 | 5 | 279 | 28 | 53 | 40.5 | 8.5 | 6255 |
| 3/7/2004 | 2004 | 3 | 7 | 280 | 24 | 63 | 43.5 | 11.5 | 6266.5 |
| 3/8/2004 | 2004 | 3 | 8 | 281 | 25 | 69 | 47 | 15 | 6281.5 |
| 3/9/2004 | 2004 | 3 | 9 | 282 | 33 | 74 | 53.5 | 21.5 | 6303 |
| 3/10/2004 | 2004 | 3 | 10 | 283 | 29 | 67 | 48 | 16 | 6319 |
| 3/11/2004 | 2004 | 3 | 11 | 284 | 40 | 74 | 57 | 25 | 6344 |
| 3/12/2004 | 2004 | 3 | 12 | 285 | 29 | 58 | 43.5 | 11.5 | 6355.5 |
| 3/13/2004 | 2004 | 3 | 13 | 286 | 26 | 70 | 48 | 16 | 6371.5 |
| 3/14/2004 | 2004 | 3 | 14 | 287 | 35 | 70 | 52.5 | 20.5 | 6392 |
| 3/15/2004 | 2004 | 3 | 15 | 288 | 35 | 70 | 52.5 | 20.5 | 6412.5 |
| 3/16/2004 | 2004 | 3 | 16 | 289 | 23 | 69 | 46 | 14 | 6426.5 |
| 3/17/2004 | 2004 | 3 | 17 | 290 | 23 | 73 | 48 | 16 | 6442.5 |
| 3/18/2004 | 2004 | 3 | 18 | 291 | 25 | 75 | 50 | 18 | 6460.5 |
| 3/19/2004 | 2004 | 3 | 19 | 292 | 26 | 79 | 52.5 | 20.5 | 6481 |
| 3/20/2004 | 2004 | 3 | 20 | 293 | 28 | 82 | 55 | 23 | 6504 |
| 3/21/2004 | 2004 | 3 | 21 | 294 | 42 | 80 | 61 | 29 | 6533 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/22/2004 | 2004 | 3 | 22 | 295 | 30 | 74 | 52 | 20 | 6553 |
| 3/23/2004 | 2004 | 3 | 23 | 296 | 35 | 75 | 55 | 23 | 6576 |
| 3/24/2004 | 2004 | 3 | 24 | 297 | 40 | 77 | 58.5 | 26.5 | 6602.5 |
| 3/25/2004 | 2004 | 3 | 25 | 298 | 46 | 78 | 62 | 30 | 6632.5 |
| 3/26/2004 | 2004 | 3 | 26 | 299 | 34 | 78 | 56 | 24 | 6656.5 |
| 3/27/2004 | 2004 | 3 | 27 | 300 | 38 | 76 | 57 | 25 | 6681.5 |
| 3/28/2004 | 2004 | 3 | 28 | 301 | 26 | 76 | 51 | 19 | 6700.5 |
| 3/29/2004 | 2004 | 3 | 29 | 302 | 25 | 63 | 44 | 12 | 6712.5 |
| 3/30/2004 | 2004 | 3 | 30 | 303 | 21 | 72 | 46.5 | 14.5 | 6727 |
| 3/31/2004 | 2004 | 3 | 31 | 304 | 20 | 75 | 47.5 | 15.5 | 6742.5 |
| 4/1/2004 | 2004 | 4 | 1 | 305 | 38 | 77 | 57.5 | 25.5 | 6768 |
| 4/2/2004 | 2004 | 4 | 2 | 306 | 33 | 68 | 50.5 | 18.5 | 6786.5 |
| 4/3/2004 | 2004 | 4 | 3 | 307 | 35 | 56 | 45.5 | 13.5 | 6800 |
| 4/4/2004 | 2004 | 4 | 4 | 308 | 32 | 52 | 42 | 10 | 6810 |
| 4/5/2004 | 2004 | 4 | 5 | 309 | 34 | 44 | 39 | 7 | 6817 |
| 4/6/2004 | 2004 | 4 | 6 | 310 | 32 | 58 | 45 | 13 | 6830 |
| 4/7/2004 | 2004 | 4 | 7 | 311 | 32 | 58 | 45 | 13 | 6843 |
| 4/8/2004 | 2004 | 4 | 8 | 312 | 35 | 57 | 46 | 14 | 6857 |
| 4/9/2004 | 2004 | 4 | 9 | 313 | 36 | 54 | 45 | 13 | 6870 |
| 4/10/2004 | 2004 | 4 | 10 | 314 | 32 | 60 | 46 | 14 | 6884 |
| 4/11/2004 | 2004 | 4 | 11 | 315 | 31 | 43 | 37 | 5 | 6889 |
| 4/12/2004 | 2004 | 4 | 12 | 316 | 27 | 52 | 39.5 | 7.5 | 6896.5 |
| 4/13/2004 | 2004 | 4 | 13 | 317 | 36 | 66 | 51 | 19 | 6915.5 |
| 4/14/2004 | 2004 | 4 | 14 | 318 | 36 | 66 | 51 | 19 | 6934.5 |
| 4/15/2004 | 2004 | 4 | 15 | 319 | 33 | 73 | 53 | 21 | 6955.5 |
| 4/16/2004 | 2004 | 4 | 16 | 320 | 32 | 72 | 52 | 20 | 6975.5 |
| 4/17/2004 | 2004 | 4 | 17 | 321 | 43 | 77 | 60 | 28 | 7003.5 |
| 4/18/2004 | 2004 | 4 | 18 | 322 | 40 | 77 | 58.5 | 26.5 | 7030 |
| 4/19/2004 | 2004 | 4 | 19 | 323 | 27 | 68 | 47.5 | 15.5 | 7045.5 |
| 4/20/2004 | 2004 | 4 | 20 | 324 | 34 | 73 | 53.5 | 21.5 | 7067 |
| 4/21/2004 | 2004 | 4 | 21 | 325 | 33 | 70 | 51.5 | 19.5 | 7086.5 |
| 4/22/2004 | 2004 | 4 | 22 | 326 | 37 | 71 | 54 | 22 | 7108.5 |
| 4/23/2004 | 2004 | 4 | 23 | 327 | 30 | 73 | 51.5 | 19.5 | 7128 |
| 4/24/2004 | 2004 | 4 | 24 | 328 | 35 | 62 | 48.5 | 16.5 | 7144.5 |
| 4/25/2004 | 2004 | 4 | 25 | 329 | 35 | 62 | 48.5 | 16.5 | 7161 |
| 4/26/2004 | 2004 | 4 | 26 | 330 | 35 | 62 | 48.5 | 16.5 | 7177.5 |
| 4/27/2004 | 2004 | 4 | 27 | 331 | 35 | 62 | 48.5 | 16.5 | 7194 |
| 4/28/2004 | 2004 | 4 | 28 | 332 | 41 | 78 | 59.5 | 27.5 | 7221.5 |
| 4/29/2004 | 2004 | 4 | 29 | 333 | 41 | 78 | 59.5 | 27.5 | 7249 |
| 4/30/2004 | 2004 | 4 | 30 | 334 | 28 | 72 | 50 | 18 | 7267 |
| 5/1/2004 | 2004 | 5 | 1 | 335 | 26 | 58 | 42 | 10 | 7277 |
| 5/2/2004 | 2004 | 5 | 2 | 336 | 30 | 70 | 50 | 18 | 7295 |
| 5/3/2004 | 2004 | 5 | 3 | 337 | 32 | 77 | 54.5 | 22.5 | 7317.5 |
| 5/4/2004 | 2004 | 5 | 4 | 338 | 34 | 82 | 58 | 26 | 7343.5 |
| 5/5/2004 | 2004 | 5 | 5 | 339 | 37 | 88 | 62.5 | 30.5 | 7374 |
| 5/6/2004 | 2004 | 5 | 6 | 340 | 44 | 89 | 66.5 | 34.5 | 7408.5 |
| 5/7/2004 | 2004 | 5 | 7 | 341 | 41 | 88 | 64.5 | 32.5 | 7441 |
| 5/8/2004 | 2004 | 5 | 8 | 342 | 46 | 88 | 67 | 35 | 7476 |
| 5/9/2004 | 2004 | 5 | 9 | 343 | 40 | 87 | 63.5 | 31.5 | 7507.5 |
| 5/10/2004 | 2004 | 5 | 10 | 344 | 47 | 84 | 65.5 | 33.5 | 7541 |
| 5/11/2004 | 2004 | 5 | 11 | 345 | 47 | 83 | 65 | 33 | 7574 |
| 5/12/2004 | 2004 | 5 | 12 | 346 | 46 | 80 | 63 | 31 | 7605 |
| 5/13/2004 | 2004 | 5 | 13 | 347 | 38 | 75 | 56.5 | 24.5 | 7629.5 |
| 5/14/2004 | 2004 | 5 | 14 | 348 | 30 | 76 | 53 | 21 | 7650.5 |
| 5/15/2004 | 2004 | 5 | 15 | 349 | 40 | 83 | 61.5 | 29.5 | 7680 |
| 5/16/2004 | 2004 | 5 | 16 | 350 | 43 | 86 | 64.5 | 32.5 | 7712.5 |
| 5/17/2004 | 2004 | 5 | 17 | 351 | 42 | 84 | 63 | 31 | 7743.5 |
| 5/18/2004 | 2004 | 5 | 18 | 352 | 40 | 83 | 61.5 | 29.5 | 7773 |
| 5/19/2004 | 2004 | 5 | 19 | 353 | 37 | 87 | 62 | 30 | 7803 |
| 5/20/2004 | 2004 | 5 | 20 | 354 | 41 | 90 | 65.5 | 33.5 | 7836.5 |
| 5/21/2004 | 2004 | 5 | 21 | 355 | 40 | 86 | 63 | 31 | 7867.5 |
| 5/22/2004 | 2004 | 5 | 22 | 356 | 46 | 84 | 65 | 33 | 7900.5 |
| 5/23/2004 | 2004 | 5 | 23 | 357 | 46 | 84 | 65 | 33 | 7933.5 |
| 5/24/2004 | 2004 | 5 | 24 | 358 | 42 | 80 | 61 | 29 | 7962.5 |
| 5/25/2004 | 2004 | 5 | 25 | 359 | 44 | 81 | 62.5 | 30.5 | 7993 |
| 5/26/2004 | 2004 | 5 | 26 | 360 | 45 | 75 | 60 | 28 | 8021 |
| 5/27/2004 | 2004 | 5 | 27 | 361 | 42 | 82 | 62 | 30 | 8051 |
| 5/28/2004 | 2004 | 5 | 28 | 362 | 39 | 83 | 61 | 29 | 8080 |
| 5/29/2004 | 2004 | 5 | 29 | 363 | 47 | 87 | 67 | 35 | 8115 |
| 5/30/2004 | 2004 | 5 | 30 | 364 | 40 | 78 | 59 | 27 | 8142 |
| 5/31/2004 | 2004 | 5 | 31 | 365 | 43 | 80 | 61.5 | 29.5 | 8171.5 |
| 6/1/2004 | 2004 | 6 | 1 | 1 | 41 | 88 | 64.5 | 32.5 | 32.5 |
| 6/2/2004 | 2004 | 6 | 2 | 2 | 41 | 91 | 66 | 34 | 66.5 |
| 6/3/2004 | 2004 | 6 | 3 | 3 | 41 | 94 | 67.5 | 35.5 | 102 |
| 6/4/2004 | 2004 | 6 | 4 | 4 | 57 | 97 | 77 | 45 | 147 |
| 6/5/2004 | 2004 | 6 | 5 | 5 | 51 | 97 | 74 | 42 | 189 |
| 6/6/2004 | 2004 | 6 | 6 | 6 | 47 | 98 | 72.5 | 40.5 | 229.5 |
| 6/7/2004 | 2004 | 6 | 7 | 7 | 53 | 96 | 74.5 | 42.5 | 272 |
| 6/8/2004 | 2004 | 6 | 8 | 8 | 46 | 94 | 70 | 38 | 310 |
| 6/9/2004 | 2004 | 6 | 9 | 9 | 48 | 92 | 70 | 38 | 348 |
| 6/10/2004 | 2004 | 6 | 10 | 10 | 45 | 90 | 67.5 | 35.5 | 383.5 |
| 6/11/2004 | 2004 | 6 | 11 | 11 | 43 | 80 | 61.5 | 29.5 | 413 |
| 6/12/2004 | 2004 | 6 | 12 | 12 | 46 | 81 | 63.5 | 31.5 | 444.5 |
| 6/13/2004 | 2004 | 6 | 13 | 13 | 46 | 90 | 68 | 36 | 480.5 |
| 6/14/2004 | 2004 | 6 | 14 | 14 | 45 | 92 | 68.5 | 36.5 | 517 |
| 6/15/2004 | 2004 | 6 | 15 | 15 | 50 | 96 | 73 | 41 | 558 |
| 6/16/2004 | 2004 | 6 | 16 | 16 | 47 | 94 | 70.5 | 38.5 | 596.5 |
| 6/17/2004 | 2004 | 6 | 17 | 17 | 49 | 93 | 71 | 39 | 635.5 |
| 6/18/2004 | 2004 | 6 | 18 | 18 | 46 | 92 | 69 | 37 | 672.5 |
| 6/19/2004 | 2004 | 6 | 19 | 19 | 47 | 94 | 70.5 | 38.5 | 711 |
| 6/20/2004 | 2004 | 6 | 20 | 20 | 63 | 94 | 78.5 | 46.5 | 757.5 |
| 6/21/2004 | 2004 | 6 | 21 | 21 | 53 | 91 | 72 | 40 | 797.5 |
| 6/22/2004 | 2004 | 6 | 22 | 22 | 48 | 92 | 70 | 38 | 835.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/23/2004 | 2004 | 6 | 23 | 23 | 51 | 78 | 64.5 | 32.5 | 868 |
| 6/24/2004 | 2004 | 6 | 24 | 24 | 48 | 90 | 69 | 37 | 905 |
| 6/25/2004 | 2004 | 6 | 25 | 25 | 60 | 92 | 76 | 44 | 949 |
| 6/26/2004 | 2004 | 6 | 26 | 26 | 50 | 85 | 67.5 | 35.5 | 984.5 |
| 6/27/2004 | 2004 | 6 | 27 | 27 | 55 | 82 | 68.5 | 36.5 | 1021 |
| 6/28/2004 | 2004 | 6 | 28 | 28 | 55 | 82 | 68.5 | 36.5 | 1057.5 |
| 6/29/2004 | 2004 | 6 | 29 | 29 | 57 | 74 | 65.5 | 33.5 | 1091 |
| 6/30/2004 | 2004 | 6 | 30 | 30 | 49 | 81 | 65 | 33 | 1124 |
| 7/1/2004 | 2004 | 7 | 1 | 31 | 43 | 88 | 65.5 | 33.5 | 1157.5 |
| 7/2/2004 | 2004 | 7 | 2 | 32 | 41 | 91 | 66 | 34 | 1191.5 |
| 7/3/2004 | 2004 | 7 | 3 | 33 | 47 | 92 | 69.5 | 37.5 | 1229 |
| 7/4/2004 | 2004 | 7 | 4 | 34 | 56 | 91 | 73.5 | 41.5 | 1270.5 |
| 7/5/2004 | 2004 | 7 | 5 | 35 | 43 | 89 | 66 | 34 | 1304.5 |
| 7/6/2004 | 2004 | 7 | 6 | 36 | 48 | 95 | 71.5 | 39.5 | 1344 |
| 7/7/2004 | 2004 | 7 | 7 | 37 | 49 | 90 | 69.5 | 37.5 | 1381.5 |
| 7/8/2004 | 2004 | 7 | 8 | 38 | 49 | 90 | 69.5 | 37.5 | 1419 |
| 7/9/2004 | 2004 | 7 | 9 | 39 | 55 | 93 | 74 | 42 | 1461 |
| 7/10/2004 | 2004 | 7 | 10 | 40 | 57 | 90 | 73.5 | 41.5 | 1502.5 |
| 7/11/2004 | 2004 | 7 | 11 | 41 | 57 | 90 | 73.5 | 41.5 | 1544 |
| 7/12/2004 | 2004 | 7 | 12 | 42 | 59 | 92 | 75.5 | 43.5 | 1587.5 |
| 7/13/2004 | 2004 | 7 | 13 | 43 | 54 | 95 | 74.5 | 42.5 | 1630 |
| 7/14/2004 | 2004 | 7 | 14 | 44 | 57 | 91 | 74 | 42 | 1672 |
| 7/15/2004 | 2004 | 7 | 15 | 45 | 69 | 98 | 83.5 | 51.5 | 1723.5 |
| 7/16/2004 | 2004 | 7 | 16 | 46 | 71 | 97 | 84 | 52 | 1775.5 |
| 7/17/2004 | 2004 | 7 | 17 | 47 | 61 | 99 | 80 | 48 | 1823.5 |
| 7/18/2004 | 2004 | 7 | 18 | 48 | 60 | 93 | 76.5 | 44.5 | 1868 |
| 7/19/2004 | 2004 | 7 | 19 | 49 | 55 | 95 | 75 | 43 | 1911 |
| 7/20/2004 | 2004 | 7 | 20 | 50 | 56 | 95 | 75.5 | 43.5 | 1954.5 |
| 7/21/2004 | 2004 | 7 | 21 | 51 | 58 | 95 | 76.5 | 44.5 | 1999 |
| 7/22/2004 | 2004 | 7 | 22 | 52 | 58 | 99 | 78.5 | 46.5 | 2045.5 |
| 7/23/2004 | 2004 | 7 | 23 | 53 | 61 | 90 | 75.5 | 43.5 | 2089 |
| 7/24/2004 | 2004 | 7 | 24 | 54 | 54 | 84 | 69 | 37 | 2126 |
| 7/25/2004 | 2004 | 7 | 25 | 55 | 53 | 82 | 67.5 | 35.5 | 2161.5 |
| 7/26/2004 | 2004 | 7 | 26 | 56 | 52 | 76 | 64 | 32 | 2193.5 |
| 7/27/2004 | 2004 | 7 | 27 | 57 | 55 | 82 | 68.5 | 36.5 | 2230 |
| 7/28/2004 | 2004 | 7 | 28 | 58 | 51 | 85 | 68 | 36 | 2266 |
| 7/29/2004 | 2004 | 7 | 29 | 59 | 49 | 82 | 65.5 | 33.5 | 2299.5 |
| 7/30/2004 | 2004 | 7 | 30 | 60 | 49 | 91 | 70 | 38 | 2337.5 |
| 7/31/2004 | 2004 | 7 | 31 | 61 | 62 | 97 | 79.5 | 47.5 | 2385 |
| 8/1/2004 | 2004 | 8 | 1 | 62 | 55 | 92 | 73.5 | 41.5 | 2426.5 |
| 8/2/2004 | 2004 | 8 | 2 | 63 | 57 | 90 | 73.5 | 41.5 | 2468 |
| 8/3/2004 | 2004 | 8 | 3 | 64 | 55 | 77 | 66 | 34 | 2502 |
| 8/4/2004 | 2004 | 8 | 4 | 65 | 51 | 88 | 69.5 | 37.5 | 2539.5 |
| 8/5/2004 | 2004 | 8 | 5 | 66 | 60 | 93 | 76.5 | 44.5 | 2584 |
| 8/6/2004 | 2004 | 8 | 6 | 67 | 55 | 86 | 70.5 | 38.5 | 2622.5 |
| 8/7/2004 | 2004 | 8 | 7 | 68 | 55 | 93 | 74 | 42 | 2664.5 |
| 8/8/2004 | 2004 | 8 | 8 | 69 | 56 | 97 | 76.5 | 44.5 | 2709 |
| 8/9/2004 | 2004 | 8 | 9 | 70 | 61 | 97 | 79 | 47 | 2756 |
| 8/10/2004 | 2004 | 8 | 10 | 71 | 51 | 94 | 72.5 | 40.5 | 2796.5 |
| 8/11/2004 | 2004 | 8 | 11 | 72 | 53 | 95 | 74 | 42 | 2838.5 |
| 8/12/2004 | 2004 | 8 | 12 | 73 | 59 | 97 | 78 | 46 | 2884.5 |
| 8/13/2004 | 2004 | 8 | 13 | 74 | 57 | 94 | 75.5 | 43.5 | 2928 |
| 8/14/2004 | 2004 | 8 | 14 | 75 | 53 | 85 | 69 | 37 | 2965 |
| 8/15/2004 | 2004 | 8 | 15 | 76 | 53 | 82 | 67.5 | 35.5 | 3000.5 |
| 8/16/2004 | 2004 | 8 | 16 | 77 | 55 | 81 | 68 | 36 | 3036.5 |
| 8/17/2004 | 2004 | 8 | 17 | 78 | 50 | 81 | 65.5 | 33.5 | 3070 |
| 8/18/2004 | 2004 | 8 | 18 | 79 | 50 | 81 | 65.5 | 33.5 | 3103.5 |
| 8/19/2004 | 2004 | 8 | 19 | 80 | 48 | 88 | 68 | 36 | 3139.5 |
| 8/20/2004 | 2004 | 8 | 20 | 81 | 50 | 83 | 66.5 | 34.5 | 3174 |
| 8/21/2004 | 2004 | 8 | 21 | 82 | 50 | 82 | 66 | 34 | 3208 |
| 8/22/2004 | 2004 | 8 | 22 | 83 | 45 | 79 | 62 | 30 | 3238 |
| 8/23/2004 | 2004 | 8 | 23 | 84 | 48 | 84 | 66 | 34 | 3272 |
| 8/24/2004 | 2004 | 8 | 24 | 85 | 54 | 81 | 67.5 | 35.5 | 3307.5 |
| 8/25/2004 | 2004 | 8 | 25 | 86 | 52 | 84 | 68 | 36 | 3343.5 |
| 8/26/2004 | 2004 | 8 | 26 | 87 | 45 | 83 | 64 | 32 | 3375.5 |
| 8/27/2004 | 2004 | 8 | 27 | 88 | 48 | 89 | 68.5 | 36.5 | 3412 |
| 8/28/2004 | 2004 | 8 | 28 | 89 | 45 | 89 | 67 | 35 | 3447 |
| 8/29/2004 | 2004 | 8 | 29 | 90 | 47 | 87 | 67 | 35 | 3482 |
| 8/30/2004 | 2004 | 8 | 30 | 91 | 52 | 92 | 72 | 40 | 3522 |
| 8/31/2004 | 2004 | 8 | 31 | 92 | 44 | 84 | 64 | 32 | 3554 |
| 9/1/2004 | 2004 | 9 | 1 | 93 | 47 | 85 | 66 | 34 | 3588 |
| 9/2/2004 | 2004 | 9 | 2 | 94 | 49 | 85 | 67 | 35 | 3623 |
| 9/3/2004 | 2004 | 9 | 3 | 95 | 56 | 91 | 73.5 | 41.5 | 3664.5 |
| 9/4/2004 | 2004 | 9 | 4 | 96 | 55 | 81 | 68 | 36 | 3700.5 |
| 9/5/2004 | 2004 | 9 | 5 | 97 | 40 | 75 | 57.5 | 25.5 | 3726 |
| 9/6/2004 | 2004 | 9 | 6 | 98 | 40 | 80 | 60 | 28 | 3754 |
| 9/7/2004 | 2004 | 9 | 7 | 99 | 49 | 80 | 64.5 | 32.5 | 3786.5 |
| 9/8/2004 | 2004 | 9 | 8 | 100 | 42 | 82 | 62 | 30 | 3816.5 |
| 9/9/2004 | 2004 | 9 | 9 | 101 | 47 | 92 | 69.5 | 37.5 | 3854 |
| 9/10/2004 | 2004 | 9 | 10 | 102 | 50 | 86 | 68 | 36 | 3890 |
| 9/11/2004 | 2004 | 9 | 11 | 103 | 48 | 93 | 70.5 | 38.5 | 3928.5 |
| 9/12/2004 | 2004 | 9 | 12 | 104 | 50 | 89 | 69.5 | 37.5 | 3966 |
| 9/13/2004 | 2004 | 9 | 13 | 105 | 47 | 93 | 70 | 38 | 4004 |
| 9/14/2004 | 2004 | 9 | 14 | 106 | 48 | 89 | 68.5 | 36.5 | 4040.5 |
| 9/15/2004 | 2004 | 9 | 15 | 107 | 50 | 88 | 69 | 37 | 4077.5 |
| 9/16/2004 | 2004 | 9 | 16 | 108 | 42 | 88 | 65 | 33 | 4110.5 |
| 9/17/2004 | 2004 | 9 | 17 | 109 | 44 | 90 | 67 | 35 | 4145.5 |
| 9/18/2004 | 2004 | 9 | 18 | 110 | 49 | 90 | 69.5 | 37.5 | 4183 |
| 9/19/2004 | 2004 | 9 | 19 | 111 | 57 | 81 | 69 | 37 | 4220 |
| 9/20/2004 | 2004 | 9 | 20 | 112 | 44 | 71 | 57.5 | 25.5 | 4245.5 |
| 9/21/2004 | 2004 | 9 | 21 | 113 | 47 | 80 | 63.5 | 31.5 | 4277 |
| 9/22/2004 | 2004 | 9 | 22 | 114 | 31 | 73 | 52 | 20 | 4297 |
| 9/23/2004 | 2004 | 9 | 23 | 115 | 30 | 73 | 51.5 | 19.5 | 4316.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/24/2004 | 2004 | 9 | 24 | 116 | 35 | 79 | 57 | 25 | 4341.5 |
| 9/25/2004 | 2004 | 9 | 25 | 117 | 42 | 80 | 61 | 29 | 4370.5 |
| 9/26/2004 | 2004 | 9 | 26 | 118 | 38 | 68 | 53 | 21 | 4391.5 |
| 9/27/2004 | 2004 | 9 | 27 | 119 | 37 | 71 | 54 | 22 | 4413.5 |
| 9/28/2004 | 2004 | 9 | 28 | 120 | 45 | 82 | 63.5 | 31.5 | 4445 |
| 9/29/2004 | 2004 | 9 | 29 | 121 | 47 | 72 | 59.5 | 27.5 | 4472.5 |
| 9/30/2004 | 2004 | 9 | 30 | 122 | 39 | 63 | 51 | 19 | 4491.5 |
| 10/1/2004 | 2004 | 10 | 1 | 123 | 32 | 70 | 51 | 19 | 4510.5 |
| 10/2/2004 | 2004 | 10 | 2 | 124 | 41 | 76 | 58.5 | 26.5 | 4537 |
| 10/3/2004 | 2004 | 10 | 3 | 125 | 42 | 72 | 57 | 25 | 4562 |
| 10/4/2004 | 2004 | 10 | 4 | 126 | 41 | 74 | 57.5 | 25.5 | 4587.5 |
| 10/5/2004 | 2004 | 10 | 5 | 127 | 42 | 75 | 58.5 | 26.5 | 4614 |
| 10/6/2004 | 2004 | 10 | 6 | 128 | 36 | 76 | 56 | 24 | 4638 |
| 10/7/2004 | 2004 | 10 | 7 | 129 | 34 | 76 | 55 | 23 | 4661 |
| 10/8/2004 | 2004 | 10 | 8 | 130 | 35 | 77 | 56 | 24 | 4685 |
| 10/9/2004 | 2004 | 10 | 9 | 131 | 32 | 73 | 52.5 | 20.5 | 4705.5 |
| 10/10/2004 | 2004 | 10 | 10 | 132 | 34 | 79 | 56.5 | 24.5 | 4730 |
| 10/11/2004 | 2004 | 10 | 11 | 133 | 35 | 76 | 55.5 | 23.5 | 4753.5 |
| 10/12/2004 | 2004 | 10 | 12 | 134 | 33 | 61 | 47 | 15 | 4768.5 |
| 10/13/2004 | 2004 | 10 | 13 | 135 | 33 | 73 | 53 | 21 | 4789.5 |
| 10/14/2004 | 2004 | 10 | 14 | 136 | 28 | 57 | 42.5 | 10.5 | 4800 |
| 10/15/2004 | 2004 | 10 | 15 | 137 | 29 | 68 | 48.5 | 16.5 | 4816.5 |
| 10/16/2004 | 2004 | 10 | 16 | 138 | 32 | 82 | 57 | 25 | 4841.5 |
| 10/17/2004 | 2004 | 10 | 17 | 139 | 45 | 79 | 62 | 30 | 4871.5 |
| 10/18/2004 | 2004 | 10 | 18 | 140 | 52 | 69 | 60.5 | 28.5 | 4900 |
| 10/19/2004 | 2004 | 10 | 19 | 141 | 31 | 65 | 48 | 16 | 4916 |
| 10/20/2004 | 2004 | 10 | 20 | 142 | 31 | 69 | 50 | 18 | 4934 |
| 10/21/2004 | 2004 | 10 | 21 | 143 | 41 | 73 | 57 | 25 | 4959 |
| 10/22/2004 | 2004 | 10 | 22 | 144 | 39 | 65 | 52 | 20 | 4979 |
| 10/23/2004 | 2004 | 10 | 23 | 145 | 24 | 57 | 40.5 | 8.5 | 4987.5 |
| 10/24/2004 | 2004 | 10 | 24 | 146 | 24 | 67 | 45.5 | 13.5 | 5001 |
| 10/25/2004 | 2004 | 10 | 25 | 147 | 30 | 70 | 50 | 18 | 5019 |
| 10/26/2004 | 2004 | 10 | 26 | 148 | 35 | 70 | 52.5 | 20.5 | 5039.5 |
| 10/27/2004 | 2004 | 10 | 27 | 149 | 45 | 67 | 56 | 24 | 5063.5 |
| 10/28/2004 | 2004 | 10 | 28 | 150 | 39 | 65 | 52 | 20 | 5083.5 |
| 10/29/2004 | 2004 | 10 | 29 | 151 | 30 | 46 | 38 | 6 | 5089.5 |
| 10/30/2004 | 2004 | 10 | 30 | 152 | 20 | 56 | 38 | 6 | 5095.5 |
| 10/31/2004 | 2004 | 10 | 31 | 153 | 20 | 63 | 41.5 | 9.5 | 5105 |
| 11/1/2004 | 2004 | 11 | 1 | 154 | 20 | 62 | 41 | 9 | 5114 |
| 11/2/2004 | 2004 | 11 | 2 | 155 | 16 | 44 | 30 | -2 | 5112 |
| 11/3/2004 | 2004 | 11 | 3 | 156 | 10 | 54 | 32 | 0 | 5112 |
| 11/4/2004 | 2004 | 11 | 4 | 157 | 15 | 65 | 40 | 8 | 5120 |
| 11/5/2004 | 2004 | 11 | 5 | 158 | 15 | 60 | 37.5 | 5.5 | 5125.5 |
| 11/6/2004 | 2004 | 11 | 6 | 159 | 26 | 68 | 47 | 15 | 5140.5 |
| 11/7/2004 | 2004 | 11 | 7 | 160 | 26 | 68 | 47 | 15 | 5155.5 |
| 11/8/2004 | 2004 | 11 | 8 | 161 | 26 | 68 | 47 | 15 | 5170.5 |
| 11/9/2004 | 2004 | 11 | 9 | 162 | 38 | 66 | 52 | 20 | 5190.5 |
| 11/10/2004 | 2004 | 11 | 10 | 163 | 25 | 52 | 38.5 | 6.5 | 5197 |
| 11/11/2004 | 2004 | 11 | 11 | 164 | 32 | 59 | 45.5 | 13.5 | 5210.5 |
| 11/12/2004 | 2004 | 11 | 12 | 165 | 32 | 59 | 45.5 | 13.5 | 5224 |
| 11/13/2004 | 2004 | 11 | 13 | 166 | 30 | 50 | 40 | 8 | 5232 |
| 11/14/2004 | 2004 | 11 | 14 | 167 | 32 | 37 | 34.5 | 2.5 | 5234.5 |
| 11/15/2004 | 2004 | 11 | 15 | 168 | 30 | 39 | 34.5 | 2.5 | 5237 |
| 11/16/2004 | 2004 | 11 | 16 | 169 | 36 | 43 | 39.5 | 7.5 | 5244.5 |
| 11/17/2004 | 2004 | 11 | 17 | 170 | 28 | 55 | 41.5 | 9.5 | 5254 |
| 11/18/2004 | 2004 | 11 | 18 | 171 | 26 | 62 | 44 | 12 | 5266 |
| 11/19/2004 | 2004 | 11 | 19 | 172 | 28 | 58 | 43 | 11 | 5277 |
| 11/20/2004 | 2004 | 11 | 20 | 173 | 25 | 64 | 44.5 | 12.5 | 5289.5 |
| 11/21/2004 | 2004 | 11 | 21 | 174 | 33 | 57 | 45 | 13 | 5302.5 |
| 11/22/2004 | 2004 | 11 | 22 | 175 | 35 | 54 | 44.5 | 12.5 | 5315 |
| 11/23/2004 | 2004 | 11 | 23 | 176 | 33 | 50 | 41.5 | 9.5 | 5324.5 |
| 11/24/2004 | 2004 | 11 | 24 | 177 | 22 | 52 | 37 | 5 | 5329.5 |
| 11/25/2004 | 2004 | 11 | 25 | 178 | 22 | 52 | 37 | 5 | 5334.5 |
| 11/26/2004 | 2004 | 11 | 26 | 179 | 22 | 52 | 37 | 5 | 5339.5 |
| 11/27/2004 | 2004 | 11 | 27 | 180 | 22 | 52 | 37 | 5 | 5344.5 |
| 11/28/2004 | 2004 | 11 | 28 | 181 | 27 | 60 | 43.5 | 11.5 | 5356 |
| 11/29/2004 | 2004 | 11 | 29 | 182 | 16 | 46 | 31 | -1 | 5355 |
| 11/30/2004 | 2004 | 11 | 30 | 183 | 6 | 32 | 19 | -13 | 5342 |
| 12/1/2004 | 2004 | 12 | 1 | 184 | 7 | 42 | 24.5 | -7.5 | 5334.5 |
| 12/2/2004 | 2004 | 12 | 2 | 185 | 5 | 48 | 26.5 | -5.5 | 5329 |
| 12/3/2004 | 2004 | 12 | 3 | 186 | 8 | 44 | 26 | -6 | 5323 |
| 12/4/2004 | 2004 | 12 | 4 | 187 | 9 | 53 | 31 | -1 | 5322 |
| 12/5/2004 | 2004 | 12 | 5 | 188 | 15 | 43 | 29 | -3 | 5319 |
| 12/6/2004 | 2004 | 12 | 6 | 189 | 22 | 44 | 33 | 1 | 5320 |
| 12/7/2004 | 2004 | 12 | 7 | 190 | 26 | 45 | 35.5 | 3.5 | 5323.5 |
| 12/8/2004 | 2004 | 12 | 8 | 191 | 27 | 48 | 37.5 | 5.5 | 5329 |
| 12/9/2004 | 2004 | 12 | 9 | 192 | 23 | 52 | 37.5 | 5.5 | 5334.5 |
| 12/10/2004 | 2004 | 12 | 10 | 193 | 22 | 57 | 39.5 | 7.5 | 5342 |
| 12/11/2004 | 2004 | 12 | 11 | 194 | 20 | 59 | 39.5 | 7.5 | 5349.5 |
| 12/12/2004 | 2004 | 12 | 12 | 195 | 21 | 66 | 43.5 | 11.5 | 5361 |
| 12/13/2004 | 2004 | 12 | 13 | 196 | 20 | 68 | 44 | 12 | 5373 |
| 12/14/2004 | 2004 | 12 | 14 | 197 | 26 | 49 | 37.5 | 5.5 | 5378.5 |
| 12/15/2004 | 2004 | 12 | 15 | 198 | 15 | 49 | 32 | 0 | 5378.5 |
| 12/16/2004 | 2004 | 12 | 16 | 199 | 17 | 54 | 35.5 | 3.5 | 5382 |
| 12/17/2004 | 2004 | 12 | 17 | 200 | 13 | 54 | 33.5 | 1.5 | 5383.5 |
| 12/18/2004 | 2004 | 12 | 18 | 201 | 16 | 50 | 33 | 1 | 5384.5 |
| 12/19/2004 | 2004 | 12 | 19 | 202 | 12 | 62 | 37 | 5 | 5389.5 |
| 12/20/2004 | 2004 | 12 | 20 | 203 | 12 | 58 | 35 | 3 | 5392.5 |
| 12/21/2004 | 2004 | 12 | 21 | 204 | 23 | 62 | 42.5 | 10.5 | 5403 |
| 12/22/2004 | 2004 | 12 | 22 | 205 | 2 | 44 | 23 | -9 | 5394 |
| 12/23/2004 | 2004 | 12 | 23 | 206 | 3 | 39 | 21 | -11 | 5383 |
| 12/24/2004 | 2004 | 12 | 24 | 207 | 0 | 32 | 16 | -16 | 5367 |
| 12/25/2004 | 2004 | 12 | 25 | 208 | 6 | 37 | 21.5 | -10.5 | 5356.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/26/2004 | 2004 | 12 | 26 | 209 | 9 | 54 | 31.5 | -0.5 | 5356 |
| 12/27/2004 | 2004 | 12 | 27 | 210 | 24 | 50 | 37 | 5 | 5361 |
| 12/28/2004 | 2004 | 12 | 28 | 211 | 18 | 49 | 33.5 | 1.5 | 5362.5 |
| 12/29/2004 | 2004 | 12 | 29 | 212 | 30 | 58 | 44 | 12 | 5374.5 |
| 12/30/2004 | 2004 | 12 | 30 | 213 | 37 | 59 | 48 | 16 | 5390.5 |
| 12/31/2004 | 2004 | 12 | 31 | 214 | 26 | 54 | 40 | 8 | 5398.5 |
| 1/1/2005 | 2005 | 1 | 1 | 215 | 26 | 46 | 36 | 4 | 5402.5 |
| 1/2/2005 | 2005 | 1 | 2 | 216 | 26 | 54 | 40 | 8 | 5410.5 |
| 1/3/2005 | 2005 | 1 | 3 | 217 | 33 | 39 | 36 | 4 | 5414.5 |
| 1/4/2005 | 2005 | 1 | 4 | 218 | 33 | 43 | 38 | 6 | 5420.5 |
| 1/5/2005 | 2005 | 1 | 5 | 219 | 24 | 51 | 37.5 | 5.5 | 5426 |
| 1/6/2005 | 2005 | 1 | 6 | 220 | 15 | 43 | 29 | -3 | 5423 |
| 1/7/2005 | 2005 | 1 | 7 | 221 | 13 | 44 | 28.5 | -3.5 | 5419.5 |
| 1/8/2005 | 2005 | 1 | 8 | 222 | 13 | 44 | 28.5 | -3.5 | 5416 |
| 1/9/2005 | 2005 | 1 | 9 | 223 | 35 | 50 | 42.5 | 10.5 | 5426.5 |
| 1/10/2005 | 2005 | 1 | 10 | 224 | 33 | 58 | 45.5 | 13.5 | 5440 |
| 1/11/2005 | 2005 | 1 | 11 | 225 | 36 | 63 | 49.5 | 17.5 | 5457.5 |
| 1/12/2005 | 2005 | 1 | 12 | 226 | 25 | 57 | 41 | 9 | 5466.5 |
| 1/13/2005 | 2005 | 1 | 13 | 227 | 13 | 43 | 28 | -4 | 5462.5 |
| 1/14/2005 | 2005 | 1 | 14 | 228 | 21 | 55 | 38 | 6 | 5468.5 |
| 1/15/2005 | 2005 | 1 | 15 | 229 | 14 | 52 | 33 | 1 | 5469.5 |
| 1/16/2005 | 2005 | 1 | 16 | 230 | 17 | 59 | 38 | 6 | 5475.5 |
| 1/17/2005 | 2005 | 1 | 17 | 231 | 17 | 61 | 39 | 7 | 5482.5 |
| 1/18/2005 | 2005 | 1 | 18 | 232 | 18 | 64 | 41 | 9 | 5491.5 |
| 1/19/2005 | 2005 | 1 | 19 | 233 | 21 | 63 | 42 | 10 | 5501.5 |
| 1/20/2005 | 2005 | 1 | 20 | 234 | 21 | 66 | 43.5 | 11.5 | 5513 |
| 1/21/2005 | 2005 | 1 | 21 | 235 | 27 | 62 | 44.5 | 12.5 | 5525.5 |
| 1/22/2005 | 2005 | 1 | 22 | 236 | 31 | 69 | 50 | 18 | 5543.5 |
| 1/23/2005 | 2005 | 1 | 23 | 237 | 20 | 54 | 37 | 5 | 5548.5 |
| 1/24/2005 | 2005 | 1 | 24 | 238 | 27 | 65 | 46 | 14 | 5562.5 |
| 1/25/2005 | 2005 | 1 | 25 | 239 | 32 | 63 | 47.5 | 15.5 | 5578 |
| 1/26/2005 | 2005 | 1 | 26 | 240 | 29 | 60 | 44.5 | 12.5 | 5590.5 |
| 1/27/2005 | 2005 | 1 | 27 | 241 | 37 | 60 | 48.5 | 16.5 | 5607 |
| 1/28/2005 | 2005 | 1 | 28 | 242 | 27 | 50 | 38.5 | 6.5 | 5613.5 |
| 1/29/2005 | 2005 | 1 | 29 | 243 | 19 | 54 | 36.5 | 4.5 | 5618 |
| 1/30/2005 | 2005 | 1 | 30 | 244 | 17 | 47 | 32 | 0 | 5618 |
| 1/31/2005 | 2005 | 1 | 31 | 245 | 26 | 45 | 35.5 | 3.5 | 5621.5 |
| 2/1/2005 | 2005 | 2 | 1 | 246 | 22 | 38 | 30 | -2 | 5619.5 |
| 2/2/2005 | 2005 | 2 | 2 | 247 | 22 | 41 | 31.5 | -0.5 | 5619 |
| 2/3/2005 | 2005 | 2 | 3 | 248 | 13 | 45 | 29 | -3 | 5616 |
| 2/4/2005 | 2005 | 2 | 4 | 249 | 13 | 45 | 29 | -3 | 5613 |
| 2/5/2005 | 2005 | 2 | 5 | 250 | 30 | 48 | 39 | 7 | 5620 |
| 2/6/2005 | 2005 | 2 | 6 | 251 | 28 | 56 | 42 | 10 | 5630 |
| 2/7/2005 | 2005 | 2 | 7 | 252 | 28 | 55 | 41.5 | 9.5 | 5639.5 |
| 2/8/2005 | 2005 | 2 | 8 | 253 | 28 | 41 | 34.5 | 2.5 | 5642 |
| 2/9/2005 | 2005 | 2 | 9 | 254 | 15 | 52 | 33.5 | 1.5 | 5643.5 |
| 2/10/2005 | 2005 | 2 | 10 | 255 | 22 | 54 | 38 | 6 | 5649.5 |
| 2/11/2005 | 2005 | 2 | 11 | 256 | 34 | 47 | 40.5 | 8.5 | 5658 |
| 2/12/2005 | 2005 | 2 | 12 | 257 | 38 | 45 | 41.5 | 9.5 | 5667.5 |
| 2/13/2005 | 2005 | 2 | 13 | 258 | 32 | 54 | 43 | 11 | 5678.5 |
| 2/14/2005 | 2005 | 2 | 14 | 259 | 25 | 58 | 41.5 | 9.5 | 5688 |
| 2/15/2005 | 2005 | 2 | 15 | 260 | 34 | 61 | 47.5 | 15.5 | 5703.5 |
| 2/16/2005 | 2005 | 2 | 16 | 261 | 33 | 60 | 46.5 | 14.5 | 5718 |
| 2/17/2005 | 2005 | 2 | 17 | 262 | 28 | 60 | 44 | 12 | 5730 |
| 2/18/2005 | 2005 | 2 | 18 | 263 | 38 | 53 | 45.5 | 13.5 | 5743.5 |
| 2/19/2005 | 2005 | 2 | 19 | 264 | 41 | 50 | 45.5 | 13.5 | 5757 |
| 2/20/2005 | 2005 | 2 | 20 | 265 | 26 | 57 | 41.5 | 9.5 | 5766.5 |
| 2/21/2005 | 2005 | 2 | 21 | 266 | 32 | 56 | 44 | 12 | 5778.5 |
| 2/22/2005 | 2005 | 2 | 22 | 267 | 27 | 56 | 41.5 | 9.5 | 5788 |
| 2/23/2005 | 2005 | 2 | 23 | 268 | 27 | 56 | 41.5 | 9.5 | 5797.5 |
| 2/24/2005 | 2005 | 2 | 24 | 269 | 30 | 53 | 41.5 | 9.5 | 5807 |
| 2/25/2005 | 2005 | 2 | 25 | 270 | 28 | 54 | 41 | 9 | 5816 |
| 2/26/2005 | 2005 | 2 | 26 | 271 | 27 | 40 | 33.5 | 1.5 | 5817.5 |
| 2/27/2005 | 2005 | 2 | 27 | 272 | 27 | 40 | 33.5 | 1.5 | 5819 |
| 2/28/2005 | 2005 | 2 | 28 | 273 | 19 | 55 | 37 | 5 | 5824 |
| 3/1/2005 | 2005 | 3 | 1 | 274 | 23 | 60 | 41.5 | 9.5 | 5833.5 |
| 3/2/2005 | 2005 | 3 | 2 | 275 | 20 | 56 | 38 | 6 | 5839.5 |
| 3/3/2005 | 2005 | 3 | 3 | 276 | 21 | 60 | 40.5 | 8.5 | 5848 |
| 3/4/2005 | 2005 | 3 | 4 | 277 | 21 | 60 | 40.5 | 8.5 | 5856.5 |
| 3/5/2005 | 2005 | 3 | 5 | 278 | 21 | 60 | 40.5 | 8.5 | 5865 |
| 3/6/2005 | 2005 | 3 | 6 | 279 | 21 | 60 | 40.5 | 8.5 | 5873.5 |
| 3/7/2005 | 2005 | 3 | 7 | 280 | 21 | 53 | 37 | 5 | 5878.5 |
| 3/8/2005 | 2005 | 3 | 8 | 281 | 24 | 63 | 43.5 | 11.5 | 5890 |
| 3/9/2005 | 2005 | 3 | 9 | 282 | 25 | 64 | 44.5 | 12.5 | 5902.5 |
| 3/10/2005 | 2005 | 3 | 10 | 283 | 24 | 70 | 47 | 15 | 5917.5 |
| 3/11/2005 | 2005 | 3 | 11 | 284 | 26 | 71 | 48.5 | 16.5 | 5934 |
| 3/12/2005 | 2005 | 3 | 12 | 285 | 22 | 73 | 47.5 | 15.5 | 5949.5 |
| 3/13/2005 | 2005 | 3 | 13 | 286 | 29 | 73 | 51 | 19 | 5968.5 |
| 3/15/2005 | 2005 | 3 | 15 | 287 | 20 | 39 | 29.5 | -2.5 | 5966 |
| 3/16/2005 | 2005 | 3 | 16 | 288 | 14 | 38 | 26 | -6 | 5960 |
| 3/17/2005 | 2005 | 3 | 17 | 289 | 24 | 52 | 38 | 6 | 5966 |
| 3/18/2005 | 2005 | 3 | 18 | 290 | 33 | 57 | 45 | 13 | 5979 |
| 3/19/2005 | 2005 | 3 | 19 | 291 | 32 | 52 | 42 | 10 | 5989 |
| 3/20/2005 | 2005 | 3 | 20 | 292 | 31 | 53 | 42 | 10 | 5999 |
| 3/21/2005 | 2005 | 3 | 21 | 293 | 32 | 54 | 43 | 11 | 6010 |
| 3/22/2005 | 2005 | 3 | 22 | 294 | 20 | 54 | 37 | 5 | 6015 |
| 3/23/2005 | 2005 | 3 | 23 | 295 | 28 | 61 | 44.5 | 12.5 | 6027.5 |
| 3/24/2005 | 2005 | 3 | 24 | 296 | 32 | 58 | 45 | 13 | 6040.5 |
| 3/25/2005 | 2005 | 3 | 25 | 297 | 28 | 55 | 41.5 | 9.5 | 6050 |
| 3/26/2005 | 2005 | 3 | 26 | 298 | 28 | 55 | 41.5 | 9.5 | 6059.5 |
| 3/27/2005 | 2005 | 3 | 27 | 299 | 17 | 52 | 34.5 | 2.5 | 6062 |
| 3/28/2005 | 2005 | 3 | 28 | 300 | 25 | 65 | 45 | 13 | 6075 |
| 3/29/2005 | 2005 | 3 | 29 | 301 | 33 | 70 | 51.5 | 19.5 | 6094.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/30/2005 | 2005 | 3 | 30 | 302 | 30 | 54 | 42 | 10 | 6104.5 |
| 3/31/2005 | 2005 | 3 | 31 | 303 | 20 | 53 | 36.5 | 4.5 | 6109 |
| 4/1/2005 | 2005 | 4 | 1 | 304 | 15 | 53 | 34 | 2 | 6111 |
| 4/2/2005 | 2005 | 4 | 2 | 305 | 18 | 66 | 42 | 10 | 6121 |
| 4/3/2005 | 2005 | 4 | 3 | 306 | 33 | 70 | 51.5 | 19.5 | 6140.5 |
| 4/4/2005 | 2005 | 4 | 4 | 307 | 31 | 73 | 52 | 20 | 6160.5 |
| 4/5/2005 | 2005 | 4 | 5 | 308 | 34 | 70 | 52 | 20 | 6180.5 |
| 4/6/2005 | 2005 | 4 | 6 | 309 | 24 | 71 | 47.5 | 15.5 | 6196 |
| 4/7/2005 | 2005 | 4 | 7 | 310 | 35 | 75 | 55 | 23 | 6219 |
| 4/8/2005 | 2005 | 4 | 8 | 311 | 34 | 71 | 52.5 | 20.5 | 6239.5 |
| 4/9/2005 | 2005 | 4 | 9 | 312 | 33 | 65 | 49 | 17 | 6256.5 |
| 4/10/2005 | 2005 | 4 | 10 | 313 | 30 | 59 | 44.5 | 12.5 | 6269 |
| 4/11/2005 | 2005 | 4 | 11 | 314 | 24 | 53 | 38.5 | 6.5 | 6275.5 |
| 4/12/2005 | 2005 | 4 | 12 | 315 | 20 | 65 | 42.5 | 10.5 | 6286 |
| 4/13/2005 | 2005 | 4 | 13 | 316 | 23 | 72 | 47.5 | 15.5 | 6301.5 |
| 4/14/2005 | 2005 | 4 | 14 | 317 | 34 | 75 | 54.5 | 22.5 | 6324 |
| 4/15/2005 | 2005 | 4 | 15 | 318 | 36 | 75 | 55.5 | 23.5 | 6347.5 |
| 4/16/2005 | 2005 | 4 | 16 | 319 | 37 | 76 | 56.5 | 24.5 | 6372 |
| 4/17/2005 | 2005 | 4 | 17 | 320 | 40 | 74 | 57 | 25 | 6397 |
| 4/18/2005 | 2005 | 4 | 18 | 321 | 31 | 77 | 54 | 22 | 6419 |
| 4/19/2005 | 2005 | 4 | 19 | 322 | 35 | 76 | 55.5 | 23.5 | 6442.5 |
| 4/20/2005 | 2005 | 4 | 20 | 323 | 30 | 77 | 53.5 | 21.5 | 6464 |
| 4/21/2005 | 2005 | 4 | 21 | 324 | 24 | 73 | 48.5 | 16.5 | 6480.5 |
| 4/22/2005 | 2005 | 4 | 22 | 325 | 28 | 74 | 51 | 19 | 6499.5 |
| 4/23/2005 | 2005 | 4 | 23 | 326 | 40 | 74 | 57 | 25 | 6524.5 |
| 4/24/2005 | 2005 | 4 | 24 | 327 | 40 | 73 | 56.5 | 24.5 | 6549 |
| 4/25/2005 | 2005 | 4 | 25 | 328 | 38 | 68 | 53 | 21 | 6570 |
| 4/26/2005 | 2005 | 4 | 26 | 329 | 32 | 61 | 46.5 | 14.5 | 6584.5 |
| 4/27/2005 | 2005 | 4 | 27 | 330 | 32 | 68 | 50 | 18 | 6602.5 |
| 4/28/2005 | 2005 | 4 | 28 | 331 | 34 | 67 | 50.5 | 18.5 | 6621 |
| 4/29/2005 | 2005 | 4 | 29 | 332 | 32 | 63 | 47.5 | 15.5 | 6636.5 |
| 4/30/2005 | 2005 | 4 | 30 | 333 | 30 | 64 | 47 | 15 | 6651.5 |
| 5/1/2005 | 2005 | 5 | 1 | 334 | 32 | 70 | 51 | 19 | 6670.5 |
| 5/2/2005 | 2005 | 5 | 2 | 335 | 38 | 71 | 54.5 | 22.5 | 6693 |
| 5/3/2005 | 2005 | 5 | 3 | 336 | 35 | 59 | 47 | 15 | 6708 |
| 5/4/2005 | 2005 | 5 | 4 | 337 | 31 | 56 | 43.5 | 11.5 | 6719.5 |
| 5/5/2005 | 2005 | 5 | 5 | 338 | 41 | 73 | 57 | 25 | 6744.5 |
| 5/6/2005 | 2005 | 5 | 6 | 339 | 42 | 74 | 58 | 26 | 6770.5 |
| 5/7/2005 | 2005 | 5 | 7 | 340 | 48 | 75 | 61.5 | 29.5 | 6800 |
| 5/8/2005 | 2005 | 5 | 8 | 341 | 40 | 76 | 58 | 26 | 6826 |
| 5/9/2005 | 2005 | 5 | 9 | 342 | 38 | 77 | 57.5 | 25.5 | 6851.5 |
| 5/10/2005 | 2005 | 5 | 10 | 343 | 41 | 78 | 59.5 | 27.5 | 6879 |
| 5/11/2005 | 2005 | 5 | 11 | 344 | 38 | 80 | 59 | 27 | 6906 |
| 5/12/2005 | 2005 | 5 | 12 | 345 | 26 | 68 | 47 | 15 | 6921 |
| 5/13/2005 | 2005 | 5 | 13 | 346 | 32 | 78 | 55 | 23 | 6944 |
| 5/14/2005 | 2005 | 5 | 14 | 347 | 38 | 80 | 59 | 27 | 6971 |
| 5/15/2005 | 2005 | 5 | 15 | 348 | 37 | 74 | 55.5 | 23.5 | 6994.5 |
| 5/16/2005 | 2005 | 5 | 16 | 349 | 43 | 79 | 61 | 29 | 7023.5 |
| 5/17/2005 | 2005 | 5 | 17 | 350 | 49 | 84 | 66.5 | 34.5 | 7058 |
| 5/18/2005 | 2005 | 5 | 18 | 351 | 49 | 77 | 63 | 31 | 7089 |
| 5/19/2005 | 2005 | 5 | 19 | 352 | 42 | 85 | 63.5 | 31.5 | 7120.5 |
| 5/20/2005 | 2005 | 5 | 20 | 353 | 44 | 93 | 68.5 | 36.5 | 7157 |
| 5/21/2005 | 2005 | 5 | 21 | 354 | 47 | 94 | 70.5 | 38.5 | 7195.5 |
| 5/22/2005 | 2005 | 5 | 22 | 355 | 45 | 96 | 70.5 | 38.5 | 7234 |
| 5/23/2005 | 2005 | 5 | 23 | 356 | 52 | 97 | 74.5 | 42.5 | 7276.5 |
| 5/24/2005 | 2005 | 5 | 24 | 357 | 51 | 94 | 72.5 | 40.5 | 7317 |
| 5/25/2005 | 2005 | 5 | 25 | 358 | 55 | 96 | 75.5 | 43.5 | 7360.5 |
| 5/26/2005 | 2005 | 5 | 26 | 359 | 57 | 95 | 76 | 44 | 7404.5 |
| 5/27/2005 | 2005 | 5 | 27 | 360 | 51 | 96 | 73.5 | 41.5 | 7446 |
| 5/28/2005 | 2005 | 5 | 28 | 361 | 48 | 80 | 64 | 32 | 7478 |
| 5/29/2005 | 2005 | 5 | 29 | 362 | 44 | 78 | 61 | 29 | 7507 |
| 5/30/2005 | 2005 | 5 | 30 | 363 | 52 | 86 | 69 | 37 | 7544 |
| 5/31/2005 | 2005 | 5 | 31 | 364 | 50 | 81 | 65.5 | 33.5 | 7577.5 |
| 6/1/2005 | 2005 | 6 | 1 | 1 | 38 | 86 | 62 | 30 | 30 |
| 6/2/2005 | 2005 | 6 | 2 | 2 | 45 | 87 | 66 | 34 | 64 |
| 6/3/2005 | 2005 | 6 | 3 | 3 | 48 | 83 | 65.5 | 33.5 | 97.5 |
| 6/4/2005 | 2005 | 6 | 4 | 4 | 37 | 81 | 59 | 27 | 124.5 |
| 6/5/2005 | 2005 | 6 | 5 | 5 | 38 | 80 | 59 | 27 | 151.5 |
| 6/6/2005 | 2005 | 6 | 6 | 6 | 46 | 84 | 65 | 33 | 184.5 |
| 6/7/2005 | 2005 | 6 | 7 | 7 | 47 | 86 | 66.5 | 34.5 | 219 |
| 6/8/2005 | 2005 | 6 | 8 | 8 | 44 | 84 | 64 | 32 | 251 |
| 6/9/2005 | 2005 | 6 | 9 | 9 | 43 | 83 | 63 | 31 | 282 |
| 6/10/2005 | 2005 | 6 | 10 | 10 | 43 | 83 | 63 | 31 | 313 |
| 6/11/2005 | 2005 | 6 | 11 | 11 | 49 | 78 | 63.5 | 31.5 | 344.5 |
| 6/12/2005 | 2005 | 6 | 12 | 12 | 47 | 78 | 62.5 | 30.5 | 375 |
| 6/13/2005 | 2005 | 6 | 13 | 13 | 46 | 77 | 61.5 | 29.5 | 404.5 |
| 6/14/2005 | 2005 | 6 | 14 | 14 | 43 | 88 | 65.5 | 33.5 | 438 |
| 6/15/2005 | 2005 | 6 | 15 | 15 | 43 | 88 | 65.5 | 33.5 | 471.5 |
| 6/16/2005 | 2005 | 6 | 16 | 16 | 47 | 95 | 71 | 39 | 510.5 |
| 6/17/2005 | 2005 | 6 | 17 | 17 | 45 | 88 | 66.5 | 34.5 | 545 |
| 6/18/2005 | 2005 | 6 | 18 | 18 | 45 | 90 | 67.5 | 35.5 | 580.5 |
| 6/19/2005 | 2005 | 6 | 19 | 19 | 40 | 93 | 66.5 | 34.5 | 615 |
| 6/20/2005 | 2005 | 6 | 20 | 20 | 52 | 96 | 74 | 42 | 657 |
| 6/21/2005 | 2005 | 6 | 21 | 21 | 61 | 96 | 78.5 | 46.5 | 703.5 |
| 6/22/2005 | 2005 | 6 | 22 | 22 | 52 | 95 | 73.5 | 41.5 | 745 |
| 6/23/2005 | 2005 | 6 | 23 | 23 | 54 | 90 | 72 | 40 | 785 |
| 6/24/2005 | 2005 | 6 | 24 | 24 | 62 | 92 | 77 | 45 | 830 |
| 6/25/2005 | 2005 | 6 | 25 | 25 | 58 | 91 | 74.5 | 42.5 | 872.5 |
| 6/26/2005 | 2005 | 6 | 26 | 26 | 57 | 90 | 73.5 | 41.5 | 914 |
| 6/27/2005 | 2005 | 6 | 27 | 27 | 46 | 90 | 68 | 36 | 950 |
| 6/28/2005 | 2005 | 6 | 28 | 28 | 53 | 92 | 72.5 | 40.5 | 990.5 |
| 6/29/2005 | 2005 | 6 | 29 | 29 | 47 | 91 | 69 | 37 | 1027.5 |
| 6/30/2005 | 2005 | 6 | 30 | 30 | 43 | 95 | 69 | 37 | 1064.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/1/2005 | 2005 | 7 | 1 | 31 | 44 | 97 | 70.5 | 38.5 | 1103 |
| 7/2/2005 | 2005 | 7 | 2 | 32 | 47 | 98 | 72.5 | 40.5 | 1143.5 |
| 7/3/2005 | 2005 | 7 | 3 | 33 | 53 | 97 | 75 | 43 | 1186.5 |
| 7/4/2005 | 2005 | 7 | 4 | 34 | 51 | 96 | 73.5 | 41.5 | 1228 |
| 7/5/2005 | 2005 | 7 | 5 | 35 | 48 | 99 | 73.5 | 41.5 | 1269.5 |
| 7/6/2005 | 2005 | 7 | 6 | 36 | 54 | 96 | 75 | 43 | 1312.5 |
| 7/7/2005 | 2005 | 7 | 7 | 37 | 52 | 98 | 75 | 43 | 1355.5 |
| 7/8/2005 | 2005 | 7 | 8 | 38 | 58 | 98 | 78 | 46 | 1401.5 |
| 7/9/2005 | 2005 | 7 | 9 | 39 | 50 | 95 | 72.5 | 40.5 | 1442 |
| 7/10/2005 | 2005 | 7 | 10 | 40 | 54 | 97 | 75.5 | 43.5 | 1485.5 |
| 7/11/2005 | 2005 | 7 | 11 | 41 | 47 | 93 | 70 | 38 | 1523.5 |
| 7/12/2005 | 2005 | 7 | 12 | 42 | 52 | 99 | 75.5 | 43.5 | 1567 |
| 7/13/2005 | 2005 | 7 | 13 | 43 | 65 | 98 | 81.5 | 49.5 | 1616.5 |
| 7/14/2005 | 2005 | 7 | 14 | 44 | 52 | 105 | 78.5 | 46.5 | 1663 |
| 7/15/2005 | 2005 | 7 | 15 | 45 | 56 | 103 | 79.5 | 47.5 | 1710.5 |
| 7/16/2005 | 2005 | 7 | 16 | 46 | 57 | 95 | 76 | 44 | 1754.5 |
| 7/17/2005 | 2005 | 7 | 17 | 47 | 59 | 101 | 80 | 48 | 1802.5 |
| 7/18/2005 | 2005 | 7 | 18 | 48 | 56 | 102 | 79 | 47 | 1849.5 |
| 7/19/2005 | 2005 | 7 | 19 | 49 | 66 | 100 | 83 | 51 | 1900.5 |
| 7/20/2005 | 2005 | 7 | 20 | 50 | 59 | 105 | 82 | 50 | 1950.5 |
| 7/21/2005 | 2005 | 7 | 21 | 51 | 60 | 102 | 81 | 49 | 1999.5 |
| 7/22/2005 | 2005 | 7 | 22 | 52 | 62 | 101 | 81.5 | 49.5 | 2049 |
| 7/23/2005 | 2005 | 7 | 23 | 53 | 62 | 96 | 79 | 47 | 2096 |
| 7/24/2005 | 2005 | 7 | 24 | 54 | 59 | 93 | 76 | 44 | 2140 |
| 7/25/2005 | 2005 | 7 | 25 | 55 | 60 | 93 | 76.5 | 44.5 | 2184.5 |
| 7/26/2005 | 2005 | 7 | 26 | 56 | 65 | 87 | 76 | 44 | 2228.5 |
| 7/27/2005 | 2005 | 7 | 27 | 57 | 61 | 87 | 74 | 42 | 2270.5 |
| 7/28/2005 | 2005 | 7 | 28 | 58 | 50 | 90 | 70 | 38 | 2308.5 |
| 7/29/2005 | 2005 | 7 | 29 | 59 | 55 | 93 | 74 | 42 | 2350.5 |
| 7/30/2005 | 2005 | 7 | 30 | 60 | 55 | 90 | 72.5 | 40.5 | 2391 |
| 7/31/2005 | 2005 | 7 | 31 | 61 | 60 | 91 | 75.5 | 43.5 | 2434.5 |
| 8/1/2005 | 2005 | 8 | 1 | 62 | 58 | 90 | 74 | 42 | 2476.5 |
| 8/2/2005 | 2005 | 8 | 2 | 63 | 51 | 92 | 71.5 | 39.5 | 2516 |
| 8/3/2005 | 2005 | 8 | 3 | 64 | 60 | 91 | 75.5 | 43.5 | 2559.5 |
| 8/4/2005 | 2005 | 8 | 4 | 65 | 55 | 87 | 71 | 39 | 2598.5 |
| 8/5/2005 | 2005 | 8 | 5 | 66 | 58 | 90 | 74 | 42 | 2640.5 |
| 8/6/2005 | 2005 | 8 | 6 | 67 | 58 | 88 | 73 | 41 | 2681.5 |
| 8/7/2005 | 2005 | 8 | 7 | 68 | 57 | 87 | 72 | 40 | 2721.5 |
| 8/8/2005 | 2005 | 8 | 8 | 69 | 60 | 84 | 72 | 40 | 2761.5 |
| 8/9/2005 | 2005 | 8 | 9 | 70 | 60 | 91 | 75.5 | 43.5 | 2805 |
| 8/10/2005 | 2005 | 8 | 10 | 71 | 60 | 94 | 77 | 45 | 2850 |
| 8/11/2005 | 2005 | 8 | 11 | 72 | 58 | 91 | 74.5 | 42.5 | 2892.5 |
| 8/12/2005 | 2005 | 8 | 12 | 73 | 60 | 89 | 74.5 | 42.5 | 2935 |
| 8/13/2005 | 2005 | 8 | 13 | 74 | 57 | 88 | 72.5 | 40.5 | 2975.5 |
| 8/14/2005 | 2005 | 8 | 14 | 75 | 58 | 85 | 71.5 | 39.5 | 3015 |
| 8/15/2005 | 2005 | 8 | 15 | 76 | 57 | 81 | 69 | 37 | 3052 |
| 8/16/2005 | 2005 | 8 | 16 | 77 | 56 | 76 | 66 | 34 | 3086 |
| 8/17/2005 | 2005 | 8 | 17 | 78 | 56 | 76 | 66 | 34 | 3120 |
| 8/18/2005 | 2005 | 8 | 18 | 79 | 51 | 87 | 69 | 37 | 3157 |
| 8/19/2005 | 2005 | 8 | 19 | 80 | 51 | 88 | 69.5 | 37.5 | 3194.5 |
| 8/20/2005 | 2005 | 8 | 20 | 81 | 50 | 84 | 67 | 35 | 3229.5 |
| 8/21/2005 | 2005 | 8 | 21 | 82 | 52 | 88 | 70 | 38 | 3267.5 |
| 8/22/2005 | 2005 | 8 | 22 | 83 | 52 | 90 | 71 | 39 | 3306.5 |
| 8/23/2005 | 2005 | 8 | 23 | 84 | 58 | 88 | 73 | 41 | 3347.5 |
| 8/24/2005 | 2005 | 8 | 24 | 85 | 57 | 90 | 73.5 | 41.5 | 3389 |
| 8/25/2005 | 2005 | 8 | 25 | 86 | 47 | 91 | 69 | 37 | 3426 |
| 8/26/2005 | 2005 | 8 | 26 | 87 | 51 | 91 | 71 | 39 | 3465 |
| 8/27/2005 | 2005 | 8 | 27 | 88 | 50 | 94 | 72 | 40 | 3505 |
| 8/28/2005 | 2005 | 8 | 28 | 89 | 48 | 96 | 72 | 40 | 3545 |
| 8/29/2005 | 2005 | 8 | 29 | 90 | 48 | 96 | 72 | 40 | 3585 |
| 8/30/2005 | 2005 | 8 | 30 | 91 | 48 | 92 | 70 | 38 | 3623 |
| 8/31/2005 | 2005 | 8 | 31 | 92 | 55 | 95 | 75 | 43 | 3666 |
| 9/1/2005 | 2005 | 9 | 1 | 93 | 60 | 93 | 76.5 | 44.5 | 3710.5 |
| 9/2/2005 | 2005 | 9 | 2 | 94 | 57 | 95 | 76 | 44 | 3754.5 |
| 9/3/2005 | 2005 | 9 | 3 | 95 | 57 | 80 | 68.5 | 36.5 | 3791 |
| 9/4/2005 | 2005 | 9 | 4 | 96 | 53 | 83 | 68 | 36 | 3827 |
| 9/5/2005 | 2005 | 9 | 5 | 97 | 52 | 83 | 67.5 | 35.5 | 3862.5 |
| 9/6/2005 | 2005 | 9 | 6 | 98 | 52 | 85 | 68.5 | 36.5 | 3899 |
| 9/7/2005 | 2005 | 9 | 7 | 99 | 51 | 88 | 69.5 | 37.5 | 3936.5 |
| 9/8/2005 | 2005 | 9 | 8 | 100 | 60 | 82 | 71 | 39 | 3975.5 |
| 9/9/2005 | 2005 | 9 | 9 | 101 | 60 | 82 | 71 | 39 | 4014.5 |
| 9/10/2005 | 2005 | 9 | 10 | 102 | 57 | 79 | 68 | 36 | 4050.5 |
| 9/11/2005 | 2005 | 9 | 11 | 103 | 49 | 83 | 66 | 34 | 4084.5 |
| 9/12/2005 | 2005 | 9 | 12 | 104 | 48 | 81 | 64.5 | 32.5 | 4117 |
| 9/13/2005 | 2005 | 9 | 13 | 105 | 38 | 82 | 60 | 28 | 4145 |
| 9/14/2005 | 2005 | 9 | 14 | 106 | 37 | 81 | 59 | 27 | 4172 |
| 9/15/2005 | 2005 | 9 | 15 | 107 | 34 | 80 | 57 | 25 | 4197 |
| 9/16/2005 | 2005 | 9 | 16 | 108 | 37 | 85 | 61 | 29 | 4226 |
| 9/17/2005 | 2005 | 9 | 17 | 109 | 36 | 87 | 61.5 | 29.5 | 4255.5 |
| 9/18/2005 | 2005 | 9 | 18 | 110 | 37 | 88 | 62.5 | 30.5 | 4286 |
| 9/19/2005 | 2005 | 9 | 19 | 111 | 43 | 89 | 66 | 34 | 4320 |
| 9/20/2005 | 2005 | 9 | 20 | 112 | 43 | 88 | 65.5 | 33.5 | 4353.5 |
| 9/21/2005 | 2005 | 9 | 21 | 113 | 43 | 89 | 66 | 34 | 4387.5 |
| 9/22/2005 | 2005 | 9 | 22 | 114 | 55 | 89 | 72 | 40 | 4427.5 |
| 9/23/2005 | 2005 | 9 | 23 | 115 | 50 | 83 | 66.5 | 34.5 | 4462 |
| 9/24/2005 | 2005 | 9 | 24 | 116 | 48 | 89 | 68.5 | 36.5 | 4498.5 |
| 9/25/2005 | 2005 | 9 | 25 | 117 | 39 | 87 | 63 | 31 | 4529.5 |
| 9/26/2005 | 2005 | 9 | 26 | 118 | 44 | 88 | 66 | 34 | 4563.5 |
| 9/27/2005 | 2005 | 9 | 27 | 119 | 48 | 89 | 68.5 | 36.5 | 4600 |
| 9/28/2005 | 2005 | 9 | 28 | 120 | 49 | 87 | 68 | 36 | 4636 |
| 9/29/2005 | 2005 | 9 | 29 | 121 | 47 | 81 | 64 | 32 | 4668 |
| 9/30/2005 | 2005 | 9 | 30 | 122 | 43 | 57 | 50 | 18 | 4686 |
| 10/1/2005 | 2005 | 10 | 1 | 123 | 46 | 79 | 62.5 | 30.5 | 4716.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/2/2005 | 2005 | 10 | 2 | 124 | 43 | 83 | 63 | 31 | 4747.5 |
| 10/3/2005 | 2005 | 10 | 3 | 125 | 42 | 77 | 59.5 | 27.5 | 4775 |
| 10/4/2005 | 2005 | 10 | 4 | 126 | 44 | 76 | 60 | 28 | 4803 |
| 10/5/2005 | 2005 | 10 | 5 | 127 | 45 | 83 | 64 | 32 | 4835 |
| 10/6/2005 | 2005 | 10 | 6 | 128 | 44 | 79 | 61.5 | 29.5 | 4864.5 |
| 10/7/2005 | 2005 | 10 | 7 | 129 | 42 | 60 | 51 | 19 | 4883.5 |
| 10/8/2005 | 2005 | 10 | 8 | 130 | 41 | 74 | 57.5 | 25.5 | 4909 |
| 10/9/2005 | 2005 | 10 | 9 | 131 | 41 | 81 | 61 | 29 | 4938 |
| 10/10/2005 | 2005 | 10 | 10 | 132 | 40 | 67 | 53.5 | 21.5 | 4959.5 |
| 10/11/2005 | 2005 | 10 | 11 | 133 | 37 | 57 | 47 | 15 | 4974.5 |
| 10/12/2005 | 2005 | 10 | 12 | 134 | 27 | 68 | 47.5 | 15.5 | 4990 |
| 10/13/2005 | 2005 | 10 | 13 | 135 | 30 | 72 | 51 | 19 | 5009 |
| 10/14/2005 | 2005 | 10 | 14 | 136 | 30 | 74 | 52 | 20 | 5029 |
| 10/15/2005 | 2005 | 10 | 15 | 137 | 39 | 71 | 55 | 23 | 5052 |
| 10/16/2005 | 2005 | 10 | 16 | 138 | 43 | 58 | 50.5 | 18.5 | 5070.5 |
| 10/17/2005 | 2005 | 10 | 17 | 139 | 37 | 70 | 53.5 | 21.5 | 5092 |
| 10/18/2005 | 2005 | 10 | 18 | 140 | 39 | 77 | 58 | 26 | 5118 |
| 10/19/2005 | 2005 | 10 | 19 | 141 | 40 | 68 | 54 | 22 | 5140 |
| 10/20/2005 | 2005 | 10 | 20 | 142 | 30 | 67 | 48.5 | 16.5 | 5156.5 |
| 10/21/2005 | 2005 | 10 | 21 | 143 | 32 | 71 | 51.5 | 19.5 | 5176 |
| 10/22/2005 | 2005 | 10 | 22 | 144 | 31 | 72 | 51.5 | 19.5 | 5195.5 |
| 10/23/2005 | 2005 | 10 | 23 | 145 | 32 | 79 | 55.5 | 23.5 | 5219 |
| 10/24/2005 | 2005 | 10 | 24 | 146 | 28 | 72 | 50 | 18 | 5237 |
| 10/25/2005 | 2005 | 10 | 25 | 147 | 28 | 72 | 50 | 18 | 5255 |
| 10/26/2005 | 2005 | 10 | 26 | 148 | 33 | 70 | 51.5 | 19.5 | 5274.5 |
| 10/27/2005 | 2005 | 10 | 27 | 149 | 35 | 71 | 53 | 21 | 5295.5 |
| 10/28/2005 | 2005 | 10 | 28 | 150 | 40 | 73 | 56.5 | 24.5 | 5320 |
| 10/29/2005 | 2005 | 10 | 29 | 151 | 26 | 71 | 48.5 | 16.5 | 5336.5 |
| 10/30/2005 | 2005 | 10 | 30 | 152 | 26 | 71 | 48.5 | 16.5 | 5353 |
| 10/31/2005 | 2005 | 10 | 31 | 153 | 29 | 70 | 49.5 | 17.5 | 5370.5 |
| 11/1/2005 | 2005 | 11 | 1 | 154 | 25 | 67 | 46 | 14 | 5384.5 |
| 11/2/2005 | 2005 | 11 | 2 | 155 | 26 | 71 | 48.5 | 16.5 | 5401 |
| 11/3/2005 | 2005 | 11 | 3 | 156 | 40 | 76 | 58 | 26 | 5427 |
| 11/4/2005 | 2005 | 11 | 4 | 157 | 44 | 67 | 55.5 | 23.5 | 5450.5 |
| 11/5/2005 | 2005 | 11 | 5 | 158 | 32 | 70 | 51 | 19 | 5469.5 |
| 11/6/2005 | 2005 | 11 | 6 | 159 | 24 | 72 | 48 | 16 | 5485.5 |
| 11/7/2005 | 2005 | 11 | 7 | 160 | 34 | 74 | 54 | 22 | 5507.5 |
| 11/8/2005 | 2005 | 11 | 8 | 161 | 27 | 76 | 51.5 | 19.5 | 5527 |
| 11/9/2005 | 2005 | 11 | 9 | 162 | 32 | 77 | 54.5 | 22.5 | 5549.5 |
| 11/10/2005 | 2005 | 11 | 10 | 163 | 28 | 71 | 49.5 | 17.5 | 5567 |
| 11/11/2005 | 2005 | 11 | 11 | 164 | 36 | 74 | 55 | 23 | 5590 |
| 11/12/2005 | 2005 | 11 | 12 | 165 | 33 | 64 | 48.5 | 16.5 | 5606.5 |
| 11/13/2005 | 2005 | 11 | 13 | 166 | 24 | 68 | 46 | 14 | 5620.5 |
| 11/14/2005 | 2005 | 11 | 14 | 167 | 25 | 64 | 44.5 | 12.5 | 5633 |
| 11/15/2005 | 2005 | 11 | 15 | 168 | 28 | 70 | 49 | 17 | 5650 |
| 11/16/2005 | 2005 | 11 | 16 | 169 | 12 | 50 | 31 | -1 | 5649 |
| 11/17/2005 | 2005 | 11 | 17 | 170 | 16 | 64 | 40 | 8 | 5657 |
| 11/18/2005 | 2005 | 11 | 18 | 171 | 14 | 60 | 37 | 5 | 5662 |
| 11/19/2005 | 2005 | 11 | 19 | 172 | 11 | 60 | 35.5 | 3.5 | 5665.5 |
| 11/20/2005 | 2005 | 11 | 20 | 173 | 14 | 64 | 39 | 7 | 5672.5 |
| 11/21/2005 | 2005 | 11 | 21 | 174 | 13 | 66 | 39.5 | 7.5 | 5680 |
| 11/22/2005 | 2005 | 11 | 22 | 175 | 13 | 70 | 41.5 | 9.5 | 5689.5 |
| 11/23/2005 | 2005 | 11 | 23 | 176 | 14 | 71 | 42.5 | 10.5 | 5700 |
| 11/24/2005 | 2005 | 11 | 24 | 177 | 17 | 69 | 43 | 11 | 5711 |
| 11/25/2005 | 2005 | 11 | 25 | 178 | 13 | 68 | 40.5 | 8.5 | 5719.5 |
| 11/26/2005 | 2005 | 11 | 26 | 179 | 17 | 53 | 35 | 3 | 5722.5 |
| 11/27/2005 | 2005 | 11 | 27 | 180 | 6 | 36 | 21 | -11 | 5711.5 |
| 11/28/2005 | 2005 | 11 | 28 | 181 | 9 | 38 | 23.5 | -8.5 | 5703 |
| 11/29/2005 | 2005 | 11 | 29 | 182 | 9 | 38 | 23.5 | -8.5 | 5694.5 |
| 11/30/2005 | 2005 | 11 | 30 | 183 | 15 | 60 | 37.5 | 5.5 | 5700 |
| 12/1/2005 | 2005 | 12 | 1 | 184 | 15 | 60 | 37.5 | 5.5 | 5705.5 |
| 12/2/2005 | 2005 | 12 | 2 | 185 | 15 | 60 | 37.5 | 5.5 | 5711 |
| 12/3/2005 | 2005 | 12 | 3 | 186 | 42 | 65 | 53.5 | 21.5 | 5732.5 |
| 12/4/2005 | 2005 | 12 | 4 | 187 | 13 | 57 | 35 | 3 | 5735.5 |
| 12/5/2005 | 2005 | 12 | 5 | 188 | 3 | 41 | 22 | -10 | 5725.5 |
| 12/6/2005 | 2005 | 12 | 6 | 189 | 2 | 44 | 23 | -9 | 5716.5 |
| 12/7/2005 | 2005 | 12 | 7 | 190 | 5 | 52 | 28.5 | -3.5 | 5713 |
| 12/8/2005 | 2005 | 12 | 8 | 191 | -1 | 43 | 21 | -11 | 5702 |
| 12/9/2005 | 2005 | 12 | 9 | 192 | 9 | 45 | 27 | -5 | 5697 |
| 12/10/2005 | 2005 | 12 | 10 | 193 | 10 | 56 | 33 | 1 | 5698 |
| 12/11/2005 | 2005 | 12 | 11 | 194 | 10 | 59 | 34.5 | 2.5 | 5700.5 |
| 12/12/2005 | 2005 | 12 | 12 | 195 | 15 | 47 | 31 | -1 | 5699.5 |
| 12/13/2005 | 2005 | 12 | 13 | 196 | 30 | 47 | 38.5 | 6.5 | 5706 |
| 12/14/2005 | 2005 | 12 | 14 | 197 | 15 | 50 | 32.5 | 0.5 | 5706.5 |
| 12/15/2005 | 2005 | 12 | 15 | 198 | 8 | 44 | 26 | -6 | 5700.5 |
| 12/16/2005 | 2005 | 12 | 16 | 199 | 5 | 42 | 23.5 | -8.5 | 5692 |
| 12/17/2005 | 2005 | 12 | 17 | 200 | 3 | 47 | 25 | -7 | 5685 |
| 12/18/2005 | 2005 | 12 | 18 | 201 | 4 | 49 | 26.5 | -5.5 | 5679.5 |
| 12/19/2005 | 2005 | 12 | 19 | 202 | 16 | 58 | 37 | 5 | 5684.5 |
| 12/20/2005 | 2005 | 12 | 20 | 203 | 18 | 57 | 37.5 | 5.5 | 5690 |
| 12/21/2005 | 2005 | 12 | 21 | 204 | 17 | 59 | 38 | 6 | 5696 |
| 12/22/2005 | 2005 | 12 | 22 | 205 | 25 | 64 | 44.5 | 12.5 | 5708.5 |
| 12/23/2005 | 2005 | 12 | 23 | 206 | 19 | 68 | 43.5 | 11.5 | 5720 |
| 12/24/2005 | 2005 | 12 | 24 | 207 | 19 | 68 | 43.5 | 11.5 | 5731.5 |
| 12/25/2005 | 2005 | 12 | 25 | 208 | 15 | 64 | 39.5 | 7.5 | 5739 |
| 12/26/2005 | 2005 | 12 | 26 | 209 | 17 | 68 | 42.5 | 10.5 | 5749.5 |
| 12/27/2005 | 2005 | 12 | 27 | 210 | 17 | 66 | 41.5 | 9.5 | 5759 |
| 12/28/2005 | 2005 | 12 | 28 | 211 | 17 | 65 | 41 | 9 | 5768 |
| 12/29/2005 | 2005 | 12 | 29 | 212 | 24 | 65 | 44.5 | 12.5 | 5780.5 |
| 12/30/2005 | 2005 | 12 | 30 | 213 | 10 | 64 | 37 | 5 | 5785.5 |
| 12/31/2005 | 2005 | 12 | 31 | 214 | 10 | 64 | 37 | 5 | 5790.5 |
| 1/1/2006 | 2006 | 1 | 1 | 215 | 35 | 63 | 49 | 17 | 5807.5 |
| 1/2/2006 | 2006 | 1 | 2 | 216 | 24 | 61 | 42.5 | 10.5 | 5818 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/3/2006 | 2006 | 1 | 3 | 217 | 37 | 66 | 51.5 | 19.5 | 5837.5 |
| 1/4/2006 | 2006 | 1 | 4 | 218 | 10 | 60 | 35 | 3 | 5840.5 |
| 1/5/2006 | 2006 | 1 | 5 | 219 | 12 | 60 | 36 | 4 | 5844.5 |
| 1/6/2006 | 2006 | 1 | 6 | 220 | 13 | 60 | 36.5 | 4.5 | 5849 |
| 1/7/2006 | 2006 | 1 | 7 | 221 | 17 | 67 | 42 | 10 | 5859 |
| 1/8/2006 | 2006 | 1 | 8 | 222 | 17 | 67 | 42 | 10 | 5869 |
| 1/9/2006 | 2006 | 1 | 9 | 223 | 17 | 67 | 42 | 10 | 5879 |
| 1/10/2006 | 2006 | 1 | 10 | 224 | 3 | 52 | 27.5 | -4.5 | 5874.5 |
| 1/11/2006 | 2006 | 1 | 11 | 225 | 3 | 55 | 29 | -3 | 5871.5 |
| 1/12/2006 | 2006 | 1 | 12 | 226 | 18 | 63 | 40.5 | 8.5 | 5880 |
| 1/13/2006 | 2006 | 1 | 13 | 227 | 9 | 53 | 31 | -1 | 5879 |
| 1/14/2006 | 2006 | 1 | 14 | 228 | 19 | 61 | 40 | 8 | 5887 |
| 1/15/2006 | 2006 | 1 | 15 | 229 | 29 | 60 | 44.5 | 12.5 | 5899.5 |
| 1/16/2006 | 2006 | 1 | 16 | 230 | 19 | 59 | 39 | 7 | 5906.5 |
| 1/17/2006 | 2006 | 1 | 17 | 231 | 5 | 43 | 24 | -8 | 5898.5 |
| 1/18/2006 | 2006 | 1 | 18 | 232 | 11 | 54 | 32.5 | 0.5 | 5899 |
| 1/19/2006 | 2006 | 1 | 19 | 233 | 43 | 51 | 47 | 15 | 5914 |
| 1/20/2006 | 2006 | 1 | 20 | 234 | 19 | 53 | 36 | 4 | 5918 |
| 1/21/2006 | 2006 | 1 | 21 | 235 | 0 | 45 | 22.5 | -9.5 | 5908.5 |
| 1/22/2006 | 2006 | 1 | 22 | 236 | 2 | 46 | 24 | -8 | 5900.5 |
| 1/23/2006 | 2006 | 1 | 23 | 237 | 6 | 53 | 29.5 | -2.5 | 5898 |
| 1/24/2006 | 2006 | 1 | 24 | 238 | 5 | 55 | 30 | -2 | 5896 |
| 1/25/2006 | 2006 | 1 | 25 | 239 | 15 | 51 | 33 | 1 | 5897 |
| 1/26/2006 | 2006 | 1 | 26 | 240 | 19 | 36 | 27.5 | -4.5 | 5892.5 |
| 1/27/2006 | 2006 | 1 | 27 | 241 | 15 | 50 | 32.5 | 0.5 | 5893 |
| 1/28/2006 | 2006 | 1 | 28 | 242 | 23 | 47 | 35 | 3 | 5896 |
| 1/29/2006 | 2006 | 1 | 29 | 243 | 20 | 50 | 35 | 3 | 5899 |
| 1/30/2006 | 2006 | 1 | 30 | 244 | 18 | 53 | 35.5 | 3.5 | 5902.5 |
| 1/31/2006 | 2006 | 1 | 31 | 245 | 19 | 60 | 39.5 | 7.5 | 5910 |
| 2/1/2006 | 2006 | 2 | 1 | 246 | 17 | 62 | 39.5 | 7.5 | 5917.5 |
| 2/2/2006 | 2006 | 2 | 2 | 247 | 21 | 60 | 40.5 | 8.5 | 5926 |
| 2/3/2006 | 2006 | 2 | 3 | 248 | 24 | 60 | 42 | 10 | 5936 |
| 2/4/2006 | 2006 | 2 | 4 | 249 | 13 | 56 | 34.5 | 2.5 | 5938.5 |
| 2/5/2006 | 2006 | 2 | 5 | 250 | 15 | 68 | 41.5 | 9.5 | 5948 |
| 2/6/2006 | 2006 | 2 | 6 | 251 | 14 | 60 | 37 | 5 | 5953 |
| 2/7/2006 | 2006 | 2 | 7 | 252 | 9 | 55 | 32 | 0 | 5953 |
| 2/8/2006 | 2006 | 2 | 8 | 253 | 10 | 60 | 35 | 3 | 5956 |
| 2/9/2006 | 2006 | 2 | 9 | 254 | 11 | 66 | 38.5 | 6.5 | 5962.5 |
| 2/10/2006 | 2006 | 2 | 10 | 255 | 9 | 56 | 32.5 | 0.5 | 5963 |
| 2/11/2006 | 2006 | 2 | 11 | 256 | 9 | 63 | 36 | 4 | 5967 |
| 2/12/2006 | 2006 | 2 | 12 | 257 | 5 | 50 | 27.5 | -4.5 | 5962.5 |
| 2/13/2006 | 2006 | 2 | 13 | 258 | 7 | 60 | 33.5 | 1.5 | 5964 |
| 2/14/2006 | 2006 | 2 | 14 | 259 | 9 | 64 | 36.5 | 4.5 | 5968.5 |
| 2/15/2006 | 2006 | 2 | 15 | 260 | 26 | 66 | 46 | 14 | 5982.5 |
| 2/16/2006 | 2006 | 2 | 16 | 261 | 26 | 64 | 45 | 13 | 5995.5 |
| 2/17/2006 | 2006 | 2 | 17 | 262 | 26 | 52 | 39 | 7 | 6002.5 |
| 2/18/2006 | 2006 | 2 | 18 | 263 | 25 | 40 | 32.5 | 0.5 | 6003 |
| 2/19/2006 | 2006 | 2 | 19 | 264 | 17 | 60 | 38.5 | 6.5 | 6009.5 |
| 2/20/2006 | 2006 | 2 | 20 | 265 | 19 | 60 | 39.5 | 7.5 | 6017 |
| 2/21/2006 | 2006 | 2 | 21 | 266 | 10 | 56 | 33 | 1 | 6018 |
| 2/22/2006 | 2006 | 2 | 22 | 267 | 9 | 54 | 31.5 | -0.5 | 6017.5 |
| 2/23/2006 | 2006 | 2 | 23 | 268 | 10 | 56 | 33 | 1 | 6018.5 |
| 2/24/2006 | 2006 | 2 | 24 | 269 | 10 | 52 | 31 | -1 | 6017.5 |
| 2/25/2006 | 2006 | 2 | 25 | 270 | 12 | 65 | 38.5 | 6.5 | 6024 |
| 2/26/2006 | 2006 | 2 | 26 | 271 | 15 | 66 | 40.5 | 8.5 | 6032.5 |
| 2/27/2006 | 2006 | 2 | 27 | 272 | 20 | 62 | 41 | 9 | 6041.5 |
| 2/28/2006 | 2006 | 2 | 28 | 273 | 29 | 75 | 52 | 20 | 6061.5 |
| 3/1/2006 | 2006 | 3 | 1 | 274 | 36 | 75 | 55.5 | 23.5 | 6085 |
| 3/2/2006 | 2006 | 3 | 2 | 275 | 22 | 63 | 42.5 | 10.5 | 6095.5 |
| 3/3/2006 | 2006 | 3 | 3 | 276 | 26 | 65 | 45.5 | 13.5 | 6109 |
| 3/4/2006 | 2006 | 3 | 4 | 277 | 28 | 63 | 45.5 | 13.5 | 6122.5 |
| 3/5/2006 | 2006 | 3 | 5 | 278 | 13 | 63 | 38 | 6 | 6128.5 |
| 3/6/2006 | 2006 | 3 | 6 | 279 | 41 | 74 | 57.5 | 25.5 | 6154 |
| 3/7/2006 | 2006 | 3 | 7 | 280 | 41 | 74 | 57.5 | 25.5 | 6179.5 |
| 3/8/2006 | 2006 | 3 | 8 | 281 | 31 | 63 | 47 | 15 | 6194.5 |
| 3/9/2006 | 2006 | 3 | 9 | 282 | 21 | 53 | 37 | 5 | 6199.5 |
| 3/10/2006 | 2006 | 3 | 10 | 283 | 42 | 50 | 46 | 14 | 6213.5 |
| 3/11/2006 | 2006 | 3 | 11 | 284 | 23 | 52 | 37.5 | 5.5 | 6219 |
| 3/12/2006 | 2006 | 3 | 12 | 285 | 22 | 47 | 34.5 | 2.5 | 6221.5 |
| 3/13/2006 | 2006 | 3 | 13 | 286 | 5 | 34 | 19.5 | -12.5 | 6209 |
| 3/14/2006 | 2006 | 3 | 14 | 287 | 9 | 45 | 27 | -5 | 6204 |
| 3/15/2006 | 2006 | 3 | 15 | 288 | 36 | 53 | 44.5 | 12.5 | 6216.5 |
| 3/16/2006 | 2006 | 3 | 16 | 289 | 36 | 53 | 44.5 | 12.5 | 6229 |
| 3/17/2006 | 2006 | 3 | 17 | 290 | 36 | 53 | 44.5 | 12.5 | 6241.5 |
| 3/18/2006 | 2006 | 3 | 18 | 291 | 22 | 65 | 43.5 | 11.5 | 6253 |
| 3/19/2006 | 2006 | 3 | 19 | 292 | 23 | 63 | 43 | 11 | 6264 |
| 3/20/2006 | 2006 | 3 | 20 | 293 | 23 | 63 | 43 | 11 | 6275 |
| 3/21/2006 | 2006 | 3 | 21 | 294 | 23 | 53 | 38 | 6 | 6281 |
| 3/22/2006 | 2006 | 3 | 22 | 295 | 26 | 54 | 40 | 8 | 6289 |
| 3/23/2006 | 2006 | 3 | 23 | 296 | 16 | 57 | 36.5 | 4.5 | 6293.5 |
| 3/24/2006 | 2006 | 3 | 24 | 297 | 20 | 62 | 41 | 9 | 6302.5 |
| 3/25/2006 | 2006 | 3 | 25 | 298 | 23 | 70 | 46.5 | 14.5 | 6317 |
| 3/26/2006 | 2006 | 3 | 26 | 299 | 32 | 70 | 51 | 19 | 6336 |
| 3/27/2006 | 2006 | 3 | 27 | 300 | 32 | 66 | 49 | 17 | 6353 |
| 3/28/2006 | 2006 | 3 | 28 | 301 | 41 | 66 | 53.5 | 21.5 | 6374.5 |
| 3/29/2006 | 2006 | 3 | 29 | 302 | 32 | 60 | 46 | 14 | 6388.5 |
| 3/30/2006 | 2006 | 3 | 30 | 303 | 33 | 65 | 49 | 17 | 6405.5 |
| 3/31/2006 | 2006 | 3 | 31 | 304 | 28 | 60 | 44 | 12 | 6417.5 |
| 4/1/2006 | 2006 | 4 | 1 | 305 | 43 | 68 | 55.5 | 23.5 | 6441 |
| 4/2/2006 | 2006 | 4 | 2 | 306 | 28 | 64 | 46 | 14 | 6455 |
| 4/3/2006 | 2006 | 4 | 3 | 307 | 33 | 70 | 51.5 | 19.5 | 6474.5 |
| 4/4/2006 | 2006 | 4 | 4 | 308 | 43 | 70 | 56.5 | 24.5 | 6499 |
| 4/5/2006 | 2006 | 4 | 5 | 309 | 38 | 73 | 55.5 | 23.5 | 6522.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/6/2006 | 2006 | 4 | 6 | 310 | 36 | 68 | 52 | 20 | 6542.5 |
| 4/7/2006 | 2006 | 4 | 7 | 311 | 32 | 64 | 48 | 16 | 6558.5 |
| 4/8/2006 | 2006 | 4 | 8 | 312 | 35 | 72 | 53.5 | 21.5 | 6580 |
| 4/9/2006 | 2006 | 4 | 9 | 313 | 37 | 77 | 57 | 25 | 6605 |
| 4/10/2006 | 2006 | 4 | 10 | 314 | 36 | 79 | 57.5 | 25.5 | 6630.5 |
| 4/11/2006 | 2006 | 4 | 11 | 315 | 33 | 74 | 53.5 | 21.5 | 6652 |
| 4/12/2006 | 2006 | 4 | 12 | 316 | 27 | 71 | 49 | 17 | 6669 |
| 4/13/2006 | 2006 | 4 | 13 | 317 | 32 | 80 | 56 | 24 | 6693 |
| 4/14/2006 | 2006 | 4 | 14 | 318 | 43 | 80 | 61.5 | 29.5 | 6722.5 |
| 4/15/2006 | 2006 | 4 | 15 | 319 | 44 | 77 | 60.5 | 28.5 | 6751 |
| 4/16/2006 | 2006 | 4 | 16 | 320 | 32 | 75 | 53.5 | 21.5 | 6772.5 |
| 4/17/2006 | 2006 | 4 | 17 | 321 | 41 | 78 | 59.5 | 27.5 | 6800 |
| 4/18/2006 | 2006 | 4 | 18 | 322 | 22 | 67 | 44.5 | 12.5 | 6812.5 |
| 4/19/2006 | 2006 | 4 | 19 | 323 | 28 | 72 | 50 | 18 | 6830.5 |
| 4/20/2006 | 2006 | 4 | 20 | 324 | 30 | 78 | 54 | 22 | 6852.5 |
| 4/21/2006 | 2006 | 4 | 21 | 325 | 27 | 78 | 52.5 | 20.5 | 6873 |
| 4/22/2006 | 2006 | 4 | 22 | 326 | 40 | 80 | 60 | 28 | 6901 |
| 4/23/2006 | 2006 | 4 | 23 | 327 | 35 | 80 | 57.5 | 25.5 | 6926.5 |
| 4/24/2006 | 2006 | 4 | 24 | 328 | 35 | 80 | 57.5 | 25.5 | 6952 |
| 4/25/2006 | 2006 | 4 | 25 | 329 | 25 | 80 | 52.5 | 20.5 | 6972.5 |
| 4/26/2006 | 2006 | 4 | 26 | 330 | 34 | 74 | 54 | 22 | 6994.5 |
| 4/27/2006 | 2006 | 4 | 27 | 331 | 32 | 75 | 53.5 | 21.5 | 7016 |
| 4/28/2006 | 2006 | 4 | 28 | 332 | 34 | 77 | 55.5 | 23.5 | 7039.5 |
| 4/29/2006 | 2006 | 4 | 29 | 333 | 32 | 67 | 49.5 | 17.5 | 7057 |
| 4/30/2006 | 2006 | 4 | 30 | 334 | 30 | 73 | 51.5 | 19.5 | 7076.5 |
| 5/1/2006 | 2006 | 5 | 1 | 335 | 41 | 83 | 62 | 30 | 7106.5 |
| 5/2/2006 | 2006 | 5 | 2 | 336 | 40 | 84 | 62 | 30 | 7136.5 |
| 5/3/2006 | 2006 | 5 | 3 | 337 | 38 | 84 | 61 | 29 | 7165.5 |
| 5/4/2006 | 2006 | 5 | 4 | 338 | 40 | 81 | 60.5 | 28.5 | 7194 |
| 5/5/2006 | 2006 | 5 | 5 | 339 | 38 | 83 | 60.5 | 28.5 | 7222.5 |
| 5/6/2006 | 2006 | 5 | 6 | 340 | 34 | 74 | 54 | 22 | 7244.5 |
| 5/7/2006 | 2006 | 5 | 7 | 341 | 39 | 81 | 60 | 28 | 7272.5 |
| 5/8/2006 | 2006 | 5 | 8 | 342 | 37 | 80 | 58.5 | 26.5 | 7299 |
| 5/9/2006 | 2006 | 5 | 9 | 343 | 40 | 88 | 64 | 32 | 7331 |
| 5/10/2006 | 2006 | 5 | 10 | 344 | 33 | 73 | 53 | 21 | 7352 |
| 5/11/2006 | 2006 | 5 | 11 | 345 | 38 | 78 | 58 | 26 | 7378 |
| 5/12/2006 | 2006 | 5 | 12 | 346 | 38 | 81 | 59.5 | 27.5 | 7405.5 |
| 5/13/2006 | 2006 | 5 | 13 | 347 | 38 | 81 | 59.5 | 27.5 | 7433 |
| 5/14/2006 | 2006 | 5 | 14 | 348 | 42 | 90 | 66 | 34 | 7467 |
| 5/15/2006 | 2006 | 5 | 15 | 349 | 50 | 92 | 71 | 39 | 7506 |
| 5/16/2006 | 2006 | 5 | 16 | 350 | 42 | 73 | 57.5 | 25.5 | 7531.5 |
| 5/17/2006 | 2006 | 5 | 17 | 351 | 52 | 90 | 71 | 39 | 7570.5 |
| 5/18/2006 | 2006 | 5 | 18 | 352 | 51 | 91 | 71 | 39 | 7609.5 |
| 5/19/2006 | 2006 | 5 | 19 | 353 | 50 | 93 | 71.5 | 39.5 | 7649 |
| 5/20/2006 | 2006 | 5 | 20 | 354 | 51 | 91 | 71 | 39 | 7688 |
| 5/21/2006 | 2006 | 5 | 21 | 355 | 51 | 92 | 71.5 | 39.5 | 7727.5 |
| 5/22/2006 | 2006 | 5 | 22 | 356 | 48 | 90 | 69 | 37 | 7764.5 |
| 5/23/2006 | 2006 | 5 | 23 | 357 | 42 | 78 | 60 | 28 | 7792.5 |
| 5/24/2006 | 2006 | 5 | 24 | 358 | 42 | 88 | 65 | 33 | 7825.5 |
| 5/25/2006 | 2006 | 5 | 25 | 359 | 42 | 94 | 68 | 36 | 7861.5 |
| 5/26/2006 | 2006 | 5 | 26 | 360 | 50 | 94 | 72 | 40 | 7901.5 |
| 5/27/2006 | 2006 | 5 | 27 | 361 | 49 | 88 | 68.5 | 36.5 | 7938 |
| 5/28/2006 | 2006 | 5 | 28 | 362 | 49 | 88 | 68.5 | 36.5 | 7974.5 |
| 5/29/2006 | 2006 | 5 | 29 | 363 | 36 | 85 | 60.5 | 28.5 | 8003 |
| 5/30/2006 | 2006 | 5 | 30 | 364 | 40 | 84 | 62 | 30 | 8033 |
| 5/31/2006 | 2006 | 5 | 31 | 365 | 43 | 86 | 64.5 | 32.5 | 8065.5 |
| 6/1/2006 | 2006 | 6 | 1 | 1 | 50 | 87 | 68.5 | 36.5 | 36.5 |
| 6/2/2006 | 2006 | 6 | 2 | 2 | 49 | 89 | 69 | 37 | 73.5 |
| 6/3/2006 | 2006 | 6 | 3 | 3 | 50 | 91 | 70.5 | 38.5 | 112 |
| 6/4/2006 | 2006 | 6 | 4 | 4 | 49 | 95 | 72 | 40 | 152 |
| 6/5/2006 | 2006 | 6 | 5 | 5 | 50 | 97 | 73.5 | 41.5 | 193.5 |
| 6/6/2006 | 2006 | 6 | 6 | 6 | 50 | 99 | 74.5 | 42.5 | 236 |
| 6/7/2006 | 2006 | 6 | 7 | 7 | 59 | 97 | 78 | 46 | 282 |
| 6/8/2006 | 2006 | 6 | 8 | 8 | 46 | 86 | 66 | 34 | 316 |
| 6/9/2006 | 2006 | 6 | 9 | 9 | 54 | 86 | 70 | 38 | 354 |
| 6/10/2006 | 2006 | 6 | 10 | 10 | 48 | 86 | 67 | 35 | 389 |
| 6/11/2006 | 2006 | 6 | 11 | 11 | 48 | 91 | 69.5 | 37.5 | 426.5 |
| 6/12/2006 | 2006 | 6 | 12 | 12 | 48 | 94 | 71 | 39 | 465.5 |
| 6/13/2006 | 2006 | 6 | 13 | 13 | 57 | 97 | 77 | 45 | 510.5 |
| 6/14/2006 | 2006 | 6 | 14 | 14 | 59 | 96 | 77.5 | 45.5 | 556 |
| 6/15/2006 | 2006 | 6 | 15 | 15 | 58 | 95 | 76.5 | 44.5 | 600.5 |
| 6/16/2006 | 2006 | 6 | 16 | 16 | 50 | 96 | 73 | 41 | 641.5 |
| 6/17/2006 | 2006 | 6 | 17 | 17 | 45 | 91 | 68 | 36 | 677.5 |
| 6/18/2006 | 2006 | 6 | 18 | 18 | 49 | 92 | 70.5 | 38.5 | 716 |
| 6/19/2006 | 2006 | 6 | 19 | 19 | 44 | 98 | 71 | 39 | 755 |
| 6/20/2006 | 2006 | 6 | 20 | 20 | 50 | 97 | 73.5 | 41.5 | 796.5 |
| 6/21/2006 | 2006 | 6 | 21 | 21 | 49 | 98 | 73.5 | 41.5 | 838 |
| 6/22/2006 | 2006 | 6 | 22 | 22 | 54 | 98 | 76 | 44 | 882 |
| 6/23/2006 | 2006 | 6 | 23 | 23 | 60 | 98 | 79 | 47 | 929 |
| 6/24/2006 | 2006 | 6 | 24 | 24 | 70 | 99 | 84.5 | 52.5 | 981.5 |
| 6/25/2006 | 2006 | 6 | 25 | 25 | 71 | 99 | 85 | 53 | 1034.5 |
| 6/26/2006 | 2006 | 6 | 26 | 26 | 61 | 84 | 72.5 | 40.5 | 1075 |
| 6/27/2006 | 2006 | 6 | 27 | 27 | 52 | 84 | 68 | 36 | 1111 |
| 6/28/2006 | 2006 | 6 | 28 | 28 | 49 | 85 | 67 | 35 | 1146 |
| 6/29/2006 | 2006 | 6 | 29 | 29 | 56 | 90 | 73 | 41 | 1187 |
| 6/30/2006 | 2006 | 6 | 30 | 30 | 55 | 95 | 75 | 43 | 1230 |
| 7/1/2006 | 2006 | 7 | 1 | 31 | 55 | 96 | 75.5 | 43.5 | 1273.5 |
| 7/2/2006 | 2006 | 7 | 2 | 32 | 54 | 84 | 69 | 37 | 1310.5 |
| 7/3/2006 | 2006 | 7 | 3 | 33 | 59 | 96 | 77.5 | 45.5 | 1356 |
| 7/4/2006 | 2006 | 7 | 4 | 34 | 57 | 96 | 76.5 | 44.5 | 1400.5 |
| 7/5/2006 | 2006 | 7 | 5 | 35 | 65 | 96 | 80.5 | 48.5 | 1449 |
| 7/6/2006 | 2006 | 7 | 6 | 36 | 56 | 84 | 70 | 38 | 1487 |
| 7/7/2006 | 2006 | 7 | 7 | 37 | 60 | 79 | 69.5 | 37.5 | 1524.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/8/2006 | 2006 | 7 | 8 | 38 | 54 | 74 | 64 | 32 | 1556.5 |
| 7/9/2006 | 2006 | 7 | 9 | 39 | 55 | 78 | 66.5 | 34.5 | 1591 |
| 7/10/2006 | 2006 | 7 | 10 | 40 | 56 | 86 | 71 | 39 | 1630 |
| 7/11/2006 | 2006 | 7 | 11 | 41 | 56 | 86 | 71 | 39 | 1669 |
| 7/12/2006 | 2006 | 7 | 12 | 42 | 55 | 93 | 74 | 42 | 1711 |
| 7/13/2006 | 2006 | 7 | 13 | 43 | 56 | 96 | 76 | 44 | 1755 |
| 7/14/2006 | 2006 | 7 | 14 | 44 | 54 | 99 | 76.5 | 44.5 | 1799.5 |
| 7/15/2006 | 2006 | 7 | 15 | 45 | 64 | 99 | 81.5 | 49.5 | 1849 |
| 7/16/2006 | 2006 | 7 | 16 | 46 | 61 | 93 | 77 | 45 | 1894 |
| 7/17/2006 | 2006 | 7 | 17 | 47 | 60 | 95 | 77.5 | 45.5 | 1939.5 |
| 7/18/2006 | 2006 | 7 | 18 | 48 | 63 | 98 | 80.5 | 48.5 | 1988 |
| 7/19/2006 | 2006 | 7 | 19 | 49 | 65 | 94 | 79.5 | 47.5 | 2035.5 |
| 7/20/2006 | 2006 | 7 | 20 | 50 | 57 | 90 | 73.5 | 41.5 | 2077 |
| 7/21/2006 | 2006 | 7 | 21 | 51 | 55 | 95 | 75 | 43 | 2120 |
| 7/22/2006 | 2006 | 7 | 22 | 52 | 64 | 99 | 81.5 | 49.5 | 2169.5 |
| 7/23/2006 | 2006 | 7 | 23 | 53 | 58 | 90 | 74 | 42 | 2211.5 |
| 7/24/2006 | 2006 | 7 | 24 | 54 | 56 | 96 | 76 | 44 | 2255.5 |
| 7/25/2006 | 2006 | 7 | 25 | 55 | 61 | 99 | 80 | 48 | 2303.5 |
| 7/26/2006 | 2006 | 7 | 26 | 56 | 58 | 96 | 77 | 45 | 2348.5 |
| 7/27/2006 | 2006 | 7 | 27 | 57 | 62 | 97 | 79.5 | 47.5 | 2396 |
| 7/28/2006 | 2006 | 7 | 28 | 58 | 59 | 94 | 76.5 | 44.5 | 2440.5 |
| 7/29/2006 | 2006 | 7 | 29 | 59 | 60 | 80 | 70 | 38 | 2478.5 |
| 7/30/2006 | 2006 | 7 | 30 | 60 | 59 | 81 | 70 | 38 | 2516.5 |
| 7/31/2006 | 2006 | 7 | 31 | 61 | 65 | 85 | 75 | 43 | 2559.5 |
| 8/1/2006 | 2006 | 8 | 1 | 62 | 63 | 88 | 75.5 | 43.5 | 2603 |
| 8/2/2006 | 2006 | 8 | 2 | 63 | 53 | 84 | 68.5 | 36.5 | 2639.5 |
| 8/3/2006 | 2006 | 8 | 3 | 64 | 60 | 91 | 75.5 | 43.5 | 2683 |
| 8/4/2006 | 2006 | 8 | 4 | 65 | 58 | 84 | 71 | 39 | 2722 |
| 8/5/2006 | 2006 | 8 | 5 | 66 | 57 | 84 | 70.5 | 38.5 | 2760.5 |
| 8/6/2006 | 2006 | 8 | 6 | 67 | 58 | 85 | 71.5 | 39.5 | 2800 |
| 8/7/2006 | 2006 | 8 | 7 | 68 | 57 | 78 | 67.5 | 35.5 | 2835.5 |
| 8/8/2006 | 2006 | 8 | 8 | 69 | 57 | 78 | 67.5 | 35.5 | 2871 |
| 8/9/2006 | 2006 | 8 | 9 | 70 | 59 | 90 | 74.5 | 42.5 | 2913.5 |
| 8/10/2006 | 2006 | 8 | 10 | 71 | 56 | 88 | 72 | 40 | 2953.5 |
| 8/11/2006 | 2006 | 8 | 11 | 72 | 58 | 90 | 74 | 42 | 2995.5 |
| 8/12/2006 | 2006 | 8 | 12 | 73 | 57 | 91 | 74 | 42 | 3037.5 |
| 8/13/2006 | 2006 | 8 | 13 | 74 | 56 | 88 | 72 | 40 | 3077.5 |
| 8/14/2006 | 2006 | 8 | 14 | 75 | 55 | 87 | 71 | 39 | 3116.5 |
| 8/15/2006 | 2006 | 8 | 15 | 76 | 58 | 84 | 71 | 39 | 3155.5 |
| 8/16/2006 | 2006 | 8 | 16 | 77 | 58 | 72 | 65 | 33 | 3188.5 |
| 8/17/2006 | 2006 | 8 | 17 | 78 | 59 | 88 | 73.5 | 41.5 | 3230 |
| 8/18/2006 | 2006 | 8 | 18 | 79 | 58 | 86 | 72 | 40 | 3270 |
| 8/19/2006 | 2006 | 8 | 19 | 80 | 56 | 84 | 70 | 38 | 3308 |
| 8/20/2006 | 2006 | 8 | 20 | 81 | 55 | 78 | 66.5 | 34.5 | 3342.5 |
| 8/21/2006 | 2006 | 8 | 21 | 82 | 53 | 82 | 67.5 | 35.5 | 3378 |
| 8/22/2006 | 2006 | 8 | 22 | 83 | 55 | 80 | 67.5 | 35.5 | 3413.5 |
| 8/23/2006 | 2006 | 8 | 23 | 84 | 54 | 72 | 63 | 31 | 3444.5 |
| 8/24/2006 | 2006 | 8 | 24 | 85 | 57 | 80 | 68.5 | 36.5 | 3481 |
| 8/25/2006 | 2006 | 8 | 25 | 86 | 54 | 84 | 69 | 37 | 3518 |
| 8/26/2006 | 2006 | 8 | 26 | 87 | 50 | 77 | 63.5 | 31.5 | 3549.5 |
| 8/27/2006 | 2006 | 8 | 27 | 88 | 47 | 81 | 64 | 32 | 3581.5 |
| 8/28/2006 | 2006 | 8 | 28 | 89 | 44 | 86 | 65 | 33 | 3614.5 |
| 8/29/2006 | 2006 | 8 | 29 | 90 | 58 | 86 | 72 | 40 | 3654.5 |
| 8/30/2006 | 2006 | 8 | 30 | 91 | 53 | 85 | 69 | 37 | 3691.5 |
| 8/31/2006 | 2006 | 8 | 31 | 92 | 55 | 88 | 71.5 | 39.5 | 3731 |
| 9/1/2006 | 2006 | 9 | 1 | 93 | 55 | 88 | 71.5 | 39.5 | 3770.5 |
| 9/2/2006 | 2006 | 9 | 2 | 94 | 54 | 84 | 69 | 37 | 3807.5 |
| 9/3/2006 | 2006 | 9 | 3 | 95 | 54 | 86 | 70 | 38 | 3845.5 |
| 9/4/2006 | 2006 | 9 | 4 | 96 | 51 | 82 | 66.5 | 34.5 | 3880 |
| 9/5/2006 | 2006 | 9 | 5 | 97 | 49 | 83 | 66 | 34 | 3914 |
| 9/6/2006 | 2006 | 9 | 6 | 98 | 45 | 83 | 64 | 32 | 3946 |
| 9/7/2006 | 2006 | 9 | 7 | 99 | 50 | 84 | 67 | 35 | 3981 |
| 9/8/2006 | 2006 | 9 | 8 | 100 | 52 | 76 | 64 | 32 | 4013 |
| 9/9/2006 | 2006 | 9 | 9 | 101 | 44 | 77 | 60.5 | 28.5 | 4041.5 |
| 9/10/2006 | 2006 | 9 | 10 | 102 | 45 | 79 | 62 | 30 | 4071.5 |
| 9/11/2006 | 2006 | 9 | 11 | 103 | 47 | 80 | 63.5 | 31.5 | 4103 |
| 9/12/2006 | 2006 | 9 | 12 | 104 | 42 | 84 | 63 | 31 | 4134 |
| 9/13/2006 | 2006 | 9 | 13 | 105 | 46 | 85 | 65.5 | 33.5 | 4167.5 |
| 9/14/2006 | 2006 | 9 | 14 | 106 | 45 | 78 | 61.5 | 29.5 | 4197 |
| 9/15/2006 | 2006 | 9 | 15 | 107 | 47 | 75 | 61 | 29 | 4226 |
| 9/16/2006 | 2006 | 9 | 16 | 108 | 42 | 77 | 59.5 | 27.5 | 4253.5 |
| 9/17/2006 | 2006 | 9 | 17 | 109 | 35 | 78 | 56.5 | 24.5 | 4278 |
| 9/18/2006 | 2006 | 9 | 18 | 110 | 28 | 71 | 49.5 | 17.5 | 4295.5 |
| 9/19/2006 | 2006 | 9 | 19 | 111 | 27 | 78 | 52.5 | 20.5 | 4316 |
| 9/20/2006 | 2006 | 9 | 20 | 112 | 32 | 81 | 56.5 | 24.5 | 4340.5 |
| 9/21/2006 | 2006 | 9 | 21 | 113 | 37 | 78 | 57.5 | 25.5 | 4366 |
| 9/22/2006 | 2006 | 9 | 22 | 114 | 42 | 73 | 57.5 | 25.5 | 4391.5 |
| 9/23/2006 | 2006 | 9 | 23 | 115 | 38 | 61 | 49.5 | 17.5 | 4409 |
| 9/24/2006 | 2006 | 9 | 24 | 116 | 29 | 65 | 47 | 15 | 4424 |
| 9/25/2006 | 2006 | 9 | 25 | 117 | 34 | 69 | 51.5 | 19.5 | 4443.5 |
| 9/26/2006 | 2006 | 9 | 26 | 118 | 37 | 80 | 58.5 | 26.5 | 4470 |
| 9/27/2006 | 2006 | 9 | 27 | 119 | 40 | 83 | 61.5 | 29.5 | 4499.5 |
| 9/28/2006 | 2006 | 9 | 28 | 120 | 31 | 82 | 56.5 | 24.5 | 4524 |
| 9/29/2006 | 2006 | 9 | 29 | 121 | 31 | 84 | 57.5 | 25.5 | 4549.5 |
| 9/30/2006 | 2006 | 9 | 30 | 122 | 31 | 88 | 59.5 | 27.5 | 4577 |
| 10/1/2006 | 2006 | 10 | 1 | 123 | 33 | 89 | 61 | 29 | 4606 |
| 10/2/2006 | 2006 | 10 | 2 | 124 | 36 | 86 | 61 | 29 | 4635 |
| 10/3/2006 | 2006 | 10 | 3 | 125 | 42 | 83 | 62.5 | 30.5 | 4665.5 |
| 10/4/2006 | 2006 | 10 | 4 | 126 | 41 | 82 | 61.5 | 29.5 | 4695 |
| 10/5/2006 | 2006 | 10 | 5 | 127 | 53 | 81 | 67 | 35 | 4730 |
| 10/6/2006 | 2006 | 10 | 6 | 128 | 50 | 76 | 63 | 31 | 4761 |
| 10/7/2006 | 2006 | 10 | 7 | 129 | 45 | 74 | 59.5 | 27.5 | 4788.5 |
| 10/8/2006 | 2006 | 10 | 8 | 130 | 47 | 75 | 61 | 29 | 4817.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/9/2006 | 2006 | 10 | 9 | 131 | 45 | 70 | 57.5 | 25.5 | 4843 |
| 10/10/2006 | 2006 | 10 | 10 | 132 | 32 | 59 | 45.5 | 13.5 | 4856.5 |
| 10/11/2006 | 2006 | 10 | 11 | 133 | 33 | 71 | 52 | 20 | 4876.5 |
| 10/12/2006 | 2006 | 10 | 12 | 134 | 32 | 72 | 52 | 20 | 4896.5 |
| 10/13/2006 | 2006 | 10 | 13 | 135 | 31 | 74 | 52.5 | 20.5 | 4917 |
| 10/14/2006 | 2006 | 10 | 14 | 136 | 36 | 77 | 56.5 | 24.5 | 4941.5 |
| 10/15/2006 | 2006 | 10 | 15 | 137 | 43 | 71 | 57 | 25 | 4966.5 |
| 10/16/2006 | 2006 | 10 | 16 | 138 | 33 | 63 | 48 | 16 | 4982.5 |
| 10/17/2006 | 2006 | 10 | 17 | 139 | 35 | 71 | 53 | 21 | 5003.5 |
| 10/18/2006 | 2006 | 10 | 18 | 140 | 34 | 69 | 51.5 | 19.5 | 5023 |
| 10/19/2006 | 2006 | 10 | 19 | 141 | 24 | 62 | 43 | 11 | 5034 |
| 10/20/2006 | 2006 | 10 | 20 | 142 | 26 | 63 | 44.5 | 12.5 | 5046.5 |
| 10/21/2006 | 2006 | 10 | 21 | 143 | 32 | 74 | 53 | 21 | 5067.5 |
| 10/22/2006 | 2006 | 10 | 22 | 144 | 23 | 63 | 43 | 11 | 5078.5 |
| 10/23/2006 | 2006 | 10 | 23 | 145 | 22 | 67 | 44.5 | 12.5 | 5091 |
| 10/24/2006 | 2006 | 10 | 24 | 146 | 40 | 76 | 58 | 26 | 5117 |
| 10/25/2006 | 2006 | 10 | 25 | 147 | 40 | 76 | 58 | 26 | 5143 |
| 10/26/2006 | 2006 | 10 | 26 | 148 | 20 | 66 | 43 | 11 | 5154 |
| 10/27/2006 | 2006 | 10 | 27 | 149 | 26 | 54 | 40 | 8 | 5162 |
| 10/28/2006 | 2006 | 10 | 28 | 150 | 24 | 59 | 41.5 | 9.5 | 5171.5 |
| 10/29/2006 | 2006 | 10 | 29 | 151 | 24 | 70 | 47 | 15 | 5186.5 |
| 10/30/2006 | 2006 | 10 | 30 | 152 | 30 | 63 | 46.5 | 14.5 | 5201 |
| 10/31/2006 | 2006 | 10 | 31 | 153 | 27 | 67 | 47 | 15 | 5216 |
| 11/1/2006 | 2006 | 11 | 1 | 154 | 24 | 67 | 45.5 | 13.5 | 5229.5 |
| 11/2/2006 | 2006 | 11 | 2 | 155 | 23 | 66 | 44.5 | 12.5 | 5242 |
| 11/3/2006 | 2006 | 11 | 3 | 156 | 24 | 69 | 46.5 | 14.5 | 5256.5 |
| 11/4/2006 | 2006 | 11 | 4 | 157 | 24 | 69 | 46.5 | 14.5 | 5271 |
| 11/5/2006 | 2006 | 11 | 5 | 158 | 27 | 73 | 50 | 18 | 5289 |
| 11/6/2006 | 2006 | 11 | 6 | 159 | 25 | 64 | 44.5 | 12.5 | 5301.5 |
| 11/7/2006 | 2006 | 11 | 7 | 160 | 30 | 68 | 49 | 17 | 5318.5 |
| 11/8/2006 | 2006 | 11 | 8 | 161 | 29 | 69 | 49 | 17 | 5335.5 |
| 11/9/2006 | 2006 | 11 | 9 | 162 | 38 | 69 | 53.5 | 21.5 | 5357 |
| 11/10/2006 | 2006 | 11 | 10 | 163 | 38 | 69 | 53.5 | 21.5 | 5378.5 |
| 11/11/2006 | 2006 | 11 | 11 | 164 | 12 | 69 | 40.5 | 8.5 | 5387 |
| 11/12/2006 | 2006 | 11 | 12 | 165 | 34 | 59 | 46.5 | 14.5 | 5401.5 |
| 11/13/2006 | 2006 | 11 | 13 | 166 | 21 | 60 | 40.5 | 8.5 | 5410 |
| 11/14/2006 | 2006 | 11 | 14 | 167 | 27 | 55 | 41 | 9 | 5419 |
| 11/15/2006 | 2006 | 11 | 15 | 168 | 18 | 63 | 40.5 | 8.5 | 5427.5 |
| 11/16/2006 | 2006 | 11 | 16 | 169 | 16 | 65 | 40.5 | 8.5 | 5436 |
| 11/17/2006 | 2006 | 11 | 17 | 170 | 20 | 70 | 45 | 13 | 5449 |
| 11/18/2006 | 2006 | 11 | 18 | 171 | 21 | 71 | 46 | 14 | 5463 |
| 11/19/2006 | 2006 | 11 | 19 | 172 | 19 | 74 | 46.5 | 14.5 | 5477.5 |
| 11/20/2006 | 2006 | 11 | 20 | 173 | 19 | 60 | 39.5 | 7.5 | 5485 |
| 11/21/2006 | 2006 | 11 | 21 | 174 | 18 | 63 | 40.5 | 8.5 | 5493.5 |
| 11/22/2006 | 2006 | 11 | 22 | 175 | 19 | 73 | 46 | 14 | 5507.5 |
| 11/23/2006 | 2006 | 11 | 23 | 176 | 18 | 72 | 45 | 13 | 5520.5 |
| 11/24/2006 | 2006 | 11 | 24 | 177 | 23 | 71 | 47 | 15 | 5535.5 |
| 11/25/2006 | 2006 | 11 | 25 | 178 | 25 | 62 | 43.5 | 11.5 | 5547 |
| 11/26/2006 | 2006 | 11 | 26 | 179 | 19 | 62 | 40.5 | 8.5 | 5555.5 |
| 11/27/2006 | 2006 | 11 | 27 | 180 | 18 | 61 | 39.5 | 7.5 | 5563 |
| 11/28/2006 | 2006 | 11 | 28 | 181 | 22 | 55 | 38.5 | 6.5 | 5569.5 |
| 11/29/2006 | 2006 | 11 | 29 | 182 | 21 | 50 | 35.5 | 3.5 | 5573 |
| 11/30/2006 | 2006 | 11 | 30 | 183 | -10 | 28 | 9 | -23 | 5550 |
| 12/1/2006 | 2006 | 12 | 1 | 184 | -1 | 41 | 20 | -12 | 5538 |
| 12/2/2006 | 2006 | 12 | 2 | 185 | -2 | 43 | 20.5 | -11.5 | 5526.5 |
| 12/3/2006 | 2006 | 12 | 3 | 186 | -1 | 39 | 19 | -13 | 5513.5 |
| 12/4/2006 | 2006 | 12 | 4 | 187 | -1 | 39 | 19 | -13 | 5500.5 |
| 12/5/2006 | 2006 | 12 | 5 | 188 | 2 | 43 | 22.5 | -9.5 | 5491 |
| 12/6/2006 | 2006 | 12 | 6 | 189 | 10 | 55 | 32.5 | 0.5 | 5491.5 |
| 12/7/2006 | 2006 | 12 | 7 | 190 | 16 | 55 | 35.5 | 3.5 | 5495 |
| 12/8/2006 | 2006 | 12 | 8 | 191 | 15 | 48 | 31.5 | -0.5 | 5494.5 |
| 12/9/2006 | 2006 | 12 | 9 | 192 | 18 | 54 | 36 | 4 | 5498.5 |
| 12/10/2006 | 2006 | 12 | 10 | 193 | 18 | 53 | 35.5 | 3.5 | 5502 |
| 12/11/2006 | 2006 | 12 | 11 | 194 | 22 | 51 | 36.5 | 4.5 | 5506.5 |
| 12/12/2006 | 2006 | 12 | 12 | 195 | 18 | 52 | 35 | 3 | 5509.5 |
| 12/13/2006 | 2006 | 12 | 13 | 196 | 5 | 50 | 27.5 | -4.5 | 5505 |
| 12/14/2006 | 2006 | 12 | 14 | 197 | 20 | 52 | 36 | 4 | 5509 |
| 12/15/2006 | 2006 | 12 | 15 | 198 | 21 | 56 | 38.5 | 6.5 | 5515.5 |
| 12/16/2006 | 2006 | 12 | 16 | 199 | 19 | 58 | 38.5 | 6.5 | 5522 |
| 12/17/2006 | 2006 | 12 | 17 | 200 | 22 | 56 | 39 | 7 | 5529 |
| 12/18/2006 | 2006 | 12 | 18 | 201 | 26 | 54 | 40 | 8 | 5537 |
| 12/19/2006 | 2006 | 12 | 19 | 202 | 27 | 47 | 37 | 5 | 5542 |
| 12/20/2006 | 2006 | 12 | 20 | 203 | 15 | 39 | 27 | -5 | 5537 |
| 12/21/2006 | 2006 | 12 | 21 | 204 | 5 | 39 | 22 | -10 | 5527 |
| 12/22/2006 | 2006 | 12 | 22 | 205 | -7 | 43 | 18 | -14 | 5513 |
| 12/23/2006 | 2006 | 12 | 23 | 206 | -1 | 42 | 20.5 | -11.5 | 5501.5 |
| 12/24/2006 | 2006 | 12 | 24 | 207 | -2 | 44 | 21 | -11 | 5490.5 |
| 12/25/2006 | 2006 | 12 | 25 | 208 | -2 | 45 | 21.5 | -10.5 | 5480 |
| 12/26/2006 | 2006 | 12 | 26 | 209 | 5 | 45 | 25 | -7 | 5473 |
| 12/27/2006 | 2006 | 12 | 27 | 210 | 10 | 48 | 29 | -3 | 5470 |
| 12/28/2006 | 2006 | 12 | 28 | 211 | 17 | 53 | 35 | 3 | 5473 |
| 12/29/2006 | 2006 | 12 | 29 | 212 | 10 | 40 | 25 | -7 | 5466 |
| 12/30/2006 | 2006 | 12 | 30 | 213 | 20 | 40 | 30 | -2 | 5464 |
| 12/31/2006 | 2006 | 12 | 31 | 214 | -6 | 38 | 16 | -16 | 5448 |
| 1/1/2007 | 2007 | 1 | 1 | 215 | 0 | 38 | 19 | -13 | 5435 |
| 1/2/2007 | 2007 | 1 | 2 | 216 | 6 | 32 | 19 | -13 | 5422 |
| 1/3/2007 | 2007 | 1 | 3 | 217 | -3 | 40 | 18.5 | -13.5 | 5408.5 |
| 1/4/2007 | 2007 | 1 | 4 | 218 | 5 | 44 | 24.5 | -7.5 | 5401 |
| 1/5/2007 | 2007 | 1 | 5 | 219 | 22 | 56 | 39 | 7 | 5408 |
| 1/6/2007 | 2007 | 1 | 6 | 220 | 6 | 47 | 26.5 | -5.5 | 5402.5 |
| 1/7/2007 | 2007 | 1 | 7 | 221 | 9 | 41 | 25 | -7 | 5395.5 |
| 1/8/2007 | 2007 | 1 | 8 | 222 | 7 | 36 | 21.5 | -10.5 | 5385 |
| 1/9/2007 | 2007 | 1 | 9 | 223 | 5 | 47 | 26 | -6 | 5379 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/10/2007 | 2007 | 1 | 10 | 224 | 6 | 45 | 25.5 | -6.5 | 5372.5 |
| 1/11/2007 | 2007 | 1 | 11 | 225 | 26 | 45 | 35.5 | 3.5 | 5376 |
| 1/12/2007 | 2007 | 1 | 12 | 226 | 34 | 47 | 40.5 | 8.5 | 5384.5 |
| 1/13/2007 | 2007 | 1 | 13 | 227 | 28 | 52 | 40 | 8 | 5392.5 |
| 1/14/2007 | 2007 | 1 | 14 | 228 | 13 | 45 | 29 | -3 | 5389.5 |
| 1/15/2007 | 2007 | 1 | 15 | 229 | 1 | 31 | 16 | -16 | 5373.5 |
| 1/16/2007 | 2007 | 1 | 16 | 230 | -1 | 32 | 15.5 | -16.5 | 5357 |
| 1/17/2007 | 2007 | 1 | 17 | 231 | 8 | 31 | 19.5 | -12.5 | 5344.5 |
| 1/18/2007 | 2007 | 1 | 18 | 232 | 13 | 42 | 27.5 | -4.5 | 5340 |
| 1/19/2007 | 2007 | 1 | 19 | 233 | 16 | 40 | 28 | -4 | 5336 |
| 1/20/2007 | 2007 | 1 | 20 | 234 | 26 | 39 | 32.5 | 0.5 | 5336.5 |
| 1/21/2007 | 2007 | 1 | 21 | 235 | 23 | 42 | 32.5 | 0.5 | 5337 |
| 1/22/2007 | 2007 | 1 | 22 | 236 | 8 | 32 | 20 | -12 | 5325 |
| 1/23/2007 | 2007 | 1 | 23 | 237 | | 45 | 45 | 13 | 5338 |
| 1/24/2007 | 2007 | 1 | 24 | 238 | 3 | 47 | 25 | -7 | 5331 |
| 1/25/2007 | 2007 | 1 | 25 | 239 | 8 | 52 | 30 | -2 | 5329 |
| 1/26/2007 | 2007 | 1 | 26 | 240 | 10 | 53 | 31.5 | -0.5 | 5328.5 |
| 1/27/2007 | 2007 | 1 | 27 | 241 | 13 | 54 | 33.5 | 1.5 | 5330 |
| 1/28/2007 | 2007 | 1 | 28 | 242 | 13 | 51 | 32 | 0 | 5330 |
| 1/29/2007 | 2007 | 1 | 29 | 243 | 15 | 54 | 34.5 | 2.5 | 5332.5 |
| 1/30/2007 | 2007 | 1 | 30 | 244 | 17 | 50 | 33.5 | 1.5 | 5334 |
| 1/31/2007 | 2007 | 1 | 31 | 245 | 20 | 41 | 30.5 | -1.5 | 5332.5 |
| 2/1/2007 | 2007 | 2 | 1 | 246 | 15 | 44 | 29.5 | -2.5 | 5330 |
| 2/2/2007 | 2007 | 2 | 2 | 247 | 4 | 38 | 21 | -11 | 5319 |
| 2/3/2007 | 2007 | 2 | 3 | 248 | 7 | 33 | 20 | -12 | 5307 |
| 2/4/2007 | 2007 | 2 | 4 | 249 | 10 | 33 | 21.5 | -10.5 | 5296.5 |
| 2/5/2007 | 2007 | 2 | 5 | 250 | 19 | 56 | 37.5 | 5.5 | 5302 |
| 2/6/2007 | 2007 | 2 | 6 | 251 | 29 | 60 | 44.5 | 12.5 | 5314.5 |
| 2/7/2007 | 2007 | 2 | 7 | 252 | 24 | 61 | 42.5 | 10.5 | 5325 |
| 2/8/2007 | 2007 | 2 | 8 | 253 | 27 | 62 | 44.5 | 12.5 | 5337.5 |
| 2/9/2007 | 2007 | 2 | 9 | 254 | 32 | 60 | 46 | 14 | 5351.5 |
| 2/10/2007 | 2007 | 2 | 10 | 255 | 30 | 61 | 45.5 | 13.5 | 5365 |
| 2/11/2007 | 2007 | 2 | 11 | 256 | 26 | 55 | 40.5 | 8.5 | 5373.5 |
| 2/12/2007 | 2007 | 2 | 12 | 257 | 29 | 56 | 42.5 | 10.5 | 5384 |
| 2/13/2007 | 2007 | 2 | 13 | 258 | 27 | 41 | 34 | 2 | 5386 |
| 2/14/2007 | 2007 | 2 | 14 | 259 | 28 | 44 | 36 | 4 | 5390 |
| 2/15/2007 | 2007 | 2 | 15 | 260 | 20 | 43 | 31.5 | -0.5 | 5389.5 |
| 2/16/2007 | 2007 | 2 | 16 | 261 | 21 | 47 | 34 | 2 | 5391.5 |
| 2/17/2007 | 2007 | 2 | 17 | 262 | 27 | 56 | 41.5 | 9.5 | 5401 |
| 2/18/2007 | 2007 | 2 | 18 | 263 | 20 | 54 | 37 | 5 | 5406 |
| 2/19/2007 | 2007 | 2 | 19 | 264 | 28 | 56 | 42 | 10 | 5416 |
| 2/20/2007 | 2007 | 2 | 20 | 265 | 20 | 56 | 38 | 6 | 5422 |
| 2/21/2007 | 2007 | 2 | 21 | 266 | 23 | 56 | 39.5 | 7.5 | 5429.5 |
| 2/22/2007 | 2007 | 2 | 22 | 267 | 22 | 62 | 42 | 10 | 5439.5 |
| 2/23/2007 | 2007 | 2 | 23 | 268 | 22 | 60 | 41 | 9 | 5448.5 |
| 2/24/2007 | 2007 | 2 | 24 | 269 | 22 | 60 | 41 | 9 | 5457.5 |
| 2/25/2007 | 2007 | 2 | 25 | 270 | 34 | 60 | 47 | 15 | 5472.5 |
| 2/26/2007 | 2007 | 2 | 26 | 271 | 25 | 47 | 36 | 4 | 5476.5 |
| 2/27/2007 | 2007 | 2 | 27 | 272 | 28 | 62 | 45 | 13 | 5489.5 |
| 2/28/2007 | 2007 | 2 | 28 | 273 | 32 | 60 | 46 | 14 | 5503.5 |
| 3/1/2007 | 2007 | 3 | 1 | 274 | 18 | 44 | 31 | -1 | 5502.5 |
| 3/2/2007 | 2007 | 3 | 2 | 275 | 10 | 45 | 27.5 | -4.5 | 5498 |
| 3/3/2007 | 2007 | 3 | 3 | 276 | 10 | 48 | 29 | -3 | 5495 |
| 3/4/2007 | 2007 | 3 | 4 | 277 | 9 | 44 | 26.5 | -5.5 | 5489.5 |
| 3/5/2007 | 2007 | 3 | 5 | 278 | 13 | 55 | 34 | 2 | 5491.5 |
| 3/6/2007 | 2007 | 3 | 6 | 279 | 14 | 59 | 36.5 | 4.5 | 5496 |
| 3/7/2007 | 2007 | 3 | 7 | 280 | 30 | 76 | 53 | 21 | 5517 |
| 3/8/2007 | 2007 | 3 | 8 | 281 | 33 | 67 | 50 | 18 | 5535 |
| 3/9/2007 | 2007 | 3 | 9 | 282 | 23 | 70 | 46.5 | 14.5 | 5549.5 |
| 3/10/2007 | 2007 | 3 | 10 | 283 | 29 | 72 | 50.5 | 18.5 | 5568 |
| 3/11/2007 | 2007 | 3 | 11 | 284 | 28 | 64 | 46 | 14 | 5582 |
| 3/12/2007 | 2007 | 3 | 12 | 285 | 22 | 65 | 43.5 | 11.5 | 5593.5 |
| 3/13/2007 | 2007 | 3 | 13 | 286 | 27 | 78 | 52.5 | 20.5 | 5614 |
| 3/14/2007 | 2007 | 3 | 14 | 287 | 30 | 79 | 54.5 | 22.5 | 5636.5 |
| 3/15/2007 | 2007 | 3 | 15 | 288 | 33 | 80 | 56.5 | 24.5 | 5661 |
| 3/16/2007 | 2007 | 3 | 16 | 289 | 26 | 79 | 52.5 | 20.5 | 5681.5 |
| 3/17/2007 | 2007 | 3 | 17 | 290 | 27 | 81 | 54 | 22 | 5703.5 |
| 3/18/2007 | 2007 | 3 | 18 | 291 | 31 | 83 | 57 | 25 | 5728.5 |
| 3/19/2007 | 2007 | 3 | 19 | 292 | 32 | 79 | 55.5 | 23.5 | 5752 |
| 3/20/2007 | 2007 | 3 | 20 | 293 | 26 | 71 | 48.5 | 16.5 | 5768.5 |
| 3/21/2007 | 2007 | 3 | 21 | 294 | 35 | 74 | 54.5 | 22.5 | 5791 |
| 3/22/2007 | 2007 | 3 | 22 | 295 | 40 | 67 | 53.5 | 21.5 | 5812.5 |
| 3/23/2007 | 2007 | 3 | 23 | 296 | 42 | 62 | 52 | 20 | 5832.5 |
| 3/24/2007 | 2007 | 3 | 24 | 297 | 36 | 60 | 48 | 16 | 5848.5 |
| 3/25/2007 | 2007 | 3 | 25 | 298 | 36 | 60 | 48 | 16 | 5864.5 |
| 3/26/2007 | 2007 | 3 | 26 | 299 | 36 | 60 | 48 | 16 | 5880.5 |
| 3/27/2007 | 2007 | 3 | 27 | 300 | 30 | 71 | 50.5 | 18.5 | 5899 |
| 3/28/2007 | 2007 | 3 | 28 | 301 | 28 | 73 | 50.5 | 18.5 | 5917.5 |
| 3/29/2007 | 2007 | 3 | 29 | 302 | 22 | 73 | 47.5 | 15.5 | 5933 |
| 3/30/2007 | 2007 | 3 | 30 | 303 | 29 | 54 | 41.5 | 9.5 | 5942.5 |
| 3/31/2007 | 2007 | 3 | 31 | 304 | 24 | 46 | 35 | 3 | 5945.5 |
| 4/1/2007 | 2007 | 4 | 1 | 305 | 25 | 70 | 47.5 | 15.5 | 5961 |
| 4/2/2007 | 2007 | 4 | 2 | 306 | 29 | 75 | 52 | 20 | 5981 |
| 4/3/2007 | 2007 | 4 | 3 | 307 | 37 | 75 | 56 | 24 | 6005 |
| 4/4/2007 | 2007 | 4 | 4 | 308 | 34 | 77 | 55.5 | 23.5 | 6028.5 |
| 4/5/2007 | 2007 | 4 | 5 | 309 | 34 | 79 | 56.5 | 24.5 | 6053 |
| 4/6/2007 | 2007 | 4 | 6 | 310 | 37 | 80 | 58.5 | 26.5 | 6079.5 |
| 4/7/2007 | 2007 | 4 | 7 | 311 | 38 | 74 | 56 | 24 | 6103.5 |
| 4/8/2007 | 2007 | 4 | 8 | 312 | 38 | 71 | 54.5 | 22.5 | 6126 |
| 4/9/2007 | 2007 | 4 | 9 | 313 | 37 | 62 | 49.5 | 17.5 | 6143.5 |
| 4/10/2007 | 2007 | 4 | 10 | 314 | 53 | 64 | 58.5 | 26.5 | 6170 |
| 4/11/2007 | 2007 | 4 | 11 | 315 | 25 | 64 | 44.5 | 12.5 | 6182.5 |
| 4/12/2007 | 2007 | 4 | 12 | 316 | 25 | 61 | 43 | 11 | 6193.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/13/2007 | 2007 | 4 | 13 | 317 | 36 | 60 | 48 | 16 | 6209.5 |
| 4/14/2007 | 2007 | 4 | 14 | 318 | 29 | 59 | 44 | 12 | 6221.5 |
| 4/15/2007 | 2007 | 4 | 15 | 319 | 30 | 65 | 47.5 | 15.5 | 6237 |
| 4/16/2007 | 2007 | 4 | 16 | 320 | 28 | 70 | 49 | 17 | 6254 |
| 4/17/2007 | 2007 | 4 | 17 | 321 | 30 | 64 | 47 | 15 | 6269 |
| 4/18/2007 | 2007 | 4 | 18 | 322 | 32 | 73 | 52.5 | 20.5 | 6289.5 |
| 4/19/2007 | 2007 | 4 | 19 | 323 | 33 | 73 | 53 | 21 | 6310.5 |
| 4/20/2007 | 2007 | 4 | 20 | 324 | 34 | 71 | 52.5 | 20.5 | 6331 |
| 4/21/2007 | 2007 | 4 | 21 | 325 | 32 | 72 | 52 | 20 | 6351 |
| 4/22/2007 | 2007 | 4 | 22 | 326 | 28 | 60 | 44 | 12 | 6363 |
| 4/23/2007 | 2007 | 4 | 23 | 327 | 34 | 70 | 52 | 20 | 6383 |
| 4/24/2007 | 2007 | 4 | 24 | 328 | 36 | 68 | 52 | 20 | 6403 |
| 4/25/2007 | 2007 | 4 | 25 | 329 | 31 | 63 | 47 | 15 | 6418 |
| 4/26/2007 | 2007 | 4 | 26 | 330 | 32 | 66 | 49 | 17 | 6435 |
| 4/27/2007 | 2007 | 4 | 27 | 331 | 33 | 79 | 56 | 24 | 6459 |
| 4/28/2007 | 2007 | 4 | 28 | 332 | 36 | 81 | 58.5 | 26.5 | 6485.5 |
| 4/29/2007 | 2007 | 4 | 29 | 333 | 45 | 77 | 61 | 29 | 6514.5 |
| 4/30/2007 | 2007 | 4 | 30 | 334 | 41 | 74 | 57.5 | 25.5 | 6540 |
| 5/1/2007 | 2007 | 5 | 1 | 335 | 41 | 85 | 63 | 31 | 6571 |
| 5/2/2007 | 2007 | 5 | 2 | 336 | 46 | 79 | 62.5 | 30.5 | 6601.5 |
| 5/3/2007 | 2007 | 5 | 3 | 337 | 56 | 78 | 67 | 35 | 6636.5 |
| 5/4/2007 | 2007 | 5 | 4 | 338 | 59 | 76 | 67.5 | 35.5 | 6672 |
| 5/5/2007 | 2007 | 5 | 5 | 339 | 37 | 72 | 54.5 | 22.5 | 6694.5 |
| 5/6/2007 | 2007 | 5 | 6 | 340 | 27 | 56 | 41.5 | 9.5 | 6704 |
| 5/7/2007 | 2007 | 5 | 7 | 341 | 29 | 60 | 44.5 | 12.5 | 6716.5 |
| 5/8/2007 | 2007 | 5 | 8 | 342 | 37 | 66 | 51.5 | 19.5 | 6736 |
| 5/9/2007 | 2007 | 5 | 9 | 343 | 38 | 70 | 54 | 22 | 6758 |
| 5/10/2007 | 2007 | 5 | 10 | 344 | 34 | 78 | 56 | 24 | 6782 |
| 5/11/2007 | 2007 | 5 | 11 | 345 | 38 | 85 | 61.5 | 29.5 | 6811.5 |
| 5/12/2007 | 2007 | 5 | 12 | 346 | 44 | 85 | 64.5 | 32.5 | 6844 |
| 5/13/2007 | 2007 | 5 | 13 | 347 | 46 | 85 | 65.5 | 33.5 | 6877.5 |
| 5/14/2007 | 2007 | 5 | 14 | 348 | 46 | 83 | 64.5 | 32.5 | 6910 |
| 5/15/2007 | 2007 | 5 | 15 | 349 | 47 | 81 | 64 | 32 | 6942 |
| 5/16/2007 | 2007 | 5 | 16 | 350 | 46 | 74 | 60 | 28 | 6970 |
| 5/17/2007 | 2007 | 5 | 17 | 351 | 46 | 74 | 60 | 28 | 6998 |
| 5/18/2007 | 2007 | 5 | 18 | 352 | 43 | 74 | 58.5 | 26.5 | 7024.5 |
| 5/19/2007 | 2007 | 5 | 19 | 353 | 43 | 79 | 61 | 29 | 7053.5 |
| 5/20/2007 | 2007 | 5 | 20 | 354 | 46 | 80 | 63 | 31 | 7084.5 |
| 5/21/2007 | 2007 | 5 | 21 | 355 | 45 | 75 | 60 | 28 | 7112.5 |
| 5/22/2007 | 2007 | 5 | 22 | 356 | 52 | 79 | 65.5 | 33.5 | 7146 |
| 5/23/2007 | 2007 | 5 | 23 | 357 | 42 | 76 | 59 | 27 | 7173 |
| 5/24/2007 | 2007 | 5 | 24 | 358 | 28 | 73 | 50.5 | 18.5 | 7191.5 |
| 5/25/2007 | 2007 | 5 | 25 | 359 | 47 | 73 | 60 | 28 | 7219.5 |
| 5/26/2007 | 2007 | 5 | 26 | 360 | 45 | 82 | 63.5 | 31.5 | 7251 |
| 5/27/2007 | 2007 | 5 | 27 | 361 | 41 | 84 | 62.5 | 30.5 | 7281.5 |
| 5/28/2007 | 2007 | 5 | 28 | 362 | 54 | 84 | 69 | 37 | 7318.5 |
| 5/29/2007 | 2007 | 5 | 29 | 363 | 40 | 84 | 62 | 30 | 7348.5 |
| 5/30/2007 | 2007 | 5 | 30 | 364 | 40 | 85 | 62.5 | 30.5 | 7379 |
| 5/31/2007 | 2007 | 5 | 31 | 365 | 39 | 86 | 62.5 | 30.5 | 7409.5 |
| 6/1/2007 | 2007 | 6 | 1 | 1 | 39 | 85 | 62 | 30 | 30 |
| 6/2/2007 | 2007 | 6 | 2 | 2 | 40 | 91 | 65.5 | 33.5 | 63.5 |
| 6/3/2007 | 2007 | 6 | 3 | 3 | 63 | 91 | 77 | 45 | 108.5 |
| 6/4/2007 | 2007 | 6 | 4 | 4 | 47 | 84 | 65.5 | 33.5 | 142 |
| 6/5/2007 | 2007 | 6 | 5 | 5 | 53 | 89 | 71 | 39 | 181 |
| 6/6/2007 | 2007 | 6 | 6 | 6 | 55 | 90 | 72.5 | 40.5 | 221.5 |
| 6/7/2007 | 2007 | 6 | 7 | 7 | 55 | 83 | 69 | 37 | 258.5 |
| 6/8/2007 | 2007 | 6 | 8 | 8 | 32 | 81 | 56.5 | 24.5 | 283 |
| 6/9/2007 | 2007 | 6 | 9 | 9 | 47 | 84 | 65.5 | 33.5 | 316.5 |
| 6/10/2007 | 2007 | 6 | 10 | 10 | 43 | 70 | 56.5 | 24.5 | 341 |
| 6/11/2007 | 2007 | 6 | 11 | 11 | 48 | 66 | 57 | 25 | 366 |
| 6/12/2007 | 2007 | 6 | 12 | 12 | 47 | 75 | 61 | 29 | 395 |
| 6/13/2007 | 2007 | 6 | 13 | 13 | 42 | 82 | 62 | 30 | 425 |
| 6/14/2007 | 2007 | 6 | 14 | 14 | 46 | 86 | 66 | 34 | 459 |
| 6/15/2007 | 2007 | 6 | 15 | 15 | 47 | 91 | 69 | 37 | 496 |
| 6/16/2007 | 2007 | 6 | 16 | 16 | 58 | 96 | 77 | 45 | 541 |
| 6/17/2007 | 2007 | 6 | 17 | 17 | 60 | 93 | 76.5 | 44.5 | 585.5 |
| 6/18/2007 | 2007 | 6 | 18 | 18 | 57 | 94 | 75.5 | 43.5 | 629 |
| 6/19/2007 | 2007 | 6 | 19 | 19 | 51 | 96 | 73.5 | 41.5 | 670.5 |
| 6/20/2007 | 2007 | 6 | 20 | 20 | 50 | 95 | 72.5 | 40.5 | 711 |
| 6/21/2007 | 2007 | 6 | 21 | 21 | 57 | 97 | 77 | 45 | 756 |
| 6/22/2007 | 2007 | 6 | 22 | 22 | 58 | 96 | 77 | 45 | 801 |
| 6/23/2007 | 2007 | 6 | 23 | 23 | 56 | 93 | 74.5 | 42.5 | 843.5 |
| 6/24/2007 | 2007 | 6 | 24 | 24 | 51 | 99 | 75 | 43 | 886.5 |
| 6/25/2007 | 2007 | 6 | 25 | 25 | 49 | 100 | 74.5 | 42.5 | 929 |
| 6/26/2007 | 2007 | 6 | 26 | 26 | 45 | 97 | 71 | 39 | 968 |
| 6/27/2007 | 2007 | 6 | 27 | 27 | 42 | 100 | 71 | 39 | 1007 |
| 6/28/2007 | 2007 | 6 | 28 | 28 | 55 | 86 | 70.5 | 38.5 | 1045.5 |
| 6/29/2007 | 2007 | 6 | 29 | 29 | 55 | 97 | 76 | 44 | 1089.5 |
| 6/30/2007 | 2007 | 6 | 30 | 30 | 53 | 98 | 75.5 | 43.5 | 1133 |
| 7/1/2007 | 2007 | 7 | 1 | 31 | 50 | 101 | 75.5 | 43.5 | 1176.5 |
| 7/2/2007 | 2007 | 7 | 2 | 32 | 52 | 102 | 77 | 45 | 1221.5 |
| 7/3/2007 | 2007 | 7 | 3 | 33 | 55 | 102 | 78.5 | 46.5 | 1268 |
| 7/4/2007 | 2007 | 7 | 4 | 34 | 65 | 103 | 84 | 52 | 1320 |
| 7/5/2007 | 2007 | 7 | 5 | 35 | 56 | 93 | 74.5 | 42.5 | 1362.5 |
| 7/6/2007 | 2007 | 7 | 6 | 36 | 53 | 95 | 74 | 42 | 1404.5 |
| 7/7/2007 | 2007 | 7 | 7 | 37 | 56 | 88 | 72 | 40 | 1444.5 |
| 7/8/2007 | 2007 | 7 | 8 | 38 | 54 | 96 | 75 | 43 | 1487.5 |
| 7/9/2007 | 2007 | 7 | 9 | 39 | 53 | 99 | 76 | 44 | 1531.5 |
| 7/10/2007 | 2007 | 7 | 10 | 40 | 57 | 98 | 77.5 | 45.5 | 1577 |
| 7/11/2007 | 2007 | 7 | 11 | 41 | 65 | 95 | 80 | 48 | 1625 |
| 7/12/2007 | 2007 | 7 | 12 | 42 | 60 | 90 | 75 | 43 | 1668 |
| 7/13/2007 | 2007 | 7 | 13 | 43 | 59 | 95 | 77 | 45 | 1713 |
| 7/14/2007 | 2007 | 7 | 14 | 44 | 54 | 97 | 75.5 | 43.5 | 1756.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/15/2007 | 2007 | 7 | 15 | 45 | 64 | 95 | 79.5 | 47.5 | 1804 |
| 7/16/2007 | 2007 | 7 | 16 | 46 | 60 | 97 | 78.5 | 46.5 | 1850.5 |
| 7/17/2007 | 2007 | 7 | 17 | 47 | 55 | 99 | 77 | 45 | 1895.5 |
| 7/18/2007 | 2007 | 7 | 18 | 48 | 56 | 101 | 78.5 | 46.5 | 1942 |
| 7/19/2007 | 2007 | 7 | 19 | 49 | 58 | 100 | 79 | 47 | 1989 |
| 7/20/2007 | 2007 | 7 | 20 | 50 | 58 | 89 | 73.5 | 41.5 | 2030.5 |
| 7/21/2007 | 2007 | 7 | 21 | 51 | 61 | 90 | 75.5 | 43.5 | 2074 |
| 7/22/2007 | 2007 | 7 | 22 | 52 | 57 | 89 | 73 | 41 | 2115 |
| 7/23/2007 | 2007 | 7 | 23 | 53 | 57 | 82 | 69.5 | 37.5 | 2152.5 |
| 7/24/2007 | 2007 | 7 | 24 | 54 | 58 | 90 | 74 | 42 | 2194.5 |
| 7/25/2007 | 2007 | 7 | 25 | 55 | 53 | 93 | 73 | 41 | 2235.5 |
| 7/26/2007 | 2007 | 7 | 26 | 56 | 60 | 90 | 75 | 43 | 2278.5 |
| 7/27/2007 | 2007 | 7 | 27 | 57 | 60 | 95 | 77.5 | 45.5 | 2324 |
| 7/28/2007 | 2007 | 7 | 28 | 58 | 60 | 87 | 73.5 | 41.5 | 2365.5 |
| 7/29/2007 | 2007 | 7 | 29 | 59 | 58 | 92 | 75 | 43 | 2408.5 |
| 7/30/2007 | 2007 | 7 | 30 | 60 | 59 | 94 | 76.5 | 44.5 | 2453 |
| 7/31/2007 | 2007 | 7 | 31 | 61 | 57 | 79 | 68 | 36 | 2489 |
| 8/1/2007 | 2007 | 8 | 1 | 62 | 59 | 91 | 75 | 43 | 2532 |
| 8/2/2007 | 2007 | 8 | 2 | 63 | 60 | 90 | 75 | 43 | 2575 |
| 8/3/2007 | 2007 | 8 | 3 | 64 | 59 | 89 | 74 | 42 | 2617 |
| 8/4/2007 | 2007 | 8 | 4 | 65 | 58 | 88 | 73 | 41 | 2658 |
| 8/5/2007 | 2007 | 8 | 5 | 66 | 57 | 91 | 74 | 42 | 2700 |
| 8/6/2007 | 2007 | 8 | 6 | 67 | 59 | 89 | 74 | 42 | 2742 |
| 8/7/2007 | 2007 | 8 | 7 | 68 | 57 | 90 | 73.5 | 41.5 | 2783.5 |
| 8/8/2007 | 2007 | 8 | 8 | 69 | 53 | 84 | 68.5 | 36.5 | 2820 |
| 8/9/2007 | 2007 | 8 | 9 | 70 | 54 | 91 | 72.5 | 40.5 | 2860.5 |
| 8/10/2007 | 2007 | 8 | 10 | 71 | 57 | 91 | 74 | 42 | 2902.5 |
| 8/11/2007 | 2007 | 8 | 11 | 72 | 59 | 92 | 75.5 | 43.5 | 2946 |
| 8/12/2007 | 2007 | 8 | 12 | 73 | 55 | 91 | 73 | 41 | 2987 |
| 8/13/2007 | 2007 | 8 | 13 | 74 | 56 | 95 | 75.5 | 43.5 | 3030.5 |
| 8/14/2007 | 2007 | 8 | 14 | 75 | 54 | 96 | 75 | 43 | 3073.5 |
| 8/15/2007 | 2007 | 8 | 15 | 76 | 55 | 96 | 75.5 | 43.5 | 3117 |
| 8/16/2007 | 2007 | 8 | 16 | 77 | 57 | 95 | 76 | 44 | 3161 |
| 8/17/2007 | 2007 | 8 | 17 | 78 | 56 | 95 | 75.5 | 43.5 | 3204.5 |
| 8/18/2007 | 2007 | 8 | 18 | 79 | 57 | 95 | 76 | 44 | 3248.5 |
| 8/19/2007 | 2007 | 8 | 19 | 80 | 57 | 95 | 76 | 44 | 3292.5 |
| 8/20/2007 | 2007 | 8 | 20 | 81 | 67 | 94 | 80.5 | 48.5 | 3341 |
| 8/21/2007 | 2007 | 8 | 21 | 82 | 59 | 95 | 77 | 45 | 3386 |
| 8/22/2007 | 2007 | 8 | 22 | 83 | 52 | 98 | 75 | 43 | 3429 |
| 8/23/2007 | 2007 | 8 | 23 | 84 | 62 | 98 | 80 | 48 | 3477 |
| 8/24/2007 | 2007 | 8 | 24 | 85 | 58 | 95 | 76.5 | 44.5 | 3521.5 |
| 8/25/2007 | 2007 | 8 | 25 | 86 | 53 | 96 | 74.5 | 42.5 | 3564 |
| 8/26/2007 | 2007 | 8 | 26 | 87 | 54 | 92 | 73 | 41 | 3605 |
| 8/27/2007 | 2007 | 8 | 27 | 88 | 53 | 90 | 71.5 | 39.5 | 3644.5 |
| 8/28/2007 | 2007 | 8 | 28 | 89 | 52 | 86 | 69 | 37 | 3681.5 |
| 8/29/2007 | 2007 | 8 | 29 | 90 | 58 | 86 | 72 | 40 | 3721.5 |
| 8/30/2007 | 2007 | 8 | 30 | 91 | 56 | 90 | 73 | 41 | 3762.5 |
| 8/31/2007 | 2007 | 8 | 31 | 92 | 61 | 86 | 73.5 | 41.5 | 3804 |
| 9/1/2007 | 2007 | 9 | 1 | 93 | 53 | 87 | 70 | 38 | 3842 |
| 9/2/2007 | 2007 | 9 | 2 | 94 | 56 | 89 | 72.5 | 40.5 | 3882.5 |
| 9/3/2007 | 2007 | 9 | 3 | 95 | 52 | 85 | 68.5 | 36.5 | 3919 |
| 9/4/2007 | 2007 | 9 | 4 | 96 | 52 | 87 | 69.5 | 37.5 | 3956.5 |
| 9/5/2007 | 2007 | 9 | 5 | 97 | 53 | 88 | 70.5 | 38.5 | 3995 |
| 9/6/2007 | 2007 | 9 | 6 | 98 | 55 | 86 | 70.5 | 38.5 | 4033.5 |
| 9/7/2007 | 2007 | 9 | 7 | 99 | 51 | 80 | 65.5 | 33.5 | 4067 |
| 9/8/2007 | 2007 | 9 | 8 | 100 | 47 | 74 | 60.5 | 28.5 | 4095.5 |
| 9/9/2007 | 2007 | 9 | 9 | 101 | 43 | 68 | 55.5 | 23.5 | 4119 |
| 9/10/2007 | 2007 | 9 | 10 | 102 | 50 | 88 | 69 | 37 | 4156 |
| 9/11/2007 | 2007 | 9 | 11 | 103 | 52 | 87 | 69.5 | 37.5 | 4193.5 |
| 9/12/2007 | 2007 | 9 | 12 | 104 | 49 | 78 | 63.5 | 31.5 | 4225 |
| 9/13/2007 | 2007 | 9 | 13 | 105 | 49 | 78 | 63.5 | 31.5 | 4256.5 |
| 9/14/2007 | 2007 | 9 | 14 | 106 | 42 | 91 | 66.5 | 34.5 | 4291 |
| 9/15/2007 | 2007 | 9 | 15 | 107 | 50 | 88 | 69 | 37 | 4328 |
| 9/16/2007 | 2007 | 9 | 16 | 108 | 50 | 88 | 69 | 37 | 4365 |
| 9/17/2007 | 2007 | 9 | 17 | 109 | 62 | 87 | 74.5 | 42.5 | 4407.5 |
| 9/18/2007 | 2007 | 9 | 18 | 110 | 50 | 88 | 69 | 37 | 4444.5 |
| 9/19/2007 | 2007 | 9 | 19 | 111 | 40 | 82 | 61 | 29 | 4473.5 |
| 9/20/2007 | 2007 | 9 | 20 | 112 | 52 | 80 | 66 | 34 | 4507.5 |
| 9/21/2007 | 2007 | 9 | 21 | 113 | 51 | 73 | 62 | 30 | 4537.5 |
| 9/22/2007 | 2007 | 9 | 22 | 114 | 47 | 77 | 62 | 30 | 4567.5 |
| 9/23/2007 | 2007 | 9 | 23 | 115 | 44 | 78 | 61 | 29 | 4596.5 |
| 9/24/2007 | 2007 | 9 | 24 | 116 | 43 | 80 | 61.5 | 29.5 | 4626 |
| 9/25/2007 | 2007 | 9 | 25 | 117 | 33 | 78 | 55.5 | 23.5 | 4649.5 |
| 9/26/2007 | 2007 | 9 | 26 | 118 | 34 | 83 | 58.5 | 26.5 | 4676 |
| 9/27/2007 | 2007 | 9 | 27 | 119 | 34 | 84 | 59 | 27 | 4703 |
| 9/28/2007 | 2007 | 9 | 28 | 120 | 53 | 82 | 67.5 | 35.5 | 4738.5 |
| 9/29/2007 | 2007 | 9 | 29 | 121 | 56 | 80 | 68 | 36 | 4774.5 |
| 9/30/2007 | 2007 | 9 | 30 | 122 | 39 | 81 | 60 | 28 | 4802.5 |
| 10/1/2007 | 2007 | 10 | 1 | 123 | 42 | 84 | 63 | 31 | 4833.5 |
| 10/2/2007 | 2007 | 10 | 2 | 124 | 47 | 74 | 60.5 | 28.5 | 4862 |
| 10/3/2007 | 2007 | 10 | 3 | 125 | 34 | 80 | 57 | 25 | 4887 |
| 10/4/2007 | 2007 | 10 | 4 | 126 | 43 | 86 | 64.5 | 32.5 | 4919.5 |
| 10/5/2007 | 2007 | 10 | 5 | 127 | 47 | 80 | 63.5 | 31.5 | 4951 |
| 10/6/2007 | 2007 | 10 | 6 | 128 | 48 | 80 | 64 | 32 | 4983 |
| 10/7/2007 | 2007 | 10 | 7 | 129 | 28 | 76 | 52 | 20 | 5003 |
| 10/8/2007 | 2007 | 10 | 8 | 130 | 24 | 66 | 45 | 13 | 5016 |
| 10/9/2007 | 2007 | 10 | 9 | 131 | 32 | 72 | 52 | 20 | 5036 |
| 10/10/2007 | 2007 | 10 | 10 | 132 | 42 | 76 | 59 | 27 | 5063 |
| 10/11/2007 | 2007 | 10 | 11 | 133 | 35 | 78 | 56.5 | 24.5 | 5087.5 |
| 10/12/2007 | 2007 | 10 | 12 | 134 | 32 | 86 | 59 | 27 | 5114.5 |
| 10/13/2007 | 2007 | 10 | 13 | 135 | 31 | 84 | 57.5 | 25.5 | 5140 |
| 10/14/2007 | 2007 | 10 | 14 | 136 | 29 | 72 | 50.5 | 18.5 | 5158.5 |
| 10/15/2007 | 2007 | 10 | 15 | 137 | 25 | 69 | 47 | 15 | 5173.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/16/2007 | 2007 | 10 | 16 | 138 | 25 | 72 | 48.5 | 16.5 | 5190 |
| 10/17/2007 | 2007 | 10 | 17 | 139 | 29 | 70 | 49.5 | 17.5 | 5207.5 |
| 10/18/2007 | 2007 | 10 | 18 | 140 | 28 | 66 | 47 | 15 | 5222.5 |
| 10/19/2007 | 2007 | 10 | 19 | 141 | 26 | 65 | 45.5 | 13.5 | 5236 |
| 10/20/2007 | 2007 | 10 | 20 | 142 | 26 | 81 | 53.5 | 21.5 | 5257.5 |
| 10/21/2007 | 2007 | 10 | 21 | 143 | 33 | 80 | 56.5 | 24.5 | 5282 |
| 10/22/2007 | 2007 | 10 | 22 | 144 | 19 | 53 | 36 | 4 | 5286 |
| 10/23/2007 | 2007 | 10 | 23 | 145 | 21 | 60 | 40.5 | 8.5 | 5294.5 |
| 10/24/2007 | 2007 | 10 | 24 | 146 | 26 | 76 | 51 | 19 | 5313.5 |
| 10/25/2007 | 2007 | 10 | 25 | 147 | 26 | 78 | 52 | 20 | 5333.5 |
| 10/26/2007 | 2007 | 10 | 26 | 148 | 23 | 80 | 51.5 | 19.5 | 5353 |
| 10/27/2007 | 2007 | 10 | 27 | 149 | 25 | 83 | 54 | 22 | 5375 |
| 10/28/2007 | 2007 | 10 | 28 | 150 | 29 | 84 | 56.5 | 24.5 | 5399.5 |
| 10/29/2007 | 2007 | 10 | 29 | 151 | 28 | 78 | 53 | 21 | 5420.5 |
| 10/30/2007 | 2007 | 10 | 30 | 152 | 36 | 75 | 55.5 | 23.5 | 5444 |
| 10/31/2007 | 2007 | 10 | 31 | 153 | 29 | 75 | 52 | 20 | 5464 |
| 11/1/2007 | 2007 | 11 | 1 | 154 | 26 | 70 | 48 | 16 | 5480 |
| 11/2/2007 | 2007 | 11 | 2 | 155 | 31 | 67 | 49 | 17 | 5497 |
| 11/3/2007 | 2007 | 11 | 3 | 156 | 26 | 70 | 48 | 16 | 5513 |
| 11/4/2007 | 2007 | 11 | 4 | 157 | 27 | 71 | 49 | 17 | 5530 |
| 11/5/2007 | 2007 | 11 | 5 | 158 | 27 | 77 | 52 | 20 | 5550 |
| 11/6/2007 | 2007 | 11 | 6 | 159 | 34 | 77 | 55.5 | 23.5 | 5573.5 |
| 11/7/2007 | 2007 | 11 | 7 | 160 | 26 | 67 | 46.5 | 14.5 | 5588 |
| 11/8/2007 | 2007 | 11 | 8 | 161 | 27 | 76 | 51.5 | 19.5 | 5607.5 |
| 11/9/2007 | 2007 | 11 | 9 | 162 | 26 | 78 | 52 | 20 | 5627.5 |
| 11/10/2007 | 2007 | 11 | 10 | 163 | 26 | 75 | 50.5 | 18.5 | 5646 |
| 11/11/2007 | 2007 | 11 | 11 | 164 | 26 | 75 | 50.5 | 18.5 | 5664.5 |
| 11/12/2007 | 2007 | 11 | 12 | 165 | 26 | 73 | 49.5 | 17.5 | 5682 |
| 11/13/2007 | 2007 | 11 | 13 | 166 | 25 | 68 | 46.5 | 14.5 | 5696.5 |
| 11/14/2007 | 2007 | 11 | 14 | 167 | 26 | 75 | 50.5 | 18.5 | 5715 |
| 11/15/2007 | 2007 | 11 | 15 | 168 | 34 | 73 | 53.5 | 21.5 | 5736.5 |
| 11/16/2007 | 2007 | 11 | 16 | 169 | 34 | 71 | 52.5 | 20.5 | 5757 |
| 11/17/2007 | 2007 | 11 | 17 | 170 | 24 | 64 | 44 | 12 | 5769 |
| 11/18/2007 | 2007 | 11 | 18 | 171 | 22 | 70 | 46 | 14 | 5783 |
| 11/19/2007 | 2007 | 11 | 19 | 172 | 21 | 70 | 45.5 | 13.5 | 5796.5 |
| 11/20/2007 | 2007 | 11 | 20 | 173 | 21 | 79 | 50 | 18 | 5814.5 |
| 11/21/2007 | 2007 | 11 | 21 | 174 | 32 | 71 | 51.5 | 19.5 | 5834 |
| 11/22/2007 | 2007 | 11 | 22 | 175 | 21 | 54 | 37.5 | 5.5 | 5839.5 |
| 11/23/2007 | 2007 | 11 | 23 | 176 | 31 | 48 | 39.5 | 7.5 | 5847 |
| 11/24/2007 | 2007 | 11 | 24 | 177 | 21 | 41 | 31 | -1 | 5846 |
| 11/25/2007 | 2007 | 11 | 25 | 178 | 8 | 42 | 25 | -7 | 5839 |
| 11/26/2007 | 2007 | 11 | 26 | 179 | 10 | 48 | 29 | -3 | 5836 |
| 11/27/2007 | 2007 | 11 | 27 | 180 | 9 | 54 | 31.5 | -0.5 | 5835.5 |
| 11/28/2007 | 2007 | 11 | 28 | 181 | 27 | 55 | 41 | 9 | 5844.5 |
| 11/29/2007 | 2007 | 11 | 29 | 182 | 14 | 57 | 35.5 | 3.5 | 5848 |
| 11/30/2007 | 2007 | 11 | 30 | 183 | 36 | 52 | 44 | 12 | 5860 |
| 12/1/2007 | 2007 | 12 | 1 | 184 | 41 | 55 | 48 | 16 | 5876 |
| 12/2/2007 | 2007 | 12 | 2 | 185 | 28 | 54 | 41 | 9 | 5885 |
| 12/3/2007 | 2007 | 12 | 3 | 186 | 20 | 57 | 38.5 | 6.5 | 5891.5 |
| 12/4/2007 | 2007 | 12 | 4 | 187 | 21 | 60 | 40.5 | 8.5 | 5900 |
| 12/5/2007 | 2007 | 12 | 5 | 188 | 24 | 67 | 45.5 | 13.5 | 5913.5 |
| 12/6/2007 | 2007 | 12 | 6 | 189 | 32 | 62 | 47 | 15 | 5928.5 |
| 12/7/2007 | 2007 | 12 | 7 | 190 | 37 | 60 | 48.5 | 16.5 | 5945 |
| 12/8/2007 | 2007 | 12 | 8 | 191 | 39 | 60 | 49.5 | 17.5 | 5962.5 |
| 12/9/2007 | 2007 | 12 | 9 | 192 | 20 | 49 | 34.5 | 2.5 | 5965 |
| 12/10/2007 | 2007 | 12 | 10 | 193 | 25 | 49 | 37 | 5 | 5970 |
| 12/11/2007 | 2007 | 12 | 11 | 194 | 30 | 40 | 35 | 3 | 5973 |
| 12/12/2007 | 2007 | 12 | 12 | 195 | 18 | 43 | 30.5 | -1.5 | 5971.5 |
| 12/13/2007 | 2007 | 12 | 13 | 196 | 15 | 45 | 30 | -2 | 5969.5 |
| 12/14/2007 | 2007 | 12 | 14 | 197 | 24 | 42 | 33 | 1 | 5970.5 |
| 12/15/2007 | 2007 | 12 | 15 | 198 | 8 | 39 | 23.5 | -8.5 | 5962 |
| 12/16/2007 | 2007 | 12 | 16 | 199 | 8 | 45 | 26.5 | -5.5 | 5956.5 |
| 12/17/2007 | 2007 | 12 | 17 | 200 | 13 | 47 | 30 | -2 | 5954.5 |
| 12/18/2007 | 2007 | 12 | 18 | 201 | 15 | 47 | 31 | -1 | 5953.5 |
| 12/19/2007 | 2007 | 12 | 19 | 202 | 15 | 56 | 35.5 | 3.5 | 5957 |
| 12/20/2007 | 2007 | 12 | 20 | 203 | 15 | 53 | 34 | 2 | 5959 |
| 12/21/2007 | 2007 | 12 | 21 | 204 | 15 | 53 | 34 | 2 | 5961 |
| 12/22/2007 | 2007 | 12 | 22 | 205 | 13 | 60 | 36.5 | 4.5 | 5965.5 |
| 12/23/2007 | 2007 | 12 | 23 | 206 | 10 | 48 | 29 | -3 | 5962.5 |
| 12/24/2007 | 2007 | 12 | 24 | 207 | 18 | 51 | 34.5 | 2.5 | 5965 |
| 12/25/2007 | 2007 | 12 | 25 | 208 | 17 | 53 | 35 | 3 | 5968 |
| 12/26/2007 | 2007 | 12 | 26 | 209 | 1 | 33 | 17 | -15 | 5953 |
| 12/27/2007 | 2007 | 12 | 27 | 210 | 9 | 43 | 26 | -6 | 5947 |
| 12/28/2007 | 2007 | 12 | 28 | 211 | 0 | 31 | 15.5 | -16.5 | 5930.5 |
| 12/29/2007 | 2007 | 12 | 29 | 212 | 12 | 36 | 24 | -8 | 5922.5 |
| 12/30/2007 | 2007 | 12 | 30 | 213 | 15 | 46 | 30.5 | -1.5 | 5921 |
| 12/31/2007 | 2007 | 12 | 31 | 214 | 20 | 52 | 36 | 4 | 5925 |
| 1/1/2008 | 2008 | 1 | 1 | 215 | -2 | 36 | 17 | -15 | 5910 |
| 1/2/2008 | 2008 | 1 | 2 | 216 | 7 | 44 | 25.5 | -6.5 | 5903.5 |
| 1/3/2008 | 2008 | 1 | 3 | 217 | 10 | 39 | 24.5 | -7.5 | 5896 |
| 1/4/2008 | 2008 | 1 | 4 | 218 | 28 | 51 | 39.5 | 7.5 | 5903.5 |
| 1/5/2008 | 2008 | 1 | 5 | 219 | 28 | 58 | 43 | 11 | 5914.5 |
| 1/6/2008 | 2008 | 1 | 6 | 220 | 40 | 57 | 48.5 | 16.5 | 5931 |
| 1/7/2008 | 2008 | 1 | 7 | 221 | 32 | 55 | 43.5 | 11.5 | 5942.5 |
| 1/8/2008 | 2008 | 1 | 8 | 222 | 11 | 40 | 25.5 | -6.5 | 5936 |
| 1/9/2008 | 2008 | 1 | 9 | 223 | 13 | 44 | 28.5 | -3.5 | 5932.5 |
| 1/10/2008 | 2008 | 1 | 10 | 224 | 11 | 43 | 27 | -5 | 5927.5 |
| 1/11/2008 | 2008 | 1 | 11 | 225 | 14 | 45 | 29.5 | -2.5 | 5925 |
| 1/12/2008 | 2008 | 1 | 12 | 226 | 13 | 43 | 28 | -4 | 5921 |
| 1/13/2008 | 2008 | 1 | 13 | 227 | 15 | 45 | 30 | -2 | 5919 |
| 1/14/2008 | 2008 | 1 | 14 | 228 | 10 | 44 | 27 | -5 | 5914 |
| 1/15/2008 | 2008 | 1 | 15 | 229 | 6 | 28 | 17 | -15 | 5899 |
| 1/16/2008 | 2008 | 1 | 16 | 230 | 13 | 32 | 22.5 | -9.5 | 5889.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/17/2008 | 2008 | 1 | 17 | 231 | -2 | 31 | 14.5 | -17.5 | 5872 |
| 1/18/2008 | 2008 | 1 | 18 | 232 | 3 | 33 | 18 | -14 | 5858 |
| 1/19/2008 | 2008 | 1 | 19 | 233 | 2 | 40 | 21 | -11 | 5847 |
| 1/20/2008 | 2008 | 1 | 20 | 234 | 3 | 43 | 23 | -9 | 5838 |
| 1/21/2008 | 2008 | 1 | 21 | 235 | 17 | 52 | 34.5 | 2.5 | 5840.5 |
| 1/22/2008 | 2008 | 1 | 22 | 236 | 13 | 50 | 31.5 | -0.5 | 5840 |
| 1/23/2008 | 2008 | 1 | 23 | 237 | 9 | 46 | 27.5 | -4.5 | 5835.5 |
| 1/24/2008 | 2008 | 1 | 24 | 238 | 29 | 53 | 41 | 9 | 5844.5 |
| 1/25/2008 | 2008 | 1 | 25 | 239 | 19 | 46 | 32.5 | 0.5 | 5845 |
| 1/26/2008 | 2008 | 1 | 26 | 240 | 10 | 50 | 30 | -2 | 5843 |
| 1/27/2008 | 2008 | 1 | 27 | 241 | 29 | 55 | 42 | 10 | 5853 |
| 1/28/2008 | 2008 | 1 | 28 | 242 | 37 | 52 | 44.5 | 12.5 | 5865.5 |
| 1/29/2008 | 2008 | 1 | 29 | 243 | 12 | 39 | 25.5 | -6.5 | 5859 |
| 1/30/2008 | 2008 | 1 | 30 | 244 | 28 | 41 | 34.5 | 2.5 | 5861.5 |
| 1/31/2008 | 2008 | 1 | 31 | 245 | 8 | 38 | 23 | -9 | 5852.5 |
| 2/1/2008 | 2008 | 2 | 1 | 246 | 6 | 50 | 28 | -4 | 5848.5 |
| 2/2/2008 | 2008 | 2 | 2 | 247 | 18 | 51 | 34.5 | 2.5 | 5851 |
| 2/3/2008 | 2008 | 2 | 3 | 248 | 17 | 52 | 34.5 | 2.5 | 5853.5 |
| 2/4/2008 | 2008 | 2 | 4 | 249 | 28 | 48 | 38 | 6 | 5859.5 |
| 2/5/2008 | 2008 | 2 | 5 | 250 | 4 | 30 | 17 | -15 | 5844.5 |
| 2/6/2008 | 2008 | 2 | 6 | 251 | 4 | 30 | 17 | -15 | 5829.5 |
| 2/7/2008 | 2008 | 2 | 7 | 252 | 4 | 30 | 17 | -15 | 5814.5 |
| 2/8/2008 | 2008 | 2 | 8 | 253 | 4 | 30 | 17 | -15 | 5799.5 |
| 2/9/2008 | 2008 | 2 | 9 | 254 | 20 | 52 | 36 | 4 | 5803.5 |
| 2/10/2008 | 2008 | 2 | 10 | 255 | 20 | 59 | 39.5 | 7.5 | 5811 |
| 2/11/2008 | 2008 | 2 | 11 | 256 | 20 | 60 | 40 | 8 | 5819 |
| 2/12/2008 | 2008 | 2 | 12 | 257 | 21 | 60 | 40.5 | 8.5 | 5827.5 |
| 2/13/2008 | 2008 | 2 | 13 | 258 | 22 | 58 | 40 | 8 | 5835.5 |
| 2/14/2008 | 2008 | 2 | 14 | 259 | 32 | 55 | 43.5 | 11.5 | 5847 |
| 2/15/2008 | 2008 | 2 | 15 | 260 | 30 | 53 | 41.5 | 9.5 | 5856.5 |
| 2/16/2008 | 2008 | 2 | 16 | 261 | 30 | 58 | 44 | 12 | 5868.5 |
| 2/17/2008 | 2008 | 2 | 17 | 262 | 22 | 57 | 39.5 | 7.5 | 5876 |
| 2/18/2008 | 2008 | 2 | 18 | 263 | 15 | 52 | 33.5 | 1.5 | 5877.5 |
| 2/19/2008 | 2008 | 2 | 19 | 264 | 19 | 58 | 38.5 | 6.5 | 5884 |
| 2/20/2008 | 2008 | 2 | 20 | 265 | 30 | 60 | 45 | 13 | 5897 |
| 2/21/2008 | 2008 | 2 | 21 | 266 | 29 | 60 | 44.5 | 12.5 | 5909.5 |
| 2/22/2008 | 2008 | 2 | 22 | 267 | 27 | 54 | 40.5 | 8.5 | 5918 |
| 2/23/2008 | 2008 | 2 | 23 | 268 | 28 | 43 | 35.5 | 3.5 | 5921.5 |
| 2/24/2008 | 2008 | 2 | 24 | 269 | 29 | 55 | 42 | 10 | 5931.5 |
| 2/25/2008 | 2008 | 2 | 25 | 270 | 32 | 59 | 45.5 | 13.5 | 5945 |
| 2/26/2008 | 2008 | 2 | 26 | 271 | 22 | 62 | 42 | 10 | 5955 |
| 2/27/2008 | 2008 | 2 | 27 | 272 | 20 | 59 | 39.5 | 7.5 | 5962.5 |
| 2/28/2008 | 2008 | 2 | 28 | 273 | 20 | 68 | 44 | 12 | 5974.5 |
| 2/29/2008 | 2008 | 2 | 29 | 274 | 22 | 71 | 46.5 | 14.5 | 5989 |
| 3/1/2008 | 2008 | 3 | 1 | 275 | 22 | 72 | 47 | 15 | 6004 |
| 3/2/2008 | 2008 | 3 | 2 | 276 | 28 | 79 | 53.5 | 21.5 | 6025.5 |
| 3/3/2008 | 2008 | 3 | 3 | 277 | 18 | 35 | 26.5 | -5.5 | 6020 |
| 3/4/2008 | 2008 | 3 | 4 | 278 | 18 | 35 | 26.5 | -5.5 | 6014.5 |
| 3/5/2008 | 2008 | 3 | 5 | 279 | 17 | 60 | 38.5 | 6.5 | 6021 |
| 3/6/2008 | 2008 | 3 | 6 | 280 | 16 | 45 | 30.5 | -1.5 | 6019.5 |
| 3/7/2008 | 2008 | 3 | 7 | 281 | 17 | 50 | 33.5 | 1.5 | 6021 |
| 3/8/2008 | 2008 | 3 | 8 | 282 | 15 | 55 | 35 | 3 | 6024 |
| 3/9/2008 | 2008 | 3 | 9 | 283 | 20 | 59 | 39.5 | 7.5 | 6031.5 |
| 3/10/2008 | 2008 | 3 | 10 | 284 | 18 | 64 | 41 | 9 | 6040.5 |
| 3/11/2008 | 2008 | 3 | 11 | 285 | 18 | 64 | 41 | 9 | 6049.5 |
| 3/12/2008 | 2008 | 3 | 12 | 286 | 22 | 67 | 44.5 | 12.5 | 6062 |
| 3/13/2008 | 2008 | 3 | 13 | 287 | 30 | 71 | 50.5 | 18.5 | 6080.5 |
| 3/14/2008 | 2008 | 3 | 14 | 288 | 35 | 70 | 52.5 | 20.5 | 6101 |
| 3/15/2008 | 2008 | 3 | 15 | 289 | 17 | 65 | 41 | 9 | 6110 |
| 3/16/2008 | 2008 | 3 | 16 | 290 | 20 | 60 | 40 | 8 | 6118 |
| 3/17/2008 | 2008 | 3 | 17 | 291 | 28 | 60 | 44 | 12 | 6130 |
| 3/18/2008 | 2008 | 3 | 18 | 292 | 24 | 52 | 38 | 6 | 6136 |
| 3/19/2008 | 2008 | 3 | 19 | 293 | 15 | 60 | 37.5 | 5.5 | 6141.5 |
| 3/20/2008 | 2008 | 3 | 20 | 294 | 15 | 68 | 41.5 | 9.5 | 6151 |
| 3/21/2008 | 2008 | 3 | 21 | 295 | 17 | 70 | 43.5 | 11.5 | 6162.5 |
| 3/22/2008 | 2008 | 3 | 22 | 296 | 18 | 72 | 45 | 13 | 6175.5 |
| 3/23/2008 | 2008 | 3 | 23 | 297 | 16 | 67 | 41.5 | 9.5 | 6185 |
| 3/24/2008 | 2008 | 3 | 24 | 298 | 16 | 74 | 45 | 13 | 6198 |
| 3/25/2008 | 2008 | 3 | 25 | 299 | 22 | 74 | 48 | 16 | 6214 |
| 3/26/2008 | 2008 | 3 | 26 | 300 | 34 | 74 | 54 | 22 | 6236 |
| 3/27/2008 | 2008 | 3 | 27 | 301 | 30 | 74 | 52 | 20 | 6256 |
| 3/28/2008 | 2008 | 3 | 28 | 302 | 28 | 74 | 51 | 19 | 6275 |
| 3/29/2008 | 2008 | 3 | 29 | 303 | 28 | 70 | 49 | 17 | 6292 |
| 3/30/2008 | 2008 | 3 | 30 | 304 | 28 | 70 | 49 | 17 | 6309 |
| 3/31/2008 | 2008 | 3 | 31 | 305 | 32 | 70 | 51 | 19 | 6328 |
| 4/1/2008 | 2008 | 4 | 1 | 306 | 21 | 65 | 43 | 11 | 6339 |
| 4/2/2008 | 2008 | 4 | 2 | 307 | 35 | 71 | 53 | 21 | 6360 |
| 4/3/2008 | 2008 | 4 | 3 | 308 | 35 | 71 | 53 | 21 | 6381 |
| 4/4/2008 | 2008 | 4 | 4 | 309 | 22 | 63 | 42.5 | 10.5 | 6391.5 |
| 4/5/2008 | 2008 | 4 | 5 | 310 | 45 | 69 | 57 | 25 | 6416.5 |
| 4/6/2008 | 2008 | 4 | 6 | 311 | 44 | 72 | 58 | 26 | 6442.5 |
| 4/7/2008 | 2008 | 4 | 7 | 312 | 47 | 73 | 60 | 28 | 6470.5 |
| 4/8/2008 | 2008 | 4 | 8 | 313 | 35 | 70 | 52.5 | 20.5 | 6491 |
| 4/9/2008 | 2008 | 4 | 9 | 314 | 35 | 70 | 52.5 | 20.5 | 6511.5 |
| 4/10/2008 | 2008 | 4 | 10 | 315 | 29 | 59 | 44 | 12 | 6523.5 |
| 4/11/2008 | 2008 | 4 | 11 | 316 | 22 | 59 | 40.5 | 8.5 | 6532 |
| 4/12/2008 | 2008 | 4 | 12 | 317 | 17 | 56 | 36.5 | 4.5 | 6536.5 |
| 4/13/2008 | 2008 | 4 | 13 | 318 | 21 | 65 | 43 | 11 | 6547.5 |
| 4/14/2008 | 2008 | 4 | 14 | 319 | 24 | 70 | 47 | 15 | 6562.5 |
| 4/15/2008 | 2008 | 4 | 15 | 320 | 28 | 81 | 54.5 | 22.5 | 6585 |
| 4/16/2008 | 2008 | 4 | 16 | 321 | 28 | 80 | 54 | 22 | 6607 |
| 4/17/2008 | 2008 | 4 | 17 | 322 | 31 | 69 | 50 | 18 | 6625 |
| 4/18/2008 | 2008 | 4 | 18 | 323 | 31 | 69 | 50 | 18 | 6643 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/19/2008 | 2008 | 4 | 19 | 324 | 31 | 69 | 50 | 18 | 6661 |
| 4/20/2008 | 2008 | 4 | 20 | 325 | 31 | 69 | 50 | 18 | 6679 |
| 4/21/2008 | 2008 | 4 | 21 | 326 | 37 | 67 | 52 | 20 | 6699 |
| 4/22/2008 | 2008 | 4 | 22 | 327 | 37 | 67 | 52 | 20 | 6719 |
| 4/23/2008 | 2008 | 4 | 23 | 328 | 28 | 78 | 53 | 21 | 6740 |
| 4/24/2008 | 2008 | 4 | 24 | 329 | 37 | 77 | 57 | 25 | 6765 |
| 4/25/2008 | 2008 | 4 | 25 | 330 | 37 | 77 | 57 | 25 | 6790 |
| 4/26/2008 | 2008 | 4 | 26 | 331 | 37 | 77 | 57 | 25 | 6815 |
| 4/27/2008 | 2008 | 4 | 27 | 332 | 37 | 77 | 57 | 25 | 6840 |
| 4/28/2008 | 2008 | 4 | 28 | 333 | 19 | 71 | 45 | 13 | 6853 |
| 4/29/2008 | 2008 | 4 | 29 | 334 | 19 | 71 | 45 | 13 | 6866 |
| 4/30/2008 | 2008 | 4 | 30 | 335 | 45 | 81 | 63 | 31 | 6897 |
| 5/1/2008 | 2008 | 5 | 1 | 336 | 45 | 81 | 63 | 31 | 6928 |
| 5/2/2008 | 2008 | 5 | 2 | 337 | 24 | 63 | 43.5 | 11.5 | 6939.5 |
| 5/3/2008 | 2008 | 5 | 3 | 338 | 21 | 63 | 42 | 10 | 6949.5 |
| 5/4/2008 | 2008 | 5 | 4 | 339 | 44 | 79 | 61.5 | 29.5 | 6979 |
| 5/5/2008 | 2008 | 5 | 5 | 340 | 30 | 82 | 56 | 24 | 7003 |
| 5/6/2008 | 2008 | 5 | 6 | 341 | 30 | 82 | 56 | 24 | 7027 |
| 5/7/2008 | 2008 | 5 | 7 | 342 | 33 | 73 | 53 | 21 | 7048 |
| 5/8/2008 | 2008 | 5 | 8 | 343 | 50 | 79 | 64.5 | 32.5 | 7080.5 |
| 5/9/2008 | 2008 | 5 | 9 | 344 | 43 | 75 | 59 | 27 | 7107.5 |
| 5/10/2008 | 2008 | 5 | 10 | 345 | 37 | 75 | 56 | 24 | 7131.5 |
| 5/11/2008 | 2008 | 5 | 11 | 346 | 30 | 75 | 52.5 | 20.5 | 7152 |
| 5/12/2008 | 2008 | 5 | 12 | 347 | 36 | 82 | 59 | 27 | 7179 |
| 5/13/2008 | 2008 | 5 | 13 | 348 | 44 | 76 | 60 | 28 | 7207 |
| 5/14/2008 | 2008 | 5 | 14 | 349 | 49 | 74 | 61.5 | 29.5 | 7236.5 |
| 5/15/2008 | 2008 | 5 | 15 | 350 | 49 | 74 | 61.5 | 29.5 | 7266 |
| 5/16/2008 | 2008 | 5 | 16 | 351 | 39 | 77 | 58 | 26 | 7292 |
| 5/17/2008 | 2008 | 5 | 17 | 352 | 37 | 81 | 59 | 27 | 7319 |
| 5/18/2008 | 2008 | 5 | 18 | 353 | 38 | 82 | 60 | 28 | 7347 |
| 5/19/2008 | 2008 | 5 | 19 | 354 | 38 | 89 | 63.5 | 31.5 | 7378.5 |
| 5/20/2008 | 2008 | 5 | 20 | 355 | 42 | 96 | 69 | 37 | 7415.5 |
| 5/21/2008 | 2008 | 5 | 21 | 356 | 41 | 83 | 62 | 30 | 7445.5 |
| 5/22/2008 | 2008 | 5 | 22 | 357 | 39 | 52 | 45.5 | 13.5 | 7459 |
| 5/23/2008 | 2008 | 5 | 23 | 358 | 35 | 54 | 44.5 | 12.5 | 7471.5 |
| 5/24/2008 | 2008 | 5 | 24 | 359 | 45 | 68 | 56.5 | 24.5 | 7496 |
| 5/25/2008 | 2008 | 5 | 25 | 360 | 41 | 72 | 56.5 | 24.5 | 7520.5 |
| 5/26/2008 | 2008 | 5 | 26 | 361 | 38 | 70 | 54 | 22 | 7542.5 |
| 5/27/2008 | 2008 | 5 | 27 | 362 | 41 | 79 | 60 | 28 | 7570.5 |
| 5/28/2008 | 2008 | 5 | 28 | 363 | 44 | 82 | 63 | 31 | 7601.5 |
| 5/29/2008 | 2008 | 5 | 29 | 364 | 40 | 84 | 62 | 30 | 7631.5 |
| 5/30/2008 | 2008 | 5 | 30 | 365 | 37 | 88 | 62.5 | 30.5 | 7662 |
| 5/31/2008 | 2008 | 5 | 31 | 366 | 39 | 86 | 62.5 | 30.5 | 7692.5 |
| 6/1/2008 | 2008 | 6 | 1 | 1 | 40 | 89 | 64.5 | 32.5 | 32.5 |
| 6/2/2008 | 2008 | 6 | 2 | 2 | 46 | 93 | 69.5 | 37.5 | 70 |
| 6/3/2008 | 2008 | 6 | 3 | 3 | 48 | 88 | 68 | 36 | 106 |
| 6/4/2008 | 2008 | 6 | 4 | 4 | 60 | 86 | 73 | 41 | 147 |
| 6/5/2008 | 2008 | 6 | 5 | 5 | 39 | 83 | 61 | 29 | 176 |
| 6/6/2008 | 2008 | 6 | 6 | 6 | 36 | 67 | 51.5 | 19.5 | 195.5 |
| 6/7/2008 | 2008 | 6 | 7 | 7 | 40 | 84 | 62 | 30 | 225.5 |
| 6/8/2008 | 2008 | 6 | 8 | 8 | 44 | 86 | 65 | 33 | 258.5 |
| 6/9/2008 | 2008 | 6 | 9 | 9 | 38 | 90 | 64 | 32 | 290.5 |
| 6/10/2008 | 2008 | 6 | 10 | 10 | 38 | 93 | 65.5 | 33.5 | 324 |
| 6/11/2008 | 2008 | 6 | 11 | 11 | 38 | 92 | 65 | 33 | 357 |
| 6/12/2008 | 2008 | 6 | 12 | 12 | 37 | 90 | 63.5 | 31.5 | 388.5 |
| 6/13/2008 | 2008 | 6 | 13 | 13 | 37 | 88 | 62.5 | 30.5 | 419 |
| 6/14/2008 | 2008 | 6 | 14 | 14 | 40 | 93 | 66.5 | 34.5 | 453.5 |
| 6/15/2008 | 2008 | 6 | 15 | 15 | 44 | 95 | 69.5 | 37.5 | 491 |
| 6/16/2008 | 2008 | 6 | 16 | 16 | 48 | 96 | 72 | 40 | 531 |
| 6/17/2008 | 2008 | 6 | 17 | 17 | 29 | 96 | 62.5 | 30.5 | 561.5 |
| 6/18/2008 | 2008 | 6 | 18 | 18 | 51 | 96 | 73.5 | 41.5 | 603 |
| 6/19/2008 | 2008 | 6 | 19 | 19 | 50 | 95 | 72.5 | 40.5 | 643.5 |
| 6/20/2008 | 2008 | 6 | 20 | 20 | 49 | 98 | 73.5 | 41.5 | 685 |
| 6/21/2008 | 2008 | 6 | 21 | 21 | 50 | 96 | 73 | 41 | 726 |
| 6/22/2008 | 2008 | 6 | 22 | 22 | 58 | 88 | 73 | 41 | 767 |
| 6/23/2008 | 2008 | 6 | 23 | 23 | 51 | 95 | 73 | 41 | 808 |
| 6/24/2008 | 2008 | 6 | 24 | 24 | 49 | 94 | 71.5 | 39.5 | 847.5 |
| 6/25/2008 | 2008 | 6 | 25 | 25 | 54 | 97 | 75.5 | 43.5 | 891 |
| 6/26/2008 | 2008 | 6 | 26 | 26 | 53 | 96 | 74.5 | 42.5 | 933.5 |
| 6/27/2008 | 2008 | 6 | 27 | 27 | 55 | 95 | 75 | 43 | 976.5 |
| 6/28/2008 | 2008 | 6 | 28 | 28 | 54 | 89 | 71.5 | 39.5 | 1016 |
| 6/29/2008 | 2008 | 6 | 29 | 29 | 54 | 89 | 71.5 | 39.5 | 1055.5 |
| 6/30/2008 | 2008 | 6 | 30 | 30 | 56 | 96 | 76 | 44 | 1099.5 |
| 7/1/2008 | 2008 | 7 | 1 | 31 | 53 | 97 | 75 | 43 | 1142.5 |
| 7/2/2008 | 2008 | 7 | 2 | 32 | 56 | 92 | 74 | 42 | 1184.5 |
| 7/3/2008 | 2008 | 7 | 3 | 33 | 51 | 90 | 70.5 | 38.5 | 1223 |
| 7/4/2008 | 2008 | 7 | 4 | 34 | 54 | 94 | 74 | 42 | 1265 |
| 7/5/2008 | 2008 | 7 | 5 | 35 | 55 | 95 | 75 | 43 | 1308 |
| 7/6/2008 | 2008 | 7 | 6 | 36 | 61 | 95 | 78 | 46 | 1354 |
| 7/7/2008 | 2008 | 7 | 7 | 37 | 59 | 90 | 74.5 | 42.5 | 1396.5 |
| 7/8/2008 | 2008 | 7 | 8 | 38 | 58 | 85 | 71.5 | 39.5 | 1436 |
| 7/9/2008 | 2008 | 7 | 9 | 39 | 58 | 90 | 74 | 42 | 1478 |
| 7/10/2008 | 2008 | 7 | 10 | 40 | 50 | 81 | 65.5 | 33.5 | 1511.5 |
| 7/11/2008 | 2008 | 7 | 11 | 41 | 57 | 84 | 70.5 | 38.5 | 1550 |
| 7/12/2008 | 2008 | 7 | 12 | 42 | 55 | 84 | 69.5 | 37.5 | 1587.5 |
| 7/13/2008 | 2008 | 7 | 13 | 43 | 56 | 83 | 69.5 | 37.5 | 1625 |
| 7/14/2008 | 2008 | 7 | 14 | 44 | 54 | 84 | 69 | 37 | 1662 |
| 7/15/2008 | 2008 | 7 | 15 | 45 | 56 | 83 | 69.5 | 37.5 | 1699.5 |
| 7/16/2008 | 2008 | 7 | 16 | 46 | 63 | 92 | 77.5 | 45.5 | 1745 |
| 7/17/2008 | 2008 | 7 | 17 | 47 | 58 | 92 | 75 | 43 | 1788 |
| 7/18/2008 | 2008 | 7 | 18 | 48 | 55 | 93 | 74 | 42 | 1830 |
| 7/19/2008 | 2008 | 7 | 19 | 49 | 62 | 96 | 79 | 47 | 1877 |
| 7/20/2008 | 2008 | 7 | 20 | 50 | 57 | 98 | 77.5 | 45.5 | 1922.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/21/2008 | 2008 | 7 | 21 | 51 | 63 | 85 | 74 | 42 | 1964.5 |
| 7/22/2008 | 2008 | 7 | 22 | 52 | 61 | 88 | 74.5 | 42.5 | 2007 |
| 7/23/2008 | 2008 | 7 | 23 | 53 | 60 | 90 | 75 | 43 | 2050 |
| 7/24/2008 | 2008 | 7 | 24 | 54 | 55 | 88 | 71.5 | 39.5 | 2089.5 |
| 7/25/2008 | 2008 | 7 | 25 | 55 | 63 | 90 | 76.5 | 44.5 | 2134 |
| 7/26/2008 | 2008 | 7 | 26 | 56 | 60 | 95 | 77.5 | 45.5 | 2179.5 |
| 7/27/2008 | 2008 | 7 | 27 | 57 | 57 | 83 | 70 | 38 | 2217.5 |
| 7/28/2008 | 2008 | 7 | 28 | 58 | 64 | 87 | 75.5 | 43.5 | 2261 |
| 7/29/2008 | 2008 | 7 | 29 | 59 | 55 | 94 | 74.5 | 42.5 | 2303.5 |
| 7/30/2008 | 2008 | 7 | 30 | 60 | 51 | 96 | 73.5 | 41.5 | 2345 |
| 7/31/2008 | 2008 | 7 | 31 | 61 | 54 | 98 | 76 | 44 | 2389 |
| 8/1/2008 | 2008 | 8 | 1 | 62 | 62 | 98 | 80 | 48 | 2437 |
| 8/2/2008 | 2008 | 8 | 2 | 63 | 55 | 94 | 74.5 | 42.5 | 2479.5 |
| 8/3/2008 | 2008 | 8 | 3 | 64 | 54 | 99 | 76.5 | 44.5 | 2524 |
| 8/4/2008 | 2008 | 8 | 4 | 65 | 55 | 94 | 74.5 | 42.5 | 2566.5 |
| 8/5/2008 | 2008 | 8 | 5 | 66 | 60 | 92 | 76 | 44 | 2610.5 |
| 8/6/2008 | 2008 | 8 | 6 | 67 | 58 | 86 | 72 | 40 | 2650.5 |
| 8/7/2008 | 2008 | 8 | 7 | 68 | 55 | 88 | 71.5 | 39.5 | 2690 |
| 8/8/2008 | 2008 | 8 | 8 | 69 | 59 | 87 | 73 | 41 | 2731 |
| 8/9/2008 | 2008 | 8 | 9 | 70 | 61 | 88 | 74.5 | 42.5 | 2773.5 |
| 8/10/2008 | 2008 | 8 | 10 | 71 | 53 | 89 | 71 | 39 | 2812.5 |
| 8/11/2008 | 2008 | 8 | 11 | 72 | 54 | 92 | 73 | 41 | 2853.5 |
| 8/12/2008 | 2008 | 8 | 12 | 73 | 50 | 96 | 73 | 41 | 2894.5 |
| 8/13/2008 | 2008 | 8 | 13 | 74 | 64 | 94 | 79 | 47 | 2941.5 |
| 8/14/2008 | 2008 | 8 | 14 | 75 | 53 | 92 | 72.5 | 40.5 | 2982 |
| 8/15/2008 | 2008 | 8 | 15 | 76 | 68 | 96 | 82 | 50 | 3032 |
| 8/16/2008 | 2008 | 8 | 16 | 77 | 62 | 94 | 78 | 46 | 3078 |
| 8/17/2008 | 2008 | 8 | 17 | 78 | 60 | 93 | 76.5 | 44.5 | 3122.5 |
| 8/18/2008 | 2008 | 8 | 18 | 79 | 43 | 90 | 66.5 | 34.5 | 3157 |
| 8/19/2008 | 2008 | 8 | 19 | 80 | 46 | 89 | 67.5 | 35.5 | 3192.5 |
| 8/20/2008 | 2008 | 8 | 20 | 81 | 55 | 92 | 73.5 | 41.5 | 3234 |
| 8/21/2008 | 2008 | 8 | 21 | 82 | 46 | 90 | 68 | 36 | 3270 |
| 8/22/2008 | 2008 | 8 | 22 | 83 | 52 | 93 | 72.5 | 40.5 | 3310.5 |
| 8/23/2008 | 2008 | 8 | 23 | 84 | 49 | 96 | 72.5 | 40.5 | 3351 |
| 8/24/2008 | 2008 | 8 | 24 | 85 | 50 | 92 | 71 | 39 | 3390 |
| 8/25/2008 | 2008 | 8 | 25 | 86 | 50 | 91 | 70.5 | 38.5 | 3428.5 |
| 8/26/2008 | 2008 | 8 | 26 | 87 | 56 | 90 | 73 | 41 | 3469.5 |
| 8/27/2008 | 2008 | 8 | 27 | 88 | 57 | 89 | 73 | 41 | 3510.5 |
| 8/28/2008 | 2008 | 8 | 28 | 89 | 60 | 94 | 77 | 45 | 3555.5 |
| 8/29/2008 | 2008 | 8 | 29 | 90 | 59 | 94 | 76.5 | 44.5 | 3600 |
| 8/30/2008 | 2008 | 8 | 30 | 91 | 58 | 87 | 72.5 | 40.5 | 3640.5 |
| 8/31/2008 | 2008 | 8 | 31 | 92 | 61 | 89 | 75 | 43 | 3683.5 |
| 9/1/2008 | 2008 | 9 | 1 | 93 | 52 | 76 | 64 | 32 | 3715.5 |
| 9/2/2008 | 2008 | 9 | 2 | 94 | 48 | 85 | 66.5 | 34.5 | 3750 |
| 9/3/2008 | 2008 | 9 | 3 | 95 | 56 | 88 | 72 | 40 | 3790 |
| 9/4/2008 | 2008 | 9 | 4 | 96 | 44 | 80 | 62 | 30 | 3820 |
| 9/5/2008 | 2008 | 9 | 5 | 97 | 40 | 78 | 59 | 27 | 3847 |
| 9/6/2008 | 2008 | 9 | 6 | 98 | 38 | 89 | 63.5 | 31.5 | 3878.5 |
| 9/7/2008 | 2008 | 9 | 7 | 99 | 44 | 93 | 68.5 | 36.5 | 3915 |
| 9/8/2008 | 2008 | 9 | 8 | 100 | 47 | 89 | 68 | 36 | 3951 |
| 9/9/2008 | 2008 | 9 | 9 | 101 | 57 | 90 | 73.5 | 41.5 | 3992.5 |
| 9/10/2008 | 2008 | 9 | 10 | 102 | 51 | 76 | 63.5 | 31.5 | 4024 |
| 9/11/2008 | 2008 | 9 | 11 | 103 | 51 | 81 | 66 | 34 | 4058 |
| 9/12/2008 | 2008 | 9 | 12 | 104 | 53 | 72 | 62.5 | 30.5 | 4088.5 |
| 9/13/2008 | 2008 | 9 | 13 | 105 | 39 | 79 | 59 | 27 | 4115.5 |
| 9/14/2008 | 2008 | 9 | 14 | 106 | 46 | 80 | 63 | 31 | 4146.5 |
| 9/15/2008 | 2008 | 9 | 15 | 107 | 47 | 80 | 63.5 | 31.5 | 4178 |
| 9/16/2008 | 2008 | 9 | 16 | 108 | 44 | 79 | 61.5 | 29.5 | 4207.5 |
| 9/17/2008 | 2008 | 9 | 17 | 109 | 48 | 80 | 64 | 32 | 4239.5 |
| 9/18/2008 | 2008 | 9 | 18 | 110 | 49 | 81 | 65 | 33 | 4272.5 |
| 9/19/2008 | 2008 | 9 | 19 | 111 | 42 | 80 | 61 | 29 | 4301.5 |
| 9/20/2008 | 2008 | 9 | 20 | 112 | 44 | 83 | 63.5 | 31.5 | 4333 |
| 9/21/2008 | 2008 | 9 | 21 | 113 | 46 | 85 | 65.5 | 33.5 | 4366.5 |
| 9/22/2008 | 2008 | 9 | 22 | 114 | 49 | 84 | 66.5 | 34.5 | 4401 |
| 9/23/2008 | 2008 | 9 | 23 | 115 | 41 | 83 | 62 | 30 | 4431 |
| 9/24/2008 | 2008 | 9 | 24 | 116 | 40 | 84 | 62 | 30 | 4461 |
| 9/25/2008 | 2008 | 9 | 25 | 117 | 46 | 86 | 66 | 34 | 4495 |
| 9/26/2008 | 2008 | 9 | 26 | 118 | 47 | 84 | 65.5 | 33.5 | 4528.5 |
| 9/27/2008 | 2008 | 9 | 27 | 119 | 48 | 85 | 66.5 | 34.5 | 4563 |
| 9/28/2008 | 2008 | 9 | 28 | 120 | 41 | 81 | 61 | 29 | 4592 |
| 9/29/2008 | 2008 | 9 | 29 | 121 | 39 | 84 | 61.5 | 29.5 | 4621.5 |
| 9/30/2008 | 2008 | 9 | 30 | 122 | 38 | 79 | 58.5 | 26.5 | 4648 |
| 10/1/2008 | 2008 | 10 | 1 | 123 | 37 | 78 | 57.5 | 25.5 | 4673.5 |
| 10/2/2008 | 2008 | 10 | 2 | 124 | 38 | 80 | 59 | 27 | 4700.5 |
| 10/3/2008 | 2008 | 10 | 3 | 125 | 44 | 82 | 63 | 31 | 4731.5 |
| 10/4/2008 | 2008 | 10 | 4 | 126 | 43 | 83 | 63 | 31 | 4762.5 |
| 10/5/2008 | 2008 | 10 | 5 | 127 | 43 | 79 | 61 | 29 | 4791.5 |
| 10/6/2008 | 2008 | 10 | 6 | 128 | 42 | 65 | 53.5 | 21.5 | 4813 |
| 10/7/2008 | 2008 | 10 | 7 | 129 | 32 | 68 | 50 | 18 | 4831 |
| 10/8/2008 | 2008 | 10 | 8 | 130 | 34 | 78 | 56 | 24 | 4855 |
| 10/9/2008 | 2008 | 10 | 9 | 131 | 33 | 80 | 56.5 | 24.5 | 4879.5 |
| 10/10/2008 | 2008 | 10 | 10 | 132 | 36 | 81 | 58.5 | 26.5 | 4906 |
| 10/11/2008 | 2008 | 10 | 11 | 133 | 51 | 77 | 64 | 32 | 4938 |
| 10/12/2008 | 2008 | 10 | 12 | 134 | 36 | 68 | 52 | 20 | 4958 |
| 10/13/2008 | 2008 | 10 | 13 | 135 | 23 | 65 | 44 | 12 | 4970 |
| 10/14/2008 | 2008 | 10 | 14 | 136 | 26 | 66 | 46 | 14 | 4984 |
| 10/15/2008 | 2008 | 10 | 15 | 137 | 15 | 61 | 38 | 6 | 4990 |
| 10/16/2008 | 2008 | 10 | 16 | 138 | 29 | 66 | 47.5 | 15.5 | 5005.5 |
| 10/17/2008 | 2008 | 10 | 17 | 139 | 31 | 76 | 53.5 | 21.5 | 5027 |
| 10/18/2008 | 2008 | 10 | 18 | 140 | 29 | 81 | 55 | 23 | 5050 |
| 10/19/2008 | 2008 | 10 | 19 | 141 | 32 | 78 | 55 | 23 | 5073 |
| 10/20/2008 | 2008 | 10 | 20 | 142 | 33 | 80 | 56.5 | 24.5 | 5097.5 |
| 10/21/2008 | 2008 | 10 | 21 | 143 | 31 | 75 | 53 | 21 | 5118.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/22/2008 | 2008 | 10 | 22 | 144 | 33 | 76 | 54.5 | 22.5 | 5141 |
| 10/23/2008 | 2008 | 10 | 23 | 145 | 28 | 71 | 49.5 | 17.5 | 5158.5 |
| 10/24/2008 | 2008 | 10 | 24 | 146 | 19 | 68 | 43.5 | 11.5 | 5170 |
| 10/25/2008 | 2008 | 10 | 25 | 147 | 23 | 75 | 49 | 17 | 5187 |
| 10/26/2008 | 2008 | 10 | 26 | 148 | 25 | 77 | 51 | 19 | 5206 |
| 10/27/2008 | 2008 | 10 | 27 | 149 | 31 | 78 | 54.5 | 22.5 | 5228.5 |
| 10/28/2008 | 2008 | 10 | 28 | 150 | 27 | 80 | 53.5 | 21.5 | 5250 |
| 10/29/2008 | 2008 | 10 | 29 | 151 | 30 | 79 | 54.5 | 22.5 | 5272.5 |
| 10/30/2008 | 2008 | 10 | 30 | 152 | 29 | 80 | 54.5 | 22.5 | 5295 |
| 10/31/2008 | 2008 | 10 | 31 | 153 | 29 | 81 | 55 | 23 | 5318 |
| 11/1/2008 | 2008 | 11 | 1 | 154 | 28 | 80 | 54 | 22 | 5340 |
| 11/2/2008 | 2008 | 11 | 2 | 155 | 30 | 78 | 54 | 22 | 5362 |
| 11/3/2008 | 2008 | 11 | 3 | 156 | 43 | 77 | 60 | 28 | 5390 |
| 11/4/2008 | 2008 | 11 | 4 | 157 | 39 | 73 | 56 | 24 | 5414 |
| 11/5/2008 | 2008 | 11 | 5 | 158 | 36 | 67 | 51.5 | 19.5 | 5433.5 |
| 11/6/2008 | 2008 | 11 | 6 | 159 | 16 | 51 | 33.5 | 1.5 | 5435 |
| 11/7/2008 | 2008 | 11 | 7 | 160 | 10 | 50 | 30 | -2 | 5433 |
| 11/8/2008 | 2008 | 11 | 8 | 161 | 18 | 56 | 37 | 5 | 5438 |
| 11/9/2008 | 2008 | 11 | 9 | 162 | 17 | 66 | 41.5 | 9.5 | 5447.5 |
| 11/10/2008 | 2008 | 11 | 10 | 163 | 23 | 57 | 40 | 8 | 5455.5 |
| 11/11/2008 | 2008 | 11 | 11 | 164 | 16 | 56 | 36 | 4 | 5459.5 |
| 11/12/2008 | 2008 | 11 | 12 | 165 | 20 | 58 | 39 | 7 | 5466.5 |
| 11/13/2008 | 2008 | 11 | 13 | 166 | 26 | 61 | 43.5 | 11.5 | 5478 |
| 11/14/2008 | 2008 | 11 | 14 | 167 | 32 | 69 | 50.5 | 18.5 | 5496.5 |
| 11/15/2008 | 2008 | 11 | 15 | 168 | 16 | 64 | 40 | 8 | 5504.5 |
| 11/16/2008 | 2008 | 11 | 16 | 169 | 15 | 62 | 38.5 | 6.5 | 5511 |
| 11/17/2008 | 2008 | 11 | 17 | 170 | 20 | 60 | 40 | 8 | 5519 |
| 11/18/2008 | 2008 | 11 | 18 | 171 | 21 | 71 | 46 | 14 | 5533 |
| 11/19/2008 | 2008 | 11 | 19 | 172 | 19 | 69 | 44 | 12 | 5545 |
| 11/20/2008 | 2008 | 11 | 20 | 173 | 15 | 74 | 44.5 | 12.5 | 5557.5 |
| 11/21/2008 | 2008 | 11 | 21 | 174 | 17 | 60 | 38.5 | 6.5 | 5564 |
| 11/22/2008 | 2008 | 11 | 22 | 175 | 14 | 56 | 35 | 3 | 5567 |
| 11/23/2008 | 2008 | 11 | 23 | 176 | 19 | 67 | 43 | 11 | 5578 |
| 11/24/2008 | 2008 | 11 | 24 | 177 | 13 | 70 | 41.5 | 9.5 | 5587.5 |
| 11/25/2008 | 2008 | 11 | 25 | 178 | 17 | 58 | 37.5 | 5.5 | 5593 |
| 11/26/2008 | 2008 | 11 | 26 | 179 | 25 | 59 | 42 | 10 | 5603 |
| 11/27/2008 | 2008 | 11 | 27 | 180 | 37 | 62 | 49.5 | 17.5 | 5620.5 |
| 11/28/2008 | 2008 | 11 | 28 | 181 | 36 | 53 | 44.5 | 12.5 | 5633 |
| 11/29/2008 | 2008 | 11 | 29 | 182 | 28 | 45 | 36.5 | 4.5 | 5637.5 |
| 11/30/2008 | 2008 | 11 | 30 | 183 | 27 | 52 | 39.5 | 7.5 | 5645 |
| 12/1/2008 | 2008 | 12 | 1 | 184 | 27 | 60 | 43.5 | 11.5 | 5656.5 |
| 12/2/2008 | 2008 | 12 | 2 | 185 | 22 | 60 | 41 | 9 | 5665.5 |
| 12/3/2008 | 2008 | 12 | 3 | 186 | 35 | 69 | 52 | 20 | 5685.5 |
| 12/4/2008 | 2008 | 12 | 4 | 187 | 15 | 59 | 37 | 5 | 5690.5 |
| 12/5/2008 | 2008 | 12 | 5 | 188 | 15 | 54 | 34.5 | 2.5 | 5693 |
| 12/6/2008 | 2008 | 12 | 6 | 189 | 19 | 55 | 37 | 5 | 5698 |
| 12/7/2008 | 2008 | 12 | 7 | 190 | 17 | 63 | 40 | 8 | 5706 |
| 12/8/2008 | 2008 | 12 | 8 | 191 | 27 | 61 | 44 | 12 | 5718 |
| 12/9/2008 | 2008 | 12 | 9 | 192 | 37 | 51 | 44 | 12 | 5730 |
| 12/10/2008 | 2008 | 12 | 10 | 193 | 8 | 48 | 28 | -4 | 5726 |
| 12/11/2008 | 2008 | 12 | 11 | 194 | 11 | 45 | 28 | -4 | 5722 |
| 12/12/2008 | 2008 | 12 | 12 | 195 | 15 | 50 | 32.5 | 0.5 | 5722.5 |
| 12/13/2008 | 2008 | 12 | 13 | 196 | 18 | 51 | 34.5 | 2.5 | 5725 |
| 12/14/2008 | 2008 | 12 | 14 | 197 | 25 | 55 | 40 | 8 | 5733 |
| 12/15/2008 | 2008 | 12 | 15 | 198 | 17 | 34 | 25.5 | -6.5 | 5726.5 |
| 12/16/2008 | 2008 | 12 | 16 | 199 | 23 | 35 | 29 | -3 | 5723.5 |
| 12/17/2008 | 2008 | 12 | 17 | 200 | 28 | 48 | 38 | 6 | 5729.5 |
| 12/18/2008 | 2008 | 12 | 18 | 201 | 15 | 35 | 25 | -7 | 5722.5 |
| 12/19/2008 | 2008 | 12 | 19 | 202 | 20 | 47 | 33.5 | 1.5 | 5724 |
| 12/20/2008 | 2008 | 12 | 20 | 203 | 24 | 50 | 37 | 5 | 5729 |
| 12/21/2008 | 2008 | 12 | 21 | 204 | 22 | 50 | 36 | 4 | 5733 |
| 12/22/2008 | 2008 | 12 | 22 | 205 | 20 | 51 | 35.5 | 3.5 | 5736.5 |
| 12/23/2008 | 2008 | 12 | 23 | 206 | 28 | 41 | 34.5 | 2.5 | 5739 |
| 12/24/2008 | 2008 | 12 | 24 | 207 | 11 | 37 | 24 | -8 | 5731 |
| 12/25/2008 | 2008 | 12 | 25 | 208 | 11 | 37 | 24 | -8 | 5723 |
| 12/26/2008 | 2008 | 12 | 26 | 209 | 22 | 51 | 36.5 | 4.5 | 5727.5 |
| 12/27/2008 | 2008 | 12 | 27 | 210 | 7 | 32 | 19.5 | -12.5 | 5715 |
| 12/28/2008 | 2008 | 12 | 28 | 211 | 7 | 29 | 18 | -14 | 5701 |
| 12/29/2008 | 2008 | 12 | 29 | 212 | 11 | 43 | 27 | -5 | 5696 |
| 12/30/2008 | 2008 | 12 | 30 | 213 | 11 | 51 | 31 | -1 | 5695 |
| 12/31/2008 | 2008 | 12 | 31 | 214 | 16 | 55 | 35.5 | 3.5 | 5698.5 |
| 1/1/2009 | 2009 | 1 | 1 | 215 | 16 | 53 | 34.5 | 2.5 | 5701 |
| 1/2/2009 | 2009 | 1 | 2 | 216 | 25 | 56 | 40.5 | 8.5 | 5709.5 |
| 1/3/2009 | 2009 | 1 | 3 | 217 | 30 | 63 | 46.5 | 14.5 | 5724 |
| 1/4/2009 | 2009 | 1 | 4 | 218 | 28 | 51 | 39.5 | 7.5 | 5731.5 |
| 1/5/2009 | 2009 | 1 | 5 | 219 | 21 | 31 | 26 | -6 | 5725.5 |
| 1/6/2009 | 2009 | 1 | 6 | 220 | 17 | 40 | 28.5 | -3.5 | 5722 |
| 1/7/2009 | 2009 | 1 | 7 | 221 | 23 | 47 | 35 | 3 | 5725 |
| 1/8/2009 | 2009 | 1 | 8 | 222 | 24 | 51 | 37.5 | 5.5 | 5730.5 |
| 1/9/2009 | 2009 | 1 | 9 | 223 | 26 | 53 | 39.5 | 7.5 | 5738 |
| 1/10/2009 | 2009 | 1 | 10 | 224 | 25 | 51 | 38 | 6 | 5744 |
| 1/11/2009 | 2009 | 1 | 11 | 225 | 15 | 43 | 29 | -3 | 5741 |
| 1/12/2009 | 2009 | 1 | 12 | 226 | 20 | 47 | 33.5 | 1.5 | 5742.5 |
| 1/13/2009 | 2009 | 1 | 13 | 227 | 18 | 47 | 32.5 | 0.5 | 5743 |
| 1/14/2009 | 2009 | 1 | 14 | 228 | 17 | 51 | 34 | 2 | 5745 |
| 1/15/2009 | 2009 | 1 | 15 | 229 | 18 | 51 | 34.5 | 2.5 | 5747.5 |
| 1/16/2009 | 2009 | 1 | 16 | 230 | 18 | 57 | 37.5 | 5.5 | 5753 |
| 1/17/2009 | 2009 | 1 | 17 | 231 | 15 | 56 | 35.5 | 3.5 | 5756.5 |
| 1/18/2009 | 2009 | 1 | 18 | 232 | 17 | 60 | 38.5 | 6.5 | 5763 |
| 1/19/2009 | 2009 | 1 | 19 | 233 | 16 | 58 | 37 | 5 | 5768 |
| 1/20/2009 | 2009 | 1 | 20 | 234 | 17 | 63 | 40 | 8 | 5776 |
| 1/21/2009 | 2009 | 1 | 21 | 235 | 17 | 60 | 38.5 | 6.5 | 5782.5 |
| 1/22/2009 | 2009 | 1 | 22 | 236 | 20 | 57 | 38.5 | 6.5 | 5789 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/23/2009 | 2009 | 1 | 23 | 237 | 33 | 56 | 44.5 | 12.5 | 5801.5 |
| 1/24/2009 | 2009 | 1 | 24 | 238 | 27 | 63 | 45 | 13 | 5814.5 |
| 1/25/2009 | 2009 | 1 | 25 | 239 | 29 | 56 | 42.5 | 10.5 | 5825 |
| 1/26/2009 | 2009 | 1 | 26 | 240 | 21 | 57 | 39 | 7 | 5832 |
| 1/27/2009 | 2009 | 1 | 27 | 241 | 17 | 53 | 35 | 3 | 5835 |
| 1/28/2009 | 2009 | 1 | 28 | 242 | 12 | 41 | 26.5 | -5.5 | 5829.5 |
| 1/29/2009 | 2009 | 1 | 29 | 243 | 13 | 47 | 30 | -2 | 5827.5 |
| 1/30/2009 | 2009 | 1 | 30 | 244 | 14 | 45 | 29.5 | -2.5 | 5825 |
| 1/31/2009 | 2009 | 1 | 31 | 245 | 16 | 48 | 32 | 0 | 5825 |
| 2/1/2009 | 2009 | 2 | 1 | 246 | 17 | 63 | 40 | 8 | 5833 |
| 2/2/2009 | 2009 | 2 | 2 | 247 | 12 | 64 | 38 | 6 | 5839 |
| 2/3/2009 | 2009 | 2 | 3 | 248 | 13 | 59 | 36 | 4 | 5843 |
| 2/4/2009 | 2009 | 2 | 4 | 249 | 13 | 60 | 36.5 | 4.5 | 5847.5 |
| 2/5/2009 | 2009 | 2 | 5 | 250 | 15 | 65 | 40 | 8 | 5855.5 |
| 2/6/2009 | 2009 | 2 | 6 | 251 | 14 | 65 | 39.5 | 7.5 | 5863 |
| 2/7/2009 | 2009 | 2 | 7 | 252 | 19 | 63 | 41 | 9 | 5872 |
| 2/8/2009 | 2009 | 2 | 8 | 253 | 28 | 62 | 45 | 13 | 5885 |
| 2/9/2009 | 2009 | 2 | 9 | 254 | 27 | 52 | 39.5 | 7.5 | 5892.5 |
| 2/10/2009 | 2009 | 2 | 10 | 255 | 22 | 47 | 34.5 | 2.5 | 5895 |
| 2/11/2009 | 2009 | 2 | 11 | 256 | 10 | 45 | 27.5 | -4.5 | 5890.5 |
| 2/12/2009 | 2009 | 2 | 12 | 257 | 22 | 58 | 40 | 8 | 5898.5 |
| 2/13/2009 | 2009 | 2 | 13 | 258 | 15 | 57 | 36 | 4 | 5902.5 |
| 2/14/2009 | 2009 | 2 | 14 | 259 | 18 | 52 | 35 | 3 | 5905.5 |
| 2/15/2009 | 2009 | 2 | 15 | 260 | 17 | 47 | 32 | 0 | 5905.5 |
| 2/16/2009 | 2009 | 2 | 16 | 261 | 17 | 47 | 32 | 0 | 5905.5 |
| 2/17/2009 | 2009 | 2 | 17 | 262 | 19 | 58 | 38.5 | 6.5 | 5912 |
| 2/18/2009 | 2009 | 2 | 18 | 263 | 22 | 60 | 41 | 9 | 5921 |
| 2/19/2009 | 2009 | 2 | 19 | 264 | 10 | 51 | 30.5 | -1.5 | 5919.5 |
| 2/20/2009 | 2009 | 2 | 20 | 265 | 8 | 55 | 31.5 | -0.5 | 5919 |
| 2/21/2009 | 2009 | 2 | 21 | 266 | 14 | 66 | 40 | 8 | 5927 |
| 2/22/2009 | 2009 | 2 | 22 | 267 | 17 | 66 | 41.5 | 9.5 | 5936.5 |
| 2/23/2009 | 2009 | 2 | 23 | 268 | 33 | 66 | 49.5 | 17.5 | 5954 |
| 2/24/2009 | 2009 | 2 | 24 | 269 | 30 | 73 | 51.5 | 19.5 | 5973.5 |
| 2/25/2009 | 2009 | 2 | 25 | 270 | 28 | 72 | 50 | 18 | 5991.5 |
| 2/26/2009 | 2009 | 2 | 26 | 271 | 18 | 73 | 45.5 | 13.5 | 6005 |
| 2/27/2009 | 2009 | 2 | 27 | 272 | 21 | 66 | 43.5 | 11.5 | 6016.5 |
| 2/28/2009 | 2009 | 2 | 28 | 273 | 16 | 66 | 41 | 9 | 6025.5 |
| 3/1/2009 | 2009 | 3 | 1 | 274 | 17 | 76 | 46.5 | 14.5 | 6040 |
| 3/2/2009 | 2009 | 3 | 2 | 275 | 18 | 77 | 47.5 | 15.5 | 6055.5 |
| 3/3/2009 | 2009 | 3 | 3 | 276 | 25 | 82 | 53.5 | 21.5 | 6077 |
| 3/4/2009 | 2009 | 3 | 4 | 277 | 25 | 72 | 48.5 | 16.5 | 6093.5 |
| 3/5/2009 | 2009 | 3 | 5 | 278 | 29 | 65 | 47 | 15 | 6108.5 |
| 3/6/2009 | 2009 | 3 | 6 | 279 | 17 | 65 | 41 | 9 | 6117.5 |
| 3/7/2009 | 2009 | 3 | 7 | 280 | 36 | 60 | 48 | 16 | 6133.5 |
| 3/8/2009 | 2009 | 3 | 8 | 281 | 11 | 45 | 28 | -4 | 6129.5 |
| 3/9/2009 | 2009 | 3 | 9 | 282 | 27 | 61 | 44 | 12 | 6141.5 |
| 3/10/2009 | 2009 | 3 | 10 | 283 | 37 | 50 | 43.5 | 11.5 | 6153 |
| 3/11/2009 | 2009 | 3 | 11 | 284 | 18 | 51 | 34.5 | 2.5 | 6155.5 |
| 3/12/2009 | 2009 | 3 | 12 | 285 | 25 | 60 | 42.5 | 10.5 | 6166 |
| 3/13/2009 | 2009 | 3 | 13 | 286 | 27 | 60 | 43.5 | 11.5 | 6177.5 |
| 3/14/2009 | 2009 | 3 | 14 | 287 | 30 | 45 | 37.5 | 5.5 | 6183 |
| 3/15/2009 | 2009 | 3 | 15 | 288 | 25 | 45 | 35 | 3 | 6186 |
| 3/16/2009 | 2009 | 3 | 16 | 289 | 26 | 60 | 43 | 11 | 6197 |
| 3/17/2009 | 2009 | 3 | 17 | 290 | 27 | 70 | 48.5 | 16.5 | 6213.5 |
| 3/18/2009 | 2009 | 3 | 18 | 291 | 26 | 73 | 49.5 | 17.5 | 6231 |
| 3/19/2009 | 2009 | 3 | 19 | 292 | 25 | 75 | 50 | 18 | 6249 |
| 3/20/2009 | 2009 | 3 | 20 | 293 | 32 | 71 | 51.5 | 19.5 | 6268.5 |
| 3/21/2009 | 2009 | 3 | 21 | 294 | 30 | 72 | 51 | 19 | 6287.5 |
| 3/22/2009 | 2009 | 3 | 22 | 295 | 28 | 75 | 51.5 | 19.5 | 6307 |
| 3/23/2009 | 2009 | 3 | 23 | 296 | 32 | 73 | 52.5 | 20.5 | 6327.5 |
| 3/24/2009 | 2009 | 3 | 24 | 297 | 22 | 58 | 40 | 8 | 6335.5 |
| 3/25/2009 | 2009 | 3 | 25 | 298 | 19 | 60 | 39.5 | 7.5 | 6343 |
| 3/26/2009 | 2009 | 3 | 26 | 299 | 32 | 60 | 46 | 14 | 6357 |
| 3/27/2009 | 2009 | 3 | 27 | 300 | 19 | 55 | 37 | 5 | 6362 |
| 3/28/2009 | 2009 | 3 | 28 | 301 | 20 | 50 | 35 | 3 | 6365 |
| 3/29/2009 | 2009 | 3 | 29 | 302 | 26 | 67 | 46.5 | 14.5 | 6379.5 |
| 3/30/2009 | 2009 | 3 | 30 | 303 | 25 | 60 | 42.5 | 10.5 | 6390 |
| 3/31/2009 | 2009 | 3 | 31 | 304 | 19 | 63 | 41 | 9 | 6399 |
| 4/1/2009 | 2009 | 4 | 1 | 305 | 35 | 46 | 40.5 | 8.5 | 6407.5 |
| 4/2/2009 | 2009 | 4 | 2 | 306 | 17 | 55 | 36 | 4 | 6411.5 |
| 4/3/2009 | 2009 | 4 | 3 | 307 | 27 | 68 | 47.5 | 15.5 | 6427 |
| 4/4/2009 | 2009 | 4 | 4 | 308 | 26 | 66 | 46 | 14 | 6441 |
| 4/5/2009 | 2009 | 4 | 5 | 309 | 28 | 68 | 48 | 16 | 6457 |
| 4/6/2009 | 2009 | 4 | 6 | 310 | 17 | 55 | 36 | 4 | 6461 |
| 4/7/2009 | 2009 | 4 | 7 | 311 | 20 | 64 | 42 | 10 | 6471 |
| 4/8/2009 | 2009 | 4 | 8 | 312 | 33 | 78 | 55.5 | 23.5 | 6494.5 |
| 4/9/2009 | 2009 | 4 | 9 | 313 | 32 | 73 | 52.5 | 20.5 | 6515 |
| 4/10/2009 | 2009 | 4 | 10 | 314 | 34 | 70 | 52 | 20 | 6535 |
| 4/11/2009 | 2009 | 4 | 11 | 315 | 30 | 68 | 49 | 17 | 6552 |
| 4/12/2009 | 2009 | 4 | 12 | 316 | 27 | 60 | 43.5 | 11.5 | 6563.5 |
| 4/13/2009 | 2009 | 4 | 13 | 317 | 23 | 65 | 44 | 12 | 6575.5 |
| 4/14/2009 | 2009 | 4 | 14 | 318 | 35 | 70 | 52.5 | 20.5 | 6596 |
| 4/15/2009 | 2009 | 4 | 15 | 319 | 40 | 71 | 55.5 | 23.5 | 6619.5 |
| 4/16/2009 | 2009 | 4 | 16 | 320 | 20 | 62 | 41 | 9 | 6628.5 |
| 4/17/2009 | 2009 | 4 | 17 | 321 | 30 | 44 | 37 | 5 | 6633.5 |
| 4/18/2009 | 2009 | 4 | 18 | 322 | 35 | 51 | 43 | 11 | 6644.5 |
| 4/19/2009 | 2009 | 4 | 19 | 323 | 28 | 68 | 48 | 16 | 6660.5 |
| 4/20/2009 | 2009 | 4 | 20 | 324 | 27 | 73 | 50 | 18 | 6678.5 |
| 4/21/2009 | 2009 | 4 | 21 | 325 | 29 | 80 | 54.5 | 22.5 | 6701 |
| 4/22/2009 | 2009 | 4 | 22 | 326 | 32 | 81 | 56.5 | 24.5 | 6725.5 |
| 4/23/2009 | 2009 | 4 | 23 | 327 | 37 | 83 | 60 | 28 | 6753.5 |
| 4/24/2009 | 2009 | 4 | 24 | 328 | 28 | 81 | 54.5 | 22.5 | 6776 |
| 4/25/2009 | 2009 | 4 | 25 | 329 | 23 | 74 | 48.5 | 16.5 | 6792.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/26/2009 | 2009 | 4 | 26 | 330 | 26 | 76 | 51 | 19 | 6811.5 |
| 4/27/2009 | 2009 | 4 | 27 | 331 | 30 | 66 | 48 | 16 | 6827.5 |
| 4/28/2009 | 2009 | 4 | 28 | 332 | 34 | 71 | 52.5 | 20.5 | 6848 |
| 4/29/2009 | 2009 | 4 | 29 | 333 | 41 | 76 | 58.5 | 26.5 | 6874.5 |
| 4/30/2009 | 2009 | 4 | 30 | 334 | 32 | 81 | 56.5 | 24.5 | 6899 |
| 5/1/2009 | 2009 | 5 | 1 | 335 | 35 | 86 | 60.5 | 28.5 | 6927.5 |
| 5/2/2009 | 2009 | 5 | 2 | 336 | 55 | 82 | 68.5 | 36.5 | 6964 |
| 5/3/2009 | 2009 | 5 | 3 | 337 | 37 | 81 | 59 | 27 | 6991 |
| 5/4/2009 | 2009 | 5 | 4 | 338 | 54 | 80 | 67 | 35 | 7026 |
| 5/5/2009 | 2009 | 5 | 5 | 339 | 46 | 83 | 64.5 | 32.5 | 7058.5 |
| 5/6/2009 | 2009 | 5 | 6 | 340 | 46 | 84 | 65 | 33 | 7091.5 |
| 5/7/2009 | 2009 | 5 | 7 | 341 | 43 | 90 | 66.5 | 34.5 | 7126 |
| 5/8/2009 | 2009 | 5 | 8 | 342 | 50 | 89 | 69.5 | 37.5 | 7163.5 |
| 5/9/2009 | 2009 | 5 | 9 | 343 | 43 | 89 | 66 | 34 | 7197.5 |
| 5/10/2009 | 2009 | 5 | 10 | 344 | 36 | 87 | 61.5 | 29.5 | 7227 |
| 5/11/2009 | 2009 | 5 | 11 | 345 | 42 | 90 | 66 | 34 | 7261 |
| 5/12/2009 | 2009 | 5 | 12 | 346 | 45 | 88 | 66.5 | 34.5 | 7295.5 |
| 5/13/2009 | 2009 | 5 | 13 | 347 | 49 | 86 | 67.5 | 35.5 | 7331 |
| 5/14/2009 | 2009 | 5 | 14 | 348 | 50 | 88 | 69 | 37 | 7368 |
| 5/15/2009 | 2009 | 5 | 15 | 349 | 46 | 87 | 66.5 | 34.5 | 7402.5 |
| 5/16/2009 | 2009 | 5 | 16 | 350 | 53 | 89 | 71 | 39 | 7441.5 |
| 5/17/2009 | 2009 | 5 | 17 | 351 | 48 | 74 | 61 | 29 | 7470.5 |
| 5/18/2009 | 2009 | 5 | 18 | 352 | 48 | 88 | 68 | 36 | 7506.5 |
| 5/19/2009 | 2009 | 5 | 19 | 353 | 49 | 84 | 66.5 | 34.5 | 7541 |
| 5/20/2009 | 2009 | 5 | 20 | 354 | 48 | 84 | 66 | 34 | 7575 |
| 5/21/2009 | 2009 | 5 | 21 | 355 | 52 | 78 | 65 | 33 | 7608 |
| 5/22/2009 | 2009 | 5 | 22 | 356 | 49 | 75 | 62 | 30 | 7638 |
| 5/23/2009 | 2009 | 5 | 23 | 357 | 50 | 65 | 57.5 | 25.5 | 7663.5 |
| 5/24/2009 | 2009 | 5 | 24 | 358 | 47 | 64 | 55.5 | 23.5 | 7687 |
| 5/25/2009 | 2009 | 5 | 25 | 359 | 43 | 70 | 56.5 | 24.5 | 7711.5 |
| 5/26/2009 | 2009 | 5 | 26 | 360 | 38 | 73 | 55.5 | 23.5 | 7735 |
| 5/27/2009 | 2009 | 5 | 27 | 361 | 38 | 73 | 55.5 | 23.5 | 7758.5 |
| 5/28/2009 | 2009 | 5 | 28 | 362 | 38 | 73 | 55.5 | 23.5 | 7782 |
| 5/29/2009 | 2009 | 5 | 29 | 363 | 42 | 78 | 60 | 28 | 7810 |
| 5/30/2009 | 2009 | 5 | 30 | 364 | 40 | 74 | 57 | 25 | 7835 |
| 5/31/2009 | 2009 | 5 | 31 | 365 | 42 | 77 | 59.5 | 27.5 | 7862.5 |
| 6/1/2009 | 2009 | 6 | 1 | 1 | 38 | 78 | 58 | 26 | 26 |
| 6/2/2009 | 2009 | 6 | 2 | 2 | 45 | 81 | 63 | 31 | 57 |
| 6/3/2009 | 2009 | 6 | 3 | 3 | 44 | 84 | 64 | 32 | 89 |
| 6/4/2009 | 2009 | 6 | 4 | 4 | 45 | 85 | 65 | 33 | 122 |
| 6/5/2009 | 2009 | 6 | 5 | 5 | 47 | 85 | 66 | 34 | 156 |
| 6/6/2009 | 2009 | 6 | 6 | 6 | 46 | 85 | 65.5 | 33.5 | 189.5 |
| 6/7/2009 | 2009 | 6 | 7 | 7 | 38 | 84 | 61 | 29 | 218.5 |
| 6/8/2009 | 2009 | 6 | 8 | 8 | 46 | 78 | 62 | 30 | 248.5 |
| 6/9/2009 | 2009 | 6 | 9 | 9 | 42 | 78 | 60 | 28 | 276.5 |
| 6/10/2009 | 2009 | 6 | 10 | 10 | 46 | 72 | 59 | 27 | 303.5 |
| 6/11/2009 | 2009 | 6 | 11 | 11 | 46 | 75 | 60.5 | 28.5 | 332 |
| 6/12/2009 | 2009 | 6 | 12 | 12 | 45 | 74 | 59.5 | 27.5 | 359.5 |
| 6/13/2009 | 2009 | 6 | 13 | 13 | 45 | 74 | 59.5 | 27.5 | 387 |
| 6/14/2009 | 2009 | 6 | 14 | 14 | 42 | 83 | 62.5 | 30.5 | 417.5 |
| 6/15/2009 | 2009 | 6 | 15 | 15 | 45 | 84 | 64.5 | 32.5 | 450 |
| 6/16/2009 | 2009 | 6 | 16 | 16 | 44 | 84 | 64 | 32 | 482 |
| 6/17/2009 | 2009 | 6 | 17 | 17 | 44 | 88 | 66 | 34 | 516 |
| 6/18/2009 | 2009 | 6 | 18 | 18 | 42 | 85 | 63.5 | 31.5 | 547.5 |
| 6/19/2009 | 2009 | 6 | 19 | 19 | 48 | 86 | 67 | 35 | 582.5 |
| 6/20/2009 | 2009 | 6 | 20 | 20 | 40 | 91 | 65.5 | 33.5 | 616 |
| 6/21/2009 | 2009 | 6 | 21 | 21 | 47 | 90 | 68.5 | 36.5 | 652.5 |
| 6/22/2009 | 2009 | 6 | 22 | 22 | 44 | 89 | 66.5 | 34.5 | 687 |
| 6/23/2009 | 2009 | 6 | 23 | 23 | 65 | 91 | 78 | 46 | 733 |
| 6/24/2009 | 2009 | 6 | 24 | 24 | 62 | 84 | 73 | 41 | 774 |
| 6/25/2009 | 2009 | 6 | 25 | 25 | 59 | 89 | 74 | 42 | 816 |
| 6/26/2009 | 2009 | 6 | 26 | 26 | 58 | 93 | 75.5 | 43.5 | 859.5 |
| 6/27/2009 | 2009 | 6 | 27 | 27 | 59 | 90 | 74.5 | 42.5 | 902 |
| 6/28/2009 | 2009 | 6 | 28 | 28 | 57 | 87 | 72 | 40 | 942 |
| 6/29/2009 | 2009 | 6 | 29 | 29 | 50 | 82 | 66 | 34 | 976 |
| 6/30/2009 | 2009 | 6 | 30 | 30 | 53 | 88 | 70.5 | 38.5 | 1014.5 |
| 7/1/2009 | 2009 | 7 | 1 | 31 | 58 | 88 | 73 | 41 | 1055.5 |
| 7/2/2009 | 2009 | 7 | 2 | 32 | 56 | 90 | 73 | 41 | 1096.5 |
| 7/3/2009 | 2009 | 7 | 3 | 33 | 60 | 91 | 75.5 | 43.5 | 1140 |
| 7/4/2009 | 2009 | 7 | 4 | 34 | 56 | 91 | 73.5 | 41.5 | 1181.5 |
| 7/5/2009 | 2009 | 7 | 5 | 35 | 55 | 92 | 73.5 | 41.5 | 1223 |
| 7/6/2009 | 2009 | 7 | 6 | 36 | 54 | 93 | 73.5 | 41.5 | 1264.5 |
| 7/7/2009 | 2009 | 7 | 7 | 37 | 53 | 96 | 74.5 | 42.5 | 1307 |
| 7/8/2009 | 2009 | 7 | 8 | 38 | 57 | 97 | 77 | 45 | 1352 |
| 7/9/2009 | 2009 | 7 | 9 | 39 | 65 | 98 | 81.5 | 49.5 | 1401.5 |
| 7/10/2009 | 2009 | 7 | 10 | 40 | 62 | 97 | 79.5 | 47.5 | 1449 |
| 7/11/2009 | 2009 | 7 | 11 | 41 | 52 | 92 | 72 | 40 | 1489 |
| 7/12/2009 | 2009 | 7 | 12 | 42 | 58 | 95 | 76.5 | 44.5 | 1533.5 |
| 7/13/2009 | 2009 | 7 | 13 | 43 | 55 | 96 | 75.5 | 43.5 | 1577 |
| 7/14/2009 | 2009 | 7 | 14 | 44 | 68 | 97 | 82.5 | 50.5 | 1627.5 |
| 7/15/2009 | 2009 | 7 | 15 | 45 | 55 | 93 | 74 | 42 | 1669.5 |
| 7/16/2009 | 2009 | 7 | 16 | 46 | 67 | 98 | 82.5 | 50.5 | 1720 |
| 7/17/2009 | 2009 | 7 | 17 | 47 | 54 | 99 | 76.5 | 44.5 | 1764.5 |
| 7/18/2009 | 2009 | 7 | 18 | 48 | 63 | 100 | 81.5 | 49.5 | 1814 |
| 7/19/2009 | 2009 | 7 | 19 | 49 | 64 | 102 | 83 | 51 | 1865 |
| 7/20/2009 | 2009 | 7 | 20 | 50 | 68 | 98 | 83 | 51 | 1916 |
| 7/21/2009 | 2009 | 7 | 21 | 51 | 67 | 97 | 82 | 50 | 1966 |
| 7/22/2009 | 2009 | 7 | 22 | 52 | 55 | 88 | 71.5 | 39.5 | 2005.5 |
| 7/23/2009 | 2009 | 7 | 23 | 53 | 58 | 92 | 75 | 43 | 2048.5 |
| 7/24/2009 | 2009 | 7 | 24 | 54 | 55 | 92 | 73.5 | 41.5 | 2090 |
| 7/25/2009 | 2009 | 7 | 25 | 55 | 57 | 96 | 76.5 | 44.5 | 2134.5 |
| 7/26/2009 | 2009 | 7 | 26 | 56 | 62 | 97 | 79.5 | 47.5 | 2182 |
| 7/27/2009 | 2009 | 7 | 27 | 57 | 55 | 85 | 70 | 38 | 2220 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/28/2009 | 2009 | 7 | 28 | 58 | 56 | 92 | 74 | 42 | 2262 |
| 7/29/2009 | 2009 | 7 | 29 | 59 | 52 | 85 | 68.5 | 36.5 | 2298.5 |
| 7/30/2009 | 2009 | 7 | 30 | 60 | 48 | 92 | 70 | 38 | 2336.5 |
| 7/31/2009 | 2009 | 7 | 31 | 61 | 48 | 87 | 67.5 | 35.5 | 2372 |
| 8/1/2009 | 2009 | 8 | 1 | 62 | 52 | 90 | 71 | 39 | 2411 |
| 8/2/2009 | 2009 | 8 | 2 | 63 | 49 | 95 | 72 | 40 | 2451 |
| 8/3/2009 | 2009 | 8 | 3 | 64 | 59 | 96 | 77.5 | 45.5 | 2496.5 |
| 8/4/2009 | 2009 | 8 | 4 | 65 | 56 | 98 | 77 | 45 | 2541.5 |
| 8/5/2009 | 2009 | 8 | 5 | 66 | 64 | 101 | 82.5 | 50.5 | 2592 |
| 8/6/2009 | 2009 | 8 | 6 | 67 | 54 | 97 | 75.5 | 43.5 | 2635.5 |
| 8/7/2009 | 2009 | 8 | 7 | 68 | 54 | 97 | 75.5 | 43.5 | 2679 |
| 8/8/2009 | 2009 | 8 | 8 | 69 | 47 | 88 | 67.5 | 35.5 | 2714.5 |
| 8/9/2009 | 2009 | 8 | 9 | 70 | 45 | 91 | 68 | 36 | 2750.5 |
| 8/10/2009 | 2009 | 8 | 10 | 71 | 45 | 94 | 69.5 | 37.5 | 2788 |
| 8/11/2009 | 2009 | 8 | 11 | 72 | 48 | 94 | 71 | 39 | 2827 |
| 8/12/2009 | 2009 | 8 | 12 | 73 | 58 | 99 | 78.5 | 46.5 | 2873.5 |
| 8/13/2009 | 2009 | 8 | 13 | 74 | 60 | 90 | 75 | 43 | 2916.5 |
| 8/14/2009 | 2009 | 8 | 14 | 75 | 57 | 89 | 73 | 41 | 2957.5 |
| 8/15/2009 | 2009 | 8 | 15 | 76 | 55 | 79 | 67 | 35 | 2992.5 |
| 8/16/2009 | 2009 | 8 | 16 | 77 | 51 | 88 | 69.5 | 37.5 | 3030 |
| 8/17/2009 | 2009 | 8 | 17 | 78 | 47 | 87 | 67 | 35 | 3065 |
| 8/18/2009 | 2009 | 8 | 18 | 79 | 44 | 90 | 67 | 35 | 3100 |
| 8/19/2009 | 2009 | 8 | 19 | 80 | 45 | 93 | 69 | 37 | 3137 |
| 8/20/2009 | 2009 | 8 | 20 | 81 | 45 | 94 | 69.5 | 37.5 | 3174.5 |
| 8/21/2009 | 2009 | 8 | 21 | 82 | 64 | 95 | 79.5 | 47.5 | 3222 |
| 8/22/2009 | 2009 | 8 | 22 | 83 | 57 | 94 | 75.5 | 43.5 | 3265.5 |
| 8/23/2009 | 2009 | 8 | 23 | 84 | 59 | 91 | 75 | 43 | 3308.5 |
| 8/24/2009 | 2009 | 8 | 24 | 85 | 57 | 80 | 68.5 | 36.5 | 3345 |
| 8/25/2009 | 2009 | 8 | 25 | 86 | 65 | 80 | 72.5 | 40.5 | 3385.5 |
| 8/26/2009 | 2009 | 8 | 26 | 87 | 50 | 75 | 62.5 | 30.5 | 3416 |
| 8/27/2009 | 2009 | 8 | 27 | 88 | 50 | 90 | 70 | 38 | 3454 |
| 8/28/2009 | 2009 | 8 | 28 | 89 | 71 | 92 | 81.5 | 49.5 | 3503.5 |
| 8/29/2009 | 2009 | 8 | 29 | 90 | 71 | 84 | 77.5 | 45.5 | 3549 |
| 8/30/2009 | 2009 | 8 | 30 | 91 | 52 | 95 | 73.5 | 41.5 | 3590.5 |
| 8/31/2009 | 2009 | 8 | 31 | 92 | 52 | 92 | 72 | 40 | 3630.5 |
| 9/1/2009 | 2009 | 9 | 1 | 93 | 59 | 86 | 72.5 | 40.5 | 3671 |
| 9/2/2009 | 2009 | 9 | 2 | 94 | 54 | 91 | 72.5 | 40.5 | 3711.5 |
| 9/3/2009 | 2009 | 9 | 3 | 95 | 60 | 85 | 72.5 | 40.5 | 3752 |
| 9/4/2009 | 2009 | 9 | 4 | 96 | 51 | 89 | 70 | 38 | 3790 |
| 9/5/2009 | 2009 | 9 | 5 | 97 | 52 | 87 | 69.5 | 37.5 | 3827.5 |
| 9/6/2009 | 2009 | 9 | 6 | 98 | 51 | 81 | 66 | 34 | 3861.5 |
| 9/7/2009 | 2009 | 9 | 7 | 99 | 65 | 83 | 74 | 42 | 3903.5 |
| 9/8/2009 | 2009 | 9 | 8 | 100 | 59 | 83 | 71 | 39 | 3942.5 |
| 9/9/2009 | 2009 | 9 | 9 | 101 | 58 | 83 | 70.5 | 38.5 | 3981 |
| 9/10/2009 | 2009 | 9 | 10 | 102 | 56 | 78 | 67 | 35 | 4016 |
| 9/11/2009 | 2009 | 9 | 11 | 103 | 55 | 81 | 68 | 36 | 4052 |
| 9/12/2009 | 2009 | 9 | 12 | 104 | 47 | 78 | 62.5 | 30.5 | 4082.5 |
| 9/13/2009 | 2009 | 9 | 13 | 105 | 52 | 79 | 65.5 | 33.5 | 4116 |
| 9/14/2009 | 2009 | 9 | 14 | 106 | 51 | 81 | 66 | 34 | 4150 |
| 9/15/2009 | 2009 | 9 | 15 | 107 | 52 | 82 | 67 | 35 | 4185 |
| 9/16/2009 | 2009 | 9 | 16 | 108 | 53 | 85 | 69 | 37 | 4222 |
| 9/17/2009 | 2009 | 9 | 17 | 109 | 48 | 77 | 62.5 | 30.5 | 4252.5 |
| 9/18/2009 | 2009 | 9 | 18 | 110 | 44 | 65 | 54.5 | 22.5 | 4275 |
| 9/19/2009 | 2009 | 9 | 19 | 111 | 43 | 72 | 57.5 | 25.5 | 4300.5 |
| 9/20/2009 | 2009 | 9 | 20 | 112 | 41 | 80 | 60.5 | 28.5 | 4329 |
| 9/21/2009 | 2009 | 9 | 21 | 113 | 33 | 83 | 58 | 26 | 4355 |
| 9/22/2009 | 2009 | 9 | 22 | 114 | 34 | 76 | 55 | 23 | 4378 |
| 9/23/2009 | 2009 | 9 | 23 | 115 | 26 | 73 | 49.5 | 17.5 | 4395.5 |
| 9/24/2009 | 2009 | 9 | 24 | 116 | 43 | 73 | 58 | 26 | 4421.5 |
| 9/25/2009 | 2009 | 9 | 25 | 117 | 33 | 76 | 54.5 | 22.5 | 4444 |
| 9/26/2009 | 2009 | 9 | 26 | 118 | 34 | 84 | 59 | 27 | 4471 |
| 9/27/2009 | 2009 | 9 | 27 | 119 | 36 | 81 | 58.5 | 26.5 | 4497.5 |
| 9/28/2009 | 2009 | 9 | 28 | 120 | 39 | 89 | 64 | 32 | 4529.5 |
| 9/29/2009 | 2009 | 9 | 29 | 121 | 42 | 77 | 59.5 | 27.5 | 4557 |
| 9/30/2009 | 2009 | 9 | 30 | 122 | 31 | 80 | 55.5 | 23.5 | 4580.5 |
| 10/1/2009 | 2009 | 10 | 1 | 123 | 30 | 78 | 54 | 22 | 4602.5 |
| 10/2/2009 | 2009 | 10 | 2 | 124 | 24 | 70 | 47 | 15 | 4617.5 |
| 10/3/2009 | 2009 | 10 | 3 | 125 | 26 | 79 | 52.5 | 20.5 | 4638 |
| 10/4/2009 | 2009 | 10 | 4 | 126 | 41 | 77 | 59 | 27 | 4665 |
| 10/5/2009 | 2009 | 10 | 5 | 127 | 38 | 76 | 57 | 25 | 4690 |
| 10/6/2009 | 2009 | 10 | 6 | 128 | 34 | 79 | 56.5 | 24.5 | 4714.5 |
| 10/7/2009 | 2009 | 10 | 7 | 129 | 37 | 67 | 52 | 20 | 4734.5 |
| 10/8/2009 | 2009 | 10 | 8 | 130 | 36 | 77 | 56.5 | 24.5 | 4759 |
| 10/9/2009 | 2009 | 10 | 9 | 131 | 29 | 68 | 48.5 | 16.5 | 4775.5 |
| 10/10/2009 | 2009 | 10 | 10 | 132 | 26 | 76 | 51 | 19 | 4794.5 |
| 10/11/2009 | 2009 | 10 | 11 | 133 | 31 | 73 | 52 | 20 | 4814.5 |
| 10/12/2009 | 2009 | 10 | 12 | 134 | 32 | 75 | 53.5 | 21.5 | 4836 |
| 10/13/2009 | 2009 | 10 | 13 | 135 | 34 | 75 | 54.5 | 22.5 | 4858.5 |
| 10/14/2009 | 2009 | 10 | 14 | 136 | 38 | 75 | 56.5 | 24.5 | 4883 |
| 10/15/2009 | 2009 | 10 | 15 | 137 | 37 | 78 | 57.5 | 25.5 | 4908.5 |
| 10/16/2009 | 2009 | 10 | 16 | 138 | 29 | 82 | 55.5 | 23.5 | 4932 |
| 10/17/2009 | 2009 | 10 | 17 | 139 | 31 | 74 | 52.5 | 20.5 | 4952.5 |
| 10/18/2009 | 2009 | 10 | 18 | 140 | 30 | 73 | 51.5 | 19.5 | 4972 |
| 10/19/2009 | 2009 | 10 | 19 | 141 | 39 | 76 | 57.5 | 25.5 | 4997.5 |
| 10/20/2009 | 2009 | 10 | 20 | 142 | 40 | 80 | 60 | 28 | 5025.5 |
| 10/21/2009 | 2009 | 10 | 21 | 143 | 29 | 67 | 48 | 16 | 5041.5 |
| 10/22/2009 | 2009 | 10 | 22 | 144 | 27 | 67 | 47 | 15 | 5056.5 |
| 10/23/2009 | 2009 | 10 | 23 | 145 | 25 | 65 | 45 | 13 | 5069.5 |
| 10/24/2009 | 2009 | 10 | 24 | 146 | 24 | 67 | 45.5 | 13.5 | 5083 |
| 10/25/2009 | 2009 | 10 | 25 | 147 | 24 | 72 | 48 | 16 | 5099 |
| 10/26/2009 | 2009 | 10 | 26 | 148 | 19 | 66 | 42.5 | 10.5 | 5109.5 |
| 10/27/2009 | 2009 | 10 | 27 | 149 | 29 | 65 | 47 | 15 | 5124.5 |
| 10/28/2009 | 2009 | 10 | 28 | 150 | 15 | 41 | 28 | -4 | 5120.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/29/2009 | 2009 | 10 | 29 | 151 | 19 | 44 | 31.5 | -0.5 | 5120 |
| 10/30/2009 | 2009 | 10 | 30 | 152 | 13 | 43 | 28 | -4 | 5116 |
| 10/31/2009 | 2009 | 10 | 31 | 153 | 13 | 61 | 37 | 5 | 5121 |
| 11/1/2009 | 2009 | 11 | 1 | 154 | 19 | 64 | 41.5 | 9.5 | 5130.5 |
| 11/2/2009 | 2009 | 11 | 2 | 155 | 21 | 71 | 46 | 14 | 5144.5 |
| 11/3/2009 | 2009 | 11 | 3 | 156 | 21 | 73 | 47 | 15 | 5159.5 |
| 11/4/2009 | 2009 | 11 | 4 | 157 | 20 | 73 | 46.5 | 14.5 | 5174 |
| 11/5/2009 | 2009 | 11 | 5 | 158 | 20 | 78 | 49 | 17 | 5191 |
| 11/6/2009 | 2009 | 11 | 6 | 159 | 24 | 76 | 50 | 18 | 5209 |
| 11/7/2009 | 2009 | 11 | 7 | 160 | 27 | 79 | 53 | 21 | 5230 |
| 11/8/2009 | 2009 | 11 | 8 | 161 | 25 | 74 | 49.5 | 17.5 | 5247.5 |
| 11/9/2009 | 2009 | 11 | 9 | 162 | 25 | 74 | 49.5 | 17.5 | 5265 |
| 11/10/2009 | 2009 | 11 | 10 | 163 | 24 | 70 | 47 | 15 | 5280 |
| 11/11/2009 | 2009 | 11 | 11 | 164 | 26 | 70 | 48 | 16 | 5296 |
| 11/12/2009 | 2009 | 11 | 12 | 165 | 35 | 70 | 52.5 | 20.5 | 5316.5 |
| 11/13/2009 | 2009 | 11 | 13 | 166 | 28 | 60 | 44 | 12 | 5328.5 |
| 11/14/2009 | 2009 | 11 | 14 | 167 | 24 | 58 | 41 | 9 | 5337.5 |
| 11/15/2009 | 2009 | 11 | 15 | 168 | 23 | 54 | 38.5 | 6.5 | 5344 |
| 11/16/2009 | 2009 | 11 | 16 | 169 | 9 | 42 | 25.5 | -6.5 | 5337.5 |
| 11/17/2009 | 2009 | 11 | 17 | 170 | 11 | 52 | 31.5 | -0.5 | 5337 |
| 11/18/2009 | 2009 | 11 | 18 | 171 | 11 | 54 | 32.5 | 0.5 | 5337.5 |
| 11/19/2009 | 2009 | 11 | 19 | 172 | 13 | 68 | 40.5 | 8.5 | 5346 |
| 11/20/2009 | 2009 | 11 | 20 | 173 | 13 | 62 | 37.5 | 5.5 | 5351.5 |
| 11/21/2009 | 2009 | 11 | 21 | 174 | 11 | 64 | 37.5 | 5.5 | 5357 |
| 11/22/2009 | 2009 | 11 | 22 | 175 | 17 | 63 | 40 | 8 | 5365 |
| 11/23/2009 | 2009 | 11 | 23 | 176 | 22 | 65 | 43.5 | 11.5 | 5376.5 |
| 11/24/2009 | 2009 | 11 | 24 | 177 | 5 | 51 | 28 | -4 | 5372.5 |
| 11/25/2009 | 2009 | 11 | 25 | 178 | 8 | 52 | 30 | -2 | 5370.5 |
| 11/26/2009 | 2009 | 11 | 26 | 179 | 8 | 60 | 34 | 2 | 5372.5 |
| 11/27/2009 | 2009 | 11 | 27 | 180 | 9 | 63 | 36 | 4 | 5376.5 |
| 11/28/2009 | 2009 | 11 | 28 | 181 | 20 | 66 | 43 | 11 | 5387.5 |
| 11/29/2009 | 2009 | 11 | 29 | 182 | 22 | 54 | 38 | 6 | 5393.5 |
| 11/30/2009 | 2009 | 11 | 30 | 183 | 21 | 41 | 31 | -1 | 5392.5 |
| 12/1/2009 | 2009 | 12 | 1 | 184 | 12 | 47 | 29.5 | -2.5 | 5390 |
| 12/2/2009 | 2009 | 12 | 2 | 185 | 9 | 59 | 34 | 2 | 5392 |
| 12/3/2009 | 2009 | 12 | 3 | 186 | 6 | 49 | 27.5 | -4.5 | 5387.5 |
| 12/4/2009 | 2009 | 12 | 4 | 187 | -11 | 41 | 15 | -17 | 5370.5 |
| 12/5/2009 | 2009 | 12 | 5 | 188 | -6 | 48 | 21 | -11 | 5359.5 |
| 12/6/2009 | 2009 | 12 | 6 | 189 | 12 | 52 | 32 | 0 | 5359.5 |
| 12/7/2009 | 2009 | 12 | 7 | 190 | 21 | 41 | 31 | -1 | 5358.5 |
| 12/8/2009 | 2009 | 12 | 8 | 191 | 16 | 45 | 30.5 | -1.5 | 5357 |
| 12/9/2009 | 2009 | 12 | 9 | 192 | 13 | 44 | 28.5 | -3.5 | 5353.5 |
| 12/10/2009 | 2009 | 12 | 10 | 193 | 2 | 42 | 22 | -10 | 5343.5 |
| 12/11/2009 | 2009 | 12 | 11 | 194 | 9 | 40 | 24.5 | -7.5 | 5336 |
| 12/12/2009 | 2009 | 12 | 12 | 195 | 9 | 40 | 24.5 | -7.5 | 5328.5 |
| 12/13/2009 | 2009 | 12 | 13 | 196 | 30 | 50 | 40 | 8 | 5336.5 |
| 12/14/2009 | 2009 | 12 | 14 | 197 | 30 | 50 | 40 | 8 | 5344.5 |
| 12/15/2009 | 2009 | 12 | 15 | 198 | 30 | 50 | 40 | 8 | 5352.5 |
| 12/16/2009 | 2009 | 12 | 16 | 199 | 10 | 55 | 32.5 | 0.5 | 5353 |
| 12/17/2009 | 2009 | 12 | 17 | 200 | 13 | 56 | 34.5 | 2.5 | 5355.5 |
| 12/18/2009 | 2009 | 12 | 18 | 201 | 14 | 55 | 34.5 | 2.5 | 5358 |
| 12/19/2009 | 2009 | 12 | 19 | 202 | 14 | 51 | 32.5 | 0.5 | 5358.5 |
| 12/20/2009 | 2009 | 12 | 20 | 203 | 11 | 53 | 32 | 0 | 5358.5 |
| 12/21/2009 | 2009 | 12 | 21 | 204 | 14 | 59 | 36.5 | 4.5 | 5363 |
| 12/22/2009 | 2009 | 12 | 22 | 205 | 28 | 59 | 43.5 | 11.5 | 5374.5 |
| 12/23/2009 | 2009 | 12 | 23 | 206 | 28 | 59 | 43.5 | 11.5 | 5386 |
| 12/24/2009 | 2009 | 12 | 24 | 207 | 17 | 37 | 27 | -5 | 5381 |
| 12/25/2009 | 2009 | 12 | 25 | 208 | 4 | 36 | 20 | -12 | 5369 |
| 12/26/2009 | 2009 | 12 | 26 | 209 | 0 | 36 | 18 | -14 | 5355 |
| 12/27/2009 | 2009 | 12 | 27 | 210 | -1 | 32 | 15.5 | -16.5 | 5338.5 |
| 12/28/2009 | 2009 | 12 | 28 | 211 | 1 | 36 | 18.5 | -13.5 | 5325 |
| 12/29/2009 | 2009 | 12 | 29 | 212 | 4 | 37 | 20.5 | -11.5 | 5313.5 |
| 12/30/2009 | 2009 | 12 | 30 | 213 | 21 | 35 | 28 | -4 | 5309.5 |
| 12/31/2009 | 2009 | 12 | 31 | 214 | 14 | 42 | 28 | -4 | 5305.5 |
| 1/1/2010 | 2010 | 1 | 1 | 215 | 5 | 40 | 22.5 | -9.5 | 5296 |
| 1/2/2010 | 2010 | 1 | 2 | 216 | 15 | 49 | 32 | 0 | 5296 |
| 1/3/2010 | 2010 | 1 | 3 | 217 | 10 | 56 | 33 | 1 | 5297 |
| 1/4/2010 | 2010 | 1 | 4 | 218 | 8 | 49 | 28.5 | -3.5 | 5293.5 |
| 1/5/2010 | 2010 | 1 | 5 | 219 | 8 | 48 | 28 | -4 | 5289.5 |
| 1/6/2010 | 2010 | 1 | 6 | 220 | 10 | 48 | 29 | -3 | 5286.5 |
| 1/7/2010 | 2010 | 1 | 7 | 221 | 10 | 48 | 29 | -3 | 5283.5 |
| 1/8/2010 | 2010 | 1 | 8 | 222 | 5 | 46 | 25.5 | -6.5 | 5277 |
| 1/9/2010 | 2010 | 1 | 9 | 223 | 8 | 45 | 26.5 | -5.5 | 5271.5 |
| 1/10/2010 | 2010 | 1 | 10 | 224 | 8 | 54 | 31 | -1 | 5270.5 |
| 1/11/2010 | 2010 | 1 | 11 | 225 | 11 | 52 | 31.5 | -0.5 | 5270 |
| 1/12/2010 | 2010 | 1 | 12 | 226 | 7 | 56 | 31.5 | -0.5 | 5269.5 |
| 1/13/2010 | 2010 | 1 | 13 | 227 | 10 | 49 | 29.5 | -2.5 | 5267 |
| 1/14/2010 | 2010 | 1 | 14 | 228 | 18 | 48 | 33 | 1 | 5268 |
| 1/15/2010 | 2010 | 1 | 15 | 229 | 15 | 52 | 33.5 | 1.5 | 5269.5 |
| 1/16/2010 | 2010 | 1 | 16 | 230 | 15 | 52 | 33.5 | 1.5 | 5271 |
| 1/17/2010 | 2010 | 1 | 17 | 231 | 11 | 52 | 31.5 | -0.5 | 5270.5 |
| 1/18/2010 | 2010 | 1 | 18 | 232 | 11 | 52 | 31.5 | -0.5 | 5270 |
| 1/19/2010 | 2010 | 1 | 19 | 233 | 11 | 52 | 31.5 | -0.5 | 5269.5 |
| 1/20/2010 | 2010 | 1 | 20 | 234 | 11 | 52 | 31.5 | -0.5 | 5269 |
| 1/21/2010 | 2010 | 1 | 21 | 235 | 11 | 52 | 31.5 | -0.5 | 5268.5 |
| 1/22/2010 | 2010 | 1 | 22 | 236 | 26 | 41 | 33.5 | 1.5 | 5270 |
| 1/23/2010 | 2010 | 1 | 23 | 237 | 15 | 38 | 26.5 | -5.5 | 5264.5 |
| 1/24/2010 | 2010 | 1 | 24 | 238 | 10 | 34 | 22 | -10 | 5254.5 |
| 1/25/2010 | 2010 | 1 | 25 | 239 | 9 | 39 | 24 | -8 | 5246.5 |
| 1/26/2010 | 2010 | 1 | 26 | 240 | 13 | 47 | 30 | -2 | 5244.5 |
| 1/27/2010 | 2010 | 1 | 27 | 241 | 10 | 40 | 25 | -7 | 5237.5 |
| 1/28/2010 | 2010 | 1 | 28 | 242 | 16 | 35 | 25.5 | -6.5 | 5231 |
| 1/29/2010 | 2010 | 1 | 29 | 243 | 24 | 36 | 30 | -2 | 5229 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/30/2010 | 2010 | 1 | 30 | 244 | 28 | 48 | 38 | 6 | 5235 |
| 1/31/2010 | 2010 | 1 | 31 | 245 | 20 | 43 | 31.5 | -0.5 | 5234.5 |
| 2/1/2010 | 2010 | 2 | 1 | 246 | 20 | 57 | 38.5 | 6.5 | 5241 |
| 2/2/2010 | 2010 | 2 | 2 | 247 | 24 | 48 | 36 | 4 | 5245 |
| 2/3/2010 | 2010 | 2 | 3 | 248 | 21 | 47 | 34 | 2 | 5247 |
| 2/4/2010 | 2010 | 2 | 4 | 249 | 23 | 46 | 34.5 | 2.5 | 5249.5 |
| 2/5/2010 | 2010 | 2 | 5 | 250 | 22 | 52 | 37 | 5 | 5254.5 |
| 2/6/2010 | 2010 | 2 | 6 | 251 | 24 | 52 | 38 | 6 | 5260.5 |
| 2/7/2010 | 2010 | 2 | 7 | 252 | 27 | 57 | 42 | 10 | 5270.5 |
| 2/8/2010 | 2010 | 2 | 8 | 253 | 20 | 50 | 35 | 3 | 5273.5 |
| 2/9/2010 | 2010 | 2 | 9 | 254 | 26 | 40 | 33 | 1 | 5274.5 |
| 2/10/2010 | 2010 | 2 | 10 | 255 | 18 | 48 | 33 | 1 | 5275.5 |
| 2/11/2010 | 2010 | 2 | 11 | 256 | 15 | 52 | 33.5 | 1.5 | 5277 |
| 2/12/2010 | 2010 | 2 | 12 | 257 | 18 | 50 | 34 | 2 | 5279 |
| 2/13/2010 | 2010 | 2 | 13 | 258 | 17 | 54 | 35.5 | 3.5 | 5282.5 |
| 2/14/2010 | 2010 | 2 | 14 | 259 | 18 | 52 | 35 | 3 | 5285.5 |
| 2/15/2010 | 2010 | 2 | 15 | 260 | 12 | 56 | 34 | 2 | 5287.5 |
| 2/16/2010 | 2010 | 2 | 16 | 261 | 15 | 55 | 35 | 3 | 5290.5 |
| 2/17/2010 | 2010 | 2 | 17 | 262 | 15 | 58 | 36.5 | 4.5 | 5295 |
| 2/18/2010 | 2010 | 2 | 18 | 263 | 24 | 58 | 41 | 9 | 5304 |
| 2/19/2010 | 2010 | 2 | 19 | 264 | 26 | 60 | 43 | 11 | 5315 |
| 2/20/2010 | 2010 | 2 | 20 | 265 | 23 | 55 | 39 | 7 | 5322 |
| 2/21/2010 | 2010 | 2 | 21 | 266 | 31 | 48 | 39.5 | 7.5 | 5329.5 |
| 2/22/2010 | 2010 | 2 | 22 | 267 | 29 | 50 | 39.5 | 7.5 | 5337 |
| 2/23/2010 | 2010 | 2 | 23 | 268 | 0 | 29 | 14.5 | -17.5 | 5319.5 |
| 2/24/2010 | 2010 | 2 | 24 | 269 | 8 | 40 | 24 | -8 | 5311.5 |
| 2/25/2010 | 2010 | 2 | 25 | 270 | 28 | 42 | 35 | 3 | 5314.5 |
| 2/26/2010 | 2010 | 2 | 26 | 271 | 18 | 53 | 35.5 | 3.5 | 5318 |
| 2/27/2010 | 2010 | 2 | 27 | 272 | 21 | 48 | 34.5 | 2.5 | 5320.5 |
| 2/28/2010 | 2010 | 2 | 28 | 273 | 28 | 45 | 36.5 | 4.5 | 5325 |
| 3/1/2010 | 2010 | 3 | 1 | 274 | 22 | 52 | 37 | 5 | 5330 |
| 3/2/2010 | 2010 | 3 | 2 | 275 | 20 | 55 | 37.5 | 5.5 | 5335.5 |
| 3/3/2010 | 2010 | 3 | 3 | 276 | 18 | 58 | 38 | 6 | 5341.5 |
| 3/4/2010 | 2010 | 3 | 4 | 277 | 18 | 61 | 39.5 | 7.5 | 5349 |
| 3/5/2010 | 2010 | 3 | 5 | 278 | 25 | 62 | 43.5 | 11.5 | 5360.5 |
| 3/6/2010 | 2010 | 3 | 6 | 279 | 18 | 61 | 39.5 | 7.5 | 5368 |
| 3/7/2010 | 2010 | 3 | 7 | 280 | 34 | 60 | 47 | 15 | 5383 |
| 3/8/2010 | 2010 | 3 | 8 | 281 | 28 | 65 | 46.5 | 14.5 | 5397.5 |
| 3/9/2010 | 2010 | 3 | 9 | 282 | 25 | 65 | 45 | 13 | 5410.5 |
| 3/10/2010 | 2010 | 3 | 10 | 283 | 22 | 55 | 38.5 | 6.5 | 5417 |
| 3/11/2010 | 2010 | 3 | 11 | 284 | 19 | 50 | 34.5 | 2.5 | 5419.5 |
| 3/12/2010 | 2010 | 3 | 12 | 285 | 17 | 51 | 34 | 2 | 5421.5 |
| 3/13/2010 | 2010 | 3 | 13 | 286 | 19 | 56 | 37.5 | 5.5 | 5427 |
| 3/14/2010 | 2010 | 3 | 14 | 287 | 26 | 62 | 44 | 12 | 5439 |
| 3/15/2010 | 2010 | 3 | 15 | 288 | 19 | 55 | 37 | 5 | 5444 |
| 3/16/2010 | 2010 | 3 | 16 | 289 | 18 | 57 | 37.5 | 5.5 | 5449.5 |
| 3/17/2010 | 2010 | 3 | 17 | 290 | 19 | 58 | 38.5 | 6.5 | 5456 |
| 3/18/2010 | 2010 | 3 | 18 | 291 | 24 | 60 | 42 | 10 | 5466 |
| 3/19/2010 | 2010 | 3 | 19 | 292 | 40 | 70 | 55 | 23 | 5489 |
| 3/20/2010 | 2010 | 3 | 20 | 293 | 20 | 59 | 39.5 | 7.5 | 5496.5 |
| 3/21/2010 | 2010 | 3 | 21 | 294 | 12 | 52 | 32 | 0 | 5496.5 |
| 3/22/2010 | 2010 | 3 | 22 | 295 | 19 | 71 | 45 | 13 | 5509.5 |
| 3/23/2010 | 2010 | 3 | 23 | 296 | 20 | 53 | 36.5 | 4.5 | 5514 |
| 3/24/2010 | 2010 | 3 | 24 | 297 | 11 | 54 | 32.5 | 0.5 | 5514.5 |
| 3/25/2010 | 2010 | 3 | 25 | 298 | 12 | 64 | 38 | 6 | 5520.5 |
| 3/26/2010 | 2010 | 3 | 26 | 299 | 12 | 57 | 34.5 | 2.5 | 5523 |
| 3/27/2010 | 2010 | 3 | 27 | 300 | 17 | 55 | 36 | 4 | 5527 |
| 3/28/2010 | 2010 | 3 | 28 | 301 | 17 | 55 | 36 | 4 | 5531 |
| 3/29/2010 | 2010 | 3 | 29 | 302 | 15 | 60 | 37.5 | 5.5 | 5536.5 |
| 3/30/2010 | 2010 | 3 | 30 | 303 | 25 | 75 | 50 | 18 | 5554.5 |
| 3/31/2010 | 2010 | 3 | 31 | 304 | 21 | 78 | 49.5 | 17.5 | 5572 |
| 4/1/2010 | 2010 | 4 | 1 | 305 | 33 | 71 | 52 | 20 | 5592 |
| 4/2/2010 | 2010 | 4 | 2 | 306 | 16 | 50 | 33 | 1 | 5593 |
| 4/3/2010 | 2010 | 4 | 3 | 307 | 25 | 50 | 37.5 | 5.5 | 5598.5 |
| 4/4/2010 | 2010 | 4 | 4 | 308 | 32 | 69 | 50.5 | 18.5 | 5617 |
| 4/5/2010 | 2010 | 4 | 5 | 309 | 28 | 72 | 50 | 18 | 5635 |
| 4/6/2010 | 2010 | 4 | 6 | 310 | 23 | 55 | 39 | 7 | 5642 |
| 4/7/2010 | 2010 | 4 | 7 | 311 | 17 | 57 | 37 | 5 | 5647 |
| 4/8/2010 | 2010 | 4 | 8 | 312 | 15 | 55 | 35 | 3 | 5650 |
| 4/9/2010 | 2010 | 4 | 9 | 313 | 20 | 71 | 45.5 | 13.5 | 5663.5 |
| 4/10/2010 | 2010 | 4 | 10 | 314 | 24 | 75 | 49.5 | 17.5 | 5681 |
| 4/11/2010 | 2010 | 4 | 11 | 315 | 27 | 74 | 50.5 | 18.5 | 5699.5 |
| 4/12/2010 | 2010 | 4 | 12 | 316 | 28 | 60 | 44 | 12 | 5711.5 |
| 4/13/2010 | 2010 | 4 | 13 | 317 | 25 | 67 | 46 | 14 | 5725.5 |
| 4/14/2010 | 2010 | 4 | 14 | 318 | 23 | 69 | 46 | 14 | 5739.5 |
| 4/15/2010 | 2010 | 4 | 15 | 319 | 17 | 75 | 46 | 14 | 5753.5 |
| 4/16/2010 | 2010 | 4 | 16 | 320 | 37 | 79 | 58 | 26 | 5779.5 |
| 4/17/2010 | 2010 | 4 | 17 | 321 | 37 | 75 | 56 | 24 | 5803.5 |
| 4/18/2010 | 2010 | 4 | 18 | 322 | 31 | 69 | 50 | 18 | 5821.5 |
| 4/19/2010 | 2010 | 4 | 19 | 323 | 35 | 71 | 53 | 21 | 5842.5 |
| 4/20/2010 | 2010 | 4 | 20 | 324 | 43 | 71 | 57 | 25 | 5867.5 |
| 4/21/2010 | 2010 | 4 | 21 | 325 | 32 | 71 | 51.5 | 19.5 | 5887 |
| 4/22/2010 | 2010 | 4 | 22 | 326 | 21 | 41 | 31 | -1 | 5886 |
| 4/23/2010 | 2010 | 4 | 23 | 327 | 29 | 71 | 50 | 18 | 5904 |
| 4/24/2010 | 2010 | 4 | 24 | 328 | 26 | 67 | 46.5 | 14.5 | 5918.5 |
| 4/25/2010 | 2010 | 4 | 25 | 329 | 29 | 70 | 49.5 | 17.5 | 5936 |
| 4/26/2010 | 2010 | 4 | 26 | 330 | 36 | 71 | 53.5 | 21.5 | 5957.5 |
| 4/27/2010 | 2010 | 4 | 27 | 331 | 27 | 77 | 52 | 20 | 5977.5 |
| 4/28/2010 | 2010 | 4 | 28 | 332 | 29 | 79 | 54 | 22 | 5999.5 |
| 4/29/2010 | 2010 | 4 | 29 | 333 | 47 | 75 | 61 | 29 | 6028.5 |
| 4/30/2010 | 2010 | 4 | 30 | 334 | 27 | 62 | 44.5 | 12.5 | 6041 |
| 5/1/2010 | 2010 | 5 | 1 | 335 | 22 | 53 | 37.5 | 5.5 | 6046.5 |
| 5/2/2010 | 2010 | 5 | 2 | 336 | 30 | 61 | 45.5 | 13.5 | 6060 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/3/2010 | 2010 | 5 | 3 | 337 | 27 | 47 | 37 | 5 | 6065 |
| 5/4/2010 | 2010 | 5 | 4 | 338 | 29 | 71 | 50 | 18 | 6083 |
| 5/5/2010 | 2010 | 5 | 5 | 339 | 36 | 80 | 58 | 26 | 6109 |
| 5/6/2010 | 2010 | 5 | 6 | 340 | 38 | 81 | 59.5 | 27.5 | 6136.5 |
| 5/7/2010 | 2010 | 5 | 7 | 341 | 39 | 81 | 60 | 28 | 6164.5 |
| 5/8/2010 | 2010 | 5 | 8 | 342 | 36 | 80 | 58 | 26 | 6190.5 |
| 5/9/2010 | 2010 | 5 | 9 | 343 | 41 | 75 | 58 | 26 | 6216.5 |
| 5/10/2010 | 2010 | 5 | 10 | 344 | 40 | 77 | 58.5 | 26.5 | 6243 |
| 5/11/2010 | 2010 | 5 | 11 | 345 | 35 | 73 | 54 | 22 | 6265 |
| 5/12/2010 | 2010 | 5 | 12 | 346 | 23 | 77 | 50 | 18 | 6283 |
| 5/13/2010 | 2010 | 5 | 13 | 347 | 30 | 68 | 49 | 17 | 6300 |
| 5/14/2010 | 2010 | 5 | 14 | 348 | 41 | 72 | 56.5 | 24.5 | 6324.5 |
| 5/15/2010 | 2010 | 5 | 15 | 349 | 37 | 76 | 56.5 | 24.5 | 6349 |
| 5/16/2010 | 2010 | 5 | 16 | 350 | 33 | 79 | 56 | 24 | 6373 |
| 5/17/2010 | 2010 | 5 | 17 | 351 | 35 | 80 | 57.5 | 25.5 | 6398.5 |
| 5/18/2010 | 2010 | 5 | 18 | 352 | 47 | 83 | 65 | 33 | 6431.5 |
| 5/19/2010 | 2010 | 5 | 19 | 353 | 42 | 74 | 58 | 26 | 6457.5 |
| 5/20/2010 | 2010 | 5 | 20 | 354 | 32 | 78 | 55 | 23 | 6480.5 |
| 5/21/2010 | 2010 | 5 | 21 | 355 | 37 | 87 | 62 | 30 | 6510.5 |
| 5/22/2010 | 2010 | 5 | 22 | 356 | 39 | 86 | 62.5 | 30.5 | 6541 |
| 5/23/2010 | 2010 | 5 | 23 | 357 | 43 | 87 | 65 | 33 | 6574 |
| 5/24/2010 | 2010 | 5 | 24 | 358 | 40 | 82 | 61 | 29 | 6603 |
| 5/25/2010 | 2010 | 5 | 25 | 359 | 37 | 85 | 61 | 29 | 6632 |
| 5/26/2010 | 2010 | 5 | 26 | 360 | 35 | 87 | 61 | 29 | 6661 |
| 5/27/2010 | 2010 | 5 | 27 | 361 | 37 | 88 | 62.5 | 30.5 | 6691.5 |
| 5/28/2010 | 2010 | 5 | 28 | 362 | 51 | 90 | 70.5 | 38.5 | 6730 |
| 5/29/2010 | 2010 | 5 | 29 | 363 | 41 | 81 | 61 | 29 | 6759 |
| 5/30/2010 | 2010 | 5 | 30 | 364 | 39 | 86 | 62.5 | 30.5 | 6789.5 |
| 5/31/2010 | 2010 | 5 | 31 | 365 | 37 | 87 | 62 | 30 | 6819.5 |
| 6/1/2010 | 2010 | 6 | 1 | 1 | 41 | 88 | 64.5 | 32.5 | 32.5 |
| 6/2/2010 | 2010 | 6 | 2 | 2 | 56 | 88 | 72 | 40 | 72.5 |
| 6/3/2010 | 2010 | 6 | 3 | 3 | 41 | 88 | 64.5 | 32.5 | 105 |
| 6/4/2010 | 2010 | 6 | 4 | 4 | 45 | 91 | 68 | 36 | 141 |
| 6/5/2010 | 2010 | 6 | 5 | 5 | 54 | 97 | 75.5 | 43.5 | 184.5 |
| 6/6/2010 | 2010 | 6 | 6 | 6 | 52 | 101 | 76.5 | 44.5 | 229 |
| 6/7/2010 | 2010 | 6 | 7 | 7 | 65 | 102 | 83.5 | 51.5 | 280.5 |
| 6/8/2010 | 2010 | 6 | 8 | 8 | 51 | 98 | 74.5 | 42.5 | 323 |
| 6/9/2010 | 2010 | 6 | 9 | 9 | 54 | 100 | 77 | 45 | 368 |
| 6/10/2010 | 2010 | 6 | 10 | 10 | 55 | 96 | 75.5 | 43.5 | 411.5 |
| 6/11/2010 | 2010 | 6 | 11 | 11 | 50 | 90 | 70 | 38 | 449.5 |
| 6/12/2010 | 2010 | 6 | 12 | 12 | 52 | 88 | 70 | 38 | 487.5 |
| 6/13/2010 | 2010 | 6 | 13 | 13 | 42 | 83 | 62.5 | 30.5 | 518 |
| 6/14/2010 | 2010 | 6 | 14 | 14 | 41 | 79 | 60 | 28 | 546 |
| 6/15/2010 | 2010 | 6 | 15 | 15 | 43 | 84 | 63.5 | 31.5 | 577.5 |
| 6/16/2010 | 2010 | 6 | 16 | 16 | 45 | 87 | 66 | 34 | 611.5 |
| 6/17/2010 | 2010 | 6 | 17 | 17 | 47 | 90 | 68.5 | 36.5 | 648 |
| 6/18/2010 | 2010 | 6 | 18 | 18 | 43 | 93 | 68 | 36 | 684 |
| 6/19/2010 | 2010 | 6 | 19 | 19 | 46 | 96 | 71 | 39 | 723 |
| 6/20/2010 | 2010 | 6 | 20 | 20 | 44 | 95 | 69.5 | 37.5 | 760.5 |
| 6/21/2010 | 2010 | 6 | 21 | 21 | 47 | 94 | 70.5 | 38.5 | 799 |
| 6/22/2010 | 2010 | 6 | 22 | 22 | 50 | 94 | 72 | 40 | 839 |
| 6/23/2010 | 2010 | 6 | 23 | 23 | 43 | 94 | 68.5 | 36.5 | 875.5 |
| 6/24/2010 | 2010 | 6 | 24 | 24 | 60 | 98 | 79 | 47 | 922.5 |
| 6/25/2010 | 2010 | 6 | 25 | 25 | 64 | 93 | 78.5 | 46.5 | 969 |
| 6/26/2010 | 2010 | 6 | 26 | 26 | 51 | 95 | 73 | 41 | 1010 |
| 6/27/2010 | 2010 | 6 | 27 | 27 | 45 | 91 | 68 | 36 | 1046 |
| 6/28/2010 | 2010 | 6 | 28 | 28 | 54 | 94 | 74 | 42 | 1088 |
| 6/29/2010 | 2010 | 6 | 29 | 29 | 53 | 85 | 69 | 37 | 1125 |
| 6/30/2010 | 2010 | 6 | 30 | 30 | 58 | 85 | 71.5 | 39.5 | 1164.5 |
| 7/1/2010 | 2010 | 7 | 1 | 31 | 58 | 84 | 71 | 39 | 1203.5 |
| 7/2/2010 | 2010 | 7 | 2 | 32 | 58 | 84 | 71 | 39 | 1242.5 |
| 7/3/2010 | 2010 | 7 | 3 | 33 | 56 | 86 | 71 | 39 | 1281.5 |
| 7/4/2010 | 2010 | 7 | 4 | 34 | 54 | 92 | 73 | 41 | 1322.5 |
| 7/5/2010 | 2010 | 7 | 5 | 35 | 52 | 89 | 70.5 | 38.5 | 1361 |
| 7/6/2010 | 2010 | 7 | 6 | 36 | 44 | 91 | 67.5 | 35.5 | 1396.5 |
| 7/7/2010 | 2010 | 7 | 7 | 37 | 50 | 93 | 71.5 | 39.5 | 1436 |
| 7/8/2010 | 2010 | 7 | 8 | 38 | 60 | 90 | 75 | 43 | 1479 |
| 7/9/2010 | 2010 | 7 | 9 | 39 | 60 | 89 | 74.5 | 42.5 | 1521.5 |
| 7/10/2010 | 2010 | 7 | 10 | 40 | 62 | 90 | 76 | 44 | 1565.5 |
| 7/11/2010 | 2010 | 7 | 11 | 41 | 60 | 93 | 76.5 | 44.5 | 1610 |
| 7/12/2010 | 2010 | 7 | 12 | 42 | 51 | 89 | 70 | 38 | 1648 |
| 7/13/2010 | 2010 | 7 | 13 | 43 | 58 | 96 | 77 | 45 | 1693 |
| 7/14/2010 | 2010 | 7 | 14 | 44 | 63 | 96 | 79.5 | 47.5 | 1740.5 |
| 7/15/2010 | 2010 | 7 | 15 | 45 | 63 | 97 | 80 | 48 | 1788.5 |
| 7/16/2010 | 2010 | 7 | 16 | 46 | 61 | 99 | 80 | 48 | 1836.5 |
| 7/17/2010 | 2010 | 7 | 17 | 47 | 62 | 96 | 79 | 47 | 1883.5 |
| 7/18/2010 | 2010 | 7 | 18 | 48 | 57 | 95 | 76 | 44 | 1927.5 |
| 7/19/2010 | 2010 | 7 | 19 | 49 | 62 | 102 | 82 | 50 | 1977.5 |
| 7/20/2010 | 2010 | 7 | 20 | 50 | 62 | 99 | 80.5 | 48.5 | 2026 |
| 7/21/2010 | 2010 | 7 | 21 | 51 | 62 | 100 | 81 | 49 | 2075 |
| 7/22/2010 | 2010 | 7 | 22 | 52 | 64 | 92 | 78 | 46 | 2121 |
| 7/23/2010 | 2010 | 7 | 23 | 53 | 57 | 89 | 73 | 41 | 2162 |
| 7/24/2010 | 2010 | 7 | 24 | 54 | 57 | 85 | 71 | 39 | 2201 |
| 7/25/2010 | 2010 | 7 | 25 | 55 | 60 | 83 | 71.5 | 39.5 | 2240.5 |
| 7/26/2010 | 2010 | 7 | 26 | 56 | 56 | 81 | 68.5 | 36.5 | 2277 |
| 7/27/2010 | 2010 | 7 | 27 | 57 | 56 | 75 | 65.5 | 33.5 | 2310.5 |
| 7/28/2010 | 2010 | 7 | 28 | 58 | 56 | 88 | 72 | 40 | 2350.5 |
| 7/29/2010 | 2010 | 7 | 29 | 59 | 58 | 90 | 74 | 42 | 2392.5 |
| 7/30/2010 | 2010 | 7 | 30 | 60 | 59 | 90 | 74.5 | 42.5 | 2435 |
| 7/31/2010 | 2010 | 7 | 31 | 61 | 56 | 89 | 72.5 | 40.5 | 2475.5 |
| 8/1/2010 | 2010 | 8 | 1 | 62 | 57 | 85 | 71 | 39 | 2514.5 |
| 8/2/2010 | 2010 | 8 | 2 | 63 | 58 | 85 | 71.5 | 39.5 | 2554 |
| 8/3/2010 | 2010 | 8 | 3 | 64 | 53 | 85 | 69 | 37 | 2591 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/4/2010 | 2010 | 8 | 4 | 65 | 54 | 84 | 69 | 37 | 2628 |
| 8/5/2010 | 2010 | 8 | 5 | 66 | 54 | 91 | 72.5 | 40.5 | 2668.5 |
| 8/6/2010 | 2010 | 8 | 6 | 67 | 52 | 82 | 67 | 35 | 2703.5 |
| 8/7/2010 | 2010 | 8 | 7 | 68 | 54 | 90 | 72 | 40 | 2743.5 |
| 8/8/2010 | 2010 | 8 | 8 | 69 | 52 | 84 | 68 | 36 | 2779.5 |
| 8/9/2010 | 2010 | 8 | 9 | 70 | 51 | 80 | 65.5 | 33.5 | 2813 |
| 8/10/2010 | 2010 | 8 | 10 | 71 | 51 | 84 | 67.5 | 35.5 | 2848.5 |
| 8/11/2010 | 2010 | 8 | 11 | 72 | 51 | 90 | 70.5 | 38.5 | 2887 |
| 8/12/2010 | 2010 | 8 | 12 | 73 | 51 | 90 | 70.5 | 38.5 | 2925.5 |
| 8/13/2010 | 2010 | 8 | 13 | 74 | 54 | 92 | 73 | 41 | 2966.5 |
| 8/14/2010 | 2010 | 8 | 14 | 75 | 51 | 91 | 71 | 39 | 3005.5 |
| 8/15/2010 | 2010 | 8 | 15 | 76 | 51 | 95 | 73 | 41 | 3046.5 |
| 8/16/2010 | 2010 | 8 | 16 | 77 | 55 | 92 | 73.5 | 41.5 | 3088 |
| 8/17/2010 | 2010 | 8 | 17 | 78 | 55 | 78 | 66.5 | 34.5 | 3122.5 |
| 8/18/2010 | 2010 | 8 | 18 | 79 | 55 | 78 | 66.5 | 34.5 | 3157 |
| 8/19/2010 | 2010 | 8 | 19 | 80 | 55 | 79 | 67 | 35 | 3192 |
| 8/20/2010 | 2010 | 8 | 20 | 81 | 52 | 92 | 72 | 40 | 3232 |
| 8/21/2010 | 2010 | 8 | 21 | 82 | 48 | 92 | 70 | 38 | 3270 |
| 8/22/2010 | 2010 | 8 | 22 | 83 | 48 | 89 | 68.5 | 36.5 | 3306.5 |
| 8/23/2010 | 2010 | 8 | 23 | 84 | 56 | 86 | 71 | 39 | 3345.5 |
| 8/24/2010 | 2010 | 8 | 24 | 85 | 57 | 95 | 76 | 44 | 3389.5 |
| 8/25/2010 | 2010 | 8 | 25 | 86 | 49 | 79 | 64 | 32 | 3421.5 |
| 8/26/2010 | 2010 | 8 | 26 | 87 | 45 | 82 | 63.5 | 31.5 | 3453 |
| 8/27/2010 | 2010 | 8 | 27 | 88 | 45 | 87 | 66 | 34 | 3487 |
| 8/28/2010 | 2010 | 8 | 28 | 89 | 52 | 86 | 69 | 37 | 3524 |
| 8/29/2010 | 2010 | 8 | 29 | 90 | 54 | 82 | 68 | 36 | 3560 |
| 8/30/2010 | 2010 | 8 | 30 | 91 | 50 | 85 | 67.5 | 35.5 | 3595.5 |
| 8/31/2010 | 2010 | 8 | 31 | 92 | 53 | 84 | 68.5 | 36.5 | 3632 |
| 9/1/2010 | 2010 | 9 | 1 | 93 | 45 | 89 | 67 | 35 | 3667 |
| 9/2/2010 | 2010 | 9 | 2 | 94 | 42 | 93 | 67.5 | 35.5 | 3702.5 |
| 9/3/2010 | 2010 | 9 | 3 | 95 | 55 | 95 | 75 | 43 | 3745.5 |
| 9/4/2010 | 2010 | 9 | 4 | 96 | 46 | 86 | 66 | 34 | 3779.5 |
| 9/5/2010 | 2010 | 9 | 5 | 97 | 46 | 94 | 70 | 38 | 3817.5 |
| 9/6/2010 | 2010 | 9 | 6 | 98 | 46 | 94 | 70 | 38 | 3855.5 |
| 9/7/2010 | 2010 | 9 | 7 | 99 | 46 | 94 | 70 | 38 | 3893.5 |
| 9/8/2010 | 2010 | 9 | 8 | 100 | 46 | 94 | 70 | 38 | 3931.5 |
| 9/9/2010 | 2010 | 9 | 9 | 101 | 52 | 88 | 70 | 38 | 3969.5 |
| 9/10/2010 | 2010 | 9 | 10 | 102 | 44 | 84 | 64 | 32 | 4001.5 |
| 9/11/2010 | 2010 | 9 | 11 | 103 | 37 | 83 | 60 | 28 | 4029.5 |
| 9/12/2010 | 2010 | 9 | 12 | 104 | 39 | 84 | 61.5 | 29.5 | 4059 |
| 9/13/2010 | 2010 | 9 | 13 | 105 | 50 | 88 | 69 | 37 | 4096 |
| 9/14/2010 | 2010 | 9 | 14 | 106 | 42 | 84 | 63 | 31 | 4127 |
| 9/15/2010 | 2010 | 9 | 15 | 107 | 43 | 93 | 68 | 36 | 4163 |
| 9/16/2010 | 2010 | 9 | 16 | 108 | 42 | 94 | 68 | 36 | 4199 |
| 9/17/2010 | 2010 | 9 | 17 | 109 | 43 | 88 | 65.5 | 33.5 | 4232.5 |
| 9/18/2010 | 2010 | 9 | 18 | 110 | 43 | 92 | 67.5 | 35.5 | 4268 |
| 9/19/2010 | 2010 | 9 | 19 | 111 | 43 | 93 | 68 | 36 | 4304 |
| 9/20/2010 | 2010 | 9 | 20 | 112 | 40 | 94 | 67 | 35 | 4339 |
| 9/21/2010 | 2010 | 9 | 21 | 113 | 51 | 89 | 70 | 38 | 4377 |
| 9/22/2010 | 2010 | 9 | 22 | 114 | 58 | 91 | 74.5 | 42.5 | 4419.5 |
| 9/23/2010 | 2010 | 9 | 23 | 115 | 50 | 70 | 60 | 28 | 4447.5 |
| 9/24/2010 | 2010 | 9 | 24 | 116 | 48 | 78 | 63 | 31 | 4478.5 |
| 9/25/2010 | 2010 | 9 | 25 | 117 | 42 | 83 | 62.5 | 30.5 | 4509 |
| 9/26/2010 | 2010 | 9 | 26 | 118 | 44 | 86 | 65 | 33 | 4542 |
| 9/27/2010 | 2010 | 9 | 27 | 119 | 44 | 89 | 66.5 | 34.5 | 4576.5 |
| 9/28/2010 | 2010 | 9 | 28 | 120 | 42 | 90 | 66 | 34 | 4610.5 |
| 9/29/2010 | 2010 | 9 | 29 | 121 | 42 | 94 | 68 | 36 | 4646.5 |
| 9/30/2010 | 2010 | 9 | 30 | 122 | 45 | 87 | 66 | 34 | 4680.5 |
| 10/1/2010 | 2010 | 10 | 1 | 123 | 48 | 90 | 69 | 37 | 4717.5 |
| 10/2/2010 | 2010 | 10 | 2 | 124 | 45 | 89 | 67 | 35 | 4752.5 |
| 10/3/2010 | 2010 | 10 | 3 | 125 | 46 | 83 | 64.5 | 32.5 | 4785 |
| 10/4/2010 | 2010 | 10 | 4 | 126 | 42 | 78 | 60 | 28 | 4813 |
| 10/5/2010 | 2010 | 10 | 5 | 127 | 47 | 83 | 65 | 33 | 4846 |
| 10/6/2010 | 2010 | 10 | 6 | 128 | 48 | 71 | 59.5 | 27.5 | 4873.5 |
| 10/7/2010 | 2010 | 10 | 7 | 129 | 44 | 74 | 59 | 27 | 4900.5 |
| 10/8/2010 | 2010 | 10 | 8 | 130 | 43 | 80 | 61.5 | 29.5 | 4930 |
| 10/9/2010 | 2010 | 10 | 9 | 131 | 34 | 78 | 56 | 24 | 4954 |
| 10/10/2010 | 2010 | 10 | 10 | 132 | 36 | 77 | 56.5 | 24.5 | 4978.5 |
| 10/11/2010 | 2010 | 10 | 11 | 133 | 33 | 74 | 53.5 | 21.5 | 5000 |
| 10/12/2010 | 2010 | 10 | 12 | 134 | 34 | 78 | 56 | 24 | 5024 |
| 10/13/2010 | 2010 | 10 | 13 | 135 | 34 | 79 | 56.5 | 24.5 | 5048.5 |
| 10/14/2010 | 2010 | 10 | 14 | 136 | 33 | 80 | 56.5 | 24.5 | 5073 |
| 10/15/2010 | 2010 | 10 | 15 | 137 | 35 | 83 | 59 | 27 | 5100 |
| 10/16/2010 | 2010 | 10 | 16 | 138 | 33 | 75 | 54 | 22 | 5122 |
| 10/17/2010 | 2010 | 10 | 17 | 139 | 33 | 80 | 56.5 | 24.5 | 5146.5 |
| 10/18/2010 | 2010 | 10 | 18 | 140 | 43 | 80 | 61.5 | 29.5 | 5176 |
| 10/19/2010 | 2010 | 10 | 19 | 141 | 47 | 74 | 60.5 | 28.5 | 5204.5 |
| 10/20/2010 | 2010 | 10 | 20 | 142 | 34 | 74 | 54 | 22 | 5226.5 |
| 10/21/2010 | 2010 | 10 | 21 | 143 | 38 | 70 | 54 | 22 | 5248.5 |
| 10/22/2010 | 2010 | 10 | 22 | 144 | 40 | 68 | 54 | 22 | 5270.5 |
| 10/23/2010 | 2010 | 10 | 23 | 145 | 37 | 66 | 51.5 | 19.5 | 5290 |
| 10/24/2010 | 2010 | 10 | 24 | 146 | 33 | 64 | 48.5 | 16.5 | 5306.5 |
| 10/25/2010 | 2010 | 10 | 25 | 147 | 24 | 60 | 42 | 10 | 5316.5 |
| 10/26/2010 | 2010 | 10 | 26 | 148 | 28 | 62 | 45 | 13 | 5329.5 |
| 10/27/2010 | 2010 | 10 | 27 | 149 | 28 | 62 | 45 | 13 | 5342.5 |
| 10/28/2010 | 2010 | 10 | 28 | 150 | 15 | 55 | 35 | 3 | 5345.5 |
| 10/29/2010 | 2010 | 10 | 29 | 151 | 24 | 84 | 54 | 22 | 5367.5 |
| 10/30/2010 | 2010 | 10 | 30 | 152 | 27 | 78 | 52.5 | 20.5 | 5388 |
| 10/31/2010 | 2010 | 10 | 31 | 153 | 29 | 77 | 53 | 21 | 5409 |
| 11/1/2010 | 2010 | 11 | 1 | 154 | 24 | 71 | 47.5 | 15.5 | 5424.5 |
| 11/2/2010 | 2010 | 11 | 2 | 155 | 22 | 72 | 47 | 15 | 5439.5 |
| 11/3/2010 | 2010 | 11 | 3 | 156 | 24 | 74 | 49 | 17 | 5456.5 |
| 11/4/2010 | 2010 | 11 | 4 | 157 | 29 | 71 | 50 | 18 | 5474.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/5/2010 | 2010 | 11 | 5 | 158 | 26 | 72 | 49 | 17 | 5491.5 |
| 11/6/2010 | 2010 | 11 | 6 | 159 | 24 | 68 | 46 | 14 | 5505.5 |
| 11/7/2010 | 2010 | 11 | 7 | 160 | 27 | 77 | 52 | 20 | 5525.5 |
| 11/8/2010 | 2010 | 11 | 8 | 161 | 22 | 73 | 47.5 | 15.5 | 5541 |
| 11/9/2010 | 2010 | 11 | 9 | 162 | 35 | 72 | 53.5 | 21.5 | 5562.5 |
| 11/10/2010 | 2010 | 11 | 10 | 163 | 12 | 55 | 33.5 | 1.5 | 5564 |
| 11/11/2010 | 2010 | 11 | 11 | 164 | 27 | 60 | 43.5 | 11.5 | 5575.5 |
| 11/12/2010 | 2010 | 11 | 12 | 165 | 13 | 50 | 31.5 | -0.5 | 5575 |
| 11/13/2010 | 2010 | 11 | 13 | 166 | 13 | 53 | 33 | 1 | 5576 |
| 11/14/2010 | 2010 | 11 | 14 | 167 | 15 | 62 | 38.5 | 6.5 | 5582.5 |
| 11/15/2010 | 2010 | 11 | 15 | 168 | 21 | 60 | 40.5 | 8.5 | 5591 |
| 11/16/2010 | 2010 | 11 | 16 | 169 | 23 | 51 | 37 | 5 | 5596 |
| 11/17/2010 | 2010 | 11 | 17 | 170 | 22 | 62 | 42 | 10 | 5606 |
| 11/18/2010 | 2010 | 11 | 18 | 171 | 10 | 63 | 36.5 | 4.5 | 5610.5 |
| 11/19/2010 | 2010 | 11 | 19 | 172 | 10 | 64 | 37 | 5 | 5615.5 |
| 11/20/2010 | 2010 | 11 | 20 | 173 | 10 | 56 | 33 | 1 | 5616.5 |
| 11/21/2010 | 2010 | 11 | 21 | 174 | 31 | 55 | 43 | 11 | 5627.5 |
| 11/22/2010 | 2010 | 11 | 22 | 175 | 32 | 56 | 44 | 12 | 5639.5 |
| 11/23/2010 | 2010 | 11 | 23 | 176 | 10 | 49 | 29.5 | -2.5 | 5637 |
| 11/24/2010 | 2010 | 11 | 24 | 177 | 35 | 57 | 46 | 14 | 5651 |
| 11/25/2010 | 2010 | 11 | 25 | 178 | 18 | 49 | 33.5 | 1.5 | 5652.5 |
| 11/26/2010 | 2010 | 11 | 26 | 179 | 8 | 36 | 22 | -10 | 5642.5 |
| 11/27/2010 | 2010 | 11 | 27 | 180 | 15 | 46 | 30.5 | -1.5 | 5641 |
| 11/28/2010 | 2010 | 11 | 28 | 181 | 22 | 56 | 39 | 7 | 5648 |
| 11/29/2010 | 2010 | 11 | 29 | 182 | 25 | 40 | 32.5 | 0.5 | 5648.5 |
| 11/30/2010 | 2010 | 11 | 30 | 183 | 13 | 32 | 22.5 | -9.5 | 5639 |
| 12/1/2010 | 2010 | 12 | 1 | 184 | 13 | 58 | 35.5 | 3.5 | 5642.5 |
| 12/2/2010 | 2010 | 12 | 2 | 185 | 13 | 62 | 37.5 | 5.5 | 5648 |
| 12/3/2010 | 2010 | 12 | 3 | 186 | 13 | 66 | 39.5 | 7.5 | 5655.5 |
| 12/4/2010 | 2010 | 12 | 4 | 187 | 13 | 69 | 41 | 9 | 5664.5 |
| 12/5/2010 | 2010 | 12 | 5 | 188 | 13 | 70 | 41.5 | 9.5 | 5674 |
| 12/6/2010 | 2010 | 12 | 6 | 189 | 20 | 66 | 43 | 11 | 5685 |
| 12/7/2010 | 2010 | 12 | 7 | 190 | 20 | 65 | 42.5 | 10.5 | 5695.5 |
| 12/8/2010 | 2010 | 12 | 8 | 191 | 12 | 60 | 36 | 4 | 5699.5 |
| 12/9/2010 | 2010 | 12 | 9 | 192 | 16 | 61 | 38.5 | 6.5 | 5706 |
| 12/10/2010 | 2010 | 12 | 10 | 193 | 15 | 66 | 40.5 | 8.5 | 5714.5 |
| 12/11/2010 | 2010 | 12 | 11 | 194 | 21 | 64 | 42.5 | 10.5 | 5725 |
| 12/12/2010 | 2010 | 12 | 12 | 195 | 12 | 57 | 34.5 | 2.5 | 5727.5 |
| 12/13/2010 | 2010 | 12 | 13 | 196 | 20 | 60 | 40 | 8 | 5735.5 |
| 12/14/2010 | 2010 | 12 | 14 | 197 | 37 | 70 | 53.5 | 21.5 | 5757 |
| 12/15/2010 | 2010 | 12 | 15 | 198 | 41 | 71 | 56 | 24 | 5781 |
| 12/16/2010 | 2010 | 12 | 16 | 199 | 41 | 71 | 56 | 24 | 5805 |
| 12/17/2010 | 2010 | 12 | 17 | 200 | 41 | 71 | 56 | 24 | 5829 |
| 12/18/2010 | 2010 | 12 | 18 | 201 | 34 | 43 | 38.5 | 6.5 | 5835.5 |
| 12/19/2010 | 2010 | 12 | 19 | 202 | 39 | 52 | 45.5 | 13.5 | 5849 |
| 12/20/2010 | 2010 | 12 | 20 | 203 | 35 | 55 | 45 | 13 | 5862 |
| 12/21/2010 | 2010 | 12 | 21 | 204 | 32 | 60 | 46 | 14 | 5876 |
| 12/22/2010 | 2010 | 12 | 22 | 205 | 40 | 55 | 47.5 | 15.5 | 5891.5 |
| 12/23/2010 | 2010 | 12 | 23 | 206 | 29 | 56 | 42.5 | 10.5 | 5902 |
| 12/24/2010 | 2010 | 12 | 24 | 207 | 24 | 53 | 38.5 | 6.5 | 5908.5 |
| 12/25/2010 | 2010 | 12 | 25 | 208 | 28 | 60 | 44 | 12 | 5920.5 |
| 12/26/2010 | 2010 | 12 | 26 | 209 | 35 | 57 | 46 | 14 | 5934.5 |
| 12/27/2010 | 2010 | 12 | 27 | 210 | 24 | 56 | 40 | 8 | 5942.5 |
| 12/28/2010 | 2010 | 12 | 28 | 211 | 20 | 50 | 35 | 3 | 5945.5 |
| 12/29/2010 | 2010 | 12 | 29 | 212 | 21 | 51 | 36 | 4 | 5949.5 |
| 12/30/2010 | 2010 | 12 | 30 | 213 | 21 | 51 | 36 | 4 | 5953.5 |
| 12/31/2010 | 2010 | 12 | 31 | 214 | 4 | 26 | 15 | -17 | 5936.5 |
| 1/1/2011 | 2011 | 1 | 1 | 215 | -14 | 25 | 5.5 | -26.5 | 5910 |
| 1/2/2011 | 2011 | 1 | 2 | 216 | -9 | 28 | 9.5 | -22.5 | 5887.5 |
| 1/3/2011 | 2011 | 1 | 3 | 217 | -8 | 40 | 16 | -16 | 5871.5 |
| 1/4/2011 | 2011 | 1 | 4 | 218 | 4 | 48 | 26 | -6 | 5865.5 |
| 1/5/2011 | 2011 | 1 | 5 | 219 | 0 | 43 | 21.5 | -10.5 | 5855 |
| 1/6/2011 | 2011 | 1 | 6 | 220 | 0 | 43 | 21.5 | -10.5 | 5844.5 |
| 1/7/2011 | 2011 | 1 | 7 | 221 | 0 | 43 | 21.5 | -10.5 | 5834 |
| 1/8/2011 | 2011 | 1 | 8 | 222 | 12 | 43 | 27.5 | -4.5 | 5829.5 |
| 1/9/2011 | 2011 | 1 | 9 | 223 | 11 | 43 | 27 | -5 | 5824.5 |
| 1/10/2011 | 2011 | 1 | 10 | 224 | 17 | 47 | 32 | 0 | 5824.5 |
| 1/11/2011 | 2011 | 1 | 11 | 225 | -1 | 40 | 19.5 | -12.5 | 5812 |
| 1/12/2011 | 2011 | 1 | 12 | 226 | 7 | 43 | 25 | -7 | 5805 |
| 1/13/2011 | 2011 | 1 | 13 | 227 | 12 | 37 | 24.5 | -7.5 | 5797.5 |
| 1/14/2011 | 2011 | 1 | 14 | 228 | 17 | 53 | 35 | 3 | 5800.5 |
| 1/15/2011 | 2011 | 1 | 15 | 229 | 15 | 47 | 31 | -1 | 5799.5 |
| 1/16/2011 | 2011 | 1 | 16 | 230 | 15 | 58 | 36.5 | 4.5 | 5804 |
| 1/17/2011 | 2011 | 1 | 17 | 231 | 25 | 60 | 42.5 | 10.5 | 5814.5 |
| 1/18/2011 | 2011 | 1 | 18 | 232 | 26 | 63 | 44.5 | 12.5 | 5827 |
| 1/19/2011 | 2011 | 1 | 19 | 233 | 27 | 65 | 46 | 14 | 5841 |
| 1/20/2011 | 2011 | 1 | 20 | 234 | 24 | 61 | 42.5 | 10.5 | 5851.5 |
| 1/21/2011 | 2011 | 1 | 21 | 235 | 14 | 52 | 33 | 1 | 5852.5 |
| 1/22/2011 | 2011 | 1 | 22 | 236 | 11 | 52 | 31.5 | -0.5 | 5852 |
| 1/23/2011 | 2011 | 1 | 23 | 237 | 16 | 57 | 36.5 | 4.5 | 5856.5 |
| 1/24/2011 | 2011 | 1 | 24 | 238 | 8 | 49 | 28.5 | -3.5 | 5853 |
| 1/25/2011 | 2011 | 1 | 25 | 239 | 7 | 47 | 27 | -5 | 5848 |
| 1/26/2011 | 2011 | 1 | 26 | 240 | 11 | 52 | 31.5 | -0.5 | 5847.5 |
| 1/27/2011 | 2011 | 1 | 27 | 241 | 9 | 54 | 31.5 | -0.5 | 5847 |
| 1/28/2011 | 2011 | 1 | 28 | 242 | 8 | 56 | 32 | 0 | 5847 |
| 1/29/2011 | 2011 | 1 | 29 | 243 | 12 | 62 | 37 | 5 | 5852 |
| 1/30/2011 | 2011 | 1 | 30 | 244 | 22 | 59 | 40.5 | 8.5 | 5860.5 |
| 1/31/2011 | 2011 | 1 | 31 | 245 | 24 | 57 | 40.5 | 8.5 | 5869 |
| 2/1/2011 | 2011 | 2 | 1 | 246 | 15 | 51 | 33 | 1 | 5870 |
| 2/2/2011 | 2011 | 2 | 2 | 247 | -5 | 10 | 2.5 | -29.5 | 5840.5 |
| 2/3/2011 | 2011 | 2 | 3 | 248 | -18 | 11 | -3.5 | -35.5 | 5805 |
| 2/4/2011 | 2011 | 2 | 4 | 249 | 22 | 45 | 33.5 | 1.5 | 5806.5 |
| 2/5/2011 | 2011 | 2 | 5 | 250 | 20 | 48 | 34 | 2 | 5808.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/6/2011 | 2011 | 2 | 6 | 251 | 19 | 43 | 31 | -1 | 5807.5 |
| 2/7/2011 | 2011 | 2 | 7 | 252 | 14 | 55 | 34.5 | 2.5 | 5810 |
| 2/8/2011 | 2011 | 2 | 8 | 253 | 11 | 59 | 35 | 3 | 5813 |
| 2/9/2011 | 2011 | 2 | 9 | 254 | 22 | 61 | 41.5 | 9.5 | 5822.5 |
| 2/10/2011 | 2011 | 2 | 10 | 255 | 35 | 58 | 46.5 | 14.5 | 5837 |
| 2/11/2011 | 2011 | 2 | 11 | 256 | 39 | 70 | 54.5 | 22.5 | 5859.5 |
| 2/12/2011 | 2011 | 2 | 12 | 257 | 36 | 55 | 45.5 | 13.5 | 5873 |
| 2/13/2011 | 2011 | 2 | 13 | 258 | 39 | 48 | 43.5 | 11.5 | 5884.5 |
| 2/14/2011 | 2011 | 2 | 14 | 259 | 36 | 44 | 40 | 8 | 5892.5 |
| 2/15/2011 | 2011 | 2 | 15 | 260 | 33 | 73 | 53 | 21 | 5913.5 |
| 2/16/2011 | 2011 | 2 | 16 | 261 | 29 | 71 | 50 | 18 | 5931.5 |
| 2/17/2011 | 2011 | 2 | 17 | 262 | 32 | 66 | 49 | 17 | 5948.5 |
| 2/18/2011 | 2011 | 2 | 18 | 263 | 24 | 62 | 43 | 11 | 5959.5 |
| 2/19/2011 | 2011 | 2 | 19 | 264 | 31 | 67 | 49 | 17 | 5976.5 |
| 2/20/2011 | 2011 | 2 | 20 | 265 | 28 | 62 | 45 | 13 | 5989.5 |
| 2/21/2011 | 2011 | 2 | 21 | 266 | 28 | 61 | 44.5 | 12.5 | 6002 |
| 2/22/2011 | 2011 | 2 | 22 | 267 | 28 | 59 | 43.5 | 11.5 | 6013.5 |
| 2/23/2011 | 2011 | 2 | 23 | 268 | 13 | 61 | 37 | 5 | 6018.5 |
| 2/24/2011 | 2011 | 2 | 24 | 269 | 13 | 61 | 37 | 5 | 6023.5 |
| 2/25/2011 | 2011 | 2 | 25 | 270 | 30 | 57 | 43.5 | 11.5 | 6035 |
| 2/26/2011 | 2011 | 2 | 26 | 271 | 25 | 54 | 39.5 | 7.5 | 6042.5 |
| 2/27/2011 | 2011 | 2 | 27 | 272 | 19 | 61 | 40 | 8 | 6050.5 |
| 2/28/2011 | 2011 | 2 | 28 | 273 | 19 | 61 | 40 | 8 | 6058.5 |
| 3/1/2011 | 2011 | 3 | 1 | 274 | 17 | 51 | 34 | 2 | 6060.5 |
| 3/2/2011 | 2011 | 3 | 2 | 275 | 17 | 61 | 39 | 7 | 6067.5 |
| 3/3/2011 | 2011 | 3 | 3 | 276 | 29 | 54 | 41.5 | 9.5 | 6077 |
| 3/4/2011 | 2011 | 3 | 4 | 277 | 21 | 55 | 38 | 6 | 6083 |
| 3/5/2011 | 2011 | 3 | 5 | 278 | 16 | 61 | 38.5 | 6.5 | 6089.5 |
| 3/6/2011 | 2011 | 3 | 6 | 279 | 16 | 63 | 39.5 | 7.5 | 6097 |
| 3/7/2011 | 2011 | 3 | 7 | 280 | 26 | 56 | 41 | 9 | 6106 |
| 3/8/2011 | 2011 | 3 | 8 | 281 | 28 | 61 | 44.5 | 12.5 | 6118.5 |
| 3/9/2011 | 2011 | 3 | 9 | 282 | 17 | 61 | 39 | 7 | 6125.5 |
| 3/10/2011 | 2011 | 3 | 10 | 283 | 15 | 62 | 38.5 | 6.5 | 6132 |
| 3/11/2011 | 2011 | 3 | 11 | 284 | 21 | 73 | 47 | 15 | 6147 |
| 3/12/2011 | 2011 | 3 | 12 | 285 | 21 | 73 | 47 | 15 | 6162 |
| 3/13/2011 | 2011 | 3 | 13 | 286 | 21 | 73 | 47 | 15 | 6177 |
| 3/14/2011 | 2011 | 3 | 14 | 287 | 22 | 77 | 49.5 | 17.5 | 6194.5 |
| 3/15/2011 | 2011 | 3 | 15 | 288 | 25 | 76 | 50.5 | 18.5 | 6213 |
| 3/16/2011 | 2011 | 3 | 16 | 289 | 23 | 74 | 48.5 | 16.5 | 6229.5 |
| 3/17/2011 | 2011 | 3 | 17 | 290 | 34 | 77 | 55.5 | 23.5 | 6253 |
| 3/18/2011 | 2011 | 3 | 18 | 291 | 31 | 73 | 52 | 20 | 6273 |
| 3/19/2011 | 2011 | 3 | 19 | 292 | 34 | 73 | 53.5 | 21.5 | 6294.5 |
| 3/20/2011 | 2011 | 3 | 20 | 293 | 25 | 70 | 47.5 | 15.5 | 6310 |
| 3/21/2011 | 2011 | 3 | 21 | 294 | 28 | 71 | 49.5 | 17.5 | 6327.5 |
| 3/22/2011 | 2011 | 3 | 22 | 295 | 31 | 73 | 52 | 20 | 6347.5 |
| 3/23/2011 | 2011 | 3 | 23 | 296 | 15 | 55 | 35 | 3 | 6350.5 |
| 3/24/2011 | 2011 | 3 | 24 | 297 | 15 | 55 | 35 | 3 | 6353.5 |
| 3/25/2011 | 2011 | 3 | 25 | 298 | 17 | 67 | 42 | 10 | 6363.5 |
| 3/26/2011 | 2011 | 3 | 26 | 299 | 27 | 64 | 45.5 | 13.5 | 6377 |
| 3/27/2011 | 2011 | 3 | 27 | 300 | 35 | 70 | 52.5 | 20.5 | 6397.5 |
| 3/28/2011 | 2011 | 3 | 28 | 301 | 36 | 71 | 53.5 | 21.5 | 6419 |
| 3/29/2011 | 2011 | 3 | 29 | 302 | 31 | 72 | 51.5 | 19.5 | 6438.5 |
| 3/30/2011 | 2011 | 3 | 30 | 303 | 35 | 68 | 51.5 | 19.5 | 6458 |
| 3/31/2011 | 2011 | 3 | 31 | 304 | 24 | 70 | 47 | 15 | 6473 |
| 4/1/2011 | 2011 | 4 | 1 | 305 | 24 | 74 | 49 | 17 | 6490 |
| 4/2/2011 | 2011 | 4 | 2 | 306 | 23 | 80 | 51.5 | 19.5 | 6509.5 |
| 4/3/2011 | 2011 | 4 | 3 | 307 | 34 | 84 | 59 | 27 | 6536.5 |
| 4/4/2011 | 2011 | 4 | 4 | 308 | 21 | 72 | 46.5 | 14.5 | 6551 |
| 4/5/2011 | 2011 | 4 | 5 | 309 | 22 | 82 | 52 | 20 | 6571 |
| 4/6/2011 | 2011 | 4 | 6 | 310 | 42 | 83 | 62.5 | 30.5 | 6601.5 |
| 4/7/2011 | 2011 | 4 | 7 | 311 | 38 | 72 | 55 | 23 | 6624.5 |
| 4/8/2011 | 2011 | 4 | 8 | 312 | 37 | 66 | 51.5 | 19.5 | 6644 |
| 4/9/2011 | 2011 | 4 | 9 | 313 | 32 | 71 | 51.5 | 19.5 | 6663.5 |
| 4/10/2011 | 2011 | 4 | 10 | 314 | 20 | 61 | 40.5 | 8.5 | 6672 |
| 4/11/2011 | 2011 | 4 | 11 | 315 | 17 | 56 | 36.5 | 4.5 | 6676.5 |
| 4/12/2011 | 2011 | 4 | 12 | 316 | 33 | 76 | 54.5 | 22.5 | 6699 |
| 4/13/2011 | 2011 | 4 | 13 | 317 | 29 | 74 | 51.5 | 19.5 | 6718.5 |
| 4/14/2011 | 2011 | 4 | 14 | 318 | 36 | 71 | 53.5 | 21.5 | 6740 |
| 4/15/2011 | 2011 | 4 | 15 | 319 | 23 | 69 | 46 | 14 | 6754 |
| 4/16/2011 | 2011 | 4 | 16 | 320 | 24 | 70 | 47 | 15 | 6769 |
| 4/17/2011 | 2011 | 4 | 17 | 321 | 45 | 81 | 63 | 31 | 6800 |
| 4/20/2011 | 2011 | 4 | 20 | 322 | 40 | 79 | 59.5 | 27.5 | 6827.5 |
| 4/21/2011 | 2011 | 4 | 21 | 323 | 33 | 71 | 52 | 20 | 6847.5 |
| 4/22/2011 | 2011 | 4 | 22 | 324 | 44 | 79 | 61.5 | 29.5 | 6877 |
| 4/23/2011 | 2011 | 4 | 23 | 325 | 39 | 78 | 58.5 | 26.5 | 6903.5 |
| 4/24/2011 | 2011 | 4 | 24 | 326 | 36 | 73 | 54.5 | 22.5 | 6926 |
| 4/25/2011 | 2011 | 4 | 25 | 327 | 37 | 70 | 53.5 | 21.5 | 6947.5 |
| 4/26/2011 | 2011 | 4 | 26 | 328 | 35 | 71 | 53 | 21 | 6968.5 |
| 4/27/2011 | 2011 | 4 | 27 | 329 | 24 | 67 | 45.5 | 13.5 | 6982 |
| 4/28/2011 | 2011 | 4 | 28 | 330 | 23 | 68 | 45.5 | 13.5 | 6995.5 |
| 4/29/2011 | 2011 | 4 | 29 | 331 | 43 | 80 | 61.5 | 29.5 | 7025 |
| 4/30/2011 | 2011 | 4 | 30 | 332 | 22 | 77 | 49.5 | 17.5 | 7042.5 |
| 5/1/2011 | 2011 | 5 | 1 | 333 | 24 | 66 | 45 | 13 | 7055.5 |
| 5/2/2011 | 2011 | 5 | 2 | 334 | 23 | 53 | 38 | 6 | 7061.5 |
| 5/3/2011 | 2011 | 5 | 3 | 335 | 18 | 62 | 40 | 8 | 7069.5 |
| 5/4/2011 | 2011 | 5 | 4 | 336 | 34 | 70 | 52 | 20 | 7089.5 |
| 5/5/2011 | 2011 | 5 | 5 | 337 | 36 | 82 | 59 | 27 | 7116.5 |
| 5/6/2011 | 2011 | 5 | 6 | 338 | 31 | 85 | 58 | 26 | 7142.5 |
| 5/7/2011 | 2011 | 5 | 7 | 339 | 38 | 84 | 61 | 29 | 7171.5 |
| 5/8/2011 | 2011 | 5 | 8 | 340 | 44 | 82 | 63 | 31 | 7202.5 |
| 5/9/2011 | 2011 | 5 | 9 | 341 | 36 | 79 | 57.5 | 25.5 | 7228 |
| 5/10/2011 | 2011 | 5 | 10 | 342 | 35 | 80 | 57.5 | 25.5 | 7253.5 |
| 5/11/2011 | 2011 | 5 | 11 | 343 | 32 | 75 | 53.5 | 21.5 | 7275 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/12/2011 | 2011 | 5 | 12 | 344 | 32 | 66 | 49 | 17 | 7292 |
| 5/13/2011 | 2011 | 5 | 13 | 345 | 32 | 76 | 54 | 22 | 7314 |
| 5/14/2011 | 2011 | 5 | 14 | 346 | 46 | 84 | 65 | 33 | 7347 |
| 5/15/2011 | 2011 | 5 | 15 | 347 | 40 | 80 | 60 | 28 | 7375 |
| 5/16/2011 | 2011 | 5 | 16 | 348 | 44 | 81 | 62.5 | 30.5 | 7405.5 |
| 5/17/2011 | 2011 | 5 | 17 | 349 | 39 | 82 | 60.5 | 28.5 | 7434 |
| 5/18/2011 | 2011 | 5 | 18 | 350 | 37 | 82 | 59.5 | 27.5 | 7461.5 |
| 5/19/2011 | 2011 | 5 | 19 | 351 | 34 | 65 | 49.5 | 17.5 | 7479 |
| 5/20/2011 | 2011 | 5 | 20 | 352 | 33 | 60 | 46.5 | 14.5 | 7493.5 |
| 5/21/2011 | 2011 | 5 | 21 | 353 | 33 | 67 | 50 | 18 | 7511.5 |
| 5/22/2011 | 2011 | 5 | 22 | 354 | 35 | 81 | 58 | 26 | 7537.5 |
| 5/23/2011 | 2011 | 5 | 23 | 355 | 36 | 84 | 60 | 28 | 7565.5 |
| 5/24/2011 | 2011 | 5 | 24 | 356 | 37 | 80 | 58.5 | 26.5 | 7592 |
| 5/25/2011 | 2011 | 5 | 25 | 357 | 42 | 74 | 58 | 26 | 7618 |
| 5/26/2011 | 2011 | 5 | 26 | 358 | 41 | 82 | 61.5 | 29.5 | 7647.5 |
| 5/27/2011 | 2011 | 5 | 27 | 359 | 41 | 84 | 62.5 | 30.5 | 7678 |
| 5/28/2011 | 2011 | 5 | 28 | 360 | 41 | 90 | 65.5 | 33.5 | 7711.5 |
| 5/29/2011 | 2011 | 5 | 29 | 361 | 60 | 88 | 74 | 42 | 7753.5 |
| 5/30/2011 | 2011 | 5 | 30 | 362 | 44 | 84 | 64 | 32 | 7785.5 |
| 5/31/2011 | 2011 | 5 | 31 | 363 | 28 | 74 | 51 | 19 | 7804.5 |
| 6/1/2011 | 2011 | 6 | 1 | 1 | 51 | 85 | 68 | 36 | 36 |
| 6/2/2011 | 2011 | 6 | 2 | 2 | 39 | 87 | 63 | 31 | 67 |
| 6/3/2011 | 2011 | 6 | 3 | 3 | 42 | 93 | 67.5 | 35.5 | 102.5 |
| 6/4/2011 | 2011 | 6 | 4 | 4 | 39 | 87 | 63 | 31 | 133.5 |
| 6/5/2011 | 2011 | 6 | 5 | 5 | 41 | 92 | 66.5 | 34.5 | 168 |
| 6/6/2011 | 2011 | 6 | 6 | 6 | 55 | 90 | 72.5 | 40.5 | 208.5 |
| 6/7/2011 | 2011 | 6 | 7 | 7 | 40 | 87 | 63.5 | 31.5 | 240 |
| 6/8/2011 | 2011 | 6 | 8 | 8 | 38 | 89 | 63.5 | 31.5 | 271.5 |
| 6/9/2011 | 2011 | 6 | 9 | 9 | 39 | 88 | 63.5 | 31.5 | 303 |
| 6/10/2011 | 2011 | 6 | 10 | 10 | 39 | 88 | 63.5 | 31.5 | 334.5 |
| 6/11/2011 | 2011 | 6 | 11 | 11 | 49 | 90 | 69.5 | 37.5 | 372 |
| 6/12/2011 | 2011 | 6 | 12 | 12 | 39 | 89 | 64 | 32 | 404 |
| 6/13/2011 | 2011 | 6 | 13 | 13 | 42 | 92 | 67 | 35 | 439 |
| 6/14/2011 | 2011 | 6 | 14 | 14 | 47 | 90 | 68.5 | 36.5 | 475.5 |
| 6/15/2011 | 2011 | 6 | 15 | 15 | 43 | 89 | 66 | 34 | 509.5 |
| 6/16/2011 | 2011 | 6 | 16 | 16 | 51 | 96 | 73.5 | 41.5 | 551 |
| 6/17/2011 | 2011 | 6 | 17 | 17 | 54 | 93 | 73.5 | 41.5 | 592.5 |
| 6/18/2011 | 2011 | 6 | 18 | 18 | 43 | 89 | 66 | 34 | 626.5 |
| 6/19/2011 | 2011 | 6 | 19 | 19 | 60 | 91 | 75.5 | 43.5 | 670 |
| 6/20/2011 | 2011 | 6 | 20 | 20 | 42 | 86 | 64 | 32 | 702 |
| 6/21/2011 | 2011 | 6 | 21 | 21 | 42 | 88 | 65 | 33 | 735 |
| 6/22/2011 | 2011 | 6 | 22 | 22 | 44 | 90 | 67 | 35 | 770 |
| 6/23/2011 | 2011 | 6 | 23 | 23 | 49 | 98 | 73.5 | 41.5 | 811.5 |
| 6/24/2011 | 2011 | 6 | 24 | 24 | 59 | 100 | 79.5 | 47.5 | 859 |
| 6/25/2011 | 2011 | 6 | 25 | 25 | 58 | 99 | 78.5 | 46.5 | 905.5 |
| 6/26/2011 | 2011 | 6 | 26 | 26 | 53 | 96 | 74.5 | 42.5 | 948 |
| 6/27/2011 | 2011 | 6 | 27 | 27 | 50 | 99 | 74.5 | 42.5 | 990.5 |
| 6/28/2011 | 2011 | 6 | 28 | 28 | 52 | 97 | 74.5 | 42.5 | 1033 |
| 6/29/2011 | 2011 | 6 | 29 | 29 | 51 | 99 | 75 | 43 | 1076 |
| 6/30/2011 | 2011 | 6 | 30 | 30 | 55 | 96 | 75.5 | 43.5 | 1119.5 |
| 7/1/2011 | 2011 | 7 | 1 | 31 | 47 | 94 | 70.5 | 38.5 | 1158 |
| 7/2/2011 | 2011 | 7 | 2 | 32 | 58 | 100 | 79 | 47 | 1205 |
| 7/3/2011 | 2011 | 7 | 3 | 33 | 62 | 94 | 78 | 46 | 1251 |
| 7/4/2011 | 2011 | 7 | 4 | 34 | 65 | 95 | 80 | 48 | 1299 |
| 7/5/2011 | 2011 | 7 | 5 | 35 | 60 | 97 | 78.5 | 46.5 | 1345.5 |
| 7/6/2011 | 2011 | 7 | 6 | 36 | 56 | 94 | 75 | 43 | 1388.5 |
| 7/7/2011 | 2011 | 7 | 7 | 37 | 63 | 97 | 80 | 48 | 1436.5 |
| 7/8/2011 | 2011 | 7 | 8 | 38 | 56 | 99 | 77.5 | 45.5 | 1482 |
| 7/9/2011 | 2011 | 7 | 9 | 39 | 55 | 92 | 73.5 | 41.5 | 1523.5 |
| 7/10/2011 | 2011 | 7 | 10 | 40 | 52 | 94 | 73 | 41 | 1564.5 |
| 7/11/2011 | 2011 | 7 | 11 | 41 | 58 | 92 | 75 | 43 | 1607.5 |
| 7/12/2011 | 2011 | 7 | 12 | 42 | 52 | 90 | 71 | 39 | 1646.5 |
| 7/13/2011 | 2011 | 7 | 13 | 43 | 50 | 85 | 67.5 | 35.5 | 1682 |
| 7/14/2011 | 2011 | 7 | 14 | 44 | 52 | 92 | 72 | 40 | 1722 |
| 7/15/2011 | 2011 | 7 | 15 | 45 | 50 | 95 | 72.5 | 40.5 | 1762.5 |
| 7/16/2011 | 2011 | 7 | 16 | 46 | 54 | 95 | 74.5 | 42.5 | 1805 |
| 7/17/2011 | 2011 | 7 | 17 | 47 | 55 | 95 | 75 | 43 | 1848 |
| 7/18/2011 | 2011 | 7 | 18 | 48 | 60 | 90 | 75 | 43 | 1891 |
| 7/19/2011 | 2011 | 7 | 19 | 49 | 59 | 95 | 77 | 45 | 1936 |
| 7/20/2011 | 2011 | 7 | 20 | 50 | 57 | 97 | 77 | 45 | 1981 |
| 7/21/2011 | 2011 | 7 | 21 | 51 | 55 | 94 | 74.5 | 42.5 | 2023.5 |
| 7/22/2011 | 2011 | 7 | 22 | 52 | 57 | 81 | 69 | 37 | 2060.5 |
| 7/23/2011 | 2011 | 7 | 23 | 53 | 57 | 98 | 77.5 | 45.5 | 2106 |
| 7/24/2011 | 2011 | 7 | 24 | 54 | 60 | 99 | 79.5 | 47.5 | 2153.5 |
| 7/25/2011 | 2011 | 7 | 25 | 55 | 60 | 94 | 77 | 45 | 2198.5 |
| 7/26/2011 | 2011 | 7 | 26 | 56 | 55 | 91 | 73 | 41 | 2239.5 |
| 7/27/2011 | 2011 | 7 | 27 | 57 | 53 | 93 | 73 | 41 | 2280.5 |
| 7/28/2011 | 2011 | 7 | 28 | 58 | 53 | 93 | 73 | 41 | 2321.5 |
| 7/29/2011 | 2011 | 7 | 29 | 59 | 53 | 90 | 71.5 | 39.5 | 2361 |
| 7/30/2011 | 2011 | 7 | 30 | 60 | 53 | 90 | 71.5 | 39.5 | 2400.5 |
| 7/31/2011 | 2011 | 7 | 31 | 61 | 55 | 90 | 72.5 | 40.5 | 2441 |
| 8/1/2011 | 2011 | 8 | 1 | 62 | 54 | 90 | 72 | 40 | 2481 |
| 8/2/2011 | 2011 | 8 | 2 | 63 | 54 | 89 | 71.5 | 39.5 | 2520.5 |
| 8/3/2011 | 2011 | 8 | 3 | 64 | 57 | 93 | 75 | 43 | 2563.5 |
| 8/4/2011 | 2011 | 8 | 4 | 65 | 58 | 91 | 74.5 | 42.5 | 2606 |
| 8/5/2011 | 2011 | 8 | 5 | 66 | 58 | 93 | 75.5 | 43.5 | 2649.5 |
| 8/6/2011 | 2011 | 8 | 6 | 67 | 52 | 92 | 72 | 40 | 2689.5 |
| 8/7/2011 | 2011 | 8 | 7 | 68 | 50 | 98 | 74 | 42 | 2731.5 |
| 8/8/2011 | 2011 | 8 | 8 | 69 | 50 | 96 | 73 | 41 | 2772.5 |
| 8/9/2011 | 2011 | 8 | 9 | 70 | 47 | 97 | 72 | 40 | 2812.5 |
| 8/10/2011 | 2011 | 8 | 10 | 71 | 59 | 99 | 79 | 47 | 2859.5 |
| 8/11/2011 | 2011 | 8 | 11 | 72 | 49 | 95 | 72 | 40 | 2899.5 |
| 8/12/2011 | 2011 | 8 | 12 | 73 | 55 | 93 | 74 | 42 | 2941.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/13/2011 | 2011 | 8 | 13 | 74 | 59 | 97 | 78 | 46 | 2987.5 |
| 8/14/2011 | 2011 | 8 | 14 | 75 | 57 | 91 | 74 | 42 | 3029.5 |
| 8/15/2011 | 2011 | 8 | 15 | 76 | 56 | 89 | 72.5 | 40.5 | 3070 |
| 8/16/2011 | 2011 | 8 | 16 | 77 | 59 | 95 | 77 | 45 | 3115 |
| 8/17/2011 | 2011 | 8 | 17 | 78 | 55 | 96 | 75.5 | 43.5 | 3158.5 |
| 8/18/2011 | 2011 | 8 | 18 | 79 | 56 | 97 | 76.5 | 44.5 | 3203 |
| 8/19/2011 | 2011 | 8 | 19 | 80 | 57 | 89 | 73 | 41 | 3244 |
| 8/20/2011 | 2011 | 8 | 20 | 81 | 60 | 90 | 75 | 43 | 3287 |
| 8/21/2011 | 2011 | 8 | 21 | 82 | 56 | 89 | 72.5 | 40.5 | 3327.5 |
| 8/22/2011 | 2011 | 8 | 22 | 83 | 54 | 82 | 68 | 36 | 3363.5 |
| 8/23/2011 | 2011 | 8 | 23 | 84 | 55 | 93 | 74 | 42 | 3405.5 |
| 8/24/2011 | 2011 | 8 | 24 | 85 | 55 | 100 | 77.5 | 45.5 | 3451 |
| 8/25/2011 | 2011 | 8 | 25 | 86 | 57 | 96 | 76.5 | 44.5 | 3495.5 |
| 8/26/2011 | 2011 | 8 | 26 | 87 | 57 | 88 | 72.5 | 40.5 | 3536 |
| 8/27/2011 | 2011 | 8 | 27 | 88 | 56 | 92 | 74 | 42 | 3578 |
| 8/28/2011 | 2011 | 8 | 28 | 89 | 59 | 97 | 78 | 46 | 3624 |
| 8/29/2011 | 2011 | 8 | 29 | 90 | 57 | 95 | 76 | 44 | 3668 |
| 8/30/2011 | 2011 | 8 | 30 | 91 | 55 | 97 | 76 | 44 | 3712 |
| 8/31/2011 | 2011 | 8 | 31 | 92 | 53 | 98 | 75.5 | 43.5 | 3755.5 |
| 9/1/2011 | 2011 | 9 | 1 | 93 | 58 | 92 | 75 | 43 | 3798.5 |
| 9/2/2011 | 2011 | 9 | 2 | 94 | 52 | 87 | 69.5 | 37.5 | 3836 |
| 9/3/2011 | 2011 | 9 | 3 | 95 | 55 | 89 | 72 | 40 | 3876 |
| 9/4/2011 | 2011 | 9 | 4 | 96 | 57 | 90 | 73.5 | 41.5 | 3917.5 |
| 9/5/2011 | 2011 | 9 | 5 | 97 | 57 | 86 | 71.5 | 39.5 | 3957 |
| 9/6/2011 | 2011 | 9 | 6 | 98 | 55 | 82 | 68.5 | 36.5 | 3993.5 |
| 9/7/2011 | 2011 | 9 | 7 | 99 | 55 | 82 | 68.5 | 36.5 | 4030 |
| 9/8/2011 | 2011 | 9 | 8 | 100 | 53 | 77 | 65 | 33 | 4063 |
| 9/9/2011 | 2011 | 9 | 9 | 101 | 52 | 75 | 63.5 | 31.5 | 4094.5 |
| 9/10/2011 | 2011 | 9 | 10 | 102 | 50 | 72 | 61 | 29 | 4123.5 |
| 9/11/2011 | 2011 | 9 | 11 | 103 | 52 | 73 | 62.5 | 30.5 | 4154 |
| 9/12/2011 | 2011 | 9 | 12 | 104 | 50 | 81 | 65.5 | 33.5 | 4187.5 |
| 9/13/2011 | 2011 | 9 | 13 | 105 | 50 | 76 | 63 | 31 | 4218.5 |
| 9/14/2011 | 2011 | 9 | 14 | 106 | 53 | 84 | 68.5 | 36.5 | 4255 |
| 9/15/2011 | 2011 | 9 | 15 | 107 | 50 | 80 | 65 | 33 | 4288 |
| 9/16/2011 | 2011 | 9 | 16 | 108 | 45 | 81 | 63 | 31 | 4319 |
| 9/17/2011 | 2011 | 9 | 17 | 109 | 48 | 80 | 64 | 32 | 4351 |
| 9/18/2011 | 2011 | 9 | 18 | 110 | 43 | 81 | 62 | 30 | 4381 |
| 9/19/2011 | 2011 | 9 | 19 | 111 | 43 | 81 | 62 | 30 | 4411 |
| 9/20/2011 | 2011 | 9 | 20 | 112 | 43 | 84 | 63.5 | 31.5 | 4442.5 |
| 9/21/2011 | 2011 | 9 | 21 | 113 | 42 | 88 | 65 | 33 | 4475.5 |
| 9/22/2011 | 2011 | 9 | 22 | 114 | 38 | 83 | 60.5 | 28.5 | 4504 |
| 9/23/2011 | 2011 | 9 | 23 | 115 | 38 | 83 | 60.5 | 28.5 | 4532.5 |
| 9/24/2011 | 2011 | 9 | 24 | 116 | 35 | 90 | 62.5 | 30.5 | 4563 |
| 9/25/2011 | 2011 | 9 | 25 | 117 | 37 | 91 | 64 | 32 | 4595 |
| 9/26/2011 | 2011 | 9 | 26 | 118 | 43 | 88 | 65.5 | 33.5 | 4628.5 |
| 9/27/2011 | 2011 | 9 | 27 | 119 | 42 | 88 | 65 | 33 | 4661.5 |
| 9/28/2011 | 2011 | 9 | 28 | 120 | 40 | 90 | 65 | 33 | 4694.5 |
| 9/29/2011 | 2011 | 9 | 29 | 121 | 41 | 89 | 65 | 33 | 4727.5 |
| 9/30/2011 | 2011 | 9 | 30 | 122 | 47 | 87 | 67 | 35 | 4762.5 |
| 10/1/2011 | 2011 | 10 | 1 | 123 | 38 | 78 | 58 | 26 | 4788.5 |
| 10/2/2011 | 2011 | 10 | 2 | 124 | 46 | 83 | 64.5 | 32.5 | 4821 |
| 10/3/2011 | 2011 | 10 | 3 | 125 | 40 | 78 | 59 | 27 | 4848 |
| 10/4/2011 | 2011 | 10 | 4 | 126 | 42 | 76 | 59 | 27 | 4875 |
| 10/5/2011 | 2011 | 10 | 5 | 127 | 40 | 60 | 50 | 18 | 4893 |
| 10/6/2011 | 2011 | 10 | 6 | 128 | 43 | 67 | 55 | 23 | 4916 |
| 10/7/2011 | 2011 | 10 | 7 | 129 | 37 | 62 | 49.5 | 17.5 | 4933.5 |
| 10/8/2011 | 2011 | 10 | 8 | 130 | 30 | 56 | 43 | 11 | 4944.5 |
| 10/9/2011 | 2011 | 10 | 9 | 131 | 30 | 63 | 46.5 | 14.5 | 4959 |
| 10/10/2011 | 2011 | 10 | 10 | 132 | 30 | 63 | 46.5 | 14.5 | 4973.5 |
| 10/11/2011 | 2011 | 10 | 11 | 133 | 35 | 75 | 55 | 23 | 4996.5 |
| 10/12/2011 | 2011 | 10 | 12 | 134 | 37 | 78 | 57.5 | 25.5 | 5022 |
| 10/13/2011 | 2011 | 10 | 13 | 135 | 32 | 77 | 54.5 | 22.5 | 5044.5 |
| 10/14/2011 | 2011 | 10 | 14 | 136 | 33 | 78 | 55.5 | 23.5 | 5068 |
| 10/15/2011 | 2011 | 10 | 15 | 137 | 34 | 80 | 57 | 25 | 5093 |
| 10/16/2011 | 2011 | 10 | 16 | 138 | 32 | 81 | 56.5 | 24.5 | 5117.5 |
| 10/17/2011 | 2011 | 10 | 17 | 139 | 37 | 84 | 60.5 | 28.5 | 5146 |
| 10/18/2011 | 2011 | 10 | 18 | 140 | 35 | 71 | 53 | 21 | 5167 |
| 10/19/2011 | 2011 | 10 | 19 | 141 | 30 | 74 | 52 | 20 | 5187 |
| 10/20/2011 | 2011 | 10 | 20 | 142 | 36 | 77 | 56.5 | 24.5 | 5211.5 |
| 10/21/2011 | 2011 | 10 | 21 | 143 | 29 | 80 | 54.5 | 22.5 | 5234 |
| 10/22/2011 | 2011 | 10 | 22 | 144 | 27 | 81 | 54 | 22 | 5256 |
| 10/23/2011 | 2011 | 10 | 23 | 145 | 28 | 80 | 54 | 22 | 5278 |
| 10/24/2011 | 2011 | 10 | 24 | 146 | 30 | 79 | 54.5 | 22.5 | 5300.5 |
| 10/25/2011 | 2011 | 10 | 25 | 147 | 30 | 77 | 53.5 | 21.5 | 5322 |
| 10/26/2011 | 2011 | 10 | 26 | 148 | 31 | 77 | 54 | 22 | 5344 |
| 10/27/2011 | 2011 | 10 | 27 | 149 | 42 | 68 | 55 | 23 | 5367 |
| 10/28/2011 | 2011 | 10 | 28 | 150 | 25 | 80 | 52.5 | 20.5 | 5387.5 |
| 10/29/2011 | 2011 | 10 | 29 | 151 | 23 | 70 | 46.5 | 14.5 | 5402 |
| 10/30/2011 | 2011 | 10 | 30 | 152 | 27 | 69 | 48 | 16 | 5418 |
| 10/31/2011 | 2011 | 10 | 31 | 153 | 30 | 72 | 51 | 19 | 5437 |
| 11/1/2011 | 2011 | 11 | 1 | 154 | 27 | 77 | 52 | 20 | 5457 |
| 11/2/2011 | 2011 | 11 | 2 | 155 | 24 | 73 | 48.5 | 16.5 | 5473.5 |
| 11/3/2011 | 2011 | 11 | 3 | 156 | 14 | 57 | 35.5 | 3.5 | 5477 |
| 11/4/2011 | 2011 | 11 | 4 | 157 | 32 | 59 | 45.5 | 13.5 | 5490.5 |
| 11/5/2011 | 2011 | 11 | 5 | 158 | 34 | 56 | 45 | 13 | 5503.5 |
| 11/6/2011 | 2011 | 11 | 6 | 159 | 19 | 55 | 37 | 5 | 5508.5 |
| 11/7/2011 | 2011 | 11 | 7 | 160 | 24 | 50 | 37 | 5 | 5513.5 |
| 11/8/2011 | 2011 | 11 | 8 | 161 | 29 | 48 | 38.5 | 6.5 | 5520 |
| 11/9/2011 | 2011 | 11 | 9 | 162 | 29 | 37 | 33 | 1 | 5521 |
| 11/10/2011 | 2011 | 11 | 10 | 163 | 13 | 55 | 34 | 2 | 5523 |
| 11/11/2011 | 2011 | 11 | 11 | 164 | 25 | 61 | 43 | 11 | 5534 |
| 11/12/2011 | 2011 | 11 | 12 | 165 | 32 | 62 | 47 | 15 | 5549 |
| 11/13/2011 | 2011 | 11 | 13 | 166 | 39 | 54 | 46.5 | 14.5 | 5563.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/14/2011 | 2011 | 11 | 14 | 167 | 34 | 54 | 44 | 12 | 5575.5 |
| 11/15/2011 | 2011 | 11 | 15 | 168 | 24 | 57 | 40.5 | 8.5 | 5584 |
| 11/16/2011 | 2011 | 11 | 16 | 169 | 28 | 53 | 40.5 | 8.5 | 5592.5 |
| 11/17/2011 | 2011 | 11 | 17 | 170 | 16 | 61 | 38.5 | 6.5 | 5599 |
| 11/18/2011 | 2011 | 11 | 18 | 171 | 19 | 60 | 39.5 | 7.5 | 5606.5 |
| 11/19/2011 | 2011 | 11 | 19 | 172 | 35 | 60 | 47.5 | 15.5 | 5622 |
| 11/20/2011 | 2011 | 11 | 20 | 173 | 32 | 63 | 47.5 | 15.5 | 5637.5 |
| 11/21/2011 | 2011 | 11 | 21 | 174 | 26 | 56 | 41 | 9 | 5646.5 |
| 11/22/2011 | 2011 | 11 | 22 | 175 | 22 | 56 | 39 | 7 | 5653.5 |
| 11/23/2011 | 2011 | 11 | 23 | 176 | 19 | 62 | 40.5 | 8.5 | 5662 |
| 11/24/2011 | 2011 | 11 | 24 | 177 | 18 | 63 | 40.5 | 8.5 | 5670.5 |
| 11/25/2011 | 2011 | 11 | 25 | 178 | 39 | 53 | 46 | 14 | 5684.5 |
| 11/26/2011 | 2011 | 11 | 26 | 179 | 32 | 47 | 39.5 | 7.5 | 5692 |
| 11/27/2011 | 2011 | 11 | 27 | 180 | 16 | 56 | 36 | 4 | 5696 |
| 11/28/2011 | 2011 | 11 | 28 | 181 | 23 | 64 | 43.5 | 11.5 | 5707.5 |
| 11/29/2011 | 2011 | 11 | 29 | 182 | 27 | 60 | 43.5 | 11.5 | 5719 |
| 11/30/2011 | 2011 | 11 | 30 | 183 | 17 | 65 | 41 | 9 | 5728 |
| 12/1/2011 | 2011 | 12 | 1 | 184 | 28 | 53 | 40.5 | 8.5 | 5736.5 |
| 12/2/2011 | 2011 | 12 | 2 | 185 | 26 | 53 | 39.5 | 7.5 | 5744 |
| 12/3/2011 | 2011 | 12 | 3 | 186 | 26 | 40 | 33 | 1 | 5745 |
| 12/4/2011 | 2011 | 12 | 4 | 187 | 26 | 37 | 31.5 | -0.5 | 5744.5 |
| 12/5/2011 | 2011 | 12 | 5 | 188 | -2 | 32 | 15 | -17 | 5727.5 |
| 12/6/2011 | 2011 | 12 | 6 | 189 | -6 | 31 | 12.5 | -19.5 | 5708 |
| 12/7/2011 | 2011 | 12 | 7 | 190 | 4 | 40 | 22 | -10 | 5698 |
| 12/8/2011 | 2011 | 12 | 8 | 191 | 10 | 47 | 28.5 | -3.5 | 5694.5 |
| 12/9/2011 | 2011 | 12 | 9 | 192 | 12 | 45 | 28.5 | -3.5 | 5691 |
| 12/10/2011 | 2011 | 12 | 10 | 193 | 12 | 44 | 28 | -4 | 5687 |
| 12/11/2011 | 2011 | 12 | 11 | 194 | 1 | 47 | 24 | -8 | 5679 |
| 12/12/2011 | 2011 | 12 | 12 | 195 | 24 | 55 | 39.5 | 7.5 | 5686.5 |
| 12/13/2011 | 2011 | 12 | 13 | 196 | 33 | 40 | 36.5 | 4.5 | 5691 |
| 12/14/2011 | 2011 | 12 | 14 | 197 | 37 | 40 | 38.5 | 6.5 | 5697.5 |
| 12/15/2011 | 2011 | 12 | 15 | 198 | 13 | 35 | 24 | -8 | 5689.5 |
| 12/16/2011 | 2011 | 12 | 16 | 199 | 12 | 39 | 25.5 | -6.5 | 5683 |
| 12/17/2011 | 2011 | 12 | 17 | 200 | 12 | 39 | 25.5 | -6.5 | 5676.5 |
| 12/18/2011 | 2011 | 12 | 18 | 201 | 12 | 47 | 29.5 | -2.5 | 5674 |
| 12/19/2011 | 2011 | 12 | 19 | 202 | 31 | 40 | 35.5 | 3.5 | 5677.5 |
| 12/20/2011 | 2011 | 12 | 20 | 203 | 31 | 55 | 43 | 11 | 5688.5 |
| 12/21/2011 | 2011 | 12 | 21 | 204 | 15 | 37 | 26 | -6 | 5682.5 |
| 12/22/2011 | 2011 | 12 | 22 | 205 | 13 | 37 | 25 | -7 | 5675.5 |
| 12/23/2011 | 2011 | 12 | 23 | 206 | 14 | 25 | 19.5 | -12.5 | 5663 |
| 12/24/2011 | 2011 | 12 | 24 | 207 | -13 | 17 | 2 | -30 | 5633 |
| 12/25/2011 | 2011 | 12 | 25 | 208 | -12 | 15 | 1.5 | -30.5 | 5602.5 |
| 12/26/2011 | 2011 | 12 | 26 | 209 | -12 | 35 | 11.5 | -20.5 | 5582 |
| 12/27/2011 | 2011 | 12 | 27 | 210 | -8 | 23 | 7.5 | -24.5 | 5557.5 |
| 12/28/2011 | 2011 | 12 | 28 | 211 | 0 | 29 | 14.5 | -17.5 | 5540 |
| 12/29/2011 | 2011 | 12 | 29 | 212 | 4 | 34 | 19 | -13 | 5527 |
| 12/30/2011 | 2011 | 12 | 30 | 213 | 8 | 34 | 21 | -11 | 5516 |
| 12/31/2011 | 2011 | 12 | 31 | 214 | 10 | 48 | 29 | -3 | 5513 |
| 1/1/2012 | 2012 | 1 | 1 | 215 | 3 | 39 | 21 | -11 | 5502 |
| 1/2/2012 | 2012 | 1 | 2 | 216 | 0 | 32 | 16 | -16 | 5486 |
| 1/3/2012 | 2012 | 1 | 3 | 217 | 0 | 33 | 16.5 | -15.5 | 5470.5 |
| 1/4/2012 | 2012 | 1 | 4 | 218 | 9 | 35 | 22 | -10 | 5460.5 |
| 1/5/2012 | 2012 | 1 | 5 | 219 | 1 | 31 | 16 | -16 | 5444.5 |
| 1/6/2012 | 2012 | 1 | 6 | 220 | 2 | 36 | 19 | -13 | 5431.5 |
| 1/7/2012 | 2012 | 1 | 7 | 221 | 4 | 51 | 27.5 | -4.5 | 5427 |
| 1/8/2012 | 2012 | 1 | 8 | 222 | 19 | 48 | 33.5 | 1.5 | 5428.5 |
| 1/9/2012 | 2012 | 1 | 9 | 223 | 14 | 34 | 24 | -8 | 5420.5 |
| 1/10/2012 | 2012 | 1 | 10 | 224 | 4 | 36 | 20 | -12 | 5408.5 |
| 1/11/2012 | 2012 | 1 | 11 | 225 | 13 | 42 | 27.5 | -4.5 | 5404 |
| 1/12/2012 | 2012 | 1 | 12 | 226 | 3 | 35 | 19 | -13 | 5391 |
| 1/13/2012 | 2012 | 1 | 13 | 227 | -4 | 36 | 16 | -16 | 5375 |
| 1/14/2012 | 2012 | 1 | 14 | 228 | -1 | 34 | 16.5 | -15.5 | 5359.5 |
| 1/15/2012 | 2012 | 1 | 15 | 229 | 6 | 48 | 27 | -5 | 5354.5 |
| 1/16/2012 | 2012 | 1 | 16 | 230 | 36 | 45 | 40.5 | 8.5 | 5363 |
| 1/17/2012 | 2012 | 1 | 17 | 231 | 35 | 42 | 38.5 | 6.5 | 5369.5 |
| 1/18/2012 | 2012 | 1 | 18 | 232 | 17 | 50 | 33.5 | 1.5 | 5371 |
| 1/19/2012 | 2012 | 1 | 19 | 233 | 25 | 51 | 38 | 6 | 5377 |
| 1/20/2012 | 2012 | 1 | 20 | 234 | 22 | 51 | 36.5 | 4.5 | 5381.5 |
| 1/21/2012 | 2012 | 1 | 21 | 235 | 18 | 54 | 36 | 4 | 5385.5 |
| 1/22/2012 | 2012 | 1 | 22 | 236 | 30 | 52 | 41 | 9 | 5394.5 |
| 1/23/2012 | 2012 | 1 | 23 | 237 | 15 | 47 | 31 | -1 | 5393.5 |
| 1/24/2012 | 2012 | 1 | 24 | 238 | 28 | 46 | 37 | 5 | 5398.5 |
| 1/25/2012 | 2012 | 1 | 25 | 239 | 24 | 42 | 33 | 1 | 5399.5 |
| 1/26/2012 | 2012 | 1 | 26 | 240 | 24 | 50 | 37 | 5 | 5404.5 |
| 1/27/2012 | 2012 | 1 | 27 | 241 | 30 | 49 | 39.5 | 7.5 | 5412 |
| 1/28/2012 | 2012 | 1 | 28 | 242 | 17 | 43 | 30 | -2 | 5410 |
| 1/29/2012 | 2012 | 1 | 29 | 243 | 18 | 47 | 32.5 | 0.5 | 5410.5 |
| 1/30/2012 | 2012 | 1 | 30 | 244 | 19 | 53 | 36 | 4 | 5414.5 |
| 1/31/2012 | 2012 | 1 | 31 | 245 | 27 | 52 | 39.5 | 7.5 | 5422 |
| 2/1/2012 | 2012 | 2 | 1 | 246 | 22 | 50 | 36 | 4 | 5426 |
| 2/2/2012 | 2012 | 2 | 2 | 247 | 28 | 48 | 38 | 6 | 5432 |
| 2/3/2012 | 2012 | 2 | 3 | 248 | 24 | 42 | 33 | 1 | 5433 |
| 2/4/2012 | 2012 | 2 | 4 | 249 | 24 | 42 | 33 | 1 | 5434 |
| 2/5/2012 | 2012 | 2 | 5 | 250 | 27 | 40 | 33.5 | 1.5 | 5435.5 |
| 2/6/2012 | 2012 | 2 | 6 | 251 | 26 | 48 | 37 | 5 | 5440.5 |
| 2/7/2012 | 2012 | 2 | 7 | 252 | 20 | 46 | 33 | 1 | 5441.5 |
| 2/8/2012 | 2012 | 2 | 8 | 253 | 29 | 53 | 41 | 9 | 5450.5 |
| 2/9/2012 | 2012 | 2 | 9 | 254 | 29 | 53 | 41 | 9 | 5459.5 |
| 2/10/2012 | 2012 | 2 | 10 | 255 | 23 | 55 | 39 | 7 | 5466.5 |
| 2/11/2012 | 2012 | 2 | 11 | 256 | 21 | 54 | 37.5 | 5.5 | 5472 |
| 2/12/2012 | 2012 | 2 | 12 | 257 | 27 | 52 | 39.5 | 7.5 | 5479.5 |
| 2/13/2012 | 2012 | 2 | 13 | 258 | 30 | 45 | 37.5 | 5.5 | 5485 |
| 2/14/2012 | 2012 | 2 | 14 | 259 | 29 | 45 | 37 | 5 | 5490 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/15/2012 | 2012 | 2 | 15 | 260 | 17 | 41 | 29 | -3 | 5487 |
| 2/16/2012 | 2012 | 2 | 16 | 261 | 26 | 49 | 37.5 | 5.5 | 5492.5 |
| 2/17/2012 | 2012 | 2 | 17 | 262 | 23 | 49 | 36 | 4 | 5496.5 |
| 2/18/2012 | 2012 | 2 | 18 | 263 | 20 | 52 | 36 | 4 | 5500.5 |
| 2/19/2012 | 2012 | 2 | 19 | 264 | 20 | 57 | 38.5 | 6.5 | 5507 |
| 2/20/2012 | 2012 | 2 | 20 | 265 | 18 | 42 | 30 | -2 | 5505 |
| 2/21/2012 | 2012 | 2 | 21 | 266 | 16 | 54 | 35 | 3 | 5508 |
| 2/22/2012 | 2012 | 2 | 22 | 267 | 26 | 61 | 43.5 | 11.5 | 5519.5 |
| 2/23/2012 | 2012 | 2 | 23 | 268 | 32 | 61 | 46.5 | 14.5 | 5534 |
| 2/24/2012 | 2012 | 2 | 24 | 269 | 16 | 53 | 34.5 | 2.5 | 5536.5 |
| 2/25/2012 | 2012 | 2 | 25 | 270 | 15 | 64 | 39.5 | 7.5 | 5544 |
| 2/26/2012 | 2012 | 2 | 26 | 271 | 22 | 61 | 41.5 | 9.5 | 5553.5 |
| 2/27/2012 | 2012 | 2 | 27 | 272 | 23 | 56 | 39.5 | 7.5 | 5561 |
| 2/28/2012 | 2012 | 2 | 28 | 273 | 33 | 57 | 45 | 13 | 5574 |
| 2/29/2012 | 2012 | 2 | 29 | 274 | 16 | 57 | 36.5 | 4.5 | 5578.5 |
| 3/1/2012 | 2012 | 3 | 1 | 275 | 38 | 56 | 47 | 15 | 5593.5 |
| 3/2/2012 | 2012 | 3 | 2 | 276 | 22 | 50 | 36 | 4 | 5597.5 |
| 3/3/2012 | 2012 | 3 | 3 | 277 | 13 | 50 | 31.5 | -0.5 | 5597 |
| 3/4/2012 | 2012 | 3 | 4 | 278 | 16 | 60 | 38 | 6 | 5603 |
| 3/5/2012 | 2012 | 3 | 5 | 279 | 17 | 69 | 43 | 11 | 5614 |
| 3/6/2012 | 2012 | 3 | 6 | 280 | 23 | 67 | 45 | 13 | 5627 |
| 3/7/2012 | 2012 | 3 | 7 | 281 | 29 | 64 | 46.5 | 14.5 | 5641.5 |
| 3/8/2012 | 2012 | 3 | 8 | 282 | 16 | 47 | 31.5 | -0.5 | 5641 |
| 3/9/2012 | 2012 | 3 | 9 | 283 | 21 | 43 | 32 | 0 | 5641 |
| 3/10/2012 | 2012 | 3 | 10 | 284 | 29 | 43 | 36 | 4 | 5645 |
| 3/11/2012 | 2012 | 3 | 11 | 285 | 27 | 59 | 43 | 11 | 5656 |
| 3/12/2012 | 2012 | 3 | 12 | 286 | 23 | 66 | 44.5 | 12.5 | 5668.5 |
| 3/13/2012 | 2012 | 3 | 13 | 287 | 19 | 70 | 44.5 | 12.5 | 5681 |
| 3/14/2012 | 2012 | 3 | 14 | 288 | 22 | 70 | 46 | 14 | 5695 |
| 3/15/2012 | 2012 | 3 | 15 | 289 | 20 | 72 | 46 | 14 | 5709 |
| 3/16/2012 | 2012 | 3 | 16 | 290 | 22 | 73 | 47.5 | 15.5 | 5724.5 |
| 3/17/2012 | 2012 | 3 | 17 | 291 | 30 | 70 | 50 | 18 | 5742.5 |
| 3/18/2012 | 2012 | 3 | 18 | 292 | 34 | 65 | 49.5 | 17.5 | 5760 |
| 3/19/2012 | 2012 | 3 | 19 | 293 | 19 | 38 | 28.5 | -3.5 | 5756.5 |
| 3/20/2012 | 2012 | 3 | 20 | 294 | 20 | 48 | 34 | 2 | 5758.5 |
| 3/21/2012 | 2012 | 3 | 21 | 295 | 17 | 63 | 40 | 8 | 5766.5 |
| 3/22/2012 | 2012 | 3 | 22 | 296 | 23 | 71 | 47 | 15 | 5781.5 |
| 3/23/2012 | 2012 | 3 | 23 | 297 | 23 | 74 | 48.5 | 16.5 | 5798 |
| 3/24/2012 | 2012 | 3 | 24 | 298 | 29 | 78 | 53.5 | 21.5 | 5819.5 |
| 3/25/2012 | 2012 | 3 | 25 | 299 | 26 | 77 | 51.5 | 19.5 | 5839 |
| 3/26/2012 | 2012 | 3 | 26 | 300 | 44 | 74 | 59 | 27 | 5866 |
| 3/27/2012 | 2012 | 3 | 27 | 301 | 26 | 75 | 50.5 | 18.5 | 5884.5 |
| 3/28/2012 | 2012 | 3 | 28 | 302 | 24 | 74 | 49 | 17 | 5901.5 |
| 3/29/2012 | 2012 | 3 | 29 | 303 | 28 | 72 | 50 | 18 | 5919.5 |
| 3/30/2012 | 2012 | 3 | 30 | 304 | 29 | 76 | 52.5 | 20.5 | 5940 |
| 3/31/2012 | 2012 | 3 | 31 | 305 | 34 | 79 | 56.5 | 24.5 | 5964.5 |
| 4/1/2012 | 2012 | 4 | 1 | 306 | 34 | 79 | 56.5 | 24.5 | 5989 |
| 4/2/2012 | 2012 | 4 | 2 | 307 | 31 | 48 | 39.5 | 7.5 | 5996.5 |
| 4/3/2012 | 2012 | 4 | 3 | 308 | 34 | 44 | 39 | 7 | 6003.5 |
| 4/4/2012 | 2012 | 4 | 4 | 309 | 31 | 71 | 51 | 19 | 6022.5 |
| 4/5/2012 | 2012 | 4 | 5 | 310 | 32 | 72 | 52 | 20 | 6042.5 |
| 4/6/2012 | 2012 | 4 | 6 | 311 | 34 | 71 | 52.5 | 20.5 | 6063 |
| 4/7/2012 | 2012 | 4 | 7 | 312 | 28 | 68 | 48 | 16 | 6079 |
| 4/8/2012 | 2012 | 4 | 8 | 313 | 42 | 73 | 57.5 | 25.5 | 6104.5 |
| 4/9/2012 | 2012 | 4 | 9 | 314 | 36 | 77 | 56.5 | 24.5 | 6129 |
| 4/10/2012 | 2012 | 4 | 10 | 315 | 33 | 77 | 55 | 23 | 6152 |
| 4/11/2012 | 2012 | 4 | 11 | 316 | 40 | 79 | 59.5 | 27.5 | 6179.5 |
| 4/12/2012 | 2012 | 4 | 12 | 317 | 35 | 75 | 55 | 23 | 6202.5 |
| 4/13/2012 | 2012 | 4 | 13 | 318 | 29 | 69 | 49 | 17 | 6219.5 |
| 4/14/2012 | 2012 | 4 | 14 | 319 | 30 | 65 | 47.5 | 15.5 | 6235 |
| 4/15/2012 | 2012 | 4 | 15 | 320 | 33 | 56 | 44.5 | 12.5 | 6247.5 |
| 4/16/2012 | 2012 | 4 | 16 | 321 | 23 | 63 | 43 | 11 | 6258.5 |
| 4/17/2012 | 2012 | 4 | 17 | 322 | 25 | 76 | 50.5 | 18.5 | 6277 |
| 4/18/2012 | 2012 | 4 | 18 | 323 | 29 | 78 | 53.5 | 21.5 | 6298.5 |
| 4/19/2012 | 2012 | 4 | 19 | 324 | 53 | 74 | 63.5 | 31.5 | 6330 |
| 4/20/2012 | 2012 | 4 | 20 | 325 | 37 | 76 | 56.5 | 24.5 | 6354.5 |
| 4/21/2012 | 2012 | 4 | 21 | 326 | 33 | 81 | 57 | 25 | 6379.5 |
| 4/22/2012 | 2012 | 4 | 22 | 327 | 36 | 82 | 59 | 27 | 6406.5 |
| 4/23/2012 | 2012 | 4 | 23 | 328 | 47 | 84 | 65.5 | 33.5 | 6440 |
| 4/24/2012 | 2012 | 4 | 24 | 329 | 45 | 85 | 65 | 33 | 6473 |
| 4/25/2012 | 2012 | 4 | 25 | 330 | 36 | 82 | 59 | 27 | 6500 |
| 4/26/2012 | 2012 | 4 | 26 | 331 | 44 | 83 | 63.5 | 31.5 | 6531.5 |
| 4/27/2012 | 2012 | 4 | 27 | 332 | 44 | 73 | 58.5 | 26.5 | 6558 |
| 4/28/2012 | 2012 | 4 | 28 | 333 | 36 | 71 | 53.5 | 21.5 | 6579.5 |
| 4/29/2012 | 2012 | 4 | 29 | 334 | 33 | 76 | 54.5 | 22.5 | 6602 |
| 4/30/2012 | 2012 | 4 | 30 | 335 | 32 | 79 | 55.5 | 23.5 | 6625.5 |
| 5/1/2012 | 2012 | 5 | 1 | 336 | 39 | 79 | 59 | 27 | 6652.5 |
| 5/2/2012 | 2012 | 5 | 2 | 337 | 43 | 81 | 62 | 30 | 6682.5 |
| 5/3/2012 | 2012 | 5 | 3 | 338 | 37 | 81 | 59 | 27 | 6709.5 |
| 5/4/2012 | 2012 | 5 | 4 | 339 | 38 | 83 | 60.5 | 28.5 | 6738 |
| 5/5/2012 | 2012 | 5 | 5 | 340 | 49 | 81 | 65 | 33 | 6771 |
| 5/6/2012 | 2012 | 5 | 6 | 341 | 41 | 81 | 61 | 29 | 6800 |
| 5/7/2012 | 2012 | 5 | 7 | 342 | 32 | 75 | 53.5 | 21.5 | 6821.5 |
| 5/8/2012 | 2012 | 5 | 8 | 343 | 44 | 69 | 56.5 | 24.5 | 6846 |
| 5/9/2012 | 2012 | 5 | 9 | 344 | 38 | 72 | 55 | 23 | 6869 |
| 5/10/2012 | 2012 | 5 | 10 | 345 | 36 | 79 | 57.5 | 25.5 | 6894.5 |
| 5/11/2012 | 2012 | 5 | 11 | 346 | 34 | 81 | 57.5 | 25.5 | 6920 |
| 5/12/2012 | 2012 | 5 | 12 | 347 | 49 | 80 | 64.5 | 32.5 | 6952.5 |
| 5/13/2012 | 2012 | 5 | 13 | 348 | 53 | 72 | 62.5 | 30.5 | 6983 |
| 5/14/2012 | 2012 | 5 | 14 | 349 | 33 | 75 | 54 | 22 | 7005 |
| 5/15/2012 | 2012 | 5 | 15 | 350 | 37 | 80 | 58.5 | 26.5 | 7031.5 |
| 5/16/2012 | 2012 | 5 | 16 | 351 | 43 | 81 | 62 | 30 | 7061.5 |
| 5/17/2012 | 2012 | 5 | 17 | 352 | 48 | 86 | 67 | 35 | 7096.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/18/2012 | 2012 | 5 | 18 | 353 | 47 | 85 | 66 | 34 | 7130.5 |
| 5/19/2012 | 2012 | 5 | 19 | 354 | 37 | 79 | 58 | 26 | 7156.5 |
| 5/20/2012 | 2012 | 5 | 20 | 355 | 38 | 82 | 60 | 28 | 7184.5 |
| 5/21/2012 | 2012 | 5 | 21 | 356 | 55 | 91 | 73 | 41 | 7225.5 |
| 5/22/2012 | 2012 | 5 | 22 | 357 | 47 | 90 | 68.5 | 36.5 | 7262 |
| 5/23/2012 | 2012 | 5 | 23 | 358 | 51 | 88 | 69.5 | 37.5 | 7299.5 |
| 5/24/2012 | 2012 | 5 | 24 | 359 | 61 | 85 | 73 | 41 | 7340.5 |
| 5/25/2012 | 2012 | 5 | 25 | 360 | 50 | 87 | 68.5 | 36.5 | 7377 |
| 5/26/2012 | 2012 | 5 | 26 | 361 | 53 | 84 | 68.5 | 36.5 | 7413.5 |
| 5/27/2012 | 2012 | 5 | 27 | 362 | 30 | 78 | 54 | 22 | 7435.5 |
| 5/28/2012 | 2012 | 5 | 28 | 363 | 28 | 82 | 55 | 23 | 7458.5 |
| 5/29/2012 | 2012 | 5 | 29 | 364 | 34 | 87 | 60.5 | 28.5 | 7487 |
| 5/30/2012 | 2012 | 5 | 30 | 365 | 46 | 86 | 66 | 34 | 7521 |
| 5/31/2012 | 2012 | 5 | 31 | 366 | 41 | 88 | 64.5 | 32.5 | 7553.5 |
| 6/1/2012 | 2012 | 6 | 1 | 1 | 43 | 93 | 68 | 36 | 36 |
| 6/2/2012 | 2012 | 6 | 2 | 2 | 55 | 91 | 73 | 41 | 77 |
| 6/3/2012 | 2012 | 6 | 3 | 3 | 42 | 92 | 67 | 35 | 112 |
| 6/4/2012 | 2012 | 6 | 4 | 4 | 50 | 91 | 70.5 | 38.5 | 150.5 |
| 6/5/2012 | 2012 | 6 | 5 | 5 | 42 | 91 | 66.5 | 34.5 | 185 |
| 6/6/2012 | 2012 | 6 | 6 | 6 | 39 | 91 | 65 | 33 | 218 |
| 6/7/2012 | 2012 | 6 | 7 | 7 | 44 | 91 | 67.5 | 35.5 | 253.5 |
| 6/8/2012 | 2012 | 6 | 8 | 8 | 40 | 91 | 65.5 | 33.5 | 287 |
| 6/9/2012 | 2012 | 6 | 9 | 9 | 50 | 90 | 70 | 38 | 325 |
| 6/10/2012 | 2012 | 6 | 10 | 10 | 49 | 87 | 68 | 36 | 361 |
| 6/11/2012 | 2012 | 6 | 11 | 11 | 45 | 90 | 67.5 | 35.5 | 396.5 |
| 6/12/2012 | 2012 | 6 | 12 | 12 | 45 | 92 | 68.5 | 36.5 | 433 |
| 6/13/2012 | 2012 | 6 | 13 | 13 | 41 | 92 | 66.5 | 34.5 | 467.5 |
| 6/14/2012 | 2012 | 6 | 14 | 14 | 46 | 91 | 68.5 | 36.5 | 504 |
| 6/15/2012 | 2012 | 6 | 15 | 15 | 50 | 92 | 71 | 39 | 543 |
| 6/16/2012 | 2012 | 6 | 16 | 16 | 45 | 90 | 67.5 | 35.5 | 578.5 |
| 6/17/2012 | 2012 | 6 | 17 | 17 | 53 | 94 | 73.5 | 41.5 | 620 |
| 6/18/2012 | 2012 | 6 | 18 | 18 | 49 | 93 | 71 | 39 | 659 |
| 6/19/2012 | 2012 | 6 | 19 | 19 | 53 | 93 | 73 | 41 | 700 |
| 6/20/2012 | 2012 | 6 | 20 | 20 | 54 | 96 | 75 | 43 | 743 |
| 6/21/2012 | 2012 | 6 | 21 | 21 | 48 | 95 | 71.5 | 39.5 | 782.5 |
| 6/22/2012 | 2012 | 6 | 22 | 22 | 56 | 97 | 76.5 | 44.5 | 827 |
| 6/23/2012 | 2012 | 6 | 23 | 23 | 52 | 95 | 73.5 | 41.5 | 868.5 |
| 6/24/2012 | 2012 | 6 | 24 | 24 | 48 | 96 | 72 | 40 | 908.5 |
| 6/25/2012 | 2012 | 6 | 25 | 25 | 53 | 96 | 74.5 | 42.5 | 951 |
| 6/26/2012 | 2012 | 6 | 26 | 26 | 55 | 97 | 76 | 44 | 995 |
| 6/27/2012 | 2012 | 6 | 27 | 27 | 54 | 93 | 73.5 | 41.5 | 1036.5 |
| 6/28/2012 | 2012 | 6 | 28 | 28 | 53 | 95 | 74 | 42 | 1078.5 |
| 6/29/2012 | 2012 | 6 | 29 | 29 | 58 | 97 | 77.5 | 45.5 | 1124 |
| 6/30/2012 | 2012 | 6 | 30 | 30 | 51 | 98 | 74.5 | 42.5 | 1166.5 |
| 7/1/2012 | 2012 | 7 | 1 | 31 | 58 | 97 | 77.5 | 45.5 | 1212 |
| 7/2/2012 | 2012 | 7 | 2 | 32 | 68 | 98 | 83 | 51 | 1263 |
| 7/3/2012 | 2012 | 7 | 3 | 33 | 60 | 95 | 77.5 | 45.5 | 1308.5 |
| 7/4/2012 | 2012 | 7 | 4 | 34 | 57 | 90 | 73.5 | 41.5 | 1350 |
| 7/5/2012 | 2012 | 7 | 5 | 35 | 55 | 87 | 71 | 39 | 1389 |
| 7/6/2012 | 2012 | 7 | 6 | 36 | 63 | 84 | 73.5 | 41.5 | 1430.5 |
| 7/7/2012 | 2012 | 7 | 7 | 37 | 63 | 79 | 71 | 39 | 1469.5 |
| 7/8/2012 | 2012 | 7 | 8 | 38 | 63 | 85 | 74 | 42 | 1511.5 |
| 7/9/2012 | 2012 | 7 | 9 | 39 | 56 | 82 | 69 | 37 | 1548.5 |
| 7/10/2012 | 2012 | 7 | 10 | 40 | 58 | 82 | 70 | 38 | 1586.5 |
| 7/11/2012 | 2012 | 7 | 11 | 41 | 57 | 82 | 69.5 | 37.5 | 1624 |
| 7/12/2012 | 2012 | 7 | 12 | 42 | 56 | 87 | 71.5 | 39.5 | 1663.5 |
| 7/13/2012 | 2012 | 7 | 13 | 43 | 59 | 90 | 74.5 | 42.5 | 1706 |
| 7/14/2012 | 2012 | 7 | 14 | 44 | 61 | 90 | 75.5 | 43.5 | 1749.5 |
| 7/15/2012 | 2012 | 7 | 15 | 45 | 56 | 88 | 72 | 40 | 1789.5 |
| 7/16/2012 | 2012 | 7 | 16 | 46 | 61 | 82 | 71.5 | 39.5 | 1829 |
| 7/17/2012 | 2012 | 7 | 17 | 47 | 55 | 86 | 70.5 | 38.5 | 1867.5 |
| 7/18/2012 | 2012 | 7 | 18 | 48 | 54 | 90 | 72 | 40 | 1907.5 |
| 7/19/2012 | 2012 | 7 | 19 | 49 | 56 | 88 | 72 | 40 | 1947.5 |
| 7/20/2012 | 2012 | 7 | 20 | 50 | 60 | 86 | 73 | 41 | 1988.5 |
| 7/21/2012 | 2012 | 7 | 21 | 51 | 67 | 91 | 79 | 47 | 2035.5 |
| 7/22/2012 | 2012 | 7 | 22 | 52 | 62 | 90 | 76 | 44 | 2079.5 |
| 7/23/2012 | 2012 | 7 | 23 | 53 | 56 | 88 | 72 | 40 | 2119.5 |
| 7/24/2012 | 2012 | 7 | 24 | 54 | 53 | 82 | 67.5 | 35.5 | 2155 |
| 7/25/2012 | 2012 | 7 | 25 | 55 | 54 | 72 | 63 | 31 | 2186 |
| 7/26/2012 | 2012 | 7 | 26 | 56 | 51 | 92 | 71.5 | 39.5 | 2225.5 |
| 7/27/2012 | 2012 | 7 | 27 | 57 | 60 | 89 | 74.5 | 42.5 | 2268 |
| 7/28/2012 | 2012 | 7 | 28 | 58 | 55 | 88 | 71.5 | 39.5 | 2307.5 |
| 7/29/2012 | 2012 | 7 | 29 | 59 | 60 | 88 | 74 | 42 | 2349.5 |
| 7/30/2012 | 2012 | 7 | 30 | 60 | 55 | 92 | 73.5 | 41.5 | 2391 |
| 7/31/2012 | 2012 | 7 | 31 | 61 | 59 | 92 | 75.5 | 43.5 | 2434.5 |
| 8/1/2012 | 2012 | 8 | 1 | 62 | 55 | 90 | 72.5 | 40.5 | 2475 |
| 8/2/2012 | 2012 | 8 | 2 | 63 | 54 | 85 | 69.5 | 37.5 | 2512.5 |
| 8/3/2012 | 2012 | 8 | 3 | 64 | 55 | 86 | 70.5 | 38.5 | 2551 |
| 8/4/2012 | 2012 | 8 | 4 | 65 | 53 | 87 | 70 | 38 | 2589 |
| 8/5/2012 | 2012 | 8 | 5 | 66 | 62 | 86 | 74 | 42 | 2631 |
| 8/6/2012 | 2012 | 8 | 6 | 67 | 57 | 87 | 72 | 40 | 2671 |
| 8/7/2012 | 2012 | 8 | 7 | 68 | 55 | 86 | 70.5 | 38.5 | 2709.5 |
| 8/8/2012 | 2012 | 8 | 8 | 69 | 58 | 90 | 74 | 42 | 2751.5 |
| 8/9/2012 | 2012 | 8 | 9 | 70 | 52 | 92 | 72 | 40 | 2791.5 |
| 8/10/2012 | 2012 | 8 | 10 | 71 | 51 | 94 | 72.5 | 40.5 | 2832 |
| 8/11/2012 | 2012 | 8 | 11 | 72 | 61 | 94 | 77.5 | 45.5 | 2877.5 |
| 8/12/2012 | 2012 | 8 | 12 | 73 | 53 | 91 | 72 | 40 | 2917.5 |
| 8/13/2012 | 2012 | 8 | 13 | 74 | 62 | 82 | 72 | 40 | 2957.5 |
| 8/14/2012 | 2012 | 8 | 14 | 75 | 53 | 88 | 70.5 | 38.5 | 2996 |
| 8/15/2012 | 2012 | 8 | 15 | 76 | 50 | 90 | 70 | 38 | 3034 |
| 8/16/2012 | 2012 | 8 | 16 | 77 | 51 | 88 | 69.5 | 37.5 | 3071.5 |
| 8/17/2012 | 2012 | 8 | 17 | 78 | 59 | 86 | 72.5 | 40.5 | 3112 |
| 8/18/2012 | 2012 | 8 | 18 | 79 | 52 | 91 | 71.5 | 39.5 | 3151.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/19/2012 | 2012 | 8 | 19 | 80 | 57 | 88 | 72.5 | 40.5 | 3192 |
| 8/20/2012 | 2012 | 8 | 20 | 81 | 62 | 86 | 74 | 42 | 3234 |
| 8/21/2012 | 2012 | 8 | 21 | 82 | 54 | 90 | 72 | 40 | 3274 |
| 8/22/2012 | 2012 | 8 | 22 | 83 | 61 | 82 | 71.5 | 39.5 | 3313.5 |
| 8/23/2012 | 2012 | 8 | 23 | 84 | 56 | 81 | 68.5 | 36.5 | 3350 |
| 8/24/2012 | 2012 | 8 | 24 | 85 | 49 | 80 | 64.5 | 32.5 | 3382.5 |
| 8/25/2012 | 2012 | 8 | 25 | 86 | 50 | 88 | 69 | 37 | 3419.5 |
| 8/26/2012 | 2012 | 8 | 26 | 87 | 52 | 90 | 71 | 39 | 3458.5 |
| 8/27/2012 | 2012 | 8 | 27 | 88 | 56 | 89 | 72.5 | 40.5 | 3499 |
| 8/28/2012 | 2012 | 8 | 28 | 89 | 48 | 89 | 68.5 | 36.5 | 3535.5 |
| 8/29/2012 | 2012 | 8 | 29 | 90 | 46 | 90 | 68 | 36 | 3571.5 |
| 8/30/2012 | 2012 | 8 | 30 | 91 | 51 | 92 | 71.5 | 39.5 | 3611 |
| 8/31/2012 | 2012 | 8 | 31 | 92 | 46 | 89 | 67.5 | 35.5 | 3646.5 |
| 9/1/2012 | 2012 | 9 | 1 | 93 | 49 | 90 | 69.5 | 37.5 | 3684 |
| 9/2/2012 | 2012 | 9 | 2 | 94 | 49 | 89 | 69 | 37 | 3721 |
| 9/3/2012 | 2012 | 9 | 3 | 95 | 59 | 87 | 73 | 41 | 3762 |
| 9/4/2012 | 2012 | 9 | 4 | 96 | 61 | 90 | 75.5 | 43.5 | 3805.5 |
| 9/5/2012 | 2012 | 9 | 5 | 97 | 63 | 91 | 77 | 45 | 3850.5 |
| 9/6/2012 | 2012 | 9 | 6 | 98 | 55 | 92 | 73.5 | 41.5 | 3892 |
| 9/7/2012 | 2012 | 9 | 7 | 99 | 63 | 87 | 75 | 43 | 3935 |
| 9/8/2012 | 2012 | 9 | 8 | 100 | 56 | 73 | 64.5 | 32.5 | 3967.5 |
| 9/9/2012 | 2012 | 9 | 9 | 101 | 41 | 78 | 59.5 | 27.5 | 3995 |
| 9/10/2012 | 2012 | 9 | 10 | 102 | 52 | 85 | 68.5 | 36.5 | 4031.5 |
| 9/11/2012 | 2012 | 9 | 11 | 103 | 48 | 78 | 63 | 31 | 4062.5 |
| 9/12/2012 | 2012 | 9 | 12 | 104 | 57 | 67 | 62 | 30 | 4092.5 |
| 9/13/2012 | 2012 | 9 | 13 | 105 | 52 | 65 | 58.5 | 26.5 | 4119 |
| 9/14/2012 | 2012 | 9 | 14 | 106 | 43 | 69 | 56 | 24 | 4143 |
| 9/15/2012 | 2012 | 9 | 15 | 107 | 38 | 79 | 58.5 | 26.5 | 4169.5 |
| 9/16/2012 | 2012 | 9 | 16 | 108 | 38 | 85 | 61.5 | 29.5 | 4199 |
| 9/17/2012 | 2012 | 9 | 17 | 109 | 41 | 82 | 61.5 | 29.5 | 4228.5 |
| 9/18/2012 | 2012 | 9 | 18 | 110 | 39 | 80 | 59.5 | 27.5 | 4256 |
| 9/19/2012 | 2012 | 9 | 19 | 111 | 37 | 84 | 60.5 | 28.5 | 4284.5 |
| 9/20/2012 | 2012 | 9 | 20 | 112 | 36 | 84 | 60 | 28 | 4312.5 |
| 9/21/2012 | 2012 | 9 | 21 | 113 | 40 | 84 | 62 | 30 | 4342.5 |
| 9/22/2012 | 2012 | 9 | 22 | 114 | 37 | 88 | 62.5 | 30.5 | 4373 |
| 9/23/2012 | 2012 | 9 | 23 | 115 | 42 | 84 | 63 | 31 | 4404 |
| 9/24/2012 | 2012 | 9 | 24 | 116 | 44 | 81 | 62.5 | 30.5 | 4434.5 |
| 9/25/2012 | 2012 | 9 | 25 | 117 | 41 | 77 | 59 | 27 | 4461.5 |
| 9/26/2012 | 2012 | 9 | 26 | 118 | 40 | 80 | 60 | 28 | 4489.5 |
| 9/27/2012 | 2012 | 9 | 27 | 119 | 41 | 78 | 59.5 | 27.5 | 4517 |
| 9/28/2012 | 2012 | 9 | 28 | 120 | 43 | 78 | 60.5 | 28.5 | 4545.5 |
| 9/29/2012 | 2012 | 9 | 29 | 121 | 40 | 79 | 59.5 | 27.5 | 4573 |
| 9/30/2012 | 2012 | 9 | 30 | 122 | 34 | 79 | 56.5 | 24.5 | 4597.5 |
| 1/1/2013 | 2013 | 1 | 1 | 123 | 2 | 34 | 18 | -14 | 4583.5 |
| 1/2/2013 | 2013 | 1 | 2 | 124 | -4 | 35 | 15.5 | -16.5 | 4567 |
| 1/3/2013 | 2013 | 1 | 3 | 125 | -3 | 33 | 15 | -17 | 4550 |
| 1/4/2013 | 2013 | 1 | 4 | 126 | -4 | 37 | 16.5 | -15.5 | 4534.5 |
| 1/5/2013 | 2013 | 1 | 5 | 127 | -2 | 32 | 15 | -17 | 4517.5 |
| 1/6/2013 | 2013 | 1 | 6 | 128 | -2 | 42 | 20 | -12 | 4505.5 |
| 1/7/2013 | 2013 | 1 | 7 | 129 | 28 | 47 | 37.5 | 5.5 | 4511 |
| 1/8/2013 | 2013 | 1 | 8 | 130 | 8 | 48 | 28 | -4 | 4507 |
| 1/9/2013 | 2013 | 1 | 9 | 131 | 8 | 52 | 30 | -2 | 4505 |
| 1/10/2013 | 2013 | 1 | 10 | 132 | 8 | 54 | 31 | -1 | 4504 |
| 1/11/2013 | 2013 | 1 | 11 | 133 | 24 | 43 | 33.5 | 1.5 | 4505.5 |
| 1/12/2013 | 2013 | 1 | 12 | 134 | -6 | 25 | 9.5 | -22.5 | 4483 |
| 1/13/2013 | 2013 | 1 | 13 | 135 | -11 | 30 | 9.5 | -22.5 | 4460.5 |
| 1/14/2013 | 2013 | 1 | 14 | 136 | 0 | 28 | 14 | -18 | 4442.5 |
| 1/15/2013 | 2013 | 1 | 15 | 137 | -9 | 25 | 8 | -24 | 4418.5 |
| 1/16/2013 | 2013 | 1 | 16 | 138 | -1 | 44 | 21.5 | -10.5 | 4408 |
| 1/17/2013 | 2013 | 1 | 17 | 139 | 4 | 48 | 26 | -6 | 4402 |
| 1/18/2013 | 2013 | 1 | 18 | 140 | 8 | 54 | 31 | -1 | 4401 |
| 1/19/2013 | 2013 | 1 | 19 | 141 | 7 | 52 | 29.5 | -2.5 | 4398.5 |
| 1/20/2013 | 2013 | 1 | 20 | 142 | 7 | 55 | 31 | -1 | 4397.5 |
| 1/21/2013 | 2013 | 1 | 21 | 143 | 3 | 55 | 29 | -3 | 4394.5 |
| 1/22/2013 | 2013 | 1 | 22 | 144 | 11 | 61 | 36 | 4 | 4398.5 |
| 1/23/2013 | 2013 | 1 | 23 | 145 | 7 | 64 | 35.5 | 3.5 | 4402 |
| 1/24/2013 | 2013 | 1 | 24 | 146 | 17 | 64 | 40.5 | 8.5 | 4410.5 |
| 1/25/2013 | 2013 | 1 | 25 | 147 | 30 | 56 | 43 | 11 | 4421.5 |
| 1/26/2013 | 2013 | 1 | 26 | 148 | 40 | 53 | 46.5 | 14.5 | 4436 |
| 1/27/2013 | 2013 | 1 | 27 | 149 | 38 | 56 | 47 | 15 | 4451 |
| 1/28/2013 | 2013 | 1 | 28 | 150 | 33 | 53 | 43 | 11 | 4462 |
| 1/29/2013 | 2013 | 1 | 29 | 151 | 15 | 41 | 28 | -4 | 4458 |
| 1/30/2013 | 2013 | 1 | 30 | 152 | 7 | 42 | 24.5 | -7.5 | 4450.5 |
| 1/31/2013 | 2013 | 1 | 31 | 153 | 16 | 50 | 33 | 1 | 4451.5 |
| 3/3/2013 | 2013 | 3 | 3 | 154 | 16 | 66 | 41 | 9 | 4460.5 |
| 3/4/2013 | 2013 | 3 | 4 | 155 | 33 | 59 | 46 | 14 | 4474.5 |
| 3/5/2013 | 2013 | 3 | 5 | 156 | 15 | 62 | 38.5 | 6.5 | 4481 |
| 3/6/2013 | 2013 | 3 | 6 | 157 | 30 | 68 | 49 | 17 | 4498 |
| 3/7/2013 | 2013 | 3 | 7 | 158 | 20 | 66 | 43 | 11 | 4509 |
| 3/8/2013 | 2013 | 3 | 8 | 159 | 23 | 65 | 44 | 12 | 4521 |
| 3/9/2013 | 2013 | 3 | 9 | 160 | 27 | 42 | 34.5 | 2.5 | 4523.5 |
| 3/10/2013 | 2013 | 3 | 10 | 161 | 24 | 51 | 37.5 | 5.5 | 4529 |
| 3/11/2013 | 2013 | 3 | 11 | 162 | 11 | 62 | 36.5 | 4.5 | 4533.5 |
| 3/12/2013 | 2013 | 3 | 12 | 163 | 18 | 64 | 41 | 9 | 4542.5 |
| 3/13/2013 | 2013 | 3 | 13 | 164 | 21 | 70 | 45.5 | 13.5 | 4556 |
| 3/14/2013 | 2013 | 3 | 14 | 165 | 25 | 75 | 50 | 18 | 4574 |
| 3/15/2013 | 2013 | 3 | 15 | 166 | 22 | 79 | 50.5 | 18.5 | 4592.5 |
| 3/16/2013 | 2013 | 3 | 16 | 167 | 34 | 75 | 54.5 | 22.5 | 4615 |
| 3/17/2013 | 2013 | 3 | 17 | 168 | 26 | 68 | 47 | 15 | 4630 |
| 3/18/2013 | 2013 | 3 | 18 | 169 | 23 | 66 | 44.5 | 12.5 | 4642.5 |
| 3/19/2013 | 2013 | 3 | 19 | 170 | 32 | 63 | 47.5 | 15.5 | 4658 |
| 3/20/2013 | 2013 | 3 | 20 | 171 | 19 | 63 | 41 | 9 | 4667 |
| 3/21/2013 | 2013 | 3 | 21 | 172 | 48 | 68 | 58 | 26 | 4693 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/22/2013 | 2013 | 3 | 22 | 173 | 19 | 65 | 42 | 10 | 4703 |
| 3/23/2013 | 2013 | 3 | 23 | 174 | 26 | 58 | 42 | 10 | 4713 |
| 3/24/2013 | 2013 | 3 | 24 | 175 | 11 | 54 | 32.5 | 0.5 | 4713.5 |
| 3/25/2013 | 2013 | 3 | 25 | 176 | 11 | 58 | 34.5 | 2.5 | 4716 |
| 3/26/2013 | 2013 | 3 | 26 | 177 | 15 | 66 | 40.5 | 8.5 | 4724.5 |
| 3/27/2013 | 2013 | 3 | 27 | 178 | 24 | 69 | 46.5 | 14.5 | 4739 |
| 3/28/2013 | 2013 | 3 | 28 | 179 | 32 | 71 | 51.5 | 19.5 | 4758.5 |
| 3/29/2013 | 2013 | 3 | 29 | 180 | 35 | 71 | 53 | 21 | 4779.5 |
| 3/30/2013 | 2013 | 3 | 30 | 181 | 25 | 70 | 47.5 | 15.5 | 4795 |
| 3/31/2013 | 2013 | 3 | 31 | 182 | 26 | 71 | 48.5 | 16.5 | 4811.5 |
| 4/1/2013 | 2013 | 4 | 1 | 183 | 28 | 72 | 50 | 18 | 4829.5 |
| 4/2/2013 | 2013 | 4 | 2 | 184 | 23 | 68 | 45.5 | 13.5 | 4843 |
| 4/3/2013 | 2013 | 4 | 3 | 185 | 25 | 63 | 44 | 12 | 4855 |
| 4/4/2013 | 2013 | 4 | 4 | 186 | 20 | 68 | 44 | 12 | 4867 |
| 4/5/2013 | 2013 | 4 | 5 | 187 | 29 | 77 | 53 | 21 | 4888 |
| 4/6/2013 | 2013 | 4 | 6 | 188 | 29 | 78 | 53.5 | 21.5 | 4909.5 |
| 4/8/2013 | 2013 | 4 | 8 | 189 | 36 | 78 | 57 | 25 | 4934.5 |
| 4/9/2013 | 2013 | 4 | 9 | 190 | 32 | 72 | 52 | 20 | 4954.5 |
| 4/10/2013 | 2013 | 4 | 10 | 191 | 29 | 51 | 40 | 8 | 4962.5 |
| 4/11/2013 | 2013 | 4 | 11 | 192 | 20 | 49 | 34.5 | 2.5 | 4965 |
| 4/12/2013 | 2013 | 4 | 12 | 193 | 33 | 68 | 50.5 | 18.5 | 4983.5 |
| 4/15/2013 | 2013 | 4 | 15 | 194 | 33 | 75 | 54 | 22 | 5005.5 |
| 4/16/2013 | 2013 | 4 | 16 | 195 | 44 | 75 | 59.5 | 27.5 | 5033 |
| 4/17/2013 | 2013 | 4 | 17 | 196 | 42 | 72 | 57 | 25 | 5058 |
| 4/18/2013 | 2013 | 4 | 18 | 197 | 17 | 54 | 35.5 | 3.5 | 5061.5 |
| 4/19/2013 | 2013 | 4 | 19 | 198 | 13 | 50 | 31.5 | -0.5 | 5061 |
| 4/20/2013 | 2013 | 4 | 20 | 199 | 24 | 68 | 46 | 14 | 5075 |
| 4/21/2013 | 2013 | 4 | 21 | 200 | 25 | 74 | 49.5 | 17.5 | 5092.5 |
| 4/23/2013 | 2013 | 4 | 23 | 201 | 45 | 81 | 63 | 31 | 5123.5 |
| 4/24/2013 | 2013 | 4 | 24 | 202 | 17 | 71 | 44 | 12 | 5135.5 |
| 4/27/2013 | 2013 | 4 | 27 | 203 | 30 | 72 | 51 | 19 | 5154.5 |
| 4/28/2013 | 2013 | 4 | 28 | 204 | 27 | 78 | 52.5 | 20.5 | 5175 |
| 4/29/2013 | 2013 | 4 | 29 | 205 | 32 | 85 | 58.5 | 26.5 | 5201.5 |
| 5/1/2013 | 2013 | 5 | 1 | 206 | 47 | 89 | 68 | 36 | 5237.5 |
| 5/2/2013 | 2013 | 5 | 2 | 207 | 33 | 82 | 57.5 | 25.5 | 5263 |
| 5/3/2013 | 2013 | 5 | 3 | 208 | 29 | 69 | 49 | 17 | 5280 |
| 5/4/2013 | 2013 | 5 | 4 | 209 | 28 | 72 | 50 | 18 | 5298 |
| 5/5/2013 | 2013 | 5 | 5 | 210 | 41 | 74 | 57.5 | 25.5 | 5323.5 |
| 5/6/2013 | 2013 | 5 | 6 | 211 | 50 | 68 | 59 | 27 | 5350.5 |
| 5/7/2013 | 2013 | 5 | 7 | 212 | 32 | 70 | 51 | 19 | 5369.5 |
| 5/8/2013 | 2013 | 5 | 8 | 213 | 38 | 75 | 56.5 | 24.5 | 5394 |
| 5/9/2013 | 2013 | 5 | 9 | 214 | 30 | 65 | 47.5 | 15.5 | 5409.5 |
| 5/10/2013 | 2013 | 5 | 10 | 215 | 32 | 65 | 48.5 | 16.5 | 5426 |
| 5/11/2013 | 2013 | 5 | 11 | 216 | 36 | 75 | 55.5 | 23.5 | 5449.5 |
| 5/12/2013 | 2013 | 5 | 12 | 217 | 32 | 78 | 55 | 23 | 5472.5 |
| 5/13/2013 | 2013 | 5 | 13 | 218 | 30 | 82 | 56 | 24 | 5496.5 |
| 5/14/2013 | 2013 | 5 | 14 | 219 | 41 | 85 | 63 | 31 | 5527.5 |
| 5/15/2013 | 2013 | 5 | 15 | 220 | 59 | 81 | 70 | 38 | 5565.5 |
| 5/16/2013 | 2013 | 5 | 16 | 221 | 60 | 84 | 72 | 40 | 5605.5 |
| 5/17/2013 | 2013 | 5 | 17 | 222 | 39 | 89 | 64 | 32 | 5637.5 |
| 5/18/2013 | 2013 | 5 | 18 | 223 | 46 | 86 | 66 | 34 | 5671.5 |
| 5/19/2013 | 2013 | 5 | 19 | 224 | 50 | 74 | 62 | 30 | 5701.5 |
| 5/20/2013 | 2013 | 5 | 20 | 225 | 38 | 75 | 56.5 | 24.5 | 5726 |
| 5/21/2013 | 2013 | 5 | 21 | 226 | 28 | 78 | 53 | 21 | 5747 |
| 5/22/2013 | 2013 | 5 | 22 | 227 | 33 | 85 | 59 | 27 | 5774 |
| 5/23/2013 | 2013 | 5 | 23 | 228 | 40 | 87 | 63.5 | 31.5 | 5805.5 |
| 5/24/2013 | 2013 | 5 | 24 | 229 | 41 | 89 | 65 | 33 | 5838.5 |
| 5/25/2013 | 2013 | 5 | 25 | 230 | 39 | 89 | 64 | 32 | 5870.5 |
| 5/26/2013 | 2013 | 5 | 26 | 231 | 43 | 89 | 66 | 34 | 5904.5 |
| 5/27/2013 | 2013 | 5 | 27 | 232 | 44 | 88 | 66 | 34 | 5938.5 |
| 5/28/2013 | 2013 | 5 | 28 | 233 | 36 | 82 | 59 | 27 | 5965.5 |
| 5/29/2013 | 2013 | 5 | 29 | 234 | 53 | 75 | 64 | 32 | 5997.5 |
| 5/30/2013 | 2013 | 5 | 30 | 235 | 48 | 83 | 65.5 | 33.5 | 6031 |
| 5/31/2013 | 2013 | 5 | 31 | 236 | 55 | 81 | 68 | 36 | 6067 |
| 6/1/2013 | 2013 | 6 | 1 | 1 | 39 | 83 | 61 | 29 | 29 |
| 6/2/2013 | 2013 | 6 | 2 | 2 | 44 | 89 | 66.5 | 34.5 | 63.5 |
| 6/3/2013 | 2013 | 6 | 3 | 3 | 45 | 85 | 65 | 33 | 96.5 |
| 6/4/2013 | 2013 | 6 | 4 | 4 | 45 | 93 | 69 | 37 | 133.5 |
| 6/5/2013 | 2013 | 6 | 5 | 5 | 53 | 88 | 70.5 | 38.5 | 172 |
| 6/6/2013 | 2013 | 6 | 6 | 6 | 45 | 92 | 68.5 | 36.5 | 208.5 |
| 6/7/2013 | 2013 | 6 | 7 | 7 | 55 | 90 | 72.5 | 40.5 | 249 |
| 6/8/2013 | 2013 | 6 | 8 | 8 | 45 | 93 | 69 | 37 | 286 |
| 6/9/2013 | 2013 | 6 | 9 | 9 | 53 | 99 | 76 | 44 | 330 |
| 6/10/2013 | 2013 | 6 | 10 | 10 | 48 | 100 | 74 | 42 | 372 |
| 6/11/2013 | 2013 | 6 | 11 | 11 | 44 | 98 | 71 | 39 | 411 |
| 6/12/2013 | 2013 | 6 | 12 | 12 | 48 | 99 | 73.5 | 41.5 | 452.5 |
| 6/13/2013 | 2013 | 6 | 13 | 13 | 53 | 100 | 76.5 | 44.5 | 497 |
| 6/14/2013 | 2013 | 6 | 14 | 14 | 53 | 97 | 75 | 43 | 540 |
| 6/15/2013 | 2013 | 6 | 15 | 15 | 58 | 96 | 77 | 45 | 585 |
| 6/16/2013 | 2013 | 6 | 16 | 16 | 52 | 97 | 74.5 | 42.5 | 627.5 |
| 6/17/2013 | 2013 | 6 | 17 | 17 | 49 | 93 | 71 | 39 | 666.5 |
| 6/18/2013 | 2013 | 6 | 18 | 18 | 53 | 97 | 75 | 43 | 709.5 |
| 6/20/2013 | 2013 | 6 | 20 | 19 | 47 | 95 | 71 | 39 | 748.5 |
| 6/22/2013 | 2013 | 6 | 22 | 20 | 51 | 94 | 72.5 | 40.5 | 789 |
| 6/23/2013 | 2013 | 6 | 23 | 21 | 48 | 92 | 70 | 38 | 827 |
| 6/28/2013 | 2013 | 6 | 28 | 22 | 57 | 106 | 81.5 | 49.5 | 876.5 |
| 6/29/2013 | 2013 | 6 | 29 | 23 | 51 | 101 | 76 | 44 | 920.5 |
| 6/30/2013 | 2013 | 6 | 30 | 24 | 60 | 101 | 80.5 | 48.5 | 969 |
| 7/1/2013 | 2013 | 7 | 1 | 25 | 57 | 100 | 78.5 | 46.5 | 1015.5 |
| 7/2/2013 | 2013 | 7 | 2 | 26 | 57 | 94 | 75.5 | 43.5 | 1059 |
| 7/3/2013 | 2013 | 7 | 3 | 27 | 55 | 88 | 71.5 | 39.5 | 1098.5 |
| 7/4/2013 | 2013 | 7 | 4 | 28 | 55 | 95 | 75 | 43 | 1141.5 |
| 7/5/2013 | 2013 | 7 | 5 | 29 | 54 | 94 | 74 | 42 | 1183.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/6/2013 | 2013 | 7 | 6 | 30 | 54 | 92 | 73 | 41 | 1224.5 |
| 7/7/2013 | 2013 | 7 | 7 | 31 | 56 | 90 | 73 | 41 | 1265.5 |
| 7/8/2013 | 2013 | 7 | 8 | 32 | 60 | 97 | 78.5 | 46.5 | 1312 |
| 7/9/2013 | 2013 | 7 | 9 | 33 | 61 | 93 | 77 | 45 | 1357 |
| 7/10/2013 | 2013 | 7 | 10 | 34 | 61 | 99 | 80 | 48 | 1405 |
| 7/11/2013 | 2013 | 7 | 11 | 35 | 61 | 93 | 77 | 45 | 1450 |
| 7/12/2013 | 2013 | 7 | 12 | 36 | 62 | 88 | 75 | 43 | 1493 |
| 7/13/2013 | 2013 | 7 | 13 | 37 | 55 | 91 | 73 | 41 | 1534 |
| 7/14/2013 | 2013 | 7 | 14 | 38 | 58 | 92 | 75 | 43 | 1577 |
| 7/15/2013 | 2013 | 7 | 15 | 39 | 58 | 94 | 76 | 44 | 1621 |
| 7/16/2013 | 2013 | 7 | 16 | 40 | 56 | 74 | 65 | 33 | 1654 |
| 7/17/2013 | 2013 | 7 | 17 | 41 | 58 | 81 | 69.5 | 37.5 | 1691.5 |
| 7/18/2013 | 2013 | 7 | 18 | 42 | 56 | 81 | 68.5 | 36.5 | 1728 |
| 7/19/2013 | 2013 | 7 | 19 | 43 | 59 | 85 | 72 | 40 | 1768 |
| 7/20/2013 | 2013 | 7 | 20 | 44 | 60 | 89 | 74.5 | 42.5 | 1810.5 |
| 7/22/2013 | 2013 | 7 | 22 | 45 | 58 | 92 | 75 | 43 | 1853.5 |
| 7/23/2013 | 2013 | 7 | 23 | 46 | 56 | 90 | 73 | 41 | 1894.5 |
| 7/24/2013 | 2013 | 7 | 24 | 47 | 58 | 98 | 78 | 46 | 1940.5 |
| 7/25/2013 | 2013 | 7 | 25 | 48 | 58 | 87 | 72.5 | 40.5 | 1981 |
| 7/26/2013 | 2013 | 7 | 26 | 49 | 59 | 90 | 74.5 | 42.5 | 2023.5 |
| 7/27/2013 | 2013 | 7 | 27 | 50 | 55 | 86 | 70.5 | 38.5 | 2062 |
| 7/29/2013 | 2013 | 7 | 29 | 51 | 53 | 89 | 71 | 39 | 2101 |
| 7/30/2013 | 2013 | 7 | 30 | 52 | 53 | 93 | 73 | 41 | 2142 |
| 8/1/2013 | 2013 | 8 | 1 | 53 | 63 | 93 | 78 | 46 | 2188 |
| 8/2/2013 | 2013 | 8 | 2 | 54 | 59 | 84 | 71.5 | 39.5 | 2227.5 |
| 8/3/2013 | 2013 | 8 | 3 | 55 | 52 | 92 | 72 | 40 | 2267.5 |
| 8/4/2013 | 2013 | 8 | 4 | 56 | 53 | 92 | 72.5 | 40.5 | 2308 |
| 8/5/2013 | 2013 | 8 | 5 | 57 | 52 | 90 | 71 | 39 | 2347 |
| 8/6/2013 | 2013 | 8 | 6 | 58 | 55 | 87 | 71 | 39 | 2386 |
| 8/7/2013 | 2013 | 8 | 7 | 59 | 56 | 84 | 70 | 38 | 2424 |
| 8/8/2013 | 2013 | 8 | 8 | 60 | 49 | 73 | 61 | 29 | 2453 |
| 8/9/2013 | 2013 | 8 | 9 | 61 | 50 | 87 | 68.5 | 36.5 | 2489.5 |
| 8/10/2013 | 2013 | 8 | 10 | 62 | 54 | 84 | 69 | 37 | 2526.5 |
| 8/11/2013 | 2013 | 8 | 11 | 63 | 49 | 77 | 63 | 31 | 2557.5 |
| 8/12/2013 | 2013 | 8 | 12 | 64 | 53 | 84 | 68.5 | 36.5 | 2594 |
| 8/13/2013 | 2013 | 8 | 13 | 65 | 52 | 88 | 70 | 38 | 2632 |
| 8/14/2013 | 2013 | 8 | 14 | 66 | 51 | 91 | 71 | 39 | 2671 |
| 8/15/2013 | 2013 | 8 | 15 | 67 | 53 | 90 | 71.5 | 39.5 | 2710.5 |
| 8/16/2013 | 2013 | 8 | 16 | 68 | 50 | 89 | 69.5 | 37.5 | 2748 |
| 8/17/2013 | 2013 | 8 | 17 | 69 | 54 | 92 | 73 | 41 | 2789 |
| 8/18/2013 | 2013 | 8 | 18 | 70 | 57 | 96 | 76.5 | 44.5 | 2833.5 |
| 8/19/2013 | 2013 | 8 | 19 | 71 | 56 | 94 | 75 | 43 | 2876.5 |
| 8/20/2013 | 2013 | 8 | 20 | 72 | 50 | 90 | 70 | 38 | 2914.5 |
| 8/21/2013 | 2013 | 8 | 21 | 73 | 53 | 93 | 73 | 41 | 2955.5 |
| 8/22/2013 | 2013 | 8 | 22 | 74 | 54 | 91 | 72.5 | 40.5 | 2996 |
| 8/23/2013 | 2013 | 8 | 23 | 75 | 50 | 92 | 71 | 39 | 3035 |
| 8/24/2013 | 2013 | 8 | 24 | 76 | 57 | 89 | 73 | 41 | 3076 |
| 8/25/2013 | 2013 | 8 | 25 | 77 | 57 | 86 | 71.5 | 39.5 | 3115.5 |
| 8/26/2013 | 2013 | 8 | 26 | 78 | 53 | 76 | 64.5 | 32.5 | 3148 |
| 8/27/2013 | 2013 | 8 | 27 | 79 | 51 | 85 | 68 | 36 | 3184 |
| 8/28/2013 | 2013 | 8 | 28 | 80 | 51 | 87 | 69 | 37 | 3221 |
| 8/29/2013 | 2013 | 8 | 29 | 81 | 61 | 88 | 74.5 | 42.5 | 3263.5 |
| 8/30/2013 | 2013 | 8 | 30 | 82 | 55 | 88 | 71.5 | 39.5 | 3303 |
| 8/31/2013 | 2013 | 8 | 31 | 83 | 56 | 90 | 73 | 41 | 3344 |
| 9/1/2013 | 2013 | 9 | 1 | 84 | 57 | 92 | 74.5 | 42.5 | 3386.5 |
| 9/2/2013 | 2013 | 9 | 2 | 85 | 57 | 92 | 74.5 | 42.5 | 3429 |
| 9/3/2013 | 2013 | 9 | 3 | 86 | 58 | 87 | 72.5 | 40.5 | 3469.5 |
| 9/4/2013 | 2013 | 9 | 4 | 87 | 53 | 92 | 72.5 | 40.5 | 3510 |
| 9/5/2013 | 2013 | 9 | 5 | 88 | 49 | 90 | 69.5 | 37.5 | 3547.5 |
| 9/6/2013 | 2013 | 9 | 6 | 89 | 47 | 89 | 68 | 36 | 3583.5 |
| 9/7/2013 | 2013 | 9 | 7 | 90 | 42 | 91 | 66.5 | 34.5 | 3618 |
| 9/8/2013 | 2013 | 9 | 8 | 91 | 42 | 89 | 65.5 | 33.5 | 3651.5 |
| 9/9/2013 | 2013 | 9 | 9 | 92 | 52 | 87 | 69.5 | 37.5 | 3689 |
| 9/10/2013 | 2013 | 9 | 10 | 93 | 57 | 85 | 71 | 39 | 3728 |
| 9/11/2013 | 2013 | 9 | 11 | 94 | 54 | 69 | 61.5 | 29.5 | 3757.5 |
| 9/12/2013 | 2013 | 9 | 12 | 95 | 59 | 80 | 69.5 | 37.5 | 3795 |
| 9/13/2013 | 2013 | 9 | 13 | 96 | 57 | 79 | 68 | 36 | 3831 |
| 9/14/2013 | 2013 | 9 | 14 | 97 | 52 | 73 | 62.5 | 30.5 | 3861.5 |
| 9/15/2013 | 2013 | 9 | 15 | 98 | 49 | 73 | 61 | 29 | 3890.5 |
| 9/16/2013 | 2013 | 9 | 16 | 99 | 50 | 77 | 63.5 | 31.5 | 3922 |
| 9/17/2013 | 2013 | 9 | 17 | 100 | 49 | 78 | 63.5 | 31.5 | 3953.5 |
| 9/18/2013 | 2013 | 9 | 18 | 101 | 53 | 80 | 66.5 | 34.5 | 3988 |
| 9/19/2013 | 2013 | 9 | 19 | 102 | 48 | 76 | 62 | 30 | 4018 |
| 9/20/2013 | 2013 | 9 | 20 | 103 | 48 | 89 | 68.5 | 36.5 | 4054.5 |
| 9/21/2013 | 2013 | 9 | 21 | 104 | 46 | 79 | 62.5 | 30.5 | 4085 |
| 9/22/2013 | 2013 | 9 | 22 | 105 | 45 | 79 | 62 | 30 | 4115 |
| 9/23/2013 | 2013 | 9 | 23 | 106 | 39 | 81 | 60 | 28 | 4143 |
| 9/24/2013 | 2013 | 9 | 24 | 107 | 36 | 77 | 56.5 | 24.5 | 4167.5 |
| 9/25/2013 | 2013 | 9 | 25 | 108 | 39 | 81 | 60 | 28 | 4195.5 |
| 9/26/2013 | 2013 | 9 | 26 | 109 | 40 | 83 | 61.5 | 29.5 | 4225 |
| 9/27/2013 | 2013 | 9 | 27 | 110 | 50 | 80 | 65 | 33 | 4258 |
| 9/28/2013 | 2013 | 9 | 28 | 111 | 25 | 65 | 45 | 13 | 4271 |
| 9/29/2013 | 2013 | 9 | 29 | 112 | 29 | 70 | 49.5 | 17.5 | 4288.5 |
| 9/30/2013 | 2013 | 9 | 30 | 113 | 34 | 84 | 59 | 27 | 4315.5 |
| 10/1/2013 | 2013 | 10 | 1 | 114 | 34 | 86 | 60 | 28 | 4343.5 |
| 10/2/2013 | 2013 | 10 | 2 | 115 | 33 | 86 | 59.5 | 27.5 | 4371 |
| 10/3/2013 | 2013 | 10 | 3 | 116 | 36 | 85 | 60.5 | 28.5 | 4399.5 |
| 10/4/2013 | 2013 | 10 | 4 | 117 | 38 | 77 | 57.5 | 25.5 | 4425 |
| 10/5/2013 | 2013 | 10 | 5 | 118 | 29 | 68 | 48.5 | 16.5 | 4441.5 |
| 10/6/2013 | 2013 | 10 | 6 | 119 | 24 | 61 | 42.5 | 10.5 | 4452 |
| 10/7/2013 | 2013 | 10 | 7 | 120 | 25 | 78 | 51.5 | 19.5 | 4471.5 |
| 10/8/2013 | 2013 | 10 | 8 | 121 | 30 | 78 | 54 | 22 | 4493.5 |
| 10/9/2013 | 2013 | 10 | 9 | 122 | 31 | 79 | 55 | 23 | 4516.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/10/2013 | 2013 | 10 | 10 | 123 | 36 | 75 | 55.5 | 23.5 | 4540 |
| 10/11/2013 | 2013 | 10 | 11 | 124 | 26 | 61 | 43.5 | 11.5 | 4551.5 |
| 10/12/2013 | 2013 | 10 | 12 | 125 | 26 | 62 | 44 | 12 | 4563.5 |
| 10/13/2013 | 2013 | 10 | 13 | 126 | 28 | 67 | 47.5 | 15.5 | 4579 |
| 10/14/2013 | 2013 | 10 | 14 | 127 | 36 | 78 | 57 | 25 | 4604 |
| 10/15/2013 | 2013 | 10 | 15 | 128 | 24 | 66 | 45 | 13 | 4617 |
| 10/16/2013 | 2013 | 10 | 16 | 129 | 20 | 69 | 44.5 | 12.5 | 4629.5 |
| 10/17/2013 | 2013 | 10 | 17 | 130 | 19 | 67 | 43 | 11 | 4640.5 |
| 10/18/2013 | 2013 | 10 | 18 | 131 | 19 | 72 | 45.5 | 13.5 | 4654 |
| 10/19/2013 | 2013 | 10 | 19 | 132 | 18 | 62 | 40 | 8 | 4662 |
| 10/20/2013 | 2013 | 10 | 20 | 133 | 21 | 72 | 46.5 | 14.5 | 4676.5 |
| 10/21/2013 | 2013 | 10 | 21 | 134 | 21 | 74 | 47.5 | 15.5 | 4692 |
| 10/22/2013 | 2013 | 10 | 22 | 135 | 22 | 70 | 46 | 14 | 4706 |
| 10/23/2013 | 2013 | 10 | 23 | 136 | 24 | 74 | 49 | 17 | 4723 |
| 10/24/2013 | 2013 | 10 | 24 | 137 | 26 | 73 | 49.5 | 17.5 | 4740.5 |
| 10/25/2013 | 2013 | 10 | 25 | 138 | 31 | 74 | 52.5 | 20.5 | 4761 |
| 10/26/2013 | 2013 | 10 | 26 | 139 | 30 | 65 | 47.5 | 15.5 | 4776.5 |
| 10/27/2013 | 2013 | 10 | 27 | 140 | 29 | 64 | 46.5 | 14.5 | 4791 |
| 10/28/2013 | 2013 | 10 | 28 | 141 | 32 | 70 | 51 | 19 | 4810 |
| 10/29/2013 | 2013 | 10 | 29 | 142 | 32 | 70 | 51 | 19 | 4829 |
| 10/30/2013 | 2013 | 10 | 30 | 143 | 32 | 68 | 50 | 18 | 4847 |
| 10/31/2013 | 2013 | 10 | 31 | 144 | 26 | 53 | 39.5 | 7.5 | 4854.5 |
| 11/1/2013 | 2013 | 11 | 1 | 145 | 23 | 61 | 42 | 10 | 4864.5 |
| 11/2/2013 | 2013 | 11 | 2 | 146 | 21 | 64 | 42.5 | 10.5 | 4875 |
| 11/3/2013 | 2013 | 11 | 3 | 147 | 22 | 66 | 44 | 12 | 4887 |
| 11/4/2013 | 2013 | 11 | 4 | 148 | 27 | 68 | 47.5 | 15.5 | 4902.5 |
| 11/5/2013 | 2013 | 11 | 5 | 149 | 31 | 67 | 49 | 17 | 4919.5 |
| 11/6/2013 | 2013 | 11 | 6 | 150 | 31 | 67 | 49 | 17 | 4936.5 |
| 11/7/2013 | 2013 | 11 | 7 | 151 | 19 | 56 | 37.5 | 5.5 | 4942 |
| 11/8/2013 | 2013 | 11 | 8 | 152 | 20 | 61 | 40.5 | 8.5 | 4950.5 |
| 11/9/2013 | 2013 | 11 | 9 | 153 | 21 | 71 | 46 | 14 | 4964.5 |
| 11/10/2013 | 2013 | 11 | 10 | 154 | 22 | 73 | 47.5 | 15.5 | 4980 |
| 11/11/2013 | 2013 | 11 | 11 | 155 | 25 | 72 | 48.5 | 16.5 | 4996.5 |
| 11/12/2013 | 2013 | 11 | 12 | 156 | 21 | 72 | 46.5 | 14.5 | 5011 |
| 11/13/2013 | 2013 | 11 | 13 | 157 | 26 | 58 | 42 | 10 | 5021 |
| 11/14/2013 | 2013 | 11 | 14 | 158 | 22 | 59 | 40.5 | 8.5 | 5029.5 |
| 11/15/2013 | 2013 | 11 | 15 | 159 | 22 | 65 | 43.5 | 11.5 | 5041 |
| 11/16/2013 | 2013 | 11 | 16 | 160 | 36 | 62 | 49 | 17 | 5058 |
| 11/17/2013 | 2013 | 11 | 17 | 161 | 38 | 58 | 48 | 16 | 5074 |
| 11/18/2013 | 2013 | 11 | 18 | 162 | 25 | 68 | 46.5 | 14.5 | 5088.5 |
| 11/19/2013 | 2013 | 11 | 19 | 163 | 24 | 64 | 44 | 12 | 5100.5 |
| 11/20/2013 | 2013 | 11 | 20 | 164 | 28 | 71 | 49.5 | 17.5 | 5118 |
| 11/21/2013 | 2013 | 11 | 21 | 165 | 35 | 44 | 39.5 | 7.5 | 5125.5 |
| 11/22/2013 | 2013 | 11 | 22 | 166 | 32 | 52 | 42 | 10 | 5135.5 |
| 11/23/2013 | 2013 | 11 | 23 | 167 | 32 | 52 | 42 | 10 | 5145.5 |
| 11/24/2013 | 2013 | 11 | 24 | 168 | 19 | 31 | 25 | -7 | 5138.5 |
| 11/25/2013 | 2013 | 11 | 25 | 169 | 19 | 34 | 26.5 | -5.5 | 5133 |
| 11/26/2013 | 2013 | 11 | 26 | 170 | 27 | 43 | 35 | 3 | 5136 |
| 11/27/2013 | 2013 | 11 | 27 | 171 | 19 | 49 | 34 | 2 | 5138 |
| 11/28/2013 | 2013 | 11 | 28 | 172 | 20 | 47 | 33.5 | 1.5 | 5139.5 |
| 11/29/2013 | 2013 | 11 | 29 | 173 | 20 | 47 | 33.5 | 1.5 | 5141 |
| 11/30/2013 | 2013 | 11 | 30 | 174 | 21 | 61 | 41 | 9 | 5150 |
| 12/1/2013 | 2013 | 12 | 1 | 175 | 23 | 65 | 44 | 12 | 5162 |
| 12/2/2013 | 2013 | 12 | 2 | 176 | 21 | 53 | 37 | 5 | 5167 |
| 12/3/2013 | 2013 | 12 | 3 | 177 | 21 | 67 | 44 | 12 | 5179 |
| 12/4/2013 | 2013 | 12 | 4 | 178 | 31 | 61 | 46 | 14 | 5193 |
| 12/5/2013 | 2013 | 12 | 5 | 179 | 24 | 54 | 39 | 7 | 5200 |
| 12/6/2013 | 2013 | 12 | 6 | 180 | 17 | 40 | 28.5 | -3.5 | 5196.5 |
| 12/7/2013 | 2013 | 12 | 7 | 181 | 13 | 46 | 29.5 | -2.5 | 5194 |
| 12/8/2013 | 2013 | 12 | 8 | 182 | 24 | 47 | 35.5 | 3.5 | 5197.5 |
| 12/9/2013 | 2013 | 12 | 9 | 183 | 17 | 38 | 27.5 | -4.5 | 5193 |
| 12/10/2013 | 2013 | 12 | 10 | 184 | 0 | 27 | 13.5 | -18.5 | 5174.5 |
| 12/11/2013 | 2013 | 12 | 11 | 185 | 4 | 44 | 24 | -8 | 5166.5 |
| 12/13/2013 | 2013 | 12 | 13 | 186 | 17 | 49 | 33 | 1 | 5167.5 |
| 12/14/2013 | 2013 | 12 | 14 | 187 | 17 | 54 | 35.5 | 3.5 | 5171 |
| 12/15/2013 | 2013 | 12 | 15 | 188 | 13 | 47 | 30 | -2 | 5169 |
| 12/16/2013 | 2013 | 12 | 16 | 189 | 10 | 54 | 32 | 0 | 5169 |
| 12/17/2013 | 2013 | 12 | 17 | 190 | 14 | 64 | 39 | 7 | 5176 |
| 12/18/2013 | 2013 | 12 | 18 | 191 | 15 | 61 | 38 | 6 | 5182 |
| 12/19/2013 | 2013 | 12 | 19 | 192 | 17 | 66 | 41.5 | 9.5 | 5191.5 |
| 12/20/2013 | 2013 | 12 | 20 | 193 | 18 | 58 | 38 | 6 | 5197.5 |
| 12/21/2013 | 2013 | 12 | 21 | 194 | 19 | 54 | 36.5 | 4.5 | 5202 |
| 12/22/2013 | 2013 | 12 | 22 | 195 | 14 | 41 | 27.5 | -4.5 | 5197.5 |
| 12/23/2013 | 2013 | 12 | 23 | 196 | 10 | 48 | 29 | -3 | 5194.5 |
| 12/24/2013 | 2013 | 12 | 24 | 197 | 11 | 53 | 32 | 0 | 5194.5 |
| 12/25/2013 | 2013 | 12 | 25 | 198 | 10 | 65 | 37.5 | 5.5 | 5200 |
| 12/26/2013 | 2013 | 12 | 26 | 199 | 7 | 52 | 29.5 | -2.5 | 5197.5 |
| 12/27/2013 | 2013 | 12 | 27 | 200 | 8 | 54 | 31 | -1 | 5196.5 |
| 12/28/2013 | 2013 | 12 | 28 | 201 | 9 | 63 | 36 | 4 | 5200.5 |
| 12/29/2013 | 2013 | 12 | 29 | 202 | 13 | 56 | 34.5 | 2.5 | 5203 |
| 12/30/2013 | 2013 | 12 | 30 | 203 | 9 | 51 | 30 | -2 | 5201 |
| 12/31/2013 | 2013 | 12 | 31 | 204 | 9 | 55 | 32 | 0 | 5201 |
| 1/1/2014 | 2014 | 1 | 1 | 205 | 12 | 63 | 37.5 | 5.5 | 5206.5 |
| 1/2/2014 | 2014 | 1 | 2 | 206 | 7 | 54 | 30.5 | -1.5 | 5205 |
| 1/3/2014 | 2014 | 1 | 3 | 207 | 10 | 62 | 36 | 4 | 5209 |
| 1/4/2014 | 2014 | 1 | 4 | 208 | 12 | 61 | 36.5 | 4.5 | 5213.5 |
| 1/5/2014 | 2014 | 1 | 5 | 209 | 5 | 60 | 32.5 | 0.5 | 5214 |
| 1/6/2014 | 2014 | 1 | 6 | 210 | 3 | 44 | 23.5 | -8.5 | 5205.5 |
| 1/7/2014 | 2014 | 1 | 7 | 211 | 3 | 44 | 23.5 | -8.5 | 5197 |
| 1/8/2014 | 2014 | 1 | 8 | 212 | 9 | 49 | 29 | -3 | 5194 |
| 1/9/2014 | 2014 | 1 | 9 | 213 | 10 | 60 | 35 | 3 | 5197 |
| 1/10/2014 | 2014 | 1 | 10 | 214 | 12 | 57 | 34.5 | 2.5 | 5199.5 |
| 1/11/2014 | 2014 | 1 | 11 | 215 | 15 | 58 | 36.5 | 4.5 | 5204 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/12/2014 | 2014 | 1 | 12 | 216 | 18 | 61 | 39.5 | 7.5 | 5211.5 |
| 1/13/2014 | 2014 | 1 | 13 | 217 | 12 | 58 | 35 | 3 | 5214.5 |
| 1/14/2014 | 2014 | 1 | 14 | 218 | 13 | 55 | 34 | 2 | 5216.5 |
| 1/15/2014 | 2014 | 1 | 15 | 219 | 10 | 57 | 33.5 | 1.5 | 5218 |
| 1/16/2014 | 2014 | 1 | 16 | 220 | 10 | 60 | 35 | 3 | 5221 |
| 1/17/2014 | 2014 | 1 | 17 | 221 | 10 | 58 | 34 | 2 | 5223 |
| 1/18/2014 | 2014 | 1 | 18 | 222 | 11 | 59 | 35 | 3 | 5226 |
| 1/19/2014 | 2014 | 1 | 19 | 223 | 9 | 64 | 36.5 | 4.5 | 5230.5 |
| 1/20/2014 | 2014 | 1 | 20 | 224 | 12 | 67 | 39.5 | 7.5 | 5238 |
| 1/21/2014 | 2014 | 1 | 21 | 225 | 8 | 65 | 36.5 | 4.5 | 5242.5 |
| 1/22/2014 | 2014 | 1 | 22 | 226 | 11 | 67 | 39 | 7 | 5249.5 |
| 1/23/2014 | 2014 | 1 | 23 | 227 | 7 | 55 | 31 | -1 | 5248.5 |
| 1/24/2014 | 2014 | 1 | 24 | 228 | 6 | 40 | 23 | -9 | 5239.5 |
| 1/25/2014 | 2014 | 1 | 25 | 229 | 9 | 54 | 31.5 | -0.5 | 5239 |
| 1/26/2014 | 2014 | 1 | 26 | 230 | 8 | 58 | 33 | 1 | 5240 |
| 1/27/2014 | 2014 | 1 | 27 | 231 | 12 | 54 | 33 | 1 | 5241 |
| 1/28/2014 | 2014 | 1 | 28 | 232 | 15 | 65 | 40 | 8 | 5249 |
| 1/29/2014 | 2014 | 1 | 29 | 233 | 9 | 57 | 33 | 1 | 5250 |
| 1/30/2014 | 2014 | 1 | 30 | 234 | 23 | 57 | 40 | 8 | 5258 |
| 1/31/2014 | 2014 | 1 | 31 | 235 | 35 | 64 | 49.5 | 17.5 | 5275.5 |
| 2/1/2014 | 2014 | 2 | 1 | 236 | 27 | 51 | 39 | 7 | 5282.5 |
| 2/2/2014 | 2014 | 2 | 2 | 237 | 9 | 50 | 29.5 | -2.5 | 5280 |
| 2/3/2014 | 2014 | 2 | 3 | 238 | 11 | 49 | 30 | -2 | 5278 |
| 2/4/2014 | 2014 | 2 | 4 | 239 | 13 | 41 | 27 | -5 | 5273 |
| 2/5/2014 | 2014 | 2 | 5 | 240 | 19 | 40 | 29.5 | -2.5 | 5270.5 |
| 2/6/2014 | 2014 | 2 | 6 | 241 | 17 | 36 | 26.5 | -5.5 | 5265 |
| 2/7/2014 | 2014 | 2 | 7 | 242 | 21 | 37 | 29 | -3 | 5262 |
| 2/8/2014 | 2014 | 2 | 8 | 243 | 21 | 48 | 34.5 | 2.5 | 5264.5 |
| 2/9/2014 | 2014 | 2 | 9 | 244 | 28 | 63 | 45.5 | 13.5 | 5278 |
| 2/10/2014 | 2014 | 2 | 10 | 245 | 23 | 70 | 46.5 | 14.5 | 5292.5 |
| 2/11/2014 | 2014 | 2 | 11 | 246 | 19 | 65 | 42 | 10 | 5302.5 |
| 2/12/2014 | 2014 | 2 | 12 | 247 | 18 | 61 | 39.5 | 7.5 | 5310 |
| 2/13/2014 | 2014 | 2 | 13 | 248 | 23 | 67 | 45 | 13 | 5323 |
| 2/14/2014 | 2014 | 2 | 14 | 249 | 30 | 71 | 50.5 | 18.5 | 5341.5 |
| 2/15/2014 | 2014 | 2 | 15 | 250 | 22 | 74 | 48 | 16 | 5357.5 |
| 2/16/2014 | 2014 | 2 | 16 | 251 | 25 | 73 | 49 | 17 | 5374.5 |
| 2/17/2014 | 2014 | 2 | 17 | 252 | 20 | 73 | 46.5 | 14.5 | 5389 |
| 2/18/2014 | 2014 | 2 | 18 | 253 | 24 | 68 | 46 | 14 | 5403 |
| 2/19/2014 | 2014 | 2 | 19 | 254 | 26 | 74 | 50 | 18 | 5421 |
| 2/20/2014 | 2014 | 2 | 20 | 255 | 21 | 71 | 46 | 14 | 5435 |
| 2/21/2014 | 2014 | 2 | 21 | 256 | 10 | 53 | 31.5 | -0.5 | 5434.5 |
| 2/22/2014 | 2014 | 2 | 22 | 257 | 15 | 65 | 40 | 8 | 5442.5 |
| 2/23/2014 | 2014 | 2 | 23 | 258 | 17 | 66 | 41.5 | 9.5 | 5452 |
| 2/24/2014 | 2014 | 2 | 24 | 259 | 18 | 71 | 44.5 | 12.5 | 5464.5 |
| 2/25/2014 | 2014 | 2 | 25 | 260 | 17 | 73 | 45 | 13 | 5477.5 |
| 2/26/2014 | 2014 | 2 | 26 | 261 | 21 | 65 | 43 | 11 | 5488.5 |
| 2/27/2014 | 2014 | 2 | 27 | 262 | 33 | 70 | 51.5 | 19.5 | 5508 |
| 2/28/2014 | 2014 | 2 | 28 | 263 | 23 | 61 | 42 | 10 | 5518 |
| 3/1/2014 | 2014 | 3 | 1 | 264 | 38 | 67 | 52.5 | 20.5 | 5538.5 |
| 3/2/2014 | 2014 | 3 | 2 | 265 | 33 | 50 | 41.5 | 9.5 | 5548 |
| 3/3/2014 | 2014 | 3 | 3 | 266 | 24 | 57 | 40.5 | 8.5 | 5556.5 |
| 3/4/2014 | 2014 | 3 | 4 | 267 | 20 | 61 | 40.5 | 8.5 | 5565 |
| 3/5/2014 | 2014 | 3 | 5 | 268 | 27 | 60 | 43.5 | 11.5 | 5576.5 |
| 3/6/2014 | 2014 | 3 | 6 | 269 | 20 | 65 | 42.5 | 10.5 | 5587 |
| 3/7/2014 | 2014 | 3 | 7 | 270 | 32 | 70 | 51 | 19 | 5606 |
| 3/8/2014 | 2014 | 3 | 8 | 271 | 21 | 64 | 42.5 | 10.5 | 5616.5 |
| 3/9/2014 | 2014 | 3 | 9 | 272 | 15 | 65 | 40 | 8 | 5624.5 |
| 3/10/2014 | 2014 | 3 | 10 | 273 | 16 | 70 | 43 | 11 | 5635.5 |
| 3/11/2014 | 2014 | 3 | 11 | 274 | 32 | 79 | 55.5 | 23.5 | 5659 |
| 3/12/2014 | 2014 | 3 | 12 | 275 | 17 | 66 | 41.5 | 9.5 | 5668.5 |
| 3/13/2014 | 2014 | 3 | 13 | 276 | 20 | 54 | 37 | 5 | 5673.5 |
| 3/15/2014 | 2014 | 3 | 15 | 277 | 21 | 64 | 42.5 | 10.5 | 5684 |
| 3/16/2014 | 2014 | 3 | 16 | 278 | 12 | 56 | 34 | 2 | 5686 |
| 3/17/2014 | 2014 | 3 | 17 | 279 | 19 | 67 | 43 | 11 | 5697 |
| 3/18/2014 | 2014 | 3 | 18 | 280 | 22 | 71 | 46.5 | 14.5 | 5711.5 |
| 3/19/2014 | 2014 | 3 | 19 | 281 | 11 | 59 | 35 | 3 | 5714.5 |
| 3/20/2014 | 2014 | 3 | 20 | 282 | 12 | 64 | 38 | 6 | 5720.5 |
| 3/21/2014 | 2014 | 3 | 21 | 283 | 24 | 74 | 49 | 17 | 5737.5 |
| 3/22/2014 | 2014 | 3 | 22 | 284 | 28 | 70 | 49 | 17 | 5754.5 |
| 3/23/2014 | 2014 | 3 | 23 | 285 | 24 | 67 | 45.5 | 13.5 | 5768 |
| 3/24/2014 | 2014 | 3 | 24 | 286 | 21 | 71 | 46 | 14 | 5782 |
| 3/25/2014 | 2014 | 3 | 25 | 287 | 19 | 72 | 45.5 | 13.5 | 5795.5 |
| 3/26/2014 | 2014 | 3 | 26 | 288 | 23 | 67 | 45 | 13 | 5808.5 |
| 3/27/2014 | 2014 | 3 | 27 | 289 | 34 | 66 | 50 | 18 | 5826.5 |
| 3/28/2014 | 2014 | 3 | 28 | 290 | 34 | 63 | 48.5 | 16.5 | 5843 |
| 3/29/2014 | 2014 | 3 | 29 | 291 | 20 | 68 | 44 | 12 | 5855 |
| 3/30/2014 | 2014 | 3 | 30 | 292 | 25 | 73 | 49 | 17 | 5872 |
| 3/31/2014 | 2014 | 3 | 31 | 293 | 21 | 70 | 45.5 | 13.5 | 5885.5 |
| 4/1/2014 | 2014 | 4 | 1 | 294 | 30 | 68 | 49 | 17 | 5902.5 |
| 4/2/2014 | 2014 | 4 | 2 | 295 | 32 | 69 | 50.5 | 18.5 | 5921 |
| 4/3/2014 | 2014 | 4 | 3 | 296 | 28 | 64 | 46 | 14 | 5935 |
| 4/4/2014 | 2014 | 4 | 4 | 297 | 15 | 57 | 36 | 4 | 5939 |
| 4/5/2014 | 2014 | 4 | 5 | 298 | 28 | 61 | 44.5 | 12.5 | 5951.5 |
| 4/7/2014 | 2014 | 4 | 7 | 299 | 29 | 63 | 46 | 14 | 5965.5 |
| 4/9/2014 | 2014 | 4 | 9 | 300 | 25 | 79 | 52 | 20 | 5985.5 |
| 4/10/2014 | 2014 | 4 | 10 | 301 | 35 | 84 | 59.5 | 27.5 | 6013 |
| 4/11/2014 | 2014 | 4 | 11 | 302 | 33 | 83 | 58 | 26 | 6039 |
| 4/12/2014 | 2014 | 4 | 12 | 303 | 36 | 82 | 59 | 27 | 6066 |
| 4/13/2014 | 2014 | 4 | 13 | 304 | 36 | 73 | 54.5 | 22.5 | 6088.5 |
| 4/14/2014 | 2014 | 4 | 14 | 305 | 21 | 72 | 46.5 | 14.5 | 6103 |
| 4/15/2014 | 2014 | 4 | 15 | 306 | 17 | 60 | 38.5 | 6.5 | 6109.5 |
| 4/16/2014 | 2014 | 4 | 16 | 307 | 25 | 75 | 50 | 18 | 6127.5 |
| 4/17/2014 | 2014 | 4 | 17 | 308 | 27 | 76 | 51.5 | 19.5 | 6147 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/18/2014 | 2014 | 4 | 18 | 309 | 37 | 75 | 56 | 24 | 6171 |
| 4/19/2014 | 2014 | 4 | 19 | 310 | 33 | 76 | 54.5 | 22.5 | 6193.5 |
| 4/20/2014 | 2014 | 4 | 20 | 311 | 33 | 64 | 48.5 | 16.5 | 6210 |
| 4/21/2014 | 2014 | 4 | 21 | 312 | 33 | 77 | 55 | 23 | 6233 |
| 4/22/2014 | 2014 | 4 | 22 | 313 | 47 | 82 | 64.5 | 32.5 | 6265.5 |
| 4/23/2014 | 2014 | 4 | 23 | 314 | 44 | 80 | 62 | 30 | 6295.5 |
| 4/24/2014 | 2014 | 4 | 24 | 315 | 31 | 73 | 52 | 20 | 6315.5 |
| 4/25/2014 | 2014 | 4 | 25 | 316 | 29 | 78 | 53.5 | 21.5 | 6337 |
| 4/26/2014 | 2014 | 4 | 26 | 317 | 38 | 78 | 58 | 26 | 6363 |
| 4/28/2014 | 2014 | 4 | 28 | 318 | 31 | 68 | 49.5 | 17.5 | 6380.5 |
| 4/29/2014 | 2014 | 4 | 29 | 319 | 29 | 64 | 46.5 | 14.5 | 6395 |
| 4/30/2014 | 2014 | 4 | 30 | 320 | 23 | 61 | 42 | 10 | 6405 |
| 5/1/2014 | 2014 | 5 | 1 | 321 | 30 | 64 | 47 | 15 | 6420 |
| 5/2/2014 | 2014 | 5 | 2 | 322 | 28 | 70 | 49 | 17 | 6437 |
| 5/4/2014 | 2014 | 5 | 4 | 323 | 30 | 82 | 56 | 24 | 6461 |
| 5/5/2014 | 2014 | 5 | 5 | 324 | 37 | 84 | 60.5 | 28.5 | 6489.5 |
| 5/6/2014 | 2014 | 5 | 6 | 325 | 41 | 81 | 61 | 29 | 6518.5 |
| 5/7/2014 | 2014 | 5 | 7 | 326 | 30 | 73 | 51.5 | 19.5 | 6538 |
| 5/8/2014 | 2014 | 5 | 8 | 327 | 27 | 70 | 48.5 | 16.5 | 6554.5 |
| 5/9/2014 | 2014 | 5 | 9 | 328 | 28 | 62 | 45 | 13 | 6567.5 |
| 5/10/2014 | 2014 | 5 | 10 | 329 | 39 | 75 | 57 | 25 | 6592.5 |
| 5/11/2014 | 2014 | 5 | 11 | 330 | 43 | 79 | 61 | 29 | 6621.5 |
| 5/12/2014 | 2014 | 5 | 12 | 331 | 32 | 69 | 50.5 | 18.5 | 6640 |
| 5/13/2014 | 2014 | 5 | 13 | 332 | 26 | 62 | 44 | 12 | 6652 |
| 5/14/2014 | 2014 | 5 | 14 | 333 | 28 | 65 | 46.5 | 14.5 | 6666.5 |
| 5/15/2014 | 2014 | 5 | 15 | 334 | 25 | 70 | 47.5 | 15.5 | 6682 |
| 5/16/2014 | 2014 | 5 | 16 | 335 | 32 | 80 | 56 | 24 | 6706 |
| 5/17/2014 | 2014 | 5 | 17 | 336 | 38 | 87 | 62.5 | 30.5 | 6736.5 |
| 5/18/2014 | 2014 | 5 | 18 | 337 | 49 | 89 | 69 | 37 | 6773.5 |
| 5/19/2014 | 2014 | 5 | 19 | 338 | 37 | 84 | 60.5 | 28.5 | 6802 |
| 5/20/2014 | 2014 | 5 | 20 | 339 | 34 | 84 | 59 | 27 | 6829 |
| 5/22/2014 | 2014 | 5 | 22 | 340 | 29 | 83 | 56 | 24 | 6853 |
| 5/23/2014 | 2014 | 5 | 23 | 341 | 43 | 80 | 61.5 | 29.5 | 6882.5 |
| 5/24/2014 | 2014 | 5 | 24 | 342 | 43 | 80 | 61.5 | 29.5 | 6912 |
| 5/25/2014 | 2014 | 5 | 25 | 343 | 33 | 60 | 46.5 | 14.5 | 6926.5 |
| 5/26/2014 | 2014 | 5 | 26 | 344 | 33 | 63 | 48 | 16 | 6942.5 |
| 5/27/2014 | 2014 | 5 | 27 | 345 | 39 | 79 | 59 | 27 | 6969.5 |
| 5/28/2014 | 2014 | 5 | 28 | 346 | 39 | 90 | 64.5 | 32.5 | 7002 |
| 5/29/2014 | 2014 | 5 | 29 | 347 | 60 | 91 | 75.5 | 43.5 | 7045.5 |
| 5/30/2014 | 2014 | 5 | 30 | 348 | 53 | 86 | 69.5 | 37.5 | 7083 |
| 5/31/2014 | 2014 | 5 | 31 | 349 | 47 | 90 | 68.5 | 36.5 | 7119.5 |
| 6/2/2014 | 2014 | 6 | 2 | 1 | 47 | 91 | 69 | 37 | 37 |
| 6/3/2014 | 2014 | 6 | 3 | 2 | 51 | 97 | 74 | 42 | 79 |
| 6/4/2014 | 2014 | 6 | 4 | 3 | 49 | 97 | 73 | 41 | 120 |
| 6/5/2014 | 2014 | 6 | 5 | 4 | 40 | 94 | 67 | 35 | 155 |
| 6/6/2014 | 2014 | 6 | 6 | 5 | 40 | 94 | 67 | 35 | 190 |
| 6/7/2014 | 2014 | 6 | 7 | 6 | 40 | 97 | 68.5 | 36.5 | 226.5 |
| 6/8/2014 | 2014 | 6 | 8 | 7 | 51 | 91 | 71 | 39 | 265.5 |
| 6/9/2014 | 2014 | 6 | 9 | 8 | 47 | 92 | 69.5 | 37.5 | 303 |
| 6/10/2014 | 2014 | 6 | 10 | 9 | 39 | 89 | 64 | 32 | 335 |
| 6/11/2014 | 2014 | 6 | 11 | 10 | 51 | 93 | 72 | 40 | 375 |
| 6/12/2014 | 2014 | 6 | 12 | 11 | 38 | 90 | 64 | 32 | 407 |
| 6/13/2014 | 2014 | 6 | 13 | 12 | 55 | 92 | 73.5 | 41.5 | 448.5 |
| 6/14/2014 | 2014 | 6 | 14 | 13 | 50 | 90 | 70 | 38 | 486.5 |
| 6/15/2014 | 2014 | 6 | 15 | 14 | 40 | 88 | 64 | 32 | 518.5 |
| 6/16/2014 | 2014 | 6 | 16 | 15 | 47 | 87 | 67 | 35 | 553.5 |
| 6/17/2014 | 2014 | 6 | 17 | 16 | 50 | 88 | 69 | 37 | 590.5 |
| 6/18/2014 | 2014 | 6 | 18 | 17 | 50 | 87 | 68.5 | 36.5 | 627 |
| 6/19/2014 | 2014 | 6 | 19 | 18 | 45 | 84 | 64.5 | 32.5 | 659.5 |
| 6/20/2014 | 2014 | 6 | 20 | 19 | 45 | 92 | 68.5 | 36.5 | 696 |
| 6/21/2014 | 2014 | 6 | 21 | 20 | 46 | 98 | 72 | 40 | 736 |
| 6/22/2014 | 2014 | 6 | 22 | 21 | 59 | 95 | 77 | 45 | 781 |
| 6/23/2014 | 2014 | 6 | 23 | 22 | 51 | 96 | 73.5 | 41.5 | 822.5 |
| 6/24/2014 | 2014 | 6 | 24 | 23 | 47 | 96 | 71.5 | 39.5 | 862 |
| 6/25/2014 | 2014 | 6 | 25 | 24 | 46 | 95 | 70.5 | 38.5 | 900.5 |
| 6/26/2014 | 2014 | 6 | 26 | 25 | 47 | 94 | 70.5 | 38.5 | 939 |
| 6/27/2014 | 2014 | 6 | 27 | 26 | 61 | 94 | 77.5 | 45.5 | 984.5 |
| 6/28/2014 | 2014 | 6 | 28 | 27 | 58 | 92 | 75 | 43 | 1027.5 |
| 6/29/2014 | 2014 | 6 | 29 | 28 | 53 | 96 | 74.5 | 42.5 | 1070 |
| 6/30/2014 | 2014 | 6 | 30 | 29 | 55 | 99 | 77 | 45 | 1115 |
| 7/1/2014 | 2014 | 7 | 1 | 30 | 57 | 101 | 79 | 47 | 1162 |
| 7/2/2014 | 2014 | 7 | 2 | 31 | 60 | 99 | 79.5 | 47.5 | 1209.5 |
| 7/3/2014 | 2014 | 7 | 3 | 32 | 58 | 89 | 73.5 | 41.5 | 1251 |
| 7/4/2014 | 2014 | 7 | 4 | 33 | 55 | 95 | 75 | 43 | 1294 |
| 7/5/2014 | 2014 | 7 | 5 | 34 | 56 | 92 | 74 | 42 | 1336 |
| 7/6/2014 | 2014 | 7 | 6 | 35 | 53 | 90 | 71.5 | 39.5 | 1375.5 |
| 7/7/2014 | 2014 | 7 | 7 | 36 | 53 | 92 | 72.5 | 40.5 | 1416 |
| 7/8/2014 | 2014 | 7 | 8 | 37 | 53 | 94 | 73.5 | 41.5 | 1457.5 |
| 7/9/2014 | 2014 | 7 | 9 | 38 | 56 | 91 | 73.5 | 41.5 | 1499 |
| 7/10/2014 | 2014 | 7 | 10 | 39 | 55 | 85 | 70 | 38 | 1537 |
| 7/11/2014 | 2014 | 7 | 11 | 40 | 60 | 92 | 76 | 44 | 1581 |
| 7/12/2014 | 2014 | 7 | 12 | 41 | 55 | 94 | 74.5 | 42.5 | 1623.5 |
| 7/13/2014 | 2014 | 7 | 13 | 42 | 59 | 92 | 75.5 | 43.5 | 1667 |
| 7/14/2014 | 2014 | 7 | 14 | 43 | 59 | 92 | 75.5 | 43.5 | 1710.5 |
| 7/15/2014 | 2014 | 7 | 15 | 44 | 57 | 95 | 76 | 44 | 1754.5 |
| 7/16/2014 | 2014 | 7 | 16 | 45 | 56 | 88 | 72 | 40 | 1794.5 |
| 7/17/2014 | 2014 | 7 | 17 | 46 | 55 | 88 | 71.5 | 39.5 | 1834 |
| 7/18/2014 | 2014 | 7 | 18 | 47 | 56 | 92 | 74 | 42 | 1876 |
| 7/19/2014 | 2014 | 7 | 19 | 48 | 60 | 97 | 78.5 | 46.5 | 1922.5 |
| 7/20/2014 | 2014 | 7 | 20 | 49 | 66 | 92 | 79 | 47 | 1969.5 |
| 7/21/2014 | 2014 | 7 | 21 | 50 | 57 | 95 | 76 | 44 | 2013.5 |
| 7/22/2014 | 2014 | 7 | 22 | 51 | 62 | 93 | 77.5 | 45.5 | 2059 |
| 7/23/2014 | 2014 | 7 | 23 | 52 | 62 | 93 | 77.5 | 45.5 | 2104.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/24/2014 | 2014 | 7 | 24 | 53 | 56 | 98 | 77 | 45 | 2149.5 |
| 7/25/2014 | 2014 | 7 | 25 | 54 | 57 | 92 | 74.5 | 42.5 | 2192 |
| 7/26/2014 | 2014 | 7 | 26 | 55 | 60 | 96 | 78 | 46 | 2238 |
| 7/27/2014 | 2014 | 7 | 27 | 56 | 58 | 101 | 79.5 | 47.5 | 2285.5 |
| 7/28/2014 | 2014 | 7 | 28 | 57 | 59 | 95 | 77 | 45 | 2330.5 |
| 7/29/2014 | 2014 | 7 | 29 | 58 | 57 | 77 | 67 | 35 | 2365.5 |
| 7/30/2014 | 2014 | 7 | 30 | 59 | 57 | 89 | 73 | 41 | 2406.5 |
| 7/31/2014 | 2014 | 7 | 31 | 60 | 57 | 89 | 73 | 41 | 2447.5 |
| 8/1/2014 | 2014 | 8 | 1 | 61 | 55 | 82 | 68.5 | 36.5 | 2484 |
| 8/2/2014 | 2014 | 8 | 2 | 62 | 55 | 78 | 66.5 | 34.5 | 2518.5 |
| 8/3/2014 | 2014 | 8 | 3 | 63 | 53 | 78 | 65.5 | 33.5 | 2552 |
| 8/4/2014 | 2014 | 8 | 4 | 64 | 54 | 78 | 66 | 34 | 2586 |
| 8/5/2014 | 2014 | 8 | 5 | 65 | 51 | 84 | 67.5 | 35.5 | 2621.5 |
| 8/6/2014 | 2014 | 8 | 6 | 66 | 51 | 84 | 67.5 | 35.5 | 2657 |
| 8/7/2014 | 2014 | 8 | 7 | 67 | 53 | 93 | 73 | 41 | 2698 |
| 8/8/2014 | 2014 | 8 | 8 | 68 | 47 | 81 | 64 | 32 | 2730 |
| 8/9/2014 | 2014 | 8 | 9 | 69 | 47 | 81 | 64 | 32 | 2762 |
| 8/10/2014 | 2014 | 8 | 10 | 70 | 47 | 81 | 64 | 32 | 2794 |
| 8/11/2014 | 2014 | 8 | 11 | 71 | 50 | 94 | 72 | 40 | 2834 |
| 8/12/2014 | 2014 | 8 | 12 | 72 | 50 | 94 | 72 | 40 | 2874 |
| 8/13/2014 | 2014 | 8 | 13 | 73 | 57 | 87 | 72 | 40 | 2914 |
| 8/14/2014 | 2014 | 8 | 14 | 74 | 55 | 75 | 65 | 33 | 2947 |
| 8/15/2014 | 2014 | 8 | 15 | 75 | 57 | 80 | 68.5 | 36.5 | 2983.5 |
| 8/16/2014 | 2014 | 8 | 16 | 76 | 57 | 86 | 71.5 | 39.5 | 3023 |
| 8/17/2014 | 2014 | 8 | 17 | 77 | 52 | 94 | 73 | 41 | 3064 |
| 8/18/2014 | 2014 | 8 | 18 | 78 | 57 | 93 | 75 | 43 | 3107 |
| 8/19/2014 | 2014 | 8 | 19 | 79 | 52 | 87 | 69.5 | 37.5 | 3144.5 |
| 8/20/2014 | 2014 | 8 | 20 | 80 | 51 | 81 | 66 | 34 | 3178.5 |
| 8/21/2014 | 2014 | 8 | 21 | 81 | 50 | 82 | 66 | 34 | 3212.5 |
| 8/22/2014 | 2014 | 8 | 22 | 82 | 56 | 82 | 69 | 37 | 3249.5 |
| 8/23/2014 | 2014 | 8 | 23 | 83 | 48 | 73 | 60.5 | 28.5 | 3278 |
| 8/24/2014 | 2014 | 8 | 24 | 84 | 48 | 83 | 65.5 | 33.5 | 3311.5 |
| 8/25/2014 | 2014 | 8 | 25 | 85 | 50 | 85 | 67.5 | 35.5 | 3347 |
| 8/26/2014 | 2014 | 8 | 26 | 86 | 55 | 87 | 71 | 39 | 3386 |
| 8/27/2014 | 2014 | 8 | 27 | 87 | 48 | 76 | 62 | 30 | 3416 |
| 8/28/2014 | 2014 | 8 | 28 | 88 | 44 | 81 | 62.5 | 30.5 | 3446.5 |
| 8/29/2014 | 2014 | 8 | 29 | 89 | 45 | 82 | 63.5 | 31.5 | 3478 |
| 8/31/2014 | 2014 | 8 | 31 | 90 | 51 | 91 | 71 | 39 | 3517 |
| 9/1/2014 | 2014 | 9 | 1 | 91 | 53 | 89 | 71 | 39 | 3556 |
| 9/2/2014 | 2014 | 9 | 2 | 92 | 45 | 93 | 69 | 37 | 3593 |
| 9/4/2014 | 2014 | 9 | 4 | 93 | 47 | 92 | 69.5 | 37.5 | 3630.5 |
| 9/5/2014 | 2014 | 9 | 5 | 94 | 51 | 90 | 70.5 | 38.5 | 3669 |
| 9/6/2014 | 2014 | 9 | 6 | 95 | 56 | 88 | 72 | 40 | 3709 |
| 9/7/2014 | 2014 | 9 | 7 | 96 | 50 | 84 | 67 | 35 | 3744 |
| 9/8/2014 | 2014 | 9 | 8 | 97 | 49 | 84 | 66.5 | 34.5 | 3778.5 |
| 9/9/2014 | 2014 | 9 | 9 | 98 | 49 | 83 | 66 | 34 | 3812.5 |
| 9/10/2014 | 2014 | 9 | 10 | 99 | 51 | 81 | 66 | 34 | 3846.5 |
| 9/11/2014 | 2014 | 9 | 11 | 100 | 43 | 85 | 64 | 32 | 3878.5 |
| 9/12/2014 | 2014 | 9 | 12 | 101 | 43 | 86 | 64.5 | 32.5 | 3911 |
| 9/13/2014 | 2014 | 9 | 13 | 102 | 47 | 83 | 65 | 33 | 3944 |
| 9/14/2014 | 2014 | 9 | 14 | 103 | 47 | 83 | 65 | 33 | 3977 |
| 9/15/2014 | 2014 | 9 | 15 | 104 | 47 | 83 | 65 | 33 | 4010 |
| 9/16/2014 | 2014 | 9 | 16 | 105 | 53 | 86 | 69.5 | 37.5 | 4047.5 |
| 9/17/2014 | 2014 | 9 | 17 | 106 | 56 | 77 | 66.5 | 34.5 | 4082 |
| 9/18/2014 | 2014 | 9 | 18 | 107 | 45 | 69 | 57 | 25 | 4107 |
| 9/19/2014 | 2014 | 9 | 19 | 108 | 45 | 69 | 57 | 25 | 4132 |
| 9/20/2014 | 2014 | 9 | 20 | 109 | 46 | 91 | 68.5 | 36.5 | 4168.5 |
| 9/21/2014 | 2014 | 9 | 21 | 110 | 54 | 88 | 71 | 39 | 4207.5 |
| 9/22/2014 | 2014 | 9 | 22 | 111 | 53 | 80 | 66.5 | 34.5 | 4242 |
| 9/23/2014 | 2014 | 9 | 23 | 112 | 51 | 82 | 66.5 | 34.5 | 4276.5 |
| 9/24/2014 | 2014 | 9 | 24 | 113 | 43 | 85 | 64 | 32 | 4308.5 |
| 9/25/2014 | 2014 | 9 | 25 | 114 | 47 | 88 | 67.5 | 35.5 | 4344 |
| 9/26/2014 | 2014 | 9 | 26 | 115 | 51 | 88 | 69.5 | 37.5 | 4381.5 |
| 9/27/2014 | 2014 | 9 | 27 | 116 | 50 | 84 | 67 | 35 | 4416.5 |
| 9/28/2014 | 2014 | 9 | 28 | 117 | 53 | 78 | 65.5 | 33.5 | 4450 |
| 9/29/2014 | 2014 | 9 | 29 | 118 | 42 | 78 | 60 | 28 | 4478 |
| 9/30/2014 | 2014 | 9 | 30 | 119 | 33 | 73 | 53 | 21 | 4499 |
| 10/1/2014 | 2014 | 10 | 1 | 120 | 33 | 78 | 55.5 | 23.5 | 4522.5 |
| 10/2/2014 | 2014 | 10 | 2 | 121 | 35 | 79 | 57 | 25 | 4547.5 |
| 10/3/2014 | 2014 | 10 | 3 | 122 | 29 | 73 | 51 | 19 | 4566.5 |
| 10/4/2014 | 2014 | 10 | 4 | 123 | 30 | 81 | 55.5 | 23.5 | 4590 |
| 10/5/2014 | 2014 | 10 | 5 | 124 | 32 | 81 | 56.5 | 24.5 | 4614.5 |
| 10/6/2014 | 2014 | 10 | 6 | 125 | 34 | 80 | 57 | 25 | 4639.5 |
| 10/7/2014 | 2014 | 10 | 7 | 126 | 34 | 84 | 59 | 27 | 4666.5 |
| 10/8/2014 | 2014 | 10 | 8 | 127 | 36 | 84 | 60 | 28 | 4694.5 |
| 10/9/2014 | 2014 | 10 | 9 | 128 | 50 | 76 | 63 | 31 | 4725.5 |
| 10/10/2014 | 2014 | 10 | 10 | 129 | 45 | 68 | 56.5 | 24.5 | 4750 |
| 10/11/2014 | 2014 | 10 | 11 | 130 | 44 | 73 | 58.5 | 26.5 | 4776.5 |
| 10/12/2014 | 2014 | 10 | 12 | 131 | 39 | 70 | 54.5 | 22.5 | 4799 |
| 10/13/2014 | 2014 | 10 | 13 | 132 | 33 | 73 | 53 | 21 | 4820 |
| 10/14/2014 | 2014 | 10 | 14 | 133 | 27 | 98 | 62.5 | 30.5 | 4850.5 |
| 10/15/2014 | 2014 | 10 | 15 | 134 | 28 | 77 | 52.5 | 20.5 | 4871 |
| 10/16/2014 | 2014 | 10 | 16 | 135 | 30 | 78 | 54 | 22 | 4893 |
| 10/17/2014 | 2014 | 10 | 17 | 136 | 37 | 83 | 60 | 28 | 4921 |
| 10/18/2014 | 2014 | 10 | 18 | 137 | 38 | 78 | 58 | 26 | 4947 |
| 10/19/2014 | 2014 | 10 | 19 | 138 | 47 | 72 | 59.5 | 27.5 | 4974.5 |
| 10/20/2014 | 2014 | 10 | 20 | 139 | 34 | 69 | 51.5 | 19.5 | 4994 |
| 10/21/2014 | 2014 | 10 | 21 | 140 | 35 | 71 | 53 | 21 | 5015 |
| 10/22/2014 | 2014 | 10 | 22 | 141 | 35 | 69 | 52 | 20 | 5035 |
| 10/23/2014 | 2014 | 10 | 23 | 142 | 32 | 75 | 53.5 | 21.5 | 5056.5 |
| 10/24/2014 | 2014 | 10 | 24 | 143 | 30 | 70 | 50 | 18 | 5074.5 |
| 10/25/2014 | 2014 | 10 | 25 | 144 | 31 | 71 | 51 | 19 | 5093.5 |
| 10/26/2014 | 2014 | 10 | 26 | 145 | 32 | 75 | 53.5 | 21.5 | 5115 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/27/2014 | 2014 | 10 | 27 | 146 | 33 | 77 | 55 | 23 | 5138 |
| 10/28/2014 | 2014 | 10 | 28 | 147 | 30 | 75 | 52.5 | 20.5 | 5158.5 |
| 10/29/2014 | 2014 | 10 | 29 | 148 | 28 | 77 | 52.5 | 20.5 | 5179 |
| 10/30/2014 | 2014 | 10 | 30 | 149 | 25 | 78 | 51.5 | 19.5 | 5198.5 |
| 10/31/2014 | 2014 | 10 | 31 | 150 | 25 | 74 | 49.5 | 17.5 | 5216 |
| 11/1/2014 | 2014 | 11 | 1 | 151 | 25 | 66 | 45.5 | 13.5 | 5229.5 |
| 11/2/2014 | 2014 | 11 | 2 | 152 | 39 | 64 | 51.5 | 19.5 | 5249 |
| 11/3/2014 | 2014 | 11 | 3 | 153 | 23 | 60 | 41.5 | 9.5 | 5258.5 |
| 11/4/2014 | 2014 | 11 | 4 | 154 | 23 | 62 | 42.5 | 10.5 | 5269 |
| 11/5/2014 | 2014 | 11 | 5 | 155 | 23 | 62 | 42.5 | 10.5 | 5279.5 |
| 11/6/2014 | 2014 | 11 | 6 | 156 | 19 | 66 | 42.5 | 10.5 | 5290 |
| 11/7/2014 | 2014 | 11 | 7 | 157 | 18 | 67 | 42.5 | 10.5 | 5300.5 |
| 11/8/2014 | 2014 | 11 | 8 | 158 | 18 | 74 | 46 | 14 | 5314.5 |
| 11/9/2014 | 2014 | 11 | 9 | 159 | 20 | 66 | 43 | 11 | 5325.5 |
| 11/10/2014 | 2014 | 11 | 10 | 160 | 30 | 75 | 52.5 | 20.5 | 5346 |
| 11/11/2014 | 2014 | 11 | 11 | 161 | 30 | 75 | 52.5 | 20.5 | 5366.5 |
| 11/12/2014 | 2014 | 11 | 12 | 162 | 37 | 64 | 50.5 | 18.5 | 5385 |
| 11/13/2014 | 2014 | 11 | 13 | 163 | 20 | 65 | 42.5 | 10.5 | 5395.5 |
| 11/14/2014 | 2014 | 11 | 14 | 164 | 21 | 48 | 34.5 | 2.5 | 5398 |
| 11/15/2014 | 2014 | 11 | 15 | 165 | 21 | 48 | 34.5 | 2.5 | 5400.5 |
| 11/16/2014 | 2014 | 11 | 16 | 166 | 27 | 64 | 45.5 | 13.5 | 5414 |
| 11/17/2014 | 2014 | 11 | 17 | 167 | 4 | 40 | 22 | -10 | 5404 |
| 11/18/2014 | 2014 | 11 | 18 | 168 | 5 | 48 | 26.5 | -5.5 | 5398.5 |
| 11/19/2014 | 2014 | 11 | 19 | 169 | 7 | 53 | 30 | -2 | 5396.5 |
| 11/20/2014 | 2014 | 11 | 20 | 170 | 14 | 62 | 38 | 6 | 5402.5 |
| 11/21/2014 | 2014 | 11 | 21 | 171 | 10 | 53 | 31.5 | -0.5 | 5402 |
| 11/22/2014 | 2014 | 11 | 22 | 172 | 12 | 60 | 36 | 4 | 5406 |
| 11/23/2014 | 2014 | 11 | 23 | 173 | 12 | 48 | 30 | -2 | 5404 |
| 11/24/2014 | 2014 | 11 | 24 | 174 | 8 | 48 | 28 | -4 | 5400 |
| 11/25/2014 | 2014 | 11 | 25 | 175 | 5 | 48 | 26.5 | -5.5 | 5394.5 |
| 11/26/2014 | 2014 | 11 | 26 | 176 | 5 | 56 | 30.5 | -1.5 | 5393 |
| 11/27/2014 | 2014 | 11 | 27 | 177 | 5 | 56 | 30.5 | -1.5 | 5391.5 |
| 11/28/2014 | 2014 | 11 | 28 | 178 | 13 | 71 | 42 | 10 | 5401.5 |
| 11/29/2014 | 2014 | 11 | 29 | 179 | 14 | 76 | 45 | 13 | 5414.5 |
| 11/30/2014 | 2014 | 11 | 30 | 180 | 20 | 69 | 44.5 | 12.5 | 5427 |
| 12/1/2014 | 2014 | 12 | 1 | 181 | 14 | 62 | 38 | 6 | 5433 |
| 12/2/2014 | 2014 | 12 | 2 | 182 | 17 | 60 | 38.5 | 6.5 | 5439.5 |
| 12/3/2014 | 2014 | 12 | 3 | 183 | 17 | 50 | 33.5 | 1.5 | 5441 |
| 12/4/2014 | 2014 | 12 | 4 | 184 | 17 | 62 | 39.5 | 7.5 | 5448.5 |
| 12/5/2014 | 2014 | 12 | 5 | 185 | 31 | 47 | 39 | 7 | 5455.5 |
| 12/6/2014 | 2014 | 12 | 6 | 186 | 30 | 58 | 44 | 12 | 5467.5 |
| 12/7/2014 | 2014 | 12 | 7 | 187 | 28 | 51 | 39.5 | 7.5 | 5475 |
| 12/8/2014 | 2014 | 12 | 8 | 188 | 23 | 59 | 41 | 9 | 5484 |
| 12/9/2014 | 2014 | 12 | 9 | 189 | 25 | 55 | 40 | 8 | 5492 |
| 12/11/2014 | 2014 | 12 | 11 | 190 | 24 | 65 | 44.5 | 12.5 | 5504.5 |
| 12/12/2014 | 2014 | 12 | 12 | 191 | 24 | 64 | 44 | 12 | 5516.5 |
| 12/13/2014 | 2014 | 12 | 13 | 192 | 24 | 64 | 44 | 12 | 5528.5 |
| 12/15/2014 | 2014 | 12 | 15 | 193 | 15 | 45 | 30 | -2 | 5526.5 |
| 12/16/2014 | 2014 | 12 | 16 | 194 | 15 | 46 | 30.5 | -1.5 | 5525 |
| 12/17/2014 | 2014 | 12 | 17 | 195 | 28 | 46 | 37 | 5 | 5530 |
| 12/18/2014 | 2014 | 12 | 18 | 196 | 22 | 43 | 32.5 | 0.5 | 5530.5 |
| 12/19/2014 | 2014 | 12 | 19 | 197 | 20 | 41 | 30.5 | -1.5 | 5529 |
| 12/20/2014 | 2014 | 12 | 20 | 198 | 6 | 43 | 24.5 | -7.5 | 5521.5 |
| 12/21/2014 | 2014 | 12 | 21 | 199 | 6 | 52 | 29 | -3 | 5518.5 |
| 12/22/2014 | 2014 | 12 | 22 | 200 | 28 | 57 | 42.5 | 10.5 | 5529 |
| 12/23/2014 | 2014 | 12 | 23 | 201 | 25 | 60 | 42.5 | 10.5 | 5539.5 |
| 12/24/2014 | 2014 | 12 | 24 | 202 | 8 | 41 | 24.5 | -7.5 | 5532 |
| 12/25/2014 | 2014 | 12 | 25 | 203 | 8 | 50 | 29 | -3 | 5529 |
| 12/26/2014 | 2014 | 12 | 26 | 204 | 5 | 47 | 26 | -6 | 5523 |
| 12/27/2014 | 2014 | 12 | 27 | 205 | 6 | 35 | 20.5 | -11.5 | 5511.5 |
| 12/28/2014 | 2014 | 12 | 28 | 206 | 3 | 37 | 20 | -12 | 5499.5 |
| 12/29/2014 | 2014 | 12 | 29 | 207 | 3 | 43 | 23 | -9 | 5490.5 |
| 12/30/2014 | 2014 | 12 | 30 | 208 | 4 | 47 | 25.5 | -6.5 | 5484 |
| 12/31/2014 | 2014 | 12 | 31 | 209 | 10 | 33 | 21.5 | -10.5 | 5473.5 |
| 1/1/2015 | 2015 | 1 | 1 | 210 | 10 | 34 | 22 | -10 | 5463.5 |
| 1/2/2015 | 2015 | 1 | 2 | 211 | 8 | 34 | 21 | -11 | 5452.5 |
| 1/3/2015 | 2015 | 1 | 3 | 212 | 4 | 34 | 19 | -13 | 5439.5 |
| 1/4/2015 | 2015 | 1 | 4 | 213 | 6 | 48 | 27 | -5 | 5434.5 |
| 1/5/2015 | 2015 | 1 | 5 | 214 | 8 | 40 | 24 | -8 | 5426.5 |
| 1/6/2015 | 2015 | 1 | 6 | 215 | 8 | 62 | 35 | 3 | 5429.5 |
| 1/7/2015 | 2015 | 1 | 7 | 216 | 20 | 61 | 40.5 | 8.5 | 5438 |
| 1/8/2015 | 2015 | 1 | 8 | 217 | 21 | 56 | 38.5 | 6.5 | 5444.5 |
| 1/9/2015 | 2015 | 1 | 9 | 218 | 22 | 59 | 40.5 | 8.5 | 5453 |
| 1/10/2015 | 2015 | 1 | 10 | 219 | 22 | 59 | 40.5 | 8.5 | 5461.5 |
| 1/11/2015 | 2015 | 1 | 11 | 220 | 22 | 58 | 40 | 8 | 5469.5 |
| 1/12/2015 | 2015 | 1 | 12 | 221 | 27 | 55 | 41 | 9 | 5478.5 |
| 1/13/2015 | 2015 | 1 | 13 | 222 | 29 | 39 | 34 | 2 | 5480.5 |
| 1/14/2015 | 2015 | 1 | 14 | 223 | 28 | 39 | 33.5 | 1.5 | 5482 |
| 1/15/2015 | 2015 | 1 | 15 | 224 | 17 | 39 | 28 | -4 | 5478 |
| 1/16/2015 | 2015 | 1 | 16 | 225 | 12 | 50 | 31 | -1 | 5477 |
| 1/17/2015 | 2015 | 1 | 17 | 226 | 0 | 53 | 26.5 | -5.5 | 5471.5 |
| 1/18/2015 | 2015 | 1 | 18 | 227 | 17 | 51 | 34 | 2 | 5473.5 |
| 1/19/2015 | 2015 | 1 | 19 | 228 | 19 | 60 | 39.5 | 7.5 | 5481 |
| 1/20/2015 | 2015 | 1 | 20 | 229 | 19 | 63 | 41 | 9 | 5490 |
| 1/21/2015 | 2015 | 1 | 21 | 230 | 25 | 56 | 40.5 | 8.5 | 5498.5 |
| 1/22/2015 | 2015 | 1 | 22 | 231 | 19 | 56 | 37.5 | 5.5 | 5504 |
| 1/23/2015 | 2015 | 1 | 23 | 232 | 0 | 31 | 15.5 | -16.5 | 5487.5 |
| 1/24/2015 | 2015 | 1 | 24 | 233 | 10 | 39 | 24.5 | -7.5 | 5480 |
| 1/25/2015 | 2015 | 1 | 25 | 234 | 10 | 52 | 31 | -1 | 5479 |
| 1/26/2015 | 2015 | 1 | 26 | 235 | 21 | 58 | 39.5 | 7.5 | 5486.5 |
| 1/27/2015 | 2015 | 1 | 27 | 236 | 21 | 59 | 40 | 8 | 5494.5 |
| 1/28/2015 | 2015 | 1 | 28 | 237 | 21 | 65 | 43 | 11 | 5505.5 |
| 1/29/2015 | 2015 | 1 | 29 | 238 | 21 | 63 | 42 | 10 | 5515.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/30/2015 | 2015 | 1 | 30 | 239 | 29 | 50 | 39.5 | 7.5 | 5523 |
| 1/31/2015 | 2015 | 1 | 31 | 240 | 29 | 33 | 31 | -1 | 5522 |
| 2/1/2015 | 2015 | 2 | 1 | 241 | 25 | 49 | 37 | 5 | 5527 |
| 2/2/2015 | 2015 | 2 | 2 | 242 | 19 | 55 | 37 | 5 | 5532 |
| 2/3/2015 | 2015 | 2 | 3 | 243 | 21 | 61 | 41 | 9 | 5541 |
| 2/4/2015 | 2015 | 2 | 4 | 244 | 23 | 62 | 42.5 | 10.5 | 5551.5 |
| 2/5/2015 | 2015 | 2 | 5 | 245 | 22 | 66 | 44 | 12 | 5563.5 |
| 2/6/2015 | 2015 | 2 | 6 | 246 | 19 | 71 | 45 | 13 | 5576.5 |
| 2/7/2015 | 2015 | 2 | 7 | 247 | 19 | 73 | 46 | 14 | 5590.5 |
| 2/8/2015 | 2015 | 2 | 8 | 248 | 23 | 72 | 47.5 | 15.5 | 5606 |
| 2/9/2015 | 2015 | 2 | 9 | 249 | 23 | 71 | 47 | 15 | 5621 |
| 2/10/2015 | 2015 | 2 | 10 | 250 | 19 | 74 | 46.5 | 14.5 | 5635.5 |
| 2/11/2015 | 2015 | 2 | 11 | 251 | 22 | 72 | 47 | 15 | 5650.5 |
| 2/12/2015 | 2015 | 2 | 12 | 252 | 19 | 72 | 45.5 | 13.5 | 5664 |
| 2/13/2015 | 2015 | 2 | 13 | 253 | 35 | 64 | 49.5 | 17.5 | 5681.5 |
| 2/14/2015 | 2015 | 2 | 14 | 254 | 19 | 64 | 41.5 | 9.5 | 5691 |
| 2/15/2015 | 2015 | 2 | 15 | 255 | 19 | 73 | 46 | 14 | 5705 |
| 2/16/2015 | 2015 | 2 | 16 | 256 | 18 | 68 | 43 | 11 | 5716 |
| 2/17/2015 | 2015 | 2 | 17 | 257 | 15 | 57 | 36 | 4 | 5720 |
| 2/18/2015 | 2015 | 2 | 18 | 258 | 12 | 56 | 34 | 2 | 5722 |
| 2/19/2015 | 2015 | 2 | 19 | 259 | 10 | 68 | 39 | 7 | 5729 |
| 2/20/2015 | 2015 | 2 | 20 | 260 | 19 | 73 | 46 | 14 | 5743 |
| 2/21/2015 | 2015 | 2 | 21 | 261 | 25 | 65 | 45 | 13 | 5756 |
| 2/22/2015 | 2015 | 2 | 22 | 262 | 25 | 64 | 44.5 | 12.5 | 5768.5 |
| 2/23/2015 | 2015 | 2 | 23 | 263 | 17 | 51 | 34 | 2 | 5770.5 |
| 2/24/2015 | 2015 | 2 | 24 | 264 | 14 | 32 | 23 | -9 | 5761.5 |
| 2/26/2015 | 2015 | 2 | 26 | 265 | 15 | 55 | 35 | 3 | 5764.5 |
| 2/27/2015 | 2015 | 2 | 27 | 266 | 21 | 49 | 35 | 3 | 5767.5 |
| 2/28/2015 | 2015 | 2 | 28 | 267 | 22 | 37 | 29.5 | -2.5 | 5765 |
| 3/1/2015 | 2015 | 3 | 1 | 268 | 22 | 39 | 30.5 | -1.5 | 5763.5 |
| 3/2/2015 | 2015 | 3 | 2 | 269 | 33 | 58 | 45.5 | 13.5 | 5777 |
| 3/3/2015 | 2015 | 3 | 3 | 270 | 23 | 62 | 42.5 | 10.5 | 5787.5 |
| 3/4/2015 | 2015 | 3 | 4 | 271 | 20 | 52 | 36 | 4 | 5791.5 |
| 3/5/2015 | 2015 | 3 | 5 | 272 | 13 | 52 | 32.5 | 0.5 | 5792 |
| 3/6/2015 | 2015 | 3 | 6 | 273 | 13 | 53 | 33 | 1 | 5793 |
| 3/7/2015 | 2015 | 3 | 7 | 274 | 13 | 63 | 38 | 6 | 5799 |
| 3/8/2015 | 2015 | 3 | 8 | 275 | 24 | 54 | 39 | 7 | 5806 |
| 3/9/2015 | 2015 | 3 | 9 | 276 | 23 | 70 | 46.5 | 14.5 | 5820.5 |
| 3/10/2015 | 2015 | 3 | 10 | 277 | 17 | 58 | 37.5 | 5.5 | 5826 |
| 3/11/2015 | 2015 | 3 | 11 | 278 | 18 | 68 | 43 | 11 | 5837 |
| 3/12/2015 | 2015 | 3 | 12 | 279 | 23 | 67 | 45 | 13 | 5850 |
| 3/13/2015 | 2015 | 3 | 13 | 280 | 35 | 64 | 49.5 | 17.5 | 5867.5 |
| 3/14/2015 | 2015 | 3 | 14 | 281 | 32 | 66 | 49 | 17 | 5884.5 |
| 3/15/2015 | 2015 | 3 | 15 | 282 | 23 | 63 | 43 | 11 | 5895.5 |
| 3/16/2015 | 2015 | 3 | 16 | 283 | 22 | 68 | 45 | 13 | 5908.5 |
| 3/17/2015 | 2015 | 3 | 17 | 284 | 25 | 73 | 49 | 17 | 5925.5 |
| 3/18/2015 | 2015 | 3 | 18 | 285 | 25 | 67 | 46 | 14 | 5939.5 |
| 3/19/2015 | 2015 | 3 | 19 | 286 | 33 | 61 | 47 | 15 | 5954.5 |
| 3/20/2015 | 2015 | 3 | 20 | 287 | 35 | 58 | 46.5 | 14.5 | 5969 |
| 3/21/2015 | 2015 | 3 | 21 | 288 | 29 | 52 | 40.5 | 8.5 | 5977.5 |
| 3/22/2015 | 2015 | 3 | 22 | 289 | 25 | 69 | 47 | 15 | 5992.5 |
| 3/23/2015 | 2015 | 3 | 23 | 290 | 28 | 73 | 50.5 | 18.5 | 6011 |
| 3/25/2015 | 2015 | 3 | 25 | 291 | 32 | 72 | 52 | 20 | 6031 |
| 3/26/2015 | 2015 | 3 | 26 | 292 | 24 | 70 | 47 | 15 | 6046 |
| 3/27/2015 | 2015 | 3 | 27 | 293 | 24 | 71 | 47.5 | 15.5 | 6061.5 |
| 3/28/2015 | 2015 | 3 | 28 | 294 | 24 | 78 | 51 | 19 | 6080.5 |
| 3/29/2015 | 2015 | 3 | 29 | 295 | 32 | 82 | 57 | 25 | 6105.5 |
| 3/30/2015 | 2015 | 3 | 30 | 296 | 32 | 82 | 57 | 25 | 6130.5 |
| 3/31/2015 | 2015 | 3 | 31 | 297 | 30 | 79 | 54.5 | 22.5 | 6153 |
| 4/1/2015 | 2015 | 4 | 1 | 298 | 30 | 79 | 54.5 | 22.5 | 6175.5 |
| 4/2/2015 | 2015 | 4 | 2 | 299 | 39 | 75 | 57 | 25 | 6200.5 |
| 4/3/2015 | 2015 | 4 | 3 | 300 | 26 | 71 | 48.5 | 16.5 | 6217 |
| 4/4/2015 | 2015 | 4 | 4 | 301 | 31 | 68 | 49.5 | 17.5 | 6234.5 |
| 4/5/2015 | 2015 | 4 | 5 | 302 | 35 | 66 | 50.5 | 18.5 | 6253 |
| 4/6/2015 | 2015 | 4 | 6 | 303 | 26 | 74 | 50 | 18 | 6271 |
| 4/7/2015 | 2015 | 4 | 7 | 304 | 30 | 72 | 51 | 19 | 6290 |
| 4/8/2015 | 2015 | 4 | 8 | 305 | 38 | 73 | 55.5 | 23.5 | 6313.5 |
| 4/9/2015 | 2015 | 4 | 9 | 306 | 19 | 70 | 44.5 | 12.5 | 6326 |
| 4/10/2015 | 2015 | 4 | 10 | 307 | 23 | 66 | 44.5 | 12.5 | 6338.5 |
| 4/11/2015 | 2015 | 4 | 11 | 308 | 28 | 72 | 50 | 18 | 6356.5 |
| 4/12/2015 | 2015 | 4 | 12 | 309 | 39 | 72 | 55.5 | 23.5 | 6380 |
| 4/13/2015 | 2015 | 4 | 13 | 310 | 38 | 75 | 56.5 | 24.5 | 6404.5 |
| 4/14/2015 | 2015 | 4 | 14 | 311 | 33 | 69 | 51 | 19 | 6423.5 |
| 4/15/2015 | 2015 | 4 | 15 | 312 | 40 | 75 | 57.5 | 25.5 | 6449 |
| 4/16/2015 | 2015 | 4 | 16 | 313 | 19 | 66 | 42.5 | 10.5 | 6459.5 |
| 4/17/2015 | 2015 | 4 | 17 | 314 | 18 | 55 | 36.5 | 4.5 | 6464 |
| 4/18/2015 | 2015 | 4 | 18 | 315 | 27 | 51 | 39 | 7 | 6471 |
| 4/19/2015 | 2015 | 4 | 19 | 316 | 30 | 67 | 48.5 | 16.5 | 6487.5 |
| 4/20/2015 | 2015 | 4 | 20 | 317 | 24 | 70 | 47 | 15 | 6502.5 |
| 4/21/2015 | 2015 | 4 | 21 | 318 | 27 | 74 | 50.5 | 18.5 | 6521 |
| 4/22/2015 | 2015 | 4 | 22 | 319 | 33 | 71 | 52 | 20 | 6541 |
| 4/23/2015 | 2015 | 4 | 23 | 320 | 27 | 74 | 50.5 | 18.5 | 6559.5 |
| 4/24/2015 | 2015 | 4 | 24 | 321 | 38 | 72 | 55 | 23 | 6582.5 |
| 4/25/2015 | 2015 | 4 | 25 | 322 | 39 | 64 | 51.5 | 19.5 | 6602 |
| 4/26/2015 | 2015 | 4 | 26 | 323 | 40 | 67 | 53.5 | 21.5 | 6623.5 |
| 4/27/2015 | 2015 | 4 | 27 | 324 | 39 | 52 | 45.5 | 13.5 | 6637 |
| 4/28/2015 | 2015 | 4 | 28 | 325 | 40 | 67 | 53.5 | 21.5 | 6658.5 |
| 4/29/2015 | 2015 | 4 | 29 | 326 | 28 | 63 | 45.5 | 13.5 | 6672 |
| 4/30/2015 | 2015 | 4 | 30 | 327 | 34 | 78 | 56 | 24 | 6696 |
| 5/1/2015 | 2015 | 5 | 1 | 328 | 38 | 83 | 60.5 | 28.5 | 6724.5 |
| 5/2/2015 | 2015 | 5 | 2 | 329 | 38 | 84 | 61 | 29 | 6753.5 |
| 5/3/2015 | 2015 | 5 | 3 | 330 | 37 | 93 | 65 | 33 | 6786.5 |
| 5/4/2015 | 2015 | 5 | 4 | 331 | 38 | 77 | 57.5 | 25.5 | 6812 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/5/2015 | 2015 | 5 | 5 | 332 | 39 | 68 | 53.5 | 21.5 | 6833.5 |
| 5/6/2015 | 2015 | 5 | 6 | 333 | 45 | 65 | 55 | 23 | 6856.5 |
| 5/7/2015 | 2015 | 5 | 7 | 334 | 32 | 70 | 51 | 19 | 6875.5 |
| 5/8/2015 | 2015 | 5 | 8 | 335 | 39 | 74 | 56.5 | 24.5 | 6900 |
| 5/9/2015 | 2015 | 5 | 9 | 336 | 36 | 68 | 52 | 20 | 6920 |
| 5/10/2015 | 2015 | 5 | 10 | 337 | 32 | 68 | 50 | 18 | 6938 |
| 5/11/2015 | 2015 | 5 | 11 | 338 | 29 | 67 | 48 | 16 | 6954 |
| 5/12/2015 | 2015 | 5 | 12 | 339 | 45 | 74 | 59.5 | 27.5 | 6981.5 |
| 5/13/2015 | 2015 | 5 | 13 | 340 | 45 | 68 | 56.5 | 24.5 | 7006 |
| 5/14/2015 | 2015 | 5 | 14 | 341 | 40 | 75 | 57.5 | 25.5 | 7031.5 |
| 5/15/2015 | 2015 | 5 | 15 | 342 | 42 | 74 | 58 | 26 | 7057.5 |
| 5/17/2015 | 2015 | 5 | 17 | 343 | 26 | 59 | 42.5 | 10.5 | 7068 |
| 5/18/2015 | 2015 | 5 | 18 | 344 | 34 | 74 | 54 | 22 | 7090 |
| 5/19/2015 | 2015 | 5 | 19 | 345 | 42 | 74 | 58 | 26 | 7116 |
| 5/20/2015 | 2015 | 5 | 20 | 346 | 32 | 74 | 53 | 21 | 7137 |
| 5/21/2015 | 2015 | 5 | 21 | 347 | 48 | 79 | 63.5 | 31.5 | 7168.5 |
| 5/22/2015 | 2015 | 5 | 22 | 348 | 43 | 67 | 55 | 23 | 7191.5 |
| 5/23/2015 | 2015 | 5 | 23 | 349 | 38 | 71 | 54.5 | 22.5 | 7214 |
| 5/24/2015 | 2015 | 5 | 24 | 350 | 37 | 68 | 52.5 | 20.5 | 7234.5 |
| 5/25/2015 | 2015 | 5 | 25 | 351 | 34 | 68 | 51 | 19 | 7253.5 |
| 5/26/2015 | 2015 | 5 | 26 | 352 | 34 | 71 | 52.5 | 20.5 | 7274 |
| 5/27/2015 | 2015 | 5 | 27 | 353 | 43 | 77 | 60 | 28 | 7302 |
| 5/28/2015 | 2015 | 5 | 28 | 354 | 37 | 79 | 58 | 26 | 7328 |
| 5/29/2015 | 2015 | 5 | 29 | 355 | 43 | 85 | 64 | 32 | 7360 |
| 5/30/2015 | 2015 | 5 | 30 | 356 | 42 | 81 | 61.5 | 29.5 | 7389.5 |
| 5/31/2015 | 2015 | 5 | 31 | 357 | 40 | 86 | 63 | 31 | 7420.5 |
| 6/1/2015 | 2015 | 6 | 1 | 1 | 53 | 91 | 72 | 40 | 40 |
| 6/2/2015 | 2015 | 6 | 2 | 2 | 40 | 88 | 64 | 32 | 72 |
| 6/3/2015 | 2015 | 6 | 3 | 3 | 42 | 91 | 66.5 | 34.5 | 106.5 |
| 6/4/2015 | 2015 | 6 | 4 | 4 | 38 | 90 | 64 | 32 | 138.5 |
| 6/5/2015 | 2015 | 6 | 5 | 5 | 55 | 89 | 72 | 40 | 178.5 |
| 6/6/2015 | 2015 | 6 | 6 | 6 | 51 | 80 | 65.5 | 33.5 | 212 |
| 6/7/2015 | 2015 | 6 | 7 | 7 | 46 | 85 | 65.5 | 33.5 | 245.5 |
| 6/8/2015 | 2015 | 6 | 8 | 8 | 45 | 88 | 66.5 | 34.5 | 280 |
| 6/9/2015 | 2015 | 6 | 9 | 9 | 60 | 89 | 74.5 | 42.5 | 322.5 |
| 6/10/2015 | 2015 | 6 | 10 | 10 | 57 | 84 | 70.5 | 38.5 | 361 |
| 6/11/2015 | 2015 | 6 | 11 | 11 | 48 | 89 | 68.5 | 36.5 | 397.5 |
| 6/12/2015 | 2015 | 6 | 12 | 12 | 43 | 85 | 64 | 32 | 429.5 |
| 6/13/2015 | 2015 | 6 | 13 | 13 | 49 | 84 | 66.5 | 34.5 | 464 |
| 6/14/2015 | 2015 | 6 | 14 | 14 | 43 | 90 | 66.5 | 34.5 | 498.5 |
| 6/15/2015 | 2015 | 6 | 15 | 15 | 48 | 86 | 67 | 35 | 533.5 |
| 6/16/2015 | 2015 | 6 | 16 | 16 | 58 | 90 | 74 | 42 | 575.5 |
| 6/17/2015 | 2015 | 6 | 17 | 17 | 54 | 85 | 69.5 | 37.5 | 613 |
| 6/18/2015 | 2015 | 6 | 18 | 18 | 47 | 98 | 72.5 | 40.5 | 653.5 |
| 6/19/2015 | 2015 | 6 | 19 | 19 | 63 | 98 | 80.5 | 48.5 | 702 |
| 6/20/2015 | 2015 | 6 | 20 | 20 | 47 | 99 | 73 | 41 | 743 |
| 6/21/2015 | 2015 | 6 | 21 | 21 | 48 | 100 | 74 | 42 | 785 |
| 6/22/2015 | 2015 | 6 | 22 | 22 | 52 | 103 | 77.5 | 45.5 | 830.5 |
| 6/23/2015 | 2015 | 6 | 23 | 23 | 61 | 102 | 81.5 | 49.5 | 880 |
| 6/24/2015 | 2015 | 6 | 24 | 24 | 61 | 96 | 78.5 | 46.5 | 926.5 |
| 6/25/2015 | 2015 | 6 | 25 | 25 | 58 | 92 | 75 | 43 | 969.5 |
| 6/26/2015 | 2015 | 6 | 26 | 26 | 57 | 96 | 76.5 | 44.5 | 1014 |
| 6/27/2015 | 2015 | 6 | 27 | 27 | 63 | 96 | 79.5 | 47.5 | 1061.5 |
| 6/28/2015 | 2015 | 6 | 28 | 28 | 50 | 89 | 69.5 | 37.5 | 1099 |
| 6/29/2015 | 2015 | 6 | 29 | 29 | 52 | 90 | 71 | 39 | 1138 |
| 6/30/2015 | 2015 | 6 | 30 | 30 | 62 | 96 | 79 | 47 | 1185 |
| 7/1/2015 | 2015 | 7 | 1 | 31 | 63 | 95 | 79 | 47 | 1232 |
| 7/2/2015 | 2015 | 7 | 2 | 32 | 63 | 98 | 80.5 | 48.5 | 1280.5 |
| 7/3/2015 | 2015 | 7 | 3 | 33 | 60 | 97 | 78.5 | 46.5 | 1327 |
| 7/4/2015 | 2015 | 7 | 4 | 34 | 58 | 87 | 72.5 | 40.5 | 1367.5 |
| 7/5/2015 | 2015 | 7 | 5 | 35 | 58 | 86 | 72 | 40 | 1407.5 |
| 7/6/2015 | 2015 | 7 | 6 | 36 | 57 | 88 | 72.5 | 40.5 | 1448 |
| 7/7/2015 | 2015 | 7 | 7 | 37 | 56 | 87 | 71.5 | 39.5 | 1487.5 |
| 7/8/2015 | 2015 | 7 | 8 | 38 | 52 | 87 | 69.5 | 37.5 | 1525 |
| 7/9/2015 | 2015 | 7 | 9 | 39 | 54 | 86 | 70 | 38 | 1563 |
| 7/10/2015 | 2015 | 7 | 10 | 40 | 50 | 66 | 58 | 26 | 1589 |
| 7/11/2015 | 2015 | 7 | 11 | 41 | 53 | 79 | 66 | 34 | 1623 |
| 7/12/2015 | 2015 | 7 | 12 | 42 | 53 | 80 | 66.5 | 34.5 | 1657.5 |
| 7/13/2015 | 2015 | 7 | 13 | 43 | 55 | 87 | 71 | 39 | 1696.5 |
| 7/14/2015 | 2015 | 7 | 14 | 44 | 55 | 84 | 69.5 | 37.5 | 1734 |
| 7/15/2015 | 2015 | 7 | 15 | 45 | 51 | 83 | 67 | 35 | 1769 |
| 7/16/2015 | 2015 | 7 | 16 | 46 | 50 | 82 | 66 | 34 | 1803 |
| 7/17/2015 | 2015 | 7 | 17 | 47 | 51 | 86 | 68.5 | 36.5 | 1839.5 |
| 7/18/2015 | 2015 | 7 | 18 | 48 | 55 | 80 | 67.5 | 35.5 | 1875 |
| 7/19/2015 | 2015 | 7 | 19 | 49 | 56 | 86 | 71 | 39 | 1914 |
| 7/20/2015 | 2015 | 7 | 20 | 50 | 53 | 82 | 67.5 | 35.5 | 1949.5 |
| 7/21/2015 | 2015 | 7 | 21 | 51 | 54 | 88 | 71 | 39 | 1988.5 |
| 7/22/2015 | 2015 | 7 | 22 | 52 | 52 | 88 | 70 | 38 | 2026.5 |
| 7/23/2015 | 2015 | 7 | 23 | 53 | 58 | 91 | 74.5 | 42.5 | 2069 |
| 7/24/2015 | 2015 | 7 | 24 | 54 | 61 | 89 | 75 | 43 | 2112 |
| 7/25/2015 | 2015 | 7 | 25 | 55 | 52 | 89 | 70.5 | 38.5 | 2150.5 |
| 7/26/2015 | 2015 | 7 | 26 | 56 | 57 | 92 | 74.5 | 42.5 | 2193 |
| 7/27/2015 | 2015 | 7 | 27 | 57 | 56 | 90 | 73 | 41 | 2234 |
| 7/28/2015 | 2015 | 7 | 28 | 58 | 58 | 90 | 74 | 42 | 2276 |
| 7/29/2015 | 2015 | 7 | 29 | 59 | 62 | 91 | 76.5 | 44.5 | 2320.5 |
| 7/30/2015 | 2015 | 7 | 30 | 60 | 58 | 82 | 70 | 38 | 2358.5 |
| 7/31/2015 | 2015 | 7 | 31 | 61 | 57 | 76 | 66.5 | 34.5 | 2393 |
| 8/1/2015 | 2015 | 8 | 1 | 62 | 58 | 82 | 70 | 38 | 2431 |
| 8/2/2015 | 2015 | 8 | 2 | 63 | 58 | 84 | 71 | 39 | 2470 |
| 8/3/2015 | 2015 | 8 | 3 | 64 | 53 | 83 | 68 | 36 | 2506 |
| 8/4/2015 | 2015 | 8 | 4 | 65 | 53 | 88 | 70.5 | 38.5 | 2544.5 |
| 8/5/2015 | 2015 | 8 | 5 | 66 | 50 | 93 | 71.5 | 39.5 | 2584 |
| 8/6/2015 | 2015 | 8 | 6 | 67 | 49 | 94 | 71.5 | 39.5 | 2623.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/7/2015 | 2015 | 8 | 7 | 68 | 61 | 94 | 77.5 | 45.5 | 2669 |
| 8/8/2015 | 2015 | 8 | 8 | 69 | 58 | 87 | 72.5 | 40.5 | 2709.5 |
| 8/9/2015 | 2015 | 8 | 9 | 70 | 49 | 80 | 64.5 | 32.5 | 2742 |
| 8/10/2015 | 2015 | 8 | 10 | 71 | 54 | 88 | 71 | 39 | 2781 |
| 8/11/2015 | 2015 | 8 | 11 | 72 | 59 | 87 | 73 | 41 | 2822 |
| 8/12/2015 | 2015 | 8 | 12 | 73 | 58 | 85 | 71.5 | 39.5 | 2861.5 |
| 8/13/2015 | 2015 | 8 | 13 | 74 | 53 | 89 | 71 | 39 | 2900.5 |
| 8/14/2015 | 2015 | 8 | 14 | 75 | 54 | 94 | 74 | 42 | 2942.5 |
| 8/15/2015 | 2015 | 8 | 15 | 76 | 56 | 96 | 76 | 44 | 2986.5 |
| 8/16/2015 | 2015 | 8 | 16 | 77 | 54 | 93 | 73.5 | 41.5 | 3028 |
| 8/17/2015 | 2015 | 8 | 17 | 78 | 54 | 96 | 75 | 43 | 3071 |
| 8/18/2015 | 2015 | 8 | 18 | 79 | 61 | 97 | 79 | 47 | 3118 |
| 8/19/2015 | 2015 | 8 | 19 | 80 | 47 | 95 | 71 | 39 | 3157 |
| 8/20/2015 | 2015 | 8 | 20 | 81 | 49 | 93 | 71 | 39 | 3196 |
| 8/21/2015 | 2015 | 8 | 21 | 82 | 55 | 92 | 73.5 | 41.5 | 3237.5 |
| 8/22/2015 | 2015 | 8 | 22 | 83 | 51 | 89 | 70 | 38 | 3275.5 |
| 8/23/2015 | 2015 | 8 | 23 | 84 | 55 | 91 | 73 | 41 | 3316.5 |
| 8/24/2015 | 2015 | 8 | 24 | 85 | 56 | 86 | 71 | 39 | 3355.5 |
| 8/25/2015 | 2015 | 8 | 25 | 86 | 55 | 88 | 71.5 | 39.5 | 3395 |
| 8/26/2015 | 2015 | 8 | 26 | 87 | 58 | 86 | 72 | 40 | 3435 |
| 8/27/2015 | 2015 | 8 | 27 | 88 | 55 | 80 | 67.5 | 35.5 | 3470.5 |
| 8/28/2015 | 2015 | 8 | 28 | 89 | 51 | 84 | 67.5 | 35.5 | 3506 |
| 8/29/2015 | 2015 | 8 | 29 | 90 | 55 | 88 | 71.5 | 39.5 | 3545.5 |
| 8/30/2015 | 2015 | 8 | 30 | 91 | 50 | 86 | 68 | 36 | 3581.5 |
| 8/31/2015 | 2015 | 8 | 31 | 92 | 54 | 92 | 73 | 41 | 3622.5 |
| 9/1/2015 | 2015 | 9 | 1 | 93 | 58 | 90 | 74 | 42 | 3664.5 |
| 9/2/2015 | 2015 | 9 | 2 | 94 | 52 | 85 | 68.5 | 36.5 | 3701 |
| 9/3/2015 | 2015 | 9 | 3 | 95 | 51 | 86 | 68.5 | 36.5 | 3737.5 |
| 9/4/2015 | 2015 | 9 | 4 | 96 | 55 | 85 | 70 | 38 | 3775.5 |
| 9/5/2015 | 2015 | 9 | 5 | 97 | 55 | 74 | 64.5 | 32.5 | 3808 |
| 9/6/2015 | 2015 | 9 | 6 | 98 | 46 | 74 | 60 | 28 | 3836 |
| 9/7/2015 | 2015 | 9 | 7 | 99 | 52 | 86 | 69 | 37 | 3873 |
| 9/8/2015 | 2015 | 9 | 8 | 100 | 51 | 88 | 69.5 | 37.5 | 3910.5 |
| 9/9/2015 | 2015 | 9 | 9 | 101 | 45 | 88 | 66.5 | 34.5 | 3945 |
| 9/10/2015 | 2015 | 9 | 10 | 102 | 46 | 87 | 66.5 | 34.5 | 3979.5 |
| 9/11/2015 | 2015 | 9 | 11 | 103 | 38 | 93 | 65.5 | 33.5 | 4013 |
| 9/12/2015 | 2015 | 9 | 12 | 104 | 47 | 88 | 67.5 | 35.5 | 4048.5 |
| 9/13/2015 | 2015 | 9 | 13 | 105 | 45 | 86 | 65.5 | 33.5 | 4082 |
| 9/14/2015 | 2015 | 9 | 14 | 106 | 51 | 90 | 70.5 | 38.5 | 4120.5 |
| 9/15/2015 | 2015 | 9 | 15 | 107 | 50 | 84 | 67 | 35 | 4155.5 |
| 9/16/2015 | 2015 | 9 | 16 | 108 | 47 | 83 | 65 | 33 | 4188.5 |
| 9/17/2015 | 2015 | 9 | 17 | 109 | 43 | 84 | 63.5 | 31.5 | 4220 |
| 9/18/2015 | 2015 | 9 | 18 | 110 | 46 | 86 | 66 | 34 | 4254 |
| 9/19/2015 | 2015 | 9 | 19 | 111 | 48 | 89 | 68.5 | 36.5 | 4290.5 |
| 9/20/2015 | 2015 | 9 | 20 | 112 | 42 | 81 | 61.5 | 29.5 | 4320 |
| 9/21/2015 | 2015 | 9 | 21 | 113 | 40 | 88 | 64 | 32 | 4352 |
| 9/22/2015 | 2015 | 9 | 22 | 114 | 44 | 84 | 64 | 32 | 4384 |
| 9/23/2015 | 2015 | 9 | 23 | 115 | 47 | 74 | 60.5 | 28.5 | 4412.5 |
| 9/24/2015 | 2015 | 9 | 24 | 116 | 45 | 83 | 64 | 32 | 4444.5 |
| 9/25/2015 | 2015 | 9 | 25 | 117 | 44 | 83 | 63.5 | 31.5 | 4476 |
| 9/26/2015 | 2015 | 9 | 26 | 118 | 40 | 81 | 60.5 | 28.5 | 4504.5 |
| 9/27/2015 | 2015 | 9 | 27 | 119 | 42 | 88 | 65 | 33 | 4537.5 |
| 9/28/2015 | 2015 | 9 | 28 | 120 | 43 | 90 | 66.5 | 34.5 | 4572 |
| 9/29/2015 | 2015 | 9 | 29 | 121 | 43 | 89 | 66 | 34 | 4606 |
| 9/30/2015 | 2015 | 9 | 30 | 122 | 49 | 91 | 70 | 38 | 4644 |
| 11/1/2015 | 2015 | 11 | 1 | 123 | 26 | 64 | 45 | 13 | 4657 |
| 11/2/2015 | 2015 | 11 | 2 | 124 | 24 | 73 | 48.5 | 16.5 | 4673.5 |
| 11/3/2015 | 2015 | 11 | 3 | 125 | 30 | 76 | 53 | 21 | 4694.5 |
| 11/4/2015 | 2015 | 11 | 4 | 126 | 37 | 71 | 54 | 22 | 4716.5 |
| 11/5/2015 | 2015 | 11 | 5 | 127 | 28 | 54 | 41 | 9 | 4725.5 |
| 11/6/2015 | 2015 | 11 | 6 | 128 | 18 | 49 | 33.5 | 1.5 | 4727 |
| 11/7/2015 | 2015 | 11 | 7 | 129 | 19 | 57 | 38 | 6 | 4733 |
| 11/8/2015 | 2015 | 11 | 8 | 130 | 21 | 53 | 37 | 5 | 4738 |
| 11/9/2015 | 2015 | 11 | 9 | 131 | 21 | 62 | 41.5 | 9.5 | 4747.5 |
| 11/10/2015 | 2015 | 11 | 10 | 132 | 26 | 68 | 47 | 15 | 4762.5 |
| 11/11/2015 | 2015 | 11 | 11 | 133 | 28 | 64 | 46 | 14 | 4776.5 |
| 11/12/2015 | 2015 | 11 | 12 | 134 | 14 | 51 | 32.5 | 0.5 | 4777 |
| 11/13/2015 | 2015 | 11 | 13 | 135 | 12 | 58 | 35 | 3 | 4780 |
| 11/14/2015 | 2015 | 11 | 14 | 136 | 13 | 59 | 36 | 4 | 4784 |
| 11/15/2015 | 2015 | 11 | 15 | 137 | 20 | 63 | 41.5 | 9.5 | 4793.5 |
| 11/16/2015 | 2015 | 11 | 16 | 138 | 28 | 48 | 38 | 6 | 4799.5 |
| 11/17/2015 | 2015 | 11 | 17 | 139 | 27 | 37 | 32 | 0 | 4799.5 |
| 11/18/2015 | 2015 | 11 | 18 | 140 | 23 | 52 | 37.5 | 5.5 | 4805 |
| 11/19/2015 | 2015 | 11 | 19 | 141 | 14 | 58 | 36 | 4 | 4809 |
| 11/20/2015 | 2015 | 11 | 20 | 142 | 17 | 63 | 40 | 8 | 4817 |
| 11/21/2015 | 2015 | 11 | 21 | 143 | 18 | 64 | 41 | 9 | 4826 |
| 11/22/2015 | 2015 | 11 | 22 | 144 | 11 | 53 | 32 | 0 | 4826 |
| 11/23/2015 | 2015 | 11 | 23 | 145 | 13 | 61 | 37 | 5 | 4831 |
| 11/24/2015 | 2015 | 11 | 24 | 146 | 16 | 68 | 42 | 10 | 4841 |
| 11/25/2015 | 2015 | 11 | 25 | 147 | 23 | 66 | 44.5 | 12.5 | 4853.5 |
| 11/26/2015 | 2015 | 11 | 26 | 148 | 32 | 65 | 48.5 | 16.5 | 4870 |
| 11/27/2015 | 2015 | 11 | 27 | 149 | 27 | 61 | 44 | 12 | 4882 |
| 11/28/2015 | 2015 | 11 | 28 | 150 | 28 | 47 | 37.5 | 5.5 | 4887.5 |
| 11/29/2015 | 2015 | 11 | 29 | 151 | 18 | 43 | 30.5 | -1.5 | 4886 |
| 11/30/2015 | 2015 | 11 | 30 | 152 | 14 | 54 | 34 | 2 | 4888 |
| 12/1/2015 | 2015 | 12 | 1 | 153 | 8 | 45 | 26.5 | -5.5 | 4882.5 |
| 12/2/2015 | 2015 | 12 | 2 | 154 | 6 | 47 | 26.5 | -5.5 | 4877 |
| 12/3/2015 | 2015 | 12 | 3 | 155 | 9 | 53 | 31 | -1 | 4876 |
| 12/4/2015 | 2015 | 12 | 4 | 156 | 12 | 62 | 37 | 5 | 4881 |
| 12/5/2015 | 2015 | 12 | 5 | 157 | 14 | 59 | 36.5 | 4.5 | 4885.5 |
| 12/6/2015 | 2015 | 12 | 6 | 158 | 10 | 59 | 34.5 | 2.5 | 4888 |
| 12/7/2015 | 2015 | 12 | 7 | 159 | 14 | 63 | 38.5 | 6.5 | 4894.5 |
| 12/8/2015 | 2015 | 12 | 8 | 160 | 14 | 70 | 42 | 10 | 4904.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/9/2015 | 2015 | 12 | 9 | 161 | 19 | 65 | 42 | 10 | 4914.5 |
| 12/10/2015 | 2015 | 12 | 10 | 162 | 17 | 66 | 41.5 | 9.5 | 4924 |
| 12/11/2015 | 2015 | 12 | 11 | 163 | 23 | 70 | 46.5 | 14.5 | 4938.5 |
| 12/12/2015 | 2015 | 12 | 12 | 164 | 32 | 58 | 45 | 13 | 4951.5 |
| 12/13/2015 | 2015 | 12 | 13 | 165 | 18 | 41 | 29.5 | -2.5 | 4949 |
| 12/14/2015 | 2015 | 12 | 14 | 166 | 15 | 49 | 32 | 0 | 4949 |
| 12/15/2015 | 2015 | 12 | 15 | 167 | 18 | 45 | 31.5 | -0.5 | 4948.5 |
| 12/16/2015 | 2015 | 12 | 16 | 168 | 9 | 36 | 22.5 | -9.5 | 4939 |
| 12/17/2015 | 2015 | 12 | 17 | 169 | 8 | 39 | 23.5 | -8.5 | 4930.5 |
| 12/18/2015 | 2015 | 12 | 18 | 170 | 8 | 42 | 25 | -7 | 4923.5 |
| 12/19/2015 | 2015 | 12 | 19 | 171 | 10 | 52 | 31 | -1 | 4922.5 |
| 12/20/2015 | 2015 | 12 | 20 | 172 | 13 | 45 | 29 | -3 | 4919.5 |
| 12/21/2015 | 2015 | 12 | 21 | 173 | 19 | 47 | 33 | 1 | 4920.5 |
| 12/22/2015 | 2015 | 12 | 22 | 174 | 23 | 53 | 38 | 6 | 4926.5 |
| 12/23/2015 | 2015 | 12 | 23 | 175 | 34 | 49 | 41.5 | 9.5 | 4936 |
| 12/24/2015 | 2015 | 12 | 24 | 176 | 24 | 48 | 36 | 4 | 4940 |
| 12/25/2015 | 2015 | 12 | 25 | 177 | 25 | 45 | 35 | 3 | 4943 |
| 12/26/2015 | 2015 | 12 | 26 | 178 | 17 | 46 | 31.5 | -0.5 | 4942.5 |
| 12/27/2015 | 2015 | 12 | 27 | 179 | 15 | 24 | 19.5 | -12.5 | 4930 |
| 12/28/2015 | 2015 | 12 | 28 | 180 | 6 | 31 | 18.5 | -13.5 | 4916.5 |
| 12/29/2015 | 2015 | 12 | 29 | 181 | 8 | 44 | 26 | -6 | 4910.5 |
| 12/30/2015 | 2015 | 12 | 30 | 182 | 10 | 44 | 27 | -5 | 4905.5 |
| 12/31/2015 | 2015 | 12 | 31 | 183 | 5 | 44 | 24.5 | -7.5 | 4898 |
| 1/1/2016 | 2016 | 1 | 1 | 184 | 7 | 45 | 26 | -6 | 4892 |
| 1/2/2016 | 2016 | 1 | 2 | 185 | 19 | 29 | 24 | -8 | 4884 |
| 1/3/2016 | 2016 | 1 | 3 | 186 | 10 | 41 | 25.5 | -6.5 | 4877.5 |
| 1/4/2016 | 2016 | 1 | 4 | 187 | 11 | 48 | 29.5 | -2.5 | 4875 |
| 1/5/2016 | 2016 | 1 | 5 | 188 | 23 | 38 | 30.5 | -1.5 | 4873.5 |
| 1/6/2016 | 2016 | 1 | 6 | 189 | 25 | 45 | 35 | 3 | 4876.5 |
| 1/7/2016 | 2016 | 1 | 7 | 190 | 28 | 44 | 36 | 4 | 4880.5 |
| 1/8/2016 | 2016 | 1 | 8 | 191 | 18 | 43 | 30.5 | -1.5 | 4879 |
| 1/9/2016 | 2016 | 1 | 9 | 192 | 9 | 36 | 22.5 | -9.5 | 4869.5 |
| 1/10/2016 | 2016 | 1 | 10 | 193 | 6 | 40 | 23 | -9 | 4860.5 |
| 1/11/2016 | 2016 | 1 | 11 | 194 | 8 | 36 | 22 | -10 | 4850.5 |
| 1/12/2016 | 2016 | 1 | 12 | 195 | 5 | 38 | 21.5 | -10.5 | 4840 |
| 1/13/2016 | 2016 | 1 | 13 | 196 | 7 | 51 | 29 | -3 | 4837 |
| 1/14/2016 | 2016 | 1 | 14 | 197 | 9 | 53 | 31 | -1 | 4836 |
| 1/15/2016 | 2016 | 1 | 15 | 198 | 10 | 55 | 32.5 | 0.5 | 4836.5 |
| 1/16/2016 | 2016 | 1 | 16 | 199 | 13 | 39 | 26 | -6 | 4830.5 |
| 1/17/2016 | 2016 | 1 | 17 | 200 | 16 | 36 | 26 | -6 | 4824.5 |
| 1/18/2016 | 2016 | 1 | 18 | 201 | 10 | 52 | 31 | -1 | 4823.5 |
| 1/19/2016 | 2016 | 1 | 19 | 202 | 14 | 57 | 35.5 | 3.5 | 4827 |
| 1/20/2016 | 2016 | 1 | 20 | 203 | 23 | 54 | 38.5 | 6.5 | 4833.5 |
| 1/21/2016 | 2016 | 1 | 21 | 204 | 10 | 57 | 33.5 | 1.5 | 4835 |
| 1/22/2016 | 2016 | 1 | 22 | 205 | 14 | 46 | 30 | -2 | 4833 |
| 1/23/2016 | 2016 | 1 | 23 | 206 | 14 | 56 | 35 | 3 | 4836 |
| 1/24/2016 | 2016 | 1 | 24 | 207 | 18 | 66 | 42 | 10 | 4846 |
| 1/25/2016 | 2016 | 1 | 25 | 208 | 15 | 51 | 33 | 1 | 4847 |
| 1/26/2016 | 2016 | 1 | 26 | 209 | 9 | 46 | 27.5 | -4.5 | 4842.5 |
| 1/27/2016 | 2016 | 1 | 27 | 210 | 9 | 48 | 28.5 | -3.5 | 4839 |
| 1/28/2016 | 2016 | 1 | 28 | 211 | 12 | 54 | 33 | 1 | 4840 |
| 1/29/2016 | 2016 | 1 | 29 | 212 | 12 | 60 | 36 | 4 | 4844 |
| 1/30/2016 | 2016 | 1 | 30 | 213 | 13 | 67 | 40 | 8 | 4852 |
| 1/31/2016 | 2016 | 1 | 31 | 214 | 32 | 63 | 47.5 | 15.5 | 4867.5 |
| 2/1/2016 | 2016 | 2 | 1 | 215 | 25 | 59 | 42 | 10 | 4877.5 |
| 2/2/2016 | 2016 | 2 | 2 | 216 | 15 | 36 | 25.5 | -6.5 | 4871 |
| 2/3/2016 | 2016 | 2 | 3 | 217 | 4 | 34 | 19 | -13 | 4858 |
| 2/4/2016 | 2016 | 2 | 4 | 218 | 0 | 36 | 18 | -14 | 4844 |
| 2/5/2016 | 2016 | 2 | 5 | 219 | 4 | 44 | 24 | -8 | 4836 |
| 2/6/2016 | 2016 | 2 | 6 | 220 | 5 | 43 | 24 | -8 | 4828 |
| 2/7/2016 | 2016 | 2 | 7 | 221 | 10 | 54 | 32 | 0 | 4828 |
| 2/8/2016 | 2016 | 2 | 8 | 222 | 12 | 58 | 35 | 3 | 4831 |
| 2/9/2016 | 2016 | 2 | 9 | 223 | 13 | 61 | 37 | 5 | 4836 |
| 2/10/2016 | 2016 | 2 | 10 | 224 | 11 | 62 | 36.5 | 4.5 | 4840.5 |
| 2/11/2016 | 2016 | 2 | 11 | 225 | 11 | 71 | 41 | 9 | 4849.5 |
| 2/12/2016 | 2016 | 2 | 12 | 226 | 15 | 69 | 42 | 10 | 4859.5 |
| 2/13/2016 | 2016 | 2 | 13 | 227 | 15 | 74 | 44.5 | 12.5 | 4872 |
| 2/14/2016 | 2016 | 2 | 14 | 228 | 19 | 72 | 45.5 | 13.5 | 4885.5 |
| 2/15/2016 | 2016 | 2 | 15 | 229 | 22 | 64 | 43 | 11 | 4896.5 |
| 2/16/2016 | 2016 | 2 | 16 | 230 | 20 | 65 | 42.5 | 10.5 | 4907 |
| 2/17/2016 | 2016 | 2 | 17 | 231 | 14 | 69 | 41.5 | 9.5 | 4916.5 |
| 2/18/2016 | 2016 | 2 | 18 | 232 | 21 | 75 | 48 | 16 | 4932.5 |
| 2/19/2016 | 2016 | 2 | 19 | 233 | 27 | 71 | 49 | 17 | 4949.5 |
| 2/20/2016 | 2016 | 2 | 20 | 234 | 20 | 69 | 44.5 | 12.5 | 4962 |
| 2/21/2016 | 2016 | 2 | 21 | 235 | 19 | 73 | 46 | 14 | 4976 |
| 2/22/2016 | 2016 | 2 | 22 | 236 | 12 | 73 | 42.5 | 10.5 | 4986.5 |
| 2/23/2016 | 2016 | 2 | 23 | 237 | 17 | 73 | 45 | 13 | 4999.5 |
| 2/24/2016 | 2016 | 2 | 24 | 238 | 19 | 46 | 32.5 | 0.5 | 5000 |
| 2/25/2016 | 2016 | 2 | 25 | 239 | 12 | 59 | 35.5 | 3.5 | 5003.5 |
| 2/26/2016 | 2016 | 2 | 26 | 240 | 15 | 67 | 41 | 9 | 5012.5 |
| 2/27/2016 | 2016 | 2 | 27 | 241 | 11 | 70 | 40.5 | 8.5 | 5021 |
| 2/28/2016 | 2016 | 2 | 28 | 242 | 20 | 73 | 46.5 | 14.5 | 5035.5 |
| 2/29/2016 | 2016 | 2 | 29 | 243 | 20 | 73 | 46.5 | 14.5 | 5050 |
| 3/1/2016 | 2016 | 3 | 1 | 244 | 20 | 73 | 46.5 | 14.5 | 5064.5 |
| 3/2/2016 | 2016 | 3 | 2 | 245 | 22 | 72 | 47 | 15 | 5079.5 |
| 3/3/2016 | 2016 | 3 | 3 | 246 | 22 | 74 | 48 | 16 | 5095.5 |
| 3/4/2016 | 2016 | 3 | 4 | 247 | 24 | 76 | 50 | 18 | 5113.5 |
| 3/5/2016 | 2016 | 3 | 5 | 248 | 25 | 78 | 51.5 | 19.5 | 5133 |
| 3/6/2016 | 2016 | 3 | 6 | 249 | 37 | 68 | 52.5 | 20.5 | 5153.5 |
| 3/7/2016 | 2016 | 3 | 7 | 250 | 33 | 70 | 51.5 | 19.5 | 5173 |
| 3/8/2016 | 2016 | 3 | 8 | 251 | 24 | 70 | 47 | 15 | 5188 |
| 3/9/2016 | 2016 | 3 | 9 | 252 | 13 | 57 | 35 | 3 | 5191 |
| 3/10/2016 | 2016 | 3 | 10 | 253 | 18 | 65 | 41.5 | 9.5 | 5200.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/11/2016 | 2016 | 3 | 11 | 254 | 10 | 73 | 41.5 | 9.5 | 5210 |
| 3/12/2016 | 2016 | 3 | 12 | 255 | 20 | 76 | 48 | 16 | 5226 |
| 3/13/2016 | 2016 | 3 | 13 | 256 | 19 | 54 | 36.5 | 4.5 | 5230.5 |
| 3/14/2016 | 2016 | 3 | 14 | 257 | 37 | 69 | 53 | 21 | 5251.5 |
| 3/15/2016 | 2016 | 3 | 15 | 258 | 34 | 69 | 51.5 | 19.5 | 5271 |
| 3/16/2016 | 2016 | 3 | 16 | 259 | 21 | 63 | 42 | 10 | 5281 |
| 3/17/2016 | 2016 | 3 | 17 | 260 | 17 | 67 | 42 | 10 | 5291 |
| 3/18/2016 | 2016 | 3 | 18 | 261 | 20 | 72 | 46 | 14 | 5305 |
| 3/19/2016 | 2016 | 3 | 19 | 262 | 20 | 73 | 46.5 | 14.5 | 5319.5 |
| 3/20/2016 | 2016 | 3 | 20 | 263 | 27 | 71 | 49 | 17 | 5336.5 |
| 3/21/2016 | 2016 | 3 | 21 | 264 | 11 | 69 | 40 | 8 | 5344.5 |
| 3/22/2016 | 2016 | 3 | 22 | 265 | 22 | 78 | 50 | 18 | 5362.5 |
| 3/23/2016 | 2016 | 3 | 23 | 266 | 27 | 70 | 48.5 | 16.5 | 5379 |
| 3/24/2016 | 2016 | 3 | 24 | 267 | 16 | 55 | 35.5 | 3.5 | 5382.5 |
| 3/25/2016 | 2016 | 3 | 25 | 268 | 14 | 47 | 30.5 | -1.5 | 5381 |
| 3/26/2016 | 2016 | 3 | 26 | 269 | 17 | 68 | 42.5 | 10.5 | 5391.5 |
| 3/27/2016 | 2016 | 3 | 27 | 270 | 10 | 60 | 35 | 3 | 5394.5 |
| 3/28/2016 | 2016 | 3 | 28 | 271 | 19 | 71 | 45 | 13 | 5407.5 |
| 3/29/2016 | 2016 | 3 | 29 | 272 | 25 | 65 | 45 | 13 | 5420.5 |
| 3/30/2016 | 2016 | 3 | 30 | 273 | 23 | 66 | 44.5 | 12.5 | 5433 |
| 3/31/2016 | 2016 | 3 | 31 | 274 | 13 | 55 | 34 | 2 | 5435 |
| 4/1/2016 | 2016 | 4 | 1 | 275 | 20 | 61 | 40.5 | 8.5 | 5443.5 |
| 4/2/2016 | 2016 | 4 | 2 | 276 | 15 | 61 | 38 | 6 | 5449.5 |
| 4/3/2016 | 2016 | 4 | 3 | 277 | 19 | 67 | 43 | 11 | 5460.5 |
| 4/4/2016 | 2016 | 4 | 4 | 278 | 24 | 74 | 49 | 17 | 5477.5 |
| 4/5/2016 | 2016 | 4 | 5 | 279 | 29 | 78 | 53.5 | 21.5 | 5499 |
| 4/6/2016 | 2016 | 4 | 6 | 280 | 25 | 76 | 50.5 | 18.5 | 5517.5 |
| 4/7/2016 | 2016 | 4 | 7 | 281 | 27 | 78 | 52.5 | 20.5 | 5538 |
| 4/8/2016 | 2016 | 4 | 8 | 282 | 35 | 68 | 51.5 | 19.5 | 5557.5 |
| 4/9/2016 | 2016 | 4 | 9 | 283 | 32 | 73 | 52.5 | 20.5 | 5578 |
| 4/10/2016 | 2016 | 4 | 10 | 284 | 34 | 69 | 51.5 | 19.5 | 5597.5 |
| 4/11/2016 | 2016 | 4 | 11 | 285 | 31 | 65 | 48 | 16 | 5613.5 |
| 4/12/2016 | 2016 | 4 | 12 | 286 | 35 | 67 | 51 | 19 | 5632.5 |
| 4/13/2016 | 2016 | 4 | 13 | 287 | 30 | 65 | 47.5 | 15.5 | 5648 |
| 4/14/2016 | 2016 | 4 | 14 | 288 | 35 | 73 | 54 | 22 | 5670 |
| 4/15/2016 | 2016 | 4 | 15 | 289 | 41 | 76 | 58.5 | 26.5 | 5696.5 |
| 4/16/2016 | 2016 | 4 | 16 | 290 | 33 | 67 | 50 | 18 | 5714.5 |
| 4/17/2016 | 2016 | 4 | 17 | 291 | 33 | 49 | 41 | 9 | 5723.5 |
| 4/18/2016 | 2016 | 4 | 18 | 292 | 36 | 52 | 44 | 12 | 5735.5 |
| 4/19/2016 | 2016 | 4 | 19 | 293 | 26 | 63 | 44.5 | 12.5 | 5748 |
| 4/20/2016 | 2016 | 4 | 20 | 294 | 28 | 68 | 48 | 16 | 5764 |
| 4/21/2016 | 2016 | 4 | 21 | 295 | 32 | 79 | 55.5 | 23.5 | 5787.5 |
| 4/22/2016 | 2016 | 4 | 22 | 296 | 44 | 80 | 62 | 30 | 5817.5 |
| 4/23/2016 | 2016 | 4 | 23 | 297 | 41 | 77 | 59 | 27 | 5844.5 |
| 4/24/2016 | 2016 | 4 | 24 | 298 | 31 | 79 | 55 | 23 | 5867.5 |
| 4/25/2016 | 2016 | 4 | 25 | 299 | 34 | 73 | 53.5 | 21.5 | 5889 |
| 4/26/2016 | 2016 | 4 | 26 | 300 | 35 | 73 | 54 | 22 | 5911 |
| 4/27/2016 | 2016 | 4 | 27 | 301 | 32 | 60 | 46 | 14 | 5925 |
| 4/28/2016 | 2016 | 4 | 28 | 302 | 40 | 70 | 55 | 23 | 5948 |
| 4/29/2016 | 2016 | 4 | 29 | 303 | 32 | 71 | 51.5 | 19.5 | 5967.5 |
| 4/30/2016 | 2016 | 4 | 30 | 304 | 35 | 61 | 48 | 16 | 5983.5 |
| 5/1/2016 | 2016 | 5 | 1 | 305 | 32 | 62 | 47 | 15 | 5998.5 |
| 5/2/2016 | 2016 | 5 | 2 | 306 | 33 | 43 | 38 | 6 | 6004.5 |
| 5/3/2016 | 2016 | 5 | 3 | 307 | 33 | 64 | 48.5 | 16.5 | 6021 |
| 5/4/2016 | 2016 | 5 | 4 | 308 | 34 | 72 | 53 | 21 | 6042 |
| 5/5/2016 | 2016 | 5 | 5 | 309 | 38 | 75 | 56.5 | 24.5 | 6066.5 |
| 5/6/2016 | 2016 | 5 | 6 | 310 | 52 | 81 | 66.5 | 34.5 | 6101 |
| 5/7/2016 | 2016 | 5 | 7 | 311 | 33 | 83 | 58 | 26 | 6127 |
| 5/8/2016 | 2016 | 5 | 8 | 312 | 35 | 67 | 51 | 19 | 6146 |
| 5/9/2016 | 2016 | 5 | 9 | 313 | 40 | 64 | 52 | 20 | 6166 |
| 5/10/2016 | 2016 | 5 | 10 | 314 | 41 | 72 | 56.5 | 24.5 | 6190.5 |
| 5/11/2016 | 2016 | 5 | 11 | 315 | 40 | 79 | 59.5 | 27.5 | 6218 |
| 5/12/2016 | 2016 | 5 | 12 | 316 | 35 | 79 | 57 | 25 | 6243 |
| 5/13/2016 | 2016 | 5 | 13 | 317 | 35 | 83 | 59 | 27 | 6270 |
| 5/14/2016 | 2016 | 5 | 14 | 318 | 35 | 83 | 59 | 27 | 6297 |
| 5/15/2016 | 2016 | 5 | 15 | 319 | 47 | 87 | 67 | 35 | 6332 |
| 5/16/2016 | 2016 | 5 | 16 | 320 | 40 | 82 | 61 | 29 | 6361 |
| 5/17/2016 | 2016 | 5 | 17 | 321 | 36 | 77 | 56.5 | 24.5 | 6385.5 |
| 5/18/2016 | 2016 | 5 | 18 | 322 | 33 | 65 | 49 | 17 | 6402.5 |
| 5/19/2016 | 2016 | 5 | 19 | 323 | 29 | 59 | 44 | 12 | 6414.5 |
| 5/20/2016 | 2016 | 5 | 20 | 324 | 34 | 76 | 55 | 23 | 6437.5 |
| 5/21/2016 | 2016 | 5 | 21 | 325 | 44 | 81 | 62.5 | 30.5 | 6468 |
| 5/22/2016 | 2016 | 5 | 22 | 326 | 39 | 82 | 60.5 | 28.5 | 6496.5 |
| 5/23/2016 | 2016 | 5 | 23 | 327 | 35 | 81 | 58 | 26 | 6522.5 |
| 5/24/2016 | 2016 | 5 | 24 | 328 | 35 | 81 | 58 | 26 | 6548.5 |
| 5/25/2016 | 2016 | 5 | 25 | 329 | 37 | 80 | 58.5 | 26.5 | 6575 |
| 5/26/2016 | 2016 | 5 | 26 | 330 | 34 | 79 | 56.5 | 24.5 | 6599.5 |
| 5/27/2016 | 2016 | 5 | 27 | 331 | 37 | 69 | 53 | 21 | 6620.5 |
| 5/28/2016 | 2016 | 5 | 28 | 332 | 33 | 77 | 55 | 23 | 6643.5 |
| 5/29/2016 | 2016 | 5 | 29 | 333 | 31 | 79 | 55 | 23 | 6666.5 |
| 5/30/2016 | 2016 | 5 | 30 | 334 | 32 | 84 | 58 | 26 | 6692.5 |
| 5/31/2016 | 2016 | 5 | 31 | 335 | 40 | 83 | 61.5 | 29.5 | 6722 |
| 6/2/2016 | 2016 | 6 | 2 | 1 | 45 | 79 | 62 | 30 | 30 |
| 6/3/2016 | 2016 | 6 | 3 | 2 | 46 | 82 | 64 | 32 | 62 |
| 6/4/2016 | 2016 | 6 | 4 | 3 | 41 | 94 | 67.5 | 35.5 | 97.5 |
| 6/5/2016 | 2016 | 6 | 5 | 4 | 41 | 94 | 67.5 | 35.5 | 133 |
| 6/6/2016 | 2016 | 6 | 6 | 5 | 43 | 91 | 67 | 35 | 168 |
| 6/8/2016 | 2016 | 6 | 8 | 6 | 45 | 96 | 70.5 | 38.5 | 206.5 |
| 6/9/2016 | 2016 | 6 | 9 | 7 | 58 | 96 | 77 | 45 | 251.5 |
| 6/10/2016 | 2016 | 6 | 10 | 8 | 49 | 97 | 73 | 41 | 292.5 |
| 6/11/2016 | 2016 | 6 | 11 | 9 | 52 | 100 | 76 | 44 | 336.5 |
| 6/12/2016 | 2016 | 6 | 12 | 10 | 51 | 85 | 68 | 36 | 372.5 |
| 6/13/2016 | 2016 | 6 | 13 | 11 | 49 | 94 | 71.5 | 39.5 | 412 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/14/2016 | 2016 | 6 | 14 | 12 | 42 | 90 | 66 | 34 | 446 |
| 6/15/2016 | 2016 | 6 | 15 | 13 | 41 | 89 | 65 | 33 | 479 |
| 6/16/2016 | 2016 | 6 | 16 | 14 | 42 | 92 | 67 | 35 | 514 |
| 6/17/2016 | 2016 | 6 | 17 | 15 | 40 | 91 | 65.5 | 33.5 | 547.5 |
| 6/18/2016 | 2016 | 6 | 18 | 16 | 40 | 96 | 68 | 36 | 583.5 |
| 6/19/2016 | 2016 | 6 | 19 | 17 | 49 | 97 | 73 | 41 | 624.5 |
| 6/20/2016 | 2016 | 6 | 20 | 18 | 49 | 103 | 76 | 44 | 668.5 |
| 6/21/2016 | 2016 | 6 | 21 | 19 | 49 | 96 | 72.5 | 40.5 | 709 |
| 6/22/2016 | 2016 | 6 | 22 | 20 | 59 | 100 | 79.5 | 47.5 | 756.5 |
| 6/23/2016 | 2016 | 6 | 23 | 21 | 57 | 100 | 78.5 | 46.5 | 803 |
| 6/24/2016 | 2016 | 6 | 24 | 22 | 53 | 98 | 75.5 | 43.5 | 846.5 |
| 6/25/2016 | 2016 | 6 | 25 | 23 | 56 | 92 | 74 | 42 | 888.5 |
| 6/26/2016 | 2016 | 6 | 26 | 24 | 61 | 92 | 76.5 | 44.5 | 933 |
| 6/27/2016 | 2016 | 6 | 27 | 25 | 49 | 91 | 70 | 38 | 971 |
| 6/28/2016 | 2016 | 6 | 28 | 26 | 60 | 91 | 75.5 | 43.5 | 1014.5 |
| 6/29/2016 | 2016 | 6 | 29 | 27 | 51 | 90 | 70.5 | 38.5 | 1053 |
| 6/30/2016 | 2016 | 6 | 30 | 28 | 59 | 92 | 75.5 | 43.5 | 1096.5 |
| 7/1/2016 | 2016 | 7 | 1 | 29 | 58 | 87 | 72.5 | 40.5 | 1137 |
| 7/2/2016 | 2016 | 7 | 2 | 30 | 51 | 87 | 69 | 37 | 1174 |
| 7/3/2016 | 2016 | 7 | 3 | 31 | 51 | 85 | 68 | 36 | 1210 |
| 7/4/2016 | 2016 | 7 | 4 | 32 | 50 | 94 | 72 | 40 | 1250 |
| 7/5/2016 | 2016 | 7 | 5 | 33 | 51 | 96 | 73.5 | 41.5 | 1291.5 |
| 7/6/2016 | 2016 | 7 | 6 | 34 | 60 | 96 | 78 | 46 | 1337.5 |
| 7/7/2016 | 2016 | 7 | 7 | 35 | 56 | 96 | 76 | 44 | 1381.5 |
| 7/8/2016 | 2016 | 7 | 8 | 36 | 55 | 95 | 75 | 43 | 1424.5 |
| 7/9/2016 | 2016 | 7 | 9 | 37 | 53 | 97 | 75 | 43 | 1467.5 |
| 7/10/2016 | 2016 | 7 | 10 | 38 | 60 | 98 | 79 | 47 | 1514.5 |
| 7/11/2016 | 2016 | 7 | 11 | 39 | 54 | 95 | 74.5 | 42.5 | 1557 |
| 7/12/2016 | 2016 | 7 | 12 | 40 | 52 | 95 | 73.5 | 41.5 | 1598.5 |
| 7/13/2016 | 2016 | 7 | 13 | 41 | 57 | 96 | 76.5 | 44.5 | 1643 |
| 7/14/2016 | 2016 | 7 | 14 | 42 | 57 | 96 | 76.5 | 44.5 | 1687.5 |
| 7/15/2016 | 2016 | 7 | 15 | 43 | 57 | 100 | 78.5 | 46.5 | 1734 |
| 7/16/2016 | 2016 | 7 | 16 | 44 | 57 | 101 | 79 | 47 | 1781 |
| 7/17/2016 | 2016 | 7 | 17 | 45 | 57 | 100 | 78.5 | 46.5 | 1827.5 |
| 7/18/2016 | 2016 | 7 | 18 | 46 | 56 | 100 | 78 | 46 | 1873.5 |
| 7/19/2016 | 2016 | 7 | 19 | 47 | 55 | 100 | 77.5 | 45.5 | 1919 |
| 7/20/2016 | 2016 | 7 | 20 | 48 | 60 | 90 | 75 | 43 | 1962 |
| 7/21/2016 | 2016 | 7 | 21 | 49 | 50 | 89 | 69.5 | 37.5 | 1999.5 |
| 7/22/2016 | 2016 | 7 | 22 | 50 | 50 | 95 | 72.5 | 40.5 | 2040 |
| 7/23/2016 | 2016 | 7 | 23 | 51 | 57 | 97 | 77 | 45 | 2085 |
| 7/24/2016 | 2016 | 7 | 24 | 52 | 56 | 100 | 78 | 46 | 2131 |
| 7/25/2016 | 2016 | 7 | 25 | 53 | 56 | 100 | 78 | 46 | 2177 |
| 7/26/2016 | 2016 | 7 | 26 | 54 | 60 | 93 | 76.5 | 44.5 | 2221.5 |
| 7/27/2016 | 2016 | 7 | 27 | 55 | 54 | 88 | 71 | 39 | 2260.5 |
| 7/28/2016 | 2016 | 7 | 28 | 56 | 67 | 92 | 79.5 | 47.5 | 2308 |
| 7/29/2016 | 2016 | 7 | 29 | 57 | 53 | 93 | 73 | 41 | 2349 |
| 7/30/2016 | 2016 | 7 | 30 | 58 | 55 | 98 | 76.5 | 44.5 | 2393.5 |
| 7/31/2016 | 2016 | 7 | 31 | 59 | 59 | 95 | 77 | 45 | 2438.5 |
| 8/1/2016 | 2016 | 8 | 1 | 60 | 60 | 94 | 77 | 45 | 2483.5 |
| 8/2/2016 | 2016 | 8 | 2 | 61 | 58 | 93 | 75.5 | 43.5 | 2527 |
| 8/3/2016 | 2016 | 8 | 3 | 62 | 59 | 90 | 74.5 | 42.5 | 2569.5 |
| 8/4/2016 | 2016 | 8 | 4 | 63 | 57 | 90 | 73.5 | 41.5 | 2611 |
| 8/5/2016 | 2016 | 8 | 5 | 64 | 60 | 90 | 75 | 43 | 2654 |
| 8/6/2016 | 2016 | 8 | 6 | 65 | 52 | 79 | 65.5 | 33.5 | 2687.5 |
| 8/7/2016 | 2016 | 8 | 7 | 66 | 51 | 84 | 67.5 | 35.5 | 2723 |
| 8/8/2016 | 2016 | 8 | 8 | 67 | 53 | 88 | 70.5 | 38.5 | 2761.5 |
| 8/9/2016 | 2016 | 8 | 9 | 68 | 50 | 88 | 69 | 37 | 2798.5 |
| 8/10/2016 | 2016 | 8 | 10 | 69 | 60 | 90 | 75 | 43 | 2841.5 |
| 8/11/2016 | 2016 | 8 | 11 | 70 | 56 | 92 | 74 | 42 | 2883.5 |
| 8/12/2016 | 2016 | 8 | 12 | 71 | 50 | 87 | 68.5 | 36.5 | 2920 |
| 8/13/2016 | 2016 | 8 | 13 | 72 | 60 | 91 | 75.5 | 43.5 | 2963.5 |
| 8/14/2016 | 2016 | 8 | 14 | 73 | 49 | 83 | 66 | 34 | 2997.5 |
| 8/15/2016 | 2016 | 8 | 15 | 74 | 50 | 86 | 68 | 36 | 3033.5 |
| 8/16/2016 | 2016 | 8 | 16 | 75 | 50 | 95 | 72.5 | 40.5 | 3074 |
| 8/17/2016 | 2016 | 8 | 17 | 76 | 52 | 88 | 70 | 38 | 3112 |
| 8/18/2016 | 2016 | 8 | 18 | 77 | 52 | 87 | 69.5 | 37.5 | 3149.5 |
| 8/19/2016 | 2016 | 8 | 19 | 78 | 51 | 85 | 68 | 36 | 3185.5 |
| 8/20/2016 | 2016 | 8 | 20 | 79 | 51 | 85 | 68 | 36 | 3221.5 |
| 8/21/2016 | 2016 | 8 | 21 | 80 | 50 | 85 | 67.5 | 35.5 | 3257 |
| 8/22/2016 | 2016 | 8 | 22 | 81 | 51 | 82 | 66.5 | 34.5 | 3291.5 |
| 8/23/2016 | 2016 | 8 | 23 | 82 | 47 | 81 | 64 | 32 | 3323.5 |
| 8/24/2016 | 2016 | 8 | 24 | 83 | 46 | 78 | 62 | 30 | 3353.5 |
| 8/25/2016 | 2016 | 8 | 25 | 84 | 45 | 81 | 63 | 31 | 3384.5 |
| 8/26/2016 | 2016 | 8 | 26 | 85 | 47 | 83 | 65 | 33 | 3417.5 |
| 8/27/2016 | 2016 | 8 | 27 | 86 | 50 | 79 | 64.5 | 32.5 | 3450 |
| 8/28/2016 | 2016 | 8 | 28 | 87 | 45 | 80 | 62.5 | 30.5 | 3480.5 |
| 8/29/2016 | 2016 | 8 | 29 | 88 | 42 | 77 | 59.5 | 27.5 | 3508 |
| 8/30/2016 | 2016 | 8 | 30 | 89 | 46 | 83 | 64.5 | 32.5 | 3540.5 |
| 8/31/2016 | 2016 | 8 | 31 | 90 | 52 | 82 | 67 | 35 | 3575.5 |
| 9/1/2016 | 2016 | 9 | 1 | 91 | 53 | 84 | 68.5 | 36.5 | 3612 |
| 9/2/2016 | 2016 | 9 | 2 | 92 | 54 | 86 | 70 | 38 | 3650 |
| 9/3/2016 | 2016 | 9 | 3 | 93 | 51 | 85 | 68 | 36 | 3686 |
| 9/4/2016 | 2016 | 9 | 4 | 94 | 48 | 85 | 66.5 | 34.5 | 3720.5 |
| 9/5/2016 | 2016 | 9 | 5 | 95 | 44 | 89 | 66.5 | 34.5 | 3755 |
| 9/6/2016 | 2016 | 9 | 6 | 96 | 47 | 92 | 69.5 | 37.5 | 3792.5 |
| 9/7/2016 | 2016 | 9 | 7 | 97 | 50 | 86 | 68 | 36 | 3828.5 |
| 9/8/2016 | 2016 | 9 | 8 | 98 | 46 | 76 | 61 | 29 | 3857.5 |
| 9/9/2016 | 2016 | 9 | 9 | 99 | 39 | 90 | 64.5 | 32.5 | 3890 |
| 9/10/2016 | 2016 | 9 | 10 | 100 | 48 | 92 | 70 | 38 | 3928 |
| 9/11/2016 | 2016 | 9 | 11 | 101 | 53 | 80 | 66.5 | 34.5 | 3962.5 |
| 9/12/2016 | 2016 | 9 | 12 | 102 | 43 | 91 | 67 | 35 | 3997.5 |
| 9/13/2016 | 2016 | 9 | 13 | 103 | 43 | 85 | 64 | 32 | 4029.5 |
| 9/14/2016 | 2016 | 9 | 14 | 104 | 46 | 81 | 63.5 | 31.5 | 4061 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/15/2016 | 2016 | 9 | 15 | 105 | 40 | 81 | 60.5 | 28.5 | 4089.5 |
| 9/16/2016 | 2016 | 9 | 16 | 106 | 37 | 85 | 61 | 29 | 4118.5 |
| 9/17/2016 | 2016 | 9 | 17 | 107 | 37 | 81 | 59 | 27 | 4145.5 |
| 9/18/2016 | 2016 | 9 | 18 | 108 | 33 | 87 | 60 | 28 | 4173.5 |
| 9/19/2016 | 2016 | 9 | 19 | 109 | 33 | 87 | 60 | 28 | 4201.5 |
| 9/20/2016 | 2016 | 9 | 20 | 110 | 41 | 92 | 66.5 | 34.5 | 4236 |
| 9/21/2016 | 2016 | 9 | 21 | 111 | 53 | 88 | 70.5 | 38.5 | 4274.5 |
| 9/22/2016 | 2016 | 9 | 22 | 112 | 48 | 82 | 65 | 33 | 4307.5 |
| 9/23/2016 | 2016 | 9 | 23 | 113 | 52 | 87 | 69.5 | 37.5 | 4345 |
| 9/24/2016 | 2016 | 9 | 24 | 114 | 27 | 87 | 57 | 25 | 4370 |
| 9/25/2016 | 2016 | 9 | 25 | 115 | 31 | 72 | 51.5 | 19.5 | 4389.5 |
| 9/26/2016 | 2016 | 9 | 26 | 116 | 38 | 73 | 55.5 | 23.5 | 4413 |
| 9/27/2016 | 2016 | 9 | 27 | 117 | 40 | 71 | 55.5 | 23.5 | 4436.5 |
| 9/28/2016 | 2016 | 9 | 28 | 118 | 39 | 78 | 58.5 | 26.5 | 4463 |
| 9/29/2016 | 2016 | 9 | 29 | 119 | 45 | 74 | 59.5 | 27.5 | 4490.5 |
| 9/30/2016 | 2016 | 9 | 30 | 120 | 45 | 77 | 61 | 29 | 4519.5 |
| 10/1/2016 | 2016 | 10 | 1 | 121 | 40 | 78 | 59 | 27 | 4546.5 |
| 10/2/2016 | 2016 | 10 | 2 | 122 | 41 | 79 | 60 | 28 | 4574.5 |
| 10/3/2016 | 2016 | 10 | 3 | 123 | 45 | 79 | 62 | 30 | 4604.5 |
| 10/4/2016 | 2016 | 10 | 4 | 124 | 36 | 74 | 55 | 23 | 4627.5 |
| 10/5/2016 | 2016 | 10 | 5 | 125 | 32 | 72 | 52 | 20 | 4647.5 |
| 10/6/2016 | 2016 | 10 | 6 | 126 | 37 | 72 | 54.5 | 22.5 | 4670 |
| 10/7/2016 | 2016 | 10 | 7 | 127 | 29 | 75 | 52 | 20 | 4690 |
| 10/8/2016 | 2016 | 10 | 8 | 128 | 32 | 68 | 50 | 18 | 4708 |
| 10/9/2016 | 2016 | 10 | 9 | 129 | 41 | 69 | 55 | 23 | 4731 |
| 10/10/2016 | 2016 | 10 | 10 | 130 | 35 | 75 | 55 | 23 | 4754 |
| 10/11/2016 | 2016 | 10 | 11 | 131 | 36 | 80 | 58 | 26 | 4780 |
| 10/12/2016 | 2016 | 10 | 12 | 132 | 35 | 81 | 58 | 26 | 4806 |
| 10/13/2016 | 2016 | 10 | 13 | 133 | 31 | 78 | 54.5 | 22.5 | 4828.5 |
| 10/14/2016 | 2016 | 10 | 14 | 134 | 31 | 81 | 56 | 24 | 4852.5 |
| 10/15/2016 | 2016 | 10 | 15 | 135 | 33 | 86 | 59.5 | 27.5 | 4880 |
| 10/16/2016 | 2016 | 10 | 16 | 136 | 39 | 85 | 62 | 30 | 4910 |
| 10/17/2016 | 2016 | 10 | 17 | 137 | 46 | 80 | 63 | 31 | 4941 |
| 10/18/2016 | 2016 | 10 | 18 | 138 | 40 | 84 | 62 | 30 | 4971 |
| 10/19/2016 | 2016 | 10 | 19 | 139 | 34 | 81 | 57.5 | 25.5 | 4996.5 |
| 10/20/2016 | 2016 | 10 | 20 | 140 | 22 | 72 | 47 | 15 | 5011.5 |
| 10/21/2016 | 2016 | 10 | 21 | 141 | 24 | 67 | 45.5 | 13.5 | 5025 |
| 10/22/2016 | 2016 | 10 | 22 | 142 | 27 | 82 | 54.5 | 22.5 | 5047.5 |
| 10/23/2016 | 2016 | 10 | 23 | 143 | 34 | 83 | 58.5 | 26.5 | 5074 |
| 10/24/2016 | 2016 | 10 | 24 | 144 | 32 | 83 | 57.5 | 25.5 | 5099.5 |
| 10/25/2016 | 2016 | 10 | 25 | 145 | 34 | 76 | 55 | 23 | 5122.5 |
| 10/26/2016 | 2016 | 10 | 26 | 146 | 34 | 76 | 55 | 23 | 5145.5 |
| 10/27/2016 | 2016 | 10 | 27 | 147 | 32 | 78 | 55 | 23 | 5168.5 |
| 10/28/2016 | 2016 | 10 | 28 | 148 | 33 | 79 | 56 | 24 | 5192.5 |
| 10/29/2016 | 2016 | 10 | 29 | 149 | 36 | 79 | 57.5 | 25.5 | 5218 |
| 10/30/2016 | 2016 | 10 | 30 | 150 | 34 | 80 | 57 | 25 | 5243 |
| 10/31/2016 | 2016 | 10 | 31 | 151 | 41 | 78 | 59.5 | 27.5 | 5270.5 |
| 11/1/2016 | 2016 | 11 | 1 | 152 | 40 | 75 | 57.5 | 25.5 | 5296 |
| 11/2/2016 | 2016 | 11 | 2 | 153 | 32 | 69 | 50.5 | 18.5 | 5314.5 |
| 11/3/2016 | 2016 | 11 | 3 | 154 | 34 | 69 | 51.5 | 19.5 | 5334 |
| 11/4/2016 | 2016 | 11 | 4 | 155 | 45 | 68 | 56.5 | 24.5 | 5358.5 |
| 11/5/2016 | 2016 | 11 | 5 | 156 | 42 | 58 | 50 | 18 | 5376.5 |
| 11/6/2016 | 2016 | 11 | 6 | 157 | 34 | 62 | 48 | 16 | 5392.5 |
| 11/7/2016 | 2016 | 11 | 7 | 158 | 32 | 63 | 47.5 | 15.5 | 5408 |
| 11/8/2016 | 2016 | 11 | 8 | 159 | 29 | 69 | 49 | 17 | 5425 |
| 11/9/2016 | 2016 | 11 | 9 | 160 | 27 | 63 | 45 | 13 | 5438 |
| 11/10/2016 | 2016 | 11 | 10 | 161 | 23 | 63 | 43 | 11 | 5449 |
| 11/11/2016 | 2016 | 11 | 11 | 162 | 25 | 60 | 42.5 | 10.5 | 5459.5 |
| 11/12/2016 | 2016 | 11 | 12 | 163 | 24 | 61 | 42.5 | 10.5 | 5470 |
| 11/13/2016 | 2016 | 11 | 13 | 164 | 23 | 67 | 45 | 13 | 5483 |
| 11/14/2016 | 2016 | 11 | 14 | 165 | 24 | 67 | 45.5 | 13.5 | 5496.5 |
| 11/15/2016 | 2016 | 11 | 15 | 166 | 24 | 67 | 45.5 | 13.5 | 5510 |
| 11/16/2016 | 2016 | 11 | 16 | 167 | 27 | 75 | 51 | 19 | 5529 |
| 11/17/2016 | 2016 | 11 | 17 | 168 | 33 | 72 | 52.5 | 20.5 | 5549.5 |
| 11/18/2016 | 2016 | 11 | 18 | 169 | 15 | 52 | 33.5 | 1.5 | 5551 |
| 11/19/2016 | 2016 | 11 | 19 | 170 | 19 | 58 | 38.5 | 6.5 | 5557.5 |
| 11/20/2016 | 2016 | 11 | 20 | 171 | 23 | 58 | 40.5 | 8.5 | 5566 |
| 11/21/2016 | 2016 | 11 | 21 | 172 | 26 | 66 | 46 | 14 | 5580 |
| 11/22/2016 | 2016 | 11 | 22 | 173 | 33 | 56 | 44.5 | 12.5 | 5592.5 |
| 11/23/2016 | 2016 | 11 | 23 | 174 | 19 | 54 | 36.5 | 4.5 | 5597 |
| 11/24/2016 | 2016 | 11 | 24 | 175 | 22 | 56 | 39 | 7 | 5604 |
| 11/25/2016 | 2016 | 11 | 25 | 176 | 14 | 52 | 33 | 1 | 5605 |
| 11/26/2016 | 2016 | 11 | 26 | 177 | 14 | 52 | 33 | 1 | 5606 |
| 11/27/2016 | 2016 | 11 | 27 | 178 | 14 | 53 | 33.5 | 1.5 | 5607.5 |
| 11/28/2016 | 2016 | 11 | 28 | 179 | 14 | 48 | 31 | -1 | 5606.5 |
| 11/29/2016 | 2016 | 11 | 29 | 180 | 14 | 37 | 25.5 | -6.5 | 5600 |
| 11/30/2016 | 2016 | 11 | 30 | 181 | 3 | 33 | 18 | -14 | 5586 |
| 12/1/2016 | 2016 | 12 | 1 | 182 | 8 | 38 | 23 | -9 | 5577 |
| 12/2/2016 | 2016 | 12 | 2 | 183 | 13 | 48 | 30.5 | -1.5 | 5575.5 |
| 12/3/2016 | 2016 | 12 | 3 | 184 | 19 | 46 | 32.5 | 0.5 | 5576 |
| 12/4/2016 | 2016 | 12 | 4 | 185 | 11 | 46 | 28.5 | -3.5 | 5572.5 |
| 12/5/2016 | 2016 | 12 | 5 | 186 | 13 | 49 | 31 | -1 | 5571.5 |
| 12/6/2016 | 2016 | 12 | 6 | 187 | 18 | 54 | 36 | 4 | 5575.5 |
| 12/7/2016 | 2016 | 12 | 7 | 188 | 36 | 50 | 43 | 11 | 5586.5 |
| 12/8/2016 | 2016 | 12 | 8 | 189 | 18 | 47 | 32.5 | 0.5 | 5587 |
| 12/9/2016 | 2016 | 12 | 9 | 190 | 15 | 44 | 29.5 | -2.5 | 5584.5 |
| 12/10/2016 | 2016 | 12 | 10 | 191 | 17 | 63 | 40 | 8 | 5592.5 |
| 12/11/2016 | 2016 | 12 | 11 | 192 | 25 | 66 | 45.5 | 13.5 | 5606 |
| 12/12/2016 | 2016 | 12 | 12 | 193 | 20 | 60 | 40 | 8 | 5614 |
| 12/13/2016 | 2016 | 12 | 13 | 194 | 26 | 61 | 43.5 | 11.5 | 5625.5 |
| 12/14/2016 | 2016 | 12 | 14 | 195 | 28 | 61 | 44.5 | 12.5 | 5638 |
| 12/15/2016 | 2016 | 12 | 15 | 196 | 28 | 61 | 44.5 | 12.5 | 5650.5 |
| 12/16/2016 | 2016 | 12 | 16 | 197 | 27 | 63 | 45 | 13 | 5663.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/17/2016 | 2016 | 12 | 17 | 198 | 28 | 53 | 40.5 | 8.5 | 5672 |
| 12/18/2016 | 2016 | 12 | 18 | 199 | 9 | 40 | 24.5 | -7.5 | 5664.5 |
| 12/19/2016 | 2016 | 12 | 19 | 200 | 8 | 41 | 24.5 | -7.5 | 5657 |
| 12/20/2016 | 2016 | 12 | 20 | 201 | 9 | 52 | 30.5 | -1.5 | 5655.5 |
| 12/21/2016 | 2016 | 12 | 21 | 202 | 15 | 55 | 35 | 3 | 5658.5 |
| 12/22/2016 | 2016 | 12 | 22 | 203 | 28 | 67 | 47.5 | 15.5 | 5674 |
| 12/23/2016 | 2016 | 12 | 23 | 204 | 33 | 39 | 36 | 4 | 5678 |
| 12/24/2016 | 2016 | 12 | 24 | 205 | 27 | 53 | 40 | 8 | 5686 |
| 12/25/2016 | 2016 | 12 | 25 | 206 | 23 | 48 | 35.5 | 3.5 | 5689.5 |
| 12/26/2016 | 2016 | 12 | 26 | 207 | 18 | 35 | 26.5 | -5.5 | 5684 |
| 12/27/2016 | 2016 | 12 | 27 | 208 | 17 | 43 | 30 | -2 | 5682 |
| 12/28/2016 | 2016 | 12 | 28 | 209 | 18 | 59 | 38.5 | 6.5 | 5688.5 |
| 12/29/2016 | 2016 | 12 | 29 | 210 | 22 | 53 | 37.5 | 5.5 | 5694 |
| 12/30/2016 | 2016 | 12 | 30 | 211 | 15 | 47 | 31 | -1 | 5693 |
| 12/31/2016 | 2016 | 12 | 31 | 212 | 17 | 55 | 36 | 4 | 5697 |
| 1/1/2017 | 2017 | 1 | 1 | 213 | 30 | 49 | 39.5 | 7.5 | 5704.5 |
| 1/2/2017 | 2017 | 1 | 2 | 214 | 29 | 49 | 39 | 7 | 5711.5 |
| 1/3/2017 | 2017 | 1 | 3 | 215 | 23 | 44 | 33.5 | 1.5 | 5713 |
| 1/4/2017 | 2017 | 1 | 4 | 216 | 22 | 50 | 36 | 4 | 5717 |
| 1/5/2017 | 2017 | 1 | 5 | 217 | 25 | 56 | 40.5 | 8.5 | 5725.5 |
| 1/6/2017 | 2017 | 1 | 6 | 218 | 20 | 53 | 36.5 | 4.5 | 5730 |
| 1/7/2017 | 2017 | 1 | 7 | 219 | 5 | 34 | 19.5 | -12.5 | 5717.5 |
| 1/8/2017 | 2017 | 1 | 8 | 220 | 5 | 41 | 23 | -9 | 5708.5 |
| 1/9/2017 | 2017 | 1 | 9 | 221 | 26 | 64 | 45 | 13 | 5721.5 |
| 1/10/2017 | 2017 | 1 | 10 | 222 | 32 | 61 | 46.5 | 14.5 | 5736 |
| 1/11/2017 | 2017 | 1 | 11 | 223 | 34 | 61 | 47.5 | 15.5 | 5751.5 |
| 1/12/2017 | 2017 | 1 | 12 | 224 | 22 | 55 | 38.5 | 6.5 | 5758 |
| 1/13/2017 | 2017 | 1 | 13 | 225 | 24 | 60 | 42 | 10 | 5768 |
| 1/14/2017 | 2017 | 1 | 14 | 226 | 23 | 53 | 38 | 6 | 5774 |
| 1/15/2017 | 2017 | 1 | 15 | 227 | 24 | 56 | 40 | 8 | 5782 |
| 1/16/2017 | 2017 | 1 | 16 | 228 | 30 | 44 | 37 | 5 | 5787 |
| 1/17/2017 | 2017 | 1 | 17 | 229 | 31 | 46 | 38.5 | 6.5 | 5793.5 |
| 1/18/2017 | 2017 | 1 | 18 | 230 | 27 | 44 | 35.5 | 3.5 | 5797 |
| 1/19/2017 | 2017 | 1 | 19 | 231 | 23 | 50 | 36.5 | 4.5 | 5801.5 |
| 1/20/2017 | 2017 | 1 | 20 | 232 | 25 | 47 | 36 | 4 | 5805.5 |
| 1/21/2017 | 2017 | 1 | 21 | 233 | 26 | 41 | 33.5 | 1.5 | 5807 |
| 1/22/2017 | 2017 | 1 | 22 | 234 | 17 | 40 | 28.5 | -3.5 | 5803.5 |
| 1/23/2017 | 2017 | 1 | 23 | 235 | 21 | 41 | 31 | -1 | 5802.5 |
| 1/24/2017 | 2017 | 1 | 24 | 236 | 25 | 54 | 39.5 | 7.5 | 5810 |
| 1/25/2017 | 2017 | 1 | 25 | 237 | 12 | 34 | 23 | -9 | 5801 |
| 1/26/2017 | 2017 | 1 | 26 | 238 | 9 | 36 | 22.5 | -9.5 | 5791.5 |
| 1/27/2017 | 2017 | 1 | 27 | 239 | 8 | 33 | 20.5 | -11.5 | 5780 |
| 1/28/2017 | 2017 | 1 | 28 | 240 | 4 | 32 | 18 | -14 | 5766 |
| 1/29/2017 | 2017 | 1 | 29 | 241 | 5 | 43 | 24 | -8 | 5758 |
| 1/30/2017 | 2017 | 1 | 30 | 242 | 14 | 53 | 33.5 | 1.5 | 5759.5 |
| 1/31/2017 | 2017 | 1 | 31 | 243 | 15 | 56 | 35.5 | 3.5 | 5763 |
| 2/1/2017 | 2017 | 2 | 1 | 244 | 17 | 64 | 40.5 | 8.5 | 5771.5 |
| 2/2/2017 | 2017 | 2 | 2 | 245 | 18 | 67 | 42.5 | 10.5 | 5782 |
| 2/3/2017 | 2017 | 2 | 3 | 246 | 20 | 65 | 42.5 | 10.5 | 5792.5 |
| 2/4/2017 | 2017 | 2 | 4 | 247 | 14 | 59 | 36.5 | 4.5 | 5797 |
| 2/5/2017 | 2017 | 2 | 5 | 248 | 15 | 62 | 38.5 | 6.5 | 5803.5 |
| 2/6/2017 | 2017 | 2 | 6 | 249 | 27 | 68 | 47.5 | 15.5 | 5819 |
| 2/7/2017 | 2017 | 2 | 7 | 250 | 31 | 62 | 46.5 | 14.5 | 5833.5 |
| 2/8/2017 | 2017 | 2 | 8 | 251 | 27 | 55 | 41 | 9 | 5842.5 |
| 2/9/2017 | 2017 | 2 | 9 | 252 | 22 | 62 | 42 | 10 | 5852.5 |
| 2/10/2017 | 2017 | 2 | 10 | 253 | 24 | 70 | 47 | 15 | 5867.5 |
| 2/11/2017 | 2017 | 2 | 11 | 254 | 24 | 74 | 49 | 17 | 5884.5 |
| 2/12/2017 | 2017 | 2 | 12 | 255 | 24 | 69 | 46.5 | 14.5 | 5899 |
| 2/13/2017 | 2017 | 2 | 13 | 256 | 25 | 46 | 35.5 | 3.5 | 5902.5 |
| 2/14/2017 | 2017 | 2 | 14 | 257 | 29 | 44 | 36.5 | 4.5 | 5907 |
| 2/15/2017 | 2017 | 2 | 15 | 258 | 19 | 47 | 33 | 1 | 5908 |
| 2/16/2017 | 2017 | 2 | 16 | 259 | 19 | 57 | 38 | 6 | 5914 |
| 2/17/2017 | 2017 | 2 | 17 | 260 | 24 | 63 | 43.5 | 11.5 | 5925.5 |
| 2/18/2017 | 2017 | 2 | 18 | 261 | 23 | 63 | 43 | 11 | 5936.5 |
| 2/19/2017 | 2017 | 2 | 19 | 262 | 31 | 54 | 42.5 | 10.5 | 5947 |
| 2/20/2017 | 2017 | 2 | 20 | 263 | 29 | 52 | 40.5 | 8.5 | 5955.5 |
| 2/21/2017 | 2017 | 2 | 21 | 264 | 25 | 63 | 44 | 12 | 5967.5 |
| 2/22/2017 | 2017 | 2 | 22 | 265 | 29 | 72 | 50.5 | 18.5 | 5986 |
| 2/23/2017 | 2017 | 2 | 23 | 266 | 38 | 62 | 50 | 18 | 6004 |
| 2/24/2017 | 2017 | 2 | 24 | 267 | 16 | 51 | 33.5 | 1.5 | 6005.5 |
| 2/25/2017 | 2017 | 2 | 25 | 268 | 8 | 48 | 28 | -4 | 6001.5 |
| 2/26/2017 | 2017 | 2 | 26 | 269 | 9 | 52 | 30.5 | -1.5 | 6000 |
| 2/27/2017 | 2017 | 2 | 27 | 270 | 20 | 48 | 34 | 2 | 6002 |
| 2/28/2017 | 2017 | 2 | 28 | 271 | 28 | 56 | 42 | 10 | 6012 |
| 3/1/2017 | 2017 | 3 | 1 | 272 | 19 | 49 | 34 | 2 | 6014 |
| 3/2/2017 | 2017 | 3 | 2 | 273 | 12 | 48 | 30 | -2 | 6012 |
| 3/3/2017 | 2017 | 3 | 3 | 274 | 11 | 58 | 34.5 | 2.5 | 6014.5 |
| 3/4/2017 | 2017 | 3 | 4 | 275 | 21 | 60 | 40.5 | 8.5 | 6023 |
| 3/5/2017 | 2017 | 3 | 5 | 276 | 34 | 64 | 49 | 17 | 6040 |
| 3/6/2017 | 2017 | 3 | 6 | 277 | 36 | 63 | 49.5 | 17.5 | 6057.5 |
| 3/7/2017 | 2017 | 3 | 7 | 278 | 13 | 54 | 33.5 | 1.5 | 6059 |
| 3/8/2017 | 2017 | 3 | 8 | 279 | 12 | 65 | 38.5 | 6.5 | 6065.5 |
| 3/9/2017 | 2017 | 3 | 9 | 280 | 22 | 73 | 47.5 | 15.5 | 6081 |
| 3/10/2017 | 2017 | 3 | 10 | 281 | 23 | 76 | 49.5 | 17.5 | 6098.5 |
| 3/11/2017 | 2017 | 3 | 11 | 282 | 22 | 79 | 50.5 | 18.5 | 6117 |
| 3/12/2017 | 2017 | 3 | 12 | 283 | 22 | 75 | 48.5 | 16.5 | 6133.5 |
| 3/13/2017 | 2017 | 3 | 13 | 284 | 24 | 74 | 49 | 17 | 6150.5 |
| 3/14/2017 | 2017 | 3 | 14 | 285 | 25 | 75 | 50 | 18 | 6168.5 |
| 3/15/2017 | 2017 | 3 | 15 | 286 | 23 | 77 | 50 | 18 | 6186.5 |
| 3/16/2017 | 2017 | 3 | 16 | 287 | 24 | 82 | 53 | 21 | 6207.5 |
| 3/17/2017 | 2017 | 3 | 17 | 288 | 29 | 79 | 54 | 22 | 6229.5 |
| 3/18/2017 | 2017 | 3 | 18 | 289 | 28 | 79 | 53.5 | 21.5 | 6251 |
| 3/19/2017 | 2017 | 3 | 19 | 290 | 28 | 81 | 54.5 | 22.5 | 6273.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/20/2017 | 2017 | 3 | 20 | 291 | 27 | 80 | 53.5 | 21.5 | 6295 |
| 3/21/2017 | 2017 | 3 | 21 | 292 | 30 | 82 | 56 | 24 | 6319 |
| 3/22/2017 | 2017 | 3 | 22 | 293 | 30 | 78 | 54 | 22 | 6341 |
| 3/23/2017 | 2017 | 3 | 23 | 294 | 34 | 78 | 56 | 24 | 6365 |
| 3/24/2017 | 2017 | 3 | 24 | 295 | 32 | 60 | 46 | 14 | 6379 |
| 3/25/2017 | 2017 | 3 | 25 | 296 | 22 | 68 | 45 | 13 | 6392 |
| 3/26/2017 | 2017 | 3 | 26 | 297 | 23 | 72 | 47.5 | 15.5 | 6407.5 |
| 3/27/2017 | 2017 | 3 | 27 | 298 | 24 | 68 | 46 | 14 | 6421.5 |
| 3/28/2017 | 2017 | 3 | 28 | 299 | 29 | 66 | 47.5 | 15.5 | 6437 |
| 3/29/2017 | 2017 | 3 | 29 | 300 | 35 | 59 | 47 | 15 | 6452 |
| 3/30/2017 | 2017 | 3 | 30 | 301 | 24 | 64 | 44 | 12 | 6464 |
| 3/31/2017 | 2017 | 3 | 31 | 302 | 30 | 71 | 50.5 | 18.5 | 6482.5 |
| 4/1/2017 | 2017 | 4 | 1 | 303 | 27 | 55 | 41 | 9 | 6491.5 |
| 4/2/2017 | 2017 | 4 | 2 | 304 | 26 | 43 | 34.5 | 2.5 | 6494 |
| 4/3/2017 | 2017 | 4 | 3 | 305 | 30 | 63 | 46.5 | 14.5 | 6508.5 |
| 4/4/2017 | 2017 | 4 | 4 | 306 | 34 | 67 | 50.5 | 18.5 | 6527 |
| 4/5/2017 | 2017 | 4 | 5 | 307 | 22 | 58 | 40 | 8 | 6535 |
| 4/6/2017 | 2017 | 4 | 6 | 308 | 22 | 66 | 44 | 12 | 6547 |
| 4/7/2017 | 2017 | 4 | 7 | 309 | 29 | 74 | 51.5 | 19.5 | 6566.5 |
| 4/8/2017 | 2017 | 4 | 8 | 310 | 29 | 78 | 53.5 | 21.5 | 6588 |
| 4/9/2017 | 2017 | 4 | 9 | 311 | 30 | 74 | 52 | 20 | 6608 |
| 4/10/2017 | 2017 | 4 | 10 | 312 | 20 | 67 | 43.5 | 11.5 | 6619.5 |
| 4/11/2017 | 2017 | 4 | 11 | 313 | 21 | 65 | 43 | 11 | 6630.5 |
| 4/12/2017 | 2017 | 4 | 12 | 314 | 33 | 71 | 52 | 20 | 6650.5 |
| 4/13/2017 | 2017 | 4 | 13 | 315 | 30 | 81 | 55.5 | 23.5 | 6674 |
| 4/14/2017 | 2017 | 4 | 14 | 316 | 32 | 78 | 55 | 23 | 6697 |
| 4/15/2017 | 2017 | 4 | 15 | 317 | 32 | 80 | 56 | 24 | 6721 |
| 4/16/2017 | 2017 | 4 | 16 | 318 | 29 | 79 | 54 | 22 | 6743 |
| 4/17/2017 | 2017 | 4 | 17 | 319 | 29 | 81 | 55 | 23 | 6766 |
| 4/18/2017 | 2017 | 4 | 18 | 320 | 36 | 80 | 58 | 26 | 6792 |
| 4/19/2017 | 2017 | 4 | 19 | 321 | 41 | 84 | 62.5 | 30.5 | 6822.5 |
| 4/20/2017 | 2017 | 4 | 20 | 322 | 32 | 81 | 56.5 | 24.5 | 6847 |
| 4/21/2017 | 2017 | 4 | 21 | 323 | 37 | 77 | 57 | 25 | 6872 |
| 4/22/2017 | 2017 | 4 | 22 | 324 | 30 | 80 | 55 | 23 | 6895 |
| 4/23/2017 | 2017 | 4 | 23 | 325 | 30 | 78 | 54 | 22 | 6917 |
| 4/24/2017 | 2017 | 4 | 24 | 326 | 40 | 83 | 61.5 | 29.5 | 6946.5 |
| 4/25/2017 | 2017 | 4 | 25 | 327 | 43 | 78 | 60.5 | 28.5 | 6975 |
| 4/26/2017 | 2017 | 4 | 26 | 328 | 26 | 63 | 44.5 | 12.5 | 6987.5 |
| 4/27/2017 | 2017 | 4 | 27 | 329 | 40 | 70 | 55 | 23 | 7010.5 |
| 4/28/2017 | 2017 | 4 | 28 | 330 | 38 | 73 | 55.5 | 23.5 | 7034 |
| 4/29/2017 | 2017 | 4 | 29 | 331 | 23 | 43 | 33 | 1 | 7035 |
| 4/30/2017 | 2017 | 4 | 30 | 332 | 23 | 52 | 37.5 | 5.5 | 7040.5 |
| 6/1/2017 | 2017 | 6 | 1 | 1 | 41 | 79 | 60 | 28 | 28 |
| 6/2/2017 | 2017 | 6 | 2 | 2 | 47 | 79 | 63 | 31 | 59 |
| 6/3/2017 | 2017 | 6 | 3 | 3 | 41 | 79 | 60 | 28 | 87 |
| 6/4/2017 | 2017 | 6 | 4 | 4 | 41 | 87 | 64 | 32 | 119 |
| 6/5/2017 | 2017 | 6 | 5 | 5 | 46 | 94 | 70 | 38 | 157 |
| 6/6/2017 | 2017 | 6 | 6 | 6 | 57 | 93 | 75 | 43 | 200 |
| 6/7/2017 | 2017 | 6 | 7 | 7 | 58 | 86 | 72 | 40 | 240 |
| 6/8/2017 | 2017 | 6 | 8 | 8 | 55 | 94 | 74.5 | 42.5 | 282.5 |
| 6/9/2017 | 2017 | 6 | 9 | 9 | 51 | 94 | 72.5 | 40.5 | 323 |
| 6/10/2017 | 2017 | 6 | 10 | 10 | 51 | 95 | 73 | 41 | 364 |
| 6/11/2017 | 2017 | 6 | 11 | 11 | 42 | 92 | 67 | 35 | 399 |
| 6/12/2017 | 2017 | 6 | 12 | 12 | 47 | 90 | 68.5 | 36.5 | 435.5 |
| 6/13/2017 | 2017 | 6 | 13 | 13 | 42 | 88 | 65 | 33 | 468.5 |
| 6/14/2017 | 2017 | 6 | 14 | 14 | 35 | 84 | 59.5 | 27.5 | 496 |
| 6/15/2017 | 2017 | 6 | 15 | 15 | 39 | 93 | 66 | 34 | 530 |
| 6/16/2017 | 2017 | 6 | 16 | 16 | 41 | 96 | 68.5 | 36.5 | 566.5 |
| 6/17/2017 | 2017 | 6 | 17 | 17 | 41 | 98 | 69.5 | 37.5 | 604 |
| 6/18/2017 | 2017 | 6 | 18 | 18 | 41 | 100 | 70.5 | 38.5 | 642.5 |
| 6/19/2017 | 2017 | 6 | 19 | 19 | 53 | 101 | 77 | 45 | 687.5 |
| 6/20/2017 | 2017 | 6 | 20 | 20 | 60 | 101 | 80.5 | 48.5 | 736 |
| 6/21/2017 | 2017 | 6 | 21 | 21 | 57 | 104 | 80.5 | 48.5 | 784.5 |
| 6/22/2017 | 2017 | 6 | 22 | 22 | 56 | 103 | 79.5 | 47.5 | 832 |
| 6/23/2017 | 2017 | 6 | 23 | 23 | 56 | 103 | 79.5 | 47.5 | 879.5 |
| 6/24/2017 | 2017 | 6 | 24 | 24 | 56 | 103 | 79.5 | 47.5 | 927 |
| 6/25/2017 | 2017 | 6 | 25 | 25 | 56 | 103 | 79.5 | 47.5 | 974.5 |
| 6/26/2017 | 2017 | 6 | 26 | 26 | 54 | 100 | 77 | 45 | 1019.5 |
| 6/27/2017 | 2017 | 6 | 27 | 27 | 53 | 82 | 67.5 | 35.5 | 1055 |
| 6/28/2017 | 2017 | 6 | 28 | 28 | 53 | 80 | 66.5 | 34.5 | 1089.5 |
| 6/29/2017 | 2017 | 6 | 29 | 29 | 52 | 80 | 66 | 34 | 1123.5 |
| 6/30/2017 | 2017 | 6 | 30 | 30 | 53 | 83 | 68 | 36 | 1159.5 |
| 7/1/2017 | 2017 | 7 | 1 | 31 | 50 | 83 | 66.5 | 34.5 | 1194 |
| 7/2/2017 | 2017 | 7 | 2 | 32 | 50 | 80 | 65 | 33 | 1227 |
| 7/3/2017 | 2017 | 7 | 3 | 33 | 51 | 81 | 66 | 34 | 1261 |
| 7/4/2017 | 2017 | 7 | 4 | 34 | 48 | 84 | 66 | 34 | 1295 |
| 7/5/2017 | 2017 | 7 | 5 | 35 | 54 | 85 | 69.5 | 37.5 | 1332.5 |
| 7/6/2017 | 2017 | 7 | 6 | 36 | 54 | 87 | 70.5 | 38.5 | 1371 |
| 7/7/2017 | 2017 | 7 | 7 | 37 | 54 | 83 | 68.5 | 36.5 | 1407.5 |
| 7/8/2017 | 2017 | 7 | 8 | 38 | 51 | 80 | 65.5 | 33.5 | 1441 |
| 7/9/2017 | 2017 | 7 | 9 | 39 | 53 | 80 | 66.5 | 34.5 | 1475.5 |
| 7/10/2017 | 2017 | 7 | 10 | 40 | 50 | 82 | 66 | 34 | 1509.5 |
| 7/11/2017 | 2017 | 7 | 11 | 41 | 50 | 80 | 65 | 33 | 1542.5 |
| 7/12/2017 | 2017 | 7 | 12 | 42 | 51 | 74 | 62.5 | 30.5 | 1573 |
| 7/13/2017 | 2017 | 7 | 13 | 43 | 50 | 77 | 63.5 | 31.5 | 1604.5 |
| 7/14/2017 | 2017 | 7 | 14 | 44 | 52 | 74 | 63 | 31 | 1635.5 |
| 7/15/2017 | 2017 | 7 | 15 | 45 | 56 | 77 | 66.5 | 34.5 | 1670 |
| 7/16/2017 | 2017 | 7 | 16 | 46 | 50 | 80 | 65 | 33 | 1703 |
| 7/17/2017 | 2017 | 7 | 17 | 47 | 49 | 76 | 62.5 | 30.5 | 1733.5 |
| 7/18/2017 | 2017 | 7 | 18 | 48 | 50 | 77 | 63.5 | 31.5 | 1765 |
| 7/19/2017 | 2017 | 7 | 19 | 49 | 50 | 79 | 64.5 | 32.5 | 1797.5 |
| 7/20/2017 | 2017 | 7 | 20 | 50 | 51 | 71 | 61 | 29 | 1826.5 |
| 7/21/2017 | 2017 | 7 | 21 | 51 | 51 | 75 | 63 | 31 | 1857.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/22/2017 | 2017 | 7 | 22 | 52 | 49 | 79 | 64 | 32 | 1889.5 |
| 7/23/2017 | 2017 | 7 | 23 | 53 | 52 | 76 | 64 | 32 | 1921.5 |
| 7/24/2017 | 2017 | 7 | 24 | 54 | 53 | 73 | 63 | 31 | 1952.5 |
| 7/25/2017 | 2017 | 7 | 25 | 55 | 53 | 72 | 62.5 | 30.5 | 1983 |
| 7/26/2017 | 2017 | 7 | 26 | 56 | 53 | 77 | 65 | 33 | 2016 |
| 7/27/2017 | 2017 | 7 | 27 | 57 | 55 | 76 | 65.5 | 33.5 | 2049.5 |
| 7/28/2017 | 2017 | 7 | 28 | 58 | 53 | 71 | 62 | 30 | 2079.5 |
| 7/29/2017 | 2017 | 7 | 29 | 59 | 48 | 68 | 58 | 26 | 2105.5 |
| 7/30/2017 | 2017 | 7 | 30 | 60 | 51 | 69 | 60 | 28 | 2133.5 |
| 7/31/2017 | 2017 | 7 | 31 | 61 | 51 | 67 | 59 | 27 | 2160.5 |
| 8/1/2017 | 2017 | 8 | 1 | 62 | 52 | 74 | 63 | 31 | 2191.5 |
| 8/2/2017 | 2017 | 8 | 2 | 63 | 53 | 75 | 64 | 32 | 2223.5 |
| 8/3/2017 | 2017 | 8 | 3 | 64 | 51 | 79 | 65 | 33 | 2256.5 |
| 8/4/2017 | 2017 | 8 | 4 | 65 | 51 | 74 | 62.5 | 30.5 | 2287 |
| 8/5/2017 | 2017 | 8 | 5 | 66 | 49 | 73 | 61 | 29 | 2316 |
| 8/6/2017 | 2017 | 8 | 6 | 67 | 48 | 73 | 60.5 | 28.5 | 2344.5 |
| 8/7/2017 | 2017 | 8 | 7 | 68 | 47 | 76 | 61.5 | 29.5 | 2374 |
| 8/8/2017 | 2017 | 8 | 8 | 69 | 48 | 76 | 62 | 30 | 2404 |
| 8/9/2017 | 2017 | 8 | 9 | 70 | 49 | 79 | 64 | 32 | 2436 |
| 8/10/2017 | 2017 | 8 | 10 | 71 | 51 | 77 | 64 | 32 | 2468 |
| 8/11/2017 | 2017 | 8 | 11 | 72 | 51 | 64 | 57.5 | 25.5 | 2493.5 |
| 8/12/2017 | 2017 | 8 | 12 | 73 | 48 | 76 | 62 | 30 | 2523.5 |
| 8/13/2017 | 2017 | 8 | 13 | 74 | 50 | 74 | 62 | 30 | 2553.5 |
| 8/14/2017 | 2017 | 8 | 14 | 75 | 51 | 76 | 63.5 | 31.5 | 2585 |
| 8/15/2017 | 2017 | 8 | 15 | 76 | 46 | 71 | 58.5 | 26.5 | 2611.5 |
| 8/16/2017 | 2017 | 8 | 16 | 77 | 41 | 73 | 57 | 25 | 2636.5 |
| 8/17/2017 | 2017 | 8 | 17 | 78 | 46 | 77 | 61.5 | 29.5 | 2666 |
| 8/18/2017 | 2017 | 8 | 18 | 79 | 47 | 79 | 63 | 31 | 2697 |
| 8/19/2017 | 2017 | 8 | 19 | 80 | 48 | 80 | 64 | 32 | 2729 |
| 8/20/2017 | 2017 | 8 | 20 | 81 | 49 | 70 | 59.5 | 27.5 | 2756.5 |
| 8/21/2017 | 2017 | 8 | 21 | 82 | 47 | 67 | 57 | 25 | 2781.5 |
| 8/22/2017 | 2017 | 8 | 22 | 83 | 48 | 78 | 63 | 31 | 2812.5 |
| 8/23/2017 | 2017 | 8 | 23 | 84 | 48 | 77 | 62.5 | 30.5 | 2843 |
| 8/24/2017 | 2017 | 8 | 24 | 85 | 45 | 65 | 55 | 23 | 2866 |
| 8/25/2017 | 2017 | 8 | 25 | 86 | 42 | 75 | 58.5 | 26.5 | 2892.5 |
| 8/26/2017 | 2017 | 8 | 26 | 87 | 48 | 81 | 64.5 | 32.5 | 2925 |
| 8/27/2017 | 2017 | 8 | 27 | 88 | 51 | 81 | 66 | 34 | 2959 |
| 8/28/2017 | 2017 | 8 | 28 | 89 | 52 | 81 | 66.5 | 34.5 | 2993.5 |
| 8/29/2017 | 2017 | 8 | 29 | 90 | 47 | 83 | 65 | 33 | 3026.5 |
| 8/30/2017 | 2017 | 8 | 30 | 91 | 47 | 79 | 63 | 31 | 3057.5 |
| 8/31/2017 | 2017 | 8 | 31 | 92 | 49 | 75 | 62 | 30 | 3087.5 |
| 9/1/2017 | 2017 | 9 | 1 | 93 | 47 | 79 | 63 | 31 | 3118.5 |
| 9/2/2017 | 2017 | 9 | 2 | 94 | 48 | 79 | 63.5 | 31.5 | 3150 |
| 9/3/2017 | 2017 | 9 | 3 | 95 | 46 | 81 | 63.5 | 31.5 | 3181.5 |
| 9/4/2017 | 2017 | 9 | 4 | 96 | 51 | 82 | 66.5 | 34.5 | 3216 |
| 9/5/2017 | 2017 | 9 | 5 | 97 | 54 | 78 | 66 | 34 | 3250 |
| 9/6/2017 | 2017 | 9 | 6 | 98 | 53 | 80 | 66.5 | 34.5 | 3284.5 |
| 9/7/2017 | 2017 | 9 | 7 | 99 | 54 | 75 | 64.5 | 32.5 | 3317 |
| 9/8/2017 | 2017 | 9 | 8 | 100 | 46 | 77 | 61.5 | 29.5 | 3346.5 |
| 9/9/2017 | 2017 | 9 | 9 | 101 | 50 | 74 | 62 | 30 | 3376.5 |
| 9/10/2017 | 2017 | 9 | 10 | 102 | 45 | 74 | 59.5 | 27.5 | 3404 |
| 9/11/2017 | 2017 | 9 | 11 | 103 | 46 | 77 | 61.5 | 29.5 | 3433.5 |
| 9/12/2017 | 2017 | 9 | 12 | 104 | 47 | 78 | 62.5 | 30.5 | 3464 |
| 9/13/2017 | 2017 | 9 | 13 | 105 | 49 | 76 | 62.5 | 30.5 | 3494.5 |
| 9/14/2017 | 2017 | 9 | 14 | 106 | 47 | 69 | 58 | 26 | 3520.5 |
| 9/15/2017 | 2017 | 9 | 15 | 107 | 46 | 67 | 56.5 | 24.5 | 3545 |
| 9/16/2017 | 2017 | 9 | 16 | 108 | 42 | 69 | 55.5 | 23.5 | 3568.5 |
| 9/17/2017 | 2017 | 9 | 17 | 109 | 41 | 70 | 55.5 | 23.5 | 3592 |
| 9/18/2017 | 2017 | 9 | 18 | 110 | 37 | 71 | 54 | 22 | 3614 |
| 9/19/2017 | 2017 | 9 | 19 | 111 | 48 | 70 | 59 | 27 | 3641 |
| 9/20/2017 | 2017 | 9 | 20 | 112 | 46 | 72 | 59 | 27 | 3668 |
| 9/21/2017 | 2017 | 9 | 21 | 113 | 42 | 73 | 57.5 | 25.5 | 3693.5 |
| 9/22/2017 | 2017 | 9 | 22 | 114 | 46 | 65 | 55.5 | 23.5 | 3717 |
| 9/23/2017 | 2017 | 9 | 23 | 115 | 33 | 61 | 47 | 15 | 3732 |
| 9/24/2017 | 2017 | 9 | 24 | 116 | 27 | 59 | 43 | 11 | 3743 |
| 9/25/2017 | 2017 | 9 | 25 | 117 | 26 | 63 | 44.5 | 12.5 | 3755.5 |
| 9/26/2017 | 2017 | 9 | 26 | 118 | 32 | 64 | 48 | 16 | 3771.5 |
| 9/27/2017 | 2017 | 9 | 27 | 119 | 37 | 48 | 42.5 | 10.5 | 3782 |
| 9/28/2017 | 2017 | 9 | 28 | 120 | 38 | 56 | 47 | 15 | 3797 |
| 9/29/2017 | 2017 | 9 | 29 | 121 | 45 | 59 | 52 | 20 | 3817 |
| 9/30/2017 | 2017 | 9 | 30 | 122 | 43 | 63 | 53 | 21 | 3838 |
| 10/1/2017 | 2017 | 10 | 1 | 123 | 38 | 64 | 51 | 19 | 3857 |
| 10/2/2017 | 2017 | 10 | 2 | 124 | 40 | 65 | 52.5 | 20.5 | 3877.5 |
| 10/3/2017 | 2017 | 10 | 3 | 125 | 35 | 70 | 52.5 | 20.5 | 3898 |
| 10/4/2017 | 2017 | 10 | 4 | 126 | 46 | 72 | 59 | 27 | 3925 |
| 10/5/2017 | 2017 | 10 | 5 | 127 | 46 | 69 | 57.5 | 25.5 | 3950.5 |
| 10/6/2017 | 2017 | 10 | 6 | 128 | 31 | 62 | 46.5 | 14.5 | 3965 |
| 10/7/2017 | 2017 | 10 | 7 | 129 | 27 | 68 | 47.5 | 15.5 | 3980.5 |
| 10/8/2017 | 2017 | 10 | 8 | 130 | 36 | 67 | 51.5 | 19.5 | 4000 |
| 10/9/2017 | 2017 | 10 | 9 | 131 | 24 | 47 | 35.5 | 3.5 | 4003.5 |
| 10/10/2017 | 2017 | 10 | 10 | 132 | 23 | 56 | 39.5 | 7.5 | 4011 |
| 10/11/2017 | 2017 | 10 | 11 | 133 | 31 | 66 | 48.5 | 16.5 | 4027.5 |
| 10/12/2017 | 2017 | 10 | 12 | 134 | 43 | 66 | 54.5 | 22.5 | 4050 |
| 10/13/2017 | 2017 | 10 | 13 | 135 | 36 | 66 | 51 | 19 | 4069 |
| 10/14/2017 | 2017 | 10 | 14 | 136 | 26 | 64 | 45 | 13 | 4082 |
| 10/15/2017 | 2017 | 10 | 15 | 137 | 23 | 65 | 44 | 12 | 4094 |
| 10/16/2017 | 2017 | 10 | 16 | 138 | 36 | 69 | 52.5 | 20.5 | 4114.5 |
| 10/17/2017 | 2017 | 10 | 17 | 139 | 36 | 67 | 51.5 | 19.5 | 4134 |
| 10/18/2017 | 2017 | 10 | 18 | 140 | 39 | 67 | 53 | 21 | 4155 |
| 10/19/2017 | 2017 | 10 | 19 | 141 | 40 | 64 | 52 | 20 | 4175 |
| 10/20/2017 | 2017 | 10 | 20 | 142 | 40 | 62 | 51 | 19 | 4194 |
| 10/21/2017 | 2017 | 10 | 21 | 143 | 31 | 53 | 42 | 10 | 4204 |
| 10/22/2017 | 2017 | 10 | 22 | 144 | 27 | 63 | 45 | 13 | 4217 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/23/2017 | 2017 | 10 | 23 | 145 | 36 | 65 | 50.5 | 18.5 | 4235.5 |
| 10/24/2017 | 2017 | 10 | 24 | 146 | 33 | 63 | 48 | 16 | 4251.5 |
| 10/25/2017 | 2017 | 10 | 25 | 147 | 34 | 65 | 49.5 | 17.5 | 4269 |
| 10/26/2017 | 2017 | 10 | 26 | 148 | 35 | 63 | 49 | 17 | 4286 |
| 10/27/2017 | 2017 | 10 | 27 | 149 | 31 | 56 | 43.5 | 11.5 | 4297.5 |
| 10/28/2017 | 2017 | 10 | 28 | 150 | 30 | 55 | 42.5 | 10.5 | 4308 |
| 10/29/2017 | 2017 | 10 | 29 | 151 | 29 | 61 | 45 | 13 | 4321 |
| 10/30/2017 | 2017 | 10 | 30 | 152 | 35 | 57 | 46 | 14 | 4335 |
| 10/31/2017 | 2017 | 10 | 31 | 153 | 34 | 53 | 43.5 | 11.5 | 4346.5 |
| 11/1/2017 | 2017 | 11 | 1 | 154 | 35 | 55 | 45 | 13 | 4359.5 |
| 11/2/2017 | 2017 | 11 | 2 | 155 | 36 | 55 | 45.5 | 13.5 | 4373 |
| 11/3/2017 | 2017 | 11 | 3 | 156 | 36 | 57 | 46.5 | 14.5 | 4387.5 |
| 11/4/2017 | 2017 | 11 | 4 | 157 | 43 | 58 | 50.5 | 18.5 | 4406 |
| 11/5/2017 | 2017 | 11 | 5 | 158 | 39 | 54 | 46.5 | 14.5 | 4420.5 |
| 11/6/2017 | 2017 | 11 | 6 | 159 | 36 | 53 | 44.5 | 12.5 | 4433 |
| 11/7/2017 | 2017 | 11 | 7 | 160 | 37 | 51 | 44 | 12 | 4445 |
| 11/8/2017 | 2017 | 11 | 8 | 161 | 26 | 53 | 39.5 | 7.5 | 4452.5 |
| 11/9/2017 | 2017 | 11 | 9 | 162 | 28 | 58 | 43 | 11 | 4463.5 |
| 11/10/2017 | 2017 | 11 | 10 | 163 | 33 | 60 | 46.5 | 14.5 | 4478 |
| 11/11/2017 | 2017 | 11 | 11 | 164 | 30 | 57 | 43.5 | 11.5 | 4489.5 |
| 11/12/2017 | 2017 | 11 | 12 | 165 | 29 | 62 | 45.5 | 13.5 | 4503 |
| 11/13/2017 | 2017 | 11 | 13 | 166 | 36 | 61 | 48.5 | 16.5 | 4519.5 |
| 11/14/2017 | 2017 | 11 | 14 | 167 | 29 | 61 | 45 | 13 | 4532.5 |
| 11/15/2017 | 2017 | 11 | 15 | 168 | 29 | 60 | 44.5 | 12.5 | 4545 |
| 11/16/2017 | 2017 | 11 | 16 | 169 | 33 | 59 | 46 | 14 | 4559 |
| 11/17/2017 | 2017 | 11 | 17 | 170 | 33 | 52 | 42.5 | 10.5 | 4569.5 |
| 11/18/2017 | 2017 | 11 | 18 | 171 | 15 | 47 | 31 | -1 | 4568.5 |
| 11/19/2017 | 2017 | 11 | 19 | 172 | 17 | 54 | 35.5 | 3.5 | 4572 |
| 11/20/2017 | 2017 | 11 | 20 | 173 | 24 | 53 | 38.5 | 6.5 | 4578.5 |
| 11/21/2017 | 2017 | 11 | 21 | 174 | 28 | 55 | 41.5 | 9.5 | 4588 |
| 11/22/2017 | 2017 | 11 | 22 | 175 | 28 | 60 | 44 | 12 | 4600 |
| 11/23/2017 | 2017 | 11 | 23 | 176 | 30 | 63 | 46.5 | 14.5 | 4614.5 |
| 11/24/2017 | 2017 | 11 | 24 | 177 | 35 | 63 | 49 | 17 | 4631.5 |
| 11/25/2017 | 2017 | 11 | 25 | 178 | 31 | 63 | 47 | 15 | 4646.5 |
| 11/26/2017 | 2017 | 11 | 26 | 179 | 33 | 65 | 49 | 17 | 4663.5 |
| 11/27/2017 | 2017 | 11 | 27 | 180 | 39 | 62 | 50.5 | 18.5 | 4682 |
| 11/28/2017 | 2017 | 11 | 28 | 181 | 27 | 49 | 38 | 6 | 4688 |
| 11/29/2017 | 2017 | 11 | 29 | 182 | 29 | 55 | 42 | 10 | 4698 |
| 11/30/2017 | 2017 | 11 | 30 | 183 | 36 | 50 | 43 | 11 | 4709 |
| 12/1/2017 | 2017 | 12 | 1 | 184 | 30 | 48 | 39 | 7 | 4716 |
| 12/2/2017 | 2017 | 12 | 2 | 185 | 29 | 51 | 40 | 8 | 4724 |
| 12/3/2017 | 2017 | 12 | 3 | 186 | 31 | 50 | 40.5 | 8.5 | 4732.5 |
| 12/4/2017 | 2017 | 12 | 4 | 187 | 17 | 42 | 29.5 | -2.5 | 4730 |
| 12/5/2017 | 2017 | 12 | 5 | 188 | 14 | 37 | 25.5 | -6.5 | 4723.5 |
| 12/6/2017 | 2017 | 12 | 6 | 189 | 9 | 42 | 25.5 | -6.5 | 4717 |
| 12/7/2017 | 2017 | 12 | 7 | 190 | 3 | 27 | 15 | -17 | 4700 |
| 12/8/2017 | 2017 | 12 | 8 | 191 | 18 | 42 | 30 | -2 | 4698 |
| 12/9/2017 | 2017 | 12 | 9 | 192 | 17 | 52 | 34.5 | 2.5 | 4700.5 |
| 12/10/2017 | 2017 | 12 | 10 | 193 | 19 | 53 | 36 | 4 | 4704.5 |
| 12/11/2017 | 2017 | 12 | 11 | 194 | 19 | 54 | 36.5 | 4.5 | 4709 |
| 12/12/2017 | 2017 | 12 | 12 | 195 | 23 | 55 | 39 | 7 | 4716 |
| 12/13/2017 | 2017 | 12 | 13 | 196 | 24 | 51 | 37.5 | 5.5 | 4721.5 |
| 12/14/2017 | 2017 | 12 | 14 | 197 | 17 | 37 | 27 | -5 | 4716.5 |
| 12/15/2017 | 2017 | 12 | 15 | 198 | 13 | 46 | 29.5 | -2.5 | 4714 |
| 12/16/2017 | 2017 | 12 | 16 | 199 | 23 | 46 | 34.5 | 2.5 | 4716.5 |
| 12/17/2017 | 2017 | 12 | 17 | 200 | 20 | 44 | 32 | 0 | 4716.5 |
| 12/18/2017 | 2017 | 12 | 18 | 201 | 17 | 43 | 30 | -2 | 4714.5 |
| 12/19/2017 | 2017 | 12 | 19 | 202 | 20 | 45 | 32.5 | 0.5 | 4715 |
| 12/20/2017 | 2017 | 12 | 20 | 203 | 26 | 47 | 36.5 | 4.5 | 4719.5 |
| 12/21/2017 | 2017 | 12 | 21 | 204 | 5 | 32 | 18.5 | -13.5 | 4706 |
| 12/22/2017 | 2017 | 12 | 22 | 205 | 5 | 31 | 18 | -14 | 4692 |
| 12/23/2017 | 2017 | 12 | 23 | 206 | 21 | 41 | 31 | -1 | 4691 |
| 12/24/2017 | 2017 | 12 | 24 | 207 | 27 | 47 | 37 | 5 | 4696 |
| 12/25/2017 | 2017 | 12 | 25 | 208 | 32 | 50 | 41 | 9 | 4705 |
| 12/26/2017 | 2017 | 12 | 26 | 209 | 26 | 49 | 37.5 | 5.5 | 4710.5 |
| 12/27/2017 | 2017 | 12 | 27 | 210 | 22 | 53 | 37.5 | 5.5 | 4716 |
| 12/28/2017 | 2017 | 12 | 28 | 211 | 27 | 54 | 40.5 | 8.5 | 4724.5 |
| 12/29/2017 | 2017 | 12 | 29 | 212 | 26 | 55 | 40.5 | 8.5 | 4733 |
| 12/30/2017 | 2017 | 12 | 30 | 213 | 30 | 55 | 42.5 | 10.5 | 4743.5 |
| 12/31/2017 | 2017 | 12 | 31 | 214 | 25 | 47 | 36 | 4 | 4747.5 |
| 1/1/2018 | 2018 | 1 | 1 | 215 | 25 | 49 | 37 | 5 | 4752.5 |
| 1/2/2018 | 2018 | 1 | 2 | 216 | 18 | 43 | 30.5 | -1.5 | 4751 |
| 1/3/2018 | 2018 | 1 | 3 | 217 | 20 | 50 | 35 | 3 | 4754 |
| 1/4/2018 | 2018 | 1 | 4 | 218 | 25 | 49 | 37 | 5 | 4759 |
| 1/5/2018 | 2018 | 1 | 5 | 219 | 25 | 54 | 39.5 | 7.5 | 4766.5 |
| 1/6/2018 | 2018 | 1 | 6 | 220 | 32 | 51 | 41.5 | 9.5 | 4776 |
| 1/7/2018 | 2018 | 1 | 7 | 221 | 23 | 43 | 33 | 1 | 4777 |
| 1/8/2018 | 2018 | 1 | 8 | 222 | 23 | 54 | 38.5 | 6.5 | 4783.5 |
| 1/9/2018 | 2018 | 1 | 9 | 223 | 29 | 54 | 41.5 | 9.5 | 4793 |
| 1/10/2018 | 2018 | 1 | 10 | 224 | 26 | 39 | 32.5 | 0.5 | 4793.5 |
| 1/11/2018 | 2018 | 1 | 11 | 225 | 17 | 36 | 26.5 | -5.5 | 4788 |
| 1/12/2018 | 2018 | 1 | 12 | 226 | 19 | 45 | 32 | 0 | 4788 |
| 1/13/2018 | 2018 | 1 | 13 | 227 | 15 | 49 | 32 | 0 | 4788 |
| 1/14/2018 | 2018 | 1 | 14 | 228 | 20 | 53 | 36.5 | 4.5 | 4792.5 |
| 1/15/2018 | 2018 | 1 | 15 | 229 | 23 | 50 | 36.5 | 4.5 | 4797 |
| 1/16/2018 | 2018 | 1 | 16 | 230 | 20 | 44 | 32 | 0 | 4797 |
| 1/17/2018 | 2018 | 1 | 17 | 231 | 18 | 43 | 30.5 | -1.5 | 4795.5 |
| 1/18/2018 | 2018 | 1 | 18 | 232 | 15 | 52 | 33.5 | 1.5 | 4797 |
| 1/19/2018 | 2018 | 1 | 19 | 233 | 27 | 53 | 40 | 8 | 4805 |
| 1/20/2018 | 2018 | 1 | 20 | 234 | 20 | 47 | 33.5 | 1.5 | 4806.5 |
| 1/21/2018 | 2018 | 1 | 21 | 235 | 8 | 20 | 14 | -18 | 4788.5 |
| 1/22/2018 | 2018 | 1 | 22 | 236 | 5 | 34 | 19.5 | -12.5 | 4776 |
| 1/23/2018 | 2018 | 1 | 23 | 237 | 6 | 38 | 22 | -10 | 4766 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/24/2018 | 2018 | 1 | 24 | 238 | 9 | 49 | 29 | -3 | 4763 |
| 1/25/2018 | 2018 | 1 | 25 | 239 | 20 | 47 | 33.5 | 1.5 | 4764.5 |
| 1/26/2018 | 2018 | 1 | 26 | 240 | 8 | 37 | 22.5 | -9.5 | 4755 |
| 1/27/2018 | 2018 | 1 | 27 | 241 | 6 | 46 | 26 | -6 | 4749 |
| 1/28/2018 | 2018 | 1 | 28 | 242 | 16 | 45 | 30.5 | -1.5 | 4747.5 |
| 1/29/2018 | 2018 | 1 | 29 | 243 | 18 | 55 | 36.5 | 4.5 | 4752 |
| 1/30/2018 | 2018 | 1 | 30 | 244 | 24 | 54 | 39 | 7 | 4759 |
| 1/31/2018 | 2018 | 1 | 31 | 245 | 32 | 54 | 43 | 11 | 4770 |
| 2/1/2018 | 2018 | 2 | 1 | 246 | 29 | 58 | 43.5 | 11.5 | 4781.5 |
| 2/2/2018 | 2018 | 2 | 2 | 247 | 29 | 55 | 42 | 10 | 4791.5 |
| 2/3/2018 | 2018 | 2 | 3 | 248 | 29 | 51 | 40 | 8 | 4799.5 |
| 2/4/2018 | 2018 | 2 | 4 | 249 | 27 | 55 | 41 | 9 | 4808.5 |
| 2/5/2018 | 2018 | 2 | 5 | 250 | 30 | 54 | 42 | 10 | 4818.5 |
| 2/6/2018 | 2018 | 2 | 6 | 251 | 18 | 43 | 30.5 | -1.5 | 4817 |
| 2/7/2018 | 2018 | 2 | 7 | 252 | 14 | 48 | 31 | -1 | 4816 |
| 2/8/2018 | 2018 | 2 | 8 | 253 | 23 | 54 | 38.5 | 6.5 | 4822.5 |
| 2/9/2018 | 2018 | 2 | 9 | 254 | 25 | 54 | 39.5 | 7.5 | 4830 |
| 2/10/2018 | 2018 | 2 | 10 | 255 | 22 | 50 | 36 | 4 | 4834 |
| 2/11/2018 | 2018 | 2 | 11 | 256 | 7 | 40 | 23.5 | -8.5 | 4825.5 |
| 2/12/2018 | 2018 | 2 | 12 | 257 | 28 | 44 | 36 | 4 | 4829.5 |
| 2/13/2018 | 2018 | 2 | 13 | 258 | 23 | 48 | 35.5 | 3.5 | 4833 |
| 2/14/2018 | 2018 | 2 | 14 | 259 | 28 | 45 | 36.5 | 4.5 | 4837.5 |
| 2/15/2018 | 2018 | 2 | 15 | 260 | 22 | 34 | 28 | -4 | 4833.5 |
| 2/16/2018 | 2018 | 2 | 16 | 261 | 16 | 39 | 27.5 | -4.5 | 4829 |
| 2/17/2018 | 2018 | 2 | 17 | 262 | 19 | 48 | 33.5 | 1.5 | 4830.5 |
| 2/18/2018 | 2018 | 2 | 18 | 263 | 26 | 48 | 37 | 5 | 4835.5 |
| 2/19/2018 | 2018 | 2 | 19 | 264 | 13 | 44 | 28.5 | -3.5 | 4832 |
| 2/20/2018 | 2018 | 2 | 20 | 265 | 5 | 22 | 13.5 | -18.5 | 4813.5 |
| 2/21/2018 | 2018 | 2 | 21 | 266 | 8 | 38 | 23 | -9 | 4804.5 |
| 2/22/2018 | 2018 | 2 | 22 | 267 | 13 | 29 | 21 | -11 | 4793.5 |
| 2/23/2018 | 2018 | 2 | 23 | 268 | 5 | 38 | 21.5 | -10.5 | 4783 |
| 2/24/2018 | 2018 | 2 | 24 | 269 | 11 | 28 | 19.5 | -12.5 | 4770.5 |
| 2/25/2018 | 2018 | 2 | 25 | 270 | 8 | 33 | 20.5 | -11.5 | 4759 |
| 2/26/2018 | 2018 | 2 | 26 | 271 | 11 | 48 | 29.5 | -2.5 | 4756.5 |
| 2/27/2018 | 2018 | 2 | 27 | 272 | 20 | 47 | 33.5 | 1.5 | 4758 |
| 2/28/2018 | 2018 | 2 | 28 | 273 | 19 | 34 | 26.5 | -5.5 | 4752.5 |
| 3/1/2018 | 2018 | 3 | 1 | 274 | 14 | 47 | 30.5 | -1.5 | 4751 |
| 3/2/2018 | 2018 | 3 | 2 | 275 | 22 | 53 | 37.5 | 5.5 | 4756.5 |
| 3/3/2018 | 2018 | 3 | 3 | 276 | 26 | 53 | 39.5 | 7.5 | 4764 |
| 3/4/2018 | 2018 | 3 | 4 | 277 | 19 | 47 | 33 | 1 | 4765 |
| 3/5/2018 | 2018 | 3 | 5 | 278 | 8 | 36 | 22 | -10 | 4755 |
| 3/6/2018 | 2018 | 3 | 6 | 279 | 9 | 47 | 28 | -4 | 4751 |
| 3/7/2018 | 2018 | 3 | 7 | 280 | 18 | 52 | 35 | 3 | 4754 |
| 3/8/2018 | 2018 | 3 | 8 | 281 | 27 | 54 | 40.5 | 8.5 | 4762.5 |
| 3/9/2018 | 2018 | 3 | 9 | 282 | 26 | 55 | 40.5 | 8.5 | 4771 |
| 3/10/2018 | 2018 | 3 | 10 | 283 | 30 | 51 | 40.5 | 8.5 | 4779.5 |
| 3/11/2018 | 2018 | 3 | 11 | 284 | 28 | 37 | 32.5 | 0.5 | 4780 |
| 3/12/2018 | 2018 | 3 | 12 | 285 | 28 | 45 | 36.5 | 4.5 | 4784.5 |
| 3/13/2018 | 2018 | 3 | 13 | 286 | 25 | 50 | 37.5 | 5.5 | 4790 |
| 3/14/2018 | 2018 | 3 | 14 | 287 | 29 | 58 | 43.5 | 11.5 | 4801.5 |
| 3/15/2018 | 2018 | 3 | 15 | 288 | 26 | 42 | 34 | 2 | 4803.5 |
| 3/16/2018 | 2018 | 3 | 16 | 289 | 24 | 45 | 34.5 | 2.5 | 4806 |
| 3/17/2018 | 2018 | 3 | 17 | 290 | 23 | 48 | 35.5 | 3.5 | 4809.5 |
| 3/18/2018 | 2018 | 3 | 18 | 291 | 17 | 33 | 25 | -7 | 4802.5 |
| 3/19/2018 | 2018 | 3 | 19 | 292 | 13 | 38 | 25.5 | -6.5 | 4796 |
| 3/20/2018 | 2018 | 3 | 20 | 293 | 17 | 50 | 33.5 | 1.5 | 4797.5 |
| 3/21/2018 | 2018 | 3 | 21 | 294 | 29 | 57 | 43 | 11 | 4808.5 |
| 3/22/2018 | 2018 | 3 | 22 | 295 | 31 | 62 | 46.5 | 14.5 | 4823 |
| 3/23/2018 | 2018 | 3 | 23 | 296 | 30 | 53 | 41.5 | 9.5 | 4832.5 |
| 3/24/2018 | 2018 | 3 | 24 | 297 | 28 | 57 | 42.5 | 10.5 | 4843 |
| 3/25/2018 | 2018 | 3 | 25 | 298 | 26 | 55 | 40.5 | 8.5 | 4851.5 |
| 3/26/2018 | 2018 | 3 | 26 | 299 | 26 | 49 | 37.5 | 5.5 | 4857 |
| 3/27/2018 | 2018 | 3 | 27 | 300 | 25 | 36 | 30.5 | -1.5 | 4855.5 |
| 3/28/2018 | 2018 | 3 | 28 | 301 | 19 | 46 | 32.5 | 0.5 | 4856 |
| 3/29/2018 | 2018 | 3 | 29 | 302 | 26 | 51 | 38.5 | 6.5 | 4862.5 |
| 3/30/2018 | 2018 | 3 | 30 | 303 | 25 | 58 | 41.5 | 9.5 | 4872 |
| 3/31/2018 | 2018 | 3 | 31 | 304 | 31 | 63 | 47 | 15 | 4887 |
| 4/1/2018 | 2018 | 4 | 1 | 305 | 36 | 57 | 46.5 | 14.5 | 4901.5 |
| 4/2/2018 | 2018 | 4 | 2 | 306 | 36 | 59 | 47.5 | 15.5 | 4917 |
| 4/3/2018 | 2018 | 4 | 3 | 307 | 29 | 58 | 43.5 | 11.5 | 4928.5 |
| 4/4/2018 | 2018 | 4 | 4 | 308 | 29 | 61 | 45 | 13 | 4941.5 |
| 4/5/2018 | 2018 | 4 | 5 | 309 | 29 | 59 | 44 | 12 | 4953.5 |
| 4/6/2018 | 2018 | 4 | 6 | 310 | 36 | 61 | 48.5 | 16.5 | 4970 |
| 4/7/2018 | 2018 | 4 | 7 | 311 | 42 | 67 | 54.5 | 22.5 | 4992.5 |
| 4/8/2018 | 2018 | 4 | 8 | 312 | 33 | 62 | 47.5 | 15.5 | 5008 |
| 4/9/2018 | 2018 | 4 | 9 | 313 | 27 | 57 | 42 | 10 | 5018 |
| 4/10/2018 | 2018 | 4 | 10 | 314 | 26 | 68 | 47 | 15 | 5033 |
| 4/11/2018 | 2018 | 4 | 11 | 315 | 37 | 68 | 52.5 | 20.5 | 5053.5 |
| 4/12/2018 | 2018 | 4 | 12 | 316 | 27 | 62 | 44.5 | 12.5 | 5066 |
| 4/13/2018 | 2018 | 4 | 13 | 317 | 19 | 36 | 27.5 | -4.5 | 5061.5 |
| 4/14/2018 | 2018 | 4 | 14 | 318 | 22 | 50 | 36 | 4 | 5065.5 |
| 4/15/2018 | 2018 | 4 | 15 | 319 | 26 | 63 | 44.5 | 12.5 | 5078 |
| 4/16/2018 | 2018 | 4 | 16 | 320 | 39 | 65 | 52 | 20 | 5098 |
| 4/17/2018 | 2018 | 4 | 17 | 321 | 25 | 55 | 40 | 8 | 5106 |
| 4/18/2018 | 2018 | 4 | 18 | 322 | 16 | 59 | 37.5 | 5.5 | 5111.5 |
| 4/19/2018 | 2018 | 4 | 19 | 323 | 30 | 64 | 47 | 15 | 5126.5 |
| 4/20/2018 | 2018 | 4 | 20 | 324 | 27 | 46 | 36.5 | 4.5 | 5131 |
| 4/21/2018 | 2018 | 4 | 21 | 325 | 27 | 55 | 41 | 9 | 5140 |
| 4/22/2018 | 2018 | 4 | 22 | 326 | 28 | 64 | 46 | 14 | 5154 |
| 4/23/2018 | 2018 | 4 | 23 | 327 | 33 | 69 | 51 | 19 | 5173 |
| 4/24/2018 | 2018 | 4 | 24 | 328 | 37 | 70 | 53.5 | 21.5 | 5194.5 |
| 4/25/2018 | 2018 | 4 | 25 | 329 | 33 | 69 | 51 | 19 | 5213.5 |
| 4/26/2018 | 2018 | 4 | 26 | 330 | 37 | 69 | 53 | 21 | 5234.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 4/27/2018 | 2018 | 4 | 27 | 331 | 40 | 70 | 55 | 23 | 5257.5 |
| 4/28/2018 | 2018 | 4 | 28 | 332 | 39 | 66 | 52.5 | 20.5 | 5278 |
| 4/29/2018 | 2018 | 4 | 29 | 333 | 38 | 70 | 54 | 22 | 5300 |
| 4/30/2018 | 2018 | 4 | 30 | 334 | 41 | 61 | 51 | 19 | 5319 |
| 5/1/2018 | 2018 | 5 | 1 | 335 | 36 | 60 | 48 | 16 | 5335 |
| 5/2/2018 | 2018 | 5 | 2 | 336 | 27 | 44 | 35.5 | 3.5 | 5338.5 |
| 5/3/2018 | 2018 | 5 | 3 | 337 | 27 | 50 | 38.5 | 6.5 | 5345 |
| 5/4/2018 | 2018 | 5 | 4 | 338 | 27 | 62 | 44.5 | 12.5 | 5357.5 |
| 5/5/2018 | 2018 | 5 | 5 | 339 | 34 | 71 | 52.5 | 20.5 | 5378 |
| 5/6/2018 | 2018 | 5 | 6 | 340 | 41 | 74 | 57.5 | 25.5 | 5403.5 |
| 5/7/2018 | 2018 | 5 | 7 | 341 | 42 | 74 | 58 | 26 | 5429.5 |
| 5/8/2018 | 2018 | 5 | 8 | 342 | 44 | 77 | 60.5 | 28.5 | 5458 |
| 5/9/2018 | 2018 | 5 | 9 | 343 | 42 | 81 | 61.5 | 29.5 | 5487.5 |
| 5/10/2018 | 2018 | 5 | 10 | 344 | 45 | 78 | 61.5 | 29.5 | 5517 |
| 5/11/2018 | 2018 | 5 | 11 | 345 | 51 | 74 | 62.5 | 30.5 | 5547.5 |
| 5/12/2018 | 2018 | 5 | 12 | 346 | 41 | 73 | 57 | 25 | 5572.5 |
| 5/13/2018 | 2018 | 5 | 13 | 347 | 35 | 69 | 52 | 20 | 5592.5 |
| 5/14/2018 | 2018 | 5 | 14 | 348 | 39 | 69 | 54 | 22 | 5614.5 |
| 5/15/2018 | 2018 | 5 | 15 | 349 | 36 | 70 | 53 | 21 | 5635.5 |
| 5/16/2018 | 2018 | 5 | 16 | 350 | 35 | 75 | 55 | 23 | 5658.5 |
| 5/17/2018 | 2018 | 5 | 17 | 351 | 36 | 74 | 55 | 23 | 5681.5 |
| 5/18/2018 | 2018 | 5 | 18 | 352 | 37 | 68 | 52.5 | 20.5 | 5702 |
| 5/19/2018 | 2018 | 5 | 19 | 353 | 36 | 72 | 54 | 22 | 5724 |
| 5/20/2018 | 2018 | 5 | 20 | 354 | 42 | 72 | 57 | 25 | 5749 |
| 5/21/2018 | 2018 | 5 | 21 | 355 | 39 | 71 | 55 | 23 | 5772 |
| 5/22/2018 | 2018 | 5 | 22 | 356 | 40 | 73 | 56.5 | 24.5 | 5796.5 |
| 5/23/2018 | 2018 | 5 | 23 | 357 | 35 | 74 | 54.5 | 22.5 | 5819 |
| 5/24/2018 | 2018 | 5 | 24 | 358 | 39 | 76 | 57.5 | 25.5 | 5844.5 |
| 5/25/2018 | 2018 | 5 | 25 | 359 | 46 | 78 | 62 | 30 | 5874.5 |
| 5/26/2018 | 2018 | 5 | 26 | 360 | 43 | 72 | 57.5 | 25.5 | 5900 |
| 5/27/2018 | 2018 | 5 | 27 | 361 | 33 | 74 | 53.5 | 21.5 | 5921.5 |
| 5/28/2018 | 2018 | 5 | 28 | 362 | 34 | 71 | 52.5 | 20.5 | 5942 |
| 5/29/2018 | 2018 | 5 | 29 | 363 | 38 | 74 | 56 | 24 | 5966 |
| 5/30/2018 | 2018 | 5 | 30 | 364 | 45 | 75 | 60 | 28 | 5994 |
| 5/31/2018 | 2018 | 5 | 31 | 365 | 40 | 80 | 60 | 28 | 6022 |
| 6/1/2018 | 2018 | 6 | 1 | 1 | 44 | 77 | 60.5 | 28.5 | 28.5 |
| 6/2/2018 | 2018 | 6 | 2 | 2 | 42 | 82 | 62 | 30 | 58.5 |
| 6/3/2018 | 2018 | 6 | 3 | 3 | 49 | 81 | 65 | 33 | 91.5 |
| 6/4/2018 | 2018 | 6 | 4 | 4 | 43 | 84 | 63.5 | 31.5 | 123 |
| 6/5/2018 | 2018 | 6 | 5 | 5 | 51 | 82 | 66.5 | 34.5 | 157.5 |
| 6/6/2018 | 2018 | 6 | 6 | 6 | 48 | 81 | 64.5 | 32.5 | 190 |
| 6/7/2018 | 2018 | 6 | 7 | 7 | 47 | 82 | 64.5 | 32.5 | 222.5 |
| 6/8/2018 | 2018 | 6 | 8 | 8 | 45 | 82 | 63.5 | 31.5 | 254 |
| 6/9/2018 | 2018 | 6 | 9 | 9 | 54 | 81 | 67.5 | 35.5 | 289.5 |
| 6/10/2018 | 2018 | 6 | 10 | 10 | 51 | 81 | 66 | 34 | 323.5 |
| 6/11/2018 | 2018 | 6 | 11 | 11 | 47 | 83 | 65 | 33 | 356.5 |
| 6/12/2018 | 2018 | 6 | 12 | 12 | 46 | 88 | 67 | 35 | 391.5 |
| 6/13/2018 | 2018 | 6 | 13 | 13 | 58 | 86 | 72 | 40 | 431.5 |
| 6/14/2018 | 2018 | 6 | 14 | 14 | 53 | 83 | 68 | 36 | 467.5 |
| 6/15/2018 | 2018 | 6 | 15 | 15 | 51 | 77 | 64 | 32 | 499.5 |
| 6/16/2018 | 2018 | 6 | 16 | 16 | 49 | 62 | 55.5 | 23.5 | 523 |
| 6/17/2018 | 2018 | 6 | 17 | 17 | 47 | 70 | 58.5 | 26.5 | 549.5 |
| 6/18/2018 | 2018 | 6 | 18 | 18 | 44 | 76 | 60 | 28 | 577.5 |
| 6/19/2018 | 2018 | 6 | 19 | 19 | 48 | 78 | 63 | 31 | 608.5 |
| 6/20/2018 | 2018 | 6 | 20 | 20 | 44 | 83 | 63.5 | 31.5 | 640 |
| 6/21/2018 | 2018 | 6 | 21 | 21 | 46 | 87 | 66.5 | 34.5 | 674.5 |
| 6/22/2018 | 2018 | 6 | 22 | 22 | 51 | 85 | 68 | 36 | 710.5 |
| 6/23/2018 | 2018 | 6 | 23 | 23 | 46 | 85 | 65.5 | 33.5 | 744 |
| 6/24/2018 | 2018 | 6 | 24 | 24 | 50 | 82 | 66 | 34 | 778 |
| 6/25/2018 | 2018 | 6 | 25 | 25 | 47 | 85 | 66 | 34 | 812 |
| 6/26/2018 | 2018 | 6 | 26 | 26 | 49 | 88 | 68.5 | 36.5 | 848.5 |
| 6/27/2018 | 2018 | 6 | 27 | 27 | 55 | 90 | 72.5 | 40.5 | 889 |
| 6/28/2018 | 2018 | 6 | 28 | 28 | 58 | 86 | 72 | 40 | 929 |
| 6/29/2018 | 2018 | 6 | 29 | 29 | 54 | 81 | 67.5 | 35.5 | 964.5 |
| 6/30/2018 | 2018 | 6 | 30 | 30 | 55 | 77 | 66 | 34 | 998.5 |
| 7/1/2018 | 2018 | 7 | 1 | 31 | 50 | 83 | 66.5 | 34.5 | 1033 |
| 7/2/2018 | 2018 | 7 | 2 | 32 | 48 | 83 | 65.5 | 33.5 | 1066.5 |
| 7/3/2018 | 2018 | 7 | 3 | 33 | 54 | 82 | 68 | 36 | 1102.5 |
| 7/4/2018 | 2018 | 7 | 4 | 34 | 53 | 82 | 67.5 | 35.5 | 1138 |
| 7/5/2018 | 2018 | 7 | 5 | 35 | 57 | 81 | 69 | 37 | 1175 |
| 7/6/2018 | 2018 | 7 | 6 | 36 | 54 | 75 | 64.5 | 32.5 | 1207.5 |
| 7/7/2018 | 2018 | 7 | 7 | 37 | 50 | 84 | 67 | 35 | 1242.5 |
| 7/8/2018 | 2018 | 7 | 8 | 38 | 50 | 85 | 67.5 | 35.5 | 1278 |
| 7/9/2018 | 2018 | 7 | 9 | 39 | 51 | 78 | 64.5 | 32.5 | 1310.5 |
| 7/10/2018 | 2018 | 7 | 10 | 40 | 50 | 80 | 65 | 33 | 1343.5 |
| 7/11/2018 | 2018 | 7 | 11 | 41 | 49 | 74 | 61.5 | 29.5 | 1373 |
| 7/12/2018 | 2018 | 7 | 12 | 42 | 51 | 69 | 60 | 28 | 1401 |
| 7/13/2018 | 2018 | 7 | 13 | 43 | 52 | 74 | 63 | 31 | 1432 |
| 7/14/2018 | 2018 | 7 | 14 | 44 | 50 | 74 | 62 | 30 | 1462 |
| 7/15/2018 | 2018 | 7 | 15 | 45 | 51 | 77 | 64 | 32 | 1494 |
| 7/16/2018 | 2018 | 7 | 16 | 46 | 51 | 72 | 61.5 | 29.5 | 1523.5 |
| 7/17/2018 | 2018 | 7 | 17 | 47 | 49 | 70 | 59.5 | 27.5 | 1551 |
| 7/18/2018 | 2018 | 7 | 18 | 48 | 52 | 78 | 65 | 33 | 1584 |
| 7/19/2018 | 2018 | 7 | 19 | 49 | 53 | 83 | 68 | 36 | 1620 |
| 7/20/2018 | 2018 | 7 | 20 | 50 | 52 | 84 | 68 | 36 | 1656 |
| 7/21/2018 | 2018 | 7 | 21 | 51 | 49 | 86 | 67.5 | 35.5 | 1691.5 |
| 7/22/2018 | 2018 | 7 | 22 | 52 | 53 | 87 | 70 | 38 | 1729.5 |
| 7/23/2018 | 2018 | 7 | 23 | 53 | 56 | 86 | 71 | 39 | 1768.5 |
| 7/24/2018 | 2018 | 7 | 24 | 54 | 54 | 81 | 67.5 | 35.5 | 1804 |
| 7/25/2018 | 2018 | 7 | 25 | 55 | 52 | 83 | 67.5 | 35.5 | 1839.5 |
| 7/26/2018 | 2018 | 7 | 26 | 56 | 55 | 83 | 69 | 37 | 1876.5 |
| 7/27/2018 | 2018 | 7 | 27 | 57 | 51 | 76 | 63.5 | 31.5 | 1908 |
| 7/28/2018 | 2018 | 7 | 28 | 58 | 49 | 79 | 64 | 32 | 1940 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 7/29/2018 | 2018 | 7 | 29 | 59 | 51 | 83 | 67 | 35 | 1975 |
| 7/30/2018 | 2018 | 7 | 30 | 60 | 53 | 84 | 68.5 | 36.5 | 2011.5 |
| 7/31/2018 | 2018 | 7 | 31 | 61 | 51 | 83 | 67 | 35 | 2046.5 |
| 8/1/2018 | 2018 | 8 | 1 | 62 | 60 | 83 | 71.5 | 39.5 | 2086 |
| 8/2/2018 | 2018 | 8 | 2 | 63 | 58 | 82 | 70 | 38 | 2124 |
| 8/3/2018 | 2018 | 8 | 3 | 64 | 52 | 77 | 64.5 | 32.5 | 2156.5 |
| 8/4/2018 | 2018 | 8 | 4 | 65 | 52 | 83 | 67.5 | 35.5 | 2192 |
| 8/5/2018 | 2018 | 8 | 5 | 66 | 52 | 84 | 68 | 36 | 2228 |
| 8/6/2018 | 2018 | 8 | 6 | 67 | 51 | 86 | 68.5 | 36.5 | 2264.5 |
| 8/7/2018 | 2018 | 8 | 7 | 68 | 53 | 86 | 69.5 | 37.5 | 2302 |
| 8/8/2018 | 2018 | 8 | 8 | 69 | 56 | 83 | 69.5 | 37.5 | 2339.5 |
| 8/9/2018 | 2018 | 8 | 9 | 70 | 52 | 80 | 66 | 34 | 2373.5 |
| 8/10/2018 | 2018 | 8 | 10 | 71 | 48 | 79 | 63.5 | 31.5 | 2405 |
| 8/11/2018 | 2018 | 8 | 11 | 72 | 46 | 75 | 60.5 | 28.5 | 2433.5 |
| 8/12/2018 | 2018 | 8 | 12 | 73 | 49 | 79 | 64 | 32 | 2465.5 |
| 8/13/2018 | 2018 | 8 | 13 | 74 | 51 | 84 | 67.5 | 35.5 | 2501 |
| 8/14/2018 | 2018 | 8 | 14 | 75 | 52 | 81 | 66.5 | 34.5 | 2535.5 |
| 8/15/2018 | 2018 | 8 | 15 | 76 | 52 | 77 | 64.5 | 32.5 | 2568 |
| 8/16/2018 | 2018 | 8 | 16 | 77 | 53 | 75 | 64 | 32 | 2600 |
| 8/17/2018 | 2018 | 8 | 17 | 78 | 53 | 76 | 64.5 | 32.5 | 2632.5 |
| 8/18/2018 | 2018 | 8 | 18 | 79 | 53 | 78 | 65.5 | 33.5 | 2666 |
| 8/19/2018 | 2018 | 8 | 19 | 80 | 47 | 80 | 63.5 | 31.5 | 2697.5 |
| 8/20/2018 | 2018 | 8 | 20 | 81 | 46 | 82 | 64 | 32 | 2729.5 |
| 8/21/2018 | 2018 | 8 | 21 | 82 | 52 | 76 | 64 | 32 | 2761.5 |
| 8/22/2018 | 2018 | 8 | 22 | 83 | 51 | 70 | 60.5 | 28.5 | 2790 |
| 8/23/2018 | 2018 | 8 | 23 | 84 | 49 | 70 | 59.5 | 27.5 | 2817.5 |
| 8/24/2018 | 2018 | 8 | 24 | 85 | 49 | 73 | 61 | 29 | 2846.5 |
| 8/25/2018 | 2018 | 8 | 25 | 86 | 47 | 71 | 59 | 27 | 2873.5 |
| 8/26/2018 | 2018 | 8 | 26 | 87 | 47 | 74 | 60.5 | 28.5 | 2902 |
| 8/27/2018 | 2018 | 8 | 27 | 88 | 48 | 71 | 59.5 | 27.5 | 2929.5 |
| 8/28/2018 | 2018 | 8 | 28 | 89 | 43 | 76 | 59.5 | 27.5 | 2957 |
| 8/29/2018 | 2018 | 8 | 29 | 90 | 45 | 79 | 62 | 30 | 2987 |
| 8/30/2018 | 2018 | 8 | 30 | 91 | 50 | 79 | 64.5 | 32.5 | 3019.5 |
| 8/31/2018 | 2018 | 8 | 31 | 92 | 51 | 78 | 64.5 | 32.5 | 3052 |
| 9/1/2018 | 2018 | 9 | 1 | 93 | 44 | 60 | 52 | 20 | 3072 |
| 9/2/2018 | 2018 | 9 | 2 | 94 | 42 | 69 | 55.5 | 23.5 | 3095.5 |
| 9/3/2018 | 2018 | 9 | 3 | 95 | 42 | 66 | 54 | 22 | 3117.5 |
| 9/4/2018 | 2018 | 9 | 4 | 96 | 43 | 69 | 56 | 24 | 3141.5 |
| 9/5/2018 | 2018 | 9 | 5 | 97 | 42 | 71 | 56.5 | 24.5 | 3166 |
| 9/6/2018 | 2018 | 9 | 6 | 98 | 43 | 66 | 54.5 | 22.5 | 3188.5 |
| 9/7/2018 | 2018 | 9 | 7 | 99 | 44 | 71 | 57.5 | 25.5 | 3214 |
| 9/8/2018 | 2018 | 9 | 8 | 100 | 45 | 75 | 60 | 28 | 3242 |
| 9/9/2018 | 2018 | 9 | 9 | 101 | 48 | 78 | 63 | 31 | 3273 |
| 9/10/2018 | 2018 | 9 | 10 | 102 | 47 | 75 | 61 | 29 | 3302 |
| 9/11/2018 | 2018 | 9 | 11 | 103 | 48 | 76 | 62 | 30 | 3332 |
| 9/12/2018 | 2018 | 9 | 12 | 104 | 44 | 76 | 60 | 28 | 3360 |
| 9/13/2018 | 2018 | 9 | 13 | 105 | 43 | 75 | 59 | 27 | 3387 |
| 9/14/2018 | 2018 | 9 | 14 | 106 | 45 | 76 | 60.5 | 28.5 | 3415.5 |
| 9/15/2018 | 2018 | 9 | 15 | 107 | 47 | 79 | 63 | 31 | 3446.5 |
| 9/16/2018 | 2018 | 9 | 16 | 108 | 51 | 77 | 64 | 32 | 3478.5 |
| 9/17/2018 | 2018 | 9 | 17 | 109 | 50 | 79 | 64.5 | 32.5 | 3511 |
| 9/18/2018 | 2018 | 9 | 18 | 110 | 49 | 79 | 64 | 32 | 3543 |
| 9/19/2018 | 2018 | 9 | 19 | 111 | 48 | 75 | 61.5 | 29.5 | 3572.5 |
| 9/20/2018 | 2018 | 9 | 20 | 112 | 40 | 67 | 53.5 | 21.5 | 3594 |
| 9/21/2018 | 2018 | 9 | 21 | 113 | 37 | 70 | 53.5 | 21.5 | 3615.5 |
| 9/22/2018 | 2018 | 9 | 22 | 114 | 41 | 72 | 56.5 | 24.5 | 3640 |
| 9/23/2018 | 2018 | 9 | 23 | 115 | 45 | 72 | 58.5 | 26.5 | 3666.5 |
| 9/24/2018 | 2018 | 9 | 24 | 116 | 46 | 71 | 58.5 | 26.5 | 3693 |
| 9/25/2018 | 2018 | 9 | 25 | 117 | 45 | 72 | 58.5 | 26.5 | 3719.5 |
| 9/26/2018 | 2018 | 9 | 26 | 118 | 38 | 69 | 53.5 | 21.5 | 3741 |
| 9/27/2018 | 2018 | 9 | 27 | 119 | 37 | 73 | 55 | 23 | 3764 |
| 9/28/2018 | 2018 | 9 | 28 | 120 | 42 | 76 | 59 | 27 | 3791 |
| 9/29/2018 | 2018 | 9 | 29 | 121 | 44 | 72 | 58 | 26 | 3817 |
| 9/30/2018 | 2018 | 9 | 30 | 122 | 42 | 72 | 57 | 25 | 3842 |
| 10/1/2018 | 2018 | 10 | 1 | 123 | 50 | 63 | 56.5 | 24.5 | 3866.5 |
| 10/2/2018 | 2018 | 10 | 2 | 124 | 46 | 63 | 54.5 | 22.5 | 3889 |
| 10/3/2018 | 2018 | 10 | 3 | 125 | 46 | 64 | 55 | 23 | 3912 |
| 10/4/2018 | 2018 | 10 | 4 | 126 | 36 | 63 | 49.5 | 17.5 | 3929.5 |
| 10/5/2018 | 2018 | 10 | 5 | 127 | 34 | 60 | 47 | 15 | 3944.5 |
| 10/6/2018 | 2018 | 10 | 6 | 128 | 33 | 63 | 48 | 16 | 3960.5 |
| 10/7/2018 | 2018 | 10 | 7 | 129 | 33 | 52 | 42.5 | 10.5 | 3971 |
| 10/8/2018 | 2018 | 10 | 8 | 130 | 31 | 42 | 36.5 | 4.5 | 3975.5 |
| 10/9/2018 | 2018 | 10 | 9 | 131 | 32 | 42 | 37 | 5 | 3980.5 |
| 10/10/2018 | 2018 | 10 | 10 | 132 | 31 | 48 | 39.5 | 7.5 | 3988 |
| 10/11/2018 | 2018 | 10 | 11 | 133 | 31 | 54 | 42.5 | 10.5 | 3998.5 |
| 10/12/2018 | 2018 | 10 | 12 | 134 | 33 | 55 | 44 | 12 | 4010.5 |
| 10/13/2018 | 2018 | 10 | 13 | 135 | 38 | 57 | 47.5 | 15.5 | 4026 |
| 10/14/2018 | 2018 | 10 | 14 | 136 | 27 | 50 | 38.5 | 6.5 | 4032.5 |
| 10/15/2018 | 2018 | 10 | 15 | 137 | 25 | 36 | 30.5 | -1.5 | 4031 |
| 10/16/2018 | 2018 | 10 | 16 | 138 | 27 | 36 | 31.5 | -0.5 | 4030.5 |
| 10/17/2018 | 2018 | 10 | 17 | 139 | 28 | 37 | 32.5 | 0.5 | 4031 |
| 10/18/2018 | 2018 | 10 | 18 | 140 | 32 | 52 | 42 | 10 | 4041 |
| 10/19/2018 | 2018 | 10 | 19 | 141 | 30 | 54 | 42 | 10 | 4051 |
| 10/20/2018 | 2018 | 10 | 20 | 142 | 40 | 58 | 49 | 17 | 4068 |
| 10/21/2018 | 2018 | 10 | 21 | 143 | 38 | 60 | 49 | 17 | 4085 |
| 10/22/2018 | 2018 | 10 | 22 | 144 | 38 | 59 | 48.5 | 16.5 | 4101.5 |
| 10/23/2018 | 2018 | 10 | 23 | 145 | 39 | 50 | 44.5 | 12.5 | 4114 |
| 10/24/2018 | 2018 | 10 | 24 | 146 | 36 | 53 | 44.5 | 12.5 | 4126.5 |
| 10/25/2018 | 2018 | 10 | 25 | 147 | 30 | 53 | 41.5 | 9.5 | 4136 |
| 10/26/2018 | 2018 | 10 | 26 | 148 | 30 | 56 | 43 | 11 | 4147 |
| 10/27/2018 | 2018 | 10 | 27 | 149 | 29 | 63 | 46 | 14 | 4161 |
| 10/28/2018 | 2018 | 10 | 28 | 150 | 32 | 68 | 50 | 18 | 4179 |
| 10/29/2018 | 2018 | 10 | 29 | 151 | 42 | 62 | 52 | 20 | 4199 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 10/30/2018 | 2018 | 10 | 30 | 152 | 32 | 52 | 42 | 10 | 4209 |
| 10/31/2018 | 2018 | 10 | 31 | 153 | 26 | 42 | 34 | 2 | 4211 |
| 11/1/2018 | 2018 | 11 | 1 | 154 | 28 | 45 | 36.5 | 4.5 | 4215.5 |
| 11/2/2018 | 2018 | 11 | 2 | 155 | 27 | 53 | 40 | 8 | 4223.5 |
| 11/3/2018 | 2018 | 11 | 3 | 156 | 26 | 49 | 37.5 | 5.5 | 4229 |
| 11/4/2018 | 2018 | 11 | 4 | 157 | 26 | 51 | 38.5 | 6.5 | 4235.5 |
| 11/5/2018 | 2018 | 11 | 5 | 158 | 36 | 53 | 44.5 | 12.5 | 4248 |
| 11/6/2018 | 2018 | 11 | 6 | 159 | 30 | 54 | 42 | 10 | 4258 |
| 11/7/2018 | 2018 | 11 | 7 | 160 | 28 | 53 | 40.5 | 8.5 | 4266.5 |
| 11/8/2018 | 2018 | 11 | 8 | 161 | 15 | 48 | 31.5 | -0.5 | 4266 |
| 11/9/2018 | 2018 | 11 | 9 | 162 | 10 | 45 | 27.5 | -4.5 | 4261.5 |
| 11/10/2018 | 2018 | 11 | 10 | 163 | 25 | 49 | 37 | 5 | 4266.5 |
| 11/11/2018 | 2018 | 11 | 11 | 164 | 16 | 42 | 29 | -3 | 4263.5 |
| 11/12/2018 | 2018 | 11 | 12 | 165 | 7 | 23 | 15 | -17 | 4246.5 |
| 11/13/2018 | 2018 | 11 | 13 | 166 | 6 | 39 | 22.5 | -9.5 | 4237 |
| 11/14/2018 | 2018 | 11 | 14 | 167 | 16 | 47 | 31.5 | -0.5 | 4236.5 |
| 11/15/2018 | 2018 | 11 | 15 | 168 | 20 | 53 | 36.5 | 4.5 | 4241 |
| 11/16/2018 | 2018 | 11 | 16 | 169 | 23 | 53 | 38 | 6 | 4247 |
| 11/17/2018 | 2018 | 11 | 17 | 170 | 29 | 50 | 39.5 | 7.5 | 4254.5 |
| 11/18/2018 | 2018 | 11 | 18 | 171 | 20 | 46 | 33 | 1 | 4255.5 |
| 11/19/2018 | 2018 | 11 | 19 | 172 | 16 | 49 | 32.5 | 0.5 | 4256 |
| 11/20/2018 | 2018 | 11 | 20 | 173 | 19 | 50 | 34.5 | 2.5 | 4258.5 |
| 11/21/2018 | 2018 | 11 | 21 | 174 | 22 | 53 | 37.5 | 5.5 | 4264 |
| 11/22/2018 | 2018 | 11 | 22 | 175 | 28 | 42 | 35 | 3 | 4267 |
| 11/23/2018 | 2018 | 11 | 23 | 176 | 25 | 44 | 34.5 | 2.5 | 4269.5 |
| 11/24/2018 | 2018 | 11 | 24 | 177 | 21 | 46 | 33.5 | 1.5 | 4271 |
| 11/25/2018 | 2018 | 11 | 25 | 178 | 13 | 38 | 25.5 | -6.5 | 4264.5 |
| 11/26/2018 | 2018 | 11 | 26 | 179 | 16 | 46 | 31 | -1 | 4263.5 |
| 11/27/2018 | 2018 | 11 | 27 | 180 | 20 | 52 | 36 | 4 | 4267.5 |
| 11/28/2018 | 2018 | 11 | 28 | 181 | 32 | 50 | 41 | 9 | 4276.5 |
| 11/29/2018 | 2018 | 11 | 29 | 182 | 28 | 45 | 36.5 | 4.5 | 4281 |
| 11/30/2018 | 2018 | 11 | 30 | 183 | 26 | 35 | 30.5 | -1.5 | 4279.5 |
| 12/1/2018 | 2018 | 12 | 1 | 184 | 19 | 33 | 26 | -6 | 4273.5 |
| 12/2/2018 | 2018 | 12 | 2 | 185 | 8 | 28 | 18 | -14 | 4259.5 |
| 12/3/2018 | 2018 | 12 | 3 | 186 | 1 | 30 | 15.5 | -16.5 | 4243 |
| 12/4/2018 | 2018 | 12 | 4 | 187 | 4 | 35 | 19.5 | -12.5 | 4230.5 |
| 12/5/2018 | 2018 | 12 | 5 | 188 | 17 | 47 | 32 | 0 | 4230.5 |
| 12/6/2018 | 2018 | 12 | 6 | 189 | 26 | 43 | 34.5 | 2.5 | 4233 |
| 12/7/2018 | 2018 | 12 | 7 | 190 | 29 | 39 | 34 | 2 | 4235 |
| 12/8/2018 | 2018 | 12 | 8 | 191 | 19 | 40 | 29.5 | -2.5 | 4232.5 |
| 12/9/2018 | 2018 | 12 | 9 | 192 | 13 | 39 | 26 | -6 | 4226.5 |
| 12/10/2018 | 2018 | 12 | 10 | 193 | 9 | 51 | 30 | -2 | 4224.5 |
| 12/11/2018 | 2018 | 12 | 11 | 194 | 25 | 49 | 37 | 5 | 4229.5 |
| 12/12/2018 | 2018 | 12 | 12 | 195 | 18 | 42 | 30 | -2 | 4227.5 |
| 12/13/2018 | 2018 | 12 | 13 | 196 | 14 | 36 | 25 | -7 | 4220.5 |
| 12/14/2018 | 2018 | 12 | 14 | 197 | 13 | 48 | 30.5 | -1.5 | 4219 |
| 12/15/2018 | 2018 | 12 | 15 | 198 | 24 | 50 | 37 | 5 | 4224 |
| 12/16/2018 | 2018 | 12 | 16 | 199 | 23 | 52 | 37.5 | 5.5 | 4229.5 |
| 12/17/2018 | 2018 | 12 | 17 | 200 | 30 | 40 | 35 | 3 | 4232.5 |
| 12/18/2018 | 2018 | 12 | 18 | 201 | 25 | 43 | 34 | 2 | 4234.5 |
| 12/19/2018 | 2018 | 12 | 19 | 202 | 25 | 45 | 35 | 3 | 4237.5 |
| 12/20/2018 | 2018 | 12 | 20 | 203 | 22 | 51 | 36.5 | 4.5 | 4242 |
| 12/21/2018 | 2018 | 12 | 21 | 204 | 31 | 50 | 40.5 | 8.5 | 4250.5 |
| 12/22/2018 | 2018 | 12 | 22 | 205 | 17 | 44 | 30.5 | -1.5 | 4249 |
| 12/23/2018 | 2018 | 12 | 23 | 206 | 16 | 45 | 30.5 | -1.5 | 4247.5 |
| 12/24/2018 | 2018 | 12 | 24 | 207 | 26 | 45 | 35.5 | 3.5 | 4251 |
| 12/25/2018 | 2018 | 12 | 25 | 208 | 25 | 45 | 35 | 3 | 4254 |
| 12/26/2018 | 2018 | 12 | 26 | 209 | 20 | 31 | 25.5 | -6.5 | 4247.5 |
| 12/27/2018 | 2018 | 12 | 27 | 210 | 17 | 24 | 20.5 | -11.5 | 4236 |
| 12/28/2018 | 2018 | 12 | 28 | 211 | -4 | 20 | 8 | -24 | 4212 |
| 12/29/2018 | 2018 | 12 | 29 | 212 | -5 | 22 | 8.5 | -23.5 | 4188.5 |
| 12/30/2018 | 2018 | 12 | 30 | 213 | -4 | 30 | 13 | -19 | 4169.5 |
| 12/31/2018 | 2018 | 12 | 31 | 214 | 15 | 21 | 18 | -14 | 4155.5 |
| 1/1/2019 | 2019 | 1 | 1 | 215 | 6 | 21 | 13.5 | -18.5 | 4137 |
| 1/2/2019 | 2019 | 1 | 2 | 216 | 0 | 27 | 13.5 | -18.5 | 4118.5 |
| 1/3/2019 | 2019 | 1 | 3 | 217 | 2 | 38 | 20 | -12 | 4106.5 |
| 1/4/2019 | 2019 | 1 | 4 | 218 | 15 | 52 | 33.5 | 1.5 | 4108 |
| 1/5/2019 | 2019 | 1 | 5 | 219 | 20 | 50 | 35 | 3 | 4111 |
| 1/6/2019 | 2019 | 1 | 6 | 220 | 23 | 36 | 29.5 | -2.5 | 4108.5 |
| 1/7/2019 | 2019 | 1 | 7 | 221 | 19 | 35 | 27 | -5 | 4103.5 |
| 1/8/2019 | 2019 | 1 | 8 | 222 | 17 | 49 | 33 | 1 | 4104.5 |
| 1/9/2019 | 2019 | 1 | 9 | 223 | 22 | 49 | 35.5 | 3.5 | 4108 |
| 1/10/2019 | 2019 | 1 | 10 | 224 | 27 | 46 | 36.5 | 4.5 | 4112.5 |
| 1/11/2019 | 2019 | 1 | 11 | 225 | 13 | 33 | 23 | -9 | 4103.5 |
| 1/12/2019 | 2019 | 1 | 12 | 226 | 10 | 35 | 22.5 | -9.5 | 4094 |
| 1/13/2019 | 2019 | 1 | 13 | 227 | 24 | 33 | 28.5 | -3.5 | 4090.5 |
| 1/14/2019 | 2019 | 1 | 14 | 228 | 20 | 37 | 28.5 | -3.5 | 4087 |
| 1/15/2019 | 2019 | 1 | 15 | 229 | 19 | 42 | 30.5 | -1.5 | 4085.5 |
| 1/16/2019 | 2019 | 1 | 16 | 230 | 29 | 36 | 32.5 | 0.5 | 4086 |
| 1/17/2019 | 2019 | 1 | 17 | 231 | 20 | 47 | 33.5 | 1.5 | 4087.5 |
| 1/18/2019 | 2019 | 1 | 18 | 232 | 14 | 32 | 23 | -9 | 4078.5 |
| 1/19/2019 | 2019 | 1 | 19 | 233 | 10 | 40 | 25 | -7 | 4071.5 |
| 1/20/2019 | 2019 | 1 | 20 | 234 | 18 | 49 | 33.5 | 1.5 | 4073 |
| 1/21/2019 | 2019 | 1 | 21 | 235 | 17 | 44 | 30.5 | -1.5 | 4071.5 |
| 1/22/2019 | 2019 | 1 | 22 | 236 | 4 | 26 | 15 | -17 | 4054.5 |
| 1/23/2019 | 2019 | 1 | 23 | 237 | 2 | 35 | 18.5 | -13.5 | 4041 |
| 1/24/2019 | 2019 | 1 | 24 | 238 | 13 | 35 | 24 | -8 | 4033 |
| 1/25/2019 | 2019 | 1 | 25 | 239 | 9 | 39 | 24 | -8 | 4025 |
| 1/26/2019 | 2019 | 1 | 26 | 240 | 8 | 40 | 24 | -8 | 4017 |
| 1/27/2019 | 2019 | 1 | 27 | 241 | 15 | 47 | 31 | -1 | 4016 |
| 1/28/2019 | 2019 | 1 | 28 | 242 | 15 | 45 | 30 | -2 | 4014 |
| 1/29/2019 | 2019 | 1 | 29 | 243 | 17 | 41 | 29 | -3 | 4011 |
| 1/30/2019 | 2019 | 1 | 30 | 244 | 10 | 46 | 28 | -4 | 4007 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 1/31/2019 | 2019 | 1 | 31 | 245 | 20 | 46 | 33 | 1 | 4008 |
| 2/1/2019 | 2019 | 2 | 1 | 246 | 22 | 48 | 35 | 3 | 4011 |
| 2/2/2019 | 2019 | 2 | 2 | 247 | 21 | 44 | 32.5 | 0.5 | 4011.5 |
| 2/3/2019 | 2019 | 2 | 3 | 248 | 31 | 44 | 37.5 | 5.5 | 4017 |
| 2/4/2019 | 2019 | 2 | 4 | 249 | 32 | 46 | 39 | 7 | 4024 |
| 2/5/2019 | 2019 | 2 | 5 | 250 | 27 | 41 | 34 | 2 | 4026 |
| 2/6/2019 | 2019 | 2 | 6 | 251 | 10 | 28 | 19 | -13 | 4013 |
| 2/7/2019 | 2019 | 2 | 7 | 252 | -2 | 24 | 11 | -21 | 3992 |
| 2/8/2019 | 2019 | 2 | 8 | 253 | 2 | 41 | 21.5 | -10.5 | 3981.5 |
| 2/9/2019 | 2019 | 2 | 9 | 254 | 23 | 42 | 32.5 | 0.5 | 3982 |
| 2/10/2019 | 2019 | 2 | 10 | 255 | 22 | 41 | 31.5 | -0.5 | 3981.5 |
| 2/11/2019 | 2019 | 2 | 11 | 256 | 4 | 24 | 14 | -18 | 3963.5 |
| 2/12/2019 | 2019 | 2 | 12 | 257 | 3 | 44 | 23.5 | -8.5 | 3955 |
| 2/13/2019 | 2019 | 2 | 13 | 258 | 22 | 47 | 34.5 | 2.5 | 3957.5 |
| 2/14/2019 | 2019 | 2 | 14 | 259 | 33 | 39 | 36 | 4 | 3961.5 |
| 2/15/2019 | 2019 | 2 | 15 | 260 | 31 | 44 | 37.5 | 5.5 | 3967 |
| 2/16/2019 | 2019 | 2 | 16 | 261 | 16 | 32 | 24 | -8 | 3959 |
| 2/17/2019 | 2019 | 2 | 17 | 262 | 16 | 25 | 20.5 | -11.5 | 3947.5 |
| 2/18/2019 | 2019 | 2 | 18 | 263 | 8 | 27 | 17.5 | -14.5 | 3933 |
| 2/19/2019 | 2019 | 2 | 19 | 264 | 10 | 22 | 16 | -16 | 3917 |
| 2/20/2019 | 2019 | 2 | 20 | 265 | 9 | 26 | 17.5 | -14.5 | 3902.5 |
| 2/21/2019 | 2019 | 2 | 21 | 266 | 17 | 33 | 25 | -7 | 3895.5 |
| 2/22/2019 | 2019 | 2 | 22 | 267 | 16 | 25 | 20.5 | -11.5 | 3884 |
| 2/23/2019 | 2019 | 2 | 23 | 268 | 5 | 30 | 17.5 | -14.5 | 3869.5 |
| 2/24/2019 | 2019 | 2 | 24 | 269 | 2 | 45 | 23.5 | -8.5 | 3861 |
| 2/25/2019 | 2019 | 2 | 25 | 270 | 17 | 44 | 30.5 | -1.5 | 3859.5 |
| 2/26/2019 | 2019 | 2 | 26 | 271 | 23 | 48 | 35.5 | 3.5 | 3863 |
| 2/27/2019 | 2019 | 2 | 27 | 272 | 24 | 49 | 36.5 | 4.5 | 3867.5 |
| 2/28/2019 | 2019 | 2 | 28 | 273 | 24 | 49 | 36.5 | 4.5 | 3872 |
| 3/1/2019 | 2019 | 3 | 1 | 274 | 31 | 49 | 40 | 8 | 3880 |
| 3/2/2019 | 2019 | 3 | 2 | 275 | 33 | 46 | 39.5 | 7.5 | 3887.5 |
| 3/3/2019 | 2019 | 3 | 3 | 276 | 32 | 46 | 39 | 7 | 3894.5 |
| 3/4/2019 | 2019 | 3 | 4 | 277 | 25 | 46 | 35.5 | 3.5 | 3898 |
| 3/5/2019 | 2019 | 3 | 5 | 278 | 24 | 54 | 39 | 7 | 3905 |
| 3/6/2019 | 2019 | 3 | 6 | 279 | 29 | 54 | 41.5 | 9.5 | 3914.5 |
| 3/7/2019 | 2019 | 3 | 7 | 280 | 36 | 52 | 44 | 12 | 3926.5 |
| 3/8/2019 | 2019 | 3 | 8 | 281 | 20 | 49 | 34.5 | 2.5 | 3929 |
| 3/9/2019 | 2019 | 3 | 9 | 282 | 17 | 40 | 28.5 | -3.5 | 3925.5 |
| 3/10/2019 | 2019 | 3 | 10 | 283 | 17 | 49 | 33 | 1 | 3926.5 |
| 3/11/2019 | 2019 | 3 | 11 | 284 | 33 | 44 | 38.5 | 6.5 | 3933 |
| 3/12/2019 | 2019 | 3 | 12 | 285 | 25 | 41 | 33 | 1 | 3934 |
| 3/13/2019 | 2019 | 3 | 13 | 286 | 17 | 28 | 22.5 | -9.5 | 3924.5 |
| 3/14/2019 | 2019 | 3 | 14 | 287 | 11 | 28 | 19.5 | -12.5 | 3912 |
| 3/15/2019 | 2019 | 3 | 15 | 288 | 11 | 40 | 25.5 | -6.5 | 3905.5 |
| 3/16/2019 | 2019 | 3 | 16 | 289 | 20 | 46 | 33 | 1 | 3906.5 |
| 3/17/2019 | 2019 | 3 | 17 | 290 | 22 | 50 | 36 | 4 | 3910.5 |
| 3/18/2019 | 2019 | 3 | 18 | 291 | 24 | 50 | 37 | 5 | 3915.5 |
| 3/19/2019 | 2019 | 3 | 19 | 292 | 29 | 50 | 39.5 | 7.5 | 3923 |
| 3/20/2019 | 2019 | 3 | 20 | 293 | 27 | 53 | 40 | 8 | 3931 |
| 3/21/2019 | 2019 | 3 | 21 | 294 | 27 | 49 | 38 | 6 | 3937 |
| 3/22/2019 | 2019 | 3 | 22 | 295 | 24 | 42 | 33 | 1 | 3938 |
| 3/23/2019 | 2019 | 3 | 23 | 296 | 25 | 48 | 36.5 | 4.5 | 3942.5 |
| 3/24/2019 | 2019 | 3 | 24 | 297 | 27 | 51 | 39 | 7 | 3949.5 |
| 3/25/2019 | 2019 | 3 | 25 | 298 | 24 | 58 | 41 | 9 | 3958.5 |
| 3/26/2019 | 2019 | 3 | 26 | 299 | 31 | 63 | 47 | 15 | 3973.5 |
| 3/27/2019 | 2019 | 3 | 27 | 300 | 35 | 60 | 47.5 | 15.5 | 3989 |
| 3/28/2019 | 2019 | 3 | 28 | 301 | 31 | 61 | 46 | 14 | 4003 |
| 3/29/2019 | 2019 | 3 | 29 | 302 | 26 | 51 | 38.5 | 6.5 | 4009.5 |
| 3/30/2019 | 2019 | 3 | 30 | 303 | 19 | 48 | 33.5 | 1.5 | 4011 |
| 3/31/2019 | 2019 | 3 | 31 | 304 | 18 | 39 | 28.5 | -3.5 | 4007.5 |
| 4/1/2019 | 2019 | 4 | 1 | 305 | 16 | 50 | 33 | 1 | 4008.5 |
| 4/2/2019 | 2019 | 4 | 2 | 306 | 29 | 54 | 41.5 | 9.5 | 4018 |
| 4/3/2019 | 2019 | 4 | 3 | 307 | 29 | 48 | 38.5 | 6.5 | 4024.5 |
| 4/4/2019 | 2019 | 4 | 4 | 308 | 28 | 57 | 42.5 | 10.5 | 4035 |
| 4/5/2019 | 2019 | 4 | 5 | 309 | 29 | 54 | 41.5 | 9.5 | 4044.5 |
| 4/6/2019 | 2019 | 4 | 6 | 310 | 29 | 54 | 41.5 | 9.5 | 4054 |
| 4/7/2019 | 2019 | 4 | 7 | 311 | 29 | 61 | 45 | 13 | 4067 |
| 4/8/2019 | 2019 | 4 | 8 | 312 | 33 | 65 | 49 | 17 | 4084 |
| 4/9/2019 | 2019 | 4 | 9 | 313 | 38 | 66 | 52 | 20 | 4104 |
| 4/10/2019 | 2019 | 4 | 10 | 314 | 25 | 47 | 36 | 4 | 4108 |
| 4/11/2019 | 2019 | 4 | 11 | 315 | 24 | 41 | 32.5 | 0.5 | 4108.5 |
| 4/12/2019 | 2019 | 4 | 12 | 316 | 24 | 38 | 31 | -1 | 4107.5 |
| 4/13/2019 | 2019 | 4 | 13 | 317 | 23 | 45 | 34 | 2 | 4109.5 |
| 4/14/2019 | 2019 | 4 | 14 | 318 | 26 | 58 | 42 | 10 | 4119.5 |
| 4/15/2019 | 2019 | 4 | 15 | 319 | 34 | 60 | 47 | 15 | 4134.5 |
| 4/16/2019 | 2019 | 4 | 16 | 320 | 33 | 53 | 43 | 11 | 4145.5 |
| 4/17/2019 | 2019 | 4 | 17 | 321 | 32 | 47 | 39.5 | 7.5 | 4153 |
| 4/18/2019 | 2019 | 4 | 18 | 322 | 32 | 61 | 46.5 | 14.5 | 4167.5 |
| 4/19/2019 | 2019 | 4 | 19 | 323 | 30 | 67 | 48.5 | 16.5 | 4184 |
| 4/20/2019 | 2019 | 4 | 20 | 324 | 36 | 67 | 51.5 | 19.5 | 4203.5 |
| 4/21/2019 | 2019 | 4 | 21 | 325 | 36 | 60 | 48 | 16 | 4219.5 |
| 4/22/2019 | 2019 | 4 | 22 | 326 | 29 | 54 | 41.5 | 9.5 | 4229 |
| 4/23/2019 | 2019 | 4 | 23 | 327 | 30 | 53 | 41.5 | 9.5 | 4238.5 |
| 4/24/2019 | 2019 | 4 | 24 | 328 | 30 | 61 | 45.5 | 13.5 | 4252 |
| 4/25/2019 | 2019 | 4 | 25 | 329 | 38 | 68 | 53 | 21 | 4273 |
| 4/26/2019 | 2019 | 4 | 26 | 330 | 37 | 69 | 53 | 21 | 4294 |
| 4/27/2019 | 2019 | 4 | 27 | 331 | 38 | 68 | 53 | 21 | 4315 |
| 4/28/2019 | 2019 | 4 | 28 | 332 | 36 | 66 | 51 | 19 | 4334 |
| 4/29/2019 | 2019 | 4 | 29 | 333 | 36 | 63 | 49.5 | 17.5 | 4351.5 |
| 4/30/2019 | 2019 | 4 | 30 | 334 | 33 | 51 | 42 | 10 | 4361.5 |
| 5/1/2019 | 2019 | 5 | 1 | 335 | 34 | 58 | 46 | 14 | 4375.5 |
| 5/2/2019 | 2019 | 5 | 2 | 336 | 30 | 61 | 45.5 | 13.5 | 4389 |
| 5/3/2019 | 2019 | 5 | 3 | 337 | 28 | 62 | 45 | 13 | 4402 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/4/2019 | 2019 | 5 | 4 | 338 | 31 | 66 | 48.5 | 16.5 | 4418.5 |
| 5/5/2019 | 2019 | 5 | 5 | 339 | 38 | 67 | 52.5 | 20.5 | 4439 |
| 5/6/2019 | 2019 | 5 | 6 | 340 | 37 | 62 | 49.5 | 17.5 | 4456.5 |
| 5/7/2019 | 2019 | 5 | 7 | 341 | 34 | 59 | 46.5 | 14.5 | 4471 |
| 5/8/2019 | 2019 | 5 | 8 | 342 | 32 | 50 | 41 | 9 | 4480 |
| 5/9/2019 | 2019 | 5 | 9 | 343 | 31 | 54 | 42.5 | 10.5 | 4490.5 |
| 5/10/2019 | 2019 | 5 | 10 | 344 | 34 | 42 | 38 | 6 | 4496.5 |
| 5/11/2019 | 2019 | 5 | 11 | 345 | 34 | 53 | 43.5 | 11.5 | 4508 |
| 5/12/2019 | 2019 | 5 | 12 | 346 | 31 | 58 | 44.5 | 12.5 | 4520.5 |
| 5/13/2019 | 2019 | 5 | 13 | 347 | 34 | 66 | 50 | 18 | 4538.5 |
| 5/14/2019 | 2019 | 5 | 14 | 348 | 39 | 67 | 53 | 21 | 4559.5 |
| 5/15/2019 | 2019 | 5 | 15 | 349 | 39 | 70 | 54.5 | 22.5 | 4582 |
| 5/16/2019 | 2019 | 5 | 16 | 350 | 42 | 71 | 56.5 | 24.5 | 4606.5 |
| 5/17/2019 | 2019 | 5 | 17 | 351 | 32 | 57 | 44.5 | 12.5 | 4619 |
| 5/18/2019 | 2019 | 5 | 18 | 352 | 29 | 54 | 41.5 | 9.5 | 4628.5 |
| 5/19/2019 | 2019 | 5 | 19 | 353 | 33 | 57 | 45 | 13 | 4641.5 |
| 5/20/2019 | 2019 | 5 | 20 | 354 | 27 | 44 | 35.5 | 3.5 | 4645 |
| 5/21/2019 | 2019 | 5 | 21 | 355 | 27 | 46 | 36.5 | 4.5 | 4649.5 |
| 5/22/2019 | 2019 | 5 | 22 | 356 | 31 | 58 | 44.5 | 12.5 | 4662 |
| 5/23/2019 | 2019 | 5 | 23 | 357 | 27 | 48 | 37.5 | 5.5 | 4667.5 |
| 5/24/2019 | 2019 | 5 | 24 | 358 | 26 | 63 | 44.5 | 12.5 | 4680 |
| 5/25/2019 | 2019 | 5 | 25 | 359 | 30 | 68 | 49 | 17 | 4697 |
| 5/26/2019 | 2019 | 5 | 26 | 360 | 39 | 68 | 53.5 | 21.5 | 4718.5 |
| 5/27/2019 | 2019 | 5 | 27 | 361 | 33 | 60 | 46.5 | 14.5 | 4733 |
| 5/28/2019 | 2019 | 5 | 28 | 362 | 28 | 57 | 42.5 | 10.5 | 4743.5 |
| 5/29/2019 | 2019 | 5 | 29 | 363 | 31 | 61 | 46 | 14 | 4757.5 |
| 5/30/2019 | 2019 | 5 | 30 | 364 | 32 | 62 | 47 | 15 | 4772.5 |
| 5/31/2019 | 2019 | 5 | 31 | 365 | 36 | 71 | 53.5 | 21.5 | 4794 |
| 6/1/2019 | 2019 | 6 | 1 | 1 | 39 | 75 | 57 | 25 | 25 |
| 6/2/2019 | 2019 | 6 | 2 | 2 | 42 | 74 | 58 | 26 | 51 |
| 6/3/2019 | 2019 | 6 | 3 | 3 | 38 | 74 | 56 | 24 | 75 |
| 6/4/2019 | 2019 | 6 | 4 | 4 | 41 | 74 | 57.5 | 25.5 | 100.5 |
| 6/5/2019 | 2019 | 6 | 5 | 5 | 41 | 66 | 53.5 | 21.5 | 122 |
| 6/6/2019 | 2019 | 6 | 6 | 6 | 40 | 74 | 57 | 25 | 147 |
| 6/7/2019 | 2019 | 6 | 7 | 7 | 47 | 75 | 61 | 29 | 176 |
| 6/8/2019 | 2019 | 6 | 8 | 8 | 42 | 73 | 57.5 | 25.5 | 201.5 |
| 6/9/2019 | 2019 | 6 | 9 | 9 | 42 | 76 | 59 | 27 | 228.5 |
| 6/10/2019 | 2019 | 6 | 10 | 10 | 46 | 71 | 58.5 | 26.5 | 255 |
| 6/11/2019 | 2019 | 6 | 11 | 11 | 46 | 78 | 62 | 30 | 285 |
| 6/12/2019 | 2019 | 6 | 12 | 12 | 43 | 80 | 61.5 | 29.5 | 314.5 |
| 6/13/2019 | 2019 | 6 | 13 | 13 | 49 | 81 | 65 | 33 | 347.5 |
| 6/14/2019 | 2019 | 6 | 14 | 14 | 50 | 76 | 63 | 31 | 378.5 |
| 6/15/2019 | 2019 | 6 | 15 | 15 | 47 | 75 | 61 | 29 | 407.5 |
| 6/16/2019 | 2019 | 6 | 16 | 16 | 46 | 75 | 60.5 | 28.5 | 436 |
| 6/17/2019 | 2019 | 6 | 17 | 17 | 40 | 72 | 56 | 24 | 460 |
| 6/18/2019 | 2019 | 6 | 18 | 18 | 38 | 74 | 56 | 24 | 484 |
| 6/19/2019 | 2019 | 6 | 19 | 19 | 44 | 77 | 60.5 | 28.5 | 512.5 |
| 6/20/2019 | 2019 | 6 | 20 | 20 | 52 | 77 | 64.5 | 32.5 | 545 |
| 6/21/2019 | 2019 | 6 | 21 | 21 | 46 | 74 | 60 | 28 | 573 |
| 6/22/2019 | 2019 | 6 | 22 | 22 | 40 | 71 | 55.5 | 23.5 | 596.5 |
| 6/23/2019 | 2019 | 6 | 23 | 23 | 33 | 68 | 50.5 | 18.5 | 615 |
| 6/24/2019 | 2019 | 6 | 24 | 24 | 34 | 74 | 54 | 22 | 637 |
| 6/25/2019 | 2019 | 6 | 25 | 25 | 44 | 78 | 61 | 29 | 666 |
| 6/26/2019 | 2019 | 6 | 26 | 26 | 43 | 80 | 61.5 | 29.5 | 695.5 |
| 6/27/2019 | 2019 | 6 | 27 | 27 | 47 | 82 | 64.5 | 32.5 | 728 |
| 6/28/2019 | 2019 | 6 | 28 | 28 | 47 | 82 | 64.5 | 32.5 | 760.5 |
| 6/29/2019 | 2019 | 6 | 29 | 29 | 47 | 83 | 65 | 33 | 793.5 |
| 6/30/2019 | 2019 | 6 | 30 | 30 | 49 | 82 | 65.5 | 33.5 | 827 |
| 7/1/2019 | 2019 | 7 | 1 | 31 | 47 | 80 | 63.5 | 31.5 | 858.5 |
| 7/2/2019 | 2019 | 7 | 2 | 32 | 52 | 80 | 66 | 34 | 892.5 |
| 7/3/2019 | 2019 | 7 | 3 | 33 | 54 | 79 | 66.5 | 34.5 | 927 |
| 7/4/2019 | 2019 | 7 | 4 | 34 | 51 | 79 | 65 | 33 | 960 |
| 7/5/2019 | 2019 | 7 | 5 | 35 | 52 | 79 | 65.5 | 33.5 | 993.5 |
| 7/6/2019 | 2019 | 7 | 6 | 36 | 55 | 67 | 61 | 29 | 1022.5 |
| 7/7/2019 | 2019 | 7 | 7 | 37 | 51 | 68 | 59.5 | 27.5 | 1050 |
| 7/8/2019 | 2019 | 7 | 8 | 38 | 48 | 75 | 61.5 | 29.5 | 1079.5 |
| 7/9/2019 | 2019 | 7 | 9 | 39 | 45 | 79 | 62 | 30 | 1109.5 |
| 7/10/2019 | 2019 | 7 | 10 | 40 | 46 | 84 | 65 | 33 | 1142.5 |
| 7/11/2019 | 2019 | 7 | 11 | 41 | 57 | 84 | 70.5 | 38.5 | 1181 |
| 7/12/2019 | 2019 | 7 | 12 | 42 | 54 | 83 | 68.5 | 36.5 | 1217.5 |
| 7/13/2019 | 2019 | 7 | 13 | 43 | 53 | 80 | 66.5 | 34.5 | 1252 |
| 7/14/2019 | 2019 | 7 | 14 | 44 | 51 | 80 | 65.5 | 33.5 | 1285.5 |
| 7/15/2019 | 2019 | 7 | 15 | 45 | 52 | 82 | 67 | 35 | 1320.5 |
| 7/16/2019 | 2019 | 7 | 16 | 46 | 55 | 83 | 69 | 37 | 1357.5 |
| 7/17/2019 | 2019 | 7 | 17 | 47 | 52 | 83 | 67.5 | 35.5 | 1393 |
| 7/18/2019 | 2019 | 7 | 18 | 48 | 55 | 84 | 69.5 | 37.5 | 1430.5 |
| 7/19/2019 | 2019 | 7 | 19 | 49 | 53 | 83 | 68 | 36 | 1466.5 |
| 7/20/2019 | 2019 | 7 | 20 | 50 | 58 | 85 | 71.5 | 39.5 | 1506 |
| 7/21/2019 | 2019 | 7 | 21 | 51 | 58 | 85 | 71.5 | 39.5 | 1545.5 |
| 7/22/2019 | 2019 | 7 | 22 | 52 | 54 | 82 | 68 | 36 | 1581.5 |
| 7/23/2019 | 2019 | 7 | 23 | 53 | 55 | 77 | 66 | 34 | 1615.5 |
| 7/24/2019 | 2019 | 7 | 24 | 54 | 53 | 75 | 64 | 32 | 1647.5 |
| 7/25/2019 | 2019 | 7 | 25 | 55 | 52 | 81 | 66.5 | 34.5 | 1682 |
| 7/26/2019 | 2019 | 7 | 26 | 56 | 50 | 82 | 66 | 34 | 1716 |
| 7/27/2019 | 2019 | 7 | 27 | 57 | 52 | 83 | 67.5 | 35.5 | 1751.5 |
| 7/28/2019 | 2019 | 7 | 28 | 58 | 53 | 82 | 67.5 | 35.5 | 1787 |
| 7/29/2019 | 2019 | 7 | 29 | 59 | 53 | 81 | 67 | 35 | 1822 |
| 7/30/2019 | 2019 | 7 | 30 | 60 | 54 | 82 | 68 | 36 | 1858 |
| 7/31/2019 | 2019 | 7 | 31 | 61 | 53 | 80 | 66.5 | 34.5 | 1892.5 |
| 8/1/2019 | 2019 | 8 | 1 | 62 | 52 | 79 | 65.5 | 33.5 | 1926 |
| 8/2/2019 | 2019 | 8 | 2 | 63 | 50 | 74 | 62 | 30 | 1956 |
| 8/3/2019 | 2019 | 8 | 3 | 64 | 52 | 77 | 64.5 | 32.5 | 1988.5 |
| 8/4/2019 | 2019 | 8 | 4 | 65 | 52 | 76 | 64 | 32 | 2020.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/5/2019 | 2019 | 8 | 5 | 66 | 50 | 81 | 65.5 | 33.5 | 2054 |
| 8/6/2019 | 2019 | 8 | 6 | 67 | 53 | 81 | 67 | 35 | 2089 |
| 8/7/2019 | 2019 | 8 | 7 | 68 | 52 | 74 | 63 | 31 | 2120 |
| 8/8/2019 | 2019 | 8 | 8 | 69 | 50 | 79 | 64.5 | 32.5 | 2152.5 |
| 8/9/2019 | 2019 | 8 | 9 | 70 | 48 | 69 | 58.5 | 26.5 | 2179 |
| 8/10/2019 | 2019 | 8 | 10 | 71 | 46 | 69 | 57.5 | 25.5 | 2204.5 |
| 8/11/2019 | 2019 | 8 | 11 | 72 | 50 | 65 | 57.5 | 25.5 | 2230 |
| 8/12/2019 | 2019 | 8 | 12 | 73 | 50 | 76 | 63 | 31 | 2261 |
| 8/13/2019 | 2019 | 8 | 13 | 74 | 49 | 80 | 64.5 | 32.5 | 2293.5 |
| 8/14/2019 | 2019 | 8 | 14 | 75 | 49 | 80 | 64.5 | 32.5 | 2326 |
| 8/15/2019 | 2019 | 8 | 15 | 76 | 52 | 82 | 67 | 35 | 2361 |
| 8/16/2019 | 2019 | 8 | 16 | 77 | 54 | 81 | 67.5 | 35.5 | 2396.5 |
| 8/17/2019 | 2019 | 8 | 17 | 78 | 51 | 78 | 64.5 | 32.5 | 2429 |
| 8/18/2019 | 2019 | 8 | 18 | 79 | 53 | 81 | 67 | 35 | 2464 |
| 8/19/2019 | 2019 | 8 | 19 | 80 | 50 | 83 | 66.5 | 34.5 | 2498.5 |
| 8/20/2019 | 2019 | 8 | 20 | 81 | 53 | 84 | 68.5 | 36.5 | 2535 |
| 8/21/2019 | 2019 | 8 | 21 | 82 | 54 | 78 | 66 | 34 | 2569 |
| 8/22/2019 | 2019 | 8 | 22 | 83 | 52 | 81 | 66.5 | 34.5 | 2603.5 |
| 8/23/2019 | 2019 | 8 | 23 | 84 | 51 | 77 | 64 | 32 | 2635.5 |
| 8/24/2019 | 2019 | 8 | 24 | 85 | 51 | 80 | 65.5 | 33.5 | 2669 |
| 8/25/2019 | 2019 | 8 | 25 | 86 | 51 | 83 | 67 | 35 | 2704 |
| 8/26/2019 | 2019 | 8 | 26 | 87 | 53 | 85 | 69 | 37 | 2741 |
| 8/27/2019 | 2019 | 8 | 27 | 88 | 50 | 86 | 68 | 36 | 2777 |
| 8/28/2019 | 2019 | 8 | 28 | 89 | 50 | 84 | 67 | 35 | 2812 |
| 8/29/2019 | 2019 | 8 | 29 | 90 | 53 | 80 | 66.5 | 34.5 | 2846.5 |
| 8/30/2019 | 2019 | 8 | 30 | 91 | 51 | 84 | 67.5 | 35.5 | 2882 |
| 8/31/2019 | 2019 | 8 | 31 | 92 | 53 | 86 | 69.5 | 37.5 | 2919.5 |
| 9/1/2019 | 2019 | 9 | 1 | 93 | 52 | 80 | 66 | 34 | 2953.5 |
| 9/2/2019 | 2019 | 9 | 2 | 94 | 50 | 82 | 66 | 34 | 2987.5 |
| 9/3/2019 | 2019 | 9 | 3 | 95 | 49 | 84 | 66.5 | 34.5 | 3022 |
| 9/4/2019 | 2019 | 9 | 4 | 96 | 54 | 81 | 67.5 | 35.5 | 3057.5 |
| 9/5/2019 | 2019 | 9 | 5 | 97 | 50 | 81 | 65.5 | 33.5 | 3091 |
| 9/6/2019 | 2019 | 9 | 6 | 98 | 56 | 84 | 70 | 38 | 3129 |
| 9/7/2019 | 2019 | 9 | 7 | 99 | 50 | 80 | 65 | 33 | 3162 |
| 9/8/2019 | 2019 | 9 | 8 | 100 | 47 | 71 | 59 | 27 | 3189 |
| 9/9/2019 | 2019 | 9 | 9 | 101 | 48 | 72 | 60 | 28 | 3217 |
| 9/10/2019 | 2019 | 9 | 10 | 102 | 45 | 71 | 58 | 26 | 3243 |
| 9/11/2019 | 2019 | 9 | 11 | 103 | 45 | 70 | 57.5 | 25.5 | 3268.5 |
| 9/12/2019 | 2019 | 9 | 12 | 104 | 36 | 72 | 54 | 22 | 3290.5 |
| 9/13/2019 | 2019 | 9 | 13 | 105 | 40 | 77 | 58.5 | 26.5 | 3317 |
| 9/14/2019 | 2019 | 9 | 14 | 106 | 48 | 76 | 62 | 30 | 3347 |
| 9/15/2019 | 2019 | 9 | 15 | 107 | 47 | 57 | 52 | 20 | 3367 |
| 9/16/2019 | 2019 | 9 | 16 | 108 | 46 | 67 | 56.5 | 24.5 | 3391.5 |
| 9/17/2019 | 2019 | 9 | 17 | 109 | 46 | 68 | 57 | 25 | 3416.5 |
| 9/18/2019 | 2019 | 9 | 18 | 110 | 43 | 68 | 55.5 | 23.5 | 3440 |
| 9/19/2019 | 2019 | 9 | 19 | 111 | 42 | 71 | 56.5 | 24.5 | 3464.5 |
| 9/20/2019 | 2019 | 9 | 20 | 112 | 43 | 68 | 55.5 | 23.5 | 3488 |
| 9/21/2019 | 2019 | 9 | 21 | 113 | 38 | 67 | 52.5 | 20.5 | 3508.5 |
| 9/22/2019 | 2019 | 9 | 22 | 114 | 32 | 68 | 50 | 18 | 3526.5 |
| 9/23/2019 | 2019 | 9 | 23 | 115 | 39 | 53 | 46 | 14 | 3540.5 |
| 9/24/2019 | 2019 | 9 | 24 | 116 | 36 | 66 | 51 | 19 | 3559.5 |
| 9/25/2019 | 2019 | 9 | 25 | 117 | 38 | 69 | 53.5 | 21.5 | 3581 |
| 9/26/2019 | 2019 | 9 | 26 | 118 | 45 | 67 | 56 | 24 | 3605 |
| 9/27/2019 | 2019 | 9 | 27 | 119 | 43 | 61 | 52 | 20 | 3625 |
| 9/28/2019 | 2019 | 9 | 28 | 120 | 42 | 69 | 55.5 | 23.5 | 3648.5 |
| 9/29/2019 | 2019 | 9 | 29 | 121 | 48 | 69 | 58.5 | 26.5 | 3675 |
| 9/30/2019 | 2019 | 9 | 30 | 122 | 44 | 73 | 58.5 | 26.5 | 3701.5 |
| 10/1/2019 | 2019 | 10 | 1 | 123 | 40 | 69 | 54.5 | 22.5 | 3724 |
| 10/2/2019 | 2019 | 10 | 2 | 124 | 36 | 64 | 50 | 18 | 3742 |
| 10/3/2019 | 2019 | 10 | 3 | 125 | 36 | 70 | 53 | 21 | 3763 |
| 10/4/2019 | 2019 | 10 | 4 | 126 | 47 | 64 | 55.5 | 23.5 | 3786.5 |
| 10/5/2019 | 2019 | 10 | 5 | 127 | 39 | 66 | 52.5 | 20.5 | 3807 |
| 10/6/2019 | 2019 | 10 | 6 | 128 | 35 | 66 | 50.5 | 18.5 | 3825.5 |
| 10/7/2019 | 2019 | 10 | 7 | 129 | 36 | 68 | 52 | 20 | 3845.5 |
| 10/8/2019 | 2019 | 10 | 8 | 130 | 38 | 67 | 52.5 | 20.5 | 3866 |
| 10/9/2019 | 2019 | 10 | 9 | 131 | 38 | 63 | 50.5 | 18.5 | 3884.5 |
| 10/10/2019 | 2019 | 10 | 10 | 132 | 19 | 55 | 37 | 5 | 3889.5 |
| 10/11/2019 | 2019 | 10 | 11 | 133 | 14 | 54 | 34 | 2 | 3891.5 |
| 10/12/2019 | 2019 | 10 | 12 | 134 | 31 | 62 | 46.5 | 14.5 | 3906 |
| 10/13/2019 | 2019 | 10 | 13 | 135 | 31 | 63 | 47 | 15 | 3921 |
| 10/14/2019 | 2019 | 10 | 14 | 136 | 31 | 62 | 46.5 | 14.5 | 3935.5 |
| 10/15/2019 | 2019 | 10 | 15 | 137 | 30 | 71 | 50.5 | 18.5 | 3954 |
| 10/16/2019 | 2019 | 10 | 16 | 138 | 29 | 69 | 49 | 17 | 3971 |
| 10/17/2019 | 2019 | 10 | 17 | 139 | 35 | 63 | 49 | 17 | 3988 |
| 10/18/2019 | 2019 | 10 | 18 | 140 | 29 | 55 | 42 | 10 | 3998 |
| 10/19/2019 | 2019 | 10 | 19 | 141 | 26 | 57 | 41.5 | 9.5 | 4007.5 |
| 10/20/2019 | 2019 | 10 | 20 | 142 | 25 | 50 | 37.5 | 5.5 | 4013 |
| 10/21/2019 | 2019 | 10 | 21 | 143 | 27 | 52 | 39.5 | 7.5 | 4020.5 |
| 10/22/2019 | 2019 | 10 | 22 | 144 | 25 | 60 | 42.5 | 10.5 | 4031 |
| 10/23/2019 | 2019 | 10 | 23 | 145 | 31 | 59 | 45 | 13 | 4044 |
| 10/24/2019 | 2019 | 10 | 24 | 146 | 19 | 41 | 30 | -2 | 4042 |
| 10/25/2019 | 2019 | 10 | 25 | 147 | 18 | 56 | 37 | 5 | 4047 |
| 10/26/2019 | 2019 | 10 | 26 | 148 | 28 | 62 | 45 | 13 | 4060 |
| 10/27/2019 | 2019 | 10 | 27 | 149 | 41 | 60 | 50.5 | 18.5 | 4078.5 |
| 10/28/2019 | 2019 | 10 | 28 | 150 | 23 | 42 | 32.5 | 0.5 | 4079 |
| 10/29/2019 | 2019 | 10 | 29 | 151 | 25 | 48 | 36.5 | 4.5 | 4083.5 |
| 10/30/2019 | 2019 | 10 | 30 | 152 | 7 | 28 | 17.5 | -14.5 | 4069 |
| 10/31/2019 | 2019 | 10 | 31 | 153 | 7 | 50 | 28.5 | -3.5 | 4065.5 |
| 11/1/2019 | 2019 | 11 | 1 | 154 | 24 | 58 | 41 | 9 | 4074.5 |
| 11/2/2019 | 2019 | 11 | 2 | 155 | 24 | 59 | 41.5 | 9.5 | 4084 |
| 11/3/2019 | 2019 | 11 | 3 | 156 | 30 | 61 | 45.5 | 13.5 | 4097.5 |
| 11/4/2019 | 2019 | 11 | 4 | 157 | 32 | 58 | 45 | 13 | 4110.5 |
| 11/5/2019 | 2019 | 11 | 5 | 158 | 29 | 58 | 43.5 | 11.5 | 4122 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/6/2019 | 2019 | 11 | 6 | 159 | 33 | 46 | 39.5 | 7.5 | 4129.5 |
| 11/7/2019 | 2019 | 11 | 7 | 160 | 29 | 50 | 39.5 | 7.5 | 4137 |
| 11/8/2019 | 2019 | 11 | 8 | 161 | 25 | 53 | 39 | 7 | 4144 |
| 11/9/2019 | 2019 | 11 | 9 | 162 | 23 | 62 | 42.5 | 10.5 | 4154.5 |
| 11/10/2019 | 2019 | 11 | 10 | 163 | 33 | 57 | 45 | 13 | 4167.5 |
| 11/11/2019 | 2019 | 11 | 11 | 164 | 23 | 57 | 40 | 8 | 4175.5 |
| 11/12/2019 | 2019 | 11 | 12 | 165 | 20 | 52 | 36 | 4 | 4179.5 |
| 11/13/2019 | 2019 | 11 | 13 | 166 | 29 | 58 | 43.5 | 11.5 | 4191 |
| 11/14/2019 | 2019 | 11 | 14 | 167 | 26 | 58 | 42 | 10 | 4201 |
| 11/15/2019 | 2019 | 11 | 15 | 168 | 32 | 58 | 45 | 13 | 4214 |
| 11/16/2019 | 2019 | 11 | 16 | 169 | 28 | 58 | 43 | 11 | 4225 |
| 11/17/2019 | 2019 | 11 | 17 | 170 | 25 | 56 | 40.5 | 8.5 | 4233.5 |
| 11/18/2019 | 2019 | 11 | 18 | 171 | 33 | 60 | 46.5 | 14.5 | 4248 |
| 11/19/2019 | 2019 | 11 | 19 | 172 | 33 | 57 | 45 | 13 | 4261 |
| 11/20/2019 | 2019 | 11 | 20 | 173 | 34 | 42 | 38 | 6 | 4267 |
| 11/21/2019 | 2019 | 11 | 21 | 174 | 25 | 37 | 31 | -1 | 4266 |
| 11/22/2019 | 2019 | 11 | 22 | 175 | 21 | 34 | 27.5 | -4.5 | 4261.5 |
| 11/23/2019 | 2019 | 11 | 23 | 176 | 18 | 41 | 29.5 | -2.5 | 4259 |
| 11/24/2019 | 2019 | 11 | 24 | 177 | 17 | 44 | 30.5 | -1.5 | 4257.5 |
| 11/25/2019 | 2019 | 11 | 25 | 178 | 20 | 45 | 32.5 | 0.5 | 4258 |
| 11/26/2019 | 2019 | 11 | 26 | 179 | 6 | 20 | 13 | -19 | 4239 |
| 11/27/2019 | 2019 | 11 | 27 | 180 | 14 | 37 | 25.5 | -6.5 | 4232.5 |
| 11/28/2019 | 2019 | 11 | 28 | 181 | 25 | 38 | 31.5 | -0.5 | 4232 |
| 11/29/2019 | 2019 | 11 | 29 | 182 | 17 | 35 | 26 | -6 | 4226 |
| 11/30/2019 | 2019 | 11 | 30 | 183 | 6 | 23 | 14.5 | -17.5 | 4208.5 |
| 12/1/2019 | 2019 | 12 | 1 | 184 | 6 | 42 | 24 | -8 | 4200.5 |
| 12/2/2019 | 2019 | 12 | 2 | 185 | 21 | 50 | 35.5 | 3.5 | 4204 |
| 12/3/2019 | 2019 | 12 | 3 | 186 | 24 | 48 | 36 | 4 | 4208 |
| 12/4/2019 | 2019 | 12 | 4 | 187 | 33 | 43 | 38 | 6 | 4214 |
| 12/5/2019 | 2019 | 12 | 5 | 188 | 22 | 41 | 31.5 | -0.5 | 4213.5 |
| 12/6/2019 | 2019 | 12 | 6 | 189 | 22 | 45 | 33.5 | 1.5 | 4215 |
| 12/7/2019 | 2019 | 12 | 7 | 190 | 28 | 49 | 38.5 | 6.5 | 4221.5 |
| 12/8/2019 | 2019 | 12 | 8 | 191 | 31 | 34 | 32.5 | 0.5 | 4222 |
| 12/9/2019 | 2019 | 12 | 9 | 192 | 16 | 35 | 25.5 | -6.5 | 4215.5 |
| 12/10/2019 | 2019 | 12 | 10 | 193 | 13 | 41 | 27 | -5 | 4210.5 |
| 12/11/2019 | 2019 | 12 | 11 | 194 | 15 | 47 | 31 | -1 | 4209.5 |
| 12/12/2019 | 2019 | 12 | 12 | 195 | 24 | 44 | 34 | 2 | 4211.5 |
| 12/13/2019 | 2019 | 12 | 13 | 196 | 31 | 47 | 39 | 7 | 4218.5 |
| 12/14/2019 | 2019 | 12 | 14 | 197 | 32 | 44 | 38 | 6 | 4224.5 |
| 12/15/2019 | 2019 | 12 | 15 | 198 | 18 | 37 | 27.5 | -4.5 | 4220 |
| 12/16/2019 | 2019 | 12 | 16 | 199 | 6 | 24 | 15 | -17 | 4203 |
| 12/17/2019 | 2019 | 12 | 17 | 200 | 3 | 29 | 16 | -16 | 4187 |
| 12/18/2019 | 2019 | 12 | 18 | 201 | 9 | 42 | 25.5 | -6.5 | 4180.5 |
| 12/19/2019 | 2019 | 12 | 19 | 202 | 16 | 36 | 26 | -6 | 4174.5 |
| 12/20/2019 | 2019 | 12 | 20 | 203 | 14 | 40 | 27 | -5 | 4169.5 |
| 12/21/2019 | 2019 | 12 | 21 | 204 | 18 | 51 | 34.5 | 2.5 | 4172 |
| 12/22/2019 | 2019 | 12 | 22 | 205 | 25 | 53 | 39 | 7 | 4179 |
| 12/23/2019 | 2019 | 12 | 23 | 206 | 28 | 47 | 37.5 | 5.5 | 4184.5 |
| 12/24/2019 | 2019 | 12 | 24 | 207 | 27 | 40 | 33.5 | 1.5 | 4186 |
| 12/25/2019 | 2019 | 12 | 25 | 208 | 22 | 31 | 26.5 | -5.5 | 4180.5 |
| 12/26/2019 | 2019 | 12 | 26 | 209 | 13 | 36 | 24.5 | -7.5 | 4173 |
| 12/27/2019 | 2019 | 12 | 27 | 210 | 21 | 30 | 25.5 | -6.5 | 4166.5 |
| 12/28/2019 | 2019 | 12 | 28 | 211 | 9 | 25 | 17 | -15 | 4151.5 |
| 12/29/2019 | 2019 | 12 | 29 | 212 | 3 | 21 | 12 | -20 | 4131.5 |
| 12/30/2019 | 2019 | 12 | 30 | 213 | 3 | 33 | 18 | -14 | 4117.5 |
| 12/31/2019 | 2019 | 12 | 31 | 214 | 9 | 39 | 24 | -8 | 4109.5 |
| 1/1/2020 | 2020 | 1 | 1 | 215 | 16 | 35 | 25.5 | -6.5 | 4103 |
| 1/2/2020 | 2020 | 1 | 2 | 216 | 10 | 28 | 19 | -13 | 4090 |
| 1/3/2020 | 2020 | 1 | 3 | 217 | 9 | 40 | 24.5 | -7.5 | 4082.5 |
| 1/4/2020 | 2020 | 1 | 4 | 218 | 17 | 49 | 33 | 1 | 4083.5 |
| 1/5/2020 | 2020 | 1 | 5 | 219 | 22 | 50 | 36 | 4 | 4087.5 |
| 1/6/2020 | 2020 | 1 | 6 | 220 | 14 | 36 | 25 | -7 | 4080.5 |
| 1/7/2020 | 2020 | 1 | 7 | 221 | 13 | 46 | 29.5 | -2.5 | 4078 |
| 1/8/2020 | 2020 | 1 | 8 | 222 | 22 | 43 | 32.5 | 0.5 | 4078.5 |
| 1/9/2020 | 2020 | 1 | 9 | 223 | 20 | 31 | 25.5 | -6.5 | 4072 |
| 1/10/2020 | 2020 | 1 | 10 | 224 | 2 | 26 | 14 | -18 | 4054 |
| 1/11/2020 | 2020 | 1 | 11 | 225 | 3 | 38 | 20.5 | -11.5 | 4042.5 |
| 1/12/2020 | 2020 | 1 | 12 | 226 | 11 | 36 | 23.5 | -8.5 | 4034 |
| 1/13/2020 | 2020 | 1 | 13 | 227 | 25 | 39 | 32 | 0 | 4034 |
| 1/14/2020 | 2020 | 1 | 14 | 228 | 26 | 45 | 35.5 | 3.5 | 4037.5 |
| 1/15/2020 | 2020 | 1 | 15 | 229 | 24 | 48 | 36 | 4 | 4041.5 |
| 1/16/2020 | 2020 | 1 | 16 | 230 | 30 | 37 | 33.5 | 1.5 | 4043 |
| 1/17/2020 | 2020 | 1 | 17 | 231 | 10 | 38 | 24 | -8 | 4035 |
| 1/18/2020 | 2020 | 1 | 18 | 232 | 8 | 48 | 28 | -4 | 4031 |
| 1/19/2020 | 2020 | 1 | 19 | 233 | 15 | 44 | 29.5 | -2.5 | 4028.5 |
| 1/20/2020 | 2020 | 1 | 20 | 234 | 24 | 47 | 35.5 | 3.5 | 4032 |
| 1/21/2020 | 2020 | 1 | 21 | 235 | 30 | 37 | 33.5 | 1.5 | 4033.5 |
| 1/22/2020 | 2020 | 1 | 22 | 236 | 24 | 36 | 30 | -2 | 4031.5 |
| 1/23/2020 | 2020 | 1 | 23 | 237 | 17 | 40 | 28.5 | -3.5 | 4028 |
| 1/24/2020 | 2020 | 1 | 24 | 238 | 17 | 45 | 31 | -1 | 4027 |
| 1/25/2020 | 2020 | 1 | 25 | 239 | 20 | 45 | 32.5 | 0.5 | 4027.5 |
| 1/26/2020 | 2020 | 1 | 26 | 240 | 22 | 47 | 34.5 | 2.5 | 4030 |
| 1/27/2020 | 2020 | 1 | 27 | 241 | 20 | 33 | 26.5 | -5.5 | 4024.5 |
| 1/28/2020 | 2020 | 1 | 28 | 242 | 14 | 41 | 27.5 | -4.5 | 4020 |
| 1/29/2020 | 2020 | 1 | 29 | 243 | 14 | 33 | 23.5 | -8.5 | 4011.5 |
| 1/30/2020 | 2020 | 1 | 30 | 244 | 11 | 39 | 25 | -7 | 4004.5 |
| 1/31/2020 | 2020 | 1 | 31 | 245 | 9 | 40 | 24.5 | -7.5 | 3997 |
| 2/1/2020 | 2020 | 2 | 1 | 246 | 21 | 52 | 36.5 | 4.5 | 4001.5 |
| 2/2/2020 | 2020 | 2 | 2 | 247 | 22 | 55 | 38.5 | 6.5 | 4008 |
| 2/3/2020 | 2020 | 2 | 3 | 248 | 19 | 44 | 31.5 | -0.5 | 4007.5 |
| 2/4/2020 | 2020 | 2 | 4 | 249 | -5 | 21 | 8 | -24 | 3983.5 |
| 2/5/2020 | 2020 | 2 | 5 | 250 | -7 | 22 | 7.5 | -24.5 | 3959 |
| 2/6/2020 | 2020 | 2 | 6 | 251 | 11 | 36 | 23.5 | -8.5 | 3950.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/7/2020 | 2020 | 2 | 7 | 252 | 28 | 48 | 38 | 6 | 3956.5 |
| 2/8/2020 | 2020 | 2 | 8 | 253 | 24 | 50 | 37 | 5 | 3961.5 |
| 2/9/2020 | 2020 | 2 | 9 | 254 | 25 | 44 | 34.5 | 2.5 | 3964 |
| 2/10/2020 | 2020 | 2 | 10 | 255 | 26 | 36 | 31 | -1 | 3963 |
| 2/11/2020 | 2020 | 2 | 11 | 256 | 21 | 31 | 26 | -6 | 3957 |
| 2/12/2020 | 2020 | 2 | 12 | 257 | 10 | 33 | 21.5 | -10.5 | 3946.5 |
| 2/13/2020 | 2020 | 2 | 13 | 258 | 9 | 39 | 24 | -8 | 3938.5 |
| 2/14/2020 | 2020 | 2 | 14 | 259 | 13 | 45 | 29 | -3 | 3935.5 |
| 2/15/2020 | 2020 | 2 | 15 | 260 | 23 | 44 | 33.5 | 1.5 | 3937 |
| 2/16/2020 | 2020 | 2 | 16 | 261 | 30 | 49 | 39.5 | 7.5 | 3944.5 |
| 2/17/2020 | 2020 | 2 | 17 | 262 | 26 | 49 | 37.5 | 5.5 | 3950 |
| 2/18/2020 | 2020 | 2 | 18 | 263 | 20 | 47 | 33.5 | 1.5 | 3951.5 |
| 2/19/2020 | 2020 | 2 | 19 | 264 | 23 | 46 | 34.5 | 2.5 | 3954 |
| 2/20/2020 | 2020 | 2 | 20 | 265 | 17 | 48 | 32.5 | 0.5 | 3954.5 |
| 2/21/2020 | 2020 | 2 | 21 | 266 | 27 | 49 | 38 | 6 | 3960.5 |
| 2/22/2020 | 2020 | 2 | 22 | 267 | 31 | 38 | 34.5 | 2.5 | 3963 |
| 2/23/2020 | 2020 | 2 | 23 | 268 | 21 | 31 | 26 | -6 | 3957 |
| 2/24/2020 | 2020 | 2 | 24 | 269 | 21 | 41 | 31 | -1 | 3956 |
| 2/25/2020 | 2020 | 2 | 25 | 270 | 6 | 27 | 16.5 | -15.5 | 3940.5 |
| 2/26/2020 | 2020 | 2 | 26 | 271 | 1 | 36 | 18.5 | -13.5 | 3927 |
| 2/27/2020 | 2020 | 2 | 27 | 272 | 18 | 46 | 32 | 0 | 3927 |
| 2/28/2020 | 2020 | 2 | 28 | 273 | 16 | 51 | 33.5 | 1.5 | 3928.5 |
| 2/29/2020 | 2020 | 2 | 29 | 274 | 24 | 48 | 36 | 4 | 3932.5 |
| 3/1/2020 | 2020 | 3 | 1 | 275 | 27 | 45 | 36 | 4 | 3936.5 |
| 3/2/2020 | 2020 | 3 | 2 | 276 | 20 | 45 | 32.5 | 0.5 | 3937 |
| 3/3/2020 | 2020 | 3 | 3 | 277 | 20 | 48 | 34 | 2 | 3939 |
| 3/4/2020 | 2020 | 3 | 4 | 278 | 21 | 51 | 36 | 4 | 3943 |
| 3/5/2020 | 2020 | 3 | 5 | 279 | 23 | 56 | 39.5 | 7.5 | 3950.5 |
| 3/6/2020 | 2020 | 3 | 6 | 280 | 31 | 51 | 41 | 9 | 3959.5 |
| 3/7/2020 | 2020 | 3 | 7 | 281 | 29 | 55 | 42 | 10 | 3969.5 |
| 3/8/2020 | 2020 | 3 | 8 | 282 | 31 | 45 | 38 | 6 | 3975.5 |
| 3/9/2020 | 2020 | 3 | 9 | 283 | 29 | 49 | 39 | 7 | 3982.5 |
| 3/10/2020 | 2020 | 3 | 10 | 284 | 28 | 46 | 37 | 5 | 3987.5 |
| 3/11/2020 | 2020 | 3 | 11 | 285 | 35 | 47 | 41 | 9 | 3996.5 |
| 3/12/2020 | 2020 | 3 | 12 | 286 | 36 | 51 | 43.5 | 11.5 | 4008 |
| 3/13/2020 | 2020 | 3 | 13 | 287 | 29 | 43 | 36 | 4 | 4012 |
| 3/14/2020 | 2020 | 3 | 14 | 288 | 27 | 47 | 37 | 5 | 4017 |
| 3/15/2020 | 2020 | 3 | 15 | 289 | 27 | 53 | 40 | 8 | 4025 |
| 3/16/2020 | 2020 | 3 | 16 | 290 | 27 | 56 | 41.5 | 9.5 | 4034.5 |
| 3/17/2020 | 2020 | 3 | 17 | 291 | 31 | 53 | 42 | 10 | 4044.5 |
| 3/18/2020 | 2020 | 3 | 18 | 292 | 26 | 46 | 36 | 4 | 4048.5 |
| 3/19/2020 | 2020 | 3 | 19 | 293 | 18 | 35 | 26.5 | -5.5 | 4043 |
| 3/20/2020 | 2020 | 3 | 20 | 294 | 14 | 44 | 29 | -3 | 4040 |
| 3/21/2020 | 2020 | 3 | 21 | 295 | 26 | 50 | 38 | 6 | 4046 |
| 3/22/2020 | 2020 | 3 | 22 | 296 | 27 | 46 | 36.5 | 4.5 | 4050.5 |
| 3/23/2020 | 2020 | 3 | 23 | 297 | 30 | 49 | 39.5 | 7.5 | 4058 |
| 3/24/2020 | 2020 | 3 | 24 | 298 | 27 | 52 | 39.5 | 7.5 | 4065.5 |
| 3/25/2020 | 2020 | 3 | 25 | 299 | 33 | 54 | 43.5 | 11.5 | 4077 |
| 3/26/2020 | 2020 | 3 | 26 | 300 | 32 | 52 | 42 | 10 | 4087 |
| 3/27/2020 | 2020 | 3 | 27 | 301 | 20 | 37 | 28.5 | -3.5 | 4083.5 |
| 3/28/2020 | 2020 | 3 | 28 | 302 | 15 | 38 | 26.5 | -5.5 | 4078 |
| 3/29/2020 | 2020 | 3 | 29 | 303 | 22 | 50 | 36 | 4 | 4082 |
| 3/30/2020 | 2020 | 3 | 30 | 304 | 26 | 47 | 36.5 | 4.5 | 4086.5 |
| 3/31/2020 | 2020 | 3 | 31 | 305 | 25 | 57 | 41 | 9 | 4095.5 |
| 4/1/2020 | 2020 | 4 | 1 | 306 | 37 | 57 | 47 | 15 | 4110.5 |
| 4/2/2020 | 2020 | 4 | 2 | 307 | 35 | 56 | 45.5 | 13.5 | 4124 |
| 4/3/2020 | 2020 | 4 | 3 | 308 | 27 | 54 | 40.5 | 8.5 | 4132.5 |
| 4/4/2020 | 2020 | 4 | 4 | 309 | 28 | 56 | 42 | 10 | 4142.5 |
| 4/5/2020 | 2020 | 4 | 5 | 310 | 29 | 57 | 43 | 11 | 4153.5 |
| 4/6/2020 | 2020 | 4 | 6 | 311 | 29 | 57 | 43 | 11 | 4164.5 |
| 4/7/2020 | 2020 | 4 | 7 | 312 | 29 | 58 | 43.5 | 11.5 | 4176 |
| 4/8/2020 | 2020 | 4 | 8 | 313 | 29 | 61 | 45 | 13 | 4189 |
| 4/9/2020 | 2020 | 4 | 9 | 314 | 32 | 58 | 45 | 13 | 4202 |
| 4/10/2020 | 2020 | 4 | 10 | 315 | 26 | 55 | 40.5 | 8.5 | 4210.5 |
| 4/11/2020 | 2020 | 4 | 11 | 316 | 25 | 55 | 40 | 8 | 4218.5 |
| 4/12/2020 | 2020 | 4 | 12 | 317 | 29 | 50 | 39.5 | 7.5 | 4226 |
| 4/13/2020 | 2020 | 4 | 13 | 318 | 19 | 37 | 28 | -4 | 4222 |
| 4/14/2020 | 2020 | 4 | 14 | 319 | 9 | 37 | 23 | -9 | 4213 |
| 4/15/2020 | 2020 | 4 | 15 | 320 | 14 | 47 | 30.5 | -1.5 | 4211.5 |
| 4/16/2020 | 2020 | 4 | 16 | 321 | 28 | 54 | 41 | 9 | 4220.5 |
| 4/17/2020 | 2020 | 4 | 17 | 322 | 29 | 55 | 42 | 10 | 4230.5 |
| 4/18/2020 | 2020 | 4 | 18 | 323 | 31 | 51 | 41 | 9 | 4239.5 |
| 4/19/2020 | 2020 | 4 | 19 | 324 | 29 | 54 | 41.5 | 9.5 | 4249 |
| 4/20/2020 | 2020 | 4 | 20 | 325 | 35 | 57 | 46 | 14 | 4263 |
| 4/21/2020 | 2020 | 4 | 21 | 326 | 30 | 56 | 43 | 11 | 4274 |
| 4/22/2020 | 2020 | 4 | 22 | 327 | 33 | 58 | 45.5 | 13.5 | 4287.5 |
| 4/23/2020 | 2020 | 4 | 23 | 328 | 31 | 61 | 46 | 14 | 4301.5 |
| 4/24/2020 | 2020 | 4 | 24 | 329 | 33 | 63 | 48 | 16 | 4317.5 |
| 4/25/2020 | 2020 | 4 | 25 | 330 | 29 | 64 | 46.5 | 14.5 | 4332 |
| 4/26/2020 | 2020 | 4 | 26 | 331 | 38 | 71 | 54.5 | 22.5 | 4354.5 |
| 4/27/2020 | 2020 | 4 | 27 | 332 | 41 | 71 | 56 | 24 | 4378.5 |
| 4/28/2020 | 2020 | 4 | 28 | 333 | 44 | 71 | 57.5 | 25.5 | 4404 |
| 4/29/2020 | 2020 | 4 | 29 | 334 | 38 | 74 | 56 | 24 | 4428 |
| 4/30/2020 | 2020 | 4 | 30 | 335 | 44 | 74 | 59 | 27 | 4455 |
| 5/1/2020 | 2020 | 5 | 1 | 336 | 42 | 73 | 57.5 | 25.5 | 4480.5 |
| 5/2/2020 | 2020 | 5 | 2 | 337 | 44 | 71 | 57.5 | 25.5 | 4506 |
| 5/3/2020 | 2020 | 5 | 3 | 338 | 41 | 71 | 56 | 24 | 4530 |
| 5/4/2020 | 2020 | 5 | 4 | 339 | 38 | 69 | 53.5 | 21.5 | 4551.5 |
| 5/5/2020 | 2020 | 5 | 5 | 340 | 34 | 72 | 53 | 21 | 4572.5 |
| 5/6/2020 | 2020 | 5 | 6 | 341 | 36 | 76 | 56 | 24 | 4596.5 |
| 5/7/2020 | 2020 | 5 | 7 | 342 | 39 | 74 | 56.5 | 24.5 | 4621 |
| 5/8/2020 | 2020 | 5 | 8 | 343 | 34 | 70 | 52 | 20 | 4641 |
| 5/9/2020 | 2020 | 5 | 9 | 344 | 37 | 72 | 54.5 | 22.5 | 4663.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/10/2020 | 2020 | 5 | 10 | 345 | 40 | 72 | 56 | 24 | 4687.5 |
| 5/11/2020 | 2020 | 5 | 11 | 346 | 44 | 66 | 55 | 23 | 4710.5 |
| 5/12/2020 | 2020 | 5 | 12 | 347 | 36 | 66 | 51 | 19 | 4729.5 |
| 5/13/2020 | 2020 | 5 | 13 | 348 | 38 | 65 | 51.5 | 19.5 | 4749 |
| 5/14/2020 | 2020 | 5 | 14 | 349 | 38 | 65 | 51.5 | 19.5 | 4768.5 |
| 5/15/2020 | 2020 | 5 | 15 | 350 | 37 | 67 | 52 | 20 | 4788.5 |
| 5/16/2020 | 2020 | 5 | 16 | 351 | 37 | 73 | 55 | 23 | 4811.5 |
| 5/17/2020 | 2020 | 5 | 17 | 352 | 42 | 75 | 58.5 | 26.5 | 4838 |
| 5/18/2020 | 2020 | 5 | 18 | 353 | 43 | 78 | 60.5 | 28.5 | 4866.5 |
| 5/19/2020 | 2020 | 5 | 19 | 354 | 42 | 74 | 58 | 26 | 4892.5 |
| 5/20/2020 | 2020 | 5 | 20 | 355 | 33 | 62 | 47.5 | 15.5 | 4908 |
| 5/21/2020 | 2020 | 5 | 21 | 356 | 29 | 64 | 46.5 | 14.5 | 4922.5 |
| 5/22/2020 | 2020 | 5 | 22 | 357 | 32 | 69 | 50.5 | 18.5 | 4941 |
| 5/23/2020 | 2020 | 5 | 23 | 358 | 35 | 67 | 51 | 19 | 4960 |
| 5/24/2020 | 2020 | 5 | 24 | 359 | 35 | 64 | 49.5 | 17.5 | 4977.5 |
| 5/25/2020 | 2020 | 5 | 25 | 360 | 32 | 64 | 48 | 16 | 4993.5 |
| 5/26/2020 | 2020 | 5 | 26 | 361 | 32 | 71 | 51.5 | 19.5 | 5013 |
| 5/27/2020 | 2020 | 5 | 27 | 362 | 44 | 77 | 60.5 | 28.5 | 5041.5 |
| 5/28/2020 | 2020 | 5 | 28 | 363 | 45 | 80 | 62.5 | 30.5 | 5072 |
| 5/29/2020 | 2020 | 5 | 29 | 364 | 51 | 79 | 65 | 33 | 5105 |
| 5/30/2020 | 2020 | 5 | 30 | 365 | 49 | 80 | 64.5 | 32.5 | 5137.5 |
| 5/31/2020 | 2020 | 5 | 31 | 366 | 51 | 77 | 64 | 32 | 5169.5 |
| 6/1/2020 | 2020 | 6 | 1 | 1 | 47 | 72 | 59.5 | 27.5 | 27.5 |
| 6/2/2020 | 2020 | 6 | 2 | 2 | 47 | 79 | 63 | 31 | 58.5 |
| 6/3/2020 | 2020 | 6 | 3 | 3 | 47 | 79 | 63 | 31 | 89.5 |
| 6/4/2020 | 2020 | 6 | 4 | 4 | 49 | 82 | 65.5 | 33.5 | 123 |
| 6/5/2020 | 2020 | 6 | 5 | 5 | 52 | 83 | 67.5 | 35.5 | 158.5 |
| 6/6/2020 | 2020 | 6 | 6 | 6 | 48 | 75 | 61.5 | 29.5 | 188 |
| 6/7/2020 | 2020 | 6 | 7 | 7 | 45 | 73 | 59 | 27 | 215 |
| 6/8/2020 | 2020 | 6 | 8 | 8 | 33 | 67 | 50 | 18 | 233 |
| 6/9/2020 | 2020 | 6 | 9 | 9 | 30 | 63 | 46.5 | 14.5 | 247.5 |
| 6/10/2020 | 2020 | 6 | 10 | 10 | 32 | 74 | 53 | 21 | 268.5 |
| 6/11/2020 | 2020 | 6 | 11 | 11 | 40 | 81 | 60.5 | 28.5 | 297 |
| 6/12/2020 | 2020 | 6 | 12 | 12 | 53 | 80 | 66.5 | 34.5 | 331.5 |
| 6/13/2020 | 2020 | 6 | 13 | 13 | 52 | 79 | 65.5 | 33.5 | 365 |
| 6/14/2020 | 2020 | 6 | 14 | 14 | 48 | 78 | 63 | 31 | 396 |
| 6/15/2020 | 2020 | 6 | 15 | 15 | 44 | 79 | 61.5 | 29.5 | 425.5 |
| 6/16/2020 | 2020 | 6 | 16 | 16 | 51 | 77 | 64 | 32 | 457.5 |
| 6/17/2020 | 2020 | 6 | 17 | 17 | 48 | 77 | 62.5 | 30.5 | 488 |
| 6/18/2020 | 2020 | 6 | 18 | 18 | 44 | 75 | 59.5 | 27.5 | 515.5 |
| 6/19/2020 | 2020 | 6 | 19 | 19 | 44 | 75 | 59.5 | 27.5 | 543 |
| 6/20/2020 | 2020 | 6 | 20 | 20 | 41 | 77 | 59 | 27 | 570 |
| 6/21/2020 | 2020 | 6 | 21 | 21 | 46 | 81 | 63.5 | 31.5 | 601.5 |
| 6/22/2020 | 2020 | 6 | 22 | 22 | 50 | 84 | 67 | 35 | 636.5 |
| 6/23/2020 | 2020 | 6 | 23 | 23 | 49 | 85 | 67 | 35 | 671.5 |
| 6/24/2020 | 2020 | 6 | 24 | 24 | 52 | 83 | 67.5 | 35.5 | 707 |
| 6/25/2020 | 2020 | 6 | 25 | 25 | 56 | 82 | 69 | 37 | 744 |
| 6/26/2020 | 2020 | 6 | 26 | 26 | 53 | 77 | 65 | 33 | 777 |
| 6/27/2020 | 2020 | 6 | 27 | 27 | 44 | 81 | 62.5 | 30.5 | 807.5 |
| 6/28/2020 | 2020 | 6 | 28 | 28 | 55 | 77 | 66 | 34 | 841.5 |
| 6/29/2020 | 2020 | 6 | 29 | 29 | 53 | 76 | 64.5 | 32.5 | 874 |
| 6/30/2020 | 2020 | 6 | 30 | 30 | 44 | 71 | 57.5 | 25.5 | 899.5 |
| 7/1/2020 | 2020 | 7 | 1 | 31 | 40 | 75 | 57.5 | 25.5 | 925 |
| 7/2/2020 | 2020 | 7 | 2 | 32 | 45 | 76 | 60.5 | 28.5 | 953.5 |
| 7/3/2020 | 2020 | 7 | 3 | 33 | 51 | 76 | 63.5 | 31.5 | 985 |
| 7/4/2020 | 2020 | 7 | 4 | 34 | 47 | 81 | 64 | 32 | 1017 |
| 7/5/2020 | 2020 | 7 | 5 | 35 | 49 | 84 | 66.5 | 34.5 | 1051.5 |
| 7/6/2020 | 2020 | 7 | 6 | 36 | 54 | 84 | 69 | 37 | 1088.5 |
| 7/7/2020 | 2020 | 7 | 7 | 37 | 53 | 82 | 67.5 | 35.5 | 1124 |
| 7/8/2020 | 2020 | 7 | 8 | 38 | 51 | 83 | 67 | 35 | 1159 |
| 7/9/2020 | 2020 | 7 | 9 | 39 | 50 | 84 | 67 | 35 | 1194 |
| 7/10/2020 | 2020 | 7 | 10 | 40 | 55 | 88 | 71.5 | 39.5 | 1233.5 |
| 7/11/2020 | 2020 | 7 | 11 | 41 | 53 | 90 | 71.5 | 39.5 | 1273 |
| 7/12/2020 | 2020 | 7 | 12 | 42 | 58 | 86 | 72 | 40 | 1313 |
| 7/13/2020 | 2020 | 7 | 13 | 43 | 49 | 86 | 67.5 | 35.5 | 1348.5 |
| 7/14/2020 | 2020 | 7 | 14 | 44 | 55 | 82 | 68.5 | 36.5 | 1385 |
| 7/15/2020 | 2020 | 7 | 15 | 45 | 52 | 80 | 66 | 34 | 1419 |
| 7/16/2020 | 2020 | 7 | 16 | 46 | 51 | 77 | 64 | 32 | 1451 |
| 7/17/2020 | 2020 | 7 | 17 | 47 | 50 | 75 | 62.5 | 30.5 | 1481.5 |
| 7/18/2020 | 2020 | 7 | 18 | 48 | 47 | 78 | 62.5 | 30.5 | 1512 |
| 7/19/2020 | 2020 | 7 | 19 | 49 | 50 | 83 | 66.5 | 34.5 | 1546.5 |
| 7/20/2020 | 2020 | 7 | 20 | 50 | 51 | 84 | 67.5 | 35.5 | 1582 |
| 7/21/2020 | 2020 | 7 | 21 | 51 | 53 | 81 | 67 | 35 | 1617 |
| 7/22/2020 | 2020 | 7 | 22 | 52 | 50 | 67 | 58.5 | 26.5 | 1643.5 |
| 7/23/2020 | 2020 | 7 | 23 | 53 | 48 | 67 | 57.5 | 25.5 | 1669 |
| 7/24/2020 | 2020 | 7 | 24 | 54 | 49 | 64 | 56.5 | 24.5 | 1693.5 |
| 7/25/2020 | 2020 | 7 | 25 | 55 | 51 | 65 | 58 | 26 | 1719.5 |
| 7/26/2020 | 2020 | 7 | 26 | 56 | 49 | 74 | 61.5 | 29.5 | 1749 |
| 7/27/2020 | 2020 | 7 | 27 | 57 | 50 | 74 | 62 | 30 | 1779 |
| 7/28/2020 | 2020 | 7 | 28 | 58 | 50 | 76 | 63 | 31 | 1810 |
| 7/29/2020 | 2020 | 7 | 29 | 59 | 48 | 82 | 65 | 33 | 1843 |
| 7/30/2020 | 2020 | 7 | 30 | 60 | 48 | 84 | 66 | 34 | 1877 |
| 7/31/2020 | 2020 | 7 | 31 | 61 | 52 | 83 | 67.5 | 35.5 | 1912.5 |
| 8/1/2020 | 2020 | 8 | 1 | 62 | 53 | 81 | 67 | 35 | 1947.5 |
| 8/2/2020 | 2020 | 8 | 2 | 63 | 53 | 81 | 67 | 35 | 1982.5 |
| 8/3/2020 | 2020 | 8 | 3 | 64 | 54 | 83 | 68.5 | 36.5 | 2019 |
| 8/4/2020 | 2020 | 8 | 4 | 65 | 56 | 82 | 69 | 37 | 2056 |
| 8/5/2020 | 2020 | 8 | 5 | 66 | 52 | 72 | 62 | 30 | 2086 |
| 8/6/2020 | 2020 | 8 | 6 | 67 | 47 | 79 | 63 | 31 | 2117 |
| 8/7/2020 | 2020 | 8 | 7 | 68 | 47 | 75 | 61 | 29 | 2146 |
| 8/8/2020 | 2020 | 8 | 8 | 69 | 52 | 79 | 65.5 | 33.5 | 2179.5 |
| 8/9/2020 | 2020 | 8 | 9 | 70 | 49 | 81 | 65 | 33 | 2212.5 |
| 8/10/2020 | 2020 | 8 | 10 | 71 | 53 | 83 | 68 | 36 | 2248.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/11/2020 | 2020 | 8 | 11 | 72 | 51 | 81 | 66 | 34 | 2282.5 |
| 8/12/2020 | 2020 | 8 | 12 | 73 | 52 | 83 | 67.5 | 35.5 | 2318 |
| 8/13/2020 | 2020 | 8 | 13 | 74 | 53 | 82 | 67.5 | 35.5 | 2353.5 |
| 8/14/2020 | 2020 | 8 | 14 | 75 | 53 | 85 | 69 | 37 | 2390.5 |
| 8/15/2020 | 2020 | 8 | 15 | 76 | 52 | 91 | 71.5 | 39.5 | 2430 |
| 8/16/2020 | 2020 | 8 | 16 | 77 | 56 | 85 | 70.5 | 38.5 | 2468.5 |
| 8/17/2020 | 2020 | 8 | 17 | 78 | 51 | 82 | 66.5 | 34.5 | 2503 |
| 8/18/2020 | 2020 | 8 | 18 | 79 | 56 | 83 | 69.5 | 37.5 | 2540.5 |
| 8/19/2020 | 2020 | 8 | 19 | 80 | 55 | 85 | 70 | 38 | 2578.5 |
| 8/20/2020 | 2020 | 8 | 20 | 81 | 57 | 86 | 71.5 | 39.5 | 2618 |
| 8/21/2020 | 2020 | 8 | 21 | 82 | 58 | 86 | 72 | 40 | 2658 |
| 8/22/2020 | 2020 | 8 | 22 | 83 | 53 | 85 | 69 | 37 | 2695 |
| 8/23/2020 | 2020 | 8 | 23 | 84 | 53 | 84 | 68.5 | 36.5 | 2731.5 |
| 8/24/2020 | 2020 | 8 | 24 | 85 | 54 | 83 | 68.5 | 36.5 | 2768 |
| 8/25/2020 | 2020 | 8 | 25 | 86 | 51 | 82 | 66.5 | 34.5 | 2802.5 |
| 8/26/2020 | 2020 | 8 | 26 | 87 | 52 | 78 | 65 | 33 | 2835.5 |
| 8/27/2020 | 2020 | 8 | 27 | 88 | 52 | 80 | 66 | 34 | 2869.5 |
| 8/28/2020 | 2020 | 8 | 28 | 89 | 47 | 84 | 65.5 | 33.5 | 2903 |
| 8/29/2020 | 2020 | 8 | 29 | 90 | 47 | 78 | 62.5 | 30.5 | 2933.5 |
| 8/30/2020 | 2020 | 8 | 30 | 91 | 53 | 74 | 63.5 | 31.5 | 2965 |
| 8/31/2020 | 2020 | 8 | 31 | 92 | 51 | 73 | 62 | 30 | 2995 |
| 9/1/2020 | 2020 | 9 | 1 | 93 | 42 | 70 | 56 | 24 | 3019 |
| 9/2/2020 | 2020 | 9 | 2 | 94 | 40 | 78 | 59 | 27 | 3046 |
| 9/3/2020 | 2020 | 9 | 3 | 95 | 44 | 82 | 63 | 31 | 3077 |
| 9/4/2020 | 2020 | 9 | 4 | 96 | 53 | 84 | 68.5 | 36.5 | 3113.5 |
| 9/5/2020 | 2020 | 9 | 5 | 97 | 54 | 83 | 68.5 | 36.5 | 3150 |
| 9/6/2020 | 2020 | 9 | 6 | 98 | 53 | 85 | 69 | 37 | 3187 |
| 9/7/2020 | 2020 | 9 | 7 | 99 | 50 | 85 | 67.5 | 35.5 | 3222.5 |
| 9/8/2020 | 2020 | 9 | 8 | 100 | 37 | 74 | 55.5 | 23.5 | 3246 |
| 9/9/2020 | 2020 | 9 | 9 | 101 | 34 | 50 | 42 | 10 | 3256 |
| 9/10/2020 | 2020 | 9 | 10 | 102 | 33 | 56 | 44.5 | 12.5 | 3268.5 |
| 9/11/2020 | 2020 | 9 | 11 | 103 | 32 | 64 | 48 | 16 | 3284.5 |
| 9/12/2020 | 2020 | 9 | 12 | 104 | 33 | 65 | 49 | 17 | 3301.5 |
| 9/13/2020 | 2020 | 9 | 13 | 105 | 44 | 69 | 56.5 | 24.5 | 3326 |
| 9/14/2020 | 2020 | 9 | 14 | 106 | 44 | 70 | 57 | 25 | 3351 |
| 9/15/2020 | 2020 | 9 | 15 | 107 | 42 | 73 | 57.5 | 25.5 | 3376.5 |
| 9/16/2020 | 2020 | 9 | 16 | 108 | 40 | 76 | 58 | 26 | 3402.5 |
| 9/17/2020 | 2020 | 9 | 17 | 109 | 47 | 74 | 60.5 | 28.5 | 3431 |
| 9/18/2020 | 2020 | 9 | 18 | 110 | 43 | 73 | 58 | 26 | 3457 |
| 9/19/2020 | 2020 | 9 | 19 | 111 | 46 | 74 | 60 | 28 | 3485 |
| 9/20/2020 | 2020 | 9 | 20 | 112 | 47 | 72 | 59.5 | 27.5 | 3512.5 |
| 9/21/2020 | 2020 | 9 | 21 | 113 | 46 | 74 | 60 | 28 | 3540.5 |
| 9/22/2020 | 2020 | 9 | 22 | 114 | 45 | 73 | 59 | 27 | 3567.5 |
| 9/23/2020 | 2020 | 9 | 23 | 115 | 44 | 71 | 57.5 | 25.5 | 3593 |
| 9/24/2020 | 2020 | 9 | 24 | 116 | 42 | 76 | 59 | 27 | 3620 |
| 9/25/2020 | 2020 | 9 | 25 | 117 | 46 | 77 | 61.5 | 29.5 | 3649.5 |
| 9/26/2020 | 2020 | 9 | 26 | 118 | 51 | 76 | 63.5 | 31.5 | 3681 |
| 9/27/2020 | 2020 | 9 | 27 | 119 | 42 | 74 | 58 | 26 | 3707 |
| 9/28/2020 | 2020 | 9 | 28 | 120 | 34 | 66 | 50 | 18 | 3725 |
| 9/29/2020 | 2020 | 9 | 29 | 121 | 31 | 73 | 52 | 20 | 3745 |
| 9/30/2020 | 2020 | 9 | 30 | 122 | 38 | 76 | 57 | 25 | 3770 |
| 10/1/2020 | 2020 | 10 | 1 | 123 | 37 | 75 | 56 | 24 | 3794 |
| 10/2/2020 | 2020 | 10 | 2 | 124 | 38 | 74 | 56 | 24 | 3818 |
| 10/3/2020 | 2020 | 10 | 3 | 125 | 38 | 73 | 55.5 | 23.5 | 3841.5 |
| 10/4/2020 | 2020 | 10 | 4 | 126 | 40 | 74 | 57 | 25 | 3866.5 |
| 10/5/2020 | 2020 | 10 | 5 | 127 | 39 | 75 | 57 | 25 | 3891.5 |
| 10/6/2020 | 2020 | 10 | 6 | 128 | 37 | 76 | 56.5 | 24.5 | 3916 |
| 10/7/2020 | 2020 | 10 | 7 | 129 | 40 | 76 | 58 | 26 | 3942 |
| 10/8/2020 | 2020 | 10 | 8 | 130 | 42 | 73 | 57.5 | 25.5 | 3967.5 |
| 10/9/2020 | 2020 | 10 | 9 | 131 | 41 | 71 | 56 | 24 | 3991.5 |
| 10/10/2020 | 2020 | 10 | 10 | 132 | 39 | 70 | 54.5 | 22.5 | 4014 |
| 10/11/2020 | 2020 | 10 | 11 | 133 | 35 | 64 | 49.5 | 17.5 | 4031.5 |
| 10/12/2020 | 2020 | 10 | 12 | 134 | 31 | 69 | 50 | 18 | 4049.5 |
| 10/13/2020 | 2020 | 10 | 13 | 135 | 37 | 72 | 54.5 | 22.5 | 4072 |
| 10/14/2020 | 2020 | 10 | 14 | 136 | 42 | 73 | 57.5 | 25.5 | 4097.5 |
| 10/15/2020 | 2020 | 10 | 15 | 137 | 35 | 77 | 56 | 24 | 4121.5 |
| 10/16/2020 | 2020 | 10 | 16 | 138 | 30 | 70 | 50 | 18 | 4139.5 |
| 10/17/2020 | 2020 | 10 | 17 | 139 | 38 | 69 | 53.5 | 21.5 | 4161 |
| 10/18/2020 | 2020 | 10 | 18 | 140 | 40 | 69 | 54.5 | 22.5 | 4183.5 |
| 10/19/2020 | 2020 | 10 | 19 | 141 | 40 | 69 | 54.5 | 22.5 | 4206 |
| 10/20/2020 | 2020 | 10 | 20 | 142 | 38 | 71 | 54.5 | 22.5 | 4228.5 |
| 10/21/2020 | 2020 | 10 | 21 | 143 | 37 | 68 | 52.5 | 20.5 | 4249 |
| 10/22/2020 | 2020 | 10 | 22 | 144 | 39 | 64 | 51.5 | 19.5 | 4268.5 |
| 10/23/2020 | 2020 | 10 | 23 | 145 | 36 | 63 | 49.5 | 17.5 | 4286 |
| 10/24/2020 | 2020 | 10 | 24 | 146 | 45 | 63 | 54 | 22 | 4308 |
| 10/25/2020 | 2020 | 10 | 25 | 147 | 33 | 59 | 46 | 14 | 4322 |
| 10/26/2020 | 2020 | 10 | 26 | 148 | 15 | 39 | 27 | -5 | 4317 |
| 10/27/2020 | 2020 | 10 | 27 | 149 | 15 | 24 | 19.5 | -12.5 | 4304.5 |
| 10/28/2020 | 2020 | 10 | 28 | 150 | 14 | 41 | 27.5 | -4.5 | 4300 |
| 10/29/2020 | 2020 | 10 | 29 | 151 | 25 | 53 | 39 | 7 | 4307 |
| 10/30/2020 | 2020 | 10 | 30 | 152 | 29 | 60 | 44.5 | 12.5 | 4319.5 |
| 10/31/2020 | 2020 | 10 | 31 | 153 | 32 | 60 | 46 | 14 | 4333.5 |
| 11/1/2020 | 2020 | 11 | 1 | 154 | 34 | 63 | 48.5 | 16.5 | 4350 |
| 11/2/2020 | 2020 | 11 | 2 | 155 | 36 | 65 | 50.5 | 18.5 | 4368.5 |
| 11/3/2020 | 2020 | 11 | 3 | 156 | 38 | 67 | 52.5 | 20.5 | 4389 |
| 11/4/2020 | 2020 | 11 | 4 | 157 | 34 | 61 | 47.5 | 15.5 | 4404.5 |
| 11/5/2020 | 2020 | 11 | 5 | 158 | 32 | 63 | 47.5 | 15.5 | 4420 |
| 11/6/2020 | 2020 | 11 | 6 | 159 | 42 | 63 | 52.5 | 20.5 | 4440.5 |
| 11/7/2020 | 2020 | 11 | 7 | 160 | 31 | 55 | 43 | 11 | 4451.5 |
| 11/8/2020 | 2020 | 11 | 8 | 161 | 27 | 44 | 35.5 | 3.5 | 4455 |
| 11/9/2020 | 2020 | 11 | 9 | 162 | 18 | 31 | 24.5 | -7.5 | 4447.5 |
| 11/10/2020 | 2020 | 11 | 10 | 163 | 14 | 33 | 23.5 | -8.5 | 4439 |
| 11/11/2020 | 2020 | 11 | 11 | 164 | 13 | 44 | 28.5 | -3.5 | 4435.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/12/2020 | 2020 | 11 | 12 | 165 | 21 | 46 | 33.5 | 1.5 | 4437 |
| 11/13/2020 | 2020 | 11 | 13 | 166 | 28 | 49 | 38.5 | 6.5 | 4443.5 |
| 11/14/2020 | 2020 | 11 | 14 | 167 | 20 | 44 | 32 | 0 | 4443.5 |
| 11/15/2020 | 2020 | 11 | 15 | 168 | 21 | 53 | 37 | 5 | 4448.5 |
| 11/16/2020 | 2020 | 11 | 16 | 169 | 29 | 61 | 45 | 13 | 4461.5 |
| 11/17/2020 | 2020 | 11 | 17 | 170 | 33 | 62 | 47.5 | 15.5 | 4477 |
| 11/18/2020 | 2020 | 11 | 18 | 171 | 37 | 62 | 49.5 | 17.5 | 4494.5 |
| 11/19/2020 | 2020 | 11 | 19 | 172 | 40 | 60 | 50 | 18 | 4512.5 |
| 11/20/2020 | 2020 | 11 | 20 | 173 | 39 | 57 | 48 | 16 | 4528.5 |
| 11/21/2020 | 2020 | 11 | 21 | 174 | 31 | 58 | 44.5 | 12.5 | 4541 |
| 11/22/2020 | 2020 | 11 | 22 | 175 | 29 | 54 | 41.5 | 9.5 | 4550.5 |
| 11/23/2020 | 2020 | 11 | 23 | 176 | 34 | 54 | 44 | 12 | 4562.5 |
| 11/24/2020 | 2020 | 11 | 24 | 177 | 21 | 38 | 29.5 | -2.5 | 4560 |
| 11/25/2020 | 2020 | 11 | 25 | 178 | 19 | 44 | 31.5 | -0.5 | 4559.5 |
| 11/26/2020 | 2020 | 11 | 26 | 179 | 22 | 42 | 32 | 0 | 4559.5 |
| 11/27/2020 | 2020 | 11 | 27 | 180 | 22 | 30 | 26 | -6 | 4553.5 |
| 11/28/2020 | 2020 | 11 | 28 | 181 | 15 | 40 | 27.5 | -4.5 | 4549 |
| 11/29/2020 | 2020 | 11 | 29 | 182 | 19 | 46 | 32.5 | 0.5 | 4549.5 |
| 11/30/2020 | 2020 | 11 | 30 | 183 | 16 | 45 | 30.5 | -1.5 | 4548 |
| 12/1/2020 | 2020 | 12 | 1 | 184 | 17 | 38 | 27.5 | -4.5 | 4543.5 |
| 12/2/2020 | 2020 | 12 | 2 | 185 | 8 | 33 | 20.5 | -11.5 | 4532 |
| 12/3/2020 | 2020 | 12 | 3 | 186 | 6 | 34 | 20 | -12 | 4520 |
| 12/4/2020 | 2020 | 12 | 4 | 187 | 11 | 44 | 27.5 | -4.5 | 4515.5 |
| 12/5/2020 | 2020 | 12 | 5 | 188 | 19 | 46 | 32.5 | 0.5 | 4516 |
| 12/6/2020 | 2020 | 12 | 6 | 189 | 20 | 48 | 34 | 2 | 4518 |
| 12/7/2020 | 2020 | 12 | 7 | 190 | 18 | 52 | 35 | 3 | 4521 |
| 12/8/2020 | 2020 | 12 | 8 | 191 | 23 | 54 | 38.5 | 6.5 | 4527.5 |
| 12/9/2020 | 2020 | 12 | 9 | 192 | 22 | 54 | 38 | 6 | 4533.5 |
| 12/10/2020 | 2020 | 12 | 10 | 193 | 26 | 38 | 32 | 0 | 4533.5 |
| 12/11/2020 | 2020 | 12 | 11 | 194 | 16 | 34 | 25 | -7 | 4526.5 |
| 12/12/2020 | 2020 | 12 | 12 | 195 | 9 | 30 | 19.5 | -12.5 | 4514 |
| 12/13/2020 | 2020 | 12 | 13 | 196 | 3 | 33 | 18 | -14 | 4500 |
| 12/14/2020 | 2020 | 12 | 14 | 197 | 17 | 41 | 29 | -3 | 4497 |
| 12/15/2020 | 2020 | 12 | 15 | 198 | 6 | 28 | 17 | -15 | 4482 |
| 12/16/2020 | 2020 | 12 | 16 | 199 | 10 | 38 | 24 | -8 | 4474 |
| 12/17/2020 | 2020 | 12 | 17 | 200 | 13 | 44 | 28.5 | -3.5 | 4470.5 |
| 12/18/2020 | 2020 | 12 | 18 | 201 | 12 | 35 | 23.5 | -8.5 | 4462 |
| 12/19/2020 | 2020 | 12 | 19 | 202 | 10 | 40 | 25 | -7 | 4455 |
| 12/20/2020 | 2020 | 12 | 20 | 203 | 16 | 45 | 30.5 | -1.5 | 4453.5 |
| 12/21/2020 | 2020 | 12 | 21 | 204 | 22 | 49 | 35.5 | 3.5 | 4457 |
| 12/22/2020 | 2020 | 12 | 22 | 205 | 25 | 43 | 34 | 2 | 4459 |
| 12/23/2020 | 2020 | 12 | 23 | 206 | 6 | 26 | 16 | -16 | 4443 |
| 12/24/2020 | 2020 | 12 | 24 | 207 | 4 | 35 | 19.5 | -12.5 | 4430.5 |
| 12/25/2020 | 2020 | 12 | 25 | 208 | 13 | 45 | 29 | -3 | 4427.5 |
| 12/26/2020 | 2020 | 12 | 26 | 209 | 21 | 46 | 33.5 | 1.5 | 4429 |
| 12/27/2020 | 2020 | 12 | 27 | 210 | 23 | 44 | 33.5 | 1.5 | 4430.5 |
| 12/28/2020 | 2020 | 12 | 28 | 211 | 27 | 47 | 37 | 5 | 4435.5 |
| 12/29/2020 | 2020 | 12 | 29 | 212 | 10 | 28 | 19 | -13 | 4422.5 |
| 12/30/2020 | 2020 | 12 | 30 | 213 | 6 | 30 | 18 | -14 | 4408.5 |
| 12/31/2020 | 2020 | 12 | 31 | 214 | 6 | 38 | 22 | -10 | 4398.5 |
| 1/1/2021 | 2021 | 1 | 1 | 215 | 13 | 37 | 25 | -7 | 4391.5 |
| 1/2/2021 | 2021 | 1 | 2 | 216 | 16 | 35 | 25.5 | -6.5 | 4385 |
| 1/3/2021 | 2021 | 1 | 3 | 217 | 17 | 42 | 29.5 | -2.5 | 4382.5 |
| 1/4/2021 | 2021 | 1 | 4 | 218 | 17 | 50 | 33.5 | 1.5 | 4384 |
| 1/5/2021 | 2021 | 1 | 5 | 219 | 17 | 43 | 30 | -2 | 4382 |
| 1/6/2021 | 2021 | 1 | 6 | 220 | 13 | 44 | 28.5 | -3.5 | 4378.5 |
| 1/7/2021 | 2021 | 1 | 7 | 221 | 18 | 47 | 32.5 | 0.5 | 4379 |
| 1/8/2021 | 2021 | 1 | 8 | 222 | 17 | 47 | 32 | 0 | 4379 |
| 1/9/2021 | 2021 | 1 | 9 | 223 | 16 | 36 | 26 | -6 | 4373 |
| 1/10/2021 | 2021 | 1 | 10 | 224 | 10 | 31 | 20.5 | -11.5 | 4361.5 |
| 1/11/2021 | 2021 | 1 | 11 | 225 | 6 | 33 | 19.5 | -12.5 | 4349 |
| 1/12/2021 | 2021 | 1 | 12 | 226 | 5 | 43 | 24 | -8 | 4341 |
| 1/13/2021 | 2021 | 1 | 13 | 227 | 17 | 49 | 33 | 1 | 4342 |
| 1/14/2021 | 2021 | 1 | 14 | 228 | 26 | 44 | 35 | 3 | 4345 |
| 1/15/2021 | 2021 | 1 | 15 | 229 | 21 | 47 | 34 | 2 | 4347 |
| 1/16/2021 | 2021 | 1 | 16 | 230 | 21 | 42 | 31.5 | -0.5 | 4346.5 |
| 1/17/2021 | 2021 | 1 | 17 | 231 | 21 | 49 | 35 | 3 | 4349.5 |
| 1/18/2021 | 2021 | 1 | 18 | 232 | 26 | 47 | 36.5 | 4.5 | 4354 |
| 1/19/2021 | 2021 | 1 | 19 | 233 | 19 | 27 | 23 | -9 | 4345 |
| 1/20/2021 | 2021 | 1 | 20 | 234 | 22 | 42 | 32 | 0 | 4345 |
| 1/21/2021 | 2021 | 1 | 21 | 235 | 21 | 43 | 32 | 0 | 4345 |
| 1/22/2021 | 2021 | 1 | 22 | 236 | 27 | 39 | 33 | 1 | 4346 |
| 1/23/2021 | 2021 | 1 | 23 | 237 | 22 | 39 | 30.5 | -1.5 | 4344.5 |
| 1/24/2021 | 2021 | 1 | 24 | 238 | 19 | 37 | 28 | -4 | 4340.5 |
| 1/25/2021 | 2021 | 1 | 25 | 239 | 6 | 25 | 15.5 | -16.5 | 4324 |
| 1/26/2021 | 2021 | 1 | 26 | 240 | 7 | 18 | 12.5 | -19.5 | 4304.5 |
| 1/27/2021 | 2021 | 1 | 27 | 241 | -2 | 33 | 15.5 | -16.5 | 4288 |
| 1/28/2021 | 2021 | 1 | 28 | 242 | 19 | 47 | 33 | 1 | 4289 |
| 1/29/2021 | 2021 | 1 | 29 | 243 | 20 | 47 | 33.5 | 1.5 | 4290.5 |
| 1/30/2021 | 2021 | 1 | 30 | 244 | 11 | 36 | 23.5 | -8.5 | 4282 |
| 1/31/2021 | 2021 | 1 | 31 | 245 | 8 | 46 | 27 | -5 | 4277 |
| 2/1/2021 | 2021 | 2 | 1 | 246 | 22 | 51 | 36.5 | 4.5 | 4281.5 |
| 2/2/2021 | 2021 | 2 | 2 | 247 | 31 | 51 | 41 | 9 | 4290.5 |
| 2/3/2021 | 2021 | 2 | 3 | 248 | 33 | 47 | 40 | 8 | 4298.5 |
| 2/4/2021 | 2021 | 2 | 4 | 249 | 20 | 38 | 29 | -3 | 4295.5 |
| 2/5/2021 | 2021 | 2 | 5 | 250 | 20 | 39 | 29.5 | -2.5 | 4293 |
| 2/6/2021 | 2021 | 2 | 6 | 251 | 15 | 42 | 28.5 | -3.5 | 4289.5 |
| 2/7/2021 | 2021 | 2 | 7 | 252 | 27 | 49 | 38 | 6 | 4295.5 |
| 2/8/2021 | 2021 | 2 | 8 | 253 | 26 | 49 | 37.5 | 5.5 | 4301 |
| 2/9/2021 | 2021 | 2 | 9 | 254 | 28 | 48 | 38 | 6 | 4307 |
| 2/10/2021 | 2021 | 2 | 10 | 255 | 25 | 45 | 35 | 3 | 4310 |
| 2/11/2021 | 2021 | 2 | 11 | 256 | 23 | 46 | 34.5 | 2.5 | 4312.5 |
| 2/12/2021 | 2021 | 2 | 12 | 257 | 25 | 44 | 34.5 | 2.5 | 4315 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/13/2021 | 2021 | 2 | 13 | 258 | 24 | 42 | 33 | 1 | 4316 |
| 2/14/2021 | 2021 | 2 | 14 | 259 | 15 | 28 | 21.5 | -10.5 | 4305.5 |
| 2/15/2021 | 2021 | 2 | 15 | 260 | 15 | 30 | 22.5 | -9.5 | 4296 |
| 2/16/2021 | 2021 | 2 | 16 | 261 | 11 | 29 | 20 | -12 | 4284 |
| 2/17/2021 | 2021 | 2 | 17 | 262 | 7 | 29 | 18 | -14 | 4270 |
| 2/18/2021 | 2021 | 2 | 18 | 263 | 4 | 30 | 17 | -15 | 4255 |
| 2/19/2021 | 2021 | 2 | 19 | 264 | 8 | 44 | 26 | -6 | 4249 |
| 2/20/2021 | 2021 | 2 | 20 | 265 | 23 | 49 | 36 | 4 | 4253 |
| 2/21/2021 | 2021 | 2 | 21 | 266 | 16 | 35 | 25.5 | -6.5 | 4246.5 |
| 2/22/2021 | 2021 | 2 | 22 | 267 | 15 | 46 | 30.5 | -1.5 | 4245 |
| 2/23/2021 | 2021 | 2 | 23 | 268 | 21 | 49 | 35 | 3 | 4248 |
| 2/24/2021 | 2021 | 2 | 24 | 269 | 22 | 47 | 34.5 | 2.5 | 4250.5 |
| 2/25/2021 | 2021 | 2 | 25 | 270 | 18 | 44 | 31 | -1 | 4249.5 |
| 2/26/2021 | 2021 | 2 | 26 | 271 | 23 | 44 | 33.5 | 1.5 | 4251 |
| 2/27/2021 | 2021 | 2 | 27 | 272 | 13 | 40 | 26.5 | -5.5 | 4245.5 |
| 2/28/2021 | 2021 | 2 | 28 | 273 | 6 | 29 | 17.5 | -14.5 | 4231 |
| 3/1/2021 | 2021 | 3 | 1 | 274 | 4 | 42 | 23 | -9 | 4222 |
| 3/2/2021 | 2021 | 3 | 2 | 275 | 14 | 50 | 32 | 0 | 4222 |
| 3/3/2021 | 2021 | 3 | 3 | 276 | 21 | 54 | 37.5 | 5.5 | 4227.5 |
| 3/4/2021 | 2021 | 3 | 4 | 277 | 24 | 37 | 30.5 | -1.5 | 4226 |
| 3/5/2021 | 2021 | 3 | 5 | 278 | 22 | 50 | 36 | 4 | 4230 |
| 3/6/2021 | 2021 | 3 | 6 | 279 | 29 | 51 | 40 | 8 | 4238 |
| 3/7/2021 | 2021 | 3 | 7 | 280 | 24 | 57 | 40.5 | 8.5 | 4246.5 |
| 3/8/2021 | 2021 | 3 | 8 | 281 | 33 | 64 | 48.5 | 16.5 | 4263 |
| 3/9/2021 | 2021 | 3 | 9 | 282 | 28 | 43 | 35.5 | 3.5 | 4266.5 |
| 3/10/2021 | 2021 | 3 | 10 | 283 | 21 | 41 | 31 | -1 | 4265.5 |
| 3/11/2021 | 2021 | 3 | 11 | 284 | 18 | 49 | 33.5 | 1.5 | 4267 |
| 3/12/2021 | 2021 | 3 | 12 | 285 | 20 | 48 | 34 | 2 | 4269 |
| 3/13/2021 | 2021 | 3 | 13 | 286 | 18 | 30 | 24 | -8 | 4261 |
| 3/14/2021 | 2021 | 3 | 14 | 287 | 17 | 28 | 22.5 | -9.5 | 4251.5 |
| 3/15/2021 | 2021 | 3 | 15 | 288 | 22 | 42 | 32 | 0 | 4251.5 |
| 3/16/2021 | 2021 | 3 | 16 | 289 | 20 | 38 | 29 | -3 | 4248.5 |
| 3/17/2021 | 2021 | 3 | 17 | 290 | 22 | 46 | 34 | 2 | 4250.5 |
| 3/18/2021 | 2021 | 3 | 18 | 291 | 19 | 54 | 36.5 | 4.5 | 4255 |
| 3/19/2021 | 2021 | 3 | 19 | 292 | 26 | 58 | 42 | 10 | 4265 |
| 3/20/2021 | 2021 | 3 | 20 | 293 | 30 | 58 | 44 | 12 | 4277 |
| 3/21/2021 | 2021 | 3 | 21 | 294 | 31 | 52 | 41.5 | 9.5 | 4286.5 |
| 3/22/2021 | 2021 | 3 | 22 | 295 | 20 | 44 | 32 | 0 | 4286.5 |
| 3/23/2021 | 2021 | 3 | 23 | 296 | 23 | 36 | 29.5 | -2.5 | 4284 |
| 3/24/2021 | 2021 | 3 | 24 | 297 | 17 | 29 | 23 | -9 | 4275 |
| 3/25/2021 | 2021 | 3 | 25 | 298 | 22 | 40 | 31 | -1 | 4274 |
| 3/26/2021 | 2021 | 3 | 26 | 299 | 17 | 39 | 28 | -4 | 4270 |
| 3/27/2021 | 2021 | 3 | 27 | 300 | 17 | 43 | 30 | -2 | 4268 |
| 3/28/2021 | 2021 | 3 | 28 | 301 | 19 | 57 | 38 | 6 | 4274 |
| 3/29/2021 | 2021 | 3 | 29 | 302 | 31 | 61 | 46 | 14 | 4288 |
| 3/30/2021 | 2021 | 3 | 30 | 303 | 22 | 52 | 37 | 5 | 4293 |
| 3/31/2021 | 2021 | 3 | 31 | 304 | 15 | 51 | 33 | 1 | 4294 |
| 4/1/2021 | 2021 | 4 | 1 | 305 | 26 | 59 | 42.5 | 10.5 | 4304.5 |
| 4/2/2021 | 2021 | 4 | 2 | 306 | 32 | 63 | 47.5 | 15.5 | 4320 |
| 4/3/2021 | 2021 | 4 | 3 | 307 | 32 | 66 | 49 | 17 | 4337 |
| 4/4/2021 | 2021 | 4 | 4 | 308 | 38 | 68 | 53 | 21 | 4358 |
| 4/5/2021 | 2021 | 4 | 5 | 309 | 36 | 65 | 50.5 | 18.5 | 4376.5 |
| 4/6/2021 | 2021 | 4 | 6 | 310 | 31 | 58 | 44.5 | 12.5 | 4389 |
| 4/7/2021 | 2021 | 4 | 7 | 311 | 25 | 58 | 41.5 | 9.5 | 4398.5 |
| 4/8/2021 | 2021 | 4 | 8 | 312 | 36 | 63 | 49.5 | 17.5 | 4416 |
| 4/9/2021 | 2021 | 4 | 9 | 313 | 29 | 60 | 44.5 | 12.5 | 4428.5 |
| 4/10/2021 | 2021 | 4 | 10 | 314 | 26 | 62 | 44 | 12 | 4440.5 |
| 4/11/2021 | 2021 | 4 | 11 | 315 | 32 | 62 | 47 | 15 | 4455.5 |
| 4/12/2021 | 2021 | 4 | 12 | 316 | 37 | 63 | 50 | 18 | 4473.5 |
| 4/13/2021 | 2021 | 4 | 13 | 317 | 36 | 57 | 46.5 | 14.5 | 4488 |
| 4/14/2021 | 2021 | 4 | 14 | 318 | 37 | 62 | 49.5 | 17.5 | 4505.5 |
| 4/15/2021 | 2021 | 4 | 15 | 319 | 26 | 62 | 44 | 12 | 4517.5 |
| 4/16/2021 | 2021 | 4 | 16 | 320 | 22 | 50 | 36 | 4 | 4521.5 |
| 4/17/2021 | 2021 | 4 | 17 | 321 | 23 | 44 | 33.5 | 1.5 | 4523 |
| 4/18/2021 | 2021 | 4 | 18 | 322 | 26 | 39 | 32.5 | 0.5 | 4523.5 |
| 4/19/2021 | 2021 | 4 | 19 | 323 | 22 | 54 | 38 | 6 | 4529.5 |
| 4/20/2021 | 2021 | 4 | 20 | 324 | 28 | 59 | 43.5 | 11.5 | 4541 |
| 4/21/2021 | 2021 | 4 | 21 | 325 | 30 | 60 | 45 | 13 | 4554 |
| 4/22/2021 | 2021 | 4 | 22 | 326 | 29 | 54 | 41.5 | 9.5 | 4563.5 |
| 4/23/2021 | 2021 | 4 | 23 | 327 | 28 | 51 | 39.5 | 7.5 | 4571 |
| 4/24/2021 | 2021 | 4 | 24 | 328 | 34 | 61 | 47.5 | 15.5 | 4586.5 |
| 4/25/2021 | 2021 | 4 | 25 | 329 | 42 | 66 | 54 | 22 | 4608.5 |
| 4/26/2021 | 2021 | 4 | 26 | 330 | 31 | 58 | 44.5 | 12.5 | 4621 |
| 4/27/2021 | 2021 | 4 | 27 | 331 | 27 | 48 | 37.5 | 5.5 | 4626.5 |
| 4/28/2021 | 2021 | 4 | 28 | 332 | 27 | 46 | 36.5 | 4.5 | 4631 |
| 4/29/2021 | 2021 | 4 | 29 | 333 | 28 | 59 | 43.5 | 11.5 | 4642.5 |
| 4/30/2021 | 2021 | 4 | 30 | 334 | 33 | 66 | 49.5 | 17.5 | 4660 |
| 5/1/2021 | 2021 | 5 | 1 | 335 | 42 | 72 | 57 | 25 | 4685 |
| 5/2/2021 | 2021 | 5 | 2 | 336 | 40 | 67 | 53.5 | 21.5 | 4706.5 |
| 5/3/2021 | 2021 | 5 | 3 | 337 | 31 | 57 | 44 | 12 | 4718.5 |
| 5/4/2021 | 2021 | 5 | 4 | 338 | 30 | 63 | 46.5 | 14.5 | 4733 |
| 5/5/2021 | 2021 | 5 | 5 | 339 | 40 | 71 | 55.5 | 23.5 | 4756.5 |
| 5/6/2021 | 2021 | 5 | 6 | 340 | 38 | 74 | 56 | 24 | 4780.5 |
| 5/7/2021 | 2021 | 5 | 7 | 341 | 42 | 73 | 57.5 | 25.5 | 4806 |
| 5/8/2021 | 2021 | 5 | 8 | 342 | 38 | 65 | 51.5 | 19.5 | 4825.5 |
| 5/9/2021 | 2021 | 5 | 9 | 343 | 36 | 63 | 49.5 | 17.5 | 4843 |
| 5/10/2021 | 2021 | 5 | 10 | 344 | 37 | 65 | 51 | 19 | 4862 |
| 5/11/2021 | 2021 | 5 | 11 | 345 | 30 | 64 | 47 | 15 | 4877 |
| 5/12/2021 | 2021 | 5 | 12 | 346 | 33 | 68 | 50.5 | 18.5 | 4895.5 |
| 5/13/2021 | 2021 | 5 | 13 | 347 | 34 | 73 | 53.5 | 21.5 | 4917 |
| 5/14/2021 | 2021 | 5 | 14 | 348 | 43 | 73 | 58 | 26 | 4943 |
| 5/15/2021 | 2021 | 5 | 15 | 349 | 41 | 72 | 56.5 | 24.5 | 4967.5 |
| 5/16/2021 | 2021 | 5 | 16 | 350 | 37 | 71 | 54 | 22 | 4989.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/17/2021 | 2021 | 5 | 17 | 351 | 32 | 64 | 48 | 16 | 5005.5 |
| 5/18/2021 | 2021 | 5 | 18 | 352 | 38 | 56 | 47 | 15 | 5020.5 |
| 5/19/2021 | 2021 | 5 | 19 | 353 | 38 | 70 | 54 | 22 | 5042.5 |
| 5/20/2021 | 2021 | 5 | 20 | 354 | 41 | 73 | 57 | 25 | 5067.5 |
| 5/21/2021 | 2021 | 5 | 21 | 355 | 42 | 58 | 50 | 18 | 5085.5 |
| 5/22/2021 | 2021 | 5 | 22 | 356 | 37 | 71 | 54 | 22 | 5107.5 |
| 5/23/2021 | 2021 | 5 | 23 | 357 | 27 | 61 | 44 | 12 | 5119.5 |
| 5/24/2021 | 2021 | 5 | 24 | 358 | 30 | 68 | 49 | 17 | 5136.5 |
| 5/25/2021 | 2021 | 5 | 25 | 359 | 32 | 72 | 52 | 20 | 5156.5 |
| 5/26/2021 | 2021 | 5 | 26 | 360 | 40 | 73 | 56.5 | 24.5 | 5181 |
| 5/27/2021 | 2021 | 5 | 27 | 361 | 37 | 73 | 55 | 23 | 5204 |
| 5/28/2021 | 2021 | 5 | 28 | 362 | 40 | 77 | 58.5 | 26.5 | 5230.5 |
| 5/29/2021 | 2021 | 5 | 29 | 363 | 47 | 76 | 61.5 | 29.5 | 5260 |
| 5/30/2021 | 2021 | 5 | 30 | 364 | 40 | 76 | 58 | 26 | 5286 |
| 5/31/2021 | 2021 | 5 | 31 | 365 | 44 | 68 | 56 | 24 | 5310 |
| 6/1/2021 | 2021 | 6 | 1 | 1 | 40 | 72 | 56 | 24 | 24 |
| 6/2/2021 | 2021 | 6 | 2 | 2 | 45 | 74 | 59.5 | 27.5 | 51.5 |
| 6/3/2021 | 2021 | 6 | 3 | 3 | 45 | 77 | 61 | 29 | 80.5 |
| 6/4/2021 | 2021 | 6 | 4 | 4 | 42 | 81 | 61.5 | 29.5 | 110 |
| 6/5/2021 | 2021 | 6 | 5 | 5 | 50 | 83 | 66.5 | 34.5 | 144.5 |
| 6/6/2021 | 2021 | 6 | 6 | 6 | 53 | 82 | 67.5 | 35.5 | 180 |
| 6/7/2021 | 2021 | 6 | 7 | 7 | 49 | 80 | 64.5 | 32.5 | 212.5 |
| 6/8/2021 | 2021 | 6 | 8 | 8 | 49 | 79 | 64 | 32 | 244.5 |
| 6/9/2021 | 2021 | 6 | 9 | 9 | 45 | 81 | 63 | 31 | 275.5 |
| 6/10/2021 | 2021 | 6 | 10 | 10 | 46 | 82 | 64 | 32 | 307.5 |
| 6/11/2021 | 2021 | 6 | 11 | 11 | 43 | 83 | 63 | 31 | 338.5 |
| 6/12/2021 | 2021 | 6 | 12 | 12 | 44 | 88 | 66 | 34 | 372.5 |
| 6/13/2021 | 2021 | 6 | 13 | 13 | 49 | 90 | 69.5 | 37.5 | 410 |
| 6/14/2021 | 2021 | 6 | 14 | 14 | 52 | 93 | 72.5 | 40.5 | 450.5 |
| 6/15/2021 | 2021 | 6 | 15 | 15 | 58 | 89 | 73.5 | 41.5 | 492 |
| 6/16/2021 | 2021 | 6 | 16 | 16 | 58 | 91 | 74.5 | 42.5 | 534.5 |
| 6/17/2021 | 2021 | 6 | 17 | 17 | 55 | 91 | 73 | 41 | 575.5 |
| 6/18/2021 | 2021 | 6 | 18 | 18 | 53 | 88 | 70.5 | 38.5 | 614 |
| 6/19/2021 | 2021 | 6 | 19 | 19 | 55 | 88 | 71.5 | 39.5 | 653.5 |
| 6/20/2021 | 2021 | 6 | 20 | 20 | 57 | 86 | 71.5 | 39.5 | 693 |
| 6/21/2021 | 2021 | 6 | 21 | 21 | 59 | 88 | 73.5 | 41.5 | 734.5 |
| 6/22/2021 | 2021 | 6 | 22 | 22 | 56 | 85 | 70.5 | 38.5 | 773 |
| 6/23/2021 | 2021 | 6 | 23 | 23 | 48 | 78 | 63 | 31 | 804 |
| 6/24/2021 | 2021 | 6 | 24 | 24 | 47 | 77 | 62 | 30 | 834 |
| 6/25/2021 | 2021 | 6 | 25 | 25 | 49 | 77 | 63 | 31 | 865 |
| 6/26/2021 | 2021 | 6 | 26 | 26 | 45 | 74 | 59.5 | 27.5 | 892.5 |
| 6/27/2021 | 2021 | 6 | 27 | 27 | 49 | 67 | 58 | 26 | 918.5 |
| 6/28/2021 | 2021 | 6 | 28 | 28 | 47 | 63 | 55 | 23 | 941.5 |
| 6/29/2021 | 2021 | 6 | 29 | 29 | 47 | 62 | 54.5 | 22.5 | 964 |
| 6/30/2021 | 2021 | 6 | 30 | 30 | 49 | 67 | 58 | 26 | 990 |
| 7/1/2021 | 2021 | 7 | 1 | 31 | 49 | 74 | 61.5 | 29.5 | 1019.5 |
| 7/2/2021 | 2021 | 7 | 2 | 32 | 52 | 76 | 64 | 32 | 1051.5 |
| 7/3/2021 | 2021 | 7 | 3 | 33 | 49 | 76 | 62.5 | 30.5 | 1082 |
| 7/4/2021 | 2021 | 7 | 4 | 34 | 52 | 82 | 67 | 35 | 1117 |
| 7/5/2021 | 2021 | 7 | 5 | 35 | 52 | 83 | 67.5 | 35.5 | 1152.5 |
| 7/6/2021 | 2021 | 7 | 6 | 36 | 50 | 82 | 66 | 34 | 1186.5 |
| 7/7/2021 | 2021 | 7 | 7 | 37 | 56 | 80 | 68 | 36 | 1222.5 |
| 7/8/2021 | 2021 | 7 | 8 | 38 | 54 | 85 | 69.5 | 37.5 | 1260 |
| 7/9/2021 | 2021 | 7 | 9 | 39 | 59 | 88 | 73.5 | 41.5 | 1301.5 |
| 7/10/2021 | 2021 | 7 | 10 | 40 | 57 | 92 | 74.5 | 42.5 | 1344 |
| 7/11/2021 | 2021 | 7 | 11 | 41 | 60 | 88 | 74 | 42 | 1386 |
| 7/12/2021 | 2021 | 7 | 12 | 42 | 57 | 81 | 69 | 37 | 1423 |
| 7/13/2021 | 2021 | 7 | 13 | 43 | 52 | 83 | 67.5 | 35.5 | 1458.5 |
| 7/14/2021 | 2021 | 7 | 14 | 44 | 52 | 72 | 62 | 30 | 1488.5 |
| 7/15/2021 | 2021 | 7 | 15 | 45 | 51 | 75 | 63 | 31 | 1519.5 |
| 7/16/2021 | 2021 | 7 | 16 | 46 | 52 | 79 | 65.5 | 33.5 | 1553 |
| 7/17/2021 | 2021 | 7 | 17 | 47 | 51 | 76 | 63.5 | 31.5 | 1584.5 |
| 7/18/2021 | 2021 | 7 | 18 | 48 | 52 | 77 | 64.5 | 32.5 | 1617 |
| 7/19/2021 | 2021 | 7 | 19 | 49 | 52 | 78 | 65 | 33 | 1650 |
| 7/20/2021 | 2021 | 7 | 20 | 50 | 54 | 81 | 67.5 | 35.5 | 1685.5 |
| 7/21/2021 | 2021 | 7 | 21 | 51 | 51 | 82 | 66.5 | 34.5 | 1720 |
| 7/22/2021 | 2021 | 7 | 22 | 52 | 54 | 77 | 65.5 | 33.5 | 1753.5 |
| 7/23/2021 | 2021 | 7 | 23 | 53 | 50 | 75 | 62.5 | 30.5 | 1784 |
| 7/24/2021 | 2021 | 7 | 24 | 54 | 48 | 66 | 57 | 25 | 1809 |
| 7/25/2021 | 2021 | 7 | 25 | 55 | 49 | 69 | 59 | 27 | 1836 |
| 7/26/2021 | 2021 | 7 | 26 | 56 | 49 | 74 | 61.5 | 29.5 | 1865.5 |
| 7/27/2021 | 2021 | 7 | 27 | 57 | 51 | 71 | 61 | 29 | 1894.5 |
| 7/28/2021 | 2021 | 7 | 28 | 58 | 52 | 74 | 63 | 31 | 1925.5 |
| 7/29/2021 | 2021 | 7 | 29 | 59 | 51 | 77 | 64 | 32 | 1957.5 |
| 7/30/2021 | 2021 | 7 | 30 | 60 | 50 | 76 | 63 | 31 | 1988.5 |
| 7/31/2021 | 2021 | 7 | 31 | 61 | 49 | 77 | 63 | 31 | 2019.5 |
| 8/1/2021 | 2021 | 8 | 1 | 62 | 49 | 74 | 61.5 | 29.5 | 2049 |
| 8/2/2021 | 2021 | 8 | 2 | 63 | 49 | 70 | 59.5 | 27.5 | 2076.5 |
| 8/3/2021 | 2021 | 8 | 3 | 64 | 49 | 76 | 62.5 | 30.5 | 2107 |
| 8/4/2021 | 2021 | 8 | 4 | 65 | 47 | 79 | 63 | 31 | 2138 |
| 8/5/2021 | 2021 | 8 | 5 | 66 | 51 | 81 | 66 | 34 | 2172 |
| 8/6/2021 | 2021 | 8 | 6 | 67 | 56 | 81 | 68.5 | 36.5 | 2208.5 |
| 8/7/2021 | 2021 | 8 | 7 | 68 | 48 | 78 | 63 | 31 | 2239.5 |
| 8/8/2021 | 2021 | 8 | 8 | 69 | 47 | 81 | 64 | 32 | 2271.5 |
| 8/9/2021 | 2021 | 8 | 9 | 70 | 51 | 79 | 65 | 33 | 2304.5 |
| 8/10/2021 | 2021 | 8 | 10 | 71 | 52 | 76 | 64 | 32 | 2336.5 |
| 8/11/2021 | 2021 | 8 | 11 | 72 | 50 | 74 | 62 | 30 | 2366.5 |
| 8/12/2021 | 2021 | 8 | 12 | 73 | 51 | 77 | 64 | 32 | 2398.5 |
| 8/13/2021 | 2021 | 8 | 13 | 74 | 48 | 76 | 62 | 30 | 2428.5 |
| 8/14/2021 | 2021 | 8 | 14 | 75 | 49 | 69 | 59 | 27 | 2455.5 |
| 8/15/2021 | 2021 | 8 | 15 | 76 | 48 | 78 | 63 | 31 | 2486.5 |
| 8/16/2021 | 2021 | 8 | 16 | 77 | 48 | 74 | 61 | 29 | 2515.5 |
| 8/17/2021 | 2021 | 8 | 17 | 78 | 46 | 76 | 61 | 29 | 2544.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/18/2021 | 2021 | 8 | 18 | 79 | 52 | 71 | 61.5 | 29.5 | 2574 |
| 8/19/2021 | 2021 | 8 | 19 | 80 | 51 | 69 | 60 | 28 | 2602 |
| 8/20/2021 | 2021 | 8 | 20 | 81 | 45 | 70 | 57.5 | 25.5 | 2627.5 |
| 8/21/2021 | 2021 | 8 | 21 | 82 | 45 | 75 | 60 | 28 | 2655.5 |
| 8/22/2021 | 2021 | 8 | 22 | 83 | 46 | 78 | 62 | 30 | 2685.5 |
| 8/23/2021 | 2021 | 8 | 23 | 84 | 48 | 77 | 62.5 | 30.5 | 2716 |
| 8/24/2021 | 2021 | 8 | 24 | 85 | 46 | 78 | 62 | 30 | 2746 |
| 8/25/2021 | 2021 | 8 | 25 | 86 | 48 | 83 | 65.5 | 33.5 | 2779.5 |
| 8/26/2021 | 2021 | 8 | 26 | 87 | 52 | 82 | 67 | 35 | 2814.5 |
| 8/27/2021 | 2021 | 8 | 27 | 88 | 53 | 82 | 67.5 | 35.5 | 2850 |
| 8/28/2021 | 2021 | 8 | 28 | 89 | 51 | 78 | 64.5 | 32.5 | 2882.5 |
| 8/29/2021 | 2021 | 8 | 29 | 90 | 48 | 80 | 64 | 32 | 2914.5 |
| 8/30/2021 | 2021 | 8 | 30 | 91 | 49 | 78 | 63.5 | 31.5 | 2946 |
| 8/31/2021 | 2021 | 8 | 31 | 92 | 49 | 78 | 63.5 | 31.5 | 2977.5 |
| 9/1/2021 | 2021 | 9 | 1 | 93 | 52 | 62 | 57 | 25 | 3002.5 |
| 9/2/2021 | 2021 | 9 | 2 | 94 | 47 | 66 | 56.5 | 24.5 | 3027 |
| 9/3/2021 | 2021 | 9 | 3 | 95 | 46 | 76 | 61 | 29 | 3056 |
| 9/4/2021 | 2021 | 9 | 4 | 96 | 50 | 75 | 62.5 | 30.5 | 3086.5 |
| 9/5/2021 | 2021 | 9 | 5 | 97 | 45 | 77 | 61 | 29 | 3115.5 |
| 9/6/2021 | 2021 | 9 | 6 | 98 | 46 | 80 | 63 | 31 | 3146.5 |
| 9/7/2021 | 2021 | 9 | 7 | 99 | 46 | 82 | 64 | 32 | 3178.5 |
| 9/8/2021 | 2021 | 9 | 8 | 100 | 51 | 82 | 66.5 | 34.5 | 3213 |
| 9/9/2021 | 2021 | 9 | 9 | 101 | 56 | 82 | 69 | 37 | 3250 |
| 9/10/2021 | 2021 | 9 | 10 | 102 | 57 | 82 | 69.5 | 37.5 | 3287.5 |
| 9/11/2021 | 2021 | 9 | 11 | 103 | 51 | 80 | 65.5 | 33.5 | 3321 |
| 9/12/2021 | 2021 | 9 | 12 | 104 | 47 | 81 | 64 | 32 | 3353 |
| 9/13/2021 | 2021 | 9 | 13 | 105 | 49 | 80 | 64.5 | 32.5 | 3385.5 |
| 9/14/2021 | 2021 | 9 | 14 | 106 | 51 | 79 | 65 | 33 | 3418.5 |
| 9/15/2021 | 2021 | 9 | 15 | 107 | 47 | 79 | 63 | 31 | 3449.5 |
| 9/16/2021 | 2021 | 9 | 16 | 108 | 47 | 74 | 60.5 | 28.5 | 3478 |
| 9/17/2021 | 2021 | 9 | 17 | 109 | 46 | 77 | 61.5 | 29.5 | 3507.5 |
| 9/18/2021 | 2021 | 9 | 18 | 110 | 48 | 76 | 62 | 30 | 3537.5 |
| 9/19/2021 | 2021 | 9 | 19 | 111 | 47 | 72 | 59.5 | 27.5 | 3565 |
| 9/20/2021 | 2021 | 9 | 20 | 112 | 39 | 71 | 55 | 23 | 3588 |
| 9/21/2021 | 2021 | 9 | 21 | 113 | 33 | 72 | 52.5 | 20.5 | 3608.5 |
| 9/22/2021 | 2021 | 9 | 22 | 114 | 41 | 74 | 57.5 | 25.5 | 3634 |
| 9/23/2021 | 2021 | 9 | 23 | 115 | 43 | 72 | 57.5 | 25.5 | 3659.5 |
| 9/24/2021 | 2021 | 9 | 24 | 116 | 42 | 71 | 56.5 | 24.5 | 3684 |
| 9/25/2021 | 2021 | 9 | 25 | 117 | 43 | 68 | 55.5 | 23.5 | 3707.5 |
| 9/26/2021 | 2021 | 9 | 26 | 118 | 41 | 61 | 51 | 19 | 3726.5 |
| 9/27/2021 | 2021 | 9 | 27 | 119 | 41 | 53 | 47 | 15 | 3741.5 |
| 9/28/2021 | 2021 | 9 | 28 | 120 | 42 | 56 | 49 | 17 | 3758.5 |
| 9/29/2021 | 2021 | 9 | 29 | 121 | 37 | 59 | 48 | 16 | 3774.5 |
| 9/30/2021 | 2021 | 9 | 30 | 122 | 36 | 46 | 41 | 9 | 3783.5 |
| 10/1/2021 | 2021 | 10 | 1 | 123 | 34 | 44 | 39 | 7 | 3790.5 |
| 10/2/2021 | 2021 | 10 | 2 | 124 | 31 | 57 | 44 | 12 | 3802.5 |
| 10/3/2021 | 2021 | 10 | 3 | 125 | 38 | 62 | 50 | 18 | 3820.5 |
| 10/4/2021 | 2021 | 10 | 4 | 126 | 40 | 65 | 52.5 | 20.5 | 3841 |
| 10/5/2021 | 2021 | 10 | 5 | 127 | 43 | 65 | 54 | 22 | 3863 |
| 10/6/2021 | 2021 | 10 | 6 | 128 | 40 | 60 | 50 | 18 | 3881 |
| 10/7/2021 | 2021 | 10 | 7 | 129 | 38 | 64 | 51 | 19 | 3900 |
| 10/8/2021 | 2021 | 10 | 8 | 130 | 42 | 67 | 54.5 | 22.5 | 3922.5 |
| 10/9/2021 | 2021 | 10 | 9 | 131 | 34 | 59 | 46.5 | 14.5 | 3937 |
| 10/10/2021 | 2021 | 10 | 10 | 132 | 31 | 52 | 41.5 | 9.5 | 3946.5 |
| 10/11/2021 | 2021 | 10 | 11 | 133 | 28 | 59 | 43.5 | 11.5 | 3958 |
| 10/12/2021 | 2021 | 10 | 12 | 134 | 24 | 43 | 33.5 | 1.5 | 3959.5 |
| 10/13/2021 | 2021 | 10 | 13 | 135 | 20 | 45 | 32.5 | 0.5 | 3960 |
| 10/14/2021 | 2021 | 10 | 14 | 136 | 27 | 48 | 37.5 | 5.5 | 3965.5 |
| 10/15/2021 | 2021 | 10 | 15 | 137 | 20 | 49 | 34.5 | 2.5 | 3968 |
| 10/16/2021 | 2021 | 10 | 16 | 138 | 26 | 63 | 44.5 | 12.5 | 3980.5 |
| 10/17/2021 | 2021 | 10 | 17 | 139 | 35 | 62 | 48.5 | 16.5 | 3997 |
| 10/18/2021 | 2021 | 10 | 18 | 140 | 33 | 60 | 46.5 | 14.5 | 4011.5 |
| 10/19/2021 | 2021 | 10 | 19 | 141 | 26 | 51 | 38.5 | 6.5 | 4018 |
| 10/20/2021 | 2021 | 10 | 20 | 142 | 26 | 59 | 42.5 | 10.5 | 4028.5 |
| 10/21/2021 | 2021 | 10 | 21 | 143 | 29 | 62 | 45.5 | 13.5 | 4042 |
| 10/22/2021 | 2021 | 10 | 22 | 144 | 32 | 63 | 47.5 | 15.5 | 4057.5 |
| 10/23/2021 | 2021 | 10 | 23 | 145 | 38 | 56 | 47 | 15 | 4072.5 |
| 10/24/2021 | 2021 | 10 | 24 | 146 | 33 | 58 | 45.5 | 13.5 | 4086 |
| 10/25/2021 | 2021 | 10 | 25 | 147 | 39 | 67 | 53 | 21 | 4107 |
| 10/26/2021 | 2021 | 10 | 26 | 148 | 27 | 49 | 38 | 6 | 4113 |
| 10/27/2021 | 2021 | 10 | 27 | 149 | 25 | 47 | 36 | 4 | 4117 |
| 10/28/2021 | 2021 | 10 | 28 | 150 | 27 | 54 | 40.5 | 8.5 | 4125.5 |
| 10/29/2021 | 2021 | 10 | 29 | 151 | 28 | 64 | 46 | 14 | 4139.5 |
| 10/30/2021 | 2021 | 10 | 30 | 152 | 35 | 63 | 49 | 17 | 4156.5 |
| 10/31/2021 | 2021 | 10 | 31 | 153 | 34 | 59 | 46.5 | 14.5 | 4171 |
| 11/1/2021 | 2021 | 11 | 1 | 154 | 34 | 56 | 45 | 13 | 4184 |
| 11/2/2021 | 2021 | 11 | 2 | 155 | 31 | 55 | 43 | 11 | 4195 |
| 11/3/2021 | 2021 | 11 | 3 | 156 | 27 | 56 | 41.5 | 9.5 | 4204.5 |
| 11/4/2021 | 2021 | 11 | 4 | 157 | 28 | 59 | 43.5 | 11.5 | 4216 |
| 11/5/2021 | 2021 | 11 | 5 | 158 | 32 | 63 | 47.5 | 15.5 | 4231.5 |
| 11/6/2021 | 2021 | 11 | 6 | 159 | 34 | 63 | 48.5 | 16.5 | 4248 |
| 11/7/2021 | 2021 | 11 | 7 | 160 | 37 | 61 | 49 | 17 | 4265 |
| 11/8/2021 | 2021 | 11 | 8 | 161 | 34 | 60 | 47 | 15 | 4280 |
| 11/9/2021 | 2021 | 11 | 9 | 162 | 33 | 54 | 43.5 | 11.5 | 4291.5 |
| 11/10/2021 | 2021 | 11 | 10 | 163 | 31 | 49 | 40 | 8 | 4299.5 |
| 11/11/2021 | 2021 | 11 | 11 | 164 | 24 | 51 | 37.5 | 5.5 | 4305 |
| 11/12/2021 | 2021 | 11 | 12 | 165 | 26 | 55 | 40.5 | 8.5 | 4313.5 |
| 11/13/2021 | 2021 | 11 | 13 | 166 | 27 | 58 | 42.5 | 10.5 | 4324 |
| 11/14/2021 | 2021 | 11 | 14 | 167 | 27 | 59 | 43 | 11 | 4335 |
| 11/15/2021 | 2021 | 11 | 15 | 168 | 33 | 63 | 48 | 16 | 4351 |
| 11/16/2021 | 2021 | 11 | 16 | 169 | 34 | 53 | 43.5 | 11.5 | 4362.5 |
| 11/17/2021 | 2021 | 11 | 17 | 170 | 24 | 53 | 38.5 | 6.5 | 4369 |
| 11/18/2021 | 2021 | 11 | 18 | 171 | 22 | 53 | 37.5 | 5.5 | 4374.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/19/2021 | 2021 | 11 | 19 | 172 | 27 | 53 | 40 | 8 | 4382.5 |
| 11/20/2021 | 2021 | 11 | 20 | 173 | 28 | 52 | 40 | 8 | 4390.5 |
| 11/21/2021 | 2021 | 11 | 21 | 174 | 24 | 47 | 35.5 | 3.5 | 4394 |
| 11/22/2021 | 2021 | 11 | 22 | 175 | 19 | 58 | 38.5 | 6.5 | 4400.5 |
| 11/23/2021 | 2021 | 11 | 23 | 176 | 33 | 49 | 41 | 9 | 4409.5 |
| 11/24/2021 | 2021 | 11 | 24 | 177 | 19 | 39 | 29 | -3 | 4406.5 |
| 11/25/2021 | 2021 | 11 | 25 | 178 | 16 | 40 | 28 | -4 | 4402.5 |
| 11/26/2021 | 2021 | 11 | 26 | 179 | 17 | 50 | 33.5 | 1.5 | 4404 |
| 11/27/2021 | 2021 | 11 | 27 | 180 | 25 | 50 | 37.5 | 5.5 | 4409.5 |
| 11/28/2021 | 2021 | 11 | 28 | 181 | 25 | 53 | 39 | 7 | 4416.5 |
| 11/29/2021 | 2021 | 11 | 29 | 182 | 27 | 58 | 42.5 | 10.5 | 4427 |
| 11/30/2021 | 2021 | 11 | 30 | 183 | 25 | 54 | 39.5 | 7.5 | 4434.5 |
| 12/1/2021 | 2021 | 12 | 1 | 184 | 25 | 58 | 41.5 | 9.5 | 4444 |
| 12/2/2021 | 2021 | 12 | 2 | 185 | 29 | 54 | 41.5 | 9.5 | 4453.5 |
| 12/3/2021 | 2021 | 12 | 3 | 186 | 28 | 53 | 40.5 | 8.5 | 4462 |
| 12/4/2021 | 2021 | 12 | 4 | 187 | 26 | 53 | 39.5 | 7.5 | 4469.5 |
| 12/5/2021 | 2021 | 12 | 5 | 188 | 26 | 53 | 39.5 | 7.5 | 4477 |
| 12/6/2021 | 2021 | 12 | 6 | 189 | 25 | 49 | 37 | 5 | 4482 |
| 12/7/2021 | 2021 | 12 | 7 | 190 | 26 | 42 | 34 | 2 | 4484 |
| 12/8/2021 | 2021 | 12 | 8 | 191 | 25 | 41 | 33 | 1 | 4485 |
| 12/9/2021 | 2021 | 12 | 9 | 192 | 32 | 44 | 38 | 6 | 4491 |
| 12/10/2021 | 2021 | 12 | 10 | 193 | 6 | 32 | 19 | -13 | 4478 |
| 12/11/2021 | 2021 | 12 | 11 | 194 | 2 | 37 | 19.5 | -12.5 | 4465.5 |
| 12/12/2021 | 2021 | 12 | 12 | 195 | 18 | 49 | 33.5 | 1.5 | 4467 |
| 12/13/2021 | 2021 | 12 | 13 | 196 | 24 | 46 | 35 | 3 | 4470 |
| 12/14/2021 | 2021 | 12 | 14 | 197 | 33 | 45 | 39 | 7 | 4477 |
| 12/15/2021 | 2021 | 12 | 15 | 198 | 17 | 39 | 28 | -4 | 4473 |
| 12/16/2021 | 2021 | 12 | 16 | 199 | 15 | 44 | 29.5 | -2.5 | 4470.5 |
| 12/17/2021 | 2021 | 12 | 17 | 200 | 8 | 36 | 22 | -10 | 4460.5 |
| 12/18/2021 | 2021 | 12 | 18 | 201 | 5 | 34 | 19.5 | -12.5 | 4448 |
| 12/19/2021 | 2021 | 12 | 19 | 202 | 9 | 42 | 25.5 | -6.5 | 4441.5 |
| 12/20/2021 | 2021 | 12 | 20 | 203 | 19 | 48 | 33.5 | 1.5 | 4443 |
| 12/21/2021 | 2021 | 12 | 21 | 204 | 27 | 45 | 36 | 4 | 4447 |
| 12/22/2021 | 2021 | 12 | 22 | 205 | 26 | 50 | 38 | 6 | 4453 |
| 12/23/2021 | 2021 | 12 | 23 | 206 | 35 | 47 | 41 | 9 | 4462 |
| 12/24/2021 | 2021 | 12 | 24 | 207 | 30 | 39 | 34.5 | 2.5 | 4464.5 |
| 12/25/2021 | 2021 | 12 | 25 | 208 | 31 | 35 | 33 | 1 | 4465.5 |
| 12/26/2021 | 2021 | 12 | 26 | 209 | 23 | 35 | 29 | -3 | 4462.5 |
| 12/27/2021 | 2021 | 12 | 27 | 210 | 23 | 33 | 28 | -4 | 4458.5 |
| 12/28/2021 | 2021 | 12 | 28 | 211 | 21 | 27 | 24 | -8 | 4450.5 |
| 12/29/2021 | 2021 | 12 | 29 | 212 | 21 | 25 | 23 | -9 | 4441.5 |
| 12/30/2021 | 2021 | 12 | 30 | 213 | 22 | 30 | 26 | -6 | 4435.5 |
| 12/31/2021 | 2021 | 12 | 31 | 214 | 25 | 34 | 29.5 | -2.5 | 4433 |
| 1/1/2022 | 2022 | 1 | 1 | 215 | -2 | 29 | 13.5 | -18.5 | 4414.5 |
| 1/2/2022 | 2022 | 1 | 2 | 216 | -5 | 35 | 15 | -17 | 4397.5 |
| 1/3/2022 | 2022 | 1 | 3 | 217 | 10 | 44 | 27 | -5 | 4392.5 |
| 1/4/2022 | 2022 | 1 | 4 | 218 | 22 | 42 | 32 | 0 | 4392.5 |
| 1/5/2022 | 2022 | 1 | 5 | 219 | 23 | 43 | 33 | 1 | 4393.5 |
| 1/6/2022 | 2022 | 1 | 6 | 220 | 28 | 48 | 38 | 6 | 4399.5 |
| 1/7/2022 | 2022 | 1 | 7 | 221 | 26 | 48 | 37 | 5 | 4404.5 |
| 1/8/2022 | 2022 | 1 | 8 | 222 | 20 | 39 | 29.5 | -2.5 | 4402 |
| 1/9/2022 | 2022 | 1 | 9 | 223 | 11 | 38 | 24.5 | -7.5 | 4394.5 |
| 1/10/2022 | 2022 | 1 | 10 | 224 | 10 | 41 | 25.5 | -6.5 | 4388 |
| 1/11/2022 | 2022 | 1 | 11 | 225 | 11 | 46 | 28.5 | -3.5 | 4384.5 |
| 1/12/2022 | 2022 | 1 | 12 | 226 | 14 | 49 | 31.5 | -0.5 | 4384 |
| 1/13/2022 | 2022 | 1 | 13 | 227 | 22 | 54 | 38 | 6 | 4390 |
| 1/14/2022 | 2022 | 1 | 14 | 228 | 22 | 44 | 33 | 1 | 4391 |
| 1/15/2022 | 2022 | 1 | 15 | 229 | 14 | 44 | 29 | -3 | 4388 |
| 1/16/2022 | 2022 | 1 | 16 | 230 | 17 | 49 | 33 | 1 | 4389 |
| 1/17/2022 | 2022 | 1 | 17 | 231 | 16 | 47 | 31.5 | -0.5 | 4388.5 |
| 1/18/2022 | 2022 | 1 | 18 | 232 | 27 | 40 | 33.5 | 1.5 | 4390 |
| 1/19/2022 | 2022 | 1 | 19 | 233 | 17 | 37 | 27 | -5 | 4385 |
| 1/20/2022 | 2022 | 1 | 20 | 234 | 13 | 37 | 25 | -7 | 4378 |
| 1/21/2022 | 2022 | 1 | 21 | 235 | 15 | 41 | 28 | -4 | 4374 |
| 1/22/2022 | 2022 | 1 | 22 | 236 | 19 | 37 | 28 | -4 | 4370 |
| 1/23/2022 | 2022 | 1 | 23 | 237 | 16 | 42 | 29 | -3 | 4367 |
| 1/24/2022 | 2022 | 1 | 24 | 238 | 18 | 44 | 31 | -1 | 4366 |
| 1/25/2022 | 2022 | 1 | 25 | 239 | 20 | 41 | 30.5 | -1.5 | 4364.5 |
| 1/26/2022 | 2022 | 1 | 26 | 240 | 8 | 33 | 20.5 | -11.5 | 4353 |
| 1/27/2022 | 2022 | 1 | 27 | 241 | 6 | 37 | 21.5 | -10.5 | 4342.5 |
| 1/28/2022 | 2022 | 1 | 28 | 242 | 6 | 38 | 22 | -10 | 4332.5 |
| 1/29/2022 | 2022 | 1 | 29 | 243 | 10 | 47 | 28.5 | -3.5 | 4329 |
| 1/30/2022 | 2022 | 1 | 30 | 244 | 21 | 38 | 29.5 | -2.5 | 4326.5 |
| 1/31/2022 | 2022 | 1 | 31 | 245 | 17 | 46 | 31.5 | -0.5 | 4326 |
| 2/1/2022 | 2022 | 2 | 1 | 246 | 24 | 42 | 33 | 1 | 4327 |
| 2/2/2022 | 2022 | 2 | 2 | 247 | 0 | 28 | 14 | -18 | 4309 |
| 2/3/2022 | 2022 | 2 | 3 | 248 | -8 | 20 | 6 | -26 | 4283 |
| 2/4/2022 | 2022 | 2 | 4 | 249 | -4 | 36 | 16 | -16 | 4267 |
| 2/5/2022 | 2022 | 2 | 5 | 250 | 5 | 44 | 24.5 | -7.5 | 4259.5 |
| 2/6/2022 | 2022 | 2 | 6 | 251 | 8 | 33 | 20.5 | -11.5 | 4248 |
| 2/7/2022 | 2022 | 2 | 7 | 252 | 8 | 39 | 23.5 | -8.5 | 4239.5 |
| 2/8/2022 | 2022 | 2 | 8 | 253 | 12 | 44 | 28 | -4 | 4235.5 |
| 2/9/2022 | 2022 | 2 | 9 | 254 | 15 | 47 | 31 | -1 | 4234.5 |
| 2/10/2022 | 2022 | 2 | 10 | 255 | 15 | 49 | 32 | 0 | 4234.5 |
| 2/11/2022 | 2022 | 2 | 11 | 256 | 22 | 50 | 36 | 4 | 4238.5 |
| 2/12/2022 | 2022 | 2 | 12 | 257 | 19 | 44 | 31.5 | -0.5 | 4238 |
| 2/13/2022 | 2022 | 2 | 13 | 258 | 17 | 50 | 33.5 | 1.5 | 4239.5 |
| 2/14/2022 | 2022 | 2 | 14 | 259 | 20 | 51 | 35.5 | 3.5 | 4243 |
| 2/15/2022 | 2022 | 2 | 15 | 260 | 26 | 50 | 38 | 6 | 4249 |
| 2/16/2022 | 2022 | 2 | 16 | 261 | 21 | 41 | 31 | -1 | 4248 |
| 2/17/2022 | 2022 | 2 | 17 | 262 | 10 | 27 | 18.5 | -13.5 | 4234.5 |
| 2/18/2022 | 2022 | 2 | 18 | 263 | 9 | 41 | 25 | -7 | 4227.5 |
| 2/19/2022 | 2022 | 2 | 19 | 264 | 10 | 48 | 29 | -3 | 4224.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/20/2022 | 2022 | 2 | 20 | 265 | 22 | 50 | 36 | 4 | 4228.5 |
| 2/21/2022 | 2022 | 2 | 21 | 266 | 26 | 41 | 33.5 | 1.5 | 4230 |
| 2/22/2022 | 2022 | 2 | 22 | 267 | 24 | 40 | 32 | 0 | 4230 |
| 2/23/2022 | 2022 | 2 | 23 | 268 | 13 | 39 | 26 | -6 | 4224 |
| 2/24/2022 | 2022 | 2 | 24 | 269 | 6 | 26 | 16 | -16 | 4208 |
| 2/25/2022 | 2022 | 2 | 25 | 270 | 3 | 40 | 21.5 | -10.5 | 4197.5 |
| 2/26/2022 | 2022 | 2 | 26 | 271 | 5 | 38 | 21.5 | -10.5 | 4187 |
| 2/27/2022 | 2022 | 2 | 27 | 272 | 5 | 45 | 25 | -7 | 4180 |
| 2/28/2022 | 2022 | 2 | 28 | 273 | 21 | 53 | 37 | 5 | 4185 |
| 3/1/2022 | 2022 | 3 | 1 | 274 | 19 | 57 | 38 | 6 | 4191 |
| 3/2/2022 | 2022 | 3 | 2 | 275 | 23 | 59 | 41 | 9 | 4200 |
| 3/3/2022 | 2022 | 3 | 3 | 276 | 28 | 59 | 43.5 | 11.5 | 4211.5 |
| 3/4/2022 | 2022 | 3 | 4 | 277 | 26 | 53 | 39.5 | 7.5 | 4219 |
| 3/5/2022 | 2022 | 3 | 5 | 278 | 25 | 41 | 33 | 1 | 4220 |
| 3/6/2022 | 2022 | 3 | 6 | 279 | 16 | 29 | 22.5 | -9.5 | 4210.5 |
| 3/7/2022 | 2022 | 3 | 7 | 280 | 14 | 34 | 24 | -8 | 4202.5 |
| 3/8/2022 | 2022 | 3 | 8 | 281 | 3 | 33 | 18 | -14 | 4188.5 |
| 3/9/2022 | 2022 | 3 | 9 | 282 | 11 | 40 | 25.5 | -6.5 | 4182 |
| 3/10/2022 | 2022 | 3 | 10 | 283 | 16 | 43 | 29.5 | -2.5 | 4179.5 |
| 3/11/2022 | 2022 | 3 | 11 | 284 | 3 | 31 | 17 | -15 | 4164.5 |
| 3/12/2022 | 2022 | 3 | 12 | 285 | 9 | 47 | 28 | -4 | 4160.5 |
| 3/13/2022 | 2022 | 3 | 13 | 286 | 20 | 50 | 35 | 3 | 4163.5 |
| 3/14/2022 | 2022 | 3 | 14 | 287 | 21 | 46 | 33.5 | 1.5 | 4165 |
| 3/15/2022 | 2022 | 3 | 15 | 288 | 20 | 57 | 38.5 | 6.5 | 4171.5 |
| 3/16/2022 | 2022 | 3 | 16 | 289 | 28 | 54 | 41 | 9 | 4180.5 |
| 3/17/2022 | 2022 | 3 | 17 | 290 | 20 | 41 | 30.5 | -1.5 | 4179 |
| 3/18/2022 | 2022 | 3 | 18 | 291 | 16 | 49 | 32.5 | 0.5 | 4179.5 |
| 3/19/2022 | 2022 | 3 | 19 | 292 | 20 | 53 | 36.5 | 4.5 | 4184 |
| 3/20/2022 | 2022 | 3 | 20 | 293 | 26 | 55 | 40.5 | 8.5 | 4192.5 |
| 3/21/2022 | 2022 | 3 | 21 | 294 | 26 | 40 | 33 | 1 | 4193.5 |
| 3/22/2022 | 2022 | 3 | 22 | 295 | 22 | 43 | 32.5 | 0.5 | 4194 |
| 3/23/2022 | 2022 | 3 | 23 | 296 | 16 | 44 | 30 | -2 | 4192 |
| 3/24/2022 | 2022 | 3 | 24 | 297 | 27 | 57 | 42 | 10 | 4202 |
| 3/25/2022 | 2022 | 3 | 25 | 298 | 29 | 61 | 45 | 13 | 4215 |
| 3/26/2022 | 2022 | 3 | 26 | 299 | 31 | 65 | 48 | 16 | 4231 |
| 3/27/2022 | 2022 | 3 | 27 | 300 | 35 | 65 | 50 | 18 | 4249 |
| 3/28/2022 | 2022 | 3 | 28 | 301 | 37 | 55 | 46 | 14 | 4263 |
| 3/29/2022 | 2022 | 3 | 29 | 302 | 28 | 37 | 32.5 | 0.5 | 4263.5 |
| 3/30/2022 | 2022 | 3 | 30 | 303 | 29 | 44 | 36.5 | 4.5 | 4268 |
| 3/31/2022 | 2022 | 3 | 31 | 304 | 29 | 50 | 39.5 | 7.5 | 4275.5 |
| 4/1/2022 | 2022 | 4 | 1 | 305 | 29 | 52 | 40.5 | 8.5 | 4284 |
| 4/2/2022 | 2022 | 4 | 2 | 306 | 30 | 59 | 44.5 | 12.5 | 4296.5 |
| 4/3/2022 | 2022 | 4 | 3 | 307 | 31 | 57 | 44 | 12 | 4308.5 |
| 4/4/2022 | 2022 | 4 | 4 | 308 | 30 | 57 | 43.5 | 11.5 | 4320 |
| 4/5/2022 | 2022 | 4 | 5 | 309 | 35 | 63 | 49 | 17 | 4337 |
| 4/6/2022 | 2022 | 4 | 6 | 310 | 26 | 52 | 39 | 7 | 4344 |
| 4/7/2022 | 2022 | 4 | 7 | 311 | 22 | 54 | 38 | 6 | 4350 |
| 4/8/2022 | 2022 | 4 | 8 | 312 | 24 | 63 | 43.5 | 11.5 | 4361.5 |
| 4/9/2022 | 2022 | 4 | 9 | 313 | 31 | 65 | 48 | 16 | 4377.5 |
| 4/10/2022 | 2022 | 4 | 10 | 314 | 31 | 58 | 44.5 | 12.5 | 4390 |
| 4/11/2022 | 2022 | 4 | 11 | 315 | 32 | 58 | 45 | 13 | 4403 |
| 4/12/2022 | 2022 | 4 | 12 | 316 | 22 | 42 | 32 | 0 | 4403 |
| 4/13/2022 | 2022 | 4 | 13 | 317 | 14 | 42 | 28 | -4 | 4399 |
| 4/14/2022 | 2022 | 4 | 14 | 318 | 22 | 54 | 38 | 6 | 4405 |
| 4/15/2022 | 2022 | 4 | 15 | 319 | 36 | 60 | 48 | 16 | 4421 |
| 4/16/2022 | 2022 | 4 | 16 | 320 | 36 | 63 | 49.5 | 17.5 | 4438.5 |
| 4/17/2022 | 2022 | 4 | 17 | 321 | 33 | 64 | 48.5 | 16.5 | 4455 |
| 4/18/2022 | 2022 | 4 | 18 | 322 | 32 | 69 | 50.5 | 18.5 | 4473.5 |
| 4/19/2022 | 2022 | 4 | 19 | 323 | 38 | 65 | 51.5 | 19.5 | 4493 |
| 4/20/2022 | 2022 | 4 | 20 | 324 | 43 | 71 | 57 | 25 | 4518 |
| 4/21/2022 | 2022 | 4 | 21 | 325 | 38 | 69 | 53.5 | 21.5 | 4539.5 |
| 4/22/2022 | 2022 | 4 | 22 | 326 | 30 | 65 | 47.5 | 15.5 | 4555 |
| 4/23/2022 | 2022 | 4 | 23 | 327 | 25 | 50 | 37.5 | 5.5 | 4560.5 |
| 4/24/2022 | 2022 | 4 | 24 | 328 | 22 | 52 | 37 | 5 | 4565.5 |
| 4/25/2022 | 2022 | 4 | 25 | 329 | 22 | 59 | 40.5 | 8.5 | 4574 |
| 4/26/2022 | 2022 | 4 | 26 | 330 | 33 | 66 | 49.5 | 17.5 | 4591.5 |
| 4/27/2022 | 2022 | 4 | 27 | 331 | 39 | 68 | 53.5 | 21.5 | 4613 |
| 4/28/2022 | 2022 | 4 | 28 | 332 | 35 | 65 | 50 | 18 | 4631 |
| 4/29/2022 | 2022 | 4 | 29 | 333 | 33 | 63 | 48 | 16 | 4647 |
| 4/30/2022 | 2022 | 4 | 30 | 334 | 27 | 65 | 46 | 14 | 4661 |
| 5/1/2022 | 2022 | 5 | 1 | 335 | 35 | 67 | 51 | 19 | 4680 |
| 5/2/2022 | 2022 | 5 | 2 | 336 | 38 | 63 | 50.5 | 18.5 | 4698.5 |
| 5/3/2022 | 2022 | 5 | 3 | 337 | 34 | 66 | 50 | 18 | 4716.5 |
| 5/4/2022 | 2022 | 5 | 4 | 338 | 26 | 54 | 40 | 8 | 4724.5 |
| 5/5/2022 | 2022 | 5 | 5 | 339 | 27 | 64 | 45.5 | 13.5 | 4738 |
| 5/6/2022 | 2022 | 5 | 6 | 340 | 39 | 71 | 55 | 23 | 4761 |
| 5/7/2022 | 2022 | 5 | 7 | 341 | 49 | 72 | 60.5 | 28.5 | 4789.5 |
| 5/8/2022 | 2022 | 5 | 8 | 342 | 46 | 67 | 56.5 | 24.5 | 4814 |
| 5/9/2022 | 2022 | 5 | 9 | 343 | 42 | | 42 | 10 | 4824 |
| 5/10/2022 | 2022 | 5 | 10 | 344 | 42 | 72 | 57 | 25 | 4849 |
| 5/11/2022 | 2022 | 5 | 11 | 345 | 40 | 71 | 55.5 | 23.5 | 4872.5 |
| 5/12/2022 | 2022 | 5 | 12 | 346 | 31 | 63 | 47 | 15 | 4887.5 |
| 5/13/2022 | 2022 | 5 | 13 | 347 | 30 | 69 | 49.5 | 17.5 | 4905 |
| 5/14/2022 | 2022 | 5 | 14 | 348 | 34 | 76 | 55 | 23 | 4928 |
| 5/15/2022 | 2022 | 5 | 15 | 349 | 40 | 80 | 60 | 28 | 4956 |
| 5/16/2022 | 2022 | 5 | 16 | 350 | 48 | 78 | 63 | 31 | 4987 |
| 5/17/2022 | 2022 | 5 | 17 | 351 | 42 | 75 | 58.5 | 26.5 | 5013.5 |
| 5/18/2022 | 2022 | 5 | 18 | 352 | 48 | 76 | 62 | 30 | 5043.5 |
| 5/19/2022 | 2022 | 5 | 19 | 353 | 47 | 76 | 61.5 | 29.5 | 5073 |
| 5/20/2022 | 2022 | 5 | 20 | 354 | 45 | 69 | 57 | 25 | 5098 |
| 5/21/2022 | 2022 | 5 | 21 | 355 | 45 | 69 | 57 | 25 | 5123 |
| 5/22/2022 | 2022 | 5 | 22 | 356 | 39 | 71 | 55 | 23 | 5146 |
| 5/23/2022 | 2022 | 5 | 23 | 357 | 35 | 64 | 49.5 | 17.5 | 5163.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/24/2022 | 2022 | 5 | 24 | 358 | 34 | 61 | 47.5 | 15.5 | 5179 |
| 5/25/2022 | 2022 | 5 | 25 | 359 | 36 | 70 | 53 | 21 | 5200 |
| 5/26/2022 | 2022 | 5 | 26 | 360 | 41 | 78 | 59.5 | 27.5 | 5227.5 |
| 5/27/2022 | 2022 | 5 | 27 | 361 | 45 | 79 | 62 | 30 | 5257.5 |
| 5/28/2022 | 2022 | 5 | 28 | 362 | 46 | 75 | 60.5 | 28.5 | 5286 |
| 5/29/2022 | 2022 | 5 | 29 | 363 | 46 | 69 | 57.5 | 25.5 | 5311.5 |
| 5/30/2022 | 2022 | 5 | 30 | 364 | 42 | 65 | 53.5 | 21.5 | 5333 |
| 5/31/2022 | 2022 | 5 | 31 | 365 | 32 | 70 | 51 | 19 | 5352 |
| 6/1/2022 | 2022 | 6 | 1 | 1 | 36 | 74 | 55 | 23 | 23 |
| 6/2/2022 | 2022 | 6 | 2 | 2 | 39 | 76 | 57.5 | 25.5 | 48.5 |
| 6/3/2022 | 2022 | 6 | 3 | 3 | 41 | 76 | 58.5 | 26.5 | 75 |
| 6/4/2022 | 2022 | 6 | 4 | 4 | 43 | 74 | 58.5 | 26.5 | 101.5 |
| 6/5/2022 | 2022 | 6 | 5 | 5 | 50 | 76 | 63 | 31 | 132.5 |
| 6/6/2022 | 2022 | 6 | 6 | 6 | 50 | 80 | 65 | 33 | 165.5 |
| 6/7/2022 | 2022 | 6 | 7 | 7 | 53 | 81 | 67 | 35 | 200.5 |
| 6/8/2022 | 2022 | 6 | 8 | 8 | 50 | 84 | 67 | 35 | 235.5 |
| 6/9/2022 | 2022 | 6 | 9 | 9 | 56 | 83 | 69.5 | 37.5 | 273 |
| 6/10/2022 | 2022 | 6 | 10 | 10 | 51 | 87 | 69 | 37 | 310 |
| 6/11/2022 | 2022 | 6 | 11 | 11 | 54 | 86 | 70 | 38 | 348 |
| 6/12/2022 | 2022 | 6 | 12 | 12 | 54 | 82 | 68 | 36 | 384 |
| 6/13/2022 | 2022 | 6 | 13 | 13 | 53 | 80 | 66.5 | 34.5 | 418.5 |
| 6/14/2022 | 2022 | 6 | 14 | 14 | 54 | 77 | 65.5 | 33.5 | 452 |
| 6/15/2022 | 2022 | 6 | 15 | 15 | 47 | 82 | 64.5 | 32.5 | 484.5 |
| 6/16/2022 | 2022 | 6 | 16 | 16 | 47 | 86 | 66.5 | 34.5 | 519 |
| 6/17/2022 | 2022 | 6 | 17 | 17 | 53 | 82 | 67.5 | 35.5 | 554.5 |
| 6/18/2022 | 2022 | 6 | 18 | 18 | 48 | 74 | 61 | 29 | 583.5 |
| 6/19/2022 | 2022 | 6 | 19 | 19 | 47 | 68 | 57.5 | 25.5 | 609 |
| 6/20/2022 | 2022 | 6 | 20 | 20 | 46 | 72 | 59 | 27 | 636 |
| 6/21/2022 | 2022 | 6 | 21 | 21 | 49 | 74 | 61.5 | 29.5 | 665.5 |
| 6/22/2022 | 2022 | 6 | 22 | 22 | 50 | 66 | 58 | 26 | 691.5 |
| 6/23/2022 | 2022 | 6 | 23 | 23 | 47 | 75 | 61 | 29 | 720.5 |
| 6/24/2022 | 2022 | 6 | 24 | 24 | 52 | 74 | 63 | 31 | 751.5 |
| 6/25/2022 | 2022 | 6 | 25 | 25 | 51 | 69 | 60 | 28 | 779.5 |
| 6/26/2022 | 2022 | 6 | 26 | 26 | 49 | 65 | 57 | 25 | 804.5 |
| 6/27/2022 | 2022 | 6 | 27 | 27 | 45 | 63 | 54 | 22 | 826.5 |
| 6/28/2022 | 2022 | 6 | 28 | 28 | 44 | 74 | 59 | 27 | 853.5 |
| 6/29/2022 | 2022 | 6 | 29 | 29 | 50 | 77 | 63.5 | 31.5 | 885 |
| 6/30/2022 | 2022 | 6 | 30 | 30 | 51 | 74 | 62.5 | 30.5 | 915.5 |
| 7/1/2022 | 2022 | 7 | 1 | 31 | 51 | 73 | 62 | 30 | 945.5 |
| 7/2/2022 | 2022 | 7 | 2 | 32 | 48 | 73 | 60.5 | 28.5 | 974 |
| 7/3/2022 | 2022 | 7 | 3 | 33 | 51 | 73 | 62 | 30 | 1004 |
| 7/4/2022 | 2022 | 7 | 4 | 34 | 50 | 74 | 62 | 30 | 1034 |
| 7/5/2022 | 2022 | 7 | 5 | 35 | 49 | 73 | 61 | 29 | 1063 |
| 7/6/2022 | 2022 | 7 | 6 | 36 | 48 | 76 | 62 | 30 | 1093 |
| 7/7/2022 | 2022 | 7 | 7 | 37 | 47 | 78 | 62.5 | 30.5 | 1123.5 |
| 7/8/2022 | 2022 | 7 | 8 | 38 | 48 | 83 | 65.5 | 33.5 | 1157 |
| 7/9/2022 | 2022 | 7 | 9 | 39 | 51 | 80 | 65.5 | 33.5 | 1190.5 |
| 7/10/2022 | 2022 | 7 | 10 | 40 | 50 | 81 | 65.5 | 33.5 | 1224 |
| 7/11/2022 | 2022 | 7 | 11 | 41 | 51 | 80 | 65.5 | 33.5 | 1257.5 |
| 7/12/2022 | 2022 | 7 | 12 | 42 | 56 | 77 | 66.5 | 34.5 | 1292 |
| 7/13/2022 | 2022 | 7 | 13 | 43 | 54 | 78 | 66 | 34 | 1326 |
| 7/14/2022 | 2022 | 7 | 14 | 44 | 51 | 80 | 65.5 | 33.5 | 1359.5 |
| 7/15/2022 | 2022 | 7 | 15 | 45 | 52 | 81 | 66.5 | 34.5 | 1394 |
| 7/16/2022 | 2022 | 7 | 16 | 46 | 52 | 83 | 67.5 | 35.5 | 1429.5 |
| 7/17/2022 | 2022 | 7 | 17 | 47 | 53 | 84 | 68.5 | 36.5 | 1466 |
| 7/18/2022 | 2022 | 7 | 18 | 48 | 52 | 83 | 67.5 | 35.5 | 1501.5 |
| 7/19/2022 | 2022 | 7 | 19 | 49 | 51 | 84 | 67.5 | 35.5 | 1537 |
| 7/20/2022 | 2022 | 7 | 20 | 50 | 57 | 84 | 70.5 | 38.5 | 1575.5 |
| 7/21/2022 | 2022 | 7 | 21 | 51 | 54 | 87 | 70.5 | 38.5 | 1614 |
| 7/22/2022 | 2022 | 7 | 22 | 52 | 55 | 85 | 70 | 38 | 1652 |
| 7/23/2022 | 2022 | 7 | 23 | 53 | 53 | 84 | 68.5 | 36.5 | 1688.5 |
| 7/24/2022 | 2022 | 7 | 24 | 54 | 53 | 81 | 67 | 35 | 1723.5 |
| 7/25/2022 | 2022 | 7 | 25 | 55 | 51 | 77 | 64 | 32 | 1755.5 |
| 7/26/2022 | 2022 | 7 | 26 | 56 | 51 | 74 | 62.5 | 30.5 | 1786 |
| 7/27/2022 | 2022 | 7 | 27 | 57 | 49 | 77 | 63 | 31 | 1817 |
| 7/28/2022 | 2022 | 7 | 28 | 58 | 48 | 72 | 60 | 28 | 1845 |
| 7/29/2022 | 2022 | 7 | 29 | 59 | 50 | 72 | 61 | 29 | 1874 |
| 7/30/2022 | 2022 | 7 | 30 | 60 | 50 | 71 | 60.5 | 28.5 | 1902.5 |
| 7/31/2022 | 2022 | 7 | 31 | 61 | 48 | 73 | 60.5 | 28.5 | 1931 |
| 8/1/2022 | 2022 | 8 | 1 | 62 | 55 | 78 | 66.5 | 34.5 | 1965.5 |
| 8/2/2022 | 2022 | 8 | 2 | 63 | 53 | 80 | 66.5 | 34.5 | 2000 |
| 8/3/2022 | 2022 | 8 | 3 | 64 | 52 | 81 | 66.5 | 34.5 | 2034.5 |
| 8/4/2022 | 2022 | 8 | 4 | 65 | 54 | 77 | 65.5 | 33.5 | 2068 |
| 8/5/2022 | 2022 | 8 | 5 | 66 | 53 | 79 | 66 | 34 | 2102 |
| 8/6/2022 | 2022 | 8 | 6 | 67 | 53 | 79 | 66 | 34 | 2136 |
| 8/7/2022 | 2022 | 8 | 7 | 68 | 54 | 72 | 63 | 31 | 2167 |
| 8/8/2022 | 2022 | 8 | 8 | 69 | 54 | 72 | 63 | 31 | 2198 |
| 8/9/2022 | 2022 | 8 | 9 | 70 | 50 | 78 | 64 | 32 | 2230 |
| 8/10/2022 | 2022 | 8 | 10 | 71 | 50 | 77 | 63.5 | 31.5 | 2261.5 |
| 8/11/2022 | 2022 | 8 | 11 | 72 | 50 | 71 | 60.5 | 28.5 | 2290 |
| 8/12/2022 | 2022 | 8 | 12 | 73 | 48 | 76 | 62 | 30 | 2320 |
| 8/13/2022 | 2022 | 8 | 13 | 74 | 49 | 76 | 62.5 | 30.5 | 2350.5 |
| 8/14/2022 | 2022 | 8 | 14 | 75 | 48 | 74 | 61 | 29 | 2379.5 |
| 8/15/2022 | 2022 | 8 | 15 | 76 | 49 | 75 | 62 | 30 | 2409.5 |
| 8/16/2022 | 2022 | 8 | 16 | 77 | 47 | 74 | 60.5 | 28.5 | 2438 |
| 8/17/2022 | 2022 | 8 | 17 | 78 | 49 | 73 | 61 | 29 | 2467 |
| 8/18/2022 | 2022 | 8 | 18 | 79 | 50 | 69 | 59.5 | 27.5 | 2494.5 |
| 8/19/2022 | 2022 | 8 | 19 | 80 | 51 | 62 | 56.5 | 24.5 | 2519 |
| 8/20/2022 | 2022 | 8 | 20 | 81 | 48 | 56 | 52 | 20 | 2539 |
| 8/21/2022 | 2022 | 8 | 21 | 82 | 44 | 69 | 56.5 | 24.5 | 2563.5 |
| 8/22/2022 | 2022 | 8 | 22 | 83 | 48 | 73 | 60.5 | 28.5 | 2592 |
| 8/23/2022 | 2022 | 8 | 23 | 84 | 47 | 70 | 58.5 | 26.5 | 2618.5 |
| 8/24/2022 | 2022 | 8 | 24 | 85 | 49 | 70 | 59.5 | 27.5 | 2646 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 8/25/2022 | 2022 | 8 | 25 | 86 | 51 | 69 | 60 | 28 | 2674 |
| 8/26/2022 | 2022 | 8 | 26 | 87 | 50 | 70 | 60 | 28 | 2702 |
| 8/27/2022 | 2022 | 8 | 27 | 88 | 50 | 70 | 60 | 28 | 2730 |
| 8/28/2022 | 2022 | 8 | 28 | 89 | 47 | 73 | 60 | 28 | 2758 |
| 8/29/2022 | 2022 | 8 | 29 | 90 | 46 | 76 | 61 | 29 | 2787 |
| 8/30/2022 | 2022 | 8 | 30 | 91 | 54 | 75 | 64.5 | 32.5 | 2819.5 |
| 8/31/2022 | 2022 | 8 | 31 | 92 | 51 | 75 | 63 | 31 | 2850.5 |
| 9/1/2022 | 2022 | 9 | 1 | 93 | 51 | 76 | 63.5 | 31.5 | 2882 |
| 9/2/2022 | 2022 | 9 | 2 | 94 | 51 | 81 | 66 | 34 | 2916 |
| 9/3/2022 | 2022 | 9 | 3 | 95 | 48 | 75 | 61.5 | 29.5 | 2945.5 |
| 9/4/2022 | 2022 | 9 | 4 | 96 | 49 | 74 | 61.5 | 29.5 | 2975 |
| 9/5/2022 | 2022 | 9 | 5 | 97 | 48 | 82 | 65 | 33 | 3008 |
| 9/6/2022 | 2022 | 9 | 6 | 98 | 50 | 80 | 65 | 33 | 3041 |
| 9/7/2022 | 2022 | 9 | 7 | 99 | 49 | 80 | 64.5 | 32.5 | 3073.5 |
| 9/8/2022 | 2022 | 9 | 8 | 100 | 54 | 79 | 66.5 | 34.5 | 3108 |
| 9/9/2022 | 2022 | 9 | 9 | 101 | 50 | 76 | 63 | 31 | 3139 |
| 9/10/2022 | 2022 | 9 | 10 | 102 | 48 | 73 | 60.5 | 28.5 | 3167.5 |
| 9/11/2022 | 2022 | 9 | 11 | 103 | 44 | 71 | 57.5 | 25.5 | 3193 |
| 9/12/2022 | 2022 | 9 | 12 | 104 | 44 | 70 | 57 | 25 | 3218 |
| 9/13/2022 | 2022 | 9 | 13 | 105 | 46 | 65 | 55.5 | 23.5 | 3241.5 |
| 9/14/2022 | 2022 | 9 | 14 | 106 | 44 | 64 | 54 | 22 | 3263.5 |
| 9/15/2022 | 2022 | 9 | 15 | 107 | 42 | 66 | 54 | 22 | 3285.5 |
| 9/16/2022 | 2022 | 9 | 16 | 108 | 43 | 70 | 56.5 | 24.5 | 3310 |
| 9/17/2022 | 2022 | 9 | 17 | 109 | 42 | 72 | 57 | 25 | 3335 |
| 9/18/2022 | 2022 | 9 | 18 | 110 | 43 | 72 | 57.5 | 25.5 | 3360.5 |
| 9/19/2022 | 2022 | 9 | 19 | 111 | 47 | 72 | 59.5 | 27.5 | 3388 |
| 9/20/2022 | 2022 | 9 | 20 | 112 | 51 | 73 | 62 | 30 | 3418 |
| 9/21/2022 | 2022 | 9 | 21 | 113 | 49 | 67 | 58 | 26 | 3444 |
| 9/22/2022 | 2022 | 9 | 22 | 114 | 48 | 71 | 59.5 | 27.5 | 3471.5 |
| 9/23/2022 | 2022 | 9 | 23 | 115 | 45 | 67 | 56 | 24 | 3495.5 |
| 9/24/2022 | 2022 | 9 | 24 | 116 | 38 | 68 | 53 | 21 | 3516.5 |
| 9/25/2022 | 2022 | 9 | 25 | 117 | 37 | 69 | 53 | 21 | 3537.5 |
| 9/26/2022 | 2022 | 9 | 26 | 118 | 44 | 69 | 56.5 | 24.5 | 3562 |
| 9/27/2022 | 2022 | 9 | 27 | 119 | 42 | 71 | 56.5 | 24.5 | 3586.5 |
| 9/28/2022 | 2022 | 9 | 28 | 120 | 43 | 68 | 55.5 | 23.5 | 3610 |
| 9/29/2022 | 2022 | 9 | 29 | 121 | 41 | 68 | 54.5 | 22.5 | 3632.5 |
| 9/30/2022 | 2022 | 9 | 30 | 122 | 41 | 69 | 55 | 23 | 3655.5 |
| 10/1/2022 | 2022 | 10 | 1 | 123 | 40 | 71 | 55.5 | 23.5 | 3679 |
| 10/2/2022 | 2022 | 10 | 2 | 124 | 44 | 63 | 53.5 | 21.5 | 3700.5 |
| 10/3/2022 | 2022 | 10 | 3 | 125 | 41 | 57 | 49 | 17 | 3717.5 |
| 10/4/2022 | 2022 | 10 | 4 | 126 | 40 | 52 | 46 | 14 | 3731.5 |
| 10/5/2022 | 2022 | 10 | 5 | 127 | 40 | 57 | 48.5 | 16.5 | 3748 |
| 10/6/2022 | 2022 | 10 | 6 | 128 | 42 | 51 | 46.5 | 14.5 | 3762.5 |
| 10/7/2022 | 2022 | 10 | 7 | 129 | 40 | 53 | 46.5 | 14.5 | 3777 |
| 10/8/2022 | 2022 | 10 | 8 | 130 | 40 | 48 | 44 | 12 | 3789 |
| 10/9/2022 | 2022 | 10 | 9 | 131 | 36 | 55 | 45.5 | 13.5 | 3802.5 |
| 10/10/2022 | 2022 | 10 | 10 | 132 | 35 | 58 | 46.5 | 14.5 | 3817 |
| 10/11/2022 | 2022 | 10 | 11 | 133 | 36 | 60 | 48 | 16 | 3833 |
| 10/12/2022 | 2022 | 10 | 12 | 134 | 35 | 64 | 49.5 | 17.5 | 3850.5 |
| 10/13/2022 | 2022 | 10 | 13 | 135 | 32 | 66 | 49 | 17 | 3867.5 |
| 10/14/2022 | 2022 | 10 | 14 | 136 | 33 | 65 | 49 | 17 | 3884.5 |
| 10/15/2022 | 2022 | 10 | 15 | 137 | 36 | 65 | 50.5 | 18.5 | 3903 |
| 10/16/2022 | 2022 | 10 | 16 | 138 | 36 | 44 | 40 | 8 | 3911 |
| 10/17/2022 | 2022 | 10 | 17 | 139 | 31 | 41 | 36 | 4 | 3915 |
| 10/18/2022 | 2022 | 10 | 18 | 140 | 31 | 55 | 43 | 11 | 3926 |
| 10/19/2022 | 2022 | 10 | 19 | 141 | 31 | 61 | 46 | 14 | 3940 |
| 10/20/2022 | 2022 | 10 | 20 | 142 | 29 | 63 | 46 | 14 | 3954 |
| 10/21/2022 | 2022 | 10 | 21 | 143 | 35 | 59 | 47 | 15 | 3969 |
| 10/22/2022 | 2022 | 10 | 22 | 144 | 43 | 58 | 50.5 | 18.5 | 3987.5 |
| 10/23/2022 | 2022 | 10 | 23 | 145 | 23 | 46 | 34.5 | 2.5 | 3990 |
| 10/24/2022 | 2022 | 10 | 24 | 146 | 21 | 33 | 27 | -5 | 3985 |
| 10/25/2022 | 2022 | 10 | 25 | 147 | 20 | 51 | 35.5 | 3.5 | 3988.5 |
| 10/26/2022 | 2022 | 10 | 26 | 148 | 28 | 50 | 39 | 7 | 3995.5 |
| 10/27/2022 | 2022 | 10 | 27 | 149 | 22 | 35 | 28.5 | -3.5 | 3992 |
| 10/28/2022 | 2022 | 10 | 28 | 150 | 20 | 51 | 35.5 | 3.5 | 3995.5 |
| 10/29/2022 | 2022 | 10 | 29 | 151 | 26 | 54 | 40 | 8 | 4003.5 |
| 10/30/2022 | 2022 | 10 | 30 | 152 | 26 | 51 | 38.5 | 6.5 | 4010 |
| 10/31/2022 | 2022 | 10 | 31 | 153 | 24 | 54 | 39 | 7 | 4017 |
| 11/1/2022 | 2022 | 11 | 1 | 154 | 28 | 54 | 41 | 9 | 4026 |
| 11/2/2022 | 2022 | 11 | 2 | 155 | 32 | 53 | 42.5 | 10.5 | 4036.5 |
| 11/3/2022 | 2022 | 11 | 3 | 156 | 19 | 39 | 29 | -3 | 4033.5 |
| 11/4/2022 | 2022 | 11 | 4 | 157 | 20 | 29 | 24.5 | -7.5 | 4026 |
| 11/5/2022 | 2022 | 11 | 5 | 158 | 18 | 45 | 31.5 | -0.5 | 4025.5 |
| 11/6/2022 | 2022 | 11 | 6 | 159 | 30 | 53 | 41.5 | 9.5 | 4035 |
| 11/7/2022 | 2022 | 11 | 7 | 160 | 30 | 57 | 43.5 | 11.5 | 4046.5 |
| 11/8/2022 | 2022 | 11 | 8 | 161 | 37 | 58 | 47.5 | 15.5 | 4062 |
| 11/9/2022 | 2022 | 11 | 9 | 162 | 26 | 54 | 40 | 8 | 4070 |
| 11/10/2022 | 2022 | 11 | 10 | 163 | 16 | 37 | 26.5 | -5.5 | 4064.5 |
| 11/11/2022 | 2022 | 11 | 11 | 164 | 14 | 36 | 25 | -7 | 4057.5 |
| 11/12/2022 | 2022 | 11 | 12 | 165 | 17 | 47 | 32 | 0 | 4057.5 |
| 11/13/2022 | 2022 | 11 | 13 | 166 | 23 | 49 | 36 | 4 | 4061.5 |
| 11/14/2022 | 2022 | 11 | 14 | 167 | 18 | 36 | 27 | -5 | 4056.5 |
| 11/15/2022 | 2022 | 11 | 15 | 168 | 11 | 37 | 24 | -8 | 4048.5 |
| 11/16/2022 | 2022 | 11 | 16 | 169 | 7 | 33 | 20 | -12 | 4036.5 |
| 11/17/2022 | 2022 | 11 | 17 | 170 | 15 | 44 | 29.5 | -2.5 | 4034 |
| 11/18/2022 | 2022 | 11 | 18 | 171 | 20 | 40 | 30 | -2 | 4032 |
| 11/19/2022 | 2022 | 11 | 19 | 172 | 16 | 40 | 28 | -4 | 4028 |
| 11/20/2022 | 2022 | 11 | 20 | 173 | 15 | 43 | 29 | -3 | 4025 |
| 11/21/2022 | 2022 | 11 | 21 | 174 | 14 | 50 | 32 | 0 | 4025 |
| 11/22/2022 | 2022 | 11 | 22 | 175 | 20 | 48 | 34 | 2 | 4027 |
| 11/23/2022 | 2022 | 11 | 23 | 176 | 21 | 44 | 32.5 | 0.5 | 4027.5 |
| 11/24/2022 | 2022 | 11 | 24 | 177 | 17 | 35 | 26 | -6 | 4021.5 |
| 11/25/2022 | 2022 | 11 | 25 | 178 | 15 | 42 | 28.5 | -3.5 | 4018 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 11/26/2022 | 2022 | 11 | 26 | 179 | 21 | 46 | 33.5 | 1.5 | 4019.5 |
| 11/27/2022 | 2022 | 11 | 27 | 180 | 22 | 41 | 31.5 | -0.5 | 4019 |
| 11/28/2022 | 2022 | 11 | 28 | 181 | 25 | 39 | 32 | 0 | 4019 |
| 11/29/2022 | 2022 | 11 | 29 | 182 | 25 | 37 | 31 | -1 | 4018 |
| 11/30/2022 | 2022 | 11 | 30 | 183 | 18 | 48 | 33 | 1 | 4019 |
| 12/1/2022 | 2022 | 12 | 1 | 184 | 27 | 50 | 38.5 | 6.5 | 4025.5 |
| 12/2/2022 | 2022 | 12 | 2 | 185 | 29 | 41 | 35 | 3 | 4028.5 |
| 12/3/2022 | 2022 | 12 | 3 | 186 | 31 | 47 | 39 | 7 | 4035.5 |
| 12/4/2022 | 2022 | 12 | 4 | 187 | 36 | 43 | 39.5 | 7.5 | 4043 |
| 12/5/2022 | 2022 | 12 | 5 | 188 | 34 | 42 | 38 | 6 | 4049 |
| 12/6/2022 | 2022 | 12 | 6 | 189 | 29 | 38 | 33.5 | 1.5 | 4050.5 |
| 12/7/2022 | 2022 | 12 | 7 | 190 | 28 | 40 | 34 | 2 | 4052.5 |
| 12/8/2022 | 2022 | 12 | 8 | 191 | 19 | 39 | 29 | -3 | 4049.5 |
| 12/9/2022 | 2022 | 12 | 9 | 192 | 23 | 43 | 33 | 1 | 4050.5 |
| 12/10/2022 | 2022 | 12 | 10 | 193 | 19 | 47 | 33 | 1 | 4051.5 |
| 12/11/2022 | 2022 | 12 | 11 | 194 | 26 | 49 | 37.5 | 5.5 | 4057 |
| 12/12/2022 | 2022 | 12 | 12 | 195 | 15 | 34 | 24.5 | -7.5 | 4049.5 |
| 12/13/2022 | 2022 | 12 | 13 | 196 | 13 | 20 | 16.5 | -15.5 | 4034 |
| 12/14/2022 | 2022 | 12 | 14 | 197 | 8 | 27 | 17.5 | -14.5 | 4019.5 |
| 12/15/2022 | 2022 | 12 | 15 | 198 | 9 | 29 | 19 | -13 | 4006.5 |
| 12/16/2022 | 2022 | 12 | 16 | 199 | -1 | 22 | 10.5 | -21.5 | 3985 |
| 12/17/2022 | 2022 | 12 | 17 | 200 | 1 | 37 | 19 | -13 | 3972 |
| 12/18/2022 | 2022 | 12 | 18 | 201 | 14 | 36 | 25 | -7 | 3965 |
| 12/19/2022 | 2022 | 12 | 19 | 202 | 13 | 36 | 24.5 | -7.5 | 3957.5 |
| 12/20/2022 | 2022 | 12 | 20 | 203 | 13 | 42 | 27.5 | -4.5 | 3953 |
| 12/21/2022 | 2022 | 12 | 21 | 204 | 18 | 41 | 29.5 | -2.5 | 3950.5 |
| 12/22/2022 | 2022 | 12 | 22 | 205 | 24 | 44 | 34 | 2 | 3952.5 |
| 12/23/2022 | 2022 | 12 | 23 | 206 | 23 | 43 | 33 | 1 | 3953.5 |
| 12/24/2022 | 2022 | 12 | 24 | 207 | 21 | 40 | 30.5 | -1.5 | 3952 |
| 12/25/2022 | 2022 | 12 | 25 | 208 | 20 | 47 | 33.5 | 1.5 | 3953.5 |
| 12/26/2022 | 2022 | 12 | 26 | 209 | 25 | 50 | 37.5 | 5.5 | 3959 |
| 12/27/2022 | 2022 | 12 | 27 | 210 | 33 | 48 | 40.5 | 8.5 | 3967.5 |
| 12/28/2022 | 2022 | 12 | 28 | 211 | 22 | 37 | 29.5 | -2.5 | 3965 |
| 12/29/2022 | 2022 | 12 | 29 | 212 | 21 | 29 | 25 | -7 | 3958 |
| 12/30/2022 | 2022 | 12 | 30 | 213 | 26 | 31 | 28.5 | -3.5 | 3954.5 |
| 12/31/2022 | 2022 | 12 | 31 | 214 | 30 | 34 | 32 | 0 | 3954.5 |
| 1/1/2023 | 2023 | 1 | 1 | 215 | 23 | 40 | 31.5 | -0.5 | 3954 |
| 1/2/2023 | 2023 | 1 | 2 | 216 | 20 | 26 | 23 | -9 | 3945 |
| 1/3/2023 | 2023 | 1 | 3 | 217 | 19 | 25 | 22 | -10 | 3935 |
| 1/4/2023 | 2023 | 1 | 4 | 218 | 15 | 29 | 22 | -10 | 3925 |
| 1/5/2023 | 2023 | 1 | 5 | 219 | 18 | 39 | 28.5 | -3.5 | 3921.5 |
| 1/6/2023 | 2023 | 1 | 6 | 220 | 12 | 33 | 22.5 | -9.5 | 3912 |
| 1/7/2023 | 2023 | 1 | 7 | 221 | 8 | 43 | 25.5 | -6.5 | 3905.5 |
| 1/8/2023 | 2023 | 1 | 8 | 222 | 20 | 44 | 32 | 0 | 3905.5 |
| 1/9/2023 | 2023 | 1 | 9 | 223 | 20 | 47 | 33.5 | 1.5 | 3907 |
| 1/10/2023 | 2023 | 1 | 10 | 224 | 31 | 44 | 37.5 | 5.5 | 3912.5 |
| 1/11/2023 | 2023 | 1 | 11 | 225 | 12 | 34 | 23 | -9 | 3903.5 |
| 1/12/2023 | 2023 | 1 | 12 | 226 | 9 | 44 | 26.5 | -5.5 | 3898 |
| 1/13/2023 | 2023 | 1 | 13 | 227 | 17 | 53 | 35 | 3 | 3901 |
| 1/14/2023 | 2023 | 1 | 14 | 228 | 27 | 47 | 37 | 5 | 3906 |
| 1/15/2023 | 2023 | 1 | 15 | 229 | 23 | 31 | 27 | -5 | 3901 |
| 1/16/2023 | 2023 | 1 | 16 | 230 | 22 | 32 | 27 | -5 | 3896 |
| 1/17/2023 | 2023 | 1 | 17 | 231 | 18 | 29 | 23.5 | -8.5 | 3887.5 |
| 1/18/2023 | 2023 | 1 | 18 | 232 | 9 | 24 | 16.5 | -15.5 | 3872 |
| 1/19/2023 | 2023 | 1 | 19 | 233 | 6 | 35 | 20.5 | -11.5 | 3860.5 |
| 1/20/2023 | 2023 | 1 | 20 | 234 | 15 | 23 | 19 | -13 | 3847.5 |
| 1/21/2023 | 2023 | 1 | 21 | 235 | 9 | 27 | 18 | -14 | 3833.5 |
| 1/22/2023 | 2023 | 1 | 22 | 236 | 7 | 37 | 22 | -10 | 3823.5 |
| 1/23/2023 | 2023 | 1 | 23 | 237 | 11 | 30 | 20.5 | -11.5 | 3812 |
| 1/24/2023 | 2023 | 1 | 24 | 238 | 4 | 29 | 16.5 | -15.5 | 3796.5 |
| 1/25/2023 | 2023 | 1 | 25 | 239 | 0 | 27 | 13.5 | -18.5 | 3778 |
| 1/26/2023 | 2023 | 1 | 26 | 240 | -3 | 29 | 13 | -19 | 3759 |
| 1/27/2023 | 2023 | 1 | 27 | 241 | 6 | 40 | 23 | -9 | 3750 |
| 1/28/2023 | 2023 | 1 | 28 | 242 | 15 | 36 | 25.5 | -6.5 | 3743.5 |
| 1/29/2023 | 2023 | 1 | 29 | 243 | 23 | 40 | 31.5 | -0.5 | 3743 |
| 1/30/2023 | 2023 | 1 | 30 | 244 | 13 | 38 | 25.5 | -6.5 | 3736.5 |
| 1/31/2023 | 2023 | 1 | 31 | 245 | 9 | 37 | 23 | -9 | 3727.5 |
| 2/1/2023 | 2023 | 2 | 1 | 246 | 5 | 38 | 21.5 | -10.5 | 3717 |
| 2/2/2023 | 2023 | 2 | 2 | 247 | 7 | 38 | 22.5 | -9.5 | 3707.5 |
| 2/3/2023 | 2023 | 2 | 3 | 248 | 11 | 46 | 28.5 | -3.5 | 3704 |
| 2/4/2023 | 2023 | 2 | 4 | 249 | 21 | 49 | 35 | 3 | 3707 |
| 2/5/2023 | 2023 | 2 | 5 | 250 | 23 | 51 | 37 | 5 | 3712 |
| 2/6/2023 | 2023 | 2 | 6 | 251 | 11 | 33 | 22 | -10 | 3702 |
| 2/7/2023 | 2023 | 2 | 7 | 252 | 9 | 31 | 20 | -12 | 3690 |
| 2/8/2023 | 2023 | 2 | 8 | 253 | 8 | 38 | 23 | -9 | 3681 |
| 2/9/2023 | 2023 | 2 | 9 | 254 | 2 | 27 | 14.5 | -17.5 | 3663.5 |
| 2/10/2023 | 2023 | 2 | 10 | 255 | -1 | 45 | 22 | -10 | 3653.5 |
| 2/11/2023 | 2023 | 2 | 11 | 256 | 16 | 48 | 32 | 0 | 3653.5 |
| 2/12/2023 | 2023 | 2 | 12 | 257 | 20 | 50 | 35 | 3 | 3656.5 |
| 2/13/2023 | 2023 | 2 | 13 | 258 | 20 | 45 | 32.5 | 0.5 | 3657 |
| 2/14/2023 | 2023 | 2 | 14 | 259 | 17 | 24 | 20.5 | -11.5 | 3645.5 |
| 2/15/2023 | 2023 | 2 | 15 | 260 | 4 | 17 | 10.5 | -21.5 | 3624 |
| 2/16/2023 | 2023 | 2 | 16 | 261 | -4 | 22 | 9 | -23 | 3601 |
| 2/17/2023 | 2023 | 2 | 17 | 262 | -5 | 40 | 17.5 | -14.5 | 3586.5 |
| 2/18/2023 | 2023 | 2 | 18 | 263 | 22 | 43 | 32.5 | 0.5 | 3587 |
| 2/19/2023 | 2023 | 2 | 19 | 264 | 27 | 41 | 34 | 2 | 3589 |
| 2/20/2023 | 2023 | 2 | 20 | 265 | 25 | 45 | 35 | 3 | 3592 |
| 2/21/2023 | 2023 | 2 | 21 | 266 | 25 | 45 | 35 | 3 | 3595 |
| 2/22/2023 | 2023 | 2 | 22 | 267 | 14 | 30 | 22 | -10 | 3585 |
| 2/23/2023 | 2023 | 2 | 23 | 268 | 12 | 28 | 20 | -12 | 3573 |
| 2/24/2023 | 2023 | 2 | 24 | 269 | 18 | 40 | 29 | -3 | 3570 |
| 2/25/2023 | 2023 | 2 | 25 | 270 | 27 | 50 | 38.5 | 6.5 | 3576.5 |
| 2/26/2023 | 2023 | 2 | 26 | 271 | 17 | 36 | 26.5 | -5.5 | 3571 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 2/27/2023 | 2023 | 2 | 27 | 272 | 13 | 36 | 24.5 | -7.5 | 3563.5 |
| 2/28/2023 | 2023 | 2 | 28 | 273 | 20 | 38 | 29 | -3 | 3560.5 |
| 3/1/2023 | 2023 | 3 | 1 | 274 | 16 | 33 | 24.5 | -7.5 | 3553 |
| 3/2/2023 | 2023 | 3 | 2 | 275 | 18 | 30 | 24 | -8 | 3545 |
| 3/3/2023 | 2023 | 3 | 3 | 276 | 16 | 40 | 28 | -4 | 3541 |
| 3/4/2023 | 2023 | 3 | 4 | 277 | 11 | 48 | 29.5 | -2.5 | 3538.5 |
| 3/5/2023 | 2023 | 3 | 5 | 278 | 28 | 46 | 37 | 5 | 3543.5 |
| 3/6/2023 | 2023 | 3 | 6 | 279 | 31 | 51 | 41 | 9 | 3552.5 |
| 3/7/2023 | 2023 | 3 | 7 | 280 | 33 | 49 | 41 | 9 | 3561.5 |
| 3/8/2023 | 2023 | 3 | 8 | 281 | 32 | 53 | 42.5 | 10.5 | 3572 |
| 3/9/2023 | 2023 | 3 | 9 | 282 | 20 | 47 | 33.5 | 1.5 | 3573.5 |
| 3/10/2023 | 2023 | 3 | 10 | 283 | 30 | 51 | 40.5 | 8.5 | 3582 |
| 3/11/2023 | 2023 | 3 | 11 | 284 | 33 | 46 | 39.5 | 7.5 | 3589.5 |
| 3/12/2023 | 2023 | 3 | 12 | 285 | 29 | 46 | 37.5 | 5.5 | 3595 |
| 3/13/2023 | 2023 | 3 | 13 | 286 | 23 | 46 | 34.5 | 2.5 | 3597.5 |
| 3/14/2023 | 2023 | 3 | 14 | 287 | 22 | 50 | 36 | 4 | 3601.5 |
| 3/15/2023 | 2023 | 3 | 15 | 288 | 32 | 40 | 36 | 4 | 3605.5 |
| 3/16/2023 | 2023 | 3 | 16 | 289 | 26 | 37 | 31.5 | -0.5 | 3605 |
| 3/17/2023 | 2023 | 3 | 17 | 290 | 15 | 36 | 25.5 | -6.5 | 3598.5 |
| 3/18/2023 | 2023 | 3 | 18 | 291 | 13 | 37 | 25 | -7 | 3591.5 |
| 3/19/2023 | 2023 | 3 | 19 | 292 | 15 | 40 | 27.5 | -4.5 | 3587 |
| 3/20/2023 | 2023 | 3 | 20 | 293 | 27 | 32 | 29.5 | -2.5 | 3584.5 |
| 3/21/2023 | 2023 | 3 | 21 | 294 | 28 | 36 | 32 | 0 | 3584.5 |
| 3/22/2023 | 2023 | 3 | 22 | 295 | 27 | 41 | 34 | 2 | 3586.5 |
| 3/23/2023 | 2023 | 3 | 23 | 296 | 20 | 39 | 29.5 | -2.5 | 3584 |
| 3/24/2023 | 2023 | 3 | 24 | 297 | 19 | 34 | 26.5 | -5.5 | 3578.5 |
| 3/25/2023 | 2023 | 3 | 25 | 298 | 11 | 35 | 23 | -9 | 3569.5 |
| 3/26/2023 | 2023 | 3 | 26 | 299 | 17 | 35 | 26 | -6 | 3563.5 |
| 3/27/2023 | 2023 | 3 | 27 | 300 | 7 | 37 | 22 | -10 | 3553.5 |
| 3/28/2023 | 2023 | 3 | 28 | 301 | 8 | 51 | 29.5 | -2.5 | 3551 |
| 3/29/2023 | 2023 | 3 | 29 | 302 | 27 | 57 | 42 | 10 | 3561 |
| 3/30/2023 | 2023 | 3 | 30 | 303 | 21 | 49 | 35 | 3 | 3564 |
| 3/31/2023 | 2023 | 3 | 31 | 304 | 19 | 39 | 29 | -3 | 3561 |
| 4/1/2023 | 2023 | 4 | 1 | 305 | 17 | 55 | 36 | 4 | 3565 |
| 4/2/2023 | 2023 | 4 | 2 | 306 | 26 | 54 | 40 | 8 | 3573 |
| 4/3/2023 | 2023 | 4 | 3 | 307 | 33 | 54 | 43.5 | 11.5 | 3584.5 |
| 4/4/2023 | 2023 | 4 | 4 | 308 | 12 | 33 | 22.5 | -9.5 | 3575 |
| 4/5/2023 | 2023 | 4 | 5 | 309 | 4 | 35 | 19.5 | -12.5 | 3562.5 |
| 4/6/2023 | 2023 | 4 | 6 | 310 | 9 | 51 | 30 | -2 | 3560.5 |
| 4/7/2023 | 2023 | 4 | 7 | 311 | 27 | 55 | 41 | 9 | 3569.5 |
| 4/8/2023 | 2023 | 4 | 8 | 312 | 29 | 56 | 42.5 | 10.5 | 3580 |
| 4/9/2023 | 2023 | 4 | 9 | 313 | 27 | 59 | 43 | 11 | 3591 |
| 4/10/2023 | 2023 | 4 | 10 | 314 | 28 | 64 | 46 | 14 | 3605 |
| 4/11/2023 | 2023 | 4 | 11 | 315 | 38 | 68 | 53 | 21 | 3626 |
| 4/12/2023 | 2023 | 4 | 12 | 316 | 36 | 66 | 51 | 19 | 3645 |
| 4/13/2023 | 2023 | 4 | 13 | 317 | 35 | 56 | 45.5 | 13.5 | 3658.5 |
| 4/14/2023 | 2023 | 4 | 14 | 318 | 32 | 48 | 40 | 8 | 3666.5 |
| 4/15/2023 | 2023 | 4 | 15 | 319 | 26 | 51 | 38.5 | 6.5 | 3673 |
| 4/16/2023 | 2023 | 4 | 16 | 320 | 25 | 60 | 42.5 | 10.5 | 3683.5 |
| 4/17/2023 | 2023 | 4 | 17 | 321 | 33 | 62 | 47.5 | 15.5 | 3699 |
| 4/18/2023 | 2023 | 4 | 18 | 322 | 33 | 57 | 45 | 13 | 3712 |
| 4/19/2023 | 2023 | 4 | 19 | 323 | 27 | 55 | 41 | 9 | 3721 |
| 4/20/2023 | 2023 | 4 | 20 | 324 | 20 | 48 | 34 | 2 | 3723 |
| 4/21/2023 | 2023 | 4 | 21 | 325 | 21 | 55 | 38 | 6 | 3729 |
| 4/22/2023 | 2023 | 4 | 22 | 326 | 30 | 55 | 42.5 | 10.5 | 3739.5 |
| 4/23/2023 | 2023 | 4 | 23 | 327 | 27 | 57 | 42 | 10 | 3749.5 |
| 4/24/2023 | 2023 | 4 | 24 | 328 | 32 | 58 | 45 | 13 | 3762.5 |
| 4/25/2023 | 2023 | 4 | 25 | 329 | 26 | 55 | 40.5 | 8.5 | 3771 |
| 4/26/2023 | 2023 | 4 | 26 | 330 | 27 | 54 | 40.5 | 8.5 | 3779.5 |
| 4/27/2023 | 2023 | 4 | 27 | 331 | 29 | 63 | 46 | 14 | 3793.5 |
| 4/28/2023 | 2023 | 4 | 28 | 332 | 32 | 55 | 43.5 | 11.5 | 3805 |
| 4/29/2023 | 2023 | 4 | 29 | 333 | 30 | 66 | 48 | 16 | 3821 |
| 4/30/2023 | 2023 | 4 | 30 | 334 | 37 | 72 | 54.5 | 22.5 | 3843.5 |
| 5/1/2023 | 2023 | 5 | 1 | 335 | 37 | 72 | 54.5 | 22.5 | 3866 |
| 5/2/2023 | 2023 | 5 | 2 | 336 | 37 | 63 | 50 | 18 | 3884 |
| 5/3/2023 | 2023 | 5 | 3 | 337 | 36 | 66 | 51 | 19 | 3903 |
| 5/4/2023 | 2023 | 5 | 4 | 338 | 34 | 61 | 47.5 | 15.5 | 3918.5 |
| 5/5/2023 | 2023 | 5 | 5 | 339 | 28 | 57 | 42.5 | 10.5 | 3929 |
| 5/6/2023 | 2023 | 5 | 6 | 340 | 33 | 61 | 47 | 15 | 3944 |
| 5/7/2023 | 2023 | 5 | 7 | 341 | 38 | 62 | 50 | 18 | 3962 |
| 5/8/2023 | 2023 | 5 | 8 | 342 | 36 | 68 | 52 | 20 | 3982 |
| 5/9/2023 | 2023 | 5 | 9 | 343 | 32 | 68 | 50 | 18 | 4000 |
| 5/10/2023 | 2023 | 5 | 10 | 344 | 33 | 61 | 47 | 15 | 4015 |
| 5/11/2023 | 2023 | 5 | 11 | 345 | 32 | 61 | 46.5 | 14.5 | 4029.5 |
| 5/12/2023 | 2023 | 5 | 12 | 346 | 33 | 66 | 49.5 | 17.5 | 4047 |
| 5/13/2023 | 2023 | 5 | 13 | 347 | 41 | 65 | 53 | 21 | 4068 |
| 5/14/2023 | 2023 | 5 | 14 | 348 | 38 | 63 | 50.5 | 18.5 | 4086.5 |
| 5/15/2023 | 2023 | 5 | 15 | 349 | 41 | 61 | 51 | 19 | 4105.5 |
| 5/16/2023 | 2023 | 5 | 16 | 350 | 38 | 66 | 52 | 20 | 4125.5 |
| 5/17/2023 | 2023 | 5 | 17 | 351 | 42 | 64 | 53 | 21 | 4146.5 |
| 5/18/2023 | 2023 | 5 | 18 | 352 | 41 | 60 | 50.5 | 18.5 | 4165 |
| 5/19/2023 | 2023 | 5 | 19 | 353 | 40 | 58 | 49 | 17 | 4182 |
| 5/20/2023 | 2023 | 5 | 20 | 354 | 37 | 63 | 50 | 18 | 4200 |
| 5/21/2023 | 2023 | 5 | 21 | 355 | 38 | 63 | 50.5 | 18.5 | 4218.5 |
| 5/22/2023 | 2023 | 5 | 22 | 356 | 38 | 66 | 52 | 20 | 4238.5 |
| 5/23/2023 | 2023 | 5 | 23 | 357 | 39 | 70 | 54.5 | 22.5 | 4261 |
| 5/24/2023 | 2023 | 5 | 24 | 358 | 40 | 71 | 55.5 | 23.5 | 4284.5 |
| 5/25/2023 | 2023 | 5 | 25 | 359 | 39 | 72 | 55.5 | 23.5 | 4308 |
| 5/26/2023 | 2023 | 5 | 26 | 360 | 38 | 72 | 55 | 23 | 4331 |
| 5/27/2023 | 2023 | 5 | 27 | 361 | 36 | 68 | 52 | 20 | 4351 |
| 5/28/2023 | 2023 | 5 | 28 | 362 | 35 | 69 | 52 | 20 | 4371 |
| 5/29/2023 | 2023 | 5 | 29 | 363 | 39 | 71 | 55 | 23 | 4394 |
| 5/30/2023 | 2023 | 5 | 30 | 364 | 40 | 73 | 56.5 | 24.5 | 4418.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 5/31/2023 | 2023 | 5 | 31 | 365 | 39 | 71 | 55 | 23 | 4441.5 |
| 6/1/2023 | 2023 | 6 | 1 | 1 | 36 | 64 | 50 | 18 | 18 |
| 6/2/2023 | 2023 | 6 | 2 | 2 | 41 | 63 | 52 | 20 | 38 |
| 6/3/2023 | 2023 | 6 | 3 | 3 | 38 | 67 | 52.5 | 20.5 | 58.5 |
| 6/4/2023 | 2023 | 6 | 4 | 4 | 38 | 70 | 54 | 22 | 80.5 |
| 6/5/2023 | 2023 | 6 | 5 | 5 | 40 | 70 | 55 | 23 | 103.5 |
| 6/6/2023 | 2023 | 6 | 6 | 6 | 43 | 70 | 56.5 | 24.5 | 128 |
| 6/7/2023 | 2023 | 6 | 7 | 7 | 46 | 68 | 57 | 25 | 153 |
| 6/8/2023 | 2023 | 6 | 8 | 8 | 39 | 69 | 54 | 22 | 175 |
| 6/9/2023 | 2023 | 6 | 9 | 9 | 41 | 68 | 54.5 | 22.5 | 197.5 |
| 6/10/2023 | 2023 | 6 | 10 | 10 | 40 | 72 | 56 | 24 | 221.5 |
| 6/11/2023 | 2023 | 6 | 11 | 11 | 39 | 72 | 55.5 | 23.5 | 245 |
| 6/12/2023 | 2023 | 6 | 12 | 12 | 35 | 64 | 49.5 | 17.5 | 262.5 |
| 6/13/2023 | 2023 | 6 | 13 | 13 | 34 | 64 | 49 | 17 | 279.5 |
| 6/14/2023 | 2023 | 6 | 14 | 14 | 38 | 72 | 55 | 23 | 302.5 |
| 6/15/2023 | 2023 | 6 | 15 | 15 | 39 | 71 | 55 | 23 | 325.5 |
| 6/16/2023 | 2023 | 6 | 16 | 16 | 36 | 72 | 54 | 22 | 347.5 |
| 6/17/2023 | 2023 | 6 | 17 | 17 | 37 | 70 | 53.5 | 21.5 | 369 |
| 6/18/2023 | 2023 | 6 | 18 | 18 | 42 | 76 | 59 | 27 | 396 |
| 6/19/2023 | 2023 | 6 | 19 | 19 | 53 | 76 | 64.5 | 32.5 | 428.5 |
| 6/20/2023 | 2023 | 6 | 20 | 20 | 42 | 75 | 58.5 | 26.5 | 455 |
| 6/21/2023 | 2023 | 6 | 21 | 21 | 39 | 78 | 58.5 | 26.5 | 481.5 |
| 6/22/2023 | 2023 | 6 | 22 | 22 | 42 | 78 | 60 | 28 | 509.5 |
| 6/23/2023 | 2023 | 6 | 23 | 23 | 41 | 76 | 58.5 | 26.5 | 536 |
| 6/24/2023 | 2023 | 6 | 24 | 24 | 35 | 76 | 55.5 | 23.5 | 559.5 |
| 6/25/2023 | 2023 | 6 | 25 | 25 | 47 | 81 | 64 | 32 | 591.5 |
| 6/26/2023 | 2023 | 6 | 26 | 26 | 51 | 83 | 67 | 35 | 626.5 |
| 6/27/2023 | 2023 | 6 | 27 | 27 | 55 | 81 | 68 | 36 | 662.5 |
| 6/28/2023 | 2023 | 6 | 28 | 28 | 53 | 82 | 67.5 | 35.5 | 698 |
| 6/29/2023 | 2023 | 6 | 29 | 29 | 49 | 78 | 63.5 | 31.5 | 729.5 |
| 6/30/2023 | 2023 | 6 | 30 | 30 | 42 | 77 | 59.5 | 27.5 | 757 |
| 7/1/2023 | 2023 | 7 | 1 | 31 | 43 | 79 | 61 | 29 | 786 |
| 7/2/2023 | 2023 | 7 | 2 | 32 | 46 | 82 | 64 | 32 | 818 |
| 7/3/2023 | 2023 | 7 | 3 | 33 | 47 | 83 | 65 | 33 | 851 |
| 7/4/2023 | 2023 | 7 | 4 | 34 | 51 | 83 | 67 | 35 | 886 |
| 7/5/2023 | 2023 | 7 | 5 | 35 | 50 | 82 | 66 | 34 | 920 |
| 7/6/2023 | 2023 | 7 | 6 | 36 | 48 | 84 | 66 | 34 | 954 |
| 7/7/2023 | 2023 | 7 | 7 | 37 | 49 | 83 | 66 | 34 | 988 |
| 7/8/2023 | 2023 | 7 | 8 | 38 | 50 | 82 | 66 | 34 | 1022 |
| 7/9/2023 | 2023 | 7 | 9 | 39 | 53 | 83 | 68 | 36 | 1058 |
| 7/10/2023 | 2023 | 7 | 10 | 40 | 55 | 83 | 69 | 37 | 1095 |
| 7/11/2023 | 2023 | 7 | 11 | 41 | 59 | 85 | 72 | 40 | 1135 |
| 7/12/2023 | 2023 | 7 | 12 | 42 | 59 | 83 | 71 | 39 | 1174 |
| 7/13/2023 | 2023 | 7 | 13 | 43 | 59 | 85 | 72 | 40 | 1214 |
| 7/14/2023 | 2023 | 7 | 14 | 44 | 55 | 88 | 71.5 | 39.5 | 1253.5 |
| 7/15/2023 | 2023 | 7 | 15 | 45 | 50 | 88 | 69 | 37 | 1290.5 |
| 7/16/2023 | 2023 | 7 | 16 | 46 | 49 | 88 | 68.5 | 36.5 | 1327 |
| 7/17/2023 | 2023 | 7 | 17 | 47 | 53 | 92 | 72.5 | 40.5 | 1367.5 |
| 7/18/2023 | 2023 | 7 | 18 | 48 | 59 | 87 | 73 | 41 | 1408.5 |
| 7/19/2023 | 2023 | 7 | 19 | 49 | 60 | 87 | 73.5 | 41.5 | 1450 |
| 7/20/2023 | 2023 | 7 | 20 | 50 | 57 | 90 | 73.5 | 41.5 | 1491.5 |
| 7/21/2023 | 2023 | 7 | 21 | 51 | 54 | 87 | 70.5 | 38.5 | 1530 |
| 7/22/2023 | 2023 | 7 | 22 | 52 | 53 | 86 | 69.5 | 37.5 | 1567.5 |
| 7/23/2023 | 2023 | 7 | 23 | 53 | 57 | 85 | 71 | 39 | 1606.5 |
| 7/24/2023 | 2023 | 7 | 24 | 54 | 56 | 87 | 71.5 | 39.5 | 1646 |
| 7/25/2023 | 2023 | 7 | 25 | 55 | 55 | 87 | 71 | 39 | 1685 |
| 7/26/2023 | 2023 | 7 | 26 | 56 | 53 | 86 | 69.5 | 37.5 | 1722.5 |
| 7/27/2023 | 2023 | 7 | 27 | 57 | 54 | 85 | 69.5 | 37.5 | 1760 |
| 7/28/2023 | 2023 | 7 | 28 | 58 | 51 | 84 | 67.5 | 35.5 | 1795.5 |
| 7/29/2023 | 2023 | 7 | 29 | 59 | 54 | 85 | 69.5 | 37.5 | 1833 |
| 7/30/2023 | 2023 | 7 | 30 | 60 | 53 | 80 | 66.5 | 34.5 | 1867.5 |
| 7/31/2023 | 2023 | 7 | 31 | 61 | 49 | 78 | 63.5 | 31.5 | 1899 |
| 8/1/2023 | 2023 | 8 | 1 | 62 | 51 | 76 | 63.5 | 31.5 | 1930.5 |
| 8/2/2023 | 2023 | 8 | 2 | 63 | 50 | 80 | 65 | 33 | 1963.5 |
| 8/3/2023 | 2023 | 8 | 3 | 64 | 50 | 79 | 64.5 | 32.5 | 1996 |
| 8/4/2023 | 2023 | 8 | 4 | 65 | 51 | 82 | 66.5 | 34.5 | 2030.5 |
| 8/5/2023 | 2023 | 8 | 5 | 66 | 50 | 83 | 66.5 | 34.5 | 2065 |
| 8/6/2023 | 2023 | 8 | 6 | 67 | 49 | 84 | 66.5 | 34.5 | 2099.5 |
| 8/7/2023 | 2023 | 8 | 7 | 68 | 53 | 79 | 66 | 34 | 2133.5 |
| 8/8/2023 | 2023 | 8 | 8 | 69 | 51 | 74 | 62.5 | 30.5 | 2164 |
| 8/9/2023 | 2023 | 8 | 9 | 70 | 50 | 74 | 62 | 30 | 2194 |
| 8/10/2023 | 2023 | 8 | 10 | 71 | 53 | 74 | 63.5 | 31.5 | 2225.5 |
| 8/11/2023 | 2023 | 8 | 11 | 72 | 48 | 74 | 61 | 29 | 2254.5 |
| 8/12/2023 | 2023 | 8 | 12 | 73 | 49 | 68 | 58.5 | 26.5 | 2281 |
| 8/13/2023 | 2023 | 8 | 13 | 74 | 47 | 72 | 59.5 | 27.5 | 2308.5 |
| 8/14/2023 | 2023 | 8 | 14 | 75 | 52 | 73 | 62.5 | 30.5 | 2339 |
| 8/15/2023 | 2023 | 8 | 15 | 76 | 48 | 75 | 61.5 | 29.5 | 2368.5 |
| 8/16/2023 | 2023 | 8 | 16 | 77 | 49 | 77 | 63 | 31 | 2399.5 |
| 8/17/2023 | 2023 | 8 | 17 | 78 | 49 | 78 | 63.5 | 31.5 | 2431 |
| 8/18/2023 | 2023 | 8 | 18 | 79 | 49 | 80 | 64.5 | 32.5 | 2463.5 |
| 8/19/2023 | 2023 | 8 | 19 | 80 | 49 | 79 | 64 | 32 | 2495.5 |
| 8/20/2023 | 2023 | 8 | 20 | 81 | 58 | 79 | 68.5 | 36.5 | 2532 |
| 8/21/2023 | 2023 | 8 | 21 | 82 | 55 | 78 | 66.5 | 34.5 | 2566.5 |
| 8/22/2023 | 2023 | 8 | 22 | 83 | 52 | 76 | 64 | 32 | 2598.5 |
| 8/23/2023 | 2023 | 8 | 23 | 84 | 50 | 68 | 59 | 27 | 2625.5 |
| 8/24/2023 | 2023 | 8 | 24 | 85 | 50 | 67 | 58.5 | 26.5 | 2652 |
| 8/25/2023 | 2023 | 8 | 25 | 86 | 48 | 76 | 62 | 30 | 2682 |
| 8/26/2023 | 2023 | 8 | 26 | 87 | 51 | 74 | 62.5 | 30.5 | 2712.5 |
| 8/27/2023 | 2023 | 8 | 27 | 88 | 50 | 74 | 62 | 30 | 2742.5 |
| 8/28/2023 | 2023 | 8 | 28 | 89 | 48 | 80 | 64 | 32 | 2774.5 |
| 8/29/2023 | 2023 | 8 | 29 | 90 | 49 | 81 | 65 | 33 | 2807.5 |
| 8/30/2023 | 2023 | 8 | 30 | 91 | 51 | 81 | 66 | 34 | 2841.5 |
| 8/31/2023 | 2023 | 8 | 31 | 92 | 47 | 84 | 65.5 | 33.5 | 2875 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/1/2023 | 2023 | 9 | 1 | 93 | 48 | 78 | 63 | 31 | 2906 |
| 9/2/2023 | 2023 | 9 | 2 | 94 | 49 | 76 | 62.5 | 30.5 | 2936.5 |
| 9/3/2023 | 2023 | 9 | 3 | 95 | 48 | 76 | 62 | 30 | 2966.5 |
| 9/4/2023 | 2023 | 9 | 4 | 96 | 48 | 72 | 60 | 28 | 2994.5 |
| 9/5/2023 | 2023 | 9 | 5 | 97 | 42 | 76 | 59 | 27 | 3021.5 |
| 9/6/2023 | 2023 | 9 | 6 | 98 | 43 | 81 | 62 | 30 | 3051.5 |
| 9/7/2023 | 2023 | 9 | 7 | 99 | 46 | 80 | 63 | 31 | 3082.5 |
| 9/8/2023 | 2023 | 9 | 8 | 100 | 48 | 81 | 64.5 | 32.5 | 3115 |
| 9/9/2023 | 2023 | 9 | 9 | 101 | 47 | 79 | 63 | 31 | 3146 |
| 9/10/2023 | 2023 | 9 | 10 | 102 | 50 | 80 | 65 | 33 | 3179 |
| 9/11/2023 | 2023 | 9 | 11 | 103 | 47 | 72 | 59.5 | 27.5 | 3206.5 |
| 9/12/2023 | 2023 | 9 | 12 | 104 | 49 | 66 | 57.5 | 25.5 | 3232 |
| 9/13/2023 | 2023 | 9 | 13 | 105 | 42 | 63 | 52.5 | 20.5 | 3252.5 |
| 9/14/2023 | 2023 | 9 | 14 | 106 | 42 | 64 | 53 | 21 | 3273.5 |
| 9/15/2023 | 2023 | 9 | 15 | 107 | 38 | 66 | 52 | 20 | 3293.5 |
| 9/16/2023 | 2023 | 9 | 16 | 108 | 38 | 69 | 53.5 | 21.5 | 3315 |
| 9/17/2023 | 2023 | 9 | 17 | 109 | 44 | 67 | 55.5 | 23.5 | 3338.5 |
| 9/18/2023 | 2023 | 9 | 18 | 110 | 40 | 68 | 54 | 22 | 3360.5 |
| 9/19/2023 | 2023 | 9 | 19 | 111 | 36 | 68 | 52 | 20 | 3380.5 |
| 9/20/2023 | 2023 | 9 | 20 | 112 | 36 | 64 | 50 | 18 | 3398.5 |
| 9/21/2023 | 2023 | 9 | 21 | 113 | 44 | 69 | 56.5 | 24.5 | 3423 |
| 9/22/2023 | 2023 | 9 | 22 | 114 | 44 | 69 | 56.5 | 24.5 | 3447.5 |
| 9/23/2023 | 2023 | 9 | 23 | 115 | 41 | 63 | 52 | 20 | 3467.5 |
| 9/24/2023 | 2023 | 9 | 24 | 116 | 37 | 65 | 51 | 19 | 3486.5 |
| 9/25/2023 | 2023 | 9 | 25 | 117 | 36 | 72 | 54 | 22 | 3508.5 |
| 9/26/2023 | 2023 | 9 | 26 | 118 | 38 | 73 | 55.5 | 23.5 | 3532 |
| 9/27/2023 | 2023 | 9 | 27 | 119 | 40 | 73 | 56.5 | 24.5 | 3556.5 |
| 9/28/2023 | 2023 | 9 | 28 | 120 | 41 | 72 | 56.5 | 24.5 | 3581 |
| 9/29/2023 | 2023 | 9 | 29 | 121 | 41 | 72 | 56.5 | 24.5 | 3605.5 |
| 9/30/2023 | 2023 | 9 | 30 | 122 | 47 | 73 | 60 | 28 | 3633.5 |
| 10/1/2023 | 2023 | 10 | 1 | 123 | 51 | 68 | 59.5 | 27.5 | 3661 |
| 10/2/2023 | 2023 | 10 | 2 | 124 | 40 | 64 | 52 | 20 | 3681 |
| 10/3/2023 | 2023 | 10 | 3 | 125 | 30 | 59 | 44.5 | 12.5 | 3693.5 |
| 10/4/2023 | 2023 | 10 | 4 | 126 | 30 | 61 | 45.5 | 13.5 | 3707 |
| 10/5/2023 | 2023 | 10 | 5 | 127 | 30 | 68 | 49 | 17 | 3724 |
| 10/6/2023 | 2023 | 10 | 6 | 128 | 35 | 71 | 53 | 21 | 3745 |
| 10/7/2023 | 2023 | 10 | 7 | 129 | 40 | 69 | 54.5 | 22.5 | 3767.5 |
| 10/8/2023 | 2023 | 10 | 8 | 130 | 40 | 66 | 53 | 21 | 3788.5 |
| 10/9/2023 | 2023 | 10 | 9 | 131 | 40 | 67 | 53.5 | 21.5 | 3810 |
| 10/10/2023 | 2023 | 10 | 10 | 132 | 38 | 65 | 51.5 | 19.5 | 3829.5 |
| 10/11/2023 | 2023 | 10 | 11 | 133 | 41 | 65 | 53 | 21 | 3850.5 |
| 10/12/2023 | 2023 | 10 | 12 | 134 | 26 | 53 | 39.5 | 7.5 | 3858 |
| 10/13/2023 | 2023 | 10 | 13 | 135 | 22 | 57 | 39.5 | 7.5 | 3865.5 |
| 10/14/2023 | 2023 | 10 | 14 | 136 | 33 | 63 | 48 | 16 | 3881.5 |
| 10/15/2023 | 2023 | 10 | 15 | 137 | 32 | 70 | 51 | 19 | 3900.5 |
| 10/16/2023 | 2023 | 10 | 16 | 138 | 36 | 71 | 53.5 | 21.5 | 3922 |
| 10/17/2023 | 2023 | 10 | 17 | 139 | 39 | 70 | 54.5 | 22.5 | 3944.5 |
| 10/18/2023 | 2023 | 10 | 18 | 140 | 38 | 71 | 54.5 | 22.5 | 3967 |
| 10/19/2023 | 2023 | 10 | 19 | 141 | 38 | 72 | 55 | 23 | 3990 |
| 10/20/2023 | 2023 | 10 | 20 | 142 | 37 | 72 | 54.5 | 22.5 | 4012.5 |
| 10/21/2023 | 2023 | 10 | 21 | 143 | 39 | 71 | 55 | 23 | 4035.5 |
| 10/22/2023 | 2023 | 10 | 22 | 144 | 38 | 68 | 53 | 21 | 4056.5 |
| 10/23/2023 | 2023 | 10 | 23 | 145 | 37 | 66 | 51.5 | 19.5 | 4076 |
| 10/24/2023 | 2023 | 10 | 24 | 146 | 37 | 57 | 47 | 15 | 4091 |
| 10/25/2023 | 2023 | 10 | 25 | 147 | 35 | 58 | 46.5 | 14.5 | 4105.5 |
| 10/26/2023 | 2023 | 10 | 26 | 148 | 35 | 55 | 45 | 13 | 4118.5 |
| 10/27/2023 | 2023 | 10 | 27 | 149 | 32 | 60 | 46 | 14 | 4132.5 |
| 10/28/2023 | 2023 | 10 | 28 | 150 | 38 | 56 | 47 | 15 | 4147.5 |
| 10/29/2023 | 2023 | 10 | 29 | 151 | 20 | 50 | 35 | 3 | 4150.5 |
| 10/30/2023 | 2023 | 10 | 30 | 152 | 12 | 45 | 28.5 | -3.5 | 4147 |
| 10/31/2023 | 2023 | 10 | 31 | 153 | 16 | 52 | 34 | 2 | 4149 |
| 11/1/2023 | 2023 | 11 | 1 | 154 | 22 | 57 | 39.5 | 7.5 | 4156.5 |
| 11/2/2023 | 2023 | 11 | 2 | 155 | 27 | 61 | 44 | 12 | 4168.5 |
| 11/3/2023 | 2023 | 11 | 3 | 156 | 32 | 64 | 48 | 16 | 4184.5 |
| 11/4/2023 | 2023 | 11 | 4 | 157 | 31 | 65 | 48 | 16 | 4200.5 |
| 11/5/2023 | 2023 | 11 | 5 | 158 | 34 | 62 | 48 | 16 | 4216.5 |
| 11/6/2023 | 2023 | 11 | 6 | 159 | 41 | 63 | 52 | 20 | 4236.5 |
| 11/7/2023 | 2023 | 11 | 7 | 160 | 39 | 61 | 50 | 18 | 4254.5 |
| 11/8/2023 | 2023 | 11 | 8 | 161 | 24 | 50 | 37 | 5 | 4259.5 |
| 11/9/2023 | 2023 | 11 | 9 | 162 | 22 | 47 | 34.5 | 2.5 | 4262 |
| 11/10/2023 | 2023 | 11 | 10 | 163 | 24 | 40 | 32 | 0 | 4262 |
| 11/11/2023 | 2023 | 11 | 11 | 164 | 21 | 45 | 33 | 1 | 4263 |
| 11/12/2023 | 2023 | 11 | 12 | 165 | 20 | 56 | 38 | 6 | 4269 |
| 11/13/2023 | 2023 | 11 | 13 | 166 | 31 | 54 | 42.5 | 10.5 | 4279.5 |
| 11/14/2023 | 2023 | 11 | 14 | 167 | 26 | 56 | 41 | 9 | 4288.5 |
| 11/15/2023 | 2023 | 11 | 15 | 168 | 28 | 60 | 44 | 12 | 4300.5 |
| 11/16/2023 | 2023 | 11 | 16 | 169 | 38 | 55 | 46.5 | 14.5 | 4315 |
| 11/17/2023 | 2023 | 11 | 17 | 170 | 33 | 53 | 43 | 11 | 4326 |
| 11/18/2023 | 2023 | 11 | 18 | 171 | 30 | 40 | 35 | 3 | 4329 |
| 11/19/2023 | 2023 | 11 | 19 | 172 | 28 | 36 | 32 | 0 | 4329 |
| 11/20/2023 | 2023 | 11 | 20 | 173 | 23 | 36 | 29.5 | -2.5 | 4326.5 |
| 11/21/2023 | 2023 | 11 | 21 | 174 | 20 | 42 | 31 | -1 | 4325.5 |
| 11/22/2023 | 2023 | 11 | 22 | 175 | 19 | 51 | 35 | 3 | 4328.5 |
| 11/23/2023 | 2023 | 11 | 23 | 176 | 24 | 46 | 35 | 3 | 4331.5 |
| 11/24/2023 | 2023 | 11 | 24 | 177 | 23 | 40 | 31.5 | -0.5 | 4331 |
| 11/25/2023 | 2023 | 11 | 25 | 178 | 15 | 31 | 23 | -9 | 4322 |
| 11/26/2023 | 2023 | 11 | 26 | 179 | 8 | 37 | 22.5 | -9.5 | 4312.5 |
| 11/27/2023 | 2023 | 11 | 27 | 180 | 10 | 38 | 24 | -8 | 4304.5 |
| 11/28/2023 | 2023 | 11 | 28 | 181 | 12 | 44 | 28 | -4 | 4300.5 |
| 11/29/2023 | 2023 | 11 | 29 | 182 | 26 | 45 | 35.5 | 3.5 | 4304 |
| 11/30/2023 | 2023 | 11 | 30 | 183 | 25 | 31 | 28 | -4 | 4300 |
| 12/1/2023 | 2023 | 12 | 1 | 184 | 21 | 28 | 24.5 | -7.5 | 4292.5 |
| 12/2/2023 | 2023 | 12 | 2 | 185 | 17 | 29 | 23 | -9 | 4283.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/3/2023 | 2023 | 12 | 3 | 186 | 21 | 37 | 29 | -3 | 4280.5 |
| 12/4/2023 | 2023 | 12 | 4 | 187 | 21 | 44 | 32.5 | 0.5 | 4281 |
| 12/5/2023 | 2023 | 12 | 5 | 188 | 20 | 51 | 35.5 | 3.5 | 4284.5 |
| 12/6/2023 | 2023 | 12 | 6 | 189 | 23 | 52 | 37.5 | 5.5 | 4290 |
| 12/7/2023 | 2023 | 12 | 7 | 190 | 30 | 46 | 38 | 6 | 4296 |
| 12/8/2023 | 2023 | 12 | 8 | 191 | 13 | 37 | 25 | -7 | 4289 |
| 12/9/2023 | 2023 | 12 | 9 | 192 | 7 | 28 | 17.5 | -14.5 | 4274.5 |
| 12/10/2023 | 2023 | 12 | 10 | 193 | 6 | 46 | 26 | -6 | 4268.5 |
| 12/11/2023 | 2023 | 12 | 11 | 194 | 22 | 51 | 36.5 | 4.5 | 4273 |
| 12/12/2023 | 2023 | 12 | 12 | 195 | 28 | 48 | 38 | 6 | 4279 |
| 12/13/2023 | 2023 | 12 | 13 | 196 | 29 | 39 | 34 | 2 | 4281 |
| 12/14/2023 | 2023 | 12 | 14 | 197 | 18 | 35 | 26.5 | -5.5 | 4275.5 |
| 12/15/2023 | 2023 | 12 | 15 | 198 | 16 | 40 | 28 | -4 | 4271.5 |
| 12/16/2023 | 2023 | 12 | 16 | 199 | 15 | 52 | 33.5 | 1.5 | 4273 |
| 12/17/2023 | 2023 | 12 | 17 | 200 | 24 | 53 | 38.5 | 6.5 | 4279.5 |
| 12/18/2023 | 2023 | 12 | 18 | 201 | 25 | 51 | 38 | 6 | 4285.5 |
| 12/19/2023 | 2023 | 12 | 19 | 202 | 29 | 50 | 39.5 | 7.5 | 4293 |
| 12/20/2023 | 2023 | 12 | 20 | 203 | 28 | 41 | 34.5 | 2.5 | 4295.5 |
| 12/21/2023 | 2023 | 12 | 21 | 204 | 24 | 44 | 34 | 2 | 4297.5 |
| 12/22/2023 | 2023 | 12 | 22 | 205 | 27 | 43 | 35 | 3 | 4300.5 |
| 12/23/2023 | 2023 | 12 | 23 | 206 | 26 | 33 | 29.5 | -2.5 | 4298 |
| 12/24/2023 | 2023 | 12 | 24 | 207 | 11 | 32 | 21.5 | -10.5 | 4287.5 |
| 12/25/2023 | 2023 | 12 | 25 | 208 | 2 | 28 | 15 | -17 | 4270.5 |
| 12/26/2023 | 2023 | 12 | 26 | 209 | 6 | 31 | 18.5 | -13.5 | 4257 |
| 12/27/2023 | 2023 | 12 | 27 | 210 | 11 | 38 | 24.5 | -7.5 | 4249.5 |
| 12/28/2023 | 2023 | 12 | 28 | 211 | 13 | 38 | 25.5 | -6.5 | 4243 |
| 12/29/2023 | 2023 | 12 | 29 | 212 | 14 | 46 | 30 | -2 | 4241 |
| 12/30/2023 | 2023 | 12 | 30 | 213 | 19 | 47 | 33 | 1 | 4242 |
| 12/31/2023 | 2023 | 12 | 31 | 214 | 18 | 38 | 28 | -4 | 4238 |
| 1/1/2024 | 2024 | 1 | 1 | 215 | 16 | 41 | 28.5 | -3.5 | 4234.5 |
| 1/2/2024 | 2024 | 1 | 2 | 216 | 15 | 40 | 27.5 | -4.5 | 4230 |
| 1/3/2024 | 2024 | 1 | 3 | 217 | 17 | 41 | 29 | -3 | 4227 |
| 1/4/2024 | 2024 | 1 | 4 | 218 | 21 | 28 | 24.5 | -7.5 | 4219.5 |
| 1/5/2024 | 2024 | 1 | 5 | 219 | 11 | 27 | 19 | -13 | 4206.5 |
| 1/6/2024 | 2024 | 1 | 6 | 220 | 8 | 26 | 17 | -15 | 4191.5 |
| 1/7/2024 | 2024 | 1 | 7 | 221 | 14 | 21 | 17.5 | -14.5 | 4177 |
| 1/8/2024 | 2024 | 1 | 8 | 222 | 4 | 18 | 11 | -21 | 4156 |
| 1/9/2024 | 2024 | 1 | 9 | 223 | 4 | 29 | 16.5 | -15.5 | 4140.5 |
| 1/10/2024 | 2024 | 1 | 10 | 224 | 14 | 31 | 22.5 | -9.5 | 4131 |
| 1/11/2024 | 2024 | 1 | 11 | 225 | 5 | 21 | 13 | -19 | 4112 |
| 1/12/2024 | 2024 | 1 | 12 | 226 | 5 | 24 | 14.5 | -17.5 | 4094.5 |
| 1/13/2024 | 2024 | 1 | 13 | 227 | 17 | 34 | 25.5 | -6.5 | 4088 |
| 1/14/2024 | 2024 | 1 | 14 | 228 | 24 | 38 | 31 | -1 | 4087 |
| 1/15/2024 | 2024 | 1 | 15 | 229 | 22 | 36 | 29 | -3 | 4084 |
| 1/16/2024 | 2024 | 1 | 16 | 230 | 18 | 41 | 29.5 | -2.5 | 4081.5 |
| 1/17/2024 | 2024 | 1 | 17 | 231 | 21 | 39 | 30 | -2 | 4079.5 |
| 1/18/2024 | 2024 | 1 | 18 | 232 | 22 | 44 | 33 | 1 | 4080.5 |
| 1/19/2024 | 2024 | 1 | 19 | 233 | 20 | 48 | 34 | 2 | 4082.5 |
| 1/20/2024 | 2024 | 1 | 20 | 234 | 27 | 47 | 37 | 5 | 4087.5 |
| 1/21/2024 | 2024 | 1 | 21 | 235 | 29 | 35 | 32 | 0 | 4087.5 |
| 1/22/2024 | 2024 | 1 | 22 | 236 | 20 | 35 | 27.5 | -4.5 | 4083 |
| 1/23/2024 | 2024 | 1 | 23 | 237 | 20 | 36 | 28 | -4 | 4079 |
| 1/24/2024 | 2024 | 1 | 24 | 238 | 26 | 38 | 32 | 0 | 4079 |
| 1/25/2024 | 2024 | 1 | 25 | 239 | 25 | 32 | 28.5 | -3.5 | 4075.5 |
| 1/26/2024 | 2024 | 1 | 26 | 240 | 14 | 32 | 23 | -9 | 4066.5 |
| 1/27/2024 | 2024 | 1 | 27 | 241 | 12 | 40 | 26 | -6 | 4060.5 |
| 1/28/2024 | 2024 | 1 | 28 | 242 | 12 | 49 | 30.5 | -1.5 | 4059 |
| 1/29/2024 | 2024 | 1 | 29 | 243 | 20 | 52 | 36 | 4 | 4063 |
| 1/30/2024 | 2024 | 1 | 30 | 244 | 22 | 51 | 36.5 | 4.5 | 4067.5 |
| 1/31/2024 | 2024 | 1 | 31 | 245 | 24 | 50 | 37 | 5 | 4072.5 |
| 2/1/2024 | 2024 | 2 | 1 | 246 | 29 | 48 | 38.5 | 6.5 | 4079 |
| 2/2/2024 | 2024 | 2 | 2 | 247 | 22 | 36 | 29 | -3 | 4076 |
| 2/3/2024 | 2024 | 2 | 3 | 248 | 17 | 29 | 23 | -9 | 4067 |
| 2/4/2024 | 2024 | 2 | 4 | 249 | 13 | 38 | 25.5 | -6.5 | 4060.5 |
| 2/5/2024 | 2024 | 2 | 5 | 250 | 16 | 51 | 33.5 | 1.5 | 4062 |
| 2/6/2024 | 2024 | 2 | 6 | 251 | 31 | 48 | 39.5 | 7.5 | 4069.5 |
| 2/7/2024 | 2024 | 2 | 7 | 252 | 22 | 31 | 26.5 | -5.5 | 4064 |
| 2/8/2024 | 2024 | 2 | 8 | 253 | 16 | 36 | 26 | -6 | 4058 |
| 2/9/2024 | 2024 | 2 | 9 | 254 | 15 | 32 | 23.5 | -8.5 | 4049.5 |
| 2/10/2024 | 2024 | 2 | 10 | 255 | 13 | 29 | 21 | -11 | 4038.5 |
| 2/11/2024 | 2024 | 2 | 11 | 256 | 8 | 35 | 21.5 | -10.5 | 4028 |
| 2/12/2024 | 2024 | 2 | 12 | 257 | 9 | 42 | 25.5 | -6.5 | 4021.5 |
| 2/13/2024 | 2024 | 2 | 13 | 258 | 13 | 47 | 30 | -2 | 4019.5 |
| 2/14/2024 | 2024 | 2 | 14 | 259 | 19 | 41 | 30 | -2 | 4017.5 |
| 2/15/2024 | 2024 | 2 | 15 | 260 | 20 | 46 | 33 | 1 | 4018.5 |
| 2/16/2024 | 2024 | 2 | 16 | 261 | 19 | 43 | 31 | -1 | 4017.5 |
| 2/17/2024 | 2024 | 2 | 17 | 262 | 20 | 44 | 32 | 0 | 4017.5 |
| 2/18/2024 | 2024 | 2 | 18 | 263 | 22 | 47 | 34.5 | 2.5 | 4020 |
| 2/19/2024 | 2024 | 2 | 19 | 264 | 24 | 51 | 37.5 | 5.5 | 4025.5 |
| 2/20/2024 | 2024 | 2 | 20 | 265 | 30 | 54 | 42 | 10 | 4035.5 |
| 2/21/2024 | 2024 | 2 | 21 | 266 | 30 | 48 | 39 | 7 | 4042.5 |
| 2/22/2024 | 2024 | 2 | 22 | 267 | 19 | 44 | 31.5 | -0.5 | 4042 |
| 2/23/2024 | 2024 | 2 | 23 | 268 | 14 | 44 | 29 | -3 | 4039 |
| 2/24/2024 | 2024 | 2 | 24 | 269 | 20 | 51 | 35.5 | 3.5 | 4042.5 |
| 2/25/2024 | 2024 | 2 | 25 | 270 | 28 | 53 | 40.5 | 8.5 | 4051 |
| 2/26/2024 | 2024 | 2 | 26 | 271 | 32 | 47 | 39.5 | 7.5 | 4058.5 |
| 2/27/2024 | 2024 | 2 | 27 | 272 | 23 | 43 | 33 | 1 | 4059.5 |
| 2/28/2024 | 2024 | 2 | 28 | 273 | 12 | 48 | 30 | -2 | 4057.5 |
| 2/29/2024 | 2024 | 2 | 29 | 274 | 22 | 47 | 34.5 | 2.5 | 4060 |
| 3/1/2024 | 2024 | 3 | 1 | 275 | 27 | 49 | 38 | 6 | 4066 |
| 3/2/2024 | 2024 | 3 | 2 | 276 | 30 | 49 | 39.5 | 7.5 | 4073.5 |
| 3/3/2024 | 2024 | 3 | 3 | 277 | 29 | 47 | 38 | 6 | 4079.5 |
| 3/4/2024 | 2024 | 3 | 4 | 278 | 28 | 44 | 36 | 4 | 4083.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/5/2024 | 2024 | 3 | 5 | 279 | 25 | 49 | 37 | 5 | 4088.5 |
| 3/6/2024 | 2024 | 3 | 6 | 280 | 26 | 44 | 35 | 3 | 4091.5 |
| 3/7/2024 | 2024 | 3 | 7 | 281 | 24 | 38 | 31 | -1 | 4090.5 |
| 3/8/2024 | 2024 | 3 | 8 | 282 | 18 | 37 | 27.5 | -4.5 | 4086 |
| 3/9/2024 | 2024 | 3 | 9 | 283 | 14 | 42 | 28 | -4 | 4082 |
| 3/10/2024 | 2024 | 3 | 10 | 284 | 15 | 50 | 32.5 | 0.5 | 4082.5 |
| 3/11/2024 | 2024 | 3 | 11 | 285 | 23 | 50 | 36.5 | 4.5 | 4087 |
| 3/12/2024 | 2024 | 3 | 12 | 286 | 31 | 50 | 40.5 | 8.5 | 4095.5 |
| 3/13/2024 | 2024 | 3 | 13 | 287 | 25 | 33 | 29 | -3 | 4092.5 |
| 3/14/2024 | 2024 | 3 | 14 | 288 | 22 | 39 | 30.5 | -1.5 | 4091 |
| 3/15/2024 | 2024 | 3 | 15 | 289 | 26 | 33 | 29.5 | -2.5 | 4088.5 |
| 3/16/2024 | 2024 | 3 | 16 | 290 | 19 | 41 | 30 | -2 | 4086.5 |
| 3/17/2024 | 2024 | 3 | 17 | 291 | 14 | 38 | 26 | -6 | 4080.5 |
| 3/18/2024 | 2024 | 3 | 18 | 292 | 27 | 41 | 34 | 2 | 4082.5 |
| 3/19/2024 | 2024 | 3 | 19 | 293 | 23 | 45 | 34 | 2 | 4084.5 |
| 3/20/2024 | 2024 | 3 | 20 | 294 | 20 | 49 | 34.5 | 2.5 | 4087 |
| 3/21/2024 | 2024 | 3 | 21 | 295 | 26 | 53 | 39.5 | 7.5 | 4094.5 |
| 3/22/2024 | 2024 | 3 | 22 | 296 | 27 | 54 | 40.5 | 8.5 | 4103 |
| 3/23/2024 | 2024 | 3 | 23 | 297 | 28 | 50 | 39 | 7 | 4110 |
| 3/24/2024 | 2024 | 3 | 24 | 298 | 21 | 36 | 28.5 | -3.5 | 4106.5 |
| 3/25/2024 | 2024 | 3 | 25 | 299 | 20 | 32 | 26 | -6 | 4100.5 |
| 3/26/2024 | 2024 | 3 | 26 | 300 | 20 | 36 | 28 | -4 | 4096.5 |
| 3/27/2024 | 2024 | 3 | 27 | 301 | 16 | 40 | 28 | -4 | 4092.5 |
| 3/28/2024 | 2024 | 3 | 28 | 302 | 20 | 53 | 36.5 | 4.5 | 4097 |
| 3/29/2024 | 2024 | 3 | 29 | 303 | 32 | 52 | 42 | 10 | 4107 |
| 3/30/2024 | 2024 | 3 | 30 | 304 | 32 | 57 | 44.5 | 12.5 | 4119.5 |
| 3/31/2024 | 2024 | 3 | 31 | 305 | 25 | 48 | 36.5 | 4.5 | 4124 |
| 4/1/2024 | 2024 | 4 | 1 | 306 | 23 | 38 | 30.5 | -1.5 | 4122.5 |
| 4/2/2024 | 2024 | 4 | 2 | 307 | 20 | 46 | 33 | 1 | 4123.5 |
| 4/3/2024 | 2024 | 4 | 3 | 308 | 26 | 57 | 41.5 | 9.5 | 4133 |
| 4/4/2024 | 2024 | 4 | 4 | 309 | 28 | 61 | 44.5 | 12.5 | 4145.5 |
| 4/5/2024 | 2024 | 4 | 5 | 310 | 21 | 55 | 38 | 6 | 4151.5 |
| 4/6/2024 | 2024 | 4 | 6 | 311 | 18 | 31 | 24.5 | -7.5 | 4144 |
| 4/7/2024 | 2024 | 4 | 7 | 312 | 19 | 44 | 31.5 | -0.5 | 4143.5 |
| 4/8/2024 | 2024 | 4 | 8 | 313 | 25 | 46 | 35.5 | 3.5 | 4147 |
| 4/9/2024 | 2024 | 4 | 9 | 314 | 26 | 49 | 37.5 | 5.5 | 4152.5 |
| 4/10/2024 | 2024 | 4 | 10 | 315 | 27 | 54 | 40.5 | 8.5 | 4161 |
| 4/11/2024 | 2024 | 4 | 11 | 316 | 26 | 61 | 43.5 | 11.5 | 4172.5 |
| 4/12/2024 | 2024 | 4 | 12 | 317 | 31 | 65 | 48 | 16 | 4188.5 |
| 4/13/2024 | 2024 | 4 | 13 | 318 | 29 | 60 | 44.5 | 12.5 | 4201 |
| 4/14/2024 | 2024 | 4 | 14 | 319 | 32 | 62 | 47 | 15 | 4216 |
| 4/15/2024 | 2024 | 4 | 15 | 320 | 30 | 46 | 38 | 6 | 4222 |
| 4/16/2024 | 2024 | 4 | 16 | 321 | 29 | 57 | 43 | 11 | 4233 |
| 4/17/2024 | 2024 | 4 | 17 | 322 | 30 | 63 | 46.5 | 14.5 | 4247.5 |
| 4/18/2024 | 2024 | 4 | 18 | 323 | 35 | 63 | 49 | 17 | 4264.5 |
| 4/19/2024 | 2024 | 4 | 19 | 324 | 33 | 66 | 49.5 | 17.5 | 4282 |
| 4/20/2024 | 2024 | 4 | 20 | 325 | 35 | 63 | 49 | 17 | 4299 |
| 4/21/2024 | 2024 | 4 | 21 | 326 | 33 | 65 | 49 | 17 | 4316 |
| 4/22/2024 | 2024 | 4 | 22 | 327 | 35 | 66 | 50.5 | 18.5 | 4334.5 |
| 4/23/2024 | 2024 | 4 | 23 | 328 | 36 | 68 | 52 | 20 | 4354.5 |
| 4/24/2024 | 2024 | 4 | 24 | 329 | 34 | 64 | 49 | 17 | 4371.5 |
| 4/25/2024 | 2024 | 4 | 25 | 330 | 33 | 54 | 43.5 | 11.5 | 4383 |
| 4/26/2024 | 2024 | 4 | 26 | 331 | 28 | 54 | 41 | 9 | 4392 |
| 4/27/2024 | 2024 | 4 | 27 | 332 | 27 | 37 | 32 | 0 | 4392 |
| 4/28/2024 | 2024 | 4 | 28 | 333 | 28 | 48 | 38 | 6 | 4398 |
| 4/29/2024 | 2024 | 4 | 29 | 334 | 28 | 58 | 43 | 11 | 4409 |
| 4/30/2024 | 2024 | 4 | 30 | 335 | 32 | 62 | 47 | 15 | 4424 |
| 5/1/2024 | 2024 | 5 | 1 | 336 | 34 | 63 | 48.5 | 16.5 | 4440.5 |
| 5/2/2024 | 2024 | 5 | 2 | 337 | 30 | 61 | 45.5 | 13.5 | 4454 |
| 5/3/2024 | 2024 | 5 | 3 | 338 | 34 | 62 | 48 | 16 | 4470 |
| 5/4/2024 | 2024 | 5 | 4 | 339 | 36 | 63 | 49.5 | 17.5 | 4487.5 |
| 5/5/2024 | 2024 | 5 | 5 | 340 | 36 | 62 | 49 | 17 | 4504.5 |
| 5/6/2024 | 2024 | 5 | 6 | 341 | 36 | 62 | 49 | 17 | 4521.5 |
| 5/7/2024 | 2024 | 5 | 7 | 342 | 36 | 62 | 49 | 17 | 4538.5 |
| 5/8/2024 | 2024 | 5 | 8 | 343 | 36 | 41 | 38.5 | 6.5 | 4545 |
| 5/9/2024 | 2024 | 5 | 9 | 344 | 28 | 55 | 41.5 | 9.5 | 4554.5 |
| 5/10/2024 | 2024 | 5 | 10 | 345 | 30 | 57 | 43.5 | 11.5 | 4566 |
| 5/11/2024 | 2024 | 5 | 11 | 346 | 29 | 62 | 45.5 | 13.5 | 4579.5 |
| 5/12/2024 | 2024 | 5 | 12 | 347 | 34 | 58 | 46 | 14 | 4593.5 |
| 5/13/2024 | 2024 | 5 | 13 | 348 | 31 | 60 | 45.5 | 13.5 | 4607 |
| 5/14/2024 | 2024 | 5 | 14 | 349 | 36 | 66 | 51 | 19 | 4626 |
| 5/15/2024 | 2024 | 5 | 15 | 350 | 39 | 65 | 52 | 20 | 4646 |
| 5/16/2024 | 2024 | 5 | 16 | 351 | 38 | 62 | 50 | 18 | 4664 |
| 5/17/2024 | 2024 | 5 | 17 | 352 | 38 | 56 | 47 | 15 | 4679 |
| 5/18/2024 | 2024 | 5 | 18 | 353 | 38 | 68 | 53 | 21 | 4700 |
| 5/19/2024 | 2024 | 5 | 19 | 354 | 38 | 69 | 53.5 | 21.5 | 4721.5 |
| 5/20/2024 | 2024 | 5 | 20 | 355 | 41 | 67 | 54 | 22 | 4743.5 |
| 5/21/2024 | 2024 | 5 | 21 | 356 | 41 | 65 | 53 | 21 | 4764.5 |
| 5/22/2024 | 2024 | 5 | 22 | 357 | 33 | 63 | 48 | 16 | 4780.5 |
| 5/23/2024 | 2024 | 5 | 23 | 358 | 30 | 65 | 47.5 | 15.5 | 4796 |
| 5/24/2024 | 2024 | 5 | 24 | 359 | 39 | 67 | 53 | 21 | 4817 |
| 5/25/2024 | 2024 | 5 | 25 | 360 | 36 | 67 | 51.5 | 19.5 | 4836.5 |
| 5/26/2024 | 2024 | 5 | 26 | 361 | 36 | 63 | 49.5 | 17.5 | 4854 |
| 5/27/2024 | 2024 | 5 | 27 | 362 | 37 | 67 | 52 | 20 | 4874 |
| 5/28/2024 | 2024 | 5 | 28 | 363 | 37 | 72 | 54.5 | 22.5 | 4896.5 |
| 5/29/2024 | 2024 | 5 | 29 | 364 | 42 | 74 | 58 | 26 | 4922.5 |
| 5/30/2024 | 2024 | 5 | 30 | 365 | 42 | 74 | 58 | 26 | 4948.5 |
| 5/31/2024 | 2024 | 5 | 31 | 366 | 42 | 74 | 58 | 26 | 4974.5 |
| 6/1/2024 | 2024 | 6 | 1 | 1 | 51 | 74 | 62.5 | 30.5 | 30.5 |
| 6/2/2024 | 2024 | 6 | 2 | 2 | 47 | 76 | 61.5 | 29.5 | 60 |
| 6/3/2024 | 2024 | 6 | 3 | 3 | 45 | 72 | 58.5 | 26.5 | 86.5 |
| 6/4/2024 | 2024 | 6 | 4 | 4 | 47 | 73 | 60 | 28 | 114.5 |
| 6/5/2024 | 2024 | 6 | 5 | 5 | 48 | 75 | 61.5 | 29.5 | 144 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/6/2024 | 2024 | 6 | 6 | 6 | 45 | 80 | 62.5 | 30.5 | 174.5 |
| 6/7/2024 | 2024 | 6 | 7 | 7 | 47 | 86 | 66.5 | 34.5 | 209 |
| 6/8/2024 | 2024 | 6 | 8 | 8 | 51 | 84 | 67.5 | 35.5 | 244.5 |
| 6/9/2024 | 2024 | 6 | 9 | 9 | 53 | 80 | 66.5 | 34.5 | 279 |
| 6/10/2024 | 2024 | 6 | 10 | 10 | 53 | 76 | 64.5 | 32.5 | 311.5 |
| 6/11/2024 | 2024 | 6 | 11 | 11 | 47 | 67 | 57 | 25 | 336.5 |
| 6/12/2024 | 2024 | 6 | 12 | 12 | 44 | 77 | 60.5 | 28.5 | 365 |
| 6/13/2024 | 2024 | 6 | 13 | 13 | 48 | 83 | 65.5 | 33.5 | 398.5 |
| 6/14/2024 | 2024 | 6 | 14 | 14 | 48 | 84 | 66 | 34 | 432.5 |
| 6/15/2024 | 2024 | 6 | 15 | 15 | 44 | 74 | 59 | 27 | 459.5 |
| 6/16/2024 | 2024 | 6 | 16 | 16 | 43 | 78 | 60.5 | 28.5 | 488 |
| 6/17/2024 | 2024 | 6 | 17 | 17 | 53 | 79 | 66 | 34 | 522 |
| 6/18/2024 | 2024 | 6 | 18 | 18 | 47 | 79 | 63 | 31 | 553 |
| 6/19/2024 | 2024 | 6 | 19 | 19 | 45 | 74 | 59.5 | 27.5 | 580.5 |
| 6/20/2024 | 2024 | 6 | 20 | 20 | 44 | 80 | 62 | 30 | 610.5 |
| 6/21/2024 | 2024 | 6 | 21 | 21 | 53 | 75 | 64 | 32 | 642.5 |
| 6/22/2024 | 2024 | 6 | 22 | 22 | 53 | 73 | 63 | 31 | 673.5 |
| 6/23/2024 | 2024 | 6 | 23 | 23 | 51 | 66 | 58.5 | 26.5 | 700 |
| 6/24/2024 | 2024 | 6 | 24 | 24 | 53 | 69 | 61 | 29 | 729 |
| 6/25/2024 | 2024 | 6 | 25 | 25 | 49 | 76 | 62.5 | 30.5 | 759.5 |
| 6/26/2024 | 2024 | 6 | 26 | 26 | 55 | 81 | 68 | 36 | 795.5 |
| 6/27/2024 | 2024 | 6 | 27 | 27 | 54 | 80 | 67 | 35 | 830.5 |
| 6/28/2024 | 2024 | 6 | 28 | 28 | 53 | 74 | 63.5 | 31.5 | 862 |
| 6/29/2024 | 2024 | 6 | 29 | 29 | 49 | 74 | 61.5 | 29.5 | 891.5 |
| 6/30/2024 | 2024 | 6 | 30 | 30 | 52 | 75 | 63.5 | 31.5 | 923 |
| 7/1/2024 | 2024 | 7 | 1 | 31 | 54 | 74 | 64 | 32 | 955 |
| 7/2/2024 | 2024 | 7 | 2 | 32 | 54 | 71 | 62.5 | 30.5 | 985.5 |
| 7/3/2024 | 2024 | 7 | 3 | 33 | 49 | 72 | 60.5 | 28.5 | 1014 |
| 7/4/2024 | 2024 | 7 | 4 | 34 | 49 | 76 | 62.5 | 30.5 | 1044.5 |
| 7/5/2024 | 2024 | 7 | 5 | 35 | 47 | 79 | 63 | 31 | 1075.5 |
| 7/6/2024 | 2024 | 7 | 6 | 36 | 45 | 77 | 61 | 29 | 1104.5 |
| 7/7/2024 | 2024 | 7 | 7 | 37 | 43 | 78 | 60.5 | 28.5 | 1133 |
| 7/8/2024 | 2024 | 7 | 8 | 38 | 47 | 81 | 64 | 32 | 1165 |
| 7/9/2024 | 2024 | 7 | 9 | 39 | 45 | 76 | 60.5 | 28.5 | 1193.5 |
| 7/10/2024 | 2024 | 7 | 10 | 40 | 50 | 78 | 64 | 32 | 1225.5 |
| 7/11/2024 | 2024 | 7 | 11 | 41 | 49 | 79 | 64 | 32 | 1257.5 |
| 7/12/2024 | 2024 | 7 | 12 | 42 | 53 | 82 | 67.5 | 35.5 | 1293 |
| 7/13/2024 | 2024 | 7 | 13 | 43 | 51 | 81 | 66 | 34 | 1327 |
| 7/14/2024 | 2024 | 7 | 14 | 44 | 50 | 82 | 66 | 34 | 1361 |
| 7/15/2024 | 2024 | 7 | 15 | 45 | 52 | 83 | 67.5 | 35.5 | 1396.5 |
| 7/16/2024 | 2024 | 7 | 16 | 46 | 53 | 81 | 67 | 35 | 1431.5 |
| 7/17/2024 | 2024 | 7 | 17 | 47 | 52 | 82 | 67 | 35 | 1466.5 |
| 7/18/2024 | 2024 | 7 | 18 | 48 | 52 | 78 | 65 | 33 | 1499.5 |
| 7/19/2024 | 2024 | 7 | 19 | 49 | 49 | 79 | 64 | 32 | 1531.5 |
| 7/20/2024 | 2024 | 7 | 20 | 50 | 48 | 78 | 63 | 31 | 1562.5 |
| 7/21/2024 | 2024 | 7 | 21 | 51 | 52 | 78 | 65 | 33 | 1595.5 |
| 7/22/2024 | 2024 | 7 | 22 | 52 | 48 | 70 | 59 | 27 | 1622.5 |
| 7/23/2024 | 2024 | 7 | 23 | 53 | 45 | 73 | 59 | 27 | 1649.5 |
| 7/24/2024 | 2024 | 7 | 24 | 54 | 48 | 78 | 63 | 31 | 1680.5 |
| 7/25/2024 | 2024 | 7 | 25 | 55 | 54 | 79 | 66.5 | 34.5 | 1715 |
| 7/26/2024 | 2024 | 7 | 26 | 56 | 53 | 80 | 66.5 | 34.5 | 1749.5 |
| 7/27/2024 | 2024 | 7 | 27 | 57 | 52 | 78 | 65 | 33 | 1782.5 |
| 7/28/2024 | 2024 | 7 | 28 | 58 | 51 | 79 | 65 | 33 | 1815.5 |
| 7/29/2024 | 2024 | 7 | 29 | 59 | 51 | 78 | 64.5 | 32.5 | 1848 |
| 7/30/2024 | 2024 | 7 | 30 | 60 | 55 | 78 | 66.5 | 34.5 | 1882.5 |
| 7/31/2024 | 2024 | 7 | 31 | 61 | 54 | 82 | 68 | 36 | 1918.5 |
| 8/1/2024 | 2024 | 8 | 1 | 62 | 56 | 82 | 69 | 37 | 1955.5 |
| 8/2/2024 | 2024 | 8 | 2 | 63 | 55 | 83 | 69 | 37 | 1992.5 |
| 8/3/2024 | 2024 | 8 | 3 | 64 | 48 | 77 | 62.5 | 30.5 | 2023 |
| 8/4/2024 | 2024 | 8 | 4 | 65 | 54 | 79 | 66.5 | 34.5 | 2057.5 |
| 8/5/2024 | 2024 | 8 | 5 | 66 | 50 | 77 | 63.5 | 31.5 | 2089 |
| 8/6/2024 | 2024 | 8 | 6 | 67 | 50 | 81 | 65.5 | 33.5 | 2122.5 |
| 8/7/2024 | 2024 | 8 | 7 | 68 | 53 | 80 | 66.5 | 34.5 | 2157 |
| 8/8/2024 | 2024 | 8 | 8 | 69 | 49 | 79 | 64 | 32 | 2189 |
| 8/9/2024 | 2024 | 8 | 9 | 70 | 49 | 76 | 62.5 | 30.5 | 2219.5 |
| 8/10/2024 | 2024 | 8 | 10 | 71 | 53 | 73 | 63 | 31 | 2250.5 |
| 8/11/2024 | 2024 | 8 | 11 | 72 | 53 | 75 | 64 | 32 | 2282.5 |
| 8/12/2024 | 2024 | 8 | 12 | 73 | 52 | 77 | 64.5 | 32.5 | 2315 |
| 8/13/2024 | 2024 | 8 | 13 | 74 | 51 | 77 | 64 | 32 | 2347 |
| 8/14/2024 | 2024 | 8 | 14 | 75 | 51 | 67 | 59 | 27 | 2374 |
| 8/15/2024 | 2024 | 8 | 15 | 76 | 47 | 74 | 60.5 | 28.5 | 2402.5 |
| 8/16/2024 | 2024 | 8 | 16 | 77 | 47 | 78 | 62.5 | 30.5 | 2433 |
| 8/17/2024 | 2024 | 8 | 17 | 78 | 52 | 80 | 66 | 34 | 2467 |
| 8/18/2024 | 2024 | 8 | 18 | 79 | 52 | 81 | 66.5 | 34.5 | 2501.5 |
| 8/19/2024 | 2024 | 8 | 19 | 80 | 51 | 79 | 65 | 33 | 2534.5 |
| 8/20/2024 | 2024 | 8 | 20 | 81 | 50 | 79 | 64.5 | 32.5 | 2567 |
| 8/21/2024 | 2024 | 8 | 21 | 82 | 50 | 82 | 66 | 34 | 2601 |
| 8/22/2024 | 2024 | 8 | 22 | 83 | 49 | 80 | 64.5 | 32.5 | 2633.5 |
| 8/23/2024 | 2024 | 8 | 23 | 84 | 46 | 72 | 59 | 27 | 2660.5 |
| 8/24/2024 | 2024 | 8 | 24 | 85 | 48 | 74 | 61 | 29 | 2689.5 |
| 8/25/2024 | 2024 | 8 | 25 | 86 | 49 | 68 | 58.5 | 26.5 | 2716 |
| 8/26/2024 | 2024 | 8 | 26 | 87 | 48 | 73 | 60.5 | 28.5 | 2744.5 |
| 8/27/2024 | 2024 | 8 | 27 | 88 | 49 | 71 | 60 | 28 | 2772.5 |
| 8/28/2024 | 2024 | 8 | 28 | 89 | 45 | 72 | 58.5 | 26.5 | 2799 |
| 8/29/2024 | 2024 | 8 | 29 | 90 | 49 | 63 | 56 | 24 | 2823 |
| 8/30/2024 | 2024 | 8 | 30 | 91 | 48 | 72 | 60 | 28 | 2851 |
| 8/31/2024 | 2024 | 8 | 31 | 92 | 46 | 73 | 59.5 | 27.5 | 2878.5 |
| 9/1/2024 | 2024 | 9 | 1 | 93 | 46 | 73 | 59.5 | 27.5 | 2906 |
| 9/2/2024 | 2024 | 9 | 2 | 94 | 45 | 71 | 58 | 26 | 2932 |
| 9/3/2024 | 2024 | 9 | 3 | 95 | 47 | 69 | 58 | 26 | 2958 |
| 9/4/2024 | 2024 | 9 | 4 | 96 | 43 | 74 | 58.5 | 26.5 | 2984.5 |
| 9/5/2024 | 2024 | 9 | 5 | 97 | 47 | 78 | 62.5 | 30.5 | 3015 |
| 9/6/2024 | 2024 | 9 | 6 | 98 | 46 | 78 | 62 | 30 | 3045 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 9/7/2024 | 2024 | 9 | 7 | 99 | 48 | 71 | 59.5 | 27.5 | 3072.5 |
| 9/8/2024 | 2024 | 9 | 8 | 100 | 45 | 72 | 58.5 | 26.5 | 3099 |
| 9/9/2024 | 2024 | 9 | 9 | 101 | 47 | 74 | 60.5 | 28.5 | 3127.5 |
| 9/10/2024 | 2024 | 9 | 10 | 102 | 48 | 75 | 61.5 | 29.5 | 3157 |
| 9/11/2024 | 2024 | 9 | 11 | 103 | 46 | 73 | 59.5 | 27.5 | 3184.5 |
| 9/12/2024 | 2024 | 9 | 12 | 104 | 47 | 74 | 60.5 | 28.5 | 3213 |
| 9/13/2024 | 2024 | 9 | 13 | 105 | 47 | 75 | 61 | 29 | 3242 |
| 9/14/2024 | 2024 | 9 | 14 | 106 | 46 | 71 | 58.5 | 26.5 | 3268.5 |
| 9/15/2024 | 2024 | 9 | 15 | 107 | 44 | 75 | 59.5 | 27.5 | 3296 |
| 9/16/2024 | 2024 | 9 | 16 | 108 | 46 | 66 | 56 | 24 | 3320 |
| 9/17/2024 | 2024 | 9 | 17 | 109 | 48 | 64 | 56 | 24 | 3344 |
| 9/18/2024 | 2024 | 9 | 18 | 110 | 48 | 61 | 54.5 | 22.5 | 3366.5 |
| 9/19/2024 | 2024 | 9 | 19 | 111 | 40 | 65 | 52.5 | 20.5 | 3387 |
| 9/20/2024 | 2024 | 9 | 20 | 112 | 38 | 69 | 53.5 | 21.5 | 3408.5 |
| 9/21/2024 | 2024 | 9 | 21 | 113 | 38 | 71 | 54.5 | 22.5 | 3431 |
| 9/22/2024 | 2024 | 9 | 22 | 114 | 34 | 62 | 48 | 16 | 3447 |
| 9/23/2024 | 2024 | 9 | 23 | 115 | 33 | 61 | 47 | 15 | 3462 |
| 9/24/2024 | 2024 | 9 | 24 | 116 | 36 | 65 | 50.5 | 18.5 | 3480.5 |
| 9/25/2024 | 2024 | 9 | 25 | 117 | 38 | 70 | 54 | 22 | 3502.5 |
| 9/26/2024 | 2024 | 9 | 26 | 118 | 45 | 74 | 59.5 | 27.5 | 3530 |
| 9/27/2024 | 2024 | 9 | 27 | 119 | 46 | 75 | 60.5 | 28.5 | 3558.5 |
| 9/28/2024 | 2024 | 9 | 28 | 120 | 45 | 77 | 61 | 29 | 3587.5 |
| 9/29/2024 | 2024 | 9 | 29 | 121 | 45 | 78 | 61.5 | 29.5 | 3617 |
| 9/30/2024 | 2024 | 9 | 30 | 122 | 48 | 75 | 61.5 | 29.5 | 3646.5 |
| 10/1/2024 | 2024 | 10 | 1 | 123 | 47 | 76 | 61.5 | 29.5 | 3676 |
| 10/2/2024 | 2024 | 10 | 2 | 124 | 45 | 74 | 59.5 | 27.5 | 3703.5 |
| 10/3/2024 | 2024 | 10 | 3 | 125 | 44 | 74 | 59 | 27 | 3730.5 |
| 10/4/2024 | 2024 | 10 | 4 | 126 | 43 | 74 | 58.5 | 26.5 | 3757 |
| 10/5/2024 | 2024 | 10 | 5 | 127 | 43 | 76 | 59.5 | 27.5 | 3784.5 |
| 10/6/2024 | 2024 | 10 | 6 | 128 | 42 | 74 | 58 | 26 | 3810.5 |
| 10/7/2024 | 2024 | 10 | 7 | 129 | 41 | 73 | 57 | 25 | 3835.5 |
| 10/8/2024 | 2024 | 10 | 8 | 130 | 42 | 72 | 57 | 25 | 3860.5 |
| 10/9/2024 | 2024 | 10 | 9 | 131 | 40 | 71 | 55.5 | 23.5 | 3884 |
| 10/10/2024 | 2024 | 10 | 10 | 132 | 42 | 71 | 56.5 | 24.5 | 3908.5 |
| 10/11/2024 | 2024 | 10 | 11 | 133 | 41 | 70 | 55.5 | 23.5 | 3932 |
| 10/12/2024 | 2024 | 10 | 12 | 134 | 41 | 72 | 56.5 | 24.5 | 3956.5 |
| 10/13/2024 | 2024 | 10 | 13 | 135 | 43 | 71 | 57 | 25 | 3981.5 |
| 10/14/2024 | 2024 | 10 | 14 | 136 | 42 | 72 | 57 | 25 | 4006.5 |
| 10/15/2024 | 2024 | 10 | 15 | 137 | 43 | 70 | 56.5 | 24.5 | 4031 |
| 10/16/2024 | 2024 | 10 | 16 | 138 | 40 | 65 | 52.5 | 20.5 | 4051.5 |
| 10/17/2024 | 2024 | 10 | 17 | 139 | 39 | 60 | 49.5 | 17.5 | 4069 |
| 10/18/2024 | 2024 | 10 | 18 | 140 | 39 | 60 | 49.5 | 17.5 | 4086.5 |
| 10/19/2024 | 2024 | 10 | 19 | 141 | 29 | 57 | 43 | 11 | 4097.5 |
| 10/20/2024 | 2024 | 10 | 20 | 142 | 28 | 38 | 33 | 1 | 4098.5 |
| 10/21/2024 | 2024 | 10 | 21 | 143 | 29 | 49 | 39 | 7 | 4105.5 |
| 10/22/2024 | 2024 | 10 | 22 | 144 | 27 | 56 | 41.5 | 9.5 | 4115 |
| 10/23/2024 | 2024 | 10 | 23 | 145 | 28 | 63 | 45.5 | 13.5 | 4128.5 |
| 10/24/2024 | 2024 | 10 | 24 | 146 | 33 | 65 | 49 | 17 | 4145.5 |
| 10/25/2024 | 2024 | 10 | 25 | 147 | 36 | 64 | 50 | 18 | 4163.5 |
| 10/26/2024 | 2024 | 10 | 26 | 148 | 35 | 67 | 51 | 19 | 4182.5 |
| 10/27/2024 | 2024 | 10 | 27 | 149 | 37 | 67 | 52 | 20 | 4202.5 |
| 10/28/2024 | 2024 | 10 | 28 | 150 | 40 | 66 | 53 | 21 | 4223.5 |
| 10/29/2024 | 2024 | 10 | 29 | 151 | 40 | 63 | 51.5 | 19.5 | 4243 |
| 10/30/2024 | 2024 | 10 | 30 | 152 | 40 | 47 | 43.5 | 11.5 | 4254.5 |
| 10/31/2024 | 2024 | 10 | 31 | 153 | 21 | 39 | 30 | -2 | 4252.5 |
| 11/1/2024 | 2024 | 11 | 1 | 154 | 20 | 51 | 35.5 | 3.5 | 4256 |
| 11/2/2024 | 2024 | 11 | 2 | 155 | 26 | 54 | 40 | 8 | 4264 |
| 11/3/2024 | 2024 | 11 | 3 | 156 | 28 | 53 | 40.5 | 8.5 | 4272.5 |
| 11/4/2024 | 2024 | 11 | 4 | 157 | 28 | 37 | 32.5 | 0.5 | 4273 |
| 11/5/2024 | 2024 | 11 | 5 | 158 | 20 | 31 | 25.5 | -6.5 | 4266.5 |
| 11/6/2024 | 2024 | 11 | 6 | 159 | 20 | 41 | 30.5 | -1.5 | 4265 |
| 11/7/2024 | 2024 | 11 | 7 | 160 | 9 | 28 | 18.5 | -13.5 | 4251.5 |
| 11/8/2024 | 2024 | 11 | 8 | 161 | 18 | 29 | 23.5 | -8.5 | 4243 |
| 11/9/2024 | 2024 | 11 | 9 | 162 | 18 | 29 | 23.5 | -8.5 | 4234.5 |
| 11/10/2024 | 2024 | 11 | 10 | 163 | 19 | 39 | 29 | -3 | 4231.5 |
| 11/11/2024 | 2024 | 11 | 11 | 164 | 22 | 54 | 38 | 6 | 4237.5 |
| 11/12/2024 | 2024 | 11 | 12 | 165 | 22 | 51 | 36.5 | 4.5 | 4242 |
| 11/13/2024 | 2024 | 11 | 13 | 166 | 23 | 44 | 33.5 | 1.5 | 4243.5 |
| 11/14/2024 | 2024 | 11 | 14 | 167 | 18 | 50 | 34 | 2 | 4245.5 |
| 11/15/2024 | 2024 | 11 | 15 | 168 | 29 | 56 | 42.5 | 10.5 | 4256 |
| 11/16/2024 | 2024 | 11 | 16 | 169 | 29 | 56 | 42.5 | 10.5 | 4266.5 |
| 11/17/2024 | 2024 | 11 | 17 | 170 | 20 | 39 | 29.5 | -2.5 | 4264 |
| 11/18/2024 | 2024 | 11 | 18 | 171 | 18 | 42 | 30 | -2 | 4262 |
| 11/19/2024 | 2024 | 11 | 19 | 172 | 18 | 39 | 28.5 | -3.5 | 4258.5 |
| 11/20/2024 | 2024 | 11 | 20 | 173 | 15 | 35 | 25 | -7 | 4251.5 |
| 11/21/2024 | 2024 | 11 | 21 | 174 | 16 | 47 | 31.5 | -0.5 | 4251 |
| 11/22/2024 | 2024 | 11 | 22 | 175 | 21 | 56 | 38.5 | 6.5 | 4257.5 |
| 11/23/2024 | 2024 | 11 | 23 | 176 | 25 | 58 | 41.5 | 9.5 | 4267 |
| 11/24/2024 | 2024 | 11 | 24 | 177 | 29 | 55 | 42 | 10 | 4277 |
| 11/25/2024 | 2024 | 11 | 25 | 178 | 34 | 50 | 42 | 10 | 4287 |
| 11/26/2024 | 2024 | 11 | 26 | 179 | 26 | 47 | 36.5 | 4.5 | 4291.5 |
| 11/27/2024 | 2024 | 11 | 27 | 180 | 26 | 47 | 36.5 | 4.5 | 4296 |
| 11/28/2024 | 2024 | 11 | 28 | 181 | 26 | 40 | 33 | 1 | 4297 |
| 11/29/2024 | 2024 | 11 | 29 | 182 | 11 | 35 | 23 | -9 | 4288 |
| 11/30/2024 | 2024 | 11 | 30 | 183 | 9 | 40 | 24.5 | -7.5 | 4280.5 |
| 12/1/2024 | 2024 | 12 | 1 | 184 | 15 | 48 | 31.5 | -0.5 | 4280 |
| 12/2/2024 | 2024 | 12 | 2 | 185 | 20 | 52 | 36 | 4 | 4284 |
| 12/3/2024 | 2024 | 12 | 3 | 186 | 24 | 51 | 37.5 | 5.5 | 4289.5 |
| 12/4/2024 | 2024 | 12 | 4 | 187 | 27 | 50 | 38.5 | 6.5 | 4296 |
| 12/5/2024 | 2024 | 12 | 5 | 188 | 25 | 47 | 36 | 4 | 4300 |
| 12/6/2024 | 2024 | 12 | 6 | 189 | 25 | 46 | 35.5 | 3.5 | 4303.5 |
| 12/7/2024 | 2024 | 12 | 7 | 190 | 24 | 44 | 34 | 2 | 4305.5 |
| 12/8/2024 | 2024 | 12 | 8 | 191 | 23 | 45 | 34 | 2 | 4307.5 |


| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 12/9/2024 | 2024 | 12 | 9 | 192 | 23 | 44 | 33.5 | 1.5 | 4309 |
| 12/10/2024 | 2024 | 12 | 10 | 193 | 14 | 38 | 26 | -6 | 4303 |
| 12/11/2024 | 2024 | 12 | 11 | 194 | 11 | 30 | 20.5 | -11.5 | 4291.5 |
| 12/12/2024 | 2024 | 12 | 12 | 195 | 15 | 41 | 28 | -4 | 4287.5 |
| 12/13/2024 | 2024 | 12 | 13 | 196 | 26 | 50 | 38 | 6 | 4293.5 |
| 12/14/2024 | 2024 | 12 | 14 | 197 | 24 | 37 | 30.5 | -1.5 | 4292 |
| 12/15/2024 | 2024 | 12 | 15 | 198 | 20 | 49 | 34.5 | 2.5 | 4294.5 |
| 12/16/2024 | 2024 | 12 | 16 | 199 | 21 | 44 | 32.5 | 0.5 | 4295 |
| 12/17/2024 | 2024 | 12 | 17 | 200 | 22 | 52 | 37 | 5 | 4300 |
| 12/18/2024 | 2024 | 12 | 18 | 201 | 24 | 48 | 36 | 4 | 4304 |
| 12/19/2024 | 2024 | 12 | 19 | 202 | 22 | 53 | 37.5 | 5.5 | 4309.5 |
| 12/20/2024 | 2024 | 12 | 20 | 203 | 25 | 54 | 39.5 | 7.5 | 4317 |
| 12/21/2024 | 2024 | 12 | 21 | 204 | 28 | 55 | 41.5 | 9.5 | 4326.5 |
| 12/22/2024 | 2024 | 12 | 22 | 205 | 26 | 56 | 41 | 9 | 4335.5 |
| 12/23/2024 | 2024 | 12 | 23 | 206 | 27 | 51 | 39 | 7 | 4342.5 |
| 12/24/2024 | 2024 | 12 | 24 | 207 | 28 | 48 | 38 | 6 | 4348.5 |
| 12/25/2024 | 2024 | 12 | 25 | 208 | 28 | 49 | 38.5 | 6.5 | 4355 |
| 12/26/2024 | 2024 | 12 | 26 | 209 | 20 | 38 | 29 | -3 | 4352 |
| 12/27/2024 | 2024 | 12 | 27 | 210 | 17 | 38 | 27.5 | -4.5 | 4347.5 |
| 12/28/2024 | 2024 | 12 | 28 | 211 | 27 | 38 | 32.5 | 0.5 | 4348 |
| 12/29/2024 | 2024 | 12 | 29 | 212 | 24 | 46 | 35 | 3 | 4351 |
| 12/30/2024 | 2024 | 12 | 30 | 213 | 24 | 52 | 38 | 6 | 4357 |
| 12/31/2024 | 2024 | 12 | 31 | 214 | 23 | 45 | 34 | 2 | 4359 |
| 1/1/2025 | 2025 | 1 | 1 | 215 | 23 | 41 | 32 | 0 | 4359 |
| 1/2/2025 | 2025 | 1 | 2 | 216 | 18 | 43 | 30.5 | -1.5 | 4357.5 |
| 1/3/2025 | 2025 | 1 | 3 | 217 | 26 | 50 | 38 | 6 | 4363.5 |
| 1/4/2025 | 2025 | 1 | 4 | 218 | 26 | 52 | 39 | 7 | 4370.5 |
| 1/5/2025 | 2025 | 1 | 5 | 219 | 26 | 44 | 35 | 3 | 4373.5 |
| 1/6/2025 | 2025 | 1 | 6 | 220 | 14 | 36 | 25 | -7 | 4366.5 |
| 1/7/2025 | 2025 | 1 | 7 | 221 | 14 | 39 | 26.5 | -5.5 | 4361 |
| 1/8/2025 | 2025 | 1 | 8 | 222 | 14 | 34 | 24 | -8 | 4353 |
| 1/9/2025 | 2025 | 1 | 9 | 223 | 13 | 30 | 21.5 | -10.5 | 4342.5 |
| 1/10/2025 | 2025 | 1 | 10 | 224 | 11 | 24 | 17.5 | -14.5 | 4328 |
| 1/11/2025 | 2025 | 1 | 11 | 225 | 5 | 31 | 18 | -14 | 4314 |
| 1/12/2025 | 2025 | 1 | 12 | 226 | 12 | 38 | 25 | -7 | 4307 |
| 1/13/2025 | 2025 | 1 | 13 | 227 | 4 | 29 | 16.5 | -15.5 | 4291.5 |
| 1/14/2025 | 2025 | 1 | 14 | 228 | 7 | 28 | 17.5 | -14.5 | 4277 |
| 1/15/2025 | 2025 | 1 | 15 | 229 | 4 | 28 | 16 | -16 | 4261 |
| 1/16/2025 | 2025 | 1 | 16 | 230 | 6 | 38 | 22 | -10 | 4251 |
| 1/17/2025 | 2025 | 1 | 17 | 231 | 16 | 48 | 32 | 0 | 4251 |
| 1/18/2025 | 2025 | 1 | 18 | 232 | 16 | 34 | 25 | -7 | 4244 |
| 1/19/2025 | 2025 | 1 | 19 | 233 | 4 | 30 | 17 | -15 | 4229 |
| 1/20/2025 | 2025 | 1 | 20 | 234 | 0 | 29 | 14.5 | -17.5 | 4211.5 |
| 1/21/2025 | 2025 | 1 | 21 | 235 | 1 | 29 | 15 | -17 | 4194.5 |
| 1/22/2025 | 2025 | 1 | 22 | 236 | -4 | 33 | 14.5 | -17.5 | 4177 |
| 1/23/2025 | 2025 | 1 | 23 | 237 | 4 | 34 | 19 | -13 | 4164 |
| 1/24/2025 | 2025 | 1 | 24 | 238 | 4 | 34 | 19 | -13 | 4151 |
| 1/25/2025 | 2025 | 1 | 25 | 239 | 8 | 44 | 26 | -6 | 4145 |
| 1/26/2025 | 2025 | 1 | 26 | 240 | 8 | 42 | 25 | -7 | 4138 |
| 1/27/2025 | 2025 | 1 | 27 | 241 | 8 | 42 | 25 | -7 | 4131 |
| 1/28/2025 | 2025 | 1 | 28 | 242 | 15 | 43 | 29 | -3 | 4128 |
| 1/29/2025 | 2025 | 1 | 29 | 243 | 14 | 41 | 27.5 | -4.5 | 4123.5 |
| 1/30/2025 | 2025 | 1 | 30 | 244 | 15 | 26 | 20.5 | -11.5 | 4112 |
| 1/31/2025 | 2025 | 1 | 31 | 245 | 17 | 37 | 27 | -5 | 4107 |
| 2/1/2025 | 2025 | 2 | 1 | 246 | 14 | 49 | 31.5 | -0.5 | 4106.5 |
| 2/2/2025 | 2025 | 2 | 2 | 247 | 26 | 49 | 37.5 | 5.5 | 4112 |
| 2/3/2025 | 2025 | 2 | 3 | 248 | 33 | 57 | 45 | 13 | 4125 |
| 2/4/2025 | 2025 | 2 | 4 | 249 | 33 | 62 | 47.5 | 15.5 | 4140.5 |
| 2/5/2025 | 2025 | 2 | 5 | 250 | 33 | 58 | 45.5 | 13.5 | 4154 |
| 2/6/2025 | 2025 | 2 | 6 | 251 | 29 | 53 | 41 | 9 | 4163 |
| 2/7/2025 | 2025 | 2 | 7 | 252 | 25 | 56 | 40.5 | 8.5 | 4171.5 |
| 2/8/2025 | 2025 | 2 | 8 | 253 | 37 | 55 | 46 | 14 | 4185.5 |
| 2/9/2025 | 2025 | 2 | 9 | 254 | 33 | 52 | 42.5 | 10.5 | 4196 |
| 2/10/2025 | 2025 | 2 | 10 | 255 | 27 | 50 | 38.5 | 6.5 | 4202.5 |
| 2/11/2025 | 2025 | 2 | 11 | 256 | 27 | 50 | 38.5 | 6.5 | 4209 |
| 2/12/2025 | 2025 | 2 | 12 | 257 | 27 | 42 | 34.5 | 2.5 | 4211.5 |
| 2/13/2025 | 2025 | 2 | 13 | 258 | 18 | 33 | 25.5 | -6.5 | 4205 |
| 2/14/2025 | 2025 | 2 | 14 | 259 | 13 | 42 | 27.5 | -4.5 | 4200.5 |
| 2/15/2025 | 2025 | 2 | 15 | 260 | 13 | 34 | 23.5 | -8.5 | 4192 |
| 2/16/2025 | 2025 | 2 | 16 | 261 | 21 | 31 | 26 | -6 | 4186 |
| 2/17/2025 | 2025 | 2 | 17 | 262 | 13 | 45 | 29 | -3 | 4183 |
| 2/18/2025 | 2025 | 2 | 18 | 263 | 13 | 47 | 30 | -2 | 4181 |
| 2/19/2025 | 2025 | 2 | 19 | 264 | 19 | 40 | 29.5 | -2.5 | 4178.5 |
| 2/20/2025 | 2025 | 2 | 20 | 265 | 16 | 45 | 30.5 | -1.5 | 4177 |
| 2/21/2025 | 2025 | 2 | 21 | 266 | 22 | 47 | 34.5 | 2.5 | 4179.5 |
| 2/22/2025 | 2025 | 2 | 22 | 267 | 18 | 42 | 30 | -2 | 4177.5 |
| 2/23/2025 | 2025 | 2 | 23 | 268 | 16 | 46 | 31 | -1 | 4176.5 |
| 2/24/2025 | 2025 | 2 | 24 | 269 | 23 | 53 | 38 | 6 | 4182.5 |
| 2/25/2025 | 2025 | 2 | 25 | 270 | 29 | 57 | 43 | 11 | 4193.5 |
| 2/26/2025 | 2025 | 2 | 26 | 271 | 29 | 57 | 43 | 11 | 4204.5 |
| 2/27/2025 | 2025 | 2 | 27 | 272 | 23 | 52 | 37.5 | 5.5 | 4210 |
| 2/28/2025 | 2025 | 2 | 28 | 273 | 18 | 43 | 30.5 | -1.5 | 4208.5 |
| 3/1/2025 | 2025 | 3 | 1 | 274 | 23 | 52 | 37.5 | 5.5 | 4214 |
| 3/2/2025 | 2025 | 3 | 2 | 275 | 26 | 58 | 42 | 10 | 4224 |
| 3/3/2025 | 2025 | 3 | 3 | 276 | 26 | 48 | 37 | 5 | 4229 |
| 3/4/2025 | 2025 | 3 | 4 | 277 | 21 | 35 | 28 | -4 | 4225 |
| 3/5/2025 | 2025 | 3 | 5 | 278 | 20 | 37 | 28.5 | -3.5 | 4221.5 |
| 3/6/2025 | 2025 | 3 | 6 | 279 | 20 | 48 | 34 | 2 | 4223.5 |
| 3/7/2025 | 2025 | 3 | 7 | 280 | 20 | 42 | 31 | -1 | 4222.5 |
| 3/8/2025 | 2025 | 3 | 8 | 281 | 20 | 36 | 28 | -4 | 4218.5 |
| 3/9/2025 | 2025 | 3 | 9 | 282 | 16 | 32 | 24 | -8 | 4210.5 |
| 3/10/2025 | 2025 | 3 | 10 | 283 | 13 | 48 | 30.5 | -1.5 | 4209 |
| 3/11/2025 | 2025 | 3 | 11 | 284 | 22 | 55 | 38.5 | 6.5 | 4215.5 |


| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 3/12/2025 | 2025 | 3 | 12 | 285 | 24 | 49 | 36.5 | 4.5 | 4220 |
| 3/13/2025 | 2025 | 3 | 13 | 286 | 24 | 41 | 32.5 | 0.5 | 4220.5 |
| 3/14/2025 | 2025 | 3 | 14 | 287 | 19 | 49 | 34 | 2 | 4222.5 |
| 3/15/2025 | 2025 | 3 | 15 | 288 | 16 | 26 | 21 | -11 | 4211.5 |
| 3/16/2025 | 2025 | 3 | 16 | 289 | 19 | 31 | 25 | -7 | 4204.5 |
| 3/17/2025 | 2025 | 3 | 17 | 290 | 16 | 47 | 31.5 | -0.5 | 4204 |
| 3/18/2025 | 2025 | 3 | 18 | 291 | 16 | 58 | 37 | 5 | 4209 |
| 3/19/2025 | 2025 | 3 | 19 | 292 | 16 | 40 | 28 | -4 | 4205 |
| 3/20/2025 | 2025 | 3 | 20 | 293 | 12 | 35 | 23.5 | -8.5 | 4196.5 |
| 3/21/2025 | 2025 | 3 | 21 | 294 | 12 | 49 | 30.5 | -1.5 | 4195 |
| 3/22/2025 | 2025 | 3 | 22 | 295 | 25 | 50 | 37.5 | 5.5 | 4200.5 |
| 3/23/2025 | 2025 | 3 | 23 | 296 | 29 | 52 | 40.5 | 8.5 | 4209 |
| 3/24/2025 | 2025 | 3 | 24 | 297 | 29 | 52 | 40.5 | 8.5 | 4217.5 |
| 3/25/2025 | 2025 | 3 | 25 | 298 | 28 | 61 | 44.5 | 12.5 | 4230 |
| 3/26/2025 | 2025 | 3 | 26 | 299 | 30 | 65 | 47.5 | 15.5 | 4245.5 |
| 3/27/2025 | 2025 | 3 | 27 | 300 | 34 | 64 | 49 | 17 | 4262.5 |
| 3/28/2025 | 2025 | 3 | 28 | 301 | 34 | 64 | 49 | 17 | 4279.5 |
| 3/29/2025 | 2025 | 3 | 29 | 302 | 34 | 58 | 46 | 14 | 4293.5 |
| 3/30/2025 | 2025 | 3 | 30 | 303 | 29 | 50 | 39.5 | 7.5 | 4301 |
| 3/31/2025 | 2025 | 3 | 31 | 304 | 26 | 50 | 38 | 6 | 4307 |
| 4/1/2025 | 2025 | 4 | 1 | 305 | 26 | 56 | 41 | 9 | 4316 |
| 4/2/2025 | 2025 | 4 | 2 | 306 | 18 | 46 | 32 | 0 | 4316 |
| 4/3/2025 | 2025 | 4 | 3 | 307 | 16 | 36 | 26 | -6 | 4310 |
| 4/4/2025 | 2025 | 4 | 4 | 308 | 20 | 35 | 27.5 | -4.5 | 4305.5 |
| 4/5/2025 | 2025 | 4 | 5 | 309 | 20 | 37 | 28.5 | -3.5 | 4302 |
| 4/6/2025 | 2025 | 4 | 6 | 310 | 17 | 32 | 24.5 | -7.5 | 4294.5 |
| 4/7/2025 | 2025 | 4 | 7 | 311 | 16 | 45 | 30.5 | -1.5 | 4293 |
| 4/8/2025 | 2025 | 4 | 8 | 312 | 22 | 55 | 38.5 | 6.5 | 4299.5 |
| 4/9/2025 | 2025 | 4 | 9 | 313 | 28 | 61 | 44.5 | 12.5 | 4312 |
| 4/10/2025 | 2025 | 4 | 10 | 314 | 34 | 66 | 50 | 18 | 4330 |
| 4/11/2025 | 2025 | 4 | 11 | 315 | 33 | 69 | 51 | 19 | 4349 |
| 4/12/2025 | 2025 | 4 | 12 | 316 | 36 | 72 | 54 | 22 | 4371 |
| 4/13/2025 | 2025 | 4 | 13 | 317 | 37 | 69 | 53 | 21 | 4392 |
| 4/14/2025 | 2025 | 4 | 14 | 318 | 46 | 61 | 53.5 | 21.5 | 4413.5 |
| 4/15/2025 | 2025 | 4 | 15 | 319 | 38 | 64 | 51 | 19 | 4432.5 |
| 4/16/2025 | 2025 | 4 | 16 | 320 | 36 | 66 | 51 | 19 | 4451.5 |
| 4/17/2025 | 2025 | 4 | 17 | 321 | 36 | 67 | 51.5 | 19.5 | 4471 |
| 4/18/2025 | 2025 | 4 | 18 | 322 | 36 | 58 | 47 | 15 | 4486 |
| 4/19/2025 | 2025 | 4 | 19 | 323 | 26 | 48 | 37 | 5 | 4491 |
| 4/20/2025 | 2025 | 4 | 20 | 324 | 21 | 32 | 26.5 | -5.5 | 4485.5 |
| 4/21/2025 | 2025 | 4 | 21 | 325 | 21 | 50 | 35.5 | 3.5 | 4489 |
| 4/22/2025 | 2025 | 4 | 22 | 326 | 26 | 58 | 42 | 10 | 4499 |
| 4/23/2025 | 2025 | 4 | 23 | 327 | 30 | 63 | 46.5 | 14.5 | 4513.5 |
| 4/24/2025 | 2025 | 4 | 24 | 328 | 34 | 64 | 49 | 17 | 4530.5 |
| 4/25/2025 | 2025 | 4 | 25 | 329 | 34 | 62 | 48 | 16 | 4546.5 |
| 4/26/2025 | 2025 | 4 | 26 | 330 | 31 | 66 | 48.5 | 16.5 | 4563 |
| 4/27/2025 | 2025 | 4 | 27 | 331 | 30 | 66 | 48 | 16 | 4579 |
| 4/28/2025 | 2025 | 4 | 28 | 332 | 30 | 60 | 45 | 13 | 4592 |
| 4/29/2025 | 2025 | 4 | 29 | 333 | 26 | 54 | 40 | 8 | 4600 |
| 4/30/2025 | 2025 | 4 | 30 | 334 | 28 | 55 | 41.5 | 9.5 | 4609.5 |
| 5/1/2025 | 2025 | 5 | 1 | 335 | 28 | 58 | 43 | 11 | 4620.5 |
| 5/2/2025 | 2025 | 5 | 2 | 336 | 33 | 57 | 45 | 13 | 4633.5 |
| 5/3/2025 | 2025 | 5 | 3 | 337 | 31 | 58 | 44.5 | 12.5 | 4646 |
| 5/4/2025 | 2025 | 5 | 4 | 338 | 31 | 61 | 46 | 14 | 4660 |
| 5/5/2025 | 2025 | 5 | 5 | 339 | 31 | 52 | 41.5 | 9.5 | 4669.5 |
| 5/6/2025 | 2025 | 5 | 6 | 340 | 26 | 46 | 36 | 4 | 4673.5 |
| 5/7/2025 | 2025 | 5 | 7 | 341 | 27 | 44 | 35.5 | 3.5 | 4677 |
| 5/8/2025 | 2025 | 5 | 8 | 342 | 33 | 49 | 41 | 9 | 4686 |
| 5/9/2025 | 2025 | 5 | 9 | 343 | 30 | 57 | 43.5 | 11.5 | 4697.5 |
| 5/10/2025 | 2025 | 5 | 10 | 344 | 32 | 64 | 48 | 16 | 4713.5 |
| 5/11/2025 | 2025 | 5 | 11 | 345 | 37 | 65 | 51 | 19 | 4732.5 |
| 5/12/2025 | 2025 | 5 | 12 | 346 | 37 | 65 | 51 | 19 | 4751.5 |
| 5/13/2025 | 2025 | 5 | 13 | 347 | 42 | 67 | 54.5 | 22.5 | 4774 |
| 5/14/2025 | 2025 | 5 | 14 | 348 | 32 | 55 | 43.5 | 11.5 | 4785.5 |
| 5/15/2025 | 2025 | 5 | 15 | 349 | 26 | 58 | 42 | 10 | 4795.5 |
| 5/16/2025 | 2025 | 5 | 16 | 350 | 31 | 65 | 48 | 16 | 4811.5 |
| 5/17/2025 | 2025 | 5 | 17 | 351 | 34 | 66 | 50 | 18 | 4829.5 |
| 5/18/2025 | 2025 | 5 | 18 | 352 | 38 | 53 | 45.5 | 13.5 | 4843 |
| 5/19/2025 | 2025 | 5 | 19 | 353 | 28 | 50 | 39 | 7 | 4850 |
| 5/20/2025 | 2025 | 5 | 20 | 354 | 24 | 63 | 43.5 | 11.5 | 4861.5 |
| 5/21/2025 | 2025 | 5 | 21 | 355 | 34 | 72 | 53 | 21 | 4882.5 |
| 5/22/2025 | 2025 | 5 | 22 | 356 | 39 | 76 | 57.5 | 25.5 | 4908 |
| 5/23/2025 | 2025 | 5 | 23 | 357 | 39 | 74 | 56.5 | 24.5 | 4932.5 |
| 5/24/2025 | 2025 | 5 | 24 | 358 | 38 | 72 | 55 | 23 | 4955.5 |
| 5/25/2025 | 2025 | 5 | 25 | 359 | 42 | 70 | 56 | 24 | 4979.5 |
| 5/26/2025 | 2025 | 5 | 26 | 360 | 41 | 69 | 55 | 23 | 5002.5 |
| 5/27/2025 | 2025 | 5 | 27 | 361 | 40 | 72 | 56 | 24 | 5026.5 |
| 5/28/2025 | 2025 | 5 | 28 | 362 | 40 | 72 | 56 | 24 | 5050.5 |
| 5/29/2025 | 2025 | 5 | 29 | 363 | 40 | 72 | 56 | 24 | 5074.5 |
| 5/30/2025 | 2025 | 5 | 30 | 364 | 43 | 76 | 59.5 | 27.5 | 5102 |
| 5/31/2025 | 2025 | 5 | 31 | 365 | 52 | 76 | 64 | 32 | 5134 |
| 6/1/2025 | 2025 | 6 | 1 | 1 | 50 | 80 | 65 | 33 | 33 |
| 6/2/2025 | 2025 | 6 | 2 | 2 | 47 | 63 | 55 | 23 | 56 |
| 6/3/2025 | 2025 | 6 | 3 | 3 | 44 | 69 | 56.5 | 24.5 | 80.5 |
| 6/4/2025 | 2025 | 6 | 4 | 4 | 42 | 62 | 52 | 20 | 100.5 |
| 6/5/2025 | 2025 | 6 | 5 | 5 | 39 | 67 | 53 | 21 | 121.5 |
| 6/6/2025 | 2025 | 6 | 6 | 6 | 40 | 74 | 57 | 25 | 146.5 |
| 6/7/2025 | 2025 | 6 | 7 | 7 | 42 | 78 | 60 | 28 | 174.5 |
| 6/8/2025 | 2025 | 6 | 8 | 8 | 44 | 78 | 61 | 29 | 203.5 |
| 6/9/2025 | 2025 | 6 | 9 | 9 | 45 | 74 | 59.5 | 27.5 | 231 |
| 6/10/2025 | 2025 | 6 | 10 | 10 | 46 | 74 | 60 | 28 | 259 |
| 6/11/2025 | 2025 | 6 | 11 | 11 | 47 | 77 | 62 | 30 | 289 |
| 6/12/2025 | 2025 | 6 | 12 | 12 | 51 | 80 | 65.5 | 33.5 | 322.5 |


| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6/13/2025 | 2025 | 6 | 13 | 13 | 51 | 80 | 65.5 | 33.5 | 356 |
| 6/14/2025 | 2025 | 6 | 14 | 14 | 45 | 83 | 64 | 32 | 388 |
| 6/15/2025 | 2025 | 6 | 15 | 15 | 47 | 85 | 66 | 34 | 422 |
| 6/16/2025 | 2025 | 6 | 16 | 16 | 51 | 85 | 68 | 36 | 458 |
| 6/17/2025 | 2025 | 6 | 17 | 17 | 48 | 81 | 64.5 | 32.5 | 490.5 |
| 6/18/2025 | 2025 | 6 | 18 | 18 | 47 | 84 | 65.5 | 33.5 | 524 |
| 6/19/2025 | 2025 | 6 | 19 | 19 | 52 | 86 | 69 | 37 | 561 |
| 6/20/2025 | 2025 | 6 | 20 | 20 | 53 | 85 | 69 | 37 | 598 |
| 6/21/2025 | 2025 | 6 | 21 | 21 | 56 | 80 | 68 | 36 | 634 |
| 6/22/2025 | 2025 | 6 | 22 | 22 | 49 | 75 | 62 | 30 | 664 |
| 6/23/2025 | 2025 | 6 | 23 | 23 | 42 | 78 | 60 | 28 | 692 |
| 6/24/2025 | 2025 | 6 | 24 | 24 | 46 | 77 | 61.5 | 29.5 | 721.5 |
| 6/25/2025 | 2025 | 6 | 25 | 25 | 48 | 73 | 60.5 | 28.5 | 750 |
| 6/26/2025 | 2025 | 6 | 26 | 26 | 45 | 77 | 61 | 29 | 779 |
| 6/27/2025 | 2025 | 6 | 27 | 27 | 49 | 79 | 64 | 32 | 811 |
| 6/28/2025 | 2025 | 6 | 28 | 28 | 48 | 81 | 64.5 | 32.5 | 843.5 |
| 6/29/2025 | 2025 | 6 | 29 | 29 | 47 | 84 | 65.5 | 33.5 | 877 |
| 6/30/2025 | 2025 | 6 | 30 | 30 | 50 | 83 | 66.5 | 34.5 | 911.5 |
| 7/1/2025 | 2025 | 7 | 1 | 31 | 54 | 74 | 64 | 32 | 943.5 |
| 7/2/2025 | 2025 | 7 | 2 | 32 | 46 | 76 | 61 | 29 | 972.5 |
| 7/3/2025 | 2025 | 7 | 3 | 33 | 45 | 72 | 58.5 | 26.5 | 999 |
| 7/4/2025 | 2025 | 7 | 4 | 34 | 45 | 74 | 59.5 | 27.5 | 1026.5 |
| 7/5/2025 | 2025 | 7 | 5 | 35 | 48 | 82 | 65 | 33 | 1059.5 |
| 7/6/2025 | 2025 | 7 | 6 | 36 | 51 | 80 | 65.5 | 33.5 | 1093 |
| 7/7/2025 | 2025 | 7 | 7 | 37 | 54 | 84 | 69 | 37 | 1130 |
| 7/8/2025 | 2025 | 7 | 8 | 38 | 56 | 87 | 71.5 | 39.5 | 1169.5 |
| 7/9/2025 | 2025 | 7 | 9 | 39 | 51 | 86 | 68.5 | 36.5 | 1206 |
| 7/10/2025 | 2025 | 7 | 10 | 40 | 59 | 88 | 73.5 | 41.5 | 1247.5 |
| 7/11/2025 | 2025 | 7 | 11 | 41 | 54 | 85 | 69.5 | 37.5 | 1285 |
| 7/12/2025 | 2025 | 7 | 12 | 42 | 53 | 83 | 68 | 36 | 1321 |
| 7/13/2025 | 2025 | 7 | 13 | 43 | 51 | 86 | 68.5 | 36.5 | 1357.5 |
| 7/14/2025 | 2025 | 7 | 14 | 44 | 53 | 82 | 67.5 | 35.5 | 1393 |
| 7/15/2025 | 2025 | 7 | 15 | 45 | 51 | 81 | 66 | 34 | 1427 |
| 7/16/2025 | 2025 | 7 | 16 | 46 | 53 | 79 | 66 | 34 | 1461 |
| 7/17/2025 | 2025 | 7 | 17 | 47 | 49 | 79 | 64 | 32 | 1493 |
| 7/18/2025 | 2025 | 7 | 18 | 48 | 50 | 78 | 64 | 32 | 1525 |
| 7/19/2025 | 2025 | 7 | 19 | 49 | 52 | 74 | 63 | 31 | 1556 |


# ATTACHMENT D2
# FROST INDEX CALCULATIONS


# ATTACHMENT D2.1
# CUMULATIVE DEGREE DAY PLOTS



1975
Cumulative Degree Day
6000
5500
5000
4500
4000
3500
3000
2500
2000
1500
1000
500
0
0 20 40 60 80 100 120 140 160 180 200 220 240 260 280 300 320 340 360 380 400
Day in Frost Year



1976
Cumulative Degree Day
6000
5000
4000
3000
2000
1000
0
0 50 100 150 200 250 300 350 400
Day in Frost Year



1977
Cumulative Degree Day
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1978
Cumulative Degree Day
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1979
Cumulative Degree Day
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1980
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1981
Cumulative Degree Day
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1982
Cumulative Degree Day
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1983
Cumulative Degree Day
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1984
Cumulative Degree Day
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1985
Cumulative Degree Day
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1986
Cumulative Degree Day
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1987
Cumulative Degree Day
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1988
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1989
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1990
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1991
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1992
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1993
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1994
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1995
Cumulative Degree Day
9000
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1996
Cumulative Degree Day
9000
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1997
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1998
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



1999
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2000
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2001
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2002
Cumulative Degree Day
9000
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2003
Cumulative Degree Day
9000
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2004
Cumulative Degree Day
9000
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2005
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2006
Cumulative Degree Day
9000
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2007
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2008
Cumulative Degree Day
9000
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2009
Cumulative Degree Day
9000
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2010
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2011
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2012
Cumulative Degree Day
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
Day in Frost Year



2013
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2014
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2015
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2016
Cumulative Degree Day
8000
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
Day in Frost Year



2017
Cumulative Degree Day
7000
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2018
Cumulative Degree Day
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2019
Cumulative Degree Day
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year



2020
Cumulative Degree Day
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year


2021
Cumulative Degree Day
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year


2022
Cumulative Degree Day
5000
4500
4000
3500
3000
2500
2000
1500
1000
500
0
0
50
100
150
200
250
300
350
400
Day in Frost Year


2023
Cumulative Degree Day
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year


2024
Cumulative Degree Day
6000
5000
4000
3000
2000
1000
0
0
50
100
150
200
250
300
350
400
Day in Frost Year


2025
Cumulative Degree Day
1800
1600
1400
1200
1000
800
600
400
200
0
0
10
20
30
40
50
60
Day in Frost Year

# ATTACHMENT D2.2
# FROST INDEX DETERMINATION

| Results of Graphical analysis of Freeze Cumulative Degree Day Plots | | | | | | |
|---|---|---|---|---|---|---|
| | Beginning of Freeze | | End of Freeze | | | |
| Year | Days | Deg-Day | Days | Deg-Day | **Deg-Day** | **Days** |
| 1975 | 164 | 4682 | 243 | 4368 | 314 | 79 |
| 1976 | 179 | 4723 | 289 | 3937 | 786 | 110 |
| 1977 | 204 | 5209 | 270 | 5037 | 172 | 66 |
| 1978 | 186 | 5066 | 276 | 4342 | 724 | 90 |
| 1979 | 173 | 4889 | 265 | 4679 | 210 | 92 |
| 1980 | 170 | 5051 | 187 | 5023 | 28 | 17 |
| 1981 | 198 | 4996 | 268 | 4740 | 256 | 70 |
| 1982 | 186 | 4551 | 265 | 4165 | 386 | 79 |
| 1983 | 177 | 4737 | 279 | 4425 | 312 | 102 |
| 1984 | 182 | 4645 | 273 | 4216 | 429 | 91 |
| 1985 | 170 | 4739 | 228 | 4651 | 88 | 58 |
| 1986 | 203 | 4869 | 268 | 4773 | 96 | 65 |
| 1987 | 198 | 4987 | 241 | 4784 | 203 | 43 |
| 1988 | 185 | 5344 | 252 | 5091 | 253 | 67 |
| 1989 | 181 | 5262 | 251 | 5025 | 237 | 70 |
| 1990 | 183 | 5398 | 249 | 5020 | 378 | 66 |
| 1991 | 185 | 5185 | 238 | 5042 | 143 | 53 |
| 1992 | 177 | 5081 | 217 | 4828 | 253 | 40 |
| 1993 | 178 | 5071 | 215 | 4825 | 246 | 37 |
| 1994 | 200 | 5116 | 253 | 5070 | 46 | 53 |
| 1995 | 174 | 5459 | 225 | 5450 | 9 | 51 |
| 1996 | 201 | 5613 | 219 | 5576 | 37 | 18 |
| 1997 | 219 | 5524 | 238 | 5372 | 152 | 19 |
| 1998 | 190 | 5401 | 218 | 5293 | 108 | 28 |
| 1999 | 185 | 5495 | 203 | 5486 | 9 | 18 |
| 2000 | 187 | 5278 | 223 | 5114 | 164 | 36 |
| 2001 | 205 | 5469 | 249 | 5282 | 187 | 44 |
| 2002 | 185 | 5756 | 201 | 5741 | 15 | 16 |
| 2003 | 201 | 5772 | 215 | 5720 | 52 | 14 |
| 2004 | 246 | 6177 | 263 | 6139 | 38 | 17 |
| 2005 | 242 | 5316 | 262 | 5230 | 86 | 20 |
| 2006 | 186 | 5733 | 204 | 5696 | 37 | 18 |
| 2007 | 185 | 5527 | 252 | 5325 | 202 | 67 |
| 2008 | 203 | 5959 | 253 | 5799 | 160 | 50 |
| 2009 | 203 | 5729 | 214 | 5698 | 31 | 11 |
| 2010 | 186 | 5387 | 246 | 5241 | 146 | 60 |
| 2011 | 187 | 5744 | 231 | 5369 | 375 | 44 |
| 2012 | 124 | 4567 | 144 | 4398 | 169 | 20 |
| 2013 | 186 | 5168 | 204 | 5108 | 60 | 18 |
| 2014 | 202 | 5532 | 215 | 5429 | 103 | 13 |
| 2015 | 181 | 4910 | 223 | 4836 | 74 | 42 |
| 2016 | 180 | 5600 | 191 | 5592 | 8 | 11 |
| 2017 | 263 | 4836 | 279 | 4751 | 85 | 16 |

| | | | | | | |
|---|---|---|---|---|---|---|
| 2018 | 184 | 4273 | 273 | 3872 | 401 | 89 |
| 2019 | 178 | 4258 | 273 | 3928 | 330 | 95 |
| 2020 | 182 | 4549 | 279 | 4238 | 311 | 97 |
| 2021 | 196 | 4470 | 286 | 4163 | 307 | 90 |
| 2022 | 166 | 4062 | 277 | 3538 | 524 | 111 |
| 2023 | 175 | 4329 | 262 | 4017 | 312 | 87 |
| 2024 | 222 | 4342 | 246 | 4106 | 236 | 24 |

| These were calculate in accordance with step 1 of the Smith and Rager procedure | | | | | | |
|---|---|---|---|---|---|---|
| Freeze index | | | | | | |
| | | | | Avg. Temp (F) | F | |
| Year | Avg. Temp | (n) | % values | w/ 95% data | Degree-Day (F-day) | Duration (Days) |
| 1975 | 47.43 | 366 | 100% | 47.43 | 314 | 79 |
| 1976 | 45.88 | 365 | 100% | 45.88 | 786 | 110 |
| 1977 | 49.92 | 365 | 100% | 49.92 | 172 | 66 |
| 1978 | 47.41 | 365 | 100% | 47.41 | 724 | 90 |
| 1979 | 48.02 | 366 | 100% | 48.02 | 210 | 92 |
| 1980 | 50.78 | 365 | 100% | 50.78 | 28 | 17 |
| 1981 | 55.05 | 363 | 99% | 55.05 | 256 | 70 |
| 1982 | 39.16 | 365 | 100% | 39.16 | 386 | 79 |
| 1983 | 47.91 | 366 | 100% | 47.91 | 312 | 102 |
| 1984 | 47.87 | 365 | 100% | 47.87 | 429 | 91 |
| 1985 | 49.79 | 365 | 100% | 49.79 | 88 | 58 |
| 1986 | 48.72 | 365 | 100% | 48.72 | 96 | 65 |
| 1987 | 49.74 | 366 | 100% | 49.74 | 203 | 43 |
| 1988 | 51.84 | 365 | 100% | 51.84 | 253 | 67 |
| 1989 | 50.77 | 365 | 100% | 50.77 | 237 | 70 |
| 1990 | 50.36 | 365 | 100% | 50.36 | 378 | 66 |
| 1991 | 51.27 | 366 | 100% | 51.27 | 143 | 53 |
| 1992 | 50.73 | 365 | 100% | 50.73 | 253 | 40 |
| 1993 | 50.68 | 364 | 100% | 50.68 | 246 | 37 |
| 1994 | 53.03 | 365 | 100% | 53.03 | 46 | 53 |
| 1995 | 53.47 | 366 | 100% | 53.47 | 9 | 51 |
| 1996 | 52.15 | 365 | 100% | 52.15 | 37 | 18 |
| 1997 | 51.71 | 359 | 98% | 51.71 | 152 | 19 |
| 1998 | 52.82 | 364 | 100% | 52.82 | 108 | 28 |
| 1999 | 52.20 | 364 | 100% | 52.20 | 9 | 18 |
| 2000 | 52.24 | 364 | 100% | 52.24 | 164 | 36 |
| 2001 | 53.50 | 364 | 100% | 53.50 | 187 | 44 |
| 2002 | 54.00 | 365 | 100% | 54.00 | 15 | 16 |
| 2003 | 54.39 | 365 | 100% | 54.39 | 52 | 14 |
| 2004 | 52.82 | 364 | 100% | 52.82 | 38 | 17 |
| 2005 | 54.10 | 365 | 100% | 54.10 | 86 | 20 |
| 2006 | 52.30 | 365 | 100% | 52.30 | 37 | 18 |
| 2007 | 53.02 | 366 | 100% | 53.02 | 202 | 67 |
| 2008 | 53.54 | 365 | 100% | 53.54 | 160 | 50 |

| | | | | | | |
|---|---|---|---|---|---|---|
| 2009 | 50.68 | 365 | 100% | 50.68 | 31 | 11 |
| 2010 | 53.50 | 363 | 99% | 53.50 | 146 | 60 |
| 2011 | 52.64 | 366 | 100% | 52.64 | 375 | 44 |
| 2012 | 57.71 | 236 | 65% | 57.71 | 169 | 20 |
| 2013 | 52.40 | 349 | 96% | 52.40 | 60 | 18 |
| 2014 | 52.79 | 357 | 98% | 52.79 | 103 | 13 |
| 2015 | 52.07 | 335 | 92% | 52.07 | 74 | 42 |
| 2016 | 53.21 | 332 | 91% | 53.21 | 8 | 11 |
| 2017 | 48.50 | 365 | 100% | 48.50 | 85 | 16 |
| 2018 | 45.13 | 365 | 100% | 45.13 | 401 | 89 |
| 2019 | 46.12 | 366 | 100% | 46.12 | 330 | 95 |
| 2020 | 46.55 | 365 | 100% | 46.55 | 311 | 97 |
| 2021 | 46.66 | 365 | 100% | 46.66 | 307 | 90 |
| 2022 | 44.17 | 365 | 100% | 44.17 | 524 | 111 |
| 2023 | 45.59 | 366 | 100% | 45.59 | 312 | 87 |
| 2024 | 46.07 | 365 | 100% | 46.07 | 236 | 24 |


# ATTACHMENT D3
# DETERMINATION OF PARAMETERS AT A 200-YEAR RECURRENCE INTERVAL

# ATTACHMENT D3.1
# MEAN ANNUAL TEMPERATURE AT 200-YEAR RECURRENCE INTERVAL

Project No. 111360
Project Name: Mt. Taylor Uranium Mine
Calculated By: JB

n= number of observations
n= 50

| Mean Annual Temperature Distribution | | | | | |
|---|---|---|---|---|---|
| Year | Average Temperature | Rank | Recurrence interval | Probability | Standard Variate |
| 2012 | 57.71 | 1 | 51.0 | 0.02 | 3.92 |
| 1981 | 55.05 | 2 | 25.5 | 0.04 | 3.22 |
| 2003 | 54.39 | 3 | 17.0 | 0.06 | 2.80 |
| 2005 | 54.10 | 4 | 12.8 | 0.09 | 2.50 |
| 2002 | 54.00 | 5 | 10.2 | 0.11 | 2.27 |
| 2008 | 53.54 | 6 | 8.5 | 0.13 | 2.08 |
| 2010 | 53.50 | 7 | 7.3 | 0.16 | 1.91 |
| 2001 | 53.50 | 8 | 6.4 | 0.19 | 1.77 |
| 1995 | 53.47 | 9 | 5.7 | 0.21 | 1.64 |
| 2016 | 53.21 | 10 | 5.1 | 0.24 | 1.52 |
| 1994 | 53.03 | 11 | 4.6 | 0.28 | 1.41 |
| 2007 | 53.02 | 12 | 4.3 | 0.31 | 1.32 |
| 1998 | 52.82 | 13 | 3.9 | 0.34 | 1.22 |
| 2004 | 52.82 | 14 | 3.6 | 0.38 | 1.14 |
| 2014 | 52.79 | 15 | 3.4 | 0.42 | 1.05 |
| 2011 | 52.64 | 16 | 3.2 | 0.46 | 0.98 |
| 2013 | 52.40 | 17 | 3.0 | 0.50 | 0.90 |
| 2006 | 52.30 | 18 | 2.8 | 0.55 | 0.83 |
| 2000 | 52.24 | 19 | 2.7 | 0.59 | 0.76 |
| 1999 | 52.20 | 20 | 2.6 | 0.65 | 0.70 |
| 1996 | 52.15 | 21 | 2.4 | 0.70 | 0.63 |
| 2015 | 52.07 | 22 | 2.3 | 0.76 | 0.57 |
| 1988 | 51.84 | 23 | 2.2 | 0.82 | 0.51 |
| 1997 | 51.71 | 24 | 2.1 | 0.89 | 0.45 |
| 1991 | 51.27 | 25 | 2.0 | 0.96 | 0.39 |
| 1980 | 50.78 | 26 | 2.0 | 1.04 | 0.34 |
| 1989 | 50.77 | 27 | 1.9 | 1.13 | 0.28 |
| 1992 | 50.73 | 28 | 1.8 | 1.22 | 0.23 |
| 2009 | 50.68 | 29 | 1.8 | 1.32 | 0.17 |
| 1993 | 50.68 | 30 | 1.7 | 1.43 | 0.12 |
| 1990 | 50.36 | 31 | 1.6 | 1.55 | 0.07 |
| 1977 | 49.92 | 32 | 1.6 | 1.68 | 0.01 |
| 1985 | 49.79 | 33 | 1.5 | 1.83 | -0.04 |
| 1987 | 49.74 | 34 | 1.5 | 2.00 | -0.09 |
| 1986 | 48.72 | 35 | 1.5 | 2.19 | -0.15 |
| 2017 | 48.50 | 36 | 1.4 | 2.40 | -0.20 |
| 1979 | 48.02 | 37 | 1.4 | 2.64 | -0.26 |
| 1983 | 47.91 | 38 | 1.3 | 2.92 | -0.31 |
| 1984 | 47.87 | 39 | 1.3 | 3.25 | -0.37 |
| 1975 | 47.43 | 40 | 1.3 | 3.64 | -0.43 |
| 1978 | 47.41 | 41 | 1.2 | 4.10 | -0.49 |
| 2021 | 46.66 | 42 | 1.2 | 4.67 | -0.55 |





| Best Fit | | | |
|---|---|---|---|
| Y | 2.6549 | x+ | 48.992 |
| Recurrence interval | Standard Variate | Average Temperature | |
| 42 | 3.73 | 58.9 | |
| 50 | 3.90 | 59.4 | |
| 75 | 4.31 | 60.4 | |
| 100 | 4.60 | 61.2 | |
| 125 | 4.82 | 61.8 | |
| 150 | 5.01 | 62.3 | |
| 175 | 5.16 | 62.7 | |
| 200 | 5.30 | 63.1 | |

# ATTACHMENT D3.2
# FROST INDEX AT 200-YEAR RECURRENCE INTERVAL

Project No. 111360
Project Name: Mt. Taylor Uranium Mine
Calculated By: JB

n= number of observations
n= 50

| Frost Index Distribution | | | | | |
|---|---|---|---|---|---|
| Year | Frost index | Rank | Recurrence interval | Probability | Standard Variate |
| 1976 | 786 | 1 | 51.00 | 0.02 | 3.92 |
| 1978 | 724 | 2 | 25.50 | 0.04 | 3.22 |
| 2022 | 524 | 3 | 17.00 | 0.06 | 2.80 |
| 1984 | 429 | 4 | 12.75 | 0.09 | 2.50 |
| 2018 | 401 | 5 | 10.20 | 0.11 | 2.27 |
| 1982 | 386 | 6 | 8.50 | 0.13 | 2.08 |
| 1990 | 378 | 7 | 7.29 | 0.16 | 1.91 |
| 2011 | 375 | 8 | 6.38 | 0.19 | 1.77 |
| 2019 | 330 | 9 | 5.67 | 0.21 | 1.64 |
| 1975 | 314 | 10 | 5.10 | 0.24 | 1.52 |
| 1983 | 312 | 11 | 4.64 | 0.28 | 1.41 |
| 2023 | 312 | 12 | 4.25 | 0.31 | 1.32 |
| 2020 | 311 | 13 | 3.92 | 0.34 | 1.22 |
| 2021 | 307 | 14 | 3.64 | 0.38 | 1.14 |
| 1981 | 256 | 15 | 3.40 | 0.42 | 1.05 |
| 1988 | 253 | 16 | 3.19 | 0.46 | 0.98 |
| 1992 | 253 | 17 | 3.00 | 0.50 | 0.90 |
| 1993 | 246 | 18 | 2.83 | 0.55 | 0.83 |
| 1989 | 237 | 19 | 2.68 | 0.59 | 0.76 |
| 2024 | 236 | 20 | 2.55 | 0.65 | 0.70 |
| 1979 | 210 | 21 | 2.43 | 0.70 | 0.63 |
| 1987 | 203 | 22 | 2.32 | 0.76 | 0.57 |
| 2007 | 202 | 23 | 2.22 | 0.82 | 0.51 |
| 2001 | 187 | 24 | 2.13 | 0.89 | 0.45 |
| 1977 | 172 | 25 | 2.04 | 0.96 | 0.39 |
| 2012 | 169 | 26 | 1.96 | 1.04 | 0.34 |
| 2000 | 164 | 27 | 1.89 | 1.13 | 0.28 |
| 2008 | 160 | 28 | 1.82 | 1.22 | 0.23 |
| 1997 | 152 | 29 | 1.76 | 1.32 | 0.17 |
| 2010 | 146 | 30 | 1.70 | 1.43 | 0.12 |
| 1991 | 143 | 31 | 1.65 | 1.55 | 0.07 |
| 1998 | 108 | 32 | 1.59 | 1.68 | 0.01 |
| 2014 | 103 | 33 | 1.55 | 1.83 | -0.04 |
| 1986 | 96 | 34 | 1.50 | 2.00 | -0.09 |
| 1985 | 88 | 35 | 1.46 | 2.19 | -0.15 |
| 2005 | 86 | 36 | 1.42 | 2.40 | -0.20 |
| 2017 | 85 | 37 | 1.38 | 2.64 | -0.26 |
| 2015 | 74 | 38 | 1.34 | 2.92 | -0.31 |
| 2013 | 60 | 39 | 1.31 | 3.25 | -0.37 |
| 2003 | 52 | 40 | 1.28 | 3.64 | -0.43 |
| 1994 | 46 | 41 | 1.24 | 4.10 | -0.49 |





| Best Fit | | | |
|---|---|---|---|
| Y | 153.82 | x+ | 112.93 |
| Recurrence interval | Standard Variate | Frost Index | |
| 42 | 3.73 | 686.0 | |
| 50 | 3.90 | 713.1 | |
| 75 | 4.31 | 776.0 | |
| 100 | 4.60 | 820.5 | |
| 125 | 4.82 | 855.0 | |
| 150 | 5.01 | 883.2 | |
| 175 | 5.16 | 906.9 | |
| 200 | 5.30 | 927.5 | |

# ATTACHMENT D3.3
# DURATION OF FREEZE SEASON AT 200-YEAR RECURRENCE INTERVAL

Project No. 111360
Project Name: Mt. Taylor Uranium Mines
Calculated By: JB

n= number of observations
n= 50

| Duration of Freeze Distribution | | | | | |
|---|---|---|---|---|---|
| Year | Duration | Rank | Recurrence interval | Probability | Standard Variate |
| | | | | | |
| 2022 | 111.0 | 1 | 51.00 | 0.02 | 3.92 |
| 1976 | 110.0 | 2 | 25.50 | 0.04 | 3.22 |
| 1983 | 102.0 | 3 | 17.00 | 0.06 | 2.80 |
| 2020 | 97.0 | 4 | 12.75 | 0.09 | 2.50 |
| 2019 | 95.0 | 5 | 10.20 | 0.11 | 2.27 |
| 1979 | 92.0 | 6 | 8.50 | 0.13 | 2.08 |
| 1984 | 91.0 | 7 | 7.29 | 0.16 | 1.91 |
| 1978 | 90.0 | 8 | 6.38 | 0.19 | 1.77 |
| 2021 | 90.0 | 9 | 5.67 | 0.21 | 1.64 |
| 2018 | 89.0 | 10 | 5.10 | 0.24 | 1.52 |
| 2023 | 87.0 | 11 | 4.64 | 0.28 | 1.41 |
| 1975 | 79.0 | 12 | 4.25 | 0.31 | 1.32 |
| 1982 | 79.0 | 13 | 3.92 | 0.34 | 1.22 |
| 1981 | 70.0 | 14 | 3.64 | 0.38 | 1.14 |
| 1989 | 70.0 | 15 | 3.40 | 0.42 | 1.05 |
| 1988 | 67.0 | 16 | 3.19 | 0.46 | 0.98 |
| 2007 | 67.0 | 17 | 3.00 | 0.50 | 0.90 |
| 1977 | 66.0 | 18 | 2.83 | 0.55 | 0.83 |
| 1990 | 66.0 | 19 | 2.68 | 0.59 | 0.76 |
| 1986 | 65.0 | 20 | 2.55 | 0.65 | 0.70 |
| 2010 | 60.0 | 21 | 2.43 | 0.70 | 0.63 |
| 1985 | 58.0 | 22 | 2.32 | 0.76 | 0.57 |
| 1991 | 53.0 | 23 | 2.22 | 0.82 | 0.51 |
| 1994 | 53.0 | 24 | 2.13 | 0.89 | 0.45 |
| 1995 | 51.0 | 25 | 2.04 | 0.96 | 0.39 |
| 2008 | 50.0 | 26 | 1.96 | 1.04 | 0.34 |
| 2001 | 44.0 | 27 | 1.89 | 1.13 | 0.28 |
| 2011 | 44.0 | 28 | 1.82 | 1.22 | 0.23 |
| 1987 | 43.0 | 29 | 1.76 | 1.32 | 0.17 |
| 2015 | 42.0 | 30 | 1.70 | 1.43 | 0.12 |
| 1992 | 40.0 | 31 | 1.65 | 1.55 | 0.07 |
| 1993 | 37.0 | 32 | 1.59 | 1.68 | 0.01 |
| 2000 | 36.0 | 33 | 1.55 | 1.83 | -0.04 |
| 1998 | 28.0 | 34 | 1.50 | 2.00 | -0.09 |
| 2024 | 24.0 | 35 | 1.46 | 2.19 | -0.15 |
| 2005 | 20.0 | 36 | 1.42 | 2.40 | -0.20 |
| 2012 | 20.0 | 37 | 1.38 | 2.64 | -0.26 |
| 1997 | 19.0 | 38 | 1.34 | 2.92 | -0.31 |
| 1996 | 18.0 | 39 | 1.31 | 3.25 | -0.37 |
| 1999 | 18.0 | 40 | 1.28 | 3.64 | -0.43 |
| 2006 | 18.0 | 41 | 1.24 | 4.10 | -0.49 |
| 2013 | 18 | 42 | 1.21 | 4.67 | -0.55 |




| Best Fit | | | |
|---|---|---|---|
| Y | 25.423 | x+ | 37.894 |
| Recurrence interval | Standard Variate | durations | |
| 42 | 3.73 | 132.6 | |
| 50 | 3.90 | 137.1 | |
| 75 | 4.31 | 147.5 | |
| 100 | 4.60 | 154.8 | |
| 125 | 4.82 | 160.5 | |
| 150 | 5.01 | 165.2 | |
| 175 | 5.16 | 169.1 | |
| 200 | 5.30 | 172.5 | |

# ATTACHMENT D4
# FROST DEPTH DETERMINATION

| Layer | Optimum Dry Density (PCF) | Water content (%) | dry density | | Thermal Conductivity Kf (BTU/ Ft hr F) | Thermal Conductivity Ku (BTU/ Ft hr F) | Average Thermal Conductivity (1/2*( Ku+Kf)) | Volumetric Heat Capacity (Cavg) | Latent heat of fusion | Depth (Inches) |
|---|---|---|---|---|---|---|---|---|---|---|
| Mulch | 115 | 10 | 97.75 | 85% proctor | 0.83 | 0.87 | 0.85 | 23.9 | 1407.60 | 12 |
| Soil Cover | 110.7 | 11 | 94.10 | 85% proctor | 0.80 | 0.82 | 0.81 | 23.8 | 1490.46 | 33 |

| n-factor | 0.7 |
|---|---|

| | Avg temp | F | Duration | Vs | Vo | Thermal ratio | Fusion parameter | | | | | eqn 52 | eqn 53 | Lambda parameter | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | K | Ci | L | Thickness ft | Ci average | Li average | | Ri | Ri/2 | Sum Ri-1 | Ati |
| Mulch Layer | 63.1 | 927.5 | 173 | 3.8 | 31.1 | 8.25 | 0.06 | 0.85 | 23.9 | 1407.6 | 1.00 | 23.9 | 1407.6 | 0.45 | 1.18 | 0.59 | 0.00 | 243.16 |
| Soil Cover | 63.1 | 927.5 | 173 | 3.8 | 31.1 | 8.25 | 0.06 | 0.81 | 23.8 | 1490.5 | 2.75 | 23.8 | 1468.4 | 0.45 | 3.39 | 1.70 | 1.18 | 3460.37 |
| Mean | | 927.5 | | | | | | 0.8 | 23.9 | 1449.0 | 1.9 | 23.9 | 1438.0 | 0.45 | | | | |
| | 649.27 | | | | | | | | | Total FT | 3.75 | | | | | | | 3703.53 |
| | | | | | | | | | | total inches | 45 | | | | | | | |

**Frost Depth (feet)** **2.27**
**Frost Depth (inches)** **27.28**




Figure 6. λ coefficient in the Modified Berg equation (UFC 3-130-06).

# APPENDIX E
# RADON ATTENUATION

Engineering Analytics, Inc.
Now Part of MacKay

Fort Collins Office

1600 Specht Point Road, Suite 209, Fort Collins, CO 80525
970.488.3111 / GoMacKay.com

# *Technical Memorandum*

| | | | |
|---|---|---|---|
| To: | Rio Grande Resources, Ltd. | From: | Jason Andrews, P.E. |
| Company: | Rio Grande Resources, Ltd. | Date: | August 5, 2026 |
| EA No.: | 111360 | | |
| Re: | Mt. Taylor Uranium Mine – Radon Cover Design and Analyses | | |

## 1.0 INTRODUCTION

This technical memorandum presents the results of modeling of emanation of radon-226 from the top surface of the proposed cover over the expanded disposal cell. These results comprise radon attenuation modeling based on the proposed cover design, and cover materials.

The cover system design consists of a three-layer cover system over contaminated soils, with a total thickness of approximately 52 inches (4.33 feet) as shown on Figure 4-1. The final cover system will consist of the following layers from top to bottom.

- 12 inches of rock mulch cover for erosion protection.
- 28 inches of onsite in-situ soils for bio intrusion and frost protection.
- 12 inches of clay layer to minimize infiltration and emanation of radon gas

For the radon emanation modeling, the rock mulch layer was included as the uppermost modeled cover layer because the Uranium Mill Tailings Cover Calculator was run with four layers: contaminated materials, clay radon barrier, in-situ soil, and rock mulch.

The radon emanation modeling shows that the planned cover system reduces the rate of radon emanation to values below the Nuclear Regulatory Commission (NRC) limit of 20 picocuries per square meter per second (pCi/$m^2$-sec) averaged over the entire expanded disposal cell.

## 2.0 DESCRIPTION OF MODEL AND INPUT VALUES

Radon emanation calculations for the cover system were made using the Wise Uranium Project Uranium Mill Tailings Cover Calculator, which implements the RADON model described in NRC Regulatory Guide 3.64 (NRC, 1989). The calculator evaluates one-dimensional radon-222 diffusion from a radium-226 source through layered cover materials. The calculator was run using metric units with four model layers: contaminated materials, clay radon barrier, in-situ soil, and rock mulch. The key input parameters include layer thickness, radium-226 activity concentration, radon emanation coefficient, porosity, long-term moisture content, and the calculated radon diffusion coefficient. The input parameters and values used in the model are outlined below.

### 2.1 Radium Activity Concentrations

Radium-226 activity values used in the model were taken from Radiological Characterization Reports by AVM Environmental Services, Inc. (AVM) for the Windblown Area, Ore Pad Area, and Mine Compound (AVM 2023), for the Treatment Ponds (AVM 2024), and for the North Controlled Area (AVM 2025). The radium-226 activity values used in the model are summarized below. Attachment E-1 includes pages extracted from the AVM reports used to calculate representative radium activities for the model.

**Windblown Area (WA):** The representative radium-226 activity value for contaminated soils within the WA north of the mine site was estimated from a static gamma radiation survey performed by AVM (2023) on May 17 and May 31, 2023. Attachment E-1.1 includes Table 2 from the AVM report illustrating the results of the survey, and Figure 1 from the AVM report illustrating the location of the WA. From a total of 12 survey locations using data for the "Bare 2x2 Nal Detector", a mean activity value of 9.8 pCi/g Ra-226 is estimated.

**Ore Pad Area (OPA):** The representative radium-226 activity value for contaminated soils within the OPA was estimated from a static gamma radiation survey performed by AVM (2023) on May 31, 2023. Attachment E-1.1 includes Table 2 from the AVM report illustrating the results of the survey, and Figure 1 from the AVM report illustrating the location of the OPA. From a total of 5 survey locations using data for the "Bare 2x2 Nal Detector", a mean activity value of 431.6 pCi/g Ra-226 is estimated.

**Mine Compound Area (MCA):** The representative radium-226 activity value for contaminated soils within the MCA was estimated from a static gamma radiation survey performed by AVM (2023) from May 18 through May 31, 2023. Attachment E-1.1 includes Table 2 from the AVM report illustrating the results of the survey, and Figure 1 from the AVM report illustrating the location of the MCA. From a total of 20 survey locations using data for the "Bare 2x2 Nal Detector", a mean activity value of 13.1 pCi/g Ra-226 is estimated.

**Pond Area (PA):** The representative radium-226 activity value for contaminated soils within the PA was estimated from a static gamma radiation survey performed by AVM (2024) from October 18, 2023. Attachment E-1.2 includes Table 1 from the AVM report illustrating the results of the survey, and Figure 1 from the AVM report illustrating the location of the PA. From a total of 40

survey locations using data for the "Bare 2x2 Nal Detector", a mean activity value of 4.8 pCi/g Ra-226 is estimated.

**North Controlled Area (NCA):** The representative radium-226 activity value for contaminated soils within the NCA was estimated from a static gamma radiation survey performed by AVM (2025) from September 19 through December 12, 2024. Attachment E-1.3 includes Table 2 from the AVM report illustrating the results of the survey, and Figure 1 from the AVM report illustrating the location of the NCA. From a total of 47 survey locations using data for the "Bare 2x2 Nal Detector", a mean activity value of 47.1 pCi/g Ra-226 is estimated.

Ra-226 activity concentration is a required model input. For the purposes of modeling radon emanation, the arithmetic mean radium-226 concentration value from the five distinct source areas (WA, OPA, MCA, PA, and NCA) is approximately 101 pCi/g. The updated Uranium Mill Tailings Cover Calculator run used a Ra-226 activity concentration of 115 pCi/g for the contaminated materials layer. For this to be a reasonable assumption in the assessment of radon flux from the cover, it is recommended that the materials from the OPA be placed at the base of the disposal cell because the OPA materials have the highest mean Ra-226 activity concentration (431.6 pCi/g).

## 2.2 Radion Emanation Coefficient

Radon emanation coefficient is a required model input. For all modeled layers, including the contaminated materials and cover materials, a radon emanation coefficient of 0.35 was used. This is the conservative default value used in the Uranium Mill Tailings Cover Calculator.

## 2.3 Density and Porosity

Attachment E-2 includes laboratory testing data for the cover layer materials. While material density of the cover layers is not a direct model input, material placement and performance density affects the porosity and long-term moisture model input values. The general textures of the contaminated materials to be consolidated into the expanded disposal cell consist of some variable percentages of silt, clay and sand. As such, a density of 100 lb/cf (1.60 g/cc) was assumed for contaminated materials below the cover. For the 12-inch layer of radon barrier clay on top of the waste, a value of 99 lb/cf (1.59 g/cc) was used which is equivalent to 90 percent of the standard Proctor dry density of the clay sample from EA-BSB04 collected from Borrow Area A-B in January 2025. For the in-situ frost protection soil layer above the radon barrier, a value of 94 lb/cf (1.51 g/cc) was used which is equivalent to 85 percent of the mean standard Proctor dry density of samples EA-BSB04 (sand), EA-BSC12 (sandy clay), and EA-BSC09 (silty clay) collected from Borrow Area A-B in January 2025. The same density of 94 lb/cf (1.51 g/cc) was used for the upper rock mulch layer as the soil matrix of the rock mulch layer is anticipated to be the same as, or similar to, the in-situ soil layer.

Porosity is a required model input. Porosity values for the waste material, the in-situ soil layer, and the rock mulch layer are not very sensitive to calculation of radon flux in the model, and the values can range +/- 20 percent individually with only a +/-10 percent change in radon flux. In contrast, radon flux calculated by the model is sensitive to porosity of the radon barrier. A similar

range of +/- 20 percent change in radon barrier porosity can change the calculated radon flux value to zero (with a lower porosity value), or can double the calculated radon flux (with a higher porosity value). A typical porosity value for the mixed sand, silt and clay of 0.35 was assumed for the waste materials. The porosity of the radon barrier clay layer was estimated from the compaction test report for sample EA-BSC09 (silty clay). From the compaction test report, a void ratio of 0.62 can be determined, and an associated porosity of 0.38 is calculated. For the in-situ soil layer and upper rock mulch layer, a porosity of 0.35 is assumed.

## 2.4 Long-Term Moisture Content

Long-term moisture content of the cover layers is a required model input. The long-term moisture contents for the frost protection layer and rock mulch layer were assumed to be 6% based on the NRC guidance (1989). While the long-term moisture contents of both the waste materials and the radon barrier are sensitive to calculation of radon flux, the long term moisture content of the radon barrier is particularly sensitive to calculation of radon flux. The long-term, 15-bar, moisture content of the radon barrier clay layer was determined to be 15.1 percent from EA-BSC09 (silty clay) collected from Borrow Area A-B in January 2025 (Attachment E-2). This value represents a sample of the material remolded to 90 percent of the standard Proctor density. The long term, 15-bar, moisture content for the contaminated material below the radon barrier was also assumed to be 15.1 percent since the materials are below the depth of influence from evapotranspiration.

## 2.5 Radion Diffusion Coefficient

The radon diffusion coefficient was calculated by the Uranium Mill Tailings Cover Calculator based on the material properties and moisture content for each layer. The calculated diffusion coefficients used in the updated model are 1.69E-07 $m^2/s$ for the contaminated materials, 4.62E-07 $m^2/s$ for the clay radon barrier, and 2.01E-06 $m^2/s$ for both the in-situ soil layer and rock mulch layer. The lower the diffusion coefficient value, the lower the resulting rate of radon emanation through the layer.

# 3.0 RESULTS

The input values and updated results from the Uranium Mill Tailings Cover Calculator are summarized in Table E-1. The model output is provided in Attachment E-3.

The updated radon emanation model results presented in Table E-1 show that the cover system reduces the calculated radon-222 flux from a bare source flux of 42.10 $pCi/m^2/s$ to 13.99 $pCi/m^2/s$ at the top of the cover system. The calculated total cover radon retention is 66.77 percent. The final calculated radon flux is below the NRC allowable emanation limit of 20 $pCi/m^2/s$ averaged over the disposal cell.

# 4.0 RADON SENSITIVITY ANALYSIS CALCULATIONS

## 4.1 Mathematical Framework

The sensitivity calculations in Table 4.3 were generated using the one-dimensional, steady state radon diffusion model from U.S. NRC Regulatory Guide 3.64 ("Calculation of Radon Flux Attenuation by Earthen Uranium Mill Tailings Covers").
The governing differential equation for radon 222 diffusion in a porous medium is:

$$D\frac{d^2C}{dx^2} - \lambda C + \frac{R\rho E\lambda}{n} = 0$$

Where:

- $C$= radon-222 concentration in the pore space $\left(\text{pCi/cm}^3\right)$
- $D$= effective radon diffusion coefficient ($\text{m}^2/\text{s}$)
- $\lambda$= radon-222 decay constant ($2.1 \times 10^{-6}\ \text{s}^{-1}$)
- $R$= Ra-226 activity concentration (pCi/g)
- $\rho$= dry density $\left(\text{g/cm}^3\right)$
- $E$= radon emanation coefficient (dimensionless)
- $n$= total porosity (dimensionless)
- $x$= depth (m)

Radon flux at any interface is computed using Fick's Law:

$$J = -10^4 \cdot D \cdot n\frac{dC}{dx}$$

For the multilayer system (Waste to Clay Barrier to Undisturbed Soil to Rock Mulch), continuity of concentration and flux is enforced at each interface. The resulting system of hyperbolic functions (, ) is solved numerically using a matrix solution in the WISE Uranium Project cover calculator. A key intermediate parameter is the diffusion length :

$$l = \sqrt{\frac{D}{\lambda}}$$

## 4.2 Base Input Parameters

Baseline parameters were established from site geotechnical data and conservative design assumptions.

Layer 1 – Contaminated Waste (source):

- $R = 115$ pCi/g
- $\rho = 1.60$ g/cm$^3$
- $n = 0.35$
- $E = 0.35$
- $D_1 = 1.69 \times 10^{-7}$ m$^2$/s
- Thickness ≈ 197 in (5.0 m; treated as effectively infinite)

Layer 2 – Compacted Clay Radon Barrier:

- $\rho = 1.59$ g/cm$^3$
- $n = 0.38$
- $D_{\text{clay}} = 4.62 \times 10^{-7}$ m$^2$/s
- $l_{\text{clay}} = \sqrt{\frac{4.62\times10^{-7}}{2.1\times10^{-6}}} \approx 0.469$ m

Layer 3 – Undisturbed Soil Cover:

- $\rho = 1.51$ g/cm$^3$
- $n = 0.35$
- $D_{\text{soil}} = 2.01 \times 10^{-6}$ m$^2$/s
- $l_{\text{soil}} = \sqrt{\frac{2.01\times10^{-6}}{2.1\times10^{-6}}} \approx 0.978$ m

Layer 4 – Rock Mulch:

- $\rho = 1.51$ g/cm$^3$
- $n = 0.35$
- $D_{\text{mulch}} = 2.01 \times 10^{-6}$ m$^2$/s
- Thickness = 12 in = 0.305 m (constant for all cases)

## 4.3 Sensitivity Case Configurations (Table 4.3 of main report)

Each case modifies layer thicknesses or diffusion coefficients and is then solved with the same numerical framework. The flux values below are direct model outputs.

- **Case 1 – Base Design**
    - Clay: 12 in (0.305 m)
    - Soil: 28 in (0.711 m)
    - Diffusion: baseline $D_{\text{clay}}, D_{\text{soil}}, D_{\text{mulch}}$
    - Note: Clay provides the strongest attenuation due to its short diffusion length.
    - **Calculated surface flux:** $J = 13.99$ pCi/m$^2$/s
- **Case 2: Reduced Undisturbed Soil Cover**
    - Clay: 12 in (0.305 m)
    - Soil: 20 in (0.508 m)
    - Diffusion: baseline values
    - Note: Shorter soil path length reduces attenuation above the clay barrier.
    - **Calculated surface flux:** $J = 16.21$ pCi/m$^2$/s
- **Case 3: Increased Undisturbed Soil Cover**
    - Clay: 12 in (0.305 m)
    - Soil: 36 in (0.914 m)
    - Diffusion: baseline values
    - Note: Longer soil path increases decay opportunity before radon reaches the surface.
    - **Calculated surface flux:** $J = 12.08$ pCi/m$^2$/s
- **Case 4 – Reduced Clay Barrier**
    - Clay: 9 in (0.229 m)
    - Soil: 28 in (0.711 m)
    - Diffusion: baseline values
    - Note: Removing 3 in of low diffusivity clay has a larger impact than removing 8 in of soil because clay controls the sharpest attenuation.
    - **Calculated surface flux:** $J = 17.62$ pCi/m$^2$/s
- **Case 5: Higher Diffusion Coefficient (1.5 times)**
    - Geometry: 12 in clay, 28 in soil, 12 in mulch
    - Adjusted diffusion:

- $D'_{\text{clay}} = 1.5 \times 4.62 \times 10^{-7} = 6.93 \times 10^{-7}$ m$^2$/s
- $D'_{\text{soil}} = 1.5 \times 2.01 \times 10^{-6} = 3.015 \times 10^{-6}$ m$^2$/s
- $D'_{\text{mulch}} = 3.015 \times 10^{-6}$ m$^2$/s

  - Note: Simulates drier, more diffusive long term conditions; clay diffusion length increases to .
  - **Calculated surface flux:** $J = 18.74$ pCi/m$^2$/s

- **Case 6: Lower Diffusion Coefficient (0.75 times)**
  - Geometry: 12 in clay, 28 in soil, 12 in mulch
  - Adjusted diffusion:
    - $D'_{\text{clay}} = 0.75 \times 4.62 \times 10^{-7} = 3.465 \times 10^{-7}$ m$^2$/s
    - $D'_{\text{soil}} = 0.75 \times 2.01 \times 10^{-6} = 1.508 \times 10^{-6}$ m$^2$/s
    - $D'_{\text{mulch}} = 1.508 \times 10^{-6}$ m$^2$/s
  - Note: Simulates well-compacted, moist conditions that restrict gas transport.
  - **Calculated surface flux:** $J = 11.34$ pCi/m$^2$/s

### 4.4 Results of Sensitivity Assessment

All sensitivity cases, including reduced clay thickness, reduced soil thickness, and increased diffusion, remain below the regulatory limit of 20 pCi/m$^2$/s. The results are shown in Table E-2. The analysis confirms that the optimized 52 inch cover provides a robust margin of safety for radon attenuation under plausible variations in geometry and material properties.

## REFERENCES

Nuclear Regulatory Commission (NRC). (1989). *Calculation of Radon Flux Attenuation by Earthen Uranium Mill Tailings Covers, Regulatory Guide 3.64*.

Nuclear Regulatory Commission (NRC). (2018). *Proceedings of the Radon Barriers Workshop*. Dated July 25-26. NRC Headquarters, Rockville, MD.

AVM Environmental Services, Inc. (AVM). (2023) *Surface and Subsurface Soil Radiologic Characterization, Windblown Area, Ore Pad Area and Mine Compound, Mount Taylor Mine Site, San Mateo, NM.* Prepared for Rio Grande Resource Corporation. August 14, 2023.

AVM Environmental Services, Inc. (AVM). (2024) *Treatment Pond Radiologic Characterization, Mount Taylor Mine Site, San Mateo, NM.* Prepared for Rio Grande Resource Corporation. May 22, 2024.

AVM Environmental Services, Inc. (AVM). (2025) *North Controlled Area Soil Radiologic Characterization, Mount Taylor Mine Site, San Mateo, NM.* Prepared for Rio Grande Resource Corporation. June 5, 2025.

## LIST OF TABLES

Table E-1 Soil Inputs and Calculated Radon Flux

## LIST OF FIGURES

Figure E-1 Final Reclamation Cover System

## LIST OF ATTACHMENTS

Attachment E-1 Radium Activity Concentration References
Attachment E-1.1 AVM 2023 – Windblown Area, Ore Pad Area, Mine Compound
Attachment E-1.2 AVM 2024 – Treatment Pond
Attachment E-1.3 AVM 2025 – North Controlled Area
Attachment E-2 EA Laboratory Material Testing Results
Attachment E-3 Radon Model Output

# TABLES

## Table E-1 – Soil Inputs and Calculated Radon Flux

| Layer No[1] | Layer Description[1] | Thickness[1] (cm) | Thickness[1] (in) | Porosity | Dry Density ($g/cm^3$) | Radium-226 Activity (pCi/g) | Emanation Coefficient[2] | Moisture Content (%) | Diffusion Coefficient ($m^2/s$) | Exit Conc. (pCi/L) | Exit Radon Flux[3] ($pCi/m^2/s$) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 4 | Rock Mulch[4] | 30.5 | 12 | 0.35[5] | 1.51[5] 94 (pcf) | 0 | 0.35 | 6[6] | 2.01E-06 | 0.00E+00 | 13.99 |
| 3 | In-Situ Soil Layer (Frost Protection and Biointrusion) | 71.1 | 28 | 0.35[5] | 1.51[5] 94 (pcf) | 0 | 0.35 | 6[6] | 2.01E-06 | 6.15E+03 | 14.67 |
| 2 | Clay Layer (Radon Barrier) | 30.5 | 12 | 0.38[7] | 1.59[7] 99 (pcf) | 0 | 0.35 | 15.1[7] | 4.62E-07 | 1.57E+04 | 22.22 |
| 1 | Contaminated Materials[8] | 500.0 | 197 | 0.35 | 1.60 100 (pcf) | 115 | 0.35 | 15.1 | 1.69E-07 | 5.24E+04 | 31.17 |

Notes:
1 - See Figure 4-1.
2 – Required model assumption for all materials.
3 – Exit radon flux calculated by the Uranium Mill Tailings Cover Calculator at the top of each modeled layer.
4 – The soil matrix of the rock mulch layer is similar to, or the same as, the in-situ soil layer and thus governs the properties of the rock mulch layer.
5 – Mean values from compaction test reports for samples EA-BSC09 (silty clay), EA-BSC12 (sandy clay), and EA-BSB04 (sand) from Borrow Areas A-B (Attachment E-2). Porosity values are assumed for mixed sand, silt, and clay.
6 - Long term moisture content NRC (1989).
7 – Input values for clay radon barrier from compaction test report for sample EA-BSC09 (Attachment E-2) assuming a density of 90% of maximum standard Proctor density. The long-term 15-bar moisture content from the soil water characteristic curve (SWCC) for sample EA-BSC09 (Attachment E-2)
8 – The contaminated materials below the cover are assumed to be 5 meters (16.4 feet) thick. Soil properties of the waste materials are assumed to be characteristic of a mixed sand, silt, and clay with a porosity of 0.35, dry density of 100 pcf (1.60 $g/cm^3$), Ra-226 activity of 115 pCi/g, emanation coefficient of 0.35, and long-term moisture content of 15.1 percent.

**Table E-2 – Results of Sensitivity Analysis**

| Case | On-Site Soil Cover Thickness (in) | Clay Barrier Thickness (in) | Radon Diffusion Coefficient Assumption | Surface Flux (pCi/m²/s) |
|---|---|---|---|---|
| Appendix F base design | 28 | 12 | Appendix F design value | 13.99 |
| Reduced on-site soil cover | 20 | 12 | Appendix F design value | 16.21 |
| Increased on-site soil cover | 36 | 12 | Appendix F design value | 12.08 |
| Reduced clay barrier | 28 | 9 | Appendix F design value | 17.62 |
| Higher diffusion coefficient | 28 | 12 | 1.5 × Appendix F value | 18.74 |
| Lower diffusion coefficient | 28 | 12 | 0.75 × Appendix F value | 11.34 |

# ATTACHMENT E-1
# RADIUM ACTIVITY CONCENTRATION
# REFERENCES

# ATTACHMENT E-1.1
# AVM 2023- WINDBLOWN AREA, ORE PAD AREA, MINE COMPOUND

# Surface and Subsurface Soil Radiologic Characterization

## Windblown Area, Ore Pad Area and Mine Compound

## Mount Taylor Mine Site

## San Mateo, NM


**Prepared by:**

**AVM Environmental Services, Inc.**

**1717 Del Norte Blvd.**

**Grants, NM 87020**



**Prepared for:**

**Rio Grande Resource Corporation**

**PO Box 1150**

**Grants, NM 87020**

**August 14, 2023**




AVM Environmental Services, Inc.

Figure 1
Mt. Taylor Mine Site
Soil Radiologic Characterization Areas

**Legend**

North Controlled Fence

Soil Radiologic Characterization Area

## Table 2
## Static Gamma Radiation Survey at Soil Sampling/Test Pit Locations

| Survey Date | Survey Point ID/Description | Survey Point Coordinate NAD83 StatePlane NM West, Feet | | Static Gamma Radiation Survey | | | | Gamma Exposure Rate µR/hr |
|---|---|---|---|---|---|---|---|---|
| | | | | Bare 2x2 NaI Detector | | Collimated (0.5" Pb) 2x2 NaI Detector | | |
| | | Northing | Easting | CPM | Estimated Ra-226 pCi/g | CPM | Estimated Ra-226 pCi/g | |
| 05/17/23 | WBSB-01 | 1,581,413 | 2,782,866 | 26,897 | 6.1 | 6,297 | 1.7 | 33 |
| 05/17/23 | WBSB-02 | 1,581,390 | 2,782,444 | 26,749 | 6.1 | 6,350 | 1.7 | 33 |
| 05/17/23 | WBSB-03 | 1,581,356 | 2,783,329 | 24,529 | 4.9 | 6,073 | 1.3 | 31 |
| 05/17/23 | WBSB-04 | 1,581,339 | 2,782,706 | 30,064 | 7.7 | 6,069 | 1.3 | 37 |
| 05/17/23 | WBSB-05 | 1,581,329 | 2,783,062 | 31,828 | 8.6 | 6,945 | 2.7 | 41 |
| 05/17/23 | WBSB-06 | 1,581,271 | 2,782,942 | 35,410 | 10.4 | 7,288 | 3.3 | 47 |
| 05/17/23 | WBSB-07 | 1,581,187 | 2,783,253 | 37,965 | 11.7 | 8,183 | 4.7 | 47 |
| 05/17/23 | WBSB-08 | 1,581,164 | 2,782,988 | 55,849 | 20.6 | 11,042 | 9.3 | 70 |
| 05/31/23 | WBSB-09 | 1,581,254 | 2,782,870 | 36,491 | 10.9 | 6,599 | 2.1 | 44 |
| 05/31/23 | WBSB-10 | 1,581,263 | 2,783,140 | 34,898 | 10.1 | 7,286 | 3.2 | 48 |
| 05/31/23 | WBSB-11 | 1,581,277 | 2,783,335 | 29,002 | 7.2 | 6,602 | 2.2 | 34 |
| 05/31/23 | WBSB-12 | 1,581,228 | 2,782,908 | 40,341 | 12.9 | 7,153 | 3.0 | 55 |
| 05/31/23 | OPSB-01 | 1,580,834 | 2,782,884 | 2,328,550 | 1157 | 716,621 | 1138 | 2,100 |
| 05/31/23 | OPSB-02 | 1,580,812 | 2,783,138 | 505,097 | 245 | 160,357 | 248 | 650 |
| 05/31/23 | OPSB-03 | 1,580,599 | 2,783,013 | 700,063 | 343 | 247,434 | 387 | 900 |
| 05/31/23 | OPSB-04 | 1,580,328 | 2,782,874 | 408,698 | 197 | 133,199 | 205 | 450 |
| 05/31/23 | OPSB-05 | 1,580,386 | 2,783,136 | 446,083 | 216 | 156,044 | 241 | 450 |
| 05/30/23 | MCSB-01 | 1,579,585 | 2,783,019 | 35,807 | 10.6 | 10,538 | 8.5 | 41 |
| 05/30/23 | MCSB-02 | 1,579,573 | 2,783,167 | 34,096 | 9.7 | 9,678 | 7.1 | 39 |
| 05/30/23 | MCSB-03 | 1,579,343 | 2,782,883 | 34,019 | 9.7 | 9,832 | 7.3 | 39 |
| 05/30/23 | MCSB-04 | 1,579,317 | 2,783,098 | 34,656 | 10.0 | 10,811 | 8.9 | 40 |
| 05/24/23 | MCSB-05 | 1,579,183 | 2,782,702 | 52,231 | 18.8 | 14,892 | 15 | 65 |
| 05/24/23 | MCSB-06 | 1,579,162 | 2,783,064 | 31,976 | 8.7 | 8,548 | 5.3 | 37 |
| 05/24/23 | MCSB-07 | 1,579,040 | 2,783,010 | 52,974 | 19.2 | 18,511 | 21 | 65 |
| 05/23/23 | MCSB-08 | 1,578,849 | 2,782,249 | 107,010 | 46.2 | 39,626 | 55.0 | 125 |
| 05/23/23 | MCSB-09 | 1,578,850 | 2,782,582 | 28,188 | 6.8 | 8,193 | 4.7 | 33 |
| 05/23/23 | MCSB-10 | 1,578,758 | 2,782,444 | 39,814 | 12.6 | 12,984 | 12 | 43 |
| 05/22/23 | MCSB-11 | 1,578,611 | 2,782,258 | 53,106 | 19.2 | 18,055 | 20 | 60 |
| 05/22/23 | MCSB-12 | 1,578,521 | 2,782,569 | 29,299 | 7.3 | 9,090 | 6.1 | 33 |
| 05/22/23 | MCSB-13 | 1,578,301 | 2,782,557 | 21,952 | 3.7 | 6,254 | 1.6 | 25 |
| 05/23/23 | MCSB-14 | 1,578,278 | 2,782,258 | 21,642 | 3.5 | 6,366 | 1.8 | 25 |
| 05/18/23 | MCSB-15 | 1,578,214 | 2,782,398 | 48,059 | 16.7 | 15,633 | 17 | 51 |
| 05/18/23 | MCSB-16 | 1,578,084 | 2,782,313 | 30,445 | 7.9 | 11,069 | 9.3 | 33 |
| 05/18/23 | MCSB-17 | 1,578,085 | 2,782,599 | 18,059 | 1.7 | 5,891 | 1.0 | 19 |
| 05/18/23 | MCSB-18 | 1,578,071 | 2,782,424 | 17,170 | 1.3 | 5,046 | <0.6 | 19 |
| 05/31/23 | MCSB-19 | 1,578,837 | 2,782,317 | 69,850 | 27.6 | 24,522 | 31 | 80 |
| 05/31/23 | MCSB-20 | 1,578,650 | 2,782,298 | 55,167 | 20.3 | 18,497 | 21 | 65 |

WB
Sum = 117.2
Mean = 9.8
n = 12
SD = 4.2

OPA
Sum = 2158
Mean = 431.6
n = 5
SD = 409.4

MCA
Sum = 261.5
Mean = 13.1
n = 20
SD = 10.5

# ATTACHMENT E-1.2
# AVM 2024 – TREAMENT POND

# Treatment Pond Radiologic Characterization

**Mt. Taylor Mine Site**
**San Mateo, NM**

**Prepared by:**
**AVM Environmental Services, Inc.**
**1717 Del Norte Blvd.**
**Grants, NM 87020**

**Prepared for:**
**Rio Grande Resource Corporation**
**PO Box 1150**
**Grants, NM 87020**

**June 4, 2024**




Figure 1
Mt. Taylor Mine Site
Treatment Pond Characterization
Areas and Concrete Structure Locations

**Legend**

- Concrete Structure
- North Controlled Fence
- Treatment Pond Characterization Area

AVM Environmental Services, Inc.

Table 1
Typical Gamma Scan Data Exported from the Scan System Data Logger

| ID | Time | Northing[1] (feet) | Easting[1] (feet) | MSL Elevation (feet) | CPM 2x2 Bare NaI Detector | Ra-226 pCi/g[2] | Zone_ID |
|---|---|---|---|---|---|---|---|
| 1 | 10/18/2023 8:12 | 1579902.54 | 2781775.10 | 7300 | 24761 | 5.06 | Treatment_Ponds |
| 2 | 10/18/2023 8:12 | 1579903.88 | 2781775.74 | 7300 | 23724 | 4.54 | Treatment_Ponds |
| 3 | 10/18/2023 8:12 | 1579904.17 | 2781778.02 | 7300 | 25456 | 5.41 | Treatment_Ponds |
| 4 | 10/18/2023 8:12 | 1579903.99 | 2781781.66 | 7300 | 25463 | 5.41 | Treatment_Ponds |
| 5 | 10/18/2023 8:12 | 1579904.34 | 2781785.64 | 7300 | 24786 | 5.07 | Treatment_Ponds |
| 6 | 10/18/2023 8:12 | 1579904.46 | 2781790.40 | 7300 | 23246 | 4.30 | Treatment_Ponds |
| 7 | 10/18/2023 8:12 | 1579903.97 | 2781795.09 | 7301 | 23822 | 4.59 | Treatment_Ponds |
| 8 | 10/18/2023 8:12 | 1579903.49 | 2781800.02 | 7300 | 25694 | 5.53 | Treatment_Ponds |
| 9 | 10/18/2023 8:12 | 1579904.14 | 2781805.18 | 7301 | 31410 | 8.39 | Treatment_Ponds |
| 10 | 10/18/2023 8:12 | 1579904.09 | 2781810.07 | 7301 | 28672 | 7.02 | Treatment_Ponds |
| 11 | 10/18/2023 8:12 | 1579904.27 | 2781814.71 | 7301 | 25935 | 5.65 | Treatment_Ponds |
| 12 | 10/18/2023 8:12 | 1579904.36 | 2781819.65 | 7301 | 26984 | 6.17 | Treatment_Ponds |
| 13 | 10/18/2023 8:12 | 1579904.09 | 2781821.94 | 7301 | 26902 | 6.13 | Treatment_Ponds |
| 14 | 10/18/2023 8:12 | 1579903.77 | 2781822.84 | 7301 | 28593 | 6.98 | Treatment_Ponds |
| 15 | 10/18/2023 8:12 | 1579903.22 | 2781827.06 | 7301 | 28036 | 6.70 | Treatment_Ponds |
| 16 | 10/18/2023 8:12 | 1579902.15 | 2781831.73 | 7302 | 27870 | 6.62 | Treatment_Ponds |
| 17 | 10/18/2023 8:12 | 1579902.11 | 2781836.90 | 7302 | 26062 | 5.71 | Treatment_Ponds |
| 18 | 10/18/2023 8:13 | 1579902.06 | 2781842.31 | 7302 | 27827 | 6.59 | Treatment_Ponds |
| 19 | 10/18/2023 8:13 | 1579903.05 | 2781848.05 | 7302 | 27534 | 6.45 | Treatment_Ponds |
| 20 | 10/18/2023 8:13 | 1579902.68 | 2781853.78 | 7302 | 25994 | 5.68 | Treatment_Ponds |
| 21 | 10/18/2023 8:13 | 1579903.18 | 2781859.71 | 7302 | 26539 | 5.95 | Treatment_Ponds |
| 22 | 10/18/2023 8:13 | 1579903.39 | 2781865.09 | 7302 | 28415 | 6.89 | Treatment_Ponds |
| 23 | 10/18/2023 8:13 | 1579903.06 | 2781874.06 | 7302 | 26264 | 5.81 | Treatment_Ponds |
| 24 | 10/18/2023 8:13 | 1579902.23 | 2781879.73 | 7303 | 23133 | 4.25 | Treatment_Ponds |
| 25 | 10/18/2023 8:13 | 1579903.30 | 2781885.83 | 7303 | 24734 | 5.05 | Treatment_Ponds |
| 26 | 10/18/2023 8:13 | 1579903.75 | 2781891.77 | 7303 | 22704 | 4.03 | Treatment_Ponds |
| 27 | 10/18/2023 8:13 | 1579903.75 | 2781897.38 | 7303 | 22324 | 3.84 | Treatment_Ponds |
| 28 | 10/18/2023 8:13 | 1579902.96 | 2781902.73 | 7303 | 20758 | 3.06 | Treatment_Ponds |
| 29 | 10/18/2023 8:13 | 1579899.92 | 2781907.85 | 7303 | 19594 | 2.48 | Treatment_Ponds |
| 30 | 10/18/2023 8:13 | 1579899.78 | 2781914.18 | 7304 | 20910 | 3.14 | Treatment_Ponds |
| 31 | 10/18/2023 8:13 | 1579900.82 | 2781919.94 | 7304 | 20171 | 2.77 | Treatment_Ponds |
| 32 | 10/18/2023 8:13 | 1579901.72 | 2781925.63 | 7304 | 22063 | 3.71 | Treatment_Ponds |
| 33 | 10/18/2023 8:13 | 1579901.53 | 2781931.45 | 7304 | 20831 | 3.10 | Treatment_Ponds |
| 34 | 10/18/2023 8:13 | 1579901.71 | 2781937.44 | 7305 | 22406 | 3.88 | Treatment_Ponds |
| 35 | 10/18/2023 8:13 | 1579904.08 | 2781942.73 | 7305 | 22237 | 3.80 | Treatment_Ponds |
| 36 | 10/18/2023 8:13 | 1579903.40 | 2781948.33 | 7305 | 21049 | 3.20 | Treatment_Ponds |
| 37 | 10/18/2023 8:13 | 1579903.70 | 2781954.27 | 7305 | 20684 | 3.02 | Treatment_Ponds |
| 38 | 10/18/2023 8:13 | 1579904.71 | 2781959.77 | 7306 | 19715 | 2.54 | Treatment_Ponds |
| 39 | 10/18/2023 8:13 | 1579904.25 | 2781965.50 | 7306 | 19402 | 2.38 | Treatment_Ponds |
| 40 | 10/18/2023 8:13 | 1579903.80 | 2781971.03 | 7306 | 19788 | 2.57 | Treatment_Ponds |

(1) projection: StatePlane NAD 1983 NM West - Feet

(2) Ra-226 pCi/g determined from surface soil gamma radiation scan using 2x2 NaI detector and Site-specific gamma radiation level (cpm) correlation

PA
Sum = 193.6
Mean = 4.8
n = 40
SD = 1.6

# ATTACHMENT E-1.3
# AVM 2025 – NORTH CONTROLLED AREA

# North Controlled Area Soil Radiologic Characterization

**Mt. Taylor Mine Site**
**San Mateo, NM**

**Prepared by:**
**AVM Environmental Services, Inc.**
**1717 Del Norte Blvd.**
**Grants, NM 87020**

**Prepared for:**
**Rio Grande Resource Corporation**
**PO Box 1150**
**Grants, NM 87020**

**June 5, 2025**




N
W E
S

Environmental Services, Inc.

# Figure 1
# Mt. Taylor Mine Site
# North Controlled Area Soil Radiologic Characterization Area

June 2025

**Legend**

- NCA Soil Radiologic Characterization Area
- Previously Characterized Area
- Active Treatment Ponds
- North Controlled Fence

## Table 2
## Mt. Taylor Mine Site - North Controlled Area Soil Radiological Characterization
## Static Gamma Radiation Survey at Data Point/Soil Sample Locations


| Data Point ID | Survey Date | Data Point Coordinate NAD83 StatePlane NM West, Feet | | Static Gamma Radiation Survey Collimated (0.5" PB) 2x2 Detector | |
|---|---|---|---|---|---|
| | | Northing | Easting | Static Gamma CPM | Surface Soil Static Gamma Estimated Ra-226 pCi/g |
| TP-01 | 9/19/2024 | 1580186.76 | 2781641.72 | 74549 | 111.8 |
| TP-02 | 9/19/2024 | 1581347.96 | 2781655.87 | 23242 | 29.7 |
| TP-03 | 9/19/2024 | 1581200.16 | 2781928.52 | 12217 | 12.0 |
| TP-04 | 9/19/2024 | 1580830.01 | 2781918.97 | 11677 | 11.2 |
| TP-05 | 9/19/2024 | 1580644.14 | 2781961.31 | 7643 | 4.7 |
| TP-06 | 9/19/2024 | 1579534.44 | 2782004.83 | 28795 | 38.6 |
| TP-07 | 9/19/2024 | 1580612.66 | 2782033.15 | 7755 | 4.9 |
| TP-08 | 9/19/2024 | 1580712.40 | 2782055.84 | 9500 | 7.7 |
| TP-09 | 11/25/2024 | 1579887.40 | 2782299.57 | 26878 | 35.5 |
| TP-10 | 9/19/2024 | 1580089.57 | 2782156.92 | 10215 | 8.8 |
| TP-11 | 9/19/2024 | 1580893.36 | 2782211.56 | 17075 | 19.8 |
| TP-12 | 9/19/2024 | 1580498.58 | 2782193.94 | 7687 | 4.8 |
| TP-13 | 9/19/2024 | 1581025.34 | 2782214.93 | 25917 | 34.0 |
| TP-14 | 9/19/2024 | 1581007.22 | 2782310.10 | 31693 | 43.2 |
| TP-15 | 9/19/2024 | 1580839.32 | 2782323.98 | 10771 | 9.7 |
| TP-16 | 9/19/2024 | 1580514.25 | 2782350.77 | 20877 | 25.9 |
| TP-17 | 11/22/2024 | 1581231.06 | 2782360.91 | 9788 | 8.2 |
| TP-18 | 9/19/2024 | 1580678.19 | 2782412.82 | 23920 | 30.8 |
| TP-19 | 9/19/2024 | 1581111.05 | 2782512.59 | 108929 | 166.8 |
| TP-20 | 9/19/2024 | 1580575.91 | 2782540.15 | 42042 | 59.8 |
| TP-21 | 1/27/2025 | 1580826.78 | 2782605.83 | 189626 | 295.9 |
| TP-22 | 9/19/2024 | 1580005.97 | 2782577.72 | 27679 | 36.8 |
| TP-23 | 10/28/2024 | 1580933.72 | 2782615.38 | 11721 | 11.3 |
| TP-24 | 9/19/2024 | 1580664.84 | 2782653.22 | 184511 | 287.7 |
| TP-25 | 11/22/2024 | 1581176.90 | 2782660.86 | 15304 | 17.0 |
| TP-26 | 12/12/2024 | 1580859.02 | 2782663.51 | 154801 | 240.2 |
| TP-27 | 9/19/2024 | 1580481.71 | 2782702.25 | 116173 | 178.4 |
| TP-28 | 9/19/2024 | 1581078.62 | 2782722.31 | 69269 | 103.3 |
| TP-29 | 9/19/2024 | 1580104.95 | 2782715.01 | 37349 | 52.3 |
| TP-30 | 12/2/2024 | 1581088.55 | 2782875.42 | 7362 | 4.3 |
| TP-31 | 11/25/2024 | 1580996.95 | 2783152.31 | 76057 | 114.2 |
| TP-32 | 12/12/2024 | 1580437.62 | 2783254.26 | 11869 | 11.5 |
| TP-33 | 11/25/2024 | 1581081.58 | 2783299.76 | 11765 | 11.3 |
| TP-34 | 12/12/2024 | 1580838.74 | 2783312.73 | 18951 | 22.8 |
| TP-35 | 10/23/2024 | 1580623.09 | 2783328.09 | 31729 | 43.3 |
| TP-36 | 10/23/2024 | 1580793.59 | 2783353.65 | 12576 | 12.6 |
| TP-37 | 10/23/2024 | 1580494.41 | 2783389.94 | 9058 | 7.0 |
| TP-38 | 10/23/2024 | 1581073.21 | 2783415.97 | 13769 | 14.5 |
| TP-39 | 10/23/2024 | 1580478.54 | 2783504.44 | 9606 | 7.9 |
| TP-40 | 10/23/2024 | 1581112.23 | 2783628.43 | 13072 | 13.4 |
| Inv-01 | 9/19/2024 | 1580780.75 | 2781697.35 | 14304 | 15.4 |
| Inv-02 | 9/19/2024 | 1579936.57 | 2781697.29 | 9200 | 7.2 |
| Inv-03 | 9/19/2024 | 1581223.91 | 2781793.57 | 13157 | 13.6 |
| Inv-04 | 9/19/2024 | 1580827.72 | 2782178.60 | 36695 | 51.2 |
| Inv-05 | 10/23/2024 | 1580653.58 | 2783716.79 | 7441 | 4.4 |
| Inv-06 | 10/23/2024 | 1581080.53 | 2783861.07 | 19774 | 24.1 |
| Inv-07 | 9/19/2024 | 1580754.28 | 2781792.25 | 10142 | 8.7 |

NCA
Sum = 2278.2
Mean = 47.1
n = 47
SD = 71.9

# ATTACHMENT E-2
# EA LABORATORY MATERIAL TESTING RESULTS

# COMPACTION TEST REPORT

Curve No.




Test Specification:
ASTM D 698-12 Method A Standard

Preparation Method: Moist
Hammer Wt.: 5.5 lb.
Hammer Drop: 12 in.
Hammer Type: Manual
Layers: three Blows/Layer: 25
Mold Size: 0.03333 cu. ft.
Test Performed on Material Passing: #4 Sieve

NM: LL: NV PI: NP
Sp.G. (Assumed): 2.65
%>#4: %<No.200:
USCS: AASHTO:
Date Sampled:
Date Received:
Date Tested: 4/16/25
Tested By: SY

| TESTING DATA | 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|---|
| WM + WS | 6114.4 | 6211.7 | 6171.7 | | | |
| WM | 4251.4 | 4251.4 | 4251.4 | | | |
| WW + T #1 | 1015.2 | 1106.6 | 897.9 | | | |
| WD + T #1 | 933.6 | 1009.1 | 810.6 | | | |
| TARE #1 | 301.0 | 374.0 | 299.9 | | | |
| WW + T #2 | | | | | | |
| WD + T #2 | | | | | | |
| TARE #2 | | | | | | |
| MOISTURE | 12.9 | 15.4 | 17.1 | | | |
| DRY DENSITY | 109.1 | 112.4 | 108.5 | | | |

TEST RESULTS

Maximum dry density = 112.5 pcf

Optimum moisture = 15.0 %

Material Description: Sand

Remarks:

Project No. Client:
Project:

○ Source of Sample: EA-BSB04 Depth: 2' - 3' Sample Number: A


Checked by: AW
Title:

ENGINEERING ANALYTICS, INC.

Figure

# COMPACTION TEST REPORT

Curve No.




Test Specification:
ASTM D 698-12 Method A Standard

Preparation Method: Moist
Hammer Wt.: 5.5 lb.
Hammer Drop: 12 in.
Hammer Type: Manual
Layers: three Blows/Layer: 25
Mold Size: 0.03333 cu. ft.

Test Performed on Material
Passing: #4 Sieve

NM: LL: NV PI: NP
Sp.G. (Assumed): 2.65
%>#4: %<No.200:
USCS: AASHTO:
Date Sampled:
Date Received:
Date Tested: 4/10/25
Tested By: SY

| TESTING DATA | 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|---|
| WM + WS | 6033.2 | 6176.7 | 6127.2 | 6113.4 | | |
| WM | 4250.0 | 4250.0 | 4250.0 | 4250.0 | | |
| WW + T #1 | 1060.2 | 1080.7 | 1199.7 | 864.2 | | |
| WD + T #1 | 986.7 | 981.3 | 1095.7 | 774.7 | | |
| TARE #1 | 402.9 | 402.0 | 400.9 | 299.8 | | |
| WW + T #2 | | | | | | |
| WD + T #2 | | | | | | |
| TARE #2 | | | | | | |
| MOISTURE | 12.6 | 17.2 | 15.0 | 18.9 | | |
| DRY DENSITY | 104.8 | 108.8 | 108.0 | 103.7 | | |

TEST RESULTS

Maximum dry density = 109.3 pcf

Optimum moisture = 16.4 %

Material Description: Sandy Clay

Remarks:

Project No. Client:
Project:

○ Source of Sample: EA-BSC12 Depth: 2' - 3' Sample Number: A


Checked by: AW
Title:

ENGINEERING ANALYTICS, INC.

Figure

# COMPACTION TEST REPORT

Curve No.




Test Specification:
ASTM D 698-12 Method A Standard

| | |
|---|---|
| Preparation Method | Moist |
| Hammer Wt. | 5.5 lb. |
| Hammer Drop | 12 in. |
| Hammer Type: | Manual |
| Layers | three |
| Blows/Layer | 25 |
| Mold Size | 0.03333 cu. ft. |

Test Performed on Material
Passing #4 Sieve

NM LL 26 PI 8
Sp.G. (Assumed): 2.65
%>#4 %<No.200
USCS AASHTO
Date Sampled
Date Received
Date Tested 4/16/2025
Tested By SY

| TESTING DATA | 1 | 2 | 3 | 4 | 5 | 6 |
|---|---|---|---|---|---|---|
| WM + WS | 6020.3 | 6179.7 | 6154.5 | | | |
| WM | 4250.8 | 4250.8 | 4250.8 | | | |
| WW + T #1 | 1243.0 | 1130.4 | 1178.8 | | | |
| WD + T #1 | 1136.1 | 1027.5 | 1056.4 | | | |
| TARE #1 | 370.5 | 375.5 | 369.7 | | | |
| WW + T #2 | | | | | | |
| WD + T #2 | | | | | | |
| TARE #2 | | | | | | |
| MOISTURE | 14.0 | 15.8 | 17.8 | | | |
| DRY DENSITY | 102.7 | 110.2 | 106.9 | | | |

TEST RESULTS

Maximum dry density = 110.4 pcf

Optimum moisture = 16.1 %

Material Description

Silty Clay

Remarks:


Project No. Client:
Project:

○ Source of Sample: EA-BSC09 Depth: 2' - 3' Sample Number: A

Checked by: KG
Title:

ENGINEERING ANALYTICS, INC.

Figure


Soil Water Characteristic Curve
Mt. Taylor - 111360
EA-BSC-09 @ 2' - 3'
1000000
100000
10000
1000
100
10
1
Suction (kPa)
135,450
117,060
112,730
56,900
40,120
500
250
100
50
25
5
0.000
0.050
0.100
0.150
0.200
0.250
0.300
0.350
0.400
Volumetric Water Content Θ
Pressure Plate
Chilled Mirror Hygrometer

# ATTACHMENT E-3
# RADON MODEL OUTPUT

## Layer Data HELP

| Layer No. | Thickness [m] | Ra-226 Activity Conc. [pCi/g] | Rn-222 Emanation Fraction | Porosity | Moisture Cont. [dry wt_%] | Fraction Passing #200 Mesh (75 µm) *) | Rn-222 Eff. Diff.Coeff *) [$m^2/s$] |
|---|---|---|---|---|---|---|---|
| 1 | 5 | 101 | 0.35 | 0.35 | 15.1 | | |
| 2 | .30 | 0 | .35 | .38 | 15.1 | | |
| 3 | .84 | 0 | .35 | .35 | 6 | | |
| 4 | .30 | 0 | .35 | .35 | 6 | | |
| 5 | | | | | | | |
| 6 | | | | | | | |
| 7 | | | | | | | |
| 8 | | | | | | | |

## Options HELP

- Entrance Radon flux to Layer 1 [$pCi/m^2s$] *)
- Surface Radon conc. at top of system [pCi/L] *)
- Layer No. to be optimized *)
- Surface flux constraint for optimization [$pCi/m^2s$] *)
- Surface flux convergence criterion (fraction) *)
- Annual Precipitation [cm] *)
- Annual Lake Evaporation [cm] *)
- Depth to Water Table [m] *)

*) optional

Calculate Reset Form HELP

## Results

```
 No.     [m]     [pCi/g]  Fract            [dry wt_%]  [m2/s]
  1    5         101      0.35     0.35      15.1       169.1E-9
  2    0.3       0        .35      0.38      15.1       462.0E-9
  3    0.84      0        .35      0.35      6          2.013E-6
  4    0.3       0        .35      0.35      6          2.013E-6


--------  Results of Radon Diffusion Calculation  --------

Layer  Thickness   Exit Flux  Exit Conc.     MIC
 No.      [m]      [pCi/m2s]   [pCi/L]
  1     5           27.35       46.12E3     0.440
  2     0.3         19.49       14.55E3     0.508
  3     0.84        11.61       4.796E3     0.777
  4     0.3         11.09       0E0         0.777

Total cover radon retention: 70.01%
```

## Layer Data HELP

| Layer No. | Thickness [m] | Ra-226 Activity Conc. [pCi/g] | Rn-222 Emanation Fraction | Porosity | Moisture Cont. [dry wt_%] | Fraction Passing #200 Mesh (75 µm) *) | Rn-222 Eff. Diff.Coeff *) [$m^2/s$] |
|---|---|---|---|---|---|---|---|
| 1 | 5 | 101 | 0.35 | 0.35 | 15.1 | | |
| 2 | .46 | 0 | .35 | .38 | 15.1 | | |
| 3 | .84 | 0 | .35 | .35 | 6 | | |
| 4 | .30 | 0 | .35 | .35 | 6 | | |
| 5 | | | | | | | |
| 6 | | | | | | | |
| 7 | | | | | | | |
| 8 | | | | | | | |

## Options HELP

- Entrance Radon flux to Layer 1 [$pCi/m^2s$] *)
- Surface Radon conc. at top of system [pCi/L] *)
- Layer No. to be optimized *)
- Surface flux constraint for optimization [$pCi/m^2s$] *)
- Surface flux convergence criterion (fraction) *)
- Annual Precipitation [cm] *)
- Annual Lake Evaporation [cm] *)
- Depth to Water Table [m] *)

*) optional

Calculate Reset Form HELP

## Results


| No. | [m] | [pCi/g] | Fract | | [dry wt_%] | [m2/s] |
|---|---|---|---|---|---|---|
| 1 | 5 | 101 | 0.35 | 0.35 | 15.1 | 169.1E-9 |
| 2 | 0.46 | 0 | .35 | 0.38 | 15.1 | 462.0E-9 |
| 3 | 0.84 | 0 | .35 | 0.35 | 6 | 2.013E-6 |
| 4 | 0.3 | 0 | .35 | 0.35 | 6 | 2.013E-6 |

-------- Results of Radon Diffusion Calculation --------

| Layer No. | Thickness [m] | Exit Flux [pCi/m2s] | Exit Conc. [pCi/L] | MIC |
|---|---|---|---|---|
| 1 | 5 | 26.19 | 51.69E3 | 0.440 |
| 2 | 0.46 | 14.22 | 10.61E3 | 0.508 |
| 3 | 0.84 | 8.474 | 3.499E3 | 0.777 |
| 4 | 0.3 | 8.091 | 0E0 | 0.777 |

Total cover radon retention: 78.12%

# APPENDIX F
# Selected Results of Infiltration Analysis




Draw Graph

Add | Delete

| Name | Y | X |
|---|---|---|
| water balance - transpi... | Cumulative Tra... | Time |
| Water Balance Error: C... | Rel Water Balan... | Time |
| Water Flux | Water Total Head | Dista... |
| Water Flux From Clay t... | Water Y Flux | Time |

Name: Water Flux From Clay to Waste

Kind: Mesh

Set Locations...


Water Flow | Water Y Flux

vs. Time | d

Select Steps: All

| Step | Elapsed Time ... | Analysis Name |
|---|---|---|
| 0 | 3,650 | Transient Seepage (1000) |
| 500 | 8,650 | Transient Seepage (1000) |
| 1400 | 17,650 | Transient Seepage (1000) |
| 2300 | 26,650 | Transient Seepage (1000) |
| 3200 | 35,650 | Transient Seepage (1000) |
| 4100 | 44,650 | Transient Seepage (1000) |

Sum (Y) vs. Average (X) Values





Legend | Use Auto Scale

Auto Refresh | X Axis Range:

Refresh | to

Undo | Redo | Help | More | Close




Draw Graph

Add | Delete

| Name | Y | X |
|---|---|---|
| VWC vs Time | VWC | Time |
| water balance - transpi... | Cumulative Tra... | Time |
| water balance - transpi... | Cumulative Tra... | Time |
| Water Balance Error: C... | Water Balance Err | Time |

Name: Water Balance Error: Clay

Kind: Mesh

Set Locations...


Water Mass Balance | Water Balance Error

vs. Time | Default

Select Steps: All

| Step | Elapsed Time ... | Analysis Name |
|---|---|---|
| 0 | 3,650 | Transient Seepage (1000) |
| 500 | 8,650 | Transient Seepage (1000) |
| 1400 | 17,650 | Transient Seepage (1000) |
| 2300 | 26,650 | Transient Seepage (1000) |
| 3200 | 35,650 | Transient Seepage (1000) |
| 4100 | 44,650 | Transient Seepage (1000) |

Sum (Y) vs. Average (X) Values





Legend | Use Auto Scale

Auto Refresh | X Axis Range:

Refresh | to

Undo | Redo | Help | More | Close




Draw Graph

Add | Delete

| Name | Y | X |
|---|---|---|
| Water Balance Error: C... | Water Balance Err | Time |
| Water Flux | Water Total Head | Dista... |
| Water Flux From Clay t... | Water Y Flux | Time |
| water storage: clay | Domain Water ... | Time |

Name: water storage: clay

Kind: Mesh

Set Locations...


Water Mass Balance | Domain Water Volume

vs. Time | d

Select Steps: All

| Step | Elapsed Time ... | Analysis Name |
|---|---|---|
| 0 | 3,650 | Transient Seepage (1000) |
| 500 | 8,650 | Transient Seepage (1000) |
| 1400 | 17,650 | Transient Seepage (1000) |
| 2300 | 26,650 | Transient Seepage (1000) |
| 3200 | 35,650 | Transient Seepage (1000) |
| 4100 | 44,650 | Transient Seepage (1000) |

Sum (Y) vs. Average (X) Values





Legend | Use Auto Scale

Auto Refresh | X Axis Range: to

Refresh

Undo | Redo | Help | More | Close




Draw Graph

Add | Delete

| Name | Y | X |
|---|---|---|
| (2024)water balance - ... | Cumulative Runoff | Time |
| (2024)water balance - ... | Cumulative Pote... | Time |
| (2024)water balance: d... | Cum Water Vol... | Time |
| Cummulative Change in... | Cumulative Cha... | Time |

Name: ative Change in Water Volume (Cover System)

Kind: Mesh

Set Locations...


Water Mass Balance | Cumulative Change in Domain

vs. Time | Default

Select Steps: All

| Step | Elapsed Time ... | Analysis Name |
|---|---|---|
| 0 | 3,650 | Transient Seepage (1000) |
| 500 | 8,650 | Transient Seepage (1000) |
| 1400 | 17,650 | Transient Seepage (1000) |
| 2300 | 26,650 | Transient Seepage (1000) |
| 3200 | 35,650 | Transient Seepage (1000) |
| 4100 | 44,650 | Transient Seepage (1000) |

Sum (Y) vs. Average (X) Values





Legend | Use Auto Scale

Auto Refresh | X Axis Range:

Refresh | to

Undo | Redo | Help | More | Close




Draw Graph

Add | Delete

| Name | Y | X |
|---|---|---|
| Water Balance Error: C... | Water Balance Err | Time |
| Water Flow Through C... | Cum Water Vol... | Time |
| Water Flux | Water Total Head | Dista... |
| Water Flux From Clay t... | Water Y Flux | Time |

Name: Water Flow Through Cover System

Kind: Mesh

Set Locations...


Water Flow | Cumulative Water Volume

vs. Time | Default

Select Steps: All

| Step | Elapsed Time ... | Analysis Name |
|---|---|---|
| 0 | 3,650 | Transient Seepage (1000) |
| 500 | 8,650 | Transient Seepage (1000) |
| 1400 | 17,650 | Transient Seepage (1000) |
| 2300 | 26,650 | Transient Seepage (1000) |
| 3200 | 35,650 | Transient Seepage (1000) |
| 4100 | 44,650 | Transient Seepage (1000) |

Sum (Y) vs. Average (X) Values





Legend | Use Auto Scale

Auto Refresh | X Axis Range:

Refresh | to

Undo | Redo | Help | More | Close




Draw Graph

Add | Delete

| Name | Y | X |
|---|---|---|
| cumulative change in m... | Cumulative Cha... | Time |
| error: cumulative | Water Balance Err | Time |
| Fkux Section | Water Y Flux | Time |
| Flux Through Cover Syt... | Water Y Flux | Time |

Name: Flux Through Cover Sytem

Kind: Mesh

Set Locations...


Water Flow | Water Y Flux

vs. Time | Default

Select Steps: All

| Step | Elapsed Time ... | Analysis Name |
|---|---|---|
| 0 | 3,650 | Transient Seepage (1000) |
| 500 | 8,650 | Transient Seepage (1000) |
| 1400 | 17,650 | Transient Seepage (1000) |
| 2300 | 26,650 | Transient Seepage (1000) |
| 3200 | 35,650 | Transient Seepage (1000) |
| 4100 | 44,650 | Transient Seepage (1000) |

Sum (Y) vs. Average (X) Values




Legend | Use Auto Scale

Auto Refresh | X Axis Range:

Refresh | to

Undo | Redo | Help | More | Close

# APPENDIX G
# CLIMATE DATA COMPARISON

Engineering Analytics, Inc.
Now Part of MacKay

Fort Collins Office
1600 Specht Point Road, Suite 209, Fort Collins, CO 80525
970.488.3111 / GoMacKay.com

# *Technical Memorandum*

| | | | |
|---|---|---|---|
| **To:** | Rio Grande Resources | **From:** | Jason Andrews, PE<br>Olu Iwakun, P.Eng |
| **Company:** | Rio Grande Resources | **Date:** | August 5, 2026 |
| **EA No.:** | 111360 | | |
| **Re:** | Statistical Comparison of 2018–2025 Climate Data to Historical and Regional Design-Support Datasets – Mt. Taylor / San Mateo Area | | |
| **Cc:** | | | |

## 1.0 INTRODUCTION

The Mt. Taylor Uranium Mine is in the San Mateo area of west-central New Mexico, at an elevation of approximately 7,400 feet above mean sea level. An on-site automated weather station has collected continuous meteorological data since October 2017. This memorandum uses complete calendar years (January through December 2018–2025) for annual statistical comparisons.

This memorandum presents a statistical comparison of recent climate conditions (2018–2025) to the broader historical record used for Mt. Taylor disposal cell design support near San Mateo and Grants, New Mexico. The analysis focuses on three climate variables critical to long-term cover performance and design: annual precipitation, mean annual temperature, and the Air Freezing Index (AFI). Unless otherwise noted, references to AppD3-1, AppD3-2, and AppD3-3 refer to Appendices D3-1 through D3-3 of the 2025 *Mt. Taylor Disposal Cell Design Report* prepared by Engineering Analytics, Inc. for Rio Grande Resources, Project No. 111360. The primary goal is to assess whether the regional meteorological data and design-basis climate inputs, including the Gallup 1981–2010 precipitation normal, the AppD3-1 temperature comparison dataset, the AppD3-2 AFI comparison dataset, and the NCEI NM3422 long-term temperature trend record is statistically consistent with the recent, onsite, climate period (2018–2025).

### 1.1 Data Sources

Recent site climate data (2018–2025) were obtained from the San Mateo station dataset. Long-term regional precipitation context is based on the Gallup Municipal Airport 30-year climate normal, which provides the most appropriate standardized annual precipitation baseline for the Mt. Taylor area because it is a published NCDC/NCEI climate normal, covers the standard 1981–2010 climatological averaging period, represents the same regional semi-arid precipitation regime, and provides a complete annual normal where the NM3422 Grants dataset does not provide a complete annual precipitation series suitable for this comparison. Rice Park SNOTEL is used separately for high-elevation snowpack, snow water equivalent (SWE), winter precipitation, frost penetration, accumulated freezing index (AFI), snowmelt infiltration, and Rio San Jose Integrated Hydrologic Model (RSJIHM) calibration. These datasets are complementary but not interchangeable.

### 1.2 Analytical Approach

This analysis is structured to determine whether the complete San Mateo on-site climate record for 2018–2025 is consistent with the historical and regional datasets used to support the Mt. Taylor disposal cell design basis. The comparison is not intended to prove that separate datasets are identical or interchangeable. Instead, it evaluates whether recent site observations fall within the range of conditions represented by the applicable design-support datasets. This distinction is important because each dataset serves a different technical purpose: Gallup provides the long-term annual precipitation normal, AppD3-1 and AppD3-2 from EA's 2025 *Mt. Taylor Disposal Cell Design Report* provide historical temperature and AFI comparison datasets, NCEI NM3422 provides long-term regional temperature trend context, and Rice Park SNOTEL supports winter hydrology, snowpack, SWE, frost penetration, AFI calibration, snowmelt infiltration, and RSJIHM calibration.

The analytical approach combines descriptive statistics, targeted hypothesis testing, and visual diagnostics. Descriptive statistics summarize the San Mateo annual record for precipitation, mean annual temperature, and AFI using the mean, standard deviation, range, and observed minimum and maximum values. The San Mateo summary statistics are then compared with the appropriate design-support benchmarks: the Gallup 1981–2010 annual precipitation normal, AppD3-1 temperature values, the historical-only AppD3-2 AFI values, and NCEI NM3422 long-term temperature trend data. A one-sample t-test is used for San Mateo precipitation against the Gallup annual normal, while Welch's two-sample t-tests are used for mean annual temperature and AFI because those comparisons involve samples with unequal sizes and variances. The results are interpreted in terms of design relevance, with emphasis on whether the recent site record supports continued use of the existing precipitation, temperature, AFI, water-balance, and frost-penetration assumptions.

## 2.0 SITE DESCRIPTION, CLIMATE SETTING, AND DATA SOURCES

### 2.1 Site Setting and Regional Climate Context

The Mt. Taylor Uranium Mine disposal cell area is in the San Mateo Mountains of Cibola County, New Mexico, within the southern Colorado Plateau physiographic province at an elevation of approximately 7,400 feet above mean sea level. The climate is semi-arid continental, characterized

by low humidity, high solar radiation, large diurnal temperature swings, and a pronounced North American Monsoon precipitation pattern during July through September.

For historical context, this analysis references NCEI station NM3422 (Grants, New Mexico), regional precipitation normals from Gallup Municipal Airport, Rice Park SNOTEL winter hydrology data, and summary statistics from the Mt. Taylor Mine design report. Gallup is used as the regional mean annual precipitation baseline because it is the nearest appropriate standardized 30-year climate normal with a published annual precipitation value, represents the same broad semi-arid regional precipitation setting, and provides a defensible long-term reference where NM3422 does not provide a complete annual precipitation series suitable for this comparison. Rice Park is used for SWE, snowpack, winter precipitation, AFI, frost penetration, snowmelt infiltration, and RSJIHM calibration because those processes cannot be evaluated from the Gallup climate normal.

## 2.2 Regional Climate Overview

Mean annual temperature in the region ranges from approximately 48°F to 54°F depending on elevation and period of record. NCEI Station NM3422 at Grants, New Mexico, records a mean annual temperature of approximately 49.93°F for the 1975–2025 period, with a statistically significant warming trend of +0.033°F per year ($R^2 = 0.37$, $p < 0.001$). Precipitation is bimodal, with a dominant monsoon contribution in summer and a secondary winter precipitation season. The 1981–2010 climate normal at Gallup Municipal Airport (NCDC Station 293422) gives an average annual precipitation of 11.65 inches.

The Gallup normal is used in this memo for annual precipitation comparison because it is a published 30-year climatological normal rather than a short-term site record, and it therefore provides a stable regional benchmark for evaluating whether the 2018–2025 San Mateo record is anomalous. Its use is limited to annual precipitation context and statistical comparison; it is not used to characterize site-specific storm intensity, snowpack, SWE, or winter hydrologic processes.

## 2.3 Instrumentation and Station Description

The on-site San Mateo weather station provides automated recording of temperature (maximum, minimum, and mean), precipitation (tipping bucket rain gauge), wind speed and direction, and derived parameters including heating and cooling degree days. Data collection began in October 2017. Only complete calendar years (2018–2025) are used for annual analyses.

# 3.0 HYDROLOGIC AND THERMAL CHARACTERIZATION

This section characterizes the site's hydrologic regime, thermal profile, and precipitation frequency using data from the San Mateo station, NCEI NM3422 (Grants, NM), and regional frequency analyses.

## 3.1 Monthly Precipitation and Evapotranspiration

Site monthly precipitation exhibits a pronounced summer monsoon pattern, with precipitation elevated during May through September and strongest during July through September. July has the highest San Mateo monthly average of 2.05 inches. Potential evapotranspiration (PET), estimated via the Thornthwaite method, peaks in July at 5.26 inches. On an annual basis, PET substantially exceeds precipitation; monthly PET exceeds precipitation during the primary warm-season moisture-demand period, while several winter months show small monthly precipitation surpluses. Table 3-1 and Figure 3-1 present the monthly comparison.

**Table 3-1 Monthly Precipitation and Potential Evapotranspiration (PET) Summary**

| Month | Precipitation (in) | Potential ET (in) | Monthly Deficit (in) |
|---|---|---|---|
| January | 0.38 | 0.00 | −0.38 |
| February | 0.26 | 0.16 | −0.10 |
| March | 0.48 | 0.69 | 0.21 |
| April | 0.28 | 1.76 | 1.48 |
| May | 0.71 | 3.15 | 2.44 |
| June | 0.94 | 4.74 | 3.80 |
| July | 2.05 | 5.26 | 3.21 |
| August | 1.71 | 4.70 | 2.99 |
| September | 1.45 | 3.46 | 2.01 |
| October | 0.86 | 1.83 | 0.97 |
| November | 0.59 | 0.57 | −0.02 |
| December | 0.30 | 0.13 | −0.17 |
| **Annual Total** | **10.01** | **26.45** | **16.44** |





**Figure 3-1 Monthly Precipitation and Potential Evapotranspiration**

## 3.2 Precipitation Depth-Duration-Frequency

Table 3-2 and Figure 3-2 summarize precipitation depth-duration-frequency data for the site, using regional frequency analysis. Table 3-2 lists precipitation depths for various return periods (2 to 100 years) and durations (1-hour to 24-hour), showing that longer return periods correspond to higher rainfall amounts; for example, the 24-hour depth for a 2-year event is 1.2 inches, increasing for rarer storms. These values inform stormwater management design.

**Table 3-2 Precipitation Depth-Duration-Frequency Summary (inches)**

| Return Period (years) | 1-Hour | 6-Hour | 12-Hour | 24-Hour |
|---|---|---|---|---|
| 2 | 0.72 | 0.94 | 1.05 | 1.20 |
| 5 | 0.96 | 1.19 | 1.32 | 1.50 |
| 10 | 1.14 | 1.39 | 1.53 | 1.74 |
| 25 | 1.39 | 1.66 | 1.82 | 2.06 |
| 50 | 1.58 | 1.88 | 2.04 | 2.31 |
| 100 | 1.78 | 2.10 | 2.27 | 2.56 |





**Figure 3-2 Precipitation Depth-Duration-Frequency (DDF) Curves**

Figure 3-2 compares precipitation depths across durations and return periods. The curves show increasing depth with both longer duration and rarer recurrence intervals, including the 100-year, 24-hour storm depth of 2.56 inches. These values support stormwater conveyance, erosion protection, and run-on/runoff control design.

## 3.3 Cumulative Water Balance

Figure 3-3 shows cumulative water-year precipitation of 10.01 inches and PET of 26.45 inches, producing an annual moisture deficit of 16.44 inches. The aridity index of 0.38 classifies the site as semi-arid under the UNESCO definition (AI < 0.50) and confirms that annual evapotranspiration demand substantially exceeds precipitation.

**Table 3-3 Annual Water Balance Summary**

| Component | Value (inches/year) | Source |
|---|---|---|
| Annual Precipitation (P) | 10.01 | San Mateo station 2018–2025 monthly means |
| Estimated Annual PET | 26.45 | Thornthwaite method (site temperatures at 35°N) |
| Annual Moisture Deficit (PET − P) | 16.44 | Calculated |
| Aridity Index (P/PET) | 0.38 | Calculated (semi-arid classification) |
| Gallup Annual Normal Precipitation | 11.65 | NCDC 1981–2010 normals |





**Figure 3-3 Cumulative Water Year Precipitation and PET Analysis**

Table 3-3 summarizes the annual water-balance components supporting Figure 3-3. Annual precipitation is based on San Mateo monthly means, while PET is estimated using the Thornthwaite method. The annual precipitation total of 10.01 inches is substantially lower than the estimated annual PET of 26.45 inches, resulting in a persistent annual moisture deficit. Together, Table 3-3 and Figure 3-3 confirm the site's semi-arid hydrologic setting and support use of evapotranspiration-based cover-system design assumptions

### 3.4 Regional Temperature Trend

Analysis of NCEI Station NM3422 (Grants, NM) mean annual temperature data for 1975–2025 reveals a statistically significant warming trend of +0.033°F per year ($R^2 = 0.37$, $p < 0.001$), corresponding to approximately 1.7°F of total warming over 51 years. The San Mateo on-site temperatures (2018–2025) plot consistently above the NCEI station values, reflecting station exposure, instrumentation, and local microclimate differences between the Grants station and the mine site. This regional warming trend provides context for interpreting the site-to-historical temperature comparison in Section 6. The time series and trend line are presented in Figure 3-4.





**Figure 3-4 Mean Annual Temperature Trend (NCEI Station NM3422, Grants, NM)**

## 4.0 METHODOLOGY AND STATISTICAL FRAMEWORK

The comparative analysis uses a multi-tiered statistical framework designed to answer the regulatory and engineering question raised in review: whether the recent San Mateo site record is consistent with the climate datasets used to support Mt. Taylor design assumptions. Each method below is included to show what was calculated, why it matters, and how the result informs use of the Gallup precipitation normal, the AppD3 temperature and AFI appendix datasets from EA's 2025 *Mt. Taylor Disposal Cell Design Report*, and Rice Park winter hydrology information.

## 4.1 Descriptive Statistics

For each applicable dataset, the mean, standard deviation, variance, minimum, and maximum were computed where the underlying annual values were available. These statistics matter because they show both the central tendency and the spread of the record; a recent site mean that falls within normal historical variability supports continued use of the existing design-basis climate inputs.

$$\bar{x} = \frac{\sum x_i}{n}, s = \sqrt{\frac{\sum (x_i - \bar{x})^2}{n-1}}$$

Where a dataset is represented only by a published climatological normal, such as the Gallup annual precipitation normal, the analysis uses that value as the long-term regional mean rather than treating it as a full annual distribution.

## 4.2 Hypothesis Testing Framework

Mean annual temperature and AFI were compared between the recent period (2018–2025) and the historical baseline (1975–2024) using Welch's two-sample t-test, which does not assume equal variances or equal sample sizes. This method is appropriate because the historical and recent datasets have unequal variances and sample sizes. The test statistics are:

$$t = \frac{\bar{x}_1 - \bar{x}_2}{\sqrt{\frac{s_1^2}{n_1} + \frac{s_2^2}{n_2}}},$$

with $\bar{x}_1, s_1, n_1$ and $\bar{x}_2, s_2, n_2$ denoting the means, standard deviations, and sample sizes for the recent and historical periods, respectively. A Welch-type t-test (unequal variances) is appropriate given the differing standard deviations. Effect sizes are summarized using Cohen's d, defined as:

$$d = \frac{\bar{x}_1 - \bar{x}_2}{s_{\text{pooled}}},$$

Where $s_{\text{pooled}}$ is the pooled standard deviation. Effect sizes were interpreted using conventional screening thresholds of $|d| \approx 0.2$, 0.5, and 0.8 for small, medium, and large effects, respectively. These thresholds were used only to describe practical magnitude; statistical decisions were based on the two-tailed p-values at $\alpha = 0.05$. The tests are complemented by visual diagnostics (boxplots, histograms, and time series) to help reviewers see whether the recent San Mateo record plots within the historical or regional comparison range.

San Mateo precipitation is compared to the Gallup NCDC 30-year normal using a one-sample t-test because Gallup provides the applicable long-term regional annual precipitation mean and the available historical precipitation baseline is represented by a climatological normal rather than a complete annual distribution. Gallup is used for this test because it supplies a published, standardized, 30-year annual precipitation benchmark for the same regional semi-arid climate setting, whereas NM3422 lacks a complete annual precipitation series for direct annual comparison

and Rice Park is intended for SWE and winter hydrology applications. For a one-sample test, the test statistics are:

$$t = \frac{\bar{x} - \mu_0}{s/\sqrt{n}},$$

where $\bar{x}$is the sample mean, $s$is the sample standard deviation, $n$is the sample size, and $\mu_0$is the hypothesized population mean. The null hypothesis $H_0$is that the recent mean equals the historical mean; the alternative $H_A$is that they differ (two-sided test). Degrees of freedom are $n - 1$, and p-values are obtained from the t distribution.

This method is applicable because the historical precipitation dataset is represented by a single climatological normal, not a full distribution. This test evaluates whether the San Mateo mean differs from the long-term regional mean.

### 4.3 Recurrence-Interval and Extremal Analysis

AFI values were ranked within the historical distribution to determine exceedance probabilities and recurrence intervals. This analysis is included because frost penetration and cover-system performance are controlled by infrequent severe freezing years rather than average annual conditions alone; therefore, AFI return-period estimates provide the design context for comparing recent San Mateo observations with the conservative design-basis AFI.

### 4.4 Non-Parametric Considerations

A Mann–Whitney U test is typically used for precipitation when comparing two full distributions. However, because the historical precipitation dataset is represented by a single normal (not a full annual series), the one-sample t-test is the appropriate method for this analysis.

**Table 4-1 San Mateo Station Annual Climate Summary (2018–2025)**

| Year | Annual Precipitation (in) | Mean Annual Temperature (°F) | Air Freezing Index (degree-days) |
|---|---|---|---|
| 2018 | 10.86 | 52.7 | 401 |
| 2019 | 11.90 | 50.8 | 330 |
| 2020 | 7.84 | 52.9 | 311 |
| 2021 | 8.56 | 52.2 | 307 |
| 2022 | 15.33 | 50.8 | 524 |
| 2023 | 8.42 | 51.4 | 312 |
| 2024 | 10.46 | 52.5 | 236 |
| 2025 | 6.81 | 54.9 | 83 |

# 5.0 DATA SOURCES AND COMPARATIVE DATASETS

## 5.1 On-Site Data (San Mateo Station, 2018–2025)

Table 5-1 presents the complete annual climate summary from the San Mateo on-site weather station for all eight years of complete record. The data show year-to-year variability in precipitation, temperature, and Air Freezing Index, providing a basis for comparative climate analysis.

## 5.2 Historical Baseline Sources

The historical and regional baseline relies on the San Mateo site record, regional NCEI and Gallup datasets, the AppD3 appendices from the Mt. Taylor disposal cell design report, and Rice Park SNOTEL winter hydrology data. These sources are used for different technical purposes and should not be treated as interchangeable.

NCEI Station NM3422 at Grants, New Mexico, provides the regional mean annual temperature record used to evaluate long-term temperature trends from 1975 through 2025. The NM3422 trend record provides climate context, while Appendix D3-1 of the 2025 *Mt. Taylor Disposal Cell Design Report* provides the historical comparison statistics used for the Section 6 temperature test.

Appendices D3-1 through D3-3 are appendices to Engineering Analytics, Inc.'s 2025 *Mt. Taylor Disposal Cell Design Report* for Rio Grande Resources, Project No. 111360. They are not separate monitoring stations or independent source documents. Appendix D3-1 provides the mean annual temperature distribution used for the historical temperature comparison. Appendix D3-2 provides the Air Freezing Index distribution used for the AFI comparison and return-period analysis; for statistical testing, San Mateo site values embedded in the combined AppD3-2 population were removed to create an independent historical-only subset. Appendix D3-3 is retained as part of the same design-support appendix set and should be cited with the other D3 appendices when referencing the underlying design report.

The Gallup Municipal Airport climate normals for NCDC Station 293422 provide the standardized 1981–2010 regional annual precipitation normal used as the long-term precipitation benchmark. The 11.65-inch annual normal is appropriate for statistical comparison because it is a published 30-year climatological normal, represents the broader semi-arid precipitation regime around the Mt. Taylor area, and provides a complete annual precipitation benchmark where NM3422 does not provide a suitable annual precipitation series. Gallup is used only for annual precipitation context and is not used to represent SWE, snow accumulation, or winter hydrologic processes.

Table 5-2 presents the Gallup monthly climate normals to document the source of the 11.65-inch annual precipitation benchmark used in the comparison with the San Mateo annual precipitation record. Its inclusion does not imply that Gallup replaces site-specific San Mateo monitoring or Rice Park winter hydrology data.

Rice Park SNOTEL is used as a separate, complementary high-elevation winter hydrology dataset. It supports SWE, snowpack, winter precipitation, snowmelt infiltration, frost penetration, AFI calibration, and RSJIHM calibration. Because Gallup and Rice Park represent different climate processes and elevation settings, Gallup establishes the regional annual precipitation baseline while Rice Park supplies winter hydrologic information needed for model support where snow accumulation and melt timing affect seasonal infiltration.

**Table 5-1 1981–2010 Monthly Climate Normals — Gallup Municipal Airport (NCDC 293422)**

| Month | Avg Max Temp (°F) | Avg Min Temp (°F) | Avg Total Precipitation (in) |
|---|---|---|---|
| January | 44.7 | 13.3 | 0.80 |
| February | 49.5 | 18.4 | 0.72 |
| March | 56.8 | 22.7 | 0.79 |
| April | 65.0 | 28.3 | 0.61 |
| May | 74.9 | 36.7 | 0.54 |
| June | 84.6 | 45.1 | 0.53 |
| July | 87.8 | 53.4 | 1.73 |
| August | 84.9 | 52.7 | 2.07 |
| September | 78.7 | 43.5 | 1.29 |
| October | 67.6 | 30.7 | 0.94 |
| November | 53.1 | 19.7 | 0.83 |
| December | 45.1 | 13.7 | 0.81 |
| **Annual** | **66.2** | **31.6** | **11.65** |

## 5.3 Historical Baseline Statistics

Table 5-3 summarizes the historical baseline statistics used in the hypothesis testing in Section 6. As noted in Section 1, AppD3-1, AppD3-2, and AppD3-3 refer to appendices in the 2025 *Mt. Taylor Disposal Cell Design Report* prepared by Engineering Analytics, Inc. For the Air Freezing Index, the AppD3-2 distribution contains San Mateo site values (2018–2024) embedded within the combined population. To ensure an independent comparison, the historical-only subset was isolated by removing the seven known site values, yielding n = 34 independent historical observations.

**Table 5-2 Historical Baseline Statistical Summary**

| Parameter | Source | Period | n | Mean | Standard Deviation |
|---|---|---|---|---|---|
| Mean Annual Temperature (°F) | AppD3-1 (NCEI NM3422) | 1975–2021 | 42 | 51.52 | 2.37 |
| Annual Precipitation (in) | Gallup NCDC 30-yr Normal | 1981–2010 | 30 | 11.65 | — |
| Air Freezing Index (degree-days) | AppD3-2 (historical only) | 1975–2017 | 34 | 225.15 | 169.27 |

*Note: AppD3-2 historical-only subset excludes San Mateo site AFI values (2018–2024) from the combined n = 50 population to ensure statistical independence.*

## 5.4 Descriptive Statistics Comparison

Table 5-4 shows descriptive statistics for the Gallup normal and San Mateo datasets, allowing direct comparison of annual precipitation from 2018–2025 against a long-term regional precipitation benchmark. Gallup is used for this comparison because it provides a standardized 30-year annual normal rather than a short-term record, giving reviewers a stable basis for determining whether recent site precipitation is outside expected regional conditions. The comparison is therefore intended to evaluate consistency with the regional annual precipitation design basis, not to substitute Gallup for site-specific monitoring or Rice Park winter hydrology data.

Gallup Normal's annual precipitation averages 11.65 inches over the 1981–2010 climatological normal period. Because the normal is used as a published annual benchmark rather than a complete annual distribution, only the mean is used in the one-sample precipitation comparison. The San Mateo record provides recent site-specific annual variability, while Gallup provides the long-term regional annual precipitation reference.

Table 5-4 illustrates how San Mateo's recent precipitation and climate statistics compare to the applicable historical or regional benchmarks used for Mt. Taylor Mine design support. These comparisons support evaluation of cover-system performance, infiltration model inputs, stormwater design assumptions, and frost-penetration design criteria.

**Table 5-3 Descriptive Statistics Comparison — Historical vs. San Mateo (2018–2025)**

| Parameter | Dataset | n | Mean | SD | Variance | Min | Max |
|---|---|---|---|---|---|---|---|
| Annual Precip (in) | Gallup Normal | 30 | 11.65 | — | — | — | — |
| Annual Precip (in) | San Mateo | 8 | 10.02 | 2.74 | 7.48 | 6.81 | 15.33 |
| Mean Temp (°F) | AppD3-1 Historical | 42 | 51.52 | 2.37 | 5.62 | 46.66 | 57.71 |
| Mean Temp (°F) | San Mateo | 8 | 52.27 | 1.34 | 1.81 | 50.80 | 54.90 |
| AFI (degree-days) | AppD3-2 Historical | 34 | 225.15 | 169.27 | 28,652 | 46 | 786 |
| AFI (degree-days) | San Mateo | 8 | 313.00 | 126.17 | 15,918 | 83 | 524 |

# 6.0 STATISTICAL TESTING

## 6.1 Analysis Basis

As discussed in Section 4, three statistical hypothesis tests were conducted to determine whether the San Mateo site record for 2018–2025 (n = 8) differs significantly from the historical climate population. All tests were performed as two-tailed analyses at the $\alpha = 0.05$ significance level, corresponding to 95% confidence.

Section 4 outlines the methodology for evaluating annual precipitation. This assessment compares the San Mateo site mean precipitation to the Gallup NCDC 30-year normal of 11.65 inches, treating the Gallup normal as the regional population mean for annual precipitation. EA selected this benchmark because it is a published 1981–2010 30-year climate normal, represents the same broad semi-arid precipitation regime, and provides a complete annual precipitation normal suitable for statistical comparison, whereas NM3422 does not provide a complete annual precipitation record for this purpose. Rice Park SNOTEL is not used as the annual precipitation baseline; instead, it supports evaluation of SWE, snowpack, winter precipitation, snowmelt infiltration, frost penetration, AFI behavior, and RSJIHM calibration.

Following the approach outlined in Section 4, we used Welch's two-sample t-test to compare mean annual temperature because the site and historical samples had unequal variances and sample sizes. The San Mateo site sample (n = 8, SD = 1.34°F) had lower variance than the historical population (n = 42, SD = 2.37°F), so the standard pooled-variance t-test would not be appropriate. To evaluate differences in AFI values between the San Mateo site and the historical-only subset of AppD3-2 (n = 34), we also applied Welch's two-sample t-test. Before testing, we ensured statistical independence by removing San Mateo AFI values from the AppD3-2 combined population.

## 6.2 Test Inputs

Table 6-1 summarizes the input parameters for the three hypothesis tests, including sample sizes, means, standard deviations, and test types. Presenting these inputs together supports reproducibility and allows direct review of the statistical basis for the results in Table 6-2.

**Table 6-1 Statistical Test Input Parameters**

| Parameter | Sample | n | Mean | Standard Deviation | Test Type |
|---|---|---|---|---|---|
| Temperature (°F) | San Mateo (site) | 8 | 52.27 | 1.34 | Welch's two-sample t-test |
| Temperature (°F) | AppD3-1 (historical) | 42 | 51.52 | 2.37 | Welch's two-sample t-test |
| Precipitation (in) | San Mateo (site) | 8 | 10.02 | 2.74 | One-sample t-test |
| Precipitation (in) | Gallup Normal (population mean) | 30 | 11.65 | — | One-sample t-test |
| AFI (degree-days) | San Mateo (site) | 8 | 313.00 | 126.17 | Welch's two-sample t-test |
| AFI (degree-days) | AppD3-2 (historical only) | 34 | 225.15 | 169.27 | Welch's two-sample t-test |

## 6.3 Hypothesis Test Results

Table 6-2 presents the complete results for all three hypothesis tests. In each case, the null hypothesis states that the site mean equals the historical mean, or the known population parameter for precipitation. The results are used to determine whether observed differences are large enough to affect design-basis interpretation.

Because all three p-values exceed 0.05, none of the tests rejects the null hypothesis. The results therefore indicate statistical consistency between the recent San Mateo record and the applicable comparison benchmarks, while recognizing that the short eight-year site record limits the ability to detect smaller long-term shifts.

**Table 6-2 Hypothesis Test Results Summary**

| Parameter | Null Hypothesis ($H_0$) | Mean Difference | t-Statistic | Degrees of Freedom | p-Value (two-tailed) | Decision at $\alpha = 0.05$ |
|---|---|---|---|---|---|---|
| Mean Annual Temperature | Site mean = Historical mean | +0.75°F | 1.26 | 16.76 | 0.224 | Fail to reject $H_0$ |
| Annual Precipitation | Site mean = 11.65 in | −1.63 in | −1.68 | 7 | 0.136 | Fail to reject $H_0$ |
| Air Freezing Index | Site mean = Historical mean | +87.85 dd | 1.65 | 13.67 | 0.122 | Fail to reject $H_0$ |

## 6.4 Variance Analysis

Table 6-3 presents variance ratios between the site and historical datasets. Ratios below 1.0 indicate that the site record has lower observed variability than the corresponding historical comparison dataset. This result is expected in part because the San Mateo record is limited to eight complete years, whereas the historical datasets span multiple decades.

**Table 6-3 Variance Ratio Summary**

| Parameter | Site Variance | Historical Variance | F-Ratio | Interpretation |
|---|---|---|---|---|
| Temperature (°F²) | 1.81 | 5.62 | 0.32 | Site variance substantially lower; narrower range of annual means |
| AFI (dd²) | 15,918 | 28,652 | 0.56 | Site variance moderately lower; compressed range relative to historical |

## 6.5 Interpretation of Results

The site's mean annual precipitation (10.02 inches) is 1.63 inches below the Gallup 30-year normal (11.65 inches), but this deficit is not statistically significant ($t = -1.68$, $p = 0.136$). Because the p-value is greater than 0.05, the analysis does not provide sufficient evidence to conclude that the recent San Mateo precipitation record differs from the long-term regional annual precipitation benchmark. The result should be interpreted as a finding of statistical consistency, not as proof that future site precipitation will remain unchanged. Interannual variability is high (SD = 2.74 inches), driven by the contrast between the 2022 wet anomaly (15.33 inches) and the 2025 drought year (6.81 inches). The wide confidence interval associated with $n = 8$ limits the power to detect moderate departures from the long-term normal, so continued monitoring remains important.

Use of the Gallup normal is appropriate for this interpretation because the question being tested is whether recent site precipitation is statistically consistent with the regional long-term annual precipitation design basis. The Gallup dataset provides that regional annual benchmark; it is not used to replace San Mateo monitoring data or to evaluate snowpack-driven processes better represented by Rice Park SNOTEL.

From an engineering standpoint, the precipitation result supports continued use of the Gallup normal as the long-term regional annual precipitation baseline for comparison and model-input justification. The San Mateo record is site-specific and recent, while the Gallup value represents a

standardized climatological normal. The two datasets serve different purposes: San Mateo documents current site observations, and Gallup provides the regional long-term annual benchmark. This distinction is important because a short site record can be strongly influenced by a few wet or dry years, whereas the climatological normal provides a more stable design-support reference.

Figure 6-1 compares the recent San Mateo annual precipitation distribution with the Gallup 30-year annual precipitation normal used as the regional benchmark. Because Gallup is represented by a climatological normal rather than a full annual distribution in this analysis, the figure should be interpreted as a visual comparison of the San Mateo record against the long-term regional mean, not as a two-distribution test. Overall, Figure 6-1 supports the conclusion that the recent site mean is below, but not statistically different from, the Gallup regional normal.





**Figure 6-1 Annual Precipitation Probability Density Function**

The San Mateo mean annual temperature is 52.27°F, which is 0.75°F above the AppD3-1 historical mean of 51.52°F. This difference is not statistically significant ($t = 1.26$, $p = 0.224$) and is consistent with normal interannual variability. The result indicates that the recent site temperature record is not statistically distinguishable from the AppD3-1 historical comparison population at the 95% confidence level. The site record also shows lower variance than the historical dataset, which is expected given the short eight-year observation period and the fact that a short record is less likely to include the full range of warm and cool years captured by a multi-decade dataset.

Figure 6-2 compares the San Mateo and historical temperature distributions and supports the conclusion that the recent site record falls within the historical comparison range.

The temperature result should also be interpreted alongside the regional warming trend discussed in Section 3.4. Although the San Mateo mean is higher than the AppD3-1 historical mean, the difference is small relative to historical variability and does not meet the statistical threshold for a significant departure. Therefore, the available record does not justify changing the temperature design basis at this time. However, because the regional record indicates a long-term warming trend, continued comparison of site data to the historical baseline is recommended as the San Mateo record lengthens.





**Figure 6-2 Mean Annual Temperature Distribution Comparison**

Figure 6-3 compares the Air Freezing Index (AFI) distribution at the San Mateo site (2018–2025) with the historical-only AppD3-2 comparison dataset. San Mateo's AFI values cluster near a higher mean (313.0 degree-days) than the historical-only mean (225.15 degree-days), but they remain within the regional range, which includes both severe and mild freezing events. Welch's two-sample t-test indicates that the difference is not statistically significant at the 0.05 significance level ($t = 1.65$, $p = 0.122$). Therefore, the recent AFI record does not demonstrate a statistically significant shift away from the historical comparison population.

Figure 6-3 illustrates the non-normal, heavy-tailed nature of AFI distributions, which is typical of datasets influenced by rare severe freezing events. Recent San Mateo AFI values include both a relatively severe winter in 2022 (524 degree-days) and a mild winter in 2025 (83 degree-days), demonstrating substantial interannual variability within the short site record.





**Figure 6-3 Air Freezing Index (AFI) Distribution Comparison**

For the Mt. Taylor design basis, the AFI (approximately 927.5°F·days for a 200-year return period; rounded to 928°F·days in Table 7-2) has been conservatively established above recorded historical data. Figure 6-3 illustrates that San Mateo's AFI values display a narrower recent distribution than the historical dataset, while still showing substantial annual variation. This variability remains important for frost-penetration evaluation and cover-system design verification.

The practical implication is that the recent site record supports, rather than undermines, the existing design-basis AFI. The highest San Mateo AFI value in the recent record is 524 degree-days, which is below both the historical maximum of 786 degree-days and the 200-year design-basis AFI of approximately 927.5°F·days. This confirms that the design basis remains conservative relative to the available observed record. At the same time, the AFI dataset is controlled by rare severe freezing years, so a short recent record should not be used to reduce the design basis or narrow the expected range of future freezing conditions.

**Overall Interpretation:** Taken together, the statistical tests show no significant difference between the recent San Mateo record and the applicable historical or regional comparison datasets for precipitation, mean annual temperature, or AFI. The results support the conclusion that the 2018–2025 site observations remain compatible with the climate assumptions used for Mt. Taylor design support. The findings do not eliminate uncertainty, particularly because the site record includes only eight complete calendar years, but they do indicate that the available evidence does not require revision of the current precipitation, temperature, or frost-index design basis.

The principal limitation of the analysis is record length. With only eight complete years of site data, the tests have limited statistical power and are sensitive to individual years such as the wet 2022 year, dry 2025 year, severe 2022 freezing season, and mild 2025 freezing season. For this reason, the results should be used as a current validation check rather than a final long-term climatological determination. Continued on-site monitoring will improve confidence, reduce uncertainty around the site mean and variance estimates, and provide a stronger basis for future updates.

# 7.0 FREQUENCY ANALYSIS OF EXTREMES

## 7.1 Temperature Return Periods

Table 7-1 presents return-period estimates for mean annual temperature using the AppD3-1 best-fit linear regression. These values provide screening-level context for evaluating unusually warm annual mean temperature conditions relative to the historical comparison dataset. The recurrence interval indicates how often a temperature value may be equaled or exceeded; longer recurrence intervals correspond to rarer conditions.

**Table 7-1 Temperature Return Period Estimates (AppD3-1 Best-Fit: Y = 2.6549x + 48.992)**

| Recurrence Interval (years) | Standard Variate | Estimated Mean Annual Temperature (°F) |
|---|---|---|
| 42 | 3.73 | 58.9 |
| 50 | 3.90 | 59.4 |
| 75 | 4.31 | 60.4 |
| 100 | 4.60 | 61.2 |
| 125 | 4.82 | 61.8 |
| 150 | 5.01 | 62.3 |
| 175 | 5.16 | 62.7 |
| 200 | 5.30 | 63.1 |

These estimates should be interpreted with caution and used alongside ongoing monitoring and regional trend information because the site record is short and interannual variability remains substantial.

## 7.2 Air Freezing Index Return Periods

Table 7-2 presents return-period estimates for the Air Freezing Index derived from the AppD3-2 best-fit linear regression (Y = 153.82x + 112.93). The 200-year return-period AFI of approximately 927.5°F·days, rounded to 928°F·days in Table 7-2, serves as the design-basis frost penetration parameter for the Mt. Taylor cover system, consistent with the 200- to 1,000-year design-life context under 10 CFR Part 40, Appendix A.

**Table 7-2 AFI Return Period Estimates (AppD3-2 Best-Fit: Y = 153.82x + 112.93)**

| Recurrence Interval (years) | Standard Variate | Estimated AFI (°F·days) |
|---|---|---|
| 42 | 3.73 | 686 |
| 50 | 3.90 | 713 |
| 75 | 4.31 | 776 |
| 100 | 4.60 | 821 |
| 125 | 4.82 | 855 |
| 150 | 5.01 | 883 |
| 175 | 5.16 | 907 |
| 200 | 5.30 | 928 |

## 7.3 Observed Extreme Event Summary

Table 7-3 presents a summary of extreme events recorded at the San Mateo station and selected historical comparison values. The wettest San Mateo year was 2022, with 15.33 inches of precipitation, while the driest year was 2025, with 6.81 inches. These observed values provide context for interpreting return period estimates in Tables 7-1 and 7-2 and for evaluating cover-system water balance, stormwater controls, and frost-penetration design assumptions.

**Table 7-3 Extreme Event Summary**

| Parameter | Value | Year / Period |
|---|---|---|
| Wettest Year (San Mateo) | 15.33 in | 2022 |
| Driest Year (San Mateo) | 6.81 in | 2025 |
| Warmest Year (San Mateo) | 54.9°F | 2025 |
| Coolest Year (San Mateo) | 50.8°F | 2019 and 2022 |
| Highest AFI (San Mateo) | 524 degree-days | 2022 |
| Lowest AFI (San Mateo) | 83 degree-days | 2025 |
| Historical Maximum AFI (AppD3-2) | 786 degree-days | 1976 |
| Historical Maximum Temperature (AppD3-1) | 57.71°F | 2012 |
| 100-Year 24-Hour Precipitation | 2.56 in | NOAA Atlas 14 Vol. 1 Ver. 5 |

## 7.4 Freeze-Thaw Considerations

The design-basis AFI for the Mt. Taylor cover system is 927.5°F·days, corresponding to the 200-year return period estimate from the AppD3-2 best-fit frequency analysis (Table 7-2). This value exceeds the historically observed maximum of 786 °F·days (1976) by approximately 18%, reflecting the additional conservatism required for facilities designed to a 200- to 1,000-year performance life under 10 CFR Part 40, Appendix A. No year in the San Mateo record has

approached the design value; the most severe recent winter (2022, AFI = 524 °F·days) is 43% below the design basis. The 50-year return period AFI is estimated at 713 degree-days, and the 100-year value at 821 °F·days (Table 7-2). These return period estimates, rather than the historical maximum alone, inform frost penetration depth calculations for the engineered liner and cover system, ensuring that the design accommodates freezing events more severely than any observed in the instrumental record.

# 8.0 WATER BALANCE AND COVER SYSTEM IMPLICATIONS

## 8.1 Annual Moisture Deficit

The annual moisture deficit of 16.44 inches (PET of 26.45 inches minus precipitation of 10.01 inches), as documented in Table 3-3, confirms that evapotranspiration substantially exceeds precipitation on an annual basis. The aridity index of 0.38 places the site firmly in the semi-arid classification zone (UNESCO: AI < 0.50), supporting the viability of evapotranspiration-based cover system designs.

## 8.2 Implications for Cover System Performance

The monsoon-influenced precipitation pattern means that a substantial portion of annual moisture input occurs during the warmest months, when PET rates are highest. This seasonal coincidence supports cover system performance by increasing the potential for moisture removal during the wettest period. As shown in Figure 3-3, the cumulative annual deficit grows through the water year, confirming that annual evapotranspiration demand substantially exceeds precipitation. The monthly data presented in Table 3-1 show that small winter monthly surpluses occur, but these are outweighed by the large annual moisture deficit.

These findings support the continued adequacy of evapotranspiration-based cover designs for the Mt. Taylor Mine disposal cell. The persistent annual moisture deficit provides a substantial margin of safety against percolation through the engineered cover, even during anomalously wet years such as 2022 (15.33 inches, as shown in Table 5-1).

# 9.0 REGULATORY COMPLIANCE ASSESSMENT

## 9.1 Compliance with 40 CFR Parts 264/265

The regulatory relevance of this analysis is limited to supporting the technical basis for climate-related design inputs and long-term cover-system performance assumptions. The statistical testing in Section 6 confirms that recent site conditions do not depart significantly from the historical or regional comparison datasets used in existing facility designs. The precipitation depth-duration-frequency analysis presented in Table 3-2 provides stormwater design context, while the AFI frequency analysis supports frost-penetration and cover-system design review.

## 9.2 Compliance with CDPHE Regulation 61

The demonstrated aridity index of 0.38 and the documented annual moisture deficit of 16.44 inches (see Table 3-3) provide technical support for evapotranspiration-based cover-system performance claims. Continued on-site monitoring will extend the data record and further strengthen future regulatory and engineering reviews with additional site-specific evidence.

### 9.3 NRC and UMTRCA Considerations

For uranium mill tailings disposal, climatological data provide technical support for long-term stability and cover-system performance evaluations. The 100-year, 24-hour precipitation depth of 2.56 inches (Table 3-2) and the design-basis AFI of approximately 927.5°F·days (Table 7-2, 200-year return period) represent the primary climate-related design inputs for stormwater, frost-penetration, erosion protection, and radon-barrier performance assessments. The design AFI exceeds the historical observed maximum of 786°F·days (1976) by approximately 18%, providing an appropriate margin of conservatism for long-term design-life evaluations.

Together, the conservative precipitation and AFI design inputs support long-term cover-system stability, erosion protection, frost-penetration assessment, and radon-barrier performance. Continued monitoring and periodic technical review will further strengthen the basis for demonstrating long-term regulatory compliance.

## 10.0 CONCLUSIONS AND RECOMMENDATIONS

### 10.1 Key Findings

This memorandum evaluates whether the recent San Mateo site record is statistically consistent with the historical and regional climate information used to support Mt. Taylor Mine disposal cell design. The analysis confirms that the available site record does not indicate a statistically significant departure from the established regional design basis, while also clarifying the appropriate role of each supporting dataset. The principal findings are as follows:

- All three hypothesis tests (temperature, precipitation, and Air Freezing Index) yield p-values above 0.05, confirming that the 2018–2025 site record is statistically consistent with the historical baseline at the 95% confidence level (see Table 6-2).
- Mean annual temperature at the San Mateo site (52.27°F) shows a modest, non-significant increase of +0.75°F relative to the AppD3-1 historical population mean of 51.52°F ($p = 0.224$).
- Mean annual precipitation at the site (10.02 inches) is 1.63 inches below the Gallup 30-year normal of 11.65 inches, but this deficit is not statistically significant ($p = 0.136$). Interannual variability is high (SD = 2.74 inches), as documented in Table 5-4.
- The Air Freezing Index shows recent winters ranging from very mild (83°F·days in 2025) to moderately severe (524°F·days in 2022), all well within the design envelope. The site's mean AFI of 313°F·days is not significantly different from the historical-only mean of 225°F·days ($p = 0.122$), as presented in Table 6-2. The design-basis AFI of 927.5°F·days (200-year return period, Table 7-2) exceeds the historical observed maximum of 786°F·days (1976) by 18%, confirming that additional conservatism is built into the design parameter.
- The annual moisture deficit of 16.44 inches and aridity index of 0.38 confirm the semi-arid classification and support evapotranspiration-based cover system designs

- Gallup and Rice Park serve different technical purposes. Gallup provides the appropriate long-term regional precipitation baseline for annual precipitation comparisons, while Rice Park SNOTEL provides high-elevation SWE, snowpack, winter precipitation, snowmelt infiltration, frost penetration, AFI, and RSJIHM calibration support. The datasets are therefore complementary, not interchangeable.

## 10.2 Engineering Implications

The statistical results support continued use of the current Mt. Taylor disposal cell climate design basis. The recent San Mateo observations do not indicate a statistically significant departure from the historical or regional comparison datasets, and the applicable design inputs remain conservative for cover-system performance, frost penetration, stormwater control, and infiltration modeling.

For frost penetration and cover design, the design-basis AFI of approximately 927.5°F·days should continue to be used for liner and cover calculations. This value corresponds to the 200-year return period from AppD3-2, exceeds the historical maximum of 786°F·days by approximately 18%, and remains well above the highest San Mateo value observed during 2018–2025, which was 524°F·days in 2022. The design basis therefore retains an appropriate margin of conservatism for long-term performance evaluations.

The engineering use of each climate dataset should remain distinct in future design reviews and regulatory submittals. The Gallup NCDC 30-year precipitation normal of 11.65 inches remains the appropriate long-term regional annual precipitation benchmark for statistical comparison and model-input justification because it is a published climatological normal and fills the annual precipitation baseline role that NM3422 cannot support with a complete annual series. The San Mateo station record should continue to document recent site conditions and test whether site observations remain consistent with the regional design basis; however, the current eight-year record should not be used by itself to replace longer-term regional benchmarks.

Rice Park SNOTEL should continue to support SWE, snowpack, winter precipitation, snowmelt infiltration, frost penetration, AFI calibration, and RSJIHM calibration because those snowpack-driven processes are not represented by the Gallup precipitation normal. Cover-system performance modeling may continue to rely on the demonstrated semi-arid setting, including the aridity index of 0.38 and annual moisture deficit of 16.44 inches, which show that evapotranspiration demand substantially exceeds precipitation over the water year. Stormwater and erosion-control design should continue to use the DDF values in Table 3-2, including the 100-year, 24-hour precipitation depth of 2.56 inches, for drainage channels, spillways, run-on/runoff controls, and erosion protection features.

Overall, the existing climate-related design parameters for the Mt. Taylor Mine disposal cell remain technically defensible. No statistical result from the 2018–2025 San Mateo record requires revision of the annual precipitation, mean annual temperature, AFI, water-balance, or stormwater design inputs at this time. Taken together, the San Mateo site record, Gallup regional precipitation normal, Rice Park winter hydrology data, and AppD3 historical temperature and AFI datasets provide a consistent technical basis for cover-system design, infiltration modeling, frost-penetration evaluation, stormwater controls, and long-term regulatory demonstrations.

## 10.3 Recommendations

The following recommendations are intended to preserve the technical distinction among the San Mateo site record, the Gallup regional precipitation normal, and Rice Park SNOTEL winter hydrology data while improving the statistical basis for future reviews.

1. Continue on-site meteorological monitoring at the San Mateo station to extend the site-specific record toward a target of $n \geq 15$ years, which will substantially improve statistical power for future comparisons.
2. Update this climatological comparison on a recurring basis, recommended every 5 years or when the site record doubles in length, whichever occurs first.
3. In future revisions, explicitly state that Gallup is the long-term annual precipitation baseline and Rice Park is the SWE/winter hydrology calibration dataset to avoid confusion during regulatory review.
4. Evaluate the potential effects of regional climate trends (the observed warming rate of +0.033°F/year at NCEI NM3422, as discussed in Section 3.4) on design-life performance when the site record exceeds 15 years.
5. Maintain the design-basis AFI of 927.5°F·days (200-year return period from AppD3-2) for frost penetration depth calculations until superseded by an updated frequency analysis incorporating additional years of record. Periodically evaluate whether the 1,000-year return period estimate should be adopted as the design basis as the dataset grows and statistical confidence improves.
6. Consider augmenting the precipitation baseline with site-specific frequency analysis once the on-site record exceeds 20 years of continuous data.

In conclusion, the 2018–2025 San Mateo record is statistically consistent with the regional design basis at the 95% confidence level, and the existing cover-system climate inputs remain defensible. Gallup should continue to define the long-term regional annual precipitation baseline because it provides the published 30-year normal needed for regional comparison and model input justification. Rice Park should continue to support SWE and winter hydrologic calibration, while San Mateo should continue to provide site-specific monitoring context as the record lengthens.

## 11.0 REFERENCES

Engineering Analytics, Inc. 2025a. "Appendix D3-1: Mean Annual Temperature Distribution." In *Mt. Taylor Disposal Cell Design Report*. Project No. 111360. Rio Grande Resources.

Engineering Analytics, Inc. 2025b. "Appendix D3-2: Frost Index Distribution." In *Mt. Taylor Disposal Cell Design Report*. Project No. 111360. Rio Grande Resources.

Engineering Analytics, Inc. 2025c. "Appendix D3-3." In *Mt. Taylor Disposal Cell Design Report*, Project No. 111360. Rio Grande Resources.

National Centers for Environmental Information. n.d. "Station NM3422, Grants, New Mexico: Mean Annual Temperature Data, 1975–2025." Accessed July 10, 2026.

National Climatic Data Center. n.d. "Station 293422, Gallup Municipal Airport, New Mexico: 1981–2010 Monthly Climate Normals." Accessed July 10, 2026.

San Mateo Weather Station. 2026. *Annual Climatological Summaries, 2018–2025*. Mt. Taylor Mine Project.

U.S. Environmental Protection Agency. n.d. "40 CFR Parts 264 and 265: Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities."

Colorado Department of Public Health and Environment. n.d. "Regulation 61: Solid Waste Disposal Sites and Facilities."

U.S. Nuclear Regulatory Commission. n.d. "10 CFR Part 40, Appendix A: Criteria Relating to the Operation of Uranium Mills and the Disposition of Tailings or Wastes Produced by the Extraction or Concentration of Source Material from Ores Processed Primarily for Their Source Material Content."

Thornthwaite, C. W. 1948. "An Approach Toward a Rational Classification of Climate." *Geographical Review* 38 (1): 55–94.

# APPENDIX H
# SLOPE STABILITY

Engineering Analytics, Inc.
Now Part of MacKay

Fort Collins Office
1600 Specht Point Road, Suite 209, Fort Collins, CO 80525
970.488.3111 / GoMacKay.com

# *Technical Memorandum*

| | | | |
|---|---|---|---|
| To: | Rio Grande Resources, Ltd. | From: | Jason Andrews, P.E. |
| Company: | Rio Grande Resources, Ltd. | Date: | August 5, 2026 |
| EA No.: | 111360 | | |
| Re: | Mt. Taylor Uranium Mine – Slope Stability Analysis | | |

**APPENDIX H — SLOPE STABILITY ANALYSIS**

## 1.0 INTRODUCTION

Rio Grande Resources, Ltd. (RGR) retained Engineering Analytics, Inc. (EA) to evaluate the long-term slope stability of the proposed expanded disposal cell at the Mt. Taylor Mine, located in Cibola County, New Mexico. The disposal cell will receive consolidated mine waste material and will be capped with a three-layer engineered cover system designed to meet the performance requirements of 10 CFR Part 40, Appendix A, and 40 CFR Part 192. Long-term physical stability of the cover and waste mass — including resistance to geomorphic, seismic, and gravity-induced failure — is a core design requirement under 10 CFR Part 40, Appendix A, Criterion 4.
Slope stability analyses were performed using the limit-equilibrium method implemented in GEO-SLOPE International's SLOPE/W software (Version 11, GEO-SLOPE International Ltd., 2021). Two cross-sections — the left flank and the right flank of the disposal cell — were analyzed under static and pseudostatic (seismic) loading conditions. No deformation analysis and no formal liquefaction assessment were performed, as the compacted waste and cover materials are not susceptible to liquefaction under the site's seismic regime.

This appendix is organized as follows:

- Section H.2 provides background on the disposal cell and site setting.
- Section H.3 provides reference materials relevant to the stability evaluation.
- Section H.4 describes the geotechnical characterization of the site materials.
- Section H.5 discusses regional seismicity and the basis for the pseudostatic seismic coefficient.
- Section H.6 presents the slope stability analyses, including loading conditions, stability criteria, material properties, and results.
- Section H.7 presents conclusions.

Graphical output from the SLOPE/W analyses is included at the end of this appendix as Figures H-1 through H-4.

## 2.0 SITE BACKGROUND AND DISPOSA CELL DESCRIPTION

The Mt. Taylor Mine is an inactive uranium mine located approximately 17 miles northeast of Grants, New Mexico, in Cibola County (T.13N., R.8W., Sections 1, 2, 11, and 12, New Mexico Principal Meridian). The site lies on the southern flank of Mt. Taylor, a Quaternary stratovolcano and the highest peak of the Datil Section of the Colorado Plateau, at a site elevation of approximately 7,400 feet above mean sea level (AMSL). The mine was operated by Rio Grande Resources, Ltd. under NRC Source Materials License SUA-1473 and is subject to reclamation and closure requirements administered jointly by the NRC and the New Mexico Environment Department (NMED).

The expanded disposal cell consolidates mine waste — including low-grade ore, mineralized waste rock, and uranium-contaminated soil — from multiple source areas at the site. The cell occupies a natural topographic depression and is bounded on all flanks by engineered slopes at a 5H:1V (20%) gradient. The cell is designed to a maximum height of approximately 200 feet above the original ground surface. The engineered cover system, described in detail in Part 2 of this report, consists of (from top to bottom): 12 inches of rock mulch, 28 inches of in-situ soil cover, and 12 inches of compacted clay radon barrier, for a total cover thickness of 52 inches.

## 3.0 GEOTECHNICAL CHARACTERIZATION

### 3.1 Geology

#### Regional Geology

The Mt. Taylor Mine site is situated on the Colorado Plateau physiographic province, within the Acoma Basin — a broad structural embayment formed during Late Cretaceous to Paleogene time. The region is underlain by a thick Mesozoic sedimentary sequence deposited in fluvial, deltaic, and shallow marine environments. The Westwater Canyon Member of the Morrison Formation (Upper Jurassic), the primary uranium ore host in the Grants Uranium District, is the principal economic formation at depth.

Overlying the Morrison Formation are Cretaceous units of the Crevasse Canyon and Gallup Sandstone members, and younger Tertiary and Quaternary volcanic deposits derived from the Mt. Taylor volcanic field. The Mt. Taylor stratocone consists of Pliocene-to-Quaternary basaltic and andesitic lavas, pyroclastic deposits, and associated volcaniclastic aprons. The site is situated on a pediment surface underlain by a thin veneer of alluvial fan and eolian deposits over the Tertiary volcanic substrate.

Regional fault structures include the Zuni Uplift fault system to the south and the Rio Grande Rift bounding faults to the east. Active faults within the immediate site vicinity have not been mapped by the USGS Quaternary Fault and Fold Database; however, the broader Rio Grande Rift is a recognized zone of ongoing extensional seismicity.

**Local Geology**

At the disposal cell site, subsurface investigations confirm that the foundation materials consist primarily of medium-dense to dense silty sand and sandy silt with gravel (SM/ML) derived from the volcanic pediment apron, underlain by competent basaltic and andesitic volcanic rock. The upper 10 to 20 feet of the profile consists of reworked pediment soil and minor eolian deposits. No significant clay lenses or groundwater-saturated zones were encountered within the depth of interest for the stability cross-sections.

The waste material placed within the disposal cell consists of consolidated mine waste: low-grade uranium ore, mineralized waste rock, and uranium-contaminated soil sourced from the Windblown Area, Ore Pad Area, Mine Compound, and adjacent source zones. The material is heterogeneous but broadly characterized as granular to silty sand with variable uranium mineral content, compacted during cell construction to a uniform state.

## 3.2 Climate

The Mt. Taylor Mine site experiences a semi-arid continental climate at approximately 7,400 feet elevation. Mean annual precipitation (MAP) is 10.01 inches per year, as established from the 2018–2025 San Mateo NOAA station record (Appendix H of the main report). Precipitation is bimodal: winter snowfall (October through March; seasonal mean Pw = 2.87 inches) and summer convective monsoon events (April through September; seasonal mean Ps = 7.14 inches). Mean annual potential evapotranspiration (PET) is 26.45 inches per year, yielding an aridity index (PET/P) of 2.64 — confirming strongly water-limited, semi-arid conditions.

The site is subject to freeze-thaw cycling, with a design frost depth of 28 inches established using the Modified Berggren method (Section 4.3 of the main report). Snow loading on the completed cover is not a stability concern given the shallow snowpack depths characteristic of this elevation and regional climate.

## 3.3 Subsurface Conditions and Groundwater

Available boring logs and geotechnical data indicate that the native foundation soils are medium-dense to dense and competent. The water table is located at depths well below the base of the disposal cell in this semi-arid upland environment. No artesian pressures, perched water tables, or saturated foundation zones were identified during site investigations. Accordingly, pore water pressures were set to zero in the stability analyses — a conservative representation consistent with the site's hydrologic regime and the extremely low infiltration through the engineered cover system (design percolation of 0.45 in/yr; Section 4.6 of the main report).

## 3.4 Laboratory and Field Testing Results

Laboratory testing and field characterization of the cover and waste materials were performed as part of the expanded disposal cell design program. Testing included classification testing (grain size analysis, Atterberg limits), standard Proctor compaction testing, and direct shear testing for

determination of effective shear strength parameters. The results inform the material properties assigned to each zone in the stability model, as summarized in Table H-2 (Section H.6.3).

The compacted clay radon barrier (12-inch CL layer) was tested to confirm achievement of a saturated hydraulic conductivity of ksat ≤ 1×10−7 cm/s (= 1×10−9 m/s), consistent with 40 CFR 192 requirements. The in-situ soil cover material (CL-ML) exhibits an available water-holding capacity (AWHC) of 0.10 in/in, as documented in Section 4.6 of the main report.

### 3.5 Representative Geologic Cross-Section

Two representative cross-sections through the disposal cell were developed for stability analysis: the left flank and the right flank. Each cross-section spans a horizontal distance of approximately 1,300 feet. Elevations range from approximately 7,280 feet AMSL at the toe to approximately 7,480 feet AMSL at the crest, corresponding to a vertical relief of approximately 200 feet. The 20% (5H:1V) cover slopes are modeled explicitly in the SLOPE/W geometry. The three cover layers (rock mulch, in-situ soil cover, compacted clay radon barrier), the compacted waste mass, and the native foundation are represented as discrete material zones. Figures H-1 through H-4 show the SLOPE/W output for each loading condition on each cross-section.

## 4.0 SEISMICITY

The Mt. Taylor Mine site is located within the tectonically active Colorado Plateau–Rio Grande Rift transition zone. The Rio Grande Rift is an active extensional province extending from southern New Mexico northward through central Colorado, capable of generating moderate-magnitude earthquakes on bounding and interior normal faults. The Jemez Mountains Volcanic Field, located approximately 75 miles northeast of the site, is a Quaternary volcanic center with associated structural complexity. The Socorro Seismic Anomaly, centered approximately 80 miles south of the site, is an area of elevated seismicity attributed to a mid-crustal magma body.

Historical seismicity records for Cibola County and the surrounding region document numerous events of Richter magnitude M 3.0 to 5.0, with larger events possible on regional fault structures. The USGS 2023 National Seismic Hazard Model (NSHM) was used to assess the probabilistic seismic hazard at the site. For site conditions representative of firm soil to soft rock (Site Class C/D), the 2,475-year return period peak ground acceleration (PGA) at the site is approximately 0.20g. This return period (2% probability of exceedance in 50 years) is consistent with the hazard level used for critical facility design.

For the pseudostatic slope stability analysis, the horizontal seismic coefficient (kh) was determined as follows: kh = 0.5 × PGA/g = 0.5 × 0.20 = 0.10.

A horizontal seismic coefficient of kh = 0.14 was adopted for the pseudostatic analyses. This value is conservative, exceeding the kh = 0.10 value (= 0.5 × PGA/g = 0.5 × 0.20) that would result from standard NUREG-1623 practice, and provides additional margin against seismic loading. The vertical seismic coefficient was conservatively set to zero.

No active faults were mapped within the immediate site footprint by the USGS Quaternary Fault and Fold Database. The nearest mapped active fault is located at sufficient distance that fault rupture through the disposal cell is not a credible scenario.

## 5.0 SLOPE STABILITY ANALYSES

### 5.1 Loading Conditions Modeled

Two loading conditions were analyzed for each cross-section:

**Condition 1 — Static Analysis (Long-Term Drained):** Gravity loading only, using effective (drained) shear strength parameters for all material zones and zero pore water pressure. This condition represents the permanent, long-term post-closure state of the disposal cell under ambient gravitational loading.

**Condition 2 — Pseudostatic Analysis (Seismic):** Static gravity loading plus a horizontal pseudostatic force equivalent to kh = 0.14 times the total weight of each soil slice. Effective shear strength parameters and zero pore water pressure are retained from Condition 1. This condition represents the response of the slope to the design seismic event.

A post-liquefaction analysis was not performed, as the compacted granular and cohesive materials comprising the disposal cell cover and waste mass are not susceptible to static or cyclic liquefaction. The cover materials and waste are not saturated under normal operating conditions, and the fine-grained clay barrier and in-situ soil cover materials are plasticity-controlled and not liquefiable per standard criteria (Boulanger and Idriss, 2004).

### 5.2 Stability Criteria

The minimum acceptable factors of safety (FS) for the Mt. Taylor disposal cell slope stability analyses are based on NRC guidance in NUREG-1620 and NUREG-1623, and on the requirements of 10 CFR Part 40, Appendix A, Criterion 4, which mandates long-term physical stability of the disposal cell. Table H-1 presents the adopted stability criteria.

**Table H-1 . Summary of Slope Stability Criteria for the Mt. Taylor Disposal Cell**

| Loading Condition | Minimum Acceptable FS | Regulatory Basis |
|---|---|---|
| Static (long-term drained) | 1.50 | NUREG-1620; 10 CFR 40, App. A, Criterion 4 |
| Pseudostatic (seismic, kh = 0.14) | 1.10 | NUREG-1623; 10 CFR 40, App. A, Criterion 4 |

The static minimum FS of 1.50 ensures adequate stability against gravity-induced failure over the 200- to 1,000-year design life. The pseudostatic minimum FS of 1.10 provides a margin above unity under the design seismic event, consistent with the understanding that limited permanent

displacement is tolerable during rare seismic loading provided the slope does not experience a flow-type failure.

## 5.3 Material Properties

The effective shear strength parameters and unit weights assigned to each material zone are based on laboratory direct shear testing, standard Proctor compaction data, and engineering judgment consistent with the materials' classification and placement specifications. All materials are treated as cohesionless ($c' = 0$ psf) in effective stress, which is conservative for the compacted clay barrier and in-situ soil cover materials, which exhibit some drained cohesion. Table H-2 presents the material properties used in all analyses.

The cohesionless assumption for all materials is conservative because: (1) the clay barrier and in-situ soil cover both exhibit measurable drained cohesion at field moisture contents; (2) pore water pressures are zero throughout the model; and (3) using $c' = 0$ for all layers ensures that the stability margin is derived entirely from frictional resistance. This approach is consistent with guidance in NUREG-1620 for long-term stability assessments of uranium disposal cells.

**Table H-2 Material Properties Used for Slope Stability Analyses**

| Material / Zone | Unit Weight, $\gamma$ (pcf) | Cohesion, $c'$ (psf) | Friction Angle, $\varphi'$ (degrees) |
|---|---|---|---|
| Rock mulch cover | 115 | 0 | 35 |
| In-situ soil cover | 110 | 0 | 25 |
| Compacted clay radon barrier | 120 | 0 | 24 |
| Compacted disposal-cell fill / waste | 102 | 0 | 25 |
| Foundation soil / overburden | 122 | 0 | 25 |

The critical failure surface in each analysis was located using a Monte Carlo search routine in SLOPE/W, evaluating several thousand candidate slip surfaces per analysis. The Morgenstern-Price method of slices was employed, satisfying both moment and force equilibrium. Rotational circular slip surfaces were considered for the deep-seated failure mode, and non-circular (composite) surfaces were also evaluated to capture potential sliding along stratigraphic contacts between material zones.

## 5.4 Results

The results of the four SLOPE/W analyses are summarized in Table 6-3. Graphical output for each analysis, showing the critical slip surface and associated minimum FS, is presented in Figures H-1 through H-4 at the end of this appendix.

**Table H-3. Summary of Slope Stability Results — Mt. Taylor Disposal Cell**

| Analysis | Cross-Section | Loading Condition | Minimum FS (SLOPE/W) | Minimum Required FS | Compliance |
|---|---|---|---|---|---|
| Left flank — static | Left flank | Static (gravity) | 2.25 | 1.50 | Compliant |
| Left flank — pseudostatic | Left flank | Pseudostatic (kh = 0.14) | 1.28 | 1.10 | Compliant |
| Right flank — static | Right flank | Static (gravity) | 2.20 | 1.50 | Compliant |
| Right flank — pseudostatic | Right flank | Pseudostatic (kh = 0.14) | 1.27 | 1.10 | Compliant |

### 5.4.1 *Static Analysis*

Static analysis of the left flank cross-section yields a minimum factor of safety of FS = 2.25, substantially exceeding the 1.50 criterion. The critical slip surface is a shallow rotational failure engaging primarily the rock mulch and in-situ soil cover layers on the 20% outslope. The high friction angle of the rock mulch layer ($\varphi' = 35°$) relative to the slope angle (approximately 11.3°) produces a large stability margin for this geometry.

Static analysis of the right flank cross-section yields a minimum factor of safety of FS = 2.20, substantially exceeding the 1.50 criterion. The critical slip surface for the right flank engages a deeper rotational geometry that incorporates the compacted clay radon barrier ($\varphi' = 24°$) and the underlying waste mass interface. The computed FS = 2.20 demonstrates a large stability margin under static loading for this geometry, and the right flank is fully compliant with the static stability criterion.

### 5.4.2 *Pseudostatic Analysis*

Pseudostatic analysis of the left flank cross-section, applying kh = 0.14, yields a minimum factor of safety of FS = 1.28, exceeding the 1.10 criterion. The reduction from the static FS of 2.25 to the pseudostatic FS of 1.28 reflects the destabilizing effect of the horizontal seismic inertia force acting on the sliding mass, consistent with expectations for a shallow, friction-dominated slope at this seismic coefficient.

Pseudostatic analysis of the right flank cross-section, applying kh = 0.14, yields a minimum factor of safety of FS = 1.27, also exceeding the 1.10 criterion. The contrast between the right flank static FS of 2.20 and the pseudostatic FS of 1.27 reflects the significant destabilizing influence of the conservative seismic coefficient on the deeper, composite slip mass geometry governing this cross-

section. Despite this reduction, the pseudostatic FS of 1.27 comfortably exceeds the 1.10 minimum criterion, confirming that the right flank is seismically stable under the design earthquake.

The behavior of the right flank critical slip surface under pseudostatic loading is consistent with deep composite slip surfaces in which the additional seismic driving moment, applied at the conservative kh = 0.14, produces a meaningful but bounded reduction from the static factor of safety. Both the static and pseudostatic analyses for the right flank demonstrate compliance with their respective criteria.

## 6.0 CONCLUSIONS

Slope stability analyses were performed for the Mt. Taylor Mine expanded disposal cell using the limit-equilibrium method in SLOPE/W (Morgenstern-Price method of slices). Two cross-sections — left flank and right flank — were evaluated under static (long-term drained) and pseudostatic (seismic) loading conditions. The following conclusions are drawn:

1. Left flank — static: The left flank of the disposal cell is stable under static loading, with a computed FS of 2.25, substantially exceeding the minimum criterion of 1.50. The critical failure mode is a shallow rotational surface governed by the high-friction rock mulch layer.
2. Left flank — pseudostatic: The left flank is seismically stable under the design horizontal seismic coefficient of kh = 0.14, with a computed FS of 1.28, exceeding the minimum criterion of 1.10. The adopted seismic coefficient is conservative, exceeding the value that would result from standard NUREG-1623 practice, and is based on the 2,475-year return period PGA of approximately 0.20g per the USGS 2023 NSHM.
3. Right flank — static: The right flank of the disposal cell is stable under static loading, with a computed FS of 2.20, substantially exceeding the minimum criterion of 1.50. The critical failure mode engages a deeper rotational geometry through the compacted clay radon barrier and waste mass interface.
4. Right flank — pseudostatic: The right flank is seismically stable under the design earthquake, with a computed FS of 1.27, exceeding the minimum pseudostatic criterion of 1.10. The conservative seismic coefficient of kh = 0.14 produces a meaningful reduction from the static FS of 2.20, yet the resulting pseudostatic FS remains well above the 1.10 minimum requirement.
5. Liquefaction: No formal liquefaction assessment was performed. The compacted cover and waste materials are not susceptible to liquefaction under the site's semi-arid hydrologic conditions and the design seismic regime.
6. Overall finding: All four slope stability analyses — left flank static (FS = 2.25 ≥ 1.50), left flank pseudostatic (FS = 1.28 ≥ 1.10), right flank static (FS = 2.20 ≥ 1.50), and right flank pseudostatic (FS = 1.27 ≥ 1.10) — meet or exceed their respective minimum required factors of safety. The Mt. Taylor Mine expanded disposal cell cover slopes are stable under both static and pseudostatic loading conditions and satisfy the long-term physical stability requirements of 10 CFR Part 40, Appendix A, Criterion 4.

## REFERENCES

Boulanger, R.W., and Idriss, I.M. (2004). Evaluating the Potential for Liquefaction or Cyclic Failure of Silts and Clays. Center for Geotechnical Modeling Report No. UCD/CGM-04/01, University of California, Davis.

Cedar Creek Associates, Inc. (2023). Mt. Taylor Mine Site Ecological Assessment. Prepared for Rio Grande Resources, Ltd.

Engineering Analytics, Inc. (EA) (2022). Grants Reclamation Project Large Tailings Pile Evapotranspiration Cover Project Design Report. Homestake Mining Company of California, EA Project No. 110829:103. Fort Collins, CO.

Engineering Analytics, Inc. (EA) (2024). Shootaring Canyon Uranium Facility Closure Design — Hydrology, Surface Cover Layer, and Diversion Channel Design, Technical Memorandum. Anfield Resources Holding Corp., EA No. 110444. Fort Collins, CO.

GEO-SLOPE International Ltd. (2021). SLOPE/W User's Guide, Version 11. Calgary, Alberta, Canada.

International Code Council, Inc. (2018). International Building Code. Country Club Hills, IL.

U.S. Nuclear Regulatory Commission (NRC) (2003). Standard Review Plan for the Review of a Reclamation Plan for Mill Tailings Sites Under Title II of the Uranium Mill Tailings Radiation Control Act. NUREG-1620. U.S. NRC, Washington, D.C.

U.S. Nuclear Regulatory Commission (NRC) (2003). Design of Erosion Protection for Long-Term Stabilization. NUREG-1623. U.S. NRC, Washington, D.C.

U.S. Geological Survey (USGS) (2023). 2023 National Seismic Hazard Model. USGS Open-File Report 2023-1098. Reston, VA.

U.S. Geological Survey (USGS). Quaternary Fault and Fold Database of the United States. Available at: http://earthquake.usgs.gov/hazards/qfaults/





**Figure H-1 — SLOPE/W Output Left Flank | Static Analysis | FS = 2.25**





**Figure H-2. SLOPE/W Output — Left Flank, Pseudostatic Analysis (kh = 0.14; FS = 1.28)**





**Figure H-3. SLOPE/W Output — Right Flank, Static Analysis (FS = 2.20)**





**Figure H-4. SLOPE/W Output — Right Flank, Pseudostatic Analysis (kh = 0.14; FS = 1.27)**

# APPENDIX I
# SURFACE WATER HYDROLOGY AND EROSION PROTECTION CALCULATIONS

# *Technical Memorandum*

| | | | |
|---|---|---|---|
| **To:** | Rio Grande Resources, Ltd. | **From:** | Jason Andrews, P.E.<br>Olu Iwakun |
| **Company:** | Rio Grande Resources, Ltd. | **Date:** | August 5, 2026 |
| **EA No.:** | 111360 | | |
| **Re:** | Surface Water Hydrology and Erosion Protection Calculations | | |
| **Cc:** | | | |

## I-1 INTRODUCTION

This appendix presents detailed calculations supporting the surface water hydrology and erosion protection design for the Mt. Taylor Mine expanded disposal cell, Cibola County, New Mexico. Calculations are organized as follows:

- I-1. Probable Maximum Precipitation (PMP) Determination
- I-2. Rock Mulch Cover Erosion Design — Unit-Width Analysis
- I-3. Leps (1973) Filter / Interstitial Velocity Check
- I-4. Gully Formation Analysis
- I-5. Diversion Channel Design
- 1-6. Wind Erosion Summary

Design parameters adopted for all calculations are listed in Table I-1.

**Table I-1 Design Parameters for Surface Water and Erosion Calculations**

| Parameter | Value | Source |
|---|---|---|
| Site elevation | ~7,400 ft above MSL | Topographic survey |
| Cover outslope | 20% (5H:1V) | Design drawings |
| Rock mulch admixture | 30% AASHTO No. 1 gravel/70% in-situ soil cover (by volume) | Cover design specification |
| D50 of gravel component | 2.2 in (nominal AASHTO No. 1) | AASHTO M43 gradation |
| D75 of gravel component | ~3.5 in | AASHTO M43 gradation |
| Manning's n (rock admixture) | 0.035 | NUREG/CR-4620, Table 3.1 |
| Runoff coefficient C | 0.80 | NUREG/CR-4620, EA judgment |
| Flow concentration factor (CF) | 3.0 | NUREG-1623, Table 5.3 |
| 100-yr/24-hr precipitation | 2.56 in | Appendix G DDF analysis |
| Unit weight of water | 62.4 lb/ft$^3$ | Standard |
| Specific gravity of rock | 2.65 | Standard |

## I-2 PROBABLE MAXIMUM PRECIPITATION (PMP) DETERMINATION

### I-2.1 Base PMP – HMR-55A Method

The Probable Maximum Precipitation (PMP) for the Mt. Taylor site was determined following the procedure in NWS Hydrometeorological Report No. 55A (HMR-55A), which applies to the region west of the 103rd meridian. The site is located at approximately 35.2°N, 107.7°W, at an elevation of approximately 7,400 ft above mean sea level.

The base 1-hour, 1-square-mile PMP at a reference elevation of 5,000 ft was read from HMR-55A Figure 14.1:

*Base 1-hr PMP (1 mi², 5,000-ft reference) = 9.94 inches*

The maximum persisting 12-hour 1,000-mb dew point for July (the critical month for convective storms) was read from HMR-55A Figure 14.2:

*$W_0$ (July, 1,000-mb, 12-hr persisting) = 72°F (Mt. Taylor site)*

### I-2.2 Elevation Adjustment

At 7,400 ft, the site elevation is above the 5,000-ft reference. The elevation adjustment factor was read from HMR-55A Figure 14.3 based on the site elevation and moisture profile:

*Elevation adjustment factor = 0.87 (at 7,400 ft, $W_0$ = 72°F)*

The elevation-adjusted 1-hour PMP is:

*PMP1hr = 9.94 × 0.87 = 8.65 inches*

### I-2.3 6-Hour PMP and Duration Conversion

The 6-hour PMP was determined from HMR-55A for the site:

*PMP6hr (unadjusted) = 12.91 inches*

*PMP6hr (elevation-adjusted) = 12.91 × 0.87 = 11.23 inches*

The 6-hour to 1-hour ratio for the region east of the Continental Divide to the 103rd meridian is 1.35 per HMR-55A:

*PMP1hr (from 6-hr) = 11.23 / 1.35 = 8.32 inches*

The governing design 1-hour PMP is taken as the maximum of the two methods:

*Design PMP (1-hr) = max(8.65, 8.32) = 8.65 inches ← GOVERNS*

### I-2.4 Sub-Hourly PMP Intensities

Sub-hourly PMP depth fractions were applied per NUREG/CR-4620 Table 2.1. Table I-2 summarizes the resulting depths and peak intensities.

**Table I-2 (NUREG / CR-4620 Table 2.1, PMP $_{1hr}$ = 8.65 in)**

| Duration (min) | % of 1-hr PMP | PMP Depth (in) | Peak Intensity (in/hr) |
|---|---|---|---|
| 2.5 | 33 | 2.855 | 68.51 |
| 5 | 45 | 3.893 | 46.71 |
| 10 | 60 | 5.190 | 31.14 |
| 15 | 70 | 6.055 | 24.22 |
| 20 | 78 | 6.747 | 20.24 |
| 30 | 88 | 7.612 | 15.22 |
| 60 | 100 | 8.650 | 8.65 |

## I-3 ROCK MULCH COVER EROSION DESIGN – UNIT- WIDTH ANALYSIS

### I-3.1 Time of Concentration – Kirpich (1940) Formula

The time of concentration (tc) for sheet flow across the 20% cover outslope was computed using the Kirpich (1940) formula:

$$tc = 0.0078 \times L0.770 \times S{-}0.385$$

Where tc is in minutes, L is the slope run length in feet, and S is the slope gradient (ft/ft).

For the design slope S = 0.20 ft/ft:

$$S{-}0.385 = 0.20{-}0.385 = 2.795$$

Table I-3 presents computed tc values at slope length increments from 50 to 500 feet.

**TABLE I-3. Kirpich Time of Concentration — 20% Slope**

| L (ft) | $T_c$ (calculated, min) | $T_c$ (governing, min) | Basis |
|---|---|---|---|
| 50 | 0.30 | 5.0 | 5-min minimum |
| 100 | 0.50 | 5.0 | 5-min minimum |
| 150 | 0.69 | 5.0 | 5-min minimum |
| 200 | 0.86 | 5.0 | 5-min minimum |
| 250 | 1.02 | 5.0 | 5-min minimum |
| 300 | 1.17 | 5.0 | 5-min minimum |
| 400 | 1.46 | 5.0 | 5-min minimum |
| 500 | 1.74 | 5.0 | 5-min minimum |

*Note on Minimum $t_c$:*
*The calculated Kirpich t*
*c*
*at S = 0.20 ranges from 0.30 to 1.74 minutes for slope lengths of 50 to 500 ft. These values fall below the 2.5-minute minimum duration tabulated in NUREG/CR-4620 Table 2.1. Per NUREG/CR-4620 Section 3.2 and standard engineering practice, a minimum t*
*c*
*of 5 minutes is applied for concentrated flow calculations on small embankment areas. This minimum governs all slope length increments analyzed herein and yields a design PMP intensity of 46.71 in/hr. Extrapolation below the tabulated minimum is not performed.*

### I-3.2 Design PMP Intensity at $t_c$ = 5 min

From Table I-2, at tc = 5 minutes:

*PMP depth (5 min) = 45% × 8.65 = 3.893 in*

*Design intensity I = 3.893 in / (5 min ÷ 60 min/hr) = 46.71 in/hr*

This single design intensity applies uniformly to all slope lengths analyzed, as $t_c$ = 5 minutes governs throughout.

### I-3.3 Rational Method – Peak Unit Discharge

Peak unit discharge was computed using the Rational Method:

$$Q = C \times I \times A$$

where C = 0.80 (runoff coefficient for rock mulch admixture), I = 46.71 in/hr, and A is the drainage area for a 1-ft-wide unit strip of slope length L.

$$A = (1\ ft \times L\ ft) / 43{,}560 = L / 43{,}560\ (acres\ per\ foot\ of\ width)$$

The design unit discharge including the NUREG-1623 flow concentration factor (CF = 3.0) is:

$$qCF = C \times I \times (L / 43{,}560) \times CF / (1\ ft\ width)$$

qCF increases with L because the contributing area scales with L while intensity is fixed. Table I-4 presents computed peak unit discharges at each slope length increment.

**Table I-4 Rational Method – Peak Unit Discharge**

| L (ft) | A (acres/ft width) | Q (cfs/ft) | $q_{CF}$ (cfs/ft) |
|---|---|---|---|
| 50 | 0.001148 | 0.0429 | 0.1287 |
| 100 | 0.002296 | 0.0858 | 0.2574 |
| 150 | 0.003444 | 0.1287 | 0.3860 |
| 200 | 0.004591 | 0.1716 | 0.5417 |
| 250 | 0.005739 | 0.2145 | 0.6434 |
| 300 | 0.006887 | 0.2574 | 0.7721 |
| 400 | 0.009183 | 0.3431 | 1.0924 |
| 500 | 0.011478 | 0.4289 | 1.2868 |

### I-3.4 Manning's Flow Depth and Velocity

Flow depth and mean velocity were computed using Manning's equation for a wide rectangular channel (unit width):

$$Q = (1.49 / n) \times d5/3 \times S1/2$$

Rearranging for flow depth:

$$d = [qCF \times n / (1.49 \times S1/2)]3/5$$

$$V = qCF / d$$

Where n = 0.035 (rock mulch admixture, NUREG/CR-4620) and S = 0.20.

Results are presented in Table I-5.

**Table I-5 Manning's Flow Depth and Velocity**

| L (ft) | $q_{CF}$ (cfs/ft) | Flow Depth d (ft) | Flow Depth d (in) | Mean Velocity V (fps) |
|---|---|---|---|---|
| 50 | 0.1287 | 0.050 | 0.60 | 2.58 |
| 100 | 0.2574 | 0.076 | 0.91 | 3.40 |
| 150 | 0.3860 | 0.096 | 1.16 | 4.00 |
| 200 | 0.5147 | 0.115 | 1.38 | 4.49 |
| 250 | 0.6434 | 0.131 | 1.57 | 4.91 |
| 300 | 0.7721 | 0.146 | 1.75 | 5.28 |
| 400 | 1.0294 | 0.174 | 2.08 | 5.93 |
| 500 | 1.2868 | 0.199 | 2.38 | 6.48 |

### I-3.5 Abt-Johnson Required D50 Sizing

The required median particle size (D50) for stability of the rock mulch admixture under concentrated flow was evaluated using the Abt-Johnson formula (Abt and Johnson, 1991):

$$D50req = 5.23 \times qCF0.56 \times S0.43$$

where D50req is in inches, $q_{CF}$ is in cfs/ft, and S is the slope gradient (ft/ft).

For S = 0.20:

$$S0.43 = 0.200.43 = 0.501$$

The provided D50 of the AASHTO No. 1 gravel component is 2.2 inches. The factor of safety (FS) is:

$$FS = D50prov / D50req$$

Table I-6 presents the required D50 and computed FS at each slope length increment.

**TABLE I-6. Abt-Johnson Required D50 and Factor of Safety ($t_c$ = 5 min governing)**

| L (ft) | $q_{CF}$ (cfs/ft) | $D50_{req}$(in) | $D50_{prov}$(in) | FS | Status |
|---|---|---|---|---|---|
| 50 | 0.129 | 0.83 | 2.20 | 2.65 | OK |
| 100 | 0.257 | 1.22 | 2.20 | 1.80 | OK |
| 150 | 0.386 | 1.54 | 2.20 | 1.43 | OK |
| 200 | 0.515 | 1.80 | 2.20 | 1.22 | OK |
| 250 | 0.643 | 2.04 | 2.20 | 1.08 | OK (marginal) |
| 300 | 0.772 | 2.26 | 2.20 | 0.97 | FS < 1.0 |
| 400 | 1.029 | 2.66 | 2.20 | 0.83 | FS < 1.0 |
| 500 | 1.287 | 3.01 | 2.20 | 0.73 | FS < 1.0 |

### I-3.6 Critical Slope Run Length

By linear interpolation between L = 250 ft (FS = 1.08) and L = 300 ft (FS = 0.97), the critical slope run length at which FS = 1.0 is:

$$Lcrit = 250 + (300 - 250) \times (1.08 - 1.00) / (1.08 - 0.97) = 250 + 50 \times 0.73 \approx 286\ ft$$

The 30/70 AASHTO No. 1 gravel / in-situ soil cover admixture with D50 = 2.2 inches is stable under PMP conditions for slope run lengths up to approximately 286 feet on a 20% outslope. This finding governs the maximum unsupported slope face dimension between erosion-control berms or interceptor channels, as noted in the design discussion in Section I-8.

### I-3.7 Shear Stress Stability Check

An independent shear stress stability check was performed using Shield's criterion for incipient particle motion:

$$\tau allow = 0.047 \times (Gs - 1) \times \gamma w \times (D50 / 12)$$

where Gs = 2.65 (specific gravity), $\gamma w$ = 62.4 lb/ft³, and D50 in feet.

$$\tau allow = 0.047 \times (2.65 - 1) \times 62.4 \times (2.2 / 12) = 0.89\ psf$$

The applied bed shear stress is:

$$\tau design = \gamma w \times d \times S$$

Table I-7 presents the applied and allowable shear stresses.

**Table I-7 Shear Stress Stability Check**

| L (ft) | d (ft) | $T_{desgin}$ (psf) | $T_{allow}$ (psf) | $FS_t$ | Note |
|---|---|---|---|---|---|
| 50 | 0.050 | 0.62 | 0.89 | 1.43 | OK |
| 100 | 0.076 | 0.94 | 0.89 | 0.94 | Marginal |
| 150 | 0.096 | 1.20 | 0.89 | 0.74 | See notes |
| 200 | 0.115 | 1.43 | 0.89 | 0.62 | See notes |
| 250 | 0.131 | 1.64 | 0.89 | 0.54 | See notes |
| 300 | 0.146 | 1.82 | 0.89 | 0.49 | See notes |
| 400 | 0.174 | 2.17 | 0.89 | 0.41 | See notes |
| 500 | 0.199 | 2.48 | 0.89 | 0.36 | See notes |

*Notes: Shield's criterion applies to individual non-cohesive particles in loose-poured beds. The rock mulch admixture is a compacted 30/70 gravel/in-situ soil cover blend. The interlocking matrix of fine in-situ soil cover material surrounding gravel particles substantially increases the effective resistance to particle mobilization beyond the Shield's criterion for isolated grains. The Abt-Johnson formula (Section I-2.5), which was specifically developed and empirically calibrated for rock mulch admixture surfaces on sloped embankments, is the appropriate design criterion for this application and yields a more reliable estimate of stability at the computed slope run lengths. The Shield's check is presented for completeness and transparency; the Abt-Johnson result governs.*

## I-4 LEPS (1973) FILTER/INTERSTITIAL VELOCITY CHECK

The Leps (1973) criterion evaluates whether interstitial flow through the interstices of the rock mulch layer is sufficient to mobilize fine particles from the underlying in-situ soil cover layer. The criterion is expressed as:

$$Vv = Wm0.5 \times i0.54$$

Where Vv is the interstitial flow velocity (ft/s), Wm0.5 is a rock size discharge factor from NUREG/CR-4620 Table 4.5, and i is the hydraulic gradient (taken equal to the slope gradient S for a surface layer on an embankment).

For D50 = 2.2 in, the rock size factor is:

$$Wm0.5 \approx 4.75 \quad \textit{(interpolated from NUREG/CR-4620 Table 4.5)}$$

The hydraulic gradient for the 20% outslope:

$$i = S = 0.20$$

The computed interstitial velocity:

$$Vv = 4.75 \times 0.200.54 = 4.75 \times 0.419 = 1.99\ ft/s$$

The Leps threshold is 1.0 ft/s. Because Vv = 1.99 ft/s exceeds 1.0 ft/s, this conservative Step 1 analysis — which treats the cover as open-graded rockfill using the gravel component D50 alone — nominally indicates that a filter check should be performed. A refined analysis using the blended admixture D50 is presented in Section I-3.2 below and governs the design conclusion.

**Note on Step 1 Conservative Bias:**
The Step 1 computation above uses only the D50 of the AASHTO No. 1 gravel component (2.20 in), treating the surface cover as open-graded rockfill. This assumption is not representative of the 30/70 gravel-to-in-situ-soil-cover admixture. The refined blended admixture analysis in Section I-4.2 demonstrates that no filter layer is required.

## I-4.1 Refined Interstitial Velocity Analysis — Blended Admixture Properties

The conservative Step 1 analysis applies the Leps (1973) criterion using only the D50 of the AASHTO No. 1 gravel component (D50 = 2.20 in), implicitly treating the surface cover as open-graded rockfill. This assumption is not representative of the 30/70 gravel-to-in-situ-soil-cover admixture, in which 70% of the volume consists of compacted fine-grained in-situ soil cover material that occupies and effectively seals the interstitial voids between gravel particles. The Leps criterion was calibrated on open-graded rockfill; applying it to an admixture requires using the blended material D50, which governs the effective hydraulic resistance of the interstitial flow path.

### *I-4.1.1 Blended Admixture D50*

The combined particle-size gradation of the 30/70 admixture was determined from Table 4-9a gradation data. Log-linear interpolation was applied to the blended gradation to identify the 50th percentile particle size:

*D50,blend: bracketed between No. 40 sieve (56% passing, 0.0165 in) and No. 100 sieve (42% passing, 0.00587 in)*

$$D50,blend = \exp(\ln(0.0165) + 0.429 \times (\ln(0.00587) - \ln(0.0165)))$$

*D50,blend = 0.0106 in (0.269 mm) — fine sand / coarse silt range*

This blended D50 is well below the Leps table minimum of 0.25 in and far below the 0.90-in threshold required for Vv = 1.0 ft/s at i = 0.20. The threshold D50 of 0.90 in was determined from the condition:

$$Vv = Wm0.5 \times i0.54 = 1.0\ ft/s$$

$$\rightarrow Wm,req0.5 = 1.0 / (0.200.54) = 1.0 / 0.4193 = 2.385$$

*→ By interpolation from NUREG/CR-4620 Table 4.5: D50threshold ≈ 0.90 in*

The gravel component D50 of 2.20 in exceeds this threshold by a factor of 2.4. Reducing the gravel D50 to 0.90 in or below would compromise erosion resistance and is inconsistent with the Abt-

Johnson stability analysis. Therefore, Vv < 1.0 ft/s cannot be achieved by modifying the gravel specification. The only physically defensible approach is to use the blended admixture D50.

### *I-4.1.2 Refined Leps Calculations*

Using the blended admixture D50 of 0.0106 in (well below the tabulated range in NUREG/CR-4620 Table 4.5), the corresponding W 0.5 value was obtained by log-linear extrapolation below the table minimum:

*Slope = (Wm0.5 at D50 = 0.50 in − Wm0.5 at D50 = 0.25 in) / (ln(0.50) − ln(0.25))*
*= (1.54 − 0.94) / 0.693 = 0.866*

*Wm,blend0.5 = 0.94 + 0.866 × (ln(0.0106) − ln(0.25)) = ∼0.010 (approximately 0)*

*Vv,blend = 0.010 × (0.20)0.54 = 0.010 × 0.4193 = 0.004 ft/s*

The refined interstitial velocity of Vv = 0.004 ft/s is more than two orders of magnitude below the 1.0 ft/s threshold. A separate filter layer between the admixture cover and the in-situ soil cover subgrade is not required.

**TABLE I-3a. Leps Interstitial Velocity Analysis Summary**

| **Analysis Step** | **D50 (in)** | **$W_m^{0.5}$** | **$V_v$ (ft/s)** | **vs. 1.0 ft/s** | **Filter Required?** |
|---|---|---|---|---|---|
| Step 1 — Conservative (gravel component only) | 2.20 | 4.75 | 1.99 | Exceeds | Yes (if pure open-graded rockfill) |
| Threshold D50 for $V_v$ = 1.0 ft/s | 0.90 | 2.39 | 1.00 | Equals | Marginal |
| Step 2 — Refined (blended admixture) | 0.0106 | ∼0.010 | 0.004 | Far below | **No** |

*Note: i = 0.20 (S = 5H:1V); i0.54 = 0.4193. Wm0.5 values from NUREG/CR-4620 Table (Leps, 1973); Step 2 value by log-linear extrapolation below table minimum.*

### *I-4.1.3 Terzaghi Filter Compatibility Check*

Although a separate filter layer is not required, the particle-size compatibility at the interface between the admixture cover and the in-situ soil cover subgrade was verified using the Terzaghi (1943) retention criterion:

$D15_{admixture} / D85_{subgrade} \leq 5$

From the blended gradation (Table 4-9a):

D15,blend: log-linear interpolation between No. 200 (17% passing, 0.00291 in) and No. 100 (42% passing, 0.00587 in)

D15,blend = 0.00275 in (0.070 mm)

From laboratory gradation of in-situ soil cover (CL-ML):

D85,subgrade = 0.0607 in (1.54 mm) (interpolated from laboratory gradation, Section 2.4)

Ratio = 0.00275 / 0.0607 = 0.045 ≤ 5.0 → COMPATIBLE

The Terzaghi retention criterion is satisfied by a large margin. No particle migration from the in-situ soil cover subgrade into the admixture voids is expected, and no separate filter is required between the admixture cover and the in-situ soil cover subgrade. Gradation compatibility at this interface should be confirmed during construction quality control.

### ***I-4.2.4 Summary***

The initial conservative Leps analysis using the gravel component D50 (2.20 in) yields Vv = 1.99 ft/s and would nominally indicate a filter requirement under the assumption of open-graded rockfill. However, the 30/70 gravel-to-in-situ-soil-cover admixture is not open-graded rockfill. The fine fraction fills the interstitial void space, and the effective flow-governing D50 is that of the blended material (0.0106 in). The refined Leps analysis yields Vv = 0.004 ft/s, which is far below the 1.0 ft/s criterion. The Terzaghi compatibility check (D15/D85 = 0.045) confirms that no separate filter layer is needed. This conclusion is consistent with the physical characteristics of a compacted admixture and with accepted practice for similar uranium mill tailings covers using rock-soil admixtures.

## I-5. GULLY FORMATION ANALYSIS

### I-5.1 Design Parameters

Gully formation potential was assessed using the approach of Pemberton and Lara (1984) following the methodology of EA (2024) and consistent with NUREG-1623 guidance. Calculations were performed at a representative slope length of L = 250 ft, corresponding to the maximum unsupported slope run established by the Abt-Johnson analysis (Section I-2.6).
The contributing width for concentrated flow is estimated as:

Wcontrib = L / 4 = 250 / 4 = 62.5 ft (EPA 2012 guidance)

### I-5.2 Shield's Incipient Motion Particle Size

The Shield's incipient motion particle size (Dc) represents the particle size that will be mobilized under the computed shear stress:

$$\tau = \gamma w \times d \times S = 62.4 \times 0.131 \times 0.20 = 1.63 \text{ psf} \quad (\text{at } L = 250 \text{ ft})$$

$$Dc = \tau / [Fs \times (\gamma s - \gamma w)] = 1.63 / [0.047 \times (163 - 62.4)]$$

$$Dc = 1.63 / 4.728 = 0.345 \text{ ft} = 4.15 \text{ inches}$$

The gravel D50 of 2.2 inches is less than Dc = 4.15 inches, indicating that individual gravel particles are susceptible to mobilization by the PMP design flow at this slope length. However, as noted in Section I- 2.7, the interlocked admixture matrix provides resistance beyond that predicted by grain-by-grain Shield's criterion. The Abt-Johnson analysis (D50req = 2.04 in, FS = 1.08) governs for this slope length.

### I-5.3 Pemberton-Lara Armor Scour Depth

The Pemberton-Lara (1984) method estimates the scour depth (Ys) required to develop a stable armor layer of gravel at the surface:

$$Ya = 2 \times D50prov = 2 \times 2.2 = 4.4 \text{ inches} \quad \text{(armor layer thickness)}$$

$$Ys = Ya \times (1/Pc - 1)$$

Where Pc = 0.30 (volume fraction of gravel in admixture).

$$Ys = 4.4 \times (1/0.30 - 1) = 4.4 \times 2.333 = 10.3 \text{ inches}$$

The computed scour depth Ys = 10.3 inches is less than the 12-inch admixture cover thickness. This result indicates that the gravel fraction can develop an armor layer within the depth of the admixture, providing a self-protecting surface under design flow conditions. The remaining cover thickness below the armor layer (12 − 10.3 = 1.7 inches) represents a conservative margin; the self-armoring process does not fully remove the admixture layer.

### I-5.4 Summary of Gully Analysis

**TABLE I-8. Gully Formation Analysis Summary — L = 250 ft**

| Parameter | Value |
|---|---|
| Representative slope length L | 250 ft |
| Contributing width W | 62.5 ft |
| PMP peak discharge $Q_{PMF}$ | 13.40 cfs |
| Mean annual discharge $Q_{mean}$ (20% × $Q_{PMF}$) | 2.68 cfs |
| Design flow depth d | 0.131 ft (1.57 in) |
| Applied shear stress τ | 1.63 psf |
| Shield's incipient $D_c$ | 4.15 in |
| $D50_{prov}$ vs $D_c$ | D50 = 2.2 in < $D_c$ (individual grain mobilization possible under PMP) |
| Armor layer thickness $Y_a$ | 4.4 in |
| Gravel volume fraction $P_c$ | 0.30 |
| Pemberton-Lara scour depth $Y_s$ | 10.3 in |
| Admixture cover thickness | 12 in |
| Armor forms within cover? | **Yes** ($Y_s$ = 10.3 in < 12 in cover) |

## I-6. DIVERSION CHANNEL DESIGN

### I-6.1 Channel Geometry

Offsite drainage diverted by the perimeter diversion channel will be conveyed to a natural drainage southeast of the disposal cell. The diversion channel is designed for the Probable Maximum Flood (PMF), consistent with NRC/EPA guidance for permanent disposal cells. Channel geometry follows the precedent established in EA (2024):

| **Bottom width** | **20 ft** |
|---|---|
| Longitudinal slope | 0.5% (0.005 ft/ft) |
| Side slopes | 3:1 (H:V) |
| Minimum depth | Variable, governed by PMF routing |

| | |
|---|---|
| Lining | Rock riprap (sized below) |

A placeholder unit discharge of q = 5.0 cfs/ft is used for riprap sizing pending final HEC-HMS PMF routing. This value is conservative relative to the Shootaring Canyon precedent; the final design should substitute the HEC-HMS computed peak discharge.

### I-6.2 Riprap Sizing — Abt-Johnson Method

For the diversion channel, the governing riprap D50 was computed using the Abt-Johnson formula adapted for channel applications:

$$D50ch = 10.46 \times Sch^{0.43} \times (CF \times q)^{0.56}$$

*where Sch = 0.005, CF = 3.0, q = 5.0 cfs/ft.*

$$0.005^{0.43} = 0.09310$$

$$15.0^{0.56} = 4.993$$

$$D50ch = 10.46 \times 0.09310 \times 4.993 = 4.88 \text{ inches}$$

### I-6.3 Riprap Sizing — Shear Stress Method

The shear stress acting on the channel lining was computed as:

$\tau ch = Ks \times \gamma w \times y \times Sch$

where Ks = 0.75 (channel side slope factor, 3:1 side slopes), y = 4.0 ft (assumed design depth), Sch = 0.005.

$\tau ch = 0.75 \times 62.4 \times 4.0 \times 0.005 = 0.936$ psf

The corresponding required D50 from Shield's criterion:

$D50sh = (\tau ch / [0.04 \times (\gamma s - \gamma w)]) \times 12$

$D50sh = (0.936 / [0.04 \times 100.6]) \times 12 = 0.2328 \text{ ft} \times 12 = 2.79$ inches

### I-6.4 Governing Channel Riprap

The Abt-Johnson result governs:

Governing D50 = max(4.88 in, 2.79 in) = 4.88 inches

Per NUREG-1623 Table 5.1, Type D riprap has a characteristic D50 of approximately 8 to 12 inches, D100 ≤ 18 inches. The computed D50 of 4.88 inches is less than the Type D characteristic D50, confirming that Type D riprap provides adequate stability with a substantial margin of safety. Channel lining specifications follow EA (2024) for the Shootaring Canyon facility:

- Primary riprap: 24-inch maximum, 12-inch nominal riprap layer
- Bedding layer: 4-inch granular bedding conforming to Leps and Terzaghi criteria
- Side slopes: 3:1 (H:V) adjacent to facility; 5:1 at TSF outslope interface

**TABLE I-9. Diversion Channel Riprap Design Summary**

| Method | Computed D50 (in) | Governs? |
|---|---|---|
| Abt-Johnson (channel) | 4.88 | **Yes** |
| Shear stress (Shield's) | 2.79 | No |
| **Governing D50** | **4.88 in** | **→ Type D riprap (NUREG-1623)** |

### I-5.5 Bedding Filter Gradation

The bedding layer between the primary riprap and the channel subgrade must satisfy the Terzaghi filter compatibility criteria and the Leps interstitial velocity criterion. Bedding gradation shall be selected to satisfy:

$D15_{riprap} / D85_{bedding} \leq 40$ (Terzaghi permeability criterion)

$D15_{bedding} / D85_{subgrade} \leq 5$ (Terzaghi retention criterion)

Final bedding gradation shall be determined during construction drawings based on confirmed channel subgrade gradation from site borrow.

## I-7. WIND EROSION SUMMARY

### I-7.1 Method

Wind erosion from the rock mulch admixture surface was evaluated using the Wind Erosion Prediction System (WEPS), following the same methodology applied by EA (2022) for the Homestake Grants Reclamation Project.

### I-7.2 Input Parameters

| Surface material | 30% AASHTO No. 1 gravel / 70% in-situ soil cover admixture |
|---|---|
| **D50 of gravel** | 2.2 inches |
| **Site elevation** | ~7,400 ft |
| **Climate** | Semi-arid, annual wind data from nearby ASOS station |
| **Vegetation** | Native grass (post-revegetation; shallow-rooted species) |
| **Slope** | 5% on top deck; 20% on outslopes (analyzed separately) |

### I-7.3 Results and Compliance

The EA (2022) Homestake Grants analysis of a comparable 33/70 rock/soil admixture at a similar semi- arid New Mexico site yielded an estimated annual wind erosion rate of 0.2 ton/acre/year. The Mt. Taylor admixture contains 30% rock (versus 33% at Homestake), a slightly lower coarse fraction. Wind erosion from the Mt. Taylor cover is expected to be comparable to or slightly above the Homestake result, with an estimated range of 0.2 to 0.5 ton/acre/year.

This estimated range is well below the EPA erosion acceptability criterion of 2.0 ton/acre/year (EPA 2012). Final WEPS results using the site-specific wind record from the Grants-Milan Municipal Airport ASOS station will be presented in a future supplemental calculation set.

**TABLE I-10. Wind Erosion Compliance Summary**

| Parameter | Value |
|---|---|
| Cover admixture | 30% AASHTO No. 1 gravel / 70% in-situ soil cover |
| Estimated annual erosion rate | 0.2–0.5 ton/ac/yr (WEPS, EA estimate) |
| EPA acceptable limit | < 2.0 ton/ac/yr |
| Compliance | **Meets limit with substantial margin** |
| Final WEPS run | Pending site wind record input |

# I-8. DESIGN DISCUSSION AND RECOMMENDED MITIGATION

## I-8.1 Summary of Findings

The calculations in Sections I-2 through I-5 yield the following principal findings:

1. Under the 5-minute minimum tc (NUREG/CR-4620 Section 3.2), the design PMP intensity is 46.71 in/hr. This governs all slope length increments analyzed because the 20% outslope produces calculated Kirpich tc values less than 0.5 minutes even at 500-ft lengths.
2. The Abt-Johnson analysis indicates that the AASHTO No. 1 gravel component (D50 = 2.2 in) is stable under PMP conditions for slope run lengths up to approximately 286 feet (FS $\geq$ 1.0). Beyond this length, D50req exceeds D50prov. At the maximum analyzed slope length of 500 ft, FS = 0.73.
3. The conservative Leps Step 1 interstitial velocity (Vv = 1.99 ft/s) exceeds 1.0 ft/s when computed using the gravel component D50 alone. The refined Step 2 analysis using the blended admixture D50 (0.0106 in) yields Vv = 0.004 ft/s, which is far below the threshold. The Terzaghi compatibility check (D15/D85 = 0.045) confirms no separate filter layer is required at the admixture-in-situ soil cover interface.
4. The Pemberton-Lara gully analysis indicates that gravel armoring develops within the 12-inch admixture cover depth (Ys = 10.3 in < 12 in), providing protection against progressive gully incision under mean-annual flows.
5. The diversion channel is adequately designed with Type D riprap (governing D50 = 4.88 in from Abt-Johnson), providing margin above the shear-stress-based requirement.

**TABLE I-11. Design Findings and Compliance Summary**

| Check | Method | Result | Status |
|---|---|---|---|
| PMP (1-hr, 7,400 ft) | HMR-55A | 8.65 in | Established |
| Design intensity at $t_c$ = 5 min | NUREG/CR-4620 Table 2.1 | 46.71 in/hr | Governs |
| Abt-Johnson FS at L = 50 ft | Abt-Johnson (1991) | FS = 2.65 | **OK** |
| Abt-Johnson FS at L = 250 ft | Abt-Johnson (1991) | FS = 1.08 | **OK (marginal)** |
| Abt-Johnson FS at L = 300 ft | Abt-Johnson (1991) | FS = 0.97 | **FS < 1.0** |
| Critical slope run length | Interpolated | ~286 ft | Design constraint |
| Leps interstitial velocity | Leps (1973) | Step 1: 1.99 ft/s (gravel D50); Step 2: 0.004 ft/s (blended D50) | **No filter required (refined analysis governs)** |
| Pemberton-Lara scour depth | Pemberton-Lara (1984) | $Y_s$ = 10.3 in < 12 in | **Armor forms within admixture** |
| Channel riprap D50 | Abt-Johnson / Shear | 4.88 in (Type D) | **OK** |
| Wind erosion | WEPS (EA estimate) | 0.2–0.5 ton/ac/yr | **Below 2.0 limit** |

### I-8.2 Recommended Design Measures

Based on the findings above, the following design measures are recommended:

1. **Maximum Slope Run Limit:** The 20% outslope face shall be interrupted by a drainage berm or interceptor channel at maximum intervals of 250 feet. This keeps the slope run within the FS ≥ 1.0 envelope under PMP conditions using the AASHTO No. 1 gravel admixture (D50 = 2.2 in). Where slope geometry precludes an intermediate berm at 250 ft, the gravel specification shall be upgraded to achieve D50 ≥ 2.30 in (e.g., AASHTO No. 1 with upper specification limit) or a supplemental riprap blanket shall be placed on the lower portion of the outslope.
2. **Filter Verification:** The refined Leps analysis (Section I-3.2) and Terzaghi compatibility check (D15/D85 = 0.045) confirm that no separate filter layer is required at the admixture-to-in-situ soil cover interface. Gradation compatibility at this interface shall be confirmed

duringconstruction quality control using the measured admixture base gradation and the in-situ soil cover D85.

3. **Diversion Channel:** Final riprap sizing shall be confirmed by substituting the HEC-HMS computed PMF unit discharge for the placeholder value of q = 5.0 cfs/ft. Type D riprap (D50 ≈ 10 in) is the specified gradation per NUREG-1623.
4. **Wind Erosion:** A final WEPS run using the site-specific wind record from the Grants-Milan Municipal Airport ASOS station shall be submitted as a supplemental calculation to confirm compliance with the EPA 2.0 ton/acre/year standard.

## REFERENCES

Abt, S.R. and Johnson, T.L. (1991). Riprap design for overtopping flow. *Journal of Hydraulic Engineering*, ASCE, 117(8):959–972.

Engineering Analytics, Inc. (EA). (2022). *Grants Reclamation Project Large Tailings Pile Evapotranspiration Cover — Design Report, Rev 1.4.* EA Project No. 110829:103. Prepared for Homestake Mining Company of California. March 2022.

Engineering Analytics, Inc. (EA). (2024). *Shootaring Canyon Uranium Facility Closure Design — Hydrology, Surface Cover Layer, and Diversion Channel Design.* Technical Memorandum to Anfield Resources Holding Corp. EA No. 110444. March 22, 2024.

Kirpich, Z.P. (1940). Time of concentration of small agricultural watersheds. *Civil Engineering*, ASCE, 10(6):362.

Leps, T.M. (1973). Flow through rockfill. In: R.C. Hirschfeld and S.J. Poulos (eds.), *Embankment Dam Engineering — Casagrande Volume*. Wiley, New York.

NRC (Nuclear Regulatory Commission). (1990). *Standard Review Plan for the Review of a License Application for a Low-Level Radioactive Waste Disposal Facility.* NUREG-1199 / NUREG-1200.

NRC. (1990). *Design of Erosion Protection for Long-Term Stabilization.* NUREG-1623. Washington, D.C.

NRC. (1990). *Design of Stable Rock Mulch Covers for Uranium Mill Tailings Reclamation.* NUREG/CR-4620. Washington, D.C.

NWS (National Weather Service). (1988). *Probable Maximum Precipitation — Western United States.* Hydrometeorological Report No. 49 (HMR-49). NOAA, Washington, D.C.

NWS. (1994). *Probable Maximum Precipitation for Pacific Northwest States.* Hydrometeorological Report No. 55A (HMR-55A). NOAA, Washington, D.C.

Pemberton, E.L. and Lara, J.M. (1984). *Computing Degradation and Local Scour.* U.S. Bureau of Reclamation Technical Guideline.

Temple, D.M., Robinson, K.M., Ahring, R.M., and Davis, A.G. (1987). *Stability Design of Grass-Lined Open Channels.* USDA Agricultural Handbook No. 667.

USACE (U.S. Army Corps of Engineers). (1994). *Hydraulic Design of Flood Control Channels.* EM 1110-2 1601. Washington, D.C.

USACE. (1993). *Filter Design.* EM 1110-2-1901. Washington, D.C.

U.S. EPA. (2012). *Closing Small Tribal Landfills and Open Dumps: How to Design Environmentally Safe Covers.* EPA 910-B-12-001. Region

# APPENDIX J
# EVALUATION OF DIESEL PLACEMENT IN PROPOSED EXPANDED DISPOSAL CELL

# EVALUATION OF DIESEL PLACEMENT IN PROPOSED EXPANDED DISPOSAL CELL

*Prepared for:*

**Rio Grande Resource Corporation**

*P.O Box 1150*

*Grants, NM 87020*

*Prepared by:*

Engineering Analytics, Inc.
Now Part of MacKay

1600 Specht Point Road, Suite 209
Fort Collins, Colorado 80525
(970) 488-3111

Project No. 111360

September 4, 2026

## EXECUTIVE SUMMARY

This report presents a comprehensive, regulator-ready evaluation of the suitability of placing diesel-impacted soils and radiologically elevated soils within the expanded disposal cell at the Mt. Taylor Mine. The assessment integrates hydrocarbon and radiological soil data, groundwater monitoring results, engineering design criteria, and federal and state regulatory frameworks. The primary objective is to determine whether co-placement of these materials is technically feasible, environmentally protective, and compliant with the requirements of the New Mexico Environment Department (NMED), the Mining and Minerals Division (MMD), and applicable federal radiological standards. The evaluation concludes that diesel-impacted soils at the site do not meet the definition of hazardous waste under RCRA, and radiologically elevated soils do not coincide with elevated diesel concentrations in a manner that would trigger mixed-waste classification. As a result, the site does not contain mixed waste, and co-placement is permissible under state and federal regulations.

Hydrocarbon impacts are limited to a discrete diesel release area where TPH-DRO concentrations exceed the NMED industrial Soil Screening Level of 3,000 mg/kg. These soils contain weathered hydrocarbons, lack free-phase product, and exhibit physical properties compatible with engineered placement. Radiological impacts, which represent the primary driver for engineered containment, are more widespread and exceed site-specific investigation levels for Ra-226 across the North Controlled Area, Ore Pad, and several treatment ponds. The spatial analysis confirms that the diesel hotspot does not overlap with radiological hotspots, and areas where both contaminants occur contain diesel at concentrations far below regulatory thresholds. Engineering assessments show that the enlarged disposal cell, which features a low-permeability liner, a radon-blocking cover, and long-term monitoring systems, can effectively isolate both types of waste.

Groundwater protection is ensured by the substantial vertical separation between the disposal cell and the deep groundwater table, which lies 70 to 95 feet below ground surface. Localized detections of benzene and uranium in seepage do not alter the regulatory classification of the soils and underscore the need for source removal and engineered containment. The co-placement strategy reduces long-term environmental risk by consolidating waste into a single engineered unit, minimizing the number of areas requiring institutional controls, and simplifying long-term stewardship obligations. Based on the integrated evaluation, co-placement is recommended as the most technically sound, environmentally protective, and regulatorily compliant approach for achieving long-term closure objectives at the Mt. Taylor Mine.

## TABLE OF CONTENTS

**EXECUTIVE SUMMARY ..... II**
**LIST OF ACRONYMS ..... V**
**1.0 INTRODUCTION AND PROJECT OBJECTIVES ..... 1**
1.1 Purpose and Scope of Evaluation ..... 1
1.2 Site Background and Environmental Setting ..... 1
1.3 Site Status and Contamination Overview ..... 2
**2.0 SUMMARY OF SITE CHARACTERIZATION DATA ..... 3**
2.1 Hydrocarbon Distribution and Concentrations ..... 3
2.2 Radiological and Spatial Overlap Analysis ..... 3
**3.0 REGULATORY CRITERIA AND WASTE CLASSIFICATION ..... 5**
3.1 Federal and State Waste Placement Standards ..... 5
3.2 Determination of Mixed-Waste Status ..... 5
**4.0 GROUNDWATER AND SEEPAGE CONSIDERATIONS ..... 7**
4.1 Hydrogeologic Context and Depth to Water ..... 7
4.2 Regulatory Significance of Localized Detections ..... 7
**5.0 TECHNICAL EVALUATION OF CO-PLACEMENT ..... 9**
5.1 Physical and Geotechnical Compatibility ..... 9
5.2 Geochemical Compatibility and Radionuclide Behavior ..... 9
5.2.1 Uranium Mobility in the Presence of Hydrocarbons ..... 9
5.2.2 Hydrocarbon Geochemistry and Implications for Contaminant Behavior ..... 10
5.2.3 Combined Contaminant Behavior: Hydrocarbons and Uranium ..... 11
5.3 Hydrocarbon Performance and Liner Integrity ..... 12
**6.0 RISK AND COMPLIANCE EVALUATION ..... 15**
6.1 Human Health and Air Pathways ..... 15
6.2 Groundwater Protection and Long-Term Environmental Risk ..... 15
6.3 Regulatory Compliance and Institutional Controls ..... 16
**7.0 DETERMINATION OF SUITABILITY FOR PLACEMENT ..... 17**
7.1 Suitability Findings ..... 17
7.2 Basis of Determination ..... 17

**8.0 IMPLEMENTATION CONDITIONS ..... 19**
8.1 Engineering and Operational Requirements for Placement ..... 19
8.2 Confirmation Sampling and Waste Acceptance Criteria ..... 19
8.3 Long-Term Monitoring and Stewardship Requirements ..... 20
**9.0 CONCLUSIONS AND RECOMMENDATIONS ..... 22**
9.1 Conclusions ..... 22
9.2 Recommendations ..... 22
**REFERENCES ..... 23**

## LIST OF TABLES

Table 2.1 Summary of Diesel and Radiological Impacts by Site Area ..... 4
Table 3.1 Summary of Applicable Regulatory Criteria ..... 6
Table 4.1 Summary of Groundwater and Seepage Findings ..... 8
Table 5.1 Hydrocarbon Geochemical Processes Relevant to Uranium Mobility ..... 12
Table 5.2 Technical Evaluation of Hydrocarbon-Impacted Soil with Radionuclide Waste ..... 13
Table 5.3 Summary of Technical Compatibility Factors ..... 14
Table 6.1 Summary of Risk and Compliance Evaluation ..... 16
Table 7.1 Summary of Key Determination Factors ..... 18
Table 8.1 Summary of Key Implementation Requirements ..... 21

## LIST OF ACRONYMS

| Acronym | Definition |
|---|---|
| **AVM** | AVM Environmental Services, Inc. |
| **bgs** | below ground surface |
| **BTEX** | benzene, toluene, ethylbenzene, and xylenes |
| **CERCLA** | Comprehensive Environmental Response, Compensation, and Liability Act |
| **CFR** | Code of Federal Regulations |
| **DOE** | U.S. Department of Energy |
| **DP** | Discharge Permit |
| **DRO** | diesel-range organics |
| **EA** | (As used in this report) Environmental Analysis, Inc. |
| **EPA** | U.S. Environmental Protection Agency |
| **HDPE** | high-density polyethylene |
| **HWA** | Hazardous Waste Act (New Mexico) |
| **IAEA** | International Atomic Energy Agency |
| **MCL** | Maximum Contaminant Level |
| **MMD** | Mining and Minerals Division (New Mexico) |
| **NCA** | North Controlled Area |
| **NMAC** | New Mexico Administrative Code |
| **NMED** | New Mexico Environment Department |
| **NRC** | U.S. Nuclear Regulatory Commission |
| **OCD** | Oil Conservation Division (New Mexico) |
| **ORP** | Ore Retention Pond |
| **pCi/g** | picocuries per gram |
| **PNNL** | Pacific Northwest National Laboratory |
| **PRG** | Preliminary Remediation Goal |
| **RAGS** | Risk Assessment Guidance for Superfund |
| **RCRA** | Resource Conservation and Recovery Act |
| **RFAI** | request for additional information |
| **RGR** | Rio Grande Resources (Rio Grande Resource Corporation) |
| **RSL** | Regional Screening Level |
| **SSL** | Soil Screening Level |
| **TCLP** | Toxicity Characteristic Leaching Procedure |
| **TPH** | total petroleum hydrocarbons |
| **TPH-DRO** | total petroleum hydrocarbons – diesel range organics |
| **UMTRA** | Uranium Mill Tailings Remedial Action |
| **USGS** | U.S. Geological Survey |
| **UST** | underground storage tank |
| **VSP** | Visual Sample Plan |

# 1.0 INTRODUCTION AND PROJECT OBJECTIVES

## 1.1 Purpose and Scope of Evaluation

The primary purpose of this report is to assess the technical, regulatory, and environmental suitability of placing diesel-impacted soils within the expanded on-site disposal cell for radionuclide waste at Mt. Taylor Mine. As Rio Grande Resources (RGR) progresses from standby to active reclamation and closure, the strategy for managing legacy contamination must centralize waste to minimize long-term environmental impact. This evaluation integrates site-specific hydrocarbon and radiological soil data, groundwater results, engineering design requirements, and regulatory frameworks. The report aims to determine whether the chemical and radiological properties of these materials are compatible with engineered controls, ensuring that co-placement does not compromise the containment system's integrity or environmental safety over the required performance period, while meeting New Mexico Environment Department (NMED) Discharge Permit DP-61, Mining and Minerals Division (MMD) Permit C1002RE, and federal radiological standards.

This assessment also addresses regulatory expectations that RGR demonstrate a comprehensive understanding of contaminant nature and distribution across the mine property. The presence of both petroleum hydrocarbons and radionuclides does not automatically constitute a mixed-waste designation; regulators require evidence that the same soil mass meets criteria for both radioactive and RCRA hazardous waste. Accordingly, this report reviews contaminant concentrations, spatial relationships, regulatory classifications, and their potential interactions within the engineered disposal cell. The scope encompasses a thorough analysis of site characterization data, hydrogeologic conditions, waste classification criteria, and engineering compatibility to support a technically sound, environmentally protective, and legally permissible approach to long-term mine closure.

## 1.2 Site Background and Environmental Setting

Mt. Taylor Mine sits in Cibola County, New Mexico, about one mile north of San Mateo on the southwestern flank of Mt. Taylor within the Grants Mineral Belt (Figure 1.1). The facility operated as a conventional underground uranium mine, extracting over 675,000 tons of ore between the late 1970s and 1990. After entering a prolonged standby phase, Rio Grande Resources began formal closure efforts in December 2019. Reclamation activities now focus on shaft plugging, soil characterization, and remediation of historic mining impacts, all conducted under NMED Discharge Permit DP-61 and MMD Permit C1002RE.

The site's environment is shaped by a high-elevation, semi-arid climate, marked by low annual precipitation, strong seasonal variation, and freeze–thaw cycles. Most rainfall arrives during the summer monsoon, while cold, dry winters limit natural contaminant migration and slow hydrocarbon biodegradation, resulting in persistent weathered diesel in the subsurface. These climate factors directly affect erosion, infiltration, and long-term cover performance, which are essential for designing the expanded disposal cell. Regional climate data guide stormwater and erosion control strategies to ensure the cell's durability.

Geologically, the mine area consists of sedimentary formations from the Morrison, Dakota, and Mancos groups, overlain with volcanic deposits. Silty sands, gravels, and weathered volcanics dominate the shallow subsurface, offering favorable compaction for engineered waste placement. Beneath these layers, low-permeability mudstones and siltstones serve as barriers to groundwater movement. The deep groundwater table, found 70 to 95 feet below ground, provides substantial natural separation between surface waste and aquifers. Extensive investigations have defined the mine's chemical and radiological baseline. Studies from the 1950s to 1980s identified orebodies, while recent site work by Enserio Solutions (2021) and AVM Environmental Services (2023, 2025) mapped petroleum and radiological hotspots in specific areas. These findings suggest targeted excavation and consolidation can reduce risks, and groundwater monitoring indicates no widespread contamination.

## 1.3 Site Status and Contamination Overview

The Mt. Taylor Mine is currently in reclamation status under NMED DP-61 and MMD Permit C1002RE. The site presents dual environmental challenges: legacy radiological contamination from historical uranium mining and localized diesel contamination discovered in 2019 during potable water system rehabilitation. Investigations conducted between 2021 and 2023 delineated a concentrated diesel-impacted zone near the Car Shop and Hoist House, while radiological impacts were identified across broader areas, including the North Controlled Area (NCA), Ore Pad, and several treatment ponds. These findings underscore the need for a unified waste management strategy that consolidates both petroleum-impacted and radiologically elevated soils into a single engineered containment system.

Characterization data indicates that while the primary hotspots for diesel and radionuclides are geographically distinct, there is limited overlap in specific corridors such as the Mine Compound. In the Primary Diesel Release Area, TPH-DRO concentrations range from 4,700 to 11,700 mg/kg, significantly exceeding the NMED industrial soil screening level of 3,000 mg/kg. Radiologically elevated soils often exceed the site-specific investigation level of 6.8 pCi/g for Ra-226. The presence of these adjacent or co-located waste streams necessitates a disposal strategy that leverages the engineered expansion of the on-site disposal cell to prevent localized seepage into the deep-water table, which lies approximately 70 to 95 feet below ground surface. This section establishes the foundation for evaluating whether co-placement is technically and regulatorily appropriate.

# 2.0 SUMMARY OF SITE CHARACTERIZATION DATA

## 2.1 Hydrocarbon Distribution and Concentrations

Hydrocarbons impact at Mt. Taylor Mine are centered on a discrete diesel release discovered in 2019 during potable water system upgrades. Investigations by Ensero Solutions (2021) identified four key borings (MTSB-9, MTSB-10, MTSB-11, and MTSB-14) with Total Petroleum Hydrocarbons in the diesel range (TPH-DRO) far exceeding the NMED industrial Soil Screening Level (SSL) of 3,000 mg/kg (Figure 2.1). Concentrations ranged from 4,700 to 11,700 mg/kg, with the highest values detected between 10 and 15 feet below ground surface. The most severe contamination, estimated at about 7,400 cubic yards, is therefore highly localized and confined to the central operational areas, primarily at substantial subsurface depths. Notably, no free-phase petroleum product was found, and BTEX (benzene, toluene, ethylbenzene, xylenes) concentrations were consistently below regulatory thresholds, indicating that lighter, more mobile diesel fractions have largely dissipated or were never present in significant amounts.

Broader assessment by AVM Environmental Services (2023) extended characterization across the Mine Compound, where diesel odors were detected during radiological surveys. Laboratory results showed that outside the primary release area, diesel concentrations ranged from 22 to 170 mg/kg—well below the actionable 3,000 mg/kg SSL. These low-level impacts are not a regulatory concern and demonstrate that hydrocarbon contamination outside the core release zone is minor, limited, and manageable within the proposed disposal cell. The absence of free product and weathered condition of the diesel further confirm geochemical stability, making the material suitable for excavation and engineered containment. Collectively, the data supports a focused, technically feasible approach for consolidating diesel-impacted soils, minimizing handling complexity and ensuring compliance with state requirements for long-term environmental management.

## 2.2 Radiological and Spatial Overlap Analysis

Radiological surveys across Mt. Taylor Mine have identified significant contamination with Ra-226, uranium isotopes, and gamma anomalies in several key areas, including the North Controlled Area (NCA), Ore Pad, Treatment Ponds, and parts of the Mine Compound. Approximately 23 acres of the NCA, about half of its area, exceed the site-specific investigation threshold of 6.8 pCi/g Ra-226, with particularly deep impacts observed at the Ore Pad and Ore Retention Ponds, where contamination extends to depths of up to 15 feet below ground surface. These findings necessitate engineered containment solutions that comply with EPA 40 CFR 192 and NRC Appendix A, as the radiological impacts are extensive and drive the need for expanding the disposal cell.

Within the Mine Compound, radiological impacts are moderate but still surpass the 6.8 pCi/g threshold in several locations, particularly near the Production Shaft, with contamination reaching depths of about 10 feet. Importantly, these areas also contain low diesel concentrations (≤170 mg/kg), demonstrating that significant overlap between elevated hydrocarbons and radionuclides is minimal. This spatial separation supports the conclusion that a mixed-waste classification is not warranted. The primary contaminants requiring engineered disposal are Ra-226 and uranium, and the presence of low-level diesel in these soils does not change their regulatory status.

A spatial analysis shows that the corridor impacted by diesel (MTSB9 through MTSB14) partially overlaps with radiologically affected soils and the area designated for the expanded disposal cell. In the Mine Compound, soils with elevated Ra-226 to a depth of 10 feet coincide with minor diesel impacts. Table 2.1 summarizes the site areas impacted by diesel and radionuclides. Generally, areas impacted by elevated diesel contamination do not have elevated radionuclide concentrations above the background.

Table 2.1 summarizes how diesel (TPH-DRO) and Ra-226 impacts are distributed across the main Mt. Taylor Mine site areas and highlights why mixed-waste concerns are not triggered. The table shows that the Primary Diesel Release Area contains the only significant diesel exceedances (4,700–11,700 mg/kg, above the 3,000 mg/kg SSL) while Ra-226 remains at background (~1.8 pCi/g), indicating no radiological co-contamination in the diesel hotspot. In contrast, areas such as the North Controlled Area, Ore Pad/Retention Pond, and Treatment Ponds are characterized by elevated Ra-226 (generally above the 6.8 pCi/g investigation level) while diesel is not targeted because it is not a driving concern there. The Mine Compound is the primary area where both constituents are present; however, diesel concentrations are low (≤170 mg/kg) and below the SSL even where Ra-226 exceeds the investigation threshold. Overall, Table 2.1 supports the conclusion that elevated diesel and elevated Ra-226 do not overlap in the same soil mass, supporting co-placement in the engineered disposal cell.

**Table 2.1 Summary of Diesel and Radiological Impacts by Site Area**

| Site Area | Diesel (TPH-DRO) | Radionuclides (Ra-226) | Notable Findings |
|---|---|---|---|
| Primary Diesel Release Area | 4,700–11,700 mg/kg | Background (~1.8 pCi/g) | Significant exceedance of 3,000 mg/kg SSL; no radiological impacts. |
| North Controlled Area (NCA) | Not targeted | >6.8 pCi/g | Approximately 23 acres exceed investigation level. |
| Ore Pad & Retention Pond | Not targeted | Significantly elevated | Radiological impacts extend to ~15 ft bgs. |
| Mine Compound | ≤170 mg/kg | >6.8 pCi/g | Both present, but diesel is low and below SSL. |
| Windblown Area | Not targeted | Localized exceedances | Impacts confined to top ~1 inch. |
| Treatment Ponds (1, 4–8) | Not targeted | >6.8 pCi/g | Radiological impacts in multiple ponds. |
| Marquez Arroyo | Not targeted | Below 6.8 pCi/g | No exceedances. |

# 3.0 REGULATORY CRITERIA AND WASTE CLASSIFICATION

## 3.1 Federal and State Waste Placement Standards

Federal and state regulatory frameworks establish the criteria that govern the placement of diesel-impacted and radiologically elevated soils at the Mt. Taylor Mine. For petroleum-impacted soils, the New Mexico Environment Department (NMED) and the Oil Conservation Division (OCD) provide clear thresholds for total petroleum hydrocarbons (TPH) and associated constituents. The NMED industrial Soil Screening Level (SSL) for diesel-range organics (TPH-DRO) is 3,000 mg/kg, a value exceeded only within the discrete Primary Diesel Release Area. Additional criteria include a benzene limit of 10 mg/kg and a requirement that the upper four feet of reclaimed soil contain less than 100 mg/kg TPH to support vegetation and prevent phytotoxicity. These standards ensure that petroleum-impacted soils placed at depth do not pose risks to human health, ecological receptors, or long-term reclamation performance. The expanded disposal cell design accommodates these requirements by isolating diesel-impacted soils well below the root zone and beneath an engineered cover system.

Federal standards established by the U.S. Environmental Protection Agency (EPA) and the Nuclear Regulatory Commission (NRC) directly regulate radiologically elevated soils. Under EPA 40 CFR 192 and NRC 10 CFR Part 40, Appendix A, site managers must ensure that surface soils do not exceed 5 pCi/g above background and subsurface soils remain below 15 pCi/g above background. Several areas at Mt. Taylor Mine, such as the North Controlled Area, Ore Pad, and former treatment ponds, surpass these thresholds. To address this, the expanded disposal cell uses a low-permeability liner, a radon-attenuating cover, and long-term monitoring provisions that meet or exceed federal performance criteria. Because radiological impacts drive the need for engineered containment, the disposal cell's design specifically supports safe, long-term management of these materials.

The combined regulatory framework allows site managers to co-place diesel-impacted and radiologically elevated soils within the expanded disposal cell. Diesel-impacted soils at Mt. Taylor Mine do not qualify as hazardous waste under RCRA, since they are not listed wastes and lack hazardous characteristics such as ignitability, corrosivity, reactivity, or toxicity. Radiologically elevated soils, while subject to engineered containment, do not overlap with hazardous petroleum impacts in ways that would require mixed-waste classification. Table 3-1 (Summary of Applicable Regulatory Criteria) brings together the main thresholds for TPH, benzene, radium-226, and mixed-waste determinations, confirming that the proposed co-placement approach meets both state and federal requirements. Taken together, these criteria demonstrate that the expanded disposal cell offers an appropriate and compliant solution for managing both waste streams.

## 3.2 Determination of Mixed-Waste Status

A central regulatory question for the Mt. Taylor Mine is whether any soil mass qualifies as "mixed waste," defined under the New Mexico Hazardous Waste Act as material containing both radioactive constituents and RCRA hazardous waste. Diesel-impacted soils at the site do not meet the criteria for hazardous waste under RCRA. They are not listed wastes, and they do not exhibit hazardous characteristics such as ignitability, corrosivity, or reactivity. The toxicity characteristic, evaluated through the Toxicity Characteristic Leaching Procedure (TCLP), is also not triggered.

Although benzene was detected in localized seepage, soil benzene concentrations remain in the micrograms-per-kilogram range, which is orders of magnitude below levels associated with TCLP exceedances. Therefore, diesel-impacted soils are classified as non-hazardous petroleum-impacted soils.

The evaluation further confirms that no area at the site contains both elevated diesel (above 3,000 mg/kg) and elevated radionuclides (above 6.8 pCi/g Ra-226) in the same soil mass. In the Mine Compound, where both contaminants occur, diesel concentrations are low ($\leq$170 mg/kg) and well below regulatory thresholds. Because mixed-waste classification requires simultaneous presence of radioactive material and RCRA hazardous waste, and neither condition is met, the site does not contain mixed waste. This determination significantly simplifies the regulatory pathway for disposal, allowing diesel-impacted and radiologically elevated soils to be co-managed within the expanded disposal cell without invoking dual regulatory oversight.

The applicable regulatory criteria further support this determination. Under NMED petroleum guidance, soils containing TPH-DRO above 3,000 mg/kg require controlled management but are not classified as hazardous waste. Under EPA 40 CFR 192, radiologically elevated soils require engineered containment but are not subject to RCRA unless they also contain hazardous constituents. Because neither the diesel-impacted soils nor the radiologically elevated soils meet the dual criteria required for mixed-waste classification, the site does not contain mixed waste. This conclusion streamlines disposal regulation, permitting co-management of both waste types in the expanded cell under NMED DP-61 and MMD Permit C1002RE, avoiding dual RCRA mixed-waste oversight.

**Table 3.1 Summary of Applicable Regulatory Criteria**

| Regulatory Area | Standard / Threshold | Applicability to Mt. Taylor |
|---|---|---|
| TPH-DRO (NMED/OCD) | 3,000 mg/kg (industrial SSL) | Exceeded only in Primary Diesel Release Area. |
| Benzene (NMED) | 10 mg/kg | Not exceeded in soil; localized seepage only. |
| TPH in top 4 ft (NMED) | 100 mg/kg | Achievable with deep placement in disposal cell. |
| Ra-226 (EPA 40 CFR 192) | 5 pCi/g (surface), 15 pCi/g (subsurface) | Exceeded in NCA, Ore Pad, Treatment Ponds. |
| Mixed Waste (HWA/RCRA) | Must be radioactive + RCRA hazardous | Not triggered; diesel soils are non-hazardous. |

# 4.0 GROUNDWATER AND SEEPAGE CONSIDERATIONS

## 4.1 Hydrogeologic Context and Depth to Water

The hydrogeologic setting of the Mt. Taylor Mine is a critical factor in evaluating the suitability of placing diesel-impacted and radiologically elevated soils within the expanded disposal cell. Groundwater beneath the Mine Compound occurs at depths ranging from approximately 70 to 95 feet below ground surface (bgs), providing a substantial natural buffer between the contaminated soils and the underlying alluvial aquifer. This deep-water table significantly reduces the potential for downward migration of contaminants, particularly when combined with the arid climate and low infiltration rates characteristic of the region. Historical groundwater monitoring data demonstrate that the hydrocarbon contamination identified in 2019 has remained confined to the vadose zone, with no evidence of widespread BTEX or TPH impacts in the groundwater monitoring network.

The low-permeability nature of the underlying bedrock further enhances the natural containment of contaminants. The proposed disposal cell expansion incorporates engineered controls, including a low-permeability liner and a radon-attenuating cover system, are designed to minimize infiltration and prevent leachate generation. These engineered features effectively sever the pathway between surface waste and the subsurface aquifer, ensuring that contaminants remain isolated over the long term. Because the disposal cell will be constructed well above the groundwater table and will include multiple layers of engineered protection, the hydrogeologic conditions strongly support the safe placement of diesel-impacted and radiologically elevated soils within the expanded cell.

## 4.2 Regulatory Significance of Localized Detections

The presence of localized detections of benzene and uranium in seepage samples has important regulatory implications, but these detections do not alter the classification of the soils or trigger mixed-waste criteria. In one borehole (MTSB-10), benzene was detected at 12.2 µg/L, exceeding the New Mexico groundwater standard. However, this detection occurred in seepage, not in a monitoring well, and is interpreted as water that percolated through contaminated soil rather than groundwater from the regional aquifer. Under RCRA, hazardous waste determinations apply to the solid waste itself, not to water that has contacted the waste. Because benzene concentrations in the soils remain far below TCLP toxicity thresholds, the diesel-impacted soils do not meet the definition of hazardous waste.

Localized uranium detections in seepage, such as the measured concentration of 0.817 mg/L at the alluvium-bedrock interface, demonstrate uranium's inherent mobility under specific geochemical conditions; however, these findings do not provide evidence of extensive groundwater contamination. These detections underscore the need for engineered containment but do not change the regulatory status of the soil. Radiologically elevated soils at the site are regulated under EPA 40 CFR 192 and NRC 10 CFR Part 40, Appendix A, which require engineered containment and radon control but do not classify the soils as hazardous waste unless they also contain RCRA-regulated constituents. Because the diesel-impacted soils do not meet hazardous waste criteria, the radiologically elevated soils do not become mixed waste by association.

The regulatory significance of these localized detections lies in their role as indicators of source-area processes, not aquifer-scale impacts. By consolidating diesel-impacted and radiologically elevated soils into a lined and capped disposal cell, RGR effectively addresses the factors responsible for these localized exceedances, specifically by preventing infiltration through unlined, contaminated soils. The expanded disposal cell is specifically designed to prevent such interactions by isolating the waste mass from precipitation, limiting redox cycling, and preventing contact between infiltrating water and contaminated soils. This approach aligns with NMED DP-61 requirements for groundwater protection and supports the conclusion that co-placement is both protective and compliant with applicable regulatory standards.

Table 4.1 consolidates the key groundwater and seepage observations that co-placement is protective and does not change waste classification. The table highlights the deep groundwater table (70–95 ft bgs) as a primary natural protective feature, and notes that BTEX is not detected in monitoring wells, indicating no site-wide hydrocarbon plume. It also documents a localized benzene detection (12.2 µg/L) in MTSB-10 seepage, emphasizing that this is interpreted as seepage from percolation through impacted soil rather than regional groundwater impacts—therefore it does not trigger RCRA hazardous waste status for the soil. Similarly, the table summarizes a localized uranium seepage detection (0.817 mg/L) as evidence of potential mobility under certain conditions, reinforcing the need for engineered containment rather than indicating widespread aquifer contamination. Overall, Table 4.1 supports the rationale that a lined and capped disposal cell will minimize infiltration and leachate potential, thereby addressing the mechanisms that produced these localized detections.

**Table 4.1 Summary of Groundwater and Seepage Findings**

| Parameter | Finding | Regulatory Significance |
|---|---|---|
| Depth to groundwater | 70–95 ft bgs | Provides natural separation from waste; supports safe placement. |
| BTEX in groundwater | Non-detect in monitoring wells | Indicates no widespread hydrocarbon plume. |
| Benzene in MTSB-10 seepage | 12.2 µg/L | Localized seepage; does not trigger hazardous waste classification. |
| Uranium in seepage | 0.817 mg/L | Indicates radiological mobility; supports need for engineered containment. |
| Leachate potential | Negligible under engineered liner | Supports suitability of co-placement in disposal cell. |

# 5.0 TECHNICAL EVALUATION OF CO-PLACEMENT

## 5.1 Physical and Geotechnical Compatibility

The physical characteristics of diesel-impacted and radiologically elevated soils at the Mt. Taylor Mine are sufficiently similar to support co-placement within the expanded disposal cell. Both soil types consist primarily of silty sands and gravels, which are non-plastic, readily compactable, and capable of achieving the density and stability required for engineered waste containment systems. These materials exhibit predictable compaction behavior, allowing them to be placed in controlled lifts that meet the structural requirements of the disposal cell design. The absence of free-phase petroleum product further enhances their suitability, as free product can interfere with compaction, reduce shear strength, and compromise the long-term stability of the waste mass. Because the diesel contamination has weathered, losing its lighter hydrocarbons, the soil acts much like clean granular material when it's excavated and placed.

Operationally, the co-placement of these soils reduces the need for segregated handling, minimizes the active footprint of waste management operations, and streamlines the overall reclamation process. Transporting both waste types to a single engineered containment area reduces equipment movement, lowers the potential for cross-contamination, and simplifies construction sequencing. Because the disposal cell expansion is located within the same operational corridor as the diesel-impacted and radiologically elevated soils, haul distances are short and operational efficiency is maximized. These factors collectively support the conclusion that the physical and geotechnical properties of the soils are compatible with co-placement and will not compromise the structural integrity of the disposal cell.

## 5.2 Geochemical Compatibility and Radionuclide Behavior

Geochemical interactions between diesel-impacted and radiologically elevated soils are not expected to present significant risks when co-placed in the engineered disposal cell. Diesel biodegradation is minimal in the cell’s dry, low-oxygen environment, reducing the likelihood of uranium or radionuclide mobilization. Uranium's mobility increases in oxidizing conditions, particularly with carbonate and dissolved organic carbon, while reducing conditions can either immobilize or remobilize it during redox cycles. Iron and manganese oxides can sorb uranium but release it when reduced (DOE, 2018; Punia et. al., 2021)). The stable geochemical setting limits both hydrocarbon breakdown and radionuclide movement, supporting long-term containment. Diesels do not influence radioactive decay, radon, or gamma emissions. The cell’s cover and liner prevent radon and contaminant migration, maintaining isolation. Together, these controls and natural soil stability confirm that co-placement does not introduce additional geochemical or radiological hazards.

### *5.2.1 Uranium Mobility in the Presence of Hydrocarbons*

The interaction between hydrocarbons and uranium-bearing soils introduces geochemical conditions that can influence uranium mobility within the vadose zone. Hydrocarbons, particularly diesel-range organics, act as electron donors that stimulate microbial activity. As microbes degrade hydrocarbons, they consume oxygen and drive the system toward reducing (low-Eh) conditions. Under these partially reducing conditions, uranium remains in its soluble U(VI) form rather than

converting to insoluble U(IV). Because the reduction process is often incomplete or spatially variable, the resulting redox gradients can enhance uranium mobility rather than immobilize it. These dynamics are especially relevant in semi-arid environments like Mt. Taylor, where infiltration events are episodic and redox conditions can fluctuate rapidly.

Hydrocarbon degradation also produces organic acids, bicarbonate, and dissolved carbon dioxide, all of which promote the formation of soluble uranyl-carbonate complexes. Complexes like $UO_2(CO_3)_2^{2-}$ and $UO_2(CO_3)_3^{4-}$ are very mobile in groundwater and stay stable over a broad range of pH levels. The increased availability of organic ligands and carbonate species enhances uranium solubility and reduces sorption to mineral surfaces. Additionally, slight decreases in pH associated with hydrocarbon biodegradation can dissolve uranium-bearing minerals or destabilize sorption sites on clays and iron oxides, further contributing to uranium mobilization.

Hydrocarbon-driven reduction of iron and manganese oxides can also release uranium previously bound to these mineral phases. As Fe(III) and Mn(IV) oxides dissolve under reducing conditions, sorbed uranium is liberated into porewater. Repeated redox cycling, which often occurs in semi-arid regions during periods of intermittent infiltration, can convert U(IV) back into U(VI), resulting in recurring surges of mobile uranium. These processes underscore the importance of engineered containment systems that minimize infiltration, stabilize redox conditions, and prevent contact between infiltrating water and contaminated soils. The expanded disposal cell design, which incorporates a low-permeability liner, radon-attenuating cover, and moisture-limiting features, effectively mitigates these geochemical mechanisms and ensures long-term isolation of uranium-bearing materials.

### *5.2.2 Hydrocarbon Geochemistry and Implications for Contaminant Behavior*

The geochemical behavior of hydrocarbons in the subsurface plays a central role in determining how diesel-impacted soils interact with radiologically elevated materials. Diesel-range organics (DRO) consist primarily of long-chain alkanes, cycloalkanes, and aromatic hydrocarbons that degrade slowly under the semi-arid climatic conditions present at the Mt. Taylor Mine. In the vadose zone, hydrocarbons undergo limited volatilization and slow microbial degradation due to low moisture availability and restricted oxygen diffusion. As a result, the diesel present at the site is highly weathered, with reduced concentrations of volatile aromatic compounds such as benzene, toluene, ethylbenzene, and xylenes (BTEX). This weathering reduces the potential for hydrocarbon migration and minimizes the likelihood of free-phase product formation, which is consistent with field observations and analytical data showing no measurable free product in any borehole.

Hydrocarbon degradation, although slow, can still influence subsurface geochemistry through the production of organic acids, carbon dioxide, and reduced species. Microbial oxidation of hydrocarbons consumes oxygen and can drive the system toward reducing conditions, particularly in microenvironments where moisture is present. These reducing conditions may promote the dissolution of iron and manganese oxides, which are common sorbents for both hydrocarbons and uranium. The dissolution of these oxides can release previously sorbed contaminants into porewater, although the extent of this process at Mt. Taylor is limited by the site's low moisture content and the weathered nature of the diesel. Additionally, the production of carbon dioxide

during hydrocarbon degradation increases bicarbonate concentrations, which can enhance the formation of uranyl-carbonate complexes and influence uranium mobility.

The physical and chemical properties of diesel-impacted soils also influence their behavior within an engineered disposal environment. Weathered hydrocarbons tend to increase soil hydrophobicity, reducing infiltration and limiting the movement of water through the waste mass. This effect can be beneficial in a disposal cell setting, as it reduces the potential for leachate generation and minimizes contact between infiltrating water and radiologically elevated soils. However, hydrocarbon-impacted soils may also exhibit slightly altered compaction characteristics, depending on moisture content and organic loading. These factors must be considered during waste placement to ensure that compaction specifications are met and that the engineered cover system performs as designed. The expanded disposal cell design accommodates these considerations by requiring controlled lift placement, moisture conditioning where necessary, and verification of compaction through construction quality assurance procedures.

Overall, the geochemical behavior of hydrocarbons at the Mt. Taylor Mine supports the conclusion that diesel-impacted soils are compatible with co-placement in the expanded disposal cell. The hydrocarbons present are weathered, immobile, and geochemically stable under site conditions. Their degradation products, while capable of influencing redox conditions and carbonate chemistry, do so in a manner that is predictable and manageable within the engineered containment system. The combination of natural geochemical stability, limited mobility, and robust engineered controls ensures that hydrocarbon-impacted soils can be safely co-managed with radiologically elevated materials without compromising long-term environmental protection.

### *5.2.3 Combined Contaminant Behavior: Hydrocarbons and Uranium*

The combined presence of hydrocarbons and uranium in the subsurface creates a complex geochemical environment in which the behavior of each contaminant influences the mobility of the other. Hydrocarbons act as electron donors that stimulate microbial activity, consuming oxygen and driving the system toward reducing conditions. These partially reducing conditions can destabilize iron and manganese oxides—key sorbents for uranium—leading to the release of previously immobilized uranium into porewater. At the same time, the degradation of hydrocarbons produces organic acids and bicarbonate, which form strong aqueous complexes with U(VI), enhancing its solubility and mobility. Thus, even though hydrocarbons at the Mt. Taylor Mine are weathered and relatively immobile, their presence can indirectly influence uranium behavior through redox modification and complexation chemistry.

The interaction between hydrocarbons and uranium is further complicated by the semi-arid climatic conditions at the site, which promote episodic infiltration and redox cycling. During wet periods, oxygenated water infiltrates the vadose zone, oxidizing U(IV) to mobile U(VI) and potentially re-mobilizing uranium that had been temporarily immobilized under reducing conditions. During dry periods, microbial degradation of hydrocarbons re-establishes reducing microenvironments, altering the stability of uranium-bearing minerals and sorption sites. These redox oscillations can create repeated pulses of uranium mobility, particularly in zones where hydrocarbons and uranium co-occur at low to moderate concentrations. Although the diesel

hotspot does not overlap with radiological hotspots at Mt. Taylor, the areas where both contaminants occur at low levels may still experience these geochemical interactions.

Despite these potential interactions, the engineered design of the expanded disposal cell effectively mitigates the conditions that promote uranium mobilization in the presence of hydrocarbons. The low-permeability liner and radon-attenuating cover limit infiltration, reducing the likelihood of redox cycling and minimizing contact between infiltrating water and contaminated soils. The engineered cover also maintains stable moisture and oxygen conditions, suppressing microbial activity and slowing hydrocarbon degradation. By isolating the waste mass from climatic fluctuations and controlling the geochemical environment within the cell, the disposal system prevents the formation of conditions that would otherwise enhance uranium mobility. As a result, the combined presence of hydrocarbons and uranium does not pose a long-term risk when managed within the engineered containment system.

**Table 5.1 Hydrocarbon Geochemical Processes Relevant to Uranium Mobility**

| Hydrocarbon Process | Geochemical Mechanism | Effect on Uranium Mobility |
|---|---|---|
| **Microbial degradation of hydrocarbons** | Consumes oxygen, lowers redox potential (Eh) | Maintains uranium in soluble U(VI) form during partial reduction |
| **Production of organic acids** | Generates acetate, lactate, citrate | Forms soluble U-organic complexes; increases mobility |
| **$CO_2$ generation and bicarbonate increase** | Hydrocarbon oxidation produces $CO_2 \rightarrow HCO_3^-$ | Promotes uranyl-carbonate complexes (highly mobile) |
| **Iron and manganese reduction** | Dissolves Fe/Mn oxides | Releases sorbed uranium into porewater |
| **Hydrophobic soil behavior** | Reduced infiltration through hydrocarbon-coated grains | Limits water movement but can create perched microenvironments |
| **pH modification** | Slight acidification from organic acids | Dissolves uranium-bearing minerals; destabilizes sorption |
| **Redox cycling** | Alternating wet/dry conditions | Re-oxidizes U(IV) to mobile U(VI); repeated mobilization pulses |

## 5.3 Hydrocarbon Performance and Liner Integrity

The behavior of diesel within the disposal cell environment is consistent with long-term containment objectives. Under a low-permeability engineered cover, hydrocarbon vapors are negligible, and any residual odors dissipate rapidly once the soils are buried. Research and site-specific evaluations indicate that weathered diesel concentrations at the levels found at Mt. Taylor—up to approximately 1.17% by weight—do not compromise the integrity of high-density polyethylene (HDPE) liners. HDPE is resistant to diesel permeation at concentrations far higher than those present at the site, and the absence of free-phase product further reduces the potential for chemical stress on the liner. This ensures that the liner will maintain its performance over the long-term design life of the disposal cell.

**Table 5.2 Technical Evaluation of Hydrocarbon-Impacted Soil with Radionuclide Waste**

| Impact Category | Technical Consideration | Potential Impact & Integration Issues |
|---|---|---|
| **Geochemical Integration** | **Redox Potential Shifts** | Hydrocarbon degradation consumes oxygen and increases biological activity, which can shift subsurface geochemistry to reducing conditions. This may convert uranium between different oxidation states, potentially altering its stability. |
| **Geochemical Integration** | **Complexation and Solubility** | Organic acids and ligands generated during the biodegradation of diesel can complex with uranium, significantly increasing its solubility and mobility within the cell. |
| **Geochemical Integration** | **Carbonate Equilibria** | Enhanced production of $CO_2$ from hydrocarbon degradation can impact carbonate equilibria, further influencing the mobility of uranium. |
| **Physical Stability** | **Slope and Structural Stability** | Hydrocarbon-impacted soils often exhibit lower shear strength, higher compressibility, and variable moisture content compared to standard mine waste. This can compromise the overall stability of the disposal cell and affect settlement patterns. |
| **Physical Stability** | **Cover System Integrity** | Differential settlement caused by the higher compressibility of oily soils can lead to cracking or failure of the engineered low-permeability cover. |
| **Liner Compatibility** | **Chemical Stress on HDPE** | While weathered diesel at observed concentrations (up to 1.17% by weight) generally does not compromise HDPE, free-phase product or high concentrations could subject the liner to chemical stress or permeation. |
| **Hydrologic Performance** | **Infiltration and Leachate** | Hydrocarbon degradation may alter soil porosity or hydrophobicity. If not tightly compacted, these soils could facilitate moisture pathways that mobilize radionuclides. |
| **Regulatory & Stakeholder** | **Dual Framework Compliance** | Co-placement requires navigating dual standards: NMED Soil Screening Levels for hydrocarbons and NRC/40 CFR 192 for radionuclides. Stakeholders may express concerns regarding the perceived risks of "mixing" these waste streams. |

Tables 5.2 and 5.3 collectively indicate that co-placement is technically achievable, provided that the disposal cell is designed and managed to effectively control key interaction mechanisms. Table 5.2 outlines primary integration risk categories, including geochemical effects (such as redox shifts, organic acid/ligand complexation, and carbonate equilibria that may impact uranium mobility), concerns regarding physical stability (including reduced shear strength, increased compressibility, differential settlement, and potential effects on cover integrity), liner

compatibility (noting that weathered diesel at observed levels typically does not damage HDPE in the absence of free product), hydrologic performance (highlighting the need for sufficient compaction to avoid preferential moisture pathways and leachate production), and regulatory/stakeholder considerations related to managing dual standards within a single unit. Table 5.3 shows that the site's compactable silty sands and gravel are suitable, with no free product detected. Diesel is stable and weathered and does not affect radon or gamma shielding. Furthermore, the HDPE liner and engineered cover are compatible with both waste types, and operational efficiencies support the consolidation of waste into a single engineered unit.

From an engineering perspective, co-placement is the most efficient and technically defensible approach. Segregating diesel-impacted soils from radiologically elevated soils would require the construction of additional disposal units, increasing the long-term stewardship burden without providing measurable environmental benefits. By consolidating both waste streams into a single engineered containment system, RGR can optimize the performance of the radon-attenuating cover, minimize the number of units requiring monitoring, and reduce the overall footprint of waste management infrastructure. This integrated approach aligns with best practices for mine reclamation and long-term environmental stewardship.

To manage environmental and geotechnical risks in the expanded disposal cell, four main engineering controls are advised: maintain low-permeability, oxygen-limited conditions via compaction and moisture; blend hydrocarbon-impacted soil with granular material for stability; use a durable, vegetated cover to reduce infiltration and volatilization; and monitor groundwater for contaminants and settlement. These steps promote consistent waste properties, limit contaminant spread and ensure long-term compliance.

**Table 5.3 Summary of Technical Compatibility Factors**

| Compatibility Area | Findings | Implications for Co-Placement |
|---|---|---|
| Physical properties | Silty sands and gravels; compactable; no free product | Suitable for stable placement in engineered lifts |
| Geochemical behavior | Minimal hydrocarbon degradation; limited redox cycling | Low potential for radionuclide mobilization |
| Radiological performance | Diesel does not affect radon or gamma emissions | Compatible with radon-attenuating cover |
| Liner compatibility | Weathered diesel does not compromise HDPE | Supports long-term containment integrity |
| Operational efficiency | Reduced handling and transport distances | Supports streamlined reclamation |

# 6.0 RISK AND COMPLIANCE EVALUATION

## 6.1 Human Health and Air Pathways

The evaluation of human health risks associated with co-placement of diesel-impacted and radiologically elevated soils focuses on potential exposure pathways during both active construction and long-term post-closure conditions. Once the soils are placed within the expanded disposal cell and covered with the engineered cap, direct exposure pathways—such as incidental ingestion, dermal contact, or inhalation of particulates—are effectively eliminated. The cover system is specifically designed to provide radon attenuation, ensuring that radon flux remains below regulatory thresholds established under EPA 40 CFR 192. Because diesel-impacted soils at the site contain weathered hydrocarbons with negligible vapor pressure, the potential for hydrocarbon vapor emissions is extremely low. This further reduces the likelihood of inhalation risks, even during the active placement phase.

Air pathway risks are also mitigated through standard operational controls during excavation, transport, and placement of the soils. Dust suppression measures, such as water application and controlled equipment movement, minimize the generation of airborne particulates. Air monitoring during construction ensures that worker exposures remain within occupational safety limits. Once the engineered cover is installed, windblown dust is no longer a concern, and the site transitions into a long-term stewardship phase where institutional controls prevent disturbance of the capped waste. Collectively, these measures ensure that co-placement does not introduce unacceptable human health risks and remains consistent with regulatory expectations for mine reclamation and closure.

## 6.2 Groundwater Protection and Long-Term Environmental Risk

Groundwater protection is a central component of the risk evaluation for the expanded disposal cell. Section 4 shows that the deep groundwater table, 70 to 95 feet below ground, acts as a significant natural barrier between waste and the aquifer. The engineered design of the disposal cell further enhances this protection by incorporating a low-permeability liner, drainage layer, and radon-attenuating cover. These features minimize infiltration, prevent leachate generation, and ensure that contaminants remain isolated from groundwater over the long term. The absence of widespread BTEX or TPH detections in the groundwater monitoring network supports the conclusion that hydrocarbon impacts have remained confined to the vadose zone since their discovery.

Long-term environmental risks are further mitigated by the consolidation of diesel-impacted and radiologically elevated soils into a single engineered containment system. This approach reduces the number of potential contaminant sources across the site and eliminates the conditions that contributed to localized seepage exceedances, such as the benzene detection in borehole MTSB-10. By removing impacted soils from unlined areas and placing them in a lined, capped cell, RGR ensures that future infiltration events cannot mobilize contaminants. The long-term monitoring program required under NMED DP-61 and MMD Permit C1002RE provides ongoing verification of groundwater protection, ensuring that any unexpected changes in groundwater quality are promptly identified and addressed.

## 6.3 Regulatory Compliance and Institutional Controls

Compliance with state and federal regulatory requirements is a critical component of the risk evaluation. The co-placement of diesel-impacted and radiologically elevated soils is consistent with the regulatory framework governing both waste types. Diesel-impacted soils at the site do not meet the criteria for RCRA hazardous waste, and radiologically elevated soils require engineered containment regardless of hydrocarbon content. The expanded disposal cell is designed to meet the requirements of EPA 40 CFR 192, NRC Appendix A, and NMED DP-61, ensuring that radon flux, infiltration, and long-term stability criteria are satisfied. Because mixed-waste classification is not triggered, the disposal cell does not require dual regulatory oversight, simplifying compliance and long-term management.

Institutional controls play a key role in ensuring long-term protection of human health and the environment. These controls include land-use restrictions, maintenance of the engineered cover, periodic inspections, and groundwater monitoring. The consolidation of waste into a single engineered unit reduces the number of areas requiring institutional controls and simplifies long-term stewardship. Documentation of waste placement, compaction records, and confirmation sampling results will be maintained to support regulatory review and eventual site release. This integrated compliance framework ensures that the co-placement strategy remains protective, verifiable, and aligned with the long-term reclamation objectives for the Mt. Taylor Mine. Table 6.1 summarizes the risk and compliance factors.

The co-placement strategy meets regulatory requirements and boosts transparency and stakeholder trust. By following clear standards and keeping detailed records, the team shows commitment to environmental and regulatory goals. Regular engagement with agencies and the public builds confidence in the management plan. These actions support approval, site closure, and address concerns about waste streams, ensuring the project aligns with community expectations and best mine reclamation practices.

**Table 6.1 Summary of Risk and Compliance Evaluation**

| Risk Area | Key Findings | Regulatory Implications |
|---|---|---|
| Human health | Exposure pathways eliminated by engineered cover | Meets EPA and NMED health-based standards |
| Air pathways | Negligible hydrocarbons vapor: radon controlled | Complies with 40 CFR 192 radon limits |
| Groundwater | Deep groundwater table; engineered liner prevents leachate | Supports DP-61 groundwater protection |
| Environmental risk | Consolidation reduces contaminant sources | Enhances long-term site stability |
| Regulatory compliance | No mixed-waste criteria triggered | Simplifies permitting and oversight |

# 7.0 DETERMINATION OF SUITABILITY FOR PLACEMENT

## 7.1 Suitability Findings

The comprehensive evaluation of hydrocarbon impacts, radiological conditions, groundwater protection, engineering design, and regulatory criteria demonstrates that diesel-impacted soils containing radiologically elevated materials are suitable for placement within the expanded disposal cell at the Mt. Taylor Mine. The technical analyses confirm that there are no physical, geotechnical, or radiological barriers to co-placement. Diesel-impacted soils exhibit stable physical properties, lack free-phase product, and contain weathered hydrocarbons that do not compromise compaction or liner integrity. Radiologically elevated soils, which represent the primary driver for engineered containment, are already designated for controlled disposal within the expanded cell. The co-location of low-level diesel in some radiological areas does not alter the classification or behavior of the soils and does not introduce new risks.

From a regulatory standpoint, the evaluation confirms that no soil mass at the site meets the dual criteria required for mixed-waste classification under the New Mexico Hazardous Waste Act or RCRA. Diesel-impacted soils are not hazardous waste, and radiologically elevated soils do not coincide with elevated diesel concentrations in a manner that would trigger mixed-waste management. This determination simplifies the regulatory pathway and supports the use of a single engineered containment system. The risk assessment further demonstrates that co-placement reduces long-term environmental risk by removing impacted soils from unlined areas and isolating them within a lined, capped disposal cell designed to meet federal and state performance standards.

## 7.2 Basis of Determination

The determination of suitability is grounded in a multi-disciplinary evaluation that integrates site characterization data, regulatory requirements, engineering design criteria, and long-term environmental protection considerations. Hydrocarbon impacts are limited in extent, well-defined, and geochemically stable. Radiological impacts are more widespread but are already slated for engineered containment. The spatial analysis confirms that the diesel hotspot does not overlap with radiological hotspots, and areas where both contaminants occur contain diesel at concentrations far below regulatory thresholds. This spatial separation is a key factor in determining that mixed-waste criteria are not met and that co-placement is permissible.

Engineering evaluations confirm that the expanded disposal cell is designed to accommodate both waste types without compromising performance. The low-permeability liner, radon-attenuating cover, and infiltration controls ensure that contaminants remain isolated from groundwater and the surrounding environment. The geochemical environment within the cell, which is characterized by low moisture, limited oxygen, and minimal redox cycle, further reduces the potential for hydrocarbon degradation or radionuclide mobilization. Collectively, these findings support the conclusion that co-placement is technically feasible, environmentally protective, and fully compliant with applicable regulatory requirements.

The key determination factors supporting co-placement include: (1) the absence of hazardous waste characteristics in diesel-impacted soils; (2) the spatial separation between diesel hotspots and radiological hotspots; (3) the engineered design of the disposal cell, which meets or exceeds

federal and state performance standards; (4) the deep water table and stable hydrogeologic conditions that limit contaminant mobility; and (5) the regulatory framework, which does not classify the soils as mixed waste. Table 7-1 consolidates these factors and demonstrates that the proposed co-placement approach aligns with all applicable regulatory criteria. Collectively, these findings provide a clear, defensible basis for assessing co-placement is appropriate and protective. Table 7.1 indicates that hydrocarbons contamination is local, weathered, and lacks free product, and radiological contamination is the primary driver for engineered containment and justifies the use of lined, and capped cell. The table highlights that the engineering design (liner and cover) is compatible with both waste types and that groundwater protection is robust due to the deep groundwater table and negligible leachate potential under the engineered system. Finally, Table 7.1 ties these findings to full regulatory compliance (DP-61, C1002RE, and 40 CFR 192), supporting the overall suitability determination.

In addition to the technical and regulatory assessments, ongoing monitoring and adaptive management strategies are proposed to ensure continued compliance and protection of environmental resources. Periodic sampling of groundwater and soil, combined with robust data tracking, will allow for early detection of any unexpected changes in contaminant behavior or migration. The integrated approach also includes contingency protocols for potential remedial actions, should future site conditions warrant intervention. By establishing clear operational guidelines and regular review processes, the placement strategy remains responsive to evolving regulatory standards and scientific advancements. This proactive framework not only reinforces the safety and reliability of the disposal cell but also demonstrates a commitment to transparency and stakeholder engagement throughout the project lifecycle.

**Table 7.1 Summary of Key Determination Factors**

| Evaluation Area | Key Findings | Conclusion |
|---|---|---|
| Hydrocarbon impacts | Localized; weathered; no free product | Suitable for controlled disposal |
| Radiological impacts | Widespread; exceed investigation levels | Require engineered containment |
| Spatial overlap | No overlap of elevated diesel and elevated Ra-226 | Mixed-waste criteria not triggered |
| Engineering design | Liner and cover compatible with both waste types | Supports co-placement |
| Groundwater protection | Deep water table; negligible leachate potential | Protective of aquifer |
| Regulatory compliance | Meets DP-61, C1002RE, 40 CFR 192 | Fully compliant |

# 8.0 IMPLEMENTATION CONDITIONS

## 8.1 Engineering and Operational Requirements for Placement

The successful implementation of co-placement within the expanded disposal cell requires adherence to specific engineering and operational conditions designed to ensure long-term stability and regulatory compliance. First, the disposal cell must incorporate a compliant low-permeability liner system capable of isolating both diesel-impacted and radiologically elevated soils from the surrounding environment. This liner must meet or exceed the performance standards established under NMED DP-61 and EPA 40 CFR 192, including requirements for hydraulic conductivity, thickness, and resistance to chemical degradation. The radon-attenuating cover must be constructed to specifications that ensure long-term control of radon flux, erosion resistance, and moisture infiltration. These engineered components form the foundation of the containment system and must be installed under rigorous quality assurance protocols.

Operationally, the placement of mixed soil must occur in controlled lifts that achieve the compaction standards specified in the engineering design. Proper compaction is essential to maintaining the structural integrity of the waste mass, preventing differential settlement, and ensuring the long-term performance of the cover system. During excavation and transport, soils must be handled in a manner that minimizes dust generation, prevents cross-contamination, and maintains clear separation between waste destined for the disposal cell and materials intended for reuse or reclamation. Equipment operators must follow established haul routes and placement procedures to maintain operational efficiency and environmental protection. These engineering and operational requirements collectively ensure that co-placement is executed safely and in accordance with regulatory expectations.

In addition, robust documentation and verification practices are essential throughout the placement process. Detailed records of liner installation, cover construction, and soil placement must be maintained to demonstrate compliance with regulatory standards and engineering specifications. This includes tracking the source and characteristics of all waste materials, documenting compaction testing results, and recording any corrective actions taken during construction. Regular inspections and third-party quality assurance reviews should be conducted to confirm that all engineered barriers and operational controls are functioning as intended. By maintaining comprehensive documentation and proactive oversight, project stakeholders can ensure that the disposal cell provides reliable containment and meets both environmental and regulatory objectives for the long term.

## 8.2 Confirmation Sampling and Waste Acceptance Criteria

To ensure that only appropriate materials are placed within the expanded disposal cell, confirmation sampling must be conducted during excavation to verify that no free-phase petroleum product is present in the diesel-impacted soils. Free products pose a risk to liner integrity and can compromise compaction, making its exclusion essential. Confirmation sampling should include visual inspection, field screening, and laboratory analysis of representative samples. Analytical parameters should include TPH-DRO, BTEX, and any additional constituents identified during site characterization. Soil exceeding the established waste acceptance criteria must be segregated and evaluated for alternative management options.

Radiologically elevated soils must also be verified through gamma screening and laboratory analysis to ensure that they meet the radiological waste acceptance criteria for the disposal cell. These criteria are based on the design assumptions for radon attenuation and long-term radiological stability. Documentation of all confirmation sampling results must be maintained as part of the project record and made available for regulatory review. This documentation provides assurance that the waste placed in the disposal cell meets the design specifications and regulatory requirements, supporting long-term compliance and environmental protection.

## 8.3 Long-Term Monitoring and Stewardship Requirements

Long-term monitoring is a critical component of the disposal cell's performance and is required under NMED DP-61 and MMD Permit C1002RE. Groundwater monitoring wells located around the disposal cell must be sampled at regular intervals to verify that no leachate is migrating from the waste mass. Analytical parameters should include petroleum hydrocarbons (TPH/BTEX) and radiological constituents (uranium and radium isotopes). Monitoring results must be evaluated for trends, exceedances, and any indications of liner or cover system failure. If anomalies are detected, corrective actions must be implemented promptly to maintain regulatory compliance and protect groundwater resources.

In addition to groundwater monitoring, the physical performance of the disposal cell must be evaluated through periodic inspections of the cover system, drainage features, and erosion controls. Inspections should assess vegetation establishment, settlement, cracking, and stormwater management. Any deficiencies must be addressed through maintenance activities such as regrading, reseeding, or repair of drainage structures. Institutional controls, including land-use restrictions and access limitations, must remain in place to prevent disturbance of the capped waste. These long-term stewardship requirements ensure that the disposal cell continues to function as designed and remains protective of human health and the environment throughout its operational life and beyond.

Table 8.1 presents the critical requirements for the successful co-placement of diesel-impacted soils within the expanded disposal cell, emphasizing both regulatory compliance and long-term stability. These requirements include ensuring containment integrity through verification of the foundation and liner system, such as the installation of a 40-mil HDPE liner and confirmation of an underlying clay layer to prevent contaminant migration. Geochemical control is achieved by maintaining an oxygen-limited, low-permeability environment via appropriate compaction, which reduces the risk of uranium and Ra-226 mobilization. Geotechnical reliability is addressed by strategically blending or layering compressible diesel-impacted soils with granular waste rock to minimize settlement and protect the cover system. Placement depth controls, notably the "5/15 rule," manage material distribution, while a multi-layer engineered cap limits infiltration and volatilization. Fluid management is assured through lined sumps and berms. Verification and stewardship are maintained with confirmation sampling, ongoing groundwater monitoring for TPH/BTEX and radionuclides, regular physical inspections, and enforcement of institutional controls, collectively ensuring the disposal cell's continued protection of human health and the environment.

**Table 8.1 Summary of Key Implementation Requirements**

| Category | Requirement | Technical Objective & Justification |
|---|---|---|
| Foundation & Liner | Liner Integrity & Clay Layer Verification | Ensure the expanded footprint utilizes min. a 40-mil HDPE liner and confirms the presence of an underlying clay liner through test pits to prevent downward migration of contaminants. |
| Geochemical Control | Oxygen-Limited / Low-Permeability Environment | Maintain reducing conditions through high compaction to prevent the mobilization of Uranium and Radium-226. |
| Waste Conditioning | Strategic Blending & Layering | Blend diesel-impacted soils (high compressibility) with dryer, granular waste rock to ensure geotechnical stability and prevent uneven settlement of the cover system. |
| Placement Depth | Subsurface Isolation (The "5/15" Rule) | Place soils with Ra-226 concentrations exceeding 15 pCi/g at depths greater than 15 cm (6 inches) below the final surface to meet federal decommissioning standards. |
| Cover System | Multi-Layer Engineered Cap | Construct a cap with low-permeability layers, erosion-resistant armoring, and vegetative stabilization to minimize infiltration and prevent the volatilization of hydrocarbons. |
| Fluid Management | Lined Sump & Runoff Containment | Install dedicated sump and perimeter berms (e.g., 2-foot interior berms) to collect and evacuate any stockpile runoff or seepage for evaporation. |
| Infrastructure | Source Removal (Piping & Buildings) | Remove, rinse, and dispose of legacy diesel piping within the cell; demolish existing buildings to allow for the full lateral excavation of the hydrocarbon source zone. |
| Verification | Confirmation Sampling (VSP) | Utilize Visual Sample Plan (VSP) software to statistically verify that the floor and sidewalls of the excavation meet the TPH cleanup goal of 3,000 mg/kg. |
| Groundwater monitoring | Regular sampling for TPH/BTEX and radionuclides | Verify containment and detect anomalies |
| Physical inspections | Evaluate cover, drainage, erosion, and settlement | Maintain long-term performance |
| Institutional controls | Land-use restrictions; access limitations | Prevent disturbance of capped waste |

# 9.0 CONCLUSIONS AND RECOMMENDATIONS

## 9.1 Conclusions

The comprehensive evaluation of the Mt. Taylor Mine confirms that co-placement of diesel-impacted and radiologically elevated soils within the expanded on-site disposal cell is appropriate and fully compliant with regulatory standards. Multiple lines of evidence, including detailed contaminant characterization, assessment of hydrogeologic conditions, engineering design review, and adherence to regulatory criteria, support this conclusion. Diesel-impacted soils at the site fall outside the scope of hazardous waste as defined by the RCRA. These soils do not qualify as listed wastes and do not display hazardous characteristics such as ignitability, corrosivity, reactivity, or toxicity. Benzene concentrations in the soil remain well below the thresholds that would trigger TCLP exceedances, and isolated benzene detections in seepage do not affect the overall classification of the solid waste.

Radiologically elevated soils, while requiring engineered containment, do not overlap with areas of elevated diesel in a manner that would necessitate a mixed-waste classification under the New Mexico Hazardous Waste Act. Spatial analysis demonstrates that the diesel-impacted area remains geographically separate from radiological hotspots, and zones where both contaminants are present contain diesel at concentrations well below regulatory thresholds. Because mixed-waste classification requires the simultaneous presence of both radioactive material and RCRA hazardous waste in the same soil mass, and neither condition exists at this site. Thus, the Mt. Taylor Mine does not contain mixed waste. This regulatory finding streamlines the permitting process and authorizes the use of a single, engineered containment system for both waste types.

## 9.2 Recommendations

Based on the technical, regulatory, and environmental analyses provided in this report, it is recommended that Rio Grande Resources (RGR) move forward with co-placing diesel-impacted and radiologically elevated soils within the expanded disposal cell at Mt. Taylor Mine. This strategy offers a comprehensive, efficient, and protective approach to managing legacy site contamination. The engineered disposal cell uses a liner with low permeability, a cover that reduces radon, and thorough long-term monitoring to keep contaminants contained and protect against future exposure risks. Co-placement of these materials into a single containment structure reduces the number of separate waste management units, lessens long-term stewardship demands, and bolsters the stability and sustainability of the reclamation landscape. To ensure proper implementation, RGR should update all permit documentation under NMED DP-61 and MMD Permit C1002RE to clearly authorize the inclusion of non-hazardous petroleum-impacted soils in the radiological cell. Maintaining thorough records—including waste acceptance criteria, confirmation sampling, compaction data, and construction quality assurance—will facilitate regulatory oversight and eventual site closure. Provided RGR adheres to the implementation requirements detailed in Section 8, this integrated approach remains protective, compliant, and consistent with best practices for mine reclamation. There is no technical, regulatory, or risk-based obstacles to this remedy, making it the most practical and effective solution for long-term closure at Mt. Taylor Mine.

## REFERENCES

AVM Environmental Services. 2023. Mine Compound Hydrocarbon and Radiological Characterization Summary. Prepared for Rio Grande Resources, Grants, NM.

AVM Environmental Services. 2025. North Controlled Area Radiological Characterization Report. Prepared for Rio Grande Resources, Grants, NM.

Department of Energy (DOE). 2018. Uranium Geochemistry in Groundwater and How to Communicate These Concepts to Laypeople. Office of Legacy Management. Presented at the Long-Term Stewardship Conference, Grand Junction, CO.

Ensero Solutions. 2021. Diesel Release Investigation and Soil Characterization Report. Prepared for Rio Grande Resources, Grants, NM.

New Mexico Environment Department (NMED). 2020. Soil Screening Guidance for Petroleum Hydrocarbons. Santa Fe, NM.

New Mexico Environment Department (NMED). 2024. Discharge Permit DP-61: Mt. Taylor Mine. Santa Fe, NM.

New Mexico Mining and Minerals Division (MMD). 2024. Permit C1002RE: Mt. Taylor Mine Reclamation Requirements. Santa Fe, NM.

Punia, A., Bharti, R. & Kumar, P. 2021. Hydrogeochemical Processes Governing Uranium Mobility: Inferences from the Anthropogenically Disturbed, Semi-arid Region of India. Arch Environ Contam Toxicol 81, 386–396 (2021). https://doi.org/10.1007/s00244-021-00879-3

Rio Grande Resources Corporation. (2021). Diesel Release Investigation Report of Findings: Mt. Taylor Mine. Ensero Solutions.


Rio Grande Resources Corporation. (2021). Diesel Release Corrective Action Plan: Mt. Taylor Mine. Ensero Solutions.


Rio Grande Resources Corporation. (2023). Mine Compound Diesel Investigation Report. AVM Environmental Services, Inc.

U.S. Environmental Protection Agency (EPA). 1983. 40 CFR 192: Health and Environmental Protection Standards for Uranium and Thorium Mill Tailings. Washington, DC.

U.S. Nuclear Regulatory Commission (NRC). 2020. 10 CFR Part 40, Appendix A: Criteria Relating to the Operation of Uranium Mills and the Disposition of Tailings or Wastes. Washington, DC.

# FIGURES








T:\111360 Mt. Taylor\Diesel Placement Figures.dwg SAVED:3/24/26 PRINTED:3/24/26

Project No. 111360

March 2026

Engineering Analytics, Inc.
Now Part of MacKay Sposito

**FIGURE 1.1**
**SITE LOCATION MAP**
**MT. TAYLOR MINE**





GENERAL NOTES:

G.1 BASE MAP ADAPTED FROM CIBOLA FOREST SERVICE MAP.

G.2 THE PERMIT AREA INCLUDES A RIGHT-OF-WAY ALONG THE TREATED WATER DISCHARGE PIPELINE. PIPELINE WAS REMOVED IN 2025.

G.3 THE PERMIT AREA INCLUDES A 50' WIDE CORRIDOR ALONG THE ACCESS ROAD FROM HIGHWAY 605 TO THE MINE SITE.




MINE UNITS AND OTHER AREAS:

| | | | | | |
|---|---|---|---|---|---|
| 1 | MINE WATER TREATMENT AREA | 7 | BORROW AREA "B" | 13 | CHILLER BENCH AREA |
| 2 | ORE PAD | 8 | SOUTH STORM WATER POND | 14 | SERVICE AND SUPPORT AREA |
| 3 | ORE PAD RUNOFF RETENTION POND | 9 | EXISTING WASTE ROCK PILE/ DISPOSAL AREA | 15 | OLD ORE LOADING AREA |
| 4 | NORTH DIVERSION CHANNEL | 10 | DISPOSAL CELL EXPANSION AREA | 16 | MINE SHAFTS |
| 5 | BORROW AREA "A" | 11 | SOUTH DIVERSION CHANNEL | 17 | BORROW AREA "C" |
| 6 | MINE ACCESS ROAD | 12 | COMPRESSOR BENCH AREA | 18 | WINDBLOWN AREA |

LEGEND:

- MINE SITE AREA
- SECTION 24 BOUNDARY
- ROADWAY
- FENCE
- EXISTING TOPOGRAPHY
- DRAINAGE PATHWAYS
- MINE BUILDINGS (PRIOR TO REMOVAL ACTIVITIES)

GENERAL NOTES:

G.1 THE MINE PERMIT AREA INCLUDES THE RIGHT OF WAY ALONG THE TREATED WATER DISCHARGE PIPELINE AND A 50' WIDE CORRIDOR FOR AN ACCESS ROAD (SEE FIGURE 1-3).

G.2 AFFECTED AREAS INCLUDE BUT ARE NOT LIMITED TO BORROW AREA "B", BORROW AREA "C", AND WINDBLOWN AREA. EVALUATION OF OTHER POSSIBLE AFFECTED AREAS IS ONGOING.

G.3 THIS DRAWING SHOWS THE SITE CONDITIONS AS OF JULY 2025. SEE FIGURE 1-2B AND TABLE 4.2 FOR DETAILED FACILITY DISPOSITION INFORMATION.

G.4 TOPOGRAPHY BASED ON A 2012 AERIAL SURVEY BY THOMAS R. MANN AND ASSOCIATES AND 2021 SURVEYS BY SOUTHWEST SURVEYING SOLUTIONS (S3).

NORTH

SCALE IN FEET

0 800'

T:\111360 Mt. Taylor\Site Ex Diesel.dwg SAVED: 3/24/26 PRINTED: 3/24/26

Project No. 111360


March 2026

Engineering Analytics, Inc.

**FIGURE 1.2**
**SITE LOCATION AND EXISTING CONDITIONS**
**MT. TAYLOR MINE**

- Soil Boring Location: Maximum PID field screening value <100 ppm. No BTEX/TPH soil samples were collected or analyzed
- Soil Boring Location: Maximum PID field screening value >100 ppm. TPH concentrations exceed screening levels (NMED, 2019)
- Soil Boring Location: Maximum PID field screening value <100 ppm. TPH/BTEX concentrations are below screening levels (NMED, 2019)
- Surface Soil: TPH/BTEX concentrations are below screening levels (NMED, 2019)

Acronyms and Abbreviations:
bgs = below ground surface
BTEX = benzene, toluene, ethylbenzene, xylene
CY = cubic yards
ft = feet
mg/kg = milligrams per kilogram
µg/kg = micrograms per kilogram
PID = photoionization detector
sq ft = square feet
TPH C10-C28 = Total petroleum hydrocarbons
TVH C6-C10 = total volatile hyrocarbons
2' = two US standard feet
TPH = Result >3,000 mg/kg





T:\111360 Mt. Taylor\Diesel Placement Figures.dwg SAVED:3/24/26 PRINTED:3/24/26

Project No. 111360

March 2026

Engineering Analytics, Inc.
Now Part of MacKay Sposito

**FIGURE 2.1**
**ENSERO (2021) SITE RESULTS**
**MT. TAYLOR MINE**




LEGEND:

| | |
|---|---|
| 4.4 | Radium (226) pCi/g |
| 1400 | TPH - DRO mg/kg |
| TPH | Total Petroleum Hydrocarbon |
| DRO | Diesel Range Organics |

| No. | Description | No. | Description | No. | Description |
|---|---|---|---|---|---|
| 1 | Mine Water treatment Area | 8 | South Stom Water Pond | 15 | Old Ore Loading Area |
| 2 | Ore Pad | 9 | Existing Waste Rock Pile/Disposal Area | 16 | Mine Shafts |
| 3 | Ore Pad Runoff Retention Pond | 10 | Disposal cell Expansion Area | 17 | Borrow Area "C" |
| 4 | North Diversion Channel | 11 | South Diversion Channel | 18 | Windblown Area |
| 5 | Borrow Area "A" | 12 | Compressor Bench Area | 19 | Ponds |
| 6 | Mine Access Road | 13 | Chiller Bench Area | 20 | Water tank |
| 7 | Borrow Area "B" | 14 | Service and Support Area | 21 | Undisturbed Area |

NORTH

APPROXIMATE SCALE IN FEET

0 60'

T:\111360 Mt. Taylor\Contaminant distribution.dwg SAVED: 3/31/26 PRINTED: 3/31/26

Project No. 111360

March 2026

Engineering Analytics, Inc.
Now Part of MacKay Sposito

**FIGURE 2.2**
**SPATIAL DISTRIBUTION OF CONTAMINANTS**
**MT. TAYLOR MINE**

# APPENDIX L

## December 17, 1997 USDA Letter

United States Department of Agriculture
Forest Service
Mt. Taylor Ranger District
1800 Lobo Canyon Rd.
Grants, NM 87020
(505) 287-8833
(505) 287-4924 - FAX

**File Code:** 2650

**Date:** December 17, 1997

Mr. Joe Lister
Rio Grande Resources
P.O. Box 1150
Grants, New Mexico 87020

Dear Mr. Lister,

I'm writing in response to our recent telephone conversation regarding the status of the old drill pads located on Forest Service administered lands on Mt. Taylor. A question had arisen as to whether reclamation of these pads should be done since so much time had elapsed from their creation.

As biologist for the District, my recommendation would be to leave these pads and access roads alone for reclamation purposes. Natural revegetation processes have begun to reclaim these areas. Pads located in ponderosa pine habitat are well grassed and contain seedling trees. Pads and access roads located in pinyon-juniper habitat are less vegetated in the understory, but match the surrounding area. Many have sapling trees that are well started.

While the roads and pads fragment the landscape, which is bad for some species, these leave edge effect habitat which is good for other species. As time passes however, these features are becoming less distinct and will eventually blend into the surrounding area. This is a a desired condition.

Reclamation of the areas at this point would disturb existing vegetation, set the clock back on revegetation already occurring and intensify the edge effect. None of these effects is desirable.

One recommendation could be made. Road density on Mt. Taylor is a significant problem. It is detrimental to all wildlife found there. It would be very beneficial if access roads to drill pads could be blocked. Only those roads presently being driven by vehicles would need to be blocked. Placing large boulders in a defendable place is all that would be needed. Many of these roads are not being used and wouldn't need anything.

Blocking drill pad access roads that are now being driven would also protect revegetation that was taking place or would allow natural establishment of vegetation to occur.

Thank you for the opportunity to comment on this activity. If there should be questions about the recommendations given, please contact me.

RITA R. SUMINSKI

Rita R Suminski

District Staff Biologist
Mt. Taylor Ranger District

# APPENDIX M

## Technical Memorandum: Outfall 001 Historical Summary and Planned Characterization

Engineering Analytics, Inc.
Now Part of MacKay

Fort Collins Office

1600 Specht Point Road, Suite 209, Fort Collins, CO 80525
970.488.3111 / GoMacKay.com

# *Technical Memorandum*

| | | | |
|---|---|---|---|
| **To:** | Mr. Jeff Schoenbacher | **From:** | Melissa Meyer, P.E. |
| **Company:** | Rio Grande Resources Corporation | **Date:** | August 26, 2026 |
| **EA No.:** | P02601.367 | | |
| **Re:** | Outfall 001 Historical Summary and Planned Characterization. | | |
| **Cc:** | Kevin Raabe, RGR President<br>Anita Wilcox, MTM Site Supervisor | | |

## 1.0 INTRODUCTION

This technical memorandum summarizes the historical investigations completed at Outfall 001, documents the progression of environmental and radiological investigations conducted to support mine closure, and distinguishes the former discharge pipeline remediation from the Outfall 001 closure activities. Additionally, it describes the planned characterization to support the completion of the Closeout/Closure Plan (CCP). This memorandum provides the technical basis for addressing the New Mexico Environment Department's (NMED) comments regarding Outfall 001 and documents the relationship between previous investigations, completed closure activities, and planned characterization efforts.

## 2.0 BACKGROUND

Historically, treated mine water from the Mt. Taylor Mine was discharged under Discharge Permit DP-61 through a 4.3-mile pipeline terminating at Outfall 001 in San Lucas Canyon. Prior to discharge, mine water was treated to remove radium and other constituents in accordance with permit requirements.

Since the cessation of mine operations, Rio Grande Resources (RGR) has completed multiple investigations to evaluate whether historical treated mine water discharges resulted in impacts to soils, sediments, groundwater, or surface water in the vicinity of Outfall 001 and within the downstream San Lucas drainage. These investigations, conducted between 2013 and 2020, included soil sampling, groundwater monitoring, surface water sampling, sediment characterization, risk evaluation, and radiological surveys completed to support mine closure activities.

The investigations completed between 2013 and 2014 generally concluded that historical treated mine water discharges had not resulted in significant impacts to downstream soils or

groundwater and that no additional characterization was warranted based on the information available at that time (RGR, 2015). As part of subsequent mine closure planning, a radiological gamma survey completed in 2020 identified localized areas of elevated gamma radiation along the former discharge pipeline, including an area at Outfall 001 (RGR, 2020). The survey was conducted as a screening investigation to identify areas requiring additional evaluation during closure planning.

The former treated mine water discharge pipeline was subsequently addressed through the pipeline abandonment project, including remediation of six isolated radiological areas identified along the pipeline corridor and documentation of those activities in the 2025 Final Status Survey (AVM, 2025). While the pipeline abandonment project addressed the designated pipeline corridor removal areas, the Outfall 001 area remained a separate closure feature requiring additional evaluation.

During review of the 2025 CCP, NMED requested clarification regarding the localized elevated gamma radiation identified at Outfall 001 and requested that the CCP either account for any remaining impacted soil requiring disposal or provide documentation demonstrating that reclamation of the Outfall 001 area is complete.

## 3.0 SUMMARY OF HISTORICAL INVESTIGATIONS

The following sections summarize the investigations in chronological order and describe how the technical understanding of Outfall 001 has evolved during mine closure planning.

### 3.1 2013 Outfall Investigation

In 2013, RGR completed a comprehensive investigation of Outfall 001 in response to NMED comments regarding the potential for historical mine water discharges to have impacted soils and groundwater in the vicinity of the outfall (RGR, 2013). The investigation included:

- Surface soil sampling upstream and downstream of the outfall;
- Soil borings and installation of monitoring wells;
- Laboratory analysis of soil uranium concentrations; and
- Groundwater sampling and laboratory analysis.

Based on the analytical results, the investigation concluded that soils near and downstream of Outfall 001 had not been contaminated by historical mine water discharge. Groundwater samples collected from the monitoring wells also did not indicate uranium impacts attributable to historical discharge activities. Based on these findings, no additional investigations were recommended at that time.

### 3.2 2014 Downstream Soil, Surface Water, and Sediment Investigation

Following the 2013 Outfall 001 investigation, RGR conducted additional downstream investigations in 2014 to further evaluate whether historical treated mine water discharges had affected soils, surface water, or sediments within the San Lucas drainage, including the Leopoldo Diversion Dam and Laguna Polvadera impoundments (RGR, 2015). The investigation included

the collection and analysis of surface soil, sediment, and surface water samples from locations downstream of Outfall 001 to evaluate potential concentrations of uranium, selenium, and molybdenum associated with historical mine water discharges (RGR, 2015).

With the exception of one water sample collected from Laguna Polvadera that exceeded the groundwater standard for uranium, analytical results indicated that constituent concentrations in water samples, surface soils and sediments were below NMED's applicable soil screening levels. The investigation further concluded that the Laguna Polvadera impoundment is not used as a drinking water source, is not known to be hydraulically connected to an underlying aquifer and posed no unacceptable risk to human health or ecological receptors. Based on the analytical results, exposure evaluation, and risk assessment, RGR concluded that historical discharges had not resulted in significant downstream impacts requiring additional characterization.

### 3.3 2020 Radiological Survey

In 2020, RGR completed a radiological survey to support mine closure planning and evaluate radiological conditions associated with the former discharge pipeline and Outfall 001 (ERG, 2020). The survey consisted of gamma scans performed along the pipeline corridor and at selected areas, including Outfall 001. Several localized areas of elevated gamma radiation were identified, including an area at Outfall 001. The radiological survey was conducted as a screening investigation to identify areas exhibiting elevated gamma radiation during closure planning. Gamma survey measurements alone do not determine whether soils exceed the Site cleanup criterion of 6.8 pCi/g Ra-226; rather, they identify locations where additional characterization may be appropriate to determine whether remediation is necessary.

### 3.4 2024 Discharge Pipeline Abandonment Work Plan

In 2024, RGR prepared the *Discharge Pipeline Abandonment Work Plan* to support the removal of the former treated mine water discharge pipeline as part of the overall mine closure program (EA, 2024). The Work Plan identified six isolated areas of elevated gamma radiation along the former discharge pipeline that were selected for remediation during pipeline abandonment.

The Work Plan officially recognized that radiological cleanup associated with the pipeline corridor and the evaluation of the Outfall 001 area were separate components of the overall closure program. Accordingly, the proposed pipeline abandonment activities focused on removal of the former discharge pipeline and remediation of the identified pipeline corridor areas, while Outfall 001 remained a separate closure feature requiring additional evaluation.

### 3.5 2025 Pipeline Corridor Radiological Remediation and Final Status Survey

In 2025, RGR completed radiological remediation of the six isolated areas identified along the former treated mine water discharge pipeline and documented the results in the *Final Status Survey – Former Discharge Pipeline Impacted Soil/Limestone Removal Area* (AVM, 2025). Remediation activities included the excavation of impacted soil and limestone material within the identified pipeline corridor removal areas, followed by confirmatory gamma surveys and collection of confirmatory soil sampling to demonstrate compliance with the Site cleanup

criterion of 6.8 pCi/g Ra-226. The Final Status Survey concluded that the remediated pipeline corridor areas satisfied the applicable cleanup criterion and were suitable for unrestricted release.

The Final Status Survey documents remediation and verification activities completed within the designated pipeline corridor removal areas. Characterization and closure of Outfall 001 will be addressed separately as part of the overall mine closure program.

## 4.0 SUMMARY OF FINDINGS

The investigations completed between 2013 and 2025 addressed two complementary aspects of the overall mine closure program: evaluation of potential environmental impacts associated with historical treated mine water discharge and evaluation of localized radiological conditions to support mine closure.

Between 2013 and 2015, investigations evaluated whether historical treated mine water discharges had adversely affected downstream soils, groundwater, surface water, and sediment. Collectively, these investigations concluded that historical treated mine water discharge had not resulted in significant environmental impacts requiring additional characterization based on the information available at that time.

As part of subsequent mine closure planning, the 2020 radiological survey was conducted to identify localized areas of elevated gamma radiation associated with the former treated mine water discharge pipeline and Outfall 001 (ERG, 2020). As a screening investigation, the survey identified areas exhibiting elevated gamma radiation but did not independently determine whether soils exceeded the applicable Site cleanup criterion for Ra-226.

The pipeline abandonment project subsequently addressed the six identified radiological areas along the former discharge pipeline through excavation, confirmation sampling, and Final Status Surveys completed in 2025 (AVM, 2025). Those activities documented completion of remediation within the designated pipeline corridor removal areas but did not document final characterization or closure of the Outfall 001 area.

Collectively, these investigations establish that the environmental investigations evaluating historical treated mine water discharges and the radiological investigations completed to support mine closure represent complementary components of the overall closure program. The historical investigations evaluated potential impacts associated with treated mine water discharge, while the radiological investigations were conducted to support closure by identifying localized areas for additional evaluation. Accordingly, the planned characterization of Outfall 001 represents the next critical step in the closure process and is intended to provide the technical basis for determining whether additional remedial actions are necessary and for documenting final closure of the Outfall 001 area.

## 5.0 PLANNED CHARACTERIZATION

To support completion of the CCP and the final closure of Outfall 001, RGR plans to conduct additional characterization of the Outfall 001 area. The characterization is intended to evaluate

the localized elevated gamma radiation identified during the 2020 radiological screening survey (ERG, 2020) and provide the information necessary to determine whether additional remedial actions are required.

The planned characterization will be designed to:

- Evaluate the area of elevated gamma radiation identified during the 2020 radiological survey;
- Determine whether radionuclide concentrations in soil exceed the applicable Site cleanup criterion;
- Delineate the lateral and vertical extent of any impacted soil, if present;
- Estimate the volume of material requiring excavation and disposal, if necessary; and
- Provide the technical basis for documenting final closure of Outfall 001.

The results of the characterization will be documented in a technical memorandum. Based on the characterization results, a work plan will be prepared, if warranted, describing the proposed remedial approach, estimated material volumes, and confirmation activities necessary to demonstrate compliance with the applicable cleanup criteria.

## 6.0 REFERENCES

AVM Environmental Services, Inc. (AVM). 2025. *Final Status Survey, Impacted Soil/Limestone Removal Area, Former Discharge Pipeline*. Prepared for Rio Grande Resources, Inc., Mt. Taylor Mine, San Mateo, New Mexico. October 20.

Engineering Analytics, Inc. (EA). 2024. *Discharge Pipeline Abandonment Work Plan, Mt. Taylor Mine*. Prepared for Rio Grande Resources, Inc., Mt. Taylor Mine, San Mateo, New Mexico. August 19.

Environmental Restoration Group, Inc. (ERG). 2020. *Radiological survey results for discharge pipeline and soils along pipeline corridor*. Technical Memorandum to Bruce Norquist. July 6.

Rio Grande Resources, Inc. (RGR). 2013. *Application for Revision of Mine Permit No. CI002RE from Standby to Active Status and Modification of Ground Water Discharge Permit DP-61*. Prepared for Rio Grande Resources, Inc., Mt. Taylor Mine, San Mateo, New Mexico. Rev 1. November.

Rio Grande Resources, Inc. (RGR). 2015. *Report on Soil and Water Sampling and Testing Water and Sediment Impoundment Locations Downstream of Mt. Taylor Mine Water Outfall 001.* January 26.