



**State of New Mexico
General Services Department
Purchasing Division
(505) 827-0472**

Amendment No. **Two**

Date: **August 21, 2025**

To: **All Potential Bidders**

Re: Invitation to Bid Number: **50-52100-25-06151**

Department: **Energy, Minerals, and Natural Resources Department**

Title: **Madrid Stormwater and Erosion Control Project**

Opening date: **August 28, 2025**

This Amendment is issued to reflect the following change to the Bid opening date:

Extend Bid opening date from: **August 28, 2025 to: September 4, 2025**

This Amendment is also issued to reflect the following:

- 1.) **Direct all bidders to the change made in the ePro/Sciquest bid application where event #60-52100-25-06151 is being cancelled and replaced in its entirety with event #50-52100-25-06151 to correctly match the ITB identification number as originally submitted. Event #50-52100-25-06151 will be treated as a continuance of the original event and only vendors that attended either of the 2 pre-bid conferences as required and detailed in event #60-52100-25-06151 (August 4, 2025 and August 11, 2025) will be eligible to bid on this project.**
- 2.) **Questions and Answers (Attached Below)**
- 3.) **August 4 and August 11 Pre-Bid Meeting Sign-in Sheet (3 pages, Attached Below)**
- 4.) **List of potential rock quarries for use (1 page, Attached Below)**
- 5.) **Western Technologies Final Geotechnical Report (66 pages, Attached Below)**
- 6.) **Page C217 on the for-bid drawing set did not print correctly. This page was printed as a duplicate of page C219 on the published version of the bid-set for unknown reasons. Please see the attached sheet as C217 (1 page, Attached Below)**
- 7.) **The contract Time for project completion has been revised. The Contract Time for project completion shall be no later than one hundred and eighty (180) calendar days, including all Sundays, holidays, and non-workdays, after the Contractor receives a Notice to Proceed.**
- 8.) **Due to the extensive questions and second pre-bid meeting, bids are due one week later and bid opening will immediately follow. Bids will now be due September 4th, 2025 at 2:00 PM MDT.**

If you have already submitted an electronic bid, you will need to acknowledge this amendment by resubmitting your bid. Your bid has changed from 'submitted' to 'in progress' and will not be accepted if you do not acknowledge this amendment. Click the link to get started:

<https://bids.sciquest.com/apps/Router/PublicEvent?CustomerOrg=StateOfNewMexico>

All other items, terms and conditions shall remain the same.

Procurement Specialist: **James Ortega** Phone: **(505) 795-2516** Email: **james.ortega@gsd.nm.gov**

Master List of Q&As for Madrid Stormwater and Erosion Control Project ITB 50-52100-25-06151

1	Q	As contractors will be required to open NM14 to install the culvert, will Jersey Barriers and other traffic control measures be included in the bid?
	A	Yes, these should be included in the Traffic Control Plan & Implementation bid item.
2	Q	Are there contours for the disposal area?
	A	Yes, the soil disposal area will require contractors grade the area per the contours shown on Sheets C222 and C223 in the For-Bid Drawing Set.
3	Q	Will there be requirements to clean the fill dirt placed in the soil disposal area?
	A	Not in general, however, contractors should be selective when burying material containing large rocks and other debris from the arroyo.
4	Q	Will EMNRD award based on base bid, or the base bid plus alternates?
	A	Bidders must bid on all Bid Lots and all Bid Items. Failure to do so will result in rejection of the bid. The base bid includes Bid Lots 1, Bid Lots 2, Additive Alternate 1 amounts. The bid evaluation will be based on the sum of these three amounts.
5	Q	Can the contractor remove the landowner's fencing to do the channel work between NM 14 and Cave Road?
	A	Yes. The contractor can remove the landowners fence between NM14 and Cave Road. All fences must be replaced or reinstalled to match existing conditions or better.
6	Q	What are the existing water lines constructed out of?
	A	We understand that all water lines are PVC. The existing line in the arroyo includes 2" PVC near the houses, 3" PVC crossing the arroyo, and an 8" PVC for the primary fire suppression line.
7	Q	What is the process if a water line is broken?
	A	The AML Program will be in contact with Madrid Water Board and will contact the Madrid Water Operator for emergency repairs. If a waterline is broken, the contractor shall repair as instructed by the Water Operator. Make every attempt to avoid waterline breaks by verifying the position of the pipes using exploratory excavation methods ("pot holing").
8	Q	How much spoil is estimated for the project?
	A	Excess soil to be placed in the soil disposal area per the For-Bid Drawing Set is estimated to be 13,000 CY.
9	Q	Are there people who park at the lot above the ballfield? Will the town move campers out of the area?
	A	The AML will work with the Town to move people and/or consolidate campers to a corner of lot during construction.
10	Q	Are there contours for the coal gob grading?
	A	Instructions for coal gob grading can be found on pages C222 and C223 of the For-Bid Drawing Set.
11	Q	Must all excess soil be disposed at the lot above the ballfield?
	A	Yes, all excess soil is to be hauled to the soil disposal (ballfield) area and graded to match the For-Bid Drawing Set.
12	Q	Will the list of possible quarries have rock that will meet the specifications?
	A	The rock quarries provided in the Project Manual are potential sources, however it is the contractor's responsibility to determine if the produced rock will meet the specifications.
13	Q	Will there be any archaeological conflicts?
	A	No archaeological conflicts are anticipated at this time and an archaeologist will be on-site during all construction to review any potential cultural conflicts. The AML Program is actively working to complete most of the archaeological excavations prior to construction.
14	Q	Can we use fill material to build up cave road temporarily during construction?
	A	Yes, construction contractors can add fill to Cave Road to create a smooth roadway for heavy machinery/trucks.
15	Q	Can we sort rock in the arroyo?
	A	Review question 23 for further information.
16	Q	What shall we do with all the green waste?
	A	Green waste will need to be hauled offsite for disposal at an approved green-waste disposal facility.

Master List of Q&As for Madrid Stormwater and Erosion Control Project ITB 50-52100-25-06151

17	Q	Will mulch be part of the reseeding?
	A	Yes. Hydromulch and composted mulch are prescribed in both the Seeding Plan (page C227) of the For-Bid Drawing Set and in Attachment C: Technical Specifications of the Project Manual.
18	Q	What bid item should potholing for utilities go in?
	A	Include potholing in the work to be performed such as Unclassified Excavation or Major Structure Excavation and Subgrade Preparation (Abutments). No additional payment will be made.
19	Q	Will the contractor be responsible for moving the utility lines, or will the utility owners be responsible?
	A	The contractor will be responsible for moving all water utility lines as shown on the Drawings. Relocation of electrical, communications, and gas lines will be the responsibility of the utility owner.
20	Q	What are the working days and hours restrictions?
	A	Regular work hours will be limited to no earlier than 7:00 am and no later than 5:00pm, Monday through Friday unless approved by AMLP in advance. Though the project is expected to start in early January 2026, due to the extensive tourism industry in Madrid, no work will be allowed during the following holidays and events: - New Years Day - Martin Luther King Day - Memorial Day - Independence Day - Labor Day - Indigenous Peoples Day - Veterans Day - Thanksgiving Day - Friday After Thanksgiving - Presidents Day - Balloon Fiesta Week - 2025 October 4th through 12th , 2025 and October 3rd through 11th, 2026 - First and Second Saturdays of December. - No work between December 22, 2024 and January 2, 2025 - No work between December 21, 2025 and January 1, 2026. See Section 01.14.00 WORK RESTRICTIONS of Attachment C: Technical Specifications of the Project Manual for additional information.
21	Q	The construction window goes into monsoon season. Is dewatering a bid item?
	A	Dewatering is not a bid item for this project. The contractor is responsible for protecting the work shall schedule work in the arroyo to avoid construction in the arroyo during monsoon season. Controls may be necessary to prevent stormwater from damaging the work. Should flood damage occur during construction, the contractor will be financially responsible to remedy any damage.
22	Q	Has AML secured funding for both the main scope of work and the alternates?
	A	Yes, funding is in place for the main scope of work and alternates. Funding was based on the engineering cost estimate for the project.
23	Q	Can the contractor reuse rock excavated from the arroyo if it is screened and tested?
	A	No. Due to the proximity to the town of Madrid as well as the potential significant negative impacts of dust, noise and public perception, the AML Program will not allow potential contractors to screen and sort rock excavated from the arroyo. However, large rock collected from the arroyo work area may be used in the project provided it meets all of the material hardness, size and shape requirements set forth in the technical specifications. Additionally, recycled large rock may only be used for grade control structures in the arroyo north of Cave road or in the soil disposal area. Note that any rock used in the project shall be approved by the engineer for conformance with the hardness standards specified in the project manual. If rock doesn't meet the specifications then additional rock must be imported.
24	Q	If rock is screened on site, is an air quality permit required? Who will cover the cost?
	A	Please refer to question 23.

Master List of Q&As for Madrid Stormwater and Erosion Control Project ITB 50-52100-25-06151

25	Q	Is there a utility allowance bid item for broken utilities during the project? If not, what bid item should it be included in, and will AML cover the cost?
	A	There is no bid item allowance for broken utilities. As stated in the Project Manual; The Contractor shall be responsible for locating and avoiding all underground utilities at the contract work site. If damage to the utilities occurs during the contract work, the damage shall be repaired at the Contractor's expense.
26	Q	It was stated on the tour sandstone was not preferable as a boulder option. If we find a source of sandstone which meets the hardness requirements, would this stone be permitted?
	A	Section 31 of the technical specs, paragraph 3.1.4 states "Large rocks must conform to the density, hardness and wear requirements of NMDOT Section 602". That's the riprap rock DOT spec, and its hardness requirements are sufficient. If a contractor's sandstone can meet those durability requirements, then it would be suitable.
27	Q	It was mentioned a couple of times regarding Class A wire-enclosed riprap being placed at certain locations. There is no bid-items for any class A riprap. Is this item included in another bid item?
	A	No, any reference to Class A riprap is an error and should be assumed to be reference to Class B riprap for bidding purposes.
28	Q	Looking at the wage decision, it looks like it may have expired on July 11 of this year. Do you have a new or renewed wage decision?
	A	We acknowledge the wage decision is expiring. We don't plan to renew it until we are closer to a signed contract. The rates should remain the same upon renewal as long as the contract is signed by the end of 2025. If for some reason the rates did change, we would increase the compensation accordingly through a change order.
29	Q	Item 33 Boulder Channels is a Lump Sum Item and a Bid Quantity of 2. Is it the intent to pay the Contractor twice for this item of work?
	A	There are two grouted boulder channels used as grade control structures. The quantity is correct, but the unit of measure should be changed to EA, instead of LS.
30	Q	The Subgrade Preparation Column on Roadway Surfacing Schedule on Sheet G006 totals 7,307SY. The Bid Schedule has a quantity of 5,819SY. We understand that Fire House Lane, Bethlehem Road, and Ice House Road Extension are not included in this contract. If we delete these roads from the surfacing schedule the schedule totals 5,737SY which is less than the bid quantity. Could you clarify which roads on this schedule should be included in the project?
	A	On Sheet G-006, only NM-14 Culvert Crossing, Cave Road, and Bridge Street in the Surfacing Schedule are included in the Contract. The total bid quantity also includes the work in the Madrid Arroyo and Ballpark disposal area which is not itemized on G-006.
31	Q	Is the 2" of ¾" minus crushed gravel, shown on the typical roadway sections on Sheet G012, incidental to the aggregate base?
	A	Yes. As described on the Bid Form for Bid Lot 1 (Additive Alternate 1): Bridge Street Project Area.

**Madrid Stormwater Project Mandatory Pre-Bid
Meeting
August 4, 2025**

ATTENDANCE ROSTER

PLEASE PRINT LEGIBLY			
Name	Street Address City State Zip	E-Mail Address	Phone Number
SCOTTY CARL	SPARKING- CONSTRUCTION	Phyllie@SPARKING-CONSTRUCTION.NET	821-1034
SCOTTY CARL Derek Bills		d.bills@SweettConstruction.com	573-1710
Gracie Kellison AZL		mino@sipermaculture.com	505-920-8264
Mino Martinez			
Dirk Holtman		dholtman@SPEAR.DNM.com	(505) 763-3001
Joe Cuilty		joecuilty@meridiancon.net	505-872-2841
CLINT ADARCY		clintecfpadilla@cc.com	505-400-4020
Randall Camp-		mandy@SWEETTCONSTRUCTION	(575) 258-5677
Cody Runyan		Cody.runyan@reganinc.com	(505) 538-1685
Adam Robins		AdamRobinsConstruction.com	(719) 580-3110
Carl Martinez		carl@vitalgrp.net	(505) 917-4017
Luke Bailey		LBailey@TurnandCoast.com	602-558-0065
Will McFar		will@compassnm.com	505-520 9515
Flavio Vega		flavio@compassnm.com	505 300 6747
Sam Wallick		bills@brunbury-studio.com	505-859-1182
Shane Bender		julier@auvinc.net	505-272-4848

**Madrid Stormwater Project Mandatory Pre-Bid
Meeting
August 4, 2025**

ATTENDANCE ROSTER

PLEASE PRINT LEGIBLY			
Name	Street Address City State Zip	E-Mail Address	Phone Number
Andrew Bink	AML	andrew.bink@cnrd.nm.gov	505-440-7379
Matthew Penabaz	AML	matthew.penabaz@cnrd.nm.gov	505-819-1955
James Hollen	AML	james.hollen@cnrd.nm.gov	505-281-8332
Andy Bizzell	Enviroworks LLC	andy@enviroworks.biz	575-444-8858
REESE DAVIS	RAINWATCH INC.	reesee@theraincatcherinc.com	505-501-4407
Michael Carr	Santa Fe County	mcarr@santafecounty.nm.gov	505-995-9515
Leiland Murray	AML	leiland.murray@cnrd.nm.gov	505-629-9677
Ashley Kretschmer	Heridian Construction	A.Kretschmer@heridianco.net	505-712-1611
Sethre Bowden	Madrid Water	glorioelectric@gmail.com	505-475-7160
Monica Harmon	Santa Fe County	mharmon@santafecounty.nm.gov	505-992-9825
Meghan McDonald	AML	meghan.mcdonald@cnrd.nm.gov	(505) 629-9872

MADRID STORMWATER PROJECT MANDATORY PRE-BID MEETING

August 11, 2025

Attendance Roster

NO	NAME	PHONE	EMAIL	COMPANY/CONTRACTOR
1	Jesse Dumas	505-206-0568	JDumas77@gmail	Summit Operations LLC
2	Andrew Luke	505-446-7379	andrew.luke@emurd.nm.gov	AML P
3	Leland Murray	505-629-9677	Leland.Murray@emurd.nm.gov	AML P
4	Meghan McDonald	505-629-9872	meghan.mcdonald@emurd.nm.gov	NM AML
5	Matt Kingstey	505-246-4491	mkingstey@emurd.nm.gov	EnviroWorks
6	Luke Simons	719 207 5189	Luke@Kimo.com	Kimo Constructors
7	Matthew Lucero	505 362 0362	MLucero@Kimo.com	Kimo Constructors
8				
9				
10				
11				
12				
13				

Potential Sources for Large Rock and Rip Rap

Blackrock Services, Albuquerque, NM, 505-250-9085 (Beverley Maeker)

Source of large rock with high quantities, and nearby to the project site. Rock is also available in smaller rip rap sizes. Active quarry and the company can deliver. Rock appears to have sufficient hardness, but contractor would need to verify.

Robins Construction, Antonito, Colorado 719-376-2351 (Adam Robins)

Grey to black basalt, hard rock, some parts of the quarry produce flat rocks, other parts irregular shape rocks. Active quarry and the company has a fleet of rock trucks to make deliveries. In the past few years they have sold thousands of rocks to the Questa Moly Mine (Chevron), and to Taos Ski Valley.

Ribera Rocks, Ribera, NM 505-369-1956 (Jonathan Ribera)

Brown & light grey tones of metamorphized sandstone, hard, relatively flat, thickness varies. Have used this rock on 3 or 4 projects. Small operation, but has recently acquired a large acreage where more rock can be harvested.

Mesa Sandstone, Cortez, CO 970- 749-0183 (Billy Goode)

Brown mixed with white sandstone, fairly hard, nice and flat, thickness varies. This quarry mines a tall open wall of rock, and quarries with dynamite. They seem to be pretty good at producing large rocks when requested.

Caja del Rio, Santa Fe, NM @ SF County Landfill

Excavation for new landfill cells has required blasting and removal of basalt bedrock. When a new cell is excavated, a large volume of rock material is produced and piled up. A third party has (in the past) harvested rocks from this waste pile and sells them on a per-ton basis. Hard rock. Used this rock on the Santa Fe River project, but the size and shape of rock varied a lot. Need to verify current quantity of rock size and shape that could be supplied.

Rock quarry at "Levi" exit off of I-25, just north of Wagon Mound. All the rock is up on top of the mesa, just to the west of the interstate. Grey basalt, good hard rock, would need to quarry the rock out of the formation. Various contractors have made agreements with the landowner (not known who that is) to extract rocks in the past.

GEOTECHNICAL EVALUATION REPORT

MADRID STORMWATER & EROSION CONTROL IMPROVEMENT

Along NM 14

Madrid, New Mexico

WT Job No. 32-223560-0

PREPARED FOR:

State of New Mexico EMNRD

1220 South St. Francis Drive

Santa Fe, New Mexico 87505

Attn: Leeland Murray

April 25, 2024



Azupuri Kaba, PhD, PE, PMP
Geotechnical Engineer

Justin M. Heinecke, PE
Senior Geotechnical Engineer

GEOTECHNICAL

ENVIRONMENTAL

INSPECTIONS

NDT

MATERIALS

8305 Washington PL NE,
Albuquerque, NM 87113

(505) 823-4488

rma-western.com

TABLE OF CONTENTS

1.0	PURPOSE	1
2.0	PROJECT DESCRIPTION	1
3.0	SCOPE OF SERVICES.....	2
3.1	Field Exploration	2
3.1.1	Hollow Stem Auger Boring.....	2
3.1.2	Refraction Microtremor (ReMi)	3
3.2	Laboratory Analyses.....	4
3.3	Analyses and Report	4
4.0	SITE CONDITIONS.....	4
4.1	Surface	4
4.2	Subsurface.....	6
5.0	GEOTECHNICAL PROPERTIES & ANALYSIS	6
5.1	Laboratory Tests	6
5.2	Field Tests	7
6.0	RECOMMENDATIONS.....	7
6.1	General.....	7
6.2	Design Considerations	7
6.3	Retaining Wall and Drainage Structures Foundations.....	8
6.4	Tank Foundations.....	9
6.5	Stormwater Pipe Foundations	10
6.6	Lateral Design Criteria.....	10
6.7	Seismic Considerations	12
6.8	Slab Support.....	12
6.9	Drainage	13
6.10	Corrosivity to Concrete and Metal Components.....	13
7.0	EARTHWORK	18
7.1	General.....	18
7.2	Site Clearing	18
7.3	Excavation	18
7.3.1	Temporary Excavations and Slopes	19
7.4	Foundation Preparation.....	19
7.5	Slab Preparation.....	20
7.6	Pavement Preparation	20
7.7	Stormwater Pipes Foundation Preparation	21
7.8	Materials	21

7.9	Placement and Compaction.....	22
7.10	Compliance	22
8.0	PLAN REVIEW	23
9.0	ADDITIONAL SERVICES	23
10.0	LIMITATIONS	23
11.0	CLOSURE.....	24
BORING LOCATION DIAGRAM		Plate 1
APPENDIX A		
	Definition of Terminology	A-1
	Method of Classification	A-2
	Boring Log Notes	A-3
	Boring Logs.....	A-4 to A-19
APPENDIX B		
	Soil Properties	B-1 to B-12
APPENDIX C		
	Seismic Refraction Microtremor.....	C-1

**GEOTECHNICAL EVALUATION
MADRID STORMWATER & EROSION CONTROL IMPROVEMENT
ALONG NM 14
MADRID, NEW MEXICO
JOB NO. 32-223560-0**

1.0 PURPOSE

This report contains the results of our geotechnical evaluation for a proposed Madrid stormwater and erosion control improvement project in Madrid, New Mexico. The purpose of these services is to provide information and recommendations regarding:

- Subsurface conditions
- Foundation design parameters
- Lateral earth pressures
- Earthwork guidelines
- Drainage
- Groundwater
- Corrosivity (soil to concrete)
- Seismic considerations
- Excavation conditions
- Pavement

Results of the field exploration, field tests, and laboratory testing program are presented in the Appendices.

2.0 PROJECT DESCRIPTION

Based on the information provided in the request for proposal (RFP), the proposed project will consist of improvement of stormwater and erosion improvements to include road improvements, arroyo improvements and drainage structures, and general pipeline installation. We assumed that maximum wall and column loads will not exceed 3 klf and 50 kips, respectively. We anticipate no extraordinary slab-on-grade criteria, and that ground floor level will be within a few feet of existing site grade. Any off-site improvements have not been included as part of this evaluation. Should any of our information or assumptions not be correct, we should be notified.

3.0 SCOPE OF SERVICES

3.1 Field Exploration

The table below outlines WT field exploration program as outlined in the RFP.

Field Exploration Program

Boring ID	Latitude (degrees)	Longitude (degrees)	Depth (feet)	Purpose
1	35.407757	-106.149751	21.5	Retaining Wall
2	35.407279	-106.150909	21.5	Retaining Wall
3	35.400532	-106.157710	11.5	Tank
4	35.410807	-106.152358	14	Culvert
5	35.410619	-106.152089	10	Culvert
6	35.408360	-106.152897	16.5	General Geotech
7	35.407840	-106.151183	16.5	Culvert
8	35.408017	-106.151583	16.5	Culvert
9	35.403267	-106.154606	16.5	Culvert
10	35.409936	-106.152206	6.5	Roadway
11	35.407908	-106.152702	2	Roadway
12	35.407020	-106.151328	6.5	Roadway
13	35.406723	-106.151494	6.5	Roadway
14	35.406602	-106.152821	6.5	Roadway
15	35.404115	-106.153807	6.5	Roadway
16	35.403931	-106.154368	6.5	Roadway
ReMi	35.407757	-106.149751	100	Tank

3.1.1 Hollow Stem Auger Boring

Nine (9) borings were drilled to depths ranging from 16.5 to 21.5 feet below the existing site grade in the proposed retaining wall, tank, and drainage conveyance structures areas. In addition, seven (7) borings were drilled to depths of about 5 feet in the proposed roadways. The specific number, locations, and depths, of our explorations were selected by the client. They were field-adjusted based on existing site features under the constraints of surface access. The borings are at the approximate locations shown on the attached Boring Location Diagram. The boring locations shown in the Boring Location Diagram and in the table above are based on

Google Earth Pro (accessed March 5, 2024) and should be considered accurate only to the degree permitted by our data sources and implied by our measuring methods.

The drilling was conducted using CME 75 and a track-mounted for less accessible areas. The drill rigs were equipped with 7" O.D. continuous flight, hollow stem augers. Disturbed but representative samples were obtained during drilling by using the Standard Penetration Test (SPT) procedure in accordance with American Society for Testing and Materials (ASTM) D1586 during the explorations. This test and sampling method consists of driving a standard 2-inch outside-diameter, split-barrel sampler to depth 18 inches into the soil with a 140-pound hammer free-falling a height of 30 inches. Disturbed bulk samples were also obtained. Marginally disturbed samples were collected by driving a 2.5-inch inside diameter, modified California brass ring sampler (ring or R) to a depth of 12 inches from a given referenced point.

The number of blows (split-barrel and ring) for each 6-inch interval were recorded and the number of blows required to drive the sampler the final 12 inches was taken as the Standard Penetration Resistance ("N") or blow count. If a total of 50 blows was recorded within one 6-inch interval, the blow count was recorded as the number of blows for the corresponding number of inches of penetration. The resistance, or N-value, provides a measure of the relative density of granular soils or the relative consistency of cohesive soils; these values are reported on the attached boring logs.

A field log was prepared for each boring. These logs contain visual classifications of the materials encountered during drilling as well as interpolation of the subsurface conditions between samples. Final logs, included in Appendix A, represent our interpretation of the field logs and may include modifications based on laboratory observations and tests of the field samples. The final logs describe the materials encountered, their thickness, and the locations where samples were obtained.

3.1.2 Refraction Microtremor (ReMi)

A refraction micro-tremor (ReMi) survey was performed to estimate the average shear wave velocity profile at the site for assessment of the seismic site classification in accordance with the 2021 IBC. The survey was conducted at the tank area. Location of the ReMi survey line is depicted on the attached Boring Location Diagram. The results of the survey are also discussed in Section 6.5 **Seismic Considerations** of this report.

3.2 Laboratory Analyses

Laboratory analyses were performed on representative soil samples to aid in material classification and to estimate pertinent engineering properties of the on-site soils for preparation of this report. Testing was performed in general accordance with applicable standard test methods. The following tests were performed and the results are presented in Appendix B.

- Field moisture content
- In-situ soil density
- Expansion Potential
- Compression
- CBR
- Gradation
- Liquid Limit and Plasticity Index
- Water Soluble Sulfate Content
- Water Soluble Chloride Content
- pH & minimum resistivity


3.3 Analyses and Report

This geotechnical engineering report includes a description of the project, a discussion of the field and laboratory testing programs, a discussion of the subsurface conditions, and design recommendations as appropriate to its purpose. The scope of services for this project does not include, either specifically or by implication, any environmental assessment of the site, discovery of underground storage tanks or other underground structures, or identification of contaminated or hazardous materials or conditions. If there is concern about the potential for such contamination, other studies should be undertaken. We are available to discuss the scope of such studies with you.

4.0 SITE CONDITIONS

4.1 Surface

At the time of our exploration, the site was a residential. The ground surface was hilly and contained a sparse to moderate growth of grasses, shrubs, and trees. Site drainage was relatively poor, and the residential roadways were in poor condition. With the exception of NM 14, all roadways within the project site were unpaved with no gravel surfacing. Photographs of the site at the time of our exploration are provided below.



4.2 Subsurface

As presented on the Boring Logs, surface soils to depths of 15 feet consist of loose to very dense Silty SAND with Gravel and Cobbles, very stiff to hard Fat CLAY and COAL fragments. Near surface soils are of nil to high plasticity. The materials underlying the surface soils and extending to the full depth of exploration consisted of medium dense to very dense Poorly-graded SAND, very stiff to hard Lean CLAY, COAL and SHALE fragments. Auger refusal occurred at 2 to 14 feet below existing site grade. Groundwater was not encountered in any boring at the time of exploration. A detailed description of the soils encountered can be found on the boring logs in Appendix A.

5.0 GEOTECHNICAL PROPERTIES & ANALYSIS

5.1 Laboratory Tests

Laboratory test results (see Appendix B) indicate that on-site subsoils near shallow foundation level exhibit low to moderately high compressibility at existing water contents. The moderately high compressible soils are in Borings 4, 5, 7 and 9 as shown Plate B-1 & B-2. Low to high levels of additional compression occurs when the water content is increased. Moderately high to high compressible soils are present in Borings 7, and 9. It should be noted that selected borings and samples were tested. It is possible that untested samples may exhibit comparable compressibility characteristics.

Near-surface soils are of nil to high plasticity. These soils exhibit low to high expansion potential when recompacted, confined by loads approximating floor loads and saturated. Highly expansive soils were recorded in Boring 1, which consisted of Fat CLAY. CLAY or clayey soils are also present in other borings and may exhibit similar expansive potential when saturated. Slabs-on-grade supported on recompacted on-site soils will have a low to high potential for heaving if the water content of the soil increases.

CBR tests were performed on representative samples from Borings 10, 11, 12, 13, 14, 15 and 16 to determine the bearing capacity of the on-sites for support of pavement. The test was performed in accordance with ASTM D1883. The test results are presented in Appendix B.

Chemical tests were performed on representative samples in Borings 3 and 5 to determine the amount of water-soluble sulfates and chlorides. The test results indicate that the soils

in the area of Boring 3 are classify as negligibly corrosive and samples in the vicinity of Boring 5 are classified as severely corrosive to concrete according to Table 19.3.1.1 of ACI 318-19.

Minimum electrical resistivity and hydrogen ion concentration (pH) were performed on representative samples to aid in assessing, by others, the potential for corrosion of buried metals. The test results are presented in Appendix B.

5.2 Field Tests

The boring logs included in this report are indicators of subsurface conditions only at the specific location and date noted. Variations from the field conditions represented by the borings may become evident during construction. If variations appear, we should be contacted to re-evaluate our recommendations.

6.0 RECOMMENDATIONS

6.1 General

Recommendations contained in this report are based on our understanding of the project criteria described in Section 2.0 and the assumption that the soil and subsurface conditions are those disclosed by the explorations. Others may change the plans, final elevations, number and type of structures, foundation loads, and floor levels during design or construction. Substantially different subsurface conditions from those described herein may be encountered or become known. Any changes in the project criteria or subsurface conditions shall be brought to our attention in writing. This report does not encompass the effects, if any, of underlying geologic hazards or regional groundwater withdrawal and expresses no opinion regarding their effects on surface movements at the project site.

6.2 Design Considerations

The borings indicate the presence of clay soils on the site. The clay soils may expand or swell with an increase in moisture content. Slabs-on-grade and related improvements situated on expansive clay soils could be subject to relatively large movements if the foundation soils experience an increase or decrease in moisture content. In addition, densification of the soil by the passage of construction equipment may increase the expansion potential of the on-site clayey soil. As expansive soils are encountered during earthwork operations,

selective placement procedures should be implemented. Moderately to highly expansive soils should not be used as fill in the structure areas within 36 inches of the final subgrade. It should be understood that if moisture penetrates expansive soils, there could be some heave and resultant cracking/distress of the proposed structures and related improvements. Conversely, as expansive soils dry, shrinkage and resultant cracking/distress of the proposed structures and related improvements may occur.

6.3 Retaining Wall and Drainage Structures Foundations

Conventional spread-type foundation can be used to support the proposed structures. We recommend that the spread foundations bear upon engineered fill for support of anticipated loads. The depth and lateral extent of the engineered fills are presented in the **EARTHWORK** section of this report. Footings should bear a minimum of 24 inches below finished grade, which is the lowest adjacent grade for perimeter footings and floor level for interior footings. Recommended minimum widths of column, wood-frame and/or masonry wall footings are 24 and 16 inches, respectively.

Alternative footing depths and allowable bearing capacities are presented in the table below:

Footing Depth Below Finished Grade ⁴ (ft)	Allowable Bearing Capacity ⁵ (psf)
2.0 ⁶	3,000
3.0	4,000

We anticipate that total and differential settlement of the proposed structures, supported as recommended, should be less than 1 inch and ½ inch, respectively. Additional foundation movements could occur if water from any source infiltrates the foundation soils. Therefore, proper drainage should be provided in the final design and during construction.

⁴ Finished grade is the lowest adjacent grade for perimeter footings and floor level for interior footings.

⁵ Allowable bearing capacities assume fulfillment of **EARTHWORK** recommendations. Pounds per square foot (psf). Allowable Bearing Capacities also assume a minimum factor of safety equal to 3.

⁶ Minimum depth for frost protection of exterior footings or footings in unheated spaces.

The uplift resistance of spread footings supporting the structures may be calculated using the cone method. The equation for determining the ultimate uplift capacity as a function of footing width, footing depth, and soil weight is presented below:

$$T = \gamma D^2 \left(0.6W + 0.6L + 0.4D + \frac{WL}{D} \right)$$

Where: T = ultimate uplift capacity (lbs.)
 D = depth of footing below final grade (ft.)
 L = length of footing (ft.)
 W = width of footing (ft.)
 γ = unit weight of soil (pcf)*

*a unit weight of 100 pcf is recommended for the soils at this site

The design uplift resistance should be calculated by dividing the ultimate uplift capacity obtained from the equation above by a factor of safety. A factor of safety of at least 1.5 is recommended for live uplift loads.

All footings, stem walls and masonry walls should be reinforced to reduce the potential for distress caused by differential foundation movements. The use of joints at openings or other discontinuities in masonry walls is recommended.

We recommend that the geotechnical engineer or his representative observe the footing excavations before reinforcing steel and concrete are placed. This observation is to evaluate whether the soils exposed are similar to those anticipated for support of the footings. Any soft, loose, or unacceptable soils should be undercut to suitable materials and backfilled with approved fill materials or lean concrete. Soil backfill should be properly compacted.

6.4 **Tank Foundations**

It is our opinion that a concrete ring wall foundation confining a concrete slab can be used to support the proposed tank. Since the on-site soils exhibit moderate to high compressibility within the upper 5 feet, the ring wall foundations should bear on engineered fills achieved by removal and recompaction of the soils below the foundations. The depth and lateral extent of the engineered fills are presented in the **EARTHWORK** section of this report. The ring wall should bear at a minimum of 24 inches below finished grade, which is the lowest adjacent grade for perimeter footings and floor level for interior footings.

We recommend that the proposed ring wall foundation be structurally reinforced to limit the anticipated total and differential settlement to $\frac{3}{4}$ inch and $\frac{1}{2}$ inch, respectively.

6.5 Stormwater Pipe Foundations

The soils encountered within the upper 10 feet are predominantly Class III according to the New Mexico Standard Specification for Public Works (NMSSPW), Section 701. These materials should provide adequate support for the culverts and stormwater pipes. Class IV material including coal were encountered in Borings 1, 5 and 7. The majority of the site is coal, which varied in the degree of lithification and cementation. Any undisturbed coal can support the proposed stormwater pipes. However, we recommend that pipe bears on a minimum of 12 inches of Class I, II, or III as recommended in the **EARTHWORK** section of this report. Class IV material is not suitable for pipe support and should be removed if encountered. The stormwater pipes foundation should be prepared in accordance with NMSSPW section 700. Differential settlement in the pipe should not exceed $\frac{1}{2}$ of an inch for 20-foot sewer sections if the recommended **EARTHWORK** is followed. Settlement will primarily result from elastic movement of the soil mass during backfill and compaction operations.

6.6 Lateral Design Criteria

Lateral loads may be resisted by concrete interface friction and by passive resistance. For shallow foundations bearing on properly compacted fill at this site, we recommend the following lateral resistance criteria:

- Passive:
 - Shallow wall footings.....250 psf/ft
 - Shallow column footings400 psf/ft
- Coefficient of base friction (passive).....0.30

Earth retaining structures less than 10 feet in height, above any free water surface, with level backfill and no surcharge loads may be designed using the equivalent fluid pressure method. Recommended active equivalent fluid pressures and coefficients of base friction for unrestrained elements are:

- Active:
 - Undisturbed subsoil.....40 psf/ft
 - Compacted granular backfill30 psf/ft
 - Compacted site soils35 psf/ft
 - On-site clayey soilsnot recommended for use
- Coefficient of base friction (active).....0.40

Where the design includes restrained elements, the following equivalent fluid pressures are recommended:

- At-rest:
 - Undisturbed subsoil.....60 psf/ft
 - Compacted granular backfill55 psf/ft

The equivalent fluid pressures presented herein do not include the lateral pressures arising from the presence of:

- hydrostatic conditions, submergence or partial submergence
- sloping backfill, positively or negatively
- surcharge loading, permanent or temporary
- seismic or dynamic conditions

We recommend a free-draining soil layer or manufactured geosynthetic material be constructed adjacent to the back of any retaining walls. A filter may be required between the soil backfill and drainage layer. This drainage zone should help prevent development of hydrostatic pressure on the wall. This vertical drainage zone should be tied into a gravity drainage system at the base of the wall. It is important that all backfill be properly placed and compacted. Backfill should be mechanically compacted in layers. Flooding or jetting should not be permitted. Care should be taken not to damage the walls when placing the backfill. Backfills should be observed and tested during placement.

Fill against footings, stem walls, and retaining walls should be compacted to densities specified in **EARTHWORK**. Compaction of each lift adjacent to walls should be accomplished with hand-operated tampers or other lightweight compactors. Over-compaction may cause excessive lateral earth pressures that could result in wall movements.

6.7 Seismic Considerations

Structures should be designed in accordance with applicable building codes. The seismic design parameters presented in the following table, in accordance with the 2021 International Building Code/American Society of Civil Engineers (ASCE) 7-16 are applicable to the project site:

Seismic Design Parameters 2021 IBC/ASCE 7-16	
Soil Site Class based on ReMi Velocity Profile	C
Mapped Spectral Response Acceleration at 0.2 sec period (S_s)	0.411g
Mapped Spectral Response Acceleration at 1.0 sec period (S_1)	0.137g
Site Coefficient for 0.2 sec period (F_a)	1.300
Site Coefficient for 1.0 sec period (F_v)	1.500
Design Spectral Response Acceleration at 0.2 sec period (S_{DS})	0.356g
Design Spectral Response Acceleration at 1.0 sec period (S_{D1})	0.137g

6.8 Slab Support

Floor slabs can be supported on properly placed and compacted fill. The slab subgrade should be prepared by the procedures outlined in this report. A minimum 4-inch layer of base course should be provided beneath all slabs to help prevent capillary rise and a damp slab. The modulus of subgrade reaction (k) is estimated to be 150 pounds per cubic inch (pci), based upon a 30-inch diameter plate.

The use of vapor retarders or barriers is desirable for any slab-on-grade where the floor will be covered by products using water-based adhesives, wood, vinyl backed carpet, impermeable floor coatings (urethane, epoxy, acrylic terrazzo, etc.) or where the floor will be in contact with moisture sensitive equipment or product. When used, the design and installation should be in accordance with the recommendations given in ACI 302.1R and 302.2R. Final determination on the use of a vapor retarder should be left to the slab designer.

All concrete placement and curing operations should follow the American Concrete Institute manual recommendations. Improper curing techniques and/or high slump (high water-cement ratio) could cause excessive shrinkage, cracking or curling. Concrete slabs

should be allowed to cure adequately before placing vinyl or other moisture sensitive floor covering.

6.9 Drainage

The major cause of soil problems in this vicinity is moisture increase in soils below structures. Therefore, it is extremely important that positive drainage be provided during construction and maintained throughout the life of the proposed structures. Infiltration of water into utility or foundation excavations must be prevented during construction. Planters or other surface features that could retain water adjacent to the proposed structures, should not be constructed. It is also important that proper planning and control of any landscape and irrigation practices be performed.

In areas where sidewalks or paving do not immediately adjoin the building, protective slopes should be provided with an outfall of 5 percent for at least 10 feet from perimeter walls. Scuppers and drainpipes should be designed to provide drainage away from the structures for a minimum of 10 feet. Backfill against footings, exterior walls, and in utility and sprinkler line trenches should be well compacted and free of all construction debris to minimize the possibility of moisture infiltration.

Water and sewer utility lines should be properly installed to avoid possible sources for subsurface saturation. It is important that all utility trenches be properly backfilled. If practicable, planters and/or landscaping should not be constructed adjacent to or near structures. If planters and/or landscaping are adjacent to or near the structures, we recommend the following:

- Planters should be sealed
- Grades should slope away from the proposed structures
- Only shallow rooted landscaping should be used
- Watering should be kept to a minimum

6.10 Corrosivity to Concrete and Metal Components

A major factor in determining soil corrosivity is electrical resistivity. The electrical resistivity of a soil is a measure of its resistance to the flow of electrical current. Corrosion of buried metal is an electrochemical process in which the amount of metal loss due to corrosion is directly proportional to the flow of electrical current (DC) from the metal into the soil.

Corrosion current, following Ohm's Law, is inversely proportional to soil resistivity. Lower electrical resistivities result from higher moisture and soluble salt contents and indicate corrosive soil.

The correlation between electrical resistivity and corrosivity ferrous metals is presented in the table below.

Soil Resistivity (ohm-cm)	Corrosivity Category
Greater than 10,000	Mildly Corrosive
2,001 to 10,000	Moderately Corrosive
1,001 to 2,000	Corrosive
0 to 1,000	Severely Corrosive

Based on the laboratory results, the soils at the site can be classified as moderately corrosive to ferrous metals and severe for sulfate attack on concrete. Consequently, ASTM Type V cement or equivalent sulfate resistant cement be used for concrete structures bearing on and/or in on-site soils. For metallic components of the structures in contact with soils and groundwater in this site, we recommend that the contractor implement corrosion protection.

6.11 **Pavements**

Pavement analysis was performed for the residential streets. We have also provided concrete paving and treated base course options for the roadway sections crossing the Madrid arroyo. We assumed design vehicles consisted of:

- 18-wheelers/trailers
- Firetrucks/ambulances
- Snowplows
- Passenger cars
- Trucks/SUVs

The encountered soils in the areas of the roadways at Borings 10, 11, 12, 13, 14, 15, and 16 consisted of predominantly COAL. The CBRs for these roadways ranged from 3 (Boring 16) to 32 (Boing 10). The coal is considered highly lithified and cemented in Borings 10 through 15. Boring 16 showed less lithification and cementations. Due to wide variation in the degree of lithification and compaction of the coal, separation pavement sections are

provided as well as subgrade preparation as outlined in the **EARTHWORK** section of this report.

This slab analysis utilized the flexible pavement CBR analysis of the U.S. Army Corps of Engineers' PCASE pavement design program. This PCASE design methodology determines a design vehicle from vehicles input by the user for analysis and then determines the equivalent number of passes or load repetitions of all the input vehicles equated to the design vehicle.

Traffic analysis was performed based on estimates of the number of passes of the fully loaded vehicle on a given point during a standard business day. The number of projected passes was not provided to us, so we performed an analysis using the estimated passes, as follows:

- 18-wheelers/trailers – 29,200 total passes - 4 loaded passes per day for 20 years
- Firetrucks/ambulances – 3,650 total passes – 0.5 loaded passes per day for 20 years
- Snowplows – 3,650 total passes – 0.5 loaded passes per day for 20 years
- Passenger cars – 584,000 total passes – 80 loaded passes per day for 20 years
- Trucks/SUVs – 146,000 total passes – 30 loaded passes per day for 20 years

The rigid pavement was designed as plain, unreinforced 650 psi flexural strength concrete. The k-value used in design calculations was 200 pounds per cubic inch (pci) for subgrade soils. The CBRs used for the various are listed on the below. The recommended section thicknesses for the paved areas are included in the following table.

Pavement Area	Surfacing Option	Design CBR	Portland Cement Concrete (PCC) Thickness	Treated ABC	ABC
Firehouse Lane	ABC	3	--	--	12
Other Residential Streets	ABC	24	--	--	10
Madrid Arroyo Crossing	PCC	24	6	--	4
	Treated ABC	24	--	8	--
Fire Lane	ABC	24	--	--	10

Note: PCC – Portland Cement Concrete
ABC- Aggregate Base Course

For the design of concrete pavement subjected to loading, the important strength property is flexural strength. The design strength value of 650 psi utilized here is reasonable and achievable for our local concrete materials. Because flexural strength is seldom measured or even understood on most commercial projects, it is usually best to specify the concrete with a required compressive strength. We recommend utilizing a concrete compressive strength of 4,000 psi or an NMDOT Class P concrete.

Pavements Sections for NM Highway 14

Pavement Areas	Design ESAL	Design Boring ID	Asphalt Concrete Pavement (inches)	Base Course (inches)
1	10	8	4.0	10
2			4.5	8

If the existing pavement sections on NM 14 are thicker than those recommended above, the existing pavement section should be matched. Once final traffic information becomes available, we can provide final pavement design sections.

Base course and asphalt concrete should conform to the New Mexico Department of Transportation (NMDOT) Standard Specifications for Road and Bridge Construction or the New Mexico Standard Specifications for Public Works Construction, whichever is applicable. Bituminous surfacing should be constructed of dense-graded, central plant-mix, asphalt concrete and SP-IV or SP-III.

Material and compaction requirements should conform to recommendations presented under **EARTHWORK**. The gradient of paved surfaces should ensure positive drainage. Water should not pond in areas directly adjoining paved sections. The on-site subgrade soils may soften and lose stability if subjected to conditions that result in an increase in water content.

Jointing

As stated in ACI 360R-10, Guide to Design of Slabs-on-Ground: “Joints are used in slab-on-ground construction to limit the frequency and width of random cracks caused by concrete volume changes.” The volume changes are caused by changing temperature and from concrete moisture loss over time. Cracking then occurs in the concrete due to resistance to those movements by gravity and subgrade friction. Joints are placed at relatively close

spacing for plain, unreinforced slabs and are typically spaced farther apart when slabs are reinforced. Joint spacing recommendations are provided in Table 2 below. Dowels should be placed in all construction joints and are not necessary in sawcut contraction joints. Dowel recommendations are also included in Table 2.

Contraction joints should be made by appropriately timed sawcuts following the guidelines of Section 6.3 of ACI 360R-10. Sawcuts can be made with conventional wet-cut (water-injection) saws, conventional dry-cut saws, or early-entry dry-cut sawcuts. Sawcuts made by conventional saws should be made to a minimum depth of 1/4 of the concrete depth whereas early-entry cuts should be a minimum of 1.5 inches deep.

An isolation joint is recommended at or along all interfaces with existing structures or building components. At those edge locations that will be subjected to vehicular loading such as at dock entry points, the concrete slab should be thickened an additional 25 percent with a taper or transition of 5 feet back to the standard pavement thickness.

The joints, and particularly the joint edges, need to be protected from degradation due to impact loading from the fire app and from the dragging of pallets, etc., across the joints. Typically, the more economical method to provide protection is to fill the joint with an appropriate material to maintain surface continuity across the joint. The typical joint fill materials for this purpose are certain types of semi-rigid epoxy and polyuria. These materials should be 100 percent solids and have a minimum ASTM D2240 Shore A hardness of 80. These particular joint fillers should be installed full depth to the bottom of the sawcut so that the sawcut ledge provides support for the filler material.

The table below summarizes joint and dowel spacing per the PCASE pavement design program.

PCASE Joint and Dowel Summary

Pavement Area	Joint Spacing, feet	Dowel Spacing, inches	Dowel Length, inches	Dowel Diameter, inches
Pavement Areas	10 – 15	12	16	0.8

7.0 EARTHWORK

7.1 General

The conclusions contained in this report for the proposed construction are contingent upon compliance with recommendations presented in this section. Any excavating, trenching, or disturbance that occurs after completion of the earthwork must be backfilled, compacted and tested in accordance with the recommendations contained herein. It is not reasonable to rely upon our conclusions and recommendations if any future unobserved and untested trenching, earthwork activities or backfilling occurs.

If any unobserved and untested earthwork, trenching or backfilling occurs, then the conclusions and recommendations in this report may not be relied on. We recommend that Western Technologies Inc. be retained to provide services during these phases of the project. Observation and testing of all foundation excavations should be performed prior to placement of reinforcing steel and concrete to confirm that foundations are constructed on satisfactory bearing materials.

7.2 Site Clearing

Strip and remove any existing vegetation, debris, and any other deleterious materials from the structures areas. The structures area is defined as areas within the structures' footprint plus 5 feet beyond the perimeter of that footprint. All exposed surfaces should be free of mounds and depressions that could prevent uniform compaction.

7.3 Excavation

We anticipate that excavations for the foundations and utility trenches for the proposed construction can be accomplished with conventional equipment. It is our opinion that that the auger refusal material is rippable, but may require the use of heavy-duty or specialized equipment to facilitate removal. The speed and ease of excavation is dependent on the nature of the deposit, the type of equipment used, and the skill and experience of the equipment operator. Note that selection of excavation equipment is the responsibility of the contractor.

The soils to be penetrated by the proposed excavations may vary significantly across the site. Our soil classifications are based solely on the materials encountered in widely spaced exploratory test borings. The contractor should verify that similar conditions exist

throughout the proposed area of excavation. If different subsurface conditions are found at the time of construction, we should be contacted immediately to evaluate the conditions encountered.

7.3.1 Temporary Excavations and Slopes

Temporary, non-surcharged construction excavations should be sloped or shored. The individual contractor should be made responsible for designing and constructing stable, temporary excavations as required to maintain stability of both the excavation sides and bottom. All excavations should be sloped or shored in the interest of safety following local and federal regulations, including current OSHA excavation and trench safety standards. OSHA recommends a maximum slope inclination of $\frac{3}{4}$:1 (horizontal:vertical) for Type A soils, 1:1 for Type B soils, and $1\frac{1}{2}$:1 for Type C soils.


As a safety measure, it is recommended that all vehicles and soil piles be kept a minimum lateral distance back from the crest of the slope at least equal to the slope height. The exposed slope face should be protected against the elements.

If any excavation, including a utility trench, is extended to a depth of more than 20 feet, it will be necessary to have the side slopes designed by a professional engineer.


We recommend that the contractor retain a geotechnical engineer to observe the soils exposed in all excavations and provide engineering design for the slopes. This will provide an opportunity to classify the soil types encountered, and to modify the excavation slopes as necessary. This also allows the opportunity to analyze the stability of the excavation slopes during construction.

7.4 Foundation Preparation

In the tank and retaining wall areas, remove existing soils throughout the entire tank footprint to a minimum depth of 3 feet below the bottom of footing elevation or 5 below existing site grade, whichever is deepest. Following the removal, scarify, moisten or dry as required, and recompact the bottom of the excavation to a minimum depth of 10 inches. Refill the excavation with properly compacted engineered fill material. The removal and replacement should extend laterally a minimum of 3 feet beyond the foundation or perimeter of the tank.



In drainage crossing areas, remove existing soils as required to a minimum depth of 2 feet below the bottom of the box culvert (length Y in the diagram below). Removal and recompaction should extend a minimum of 3 feet beyond the footing edges (length X in the diagram below).



7.5 Slab Preparation

Slabs should be founded on engineered fill material. Remove existing soils to a minimum depth of 24 inches below the bottom of the slab. Replace with properly compacted, low-expansive, fill material.

7.6 Pavement Preparation

In pavement areas, remove existing soils to minimum depths of 18 inches and replace with engineered fill. Following the removal, the bottom of the excavation should be scarified, moistened as required, and recompact to a minimum depth of 10 inches prior to placement of fill and pavement materials.

7.7 Stormwater Pipes Foundation Preparation

The sewer line should be installed in accordance with New Mexico Standard Specification for Public Works (NMSSPW), specifically, Section 701.13 and any other applicable national, state, city, and county standards. Bedding materials should surround the sewer line for support. The sewer line trench backfill should be designed in accordance with NMSSPW, Section 701.14.

7.8 Materials

Clean on-site soils with low expansive potentials and maximum dimension of 6 inches or imported materials may be used as fill material for the following:

- Foundation areas
- Slabs
- Pavement
- Backfill

Frozen soils should not be used as fill or backfill.

Imported soils should conform to the following:

- Gradation (ASTM C136): percent finer by weight

6"	100
4"	85-100
¾"	70-100
No. 4 Sieve	50-100
No. 200 Sieve	30 (max)
- Maximum Plasticity Index 5
- Maximum soluble sulfates (%) 0.10

On-site low expansive soils can be used as backfill.

Base course should conform to the New Mexico Department of Transportation (NMDOT) Standard Specifications for Road and Bridge Construction or the New Mexico Standard Specifications for Public Works Construction, whichever is applicable.

7.9 Placement and Compaction

- a. Place and compact fill in horizontal lifts, using equipment and procedures that will produce recommended water contents and densities throughout the lift.
- b. Uncompacted lift thickness should not exceed 10 inches.
- c. Materials should be compacted to the following:

Minimum Percent Material Compaction (ASTM D1557)

- On-site or imported soil, reworked and fill 95
- Base course below slabs-on-grade 95
- Aggregate base below pavement 96
- Nonstructural backfill 90

Fill at depths greater than 5 feet below finished grade should be compacted to at least 98 percent of the ASTM D1557 dry-density value to within 5 feet of finished grade. Fill at depths less than 5 feet below finished grade should be compacted to the minimum values provided above.

Imported or blended soils meeting import soils specification should be compacted to within a water content range of 3 percent below to 3 percent above optimum. On-site clay soils should be compacted to within a water content range of 1 percent below to 3 percent above optimum.

7.10 Compliance

Recommendations for foundations, and pavements supported on compacted fills or prepared subgrade depend upon compliance with the **EARTHWORK** recommendations. To assess compliance, observation and testing should be performed under the direction of a WT geotechnical engineer. Please contact us to provide these observation and testing services.

8.0 PLAN REVIEW

Foundation and grading plans were not available at the time of this report. WT should be retained to review the final plans to determine if they are consistent with the recommendations presented in this report. If the Client does not retain WT to review the plans and specifications, WT shall have no responsibility for the suitability of the plans for project application.

9.0 ADDITIONAL SERVICES

The recommendations provided in this report are based on the assumption that a sufficient schedule of tests and observations will be performed during construction to verify compliance. At a minimum, these tests and observations should be comprised of the following:

- Observations and testing during site preparation and earthwork,
- Observation of foundation excavations, and
- Consultation as may be required during construction.

Retaining the geotechnical engineer who developed your report to provide construction observation is the best way to verify compliance and to help you manage the risks associated with unanticipated conditions.

10.0 LIMITATIONS

This report has been prepared assuming the project criteria described in **2.0 PROJECT DESCRIPTION**. If changes in the project criteria occur, or if different subsurface conditions are encountered or become known, the conclusions and recommendations presented herein shall become invalid. In any such event, WT should be contacted in order to assess the effect that such variations may have on our conclusions and recommendations. If WT is not retained for the construction observation and testing services to determine compliance with this report, our professional responsibility is accordingly limited.

The recommendations presented are based entirely upon data derived from a limited number of samples obtained from widely spaced explorations. The attached logs are indicators of subsurface conditions only at the specific locations and times noted. This report assumes the uniformity of the geology and soil structure between explorations, however variations can and

often do exist. Whenever any deviation, difference, or change is encountered or becomes known, WT should be contacted.

This report is for the exclusive benefit of our client alone. There are no intended third-party beneficiaries of our contract with the client or this report, and nothing contained in the contract or this report shall create any express or implied contractual or any other relationship with, or claim or cause of action for, any third party against WT.

This report is valid for the earlier of one year from the date of issuance, a change in circumstances, or discovered variations. After expiration, no person or entity shall rely on this report without the express written authorization of WT.

11.0 CLOSURE

We prepared this report as an aid to the designers of the proposed project. The comments, statements, recommendations and conclusions set forth in this report reflect the opinions of the authors. These opinions are based upon data obtained at the location of the explorations, and from laboratory tests. Work on your project was performed in accordance with generally accepted standards and practices utilized by professionals providing similar services in this locality. No other warranty, express or implied, is made.



- Approximate ReMi Location
- Approximate Boring Location



PROJECT:	MADRID STORMWATER & EROSION CONTROL
JOB NO.:	32-223560-0

BORING LOCATION DIAGRAM

PLATE

1

Allowable Soil Bearing Capacity	The recommended maximum contact stress developed at the interface of the foundation element and the supporting material.
Backfill	A specified material placed and compacted in a confined area.
Base Course	A layer of specified aggregate material placed on a subgrade or subbase.
Base Course Grade	Top of base course.
Bench	A horizontal surface in a sloped deposit.
Caisson/Drilled Shaft	A concrete foundation element cast in a circular excavation which may have an enlarged base (or belled caisson).
Concrete Slabs-On-Grade	A concrete surface layer cast directly upon base course, subbase or subgrade.
Crushed Rock Base Course	A base course composed of crushed rock of a specified gradation.
Differential Settlement	Unequal settlement between or within foundation elements of a structure.
Engineered Fill	Specified soil or aggregate material placed and compacted to specified density and/or moisture conditions under observations of a representative of a soil engineer.
Existing Fill	Materials deposited through the action of man prior to exploration of the site.
Existing Grade	The ground surface at the time of field exploration.
Expansive Potential	The potential of a soil to expand (increase in volume) due to absorption of moisture.
Fill	Materials deposited by the actions of man.
Finished Grade	The final grade created as a part of the project.
Gravel Base Course	A base course composed of naturally occurring gravel with a specified gradation.
Heave	Upward movement.
Native Grade	The naturally occurring ground surface.
Native Soil	Naturally occurring on-site soil.
Rock	A natural aggregate of mineral grains connected by strong and permanent cohesive forces. Usually requires drilling, wedging, blasting or other methods of extraordinary force for excavation.
Sand and Gravel Base Course	A base course of sand and gravel of a specified gradation.
Sand Base Course	A base course composed primarily of sand of a specified gradation.
Scarify	To mechanically loosen soil or break down existing soil structure.
Settlement	Downward movement.
Soil	Any unconsolidated material composed of discrete solid particles, derived from the physical and/or chemical disintegration of vegetable or mineral matter, which can be separated by gentle mechanical means such as agitation in water.
Strip	To remove from present location.
Subbase	A layer of specified material placed to form a layer between the subgrade and base course.
Subbase Grade	Top of subbase.
Subgrade	Prepared native soil surface.

COARSE-GRAINED SOILS
LESS THAN 50% FINES

GROUP SYMBOLS	DESCRIPTION	MAJOR DIVISIONS
GW	WELL-GRADED GRAVEL OR WELL-GRADED GRAVEL WITH SAND, LESS THAN 5% FINES	GRAVELS MORE THAN HALF OF COARSE FRACTION IS LARGER THAN NO. 4 SIEVE SIZE
GP	POORLY-GRADED GRAVEL OR POORLY-GRADED GRAVEL WITH SAND, LESS THAN 5% FINES	
GM	SILTY GRAVEL OR SILTY GRAVEL WITH SAND, MORE THAN 12% FINES	
GC	CLAYEY GRAVEL OR CLAYEY GRAVEL WITH SAND, MORE THAN 12% FINES	
SW	WELL-GRADED SAND OR WELL-GRADED SAND WITH GRAVEL, LESS THAN 5% FINES	SANDS MORE THAN HALF OF COARSE FRACTION IS SMALLER THAN NO. 4 SIEVE SIZE
SP	POORLY-GRADED SAND OR POORLY-GRADED SAND WITH GRAVEL, LESS THAN 5% FINES	
SM	SILTY SAND OR SILTY SAND WITH GRAVEL, MORE THAN 12% FINES	
SC	CLAYEY SAND OR CLAYEY SAND WITH GRAVEL, MORE THAN 12% FINES	

NOTE: Coarse-grained soils receive dual symbols if they contain 5% to 12% fines (e.g., SW-SM, GP-GC).

FINE-GRAINED SOILS
MORE THAN 50% FINES

GROUP SYMBOLS	DESCRIPTION	MAJOR DIVISIONS
ML	SILT, SILT WITH SAND OR GRAVEL, SANDY SILT, OR GRAVELLY SILT	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50
CL	LEAN CLAY OF LOW TO MEDIUM PLASTICITY, SANDY CLAY, OR GRAVELLY CLAY	
OL	ORGANIC SILT OR ORGANIC CLAY OF LOW TO MEDIUM PLASTICITY	
MH	ELASTIC SILT, SANDY ELASTIC SILT, OR GRAVELLY ELASTIC SILT	SILTS AND CLAYS LIQUID LIMIT MORE THAN 50
CH	FAT CLAY OF HIGH PLASTICITY, SANDY FAT CLAY, OR GRAVELLY FAT CLAY	
OH	ORGANIC SILT OR ORGANIC CLAY OF HIGH PLASTICITY	
PT	PEAT AND OTHER HIGHLY ORGANIC SOILS	HIGHLY ORGANIC SOILS

NOTE: Fine-grained soils may receive dual classification based upon plasticity characteristics (e.g. CL-ML).

SOIL SIZES

COMPONENT	SIZE RANGE
BOULDERS	Above 12 in.
COBBLES	3 in. – 12 in.
GRAVEL	No. 4 – 3 in.
Coarse	¾ in. – 3 in.
Fine	No. 4 – ¾ in.
SAND	No. 200 – No. 4
Coarse	No. 10 – No. 4
Medium	No. 40 – No. 10
Fine	No. 200 – No. 40
Fines (Silt or Clay)	Below No. 200

NOTE: Only sizes smaller than three inches are used to classify soils

CONSISTENCY

CLAYS & SILTS	BLOWS PER FOOT
VERY SOFT	0 – 2
SOFT	3 – 4
FIRM	5 – 8
STIFF	9 – 15
VERY STIFF	16 – 30
HARD	OVER 30

RELATIVE DENSITY

SANDS & GRAVELS	BLOWS PER FOOT
VERY LOOSE	0 – 4
LOOSE	5 – 10
MEDIUM DENSE	11 – 30
DENSE	31 – 50
VERY DENSE	OVER 50

NOTE: Number of blows using 140-pound hammer falling 30 inches to drive a 2-inch-OD (1½-inch ID) split-barrel sampler (ASTM D1586).

PLASTICITY OF FINE GRAINED SOILS

PLASTICITY INDEX	TERM
0	NON-PLASTIC
1 – 7	LOW
8 – 20	MEDIUM
Over 20	HIGH

DEFINITION OF WATER CONTENT

DRY
SLIGHTLY DAMP
DAMP
MOIST
WET
SATURATED



METHOD OF CLASSIFICATION

PLATE

A-2

The number shown in **"BORING NO."** or **"TEST PIT NO."** refers to the approximate location of the same number indicated on the "Boring and Test Pit Location Diagram" as positioned in the field by pacing or measurement from property lines and/or existing features, or through the use of Global Positioning System (GPS) devices. The accuracy of GPS devices is somewhat variable.

"DRILLING TYPE" refers to the exploratory equipment used in the boring wherein **HSA = hollow stem auger**, and the dimension presented is the outside diameter of the HSA used.

"EQUIPMENT TYPE" refers to the equipment used in the excavation of the test pit, and may include the width of the bucket on the excavator and the use of "rock" teeth or attachments.

"N" in "BLOW COUNTS" refers to a 2-in. outside diameter split-barrel sampler driven into the ground with a 140 lb. drop-hammer dropped 30 in. repeatedly until a penetration of 18 in. is achieved or until refusal. The number of blows, or "blow count", of the hammer is recorded for each of three 6-in. increments totaling 18 in. The number of blows required for advancing the sampler for the last 12 in. (2nd and 3rd increments) is defined as the Standard Penetration Test (SPT) "N"-Value. Refusal to penetration is considered more than 50 blows for a 6-inch increment. (Ref. ASTM D1586).

If,

N = a whole # e.g. "15", it represents the SPT blow counts for the last 12 inches.

N = stacked numbers e.g., 5/10/20, it represents the blow counts for each 6 inches increment.

"R" in "BLOW COUNTS" refers to a 3-in. outside diameter ring-lined split spoon sampler driven into the ground with a 140 lb. drop-hammer dropped 30 inches repeatedly until a penetration of 12 inches is achieved or until refusal. The number of blows required to advance the sampler 12 inches is defined as the "R" blow count. The "R" blow count requires an engineered conversion to an equivalent SPT N-Value. Refusal to penetration is considered more than 50 blows for a 6-inch increment. (Ref. ASTM D3550).

If,

R = a whole # e.g. "15", it represents the unconverted blow counts for 12 inches.

For refusal (penetration less than 12 inches), R=a whole #/X" e.g., 50/10"

"CS" in "BLOWS/FT." refers to a 2½-in. outside diameter California style split-barrel sampler, lined with brass sleeves, driven into the ground with a 140-pound hammer dropped 30 inches repeatedly until a penetration of 18 inches is achieved or until refusal. The number of blows of the hammer is recorded for each of the three 6-inch increments totaling 18 inches. The number of blows required for advancing the sampler for the last 12 inches (2nd and 3rd increments) is defined as the "CS" blow count. The "CS" blow count requires an engineered conversion to an equivalent SPT N-Value. Refusal to penetration is considered more than 50 blows for a 6-inch increment. (Ref. ASTM D3550)

"SAMPLE TYPE" refers to the form of sample recovery, in which **N** = Split-barrel sample, **R** = Ring-lined sample, **CS** = California style split-barrel sample, **G** = Grab sample, **B** = Bucket sample, **C** = Core sample (ex. diamond-bit rock coring), **S** = Shelby Tube.

"DRY DENSITY (LBS/CU FT)" refers to the laboratory-determined dry density in pounds per cubic foot. The symbol **"NR"** indicates that no sample was recovered.

"WATER (MOISTURE) CONTENT (% OF DRY WT.)" refers to the laboratory-determined water content in percent using the standard test method ASTM D2216.

"USCS" refers to the "Unified Soil Classification System" Group Symbol for the soil type as defined by ASTM D2487 and D2488. The soils were classified visually in the field, and where appropriate, classifications were modified by visual examination of samples in the laboratory and/or by appropriate tests.

These notes and boring logs are intended for use in conjunction with the purposes of our services defined in the text. Boring log data should not be construed as part of the construction plans nor as defining construction conditions.

Boring logs depict our interpretations of subsurface conditions at the locations and on the date(s) noted. Variations in subsurface conditions and characteristics may occur between borings. Groundwater levels may fluctuate due to seasonal variations and other factors.

The stratification lines shown on the boring logs represent our interpretation of the approximate boundary between soil or rock types based upon visual field classification at the boring location. The transition between materials is approximate and may be more or less gradual than indicated.

Project: MADRID STORMWATER END EROSION CONTROL	BORING NO. 1	
Project Number: 32-223560-0		

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 21.5
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0				G		CH		Fat CLAY with Sand and Gravel; dark grey, very stiff or medium dense, moist	
				N	9 14 15			no gravel	
5				R	41				
				N	13 15 19			hard or dense	
10				R	50/10"			brown, hard or dense, damp	
				G					
15				N	76/4"	SC		Clayey SAND; brown, very dense, damp	
20				N	50/5"	CL		Lean CLAY; with shale / sandstone, dark brown, hard, damp	
								BORING TERMINATED AT 21.5 FEET	
25									

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL	BORING NO. 2	
Project Number: 32-223560-0		

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 21.5
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0						SC		Clayey SAND; light brown, medium dense, damp	
3.7			B		37				
5			N		68/5"	Sandstone		with sandstone, very dense	
5.0			R		50/4"				
10			N		29 39 36	CL		Lean CLAY; grey, hard, damp	
10.0			G						
15			N		79/45"			with coal, black, very dense, damp	
15.0			G					less coal, dark grey	
20			N		92/3"				
21.5								BRING TERMINATED AT 21.5 FEET	

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL	BORING NO. 3	
Project Number: 32-223560-0		

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 11.5
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0				G		SC		Clayey SAND with cobbles and Gravel; dark brown, dense, fine to coarse grained, low to medium PI, damp	
				R	54			white layers / light brown	
5				N	13 12 17	SP-SM		Poorly-graded SAND with Silt; with gravel and cobbles, light brown / white, medium dense, fine to coarse grained, low to medium PI	
10				R	50/8"			partial recovery, cobbles, dense, low PI	
								REFUSAL ENCOUNTERED AT 11.5 FEET	
15									
20									
25									

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

**Project: MADRID STORMWATER
END EROSION CONTROL**

Project Number: 32-223560-0

BORING NO. 4



Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 14
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0				G		SM		Silty SAND with Gravel and Cobbles; brown, medium dense	
10				N	10 7 8				
5				N	9 11 15				
				R	20				
10				N	13 18 27	SP-SM		Poorly-graded SAND with Silt; brown, medium dense, damp	
				N	50/2"			cobbles	
15								REFUSAL ENCOUNTERED AT 14 FEET	
20									
25									

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL	BORING NO. 5	
Project Number: 32-223560-0		

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 10
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0				G		C		COAL consisting of Poorly-graded to Silty Sand fragments that of fine to coarse grained	
				N	3 4 4				
5				R	15				
	NR			N	50/3"			cobbles	
10	NR			N	50/1"				
								REFUSAL ENCOUNTERED AT 10 FEET	
15									

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL	BORING NO. 6	
Project Number: 32-223560-0		

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0				G		SM		Silty SAND with Gravel and Cobbles; dark brown, fine to coarse grained, low PI	
								large boulders	
5				N	8 10 10	SP-SM		Poorly-graded SAND with Silt; trace gravel and coal, brown /white / grey, medium dense, coarse grained, low PI	
				R	60			cobbles, dark brown, dense	
10				N	55/4.5"			some gravel, grey, very dense	
15				N	50/3"				
								BORING TERMINATED AT 16.5 FEET	
20									

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL	BORING NO. 7	 Western Technologies An RMA Company
Project Number: 32-223560-0		

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 16.5
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0	18.7			G		CL		Sandy Lean CLAY; dark brown, very stiff, moist	
				N	6 8 8			with coal	
5	8.9	95		G	18			grey / brown	
				N	12 15 20				
10				N	11 15 21	Shale		with shale	
15				N	50/4"			lots of shale	
								BORING TERMINATED AT 16.5 FEET	
20									

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL	BORING NO. 8	 Western Technologies An RMA Company
Project Number: 32-223560-0		

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 16.5
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0	8.7			G		SC		Clayey SAND with Gravel; dark brown, dense, damp	
13.1	103			R	50/7"				
5				N	22 38 49	CL		Lean CLAY; dark brown / dark grey, hard, damp	
10.8	95			R	50/6"				
10				N	50/3"				
				G					
15				N	50/3"	Shale		shale and sandstone	
								BORING TERMINATED AT 16.5 FEET	
20									

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL	BORING NO. 9	 Western Technologies An RMA Company
Project Number: 32-223560-0		

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 16.5
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0				G		C		COAL consisting of Poorly-graded to Silty Sand fragments that of fine to coarse grained	
				R	6				
5				G	238				
				N	38			medium dense	
10				R	41	CL		Lean CLAY; trace coal, brown / grey, hard, damp	
15				N	343538			very hard	
								BORING TERMINATED AT 16.5 FEET	
20									

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL	BORING NO. 10	 Western Technologies An RMA Company
Project Number: 32-223560-0		

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 6.5
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0	18.1			G		SM		Silty SAND; dark brown, medium dense, moist	
6.0		104		R	32			with gravel	
5				N	23 27 13			dense	
10								BORING TERMINATED AT 6.5 FEET	

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL Project Number: 32-223560-0	BORING NO. 11	 Western Technologies An RMA Company
---	----------------------	---


Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 2
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0				G		SC		Clayey SAND with Gravel and Cobbles; dark brown, very dense, moist	
				N	50/1"			REFUSAL ENCOUNTERED AT 2 FEET	
5									

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL Project Number: 32-223560-0	BORING NO. 12	
---	----------------------	---

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 6.5
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	



G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL Project Number: 32-223560-0	BORING NO. 13	 Western Technologies An RMA Company
---	----------------------	---


Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 5
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location 35.40836°,-106.15289°	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0						SC		Clayey SAND; light brown, medium PI, damp	
14.4				G					A-6(5)
5								BORING TERMINATED AT 5 FEET	
10									

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL Project Number: 32-223560-0	BORING NO. 14	 Western Technologies An RMA Company
---	----------------------	---

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 6.5
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	



G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Project: MADRID STORMWATER END EROSION CONTROL Project Number: 32-223560-0	BORING NO. 15	
---	----------------------	---

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 6.5
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0	12.5			G		C		COAL consisting of Poorly-graded to Silty Sand fragments that of fine to coarse grained	
10.6				G					
9.6	65			R	15				
5								basalt	
								loose, damp	
								BORING TERMINATED AT 6.5 FEET	
10									

Project: MADRID STORMWATER END EROSION CONTROL	BORING NO. 16	
Project Number: 32-223560-0		

Date(s) Drilled 1/17/2024	Logged By S. O'HERRON-ALEX	Checked By A. KABA
Drilling Method GEOPROB	Drill Bit Size/Type 7"	Total Depth of Borehole 6.5
Drill Rig Type GEOPROB	Drilling Contractor WESTERN TECHNOLOGIES	Approximate Surface Elevation NOT DETERMINED
Groundwater Level and Date Measured NO GROUNDWATER ENCOUNTERED	Sampling Method(s) GRAB, RING, SPT	Hammer Data 140-LB AUTOHAMMER
Borehole Backfill GEOPROB CUTTINGS	Location SEE LOCATION DIAGRAM	

Depth (feet)	WATER CONTENT	DRY DENSITY (LBS/CU FT)	SAMPLE TYPE	SAMPLE	BLOW COUNTS	USCS	GRAPHIC LOG	SOIL DESCRIPTION	REMARKS AND OTHER TESTS
0	10.1			G		SC		Clayey SAND with gravel; dark brown / black, very dense, moist	
	NR			R	50/2"			with cobbles	
						SP-SC		Poorly-graded SAND with Clay; trace gravel, brown, medium dense, damp	
5				N					
								BORING TERMINATED AT 6.5 FEET	
10									

G:\2023\32-223560-0-STATE OF-MADRID STORMWATER\223560BoringLogs.bg4[Lym.tp]

Boring No.	Depth (ft.)	USCS (AASHTO)	Initial Dry Density (pcf)	Initial Water Content (%)	Compression Properties			Expansion Properties		Plasticity		Soluble Sulfate (ppm)	Soluble Sulfate (ppm)	Remarks
					Surcharge (ksf)	Total Compression (%)		Surcharge (ksf)	Expansion (%)	Liquid Limit	Plasticity Index			
						In-Situ	After Saturation							
1	5-6	CH (A-7-6(27))	112	9.1				0.1	6.0					1,2
1	5-6	CH (A-7-6(27))	112	9.1	0.5	-0.4	3.6							2
					1.0		3.3					2		
					2.0		2.4					2		
					4.0		1.0					2		
2	2-3	SC (A-6(7))	100	6.4	0.5	0.4								
					1.0	1.0								
					2.0	1.4	2.3					2		
					4.0	3.6						2		
4	7-8	SM (A-1-b(0))	104	3.0	0.5	1.6								
					1.0	2.9								
					2.0	3.9	9.2					2		
					4.0	11.2						2		

Note: Initial Dry Density and Initial Water Content are in-situ values unless otherwise noted.
NP = Non-Plastic

Remarks

1. Compacted density (approx. 95% of ASTM D1557 max. density at moisture content slightly below optimum.)
2. Submerged to approximate saturation.
3. Slight rebound after saturation.
4. Sample disturbance observed.



PROJECT: **MADRID STORMWATER**
JOB NO.: **32-223560-0**

SOIL PROPERTIES

PLATE

B-1

Boring No.	Depth (ft.)	USCS (AASHTO)	Initial Dry Density (pcf)	Initial Water Content (%)	Compression Properties			Expansion Properties		Plasticity		Soluble Chloride (ppm)	Soluble Sulfate (ppm)	Remarks	
					Surcharge (ksf)	Total Compression (%)		Surcharge (ksf)	Expansion (%)	Liquid Limit	Plasticity Index				
						In-Situ	After Saturation								
5	5-6	COAL (A-1-a(0))	77	5.6	0.5	1.6									
					1.0	2.1									
					2.0	3.1									4.6
					4.0										6.7
														2	
5	0-5	COAL (A-1-a(0))										ND	2200		
7	5-6	CL (A-6(9))	95	8.9				0.1	0.4					1,2	
7	5-6	CL (A-6(9))	95	8.9	0.6	1.5	6.4							2	
					1.1		9.1					2			
					2.2		12.7					2			
					4.4		16.5					2			
9	2-3	SP-SM (A-1-b(0))	46	10.3	0.6	2.6									
					1.1	3.7									
					2.2	5.7	7.3					2			
					4.4		10.4					2			

Note: Initial Dry Density and Initial Water Content are in-situ values unless otherwise noted.
NP = Non-Plastic

Remarks

1. Compacted density (approx. 95% of ASTM D1557 max. density at moisture content slightly below optimum.)
2. Submerged to approximate saturation.
3. Slight rebound after saturation.
4. Sample disturbance observed.



PROJECT: MADRID STORMWATER
JOB NO.: 32-223560-0

SOIL PROPERTIES

PLATE
B-2

Boring No.	Depth (ft.)	USCS Class.	Initial Dry Density (pcf)	Initial Water Content (%)	Compression Properties			Expansion Properties		Plasticity		Soluble Chloride (ppm)	Soluble Sulfate (ppm)	Minimum Resistivity (OHM-CM)	pH	Remarks
					Surcharge (ksf)	Total Compression (%)		Surcharge (ksf)	Expansion (%)	Liquid Limit	Plasticity Index					
						In-Situ	After Saturation									
5	0-5	COAL		9.4						NV	NP	ND	2200	1400	8	
5	5-6	COAL	77	5.6	0.5	1.6										
					1.0	2.1										
					2.0	3.1	4.6									2
					4.0		6.7									2
7	5-6	CL	95	8.9				0.1	0.4							1,2
7	5-6	CL	95	8.9	0.6	1.5	6.4									2
					1.1		9.1									2
					2.2		12.7									2
					4.4		16.5									2
9	2-3	COAL	46	10.3	0.6	2.6										
					1.1	3.7										
					2.2	5.7	7.3									2
					4.4		10.4									2

Note: Initial Dry Density and Initial Water Content are in-situ values unless otherwise noted.

NP = Non-Plastic

Remarks

1. Compacted density (approx. 95% of ASTM D1557 max. density at moisture content slightly below optimum.)
2. Submerged to approximate saturation.
3. Slight rebound after saturation.
4. Sample disturbance observed.



PROJECT: **MADRID STORMWATER**
JOB NO.: **32-223560-0**

SOIL PROPERTIES

PLATE

B-2

SOIL PROPERTIES																			
Boring No.	Depth (ft.)	Soil Class (AASHTO)	Particle Size Distribution - (%) Passing by Weight														Plasticity		Remarks
			1¼"	1"	¾"	½"	3/8"	#4	#8	#10	#16	#30	#40	#50	#100	#200	L L	P I	
1	0-5	CH (A-7-6(27))	-	100	97	96	96	94	92	91	90	89	88	87	83	78	56	33	
2	0-5	SC (A-6(7))	-	-	100	99	98	91	84	83	77	72	70	69	56	49	39	23	
3	0-5	SC (A-2-6(0))	-	100	93	84	78	65	54	52	45	42	40	36	29	28	29	13	
4	0-5	SM (A-1-b(0))	-	100	88	85	77	66	60	59	55	50	46	42	30	19	NV	NP	
5	0-5	COAL (A-1-a(0))	-	100	95	88	79	53	37	34	27	21	18	16	12	8.8	NV	NP	
6	0-5	SM (A-1-b(0))	-	100	93	86	80	68	57	55	46	37	32	28	19	13	NV	NP	
6	15-16.5	SC (A-2-6(0))	-	100	97	91	88	72	55	52	42	35	32	29	24	20	29	14	
7	0-5	CL (A-6(9))	-	-	100	98	96	91	86	85	81	78	76	73	65	57	39	21	

Note: NP = Non-Plastic

Samples obtained excluded cobbles and boulders.



PROJECT: MADRID STORMWATER

JOB NO.: 32-223560-0

SOIL PROPERTIES

PLATE

B-3

SOIL PROPERTIES																			
Boring No.	Depth (ft.)	Soil Class (AASHTO)	Particle Size Distribution - (%) Passing by Weight														Plasticity		Remarks
			1¼"	1"	¾"	½"	3/8"	#4	#8	#10	#16	#30	#40	#50	#100	#200	L L	P I	
8	0-5	SC (A-6(3))	-	100	91	88	87	83	76	75	70	63	60	56	47	40	40	20	
9	0-5	SP-SM (A-1-b(0))	-	-	100	98	95	83	61	58	45	33	27	23	16	12	NV	NP	
10	0-5	SM (A-2-4(0))	-	-	100	97	96	92	85	84	79	71	64	57	34	19	NV	NP	
11	0-5	SM (A-1-b(0))	-	100	89	86	81	75	68	67	61	54	48	43	31	21	NV	NP	
12	0-5	SC (A-6(5))	-	-	100	97	95	91	85	84	79	72	69	64	55	48	40	19	
13	0-5	SC (A-6(5))	-	-	100	97	95	95	91	85	84	76	72	69	65	55	40	19	
14	0-5	SC (A-2-4(0))	-	100	96	89	80	70	62	61	56	50	44	41	34	29	27	10	
15	0-4	COAL (A-1-b(0))	-	-	100	97	94	84	71	68	56	43	37	32	23	17	NV	NP	

Note: NP = Non-Plastic

Samples obtained excluded cobbles and boulders.



PROJECT: MADRID STORMWATER

JOB NO.: 32-223560-0

SOIL PROPERTIES

PLATE

B-4

SOIL PROPERTIES																			
Boring No.	Depth (ft.)	Soil Class (AASHTO)	Particle Size Distribution - (%) Passing by Weight														Plasticity		Remarks
			1¼"	1"	¾"	½"	3/8"	#4	#8	#10	#16	#30	#40	#50	#100	#200	L L	P I	
15	4-5	SP-SM (A-1-b(0))	-	100	98	96	95	82	62	57	44	31	26	22	16	12	NV	NP	
16	0-5	SM (A-1-b(0))	-	100	89	85	80	67	57	55	49	41	37	34	25	16	NV	NP	

Note: NP = Non-Plastic
 Samples obtained excluded cobbles and boulders.



PROJECT: MADRID STORMWATER
 JOB NO.: 32-223560-0

SOIL PROPERTIES

PLATE
B-5

CALIFORNIA BEARING RATIO (CBR) Boring 10 (0'-5')

Client: State of New Mexico EMNRD
Address:
City, State: Madrid, New Mexico
Attn: Leeland Murray

Job Number: 32-223560-0
Lab Number:
Report Date:

Project: Madrid Stormwater & Erosion Control
Location: Madrid, New Mexico
Material:
Source: B 10 (0-5')

Authorized By:
Sampled By:
Submitted By:
Date:
Date:
Date:



Moisture Density Relationship

Procedure: ASTM D1557 Method: A
Maximum Dry Density, pcf: 109.5
Optimum Moisture, %: 12.0

Compacted Specimen Results

Procedure: ASTM D1883

Compactive Effort (Blows per Layer):	10	25	56
Dry Density at Compaction, pcf:	96.2	102.3	107.8
Percent of Maximum Dry Density:	87.9	93.4	98.4
Percent Moisture Before Compaction:	11.1	11.8	11.9
Percent Moisture After Compaction:	11.1	12.0	11.8
Percent Moisture after Soaking (Avg. of Total Sample):	18.1	15.3	11.9
Dry Density after Soaking, pcf:	97.9	104.4	110.9
Percent Moisture after Soaking (Top 1 in.):	19.0	16.1	11.9
Swell, %:	0.0	0.0	0.0
Corrected CBR at 0.100 in. Penetration:	7	21	55
Corrected CBR at 0.200 in. Penetration:	7	19	63
Surcharge Weight, lbs.:	10	10	10
California Bearing Ratio (CBR) at 95% Relative Compaction:	32		



PROJECT: MADRID STORMWATER & EROSION CONTROL IMPROVEMENT
JOB NO.: 32-223560-0

CALIFORNIA BEARING RATIO

PLATE

B-5

CALIFORNIA BEARING RATIO (CBR)

Boring 11 (0'-5')



CALIFORNIA BEARING RATIO (CBR)

Client: State of New Mexico EMNRD	Job Number: 32-223560-0
Address:	Lab Number:
City, State: Madrid, New Mexico	Report Date:
Attn: Leeland Murray	

Project: Madrid Stormwater & Erosion Control	Authorized By:	Date:
Location: Madrid, New Mexico	Sampled By:	Date:
Material:	Submitted By:	Date:
Source: B 11 (0-5')		

Moisture Density Relationship		
Procedure: ASTM D1557	Method: A	
Maximum Dry Density, pcf: 118.7		
Optimum Moisture, %: 9.3		

Compacted Specimen Results	Procedure: ASTM D1883		
Compactive Effort (Blows per Layer):	10	25	56
Dry Density at Compaction, pcf:	104.3	111.7	116.3
Percent of Maximum Dry Density:	87.9	94.1	98.0
Percent Moisture Before Compaction:	8.6	10.0	8.7
Percent Moisture After Compaction:	8.8	9.9	9.0
Percent Moisture after Soaking (Avg. of Total Sample):	17.8	14.4	12.7
Dry Density after Soaking, pcf:	104.4	111.5	116.8
Percent Moisture after Soaking (Top 1 in.):	20.4	15.4	14.3
Swell, %:	0.1	0.1	0.0
Corrected CBR at 0.100 in. Penetration:	3	16	49
Corrected CBR at 0.200 in. Penetration:	3	16	54
Surcharge Weight, lbs.:	10	10	10
California Bearing Ratio (CBR) at 95% Relative Compaction:	24		



PROJECT: **MADRID STORMWATER & EROSION CONTROL IMPROVEMENT**
 JOB NO.: **32-223560-0**

CALIFORNIA BEARING RATIO

PLATE

B-6

CALIFORNIA BEARING RATIO (CBR)



Boring 14 (0'-5')

Client: State of New Mexico EMNRD	Job Number: 32-223560-0
Address:	Lab Number:
City, State: Madrid, New Mexico	Report Date:
Attn: Leeland Murray	

Project: Madrid Stormwater & Erosion Control	Authorized By:	Date:
Location: Madrid, New Mexico	Sampled By:	Date:
Material:	Submitted By:	Date:
Source: B 14 (0-5')		

Moisture Density Relationship		
Procedure: ASTM D1557	Method: C	
Maximum Dry Density, pcf: 129.8		
Optimum Moisture, %: 8.2		

Compacted Specimen Results	Procedure: ASTM D1883		
Compactive Effort (Blows per Layer):	10	25	56
Dry Density at Compaction, pcf:	113.5	122.2	126.7
Percent of Maximum Dry Density:	87.4	94.2	97.6
Percent Moisture Before Compaction:	7.7	7.6	7.8
Percent Moisture After Compaction:	7.9	7.7	8.1
Percent Moisture after Soaking (Avg. of Total Sample):	14.3	13.6	12.9
Dry Density after Soaking, pcf:	112.7	123.6	124.3
Percent Moisture after Soaking (Top 1 in.):	15.6	15.2	14.6
Swell, %:	0.1	0.1	0.2
Corrected CBR at 0.100 in. Penetration:	4	13	32
Corrected CBR at 0.200 in. Penetration:	4	14	41
Surcharge Weight, lbs.:	10	10	10
California Bearing Ratio (CBR) at 95% Relative Compaction:	17		



PROJECT: **MADRID STORMWATER & EROSION CONTROL IMPROVEMENT**
 JOB NO.: **32-223560-0**

CALIFORNIA BEARING RATIO

PLATE

B-6

CALIFORNIA BEARING RATIO (CBR)

Boring 15 (0'-5')

CALIFORNIA BEARING RATIO (CBR)

Client: State of New Mexico EMNRD
Address:
City, State: Madrid, New Mexico
Attn: Leeland Murray

Job Number: 32-223560-0
Lab Number:
Report Date:

Project: Madrid Stormwater & Erosion Control
Location: Madrid, New Mexico
Material:
Source: B 15 (0-5')

Authorized By:
Sampled By:
Submitted By:
Date:



Moisture Density Relationship

Procedure: ASTM D1557 Method: A
Maximum Dry Density, pcf: 95.6
Optimum Moisture, %: 14.8

Compacted Specimen Results

Procedure: ASTM D1883

Compactive Effort (Blows per Layer):	10	25	56
Dry Density at Compaction, pcf:	84.2	89.5	93.0
Percent of Maximum Dry Density:	88.1	93.6	97.3
Percent Moisture Before Compaction:	15.1	14.9	16.1
Percent Moisture After Compaction:	15.0	14.8	14.7
Percent Moisture after Soaking (Avg. of Total Sample):	20.5	17.0	15.4
Dry Density after Soaking, pcf:	85.8	90.6	94.6
Percent Moisture after Soaking (Top 1 in.):	21.6	18.0	16.1
Swell, %:	0.0	0.0	0.0
Corrected CBR at 0.100 in. Penetration:	6	20	32
Corrected CBR at 0.200 in. Penetration:	7	27	47
Surcharge Weight, lbs.:	10	10	10
California Bearing Ratio (CBR) at 95% Relative Compaction:	24		



PROJECT: MADRID STORMWATER & EROSION CONTROL IMPROVEMENT
JOB NO.: 32-223560-0

CALIFORNIA BEARING RATIO

PLATE

B-8

CALIFORNIA BEARING RATIO (CBR)

Boring 16 (0'-5')

CALIFORNIA BEARING RATIO (CBR)

Client: State of New Mexico EMNRD	Job Number: 32-223560-0
Address:	Lab Number:
City, State: Madrid, New Mexico	Report Date:
Attn: Leeland Murray	

Project: Madrid Stormwater & Erosion Control	Authorized By:	Date:
Location: Madrid, New Mexico	Sampled By:	Date:
Material:	Submitted By:	Date:
Source: B 16 (0-5')		



Moisture Density Relationship

Procedure: ASTM D1557 Method: A
Maximum Dry Density, pcf: 110.6
Optimum Moisture, %: 13.8

Compacted Specimen Results

Procedure: ASTM D1883

Compactive Effort (Blows per Layer):	10	25	56
Dry Density at Compaction, pcf:	97.0	101.8	106.4
Percent of Maximum Dry Density:	87.7	92.1	96.2
Percent Moisture Before Compaction:	14.7	14.9	14.8
Percent Moisture After Compaction:	14.3	14.6	14.8
Percent Moisture after Soaking (Avg. of Total Sample):	27.8	25.7	23.5
Dry Density after Soaking, pcf:	91.8	99.3	103.3
Percent Moisture after Soaking (Top 1 in.):	30.5	28.6	27.5
Swell, %:	0.4	0.4	0.4
Corrected CBR at 0.100 in. Penetration:	0	2	3
Corrected CBR at 0.200 in. Penetration:	0	2	4
Surcharge Weight, lbs.:	10	10	10
California Bearing Ratio (CBR) at 95% Relative Compaction:	3		



PROJECT: MADRID STORMWATER & EROSION CONTROL IMPROVEMENT
JOB NO.: 32-223560-0

CALIFORNIA BEARING RATIO

PLATE

B-9

CALIFORNIA BEARING RATIO (CBR)

Boring 13 (0'-5')

CALIFORNIA BEARING RATIO (CBR)

Client: State of New Mexico EMNRD
Address:
City, State: Madrid, New Mexico
Attn: Leeland Murray

Job Number: 32-223560-0
Lab Number:
Report Date:

Project: Madrid Stormwater & Erosion Control
Location: Madrid, New Mexico
Material:
Source: B 13 (0-5')

Authorized By:
Sampled By:
Submitted By:
Date:



Moisture Density Relationship

Procedure: ASTM D1557 Method: A
Maximum Dry Density, pcf: 103.5
Optimum Moisture, %: 12.7

Compacted Specimen Results

Procedure: ASTM D1883

Compactive Effort (Blows per Layer):	10	25	56
Dry Density at Compaction, pcf:	90.9	99.1	100.6
Percent of Maximum Dry Density:	87.9	95.8	97.2
Percent Moisture Before Compaction:	11.1	12.4	11.5
Percent Moisture After Compaction:	11.1	12.2	11.7
Percent Moisture after Soaking (Avg. of Total Sample):	19.4	16.7	14.3
Dry Density after Soaking, pcf:	90.1	97.3	101.5
Percent Moisture after Soaking (Top 1 in.):	20.1	17.7	16.1
Swell, %:	0.0	0.0	0.0
Corrected CBR at 0.100 in. Penetration:	6	13	28
Corrected CBR at 0.200 in. Penetration:	6	19	32
Surcharge Weight, lbs.:	10	10	10
California Bearing Ratio (CBR) at 95% Relative Compaction:	12		



PROJECT: MADRID STORMWATER & EROSION CONTROL IMPROVEMENT
JOB NO.: 32-223560-0

CALIFORNIA BEARING RATIO

PLATE


B-10

Client **STATE OF NEW MEXICO EMNRD**
1220 SOUTH ST FRANCIS DRIVE
SANTA FE , NM

Date of Report **03/26/24**
Job No. **32-223560-0**
Event No. **10 (0-5)**
Authorized By **A. Kaba**
Sample Location Designated By
Sampled By **S. O'Herron-Alex**
Submitted By **L. Anderson**

Page **1** of **1**
Lab No. **50535**
Date **01/17/24**
Date
Date **01/17/24**
Date **03/26/24**

Project **MADRID STORMWATER AND EROSION CONTROL PROJECT**
Project Address **ICE HOUSE ROAD TO FIREHOUSE LANE - MADRID, NM**
Material Description **A-2-4 (0)**
Material Use **Silty SAND**
Material Source **B 10 (0-5')**
Sample Location
Special Instructions

Sieve analysis AASHTO T27 Non-Referee Finer Than No. 200 AASHTO T11, Procedure A			Laboratory compaction characteristics ASTM D1557 Method A	
Sieve	Accumulative % passing	Specification	Dry unit weight, lb/ft³ 	
6 in.				
4 in.				
3 in.				
2 in.				
1-1/2 in.				
1 in.				
3/4 in.	100			
1/2 in.	97			
3/8 in.	96			
1/4 in.	95			
No. 4	92			
No. 8	85			
No. 10	84			
No. 16	79			
No. 30	71			
No. 40	64			
No. 50	57			
No. 100	34			
No. 200	19			
			Sample Preparation Moist Rammer Used Mechanical Proctor curve Id. No. 3 Maximum dry unit weight, lb/ft³ 109.5 Optimum water content, % 12.0 Oversize Aggregate Assumed bulk specific gravity 2.60 Assumed absorption, % 1.0 Oversize in laboratory sample, % 0	
			Result	Specs.
Liquid Limit, Plastic Limit & Plasticity Index			Los Angeles (LA) Abrasion Grading rev., % loss Grading rev., % loss	
Preparation method Oven-dried			Fractured Faces By Weight	
Processing method ASTM D4318, Dry Preparation			One or more, %	
Liquid Limit ASTM D4318, Method B LL NV			Two or more, %	
Plastic Limit ASTM D4318 PL NP			Total Salts (Solubility)	
Plasticity Index ASTM D4318 PI NP			%	
Water Content AASHTO T265 % dry weight 18.1			Sulfates	
Swell Test Surcharge psf Expansion, %			Chlorides	
Compacted to approximately of ASTM Method			pH Determination pH	
Initial water content % Dry unit weight lb/ft ³			Minimum Resistivity ohm-cm	
Organic Matter %			Expansion Index of Soil EI	
Unified Soil Classification AASHTO M145			Initial dry unit weight, lb/ft ³	
Group Symbol: A-2-4(0) Name: Silty Sand			Initial degree of saturation	
			Initial water content, %	
			Final water content, %	

Comments:


The services referred to herein were performed in accordance with the standard of care practiced locally for the referenced method(s) and relate only to the condition(s) observed or sample(s) tested at the time and place stated herein. Western Technologies Inc. (WT) makes no other warranty or representation, express or implied, and has not confirmed information including source of materials submitted by others. This report shall not be reproduced, except in full, without the prior written approval of WT.

Client **STATE OF NEW MEXICO EMNRD**
1220 SOUTH ST FRANCIS DRIVE
SANTA FE , NM

Date of Report **03/26/24**
Job No. **32-223560-0**
Event No. **11 (0-5)**
Authorized By **A. Kaba**
Sample Location Designated By
Sampled By **S. O'Herron-Alex**
Submitted By **L. Anderson**

Page **1** of **1**
Lab No. **50518**
Date **01/17/24**
Date
Date **01/17/24**
Date **03/26/24**

Project **MADRID STORMWATER AND EROSION CONTROL PROJECT**
Project Address **ICE HOUSE ROAD TO FIREHOUSE LANE, MADRID, NM**
Material Description **A-1-b (0)**
Material Use **Silty SAND with Gravel**
Material Source **B 11 (0-5)**
Sample Location **B 11 (0-5)**
Special Instructions

Sieve analysis AASHTO T27 Non-Referee Finer Than No. 200 AASHTO T11, Procedure A			Laboratory compaction characteristics ASTM D1557 Method C						
Sieve	Accumulative % passing	Specification	Dry unit weight, lb/ft³  Sample Preparation Moist Rammer Used Mechanical Proctor curve Id. No. 1 Maximum dry unit weight, lb/ft³ 118.7 Optimum water content, % 9.3 Oversize Aggregate Assumed bulk specific gravity 2.60 Assumed absorption, % 1.0 Oversize in laboratory sample, % 0						
6 in.									
4 in.									
3 in.									
2 in.									
1-1/2 in.									
1 in.	100								
3/4 in.	89								
1/2 in.	86								
3/8 in.	81								
1/4 in.	78								
No. 4	75								
No. 8	68								
No. 10	67								
No. 16	61								
No. 30	53								
No. 40	48								
No. 50	43								
No. 100	31								
No. 200	21								
			Result	Specs.			Result	Specs.	
Liquid Limit, Plastic Limit & Plasticity Index			NV		Los Angeles (LA) Abrasion	Grading rev., % loss			
Preparation method Oven-dried					Grading	rev., % loss			
Processing method ASTM D4318, Dry Preparation					Fractured Faces By Weight		One or more, %		
Liquid Limit ASTM D4318, Method B							Two or more, %		
Plastic Limit ASTM D4318									
Plasticity Index ASTM D4318									
Water Content AASHTO T265 % dry weight			11.3		Sulfates		%		
Swell Test Surcharge psf Expansion, %					Chlorides				
Compacted to approximately of ASTM Method					pH Determination		pH		
Initial water content % Dry unit weight lb/ft³					Minimum Resistivity		ohm-cm		
Organic Matter %					Expansion Index of Soil		EI		
Unified Soil Classification AASHTO M145						Initial dry unit weight, lb/ft³			
Group Symbol: A-1-b(0) Name: Silty Sand with Gravel						Initial degree of saturation			
						Initial water content, %		Final water content, %	

Comments:


The services referred to herein were performed in accordance with the standard of care practiced locally for the referenced method(s) and relate only to the condition(s) observed or sample(s) tested at the time and place stated herein. Western Technologies Inc. (WT) makes no other warranty or representation, express or implied, and has not confirmed information including source of materials submitted by others. This report shall not be reproduced, except in full, without the prior written approval of WT.

Client **STATE OF NEW MEXICO EMNRD**
1220 SOUTH ST FRANCIS DRIVE
SANTA FE , NM

Date of Report **03/26/24**
Job No. **32-223560-0**
Event No. **13 (0-5)**
Authorized By **A. Kaba**
Sample Location Designated By
Sampled By **S. O'Herron-Alex**
Submitted By **L. Anderson**

Page **1** of **1**
Lab No. **50773**
Date **01/17/24**
Date
Date **01/17/24**
Date **03/26/24**

Project **MADRID STORMWATER AND EROSION CONTROL PROJECT**
Project Address **ICE HOUSE ROAD TO FIREHOUSE LANE, MADRID, NM**
Material Description **A-6 (5)**
Material Use **Clayey SAND**
Material Source **B 13 (0-5')**
Sample Location
Special Instructions

Sieve analysis AASHTO T27 Non-Referee Finer Than No. 200 AASHTO T11, Procedure A			Laboratory compaction characteristics ASTM D1557 Method A			
Sieve	Accumulative % passing	Specification	Dry unit weight, lbf/ft³  Sample Preparation Moist Rammer Used Manual Proctor curve Id. No. 6 Maximum dry unit weight, lbf/ft³ 103.5 Optimum water content, % 12.7 Oversize Aggregate Assumed bulk specific gravity 2.60 Assumed absorption, % 1.0 Oversize in laboratory sample, % 0			
6 in.						
4 in.						
3 in.						
2 in.						
1-1/2 in.						
1 in.						
3/4 in.	100					
1/2 in.	97					
3/8 in.	95					
1/4 in.	95					
No. 4	91					
No. 8	85					
No. 10	84					
No. 16	79					
No. 30	72					
No. 40	69					
No. 50	64					
No. 100	55					
No. 200	48					
			Result	Specs.	Result	Specs.
Liquid Limit, Plastic Limit & Plasticity Index					Los Angeles (LA) Abrasion	Grading rev., % loss
Preparation method Oven-dried						Grading rev., % loss
Processing method ASTM D4318, Dry Preparation					Fractured Faces By Weight One or more, %	
Liquid Limit ASTM D4318, Method B LL 40					Two or more, %	
Plastic Limit ASTM D4318 PL 21					Total Salts (Solubility) %	
Plasticity Index ASTM D4318 PI 19					Sulfates %	
Water Content AASHTO T265 % dry weight 14.4					Chlorides	
Swell Test Surcharge psf Expansion, %					pH Determination pH	
Compacted to approximately of ASTM Method					Minimum Resistivity ohm-cm	
Initial water content % Dry unit weight lbf/ft ³					Expansion Index of Soil EI	
Organic Matter %					Initial dry unit weight, lbf/ft ³	
Unified Soil Classification AASHTO M145					Initial degree of saturation	
Group Symbol: A-6(5) Name: Clayey Sand					Initial water content, % Final water content, %	

Comments:


The services referred to herein were performed in accordance with the standard of care practiced locally for the referenced method(s) and relate only to the condition(s) observed or sample(s) tested at the time and place stated herein. Western Technologies Inc. (WT) makes no other warranty or representation, express or implied, and has not confirmed information including source of materials submitted by others. This report shall not be reproduced, except in full, without the prior written approval of WT.

Client **STATE OF NEW MEXICO EMNRD**
1220 SOUTH ST FRANCIS DRIVE
SANTA FE , NM

Date of Report **03/26/24**
Job No. **32-223560-0**
Event No. **14 (0-5)**
Authorized By **A. Kaba**
Sample Location Designated By
Sampled By **S. O'Herron-Alex**
Submitted By **L. Anderson**

Page **1** of **1**
Lab No. **50534**
Date **01/17/24**
Date
Date **01/17/24**
Date **03/26/24**

Project **MADRID STORMWATER AND EROSION CONTROL PROJECT**
Project Address **ICE HOUSE ROAD TO FIREHOUSE LANE, MADRID, NM**
Material Description **A-2-4 (0)**
Material Use **Clayey SAND with Gravel**
Material Source **B 14 (0-5')**
Sample Location
Special Instructions

Sieve analysis AASHTO T27 Non-Referee Finer Than No. 200 AASHTO T11, Procedure A			Laboratory compaction characteristics ASTM D1557 Method C			
Sieve	Accumulative % passing	Specification	Dry unit weight, lbf/ft³ 			
6 in.						
4 in.						
3 in.						
2 in.						
1-1/2 in.						
1 in.	100					
3/4 in.	96					
1/2 in.	86					
3/8 in.	80					
1/4 in.	79					
No. 4	70					
No. 8	62					
No. 10	61					
No. 16	56					
No. 30	50					
No. 40	44					
No. 50	41					
No. 100	29					
No. 200	29					
			Sample Preparation Moist Rammer Used Mechanical Proctor curve Id. No. 2 Maximum dry unit weight, lbf/ft³ 129.8 Optimum water content, % 8.2 Oversize Aggregate Assumed bulk specific gravity 2.60 Assumed absorption, % 1.0 Oversize in laboratory sample, % 0			
			Result	Specs.	Result	Specs.
Liquid Limit, Plastic Limit & Plasticity Index			Los Angeles (LA) Abrasion Grading rev., % loss Grading rev., % loss			
Preparation method Oven-dried			Fractured Faces By Weight			
Processing method ASTM D4318, Dry Preparation			One or more, %			
Liquid Limit ASTM D4318, Method B LL 27			Two or more, %			
Plastic Limit ASTM D4318 PL 17			Total Salts (Solubility)			
Plasticity Index ASTM D4318 PI 10			%			
Water Content AASHTO T265 % dry weight 7.0			Sulfates			
Swell Test Surcharge psf Expansion, %			Chlorides			
Compacted to approximately of ASTM Method			pH Determination pH			
Initial water content % Dry unit weight lbf/ft ³			Minimum Resistivity ohm-cm			
Organic Matter %			Expansion Index of Soil EI			
Unified Soil Classification AASHTO M145			Initial dry unit weight, lbf/ft ³			
Group Symbol: A-2-4(0) Name: Clayey Sand with Gravel			Initial degree of saturation			
			Initial water content, % Final water content, %			

Comments:


The services referred to herein were performed in accordance with the standard of care practiced locally for the referenced method(s) and relate only to the condition(s) observed or sample(s) tested at the time and place stated herein. Western Technologies Inc. (WT) makes no other warranty or representation, express or implied, and has not confirmed information including source of materials submitted by others. This report shall not be reproduced, except in full, without the prior written approval of WT.

Client **STATE OF NEW MEXICO EMNRD**
1220 SOUTH ST FRANCIS DRIVE
SANTA FE , NM

Date of Report **03/26/24**
Job No. **32-223560-0**
Event No. **15 (0-5)**
Authorized By **A. Kaba**
Sample Location Designated By
Sampled By **S. O'Herron-Alex**
Submitted By **L. Anderson**

Page **1** of **1**
Lab No. **50638**
Date **01/17/24**
Date
Date **01/17/24**
Date **03/26/24**

Project **MADRID STORMWATER AND EROSION CONTROL PROJECT**
Project Address **ICE HOUSE ROAD TO FIREHOUSE LANE, MADRID, NM**
Material Description **A-1-b (0)**
Material Use **Silty SAND with Gravel**
Material Source **B 15 (0-5')**
Sample Location
Special Instructions

Sieve analysis AASHTO T27 Non-Referee Finer Than No. 200 AASHTO T11, Procedure A			Laboratory compaction characteristics ASTM D1557 Method A	
Sieve	Accumulative % passing	Specification	Dry unit weight, lb/ft³ 	
6 in.				
4 in.				
3 in.				
2 in.				
1-1/2 in.				
1 in.				
3/4 in.	100			
1/2 in.	97			
3/8 in.	94			
1/4 in.	93			
No. 4	84			
No. 8	71			
No. 10	68			
No. 16	56			
No. 30	43			
No. 40	37			
No. 50	32			
No. 100	23			
No. 200	17			
			Sample Preparation Moist Rammer Used Manual Proctor curve Id. No. 5 Maximum dry unit weight, lb/ft³ 95.6 Optimum water content, % 14.8 Oversize Aggregate Assumed bulk specific gravity 2.60 Assumed absorption, % 1.0 Oversize in laboratory sample, % 0	
Liquid Limit, Plastic Limit & Plasticity Index			Result	Specs.
Preparation method Oven-dried				
Processing method ASTM D4318, Dry Preparation				
Liquid Limit ASTM D4318, Method B LL NV			Los Angeles (LA) Abrasion	Grading rev., % loss
Plastic Limit ASTM D4318 PL NP			Grading	rev., % loss
Plasticity Index ASTM D4318 PI NP			Fractured Faces By Weight	One or more, %
Water Content AASHTO T265 % dry weight 12.5				Two or more, %
Swell Test Surcharge psf Expansion, %			Total Salts (Solubility)	%
Compacted to approximately of ASTM Method			Sulfates	%
Initial water content % Dry unit weight lb/ft ³			Chlorides	
Organic Matter %			pH Determination	pH
Unified Soil Classification AASHTO M145			Minimum Resistivity	ohm-cm
Group Symbol: A-1-b(0) Name: Silty Sand with Gravel			Expansion Index of Soil	EI
			Initial dry unit weight, lb/ft ³	
			Initial degree of saturation	
			Initial water content, %	Final water content, %

Comments:


The services referred to herein were performed in accordance with the standard of care practiced locally for the referenced method(s) and relate only to the condition(s) observed or sample(s) tested at the time and place stated herein. Western Technologies Inc. (WT) makes no other warranty or representation, express or implied, and has not confirmed information including source of materials submitted by others. This report shall not be reproduced, except in full, without the prior written approval of WT.

Client **STATE OF NEW MEXICO EMNRD**
1220 SOUTH ST FRANCIS DRIVE
SANTA FE , NM

Date of Report **03/26/24**
Job No. **32-223560-0**
Event No. **16 (0-5)**
Authorized By **A. Kaba**
Sample Location Designated By
Sampled By **S. O'Herron-Alex**
Submitted By **L. Anderson**


Page **1** of **1**
Lab No. **50609**
Date **01/17/24**
Date
Date **01/17/24**
Date **03/26/24**

Project **MADRID STORMWATER AND EROSION CONTROL PROJECT**
Project Address **ICE HOUSE ROAD TO FIREHOUSE LANE, MADRID, NM**
Material Description **A-1-b (0)**
Material Use **Silty SAND with Gravel**
Material Source **B 16 (0-5')**
Sample Location
Special Instructions

Sieve analysis AASHTO T27 Non-Referee Finer Than No. 200 AASHTO T11, Procedure A			Laboratory compaction characteristics ASTM D1557 Method A					
Sieve	Accumulative % passing	Specification	Dry unit weight, lbf/ft³  Sample Preparation Moist Rammer Used Manual Proctor curve Id. No. 4 Maximum dry unit weight, lbf/ft³ 110.6 Optimum water content, % 13.8 Oversize Aggregate Assumed bulk specific gravity 2.60 Assumed absorption, % 1.0 Oversize in laboratory sample, % 0					
6 in.								
4 in.								
3 in.								
2 in.								
1-1/2 in.								
1 in.	100							
3/4 in.	89							
1/2 in.	85							
3/8 in.	80							
1/4 in.	80							
No. 4	67							
No. 8	57							
No. 10	55							
No. 16	49							
No. 30	41							
No. 40	37							
No. 50	34							
No. 100	25							
No. 200	16							
			Result	Specs.			Result	Specs.
Liquid Limit, Plastic Limit & Plasticity Index			NV	NP	Los Angeles (LA) Abrasion	Grading rev., % loss		
Preparation method Oven-dried					Grading rev., % loss			
Processing method ASTM D4318, Dry Preparation					Fractured Faces By Weight	One or more, %		
Liquid Limit ASTM D4318, Method B					Two or more, %			
Plastic Limit ASTM D4318					Total Salts (Solubility)	%		
Plasticity Index ASTM D4318					Sulfates	%		
Water Content AASHTO T265 % dry weight			10.1		Chlorides			
Swell Test Surcharge psf Expansion, %					pH Determination	pH		
Compacted to approximately of ASTM Method					Minimum Resistivity	ohm-cm		
Initial water content % Dry unit weight lbf/ft³					Expansion Index of Soil	EI		
Organic Matter %					Initial dry unit weight, lbf/ft³			
Unified Soil Classification AASHTO M145					Initial degree of saturation			
Group Symbol: A-1-b(0) Name: Silty Sand with Gravel					Initial water content, %	Final water content, %		






Comments:

The services referred to herein were performed in accordance with the standard of care practiced locally for the referenced method(s) and relate only to the condition(s) observed or sample(s) tested at the time and place stated herein. Western Technologies Inc. (WT) makes no other warranty or representation, express or implied, and has not confirmed information including source of materials submitted by others. This report shall not be reproduced, except in full, without the prior written approval of WT.




AVS = 1616.9 ft/s

Site Classification is Class C



B	11/4/24		100% FINAL				
C	3/27/25		FOR-BID				
NO.	DATE	APPR.	REVISION	NO.	DATE	APPR.	REVISION

VILLAGE OF MADRID, NM STORM WATER & EROSION CONTROL PROJECT	
MADRID	NEW MEXICO
	
ALBUQUERQUE	NEW MEXICO

CHECKED	CP	DATE 10/31/24	CLIENT APPROVALS	DATE
DES. ENG.	CP	10/31/24		
PROJ. ENG.	CP	10/31/24		
PROJ. MGR.	RE	10/31/24		
APPROVED				
APPROVED				

	MADRID ARROYO TYPICAL SECTIONS ROAD, TRAIL, ARROYO				
	DRAWN C. PHILIPS	DATE ----	DWG. NO. C217	REV. C	
	SCALE	W.O. NO. 15740.001.003	SHT. 67 of 83		