


TIN PAN CANYON GOB RECLAMATION PROJECT

RATON, NEW MEXICO PROJECT LOCATION OVERVIEW







INDEX OF FIGURES:

- 1. Title Sheet
- 2. Tin Pan Canyon Plan View
- 3. South Gob Pile Plan View
- 4. North Gob Pile Plan View
- 5. Straw Bale and Erosion Control Wattle Terraces
- 6. Sediment Barrier Dam
- 7. Avoidance and Staging Areas
- 8. Rock Staging Area


Attachment A:


- 1A. NCD Tin Pan Canyon Headcut Stabilization Cover Sheet: Location and Index
- 2A: Project Specifications
- 3A: Project OVerview, Sheet Index, and Quantities
- 4A: Rock Chute Overview & Layout
- 5A: DETAIL: Rock Chute
- 6A: Road Crossing Overview & Layout
- 7A. DETAIL: Rock Check Dams




MINING & MINERALS DIVISION ENERGY, MINERALS AND NATURAL RESOURCES DEPT. SANTA FE. NEW MEXICO

PROJECT NO. EMNRD-MMD-2020-02








TYPICAL SECTION - TYPE "SB"

STRAW BALE TERRACE


(ON SLOPES LESS STEEP THAN 1.5:1)



TYPICAL SECTION — EROSION CONTROL WATTLE TERRACE

ABANDONED MINE LAND PROGRAM MINING AND MINERALS DIVISION NEW MEXICO ENERGY, MINERALS, AND NATURAL RESOURCES DEPARTMENT				
SCALE: NOT TO SCALE		DRAWN BY: JAK		
DATE: 12/11/2019		REVISED BY: YM		
STF	RAW BALE AND EROSION CONTROL WATTLE TERRAC	DES		
TIN PAN CA	NYON GOB RECLAMATION PROJECT	FIGURE: 5		

AWBALE_COIRROLL.DWG PLOT SCALE 1 = 16



SECTION


TYPICAL DETAILS SEDIMENT BARRIER DAMS

NOTE ON SEEDLING PLANTING AT SEDIMENT BARRIER DAMS: SEEDLING PROTECTION TUBES AND MULCH ARE NOT REQUIRED AT SEDIMENT BARRIER DAMS. PLANT SEEDLINGS AT ALL SEDIMENT DAMS, EXCEPT FOR THOSE WHERE EXISTING CHANNEL VEGETATION OR OVERHANGING VEGETATION IS DENSE, AS THE PROJECT MANAGER DIRECTS.


ABANDONED MINE LAND PROGRAM MINING AND MINERALS DIVISION NEW MEXICO ENERGY, MINERALS, AND NATURAL RESOURCES DEPARTMENT		
SCALE: NOT TO SCALE		DRAWN E
DATE: 12/11/2019		REVISED


SEDIMENT BARRIER DAM FIGURE: 6

BY: YM









LOCATION MAP

Lat: 39.94° Long: 104.54°
Tin Pan Canyon, Colfax County, New Mexico

Project Manager: Joe Vinson

New Mexico Department of Energy, Minerals and Natural Resources

Abandoned Mines Land Program

1220 South St. Francis Drive (505) 476-3414 (office) (505) 690-8070 (cell)



Land Owner: Vermejo Park Ranch 40 Miles WEst Hwy 55 Raton, NM 87740

Tin Pan Canyon Headcut Stabilization Project

Prepared for:

New Mexico Department of Energy, Minerals and Resources Abandoned Mines Land Program



Tin Pan Canyon Drainage CONTRIBUTING WATERSHED AREA TO PROJECT SITE: 28 ACRES

INDEX OF DRAWINGS

SHEET NO.	TITLE
1 A	COVER SHEET: Location and Index
2 A	Project Specifications
3 A	Project Overview, Sheet Index, and Quantities
4 A	Rock Chute Overview & Layout
5 A	DETAIL: Rock Chute
6 A	Road Crossing Overview & Layout
7 A	DETAIL: Rock Check Dams

Prepared By:

Natural Channel


Design, Inc

2900 N West Street Sulte #5 Flagstaff, Artzona 86004 Phone: (602) 774-2336

Natural Channel	DRAWN BY: D. HALLORAN & J. FLEISHMAN				
	Design, Inc Designed by: M. K	EARLY			
	REV	DATE	BY	REVISION	
2900 N. West St. Sulte #5 Flagstaff, Arlzona 86004 (928) 774-2336					
	•				

COVER SHEET: Location and Index

Tin Pan Canyon **Headcut Stablization Project**



UNAUTHORIZED CHANGES & USES THE ENGINEER

PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO OR USES OF THESE PLANS. ALL CHANGES MUST BE IN WRITING AND MUST BE APPROVED BY THE PREPARER OF THESE PLANS.

DIAL 811 BEFORE YOU DIG

Ξ	OF THESE FLANS.		
,,,,,,,,	FILE NAME:	D 04 00 04	
	Tin Pan	DATE: 01-28-20	019
	PROJECT NO:	SHEET:	A of 7
	18-306NM	1	n. '

PROJECT DESCRIPTION

The purpose of this project is to arrest a headcut that is advancing through coal gob mine waste and stabilize an associated ranch road drainage crossing on the Vermejo Ranch in Colfax County, NM. The included plans were developed with an understanding that the site is located in a remote location in an actively evolving setting. Additionally, rock materials that will be supplied by the ranch to form a rock—lined chute have not been specifically tested for gradation or size. Given the dynamics of the pre-existing condition and unknowns relative to availability and quality of materials, it is understood that some field adjustments may be necessary during construction but should only be made with prior approval of the Project Manager and the Engineer. The Improvement Plan includes:

- 1. Stabilization of the headcut with rock lined chute.
- 2. Grade road to eliminate erosion and convey runoff into the rock chute.
- 3. Stabilize downstream channel with rock check dams.
- 4. Armor road crossing with rock pad to hold road grade.
- Cleanup and smoothing of disturbed areas
- 6. Seeding and other revegetation work will be completed by the New Mexico Abandoned Mines program after site disturbance and prior to monsoon precipitation.

GENERAL NOTES

- 1. Site topographic survey data was collected by NCD in October 2018.
- 2. All existing conditions are to be verified in the field prior to construction. If differences in the site have occurred in the time between the intitial survey and construction, the engineer shall be consulted for any necessary modifications to the design and plans.
- 3. No representation is made as to the existence or nonexistence of any utilities, public or private. Absence of utilities on these drawings IS NOT assurance that no utilities are present. The existence, location and depth of any utility must be determined by the contractor prior to any excavation. Call New Mexico Blue Stake before you dig to be sure - dial 811.
- 4. No construction shall begin until all necessary permits, easements, and funding authorizations are
- 5. Construction activities will be conducted in a manner consistent with all safety regulations, and other permitting required by New Mexico Mining and Minerals Division, and others.
- 6. Installation shall be constructed to the lines and grades as shown on the drawings or as staked in the field by the ENGINEER or authorized representative, recognizing there is variation in nature.

CONSTRUCTION SPECIFICATIONS

The specifications included herein are provided as a partial list of construction standards and requirements for this project. As a companion to this plan set, a full compilation of applicable technical specifications is provided. The person(s) performing the work shall familiarize themselves with those specifications and contact the engineer prior to starting construction with any questions or for clarification.

EARTHWORK

The earthwork activities shall consist of chute preperation cut and fill, hill slope rehabilitation, chute base construction and spreading of any removed sediment on the slopes adjacent to the chute.

Excavation

Excavation shall be limited to spillway construction and layback of vertical banks at the end of the chute as shown on the drawings and as will be staked in the field. Some excavation will also be required to prepare overly steep existing slopes prior to placing new fill and prior to rock placement. Disturbance of existing native vegetation shall be minimized to the greatest extent possible during excavation.

Excavated material shall be placed in the specified chute subgrade and compacted and hillslope locations as shown on the drawings. All finished surfaces shall be generally smooth and pleasing in appearance and blend into surrounding terrain.

Earthfill

Materials: All fill materials shall be obtained from the required excavations or approved borrow sources. Fill materials shall not contain sod, brush, roots, perishable or frozen materials.

Placement: The placement of fill materials shall follow these guidelines:

- Any vertical bank greater than 30" in height shall be sloped or stepped before placement of fill material. The placing and spreading of fill material shall be started at the lowest point and the fill brought
- up and compacted to obtain a density similar to the surrounding bank material.
- Material, when placed, shall contain sufficient moisture so that a sample taken in the hand and squeezed shall remain intact when released.
- For general fill placement, the placing and spreading of fill material shall be started at the lowest point and the fill brought up in horizontal layers not to exceed: 12"—16" inches of loose fill for compaction with excavator attached compaction wheel. Construction equipment shall
- be operated over the areas of each layer of fill to insure that the required compaction is obtained. Fill shall not be placed on frozen soil, snow or ice or upon vegetation that has not been removed.
- NRCS Specification CS-AZ-23 addresses large scale fill placement and compaction equipment. Smaller equipment and modified methods, as applicable to the equipment used, may be substituted with the approval of the ENGINEER or his representative.
- The ENGINEER or his representative shall be present during all embankment related fill placement.
- Notify the ENGINEER a minimum of 3 working days prior to such activities.

 All finished surfaces shall be generally smooth and pleasing in appearance and blend into surrounding terrain.
- NRCS Specification CS-AZ-23 references testing requirements. The ENGINEER or his representative will be present during chute subgrade related fill placement to ensure proper compaction procedures are followed and relative densities are achieved. However, no specific compaction testing is anticipated to be required. Compaction of the subgrade materails shall be in lifts compatible with the means and methods of compaction used and acheive densities that approximate those of the adjacent undisturbed native earth.

BMPs & REVEGETATION


It is understood that New Mexico Abandoned Mine Land Program will reseed and revegetate all areas where ground work has occured with this project as part of a second project that will rehabilitate and revegetate the adjacent coal gob pile. No reseeding is required by the contractor of this project. It is also understood that any required BMPs and Stormwater Pollution Prevention will also be installed/provided as part of that project.

ROCK LINED CHUTES

The headcut stabilization work shall consist of headcut excavation and bank sloping; installing loose rock including placement of geotextile filter fabric. See the included plan sheets and associated details.

- The site shall be excavated and backfilled to the grades shown on drawings. Excavation shall be limited to the headcut remediation area as shown on the drawings.
- All fill material shall be compacted to the approximate density of surrounding undisturbed areas.
- Additional spoils shall be spread outside the channel and sloped in such a way as to direct flows toward rock—lined chute.
- Disturbance of existing native vegetation shall be minimized.
- Non-woven geotextile shall be placed behind/below the rock. Fabric shall meet the requirements of NRCS MS-AZ-592 Geotextile material specifications for Class III nonwoven geotextiles. The geotextile shall be joined by overlapping a minimum of 18 inches and secured against the underlying foundation material. Securing pins shall be installed as necessary to prevent undue slippage or movement of the geotextile. Recommend 3/16—inch steel bars pointed on one end and fabricated with a head to retain a steel washer. (1.5—inch diameter). Pin length shall be not less than 18 inches. U—shaped pins are acceptable.
- Rock will be provided by the Vermejo Ranch and delivered to the site by the ranch and staged in the open area on the upstream side of the road, above the rock chute construction area.
- Rock should be angular, dense, sound and free from cracks, seams, or other defects conducive to accelerated weathering. The least dimension of an individual rock should not be less than one—half the greatest dimension. Rock source shall be approved by the ENGINEER or authorized representative and have a bulk specific gravity of not less that 2.5 per ASTM C127.
- Rock placement shall begin at the bottom of prepared slope and progress upslope. Rock shall not be dropped more than 3 feet onto geotextile. Some hand sorting may be required during placement to ensure contact between stones.

Natural **DIAL 811** DRAWN BY: D. HALLORAN & J. FLEISHMAN UNAUTHORIZED CHANGES & USES THE ENGINEER **Project Specifications** PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO OR USES OF THESE PLANS. ALL CHANGES MUST BE IN WRITING AND MUST BE APPOVED BY THE PREPARER OF THESE PLANS. Channel **BEFORE** YOU DIG Design, Inc | Designed by: M. Kearly 23330 FILE NAME: REV REVISION DATE BY Tin Pan Canyon DATE: 01-28-2019 Tin Pan 2900 N. West St. Suite #5 PROJECT NO: **Headcut Stablization Project** SHEET: Flagstaff, Arlzona 86004 2A of 7 (928) 774-2336 18-306NM



CONSTRUCTION NOTES

1 Is Prepare chute subgrade for rock placement. Estimated earthwork: 140 cy cut and 120 cy of compacted fill as per Sheets 4, 5 and 6.

2) 158 cy Install rock for chute. Rock to be D50=12 to 18 inch rock and placed 24 inches thick. See rock gradation on this sheet. Underlay all rock with non-woven geotextile fabric meeting NRCS Spec MS-AZ-592. Estimated quantity of 313 sy of geotextile (not including anchor trenches and overlap) See also, details on Sheets 4, 5 and 6.

5 ea Install rock sills using 21 — 36 to 48 inch feature rocks and 27 — 18 to 24 inch footer rocks and 16 cy of cut. Place rock as per included details, Sheet 7.

4) 25 cy Grade approximately 140 If of road as per the typical cross section details, Sheets 4 and 6. Ensure road is graded to collect and direct any water from the adjacenet uphill areas to the rock chute. Estimated earthwork to be included: 21 cy compacted fill per Section B, Sheet 6.

(5) NPI Protect existing pine tree in place.

QUANTITY/MATERIAL NOTES

 All rock is to be supplied by the land owner and will be delivered to the site and staged in the level area on the upstream side of the road crossing prior to project construction.

- Rock chute construction is paid per cubic yard of placement of supplied rock to create the drainage chute.

Unit cost shall include supplying and installing geotextile underlayment and supplying and placing a 4 inch thick layer of sand bedding to protect the fabric below rock and to allow for light equipment traffic. Sand may be concrete sand, cinder sand or 3/8" minus sand bedding per NMDOT Spec. 206.2.3.

- Preparation of the rock chute to súbgrade is paid as a separate lump sum item for the necessary excavation and fill placement to achieve subgrade elevations.

- Earthwork has been designed to approximately balance for the project as a whole. Tie slopes are designed to utilize all available excavation spoils within the project site. Fill tie slopes may be altered between 3:1 and 5:1 as necessary to use or conserve material.

 No accounting for shrinkage or swell has been included in the earthwork volumes. Volumes are for in place native or compacted fill volumes.

Rock sills are paid per each sill placed and shall include all excavation shaping and placement of rocks per the details provided herein. Transport of the rock from the staging area to the individual rock sill locations shall also be included as well as obliteration of any temporary access routes/tracks that are created during construction.

- Access route to the rock check dams shall be from the bottom of the rock chute to the check dams adjacent

to the existing channel and shall minimize disturbance into and out of the downstream areas.

- Temporary access routes shall be obliterated at the end of construction.

Obliteration of tracks/access routes shall include scarification of the tracks to a 4 inch depth and smoothing as necessary to restore pre—existing grades, to disguise (as best as possible) the disturbance and to prepare the around for reseeding.

Minor grading of the existing ranch road to the limits indicated herein will be necessary and per the typical cross section provided, Sheet 6. This road grading will be paid per cubic yard of fill placement to achieve the cross section indicated. Excess spoil is expected to be available from the excavation related work on the rest of the project.

Contractor shall utilize the corridor of the chute construction for access up and down the slope. No disturbance
outside of the limits of the chute construction, rock sills (and related temporary access) and road regrading will
be allowed.

Rock staging in the flat area on the upstream side of the road will be on a bed of sand or wood chips supplied
by the land owner. As the contractor removes the rocks for placement in the chute, care shall be taken not to
disturb the soils beneath the wood chip layer due to archeological concerns.

ESTIMATED MATERIALS SUMMARY

CHUTE ROCK (24" THICK):	158 cy
CHECK DAM ROCK (36"-48"):	21 ea
CHECK DAM FOOTER ROCKS (18"-24"):	27 ea
NON-WOVEN GEOTEXTILE FABRIC:	313 sy
SAND BEDDING ^a :	12 cy
WOOD CHIPS b:	15 cy
	_

^aSand per quantity/material notes above. Bedding need only cover bottom and not the sloped sides.

^b Wood chips will be supplied by the Vermejo Ranch and shall be spread to a 4 inch depth in the rock staging area prior to recieving rock.

TARGET ROCK GRADATION

Size	Dia.	(in.)
D100	18-	-24
D85	16-	-22
D50	12-	-18
D10	4-1	5

Some variability of the rock gradation may be expected depending upon what is available and delivered from Vermejo Ranch. Contractor shall ensure that rock placement is in such a manner that voids between the individual rocks are minimized and generally less than 3 inches across in any direction.

PLAN LEGEND:



Riprap / Rock Lined Chute



 ∞

Existing Road

Rock Check Dam




----- Limit of Disturbance

Flow Line

— Major Contour— Existing
— — — — — Minor Contour— Existing
— — C — — C — Cut Boundry

- - c - - - c - · Cut Boundry

Detail Locator





— Detail Identifier Detail on Same Sheet

Sheet Reference

EARTHWORK SUMMARY

CHUTE

CUT: 140 cy FILL: 120 cy

ROCK CHECK DAMS

CUT: 16 cy FILL: 0 cy

ROAD GRADING

CUT: 0 cy FILL: 25 cy

- * "Waste" material will be used to spread as topsoil on finished rock chute to fill voids and provide a medium for grass seed to germinate. Any available topsoil should be set aside and reserved for this purpose. Any remaining waste may be spread adjacent to the chute and smoothed at a 2:1 to 5:1 slope up from edge of rock. See details, Sht 5.
- * Earthwork calculations do not include shrinkage due to compaction or swell factor if rock were encountered during excavation.

Design, Inc Designed/Checked By: M. Kearly REV DATE BY REVISION 2900 N. West St. Sulte #5 Flagstaff, Arizona 86004

(928) 774-2336

Project Overview, Sheet Index, & Quantities

Tin Pan Canyon Headcut Stablization Project



UNAUTHORIZED CHANGES & USES THE ENGINEER

PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO OR USES OF THESE PLANS. ALL CHANGES MUST BE IN WRITING AND MUST BE APPROVED BY THE PREPARER OF THESE PLANS.

DIAL 811 BEFORE YOU DIG

FILE NAME:

Tin Pan


PROJECT NO:


18-306NM


DATE: 01-28-2019

SHEET:

3 A of 7











850	Road	Crossing Poi	nt Table		
,	851 Pt#	Northing	Easting	Elev	Descriptor
830 836 837	830	2162698.4	481507.9	7195.5	Edge Riprap
836 837	831 831	2162696.5	481534.7	7195.5	Edge Riprap
	832	2162684.6	481531.6	7195.5	Edge Riprap
	833	2162684.9	481509.9	7195.5	Edge Riprap
838 830	834	2162675.9	481527.3	7194.6	Begin 2:1 Side Slope
838 839	835	2162676.9	481511.4	7194.6	Begin 2:1 Side Slope
077	836	2162697.8	481516.7	7194.5	Bottom of Slope
833	837	2162697.2	481524.7	7194.5	Bottom of Slope
\	838	2162687.6	481516.1	7194.5	Bottom of Slope
	839	2162687.1	481524.0	7194.5	Bottom of Slope
835	840	2162676.7	481515.4	7193.6	Bottom of Slope
841 834	841	2162676.2	481523.3	7193.6	Bottom of Slope
	850	2162703.3	481508.9	7196.7	Top Rip Rap—Tie to Ex Grade
	851	2162701.4	481535.5	7196.7	Top Rip Rap—Tie to Ex Grade





(NOT TO SCALE)

Roa	Road Grading Point Table					
Pt#	Northing	Easting	Elevation	Descriptor		
266	2162648.0	481600.3	7198.9	flow line		
272	2162674.4	481578.4	7196.5	flow line		
273	2162690.0	481561.8	7195.8			
279	2162700.3	481536.1	7195.0	flow line		
280	2162654.3	481479.8	7195.7	flow line		
286	2162663.6	481484.6	7195.6	flow line		
287	2162692.7	481501.7	7195.2	flow line		
293	2162698.0	481507.8	7195.0	flow line		
	1					

SURVEY INFORMATION

DATUM & COORDINATE GRID INFORMATION

Coordinate Projection:	New Mexico State Plane, East 3001 Zone, US Survey Feet
Datum:	North American Datum 1083 (Conus) (Mol)
Geoid Model:	Geoid09 (Conus)

CONTROL POINT LIST

NO.	Northing	Easting	Elevation	Station N	Name	Description
1	2162547.901	481341.891	7206.860	NCD-1		Re-bar with Blue Plastic Cap
2	2162660.624	481551.618	7198.390	NCD-2		Re-bar with Blue Plastic Cap

Design is based on LIDAR data obtained from Vermejo Park Ranch with supplemental on—site topographic survey preformed by NCD on 10/9/2018. The LIDAR data was adjusted to match local survey control set during the 10/9/18 survey. The location of CP1 and CP2 is shown on Sheet 3 in the Project Overview Plan View. If the control points (rebar with caps) have been disturbed, NCD can assist in adjusting the elevation control provided herein to new control that may need to be set during construction.


NOTES

It is understood that NCD will be on—site during portions of construction to observe construction (per a separate contract with NMAML) and consult as necessary to ensure the intent of this design is met.

Natural Channel Design, Inc Design, Inc 2900 N. West St. Sulte #5 Flagstaff, Arizona 86004 (928) 774-2336 Channel DESIGNED BY: M. KEARLY REV DATE BY REVISION

Road Crossing Overview & Layout

Tin Pan Canyon Headcut Stablization Project




UNAUTHORIZED CHANGES & USES THE ENGINEER


PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO OR USES OF THESE PLANS. ALL CHANGES MUST BE IN WRITING AND MUST BE APPROVED BY THE PREPARER OF THESE PLANS.

DIAL 811 BEFORE YOU DIG


FILE NAME: Tin Pan	DATE: 01-28-2019
PROJECT NO: 18-306NM	SHEET: 6A of 7

ROCK CHECK DAMS — PLAN VIEW (NOT TO SCALE)






PLAN VIEW: ROCK CHECK DAM, TYPICAL (NOT TO SCALE)



CROSS SECTION VIEW: ROCK CHECK DAM (NOT TO SCALE)



PROFILE VIEW: ROCK CHECK DAM, TYPICAL (NOT TO SCALE)

ROCK CHECK DAM- LAYOUT

Rock Check Dam Point Table									
Pt #	Northing	Easting	Elevation	Descriptor					
10	2162528.3	481507.8	7169.0	check dam 1					
12	2162508.3	481453.5	7162.9	check dam 2					
14	2162459.2	481405.4	7158.6	check dam 3					
16	2162432.9	481368.9	7152.0	check dam 4					
18	2162415.9	481339.3	7148.0	check dam 5					

GENERAL NOTES

- Two feature rocks will be placed in the middle of the channel, 16"-24" below grade. Two additional feature rocks will be placed on the banks of the channel and will be burried 16"-24" below grade. See section B above.
 Footer rocks will be placed on the downstream side of the feature rocks to prevent scouring. The footer rocks will be 1/2 the diameter of the feature rocks and will be placed under ground. Five footer rocks will be used for each check dam.
 Check Dam 1 (Pt 10) will need three feature rocks in the middle of the channel and seven footer rocks on the downstream side.

- seven footer rocks on the downstream side.

 Some adjustments to the location and configuration of the check dams may be warranted, depending on field conditions at the time of construction and the available rock that is delivered to the site.

Na	itural Channel	DRAWN BY: D. HALLORAN & J. FLEISHMAN			LORAN & J. FLEISHMAN	DETAIL: Rock Check Dams	ale X	AEL D. KANA	UNAUTHORIZED CHANGES & USES PREPARING THESE PLANS WILL NOT		DIAL 811 BEFORE
	Design, Inc	DESIGNED BY: M. KEARLY				DEI/ (IEI NOOK OHOOK DAIH)		23330	PREPARING THESE PLANS WILL NOT FOR, OR LIBBLE FOR, UNAUTHORIZE OR USES OF THESE PLANS. ALL CH. IN WRITING AND MUST BE APPROVED IN OF THESE PLANS.	D CHANGES TO ANGES MUST BE BY THE PREPARER	YOU DIG
		REV	DATE	BY	REVISION	Tin Pan Canyon	PR		FILE NAME: Tin Pan	DATE: 01-28	8-2019
	900 N. West St. Sulte #5 agstaff, Arlzona 86004 (928) 774-2336					Headcut Stablization Project	I SSIONAL ENGINEERS	PROJECT NO: 18-306NM	SHEET:	7A of 7	